
SciPy Reference Guide

Release 1.6.0

Written by the SciPy community

December 31, 2020

CONTENTS

1	Installing and upgrading	3
2	SciPy API	5
2.1	Importing from SciPy	5
2.2	Guidelines for importing functions from SciPy	5
2.3	API definition	6
2.4	SciPy structure	7
3	Release Notes	9
3.1	SciPy 1.6.0 Release Notes	9
3.2	SciPy 1.5.4 Release Notes	32
3.3	SciPy 1.5.3 Release Notes	34
3.4	SciPy 1.5.2 Release Notes	35
3.5	SciPy 1.5.1 Release Notes	37
3.6	SciPy 1.5.0 Release Notes	38
3.7	SciPy 1.4.1 Release Notes	66
3.8	SciPy 1.4.0 Release Notes	67
3.9	SciPy 1.3.3 Release Notes	91
3.10	SciPy 1.3.2 Release Notes	92
3.11	SciPy 1.3.1 Release Notes	93
3.12	SciPy 1.3.0 Release Notes	95
3.13	SciPy 1.2.3 Release Notes	109
3.14	SciPy 1.2.2 Release Notes	111
3.15	SciPy 1.2.1 Release Notes	112
3.16	SciPy 1.2.0 Release Notes	113
3.17	SciPy 1.1.0 Release Notes	130
3.18	SciPy 1.0.1 Release Notes	146
3.19	SciPy 1.0.0 Release Notes	148
3.20	SciPy 0.19.1 Release Notes	169
3.21	SciPy 0.19.0 Release Notes	170
3.22	SciPy 0.18.1 Release Notes	189
3.23	SciPy 0.18.0 Release Notes	190
3.24	SciPy 0.17.1 Release Notes	209
3.25	SciPy 0.17.0 Release Notes	210
3.26	SciPy 0.16.1 Release Notes	226
3.27	SciPy 0.16.0 Release Notes	227
3.28	SciPy 0.15.1 Release Notes	243
3.29	SciPy 0.15.0 Release Notes	243
3.30	SciPy 0.14.1 Release Notes	259
3.31	SciPy 0.14.0 Release Notes	259

3.32	SciPy 0.13.2 Release Notes	271
3.33	SciPy 0.13.1 Release Notes	271
3.34	SciPy 0.13.0 Release Notes	272
3.35	SciPy 0.12.1 Release Notes	279
3.36	SciPy 0.12.0 Release Notes	279
3.37	SciPy 0.11.0 Release Notes	285
3.38	SciPy 0.10.1 Release Notes	291
3.39	SciPy 0.10.0 Release Notes	292
3.40	SciPy 0.9.0 Release Notes	296
3.41	SciPy 0.8.0 Release Notes	300
3.42	SciPy 0.7.2 Release Notes	305
3.43	SciPy 0.7.1 Release Notes	306
3.44	SciPy 0.7.0 Release Notes	308
4	Tutorial	315
4.1	SciPy Tutorial	315
4.1.1	Introduction	315
4.1.2	Special functions (<code>scipy.special</code>)	318
4.1.3	Integration (<code>scipy.integrate</code>)	322
4.1.4	Optimization (<code>scipy.optimize</code>)	333
4.1.5	Interpolation (<code>scipy.interpolate</code>)	362
4.1.6	Fourier Transforms (<code>scipy.fft</code>)	376
4.1.7	Signal Processing (<code>scipy.signal</code>)	387
4.1.8	Linear Algebra (<code>scipy.linalg</code>)	408
4.1.9	Sparse eigenvalue problems with ARPACK	421
4.1.10	Compressed Sparse Graph Routines (<code>scipy.sparse.csgraph</code>)	426
4.1.11	Spatial data structures and algorithms (<code>scipy.spatial</code>)	430
4.1.12	Statistics (<code>scipy.stats</code>)	437
4.1.13	Multidimensional image processing (<code>scipy.ndimage</code>)	526
4.1.14	File IO (<code>scipy.io</code>)	553
5	Developer Documentation	561
5.1	SciPy Code of Conduct	561
5.2	Ways to Contribute	563
5.3	SciPy contributor guide	567
5.4	SciPy Roadmap	568
5.5	Detailed SciPy Roadmap	570
5.6	Toolchain Roadmap	577
5.7	SciPy Core Developer Guide	581
5.8	Deciding on new features	582
5.9	SciPy API Development Guide	592
5.10	SciPy Project Governance	595
5.11	Development environment quickstart guide (macOS)	600
5.12	Development environment quickstart guide (Ubuntu)	602
5.13	Development workflow	604
5.14	PEP8 and SciPy	608
5.15	Rendering Documentation with Sphinx	609
5.16	Running SciPy Tests Locally	610
5.17	Benchmarking SciPy with airtspeed velocity	611
5.18	Adding Cython to SciPy	613
5.19	Public Cython APIs	615
5.20	Adding New Methods, Functions, and Classes	617
6	API Reference	621

6.1	Clustering package (<code>scipy.cluster</code>)	621
6.2	K-means clustering and vector quantization (<code>scipy.cluster.vq</code>)	621
6.3	Hierarchical clustering (<code>scipy.cluster.hierarchy</code>)	628
6.4	Constants (<code>scipy.constants</code>)	680
6.5	Discrete Fourier transforms (<code>scipy.fft</code>)	696
6.6	Legacy discrete Fourier transforms (<code>scipy.fftpack</code>)	740
6.7	Integration and ODEs (<code>scipy.integrate</code>)	766
6.8	Interpolation (<code>scipy.interpolate</code>)	827
6.9	Input and output (<code>scipy.io</code>)	949
6.10	Linear algebra (<code>scipy.linalg</code>)	974
6.11	Low-level BLAS functions (<code>scipy.linalg.blas</code>)	1091
6.12	Low-level LAPACK functions (<code>scipy.linalg.lapack</code>)	1157
6.13	BLAS Functions for Cython	1412
6.14	LAPACK functions for Cython	1417
6.15	Interpolative matrix decomposition (<code>scipy.linalg.interpolative</code>)	1458
6.16	Miscellaneous routines (<code>scipy.misc</code>)	1468
6.17	Multidimensional image processing (<code>scipy.ndimage</code>)	1475
6.18	Orthogonal distance regression (<code>scipy.odr</code>)	1577
6.19	Optimization and root finding (<code>scipy.optimize</code>)	1590
6.20	Nonlinear solvers	1750
6.21	Cython optimize zeros API	1751
6.22	Signal processing (<code>scipy.signal</code>)	1754
6.23	Sparse matrices (<code>scipy.sparse</code>)	2010
6.24	Sparse linear algebra (<code>scipy.sparse.linalg</code>)	2157
6.25	Compressed sparse graph routines (<code>scipy.sparse.csgraph</code>)	2202
6.26	Spatial algorithms and data structures (<code>scipy.spatial</code>)	2236
6.27	Distance computations (<code>scipy.spatial.distance</code>)	2288
6.28	Special functions (<code>scipy.special</code>)	2314
6.29	Statistical functions (<code>scipy.stats</code>)	2542
6.30	Low-level callback functions	3085
	Bibliography	3087
	Index	3123

Release

1.6.0

Date

December 31, 2020

SciPy (pronounced “Sigh Pie”) is open-source software for mathematics, science, and engineering.

INSTALLING AND UPGRADING

Information on how to install SciPy and/or the SciPy Stack (a larger set of packages for scientific computing with Python) can be found at <https://scipy.org/install.html>.

It is recommended that users use a scientific Python distribution or binaries for their platform. If building from source is required, documentation about that can be found at [building/index](#).

If you already have SciPy installed and want to upgrade to a newer version, use the same install mechanism as you have used to install SciPy before. Before upgrading to a newer version, it is recommended to check that your own code does not use any deprecated SciPy functionality. To do so, run your code with `python -Wd`.

2.1 Importing from SciPy

In Python the distinction between what is the public API of a library and what are private implementation details is not always clear. Unlike in other languages like Java, it is possible in Python to access “private” function or objects. Occasionally this may be convenient, but be aware that if you do so your code may break without warning in future releases. Some widely understood rules for what is and isn’t public in Python are:

- Methods / functions / classes and module attributes whose names begin with a leading underscore are private.
- If a class name begins with a leading underscore, none of its members are public, whether or not they begin with a leading underscore.
- If a module name in a package begins with a leading underscore none of its members are public, whether or not they begin with a leading underscore.
- If a module or package defines `__all__`, that authoritatively defines the public interface.
- If a module or package doesn’t define `__all__`, then all names that don’t start with a leading underscore are public.

Note: Reading the above guidelines one could draw the conclusion that every private module or object starts with an underscore. This is not the case; the presence of underscores do mark something as private, but the absence of underscores do not mark something as public.

In SciPy there are modules whose names don’t start with an underscore, but that should be considered private. To clarify which modules these are, we define below what the public API is for SciPy, and give some recommendations for how to import modules/functions/objects from SciPy.

2.2 Guidelines for importing functions from SciPy

The `scipy` namespace itself only contains functions imported from `numpy`. These functions still exist for backwards compatibility, but should be imported from `numpy` directly.

Everything in the namespaces of `scipy` submodules is public. In general, it is recommended to import functions from submodule namespaces. For example, the function `curve_fit` (defined in `scipy/optimize/minpack.py`) should be imported like this:

```
from scipy import optimize
result = optimize.curve_fit(...)
```

This form of importing submodules is preferred for all submodules except `scipy.io` (because `io` is also the name of a module in the Python stdlib):

```
from scipy import interpolate
from scipy import integrate
import scipy.io as spio
```

In some cases, the public API is one level deeper. For example, the `scipy.sparse.linalg` module is public, and the functions it contains are not available in the `scipy.sparse` namespace. Sometimes it may result in more easily understandable code if functions are imported from one level deeper. For example, in the following it is immediately clear that `lomax` is a distribution if the second form is chosen:

```
# first form
from scipy import stats
stats.lomax(...)

# second form
from scipy.stats import distributions
distributions.lomax(...)
```

In that case, the second form can be chosen **if** it is documented in the next section that the submodule in question is public.

2.3 API definition

Every submodule listed below is public. That means that these submodules are unlikely to be renamed or changed in an incompatible way, and if that is necessary, a deprecation warning will be raised for one SciPy release before the change is made.

- `scipy.cluster`
 - `scipy.cluster.vq`
 - `scipy.cluster.hierarchy`
- `scipy.constants`
- `scipy.fft`
- `scipy.fftpack`
- `scipy.integrate`
- `scipy.interpolate`
- `scipy.io`
 - `scipy.io.arff`
 - `scipy.io.harwell_boeing`
 - `scipy.io.idl`
 - `scipy.io.matlab`
 - `scipy.io.netcdf`
 - `scipy.io.wavfile`
- `scipy.linalg`
 - `scipy.linalg.blas`

- `scipy.linalg.cython_blas`
- `scipy.linalg.lapack`
- `scipy.linalg.cython_lapack`
- `scipy.linalg.interpolative`
- `scipy.misc`
- `scipy.ndimage`
- `scipy.odr`
- `scipy.optimize`
- `scipy.signal`
 - `scipy.signal.windows`
- `scipy.sparse`
 - `scipy.sparse.linalg`
 - `scipy.sparse.csgraph`
- `scipy.spatial`
 - `scipy.spatial.distance`
 - `scipy.spatial.transform`
- `scipy.special`
- `scipy.stats`
 - `scipy.stats.distributions`
 - `scipy.stats.mstats`

2.4 SciPy structure

All SciPy modules should follow the following conventions. In the following, a *SciPy module* is defined as a Python package, say `yyy`, that is located in the `scipy/` directory.

- Ideally, each SciPy module should be as self-contained as possible. That is, it should have minimal dependencies on other packages or modules. Even dependencies on other SciPy modules should be kept to a minimum. A dependency on NumPy is of course assumed.
- Directory `yyy/` contains:
 - A file `setup.py` that defines `configuration(parent_package='', top_path=None)` function for `numpy.distutils`.
 - A directory `tests/` that contains files `test_<name>.py` corresponding to modules `yyy/<name>{.py, .so, /}`.
- Private modules should be prefixed with an underscore `_`, for instance `yyy/_somemodule.py`.
- User-visible functions should have good documentation following the [NumPy documentation style](#).
- The `__init__.py` of the module should contain the main reference documentation in its docstring. This is connected to the Sphinx documentation under `doc/` via Sphinx's `automodule` directive.

The reference documentation should first give a categorized list of the contents of the module using `autosummary::` directives, and after that explain points essential for understanding the use of the module.

Tutorial-style documentation with extensive examples should be separate and put under `doc/source/tutorial/`.

See the existing SciPy submodules for guidance.

For further details on NumPy distutils, see [NumPy Distutils - User's Guide](#).

RELEASE NOTES

3.1 SciPy 1.6.0 Release Notes

Contents

- *SciPy 1.6.0 Release Notes*
 - *Highlights of this release*
 - * *New features*
 - `scipy.special` improvements
 - `scipy.odr` improvements
 - `scipy.integrate` improvements
 - `scipy.cluster` improvements
 - `scipy.interpolate` improvements
 - `scipy.io` improvements
 - `scipy.linalg` improvements
 - `scipy.ndimage` improvements
 - `scipy.optimize` improvements
 - `scipy.signal` improvements
 - `scipy.sparse` improvements
 - `scipy.sparse.linalg` improvements
 - `scipy.fft` improvements
 - `scipy.spatial` improvements
 - `scipy.stats` improvements
 - * *Deprecated features*
 - `scipy.spatial` changes
 - * *Backwards incompatible changes*
 - `scipy` changes
 - `scipy.interpolate` changes

- `scipy.linalg` changes
- `scipy.signal` changes
- `scipy.spatial` changes
- `scipy.stats` changes
 - * *Other changes*
 - * *Authors*
- *Issues closed for 1.6.0*
- *Pull requests for 1.6.0*

SciPy 1.6.0 is the culmination of 6 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Before upgrading, we recommend that users check that their own code does not use deprecated SciPy functionality (to do so, run your code with `python -Wd` and check for `DeprecationWarning`s). Our development attention will now shift to bug-fix releases on the 1.6.x branch, and on adding new features on the master branch.

This release requires Python 3.7+ and NumPy 1.16.5 or greater.

For running on PyPy, PyPy3 6.0+ is required.

3.1.1 Highlights of this release

- `scipy.ndimage` improvements: Fixes and enhancements to boundary extension modes for interpolation functions. Support for complex-valued inputs in many filtering and interpolation functions. New `grid_mode` option for `scipy.ndimage.zoom` to enable results consistent with scikit-image's `rescale`.
- `scipy.optimize.linprog` has fast, new methods for large, sparse problems from the HiGHS library.
- `scipy.stats` improvements including new distributions, a new test, and enhancements to existing distributions and tests

New features

3.1.2 `scipy.special` improvements

`scipy.special` now has improved support for 64-bit LAPACK backend

3.1.3 `scipy.odr` improvements

`scipy.odr` now has support for 64-bit integer BLAS

`scipy.odr.ODR` has gained an optional `overwrite` argument so that existing files may be overwritten.

3.1.4 `scipy.integrate` improvements

Some renames of functions with poor names were done, with the old names retained without being in the reference guide for backwards compatibility reasons: - `integrate.simps` was renamed to `integrate.simpson` - `integrate.trapz` was renamed to `integrate.trapezoid` - `integrate.cumtrapz` was renamed to `integrate.cumulative_trapezoid`

3.1.5 `scipy.cluster` improvements

`scipy.cluster.hierarchy.DisjointSet` has been added for incremental connectivity queries.

`scipy.cluster.hierarchy.dendrogram` return value now also includes leaf color information in `leaves_color_list`.

3.1.6 `scipy.interpolate` improvements

`scipy.interpolate.interp1d` has a new method `nearest-up`, similar to the existing method `nearest` but rounds half-integers up instead of down.

3.1.7 `scipy.io` improvements

Support has been added for reading arbitrary bit depth integer PCM WAV files from 1- to 32-bit, including the commonly-requested 24-bit depth.

3.1.8 `scipy.linalg` improvements

The new function `scipy.linalg.matmul_toeplitz` uses the FFT to compute the product of a Toeplitz matrix with another matrix.

`scipy.linalg.sqrtrm` and `scipy.linalg.logm` have performance improvements thanks to additional Cython code.

Python LAPACK wrappers have been added for `pptrf`, `pptrs`, `ppsv`, `pptri`, and `ppcon`.

`scipy.linalg.norm` and the `svd` family of functions will now use 64-bit integer backends when available.

3.1.9 `scipy.ndimage` improvements

`scipy.ndimage.convolve`, `scipy.ndimage.correlate` and their 1d counterparts now accept both complex-valued images and/or complex-valued filter kernels. All convolution-based filters also now accept complex-valued inputs (e.g. `gaussian_filter`, `uniform_filter`, etc.).

Multiple fixes and enhancements to boundary handling were introduced to `scipy.ndimage` interpolation functions (i.e. `affine_transform`, `geometric_transform`, `map_coordinates`, `rotate`, `shift`, `zoom`).

A new boundary mode, `grid-wrap` was added which wraps images periodically, using a period equal to the shape of the input image grid. This is in contrast to the existing `wrap` mode which uses a period that is one sample smaller than the original signal extent along each dimension.

A long-standing bug in the `reflect` boundary condition has been fixed and the mode `grid-mirror` was introduced as a synonym for `reflect`.

A new boundary mode, `grid-constant` is now available. This is similar to the existing `ndimage constant` mode, but interpolation will still performed at coordinate values outside of the original image extent. This `grid-constant` mode is consistent with OpenCV's `BORDER_CONSTANT` mode and `scikit-image`'s `constant` mode.

Spline pre-filtering (used internally by `ndimage` interpolation functions when `order >= 2`), now supports all boundary modes rather than always defaulting to mirror boundary conditions. The standalone functions `spline_filter` and `spline_filter1d` have analytical boundary conditions that match modes `mirror`, `grid-wrap` and `reflect`.

`scipy.ndimage` interpolation functions now accept complex-valued inputs. In this case, the interpolation is applied independently to the real and imaginary components.

The `ndimage` tutorials (<https://docs.scipy.org/doc/scipy/reference/tutorial/ndimage.html>) have been updated with new figures to better clarify the exact behavior of all of the interpolation boundary modes.

`scipy.ndimage.zoom` now has a `grid_mode` option that changes the coordinate of the center of the first pixel along an axis from 0 to 0.5. This allows resizing in a manner that is consistent with the behavior of `scikit-image`'s `resize` and `rescale` functions (and OpenCV's `cv2.resize`).

3.1.10 `scipy.optimize` improvements

`scipy.optimize.linprog` has fast, new methods for large, sparse problems from the HiGHS C++ library. `method='highs-ds'` uses a high performance dual revised simplex implementation (HSOL), `method='highs-ipm'` uses an interior-point method with crossover, and `method='highs'` chooses between the two automatically. These methods are typically much faster and often exceed the accuracy of other `linprog` methods, so we recommend explicitly specifying one of these three method values when using `linprog`.

`scipy.optimize.quadratic_assignment` has been added for approximate solution of the quadratic assignment problem.

`scipy.optimize.linear_sum_assignment` now has a substantially reduced overhead for small cost matrix sizes

`scipy.optimize.least_squares` has improved performance when the user provides the jacobian as a sparse jacobian already in `csr_matrix` format

`scipy.optimize.linprog` now has an `rr_method` argument for specification of the method used for redundancy handling, and a new method for this purpose is available based on the interpolative decomposition approach.

3.1.11 `scipy.signal` improvements

`scipy.signal.gammatone` has been added to design FIR or IIR filters that model the human auditory system.

`scipy.signal.iircomb` has been added to design IIR peaking/notching comb filters that can boost/attenuate a frequency from a signal.

`scipy.signal.sosfilt` performance has been improved to avoid some previously- observed slowdowns

`scipy.signal.windows.taylor` has been added—the Taylor window function is commonly used in radar digital signal processing

`scipy.signal.gauss_spline` now supports `list` type input for consistency with other related SciPy functions

`scipy.signal.correlation_lags` has been added to allow calculation of the lag/ displacement indices array for 1D cross-correlation.

3.1.12 `scipy.sparse` improvements

A solver for the minimum weight full matching problem for bipartite graphs, also known as the linear assignment problem, has been added in `scipy.sparse.csgraph.min_weight_full_bipartite_matching`. In particular, this provides functionality analogous to that of `scipy.optimize.linear_sum_assignment`, but with improved performance for sparse inputs, and the ability to handle inputs whose dense representations would not fit in memory.

The time complexity of `scipy.sparse.block_diag` has been improved dramatically from quadratic to linear.

3.1.13 `scipy.sparse.linalg` improvements

The vendored version of SuperLU has been updated

3.1.14 `scipy.fft` improvements

The vendored `pocketfft` library now supports compiling with ARM neon vector extensions and has improved thread pool behavior.

3.1.15 `scipy.spatial` improvements

The python implementation of `KDTree` has been dropped and `KDTree` is now implemented in terms of `cKDTree`. You can now expect `cKDTree`-like performance by default. This also means `sys.setrecursionlimit` no longer needs to be increased for querying large trees.

`transform.Rotation` has been updated with support for Modified Rodrigues Parameters alongside the existing rotation representations (PR gh-12667).

`scipy.spatial.transform.Rotation` has been partially cythonized, with some performance improvements observed

`scipy.spatial.distance.cdist` has improved performance with the `minkowski` metric, especially for `p`-norm values of 1 or 2.

3.1.16 `scipy.stats` improvements

New distributions have been added to `scipy.stats`:

- The asymmetric Laplace continuous distribution has been added as `scipy.stats.laplace_asymmetric`.
- The negative hypergeometric distribution has been added as `scipy.stats.nhypergeom`.
- The multivariate t distribution has been added as `scipy.stats.multivariate_t`.
- The multivariate hypergeometric distribution has been added as `scipy.stats.multivariate_hypergeom`.

The `fit` method has been overridden for several distributions (`laplace`, `pareto`, `rayleigh`, `invgauss`, `logistic`, `gumbel_l`, `gumbel_r`); they now use analytical, distribution-specific maximum likelihood estimation results for greater speed and accuracy than the generic (numerical optimization) implementation.

The one-sample Cramér-von Mises test has been added as `scipy.stats.cramervonmises`.

An option to compute one-sided p-values was added to `scipy.stats.ttest_1samp`, `scipy.stats.ttest_ind_from_stats`, `scipy.stats.ttest_ind` and `scipy.stats.ttest_rel`.

The function `scipy.stats.kendalltau` now has an option to compute Kendall's tau-c (also known as Stuart's tau-c), and support has been added for exact p-value calculations for sample sizes > 171 .

`stats.trapz` was renamed to `stats.trapezoid`, with the former name retained as an alias for backwards compatibility reasons.

The function `scipy.stats.linregress` now includes the standard error of the intercept in its return value.

The `_logpdf`, `_sf`, and `_isf` methods have been added to `scipy.stats.nakagami`; `_sf` and `_isf` methods also added to `scipy.stats.gumbel_r`

The `sf` method has been added to `scipy.stats.levy` and `scipy.stats.levy_l` for improved precision.

`scipy.stats.binned_statistic_dd` performance improvements for the following computed statistics: `max`, `min`, `median`, and `std`.

We gratefully acknowledge the Chan-Zuckerberg Initiative Essential Open Source Software for Science program for supporting many of these improvements to `scipy.stats`.

Deprecated features

3.1.17 `scipy.spatial` changes

Calling `KDTree.query` with `k=None` to find all neighbours is deprecated. Use `KDTree.query_ball_point` instead.

`distance.wminkowski` was deprecated; use `distance.minkowski` and supply weights with the `w` keyword instead.

Backwards incompatible changes

3.1.18 `scipy` changes

Using `scipy.fft` as a function aliasing `numpy.fft.fft` was removed after being deprecated in SciPy 1.4.0. As a result, the `scipy.fft` submodule must be explicitly imported now, in line with other SciPy subpackages.

3.1.19 `scipy.interpolate` changes

3.1.20 `scipy.linalg` changes

3.1.21 `scipy.signal` changes

The output of `decimate`, `lfilter_zi`, `lfiltic`, `sos2tf`, and `sosfilt_zi` have been changed to match `numpy.result_type` of their inputs.

The window function `slepian` was removed. It had been deprecated since SciPy 1.1.

3.1.22 `scipy.spatial` changes

`cKDTree.query` now returns 64-bit rather than 32-bit integers on Windows, making behaviour consistent between platforms (PR gh-12673).

3.1.23 `scipy.stats` changes

The `frechet_l` and `frechet_r` distributions were removed. They were deprecated since SciPy 1.0.

Other changes

`setup_requires` was removed from `setup.py`. This means that users invoking `python setup.py install` without having `numpy` already installed will now get an error, rather than having `numpy` installed for them via `easy_install`. This install method was always fragile and problematic, users are encouraged to use `pip` when installing from source.

- Fixed a bug in `scipy.optimize.dual_annealing` `accept_reject` calculation that caused uphill jumps to be accepted less frequently.
- The time required for (un)pickling of `scipy.stats.rv_continuous`, `scipy.stats.rv_discrete`, and `scipy.stats.rv_frozen` has been significantly reduced (gh12550). Inheriting subclasses should note that `__setstate__` no longer calls `__init__` upon unpickling.

Authors

- @endolith
- @vkk800
- aditya +
- George Bateman +
- Christoph Baumgarten
- Peter Bell
- Tobias Biester +
- Keaton J. Burns +
- Evgeni Burovski
- Rüdiger Busche +
- Matthias Bussonnier
- Dominic C +
- Corallus Caninus +
- CJ Carey
- Thomas A Caswell
- chapochn +
- Lucía Cheung
- Zach Colbert +

- Coloquinte +
- Yannick Copin +
- Devin Crowley +
- Terry Davis +
- Michaël Defferrard +
- devonwp +
- Didier +
- divenex +
- Thomas Duvernay +
- Eoghan O'Connell +
- Gökçen Eraslan
- Kristian Eschenburg +
- Ralf Gommers
- Thomas Grainger +
- GreatV +
- Gregory Gundersen +
- h-vetinari +
- Matt Haberland
- Mark Harfouche +
- He He +
- Alex Henrie
- Chun-Ming Huang +
- Martin James McHugh III +
- Alex Izvorski +
- Joey +
- ST John +
- Jonas Jonker +
- Julius Bier Kirkegaard
- Marcin Konowalczyk +
- Konrad0
- Sam Van Kooten +
- Sergey Koposov +
- Peter Mahler Larsen
- Eric Larson
- Antony Lee
- Gregory R. Lee

- Loïc Estève
- Jean-Luc Margot +
- MarkusKoebis +
- Nikolay Mayorov
- G. D. McBain
- Andrew McCluskey +
- Nicholas McKibben
- Sturla Molden
- Denali Molitor +
- Eric Moore
- Shashaank N +
- Prashanth Nadukandi +
- nbelakovski +
- Andrew Nelson
- Nick +
- Nikola Forró +
- odidev
- ofirr +
- Sambit Panda
- Dima Pasechnik
- Tirth Patel +
- Matti Picus
- Paweł Redzyński +
- Vladimir Philipenko +
- Philipp Thölke +
- Ilhan Polat
- Eugene Prilepin +
- Vladyslav Rachek
- Ram Rachum +
- Tyler Reddy
- Martin Reinecke +
- Simon Segerblom Rex +
- Lucas Roberts
- Benjamin Rowell +
- Eli Rykoff +
- Atsushi Sakai

- Moritz Schulte +
- Daniel B. Smith
- Steve Smith +
- Jan Soedingrekso +
- Victor Stinner +
- Jose Storopoli +
- Diana Sukhoverkhova +
- Søren Fuglede Jørgensen
- taoky +
- Mike Taves +
- Ian Thomas +
- Will Tirone +
- Frank Torres +
- Seth Troisi
- Ronald van Elburg +
- Hugo van Kemenade
- Paul van Mulbregt
- Saul Ivan Rivas Vega +
- Pauli Virtanen
- Jan Vleeshouwers
- Samuel Wallan
- Warren Weckesser
- Ben West +
- Eric Wieser
- WillTirone +
- Levi John Wolf +
- Zhiqing Xiao
- Rory Yorke +
- Yun Wang (Maigo) +
- Egor Zemlyanoy +
- ZhihuiChen0903 +
- Jacob Zhong +

A total of 122 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

3.1.24 Issues closed for 1.6.0

- #1323: ndimage.shift destroys data from edges (Trac #796)
- #1892: using rptfile= with an existing file causes a Fortran runtime...
- #1903: ndimage.rotate misses some values (Trac #1378)
- #1930: scipy.io.wavfile should be able to read 24 bit signed wave (Trac...)
- #3158: Odd casting behaviour of signal.filtfilt
- #3203: interpolation.zoom incorrect output for certain cases
- #3645: BUG: stats: mstats.pearsonr calculation is wrong if the masks...
- #3665: Return Bunch objects from stats functions
- #4922: unexpected zero output values from zoom
- #5202: BUG: stats: Spurious warnings from the pdf method of several...
- #5223: Zoom does not return the same values when resizing a sub-array...
- #5396: scipy.spatial.distance.pdist documentation bug
- #5489: ValueError: failed to create intent(cachehide)optional array-...
- #6096: loadmat drops dtype of empty arrays when squeeze_me=True
- #6713: scipy.ndimage.zoom returns artefacts and boundaries in some cases
- #7125: Impossible to know number of dimensions in c function used by...
- #7324: scipy.ndimage.zoom bad interpolation when downsampling (zoom...)
- #8131: BUG: geometric_transform wrap mode possible bug
- #8163: LSMR fails on some random values when providing an x0
- #8210: Why should I choose order > 1 for scipy.ndimage.zoom?
- #8465: Unexpected behavior with reflect mode of ndimage.rotate
- #8776: cdist behavior with Minkowsky and np.inf
- #9168: documentation of pearson3 in scipy.stats unclear
- #9223: Faster implementation of scipy.sparse.block_diag
- #9476: Invalid index in signal.medfilt2d's QUICK_SELECT
- #9857: scipy.odr.Output.sd_beta is not standard error
- #9865: Strange behavior of `ndimage.shift` and `ndimage.affine_transform`
- #10042: Consider support for multivariate student-t distribution?
- #10134: gausshyper distribution accepts invalid parameters
- #10179: str+bytes concatenation error in test_lapack.py
- #10216: cKDTree.query_ball_point speed regression
- #10463: ENH: vectorize scipy.fft for more CPU architectures
- #10593: Rename `sum` ndimage function
- #10595: scipy.stats.ttest_1samp should support alternative hypothesis
- #10610: ndimage.interpolation.spline_filter1d default value of mode

- #10620: `ndimage.interpolation.zoom()` option to work like `skimage.transform.resize()`
- #10711: Array Shapes Not Aligned Bug in `scipy.optimize._lsq.lsqr_linear.py`
- #10782: BUG: optimize: methods unknown to ``scipy.optimize.show_options``
- #10892: Possible typo in an equation of `optimize/dual_annealing`
- #11020: `signal.fftconvolve` return a tuple including lag information
- #11093: `scipy.interpolate.interp1d` can not handle `datetime64`
- #11170: Use `manylinux2014` to get `aarch64/ppc64le` support
- #11186: BUG: stats: `pearson3` CDF and SF functions incorrect when skew...
- #11366: `DeprecationWarning` due to invalid escape sequences
- #11403: Optimize raises “`ValueError: `x0` violates bound constraints``”...
- #11558: ENH: IIR comb filter
- #11559: BUG: `iirdesign` doesn't fail for frequencies above Nyquist
- #11567: `scipy.signal.iirdesign` doesn't check consistency of `wp` and `ws`...
- #11654: ENH: Add Negative Hypergeometric Distribution
- #11720: BUG: stats: wrong shape from `median_absolute_deviation` for arrays...
- #11746: BUG: stats: `pearson3` returns size 1 arrays where other distributions...
- #11756: Improve and fix `*Spline` docstrings and code
- #11758: BUG: of `scipy.interpolate.CubicSpline` when ``bc_type`` is set...
- #11925: MAINT: remove character encoding check in CI?
- #11963: Test failures - `TestLinprogIPsparseCholmod`
- #12102: incorrect first moment of non central t-distribution
- #12113: `scipy.stats.poisson` docs for `rate = 0`
- #12152: ENH: `signal.gauss_spline` should accept a list
- #12157: BUG: Iteration index initialisation is wrong in `scipy.optimize.linesearch.scalar_search_wolfe2`
- #12162: Storing Rotation object in NumPy array returns an array with...
- #12176: cannot modify the slice of an array returned by ``wavfile.read``
- #12190: retrieve leave colors from dendrogram
- #12196: PERF: `scipy.linalg.pinv` is very slow compared to `numpy.linalg.pinv`
- #12222: Interpolating categorical data (`interp1d`)
- #12231: Is the p-value of the Kruskal-Wallis test two-sided?
- #12249: ENH: `least_squares`: should not re-instantiate `csr_matrix` if already...
- #12264: DOC: optimize: `linprog` method-specific function signature
- #12290: DOC: Convex Hull areas are actually perimeters for 2-dimensional...
- #12308: `integrate.solve_ivp` with DOP853 method fails when `yDot = 0`
- #12326: BUG: stats: `exponnorm.pdf` returns 0 for small K
- #12337: `scipy.sparse.linalg.eigsh` documentation is misleading

- #12339: `scipy.io.wavfile.write` documentation has wrong example
- #12340: `sparse.lil_matrix.tocsr()` fails silently on matrices with `nzn...`
- #12350: Create a 2-parameter version of the gamma distribution
- #12369: `scipy.signal.correlate` has an error in the documentation, examples...
- #12373: `interp1d` returns incorrect values for step functions
- #12378: `interpolate.NearestNDInterpolator.__call__` & `LinearNDInterpolator.__call__`...
- #12411: `scipy.stats.spearmanr` mishandles nan variables with “propagate”
- #12413: DOC: Remove the “Basic functions” section from the SciPy tutorial.
- #12415: `scipy.stats.dirichlet` documentation issue
- #12419: `least_squares` `ValueError` with ‘lm’ method - regression from 1.4.1...
- #12431: Request for Python wrapper for LAPACK’s `?pptrf` (Cholesky factorization...)
- #12458: `spearmanr` with entire NaN columns produces errors
- #12477: WIP: Addition of MLE for `stats.invgauss/wald`
- #12483: reading `.wav` fails when the file is too big on python 3.6.0
- #12490: BUG: `stats`: logistic and genlogistic `logpdf` overflow for large...
- #12499: `LinearNDInterpolator` raises `ValueError` when value array has `writable=False`...
- #12523: Wrong key in `__odrpack.c`
- #12547: typo in `scipy/cluster/_hierarchy.pyx`
- #12549: DOC: `least_squares` return type is poorly formatted.
- #12578: TST: `test_bounds_infeasible_2` failing on wheels repo cron jobs
- #12585: ENH: Add Multivariate Hypergeometric Distribution
- #12604: unintuitive conversion in ``scipy.constants.lambda2nu``
- #12606: DOC: Invalid syntax in example.
- #12665: List of possible bugs found by automated code analysis
- #12696: `scipy.optimize.fminbound`, `numpy` depreciation warning Creating...
- #12699: `TestProjections.test_iterative_refinements_dense` failure
- #12701: `TestDifferentialEvolutionSolver::test_L4` failing
- #12719: Misleading `scipy.signal.get_window()` docstring with ‘exponential’...
- #12740: `circstd` doesn’t handle `R = hypot(S, C) > 1`
- #12749: ENH: `interp1d` Matlab compatibility
- #12773: Meta-issue: `ndimage` spline boundary handling (NumFOCUS proposal)
- #12813: `optimize.root(method=”krylov”)` fails if `options[“tol_norm”]` expects...
- #12815: `stats.zscore` inconsistent behavior when all values are the same
- #12840: `scipy.signal.windows.dpss` docstring typo
- #12874: `Rotation.random` vs `stats.special_ortho_group`
- #12881: FFT - documentation - examples - `linspace` construction

- #12904: BUG: parsing in loadarff()
- #12917: GitHub Actions nightly build triggered on forks
- #12919: BUG: numerical precision, use gammaln in nct.mean
- #12924: Rename Sample Based Integration Methods to Comply with Code of...
- #12940: Should the minimum numpy for AIX be bumped to 1.16.5
- #12951: A possible typo in scipy.stats.weightedtau
- #12952: [Documentation question] Would it be more precise to specify...
- #12970: Documentation presents second order sections as the correct choice...
- #12982: Calculate standard error of the intercept in linregress
- #12985: Possible wrong link in scipy.stats.wilcoxon doc
- #12991: least_squares broken with float32
- #13001: `OptimizeResult.message` from `L-BFGS-B` is a bytes, not...
- #13030: BUG: lint_diff.py still fails for backport PRs
- #13077: CI: codecov proper patch diffs
- #13085: Build failing on main branch after HiGHS solver merge
- #13088: BLD, BUG: wheel builds failure with HiGHS/optimize
- #13099: Wrong output format for empty sparse results of kron
- #13108: TST, CI: GitHub Actions MacOS Failures
- #13111: BUG, DOC: refguide check is failing
- #13127: ODR output file writing broken in conda env with system compilers
- #13134: FromTravis migration tracker
- #13140: BUG: signal: `ss2tf` incorrectly truncates output to integers.
- #13179: CI: lint is failing because of output to stderr
- #13182: Key appears twice in `test_optimize.test_show_options`
- #13191: `scipy.linalg.lapack.dgesjv` overwrites original arrays if...
- #13207: TST: Erratic test failure in test_cossin_separate
- #13221: BUG: pavement.py glitch
- #13239: Segmentation fault with `eigh(..., driver="evx")` for 10x10...
- #13248: ndimage: improper cval handling for complex-valued inputs

3.1.25 Pull requests for 1.6.0

- #8032: ENH: Add in taylor window common in Radar processing
- #8779: CI: Run benchmarks
- #9361: ENH: Add Kendall's tau-a and tau-c variants to `scipy.stats.kendalltau()`
- #11068: ENH: Adds `correlation_lags` function to `scipy.signal`
- #11119: ENH: add Cramer-von-Mises (one-sample) test to `scipy.stats`
- #11249: ENH: optimize: interpolative decomposition redundancy removal...
- #11346: ENH: add fast toeplitz matrix multiplication using FFT
- #11413: ENH: Multivariate t-distribution (stale)
- #11563: ENH: exact p-value in `stats.kendalltau()` for sample sizes > 171
- #11691: ENH: add a stack of reversal functions to `linprog`
- #12043: ENH: optimize: add HiGHS methods to `linprog` - continued
- #12061: Check parameter consistency in `signal.iirdesign`
- #12067: MAINT: Cleanup OLDAPI in `ndimage/src/_ctest.c`
- #12069: DOC: Add developer guidelines for implementing the `nan_policy`...
- #12077: MAINT: malloc return value checks for cython
- #12080: MAINT: Remove `suppress_warnings`
- #12085: ENH: special: support ILP64 Lapack
- #12086: MAINT: Cleanup `PyMODINIT_FUNC` used during 2to3
- #12097: ENH: stats: override `stats.rayleigh.fit` with analytical MLE
- #12112: DOC: Improve `integrate.nquad` docstring
- #12125: TST: Add a test for `stats.gmean` with negative input
- #12139: TST: Reduce flakiness in `lsmr` test
- #12142: DOC: add a note in poisson distribution when $\mu=0$ and $k=0$ in...
- #12144: DOC: Update `ndimage.morphology.distance_transform*`
- #12154: ENH: `scipy.signal`: allow lists in `gauss_spline`
- #12170: ENH: `scipy.stats`: add negative hypergeometric distribution
- #12177: MAINT: Correctly add input line to `ValueError`
- #12183: ENH: Use `fromfile` where possible
- #12186: MAINT: generalize tests in `SphericalVoronoi`
- #12198: TST: Fix str + bytes error
- #12199: ENH: match `np.result_type` behaviour in some `scipy.signal` functions
- #12200: ENH: add FIR and IIR gammatone filters to `scipy.signal`
- #12204: ENH: Add `overwrite` argument for `odr.ODR()` and its test.
- #12206: MAINT: `lstsq`: Switch to tranposed problem if the array is tall
- #12208: wavfile bugfixes and maintenance

- #12214: DOC: fix docstring of “sd_beta” of odr.Output.
- #12234: MAINT: prevent divide by zero warnings in scipy.optimize BFGS...
- #12235: REL: set version to 1.6.0.dev0
- #12237: BUG: Fix exit condition for QUICK_SELECT pivot
- #12242: ENH: Rename ndimage.sum to ndimage.sum_labels (keep sum as alias)
- #12243: EHN: Update SuperLU
- #12244: MAINT: stats: avoid spurious warnings in ncx2.pdf
- #12245: DOC: Fixed incorrect default for mode in scipy.ndimage.spline_filter1d
- #12248: MAINT: clean up pavement.py
- #12250: ENH: Replaced csr_matrix() by tocsr() and complemented docstring
- #12253: TST, CI: turn on codecov patch diffs
- #12259: MAINT: Remove duplicated test for import cycles
- #12263: ENH: Rename LocalSearchWrapper bounds
- #12265: BUG optimize: Accept np.matrix in lsq_linear
- #12266: BUG: Fix paren error in dual annealing accept_reject calculation
- #12269: MAINT: Included mismatched shapes in error messages.
- #12279: MAINT: `__array__` and array protocols cannot be used in sparse.
- #12281: DOC: update wheel DL docs
- #12283: ENH: odr: ILP64 Blas support in ODR
- #12284: ENH: linalg: support for ILP64 BLAS/LAPACK in f2py wrappers
- #12286: ENH: Cythonize scipy.spatial.transform.Rotation
- #12287: ENH: Read arbitrary bit depth (including 24-bit) WAVs
- #12292: BLD: fix musl compilation
- #12293: MAINT: Fix a DeprecationWarning in validate_runttests_log.py.
- #12296: DOC: Clarify area/volume in scipy.spatial.ConvexHull docstrings
- #12302: CI: Run travis builds on master to keep cache up to date
- #12305: TST: Cleanup print statements in tests
- #12323: ENH: Add a Bunch-like class to use as a backwards compatible...
- #12324: BUG: io: Fix an error that occurs when attempting to raise a...
- #12327: DOC: clarify docstrings of `query_ball_tree` and `query_pairs`
- #12334: PERF: Improve cKDTree.query_ball_point constant time cython overhead
- #12338: DOC: improve consistency and clarity of docs in linalg and sparse/linalg
- #12341: DOC: add Examples for KDTree query_ball_tree and query_pairs
- #12343: DOC: add examples for special.eval_legendre()
- #12349: BUG: avoid overflow in sum() for 32-bit systems
- #12351: DOC: Fix example wavfile to be 16bit

- #12352: [BUG] Consider 0/0 division in DOP853 error estimation
- #12353: Fix exception causes in vq.py
- #12354: MAINT: Cleanup unneeded void* cast in setlist.pxd
- #12355: TST: Remove hack for old win-amd64 bug
- #12356: ENH: Faster implementation of scipy.sparse.block_diag (#9411...
- #12357: MAINT,TST: update and run scipy/special/utis/convert.py
- #12358: TST: Check mstat.skewtest pvalue
- #12359: TST: Sparse matrix test with int64 indptr and indices
- #12363: DOC: ref. in CloughTocher2DInterpolator
- #12364: DOC: `sparse_distance_matrix` and `count_neighbors` examples
- #12371: MAINT, CI: bump to latest stable OpenBLAS
- #12372: MAINT: Minor cleanup of (c)KDTree tests
- #12374: DEP: Deprecate `distance.wminkowski`
- #12375: ENH: Add fast path for minkowski distance with p=1,2 and support...
- #12376: Fix exception causes in most of the codebase
- #12377: DOC: Quick fix - adds newline to correlation_lags docstring Examples...
- #12381: BENCH: remove obsolete goal_time param
- #12382: ENH: Replace KDTree with a thin wrapper over cKDTree
- #12385: DOC: improve docstrings of interpolate.NearestNDInterpolator.__call__...
- #12387: DOC/STY: add example to scipy.signal.correlate
- #12393: CI: Replace the existing check for non-ASCII characters with...
- #12394: CI: arm64 numpy now available
- #12395: ENH: improve stats.binned_statistic_dd performance
- #12396: DOC, MAINT: forward port 1.5.0 relnotes
- #12398: API: Disable len() and indexing of Rotation instances with single...
- #12399: MAINT: Replace some Unicode dash-like chars with an ASCII hyphen.
- #12402: update .mailmap
- #12404: MAINT: io: Change the encoding comment of test_mio.py to utf-8.
- #12416: CI: cache mingw, azure pipelines
- #12427: BUG: logic error in loop unrolling (cKDTree)
- #12432: DOC: Remove the “Basic functions” section from the SciPy tutorial.
- #12434: ENH:linalg: Add LAPACK wrappers pptrf/pptrs/ppsv/pptri/ppcon
- #12435: DOC: fix simplex math for scipy.stats.dirichlet documentation
- #12439: DOC: add API methods summary for NdPPoly
- #12443: BUG: stats: Improve calculation of exponnorm.pdf
- #12448: DOC: stats: Add “Examples” to the ansari docstring.

- #12450: ENH: add `leaves_color_list` for `cluster.dendrogram` dictionary.
- #12451: MAINT: remove “blacklist” terminology from code base
- #12452: DOC: clarify the meaning of whitening for `cluster.vq.whiten()`
- #12455: MAINT: clearer error message in `setup.py`
- #12457: ENH: stats: override `stats.pareto.fit` with analytical MLE
- #12460: check if column in `spearman rho` is entirely NaN or Inf
- #12463: DOC: improve and clean up `*Spline` docstrings in `fitpack2.py`
- #12474: ENH: linalg: speedup `_sqrtm_triu` by moving tight loop to Cython
- #12476: ENH: add IIR comb filter to `scipy.signal`
- #12484: Fix documentation for `minimize`
- #12486: DOC: add a note in `poisson` distribution when `mu=0` and `k=0` in...
- #12491: MAINT: forward port 1.5.1 release notes
- #12508: Fix exception causes all over the codebase
- #12514: ENH: stats: override `stats.invgauss.fit` with analytical MLE
- #12519: PERF: Avoid `np.zeros` when custom initialization is needed anyway
- #12520: DOC: Minor RST section renaming.
- #12521: MAINT: Remove unused imports
- #12522: PERF: Get rid of unnecessary allocation in `VarReader5.cread_fieldnames`
- #12524: DOC: special: Set `Axes3D rect` to avoid clipping labels in plot.
- #12525: Fix large sparse `nnz`
- #12526: DOC: Remove double section and too long header underline.
- #12527: Improve error message for wrong interpolation type
- #12530: Move redundant logic outside loop for conditional speedup in...
- #12532: ENH: Add `norm={“forward”, “backward”}` to `scipy.fft``
- #12535: MAINT: Avoid sphinx deprecated aliases for `SeeAlso` and `Only`
- #12540: BUG: fix `odr.output.work_ind` key bug and add its test.
- #12541: ENH: add solver for minimum weight full bipartite matching
- #12550: PERF: pickling speed of `rv*`
- #12551: DOC: fix typo in `cluster/_hierarchy.pyx`
- #12552: CI: Cleanup travis pip installs
- #12556: BUG: Fix problem with `Scipy.integrate.solve_bvp` for big problems
- #12557: MAINT: Use extern templates to improve `sparsetools` compile time
- #12558: MAINT: Remove hack to allow `scipy.fft` to act like a function
- #12563: MAINT: Remove unused `mu0` in `special/orthogonal.py`
- #12564: DOC: fix return type docstring for `least_squares`
- #12565: DOC: stats: respond to query about Kruskal-Wallis test being...

- #12566: BUG: Interpolate: use stable sort
- #12568: Updated documentation for `as_quat`
- #12571: DEP: remove deprecated slepian window
- #12573: DEP: remove ``frechet_l`` and ``frechet_r``
- #12575: BUG: stats: fix multinomial.pmf NaNs when params sum > 1
- #12576: MAINT: remove warning from `LSQSphereBivariateSpline`
- #12582: ENH: Multivariate t-distribution
- #12587: ENH: speed up rvs of `gengamma` in `scipy.stats`
- #12588: DOC: add Examples add see also sections for `LinearNDInterpolator`,...
- #12597: ENH: Add single-sided p-values to t-tests
- #12599: Small update to `scipy FFT` tutorial
- #12600: ENH: disjoint set data structure
- #12602: BUG: add const for Read-only views in `interpnd.pyx`
- #12605: BUG: correct ``np.asanyarray`` use in ``scipy.constants.lambda2nu``
- #12610: MAINT: forward port 1.5.2 release notes
- #12612: MAINT: stats: Use explicit keyword parameters instead of ``**kwds``.
- #12616: DOC: make explicit docstring that `interpolate.interp1d` only accepts...
- #12618: DOC: Minor doc formatting.
- #12640: MAINT: stats: fix issues with `scipy.stats.pearson3` docs, moment,...
- #12647: TST: Add `Boost ellipr[cdfgj]_data` test data
- #12648: DOC: Update `special/utis/README` with instructions
- #12649: DOC: simplified pip quickstart guide
- #12650: DOC: stats: Fix `boxcox` docstring: `lambda` can be negative.
- #12655: DOC: update Steering Council members listed in governance docs
- #12659: `rv_sample` expect bug
- #12663: DOC: optimize: try to fix `linprog` method-specific documentation
- #12664: BUG: stats: Fix `logpdf` with large negative values for `logistic`...
- #12666: MAINT: Fixes from static analysis
- #12667: ENH: Adding Modified Rodrigues Parameters to the `Rotation` class
- #12670: DOC: Update documentation for `Gamma` distribution
- #12673: API: Unconditionally return `np.intp` from `cKDTree.query`
- #12677: MAINT: Add Autogenerated notice to `ufuncs.pyi`
- #12682: MAINT: Remove `_util._valarray`
- #12688: MAINT: add `f2py`-generated `scipy.integrate` files to `.gitignore`
- #12689: BENCH: simplify benchmark setup, remove `benchmarks/run.py`
- #12694: `scipy/stats`: Add `laplace_asymmetric` continuous distribution

- #12695: DOC: update Ubuntu quickstart; conda compilers now work!
- #12698: MAINT: Replace np.max with np.maximum
- #12700: TST: bump test precision for constrained trustregion test
- #12702: TST: bump test tolerance for `DifferentialEvolutionSolver.test_L4`
- #12703: BUG: Improve input validation for sepfir2d
- #12708: MAINT: fix a typo in scipy.sparse
- #12709: BUG: bvlx can fail catastrophically to converge
- #12711: MAINT: Use platform.python_implementation to determine IS_PYPY
- #12713: TST: Fix flaky test_lgmres
- #12716: DOC: add examples and tutorial links for interpolate functions...
- #12717: DOC: Fix Issue #5396
- #12725: ENH: Support complex-valued images and kernels for many ndimage...
- #12729: DEP: remove setup_requires
- #12732: BENCH: skip benchmarks instead of hiding them when SCIPY_XSLOW=0
- #12734: CI: Don't ignore line-length in the lint_diff check.
- #12736: DOC: Fix signal.windows.get_window() 'exponential' docstring
- #12737: ENH: stats: override stats.gumbel_r.fit and stats.gumbel_l.fit...
- #12738: ENH: stats: override stats.logistic.fit with system of equations...
- #12743: BUG: Avoid negative variances in circular statistics
- #12744: Prevent build error on GNU/Hurd
- #12746: TST: parameterize the test cases in test_ndimage.py
- #12752: DOC: Add examples for some root finding functions.
- #12754: MAINT, CI: Azure windows deps multiline
- #12756: ENH: stats: Add an sf method to levy for improved precision in...
- #12757: ENH: stats: Add an sf method to levy_l for improved precision.
- #12765: TST, MAINT: infeasible_2 context
- #12767: Fix spline interpolation boundary handling for modes reflect...
- #12769: DOC: syntax error in scipy.interpolate.bspl
- #12770: ENH: add nearest-up rounding to scipy.interpolate.interpld
- #12771: TST: fix invalid input unit test for scipy.signal.gammatone
- #12775: ENH: Adds quadratic_assignment with two methods
- #12776: ENH: add grid-constant boundary handling in ndimage interpolation...
- #12777: Add Taylor Window function - Common in Radar DSP
- #12779: ENH: Improvements to pocketfft thread pool and ARM neon vectorization
- #12788: API: Rename cKDTree n_jobs argument to workers
- #12792: DOC: remove THANKS.txt file in favor of scipy.org

- #12793: Add new flag to authors tool
- #12802: BENCH: add `scipy.ndimage.interpolation` benchmarks
- #12803: Do not pin the version of `numpy` in unsupported python versions
- #12810: CI: fix 32-bit Linux build failure on Azure CI runs
- #12812: ENH: support interpolation of complex-valued images
- #12814: BUG: `nonlin_solve` shouldn't pass non-vector `dx` to `tol_norm`
- #12818: Update `ckdtree.pyx`
- #12822: MAINT: simplify `directed_hausdorff`
- #12827: DOC: Fix wrong name `w` being used instead of `worN` in docs.
- #12831: DOC: fix typo in `sparse/base.py`
- #12835: MAINT: stats: Improve `vonmises` PDF calculation.
- #12839: ENH: `scipy.stats`: add multivariate hypergeometric distribution
- #12843: changed `M` to `N` in `windows.dpss`
- #12846: MAINT: update minimum NumPy version to 1.16.5
- #12847: DOC: Unify the formula in docs of `scipy.stats.pearsonr()`
- #12849: DOC: polish QAP docs for consistency and readability
- #12852: ENH, MAINT: Bring `KDTree` interface to feature-parity with `cKDTree`
- #12858: DOC: use `:doi:` and `:arxiv:` directives for references
- #12872: lazily import `multiprocessing.Pool` in `MapWrapper`
- #12878: DOC: document `ScalarFunction`
- #12882: MAINT: stats: Change a test to use `<=` instead of strictly less...
- #12885: `numpy.linspace` calls edited to ensure correct spacing.
- #12886: DOC: stats: Add 'versionadded' to `cramervonmises` docstring.
- #12899: TST: make a couple of tests expected to fail on 32-bit architectures
- #12903: DOC: update Windows build guide and move into contributor guide
- #12907: DOC: clarify which array the `precenter` option applies to
- #12908: MAINT: `spatial`: Remove two occurrences of unused variables in...
- #12909: ENH: stats: Add methods `gumbel_r_sf` and `gumbel_r_isf`
- #12910: CI: travis: Remove some unnecessary code from `.travis.yml`.
- #12911: Minor fixes to dendrogram plotting
- #12921: CI: don't run GitHub Actions on fork or in cron job
- #12927: MAINT: rename `integrate.simps` to `simpson`
- #12934: MAINT: rename `trapz` and `cumtrapz` to `(cumulative_)trapezoid`
- #12936: MAINT: fix numerical precision in `nct.stats`
- #12938: MAINT: fix linter on master
- #12941: Update minimum AIX pinnings to match non AIX builds

- #12955: BUG: Fixed wrong NaNs check in `scipy.stats.weightedtau`
- #12958: ENH: stats: Implement `_logpdf`, `_sf` and `_isf` for `nakagami`.
- #12962: Correcting that `p` should be in `[0,1]` for a variety of discrete...
- #12964: BUG: added `line.strip()` to `split_data_line()`
- #12968: ENH: stats: Use only an analytical formula or scalar root-finding...
- #12971: MAINT: Declare support for Python 3.9
- #12972: MAINT: Remove redundant Python < 3.6 code
- #12980: DOC: Update documentation on `optimize.rosen`
- #12983: ENH: improvements to `stats.linregress`
- #12990: DOC: Clarify that using `sos` as output type for `iirdesign` can...
- #12992: DOC: capitalization and formatting in `lsmr`
- #12995: DOC: stats: Several documentation fixes.
- #12996: BUG: Improve error messages for ``range`` arg of `binned_statistic_dd`
- #12998: MAINT: `approx_derivative` with FP32 closes #12991
- #13004: TST: `isinstance(OptimizeResult.message, str)` closes #13001
- #13006: Keep correct dtype when loading empty mat arrays.
- #13009: MAINT: clip SLSQP step within bounds
- #13012: DOC: fix `bilinear_zpk` example labels
- #13013: ENH: Add ``subset`` and ``subsets`` methods to ``DisjointSet``...
- #13029: MAINT: `basinhopping` callback for initial minimisation
- #13032: DOC: fix docstring errors in `stats.wilcoxon`
- #13036: BUG: forward port `lint_diff` shims
- #13041: MAINT: `dogbox` ensure `x` is within bounds closes #11403
- #13042: MAINT: forward port 1.5.4 release notes
- #13046: DOC: Update `optimize.least_squares` doc for all tolerance must...
- #13052: Typo fix for cluster documentation
- #13054: BUG: fix ``scipy.optimize.show_options`` for unknown methods....
- #13056: MAINT: `fft`: Fix a C++ compiler warning.
- #13057: Minor fixes on doc of function `csr_tocsc`
- #13058: DOC: stats: Replace `np.float` with `np.float64` in a tutorial file.
- #13059: DOC: stats: Update the "Returns" section of the `linregress` docstring.
- #13060: MAINT: `clip_x_for_func` should be private
- #13061: DOC: `signal.win` -> `signal.windows.win` in Examples
- #13063: MAINT: Add `suite-sparse` and `sksparse` installation check
- #13070: MAINT: stats: Remove a couple obsolete comments.
- #13073: BUG: Fix `scalar_search_wolfe2` to resolve #12157

- #13078: CI, MAINT: migrate Lint to Azure
- #13081: BLD: drop Python 3.6 support (NEP 29)
- #13082: MAINT: update minimum NumPy version to 1.16.5 in a couple more...
- #13083: DOC: update toolchain.rst
- #13086: DOC: Update the Parameters section of the correlation docstring
- #13087: ENH:signal: Speed-up Cython implementation of `_sosfilt`
- #13089: BLD, BUG: add c99 compiler flag to HiGHS basiclu library
- #13091: BUG: Fix GIL handling in `_sosfilt`
- #13094: DOC: clarify "location" in docstring of `cKDTree.query`
- #13095: Zoom resize update
- #13097: BUG: fix `CubicSpline(..., bc_type="periodic")` #11758
- #13100: BUG: sparse: Correct output format of `kron`
- #13107: ENH: faster `linear_sum_assignment` for small cost matrices
- #13110: CI, MAINT: refguide/asv checks to azure
- #13112: CI: fix MacOS CI
- #13113: CI: Install word list package for refguide-check
- #13115: BUG: add value range check for `signal.iirdesign()`
- #13116: CI: Don't report name errors after an exception in refguide-check
- #13117: CI: move sdist/pre-release test Azure
- #13119: Improve error message on `friedmanchisquare` function
- #13121: Fix `factorial()` for NaN on Python 3.10
- #13123: BLD: Specify file extension for language standard version tests
- #13128: TST: skip Fortran I/O test for ODR
- #13130: TST: skip `factorial()` float tests on Python 3.10
- #13136: CI:Add python dbg run to GH Actions
- #13138: CI: Port coverage, 64-bit BLAS, GCC 4.8 build to azure
- #13139: Fix edge case for `mode='nearest'` in `ndimage.interpolation` functions
- #13141: BUG: signal: Fix data type of the numerator returned by `ss2tf`.
- #13144: MAINT: stats: restrict `gausshyper z > -1`
- #13146: typo in `csr.py`
- #13148: BUG: stats: fix typo in stable rvs per gh-12870
- #13149: DOC: spatial/stats: cross-ref random rotation matrix functions
- #13151: MAINT: stats: Fix a test and a couple PEP-8 issues.
- #13152: MAINT: stats: Use `np.take_along_axis` in the private function...
- #13154: ENH: stats: Implement defined handling of constant inputs in...
- #13156: DOC: maintain equal display range for `ndimage.zoom` example

- #13159: CI: Azure: Don't run tests on merge commits, except for coverage
- #13160: DOC: stats: disambiguate location-shifted/noncentral
- #13161: BUG: DifferentialEvolutionSolver.__del__ can fail in garbage...
- #13163: BUG: stats: fix bug in spearmanr nan propagation
- #13167: MAINT: stats: Fix a test.
- #13169: BUG: stats: Fix handling of misaligned masks in mstats.pearsonr.
- #13178: CI: testing.yml -> macos.yml
- #13181: CI: fix lint
- #13190: BUG: optimize: fix a duplicate key bug for `test_show_options`
- #13192: BUG:linalg: Add overwrite option to gejsv wrapper
- #13194: BUG: slsqp should be able to use rel_step
- #13199: [skip travis] DOC: 1.6.0 release notes
- #13203: fix typos
- #13209: TST:linalg: set the seed for cossin test
- #13212: [DOC] Backtick and directive consistency.
- #13217: REL: add necessary setuptools and numpy version pins in pyproject.toml...
- #13226: BUG: pavement.py file handle fixes
- #13249: Handle cval correctly for ndimage functions with complex-valued...
- #13253: BUG,MAINT: Ensure all Pool objects are closed
- #13255: BUG:linalg: Fix heevx wrappers and add new tests
- #13260: CI: fix macOS testing
- #13269: CI: github actions: In the linux dbg tests, update apt before...
- #13279: MAINT: 1.6.0 rc2 backports

3.2 SciPy 1.5.4 Release Notes

Contents

- *SciPy 1.5.4 Release Notes*
 - *Authors*
 - * *Issues closed for 1.5.4*
 - * *Pull requests for 1.5.4*

SciPy 1.5.4 is a bug-fix release with no new features compared to 1.5.3. Importantly, wheels are now available for Python 3.9 and a more complete fix has been applied for issues building with XCode 12.

3.2.1 Authors

- Peter Bell
- CJ Carey
- Andrew McCluskey +
- Andrew Nelson
- Tyler Reddy
- Eli Rykoff +
- Ian Thomas +

A total of 7 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 1.5.4

- #12763: ndimage.fourier_ellipsoid segmentation fault
- #12789: TestConvolve2d.test_large_array failing on Windows ILP64 CI job
- #12857: sparse A[0,:] = ndarray is ok, A[:,0] = ndarray ValueError from...
- #12860: BUG: Build failure with Xcode 12
- #12935: Failure to build with Python 3.9.0 on macOS
- #12966: MAINT: lint_diff.py on some backport PRs
- #12988: BUG: Highly multi-dimensional `gaussian_kde` giving `-inf`...

Pull requests for 1.5.4

- #12790: TST: Skip TestConvolve2d.test_large_array if not enough memory
- #12851: BUG: sparse: fix inner indexed assignment of a 1d array
- #12875: BUG: segfault in ndimage.fourier_ellipsoid with length-1 dims
- #12937: CI: macOS3.9 testing
- #12957: MAINT: fixes XCode 12/ python 3.9.0 build for 1.5.x maint branch
- #12959: CI: add Windows Python 3.9 to CI
- #12974: MAINT: Run lint_diff.py against the merge target and only for...
- #12978: DOC: next_fast_len output doesn't match docstring
- #12979: BUG: fft.next_fast_len should accept keyword arguments
- #12989: BUG: improved the stability of kde for highly (1000s) multi-dimension...
- #13017: BUG: Add explicit cast to _tmp sum.
- #13022: TST: xfail test_maxiter_worsening()

3.3 SciPy 1.5.3 Release Notes

Contents

- *SciPy 1.5.3 Release Notes*
 - *Authors*
 - * *Issues closed for 1.5.3*
 - * *Pull requests for 1.5.3*

SciPy 1.5.3 is a bug-fix release with no new features compared to 1.5.2. In particular, Linux ARM64 wheels are now available and a compatibility issue with XCode 12 has been fixed.

3.3.1 Authors

- Peter Bell
- CJ Carey
- Thomas Duvernay +
- Gregory Lee
- Eric Moore
- odidev
- Dima Pasechnik
- Tyler Reddy
- Simon Segerblom Rex +
- Daniel B. Smith
- Will Tirone +
- Warren Weckesser

A total of 12 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 1.5.3

- #9611: Overflow error with new way of p-value calculation in kendall...
- #10069: scipy.ndimage.watershed_ift regression in 1.0.0
- #11260: BUG: DOP853 with complex data computes complex error norm, causing...
- #11479: RuntimeError: dictionary changed size during iteration on loading...
- #11972: BUG (solved): Error estimation in DOP853 ODE solver fails for...
- #12543: BUG: Picture rotated 180 degrees and rotated -180 degrees should...
- #12613: Travis X.4 and X.7 failures in master
- #12654: scipy.stats.combine_pvalues produces wrong results with method='mudholkar_george'

- #12819: BUG: Scipy Sparse slice indexing assignment Bug with zeros
- #12834: BUG: ValueError upon calling Scipy Interpolator objects
- #12836: ndimage.median can return incorrect values for integer inputs
- #12860: Build failure with Xcode 12

Pull requests for 1.5.3

- #12611: MAINT: prepare for SciPy 1.5.3
- #12614: MAINT: prevent reverse broadcasting
- #12617: MAINT: optimize: Handle nonscalar size 1 arrays in fmin_slsqp...
- #12623: MAINT: stats: Loosen some test tolerances.
- #12638: CI, MAINT: pin pytest for Azure win
- #12668: BUG: Ensure factorial is not too large in mstats.kendalltau
- #12705: MAINT: `openblas_support` added sha256 hash
- #12706: BUG: fix incorrect 1d case of the fourier_ellipsoid filter
- #12721: BUG: use special.sindg in ndimage.rotate
- #12724: BUG: per #12654 adjusted mudholkar_george method to combine p...
- #12726: BUG: Fix DOP853 error norm for complex problems
- #12730: CI: pin xdist for Azure windows
- #12786: BUG: stats: Fix formula in the `stats` method of the ARGUS...
- #12795: CI: Pin setuptools on windows CI
- #12830: [BUG] sparse: Avoid using size attribute in LIL __setitem__
- #12833: BUG: change list of globals items to list of a copy
- #12842: BUG: Use uint16 for cost in NI_WatershedElement
- #12845: BUG: avoid boolean or integer addition error in ndimage.measurements.median
- #12864: BLD: replace the #include of libqull_r.h with with this of qhull_ra.h...
- #12867: BUG: Fixes a ValueError yielded upon calling Scipy Interpolator...
- #12902: CI: Remove `env` from pytest.ini
- #12913: MAINT: Ignore pytest's PytestConfigWarning

3.4 SciPy 1.5.2 Release Notes

Contents

- *SciPy 1.5.2 Release Notes*
 - *Authors*
 - * *Issues closed for 1.5.2*

** Pull requests for 1.5.2*

SciPy 1.5.2 is a bug-fix release with no new features compared to 1.5.1.

3.4.1 Authors

- Peter Bell
- Tobias Biester +
- Evgeni Burovski
- Thomas A Caswell
- Ralf Gommers
- Sturla Molden
- Andrew Nelson
- ofirr +
- Sambit Panda
- Ilhan Polat
- Tyler Reddy
- Atsushi Sakai
- Pauli Virtanen

A total of 13 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 1.5.2

- #3847: Crash of `interpolate.splprep(task=-1)`
- #7395: `splprep` segfaults if fixed knots are specified
- #10761: `scipy.signal.convolve2d` produces incorrect values for large arrays
- #11971: DOC: search in devdocs returns wrong link
- #12155: BUG: Fix permutation of distance matrices in `scipy.stats.multiscale_graphcorr`
- #12203: Unable to install on PyPy 7.3.1 (Python 3.6.9)
- #12316: negative `scipy.spatial.distance.correlation`
- #12422: BUG: `slsqp`: `ValueError: failed to initialize intent(inout) array...`
- #12428: `stats.truncnorm.rvs()` never returns a scalar in 1.5
- #12441: `eigvalsh` inconsistent `eigvals=` `subset_by_index=`
- #12445: DOC: `scipy.linalg.eigh`
- #12449: Warnings are not filtered in `csr_matrix.sum()`
- #12469: SciPy 1.9 exception in `LSQSphereBivariateSpline`
- #12487: BUG: `optimize`: incorrect result from `approx_fprime`

- #12493: CI: GitHub Actions for maintenance branches
- #12533: eigh gives incorrect results
- #12579: BLD, MAINT: distutils issues in wheels repo

Pull requests for 1.5.2

- #12156: BUG: Fix permutation of distance matrices in `scipy.stats.multiscale_graphcorr`
- #12238: BUG: Use 64-bit indexing in `convolve2d` to avoid overflow
- #12256: BLD: Build `lsap` as a single extension instead of extension + ...
- #12320: BUG: `spatial`: avoid returning negative correlation distance
- #12383: ENH: Make `cKDTree.tree` more efficient
- #12392: DOC: update `scipy-sphinx-theme`
- #12430: BUG: `truncnorm` and `geninvgauss` never return scalars from `rvs`
- #12437: BUG: `optimize`: cast bounds to floats in `new_bounds_to_old/old_bounds_to_new`
- #12442: MAINT: `linalg`: Fix for input args of `eigvalsh`
- #12461: MAINT: `sparse`: write `matrix/asmatrix` wrappers without warning...
- #12478: BUG: fix `array_like` input defects and add tests for all functions...
- #12488: BUG: fix `approx_derivative` step size. Closes #12487
- #12500: CI: actions branch trigger fix
- #12501: CI: actions branch trigger fix
- #12504: BUG: `cKDTreeNode` use after free
- #12529: MAINT: allow graceful docs re-upload
- #12538: BUG: `linalg`: `eigh` type parameter handling corrected
- #12560: MAINT: `truncnorm.rvs` compatibility for ``Generator``
- #12562: redo gh-12188: fix segfaults in `splprep` with fixed knots
- #12586: BLD: Add `-std=c99` to `sigtools` to compile with C99
- #12590: CI: Add GCC 4.8 entry to travis build matrix
- #12591: BLD: fix cython error on master-branch cython

3.5 SciPy 1.5.1 Release Notes

Contents

- *SciPy 1.5.1 Release Notes*
 - *Authors*
 - * *Issues closed for 1.5.1*
 - * *Pull requests for 1.5.1*

SciPy 1.5.1 is a bug-fix release with no new features compared to 1.5.0. In particular, an issue where DLL loading can fail for SciPy wheels on Windows with Python 3.6 has been fixed.

3.5.1 Authors

- Peter Bell
- Loïc Estève
- Philipp Thölke +
- Tyler Reddy
- Paul van Mulbregt
- Pauli Virtanen
- Warren Weckesser

A total of 7 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 1.5.1

- #9108: documentation: `scipy.spatial.KDTree` vs. `scipy.spatial.cKDTree`
- #12218: Type error in `stats.ks_2samp` when `alternative != 'two-sided-`
- #12406: DOC: Docstring in `stats.anderson` function not properly formatted
- #12418: Regression in `hierarchy.dendrogram`

Pull requests for 1.5.1

- #12280: BUG: Fixes gh-12218, TypeError converting int to float inside...
- #12336: BUG: KDTree should reject complex input points
- #12344: MAINT: Don't use numpy's aliases of Python builtin objects.
- #12407: DOC: Fix docstring for `dist` param in `anderson` function
- #12410: CI: Run the Azure Windows Python36 32bit tests with mode 'fast'
- #12421: Fix regression in `scipy 1.5.0` in `dendrogram` when `labels` is a `numpy...`
- #12462: MAINT: move `distributor_init` import after `__config__` import

3.6 SciPy 1.5.0 Release Notes

Contents

- *SciPy 1.5.0 Release Notes*
 - *Highlights of this release*
 - * *New features*

- `scipy.cluster` *improvements*
- `scipy.fft` *improvements*
- `scipy.integrate` *improvements*
- `scipy.interpolate` *improvements*
- `scipy.io` *improvements*
- `scipy.linalg` *improvements*
- `scipy.ndimage` *improvements*
- `scipy.optimize` *improvements*
- `scipy.signal` *improvements*
- `scipy.sparse` *improvements*
- `scipy.spatial` *improvements*
- `scipy.special` *improvements*
- `scipy.stats` *improvements*
 - * *Deprecated features*
- `scipy` *deprecations*
- `scipy.special` *changes*
- `scipy.stats` *changes*
 - * *Backwards incompatible changes*
- `scipy.interpolate` *changes*
- `scipy.linalg` *changes*
- `scipy.signal` *changes*
- `scipy.stats` *changes*
 - * *Other changes*
 - * *Authors*
- *Issues closed for 1.5.0*
- *Pull requests for 1.5.0*

SciPy 1.5.0 is the culmination of 6 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Before upgrading, we recommend that users check that their own code does not use deprecated SciPy functionality (to do so, run your code with `python -Wd` and check for `DeprecationWarnings`). Our development attention will now shift to bug-fix releases on the 1.5.x branch, and on adding new features on the master branch.

This release requires Python 3.6+ and NumPy 1.14.5 or greater.

For running on PyPy, PyPy3 6.0+ and NumPy 1.15.0 are required.

3.6.1 Highlights of this release

- wrappers for more than a dozen new LAPACK routines are now available in `scipy.linalg.lapack`
- Improved support for leveraging 64-bit integer size from linear algebra backends
- addition of the probability distribution for two-sided one-sample Kolmogorov-Smirnov tests

New features

3.6.2 `scipy.cluster` improvements

Initialization of `scipy.cluster.vq.kmeans2` using `minit="++"` had a quadratic complexity in the number of samples. It has been improved, resulting in a much faster initialization with quasi-linear complexity.

`scipy.cluster.hierarchy.dendrogram` now respects the `matplotlib` color palette

3.6.3 `scipy.fft` improvements

A new keyword-only argument `plan` is added to all FFT functions in this module. It is reserved for passing in a pre-computed plan from libraries providing a FFT backend (such as `PyFFTW` and `mkl-fft`), and it is currently not used in SciPy.

3.6.4 `scipy.integrate` improvements

3.6.5 `scipy.interpolate` improvements

3.6.6 `scipy.io` improvements

`scipy.io.wavfile` error messages are more explicit about what's wrong, and extraneous bytes at the ends of files are ignored instead of raising an error when the data has successfully been read.

`scipy.io.loadmat` gained a `simplify_cells` parameter, which if set to `True` simplifies the structure of the return value if the `.mat` file contains cell arrays.

`pathlib.Path` objects are now supported in `scipy.io` Matrix Market I/O functions

3.6.7 `scipy.linalg` improvements

`scipy.linalg.eigh` has been improved. Now various LAPACK drivers can be selected at will and also subsets of eigenvalues can be requested via `subset_by_value` keyword. Another keyword `subset_by_index` is introduced. Keywords `turbo` and `eigvals` are deprecated.

Similarly, standard and generalized Hermitian eigenvalue LAPACK routines `?<sy/he>evx` are added and existing ones now have full `_lwork` counterparts.

Wrappers for the following LAPACK routines have been added to `scipy.linalg.lapack`:

- `?getc2`: computes the LU factorization of a general matrix with complete pivoting
- `?gesc2`: solves a linear system given an LU factorization from `?getc2`

- *?gejsv: computes the singular value decomposition of a general matrix*
with higher accuracy calculation of tiny singular values and their corresponding singular vectors
- *?geqrfp: computes the QR factorization of a general matrix with*
non-negative elements on the diagonal of R
- ?gtsvx: solves a linear system with general tridiagonal matrix
- ?gttrf: computes the LU factorization of a tridiagonal matrix
- ?gttrs: solves a linear system given an LU factorization from ?gttrf
- *?ptsvx: solves a linear system with symmetric positive definite*
tridiagonal matrix
- *?pttrf: computes the LU factorization of a symmetric positive definite*
tridiagonal matrix
- ?pttrs: solves a linear system given an LU factorization from ?pttrf
- *?pteqr: computes the eigenvectors and eigenvalues of a positive definite*
tridiagonal matrix
- ?tbtrs: solves a linear system with a triangular banded matrix
- *?csd: computes the Cosine Sine decomposition of an orthogonal/unitary*
matrix

Generalized QR factorization routines (?geqrf) now have full `_lwork` counterparts.

`scipy.linalg.cossin` Cosine Sine decomposition of unitary matrices has been added.

The function `scipy.linalg.khatri_rao`, which computes the Khatri-Rao product, was added.

The new function `scipy.linalg.convolution_matrix` constructs the Toeplitz matrix representing one-dimensional convolution.

3.6.8 `scipy.ndimage` improvements

3.6.9 `scipy.optimize` improvements

The finite difference numerical differentiation used in various `minimize` methods that use gradients has several new features:

- 2-point, 3-point, or complex step finite differences can be used. Previously only a 2-step finite difference was available.
- There is now the possibility to use a relative step size, previously only an absolute step size was available.
- If the `minimize` method uses bounds the numerical differentiation strictly obeys those limits.
- The numerical differentiation machinery now makes use of a simple cache, which in some cases can reduce the number of function evaluations.
- `minimize`'s `method= 'powell'` now supports simple bound constraints

There have been several improvements to `scipy.optimize.linprog`:

- The `linprog` benchmark suite has been expanded considerably.
- `linprog`'s dense pivot-based redundancy removal routine and sparse presolve are faster

- When `scikit-sparse` is available, solving sparse problems with `method='interior-point'` is faster

The caching of values when optimizing a function returning both value and gradient together has been improved, avoiding repeated function evaluations when using a HessianApproximation such as BFGS.

`differential_evolution` can now use the modern `np.random.Generator` as well as the legacy `np.random.RandomState` as a seed.

3.6.10 `scipy.signal` improvements

A new optional argument `include_nyquist` is added to `freqz` functions in this module. It is used for including the last frequency (Nyquist frequency).

`scipy.signal.find_peaks_cwt` now accepts a `window_size` parameter for the size of the window used to calculate the noise floor.

3.6.11 `scipy.sparse` improvements

Outer indexing is now faster when using a 2d column vector to select column indices.

`scipy.sparse.lil.tocsr` is faster

Fixed/improved comparisons between pydata sparse arrays and sparse matrices

BSR format sparse multiplication performance has been improved.

`scipy.sparse.linalg.LinearOperator` has gained the new `ndim` class attribute

3.6.12 `scipy.spatial` improvements

`scipy.spatial.geometric_slerp` has been added to enable geometric spherical linear interpolation on an n-sphere

`scipy.spatial.SphericalVoronoi` now supports calculation of region areas in 2D and 3D cases

The tree building algorithm used by `cKDTree` has improved from quadratic worst case time complexity to loglinear. Benchmarks are also now available for building and querying of balanced/unbalanced kd-trees.

3.6.13 `scipy.special` improvements

The following functions now have Cython interfaces in `cython_special`:

- `scipy.special.erfinv`
- `scipy.special.erfcinv`
- `scipy.special.spherical_jn`
- `scipy.special.spherical_yn`
- `scipy.special.spherical_in`
- `scipy.special.spherical_kn`

`scipy.special.log_softmax` has been added to calculate the logarithm of softmax function. It provides better accuracy than `log(scipy.special.softmax(x))` for inputs that make softmax saturate.

3.6.14 `scipy.stats` improvements

The function for generating random samples in `scipy.stats.dlaplace` has been improved. The new function is approximately twice as fast with a memory footprint reduction between 25 % and 60 % (see gh-11069).

`scipy.stats` functions that accept a seed for reproducible calculations using random number generation (e.g. random variates from distributions) can now use the modern `np.random.Generator` as well as the legacy `np.random.RandomState` as a seed.

The `axis` parameter was added to `scipy.stats.rankdata`. This allows slices of an array along the given axis to be ranked independently.

The `axis` parameter was added to `scipy.stats.f_oneway`, allowing it to compute multiple one-way ANOVA tests for data stored in n-dimensional arrays. The performance of `f_oneway` was also improved for some cases.

The PDF and CDF methods for `stats.geninvgauss` are now significantly faster as the numerical integration to calculate the CDF uses a Cython based `LowLevelCallable`.

Moments of the normal distribution (`scipy.stats.norm`) are now calculated using analytical formulas instead of numerical integration for greater speed and accuracy

Moments and entropy trapezoidal distribution (`scipy.stats.trapz`) are now calculated using analytical formulas instead of numerical integration for greater speed and accuracy

Methods of the truncated normal distribution (`scipy.stats.truncnorm`), especially `_rvs`, are significantly faster after a complete rewrite.

The `fit` method of the Laplace distribution, `scipy.stats.laplace`, now uses the analytical formulas for the maximum likelihood estimates of the parameters.

Generation of random variates is now thread safe for all SciPy distributions. 3rd-party distributions may need to modify the signature of the `_rvs()` method to conform to `_rvs(self, ..., size=None, random_state=None)`. (A one-time `VisibleDeprecationWarning` is emitted when using non-conformant distributions.)

The Kolmogorov-Smirnov two-sided test statistic distribution (`scipy.stats.kstwo`) was added. Calculates the distribution of the K-S two-sided statistic D_n for a sample of size n , using a mixture of exact and asymptotic algorithms.

The new function `median_abs_deviation` replaces the deprecated `median_absolute_deviation`.

The `wilcoxon` function now computes the p-value for Wilcoxon's signed rank test using the exact distribution for inputs up to length 25. The function has a new `mode` parameter to specify how the p-value is to be computed. The default is "auto", which uses the exact distribution for inputs up to length 25 and the normal approximation for larger inputs.

Added a new Cython-based implementation to evaluate gaussian kernel estimates, which should improve the performance of `gaussian_kde`

The `winsorize` function now has a `nan_policy` argument for refined handling of nan input values.

The `binned_statistic_dd` function with `statistic="std"` performance was improved by ~4x.

`scipy.stats.kstest(rvs, cdf, ...)` now handles both one-sample and two-sample testing. The one-sample variation uses `scipy.stats.kstest` (or `scipy.stats.kstest` with back off to `scipy.stats.kstest`) to calculate the p-value. The two-sample variation, invoked if `cdf` is array_like, uses an algorithm described by Hodges to compute the probability directly, only backing off to `scipy.stats.kstest` in case of overflow. The result in both cases is more accurate p-values, especially for two-sample testing with smaller (or quite different) sizes.

`scipy.stats.maxwell` performance improvements include a 20 % speed up for `fit()` and 5 % for `pdf()`

`scipy.stats.shapiro` and `scipy.stats.jarque_bera` now return a named tuple for greater consistency with other `stats` functions

Deprecated features

3.6.15 `scipy` deprecations

3.6.16 `scipy.special` changes

The `bdtr`, `bdtrc`, and `bdtri` functions are deprecating non-negative non-integral `n` arguments.

3.6.17 `scipy.stats` changes

The function `median_absolute_deviation` is deprecated. Use `median_abs_deviation` instead.

The use of the string "raw" with the `scale` parameter of `iqr` is deprecated. Use `scale=1` instead.

Backwards incompatible changes

3.6.18 `scipy.interpolate` changes

3.6.19 `scipy.linalg` changes

The output signatures of `?syevr`, `?heevr` have been changed from `w, v, info` to `w, v, m, isuppz, info`

The order of output arguments `w, v` of `<sy/he>{gv, gvd, gv}` is swapped.

3.6.20 `scipy.signal` changes

The output length of `scipy.signal.upfirdn` has been corrected, resulting outputs may now be shorter for some combinations of up/down ratios and input signal and filter lengths.

`scipy.signal.resample` now supports a `domain` keyword argument for specification of time or frequency domain input.

3.6.21 `scipy.stats` changes

Other changes

Improved support for leveraging 64-bit integer size from linear algebra backends in several parts of the SciPy codebase.

Shims designed to ensure the compatibility of SciPy with Python 2.7 have now been removed.

Many warnings due to unused imports and unused assignments have been addressed.

Many usage examples were added to function docstrings, and many input validations and intuitive exception messages have been added throughout the codebase.

Early stage adoption of type annotations in a few parts of the codebase

Authors

- @endolith
- Hameer Abbasi
- ADmitri +
- Wesley Alves +
- Berkay Antmen +
- Sylwester Arabas +
- Arne Küderle +
- Christoph Baumgarten
- Peter Bell
- Felix Berkenkamp
- Jordão Bragantini +
- Clemens Brunner +
- Evgeni Burovski
- Matthias Bussonnier +
- CJ Carey
- Derrick Chambers +
- Leander Claes +
- Christian Clauss
- Luigi F. Cruz +
- dankleeman
- Andras Deak
- Milad Sadeghi DM +
- jeremie du boisberranger +
- Stefan Endres
- Malte Esders +
- Leo Fang +
- felixhekhorn +
- Isuru Fernando
- Andrew Fowlie
- Lakshay Garg +
- Gaurav Gijare +
- Ralf Gommers
- Emmanuelle Guillard +
- Kevin Green +
- Martin Grignard +

- Maja Gwozdz
- Sturla Molden
- gyu-don +
- Matt Haberland
- hakeemo +
- Charles Harris
- Alex Henrie
- Santi Hernandez +
- William Hickman +
- Till Hoffmann +
- Joseph T. Iosue +
- Anany Shrey Jain
- Jakob Jakobson
- Charles Jekel +
- Julien Jerphanion +
- Jiacheng-Liu +
- Christoph Kecht +
- Paul Kienzle +
- Reidar Kind +
- Dmitry E. Kislov +
- Konrad +
- Konrad0
- Takuya KOUMURA +
- Krzysztof Pióro
- Peter Mahler Larsen
- Eric Larson
- Antony Lee
- Gregory Lee +
- Gregory R. Lee
- Chelsea Liu
- Cong Ma +
- Kevin Mader +
- Maja Gwóźdź +
- Alex Marvin +
- Matthias Kümmerer
- Nikolay Mayorov

- Mazay0 +
- G. D. McBain
- Nicholas McKibben +
- Sabrina J. Mielke +
- Sebastian J. Mielke +
- Miloš Komarčević +
- Shubham Mishra +
- Santiago M. Mola +
- Grzegorz Mrukwa +
- Peyton Murray
- Andrew Nelson
- Nico Schlömer
- nwjenkins +
- odidev +
- Sambit Panda
- Vikas Pandey +
- Rick Paris +
- Harshal Prakash Patankar +
- Balint Pato +
- Matti Picus
- Ilhan Polat
- poom +
- Siddhesh Poyarekar
- Vladyslav Rachek +
- Bharat Raghunathan
- Manu Rajput +
- Tyler Reddy
- Andrew Reed +
- Lucas Roberts
- Ariel Rokem
- Heshy Roskes
- Matt Ruffalo
- Atsushi Sakai +
- Benjamin Santos +
- Christoph Schock +
- Lisa Schwetlick +

- Chris Simpson +
- Leo Singer
- Kai Striega
- Søren Fuglede Jørgensen
- Kale-ab Tessera +
- Seth Troisi +
- Robert Uhl +
- Paul van Mulbregt
- Vasilij +
- Isaac Virshup +
- Pauli Virtanen
- Shakthi Visagan +
- Jan Vleeshouwers +
- Sam Wallan +
- Lijun Wang +
- Warren Weckesser
- Richard Weiss +
- wenhui-prudencemed +
- Eric Wieser
- Josh Wilson
- James Wright +
- Ruslan Yevdokymov +
- Ziyao Zhang +

A total of 129 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

3.6.22 Issues closed for 1.5.0

- #1455: ellipord does returns bogus values if gstop or gpass are negative...
- #1968: correlate2d's output does not agree with correlate's output in...
- #2744: BUG: optimize: '**kw' argument of 'newton_krylov' is not documented
- #4755: TypeError: data type "<i0" not understood
- #4921: scipy.optimize maxiter option not working as expected
- #5144: RuntimeWarning on csgraph.shortest_path when edge lengths are...
- #5309: Documentation of 'hybr' and 'lm' inconsistent in optimize.root
- #6026: Replace approx_grad with _numdiff.approx_derivative in scipy.optimize
- #6502: Computing Eigenvalues in an Interval with LAPACK

- #7058: Errors in `special.bdtri` and `special.bdtr` for non-integer `k` values
- #7700: SuperLU does not respect `perm_c="NATURAL"`
- #7895: Improvements to `io.loadmat`
- #8205: `ValueError` in `scipy.linalg.eigvalsh` for large matrix
- #8278: Memory limit for `scipy.sparse.linalg.spsolve` with `scikit-umfpack`
- #8327: `scipy.stats.mstats.winsorize` NaN handling
- #8341: `scipy.stats.ks_2samp` for masked and unmasked data give different...
- #8748: `scipy.stats.kstest` for same distribution: p-values nonuniform
- #9042: `optimize`: Incorrect statement about ``jac`` in the ``minimize``...
- #9197: problem with `scipy.signal.butter` with 1000+ points array
- #9212: EIGH very very slow → suggesting an easy fix
- #9553: `ndimage` routines behave badly when output has memory overlap...
- #9632: `ndimage.maximum_filter` undocumented behaviour using footprint...
- #9658: `scipy.optimize.minimize(method='COBYLA')` not threadsafe
- #9710: `stats.weightedtau([1], [1.0])` SEGFAULTs
- #9797: Master Tracker for some Kolmogorov-Smirnov test Issues
- #9844: `scipy.signal.upfirdn` gives different length matrix versus MATLAB...
- #9872: `scipy.signal.convolve` is slower when vectorized
- #9913: BUG: No `dt` in `StateSpace` operations
- #10014: Distribution names ``weibull_min`` and ``weibull_max`` should...
- #10159: BUG: `stats.chisquare` returns incorrect results for arrays of...
- #10302: `scipy.fft`: Add a ``plan`` argument
- #10332: 'Incomplete wav chunk' inconsistent/reason unknown
- #10441: Remove uses of ``numpy.dual``?
- #10558: Document implicit sum in `csr_matrix()` constructor
- #10788: LU with full pivoting
- #10841: Unexpected behavior in `linalg.blas.dtrmm` wrapper
- #10919: `optimize._lbfgsb.setulb()` function violates parameter bounds
- #10963: `kstest`, `ks_2samp`: confusing ``mode`` argument descriptions
- #11022: Unexpected Result in factorial function with NaN input
- #11028: Documentation error in `optimize.minimize`
- #11058: Adding `logsoftmax` function
- #11076: `ValueError`: Unknown wave file format
- #11090: Misconception of the median absolute deviation in `stats?`
- #11095: BUG: `find_peaks_cwt` test failures in 32-bit Linux wheels
- #11107: `scipy.io.mmread` generated an error "TypeError: startswith first..."

- #11123: Add wrapper for ?gttrf/?gttrs
- #11128: OverflowError in resample_poly (upfirdn)
- #11132: Possible bug: rv_discret.ppf for percentiles 0 and 100 and loc...
- #11163: Comparisons between scipy spmatrix and can sparse.SparseArray...
- #11168: Generalized Pareto variance inaccurate for concentrations near...
- #11169: Add wrapper for ?geqrfp
- #11184: 2-sided Kolmogorov Smirnov returns p-value of 1
- #11185: The .roots() or solve() function of scipy.interpolate.CubicHermiteSpline...
- #11190: Add wrapper for ?tbtrs
- #11200: Can no longer slice csr_matrix in 1.3.0
- #11207: _minimize_scalar_bounded: reference before assignment
- #11216: linprog: interior-point: Cholmod reordering can be reused
- #11223: Add wrappers for ?pttrf, ?pttrs
- #11224: Add wrapperfor ?pteqr
- #11235: MAINT: Misleading Error Message for IIR Filter
- #11244: Missing reference in `scipy.optimize.line_search`
- #11262: Hermitian Eigenvalue Problem eigh() API and wrapper change proposal
- #11266: Sparse matrix constructor data type detection changes on Numpy...
- #11270: CI failing: Travis CI Py36 refguide and Linux_Python_36_32bit_full...
- #11279: linalg.eigh checks whole array for finite values
- #11295: CI: azure does not auto-cancel old jobs on pushes
- #11299: stats.truncnorm.rvs 100x slower in v1.4.x than v1.3.3
- #11315: BUG: special: rgamma on negative integers smaller -34
- #11319: Missing `int64_t` declaration in rectangular_lsap.cpp
- #11323: Compilation failure due to missing symbol pthread_atfork
- #11332: BUG: directed_hausdorff distance on sets u and v when u is a...
- #11350: Khatri-Rao product
- #11354: ENH: Add wrapper for ?gejsv
- #11361: Dropped NaN in eval_genlaguerre function
- #11363: Dropped NaN in hyperu function
- #11365: scipy.stats.binned_statistic regressed in v1.4.0
- #11369: Dropped NaN in eval_hermite
- #11370: Dropped NaN in eval_gegenbauer
- #11373: Add wrapper for ?gtsvx
- #11374: Add wrapper for ?ptsvx
- #11391: csgraph.minimum_spanning_tree loses precision

- #11398: Update stats to cope with ``np.random.Generator`` machinery
- #11412: Array copying causes unwanted type casting from complex to float...
- #11415: Where is the Wiener Filter derived from?
- #11416: `_lib._util.getargspec_no_self` is missing `KEYWORD_ONLY` support
- #11428: Documentation on SHGO inequality constraints appears contradictory
- #11429: Add LAPACK's ZUNCSD cosine sine decomposition
- #11438: `run_dualannealing` passes bounds incorrectly in `benchmarks/optimize.py`
- #11441: Can't run optimize benchmarks
- #11442: Chebyshev weights
- #11448: Wrongly typed comparison in `integrate.quad`
- #11458: BUG: `maximum_bipartite_matching` produces infeasible solution
- #11460: CI failing: 2 Travis CI tests fail with numpy build or version...
- #11462: Bug on "++" initialization on "kmeans2"
- #11464: Shouldn't data type of KDE evaluation should be like in the input...
- #11468: performance of `binned_statistics_2d` 100x slowdown from 1.3.2...
- #11484: Callback function doesn't give the same value as the one being...
- #11492: Confusing dendrogram labelling
- #11493: `scipy.optimize.least_squares` fails if the return array of the...
- #11494: Error performing kronecker product between large sparse vectors
- #11503: `medfilt` produces 0 on input of length 1
- #11529: Pyflakes generates almost 700 warnings.
- #11566: `irfft/irfft2/irfftn` docs are slightly confusing re: input type.
- #11572: `least_squares`: too small tolerances not caught with `method='lm'`
- #11581: DOC: `scipy.interpolate.RectSphereBivariateSpline`
- #11586: Differential evolution breaks with `LinearConstraints` with sparse...
- #11595: `scipy.spatial.cKDTree` construction slow for some datasets
- #11598: output of `special.voigt_profile` when `sigma=0`
- #11601: `linalg` tests failing in `runtests.py`
- #11602: `scipy.optimize.linear_sum_assignment` returns reverse diagonal...
- #11610: Analytic formula for normal moments
- #11611: Build failure with `gfortran 10`
- #11613: TST, MAINT: `test_quadpack TestCtypesQuad` wasn't fully migrated...
- #11630: `SmoothBivariateSpline` `bbox` parameter
- #11635: typo in docstring of `scipy.stats.norminvgauss`
- #11637: BUG: core dumps when calling `scipy.interpolate.interp1d` with...
- #11638: better documentation for 'return_all' option in `minimize(Nelder...`

- #11652: TST, MAINT: CI failures for pre-release NumPy wheels
- #11659: optimize.fmin_l_bfgs_b needs bound check and appropriate error...
- #11660: BUG/ENH: distribution.ncf with nc=0 returns nan
- #11661: scipy.ndimage.convolve1d and correlate1d don't behave properly...
- #11669: p-value varies with the order of the data
- #11676: documentation of scipy.spatial.HalfspaceIntersection: wrong method...
- #11685: Rotation cannot be expressed as matrix
- #11686: MAINT: mypy imports of Cython "modules"
- #11693: TestDifferentialEvolutionSolver::test_L4 failing in CI
- #11696: DOC: incorrect compiler information for macOS in docs
- #11709: eig() tests fail to pass, crash Python with seemingly random...
- #11763: Small error in gamma continuous rv fit comments
- #11769: truncnorm.rvs Weird Behaviors
- #11770: crash in TestEigh::test_value_subsets
- #11795: trapz distribution mean computed using single precision
- #11800: Segmentation fault in scipy.odr for multidimensional independent...
- #11811: pyflakes silently failing on travis-ci
- #11826: Error with _fblas
- #11827: `fft.tests.test_numpy.test_multiprocess` hangs on Python3.8...
- #11835: tests with `multiprocessing` hang on Python 3.8 on macOS
- #11839: linalg.expm returns nans with RuntimeWarning: overflow encountered...
- #11856: Documentation of fit methods for `weibull_min` and `exponweib`...
- #11868: Function always evaluated twice when using HessianUpdateStrategy...
- #11875: Typo in the docstring of simpso()
- #11877: kmeans2 '+' method is orders of magnitude slower than sklearn.cluster.KMeans()
- #11884: The upper code lines are dead code
- #11886: Array shape mismatch in scipy.optimize
- #11892: BUG: stats: Incorrect handling of edges cases by ttest_rel and...
- #11908: LinearOperator should have ndim attribute
- #11910: Documentation missing for what M is in init argument
- #11922: macOS actions CI has started failing in last couple of days.
- #11928: DOC: signal: Wrong description for sepfir2d, cspline2d, qspline2d
- #11944: curve_fit documentation unclear on default value of absolute_sigma
- #11945: Add a (potentially temporary) py.typed file?
- #11949: ValueError 'k exceeds matrix dimensions' for sparse.diagonal()...
- #11951: BUG: asv benchmark failed because of cython version

- #11967: BLD: Azure windows runs complain about drives
- #11973: `oaconvolve(a,b,'same')` differs in shape from `convolve(a,b,'same')`...
- #12002: pybind11 license
- #12003: MAINT: circular SphericalVoronoi input
- #12015: Reordering of CSC matrix breaks when you go above int32 limits
- #12031: Documentation Rendering Issues Visible in CircleCI Artifacts
- #12037: MAINT, CI: new Cython 3.0a4 issue
- #12087: DOC: some odr models are missing docs
- #12119: `signal.fftconvolve` no longer convolves types `f8` and `numpy.float64`
- #12149: Documentation of Rosenbrock function
- #12173: Large memory usage when indexing sparse matrices with ``np.ix_``
- #12178: BUG: stats: Some discrete distributions don't accept lists of ...
- #12220: BUG, REL: `gh_lists.py` compromised scraping
- #12239: BUG: median absolute deviation handling of nan
- #12301: integer overflow in `scipy.sparse.sputils.check_shape` when matrix size $> 2^{32}$
- #12314: `scipy.spatial.transform.Rotation` multiplication does not normalize quaternion

3.6.23 Pull requests for 1.5.0

- #6510: Add Eigenvalue Range Functionality for Symmetric Eigenvalue Problems
- #9525: BUG: SuperLU 'NATURAL' order applies a column permutation
- #9634: Add the number of Jacobian evaluations to the output of L-BFGS-B.
- #9719: ENH: Added `kstwo` probability distribution for two-sided one-sample...
- #9783: WIP: optimize: added (dense) interpolative decomposition redundancy...
- #10053: Adding docstring to `weibull_min` and `weibull_max` based on issue...
- #10136: DEP: Add warning to `linprog_verbose_callback`
- #10380: ENH: add `geometric_slerp`
- #10602: MAINT: optimize: refactor common `linprog` arguments into `namedtuple`
- #10648: Bounds for the Powell minimization method
- #10673: ENH: `approx_fprime` \rightarrow `approx_derivative`
- #10759: ENH: calculation of region areas in `spatial.SphericalVoronoi`
- #10762: BENCH: optimize: more comprehensive `linprog` benchmarking
- #10796: ENH exact p-values of wilcoxon test in `scipy.stats`
- #10797: ENH: `linalg`: LU with full pivoting (wrappers for `?getc2/?gesc2`)
- #10824: ENH: Fast gaussian kernel estimator
- #10942: BUG: prevent bound violation in L-BFGS-B optimize method
- #11003: ENH: add `scipy.linalg.convolution_matrix`

- #11023: improving error message for cubic-interpolate with duplicates
- #11045: MAINT: make `bdt{r,rc,ri}()` functions accept double `n,k` args +...
- #11063: Fix documentation error in `optimize.minimize`
- #11069: ENH: `stats.dlaplace.rvs` improvements
- #11071: DOC: Added examples to `maximum_position` in `ndimage`
- #11075: DOC: Update stylistic consistency in multiple files
- #11097: BUG: `stats`: fixing `chisquare` to return correct results for arrays...
- #11110: ENH: special: Cythonise `erfinv`, `erfcinv`
- #11112: BUG: special: Return NaN outside the domain of ``eval_hermite``
- #11114: BUG: special: fix ``hyp1f1`` for nonnegative integral ``a`` and...
- #11115: DOC: special: add docstrings for ``kei``, ``ker``, ``keip``,...
- #11130: ENH: support for circular input
- #11136: BUG: `expm` handling of empty input
- #11138: DOC: stylistic consistency, punctuation, etc.
- #11139: MAINT: cluster: use `cython_blas`, remove handwritten BLAS wrappers
- #11146: DOC: update docs on `bp` parameter for `detrend`
- #11151: DOC: special: add docstrings for ``bei``, ``ber``, ``beip``,...
- #11156: ENH: add input validation for `ellipord`.
- #11157: DOC: stylistic revision, punctuation, consistency
- #11160: ignore warning on `0 * inf` in basin hopping
- #11162: DOC: minor stylistic revision, undo changes
- #11164: ENH/ BUG: Pydata sparse equality
- #11171: Fix dtype validation of “seuclidean” metric `V` parameter
- #11177: BUG: `stats`: Improve `genpareto` stats calculations.
- #11180: MAINT: `stats`: Some clean up in `test_distributions.py`.
- #11187: ENH: add functionality `log_softmax` to `SciPy.special`.
- #11188: MAINT: add `rvs` method to `argus` in `scipy.stats`
- #11196: DOC: special: add to docstrings of Kelvin zeros functions
- #11202: BUG: fix edge counting in `shortest_path`
- #11218: BUG: `scipy/interpolate`: fix `PPoly/Cubic*Spline` `roots()` extrapolation...
- #11225: Add a warning to constant input for `spearmanr()` function
- #11226: Speed up of interior-point method for cholesky solver
- #11229: BUG: Explicit dtype specification in `_upfirdn.py`
- #11230: Additional citation for optimize tutorial
- #11231: Adds SLSQP test for duplicate f-evals (#10738)
- #11236: MAINT: Improved error message for `Wn` range in `iirfilter`.

- #11245: ENH: optimize: dense redundancy removal routine optimizations
- #11247: MAINT: Remove `_lib/_numpy_compat.py`
- #11248: BUG: `rv_discrete.ppf()` to handle loc
- #11251: DOC: add reference for linesearch zoom algorithm
- #11253: BUG: fix kendalltau issue where p-value becomes >1
- #11254: MAINT: make `special.factorial` handle nan correctly
- #11256: DOC: Updated documentation for `scipy.linalg.qr`
- #11265: Fix: Can no longer slice `csr_matrix` in 1.3.0
- #11267: BUG: Rework the scaling in the `ks_2samp` two-sided exact test.
- #11268: DOC: example of `NonLinearConstraint`
- #11269: Fix: Sparse matrix constructor data type detection changes on...
- #11276: BLD: update minimum Python, NumPy, Cython, Pybind11 versions
- #11277: MAINT: Cleanup conditionals for unsupported numpy versions
- #11278: MAINT: Cleanup `stats.iqr` workarounds for unsupported NumPy versions
- #11282: TST/CI: improve traceback formatting for test failures
- #11284: fix docs & behavior for mode sequences in `ndimage` filters
- #11285: DOC: special: complete the docstrings of Chi-square functions
- #11286: BUG: make `loadmat/savemat` file opening close resources correctly
- #11287: CI: skip Azure and TravisCI builds on merges and direct pushes...
- #11288: DOC: Fix import in `scipy.io.wavfile.read` sample code
- #11289: BUG: Use context manager for open
- #11290: MAINT: Remove `_lib._version` in favour of `_lib._pep440`
- #11292: DOC: special: add docstrings for various convenience functions
- #11293: DOC: special: fix typo in ``chdtri`` docstring
- #11296: DOC: special: add to docstrings of Bessel zeros and derivatives
- #11297: DOC: special: add parameters/returns sections for Bessel integrals
- #11300: MAINT: Update vendored `uarray` version
- #11301: CI: azure conditions should require `succeeded()`
- #11302: ENH: build infrastructure for ILP64 BLAS + ARPACK conversion
- #11303: DOC: special: fix typo in ``besselpoly`` docstring
- #11304: ENH: MAINT: Rewrite of `eigh()` and relevant wrappers
- #11306: TST: skip `test_aligned_mem` `linalg` test that is crashing on `ppc64`
- #11307: MAINT: Fix typo `'solutuion'` -> `'solution'`
- #11308: ENH: do not create 1d array out of a scalar
- #11310: MAINT: clean up object array creation, scalar/1d confusion
- #11311: DOC: Specify custom callable option for metric in `cluster.hierarchy.fclusterdata`

- #11316: BUG: special: fix behavior for `rgamma` zeros
- #11317: BUG: fix floating-point literal comparisons under C99
- #11318: TST: optimize: mark two linprog tests for skipping
- #11320: BUG: Include `int64_t` declaration to `rectangular_lsap.cpp`
- #11330: MAINT: Update vendored pypocketfft version
- #11333: BUG: directed_hausdorff subset fix
- #11335: [ENH] sparse: Loosen check for sparse outer indexing fast path
- #11337: Undefined name 'e' in pavement.py
- #11338: scipyoptdoc.py: Remove unused variable 'sixu'
- #11340: xrange() was removed in Python 3 in favor of range()
- #11342: range() was removed in Py3 in _binned_statistic.py
- #11343: BUG: constants: fix 'exact' values table
- #11347: ENH: add input validation function and apply it to needed functions
- #11348: MAINT: remove six.string_types usages
- #11349: MAINT: minor doc fix _minimize_trustregion_constr
- #11353: MAINT: py3 remove various six usages
- #11358: ENH: optimize: Use CSR format instead of LIL for speed
- #11362: MAINT: sys.version_info >= 3.5
- #11364: ENH: cache square of sums for f_oneway
- #11368: ENH: add optional argument, "include_nyquist", for freqz()
- #11372: BENCH: optimize: added linprog presolve benchmarks
- #11376: ENH: Add wrapper for ?gttrf/?gttrs
- #11377: MAINT: Remove Python 2 code from tools/authors.py
- #11378: ENH (WIP): Python wrapper for ?tbtrs
- #11379: MAINT: Remove six.with_metaclass from benchmarks/cython_special.py
- #11380: BUG: sparse/islve: bicg and qmr don't treat x0 correctly
- #11382: MAINT: remove error throw in binned_statistic_dd() on non-finite...
- #11383: MAINT: _lib: remove py2 compat shims in getargspec
- #11384: MAINT: Use numpy scalar types directly
- #11385: ENH: special: add spherical Bessel functions to `cython_special`
- #11389: MAINT: line.startswith shouldn't be bytes
- #11393: ENH: Speed up truncnorm's ppf() and rvs() methods
- #11394: MAINT: Remove self._size (and self._random_state) from stats...
- #11395: correction in error message (%d->%g format)
- #11396: DOC: revert gh10540, removing mtrand
- #11397: MAINT: differential_evolution accepts np.random.Generator

- #11402: ENH: stats can use np.random.Generator
- #11404: ENH: add docstring of butter() for transfer function syntax problem
- #11405: DOC: Fix “see also” for SmoothBivariateSpline
- #11408: ENH: Add a `plan` argument to FFT functions in `scipy.fft`
- #11411: MAINT: check minimize duplicate evaluations
- #11418: ENH: Linalg: Python wrapper for ?geqrfp
- #11419: TST: Python 3.7 mac OS gcc multibuild fix
- #11423: ENH: Add tool to lint diffs
- #11425: FIX: `_array_newton` should preserve complex inputs
- #11426: MAINT: licence for global optimization benchmarks
- #11431: Make median_absolute_deviation scale argument aligned w/iqr
- #11432: Fix error message typo
- #11433: DOC: Remove L from longs
- #11434: MAINT: Python3 improvements to refguide_check.py
- #11435: DOC: Update runtest -parallel help
- #11436: MAINT: Remove checks for sys.version < 3.5
- #11437: DOC: Fix documentation issue
- #11439: Support path objects (PEP 519) in mmio functions
- #11440: correct bounds pass in run_dualannealing for benchmarks/optimize.py
- #11443: BENCH: optimize_linprog remove ImportError exception
- #11453: BUG: sparse: convert csc/csr indices to int64 as needed
- #11454: DOC: Remove caveat on `maximum_bipartite_matching`
- #11455: BUG: Fix `_lib._util.getargspec_no_self` lack of KEYWORD_ONLY support.
- #11456: Implementation of khatri_rao product
- #11459: BUG: fix augmentation being broken in maximum_bipartite_matching
- #11461: MAINT: minor spelling corrections in comments in SciPy.sparse.linalg.arpack
- #11467: [MRG] Make result data type of KDE evaluation like in the input...
- #11469: Update integrate.quad documentation
- #11472: Fixed result typo
- #11476: DOC: stats: Copy-edit the anderson docstring.
- #11478: ENH: avoid unnecessary array copies in matrix product
- #11481: BUG: Make special.hyperu return nan if any argument is nan
- #11483: BUG: Fixed `_kpp` initialization on `scipy.cluster.vq`, closing...
- #11485: ENH: Update docstring of class KrylovJacobian to fix #2744
- #11486: BUG: make special.eval_hermite return nan if second argument...
- #11487: ENH: improve docstring of correlate and correlate2d to fix #1968

- #11488: FIX: change “func -> fun” of `scipy.optimize._root.py` to solve...
- #11489: BUG: fixes typo introduced in PR #11253 in `stats.mstats.kendalltau()`
- #11490: DOC: fix typo in `scipy/io/matlab/mio4.py`
- #11495: MAINT: refactor `slsqp` to fix issue in callback function
- #11498: [DOC] mention graph cuts in maximum flow docstring
- #11499: DOC: Improve documentation of `scipy.signal.signaltools.wiener`
- #11506: DOC: Fix typo in documentation of `scipy.stats.morestats`
- #11508: ENH: avoid copy on sparse `__init__` when dtype is given
- #11509: ENH: avoid unnecessary array copies in matrix product (again)
- #11510: [DOC] An ex. for creating arbitrary size tri-diagonal
- #11511: TST: pin numba for Travis/sparse
- #11513: TST: disable NumPy cache dir `ppc64le`
- #11514: BUG: make `special.eval_genlaguerre` return nan if passed nan
- #11517: ENH: improve `sparse.lil.tocsr` performance
- #11519: Fix fresnel documentation
- #11520: BUG: make `special.eval_gegenbauer` return nan if passed nan
- #11524: ENH: Cosine Sine Decomposition
- #11526: BUG: fix SLSQP max iteration setting to fix #4921
- #11527: ENH: improve docstring of `weibull_min_gen` and `weibull_max_gen`...
- #11530: MAINT: Removed 3 unused imports, 3 unused assignments from `ndimage`.
- #11531: DOC: fix typos in `bdtr` and `bdtrc` from gh PR 11045
- #11532: MAINT: Fixed several unused imports and unused assignments from...
- #11533: MAINT: Fixed about 100 unused imports, unused assignment warnings...
- #11534: FIX: Allow non-native byte order inputs to `scipy.fft`
- #11535: MAINT: Fixed several unused imports in `_lib`.
- #11536: MAINT: Fixed several unused imports and unused assignments in...
- #11537: MAINT: Removed an unused import in `scipy/constants`.
- #11538: MAINT: Fixed several unused imports in `scipy/fft`.
- #11539: MAINT: Fixed several unused imports and unused assignments in...
- #11540: MAINT: Fixed two unused imports in `scipy/misc`.
- #11541: MAINT: Fixed several unused imports and unused assignments in...
- #11542: MAINT: Fixed an unused import in `scipy/odr`.
- #11543: MAINT: Fixed several unused imports and unused assignments in...
- #11544: MAINT: Fixed unused imports and unused assignments in `scipy/integrate`.
- #11545: MAINT: Removed unused imports and fixed unused assignments in...
- #11546: MAINT: Removed unused imports; fixed unused assignments in `scipy/signal`.

- #11547: MAINT: Removed unused imports; fixed unused assignments in `scipy/spatial`
- #11548: MAINT: Removed unused imports; fixed unused assignments in `scipy.sparse`.
- #11549: MAINT: Replace `xrange` with `range`
- #11560: MAINT: stats: remove an `_argcheck` call
- #11573: MAINT: Removed unused imports; fixed unused assignments in `scipy/stats`.
- #11574: MAINT: Small change to ``optimize.nnl`` error messages.
- #11575: MAINT: Update `sytrd/hetrd` tests
- #11582: MAINT: fix typo in `quadpack.py` closes #11448
- #11585: TST: add `openblas_support.py`
- #11587: BUG: Differential evolution with `LinearConstraint` with sparse...
- #11588: MAINT: Fully display problem size in `lsqr/lsqr`.
- #11589: MAINT: Remove Python 2 workarounds
- #11590: MAINT: Remove `Python2` module init
- #11605: Standardization of bounds in `_linprog_util.py`
- #11608: BUG: fix use of `is` in DE callback
- #11614: TST, MAINT: `TestCtypesQuad` skip with `pytest`
- #11619: ENH: add `nan_policy` argument and functionality to `stats.mstats.winsorize`
- #11621: MAINT: Cleanup uses of `PY_VERSION_HEX`, `NPY_PY3K` in `ndimage`
- #11622: MAINT: Cleanup uses of `PY_VERSION_HEX`, `NPY_PY3K` in `sparse`
- #11623: MAINT: Remove unnecessary `'from __future__ import ...'` statements
- #11626: MAINT: Cleanup uses of `PY_VERSION_HEX`
- #11627: ENH: add analytic formula for normal moments
- #11628: MAINT, TST: adjust `azure` for `matplotlib` release
- #11631: Revert to old behaviour for constant cost matrices in ``linear_sum_assignment``
- #11632: MAINT: Define `ARRAY_ANYORDER` with `DEF` instead of `cdef`
- #11639: BUG: `interpolate/interp1d`: fail gracefully on all-nan inputs
- #11640: MAINT: Fix BLAS3 `trmm` wrapper for "side" arg
- #11642: TST, MAINT: remove dead code in Travis CI
- #11643: MAINT: fix conversion in `binom_test`
- #11645: MAINT: Assorted clean up.
- #11646: MAINT: Remove unnecessary `'from __future__ import ...'` statements
- #11647: DOC: document `return_all` arguments
- #11648: Perform geometric `slerp` in quaternion space
- #11651: DOC: Update paper URL in `lambertw` documentation
- #11653: PERF: Switch to C++ STL `std::nth_element`
- #11655: MAINT: Remove Python2 `cstringstream`

- #11657: ENH: Add wrapper for `?pttrf/?pttrs`
- #11664: ENH: Add wrapper for `?gejsv`
- #11665: ENH: Add wrapper for `?pteqr`
- #11667: BUG: Non-central Fisher distribution (fix nan-values when `nc=0`)
- #11668: ENH: Add wrapper for `?gtsvx`
- #11671: TST, CI: restore Azure temporarily
- #11672: Add warning to `medfilt` when `array size < kernel_size`
- #11674: TST: bump test precision for two `np.dot` related `linalg` tests.
- #11675: MAINT: `pycodestyle` clean-up
- #11677: ENH: Add wrapper for `?ptsvx`
- #11679: BENCH: `cKDTree` benchmarks added: balanced/unbalanced tree (related...)
- #11680: MAINT: `rng_integers` allows `RandomState.randint` or `Generator.integers`
- #11683: BUG: fix `mode='mirror'` on length 1 axes
- #11684: BUG: fix `scipy.special.voigt_profile`
- #11687: MAINT: `sparse.linalg`: avoid importing from ``np.core``
- #11688: ENH: `mypy`: get specific about ignoring missing imports
- #11690: MAINT: `mypy`: fix errors about incompatible types in lists
- #11692: MAINT: `mypy`: fix remaining type errors
- #11694: TST, MAINT: bump to OpenBLAS 0.3.9 stable, raise `tol` for Win...
- #11697: DOC: fix pdf of `norminvgauss` in `scipy.stats`
- #11701: MAINT: `special`: add rudimentary types for ``_ufuncs`` extension...
- #11702: BUG: Fixed a post-merge bug for `eigh()`
- #11703: Improves docstring with consistent L2-norm
- #11705: DOC: Slerp the `SphericalVoronoi` docstring
- #11706: ENH: `mypy`: add ``-mypy`` option to ``runtests.py``
- #11710: ENH: Modified `stats.kstest()` to use the exact `stats.kstwo.sf()`...
- #11715: DOC: add `.. versionadded::` to `as_matrix/from_matrix` in `spatial/transf...`
- #11716: BENCH: fix benchmark imports for ``optimize_linprog.py``
- #11721: MAINT: `io`: Remove now-unnecessary ``# type: ignore``
- #11722: MAINT: `mypy`: remove `mpmath` from the ratchet
- #11726: Handle constant input for `scipy.stats.f_oneway`
- #11729: BENCH: `optimize`: added infeasible benchmarks for `linprog`
- #11731: fix inaccurate information about Mac OS compiler (#11696)
- #11733: Fix inaccurate docstring example of `HalfspaceIntersection`
- #11734: Doc: fix inaccurate docstring of `SmoothBivariateSpline`.
- #11735: Bug: `stats`: fix wrong shape from `median_absolute_deviation` for...

- #11736: ENH: add input validations and its tests for FITPACK in fitpack2.py
- #11737: BUG: Prevent crashes due to MKL bug in ?heevr
- #11739: MAINT: special: add type stubs for `_test_round.pyx`
- #11740: MAINT: special: remove unused specfun f2py wrappers
- #11741: BUG: fix small tolerances handling for minpack and add a test.
- #11743: Doc: fix docstring of rfft, rfft2, rfftn, irfft, irfft2, irfftn...
- #11744: MAINT: Remove unused py3k.h code
- #11745: DOC: stats: Clean up ncf documentation.
- #11748: MAINT: special: type `cython_special` as `Any`
- #11750: MAINT: type hints for `_spherical_voronoi`
- #11752: DOC: fix docstring of scipy.optimize.least_squares
- #11753: ENH: add input validation for dendrogram and a test.
- #11755: MAINT: Replace uses of tostring with tobytes
- #11757: ENH: improve binned_statistics_2d performance.
- #11759: ENH: optimize: add HiGHS methods to linprog
- #11760: MAINT: Remove FileStream replaced by GenericStream
- #11761: MAINT: Replace npy_3kcompat.h shims
- #11765: TST: Speedup test_pascal which is VERY slow on Azure
- #11766: TST: speed up differential_evolution L8 test
- #11767: Change comment in continuous rv gamma fit function
- #11776: Add domain option for resample.
- #11784: BUG: Fixed calculation of nonzero elements in scipy.sparse.random
- #11786: ENH: stats: add axis keyword argument to scipy.stats.rankdata
- #11789: Doc: fix docstring of scipy.spatial.chebyshev
- #11792: DOC: dev: add guidelines for developing public Cython APIs
- #11794: MAINT: add comments explaining a problem in cython_optimize organization
- #11796: DOC: add a note about precision losing in csgraph.minimum_spanning_tree...
- #11797: ENH: Allow negative `axis` in `interpolate.BSpline`. Also...
- #11798: Add simplify_cells parameter to scipy.io.loadmat
- #11801: MAINT, DOC: minor changes of ratio-of-uniforms in scipy.stats
- #11802: BUG: fix scipy.odr to handle multidimensional independent and...
- #11803: scipy.stats.trapz: Use analytic formulas for stats and entropy.
- #11808: DOC: add Examples in the scipy.interpolate.interpn docstring.
- #11809: Duplicate entries are added together in csr_matrix constructor
- #11813: MAINT: bump pyflakes to version 2.1.1
- #11814: BUG: scipy.sparse.csr doctest failing with incorrect output value

- #11817: DOC: add Examples in the `scipy.optimize.leastsq` docstring
- #11820: ENH: Raise an error on incorrect bounds format in `optimize.fmin_l_bfgs_b`
- #11822: CI: add github actions for macOS
- #11824: DOC: add Examples in `scipy.optimize.line_search` docstring (`line_search_wolfe2`)
- #11830: TST: Always use fork for multiprocessing in fft tests
- #11831: DOC: add Examples and Returns in `scipy.misc.central_diff_weights...`
- #11832: DOC: stats: Some small corrections to a couple docstrings.
- #11833: BUG: Fix `compiler_name` when there are paths used in flags
- #11836: MAINT: re-introduce multiprocessing tests on Python3.8
- #11837: Doc: add Examples in `scipy.optimize.fsolve` docstring
- #11838: Doc: add Examples in `scipy.sparse.linalg.minres` docstring
- #11840: BUG: `sparse.linalg`: fix overflow in expm intermediate computation
- #11842: BLD: fix build with gfortran 10
- #11843: MAINT: Simplify floats in `constants.py`
- #11847: DOC: add a tutorial of `scipy.optimize.linprog`
- #11849: ENH: speed up `geninvgauss` by using cython
- #11852: CI: remove osx from travisCI
- #11857: BUG: Change parameter `fc` of `gausspulse` to float.
- #11861: order = degree + 1 for splines
- #11863: Make g77 ABI wrapper work with gfortran ABI lapack
- #11866: MAINT: add type ignores to `sympy` and `matplotlib` imports
- #11867: CI: Add arm64 in travis-ci
- #11869: DOC: signal: Add an example to the `lsim2` docstring.
- #11870: DOC: signal: Use `impulse` instead of `impulse2` in the `impulse` example...
- #11871: ENH: type `ufuncs` in `special` as `ufuncs` instead of `Any`
- #11872: BUG: avoid recomputing in `scipy.optimize.optimize.MemoizeJac`
- #11873: DOC: signal: Fix ODE in `impulse` and `impulse2` docstrings.
- #11874: DOC: add Examples of docstring for `scipy.interpolate.approximate_taylor_polynomial`
- #11878: DOC: fixed a typo under `scipy/integrate/quadrature.py`
- #11879: BUG: Fix index arrays overflow in `sparse.kron`
- #11880: DOC: stats: Add Examples for `bartlett`, `fligner`, `levene`.
- #11881: MAINT: normalise `numpy`→`np` in `optimize.py`
- #11882: DOC: add Examples for `scipy.io.readsav` docstring.
- #11883: DOC: add Returns and Examples for `scipy.ndimage.correlate()` docstring
- #11885: BUG: stats: Handle multidimensional arrays in `f_oneway`, and more.
- #11889: DOC: signal: Unify `lsim` and `lsim2` examples.

- #11896: BUG: stats: Fix handling of size 0 inputs for `ttest_rel` and `ttest_ind`.
- #11897: DOC: Remove misleading default values from fit method
- #11898: MAINT: `LinearVectorFunction.J` is ndarray closes #11886
- #11902: BUG: linalg: `test_heeclub` failure
- #11904: fix real-to-real transforms for complex inputs and `overwrite_x=True`
- #11906: DOC: stats: fix error caused by `trapz` docstring
- #11907: BUG: stats: fixed `SEGFAULT` from Issue #9710
- #11912: ENH: Respect matplotlib color palette with hierarchy/dendrogram.
- #11914: DOC: refine doc for `spatial.distance.squareform`
- #11915: ENH: Ndim linear operator
- #11919: ENH: expose “`window_size`” parameter in `find_peaks_cwt()`
- #11920: DOC: explain `M`, `diffev`
- #11923: CI: macOS install swig closes #11922
- #11924: DOC: add Examples for `scipy.optimize.bracket()` docstring
- #11930: DOC: add Examples and clean up for `signal.qspline1d` and `signal.qspline_eval...`
- #11931: DOC: add Examples for `sparse.linalg.bicg` docstring.
- #11933: DOC: Add original reference for Yao-Liu objective functions
- #11934: DOC, MAINT: mailmap update
- #11935: DOC: make `scipy.stats.mode` documentation reflect that the function...
- #11936: ENH: special: add type stubs for ``orthogonal.py``
- #11937: DOC: Add docstring examples to `fft2`, `ifft2`, `io.savemat`
- #11938: MAINT: add helper function for deprecating Cython API functions
- #11942: MAINT: ignore conditional import in `_lib/_util`
- #11943: MAINT: special: add types for `geterr/seterr/errstate`
- #11946: MAINT: add `py.typed` marker
- #11950: TST:MAINT: separated and stabilized heeclub tests
- #11952: DOC: update toolchain roadmap for py38, C99, C++11/14
- #11957: MAINT: Use `np.errstate` context manager instead of `np.seterr`.
- #11958: MAINT: interpolate: Remove some trailing spaces.
- #11960: MAINT: Cleanup Python2 compatibility code
- #11961: MAINT: Remove `numpy/np_3kcompat.h` from `_superluobject.c`
- #11962: DOC: Fix type of ``codes`` in docstring of ``_vq._vq()``
- #11964: MAINT: Cleanup unused `IS_PYPY`
- #11969: DOC: add Examples and fix docstring for `special.airye`
- #11970: BUG: sparse: ‘diagonal’ of sparse matrices fixed to match numpy’s...
- #11974: BUG: Reshape `oaconvolve` output even when no axes are convolved

- #11976: MAINT: add logo for github actions
- #11977: CI: test bleeding edge Python
- #11979: DOC: add Examples for stats.ranksums() docstring.
- #11982: Fix KMeans++ initialisation slowness
- #11983: DOC: add Examples for stats.mstats.argstoarray() docstring.
- #11986: Avoid bugs in ndimage when the output and input arrays overlap...
- #11988: ENH: Override fit method of Laplace distribution with Maximum...
- #11993: TST, CI: Azure Windows path fixups
- #11995: MAINT, CI: remove custom mingw Azure
- #11996: DOC: add Examples and fix pep warning for fft.set_global_backend...
- #11997: MAINT, CI: Azure OpenBLAS simplify
- #11998: BENCH: Run against current HEAD instead of master
- #12001: ENH: stats: Implement _logpdf for the maxwell distribution.
- #12004: DOC: add examples for integrate.quad_vec() and integrate.quad_explain()
- #12005: MAINT: Use helper functions in ?tbtrs tests
- #12007: MAINT: updated LICENSES_bundled for pybind11 and six
- #12008: DOC: roadmap update
- #12009: ENH: optimize: support 64-bit BLAS in lbfgsb
- #12010: ENH: sparse.linalg: support 64-bit BLAS in isolve
- #12012: DOC: add Examples for interpolate.barycentric_interpolate(),...
- #12013: MAINT: remove last uses of numpy.dual
- #12014: CI: print 10 slowest tests
- #12020: MAINT: Removed handling of circular input in SphericalVoronoi
- #12022: DOC : added default value of absolute_sigma to False in scipy.optimize.curve_fit docs
- #12024: DOC: add Examples for io.hb_read() and io.hb_write()
- #12025: MAINT: Remove numpy/np_3kcompat.h from nd_image
- #12028: Spelling correction
- #12030: ENH: optimize/_trlib: support ILP64 blas/lapack
- #12036: MAINT: Add some generated C files .gitignore
- #12038: MAINT, CI: Travis rackcdn->conda.org
- #12039: MAINT: signal: Lower the resolution of the plots in the chirp...
- #12040: DOC: add Examples for ndimage.spline_filter1d() and spline_filter()...
- #12044: MAINT: combine apt-get update and apt-get install into one RUN
- #12045: TST: Reduce size of test_diagonal_types to speed up tests
- #12046: MAINT: Remove unused npy_3kcompat.h
- #12047: MAINT: Cython 3.0 compat

- #12050: DOC: add download number badges of PyPI and conda-forge in README.rst
- #12052: DOC: add Examples `odr.models.polynomial()` and fix `odr.odr.docstring...`
- #12056: ENH: Modifies `shapiro` to return a named tuple
- #12057: Adding my name into THANKS.txt
- #12060: TST: Reduce number of `test_diagonal_types` configs
- #12062: TST: Change `dec.slow` to `pytest.mark.slow`
- #12068: ENH: Modifies `jarque_bera` to return a named tuple
- #12070: MAINT, CI: `appveyor rack->conda.org`
- #12072: TST: filter out `factorial(float)` deprecation warning
- #12078: TST: Skip test on colab with large memory alloc
- #12079: DOC: Remove Python2 reference from stats tutorial
- #12081: DOC: add Examples docstring for `optimize.show_options()`
- #12084: BUG: `interpolate`: fix `BarycentricInterpolator` with integer input...
- #12089: ENH: `spatial/qhull`: support ILP64 Lapack
- #12090: ENH: `integrate`: support ILP64 BLAS in `odeint/vode/lstsq`
- #12091: ENH: `integrate`: support ILP64 in `quadpack`
- #12092: BUG: Fix dropping `dt` in `signal.StateSpace`
- #12093: MAINT: Rollback `python2.6` workaround
- #12094: MAINT: ``openblas_support`` hash checks
- #12095: MAINT: `ndimage`: change ``shares_memory`` to ``may_share_memory``
- #12098: Doc: change 4 model instances of `odr` to be instances of ``Model``...
- #12101: Removed more unused imports and assignments.
- #12107: ENH: Area calculation for 2D inputs in `SphericalVoronoi`
- #12108: MAINT: ensure attributes have correct data type in ``SphericalVoronoi``
- #12109: `degree` is not `order` in `splines`
- #12110: ENH: More helpful/forgiving `io.wavfile` errors
- #12117: BUG: fix newline
- #12123: [MAINT] Fix error on `PyData/Sparse` import.
- #12124: TST: Always test `matmul` now that Python3.5+ is required
- #12126: TST: Cleanup unused `matplotlib` code.
- #12127: DOC: update docstrings of `signal.cspline2d`, `qspline2d`, `sepfir2d`
- #12130: MAINT: Fixing broken links with `linkchecker`
- #12135: ENH: `linalg`: Add the function `convolution_matrix`.
- #12136: MAINT: Cleanup `np.poly1d` hack
- #12137: TST, CI: reproduce wheels 32-bit setup
- #12140: TST: `stats`: add `kstwo`, `ksone` to slow tests.

- #12141: Support 64-bit integer size in Fitpack
- #12151: DOC: Correct Rosenbrock function sum
- #12159: BUG: Fix length calculation in upfirdn
- #12160: BUG: Fix M_PI
- #12168: DOC: add an obsolete version checking javascript to doc release...
- #12171: CI, MAINT: Azure OpenBLAS drive flip
- #12172: ENH: Bounds for the Powell minimization method
- #12175: BLD: support more Fortran compilers for ilp64 and macro expansion...
- #12179: BUG: stats: A few distributions didn't accept lists as arguments.
- #12180: MAINT: removed redundant import in SphericalVoronoi tests
- #12181: DOC: for versionwarning don't use \$.getScript
- #12182: MAINT: random sampling on the hypersphere in SphericalVoronoi...
- #12194: MAINT: Module and example cleanups for doc build
- #12202: ENH: tool to DL release wheels from Anaconda
- #12210: Remove py.typed marker (at least for the release)
- #12217: BUG: stats: Fix handling of edge cases in median_abs_deviation.
- #12223: BUG: stats: wilcoxon returned $p > 1$ for certain inputs.
- #12227: BLD: Set macos min version when building rectangular_lsap
- #12229: MAINT: tools/gh_lists.py: fix http header case sensitivity issue
- #12236: DOC: Fix a couple grammatical mistakes in 1.5.0-notes.rst.
- #12276: TST: skip *test_heeclub*, it fails intermittently.
- #12285: CI: split travis arm64 run into two
- #12317: BUG: prevent error accumulation in *Rotation* multiplication
- #12318: BUG: sparse: avoid np.prod overflow in check_shape
- #12319: BUG: Make cobyla threadsafe
- #12335: MAINT: Work around Sphinx bug

3.7 SciPy 1.4.1 Release Notes

Contents

- *SciPy 1.4.1 Release Notes*
 - *Authors*
 - * *Issues closed for 1.4.1*
 - * *Pull requests for 1.4.1*

SciPy 1.4.1 is a bug-fix release with no new features compared to 1.4.0. Importantly, it aims to fix a problem where an older version of pybind11 may cause a segmentation fault when imported alongside incompatible libraries.

3.7.1 Authors

- Ralf Gommers
- Tyler Reddy

Issues closed for 1.4.1

- #11237: Seg fault when importing torch

Pull requests for 1.4.1

- #11238: BLD: update minimum pybind11 version to 2.4.0.

3.8 SciPy 1.4.0 Release Notes

Contents

- *SciPy 1.4.0 Release Notes*
 - *Highlights of this release*
 - * *New features*
 - *Infrastructure*
 - *scipy.constants improvements*
 - *scipy.fft added*
 - *scipy.fftpack improvements*
 - *scipy.integrate improvements*
 - *scipy.interpolate improvements*
 - *scipy.io improvements*
 - *scipy.linalg improvements*
 - *scipy.ndimage improvements*
 - *scipy.optimize improvements*
 - *scipy.signal improvements*
 - *scipy.sparse improvements*
 - *scipy.spatial improvements*
 - *scipy.special improvements*
 - *scipy.stats improvements*

- * *Deprecated features*
- *scipy deprecations*
- * *Backwards incompatible changes*
- *scipy.special changes*
- *scipy.sparse changes*
- *scipy.signal changes*
- *scipy.stats changes*
- * *Other changes*
- * *Authors*
- *Issues closed for 1.4.0*
- *Pull requests for 1.4.0*

SciPy 1.4.0 is the culmination of 6 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Before upgrading, we recommend that users check that their own code does not use deprecated SciPy functionality (to do so, run your code with `python -Wd` and check for `DeprecationWarning`s). Our development attention will now shift to bug-fix releases on the 1.4.x branch, and on adding new features on the master branch.

This release requires Python 3.5+ and NumPy $\geq 1.13.3$ (for Python 3.5, 3.6), $\geq 1.14.5$ (for Python 3.7), $\geq 1.17.3$ (for Python 3.8)

For running on PyPy, PyPy3 6.0+ and NumPy 1.15.0 are required.

3.8.1 Highlights of this release

- a new submodule, `scipy.fft`, now supersedes `scipy.fftpack`; this means support for long double transforms, faster multi-dimensional transforms, improved algorithm time complexity, release of the global interpreter lock, and control over threading behavior
- support for pydata/sparse arrays in `scipy.sparse.linalg`
- substantial improvement to the documentation and functionality of several `scipy.special` functions, and some new additions
- the generalized inverse Gaussian distribution has been added to `scipy.stats`
- an implementation of the Edmonds-Karp algorithm in `scipy.sparse.csgraph.maximum_flow`
- **`scipy.spatial.SphericalVoronoi` now supports *n*-dimensional input,**
has linear memory complexity, improved performance, and supports single-hemisphere generators

New features

3.8.2 Infrastructure

Documentation can now be built with `runtests.py --doc`

A `Dockerfile` is now available in the `scipy/scipy-dev` repository to facilitate getting started with SciPy development.

3.8.3 `scipy.constants` improvements

`scipy.constants` has been updated with the CODATA 2018 constants.

3.8.4 `scipy.fft` added

`scipy.fft` is a new submodule that supersedes the `scipy.fftpack` submodule. For the most part, this is a drop-in replacement for `numpy.fft` and `scipy.fftpack` alike. With some important differences, `scipy.fft`: - uses NumPy's conventions for real transforms (`rfft`). This means the return value is a complex array, half the size of the full `fft` output. This is different from the output of `fftpack` which returned a real array representing complex components packed together. - the inverse real to real transforms (`idct` and `idst`) are normalized for `norm=None` in the same way as `ifft`. This means the identity `idct(dct(x)) == x` is now `True` for all `norm` modes. - does not include the convolutions or pseudo-differential operators from `fftpack`.

This submodule is based on the `pypocketfft` library, developed by the author of `pocketfft` which was recently adopted by NumPy as well. `pypocketfft` offers a number of advantages over fortran `FFTPACK`: - support for long double (`np.longfloat`) precision transforms. - faster multi-dimensional transforms using vectorisation - Bluestein's algorithm removes the worst-case $O(n^2)$ complexity of `FFTPACK` - the global interpreter lock (GIL) is released during transforms - optional multithreading of multi-dimensional transforms via the `workers` argument

Note that `scipy.fftpack` has not been deprecated and will continue to be maintained but is now considered legacy. New code is recommended to use `scipy.fft` instead, where possible.

3.8.5 `scipy.fftpack` improvements

`scipy.fftpack` now uses `pypocketfft` to perform its FFTs, offering the same speed and accuracy benefits listed for `scipy.fft` above but without the improved API.

3.8.6 `scipy.integrate` improvements

The function `scipy.integrate.solve_ivp` now has an `args` argument. This allows the user-defined functions passed to the function to have additional parameters without having to create wrapper functions or lambda expressions for them.

`scipy.integrate.solve_ivp` can now return a `y_events` attribute representing the solution of the ODE at event times

New `OdeSolver` is implemented — `DOP853`. This is a high-order explicit Runge-Kutta method originally implemented in Fortran. Now we provide a pure Python implementation usable through `solve_ivp` with all its features.

`scipy.integrate.quad` provides better user feedback when break points are specified with a weighted integrand.

`scipy.integrate.quad_vec` is now available for general purpose integration of vector-valued functions

3.8.7 `scipy.interpolate` improvements

`scipy.interpolate.pade` now handles complex input data gracefully

`scipy.interpolate.Rbf` can now interpolate multi-dimensional functions

3.8.8 `scipy.io` improvements

`scipy.io.wavfile.read` can now read data from a WAV file that has a malformed header, similar to other modern WAV file parsers

`scipy.io.FortranFile` now has an expanded set of available `Exception` classes for handling poorly-formatted files

3.8.9 `scipy.linalg` improvements

The function `scipy.linalg.subspace_angles(A, B)` now gives correct results for complex-valued matrices. Before this, the function only returned correct values for real-valued matrices.

New boolean keyword argument `check_finite` for `scipy.linalg.norm`; whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

`scipy.linalg.solve_triangular` has improved performance for a C-ordered triangular matrix

LAPACK wrappers have been added for `?geequ`, `?geequb`, `?syequb`, and `?heequb`

Some performance improvements may be observed due to an internal optimization in operations involving LAPACK routines via `_compute_lwork`. This is particularly true for operations on small arrays.

Block QR wrappers are now available in `scipy.linalg.lapack`

3.8.10 `scipy.ndimage` improvements

3.8.11 `scipy.optimize` improvements

It is now possible to use linear and non-linear constraints with `scipy.optimize.differential_evolution`.

`scipy.optimize.linear_sum_assignment` has been re-written in C++ to improve performance, and now allows input costs to be infinite.

A `ScalarFunction.fun_and_grad` method was added for convenient simultaneous retrieval of a function and gradient evaluation

`scipy.optimize.minimize` BFGS method has improved performance by avoiding duplicate evaluations in some cases

Better user feedback is provided when an objective function returns an array instead of a scalar.

3.8.12 `scipy.signal` improvements

Added a new function to calculate convolution using the overlap-add method, named `scipy.signal.oaconvolve`. Like `scipy.signal.fftconvolve`, this function supports specifying dimensions along which to do the convolution.

`scipy.signal.cwt` now supports complex wavelets.

The implementation of `choose_conv_method` has been updated to reflect the new FFT implementation. In addition, the performance has been significantly improved (with rather drastic improvements in edge cases).

The function `upfirdn` now has a `mode` keyword argument that can be used to select the signal extension mode used at the signal boundaries. These modes are also available for use in `resample_poly` via a newly added `padtype` argument.

`scipy.signal.sosfilt` now benefits from Cython code for improved performance

`scipy.signal.resample` should be more efficient by leveraging `rfft` when possible

3.8.13 `scipy.sparse` improvements

It is now possible to use the LOBPCG method in `scipy.sparse.linalg.svds`.

`scipy.sparse.linalg.LinearOperator` now supports the operation `rmatmat` for adjoint matrix-matrix multiplication, in addition to `rmatvec`.

Multiple stability updates enable float32 support in the LOBPCG eigenvalue solver for symmetric and Hermitian eigenvalues problems in `scipy.sparse.linalg.lobpcg`.

A solver for the maximum flow problem has been added as `scipy.sparse.csgraph.maximum_flow`.

`scipy.sparse.csgraph.maximum_bipartite_matching` now allows non-square inputs, no longer requires a perfect matching to exist, and has improved performance.

`scipy.sparse.lil_matrix` conversions now perform better in some scenarios

Basic support is available for pydata/sparse arrays in `scipy.sparse.linalg`

`scipy.sparse.linalg.spsolve_triangular` now supports the `unit_diagonal` argument to improve call signature similarity with its dense counterpart, `scipy.linalg.solve_triangular`

`assertAlmostEqual` may now be used with sparse matrices, which have added support for `__round__`

3.8.14 `scipy.spatial` improvements

The bundled Qhull library was upgraded to version 2019.1, fixing several issues. Scipy-specific patches are no longer applied to it.

`scipy.spatial.SphericalVoronoi` now has linear memory complexity, improved performance, and supports single-hemisphere generators. Support has also been added for handling generators that lie on a great circle arc (geodesic input) and for generators in n-dimensions.

`scipy.spatial.transform.Rotation` now includes functions for calculation of a mean rotation, generation of the 3D rotation groups, and reduction of rotations with rotational symmetries.

`scipy.spatial.transform.Slerp` is now callable with a scalar argument

`scipy.spatial.voronoi_plot_2d` now supports furthest site Voronoi diagrams

`scipy.spatial.Delaunay` and `scipy.spatial.Voronoi` now have attributes for tracking whether they are furthest site diagrams

3.8.15 `scipy.special` improvements

The Voigt profile has been added as `scipy.special.voigt_profile`.

A real dispatch has been added for the Wright Omega function (`scipy.special.wrightomega`).

The analytic continuation of the Riemann zeta function has been added. (The Riemann zeta function is the one-argument variant of `scipy.special.zeta`.)

The complete elliptic integral of the first kind (`scipy.special.ellipk`) is now available in `scipy.special.cython_special`.

The accuracy of `scipy.special.hyp1f1` for real arguments has been improved.

The documentation of many functions has been improved.

3.8.16 `scipy.stats` improvements

`scipy.stats.multiscale_graphcorr` added as an independence test that operates on high dimensional and nonlinear data sets. It has higher statistical power than other `scipy.stats` tests while being the only one that operates on multivariate data.

The generalized inverse Gaussian distribution (`scipy.stats.geninvgauss`) has been added.

It is now possible to efficiently reuse `scipy.stats.binned_statistic_dd` with new values by providing the result of a previous call to the function.

`scipy.stats.hmean` now handles input with zeros more gracefully.

The beta-binomial distribution is now available in `scipy.stats.betabinom`.

`scipy.stats.zscore`, `scipy.stats.circmean`, `scipy.stats.circstd`, and `scipy.stats.circvar` now support the `nan_policy` argument for enhanced handling of NaN values

`scipy.stats.entropy` now accepts an `axis` argument

`scipy.stats.gaussian_kde.resample` now accepts a `seed` argument to empower reproducibility

`scipy.stats.kendalltau` performance has improved, especially for large inputs, due to improved cache usage

`scipy.stats.truncnorm` distribution has been rewritten to support much wider tails

Deprecated features

3.8.17 `scipy` deprecations

Support for NumPy functions exposed via the root SciPy namespace is deprecated and will be removed in 2.0.0. For example, if you use `scipy.rand` or `scipy.diag`, you should change your code to directly use `numpy.random.default_rng` or `numpy.diag`, respectively. They remain available in the currently continuing SciPy 1.x release series.

The exception to this rule is using `scipy.fft` as a function – `scipy.fft` is now meant to be used only as a module, so the ability to call `scipy.fft(...)` will be removed in SciPy 1.5.0.

In `scipy.spatial.Rotation` methods `from_dcm`, `as_dcm` were renamed to `from_matrix`, `as_matrix` respectively. The old names will be removed in SciPy 1.6.0.

Method `Rotation.match_vectors` was deprecated in favor of `Rotation.align_vectors`, which provides a more logical and general API to the same functionality. The old method will be removed in SciPy 1.6.0.

Backwards incompatible changes

3.8.18 `scipy.special` changes

The deprecated functions `hyp2f0`, `hyp1f2`, and `hyp3f0` have been removed.

The deprecated function `bessel_diff_formula` has been removed.

The function `i0` is no longer registered with `numpy.dual`, so that `numpy.dual.i0` will unconditionally refer to the NumPy version regardless of whether `scipy.special` is imported.

The function `expn` has been changed to return `nan` outside of its domain of definition ($x, n < 0$) instead of `inf`.

3.8.19 `scipy.sparse` changes

Sparse matrix reshape now raises an error if shape is not two-dimensional, rather than guessing what was meant. The behavior is now the same as before SciPy 1.1.0.

CSR and CSC sparse matrix classes should now return empty matrices of the same type when indexed out of bounds. Previously, for some versions of SciPy, this would raise an `IndexError`. The change is largely motivated by greater consistency with `ndarray` and `numpy.matrix` semantics.

3.8.20 `scipy.signal` changes

`scipy.signal.resample` behavior for length-1 signal inputs has been fixed to output a constant (DC) value rather than an impulse, consistent with the assumption of signal periodicity in the FFT method.

`scipy.signal.cwt` now performs complex conjugation and time-reversal of wavelet data, which is a backwards-incompatible bugfix for time-asymmetric wavelets.

3.8.21 `scipy.stats` changes

`scipy.stats.loguniform` added with better documentation as (an alias for `scipy.stats.reciprocal`). `loguniform` generates random variables that are equally likely in the log space; e.g., 1, 10 and 100 are all equally likely if `loguniform(10 ** 0, 10 ** 2).rvs()` is used.

Other changes

The LSODA method of `scipy.integrate.solve_ivp` now correctly detects stiff problems.

`scipy.spatial.cKDTree` now accepts and correctly handles empty input data

`scipy.stats.binned_statistic_dd` now calculates the standard deviation statistic in a numerically stable way.

`scipy.stats.binned_statistic_dd` now throws an error if the input data contains either `np.nan` or `np.inf`. Similarly, in `scipy.stats` now all continuous distributions' `.fit()` methods throw an error if the input data contain any instance of either `np.nan` or `np.inf`.

Authors

- @endolith
- @wenhui-prudencemed +
- Abhinav +
- Anne Archibald
- ashwinpathak20nov1996 +
- Danilo Augusto +
- Nelson Auner +
- aypiggott +
- Christoph Baumgarten
- Peter Bell
- Sebastian Berg
- Arman Bilge +
- Benedikt Boecking +
- Christoph Boeddeker +
- Daniel Bunting
- Evgeni Burovski
- Angeline Burrell +
- Angeline G. Burrell +
- CJ Carey
- Carlos Ramos Carreño +
- Mak Sze Chun +
- Malayaja Chutani +
- Christian Clauss +
- Jonathan Conroy +
- Stephen P Cook +
- Dylan Cutler +
- Anirudh Dagar +
- Aidan Dang +
- dankleeman +
- Brandon David +
- Tyler Dawson +
- Dieter Werthmüller
- Joe Driscoll +
- Jakub Dyczek +
- Dávid Bodnár

- Fletcher Easton +
- Stefan Endres
- etienne +
- Johann Faouzi
- Yu Feng
- Isuru Fernando +
- Matthew H Flamm
- Martin Gauch +
- Gabriel Gerlero +
- Ralf Gommers
- Chris Gorgolewski +
- Domen Gorjup +
- Edouard Goudenhoofdt +
- Jan Gwinner +
- Maja Gwozdz +
- Matt Haberland
- hadshirt +
- Pierre Haessig +
- David Hagen
- Charles Harris
- Gina Helfrich +
- Alex Henrie +
- Francisco J. Hernandez Heras +
- Andreas Hilboll
- Lindsey Hiltner
- Thomas Hisch
- Min ho Kim +
- Gert-Ludwig Ingold
- jakobjakobson13 +
- Todd Jennings
- He Jia
- Muhammad Firmansyah Kasim +
- Andrew Knyazev +
- Holger Kohr +
- Mateusz Konieczny +
- Krzysztof Pióro +

- Philipp Lang +
- Peter Mahler Larsen +
- Eric Larson
- Antony Lee
- Gregory R. Lee
- Chelsea Liu +
- Jesse Livezey
- Peter Lysakovski +
- Jason Manley +
- Michael Marien +
- Nikolay Mayorov
- G. D. McBain +
- Sam McCormack +
- Melissa Weber Mendonça +
- Kevin Michel +
- mikeWShef +
- Sturla Molden
- Eric Moore
- Peyton Murray +
- Andrew Nelson
- Clement Ng +
- Juan Nunez-Iglesias
- Renee Otten +
- Kellie Ottoboni +
- Ayappan P
- Sambit Panda +
- Tapasweni Pathak +
- Oleksandr Pavlyk
- Fabian Pedregosa
- Petar Mlinarić
- Matti Picus
- Marcel Plch +
- Christoph Pohl +
- Ilhan Polat
- Siddhesh Poyarekar +
- Ioannis Prapas +

- James Alan Preiss +
- Yisheng Qiu +
- Eric Quintero
- Bharat Raghunathan +
- Tyler Reddy
- Joscha Reimer
- Antonio Horta Ribeiro
- Lucas Roberts
- rtshort +
- Josua Sassen
- Kevin Sheppard
- Scott Sievert
- Leo Singer
- Kai Striega
- Søren Fuglede Jørgensen
- tborisow +
- Étienne Tremblay +
- tuxcell +
- Miguel de Val-Borro
- Andrew Valentine +
- Hugo van Kemenade
- Paul van Mulbregt
- Sebastiano Vigna
- Pauli Virtanen
- Dany Vohl +
- Ben Walsh +
- Huize Wang +
- Warren Weckesser
- Anreas Weh +
- Joseph Weston +
- Adrian Wijaya +
- Timothy Willard +
- Josh Wilson
- Kentaro Yamamoto +
- Dave Zbarsky +

A total of 142 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

3.8.22 Issues closed for 1.4.0

- #1255: maxiter broken for `Scipy.sparse.linalg.gmres`, in addition to...
- #1301: consolidate `multipack.h` from `interpolate` and `integrate` packages...
- #1739: Single precision FFT insufficiently accurate. (Trac #1212)
- #1795: `stats.test_distributions.py`: replace old fuzz tests (Trac #1269)
- #2233: `fftpack` segfault with big arrays (Trac #1714)
- #2434: `rmatmat` and the sophistication of linear operator objects
- #2477: `stats.truncnorm.rvs()` does not give symmetric results for negative...
- #2629: `FFTPack` is unacceptably slow on non power of 2
- #2883: `UnboundLocalError` in `scipy.interpolate.splrep`
- #2956: Feature Request: axis argument for `stats.entropy` function
- #3528: Segfault on `test_djbfft` (possibly MKL-related?)
- #3793: `cwt` should also return complex array
- #4464: TST: `residue/residuez/invres/invresz` don't have any tests
- #4561: BUG: `tf` filter trailing and leading zeros in `residuez`
- #4669: Rewrite `sosfilt` to make a single loop over the input?
- #5040: BUG: Empty data handling of `(c)KDTrees`
- #5112: `boxcox` transform edge cases could use more care
- #5441: `scipy.stats.ncx2` fails for `nc=0`
- #5502: `args` keyword not handled in `optimize.curve_fit`
- #6484: `Qhull` segmentation fault
- #6900: `linear_sum_assignment` with infinite weights
- #6966: Hypergeometric Functions documentation is lacking
- #6999: possible false positive corruption check in `compressed_loadmat()`
- #7018: `ydata` that needs broadcasting renders `curve_fit` unable to compute...
- #7140: trouble with documentation for `windows`
- #7327: `interpolate.ndgriddata.griddata` causes Python to crash rather...
- #7396: `MatrixLinearOperator` implements `_adjoint()`, but not `_transpose()`
- #7400: BUG(?): `special.factorial` and `special.factorial2` return a 0-dimensional...
- #7434: Testing of `scipy.stats` continuous distributions misses 25 distributions
- #7491: Several `scipy.stats` distributions (`fisk`, `burr`, `burr12`, `f`) return...
- #7759: Overflow in `stats.kruskal` for large samples
- #7906: Wrong result from `scipy.interpolate.UnivariateSpline.integral`...

- #8165: ENH: match functionality of R for hmean
- #8417: optimize.minimize(method='L-BFGS-B', options={'disp': True})...
- #8535: Strictly increasing requirement in UnivariateSpline
- #8815: [BUG] GMRES: number of iteration is only increased if callback...
- #9207: scipy.linalg.solve_triangular speed after scipy.linalg.lu_factor
- #9275: new feature: adding LOBPCG solver in svds in addition to ARPACK
- #9403: range of truncnorm.logpdf could be extended
- #9429: gaussian_kde not working with numpy matrix
- #9515: ndimage implementation relies on undefined behavior
- #9643: arpack returns singular values in ascending order
- #9669: DOC: matthew-brett/build-openblas has been retired
- #9852: scipy.spatial.ConvexHull exit with code 134, free(): invalid...
- #9902: scipy.stats.truncnorm second moment may be wrong
- #9943: Custom sampling methods in shgo do not work
- #9947: DOC: Incorrect documentation for `nan_policy='propagate` in...
- #9994: BUG: sparse: reshape method allows a shape containing an arbitrary...
- #10036: Official Nelder mead tutorial uses xtol instead of xatol, which...
- #10078: possible to get a better error message when objective function...
- #10092: overflow in truncnorm.rvs
- #10121: A little spelling mistake
- #10126: inaccurate std implementation in binned_statistic
- #10161: Error in documentation scipy.special.modstruve
- #10195: Derivative of spline with 'const' extrapolation is also extrapolated...
- #10206: sparse matrices indexing with scipy 1.3
- #10236: Non-descriptive error on type mismatch for functions of scipy.optimize...
- #10258: LOBPCG convergence failure if guess provided
- #10262: distance matrix lacks dtype checks / warnings
- #10271: BUG: optimize failure on wheels
- #10277: scipy.special.zeta(0) = NAN
- #10292: DOC/REL: Some sections of the release notes are not nested correctly.
- #10300: scipy.stats.rv_continuous.fit throws empty RuntimeError when...
- #10319: events in scipy.integrate.solve_ivp: How do I setup an events...
- #10323: Adding more low-level LAPACK wrappers
- #10360: firwin2 inadvertently modifies input and may result in undefined...
- #10388: BLD: TestHerd::test_hetrd core dumps with Python-dbg
- #10395: Remove warning about output shape of zoom

- #10403: DOC: `scipy.signal.resample` ignores `t` parameter
- #10421: Yeo-Johnson power transformation fails with integer input data
- #10422: BUG: `scipy.fft` does not support multiprocessing
- #10427: ENH: `convolve` numbers should be updated
- #10444: BUG: `scipy.spatial.transform.Rotation.match_vectors` returns improper...
- #10488: ENH: DCTs/DSTs for `scipy.fft`
- #10501: BUG: `scipy.spatial.HalfspaceIntersection` works incorrectly
- #10514: BUG: `cKDTree` GIL handling is incorrect
- #10535: TST: master branch CI failures
- #10588: `scipy.fft` and `numpy.fft` inconsistency when `axes=None` and `shape...`
- #10628: Scipy python>3.6 Windows wheels don't ship `msvc*.dll`
- #10733: DOC/BUG: `min_only` result does not match documentation
- #10774: `min_only=true` `dijkstra` infinite loop with duplicate indices
- #10775: `UnboundLocalError` in `Radau` when given a `NaN`
- #10835: `io.wavfile.read` unnecessarily raises an error for a bad wav header
- #10838: Error in documentation for `scipy.linalg.lu_factor`
- #10875: DOC: Graphical guides (using TikZ)
- #10880: setting `verbose > 2` in `minimize` with `trust-constr` method leads...
- #10887: `scipy.signal.signaltools._fftconv_faster` has incorrect estimates
- #10948: `gammainc(0,x) = nan` but should be 1, `gammaincc(0,x) = nan` but...
- #10952: `TestQRdelete_F.test_delete_last_p_col` test failure
- #10968: API: Change `normalized=False` to `normalize=True` in `Rotation`
- #10987: Memory leak in `shgo` triangulation
- #10991: Error running `openBlas` probably missing a step
- #11033: deadlock on `osx` for python 3.8
- #11041: Test failure in wheel builds for `TestTf2zpk.test_simple`
- #11089: Regression in `scipy.stats` where distribution will not accept `loc` and `scale` parameters
- #11100: BUG: `multiscale_graphcorr` random state seeding and parallel use
- #11121: Calls to `scipy.interpolate.splprep` increase RAM usage.
- #11125: BUG: segfault when slicing a `CSR` or `CSC` sparse matrix with slice start index > stop index
- #11198: BUG: `sparse eigs (arpack)` shift-invert drops the smallest eigenvalue for some `k`

3.8.23 Pull requests for 1.4.0

- #4591: BUG, TST: Several issues with `scipy.signal.residue`
- #6629: ENH: sparse: canonicalize on initialization
- #7076: ENH: add complex wavelet support to `scipy.signal.cwt`.
- #8681: ENH add generalized inverse Gaussian distribution to `scipy.stats`
- #9064: BUG/ENH: Added default `_transpose` into `LinearOperator`. Fixes...
- #9215: ENH: Rbf interpolation of large multi-dimensional data
- #9311: ENH: Added `voigt` in `scipy.special`.
- #9642: ENH: integrate: `quad()` for vector-valued functions
- #9679: DOC: expand docstring of `exponweib` distribution
- #9684: TST: add `ppc64le` ci testing
- #9800: WIP : ENH: Refactored `_hungarian.py` for speed and added a `minimize/maximize`...
- #9847: DOC: Change integrate tutorial to use `solve_ivp` instead of `odeint`
- #9876: ENH: Use `rfft` when possible in resampling
- #9998: BUG: Do not remove 1s when calling sparse: `reshape` method #9994
- #10002: ENH: adds constraints for differential evolution
- #10098: ENH: integrate: add `args` argument to `solve_ivp`.
- #10099: DOC: Add missing docs for `linprog` `unknown_options`
- #10104: BUG: Rewrite of `stats.truncnorm` distribution.
- #10105: MAINT improve efficiency of `rvs_ratio_uniforms` in `scipy.stats`
- #10107: TST: `dual_annealing` set seed
- #10108: ENH: stats: improve `kendall_tau` cache usage
- #10110: MAINT: `_lib`: Fix a build warning.
- #10114: FIX: only print bounds when supported by minimizer (`shgo`)
- #10115: TST: Add a test with an almost singular design matrix for `lsq_linear`
- #10118: MAINT: fix `rdist` methods in `scipy.stats`
- #10119: MAINT: improve `rvs` of `randint` in `scipy.stats`
- #10127: Fix typo in record array field name (`spatial-ckdtree-sparse_distance...`)
- #10130: MAINT: `ndimage`: Fix some compiler warnings.
- #10131: DOC: Note the `solve_ivp` `args` enhancement in the 1.4.0 release...
- #10133: MAINT: add `rvs` for `semicircular` in `scipy.stats`
- #10138: BUG: special: Invalid arguments to `ellip_harm` can crash Python.
- #10139: MAINT: spatial: Fix some compiler warnings in the file `distance_wrap.c`.
- #10140: ENH: add handling of NaN in `RuntimeWarning` except clause
- #10142: DOC: return value of `scipy.special.comb`
- #10143: MAINT: Loosen `linprog` tol

- #10152: BUG: Fix custom sampling input for shgo, add unittest
- #10154: MAINT: add moments and improve doc of mielke in scipy.stats
- #10158: Issue #6999: read zlib checksum before checking bytes read.
- #10166: BUG: Correctly handle broadcasted ydata in curve_fit pcov computation.
- #10167: DOC: special: Add missing factor of ``i`` to ``modstruve`` docstring
- #10168: MAINT: stats: Fix an incorrect comment.
- #10169: ENH: optimize: Clarify error when objective function returns...
- #10172: DEV: Run tests in parallel when `-parallel` flag is passed to...
- #10173: ENH: Implement DOP853 ODE integrator
- #10176: Fixed typo
- #10182: TST: fix test issue for stats.pearsonr
- #10184: MAINT: stats: Simplify zmap and zscore (we can use keepdims now).
- #10191: DOC: fix a formatting issue in the scipy.spatial module docstring.
- #10193: DOC: Updated docstring for optimize.nnls
- #10198: DOC, ENH: special: Make ``hyp2f1`` references more specific
- #10202: DOC: Format DST and DCT definitions as latex equations
- #10207: BUG: Compressed matrix indexing should return a scalar
- #10210: DOC: Update docs for `connection='weak'` in `connected_components`
- #10225: DOC: Clarify new interfaces for legacy functions in `'optimize'`
- #10231: DOC, MAINT: gpg2 updates to release docs / pavement
- #10235: LICENSE: split license file in standard BSD 3-clause and bundled.
- #10238: ENH: Add new scipy.fft module using pocketfft
- #10243: BUG: fix ARFF reader regression with quoted values.
- #10248: DOC: update README file
- #10255: CI: bump OpenBLAS to match wheels
- #10264: TST: add tests for stats.tvar with unflattened arrays
- #10280: MAINT: stats: Use a constant value for `sqrt(2/PI)`.
- #10286: Development Documentation Overhaul
- #10290: MAINT: Deprecate NumPy functions in SciPy root
- #10291: FIX: Avoid importing xdist when checking for availability
- #10295: Disable deprecated Numpy API in `__odrpack.c`
- #10296: ENH: C++ extension for linear assignment problem
- #10298: ENH: Made pade function work with complex inputs
- #10301: DOC: Fix critical value significance levels in stats.anderson_ksamp
- #10307: Minkowski Distance Type Fix (issue #10262)
- #10309: BUG: Pass `jac=None` directly to lsoda

- #10310: BUG: interpolate: UnivariateSpline.derivative.ext is 'zeros'...
- #10312: FIX: Fixing a typo in a comment
- #10314: scipy.spatial enhancement request
- #10315: DOC: Update integration tutorial to solve_ivp
- #10318: DOC: update the example for PPoly.solve
- #10333: TST: add tests for stats.tvar with unflattened arrays
- #10334: MAINT: special: Remove deprecated `hyp2f0`, `hyp1f2`, and...
- #10336: BUG: linalg/interpolative: fix interp_decomp modifying input
- #10341: BUG: sparse.linalg/gmres: deprecate effect of callback on semantics...
- #10344: DOC: improve wording of mathematical formulation
- #10345: ENH: Tiled QR wrappers for scipy.linalg.lapack
- #10350: MAINT: linalg: Use the new fft subpackage in linalg.dft test...
- #10351: BUG: Fix unstable standard deviation calculation in histogram
- #10353: Bug: interpolate.NearestNDInterpolator (issue #10352)
- #10357: DOC: linalg: Refer to scipy.fft.fft (not fftpack) in the dft...
- #10359: DOC: Update roadmap now scipy.fft has been merged
- #10361: ENH: Prefer scipy.fft to scipy.fftpack in scipy.signal
- #10371: DOC: Tweaks to fft documentation
- #10372: DOC: Fix typos
- #10377: TST, MAINT: adjustments for pytest 5.0
- #10378: ENH: _lib: allow new np.random.Generator in check_random_state
- #10379: BUG: sparse: set writeability to be forward-compatible with numpy>=1.17
- #10381: BUG: Fixes gh-7491, pdf at $x=0$ of fisk/burr/burr12/f distributions.
- #10387: ENH: optimize/bfgs: don't evaluate twice at initial point for...
- #10392: [DOC] Add an example for _binned_statistic_dd
- #10396: Remove warning about output shape of zoom
- #10397: ENH: Add check_finite to sp.linalg.norm
- #10399: ENH: Add __round__ method to sparse matrix
- #10407: MAINT: drop pybind11 from install_requires, it's only build-time...
- #10408: TST: use pytest.raises, not numpy assert_raises
- #10409: CI: uninstall nose on Travis
- #10410: [ENH] ncx2 dispatch to chi2 when nc=0
- #10411: TST: optimize: test should use assert_allclose for fp comparisons
- #10414: DOC: add pybind11 to the other part of quickstart guides
- #10417: DOC: special: don't mark non-ufuncs with a `[+]`
- #10423: FIX: Use pybind11::isinstance to check array dtypes

- #10424: DOC: add doctest example for binary data for `ttest_ind_from_stats`
- #10425: ENH: Add missing Hermitian transforms to `scipy.fft`
- #10426: MAINT: Fix doc build bugs
- #10431: Update numpy version for AIX
- #10433: MAINT: Minor fixes for the stats
- #10434: BUG: special: make ``ndtri`` return NaN outside domain of definition
- #10435: BUG: Allow integer input data in `scipy.stats.yeojohnson`
- #10438: [DOC] Add example for kurtosis
- #10440: ENH: special: make ``ellipk`` a ufunc
- #10443: MAINT: ndimage: malloc fail check
- #10447: BLD: Divert output from test compiles into a temporary directory
- #10451: MAINT: signal: malloc fail check
- #10455: BUG: special: fix values of ``hyperu`` for negative ``x``
- #10456: DOC: Added comment clarifying the call for `dscrch.f` in `lbfgsb.f`
- #10457: BUG: Allow `ckdtree` to accept empty data input
- #10459: BUG:TST: Compute `lwork` safely
- #10460: [DOC] Add example to entropy
- #10461: DOC: Quickstart Guide updates
- #10462: TST: special: only show max `atol/rtol` for test points that failed
- #10465: BUG: Correctly align `fft` inputs
- #10467: ENH: lower-memory duplicate generator checking in `spatial.SphericalVoronoi`
- #10470: ENH: Normalise the inverse DCT/DST in `scipy.fft`
- #10472: BENCH: adjust timeout for slow `setup_cache`
- #10475: CI: include python debug for Travis-ci
- #10476: TST: special: use ``__tracebackhide__`` to get better error messages
- #10477: ENH: faster region building in `spatial.SphericalVoronoi`
- #10479: BUG: stats: Fix a few issues with the distributions' fit method.
- #10480: Add `RuntimeError` in `_distn_infrastructure.py` in `fit()` method
- #10481: BENCH, MAINT: `wheel_cache_size` has been renamed `build_cache_size`
- #10494: ENH: faster circumcenter calculation in `spatial.SphericalVoronoi`
- #10500: Splrep `_curfit_cache` global variable bugfix
- #10503: BUG: `spatial/qhull`: get `HalfspaceIntersection.dual_points` from...
- #10506: DOC: `interp2d`, note nearest neighbor extrapolation
- #10507: MAINT: Remove fortran `fftpack` library in favour of `pypocketfft`
- #10508: TST: fix a bug in the circular import test.
- #10509: MAINT: Set up `_build_utils` as subpackage

- #10516: BUG: Use nogil contexts in cKDTree
- #10517: ENH: fftconvolve should not FFT broadcastable axes
- #10518: ENH: Speedup fftconvolve
- #10520: DOC: Proper .rst formatting for deprecated features and Backwards...
- #10523: DOC: Improve scipy.signal.resample documentation
- #10524: ENH: Add MGC to scipy.stats
- #10525: [ENH] ncx2.ppf dispatch to chi2 when nc=0
- #10526: DOC: clarify laplacian normalization
- #10528: API: Rename scipy.fft DCT/DST shape argument to s
- #10531: BUG: fixed improper rotations in spatial.transform.rotation.match_vectors
- #10533: [DOC] Add example for winsorize function
- #10539: MAINT: special: don't register `i0` with `numpy.dual`
- #10540: MAINT: Fix Travis and Circle
- #10542: MAINT: interpolate: use cython_lapack
- #10547: Feature request. Add furthest site Voronoi diagrams to scipy.spatial.plotutils.
- #10549: [BUG] Fix bug in trimr when inclusive=False
- #10552: add scipy.signal.upfirdn signal extension modes
- #10555: MAINT: special: move `c_misc` into Cephes
- #10556: [DOC] Add example for trima
- #10562: [DOC] Fix triple string fo trimmed so that __doc__ can show...
- #10563: improve least_squares error msg for mismatched shape
- #10564: ENH: linalg: memoize get_lapack/blas_funcs to speed it up
- #10566: ENH: add implementation of solver for the maximum flow problem
- #10567: BUG: spatial: use c++11 construct for getting start of vector...
- #10568: DOC: special: small tweaks to the `zetac` docstring
- #10571: [ENH] Gaussian_kde can accept matrix dataset
- #10574: ENH: linalg: speed up _compute_lwork by avoiding numpy constructs
- #10582: Fix typos with typos in bundled libraries reverted
- #10583: ENH: special: add the analytic continuation of Riemann zeta
- #10584: MAINT: special: clean up `special.__all__`
- #10586: BUG: multidimensional scipy.fft functions should accept 's' rather...
- #10587: BUG: integrate/lsoda: never abort run, set error istate instead
- #10594: API: Replicate numpy's fftn behaviour when s is given but not...
- #10599: DOC: dev: update documentation vs. github pull request workflow...
- #10603: MAINT: installer scripts removed
- #10604: MAINT: Change `c*np.ones(...)` to `np.full(..., c, ...)` in many...

- #10608: Univariate splines should require x to be strictly increasing...
- #10613: ENH: Add seed option for gaussian_kde.resample
- #10614: ENH: Add parallel computation to scipy.fft
- #10615: MAINT: interpolate: remove unused header file
- #10616: MAINT: Clean up 32-bit platform xfail markers
- #10618: BENCH: Added 'trust-constr' to minimize benchmarks
- #10621: [MRG] multiple stability updates in lobpeg
- #10622: MAINT: forward port 1.3.1 release notes
- #10624: DOC: stats: Fix spelling of 'support'.
- #10627: DOC: stats: Add references for the alpha distribution.
- #10629: MAINT: special: avoid overflow longer in `zeta` for negative...
- #10630: TST: GH10271, relax test assertion, fixes #10271
- #10631: DOC: nelder-mean uses xatol fixes #10036
- #10633: BUG: interpolate: integral(a, b) should be zero when both limits...
- #10635: DOC: special: complete hypergeometric functions documentation
- #10636: BUG: special: use series for `hyp1f1` when it converges rapidly
- #10641: ENH: allow matching of general bipartite graphs
- #10643: ENH: scipy.sparse.linalg.spsolve triangular unit diagonal
- #10650: ENH: Cythonize sosfilt
- #10654: DOC: Vertical alignment of table entries
- #10655: ENH: Dockerfile for scipy development
- #10660: TST: clean up tests for rvs in scipy.stats
- #10664: Throw error on non-finite input for binned_statistic_dd()
- #10665: DOC: special: improve the docstrings for `gamma` and `gammasgn`
- #10669: TST: Update scipy.fft real transform tests
- #10670: DOC: Clarify docs and error messages for scipy.signal.butter
- #10672: ENH: return solution attribute when using events in solve_ivp
- #10675: MAINT: special: add an explicit NaN check for `iv` arguments
- #10679: DOC: special: Add documentation for `beta` function
- #10681: TST: sparse.linalg: fix arnoldi test seed
- #10682: DOC: special: Add documentation for `betainc` function
- #10684: TST: special: require Mpmath 1.1.0 for `test_hyperu_around_0`
- #10686: FIX: sphinx isattributedescriptor is not available in sphinx...
- #10687: DOC: added Docker quickstart guide by @andyfaff
- #10689: DOC: special: clarify format of parameters/returns sections for...
- #10690: DOC: special: improve docstrings of incomplete gamma functions

- #10692: ENH: higher-dimensional input in ``spatial.SphericalVoronoi``
- #10694: ENH: `ScalarFunction.fun_and_grad`
- #10698: DOC: special: Add documentation for ``betaincinv``
- #10699: MAINT: remove time print lbfgsb fixes #8417
- #10701: TST, MAINT: bump OpenBLAS to 0.3.7 stable
- #10702: DOC: clarify iterations consume multiple function calls
- #10703: DOC: `iprint doc lbfgsb closes #5482`
- #10708: TST: test suggested in gh1758
- #10710: ENH: Added `nan_policy` to `circ` functions in ``stats``
- #10712: ENH: add axis parameter to `stats.entropy`
- #10714: DOC: Formatting fix `rv_continuous.expect docs`
- #10715: DOC: BLD: update doc Makefile for python version; add scipy version...
- #10717: MAINT: modernize doc/Makefile
- #10719: Enable setting minres initial vector
- #10720: DOC: silence random warning in doc build for ``stats.binned_statistic_dd``
- #10724: DEV: Add doc option to `runtests.py`
- #10728: MAINT: get rid of `gramA`, `gramB` text files that `lobpcg` tests leave...
- #10732: DOC: add `min_only` to docstring for Dijkstra's algorithm
- #10734: DOC: spell out difference between source and target in `shortest...`
- #10735: Fix for Python 4
- #10739: BUG: `optimize/slsqp`: deal with singular BFGS update
- #10741: ENH: LAPACK wrappers for `?geequ`, `?geequb`, `?syequb`, `?heequb`
- #10742: DOC: special: add to the docstring of ``gammaIn``
- #10743: ENH: special: add a real dispatch for ``wrightomega``
- #10746: MAINT: Fix typos in comments, docs and test name
- #10747: Remove spurious quotes
- #10750: MAINT: make cython code more precise
- #10751: MAINT: Check that `scipy.linalg.lapack` functions are documented
- #10752: MAINT: special: use ``sf_error`` in `Cephes`
- #10755: DOC: cluster: Add 'See Also' and 'Examples' for `kmeans2`.
- #10763: MAINT: list of minimize methods
- #10768: BUG: Fix corner case for `sos2zpk`
- #10773: Fix error type for complex input to `scipy.fftpack.rfft` and `irfft`
- #10776: ENH: handle geodesic input in ``spatial.SphericalVoronoi``
- #10777: MAINT: `minimizer`→`custom` should handle the kinds of bounds/constrain.....
- #10781: ENH: `solve_triangular` C order improvement

- #10787: Fix behavior of ``exp1`` on branch cut and add docstring
- #10789: DOC: special: add parameters/returns doc sections for `erfc/erfcx/erfi`
- #10790: Travis CI: sudo is deprecated and Xenial is default distro
- #10792: DOC: special: add full docstring for ``expi``
- #10799: DOC: special: add a complete docstring for ``expn``
- #10800: Docs edits (GSoD)
- #10802: BUG: fix `UnboundLocalError` in `Radau` (scipy#10775)
- #10804: ENH: Speed up `next_fast_len` with LRU cache
- #10805: DOC: Fix unbalanced quotes in `signal.place_poles`
- #10809: ENH: Speed up `next_fast_len`
- #10810: ENH: Raise catchable exceptions for bad Fortran files
- #10811: MAINT: optimize: Remove extra variable from `_remove_redundancy_dense`
- #10813: MAINT: special: Remove unused variables from `_kolmogi` and `_smirnovi`
- #10815: DOC, API: `scipy.stats.reciprocal` is “log-uniform”
- #10816: MAINT: special: remove deprecated ``bessel_diff_formula``
- #10817: DOC: special: complete the docstring for ``fresnel``
- #10820: Fixed `compiler_helper.py` to allow compilation with ICC on Linux
- #10823: DOC: updated reference guide text for consistency in writing...
- #10825: MAINT: special: change some features of the Voigt function
- #10828: MAINT: integrate: Remove unused variable from `init_callback`
- #10830: Adding LOBPCG solver in `svds` in addition to ARPACK
- #10837: WIP: ENH: reduction function for ``spatial.transform.Rotation``...
- #10843: ENH: Adding optional parameter to `stats.zscores` to allow for...
- #10845: Rebase `kruskal` fix
- #10847: remove redundant `__getitem__` from `scipy.sparse.lil`
- #10848: Better handling of empty (not missing) docstrings
- #10849: ENH: implement `rmatmat` for `LinearOperator`
- #10850: MAINT : Refactoring `lil` List of Lists
- #10851: DOC: add a generative art example to the `scipy.spatial` tutorial.
- #10852: DOC: `linalg`: fixed gh-10838 unused imports in example deleted
- #10854: DOC: special: add a full docstring for ``pdtr``
- #10861: ENH: option to reuse `binnumbers` in `stats.binned_statistic_dd`
- #10863: DOC: partial standardization and validation of `scipy.stats` reference...
- #10865: BUG: special: fix incomplete gamma functions for infinite ``a``
- #10866: ENH: calculation of mean in `spatial.transform.Rotation`
- #10867: MAINT: Also store latex directory

- #10869: ENH: Implement overlap-add convolution
- #10870: ENH: Do not raise EOF error if wavfile data read
- #10876: ENH: Add beta-binomial distribution to scipy.stats
- #10878: MAINT: Update R project URL
- #10883: MAINT: (ndimage) More robust check for output being a numpy dtype
- #10884: DOC: Added instructions on adding a new distribution to scipy.stats.
- #10885: [BUG] fix lobpcg with maxiter=None results in Exception
- #10899: ENH: Match R functionality for hmean
- #10900: MAINT: stats: Use keepdims to simplify a few lines in power_divergence.
- #10901: ENH: sparse/linalg: support pydata/sparse matrices
- #10907: Check whether `maxiter` is integer
- #10912: ENH: warn user that quad() ignores `points=...` when `weight=...`...
- #10918: CI: fix Travis CI py3.8 build
- #10920: MAINT: Update constants to codata 2018 values (second try)
- #10921: ENH: scipy.sparse.lil: tocsr accelerated
- #10924: BUG: Forbid passing 'args' as kwarg in scipy.optimize.curve_fit
- #10928: DOC: Add examples to io.wavfile docstrings
- #10934: typo fix
- #10935: BUG: Avoid undefined behaviour on float to unsigned conversion
- #10936: DOC: Added missing example to stats.mstats.variation
- #10939: ENH: scipy.sparse.lil: tocsr accelerated depending on density
- #10946: BUG: setting verbose > 2 in minimize with trust-constr method...
- #10947: DOC: special: small improvements to the `poch` docstring
- #10949: BUG: fix return type of erlang_gen._argcheck
- #10951: DOC: fixed Ricker wavelet formula
- #10954: BUG: special: fix `factorial` return type for 0-d inputs
- #10955: MAINT: Relax the assert_unitary atol value
- #10956: WIP: make pdtr(int, double) be pdtr(double, double)
- #10957: BUG: Ensure full binary compatibility of long double test data
- #10964: ENH: Make Slerp callable with a scalar argument
- #10972: BUG: Handle complex gains in zpk2sos
- #10975: TST: skip test_kendalltau ppc64le
- #10978: BUG: boxcox data dimension and constancy check #5112
- #10979: API: Rename dcm to (rotation) matrix in Rotation class
- #10981: MAINT: add support for a==0 and x>0 edge case to igam and igamc
- #10986: MAINT: Remove direct imports from numpy in signaltools.py

- #10988: BUG: signal: fixed issue #10360
- #10989: FIX binned_statistic_dd Mac wheel test fails
- #10990: BUG: Fix memory leak in shgo triangulation
- #10992: TST: Relax tolerance in upfirdn test_modes
- #10993: TST: bump tolerance in optimize tests
- #10997: MAINT: Rework residue and residuez
- #11001: DOC: Updated Windows build tutorial
- #11004: BUG: integrate/quad_vec: fix several bugs in quad_vec
- #11005: TST: add Python 3.8 Win CI
- #11006: DOC: special: add a reference for ``kl_div``
- #11012: MAINT: Rework invres and invresz
- #11015: DOC: special: add references for ``rel_entr``
- #11017: DOC: numpydoc validation of morestats.py
- #11018: MAINT: Filter unrelated warning
- #11031: MAINT: update choose_conv_method for pocketfft implementation
- #11034: MAINT: TST: Skip tests with multiprocessing that use “spawn”...
- #11036: DOC: update doc/README with some more useful content.
- #11037: DOC: special: add a complete docstring for ``rgamma``
- #11038: DOC: special: add a reference for the polygamma function
- #11042: TST: fix tf2zpk test failure due to incorrect complex sorting.
- #11044: MAINT: choose_conv_method can choose fftconvolution for longcomplex
- #11046: TST: Reduce tolerance for ppc64le with reference lapack
- #11048: DOC: special: add reference for orthogonal polynomial functions
- #11049: MAINT: proper random number initialization and readability fix
- #11051: MAINT: pep8 cleanup
- #11054: TST: bump test precision for dual_annealing SLSQP test
- #11055: DOC: special: add a reference for ``zeta``
- #11056: API: Deprecated normalized keyword in Rotation
- #11065: DOC: Ubuntu Development Environment Quickstart should not modify...
- #11066: BUG: skip deprecation for numpy top-level types
- #11067: DOC: updated documentation for consistency in writing style
- #11070: DOC: Amendment to Ubuntu Development Environment Quickstart should...
- #11073: DOC: fix 1.4.0 release notes
- #11081: API: Replace Rotation.match_vectors with align_vectors
- #11083: DOC: more 1.4.0 release note fixes
- #11092: BUG: stats: fix freezing of some distributions

- #11096: BUG: scipy.sparse.csgraph: fixed issue #10774
- #11124: fix Cython warnings related to _stats.pyx
- #11126: BUG: interpolate/fitpack: fix memory leak in splprep
- #11127: Avoid potential segfault in CSR and CSC matrix indexing
- #11152: BUG: Fix random state bug multiscale_graphcorr
- #11166: BUG: empty sparse slice shapes
- #11167: BUG: redundant fft in signal.resample
- #11181: TST: Fix tolerance of tests for aarch64
- #11182: TST: Bump up tolerance for test_maxiter_worsening
- #11199: BUG: sparse.linalg: mistake in unsymm. real shift-invert ARPACK eigenvalue selection

3.9 SciPy 1.3.3 Release Notes

Contents

- *SciPy 1.3.3 Release Notes*
 - *Authors*
 - * *Issues closed for 1.3.3*
 - * *Pull requests for 1.3.3*

SciPy 1.3.3 is a bug-fix release with no new features compared to 1.3.2. In particular, a test suite issue involving multiprocessing was fixed for Windows and Python 3.8 on macOS.

Wheels were also updated to place msvc140.dll at the appropriate location, which was previously causing issues.

3.9.1 Authors

Ilhan Polat Tyler Reddy Ralf Gommers

Issues closed for 1.3.3

- #11033: deadlock on osx for python 3.8

Pull requests for 1.3.3

- #11034: MAINT: TST: Skip tests with multiprocessing that use “spawn” start method

3.10 SciPy 1.3.2 Release Notes

Contents

- *SciPy 1.3.2 Release Notes*
 - *Authors*
 - * *Issues closed for 1.3.2*
 - * *Pull requests for 1.3.2*

SciPy 1.3.2 is a bug-fix and maintenance release that adds support for Python 3.8.

3.10.1 Authors

- CJ Carey
- Dany Vohl
- Martin Gauch +
- Ralf Gommers
- Matt Haberland
- Eric Larson
- Nikolay Mayorov
- Sam McCormack +
- Andrew Nelson
- Tyler Reddy
- Pauli Virtanen
- Huize Wang +
- Warren Weckesser
- Joseph Weston +

A total of 14 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 1.3.2

- #4915: Bug in `unique_roots` in `scipy.signal.signaltools.py` for roots...
- #5161: Optimizers reporting success when the minimum is NaN
- #5546: `ValueError` raised if `scipy.sparse.linalg.expm` receives array...
- #10124: `linprog(method='revised simplex')` doctest bug
- #10609: Graph shortest path with Floyd-Warshall removes explicit zeros.
- #10658: BUG: stats: Formula for the variance of the noncentral F distribution...
- #10695: BUG: Assignment issues in `csr_matrix` with fancy indexing

- #10846: root_scalar fails when passed a function wrapped with functools.lru_cache
- #10902: CI: travis osx build failure
- #10967: macOS build failure in SuperLU on maintenance/1.3.x
- #10976: Typo in sp.stats.wilcoxon docstring

Pull requests for 1.3.2

- #10498: TST: optimize: fixed `linprog` ``disp``: True` bug
- #10536: CI: add 3.8-dev to travis
- #10671: BUG: stats: Fix the formula for the variance of the noncentral...
- #10693: BUG: ScalarFunction stores original array
- #10700: BUG: sparse: Loosen checks on sparse fancy assignment
- #10709: BUG: Fix floyd_warshall to support zero-weight edges
- #10756: BUG: optimize: ensure solvers exit with success=False for nan...
- #10833: BUG: Fix subspace_angles for complex values
- #10882: BUG: sparse/arpark: fix incorrect code for complex hermitian...
- #10891: BUG: make C-implemented root finders work with functools.lru_cache
- #10906: BUG: sparse/linalg: fix expm for np.matrix inputs
- #10917: CI: fix travis osx CI
- #10930: MAINT: Updates for 3.8
- #10938: MAINT: Add Python 3.8 to pyproject.toml
- #10943: BLD: update Cython version to 0.29.13
- #10961: BUG: Fix signal.unique_roots
- #10971: MAINT: use 3.8 stable in CI
- #10977: DOC: Fix typo in sp.stats.wilcoxon docstring
- #11025: Update _peak_finding.py

3.11 SciPy 1.3.1 Release Notes

Contents

- *SciPy 1.3.1 Release Notes*
 - *Authors*
 - * *Issues closed for 1.3.1*
 - * *Pull requests for 1.3.1*

SciPy 1.3.1 is a bug-fix release with no new features compared to 1.3.0.

3.11.1 Authors

- Matt Haberland
- Geordie McBain
- Yu Feng
- Evgeni Burovski
- Sturla Molden
- Tapasweni Pathak
- Eric Larson
- Peter Bell
- Carlos Ramos Carreño +
- Ralf Gommers
- David Hagen
- Antony Lee
- Ayappan P
- Tyler Reddy
- Pauli Virtanen

A total of 15 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 1.3.1

- #5040: BUG: Empty data handling of (c)KDTrees
- #9901: lsoda fails to detect stiff problem when called from solve_ivp
- #10206: sparse matrices indexing with scipy 1.3
- #10232: Exception in loadarff with quoted nominal attributes in scipy...
- #10292: DOC/REL: Some sections of the release notes are not nested correctly.
- #10303: BUG: optimize: *linprog* failing TestLinprogSimplexBland::test_unbounded_below_no_presolve_corrected
- #10376: TST: Travis CI fails (with pytest 5.0 ?)
- #10384: CircleCI doc build failing on new warnings
- #10398: Scipy 1.3.0 build broken in AIX
- #10501: BUG: scipy.spatial.HalfspaceIntersection works incorrectly
- #10514: BUG: cKDTree GIL handling is incorrect
- #10535: TST: master branch CI failures
- #10572: BUG: ckdtree query_ball_point errors on discontinuous input
- #10597: BUG: No warning on PchipInterpolator changing from bernstein base to local power base

Pull requests for 1.3.1

- #10071: DOC: reconstruct SuperLU permutation matrices avoiding SparseEfficiencyWarning
- #10196: Fewer checks on xdata for curve_fit.
- #10207: BUG: Compressed matrix indexing should return a scalar
- #10233: Fix for ARFF reader regression (#10232)
- #10306: BUG: optimize: Fix for 10303
- #10309: BUG: Pass jac=None directly to lsoda
- #10377: TST, MAINT: adjustments for pytest 5.0
- #10379: BUG: sparse: set writeability to be forward-compatible with numpy>=1.17
- #10426: MAINT: Fix doc build bugs
- #10431: Update numpy version for AIX
- #10457: BUG: Allow ckdtree to accept empty data input
- #10503: BUG: spatial/qhull: get HalfspaceIntersection.dual_points from the correct array
- #10516: BUG: Use nogil contexts in cKDTree
- #10520: DOC: Proper .rst formatting for deprecated features and Backwards incompatible changes
- #10540: MAINT: Fix Travis and Circle
- #10573: BUG: Fix query_ball_point with discontinuous input
- #10600: BUG: interpolate: fix broken conversions between PPoly/BPoly objects

3.12 SciPy 1.3.0 Release Notes

Contents

- *SciPy 1.3.0 Release Notes*
 - *Highlights of this release*
 - *New features*
 - * *scipy.interpolate improvements*
 - * *scipy.io improvements*
 - * *scipy.linalg improvements*
 - * *scipy.ndimage improvements*
 - * *scipy.optimize improvements*
 - * *scipy.signal improvements*
 - * *scipy.sparse improvements*
 - * *scipy.spatial improvements*
 - * *scipy.stats improvements*

- *Backwards-incompatible changes*
 - * `scipy.interpolate` changes
 - * `scipy.linalg` changes
 - * `scipy.optimize` changes
 - * `scipy.stats` changes
- *Other changes*
- *Authors*
 - * *Issues closed for 1.3.0*
 - * *Pull requests for 1.3.0*

SciPy 1.3.0 is the culmination of 5 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been some API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Before upgrading, we recommend that users check that their own code does not use deprecated SciPy functionality (to do so, run your code with `python -Wd` and check for `DeprecationWarnings`). Our development attention will now shift to bug-fix releases on the 1.3.x branch, and on adding new features on the master branch.

This release requires Python 3.5+ and NumPy 1.13.3 or greater.

For running on PyPy, PyPy3 6.0+ and NumPy 1.15.0 are required.

3.12.1 Highlights of this release

- Three new `stats` functions, a rewrite of `pearsonr`, and an exact computation of the Kolmogorov-Smirnov two-sample test.
- A new Cython API for bounded scalar-function root-finders in `scipy.optimize`.
- Substantial CSR and CSC sparse matrix indexing performance improvements.
- Added support for interpolation of rotations with continuous angular rate and acceleration in `RotationSpline`.

3.12.2 New features

`scipy.interpolate` improvements

A new class `CubicHermiteSpline` is introduced. It is a piecewise-cubic interpolator which matches observed values and first derivatives. Existing cubic interpolators `CubicSpline`, `PchipInterpolator` and `Akima1DInterpolator` were made subclasses of `CubicHermiteSpline`.

scipy.io improvements

For the Attribute-Relation File Format (ARFF) `scipy.io.arff.loader` now supports relational attributes.

`scipy.io.mmread` can now parse Matrix Market format files with empty lines.

scipy.linalg improvements

Added wrappers for `?syconv` routines, which convert a symmetric matrix given by a triangular matrix factorization into two matrices and vice versa.

`scipy.linalg.clarkson_woodruff_transform` now uses an algorithm that leverages sparsity. This may provide a 60-90 percent speedup for dense input matrices. Truly sparse input matrices should also benefit from the improved sketch algorithm, which now correctly runs in $O(\text{nnz}(A))$ time.

Added new functions to calculate symmetric Fiedler matrices and Fiedler companion matrices, named `scipy.linalg.fiedler` and `scipy.linalg.fiedler_companion`, respectively. These may be used for root finding.

scipy.ndimage improvements

Gaussian filter performances may improve by an order of magnitude in some cases, thanks to the removal of a dependence on `np.polynomial`. This may impact `scipy.ndimage.gaussian_filter` for example.

scipy.optimize improvements

The `scipy.optimize.brute` minimizer obtained a new keyword `workers`, which can be used to parallelize computation.

A Cython API for bounded scalar-function root-finders in `scipy.optimize` is available in a new module `scipy.optimize.cython_optimize` via `cimport`. This API may be used with `nogil` and `prange` to loop over an array of function arguments to solve for an array of roots more quickly than with pure Python.

'interior-point' is now the default method for `linprog`, and 'interior-point' now uses SuiteSparse for sparse problems when the required scikits (scikit-umfpack and scikit-sparse) are available. On benchmark problems (gh-10026), execution time reductions by factors of 2-3 were typical. Also, a new `method='revised simplex'` has been added. It is not as fast or robust as `method='interior-point'`, but it is a faster, more robust, and equally accurate substitute for the legacy `method='simplex'`.

`differential_evolution` can now use a `Bounds` class to specify the bounds for the optimizing argument of a function.

`scipy.optimize.dual_annealing` performance improvements related to vectorization of some internal code.

scipy.signal improvements

Two additional methods of discretization are now supported by `scipy.signal.cont2discrete`: `impulse` and `foh`.

`scipy.signal.firls` now uses faster solvers.

`scipy.signal.detrend` now has a lower physical memory footprint in some cases, which may be leveraged using the new `overwrite_data` keyword argument.

`scipy.signal.firwin` `pass_zero` argument now accepts new string arguments that allow specification of the desired filter type: 'bandpass', 'lowpass', 'highpass', and 'bandstop'.

`scipy.signal.sosfilt` may have improved performance due to lower retention of the global interpreter lock (GIL) in the algorithm.

scipy.sparse improvements

A new keyword was added to `csgraph.dijkstra` that allows users to query the shortest path to ANY of the passed-in indices, as opposed to the shortest path to EVERY passed index.

`scipy.sparse.linalg.lsmr` performance has been improved by roughly 10 percent on large problems.

Improved performance and reduced physical memory footprint of the algorithm used by `scipy.sparse.linalg.lobpcg`.

CSR and CSC sparse matrix fancy indexing performance has been improved substantially.

scipy.spatial improvements

`scipy.spatial.ConvexHull` now has a good attribute that can be used alongside the `QGn` `Qhull` options to determine which external facets of a convex hull are visible from an external query point.

`scipy.spatial.cKDTree.query_ball_point` has been modernized to use some newer Cython features, including GIL handling and exception translation. An issue with `return_sorted=True` and scalar queries was fixed, and a new mode named `return_length` was added. `return_length` only computes the length of the returned indices list instead of allocating the array every time.

`scipy.spatial.transform.RotationSpline` has been added to enable interpolation of rotations with continuous angular rates and acceleration.

scipy.stats improvements

Added a new function to compute the Epps-Singleton test statistic, `scipy.stats.epps_singleton_2samp`, which can be applied to continuous and discrete distributions.

New functions `scipy.stats.median_absolute_deviation` and `scipy.stats.gstd` (geometric standard deviation) were added. The `scipy.stats.combine_pvalues` method now supports `pearson`, `tippett` and `mudholkar_george` pvalue combination methods.

The `scipy.stats.ortho_group` and `scipy.stats.special_ortho_group` `rvs(dim)` functions' algorithms were updated from a $O(\text{dim}^4)$ implementation to a $O(\text{dim}^3)$ which gives large speed improvements for $\text{dim} > 100$.

A rewrite of `scipy.stats.pearsonr` to use a more robust algorithm, provide meaningful exceptions and warnings on potentially pathological input, and fix at least five separate reported issues in the original implementation.

Improved the precision of `hypergeom.logcdf` and `hypergeom.logsf`.

Added exact computation for Kolmogorov-Smirnov (KS) two-sample test, replacing the previously approximate computation for the two-sided test `stats.ks_2samp`. Also added a one-sided, two-sample KS test, and a keyword alternative to `stats.ks_2samp`.

3.12.3 Backwards-incompatible changes

`scipy.interpolate` changes

Functions from `scipy.interpolate` (`spleval`, `spline`, `splmake`, and `spltopp`) and functions from `scipy.misc` (`bytescale`, `fromimage`, `imfilter`, `imread`, `imresize`, `imrotate`, `imsave`, `imshow`, `toimage`) have been removed. The former set has been deprecated since v0.19.0 and the latter has been deprecated since v1.0.0. Similarly, aliases from `scipy.misc` (`comb`, `factorial`, `factorial2`, `factorialk`, `logsumexp`, `pade`, `info`, `source`, `who`) which have been deprecated since v1.0.0 are removed. [SciPy documentation for v1.1.0](#) can be used to track the new import locations for the relocated functions.

`scipy.linalg` changes

For `pinv`, `pinv2`, and `pinvh`, the default cutoff values are changed for consistency (see the docs for the actual values).

`scipy.optimize` changes

The default method for `linprog` is now `'interior-point'`. The method's robustness and speed come at a cost: solutions may not be accurate to machine precision or correspond with a vertex of the polytope defined by the constraints. To revert to the original simplex method, include the argument `method='simplex'`.

`scipy.stats` changes

Previously, `ks_2samp(data1, data2)` would run a two-sided test and return the approximated p-value. The new signature, `ks_2samp(data1, data2, alternative="two-sided", method="auto")`, still runs the two-sided test by default but returns the exact p-value for small samples and the approximated value for large samples. `method="asympt"` would be equivalent to the old version but `auto` is the better choice.

3.12.4 Other changes

Our tutorial has been expanded with a new section on global optimizers.

There has been a rework of the `stats.distributions` tutorials.

`scipy.optimize` now correctly sets the convergence flag of the result to `CONVERR`, a convergence error, for bounded scalar-function root-finders if the maximum iterations has been exceeded, `disp` is false, and `full_output` is true.

`scipy.optimize.curve_fit` no longer fails if `xdata` and `ydata` dtypes differ; they are both now automatically cast to `float64`.

`scipy.ndimage` functions including `binary_erosion`, `binary_closing`, and `binary_dilation` now require an integer value for the number of iterations, which alleviates a number of reported issues.

Fixed normal approximation in case `zero_method == "pratt"` in `scipy.stats.wilcoxon`.

Fixes for incorrect probabilities, broadcasting issues and thread-safety related to stats distributions setting member variables inside `__argcheck()`.

`scipy.optimize.newton` now correctly raises a `RuntimeError` in the following cases: when default arguments are used and if a derivative of value zero is obtained (which is a special case of failing to converge).

A draft toolchain roadmap is now available, laying out a compatibility plan including Python versions, C standards, and NumPy versions.

3.12.5 Authors

- ananyashreyjain +
- ApamNapat +
- Scott Calabrese Barton +
- Christoph Baumgarten
- Peter Bell +
- Jacob Blomgren +
- Doctor Bob +
- Mana Borwornpadungkitti +
- Matthew Brett
- Evgeni Burovski
- CJ Carey
- Vega Theil Carstensen +
- Robert Cimrman
- Forrest Collman +
- Pietro Cottone +
- David +
- Idan David +
- Christoph Deil
- Dieter Werthmüller
- Conner DiPaolo +
- Dowon
- Michael Dunphy +
- Peter Andreas Entschew +
- Gökçen Eraslan +
- Johann Faouzi +
- Yu Feng
- Piotr Figiel +
- Matthew H Flamm
- Franz Forstmayr +
- Christoph Gohlke
- Richard Janis Goldschmidt +
- Ralf Gommers
- Lars Grueter
- Sylvain Gubian
- Matt Haberland

- Yaroslav Halchenko
- Charles Harris
- Lindsey Hiltner
- JakobStruye +
- He Jia +
- Jwink3101 +
- Greg Kiar +
- Julius Bier Kirkegaard
- John Kirkham +
- Thomas Kluyver
- Vladimir Korolev +
- Joseph Kuo +
- Michael Lamparski +
- Eric Larson
- Denis Laxalde
- Katrin Leinweber
- Jesse Livezey
- ludcila +
- Dhruv Madeka +
- Magnus +
- Nikolay Mayorov
- Mark Mikofski
- Jarrod Millman
- Markus Mohrhard +
- Eric Moore
- Andrew Nelson
- Aki Nishimura +
- OGordon100 +
- Petar Mlinarić +
- Stefan Peterson
- Matti Picus +
- Ilhan Polat
- Aaron Pries +
- Matteo Ravasi +
- Tyler Reddy
- Ashton Reimer +

- Joscha Reimer
- rfezzani +
- Riadh +
- Lucas Roberts
- Heshy Roskes +
- Mirko Scholz +
- Taylor D. Scott +
- Srikrishna Sekhar +
- Kevin Sheppard +
- Sourav Singh
- skjerns +
- Kai Striega
- SyedSaifAliAlvi +
- Gopi Manohar T +
- Albert Thomas +
- Timon +
- Paul van Mulbregt
- Jacob Vanderplas
- Daniel Vargas +
- Pauli Virtanen
- VNMabus +
- Stefan van der Walt
- Warren Weckesser
- Josh Wilson
- Nate Yoder +
- Roman Yurchak

A total of 97 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 1.3.0

- [#1320](#): `scipy.stats.distribution`: problem with `self.a`, `self.b` if they...
- [#2002](#): `members` set in `scipy.stats.distributions.##_argcheck` (Trac #1477)
- [#2823](#): `distribution` methods add `tmp`
- [#3220](#): `Scipy.optimize.fmin_powell` `direc` argument syntax unclear
- [#3728](#): `scipy.stats.pearsonr`: possible bug with zero variance input
- [#6805](#): `error-in-scipy-wilcoxon-signed-rank-test-for-equal-series`

- #6873: 'stats.boxcox' return all same values
- #7117: Warn users when using float32 input data to curve_fit and friends
- #7632: it's not possible to tell the `optimize.least_squares` solver...
- #7730: stats.pearsonr: Potential division by zero for dataset of length...
- #7933: stats.truncnorm fails when providing values outside truncation...
- #8033: Add standard filter types to firwin to set pass_zero intuitively...
- #8600: lfilter.c.src zfill has erroneous header
- #8692: Non-negative values of `stats.hypergeom.logcdf`
- #8734: Enable pip build isolation
- #8861: scipy.linalg.pinv gives wrong result while scipy.linalg.pinv2...
- #8915: need to fix macOS build against older numpy versions
- #8980: scipy.stats.pearsonr overflows with high values of x and y
- #9226: BUG: signal: SystemError: <built-in function _linear_filter>...
- #9254: BUG: root finders brentq, etc, flag says "converged" even if...
- #9308: Test failure - test_initial_constraints_as_canonical
- #9353: scipy.stats.pearsonr returns r=1 if r_num/r_den = inf
- #9359: Planck distribution is a geometric distribution
- #9381: linregress should warn user in 2x2 array case
- #9406: BUG: stats: In pearsonr, when r is nan, the p-value must also...
- #9437: Cannot create sparse matrix from size_t indexes
- #9518: Relational attributes in loadarff
- #9551: BUG: scipy.optimize.newton says the root of x^2+1 is zero.
- #9564: rv_sample accepts invalid input in scipy.stats
- #9565: improper handling of multidimensional input in stats.rv_sample
- #9581: Least-squares minimization fails silently when x and y data are...
- #9587: Outdated value for scipy.constants.au
- #9611: Overflow error with new way of p-value calculation in kendall...
- #9645: `scipy.stats.mode` crashes with variable length arrays (`dtype=object`)
- #9734: PendingDeprecationWarning for np.matrix with pytest
- #9786: stats.ks_2samp() misleading for small data sets.
- #9790: Excessive memory usage on detrend
- #9801: dual_annealing does not set the success attribute in OptimizeResult
- #9833: IntegrationWarning from mielke.stats() during build of html doc.
- #9835: scipy.signal.firls seems to be inefficient versus MATLAB firls
- #9864: Curve_fit does not check for empty input data if called with...
- #9869: scipy.ndimage.label: Minor documentation issue

- #9882: format at the wrong paranthesis in `scipy.spatial.transform`
- #9889: `scipy.signal.find_peaks` minor documentation issue
- #9890: Minkowski p-norm Issues in `cKDTree` For Values Other Than 2 Or...
- #9896: `scipy.stats._argcheck` sets (not just checks) values
- #9905: Memory error in `ndimage.binary_erosion`
- #9909: `binary_dilation/erosion/closing` crashes when iterations is float
- #9919: BUG: ``coo_matrix`` does not validate the ``shape`` argument.
- #9982: `lsq_linear` hangs/infinite loop with `'trf'` method
- #10003: `exponnorm.pdf` returns NAN for small K
- #10011: Incorrect check for invalid rotation plane in `scipy.ndimage.rotate`
- #10024: Fails to build from git
- #10048: DOC: `scipy.optimize.root_scalar`
- #10068: DOC: `scipy.interpolate.splev`
- #10074: BUG: ``expm`` calculates the wrong coefficients in the backward...

Pull requests for 1.3.0

- #7827: ENH: sparse: overhaul of sparse matrix indexing
- #8431: ENH: Cython optimize zeros api
- #8743: DOC: Updated `linalg.pinv`, `.pinv2`, `.pinvh` docstrings
- #8744: DOC: added examples to `remez` docstring
- #9227: DOC: update description of `"direc"` parameter of `"fmin_powell"`
- #9263: ENH: optimize: added `"revised simplex"` for `scipy.optimize.linprog`
- #9325: DEP: Remove deprecated functions for 1.3.0
- #9330: Add note on push and pull affine transformations
- #9423: DOC: Clearly state how 2x2 input arrays are handled in `stats.linregress`
- #9428: ENH: parallelised brute
- #9438: BUG: Initialize `coo` matrix with `size_t` indexes
- #9455: MAINT: Speed up `get_(lapack,blas)_func`
- #9465: MAINT: Clean up `optimize.zeros` C solvers interfaces/code.
- #9477: DOC: `linalg`: fix `lstsq` docstring on residues shape
- #9478: DOC: Add docstring examples for rosen functions
- #9479: DOC: Add docstring example for `ai_zeros` and `bi_zeros`
- #9480: MAINT: `linalg`: `lstsq` clean up
- #9489: DOC: roadmap update for changes over the last year.
- #9492: MAINT: stats: Improve implementation of `chi2` ppf method.
- #9497: DOC: Improve docstrings `sparse.linalg.isolve`

- #9499: DOC: Replace “Scipy” with “SciPy” in the .rst doc files for consistency.
- #9500: DOC: Document the toolchain and its roadmap.
- #9505: DOC: specify which definition of skewness is used
- #9511: DEP: interpolate: remove deprecated interpolate_wrapper
- #9517: BUG: improve error handling in stats.iqr
- #9522: ENH: Add Fiedler and fiedler companion to special matrices
- #9526: TST: relax precision requirements in signal.correlate tests
- #9529: DOC: fix missing random seed in optimize.newton example
- #9533: MAINT: Use list comprehension when possible
- #9537: DOC: add a “big picture” roadmap
- #9538: DOC: Replace “Numpy” with “NumPy” in .py, .rst and .txt doc files...
- #9539: ENH: add two-sample test (Epps-Singleton) to scipy.stats
- #9559: DOC: add section on global optimizers to tutorial
- #9561: ENH: remove noprefix.h, change code appropriately
- #9562: MAINT: stats: Rewrite pearsonr.
- #9563: BUG: Minor bug fix Callback in linprog(method='simplex')
- #9568: MAINT: raise runtime error for newton with zeroder if disp true,...
- #9570: Correct docstring in show_options in optimize. Fixes #9407
- #9573: BUG fixes range of pk variable pre-check
- #9577: TST: fix minor issue in a signal.stft test.
- #9580: Included blank line before list - Fixes #8658
- #9582: MAINT: drop Python 2.7 and 3.4
- #9588: MAINT: update `constants.astronomical_unit` to new 2012 value.
- #9592: TST: Add 32-bit testing to CI
- #9593: DOC: Replace cumulative density with cumulative distribution
- #9596: TST: remove VC 9.0 from Azure CI
- #9599: Hyperlink DOI to preferred resolver
- #9601: DEV: try to limit GC memory use on PyPy
- #9603: MAINT: improve logcdf and logsf of hypergeometric distribution
- #9605: Reference to pylops in LinearOperator notes and ARPACK example
- #9617: TST: reduce max memory usage for sparse.linalg.lgmres test
- #9619: FIX: Sparse matrix addition/subtraction eliminates explicit zeros
- #9621: bugfix in rv_sample in scipy.stats
- #9622: MAINT: Raise error in directed_hausdorff distance
- #9623: DOC: Build docs with warnings as errors
- #9625: Return the number of calls to 'hessp' (not just 'hess') in trust...

- #9627: BUG: ignore empty lines in mmio
- #9637: Function to calculate the MAD of an array
- #9646: BUG: stats: mode for objects w/ndim > 1
- #9648: Add `stats.contingency` to refguide-check
- #9650: ENH: many lobpcg() algorithm improvements
- #9652: Move misc.doccer to `_lib.doccer`
- #9660: ENH: add pearson, tippett, and mudholkar-george to `combine_pvalues`
- #9661: BUG: Fix ksone right-hand endpoint, documentation and tests.
- #9664: ENH: adding multi-target dijkstra performance enhancement
- #9670: MAINT: link planck and geometric distribution in `scipy.stats`
- #9676: ENH: optimize: change default linprog method to interior-point
- #9685: Added reference to `ndimage.filters.median_filter`
- #9705: Fix coefficients in `expm` helper function
- #9711: Release the GIL during `sosfilt` processing for simple types
- #9721: ENH: Convexhull visiblefacets
- #9723: BLD: Modify `rv_generic._construct_doc` to print out failing distribution...
- #9726: BUG: Fix small issues with `signal.lfilter`
- #9729: BUG: Typecheck iterations for binary image operations
- #9730: ENH: reduce `sizeof(NI_WatershedElement)` by 20%
- #9731: ENH: remove suspicious sequence of type castings
- #9739: BUG: `qr_updates` fails if `u` is exactly in span `Q`
- #9749: BUG: `MapWrapper.__exit__` should terminate
- #9753: ENH: Added exact computation for Kolmogorov-Smirnov two-sample...
- #9755: DOC: Added example for `signal.impulse`, copied from `impulse2`
- #9756: DOC: Added docstring example for `iirdesign`
- #9757: DOC: Added examples for step functions
- #9759: ENH: Allow `pass_zero` to act like `btype`
- #9760: DOC: Added docstring for `lp2bs`
- #9761: DOC: Added docstring and example for `lp2bp`
- #9764: BUG: Catch internal warnings for `matrix`
- #9766: ENH: Speed up `_gaussian_kernel1d` by removing dependence on `np.polynomial`
- #9769: BUG: Fix Cubic Spline Read Only issues
- #9773: DOC: Several docstrings
- #9774: TST: bump Azure CI OpenBLAS version to match wheels
- #9775: DOC: Improve clarity of `cov_x` documentation for `scipy.optimize.leastsq`
- #9779: ENH: `dual_annealing` vectorise `visit_fn`

- #9788: TST, BUG: f2py-related issues with NumPy < 1.14.0
- #9791: BUG: fix amax constraint not enforced in scalar_search_wolfe2
- #9792: ENH: Allow inplace copying in place in “detrnd” function
- #9795: DOC: Fix/update docstring for dstn and dst
- #9796: MAINT: Allow None tolerances in least_squares
- #9798: BUG: fixes abort trap 6 error in scipy issue 9785 in unit tests
- #9807: MAINT: improve doc and add alternative keyword to wilcoxon in...
- #9808: Fix PPoly integrate and test for CubicSpline
- #9810: ENH: Add the geometric standard deviation function
- #9811: MAINT: remove invalid derphi default None value in scalar_search_wolfe2
- #9813: Adapt hamming distance in C to support weights
- #9817: DOC: Copy solver description to solver modules
- #9829: ENH: Add FOH and equivalent impulse response discretizations...
- #9831: ENH: Implement RotationSpline
- #9834: DOC: Change mielke distribution default parameters to ensure...
- #9838: ENH: Use faster solvers for firfs
- #9854: ENH: loadarff now supports relational attributes.
- #9856: integrate.bvp - improve handling of nonlinear boundary conditions
- #9862: TST: reduce Appveyor CI load
- #9874: DOC: Update requirements in release notes
- #9883: BUG: fixed parenthesis in spatial.rotation
- #9884: ENH: Use Sparsity in Clarkson-Woodruff Sketch
- #9888: MAINT: Replace NumPy aliased functions
- #9892: BUG: Fix 9890 query_ball_point returns wrong result when p is...
- #9893: BUG: curve_fit doesn't check for empty input if called with bounds
- #9894: scipy.signal.find_peaks documentation error
- #9898: BUG: Set success attribute in OptimizeResult. See #9801
- #9900: BUG: Restrict rv_generic._argcheck() and its overrides from setting...
- #9906: fixed a bug in kde logpdf
- #9911: DOC: replace example for “np.select” with the one from numpy...
- #9912: BF(DOC): point to numpy.select instead of plain (python) .select
- #9914: DOC: change ValueError message in _validate_pad of signaltools.
- #9915: cKDTree query_ball_point improvements
- #9918: Update ckdtree.pyx with boxsize argument in docstring
- #9920: BUG: sparse: Validate explicit shape if given with dense argument...
- #9924: BLD: add back pyproject.toml

- #9931: Fix empty constraint
- #9935: DOC: fix references for stats.f_oneway
- #9936: Revert gh-9619: “FIX: Sparse matrix addition/subtraction eliminates...
- #9937: MAINT: fix PEP8 issues and update to pycodestyle 2.5.0
- #9939: DOC: correct `structure` description in `ndimage.label` docstring
- #9940: MAINT: remove extraneous distutils copies
- #9945: ENH: differential_evolution can use Bounds object
- #9949: Added `std` to add docstrings since it is a `known_stats`...
- #9953: DOC: Documentation cleanup for stats tutorials.
- #9962: `__repr__` for Bounds
- #9971: ENH: Improve performance of lsqr
- #9987: CI: pin Sphinx version to 1.8.5
- #9990: ENH: constraint violation
- #9991: BUG: Avoid inplace modification of input array in newton
- #9995: MAINT: sparse.csgraph: Add cdef to stop build warning.
- #9996: BUG: Make minimize_quadratic_1d work with infinite bounds correctly
- #10004: BUG: Fix unbound local error in linprog - simplex.
- #10007: BLD: fix Python 3.7 build with build isolation
- #10009: BUG: Make sure that `_binary_erosion` only accepts an integer number...
- #10016: Update link to airspeed-velocity
- #10017: DOC: Update `interpolate.LSQSphereBivariateSpline` to include...
- #10018: MAINT: special: Fix a few warnings that occur when compiling...
- #10019: TST: Azure summarizes test failures
- #10021: ENH: Introduce CubicHermiteSpline
- #10022: BENCH: Increase cython version in asv to fix benchmark builds
- #10023: BUG: Avoid expnorm producing nan for small K values.
- #10025: BUG: optimize: tweaked linprog status 4 error message
- #10026: ENH: optimize: use SuiteSparse in linprog interior-point when...
- #10027: MAINT: cluster: clean up the use of malloc() in the function...
- #10028: Fix rotate invalid plane check
- #10040: MAINT: fix pratt method of wilcox test in scipy.stats
- #10041: MAINT: special: Fix a warning generated when building the AMOS...
- #10044: DOC: fix up spatial.transform.Rotation docstrings
- #10047: MAINT: interpolate: Fix a few build warnings.
- #10051: Add project_urls to setup
- #10052: don't set flag to “converged” if max iter exceeded

- #10054: MAINT: signal: Fix a few build warnings and modernize some C...
- #10056: BUG: Ensure factorial is not too large in kendaltau
- #10058: Small speedup in sampling from ortho and special_ortho groups
- #10059: BUG: optimize: fix #10038 by increasing tol
- #10061: BLD: DOC: make building docs easier by parsing python version.
- #10064: ENH: Significant speedup for ortho and special ortho group
- #10065: DOC: Reword parameter descriptions in `optimize.root_scalar`
- #10066: BUG: signal: Fix error raised by savgol_coeffs when deriv > polyorder.
- #10067: MAINT: Fix the cutoff value inconsistency for pinvh and pinvh
- #10072: BUG: stats: Fix boxcox_llf to avoid loss of precision.
- #10075: ENH: Add wrappers for ?syconv routines
- #10076: BUG: optimize: fix curve_fit for mixed float32/float64 input
- #10077: DOC: Replace undefined `k` in `interpolate.splev` docstring
- #10079: DOC: Fixed typo, rearranged some doc of stats.morestats.wilcoxon.
- #10080: TST: install scikit-sparse for full TravisCI tests
- #10083: Clean ``_clean_inputs`` in optimize.linprog
- #10088: ENH: optimize: linprog test CHOLMOD/UMFPACK solvers when available
- #10090: MAINT: Fix CubicSplineInterpolator for pandas
- #10091: MAINT: improve logcdf and logsf of hypergeometric distribution
- #10095: MAINT: Clean ``_clean_inputs`` in linprog
- #10116: MAINT: update scipy-sphinx-theme
- #10135: BUG: fix linprog revised simplex docstring problem failure

3.13 SciPy 1.2.3 Release Notes

Contents

- *SciPy 1.2.3 Release Notes*
 - *Authors*
 - * *Issues closed for 1.2.3*
 - * *Pull requests for 1.2.3*

SciPy 1.2.3 is a bug-fix release with no new features compared to 1.2.2. It is part of the long-term support (LTS) release series for Python 2.7.

3.13.1 Authors

- Geordie McBain
- Matt Haberland
- David Hagen
- Tyler Reddy
- Pauli Virtanen
- Eric Larson
- Yu Feng
- ananyashreyjain
- Nikolay Mayorov
- Evgeni Burovski
- Warren Weckesser

Issues closed for 1.2.3

- #4915: Bug in `unique_roots` in `scipy.signal.signaltools.py` for roots with same magnitude
- #5546: `ValueError` raised if `scipy.sparse.linalg.expm` receives array larger than 200x200
- #7117: Warn users when using `float32` input data to `curve_fit` and friends
- #7906: Wrong result from `scipy.interpolate.UnivariateSpline.integral` for out-of-bounds
- #9581: Least-squares minimization fails silently when `x` and `y` data are different types
- #9901: `lsoda` fails to detect stiff problem when called from `solve_ivp`
- #9988: doc build broken with Sphinx 2.0.0
- #10303: BUG: optimize: `linprog` failing `TestLinprogSimplexBland::test_unbounded_below_no_presolve_corrected`
- #10376: TST: Travis CI fails (with `pytest 5.0` ?)
- #10384: CircleCI doc build failing on new warnings
- #10535: TST: master branch CI failures
- #11121: Calls to `scipy.interpolate.splprep` increase RAM usage.
- #11198: BUG: sparse eigs (arpack) shift-invert drops the smallest eigenvalue for some `k`
- #11266: Sparse matrix constructor data type detection changes on Numpy 1.18.0

Pull requests for 1.2.3

- #9992: MAINT: Undo Sphinx pin
- #10071: DOC: reconstruct SuperLU permutation matrices avoiding SparseEfficiencyWarning
- #10076: BUG: optimize: fix curve_fit for mixed float32/float64 input
- #10138: BUG: special: Invalid arguments to ellip_harm can crash Python.
- #10306: BUG: optimize: Fix for 10303
- #10309: BUG: Pass jac=None directly to lsoda
- #10377: TST, MAINT: adjustments for pytest 5.0
- #10379: BUG: sparse: set writeability to be forward-compatible with numpy>=1.17
- #10426: MAINT: Fix doc build bugs
- #10540: MAINT: Fix Travis and Circle
- #10633: BUG: interpolate: integral(a, b) should be zero when both limits are outside of the interpolation range
- #10833: BUG: Fix subspace_angles for complex values
- #10882: BUG: sparse/arpack: fix incorrect code for complex hermitian M
- #10906: BUG: sparse/linalg: fix expm for np.matrix inputs
- #10961: BUG: Fix signal.unique_roots
- #11126: BUG: interpolate/fitpack: fix memory leak in splprep
- #11199: BUG: sparse.linalg: mistake in unsymm. real shift-invert ARPACK eigenvalue selection
- #11269: Fix: Sparse matrix constructor data type detection changes on Numpy 1.18.0

3.14 SciPy 1.2.2 Release Notes

Contents

- *SciPy 1.2.2 Release Notes*
 - *Authors*
 - * *Issues closed for 1.2.2*
 - * *Pull requests for 1.2.2*

SciPy 1.2.2 is a bug-fix release with no new features compared to 1.2.1. Importantly, the SciPy 1.2.2 wheels are built with OpenBLAS 0.3.7.dev to alleviate issues with SkylakeX AVX512 kernels.

3.14.1 Authors

- CJ Carey
- Tyler Dawson +
- Ralf Gommers
- Kai Striega
- Andrew Nelson
- Tyler Reddy
- Kevin Sheppard +

A total of 7 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 1.2.2

- #9611: Overflow error with new way of p-value calculation in kendall tau correlation for perfectly monotonic vectors
- #9964: optimize.newton : overwrites x0 argument when it is a numpy array
- #9784: TST: Minimum NumPy version is not being CI tested
- #10132: Docs: Description of nnz attribute of sparse.csc_matrix misleading

Pull requests for 1.2.2

- #10056: BUG: Ensure factorial is not too large in kendaltau
- #9991: BUG: Avoid inplace modification of input array in newton
- #9788: TST, BUG: f2py-related issues with NumPy < 1.14.0
- #9749: BUG: MapWrapper.__exit__ should terminate
- #10141: Update description for nnz on csc.py

3.15 SciPy 1.2.1 Release Notes

Contents

- *SciPy 1.2.1 Release Notes*
 - *Authors*
 - * *Issues closed for 1.2.1*
 - * *Pull requests for 1.2.1*

SciPy 1.2.1 is a bug-fix release with no new features compared to 1.2.0. Most importantly, it solves the issue that 1.2.0 cannot be installed from source on Python 2.7 because of non-ascii character issues.

It is also notable that SciPy 1.2.1 wheels were built with OpenBLAS 0.3.5.dev, which may alleviate some linear algebra issues observed in SciPy 1.2.0.

3.15.1 Authors

- Eric Larson
- Mark Mikofski
- Evgeni Burovski
- Ralf Gommers
- Eric Moore
- Tyler Reddy

Issues closed for 1.2.1

- #9606: SyntaxError: Non-ASCII character 'xe2' in file scipy/stats/_continuous_distns.py on line 3346, but no encoding declared
- #9608: Version 1.2.0 introduces *too many indices for array* error in...
- #9709: scipy.stats.gaussian_kde normalizes the weights keyword argument...
- #9733: scipy.linalg.qr_update gives NaN result
- #9724: CI: Is scipy.scipy Windows Python36-32bit-full working?

Pull requests for 1.2.1

- #9612: BUG: don't use array newton unless size is greater than 1
- #9615: ENH: Add test for encoding
- #9720: BUG: stats: weighted KDE does not modify the weights array
- #9739: BUG: qr_updates fails if u is exactly in span Q
- #9725: TST: pin mingw for Azure Win CI
- #9736: TST: adjust to vmImage dispatch in Azure
- #9681: BUG: Fix failing stats tests (partial backport)
- #9662: TST: interpolate: avoid pytest deprecations

3.16 SciPy 1.2.0 Release Notes

Contents

- *SciPy 1.2.0 Release Notes*
 - *Highlights of this release*
 - *New features*

- * `scipy.ndimage` *improvements*
- * `scipy.fftpack` *improvements*
- * `scipy.interpolate` *improvements*
- * `scipy.cluster` *improvements*
- * `scipy.special` *improvements*
- * `scipy.optimize` *improvements*
- * `scipy.signal` *improvements*
- * `scipy.sparse` *improvements*
- * `scipy.spatial` *improvements*
- * `scipy.stats` *improvements*
- * `scipy.linalg` *improvements*
- *Deprecated features*
- *Backwards-incompatible changes*
- *Authors*
 - * *Issues closed for 1.2.0*
 - * *Pull requests for 1.2.0*

SciPy 1.2.0 is the culmination of 6 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Before upgrading, we recommend that users check that their own code does not use deprecated SciPy functionality (to do so, run your code with `python -Wd` and check for `DeprecationWarnings`). Our development attention will now shift to bug-fix releases on the 1.2.x branch, and on adding new features on the master branch.

This release requires Python 2.7 or 3.4+ and NumPy 1.8.2 or greater.

Note: This will be the last SciPy release to support Python 2.7. Consequently, the 1.2.x series will be a long term support (LTS) release; we will backport bug-fixes until 1 Jan 2020.

For running on PyPy, PyPy3 6.0+ and NumPy 1.15.0 are required.

3.16.1 Highlights of this release

- 1-D root finding improvements with a new solver, `toms748`, and a new unified interface, `root_scalar`
- new `dual_annealing` optimization method that combines stochastic and local deterministic searching
- a new optimization algorithm, `shgo` (simplicial homology global optimization), for derivative-free optimization problems
- a new category of quaternion-based transformations are available in `scipy.spatial.transform`

3.16.2 New features

`scipy.ndimage` improvements

Proper spline coefficient calculations have been added for the `mirror`, `wrap`, and `reflect` modes of `scipy.ndimage.rotate`.

`scipy.fftpack` improvements

DCT-IV, DST-IV, DCT-I, and DST-I orthonormalization are now supported in `scipy.fftpack`.

`scipy.interpolate` improvements

`scipy.interpolate.pade` now accepts a new argument for the order of the numerator.

`scipy.cluster` improvements

`scipy.cluster.vq.kmeans2` gained a new initialization method, `kmeans++`.

`scipy.special` improvements

The function `softmax` was added to `scipy.special`.

`scipy.optimize` improvements

The one-dimensional nonlinear solvers have been given a unified interface `scipy.optimize.root_scalar`, similar to the `scipy.optimize.root` interface for multi-dimensional solvers. `scipy.optimize.root_scalar(f, bracket=[a, b], method="brenth")` is equivalent to `scipy.optimize.brenth(f, a, b)`. If no method is specified, an appropriate one will be selected based upon the bracket and the number of derivatives available.

The so-called Algorithm 748 of Alefeld, Potra and Shi for root-finding within an enclosing interval has been added as `scipy.optimize.toms748`. This provides guaranteed convergence to a root with convergence rate per function evaluation of approximately 1.65 (for sufficiently well-behaved functions).

`differential_evolution` now has the `updating` and `workers` keywords. The first chooses between continuous updating of the best solution vector (the default), or once per generation. Continuous updating can lead to faster convergence. The `workers` keyword accepts an `int` or map-like callable, and parallelises the solver (having the side effect of updating once per generation). Supplying an `int` evaluates the trial solutions in `N` parallel parts. Supplying a map-like callable allows other parallelisation approaches (such as `mpi4py`, or `joblib`) to be used.

`dual_annealing` (and `shgo` below) is a powerful new general-purpose global optimization (GO) algorithm. `dual_annealing` uses two annealing processes to accelerate the convergence towards the global minimum of an objective mathematical function. The first annealing process controls the stochastic Markov chain searching and the second annealing process controls the deterministic minimization. So, dual annealing is a hybrid method that takes advantage of stochastic and local deterministic searching in an efficient way.

`shgo` (simplicial homology global optimization) is a similar algorithm appropriate for solving black box and derivative-free optimization (DFO) problems. The algorithm generally converges to the global solution in finite time. The convergence holds for non-linear inequality and equality constraints. In addition to returning a global minimum, the algorithm also returns any other global and local minima found after every iteration. This makes it useful for exploring the solutions in a domain.

`scipy.optimize.newton` can now accept a scalar or an array.

MINPACK usage is now thread-safe, such that MINPACK + callbacks may be used on multiple threads.

scipy.signal improvements

Digital filter design functions now include a parameter to specify the sampling rate. Previously, digital filters could only be specified using normalized frequency, but different functions used different scales (e.g. 0 to 1 for `butter` vs 0 to π for `freqz`), leading to errors and confusion. With the `fs` parameter, ordinary frequencies can now be entered directly into functions, with the normalization handled internally.

`find_peaks` and related functions no longer raise an exception if the properties of a peak have unexpected values (e.g. a prominence of 0). A `PeakPropertyWarning` is given instead.

The new keyword argument `plateau_size` was added to `find_peaks`. `plateau_size` may be used to select peaks based on the length of the flat top of a peak.

`welch()` and `csd()` methods in `scipy.signal` now support calculation of a median average PSD, using `average='mean'` keyword.

scipy.sparse improvements

The `scipy.sparse.bsr_matrix.tocsr` method is now implemented directly instead of converting via COO format, and the `scipy.sparse.bsr_matrix.tocsc` method is now also routed via CSR conversion instead of COO. The efficiency of both conversions is now improved.

The issue where SuperLU or UMFPACK solvers crashed on matrices with non-canonical format in `scipy.sparse.linalg` was fixed. The solver wrapper canonicalizes the matrix if necessary before calling the SuperLU or UMFPACK solver.

The `largest` option of `scipy.sparse.linalg.lobpcg()` was fixed to have a correct (and expected) behavior. The order of the eigenvalues was made consistent with the ARPACK solver (`eigs()`), i.e. ascending for the smallest eigenvalues, and descending for the largest eigenvalues.

The `scipy.sparse.random` function is now faster and also supports integer and complex values by passing the appropriate value to the `dtype` argument.

scipy.spatial improvements

The function `scipy.spatial.distance.jaccard` was modified to return 0 instead of `np.nan` when two all-zero vectors are compared.

Support for the Jensen Shannon distance, the square-root of the divergence, has been added under `scipy.spatial.distance.jensenshannon`.

An optional keyword was added to the function `scipy.spatial.cKDTree.query_ball_point()` to sort or not sort the returned indices. Not sorting the indices can speed up calls.

A new category of quaternion-based transformations are available in `scipy.spatial.transform`, including spherical linear interpolation of rotations (`Slerp`), conversions to and from quaternions, Euler angles, and general rotation and inversion capabilities (`spatial.transform.Rotation`), and uniform random sampling of 3D rotations (`spatial.transform.Rotation.random`).

scipy.stats improvements

The Yeo-Johnson power transformation is now supported (`yeojohnson`, `yeojohnson_llf`, `yeojohnson_normmax`, `yeojohnson_normplot`). Unlike the Box-Cox transformation, the Yeo-Johnson transformation can accept negative values.

Added a general method to sample random variates based on the density only, in the new function `rvs_ratio_uniforms`.

The Yule-Simon distribution (`yulesimon`) was added – this is a new discrete probability distribution.

`stats` and `mstats` now have access to a new regression method, `siegelslopes`, a robust linear regression algorithm. `scipy.stats.gaussian_kde` now has the ability to deal with weighted samples, and should have a modest improvement in performance.

Levy Stable Parameter Estimation, PDF, and CDF calculations are now supported for `scipy.stats.levy_stable`.

The Brunner-Munzel test is now available as `brunnermunzel` in `stats` and `mstats`.

scipy.linalg improvements

`scipy.linalg.lapack` now exposes the LAPACK routines using the Rectangular Full Packed storage (RFP) for upper triangular, lower triangular, symmetric, or Hermitian matrices; the upper trapezoidal fat matrix RZ decomposition routines are now available as well.

3.16.3 Deprecated features

The functions `hyp2f0`, `hyp1f2` and `hyp3f0` in `scipy.special` have been deprecated.

3.16.4 Backwards-incompatible changes

LAPACK version 3.4.0 or later is now required. Building with Apple Accelerate is no longer supported.

The function `scipy.linalg.subspace_angles(A, B)` now gives correct results for all angles. Before this, the function only returned correct values for those angles which were greater than $\pi/4$.

Support for the Bento build system has been removed. Bento had not been maintained for several years, and did not have good Python 3 or wheel support, hence it was time to remove it.

The required signature of `scipy.optimize.lingprog` `method=simplex` callback function has changed. Before iteration begins, the simplex solver first converts the problem into a standard form that does not, in general, have the same variables or constraints as the problem defined by the user. Previously, the simplex solver would pass a user-specified callback function several separate arguments, such as the current solution vector `xk`, corresponding to this standard-form problem. Unfortunately, the relationship between the standard-form problem and the user-defined problem was not documented, limiting the utility of the information passed to the callback function.

In addition to numerous bug-fix changes, the simplex solver now passes a user-specified callback function a single `OptimizeResult` object containing information that corresponds directly to the user-defined problem. In future releases, this `OptimizeResult` object may be expanded to include additional information, such as variables corresponding to the standard-form problem and information concerning the relationship between the standard-form and user-defined problems.

The implementation of `scipy.sparse.random` has changed, and this affects the numerical values returned for both `sparse.random` and `sparse.rand` for some matrix shapes and a given seed.

`scipy.optimize.newton` will no longer use Halley's method in cases where it negatively impacts convergence.

3.16.5 Authors

- @endolith
- @luzpaz
- Hameer Abbasi +
- akahard2dj +
- Anton Akhmerov
- Joseph Albert
- alexthomas93 +
- ashish +
- atpage +
- Blair Azzopardi +
- Yoshiki Vázquez Baeza
- Bence Bagi +
- Christoph Baumgarten
- Lucas Bellomo +
- BH4 +
- Aditya Bharti
- Max Bolingbroke
- François Boulogne
- Ward Bradt +
- Matthew Brett
- Evgeni Burovski
- Rafał Byczek +
- Alfredo Canziani +
- CJ Carey
- Lucía Cheung +
- Poom Chiarawongse +
- Jeanne Choo +
- Robert Cimrman
- Graham Clenaghan +
- cynthia-rempel +
- Johannes Damp +
- Jaime Fernandez del Rio
- Dowon +
- emmi474 +
- Stefan Endres +

- Thomas Etherington +
- Piotr Figiel
- Alex Fikl +
- fo40225 +
- Joseph Fox-Rabinovitz
- Lars G
- Abhinav Gautam +
- Stiaan Gerber +
- C.A.M. Gerlach +
- Ralf Gommers
- Todd Goodall
- Lars Grueter +
- Sylvain Gubian +
- Matt Haberland
- David Hagen
- Will Handley +
- Charles Harris
- Ian Henriksen
- Thomas Hisch +
- Theodore Hu
- Michael Hudson-Doyle +
- Nicolas Hug +
- jakirkham +
- Jakob Jakobson +
- James +
- Jan Schlüter
- jeanpauphilet +
- josephmernst +
- Kai +
- Kai-Striega +
- kalash04 +
- Toshiki Kataoka +
- Konrad0 +
- Tom Krauss +
- Johannes Kulick
- Lars Grüter +

- Eric Larson
- Denis Laxalde
- Will Lee +
- Katrin Leinweber +
- Yin Li +
- P. L. Lim +
- Jesse Livezey +
- Duncan Macleod +
- MatthewFlamm +
- Nikolay Mayorov
- Mike McClurg +
- Christian Meyer +
- Mark Mikofski
- Naoto Mizuno +
- mohmmadd +
- Nathan Musoke
- Anju Geetha Nair +
- Andrew Nelson
- Ayappan P +
- Nick Papior
- Haesun Park +
- Ronny Pfannschmidt +
- pijyoi +
- Ilhan Polat
- Anthony Polloreno +
- Ted Pudlik
- puenka
- Eric Quintero
- Pradeep Reddy Raamana +
- Vyas Ramasubramani +
- Ramon Viñas +
- Tyler Reddy
- Joscha Reimer
- Antonio H Ribeiro
- richardjgowers +
- Rob +

- robbystk +
- Lucas Roberts +
- rohan +
- Joaquin Derrac Rus +
- Josua Sassen +
- Bruce Sharpe +
- Max Shinn +
- Scott Sievert
- Sourav Singh
- Strahinja Lukić +
- Kai Striega +
- Shinya SUZUKI +
- Mike Toews +
- Piotr Uchwat
- Miguel de Val-Borro +
- Nicky van Foreest
- Paul van Mulbregt
- Gael Varoquaux
- Pauli Virtanen
- Stefan van der Walt
- Warren Weckesser
- Joshua Wharton +
- Bernhard M. Wiedemann +
- Eric Wieser
- Josh Wilson
- Tony Xiang +
- Roman Yurchak +
- Roy Zywina +

A total of 137 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 1.2.0

- #9520: `signal.correlate` with `method='fft'` doesn't benefit from long...
- #9547: signature of `dual_annealing` doesn't match other optimizers
- #9540: SciPy v1.2.0rc1 cannot be imported on Python 2.7.15
- #1240: Allowing multithreaded use of minpack through `scipy.optimize...`
- #1432: `scipy.stats.mode` extremely slow (Trac #905)
- #3372: Please add Sphinx search field to online scipy html docs
- #3678: `_clough_tocher_2d_single` direction between centroids
- #4174: `lobpcg` "largest" option invalid?
- #5493: `anderson_ksamp` p-values>1
- #5743: `slsqp` fails to detect infeasible problem
- #6139: `scipy.optimize.linprog` failed to find a feasible starting point...
- #6358: stats: docstring for `vonmises_line` points to `vonmises_line...`
- #6498: `runtests.py` is missing in pypi distfile
- #7426: `scipy.stats.ksone(n).pdf(x)` returns nan for positive values of...
- #7455: `scipy.stats.ksone.pdf(2,x)` return incorrect values for x near...
- #7456: `scipy.special.smirnov` and `scipy.special.smirnovi` have accuracy...
- #7492: `scipy.special.kolmogorov(x)/kolmogi(p)` inefficient, inaccurate...
- #7914: TravisCI not failing when it should for -OO run
- #8064: `linalg.solve` test crashes on Windows
- #8212: LAPACK Rectangular Full Packed routines
- #8256: `differential_evolution` bug converges to wrong results in complex...
- #8443: Deprecate `hyp2f0`, `hyp1f2`, and `hyp3f0`?
- #8452: DOC: ARPACK tutorial has two conflicting equations
- #8680: scipy fails compilation when building from source
- #8686: Division by zero in `_trustregion.py` when `x0` is exactly equal...
- #8700: `_MINPACK_LOCK` not held when calling into minpack from `least_squares`
- #8786: erroneous moment values for t-distribution
- #8791: Checking COLA condition in `istft` should be optional (or omitted)
- #8843: `imresize` cannot be deprecated just yet
- #8844: Inverse Wishart Log PDF Incorrect for Non-diagonal Scale Matrix?
- #8878: `vonmises` and `vonmises_line` in stats: `vonmises` wrong and superfluous?
- #8895: v1.1.0 `ndi.rotate` documentation – reused parameters not filled...
- #8900: Missing complex conjugation in `scipy.sparse.linalg.LinearOperator`
- #8904: BUG: if zero derivative at root, then Newton fails with `RuntimeWarning`
- #8911: `make_interp_spline` `bc_type` incorrect input interpretation

- #8942: MAINT: Refactor `_linprog.py` and `_linprog_ip.py` to remove...
- #8947: `np.int64` in `scipy.fftpack.next_fast_len`
- #9020: BUG: `linalg.subspace_angles` gives wrong results
- #9033: `scipy.stats.normaltest` sometimes gives incorrect returns b/c...
- #9036: Bizarre times for `scipy.sparse.rand` function with 'low' density...
- #9044: `optimize.minimize(method='trust-constr')` result dict does not...
- #9071: doc/linalg: add `cho_solve_banded` to see also of `cholesky_banded`
- #9082: eigenvalue sorting in `scipy.sparse.linalg.eigsh`
- #9086: `signaltools.py:491: FutureWarning: Using a non-tuple sequence...`
- #9091: `test_spline_filter` failure on 32-bit
- #9122: Typo on scipy minimization tutorial
- #9135: doc error at https://docs.scipy.org/doc/scipy/reference/tutorial/stats/discrete_poisson.html
- #9167: DOC: BUG: typo in `ndimage.LowLevelCallable` tutorial example
- #9169: `truncnorm` does not work if `b < a` in `scipy.stats`
- #9250: `scipy.special.tests.test_mpmath::TestSystematic::test_pcfw` fails...
- #9259: `rv.expect() == rv.mean()` is false for `rv.mean() == nan` (and `inf`)
- #9286: DOC: Rosenbrock expression in `optimize.minimize` tutorial
- #9316: SLSQP fails in nested optimization
- #9337: `scipy.signal.find_peaks` key typo in documentation
- #9345: Example from documentation of `scipy.sparse.linalg.eigs` raises...
- #9383: Default value for "mode" in "`ndimage.shift`"
- #9419: `dual_annealing` off by one in the number of iterations
- #9442: Error in Definition of Rosenbrock Function
- #9453: TST: `test_eigs_consistency()` doesn't have consistent results

Pull requests for 1.2.0

- #9526: TST: relax precision requirements in `signal.correlate` tests
- #9507: CI: MAINT: Skip a `ckdtree` test on pypy
- #9512: TST: `test_random_sampling` 32-bit handling
- #9494: TST: `test_kolmogorov_xfail` 32-bit
- #9486: BUG: fix sparse random int handling
- #9550: BUG: `scipy/_lib/_numpy_compat: get_randint`
- #9549: MAINT: make `dual_annealing` signature match other optimizers
- #9541: BUG: fix `SyntaxError` due to non-ascii character on Python 2.7
- #7352: ENH: add Brunner Munzel test to `scipy.stats`.
- #7373: BUG: Jaccard distance for all-zero arrays would return `np.nan`

- #7374: ENH: Add PDF, CDF and parameter estimation for Stable Distributions
- #8098: ENH: Add shgo for global optimization of NLPs.
- #8203: ENH: adding simulated dual annealing to optimize
- #8259: Option to follow original Storn and Price algorithm and its parallelisation
- #8293: ENH add ratio-of-uniforms method for rv generation to `scipy.stats`
- #8294: BUG: Fix slowness in `stats.mode`
- #8295: ENH: add Jensen Shannon distance to `scipy.spatial.distance`
- #8357: ENH: vectorize scalar zero-search-functions
- #8397: Add `fs=` parameter to filter design functions
- #8537: ENH: Implement mode parameter for spline filtering.
- #8558: ENH: small speedup for `stats.gaussian_kde`
- #8560: BUG: fix p-value calc of `anderson_ksamp` in `scipy.stats`
- #8614: ENH: correct p-values for `stats.kendalltau` and `stats.mstats.kendalltau`
- #8670: ENH: Require Lapack 3.4.0
- #8683: Correcting kmeans documentation
- #8725: MAINT: Cleanup `scipy.optimize.leastsq`
- #8726: BUG: Fix `_get_output` in `scipy.ndimage` to support string
- #8733: MAINT: stats: A bit of clean up.
- #8737: BUG: Improve numerical precision/convergence failures of `smirnov/kolmogorov`
- #8738: MAINT: stats: A bit of clean up in `test_distributions.py`.
- #8740: BF/ENH: make minpack thread safe
- #8742: BUG: Fix division by zero in trust-region optimization methods
- #8746: MAINT: signal: Fix a docstring of a private function, and fix...
- #8750: DOC clarified description of `norminvgauss` in `scipy.stats`
- #8753: DOC: signal: Fix a plot title in the `chirp` docstring.
- #8755: DOC: MAINT: Fix link to the `wheel` documentation in `developer...`
- #8760: BUG: stats: `boltzmann` wasn't setting the upper bound.
- #8763: [DOC] Improved `scipy.cluster.hierarchy` documentation
- #8765: DOC: added example for `scipy.stat.mstats.tmin`
- #8788: DOC: fix definition of optional `disp` parameter
- #8802: MAINT: Suppress `dd_real` unused function compiler warnings.
- #8803: ENH: Add `full_output` support to `optimize.newton()`
- #8804: MAINT: stats cleanup
- #8808: DOC: add note about `isinstance` for frozen rvs
- #8812: Updated `numpydoc` submodule
- #8813: MAINT: stats: Fix multinomial docstrings, and do some clean up.

- #8816: BUG: fixed `_stats` of t-distribution in `scipy.stats`
- #8817: BUG: `ndimage`: Fix validation of the origin argument in `correlate...`
- #8822: BUG: `integrate`: Fix crash with repeated t values in `odeint`.
- #8832: Hyperlink DOIs against preferred resolver
- #8837: BUG: `sparse`: Ensure correct dtype for sparse comparison operations.
- #8839: DOC: `stats`: A few tweaks to the `linregress` docstring.
- #8846: BUG: `stats`: Fix `logpdf` method of `invwishart`.
- #8849: DOC: `signal`: Fixed mistake in the `firwin` docstring.
- #8854: DOC: fix type descriptors in `ltisys` documentation
- #8865: Fix tiny typo in docs for `chi2` pdf
- #8870: Fixes related to invertibility of STFT
- #8872: ENH: `special`: Add the softmax function
- #8874: DOC correct gamma function in docstrings in `scipy.stats`
- #8876: ENH: Added TOMS Algorithm 748 as 1-d root finder; 17 test function...
- #8882: ENH: Only use Halley's adjustment to Newton if close enough.
- #8883: FIX: `optimize`: make `jac` and `hess` truly optional for 'trust-constr'
- #8885: TST: Do not error on warnings raised about non-tuple indexing.
- #8887: MAINT: filter out `np.matrix PendingDeprecationWarning`'s in `numpy...`
- #8889: DOC: `optimize`: separate legacy interfaces from new ones
- #8890: ENH: Add `optimize.root_scalar()` as a universal dispatcher for...
- #8899: DCT-IV, DST-IV and DCT-I, DST-I orthonormalization support in...
- #8901: MAINT: Reorganize `flapack.pyf.src` file
- #8907: BUG: ENH: Check if guess for newton is already zero before checking...
- #8908: ENH: Make sorting optional for `cKDTree.query_ball_point()`
- #8910: DOC: `sparse.csrgraph` simple examples.
- #8914: DOC: `interpolate`: fix equivalences of string aliases
- #8918: add `float_control(precise, on)` to `_fpumode.c`
- #8919: MAINT: `interpolate`: improve error messages for common `bc_type...`
- #8920: DOC: update Contributing to SciPy to say "prefer no PEP8 only..."
- #8924: MAINT: `special`: deprecate `hyp2f0`, `hyp1f2`, and `hyp3f0`
- #8927: MAINT: `special`: remove `errprint`
- #8932: Fix broadcasting scale arg of `entropy`
- #8936: Fix (some) non-tuple index warnings
- #8937: ENH: implement sparse matrix BSR to CSR conversion directly.
- #8938: DOC: add `@_ni_docstrings.docfiller` in `ndimage.rotate`
- #8940: Update `_discrete_distns.py`

- #8943: DOC: Finish dangling sentence in *convolve* docstring
- #8944: MAINT: Address tuple indexing and warnings
- #8945: ENH: `spatial.transform.Rotation` [GSOC2018]
- #8950: `csgraph` Dijkstra function description rewording
- #8953: DOC, MAINT: HTTP -> HTTPS, and other linkrot fixes
- #8955: BUG: `np.int64` in `scipy.fftpack.next_fast_len`
- #8958: MAINT: Add more descriptive error message for phase one simplex.
- #8962: BUG: `sparse.linalg`: add missing conjugate to `_ScaledLinearOperator.adjoint`
- #8963: BUG: `sparse.linalg`: downgrade `LinearOperator` `TypeError` to warning
- #8965: ENH: Wrapped RFP format and RZ decomposition routines
- #8969: MAINT: doc and code fixes for `optimize.newton`
- #8970: Added 'average' keyword for `welch/csd` to enable median averaging
- #8971: Better `imresize` deprecation warning
- #8972: MAINT: Switch `np.where(c)` for `np.nonzero(c)`
- #8975: MAINT: Fix warning-based failures
- #8979: DOC: fix description of `count_sort` keyword of `dendrogram`
- #8982: MAINT: `optimize`: Fixed minor mistakes in `test_linprog.py` (#8978)
- #8984: BUG: `sparse.linalg`: ensure `expm` casts integer inputs to float
- #8986: BUG: `optimize/slsqp`: do not exit with convergence on steps where...
- #8989: MAINT: use `collections.abc` in `basinhopping`
- #8990: ENH extend p-values of `anderson_ksamp` in `scipy.stats`
- #8991: ENH: Weighted kde
- #8993: ENH: `spatial.transform.Rotation.random` [GSOC 2018]
- #8994: ENH: `spatial.transform.Slerp` [GSOC 2018]
- #8995: TST: `time.time` in test
- #9007: Fix typo in `fftpack.rst`
- #9013: Added correct plotting code for two sided output from spectrogram
- #9014: BUG: `differential_evolution` with `inf` objective functions
- #9017: BUG: fixed #8446 corner case for `asformat(array/dense)`
- #9018: MAINT: `_lib/ccallback`: remove unused code
- #9021: BUG: Issue with `subspace_angles`
- #9022: DOC: Added "See Also" section to `lombscargle` docstring
- #9034: BUG: Fix tolerance printing behavior, remove meaningless tol...
- #9035: TST: improve `signal.bsplines` test coverage
- #9037: ENH: add a new `init` method for k-means
- #9039: DOC: Add examples to `fftpack.irfft` docstrings

- #9048: ENH: `scipy.sparse.random`
- #9050: BUG: `scipy.io.hb_write`: fails for matrices not in csc format
- #9051: MAINT: Fix slow `sparse.rand` for $k < mn/3$ (#9036).
- #9054: MAINT: `spatial`: Explicitly initialize LAPACK output parameters.
- #9055: DOC: Add examples to `scipy.special` docstrings
- #9056: ENH: Use one thread in OpenBLAS
- #9059: DOC: Update README with link to Code of Conduct
- #9060: BLD: remove support for the Bento build system.
- #9062: DOC add sections to overview in `scipy.stats`
- #9066: BUG: Correct “remez” error message
- #9069: DOC: update `linalg` section of roadmap for LAPACK versions.
- #9079: MAINT: add `spatial.transform` to `refguide` check; complete some...
- #9081: MAINT: Add warnings if pivot value is close to tolerance in `linprog(method='simplex')`
- #9084: BUG fix incorrect p-values of `kurtosistest` in `scipy.stats`
- #9095: DOC: add sections to `mstats` overview in `scipy.stats`
- #9096: BUG: Add test for Stackoverflow example from issue 8174.
- #9101: ENH: add Siegel slopes (robust regression) to `scipy.stats`
- #9105: allow `resample_poly()` to output float32 for float32 inputs.
- #9112: MAINT: optimize: make `trust-constr` accept constraint dict (#9043)
- #9118: Add doc entry to `cholesky_banded`
- #9120: `eigsh` documentation parameters
- #9125: `interpolative`: correctly reconstruct full rank matrices
- #9126: MAINT: Use warnings for unexpected peak properties
- #9129: BUG: Do not catch and silence `KeyboardInterrupt`
- #9131: DOC: Correct the typo in `scipy.optimize` tutorial page
- #9133: FIX: Avoid use of bare `except`
- #9134: DOC: Update of ‘`return_eigenvectors`’ description
- #9137: DOC: typo fixes for discrete Poisson tutorial
- #9139: FIX: Doctest failure in `optimize` tutorial
- #9143: DOC: missing `sigma` in Pearson r formula
- #9145: MAINT: Refactor linear programming solvers
- #9149: FIX: Make `scipy.odr.ODR` `ifixx` equal to its `data.fix` if given
- #9156: DOC: `special`: Mention the sigmoid function in the `expit` docstring.
- #9160: Fixed a latex delimiter error in `levy()`
- #9170: DOC: correction / update of docstrings of distributions in `scipy.stats`
- #9171: better description of the hierarchical clustering parameter

- #9174: domain check for $a < b$ in `stats.truncnorm`
- #9175: DOC: Minor grammar fix
- #9176: BUG: `CloughTocher2DInterpolator`: fix miscalculation at `neighborless...`
- #9177: BUILD: Document the “clean” target in the `doc/Makefile`.
- #9178: MAINT: make `refguide-check` more robust for printed numpy arrays
- #9186: MAINT: Remove `np.ediff1d` occurrence
- #9188: DOC: correct typo in extending `ndimage` with C
- #9190: ENH: Support specifying axes for `fftconvolve`
- #9192: MAINT: optimize: fixed `@pv` style suggestions from #9112
- #9200: Fix `make_interp_spline(..., k=0 or 1, axis<0)`
- #9201: BUG: `sparse.linalg/gmres`: use machine eps in breakdown check
- #9204: MAINT: fix up `stats.spearmanr` and match `mstats.spearmanr` with...
- #9206: MAINT: include benchmarks and dev files in `sdist`.
- #9208: TST: signal: bump bsplines test tolerance for complex data
- #9210: TST: mark tests as slow, fix missing random seed
- #9211: ENH: add capability to specify orders in `pade` func
- #9217: MAINT: Include `success` and `nit` in `OptimizeResult` returned...
- #9222: ENH: interpolate: Use `scipy.spatial.distance` to speed-up `Rbf`
- #9229: MNT: Fix Fourier filter double case
- #9233: BUG: `spatial/distance`: fix `pdist/cdist` performance regression...
- #9234: FIX: Proper suppression
- #9235: BENCH: rationalize slow benchmarks + miscellaneous fixes
- #9238: BENCH: limit number of parameter combinations in `spatial.*KDTree...`
- #9239: DOC: stats: Fix LaTeX markup of a couple distribution PDFs.
- #9241: ENH: Evaluate plateau size during peak finding
- #9242: ENH: stats: Implement `_ppf` and `_logpdf` for `crystalball`, and do...
- #9246: DOC: Properly render `versionadded` directive in HTML documentation
- #9255: DOC: mention `RootResults` in optimization reference guide
- #9260: TST: relax some tolerances so tests pass with x87 math
- #9264: TST Use `assert_raises` “match” parameter instead of the “message”...
- #9267: DOC: clarify `expect()` return val when moment is `inf/nan`
- #9272: DOC: Add description of default bounds to `linprog`
- #9277: MAINT: `sparse/linalg`: make test deterministic
- #9278: MAINT: interpolate: pep8 cleanup in `test_polyint`
- #9279: Fixed docstring for `resample`
- #9280: removed first check for float in `get_sum_dtype`

- #9281: BUG: only accept 1d input for bartlett / levene in scipy.stats
- #9282: MAINT: dense_output and t_eval are mutually exclusive inputs
- #9283: MAINT: add docs and do some cleanups in interpolate.Rbf
- #9288: Run distance_transform_edt tests on all types
- #9294: DOC: fix the formula typo
- #9298: MAINT: optimize/trust-constr: restore .niter attribute for backward-compat
- #9299: DOC: clarification of default rvs method in scipy.stats
- #9301: MAINT: removed unused import sys
- #9302: MAINT: removed unused imports
- #9303: DOC: signal: Refer to fs instead of nyq in the firwin docstring.
- #9305: ENH: Added Yeo-Johnson power transformation
- #9306: ENH - add dual annealing
- #9309: ENH add the yulesimon distribution to scipy.stats
- #9317: Nested SLSQP bug fix.
- #9320: MAINT: stats: avoid underflow in stats.geom.ppf
- #9326: Add example for Rosenbrock function
- #9332: Sort file lists
- #9340: Fix typo in find_peaks documentation
- #9343: MAINT Use np.full when possible
- #9344: DOC: added examples to docstring of dirichlet class
- #9346: DOC: Fix import of scipy.sparse.linalg in example (#9345)
- #9350: Fix interpolate read only
- #9351: MAINT: special.erf: use the x->-x symmetry
- #9356: Fix documentation typo
- #9358: DOC: improve doc for ksone and kstwobign in scipy.stats
- #9362: DOC: Change datatypes of A matrices in linprog
- #9364: MAINT: Adds implicit none to fftpack fortran sources
- #9369: DOC: minor tweak to CoC (updated NumFOCUS contact address).
- #9373: Fix exception if python is called with -OO option
- #9374: FIX: AIX compilation issue with NAN and INFINITY
- #9376: COBLA -> COBYLA in docs
- #9377: DOC: Add examples integrate: fixed_quad and quadrature
- #9379: MAINT: TST: Make tests NumPy 1.8 compatible
- #9385: CI: On Travis matrix "OPTIMIZE=-OO" flag ignored
- #9387: Fix default value for 'mode' in 'ndimage.shift' in the doc
- #9392: BUG: rank has to be integer in rank_filter: fixed issue 9388

- #9399: DOC: Misc. typos
- #9400: TST: stats: Fix the expected r-value of a linregress test.
- #9405: BUG: np.hstack does not accept generator expressions
- #9408: ENH: linalg: Shorter ill-conditioned warning message
- #9418: DOC: Fix ndimage docstrings and reduce doc build warnings
- #9421: DOC: Add missing docstring examples in scipy.spatial
- #9422: DOC: Add an example to integrate.newton_cotes
- #9427: BUG: Fixed defect with maxiter #9419 in dual annealing
- #9431: BENCH: Add dual annealing to scipy benchmark (see #9415)
- #9435: DOC: Add docstring examples for stats.binom_test
- #9443: DOC: Fix the order of indices in optimize tutorial
- #9444: MAINT: interpolate: use operator.index for checking/coercing...
- #9445: DOC: Added missing example to stats.mstats.kruskal
- #9446: DOC: Add note about version changed for jaccard distance
- #9447: BLD: version-script handling in setup.py
- #9448: TST: skip a problematic linalg test
- #9449: TST: fix missing seed in lobpcg test.
- #9456: TST: test_eigs_consistency() now sorts output

3.17 SciPy 1.1.0 Release Notes

Contents

- *SciPy 1.1.0 Release Notes*
 - *New features*
 - * *scipy.integrate improvements*
 - * *scipy.linalg improvements*
 - * *scipy.misc improvements*
 - * *scipy.ndimage improvements*
 - * *scipy.optimize improvements*
 - * *scipy.signal improvements*
 - * *scipy.sparse improvements*
 - * *scipy.special improvements*
 - * *scipy.stats improvements*
 - *Deprecated features*
 - *Backwards incompatible changes*

- *Other changes*
- *Authors*
 - * *Issues closed for 1.1.0*
 - * *Pull requests for 1.1.0*

SciPy 1.1.0 is the culmination of 7 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Before upgrading, we recommend that users check that their own code does not use deprecated SciPy functionality (to do so, run your code with `python -Wd` and check for `DeprecationWarning`s). Our development attention will now shift to bug-fix releases on the 1.1.x branch, and on adding new features on the master branch.

This release requires Python 2.7 or 3.4+ and NumPy 1.8.2 or greater.

This release has improved but not necessarily 100% compatible with the PyPy Python implementation. For running on PyPy, PyPy 6.0+ and Numpy 1.15.0+ are required.

3.17.1 New features

scipy.integrate improvements

The argument `tfirst` has been added to the function `scipy.integrate.odeint`. This allows `odeint` to use the same user functions as `scipy.integrate.solve_ivp` and `scipy.integrate.ode` without the need for wrapping them in a function that swaps the first two arguments.

Error messages from `quad()` are now clearer.

scipy.linalg improvements

The function `scipy.linalg.ldl` has been added for factorization of indefinite symmetric/hermitian matrices into triangular and block diagonal matrices.

Python wrappers for LAPACK `sygst`, `hegst` added in `scipy.linalg.lapack`.

Added `scipy.linalg.null_space`, `scipy.linalg.cdf2rdf`, `scipy.linalg.rsf2csf`.

scipy.misc improvements

An electrocardiogram has been added as an example dataset for a one-dimensional signal. It can be accessed through `scipy.misc.electrocardiogram`.

scipy.ndimage improvements

The routines `scipy.ndimage.binary_opening`, and `scipy.ndimage.binary_closing` now support masks and different border values.

scipy.optimize improvements

The method `trust-constr` has been added to `scipy.optimize.minimize`. The method switches between two implementations depending on the problem definition. For equality-constrained problems it is an implementation of a trust-region sequential quadratic programming solver and, when inequality constraints are imposed, it switches to a trust-region interior point method. Both methods are appropriate for large scale problems. Quasi-Newton options BFGS and SR1 were implemented and can be used to approximate second-order derivatives for this new method. Also, finite-differences can be used to approximate either first-order or second-order derivatives.

Random-to-Best/1/bin and Random-to-Best/1/exp mutation strategies were added to `scipy.optimize.differential_evolution` as `randtobest1bin` and `randtobest1exp`, respectively. Note: These names were already in use but implemented a different mutation strategy. See *Backwards-incompatible changes* below. The `init` keyword for the `scipy.optimize.differential_evolution` function can now accept an array. This array allows the user to specify the entire population.

Added an adaptive option to Nelder-Mead to use step parameters adapted to the dimensionality of the problem.

Minor improvements in `scipy.optimize.basinhopping`.

scipy.signal improvements

Three new functions for peak finding in one-dimensional arrays were added. `scipy.signal.find_peaks` searches for peaks (local maxima) based on simple value comparison of neighboring samples and returns those peaks whose properties match optionally specified conditions for their height, prominence, width, threshold and distance to each other. `scipy.signal.peak_prominences` and `scipy.signal.peak_widths` can directly calculate the prominences or widths of known peaks.

Added ZPK versions of frequency transformations: `scipy.signal.bilinear_zpk`, `scipy.signal.lp2bp_zpk`, `scipy.signal.lp2bs_zpk`, `scipy.signal.lp2hp_zpk`, `scipy.signal.lp2lp_zpk`.

Added `scipy.signal.windows.dpss`, `scipy.signal.windows.general_cosine` and `scipy.signal.windows.general_hamming`.

scipy.sparse improvements

Previously, the `reshape` method only worked on `scipy.sparse.lil_matrix`, and in-place reshaping did not work on any matrices. Both operations are now implemented for all matrices. Handling of shapes has been made consistent with `numpy.matrix` throughout the `scipy.sparse` module (shape can be a tuple or splatted, negative number acts as placeholder, padding and unpadding dimensions of size 1 to ensure length-2 shape).

scipy.special improvements

Added Owen's T function as `scipy.special.owens_t`.

Accuracy improvements in `chndtr`, `digamma`, `gammaincinv`, `lambertw`, `zetac`.

scipy.stats improvements

The Moyal distribution has been added as `scipy.stats.moyal`.

Added the normal inverse Gaussian distribution as `scipy.stats.norminvgauss`.

3.17.2 Deprecated features

The iterative linear equation solvers in `scipy.sparse.linalg` had a sub-optimal way of how absolute tolerance is considered. The default behavior will be changed in a future SciPy release to a more standard and less surprising one. To silence deprecation warnings, set the `atol=` parameter explicitly.

`scipy.signal.windows.slepian` is deprecated, replaced by `scipy.signal.windows.dpss`.

The window functions in `scipy.signal` are now available in `scipy.signal.windows`. They will remain also available in the old location in the `scipy.signal` namespace in future SciPy versions. However, importing them from `scipy.signal.windows` is preferred, and new window functions will be added only there.

Indexing sparse matrices with floating-point numbers instead of integers is deprecated.

The function `scipy.stats.itemfreq` is deprecated.

3.17.3 Backwards incompatible changes

Previously, `scipy.linalg.orth` used a singular value cutoff value appropriate for double precision numbers also for single-precision input. The cutoff value is now tunable, and the default has been changed to depend on the input data precision.

In previous versions of SciPy, the `randtobest1bin` and `randtobest1exp` mutation strategies in `scipy.optimize.differential_evolution` were actually implemented using the Current-to-Best/1/bin and Current-to-Best/1/exp strategies, respectively. These strategies were renamed to `currenttobest1bin` and `currenttobest1exp` and the implementations of `randtobest1bin` and `randtobest1exp` strategies were corrected.

Functions in the `ndimage` module now always return their output array. Before, most functions only returned the output array if it had been allocated by the function, and would return `None` if it had been provided by the user.

Distance metrics in `scipy.spatial.distance` now require non-negative weights.

`scipy.special.loggamma` now returns real-valued result when the input is real-valued.

3.17.4 Other changes

When building on Linux with GNU compilers, the `.so` Python extension files now hide all symbols except those required by Python, which can avoid problems when embedding the Python interpreter.

3.17.5 Authors

- Saurabh Agarwal +
- Diogo Aguiam +
- Joseph Albert +
- Gerrit Ansmann +
- Jean-François B +

- Vahan Babayan +
- Alessandro Pietro Bardelli
- Christoph Baumgarten +
- Felix Berkenkamp
- Lilian Besson +
- Aditya Bharti +
- Matthew Brett
- Evgeni Burovski
- CJ Carey
- Martin Ø. Christensen +
- Robert Cimrman
- Vicky Close +
- Peter Cock +
- Philip DeBoer
- Jaime Fernandez del Rio
- Dieter Werthmüller +
- Tom Donoghue +
- Matt Dzugan +
- Lars G +
- Jacques Gaudin +
- Andriy Gelman +
- Sean Gillies +
- Dezmond Goff
- Christoph Gohlke
- Ralf Gommers
- Uri Goren +
- Deepak Kumar Gouda +
- Douglas Lessa Graciosa +
- Matt Haberland
- David Hagen
- Charles Harris
- Jordan Heemskerk +
- Danny Hermes +
- Stephan Hoyer +
- Theodore Hu +
- Jean-François B. +

- Mads Jensen +
- Jon Haitz Legarreta Gorroño +
- Ben Jude +
- Noel Kippers +
- Julius Bier Kirkegaard +
- Maria Knorps +
- Mikkel Kristensen +
- Eric Larson
- Kasper Primdal Lauritzen +
- Denis Laxalde
- KangWon Lee +
- Jan Lehky +
- Jackie Leng +
- P.L. Lim +
- Nikolay Mayorov
- Mihai Capotă +
- Max Mikhaylov +
- Mark Mikofski +
- Jarrod Millman
- Raden Muhammad +
- Paul Nation
- Andrew Nelson
- Nico Schlömer
- Joel Nothman
- Kyle Oman +
- Egor Panfilov +
- Nick Papior
- Anubhav Patel +
- Oleksandr Pavlyk
- Ilhan Polat
- Robert Pollak +
- Anant Prakash +
- Aman Pratik
- Sean Quinn +
- Giftlin Rajaiah +
- Tyler Reddy

- Joscha Reimer
- Antonio H Ribeiro +
- Antonio Horta Ribeiro
- Benjamin Rose +
- Fabian Rost
- Divakar Roy +
- Scott Sievert
- Leo Singer
- Sourav Singh
- Martino Sorbaro +
- Eric Stansifer +
- Martin Thoma
- Phil Tooley +
- Piotr Uchwat +
- Paul van Mulbregt
- Pauli Virtanen
- Stefan van der Walt
- Warren Weckesser
- Florian Weimer +
- Eric Wieser
- Josh Wilson
- Ted Ying +
- Evgeny Zhurko
- Zé Vinícius
- @Astrofysicus +
- @awakenting +
- @endolith
- @FormerPhysicist +
- @gaulinmp +
- @hugovk
- @ksemb +
- @kshitij12345 +
- @luzpaz +
- @NKrvavica +
- @rafalalgo +
- @samyak0210 +

- @soluwalana +
- @sudheerachary +
- @Tokixix +
- @tttthomasssss +
- @vkk800 +
- @xoviat
- @ziejcow +

A total of 122 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 1.1.0

- #979: Allow Hermitian matrices in lobpcg (Trac #452)
- #2694: Solution of iterative solvers can be less accurate than tolerance...
- #3164: RectBivariateSpline usage inconsistent with other interpolation...
- #4161: Missing ITMAX optional argument in scipy.optimize.nnls
- #4354: signal.slepian should use definition of digital window
- #4866: Shouldn't scipy.linalg.sqrtm raise an error if matrix is singular?
- #4953: The dirichlet distribution unnecessarily requires strictly positive...
- #5336: sqrtm on a diagonal matrix can warn “Matrix is singular and may...
- #5922: Suboptimal convergence of Halley's method?
- #6036: Incorrect edge case in scipy.stats.triang.pdf
- #6202: Enhancement: Add LDLt factorization to scipy
- #6589: sparse.random with custom rvs callable does pass on arg to subclass
- #6654: Spearman's rank correlation coefficient slow with nan values...
- #6794: Remove NumarrayType struct with numarray type names from ndimage
- #7136: The dirichlet distribution unnecessarily rejects probabilities...
- #7169: Will it be possible to add LDL' factorization for Hermitian indefinite...
- #7291: fsolve docs should say it doesn't handle over- or under-determined...
- #7453: binary_opening/binary_closing missing arguments
- #7500: linalg.solve test failure on OS X with Accelerate
- #7555: Integrate a function with singularities using the quad routine
- #7624: allow setting both absolute and relative tolerance of sparse...
- #7724: odeint documentation refers to t0 instead of t
- #7746: False CDF values for skew normal distribution
- #7750: mstats.winsorize documentation needs clarification
- #7787: Documentation error in spherical Bessel, Neumann, modified spherical...

- #7836: Scipy mmwrite incorrectly writes the zeros for skew-symmetric,...
- #7839: sqrtm is unable to compute square root of zero matrix
- #7847: solve is very slow since #6775
- #7888: Scipy 1.0.0b1 prints spurious DVODE/ZVODE/lsoda messages
- #7909: `bessel kv` function in 0 is nan
- #7915: `LinearOperator`'s `__init__` runs two times when instantiating the...
- #7958: `integrate.quad` could use better error messages when given bad...
- #7968: `integrate.quad` handles decreasing limits ($b < a$) inconsistently
- #7970: ENH: matching return dtype for `loggamma/gammaln`
- #7991: `lfilter` segfaults for integer inputs
- #8076: "make dist" for the docs doesn't complete cleanly
- #8080: Use JSON in `special/_generate_pyx.py?`
- #8127: `scipy.special.psi(x)` very slow for some values of `x`
- #8145: BUG: `ndimage.geometric_transform` and `zoom` using deprecated NumPy...
- #8158: BUG: `romb` print output requires correction
- #8181: `loadmat()` raises `TypeError` instead of `FileNotFound` when reading...
- #8228: bug for `log1p` on `csr_matrix`
- #8235: `scipy.stats.multinomial.pmf` return nan
- #8271: `scipy.io.mmwrite` raises type error for `uint16`
- #8288: Should tests be written for `scipy.sparse.linalg.isolve.minres...`
- #8298: Broken links on scipy API web page
- #8329: `_gels` fails for fat `A` matrix
- #8346: Avoidable overflow in `scipy.special.binom(n, k)`
- #8371: BUG: `special.zetac(x)` returns 0 for $x < -30.8148$
- #8382: `collections.OrderedDict` in `test_mio.py`
- #8492: Missing documentation for `brute_force` parameter in `scipy.ndimage.morphology`
- #8532: `leastsq` needlessly appends extra dimension for scalar problems
- #8544: [feature request] Convert complex diagonal form to real block...
- #8561: [Bug?] Example of Bland's Rule for `optimize.linprog (simplex)...`
- #8562: CI: Appveyor builds fail because it can't import `ConvexHull` from...
- #8576: BUG: `optimize.show_options(solver='minimize', method='Newton-CG')`...
- #8603: `test_roots_gegenbauer/chebyt/chebyc` failures on manylinux
- #8604: Test failures in `scipy.sparse.test_inplace_dense`
- #8616: `special: ellpj.c` code can be cleaned up a bit
- #8625: `scipy 1.0.1` no longer allows overwriting variables in `netcdf...`
- #8629: `gcrotmk.test_atol` failure with MKL

- #8632: Sigma clipping on data with the same value
- #8646: `scipy.special.sinp` test failures in `test_zero_sign` on old MSVC
- #8663: `linprog` with `method=interior-point` produced incorrect answer...
- #8694: `linalg:TestSolve.test_all_type_size_routine_combinations` fails...
- #8703: Q: Does `runtests.py --refguide-check` need `env` (or other) variables...

Pull requests for 1.1.0

- #6590: BUG: sparse: fix custom rvs callable argument in `sparse.random`
- #7004: ENH: `scipy.linalg.eigsh` cannot get all eigenvalues
- #7120: ENH: implemented Owen's T function
- #7483: ENH: Addition/multiplication operators for `StateSpace` systems
- #7566: Informative exception when passing a sparse matrix
- #7592: Adaptive Nelder-Mead
- #7729: WIP: ENH: optimize: large-scale constrained optimization algorithms...
- #7802: MRG: Add `dpss` window function
- #7803: DOC: Add examples to `spatial.distance`
- #7821: Add Returns section to the docstring
- #7833: ENH: Performance improvements in `scipy.linalg.special_matrices`
- #7864: MAINT: sparse: Simplify `sputils.isintlike`
- #7865: ENH: Improved speed of copy into L, U matrices
- #7871: ENH: sparse: Add 64-bit integer to `sparsetools`
- #7879: ENH: re-enabled old `sv lapack` routine as defaults
- #7889: DOC: Show probability density functions as math
- #7900: API: Soft deprecate `signal.* windows`
- #7910: ENH: allow `sqrtn` to compute the root of some singular matrices
- #7911: MAINT: Avoid unnecessary array copies in `xdist`
- #7913: DOC: Clarifies the meaning of *initial* of `scipy.integrate.cumtrapz()`
- #7916: BUG: `sparse.linalg`: fix wrong use of `__new__` in `LinearOperator`
- #7921: BENCH: split spatial benchmark imports
- #7927: ENH: added `sygst/hegst` routines to `lapack`
- #7934: MAINT: add `io/_test_fortranmodule` to `gitignore`
- #7936: DOC: Fixed typo in `scipy.special.roots_jacobi` documentation
- #7937: MAINT: special: Mark a test that fails on i686 as a known failure.
- #7941: ENH: LDLt decomposition for indefinite symmetric/hermitian matrices
- #7945: ENH: Implement reshape method on sparse matrices
- #7947: DOC: update docs on releasing and installing/upgrading

- #7954: Basin-hopping changes
- #7964: BUG: test_falker not robust against numerical fuss in eigenvalues
- #7967: QUADPACK Errors - human friendly errors to replace 'Invalid Input'
- #7975: Make sure integrate.quad doesn't double-count singular points
- #7978: TST: ensure negative weights are not allowed in distance metrics
- #7980: MAINT: Truncate the warning msg about ill-conditioning
- #7981: BUG: special: fix hyp2f1 behavior in certain circumstances
- #7983: ENH: special: Add a real dispatch to *loggamma*
- #7989: BUG: special: make *kv* return *inf* at a zero real argument
- #7990: TST: special: test ufuncs in special at *nan* inputs
- #7994: DOC: special: fix typo in spherical Bessel function documentation
- #7995: ENH: linalg: add *null_space* for computing null spaces via *svd*
- #7999: BUG: optimize: Protect *_minpack* calls with a lock.
- #8003: MAINT: consolidate c99 compatibility
- #8004: TST: special: get all *cython_special* tests running again
- #8006: MAINT: Consolidate an additional *_c99compat.h*
- #8011: Add new example of *integrate.quad*
- #8015: DOC: special: remove *jn* from the *refguide* (again)
- #8018: BUG - Issue with *uint* datatypes for array in *get_index_dtype*
- #8021: DOC: spatial: Simplify Delaunay plotting
- #8024: Documentation fix
- #8027: BUG: io.matlab: fix saving unicode matrix names on *py2*
- #8028: BUG: special: some fixes for *lambertw*
- #8030: MAINT: Bump Cython version
- #8034: BUG: sparse.linalg: fix corner-case bug in *expm*
- #8035: MAINT: special: remove complex division hack
- #8038: ENH: Cythonize *pyx* files if *pxd* dependencies change
- #8042: TST: stats: reduce required precision in *test_flgner*
- #8043: TST: Use *diff.* values for decimal keyword for single and doubles
- #8044: TST: accuracy of tests made different for singles and doubles
- #8049: Unhelpful error message when calling *scipy.sparse.save_npz* on...
- #8052: TST: spatial: add a regression test for *gh-8051*
- #8059: BUG: special: fix *ufunc* results for *nan* arguments
- #8066: MAINT: special: reimplement inverses of incomplete gamma functions
- #8072: Example for *scipy.fftpack.iff*t, <https://github.com/scipy/scipy/issues/7168>
- #8073: Example for *ifftn*, <https://github.com/scipy/scipy/issues/7168>

- #8078: Link to CoC in contributing.rst doc
- #8085: BLD: Fix `np.isnan` of integer variables in `cephes`
- #8088: DOC: note version for which new attributes have been added to...
- #8090: BUG: special: add nan check to `_legacy_cast_check` functions
- #8091: Doxy Typos + trivial comment typos (2nd attempt)
- #8096: TST: special: simplify `Arg`
- #8101: MAINT: special: run `_generate_pyx.py` when `add_newdocs.py`...
- #8104: Input checking for `scipy.sparse.linalg.inverse()`
- #8105: DOC: special: Update the 'euler' docstring.
- #8109: MAINT: fixing code comments and `hyp2f1` docstring: see issues...
- #8112: More trivial typos
- #8113: MAINT: special: generate test data npz files in `setup.py` and...
- #8116: DOC: add build instructions
- #8120: DOC: Clean up README
- #8121: DOC: Add missing colons in docstrings
- #8123: BLD: update Bento build config files for recent C99 changes.
- #8124: Change to avoid use of `fmod` in `scipy.signal.chewin`
- #8126: Added examples for mode `arg` in `geometric_transform`
- #8128: relax relative tolerance parameter in `TestMinimumPhase.test_hilbert`
- #8129: ENH: special: use rational approximation for `\digamma` on `[1,...`
- #8137: DOC Correct matrix width
- #8141: MAINT: optimize: remove unused `__main__` code in L-BSGS-B
- #8147: BLD: update Bento build for removal of `.npz` `scipy.special` test...
- #8148: Alias `hanning` as an explanatory function of `hann`
- #8149: MAINT: special: small fixes for `digamma`
- #8159: Update version classifiers
- #8164: BUG: `riccati` solvers don't catch ill-conditioned problems sufficiently...
- #8168: DOC: release note for sparse resize methods
- #8170: BUG: correctly pad netCDF files with null bytes
- #8171: ENH added normal inverse gaussian distribution to `scipy.stats`
- #8175: DOC: Add example to `scipy.ndimage.zoom`
- #8177: MAINT: diffv small speedup in `ensure_constraint`
- #8178: FIX: `linalg._qz` String formatter syntax error
- #8179: TST: Added `pdist` to `asv` spatial benchmark suite
- #8180: TST: ensure `constraint` test improved
- #8183: `0d` `conj` correlate

- #8186: BUG: special: fix derivative of *spherical_jn(1, 0)*
- #8194: Fix warning message
- #8196: BUG: correctly handle inputs with nan's and ties in `spearmanr`
- #8198: MAINT: `stats.triang` edge case fixes #6036
- #8200: DOC: Completed "Examples" sections of all `linalg` funcs
- #8201: MAINT: `stats.trapz` edge cases
- #8204: ENH: `sparse.linalg/lobpcg`: change `.T` to `.T.conj()` to support...
- #8206: MAINT: missed `triang` edge case.
- #8214: BUG: Fix memory corruption in `linalg._decomp_update` C extension
- #8222: DOC: recommend `scipy.integrate.solve_ivp`
- #8223: ENH: added Moyal distribution to `scipy.stats`
- #8232: BUG: `sparse`: Use deduped data for `numpy.ufuncs`
- #8236: Fix #8235
- #8253: BUG: optimize: fix bug related with function call calculation...
- #8264: ENH: Extend peak finding capabilities in `scipy.signal`
- #8273: BUG fixed printing of convergence message in `minimize_scalar`...
- #8276: DOC: Add notes to explain constrains on `overwrite_<>`
- #8279: CI: fixing doctests
- #8282: MAINT: `weightedtau`, change search for nan
- #8287: Improving documentation of `solve_ivp` and the underlying solvers
- #8291: DOC: fix non-ascii characters in docstrings which broke the doc...
- #8292: CI: use `numpy 1.13` for `refguide` check build
- #8296: Fixed bug reported in issue #8181
- #8297: DOC: Examples for `linalg/decomp` eigvals function
- #8300: MAINT: Housekeeping for minimizing the `linalg` compiler warnings
- #8301: DOC: make public API documentation cross-link to `refguide`.
- #8302: make sure `_onenorm_matrix_power_nnm` actually returns a float
- #8313: Change copyright to outdated 2008-2016 to 2008-year
- #8315: TST: Add tests for ``scipy.sparse.linalg.isolve.minres``
- #8318: ENH: `odeint`: Add the argument `'first'` to `odeint`.
- #8328: ENH: optimize: `trust-constr` optimization algorithms [GSoC...]
- #8330: ENH: add a `maxiter` argument to NNLS
- #8331: DOC: tweak the Moyal distribution docstring
- #8333: FIX: Rewrapped `?gels` and `?gels_lwork` routines
- #8336: MAINT: `integrate`: handle `b < a` in `quad`
- #8337: BUG: special: Ensure `zetac(1)` returns `inf`.

- #8347: BUG: Fix overflow in special.binom. Issue #8346
- #8356: DOC: Corrected Documentation Issue #7750 winsorize function
- #8358: ENH: stats: Use explicit MLE formulas in lognorm.fit and expon.fit
- #8374: BUG: gh7854, maxiter for l-bfgs-b closes #7854
- #8379: CI: enable gcov coverage on travis
- #8383: Removed collections.OrderedDict import ignore.
- #8384: TravisCI: tool pep8 is now pycodestyle
- #8387: MAINT: special: remove unused specfun code for Struve functions
- #8393: DOC: Replace old type names in ndimage tutorial.
- #8400: Fix tolerance specification in sparse.linalg iterative solvers
- #8402: MAINT: Some small cleanups in ndimage.
- #8403: FIX: Make scipy.optimize.zeros run under PyPy
- #8407: BUG: sparse.linalg: fix termination bugs for cg, cgs
- #8409: MAINT: special: add a *pxd* file for Cephes functions
- #8412: MAINT: special: remove *cephes/protos.h*
- #8421: Setting “unknown” message in OptimizeResult when calling MINPACK.
- #8423: FIX: Handle unsigned integers in mmio
- #8426: DOC: correct FAQ entry on Apache license compatibility. Closes...
- #8433: MAINT: add *pytest_cache* to the *gitignore*
- #8436: MAINT: scipy.sparse: less copies at transpose method
- #8437: BUG: correct behavior for skew-symmetric matrices in io.mmwrite
- #8440: DOC: Add examples to integrate.quadpack docstrings
- #8441: BUG: sparse.linalg/gmres: deal with exact breakdown in gmres
- #8442: MAINT: special: clean up Cephes header files
- #8448: TST: Generalize doctest stopwords `.axis(` `.plot(`
- #8457: MAINT: special: use JSON for function signatures in *_generate_pyx.py*
- #8461: MAINT: Simplify return value of ndimage functions.
- #8464: MAINT: Trivial typos
- #8474: BUG: spatial: make *qhull.pyx* more pypy-friendly
- #8476: TST: `_lib`: disable refcounting tests on PyPy
- #8479: BUG: io/matlab: fix issues in matlab i/o on pypy
- #8481: DOC: Example for `signal.cmplx_sort`
- #8482: TST: integrate: use integers instead of PyCapsules to store pointers
- #8483: ENH: io/netcdf: make `mmap=False` the default on PyPy
- #8484: BUG: io/matlab: work around issue in `to_writeable` on PyPy
- #8488: MAINT: special: add const/static specifiers where possible

- #8489: BUG: ENH: use common halley's method instead of parabolic variant
- #8491: DOC: fix typos
- #8496: ENH: special: make Chebyshev nodes symmetric
- #8501: BUG: stats: Split the integral used to compute skewnorm.cdf.
- #8502: WIP: Port CircleCI to v2
- #8507: DOC: Add missing description to *brute_force* parameter.
- #8509: BENCH: forgot to add nelder-mead to list of methods
- #8512: MAINT: Move spline interpolation code to spline.c
- #8513: TST: special: mark a slow test as xslow
- #8514: CircleCI: Share data between jobs
- #8515: ENH: special: improve accuracy of *zetac* for negative arguments
- #8520: TST: Decrease the array sizes for two linalg tests
- #8522: TST: special: restrict range of *test_besselk/test_besselk_int*
- #8527: Documentation - example added for voronoi_plot_2d
- #8528: DOC: Better, shared docstrings in ndimage
- #8533: BUG: Fix PEP8 errors introduced in #8528.
- #8534: ENH: Expose additional window functions
- #8538: MAINT: Fix a couple mistakes in .pyf files.
- #8540: ENH: interpolate: allow string aliases in make_interp_spline...
- #8541: ENH: Cythonize peak_prominences
- #8542: Remove numerical arguments from convolve2d / correlate2d
- #8546: ENH: New arguments, documentation, and tests for ndimage.binary_opening
- #8547: Giving both size and input now raises UserWarning (#7334)
- #8549: DOC: stats: invweibull is also known as Frechet or type II extreme...
- #8550: add cdf2rdf function
- #8551: ENH: Port of most of the dd_real part of the qd high-precision...
- #8553: Note in docs to address issue #3164.
- #8554: ENH: stats: Use explicit MLE formulas in uniform.fit()
- #8555: MAINT: adjust benchmark config
- #8557: [DOC]: fix Nakagami density docstring
- #8559: DOC: Fix docstring of diric(x, n)
- #8563: [DOC]: fix gamma density docstring
- #8564: BLD: change default Python version for doc build from 2.7 to...
- #8568: BUG: Fixes Bland's Rule for pivot row/leaving variable, closes...
- #8572: ENH: Add previous/next to interp1d
- #8578: Example for linalg.eig()

- #8580: DOC: update link to asv docs
- #8584: filter_design: switch to explicit arguments, keeping None as...
- #8586: DOC: stats: Add parentheses that were missing in the exponnorm...
- #8587: TST: add benchmark for newton, secant, halley
- #8588: DOC: special: Remove heaviside from “functions not in special”...
- #8591: DOC: cdf2rdf Added version info and “See also”
- #8594: ENH: Cythonize peak_widths
- #8595: MAINT/ENH/BUG/TST: cdf2rdf: Address review comments made after...
- #8597: DOC: add versionadded 1.1.0 for new keywords in ndimage.morphology
- #8605: MAINT: special: improve implementations of *sinpi* and *cospi*
- #8607: MAINT: add 2D benchmarks for convolve
- #8608: FIX: Fix int check
- #8613: fix typo in doc of signal.peak_widths
- #8615: TST: fix failing linalg.qz float32 test by decreasing precision.
- #8617: MAINT: clean up code in ellpj.c
- #8618: add fsolve docs it doesn't handle over- or under-determined problems
- #8620: DOC: add note on dtype attribute of aslinearoperator() argument
- #8627: ENH: Add example 1D signal (ECG) to scipy.misc
- #8630: ENH: Remove unnecessary copying in stats.percentileofscore
- #8631: BLD: fix pdf doc build. closes gh-8076
- #8633: BUG: fix regression in *io.netcdf_file* with append mode.
- #8635: MAINT: remove spurious warning from (z)vode and lsoda. Closes...
- #8636: BUG: sparse.linalg/gcrotmk: avoid rounding error in termination...
- #8637: For pdf build
- #8639: CI: build pdf documentation on circleci
- #8640: TST: fix special test that was importing *np.testing.utils* (deprecated)
- #8641: BUG: optimize: fixed sparse redundancy removal bug
- #8645: BUG: modified sigmaclip to avoid clipping of constant input in...
- #8647: TST: sparse: skip test_inplace_dense for numpy<1.13
- #8657: Latex reduce left margins
- #8659: TST: special: skip sign-of-zero test on 32-bit win32 with old...
- #8661: Fix dblquad and tplquad not accepting float boundaries
- #8666: DOC: fixes #8532
- #8667: BUG: optimize: fixed issue #8663
- #8668: Fix example in docstring of netcdf_file
- #8671: DOC: Replace deprecated matplotlib kwarg

- #8673: BUG: special: Use a stricter tolerance for the chndtr calculation.
- #8674: ENH: In the Dirichlet distribution allow x_i to be 0 if $\alpha_i \dots$
- #8676: BUG: optimize: partial fix to linprog fails to detect infeasibility...
- #8685: DOC: Add interp1d-next/previous example to tutorial
- #8687: TST: netcdf: explicit mmap=True in test
- #8688: BUG: signal, stats: use Python sum() instead of np.sum for summing...
- #8689: TST: bump tolerances in tests
- #8690: DEP: deprecate stats.itemfreq
- #8691: BLD: special: fix build vs. dd_real.h package
- #8695: DOC: Improve examples in signal.find_peaks with ECG signal
- #8697: BUG: Fix *setup.py build install egg_info*, which did not previously...
- #8704: TST: linalg: drop large size from solve() test
- #8705: DOC: Describe signal.find_peaks and related functions behavior...
- #8706: DOC: Specify encoding of rst file, remove an ambiguity in an...
- #8710: MAINT: fix an import cycle sparse -> special -> integrate ->...
- #8711: ENH: remove an avoidable overflow in scipy.stats.norminvgauss.pdf()
- #8716: BUG: interpolate: allow list inputs for make_interp_spline(...,...
- #8720: np.testing import that is compatible with numpy 1.15
- #8724: CI: don't use pyproject.toml in the CI builds

3.18 SciPy 1.0.1 Release Notes

Contents

- *SciPy 1.0.1 Release Notes*
 - *Authors*
 - * *Issues closed for 1.0.1*
 - * *Pull requests for 1.0.1*

SciPy 1.0.1 is a bug-fix release with no new features compared to 1.0.0. Probably the most important change is a fix for an incompatibility between SciPy 1.0.0 and `numpy.f2py` in the NumPy master branch.

3.18.1 Authors

- Saurabh Agarwal +
- Alessandro Pietro Bardelli
- Philip DeBoer
- Ralf Gommers
- Matt Haberland
- Eric Larson
- Denis Laxalde
- Mihai Capotă +
- Andrew Nelson
- Oleksandr Pavlyk
- Ilhan Polat
- Anant Prakash +
- Pauli Virtanen
- Warren Weckesser
- @xoviat
- Ted Ying +

A total of 16 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 1.0.1

- #7493: `ndimage.morphology` functions are broken with numpy 1.13.0
- #8118: `minimize_cobyla` broken if `disp=True` passed
- #8142: `scipy-v1.0.0 pdist` with `metric='minkowski'` raises ``ValueError:...`
- #8173: `scipy.stats.ortho_group` produces all negative determinants...
- #8207: `gaussian_filter` seg faults on float16 numpy arrays
- #8234: `scipy.optimize.linprog interior-point` presolve bug with trivial...
- #8243: Make `csgraph` importable again via `from scipy.sparse import*`
- #8320: `scipy.root` segfaults with optimizer 'lm'

Pull requests for 1.0.1

- #8068: BUG: fix numpy deprecation test failures
- #8082: BUG: fix solve_lyapunov import
- #8144: MRG: Fix for cobyta
- #8150: MAINT: resolve UPDATEIFCOPY deprecation errors
- #8156: BUG: missing check on minkowski w kwarg
- #8187: BUG: Sign of elements in random orthogonal 2D matrices in “ortho_group_gen”...
- #8197: CI: uninstall oclint
- #8215: Fixes Numpy datatype compatibility issues
- #8237: BUG: optimize: fix bug when variables fixed by bounds are inconsistent...
- #8248: BUG: declare “gfk” variable before call of terminate() in newton-cg
- #8280: REV: reintroduce csgraph import in scipy.sparse
- #8322: MAINT: prevent scipy.optimize.root segfault closes #8320
- #8334: TST: stats: don't use exact equality check for hdmedian test
- #8477: BUG: signal/signaltools: fix wrong refcounting in PyArray_OrderFilterND
- #8530: BUG: linalg: Fixed typo in flapack.pyf.src.
- #8566: CI: Temporarily pin Cython version to 0.27.3
- #8573: Backports for 1.0.1
- #8581: Fix Cython 0.28 build break of qhull.pyx

3.19 SciPy 1.0.0 Release Notes

Contents

- *SciPy 1.0.0 Release Notes*
 - *Why 1.0 now?*
 - *Some history and perspectives*
 - *Highlights of this release*
 - *Upgrading and compatibility*
 - * *New features*
 - *scipy.cluster improvements*
 - *scipy.fftpack improvements*
 - *scipy.integrate improvements*
 - *scipy.linalg improvements*
 - *scipy.ndimage improvements*

- `scipy.optimize` *improvements*
- `scipy.signal` *improvements*
- `scipy.sparse` *improvements*
- `scipy.sparse.linalg` *improvements*
- `scipy.spatial` *improvements*
- `scipy.stats` *improvements*
 - * *Deprecated features*
 - * *Backwards incompatible changes*
 - * *Other changes*
 - * *Authors*
- *Issues closed for 1.0.0*
- *Pull requests for 1.0.0*

We are extremely pleased to announce the release of SciPy 1.0, 16 years after version 0.1 saw the light of day. It has been a long, productive journey to get here, and we anticipate many more exciting new features and releases in the future.

3.19.1 Why 1.0 now?

A version number should reflect the maturity of a project - and SciPy was a mature and stable library that is heavily used in production settings for a long time already. From that perspective, the 1.0 version number is long overdue.

Some key project goals, both technical (e.g. Windows wheels and continuous integration) and organisational (a governance structure, code of conduct and a roadmap), have been achieved recently.

Many of us are a bit perfectionist, and therefore are reluctant to call something “1.0” because it may imply that it’s “finished” or “we are 100% happy with it”. This is normal for many open source projects, however that doesn’t make it right. We acknowledge to ourselves that it’s not perfect, and there are some dusty corners left (that will probably always be the case). Despite that, SciPy is extremely useful to its users, on average has high quality code and documentation, and gives the stability and backwards compatibility guarantees that a 1.0 label imply.

3.19.2 Some history and perspectives

- 2001: the first SciPy release
- 2005: transition to NumPy
- 2007: creation of scikits
- 2008: `scipy.spatial` module and first Cython code added
- 2010: moving to a 6-monthly release cycle
- 2011: SciPy development moves to GitHub
- 2011: Python 3 support
- 2012: adding a sparse graph module and unified optimization interface
- 2012: removal of `scipy.maxentropy`
- 2013: continuous integration with TravisCI

- 2015: adding Cython interface for BLAS/LAPACK and a benchmark suite
- 2017: adding a unified C API with `scipy.LowLevelCallable`; removal of `scipy.weave`
- 2017: SciPy 1.0 release

Pauli Virtanen is SciPy's Benevolent Dictator For Life (BDFL). He says:

Truthfully speaking, we could have released a SciPy 1.0 a long time ago, so I'm happy we do it now at long last. The project has a long history, and during the years it has matured also as a software project. I believe it has well proved its merit to warrant a version number starting with unity.

Since its conception 15+ years ago, SciPy has largely been written by and for scientists, to provide a box of basic tools that they need. Over time, the set of people active in its development has undergone some rotation, and we have evolved towards a somewhat more systematic approach to development. Regardless, this underlying drive has stayed the same, and I think it will also continue propelling the project forward in future. This is all good, since not long after 1.0 comes 1.1.

Travis Oliphant is one of SciPy's creators. He says:

I'm honored to write a note of congratulations to the SciPy developers and the entire SciPy community for the release of SciPy 1.0. This release represents a dream of many that has been patiently pursued by a stalwart group of pioneers for nearly 2 decades. Efforts have been broad and consistent over that time from many hundreds of people. From initial discussions to efforts coding and packaging to documentation efforts to extensive conference and community building, the SciPy effort has been a global phenomenon that it has been a privilege to participate in.

The idea of SciPy was already in multiple people's minds in 1997 when I first joined the Python community as a young graduate student who had just fallen in love with the expressibility and extensibility of Python. The internet was just starting to bringing together like-minded mathematicians and scientists in nascent electronically-connected communities. In 1998, there was a concerted discussion on the matrix-SIG, python mailing list with people like Paul Barrett, Joe Harrington, Perry Greenfield, Paul Dubois, Konrad Hinsen, David Ascher, and others. This discussion encouraged me in 1998 and 1999 to procrastinate my PhD and spend a lot of time writing extension modules to Python that mostly wrapped battle-tested Fortran and C-code making it available to the Python user. This work attracted the help of others like Robert Kern, Pearu Peterson and Eric Jones who joined their efforts with mine in 2000 so that by 2001, the first SciPy release was ready. This was long before Github simplified collaboration and input from others and the "patch" command and email was how you helped a project improve.

Since that time, hundreds of people have spent an enormous amount of time improving the SciPy library and the community surrounding this library has dramatically grown. I stopped being able to participate actively in developing the SciPy library around 2010. Fortunately, at that time, Pauli Virtanen and Ralf Gommers picked up the pace of development supported by dozens of other key contributors such as David Cournapeau, Evgeni Burovski, Josef Perktold, and Warren Weckesser. While I have only been able to admire the development of SciPy from a distance for the past 7 years, I have never lost my love of the project and the concept of community-driven development. I remain driven even now by a desire to help sustain the development of not only the SciPy library but many other affiliated and related open-source projects. I am extremely pleased that SciPy is in the hands of a world-wide community of talented developers who will ensure that SciPy remains an example of how grass-roots, community-driven development can succeed.

Fernando Perez offers a wider community perspective:

The existence of a nascent Scipy library, and the incredible –if tiny by today's standards– community surrounding it is what drew me into the scientific Python world while still a physics graduate student in 2001. Today, I am awed when I see these tools power everything from high school education to the research that led to the 2017 Nobel Prize in physics.

Don't be fooled by the 1.0 number: this project is a mature cornerstone of the modern scientific computing ecosystem. I am grateful for the many who have made it possible, and hope to be able to contribute again to it in the future. My sincere congratulations to the whole team!

3.19.3 Highlights of this release

Some of the highlights of this release are:

- Major build improvements. Windows wheels are available on PyPI for the first time, and continuous integration has been set up on Windows and OS X in addition to Linux.
- A set of new ODE solvers and a unified interface to them (`scipy.integrate.solve_ivp`).
- Two new trust region optimizers and a new linear programming method, with improved performance compared to what `scipy.optimize` offered previously.
- Many new BLAS and LAPACK functions were wrapped. The BLAS wrappers are now complete.

3.19.4 Upgrading and compatibility

There have been a number of deprecations and API changes in this release, which are documented below. Before upgrading, we recommend that users check that their own code does not use deprecated SciPy functionality (to do so, run your code with `python -Wd` and check for `DeprecationWarnings`).

This release requires Python 2.7 or ≥ 3.4 and NumPy 1.8.2 or greater.

This is also the last release to support LAPACK 3.1.x - 3.3.x. Moving the lowest supported LAPACK version to $>3.2.x$ was long blocked by Apple Accelerate providing the LAPACK 3.2.1 API. We have decided that it's time to either drop Accelerate or, if there is enough interest, provide shims for functions added in more recent LAPACK versions so it can still be used.

New features

3.19.5 `scipy.cluster` improvements

`scipy.cluster.hierarchy.optimal_leaf_ordering`, a function to reorder a linkage matrix to minimize distances between adjacent leaves, was added.

3.19.6 `scipy.fftpack` improvements

N-dimensional versions of the discrete sine and cosine transforms and their inverses were added as `dctn`, `idctn`, `dstn` and `idstn`.

3.19.7 `scipy.integrate` improvements

A set of new ODE solvers have been added to `scipy.integrate`. The convenience function `scipy.integrate.solve_ivp` allows uniform access to all solvers. The individual solvers (RK23, RK45, Radau, BDF and LSODA) can also be used directly.

3.19.8 `scipy.linalg` improvements

The BLAS wrappers in `scipy.linalg.blas` have been completed. Added functions are `*gbmv`, `*hbmV`, `*hpmv`, `*hpr`, `*hpr2`, `*spmv`, `*spr`, `*tbmv`, `*tbsv`, `*tpmv`, `*tpsv`, `*trsm`, `*trsv`, `*sbmv`, `*spr2`,

Wrappers for the LAPACK functions `*gels`, `*stev`, `*sytrd`, `*hetrd`, `*sytf2`, `*hetrf`, `*sytrf`, `*sycon`, `*hecon`, `*gglse`, `*stebz`, `*stemr`, `*sterf`, and `*stein` have been added.

The function `scipy.linalg.subspace_angles` has been added to compute the subspace angles between two matrices.

The function `scipy.linalg.clarkson_woodruff_transform` has been added. It finds low-rank matrix approximation via the Clarkson-Woodruff Transform.

The functions `scipy.linalg.eigh_tridiagonal` and `scipy.linalg.eigvalsh_tridiagonal`, which find the eigenvalues and eigenvectors of tridiagonal hermitian/symmetric matrices, were added.

3.19.9 `scipy.ndimage` improvements

Support for homogeneous coordinate transforms has been added to `scipy.ndimage.affine_transform`.

The `ndimage` C code underwent a significant refactoring, and is now a lot easier to understand and maintain.

3.19.10 `scipy.optimize` improvements

The methods `trust-region-exact` and `trust-krylov` have been added to the function `scipy.optimize.minimize`. These new trust-region methods solve the subproblem with higher accuracy at the cost of more Hessian factorizations (compared to `dogleg`) or more matrix vector products (compared to `ncg`) but usually require less nonlinear iterations and are able to deal with indefinite Hessians. They seem very competitive against the other Newton methods implemented in `scipy`.

`scipy.optimize.linprog` gained an interior point method. Its performance is superior (both in accuracy and speed) to the older simplex method.

3.19.11 `scipy.signal` improvements

An argument `fs` (sampling frequency) was added to the following functions: `firwin`, `firwin2`, `firls`, and `remez`. This makes these functions consistent with many other functions in `scipy.signal` in which the sampling frequency can be specified.

`scipy.signal.freqz` has been sped up significantly for FIR filters.

3.19.12 `scipy.sparse` improvements

Iterating over and slicing of CSC and CSR matrices is now faster by up to ~35%.

The `tocsr` method of COO matrices is now several times faster.

The `diagonal` method of sparse matrices now takes a parameter, indicating which diagonal to return.

3.19.13 `scipy.sparse.linalg` improvements

A new iterative solver for large-scale nonsymmetric sparse linear systems, `scipy.sparse.linalg.gcrotmk`, was added. It implements GCROT (m, k), a flexible variant of GCROT.

`scipy.sparse.linalg.lsmr` now accepts an initial guess, yielding potentially faster convergence.

SuperLU was updated to version 5.2.1.

3.19.14 `scipy.spatial` improvements

Many distance metrics in `scipy.spatial.distance` gained support for weights.

The signatures of `scipy.spatial.distance.pdist` and `scipy.spatial.distance.cdist` were changed to `*args, **kwargs` in order to support a wider range of metrics (e.g. string-based metrics that need extra keywords). Also, an optional `out` parameter was added to `pdist` and `cdist` allowing the user to specify where the resulting distance matrix is to be stored

3.19.15 `scipy.stats` improvements

The methods `cdf` and `logcdf` were added to `scipy.stats.multivariate_normal`, providing the cumulative distribution function of the multivariate normal distribution.

New statistical distance functions were added, namely `scipy.stats.wasserstein_distance` for the first Wasserstein distance and `scipy.stats.energy_distance` for the energy distance.

Deprecated features

The following functions in `scipy.misc` are deprecated: `bytescale`, `fromimage`, `imfilter`, `imread`, `imresize`, `imrotate`, `imsave`, `imshow` and `toimage`. Most of those functions have unexpected behavior (like rescaling and type casting image data without the user asking for that). Other functions simply have better alternatives.

`scipy.interpolate.interpolate_wrapper` and all functions in that submodule are deprecated. This was a never finished set of wrapper functions which is not relevant anymore.

The `fillvalue` of `scipy.signal.convolve2d` will be cast directly to the dtypes of the input arrays in the future and checked that it is a scalar or an array with a single element.

`scipy.spatial.distance.matching` is deprecated. It is an alias of `scipy.spatial.distance.hamming`, which should be used instead.

Implementation of `scipy.spatial.distance.wminkowski` was based on a wrong interpretation of the metric definition. In scipy 1.0 it has been just deprecated in the documentation to keep retro-compatibility but is recommended to use the new version of `scipy.spatial.distance.minkowski` that implements the correct behaviour.

Positional arguments of `scipy.spatial.distance.pdist` and `scipy.spatial.distance.cdist` should be replaced with their keyword version.

Backwards incompatible changes

The following deprecated functions have been removed from `scipy.stats`: `betai`, `chisqprob`, `f_value`, `histogram`, `histogram2`, `pdf_fromgamma`, `signaltonoise`, `square_of_sums`, `ss` and `threshold`.

The following deprecated functions have been removed from `scipy.stats.mstats`: `betai`, `f_value_wilks_lambda`, `signaltonoise` and `threshold`.

The deprecated `a` and `reta` keywords have been removed from `scipy.stats.shapiro`.

The deprecated functions `sparse.csgraph.cs_graph_components` and `sparse.linalg.symeig` have been removed from `scipy.sparse`.

The following deprecated keywords have been removed in `scipy.sparse.linalg`: `drop_tol` from `splu`, and `xtype` from `bicg`, `bicgstab`, `cg`, `cgs`, `gmres`, `qmr` and `minres`.

The deprecated functions `expm2` and `expm3` have been removed from `scipy.linalg`. The deprecated keyword `q` was removed from `scipy.linalg.expm`. And the deprecated submodule `linalg.calc_lwork` was removed.

The deprecated functions `C2K`, `K2C`, `F2C`, `C2F`, `F2K` and `K2F` have been removed from `scipy.constants`.

The deprecated `ppform` class was removed from `scipy.interpolate`.

The deprecated keyword `iprint` was removed from `scipy.optimize.fmin_cobyla`.

The default value for the `zero_phase` keyword of `scipy.signal.decimate` has been changed to `True`.

The `kmeans` and `kmeans2` functions in `scipy.cluster.vq` changed the method used for random initialization, so using a fixed random seed will not necessarily produce the same results as in previous versions.

`scipy.special.gammaln` does not accept complex arguments anymore.

The deprecated functions `sph_jn`, `sph_yn`, `sph_jnyn`, `sph_in`, `sph_kn`, and `sph_inkn` have been removed. Users should instead use the functions `spherical_jn`, `spherical_yn`, `spherical_in`, and `spherical_kn`. Be aware that the new functions have different signatures.

The cross-class properties of `scipy.signal.lti` systems have been removed. The following properties/setters have been removed:

Name - (accessing/setting has been removed) - (setting has been removed)

- `StateSpace` - (num, den, gain) - (zeros, poles)
- `TransferFunction` (A, B, C, D, gain) - (zeros, poles)
- `ZerosPolesGain` (A, B, C, D, num, den) - ()

`signal.freqz(b, a)` with `b` or `a > 1-D` raises a `ValueError`. This was a corner case for which it was unclear that the behavior was well-defined.

The method `var` of `scipy.stats.dirichlet` now returns a scalar rather than an ndarray when the length of `alpha` is 1.

Other changes

SciPy now has a formal governance structure. It consists of a BDFL (Pauli Virtanen) and a Steering Committee. See [the governance document](#) for details.

It is now possible to build SciPy on Windows with MSVC + gfortran! Continuous integration has been set up for this build configuration on Appveyor, building against OpenBLAS.

Continuous integration for OS X has been set up on TravisCI.

The SciPy test suite has been migrated from `nose` to `pytest`.

`scipy/_distributor_init.py` was added to allow redistributors of SciPy to add custom code that needs to run when importing SciPy (e.g. checks for hardware, DLL search paths, etc.).

Support for PEP 518 (specifying build system requirements) was added - see `pyproject.toml` in the root of the SciPy repository.

In order to have consistent function names, the function `scipy.linalg.solve_lyapunov` is renamed to `scipy.linalg.solve_continuous_lyapunov`. The old name is kept for backwards-compatibility.

Authors

- @arcady +
- @xoviat +
- Anton Akhmerov
- Dominic Antonacci +
- Alessandro Pietro Bardelli
- Ved Basu +
- Michael James Bedford +
- Ray Bell +
- Juan M. Bello-Rivas +
- Sebastian Berg
- Felix Berkenkamp
- Jyotirmoy Bhattacharya +
- Matthew Brett
- Jonathan Bright
- Bruno Jiménez +
- Evgeni Burovski
- Patrick Callier
- Mark Campanelli +
- CJ Carey
- Robert Cimrman
- Adam Cox +
- Michael Danilov +

- David Haberthür +
- Andras Deak +
- Philip DeBoer
- Anne-Sylvie Deutsch
- Cathy Douglass +
- Dominic Else +
- Guo Fei +
- Roman Feldbauer +
- Yu Feng
- Jaime Fernandez del Rio
- Orestis Floros +
- David Freese +
- Adam Geitgey +
- James Gerity +
- Dezmond Goff +
- Christoph Gohlke
- Ralf Gommers
- Dirk Gorissen +
- Matt Haberland +
- David Hagen +
- Charles Harris
- Lam Yuen Hei +
- Jean Helie +
- Gaute Hope +
- Guillaume Horel +
- Franziska Horn +
- Yevhenii Hyzyla +
- Vladislav Iakovlev +
- Marvin Kastner +
- Mher Kazandjian
- Thomas Keck
- Adam Kurkiewicz +
- Ronan Lamy +
- J.L. Lanfranchi +
- Eric Larson
- Denis Laxalde

- Gregory R. Lee
- Felix Lenders +
- Evan Limanto
- Julian Lukwata +
- François Magimel
- Syrtis Major +
- Charles Masson +
- Nikolay Mayorov
- Tobias Megies
- Markus Meister +
- Roman Mirochnik +
- Jordi Montes +
- Nathan Musoke +
- Andrew Nelson
- M.J. Nichol
- Juan Nunez-Iglesias
- Arno Onken +
- Nick Papior +
- Dima Pasechnik +
- Ashwin Pathak +
- Oleksandr Pavlyk +
- Stefan Peterson
- Ilhan Polat
- Andrey Portnoy +
- Ravi Kumar Prasad +
- Aman Pratik
- Eric Quintero
- Vedant Rathore +
- Tyler Reddy
- Joscha Reimer
- Philipp Rentzsch +
- Antonio Horta Ribeiro
- Ned Richards +
- Kevin Rose +
- Benoit Rostykus +
- Matt Ruffalo +

- Eli Sadoff +
- Pim Schellart
- Nico Schlömer +
- Klaus Sembritzki +
- Nikolay Shebanov +
- Jonathan Tammo Siebert
- Scott Sievert
- Max Silbiger +
- Mandeep Singh +
- Michael Stewart +
- Jonathan Sutton +
- Deep Tavker +
- Martin Thoma
- James Tocknell +
- Aleksandar Trifunovic +
- Paul van Mulbregt +
- Jacob Vanderplas
- Aditya Vijaykumar
- Pauli Virtanen
- James Webber
- Warren Weckesser
- Eric Wieser +
- Josh Wilson
- Zhiqing Xiao +
- Evgeny Zhurko
- Nikolay Zinov +
- Zé Vinícius +

A total of 121 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

3.19.16 Issues closed for 1.0.0

- #2300: `scipy.misc.toimage` (and therefore `imresize`) converts to `uint32`...
- #2347: Several `misc.im*` functions incorrectly handle 3 or 4-channeled...
- #2442: `scipy.misc.pilutil` -> `scipy.ndimage`?
- #2829: Mingw Gfortran on Windows?
- #3154: `scipy.misc.imsave` creates wrong bitmap header
- #3505: `scipy.linalg.lstsq()` residual's help text is a lil strange
- #3808: Is Brent's method for minimizing the value of a function implemented...
- #4121: Add `cdf()` method to `stats.multivariate_normal`
- #4458: `scipy.misc.imresize` changes image range
- #4575: Docs for L-BFGS-B mention non-existent parameter
- #4893: `misc.imsave` does not work with file type defined
- #5231: Discrepancies in `scipy.optimize.minimize(method='L-BFGS-B')`
- #5238: Optimal leaf ordering in `scipy.cluster.hierarchy.dendrogram`
- #5305: Wrong image scaling in `scipy/misc/pilutil.py` with `misc.imsave`?
- #5823: test failure in `filter_design`
- #6061: `scipy.stats.spearmanr` return values outside range -1 to 1
- #6242: Inconsistency / duplication for `imread` and `imshow`, `imsave`
- #6265: BUG: `signal.iirfilter` of bandpass type is unstable when high...
- #6370: `scipy.optimize.linear_sum_assignment` hangs on undefined matrix
- #6417: `scipy.misc.imresize` converts images to `uint8`
- #6618: `splrep` and `splprep` inconsistent
- #6854: Support PEP 519 in I/O functions
- #6921: [Feature request] Random unitary matrix
- #6930: `uniform_filter1d` appears to truncate rather than round when output...
- #6949: `interp2d` function crashes python
- #6959: `scipy.interpolate.LSQUnivariateSpline` - check for increasing...
- #7005: `linear_sum_assignment` in `scipy.optimize` never return if one of...
- #7010: `scipy.stats.binned_statistic_2d`: incorrect binnnumbers returned
- #7049: `expm_multiply` is excessively slow when called for intervals
- #7050: Documenting `_argcheck` for `rv_discrete`
- #7077: `coo_matrix.tocsr()` still slow
- #7093: Wheels licensing
- #7122: Sketching-based Matrix Computations
- #7133: Discontinuity of a scipy special function
- #7141: Improve documentation for Elliptic Integrals

- #7181: A change in `numpy.poly1d` is causing the scipy tests to fail.
- #7220: String Formatting Issue in `LinearOperator.__init__`
- #7239: Source tarball distribution
- #7247: `genlaguerre poly1d-object` doesn't respect 'monic' option at evaluation
- #7248: BUG: regression in Legendre polynomials on master
- #7316: `dgels` is missing
- #7381: Krogh interpolation fails to produce derivatives for complex...
- #7416: `scipy.stats.kappa4(h,k)` raise a `ValueError` for positive integer...
- #7421: `scipy.stats.arcsine().pdf` and `scipy.stats.beta(0.5, 0.5).pdf`...
- #7429: `test_matrix_norms()` in `scipy/linalg/tests/test_basic.py` calls...
- #7444: Doc: `stats.dirichlet.var` output description is wrong
- #7475: Parameter `amax` in `scalar_search_wolfe2` is not used
- #7510: Operations between `numpy.array` and `scipy.sparse` matrix return...
- #7550: DOC: signal tutorial: Typo in explanation of convolution
- #7551: `stdint.h` included in SuperLU header files, but does not exist...
- #7553: Build for master broken on OS X
- #7557: Error in `scipy.signal.periodogram` example
- #7590: OSX test fail - `test_ltisys.TestPlacePoles.test_real`
- #7658: `optimize.BenchGlobal` broken
- #7669: nan result from `multivariate_normal.cdf`
- #7733: Inconsistent usage of indices, `indptr` in `Delaunay.vertex_neighbor_vertices`
- #7747: Numpy changes in `np.random.dirichlet` cause test failures
- #7772: Fix numpy `lstsq rcond=` parameter
- #7776: tests require ``nose``
- #7798: contributor names for 1.0 release notes
- #7828: 32-bit Linux test errors on `TestCephes`
- #7893: `scipy.spatial.distance.wminkowski` behaviour change in 1.0.0b1
- #7898: DOC: Window functions
- #7959: BUG maybe: `fmin_bfgs` possibly broken in 1.0
- #7969: `scipy 1.0.0rc1` windows wheels depend on missing `msvcpl140.dll`

3.19.17 Pull requests for 1.0.0

- #4978: WIP: add `pre_center` and `normalize` options to `lombscargle`
- #5796: TST: Remove all permanent filter changes from tests
- #5910: ENH: `sparse.linalg`: add `GCROT(m,k)`
- #6326: ENH: New ODE solvers
- #6480: ENH: Make `signal.decimate` default to `zero_phase=True`
- #6705: ENH: add initial guess to `sparse.linalg.lsqr`
- #6706: ENH: add initial guess to `sparse.linalg.lsmr`
- #6769: BUG: optimize: add sufficient descent condition check to CG line...
- #6855: Handle objects supporting PEP 519 in I/O functions
- #6945: MAINT: `ckdtree` codebase clean up
- #6953: DOC: add a SciPy Project Governance document
- #6998: fix documentation of `spearman rank corrcoef`
- #7017: ENH: add methods `logcdf` and `cdf` to `scipy.stats.multivariate_normal`
- #7027: Add random unitary matrices
- #7030: ENH: Add strictly-increasing checks for `x` to 1D splines
- #7031: BUG: Fix `linear_sum_assignment` hanging on an undefined matrix
- #7041: DOC: Clarify that windows are DFT-even by default
- #7048: DOC: modified docs for `find_peak_cwt`. Fixes #6922
- #7056: Fix insufficient precision when calculating `spearman/kendall...`
- #7057: MAINT: change `dtype` comparison in `optimize.linear_sum_assignment`.
- #7059: TST: make `Xdist_deprecated_args` cover all metrics
- #7061: Fix `msvc 9` and `10` compile errors
- #7070: ENH: `sparse`: optimizing CSR/CSC slicing fast paths
- #7078: ENH: `sparse`: defer `sum_duplicates` to `csr/csc`
- #7079: ENH: `sparse`: allow subclasses to override specific math operations
- #7081: ENH: `sparse`: speed up CSR/CSC `toarray()`
- #7082: MAINT: Add missing `PyType_Ready (&SuperLUGlobalType)` for Py3
- #7083: Corrected typo in the doc of `scipy.linalg.lstsq()`
- #7086: Fix bug #7049 causing excessive slowness in `expm_multiply`
- #7088: Documented `_argcheck` for `rv_discrete`
- #7094: MAINT: Fix mistake in PR #7082
- #7098: BF: return `NULL` from failed Py3 module check
- #7105: MAINT: Customize `?TRSYL` call in `lyapunov` solver
- #7111: Fix error message typo in `UnivariateSpline`
- #7113: FIX: Add `add float` to return type in documentation

- #7119: ENH: sparse.linalg: remove `_count_nonzero` hack
- #7123: ENH: added “interior-point” method for `scipy.optimize.linprog`
- #7137: DOC: clarify `stats.linregress` docstring, closes gh-7074
- #7138: DOC: special: Add an example to the `airy` docstring.
- #7139: DOC: stats: Update stats tutorial
- #7142: BUG: special: prevent segfault in `pbwa`
- #7143: DOC: special: warn about alternate elliptic integral parameterizations
- #7146: fix docstring of `NearestNDInterpolator`
- #7148: DOC: special: Add Parameters, Returns and Examples to `gamma` docstring
- #7152: MAINT: spatial: Remove two unused variables in `ckdtree/src/distance.h`
- #7153: MAINT: special: remove deprecated variant of `gammaln`
- #7154: MAINT: Fix some code that generates C compiler warnings
- #7155: DOC: linalg: Add examples for `solve_banded` and `solve_triangular`
- #7156: DOC: fix docstring of `NearestNDInterpolator`
- #7159: BUG: special: fix sign of derivative when $x < 0$ in `pbwa`
- #7161: MAINT: interpolate: make `Rbf.A` array a property
- #7163: MAINT: special: return nan for inaccurate regions of `pbwa`
- #7165: ENH: optimize: changes to make BFGS implementation more efficient.
- #7166: BUG: Prevent infinite loop in `optimize._lsq.trf_linear.py`
- #7173: BUG: sparse: return a numpy matrix from `_add_dense`
- #7179: DOC: Fix an error in `sparse.argmax` docstring
- #7180: MAINT: interpolate: A bit of clean up in `interpolate/src/_interpolate.cpp`
- #7182: Allow homogeneous coordinate transforms in `affine_transform`
- #7184: MAINT: Remove hack modifying a readonly attr
- #7185: ENH: Add evaluation of periodic splines #6730
- #7186: MAINT: PPoly: improve error messages for wrong shape/axis
- #7187: DEP: interpolate: deprecate `interpolate_wrapper`
- #7198: DOC: linalg: Add examples for `solveh_banded` and `solve_toeplitz`.
- #7200: DOC: stats: Added tutorial documentation for the generalized...
- #7208: DOC: Added docstrings to `issparse/isspmatrix(...)` methods and...
- #7213: DOC: Added examples to `circmean`, `circvar`, `circstd`
- #7215: DOC: Adding examples to `scipy.sparse.linalg...` docstrings
- #7223: DOC: special: Add examples for `expit` and `logit`.
- #7224: BUG: interpolate: fix integer overflow in `fitpack.bispev`
- #7225: DOC: update 1.0 release notes for several recent PRs.
- #7226: MAINT: update docs and code for mailing list move to python.org

- #7233: Fix issue #7232: Do not mask exceptions in objective func evaluation
- #7234: MAINT: cluster: cleaning up VQ/k-means code
- #7236: DOC: Fixed typo
- #7238: BUG: fix syntaxerror due to unicode character in `trustregion_exact`.
- #7243: DOC: Update docstring in `misc/pilutil.py`
- #7246: DEP: misc: deprecate imported names
- #7249: DOC: Add plotted example to `scipy.cluster.vq.kmeans`
- #7252: Fix 5231: docs of `factr`, `ftol` in sync w/ code
- #7254: ENH: SphericalVoronoi Input Handling
- #7256: fix for issue #7255 - Circular statistics functions give wrong...
- #7263: CI: use python's fault handler to ease tracing segfaults
- #7288: ENH: linalg: add `subspace_angles` function.
- #7290: BUG: stats: Fix spurious warnings in `genextreme`.
- #7292: ENH: optimize: added trust region method `trust-trlib`
- #7296: DOC: stats: Add an example to the `ttest_ind_from_stats` docstring.
- #7297: DOC: signal: Add examples for `chirp()` and `sweep_poly()`.
- #7299: DOC: Made difference between `brent` and `fminbound` clearer
- #7305: Simplify if-statements and constructor calls in `integrate._ode`
- #7309: Comply with PEP 518.
- #7313: REL: add `python_requires` to `setup.py`, fix Python version check.
- #7315: BUG: Fixed bug with Laguerre and Legendre polynomials
- #7320: DOC: clarify meaning of flags in `ode.integrate`
- #7333: DOC: Add examples to `scipy.ndimage.gaussian_filter1d`
- #7337: ENH: add n-dimensional DCT and IDCT to `fftpack`
- #7353: Add `_gels` functions
- #7357: DOC: linalg: Add examples to the `svdvals` docstring.
- #7359: Bump Sphinx version to 1.5.5
- #7361: DOC: linalg: Add some 'See Also' links among special matrices...
- #7362: TST: Fix some Fedora 25 test failures.
- #7363: DOC: linalg: tweak the docstring example of `svd`
- #7365: MAINT: fix `refguide_check.py` for Sphinx ≥ 1.5
- #7367: BUG: odrpack: fix invalid stride checks in `d_lpkbls.f`
- #7368: DOC: constants: Add examples to the 'find' docstring.
- #7376: MAINT: bundle Mathjax with built docs
- #7377: MAINT: optimize: Better name for `trust-region-exact` method.
- #7378: Improve wording in tutorial

- #7383: fix KroghInterpolator.derivatives failure with complex input
- #7389: FIX: Copy mutable window in `resample_poly`
- #7390: DOC: optimize: A few tweaks of the examples in the `curve_fit`
- #7391: DOC: Add examples to `scipy.stats`
- #7394: “Weight” is actually mass. Add slugs and slinches/blobs to mass
- #7398: DOC: Correct minor typo in `optimize.{brenth,brentq}`
- #7401: DOC: zeta only accepts real input
- #7413: BUG: fix error messages in `_minimize_trustregion_exact`
- #7414: DOC: fix `ndimage.distance_transform_bf` docstring [ci skip]
- #7415: DOC: fix skew docstring [ci skip]
- #7423: Expand `binnumbers` with correct dimensions
- #7431: BUG: Extend `scipy.stats.arcsine.pdf` to endpoints 0 and 1 #7427
- #7432: DOC: Add examples to `scipy.cluster.hierarchy`
- #7448: ENH: stats: Implement the survival function for pareto.
- #7454: FIX Replaced `np.assert_allclose` with imported `assert_allclose`
- #7460: TST: fix `integrate.ivp` test that fails on 32-bit Python.
- #7461: Doc: Added tutorial documentation for stats distributions `ksone`
- #7463: DOC: Fix typos and remove trailing whitespace
- #7465: Fix some `ndimage.interpolation` endianness bugs
- #7468: del redundance in `interpolate.py`
- #7470: Initialize “info” in `minpack_lmdif`
- #7478: Added more testing of `smirnov/smironvi` functions
- #7479: MAINT: update for new `FutureWarning`'s in `numpy 1.13.0`
- #7480: DOC: correctly describe output shape of `dirichlet.mean()` and...
- #7482: `signal.lti`: Remove deprecated cross-system properties
- #7484: MAINT: Clean-up uses of `np.asarray` in `ndimage`
- #7485: ENH: support any order ≥ 0 in `ndimage.gaussian_filter`
- #7486: ENH: Support $k \neq 0$ for `sparse.diagonal()`
- #7498: BUG: `sparse`: pass `assumeSortedIndices` option to `scikit.umfpack`
- #7501: ENH: add optimal leaf ordering for linkage matrices
- #7506: MAINT: remove overflow in Metropolis fixes #7495
- #7507: TST: speed up full test suite by less eval points in `mpmath` tests.
- #7509: BUG: fix issue when using `python setup.py somecommand --force`.
- #7511: fix some alerts found with `lgtm`
- #7514: Add explanation what the integer returned mean.
- #7516: BUG: Fix roundoff errors in `ndimage.uniform_filter1d`.

- #7517: TST: fix `signal.convolve` test that was effectively being skipped.
- #7523: ENH: `linalg`: allow `lstsq` to work with 0-shaped arrays
- #7525: TST: Warning cleanup
- #7526: DOC: params in `ndimage.interpolation` functions not optional
- #7527: MAINT: Encapsulate error message handling in `NI_LineBuffer`.
- #7528: MAINT: Remove `ndimage` aliases for `NPY_MAXDIMS`.
- #7529: MAINT: Remove `NI_(UN)LIKELY` macros in favor of numpy ones.
- #7537: MAINT: Use accessor function for numpy array internals
- #7541: MAINT: Remove some uses of Numarray types in `ndimage`.
- #7543: MAINT: Replace all NumarrayTypes uses in `ni_fourier.c`
- #7544: MAINT: Replace all uses of NumarrayTypes in `ni_interpolation.c`
- #7545: MAINT: Replace all uses of NumarrayTypes in `ni_measure.c`
- #7546: MAINT: Replace all uses of NumarrayTypes in `ni_morphology.c`
- #7548: DOC: make a note in benchmarks README on how to run without rebuilding.
- #7549: MAINT: Get rid of NumarrayTypes.
- #7552: TST: Fix new warnings -> error bugs found on OSX
- #7554: Update `superlu` to 5.2.1 + fix `stdint.h` issue on MSVC
- #7556: MAINT: Fix some types from #7549 + miscellaneous warnings.
- #7558: MAINT: Use correct `#define NO_IMPORT_ARRAY`, not `NO_ARRAY_IMPORT...`
- #7562: BUG: Copy `import_nose` from numpy.
- #7563: ENH: Add the first Wasserstein and the Cramér-von Mises statistical...
- #7568: Test janitoring
- #7571: Test janitoring pt. 2
- #7572: Pytestifying
- #7574: TST: Remove ignore warnings filters from stats
- #7577: MAINT: Remove unused code in `ndimage/ni_measure.c` and `.h`
- #7578: TST: Remove ignore warnings filters from `sparse`, clean up warning...
- #7581: BUG: properly deallocate memory from `PyArray_IntpConverter`.
- #7582: DOC: signal tutorial: Typo in explanation of convolution
- #7583: Remove remaining ignore warnings filters
- #7586: DOC: add note to `HACKING.rst` on where to find build docs.
- #7587: DOC: Add examples to `scipy.optimize`
- #7594: TST: Add tests for `ndimage` converter functions.
- #7596: Added a sanity check to `signal.savgol_filter`
- #7599: `_upfirdn_apply` stopping condition bugfix
- #7601: MAINT: special: remove `sph_jn` et al.

- #7602: TST: fix test failures in trimmed statistics tests with numpy...
- #7605: Be clear about required dimension order
- #7606: MAINT: Remove unused function `NI_NormalizeType`.
- #7607: TST: add osx to travis matrix
- #7608: DOC: improve HACKING guide - mention reviewing PRs as contribution.
- #7609: MAINT: Remove unnecessary warning filter by avoiding unnecessary...
- #7610: #7557 : fix example code in periodogram
- #7611: #7220 : fix TypeError while raising ValueError for invalid shape
- #7612: Convert yield tests to pytest parametrized tests
- #7613: Add distributor init file
- #7614: fixup header
- #7615: BUG: sparse: Fix assignment w/ non-canonical sparse argument
- #7617: DOC: Clarify digital filter functions
- #7619: ENH: `scipy.sparse.spmatrix.astype`: casting and copy parameter...
- #7621: Expose VODE/ZVODE/LSODE IDID return code to user
- #7622: MAINT: special: remove out-of-date comment for `ellpk`
- #7625: TST: Add a test for “ignore” warning filters
- #7628: MAINT: refactoring and cleaning `distance.py/c/h`
- #7629: DEP: deprecate args usage in `xdist`
- #7630: ENH: weighted metrics
- #7634: Follow-up to #6855
- #7635: `interpolate.splprep`: Test some error cases, give slightly better...
- #7642: Add an example to `interpolate.lagrange`
- #7643: ENH: Added wrappers for LAPACK `<s,d>stev`
- #7649: Fix #7636, add PEP 519 test coverage to remaining I/O functions
- #7650: DOC: signal: Add ‘Examples’ to the docstring for `sosfiltfilt`.
- #7651: Fix up `ccache` usage on Travis + try enabling on OSX
- #7653: DOC: transition of examples from 2 to 3. Closes #7366
- #7659: BENCH: fix `optimize.BenchGlobal`. Closes gh-7658.
- #7662: CI: speed up continuous integration builds
- #7664: Update odr documentation
- #7665: BUG: `wolfe2` line/scalar search now uses `amax` parameter
- #7671: MAINT: `_lib/ccallback.h`: `PyCapsule_GetName` returns `const char*`
- #7672: TST: `interpolate`: test integrating periodic b-splines against...
- #7674: Tests tuning
- #7675: CI: move `refguide-check` to faster build

- #7676: DOC: bump scipy-sphinx-theme to fix copybutton.js
- #7678: Note the zero-padding of the results of `splprep` and `splprep`
- #7681: MAINT: `_lib`: add user-overridable available memory determination
- #7684: TST: `linalg`: explicitly close opened npz files
- #7686: MAINT: remove unnecessary shebang lines and executable bits
- #7687: BUG: `stats`: don't emit invalid warnings if moments are infinite
- #7690: ENH: allow int-like parameters in several routines
- #7691: DOC: Drop non-working source links from docs
- #7694: fix `ma.rarray` to `ma.array` in `func median_cihs`
- #7698: BUG: `stats`: fix nan result from `multivariate_normal.cdf` (#7669)
- #7703: DOC: special: Update the docstrings for noncentral F functions.
- #7709: BLD: `integrate`: avoid symbol clash between `lsoda` and `vode`
- #7711: TST: `_lib`: make `test_parallel_threads` to not fail falsely
- #7712: TST: `stats`: bump test tolerance in `TestMultivariateNormal.test_broadcasting`
- #7715: MAINT: fix deprecated use of `numpy.issubdtype`
- #7716: TST: `integrate`: drop timing tests
- #7717: MAINT: `mstats.winsorize` inclusion bug fix
- #7719: DOC: `stats`: Add a note about the special cases of the `rdist` distribution.
- #7720: DOC: Add example and math to `stats.pearsonr`
- #7723: DOC: Added Mann-Whitney U statistic reference
- #7727: BUG: `special/cdflib`: deal with nan and nonfinite inputs
- #7728: BLD: `spatial`: fix `ckdtree` depends header list
- #7732: BLD: update Bento build for `optimal_leaf_ordering` addition
- #7734: DOC: `signal`: Copy-edit and add examples to the Kaiser-related...
- #7736: BUG: Fixes #7735: Prevent integer overflow in concatenated index...
- #7737: DOC: rename `indices/indptr` for `spatial.Delaunay` `vertex_neighbor_vertices`
- #7738: ENH: Speed up `freqz` computation
- #7739: TST: ignore `ncfdtridfn` failure in win32 and warn on FPU mode changes
- #7740: Fix overflow in Anderson-Darling k-sample test
- #7742: TST: special: limit `expm1` `mpmath` comparison range
- #7748: TST: `stats`: don't pass invalid `alpha` to `np.random.dirichlet`
- #7749: BUG/DOC: `optimize`: method is 'interior-point', not 'interior...
- #7751: BUG: `optimize`: `show_options('linprog', method='interior-point')`...
- #7753: ENH: `io`: easier syntax for `FortranFile` read/write of mixed records
- #7754: BLD: add `_lib._fpumode` extension to Bento build.
- #7756: DOC: Show probability density functions as math

- #7757: MAINT: remove outdated OS X build scripts. Fixes pytest failure.
- #7758: MAINT: stats: pep8, wrap lines
- #7760: DOC: special: add instructions on how to add special functions
- #7761: DOC: allow specifying Python version for Sphinx makefile
- #7765: TST: fix test coverage of `mstats_extras.py`
- #7767: DOC: update 1.0 release notes.
- #7768: DOC: update notes on how to release. Also change paver file to...
- #7769: Add the `_sf` and `_logsf` function for `planck` dist
- #7770: DOC: Replace rotten links in the docstring of `minres`
- #7771: MAINT: f2py build output cleanup
- #7773: DOC: optimize: Some copy-editing of `linprog` docs.
- #7774: MAINT: set `rcond` explicitly for `np.linalg.lstsq` calls
- #7777: remove leftover `nose` imports
- #7780: ENH: Wrap LAPACK's `dsytrd`
- #7781: DOC: Link `rfft`
- #7782: MAINT: run `pyx` autogeneration in `cythonize` & remove `autogen` files
- #7783: FIX: Disallow `Wn==1` in digital filters
- #7790: Fix test errors introduced by `gh-5910`
- #7792: MAINT: fix syntax in `pyproject.toml`
- #7809: ENH: sketches - Clarkson Woodruff Transform
- #7810: ENH: Add `eig(vals)_tridiagonal`
- #7811: BUG: stats: Fix warnings in `binned_statistics_dd`
- #7814: ENH: signal: Replace 'nyq' and 'Hz' arguments with 'fs'.
- #7820: DOC: update 1.0 release notes and mailmap
- #7823: BUG: memory leak in `messagestream / qhull.pyx`
- #7830: DOC: `linalg`: Add an example to the `lstsq` docstring.
- #7835: ENH: Automatic FIR order for `decimate`
- #7838: MAINT: stats: Deprecate `frechet_l` and `frechet_r`.
- #7841: `slsqp` PEP8 formatting fixes, typos, etc.
- #7843: ENH: Wrap all BLAS routines
- #7844: DOC: update `LICENSE.txt` with licenses of bundled libs as needed.
- #7851: ENH: Add wrappers for `?GGLSE`, `?(HE/SY)CON`, `?SYTF2`, `?(HE/SY)TRF`
- #7856: ENH: added `out` argument to `Xdist`
- #7858: BUG: `special/cdflib`: fix fatal loss of precision issues in `cumfnc`
- #7859: FIX: Squash `place_poles` warning corner case
- #7861: dummy statement for undefined `WITH_THREAD`

- #7863: MAINT: add license texts to binary distributions
- #7866: DOC, MAINT: fix links in the doc
- #7867: DOC: fix up descriptions of pdf's in distribution docstrings.
- #7869: DEP: deprecate misc.pilutil functions
- #7870: DEP: remove deprecated functions
- #7872: TST: silence RuntimeWarning for stats.truncnorm test marked as...
- #7874: TST: fix an optimize.linprog test that fails intermittently.
- #7875: TST: filter two integration warnings in stats tests.
- #7876: GEN: Add comments to the tests for clarification
- #7891: ENH: backport #7879 to 1.0.x
- #7902: MAINT: signal: Make freqz handling of multidim. arrays match...
- #7905: REV: restore wminkowski
- #7908: FIX: Avoid bad `__del__` (close) behavior
- #7918: TST: mark two optimize.linprog tests as xfail. See gh-7877.
- #7929: MAINT: changed defaults to lower in sytf2, sytrf and hetrf
- #7939: Fix umfpack solver construction for win-amd64
- #7948: DOC: add note on checking for deprecations before upgrade to...
- #7952: DOC: update SciPy Roadmap for 1.0 release and recent discussions.
- #7960: BUG: optimize: revert changes to bfgs in gh-7165
- #7962: TST: special: mark a failing hyp2f1 test as xfail
- #7973: BUG: fixed keyword in 'info' in `_get_mem_available` utility
- #8001: TST: fix test failures from Matplotlib 2.1 update
- #8010: BUG: signal: fix crash in lfilter
- #8019: MAINT: fix test failures with NumPy master

3.20 SciPy 0.19.1 Release Notes

SciPy 0.19.1 is a bug-fix release with no new features compared to 0.19.0. The most important change is a fix for a severe memory leak in `integrate.quad`.

3.20.1 Authors

- Evgeni Burovski
- Patrick Callier +
- Yu Feng
- Ralf Gommers
- Ilhan Polat

- Eric Quintero
- Scott Sievert
- Pauli Virtanen
- Warren Weckesser

A total of 9 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 0.19.1

- #7214: Memory use in `integrate.quad` in `scipy-0.19.0`
- #7258: `linalg.matrix_balance` gives wrong transformation matrix
- #7262: Segfault in daily testing
- #7273: `scipy.interpolate._bspl.evaluate_spline` gets wrong type
- #7335: `scipy.signal.dlti(A,B,C,D).freqresp()` fails

Pull requests for 0.19.1

- #7211: BUG: `convolve` may yield inconsistent dtypes with method changed
- #7216: BUG: `integrate`: fix recounting bug in `quad()`
- #7229: MAINT: special: Rewrite a test of `wrightomega`
- #7261: FIX: Corrected the transformation matrix permutation
- #7265: BUG: Fix broken axis handling in spectral functions
- #7266: FIX 7262: `ckdtree` crashes in `query_knn`.
- #7279: Upcast half- and single-precision floats to doubles in `BSpline...`
- #7336: BUG: Fix `signal.dfreqresp` for `StateSpace` systems
- #7419: Fix several issues in `sparse.load_npz`, `save_npz`
- #7420: BUG: `stats`: allow integers as `kappa4` shape parameters

3.21 SciPy 0.19.0 Release Notes

Contents

- *SciPy 0.19.0 Release Notes*
 - *New features*
 - * *Foreign function interface improvements*
 - * *scipy.linalg improvements*
 - * *scipy.spatial improvements*
 - * *scipy.ndimage improvements*

- * `scipy.optimize` improvements
- * `scipy.signal` improvements
- * `scipy.fftpack` improvements
- * `scipy.cluster` improvements
- * `scipy.sparse` improvements
- * `scipy.special` improvements
- * `scipy.stats` improvements
- * `scipy.interpolate` improvements
- * `scipy.integrate` improvements
- *Deprecated features*
- *Backwards incompatible changes*
- *Other changes*
- *Authors*
 - * *Issues closed for 0.19.0*
 - * *Pull requests for 0.19.0*

SciPy 0.19.0 is the culmination of 7 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Moreover, our development attention will now shift to bug-fix releases on the 0.19.x branch, and on adding new features on the master branch.

This release requires Python 2.7 or 3.4-3.6 and NumPy 1.8.2 or greater.

Highlights of this release include:

- A unified foreign function interface layer, `scipy.LowLevelCallable`.
- Cython API for scalar, typed versions of the universal functions from the `scipy.special` module, via `import scipy.special.cython_special`.

3.21.1 New features

Foreign function interface improvements

`scipy.LowLevelCallable` provides a new unified interface for wrapping low-level compiled callback functions in the Python space. It supports Cython imported “api” functions, ctypes function pointers, CFFI function pointers, PyCapsules, Numba jitted functions and more. See [gh-6509](#) for details.

scipy.linalg improvements

The function `scipy.linalg.solve` obtained two more keywords `assume_a` and `transposed`. The underlying LAPACK routines are replaced with “expert” versions and now can also be used to solve symmetric, hermitian and positive definite coefficient matrices. Moreover, ill-conditioned matrices now cause a warning to be emitted with the estimated condition number information. Old `sym_pos` keyword is kept for backwards compatibility reasons however it is identical to using `assume_a='pos'`. Moreover, the `debug` keyword, which had no function but only printing the `overwrite_<a, b>` values, is deprecated.

The function `scipy.linalg.matrix_balance` was added to perform the so-called matrix balancing using the LAPACK `xGEBAL` routine family. This can be used to approximately equate the row and column norms through diagonal similarity transformations.

The functions `scipy.linalg.solve_continuous_are` and `scipy.linalg.solve_discrete_are` have numerically more stable algorithms. These functions can also solve generalized algebraic matrix Riccati equations. Moreover, both gained a `balanced` keyword to turn balancing on and off.

scipy.spatial improvements

`scipy.spatial.SphericalVoronoi.sort_vertices_of_regions` has been re-written in Cython to improve performance.

`scipy.spatial.SphericalVoronoi` can handle > 200 k points (at least 10 million) and has improved performance.

The function `scipy.spatial.distance.directed_hausdorff` was added to calculate the directed Hausdorff distance.

`count_neighbors` method of `scipy.spatial.cKDTree` gained an ability to perform weighted pair counting via the new keywords `weights` and `cumulative`. See [gh-5647](#) for details.

`scipy.spatial.distance.pdist` and `scipy.spatial.distance.cdist` now support non-double custom metrics.

scipy.ndimage improvements

The callback function C API supports PyCapsules in Python 2.7

Multidimensional filters now allow having different extrapolation modes for different axes.

scipy.optimize improvements

The `scipy.optimize.basinhopping` global minimizer obtained a new keyword, `seed`, which can be used to seed the random number generator and obtain repeatable minimizations.

The keyword `sigma` in `scipy.optimize.curve_fit` was overloaded to also accept the covariance matrix of errors in the data.

scipy.signal improvements

The function `scipy.signal.correlate` and `scipy.signal.convolve` have a new optional parameter `method`. The default value of `auto` estimates the fastest of two computation methods, the direct approach and the Fourier transform approach.

A new function has been added to choose the convolution/correlation method, `scipy.signal.choose_conv_method` which may be appropriate if convolutions or correlations are performed on many arrays of the same size.

New functions have been added to calculate complex short time fourier transforms of an input signal, and to invert the transform to recover the original signal: `scipy.signal.stft` and `scipy.signal.istft`. This implementation also fixes the previously incorrect output of `scipy.signal.spectrogram` when complex output data were requested.

The function `scipy.signal.sosfreqz` was added to compute the frequency response from second-order sections.

The function `scipy.signal.unit_impulse` was added to conveniently generate an impulse function.

The function `scipy.signal.iirnotch` was added to design second-order IIR notch filters that can be used to remove a frequency component from a signal. The dual function `scipy.signal.iirpeak` was added to compute the coefficients of a second-order IIR peak (resonant) filter.

The function `scipy.signal.minimum_phase` was added to convert linear-phase FIR filters to minimum phase.

The functions `scipy.signal.upfirdn` and `scipy.signal.resample_poly` are now substantially faster when operating on some n-dimensional arrays when $n > 1$. The largest reduction in computation time is realized in cases where the size of the array is small (<1k samples or so) along the axis to be filtered.

scipy.fftpack improvements

Fast Fourier transform routines now accept `np.float16` inputs and upcast them to `np.float32`. Previously, they would raise an error.

scipy.cluster improvements

Methods "centroid" and "median" of `scipy.cluster.hierarchy.linkage` have been significantly sped up. Long-standing issues with using `linkage` on large input data (over 16 GB) have been resolved.

scipy.sparse improvements

The functions `scipy.sparse.save_npz` and `scipy.sparse.load_npz` were added, providing simple serialization for some sparse formats.

The `prune` method of classes `bsr_matrix`, `csc_matrix`, and `csr_matrix` was updated to reallocate backing arrays under certain conditions, reducing memory usage.

The methods `argmin` and `argmax` were added to classes `coo_matrix`, `csc_matrix`, `csr_matrix`, and `bsr_matrix`.

New function `scipy.sparse.csgraph.structural_rank` computes the structural rank of a graph with a given sparsity pattern.

New function `scipy.sparse.linalg.spsolve_triangular` solves a sparse linear system with a triangular left hand side matrix.

scipy.special improvements

Scalar, typed versions of universal functions from `scipy.special` are available in the Cython space via `cimport` from the new module `scipy.special.cython_special`. These scalar functions can be expected to be significantly faster than the universal functions for scalar arguments. See the `scipy.special` tutorial for details.

Better control over special-function errors is offered by the functions `scipy.special.geterr` and `scipy.special.seterr` and the context manager `scipy.special.errstate`.

The names of orthogonal polynomial root functions have been changed to be consistent with other functions relating to orthogonal polynomials. For example, `scipy.special.j_roots` has been renamed `scipy.special.roots_jacobi` for consistency with the related functions `scipy.special.jacobi` and `scipy.special.eval_jacobi`. To preserve back-compatibility the old names have been left as aliases.

Wright Omega function is implemented as `scipy.special.wrightomega`.

scipy.stats improvements

The function `scipy.stats.weightedtau` was added. It provides a weighted version of Kendall's tau.

New class `scipy.stats.multinomial` implements the multinomial distribution.

New class `scipy.stats.rv_histogram` constructs a continuous univariate distribution with a piecewise linear CDF from a binned data sample.

New class `scipy.stats.argus` implements the Argus distribution.

scipy.interpolate improvements

New class `scipy.interpolate.BSpline` represents splines. `BSpline` objects contain knots and coefficients and can evaluate the spline. The format is consistent with FITPACK, so that one can do, for example:

```
>>> t, c, k = splrep(x, y, s=0)
>>> spl = BSpline(t, c, k)
>>> np.allclose(spl(x), y)
```

`spl*` functions, `scipy.interpolate.splev`, `scipy.interpolate.splint`, `scipy.interpolate.splder` and `scipy.interpolate.splantider`, accept both `BSpline` objects and `(t, c, k)` tuples for backwards compatibility.

For multidimensional splines, `c.ndim > 1`, `BSpline` objects are consistent with piecewise polynomials, `scipy.interpolate.PPoly`. This means that `BSpline` objects are not immediately consistent with `scipy.interpolate.splprep`, and one *cannot* do `>>> BSpline(*splprep([x, y])[0])`. Consult the `scipy.interpolate` test suite for examples of the precise equivalence.

In new code, prefer using `scipy.interpolate.BSpline` objects instead of manipulating `(t, c, k)` tuples directly.

New function `scipy.interpolate.make_interp_spline` constructs an interpolating spline given data points and boundary conditions.

New function `scipy.interpolate.make_lsq_spline` constructs a least-squares spline approximation given data points.

scipy.integrate improvements

Now `scipy.integrate.fixed_quad` supports vector-valued functions.

3.21.2 Deprecated features

`scipy.interpolate.splmake`, `scipy.interpolate.spleval` and `scipy.interpolate.spline` are deprecated. The format used by `splmake/spleval` was inconsistent with `splrep/splev` which was confusing to users.

`scipy.special.errprint` is deprecated. Improved functionality is available in `scipy.special.seterr`.

calling `scipy.spatial.distance.pdist` or `scipy.spatial.distance.cdist` with arguments not needed by the chosen metric is deprecated. Also, metrics “`old_cosine`” and “`old_cos`” are deprecated.

3.21.3 Backwards incompatible changes

The deprecated `scipy.weave` submodule was removed.

`scipy.spatial.distance.squareform` now returns arrays of the same dtype as the input, instead of always float64.

`scipy.special.errprint` now returns a boolean.

The function `scipy.signal.find_peaks_cwt` now returns an array instead of a list.

`scipy.stats.kendalltau` now computes the correct p-value in case the input contains ties. The p-value is also identical to that computed by `scipy.stats.mstats.kendalltau` and by R. If the input does not contain ties there is no change w.r.t. the previous implementation.

The function `scipy.linalg.block_diag` will not ignore zero-sized matrices anymore. Instead it will insert rows or columns of zeros of the appropriate size. See gh-4908 for more details.

3.21.4 Other changes

SciPy wheels will now report their dependency on `numpy` on all platforms. This change was made because Numpy wheels are available, and because the pip upgrade behavior is finally changing for the better (use `--upgrade-strategy=only-if-needed` for `pip >= 8.2`; that behavior will become the default in the next major version of pip).

Numerical values returned by `scipy.interpolate.interp1d` with `kind="cubic"` and `"quadratic"` may change relative to previous scipy versions. If your code depended on specific numeric values (i.e., on implementation details of the interpolators), you may want to double-check your results.

3.21.5 Authors

- @endolith
- Max Argus +
- Hervé Audren
- Alessandro Pietro Bardelli +
- Michael Benfield +
- Felix Berkenkamp

- Matthew Brett
- Per Brodtkorb
- Evgeni Burovski
- Pierre de Buyl
- CJ Carey
- Brandon Carter +
- Tim Cera
- Klesk Chonkin
- Christian Häggström +
- Luca Citi
- Peadar Coyle +
- Daniel da Silva +
- Greg Dooper +
- John Draper +
- drlvk +
- David Ellis +
- Yu Feng
- Baptiste Fontaine +
- Jed Frey +
- Siddhartha Gandhi +
- Wim Glenn +
- Akash Goel +
- Christoph Gohlke
- Ralf Gommers
- Alexander Goncarenco +
- Richard Gowers +
- Alex Griffing
- Radoslaw Guzinski +
- Charles Harris
- Callum Jacob Hays +
- Ian Henriksen
- Randy Heydon +
- Lindsey Hiltner +
- Gerrit Holl +
- Hiroki IKEDA +
- jfinkels +

- Mher Kazandjian +
- Thomas Keck +
- keuj6 +
- Kornel Kielczewski +
- Sergey B Kirpichev +
- Vasily Kokorev +
- Eric Larson
- Denis Laxalde
- Gregory R. Lee
- Josh Lefler +
- Julien Lhermitte +
- Evan Limanto +
- Jin-Guo Liu +
- Nikolay Mayorov
- Geordie McBain +
- Josue Melka +
- Matthieu Melot
- michaelmartin15 +
- Surhud More +
- Brett M. Morris +
- Chris Mutel +
- Paul Nation
- Andrew Nelson
- David Nicholson +
- Aaron Nielsen +
- Joel Nothman
- nrrrk +
- Juan Nunez-Iglesias
- Mikhail Pak +
- Gavin Parnaby +
- Thomas Pingel +
- Ilhan Polat +
- Aman Pratik +
- Sebastian Pucilowski
- Ted Pudlik
- puenka +

- Eric Quintero
- Tyler Reddy
- Joscha Reimer
- Antonio Horta Ribeiro +
- Edward Richards +
- Roman Ring +
- Rafael Rossi +
- Colm Ryan +
- Sami Salonen +
- Alvaro Sanchez-Gonzalez +
- Johannes Schmitz
- Kari Schoonbee
- Yurii Shevchuk +
- Jonathan Siebert +
- Jonathan Tammo Siebert +
- Scott Sievert +
- Sourav Singh
- Byron Smith +
- Srikiran +
- Samuel St-Jean +
- Yoni Teitelbaum +
- Bhavika Tekwani
- Martin Thoma
- timbalam +
- Svend Vanderveken +
- Sebastiano Vigna +
- Aditya Vijaykumar +
- Santi Villalba +
- Ze Vinicius
- Pauli Virtanen
- Matteo Visconti
- Yusuke Watanabe +
- Warren Weckesser
- Phillip Weinberg +
- Nils Werner
- Jakub Wilk

- Josh Wilson
- wirew0rm +
- David Wolever +
- Nathan Woods
- ybeltukov +
- G Young
- Evgeny Zhurko +

A total of 121 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 0.19.0

- #1767: Function definitions in `__fitpack.h` should be moved. (Trac #1240)
- #1774: `_kmeans` chokes on large thresholds (Trac #1247)
- #2089: Integer overflows cause segfault in linkage function with large...
- #2190: Are odd-length window functions supposed to be always symmetrical?...
- #2251: `solve_discrete_are` in `scipy.linalg` does (sometimes) not solve...
- #2580: `scipy.interpolate.UnivariateSpline` (or a new superclass of it)...
- #2592: `scipy.stats.anderson` assumes `gumbel_1`
- #3054: `scipy.linalg.eig` does not handle infinite eigenvalues
- #3160: multinomial pmf / logpmf
- #3904: `scipy.special.ellipj` dn wrong values at quarter period
- #4044: Inconsistent code book initialization in `kmeans`
- #4234: `scipy.signal.flatop` documentation doesn't list a source for...
- #4831: Bugs in C code in `__quadpack.h`
- #4908: bug: unnessesary validity check for block dimension in `scipy.sparse.block_diag`
- #4917: BUG: indexing error for sparse matrix with `ix_`
- #4938: Docs on extending `ndimage` need to be updated.
- #5056: sparse matrix element-wise multiplying dense matrix returns dense...
- #5337: Formula in documentation for `correlate` is wrong
- #5537: use `OrderedDict` in `io.netcdf`
- #5750: [doc] missing data index value in `KDTree`, `cKDTree`
- #5755: p-value computation in `scipy.stats.kendalltau()` in broken in...
- #5757: BUG: Incorrect complex output of `signal.spectrogram`
- #5964: ENH: expose scalar versions of `scipy.special` functions to cython
- #6107: `scipy.cluster.hierarchy.single` segmentation fault with `2**16`...
- #6278: `optimize.basinhopping` should take a `RandomState` object

- #6296: InterpolatedUnivariateSpline: check_finite fails when w is unspecified
- #6306: Anderson-Darling bad results
- #6314: scipy.stats.kendalltau() p value not in agreement with R, SPSS...
- #6340: Curve_fit bounds and maxfev
- #6377: expm_multiply, complex matrices not working using start,stop,etc...
- #6382: optimize.differential_evolution stopping criterion has unintuitive...
- #6391: Global Benchmarking times out at 600s.
- #6397: mmwrite errors with large (but still 64-bit) integers
- #6413: scipy.stats.dirichlet computes multivariate gaussian differential...
- #6428: scipy.stats.mstats.mode modifies input
- #6440: Figure out ABI break policy for scipy.special Cython API
- #6441: Using Qhull for halfspace intersection : segfault
- #6442: scipy.spatial : In incremental mode volume is not recomputed
- #6451: Documentation for scipy.cluster.hierarchy.to_tree is confusing...
- #6490: interp1d (kind=zero) returns wrong value for rightmost interpolation...
- #6521: scipy.stats.entropy does *not* calculate the KL divergence
- #6530: scipy.stats.spearmanr unexpected NaN handling
- #6541: Test runner does not run scipy._lib/tests?
- #6552: BUG: misc.bytescale returns unexpected results when using cmin/cmax...
- #6556: RectSphereBivariateSpline(u, v, r) fails if min(v) >= pi
- #6559: Differential_evolution maxiter causing memory overflow
- #6565: Coverage of spectral functions could be improved
- #6628: Incorrect parameter name in binomial documentation
- #6634: Expose LAPACK's xGESVX family for linalg.solve ill-conditioned...
- #6657: Confusing documentation for `scipy.special.sph_harm`
- #6676: optimize: Incorrect size of Jacobian returned by `minimize(...)`
- #6681: add a new context manager to wrap `scipy.special.seterr`
- #6700: BUG: scipy.io.wavfile.read stays in infinite loop, warns on wav...
- #6721: scipy.special.chebyt(N) throw a 'TypeError' when N > 64
- #6727: Documentation for scipy.stats.norm.fit is incorrect
- #6764: Documentation for scipy.spatial.Delaunay is partially incorrect
- #6811: scipy.spatial.SphericalVoronoi fails for large number of points
- #6841: spearmanr fails when nan_policy='omit' is set
- #6869: Currently in gaussian_kde, the logpdf function is calculated...
- #6875: SLSQP inconsistent handling of invalid bounds
- #6876: Python stopped working (Segfault?) with minimum/maximum filter...

- #6889: dblquad gives different results under scipy 0.17.1 and 0.18.1
- #6898: BUG: dblquad ignores error tolerances
- #6901: Solving sparse linear systems in CSR format with complex values
- #6903: issue in spatial.distance.pdist docstring
- #6917: Problem in passing drop_rule to scipy.sparse.linalg.spilu
- #6926: signature mismatches for LowLevelCallable
- #6961: Scipy contains shebang pointing to /usr/bin/python and /bin/bash...
- #6972: BUG: special: *generate_ufuncs.py* is broken
- #6984: Assert raises test failure for test_ill_condition_warning
- #6990: BUG: sparse: Bad documentation of the *k* argument in *sparse.linalg.eigs*
- #6991: Division by zero in linregress()
- #7011: possible speed improvment in rv_continuous.fit()
- #7015: Test failure with Python 3.5 and numpy master
- #7055: SciPy 0.19.0rc1 test errors and failures on Windows
- #7096: macOS test failues for test_solve_continuous_are
- #7100: test_distance.test_Xdist_deprecated_args test error in 0.19.0rc2

Pull requests for 0.19.0

- #2908: Scipy 1.0 Roadmap
- #3174: add b-splines
- #4606: ENH: Add a unit impulse waveform function
- #5608: Adds keyword argument to choose faster convolution method
- #5647: ENH: Faster count_neighbour in cKDTree / + weighted input data
- #6021: Netcdf append
- #6058: ENH: scipy.signal - Add stft and istft
- #6059: ENH: More accurate signal.freqresp for zpk systems
- #6195: ENH: Cython interface for special
- #6234: DOC: Fixed a typo in ward() help
- #6261: ENH: add docstring and clean up code for signal.normalize
- #6270: MAINT: special: add tests for cdflib
- #6271: Fix for scipy.cluster.hierarchy.is_isomorphic
- #6273: optimize: rewrite while loops as for loops
- #6279: MAINT: Bessel tweaks
- #6291: Fixes gh-6219: remove runtime warning from genextreme distribution
- #6294: STY: Some PEP8 and cleaning up imports in stats/_continuous_distns.py
- #6297: Clarify docs in misc/__init__.py

- #6300: ENH: sparse: Loosen input validation for *diags* with empty inputs
- #6301: BUG: standardizes `check_finite` behavior re optional weights,...
- #6303: Fixing example in `_lazyselct` docstring.
- #6307: MAINT: more improvements to `gammmainc/gammmaincc`
- #6308: Clarified documentation of hypergeometric distribution.
- #6309: BUG: stats: Improve calculation of the Anderson-Darling statistic.
- #6315: ENH: Descending order of `x` in `PPoly`
- #6317: ENH: stats: Add support for `nan_policy` to `stats.median_test`
- #6321: TST: fix a typo in test name
- #6328: ENH: `sosfreqz`
- #6335: Define `LinregressResult` outside of `linregress`
- #6337: In `anderson test`, added support for right skewed gumbel distribution.
- #6341: Accept several spellings for the `curve_fit` max number of function...
- #6342: DOC: cluster: clarify hierarchy.linkage usage
- #6352: DOC: removed `brentq` from its own 'see also'
- #6362: ENH: stats: Use explicit formulas for `sf`, `logsf`, etc in `weibull...`
- #6369: MAINT: special: add a comment to `hyp0f1_complex`
- #6375: Added the multinomial distribution.
- #6387: MAINT: special: improve accuracy of `ellipj`'s *dn* at quarter...
- #6388: BenchmarkGlobal - getting it to work in Python3
- #6394: ENH: `scipy.sparse`: add save and load functions for sparse matrices
- #6400: MAINT: moves global benchmark run from `setup_cache` to `track_all`
- #6403: ENH: seed kwd for `basinhopping`. Closes #6278
- #6404: ENH: signal: added `irrnotch` and `iirpeak` functions.
- #6406: ENH: special: extend *sicilshichi* to complex arguments
- #6407: ENH: Window functions should not accept non-integer or negative...
- #6408: MAINT: `_differentialevolution` now uses `_lib._util.check_random_state`
- #6427: MAINT: Fix `gmpy` build & test that `mpmath` uses `gmpy`
- #6439: MAINT: `ndimage`: update callback function `c` api
- #6443: BUG: Fix volume computation in incremental mode
- #6447: Fixes issue #6413 - Minor documentation fix in the entropy function...
- #6448: ENH: Add halfspace mode to `Qhull`
- #6449: ENH: `rtol` and `atol` for `differential_evolution` termination fixes...
- #6453: DOC: Add some See Also links between similar functions
- #6454: DOC: `linalg`: clarify callable signature in *ordqz*
- #6457: ENH: spatial: enable non-double dtypes in `squareform`

- #6459: BUG: Complex matrices not handled correctly by `expm_multiply...`
- #6465: TST DOC Window docs, tests, etc.
- #6469: ENH: `linalg`: better handling of infinite eigenvalues in `eig/eigvals`
- #6475: DOC: calling `interp1d/interp2d` with NaNs is undefined
- #6477: Document magic numbers in `optimize.py`
- #6481: TST: Suppress some warnings from `test_windows`
- #6485: DOC: `spatial`: correct typo in `procrustes`
- #6487: Fix Bray-Curtis formula in `pdist` docstring
- #6493: ENH: Add covariance functionality to `scipy.optimize.curve_fit`
- #6494: ENH: `stats`: Use `log1p()` to improve some calculations.
- #6495: BUG: Use MST algorithm instead of SLINK for single linkage clustering
- #6497: MRG: Add `minimum_phase` filter function
- #6505: reset `scipy.signal.resample` window shape to 1-D
- #6507: BUG: `linkage`: Raise exception if `y` contains non-finite elements
- #6509: ENH: `_lib`: add common machinery for low-level callback functions
- #6520: `scipy.sparse.base.__mul__` non-numpy/scipy objects with 'shape'...
- #6522: Replace `kl_div` by `rel_entr` in `entropy`
- #6524: DOC: add `next_fast_len` to list of functions
- #6527: DOC: Release notes to reflect the new covariance feature in `optimize.curve_fit`
- #6532: ENH: Simplify `_cos_win`, document it, add `symmetric/periodic` arg
- #6535: MAINT: `sparse.csgraph`: updating old cython loops
- #6540: DOC: add to documentation of orthogonal polynomials
- #6544: TST: Ensure tests for `scipy._lib` are run by `scipy.test()`
- #6546: updated docstring of `stats.linregress`
- #6553: committed changes that I originally submitted for `scipy.signal.cspline...`
- #6561: BUG: modify `signal.find_peaks_cwt()` to return array and accept...
- #6562: DOC: Negative binomial distribution clarification
- #6563: MAINT: be more liberal in requiring numpy
- #6567: MAINT: use `xrange` for iteration in `differential_evolution` fixes...
- #6572: BUG: "`sp.linalg.solve_discrete_are`" fails for random data
- #6578: BUG: `misc`: allow both `cmin/cmax` and `low/high` params in `bytescale`
- #6581: Fix some unfortunate typos
- #6582: MAINT: `linalg`: make handling of infinite eigenvalues in `ordqz...`
- #6585: DOC: `interpolate`: correct `seealso` links to `ndimage`
- #6588: Update docstring of `scipy.spatial.distance_matrix`
- #6592: DOC: Replace 'first' by 'smallest' in `mode`

- #6593: MAINT: remove `scipy.weave` submodule
- #6594: DOC: `distance.squareform`: fix html docs, add note about dtype...
- #6598: [DOC] Fix incorrect error message in `medfilt2d`
- #6599: MAINT: `linalg`: turn a `solve_discrete_are` test back on
- #6600: DOC: Add SOS goals to roadmap
- #6601: DEP: Raise minimum `numpy` version to 1.8.2
- #6605: MAINT: 'new' module is deprecated, don't use it
- #6607: DOC: add note on change in wheel dependency on `numpy` and `pip`...
- #6609: Fixes #6602 - Typo in docs
- #6616: ENH: generalization of continuous and discrete Riccati solvers...
- #6621: DOC: improve `cluster.hierarchy` docstrings.
- #6623: CS matrix prune method should copy data from large unpruned arrays
- #6625: DOC: special: complete documentation of `eval_*` functions
- #6626: TST: special: silence some deprecation warnings
- #6631: fix parameter name doc for discrete distributions
- #6632: MAINT: stats: change some instances of `special` to `sc`
- #6633: MAINT: `refguide`: py2k long integers are equal to py3k integers
- #6638: MAINT: change type declaration in `cluster.linkage`, prevent overflow
- #6640: BUG: fix issue with duplicate values used in `cluster.vq.kmeans`
- #6641: BUG: fix corner case in `cluster.vq.kmeans` for large thresholds
- #6643: MAINT: clean up truncation modes of dendrogram
- #6645: MAINT: special: rename `*_roots` functions
- #6646: MAINT: clean up `mpmath` imports
- #6647: DOC: add `sqrt` to Mahalanobis description for `pdist`
- #6648: DOC: special: add a section on `cython_special` to the tutorial
- #6649: ENH: Added `scipy.spatial.distance.directed_hausdorff`
- #6650: DOC: add Sphinx roles for DOI and arXiv links
- #6651: BUG: `mstats`: make sure `mode(..., None)` does not modify its input
- #6652: DOC: special: add section to tutorial on functions not in special
- #6653: ENH: special: add the Wright Omega function
- #6656: ENH: don't coerce input to double with custom metric in `cdist`...
- #6658: Faster/shorter code for computation of discordances
- #6659: DOC: special: make `__init__` summaries and html summaries match
- #6661: `general.rst`: Fix a typo
- #6664: TST: Spectral functions' window correction factor
- #6665: [DOC] Conditions on `v` in `RectSphereBivariateSpline`

- #6668: DOC: Mention negative masses for center of mass
- #6675: MAINT: special: remove outdated README
- #6677: BUG: Fixes computation of p-values.
- #6679: BUG: optimize: return correct Jacobian for method ‘SLSQP’ in...
- #6680: ENH: Add structural rank to sparse.csgraph
- #6686: TST: Added Airspeed Velocity benchmarks for SphericalVoronoi
- #6687: DOC: add section “deciding on new features” to developer guide.
- #6691: ENH: Clearer error when fmin_slsqp obj doesn’t return scalar
- #6702: TST: Added airspeed velocity benchmarks for scipy.spatial.distance.cdist
- #6707: TST: interpolate: test fitpack wrappers, not _impl
- #6709: TST: fix a number of test failures on 32-bit systems
- #6711: MAINT: move function definitions from __fitpack.h to _fitpackmodule.c
- #6712: MAINT: clean up wishlist in stats.morestats, and copyright statement.
- #6715: DOC: update the release notes with BSpline et al.
- #6716: MAINT: scipy.io.wavfile: No infinite loop when trying to read...
- #6717: some style cleanup
- #6723: BUG: special: cast to float before in-place multiplication in...
- #6726: address performance regressions in interp1d
- #6728: DOC: made code examples in *integrate* tutorial copy-pasteable
- #6731: DOC: scipy.optimize: Added an example for wrapping complex-valued...
- #6732: MAINT: cython_special: remove *errprint*
- #6733: MAINT: special: fix some pyflakes warnings
- #6734: DOC: sparse.linalg: fixed matrix description in *bicgstab* doc
- #6737: BLD: update *cythonize.py* to detect changes in pxi files
- #6740: DOC: special: some small fixes to docstrings
- #6741: MAINT: remove dead code in interpolate.py
- #6742: BUG: fix `linalg.block_diag` to support zero-sized matrices.
- #6744: ENH: interpolate: make `PPoly.from_spline` accept BSpline objects
- #6746: DOC: special: clarify use of Condon-Shortley phase in *sph_harmllpmv*
- #6750: ENH: sparse: avoid densification on broadcasted elem-wise mult
- #6751: sinm doc explained cosm
- #6753: ENH: special: allow for more fine-tuned error handling
- #6759: Move `logsumexp` and `pade` from `scipy.misc` to `scipy.special` and...
- #6761: ENH: `argmax` and `argmin` methods for sparse matrices
- #6762: DOC: Improve docstrings of sparse matrices
- #6763: ENH: Weighted tau

- #6768: ENH: cythonized spherical Voronoi region polygon vertex sorting
- #6770: Correction of Delaunay class' documentation
- #6775: ENH: Integrating LAPACK "expert" routines with conditioning warnings...
- #6776: MAINT: Removing the trivial f2py warnings
- #6777: DOC: Update `rv_continuous.fit` doc.
- #6778: MAINT: `cluster.hierarchy`: Improved wording of error msgs
- #6786: BLD: increase minimum Cython version to 0.23.4
- #6787: DOC: expand on `linalg.block_diag` changes in 0.19.0 release...
- #6789: ENH: Add further documentation for `norm.fit`
- #6790: MAINT: Fix a potential problem in `nn_chain` linkage algorithm
- #6791: DOC: Add examples to `scipy.ndimage.fourier`
- #6792: DOC: fix some `numpydoc` / `Sphinx` issues.
- #6793: MAINT: fix circular import after moving functions out of `misc`
- #6796: TST: test importing each submodule. Regression test for gh-6793.
- #6799: ENH: stats: Argus distribution
- #6801: ENH: stats: Histogram distribution
- #6803: TST: make sure tests for `_build_utils` are run.
- #6804: MAINT: more fixes in `loggamma`
- #6806: ENH: Faster linkage for 'centroid' and 'median' methods
- #6810: ENH: speed up `upfirdn` and `resample_poly` for n-dimensional arrays
- #6812: TST: Added `ConvexHull` `asv` benchmark code
- #6814: ENH: Different extrapolation modes for different dimensions in...
- #6826: Signal spectral window default fix
- #6828: BUG: `SphericalVoronoi` Space Complexity (Fixes #6811)
- #6830: `RealData` docstring correction
- #6834: DOC: Added reference for `skewtest` function. See #6829
- #6836: DOC: Added `mode='mirror'` in the docstring for the functions accepting...
- #6838: MAINT: `sparse`: start removing old BSR methods
- #6844: handle incompatible dimensions when input is not an `ndarray` in...
- #6847: Added `maxiter` to golden search.
- #6850: BUG: added check for optional param `scipy.stats.spearmanr`
- #6858: MAINT: Removing redundant tests
- #6861: DEP: Fix escape sequences deprecated in Python 3.6.
- #6862: DOC: `dx` should be float, not int
- #6863: updated documentation `curve_fit`
- #6866: DOC : added some documentation to `j1` referring to `spherical_jn`

- #6867: DOC: cdist move long examples list into Notes section
- #6868: BUG: Make stats.mode return a ModeResult namedtuple on empty...
- #6871: Corrected documentation.
- #6874: ENH: gaussian_kde.logpdf based on logsumexp
- #6877: BUG: ndimage: guard against footprints of all zeros
- #6881: python 3.6
- #6885: Vectorized integrate.fixed_quad
- #6886: fixed typo
- #6891: TST: fix failures for linalg.dare/care due to tightened test...
- #6892: DOC: fix a bunch of Sphinx errors.
- #6894: TST: Added asv benchmarks for scipy.spatial.Voronoi
- #6908: BUG: Fix return dtype for complex input in spsolve
- #6909: ENH: fftpack: use float32 routines for float16 inputs.
- #6911: added min/max support to binned_statistic
- #6913: Fix 6875: SLSQP raise ValueError for all invalid bounds.
- #6914: DOCS: GH6903 updating docs of Spatial.distance.pdist
- #6916: MAINT: fix some issues for 32-bit Python
- #6924: BLD: update Bento build for scipy.LowLevelCallable
- #6932: ENH: Use OrderedDict in io.netcdf. Closes gh-5537
- #6933: BUG: fix LowLevelCallable issue on 32-bit Python.
- #6936: BUG: sparse: handle size-1 2D indexes correctly
- #6938: TST: fix test failures in special on 32-bit Python.
- #6939: Added attributes list to cKDTree docstring
- #6940: improve efficiency of dok_matrix.tocoo
- #6942: DOC: add link to liac-arff package in the io.arff docstring.
- #6943: MAINT: Docstring fixes and an additional test for linalg.solve
- #6944: DOC: Add example of odeint with a banded Jacobian to the integrate...
- #6946: ENH: hypergeom.logpmf in terms of betaln
- #6947: TST: speedup distance tests
- #6948: DEP: Deprecate the keyword "debug" from linalg.solve
- #6950: BUG: Correctly treat large integers in MMIO (fixes #6397)
- #6952: ENH: Minor user-friendliness cleanup in LowLevelCallable
- #6956: DOC: improve description of 'output' keyword for convolve
- #6957: ENH more informative error in sparse.bmat
- #6962: Shebang fixes
- #6964: DOC: note argmin/argmax addition

- #6965: BUG: Fix issues passing error tolerances in `dblquad` and `tplquad`.
- #6971: fix the docstring of `signaltools.correlate`
- #6973: Silence expected numpy warnings in `scipy.ndimage.interpolation.zoom()`
- #6975: BUG: special: fix regex in `generate_ufuncs.py`
- #6976: Update docstring for `griddata`
- #6978: Avoid division by zero in zoom factor calculation
- #6979: BUG: ARE solvers did not check the generalized case carefully
- #6985: ENH: sparse: add `scipy.sparse.linalg.spsolve_triangular`
- #6994: MAINT: spatial: updates to plotting utils
- #6995: DOC: Bad documentation of `k` in `sparse.linalg.eigs` See #6990
- #6997: TST: Changed the test with a less singular example
- #7000: DOC: clarify `interp1d` 'zero' argument
- #7007: BUG: Fix division by zero in `linregress()` for 2 data points
- #7009: BUG: Fix problem in passing `drop_rule` to `scipy.sparse.linalg.spilu`
- #7012: speed improvement in `_distn_infrastructure.py`
- #7014: Fix Typo: add a single quotation mark to fix a slight typo
- #7021: MAINT: stats: use machine constants from `np.finfo`, not `machar`
- #7026: MAINT: update `.mailmap`
- #7032: Fix layout of `rv_histogram` docs
- #7035: DOC: update 0.19.0 release notes
- #7036: ENH: Add more boundary options to `signal.stft`
- #7040: TST: stats: skip too slow tests
- #7042: MAINT: sparse: speed up `setdiag` tests
- #7043: MAINT: refactor and code cleaning `Xdist`
- #7053: Fix msvc 9 and 10 compile errors
- #7060: DOC: updated release notes with #7043 and #6656
- #7062: MAINT: Change default STFT boundary kwarg to "zeros"
- #7064: Fix `ValueError`: path is on mount 'X:', start on mount 'D:' on...
- #7067: TST: Fix `PermissionError`: [Errno 13] Permission denied on Windows
- #7068: TST: Fix `UnboundLocalError`: local variable 'data' referenced...
- #7069: Fix `OverflowError`: Python int too large to convert to C long...
- #7071: TST: silence `RuntimeWarning` for nan test of `stats.spearmanr`
- #7072: Fix `OverflowError`: Python int too large to convert to C long...
- #7084: TST: `linalg`: bump tolerance in `test_falker`
- #7095: TST: `linalg`: bump more tolerances in `test_falker`
- #7101: TST: Relax `solve_continuous_are` test case 2 and 12

- #7106: BUG: stop cdist “correlation” modifying input
- #7116: Backports to 0.19.0rc2

3.22 SciPy 0.18.1 Release Notes

SciPy 0.18.1 is a bug-fix release with no new features compared to 0.18.0.

3.22.1 Authors

- @kleskjr
- Evgeni Burovski
- CJ Carey
- Luca Citi +
- Yu Feng
- Ralf Gommers
- Johannes Schmitz +
- Josh Wilson
- Nathan Woods

A total of 9 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 0.18.1

- #6357: scipy 0.17.1 piecewise cubic hermite interpolation does not return...
- #6420: circmean() changed behaviour from 0.17 to 0.18
- #6421: scipy.linalg.solve_banded overwrites input ‘b’ when the inversion...
- #6425: cKDTree INF bug
- #6435: scipy.stats.ks_2samp returns different values on different computers
- #6458: Error in scipy.integrate.dblquad when using variable integration...

Pull requests for 0.18.1

- #6405: BUG: sparse: fix elementwise divide for CSR/CSC
- #6431: BUG: result for insufficient neighbours from cKDTree is wrong.
- #6432: BUG Issue #6421: scipy.linalg.solve_banded overwrites input ‘b’...
- #6455: DOC: add links to release notes
- #6462: BUG: interpolate: fix .roots method of PchipInterpolator
- #6492: BUG: Fix regression in dblquad: #6458
- #6543: fix the regression in circmean

- #6545: Revert gh-5938, restore ks_2samp
- #6557: Backports for 0.18.1

3.23 SciPy 0.18.0 Release Notes

Contents

- *SciPy 0.18.0 Release Notes*
 - *New features*
 - * `scipy.integrate` improvements
 - * `scipy.interpolate` improvements
 - * `scipy.fftpack` improvements
 - * `scipy.signal` improvements
 - *Discrete-time linear systems*
 - * `scipy.sparse` improvements
 - * `scipy.optimize` improvements
 - * `scipy.stats` improvements
 - *Random matrices*
 - * `scipy.linalg` improvements
 - * `scipy.spatial` improvements
 - * `scipy.cluster` improvements
 - * `scipy.special` improvements
 - *Deprecated features*
 - *Backwards incompatible changes*
 - * `scipy.optimize`
 - * `scipy.ndimage`
 - * `scipy.stats`
 - * `scipy.io`
 - * `scipy.interpolate`
 - *Other changes*
 - *Authors*
 - * *Issues closed for 0.18.0*
 - * *Pull requests for 0.18.0*

SciPy 0.18.0 is the culmination of 6 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and

optimizations. Moreover, our development attention will now shift to bug-fix releases on the 0.19.x branch, and on adding new features on the master branch.

This release requires Python 2.7 or 3.4-3.5 and NumPy 1.7.1 or greater.

Highlights of this release include:

- A new ODE solver for two-point boundary value problems, `scipy.optimize.solve_bvp`.
- A new class, `CubicSpline`, for cubic spline interpolation of data.
- N-dimensional tensor product polynomials, `scipy.interpolate.NdPPoly`.
- Spherical Voronoi diagrams, `scipy.spatial.SphericalVoronoi`.
- Support for discrete-time linear systems, `scipy.signal.dlti`.

3.23.1 New features

`scipy.integrate` improvements

A solver of two-point boundary value problems for ODE systems has been implemented in `scipy.integrate.solve_bvp`. The solver allows for non-separated boundary conditions, unknown parameters and certain singular terms. It finds a C1 continuous solution using a fourth-order collocation algorithm.

`scipy.interpolate` improvements

Cubic spline interpolation is now available via `scipy.interpolate.CubicSpline`. This class represents a piecewise cubic polynomial passing through given points and C2 continuous. It is represented in the standard polynomial basis on each segment.

A representation of n-dimensional tensor product piecewise polynomials is available as the `scipy.interpolate.NdPPoly` class.

Univariate piecewise polynomial classes, `PPoly` and `Bpoly`, can now be evaluated on periodic domains. Use `extrapolate="periodic"` keyword argument for this.

`scipy.fftpack` improvements

`scipy.fftpack.next_fast_len` function computes the next “regular” number for FFTPACK. Padding the input to this length can give significant performance increase for `scipy.fftpack.fft`.

`scipy.signal` improvements

Resampling using polyphase filtering has been implemented in the function `scipy.signal.resample_poly`. This method upsamples a signal, applies a zero-phase low-pass FIR filter, and downsamples using `scipy.signal.upfirdn` (which is also new in 0.18.0). This method can be faster than FFT-based filtering provided by `scipy.signal.resample` for some signals.

`scipy.signal.firls`, which constructs FIR filters using least-squares error minimization, was added.

`scipy.signal.sosfiltfilt`, which does forward-backward filtering like `scipy.signal.filtfilt` but for second-order sections, was added.

Discrete-time linear systems

`scipy.signal.dlti` provides an implementation of discrete-time linear systems. Accordingly, the `StateSpace`, `TransferFunction` and `ZerosPolesGain` classes have learned a the new keyword, `dt`, which can be used to create discrete-time instances of the corresponding system representation.

`scipy.sparse` improvements

The functions `sum`, `max`, `mean`, `min`, `transpose`, and `reshape` in `scipy.sparse` have had their signatures augmented with additional arguments and functionality so as to improve compatibility with analogously defined functions in `numpy`.

Sparse matrices now have a `count_nonzero` method, which counts the number of nonzero elements in the matrix. Unlike `getnnz()` and `nnz` property, which return the number of stored entries (the length of the data attribute), this method counts the actual number of non-zero entries in data.

`scipy.optimize` improvements

The implementation of Nelder-Mead minimization, `scipy.minimize(..., method="Nelder-Mead")`, obtained a new keyword, `initial_simplex`, which can be used to specify the initial simplex for the optimization process.

Initial step size selection in CG and BFGS minimizers has been improved. We expect that this change will improve numeric stability of optimization in some cases. See pull request gh-5536 for details.

Handling of infinite bounds in SLSQP optimization has been improved. We expect that this change will improve numeric stability of optimization in the some cases. See pull request gh-6024 for details.

A large suite of global optimization benchmarks has been added to `scipy/benchmarks/go_benchmark_functions`. See pull request gh-4191 for details.

Nelder-Mead and Powell minimization will now only set defaults for maximum iterations or function evaluations if neither limit is set by the caller. In some cases with a slow converging function and only 1 limit set, the minimization may continue for longer than with previous versions and so is more likely to reach convergence. See issue gh-5966.

`scipy.stats` improvements

Trapezoidal distribution has been implemented as `scipy.stats.trapz`. Skew normal distribution has been implemented as `scipy.stats.skewnorm`. Burr type XII distribution has been implemented as `scipy.stats.burr12`. Three- and four-parameter kappa distributions have been implemented as `scipy.stats.kappa3` and `scipy.stats.kappa4`, respectively.

New `scipy.stats.iqr` function computes the interquartile region of a distribution.

Random matrices

`scipy.stats.special_ortho_group` and `scipy.stats.ortho_group` provide generators of random matrices in the SO(N) and O(N) groups, respectively. They generate matrices in the Haar distribution, the only uniform distribution on these group manifolds.

`scipy.stats.random_correlation` provides a generator for random correlation matrices, given specified eigenvalues.

scipy.linalg improvements

`scipy.linalg.svd` gained a new keyword argument, `lapack_driver`. Available drivers are `gesdd` (default) and `gesvd`.

`scipy.linalg.lapack.ilaver` returns the version of the LAPACK library SciPy links to.

scipy.spatial improvements

Boolean distances, `scipy.spatial.pdist`, have been sped up. Improvements vary by the function and the input size. In many cases, one can expect a speed-up of $\times 2$ – $\times 10$.

New class `scipy.spatial.SphericalVoronoi` constructs Voronoi diagrams on the surface of a sphere. See pull request gh-5232 for details.

scipy.cluster improvements

A new clustering algorithm, the nearest neighbor chain algorithm, has been implemented for `scipy.cluster.hierarchy.linkage`. As a result, one can expect a significant algorithmic improvement ($O(N^2)$ instead of $O(N^3)$) for several linkage methods.

scipy.special improvements

The new function `scipy.special.loggamma` computes the principal branch of the logarithm of the Gamma function. For real input, `loggamma` is compatible with `scipy.special.gammaln`. For complex input, it has more consistent behavior in the complex plane and should be preferred over `gammaln`.

Vectorized forms of spherical Bessel functions have been implemented as `scipy.special.spherical_jn`, `scipy.special.spherical_kn`, `scipy.special.spherical_in` and `scipy.special.spherical_yn`. They are recommended for use over `sph_*` functions, which are now deprecated.

Several special functions have been extended to the complex domain and/or have seen domain/stability improvements. This includes `spence`, `digamma`, `log1p` and several others.

3.23.2 Deprecated features

The cross-class properties of *lti* systems have been deprecated. The following properties/setters will raise a *DeprecationWarning*:

Name - (accessing/setting raises warning) - (setting raises warning) * StateSpace - (*num*, *den*, *gain*) - (*zeros*, *poles*) * TransferFunction (*A*, *B*, *C*, *D*, *gain*) - (*zeros*, *poles*) * ZerosPolesGain (*A*, *B*, *C*, *D*, *num*, *den*) - ()

Spherical Bessel functions, `sph_in`, `sph_jn`, `sph_kn`, `sph_yn`, `sph_jnyn` and `sph_inkn` have been deprecated in favor of `scipy.special.spherical_jn` and `spherical_kn`, `spherical_yn`, `spherical_in`.

The following functions in `scipy.constants` are deprecated: `C2K`, `K2C`, `C2F`, `F2C`, `F2K` and `K2F`. They are superseded by a new function `scipy.constants.convert_temperature` that can perform all those conversions plus to/from the Rankine temperature scale.

3.23.3 Backwards incompatible changes

`scipy.optimize`

The convergence criterion for `optimize.bisect`, `optimize.brentq`, `optimize.brenth`, and `optimize.ridder` now works the same as `numpy.allclose`.

`scipy.ndimage`

The offset in `ndimage.interpolation.affine_transform` is now consistently added after the matrix is applied, independent of if the matrix is specified using a one-dimensional or a two-dimensional array.

`scipy.stats`

`stats.ks_2samp` used to return nonsensical values if the input was not real or contained nans. It now raises an exception for such inputs.

Several deprecated methods of `scipy.stats` distributions have been removed: `est_loc_scale`, `vecfunc`, `veccdf` and `vec_generic_moment`.

Deprecated functions `nanmean`, `nanstd` and `nanmedian` have been removed from `scipy.stats`. These functions were deprecated in scipy 0.15.0 in favor of their `numpy` equivalents.

A bug in the `rvs()` method of the distributions in `scipy.stats` has been fixed. When arguments to `rvs()` were given that were shaped for broadcasting, in many cases the returned random samples were not random. A simple example of the problem is `stats.norm.rvs(loc=np.zeros(10))`. Because of the bug, that call would return 10 identical values. The bug only affected code that relied on the broadcasting of the shape, location and scale parameters.

The `rvs()` method also accepted some arguments that it should not have. There is a potential for backwards incompatibility in cases where `rvs()` accepted arguments that are not, in fact, compatible with broadcasting. An example is

```
stats.gamma.rvs([2, 5, 10, 15], size=(2,2))
```

The shape of the first argument is not compatible with the requested size, but the function still returned an array with shape (2, 2). In scipy 0.18, that call generates a `ValueError`.

`scipy.io`

`scipy.io.netcdf` masking now gives precedence to the `_FillValue` attribute over the `missing_value` attribute, if both are given. Also, data are only treated as missing if they match one of these attributes exactly: values that differ by roundoff from `_FillValue` or `missing_value` are no longer treated as missing values.

`scipy.interpolate`

`scipy.interpolate.PiecewisePolynomial` class has been removed. It has been deprecated in scipy 0.14.0, and `scipy.interpolate.BPoly.from_derivatives` serves as a drop-in replacement.

3.23.4 Other changes

Scipy now uses `setuptools` for its builds instead of plain `distutils`. This fixes usage of `install_requires='scipy'` in the `setup.py` files of projects that depend on Scipy (see Numpy issue [gh-6551](#) for details). It potentially affects the way that build/install methods for Scipy itself behave though. Please report any unexpected behavior on the Scipy issue tracker.

PR [#6240](#) changes the interpretation of the `maxfun` option in *L-BFGS-B* based routines in the `scipy.optimize` module. An *L-BFGS-B* search consists of multiple iterations, with each iteration consisting of one or more function evaluations. Whereas the old search strategy terminated immediately upon reaching `maxfun` function evaluations, the new strategy allows the current iteration to finish despite reaching `maxfun`.

The bundled copy of Qhull in the `scipy.spatial` subpackage has been upgraded to version 2015.2.

The bundled copy of ARPACK in the `scipy.sparse.linalg` subpackage has been upgraded to `arpack-ng` 3.3.0.

The bundled copy of SuperLU in the `scipy.sparse` subpackage has been upgraded to version 5.1.1.

3.23.5 Authors

- @endolith
- @yanxun827 +
- @kleskjr +
- @MYheavyGo +
- @solarjoe +
- Gregory Allen +
- Gilles Aouizerate +
- Tom Augspurger +
- Henrik Bengtsson +
- Felix Berkenkamp
- Per Brodtkorb
- Lars Buitinck
- Daniel Bunting +
- Evgeni Burovski
- CJ Carey
- Tim Cera
- Grey Christoforo +
- Robert Cimrman
- Philip DeBoer +
- Yves Delley +
- Dávid Bodnár +
- Ion Elberdin +
- Gabriele Farina +

- Yu Feng
- Andrew Fowlie +
- Joseph Fox-Rabinovitz
- Simon Gibbons +
- Neil Girdhar +
- Kolja Glogowski +
- Christoph Gohlke
- Ralf Gommers
- Todd Goodall +
- Johnnie Gray +
- Alex Griffing
- Olivier Grisel
- Thomas Haslwanter +
- Michael Hirsch +
- Derek Homeier
- Golnaz Irannejad +
- Marek Jacob +
- InSuk Joung +
- Tetsuo Koyama +
- Eugene Krokshalev +
- Eric Larson
- Denis Laxalde
- Antony Lee
- Jerry Li +
- Henry Lin +
- Nelson Liu +
- Loïc Estève
- Lei Ma +
- Osvaldo Martin +
- Stefano Martina +
- Nikolay Mayorov
- Matthieu Melot +
- Sturla Molden
- Eric Moore
- Alistair Muldal +
- Maniteja Nandana

- Tavi Nathanson +
- Andrew Nelson
- Joel Nothman
- Behzad Nouri
- Nikolai Nowaczyk +
- Juan Nunez-Iglesias +
- Ted Pudlik
- Eric Quintero
- Yoav Ram
- Jonas Rauber +
- Tyler Reddy +
- Juha Remes
- Garrett Reynolds +
- Ariel Rokem +
- Fabian Rost +
- Bill Sacks +
- Jona Sassenhagen +
- Kari Schoonbee +
- Marcello Seri +
- Sourav Singh +
- Martin Spacek +
- Søren Fuglede Jørgensen +
- Bhavika Tekwani +
- Martin Thoma +
- Sam Tygier +
- Meet Udeshi +
- Utkarsh Upadhyay
- Bram Vandekerckhove +
- Sebastián Vanrell +
- Ze Vinicius +
- Pauli Virtanen
- Stefan van der Walt
- Warren Weckesser
- Jakub Wilk +
- Josh Wilson
- Phillip J. Wolfram +

- Nathan Woods
- Haochen Wu
- G Young +

A total of 99 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 0.18.0

- #1484: SVD using *GESVD lapack drivers (Trac #957)
- #1547: Inconsistent use of offset in `ndimage.interpolation.affine_transform()`...
- #1609: `special.hyp0f1` returns nan (Trac #1082)
- #1656: `fmin_slsqp` enhancement (Trac #1129)
- #2069: stats broadcasting in `rvs` (Trac #1544)
- #2165: `sph_jn` returns false results for some orders/values (Trac #1640)
- #2255: Incorrect order of translation and rotation in `affine_transform...`
- #2332: `hyp0f1` args and return values are unumpyic (Trac #1813)
- #2534: The sparse `.sum()` method with `uint8` dtype does not act like the...
- #3113: Implement `ufuncs` for `CSPHJY`, `SPHJ`, `SPHY`, `CSPHIK`, `SPHI`, `SPHIK...`
- #3568: SciPy 0.13.3 - CentOS5 - Errors in `test_arpack`
- #3581: `optimize`: `stepsize` in `fmin_bfgs` is “bad”
- #4476: `scipy.sparse` non-native endian bug
- #4484: `ftol` in `optimize.fmin` fails to work
- #4510: `sparsetools.cxx` `call_thunk` can segfault due to out of bounds...
- #5051: `ftol` and `xtol` for `_minimize_neldermead` are absolute instead of...
- #5097: proposal: spherical Voronoi diagrams
- #5123: Call to `scipy.sparse.coo_matrix` fails when passed Cython typed...
- #5220: `scipy.cluster.hierarchy`.`{ward,median,centroid}` does not work...
- #5379: Add a build step at the end of `.travis.yml` that uploads working...
- #5440: `scipy.optimize.basinhopping`: `accept_test` returning `numpy.bool_...`
- #5452: Error in `scipy.integrate.nquad` when using variable integration...
- #5520: Cannot inherit `csr_matrix` properly
- #5533: Kendall tau implementation uses Python mergesort
- #5553: `stats.tiecorrect` overflows
- #5589: Add the Type XII Burr distribution to `stats`.
- #5612: `sparse.linalg` factorizations slow for small `k` due to default...
- #5626: `io.netcdf` masking should use `masked_equal` rather than `masked_value`
- #5637: Simple cubic spline interpolation?

- #5683: BUG: Akima1DInterpolator may return nans given multidimensional...
- #5686: scipy.stats.ttest_ind_from_stats does not accept arrays
- #5702: scipy.ndimage.interpolation.affine_transform lacks documentation...
- #5718: Wrong computation of weighted minkowski distance in cdist
- #5745: move to setuptools for next release
- #5752: DOC: solve_discrete_lyapunov equation puts transpose in wrong...
- #5760: signal.ss2tf doesn't handle zero-order state-space models
- #5764: Hypergeometric function hyp0f1 behaves incorrectly for complex...
- #5814: stats NaN Policy Error message inconsistent with code
- #5833: docstring of stats.binom_test() needs an update
- #5853: Error in scipy.linalg.expm for complex matrix with shape (1,1)
- #5856: Specify Nelder-Mead initial simplex
- #5865: scipy.linalg.expm fails for certain numpy matrices
- #5915: optimize.basinhopping - variable referenced before assignment.
- #5916: LSQUnivariateSpline fitting failed with knots generated from...
- #5927: unicode vs. string comparison in scipy.stats.binned_statistic_dd
- #5936: faster implementation of ks_2samp
- #5948: csc matrix .mean returns single element matrix rather than scalar
- #5959: BUG: optimize test error for root when using lgmres
- #5972: Test failures for sparse sum tests on 32-bit Python
- #5976: Unexpected exception in scipy.sparse.bmat while using 0 x 0 matrix
- #6008: scipy.special.kl_div not available in 0.14.1
- #6011: The von-Mises entropy is broken
- #6016: python crashes for linalg.interpolative.svd with certain large...
- #6017: Wilcoxon signed-rank test with zero_method="pratt" or "zsplit"...
- #6028: stats.distributions does not have trapezoidal distribution
- #6035: Wrong link in f_oneway
- #6056: BUG: signal.decimate should only accept discrete LTI objects
- #6093: Precision error on Linux 32 bit with openblas
- #6101: Barycentric transforms test error on Python3, 32-bit Linux
- #6105: scipy.misc.face docstring is incorrect
- #6113: scipy.linalg.logm fails for a trivial matrix
- #6128: Error in dot method of sparse COO array, when used with numpy...
- #6132: Failures with latest MKL
- #6136: Failures on *master* with MKL
- #6162: fmin_l_bfgs_b returns inconsistent results ($f_{min} \neq f(x_{min})$) and...

- #6165: optimize.minimize infinite loop with Newton-CG
- #6167: incorrect distribution fitting for data containing boundary values.
- #6194: lstsq() and others detect numpy.complex256 as real
- #6216: ENH: improve accuracy of ppf cdf roundtrip for bradford
- #6217: BUG: weibull_min.logpdf return nan for c=1 and x=0
- #6218: Is there a method to cap shortest path search distances?
- #6222: PchipInterpolator no longer handles a 2-element array
- #6226: ENH: improve accuracy for logistic.ppf and logistic.isf
- #6227: ENH: improve accuracy for rayleigh.logpdf and rayleigh.logsf...
- #6228: ENH: improve accuracy of ppf cdf roundtrip for gumbel_l
- #6235: BUG: alpha.pdf and alpha.logpdf returns nan for x=0
- #6245: ENH: improve accuracy for ppf-cdf and sf-isf roundtrips for invgamma
- #6263: BUG: stats: Inconsistency in the multivariate_normal docstring
- #6292: Python 3 unorderable type errors in test_sparsetools.TestInt32Overflow
- #6316: TestCloughTocher2DInterpolator.test_dense crashes python3.5.2rc1_64bit...
- #6318: Scipy interp1d 'nearest' not working for high values on x-axis

Pull requests for 0.18.0

- #3226: DOC: Change *nb* and *na* to conventional *m* and *n*
- #3867: allow cKDTree.query taking a list input in *k*.
- #4191: ENH: Benchmarking global optimizers
- #4356: ENH: add PPoly.solve(*y*) for solving $p(x) == y$
- #4370: DOC separate boolean distance functions for clarity
- #4678: BUG: sparse: ensure index dtype is large enough to pass all parameters...
- #4881: scipy.signal: Add the class dlti for linear discrete-time systems...
- #4901: MAINT: add benchmark and improve docstring for signal.lfilter
- #5043: ENH: sparse: add count_nonzero method
- #5136: Attribute kurtosistest() to Anscombe & Glynn (1983)
- #5186: ENH: Port upfirdn
- #5232: ENH: adding spherical Voronoi diagram algorithm to scipy.spatial
- #5279: ENH: Bessel filters with different normalizations, high order
- #5384: BUG: Closes #5027 distance function always casts bool to double
- #5392: ENH: Add zero_phase kwarg to signal.decimate
- #5394: MAINT: sparse: non-canonical test cleanup and fixes
- #5424: DOC: add Scipy developers guide
- #5442: STY: PEP8 amendments

- #5472: Online QR in LGMRES
- #5526: BUG: stats: Fix broadcasting in the `rvs()` method of the distributions.
- #5530: MAINT: sparse: set `format` attr explicitly
- #5536: optimize: fix up `cg/bfgs` initial step sizes
- #5548: PERF: improves performance in `stats.kendalltau`
- #5549: ENH: Nearest-neighbor chain algorithm for hierarchical clustering
- #5554: MAINT/BUG: closes overflow bug in `stats.tiecorrect`
- #5557: BUG: modify `optimize.bisect` to achieve desired tolerance
- #5581: DOC: Tutorial for `least_squares`
- #5606: ENH: `differential_evolution` - moving core loop of `solve` method...
- #5609: [MRG] test against `numpy dev`
- #5611: use `setuptools` for `bdist_egg` distributions
- #5615: MAINT: `linalg`: tighten `_decomp_update` + special: remove unused...
- #5622: Add `SO(N)` rotation matrix generator
- #5623: ENH: special: Add vectorized spherical Bessel functions.
- #5627: Response to issue #5160, implements the skew normal distribution...
- #5628: DOC: Align the description and operation
- #5632: DOC: special: Expanded docs for Airy, elliptic, Bessel functions.
- #5633: MAINT: `linalg`: unchecked `malloc` in `_decomp_update`
- #5634: MAINT: optimize: tighten `_group_columns`
- #5640: Fixes for `io.netcdf` masking
- #5645: MAINT: size 0 vector handling in `cKDTree` range queries
- #5649: MAINT: update license text
- #5650: DOC: Clarify Exponent Order in `Itisys.py`
- #5651: DOC: Clarify Documentation for `scipy.special.gammaln`
- #5652: DOC: Fixed `scipy.special.betaln` Doc
- #5653: [MRG] ENH: `CubicSpline` interpolator
- #5654: ENH: `Burr12` distribution to `stats` module
- #5659: DOC: Define BEFORE/AFTER in `runtests.py -h` for `bench-compare`
- #5660: MAINT: remove functions deprecated before 0.16.0
- #5662: ENH: Circular statistic optimization
- #5663: MAINT: remove uses of `np.testing.rand`
- #5665: MAINT: `spatial`: remove matching distance implementation
- #5667: Change some HTTP links to HTTPS
- #5669: DOC: `zpk2sos` can't do `analog`, `array_like`, etc.
- #5670: Update `conf.py`

- #5672: MAINT: move a sample distribution to a subclass of `rv_discrete`
- #5678: MAINT: stats: remove `est_loc_scale` method
- #5679: MAINT: DRY up generic computations for discrete distributions
- #5680: MAINT: stop shadowing builtins in `stats.distributions`
- #5681: forward port ENH: Re-enable broadcasting of `fill_value`
- #5684: BUG: Fix `Akima1DInterpolator` returning nans
- #5690: BUG: fix `stats.ttest_ind_from_stats` to handle arrays.
- #5691: BUG: fix generator in `io._loadarff` to comply with PEP 0479
- #5693: ENH: use `math.factorial` for exact factorials
- #5695: DOC: `dx` might be a float, not only an integer
- #5699: MAINT: `io`: micro-optimize Matlab reading code for size
- #5701: Implement `OptimizeResult.__dir__`
- #5703: ENH: stats: make R^2 printing optional in `probplot`
- #5704: MAINT: typo `ouf`->`out`
- #5705: BUG: fix typo in `query_pairs`
- #5707: DOC: Add some explanation for `ftol` `xtol` in `scipy.optimize.fmin`
- #5708: DOC: `optimize`: PEP8 minimize docstring
- #5709: MAINT: optimize Cython code for speed and size
- #5713: [DOC] Fix broken link to reference
- #5717: DOC: `curve_fit` raises `RuntimeError` on failure.
- #5724: forward port gh-5720
- #5728: STY: remove a blank line
- #5729: ENH: `spatial`: speed up boolean distances
- #5732: MAINT: `differential_evolution` changes to default keywords `break...`
- #5733: TST: `differential_evolution` - population initiation tests
- #5736: Complex number support in `log1p`, `expm1`, and `xlog1py`
- #5741: MAINT: `sparse`: clean up extraction functions
- #5742: DOC: `signal`: Explain `fftbins` in `get_window`
- #5748: ENH: Add $O(N)$ random matrix generator
- #5749: ENH: Add polyphase resampling
- #5756: RFC: Bump the minimum numpy version, drop older python versions
- #5761: DOC: Some improvements to least squares docstrings
- #5762: MAINT: `spatial`: distance refactoring
- #5768: DOC: Fix `io.loadmat` docstring for `mdict` param
- #5770: BUG: Accept anything `np.dtype` can handle for a `dtype` in `sparse.random`
- #5772: Update `sparse.csgraph.laplacian` docstring

- #5777: BUG: fix special.hyp0f1 to work correctly for complex inputs.
- #5780: DOC: Update PIL error install URL
- #5781: DOC: Fix documentation on solve_discrete_lyapunov
- #5782: DOC: cKDTree and KDTree now reference each other
- #5783: DOC: Clarify finish behaviour in scipy.optimize.brute
- #5784: MAINT: Change default tolerances of least_squares to 1e-8
- #5787: BUG: Allow Processing of Zero Order State Space Models in signal.ss2tf
- #5788: DOC, BUG: Clarify and Enforce Input Types to 'Data' Objects
- #5789: ENH: sparse: speedup LIL matrix slicing (was #3338)
- #5791: DOC: README: remove coveralls.io
- #5792: MAINT: remove uses of deprecated np.random.random_integers
- #5794: fix affine_transform (fixes #1547 and #5702)
- #5795: DOC: Removed uniform method from kmeans2 doc
- #5797: DOC: Clarify the computation of weighted minkowski
- #5798: BUG: Ensure scipy's _asfarray returns ndarray
- #5799: TST: Mpmath testing patch
- #5801: allow reading of certain IDL 8.0 .sav files
- #5803: DOC: fix module name in error message
- #5804: DOC: special: Expanded docs for special functions.
- #5805: DOC: Fix order of returns in _spectral_helper
- #5806: ENH: sparse: vectorized coo_matrix.diagonal
- #5808: ENH: Added iqr function to compute IQR metric in scipy/stats/stats.py
- #5810: MAINT/BENCH: sparse: Benchmark cleanup and additions
- #5811: DOC: sparse.linalg: shape, not size
- #5813: Update sparse ARPACK functions min *ncv* value
- #5815: BUG: Error message contained wrong values
- #5816: remove dead code from stats tests
- #5820: "in"->"a" in order_filter docstring
- #5821: DOC: README: INSTALL.txt was renamed in 2014
- #5825: DOC: typo in the docstring of least_squares
- #5826: MAINT: sparse: increase test coverage
- #5827: NdPPoly rebase
- #5828: Improve numerical stability of hyp0f1 for large orders
- #5829: ENH: sparse: Add copy parameter to all .toXXX() methods in sparse...
- #5830: DOC: rework INSTALL.rst.txt
- #5831: Adds plotting options to voronoi_plot_2d

- #5834: Update stats.binom_test() docstring
- #5836: ENH, TST: Allow SIMO tf's for tf2ss
- #5837: DOC: Image examples
- #5838: ENH: sparse: add eliminate_zeros() to coo_matrix
- #5839: BUG: Fixed name of NumpyVersion.__repr__
- #5845: MAINT: Fixed typos in documentation
- #5847: Fix bugs in sparsertools
- #5848: BUG: sparse.linalg: add locks to ensure ARPACK threadsafety
- #5849: ENH: sparse.linalg: upgrade to superlu 5.1.1
- #5851: ENH: expose lapack's ilaver to python to allow lapack version...
- #5852: MAINT: runtests.py: ensure Ctrl-C interrupts the build
- #5854: DOC: Minor update to documentation
- #5855: Pr 5640
- #5859: ENH: Add random correlation matrix generator
- #5862: BUG: Allow expm for complex matrix with shape (1, 1)
- #5863: FIX: Fix test
- #5864: DOC: add a little note about the Normal survival function (Q-function)
- #5867: Fix for #5865
- #5869: extend normal distribution cdf to complex domain
- #5872: DOC: Note that morlet and cwt don't work together
- #5875: DOC: interp2d class description
- #5876: MAINT: spatial: remove a stray print statement
- #5878: MAINT: Fixed noisy UserWarnings in ndimage tests. Fixes #5877
- #5879: MAINT: sparse.linalg/superlu: add explicit casts to resolve compiler...
- #5880: MAINT: signal: import gcd from math and not fractions when on...
- #5887: Neldermead initial simplex
- #5894: BUG: _CustomLinearOperator unpicklable in python3.5
- #5895: DOC: special: slightly improve the multigammaln docstring
- #5900: Remove duplicate assignment.
- #5901: Update bundled ARPACK
- #5904: ENH: Make convolve and correlate order-agnostic
- #5905: ENH: sparse.linalg: further LGMRES cleanups
- #5906: Enhancements and cleanup in scipy.integrate (attempt #2)
- #5907: ENH: Change sparse sum and mean dtype casting to match...
- #5909: changes for convolution symmetry
- #5913: MAINT: basinhopping remove instance test closes #5440

- #5919: MAINT: uninitialised var if basinhopping niter=0. closes #5915
- #5920: BLD: Fix missing lsame.c error for MKL
- #5921: DOC: interpolate: add example showing how to work around issue...
- #5926: MAINT: spatial: upgrade to Qhull 2015.2
- #5928: MAINT: sparse: optimize DIA sum/diagonal, csgraph.laplacian
- #5929: Update info/URL for octave-maintainers discussion
- #5930: TST: special: silence DeprecationWarnings from sph_yn
- #5931: ENH: implement the principle branch of the logarithm of Gamma.
- #5934: Typo: “mush” => “must”
- #5935: BUG:string comparison stats._binned_statistic closes #5927
- #5938: Cythonize stats.ks_2samp for a ~33% gain in speed.
- #5939: DOC: fix optimize.fmin convergence docstring
- #5941: Fix minor typo in squareform docstring
- #5942: Update linregress stderr description.
- #5943: ENH: Improve numerical accuracy of lognorm
- #5944: Merge vonmises into stats pyx
- #5945: MAINT: interpolate: Tweak declaration to avoid cython warning...
- #5946: MAINT: sparse: clean up format conversion methods
- #5949: BUG: fix sparse .mean to return a scalar instead of a matrix
- #5955: MAINT: Replace calls to *hanning* with *hann*
- #5956: DOC: Missing periods interfering with parsing
- #5958: MAINT: add a test for lognorm.sf underflow
- #5961: MAINT _centered(): rename size to shape
- #5962: ENH: constants: Add multi-scale temperature conversion function
- #5965: ENH: special: faster way for calculating comb() for exact=True
- #5975: ENH: Improve FIR path of signal.decimate
- #5977: MAINT/BUG: sparse: remove overzealous bmat checks
- #5978: minimize_neldermead() stop at user requested maxiter or maxfev
- #5983: ENH: make sparse *sum* cast dtypes like NumPy *sum* for 32-bit...
- #5985: BUG, API: Add *jac* parameter to *curve_fit*
- #5989: ENH: Add firls least-squares fitting
- #5990: BUG: read tries to handle 20-bit WAV files but shouldn't
- #5991: DOC: Cleanup wav read/write docs and add tables for common types
- #5994: ENH: Add gesvd method for svd
- #5996: MAINT: Wave cleanup
- #5997: TST: Break up upfirdn tests & compare to lfilter

- #6001: Filter design docs
- #6002: COMPAT: Expand compatibility fromnumeric.py
- #6007: ENH: Skip conversion of TF to TF in freqresp
- #6009: DOC: fix incorrect versionadded for entr, rel_entr, kl_div
- #6013: Fixed the entropy calculation of the von Mises distribution.
- #6014: MAINT: make gamma, rgamma use loggamma for complex arguments
- #6020: WIP: ENH: add exact=True factorial for vectors
- #6022: Added 'lanczos' to the image interpolation function list.
- #6024: BUG: optimize: do not use dummy constraints in SLSQP when no...
- #6025: ENH: Boundary value problem solver for ODE systems
- #6029: MAINT: Future imports for optimize._lsq
- #6030: ENH: stats.trap - adding trapezoidal distribution closes #6028
- #6031: MAINT: Some improvements to optimize._numdiff
- #6032: MAINT: Add special/_comb.c to .gitignore
- #6033: BUG: check the requested approximation rank in interpolative.svd
- #6034: DOC: Doc for mannwhitneyu in stats.py corrected
- #6040: FIX: Edit the wrong link in f_oneway
- #6044: BUG: (ordqz) always increase parameter lwork by 1.
- #6047: ENH: extend special.spence to complex arguments.
- #6049: DOC: Add documentation of PR #5640 to the 0.18.0 release notes
- #6050: MAINT: small cleanups related to loggamma
- #6070: Add asarray to explicitly cast list to numpy array in wilcoxon...
- #6071: DOC: antialiasing filter and link decimate resample, etc.
- #6075: MAINT: reimplement special.digamma for complex arguments
- #6080: avoid multiple computation in kstest
- #6081: Clarified pearson correlation return value
- #6085: ENH: allow long indices of sparse matrix with umfpack in spsolve()
- #6086: fix description for associated Laguerre polynomials
- #6087: Corrected docstring of splrep.
- #6094: ENH: special: change zeta signature to zeta(x, q=1)
- #6095: BUG: fix integer overflow in special.spence
- #6106: Fixed Issue #6105
- #6116: BUG: matrix logarithm edge case
- #6119: TST: DeprecationWarnings in stats on python 3.5 closes #5885
- #6120: MAINT: sparse: clean up sputils.isintlike
- #6122: DOC: optimize: linprog docs should say minimize instead of maximize

- #6123: DOC: optimize: document the *fun* field in `scipy.optimize.OptimizeResult`
- #6124: Move FFT zero-padding calculation from signaltools to fftpack
- #6125: MAINT: improve special.gammainc in the $a \sim x$ regime.
- #6130: BUG: sparse: Fix COO dot with zero columns
- #6138: ENH: stats: Improve behavior of `genextreme.sf` and `genextreme.isf`
- #6146: MAINT: simplify the `expit` implementation
- #6151: MAINT: special: make `generate_ufuncs.py` output deterministic
- #6152: TST: special: better test for `gammainc` at large arguments
- #6153: ENH: Make `next_fast_len` public and faster
- #6154: fix typo “mush”→”must”
- #6155: DOC: Fix some incorrect RST definition lists
- #6160: make `logsumexp` error out on a masked array
- #6161: added missing bracket to `rosen` documentation
- #6163: ENH: Added “kappa4” and “kappa3” distributions.
- #6164: DOC: Minor clean-up in `integrate._bvp`
- #6169: Fix `mpf_assert_allclose` to handle iterable results, such as maps
- #6170: Fix `pchip_interpolate` convenience function
- #6172: Corrected misplaced bracket in doc string
- #6175: ENH: `sparse.csgraph`: Pass indices to `shortest_path`
- #6178: TST: increase test coverage of `sf` and `isf` of a generalized extreme...
- #6179: TST: avoid a deprecation warning from numpy
- #6181: ENH: Boundary conditions for `CubicSpline`
- #6182: DOC: Add examples/graphs to `max_len_seq`
- #6183: BLD: update Bento build config files for recent changes.
- #6184: BUG: fix issue in `io/wavfile` for float96 input.
- #6186: ENH: Periodic extrapolation for `PPoly` and `BPoly`
- #6192: MRG: Add circle-CI
- #6193: ENH: sparse: avoid `setitem` densification
- #6196: Fixed missing `sqrt` in docstring of Mahalanobis distance in `cdist`,...
- #6206: MAINT: Minor changes in `solve_bvp`
- #6207: BUG: `linalg`: for BLAS, downcast `complex256` to `complex128`, not...
- #6209: BUG: `io.matlab`: avoid buffer overflows in `read_element_into`
- #6210: BLD: use `setuptools` when building.
- #6214: BUG: `sparse.linalg`: fix bug in LGMRES breakdown handling
- #6215: MAINT: special: make `loggamma` use `zdiv`
- #6220: DOC: Add parameter

- #6221: ENH: Improve Newton solver for solve_bvp
- #6223: pchip should work for length-2 arrays
- #6224: signal.lti: deprecate cross-class properties/setters
- #6229: BUG: optimize: avoid an infinite loop in Newton-CG
- #6230: Add example for application of gaussian filter
- #6236: MAINT: gumbel_l accuracy
- #6237: MAINT: rayleigh accuracy
- #6238: MAINT: logistic accuracy
- #6239: MAINT: bradford distribution accuracy
- #6240: MAINT: avoid bad fmin in l-bfgs-b due to maxfun interruption
- #6241: MAINT: weibull_min accuracy
- #6246: ENH: Add _support_mask to distributions
- #6247: fixed a print error for an example of ode
- #6249: MAINT: change x-axis label for stats.probplot to “theoretical...
- #6250: DOC: fix typos
- #6251: MAINT: constants: filter out test noise from deprecated conversions
- #6252: MAINT: io/arff: remove unused variable
- #6253: Add examples to scipy.ndimage.filters
- #6254: MAINT: special: fix some build warnings
- #6258: MAINT: inverse gamma distribution accuracy
- #6260: MAINT: signal.decimate - Use discrete-time objects
- #6262: BUG: odr: fix string formatting
- #6267: TST: fix some test issues in interpolate and stats.
- #6269: TST: fix some warnings in the test suite
- #6274: ENH: Add sosfiltfilt
- #6276: DOC: update release notes for 0.18.0
- #6277: MAINT: update the author name mapping
- #6282: DOC: Correcting references for scipy.stats.normaltest
- #6283: DOC: some more additions to 0.18.0 release notes.
- #6284: Add *versionadded::* directive to *loggamma*.
- #6285: BUG: stats: Inconsistency in the multivariate_normal docstring...
- #6290: Add author list, gh-lists to 0.18.0 release notes
- #6293: TST: special: relax a test’s precision
- #6295: BUG: sparse: stop comparing None and int in bsr_matrix constructor
- #6313: MAINT: Fix for python 3.5 travis-ci build problem.
- #6327: TST: signal: use assert_allclose for testing near-equality in...

- #6330: BUG: spatial/qhull: allocate qhT via malloc to ensure CRT likes...
- #6332: TST: fix stats.iqr test to not emit warnings, and fix line lengths.
- #6334: MAINT: special: fix a test for hyp0f1
- #6347: TST: spatial.qhull: skip a test on 32-bit platforms
- #6350: BUG: optimize/slsqp: don't overwrite an array out of bounds
- #6351: BUG: #6318 Interp1d 'nearest' integer x-axis overflow issue fixed
- #6355: Backports for 0.18.0

3.24 SciPy 0.17.1 Release Notes

SciPy 0.17.1 is a bug-fix release with no new features compared to 0.17.0.

3.24.1 Issues closed for 0.17.1

- #5817: BUG: skew, kurtosis return np.nan instead of "propagate"
- #5850: Test failed with sgelsy
- #5898: interpolate.interp1d crashes using float128
- #5953: Massive performance regression in cKDTree.query with L_inf distance...
- #6062: mannwhitneyu breaks backward compatibility in 0.17.0
- #6134: T test does not handle nans

3.24.2 Pull requests for 0.17.1

- #5902: BUG: interpolate: make interp1d handle np.float128 again
- #5957: BUG: slow down with p=np.inf in 0.17 cKDTree.query
- #5970: Actually propagate nans through stats functions with nan_policy="propagate"
- #5971: BUG: linalg: fix lwork check in *gelsy
- #6074: BUG: special: fixed violation of strict aliasing rules.
- #6083: BUG: Fix dtype for sum of linear operators
- #6100: BUG: Fix mannwhitneyu to be backward compatible
- #6135: Don't pass null pointers to LAPACK, even during workspace queries.
- #6148: stats: fix handling of nan values in T tests and kendalltau

3.25 SciPy 0.17.0 Release Notes

Contents

- *SciPy 0.17.0 Release Notes*
 - *New features*
 - * *scipy.cluster improvements*
 - * *scipy.io improvements*
 - * *scipy.optimize improvements*
 - *Linear assignment problem solver*
 - *Least squares optimization*
 - * *scipy.signal improvements*
 - * *scipy.stats improvements*
 - * *scipy.sparse improvements*
 - * *scipy.spatial improvements*
 - * *scipy.interpolate improvements*
 - * *scipy.linalg improvements*
 - *Deprecated features*
 - *Backwards incompatible changes*
 - *Other changes*
 - *Authors*
 - * *Issues closed for 0.17.0*
 - * *Pull requests for 0.17.0*

SciPy 0.17.0 is the culmination of 6 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Moreover, our development attention will now shift to bug-fix releases on the 0.17.x branch, and on adding new features on the master branch.

This release requires Python 2.6, 2.7 or 3.2-3.5 and NumPy 1.6.2 or greater.

Release highlights:

- New functions for linear and nonlinear least squares optimization with constraints: `scipy.optimize.lsq_linear` and `scipy.optimize.least_squares`
- Support for fitting with bounds in `scipy.optimize.curve_fit`.
- Significant improvements to `scipy.stats`, providing many functions with better handling of inputs which have NaNs or are empty, improved documentation, and consistent behavior between `scipy.stats` and `scipy.stats.mstats`.
- Significant performance improvements and new functionality in `scipy.spatial.cKDTree`.

3.25.1 New features

`scipy.cluster` improvements

A new function `scipy.cluster.hierarchy.cut_tree`, which determines a cut tree from a linkage matrix, was added.

`scipy.io` improvements

`scipy.io.mmwrite` gained support for symmetric sparse matrices.

`scipy.io.netcdf` gained support for masking and scaling data based on data attributes.

`scipy.optimize` improvements

Linear assignment problem solver

`scipy.optimize.linear_sum_assignment` is a new function for solving the linear sum assignment problem. It uses the Hungarian algorithm (Kuhn-Munkres).

Least squares optimization

A new function for *nonlinear* least squares optimization with constraints was added: `scipy.optimize.least_squares`. It provides several methods: Levenberg-Marquardt for unconstrained problems, and two trust-region methods for constrained ones. Furthermore it provides different loss functions. New trust-region methods also handle sparse Jacobians.

A new function for *linear* least squares optimization with constraints was added: `scipy.optimize.lsq_linear`. It provides a trust-region method as well as an implementation of the Bounded-Variable Least-Squares (BVLS) algorithm.

`scipy.optimize.curve_fit` now supports fitting with bounds.

`scipy.signal` improvements

A `mode` keyword was added to `scipy.signal.spectrogram`, to let it return other spectrograms than power spectral density.

`scipy.stats` improvements

Many functions in `scipy.stats` have gained a `nan_policy` keyword, which allows specifying how to treat input with NaNs in them: propagate the NaNs, raise an error, or omit the NaNs.

Many functions in `scipy.stats` have been improved to correctly handle input arrays that are empty or contain infs/nans.

A number of functions with the same name in `scipy.stats` and `scipy.stats.mstats` were changed to have matching signature and behavior. See [gh-5474](#) for details.

`scipy.stats.binom_test` and `scipy.stats.mannwhitneyu` gained a keyword alternative, which allows specifying the hypothesis to test for. Eventually all hypothesis testing functions will get this keyword.

For methods of many continuous distributions, complex input is now accepted.

Matrix normal distribution has been implemented as `scipy.stats.matrix_normal`.

scipy.sparse improvements

The `axis` keyword was added to sparse norms, `scipy.sparse.linalg.norm`.

scipy.spatial improvements

`scipy.spatial.cKDTree` was partly rewritten for improved performance and several new features were added to it:

- the `query_ball_point` method became significantly faster
- `query` and `query_ball_point` gained an `n_jobs` keyword for parallel execution
- `build` and `query` methods now release the GIL
- full pickling support
- support for periodic spaces
- the `sparse_distance_matrix` method can now return and sparse matrix type

scipy.interpolate improvements

Out-of-bounds behavior of `scipy.interpolate.interp1d` has been improved. Use a two-element tuple for the `fill_value` argument to specify separate fill values for input below and above the interpolation range. Linear and nearest interpolation kinds of `scipy.interpolate.interp1d` support extrapolation via the `fill_value="extrapolate"` keyword.

`fill_value` can also be set to an array-like (or a two-element tuple of array-likes for separate below and above values) so long as it broadcasts properly to the non-interpolated dimensions of an array. This was implicitly supported by previous versions of `scipy`, but support has now been formalized and gets compatibility-checked before use. For example, a set of `y` values to interpolate with shape `(2, 3, 5)` interpolated along the last axis (2) could accept a `fill_value` array with shape `()` (singleton), `(1,)`, `(2, 1)`, `(1, 3)`, `(3,)`, or `(2, 3)`; or it can be a 2-element tuple to specify separate below and above bounds, where each of the two tuple elements obeys proper broadcasting rules.

scipy.linalg improvements

The default algorithm for `scipy.linalg.leastsq` has been changed to use LAPACK's function `*gelsd`. Users wanting to get the previous behavior can use a new keyword `lapack_driver="gelss"` (allowed values are "gelss", "gelsd" and "gelsy").

`scipy.sparse` matrices and linear operators now support the `matmul` (`@`) operator when available (Python 3.5+). See [PEP 465](<https://legacy.python.org/dev/peps/pep-0465/>)

A new function `scipy.linalg.ordqz`, for QZ decomposition with reordering, has been added.

3.25.2 Deprecated features

`scipy.stats.histogram` is deprecated in favor of `np.histogram`, which is faster and provides the same functionality.

`scipy.stats.threshold` and `scipy.mstats.threshold` are deprecated in favor of `np.clip`. See issue #617 for details.

`scipy.stats.ss` is deprecated. This is a support function, not meant to be exposed to the user. Also, the name is unclear. See issue #663 for details.

`scipy.stats.square_of_sums` is deprecated. This too is a support function not meant to be exposed to the user. See issues #665 and #663 for details.

`scipy.stats.f_value`, `scipy.stats.f_value_multivariate`, `scipy.stats.f_value_wilks_lambda`, and `scipy.mstats.f_value_wilks_lambda` are deprecated. These are related to ANOVA, for which `scipy.stats` provides quite limited functionality and these functions are not very useful standalone. See issues #660 and #650 for details.

`scipy.stats.chisqprob` is deprecated. This is an alias. `stats.chi2.sf` should be used instead.

`scipy.stats.betainc` is deprecated. This is an alias for `special.betainc` which should be used instead.

3.25.3 Backwards incompatible changes

The functions `stats.triml` and `stats.trimboth` now make sure the elements trimmed are the lowest and/or highest, depending on the case. Slicing without at least partial sorting was previously done, but didn't make sense for unsorted input.

When `variable_names` is set to an empty list, `scipy.io.loadmat` now correctly returns no values instead of all the contents of the MAT file.

Element-wise multiplication of sparse matrices now returns a sparse result in all cases. Previously, multiplying a sparse matrix with a dense matrix or array would return a dense matrix.

The function `misc.lena` has been removed due to license incompatibility.

The constructor for `sparse.coo_matrix` no longer accepts `(None, (m, n))` to construct an all-zero matrix of shape `(m, n)`. This functionality was deprecated since at least 2007 and was already broken in the previous SciPy release. Use `coo_matrix((m, n))` instead.

The Cython wrappers in `linalg.cython_lapack` for the LAPACK routines `*gges`, `*gegv`, `*gelsx`, `*geqpf`, `*ggsvd`, `*ggsvp`, `*lahrd`, `*latzm`, `*tZRqf` have been removed since these routines are not present in the new LAPACK 3.6.0 release. With the exception of the routines `*ggsvd` and `*ggsvp`, these were all deprecated in favor of routines that are currently present in our Cython LAPACK wrappers.

Because the LAPACK `*gegv` routines were removed in LAPACK 3.6.0. The corresponding Python wrappers in `scipy.linalg.lapack` are now deprecated and will be removed in a future release. The source files for these routines have been temporarily included as a part of `scipy.linalg` so that SciPy can be built against LAPACK versions that do not provide these deprecated routines.

3.25.4 Other changes

Html and pdf documentation of development versions of Scipy is now automatically rebuilt after every merged pull request.

`scipy.constants` is updated to the CODATA 2014 recommended values.

Usage of `scipy.fftpack` functions within Scipy has been changed in such a way that `PyFFTW` can easily replace `scipy.fftpack` functions (with improved performance). See [gh-5295](#) for details.

The `imread` functions in `scipy.misc` and `scipy.ndimage` were unified, for which a `mode` argument was added to `scipy.misc.imread`. Also, bugs for 1-bit and indexed RGB image formats were fixed.

`runtests.py`, the development script to build and test Scipy, now allows building in parallel with `--parallel`.

3.25.5 Authors

- @cel4 +
- @chemelnuclin +
- @endolith
- @mamrehn +
- @tosh1ki +
- Joshua L. Adelman +
- Anne Archibald
- Hervé Audren +
- Vincent Barrielle +
- Bruno Beltran +
- Sumit Binnani +
- Joseph Jon Booker
- Olga Botvinnik +
- Michael Boyle +
- Matthew Brett
- Zaz Brown +
- Lars Buitinck
- Pete Bunch +
- Evgeni Burovski
- CJ Carey
- Ien Cheng +
- Cody +
- Jaime Fernandez del Rio
- Ales Erjavec +
- Abraham Escalante
- Yves-Rémi Van Eycke +

- Yu Feng +
- Eric Firing
- Francis T. O'Donovan +
- André Gaul
- Christoph Gohlke
- Ralf Gommers
- Alex Griffing
- Alexander Grigorievskiy
- Charles Harris
- Jörn Hees +
- Ian Henriksen
- Derek Homeier +
- David Menéndez Hurtado
- Gert-Ludwig Ingold
- Aakash Jain +
- Rohit Jamuar +
- Jan Schlüter
- Johannes Ballé
- Luke Zoltan Kelley +
- Jason King +
- Andreas Kopecky +
- Eric Larson
- Denis Laxalde
- Antony Lee
- Gregory R. Lee
- Josh Levy-Kramer +
- Sam Lewis +
- François Magimel +
- Martín Gaitán +
- Sam Mason +
- Andreas Mayer
- Nikolay Mayorov
- Damon McDougall +
- Robert McGibbon
- Sturla Molden
- Will Monroe +

- Eric Moore
- Maniteja Nandana
- Vikram Natarajan +
- Andrew Nelson
- Marti Nito +
- Behzad Nouri +
- Daisuke Oyama +
- Giorgio Patrini +
- Fabian Paul +
- Christoph Paulik +
- Mad Physicist +
- Irvin Probst
- Sebastian Pucilowski +
- Ted Pudlik +
- Eric Quintero
- Yoav Ram +
- Joscha Reimer +
- Juha Remes
- Frederik Rietdijk +
- Rémy Léone +
- Christian Sachs +
- Skipper Seabold
- Sebastian Skoupý +
- Alex Seewald +
- Andreas Sorge +
- Bernardo Sulzbach +
- Julian Taylor
- Louis Tiao +
- Utkarsh Upadhyay +
- Jacob Vanderplas
- Gael Varoquaux +
- Pauli Virtanen
- Fredrik Wallner +
- Stefan van der Walt
- James Webber +
- Warren Weckesser

- Raphael Wettinger +
- Josh Wilson +
- Nat Wilson +
- Peter Yin +

A total of 101 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 0.17.0

- #1923: problem with numpy 0's in stats.poisson.rvs (Trac #1398)
- #2138: scipy.misc.imread segfaults on 1 bit png (Trac #1613)
- #2237: distributions do not accept complex arguments (Trac #1718)
- #2282: scipy.special.hyp1f1(0.5, 1.5, -1000) fails (Trac #1763)
- #2618: poisson.pmf returns NaN if mu is 0
- #2957: hyp1f1 precision issue
- #2997: FAIL: test_qhull.TestUtilities.test_more_barycentric_transforms
- #3129: No way to set ranges for fitting parameters in Optimize functions
- #3191: interp1d should contain a fill_value_below and a fill_value_above...
- #3453: PchipInterpolator sets slopes at edges differently than Matlab's...
- #4106: ndimage._ni_support._normalize_sequence() fails with numpy.int64
- #4118: `scipy.integrate.ode.set_solout` called after `scipy.integrate.ode.set_initial_value` fails silently
- #4233: 1D scipy.interpolate.griddata using method=nearest produces nans...
- #4375: All tests fail due to bad file permissions
- #4580: scipy.ndimage.filters.convolve documentation is incorrect
- #4627: logsumexp with sign indicator - enable calculation with negative...
- #4702: logsumexp with zero scaling factor
- #4834: gammainc should return 1.0 instead of NaN for infinite x
- #4838: enh: exprel special function
- #4862: the scipy.special.boxcox function is inaccurate for denormal...
- #4887: Spherical harmonic incongruences
- #4895: some scipy ufuncs have inconsistent output dtypes?
- #4923: logm does not aggressively convert complex outputs to float
- #4932: BUG: stats: The *fit* method of the distributions silently ignores...
- #4956: Documentation error in `scipy.special.bi_zeros`
- #4957: Docstring for `pbvv_seq` is wrong
- #4967: block_diag should look at dtypes of all arguments, not only the...
- #5037: scipy.optimize.minimize error messages are printed to stdout...

- #5039: Cubic interpolation: On entry to DGESDD parameter number 12 had...
- #5163: Base case example of Hierarchical Clustering (offer)
- #5181: BUG: stats.genextreme.entropy should use the explicit formula
- #5184: Some? wheels don't express a numpy dependency
- #5197: mstats: test_kurtosis fails (ULP max is 2)
- #5260: Typo causing an error in splrep
- #5263: Default epsilon in rbf.py fails for colinear points
- #5276: Reading empty (no data) arff file fails
- #5280: 1d scipy.signal.convolve much slower than numpy.convolve
- #5326: Implementation error in scipy.interpolate.PchipInterpolator
- #5370: Test issue with test_quadpack and libm.so as a linker script
- #5426: ERROR: test_stats.test_chisquare_masked_arrays
- #5427: Automate installing correct numpy versions in numpy-vendor image
- #5430: Python3 : Numpy scalar types "not iterable"; specific instance...
- #5450: BUG: spatial.ConvexHull triggers a seg. fault when given nans.
- #5478: clarify the relation between matrix normal distribution and *multivariate_normal*
- #5539: lstsq related test failures on windows binaries from numpy-vendor
- #5560: doc: scipy.stats.burr pdf issue
- #5571: lstsq test failure after lapack_driver change
- #5577: ordqz segfault on Python 3.4 in Wine
- #5578: scipy.linalg test failures on python 3 in Wine
- #5607: Overloaded 'isnan(double&)' is ambiguous when compiling with...
- #5629: Test for lstsq randomly failed
- #5630: memory leak with scipy 0.16 spatial cKDtree
- #5689: isnan errors compiling scipy/special/Faddeeva.cc with clang++
- #5694: fftpack test failure in test_import
- #5719: curve_fit(method!="lm") ignores initial guess

Pull requests for 0.17.0

- #3022: hyp1f1: better handling of large negative arguments
- #3107: ENH: Add ordered QZ decomposition
- #4390: ENH: Allow axis and keepdims arguments to be passed to scipy.linalg.norm.
- #4671: ENH: add axis to sparse norms
- #4796: ENH: Add cut tree function to scipy.cluster.hierarchy
- #4809: MAINT: cauchy moments are undefined
- #4821: ENH: stats: make distribution instances picklable

- #4839: ENH: Add `scipy.special.exprel` relative error exponential ufunc
- #4859: Logsumexp fixes - allows sign flags and `b==0`
- #4865: BUG: `scipy.io.mmio.write`: error with big indices and low precision
- #4869: add `as_inexact` option to `_lib._util._asarray_validated`
- #4884: ENH: Finite difference approximation of Jacobian matrix
- #4890: ENH: Port `cKDTree` query methods to C++, allow pickling on Python...
- #4892: how much doctesting is too much?
- #4896: MAINT: work around a possible numpy ufunc loop selection bug
- #4898: MAINT: A bit of pyflakes-driven cleanup.
- #4899: ENH: add 'alternative' keyword to hypothesis tests in stats
- #4903: BENCH: Benchmarks for interpolate module
- #4905: MAINT: prepend underscore to `mask_to_limits`; delete `masked_var`.
- #4906: MAINT: Benchmarks for `optimize.leastsq`
- #4910: WIP: Trimmed statistics functions have inconsistent API.
- #4912: MAINT: fix typo in stats tutorial. Closes gh-4911.
- #4914: DEP: deprecate `scipy.stats.ss` and `scipy.stats.square_of_sums`.
- #4924: MAINT: if the imaginary part of `logm` of a real matrix is small,...
- #4930: BENCH: Benchmarks for signal module
- #4941: ENH: update `find_repeats`.
- #4942: MAINT: use `np.float64_t` instead of `np.float_t` in `cKDTree`
- #4944: BUG: integer overflow in `correlate_nd`
- #4951: do not ignore invalid kwargs in distributions fit method
- #4958: Add some detail to docstrings for special functions
- #4961: ENH: `stats.describe`: add bias kw and empty array handling
- #4963: ENH: `scipy.sparse.coo.coo_matrix.__init__`: less memory needed
- #4968: DEP: deprecate `stats.f_value*` and `mstats.f_value*` functions.
- #4969: ENH: review `stats.relfreq` and `stats.cumfreq`; fixes to `stats.histogram`
- #4971: Extend github source links to line ranges
- #4972: MAINT: improve the error message in `validate_runtests_log`
- #4976: DEP: deprecate `scipy.stats.threshold`
- #4977: MAINT: more careful dtype treatment in block diagonal matrix...
- #4979: ENH: distributions, complex arguments
- #4984: clarify dirichlet distribution error handling
- #4992: ENH: `stats.fligner` and `stats.bartlett` empty input handling.
- #4996: DOC: fix `stats.spearmanr` docs
- #4997: Fix up `boxcox` for underflow / loss of precision

- #4998: DOC: improved documentation for *stats.ppc_max*
- #5000: ENH: added empty input handling *scipy.moment*; doc enhancements
- #5003: ENH: improves rankdata algorithm
- #5005: *scipy.stats*: numerical stability improvement
- #5007: ENH: nan handling in functions that use *stats._chk_asarray*
- #5009: remove *coveralls.io*
- #5010: Hypergeometric distribution log survival function
- #5014: Patch to compute the volume and area of convex hulls
- #5015: DOC: Fix mistaken variable name in *sawtooth*
- #5016: DOC: resample example
- #5017: DEP: deprecate *stats.betai* and *stats.chisqprob*
- #5018: ENH: Add test on random input to volume computations
- #5026: BUG: Fix return dtype of *lil_matrix.getnnz(axis=0)*
- #5030: DOC: resample slow for prime output too
- #5033: MAINT: integrate, special: remove unused RIMACH and Makefile
- #5034: MAINT: signal: lift *max_len_seq* validation out of Cython
- #5035: DOC/MAINT: *refguide / doctest* drudgery
- #5041: BUG: fixing some small memory leaks detected by *cppcheck*
- #5044: [GSoC] ENH: New least-squares algorithms
- #5050: MAINT: C fixes, trimmed a lot of dead code from Cephes
- #5057: ENH: sparse: avoid densifying on sparse/dense elementwise mult
- #5058: TST: stats: add a sample distribution to the test loop
- #5061: ENH: spatial: faster 2D Voronoi and Convex Hull plotting
- #5065: TST: improve test coverage for *stats.mvsdist* and *stats.bayes_mvs*
- #5066: MAINT: *fitpack*: remove a noop
- #5067: ENH: empty and nan input handling for *stats.kstat* and *stats.kstatvar*
- #5071: DOC: optimize: Correct paper reference, add doi
- #5072: MAINT: *scipy.sparse* cleanup
- #5073: DOC: special: Add an example showing the relation of *diric* to...
- #5075: DOC: clarified parameterization of *stats.lognorm*
- #5076: use *int*, *float*, *bool* instead of *np.int*, *np.float*, *np.bool*
- #5078: DOC: Rename *fitpack* docs to README
- #5081: BUG: Correct handling of scalar 'b' in *lsqr* and *lsqr*
- #5082: *loadmat* *variable_names*: don't confuse [] and None.
- #5083: Fix *integrate.fixed_quad* docstring to indicate None return value
- #5086: Use *solve()* instead of *inv()* for *gaussian_kde*

- #5090: MAINT: stats: add explicit `_sf`, `_isf` to gengamma distribution
- #5094: ENH: `scipy.interpolate.NearestNDInterpolator`: cKDTree configurable
- #5098: DOC: special: fix typesetting in `*_roots` quadrature functions
- #5099: DOC: make the docstring of `stats.moment` raw
- #5104: DOC/ENH fixes and micro-optimizations for `scipy.linalg`
- #5105: enh: made `l-bfgs-b` parameter for the maximum number of line search...
- #5106: TST: add NIST test cases to `stats.f_oneway`
- #5110: [GSoC]: Bounded linear least squares
- #5111: MAINT: special: Cephes cleanup
- #5118: BUG: FIR path failed if `len(x) < len(b)` in `lfilter`.
- #5124: ENH: move the filliben approximation to a publicly visible function
- #5126: StatisticsCleanup: `stats.kruskal` review
- #5130: DOC: update PyPi trove classifiers. Beta -> Stable. Add license.
- #5131: DOC: `differential_evolution`, improve docstring for mutation and...
- #5132: MAINT: `differential_evolution` improve `init_population_lhs` comments...
- #5133: MRG: rebased `mmio` refactoring
- #5135: MAINT: `stats.mstats` consistency with `stats.stats`
- #5139: TST: `linalg`: add a smoke test for gh-5039
- #5140: EHN: Update `constants.codata` to CODATA 2014
- #5145: added `ValueError` to docstring as possible error raised
- #5146: MAINT: Improve implementation details and doc in `stats.shapiro`
- #5147: [GSoC] ENH: Upgrades to `curve_fit`
- #5150: Fix misleading `wavelets/cwt` example
- #5152: BUG: `cluster.hierarchy.dendrogram`: missing font size doesn't...
- #5153: add keywords to control the summation in discrete distributions...
- #5156: DOC: added comments on algorithms used in Legendre function
- #5158: ENH: `optimize`: add the Hungarian algorithm
- #5162: FIX: Remove `lena`
- #5164: MAINT: fix `cluster.hierarchy.dendrogram` issues and docs
- #5166: MAINT: changed `stats.pointbiserialr` to delegate to `stats.pearsonr`
- #5167: ENH: add `nan_policy` to `stats.kendalltau`.
- #5168: TST: added nist test case (Norris) to `stats.linregress`.
- #5169: update `lpmv` docstring
- #5171: Clarify metric parameter in `linkage` docstring
- #5172: ENH: add `mode` keyword to `signal.spectrogram`
- #5177: DOC: graphical example for `KDTree.query_ball_point`

- #5179: MAINT: stats: tweak the formula for `ncx2.pdf`
- #5188: MAINT: `linalg`: A bit of clean up.
- #5189: BUG: stats: Use the explicit formula in `stats.genextreme.entropy`
- #5193: BUG: fix uninitialized use in `lartg`
- #5194: BUG: properly return error to fortran from `ode_jacobian_function`
- #5198: TST: Fix `TestCtypesQuad` failure on Python 3.5 for Windows
- #5201: allow extrapolation in `interp1d`
- #5209: MAINT: Change complex parameter to boolean in `Y_()`
- #5213: BUG: sparse: fix logical comparison dtype conflicts
- #5216: BUG: sparse: fixing unbound local error
- #5218: DOC and BUG: Bessel function docstring improvements, fix `array_like,...`
- #5222: MAINT: sparse: fix COO ctor
- #5224: DOC: optimize: type of `OptimizeResult.hess_inv` varies
- #5228: ENH: Add `maskandscale` support to `netcdf`; based on `pupynere` and...
- #5229: DOC: `sparse.linalg.svds` doc typo fixed
- #5234: MAINT: sparse: simplify COO ctor
- #5235: MAINT: sparse: warn on `todia()` with many diagonals
- #5236: MAINT: `ndimage`: simplify thread handling/recursion + constness
- #5239: BUG: `integrate`: Fixed issue 4118
- #5241: `qr_insert` fixes, closes #5149
- #5246: Doctest tutorial files
- #5247: DOC: optimize: typo/import fix in `linear_sum_assignment`
- #5248: remove `inspect.getargspec` and test python 3.5 on Travis CI
- #5250: BUG: Fix sparse multiply by single-element zero
- #5261: Fix bug causing a `TypeError` in `splrep` when a runtime warning...
- #5262: Follow up to 4489 (Addition LAPACK routines in `linalg.lstsq`)
- #5264: ignore zero-length edges for default epsilon
- #5269: DOC: Typos and spell-checking
- #5272: MAINT: `signal`: Convert array syntax to memoryviews
- #5273: DOC: raw strings for docstrings with math
- #5274: MAINT: sparse: update cython code for MST
- #5278: BUG: io: Stop guessing the data delimiter in ARFF files.
- #5289: BUG: misc: Fix the Pillow work-around for 1-bit images.
- #5291: ENH: call `np.correlate` for 1d in `scipy.signal.correlate`
- #5294: DOC: special: Remove a potentially misleading example from the...
- #5295: Simplify replacement of `fftpack` by `pyfftw`

- #5296: ENH: Add matrix normal distribution to stats
- #5297: Fixed leaf_rotation and leaf_font_size in Python 3
- #5303: MAINT: stats: rewrite find_repeats
- #5307: MAINT: stats: remove unused Fortran routine
- #5313: BUG: sparse: fix diags for nonsquare matrices
- #5315: MAINT: special: Cephes cleanup
- #5316: fix input check for sparse.linalg.svds
- #5319: MAINT: Cython code maintenance
- #5328: BUG: Fix place_poles return values
- #5329: avoid a spurious divide-by-zero in Student t stats
- #5334: MAINT: integrate: miscellaneous cleanup
- #5340: MAINT: Printing Error Msg to STDERR and Removing iterate.dat
- #5347: ENH: add Py3.5-style matmul operator (e.g. $A @ B$) to sparse linear...
- #5350: FIX error, when reading 32-bit float wav files
- #5351: refactor the PCHIP interpolant's algorithm
- #5354: MAINT: construct csr and csc matrices from integer lists
- #5359: add a fast path to interp1d
- #5364: Add two fill_values to interp1d.
- #5365: ABCD docstrings
- #5366: Fixed typo in the documentation for scipy.signal.cwt() per #5290.
- #5367: DOC updated scipy.spatial.Delaunay example
- #5368: ENH: Do not create a throwaway class at every function call
- #5372: DOC: spectral: fix reference formatting
- #5375: PEP8 amendments to fftpack_basic.py
- #5377: BUG: integrate: builtin name no longer shadowed
- #5381: PEP8ified fftpack_pseudo_diffs.py
- #5385: BLD: fix Bento build for changes to optimize and spatial
- #5386: STY: PEP8 amendments to interpolate.py
- #5387: DEP: deprecate stats.histogram
- #5388: REL: add "make upload" command to doc/Makefile.
- #5389: DOC: updated origin param of scipy.ndimage.filters.convolve
- #5395: BUG: special: fix a number of edge cases related to $x = np.inf$.
- #5398: MAINT: stats: avoid spurious warnings in lognorm.pdf(0, s)
- #5407: ENH: stats: Handle mu=0 in stats.poisson
- #5409: Fix the behavior of discrete distributions at the right-hand...
- #5412: TST: stats: skip a test to avoid a spurious log(0) warning

- #5413: BUG: linalg: work around LAPACK single-precision lwork computation...
- #5414: MAINT: stats: move creation of namedtuples outside of function...
- #5415: DOC: fix up sections in ToC in the pdf reference guide
- #5416: TST: fix issue with a ctypes test for integrate on Fedora.
- #5418: DOC: fix bugs in signal.TransferFunction docstring. Closes gh-5287.
- #5419: MAINT: sparse: fix usage of NotImplementedError
- #5420: Raise proper error if maxiter < 1
- #5422: DOC: changed documentation of brent to be consistent with bracket
- #5444: BUG: gaussian_filter, BPoly.from_derivatives fail on numpy int...
- #5445: MAINT: stats: fix incorrect deprecation warnings and test noise
- #5446: DOC: add note about PyFFTW in fftpack tutorial.
- #5459: DOC: integrate: Some improvements to the differential equation...
- #5465: BUG: Relax mstats kurtosis test tolerance by a few ulp
- #5471: ConvexHull should raise ValueError for NaNs.
- #5473: MAINT: update decorators.py module to version 4.0.5
- #5476: BUG: imsave searches for wrong channel axis if image has 3 or...
- #5477: BLD: add numpy to setup/install_requires for OS X wheels
- #5479: ENH: return Jacobian/Hessian from BasinHopping
- #5484: BUG: fix ttest zero division handling
- #5486: Fix crash on kmeans2
- #5491: MAINT: Expose parallel build option to runtests.py
- #5494: Sort OptimizeResult.__repr__ by key
- #5496: DOC: update the author name mapping
- #5497: Enhancement to binned_statistic: option to unraveled returned...
- #5498: BUG: sparse: fix a bug in sparsetools input dtype resolution
- #5500: DOC: detect unprintable characters in docstrings
- #5505: BUG: misc: Ensure fromimage converts mode 'P' to 'RGB' or 'RGBA'.
- #5514: DOC: further update the release notes
- #5515: ENH: optionally disable fixed-point acceleration
- #5517: DOC: Improvements and additions to the matrix_normal doc
- #5518: Remove wrappers for LAPACK deprecated routines
- #5521: TST: skip a linalg.orth memory test on 32-bit platforms.
- #5523: DOC: change a few floats to integers in docstring examples
- #5524: DOC: more updates to 0.17.0 release notes.
- #5525: Fix to minor typo in documentation for scipy.integrate.ode
- #5527: TST: bump arccosh tolerance to allow for inaccurate numpy or...

- #5535: DOC: signal: minor clarification to docstring of TransferFunction.
- #5538: DOC: signal: fix find_peaks_cwt documentation
- #5545: MAINT: Fix typo in linalg/basic.py
- #5547: TST: mark TestEig.test_singular as knownfail in master.
- #5550: MAINT: work around lstsq driver selection issue
- #5556: BUG: Fixed broken dogbox trust-region radius update
- #5561: BUG: eliminate warnings, exception (on Win) in test_maskandscale;...
- #5567: TST: a few cleanups in the test suite; run_module_suite and clearer...
- #5568: MAINT: simplify poisson's _argcheck
- #5569: TST: bump GMean test tolerance to make it pass on Wine
- #5572: TST: lstsq: bump test tolerance for TravisCI
- #5573: TST: remove use of np.fromfile from cluster.vq tests
- #5576: Lapack deprecations
- #5579: TST: skip tests of linalg.norm axis keyword on numpy <= 1.7.x
- #5582: Clarify language of survival function documentation
- #5583: MAINT: stats/tests: A bit of clean up.
- #5588: DOC: stats: Add a note that stats.burr is the Type III Burr distribution.
- #5595: TST: fix test_lamch failures on Python 3
- #5600: MAINT: Ignore spatial/ckdtree.cxx and .h
- #5602: Explicitly numbered replacement fields for maintainability
- #5605: MAINT: collection of small fixes to test suite
- #5614: Minor doc change.
- #5624: FIX: Fix interpolate
- #5625: BUG: msvc9 binaries crash when indexing std::vector of size 0
- #5635: BUG: misspelled __dealloc__ in cKDTree.
- #5642: STY: minor fixup of formatting of 0.17.0 release notes.
- #5643: BLD: fix a build issue in special/Faddeeva.cc with isnan.
- #5661: TST: linalg tests used stdlib random instead of numpy.random.
- #5682: backports for 0.17.0
- #5696: Minor improvements to least_squares' docstring.
- #5697: BLD: fix for isnan/isinf issues in special/Faddeeva.cc
- #5720: TST: fix for file opening error in fftpack test_import.py
- #5722: BUG: Make curve_fit respect an initial guess with bounds
- #5726: Backports for v0.17.0rc2
- #5727: API: Changes to least_squares API

3.26 SciPy 0.16.1 Release Notes

SciPy 0.16.1 is a bug-fix release with no new features compared to 0.16.0.

3.26.1 Issues closed for 0.16.1

- #5077: cKDTree not indexing properly for arrays with too many elements
- #5127: Regression in 0.16.0: solve_banded errors out in patsy test suite
- #5149: linalg tests apparently cause python to crash with numpy 1.10.0b1
- #5154: 0.16.0 fails to build on OS X; can't find Python.h
- #5173: failing stats.histogram test with numpy 1.10
- #5191: Scipy 0.16.x - TypeError: _asarray_validated() got an unexpected...
- #5195: tarballs missing documentation source
- #5363: FAIL: test_orthogonal.test_j_roots, test_orthogonal.test_js_roots

3.26.2 Pull requests for 0.16.1

- #5088: BUG: fix logic error in cKDTree.sparse_distance_matrix
- #5089: BUG: Don't overwrite b in lfilter's FIR path
- #5128: BUG: solve_banded failed when solving 1x1 systems
- #5155: BLD: fix missing Python include for Homebrew builds.
- #5192: BUG: backport as_inexact kwarg to _asarray_validated
- #5203: BUG: fix uninitialized use in lartg 0.16 backport
- #5204: BUG: properly return error to fortran from ode_jacobian_function...
- #5207: TST: Fix TestCtypesQuad failure on Python 3.5 for Windows
- #5352: TST: sparse: silence warnings about boolean indexing
- #5355: MAINT: backports for 0.16.1 release
- #5356: REL: update Paver file to ensure sdist contents are OK for releases.
- #5382: 0.16.x backport: MAINT: work around a possible numpy ufunc loop...
- #5393: TST:special: bump tolerance levels for test_j_roots and test_js_roots
- #5417: MAINT: stats: move namedtuple creating outside function calls.

3.27 SciPy 0.16.0 Release Notes

Contents

- *SciPy 0.16.0 Release Notes*
 - *New features*
 - * *Benchmark suite*
 - * *scipy.linalg improvements*
 - * *scipy.signal improvements*
 - * *scipy.sparse improvements*
 - * *scipy.spatial improvements*
 - * *scipy.stats improvements*
 - * *scipy.optimize improvements*
 - *Deprecated features*
 - *Backwards incompatible changes*
 - *Other changes*
 - *Authors*
 - * *Issues closed for 0.16.0*
 - * *Pull requests for 0.16.0*

SciPy 0.16.0 is the culmination of 7 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Moreover, our development attention will now shift to bug-fix releases on the 0.16.x branch, and on adding new features on the master branch.

This release requires Python 2.6, 2.7 or 3.2-3.4 and NumPy 1.6.2 or greater.

Highlights of this release include:

- A Cython API for BLAS/LAPACK in *scipy.linalg*
- A new benchmark suite. It's now straightforward to add new benchmarks, and they're routinely included with performance enhancement PRs.
- Support for the second order sections (SOS) format in *scipy.signal*.

3.27.1 New features

Benchmark suite

The benchmark suite has switched to using [Airspeed Velocity](#) for benchmarking. You can run the suite locally via `python runttests.py --bench`. For more details, see `benchmarks/README.rst`.

`scipy.linalg` improvements

A full set of Cython wrappers for BLAS and LAPACK has been added in the modules `scipy.linalg.cython_blas` and `scipy.linalg.cython_lapack`. In Cython, these wrappers can now be imported from their corresponding modules and used without linking directly against BLAS or LAPACK.

The functions `scipy.linalg.qr_delete`, `scipy.linalg.qr_insert` and `scipy.linalg.qr_update` for updating QR decompositions were added.

The function `scipy.linalg.solve_circulant` solves a linear system with a circulant coefficient matrix.

The function `scipy.linalg.invpascal` computes the inverse of a Pascal matrix.

The function `scipy.linalg.solve_toeplitz`, a Levinson-Durbin Toeplitz solver, was added.

Added wrapper for potentially useful LAPACK function `*lasd4`. It computes the square root of the *i*-th updated eigenvalue of a positive symmetric rank-one modification to a positive diagonal matrix. See its LAPACK documentation and unit tests for it to get more info.

Added two extra wrappers for LAPACK least-square solvers. Namely, they are `*gelsd` and `*gelsy`.

Wrappers for the LAPACK `*lange` functions, which calculate various matrix norms, were added.

Wrappers for `*gtsv` and `*ptsv`, which solve $A \cdot X = B$ for tri-diagonal matrix *A*, were added.

`scipy.signal` improvements

Support for second order sections (SOS) as a format for IIR filters was added. The new functions are:

- `scipy.signal.sosfilt`
- `scipy.signal.sosfilt_zi`,
- `scipy.signal.sos2tf`
- `scipy.signal.sos2zpk`
- `scipy.signal.tf2sos`
- `scipy.signal.zpk2sos`.

Additionally, the filter design functions `iirdesign`, `iirfilter`, `butter`, `cheby1`, `cheby2`, `ellip`, and `bessel` can return the filter in the SOS format.

The function `scipy.signal.place_poles`, which provides two methods to place poles for linear systems, was added.

The option to use Gustafsson's method for choosing the initial conditions of the forward and backward passes was added to `scipy.signal.filtfilt`.

New classes `TransferFunction`, `StateSpace` and `ZerosPolesGain` were added. These classes are now returned when instantiating `scipy.signal.lti`. Conversion between those classes can be done explicitly now.

An exponential (Poisson) window was added as `scipy.signal.exponential`, and a Tukey window was added as `scipy.signal.tukey`.

The function for computing digital filter group delay was added as `scipy.signal.group_delay`.

The functionality for spectral analysis and spectral density estimation has been significantly improved: `scipy.signal.welch` became ~8x faster and the functions `scipy.signal.spectrogram`, `scipy.signal.coherence` and `scipy.signal.csd` (cross-spectral density) were added.

`scipy.signal.lsim` was rewritten - all known issues are fixed, so this function can now be used instead of `lsim2`; `lsim` is orders of magnitude faster than `lsim2` in most cases.

scipy.sparse improvements

The function `scipy.sparse.norm`, which computes sparse matrix norms, was added.

The function `scipy.sparse.random`, which allows to draw random variates from an arbitrary distribution, was added.

scipy.spatial improvements

`scipy.spatial.cKDTree` has seen a major rewrite, which improved the performance of the `query` method significantly, added support for parallel queries, pickling, and options that affect the tree layout. See pull request 4374 for more details.

The function `scipy.spatial.procrustes` for Procrustes analysis (statistical shape analysis) was added.

scipy.stats improvements

The Wishart distribution and its inverse have been added, as `scipy.stats.wishart` and `scipy.stats.invwishart`.

The Exponentially Modified Normal distribution has been added as `scipy.stats.exponnorm`.

The Generalized Normal distribution has been added as `scipy.stats.gennorm`.

All distributions now contain a `random_state` property and allow specifying a specific `numpy.random.RandomState` random number generator when generating random variates.

Many statistical tests and other `scipy.stats` functions that have multiple return values now return `namedtuples`. See pull request 4709 for details.

scipy.optimize improvements

A new derivative-free method DF-SANE has been added to the nonlinear equation system solving function `scipy.optimize.root`.

3.27.2 Deprecated features

`scipy.stats.pdf_fromgamma` is deprecated. This function was undocumented, untested and rarely used. `Statsmodels` provides equivalent functionality with `statsmodels.distributions.ExpandedNormal`.

`scipy.stats.fastsort` is deprecated. This function is unnecessary, `numpy.argsort` can be used instead.

`scipy.stats.signaltonoise` and `scipy.stats.mstats.signaltonoise` are deprecated. These functions did not belong in `scipy.stats` and are rarely used. See issue #609 for details.

`scipy.stats.histogram2` is deprecated. This function is unnecessary, `numpy.histogram2d` can be used instead.

3.27.3 Backwards incompatible changes

The deprecated global optimizer `scipy.optimize.anneal` was removed.

The following deprecated modules have been removed: `scipy.lib.blas`, `scipy.lib.lapack`, `scipy.linalg.cblas`, `scipy.linalg.fblas`, `scipy.linalg.clapack`, `scipy.linalg.flapack`. They had been deprecated since SciPy 0.12.0, the functionality should be accessed as `scipy.linalg.blas` and `scipy.linalg.lapack`.

The deprecated function `scipy.special.all_mat` has been removed.

The deprecated functions `fprob`, `ksprob`, `zprob`, `randwcdf` and `randwppf` have been removed from `scipy.stats`.

3.27.4 Other changes

The version numbering for development builds has been updated to comply with PEP 440.

Building with `python setup.py develop` is now supported.

3.27.5 Authors

- @axiru +
- @endolith
- Elliott Sales de Andrade +
- Anne Archibald
- Yoshiki Vázquez Baeza +
- Sylvain Bellemare
- Felix Berkenkamp +
- Raoul Bourquin +
- Matthew Brett
- Per Brodtkorb
- Christian Brueffer
- Lars Buitinck
- Evgeni Burovski
- Steven Byrnes
- CJ Carey
- George Castillo +
- Alex Conley +
- Liam Damewood +
- Rupak Das +
- Abraham Escalante +
- Matthias Feurer +

- Eric Firing +
- Clark Fitzgerald
- Chad Fulton
- André Gaul
- Andreea Georgescu +
- Christoph Gohlke
- Andrey Golovizin +
- Ralf Gommers
- J.J. Green +
- Alex Griffing
- Alexander Grigorievskiy +
- Hans Moritz Gunther +
- Jonas Hahnfeld +
- Charles Harris
- Ian Henriksen
- Andreas Hilboll
- Åsmund Hjulstad +
- Jan Schlüter +
- Janko Slavič +
- Daniel Jensen +
- Johannes Ballé +
- Terry Jones +
- Amato Kasahara +
- Eric Larson
- Denis Laxalde
- Antony Lee
- Gregory R. Lee
- Perry Lee +
- Loïc Estève
- Martin Manns +
- Eric Martin +
- Matěj Kocián +
- Andreas Mayer +
- Nikolay Mayorov +
- Robert McGibbon +
- Sturla Molden

- Nicola Montecchio +
- Eric Moore
- Jamie Morton +
- Nikolas Moya +
- Maniteja Nandana +
- Andrew Nelson
- Joel Nothman
- Aldrian Obaja
- Regina Ongowarsito +
- Paul Ortyl +
- Pedro López-Adeva Fernández-Layos +
- Stefan Peterson +
- Irvin Probst +
- Eric Quintero +
- John David Reaver +
- Juha Remes +
- Thomas Robitaille
- Clancy Rowley +
- Tobias Schmidt +
- Skipper Seabold
- Aman Singh +
- Eric Soroos
- Valentine Svensson +
- Julian Taylor
- Aman Thakral +
- Helmut Topfitzer +
- Fukumu Tsutsumi +
- Anastasiia Tsyplia +
- Jacob Vanderplas
- Pauli Virtanen
- Matteo Visconti +
- Warren Weckesser
- Florian Wilhelm +
- Nathan Woods
- Haochen Wu +
- Daan Wynen +

A total of 93 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed for 0.16.0

- #1063: Implement a wishart distribution (Trac #536)
- #1885: Rbf: floating point warnings - possible bug (Trac #1360)
- #2020: Rbf default epsilon too large (Trac #1495)
- #2325: extending distributions, hypergeom, to degenerate cases (Trac...
- #3502: [ENH] linalg.hessenberg should use ORGHR for calc_q=True
- #3603: Passing array as window into signal.resample() fails
- #3675: Intermittent failures for signal.slepian on Windows
- #3742: Pchipinterpolator inconvenient as ppoly
- #3786: add procrustes?
- #3798: scipy.io.savemat fails for empty dicts
- #3975: Use RandomState in scipy.stats
- #4022: savemat incorrectly saves logical arrays
- #4028: scipy.stats.geom.logpmf(1,1) returns nan. The correct value is...
- #4030: simplify scipy.stats.betaprime.cdf
- #4031: improve accuracy of scipy.stats.gompertz distribution for small...
- #4033: improve accuracy of scipy.stats.lomax distribution for small...
- #4034: improve accuracy of scipy.stats.rayleigh distribution for large...
- #4035: improve accuracy of scipy.stats.truncexpon distribution for small...
- #4081: Error when reading matlab file: buffer is too small for requested...
- #4100: Why does qr(a, lwork=0) not fail?
- #4134: scipy.stats: rv_frozen has no expect() method
- #4204: Please add docstring to scipy.optimize.RootResults
- #4206: Wrap LAPACK tridiagonal solve routine *gtsv*
- #4208: Empty sparse matrices written to MAT file cannot be read by MATLAB
- #4217: use a TravisCI configuration with numpy built with NPY_RELAXED_STRIDES_CHECKING=1
- #4282: integrate.odeint raises an exception when full_output=1 and the...
- #4301: scipy and numpy version names do not follow pep 440
- #4355: PPoly.antiderivative() produces incorrect output
- #4391: spsolve becomes extremely slow with large b matrix
- #4393: Documentation glitch in sparse.linalg.spilu
- #4408: Vector-valued constraints in minimize() et al
- #4412: Documentation of scipy.signal.cwt error

- #4428: dok.__setitem__ problem with negative indices
- #4434: Incomplete documentation for sparse.linalg.spsolve
- #4438: linprog() documentation example wrong
- #4445: Typo in scipy.special.expi doc
- #4467: Documentation Error in scipy.optimize options for TNC
- #4492: solve_toeplitz benchmark is bitrotting already
- #4506: lobpcg/sparse performance regression Jun 2014?
- #4520: g77_abi_wrappers needed on Linux for MKL as well
- #4521: Broken check in uses_mkl for newer versions of the library
- #4523: rbf with gaussian kernel seems to produce more noise than original...
- #4526: error in site documentation for poisson.pmf() method
- #4527: KDTree example doesn't work in Python 3
- #4550: `scipy.stats.mode` - UnboundLocalError on empty sequence
- #4554: filter out convergence warnings in optimization tests
- #4565: odeint messages
- #4569: remez: "ValueError: Failure to converge after 25 iterations...."
- #4582: DOC: optimize: `_minimize_scalar_brent` does not have a `disp` option
- #4585: DOC: Erroneous latex-related characters in tutorial.
- #4590: sparse.linalg.svds should throw an exception if which not in...
- #4594: scipy.optimize.linprog IndexError when a callback is provided
- #4596: scipy.linalg.block_diag misbehavior with empty array inputs (v0.13.3)
- #4599: scipy.integrate.nquad should call `_OptFunc` when called with only...
- #4612: Crash in signal.lfilter on nd input with wrong shaped zi
- #4613: scipy.io.readsav error on reading sav file
- #4673: scipy.interpolate.RectBivariateSpline construction locks PyQt...
- #4681: Broadcasting in signal.lfilter still not quite right.
- #4705: kmeans `k_or_guess` parameter error if guess is not square array
- #4719: Build failure on 14.04.2
- #4724: GenGamma `_munp` function fails due to overflow
- #4726: FAIL: test_cobyla.test_vector_constraints
- #4734: Failing tests in stats with numpy master.
- #4736: qr_update bug or incompatibility with numpy 1.10?
- #4746: linprog returns solution violating equality constraint
- #4757: optimize.leastsq docstring mismatch
- #4774: Update contributor list for v0.16
- #4779: circmean and others do not appear in the documentation

- #4788: problems with scipy sparse linalg isolve iterative.py when complex
- #4791: BUG: scipy.spatial: incremental Voronoi doesn't increase size...

Pull requests for 0.16.0

- #3116: sparse: enhancements for DIA format
- #3157: ENH: linalg: add the function 'solve_circulant' for solving a...
- #3442: ENH: signal: Add Gustafsson's method as an option for the filtfilt...
- #3679: WIP: fix sporadic slepian failures
- #3680: Some cleanups in stats
- #3717: ENH: Add second-order sections filtering
- #3741: Dltisys changes
- #3956: add note to scipy.signal.resample about prime sample numbers
- #3980: Add check_finite flag to UnivariateSpline
- #3996: MAINT: stricter linalg argument checking
- #4001: BUG: numerical precision in dirichlet
- #4012: ENH: linalg: Add a function to compute the inverse of a Pascal...
- #4021: ENH: Cython api for lapack and blas
- #4089: Fixes for various PEP8 issues.
- #4116: MAINT: fitpack: trim down compiler warnings (unused labels, variables)
- #4129: ENH: stats: add a random_state property to distributions
- #4135: ENH: Add Wishart and inverse Wishart distributions
- #4195: improve the interpolate docs
- #4200: ENH: Add t-test from descriptive stats function.
- #4202: Dendrogram threshold color
- #4205: BLD: fix a number of Bento build warnings.
- #4211: add an ufunc for the inverse Box-Cox transform
- #4212: MRG:fix for gh-4208
- #4213: ENH: specific warning if matlab file is empty
- #4215: Issue #4209: splprep documentation updated to reflect dimensional...
- #4219: DOC: silence several Sphinx warnings when building the docs
- #4223: MAINT: remove two redundant lines of code
- #4226: try forcing the numpy rebuild with relaxed strides
- #4228: BLD: some updates to Bento config files and docs. Closes gh-3978.
- #4232: wrong references in the docs
- #4242: DOC: change example sample spacing
- #4245: Arff fixes

- #4246: MAINT: C fixes
- #4247: MAINT: remove some unused code
- #4249: Add routines for updating QR decompositions
- #4250: MAINT: Some pyflakes-driven cleanup in linalg and sparse
- #4252: MAINT trim away >10 kLOC of generated C code
- #4253: TST: stop shadowing ellip* tests vs boost data
- #4254: MAINT: special: use NPY_PI, not M_PI
- #4255: DOC: INSTALL: use Py3-compatible print syntax, and don't mention...
- #4256: ENH: spatial: reimplement cdist_cosine using np.dot
- #4258: BUG: io.arff #4429 #2088
- #4261: MAINT: signal: PEP8 and related style clean up.
- #4262: BUG: newton_krylov() was ignoring norm_tol argument, closes #4259
- #4263: MAINT: clean up test noise and optimize tests for docstrings...
- #4266: MAINT: io: Give an informative error when attempting to read...
- #4268: MAINT: fftpack benchmark integer division vs true division
- #4269: MAINT: avoid shadowing the eigvals function
- #4272: BUG: sparse: Fix bench_sparse.py
- #4276: DOC: remove confusing parts of the documentation related to writing...
- #4281: Sparse matrix multiplication: only convert array if needed (with...
- #4284: BUG: integrate: odeint crashed when the integration time was...
- #4286: MRG: fix matlab output type of logical array
- #4287: DEP: deprecate stats.pdf_fromgamma. Closes gh-699.
- #4291: DOC: linalg: fix layout in cholesky_banded docstring
- #4292: BUG: allow empty dict as proxy for empty struct
- #4293: MAINT: != -> not_equal in hamming distance implementation
- #4295: Pole placement
- #4296: MAINT: some cleanups in tests of several modules
- #4302: ENH: Solve toeplitz linear systems
- #4306: Add benchmark for conjugate gradient solver.
- #4307: BLD: PEP 440
- #4310: BUG: make stats.geom.logpmf(1,1) return 0.0 instead of nan
- #4311: TST: restore a test that uses slogdet now that we have dropped...
- #4313: Some minor fixes for stats.wishart addition.
- #4315: MAINT: drop numpy 1.5 compatibility code in sparse matrix tests
- #4318: ENH: Add random_state to multivariate distributions
- #4319: MAINT: fix hamming distance regression for exotic arrays, with...

- #4320: TST: a few changes like `self.assertTrue(x == y, message) -> assert_equal(x,...`
- #4321: TST: more changes like `self.assertTrue(x == y, message) -> assert_equal(x,...`
- #4322: TST: in `test_signaltools`, changes like `self.assertTrue(x == y,...`
- #4323: MAINT: clean up benchmarks so they can all be run as single files.
- #4324: Add more detailed committer guidelines, update `MAINTAINERS.txt`
- #4326: TST: use `numpy.testing` in `test_hierarchy.py`
- #4329: MAINT: stats: rename `check_random_state` test function
- #4330: Update distance tests
- #4333: MAINT: import `comb`, `factorial` from `scipy.special`, not `scipy.misc`
- #4338: TST: more conversions from `nose` to `numpy.testing`
- #4339: MAINT: remove the deprecated `all_mat` function from `special_matrices.py`
- #4340: add several features to frozen distributions
- #4344: BUG: Fix/test invalid `lwork` param in `qr`
- #4345: Fix test noise visible with Python 3.x
- #4347: Remove deprecated `blas/lapack` imports, rename `lib` to `_lib`
- #4349: DOC: add a nontrivial example to `stats.binned_statistic`.
- #4350: MAINT: remove `optimize.anneal` for 0.16.0 (was deprecated in 0.14.0).
- #4351: MAINT: fix usage of deprecated Numpy C API in `optimize...`
- #4352: MAINT: fix a number of special test failures
- #4353: implement cdf for betaprime distribution
- #4357: BUG: piecewise polynomial antiderivative
- #4358: BUG: integrate: fix handling of banded Jacobians in `odeint`, plus...
- #4359: MAINT: remove a code path taken for Python version `< 2.5`
- #4360: MAINT: `stats.mstats`: Remove some unused variables (thanks, `pyflakes`).
- #4362: Removed erroneous reference to smoothing parameter #4072
- #4363: MAINT: `interpolate`: clean up in `fitpack.py`
- #4364: MAINT: `lib`: don't export "partial" from decorator
- #4365: `svdvals` now returns a length-0 sequence of singular values given...
- #4367: DOC: slightly improve TeX rendering of `wishart/invwishart` docstring
- #4373: ENH: wrap `gtsv` and `ptsv` for `solve_banded` and `solveh_banded`.
- #4374: ENH: Enhancements to `spatial.cKDTree`
- #4376: BF: fix reading off-spec matlab logical sparse
- #4377: MAINT: `integrate`: Clean up some Fortran test code.
- #4378: MAINT: fix usage of deprecated Numpy C API in `signal`
- #4380: MAINT: `scipy.optimize`, removing further `anneal` references
- #4381: ENH: Make `DCT` and `DST` accept `int` and `complex` types like `fft`

- #4392: ENH: optimize: add DF-SANE nonlinear derivative-free solver
- #4394: Make reordering algorithms 64-bit clean
- #4396: BUG: bundle cblas.h in Accelerate ABI wrappers to enable compilation...
- #4398: FIX pdist bug where wminkowski's w.dtype != double
- #4402: BUG: fix stat.hypergeom argcheck
- #4404: MAINT: Fill in the full symmetric squareform in the C loop
- #4405: BUG: avoid X += X.T (refs #4401)
- #4407: improved accuracy of gompertz distribution for small x
- #4414: DOC:fix error in scipy.signal.cwt documentation.
- #4415: ENH: Improve accuracy of lomax for small x.
- #4416: DOC: correct a parameter name in docstring of SuperLU.solve....
- #4419: Restore scipy.linalg.calc_lwork also in master
- #4420: fix a performance issue with a sparse solver
- #4423: ENH: improve rayleigh accuracy for large x.
- #4424: BUG: optimize.minimize: fix overflow issue with integer x0 input.
- #4425: ENH: Improve accuracy of truncexpon for small x
- #4426: ENH: improve rayleigh accuracy for large x.
- #4427: MAINT: optimize: cleanup of TNC code
- #4429: BLD: fix build failure with numpy 1.7.x and 1.8.x.
- #4430: BUG: fix a sparse.dok_matrix set/get copy-paste bug
- #4433: Update _minimize.py
- #4435: ENH: release GIL around batch distance computations
- #4436: Fixed incomplete documentation for spsolve
- #4439: MAINT: integrate: Some clean up in the tests.
- #4440: Fast permutation t-test
- #4442: DOC: optimize: fix wrong result in docstring
- #4447: DOC: signal: Some additional documentation to go along with the...
- #4448: DOC: tweak the docstring of lapack.linalg module
- #4449: fix a typo in the expit docstring
- #4451: ENH: vectorize distance loops with gcc
- #4456: MAINT: don't fail large data tests on MemoryError
- #4461: CI: use travis_retry to deal with network timeouts
- #4462: DOC: rationalize minimize() et al. documentation
- #4470: MAINT: sparse: inherit dok_matrix.toarray from spmatrix
- #4473: BUG: signal: Fix validation of the zi shape in sosfilt.
- #4475: BLD: setup.py: update min numpy version and support "setup.py...

- #4481: ENH: add a new linalg special matrix: the Helmert matrix
- #4485: MRG: some changes to allow reading bad mat files
- #4490: [ENH] linalg.hessenberg: use orghr - rebase
- #4491: ENH: linalg: Adding wrapper for potentially useful LAPACK function...
- #4493: BENCH: the solve_toeplitz benchmark used outdated syntax and...
- #4494: MAINT: stats: remove duplicated code
- #4496: References added for watershed_ifit algorithm
- #4499: DOC: reshuffle stats distributions documentation
- #4501: Replace benchmark suite with airspeed velocity
- #4502: SLSQP should strictly satisfy bound constraints
- #4503: DOC: forward port 0.15.x release notes and update author name...
- #4504: ENH: option to avoid computing possibly unused svd matrix
- #4505: Rebase of PR 3303 (sparse matrix norms)
- #4507: MAINT: fix lobpcg performance regression
- #4509: DOC: sparse: replace dead link
- #4511: Fixed differential evolution bug
- #4512: Change to fully PEP440 compliant dev version numbers (always...
- #4525: made tiny style corrections (pep8)
- #4533: Add exponentially modified gaussian distribution (scipy.stats.expongauss)
- #4534: MAINT: benchmarks: make benchmark suite importable on all scipy...
- #4535: BUG: Changed zip() to list(zip()) so that it could work in Python...
- #4536: Follow up to pr 4348 (exponential window)
- #4540: ENH: spatial: Add procrustes analysis
- #4541: Bench fixes
- #4542: TST: NumpyVersion dev -> dev0
- #4543: BUG: Overflow in savgol_coeffs
- #4544: pep8 fixes for stats
- #4546: MAINT: use reduction axis arguments in one-norm estimation
- #4549: ENH : Added group_delay to scipy.signal
- #4553: ENH: Significantly faster moment function
- #4556: DOC: document the changes of the sparse.linalg.svds (optional...
- #4559: DOC: stats: describe loc and scale parameters in the docstring...
- #4563: ENH: rewrite of stats.ppcp_plot
- #4564: Be more (or less) forgiving when user passes +-inf instead of...
- #4566: DEP: remove a bunch of deprecated function from scipy.stats,...
- #4570: MNT: Suppress LineSearchWarning's in scipy.optimize tests

- #4572: ENH: Extract inverse hessian information from L-BFGS-B
- #4576: ENH: Split `signal.lti` into subclasses, part of #2912
- #4578: MNT: Reconcile docstrings and function signatures
- #4581: Fix build with Intel MKL on Linux
- #4583: DOC: optimize: remove references to unused `disp kwarg`
- #4584: ENH: `scipy.signal` - Tukey window
- #4587: Hermite asymptotic
- #4593: DOC - add example to `RegularGridInterpolator`
- #4595: DOC: Fix erroneous latex characters in tutorial/optimize.
- #4600: Add return codes to `optimize.tnc` docs
- #4603: ENH: Wrap LAPACK `*lange` functions for matrix norms
- #4604: `scipy.stats`: generalized normal distribution
- #4609: MAINT: `interpolate`: fix a few inconsistencies between docstrings...
- #4610: MAINT: make `runtest.py --bench-compare` use `asv` continuous and...
- #4611: DOC: `stats`: explain rice scaling; add a note to the tutorial...
- #4614: BUG: `lfilter`, the size of `zi` was not checked correctly for nd...
- #4617: MAINT: `integrate`: Clean the C code behind `odeint`.
- #4618: FIX: Raise error when window length \neq data length
- #4619: Issue #4550: `scipy.stats.mode` - `UnboundLocalError` on empty...
- #4620: Fixed a problem (#4590) with `svds` accepting wrong eigenvalue...
- #4621: Speed up `special.ai_zeros/bi_zeros` by 10x
- #4623: MAINT: some tweaks to `spatial.procrustes` (private file, html...
- #4628: Speed up `signal.lfilter` and add a convolution path for FIR filters
- #4629: Bug: `integrate.nquad`; resolve issue #4599
- #4631: MAINT: `integrate`: Remove unused variables in a Fortran test function.
- #4633: MAINT: Fix convergence message for `remez`
- #4635: PEP8: indentation (so that pep8 bot does not complain)
- #4637: MAINT: generalize a sign function to do the right thing for complex...
- #4639: Amended typo in `apple_sgemv_fix.c`
- #4642: MAINT: use `lapack` for `scipy.linalg.norm`
- #4643: RBF default epsilon too large 2020
- #4646: Added `atleast_1d` around `poly` in `invres` and `invresz`
- #4647: fix doc pdf build
- #4648: BUG: Fixes #4408: Vector-valued constraints in `minimize()` et...
- #4649: `Vonmisesfix`
- #4650: Signal example clean up in `Tukey` and `place_poles`

- #4652: DOC: Fix the error in convolve for same mode
- #4653: improve erf performance
- #4655: DEP: deprecate `scipy.stats.histogram2` in favour of `np.histogram2d`
- #4656: DEP: deprecate `scipy.stats.signaltonoise`
- #4660: Avoid extra copy for sparse compressed `[:, seq]` and `[seq, :]`...
- #4661: Clean, rebase of #4478, adding `?gelsy` and `?gelsd` wrappers
- #4662: MAINT: Correct odeint messages
- #4664: Update `_monotone.py`
- #4672: fix behavior of `scipy.linalg.block_diag` for empty input
- #4675: Fix `lsim`
- #4676: Added missing colon to `:math:` directive in docstring.
- #4679: ENH: sparse `randn`
- #4682: ENH: `scipy.signal` - Addition of CSD, coherence; Enhancement of...
- #4684: BUG: various errors in weight calculations in `orthogonal.py`
- #4685: BUG: Fixes #4594: `optimize.linprog` `IndexError` when a callback...
- #4686: MAINT: `cluster`: Clean up duplicated exception raising code.
- #4688: Improve `is_distance_dm` exception message
- #4692: MAINT: `stats`: Simplify the calculation in `tukeylambda._ppf`
- #4693: ENH: added functionality to handle scalars in `stats._chk_asarray`
- #4694: Vectorization of Anderson-Darling computations.
- #4696: Fix singleton expansion in `lfilter`.
- #4698: MAINT: quiet warnings from `cephes`.
- #4701: add `Bpoly.antiderivatives / integrals`
- #4703: Add citation of published paper
- #4706: MAINT: `special`: avoid out-of-bounds access in `specfun`
- #4707: MAINT: fix issues with `np.matrix` as input to functions related...
- #4709: ENH: `scipy.stats` now returns namedtuples.
- #4710: `scipy.io.idl`: make reader more robust to missing variables in...
- #4711: Fix crash for unknown chunks at the end of file
- #4712: Reduce `onenormest` memory usage
- #4713: MAINT: `interpolate`: no need to pass `dtype` around if it can be...
- #4714: BENCH: Add benchmarks for `stats` module
- #4715: MAINT: polish `signal.place_poles` and `signal/test_ltsys.py`
- #4716: DEP: deprecate `mstats.signaltonoise` ...
- #4717: MAINT: `basinhopping`: fix error in tests, silence /0 warning,...
- #4718: ENH: `stats`: can specify f-shapes to fix in fitting by name

- #4721: Document that `imresize` converts the input to a PIL image
- #4722: MAINT: `PyArray_BASE` is not an lvalue unless the deprecated API...
- #4725: Fix `gengamma_numpy` failure
- #4728: DOC: add `poch` to the list of scipy special function descriptions
- #4735: MAINT: stats: avoid (a spurious) division-by-zero in `skew`
- #4738: TST: silence runtime warnings for some corner cases in `stats...`
- #4739: BLD: try to build numpy instead of using the one on TravisCI
- #4740: DOC: Update some docstrings with 'versionadded'.
- #4742: BLD: make sure that relaxed strides checking is in effect on...
- #4750: DOC: special: TeX typesetting of `rel ENTR`, `kl DIV` and `pseudo_huber`
- #4751: BENCH: add sparse null slice benchmark
- #4753: BUG: Fixed compilation with recent Cython versions.
- #4756: BUG: Fixes #4733: `optimize.brute` finish option is not compatible...
- #4758: DOC: `optimize.leastsq` default `maxfev` clarification
- #4759: improved stats mle fit
- #4760: MAINT: count bfgs updates more carefully
- #4762: BUGS: Fixes #4746 and #4594: `linprog` returns solution violating...
- #4763: fix small `linprog` bugs
- #4766: BENCH: add `signal.lsim` benchmark
- #4768: fix python syntax errors in docstring examples
- #4769: Fixes #4726: `test_cobyla.test_vector_constraints`
- #4770: Mark FITPACK functions as thread safe.
- #4771: edited `scipy/stats/stats.py` to fix doctest for `fisher_exact`
- #4773: DOC: update 0.16.0 release notes.
- #4775: DOC: `linalg`: add `funm_psd` as a docstring example
- #4778: Use a dictionary for function name synonyms
- #4780: Include apparently-forgotten functions in docs
- #4783: Added many missing special functions to docs
- #4784: add an axis attribute to `PPoly` and friends
- #4785: Brief note about origin of Lena image
- #4786: DOC: reformat the Methods section of the KDE docstring
- #4787: Add `rice` cdf and `ppf`.
- #4792: CI: add a kludge for detecting test failures which try to disguise...
- #4795: Make `refguide_check` smarter about false positives
- #4797: BUG/TST: `numpyoints` not updated for incremental Voronoi
- #4799: BUG: spatial: Fix a couple edge cases for the Mahalanobis metric...

- #4801: BUG: Fix TypeError in `scipy.optimize._trust-region.py` when `disp=True`.
- #4803: Issues with relaxed strides in QR updating routines
- #4806: MAINT: use an informed initial guess for cauchy fit
- #4810: PEP8ify `codata.py`
- #4812: BUG: Relaxed strides cleanup in `decomp_update.pyx.in`
- #4820: BLD: update Bento build for `sgemv` fix and install cython blas/lapack...
- #4823: ENH: `scipy.signal` - Addition of spectrogram function
- #4827: DOC: add `csd` and `coherence` to `__init__.py`
- #4833: BLD: fix issue in `linalg *lange` wrappers for `g77` builds.
- #4841: TST: fix test failures in `scipy.special` with `mingw32` due to test...
- #4842: DOC: update `site.cfg.example`. Mostly taken over from Numpy
- #4845: BUG: `signal`: Make spectrogram's return values order match the...
- #4849: DOC: Fix error in `ode` docstring example
- #4856: BUG: fix typo causing memleak

3.28 SciPy 0.15.1 Release Notes

SciPy 0.15.1 is a bug-fix release with no new features compared to 0.15.0.

3.28.1 Issues fixed

- #4413: BUG: Tests too strict, `f2py` doesn't have to overwrite this array
- #4417: BLD: avoid using `NPY_API_VERSION` to check not using deprecated...
- #4418: Restore and deprecate `scipy.linalg.calc_work`

3.29 SciPy 0.15.0 Release Notes

Contents

- *SciPy 0.15.0 Release Notes*
 - *New features*
 - * *Linear Programming Interface*
 - * *Differential evolution, a global optimizer*
 - * *scipy.signal improvements*
 - * *scipy.integrate improvements*
 - * *scipy.linalg improvements*
 - * *scipy.sparse improvements*

- * *scipy.special improvements*
- * *scipy.sparse.csgraph improvements*
- * *scipy.stats improvements*
- *Deprecated features*
- *Backwards incompatible changes*
 - * *scipy.ndimage*
 - * *scipy.integrate*
- *Authors*
 - * *Issues closed*
 - * *Pull requests*

SciPy 0.15.0 is the culmination of 6 months of hard work. It contains several new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Moreover, our development attention will now shift to bug-fix releases on the 0.16.x branch, and on adding new features on the master branch.

This release requires Python 2.6, 2.7 or 3.2-3.4 and NumPy 1.5.1 or greater.

3.29.1 New features

Linear Programming Interface

The new function `scipy.optimize.linprog` provides a generic linear programming similar to the way `scipy.optimize.minimize` provides a generic interface to nonlinear programming optimizers. Currently the only method supported is `simplex` which provides a two-phase, dense-matrix-based simplex algorithm. Callbacks functions are supported, allowing the user to monitor the progress of the algorithm.

Differential evolution, a global optimizer

A new `scipy.optimize.differential_evolution` function has been added to the `optimize` module. Differential Evolution is an algorithm used for finding the global minimum of multivariate functions. It is stochastic in nature (does not use gradient methods), and can search large areas of candidate space, but often requires larger numbers of function evaluations than conventional gradient based techniques.

scipy.signal improvements

The function `scipy.signal.max_len_seq` was added, which computes a Maximum Length Sequence (MLS) signal.

scipy.integrate improvements

It is now possible to use *scipy.integrate* routines to integrate multivariate ctypes functions, thus avoiding callbacks to Python and providing better performance.

scipy.linalg improvements

The function *scipy.linalg.orthogonal_procrustes* for solving the procrustes linear algebra problem was added.

BLAS level 2 functions *her*, *syr*, *her2* and *syr2* are now wrapped in *scipy.linalg*.

scipy.sparse improvements

scipy.sparse.linalg.svds can now take a `LinearOperator` as its main input.

scipy.special improvements

Values of ellipsoidal harmonic (i.e. Lamé) functions and associated normalization constants can be now computed using *ellip_harm*, *ellip_harm_2*, and *ellip_normal*.

New convenience functions *entr*, *rel_entr*, *kl_div*, *huber*, and *pseudo_huber* were added.

scipy.sparse.csgraph improvements

Routines *reverse_cuthill_mckee* and *maximum_bipartite_matching* for computing reorderings of sparse graphs were added.

scipy.stats improvements

Added a Dirichlet multivariate distribution, *scipy.stats.dirichlet*.

The new function *scipy.stats.median_test* computes Mood's median test.

The new function *scipy.stats.combine_pvalues* implements Fisher's and Stouffer's methods for combining p-values.

scipy.stats.describe returns a namedtuple rather than a tuple, allowing users to access results by index or by name.

3.29.2 Deprecated features

The *scipy.weave* module is deprecated. It was the only module never ported to Python 3.x, and is not recommended to be used for new code - use Cython instead. In order to support existing code, *scipy.weave* has been packaged separately: <https://github.com/scipy/weave>. It is a pure Python package, and can easily be installed with `pip install weave`.

scipy.special.bessel_diff_formula is deprecated. It is a private function, and therefore will be removed from the public API in a following release.

scipy.stats.nanmean, *nanmedian* and *nanstd* functions are deprecated in favor of their numpy equivalents.

3.29.3 Backwards incompatible changes

scipy.ndimage

The functions `scipy.ndimage.minimum_positions`, `scipy.ndimage.maximum_positions`` and `scipy.ndimage.extrema` return positions as ints instead of floats.

scipy.integrate

The format of banded Jacobians in `scipy.integrate.ode` solvers is changed. Note that the previous documentation of this feature was erroneous.

3.29.4 Authors

- Abject +
- Ankit Agrawal +
- Sylvain Bellemare +
- Matthew Brett
- Christian Brodbeck
- Christian Brueffer
- Lars Buitinck
- Evgeni Burovski
- Pierre de Buyl +
- Greg Caporaso +
- CJ Carey
- Jacob Carey +
- Thomas A Caswell
- Helder Cesar +
- Björn Dahlgren +
- Kevin Davies +
- Yotam Doron +
- Marcos Duarte +
- endolith
- Jesse Engel +
- Rob Falck +
- Corey Farwell +
- Jaime Fernandez del Rio +
- Clark Fitzgerald +
- Tom Flannaghan +

- Chad Fulton +
- Jochen Garcke +
- François Garillot +
- André Gaul
- Christoph Gohlke
- Ralf Gommers
- Alex Griffing
- Blake Griffith
- Olivier Grisel
- Charles Harris
- Trent Hauck +
- Ian Henriksen +
- Jinhyok Heo +
- Matt Hickford +
- Andreas Hilboll
- Danilo Horta +
- David Menéndez Hurtado +
- Gert-Ludwig Ingold
- Thouis (Ray) Jones
- Chris Kerr +
- Carl Kleffner +
- Andreas Kloeckner
- Thomas Kluyver +
- Adrian Kretz +
- Johannes Kulick +
- Eric Larson
- Brianna Laughner +
- Denis Laxalde
- Antony Lee +
- Gregory R. Lee +
- Brandon Liu
- Alex Loew +
- Loïc Estève +
- Jaakko Luttinen +
- Benny Malengier
- Tobias Megies +

- Sturla Molden
- Eric Moore
- Brett R. Murphy +
- Paul Nation +
- Andrew Nelson
- Brian Newsom +
- Joel Nothman
- Sergio Oller +
- Janani Padmanabhan +
- Tiago M.D. Pereira +
- Nicolas Del Piano +
- Manuel Reinhardt +
- Thomas Robitaille
- Mike Romberg +
- Alex Rothberg +
- Sebastian Pölsterl +
- Maximilian Singh +
- Brigitta Sipocz +
- Alex Stewart +
- Julian Taylor
- Collin Tokheim +
- James Tomlinson +
- Benjamin Trendelkamp-Schroer +
- Richard Tsai
- Alexey Umnov +
- Jacob Vanderplas
- Joris Vankerschaver
- Bastian Venthur +
- Pauli Virtanen
- Stefan van der Walt
- Yuxiang Wang +
- James T. Webber
- Warren Weckesser
- Axl West +
- Nathan Woods
- Benda Xu +

- Víctor Zabalza +
- Tiziano Zito +

A total of 99 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed

- #1431: `ellipk(x)` extending its domain for $x < 0$ (Trac #904)
- #1727: consistency of std interface (Trac #1200)
- #1851: Shape parameter negated in `genextreme` (relative to R, MATLAB, ...)
- #1889: `interp2d` is weird (Trac #1364)
- #2188: `splev` gives wrong values or crashes outside of support when der...
- #2343: `scipy.insterpolate`'s `sprep` function fails with certain combinations...
- #2669: `.signal.ltisys.ss2tf` should only apply to MISO systems in current...
- #2911: `interpolate.splder()` failure on Fedora
- #3171: future of `weave` in `scipy`
- #3176: Suggestion to improve error message in `scipy.integrate.odeint`
- #3198: `pdf()` and `logpdf()` methods for `scipy.stats.gaussian_kde`
- #3318: Travis CI is breaking on test(“full”)
- #3329: `scipy.stats.scoreatpercentile` backward-incompatible change not...
- #3362: Reference cycle in `scipy.sparse.linalg.eigs` with `shift-invert...`
- #3364: BUG: `linalg.hessenberg` broken (wrong results)
- #3376: `stats.f_oneway` needs floats
- #3379: Installation of `scipy 0.13.3` via `zc.buildout` fails
- #3403: `hierarchy.linkage` raises an ugly exception for a compressed 2x2...
- #3422: `optimize.curve_fit()` handles NaN by returning all parameters...
- #3457: `linalg.fractional_matrix_power` has no docstring
- #3469: DOC: `ndimage.find_object` ignores zero-values
- #3491: `optimize.leastsq()` documentation should mention it does not work...
- #3499: `cluster.vq.whiten` return nan for all zeros column in observations
- #3503: `minimize` attempts to do vector addition when numpy arrays are...
- #3508: `exponweib.logpdf` fails for valid parameters
- #3509: `libatlas3-base-dev` does not exist
- #3550: BUG: anomalous values computed by `special.ellipkinc`
- #3555: `scipy.ndimage` positions are float instead of int
- #3557: `UnivariateSpline.__call__` should pass all relevant args through...
- #3569: No license statement for test data imported from boost?

- #3576: mstats test failure (too sensitive?)
- #3579: Errors on scipy 0.14.x branch using MKL, Ubuntu 14.04 x86_64
- #3580: Operator overloading with sparse matrices
- #3587: Wrong alphabetical order in continuous statistical distribution...
- #3596: scipy.signal.fftconvolve no longer threadsafe
- #3623: BUG: signal.convolve takes longer than it needs to
- #3655: Integer returned from integer data in scipy.signal.periodogram...
- #3662: Travis failure on Numpy 1.5.1 (not reproducible?)
- #3668: dendrogram(orientation='foo')
- #3669: KroghInterpolator doesn't pass through points
- #3672: Inserting a knot in a spline
- #3682: misleading documentation of scipy.optimize.curve_fit
- #3699: BUG?: minor problem with scipy.signal.lfilter w/initial conditions
- #3700: Inconsistent exceptions raised by scipy.io.loadmat
- #3703: TypeError for RegularGridInterpolator with big-endian data
- #3714: Misleading error message in eigsh: k must be between 1 and rank(A)-1
- #3720: coo_matrix.setdiag() fails
- #3740: Scipy.Spatial.KdTree (Query) Return Type?
- #3761: Invalid result from scipy.special.btdtri
- #3784: DOC - Special Functions - Drum example fix for higher modes
- #3785: minimize() should have friendlier args=
- #3787: BUG: signal: Division by zero in lombscargle
- #3800: BUG: scipy.sparse.csgraph.shortest_path overwrites input matrix
- #3817: Warning in calculating moments from Binomial distribution for...
- #3821: review scipy usage of *np.ma.is_masked*
- #3829: Linear algebra function documentation doesn't mention default...
- #3830: A bug in Docstring of scipy.linalg.eig
- #3844: Issue with shape parameter returned by genextreme
- #3858: "ImportError: No module named Cython.Compiler.Main" on install
- #3876: savgol_filter not in release notes and has no versionadded
- #3884: scipy.stats.kendalltau empty array error
- #3895: ValueError: illegal value in 12-th argument of internal gesdd...
- #3898: skimage test broken by minmax filter change
- #3901: scipy sparse errors with numpy master
- #3905: DOC: optimize: linprog docstring has two "Returns" sections
- #3915: DOC: sphinx warnings because of ***kws* in the stats distributions...

- #3935: Split stats.distributions files in tutorial
- #3969: gh-3607 breaks backward compatibility in ode solver banded jacobians
- #4025: DOC: signal: The return value of find_peaks_cwt is not documented.
- #4029: scipy.stats.nbinom.logpmf(0,1,1) returns nan. Correct value is...
- #4032: ERROR: test_imresize (test_pilutil.TestPILUtil)
- #4038: errors do not propagate through scipy.integrate.odeint properly
- #4171: orthogonal_procrustes always returns scale.
- #4176: Solving the Discrete Lyapunov Equation does not work with matrix...

Pull requests

- #3109: ENH Added Fisher's method and Stouffer's Z-score method
- #3225: Add the limiting distributions to generalized Pareto distribution...
- #3262: Implement back end of faster multivariate integration
- #3266: ENH: signal: add type=False as parameter for periodogram and...
- #3273: Add PEP8 check to Travis-CI
- #3342: ENH: linprog function for linear programming
- #3348: BUG: add proper error handling when using interp2d on regular...
- #3351: ENH: Add MLS method
- #3382: ENH: scipy.special information theory functions
- #3396: ENH: improve stats.nanmedian more by assuming nans are rare
- #3398: Added two wrappers to the gaussian_kde class.
- #3405: BUG: cluster.linkage array conversion to double dtype
- #3407: MAINT: use assert_warns instead of a more complicated mechanism
- #3409: ENH: change to use array view in signal/_peak_finding.py
- #3416: Issue 3376 : stats f_oneway needs floats
- #3419: BUG: tools: Fix list of FMA instructions in detect_cpu_extensions_wine.py
- #3420: DOC: stats: Add 'entropy' to the stats package-level documentation.
- #3429: BUG: close intermediate file descriptor right after it is used...
- #3430: MAINT: Fix some cython variable declarations to avoid warnings...
- #3433: Correcting the normalization of chebwin window function
- #3435: Add more precise link to R's quantile documentation
- #3446: ENH: scipy.optimize - adding differential_evolution
- #3450: MAINT: remove unused function scipy.stats.mstats_basic._kolmog1
- #3458: Reworked version of PR-3084 (mstats-stats comparison)
- #3462: MAINT : Returning a warning for low attenuation values of chebwin...
- #3463: DOC: linalg: Add examples to functions in matfuncs.py

- #3477: ENH: sparse: release GIL in sparsertools routines
- #3480: DOC: Add more details to deconvolve docstring
- #3484: BLD: fix Qhull build issue with MinGW-w64. Closes gh-3237.
- #3498: MAINT: io: remove old warnings from idl.py
- #3504: BUG: cluster.vq.whiten returns nan or inf when std==0
- #3510: MAINT: stats: Reimplement the pdf and logpdf methods of exponweib.
- #3512: Fix PEP8 errors showing up on TravisCI after pep8 1.5 release
- #3514: DOC: libatlas3-base-dev seems to have never been a thing
- #3516: DOC improve scipy.sparse docstrings
- #3517: ENH: speed-up ndimage.filters.min(max)imum_filter1d
- #3518: Issues in scipy.misc.logsumexp
- #3526: DOC: graphical example for cwt, and use a more interesting signal
- #3527: ENH: Implement min(max)imum_filter1d using the MINLIST algorithm
- #3537: STY: reduce number of C compiler warnings
- #3540: DOC: linalg: add docstring to fractional_matrix_power
- #3542: kde.py Doc Typo
- #3545: BUG: stats: stats.levy.cdf with small arguments loses precision.
- #3547: BUG: special: erfcinv with small arguments loses precision.
- #3553: DOC: Convolve examples
- #3561: FIX: in ndimage.measurements return positions as int instead...
- #3564: Fix test failures with numpy master. Closes gh-3554
- #3565: ENH: make interp2d accept unsorted arrays for interpolation.
- #3566: BLD: add numpy requirement to metadata if it can't be imported.
- #3567: DOC: move matfuncs docstrings to user-visible functions
- #3574: Fixes multiple bugs in mstats.theilslopes
- #3577: TST: decrease sensitivity of an mstats test
- #3585: Cleanup of code in scipy.constants
- #3589: BUG: sparse: allow operator overloading
- #3594: BUG: lobpcg returned wrong values for small matrices ($n < 10$)
- #3598: MAINT: fix coverage and coveralls
- #3599: MAINT: symeig – now that's a name I've not heard in a long time
- #3602: MAINT: clean up the new optimize.linprog and add a few more tests
- #3607: BUG: integrate: Fix some bugs and documentation errors in the...
- #3609: MAINT integrate/odepack: kill dead Fortran code
- #3616: FIX: Invalid values
- #3617: Sort netcdf variables in a Python-3 compatible way

- #3622: DOC: Added 0.15.0 release notes entry for linprog function.
- #3625: Fix documentation for `cKDTree.sparse_distance_matrix`
- #3626: MAINT: `linalg.orth` memory efficiency
- #3627: MAINT: stats: A bit of clean up
- #3628: MAINT: signal: remove a useless function from `wavelets.py`
- #3632: ENH: stats: Add Mood's median test.
- #3636: MAINT: cluster: some clean up
- #3638: DOC: docstring of `optimize.basinhopping` confuses singular and...
- #3639: BUG: change `ddof` default to 1 in `mstats.sem`, consistent with...
- #3640: Weave: deprecate the module and disable slow tests on TravisCI
- #3641: ENH: Added support for date attributes to `io.arff.arffread`
- #3644: MAINT: stats: remove superfluous alias in `mstats_basic.py`
- #3646: ENH: adding `sum_duplicates` method to COO sparse matrix
- #3647: Fix for #3596: Make `fitconvolve` threadsafe
- #3650: BUG: sparse: smarter random index selection
- #3652: fix wrong option name in `power_divergence` docstring example
- #3654: Changing EPD to Canopy
- #3657: BUG: `signal.welch`: ensure floating point dtype regardless of...
- #3660: TST: mark a test as known fail
- #3661: BLD: ignore pep8 E302 (expected 2 blank lines, found 1)
- #3663: BUG: fix leaking `errstate`, and ignore `invalid=` errors in a test
- #3664: BUG: `correlate` was extremely slow when `in2.size > in1.size`
- #3667: ENH: Adds default params to pdfs of `multivariate_norm`
- #3670: ENH: Small speedup of FFT size check
- #3671: DOC: adding `differential_evolution` function to 0.15 release notes
- #3673: BUG: `interpolate/fitpack`: arguments to fortran routines may not...
- #3674: Add support for appending to existing netcdf files
- #3681: Speed up test('full'), solve Travis CI timeout issues
- #3683: ENH: cluster: rewrite and optimize `vq` in Cython
- #3684: Update special docs
- #3688: Spacing in special docstrings
- #3692: ENH: `scipy.special`: Improving `sph_harm` function
- #3693: Update `refguide` entries for signal and `fftpack`
- #3695: Update `continuous.rst`
- #3696: ENH: check for valid 'orientation' kwarg in `dendrogram()`
- #3701: make 'a' and 'b' coefficients atleast_1d array in `filtfilt`

- #3702: BUG: cluster: _vq unable to handle large features
- #3704: BUG: special: ellip(k,e)inc nan and double expected value
- #3707: BUG: handle fill_value dtype checks correctly in RegularGridInterpolator
- #3708: Reraise exception on failure to read mat file.
- #3709: BUG: cast 'x' to correct dtype in KroghInterpolator._evaluate
- #3712: ENH: cluster: reimplement the update-step of K-means in Cython
- #3713: FIX: Check type of lfilter
- #3718: Changed INSTALL file extension to rst
- #3719: address svds returning nans for zero input matrix
- #3722: MAINT: spatial: static, unused code, sqrt(squeclidean)
- #3725: ENH: use numpys nanmedian if available
- #3727: TST: add a new fixed_point test and change some test function...
- #3731: BUG: fix romb in scipy.integrate.quadrature
- #3734: DOC: simplify examples with semilogx
- #3735: DOC: Add minimal docstrings to lti.impulse/step
- #3736: BUG: cast pchip arguments to floats
- #3744: stub out inherited methods of Akima1DInterpolator
- #3746: DOC: Fix formatting for Raises section
- #3748: ENH: Added discrete Lyapunov transformation solve
- #3750: Enable automated testing with Python 3.4
- #3751: Reverse Cuthill-McKee and Maximum Bipartite Matching reorderings...
- #3759: MAINT: avoid indexing with a float array
- #3762: TST: filter out RuntimeWarning in vq tests
- #3766: TST: cluster: some cleanups in test_hierarchy.py
- #3767: ENH/BUG: support negative m in elliptic integrals
- #3769: ENH: avoid repeated matrix inverse
- #3770: BUG: signal: In lfilter_zi, b was not rescaled correctly when...
- #3772: STY avoid unnecessary transposes in csr_matrix.getcol/row
- #3773: ENH: Add ext parameter to UnivariateSpline call
- #3774: BUG: in integrate/quadpack.h, put all declarations before statements.
- #3779: Incbet fix
- #3788: BUG: Fix lombscargle ZeroDivisionError
- #3791: Some maintenance for doc builds
- #3795: scipy.special.legendre docstring
- #3796: TYPO: sheroidal -> spheroidal
- #3801: BUG: shortest_path overwrite

- #3803: TST: lombscargle regression test related to atan vs atan2
- #3809: ENH: orthogonal procrustes solver
- #3811: ENH: scipy.special, Implemented Ellipsoidal harmonic function:...
- #3819: BUG: make a fully connected csgraph from an ndarray with no zeros
- #3820: MAINT: avoid spurious warnings in binom(n, p=0).mean() etc
- #3825: Don't claim scipy.cluster does distance matrix calculations.
- #3827: get and set diagonal of coo_matrix, and related csgraph laplacian...
- #3832: DOC: Minor additions to integrate/nquad docstring.
- #3845: Bug fix for #3842: Bug in scipy.optimize.line_search
- #3848: BUG: edge case where the covariance matrix is exactly zero
- #3850: DOC: typo
- #3851: DOC: document default argument values for some arpack functions
- #3860: DOC: sparse: add the function 'find' to the module-level docstring
- #3861: BUG: Removed unnecessary storage of args as instance variables...
- #3862: BUG: signal: fix handling of multi-output systems in ss2tf.
- #3865: Feature request: ability to read heterogeneous types in FortranFile
- #3866: MAINT: update pip wheelhouse for installs
- #3871: MAINT: linalg: get rid of calc_lwork.f
- #3872: MAINT: use scipy.linalg instead of np.dual
- #3873: BLD: show a more informative message if Cython wasn't installed.
- #3874: TST: cluster: cleanup the hierarchy test data
- #3877: DOC: Savitzky-Golay filter version added
- #3878: DOC: move versionadded to notes
- #3879: small tweaks to the docs
- #3881: FIX incorrect sorting during fancy assignment
- #3885: kendalltau function now returns a nan tuple if empty arrays used...
- #3886: BUG: fixing linprog's kwarg order to match docs
- #3888: BUG: optimize: In _linprog_simplex, handle the case where the...
- #3891: BUG: stats: Fix ValueError message in chi2_contingency.
- #3892: DOC: sparse.linalg: Fix lobpcg docstring.
- #3894: DOC: stats: Assorted docstring edits.
- #3896: Fix 2 mistakes in MatrixMarket format parsing
- #3897: BUG: associated Legendre function of second kind for $1 < x < 1.0001$
- #3899: BUG: fix undefined behavior in alngam
- #3906: MAINT/DOC: Whitespace tweaks in several docstrings.
- #3907: TST: relax bounds of interpolate test to accomodate rounding...

- #3909: MAINT: Create a common version of *count_nonzero* for compatibility...
- #3910: Fix a couple of test errors in master
- #3911: Use MathJax for the html docs
- #3914: Rework the *_roots* functions and document them.
- #3916: Remove all *linpack_lite* code and replace with LAPACK routines
- #3917: splines, constant extrapolation
- #3918: DOC: tweak the *rv_discrete* docstring example
- #3919: Quadrature speed-up: *scipy.special.orthogonal.p_roots* with cache
- #3920: DOC: Clarify docstring for *sigma* parameter for *curve_fit*
- #3922: Fixed Docstring issues in *linprog* (Fixes #3905).
- #3924: Coerce args into tuple if necessary.
- #3926: DOC: Surround stats class methods in docstrings with backticks.
- #3927: Changed doc for *romb*'s *dx* parameter to int.
- #3928: check FITPACK conditions in *LSQUnivariateSpline*
- #3929: Added a warning about *leastsq* using with NaNs.
- #3930: ENH: optimize: *curve_fit* now warns if *pcov* is undetermined
- #3932: Clarified the $k > n$ case.
- #3933: DOC: remove *import scipy as sp* abbreviation here and there
- #3936: Add license and copyright holders to test data imported from...
- #3938: DOC: Corrected documentation for return types.
- #3939: DOC: *fitpack*: add a note about Sch-W conditions to *splrep* docstring
- #3940: TST: *integrate*: Remove an invalid test of *odeint*.
- #3942: FIX: Corrected error message of *eigsh*.
- #3943: ENH: release GIL for filter and interpolation of *ndimage*
- #3944: FIX: Raise value error if window data-type is unsupported
- #3946: Fixed *signal.get_window* with unicode window name
- #3947: MAINT: some docstring fixes and style cleanups in *stats.mstats*
- #3949: DOC: fix a couple of issues in stats docstrings.
- #3950: TST: *sparse*: remove known failure that doesn't fail
- #3951: TST: switch from Rackspace wheelhouse to numpy/cython source...
- #3952: DOC: stats: Small formatting correction to the 'chi' distribution...
- #3953: DOC: stats: Several corrections and small additions to docstrings.
- #3955: *signal.__init__.py*: remove duplicated *get_window* entry
- #3959: TST: *sparse*: more "known failures" for DOK that don't fail
- #3960: BUG: *io.netcdf*: do not close *mmap* if there are references left...
- #3965: DOC: Fix a few more sphinx warnings that occur when building...

- #3966: DOC: add guidelines for using test generators in HACKING
- #3968: BUG: sparse.linalg: make Inv objects in arpack garbage-collectable...
- #3971: Remove all linpack_lite code and replace with LAPACK routines
- #3972: fix typo in error message
- #3973: MAINT: better error message for multivariate normal.
- #3981: turn the cryptically named scipy.special information theory functions...
- #3984: Wrap her, syr, her2, syr2 blas routines
- #3990: improve UnivariateSpline docs
- #3991: ENH: stats: return namedtuple for describe output
- #3993: DOC: stats: percentileofscore references np.percentile
- #3997: BUG: linalg: pascal(35) was incorrect: last element overflowed...
- #3998: MAINT: use isMaskedArray instead of is_masked to check type
- #3999: TST: test against all of boost data files.
- #4000: BUG: stats: Fix edge-case handling in a few distributions.
- #4003: ENH: using python's warnings instead of prints in fitpack.
- #4004: MAINT: optimize: remove a couple unused variables in zeros.c
- #4006: BUG: Fix C90 compiler warnings in *NI_MinOrMaxFilter1D*
- #4007: MAINT/DOC: Fix spelling of 'decomposition' in several files.
- #4008: DOC: stats: Split the descriptions of the distributions in the...
- #4015: TST: logsumexp regression test
- #4016: MAINT: remove some inf-related warnings from logsumexp
- #4020: DOC: stats: fix whitespace in docstrings of several distributions
- #4023: Exactly one space required before assignments
- #4024: In dendrogram(): Correct an argument name and a grammar issue...
- #4041: BUG: misc: Ensure that the 'size' argument of PIL's 'resize'...
- #4049: BUG: Return of _logpmf
- #4051: BUG: expm of integer matrices
- #4052: ENH: integrate: odeint: Handle exceptions in the callback functions.
- #4053: BUG: stats: Refactor argument validation to avoid a unicode issue.
- #4057: Added newline to scipy.sparse.linalg.svds documentation for correct...
- #4058: MAINT: stats: Add note about change to scoreatpercentile in release...
- #4059: ENH: interpolate: Allow splev to accept an n-dimensional array.
- #4064: Documented the return value for scipy.signal.find_peaks_cwt
- #4074: ENH: Support LinearOperator as input to svds
- #4084: BUG: Match exception declarations in scipy/io/matlab/streams.pyx...
- #4091: DOC: special: more clear instructions on how to evaluate polynomials

- #4105: BUG: Workaround for SGEMV segfault in Accelerate
- #4107: DOC: get rid of 'import *' in examples
- #4113: DOC: fix typos in distance.yule
- #4114: MAINT C fixes
- #4117: deprecate nanmean, nanmedian and nanstd in favor of their numpy...
- #4126: scipy.io.idl: support description records and fix bug with null...
- #4131: ENH: release GIL in more ndimage functions
- #4132: MAINT: stats: fix a typo [skip ci]
- #4145: DOC: Fix documentation error for nc chi-squared dist
- #4150: Fix _nd_image.geometric_transform endianness bug
- #4153: MAINT: remove use of deprecated numpy API in lib/lapack/ f2py...
- #4156: MAINT: optimize: remove dead code
- #4159: MAINT: optimize: clean up Zeros code
- #4165: DOC: add missing special functions to __doc__
- #4172: DOC: remove misleading procrustes docstring line
- #4175: DOC: sparse: clarify CSC and CSR constructor usage
- #4177: MAINT: enable np.matrix inputs to solve_discrete_lyapunov
- #4179: TST: fix an intermittently failing test case for special.legendre
- #4181: MAINT: remove unnecessary null checks before free
- #4182: Ellipsoidal harmonics
- #4183: Skip Cython build in Travis-CI
- #4184: Pr 4074
- #4187: Pr/3923
- #4190: BUG: special: fix up ellip_harm build
- #4193: BLD: fix msvc compiler errors
- #4194: BUG: fix buffer dtype mismatch on win-amd64
- #4199: ENH: Changed scipy.stats.describe output from datalen to nobs
- #4201: DOC: add blas2 and nan* deprecations to the release notes
- #4243: TST: bump test tolerances

3.30 SciPy 0.14.1 Release Notes

SciPy 0.14.1 is a bug-fix release with no new features compared to 0.14.0.

3.30.1 Issues closed

- #3630: NetCDF reading results in a segfault
- #3631: SuperLU object not working as expected for complex matrices
- #3733: segfault from map_coordinates
- #3780: Segfault when using CSR/CSC matrix and uint32/uint64
- #3781: BUG: sparse: fix omitted types in sparsertools typemaps
- #3802: 0.14.0 API breakage: _gen generators are missing from scipy.stats.distributions API
- #3805: ndimage test failures with numpy 1.10
- #3812: == sometimes wrong on csr_matrix
- #3853: Many scipy.sparse test errors/failures with numpy 1.9.0b2
- #4084: fix exception declarations for Cython 0.21.1 compatibility
- #4093: BUG: fitpack: avoid a memory error in splev(x, tck, der=k)
- #4104: BUG: Workaround SGEMV segfault in Accelerate (maintenance 0.14.x)
- #4143: BUG: fix ndimage functions for large data
- #4149: Bug in expm for integer arrays
- #4154: Backport gh-4041 for 0.14.1 (Ensure that the 'size' argument of PIL's 'resize' method is a tuple)
- #4163: Backport #4142 (ZeroDivisionError in scipy.sparse.linalg.lsqr)
- #4164: Backport gh-4153 (remove use of deprecated numpy API in lib/lapack/ f2py wrapper)
- #4180: backport pil resize support tuple fix
- #4168: Lots of arpack test failures on windows 32 bits with numpy 1.9.1
- #4203: Matrix multiplication in 0.14.x is more than 10x slower compared...
- #4218: attempt to make ndimage interpolation compatible with numpy relaxed...
- #4225: BUG: off-by-one error in PPoly shape checks
- #4248: BUG: optimize: fix issue with incorrect use of closure for slsqp.

3.31 SciPy 0.14.0 Release Notes

Contents

- *SciPy 0.14.0 Release Notes*
 - *New features*
 - * *scipy.interpolate improvements*

- * *scipy.linalg* improvements
- * *scipy.optimize* improvements
- * *scipy.stats* improvements
- * *scipy.signal* improvements
- * *scipy.special* improvements
- * *scipy.sparse* improvements
- *Deprecated features*
 - * *anneal*
 - * *scipy.stats*
 - * *scipy.interpolate*
- *Backwards incompatible changes*
 - * *scipy.special.lpmn*
 - * *scipy.sparse.linalg*
 - * *scipy.stats*
 - * *scipy.interpolate*
- *Other changes*
- *Authors*
 - * *Issues closed*
 - * *Pull requests*

SciPy 0.14.0 is the culmination of 8 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Moreover, our development attention will now shift to bug-fix releases on the 0.14.x branch, and on adding new features on the master branch.

This release requires Python 2.6, 2.7 or 3.2-3.4 and NumPy 1.5.1 or greater.

3.31.1 New features

scipy.interpolate improvements

A new wrapper function *scipy.interpolate.interpn* for interpolation on regular grids has been added. *interpn* supports linear and nearest-neighbor interpolation in arbitrary dimensions and spline interpolation in two dimensions.

Faster implementations of piecewise polynomials in power and Bernstein polynomial bases have been added as *scipy.interpolate.PPoly* and *scipy.interpolate.BPoly*. New users should use these in favor of *scipy.interpolate.PiecewisePolynomial*.

scipy.interpolate.interp1d now accepts non-monotonic inputs and sorts them. If performance is critical, sorting can be turned off by using the new `assume_sorted` keyword.

Functionality for evaluation of bivariate spline derivatives in *scipy.interpolate* has been added.

The new class *scipy.interpolate.Akima1DInterpolator* implements the piecewise cubic polynomial interpolation scheme devised by H. Akima.

Functionality for fast interpolation on regular, unevenly spaced grids in arbitrary dimensions has been added as `scipy.interpolate.RegularGridInterpolator`.

scipy.linalg improvements

The new function `scipy.linalg.dft` computes the matrix of the discrete Fourier transform.

A condition number estimation function for matrix exponential, `scipy.linalg.expm_cond`, has been added.

scipy.optimize improvements

A set of benchmarks for optimize, which can be run with `optimize.bench()`, has been added.

`scipy.optimize.curve_fit` now has more controllable error estimation via the `absolute_sigma` keyword.

Support for passing custom minimization methods to `optimize.minimize()` and `optimize.minimize_scalar()` has been added, currently useful especially for combining `optimize.basinhopping()` with custom local optimizer routines.

scipy.stats improvements

A new class `scipy.stats.multivariate_normal` with functionality for multivariate normal random variables has been added.

A lot of work on the `scipy.stats` distribution framework has been done. Moment calculations (skew and kurtosis mainly) are fixed and verified, all examples are now runnable, and many small accuracy and performance improvements for individual distributions were merged.

The new function `scipy.stats.anderson_ksamp` computes the k-sample Anderson-Darling test for the null hypothesis that k samples come from the same parent population.

scipy.signal improvements

`scipy.signal.iirfilter` and related functions to design Butterworth, Chebyshev, elliptical and Bessel IIR filters now all use pole-zero (“zpk”) format internally instead of using transformations to numerator/denominator format. The accuracy of the produced filters, especially high-order ones, is improved significantly as a result.

The Savitzky-Golay filter was added with the new functions `scipy.signal.savgol_filter` and `scipy.signal.savgol_coeffs`.

The new function `scipy.signal.vectorstrength` computes the vector strength, a measure of phase synchrony, of a set of events.

scipy.special improvements

The functions `scipy.special.boxcox` and `scipy.special.boxcox1p`, which compute the Box-Cox transformation, have been added.

scipy.sparse improvements

- Significant performance improvement in CSR, CSC, and DOK indexing speed.
- When using Numpy ≥ 1.9 (to be released in MM 2014), sparse matrices function correctly when given to arguments of `np.dot`, `np.multiply` and other ufuncs. With earlier Numpy and Scipy versions, the results of such operations are undefined and usually unexpected.
- Sparse matrices are no longer limited to 2^{31} nonzero elements. They automatically switch to using 64-bit index data type for matrices containing more elements. User code written assuming the sparse matrices use `int32` as the index data type will continue to work, except for such large matrices. Code dealing with larger matrices needs to accept either `int32` or `int64` indices.

3.31.2 Deprecated features

anneal

The global minimization function `scipy.optimize.anneal` is deprecated. All users should use the `scipy.optimize.basinhopping` function instead.

scipy.stats

`randwcdf` and `randwppf` functions are deprecated. All users should use distribution-specific `rvs` methods instead.

Probability calculation aliases `zprob`, `fprob` and `ksprob` are deprecated. Use instead the `sf` methods of the corresponding distributions or the `special` functions directly.

scipy.interpolate

`PiecewisePolynomial` class is deprecated.

3.31.3 Backwards incompatible changes

scipy.special.lpmn

`lpmn` no longer accepts complex-valued arguments. A new function `clpmn` with uniform complex analytic behavior has been added, and it should be used instead.

scipy.sparse.linalg

Eigenvectors in the case of generalized eigenvalue problem are normalized to unit vectors in 2-norm, rather than following the LAPACK normalization convention.

The deprecated UMFPACK wrapper in `scipy.sparse.linalg` has been removed due to license and install issues. If available, `scikits.umfpack` is still used transparently in the `spsolve` and `factorized` functions. Otherwise, SuperLU is used instead in these functions.

scipy.stats

The deprecated functions `glm`, `oneway` and `cmedian` have been removed from `scipy.stats`.
`stats.scoreatpercentile` now returns an array instead of a list of percentiles.

scipy.interpolate

The API for computing derivatives of a monotone piecewise interpolation has changed: if `p` is a `PchipInterpolator` object, `p.derivative(der)` returns a callable object representing the derivative of `p`. For in-place derivatives use the second argument of the `__call__` method: `p(0.1, der=2)` evaluates the second derivative of `p` at `x=0.1`.

The method `p.derivatives` has been removed.

3.31.4 Other changes

3.31.5 Authors

- Marc Abramowitz +
- Anders Bech Borchersen +
- Vincent Arel-Bundock +
- Petr Baudis +
- Max Bolingbroke
- François Boulogne
- Matthew Brett
- Lars Buitinck
- Evgeni Burovski
- CJ Carey +
- Thomas A Caswell +
- Pawel Chojnacki +
- Phillip Cloud +
- Stefano Costa +
- David Cournapeau
- David Menendez Hurtado +
- Matthieu Dartiailh +
- Christoph Deil +
- Jörg Dietrich +
- endolith
- Francisco de la Peña +
- Ben FrantzDale +
- Jim Garrison +

- André Gaul
- Christoph Gohlke
- Ralf Gommers
- Robert David Grant
- Alex Griffing
- Blake Griffith
- Yaroslav Halchenko
- Andreas Hilboll
- Kat Huang
- Gert-Ludwig Ingold
- James T. Webber +
- Dorota Jarecka +
- Todd Jennings +
- Thouis (Ray) Jones
- Juan Luis Cano Rodríguez
- ktritz +
- Jacques Kvam +
- Eric Larson +
- Justin Lavoie +
- Denis Laxalde
- Jussi Leinonen +
- lemonlaug +
- Tim Leslie
- Alain Leufroy +
- George Lewis +
- Max Linke +
- Brandon Liu +
- Benny Malengier +
- Matthias Kümmerer +
- Cimarron Mittelsteadt +
- Eric Moore
- Andrew Nelson +
- Niklas Hambüchen +
- Joel Nothman +
- Clemens Novak
- Emanuele Olivetti +

- Stefan Otte +
- peb +
- Josef Perktold
- pjwernneck
- poolio
- Jérôme Roy +
- Carl Sandrock +
- Andrew Sczesnak +
- Shauna +
- Fabrice Silva
- Daniel B. Smith
- Patrick Snape +
- Thomas Spura +
- Jacob Stevenson
- Julian Taylor
- Tomas Tomecek
- Richard Tsai
- Jacob Vanderplas
- Joris Vankerschaver +
- Pauli Virtanen
- Warren Weckesser

A total of 80 people contributed to this release. People with a “+” by their names contributed a patch for the first time. This list of names is automatically generated, and may not be fully complete.

Issues closed

- #1325: add custom axis keyword to dendrogram function in `scipy.cluster.hierarchy...`
- #1437: Wrong pochhammer symbol for negative integers (Trac #910)
- #1555: `scipy.io.netcdf` leaks file descriptors (Trac #1028)
- #1569: sparse matrix failed with element-wise multiplication using `numpy.multiply()`...
- #1833: Sparse matrices are limited to 2^{32} non-zero elements (Trac #1307)
- #1834: `scipy.linalg.eig` does not normalize eigenvector if B is given...
- #1866: stats for `invgamma` (Trac #1340)
- #1886: stats.zipf floating point warnings (Trac #1361)
- #1887: Stats continuous distributions - floating point warnings (Trac...)
- #1897: `scoreatpercentile()` does not handle empty list inputs (Trac #1372)
- #1918: `splint` returns incorrect results (Trac #1393)

- #1949: kurtosistest fails in mstats with type error (Trac #1424)
- #2092: scipy.test leaves darwin27compiled_catalog, cpp and so files...
- #2106: stats ENH: shape parameters in distribution docstrings (Trac...)
- #2123: Bad behavior of sparse matrices in a binary ufunc (Trac #1598)
- #2152: Fix mmio/fromfile on gzip on Python 3 (Trac #1627)
- #2164: stats.rice.pdf(x, 0) returns nan (Trac #1639)
- #2169: scipy.optimize.fmin_bfgs not handling functions with boundaries...
- #2177: scipy.cluster.hierarchy.ClusterNode.pre_order returns IndexError...
- #2179: coo.todense() segfaults (Trac #1654)
- #2185: Precision of scipy.ndimage.gaussian_filter*() limited (Trac #1660)
- #2186: scipy.stats.mstats.kurtosistest crashes on 1d input (Trac #1661)
- #2238: Negative p-value on hypergeom.cdf (Trac #1719)
- #2283: ascending order in interpolation routines (Trac #1764)
- #2288: mstats.kurtosistest is incorrectly converting to float, and fails...
- #2396: lpmn wrong results for $|z| > 1$ (Trac #1877)
- #2398: ss2tf returns num as 2D array instead of 1D (Trac #1879)
- #2406: linkage does not take Unicode strings as method names (Trac #1887)
- #2443: IIR filter design should not transform to tf representation internally
- #2572: class method solve of splu return object corrupted or falsely...
- #2667: stats endless loop ?
- #2671: .stats.hypergeom documentation error in the note about pmf
- #2691: BUG scipy.linalg.lapack: potrf/ptroi interpret their 'lower'...
- #2721: Allow use of ellipsis in scipy.sparse slicing
- #2741: stats: deprecate and remove alias for special functions
- #2742: stats add rvs to rice distribution
- #2765: bugs stats entropy
- #2832: argrextrema returns tuple of 2 empty arrays when no peaks found...
- #2861: scipy.stats.scoreatpercentile broken for vector *per*
- #2891: COBYLA successful termination when constraints violated
- #2919: test failure with the current master
- #2922: ndimage.percentile_filter ignores origin argument for multidimensional...
- #2938: Sparse/dense matrix inplace operations fail due to `__numpy_ufunc__`
- #2944: MacPorts builds yield 40Mb worth of build warnings
- #2945: FAIL: test_random_complex (test_basic.TestDet)
- #2947: FAIL: Test some trivial edge cases for savgol_filter()
- #2953: Scipy Delaunay triangulation is not oriented

- #2971: `scipy.stats.mstats.winsorize` documentation error
- #2980: Problems running what seems a perfectly valid example
- #2996: entropy for `rv_discrete` is incorrect?!
- #2998: Fix numpy version comparisons
- #3002: python `setup.py` install fails
- #3014: Bug in `stats.fisher_exact`
- #3030: relative entropy using `scipy.stats.distribution.entropy` when...
- #3037: `scipy.optimize.curve_fit` leads to unexpected behavior when input...
- #3047: `mstats.ttest_rel` `axis=None`, requires masked array
- #3059: BUG: Slices of sparse matrices return incorrect dtype
- #3063: `range` keyword in `binned_statistics` incorrect
- #3067: `cumtrapz` not working as expected
- #3069: `sinc`
- #3086: standard error calculation inconsistent between 'stats' and 'mstats'
- #3094: Add a `perm` function into `scipy.misc` and an enhancement of...
- #3111: `scipy.sparse.[hv]stack` don't respect anymore the dtype parameter
- #3172: `optimize.curve_fit` uses different nomenclature from `optimize.leastsq`
- #3196: `scipy.stats.mstats.gmean` does not actually take dtype
- #3212: Dot product of `csr_matrix` causes segmentation fault
- #3227: `ZeroDivisionError` in `broyden1` when initial guess is the right...
- #3238: `lbfgsb` output not suppressed by `disp=0`
- #3249: Sparse matrix `min/max/etc` don't support `axis=-1`
- #3251: `cdist` performance issue with 'sqeuclidean' metric
- #3279: `logm` fails for singular matrix
- #3285: `signal.chirp(method='hyp')` disallows hyperbolic upsweep
- #3299: MEMORY LEAK: `fmin_tnc`
- #3330: test failures with the current master
- #3345: `scipy` and/or `numpy` change is causing tests to fail in another...
- #3363: `splu` does not work for non-vector inputs
- #3385: `expit` does not handle large arguments well
- #3395: `specfun.f` doesn't compile with MinGW
- #3399: Error message bug in `scipy.cluster.hierarchy.linkage`
- #3404: `interpolate._ppoly` doesn't build with MinGW
- #3412: Test failures in `signal`
- #3466: ``scipy.sparse.csgraph.shortest_path`` does not work on ``scipy.sparse.csr_matrix`` or ``lil_matrix``

Pull requests

- #442: ENH: sparse: enable 64-bit index arrays & nnz > 2**31
- #2766: DOC: remove doc/seps/technology-preview.rst
- #2772: TST: stats: Added a regression test for stats.wilcoxon. Closes...
- #2778: Clean up stats._support, close statistics review issues
- #2792: BUG io: fix file descriptor closing for netcdf variables
- #2847: Rice distribution: extend to b=0, add an explicit rvs method.
- #2878: [stats] fix formulas for higher moments of dweibull distribution
- #2904: ENH: moments for the zipf distribution
- #2907: ENH: add coverage info with coveralls.io for Travis runs.
- #2932: BUG+TST: setdiag implementation for dia_matrix (Close #2931)...
- #2942: Misc fixes pointed out by Eclipse PyDev static code analysis
- #2946: ENH: allow non-monotonic input in interp1d
- #2986: BUG: runtests: chdir away from root when running tests
- #2987: DOC: linalg: don't recommend np.linalg.norm
- #2992: ENH: Add "limit" parameter to dijkstra calculation
- #2995: ENH: Use int shape
- #3006: DOC: stats: add a log base note to the docstring
- #3007: DEP: stats: Deprecate randwppf and randwcdf
- #3008: Fix mstats.kurtosistest, and test coverage for skewtest/normaltest
- #3009: Minor reST typo
- #3010: Add *scipy.optimize.Result* to API docs
- #3012: Corrects documentation error
- #3052: PEP-8 conformance improvements
- #3064: Binned statistic
- #3068: Fix Issue #3067 fix cumtrapz that was raising an exception when...
- #3073: Arff reader with nominal value of 1 character
- #3074: Some maintenance work
- #3080: Review and clean up all Box-Cox functions
- #3083: Bug: should return 0 if no regions found
- #3085: BUG: Use zpk in IIR filter design to improve accuracy
- #3101: refactor stats tests a bit
- #3112: ENH: implement Akima interpolation in 1D
- #3123: MAINT: an easier way to make ranges from slices
- #3124: File object support for imread and imsave
- #3126: pep8ify stats/distributions.py

- #3134: MAINT: split distributions.py into three files
- #3138: clean up tests for discrete distributions
- #3155: special: handle the edge case lambda=0 in pdtr, pdtrc and pdtrik
- #3156: Rename optimize.Result to OptimizeResult
- #3166: BUG: make curve_fit() work with array_like input. Closes gh-3037.
- #3170: Fix numpy version checks
- #3175: use numpy sinc
- #3177: Update numpy version warning, remove oldnumeric import
- #3178: DEP: remove deprecated umfpack wrapper. Closes gh-3002.
- #3179: DOC: add BPoly to the docs
- #3180: Suppress warnings when running stats.test()
- #3181: altered sem func in mstats to match stats
- #3182: Make weave tests behave
- #3183: ENH: Add k-sample Anderson-Darling test to stats module
- #3186: Fix stats.scoreatpercentile
- #3187: DOC: make curve_fit nomenclature same as leastsq
- #3201: Added axis keyword to dendrogram function
- #3207: Make docstring examples in stats.distributions docstrings runnable
- #3218: BUG: integrate: Fix banded jacobian handling in the “vode” and...
- #3222: BUG: limit input ranges in special.nctdtr
- #3223: Fix test errors with numpy master
- #3224: Fix int32 overflows in sparsertools
- #3228: DOC: tf2ss zpk2ss note controller canonical form
- #3234: Add See Also links and Example graphs to filter design *ord functions
- #3235: Updated the buttord function to be consistent with the other...
- #3239: correct doc for pchip interpolation
- #3240: DOC: fix ReST errors in the BPoly docstring
- #3241: RF: check write attr of fileobject without writing
- #3243: a bit of maintenance work in stats
- #3245: BUG/ENH: stats: make frozen distributions hold separate instances
- #3247: ENH function to return nnz per row/column in some sparse matrices
- #3248: ENH much more efficient sparse min/max with axis
- #3252: Fast sseuclidean
- #3253: FIX support axis=-1 and -2 for sparse reduce methods
- #3254: TST tests for non-canonical input to sparse matrix operations
- #3272: BUG: sparse: fix bugs in dia_matrix.setdiag

- #3278: Also generate a tar.xz when running paver sdist
- #3286: DOC: update 0.14.0 release notes.
- #3289: TST: remove insecure mktemp use in tests
- #3292: MAINT: fix a backwards incompatible change to stats.distributions.__all__
- #3293: ENH: signal: Allow upsweeps of frequency in the 'hyperbolic'...
- #3302: ENH: add dtype arg to stats.mstats.gmean and stats.mstats.hmean
- #3307: DOC: add note about different ba forms in tf2zpk
- #3309: doc enhancements to scipy.stats.mstats.winsorize
- #3310: DOC: clarify matrix vs array in mmio docstrings
- #3314: BUG: fix scipy.io.mmread() of gzipped files under Python3
- #3323: ENH: Efficient interpolation on regular grids in arbitrary dimensions
- #3332: DOC: clean up scipy.special docs
- #3335: ENH: improve nanmedian performance
- #3347: BUG: fix use of np.max in stats.fisher_exact
- #3356: ENH: sparse: speed up LIL indexing + assignment via Cython
- #3357: Fix "imresize does not work with size = int"
- #3358: MAINT: rename AkimaInterpolator to Akima1DInterpolator
- #3366: WHT: sparse: reindent dsolve/*.c *.h
- #3367: BUG: sparse/dsolve: fix dense matrix fortran order bugs in superlu...
- #3369: ENH minimize, minimize_scalar: Add support for user-provided...
- #3371: scipy.stats.sigmaclip doesn't appear in the html docs.
- #3373: BUG: sparse/dsolve: detect invalid LAPACK parameters in superlu...
- #3375: ENH: sparse/dsolve: make the L and U factors of splu and spilu...
- #3377: MAINT: make travis build one target against Numpy 1.5
- #3378: MAINT: fftpack: Remove the use of 'import *' in a couple test...
- #3381: MAINT: replace np.isinf(x) & (x>0) -> np.isposinf(x) to avoid...
- #3383: MAINT: skip float96 tests on platforms without float96
- #3384: MAINT: add pyflakes to Travis-CI
- #3386: BUG: stable evaluation of expit
- #3388: BUG: SuperLU: fix missing declaration of dlamch
- #3389: BUG: sparse: downcast 64-bit indices safely to intp when required
- #3390: BUG: nonlinear solvers are not confused by lucky guess
- #3391: TST: fix sparse test errors due to axis=-1,-2 usage in np.matrix.sum().
- #3392: BUG: sparse/lil: fix up Cython bugs in fused type lookup
- #3393: BUG: sparse/compressed: work around bug in np.unique in earlier...
- #3394: BUG: allow ClusterNode.pre_order() for non-root nodes

- #3400: BUG: cluster.linkage ValueError typo bug
- #3402: BUG: special: In `specfun.f`, replace the use of `CMPLX` with `DCMPLX`,...
- #3408: MAINT: sparse: Numpy 1.5 compatibility fixes
- #3410: MAINT: interpolate: fix blas defs in `_ppoly`
- #3411: MAINT: Numpy 1.5 fixes in `interpolate`
- #3413: Fix more test issues with older numpy versions
- #3414: TST: signal: loosen some error tolerances in the filter tests....
- #3415: MAINT: tools: automated close issue + pr listings for release...
- #3440: MAINT: wrap `sparsetools` manually instead via SWIG
- #3460: TST: open image file in binary mode
- #3467: BUG: fix validation in `csgraph.shortest_path`

3.32 SciPy 0.13.2 Release Notes

SciPy 0.13.2 is a bug-fix release with no new features compared to 0.13.1.

3.32.1 Issues fixed

- 3096: require Cython 0.19, earlier versions have memory leaks in fused types
- 3079: `ndimage.label` fix swapped 64-bitness test
- 3108: `optimize.fmin_slsqp` constraint violation

3.33 SciPy 0.13.1 Release Notes

SciPy 0.13.1 is a bug-fix release with no new features compared to 0.13.0. The only changes are several fixes in `ndimage`, one of which was a serious regression in `ndimage.label` (Github issue 3025), which gave incorrect results in 0.13.0.

3.33.1 Issues fixed

- 3025: `ndimage.label` returns incorrect results in `scipy 0.13.0`
- 1992: `ndimage.label` return type changed from `int32` to `uint32`
- 1992: `ndimage.find_objects` doesn't work with `int32` input in some cases

3.34 SciPy 0.13.0 Release Notes

Contents

- *SciPy 0.13.0 Release Notes*
 - *New features*
 - * *scipy.integrate improvements*
 - *N-dimensional numerical integration*
 - *dopri* improvements*
 - * *scipy.linalg improvements*
 - *Interpolative decompositions*
 - *Polar decomposition*
 - *BLAS level 3 functions*
 - *Matrix functions*
 - * *scipy.optimize improvements*
 - *Trust-region unconstrained minimization algorithms*
 - * *scipy.sparse improvements*
 - *Boolean comparisons and sparse matrices*
 - *CSR and CSC fancy indexing*
 - * *scipy.sparse.linalg improvements*
 - * *scipy.spatial improvements*
 - * *scipy.signal improvements*
 - * *scipy.special improvements*
 - * *scipy.io improvements*
 - *Unformatted Fortran file reader*
 - *scipy.io.wavfile enhancements*
 - * *scipy.interpolate improvements*
 - *B-spline derivatives and antiderivatives*
 - * *scipy.stats improvements*
 - *Deprecated features*
 - * *expm2 and expm3*
 - * *scipy.stats functions*
 - *Backwards incompatible changes*
 - * *LIL matrix assignment*
 - * *Deprecated radon function removed*
 - * *Removed deprecated keywords xa and xb from stats.distributions*

* *Changes to MATLAB file readers / writers*

- *Other changes*
- *Authors*

SciPy 0.13.0 is the culmination of 7 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Moreover, our development attention will now shift to bug-fix releases on the 0.13.x branch, and on adding new features on the master branch.

This release requires Python 2.6, 2.7 or 3.1-3.3 and NumPy 1.5.1 or greater. Highlights of this release are:

- support for fancy indexing and boolean comparisons with sparse matrices
- interpolative decompositions and matrix functions in the `linalg` module
- two new trust-region solvers for unconstrained minimization

3.34.1 New features

`scipy.integrate` improvements

N-dimensional numerical integration

A new function `scipy.integrate.nquad`, which provides N-dimensional integration functionality with a more flexible interface than `dblquad` and `tplquad`, has been added.

dopri* improvements

The intermediate results from the `dopri` family of ODE solvers can now be accessed by a `solout` callback function.

`scipy.linalg` improvements

Interpolative decompositions

Scipy now includes a new module `scipy.linalg.interpolative` containing routines for computing interpolative matrix decompositions (ID). This feature is based on the ID software package by P.G. Martinsson, V. Rokhlin, Y. Shkolnisky, and M. Tygert, previously adapted for Python in the `PymatrixId` package by K.L. Ho.

Polar decomposition

A new function `scipy.linalg.polar`, to compute the polar decomposition of a matrix, was added.

BLAS level 3 functions

The BLAS functions `symm`, `syrk`, `syr2k`, `hemm`, `herk` and `her2k` are now wrapped in `scipy.linalg`.

Matrix functions

Several matrix function algorithms have been implemented or updated following detailed descriptions in recent papers of Nick Higham and his co-authors. These include the matrix square root (`sqrtm`), the matrix logarithm (`logm`), the matrix exponential (`expm`) and its Frechet derivative (`expm_frechet`), and fractional matrix powers (`fractional_matrix_power`).

`scipy.optimize` improvements

Trust-region unconstrained minimization algorithms

The `minimize` function gained two trust-region solvers for unconstrained minimization: `dogleg` and `trust-ncg`.

`scipy.sparse` improvements

Boolean comparisons and sparse matrices

All sparse matrix types now support boolean data, and boolean operations. Two sparse matrices A and B can be compared in all the expected ways $A < B$, $A >= B$, $A != B$, producing similar results as dense Numpy arrays. Comparisons with dense matrices and scalars are also supported.

CSR and CSC fancy indexing

Compressed sparse row and column sparse matrix types now support fancy indexing with boolean matrices, slices, and lists. So where A is a (CSC or CSR) sparse matrix, you can do things like:

```
>>> A[A > 0.5] = 1 # since Boolean sparse matrices work
>>> A[:,2, :3] = 2
>>> A[[1,2], 2] = 3
```

`scipy.sparse.linalg` improvements

The new function `onenormest` provides a lower bound of the 1-norm of a linear operator and has been implemented according to Higham and Tisseur (2000). This function is not only useful for sparse matrices, but can also be used to estimate the norm of products or powers of dense matrices without explicitly building the intermediate matrix.

The multiplicative action of the matrix exponential of a linear operator (`expm_multiply`) has been implemented following the description in Al-Mohy and Higham (2011).

Abstract linear operators (`scipy.sparse.linalg.LinearOperator`) can now be multiplied, added to each other, and exponentiated, producing new linear operators. This enables easier construction of composite linear operations.

`scipy.spatial` improvements

The vertices of a *ConvexHull* can now be accessed via the `vertices` attribute, which gives proper orientation in 2-D.

scipy.signal improvements

The cosine window function `scipy.signal.cosine` was added.

scipy.special improvements

New functions `scipy.special.xlogy` and `scipy.special.xlog1py` were added. These functions can simplify and speed up code that has to calculate $x * \log(y)$ and give 0 when $x == 0$.

scipy.io improvements

Unformatted Fortran file reader

The new class `scipy.io.FortranFile` facilitates reading unformatted sequential files written by Fortran code.

scipy.io.wavfile enhancements

`scipy.io.wavfile.write` now accepts a file buffer. Previously it only accepted a filename.

`scipy.io.wavfile.read` and `scipy.io.wavfile.write` can now handle floating point WAV files.

scipy.interpolate improvements

B-spline derivatives and antiderivatives

`scipy.interpolate.splder` and `scipy.interpolate.splantider` functions for computing B-splines that represent derivatives and antiderivatives of B-splines were added. These functions are also available in the class-based FITPACK interface as `UnivariateSpline.derivative` and `UnivariateSpline.antiderivative`.

scipy.stats improvements

Distributions now allow using keyword parameters in addition to positional parameters in all methods.

The function `scipy.stats.power_divergence` has been added for the Cressie-Read power divergence statistic and goodness of fit test. Included in this family of statistics is the “G-test” (<https://en.wikipedia.org/wiki/G-test>).

`scipy.stats.mood` now accepts multidimensional input.

An option was added to `scipy.stats.wilcoxon` for continuity correction.

`scipy.stats.chisquare` now has an *axis* argument.

`scipy.stats.mstats.chisquare` now has *axis* and *ddof* arguments.

3.34.2 Deprecated features

expm2 and expm3

The matrix exponential functions `scipy.linalg.expm2` and `scipy.linalg.expm3` are deprecated. All users should use the numerically more robust `scipy.linalg.expm` function instead.

scipy.stats functions

`scipy.stats.oneway` is deprecated; `scipy.stats.f_oneway` should be used instead.

`scipy.stats.glm` is deprecated. `scipy.stats.ttest_ind` is an equivalent function; more full-featured general (and generalized) linear model implementations can be found in `statsmodels`.

`scipy.stats.cmedian` is deprecated; `numpy.median` should be used instead.

3.34.3 Backwards incompatible changes

LIL matrix assignment

Assigning values to LIL matrices with two index arrays now works similarly as assigning into `ndarrays`:

```
>>> x = lil_matrix((3, 3))
>>> x[[0, 1, 2], [0, 1, 2]] = [0, 1, 2]
>>> x.todense()
matrix([[ 0.,  0.,  0.],
        [ 0.,  1.,  0.],
        [ 0.,  0.,  2.]])
```

rather than giving the result:

```
>>> x.todense()
matrix([[ 0.,  1.,  2.],
        [ 0.,  1.,  2.],
        [ 0.,  1.,  2.]])
```

Users relying on the previous behavior will need to revisit their code. The previous behavior is obtained by `x[numpy.ix_([0, 1, 2], [0, 1, 2])] = ...`

Deprecated `radon` function removed

The `misc.radon` function, which was deprecated in `scipy 0.11.0`, has been removed. Users can find a more full-featured `radon` function in `scikit-image`.

Removed deprecated keywords `xa` and `xb` from `stats.distributions`

The keywords `xa` and `xb`, which were deprecated since `0.11.0`, have been removed from the distributions in `scipy.stats`.

Changes to MATLAB file readers / writers

The major change is that 1D arrays in `numpy` now become row vectors (shape `1, N`) when saved to a MATLAB 5 format file. Previously 1D arrays saved as column vectors (`N, 1`). This is to harmonize the behavior of writing MATLAB 4 and 5 formats, and adapt to the defaults of `numpy` and MATLAB - for example `np.atleast_2d` returns 1D arrays as row vectors.

Trying to save arrays of greater than 2 dimensions in MATLAB 4 format now raises an error instead of silently reshaping the array as 2D.

`scipy.io.loadmat('afile')` used to look for *afile* on the Python system path (`sys.path`); now `loadmat` only looks in the current directory for a relative path filename.

3.34.4 Other changes

Security fix: `scipy.weave` previously used temporary directories in an insecure manner under certain circumstances.

Cython is now required to build *unreleased* versions of `scipy`. The C files generated from Cython sources are not included in the git repo anymore. They are however still shipped in source releases.

The code base received a fairly large PEP8 cleanup. A `tox pep8` command has been added; new code should pass this test command.

Scipy cannot be compiled with gfortran 4.1 anymore (at least on RH5), likely due to that compiler version not supporting entry constructs well.

3.34.5 Authors

This release contains work by the following people (contributed at least one patch to this release, names in alphabetical order):

- Jorge Cañardo Alastuey +
- Tom Aldcroft +
- Max Bolingbroke +
- Joseph Jon Booker +
- François Boulogne
- Matthew Brett
- Christian Brodbeck +
- Per Brodtkorb +
- Christian Brueffer +
- Lars Buitinck
- Evgeni Burovski +
- Tim Cera
- Lawrence Chan +
- David Cournapeau
- Dražen Lučanin +
- Alexander J. Dunlap +
- endolith
- André Gaul +
- Christoph Gohlke
- Ralf Gommers
- Alex Griffing +
- Blake Griffith +

- Charles Harris
- Bob Helmbold +
- Andreas Hilboll
- Kat Huang +
- Oleksandr (Sasha) Huziy +
- Gert-Ludwig Ingold +
- Thouis (Ray) Jones
- Juan Luis Cano Rodríguez +
- Robert Kern
- Andreas Kloeckner +
- Sytse Knyppstra +
- Gustav Larsson +
- Denis Laxalde
- Christopher Lee
- Tim Leslie
- Wendy Liu +
- Clemens Novak +
- Takuya Oshima +
- Josef Perktold
- Illia Polosukhin +
- Przemek Porebski +
- Steve Richardson +
- Branden Rolston +
- Skipper Seabold
- Fazlul Shahriar
- Leo Singer +
- Rohit Sivaprasad +
- Daniel B. Smith +
- Julian Taylor
- Louis Thibault +
- Tomas Tomecek +
- John Travers
- Richard Tsai +
- Jacob Vanderplas
- Patrick Varilly
- Pauli Virtanen

- Stefan van der Walt
- Warren Weckesser
- Pedro Werneck +
- Nils Werner +
- Michael Wimmer +
- Nathan Woods +
- Tony S. Yu +

A total of 65 people contributed to this release. People with a “+” by their names contributed a patch for the first time.

3.35 SciPy 0.12.1 Release Notes

SciPy 0.12.1 is a bug-fix release with no new features compared to 0.12.0. The single issue fixed by this release is a security issue in `scipy.weave`, which was previously using temporary directories in an insecure manner under certain circumstances.

3.36 SciPy 0.12.0 Release Notes

Contents

- *SciPy 0.12.0 Release Notes*
 - *New features*
 - * *scipy.spatial improvements*
 - *cKDTree feature-complete*
 - *Voronoi diagrams and convex hulls*
 - *Delaunay improvements*
 - * *Spectral estimators (scipy.signal)*
 - * *scipy.optimize improvements*
 - *Callback functions in L-BFGS-B and TNC*
 - *Basin hopping global optimization (scipy.optimize.basinhopping)*
 - * *scipy.special improvements*
 - *Revised complex error functions*
 - *Faster orthogonal polynomials*
 - * *scipy.sparse.linalg features*
 - * *Listing Matlab(R) file contents in scipy.io*
 - * *Documented BLAS and LAPACK low-level interfaces (scipy.linalg)*
 - * *Polynomial interpolation improvements (scipy.interpolate)*
 - *Deprecated features*

- * `scipy.lib.lapack`
- * `fblas` and `cblas`
- *Backwards incompatible changes*
 - * *Removal of `scipy.io.save_as_module`*
 - * *axis argument added to `scipy.stats.scoreatpercentile`*
- *Authors*

SciPy 0.12.0 is the culmination of 7 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Moreover, our development attention will now shift to bug-fix releases on the 0.12.x branch, and on adding new features on the master branch.

Some of the highlights of this release are:

- Completed QHull wrappers in `scipy.spatial`.
- `cKDTree` now a drop-in replacement for `KDTree`.
- A new global optimizer, `basinhopping`.
- Support for Python 2 and Python 3 from the same code base (no more 2to3).

This release requires Python 2.6, 2.7 or 3.1-3.3 and NumPy 1.5.1 or greater. Support for Python 2.4 and 2.5 has been dropped as of this release.

3.36.1 New features

`scipy.spatial` improvements

`cKDTree` feature-complete

Cython version of `KDTree`, `cKDTree`, is now feature-complete. Most operations (`construction`, `query`, `query_ball_point`, `query_pairs`, `count_neighbors` and `sparse_distance_matrix`) are between 200 and 1000 times faster in `cKDTree` than in `KDTree`. With very minor caveats, `cKDTree` has exactly the same interface as `KDTree`, and can be used as a drop-in replacement.

Voronoi diagrams and convex hulls

`scipy.spatial` now contains functionality for computing Voronoi diagrams and convex hulls using the Qhull library. (Delaunay triangulation was available since Scipy 0.9.0.)

Delaunay improvements

It's now possible to pass in custom Qhull options in Delaunay triangulation. Coplanar points are now also recorded, if present. Incremental construction of Delaunay triangulations is now also possible.

Spectral estimators (`scipy.signal`)

The functions `scipy.signal.periodogram` and `scipy.signal.welch` were added, providing DFT-based spectral estimators.

`scipy.optimize` improvements

Callback functions in L-BFGS-B and TNC

A callback mechanism was added to L-BFGS-B and TNC minimization solvers.

Basin hopping global optimization (`scipy.optimize.basinhopping`)

A new global optimization algorithm. Basinhopping is designed to efficiently find the global minimum of a smooth function.

`scipy.special` improvements

Revised complex error functions

The computation of special functions related to the error function now uses a new [Faddeeva library from MIT](#) which increases their numerical precision. The scaled and imaginary error functions `erfcx` and `erfi` were also added, and the Dawson integral `dawsn` can now be evaluated for a complex argument.

Faster orthogonal polynomials

Evaluation of orthogonal polynomials (the `eval_*` routines) is now faster in `scipy.special`, and their `out=` argument functions properly.

`scipy.sparse.linalg` features

- In `scipy.sparse.linalg.spsolve`, the `b` argument can now be either a vector or a matrix.
- `scipy.sparse.linalg.inv` was added. This uses `spsolve` to compute a sparse matrix inverse.
- `scipy.sparse.linalg.expm` was added. This computes the exponential of a sparse matrix using a similar algorithm to the existing dense array implementation in `scipy.linalg.expm`.

Listing Matlab(R) file contents in `scipy.io`

A new function `whosmat` is available in `scipy.io` for inspecting contents of MAT files without reading them to memory.

Documented BLAS and LAPACK low-level interfaces (`scipy.linalg`)

The modules `scipy.linalg.blas` and `scipy.linalg.lapack` can be used to access low-level BLAS and LAPACK functions.

Polynomial interpolation improvements (`scipy.interpolate`)

The barycentric, Krogh, piecewise and pchip polynomial interpolators in `scipy.interpolate` accept now an `axis` argument.

3.36.2 Deprecated features

scipy.lib.lapack

The module `scipy.lib.lapack` is deprecated. You can use `scipy.linalg.lapack` instead. The module `scipy.lib.blas` was deprecated earlier in SciPy 0.10.0.

fblas and *cblas*

Accessing the modules `scipy.linalg.fblas`, `cblas`, `flapack`, `clapack` is deprecated. Instead, use the modules `scipy.linalg.lapack` and `scipy.linalg.blas`.

3.36.3 Backwards incompatible changes

Removal of `scipy.io.save_as_module`

The function `scipy.io.save_as_module` was deprecated in SciPy 0.11.0, and is now removed.

Its private support modules `scipy.io.dumbdbm_patched` and `scipy.io.dumb_shelve` are also removed.

axis argument added to `scipy.stats.scoreatpercentile`

The function `scipy.stats.scoreatpercentile` has been given an *axis* argument. The default argument is *axis=None*, which means the calculation is done on the flattened array. Before this change, `scoreatpercentile` would act as if *axis=0* had been given. Code using `scoreatpercentile` with a multidimensional array will need to add *axis=0* to the function call to preserve the old behavior. (This API change was not noticed until long after the release of 0.12.0.)

3.36.4 Authors

- Anton Akhmerov +
- Alexander Eberspächer +
- Anne Archibald
- Jisk Attema +
- K.-Michael Aye +
- bemasc +
- Sebastian Berg +
- François Boulogne +
- Matthew Brett
- Lars Buitinck
- Steven Byrnes +

- Tim Cera +
- Christian +
- Keith Clawson +
- David Cournapeau
- Nathan Crock +
- endolith
- Bradley M. Froehle +
- Matthew R Goodman
- Christoph Gohlke
- Ralf Gommers
- Robert David Grant +
- Yaroslav Halchenko
- Charles Harris
- Jonathan Helmus
- Andreas Hilboll
- Hugo +
- Oleksandr Huziy
- Jeroen Demeyer +
- Johannes Schönberger +
- Steven G. Johnson +
- Chris Jordan-Squire
- Jonathan Taylor +
- Niklas Kroeger +
- Jerome Kieffer +
- kingson +
- Josh Lawrence
- Denis Laxalde
- Alex Leach +
- Tim Leslie
- Richard Lindsley +
- Lorenzo Luengo +
- Stephen McQuay +
- MinRK
- Sturla Molden +
- Eric Moore +
- mszep +

- Matt Newville +
- Vlad Niculae
- Travis Oliphant
- David Parker +
- Fabian Pedregosa
- Josef Perktold
- Zach Ploskey +
- Alex Reinhart +
- Gilles Rochefort +
- Ciro Duran Santilli +
- Jan Schlueter +
- Jonathan Scholz +
- Anthony Scopatz
- Skipper Seabold
- Fabrice Silva +
- Scott Sinclair
- Jacob Stevenson +
- Sturla Molden +
- Julian Taylor +
- thorstenkranz +
- John Travers +
- True Price +
- Nicky van Foreest
- Jacob Vanderplas
- Patrick Varilly
- Daniel Velkov +
- Pauli Virtanen
- Stefan van der Walt
- Warren Weckesser

A total of 75 people contributed to this release. People with a “+” by their names contributed a patch for the first time.

3.37 SciPy 0.11.0 Release Notes

Contents

- *SciPy 0.11.0 Release Notes*
 - *New features*
 - * *Sparse Graph Submodule*
 - * *scipy.optimize improvements*
 - *Unified interfaces to minimizers*
 - *Unified interface to root finding algorithms*
 - * *scipy.linalg improvements*
 - *New matrix equation solvers*
 - *QZ and QR Decomposition*
 - *Pascal matrices*
 - * *Sparse matrix construction and operations*
 - * *LSMR iterative solver*
 - * *Discrete Sine Transform*
 - * *scipy.interpolate improvements*
 - * *Binned statistics (scipy.stats)*
 - *Deprecated features*
 - *Backwards incompatible changes*
 - * *Removal of scipy.maxentropy*
 - * *Minor change in behavior of splev*
 - * *Behavior of scipy.integrate.complex_ode*
 - * *Minor change in behavior of T-tests*
 - *Other changes*
 - *Authors*

SciPy 0.11.0 is the culmination of 8 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. Highlights of this release are:

- A new module has been added which provides a number of common sparse graph algorithms.
- New unified interfaces to the existing optimization and root finding functions have been added.

All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Our development attention will now shift to bug-fix releases on the 0.11.x branch, and on adding new features on the master branch.

This release requires Python 2.4-2.7 or 3.1-3.2 and NumPy 1.5.1 or greater.

3.37.1 New features

Sparse Graph Submodule

The new submodule `scipy.sparse.csgraph` implements a number of efficient graph algorithms for graphs stored as sparse adjacency matrices. Available routines are:

- `connected_components` - determine connected components of a graph
- `laplacian` - compute the laplacian of a graph
- `shortest_path` - compute the shortest path between points on a positive graph
- `dijkstra` - use Dijkstra's algorithm for shortest path
- `floyd_warshall` - use the Floyd-Warshall algorithm for shortest path
- `breadth_first_order` - compute a breadth-first order of nodes
- `depth_first_order` - compute a depth-first order of nodes
- `breadth_first_tree` - construct the breadth-first tree from a given node
- `depth_first_tree` - construct a depth-first tree from a given node
- `minimum_spanning_tree` - construct the minimum spanning tree of a graph

`scipy.optimize` improvements

The optimize module has received a lot of attention this release. In addition to added tests, documentation improvements, bug fixes and code clean-up, the following improvements were made:

- A unified interface to minimizers of univariate and multivariate functions has been added.
- A unified interface to root finding algorithms for multivariate functions has been added.
- The L-BFGS-B algorithm has been updated to version 3.0.

Unified interfaces to minimizers

Two new functions `scipy.optimize.minimize` and `scipy.optimize.minimize_scalar` were added to provide a common interface to minimizers of multivariate and univariate functions respectively. For multivariate functions, `scipy.optimize.minimize` provides an interface to methods for unconstrained optimization (`fmin`, `fmin_powell`, `fmin_cg`, `fmin_ncg`, `fmin_bfgs` and `anneal`) or constrained optimization (`fmin_l_bfgs_b`, `fmin_tnc`, `fmin_cobyla` and `fmin_slsqp`). For univariate functions, `scipy.optimize.minimize_scalar` provides an interface to methods for unconstrained and bounded optimization (`brent`, `golden`, `fminbound`). This allows for easier comparing and switching between solvers.

Unified interface to root finding algorithms

The new function `scipy.optimize.root` provides a common interface to root finding algorithms for multivariate functions, embedding `fsolve`, `leastsq` and `nonlin` solvers.

`scipy.linalg` improvements

New matrix equation solvers

Solvers for the Sylvester equation (`scipy.linalg.solve_sylvester`, discrete and continuous Lyapunov equations (`scipy.linalg.solve_lyapunov`, `scipy.linalg.solve_discrete_lyapunov`) and discrete and continuous algebraic Riccati equations (`scipy.linalg.solve_continuous_are`, `scipy.linalg.solve_discrete_are`) have been added to `scipy.linalg`. These solvers are often used in the field of linear control theory.

QZ and QR Decomposition

It is now possible to calculate the QZ, or Generalized Schur, decomposition using `scipy.linalg.qz`. This function wraps the LAPACK routines `sgges`, `dgges`, `cgges`, and `zgges`.

The function `scipy.linalg.qr_multiply`, which allows efficient computation of the matrix product of Q (from a QR decomposition) and a vector, has been added.

Pascal matrices

A function for creating Pascal matrices, `scipy.linalg.pascal`, was added.

Sparse matrix construction and operations

Two new functions, `scipy.sparse.diags` and `scipy.sparse.block_diag`, were added to easily construct diagonal and block-diagonal sparse matrices respectively.

`scipy.sparse.csc_matrix` and `csr_matrix` now support the operations `sin`, `tan`, `arcsin`, `arctan`, `sinh`, `tanh`, `arcsinh`, `arctanh`, `rint`, `sign`, `expm1`, `log1p`, `deg2rad`, `rad2deg`, `floor`, `ceil` and `trunc`. Previously, these operations had to be performed by operating on the matrices' `data` attribute.

LSMR iterative solver

LSMR, an iterative method for solving (sparse) linear and linear least-squares systems, was added as `scipy.sparse.linalg.lsmr`.

Discrete Sine Transform

Bindings for the discrete sine transform functions have been added to `scipy.fftpack`.

`scipy.interpolate` improvements

For interpolation in spherical coordinates, the three classes `scipy.interpolate.SmoothSphereBivariateSpline`, `scipy.interpolate.LSQSphereBivariateSpline`, and `scipy.interpolate.RectSphereBivariateSpline` have been added.

Binned statistics (`scipy.stats`)

The stats module has gained functions to do binned statistics, which are a generalization of histograms, in 1-D, 2-D and multiple dimensions: `scipy.stats.binned_statistic`, `scipy.stats.binned_statistic_2d` and `scipy.stats.binned_statistic_dd`.

3.37.2 Deprecated features

`scipy.sparse.cs_graph_components` has been made a part of the sparse graph submodule, and renamed to `scipy.sparse.csgraph.connected_components`. Calling the former routine will result in a deprecation warning.

`scipy.misc.radon` has been deprecated. A more full-featured radon transform can be found in `scikit-image`.

`scipy.io.save_as_module` has been deprecated. A better way to save multiple Numpy arrays is the `numpy.savez` function.

The `xa` and `xb` parameters for all distributions in `scipy.stats.distributions` already weren't used; they have now been deprecated.

3.37.3 Backwards incompatible changes

Removal of `scipy.maxentropy`

The `scipy.maxentropy` module, which was deprecated in the 0.10.0 release, has been removed. Logistic regression in `scikit.learn` is a good and modern alternative for this functionality.

Minor change in behavior of `splev`

The spline evaluation function now behaves similarly to `interp1d` for size-1 arrays. Previous behavior:

```
>>> from scipy.interpolate import splev, splrep, interp1d
>>> x = [1,2,3,4,5]
>>> y = [4,5,6,7,8]
>>> tck = splrep(x, y)
>>> splev([1], tck)
4.
>>> splev(1, tck)
4.
```

Corrected behavior:

```
>>> splev([1], tck)
array([ 4.])
>>> splev(1, tck)
array(4.)
```

This affects also the `UnivariateSpline` classes.

Behavior of `scipy.integrate.complex_ode`

The behavior of the `y` attribute of `complex_ode` is changed. Previously, it expressed the complex-valued solution in the form:

```
z = ode.y[:,2] + 1j * ode.y[1:,2]
```

Now, it is directly the complex-valued solution:

```
z = ode.y
```

Minor change in behavior of T-tests

The T-tests `scipy.stats.ttest_ind`, `scipy.stats.ttest_rel` and `scipy.stats.ttest_1samp` have been changed so that `0 / 0` now returns `NaN` instead of `1`.

3.37.4 Other changes

The SuperLU sources in `scipy.sparse.linalg` have been updated to version 4.3 from upstream.

The function `scipy.signal.bode`, which calculates magnitude and phase data for a continuous-time system, has been added.

The two-sample T-test `scipy.stats.ttest_ind` gained an option to compare samples with unequal variances, i.e. Welch's T-test.

`scipy.misc.logsumexp` now takes an optional `axis` keyword argument.

3.37.5 Authors

This release contains work by the following people (contributed at least one patch to this release, names in alphabetical order):

- Jeff Armstrong
- Chad Baker
- Brandon Beacher +
- behrisch +
- borishim +
- Matthew Brett
- Lars Buitinck
- Luis Pedro Coelho +
- Johann Cohen-Tanugi
- David Cournapeau
- dougal +
- Ali Ebrahim +
- endolith +
- Bjørn Forsman +

- Robert Gantner +
- Sebastian Gassner +
- Christoph Gohlke
- Ralf Gommers
- Yaroslav Halchenko
- Charles Harris
- Jonathan Helmus +
- Andreas Hilboll +
- Marc Honnorat +
- Jonathan Hunt +
- Maxim Ivanov +
- Thouis (Ray) Jones
- Christopher Kuster +
- Josh Lawrence +
- Denis Laxalde +
- Travis Oliphant
- Joonas Paalasmaa +
- Fabian Pedregosa
- Josef Perktold
- Gavin Price +
- Jim Radford +
- Andrew Schein +
- Skipper Seabold
- Jacob Silterra +
- Scott Sinclair
- Alexis Tabary +
- Martin Teichmann
- Matt Terry +
- Nicky van Foreest +
- Jacob Vanderplas
- Patrick Varilly +
- Pauli Virtanen
- Nils Wagner +
- Darryl Wally +
- Stefan van der Walt
- Liming Wang +

- David Warde-Farley +
- Warren Weckesser
- Sebastian Werk +
- Mike Wimmer +
- Tony S Yu +

A total of 55 people contributed to this release. People with a “+” by their names contributed a patch for the first time.

3.38 SciPy 0.10.1 Release Notes

Contents

- *SciPy 0.10.1 Release Notes*
 - *Main changes*
 - *Other issues fixed*

SciPy 0.10.1 is a bug-fix release with no new features compared to 0.10.0.

3.38.1 Main changes

The most important changes are:

1. The single precision routines of `eigs` and `eigsh` in `scipy.sparse.linalg` have been disabled (they internally use double precision now).
2. A compatibility issue related to changes in NumPy macros has been fixed, in order to make `scipy 0.10.1` compile with the upcoming `numpy 1.7.0` release.

3.38.2 Other issues fixed

- #835: stats: nan propagation in `stats.distributions`
- #1202: io: `netcdf` segfault
- #1531: optimize: make `curve_fit` work with `method` as callable.
- #1560: linalg: fixed mistake in `eig_banded` documentation.
- #1565: ndimage: bug in `ndimage.variance`
- #1457: ndimage: `standard_deviation` does not work with sequence of indexes
- #1562: cluster: segfault in `linkage` function
- #1568: stats: `One-sided_fisher_exact()` returns $p < 1$ for 0 successful attempts
- #1575: stats: `zscore` and `zmap` handle the `axis` keyword incorrectly

3.39 SciPy 0.10.0 Release Notes

Contents

- *SciPy 0.10.0 Release Notes*
 - *New features*
 - * *Bento: new optional build system*
 - * *Generalized and shift-invert eigenvalue problems in `scipy.sparse.linalg`*
 - * *Discrete-Time Linear Systems (`scipy.signal`)*
 - * *Enhancements to `scipy.signal`*
 - * *Additional decomposition options (`scipy.linalg`)*
 - * *Additional special matrices (`scipy.linalg`)*
 - * *Enhancements to `scipy.stats`*
 - * *Enhancements to `scipy.special`*
 - * *Basic support for Harwell-Boeing file format for sparse matrices*
 - *Deprecated features*
 - * *`scipy.maxentropy`*
 - * *`scipy.lib.blas`*
 - * *Numscons build system*
 - *Backwards-incompatible changes*
 - *Other changes*
 - *Authors*

SciPy 0.10.0 is the culmination of 8 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a limited number of deprecations and backwards-incompatible changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Moreover, our development attention will now shift to bug-fix releases on the 0.10.x branch, and on adding new features on the development master branch.

Release highlights:

- Support for Bento as optional build system.
- Support for generalized eigenvalue problems, and all shift-invert modes available in ARPACK.

This release requires Python 2.4-2.7 or 3.1- and NumPy 1.5 or greater.

3.39.1 New features

Bento: new optional build system

SciPy can now be built with **Bento**. Bento has some nice features like parallel builds and partial rebuilds, that are not possible with the default build system (distutils). For usage instructions see BENTO_BUILD.txt in the scipy top-level directory.

Currently SciPy has three build systems, distutils, numscs and bento. Numscs is deprecated and is planned and will likely be removed in the next release.

Generalized and shift-invert eigenvalue problems in `scipy.sparse.linalg`

The sparse eigenvalue problem solver functions `scipy.sparse.eigs/eigh` now support generalized eigenvalue problems, and all shift-invert modes available in ARPACK.

Discrete-Time Linear Systems (`scipy.signal`)

Support for simulating discrete-time linear systems, including `scipy.signal.dlsim`, `scipy.signal.dimpulse`, and `scipy.signal.dstep`, has been added to SciPy. Conversion of linear systems from continuous-time to discrete-time representations is also present via the `scipy.signal.cont2discrete` function.

Enhancements to `scipy.signal`

A Lomb-Scargle periodogram can now be computed with the new function `scipy.signal.lombscargle`.

The forward-backward filter function `scipy.signal.filtfilt` can now filter the data in a given axis of an n-dimensional numpy array. (Previously it only handled a 1-dimensional array.) Options have been added to allow more control over how the data is extended before filtering.

FIR filter design with `scipy.signal.firwin2` now has options to create filters of type III (zero at zero and Nyquist frequencies) and IV (zero at zero frequency).

Additional decomposition options (`scipy.linalg`)

A sort keyword has been added to the Schur decomposition routine (`scipy.linalg.schur`) to allow the sorting of eigenvalues in the resultant Schur form.

Additional special matrices (`scipy.linalg`)

The functions `hilbert` and `invhilbert` were added to `scipy.linalg`.

Enhancements to `scipy.stats`

- The *one-sided form* of Fisher's exact test is now also implemented in `stats.fisher_exact`.
- The function `stats.chi2_contingency` for computing the chi-square test of independence of factors in a contingency table has been added, along with the related utility functions `stats.contingency.margins` and `stats.contingency.expected_freq`.

Enhancements to `scipy.special`

The functions $\text{logit}(p) = \log(p/(1-p))$ and $\text{expit}(x) = 1/(1+\exp(-x))$ have been implemented as `scipy.special.logit` and `scipy.special.expit` respectively.

Basic support for Harwell-Boeing file format for sparse matrices

Both read and write are support through a simple function-based API, as well as a more complete API to control number format. The functions may be found in `scipy.sparse.io`.

The following features are supported:

- Read and write sparse matrices in the CSC format
- Only real, symmetric, assembled matrix are supported (RUA format)

3.39.2 Deprecated features

`scipy.maxentropy`

The `maxentropy` module is unmaintained, rarely used and has not been functioning well for several releases. Therefore it has been deprecated for this release, and will be removed for `scipy 0.11`. Logistic regression in `scikits.learn` is a good alternative for this functionality. The `scipy.maxentropy.logsumexp` function has been moved to `scipy.misc`.

`scipy.lib.blas`

There are similar BLAS wrappers in `scipy.linalg` and `scipy.lib`. These have now been consolidated as `scipy.linalg.blas`, and `scipy.lib.blas` is deprecated.

Numscons build system

The `numscons` build system is being replaced by `Bento`, and will be removed in one of the next `scipy` releases.

3.39.3 Backwards-incompatible changes

The deprecated name `invnorm` was removed from `scipy.stats.distributions`, this distribution is available as `invgauss`.

The following deprecated nonlinear solvers from `scipy.optimize` have been removed:

```
- ``broyden_modified`` (bad performance)
- ``broyden1_modified`` (bad performance)
- ``broyden_generalized`` (equivalent to ``anderson``)
- ``anderson2`` (equivalent to ``anderson``)
- ``broyden3`` (obsoleted by new limited-memory broyden methods)
- ``vackar`` (renamed to ``diagbroyden``)
```

3.39.4 Other changes

`scipy.constants` has been updated with the CODATA 2010 constants.

`__all__` dicts have been added to all modules, which has cleaned up the namespaces (particularly useful for interactive work).

An API section has been added to the documentation, giving recommended import guidelines and specifying which submodules are public and which aren't.

3.39.5 Authors

This release contains work by the following people (contributed at least one patch to this release, names in alphabetical order):

- Jeff Armstrong +
- Matthew Brett
- Lars Buitinck +
- David Cournapeau
- FISH 2000 +
- Michael McNeil Forbes +
- Matty G +
- Christoph Gohlke
- Ralf Gommers
- Yaroslav Halchenko
- Charles Harris
- Thouis (Ray) Jones +
- Chris Jordan-Squire +
- Robert Kern
- Chris Lasher +
- Wes McKinney +
- Travis Oliphant
- Fabian Pedregosa
- Josef Perktold
- Thomas Robitaille +

- Pim Schellart +
- Anthony Scopatz +
- Skipper Seabold +
- Fazlul Shahriar +
- David Simcha +
- Scott Sinclair +
- Andrey Smirnov +
- Collin RM Stocks +
- Martin Teichmann +
- Jake Vanderplas +
- Gaël Varoquaux +
- Pauli Virtanen
- Stefan van der Walt
- Warren Weckesser
- Mark Wiebe +

A total of 35 people contributed to this release. People with a “+” by their names contributed a patch for the first time.

3.40 SciPy 0.9.0 Release Notes

Contents

- *SciPy 0.9.0 Release Notes*
 - *Python 3*
 - *Scipy source code location to be changed*
 - *New features*
 - * *Delaunay tessellations (`scipy.spatial`)*
 - * *N-dimensional interpolation (`scipy.interpolate`)*
 - * *Nonlinear equation solvers (`scipy.optimize`)*
 - * *New linear algebra routines (`scipy.linalg`)*
 - * *Improved FIR filter design functions (`scipy.signal`)*
 - * *Improved statistical tests (`scipy.stats`)*
 - *Deprecated features*
 - * *Obsolete nonlinear solvers (in `scipy.optimize`)*
 - *Removed features*
 - * *Old correlate/convolve behavior (in `scipy.signal`)*
 - * *`scipy.stats`*

- * `scipy.sparse`
- * `scipy.sparse.linalg.arpack.speigs`
- *Other changes*
 - * *ARPACK interface changes*

SciPy 0.9.0 is the culmination of 6 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Moreover, our development attention will now shift to bug-fix releases on the 0.9.x branch, and on adding new features on the development trunk.

This release requires Python 2.4 - 2.7 or 3.1 - and NumPy 1.5 or greater.

Please note that SciPy is still considered to have “Beta” status, as we work toward a SciPy 1.0.0 release. The 1.0.0 release will mark a major milestone in the development of SciPy, after which changing the package structure or API will be much more difficult. Whilst these pre-1.0 releases are considered to have “Beta” status, we are committed to making them as bug-free as possible.

However, until the 1.0 release, we are aggressively reviewing and refining the functionality, organization, and interface. This is being done in an effort to make the package as coherent, intuitive, and useful as possible. To achieve this, we need help from the community of users. Specifically, we need feedback regarding all aspects of the project - everything - from which algorithms we implement, to details about our function’s call signatures.

3.40.1 Python 3

Scipy 0.9.0 is the first SciPy release to support Python 3. The only module that is not yet ported is `scipy.weave`.

3.40.2 Scipy source code location to be changed

Soon after this release, Scipy will stop using SVN as the version control system, and move to Git. The development source code for Scipy can from then on be found at

<https://github.com/scipy/scipy>

3.40.3 New features

Delaunay tessellations (`scipy.spatial`)

Scipy now includes routines for computing Delaunay tessellations in N dimensions, powered by the [Qhull](#) computational geometry library. Such calculations can now make use of the new `scipy.spatial.Delaunay` interface.

N-dimensional interpolation (`scipy.interpolate`)

Support for scattered data interpolation is now significantly improved. This version includes a `scipy.interpolate.griddata` function that can perform linear and nearest-neighbour interpolation for N-dimensional scattered data, in addition to cubic spline (C1-smooth) interpolation in 2D and 1D. An object-oriented interface to each interpolator type is also available.

Nonlinear equation solvers (`scipy.optimize`)

Scipy includes new routines for large-scale nonlinear equation solving in `scipy.optimize`. The following methods are implemented:

- Newton-Krylov (`scipy.optimize.newton_krylov`)
- (Generalized) secant methods:
 - Limited-memory Broyden methods (`scipy.optimize.broyden1`, `scipy.optimize.broyden2`)
 - Anderson method (`scipy.optimize.anderson`)
- Simple iterations (`scipy.optimize.diagbroyden`, `scipy.optimize.excitingmixing`, `scipy.optimize.linearmixing`)

The `scipy.optimize.nonlin` module was completely rewritten, and some of the functions were deprecated (see above).

New linear algebra routines (`scipy.linalg`)

Scipy now contains routines for effectively solving triangular equation systems (`scipy.linalg.solve_triangular`).

Improved FIR filter design functions (`scipy.signal`)

The function `scipy.signal.firwin` was enhanced to allow the design of highpass, bandpass, bandstop and multi-band FIR filters.

The function `scipy.signal.firwin2` was added. This function uses the window method to create a linear phase FIR filter with an arbitrary frequency response.

The functions `scipy.signal.kaiser_atten` and `scipy.signal.kaiser_beta` were added.

Improved statistical tests (`scipy.stats`)

A new function `scipy.stats.fisher_exact` was added, that provides Fisher's exact test for 2x2 contingency tables.

The function `scipy.stats.kendalltau` was rewritten to make it much faster ($O(n \log(n))$ vs $O(n^2)$).

3.40.4 Deprecated features

Obsolete nonlinear solvers (in `scipy.optimize`)

The following nonlinear solvers from `scipy.optimize` are deprecated:

- `broyden_modified` (bad performance)
- `broyden1_modified` (bad performance)
- `broyden_generalized` (equivalent to `anderson`)
- `anderson2` (equivalent to `anderson`)
- `broyden3` (obsoleted by new limited-memory broyden methods)
- `vackar` (renamed to `diagbroyden`)

3.40.5 Removed features

The deprecated modules `helpmod`, `pexec` and `ppimport` were removed from `scipy.misc`.

The `output_type` keyword in many `scipy.ndimage` interpolation functions has been removed.

The `econ` keyword in `scipy.linalg.qr` has been removed. The same functionality is still available by specifying `mode='economic'`.

Old correlate/convolve behavior (in `scipy.signal`)

The old behavior for `scipy.signal.convolve`, `scipy.signal.convolve2d`, `scipy.signal.correlate` and `scipy.signal.correlate2d` was deprecated in 0.8.0 and has now been removed. `Convolve` and `correlate` used to swap their arguments if the second argument has dimensions larger than the first one, and the mode was relative to the input with the largest dimension. The current behavior is to never swap the inputs, which is what most people expect, and is how correlation is usually defined.

`scipy.stats`

Many functions in `scipy.stats` that are either available from `numpy` or have been superseded, and have been deprecated since version 0.7, have been removed: `std`, `var`, `mean`, `median`, `cov`, `corrcoef`, `z`, `zs`, `stderr`, `samplestd`, `samplevar`, `pdfapprox`, `pdf_moments` and `erfc`. These changes are mirrored in `scipy.stats.mstats`.

`scipy.sparse`

Several methods of the sparse matrix classes in `scipy.sparse` which had been deprecated since version 0.7 were removed: `save`, `rowcol`, `getdata`, `listprint`, `ensure_sorted_indices`, `matvec`, `matmat` and `rmatvec`.

The functions `spkron`, `speye`, `spidentity`, `lil_eye` and `lil_diags` were removed from `scipy.sparse`. The first three functions are still available as `scipy.sparse.kron`, `scipy.sparse.eye` and `scipy.sparse.identity`.

The `dims` and `nzmax` keywords were removed from the sparse matrix constructor. The `colind` and `rowind` attributes were removed from CSR and CSC matrices respectively.

`scipy.sparse.linalg.arpack.speigs`

A duplicated interface to the ARPACK library was removed.

3.40.6 Other changes

ARPACK interface changes

The interface to the ARPACK eigenvalue routines in `scipy.sparse.linalg` was changed for more robustness.

The eigenvalue and SVD routines now raise `ArpackNoConvergence` if the eigenvalue iteration fails to converge. If partially converged results are desired, they can be accessed as follows:

```
import numpy as np
from scipy.sparse.linalg import eigs, ArpackNoConvergence

m = np.random.randn(30, 30)
try:
    w, v = eigs(m, 6)
except ArpackNoConvergence, err:
    partially_converged_w = err.eigenvalues
    partially_converged_v = err.eigenvectors
```

Several bugs were also fixed.

The routines were moreover renamed as follows:

- `eigen` → `eigs`
- `eigen_symmetric` → `eigsh`
- `svd` → `svds`

3.41 SciPy 0.8.0 Release Notes

Contents

- *SciPy 0.8.0 Release Notes*
 - *Python 3*
 - *Major documentation improvements*
 - *Deprecated features*
 - * *Swapping inputs for correlation functions (`scipy.signal`)*
 - * *Obsolete code deprecated (`scipy.misc`)*
 - * *Additional deprecations*
 - *New features*
 - * *DCT support (`scipy.fftpack`)*
 - * *Single precision support for fft functions (`scipy.fftpack`)*

- * *Correlation functions now implement the usual definition (scipy.signal)*
- * *Additions and modification to LTI functions (scipy.signal)*
- * *Improved waveform generators (scipy.signal)*
- * *New functions and other changes in scipy.linalg*
- * *New function and changes in scipy.optimize*
- * *New sparse least squares solver*
- * *ARPACK-based sparse SVD*
- * *Alternative behavior available for scipy.constants.find*
- * *Incomplete sparse LU decompositions*
- * *Faster matlab file reader and default behavior change*
- * *Faster evaluation of orthogonal polynomials*
- * *Lambert W function*
- * *Improved hypergeometric 2F1 function*
- * *More flexible interface for Radial basis function interpolation*
- *Removed features*
 - * *scipy.io*

SciPy 0.8.0 is the culmination of 17 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Moreover, our development attention will now shift to bug-fix releases on the 0.8.x branch, and on adding new features on the development trunk. This release requires Python 2.4 - 2.6 and NumPy 1.4.1 or greater.

Please note that SciPy is still considered to have “Beta” status, as we work toward a SciPy 1.0.0 release. The 1.0.0 release will mark a major milestone in the development of SciPy, after which changing the package structure or API will be much more difficult. Whilst these pre-1.0 releases are considered to have “Beta” status, we are committed to making them as bug-free as possible.

However, until the 1.0 release, we are aggressively reviewing and refining the functionality, organization, and interface. This is being done in an effort to make the package as coherent, intuitive, and useful as possible. To achieve this, we need help from the community of users. Specifically, we need feedback regarding all aspects of the project - everything - from which algorithms we implement, to details about our function’s call signatures.

3.41.1 Python 3

Python 3 compatibility is planned and is currently technically feasible, since Numpy has been ported. However, since the Python 3 compatible Numpy 1.5 has not been released yet, support for Python 3 in Scipy is not yet included in Scipy 0.8. SciPy 0.9, planned for fall 2010, will very likely include experimental support for Python 3.

3.41.2 Major documentation improvements

SciPy documentation is greatly improved.

3.41.3 Deprecated features

Swapping inputs for correlation functions (`scipy.signal`)

Concern `correlate`, `correlate2d`, `convolve` and `convolve2d`. If the second input is larger than the first input, the inputs are swapped before calling the underlying computation routine. This behavior is deprecated, and will be removed in `scipy` 0.9.0.

Obsolete code deprecated (`scipy.misc`)

The modules `helpmod`, `ppimport` and `pexec` from `scipy.misc` are deprecated. They will be removed from SciPy in version 0.9.

Additional deprecations

- `linalg`: The function `solveh_banded` currently returns a tuple containing the Cholesky factorization and the solution to the linear system. In SciPy 0.9, the return value will be just the solution.
- The function `constants.codata.find` will generate a `DeprecationWarning`. In Scipy version 0.8.0, the keyword argument `'disp'` was added to the function, with the default value `'True'`. In 0.9.0, the default will be `'False'`.
- The `qshape` keyword argument of `signal.chirp` is deprecated. Use the argument `vertex_zero` instead.
- Passing the coefficients of a polynomial as the argument `f0` to `signal.chirp` is deprecated. Use the function `signal.sweep_poly` instead.
- The `io.recaster` module has been deprecated and will be removed in 0.9.0.

3.41.4 New features

DCT support (`scipy.fftpack`)

New realtransforms have been added, namely `dct` and `idct` for Discrete Cosine Transform; type I, II and III are available.

Single precision support for fft functions (`scipy.fftpack`)

fft functions can now handle single precision inputs as well: `fft(x)` will return a single precision array if `x` is single precision. At the moment, for FFT sizes that are not composites of 2, 3, and 5, the transform is computed internally in double precision to avoid rounding error in FFTPACK.

Correlation functions now implement the usual definition (`scipy.signal`)

The outputs should now correspond to their matlab and R counterparts, and do what most people expect if the `old_behavior=False` argument is passed:

- `correlate`, `convolve` and their 2d counterparts do not swap their inputs depending on their relative shape anymore;
- correlation functions now conjugate their second argument while computing the slided sum-products, which correspond to the usual definition of correlation.

Additions and modification to LTI functions (`scipy.signal`)

- The functions `impulse2` and `step2` were added to `scipy.signal`. They use the function `scipy.signal.lsim2` to compute the impulse and step response of a system, respectively.
- The function `scipy.signal.lsim2` was changed to pass any additional keyword arguments to the ODE solver.

Improved waveform generators (`scipy.signal`)

Several improvements to the `chirp` function in `scipy.signal` were made:

- The waveform generated when `method="logarithmic"` was corrected; it now generates a waveform that is also known as an “exponential” or “geometric” chirp. (See <https://en.wikipedia.org/wiki/Chirp>.)
- A new `chirp` method, “hyperbolic”, was added.
- Instead of the keyword `qshape`, `chirp` now uses the keyword `vertex_zero`, a boolean.
- `chirp` no longer handles an arbitrary polynomial. This functionality has been moved to a new function, `sweep_poly`.

A new function, `sweep_poly`, was added.

New functions and other changes in `scipy.linalg`

The functions `cho_solve_banded`, `circulant`, `companion`, `hadamard` and `leslie` were added to `scipy.linalg`.

The function `block_diag` was enhanced to accept scalar and 1D arguments, along with the usual 2D arguments.

New function and changes in `scipy.optimize`

The `curve_fit` function has been added; it takes a function and uses non-linear least squares to fit that to the provided data.

The `leastsq` and `fsolve` functions now return an array of size one instead of a scalar when solving for a single parameter.

New sparse least squares solver

The `lsqr` function was added to `scipy.sparse`. This routine finds a least-squares solution to a large, sparse, linear system of equations.

ARPACK-based sparse SVD

A naive implementation of SVD for sparse matrices is available in `scipy.sparse.linalg.eigen.arpack`. It is based on using an symmetric solver on $\langle A, A \rangle$, and as such may not be very precise.

Alternative behavior available for `scipy.constants.find`

The keyword argument `disp` was added to the function `scipy.constants.find`, with the default value `True`. When `disp` is `True`, the behavior is the same as in Scipy version 0.7. When `False`, the function returns the list of keys instead of printing them. (In SciPy version 0.9, the default will be reversed.)

Incomplete sparse LU decompositions

Scipy now wraps SuperLU version 4.0, which supports incomplete sparse LU decompositions. These can be accessed via `scipy.sparse.linalg.spilu`. Upgrade to SuperLU 4.0 also fixes some known bugs.

Faster matlab file reader and default behavior change

We've rewritten the matlab file reader in Cython and it should now read matlab files at around the same speed that Matlab does.

The reader reads matlab named and anonymous functions, but it can't write them.

Until scipy 0.8.0 we have returned arrays of matlab structs as numpy object arrays, where the objects have attributes named for the struct fields. As of 0.8.0, we return matlab structs as numpy structured arrays. You can get the older behavior by using the optional `struct_as_record=False` keyword argument to `scipy.io.loadmat` and friends.

There is an inconsistency in the matlab file writer, in that it writes numpy 1D arrays as column vectors in matlab 5 files, and row vectors in matlab 4 files. We will change this in the next version, so both write row vectors. There is a *FutureWarning* when calling the writer to warn of this change; for now we suggest using the `oned_as='row'` keyword argument to `scipy.io.savemat` and friends.

Faster evaluation of orthogonal polynomials

Values of orthogonal polynomials can be evaluated with new vectorized functions in `scipy.special`: `eval_legendre`, `eval_chebyt`, `eval_chebyu`, `eval_chebyc`, `eval_chebys`, `eval_jacobi`, `eval_laguerre`, `eval_genlaguerre`, `eval_hermite`, `eval_hermitenorm`, `eval_gegenbauer`, `eval_sh_legendre`, `eval_sh_chebyt`, `eval_sh_chebyu`, `eval_sh_jacobi`. This is faster than constructing the full coefficient representation of the polynomials, which was previously the only available way.

Note that the previous orthogonal polynomial routines will now also invoke this feature, when possible.

Lambert W function

`scipy.special.lambertw` can now be used for evaluating the Lambert W function.

Improved hypergeometric 2F1 function

Implementation of `scipy.special.hyp2f1` for real parameters was revised. The new version should produce accurate values for all real parameters.

More flexible interface for Radial basis function interpolation

The `scipy.interpolate.Rbf` class now accepts a callable as input for the “function” argument, in addition to the built-in radial basis functions which can be selected with a string argument.

3.41.5 Removed features

`scipy.stsci`: the package was removed

The module `scipy.misc.limits` was removed.

scipy.io

The IO code in both NumPy and SciPy is being extensively reworked. NumPy will be where basic code for reading and writing NumPy arrays is located, while SciPy will house file readers and writers for various data formats (data, audio, video, images, matlab, etc.).

Several functions in `scipy.io` are removed in the 0.8.0 release including: `npfile`, `save`, `load`, `create_module`, `create_shelf`, `objload`, `objsave`, `fopen`, `read_array`, `write_array`, `fread`, `fwrite`, `bswap`, `packbits`, `unpackbits`, and `convert_objectarray`. Some of these functions have been replaced by NumPy’s raw reading and writing capabilities, memory-mapping capabilities, or array methods. Others have been moved from SciPy to NumPy, since basic array reading and writing capability is now handled by NumPy.

3.42 SciPy 0.7.2 Release Notes

Contents

- [SciPy 0.7.2 Release Notes](#)

SciPy 0.7.2 is a bug-fix release with no new features compared to 0.7.1. The only change is that all C sources from Cython code have been regenerated with Cython 0.12.1. This fixes the incompatibility between binaries of SciPy 0.7.1 and NumPy 1.4.

3.43 SciPy 0.7.1 Release Notes

Contents

- *SciPy 0.7.1 Release Notes*
 - *scipy.io*
 - *scipy.odr*
 - *scipy.signal*
 - *scipy.sparse*
 - *scipy.special*
 - *scipy.stats*
 - *Windows binaries for python 2.6*
 - *Universal build for scipy*

SciPy 0.7.1 is a bug-fix release with no new features compared to 0.7.0.

3.43.1 **scipy.io**

Bugs fixed:

- Several fixes in Matlab file IO

3.43.2 **scipy.odr**

Bugs fixed:

- Work around a failure with Python 2.6

3.43.3 **scipy.signal**

Memory leak in lfilter have been fixed, as well as support for array object

Bugs fixed:

- #880, #925: lfilter fixes
- #871: bicgstab fails on Win32

3.43.4 `scipy.sparse`

Bugs fixed:

- #883: `scipy.io.mmread` with `scipy.sparse.lil_matrix` broken
- `lil_matrix` and `csc_matrix` reject now unexpected sequences, cf. <http://thread.gmane.org/gmane.comp.python.scientific.user/19996> (dead link)

3.43.5 `scipy.special`

Several bugs of varying severity were fixed in the special functions:

- #503, #640: `iv`: problems at large arguments fixed by new implementation
- #623: `jv`: fix errors at large arguments
- #679: `struve`: fix wrong output for $v < 0$
- #803: `pbdv` produces invalid output
- #804: `lqmn`: fix crashes on some input
- #823: `betainc`: fix documentation
- #834: `exp1` strange behavior near negative integer values
- #852: `jn_zeros`: more accurate results for large s , also in `jnp/yn/ynp_zeros`
- #853: `jv`, `yv`, `iv`: invalid results for non-integer $v < 0$, complex x
- #854: `jv`, `yv`, `iv`, : return nan more consistently when out-of-domain
- #927: `ellipj`: fix segfault on Windows
- #946: `ellpj`: fix segfault on Mac OS X/python 2.6 combination.
- `ive`, `jve`, `yve`, , `kve`: with real-valued input, return nan for out-of-domain instead of returning only the real part of the result.

Also, when `scipy.special.errprint(1)` has been enabled, warning messages are now issued as Python warnings instead of printing them to `stderr`.

3.43.6 `scipy.stats`

- `linregress`, `mannwhitneyu`, `describe`: errors fixed
- `kstwobign`, `norm`, `expon`, `exponweib`, `exponpow`, `frechet`, `genexpon`, `rdist`, `truncexpon`, `planck`: improvements to numerical accuracy in distributions

3.43.7 Windows binaries for python 2.6

python 2.6 binaries for windows are now included. The binary for python 2.5 requires numpy 1.2.0 or above, and the one for python 2.6 requires numpy 1.3.0 or above.

3.43.8 Universal build for scipy

Mac OS X binary installer is now a proper universal build, and does not depend on gfortran anymore (libgfortran is statically linked). The python 2.5 version of scipy requires numpy 1.2.0 or above, the python 2.6 version requires numpy 1.3.0 or above.

3.44 SciPy 0.7.0 Release Notes

Contents

- *SciPy 0.7.0 Release Notes*
 - *Python 2.6 and 3.0*
 - *Major documentation improvements*
 - *Running Tests*
 - *Building SciPy*
 - *Sandbox Removed*
 - *Sparse Matrices*
 - *Statistics package*
 - *Reworking of IO package*
 - *New Hierarchical Clustering module*
 - *New Spatial package*
 - *Reworked fftpack package*
 - *New Constants package*
 - *New Radial Basis Function module*
 - *New complex ODE integrator*
 - *New generalized symmetric and hermitian eigenvalue problem solver*
 - *Bug fixes in the interpolation package*
 - *Weave clean up*
 - *Known problems*

SciPy 0.7.0 is the culmination of 16 months of hard work. It contains many new features, numerous bug-fixes, improved test coverage and better documentation. There have been a number of deprecations and API changes in this release, which are documented below. All users are encouraged to upgrade to this release, as there are a large number of bug-fixes and optimizations. Moreover, our development attention will now shift to bug-fix releases on the 0.7.x branch, and on adding new features on the development trunk. This release requires Python 2.4 or 2.5 and NumPy 1.2 or greater.

Please note that SciPy is still considered to have “Beta” status, as we work toward a SciPy 1.0.0 release. The 1.0.0 release will mark a major milestone in the development of SciPy, after which changing the package structure or API will be much more difficult. Whilst these pre-1.0 releases are considered to have “Beta” status, we are committed to making them as bug-free as possible. For example, in addition to fixing numerous bugs in this release, we have also doubled the number of unit tests since the last release.

However, until the 1.0 release, we are aggressively reviewing and refining the functionality, organization, and interface. This is being done in an effort to make the package as coherent, intuitive, and useful as possible. To achieve this, we need help from the community of users. Specifically, we need feedback regarding all aspects of the project - everything - from which algorithms we implement, to details about our function’s call signatures.

Over the last year, we have seen a rapid increase in community involvement, and numerous infrastructure improvements to lower the barrier to contributions (e.g., more explicit coding standards, improved testing infrastructure, better documentation tools). Over the next year, we hope to see this trend continue and invite everyone to become more involved.

3.44.1 Python 2.6 and 3.0

A significant amount of work has gone into making SciPy compatible with Python 2.6; however, there are still some issues in this regard. The main issue with 2.6 support is NumPy. On UNIX (including Mac OS X), NumPy 1.2.1 mostly works, with a few caveats. On Windows, there are problems related to the compilation process. The upcoming NumPy 1.3 release will fix these problems. Any remaining issues with 2.6 support for SciPy 0.7 will be addressed in a bug-fix release.

Python 3.0 is not supported at all; it requires NumPy to be ported to Python 3.0. This requires immense effort, since a lot of C code has to be ported. The transition to 3.0 is still under consideration; currently, we don’t have any timeline or roadmap for this transition.

3.44.2 Major documentation improvements

SciPy documentation is greatly improved; you can view a HTML reference manual [online](#) or download it as a PDF file. The new reference guide was built using the popular [Sphinx](#) tool.

This release also includes an updated tutorial, which hadn’t been available since SciPy was ported to NumPy in 2005. Though not comprehensive, the tutorial shows how to use several essential parts of SciPy. It also includes the `ndimage` documentation from the `numarray` manual.

Nevertheless, more effort is needed on the documentation front. Luckily, contributing to SciPy documentation is now easier than before: if you find that a part of it requires improvements, and want to help us out, please register a user name in our web-based documentation editor at <https://docs.scipy.org/> and correct the issues.

3.44.3 Running Tests

NumPy 1.2 introduced a new testing framework based on `nose`. Starting with this release, SciPy now uses the new NumPy test framework as well. Taking advantage of the new testing framework requires `nose` version 0.10, or later. One major advantage of the new framework is that it greatly simplifies writing unit tests - which has all ready paid off, given the rapid increase in tests. To run the full test suite:

```
>>> import scipy
>>> scipy.test('full')
```

For more information, please see [The NumPy/SciPy Testing Guide](#).

We have also greatly improved our test coverage. There were just over 2,000 unit tests in the 0.6.0 release; this release nearly doubles that number, with just over 4,000 unit tests.

3.44.4 Building SciPy

Support for NumScons has been added. NumScons is a tentative new build system for NumPy/SciPy, using SCons at its core.

SCons is a next-generation build system, intended to replace the venerable Make with the integrated functionality of autoconf/automake and ccache. Scons is written in Python and its configuration files are Python scripts. NumScons is meant to replace NumPy's custom version of distutils providing more advanced functionality, such as autoconf, improved fortran support, more tools, and support for `numpy.distutils/scons` cooperation.

3.44.5 Sandbox Removed

While porting SciPy to NumPy in 2005, several packages and modules were moved into `scipy.sandbox`. The sandbox was a staging ground for packages that were undergoing rapid development and whose APIs were in flux. It was also a place where broken code could live. The sandbox has served its purpose well, but was starting to create confusion. Thus `scipy.sandbox` was removed. Most of the code was moved into `scipy`, some code was made into a `scikit`, and the remaining code was just deleted, as the functionality had been replaced by other code.

3.44.6 Sparse Matrices

Sparse matrices have seen extensive improvements. There is now support for integer dtypes such `int8`, `uint32`, etc. Two new sparse formats were added:

- new class `dia_matrix`: the sparse DIAGONAL format
- new class `bsr_matrix`: the Block CSR format

Several new sparse matrix construction functions were added:

- `sparse.kron`: sparse Kronecker product
- `sparse.bmat`: sparse version of `numpy.bmat`
- `sparse.vstack`: sparse version of `numpy.vstack`
- `sparse.hstack`: sparse version of `numpy.hstack`

Extraction of submatrices and nonzero values have been added:

- `sparse.tril`: extract lower triangle
- `sparse.triu`: extract upper triangle
- `sparse.find`: nonzero values and their indices

`csr_matrix` and `csc_matrix` now support slicing and fancy indexing (e.g., `A[1:3, 4:7]` and `A[[3,2,6,8],:]`). Conversions among all sparse formats are now possible:

- using member functions such as `.tocsr()` and `.tolil()`
- using the `.asformat()` member function, e.g. `A.asformat('csr')`
- using constructors `A = lil_matrix([[1,2]]); B = csr_matrix(A)`

All sparse constructors now accept dense matrices and lists of lists. For example:

- `A = csr_matrix(rand(3,3))` and `B = lil_matrix([[1,2],[3,4]])`

The handling of diagonals in the `spdiags` function has been changed. It now agrees with the MATLAB(TM) function of the same name.

Numerous efficiency improvements to format conversions and sparse matrix arithmetic have been made. Finally, this release contains numerous bugfixes.

3.44.7 Statistics package

Statistical functions for masked arrays have been added, and are accessible through `scipy.stats.mstats`. The functions are similar to their counterparts in `scipy.stats` but they have not yet been verified for identical interfaces and algorithms.

Several bugs were fixed for statistical functions, of those, `kstest` and `percentileofscore` gained new keyword arguments.

Added deprecation warning for `mean`, `median`, `var`, `std`, `cov`, and `corrcoef`. These functions should be replaced by their numpy counterparts. Note, however, that some of the default options differ between the `scipy.stats` and numpy versions of these functions.

Numerous bug fixes to `stats.distributions`: all generic methods now work correctly, several methods in individual distributions were corrected. However, a few issues remain with higher moments (`skew`, `kurtosis`) and entropy. The maximum likelihood estimator, `fit`, does not work out-of-the-box for some distributions - in some cases, starting values have to be carefully chosen, in other cases, the generic implementation of the maximum likelihood method might not be the numerically appropriate estimation method.

We expect more bugfixes, increases in numerical precision and enhancements in the next release of `scipy`.

3.44.8 Reworking of IO package

The IO code in both NumPy and SciPy is being extensively reworked. NumPy will be where basic code for reading and writing NumPy arrays is located, while SciPy will house file readers and writers for various data formats (data, audio, video, images, matlab, etc.).

Several functions in `scipy.io` have been deprecated and will be removed in the 0.8.0 release including `npfile`, `save`, `load`, `create_module`, `create_shelf`, `objload`, `objsave`, `fopen`, `read_array`, `write_array`, `fread`, `fwrite`, `bswap`, `packbits`, `unpackbits`, and `convert_objectarray`. Some of these functions have been replaced by NumPy's raw reading and writing capabilities, memory-mapping capabilities, or array methods. Others have been moved from SciPy to NumPy, since basic array reading and writing capability is now handled by NumPy.

The Matlab (TM) file readers/writers have a number of improvements:

- default version 5
- v5 writers for structures, cell arrays, and objects
- v5 readers/writers for function handles and 64-bit integers
- new `struct_as_record` keyword argument to `loadmat`, which loads struct arrays in matlab as record arrays in numpy
- string arrays have `dtype='U...'` instead of `dtype=object`
- `loadmat` no longer squeezes singleton dimensions, i.e. `squeeze_me=False` by default

3.44.9 New Hierarchical Clustering module

This module adds new hierarchical clustering functionality to the `scipy.cluster` package. The function interfaces are similar to the functions provided MATLAB(TM)'s Statistics Toolbox to help facilitate easier migration to the NumPy/SciPy framework. Linkage methods implemented include single, complete, average, weighted, centroid, median, and ward.

In addition, several functions are provided for computing inconsistency statistics, cophenetic distance, and maximum distance between descendants. The `fcluster` and `fclusterdata` functions transform a hierarchical clustering into a set of flat clusters. Since these flat clusters are generated by cutting the tree into a forest of trees, the `leaders` function takes a linkage and a flat clustering, and finds the root of each tree in the forest. The `ClusterNode` class represents a hierarchical clustering as a field-navigable tree object. `to_tree` converts a matrix-encoded hierarchical clustering to a `ClusterNode` object. Routines for converting between MATLAB and SciPy linkage encodings are provided. Finally, a `dendrogram` function plots hierarchical clusterings as a dendrogram, using `matplotlib`.

3.44.10 New Spatial package

The new spatial package contains a collection of spatial algorithms and data structures, useful for spatial statistics and clustering applications. It includes rapidly compiled code for computing exact and approximate nearest neighbors, as well as a pure-python kd-tree with the same interface, but that supports annotation and a variety of other algorithms. The API for both modules may change somewhat, as user requirements become clearer.

It also includes a `distance` module, containing a collection of distance and dissimilarity functions for computing distances between vectors, which is useful for spatial statistics, clustering, and kd-trees. Distance and dissimilarity functions provided include Bray-Curtis, Canberra, Chebyshev, City Block, Cosine, Dice, Euclidean, Hamming, Jaccard, Kulinski, Mahalanobis, Matching, Minkowski, Rogers-Tanimoto, Russell-Rao, Squared Euclidean, Standardized Euclidean, Sokal-Michener, Sokal-Sneath, and Yule.

The `pdist` function computes pairwise distance between all unordered pairs of vectors in a set of vectors. The `cdist` computes the distance on all pairs of vectors in the Cartesian product of two sets of vectors. Pairwise distance matrices are stored in condensed form; only the upper triangular is stored. `squareform` converts distance matrices between square and condensed forms.

3.44.11 Reworked fftpack package

FFTW2, FFTW3, MKL and DJBFFT wrappers have been removed. Only (NETLIB) `fftpack` remains. By focusing on one backend, we hope to add new features - like float32 support - more easily.

3.44.12 New Constants package

`scipy.constants` provides a collection of physical constants and conversion factors. These constants are taken from CODATA Recommended Values of the Fundamental Physical Constants: 2002. They may be found at physics.nist.gov/constants. The values are stored in the dictionary `physical_constants` as a tuple containing the value, the units, and the relative precision - in that order. All constants are in SI units, unless otherwise stated. Several helper functions are provided.

3.44.13 New Radial Basis Function module

`scipy.interpolate` now contains a Radial Basis Function module. Radial basis functions can be used for smoothing/interpolating scattered data in n-dimensions, but should be used with caution for extrapolation outside of the observed data range.

3.44.14 New complex ODE integrator

`scipy.integrate.ode` now contains a wrapper for the ZVODE complex-valued ordinary differential equation solver (by Peter N. Brown, Alan C. Hindmarsh, and George D. Byrne).

3.44.15 New generalized symmetric and hermitian eigenvalue problem solver

`scipy.linalg.eigh` now contains wrappers for more LAPACK symmetric and hermitian eigenvalue problem solvers. Users can now solve generalized problems, select a range of eigenvalues only, and choose to use a faster algorithm at the expense of increased memory usage. The signature of the `scipy.linalg.eigh` changed accordingly.

3.44.16 Bug fixes in the interpolation package

The shape of return values from `scipy.interpolate.interp1d` used to be incorrect, if interpolated data had more than 2 dimensions and the `axis` keyword was set to a non-default value. This has been fixed. Moreover, `interp1d` returns now a scalar (0D-array) if the input is a scalar. Users of `scipy.interpolate.interp1d` may need to revise their code if it relies on the previous behavior.

3.44.17 Weave clean up

There were numerous improvements to `scipy.weave`. `blitz++` was relicensed by the author to be compatible with the SciPy license. `wx_spec.py` was removed.

3.44.18 Known problems

Here are known problems with `scipy 0.7.0`:

- `weave` test failures on windows: those are known, and are being revised.
- `weave` test failure with `gcc 4.3 (std::labs)`: this is a `gcc 4.3` bug. A workaround is to add `#include <cstdlib>` in `scipy/weave/blitz/blitz/funcs.h` (line 27). You can make the change in the installed `scipy` (in `site-packages`).

Tutorials with worked examples and background information for most SciPy submodules.

4.1 SciPy Tutorial

4.1.1 Introduction

Contents

- *Introduction*
 - *SciPy Organization*
 - *Finding Documentation*

SciPy is a collection of mathematical algorithms and convenience functions built on the NumPy extension of Python. It adds significant power to the interactive Python session by providing the user with high-level commands and classes for manipulating and visualizing data. With SciPy, an interactive Python session becomes a data-processing and system-prototyping environment rivaling systems, such as MATLAB, IDL, Octave, R-Lab, and SciLab.

The additional benefit of basing SciPy on Python is that this also makes a powerful programming language available for use in developing sophisticated programs and specialized applications. Scientific applications using SciPy benefit from the development of additional modules in numerous niches of the software landscape by developers across the world. Everything from parallel programming to web and data-base subroutines and classes have been made available to the Python programmer. All of this power is available in addition to the mathematical libraries in SciPy.

This tutorial will acquaint the first-time user of SciPy with some of its most important features. It assumes that the user has already installed the SciPy package. Some general Python facility is also assumed, such as could be acquired by working through the Python distribution's Tutorial. For further introductory help the user is directed to the NumPy documentation.

For brevity and convenience, we will often assume that the main packages (`numpy`, `scipy`, and `matplotlib`) have been imported as:

```
>>> import numpy as np
>>> import matplotlib as mpl
>>> import matplotlib.pyplot as plt
```

These are the import conventions that our community has adopted after discussion on public mailing lists. You will see these conventions used throughout NumPy and SciPy source code and documentation. While we obviously don't require you to follow these conventions in your own code, it is highly recommended.

SciPy Organization

SciPy is organized into subpackages covering different scientific computing domains. These are summarized in the following table:

Subpackage	Description
<i>cluster</i>	Clustering algorithms
<i>constants</i>	Physical and mathematical constants
<i>fftpack</i>	Fast Fourier Transform routines
<i>integrate</i>	Integration and ordinary differential equation solvers
<i>interpolate</i>	Interpolation and smoothing splines
<i>io</i>	Input and Output
<i>linalg</i>	Linear algebra
<i>ndimage</i>	N-dimensional image processing
<i>odr</i>	Orthogonal distance regression
<i>optimize</i>	Optimization and root-finding routines
<i>signal</i>	Signal processing
<i>sparse</i>	Sparse matrices and associated routines
<i>spatial</i>	Spatial data structures and algorithms
<i>special</i>	Special functions
<i>stats</i>	Statistical distributions and functions

SciPy sub-packages need to be imported separately, for example:

```
>>> from scipy import linalg, optimize
```

Because of their ubiquitousness, some of the functions in these subpackages are also made available in the *scipy* namespace to ease their use in interactive sessions and programs. In addition, many basic array functions from *numpy* are also available at the top-level of the *scipy* package. Before looking at the sub-packages individually, we will first look at some of these common functions.

Finding Documentation

SciPy and NumPy have documentation versions in both HTML and PDF format available at <https://docs.scipy.org/>, that cover nearly all available functionality. However, this documentation is still work-in-progress and some parts may be incomplete or sparse. As we are a volunteer organization and depend on the community for growth, your participation - everything from providing feedback to improving the documentation and code - is welcome and actively encouraged.

Python's documentation strings are used in SciPy for on-line documentation. There are two methods for reading them and getting help. One is Python's command *help* in the *pydoc* module. Entering this command with no arguments (i.e. `>>> help`) launches an interactive help session that allows searching through the keywords and modules available to all of Python. Secondly, running the command *help(obj)* with an object as the argument displays that object's calling signature, and documentation string.

The *pydoc* method of *help* is sophisticated but uses a pager to display the text. Sometimes this can interfere with the terminal within which you are running the interactive session. A *numpy/scipy*-specific help system is also available under the command *numpy.info*. The signature and documentation string for the object passed to the *help* command are printed to standard output (or to a writeable object passed as the third argument). The second keyword argument of *numpy.info* defines the maximum width of the line for printing. If a module is passed as the argument to *help* then a list of the functions and classes defined in that module is printed. For example:

```
>>> np.info(optimize.fmin)
fmin(func, x0, args=(), xtol=0.0001, ftol=0.0001, maxiter=None, maxfun=None,
                                            (continues on next page)
```


(continued from previous page)

```
full_output=0, disp=1, retall=0, callback=None)
```

Minimize a function using the downhill simplex algorithm.

Parameters

```
func : callable func(x,*args)
    The objective function to be minimized.
x0 : ndarray
    Initial guess.
args : tuple
    Extra arguments passed to func, i.e. ``f(x,*args)``.
callback : callable
    Called after each iteration, as callback(xk), where xk is the
    current parameter vector.
```

Returns

```
xopt : ndarray
    Parameter that minimizes function.
fopt : float
    Value of function at minimum: ``fopt = func(xopt)``.
iter : int
    Number of iterations performed.
funcalls : int
    Number of function calls made.
warnflag : int
    1 : Maximum number of function evaluations made.
    2 : Maximum number of iterations reached.
allvecs : list
    Solution at each iteration.
```

Other parameters

```
xtol : float
    Relative error in xopt acceptable for convergence.
ftol : number
    Relative error in func(xopt) acceptable for convergence.
maxiter : int
    Maximum number of iterations to perform.
maxfun : number
    Maximum number of function evaluations to make.
full_output : bool
    Set to True if fopt and warnflag outputs are desired.
disp : bool
    Set to True to print convergence messages.
retall : bool
    Set to True to return list of solutions at each iteration.
```

Notes

Uses a Nelder-Mead simplex algorithm to find the minimum of function of

(continues on next page)

```
one or more variables.
```

Another useful command is `dir`, which can be used to look at the namespace of a module or package.

4.1.2 Special functions (`scipy.special`)

The main feature of the `scipy.special` package is the definition of numerous special functions of mathematical physics. Available functions include `airy`, `elliptic`, `bessel`, `gamma`, `beta`, `hypergeometric`, `parabolic cylinder`, `mathieu`, `spheroidal wave`, `struve`, and `kelvin`. There are also some low-level stats functions that are not intended for general use as an easier interface to these functions is provided by the `stats` module. Most of these functions can take array arguments and return array results following the same broadcasting rules as other math functions in Numerical Python. Many of these functions also accept complex numbers as input. For a complete list of the available functions with a one-line description type `>>> help(special)`. Each function also has its own documentation accessible using `help`. If you don't see a function you need, consider writing it and contributing it to the library. You can write the function in either C, Fortran, or Python. Look in the source code of the library for examples of each of these kinds of functions.

Bessel functions of real order(`jv`, `jn_zeros`)


Bessel functions are a family of solutions to Bessel's differential equation with real or complex order α :

$$x^2 \frac{d^2 y}{dx^2} + x \frac{dy}{dx} + (x^2 - \alpha^2)y = 0$$

Among other uses, these functions arise in wave propagation problems, such as the vibrational modes of a thin drum head. Here is an example of a circular drum head anchored at the edge:

```
>>> from scipy import special
>>> def drumhead_height(n, k, distance, angle, t):
...     kth_zero = special.jn_zeros(n, k)[-1]
...     return np.cos(t) * np.cos(n*angle) * special.jn(n, distance*kth_zero)
>>> theta = np.r_[0:2*np.pi:50j]
>>> radius = np.r_[0:1:50j]
>>> x = np.array([r * np.cos(theta) for r in radius])
>>> y = np.array([r * np.sin(theta) for r in radius])
>>> z = np.array([drumhead_height(1, 1, r, theta, 0.5) for r in radius])
```

```
>>> import matplotlib.pyplot as plt
>>> from mpl_toolkits.mplot3d import Axes3D
>>> from matplotlib import cm
>>> fig = plt.figure()
>>> ax = Axes3D(fig, rect=(0, 0.05, 0.95, 0.95))
>>> ax.plot_surface(x, y, z, rstride=1, cstride=1, cmap='RdBu_r', vmin=-0.5,
->vmax=0.5)
>>> ax.set_xlabel('X')
>>> ax.set_ylabel('Y')
>>> ax.set_xticks(np.arange(-1, 1.1, 0.5))
>>> ax.set_yticks(np.arange(-1, 1.1, 0.5))
>>> ax.set_zlabel('Z')
>>> plt.show()
```



Cython Bindings for Special Functions (`scipy.special.cython_special`)

SciPy also offers Cython bindings for scalar, typed versions of many of the functions in `special`. The following Cython code gives a simple example of how to use these functions:

```
cimport scipy.special.cython_special as csc

cdef:
    double x = 1
    double complex z = 1 + 1j
    double si, ci, rgam
    double complex cgam

rgam = csc.gamma(x)
print(rgam)
cgam = csc.gamma(z)
print(cgam)
csc.sici(x, &si, &ci)
print(si, ci)
```

(See the [Cython documentation](#) for help with compiling Cython.) In the example the function `csc.gamma` works essentially like its ufunc counterpart `gamma`, though it takes C types as arguments instead of NumPy arrays. Note, in particular, that the function is overloaded to support real and complex arguments; the correct variant is selected at compile time. The function `csc.sici` works slightly differently from `sici`; for the ufunc we could write `ai, bi = sici(x)`, whereas in the Cython version multiple return values are passed as pointers. It might help to think of this as analogous to calling a ufunc with an output array: `sici(x, out=(si, ci))`.

There are two potential advantages to using the Cython bindings:

- they avoid Python function overhead
- they do not require the Python Global Interpreter Lock (GIL)

The following sections discuss how to use these advantages to potentially speed up your code, though, of course, one should always profile the code first to make sure putting in the extra effort will be worth it.

Avoiding Python Function Overhead

For the ufuncs in special, Python function overhead is avoided by vectorizing, that is, by passing an array to the function. Typically, this approach works quite well, but sometimes it is more convenient to call a special function on scalar inputs inside a loop, for example, when implementing your own ufunc. In this case, the Python function overhead can become significant. Consider the following example:

```
import scipy.special as sc
cimport scipy.special.cython_special as csc

def python_tight_loop():
    cdef:
        int n
        double x = 1

    for n in range(100):
        sc.jv(n, x)

def cython_tight_loop():
    cdef:
        int n
        double x = 1

    for n in range(100):
        csc.jv(n, x)
```

On one computer `python_tight_loop` took about 131 microseconds to run and `cython_tight_loop` took about 18.2 microseconds to run. Obviously this example is contrived: one could just call `special.jv(np.arange(100), 1)` and get results just as fast as in `cython_tight_loop`. The point is that if Python function overhead becomes significant in your code, then the Cython bindings might be useful.

Releasing the GIL

One often needs to evaluate a special function at many points, and typically the evaluations are trivially parallelizable. Since the Cython bindings do not require the GIL, it is easy to run them in parallel using Cython's `prange` function. For example, suppose that we wanted to compute the fundamental solution to the Helmholtz equation:

$$\Delta_x G(x, y) + k^2 G(x, y) = \delta(x - y),$$

where k is the wavenumber and δ is the Dirac delta function. It is known that in two dimensions the unique (radiating) solution is

$$G(x, y) = \frac{i}{4} H_0^{(1)}(k|x - y|),$$

where $H_0^{(1)}$ is the Hankel function of the first kind, i.e., the function `hankell1`. The following example shows how we could compute this function in parallel:

```
from libc.math cimport fabs
cimport cython
from cython.parallel cimport prange

import numpy as np
import scipy.special as sc
cimport scipy.special.cython_special as csc
```

(continues on next page)

(continued from previous page)

```

def serial_G(k, x, y):
    return 0.25j*sc.hankel1(0, k*np.abs(x - y))

@cython.boundscheck(False)
@cython.wraparound(False)
cdef void _parallel_G(double k, double[:,:] x, double[:,:] y,
                    double complex[:,:] out) nogil:
    cdef int i, j

    for i in prange(x.shape[0]):
        for j in range(y.shape[0]):
            out[i,j] = 0.25j*csc.hankel1(0, k*fabs(x[i,j] - y[i,j]))

def parallel_G(k, x, y):
    out = np.empty_like(x, dtype='complex128')
    _parallel_G(k, x, y, out)
    return out

```

(For help with compiling parallel code in Cython see [here](#).) If the above Cython code is in a file `test.pyx`, then we can write an informal benchmark which compares the parallel and serial versions of the function:

```

import timeit

import numpy as np

from test import serial_G, parallel_G

def main():
    k = 1
    x, y = np.linspace(-100, 100, 1000), np.linspace(-100, 100, 1000)
    x, y = np.meshgrid(x, y)

    def serial():
        serial_G(k, x, y)

    def parallel():
        parallel_G(k, x, y)

    time_serial = timeit.timeit(serial, number=3)
    time_parallel = timeit.timeit(parallel, number=3)
    print("Serial method took {:.3} seconds".format(time_serial))
    print("Parallel method took {:.3} seconds".format(time_parallel))

if __name__ == "__main__":
    main()

```

On one quad-core computer the serial method took 1.29 seconds and the parallel method took 0.29 seconds.

Functions not in `scipy.special`

Some functions are not included in `special` because they are straightforward to implement with existing functions in NumPy and SciPy. To prevent reinventing the wheel, this section provides implementations of several such functions, which hopefully illustrate how to handle similar functions. In all examples NumPy is imported as `np` and `special` is imported as `sc`.

The binary entropy function:

```
def binary_entropy(x):
    return -(sc.xlogy(x, x) + sc.xlog1py(1 - x, -x))/np.log(2)
```

A rectangular step function on `[0, 1]`:

```
def step(x):
    return 0.5*(np.sign(x) + np.sign(1 - x))
```

Translating and scaling can be used to get an arbitrary step function.

The ramp function:

```
def ramp(x):
    return np.maximum(0, x)
```

4.1.3 Integration (`scipy.integrate`)

The `scipy.integrate` sub-package provides several integration techniques including an ordinary differential equation integrator. An overview of the module is provided by the help command:

```
>>> help(integrate)
Methods for Integrating Functions given function object.

quad          -- General purpose integration.
dblquad       -- General purpose double integration.
tplquad       -- General purpose triple integration.
fixed_quad    -- Integrate func(x) using Gaussian quadrature of order n.
quadrature    -- Integrate with given tolerance using Gaussian quadrature.
romberg       -- Integrate func using Romberg integration.

Methods for Integrating Functions given fixed samples.

trapezoid     -- Use trapezoidal rule to compute integral.
cumulative_trapezoid -- Use trapezoidal rule to cumulatively compute
->integral.
sims          -- Use Simpson's rule to compute integral from
->samples.
romb          -- Use Romberg Integration to compute integral from
-- (2**k + 1) evenly-spaced samples.

See the special module's orthogonal polynomials (special) for Gaussian
quadrature roots and weights for other weighting factors and regions.

Interface to numerical integrators of ODE systems.
```

(continues on next page)

(continued from previous page)

```
odeint      -- General integration of ordinary differential equations.
ode         -- Integrate ODE using VODE and ZVODE routines.
```

General integration (quad)

The function `quad` is provided to integrate a function of one variable between two points. The points can be $\pm\infty$ (`± inf`) to indicate infinite limits. For example, suppose you wish to integrate a Bessel function `jv(2.5, x)` along the interval `[0, 4.5]`.

$$I = \int_0^{4.5} J_{2.5}(x) dx.$$

This could be computed using `quad`:

```
>>> import scipy.integrate as integrate
>>> import scipy.special as special
>>> result = integrate.quad(lambda x: special.jv(2.5,x), 0, 4.5)
>>> result
(1.1178179380783249, 7.8663172481899801e-09)
```

```
>>> from numpy import sqrt, sin, cos, pi
>>> I = sqrt(2/pi)*(18.0/27*sqrt(2)*cos(4.5) - 4.0/27*sqrt(2)*sin(4.5) +
...          sqrt(2*pi) * special.fresnel(3/sqrt(pi))[0])
>>> I
1.117817938088701
```

```
>>> print(abs(result[0]-I))
1.03761443881e-11
```

The first argument to `quad` is a “callable” Python object (i.e., a function, method, or class instance). Notice the use of a `lambda`-function in this case as the argument. The next two arguments are the limits of integration. The return value is a tuple, with the first element holding the estimated value of the integral and the second element holding an upper bound on the error. Notice, that in this case, the true value of this integral is

$$I = \sqrt{\frac{2}{\pi}} \left(\frac{18}{27} \sqrt{2} \cos(4.5) - \frac{4}{27} \sqrt{2} \sin(4.5) + \sqrt{2\pi} \text{Si} \left(\frac{3}{\sqrt{\pi}} \right) \right),$$

where

$$\text{Si}(x) = \int_0^x \sin\left(\frac{\pi}{2}t^2\right) dt.$$

is the Fresnel sine integral. Note that the numerically-computed integral is within 1.04×10^{-11} of the exact result — well below the reported error bound.

If the function to integrate takes additional parameters, they can be provided in the `args` argument. Suppose that the following integral shall be calculated:

$$I(a, b) = \int_0^1 ax^2 + b dx.$$

This integral can be evaluated by using the following code:

```
>>> from scipy.integrate import quad
>>> def integrand(x, a, b):
...     return a*x**2 + b
...
>>> a = 2
>>> b = 1
>>> I = quad(integrand, 0, 1, args=(a,b))
>>> I
(1.6666666666666667, 1.8503717077085944e-14)
```

Infinite inputs are also allowed in `quad` by using $\pm \text{inf}$ as one of the arguments. For example, suppose that a numerical value for the exponential integral:

$$E_n(x) = \int_1^{\infty} \frac{e^{-xt}}{t^n} dt.$$

is desired (and the fact that this integral can be computed as `special.expn(n, x)` is forgotten). The functionality of the function `special.expn` can be replicated by defining a new function `vec_expint` based on the routine `quad`:

```
>>> from scipy.integrate import quad
>>> def integrand(t, n, x):
...     return np.exp(-x*t) / t**n
...
...

```

```
>>> def expint(n, x):
...     return quad(integrand, 1, np.inf, args=(n, x))[0]
...
...

```

```
>>> vec_expint = np.vectorize(expint)
```

```
>>> vec_expint(3, np.arange(1.0, 4.0, 0.5))
array([ 0.1097,  0.0567,  0.0301,  0.0163,  0.0089,  0.0049])
>>> import scipy.special as special
>>> special.expn(3, np.arange(1.0, 4.0, 0.5))
array([ 0.1097,  0.0567,  0.0301,  0.0163,  0.0089,  0.0049])
```

The function which is integrated can even use the `quad` argument (though the error bound may underestimate the error due to possible numerical error in the integrand from the use of `quad`). The integral in this case is

$$I_n = \int_0^{\infty} \int_1^{\infty} \frac{e^{-xt}}{t^n} dt dx = \frac{1}{n}.$$

```
>>> result = quad(lambda x: expint(3, x), 0, np.inf)
>>> print(result)
(0.33333333324560266, 2.8548934485373678e-09)
```

```
>>> I3 = 1.0/3.0
>>> print(I3)
0.333333333333
```

```
>>> print(I3 - result[0])
8.77306560731e-11
```

This last example shows that multiple integration can be handled using repeated calls to `quad`.

General multiple integration (`dblquad`, `tplquad`, `nquad`)

The mechanics for double and triple integration have been wrapped up into the functions `dblquad` and `tplquad`. These functions take the function to integrate and four, or six arguments, respectively. The limits of all inner integrals need to be defined as functions.

An example of using double integration to compute several values of I_n is shown below:

```
>>> from scipy.integrate import quad, dblquad
>>> def I(n):
...     return dblquad(lambda t, x: np.exp(-x*t)/t**n, 0, np.inf, lambda x: 1,
...                   lambda x: np.inf)
... 
```

```
>>> print(I(4))
(0.25000000000043577, 1.29830334693681e-08)
>>> print(I(3))
(0.33333333325010883, 1.3888461883425516e-08)
>>> print(I(2))
(0.4999999999985751, 1.3894083651858995e-08)
```

As example for non-constant limits consider the integral

$$I = \int_{y=0}^{1/2} \int_{x=0}^{1-2y} xy \, dx \, dy = \frac{1}{96}.$$

This integral can be evaluated using the expression below (Note the use of the non-constant lambda functions for the upper limit of the inner integral):

```
>>> from scipy.integrate import dblquad
>>> area = dblquad(lambda x, y: x*y, 0, 0.5, lambda x: 0, lambda x: 1-2*x)
>>> area
(0.010416666666666668, 1.1564823173178715e-16)
```

For n-fold integration, `scipy` provides the function `nquad`. The integration bounds are an iterable object: either a list of constant bounds, or a list of functions for the non-constant integration bounds. The order of integration (and therefore the bounds) is from the innermost integral to the outermost one.

The integral from above

$$I_n = \int_0^\infty \int_1^\infty \frac{e^{-xt}}{t^n} dt \, dx = \frac{1}{n}$$

can be calculated as

```
>>> from scipy import integrate
>>> N = 5
>>> def f(t, x):
...     return np.exp(-x*t) / t**N
...
>>> integrate.nquad(f, [[1, np.inf],[0, np.inf]])
(0.20000000000002294, 1.2239614263187945e-08)
```

Note that the order of arguments for f must match the order of the integration bounds; i.e., the inner integral with respect to t is on the interval $[1, \infty]$ and the outer integral with respect to x is on the interval $[0, \infty]$.

Non-constant integration bounds can be treated in a similar manner; the example from above

$$I = \int_{y=0}^{1/2} \int_{x=0}^{1-2y} xy \, dx \, dy = \frac{1}{96}.$$

can be evaluated by means of

```
>>> from scipy import integrate
>>> def f(x, y):
...     return x*y
...
>>> def bounds_y():
...     return [0, 0.5]
...
>>> def bounds_x(y):
...     return [0, 1-2*y]
...
>>> integrate.nquad(f, [bounds_x, bounds_y])
(0.010416666666666668, 4.101620128472366e-16)
```

which is the same result as before.

Gaussian quadrature

A few functions are also provided in order to perform simple Gaussian quadrature over a fixed interval. The first is *fixed_quad*, which performs fixed-order Gaussian quadrature. The second function is *quadrature*, which performs Gaussian quadrature of multiple orders until the difference in the integral estimate is beneath some tolerance supplied by the user. These functions both use the module `scipy.special.orthogonal`, which can calculate the roots and quadrature weights of a large variety of orthogonal polynomials (the polynomials themselves are available as special functions returning instances of the polynomial class — e.g., *special.legendre*).

Romberg Integration

Romberg's method [WPR] is another method for numerically evaluating an integral. See the help function for *romberg* for further details.

Integrating using Samples

If the samples are equally-spaced and the number of samples available is $2^k + 1$ for some integer k , then Romberg *romb* integration can be used to obtain high-precision estimates of the integral using the available samples. Romberg integration uses the trapezoid rule at step-sizes related by a power of two and then performs Richardson extrapolation on these estimates to approximate the integral with a higher degree of accuracy.

In case of arbitrary spaced samples, the two functions *trapezoid* and *simpson* are available. They are using Newton-Coates formulas of order 1 and 2 respectively to perform integration. The trapezoidal rule approximates the function as a straight line between adjacent points, while Simpson's rule approximates the function between three adjacent points as a parabola.

For an odd number of samples that are equally spaced Simpson's rule is exact if the function is a polynomial of order 3 or less. If the samples are not equally spaced, then the result is exact only if the function is a polynomial of order 2 or less.

```

>>> import numpy as np
>>> def f1(x):
...     return x**2
...
>>> def f2(x):
...     return x**3
...
>>> x = np.array([1,3,4])
>>> y1 = f1(x)
>>> from scipy.integrate import simpson
>>> I1 = simpson(y1, x)
>>> print(I1)
21.0

```

This corresponds exactly to

$$\int_1^4 x^2 dx = 21,$$

whereas integrating the second function

```

>>> y2 = f2(x)
>>> I2 = integrate.simpson(y2, x)
>>> print(I2)
61.5

```

does not correspond to

$$\int_1^4 x^3 dx = 63.75$$

because the order of the polynomial in f2 is larger than two.

Faster integration using low-level callback functions

A user desiring reduced integration times may pass a C function pointer through `scipy.LowLevelCallable` to `quad`, `dblquad`, `tplquad` or `nquad` and it will be integrated and return a result in Python. The performance increase here arises from two factors. The primary improvement is faster function evaluation, which is provided by compilation of the function itself. Additionally we have a speedup provided by the removal of function calls between C and Python in `quad`. This method may provide a speed improvements of ~2x for trivial functions such as sine but can produce a much more noticeable improvements (10x+) for more complex functions. This feature then, is geared towards a user with numerically intensive integrations willing to write a little C to reduce computation time significantly.

The approach can be used, for example, via `ctypes` in a few simple steps:

- 1.) Write an integrand function in C with the function signature `double f(int n, double *x, void *user_data)`, where `x` is an array containing the point the function `f` is evaluated at, and `user_data` to arbitrary additional data you want to provide.

```

/* testlib.c */
double f(int n, double *x, void *user_data) {
    double c = *(double *)user_data;
    return c + x[0] - x[1] * x[2]; /* corresponds to c + x - y * z */
}

```

2.) Now compile this file to a shared/dynamic library (a quick search will help with this as it is OS-dependent). The user must link any math libraries, etc., used. On linux this looks like:

```
$ gcc -shared -fPIC -o testlib.so testlib.c
```

The output library will be referred to as `testlib.so`, but it may have a different file extension. A library has now been created that can be loaded into Python with `ctypes`.

3.) Load shared library into Python using `ctypes` and set `restypes` and `argtypes` - this allows SciPy to interpret the function correctly:

```
import os, ctypes
from scipy import integrate, LowLevelCallable

lib = ctypes.CDLL(os.path.abspath('testlib.so'))
lib.f.restype = ctypes.c_double
lib.f.argtypes = (ctypes.c_int, ctypes.POINTER(ctypes.c_double), ctypes.c_
    ↪void_p)

c = ctypes.c_double(1.0)
user_data = ctypes.cast(ctypes.pointer(c), ctypes.c_void_p)

func = LowLevelCallable(lib.f, user_data)
```

The last `void *user_data` in the function is optional and can be omitted (both in the C function and `ctypes` `argtypes`) if not needed. Note that the coordinates are passed in as an array of doubles rather than a separate argument.

4.) Now integrate the library function as normally, here using `nquad`:

```
>>> integrate.nquad(func, [[0, 10], [-10, 0], [-1, 1]])
(1200.0, 1.1102230246251565e-11)
```

The Python tuple is returned as expected in a reduced amount of time. All optional parameters can be used with this method including specifying singularities, infinite bounds, etc.

Ordinary differential equations (`solve_ivp`)

Integrating a set of ordinary differential equations (ODEs) given initial conditions is another useful example. The function `solve_ivp` is available in SciPy for integrating a first-order vector differential equation:

$$\frac{dy}{dt} = \mathbf{f}(\mathbf{y}, t),$$

given initial conditions $\mathbf{y}(0) = \mathbf{y}_0$, where \mathbf{y} is a length N vector and \mathbf{f} is a mapping from \mathcal{R}^N to \mathcal{R}^N . A higher-order ordinary differential equation can always be reduced to a differential equation of this type by introducing intermediate derivatives into the \mathbf{y} vector.

For example, suppose it is desired to find the solution to the following second-order differential equation:

$$\frac{d^2w}{dz^2} - zw(z) = 0$$

with initial conditions $w(0) = \frac{1}{\sqrt[3]{3^2}\Gamma(\frac{2}{3})}$ and $\frac{dw}{dz}|_{z=0} = -\frac{1}{\sqrt[3]{3}\Gamma(\frac{1}{3})}$. It is known that the solution to this differential equation with these boundary conditions is the Airy function

$$w = \text{Ai}(z),$$

which gives a means to check the integrator using `special.airy`.

First, convert this ODE into standard form by setting $\mathbf{y} = \begin{bmatrix} \frac{dw}{dz} \\ w \end{bmatrix}$ and $t = z$. Thus, the differential equation becomes

$$\frac{d\mathbf{y}}{dt} = \begin{bmatrix} ty_1 \\ y_0 \end{bmatrix} = \begin{bmatrix} 0 & t \\ 1 & 0 \end{bmatrix} \begin{bmatrix} y_0 \\ y_1 \end{bmatrix} = \begin{bmatrix} 0 & t \\ 1 & 0 \end{bmatrix} \mathbf{y}.$$

In other words,

$$\mathbf{f}(\mathbf{y}, t) = \mathbf{A}(t) \mathbf{y}.$$

As an interesting reminder, if $\mathbf{A}(t)$ commutes with $\int_0^t \mathbf{A}(\tau) d\tau$ under matrix multiplication, then this linear differential equation has an exact solution using the matrix exponential:

$$\mathbf{y}(t) = \exp\left(\int_0^t \mathbf{A}(\tau) d\tau\right) \mathbf{y}(0),$$

However, in this case, $\mathbf{A}(t)$ and its integral do not commute.

This differential equation can be solved using the function `solve_ivp`. It requires the derivative, `fprime`, the time span `[t_start, t_end]` and the initial conditions vector, `y0`, as input arguments and returns an object whose `y` field is an array with consecutive solution values as columns. The initial conditions are therefore given in the first output column.

```
>>> from scipy.integrate import solve_ivp
>>> from scipy.special import gamma, airy
>>> y1_0 = +1 / 3**(2/3) / gamma(2/3)
>>> y0_0 = -1 / 3**(1/3) / gamma(1/3)
>>> y0 = [y0_0, y1_0]
>>> def func(t, y):
...     return [t*y[1], y[0]]
...
>>> t_span = [0, 4]
>>> sol1 = solve_ivp(func, t_span, y0)
>>> print("sol1.t: {}".format(sol1.t))
sol1.t: [0.          0.10097672  1.04643602  1.91060117  2.49872472  3.08684827
 3.62692846  4.          ]
```

As it can be seen `solve_ivp` determines its time steps automatically if not specified otherwise. To compare the solution of `solve_ivp` with the `airy` function the time vector created by `solve_ivp` is passed to the `airy` function.

```
>>> print("sol1.y[1]: {}".format(sol1.y[1]))
sol1.y[1]: [0.35502805  0.328952    0.12801343  0.04008508  0.01601291  0.00623879
 0.00356316  0.00405982]
>>> print("airy(sol.t)[0]: {}".format(airy(sol.t)[0]))
airy(sol.t)[0]: [0.35502805  0.328952    0.12804768  0.03995804  0.01575943  0.
↪00562799
 0.00201689  0.00095156]
```

The solution of `solve_ivp` with its standard parameters shows a big deviation to the `airy` function. To minimize this deviation, relative and absolute tolerances can be used.

```
>>> rtol, atol = (1e-8, 1e-8)
>>> sol2 = solve_ivp(func, t_span, y0, rtol=rtol, atol=atol)
>>> print("sol2.y[1][::6]: {}".format(sol2.y[1][::6]))
sol2.y[1][::6]: [0.35502805  0.19145234  0.06368989  0.0205917   0.00554734  0.
↪00106409]
```

(continues on next page)

(continued from previous page)

```
>>> print("airy(sol2.t)[0][::6]: {}".format(airy(sol2.t)[0][::6]))
airy(sol2.t)[0][::6]: [0.35502805 0.19145234 0.06368989 0.0205917 0.00554733_
↪0.00106406]
```

To specify user defined time points for the solution of `solve_ivp`, `solve_ivp` offers two possibilities that can also be used complementarily. By passing the `t_eval` option to the function call `solve_ivp` returns the solutions of these time points of `t_eval` in its output.

```
>>> import numpy as np
>>> t = np.linspace(0, 4, 100)
>>> sol3 = solve_ivp(func, t_span, y0, t_eval=t)
```

If the jacobian matrix of function is known, it can be passed to the `solve_ivp` to achieve better results. Please be aware however that the default integration method `RK45` does not support jacobian matrices and thereby another integration method has to be chosen. One of the integration methods that support a jacobian matrix is the for example the `Radau` method of following example.

```
>>> def gradient(t, y):
...     return [[0,t], [1,0]]
>>> sol4 = solve_ivp(func, t_span, y0, method='Radau', jac=gradient)
```

Solving a system with a banded Jacobian matrix

`odeint` can be told that the Jacobian is *banded*. For a large system of differential equations that are known to be stiff, this can improve performance significantly.

As an example, we'll solve the 1-D Gray-Scott partial differential equations using the method of lines [MOL]. The Gray-Scott equations for the functions $u(x, t)$ and $v(x, t)$ on the interval $x \in [0, L]$ are

$$\begin{aligned}\frac{\partial u}{\partial t} &= D_u \frac{\partial^2 u}{\partial x^2} - uv^2 + f(1 - u) \\ \frac{\partial v}{\partial t} &= D_v \frac{\partial^2 v}{\partial x^2} + uv^2 - (f + k)v\end{aligned}$$

where D_u and D_v are the diffusion coefficients of the components u and v , respectively, and f and k are constants. (For more information about the system, see <http://groups.csail.mit.edu/mac/projects/amorphous/GrayScott/>)

We'll assume Neumann (i.e., “no flux”) boundary conditions:

$$\frac{\partial u}{\partial x}(0, t) = 0, \quad \frac{\partial v}{\partial x}(0, t) = 0, \quad \frac{\partial u}{\partial x}(L, t) = 0, \quad \frac{\partial v}{\partial x}(L, t) = 0$$

To apply the method of lines, we discretize the x variable by defining the uniformly spaced grid of N points $\{x_0, x_1, \dots, x_{N-1}\}$, with $x_0 = 0$ and $x_{N-1} = L$. We define $u_j(t) \equiv u(x_k, t)$ and $v_j(t) \equiv v(x_k, t)$, and replace the x derivatives with finite differences. That is,

$$\frac{\partial^2 u}{\partial x^2}(x_j, t) \rightarrow \frac{u_{j-1}(t) - 2u_j(t) + u_{j+1}(t)}{(\Delta x)^2}$$

We then have a system of $2N$ ordinary differential equations:

$$\begin{aligned}\frac{du_j}{dt} &= \frac{D_u}{(\Delta x)^2} (u_{j-1} - 2u_j + u_{j+1}) - u_j v_j^2 + f(1 - u_j) \\ \frac{dv_j}{dt} &= \frac{D_v}{(\Delta x)^2} (v_{j-1} - 2v_j + v_{j+1}) + u_j v_j^2 - (f + k)v_j\end{aligned}\tag{4.1}$$

For convenience, the (t) arguments have been dropped.

To enforce the boundary conditions, we introduce “ghost” points x_{-1} and x_N , and define $u_{-1}(t) \equiv u_1(t)$, $u_N(t) \equiv u_{N-2}(t)$; $v_{-1}(t)$ and $v_N(t)$ are defined analogously.

Then

$$\begin{aligned} \frac{du_0}{dt} &= \frac{D_u}{(\Delta x)^2} (2u_1 - 2u_0) - u_0 v_0^2 + f(1 - u_0) \\ \frac{dv_0}{dt} &= \frac{D_v}{(\Delta x)^2} (2v_1 - 2v_0) + u_0 v_0^2 - (f + k)v_0 \end{aligned} \tag{4.2}$$

and

$$\begin{aligned} \frac{du_{N-1}}{dt} &= \frac{D_u}{(\Delta x)^2} (2u_{N-2} - 2u_{N-1}) - u_{N-1} v_{N-1}^2 + f(1 - u_{N-1}) \\ \frac{dv_{N-1}}{dt} &= \frac{D_v}{(\Delta x)^2} (2v_{N-2} - 2v_{N-1}) + u_{N-1} v_{N-1}^2 - (f + k)v_{N-1} \end{aligned} \tag{4.3}$$

Our complete system of $2N$ ordinary differential equations is (4.1) for $k = 1, 2, \dots, N - 2$, along with (4.2) and (4.3).

We can now start implementing this system in code. We must combine $\{u_k\}$ and $\{v_k\}$ into a single vector of length $2N$. The two obvious choices are $\{u_0, u_1, \dots, u_{N-1}, v_0, v_1, \dots, v_{N-1}\}$ and $\{u_0, v_0, u_1, v_1, \dots, u_{N-1}, v_{N-1}\}$. Mathematically, it does not matter, but the choice affects how efficiently `odeint` can solve the system. The reason is in how the order affects the pattern of the nonzero elements of the Jacobian matrix.

When the variables are ordered as $\{u_0, u_1, \dots, u_{N-1}, v_0, v_1, \dots, v_{N-1}\}$, the pattern of nonzero elements of the Jacobian matrix is

```

* * 0 0 0 0 0 * 0 0 0 0 0 0
* * * 0 0 0 0 0 * 0 0 0 0 0
0 * * * 0 0 0 0 0 * 0 0 0 0
0 0 * * * 0 0 0 0 0 * 0 0 0
0 0 0 * * * 0 0 0 0 0 * 0 0
0 0 0 0 * * * 0 0 0 0 0 * 0
* 0 0 0 0 0 * * * 0 0 0 0 0
0 * 0 0 0 0 0 * * * 0 0 0 0
0 0 * 0 0 0 0 0 * * * 0 0 0
0 0 0 * 0 0 0 0 0 * * * 0
0 0 0 0 * 0 0 0 0 0 * * * 0
0 0 0 0 0 * 0 0 0 0 0 * * *
0 0 0 0 0 0 * 0 0 0 0 0 * *

```

The Jacobian pattern with variables interleaved as $\{u_0, v_0, u_1, v_1, \dots, u_{N-1}, v_{N-1}\}$ is

```

* * * 0 0 0 0 0 0 0 0 0 0 0
* * 0 * 0 0 0 0 0 0 0 0 0
* 0 * * * 0 0 0 0 0 0 0 0
0 * * * 0 * 0 0 0 0 0 0 0
0 0 * 0 * * * 0 0 0 0 0 0
0 0 0 * * * 0 * 0 0 0 0 0
0 0 0 0 * 0 * * * 0 0 0 0
0 0 0 0 0 * * * 0 * 0 0 0
0 0 0 0 0 0 * * * 0 * 0 0
0 0 0 0 0 0 0 * * * 0 * 0
0 0 0 0 0 0 0 0 * * * 0 *
0 0 0 0 0 0 0 0 0 * * * 0
0 0 0 0 0 0 0 0 0 0 * * *

```

In both cases, there are just five nontrivial diagonals, but when the variables are interleaved, the bandwidth is much smaller. That is, the main diagonal and the two diagonals immediately above and the two immediately below the main diagonal are the nonzero diagonals. This is important, because the inputs `mu` and `m1` of `odeint` are the upper and lower bandwidths of the Jacobian matrix. When the variables are interleaved, `mu` and `m1` are 2. When the variables are stacked with $\{v_k\}$ following $\{u_k\}$, the upper and lower bandwidths are N .

With that decision made, we can write the function that implements the system of differential equations.

First, we define the functions for the source and reaction terms of the system:

```

def G(u, v, f, k):
    return f * (1 - u) - u*v**2

def H(u, v, f, k):
    return -(f + k) * v + u*v**2

```

Next, we define the function that computes the right-hand side of the system of differential equations:

```
def graycott1d(y, t, f, k, Du, Dv, dx):
    """
    Differential equations for the 1-D Gray-Scott equations.

    The ODEs are derived using the method of lines.
    """
    # The vectors u and v are interleaved in y. We define
    # views of u and v by slicing y.
    u = y[::2]
    v = y[1::2]

    # dydt is the return value of this function.
    dydt = np.empty_like(y)

    # Just like u and v are views of the interleaved vectors
    # in y, dudt and dvdt are views of the interleaved output
    # vectors in dydt.
    dudt = dydt[::2]
    dvdt = dydt[1::2]

    # Compute du/dt and dv/dt. The end points and the interior points
    # are handled separately.
    dudt[0] = G(u[0], v[0], f, k) + Du * (-2.0*u[0] + 2.0*u[1]) /_
    ↪dx**2
    dudt[1:-1] = G(u[1:-1], v[1:-1], f, k) + Du * np.diff(u,2) / dx**2
    dudt[-1] = G(u[-1], v[-1], f, k) + Du * (- 2.0*u[-1] + 2.0*u[-2]) /_
    ↪dx**2
    dvdt[0] = H(u[0], v[0], f, k) + Dv * (-2.0*v[0] + 2.0*v[1]) /_
    ↪dx**2
    dvdt[1:-1] = H(u[1:-1], v[1:-1], f, k) + Dv * np.diff(v,2) / dx**2
    dvdt[-1] = H(u[-1], v[-1], f, k) + Dv * (-2.0*v[-1] + 2.0*v[-2]) /_
    ↪dx**2

    return dydt
```

We won't implement a function to compute the Jacobian, but we will tell `odeint` that the Jacobian matrix is banded. This allows the underlying solver (LSODA) to avoid computing values that it knows are zero. For a large system, this improves the performance significantly, as demonstrated in the following ipython session.

First, we define the required inputs:

```
In [31]: y0 = np.random.randn(5000)

In [32]: t = np.linspace(0, 50, 11)

In [33]: f = 0.024

In [34]: k = 0.055

In [35]: Du = 0.01

In [36]: Dv = 0.005
```

(continues on next page)

(continued from previous page)

```
In [37]: dx = 0.025
```

Time the computation without taking advantage of the banded structure of the Jacobian matrix:

```
In [38]: %timeit sola = odeint(grayscott1d, y0, t, args=(f, k, Du, Dv, dx))
1 loop, best of 3: 25.2 s per loop
```

Now set `ml=2` and `mu=2`, so `odeint` knows that the Jacobian matrix is banded:

```
In [39]: %timeit solb = odeint(grayscott1d, y0, t, args=(f, k, Du, Dv, dx),
↳ ml=2, mu=2)
10 loops, best of 3: 191 ms per loop
```

That is quite a bit faster!

Let's ensure that they have computed the same result:

```
In [41]: np.allclose(sola, solb)
Out[41]: True
```

References

4.1.4 Optimization (`scipy.optimize`)

Contents

- *Optimization* (`scipy.optimize`)
 - *Unconstrained minimization of multivariate scalar functions* (`minimize`)
 - * *Nelder-Mead Simplex algorithm* (`method='Nelder-Mead'`)
 - * *Broyden-Fletcher-Goldfarb-Shanno algorithm* (`method='BFGS'`)
 - * *Newton-Conjugate-Gradient algorithm* (`method='Newton-CG'`)
 - *Full Hessian example:*
 - *Hessian product example:*
 - * *Trust-Region Newton-Conjugate-Gradient Algorithm* (`method='trust-ncg'`)
 - *Full Hessian example:*
 - *Hessian product example:*
 - * *Trust-Region Truncated Generalized Lanczos / Conjugate Gradient Algorithm* (`method='trust-krylov'`)
 - *Full Hessian example:*
 - *Hessian product example:*
 - * *Trust-Region Nearly Exact Algorithm* (`method='trust-exact'`)
 - *Constrained minimization of multivariate scalar functions* (`minimize`)
 - * *Trust-Region Constrained Algorithm* (`method='trust-constr'`)

- *Defining Bounds Constraints:*
- *Defining Linear Constraints:*
- *Defining Nonlinear Constraints:*
- *Solving the Optimization Problem:*
 - * *Sequential Least Squares Programming (SLSQP) Algorithm (method='SLSQP')*
- *Global optimization*
- *Least-squares minimization (least_squares)*
 - * *Example of solving a fitting problem*
 - * *Further examples*
- *Univariate function minimizers (minimize_scalar)*
 - * *Unconstrained minimization (method='brent')*
 - * *Bounded minimization (method='bounded')*
- *Custom minimizers*
- *Root finding*
 - * *Scalar functions*
 - * *Fixed-point solving*
 - * *Sets of equations*
 - * *Root finding for large problems*
 - * *Still too slow? Preconditioning.*
- *Linear programming (linprog)*
 - * *Linear programming example*

The `scipy.optimize` package provides several commonly used optimization algorithms. A detailed listing is available: `scipy.optimize` (can also be found by `help(scipy.optimize)`).

Unconstrained minimization of multivariate scalar functions (`minimize`)

The `minimize` function provides a common interface to unconstrained and constrained minimization algorithms for multivariate scalar functions in `scipy.optimize`. To demonstrate the minimization function, consider the problem of minimizing the Rosenbrock function of N variables:

$$f(\mathbf{x}) = \sum_{i=1}^{N-1} 100 (x_{i+1} - x_i^2)^2 + (1 - x_i)^2.$$

The minimum value of this function is 0 which is achieved when $x_i = 1$.

Note that the Rosenbrock function and its derivatives are included in `scipy.optimize`. The implementations shown in the following sections provide examples of how to define an objective function as well as its jacobian and hessian functions.

Nelder-Mead Simplex algorithm (method='Nelder-Mead')

In the example below, the `minimize` routine is used with the *Nelder-Mead* simplex algorithm (selected through the `method` parameter):

```
>>> import numpy as np
>>> from scipy.optimize import minimize
```

```
>>> def rosen(x):
...     """The Rosenbrock function"""
...     return sum(100.0*(x[1:]-x[:-1])**2.0)**2.0 + (1-x[:-1])**2.0
```

```
>>> x0 = np.array([1.3, 0.7, 0.8, 1.9, 1.2])
>>> res = minimize(rosen, x0, method='nelder-mead',
...               options={'xatol': 1e-8, 'disp': True})
Optimization terminated successfully.
    Current function value: 0.000000
    Iterations: 339
    Function evaluations: 571
```

```
>>> print(res.x)
[1. 1. 1. 1. 1.]
```

The simplex algorithm is probably the simplest way to minimize a fairly well-behaved function. It requires only function evaluations and is a good choice for simple minimization problems. However, because it does not use any gradient evaluations, it may take longer to find the minimum.

Another optimization algorithm that needs only function calls to find the minimum is *Powell's* method available by setting `method='powell'` in `minimize`.

Broyden-Fletcher-Goldfarb-Shanno algorithm (method='BFGS')

In order to converge more quickly to the solution, this routine uses the gradient of the objective function. If the gradient is not given by the user, then it is estimated using first-differences. The Broyden-Fletcher-Goldfarb-Shanno (BFGS) method typically requires fewer function calls than the simplex algorithm even when the gradient must be estimated.

To demonstrate this algorithm, the Rosenbrock function is again used. The gradient of the Rosenbrock function is the vector:

$$\begin{aligned}\frac{\partial f}{\partial x_j} &= \sum_{i=1}^N 200 (x_i - x_{i-1}^2) (\delta_{i,j} - 2x_{i-1}\delta_{i-1,j}) - 2(1 - x_{i-1})\delta_{i-1,j} \\ &= 200(x_j - x_{j-1}^2) - 400x_j(x_{j+1} - x_j^2) - 2(1 - x_j).\end{aligned}$$

This expression is valid for the interior derivatives. Special cases are

$$\begin{aligned}\frac{\partial f}{\partial x_0} &= -400x_0(x_1 - x_0^2) - 2(1 - x_0), \\ \frac{\partial f}{\partial x_{N-1}} &= 200(x_{N-1} - x_{N-2}^2).\end{aligned}$$

A Python function which computes this gradient is constructed by the code-segment:

```
>>> def rosen_der(x):
...     xm = x[1:-1]
...     xm_m1 = x[:-2]
```

(continues on next page)

(continued from previous page)

```

...     xm_p1 = x[2:]
...     der = np.zeros_like(x)
...     der[1:-1] = 200*(xm-xm_m1**2) - 400*(xm_p1 - xm**2)*xm - 2*(1-xm)
...     der[0] = -400*x[0]*(x[1]-x[0]**2) - 2*(1-x[0])
...     der[-1] = 200*(x[-1]-x[-2]**2)
...     return der

```

This gradient information is specified in the `minimize` function through the `jac` parameter as illustrated below.

```

>>> res = minimize(rosen, x0, method='BFGS', jac=rosen_der,
...                 options={'disp': True})
Optimization terminated successfully.
      Current function value: 0.000000
      Iterations: 51                # may vary
      Function evaluations: 63
      Gradient evaluations: 63
>>> res.x
array([1., 1., 1., 1., 1.])

```

Newton-Conjugate-Gradient algorithm (`method='Newton-CG'`)

Newton-Conjugate Gradient algorithm is a modified Newton's method and uses a conjugate gradient algorithm to (approximately) invert the local Hessian [NW]. Newton's method is based on fitting the function locally to a quadratic form:

$$f(\mathbf{x}) \approx f(\mathbf{x}_0) + \nabla f(\mathbf{x}_0) \cdot (\mathbf{x} - \mathbf{x}_0) + \frac{1}{2} (\mathbf{x} - \mathbf{x}_0)^T \mathbf{H}(\mathbf{x}_0) (\mathbf{x} - \mathbf{x}_0).$$

where $\mathbf{H}(\mathbf{x}_0)$ is a matrix of second-derivatives (the Hessian). If the Hessian is positive definite then the local minimum of this function can be found by setting the gradient of the quadratic form to zero, resulting in

$$\mathbf{x}_{\text{opt}} = \mathbf{x}_0 - \mathbf{H}^{-1} \nabla f.$$

The inverse of the Hessian is evaluated using the conjugate-gradient method. An example of employing this method to minimizing the Rosenbrock function is given below. To take full advantage of the Newton-CG method, a function which computes the Hessian must be provided. The Hessian matrix itself does not need to be constructed, only a vector which is the product of the Hessian with an arbitrary vector needs to be available to the minimization routine. As a result, the user can provide either a function to compute the Hessian matrix, or a function to compute the product of the Hessian with an arbitrary vector.

Full Hessian example:

The Hessian of the Rosenbrock function is

$$\begin{aligned}
 H_{ij} = \frac{\partial^2 f}{\partial x_i \partial x_j} &= 200(\delta_{i,j} - 2x_{i-1}\delta_{i-1,j}) - 400x_i(\delta_{i+1,j} - 2x_i\delta_{i,j}) - 400\delta_{i,j}(x_{i+1} - x_i^2) + 2\delta_{i,j}, \\
 &= (202 + 1200x_i^2 - 400x_{i+1})\delta_{i,j} - 400x_i\delta_{i+1,j} - 400x_{i-1}\delta_{i-1,j},
 \end{aligned}$$

if $i, j \in [1, N - 2]$ with $i, j \in [0, N - 1]$ defining the $N \times N$ matrix. Other non-zero entries of the matrix are

$$\begin{aligned}\frac{\partial^2 f}{\partial x_0^2} &= 1200x_0^2 - 400x_1 + 2, \\ \frac{\partial^2 f}{\partial x_0 \partial x_1} &= \frac{\partial^2 f}{\partial x_1 \partial x_0} = -400x_0, \\ \frac{\partial^2 f}{\partial x_{N-1} \partial x_{N-2}} &= \frac{\partial^2 f}{\partial x_{N-2} \partial x_{N-1}} = -400x_{N-2}, \\ \frac{\partial^2 f}{\partial x_{N-1}^2} &= 200.\end{aligned}$$

For example, the Hessian when $N = 5$ is

$$\mathbf{H} = \begin{bmatrix} 1200x_0^2 - 400x_1 + 2 & -400x_0 & 0 & 0 & 0 \\ -400x_0 & 202 + 1200x_1^2 - 400x_2 & -400x_1 & 0 & 0 \\ 0 & -400x_1 & 202 + 1200x_2^2 - 400x_3 & -400x_2 & 0 \\ 0 & 0 & -400x_2 & 202 + 1200x_3^2 - 400x_4 & -400x_3 \\ 0 & 0 & 0 & -400x_3 & 200 \end{bmatrix}.$$

The code which computes this Hessian along with the code to minimize the function using Newton-CG method is shown in the following example:

```
>>> def rosen_hess(x):
...     x = np.asarray(x)
...     H = np.diag(-400*x[:-1], 1) - np.diag(400*x[:-1], -1)
...     diagonal = np.zeros_like(x)
...     diagonal[0] = 1200*x[0]**2 - 400*x[1] + 2
...     diagonal[-1] = 200
...     diagonal[1:-1] = 202 + 1200*x[1:-1]**2 - 400*x[2:]
...     H = H + np.diag(diagonal)
...     return H
```

```
>>> res = minimize(rosen, x0, method='Newton-CG',
...                 jac=rosen_der, hess=rosen_hess,
...                 options={'xtol': 1e-8, 'disp': True})
Optimization terminated successfully.
    Current function value: 0.000000
    Iterations: 19 # may vary
    Function evaluations: 22
    Gradient evaluations: 19
    Hessian evaluations: 19
>>> res.x
array([1., 1., 1., 1., 1.]
```

Hessian product example:

For larger minimization problems, storing the entire Hessian matrix can consume considerable time and memory. The Newton-CG algorithm only needs the product of the Hessian times an arbitrary vector. As a result, the user can supply code to compute this product rather than the full Hessian by giving a `hess` function which take the minimization vector as the first argument and the arbitrary vector as the second argument (along with extra arguments passed to the function to be minimized). If possible, using Newton-CG with the Hessian product option is probably the fastest way to minimize the function.

In this case, the product of the Rosenbrock Hessian with an arbitrary vector is not difficult to compute. If \mathbf{p} is the arbitrary vector, then $\mathbf{H}(\mathbf{x}) \mathbf{p}$ has elements:

$$\mathbf{H}(\mathbf{x}) \mathbf{p} = \begin{bmatrix} (1200x_0^2 - 400x_1 + 2) p_0 - 400x_0 p_1 \\ \vdots \\ -400x_{i-1} p_{i-1} + (202 + 1200x_i^2 - 400x_{i+1}) p_i - 400x_i p_{i+1} \\ \vdots \\ -400x_{N-2} p_{N-2} + 200p_{N-1} \end{bmatrix}.$$

Code which makes use of this Hessian product to minimize the Rosenbrock function using `minimize` follows:

```
>>> def rosen_hess_p(x, p):
...     x = np.asarray(x)
...     Hp = np.zeros_like(x)
...     Hp[0] = (1200*x[0]**2 - 400*x[1] + 2)*p[0] - 400*x[0]*p[1]
...     Hp[1:-1] = -400*x[:-2]*p[:-2] + (202+1200*x[1:-1]**2-400*x[2:]) *p[1:-1]
...     Hp[-1] = -400*x[1:-1]*p[2:]
...     Hp[-1] = -400*x[-2]*p[-2] + 200*p[-1]
...     return Hp
```

```
>>> res = minimize(rosen, x0, method='Newton-CG',
...               jac=rosen_der, hessp=rosen_hess_p,
...               options={'xtol': 1e-8, 'disp': True})
Optimization terminated successfully.
    Current function value: 0.000000
    Iterations: 20 # may vary
    Function evaluations: 23
    Gradient evaluations: 20
    Hessian evaluations: 44
>>> res.x
array([1., 1., 1., 1., 1.]
```

According to [NW] p. 170 the `Newton-CG` algorithm can be inefficient when the Hessian is ill-conditioned because of the poor quality search directions provided by the method in those situations. The method `trust-ncg`, according to the authors, deals more effectively with this problematic situation and will be described next.

Trust-Region Newton-Conjugate-Gradient Algorithm (`method='trust-ncg'`)

The `Newton-CG` method is a line search method: it finds a direction of search minimizing a quadratic approximation of the function and then uses a line search algorithm to find the (nearly) optimal step size in that direction. An alternative approach is to, first, fix the step size limit Δ and then find the optimal step \mathbf{p} inside the given trust-radius by solving the following quadratic subproblem:

$$\min_{\mathbf{p}} f(\mathbf{x}_k) + \nabla f(\mathbf{x}_k) \cdot \mathbf{p} + \frac{1}{2} \mathbf{p}^T \mathbf{H}(\mathbf{x}_k) \mathbf{p};$$

subject to: $\|\mathbf{p}\| \leq \Delta$.

The solution is then updated $\mathbf{x}_{k+1} = \mathbf{x}_k + \mathbf{p}$ and the trust-radius Δ is adjusted according to the degree of agreement of the quadratic model with the real function. This family of methods is known as trust-region methods. The `trust-ncg` algorithm is a trust-region method that uses a conjugate gradient algorithm to solve the trust-region subproblem [NW].

Full Hessian example:

```
>>> res = minimize(rosen, x0, method='trust-ncg',
...               jac=rosen_der, hess=rosen_hess,
...               options={'gtol': 1e-8, 'disp': True})
Optimization terminated successfully.
    Current function value: 0.000000
    Iterations: 20          # may vary
    Function evaluations: 21
    Gradient evaluations: 20
    Hessian evaluations: 19
>>> res.x
array([1., 1., 1., 1., 1.]
```

Hessian product example:

```
>>> res = minimize(rosen, x0, method='trust-ncg',
...               jac=rosen_der, hessp=rosen_hess_p,
...               options={'gtol': 1e-8, 'disp': True})
Optimization terminated successfully.
    Current function value: 0.000000
    Iterations: 20          # may vary
    Function evaluations: 21
    Gradient evaluations: 20
    Hessian evaluations: 0
>>> res.x
array([1., 1., 1., 1., 1.]
```

Trust-Region Truncated Generalized Lanczos / Conjugate Gradient Algorithm (method='trust-krylov')

Similar to the `trust-ncg` method, the `trust-krylov` method is a method suitable for large-scale problems as it uses the hessian only as linear operator by means of matrix-vector products. It solves the quadratic subproblem more accurately than the `trust-ncg` method.

$$\min_{\mathbf{p}} f(\mathbf{x}_k) + \nabla f(\mathbf{x}_k) \cdot \mathbf{p} + \frac{1}{2} \mathbf{p}^T \mathbf{H}(\mathbf{x}_k) \mathbf{p};$$

subject to: $\|\mathbf{p}\| \leq \Delta$.

This method wraps the [TRLIB] implementation of the [GLTR] method solving exactly a trust-region subproblem restricted to a truncated Krylov subspace. For indefinite problems it is usually better to use this method as it reduces the number of nonlinear iterations at the expense of few more matrix-vector products per subproblem solve in comparison to the `trust-ncg` method.

Full Hessian example:

```
>>> res = minimize(rosen, x0, method='trust-krylov',
...               jac=rosen_der, hess=rosen_hess,
...               options={'gtol': 1e-8, 'disp': True})
Optimization terminated successfully.
    Current function value: 0.000000
    Iterations: 19          # may vary
    Function evaluations: 20
    Gradient evaluations: 20
    Hessian evaluations: 18
>>> res.x
array([1., 1., 1., 1., 1.]
```

Hessian product example:

```
>>> res = minimize(rosen, x0, method='trust-krylov',
...               jac=rosen_der, hessp=rosen_hess_p,
...               options={'gtol': 1e-8, 'disp': True})
Optimization terminated successfully.
    Current function value: 0.000000
    Iterations: 19          # may vary
    Function evaluations: 20
    Gradient evaluations: 20
    Hessian evaluations: 0
>>> res.x
array([1., 1., 1., 1., 1.]
```

Trust-Region Nearly Exact Algorithm (method='trust-exact')

All methods `Newton-CG`, `trust-ncg` and `trust-krylov` are suitable for dealing with large-scale problems (problems with thousands of variables). That is because the conjugate gradient algorithm approximately solve the trust-region subproblem (or invert the Hessian) by iterations without the explicit Hessian factorization. Since only the product of the Hessian with an arbitrary vector is needed, the algorithm is specially suited for dealing with sparse Hessians, allowing low storage requirements and significant time savings for those sparse problems.

For medium-size problems, for which the storage and factorization cost of the Hessian are not critical, it is possible to obtain a solution within fewer iteration by solving the trust-region subproblems almost exactly. To achieve that, a certain nonlinear equations is solved iteratively for each quadratic subproblem [CGT]. This solution requires usually 3 or 4 Cholesky factorizations of the Hessian matrix. As the result, the method converges in fewer number of iterations and takes fewer evaluations of the objective function than the other implemented trust-region methods. The Hessian product option is not supported by this algorithm. An example using the Rosenbrock function follows:

```
>>> res = minimize(rosen, x0, method='trust-exact',
...               jac=rosen_der, hess=rosen_hess,
...               options={'gtol': 1e-8, 'disp': True})
Optimization terminated successfully.
    Current function value: 0.000000
    Iterations: 13          # may vary
    Function evaluations: 14
    Gradient evaluations: 13
    Hessian evaluations: 14
```

(continues on next page)

(continued from previous page)

```
>>> res.x
array([1., 1., 1., 1., 1.])
```

Constrained minimization of multivariate scalar functions (`minimize`)

The `minimize` function provides algorithms for constrained minimization, namely `'trust-constr'`, `'SLSQP'` and `'COBYLA'`. They require the constraints to be defined using slightly different structures. The method `'trust-constr'` requires the constraints to be defined as a sequence of objects `LinearConstraint` and `NonlinearConstraint`. Methods `'SLSQP'` and `'COBYLA'`, on the other hand, require constraints to be defined as a sequence of dictionaries, with keys `type`, `fun` and `jac`.

As an example let us consider the constrained minimization of the Rosenbrock function:

$$\begin{aligned} \min_{x_0, x_1} \quad & 100(x_1 - x_0^2)^2 + (1 - x_0)^2 \\ \text{subject to:} \quad & x_0 + 2x_1 \leq 1 \\ & x_0^2 + x_1 \leq 1 \\ & x_0^2 - x_1 \leq 1 \\ & 2x_0 + x_1 = 1 \\ & 0 \leq x_0 \leq 1 \\ & -0.5 \leq x_1 \leq 2.0. \end{aligned}$$

This optimization problem has the unique solution $[x_0, x_1] = [0.4149, 0.1701]$, for which only the first and fourth constraints are active.

Trust-Region Constrained Algorithm (`method='trust-constr'`)

The trust-region constrained method deals with constrained minimization problems of the form:

$$\begin{aligned} \min_x \quad & f(x) \\ \text{subject to:} \quad & c^l \leq c(x) \leq c^u, \\ & x^l \leq x \leq x^u. \end{aligned}$$

When $c_j^l = c_j^u$ the method reads the j -th constraint as an equality constraint and deals with it accordingly. Besides that, one-sided constraint can be specified by setting the upper or lower bound to `np.inf` with the appropriate sign.

The implementation is based on [EQSQP] for equality-constraint problems and on [TRIP] for problems with inequality constraints. Both are trust-region type algorithms suitable for large-scale problems.

Defining Bounds Constraints:

The bound constraints $0 \leq x_0 \leq 1$ and $-0.5 \leq x_1 \leq 2.0$ are defined using a `Bounds` object.

```
>>> from scipy.optimize import Bounds
>>> bounds = Bounds([0, -0.5], [1.0, 2.0])
```

Defining Linear Constraints:

The constraints $x_0 + 2x_1 \leq 1$ and $2x_0 + x_1 = 1$ can be written in the linear constraint standard format:

$$\begin{bmatrix} -\infty \\ 1 \end{bmatrix} \leq \begin{bmatrix} 1 & 2 \\ 2 & 1 \end{bmatrix} \begin{bmatrix} x_0 \\ x_1 \end{bmatrix} \leq \begin{bmatrix} 1 \\ 1 \end{bmatrix},$$

and defined using a *LinearConstraint* object.

```
>>> from scipy.optimize import LinearConstraint
>>> linear_constraint = LinearConstraint([[1, 2], [2, 1]], [-np.inf, 1], [1, 1])
```

Defining Nonlinear Constraints:

The nonlinear constraint:

$$c(x) = \begin{bmatrix} x_0^2 + x_1 \\ x_0^2 - x_1 \end{bmatrix} \leq \begin{bmatrix} 1 \\ 1 \end{bmatrix},$$

with Jacobian matrix:

$$J(x) = \begin{bmatrix} 2x_0 & 1 \\ 2x_0 & -1 \end{bmatrix},$$

and linear combination of the Hessians:

$$H(x, v) = \sum_{i=0}^1 v_i \nabla^2 c_i(x) = v_0 \begin{bmatrix} 2 & 0 \\ 0 & 0 \end{bmatrix} + v_1 \begin{bmatrix} 2 & 0 \\ 0 & 0 \end{bmatrix},$$

is defined using a *NonlinearConstraint* object.

```
>>> def cons_f(x):
...     return [x[0]**2 + x[1], x[0]**2 - x[1]]
>>> def cons_J(x):
...     return [[2*x[0], 1], [2*x[0], -1]]
>>> def cons_H(x, v):
...     return v[0]*np.array([[2, 0], [0, 0]]) + v[1]*np.array([[2, 0], [0, 0]])
>>> from scipy.optimize import NonlinearConstraint
>>> nonlinear_constraint = NonlinearConstraint(cons_f, -np.inf, 1, jac=cons_J,
...     hess=cons_H)
```

Alternatively, it is also possible to define the Hessian $H(x, v)$ as a sparse matrix,

```
>>> from scipy.sparse import csc_matrix
>>> def cons_H_sparse(x, v):
...     return v[0]*csc_matrix([[2, 0], [0, 0]]) + v[1]*csc_matrix([[2, 0], [0, 0]])
>>> nonlinear_constraint = NonlinearConstraint(cons_f, -np.inf, 1,
...     jac=cons_J, hess=cons_H_sparse)
```

or as a *LinearOperator* object.

```
>>> from scipy.sparse.linalg import LinearOperator
>>> def cons_H_linear_operator(x, v):
...     def matvec(p):
...         return np.array([p[0]*2*(v[0]+v[1]), 0])
...     return LinearOperator((2, 2), matvec=matvec)
>>> nonlinear_constraint = NonlinearConstraint(cons_f, -np.inf, 1,
...                                           jac=cons_J, hess=cons_H_linear_
↳ operator)
```

When the evaluation of the Hessian $H(x, v)$ is difficult to implement or computationally infeasible, one may use *HessianUpdateStrategy*. Currently available strategies are *BFGS* and *SR1*.

```
>>> from scipy.optimize import BFGS
>>> nonlinear_constraint = NonlinearConstraint(cons_f, -np.inf, 1, jac=cons_J,
↳ hess=BFGS())
```

Alternatively, the Hessian may be approximated using finite differences.

```
>>> nonlinear_constraint = NonlinearConstraint(cons_f, -np.inf, 1, jac=cons_J,
↳ hess='2-point')
```

The Jacobian of the constraints can be approximated by finite differences as well. In this case, however, the Hessian cannot be computed with finite differences and needs to be provided by the user or defined using *HessianUpdateStrategy*.

```
>>> nonlinear_constraint = NonlinearConstraint(cons_f, -np.inf, 1, jac='2-
↳ point', hess=BFGS())
```

Solving the Optimization Problem:

The optimization problem is solved using:

```
>>> x0 = np.array([0.5, 0])
>>> res = minimize(rosen, x0, method='trust-constr', jac=rosen_der,
↳ hess=rosen_hess,
...               constraints=[linear_constraint, nonlinear_constraint],
...               options={'verbose': 1}, bounds=bounds)
# may vary
`gtol` termination condition is satisfied.
Number of iterations: 12, function evaluations: 8, CG iterations: 7,
↳ optimality: 2.99e-09, constraint violation: 1.11e-16, execution time: 0.016
↳ s.
>>> print(res.x)
[0.41494531 0.17010937]
```

When needed, the objective function Hessian can be defined using a *LinearOperator* object,

```
>>> def rosen_hess_linop(x):
...     def matvec(p):
...         return rosen_hess_p(x, p)
...     return LinearOperator((2, 2), matvec=matvec)
>>> res = minimize(rosen, x0, method='trust-constr', jac=rosen_der,
↳ hess=rosen_hess_linop,
```

(continues on next page)

(continued from previous page)

```

...         constraints=[linear_constraint, nonlinear_constraint],
...         options={'verbose': 1}, bounds=bounds)
# may vary
`gtol` termination condition is satisfied.
Number of iterations: 12, function evaluations: 8, CG iterations: 7,
↳optimality: 2.99e-09, constraint violation: 1.11e-16, execution time: 0.018
↳s.
>>> print(res.x)
[0.41494531 0.17010937]

```

or a Hessian-vector product through the parameter `hessp`.

```

>>> res = minimize(rosen, x0, method='trust-constr', jac=rosen_der,
↳hessp=rosen_hess_p,
...         constraints=[linear_constraint, nonlinear_constraint],
...         options={'verbose': 1}, bounds=bounds)
# may vary
`gtol` termination condition is satisfied.
Number of iterations: 12, function evaluations: 8, CG iterations: 7,
↳optimality: 2.99e-09, constraint violation: 1.11e-16, execution time: 0.018
↳s.
>>> print(res.x)
[0.41494531 0.17010937]

```

Alternatively, the first and second derivatives of the objective function can be approximated. For instance, the Hessian can be approximated with *SR1* quasi-Newton approximation and the gradient with finite differences.

```

>>> from scipy.optimize import SR1
>>> res = minimize(rosen, x0, method='trust-constr', jac="2-point",
↳hess=SR1(),
...         constraints=[linear_constraint, nonlinear_constraint],
...         options={'verbose': 1}, bounds=bounds)
# may vary
`gtol` termination condition is satisfied.
Number of iterations: 12, function evaluations: 24, CG iterations: 7,
↳optimality: 4.48e-09, constraint violation: 0.00e+00, execution time: 0.016
↳s.
>>> print(res.x)
[0.41494531 0.17010937]

```

Sequential Least Squares Programming (SLSQP) Algorithm (`method='SLSQP'`)

The SLSQP method deals with constrained minimization problems of the form:

$$\begin{aligned}
 & \min_x && f(x) \\
 \text{subject to:} && c_j(x) = 0, && j \in \mathcal{E} \\
 && c_j(x) \geq 0, && j \in \mathcal{I} \\
 && \text{lb}_i \leq x_i \leq \text{ub}_i, && i = 1, \dots, N.
 \end{aligned}$$

Where \mathcal{E} or \mathcal{I} are sets of indices containing equality and inequality constraints.

Both linear and nonlinear constraints are defined as dictionaries with keys `type`, `fun` and `jac`.

```

>>> ineq_cons = {'type': 'ineq',
...             'fun' : lambda x: np.array([1 - x[0] - 2*x[1],
...                                       1 - x[0]**2 - x[1],
...                                       1 - x[0]**2 + x[1]]),
...             'jac' : lambda x: np.array([[ -1.0, -2.0],
...                                       [-2*x[0], -1.0],
...                                       [-2*x[0], 1.0]])}
>>> eq_cons = {'type': 'eq',
...            'fun' : lambda x: np.array([2*x[0] + x[1] - 1]),
...            'jac' : lambda x: np.array([2.0, 1.0])}

```

And the optimization problem is solved with:

```

>>> x0 = np.array([0.5, 0])
>>> res = minimize(rosen, x0, method='SLSQP', jac=rosen_der,
...              constraints=[eq_cons, ineq_cons], options={'ftol': 1e-9,
...              ↪ 'disp': True},
...              bounds=bounds)
# may vary
Optimization terminated successfully.      (Exit mode 0)
        Current function value: 0.342717574857755
        Iterations: 5
        Function evaluations: 6
        Gradient evaluations: 5
>>> print(res.x)
[0.41494475 0.1701105 ]

```

Most of the options available for the method 'trust-constr' are not available for 'SLSQP'.

Global optimization

Global optimization aims to find the global minimum of a function within given bounds, in the presence of potentially many local minima. Typically, global minimizers efficiently search the parameter space, while using a local minimizer (e.g., *minimize*) under the hood. SciPy contains a number of good global optimizers. Here, we'll use those on the same objective function, namely the (aptly named) *eggholder* function:

```

>>> def eggholder(x):
...     return -(x[1] + 47) * np.sin(np.sqrt(abs(x[0]/2 + (x[1] + 47))))
...     -x[0] * np.sin(np.sqrt(abs(x[0] - (x[1] + 47))))
>>> bounds = [(-512, 512), (-512, 512)]

```

This function looks like an egg carton:

```

>>> import matplotlib.pyplot as plt
>>> from mpl_toolkits.mplot3d import Axes3D


>>> x = np.arange(-512, 513)
>>> y = np.arange(-512, 513)
>>> xgrid, ygrid = np.meshgrid(x, y)
>>> xy = np.stack([xgrid, ygrid])

```

(continues on next page)

(continued from previous page)

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111, projection='3d')
>>> ax.view_init(45, -45)
>>> ax.plot_surface(xgrid, ygrid, eggholder(xy), cmap='terrain')
>>> ax.set_xlabel('x')
>>> ax.set_ylabel('y')
>>> ax.set_zlabel('eggholder(x, y)')
>>> plt.show()
```



We now use the global optimizers to obtain the minimum and the function value at the minimum. We'll store the results in a dictionary so we can compare different optimization results later.

```
>>> from scipy import optimize
>>> results = dict()
>>> results['shgo'] = optimize.shgo(eggholder, bounds)
>>> results['shgo']
  fun: -935.3379515604197 # may vary
  funl: array([-935.33795156])
message: 'Optimization terminated successfully.'
  nfev: 42
   nit: 2
  nlfv: 37
  nlhev: 0
  nljev: 9
success: True
   x: array([[439.48096952, 453.97740589]])
  xl: array([[439.48096952, 453.97740589]])
```

```
>>> results['DA'] = optimize.dual_annealing(eggholder, bounds)
>>> results['DA']
    fun: -956.9182316237413 # may vary
message: ['Maximum number of iteration reached']
  nfev: 4091
  nhev: 0
   nit: 1000
  njev: 0
    x: array([482.35324114, 432.87892901])
```

All optimizers return an `OptimizeResult`, which in addition to the solution contains information on the number of function evaluations, whether the optimization was successful, and more. For brevity, we won't show the full output of the other optimizers:

```
>>> results['DE'] = optimize.differential_evolution(eggholder, bounds)
>>> results['BH'] = optimize.basinhopping(eggholder, bounds)
```

`shgo` has a second method, which returns all local minima rather than only what it thinks is the global minimum:

```
>>> results['shgo_sobol'] = optimize.shgo(eggholder, bounds, n=200, iters=5,
...                                     sampling_method='sobol')
```


We'll now plot all found minima on a heatmap of the function:

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> im = ax.imshow(eggholder(xy), interpolation='bilinear', origin='lower',
...               cmap='gray')
>>> ax.set_xlabel('x')
>>> ax.set_ylabel('y')
>>>
>>> def plot_point(res, marker='o', color=None):
...     ax.plot(512+res.x[0], 512+res.x[1], marker=marker, color=color, ms=10)

>>> plot_point(results['BH'], color='y') # basinhopping - yellow
>>> plot_point(results['DE'], color='c') # differential_evolution - cyan
>>> plot_point(results['DA'], color='w') # dual_annealing. - white

>>> # SHGO produces multiple minima, plot them all (with a smaller marker_
↳size)
>>> plot_point(results['shgo'], color='r', marker='+')
>>> plot_point(results['shgo_sobol'], color='r', marker='x')
>>> for i in range(results['shgo_sobol'].xl.shape[0]):
...     ax.plot(512 + results['shgo_sobol'].xl[i, 0],
...             512 + results['shgo_sobol'].xl[i, 1],
...             'ro', ms=2)

>>> ax.set_xlim([-4, 514*2])
>>> ax.set_ylim([-4, 514*2])
>>> plt.show()
```



Least-squares minimization (`least_squares`)

SciPy is capable of solving robustified bound-constrained nonlinear least-squares problems:

$$\min_{\mathbf{x}} \frac{1}{2} \sum_{i=1}^m \rho(f_i(\mathbf{x})^2) \quad (4.4)$$

$$\text{subject to } \mathbf{lb} \leq \mathbf{x} \leq \mathbf{ub} \quad (4.5)$$

Here $f_i(\mathbf{x})$ are smooth functions from \mathbb{R}^n to \mathbb{R} , we refer to them as residuals. The purpose of a scalar-valued function $\rho(\cdot)$ is to reduce the influence of outlier residuals and contribute to robustness of the solution, we refer to it as a loss function. A linear loss function gives a standard least-squares problem. Additionally, constraints in a form of lower and upper bounds on some of x_j are allowed.

All methods specific to least-squares minimization utilize a $m \times n$ matrix of partial derivatives called Jacobian and defined as $J_{ij} = \partial f_i / \partial x_j$. It is highly recommended to compute this matrix analytically and pass it to `least_squares`, otherwise, it will be estimated by finite differences, which takes a lot of additional time and can be very inaccurate in hard cases.

Function `least_squares` can be used for fitting a function $\varphi(t; \mathbf{x})$ to empirical data $\{(t_i, y_i), i = 0, \dots, m - 1\}$. To do this, one should simply precompute residuals as $f_i(\mathbf{x}) = w_i(\varphi(t_i; \mathbf{x}) - y_i)$, where w_i are weights assigned to each observation.

Example of solving a fitting problem

Here we consider an enzymatic reaction¹. There are 11 residuals defined as

$$f_i(x) = \frac{x_0(u_i^2 + u_i x_1)}{u_i^2 + u_i x_2 + x_3} - y_i, \quad i = 0, \dots, 10,$$

where y_i are measurement values and u_i are values of the independent variable. The unknown vector of parameters is $\mathbf{x} = (x_0, x_1, x_2, x_3)^T$. As was said previously, it is recommended to compute Jacobian matrix in a closed form:

$$J_{i0} = \frac{\partial f_i}{\partial x_0} = \frac{u_i^2 + u_i x_1}{u_i^2 + u_i x_2 + x_3} \quad (4.6)$$

$$J_{i1} = \frac{\partial f_i}{\partial x_1} = \frac{u_i x_0}{u_i^2 + u_i x_2 + x_3} \quad (4.7)$$

$$J_{i2} = \frac{\partial f_i}{\partial x_2} = -\frac{x_0(u_i^2 + u_i x_1)u_i}{(u_i^2 + u_i x_2 + x_3)^2} \quad (4.8)$$

$$J_{i3} = \frac{\partial f_i}{\partial x_3} = -\frac{x_0(u_i^2 + u_i x_1)}{(u_i^2 + u_i x_2 + x_3)^2} \quad (4.9)$$

We are going to use the “hard” starting point defined in². To find a physically meaningful solution, avoid potential division by zero and assure convergence to the global minimum we impose constraints $0 \leq x_j \leq 100, j = 0, 1, 2, 3$.

The code below implements least-squares estimation of \mathbf{x} and finally plots the original data and the fitted model function:

```
>>> from scipy.optimize import least_squares
```

```
>>> def model(x, u):
...     return x[0] * (u ** 2 + x[1] * u) / (u ** 2 + x[2] * u + x[3])
```

```
>>> def fun(x, u, y):
...     return model(x, u) - y
```

```
>>> def jac(x, u, y):
...     J = np.empty((u.size, x.size))
...     den = u ** 2 + x[2] * u + x[3]
...     num = u ** 2 + x[1] * u
...     J[:, 0] = num / den
...     J[:, 1] = x[0] * u / den
...     J[:, 2] = -x[0] * num * u / den ** 2
...     J[:, 3] = -x[0] * num / den ** 2
...     return J
```

```
>>> u = np.array([4.0, 2.0, 1.0, 5.0e-1, 2.5e-1, 1.67e-1, 1.25e-1, 1.0e-1,
...              8.33e-2, 7.14e-2, 6.25e-2])
... y = np.array([1.957e-1, 1.947e-1, 1.735e-1, 1.6e-1, 8.44e-2, 6.27e-2,
...              4.56e-2, 3.42e-2, 3.23e-2, 2.35e-2, 2.46e-2])
... x0 = np.array([2.5, 3.9, 4.15, 3.9])
>>> res = least_squares(fun, x0, jac=jac, bounds=(0, 100), args=(u, y),
...                    ↪ verbose=1)
```

(continues on next page)


¹ J. Kowalik and J. F. Morrison, “Analysis of kinetic data for allosteric enzyme reactions as a nonlinear regression problem”, Math. Biosci., vol. 2, pp. 57-66, 1968.

² B. M. Averick et al., “The MINPACK-2 Test Problem Collection”.

(continued from previous page)

```
# may vary
`ftol` termination condition is satisfied.
Function evaluations 130, initial cost 4.4383e+00, final cost 1.5375e-04,
↳first-order optimality 4.92e-08.
>>> res.x
array([ 0.19280596,  0.19130423,  0.12306063,  0.13607247])
```

```
>>> import matplotlib.pyplot as plt
>>> u_test = np.linspace(0, 5)
>>> y_test = model(res.x, u_test)
>>> plt.plot(u, y, 'o', markersize=4, label='data')
>>> plt.plot(u_test, y_test, label='fitted model')
>>> plt.xlabel("u")
>>> plt.ylabel("y")
>>> plt.legend(loc='lower right')
>>> plt.show()
```



Further examples

Three interactive examples below illustrate usage of `least_squares` in greater detail.

1. [Large-scale bundle adjustment in scipy](#) demonstrates large-scale capabilities of `least_squares` and how to efficiently compute finite difference approximation of sparse Jacobian.
2. [Robust nonlinear regression in scipy](#) shows how to handle outliers with a robust loss function in a nonlinear regression.
3. [Solving a discrete boundary-value problem in scipy](#) examines how to solve a large system of equations and use bounds to achieve desired properties of the solution.

For the details about mathematical algorithms behind the implementation refer to documentation of `least_squares`.

Univariate function minimizers (`minimize_scalar`)

Often only the minimum of an univariate function (i.e., a function that takes a scalar as input) is needed. In these circumstances, other optimization techniques have been developed that can work faster. These are accessible from the `minimize_scalar` function, which proposes several algorithms.

Unconstrained minimization (`method='brent'`)

There are, actually, two methods that can be used to minimize an univariate function: `brent` and `golden`, but `golden` is included only for academic purposes and should rarely be used. These can be respectively selected through the `method` parameter in `minimize_scalar`. The `brent` method uses Brent's algorithm for locating a minimum. Optimally, a bracket (the `bracket` parameter) should be given which contains the minimum desired. A bracket is a triple (a, b, c) such that $f(a) > f(b) < f(c)$ and $a < b < c$. If this is not given, then alternatively two starting points can be chosen and a bracket will be found from these points using a simple marching algorithm. If these two starting points are not provided, 0 and 1 will be used (this may not be the right choice for your function and result in an unexpected minimum being returned).

Here is an example:

```
>>> from scipy.optimize import minimize_scalar
>>> f = lambda x: (x - 2) * (x + 1)**2
>>> res = minimize_scalar(f, method='brent')
>>> print(res.x)
1.0
```

Bounded minimization (`method='bounded'`)

Very often, there are constraints that can be placed on the solution space before minimization occurs. The `bounded` method in `minimize_scalar` is an example of a constrained minimization procedure that provides a rudimentary interval constraint for scalar functions. The interval constraint allows the minimization to occur only between two fixed endpoints, specified using the mandatory `bounds` parameter.

For example, to find the minimum of $J_1(x)$ near $x = 5$, `minimize_scalar` can be called using the interval $[4, 7]$ as a constraint. The result is $x_{\min} = 5.3314$:

```
>>> from scipy.special import j1
>>> res = minimize_scalar(j1, bounds=(4, 7), method='bounded')
>>> res.x
5.33144184241
```

Custom minimizers

Sometimes, it may be useful to use a custom method as a (multivariate or univariate) minimizer, for example, when using some library wrappers of `minimize` (e.g., `basinhopping`).

We can achieve that by, instead of passing a method name, passing a callable (either a function or an object implementing a `__call__` method) as the `method` parameter.

Let us consider an (admittedly rather virtual) need to use a trivial custom multivariate minimization method that will just search the neighborhood in each dimension independently with a fixed step size:

```
>>> from scipy.optimize import OptimizeResult
>>> def custmin(fun, x0, args=(), maxfev=None, stepsize=0.1,
...           maxiter=100, callback=None, **options):
...     bestx = x0
```

(continues on next page)

(continued from previous page)

```

...     besty = fun(x0)
...     funcalls = 1
...     niter = 0
...     improved = True
...     stop = False
...
...     while improved and not stop and niter < maxiter:
...         improved = False
...         niter += 1
...         for dim in range(np.size(x0)):
...             for s in [bestx[dim] - stepsize, bestx[dim] + stepsize]:
...                 testx = np.copy(bestx)
...                 testx[dim] = s
...                 testy = fun(testx, *args)
...                 funcalls += 1
...                 if testy < besty:
...                     besty = testy
...                     bestx = testx
...                     improved = True
...                 if callback is not None:
...                     callback(bestx)
...                 if maxfev is not None and funcalls >= maxfev:
...                     stop = True
...                     break
...
...     return OptimizeResult(fun=besty, x=bestx, nit=niter,
...                           nfev=funcalls, success=(niter > 1))
>>> x0 = [1.35, 0.9, 0.8, 1.1, 1.2]
>>> res = minimize(rosen, x0, method=custmin, options=dict(stepsize=0.05))
>>> res.x
array([1., 1., 1., 1., 1.])

```

This will work just as well in case of univariate optimization:

```

>>> def custmin(fun, bracket, args=(), maxfev=None, stepsize=0.1,
...             maxiter=100, callback=None, **options):
...     bestx = (bracket[1] + bracket[0]) / 2.0
...     besty = fun(bestx)
...     funcalls = 1
...     niter = 0
...     improved = True
...     stop = False
...
...     while improved and not stop and niter < maxiter:
...         improved = False
...         niter += 1
...         for testx in [bestx - stepsize, bestx + stepsize]:
...             testy = fun(testx, *args)
...             funcalls += 1
...             if testy < besty:
...                 besty = testy
...                 bestx = testx

```

(continues on next page)

(continued from previous page)

```

...         improved = True
...     if callback is not None:
...         callback(bestx)
...     if maxfev is not None and funcalls >= maxfev:
...         stop = True
...         break
...
...     return OptimizeResult(fun=besty, x=bestx, nit=niter,
...                           nfev=funcalls, success=(niter > 1))
>>> def f(x):
...     return (x - 2)**2 * (x + 2)**2
>>> res = minimize_scalar(f, bracket=(-3.5, 0), method=custmin,
...                       options=dict(stepsize = 0.05))
>>> res.x
-2.0

```

Root finding

Scalar functions

If one has a single-variable equation, there are multiple different root finding algorithms that can be tried. Most of these algorithms require the endpoints of an interval in which a root is expected (because the function changes signs). In general, *brentq* is the best choice, but the other methods may be useful in certain circumstances or for academic purposes. When a bracket is not available, but one or more derivatives are available, then *newton* (or *halley*, *secant*) may be applicable. This is especially the case if the function is defined on a subset of the complex plane, and the bracketing methods cannot be used.

Fixed-point solving

A problem closely related to finding the zeros of a function is the problem of finding a fixed point of a function. A fixed point of a function is the point at which evaluation of the function returns the point: $g(x) = x$. Clearly, the fixed point of g is the root of $f(x) = g(x) - x$. Equivalently, the root of f is the fixed point of $g(x) = f(x) + x$. The routine *fixed_point* provides a simple iterative method using Aitkens sequence acceleration to estimate the fixed point of g given a starting point.

Sets of equations

Finding a root of a set of non-linear equations can be achieved using the *root* function. Several methods are available, amongst which *hybr* (the default) and *lm*, which, respectively, use the hybrid method of Powell and the Levenberg-Marquardt method from MINPACK.

The following example considers the single-variable transcendental equation

$$x + 2 \cos(x) = 0,$$

a root of which can be found as follows:

```

>>> import numpy as np
>>> from scipy.optimize import root
>>> def func(x):
...     return x + 2 * np.cos(x)
>>> sol = root(func, 0.3)
>>> sol.x

```

(continues on next page)

(continued from previous page)

```
array([-1.02986653])
>>> sol.fun
array([-6.66133815e-16])
```

Consider now a set of non-linear equations

$$\begin{aligned}x_0 \cos(x_1) &= 4, \\x_0 x_1 - x_1 &= 5.\end{aligned}$$

We define the objective function so that it also returns the Jacobian and indicate this by setting the `jac` parameter to `True`. Also, the Levenberg-Marquardt solver is used here.

```
>>> def func2(x):
...     f = [x[0] * np.cos(x[1]) - 4,
...          x[1]*x[0] - x[1] - 5]
...     df = np.array([[np.cos(x[1]), -x[0] * np.sin(x[1])],
...                    [x[1], x[0] - 1]])
...     return f, df
>>> sol = root(func2, [1, 1], jac=True, method='lm')
>>> sol.x
array([ 6.50409711,  0.90841421])
```

Root finding for large problems

Methods `hybr` and `lm` in `root` cannot deal with a very large number of variables (N), as they need to calculate and invert a dense $N \times N$ Jacobian matrix on every Newton step. This becomes rather inefficient when N grows.

Consider, for instance, the following problem: we need to solve the following integrodifferential equation on the square $[0, 1] \times [0, 1]$:

$$(\partial_x^2 + \partial_y^2)P + 5 \left(\int_0^1 \int_0^1 \cosh(P) dx dy \right)^2 = 0$$

with the boundary condition $P(x, 1) = 1$ on the upper edge and $P = 0$ elsewhere on the boundary of the square. This can be done by approximating the continuous function P by its values on a grid, $P_{n,m} \approx P(nh, mh)$, with a small grid spacing h . The derivatives and integrals can then be approximated; for instance $\partial_x^2 P(x, y) \approx (P(x+h, y) - 2P(x, y) + P(x-h, y))/h^2$. The problem is then equivalent to finding the root of some function `residual(P)`, where `P` is a vector of length $N_x N_y$.

Now, because $N_x N_y$ can be large, methods `hybr` or `lm` in `root` will take a long time to solve this problem. The solution can, however, be found using one of the large-scale solvers, for example `krylov`, `broyden2`, or `anderson`. These use what is known as the inexact Newton method, which instead of computing the Jacobian matrix exactly, forms an approximation for it.

The problem we have can now be solved as follows:

```
import numpy as np
from scipy.optimize import root
from numpy import cosh, zeros_like, mgrid, zeros

# parameters
nx, ny = 75, 75
hx, hy = 1./(nx-1), 1./(ny-1)
```

(continues on next page)

(continued from previous page)

```

P_left, P_right = 0, 0
P_top, P_bottom = 1, 0

def residual(P):
    d2x = zeros_like(P)
    d2y = zeros_like(P)

    d2x[1:-1] = (P[2:] - 2*P[1:-1] + P[:-2]) / hx/hx
    d2x[0] = (P[1] - 2*P[0] + P_left)/hx/hx
    d2x[-1] = (P_right - 2*P[-1] + P[-2])/hx/hx


    d2y[:,1:-1] = (P[:,2:] - 2*P[:,1:-1] + P[:, :-2])/hy/hy
    d2y[:,0] = (P[:,1] - 2*P[:,0] + P_bottom)/hy/hy
    d2y[:, -1] = (P_top - 2*P[:, -1] + P[:, -2])/hy/hy

    return d2x + d2y + 5*cosh(P).mean()**2

# solve
guess = zeros((nx, ny), float)
sol = root(residual, guess, method='krylov', options={'disp': True})
#sol = root(residual, guess, method='broyden2', options={'disp': True, 'max_
→rank': 50})
#sol = root(residual, guess, method='anderson', options={'disp': True, 'M':_
→10})
print('Residual: %g' % abs(residual(sol.x)).max())

# visualize
import matplotlib.pyplot as plt
x, y = mgrid[0:1:(nx*1j), 0:1:(ny*1j)]
plt.pcolormesh(x, y, sol.x, shading='gouraud')
plt.colorbar()
plt.show()

```



Still too slow? Preconditioning.

When looking for the zero of the functions $f_i(\mathbf{x}) = 0$, $i = 1, 2, \dots, N$, the `krylov` solver spends most of the time inverting the Jacobian matrix,

$$J_{ij} = \frac{\partial f_i}{\partial x_j}.$$

If you have an approximation for the inverse matrix $M \approx J^{-1}$, you can use it for *preconditioning* the linear-inversion problem. The idea is that instead of solving $J\mathbf{s} = \mathbf{y}$ one solves $MJ\mathbf{s} = M\mathbf{y}$: since matrix MJ is “closer” to the identity matrix than J is, the equation should be easier for the Krylov method to deal with.

The matrix M can be passed to `root` with method `krylov` as an option `options['jac_options']['inner_M']`. It can be a (sparse) matrix or a `scipy.sparse.linalg.LinearOperator` instance.

For the problem in the previous section, we note that the function to solve consists of two parts: the first one is the application of the Laplace operator, $[\partial_x^2 + \partial_y^2]P$, and the second is the integral. We can actually easily compute the Jacobian corresponding to the Laplace operator part: we know that in 1-D

$$\partial_x^2 \approx \frac{1}{h_x^2} \begin{pmatrix} -2 & 1 & 0 & 0 \dots \\ 1 & -2 & 1 & 0 \dots \\ 0 & 1 & -2 & 1 \dots \\ \dots & & & \dots \end{pmatrix} = h_x^{-2} L$$

so that the whole 2-D operator is represented by

$$J_1 = \partial_x^2 + \partial_y^2 \simeq h_x^{-2} L \otimes I + h_y^{-2} I \otimes L$$

The matrix J_2 of the Jacobian corresponding to the integral is more difficult to calculate, and since *all* of its entries are nonzero, it will be difficult to invert. J_1 on the other hand is a relatively simple matrix, and can be inverted by `scipy.sparse.linalg.splu` (or the inverse can be approximated by `scipy.sparse.linalg.spilu`). So we are content to take $M \approx J_1^{-1}$ and hope for the best.

In the example below, we use the preconditioner $M = J_1^{-1}$.

```
import numpy as np
from scipy.optimize import root
from scipy.sparse import spdiags, kron
from scipy.sparse.linalg import spilu, LinearOperator
from numpy import cosh, zeros_like, mgrid, zeros, eye

# parameters
nx, ny = 75, 75
hx, hy = 1./(nx-1), 1./(ny-1)

P_left, P_right = 0, 0
P_top, P_bottom = 1, 0

def get_preconditioner():
    """Compute the preconditioner M"""
    diags_x = zeros((3, nx))
    diags_x[0, :] = 1/hx/hx
    diags_x[1, :] = -2/hx/hx
    diags_x[2, :] = 1/hx/hx
    Lx = spdiags(diags_x, [-1, 0, 1], nx, nx)
```

(continues on next page)

(continued from previous page)

```

diags_y = zeros((3, ny))
diags_y[0,:] = 1/hy/hy
diags_y[1,:] = -2/hy/hy
diags_y[2,:] = 1/hy/hy
Ly = spdiags(diags_y, [-1,0,1], ny, ny)

J1 = kron(Lx, eye(ny)) + kron(eye(nx), Ly)

# Now we have the matrix `J_1`. We need to find its inverse `M` --
# however, since an approximate inverse is enough, we can use
# the *incomplete LU* decomposition

J1_ilu = spilu(J1)

# This returns an object with a method .solve() that evaluates
# the corresponding matrix-vector product. We need to wrap it into
# a LinearOperator before it can be passed to the Krylov methods:

M = LinearOperator(shape=(nx*ny, nx*ny), matvec=J1_ilu.solve)
return M

def solve(preconditioning=True):
    """Compute the solution"""
    count = [0]

    def residual(P):
        count[0] += 1

        d2x = zeros_like(P)
        d2y = zeros_like(P)

        d2x[1:-1] = (P[2:] - 2*P[1:-1] + P[:-2])/hx/hx
        d2x[0] = (P[1] - 2*P[0] + P_left)/hx/hx
        d2x[-1] = (P_right - 2*P[-1] + P[-2])/hx/hx

        d2y[:,1:-1] = (P[:,2:] - 2*P[:,1:-1] + P[:, :-2])/hy/hy
        d2y[:,0] = (P[:,1] - 2*P[:,0] + P_bottom)/hy/hy
        d2y[:, -1] = (P_top - 2*P[:, -1] + P[:, -2])/hy/hy

        return d2x + d2y + 5*cosh(P).mean()*2

    # preconditioner
    if preconditioning:
        M = get_preconditioner()
    else:
        M = None

    # solve
    guess = zeros((nx, ny), float)

    sol = root(residual, guess, method='krylov',
               options={'disp': True,
```

(continues on next page)

(continued from previous page)

```
        'jac_options': {'inner_M': M})
print('Residual', abs(residual(sol.x)).max())
print('Evaluations', count[0])

return sol.x

def main():
    sol = solve(preconditioning=True)

    # visualize
    import matplotlib.pyplot as plt
    x, y = mgrid[0:1:(nx*1j), 0:1:(ny*1j)]
    plt.clf()
    plt.pcolor(x, y, sol)
    plt.clim(0, 1)
    plt.colorbar()
    plt.show()

if __name__ == "__main__":
    main()
```

Resulting run, first without preconditioning:

```
0: |F(x)| = 803.614; step 1; tol 0.000257947
1: |F(x)| = 345.912; step 1; tol 0.166755
2: |F(x)| = 139.159; step 1; tol 0.145657
3: |F(x)| = 27.3682; step 1; tol 0.0348109
4: |F(x)| = 1.03303; step 1; tol 0.00128227
5: |F(x)| = 0.0406634; step 1; tol 0.00139451
6: |F(x)| = 0.00344341; step 1; tol 0.00645373
7: |F(x)| = 0.000153671; step 1; tol 0.00179246
8: |F(x)| = 6.7424e-06; step 1; tol 0.00173256
Residual 3.57078908664e-07
Evaluations 317
```

and then with preconditioning:

```
0: |F(x)| = 136.993; step 1; tol 7.49599e-06
1: |F(x)| = 4.80983; step 1; tol 0.00110945
2: |F(x)| = 0.195942; step 1; tol 0.00149362
3: |F(x)| = 0.000563597; step 1; tol 7.44604e-06
4: |F(x)| = 1.00698e-09; step 1; tol 2.87308e-12
Residual 9.29603061195e-11
Evaluations 77
```

Using a preconditioner reduced the number of evaluations of the `residual` function by a factor of 4. For problems where the residual is expensive to compute, good preconditioning can be crucial — it can even decide whether the problem is solvable in practice or not.

Preconditioning is an art, science, and industry. Here, we were lucky in making a simple choice that worked reasonably well, but there is a lot more depth to this topic than is shown here.

Linear programming (`linprog`)

The function `linprog` can minimize a linear objective function subject to linear equality and inequality constraints. This kind of problem is well known as linear programming. Linear programming solves problems of the following form:

$$\begin{aligned} \min_x \quad & c^T x \\ \text{such that} \quad & A_{ub}x \leq b_{ub}, \\ & A_{eq}x = b_{eq}, \\ & l \leq x \leq u, \end{aligned}$$

where x is a vector of decision variables; c , b_{ub} , b_{eq} , l , and u are vectors; and A_{ub} and A_{eq} are matrices.

In this tutorial, we will try to solve a typical linear programming problem using `linprog`.

Linear programming example

Consider the following simple linear programming problem:

$$\begin{aligned} \max_{x_1, x_2, x_3, x_4} \quad & 29x_1 + 45x_2 \\ \text{such that} \quad & x_1 - x_2 - 3x_3 \leq 5 \\ & 2x_1 - 3x_2 - 7x_3 + 3x_4 \geq 10 \\ & 2x_1 + 8x_2 + x_3 = 60 \\ & 4x_1 + 4x_2 + x_4 = 60 \\ & 0 \leq x_0 \\ & 0 \leq x_1 \leq 5 \\ & x_2 \leq 0.5 \\ & -3 \leq x_3 \end{aligned}$$

We need some mathematical manipulations to convert the target problem to the form accepted by `linprog`.

First of all, let's consider the objective function. We want to maximize the objective function, but `linprog` can only accept a minimization problem. This is easily remedied by converting the maximize $29x_1 + 45x_2$ to minimizing $-29x_1 - 45x_2$. Also, x_3, x_4 are not shown in the objective function. That means the weights corresponding with x_3, x_4 are zero. So, the objective function can be converted to:

$$\min_{x_1, x_2, x_3, x_4} \quad -29x_1 - 45x_2 + 0x_3 + 0x_4$$

If we define the vector of decision variables $x = [x_1, x_2, x_3, x_4]^T$, the objective weights vector c of `linprog` in this problem should be

$$c = [-29, -45, 0, 0]^T$$

Next, let's consider the two inequality constraints. The first one is a "less than" inequality, so it is already in the form accepted by `linprog`. The second one is a "greater than" inequality, so we need to multiply both sides by -1 to convert it to a "less than" inequality. Explicitly showing zero coefficients, we have:

$$\begin{aligned} x_1 - x_2 - 3x_3 + 0x_4 &\leq 5 \\ -2x_1 + 3x_2 + 7x_3 - 3x_4 &\leq -10 \end{aligned}$$

These equations can be converted to matrix form:

$$A_{ub}x \leq b_{ub}$$

where

$$A_{ub} = \begin{bmatrix} 1 & -1 & -3 & 0 \\ -2 & 3 & 7 & -3 \end{bmatrix}$$

$$b_{ub} = \begin{bmatrix} 5 \\ -10 \end{bmatrix}$$

Next, let's consider the two equality constraints. Showing zero weights explicitly, these are:

$$2x_1 + 8x_2 + 1x_3 + 0x_4 = 60$$

$$4x_1 + 4x_2 + 0x_3 + 1x_4 = 60$$

These equations can be converted to matrix form:

$$A_{eq}x = b_{eq}$$

where

$$A_{eq} = \begin{bmatrix} 2 & 8 & 1 & 0 \\ 4 & 4 & 0 & 1 \end{bmatrix}$$

$$b_{eq} = \begin{bmatrix} 60 \\ 60 \end{bmatrix}$$

Lastly, let's consider the separate inequality constraints on individual decision variables, which are known as “box constraints” or “simple bounds”. These constraints can be applied using the bounds argument of `linprog`. As noted in the `linprog` documentation, the default value of bounds is `(0, None)`, meaning that the lower bound on each decision variable is 0, and the upper bound on each decision variable is infinity: all the decision variables are non-negative. Our bounds are different, so we will need to specify the lower and upper bound on each decision variable as a tuple and group these tuples into a list.

Finally, we can solve the transformed problem using `linprog`.

```
>>> import numpy as np
>>> from scipy.optimize import linprog
>>> c = np.array([-29.0, -45.0, 0.0, 0.0])
>>> A_ub = np.array([[1.0, -1.0, -3.0, 0.0],
...                 [-2.0, 3.0, 7.0, -3.0]])
>>> b_ub = np.array([5.0, -10.0])
>>> A_eq = np.array([[2.0, 8.0, 1.0, 0.0],
...                 [4.0, 4.0, 0.0, 1.0]])
>>> b_eq = np.array([60.0, 60.0])
>>> x0_bounds = (0, None)
>>> x1_bounds = (0, 5.0)
>>> x2_bounds = (-np.inf, 0.5) # +/- np.inf can be used instead of None
>>> x3_bounds = (-3.0, None)
>>> bounds = [x0_bounds, x1_bounds, x2_bounds, x3_bounds]
>>> result = linprog(c, A_ub=A_ub, b_ub=b_ub, A_eq=A_eq, b_eq=b_eq,
->bounds=bounds)
>>> print(result)
      con: array([15.5361242 , 16.61288005]) # may vary
      fun: -370.2321976308326 # may vary
message: 'The algorithm terminated successfully and determined that the
->problem is infeasible.'
      nit: 6 # may vary
      slack: array([ 0.79314989, -1.76308532]) # may vary
      status: 2
      success: False
           x: array([ 6.60059391,  3.97366609, -0.52664076,  1.09007993]) # may
->vary
```

The result states that our problem is infeasible, meaning that there is no solution vector that satisfies all the constraints. That doesn't necessarily mean we did anything wrong; some problems truly are infeasible. Suppose, however, that we were to decide that our bound constraint on x_1 was too tight and that it could be loosened to $0 \leq x_1 \leq 6$. After adjusting our code `x1_bounds = (0, 6)` to reflect the change and executing it again:

```
>>> x1_bounds = (0, 6)
>>> bounds = [x0_bounds, x1_bounds, x2_bounds, x3_bounds]
>>> result = linprog(c, A_ub=A_ub, b_ub=b_ub, A_eq=A_eq, b_eq=b_eq,
↳ bounds=bounds)
>>> print(result)
   con: array([9.78840831e-09, 1.04662945e-08]) # may vary
   fun: -505.97435889013434 # may vary
message: 'Optimization terminated successfully.'
   nit: 4 # may vary
   slack: array([ 6.52747190e-10, -2.26730279e-09]) # may vary
   status: 0
   success: True
         x: array([ 9.41025641,  5.17948718, -0.25641026,  1.64102564]) # may
↳ vary
```

The result shows the optimization was successful. We can check the objective value (`result.fun`) is same as $c^T x$:

```
>>> x = np.array(result.x)
>>> print(c @ x)
-505.97435889013434 # may vary
```

We can also check that all constraints are satisfied within reasonable tolerances:

```
>>> print(b_ub - (A_ub @ x).flatten()) # this is equivalent to result.slack
[ 6.52747190e-10, -2.26730279e-09] # may vary
>>> print(b_eq - (A_eq @ x).flatten()) # this is equivalent to result.con
[ 9.78840831e-09, 1.04662945e-08] # may vary
>>> print([0 <= result.x[0], 0 <= result.x[1] <= 6.0, result.x[2] <= 0.5, -3.
↳ 0 <= result.x[3]])
[True, True, True, True]
```

If we need greater accuracy, typically at the expense of speed, we can solve using the revised simplex method:

```
>>> result = linprog(c, A_ub=A_ub, b_ub=b_ub, A_eq=A_eq, b_eq=b_eq,
↳ bounds=bounds, method='revised simplex')
>>> print(result)
   con: array([0.00000000e+00, 7.10542736e-15]) # may vary
   fun: -505.97435897435895 # may vary
message: 'Optimization terminated successfully.'
   nit: 5 # may vary
   slack: array([ 1.77635684e-15, -3.55271368e-15]) # may vary
   status: 0
   success: True
         x: array([ 9.41025641,  5.17948718, -0.25641026,  1.64102564]) # may
↳ vary
```

References

Some further reading and related software, such as Newton-Krylov [KK], PETSc [PP], and PyAMG [AMG]:

4.1.5 Interpolation (`scipy.interpolate`)

Contents

- *Interpolation* (`scipy.interpolate`)
 - *1-D interpolation* (`interp1d`)
 - *Multivariate data interpolation* (`griddata`)
 - *Spline interpolation*
 - * *Spline interpolation in 1-D: Procedural* (`interpolate.splXXX`)
 - * *Spline interpolation in 1-d: Object-oriented* (`UnivariateSpline`)
 - * *2-D spline representation: Procedural* (`bisplrep`)
 - * *2-D spline representation: Object-oriented* (`BivariateSpline`)
 - *Using radial basis functions for smoothing/interpolation*
 - * *1-D Example*
 - * *2-D Example*

There are several general interpolation facilities available in SciPy, for data in 1, 2, and higher dimensions:

- A class representing an interpolant (`interp1d`) in 1-D, offering several interpolation methods.
- Convenience function `griddata` offering a simple interface to interpolation in N dimensions (N = 1, 2, 3, 4, ...). Object-oriented interface for the underlying routines is also available.
- Functions for 1- and 2-D (smoothed) cubic-spline interpolation, based on the FORTRAN library FITPACK. They are both procedural and object-oriented interfaces for the FITPACK library.
- Interpolation using radial basis functions.


1-D interpolation (`interp1d`)

The `interp1d` class in `scipy.interpolate` is a convenient method to create a function based on fixed data points, which can be evaluated anywhere within the domain defined by the given data using linear interpolation. An instance of this class is created by passing the 1-D vectors comprising the data. The instance of this class defines a `__call__` method and can therefore be treated like a function which interpolates between known data values to obtain unknown values (it also has a docstring for help). Behavior at the boundary can be specified at instantiation time. The following example demonstrates its use, for linear and cubic spline interpolation:

```
>>> from scipy.interpolate import interp1d
```

```
>>> x = np.linspace(0, 10, num=11, endpoint=True)
>>> y = np.cos(-x**2/9.0)
>>> f = interp1d(x, y)
>>> f2 = interp1d(x, y, kind='cubic')
```

```
>>> xnew = np.linspace(0, 10, num=41, endpoint=True)
>>> import matplotlib.pyplot as plt
>>> plt.plot(x, y, 'o', xnew, f(xnew), '-', xnew, f2(xnew), '--')
>>> plt.legend(['data', 'linear', 'cubic'], loc='best')
>>> plt.show()
```




Another set of interpolations in `interp1d` is *nearest*, *previous*, and *next*, where they return the nearest, previous, or next point along the x-axis. Nearest and next can be thought of as a special case of a causal interpolating filter. The following example demonstrates their use, using the same data as in the previous example:

```
>>> from scipy.interpolate import interp1d
```

```
>>> x = np.linspace(0, 10, num=11, endpoint=True)
>>> y = np.cos(-x**2/9.0)
>>> f1 = interp1d(x, y, kind='nearest')
>>> f2 = interp1d(x, y, kind='previous')
>>> f3 = interp1d(x, y, kind='next')
```

```
>>> xnew = np.linspace(0, 10, num=1001, endpoint=True)
>>> import matplotlib.pyplot as plt
>>> plt.plot(x, y, 'o')
>>> plt.plot(xnew, f1(xnew), '-', xnew, f2(xnew), '--', xnew, f3(xnew), ':')
>>> plt.legend(['data', 'nearest', 'previous', 'next'], loc='best')
>>> plt.show()
```



Multivariate data interpolation (`griddata`)

Suppose you have multidimensional data, for instance, for an underlying function $f(x, y)$ you only know the values at points $(x[i], y[i])$ that do not form a regular grid.

Suppose we want to interpolate the 2-D function

```
>>> def func(x, y):
...     return x*(1-x)*np.cos(4*np.pi*x) * np.sin(4*np.pi*y**2)**2
```

on a grid in $[0, 1] \times [0, 1]$

```
>>> grid_x, grid_y = np.mgrid[0:1:100j, 0:1:200j]
```

but we only know its values at 1000 data points:

```
>>> points = np.random.rand(1000, 2)
>>> values = func(points[:,0], points[:,1])
```

This can be done with `griddata` – below, we try out all of the interpolation methods:

```
>>> from scipy.interpolate import griddata
>>> grid_z0 = griddata(points, values, (grid_x, grid_y), method='nearest')
>>> grid_z1 = griddata(points, values, (grid_x, grid_y), method='linear')
>>> grid_z2 = griddata(points, values, (grid_x, grid_y), method='cubic')
```


One can see that the exact result is reproduced by all of the methods to some degree, but for this smooth function the piecewise cubic interpolant gives the best results:

```
>>> import matplotlib.pyplot as plt
>>> plt.subplot(221)
>>> plt.imshow(func(grid_x, grid_y).T, extent=(0,1,0,1), origin='lower')
>>> plt.plot(points[:,0], points[:,1], 'k.', ms=1)
>>> plt.title('Original')
>>> plt.subplot(222)
```

(continues on next page)

(continued from previous page)

```
>>> plt.imshow(grid_z0.T, extent=(0,1,0,1), origin='lower')
>>> plt.title('Nearest')
>>> plt.subplot(223)
>>> plt.imshow(grid_z1.T, extent=(0,1,0,1), origin='lower')
>>> plt.title('Linear')
>>> plt.subplot(224)
>>> plt.imshow(grid_z2.T, extent=(0,1,0,1), origin='lower')
>>> plt.title('Cubic')
>>> plt.gcf().set_size_inches(6, 6)
>>> plt.show()
```



Spline interpolation

Spline interpolation in 1-D: Procedural (interpolate.splXXX)

Spline interpolation requires two essential steps: (1) a spline representation of the curve is computed, and (2) the spline is evaluated at the desired points. In order to find the spline representation, there are two different ways to represent a curve and obtain (smoothing) spline coefficients: directly and parametrically. The direct method finds the spline representation of a curve in a 2-D plane using the function `splrep`. The first two arguments are the only ones required, and these provide the x and y components of the curve. The normal output is a 3-tuple, (t, c, k) , containing the knot-points, t , the coefficients c and the order k of the spline. The default spline order is cubic, but this can be changed with the input keyword, k .

For curves in N-D space the function `splprep` allows defining the curve parametrically. For this function only 1 input argument is required. This input is a list of N -arrays representing the curve in N-D space. The length of each array is the number of curve points, and each array provides one component of the N-D data point. The parameter variable is given with the keyword argument, u , which defaults to an equally-spaced monotonic sequence between 0 and 1. The default output consists of two objects: a 3-tuple, (t, c, k) , containing the spline representation and the parameter variable u .

The keyword argument, s , is used to specify the amount of smoothing to perform during the spline fit. The default value of s is $s = m - \sqrt{2m}$ where m is the number of data-points being fit. Therefore, **if no smoothing is desired a value of $s = 0$ should be passed to the routines.**

Once the spline representation of the data has been determined, functions are available for evaluating the spline (`splev`) and its derivatives (`splev`, `spalde`) at any point and the integral of the spline between any two points (`splint`). In addition, for cubic splines ($k = 3$) with 8 or more knots, the roots of the spline can be estimated (`sproot`). These functions are demonstrated in the example that follows.

```
>>> import numpy as np
>>> import matplotlib.pyplot as plt
>>> from scipy import interpolate
```



Cubic-spline

```
>>> x = np.arange(0, 2*np.pi+np.pi/4, 2*np.pi/8)
>>> y = np.sin(x)
>>> tck = interpolate.splrep(x, y, s=0)
>>> xnew = np.arange(0, 2*np.pi, np.pi/50)
>>> ynew = interpolate.splev(xnew, tck, der=0)
```

```
>>> plt.figure()
>>> plt.plot(x, y, 'x', xnew, ynew, xnew, np.sin(xnew), x, y, 'b')
>>> plt.legend(['Linear', 'Cubic Spline', 'True'])
>>> plt.axis([-0.05, 6.33, -1.05, 1.05])
>>> plt.title('Cubic-spline interpolation')
>>> plt.show()
```

Derivative of spline


```
>>> yder = interpolate.splev(xnew, tck, der=1)
>>> plt.figure()
>>> plt.plot(xnew, yder, xnew, np.cos(xnew), '--')
>>> plt.legend(['Cubic Spline', 'True'])
>>> plt.axis([-0.05, 6.33, -1.05, 1.05])
>>> plt.title('Derivative estimation from spline')
>>> plt.show()
```



All derivatives of spline

```

>>> yders = interpolate.spalde(xnew, tck)
>>> plt.figure()
>>> for i in range(len(yders[0])):
...     plt.plot(xnew, [d[i] for d in yders], '--', label=f"{i} derivative")
>>> plt.legend()
>>> plt.axis([-0.05, 6.33, -1.05, 1.05])
>>> plt.title('All derivatives of a B-spline')
>>> plt.show()
    
```



Integral of spline

```

>>> def integ(x, tck, constant=-1):
...     x = np.atleast_1d(x)
...     out = np.zeros(x.shape, dtype=x.dtype)
...     for n in range(len(out)):
...         out[n] = interpolate.splint(0, x[n], tck)
...     out += constant
...     return out
    
```

```


>>> yint = integ(xnew, tck)
>>> plt.figure()
>>> plt.plot(xnew, yint, xnew, -np.cos(xnew), '--')
>>> plt.legend(['Cubic Spline', 'True'])
>>> plt.axis([-0.05, 6.33, -1.05, 1.05])
>>> plt.title('Integral estimation from spline')
>>> plt.show()
    
```

Roots of spline

```

>>> interpolate.sproot(tck)
array([3.1416])
    
```

Notice that `sproot` failed to find an obvious solution at the edge of the approximation interval, $x = 0$. If we define the



spline on a slightly larger interval, we recover both roots $x = 0$ and $x = 2\pi$:

```
>>> x = np.linspace(-np.pi/4, 2.*np.pi + np.pi/4, 21)
>>> y = np.sin(x)
>>> tck = interpolate.splprep(x, y, s=0)
>>> interpolate.sproot(tck)
array([0., 3.1416])
```


Parametric spline

```
>>> t = np.arange(0, 1.1, .1)
>>> x = np.sin(2*np.pi*t)
>>> y = np.cos(2*np.pi*t)
>>> tck, u = interpolate.splprep([x, y], s=0)
>>> unew = np.arange(0, 1.01, 0.01)
>>> out = interpolate.splev(unew, tck)
>>> plt.figure()
>>> plt.plot(x, y, 'x', out[0], out[1], np.sin(2*np.pi*unew), np.cos(2*np.
  ↳ pi*unew), x, y, 'b')
>>> plt.legend(['Linear', 'Cubic Spline', 'True'])
>>> plt.axis([-1.05, 1.05, -1.05, 1.05])
>>> plt.title('Spline of parametrically-defined curve')
>>> plt.show()
```

Spline interpolation in 1-d: Object-oriented (`UnivariateSpline`)

The spline-fitting capabilities described above are also available via an object-oriented interface. The 1-D splines are objects of the `UnivariateSpline` class, and are created with the x and y components of the curve provided as arguments to the constructor. The class defines `__call__`, allowing the object to be called with the x-axis values, at which the spline should be evaluated, returning the interpolated y-values. This is shown in the example below for the subclass `InterpolatedUnivariateSpline`. The `integral`, `derivatives`, and `roots` methods are also available on `UnivariateSpline` objects, allowing definite integrals, derivatives, and roots to be computed for the spline.

The `UnivariateSpline` class can also be used to smooth data by providing a non-zero value of the smoothing parameter



s , with the same meaning as the s keyword of the `splrep` function described above. This results in a spline that has fewer knots than the number of data points, and hence is no longer strictly an interpolating spline, but rather a smoothing spline. If this is not desired, the `InterpolatedUnivariateSpline` class is available. It is a subclass of `UnivariateSpline` that always passes through all points (equivalent to forcing the smoothing parameter to 0). This class is demonstrated in the example below.

The `LSQUnivariateSpline` class is the other subclass of `UnivariateSpline`. It allows the user to specify the number and location of internal knots explicitly with the parameter t . This allows for the creation of customized splines with non-linear spacing, to interpolate in some domains and smooth in others, or change the character of the spline.

```
>>> import numpy as np
>>> import matplotlib.pyplot as plt
>>> from scipy import interpolate
```


InterpolatedUnivariateSpline

```
>>> x = np.arange(0, 2*np.pi+np.pi/4, 2*np.pi/8)
>>> y = np.sin(x)
>>> s = interpolate.InterpolatedUnivariateSpline(x, y)
>>> xnew = np.arange(0, 2*np.pi, np.pi/50)
>>> ynew = s(xnew)
```


```
>>> plt.figure()
>>> plt.plot(x, y, 'x', xnew, ynew, xnew, np.sin(xnew), x, y, 'b')
>>> plt.legend(['Linear', 'InterpolatedUnivariateSpline', 'True'])
>>> plt.axis([-0.05, 6.33, -1.05, 1.05])
>>> plt.title('InterpolatedUnivariateSpline')
>>> plt.show()
```

LSQUnivariateSpline with non-uniform knots

```
>>> t = [np.pi/2-.1, np.pi/2+.1, 3*np.pi/2-.1, 3*np.pi/2+.1]
>>> s = interpolate.LSQUnivariateSpline(x, y, t, k=2)
>>> ynew = s(xnew)
```



```
>>> plt.figure()
>>> plt.plot(x, y, 'x', xnew, ynew, xnew, np.sin(xnew), x, y, 'b')
>>> plt.legend(['Linear', 'LSQUnivariateSpline', 'True'])
>>> plt.axis([-0.05, 6.33, -1.05, 1.05])
>>> plt.title('Spline with Specified Interior Knots')
>>> plt.show()
```



2-D spline representation: Procedural (`bisplrep`)

For (smooth) spline-fitting to a 2-D surface, the function `bisplrep` is available. This function takes as required inputs the **1-D** arrays `x`, `y`, and `z`, which represent points on the surface $z = f(x, y)$. The default output is a list `[tx, ty, c, kx, ky]` whose entries represent respectively, the components of the knot positions, the coefficients of the spline, and the order of the spline in each coordinate. It is convenient to hold this list in a single object, `tck`, so that it can be passed easily to the function `bisplev`. The keyword, `s`, can be used to change the amount of smoothing performed on the data while determining the appropriate spline. The default value is $s = m - \sqrt{2m}$, where m is the number of data points in the `x`, `y`, and `z` vectors. As a result, if no smoothing is desired, then $s = 0$ should be passed to `bisplrep`.

To evaluate the 2-D spline and its partial derivatives (up to the order of the spline), the function `bisplev` is required. This function takes as the first two arguments **two 1-D arrays** whose cross-product specifies the domain over which to evaluate the spline. The third argument is the `tck` list returned from `bisplrep`. If desired, the fourth and fifth arguments provide the orders of the partial derivative in the `x` and `y` direction, respectively.

It is important to note that 2-D interpolation should not be used to find the spline representation of images. The algorithm used is not amenable to large numbers of input points. The signal-processing toolbox contains more appropriate algorithms for finding the spline representation of an image. The 2-D interpolation commands are intended for use when interpolating a 2-D function as shown in the example that follows. This example uses the `mgrid` command in NumPy which is useful for defining a “mesh-grid” in many dimensions. (See also the `ogrid` command if the full-mesh is not needed). The number of output arguments and the number of dimensions of each argument is determined by the number of indexing objects passed in `mgrid`.

```
>>> import numpy as np
>>> from scipy import interpolate
>>> import matplotlib.pyplot as plt
```

Define function over a sparse 20x20 grid



```
>>> x_edges, y_edges = np.mgrid[-1:1:21j, -1:1:21j]
>>> x = x_edges[:-1, :-1] + np.diff(x_edges[:2, 0])[0] / 2.
>>> y = y_edges[:-1, :-1] + np.diff(y_edges[0, :2])[0] / 2.
>>> z = (x+y) * np.exp(-6.0*(x*x+y*y))
```

```
>>> plt.figure()
>>> lims = dict(cmap='RdBu_r', vmin=-0.25, vmax=0.25)
>>> plt.pcolormesh(x_edges, y_edges, z, shading='flat', **lims)
>>> plt.colorbar()
>>> plt.title("Sparsely sampled function.")
>>> plt.show()
```

Interpolate function over a new 70x70 grid

```
>>> xnew_edges, ynew_edges = np.mgrid[-1:1:71j, -1:1:71j]
>>> xnew = xnew_edges[:-1, :-1] + np.diff(xnew_edges[:2, 0])[0] / 2.
>>> ynew = ynew_edges[:-1, :-1] + np.diff(ynew_edges[0, :2])[0] / 2.
>>> tck = interpolate.bisplrep(x, y, z, s=0)
>>> znew = interpolate.bisplev(xnew[:,0], ynew[0,:], tck)
```

```
>>> plt.figure()
>>> plt.pcolormesh(xnew_edges, ynew_edges, znew, shading='flat', **lims)
>>> plt.colorbar()
>>> plt.title("Interpolated function.")
>>> plt.show()
```

2-D spline representation: Object-oriented (*BivariateSpline*)

The *BivariateSpline* class is the 2-D analog of the *UnivariateSpline* class. It and its subclasses implement the FITPACK functions described above in an object-oriented fashion, allowing objects to be instantiated that can be called to compute the spline value by passing in the two coordinates as the two arguments.

Using radial basis functions for smoothing/interpolation

Radial basis functions can be used for smoothing/interpolating scattered data in N dimensions, but should be used with caution for extrapolation outside of the observed data range.

1-D Example

This example compares the usage of the *Rbf* and *UnivariateSpline* classes from the `scipy.interpolate` module.

```
>>> import numpy as np
>>> from scipy.interpolate import Rbf, InterpolatedUnivariateSpline
>>> import matplotlib.pyplot as plt
```


```
>>> # setup data
>>> x = np.linspace(0, 10, 9)
>>> y = np.sin(x)
>>> xi = np.linspace(0, 10, 101)
```

```
>>> # use fitpack2 method
>>> ius = InterpolatedUnivariateSpline(x, y)
>>> yi = ius(xi)
```

```
>>> plt.subplot(2, 1, 1)
>>> plt.plot(x, y, 'bo')
>>> plt.plot(xi, yi, 'g')
>>> plt.plot(xi, np.sin(xi), 'r')
>>> plt.title('Interpolation using univariate spline')
```

```
>>> # use RBF method
>>> rbf = Rbf(x, y)
>>> fi = rbf(xi)
```

```
>>> plt.subplot(2, 1, 2)
>>> plt.plot(x, y, 'bo')
>>> plt.plot(xi, fi, 'g')
>>> plt.plot(xi, np.sin(xi), 'r')
>>> plt.title('Interpolation using RBF - multiquadrics')
>>> plt.show()
```



2-D Example


This example shows how to interpolate scattered 2-D data:

```
>>> import numpy as np
>>> from scipy.interpolate import Rbf
>>> import matplotlib.pyplot as plt
>>> from matplotlib import cm
```

```
>>> # 2-d tests - setup scattered data
>>> x = np.random.rand(100)*4.0-2.0
>>> y = np.random.rand(100)*4.0-2.0
>>> z = x*np.exp(-x**2-y**2)
>>> edges = np.linspace(-2.0, 2.0, 101)
>>> centers = edges[:-1] + np.diff(edges[:2])[0] / 2.
>>> XI, YI = np.meshgrid(centers, centers)
```

```
>>> # use RBF
>>> rbf = Rbf(x, y, z, epsilon=2)
>>> ZI = rbf(XI, YI)
```

```
>>> # plot the result
>>> plt.subplot(1, 1, 1)
>>> X_edges, Y_edges = np.meshgrid(edges, edges)
>>> lims = dict(cmap='RdBu_r', vmin=-0.4, vmax=0.4)
>>> plt.pcolormesh(X_edges, Y_edges, ZI, shading='flat', **lims)
>>> plt.scatter(x, y, 100, z, edgecolor='w', lw=0.1, **lims)
>>> plt.title('RBF interpolation - multiquadrics')
>>> plt.xlim(-2, 2)
>>> plt.ylim(-2, 2)
>>> plt.colorbar()
```



4.1.6 Fourier Transforms (`scipy.fft`)

Contents

- *Fourier Transforms* (`scipy.fft`)
 - *Fast Fourier transforms*
 - * *1-D discrete Fourier transforms*
 - * *2- and N-D discrete Fourier transforms*
 - *Discrete Cosine Transforms*
 - * *Type I DCT*
 - * *Type II DCT*
 - * *Type III DCT*
 - * *Type IV DCT*
 - * *DCT and IDCT*
 - * *Example*
 - *Discrete Sine Transforms*
 - * *Type I DST*
 - * *Type II DST*
 - * *Type III DST*
 - * *Type IV DST*
 - * *DST and IDST*
 - *References*

Fourier analysis is a method for expressing a function as a sum of periodic components, and for recovering the signal

from those components. When both the function and its Fourier transform are replaced with discretized counterparts, it is called the discrete Fourier transform (DFT). The DFT has become a mainstay of numerical computing in part because of a very fast algorithm for computing it, called the Fast Fourier Transform (FFT), which was known to Gauss (1805) and was brought to light in its current form by Cooley and Tukey [CT65]. Press et al. [NR07] provide an accessible introduction to Fourier analysis and its applications.

Fast Fourier transforms

1-D discrete Fourier transforms

The FFT $y[k]$ of length N of the length- N sequence $x[n]$ is defined as

$$y[k] = \sum_{n=0}^{N-1} e^{-2\pi j \frac{kn}{N}} x[n],$$

and the inverse transform is defined as follows

$$x[n] = \frac{1}{N} \sum_{k=0}^{N-1} e^{2\pi j \frac{kn}{N}} y[k].$$

These transforms can be calculated by means of `fft` and `ifft`, respectively, as shown in the following example.

```
>>> from scipy.fft import fft, ifft
>>> x = np.array([1.0, 2.0, 1.0, -1.0, 1.5])
>>> y = fft(x)
>>> y
array([ 4.5+0.j, 2.08155948-1.65109876j,
       -1.83155948+1.60822041j, -1.83155948-1.60822041j,
        2.08155948+1.65109876j])
>>> yinv = ifft(y)
>>> yinv
array([ 1.0+0.j, 2.0+0.j, 1.0+0.j, -1.0+0.j, 1.5+0.j])
```

From the definition of the FFT it can be seen that

$$y[0] = \sum_{n=0}^{N-1} x[n].$$

In the example

```
>>> np.sum(x)
4.5
```

which corresponds to $y[0]$. For N even, the elements $y[1]..y[N/2 - 1]$ contain the positive-frequency terms, and the elements $y[N/2]..y[N - 1]$ contain the negative-frequency terms, in order of decreasingly negative frequency. For N odd, the elements $y[1]..y[(N - 1)/2]$ contain the positive-frequency terms, and the elements $y[(N + 1)/2]..y[N - 1]$ contain the negative-frequency terms, in order of decreasingly negative frequency.


In case the sequence x is real-valued, the values of $y[n]$ for positive frequencies is the conjugate of the values $y[n]$ for negative frequencies (because the spectrum is symmetric). Typically, only the FFT corresponding to positive frequencies is plotted.

The example plots the FFT of the sum of two sines.

```

>>> from scipy.fft import fft, fftfreq
>>> # Number of sample points
>>> N = 600
>>> # sample spacing
>>> T = 1.0 / 800.0
>>> x = np.linspace(0.0, N*T, N, endpoint=False)
>>> y = np.sin(50.0 * 2.0*np.pi*x) + 0.5*np.sin(80.0 * 2.0*np.pi*x)
>>> yf = fft(y)
>>> xf = fftfreq(N, T)[:N//2]
>>> import matplotlib.pyplot as plt
>>> plt.plot(xf, 2.0/N * np.abs(yf[0:N//2]))
>>> plt.grid()
>>> plt.show()

```



The FFT input signal is inherently truncated. This truncation can be modeled as multiplication of an infinite signal with a rectangular window function. In the spectral domain this multiplication becomes convolution of the signal spectrum with the window function spectrum, being of form $\sin(x)/x$. This convolution is the cause of an effect called spectral leakage (see [WPW]). Windowing the signal with a dedicated window function helps mitigate spectral leakage. The example below uses a Blackman window from `scipy.signal` and shows the effect of windowing (the zero component of the FFT has been truncated for illustrative purposes).

```

>>> from scipy.fft import fft, fftfreq
>>> # Number of sample points
>>> N = 600
>>> # sample spacing
>>> T = 1.0 / 800.0
>>> x = np.linspace(0.0, N*T, N, endpoint=False)
>>> y = np.sin(50.0 * 2.0*np.pi*x) + 0.5*np.sin(80.0 * 2.0*np.pi*x)
>>> yf = fft(y)
>>> from scipy.signal import blackman
>>> w = blackman(N)
>>> ywf = fft(y*w)
>>> xf = fftfreq(N, T)[:N//2]

```


(continues on next page)

(continued from previous page)

```

>>> import matplotlib.pyplot as plt
>>> plt.semilogy(xf[1:N//2], 2.0/N * np.abs(yf[1:N//2]), '-b')
>>> plt.semilogy(xf[1:N//2], 2.0/N * np.abs(ywf[1:N//2]), '-r')
>>> plt.legend(['FFT', 'FFT w. window'])
>>> plt.grid()
>>> plt.show()

```



In case the sequence x is complex-valued, the spectrum is no longer symmetric. To simplify working with the FFT functions, `scipy` provides the following two helper functions.

The function `fftfreq` returns the FFT sample frequency points.

```

>>> from scipy.fft import fftfreq
>>> freq = fftfreq(8, 0.125)
>>> freq
array([ 0.,  1.,  2.,  3., -4., -3., -2., -1.])

```

In a similar spirit, the function `fftshift` allows swapping the lower and upper halves of a vector, so that it becomes suitable for display.

```

>>> from scipy.fft import fftshift
>>> x = np.arange(8)
>>> fftshift(x)
array([4, 5, 6, 7, 0, 1, 2, 3])

```

The example below plots the FFT of two complex exponentials; note the asymmetric spectrum.

```

>>> from scipy.fft import fft, fftfreq, fftshift
>>> # number of signal points
>>> N = 400
>>> # sample spacing
>>> T = 1.0 / 800.0
>>> x = np.linspace(0.0, N*T, N, endpoint=False)
>>> y = np.exp(50.0 * 1.j * 2.0*np.pi*x) + 0.5*np.exp(-80.0 * 1.j * 2.0*np.
↪pi*x)

```


(continues on next page)

(continued from previous page)

```

>>> yf = fft(y)
>>> xf = fftfreq(N, T)
>>> xf = fftshift(xf)
>>> yplot = fftshift(yf)
>>> import matplotlib.pyplot as plt
>>> plt.plot(xf, 1.0/N * np.abs(yplot))
>>> plt.grid()
>>> plt.show()

```



The function `rfft` calculates the FFT of a real sequence and outputs the complex FFT coefficients $y[n]$ for only half of the frequency range. The remaining negative frequency components are implied by the Hermitian symmetry of the FFT for a real input ($y[n] = \text{conj}(y[-n])$). In case of N being even: $[Re(y[0]) + 0j, y[1], \dots, Re(y[N/2]) + 0j]$; in case of N being odd $[Re(y[0]) + 0j, y[1], \dots, y[N/2]]$. The terms shown explicitly as $Re(y[k]) + 0j$ are restricted to be purely real since, by the hermitian property, they are their own complex conjugate.

The corresponding function `irfft` calculates the IFFT of the FFT coefficients with this special ordering.

```

>>> from scipy.fft import fft, rfft, irfft
>>> x = np.array([1.0, 2.0, 1.0, -1.0, 1.5, 1.0])
>>> fft(x)
array([ 5.5 +0.j          ,  2.25-0.4330127j , -2.75-1.29903811j,
        1.5 +0.j          , -2.75+1.29903811j,  2.25+0.4330127j ])
>>> yr = rfft(x)
>>> yr
array([ 5.5 +0.j          ,  2.25-0.4330127j , -2.75-1.29903811j,
        1.5 +0.j          ])
>>> irfft(yr)
array([ 1. ,  2. ,  1. , -1. ,  1.5,  1. ])
>>> x = np.array([1.0, 2.0, 1.0, -1.0, 1.5])
>>> fft(x)
array([ 4.5          +0.j          ,  2.08155948-1.65109876j,
       -1.83155948+1.60822041j, -1.83155948-1.60822041j,
        2.08155948+1.65109876j])

```

(continues on next page)

(continued from previous page)

```
>>> yr = rfft(x)
>>> yr
array([ 4.5          +0.j          ,  2.08155948-1.65109876j,
       -1.83155948+1.60822041j])
```

Notice that the *rfft* of odd and even length signals are of the same shape. By default, *irfft* assumes the output signal should be of even length. And so, for odd signals, it will give the wrong result:

```
>>> irfft(yr)
array([ 1.70788987,  2.40843925, -0.37366961,  0.75734049])
```

To recover the original odd-length signal, we **must** pass the output shape by the *n* parameter.

```
>>> irfft(yr, n=len(x))
array([ 1. ,  2. ,  1. , -1. ,  1.5])
```


2- and N-D discrete Fourier transforms

The functions *fft2* and *ifft2* provide 2-D FFT and IFFT, respectively. Similarly, *fftn* and *ifftn* provide N-D FFT, and IFFT, respectively.

For real-input signals, similarly to *rfft*, we have the functions *rfft2* and *irfft2* for 2-D real transforms; *rfftn* and *irfftn* for N-D real transforms.

The example below demonstrates a 2-D IFFT and plots the resulting (2-D) time-domain signals.

```
>>> from scipy.fft import ifftn
>>> import matplotlib.pyplot as plt
>>> import matplotlib.cm as cm
>>> N = 30
>>> f, ((ax1, ax2, ax3), (ax4, ax5, ax6)) = plt.subplots(2, 3, sharex='col',
↳sharey='row')
>>> xf = np.zeros((N,N))
>>> xf[0, 5] = 1
>>> xf[0, N-5] = 1
>>> Z = ifftn(xf)
>>> ax1.imshow(xf, cmap=cm.Reds)
>>> ax4.imshow(np.real(Z), cmap=cm.gray)
>>> xf = np.zeros((N, N))
>>> xf[5, 0] = 1
>>> xf[N-5, 0] = 1
>>> Z = ifftn(xf)
>>> ax2.imshow(xf, cmap=cm.Reds)
>>> ax5.imshow(np.real(Z), cmap=cm.gray)
>>> xf = np.zeros((N, N))
>>> xf[5, 10] = 1
>>> xf[N-5, N-10] = 1
>>> Z = ifftn(xf)
>>> ax3.imshow(xf, cmap=cm.Reds)
>>> ax6.imshow(np.real(Z), cmap=cm.gray)
>>> plt.show()
```



Discrete Cosine Transforms

SciPy provides a DCT with the function `dct` and a corresponding IDCT with the function `idct`. There are 8 types of the DCT [WPC], [Mak]; however, only the first 4 types are implemented in scipy. “The” DCT generally refers to DCT type 2, and “the” Inverse DCT generally refers to DCT type 3. In addition, the DCT coefficients can be normalized differently (for most types, scipy provides `None` and `ortho`). Two parameters of the `dct/idct` function calls allow setting the DCT type and coefficient normalization.

For a single dimension array `x`, `dct(x, norm='ortho')` is equal to MATLAB `dct(x)`.

Type I DCT

SciPy uses the following definition of the unnormalized DCT-I (`norm=None`):

$$y[k] = x_0 + (-1)^k x_{N-1} + 2 \sum_{n=1}^{N-2} x[n] \cos\left(\frac{\pi nk}{N-1}\right), \quad 0 \leq k < N.$$

Note that the DCT-I is only supported for input size > 1 .

Type II DCT

SciPy uses the following definition of the unnormalized DCT-II (`norm=None`):

$$y[k] = 2 \sum_{n=0}^{N-1} x[n] \cos\left(\frac{\pi(2n+1)k}{2N}\right) \quad 0 \leq k < N.$$

In case of the normalized DCT (`norm='ortho'`), the DCT coefficients $y[k]$ are multiplied by a scaling factor f :

$$f = \begin{cases} \sqrt{1/(4N)}, & \text{if } k = 0 \\ \sqrt{1/(2N)}, & \text{otherwise} \end{cases}.$$

In this case, the DCT “base functions” $\phi_k[n] = 2f \cos\left(\frac{\pi(2n+1)k}{2N}\right)$ become orthonormal:

$$\sum_{n=0}^{N-1} \phi_k[n] \phi_l[n] = \delta_{lk}.$$

Type III DCT

SciPy uses the following definition of the unnormalized DCT-III (`norm=None`):

$$y[k] = x_0 + 2 \sum_{n=1}^{N-1} x[n] \cos\left(\frac{\pi n(2k+1)}{2N}\right) \quad 0 \leq k < N,$$

or, for `norm='ortho'`:

$$y[k] = \frac{x_0}{\sqrt{N}} + \frac{2}{\sqrt{N}} \sum_{n=1}^{N-1} x[n] \cos\left(\frac{\pi n(2k+1)}{2N}\right) \quad 0 \leq k < N.$$

Type IV DCT

SciPy uses the following definition of the unnormalized DCT-IV (`norm=None`):

$$y[k] = 2 \sum_{n=0}^{N-1} x[n] \cos\left(\frac{\pi(2n+1)(2k+1)}{4N}\right) \quad 0 \leq k < N,$$

or, for `norm='ortho'`:

$$y[k] = \sqrt{\frac{2}{N}} \sum_{n=0}^{N-1} x[n] \cos\left(\frac{\pi(2n+1)(2k+1)}{4N}\right) \quad 0 \leq k < N$$

DCT and IDCT

The (unnormalized) DCT-III is the inverse of the (unnormalized) DCT-II, up to a factor of $2N$. The orthonormalized DCT-III is exactly the inverse of the orthonormalized DCT-II. The function `idct` performs the mappings between the DCT and IDCT types, as well as the correct normalization.

The following example shows the relation between DCT and IDCT for different types and normalizations.

```
>>> from scipy.fft import dct, idct
>>> x = np.array([1.0, 2.0, 1.0, -1.0, 1.5])
```

The DCT-II and DCT-III are each other's inverses, so for an orthonormal transform we return back to the original signal.

```
>>> dct(dct(x, type=2, norm='ortho'), type=3, norm='ortho')
array([ 1. ,  2. ,  1. , -1. ,  1.5])
```

Doing the same under default normalization, however, we pick up an extra scaling factor of $2N = 10$ since the forward transform is unnormalized.

```
>>> dct(dct(x, type=2), type=3)
array([ 10.,  20.,  10., -10.,  15.])
```

For this reason, we should use the function `idct` using the same type for both, giving a correctly normalized result.

```
>>> # Normalized inverse: no scaling factor
>>> idct(dct(x, type=2), type=2)
array([ 1. ,  2. ,  1. , -1. ,  1.5])
```

Analogous results can be seen for the DCT-I, which is its own inverse up to a factor of $2(N-1)$.

```

>>> dct(dct(x, type=1, norm='ortho'), type=1, norm='ortho')
array([ 1. ,  2. ,  1. , -1. ,  1.5])
>>> # Unnormalized round-trip via DCT-I: scaling factor 2*(N-1) = 8
>>> dct(dct(x, type=1), type=1)
array([ 8. , 16.,  8. , -8. , 12.])
>>> # Normalized inverse: no scaling factor
>>> idct(dct(x, type=1), type=1)
array([ 1. ,  2. ,  1. , -1. ,  1.5])

```

And for the DCT-IV, which is also its own inverse up to a factor of $2N$.

```

>>> dct(dct(x, type=4, norm='ortho'), type=4, norm='ortho')
array([ 1. ,  2. ,  1. , -1. ,  1.5])
>>> # Unnormalized round-trip via DCT-IV: scaling factor 2*N = 10
>>> dct(dct(x, type=4), type=4)
array([ 10., 20., 10., -10., 15.])
>>> # Normalized inverse: no scaling factor
>>> idct(dct(x, type=4), type=4)
array([ 1. ,  2. ,  1. , -1. ,  1.5])

```

Example


The DCT exhibits the “energy compaction property”, meaning that for many signals only the first few DCT coefficients have significant magnitude. Zeroing out the other coefficients leads to a small reconstruction error, a fact which is exploited in lossy signal compression (e.g. JPEG compression).

The example below shows a signal x and two reconstructions (x_{20} and x_{15}) from the signal’s DCT coefficients. The signal x_{20} is reconstructed from the first 20 DCT coefficients, x_{15} is reconstructed from the first 15 DCT coefficients. It can be seen that the relative error of using 20 coefficients is still very small ($\sim 0.1\%$), but provides a five-fold compression rate.

```

>>> from scipy.fft import dct, idct
>>> import matplotlib.pyplot as plt
>>> N = 100
>>> t = np.linspace(0,20,N, endpoint=False)
>>> x = np.exp(-t/3)*np.cos(2*t)
>>> y = dct(x, norm='ortho')
>>> window = np.zeros(N)
>>> window[:20] = 1
>>> yr = idct(y*window, norm='ortho')
>>> sum(abs(x-yr)**2) / sum(abs(x)**2)
0.0009872817275276098
>>> plt.plot(t, x, '-bx')
>>> plt.plot(t, yr, 'ro')
>>> window = np.zeros(N)
>>> window[:15] = 1
>>> yr = idct(y*window, norm='ortho')
>>> sum(abs(x-yr)**2) / sum(abs(x)**2)
0.06196643004256714
>>> plt.plot(t, yr, 'g+')
>>> plt.legend(['x', '$x_{20}$', '$x_{15}$'])
>>> plt.grid()
>>> plt.show()

```



Discrete Sine Transforms

SciPy provides a DST [Mak] with the function `dst` and a corresponding IDST with the function `idst`.

There are, theoretically, 8 types of the DST for different combinations of even/odd boundary conditions and boundary offsets [WPS], only the first 4 types are implemented in scipy.

Type I DST

DST-I assumes the input is odd around $n=-1$ and $n=N$. SciPy uses the following definition of the unnormalized DST-I (`norm=None`):

$$y[k] = 2 \sum_{n=0}^{N-1} x[n] \sin\left(\frac{\pi(n+1)(k+1)}{N+1}\right), \quad 0 \leq k < N.$$

Note also that the DST-I is only supported for input size > 1 . The (unnormalized) DST-I is its own inverse, up to a factor of $2(N+1)$.

Type II DST

DST-II assumes the input is odd around $n=-1/2$ and even around $n=N$. SciPy uses the following definition of the unnormalized DST-II (`norm=None`):

$$y[k] = 2 \sum_{n=0}^{N-1} x[n] \sin\left(\frac{\pi(n+1/2)(k+1)}{N}\right), \quad 0 \leq k < N.$$

Type III DST

DST-III assumes the input is odd around $n=-1$ and even around $n=N-1$. SciPy uses the following definition of the unnormalized DST-III (`norm=None`):

$$y[k] = (-1)^k x[N-1] + 2 \sum_{n=0}^{N-2} x[n] \sin\left(\frac{\pi(n+1)(k+1/2)}{N}\right), \quad 0 \leq k < N.$$

Type IV DST

SciPy uses the following definition of the unnormalized DST-IV (`norm=None`):

$$y[k] = 2 \sum_{n=0}^{N-1} x[n] \sin\left(\frac{\pi(2n+1)(2k+1)}{4N}\right) \quad 0 \leq k < N,$$

or, for `norm='ortho'`:

$$y[k] = \sqrt{\frac{2}{N}} \sum_{n=0}^{N-1} x[n] \sin\left(\frac{\pi(2n+1)(2k+1)}{4N}\right) \quad 0 \leq k < N,$$

DST and IDST

The following example shows the relation between DST and IDST for different types and normalizations.

```
>>> from scipy.fft import dst, idst
>>> x = np.array([1.0, 2.0, 1.0, -1.0, 1.5])
```

The DST-II and DST-III are each other's inverses, so for an orthonormal transform we return back to the original signal.

```
>>> dst(dst(x, type=2, norm='ortho'), type=3, norm='ortho')
array([ 1. ,  2. ,  1. , -1. ,  1.5])
```

Doing the same under default normalization, however, we pick up an extra scaling factor of $2N = 10$ since the forward transform is unnormalized.

```
>>> dst(dst(x, type=2), type=3)
array([ 10.,  20.,  10., -10.,  15.])
```

For this reason, we should use the function `idst` using the same type for both, giving a correctly normalized result.

```
>>> idst(dst(x, type=2), type=2)
array([ 1. ,  2. ,  1. , -1. ,  1.5])
```

Analogous results can be seen for the DST-I, which is its own inverse up to a factor of $2(N-1)$.

```
>>> dst(dst(x, type=1, norm='ortho'), type=1, norm='ortho')
array([ 1. ,  2. ,  1. , -1. ,  1.5])
>>> # scaling factor 2*(N+1) = 12
>>> dst(dst(x, type=1), type=1)
array([ 12.,  24.,  12., -12.,  18.])
>>> # no scaling factor
>>> idst(dst(x, type=1), type=1)
array([ 1. ,  2. ,  1. , -1. ,  1.5])
```

And for the DST-IV, which is also its own inverse up to a factor of $2N$.

```
>>> dst(dst(x, type=4, norm='ortho'), type=4, norm='ortho')
array([ 1. ,  2. ,  1. , -1. ,  1.5])
>>> # scaling factor 2*N = 10
>>> dst(dst(x, type=4), type=4)
array([ 10.,  20.,  10., -10.,  15.])
>>> # no scaling factor
>>> idst(dst(x, type=4), type=4)
array([ 1. ,  2. ,  1. , -1. ,  1.5])
```

References

4.1.7 Signal Processing (`scipy.signal`)

The signal processing toolbox currently contains some filtering functions, a limited set of filter design tools, and a few B-spline interpolation algorithms for 1- and 2-D data. While the B-spline algorithms could technically be placed under the interpolation category, they are included here because they only work with equally-spaced data and make heavy use of filter-theory and transfer-function formalism to provide a fast B-spline transform. To understand this section, you will need to understand that a signal in SciPy is an array of real or complex numbers.

B-splines

A B-spline is an approximation of a continuous function over a finite- domain in terms of B-spline coefficients and knot points. If the knot- points are equally spaced with spacing Δx , then the B-spline approximation to a 1-D function is the finite-basis expansion.

$$y(x) \approx \sum_j c_j \beta^o \left(\frac{x}{\Delta x} - j \right).$$

In two dimensions with knot-spacing Δx and Δy , the function representation is

$$z(x, y) \approx \sum_j \sum_k c_{jk} \beta^o \left(\frac{x}{\Delta x} - j \right) \beta^o \left(\frac{y}{\Delta y} - k \right).$$

In these expressions, $\beta^o(\cdot)$ is the space-limited B-spline basis function of order o . The requirement of equally-spaced knot-points and equally-spaced data points, allows the development of fast (inverse-filtering) algorithms for determining the coefficients, c_j , from sample-values, y_n . Unlike the general spline interpolation algorithms, these algorithms can quickly find the spline coefficients for large images.

The advantage of representing a set of samples via B-spline basis functions is that continuous-domain operators (derivatives, re- sampling, integral, etc.), which assume that the data samples are drawn from an underlying continuous function, can be computed with relative ease from the spline coefficients. For example, the second derivative of a spline is

$$y''(x) = \frac{1}{\Delta x^2} \sum_j c_j \beta^{o''} \left(\frac{x}{\Delta x} - j \right).$$

Using the property of B-splines that

$$\frac{d^2 \beta^o(w)}{dw^2} = \beta^{o-2}(w+1) - 2\beta^{o-2}(w) + \beta^{o-2}(w-1),$$

it can be seen that

$$y''(x) = \frac{1}{\Delta x^2} \sum_j c_j \left[\beta^{o-2} \left(\frac{x}{\Delta x} - j + 1 \right) - 2\beta^{o-2} \left(\frac{x}{\Delta x} - j \right) + \beta^{o-2} \left(\frac{x}{\Delta x} - j - 1 \right) \right].$$

If $o = 3$, then at the sample points:

$$\begin{aligned} \Delta x^2 y'(x)|_{x=n\Delta x} &= \sum_j c_j \delta_{n-j+1} - 2c_j \delta_{n-j} + c_j \delta_{n-j-1}, \\ &= c_{n+1} - 2c_n + c_{n-1}. \end{aligned}$$

Thus, the second-derivative signal can be easily calculated from the spline fit. If desired, smoothing splines can be found to make the second derivative less sensitive to random errors.

The savvy reader will have already noticed that the data samples are related to the knot coefficients via a convolution operator, so that simple convolution with the sampled B-spline function recovers the original data from the spline coefficients. The output of convolutions can change depending on how the boundaries are handled (this becomes increasingly more important as the number of dimensions in the dataset increases). The algorithms relating to B-splines in the signal-processing subpackage assume mirror-symmetric boundary conditions. Thus, spline coefficients are computed based on that assumption, and data-samples can be recovered exactly from the spline coefficients by assuming them to be mirror-symmetric also.

Currently the package provides functions for determining second- and third- order cubic spline coefficients from equally-spaced samples in one and two dimensions (*qspline1d*, *qspline2d*, *cspline1d*, *cspline2d*). The package also supplies a function (*bspline*) for evaluating the B-spline basis function, $\beta^o(x)$ for arbitrary order and x . For large o , the B-spline basis function can be approximated well by a zero-mean Gaussian function with standard-deviation equal to $\sigma_o = (o + 1)/12$:

$$\beta^o(x) \approx \frac{1}{\sqrt{2\pi\sigma_o^2}} \exp\left(-\frac{x^2}{2\sigma_o}\right).$$

A function to compute this Gaussian for arbitrary x and o is also available (*gauss_spline*). The following code and figure use spline-filtering to compute an edge-image (the second derivative of a smoothed spline) of a raccoon's face, which is an array returned by the command *scipy.misc.face*. The command *sepfir2d* was used to apply a separable 2-D FIR filter with mirror-symmetric boundary conditions to the spline coefficients. This function is ideally-suited for reconstructing samples from spline coefficients and is faster than *convolve2d*, which convolves arbitrary 2-D filters and allows for choosing mirror-symmetric boundary conditions.

```
>>> import numpy as np
>>> from scipy import signal, misc
>>> import matplotlib.pyplot as plt
```



```
>>> image = misc.face(gray=True).astype(np.float32)
>>> derfilt = np.array([1.0, -2, 1.0], dtype=np.float32)
>>> ck = signal.cspline2d(image, 8.0)
>>> deriv = (signal.sepfir2d(ck, derfilt, [1]) +
...         signal.sepfir2d(ck, [1], derfilt))
```

Alternatively, we could have done:

```
laplacian = np.array([[0,1,0], [1,-4,1], [0,1,0]], dtype=np.float32)
deriv2 = signal.convolve2d(ck, laplacian, mode='same', boundary='symm')
```

```
>>> plt.figure()
>>> plt.imshow(image)
>>> plt.gray()
>>> plt.title('Original image')
>>> plt.show()
```

```
>>> plt.figure()
>>> plt.imshow(deriv)
>>> plt.gray()
>>> plt.title('Output of spline edge filter')
>>> plt.show()
```

Filtering

Filtering is a generic name for any system that modifies an input signal in some way. In SciPy, a signal can be thought of as a NumPy array. There are different kinds of filters for different kinds of operations. There are two broad kinds of filtering operations: linear and non-linear. Linear filters can always be reduced to multiplication of the flattened NumPy array by an appropriate matrix resulting in another flattened NumPy array. Of course, this is not usually the best way to compute the filter, as the matrices and vectors involved may be huge. For example, filtering a 512×512 image with this method would require multiplication of a $512^2 \times 512^2$ matrix with a 512^2 vector. Just trying to store the $512^2 \times 512^2$ matrix using a standard NumPy array would require 68,719,476,736 elements. At 4 bytes per element this would require 256GB of memory. In most applications, most of the elements of this matrix are zero and a different method for computing the output of the filter is employed.

Convolution/Correlation

Many linear filters also have the property of shift-invariance. This means that the filtering operation is the same at different locations in the signal and it implies that the filtering matrix can be constructed from knowledge of one row (or column) of the matrix alone. In this case, the matrix multiplication can be accomplished using Fourier transforms.

Let $x[n]$ define a 1-D signal indexed by the integer n . Full convolution of two 1-D signals can be expressed as

$$y[n] = \sum_{k=-\infty}^{\infty} x[k] h[n-k].$$

This equation can only be implemented directly if we limit the sequences to finite-support sequences that can be stored in a computer, choose $n = 0$ to be the starting point of both sequences, let $K + 1$ be that value for which $x[n] = 0$ for all $n \geq K + 1$ and $M + 1$ be that value for which $h[n] = 0$ for all $n \geq M + 1$, then the discrete convolution expression is

$$y[n] = \sum_{k=\max(n-M,0)}^{\min(n,K)} x[k] h[n-k].$$

For convenience, assume $K \geq M$. Then, more explicitly, the output of this operation is

$$\begin{aligned} y[0] &= x[0] h[0] \\ y[1] &= x[0] h[1] + x[1] h[0] \\ y[2] &= x[0] h[2] + x[1] h[1] + x[2] h[0] \\ &\vdots \\ y[M] &= x[0] h[M] + x[1] h[M-1] + \dots + x[M] h[0] \\ y[M+1] &= x[1] h[M] + x[2] h[M-1] + \dots + x[M+1] h[0] \\ &\vdots \\ y[K] &= x[K-M] h[M] + \dots + x[K] h[0] \\ y[K+1] &= x[K+1-M] h[M] + \dots + x[K] h[1] \\ &\vdots \\ y[K+M-1] &= x[K-1] h[M] + x[K] h[M-1] \\ y[K+M] &= x[K] h[M]. \end{aligned}$$

Thus, the full discrete convolution of two finite sequences of lengths $K + 1$ and $M + 1$, respectively, results in a finite sequence of length $K + M + 1 = (K + 1) + (M + 1) - 1$.

1-D convolution is implemented in SciPy with the function `convolve`. This function takes as inputs the signals x , h , and two optional flags ‘mode’ and ‘method’, and returns the signal y .

The first optional flag, ‘mode’, allows for the specification of which part of the output signal to return. The default value of ‘full’ returns the entire signal. If the flag has a value of ‘same’, then only the middle K values are returned, starting at

$y \lfloor \lfloor \frac{M-1}{2} \rfloor \rfloor$, so that the output has the same length as the first input. If the flag has a value of 'valid', then only the middle $K - M + 1 = (K + 1) - (M + 1) + 1$ output values are returned, where z depends on all of the values of the smallest input from $h[0]$ to $h[M]$. In other words, only the values $y[M]$ to $y[K]$ inclusive are returned.

The second optional flag, 'method', determines how the convolution is computed, either through the Fourier transform approach with `fftconvolve` or through the direct method. By default, it selects the expected faster method. The Fourier transform method has order $O(N \log N)$, while the direct method has order $O(N^2)$. Depending on the big O constant and the value of N , one of these two methods may be faster. The default value, 'auto', performs a rough calculation and chooses the expected faster method, while the values 'direct' and 'fft' force computation with the other two methods.

The code below shows a simple example for convolution of 2 sequences:

```
>>> x = np.array([1.0, 2.0, 3.0])
>>> h = np.array([0.0, 1.0, 0.0, 0.0, 0.0])
>>> signal.convolve(x, h)
array([ 0.,  1.,  2.,  3.,  0.,  0.,  0.])
>>> signal.convolve(x, h, 'same')
array([ 2.,  3.,  0.])
```

This same function `convolve` can actually take N-D arrays as inputs and will return the N-D convolution of the two arrays, as is shown in the code example below. The same input flags are available for that case as well.

```
>>> x = np.array([[1., 1., 0., 0.], [1., 1., 0., 0.], [0., 0., 0., 0.], [0., 0., 0., 0.]])
>>> h = np.array([[1., 0., 0., 0.], [0., 0., 0., 0.], [0., 0., 1., 0.], [0., 0., 0., 0.]])
>>> signal.convolve(x, h)
array([[ 1.,  1.,  0.,  0.,  0.,  0.,  0.],
       [ 1.,  1.,  0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  1.,  1.,  0.,  0.,  0.],
       [ 0.,  0.,  1.,  1.,  0.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.,  0.,  0.]])
```

Correlation is very similar to convolution except that the minus sign becomes a plus sign. Thus,

$$w[n] = \sum_{k=-\infty}^{\infty} y[k] x[n+k],$$

is the (cross) correlation of the signals y and x . For finite-length signals with $y[n] = 0$ outside of the range $[0, K]$ and $x[n] = 0$ outside of the range $[0, M]$, the summation can simplify to

$$w[n] = \sum_{k=\max(0, -n)}^{\min(K, M-n)} y[k] x[n+k].$$

Assuming again that $K \geq M$, this is

$$\begin{aligned}
 w[-K] &= y[K] x[0] \\
 w[-K+1] &= y[K-1] x[0] + y[K] x[1] \\
 &\vdots \\
 w[M-K] &= y[K-M] x[0] + y[K-M+1] x[1] + \cdots + y[K] x[M] \\
 w[M-K+1] &= y[K-M-1] x[0] + \cdots + y[K-1] x[M] \\
 &\vdots \\
 w[-1] &= y[1] x[0] + y[2] x[1] + \cdots + y[M+1] x[M] \\
 w[0] &= y[0] x[0] + y[1] x[1] + \cdots + y[M] x[M] \\
 w[1] &= y[0] x[1] + y[1] x[2] + \cdots + y[M-1] x[M] \\
 w[2] &= y[0] x[2] + y[1] x[3] + \cdots + y[M-2] x[M] \\
 &\vdots \\
 w[M-1] &= y[0] x[M-1] + y[1] x[M] \\
 w[M] &= y[0] x[M].
 \end{aligned}$$

The SciPy function `correlate` implements this operation. Equivalent flags are available for this operation to return the full $K + M + 1$ length sequence ('full') or a sequence with the same size as the largest sequence starting at $w[-K + \lfloor \frac{M-1}{2} \rfloor]$ ('same') or a sequence where the values depend on all the values of the smallest sequence ('valid'). This final option returns the $K - M + 1$ values $w[M - K]$ to $w[0]$ inclusive.

The function `correlate` can also take arbitrary N-D arrays as input and return the N-D convolution of the two arrays on output.

When $N = 2$, `correlate` and/or `convolve` can be used to construct arbitrary image filters to perform actions such as blurring, enhancing, and edge-detection for an image.



```
>>> import numpy as np
>>> from scipy import signal, misc
>>> import matplotlib.pyplot as plt
```

```
>>> image = misc.face(gray=True)
>>> w = np.zeros((50, 50))
>>> w[0][0] = 1.0
>>> w[49][25] = 1.0
>>> image_new = signal.fftconvolve(image, w)
```

```
>>> plt.figure()
>>> plt.imshow(image)
>>> plt.gray()
>>> plt.title('Original image')
>>> plt.show()
```

```
>>> plt.figure()
>>> plt.imshow(image_new)
>>> plt.gray()
>>> plt.title('Filtered image')
>>> plt.show()
```

Calculating the convolution in the time domain as above is mainly used for filtering when one of the signals is much smaller



than the other ($K \gg M$), otherwise linear filtering is more efficiently calculated in the frequency domain provided by the function `fftconvolve`. By default, `convolve` estimates the fastest method using `choose_conv_method`.

If the filter function $w[n, m]$ can be factored according to

$$h[n, m] = h_1[n]h_2[m],$$

convolution can be calculated by means of the function `sepfir2d`. As an example, we consider a Gaussian filter gaussian


$$h[n, m] \propto e^{-x^2-y^2} = e^{-x^2} e^{-y^2},$$

which is often used for blurring.


```
>>> import numpy as np
>>> from scipy import signal, misc
>>> import matplotlib.pyplot as plt
```

```
>>> image = misc.ascent()
>>> w = signal.windows.gaussian(51, 10.0)
>>> image_new = signal.sepfir2d(image, w, w)
```

```
>>> plt.figure()
>>> plt.imshow(image)
>>> plt.gray()
>>> plt.title('Original image')
>>> plt.show()
```



```
>>> plt.figure()
>>> plt.imshow(image_new)
>>> plt.gray()
>>> plt.title('Filtered image')
>>> plt.show()
```



Difference-equation filtering

A general class of linear 1-D filters (that includes convolution filters) are filters described by the difference equation

$$\sum_{k=0}^N a_k y[n-k] = \sum_{k=0}^M b_k x[n-k],$$

where $x[n]$ is the input sequence and $y[n]$ is the output sequence. If we assume initial rest so that $y[n] = 0$ for $n < 0$, then this kind of filter can be implemented using convolution. However, the convolution filter sequence $h[n]$ could be infinite if $a_k \neq 0$ for $k \geq 1$. In addition, this general class of linear filter allows initial conditions to be placed on $y[n]$ for $n < 0$ resulting in a filter that cannot be expressed using convolution.

The difference equation filter can be thought of as finding $y[n]$ recursively in terms of its previous values

$$a_0 y[n] = -a_1 y[n-1] - \dots - a_N y[n-N] + \dots + b_0 x[n] + \dots + b_M x[n-M].$$

Often, $a_0 = 1$ is chosen for normalization. The implementation in SciPy of this general difference equation filter is a little more complicated than would be implied by the previous equation. It is implemented so that only one signal needs to be delayed. The actual implementation equations are (assuming $a_0 = 1$):

$$\begin{aligned} y[n] &= b_0 x[n] + z_0[n-1] \\ z_0[n] &= b_1 x[n] + z_1[n-1] - a_1 y[n] \\ z_1[n] &= b_2 x[n] + z_2[n-1] - a_2 y[n] \\ &\vdots \\ z_{K-2}[n] &= b_{K-1} x[n] + z_{K-1}[n-1] - a_{K-1} y[n] \\ z_{K-1}[n] &= b_K x[n] - a_K y[n], \end{aligned}$$

where $K = \max(N, M)$. Note that $b_K = 0$ if $K > M$ and $a_K = 0$ if $K > N$. In this way, the output at time n depends only on the input at time n and the value of z_0 at the previous time. This can always be calculated as long as the K values $z_0[n-1] \dots z_{K-1}[n-1]$ are computed and stored at each time step.

The difference-equation filter is called using the command `lfilter` in SciPy. This command takes as inputs the vector b , the vector a , a signal x and returns the vector y (the same length as x) computed using the equation given above. If x is N-D, then the filter is computed along the axis provided. If desired, initial conditions providing the values of $z_0[-1]$ to $z_{K-1}[-1]$ can be provided or else it will be assumed that they are all zero. If initial conditions are provided, then the final

conditions on the intermediate variables are also returned. These could be used, for example, to restart the calculation in the same state.

Sometimes, it is more convenient to express the initial conditions in terms of the signals $x[n]$ and $y[n]$. In other words, perhaps you have the values of $x[-M]$ to $x[-1]$ and the values of $y[-N]$ to $y[-1]$ and would like to determine what values of $z_m[-1]$ should be delivered as initial conditions to the difference-equation filter. It is not difficult to show that, for $0 \leq m < K$,

$$z_m[n] = \sum_{p=0}^{K-m-1} (b_{m+p+1}x[n-p] - a_{m+p+1}y[n-p]).$$

Using this formula, we can find the initial-condition vector $z_0[-1]$ to $z_{K-1}[-1]$ given initial conditions on y (and x). The command `lfiltic` performs this function.

As an example, consider the following system:

$$y[n] = \frac{1}{2}x[n] + \frac{1}{4}x[n-1] + \frac{1}{3}y[n-1]$$

The code calculates the signal $y[n]$ for a given signal $x[n]$; first for initial conditions $y[-1] = 0$ (default case), then for $y[-1] = 2$ by means of `lfiltic`.

```
>>> import numpy as np
>>> from scipy import signal
```

```
>>> x = np.array([1., 0., 0., 0.])
>>> b = np.array([1.0/2, 1.0/4])
>>> a = np.array([1.0, -1.0/3])
>>> signal.lfilter(b, a, x)
array([0.5, 0.41666667, 0.13888889, 0.0462963])
>>> zi = signal.lfiltic(b, a, y=[2.])
>>> signal.lfilter(b, a, x, zi=zi)
(array([ 1.16666667,  0.63888889,  0.21296296,  0.07098765]), array([0.
↪02366]))
```

Note that the output signal $y[n]$ has the same length as the length as the input signal $x[n]$.

Analysis of Linear Systems

Linear system described a linear-difference equation can be fully described by the coefficient vectors a and b as was done above; an alternative representation is to provide a factor k , N_z zeros z_k and N_p poles p_k , respectively, to describe the system by means of its transfer function $H(z)$, according to

$$H(z) = k \frac{(z - z_1)(z - z_2)\dots(z - z_{N_z})}{(z - p_1)(z - p_2)\dots(z - p_{N_p})}.$$

This alternative representation can be obtained with the scipy function `tf2zpk`; the inverse is provided by `zpk2tf`.

For the above example we have

```
>>> b = np.array([1.0/2, 1.0/4])
>>> a = np.array([1.0, -1.0/3])
>>> signal.tf2zpk(b, a)
(array([-0.5]), array([ 0.33333333]), 0.5)
```


i.e., the system has a zero at $z = -1/2$ and a pole at $z = 1/3$.

The scipy function `freqz` allows calculation of the frequency response of a system described by the coefficients a_k and b_k . See the help of the `freqz` function for a comprehensive example.

Filter Design

Time-discrete filters can be classified into finite response (FIR) filters and infinite response (IIR) filters. FIR filters can provide a linear phase response, whereas IIR filters cannot. SciPy provides functions for designing both types of filters.

FIR Filter


The function `firwin` designs filters according to the window method. Depending on the provided arguments, the function returns different filter types (e.g., low-pass, band-pass...).

The example below designs a low-pass and a band-stop filter, respectively.

```
>>> import numpy as np
>>> import scipy.signal as signal
>>> import matplotlib.pyplot as plt
```

```
>>> b1 = signal.firwin(40, 0.5)
>>> b2 = signal.firwin(41, [0.3, 0.8])
>>> w1, h1 = signal.freqz(b1)
>>> w2, h2 = signal.freqz(b2)
```

```
>>> plt.title('Digital filter frequency response')
>>> plt.plot(w1, 20*np.log10(np.abs(h1)), 'b')
>>> plt.plot(w2, 20*np.log10(np.abs(h2)), 'r')
>>> plt.ylabel('Amplitude Response (dB)')
>>> plt.xlabel('Frequency (rad/sample)')
>>> plt.grid()
>>> plt.show()
```



Note that `firwin` uses, per default, a normalized frequency defined such that the value 1 corresponds to the Nyquist frequency, whereas the function `freqz` is defined such that the value π corresponds to the Nyquist frequency.


The function `firwin2` allows design of almost arbitrary frequency responses by specifying an array of corner frequencies and corresponding gains, respectively.

The example below designs a filter with such an arbitrary amplitude response.

```
>>> import numpy as np
>>> import scipy.signal as signal
>>> import matplotlib.pyplot as plt
```

```
>>> b = signal.firwin2(150, [0.0, 0.3, 0.6, 1.0], [1.0, 2.0, 0.5, 0.0])
>>> w, h = signal.freqz(b)
```

```
>>> plt.title('Digital filter frequency response')
>>> plt.plot(w, np.abs(h))
>>> plt.title('Digital filter frequency response')
>>> plt.ylabel('Amplitude Response')
>>> plt.xlabel('Frequency (rad/sample)')
>>> plt.grid()
>>> plt.show()
```



Note the linear scaling of the y-axis and the different definition of the Nyquist frequency in `firwin2` and `freqz` (as explained above).

IIR Filter


SciPy provides two functions to directly design IIR *iirdesign* and *iirfilter*, where the filter type (e.g., elliptic) is passed as an argument and several more filter design functions for specific filter types, e.g., *ellip*.

The example below designs an elliptic low-pass filter with defined pass-band and stop-band ripple, respectively. Note the much lower filter order (order 4) compared with the FIR filters from the examples above in order to reach the same stop-band attenuation of ≈ 60 dB.

```
>>> import numpy as np
>>> import scipy.signal as signal
>>> import matplotlib.pyplot as plt
```

```
>>> b, a = signal.iirfilter(4, Wn=0.2, rp=5, rs=60, btype='lowpass', ftype=
↳'ellip')
>>> w, h = signal.freqz(b, a)
```

```
>>> plt.title('Digital filter frequency response')
>>> plt.plot(w, 20*np.log10(np.abs(h)))
>>> plt.title('Digital filter frequency response')
>>> plt.ylabel('Amplitude Response [dB]')
>>> plt.xlabel('Frequency (rad/sample)')
>>> plt.grid()
>>> plt.show()
```



Filter Coefficients

Filter coefficients can be stored in several different formats:

- ‘ba’ or ‘tf’ = transfer function coefficients
- ‘zpk’ = zeros, poles, and overall gain
- ‘ss’ = state-space system representation
- ‘sos’ = transfer function coefficients of second-order sections

Functions, such as `tf2zpk` and `zpk2ss`, can convert between them.

Transfer function representation

The `ba` or `tf` format is a 2-tuple (b, a) representing a transfer function, where b is a length $M+1$ array of coefficients of the M -order numerator polynomial, and a is a length $N+1$ array of coefficients of the N -order denominator, as positive, descending powers of the transfer function variable. So the tuple of $b = [b_0, b_1, \dots, b_M]$ and $a = [a_0, a_1, \dots, a_N]$ can represent an analog filter of the form:

$$H(s) = \frac{b_0 s^M + b_1 s^{(M-1)} + \dots + b_M}{a_0 s^N + a_1 s^{(N-1)} + \dots + a_N} = \frac{\sum_{i=0}^M b_i s^{(M-i)}}{\sum_{i=0}^N a_i s^{(N-i)}}$$

or a discrete-time filter of the form:

$$H(z) = \frac{b_0 z^M + b_1 z^{(M-1)} + \dots + b_M}{a_0 z^N + a_1 z^{(N-1)} + \dots + a_N} = \frac{\sum_{i=0}^M b_i z^{(M-i)}}{\sum_{i=0}^N a_i z^{(N-i)}}$$

This “positive powers” form is found more commonly in controls engineering. If M and N are equal (which is true for all filters generated by the bilinear transform), then this happens to be equivalent to the “negative powers” discrete-time form preferred in DSP:

$$H(z) = \frac{b_0 + b_1 z^{-1} + \dots + b_M z^{-M}}{a_0 + a_1 z^{-1} + \dots + a_N z^{-N}} = \frac{\sum_{i=0}^M b_i z^{-i}}{\sum_{i=0}^N a_i z^{-i}}$$

Although this is true for common filters, remember that this is not true in the general case. If M and N are not equal, the discrete-time transfer function coefficients must first be converted to the “positive powers” form before finding the poles and zeros.

This representation suffers from numerical error at higher orders, so other formats are preferred when possible.

Zeros and poles representation

The `zpk` format is a 3-tuple (z, p, k) , where z is an M -length array of the complex zeros of the transfer function $z = [z_0, z_1, \dots, z_{M-1}]$, p is an N -length array of the complex poles of the transfer function $p = [p_0, p_1, \dots, p_{N-1}]$, and k is a scalar gain. These represent the digital transfer function:

$$H(z) = k \cdot \frac{(z - z_0)(z - z_1) \cdots (z - z_{(M-1)})}{(z - p_0)(z - p_1) \cdots (z - p_{(N-1)})} = k \frac{\prod_{i=0}^{M-1} (z - z_i)}{\prod_{i=0}^{N-1} (z - p_i)}$$

or the analog transfer function:

$$H(s) = k \cdot \frac{(s - z_0)(s - z_1) \cdots (s - z_{(M-1)})}{(s - p_0)(s - p_1) \cdots (s - p_{(N-1)})} = k \frac{\prod_{i=0}^{M-1} (s - z_i)}{\prod_{i=0}^{N-1} (s - p_i)}$$

Although the sets of roots are stored as ordered NumPy arrays, their ordering does not matter: $([-1, -2], [-3, -4], 1)$ is the same filter as $([-2, -1], [-4, -3], 1)$.

State-space system representation

The `ss` format is a 4-tuple of arrays (A , B , C , D) representing the state-space of an N -order digital/discrete-time system of the form:

$$\begin{aligned}\mathbf{x}[k+1] &= A\mathbf{x}[k] + B\mathbf{u}[k] \\ \mathbf{y}[k] &= C\mathbf{x}[k] + D\mathbf{u}[k]\end{aligned}$$

or a continuous/analog system of the form:

$$\begin{aligned}\dot{\mathbf{x}}(t) &= A\mathbf{x}(t) + B\mathbf{u}(t) \\ \mathbf{y}(t) &= C\mathbf{x}(t) + D\mathbf{u}(t),\end{aligned}$$

with P inputs, Q outputs and N state variables, where:

- x is the state vector
- y is the output vector of length Q
- u is the input vector of length P
- A is the state matrix, with shape (N, N)
- B is the input matrix with shape (N, P)
- C is the output matrix with shape (Q, N)
- D is the feedthrough or feedforward matrix with shape (Q, P) . (In cases where the system does not have a direct feedthrough, all values in D are zero.)

State-space is the most general representation and the only one that allows for multiple-input, multiple-output (MIMO) systems. There are multiple state-space representations for a given transfer function. Specifically, the “controllable canonical form” and “observable canonical form” have the same coefficients as the `tf` representation, and, therefore, suffer from the same numerical errors.

Second-order sections representation

The `sos` format is a single 2-D array of shape $(n_sections, 6)$, representing a sequence of second-order transfer functions which, when cascaded in series, realize a higher-order filter with minimal numerical error. Each row corresponds to a second-order `tf` representation, with the first three columns providing the numerator coefficients and the last three providing the denominator coefficients:

$$[b_0, b_1, b_2, a_0, a_1, a_2]$$

The coefficients are typically normalized, such that a_0 is always 1. The section order is usually not important with floating-point computation; the filter output will be the same, regardless of the order.

Filter transformations

The IIR filter design functions first generate a prototype analog low-pass filter with a normalized cutoff frequency of 1 rad/sec. This is then transformed into other frequencies and band types using the following substitutions:

Type	Transformation
<code>lp2lp</code>	$s \rightarrow \frac{s}{\omega_0}$
<code>lp2hp</code>	$s \rightarrow \frac{\omega_0}{s}$
<code>lp2bp</code>	$s \rightarrow \frac{s^2 + \omega_0^2}{s \cdot BW}$
<code>lp2bs</code>	$s \rightarrow \frac{s \cdot BW}{s^2 + \omega_0^2}$

Here, ω_0 is the new cutoff or center frequency, and BW is the bandwidth. These preserve symmetry on a logarithmic frequency axis.

To convert the transformed analog filter into a digital filter, the *bilinear* transform is used, which makes the following substitution:

$$s \rightarrow \frac{2}{T} \frac{z - 1}{z + 1},$$

where T is the sampling time (the inverse of the sampling frequency).

Other filters

The signal processing package provides many more filters as well.

Median Filter

A median filter is commonly applied when noise is markedly non-Gaussian or when it is desired to preserve edges. The median filter works by sorting all of the array pixel values in a rectangular region surrounding the point of interest. The sample median of this list of neighborhood pixel values is used as the value for the output array. The sample median is the middle-array value in a sorted list of neighborhood values. If there are an even number of elements in the neighborhood, then the average of the middle two values is used as the median. A general purpose median filter that works on N-D arrays is *medfilt*. A specialized version that works only for 2-D arrays is available as *medfilt2d*.

Order Filter

A median filter is a specific example of a more general class of filters called order filters. To compute the output at a particular pixel, all order filters use the array values in a region surrounding that pixel. These array values are sorted and then one of them is selected as the output value. For the median filter, the sample median of the list of array values is used as the output. A general-order filter allows the user to select which of the sorted values will be used as the output. So, for example, one could choose to pick the maximum in the list or the minimum. The order filter takes an additional argument besides the input array and the region mask that specifies which of the elements in the sorted list of neighbor array values should be used as the output. The command to perform an order filter is *order_filter*.

Wiener filter

The Wiener filter is a simple deblurring filter for denoising images. This is not the Wiener filter commonly described in image-reconstruction problems but, instead, it is a simple, local-mean filter. Let x be the input signal, then the output is

$$y = \begin{cases} \frac{\sigma_x^2}{\sigma_x^2 + \sigma^2} m_x + \left(1 - \frac{\sigma_x^2}{\sigma_x^2 + \sigma^2}\right) x & \sigma_x^2 \geq \sigma^2, \\ m_x & \sigma_x^2 < \sigma^2, \end{cases}$$

where m_x is the local estimate of the mean and σ_x^2 is the local estimate of the variance. The window for these estimates is an optional input parameter (default is 3×3). The parameter σ^2 is a threshold noise parameter. If σ is not given, then it is estimated as the average of the local variances.

Hilbert filter

The Hilbert transform constructs the complex-valued analytic signal from a real signal. For example, if $x = \cos \omega n$, then $y = \text{hilbert}(x)$ would return (except near the edges) $y = \exp(j\omega n)$. In the frequency domain, the hilbert transform performs

$$Y = X \cdot H,$$

where H is 2 for positive frequencies, 0 for negative frequencies, and 1 for zero-frequencies.

Analog Filter Design


The functions `iirdesign`, `iirfilter`, and the filter design functions for specific filter types (e.g., `ellip`) all have a flag `analog`, which allows the design of analog filters as well.

The example below designs an analog (IIR) filter, obtains via `tf2zpk` the poles and zeros and plots them in the complex s-plane. The zeros at $\omega \approx 150$ and $\omega \approx 300$ can be clearly seen in the amplitude response.

```
>>> import numpy as np
>>> import scipy.signal as signal
>>> import matplotlib.pyplot as plt
```

```
>>> b, a = signal.iirdesign(wp=100, ws=200, gpass=2.0, gstop=40., analog=True)
>>> w, h = signal.freqs(b, a)
```


```
>>> plt.title('Analog filter frequency response')
>>> plt.plot(w, 20*np.log10(np.abs(h)))
>>> plt.ylabel('Amplitude Response [dB]')
>>> plt.xlabel('Frequency')
>>> plt.grid()
>>> plt.show()
```



```
>>> z, p, k = signal.tf2zpk(b, a)
```

```
>>> plt.plot(np.real(z), np.imag(z), 'xb')
>>> plt.plot(np.real(p), np.imag(p), 'or')
>>> plt.legend(['Zeros', 'Poles'], loc=2)
```

```
>>> plt.title('Pole / Zero Plot')
>>> plt.ylabel('Real')
>>> plt.xlabel('Imaginary')
>>> plt.grid()
>>> plt.show()
```



Spectral Analysis

Periodogram Measurements

The `scipy` function `periodogram` provides a method to estimate the spectral density using the periodogram method.

The example below calculates the periodogram of a sine signal in white Gaussian noise.


```
>>> import numpy as np
>>> import scipy.signal as signal
>>> import matplotlib.pyplot as plt
```

```
>>> fs = 10e3
>>> N = 1e5
>>> amp = 2*np.sqrt(2)
>>> freq = 1270.0
>>> noise_power = 0.001 * fs / 2
>>> time = np.arange(N) / fs
>>> x = amp*np.sin(2*np.pi*freq*time)
>>> x += np.random.normal(scale=np.sqrt(noise_power), size=time.shape)
```

```
>>> f, Pper_spec = signal.periodogram(x, fs, 'flattop', scaling='spectrum')
```



```
>>> plt.semilogy(f, Pper_spec)
>>> plt.xlabel('frequency [Hz]')
>>> plt.ylabel('PSD')
>>> plt.grid()
>>> plt.show()
```



Spectral Analysis using Welch's Method

An improved method, especially with respect to noise immunity, is Welch's method, which is implemented by the `scipy` function `welch`.


The example below estimates the spectrum using Welch's method and uses the same parameters as the example above. Note the much smoother noise floor of the spectrogram.

```
>>> import numpy as np
>>> import scipy.signal as signal
>>> import matplotlib.pyplot as plt
```

```
>>> fs = 10e3
>>> N = 1e5
>>> amp = 2*np.sqrt(2)
>>> freq = 1270.0
>>> noise_power = 0.001 * fs / 2
>>> time = np.arange(N) / fs
>>> x = amp*np.sin(2*np.pi*freq*time)
>>> x += np.random.normal(scale=np.sqrt(noise_power), size=time.shape)
```

```
>>> f, Pwelch_spec = signal.welch(x, fs, scaling='spectrum')
```

```
>>> plt.semilogy(f, Pwelch_spec)
>>> plt.xlabel('frequency [Hz]')
>>> plt.ylabel('PSD')
>>> plt.grid()
>>> plt.show()
```



Lomb-Scargle Periodograms (`lombscargle`)

Least-squares spectral analysis (LSSA)¹² is a method of estimating a frequency spectrum, based on a least-squares fit of sinusoids to data samples, similar to Fourier analysis. Fourier analysis, the most used spectral method in science, generally boosts long-periodic noise in long-gapped records; LSSA mitigates such problems.

The Lomb-Scargle method performs spectral analysis on unevenly-sampled data and is known to be a powerful way to find, and test the significance of, weak periodic signals.

For a time series comprising N_t measurements $X_j \equiv X(t_j)$ sampled at times t_j , where $(j = 1, \dots, N_t)$, assumed to have been scaled and shifted, such that its mean is zero and its variance is unity, the normalized Lomb-Scargle periodogram at frequency f is

$$P_n(f) \frac{1}{2} \left\{ \frac{\left[\sum_j^{N_t} X_j \cos \omega(t_j - \tau) \right]^2}{\sum_j^{N_t} \cos^2 \omega(t_j - \tau)} + \frac{\left[\sum_j^{N_t} X_j \sin \omega(t_j - \tau) \right]^2}{\sum_j^{N_t} \sin^2 \omega(t_j - \tau)} \right\}.$$

Here, $\omega \equiv 2\pi f$ is the angular frequency. The frequency-dependent time offset τ is given by

$$\tan 2\omega\tau = \frac{\sum_j^{N_t} \sin 2\omega t_j}{\sum_j^{N_t} \cos 2\omega t_j}.$$

The `lombscargle` function calculates the periodogram using a slightly modified algorithm due to Townsend³, which allows the periodogram to be calculated using only a single pass through the input arrays for each frequency.

The equation is refactored as:

$$P_n(f) = \frac{1}{2} \left[\frac{(c_\tau X C + s_\tau X S)^2}{c_\tau^2 C C + 2c_\tau s_\tau C S + s_\tau^2 S S} + \frac{(c_\tau X S - s_\tau X C)^2}{c_\tau^2 S S - 2c_\tau s_\tau C S + s_\tau^2 C C} \right]$$

and

$$\tan 2\omega\tau = \frac{2CS}{CC - SS}.$$

¹ N.R. Lomb “Least-squares frequency analysis of unequally spaced data”, *Astrophysics and Space Science*, vol 39, pp. 447-462, 1976

² J.D. Scargle “Studies in astronomical time series analysis. II - Statistical aspects of spectral analysis of unevenly spaced data”, *The Astrophysical Journal*, vol 263, pp. 835-853, 1982

³ R.H.D. Townsend, “Fast calculation of the Lomb-Scargle periodogram using graphics processing units.”, *The Astrophysical Journal Supplement Series*, vol 191, pp. 247-253, 2010

Here,

$$c_\tau = \cos \omega\tau, \quad s_\tau = \sin \omega\tau,$$

while the sums are

$$\begin{aligned} XC &= \sum_j^{N_t} X_j \cos \omega t_j \\ XS &= \sum_j^{N_t} X_j \sin \omega t_j \\ CC &= \sum_j^{N_t} \cos^2 \omega t_j \\ SS &= \sum_j^{N_t} \sin^2 \omega t_j \\ CS &= \sum_j^{N_t} \cos \omega t_j \sin \omega t_j. \end{aligned}$$

This requires $N_f(2N_t + 3)$ trigonometric function evaluations giving a factor of ~ 2 speed increase over the straightforward implementation.

Detrend


SciPy provides the function `detrend` to remove a constant or linear trend in a data series in order to see effect of higher order.

The example below removes the constant and linear trend of a second-order polynomial time series and plots the remaining signal components.

```
>>> import numpy as np
>>> import scipy.signal as signal
>>> import matplotlib.pyplot as plt
```

```
>>> t = np.linspace(-10, 10, 20)
>>> y = 1 + t + 0.01*t**2
>>> yconst = signal.detrend(y, type='constant')
>>> ylin = signal.detrend(y, type='linear')
```

```
>>> plt.plot(t, y, '-rx')
>>> plt.plot(t, yconst, '-bo')
>>> plt.plot(t, ylin, '-k+')
>>> plt.grid()
>>> plt.legend(['signal', 'const. detrend', 'linear detrend'])
>>> plt.show()
```



References

Some further reading and related software:

4.1.8 Linear Algebra (`scipy.linalg`)

When SciPy is built using the optimized ATLAS LAPACK and BLAS libraries, it has very fast linear algebra capabilities. If you dig deep enough, all of the raw LAPACK and BLAS libraries are available for your use for even more speed. In this section, some easier-to-use interfaces to these routines are described.

All of these linear algebra routines expect an object that can be converted into a 2-D array. The output of these routines is also a 2-D array.

`scipy.linalg` vs `numpy.linalg`

`scipy.linalg` contains all the functions in `numpy.linalg`, plus some other more advanced ones not contained in `numpy.linalg`.

Another advantage of using `scipy.linalg` over `numpy.linalg` is that it is always compiled with BLAS/LAPACK support, while for `numpy` this is optional. Therefore, the `scipy` version might be faster depending on how `numpy` was installed.

Therefore, unless you don't want to add `scipy` as a dependency to your `numpy` program, use `scipy.linalg` instead of `numpy.linalg`.

numpy.matrix vs 2-D numpy.ndarray

The classes that represent matrices, and basic operations, such as matrix multiplications and transpose are a part of `numpy`. For convenience, we summarize the differences between `numpy.matrix` and `numpy.ndarray` here.

`numpy.matrix` is matrix class that has a more convenient interface than `numpy.ndarray` for matrix operations. This class supports, for example, MATLAB-like creation syntax via the semicolon, has matrix multiplication as default for the `*` operator, and contains `I` and `T` members that serve as shortcuts for inverse and transpose:

```
>>> import numpy as np
>>> A = np.mat(' [1 2; 3 4] ')
>>> A
matrix([[1, 2],
        [3, 4]])
>>> A.I
matrix([[ -2. ,  1. ],
        [ 1.5, -0.5]])
>>> b = np.mat(' [5 6] ')
>>> b
matrix([[5, 6]])
>>> b.T
matrix([[5],
        [6]])
>>> A*b.T
matrix([[17],
        [39]])
```

Despite its convenience, the use of the `numpy.matrix` class is discouraged, since it adds nothing that cannot be accomplished with 2-D `numpy.ndarray` objects, and may lead to a confusion of which class is being used. For example, the above code can be rewritten as:

```
>>> import numpy as np
>>> from scipy import linalg
>>> A = np.array([[1,2],[3,4]])
>>> A
array([[1, 2],
       [3, 4]])
>>> linalg.inv(A)
array([[ -2. ,  1. ],
       [ 1.5, -0.5]])
>>> b = np.array([[5,6]]) #2D array
>>> b
array([[5, 6]])
>>> b.T
array([[5],
       [6]])
>>> A*b #not matrix multiplication!
array([[ 5, 12],
       [15, 24]])
>>> A.dot(b.T) #matrix multiplication
array([[17],
       [39]])
>>> b = np.array([5,6]) #1D array
>>> b
```

(continues on next page)

(continued from previous page)

```
array([5, 6])
>>> b.T #not matrix transpose!
array([5, 6])
>>> A.dot(b) #does not matter for multiplication
array([17, 39])
```

scipy.linalg operations can be applied equally to numpy.matrix or to 2D numpy.ndarray objects.

Basic routines

Finding the inverse

The inverse of a matrix \mathbf{A} is the matrix \mathbf{B} , such that $\mathbf{AB} = \mathbf{I}$, where \mathbf{I} is the identity matrix consisting of ones down the main diagonal. Usually, \mathbf{B} is denoted $\mathbf{B} = \mathbf{A}^{-1}$. In SciPy, the matrix inverse of the NumPy array, \mathbf{A} , is obtained using `linalg.inv(A)`, or using `A.I` if \mathbf{A} is a Matrix. For example, let

$$\mathbf{A} = \begin{bmatrix} 1 & 3 & 5 \\ 2 & 5 & 1 \\ 2 & 3 & 8 \end{bmatrix},$$

then

$$\mathbf{A}^{-1} = \frac{1}{25} \begin{bmatrix} -37 & 9 & 22 \\ 14 & 2 & -9 \\ 4 & -3 & 1 \end{bmatrix} = \begin{bmatrix} -1.48 & 0.36 & 0.88 \\ 0.56 & 0.08 & -0.36 \\ 0.16 & -0.12 & 0.04 \end{bmatrix}.$$

The following example demonstrates this computation in SciPy

```
>>> import numpy as np
>>> from scipy import linalg
>>> A = np.array([[1, 3, 5], [2, 5, 1], [2, 3, 8]])
>>> A
array([[1, 3, 5],
       [2, 5, 1],
       [2, 3, 8]])
>>> linalg.inv(A)
array([[ -1.48,  0.36,  0.88],
       [ 0.56,  0.08, -0.36],
       [ 0.16, -0.12,  0.04]])
>>> A.dot(linalg.inv(A)) #double check
array([[ 1.00000000e+00, -1.11022302e-16, -5.55111512e-17],
       [ 3.05311332e-16,  1.00000000e+00,  1.87350135e-16],
       [ 2.22044605e-16, -1.11022302e-16,  1.00000000e+00]])
```

Solving a linear system

Solving linear systems of equations is straightforward using the scipy command `linalg.solve`. This command expects an input matrix and a right-hand side vector. The solution vector is then computed. An option for entering a symmetric matrix is offered, which can speed up the processing when applicable. As an example, suppose it is desired to solve the following simultaneous equations:

$$\begin{aligned} x + 3y + 5z &= 10 \\ 2x + 5y + z &= 8 \\ 2x + 3y + 8z &= 3 \end{aligned}$$

We could find the solution vector using a matrix inverse:

$$\begin{bmatrix} x \\ y \\ z \end{bmatrix} = \begin{bmatrix} 1 & 3 & 5 \\ 2 & 5 & 1 \\ 2 & 3 & 8 \end{bmatrix}^{-1} \begin{bmatrix} 10 \\ 8 \\ 3 \end{bmatrix} = \frac{1}{25} \begin{bmatrix} -232 \\ 129 \\ 19 \end{bmatrix} = \begin{bmatrix} -9.28 \\ 5.16 \\ 0.76 \end{bmatrix}.$$

However, it is better to use the `linalg.solve` command, which can be faster and more numerically stable. In this case, it, however, gives the same answer as shown in the following example:

```
>>> import numpy as np
>>> from scipy import linalg
>>> A = np.array([[1, 2], [3, 4]])
>>> A
array([[1, 2],
       [3, 4]])
>>> b = np.array([[5], [6]])
>>> b
array([[5],
       [6]])
>>> linalg.inv(A).dot(b) # slow
array([[ -4. ],
       [ 4.5]])
>>> A.dot(linalg.inv(A).dot(b)) - b # check
array([[ 8.88178420e-16],
       [ 2.66453526e-15]])
>>> np.linalg.solve(A, b) # fast
array([[ -4. ],
       [ 4.5]])
>>> A.dot(np.linalg.solve(A, b)) - b # check
array([[ 0. ],
       [ 0.]])
```

Finding the determinant

The determinant of a square matrix \mathbf{A} is often denoted $|\mathbf{A}|$ and is a quantity often used in linear algebra. Suppose a_{ij} are the elements of the matrix \mathbf{A} and let $M_{ij} = |\mathbf{A}_{ij}|$ be the determinant of the matrix left by removing the i^{th} row and j^{th} column from \mathbf{A} . Then, for any row i ,

$$|\mathbf{A}| = \sum_j (-1)^{i+j} a_{ij} M_{ij}.$$

This is a recursive way to define the determinant, where the base case is defined by accepting that the determinant of a 1×1 matrix is the only matrix element. In SciPy the determinant can be calculated with `linalg.det`. For example, the determinant of

$$\mathbf{A} = \begin{bmatrix} 1 & 3 & 5 \\ 2 & 5 & 1 \\ 2 & 3 & 8 \end{bmatrix}$$

is

$$\begin{aligned} |\mathbf{A}| &= 1 \begin{vmatrix} 5 & 1 \\ 3 & 8 \end{vmatrix} - 3 \begin{vmatrix} 2 & 1 \\ 2 & 8 \end{vmatrix} + 5 \begin{vmatrix} 2 & 5 \\ 2 & 3 \end{vmatrix} \\ &= 1(5 \cdot 8 - 3 \cdot 1) - 3(2 \cdot 8 - 2 \cdot 1) + 5(2 \cdot 3 - 2 \cdot 5) = -25. \end{aligned}$$

. In SciPy, this is computed as shown in this example:

```

>>> import numpy as np
>>> from scipy import linalg
>>> A = np.array([[1, 2], [3, 4]])
>>> A
array([[1, 2],
       [3, 4]])
>>> linalg.det(A)
-2.0

```

Computing norms

Matrix and vector norms can also be computed with SciPy. A wide range of norm definitions are available using different parameters to the order argument of `linalg.norm`. This function takes a rank-1 (vectors) or a rank-2 (matrices) array and an optional order argument (default is 2). Based on these inputs, a vector or matrix norm of the requested order is computed.

For vector x , the order parameter can be any real number including `inf` or `-inf`. The computed norm is

$$\|x\| = \begin{cases} \max |x_i| & \text{ord} = \text{inf} \\ \min |x_i| & \text{ord} = -\text{inf} \\ \left(\sum_i |x_i|^{\text{ord}}\right)^{1/\text{ord}} & |\text{ord}| < \infty. \end{cases}$$

For matrix A , the only valid values for norm are ± 2 , ± 1 , $\pm \text{inf}$, and 'fro' (or 'f') Thus,

$$\|A\| = \begin{cases} \max_i \sum_j |a_{ij}| & \text{ord} = \text{inf} \\ \min_i \sum_j |a_{ij}| & \text{ord} = -\text{inf} \\ \max_j \sum_i |a_{ij}| & \text{ord} = 1 \\ \min_j \sum_i |a_{ij}| & \text{ord} = -1 \\ \max \sigma_i & \text{ord} = 2 \\ \min \sigma_i & \text{ord} = -2 \\ \sqrt{\text{trace}(A^H A)} & \text{ord} = \text{'fro'}$$

where σ_i are the singular values of A .

Examples:

```

>>> import numpy as np
>>> from scipy import linalg
>>> A=np.array([[1, 2], [3, 4]])
>>> A
array([[1, 2],
       [3, 4]])
>>> linalg.norm(A)
5.4772255750516612
>>> linalg.norm(A, 'fro') # frobenius norm is the default
5.4772255750516612
>>> linalg.norm(A, 1) # L1 norm (max column sum)
6
>>> linalg.norm(A, -1)
4
>>> linalg.norm(A, np.inf) # L inf norm (max row sum)
7

```


Solving linear least-squares problems and pseudo-inverses

Linear least-squares problems occur in many branches of applied mathematics. In this problem, a set of linear scaling coefficients is sought that allows a model to fit the data. In particular, it is assumed that data y_i is related to data x_i through a set of coefficients c_j and model functions $f_j(\mathbf{x}_i)$ via the model

$$y_i = \sum_j c_j f_j(\mathbf{x}_i) + \epsilon_i,$$

where ϵ_i represents uncertainty in the data. The strategy of least squares is to pick the coefficients c_j to minimize

$$J(\mathbf{c}) = \sum_i \left| y_i - \sum_j c_j f_j(x_i) \right|^2.$$

Theoretically, a global minimum will occur when

$$\frac{\partial J}{\partial c_n^*} = 0 = \sum_i \left(y_i - \sum_j c_j f_j(x_i) \right) (-f_n^*(x_i))$$

or

$$\begin{aligned} \sum_j c_j \sum_i f_j(x_i) f_n^*(x_i) &= \sum_i y_i f_n^*(x_i) \\ \mathbf{A}^H \mathbf{A} \mathbf{c} &= \mathbf{A}^H \mathbf{y} \end{aligned}$$

, where

$$\{\mathbf{A}\}_{ij} = f_j(x_i).$$

When $\mathbf{A}^H \mathbf{A}$ is invertible, then

$$\mathbf{c} = (\mathbf{A}^H \mathbf{A})^{-1} \mathbf{A}^H \mathbf{y} = \mathbf{A}^\dagger \mathbf{y},$$

where \mathbf{A}^\dagger is called the pseudo-inverse of \mathbf{A} . Notice that using this definition of \mathbf{A} the model can be written

$$\mathbf{y} = \mathbf{A} \mathbf{c} + \boldsymbol{\epsilon}.$$

The command `linalg.lstsq` will solve the linear least-squares problem for \mathbf{c} given \mathbf{A} and \mathbf{y} . In addition, `linalg.pinv` or `linalg.pinv2` (uses a different method based on singular value decomposition) will find \mathbf{A}^\dagger given \mathbf{A} .

The following example and figure demonstrate the use of `linalg.lstsq` and `linalg.pinv` for solving a data-fitting problem. The data shown below were generated using the model:

$$y_i = c_1 e^{-x_i} + c_2 x_i,$$

where $x_i = 0.1i$ for $i = 1 \dots 10$, $c_1 = 5$, and $c_2 = 4$. Noise is added to y_i and the coefficients c_1 and c_2 are estimated using linear least squares.


```
>>> import numpy as np
>>> from scipy import linalg
>>> import matplotlib.pyplot as plt
```

```
>>> c1, c2 = 5.0, 2.0
>>> i = np.r_[1:11]
>>> xi = 0.1*i
>>> yi = c1*np.exp(-xi) + c2*xi
>>> zi = yi + 0.05 * np.max(yi) * np.random.randn(len(yi))
```

```
>>> A = np.c_[np.exp(-xi)[:, np.newaxis], xi[:, np.newaxis]]
>>> c, resid, rank, sigma = linalg.lstsq(A, zi)
```

```
>>> xi2 = np.r_[0.1:1.0:100j]
>>> yi2 = c[0]*np.exp(-xi2) + c[1]*xi2
```

```
>>> plt.plot(xi, zi, 'x', xi2, yi2)
>>> plt.axis([0, 1.1, 3.0, 5.5])
>>> plt.xlabel('$x_i$')
>>> plt.title('Data fitting with linalg.lstsq')
>>> plt.show()
```



Generalized inverse

The generalized inverse is calculated using the command `linalg.pinv` or `linalg.pinv2`. These two commands differ in how they compute the generalized inverse. The first uses the `linalg.lstsq` algorithm, while the second uses singular value decomposition. Let \mathbf{A} be an $M \times N$ matrix, then if $M > N$, the generalized inverse is

$$\mathbf{A}^\dagger = (\mathbf{A}^H \mathbf{A})^{-1} \mathbf{A}^H,$$

while if $M < N$ matrix, the generalized inverse is

$$\mathbf{A}^\# = \mathbf{A}^H (\mathbf{A} \mathbf{A}^H)^{-1}.$$

In the case that $M = N$, then

$$\mathbf{A}^\dagger = \mathbf{A}^\# = \mathbf{A}^{-1},$$

as long as \mathbf{A} is invertible.

Decompositions

In many applications, it is useful to decompose a matrix using other representations. There are several decompositions supported by SciPy.

Eigenvalues and eigenvectors

The eigenvalue-eigenvector problem is one of the most commonly employed linear algebra operations. In one popular form, the eigenvalue-eigenvector problem is to find for some square matrix \mathbf{A} scalars λ and corresponding vectors \mathbf{v} , such that

$$\mathbf{A}\mathbf{v} = \lambda\mathbf{v}.$$

For an $N \times N$ matrix, there are N (not necessarily distinct) eigenvalues — roots of the (characteristic) polynomial

$$|\mathbf{A} - \lambda\mathbf{I}| = 0.$$

The eigenvectors, \mathbf{v} , are also sometimes called right eigenvectors to distinguish them from another set of left eigenvectors that satisfy

$$\mathbf{v}_L^H \mathbf{A} = \lambda \mathbf{v}_L^H$$

or

$$\mathbf{A}^H \mathbf{v}_L = \lambda^* \mathbf{v}_L.$$

With its default optional arguments, the command `linalg.eig` returns λ and \mathbf{v} . However, it can also return \mathbf{v}_L and just λ by itself (`linalg.eigvals` returns just λ as well).

In addition, `linalg.eig` can also solve the more general eigenvalue problem

$$\begin{aligned} \mathbf{A}\mathbf{v} &= \lambda\mathbf{B}\mathbf{v} \\ \mathbf{A}^H \mathbf{v}_L &= \lambda^* \mathbf{B}^H \mathbf{v}_L \end{aligned}$$

for square matrices \mathbf{A} and \mathbf{B} . The standard eigenvalue problem is an example of the general eigenvalue problem for $\mathbf{B} = \mathbf{I}$. When a generalized eigenvalue problem can be solved, it provides a decomposition of \mathbf{A} as

$$\mathbf{A} = \mathbf{B}\mathbf{V}\mathbf{\Lambda}\mathbf{V}^{-1},$$

where \mathbf{V} is the collection of eigenvectors into columns and $\mathbf{\Lambda}$ is a diagonal matrix of eigenvalues.

By definition, eigenvectors are only defined up to a constant scale factor. In SciPy, the scaling factor for the eigenvectors is chosen so that $\|\mathbf{v}\|^2 = \sum_i v_i^2 = 1$.

As an example, consider finding the eigenvalues and eigenvectors of the matrix

$$\mathbf{A} = \begin{bmatrix} 1 & 5 & 2 \\ 2 & 4 & 1 \\ 3 & 6 & 2 \end{bmatrix}.$$

The characteristic polynomial is

$$\begin{aligned} |\mathbf{A} - \lambda\mathbf{I}| &= (1 - \lambda)[(4 - \lambda)(2 - \lambda) - 6] - \\ &\quad 5[2(2 - \lambda) - 3] + 2[12 - 3(4 - \lambda)] \\ &= -\lambda^3 + 7\lambda^2 + 8\lambda - 3. \end{aligned}$$

The roots of this polynomial are the eigenvalues of **A**:

$$\begin{aligned}\lambda_1 &= 7.9579 \\ \lambda_2 &= -1.2577 \\ \lambda_3 &= 0.2997.\end{aligned}$$

The eigenvectors corresponding to each eigenvalue can be found using the original equation. The eigenvectors associated with these eigenvalues can then be found.

```
>>> import numpy as np
>>> from scipy import linalg
>>> A = np.array([[1, 2], [3, 4]])
>>> la, v = linalg.eig(A)
>>> l1, l2 = la
>>> print(l1, l2)      # eigenvalues
(-0.3722813232690143+0j) (5.372281323269014+0j)
>>> print(v[:, 0])    # first eigenvector
[-0.82456484  0.56576746]
>>> print(v[:, 1])    # second eigenvector
[-0.41597356 -0.90937671]
>>> print(np.sum(abs(v**2), axis=0)) # eigenvectors are unitary
[1. 1.]
>>> v1 = np.array(v[:, 0]).T
>>> print(linalg.norm(A.dot(v1) - l1*v1)) # check the computation
3.23682852457e-16
```

Singular value decomposition

Singular value decomposition (SVD) can be thought of as an extension of the eigenvalue problem to matrices that are not square. Let **A** be an $M \times N$ matrix with M and N arbitrary. The matrices $\mathbf{A}^H \mathbf{A}$ and $\mathbf{A} \mathbf{A}^H$ are square hermitian matrices¹ of size $N \times N$ and $M \times M$, respectively. It is known that the eigenvalues of square hermitian matrices are real and non-negative. In addition, there are at most $\min(M, N)$ identical non-zero eigenvalues of $\mathbf{A}^H \mathbf{A}$ and $\mathbf{A} \mathbf{A}^H$. Define these positive eigenvalues as σ_i^2 . The square-root of these are called singular values of **A**. The eigenvectors of $\mathbf{A}^H \mathbf{A}$ are collected by columns into an $N \times N$ unitary² matrix **V**, while the eigenvectors of $\mathbf{A} \mathbf{A}^H$ are collected by columns in the unitary matrix **U**, the singular values are collected in an $M \times N$ zero matrix Σ with main diagonal entries set to the singular values. Then

$$\mathbf{A} = \mathbf{U} \Sigma \mathbf{V}^H$$

is the singular value decomposition of **A**. Every matrix has a singular value decomposition. Sometimes, the singular values are called the spectrum of **A**. The command `linalg.svd` will return **U**, \mathbf{V}^H , and σ_i as an array of the singular values. To obtain the matrix Σ , use `linalg.diagsvd`. The following example illustrates the use of `linalg.svd`:

```
>>> import numpy as np
>>> from scipy import linalg
>>> A = np.array([[1, 2, 3], [4, 5, 6]])
>>> A
array([[1, 2, 3],
       [4, 5, 6]])
>>> M,N = A.shape
>>> U,s,Vh = linalg.svd(A)
>>> Sig = linalg.diagsvd(s,M,N)
```

(continues on next page)

¹ A hermitian matrix **D** satisfies $\mathbf{D}^H = \mathbf{D}$.

² A unitary matrix **D** satisfies $\mathbf{D}^H \mathbf{D} = \mathbf{I} = \mathbf{D} \mathbf{D}^H$ so that $\mathbf{D}^{-1} = \mathbf{D}^H$.

(continued from previous page)

```

>>> U, Vh = U, Vh
>>> U
array([[ -0.3863177 , -0.92236578],
       [-0.92236578,  0.3863177 ]])
>>> Sig
array([[ 9.508032 ,  0.          ,  0.          ],
       [ 0.          ,  0.77286964,  0.          ]])
>>> Vh
array([[ -0.42866713, -0.56630692, -0.7039467 ],
       [ 0.80596391,  0.11238241, -0.58119908],
       [ 0.40824829, -0.81649658,  0.40824829]])
>>> U.dot(Sig.dot(Vh)) #check computation
array([[ 1.,  2.,  3.],
       [ 4.,  5.,  6.]])

```

LU decomposition

The LU decomposition finds a representation for the $M \times N$ matrix \mathbf{A} as

$$\mathbf{A} = \mathbf{P}\mathbf{L}\mathbf{U},$$

where \mathbf{P} is an $M \times M$ permutation matrix (a permutation of the rows of the identity matrix), \mathbf{L} is in $M \times K$ lower triangular or trapezoidal matrix ($K = \min(M, N)$) with unit-diagonal, and \mathbf{U} is an upper triangular or trapezoidal matrix. The SciPy command for this decomposition is `linalg.lu`.

Such a decomposition is often useful for solving many simultaneous equations where the left-hand side does not change but the right-hand side does. For example, suppose we are going to solve

$$\mathbf{A}\mathbf{x}_i = \mathbf{b}_i$$

for many different \mathbf{b}_i . The LU decomposition allows this to be written as

$$\mathbf{P}\mathbf{L}\mathbf{U}\mathbf{x}_i = \mathbf{b}_i.$$

Because \mathbf{L} is lower-triangular, the equation can be solved for $\mathbf{U}\mathbf{x}_i$ and, finally, \mathbf{x}_i very rapidly using forward- and back-substitution. An initial time spent factoring \mathbf{A} allows for very rapid solution of similar systems of equations in the future. If the intent for performing LU decomposition is for solving linear systems, then the command `linalg.lu_factor` should be used followed by repeated applications of the command `linalg.lu_solve` to solve the system for each new right-hand side.

Cholesky decomposition

Cholesky decomposition is a special case of LU decomposition applicable to Hermitian positive definite matrices. When $\mathbf{A} = \mathbf{A}^H$ and $\mathbf{x}^H \mathbf{A} \mathbf{x} \geq 0$ for all \mathbf{x} , then decompositions of \mathbf{A} can be found so that

$$\begin{aligned} \mathbf{A} &= \mathbf{U}^H \mathbf{U} \\ \mathbf{A} &= \mathbf{L}\mathbf{L}^H \end{aligned}$$

, where \mathbf{L} is lower triangular and \mathbf{U} is upper triangular. Notice that $\mathbf{L} = \mathbf{U}^H$. The command `linalg.cholesky` computes the Cholesky factorization. For using the Cholesky factorization to solve systems of equations, there are also `linalg.cho_factor` and `linalg.cho_solve` routines that work similarly to their LU decomposition counterparts.

QR decomposition

The QR decomposition (sometimes called a polar decomposition) works for any $M \times N$ array and finds an $M \times M$ unitary matrix \mathbf{Q} and an $M \times N$ upper-trapezoidal matrix \mathbf{R} , such that

$$\mathbf{A} = \mathbf{QR}.$$

Notice that if the SVD of \mathbf{A} is known, then the QR decomposition can be found.

$$\mathbf{A} = \mathbf{U}\mathbf{\Sigma}\mathbf{V}^H = \mathbf{QR}$$

implies that $\mathbf{Q} = \mathbf{U}$ and $\mathbf{R} = \mathbf{\Sigma}\mathbf{V}^H$. Note, however, that in SciPy independent algorithms are used to find QR and SVD decompositions. The command for QR decomposition is `linalg.qr`.

Schur decomposition

For a square $N \times N$ matrix, \mathbf{A} , the Schur decomposition finds (not necessarily unique) matrices \mathbf{T} and \mathbf{Z} , such that

$$\mathbf{A} = \mathbf{Z}\mathbf{T}\mathbf{Z}^H,$$

where \mathbf{Z} is a unitary matrix and \mathbf{T} is either upper triangular or quasi upper triangular, depending on whether or not a real Schur form or complex Schur form is requested. For a real Schur form both \mathbf{T} and \mathbf{Z} are real-valued when \mathbf{A} is real-valued. When \mathbf{A} is a real-valued matrix, the real Schur form is only quasi upper triangular because 2×2 blocks extrude from the main diagonal corresponding to any complex-valued eigenvalues. The command `linalg.schur` finds the Schur decomposition, while the command `linalg.rsf2csf` converts \mathbf{T} and \mathbf{Z} from a real Schur form to a complex Schur form. The Schur form is especially useful in calculating functions of matrices.

The following example illustrates the Schur decomposition:

```
>>> from scipy import linalg
>>> A = np.mat('[1 3 2; 1 4 5; 2 3 6]')
>>> T, Z = linalg.schur(A)
>>> T1, Z1 = linalg.schur(A, 'complex')
>>> T2, Z2 = linalg.rsf2csf(T, Z)
>>> T
array([[ 9.90012467,  1.78947961, -0.65498528],
       [ 0.          ,  0.54993766, -1.57754789],
       [ 0.          ,  0.51260928,  0.54993766]])
>>> T2
array([[ 9.90012467+0.00000000e+00j, -0.32436598+1.55463542e+00j,
       -0.88619748+5.69027615e-01j],
       [ 0.          +0.00000000e+00j,  0.54993766+8.99258408e-01j,
        1.06493862+3.05311332e-16j],
       [ 0.          +0.00000000e+00j,  0.          +0.00000000e+00j,
        0.54993766-8.99258408e-01j]])
>>> abs(T1 - T2) # different
array([[ 1.06604538e-14,  2.06969555e+00,  1.69375747e+00], # may vary
       [ 0.00000000e+00,  1.33688556e-15,  4.74146496e-01],
       [ 0.00000000e+00,  0.00000000e+00,  1.13220977e-15]])
>>> abs(Z1 - Z2) # different
array([[ 0.06833781,  0.88091091,  0.79568503], # may vary
       [ 0.11857169,  0.44491892,  0.99594171],
       [ 0.12624999,  0.60264117,  0.77257633]])
>>> T, Z, T1, Z1, T2, Z2 = map(np.mat, (T, Z, T1, Z1, T2, Z2))
>>> abs(A - Z*T*Z.H) # same
matrix([[ 5.55111512e-16,  1.77635684e-15,  2.22044605e-15],
```

(continues on next page)

(continued from previous page)

```

      [ 0.00000000e+00,  3.99680289e-15,  8.88178420e-16],
      [ 1.11022302e-15,  4.44089210e-16,  3.55271368e-15]])
>>> abs(A - Z1*T1*Z1.H) # same
matrix([[ 4.26993904e-15,  6.21793362e-15,  8.00007092e-15],
        [ 5.77945386e-15,  6.21798014e-15,  1.06653681e-14],
        [ 7.16681444e-15,  8.90271058e-15,  1.77635764e-14]])
>>> abs(A - Z2*T2*Z2.H) # same
matrix([[ 6.02594127e-16,  1.77648931e-15,  2.22506907e-15],
        [ 2.46275555e-16,  3.99684548e-15,  8.91642616e-16],
        [ 8.88225111e-16,  8.88312432e-16,  4.44104848e-15]])

```

Interpolative decomposition

`scipy.linalg.interpolative` contains routines for computing the interpolative decomposition (ID) of a matrix. For a matrix $A \in \mathbb{C}^{m \times n}$ of rank $k \leq \min\{m, n\}$ this is a factorization

$$A\Pi = [A\Pi_1 \quad A\Pi_2] = A\Pi_1 [I \quad T],$$

where $\Pi = [\Pi_1, \Pi_2]$ is a permutation matrix with $\Pi_1 \in \{0, 1\}^{n \times k}$, i.e., $A\Pi_2 = A\Pi_1 T$. This can equivalently be written as $A = BP$, where $B = A\Pi_1$ and $P = [I, T]\Pi^T$ are the *skeleton* and *interpolation matrices*, respectively.

See also:

`scipy.linalg.interpolative` — for more information.

Matrix functions

Consider the function $f(x)$ with Taylor series expansion

$$f(x) = \sum_{k=0}^{\infty} \frac{f^{(k)}(0)}{k!} x^k.$$

A matrix function can be defined using this Taylor series for the square matrix \mathbf{A} as

$$f(\mathbf{A}) = \sum_{k=0}^{\infty} \frac{f^{(k)}(0)}{k!} \mathbf{A}^k.$$

While this serves as a useful representation of a matrix function, it is rarely the best way to calculate a matrix function.

Exponential and logarithm functions

The matrix exponential is one of the more common matrix functions. The preferred method for implementing the matrix exponential is to use scaling and a Padé approximation for e^x . This algorithm is implemented as `linalg.expm`.

The inverse of the matrix exponential is the matrix logarithm defined as the inverse of the matrix exponential:

$$\mathbf{A} \equiv \exp(\log(\mathbf{A})).$$

The matrix logarithm can be obtained with `linalg.logm`.

Trigonometric functions

The trigonometric functions, `sin`, `cos`, and `tan`, are implemented for matrices in `linalg.sinm`, `linalg.cosm`, and `linalg.tanm`, respectively. The matrix sine and cosine can be defined using Euler's identity as

$$\begin{aligned}\sin(\mathbf{A}) &= \frac{e^{j\mathbf{A}} - e^{-j\mathbf{A}}}{2j} \\ \cos(\mathbf{A}) &= \frac{e^{j\mathbf{A}} + e^{-j\mathbf{A}}}{2}.\end{aligned}$$

The tangent is

$$\tan(x) = \frac{\sin(x)}{\cos(x)} = [\cos(x)]^{-1} \sin(x)$$

and so the matrix tangent is defined as

$$[\cos(\mathbf{A})]^{-1} \sin(\mathbf{A}).$$

Hyperbolic trigonometric functions

The hyperbolic trigonometric functions, `sinh`, `cosh`, and `tanh`, can also be defined for matrices using the familiar definitions:

$$\begin{aligned}\sinh(\mathbf{A}) &= \frac{e^{\mathbf{A}} - e^{-\mathbf{A}}}{2} \\ \cosh(\mathbf{A}) &= \frac{e^{\mathbf{A}} + e^{-\mathbf{A}}}{2} \\ \tanh(\mathbf{A}) &= [\cosh(\mathbf{A})]^{-1} \sinh(\mathbf{A}).\end{aligned}$$

These matrix functions can be found using `linalg.sinhm`, `linalg.coshm`, and `linalg.tanhm`.

Arbitrary function

Finally, any arbitrary function that takes one complex number and returns a complex number can be called as a matrix function using the command `linalg.funm`. This command takes the matrix and an arbitrary Python function. It then implements an algorithm from Golub and Van Loan's book "Matrix Computations" to compute the function applied to the matrix using a Schur decomposition. Note that *the function needs to accept complex numbers* as input in order to work with this algorithm. For example, the following code computes the zeroth-order Bessel function applied to a matrix.

```
>>> from scipy import special, random, linalg
>>> np.random.seed(1234)
>>> A = random.rand(3, 3)
>>> B = linalg.funm(A, lambda x: special.jv(0, x))
>>> A
array([[ 0.19151945,  0.62210877,  0.43772774],
       [ 0.78535858,  0.77997581,  0.27259261],
       [ 0.27646426,  0.80187218,  0.95813935]])
>>> B
array([[ 0.86511146, -0.19676526, -0.13856748],
       [-0.17479869,  0.7259118 , -0.16606258],
       [-0.19212044, -0.32052767,  0.73590704]])
>>> linalg.eigvals(A)
array([ 1.73881510+0.j, -0.20270676+0.j,  0.39352627+0.j])
>>> special.jv(0, linalg.eigvals(A))
array([ 0.37551908+0.j,  0.98975384+0.j,  0.96165739+0.j])
>>> linalg.eigvals(B)
array([ 0.37551908+0.j,  0.98975384+0.j,  0.96165739+0.j])
```


Note how, by virtue of how matrix analytic functions are defined, the Bessel function has acted on the matrix eigenvalues.

Special matrices

SciPy and NumPy provide several functions for creating special matrices that are frequently used in engineering and science.

Type	Function	Description
block diagonal	<code>scipy.linalg.block_diag</code>	Create a block diagonal matrix from the provided arrays.
circulant	<code>scipy.linalg.circulant</code>	Create a circulant matrix.
companion	<code>scipy.linalg.companion</code>	Create a companion matrix.
convolution	<code>scipy.linalg.convolution_matrix</code>	Create a convolution matrix.
Discrete Fourier	<code>scipy.linalg.dft</code>	Create a discrete Fourier transform matrix.
Fiedler	<code>scipy.linalg.fiedler</code>	Create a symmetric Fiedler matrix.
Fiedler Companion	<code>scipy.linalg.fiedler_companion</code>	Create a Fiedler companion matrix.
Hadamard	<code>scipy.linalg.hadamard</code>	Create an Hadamard matrix.
Hankel	<code>scipy.linalg.hankel</code>	Create a Hankel matrix.
Helmert	<code>scipy.linalg.helmert</code>	Create a Helmert matrix.
Hilbert	<code>scipy.linalg.hilbert</code>	Create a Hilbert matrix.
Inverse Hilbert	<code>scipy.linalg.invhilbert</code>	Create the inverse of a Hilbert matrix.
Leslie	<code>scipy.linalg.leslie</code>	Create a Leslie matrix.
Pascal	<code>scipy.linalg.pascal</code>	Create a Pascal matrix.
Inverse Pascal	<code>scipy.linalg.inv_pascal</code>	Create the inverse of a Pascal matrix.
Toeplitz	<code>scipy.linalg.toeplitz</code>	Create a Toeplitz matrix.
Van der Monde	<code>numpy.vander</code>	Create a Van der Monde matrix.

For examples of the use of these functions, see their respective docstrings.

4.1.9 Sparse eigenvalue problems with ARPACK

Introduction

ARPACK¹ is a Fortran package which provides routines for quickly finding a few eigenvalues/eigenvectors of large sparse matrices. In order to find these solutions, it requires only left-multiplication by the matrix in question. This operation is performed through a *reverse-communication* interface. The result of this structure is that ARPACK is able to find eigenvalues and eigenvectors of any linear function mapping a vector to a vector.

All of the functionality provided in ARPACK is contained within the two high-level interfaces `scipy.sparse.linalg.eigs` and `scipy.sparse.linalg.eigsh`. `eigs` provides interfaces for finding the eigenvalues/vectors of real or complex nonsymmetric square matrices, while `eigsh` provides interfaces for real-symmetric or complex-hermitian matrices.

¹ <http://www.caam.rice.edu/software/ARPACK/>

Basic functionality

ARPACK can solve either standard eigenvalue problems of the form

$$A\mathbf{x} = \lambda\mathbf{x}$$

or general eigenvalue problems of the form

$$A\mathbf{x} = \lambda M\mathbf{x}.$$

The power of ARPACK is that it can compute only a specified subset of eigenvalue/eigenvector pairs. This is accomplished through the keyword `which`. The following values of `which` are available:

- `which = 'LM'` : Eigenvalues with largest magnitude (`eigs`, `eigsh`), that is, largest eigenvalues in the euclidean norm of complex numbers.
- `which = 'SM'` : Eigenvalues with smallest magnitude (`eigs`, `eigsh`), that is, smallest eigenvalues in the euclidean norm of complex numbers.
- `which = 'LR'` : Eigenvalues with largest real part (`eigs`).
- `which = 'SR'` : Eigenvalues with smallest real part (`eigs`).
- `which = 'LI'` : Eigenvalues with largest imaginary part (`eigs`).
- `which = 'SI'` : Eigenvalues with smallest imaginary part (`eigs`).
- `which = 'LA'` : Eigenvalues with largest algebraic value (`eigsh`), that is, largest eigenvalues inclusive of any negative sign.
- `which = 'SA'` : Eigenvalues with smallest algebraic value (`eigsh`), that is, smallest eigenvalues inclusive of any negative sign.
- `which = 'BE'` : Eigenvalues from both ends of the spectrum (`eigsh`).

Note that ARPACK is generally better at finding extremal eigenvalues, that is, eigenvalues with large magnitudes. In particular, using `which = 'SM'` may lead to slow execution time and/or anomalous results. A better approach is to use *shift-invert mode*.

Shift-invert mode

Shift-invert mode relies on the following observation. For the generalized eigenvalue problem

$$A\mathbf{x} = \lambda M\mathbf{x},$$

it can be shown that

$$(A - \sigma M)^{-1} M\mathbf{x} = \nu\mathbf{x},$$

where

$$\nu = \frac{1}{\lambda - \sigma}.$$

Examples

Imagine you'd like to find the smallest and largest eigenvalues and the corresponding eigenvectors for a large matrix. ARPACK can handle many forms of input: dense matrices, such as `numpy.ndarray` instances, sparse matrices, such as `scipy.sparse.csr_matrix`, or a general linear operator derived from `scipy.sparse.linalg.LinearOperator`. For this example, for simplicity, we'll construct a symmetric, positive-definite matrix.

```
>>> import numpy as np
>>> from scipy.linalg import eig, eigh
>>> from scipy.sparse.linalg import eigs, eigsh
>>> np.set_printoptions(suppress=True)
>>>
>>> np.random.seed(0)
>>> X = np.random.random((100,100)) - 0.5
>>> X = np.dot(X, X.T) #create a symmetric matrix
```

We now have a symmetric matrix `X`, with which to test the routines. First, compute a standard eigenvalue decomposition using `eigh`:

```
>>> evals_all, evects_all = eigh(X)
```

As the dimension of `X` grows, this routine becomes very slow. Especially, if only a few eigenvectors and eigenvalues are needed, ARPACK can be a better option. First let's compute the largest eigenvalues (which = 'LM') of `X` and compare them to the known results:

```
>>> evals_large, evects_large = eigsh(X, 3, which='LM')
>>> print(evals_all[-3:])
[29.1446102  30.05821805  31.19467646]
>>> print(evals_large)
[29.1446102  30.05821805  31.19467646]
>>> print(np.dot(evects_large.T, evects_all[:, -3:]))
array([[ -1.   0.   0.],          # may vary (signs)
       [  0.   1.   0.],
       [ -0.   0.  -1.]])
```

The results are as expected. ARPACK recovers the desired eigenvalues and they match the previously known results. Furthermore, the eigenvectors are orthogonal, as we'd expect. Now, let's attempt to solve for the eigenvalues with smallest magnitude:

```
>>> evals_small, evects_small = eigsh(X, 3, which='SM')
Traceback (most recent call last):          # may vary (convergence)
...
scipy.sparse.linalg.eigen.arpark.arpark.ArpackNoConvergence:
ARPACK error -1: No convergence (1001 iterations, 0/3 eigenvectors converged)
```

Oops. We see that, as mentioned above, ARPACK is not quite as adept at finding small eigenvalues. There are a few ways this problem can be addressed. We could increase the tolerance (`tol`) to lead to faster convergence:

```
>>> evals_small, evects_small = eigsh(X, 3, which='SM', tol=1E-2)
>>> evals_all[:3]
array([0.0003783, 0.00122714, 0.00715878])
>>> evals_small
array([0.00037831, 0.00122714, 0.00715881])
>>> np.dot(evects_small.T, evects_all[:, :3])
```

(continues on next page)

(continued from previous page)

```
array([[ 0.99999999  0.00000024 -0.00000049],      # may vary (signs)
       [-0.00000023  0.99999999  0.00000056],
       [ 0.00000031 -0.00000037  0.99999852]])
```

This works, but we lose the precision in the results. Another option is to increase the maximum number of iterations (`maxiter`) from 1000 to 5000:

```
>>> evals_small, evects_small = eigsh(X, 3, which='SM', maxiter=5000)
>>> evals_all[:3]
array([0.0003783, 0.00122714, 0.00715878])
>>> evals_small
array([0.0003783, 0.00122714, 0.00715878])
>>> np.dot(evects_small.T, evects_all[:, :3])
array([[ 1.  0.  0.],      # may vary (signs)
       [-0.  1.  0.],
       [ 0.  0. -1.]])
```

We get the results we'd hoped for, but the computation time is much longer. Fortunately, ARPACK contains a mode that allows a quick determination of non-external eigenvalues: *shift-invert mode*. As mentioned above, this mode involves transforming the eigenvalue problem to an equivalent problem with different eigenvalues. In this case, we hope to find eigenvalues near zero, so we'll choose `sigma = 0`. The transformed eigenvalues will then satisfy $\nu = 1/(\lambda - \sigma) = 1/\lambda$, so our small eigenvalues λ become large eigenvalues ν .

```
>>> evals_small, evects_small = eigsh(X, 3, sigma=0, which='LM')
>>> evals_all[:3]
array([0.0003783, 0.00122714, 0.00715878])
>>> evals_small
array([0.0003783, 0.00122714, 0.00715878])
>>> np.dot(evects_small.T, evects_all[:, :3])
array([[ 1.  0.  0.],      # may vary (signs)
       [ 0. -1. -0.],
       [-0. -0.  1.]])
```

We get the results we were hoping for, with much less computational time. Note that the transformation from $\nu \rightarrow \lambda$ takes place entirely in the background. The user need not worry about the details.

The shift-invert mode provides more than just a fast way to obtain a few small eigenvalues. Say, you desire to find internal eigenvalues and eigenvectors, e.g., those nearest to $\lambda = 1$. Simply set `sigma = 1` and ARPACK will take care of the rest:

```
>>> evals_mid, evects_mid = eigsh(X, 3, sigma=1, which='LM')
>>> i_sort = np.argsort(abs(1. / (1 - evals_all)))[-3:]
>>> evals_all[i_sort]
array([1.16577199, 0.85081388, 1.06642272])
>>> evals_mid
array([0.85081388, 1.06642272, 1.16577199])
>>> print(np.dot(evects_mid.T, evects_all[:, i_sort]))
array([[ -0.  1.  0.],      # may vary (signs)
       [-0. -0.  1.],
       [ 1.  0.  0.]])
```

The eigenvalues come out in a different order, but they're all there. Note that the shift-invert mode requires the internal solution of a matrix inverse. This is taken care of automatically by `eigsh` and `eigs`, but the operation can also be

specified by the user. See the docstring of `scipy.sparse.linalg.eigsh` and `scipy.sparse.linalg.eigs` for details.

Use of LinearOperator

We consider now the case where you'd like to avoid creating a dense matrix and use `scipy.sparse.linalg.LinearOperator` instead. Our first linear operator applies element-wise multiplication between the input vector and a vector `d` provided by the user to the operator itself. This operator mimics a diagonal matrix with the elements of `d` along the main diagonal and it has the main benefit that the forward and adjoint operations are simple element-wise multiplications other than matrix-vector multiplications. For a diagonal matrix, we expect the eigenvalues to be equal to the elements along the main diagonal, in this case `d`. The eigenvalues and eigenvectors obtained with `eigsh` are compared to those obtained by using `eigh` when applied to the dense matrix:

```
>>> from scipy.sparse.linalg import LinearOperator
>>> class Diagonal(LinearOperator):
...     def __init__(self, diag, dtype='float32'):
...         self.diag = diag
...         self.shape = (len(self.diag), len(self.diag))
...         self.dtype = np.dtype(dtype)
...     def _matvec(self, x):
...         return self.diag*x
...     def _rmatvec(self, x):
...         return self.diag*x
```

```
>>> np.random.seed(0)
>>> N = 100
>>> d = np.random.normal(0, 1, N).astype(np.float64)
>>> D = np.diag(d)
>>> Dop = Diagonal(d, dtype=np.float64)
```

```
>>> evals_all, evecs_all = eig(D)
>>> evals_large, evecs_large = eigsh(Dop, 3, which='LA', maxiter=1e3)
>>> evals_all[-3:]
array([1.9507754 , 2.2408932 , 2.26975462])
>>> evals_large
array([1.9507754 , 2.2408932 , 2.26975462])
>>> print(np.dot(evecs_large.T, evecs_all[:, -3:]))
array([[ -1.  0.  0.],          # may vary (signs)
       [ -0. -1.  0.],
       [ 0.  0. -1.]])
```

In this case, we have created a quick and easy `Diagonal` operator. The external library `PyLops` provides similar capabilities in the `Diagonal` operator, as well as several other operators.

Finally, we consider a linear operator that mimics the application of a first-derivative stencil. In this case, the operator is equivalent to a real nonsymmetric matrix. Once again, we compare the estimated eigenvalues and eigenvectors with those from a dense matrix that applies the same first derivative to an input signal:

```
>>> class FirstDerivative(LinearOperator):
...     def __init__(self, N, dtype='float32'):
...         self.N = N
...         self.shape = (self.N, self.N)
...         self.dtype = np.dtype(dtype)
```

(continues on next page)

(continued from previous page)

```

...     def _matvec(self, x):
...         y = np.zeros(self.N, self.dtype)
...         y[1:-1] = (0.5*x[2:]-0.5*x[0:-2])
...         return y
...     def _rmatvec(self, x):
...         y = np.zeros(self.N, self.dtype)
...         y[0:-2] = y[0:-2] - (0.5*x[1:-1])
...         y[2:] = y[2:] + (0.5*x[1:-1])
...         return y

```

```

>>> N = 21
>>> D = np.diag(0.5*np.ones(N-1), k=1) - np.diag(0.5*np.ones(N-1), k=-1)
>>> D[0] = D[-1] = 0 # take away edge effects
>>> Dop = FirstDerivative(N, dtype=np.float64)

```

```

>>> evals_all, evecs_all = eig(D)
>>> evals_large, evecs_large = eigs(Dop, 4, which='LI')
>>> evals_all_imag = evals_all.imag
>>> isort_imag = np.argsort(np.abs(evals_all_imag))
>>> evals_all_imag = evals_all_imag[isort_imag]
>>> evals_large_imag = evals_large.imag
>>> isort_imag = np.argsort(np.abs(evals_large_imag))
>>> evals_large_imag = evals_large_imag[isort_imag]
>>> evals_all_imag[-4:]
array([-0.95105652,  0.95105652, -0.98768834,  0.98768834])
>>> evals_large_imag
array([0.95105652, -0.95105652,  0.98768834, -0.98768834])

```

Note that the eigenvalues of this operator are all imaginary. Moreover, the keyword `which='LI'` of `scipy.sparse.linalg.eigs` produces the eigenvalues with largest absolute imaginary part (both positive and negative). Again, a more advanced implementation of the first-derivative operator is available in the `PyLops` library under the name of `FirstDerivative` operator.

References

4.1.10 Compressed Sparse Graph Routines (`scipy.sparse.csgraph`)

Example: Word Ladders

A **Word Ladder** is a word game invented by Lewis Carroll, in which players find paths between words by switching one letter at a time. For example, one can link “ape” and “man” in the following way:

ape → apt → ait → bit → big → bag → mag → man

Note that each step involves changing just one letter of the word. This is just one possible path from “ape” to “man”, but is it the shortest possible path? If we desire to find the shortest word-ladder path between two given words, the sparse graph submodule can help.

First, we need a list of valid words. Many operating systems have such a list built in. For example, on linux, a word list can often be found at one of the following locations:

```
/usr/share/dict
/var/lib/dict
```

Another easy source for words are the Scrabble word lists available at various sites around the internet (search with your favorite search engine). We'll first create this list. The system word lists consist of a file with one word per line. The following should be modified to use the particular word list you have available:

```
>>> word_list = open('/usr/share/dict/words').readlines()
>>> word_list = map(str.strip, word_list)
```

We want to look at words of length 3, so let's select just those words of the correct length. We'll also eliminate words which start with upper-case (proper nouns) or contain non-alphanumeric characters, like apostrophes and hyphens. Finally, we'll make sure everything is lower-case for comparison later:

```
>>> word_list = [word for word in word_list if len(word) == 3]
>>> word_list = [word for word in word_list if word[0].islower()]
>>> word_list = [word for word in word_list if word.isalpha()]
>>> word_list = list(map(str.lower, word_list))
>>> len(word_list)
586      # may vary
```

Now we have a list of 586 valid three-letter words (the exact number may change depending on the particular list used). Each of these words will become a node in our graph, and we will create edges connecting the nodes associated with each pair of words which differs by only one letter.

There are efficient ways to do this, and inefficient ways to do this. To do this as efficiently as possible, we're going to use some sophisticated numpy array manipulation:

```
>>> import numpy as np
>>> word_list = np.asarray(word_list)
>>> word_list.dtype      # these are unicode characters in Python 3
dtype('<U3')
>>> word_list.sort()    # sort for quick searching later
```

We have an array where each entry is three unicode characters long. We'd like to find all pairs where exactly one character is different. We'll start by converting each word to a 3-D vector:

```
>>> word_bytes = np.ndarray((word_list.size, word_list.itemsize),
...                          dtype='uint8',
...                          buffer=word_list.data)
>>> # each unicode character is four bytes long. We only need first byte
>>> # we know that there are three characters in each word
>>> word_bytes = word_bytes[:, ::word_list.itemsize//3]
>>> word_bytes.shape
(586, 3)      # may vary
```

Now, we'll use the [Hamming distance](#) between each point to determine which pairs of words are connected. The Hamming distance measures the fraction of entries between two vectors which differ: any two words with a Hamming distance equal to $1/N$, where N is the number of letters, are connected in the word ladder:

```
>>> from scipy.spatial.distance import pdist, squareform
>>> from scipy.sparse import csr_matrix
>>> hamming_dist = pdist(word_bytes, metric='hamming')
>>> # there are three characters in each word
>>> graph = csr_matrix(squareform(hamming_dist < 1.5 / 3))
```

When comparing the distances, we don't use an equality because this can be unstable for floating point values. The inequality produces the desired result, as long as no two entries of the word list are identical. Now, that our graph is set up, we'll use a shortest path search to find the path between any two words in the graph:

```
>>> i1 = word_list.searchsorted('ape')
>>> i2 = word_list.searchsorted('man')
>>> word_list[i1]
'ape'
>>> word_list[i2]
'man'
```

We need to check that these match, because if the words are not in the list, that will not be the case. Now, all we need is to find the shortest path between these two indices in the graph. We'll use [Dijkstra's algorithm](#), because it allows us to find the path for just one node:

```
>>> from scipy.sparse.csgraph import dijkstra
>>> distances, predecessors = dijkstra(graph, indices=i1,
...                               return_predecessors=True)
>>> print(distances[i2])
5.0      # may vary
```

So we see that the shortest path between “ape” and “man” contains only five steps. We can use the predecessors returned by the algorithm to reconstruct this path:

```
>>> path = []
>>> i = i2
>>> while i != i1:
...     path.append(word_list[i])
...     i = predecessors[i]
>>> path.append(word_list[i1])
>>> print(path[::-1])
['ape', 'apt', 'opt', 'oat', 'mat', 'man']      # may vary
```

This is three fewer links than our initial example: the path from “ape” to “man” is only five steps.

Using other tools in the module, we can answer other questions. For example, are there three-letter words which are not linked in a word ladder? This is a question of connected components in the graph:

```
>>> from scipy.sparse.csgraph import connected_components
>>> N_components, component_list = connected_components(graph)
>>> print(N_components)
15      # may vary
```

In this particular sample of three-letter words, there are 15 connected components: that is, 15 distinct sets of words with no paths between the sets. How many words are there in each of these sets? We can learn this from the list of components:

```
>>> [np.sum(component_list == i) for i in range(N_components)]
[571, 1, 1, 1, 2, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1]      # may vary
```

There is one large connected set and 14 smaller ones. Let's look at the words in the smaller ones:

```
>>> [list(word_list[np.nonzero(component_list == i)]) for i in range(1, N_
↪components)]
[['aha'],      # may vary
 ['chi'],
```

(continues on next page)

(continued from previous page)

```

['ebb'],
['ems', 'emu'],
['gnu'],
['ism'],
['khz'],
['nth'],
['ova'],
['qua'],
['ugh'],
['ups'],
['urn'],
['use']]

```

These are all the three-letter words which do not connect to others via a word ladder.

We might also be curious about which words are maximally separated. Which two words take the most links to connect? We can determine this by computing the matrix of all shortest paths. Note that, by convention, the distance between two non-connected points is reported to be infinity, so we'll need to remove these before finding the maximum:

```

>>> distances, predecessors = dijkstra(graph, return_predecessors=True)
>>> max_distance = np.max(distances[~np.isinf(distances)])
>>> print(max_distance)
13.0      # may vary

```

So, there is at least one pair of words which takes 13 steps to get from one to the other! Let's determine which these are:

```

>>> i1, i2 = np.nonzero(distances == max_distance)
>>> list(zip(word_list[i1], word_list[i2]))
[('imp', 'ohm'),      # may vary
 ('imp', 'ohs'),
 ('ohm', 'imp'),
 ('ohm', 'ump'),
 ('ohs', 'imp'),
 ('ohs', 'ump'),
 ('ump', 'ohm'),
 ('ump', 'ohs')]

```

We see that there are two pairs of words which are maximally separated from each other: 'imp' and 'ump' on the one hand, and 'ohm' and 'ohs' on the other. We can find the connecting list in the same way as above:

```

>>> path = []
>>> i = i2[0]
>>> while i != i1[0]:
...     path.append(word_list[i])
...     i = predecessors[i1[0], i]
>>> path.append(word_list[i1[0]])
>>> print(path[::-1])
['imp', 'amp', 'asp', 'ass', 'ads', 'add', 'aid', 'mid', 'mod', 'moo', 'too',
 → 'tho', 'oho', 'ohm']      # may vary

```

This gives us the path we desired to see.

Word ladders are just one potential application of scipy's fast graph algorithms for sparse matrices. Graph theory makes appearances in many areas of mathematics, data analysis, and machine learning. The sparse graph tools are flexible enough

to handle many of these situations.

4.1.11 Spatial data structures and algorithms (`scipy.spatial`)

`scipy.spatial` can compute triangulations, Voronoi diagrams, and convex hulls of a set of points, by leveraging the Qhull library.

Moreover, it contains *KDTree* implementations for nearest-neighbor point queries, and utilities for distance computations in various metrics.

Delaunay triangulations

The Delaunay triangulation is a subdivision of a set of points into a non-overlapping set of triangles, such that no point is inside the circumcircle of any triangle. In practice, such triangulations tend to avoid triangles with small angles.

Delaunay triangulation can be computed using `scipy.spatial` as follows:

```
>>> from scipy.spatial import Delaunay
>>> points = np.array([[0, 0], [0, 1.1], [1, 0], [1, 1]])
>>> tri = Delaunay(points)
```

We can visualize it:

```
>>> import matplotlib.pyplot as plt
>>> plt.triplot(points[:,0], points[:,1], tri.simplices)
>>> plt.plot(points[:,0], points[:,1], 'o')
```

And add some further decorations:


```
>>> for j, p in enumerate(points):
...     plt.text(p[0]-0.03, p[1]+0.03, j, ha='right') # label the points
>>> for j, s in enumerate(tri.simplices):
...     p = points[s].mean(axis=0)
...     plt.text(p[0], p[1], '#%d' % j, ha='center') # label triangles
>>> plt.xlim(-0.5, 1.5); plt.ylim(-0.5, 1.5)
>>> plt.show()
```

The structure of the triangulation is encoded in the following way: the `simplices` attribute contains the indices of the points in the `points` array that make up the triangle. For instance:

```
>>> i = 1
>>> tri.simplices[i,:]
array([3, 1, 0], dtype=int32)
>>> points[tri.simplices[i,:]]
array([[ 1. ,  1. ],
       [ 0. ,  1.1],
       [ 0. ,  0. ]])
```

Moreover, neighboring triangles can also be found:

```
>>> tri.neighbors[i]
array([-1,  0, -1], dtype=int32)
```



What this tells us is that this triangle has triangle #0 as a neighbor, but no other neighbors. Moreover, it tells us that neighbor 0 is opposite the vertex 1 of the triangle:

```
>>> points[tri.simplices[i, 1]]
array([ 0. ,  1.1])
```

Indeed, from the figure, we see that this is the case.

Qhull can also perform tessellations to simplices for higher-dimensional point sets (for instance, subdivision into tetrahedra in 3-D).

Coplanar points

It is important to note that not *all* points necessarily appear as vertices of the triangulation, due to numerical precision issues in forming the triangulation. Consider the above with a duplicated point:

```
>>> points = np.array([[0, 0], [0, 1], [1, 0], [1, 1], [1, 1]])
>>> tri = Delaunay(points)
>>> np.unique(tri.simplices.ravel())
array([0, 1, 2, 3], dtype=int32)
```

Observe that point #4, which is a duplicate, does not occur as a vertex of the triangulation. That this happened is recorded:

```
>>> tri.coplanar
array([[4, 0, 3]], dtype=int32)
```

This means that point 4 resides near triangle 0 and vertex 3, but is not included in the triangulation.

Note that such degeneracies can occur not only because of duplicated points, but also for more complicated geometrical reasons, even in point sets that at first sight seem well-behaved.

However, Qhull has the “QJ” option, which instructs it to perturb the input data randomly until degeneracies are resolved:

```
>>> tri = Delaunay(points, qhull_options="QJ Pp")
>>> points[tri.simplices]
array([[1, 0],
```

(continues on next page)

(continued from previous page)

```

    [1, 1],
    [0, 0]],
  [[1, 1],
   [1, 1],
   [1, 0]],
  [[1, 1],
   [0, 1],
   [0, 0]],
  [[0, 1],
   [1, 1],
   [1, 1]]])

```

Two new triangles appeared. However, we see that they are degenerate and have zero area.

Convex hulls

A convex hull is the smallest convex object containing all points in a given point set.

These can be computed via the Qhull wrappers in `scipy.spatial` as follows:

```

>>> from scipy.spatial import ConvexHull
>>> points = np.random.rand(30, 2) # 30 random points in 2-D
>>> hull = ConvexHull(points)

```


The convex hull is represented as a set of N 1-D simplices, which in 2-D means line segments. The storage scheme is exactly the same as for the simplices in the Delaunay triangulation discussed above.

We can illustrate the above result:

```

>>> import matplotlib.pyplot as plt
>>> plt.plot(points[:,0], points[:,1], 'o')
>>> for simplex in hull.simplices:
...     plt.plot(points[simplex,0], points[simplex,1], 'k-')
>>> plt.show()

```



The same can be achieved with `scipy.spatial.convex_hull_plot_2d`.

Voronoi diagrams


A Voronoi diagram is a subdivision of the space into the nearest neighborhoods of a given set of points.

There are two ways to approach this object using `scipy.spatial`. First, one can use the `KDTree` to answer the question “which of the points is closest to this one”, and define the regions that way:

```
>>> from scipy.spatial import KDTree
>>> points = np.array([[0, 0], [0, 1], [0, 2], [1, 0], [1, 1], [1, 2],
...                   [2, 0], [2, 1], [2, 2]])
>>> tree = KDTree(points)
>>> tree.query([0.1, 0.1])
(0.14142135623730953, 0)
```

So the point $(0.1, 0.1)$ belongs to region 0. In color:

```
>>> x = np.linspace(-0.5, 2.5, 31)
>>> y = np.linspace(-0.5, 2.5, 33)
>>> xx, yy = np.meshgrid(x, y)
>>> xy = np.c_[xx.ravel(), yy.ravel()]
>>> import matplotlib.pyplot as plt
>>> dx_half, dy_half = np.diff(x[:2])[0] / 2., np.diff(y[:2])[0] / 2.
>>> x_edges = np.concatenate((x - dx_half, [x[-1] + dx_half]))
>>> y_edges = np.concatenate((y - dy_half, [y[-1] + dy_half]))
>>> plt.pcolormesh(x_edges, y_edges, tree.query(xy)[1].reshape(33, 31),
-> shading='flat')
>>> plt.plot(points[:,0], points[:,1], 'ko')
>>> plt.show()
```



This does not, however, give the Voronoi diagram as a geometrical object.

The representation in terms of lines and points can be again obtained via the Qhull wrappers in `scipy.spatial`:

```
>>> from scipy.spatial import Voronoi
>>> vor = Voronoi(points)
>>> vor.vertices
array([[0.5, 0.5],
       [0.5, 1.5],
       [1.5, 0.5],
       [1.5, 1.5]])
```

The Voronoi vertices denote the set of points forming the polygonal edges of the Voronoi regions. In this case, there are 9 different regions:

```
>>> vor.regions
[[[], [-1, 0], [-1, 1], [1, -1, 0], [3, -1, 2], [-1, 3], [-1, 2], [0, 1, 3, 2],
  ↪ [2, -1, 0], [3, -1, 1]]
```

Negative value `-1` again indicates a point at infinity. Indeed, only one of the regions, `[0, 1, 3, 2]`, is bounded. Note here that due to similar numerical precision issues as in Delaunay triangulation above, there may be fewer Voronoi regions than input points.

The ridges (lines in 2-D) separating the regions are described as a similar collection of simplices as the convex hull pieces:

```
>>> vor.ridge_vertices
[[-1, 0], [-1, 0], [-1, 1], [-1, 1], [0, 1], [-1, 3], [-1, 2], [2, 3], [-1, ↪
  ↪ 3], [-1, 2], [1, 3], [0, 2]]
```

These numbers present the indices of the Voronoi vertices making up the line segments. `-1` is again a point at infinity — only 4 of the 12 lines are a bounded line segment, while others extend to infinity.

The Voronoi ridges are perpendicular to the lines drawn between the input points. To which two points each ridge corresponds is also recorded:

```
>>> vor.ridge_points
array([[0, 3],
       [0, 1],
       [2, 5],
       [2, 1],
       [1, 4],
       [7, 8],
       [7, 6],
       [7, 4],
       [8, 5],
       [6, 3],
       [4, 5],
       [4, 3]], dtype=int32)
```

This information, taken together, is enough to construct the full diagram.

We can plot it as follows. First, the points and the Voronoi vertices:


```
>>> plt.plot(points[:, 0], points[:, 1], 'o')
>>> plt.plot(vor.vertices[:, 0], vor.vertices[:, 1], '*')
>>> plt.xlim(-1, 3); plt.ylim(-1, 3)
```

Plotting the finite line segments goes as for the convex hull, but now we have to guard for the infinite edges:

```
>>> for simplex in vor.ridge_vertices:
...     simplex = np.asarray(simplex)
...     if np.all(simplex >= 0):
...         plt.plot(vor.vertices[simplex, 0], vor.vertices[simplex, 1], 'k-')
```

The ridges extending to infinity require a bit more care:

```
>>> center = points.mean(axis=0)
>>> for pointidx, simplex in zip(vor.ridge_points, vor.ridge_vertices):
...     simplex = np.asarray(simplex)
...     if np.any(simplex < 0):
...         i = simplex[simplex >= 0][0] # finite end Voronoi vertex
...         t = points[pointidx[1]] - points[pointidx[0]] # tangent
...         t = t / np.linalg.norm(t)
...         n = np.array([-t[1], t[0]]) # normal
...         midpoint = points[pointidx].mean(axis=0)
...         far_point = vor.vertices[i] + np.sign(np.dot(midpoint - center,
... ↪n)) * n * 100
...         plt.plot([vor.vertices[i,0], far_point[0]],
...                   [vor.vertices[i,1], far_point[1]], 'k--')
>>> plt.show()
```



This plot can also be created using `scipy.spatial.voronoi_plot_2d`.

Voronoi diagrams can be used to create interesting generative art. Try playing with the settings of this mandala function to create your own!

```
>>> import numpy as np
>>> from scipy import spatial
>>> import matplotlib.pyplot as plt
```

```
>>> def mandala(n_iter, n_points, radius):
...     """Creates a mandala figure using Voronoi tessellations.
...     """
...     ...
```

(continues on next page)

(continued from previous page)

```

...     Parameters
...     -----
...     n_iter : int
...         Number of iterations, i.e. how many times the equidistant points_
↳will
...         be generated.
...     n_points : int
...         Number of points to draw per iteration.
...     radius : scalar
...         The radial expansion factor.
...
...     Returns
...     -----
...     fig : matplotlib.Figure instance
...
...     Notes
...     -----
...     This code is adapted from the work of Audrey Roy Greenfeld [1]_ and_
↳Carlos
...     Focil-Espinosa [2]_, who created beautiful mandalas with Python code._
↳ That
...     code in turn was based on Antonio Sánchez Chinchón's R code [3]_.
...
...     References
...     -----
...     .. [1] https://www.codemakesmehappy.com/2019/09/voronoi-mandalas.html
...     .. [2] https://github.com/CarlosFocil/mandalapy
...     .. [3] https://github.com/aschinchon/mandalas
...
...     """
...     fig = plt.figure(figsize=(10, 10))
...     ax = fig.add_subplot(111)
...     ax.set_axis_off()
...     ax.set_aspect('equal', adjustable='box')
...
...     angles = np.linspace(0, 2*np.pi * (1 - 1/n_points), num=n_points) +_
↳np.pi/2
...     # Starting from a single center point, add points iteratively
...     xy = np.array([[0, 0]])
...     for k in range(n_iter):
...         t1 = np.array([])
...         t2 = np.array([])
...         # Add `n_points` new points around each existing point in this_
↳iteration
...         for i in range(xy.shape[0]):
...             t1 = np.append(t1, xy[i, 0] + radius**k * np.cos(angles))
...             t2 = np.append(t2, xy[i, 1] + radius**k * np.sin(angles))
...
...         xy = np.column_stack((t1, t2))
...

```

(continues on next page)

(continued from previous page)

```

...     # Create the Mandala figure via a Voronoi plot
...     spatial.voronoi_plot_2d(spatial.Voronoi(xy), ax=ax)
...
...     return fig

```

```

>>> # Modify the following parameters in order to get different figures
>>> n_iter = 3
>>> n_points = 6
>>> radius = 4

```

```

>>> fig = mandala(n_iter, n_points, radius)
>>> plt.show()

```

4.1.12 Statistics (`scipy.stats`)

Introduction

In this tutorial, we discuss many, but certainly not all, features of `scipy.stats`. The intention here is to provide a user with a working knowledge of this package. We refer to the *reference manual* for further details.

Note: This documentation is work in progress.

Discrete Statistical Distributions

Discrete random variables take on only a countable number of values. The commonly used distributions are included in SciPy and described in this document. Each discrete distribution can take one extra integer parameter: L . The relationship between the general distribution p and the standard distribution p_0 is

$$p(x) = p_0(x - L)$$

which allows for shifting of the input. When a distribution generator is initialized, the discrete distribution can either specify the beginning and ending (integer) values a and b which must be such that

$$p_0(x) = 0 \quad x < a \text{ or } x > b$$

in which case, it is assumed that the pdf function is specified on the integers $a + mk \leq b$ where k is a non-negative integer ($0, 1, 2, \dots$) and m is a positive integer multiplier. Alternatively, the two lists x_k and $p(x_k)$ can be provided directly in which case a dictionary is set up internally to evaluate probabilities and generate random variates.

Probability Mass Function (PMF)

The probability mass function of a random variable X is defined as the probability that the random variable takes on a particular value.


$$p(x_k) = P[X = x_k]$$

This is also sometimes called the probability density function, although technically

$$f(x) = \sum_k p(x_k) \delta(x - x_k)$$

is the probability density function for a discrete distribution¹.

¹ XXX: Unknown layout Plain Layout: Note that we will be using p to represent the probability mass function and a parameter (a XXX: probability). The usage should be obvious from context.



Cumulative Distribution Function (CDF)

The cumulative distribution function is

$$F(x) = P[X \leq x] = \sum_{x_k \leq x} p(x_k)$$

and is also useful to be able to compute. Note that

$$F(x_k) - F(x_{k-1}) = p(x_k)$$

Survival Function

The survival function is just

$$S(x) = 1 - F(x) = P[X > k]$$

the probability that the random variable is strictly larger than k .

Percent Point Function (Inverse CDF)

The percent point function is the inverse of the cumulative distribution function and is

$$G(q) = F^{-1}(q)$$

for discrete distributions, this must be modified for cases where there is no x_k such that $F(x_k) = q$. In these cases we choose $G(q)$ to be the smallest value $x_k = G(q)$ for which $F(x_k) \geq q$. If $q = 0$ then we define $G(0) = a - 1$. This definition allows random variates to be defined in the same way as with continuous rv's using the inverse cdf on a uniform distribution to generate random variates.

Inverse survival function

The inverse survival function is the inverse of the survival function

$$Z(\alpha) = S^{-1}(\alpha) = G(1 - \alpha)$$

and is thus the smallest non-negative integer k for which $F(k) \geq 1 - \alpha$ or the smallest non-negative integer k for which $S(k) \leq \alpha$.

Hazard functions

If desired, the hazard function and the cumulative hazard function could be defined as

$$h(x_k) = \frac{p(x_k)}{1 - F(x_k)}$$

and

$$H(x) = \sum_{x_k \leq x} h(x_k) = \sum_{x_k \leq x} \frac{F(x_k) - F(x_{k-1})}{1 - F(x_k)}$$

Moments

Non-central moments are defined using the PDF

$$\mu'_m = E[X^m] = \sum_k x_k^m p(x_k).$$

Central moments are computed similarly $\mu = \mu'_1$

$$\begin{aligned} \mu_m = E[(X - \mu)^m] &= \sum_k (x_k - \mu)^m p(x_k) \\ &= \sum_{k=0}^m (-1)^{m-k} \binom{m}{k} \mu^{m-k} \mu'_k \end{aligned}$$

The mean is the first moment

$$\mu = \mu'_1 = E[X] = \sum_k x_k p(x_k)$$

the variance is the second central moment

$$\mu_2 = E[(X - \mu)^2] = \sum_{x_k} x_k^2 p(x_k) - \mu^2.$$

Skewness is defined as

$$\gamma_1 = \frac{\mu_3}{\mu_2^{3/2}}$$

while (Fisher) kurtosis is

$$\gamma_2 = \frac{\mu_4}{\mu_2^2} - 3,$$

so that a normal distribution has a kurtosis of zero.

Moment generating function

The moment generating function is defined as

$$M_X(t) = E[e^{Xt}] = \sum_{x_k} e^{x_k t} p(x_k)$$

Moments are found as the derivatives of the moment generating function evaluated at 0.

Fitting data

To fit data to a distribution, maximizing the likelihood function is common. Alternatively, some distributions have well-known minimum variance unbiased estimators. These will be chosen by default, but the likelihood function will always be available for minimizing.

If $f_i(k; \theta)$ is the PDF of a random-variable where θ is a vector of parameters (e.g. L and S), then for a collection of N independent samples from this distribution, the joint distribution the random vector \mathbf{k} is

$$f(\mathbf{k}; \theta) = \prod_{i=1}^N f_i(k_i; \theta).$$

The maximum likelihood estimate of the parameters θ are the parameters which maximize this function with \mathbf{x} fixed and given by the data:

$$\begin{aligned}\hat{\theta} &= \arg \max_{\theta} f(\mathbf{k}; \theta) \\ &= \arg \min_{\theta} l_{\mathbf{k}}(\theta).\end{aligned}$$

Where

$$\begin{aligned}l_{\mathbf{k}}(\theta) &= -\sum_{i=1}^N \log f(k_i; \theta) \\ &= -N \overline{\log f(k_i; \theta)}\end{aligned}$$

Standard notation for mean

We will use

$$\overline{y(\mathbf{x})} = \frac{1}{N} \sum_{i=1}^N y(x_i)$$

where N should be clear from context.

Combinations

Note that

$$k! = k \cdot (k-1) \cdot (k-2) \cdot \dots \cdot 1 = \Gamma(k+1)$$

and has special cases of

$$\begin{aligned}0! &\equiv 1 \\ k! &\equiv 0 \quad k < 0\end{aligned}$$

and

$$\binom{n}{k} = \frac{n!}{(n-k)!k!}.$$

If $n < 0$ or $k < 0$ or $k > n$ we define $\binom{n}{k} = 0$

Discrete Distributions in `scipy.stats`

Bernoulli Distribution

A Bernoulli random variable of parameter p takes one of only two values $X = 0$ or $X = 1$. The probability of success ($X = 1$) is p , and the probability of failure ($X = 0$) is $1 - p$. It can be thought of as a binomial random variable with

$n = 1$. The PMF is $p(k) = 0$ for $k \neq 0, 1$ and

$$\begin{aligned}
 p(k; p) &= \begin{cases} 1 - p & k = 0 \\ p & k = 1 \end{cases} \\
 F(x; p) &= \begin{cases} 0 & x < 0 \\ 1 - p & 0 \leq x < 1 \\ 1 & 1 \leq x \end{cases} \\
 G(q; p) &= \begin{cases} 0 & 0 \leq q < 1 - p \\ 1 & 1 - p \leq q \leq 1 \end{cases} \\
 \mu &= p \\
 \mu_2 &= p(1 - p) \\
 \gamma_3 &= \frac{1 - 2p}{\sqrt{p(1 - p)}} \\
 \gamma_4 &= \frac{1 - 6p(1 - p)}{p(1 - p)} \\
 M(t) &= 1 - p(1 - e^t) \\
 \mu'_m &= p \\
 h[X] &= p \log p + (1 - p) \log(1 - p)
 \end{aligned}$$

Implementation: `scipy.stats.bernoulli`

Beta-Binomial Distribution

The beta-binomial distribution is a binomial distribution with a probability of success p that follows a beta distribution. The probability mass function for *betabinom*, defined for $0 \leq k \leq n$, is:

$$f(k; n, a, b) = \binom{n}{k} \frac{B(k + a, n - k + b)}{B(a, b)}$$

for k in $\{0, 1, \dots, n\}$, where $B(a, b)$ is the Beta function.

In the limiting case of $a = b = 1$, the beta-binomial distribution reduces to a discrete uniform distribution:

$$f(k; n, 1, 1) = \frac{1}{n + 1}$$

In the limiting case of $n = 1$, the beta-binomial distribution reduces to a Bernoulli distribution with the shape parameter $p = a/(a + b)$:

$$f(k; 1, a, b) = \begin{cases} a/(a + b) & \text{if } k = 0 \\ b/(a + b) & \text{if } k = 1 \end{cases}$$

Implementation: `scipy.stats.betabinom`

Binomial Distribution

A binomial random variable with parameters (n, p) can be described as the sum of n independent Bernoulli random variables of parameter p ;

$$Y = \sum_{i=1}^n X_i.$$

Therefore, this random variable counts the number of successes in n independent trials of a random experiment where the probability of success is p .

$$p(k; n, p) = \binom{n}{k} p^k (1-p)^{n-k} \quad k \in \{0, 1, \dots, n\},$$

$$F(x; n, p) = \sum_{k \leq x} \binom{n}{k} p^k (1-p)^{n-k} = I_{1-p}(n - \lfloor x \rfloor, \lfloor x \rfloor + 1) \quad x \geq 0$$

where the incomplete beta integral is

$$I_x(a, b) = \frac{\Gamma(a+b)}{\Gamma(a)\Gamma(b)} \int_0^x t^{a-1} (1-t)^{b-1} dt.$$

Now

$$\begin{aligned} \mu &= np \\ \mu_2 &= np(1-p) \\ \gamma_1 &= \frac{1-2p}{\sqrt{np(1-p)}} \\ \gamma_2 &= \frac{1-6p(1-p)}{np(1-p)}. \end{aligned}$$

$$M(t) = [1 - p(1 - e^t)]^n$$

Implementation: `scipy.stats.binom`

Boltzmann (truncated Planck) Distribution

$$p(k; N, \lambda) = \frac{1 - e^{-\lambda}}{1 - e^{-\lambda N}} \exp(-\lambda k) \quad k \in \{0, 1, \dots, N-1\}$$

$$F(x; N, \lambda) = \begin{cases} 0 & x < 0 \\ \frac{1 - \exp[-\lambda(\lfloor x \rfloor + 1)]}{1 - \exp(-\lambda N)} & 0 \leq x \leq N-1 \\ 1 & x \geq N-1 \end{cases}$$

$$G(q, \lambda) = \left\lceil -\frac{1}{\lambda} \log [1 - q(1 - e^{-\lambda N})] - 1 \right\rceil$$

Define $z = e^{-\lambda}$

$$\begin{aligned}\mu &= \frac{z}{1-z} - \frac{Nz^N}{1-z^N} \\ \mu_2 &= \frac{z}{(1-z)^2} - \frac{N^2z^N}{(1-z^N)^2} \\ \gamma_1 &= \frac{z(1+z)\left(\frac{1-z^N}{1-z}\right)^3 - N^3z^N(1+z^N)}{\left[z\left(\frac{1-z^N}{1-z}\right)^2 - N^2z^N\right]^{3/2}} \\ \gamma_2 &= \frac{z(1+4z+z^2)\left(\frac{1-z^N}{1-z}\right)^4 - N^4z^N(1+4z^N+z^{2N})}{\left[z\left(\frac{1-z^N}{1-z}\right)^2 - N^2z^N\right]^2} \\ M(t) &= \frac{1 - e^{N(t-\lambda)}}{1 - e^{t-\lambda}} \frac{1 - e^{-\lambda}}{1 - e^{-\lambda N}}\end{aligned}$$

Implementation: `scipy.stats.boltzmann`

Planck (discrete exponential) Distribution

Named Planck because of its relationship to the black-body problem he solved.

$$\begin{aligned}p(k; \lambda) &= (1 - e^{-\lambda}) e^{-\lambda k} \quad k\lambda \geq 0 \\ F(x; \lambda) &= 1 - e^{-\lambda(\lfloor x \rfloor + 1)} \quad x\lambda \geq 0 \\ G(q; \lambda) &= \left\lceil -\frac{1}{\lambda} \log[1 - q] - 1 \right\rceil.\end{aligned}$$

$$\begin{aligned}\mu &= \frac{1}{e^\lambda - 1} \\ \mu_2 &= \frac{e^{-\lambda}}{(1 - e^{-\lambda})^2} \\ \gamma_1 &= 2 \cosh\left(\frac{\lambda}{2}\right) \\ \gamma_2 &= 4 + 2 \cosh(\lambda) \\ M(t) &= \frac{1 - e^{-\lambda}}{1 - e^{t-\lambda}} \\ h[X] &= \frac{\lambda e^{-\lambda}}{1 - e^{-\lambda}} - \log(1 - e^{-\lambda})\end{aligned}$$

Implementation: `scipy.stats.planck`

Poisson Distribution

The Poisson random variable counts the number of successes in n independent Bernoulli trials in the limit as $n \rightarrow \infty$ and $p \rightarrow 0$ where the probability of success in each trial is p and $np = \lambda \geq 0$ is a constant. It can be used to approximate the Binomial random variable or in its own right to count the number of events that occur in the interval $[0, t]$ for a process satisfying certain “sparsity” constraints. The functions are:

$$\begin{aligned}
 p(k; \lambda) &= e^{-\lambda} \frac{\lambda^k}{k!} \quad k \geq 0, \\
 F(x; \lambda) &= \sum_{n=0}^{\lfloor x \rfloor} e^{-\lambda} \frac{\lambda^n}{n!} = \frac{1}{\Gamma(\lfloor x \rfloor + 1)} \int_{\lambda}^{\infty} t^{\lfloor x \rfloor} e^{-t} dt, \\
 \mu &= \lambda \\
 \mu_2 &= \lambda \\
 \gamma_1 &= \frac{1}{\sqrt{\lambda}} \\
 \gamma_2 &= \frac{1}{\lambda}. \\
 M(t) &= \exp[\lambda(e^t - 1)].
 \end{aligned}$$

Implementation: `scipy.stats.poisson`

Geometric Distribution

The geometric random variable with parameter $p \in (0, 1)$ can be defined as the number of trials required to obtain a success where the probability of success on each trial is p . Thus,

$$\begin{aligned}
 p(k; p) &= (1-p)^{k-1} p \quad k \geq 1 \\
 F(x; p) &= 1 - (1-p)^{\lfloor x \rfloor} \quad x \geq 1 \\
 G(q; p) &= \left\lceil \frac{\log(1-q)}{\log(1-p)} \right\rceil \\
 \mu &= \frac{1}{p} \\
 \mu_2 &= \frac{1-p}{p^2} \\
 \gamma_1 &= \frac{2-p}{\sqrt{1-p}} \\
 \gamma_2 &= \frac{p^2 - 6p + 6}{1-p}. \\
 M(t) &= \frac{p}{e^{-t} - (1-p)}
 \end{aligned}$$

Implementation: `scipy.stats.geom`

Negative Binomial Distribution

The negative binomial random variable with parameters n and $p \in (0, 1)$ can be defined as the number of *extra* independent trials (beyond n) required to accumulate a total of n successes where the probability of a success on each trial is p . Equivalently, this random variable is the number of failures encountered while accumulating n successes during independent trials of an experiment that succeeds with probability p . Thus,

$$\begin{aligned}
 p(k; n, p) &= \binom{k+n-1}{n-1} p^n (1-p)^k \quad k \geq 0 \\
 F(x; n, p) &= \sum_{i=0}^{\lfloor x \rfloor} \binom{i+n-1}{i} p^n (1-p)^i \quad x \geq 0 \\
 &= I_p(n, \lfloor x \rfloor + 1) \quad x \geq 0 \\
 \mu &= n \frac{1-p}{p} \\
 \mu_2 &= n \frac{1-p}{p^2} \\
 \gamma_1 &= \frac{2-p}{\sqrt{n(1-p)}} \\
 \gamma_2 &= \frac{p^2 + 6(1-p)}{n(1-p)}.
 \end{aligned}$$

Recall that $I_p(a, b)$ is the incomplete beta integral.

Implementation: `scipy.stats.nbinom`

Hypergeometric Distribution

The hypergeometric random variable with parameters (M, n, N) counts the number of “good” objects in a sample of size N chosen without replacement from a population of M objects where n is the number of “good” objects in the total population.

$$\begin{aligned}
 p(k; N, n, M) &= \frac{\binom{n}{k} \binom{M-n}{N-k}}{\binom{M}{N}} \quad N - (M - n) \leq k \leq \min(n, N) \\
 F(x; N, n, M) &= \sum_{k=0}^{\lfloor x \rfloor} \frac{\binom{m}{k} \binom{N-m}{n-k}}{\binom{N}{n}}, \\
 \mu &= \frac{nN}{M} \\
 \mu_2 &= \frac{nN(M-n)(M-N)}{M^2(M-1)} \\
 \gamma_1 &= \frac{(M-2n)(M-2N)}{M-2} \sqrt{\frac{M-1}{nN(M-m)(M-n)}} \\
 \gamma_2 &= \frac{g(N, n, M)}{nN(M-n)(M-3)(M-2)(N-M)}
 \end{aligned}$$

where (defining $m = M - n$)

$$\begin{aligned}
 g(N, n, M) = & m^3 - m^5 + 3m^2n - 6m^3n + m^4n + 3mn^2 \\
 & -12m^2n^2 + 8m^3n^2 + n^3 - 6mn^3 + 8m^2n^3 \\
 & +mn^4 - n^5 - 6m^3N + 6m^4N + 18m^2nN \\
 & -6m^3nN + 18mn^2N - 24m^2n^2N - 6n^3N \\
 & -6mn^3N + 6n^4N + 6m^2N^2 - 6m^3N^2 - 24mnN^2 \\
 & +12m^2nN^2 + 6n^2N^2 + 12mn^2N^2 - 6n^3N^2.
 \end{aligned}$$

Implementation: `scipy.stats.hypergeom`

Negative Hypergeometric Distribution

Consider a box containing M balls: n red and $M - n$ blue. We randomly sample balls from the box, one at a time and *without* replacement, until we have picked r blue balls. `nhypergeom` is the distribution of the number of red balls k we have picked.

$$p(k; M, n, r) = \frac{\binom{k+r-1}{k} \binom{M-r-k}{n-k}}{\binom{M}{n}} \quad 0 \leq k \leq M - n,$$

$$F(x; M, n, r) = \sum_{k=0}^{\lfloor x \rfloor} p(k; M, n, r),$$

$$\mu = \frac{rn}{M - n + 1},$$

$$\mu_2 = \frac{rn(M+1)}{(M-n+1)(M-n+2)} \left(1 - \frac{r}{M-n+1} \right)$$

for $k \in 0, 1, 2, \dots, n$, where the binomial coefficients are defined as,

$$\binom{n}{k} \equiv \frac{n!}{k!(n-k)!}$$

The cumulative distribution, survivor function, hazard function, cumulative hazard function, inverse distribution function, moment generating function, and characteristic function on the support of k are mathematically intractable.

Implementation: `scipy.stats.nhypergeom`

Zipf (Zeta) Distribution

A random variable has the zeta distribution (also called the zipf distribution) with parameter $\alpha > 1$ if its probability mass function is given by

$$p(k; \alpha) = \frac{1}{\zeta(\alpha) k^\alpha} \quad k \geq 1$$

where

$$\zeta(\alpha) = \sum_{n=1}^{\infty} \frac{1}{n^\alpha}$$

is the Riemann zeta function. Other functions of this distribution are

$$\begin{aligned}
 F(x; \alpha) &= \frac{1}{\zeta(\alpha)} \sum_{k=1}^{\lfloor x \rfloor} \frac{1}{k^\alpha} \\
 \mu &= \frac{\zeta_1}{\zeta_0} \quad \alpha > 2 \\
 \mu_2 &= \frac{\zeta_2 \zeta_0 - \zeta_1^2}{\zeta_0^2} \quad \alpha > 3 \\
 \gamma_1 &= \frac{\zeta_3 \zeta_0^2 - 3\zeta_0 \zeta_1 \zeta_2 + 2\zeta_1^3}{[\zeta_2 \zeta_0 - \zeta_1^2]^{3/2}} \quad \alpha > 4 \\
 \gamma_2 &= \frac{\zeta_4 \zeta_0^3 - 4\zeta_3 \zeta_1 \zeta_0^2 + 12\zeta_2 \zeta_1^2 \zeta_0 - 6\zeta_1^4 - 3\zeta_2^2 \zeta_0^2}{(\zeta_2 \zeta_0 - \zeta_1^2)^2} \\
 M(t) &= \frac{\text{Li}_\alpha(e^t)}{\zeta(\alpha)}
 \end{aligned}$$

where $\zeta_i = \zeta(\alpha - i)$ and $\text{Li}_n(z)$ is the n^{th} polylogarithm function of z defined as

$$\begin{aligned}
 \text{Li}_n(z) &\equiv \sum_{k=1}^{\infty} \frac{z^k}{k^n} \\
 \mu'_n = M^{(n)}(t) \Big|_{t=0} &= \frac{\text{Li}_{\alpha-n}(e^t)}{\zeta(\alpha)} \Big|_{t=0} = \frac{\zeta(\alpha - n)}{\zeta(\alpha)}
 \end{aligned}$$

Implementation: `scipy.stats.zipf`

Logarithmic (Log-Series, Series) Distribution

The logarithmic distribution with parameter p has a probability mass function with terms proportional to the Taylor series expansion of $\log(1 - p)$

$$\begin{aligned}
 p(k; p) &= -\frac{p^k}{k \log(1 - p)} \quad k \geq 1 \\
 F(x; p) &= -\frac{1}{\log(1 - p)} \sum_{k=1}^{\lfloor x \rfloor} \frac{p^k}{k} = 1 + \frac{p^{1+\lfloor x \rfloor} \Phi(p, 1, 1 + \lfloor x \rfloor)}{\log(1 - p)}
 \end{aligned}$$

where

$$\Phi(z, s, a) = \sum_{k=0}^{\infty} \frac{z^k}{(a + k)^s}$$

is the Lerch Transcendent. Also define $r = \log(1 - p)$

$$\begin{aligned}
 \mu &= -\frac{p}{(1 - p)r} \\
 \mu_2 &= -\frac{p[p + r]}{(1 - p)^2 r^2} \\
 \gamma_1 &= -\frac{2p^2 + 3pr + (1 + p)r^2}{r(p + r)\sqrt{-p(p + r)}} r \\
 \gamma_2 &= -\frac{6p^3 + 12p^2 r + p(4p + 7)r^2 + (p^2 + 4p + 1)r^3}{p(p + r)^2}
 \end{aligned}$$

$$\begin{aligned}
 M(t) &= -\frac{1}{\log(1-p)} \sum_{k=1}^{\infty} \frac{e^{tk} p^k}{k} \\
 &= \frac{\log(1-pe^t)}{\log(1-p)}
 \end{aligned}$$

Thus,

$$\mu'_n = M^{(n)}(t) \Big|_{t=0} = \frac{\text{Li}_{1-n}(pe^t)}{\log(1-p)} \Big|_{t=0} = -\frac{\text{Li}_{1-n}(p)}{\log(1-p)}.$$

Implementation: `scipy.stats.logser`

Discrete Uniform (randint) Distribution

The discrete uniform distribution with parameters (a, b) constructs a random variable that has an equal probability of being any one of the integers in the half-open range $[a, b)$. If a is not given it is assumed to be zero and the only parameter is b . Therefore,

$$\begin{aligned}
 p(k, a, b) &= \frac{1}{b-a} \quad a \leq k < b \\
 F(x; a, b) &= \frac{\lfloor x \rfloor - a}{b-a} \quad a \leq x \leq b \\
 G(q; a, b) &= \lceil q(b-a) + a \rceil \\
 \mu &= \frac{b+a-1}{2} \\
 \mu_2 &= \frac{(b-a-1)(b-a+1)}{12} \\
 \gamma_1 &= 0 \\
 \gamma_2 &= -\frac{6}{5} \frac{(b-a)^2 + 1}{(b-a-1)(b-a+1)}.
 \end{aligned}$$

$$\begin{aligned}
 M(t) &= \frac{1}{b-a} \sum_{k=a}^{b-1} e^{tk} \\
 &= \frac{e^{bt} - e^{at}}{(b-a)(e^t - 1)}
 \end{aligned}$$

Implementation: `scipy.stats.randint`

Discrete Laplacian Distribution

Defined over all integers for $a > 0$

$$\begin{aligned}
 p(k) &= \tanh\left(\frac{a}{2}\right) e^{-a|k|}, \\
 F(x) &= \begin{cases} \frac{e^{a(\lfloor x \rfloor + 1)}}{e^a + 1} & \lfloor x \rfloor < 0, \\ 1 - \frac{e^{-a\lfloor x \rfloor}}{e^a + 1} & \lfloor x \rfloor \geq 0. \end{cases} \\
 G(q) &= \begin{cases} \lceil \frac{1}{a} \log[q(e^a + 1)] - 1 \rceil & q < \frac{1}{1+e^{-a}}, \\ \lceil -\frac{1}{a} \log[(1-q)(1+e^a)] \rceil & q \geq \frac{1}{1+e^{-a}}. \end{cases}
 \end{aligned}$$

$$\begin{aligned}
 M(t) &= \tanh\left(\frac{a}{2}\right) \sum_{k=-\infty}^{\infty} e^{tk} e^{-a|k|} \\
 &= C \left(1 + \sum_{k=1}^{\infty} e^{-(t+a)k} + \sum_{k=1}^{\infty} e^{(t-a)k} \right) \\
 &= \tanh\left(\frac{a}{2}\right) \left(1 + \frac{e^{-(t+a)}}{1 - e^{-(t+a)}} + \frac{e^{t-a}}{1 - e^{t-a}} \right) \\
 &= \frac{\tanh\left(\frac{a}{2}\right) \sinh a}{\cosh a - \cosh t}.
 \end{aligned}$$

Thus,

$$\mu'_n = M^{(n)}(0) = [1 + (-1)^n] \text{Li}_{-n}(e^{-a})$$

where $\text{Li}_{-n}(z)$ is the polylogarithm function of order $-n$ evaluated at z .

$$h[X] = -\log\left(\tanh\left(\frac{a}{2}\right)\right) + \frac{a}{\sinh a}$$

Implementation: `scipy.stats.dlaplace`

Yule-Simon Distribution

A Yule-Simon random variable with parameter $\alpha > 0$ can be represented as a mixture of exponential random variates. To see this write W as an exponential random variate with rate ρ and a Geometric random variate K with probability $1 - \exp(-W)$ then K marginally has a Yule-Simon distribution. The latent variable representation described above is used for random variate generation.

$$\begin{aligned}
 p(k; \alpha) &= \alpha \frac{\Gamma(k) \Gamma(\alpha + 1)}{\Gamma(k + \alpha + 1)} \\
 F(k; \alpha) &= 1 - \frac{k \Gamma(k) \Gamma(\alpha + 1)}{\Gamma(k + \alpha + 1)}
 \end{aligned}$$

for $k = 1, 2, \dots$

Now

$$\begin{aligned}
 \mu &= \frac{\alpha}{\alpha - 1} \\
 \mu_2 &= \frac{\alpha^2}{(\alpha - 1)^2 (\alpha - 2)} \\
 \gamma_1 &= \frac{\sqrt{(\alpha - 2)} (\alpha + 1)^2}{\alpha (\alpha - 3)} \\
 \gamma_2 &= \frac{(\alpha + 3) + (\alpha^3 - 49\alpha - 22)}{\alpha (\alpha - 4) (\alpha - 3)}
 \end{aligned}$$

for $\alpha > 1$ otherwise the mean is infinite and the variance does not exist. For the variance, $\alpha > 2$ otherwise the variance does not exist. Similarly, for the skewness and kurtosis to be finite, $\alpha > 3$ and $\alpha > 4$ respectively.

Implementation: `scipy.stats.yulesimon`

Continuous Statistical Distributions

Overview

All distributions will have location (L) and Scale (S) parameters along with any shape parameters needed, the names for the shape parameters will vary. Standard form for the distributions will be given where $L = 0.0$ and $S = 1.0$. The nonstandard forms can be obtained for the various functions using (note U is a standard uniform random variate).

Function Name	Standard Function	Transformation
Cumulative Distribution Function (CDF)	$F(x)$	$F(x; L, S) = F\left(\frac{(x-L)}{S}\right)$
Probability Density Function (PDF)	$f(x) = F'(x)$	$f(x; L, S) = \frac{1}{S} f\left(\frac{(x-L)}{S}\right)$
Percent Point Function (PPF)	$G(q) = F^{-1}(q)$	$G(q; L, S) = L + SG(q)$
Probability Sparsity Function (PSF)	$g(q) = G'(q)$	$g(q; L, S) = Sg(q)$
Hazard Function (HF)	$h_a(x) = \frac{f(x)}{1-F(x)}$	$h_a(x; L, S) = \frac{1}{S} h_a\left(\frac{(x-L)}{S}\right)$
Cumulative Hazard Function (CHF)	$H_a(x) = \log \frac{1}{1-F(x)}$	$H_a(x; L, S) = H_a\left(\frac{(x-L)}{S}\right)$
Survival Function (SF)	$S(x) = 1 - F(x)$	$S(x; L, S) = S\left(\frac{(x-L)}{S}\right)$
Inverse Survival Function (ISF)	$Z(\alpha) = S^{-1}(\alpha) = G(1 - \alpha)$	$Z(\alpha; L, S) = L + SZ(\alpha)$
Moment Generating Function (MGF)	$M_Y(t) = E[e^{Yt}]$	$M_X(t) = e^{Lt} M_Y(S t)$
Random Variates	$Y = G(U)$	$X = L + SY$
(Differential) Entropy	$h[Y] = -\int f(y) \log f(y) dy$	$h[X] = h[Y] + \log S$
(Non-central) Moments	$\mu'_n = E[Y^n]$	$E[X^n] = L^n \sum_{k=0}^n \binom{n}{k} \left(\frac{S}{L}\right)^k \mu'_k$
Central Moments	$\mu_n = E[(Y - \mu)^n]$	$E[(X - \mu_X)^n] = S^n \mu_n$
mean (mode, median), var	μ, μ_2	$L + S\mu, S^2\mu_2$
skewness	$\gamma_1 = \frac{\mu_3}{(\mu_2)^{3/2}}$	γ_1
kurtosis	$\gamma_2 = \frac{\mu_4}{(\mu_2)^2} - 3$	γ_2

Moments

Non-central moments are defined using the PDF

$$\mu'_n = \int_{-\infty}^{\infty} x^n f(x) dx.$$

Note, that these can always be computed using the PPF. Substitute $x = G(q)$ in the above equation and get

$$\mu'_n = \int_0^1 G^n(q) dq$$

which may be easier to compute numerically. Note that $q = F(x)$ so that $dq = f(x) dx$. Central moments are computed similarly $\mu = \mu'_1$

$$\begin{aligned} \mu_n &= \int_{-\infty}^{\infty} (x - \mu)^n f(x) dx \\ &= \int_0^1 (G(q) - \mu)^n dq \\ &= \sum_{k=0}^n \binom{n}{k} (-\mu)^k \mu'_{n-k} \end{aligned}$$

In particular

$$\begin{aligned}\mu_3 &= \mu'_3 - 3\mu\mu'_2 + 2\mu^3 \\ &= \mu'_3 - 3\mu\mu_2 - \mu^3 \\ \mu_4 &= \mu'_4 - 4\mu\mu'_3 + 6\mu^2\mu'_2 - 3\mu^4 \\ &= \mu'_4 - 4\mu\mu_3 - 6\mu^2\mu_2 - \mu^4\end{aligned}$$

Skewness is defined as

$$\gamma_1 = \sqrt{\beta_1} = \frac{\mu_3}{\mu_2^{3/2}}$$

while (Fisher) kurtosis is

$$\gamma_2 = \frac{\mu_4}{\mu_2^2} - 3,$$

so that a normal distribution has a kurtosis of zero.

Median and mode

The median, m_n is defined as the point at which half of the density is on one side and half on the other. In other words, $F(m_n) = \frac{1}{2}$ so that

$$m_n = G\left(\frac{1}{2}\right).$$

In addition, the mode, m_d , is defined as the value for which the probability density function reaches it's peak

$$m_d = \arg \max_x f(x).$$

Fitting data

To fit data to a distribution, maximizing the likelihood function is common. Alternatively, some distributions have well-known minimum variance unbiased estimators. These will be chosen by default, but the likelihood function will always be available for minimizing.

If $f(x; \theta)$ is the PDF of a random-variable where θ is a vector of parameters (*e.g.* L and S), then for a collection of N independent samples from this distribution, the joint distribution the random vector \mathbf{x} is

$$f(\mathbf{x}; \theta) = \prod_{i=1}^N f(x_i; \theta).$$

The maximum likelihood estimate of the parameters θ are the parameters which maximize this function with \mathbf{x} fixed and given by the data:

$$\begin{aligned}\theta_{es} &= \arg \max_{\theta} f(\mathbf{x}; \theta) \\ &= \arg \min_{\theta} l_{\mathbf{x}}(\theta).\end{aligned}$$

Where

$$\begin{aligned}l_{\mathbf{x}}(\theta) &= -\sum_{i=1}^N \log f(x_i; \theta) \\ &= -N \overline{\log f(x_i; \theta)}\end{aligned}$$

Note that if θ includes only shape parameters, the location and scale-parameters can be fit by replacing x_i with $(x_i - L)/S$ in the log-likelihood function adding $N \log S$ and minimizing, thus

$$\begin{aligned} l_{\mathbf{x}}(L, S; \theta) &= N \log S - \sum_{i=1}^N \log f\left(\frac{x_i - L}{S}; \theta\right) \\ &= N \log S + l_{\frac{\mathbf{x}-L}{S}}(\theta) \end{aligned}$$

If desired, sample estimates for L and S (not necessarily maximum likelihood estimates) can be obtained from samples estimates of the mean and variance using

$$\begin{aligned} \hat{S} &= \sqrt{\frac{\hat{\mu}_2}{\mu_2}} \\ \hat{L} &= \hat{\mu} - \hat{S}\mu \end{aligned}$$

where μ and μ_2 are assumed known as the mean and variance of the **untransformed** distribution (when $L = 0$ and $S = 1$) and

$$\begin{aligned} \hat{\mu} &= \frac{1}{N} \sum_{i=1}^N x_i = \bar{\mathbf{x}} \\ \hat{\mu}_2 &= \frac{1}{N-1} \sum_{i=1}^N (x_i - \hat{\mu})^2 = \frac{N}{N-1} \overline{(\mathbf{x} - \bar{\mathbf{x}})^2} \end{aligned}$$

Standard notation for mean

We will use

$$\overline{y(\mathbf{x})} = \frac{1}{N} \sum_{i=1}^N y(x_i)$$

where N should be clear from context as the number of samples x_i

References

- Documentation for ranlib, rv2, cdfib
- Eric Weisstein's world of mathematics <http://mathworld.wolfram.com/>, <http://mathworld.wolfram.com/topics/StatisticalDistributions.html>
- Documentation to Regress+ by Michael McLaughlin item Engineering and Statistics Handbook (NIST), <https://www.itl.nist.gov/div898/handbook/>
- Documentation for DATAPLOT from NIST, <https://www.itl.nist.gov/div898/software/dataplot/distribu.htm>
- Norman Johnson, Samuel Kotz, and N. Balakrishnan Continuous Univariate Distributions, second edition, Volumes I and II, Wiley & Sons, 1994.

In the tutorials several special functions appear repeatedly and are listed here.

Symbol	Description	Definition
$\gamma(s, x)$	lower incomplete Gamma function	$\int_0^x t^{s-1} e^{-t} dt$
$\Gamma(s, x)$	upper incomplete Gamma function	$\int_x^\infty t^{s-1} e^{-t} dt$
$B(x; a, b)$	incomplete Beta function	$\int_0^x t^{a-1} (1-t)^{b-1} dt$
$I(x; a, b)$	regularized incomplete Beta function	$\frac{\Gamma(a+b)}{\Gamma(a)\Gamma(b)} \int_0^x t^{a-1} (1-t)^{b-1} dt$
$\phi(x)$	PDF for normal distribution	$\frac{1}{\sqrt{2\pi}} e^{-x^2/2}$
$\Phi(x)$	CDF for normal distribution	$\int_{-\infty}^x \phi(t) dt = \frac{1}{2} + \frac{1}{2} \operatorname{erf}\left(\frac{x}{\sqrt{2}}\right)$
$\psi(z)$	digamma function	$\frac{d}{dz} \log(\Gamma(z))$
$\psi_n(z)$	polygamma function	$\frac{d^{n+1}}{dz^{n+1}} \log(\Gamma(z))$
$I_\nu(y)$	modified Bessel function of the first kind	
$\operatorname{Ei}(z)$	exponential integral	$-\int_{-x}^\infty \frac{e^{-t}}{t} dt$
$\zeta(n)$	Riemann zeta function	$\sum_{k=1}^\infty \frac{1}{k^n}$
$\zeta(n, z)$	Hurwitz zeta function	$\sum_{k=0}^\infty \frac{1}{(k+z)^n}$
${}_pF_q(a_1, \dots, a_p; b_1, \dots, b_q; z)$	Hypergeometric function	$\sum_{n=0}^\infty \frac{(a_1)_n \cdots (a_p)_n}{(b_1)_n \cdots (b_q)_n} \frac{z^n}{n!}$

Continuous Distributions in `scipy.stats`

Alpha Distribution

One shape parameter $\alpha > 0$ (parameter β in DATAPLOT is a scale-parameter). The support for the standard form is $x > 0$.

$$f(x; \alpha) = \frac{1}{x^2 \Phi(\alpha) \sqrt{2\pi}} \exp\left(-\frac{1}{2} \left(\alpha - \frac{1}{x}\right)^2\right)$$

$$F(x; \alpha) = \frac{\Phi\left(\alpha - \frac{1}{x}\right)}{\Phi(\alpha)}$$

$$G(q; \alpha) = \left[\alpha - \Phi^{-1}(q\Phi(\alpha))\right]^{-1}$$

$$M(t) = \frac{1}{\Phi(\alpha) \sqrt{2\pi}} \int_0^\infty \frac{e^{xt}}{x^2} \exp\left(-\frac{1}{2} \left(\alpha - \frac{1}{x}\right)^2\right) dx$$

No moments?

$$l_{\mathbf{x}}(\alpha) = N \log \left[\Phi(\alpha) \sqrt{2\pi} \right] + 2N \overline{\log \mathbf{x}} + \frac{N}{2} \alpha^2 - \alpha \overline{\mathbf{x}^{-1}} + \frac{1}{2} \overline{\mathbf{x}^{-2}}$$

Implementation: `scipy.stats.alpha`

Anglit Distribution

Defined over $x \in \left[-\frac{\pi}{4}, \frac{\pi}{4}\right]$.

$$f(x) = \sin\left(2x + \frac{\pi}{2}\right) = \cos(2x)$$

$$F(x) = \sin^2\left(x + \frac{\pi}{4}\right)$$

$$G(q) = \arcsin(\sqrt{q}) - \frac{\pi}{4}$$

$$\begin{aligned}\mu &= 0 \\ \mu_2 &= \frac{\pi^2}{16} - \frac{1}{2} \\ \gamma_1 &= 0 \\ \gamma_2 &= -2 \frac{\pi^4 - 96}{(\pi^2 - 8)^2}\end{aligned}$$

$$\begin{aligned}h[X] &= 1 - \log 2 \\ &\approx 0.30685281944005469058\end{aligned}$$

$$\begin{aligned}M(t) &= \int_{-\frac{\pi}{4}}^{\frac{\pi}{4}} \cos(2x) e^{xt} dx \\ &= \frac{4 \cosh\left(\frac{\pi t}{4}\right)}{t^2 + 4}\end{aligned}$$

$$l_{\mathbf{x}}(\cdot) = -N \log [\cos(2\mathbf{x})]$$

Implementation: `scipy.stats.anglit`

Arcsine Distribution

Defined over $x \in [0, 1]$. To get the JKB definition put $x = \frac{u+1}{2}$. i.e. $L = -1$ and $S = 2$.

$$f(x) = \frac{1}{\pi \sqrt{x(1-x)}}$$

$$F(x) = \frac{2}{\pi} \arcsin(\sqrt{x})$$

$$G(q) = \sin^2\left(\frac{\pi}{2}q\right)$$

$$M(t) = E^{t/2} I_0\left(\frac{t}{2}\right)$$

$$\begin{aligned}\mu'_n &= \frac{1}{\pi} \int_0^1 x^{n-1/2} (1-x)^{-1/2} dx \\ &= \frac{1}{\pi} B\left(\frac{1}{2}, n + \frac{1}{2}\right) = \frac{(2n-1)!!}{2^n n!}\end{aligned}$$

$$\mu = \frac{1}{2}$$

$$\mu_2 = \frac{1}{8}$$

$$\gamma_1 = 0$$

$$\gamma_2 = -\frac{3}{2}$$

$$h[X] = \log\left(\frac{\pi}{4}\right) \approx -0.24156447527049044468$$

$$l_{\mathbf{x}}(\cdot) = N \log \pi + \frac{N}{2} \log \mathbf{x} + \frac{N}{2} \log(1 - \mathbf{x})$$

Implementation: `scipy.stats.arcsine`

Beta Distribution

There are two shape parameters $a, b > 0$ and the support is $x \in [0, 1]$.

$$\begin{aligned}
 f(x; a, b) &= \frac{\Gamma(a+b)}{\Gamma(a)\Gamma(b)} x^{a-1} (1-x)^{b-1} \\
 F(x; a, b) &= \int_0^x f(y; a, b) dy = I(x; a, b) \\
 G(q; a, b) &= I^{-1}(q; a, b) \\
 M(t) &= \frac{\Gamma(a)\Gamma(b)}{\Gamma(a+b)} {}_1F_1(a; a+b; t) \\
 \mu &= \frac{a}{a+b} \\
 \mu_2 &= \frac{ab(a+b+1)}{(a+b)^2} \\
 \gamma_1 &= 2 \frac{b-a}{a+b+2} \sqrt{\frac{a+b+1}{ab}} \\
 \gamma_2 &= \frac{6(a^3 + a^2(1-2b) + b^2(b+1) - 2ab(b+2))}{ab(a+b+2)(a+b+3)} \\
 m_d &= \frac{(a-1)}{(a+b-2)} a + b \neq 2
 \end{aligned}$$

where $I(x; a, b)$ is the regularized incomplete Beta function. $f(x; a, 1)$ is also called the Power-function distribution.

$$l_{\mathbf{x}}(a, b) = -N \log \Gamma(a+b) + N \log \Gamma(a) + N \log \Gamma(b) - N(a-1) \overline{\log \mathbf{x}} - N(b-1) \overline{\log(1-\mathbf{x})}$$

Implementation: `scipy.stats.beta`

Beta Prime Distribution

There are two shape parameters $a, b > 0$ and the support is $x \in [0, \infty)$. Note the CDF evaluation uses Eq. 3.194.1 on pg. 313 of Gradshteyn & Ryzhik (sixth edition).

$$\begin{aligned}
 f(x; \alpha, \beta) &= \frac{\Gamma(\alpha+\beta)}{\Gamma(\alpha)\Gamma(\beta)} x^{\alpha-1} (1+x)^{-\alpha-\beta} \\
 F(x; \alpha, \beta) &= \frac{\Gamma(\alpha+\beta)}{\alpha\Gamma(\alpha)\Gamma(\beta)} x^\alpha {}_2F_1(\alpha+\beta, \alpha; 1+\alpha; -x) \\
 G(q; \alpha, \beta) &= F^{-1}(x; \alpha, \beta) \\
 \mu'_n &= \begin{cases} \frac{\Gamma(n+\alpha)\Gamma(\beta-n)}{\Gamma(\alpha)\Gamma(\beta)} = \frac{(\alpha)_n}{(\beta-n)_n} & \beta > n \\ \infty & \text{otherwise} \end{cases}
 \end{aligned}$$

Therefore,

$$\begin{aligned}\mu &= \frac{\alpha}{\beta - 1} \quad \text{for } \beta > 1 \\ \mu_2 &= \frac{\alpha(\alpha + 1)}{(\beta - 2)(\beta - 1)} - \frac{\alpha^2}{(\beta - 1)^2} \quad \text{for } \beta > 2 \\ \gamma_1 &= \frac{\frac{\alpha(\alpha+1)(\alpha+2)}{(\beta-3)(\beta-2)(\beta-1)} - 3\mu\mu_2 - \mu^3}{\mu_2^{3/2}} \quad \text{for } \beta > 3 \\ \gamma_2 &= \frac{\mu_4}{\mu_2^2} - 3 \\ \mu_4 &= \frac{\alpha(\alpha + 1)(\alpha + 2)(\alpha + 3)}{(\beta - 4)(\beta - 3)(\beta - 2)(\beta - 1)} - 4\mu\mu_3 - 6\mu^2\mu_2 - \mu^4 \quad \text{for } \beta > 4\end{aligned}$$

Implementation: `scipy.stats.betaprime`

Bradford Distribution

There is one shape parameter, $c > 0$, and the support is $x \in [0, 1]$.

$$\begin{aligned}\text{Let } k &= \log(1 + c) \\ \text{Then} \\ f(x; c) &= \frac{c}{k(1 + cx)} \\ F(x; c) &= \frac{\log(1 + cx)}{k} \\ G(q; c) &= \frac{(1 + c)^q - 1}{c} \\ M(t) &= \frac{1}{k} e^{-t/c} \left[\text{Ei} \left(t + \frac{t}{c} \right) - \text{Ei} \left(\frac{t}{c} \right) \right] \\ \mu &= \frac{c - k}{ck} \\ \mu_2 &= \frac{(c + 2)k - 2c}{2ck^2} \\ \gamma_1 &= \frac{\sqrt{2} (12c^2 - 9kc(c + 2) + 2k^2(c(c + 3) + 3))}{\sqrt{c(c(k - 2) + 2k)} (3c(k - 2) + 6k)} \\ \gamma_2 &= \frac{c^3(k - 3)(k(3k - 16) + 24) + 12kc^2(k - 4)(k - 3) + 6ck^2(3k - 14) + 12k^3}{3c(c(k - 2) + 2k)^2} \\ m_d &= 0 \\ m_n &= \sqrt{1 + c} - 1 \\ h[X] &= \frac{1}{2} \log(1 + c) - \log \left(\frac{c}{\log(1 + c)} \right)\end{aligned}$$

where $\text{Ei}(z)$ is the exponential integral function.

Implementation: `scipy.stats.bradford`

Burr Distribution

There are two shape parameters $c, d > 0$ and the support is $x \in [0, \infty)$.

$$\begin{aligned} \text{Let } k &= \Gamma(d) \Gamma\left(1 - \frac{2}{c}\right) \Gamma\left(\frac{2}{c} + d\right) - \Gamma^2\left(1 - \frac{1}{c}\right) \Gamma^2\left(\frac{1}{c} + d\right) \\ f(x; c, d) &= \frac{cd}{x^{c+1} (1 + x^{-c})^{d+1}} \\ F(x; c, d) &= (1 + x^{-c})^{-d} \\ G(q; c, d) &= (q^{-1/d} - 1)^{-1/c} \\ \mu &= \frac{\Gamma\left(1 - \frac{1}{c}\right) \Gamma\left(\frac{1}{c} + d\right)}{\Gamma(d)} \\ \mu_2 &= \frac{k}{\Gamma^2(d)} \\ \gamma_1 &= \frac{1}{\sqrt{k^3}} \left[2\Gamma^3\left(1 - \frac{1}{c}\right) \Gamma^3\left(\frac{1}{c} + d\right) + \Gamma^2(d) \Gamma\left(1 - \frac{3}{c}\right) \Gamma\left(\frac{3}{c} + d\right) \right. \\ &\quad \left. - 3\Gamma(d) \Gamma\left(1 - \frac{2}{c}\right) \Gamma\left(1 - \frac{1}{c}\right) \Gamma\left(\frac{1}{c} + d\right) \Gamma\left(\frac{2}{c} + d\right) \right] \\ \gamma_2 &= -3 + \frac{1}{k^2} \left[6\Gamma(d) \Gamma\left(1 - \frac{2}{c}\right) \Gamma^2\left(1 - \frac{1}{c}\right) \Gamma^2\left(\frac{1}{c} + d\right) \Gamma\left(\frac{2}{c} + d\right) \right. \\ &\quad \left. - 3\Gamma^4\left(1 - \frac{1}{c}\right) \Gamma^4\left(\frac{1}{c} + d\right) + \Gamma^3(d) \Gamma\left(1 - \frac{4}{c}\right) \Gamma\left(\frac{4}{c} + d\right) \right. \\ &\quad \left. - 4\Gamma^2(d) \Gamma\left(1 - \frac{3}{c}\right) \Gamma\left(1 - \frac{1}{c}\right) \Gamma\left(\frac{1}{c} + d\right) \Gamma\left(\frac{3}{c} + d\right) \right] \\ m_d &= \left(\frac{cd - 1}{c + 1}\right)^{1/c} \quad \text{if } cd > 1, \text{ otherwise } 0 \\ m_n &= (2^{1/d} - 1)^{-1/c} \end{aligned}$$

Implementation: `scipy.stats.burr`

Burr12 Distribution

There are two shape parameters $c, d > 0$ and the support is $x \in [0, \infty)$. The Burr12 distribution is also known as the Singh-Maddala distribution.

$$\begin{aligned}
 f(x; c, d) &= cd \frac{x^{c-1}}{(1+x^c)^{d+1}} \\
 F(x; c, d) &= 1 - (1+x^c)^{-d} \\
 G(q; c, d) &= \left((1-q)^{-1/d} - 1 \right)^{-1/c} \\
 S(x; c, d) &= (1+x^c)^{-d} \\
 \mu &= dB \left(d - \frac{1}{c}, 1 + \frac{1}{c} \right) \\
 \mu_n &= dB \left(d - \frac{n}{c}, 1 + \frac{n}{c} \right) \\
 m_d &= \left(\frac{c-1}{cd+1} \right)^{1/c} \quad \text{if } c > 1, \text{ otherwise } 0 \\
 m_n &= \left(2^{1/d} - 1 \right)^{-1/c}
 \end{aligned}$$

where $B(a, b) = \frac{\Gamma(a)\Gamma(b)}{\Gamma(a+b)}$ is the Beta function.

Implementation: `scipy.stats.burr12`

Cauchy Distribution

The support is $x \in \mathbb{R}$.

$$\begin{aligned}
 f(x) &= \frac{1}{\pi(1+x^2)} \\
 F(x) &= \frac{1}{2} + \frac{1}{\pi} \tan^{-1} x \\
 G(q) &= \tan \left(\pi q - \frac{\pi}{2} \right) \\
 m_d &= 0 \\
 m_n &= 0
 \end{aligned}$$

No finite moments. This is the t distribution with one degree of freedom.

$$\begin{aligned}
 h[X] &= \log(4\pi) \\
 &\approx 2.5310242469692907930.
 \end{aligned}$$

Implementation: `scipy.stats.cauchy`

Chi Distribution

Generated by taking the (positive) square-root of chi-squared variates. The one shape parameter is ν , a positive integer, the degrees of freedom. The support is $x \geq 0$.

$$\begin{aligned}
 f(x; \nu) &= \frac{x^{\nu-1} e^{-x^2/2}}{2^{\nu/2-1} \Gamma(\frac{\nu}{2})} \\
 F(x; \nu) &= \frac{\gamma(\frac{\nu}{2}, \frac{x^2}{2})}{\Gamma(\frac{\nu}{2})} \\
 G(q; \nu) &= \sqrt{2\gamma^{-1}(\frac{\nu}{2}, q\Gamma(\frac{\nu}{2}))} \\
 M(t) &= \Gamma(\frac{\nu}{2}) {}_1F_1\left(\frac{\nu}{2}; \frac{1}{2}; \frac{t^2}{2}\right) + \frac{t}{\sqrt{2}} \Gamma\left(\frac{1+\nu}{2}\right) {}_1F_1\left(\frac{1+\nu}{2}; \frac{3}{2}; \frac{t^2}{2}\right) \\
 \mu &= \frac{\sqrt{2}\Gamma(\frac{\nu+1}{2})}{\Gamma(\frac{\nu}{2})} \\
 \mu_2 &= \nu - \mu^2 \\
 \gamma_1 &= \frac{2\mu^3 + \mu(1 - 2\nu)}{\mu_2^{3/2}} \\
 \gamma_2 &= \frac{2\nu(1 - \nu) - 6\mu^4 + 4\mu^2(2\nu - 1)}{\mu_2^2} \\
 m_d &= \sqrt{\nu - 1} \quad \nu \geq 1 \\
 m_n &= \sqrt{2\gamma^{-1}(\frac{\nu}{2}, \frac{1}{2}\Gamma(\frac{\nu}{2}))}
 \end{aligned}$$

Implementation: `scipy.stats.chi`

Chi-squared Distribution

This is the gamma distribution with $L = 0.0$ and $S = 2.0$ and $\alpha = \nu/2$ where ν is called the degrees of freedom. If $Z_1 \dots Z_\nu$ are all standard normal distributions, then $W = \sum_k Z_k^2$ has (standard) chi-square distribution with ν degrees of freedom.

The standard form (most often used in standard form only) has support $x \geq 0$.

$$\begin{aligned}
 f(x; \alpha) &= \frac{1}{2\Gamma(\frac{\nu}{2})} \left(\frac{x}{2}\right)^{\nu/2-1} e^{-x/2} \\
 F(x; \alpha) &= \frac{\gamma(\frac{\nu}{2}, \frac{x}{2})}{\Gamma(\frac{\nu}{2})} \\
 G(q; \alpha) &= 2\gamma^{-1}\left(\frac{\nu}{2}, q\Gamma(\frac{\nu}{2})\right)
 \end{aligned}$$

where γ is the lower incomplete gamma function, $\gamma(s, x) = \int_0^x t^{s-1} e^{-t} dt$.

$$M(t) = \frac{\Gamma(\frac{\nu}{2})}{(\frac{1}{2} - t)^{\nu/2}}$$

$$\begin{aligned}\mu &= \nu \\ \mu_2 &= 2\nu \\ \gamma_1 &= \frac{2\sqrt{2}}{\sqrt{\nu}} \\ \gamma_2 &= \frac{12}{\nu} \\ m_d &= \frac{\nu}{2} - 1\end{aligned}$$

Implementation: `scipy.stats.chi2`

Cosine Distribution

Approximation to the normal distribution. The support is $[-\pi, \pi]$.

$$\begin{aligned}f(x) &= \frac{1}{2\pi} (1 + \cos x) \\ F(x) &= \frac{1}{2\pi} (\pi + x + \sin x) \\ G(q) &= F^{-1}(q) \\ M(t) &= \frac{\sinh(\pi t)}{\pi t (1 + t^2)} \\ \mu = m_d = m_n &= 0 \\ \mu_2 &= \frac{\pi^2}{3} - 2 \\ \gamma_1 &= 0 \\ \gamma_2 &= \frac{-6(\pi^4 - 90)}{5(\pi^2 - 6)^2}\end{aligned}$$

$$\begin{aligned}h[X] &= \log(4\pi) - 1 \\ &\approx 1.531024242469692907930.\end{aligned}$$

Implementation: `scipy.stats.cosine`

Double Gamma Distribution

The double gamma is the signed version of the Gamma distribution. For $\alpha > 0$:

$$\begin{aligned}f(x; \alpha) &= \frac{1}{2\Gamma(\alpha)} |x|^{\alpha-1} e^{-|x|} \\ F(x; \alpha) &= \begin{cases} \frac{1}{2} - \frac{\gamma(\alpha, |x|)}{2\Gamma(\alpha)} & x \leq 0 \\ \frac{1}{2} + \frac{\gamma(\alpha, |x|)}{2\Gamma(\alpha)} & x > 0 \end{cases} \\ G(q; \alpha) &= \begin{cases} -\gamma^{-1}(\alpha, |2q - 1|\Gamma(\alpha)) & q \leq \frac{1}{2} \\ \gamma^{-1}(\alpha, |2q - 1|\Gamma(\alpha)) & q > \frac{1}{2} \end{cases} \\ M(t) &= \frac{1}{2(1-t)^\alpha} + \frac{1}{2(1+t)^\alpha}\end{aligned}$$

$$\begin{aligned}
 \mu = m_n &= 0 \\
 \mu_2 &= \alpha(\alpha + 1) \\
 \gamma_1 &= 0 \\
 \gamma_2 &= \frac{(\alpha + 2)(\alpha + 3)}{\alpha(\alpha + 1)} - 3 \\
 m_d &= \text{NA}
 \end{aligned}$$

Implementation: `scipy.stats.dgamma`

Double Weibull Distribution

This is a signed form of the Weibull distribution. There is one shape parameter $c > 0$. Support is $x \in \mathbb{R}$.

$$\begin{aligned}
 f(x; c) &= \frac{c}{2} |x|^{c-1} \exp(-|x|^c) \\
 F(x; c) &= \begin{cases} \frac{1}{2} \exp(-|x|^c) & x \leq 0 \\ 1 - \frac{1}{2} \exp(-|x|^c) & x > 0 \end{cases} \\
 G(q; c) &= \begin{cases} -\log^{1/c}\left(\frac{1}{2q}\right) & q \leq \frac{1}{2} \\ \log^{1/c}\left(\frac{1}{2q-1}\right) & q > \frac{1}{2} \end{cases} \\
 \mu'_n = \mu_n &= \begin{cases} \Gamma\left(1 + \frac{n}{c}\right) & n \text{ even} \\ 0 & n \text{ odd} \end{cases}
 \end{aligned}$$

$$\begin{aligned}
 m_n = \mu &= 0 \\
 \mu_2 &= \Gamma\left(\frac{c+2}{c}\right) \\
 \gamma_1 &= 0 \\
 \gamma_2 &= \frac{\Gamma\left(1 + \frac{4}{c}\right)}{\Gamma^2\left(1 + \frac{2}{c}\right)} \\
 m_d &= \text{NA bimodal}
 \end{aligned}$$

Implementation: `scipy.stats.dweibull`

Erlang Distribution

This is just the Gamma distribution with shape parameter $\alpha = n$ an integer.

Implementation: `scipy.stats.erlang`

Exponential Distribution

This is a special case of the Gamma (and Erlang) distributions with shape parameter ($\alpha = 1$) and the same location and scale parameters. The standard form is therefore ($x \geq 0$)

$$\begin{aligned}
 f(x) &= e^{-x} \\
 F(x) &= \gamma(1, x) = 1 - e^{-x} \\
 G(q) &= -\log(1 - q) \\
 \mu'_n &= n!
 \end{aligned}$$

$$M(t) = \frac{1}{1-t}$$

$$\mu = 1$$

$$\mu_2 = 1$$

$$\gamma_1 = 2$$

$$\gamma_2 = 6$$

$$m_d = 0$$

$$h[X] = 1.$$

Implementation: `scipy.stats.expon`

Exponentiated Weibull Distribution

Two positive shape parameters $a, c > 0$, and the support is $x \in [0, \infty)$.

$$f(x; a, c) = ac [1 - \exp(-x^c)]^{a-1} \exp(-x^c) x^{c-1}$$

$$F(x; a, c) = [1 - \exp(-x^c)]^a$$

$$G(q; a, c) = \left[-\log(1 - q^{1/a}) \right]^{1/c}$$

Implementation: `scipy.stats.exponweib`

Exponential Power Distribution

One positive shape parameter b . The support is $x \geq 0$.

$$f(x; b) = ebx^{b-1} \exp(x^b - e^{x^b})$$

$$F(x; b) = 1 - \exp(1 - e^{x^b})$$

$$G(q; b) = \log(1 - \log(1 - q))^{1/b}$$

Implementation: `scipy.stats.exponpow`

Fatigue Life (Birnbaum-Saunders) Distribution

This distribution's pdf is the average of the inverse-Gaussian ($\mu = 1$) and reciprocal inverse-Gaussian pdf ($\mu = 1$). We follow the notation of JKB here with $\beta = S$. There is one shape parameter $c > 0$, and the support is $x \geq 0$.

$$f(x; c) = \frac{x+1}{2c\sqrt{2\pi}x^3} \exp\left(-\frac{(x-1)^2}{2xc^2}\right)$$

$$F(x; c) = \Phi\left(\frac{1}{c}\left(\sqrt{x} - \frac{1}{\sqrt{x}}\right)\right)$$

$$G(q; c) = \frac{1}{4} \left[c\Phi^{-1}(q) + \sqrt{c^2(\Phi^{-1}(q))^2 + 4} \right]^2$$

$$M(t) = c\sqrt{2\pi} \exp\left(\frac{1}{c^2}\left(1 - \sqrt{1 - 2c^2t}\right)\right) \left(1 + \frac{1}{\sqrt{1 - 2c^2t}}\right)$$

$$\begin{aligned}\mu &= \frac{c^2}{2} + 1 \\ \mu_2 &= c^2 \left(\frac{5}{4}c^2 + 1 \right) \\ \gamma_1 &= \frac{4c\sqrt{11c^2 + 6}}{(5c^2 + 4)^{3/2}} \\ \gamma_2 &= \frac{6c^2(93c^2 + 41)}{(5c^2 + 4)^2}\end{aligned}$$

Implementation: `scipy.stats.fatiguelife`

Fisk (Log Logistic) Distribution

Special case of the Burr distribution with $d = 1$. There is one shape parameter $c > 0$ and the support is $x \in [0, \infty)$.

$$\begin{aligned}\text{Let } k &= \Gamma\left(1 - \frac{2}{c}\right) \Gamma\left(\frac{2}{c} + 1\right) - \Gamma^2\left(1 - \frac{1}{c}\right) \Gamma^2\left(\frac{1}{c} + 1\right) \\ f(x; c, d) &= \frac{cx^{c-1}}{(1+x^c)^2} \\ F(x; c, d) &= (1+x^{-c})^{-1} \\ G(q; c, d) &= (q^{-1} - 1)^{-1/c} \\ \mu &= \Gamma\left(1 - \frac{1}{c}\right) \Gamma\left(\frac{1}{c} + 1\right) \\ \mu_2 &= k \\ \gamma_1 &= \frac{1}{\sqrt{k^3}} \left[2\Gamma^3\left(1 - \frac{1}{c}\right) \Gamma^3\left(\frac{1}{c} + 1\right) + \Gamma\left(1 - \frac{3}{c}\right) \Gamma\left(\frac{3}{c} + 1\right) \right. \\ &\quad \left. - 3\Gamma\left(1 - \frac{2}{c}\right) \Gamma\left(1 - \frac{1}{c}\right) \Gamma\left(\frac{1}{c} + 1\right) \Gamma\left(\frac{2}{c} + 1\right) \right] \\ \gamma_2 &= -3 + \frac{1}{k^2} \left[6\Gamma\left(1 - \frac{2}{c}\right) \Gamma^2\left(1 - \frac{1}{c}\right) \Gamma^2\left(\frac{1}{c} + 1\right) \Gamma\left(\frac{2}{c} + 1\right) \right. \\ &\quad \left. - 3\Gamma^4\left(1 - \frac{1}{c}\right) \Gamma^4\left(\frac{1}{c} + 1\right) + \Gamma\left(1 - \frac{4}{c}\right) \Gamma\left(\frac{4}{c} + 1\right) \right. \\ &\quad \left. - 4\Gamma\left(1 - \frac{3}{c}\right) \Gamma\left(1 - \frac{1}{c}\right) \Gamma\left(\frac{1}{c} + 1\right) \Gamma\left(\frac{3}{c} + 1\right) \right] \\ m_d &= \left(\frac{c-1}{c+1}\right)^{1/c} \text{ if } c > 1, \text{ otherwise } 0 \\ m_n &= 1 \\ h[X] &= 2 - \log c\end{aligned}$$

Implementation: `scipy.stats.fisk`

Folded Cauchy Distribution

This formula can be expressed in terms of the standard formulas for the Cauchy distribution (call the cdf $C(x)$ and the pdf $d(x)$). If Y is cauchy then $|Y|$ is folded cauchy. There is one shape parameter c and the support is $x \geq 0$.

$$\begin{aligned} f(x; c) &= \frac{1}{\pi \left(1 + (x - c)^2\right)} + \frac{1}{\pi \left(1 + (x + c)^2\right)} \\ F(x; c) &= \frac{1}{\pi} \tan^{-1}(x - c) + \frac{1}{\pi} \tan^{-1}(x + c) \\ G(q; c) &= F^{-1}(q; c) \end{aligned}$$

No moments

Implementation: `scipy.stats.foldcauchy`

Folded Normal Distribution

If Z is Normal with mean L and $\sigma = S$, then $|Z|$ is a folded normal with shape parameter $c = |L|/S$, location parameter 0 and scale parameter S . This is a special case of the non-central chi distribution with one- degree of freedom and non-centrality parameter c^2 . Note that $c \geq 0$. The standard form of the folded normal is

$$\begin{aligned} f(x; c) &= \sqrt{\frac{2}{\pi}} \cosh(cx) \exp\left(-\frac{x^2 + c^2}{2}\right) \\ F(x; c) &= \Phi(x - c) - \Phi(-x - c) = \Phi(x - c) + \Phi(x + c) - 1 \\ G(q; c) &= F^{-1}(q; c) \\ M(t) &= \exp\left(\frac{t}{2}(t - 2c)\right) (1 + e^{2ct}) \\ k &= \operatorname{erf}\left(\frac{c}{\sqrt{2}}\right) \\ p &= \exp\left(-\frac{c^2}{2}\right) \\ \mu &= \sqrt{\frac{2}{\pi}} p + ck \\ \mu_2 &= c^2 + 1 - \mu^2 \\ \gamma_1 &= \frac{\sqrt{\frac{2}{\pi}} p^3 \left(4 - \frac{\pi}{p^2} (2c^2 + 1)\right) + 2ck (6p^2 + 3cpk\sqrt{2\pi} + \pi c (k^2 - 1))}{\pi \mu_2^{3/2}} \\ \gamma_2 &= \frac{c^4 + 6c^2 + 3 + 6(c^2 + 1)\mu^2 - 3\mu^4 - 4p\mu \left(\sqrt{\frac{2}{\pi}} (c^2 + 2) + \frac{ck}{p} (c^2 + 3)\right)}{\mu_2^2} \end{aligned}$$

Implementation: `scipy.stats.foldnorm`

Fratio (or F) Distribution

The distribution of (X_1/X_2) (ν_2/ν_1) if X_1 is chi-squared with ν_1 degrees of freedom and X_2 is chi-squared with ν_2 degrees of freedom. The support is $x \geq 0$.

$$\begin{aligned}
 f(x; \nu_1, \nu_2) &= \frac{\nu_2^{\nu_2/2} \nu_1^{\nu_1/2} x^{\nu_1/2-1}}{(\nu_2 + \nu_1 x)^{(\nu_1+\nu_2)/2} B\left(\frac{\nu_1}{2}, \frac{\nu_2}{2}\right)} \\
 F(x; \nu_1, \nu_2) &= I\left(\frac{\nu_1 x}{\nu_2 + \nu_1 x}; \frac{\nu_1}{2}, \frac{\nu_2}{2}\right) \\
 G(q; \nu_1, \nu_2) &= \left(\frac{\nu_2}{I^{-1}(q; \nu_1/2, \nu_2/2)} - \frac{\nu_1}{\nu_2}\right)^{-1} \\
 \mu &= \frac{\nu_2}{\nu_2 - 2} \quad \text{for } \nu_2 > 2 \\
 \mu_2 &= \frac{2\nu_2^2(\nu_1 + \nu_2 - 2)}{\nu_1(\nu_2 - 2)^2(\nu_2 - 4)} \quad \text{for } \nu_2 > 4 \\
 \gamma_1 &= \frac{2(2\nu_1 + \nu_2 - 2)}{\nu_2 - 6} \sqrt{\frac{2(\nu_2 - 4)}{\nu_1(\nu_1 + \nu_2 - 2)}} \quad \text{for } \nu_2 > 6 \\
 \gamma_2 &= \frac{3(8 + (\nu_2 - 6)\gamma_1^2)}{2\nu_2 - 16} \quad \text{for } \nu_2 > 8
 \end{aligned}$$

where $I(x; a, b) = I_x(a, b)$ is the regularized incomplete Beta function.

Implementation: `scipy.stats.f`

Gamma Distribution

The standard form for the gamma distribution is ($\alpha > 0$) valid for $x \geq 0$.

$$\begin{aligned}
 f(x; \alpha) &= \frac{1}{\Gamma(\alpha)} x^{\alpha-1} e^{-x} \\
 F(x; \alpha) &= \frac{\gamma(\alpha, x)}{\Gamma(\alpha)} \\
 G(q; \alpha) &= \gamma^{-1}(\alpha, q\Gamma(\alpha))
 \end{aligned}$$

where γ is the lower incomplete gamma function, $\gamma(s, x) = \int_0^x t^{s-1} e^{-t} dt$.

$$M(t) = \frac{1}{(1-t)^\alpha}$$

$$\begin{aligned}
 \mu &= \alpha \\
 \mu_2 &= \alpha \\
 \gamma_1 &= \frac{2}{\sqrt{\alpha}} \\
 \gamma_2 &= \frac{6}{\alpha} \\
 m_d &= \alpha - 1
 \end{aligned}$$

$$h[X] = \Psi(\alpha) [1 - a] + a + \log \Gamma(\alpha)$$

where

$$\Psi(\alpha) = \frac{\Gamma'(\alpha)}{\Gamma(\alpha)}.$$

Implementation: `scipy.stats.gamma`

Generalized Logistic Distribution

Has been used in the analysis of extreme values. There is one shape parameter $c > 0$. The support is $x \geq 0$.

$$\begin{aligned} f(x; c) &= \frac{c \exp(-x)}{[1 + \exp(-x)]^{c+1}} \\ F(x; c) &= \frac{1}{[1 + \exp(-x)]^c} \\ G(q; c) &= -\log(q^{-1/c} - 1) \\ M(t) &= \frac{c}{1-t} {}_2F_1(1+c, 1-t; 2-t; -1) \end{aligned}$$

$$\begin{aligned} \mu &= \gamma + \psi_0(c) \\ \mu_2 &= \frac{\pi^2}{6} + \psi_1(c) \\ \gamma_1 &= \frac{\psi_2(c) + 2\zeta(3)}{\mu_2^{3/2}} \\ \gamma_2 &= \frac{\left(\frac{\pi^4}{15} + \psi_3(c)\right)}{\mu_2^2} \\ m_d &= \log c \\ m_n &= -\log(2^{1/c} - 1) \end{aligned}$$

Note that the polygamma function is

$$\begin{aligned} \psi_n(z) &= \frac{d^{n+1}}{dz^{n+1}} \log \Gamma(z) \\ &= (-1)^{n+1} n! \sum_{k=0}^{\infty} \frac{1}{(z+k)^{n+1}} \\ &= (-1)^{n+1} n! \zeta(n+1, z) \end{aligned}$$

where $\zeta(k, x)$ is a generalization of the Riemann zeta function called the Hurwitz zeta function. Note that $\zeta(n) \equiv \zeta(n, 1)$.

Implementation: `scipy.stats.genlogistic`

Generalized Pareto Distribution

There is one shape parameter $c \neq 0$. The support is $x \geq 0$ if $c > 0$, and $0 \leq x < \frac{1}{|c|}$ if c is negative.

$$\begin{aligned} f(x; c) &= (1 + cx)^{-1-\frac{1}{c}} \\ F(x; c) &= 1 - \frac{1}{(1 + cx)^{1/c}} \\ G(q; c) &= \frac{1}{c} \left[\left(\frac{1}{1-q} \right)^c - 1 \right] \\ M(t) &= \begin{cases} \left(-\frac{t}{c}\right)^{\frac{1}{c}} e^{-\frac{t}{c}} \left[\Gamma\left(1 - \frac{1}{c}\right) + \left(\gamma\left(-\frac{1}{c}, -\frac{t}{c}\right) / \Gamma\left(\frac{1}{c}\right)\right) - \pi \csc\left(\frac{\pi}{c}\right) / \Gamma\left(\frac{1}{c}\right) \right] & c > 0 \\ \left(\frac{|c|}{t}\right)^{1/|c|} \Gamma\left(\frac{1}{|c|}, \frac{t}{|c|}\right) \frac{1}{\Gamma\left(\frac{1}{|c|}\right)} & c < 0 \end{cases} \end{aligned}$$

$$\mu'_n = \frac{(-1)^n}{c^n} \sum_{k=0}^n \binom{n}{k} \frac{(-1)^k}{1 - ck} \quad \text{if } cn < 1$$

$$\mu'_1 = \frac{1}{1 - c} \quad c < 1$$

$$\mu'_2 = \frac{2}{(1 - 2c)(1 - c)} \quad c < \frac{1}{2}$$

$$\mu'_3 = \frac{6}{(1 - c)(1 - 2c)(1 - 3c)} \quad c < \frac{1}{3}$$

$$\mu'_4 = \frac{24}{(1 - c)(1 - 2c)(1 - 3c)(1 - 4c)} \quad c < \frac{1}{4}$$

Thus,

$$\mu = \mu'_1$$

$$\mu_2 = \mu'_2 - \mu^2$$

$$\gamma_1 = \frac{\mu'_3 - 3\mu\mu_2 - \mu^3}{\mu_2^{3/2}}$$

$$\gamma_2 = \frac{\mu'_4 - 4\mu\mu_3 - 6\mu^2\mu_2 - \mu^4}{\mu_2^2} - 3$$

$$h[X] = 1 + c \quad c > 0$$

Implementation: `scipy.stats.genpareto`

Generalized Exponential Distribution

Three positive shape parameters $a, b, c > 0$ with support $x \geq 0$.

$$f(x; a, b, c) = (a + b(1 - e^{-cx})) \exp\left(ax - bx + \frac{b}{c}(1 - e^{-cx})\right)$$

$$F(x; a, b, c) = 1 - \exp\left(ax - bx + \frac{b}{c}(1 - e^{-cx})\right)$$

$$G(q; a, b, c) = F^{-1}$$

Implementation: `scipy.stats.genexpon`

Generalized Extreme Value Distribution

Extreme value distributions with one shape parameter c .

If $c > 0$, the support is $-\infty < x \leq 1/c$. If $c < 0$, the support is $\frac{1}{c} \leq x < \infty$.

$$f(x; c) = \exp\left(-(1 - cx)^{1/c}\right) (1 - cx)^{1/c-1}$$

$$F(x; c) = \exp\left(-(1 - cx)^{1/c}\right)$$

$$G(q; c) = \frac{1}{c} (1 - (-\log q)^c)$$

$$\mu'_n = \frac{1}{c^n} \sum_{k=0}^n \binom{n}{k} (-1)^k \Gamma(ck + 1) \quad \text{if } cn > -1$$

So,

$$\begin{aligned}\mu'_1 &= \frac{1}{c} (1 - \Gamma(1 + c)) \quad c > -1 \\ \mu'_2 &= \frac{1}{c^2} (1 - 2\Gamma(1 + c) + \Gamma(1 + 2c)) \quad c > -\frac{1}{2} \\ \mu'_3 &= \frac{1}{c^3} (1 - 3\Gamma(1 + c) + 3\Gamma(1 + 2c) - \Gamma(1 + 3c)) \quad c > -\frac{1}{3} \\ \mu'_4 &= \frac{1}{c^4} (1 - 4\Gamma(1 + c) + 6\Gamma(1 + 2c) - 4\Gamma(1 + 3c) + \Gamma(1 + 4c)) \quad c > -\frac{1}{4}\end{aligned}$$

For $c = 0$ the distribution is the same as the (left-skewed) Gumbel distribution, and the support is \mathbb{R} .

$$\begin{aligned}f(x; 0) &= \exp(-e^{-x}) e^{-x} \\ F(x; 0) &= \exp(-e^{-x}) \\ G(q; 0) &= -\log(-\log q)\end{aligned}$$

$$\begin{aligned}\mu &= \gamma = -\psi_0(1) \\ \mu_2 &= \frac{\pi^2}{6} \\ \gamma_1 &= \frac{12\sqrt{6}}{\pi^3} \zeta(3) \\ \gamma_2 &= \frac{12}{5}\end{aligned}$$

Implementation: `scipy.stats.genextreme`

Generalized Gamma Distribution

A general probability form that reduces to many common distributions. There are two shape parameters $a > 0$ and $c \neq 0$. The support is $x \geq 0$.

$$\begin{aligned}f(x; a, c) &= \frac{|c| x^{ca-1}}{\Gamma(a)} \exp(-x^c) \\ F(x; a, c) &= \begin{cases} \frac{\gamma(a, x^c)}{\Gamma(a)} & c > 0 \\ 1 - \frac{\gamma(a, x^c)}{\Gamma(a)} & c < 0 \end{cases} \\ G(q; a, c) &= \begin{cases} \gamma^{-1}(a, \Gamma(a) q)^{1/c} & c > 0 \\ \gamma^{-1}(a, \Gamma(a) (1 - q))^{1/c} & c < 0 \end{cases}\end{aligned}$$

where γ is the lower incomplete gamma function, $\gamma(s, x) = \int_0^x t^{s-1} e^{-t} dt$.

$$\begin{aligned}\mu'_n &= \frac{\Gamma(a + \frac{n}{c})}{\Gamma(a)} \\ \mu &= \frac{\Gamma(a + \frac{1}{c})}{\Gamma(a)} \\ \mu_2 &= \frac{\Gamma(a + \frac{2}{c})}{\Gamma(a)} - \mu^2 \\ \gamma_1 &= \frac{\Gamma(a + \frac{3}{c})/\Gamma(a) - 3\mu\mu_2 - \mu^3}{\mu_2^{3/2}} \\ \gamma_2 &= \frac{\Gamma(a + \frac{4}{c})/\Gamma(a) - 4\mu\mu_3 - 6\mu^2\mu_2 - \mu^4}{\mu_2^2} - 3 \\ m_d &= \left(\frac{ac - 1}{c}\right)^{1/c}\end{aligned}$$

Special cases are Weibull ($a = 1$), half-normal ($a = 1/2, c = 2$) and ordinary gamma distributions $c = 1$. If $c = -1$ then it is the inverted gamma distribution.

$$h[X] = a - a\Psi(a) + \frac{1}{c}\Psi(a) + \log \Gamma(a) - \log |c|.$$

Implementation: `scipy.stats.gengamma`

Generalized Half-Logistic Distribution

One shape parameter $c > 0$ and support $x \in [0, 1/c]$.

$$\begin{aligned}f(x; c) &= \frac{2(1 - cx)^{\frac{1}{c}-1}}{\left(1 + (1 - cx)^{1/c}\right)^2} \\ F(x; c) &= \frac{1 - (1 - cx)^{1/c}}{1 + (1 - cx)^{1/c}} \\ G(q; c) &= \frac{1}{c} \left[1 - \left(\frac{1 - q}{1 + q} \right)^c \right] \\ h[X] &= 2 - (2c + 1) \log 2.\end{aligned}$$

Implementation: `scipy.stats.genhalflogistic`

Generalized Inverse Gaussian Distribution

The probability density function is given by:

$$f(x; p, b) = x^{p-1} \exp(-b(x + 1/x)/2) / (2K_p(b)),$$

where $x > 0$ is a real number and the parameters p, b satisfy $b > 0$. K_v is the modified Bessel function of second kind of order v (`scipy.special.kv`).

If X is `geninvgauss(p, b)`, then the distribution of $1/X$ is `geninvgauss(-p, b)`. The inverse Gaussian distribution (`scipy.stats.invgauss`) is a special case with $p=-1/2$.

Implementation: `scipy.stats.geninvgauss`

Generalized Normal Distribution

This distribution is also known as the exponential power distribution. It has a single shape parameter $\beta > 0$. It reduces to a number of common distributions.

Functions

$$f(x; \beta) = \frac{\beta}{2\Gamma(1/\beta)} e^{-|x|^\beta}$$

$$F(x; \beta) = \frac{1}{2} + \operatorname{sgn}(x) \frac{\gamma(1/\beta, x^\beta)}{2\Gamma(1/\beta)}$$

γ is the lower incomplete gamma function. $\gamma(s, x) = \int_0^x t^{s-1} e^{-t} dt$.

$$h[X; \beta] = \frac{1}{\beta} - \log\left(\frac{\beta}{2\Gamma(1/\beta)}\right)$$

Moments

$$\begin{aligned} \mu &= 0 \\ m_n &= 0 \\ m_d &= 0 \\ \mu_2 &= \frac{\Gamma(3/\beta)}{\gamma(1/\beta)} \\ \gamma_1 &= 0 \\ \gamma_2 &= \frac{\Gamma(5/\beta)\Gamma(1/\beta)}{\Gamma(3/\beta)^2} - 3 \end{aligned}$$

Special Cases

- Laplace distribution ($\beta = 1$)
- Normal distribution with $\mu_2 = 1/2$ ($\beta = 2$)
- Uniform distribution over the interval $[-1, 1]$ ($\beta \rightarrow \infty$)

Sources

- https://en.wikipedia.org/wiki/Generalized_normal_distribution#Version_1
- https://en.wikipedia.org/wiki/Incomplete_gamma_function#Lower_incomplete_Gamma_function

Implementation: `scipy.stats.gennorm`

Gilbrat Distribution

Special case of the log-normal with $\sigma = 1$ and $S = 1.0$, typically also $L = 0.0$.)

$$\begin{aligned} f(x; \sigma) &= \frac{1}{x\sqrt{2\pi}} \exp\left(-\frac{1}{2}(\log x)^2\right) \\ F(x; \sigma) &= \Phi(\log x) = \frac{1}{2} \left(1 + \operatorname{erf}\left(\frac{\log x}{\sqrt{2}}\right)\right) \\ G(q; \sigma) &= \exp\left(\Phi^{-1}(q)\right) \end{aligned}$$

$$\begin{aligned} \mu &= \sqrt{e} \\ \mu_2 &= e[e - 1] \\ \gamma_1 &= \sqrt{e - 1}(2 + e) \\ \gamma_2 &= e^4 + 2e^3 + 3e^2 - 6 \end{aligned}$$

$$\begin{aligned} h[X] &= \log\left(\sqrt{2\pi e}\right) \\ &\approx 1.4189385332046727418 \end{aligned}$$

Implementation: `scipy.stats.gilbrat`

Gompertz (Truncated Gumbel) Distribution

For $x \geq 0$ and $c > 0$. In JKB the two shape parameters b, a are reduced to the single shape-parameter $c = b/a$. As a is just a scale parameter when $a \neq 0$. If $a = 0$, the distribution reduces to the exponential distribution scaled by $1/b$. Thus, the standard form is given as

$$\begin{aligned} f(x; c) &= ce^x \exp(-c(e^x - 1)) \\ F(x; c) &= 1 - \exp(-c(e^x - 1)) \\ G(q; c) &= \log\left(1 - \frac{1}{c} \log(1 - q)\right) \\ h[X] &= 1 - \log(c) - e^c \operatorname{Ei}(1, c), \end{aligned}$$

where

$$\operatorname{Ei}(n, x) = \int_1^\infty t^{-n} \exp(-xt) dt$$

Implementation: `scipy.stats.gompertz`

Gumbel (LogWeibull, Fisher-Tippetts, Type I Extreme Value) Distribution

One of a class of extreme value distributions (right-skewed).

$$\begin{aligned} f(x) &= \exp\left(-\left(x + e^{-x}\right)\right) \\ F(x) &= \exp\left(-e^{-x}\right) \\ G(q) &= -\log\left(-\log(q)\right) \\ M(t) &= \Gamma(1 - t) \end{aligned}$$

$$\begin{aligned}\mu &= \gamma = -\psi_0(1) \\ \mu_2 &= \frac{\pi^2}{6} \\ \gamma_1 &= \frac{12\sqrt{6}}{\pi^3} \zeta(3) \\ \gamma_2 &= \frac{12}{5} \\ m_d &= 0 \\ m_n &= -\log(\log 2)\end{aligned}$$

$$h[X] \approx 1.0608407169541684911$$

Implementation: `scipy.stats.gumbel_r`

Gumbel Left-skewed (for minimum order statistic) Distribution

$$\begin{aligned}f(x) &= \exp(x - e^x) \\ F(x) &= 1 - \exp(-e^x) \\ G(q) &= \log(-\log(1 - q)) \\ M(t) &= \Gamma(1 + t)\end{aligned}$$

Note, that μ is negative the mean for the right-skewed distribution. Similar for median and mode. All other moments are the same.

$$h[X] \approx 1.0608407169541684911.$$

Implementation: `scipy.stats.gumbel_l`

HalfCauchy Distribution

If Z is Hyperbolic Secant distributed then e^Z is Half-Cauchy distributed. Also, if W is (standard) Cauchy distributed, then $|W|$ is Half-Cauchy distributed. Special case of the Folded Cauchy distribution with $c = 0$. The support is $x \geq 0$. The standard form is

$$\begin{aligned}f(x) &= \frac{2}{\pi(1+x^2)} \\ F(x) &= \frac{2}{\pi} \arctan(x) \\ G(q) &= \tan\left(\frac{\pi}{2}q\right)\end{aligned}$$

$$M(t) = \cos t + \frac{2}{\pi} [\text{Si}(t) \cos t - \text{Ci}(-t) \sin t]$$

where $\text{Si}(t) = \int_0^t \frac{\sin x}{x} dx$, $\text{Ci}(t) = -\int_t^\infty \frac{\cos x}{x} dx$.

$$\begin{aligned}m_d &= 0 \\ m_n &= \tan\left(\frac{\pi}{4}\right)\end{aligned}$$

No moments, as the integrals diverge.

$$\begin{aligned}h[X] &= \log(2\pi) \\ &\approx 1.8378770664093454836.\end{aligned}$$

Implementation: `scipy.stats.halfcauchy`

HalfNormal Distribution

This is a special case of the chi distribution with $L = a$ and $S = b$ and $\nu = 1$. This is also a special case of the folded normal with shape parameter $c = 0$ and $S = S$. If Z is (standard) normally distributed then, $|Z|$ is half-normal. The standard form is

$$\begin{aligned} f(x) &= \sqrt{\frac{2}{\pi}} e^{-x^2/2} \\ F(x) &= 2\Phi(x) - 1 \\ G(q) &= \Phi^{-1}\left(\frac{1+q}{2}\right) \end{aligned}$$

$$M(t) = \sqrt{2\pi} e^{t^2/2} \Phi(t)$$

$$\begin{aligned} \mu &= \sqrt{\frac{2}{\pi}} \\ \mu_2 &= 1 - \frac{2}{\pi} \\ \gamma_1 &= \frac{\sqrt{2}(4-\pi)}{(\pi-2)^{3/2}} \\ \gamma_2 &= \frac{8(\pi-3)}{(\pi-2)^2} \\ m_d &= 0 \\ m_n &= \Phi^{-1}\left(\frac{3}{4}\right) \end{aligned}$$

$$\begin{aligned} h[X] &= \log\left(\sqrt{\frac{\pi e}{2}}\right) \\ &\approx 0.72579135264472743239. \end{aligned}$$

Implementation: `scipy.stats.halfnorm`

Half-Logistic Distribution

In the limit as $c \rightarrow \infty$ for the generalized half-logistic we have the half-logistic defined over $x \geq 0$. Also, the distribution of $|X|$ where X has logistic distribution.

$$\begin{aligned} f(x) &= \frac{2e^{-x}}{(1+e^{-x})^2} = \frac{1}{2} \operatorname{sech}^2\left(\frac{x}{2}\right) \\ F(x) &= \frac{1-e^{-x}}{1+e^{-x}} = \tanh\left(\frac{x}{2}\right) \\ G(q) &= \log\left(\frac{1+q}{1-q}\right) = 2 \operatorname{arctanh}(q) \\ M(t) &= 1 - t\psi_0\left(\frac{1-t}{2}\right) + t\psi_0\left(1 - \frac{t}{2}\right) \end{aligned}$$

where ψ_m is the polygamma function $\psi_m(z) = \frac{d^{m+1}}{dz^{m+1}} \log(\Gamma(z))$.

$$\mu'_n = 2(1-2^{1-n})n!\zeta(n) \quad n \neq 1$$

$$\begin{aligned}\mu'_1 &= 2 \log(2) \\ \mu'_2 &= 2\zeta(2) = \frac{\pi^2}{3} \\ \mu'_3 &= 9\zeta(3) \\ \mu'_4 &= 42\zeta(4) = \frac{7\pi^4}{15}\end{aligned}$$

$$\begin{aligned}h[X] &= 2 - \log(2) \\ &\approx 1.3068528194400546906.\end{aligned}$$

Implementation: `scipy.stats.halflogistic`

Hyperbolic Secant Distribution

Related to the logistic distribution and used in lifetime analysis. Standard form is (defined over all x)

$$\begin{aligned}f(x) &= \frac{1}{\pi} \operatorname{sech}(x) \\ F(x) &= \frac{2}{\pi} \arctan(e^x) \\ G(q) &= \log\left(\tan\left(\frac{\pi}{2}q\right)\right) \\ M(t) &= \sec\left(\frac{\pi}{2}t\right)\end{aligned}$$

$$\begin{aligned}\mu'_n &= \frac{1 + (-1)^n}{2\pi 2^{2n}} n! \left[\zeta\left(n+1, \frac{1}{4}\right) - \zeta\left(n+1, \frac{3}{4}\right) \right] \\ &= \begin{cases} 0 & n \text{ odd} \\ C_{n/2} \frac{\pi^n}{2^n} & n \text{ even} \end{cases}\end{aligned}$$

where C_m is an integer given by

$$\begin{aligned}C_m &= \frac{(2m)! \left[\zeta\left(2m+1, \frac{1}{4}\right) - \zeta\left(2m+1, \frac{3}{4}\right) \right]}{\pi^{2m+1} 2^{2m}} \\ &= 4(-1)^{m-1} \frac{16^m}{2m+1} B_{2m+1}\left(\frac{1}{4}\right)\end{aligned}$$

where $B_{2m+1}\left(\frac{1}{4}\right)$ is the Bernoulli polynomial of order $2m+1$ evaluated at $1/4$. Thus

$$\mu'_n = \begin{cases} 0 & n \text{ odd} \\ 4(-1)^{n/2-1} \frac{(2\pi)^n}{n+1} B_{n+1}\left(\frac{1}{4}\right) & n \text{ even} \end{cases}$$

$$\begin{aligned}m_d = m_n = \mu &= 0 \\ \mu_2 &= \frac{\pi^2}{4} \\ \gamma_1 &= 0 \\ \gamma_2 &= 2\end{aligned}$$

$$h[X] = \log(2\pi).$$

Implementation: `scipy.stats.hypsecant`

Gauss Hypergeometric Distribution

The four shape parameters are $\alpha > 0$, $\beta > 0$, $-\infty < \gamma < \infty$, and $z > -1$. The support is $x \in [0, 1]$.

$$\text{Let } C = \frac{1}{B(\alpha, \beta) {}_2F_1(\gamma, \alpha; \alpha + \beta; -z)}$$

$$f(x; \alpha, \beta, \gamma, z) = C x^{\alpha-1} \frac{(1-x)^{\beta-1}}{(1+zx)^\gamma}$$

$$\mu'_n = \frac{B(n+\alpha, \beta) {}_2F_1(\gamma, \alpha+n; \alpha+\beta+n; -z)}{B(\alpha, \beta) {}_2F_1(\gamma, \alpha; \alpha+\beta; -z)}$$

Implementation: `scipy.stats.gausshyper`

Inverted Gamma Distribution

Special case of the generalized Gamma distribution with $c = -1$ and $a > 0$ and support $x \geq 0$.

$$f(x; a) = \frac{x^{-a-1}}{\Gamma(a)} \exp\left(-\frac{1}{x}\right)$$

$$F(x; a) = \frac{\Gamma(a, \frac{1}{x})}{\Gamma(a)}$$

$$G(q; a) = \{\Gamma^{-1}(a, \Gamma(a)q)\}^{-1}$$

$$\mu'_n = \frac{\Gamma(a-n)}{\Gamma(a)} \quad a > n$$

$$\mu = \frac{1}{a-1} \quad a > 1$$

$$\mu_2 = \frac{1}{(a-2)(a-1)} - \mu^2 \quad a > 2$$

$$\gamma_1 = \frac{\frac{1}{(a-3)(a-2)(a-1)} - 3\mu\mu_2 - \mu^3}{\mu_2^{3/2}}$$

$$\gamma_2 = \frac{\frac{1}{(a-4)(a-3)(a-2)(a-1)} - 4\mu\mu_3 - 6\mu^2\mu_2 - \mu^4}{\mu_2^2} - 3$$

$$m_d = \frac{1}{a+1}$$

$$h[X] = a - (a+1)\psi(a) + \log \Gamma(a).$$

where Ψ is the digamma function $\psi(z) = \frac{d}{dz} \log(\Gamma(z))$.

Implementation: `scipy.stats.invgamma`

Inverse Normal (Inverse Gaussian) Distribution

The standard form involves the shape parameter μ (in most definitions, $L = 0.0$ is used). (In terms of the regress documentation $\mu = A/B$) and $B = S$ and L is not a parameter in that distribution. A standard form is $x > 0$

$$\begin{aligned} f(x; \mu) &= \frac{1}{\sqrt{2\pi x^3}} \exp\left(-\frac{(x-\mu)^2}{2x\mu^2}\right) \\ F(x; \mu) &= \Phi\left(\frac{1}{\sqrt{x}} \frac{x-\mu}{\mu}\right) + \exp\left(\frac{2}{\mu}\right) \Phi\left(-\frac{1}{\sqrt{x}} \frac{x+\mu}{\mu}\right) \\ G(q; \mu) &= F^{-1}(q; \mu) \end{aligned}$$

$$\begin{aligned} \mu &= \mu \\ \mu_2 &= \mu^3 \\ \gamma_1 &= 3\sqrt{\mu} \\ \gamma_2 &= 15\mu \\ m_d &= \frac{\mu}{2} \left(\sqrt{9\mu^2 + 4} - 3\mu\right) \end{aligned}$$

This is related to the canonical form or JKB “two-parameter” inverse Gaussian when written in it’s full form with scale parameter S and location parameter L by taking $L = 0$ and $S \equiv \lambda$, then μS is equal to μ_2 where μ_2 is the parameter used by JKB. We prefer this form because of it’s consistent use of the scale parameter. Notice that in JKB the skew ($\sqrt{\beta_1}$) and the kurtosis ($\beta_2 - 3$) are both functions only of $\mu_2/\lambda = \mu S/S = \mu$ as shown here, while the variance and mean of the standard form here are transformed appropriately.

Implementation: `scipy.stats.invgauss`

Inverted Weibull Distribution

There is one shape parameter $c > 0$ and the support is $x \geq 0$. Then

$$\begin{aligned} f(x; c) &= cx^{-c-1} \exp(-x^{-c}) \\ F(x; c) &= \exp(-x^{-c}) \\ G(q; c) &= (-\log q)^{-1/c} \\ h[X] &= 1 + \gamma + \frac{\gamma}{c} - \log(c) \end{aligned}$$

where γ is Euler’s constant.

Implementation: `scipy.stats.invweibull`

Johnson SB Distribution

There are two shape parameters $a \in \mathbb{R}$ and $b > 0$, and the support is $x \in [0, 1]$.

$$\begin{aligned} f(x; a, b) &= \frac{b}{x(1-x)} \phi\left(a + b \log \frac{x}{1-x}\right) \\ F(x; a, b) &= \Phi\left(a + b \log \frac{x}{1-x}\right) \\ G(q; a, b) &= \frac{1}{1 + \exp\left(-\frac{1}{b} (\Phi^{-1}(q) - a)\right)} \end{aligned}$$

Implementation: `scipy.stats.johnsonsb`

Johnson SU Distribution

There are two shape parameters $a \in \mathbb{R}$ and $b > 0$, and the support is $x \in \mathbb{R}$.

$$\begin{aligned} f(x; a, b) &= \frac{b}{\sqrt{x^2 + 1}} \phi\left(a + b \log\left(x + \sqrt{x^2 + 1}\right)\right) \\ F(x; a, b) &= \Phi\left(a + b \log\left(x + \sqrt{x^2 + 1}\right)\right) \\ G(q; a, b) &= \sinh\left(\frac{\Phi^{-1}(q) - a}{b}\right) \end{aligned}$$

Implementation: `scipy.stats.johnsonsu`

KSone Distribution

This is the distribution of maximum positive differences between an empirical distribution function, computed from n samples or observations, and a comparison (or target) cumulative distribution function.

Writing $D_n^+ = \sup_t (F_{\text{empirical},n}(t) - F_{\text{target}}(t))$, `ksone` is the distribution of the D_n^+ values. (The distribution of $D_n^- = \sup_t (F_{\text{target}}(t) - F_{\text{empirical},n}(t))$ differences follows the same distribution, so `ksone` can be used for one-sided tests on either side.)

There is one shape parameter n , a positive integer, and the support is $x \in [0, 1]$.

$$\begin{aligned} F(n, x) &= 1 - \sum_{j=0}^{\lfloor n(1-x) \rfloor} \binom{n}{j} x \left(x + \frac{j}{n}\right)^{j-1} \left(1 - x - \frac{j}{n}\right)^{n-j} \\ &= 1 - \text{scipy.special.smirnov}(n, x) \\ \lim_{n \rightarrow \infty} F\left(n, \frac{x}{\sqrt{n}}\right) &= e^{-2x^2} \end{aligned}$$

References

- “Kolmogorov-Smirnov test”, Wikipedia https://en.wikipedia.org/wiki/Kolmogorov-Smirnov_test
- Birnbaum, Z. W.; Tingey, Fred H. “One-Sided Confidence Contours for Probability Distribution Functions.” *Ann. Math. Statist.* 22 (1951), no. 4, 592–596.

Implementation: `scipy.stats.ksone`

KStwo Distribution

This is the distribution of the maximum absolute differences between an empirical distribution function, computed from n samples or observations, and a comparison (or target) cumulative distribution function, which is assumed to be continuous. (The “two” in the name is because this is the two-sided difference. `ksone` is the distribution of the positive differences, D_n^+ , hence it concerns one-sided differences. `kstwobign` is the limiting distribution of the *normalized* maximum absolute differences $\sqrt{n}D_n$.)

Writing $D_n = \sup_t |F_{\text{empirical},n}(t) - F_{\text{target}}(t)|$, `kstwo` is the distribution of the D_n values.

`kstwo` can also be used with the differences between two empirical distribution functions, for sets of observations with m and n samples respectively. Writing $D_{m,n} = \sup_t |F_{1,m}(t) - F_{2,n}(t)|$, where $F_{1,m}$ and $F_{2,n}$ are the two empirical distribution functions, then $Pr(D_{m,n} \leq x) \approx Pr(D_N \leq x)$ under appropriate conditions, where $N = \sqrt{\left(\frac{mn}{m+n}\right)}$.

There is one shape parameter n , a positive integer, and the support is $x \in [0, 1]$.

The implementation follows Simard & L'Ecuyer, which combines exact algorithms of Durbin and Pomeranz with asymptotic estimates of Li-Chien, Pelz and Good to compute the CDF with 5-15 accurate digits.

Examples

```
>>> from scipy.stats import kstwo
```

Show the probability of a gap at least as big as 0, 0.5 and 1.0 for a sample of size 5

```
>>> kstwo.sf([0, 0.5, 1.0], 5)
array([1.      , 0.112, 0.     ])
```

Compare a sample of size 5 drawn from a source $N(0.5, 1)$ distribution against a target $N(0, 1)$ CDF.

```
>>> from scipy.stats import norm
>>> n = 5
>>> gendist = norm(0.5, 1)      # Normal distribution, mean 0.5, stddev 1
>>> np.random.seed(seed=423)   # Set the seed for reproducibility
>>> x = np.sort(gendist.rvs(size=n))
>>> x
array([-1.59113056, -0.66335147,  0.54791569,  0.78009321,  1.27641365])
>>> target = norm(0, 1)
>>> cdfs = target.cdf(x)
>>> cdfs
array([0.0557901 , 0.25355274, 0.7081251 , 0.78233199, 0.89909533])
# Construct the Empirical CDF and the K-S statistics (Dn+, Dn-, Dn)
>>> ecdfs = np.arange(n+1, dtype=float)/n
>>> cols = np.column_stack([x, ecdfs[1:], cdfs, cdfs - ecdfs[1:], ecdfs[1:] -
    ↪ cdfs])
>>> np.set_printoptions(precision=3)
>>> cols
array([[ -1.591,  0.2  ,  0.056,  0.056,  0.144],
       [ -0.663,  0.4  ,  0.254,  0.054,  0.146],
       [  0.548,  0.6  ,  0.708,  0.308, -0.108],
       [  0.78 ,  0.8  ,  0.782,  0.182,  0.018],
       [  1.276,  1.   ,  0.899,  0.099,  0.101]])
>>> gaps = cols[:, -2:]
>>> Dnpm = np.max(gaps, axis=0)
>>> Dn = np.max(Dnpm)
>>> iminus, iplus = np.argmax(gaps, axis=0)
>>> print('Dn- = %f (at x=%.2f)' % (Dnpm[0], x[iminus]))
Dn- = 0.308125 (at x=0.55)
>>> print('Dn+ = %f (at x=%.2f)' % (Dnpm[1], x[iplus]))
Dn+ = 0.146447 (at x=-0.66)
>>> print('Dn = %f' % (Dn))
Dn = 0.308125
```

```
>>> probs = kstwo.sf(Dn, n)
>>> print(chr(10).join(['For a sample of size %d drawn from a N(0, 1)
    ↪ distribution:' % n,
...      'Kolmogorov-Smirnov 2-sided n=%d: Prob(Dn >= %f) = %.4f' % (n, Dn,
    ↪ probs)]))
```

(continues on next page)

(continued from previous page)

For a sample of size 5 drawn from a $N(0, 1)$ distribution:
 Kolmogorov-Smirnov 2-sided $n=5$: $\text{Prob}(D_n \geq 0.308125) = 0.6319$

Plot the Empirical CDF against the target $N(0, 1)$ CDF

```
>>> import matplotlib.pyplot as plt
>>> plt.step(np.concatenate([[ -3], x]), ecdfs, where='post', label='Empirical_
↳CDF')
>>> x3 = np.linspace(-3, 3, 100)
>>> plt.plot(x3, target.cdf(x3), label='CDF for N(0, 1)')
>>> plt.ylim([0, 1]); plt.grid(True); plt.legend();
>>> plt.vlines([x[iminus]], ecdfs[iminus], cdfs[iminus], color='r', linestyle=
↳'solid', lw=4)
>>> plt.vlines([x[iplus]], cdfs[iplus], ecdfs[iplus+1], color='m', linestyle=
↳'solid', lw=4)
>>> plt.annotate('Dn-', xy=(x[iminus], (ecdfs[iminus]+ cdfs[iminus])/2),
...               xytext=(x[iminus]+1, (ecdfs[iminus]+ cdfs[iminus])/2 - 0.02),
...               arrowprops=dict(facecolor='white', edgecolor='r', shrink=0.
↳05), size=15, color='r');
>>> plt.annotate('Dn+', xy=(x[iplus], (ecdfs[iplus+1]+ cdfs[iplus])/2),
...               xytext=(x[iplus]-2, (ecdfs[iplus+1]+ cdfs[iplus])/2 - 0.02),
...               arrowprops=dict(facecolor='white', edgecolor='m', shrink=0.
↳05), size=15, color='m');
>>> plt.show()
```

References

- “Kolmogorov-Smirnov test”, Wikipedia https://en.wikipedia.org/wiki/Kolmogorov-Smirnov_test
- Durbin J. “The Probability that the Sample Distribution Function Lies Between Two Parallel Straight Lines.” *Ann. Math. Statist.*, 39 (1968) 39, 398-411.
- Pomeranz J. “Exact Cumulative Distribution of the Kolmogorov-Smirnov Statistic for Small Samples (Algorithm 487).” *Communications of the ACM*, 17(12), (1974) 703-704.
- Li-Chien, C. “On the exact distribution of the statistics of A. N. Kolmogorov and their asymptotic expansion.” *Acta Mathematica Sinica*, 6, (1956) 55-81.
- Pelz W, Good IJ. “Approximating the Lower Tail-areas of the Kolmogorov-Smirnov One-sample Statistic.” *Journal of the Royal Statistical Society, Series B*, (1976) 38(2), 152-156.
- Simard, R., L’Ecuyer, P. “Computing the Two-Sided Kolmogorov-Smirnov Distribution”, *Journal of Statistical Software*, Vol 39, (2011) 11.

Implementation: `scipy.stats.kstwo`

KStwobign Distribution

This is the limiting distribution of the normalized maximum absolute differences between an empirical distribution function, computed from n samples or observations, and a comparison (or target) cumulative distribution function. (`kstwbign` is the distribution of the unnormalized positive differences, D_n^+ .)

Writing $D_n = \sup_t |F_{\text{empirical},n}(t) - F_{\text{target}}(t)|$, the normalization factor is \sqrt{n} , and `kstwbign` is the limiting distribution of the $\sqrt{n}D_n$ values as $n \rightarrow \infty$.

Note that $D_n = \max(D_n^+, D_n^-)$, but D_n^+ and D_n^- are not independent.

`kstwbign` can also be used with the differences between two empirical distribution functions, for sets of observations with m and n samples respectively, where m and n are “big”. Writing $D_{m,n} = \sup_t |F_{1,m}(t) - F_{2,n}(t)|$, where $F_{1,m}$ and $F_{2,n}$ are the two empirical distribution functions, then `kstwbign` is also the limiting distribution of the $\sqrt{\left(\frac{mn}{m+n}\right)} D_{m,n}$ values, as $m, n \rightarrow \infty$ and $m/n \rightarrow a \neq 0, \infty$.

There are no shape parameters, and the support is $x \in [0, \infty)$.

$$\begin{aligned} F(x) &= 1 - 2 \sum_{k=1}^{\infty} (-1)^{k-1} e^{-2k^2 x^2} \\ &= \frac{\sqrt{2\pi}}{x} \sum_{k=1}^{\infty} e^{-(2k-1)^2 \pi^2 / (8x^2)} \\ &= 1 - \text{scipy.special.kolmogorov}(n, x) \\ f(x) &= 8x \sum_{k=1}^{\infty} (-1)^{k-1} k^2 e^{-2k^2 x^2} \end{aligned}$$

References

- “Kolmogorov-Smirnov test”, Wikipedia https://en.wikipedia.org/wiki/Kolmogorov-Smirnov_test
- Kolmogoroff, A. “Confidence Limits for an Unknown Distribution Function.”” *Ann. Math. Statist.* 12 (1941), no. 4, 461–463.
- Smirnov, N. “On the estimation of the discrepancy between empirical curves of distribution for two independent samples” *Bull. Math. Univ. Moscou.*, 2 (1039), 2-26.
- Feller, W. “On the Kolmogorov-Smirnov Limit Theorems for Empirical Distributions.” *Ann. Math. Statist.* 19 (1948), no. 2, 177–189. and “Errata” *Ann. Math. Statist.* 21 (1950), no. 2, 301–302.

Implementation: `scipy.stats.kstwbign`

Laplace (Double Exponential, Bilateral Exponential) Distribution

$$\begin{aligned} f(x) &= \frac{1}{2} e^{-|x|} \\ F(x) &= \begin{cases} \frac{1}{2} e^x & x \leq 0 \\ 1 - \frac{1}{2} e^{-x} & x > 0 \end{cases} \\ G(q) &= \begin{cases} \log(2q) & q \leq \frac{1}{2} \\ -\log(2 - 2q) & q > \frac{1}{2} \end{cases} \end{aligned}$$

$$\begin{aligned} m_d = m_n = \mu &= 0 \\ \mu_2 &= 2 \\ \gamma_1 &= 0 \\ \gamma_2 &= 3 \end{aligned}$$

The ML estimator of the location parameter is

$$\hat{L} = \text{median}(X_i)$$

where X_i is a sequence of N mutually independent Laplace RV's and the median is some number between the $\frac{1}{2}N$ th and the $(N/2 + 1)$ th order statistic (e.g. take the average of these two) when N is even. Also,

$$\hat{S} = \frac{1}{N} \sum_{j=1}^N |X_j - \hat{L}|.$$

Replace \hat{L} with L if it is known. If L is known then this estimator is distributed as $(2N)^{-1} S \cdot \chi_{2N}^2$.

$$\begin{aligned} h[X] &= \log(2e) \\ &\approx 1.6931471805599453094. \end{aligned}$$

Implementation: `scipy.stats.laplace`

Asymmetric Laplace Distribution

This distribution is a generalization of the Laplace distribution. It has a single shape parameter $\kappa > 0$ that species the distribution's asymmetry. The special case $\kappa = 1$ yields the Laplace distribution.

Functions

$$\begin{aligned} F(x, \kappa) &= 1 - \frac{\kappa^{-1}}{\kappa + \kappa^{-1}} \exp(-x\kappa), \quad x \geq 0; \\ &= \frac{\kappa}{\kappa + \kappa^{-1}} \exp(x/\kappa), \quad x < 0. \\ f(x, \kappa) &= \frac{1}{\kappa + \kappa^{-1}} \exp(-x\kappa), \quad x \geq 0; \\ &= \frac{1}{\kappa + \kappa^{-1}} \exp(x/\kappa), \quad x < 0. \end{aligned}$$

$$\begin{aligned} \mu &= \kappa^{-1} - \kappa \\ \mu_2 &= \kappa^{-2} + \kappa^2 \\ \gamma_1 &= \frac{2(1 - \kappa^6)}{(1 + \kappa^4)^{3/2}} \\ \gamma_2 &= \frac{6(1 + \kappa^8)}{(1 + \kappa^4)^2} \end{aligned}$$

References

- “Asymmetric Laplace distribution”, Wikipedia https://en.wikipedia.org/wiki/Asymmetric_Laplace_distribution
- Kozubowski TJ and Podgórski K, “A Multivariate and Asymmetric Generalization of Laplace Distribution,” *Computational Statistics* 15, 531–540 (2000). DOI:10.1007/PL00022717

Implementation: `scipy.stats.laplace_asymmetric`

Left-skewed Lévy Distribution

Special case of Lévy-stable distribution with $\alpha = \frac{1}{2}$ and $\beta = -1$. The support is $x \leq 0$. In standard form

$$\begin{aligned} f(x) &= \frac{1}{|x| \sqrt{2\pi|x|}} \exp\left(-\frac{1}{2|x|}\right) \\ F(x) &= 2\Phi\left(\frac{1}{\sqrt{|x|}}\right) - 1 \\ G(q) &= -\left[\Phi^{-1}\left(\frac{q+1}{2}\right)\right]^{-2}. \end{aligned}$$

No moments.

Implementation: `scipy.stats.levy_l`

Lévy Distribution

A special case of Lévy-stable distributions with $\alpha = \frac{1}{2}$ and $\beta = 1$ and support $x \geq 0$. In standard form it is defined for $x > 0$ as

$$\begin{aligned} f(x) &= \frac{1}{x\sqrt{2\pi x}} \exp\left(-\frac{1}{2x}\right) \\ F(x) &= 2\left[1 - \Phi\left(\frac{1}{\sqrt{x}}\right)\right] \\ G(q) &= \left[\Phi^{-1}\left(1 - \frac{q}{2}\right)\right]^{-2}. \end{aligned}$$

It has no finite moments.

Implementation: `scipy.stats.levy`

Logistic (Sech-squared) Distribution

A special case of the Generalized Logistic distribution with $c = 1$. Defined for $x \geq 0$

$$\begin{aligned} f(x) &= \frac{\exp(-x)}{(1 + \exp(-x))^2} \\ F(x) &= \frac{1}{1 + \exp(-x)} \\ G(q) &= -\log(1/q - 1) \end{aligned}$$

$$\begin{aligned}
 \mu &= \gamma + \psi_0(1) = 0 \\
 \mu_2 &= \frac{\pi^2}{6} + \psi_1(1) = \frac{\pi^2}{3} \\
 \gamma_1 &= \frac{\psi_2(1) + 2\zeta(3)}{\mu_2^{3/2}} = 0 \\
 \gamma_2 &= \frac{\left(\frac{\pi^4}{15} + \psi_3(1)\right)}{\mu_2^2} = \frac{6}{5} \\
 m_d &= \log 1 = 0 \\
 m_n &= -\log(2 - 1) = 0
 \end{aligned}$$

where ψ_m is the polygamma function $\psi_m(z) = \frac{d^{m+1}}{dz^{m+1}} \log(\Gamma(z))$.

$$h[X] = 1.$$

Implementation: `scipy.stats.logistic`

Log Double Exponential (Log-Laplace) Distribution

One shape parameter $c > 0$. The support is $x \geq 0$.

$$\begin{aligned}
 f(x; c) &= \begin{cases} \frac{c}{2} x^{c-1} & 0 < x < 1 \\ \frac{c}{2} x^{-c-1} & x \geq 1 \end{cases} \\
 F(x; c) &= \begin{cases} \frac{1}{2} x^c & 0 < x < 1 \\ 1 - \frac{1}{2} x^{-c} & x \geq 1 \end{cases} \\
 G(q; c) &= \begin{cases} (2q)^{1/c} & 0 \leq q < \frac{1}{2} \\ (2 - 2q)^{-1/c} & \frac{1}{2} \leq q \leq 1 \end{cases} \\
 h[X] &= \log\left(\frac{2e}{c}\right)
 \end{aligned}$$

Implementation: `scipy.stats.loglaplace`

Log Gamma Distribution

A single shape parameter $c > 0$. The support is $x \in \mathbb{R}$.

$$\begin{aligned}
 f(x; c) &= \frac{\exp(cx - e^x)}{\Gamma(c)} \\
 F(x; c) &= \frac{\gamma(c, e^x)}{\Gamma(c)} \\
 G(q; c) &= \log(\gamma^{-1}(c, q\Gamma(c)))
 \end{aligned}$$

where γ is the lower incomplete gamma function, $\gamma(s, x) = \int_0^x t^{s-1} e^{-t} dt$.

$$\mu'_n = \int_0^\infty [\log y]^n y^{c-1} \exp(-y) dy.$$

$$\begin{aligned}\mu &= \mu'_1 \\ \mu_2 &= \mu'_2 - \mu^2 \\ \gamma_1 &= \frac{\mu'_3 - 3\mu\mu_2 - \mu^3}{\mu_2^{3/2}} \\ \gamma_2 &= \frac{\mu'_4 - 4\mu\mu_3 - 6\mu^2\mu_2 - \mu^4}{\mu_2^2} - 3\end{aligned}$$

Implementation: `scipy.stats.loggamma`

Log Normal (Cobb-Douglass) Distribution

Has one shape parameter $\sigma > 0$. (Notice that the “Regress” $A = \log S$ where S is the scale parameter and A is the mean of the underlying normal distribution). The support is $x \geq 0$.

$$\begin{aligned}f(x; \sigma) &= \frac{1}{\sigma x \sqrt{2\pi}} \exp\left(-\frac{1}{2} \left(\frac{\log x}{\sigma}\right)^2\right) \\ F(x; \sigma) &= \Phi\left(\frac{\log x}{\sigma}\right) \\ G(q; \sigma) &= \exp(\sigma \Phi^{-1}(q))\end{aligned}$$

$$\begin{aligned}\mu &= \exp(\sigma^2/2) \\ \mu_2 &= \exp(\sigma^2) [\exp(\sigma^2) - 1] \\ \gamma_1 &= \sqrt{p-1} (2+p) \\ \gamma_2 &= p^4 + 2p^3 + 3p^2 - 6 \quad p = e^{\sigma^2}\end{aligned}$$

Notice that using JKB notation we have $\theta = L$, $\zeta = \log S$ and we have given the so-called antilognormal form of the distribution. This is more consistent with the location, scale parameter description of general probability distributions.

$$h[X] = \frac{1}{2} [1 + \log(2\pi) + 2 \log(\sigma)].$$

Also, note that if X is a log-normally distributed random-variable with $L = 0$ and S and shape parameter σ . Then, $\log X$ is normally distributed with variance σ^2 and mean $\log S$.

Implementation: `scipy.stats.lognorm`

Log-Uniform Distribution

This random variable is log-uniform. That is, if `loguniform(10**-1, 10**1)` is specified, 0.1, 1, 10 are all equally likely.

There are two shape parameters $a, b > 0$ and the support is $x \in [a, b]$.

$$\begin{aligned}f(x; a, b) &= \frac{1}{x \log(b/a)} \\ F(x; a, b) &= \frac{\log(x/a)}{\log(b/a)} \\ G(q; a, b) &= a \exp(q \log(b/a)) = a \left(\frac{b}{a}\right)^q\end{aligned}$$

$$\begin{aligned}
 d &= \log(a/b) \\
 \mu &= \frac{a-b}{d} \\
 \mu_2 &= \mu \frac{a+b}{2} - \mu^2 = \frac{(a-b)[a(d-2)+b(d+2)]}{2d^2} \\
 \gamma_1 &= \frac{\sqrt{2} [12d(a-b)^2 + d^2(a^2(2d-9) + 2abd + b^2(2d+9))]}{3d\sqrt{a-b}[a(d-2)+b(d+2)]^{3/2}} \\
 \gamma_2 &= \frac{-36(a-b)^3 + 36d(a-b)^2(a+b) - 16d^2(a^3-b^3) + 3d^3(a^2+b^2)(a+b)}{3(a-b)[a(d-2)+b(d+2)]^2} - 3 \\
 m_d &= a \\
 m_n &= \sqrt{ab}
 \end{aligned}$$

$$h[X] = \frac{1}{2} \log(ab) + \log \left[\log \left(\frac{b}{a} \right) \right].$$

Implementation: `scipy.stats.loguniform`.

Maxwell Distribution

This is a special case of the Chi distribution with $L = 0$ and $S = \frac{1}{\sqrt{a}}$ and $\nu = 3$. The support is $x \geq 0$.

$$\begin{aligned}
 f(x) &= \sqrt{\frac{2}{\pi}} x^2 e^{-x^2/2} \\
 F(x) &= \frac{\gamma\left(\frac{3}{2}, \frac{x^2}{2}\right)}{\Gamma\left(\frac{3}{2}\right)} \\
 G(q) &= \sqrt{2\gamma^{-1}\left(\frac{3}{2}, q\Gamma\left(\frac{3}{2}\right)\right)}
 \end{aligned}$$

$$\begin{aligned}
 \mu &= 2\sqrt{\frac{2}{\pi}} \\
 \mu_2 &= 3 - \frac{8}{\pi} \\
 \gamma_1 &= \sqrt{2} \frac{32 - 10\pi}{(3\pi - 8)^{3/2}} \\
 \gamma_2 &= \frac{-12\pi^2 + 160\pi - 384}{(3\pi - 8)^2} \\
 m_d &= \sqrt{2} \\
 m_n &= \sqrt{2\gamma^{-1}\left(\frac{3}{2}, \frac{1}{2}\Gamma\left(\frac{3}{2}\right)\right)}
 \end{aligned}$$

$$h[X] = \log \left(\sqrt{\frac{2\pi}{e}} \right) + \gamma.$$

Implementation: `scipy.stats.maxwell`

Mielke's Beta-Kappa Distribution

A generalized F distribution. Two shape parameters κ and θ , with support $x \geq 0$. The β in the DATAPLOT reference is a scale parameter.

$$\begin{aligned} f(x; \kappa, \theta) &= \frac{\kappa x^{\kappa-1}}{(1+x^\theta)^{1+\frac{\kappa}{\theta}}} \\ F(x; \kappa, \theta) &= \frac{x^\kappa}{(1+x^\theta)^{\kappa/\theta}} \\ G(q; \kappa, \theta) &= \left(\frac{q^{\theta/\kappa}}{1-q^{\theta/\kappa}} \right)^{1/\theta} \end{aligned}$$

Implementation: `scipy.stats.mielke`

Nakagami Distribution

Generalization of the chi distribution. Shape parameter is $\nu > 0$. The support is $x \geq 0$.

$$\begin{aligned} f(x; \nu) &= \frac{2\nu^\nu}{\Gamma(\nu)} x^{2\nu-1} \exp(-\nu x^2) \\ F(x; \nu) &= \frac{\gamma(\nu, \nu x^2)}{\Gamma(\nu)} \\ G(q; \nu) &= \sqrt{\frac{1}{\nu} \gamma^{-1}(\nu, q\Gamma(\nu))} \end{aligned}$$

where γ is the lower incomplete gamma function, $\gamma(\nu, x) = \int_0^x t^{\nu-1} e^{-t} dt$.

$$\begin{aligned} \mu &= \frac{\Gamma(\nu + \frac{1}{2})}{\sqrt{\nu}\Gamma(\nu)} \\ \mu_2 &= [1 - \mu^2] \\ \gamma_1 &= \frac{\mu(1 - 4\nu\mu_2)}{2\nu\mu_2^{3/2}} \\ \gamma_2 &= \frac{-6\mu^4\nu + (8\nu - 2)\mu^2 - 2\nu + 1}{\nu\mu_2^2} \end{aligned}$$

Implementation: `scipy.stats.nakagami`

Noncentral chi-squared Distribution

The distribution of $\sum_{i=1}^{\nu} (Z_i + \delta_i)^2$ where Z_i are independent standard normal variables and δ_i are constants. $\lambda = \sum_{i=1}^{\nu} \delta_i^2 > 0$. (In communications it is called the Marcum-Q function). It can be thought of as a Generalized Rayleigh-Rice distribution.

The two shape parameters are ν , a positive integer, and λ , a positive real number. The support is $x \geq 0$.

$$\begin{aligned}
 f(x; \nu, \lambda) &= e^{-(\lambda+x)/2} \frac{1}{2} \left(\frac{x}{\lambda}\right)^{(\nu-2)/4} I_{(\nu-2)/2}(\sqrt{\lambda x}) \\
 F(x; \nu, \lambda) &= \sum_{j=0}^{\infty} \left\{ \frac{(\lambda/2)^j}{j!} e^{-\lambda/2} \right\} \Pr[\chi_{\nu+2j}^2 \leq x] \\
 G(q; \nu, \lambda) &= F^{-1}(q; \nu, \lambda) \\
 \mu &= \nu + \lambda \\
 \mu_2 &= 2(\nu + 2\lambda) \\
 \gamma_1 &= \frac{\sqrt{8}(\nu + 3\lambda)}{(\nu + 2\lambda)^{3/2}} \\
 \gamma_2 &= \frac{12(\nu + 4\lambda)}{(\nu + 2\lambda)^2}
 \end{aligned}$$

where $I_\nu(y)$ is a modified Bessel function of the first kind.

References

- “Noncentral chi-squared distribution”, Wikipedia https://en.wikipedia.org/wiki/Noncentral_chi-squared_distribution

Implementation: `scipy.stats.ncx2`

Noncentral F Distribution

The distribution of $(X_1/X_2)(\nu_2/\nu_1)$ if X_1 is non-central chi-squared with ν_1 degrees of freedom and parameter λ , and X_2 is chi-squared with ν_2 degrees of freedom.

There are 3 shape parameters: the degrees of freedom $\nu_1 > 0$ and $\nu_2 > 0$; and $\lambda \geq 0$.

$$\begin{aligned}
 f(x; \lambda, \nu_1, \nu_2) &= \exp\left[\frac{\lambda}{2} + \frac{(\lambda\nu_1 x)}{2(\nu_1 x + \nu_2)}\right] \nu_1^{\nu_1/2} \nu_2^{\nu_2/2} x^{\nu_1/2-1} \\
 &\times (\nu_2 + \nu_1 x)^{-(\nu_1+\nu_2)/2} \frac{\Gamma(\frac{\nu_1}{2}) \Gamma(1 + \frac{\nu_2}{2}) L_{\nu_2/2}^{\nu_1/2-1}\left(-\frac{\lambda\nu_1 x}{2(\nu_1 x + \nu_2)}\right)}{B(\frac{\nu_1}{2}, \frac{\nu_2}{2}) \Gamma(\frac{\nu_1+\nu_2}{2})}
 \end{aligned}$$

where $L_{\nu_2/2}^{\nu_1/2-1}(x)$ is an associated Laguerre polynomial.

If $\lambda = 0$, the distribution becomes equivalent to the Fisher distribution with ν_1 and ν_2 degrees of freedom.

Implementation: `scipy.stats.ncf`

Noncentral t Distribution

The distribution of the ratio

$$\frac{U + \lambda}{\chi_\nu / \sqrt{\nu}}$$

where U and χ_ν are independent and distributed as a standard normal and chi with ν degrees of freedom. Note $\lambda > 0$ and $\nu > 0$.

$$\begin{aligned}
 f(x; \lambda, \nu) &= \frac{\nu^{\nu/2} \Gamma(\nu + 1)}{2^\nu e^{\lambda^2/2} (\nu + x^2)^{\nu/2} \Gamma(\nu/2)} \\
 &\times \left\{ \frac{\sqrt{2} \lambda x {}_1F_1\left(\frac{\nu}{2} + 1; \frac{3}{2}; \frac{\lambda^2 x^2}{2(\nu + x^2)}\right)}{(\nu + x^2) \Gamma\left(\frac{\nu+1}{2}\right)} \right. \\
 &\quad \left. - \frac{{}_1F_1\left(\frac{\nu+1}{2}; \frac{1}{2}; \frac{\lambda^2 x^2}{2(\nu + x^2)}\right)}{\sqrt{\nu + x^2} \Gamma\left(\frac{\nu}{2} + 1\right)} \right\} \\
 &= \frac{\Gamma(\nu + 1)}{2^{(\nu-1)/2} \sqrt{\pi} \nu \Gamma(\nu/2)} \exp\left[-\frac{\nu \lambda^2}{\nu + x^2}\right] \\
 &\times \left(\frac{\nu}{\nu + x^2}\right)^{(\nu-1)/2} Hh_\nu\left(-\frac{\lambda x}{\sqrt{\nu + x^2}}\right) \\
 F(x; \lambda, \nu) &= \begin{cases} \tilde{F}_{\nu, \mu}(x) & x \geq 0 \\ 1 - \tilde{F}_{\nu, -\mu}(x) & x < 0 \end{cases}
 \end{aligned}$$

where

$$\tilde{F}_{\nu, \mu}(x) = \Phi(-\mu) + \frac{1}{2} \sum_{j=0}^{\infty} \left[p_j I_y\left(j + \frac{1}{2}, \frac{\nu}{2}\right) + q_j I_y\left(j + 1, \frac{\nu}{2}\right) \right]$$

$$y = \frac{x^2}{x^2 + \nu}$$

$$p_j = \frac{e^{(-\frac{\mu^2}{2})}}{j!} \left(\frac{\mu^2}{2}\right)^j$$

$$q_j = \frac{\mu e^{(-\frac{\mu^2}{2})}}{\sqrt{2} \Gamma(j + 3/2)} \left(\frac{\mu^2}{2}\right)^j$$

where $I_y(a, b)$ is the regularized incomplete beta function and Airy's Hh function is $Hh_\nu(x) = \frac{1}{\Gamma(\nu+1)} \int_0^\infty t^\nu e^{-\frac{(t+x)^2}{2}} dt$.

Implementation: `scipy.stats.nct`

Normal Distribution

$$f(x) = \frac{e^{-x^2/2}}{\sqrt{2\pi}}$$

$$F(x) = \Phi(x) = \frac{1}{2} + \frac{1}{2} \operatorname{erf}\left(\frac{x}{\sqrt{2}}\right)$$

$$G(q) = \Phi^{-1}(q)$$

$$m_d = m_n = \mu = 0$$

$$\mu_2 = 1$$

$$\gamma_1 = 0$$

$$\gamma_2 = 0$$

$$h[X] = \log(\sqrt{2\pi e})$$

$$\approx 1.4189385332046727418$$

Implementation: `scipy.stats.norm`

Normal Inverse Gaussian Distribution

The probability density function is given by:

$$f(x; a, b) = \frac{a \exp(\sqrt{a^2 - b^2} + bx)}{\pi \sqrt{1 + x^2}} K_1(a * \text{sqrt}(1 + x^2)),$$

where x is a real number, the parameter a is the tail heaviness and b is the asymmetry parameter satisfying $a > 0$ and $|b| \leq a$. K_1 is the modified Bessel function of second kind (`scipy.special.k1`).

A normal inverse Gaussian random variable with parameters a and b can be expressed as $X = bV + \sqrt{(V)}X$ where X is `norm(0,1)` and V is `invgauss(mu=1/sqrt(a**2 - b**2))`. Hence, the normal inverse Gaussian distribution is a special case of normal variance-mean mixtures.

Implementation: `scipy.stats.norminvgauss`

Pareto Distribution

One shape parameter $b > 0$ and support $x \geq 1$. The standard form is

$$f(x; b) = \frac{b}{x^{b+1}}$$

$$F(x; b) = 1 - \frac{1}{x^b}$$

$$G(q; b) = (1 - q)^{-1/b}$$

$$\mu = \frac{b}{b-1} \quad b > 1$$

$$\mu_2 = \frac{b}{(b-2)(b-1)^2} \quad b > 2$$

$$\gamma_1 = \frac{2(b+1)\sqrt{b-2}}{(b-3)\sqrt{b}} \quad b > 3$$

$$\gamma_2 = \frac{6(b^3 + b^2 - 6b - 2)}{b(b^2 - 7b + 12)} \quad b > 4$$

$$h(X) = \frac{1}{c} + 1 - \log(c)$$

Implementation: `scipy.stats.pareto`

Pareto Second Kind (Lomax) Distribution

This is Pareto of the first kind with $L = -1.0$. There is one shape parameter $c > 0$ and support $x \geq 0$.

$$\begin{aligned} f(x; c) &= \frac{c}{(1+x)^{c+1}} \\ F(x; c) &= 1 - \frac{1}{(1+x)^c} \\ G(q; c) &= (1-q)^{-1/c} - 1 \\ h[X] &= \frac{1}{c} + 1 - \log(c). \end{aligned}$$

Implementation: `scipy.stats.lomax`

Power Log Normal Distribution

A generalization of the log-normal distribution with shape parameters $\sigma > 0$, $c > 0$ and support $x \geq 0$.

$$\begin{aligned} f(x; \sigma, c) &= \frac{c}{x\sigma} \phi\left(\frac{\log x}{\sigma}\right) \left(\Phi\left(-\frac{\log x}{\sigma}\right)\right)^{c-1} \\ F(x; \sigma, c) &= 1 - \left(\Phi\left(-\frac{\log x}{\sigma}\right)\right)^c \\ G(q; \sigma, c) &= \exp\left(-\sigma\Phi^{-1}\left((1-q)^{1/c}\right)\right) \\ \mu'_n &= \int_0^1 \exp\left(-n\sigma\Phi^{-1}\left(y^{1/c}\right)\right) dy \\ \mu &= \mu'_1 \\ \mu_2 &= \mu'_2 - \mu^2 \\ \gamma_1 &= \frac{\mu'_3 - 3\mu\mu_2 - \mu^3}{\mu_2^{3/2}} \\ \gamma_2 &= \frac{\mu'_4 - 4\mu\mu_3 - 6\mu^2\mu_2 - \mu^4}{\mu_2^2} - 3 \end{aligned}$$

This distribution reduces to the log-normal distribution when $c = 1$.

Implementation: `scipy.stats.powerlognorm`

Power Normal Distribution

A generalization of the normal distribution, with one shape parameter $c > 0$ and support $x \geq 0$.

$$\begin{aligned} f(x; c) &= c\phi(x) (\Phi(-x))^{c-1} \\ F(x; c) &= 1 - (\Phi(-x))^c \\ G(q; c) &= -\Phi^{-1}\left((1-q)^{1/c}\right) \\ \mu'_n &= (-1)^n \int_0^1 \left[\Phi^{-1}\left(y^{1/c}\right)\right]^n dy \end{aligned}$$

$$\begin{aligned}\mu &= \mu'_1 \\ \mu_2 &= \mu'_2 - \mu^2 \\ \gamma_1 &= \frac{\mu'_3 - 3\mu\mu_2 - \mu^3}{\mu_2^{3/2}} \\ \gamma_2 &= \frac{\mu'_4 - 4\mu\mu_3 - 6\mu^2\mu_2 - \mu^4}{\mu_2^2} - 3\end{aligned}$$

For $c = 1$ this reduces to the normal distribution.

Implementation: `scipy.stats.powernorm`

Power-function Distribution

A special case of the beta distribution with $b = 1$. There is one shape parameter $a > 0$ and support $x \in [0, 1]$.

$$\begin{aligned}f(x; a) &= ax^{a-1} \\ F(x; a) &= x^a \\ G(q; a) &= q^{1/a} \\ \mu &= \frac{a}{a+1} \\ \mu_2 &= \frac{a(a+2)}{(a+1)^2} \\ \gamma_1 &= 2(1-a)\sqrt{\frac{a+2}{a(a+3)}} \\ \gamma_2 &= \frac{6(a^3 - a^2 - 6a + 2)}{a(a+3)(a+4)} \\ m_d &= 1 \\ h[X] &= 1 - \frac{1}{a} - \log(a)\end{aligned}$$

Implementation: `scipy.stats.powerlaw`

R-distribution Distribution

A general-purpose distribution with a variety of shapes controlled by one shape parameter $c > 0$. The support of the standard distribution is $x \in [-1, 1]$.

$$\begin{aligned}f(x; c) &= \frac{(1-x^2)^{c/2-1}}{B\left(\frac{1}{2}, \frac{c}{2}\right)} \\ F(x; c) &= \frac{1}{2} + \frac{x}{B\left(\frac{1}{2}, \frac{c}{2}\right)} {}_2F_1\left(\frac{1}{2}, 1 - \frac{c}{2}; \frac{3}{2}; x^2\right) \\ \mu'_n &= \frac{(1+(-1)^n)}{2} B\left(\frac{n+1}{2}, \frac{c}{2}\right)\end{aligned}$$

The R-distribution with parameter n is the distribution of the correlation coefficient of a random sample of size n drawn from a bivariate normal distribution with $\rho = 0$. The mean of the standard distribution is always zero and as the sample size grows, the distribution's mass concentrates more closely about this mean.

Implementation: `scipy.stats.rdist`

Rayleigh Distribution

This is a special case of the Chi distribution with $L = 0.0$ and $\nu = 2$ (no location parameter is generally used), the mode of the distribution is S .

$$\begin{aligned} f(r) &= r e^{-r^2/2} \\ F(r) &= 1 - e^{-r^2/2} \\ G(q) &= \sqrt{-2 \log(1 - q)} \end{aligned}$$

$$\begin{aligned} \mu &= \sqrt{\frac{\pi}{2}} \\ \mu_2 &= \frac{4 - \pi}{2} \\ \gamma_1 &= \frac{2(\pi - 3)\sqrt{\pi}}{(4 - \pi)^{3/2}} \\ \gamma_2 &= \frac{24\pi - 6\pi^2 - 16}{(4 - \pi)^2} \\ m_d &= 1 \\ m_n &= \sqrt{2 \log(2)} \\ h[X] &= \frac{\gamma}{2} + \log\left(\frac{e}{\sqrt{2}}\right) \\ \mu'_n &= \sqrt{2^n} \Gamma\left(\frac{n}{2} + 1\right) \end{aligned}$$

Implementation: `scipy.stats.rayleigh`

Rice Distribution

There is one shape parameter $b \geq 0$ (the “distance from the origin”) and the support is $x \geq 0$.

$$\begin{aligned} f(x; b) &= x \exp\left(-\frac{x^2 + b^2}{2}\right) I_0(xb) \\ F(x; b) &= \int_0^x \alpha \exp\left(-\frac{\alpha^2 + b^2}{2}\right) I_0(\alpha b) d\alpha \end{aligned}$$

where $I_0(y)$ is the modified Bessel function of the first kind of order 0.

$$\mu'_n = \sqrt{2^n} \Gamma\left(1 + \frac{n}{2}\right) {}_1F_1\left(-\frac{n}{2}; 1; -\frac{b^2}{2}\right)$$

Implementation: `scipy.stats.rice`

Reciprocal Inverse Gaussian Distribution

The pdf is found from the inverse gaussian (IG), $f_{RIG}(x; \mu) = \frac{1}{x^2} f_{IG}\left(\frac{1}{x}; \mu\right)$ defined for $x \geq 0$ as

$$\begin{aligned} f_{IG}(x; \mu) &= \frac{1}{\sqrt{2\pi x^3}} \exp\left(-\frac{(x - \mu)^2}{2x\mu^2}\right) \\ F_{IG}(x; \mu) &= \Phi\left(\frac{1}{\sqrt{x}} \frac{x - \mu}{\mu}\right) + \exp\left(\frac{2}{\mu}\right) \Phi\left(-\frac{1}{\sqrt{x}} \frac{x + \mu}{\mu}\right) \end{aligned}$$

$$\begin{aligned}
 f_{RIG}(x; \mu) &= \frac{1}{\sqrt{2\pi x}} \exp\left(-\frac{(1-\mu x)^2}{2x\mu^2}\right) \\
 F_{RIG}(x; \mu) &= 1 - F_{IG}\left(\frac{1}{x}, \mu\right) \\
 &= 1 - \Phi\left(\frac{1}{\sqrt{x}} \frac{1-\mu x}{\mu}\right) - \exp\left(\frac{2}{\mu}\right) \Phi\left(-\frac{1}{\sqrt{x}} \frac{1+\mu x}{\mu}\right)
 \end{aligned}$$

Implementation: `scipy.stats.recipinvgauss`

Semicircular Distribution

Defined on $x \in [-1, 1]$

$$\begin{aligned}
 f(x) &= \frac{2}{\pi} \sqrt{1-x^2} \\
 F(x) &= \frac{1}{2} + \frac{1}{\pi} \left[x\sqrt{1-x^2} + \arcsin x \right] \\
 G(q) &= F^{-1}(q)
 \end{aligned}$$

$$\begin{aligned}
 m_d = m_n = \mu &= 0 \\
 \mu_2 &= \frac{1}{4} \\
 \gamma_1 &= 0 \\
 \gamma_2 &= -1
 \end{aligned}$$

$$h[X] = 0.64472988584940017414.$$

Implementation: `scipy.stats.semicircular`

Student t Distribution

There is one shape parameter $\nu > 0$ and the support is $x \in \mathbb{R}$.

$$\begin{aligned}
 f(x; \nu) &= \frac{\Gamma\left(\frac{\nu+1}{2}\right)}{\sqrt{\pi\nu}\Gamma\left(\frac{\nu}{2}\right) \left[1 + \frac{x^2}{\nu}\right]^{\frac{\nu+1}{2}}} \\
 F(x; \nu) &= \begin{cases} \frac{1}{2} I\left(\frac{\nu}{\nu+x^2}; \frac{\nu}{2}, \frac{1}{2}\right) & x \leq 0 \\ 1 - \frac{1}{2} I\left(\frac{\nu}{\nu+x^2}; \frac{\nu}{2}, \frac{1}{2}\right) & x \geq 0 \end{cases} \\
 G(q; \nu) &= \begin{cases} -\sqrt{\frac{\nu}{I^{-1}\left(2q; \frac{\nu}{2}, \frac{1}{2}\right)} - \nu} & q \leq \frac{1}{2} \\ \sqrt{\frac{\nu}{I^{-1}\left(2-2q; \frac{\nu}{2}, \frac{1}{2}\right)} - \nu} & q \geq \frac{1}{2} \end{cases}
 \end{aligned}$$

$$\begin{aligned}
 m_n = m_d = \mu &= 0 \\
 \mu_2 &= \frac{\nu}{\nu-2} \quad \nu > 2 \\
 \gamma_1 &= 0 \quad \nu > 3 \\
 \gamma_2 &= \frac{6}{\nu-4} \quad \nu > 4
 \end{aligned}$$

where $I(x; a, b)$ is the incomplete beta integral and $I^{-1}(I(x; a, b); a, b) = x$. As $\nu \rightarrow \infty$, this distribution approaches the standard normal distribution.

$$h[X] = \frac{1}{4} \log \left(\frac{\pi c \Gamma^2 \left(\frac{c}{2} \right)}{\Gamma^2 \left(\frac{c+1}{2} \right)} \right) - \frac{(c+1)}{4} \left[\Psi \left(\frac{c}{2} \right) - cZ(c) + \pi \tan \left(\frac{\pi c}{2} \right) + \gamma + 2 \log 2 \right]$$

where

$$Z(c) = {}_3F_2 \left(1, 1, 1 + \frac{c}{2}; \frac{3}{2}, 2; 1 \right) = \sum_{k=0}^{\infty} \frac{k!}{k+1} \frac{\Gamma \left(\frac{c}{2} + 1 + k \right)}{\Gamma \left(\frac{c}{2} + 1 \right)} \frac{\Gamma \left(\frac{3}{2} \right)}{\Gamma \left(\frac{3}{2} + k \right)}$$

Implementation: `scipy.stats.t`

Trapezoidal Distribution

Two shape parameters $c \in [0, 1]$, $d \in [0, 1]$ giving the distances to the first and second modes as a percentage of the total extent of the non-zero portion. The location parameter is the start of the non-zero portion, and the scale-parameter is the width of the non-zero portion. In standard form we have $x \in [0, 1]$.

$$\begin{aligned} u(c, d) &= \frac{2}{d - c + 1} \\ f(x; c, d) &= \begin{cases} \frac{ux}{c} & x < c \\ u & c \leq x \leq d \\ u \frac{1-x}{1-d} & x > d \end{cases} \\ F(x; c, d) &= \begin{cases} \frac{ux^2}{2c} & x < c \\ \frac{uc}{2} + u(x - c) & c \leq x \leq d \\ 1 - \frac{u(1-x)^2}{2(1-d)} & x > d \end{cases} \\ G(q; c, d) &= \begin{cases} \sqrt{qc(d - c + 1)} & q < c \\ \frac{q}{u} + \frac{c}{2} & q \leq d \\ 1 - \sqrt{\frac{2(1-q)(1-d)}{u}} & q > d \end{cases} \end{aligned}$$

Implementation: `scipy.stats.trapezoid`

Triangular Distribution

One shape parameter $c \in [0, 1]$ giving the distance to the peak as a percentage of the total extent of the non-zero portion. The location parameter is the start of the non-zero portion, and the scale-parameter is the width of the non-zero portion. In standard form we have $x \in [0, 1]$.

$$\begin{aligned} f(x; c) &= \begin{cases} 2 \frac{x}{c} & x < c \\ 2 \frac{1-x}{1-c} & x \geq c \end{cases} \\ F(x; c) &= \begin{cases} \frac{x^2}{c} & x < c \\ \frac{x^2 - 2x + c}{c-1} & x \geq c \end{cases} \\ G(q; c) &= \begin{cases} \sqrt{cq} & q < c \\ 1 - \sqrt{(1-c)(1-q)} & q \geq c \end{cases} \end{aligned}$$

$$\begin{aligned}\mu &= \frac{c}{3} + \frac{1}{3} \\ \mu_2 &= \frac{1 - c + c^2}{18} \\ \gamma_1 &= \frac{\sqrt{2}(2c - 1)(c + 1)(c - 2)}{5(1 - c + c^2)^{3/2}} \\ \gamma_2 &= -\frac{3}{5} \\ h(X) &= \log\left(\frac{1}{2}\sqrt{e}\right) \\ &\approx -0.19314718055994530942.\end{aligned}$$

Implementation: `scipy.stats.triang`

Truncated Exponential Distribution

This is an exponential distribution defined only over a certain region $0 \leq x \leq B$. In standard form this is

$$\begin{aligned}f(x; B) &= \frac{e^{-x}}{1 - e^{-B}} \\ F(x; B) &= \frac{1 - e^{-x}}{1 - e^{-B}} \\ G(q; B) &= -\log(1 - q + qe^{-B}) \\ \mu'_n &= \Gamma(1 + n) - \Gamma(1 + n, B) \\ h[X] &= \log(e^B - 1) + \frac{1 + e^B(B - 1)}{1 - e^B}.\end{aligned}$$

Implementation: `scipy.stats.truncexpon`

Truncated Normal Distribution

A normal distribution restricted to lie within a certain range given by two parameters A and B . Notice that this A and B correspond to the bounds on x in standard form. For $x \in [A, B]$ we get

$$\begin{aligned}f(x; A, B) &= \frac{\phi(x)}{\Phi(B) - \Phi(A)} \\ F(x; A, B) &= \frac{\Phi(x) - \Phi(A)}{\Phi(B) - \Phi(A)} \\ G(q; A, B) &= \Phi^{-1}(q\Phi(B) + \Phi(A)(1 - q))\end{aligned}$$

where

$$\begin{aligned}\phi(x) &= \frac{1}{\sqrt{2\pi}}e^{-x^2/2} \\ \Phi(x) &= \int_{-\infty}^x \phi(u) du. \\ \mu &= \frac{\phi(A) - \phi(B)}{\Phi(B) - \Phi(A)} \\ \mu_2 &= 1 + \frac{A\phi(A) - B\phi(B)}{\Phi(B) - \Phi(A)} - \left(\frac{\phi(A) - \phi(B)}{\Phi(B) - \Phi(A)}\right)^2\end{aligned}$$

Implementation: `scipy.stats.truncnorm`

Tukey-Lambda Distribution

There is one shape parameter λ . The support is $x \in \mathbb{R}$.

$$f(x; \lambda) = F'(x; \lambda) = \frac{1}{G'(F(x; \lambda); \lambda)} = \frac{1}{F^{\lambda-1}(x; \lambda) + [1 - F(x; \lambda)]^{\lambda-1}}$$

$$F(x; \lambda) = G^{-1}(x; \lambda)$$

$$G(p; \lambda) = \frac{p^\lambda - (1-p)^\lambda}{\lambda}$$

$$\mu = 0$$

$$\begin{aligned} \mu_2 &= \int_0^1 G^2(p; \lambda) dp \\ &= \frac{2\Gamma(\lambda + \frac{3}{2}) - \lambda 4^{-\lambda} \sqrt{\pi} \Gamma(\lambda) (1 - 2\lambda)}{\lambda^2 (1 + 2\lambda) \Gamma(\lambda + \frac{3}{2})} \end{aligned}$$

$$\gamma_1 = 0$$

$$\gamma_2 = \frac{\mu_4}{\mu_2^2} - 3$$

$$\begin{aligned} \mu_4 &= \frac{3\Gamma(\lambda) \Gamma(\lambda + \frac{1}{2}) 2^{-2\lambda}}{\lambda^3 \Gamma(2\lambda + \frac{3}{2})} + \frac{2}{\lambda^4 (1 + 4\lambda)} \\ &\quad - \frac{2\sqrt{3}\Gamma(\lambda) 2^{-6\lambda} 3^{3\lambda} \Gamma(\lambda + \frac{1}{3}) \Gamma(\lambda + \frac{2}{3})}{\lambda^3 \Gamma(2\lambda + \frac{3}{2}) \Gamma(\lambda + \frac{1}{2})}. \end{aligned}$$

Notice that the $\lim_{\lambda \rightarrow 0} G(p; \lambda) = \log(p/(1-p))$

$$\begin{aligned} h[X] &= \int_0^1 \log[G'(p)] dp \\ &= \int_0^1 \log[p^{\lambda-1} + (1-p)^{\lambda-1}] dp. \end{aligned}$$

Implementation: `scipy.stats.tukeylambda`

Uniform Distribution

Standard form $x \in [0, 1]$. In general form, the lower limit is L , the upper limit is $S + L$.

$$f(x) = 1$$

$$F(x) = x$$

$$G(q) = q$$

$$\mu = \frac{1}{2}$$

$$\mu_2 = \frac{1}{12}$$

$$\gamma_1 = 0$$

$$\gamma_2 = -\frac{6}{5}$$

$$h[X] = 0$$

Implementation: `scipy.stats.uniform`

Von Mises Distribution

There is one shape parameter $\kappa > 0$, with support $x \in [-\pi, \pi]$. For values of $\kappa < 100$ the PDF and CDF formulas below are used. Otherwise, a normal approximation with variance $1/\kappa$ is used. [Note that the PDF and CDF functions below are periodic with period 2π . If an input outside $x \in [-\pi, \pi]$ is given, it is converted to the equivalent angle in this range.]

$$\begin{aligned} f(x; \kappa) &= \frac{e^{\kappa \cos x}}{2\pi I_0(\kappa)} \\ F(x; \kappa) &= \frac{1}{2} + \frac{x}{2\pi} + \sum_{k=1}^{\infty} \frac{I_k(\kappa) \sin(kx)}{I_0(\kappa) \pi k} \\ G(q; \kappa) &= F^{-1}(x; \kappa) \end{aligned}$$

where $I_k(\kappa)$ is a modified Bessel function of the first kind.

$$\begin{aligned} \mu &= 0 \\ \mu_2 &= \int_{-\pi}^{\pi} x^2 f(x; \kappa) dx \\ \gamma_1 &= 0 \\ \gamma_2 &= \frac{\int_{-\pi}^{\pi} x^4 f(x; \kappa) dx}{\mu_2^2} - 3 \end{aligned}$$

This can be used for defining circular variance.

Implementation: `scipy.stats.vonmises`

Wald Distribution

Special case of the Inverse Normal with shape parameter set to 1.0. It has support $x \geq 0$.

$$\begin{aligned} f(x) &= \frac{1}{\sqrt{2\pi x^3}} \exp\left(-\frac{(x-1)^2}{2x}\right) \\ F(x) &= \Phi\left(\frac{x-1}{\sqrt{x}}\right) + \exp(2) \Phi\left(-\frac{x+1}{\sqrt{x}}\right) \\ G(q; \mu) &= F^{-1}(q; \mu) \end{aligned}$$

$$\begin{aligned} \mu &= 1 \\ \mu_2 &= 1 \\ \gamma_1 &= 3 \\ \gamma_2 &= 15 \\ m_d &= \frac{1}{2}(\sqrt{13} - 3) \end{aligned}$$

Implementation: `scipy.stats.wald`

Weibull Maximum Extreme Value Distribution

Defined for $x < 0$ and $c > 0$.

$$\begin{aligned} f(x; c) &= c(-x)^{c-1} \exp(-(-x)^c) \\ F(x; c) &= \exp(-(-x)^c) \\ G(q; c) &= -(-\log q)^{1/c} \end{aligned}$$

The mean is the negative of the right-skewed Frechet distribution given above, and the other statistical parameters can be computed from

$$\begin{aligned} \mu'_n &= (-1)^n \Gamma\left(1 + \frac{n}{c}\right). \\ \mu &= -\Gamma\left(1 + \frac{1}{c}\right) \\ \mu_2 &= \Gamma\left(1 + \frac{2}{c}\right) - \Gamma^2\left(1 + \frac{1}{c}\right) \\ \gamma_1 &= -\frac{\Gamma\left(1 + \frac{3}{c}\right) - 3\Gamma\left(1 + \frac{2}{c}\right)\Gamma\left(1 + \frac{1}{c}\right) + 2\Gamma^3\left(1 + \frac{1}{c}\right)}{\mu_2^{3/2}} \\ \gamma_2 &= \frac{\Gamma\left(1 + \frac{4}{c}\right) - 4\Gamma\left(1 + \frac{1}{c}\right)\Gamma\left(1 + \frac{3}{c}\right) + 6\Gamma^2\left(1 + \frac{1}{c}\right)\Gamma\left(1 + \frac{2}{c}\right) - 3\Gamma^4\left(1 + \frac{1}{c}\right)}{\mu_2^2} - 3 \\ m_d &= \begin{cases} -\left(\frac{c-1}{c}\right)^{\frac{1}{c}} & \text{if } c > 1 \\ 0 & \text{if } c \leq 1 \end{cases} \\ m_n &= -\ln(2)^{\frac{1}{c}} \end{aligned}$$

$$h[X] = -\frac{\gamma}{c} - \log(c) + \gamma + 1$$

where γ is Euler's constant and equal to

$$\gamma \approx 0.57721566490153286061.$$

Implementation: `scipy.stats.weibull_max`

Weibull Minimum Extreme Value Distribution

A type of extreme-value distribution with a lower bound. Defined for $x > 0$ and $c > 0$

$$\begin{aligned} f(x; c) &= cx^{c-1} \exp(-x^c) \\ F(x; c) &= 1 - \exp(-x^c) \\ G(q; c) &= [-\log(1 - q)]^{1/c} \\ \mu'_n &= \Gamma\left(1 + \frac{n}{c}\right) \end{aligned}$$

$$\begin{aligned}\mu &= \Gamma\left(1 + \frac{1}{c}\right) \\ \mu_2 &= \Gamma\left(1 + \frac{2}{c}\right) - \Gamma^2\left(1 + \frac{1}{c}\right) \\ \gamma_1 &= \frac{\Gamma\left(1 + \frac{3}{c}\right) - 3\Gamma\left(1 + \frac{2}{c}\right)\Gamma\left(1 + \frac{1}{c}\right) + 2\Gamma^3\left(1 + \frac{1}{c}\right)}{\mu_2^{3/2}} \\ \gamma_2 &= \frac{\Gamma\left(1 + \frac{4}{c}\right) - 4\Gamma\left(1 + \frac{1}{c}\right)\Gamma\left(1 + \frac{3}{c}\right) + 6\Gamma^2\left(1 + \frac{1}{c}\right)\Gamma\left(1 + \frac{2}{c}\right) - 3\Gamma^4\left(1 + \frac{1}{c}\right)}{\mu_2^2} - 3 \\ m_d &= \begin{cases} \left(\frac{c-1}{c}\right)^{\frac{1}{c}} & \text{if } c > 1 \\ 0 & \text{if } c \leq 1 \end{cases} \\ m_n &= \ln(2)^{\frac{1}{c}}\end{aligned}$$

$$h[X] = -\frac{\gamma}{c} - \log(c) + \gamma + 1$$

where γ is Euler's constant and equal to

$$\gamma \approx 0.57721566490153286061.$$

Implementation: `scipy.stats.weibull_min`

Wrapped Cauchy Distribution

There is one shape parameter $c \in (0, 1)$ with support $x \in [0, 2\pi]$.

$$\begin{aligned}f(x; c) &= \frac{1 - c^2}{2\pi(1 + c^2 - 2c \cos x)} \\ g_c(x) &= \frac{1}{\pi} \arctan\left(\frac{1 + c}{1 - c} \tan\left(\frac{x}{2}\right)\right) \\ r_c(q) &= 2 \arctan\left(\frac{1 - c}{1 + c} \tan(\pi q)\right) \\ F(x; c) &= \begin{cases} g_c(x) & 0 \leq x < \pi \\ 1 - g_c(2\pi - x) & \pi \leq x \leq 2\pi \end{cases} \\ G(q; c) &= \begin{cases} r_c(q) & 0 \leq q < \frac{1}{2} \\ 2\pi - r_c(1 - q) & \frac{1}{2} \leq q \leq 1 \end{cases} \\ h[X] &= \log(2\pi(1 - c^2)).\end{aligned}$$

Implementation: `scipy.stats.wrapcauchy`

Random variables

There are two general distribution classes that have been implemented for encapsulating *continuous random variables* and *discrete random variables*. Over 80 continuous random variables (RVs) and 10 discrete random variables have been implemented using these classes. Besides this, new routines and distributions can be easily added by the end user. (If you create one, please contribute it.)

All of the statistics functions are located in the sub-package `scipy.stats` and a fairly complete listing of these functions can be obtained using `info(stats)`. The list of the random variables available can also be obtained from the docstring for the stats sub-package.

In the discussion below, we mostly focus on continuous RVs. Nearly everything also applies to discrete variables, but we point out some differences here: *Specific points for discrete distributions*.

In the code samples below, we assume that the `scipy.stats` package is imported as

```
>>> from scipy import stats
```

and in some cases we assume that individual objects are imported as

```
>>> from scipy.stats import norm
```

Getting help

First of all, all distributions are accompanied with help functions. To obtain just some basic information, we print the relevant docstring: `print(stats.norm.__doc__)`.

To find the support, i.e., upper and lower bounds of the distribution, call:

```
>>> print('bounds of distribution lower: %s, upper: %s' % (norm.a, norm.b))
bounds of distribution lower: -inf, upper: inf
```

We can list all methods and properties of the distribution with `dir(norm)`. As it turns out, some of the methods are private, although they are not named as such (their names do not start with a leading underscore), for example `veccdf`, are only available for internal calculation (those methods will give warnings when one tries to use them, and will be removed at some point).

To obtain the *real* main methods, we list the methods of the frozen distribution. (We explain the meaning of a *frozen* distribution below).

```
>>> rv = norm()
>>> dir(rv) # reformatted
['__class__', '__delattr__', '__dict__', '__dir__', '__doc__', '__eq__',
 '__format__', '__ge__', '__getattr__', '__gt__', '__hash__',
 '__init__', '__le__', '__lt__', '__module__', '__ne__', '__new__',
 '__reduce__', '__reduce_ex__', '__repr__', '__setattr__', '__sizeof__',
 '__str__', '__subclasshook__', '__weakref__', 'a', 'args', 'b', 'cdf',
 'dist', 'entropy', 'expect', 'interval', 'isf', 'kwds', 'logcdf',
 'logpdf', 'logpmf', 'logsf', 'mean', 'median', 'moment', 'pdf', 'pmf',
 'ppf', 'random_state', 'rvs', 'sf', 'stats', 'std', 'var']
```

Finally, we can obtain the list of available distribution through introspection:

```
>>> dist_continu = [d for d in dir(stats) if
...                 isinstance(getattr(stats, d), stats.rv_continuous)]
>>> dist_discrete = [d for d in dir(stats) if
...                  isinstance(getattr(stats, d), stats.rv_discrete)]
>>> print('number of continuous distributions: %d' % len(dist_continu))
number of continuous distributions: 101
>>> print('number of discrete distributions: %d' % len(dist_discrete))
number of discrete distributions: 16
```

Common methods

The main public methods for continuous RVs are:

- `rvs`: Random Variates
- `pdf`: Probability Density Function
- `cdf`: Cumulative Distribution Function
- `sf`: Survival Function (1-CDF)
- `ppf`: Percent Point Function (Inverse of CDF)
- `isf`: Inverse Survival Function (Inverse of SF)
- `stats`: Return mean, variance, (Fisher's) skew, or (Fisher's) kurtosis
- `moment`: non-central moments of the distribution

Let's take a normal RV as an example.

```
>>> norm.cdf(0)
0.5
```

To compute the `cdf` at a number of points, we can pass a list or a numpy array.

```
>>> norm.cdf([-1., 0, 1])
array([ 0.15865525,  0.5,  0.84134475])
>>> import numpy as np
>>> norm.cdf(np.array([-1., 0, 1]))
array([ 0.15865525,  0.5,  0.84134475])
```

Thus, the basic methods, such as `pdf`, `cdf`, and so on, are vectorized.

Other generally useful methods are supported too:

```
>>> norm.mean(), norm.std(), norm.var()
(0.0, 1.0, 1.0)
>>> norm.stats(moments="mv")
(array(0.0), array(1.0))
```

To find the median of a distribution, we can use the percent point function `ppf`, which is the inverse of the `cdf`:

```
>>> norm.ppf(0.5)
0.0
```

To generate a sequence of random variates, use the `size` keyword argument:

```
>>> norm.rvs(size=3)
array([-0.35687759,  1.34347647, -0.11710531]) # random
```

Note that drawing random numbers relies on generators from `numpy.random` package. In the example above, the specific stream of random numbers is not reproducible across runs. To achieve reproducibility, you can explicitly seed a global variable

```
>>> np.random.seed(1234)
```

Relying on a global state is not recommended, though. A better way is to use the `random_state` parameter, which accepts an instance of `numpy.random.RandomState` class, or an integer, which is then used to seed an internal `RandomState` object:

```
>>> norm.rvs(size=5, random_state=1234)
array([ 0.47143516, -1.19097569,  1.43270697, -0.3126519 , -0.72058873])
```

Don't think that `norm.rvs(5)` generates 5 variates:

```
>>> norm.rvs(5)
5.471435163732493
```

Here, 5 with no keyword is being interpreted as the first possible keyword argument, `loc`, which is the first of a pair of keyword arguments taken by all continuous distributions. This brings us to the topic of the next subsection.

Shifting and scaling

All continuous distributions take `loc` and `scale` as keyword parameters to adjust the location and scale of the distribution, e.g., for the standard normal distribution, the location is the mean and the scale is the standard deviation.

```
>>> norm.stats(loc=3, scale=4, moments="mv")
(array(3.0), array(16.0))
```

In many cases, the standardized distribution for a random variable X is obtained through the transformation $(X - \text{loc}) / \text{scale}$. The default values are `loc = 0` and `scale = 1`.

Smart use of `loc` and `scale` can help modify the standard distributions in many ways. To illustrate the scaling further, the `cdf` of an exponentially distributed RV with mean $1/\lambda$ is given by

$$F(x) = 1 - \exp(-\lambda x)$$

By applying the scaling rule above, it can be seen that by taking `scale = 1./lambda` we get the proper scale.

```
>>> from scipy.stats import expon
>>> expon.mean(scale=3.)
3.0
```

Note: Distributions that take shape parameters may require more than simple application of `loc` and/or `scale` to achieve the desired form. For example, the distribution of 2-D vector lengths given a constant vector of length R perturbed by independent $N(0, \sigma^2)$ deviations in each component is `rice(R/σ , scale= σ)`. The first argument is a shape parameter that needs to be scaled along with x .

The uniform distribution is also interesting:

```
>>> from scipy.stats import uniform
>>> uniform.cdf([0, 1, 2, 3, 4, 5], loc=1, scale=4)
array([ 0. ,  0. ,  0.25,  0.5 ,  0.75,  1.  ])
```

Finally, recall from the previous paragraph that we are left with the problem of the meaning of `norm.rvs(5)`. As it turns out, calling a distribution like this, the first argument, i.e., the 5, gets passed to set the `loc` parameter. Let's see:

```
>>> np.mean(norm.rvs(5, size=500))
5.0098355106969992
```

Thus, to explain the output of the example of the last section: `norm.rvs(5)` generates a single normally distributed random variate with mean `loc=5`, because of the default `size=1`.

We recommend that you set `loc` and `scale` parameters explicitly, by passing the values as keywords rather than as arguments. Repetition can be minimized when calling more than one method of a given RV by using the technique of *Freezing a Distribution*, as explained below.

Shape parameters

While a general continuous random variable can be shifted and scaled with the `loc` and `scale` parameters, some distributions require additional shape parameters. For instance, the gamma distribution with density

$$\gamma(x, a) = \frac{\lambda(\lambda x)^{a-1}}{\Gamma(a)} e^{-\lambda x},$$

requires the shape parameter a . Observe that setting λ can be obtained by setting the `scale` keyword to $1/\lambda$.

Let's check the number and name of the shape parameters of the gamma distribution. (We know from the above that this should be 1.)

```
>>> from scipy.stats import gamma
>>> gamma.numargs
1
>>> gamma.shapes
'a'
```

Now, we set the value of the shape variable to 1 to obtain the exponential distribution, so that we compare easily whether we get the results we expect.

```
>>> gamma(1, scale=2.).stats(moments="mv")
(array(2.0), array(4.0))
```

Notice that we can also specify shape parameters as keywords:

```
>>> gamma(a=1, scale=2.).stats(moments="mv")
(array(2.0), array(4.0))
```

Freezing a distribution

Passing the `loc` and `scale` keywords time and again can become quite bothersome. The concept of *freezing* a RV is used to solve such problems.

```
>>> rv = gamma(1, scale=2.)
```

By using `rv` we no longer have to include the scale or the shape parameters anymore. Thus, distributions can be used in one of two ways, either by passing all distribution parameters to each method call (such as we did earlier) or by freezing the parameters for the instance of the distribution. Let us check this:

```
>>> rv.mean(), rv.std()
(2.0, 2.0)
```

This is, indeed, what we should get.

Broadcasting

The basic methods `pdf`, and so on, satisfy the usual numpy broadcasting rules. For example, we can calculate the critical values for the upper tail of the t distribution for different probabilities and degrees of freedom.

```
>>> stats.t.isf([0.1, 0.05, 0.01], [[10], [11]])
array([[ 1.37218364,  1.81246112,  2.76376946],
       [ 1.36343032,  1.79588482,  2.71807918]])
```

Here, the first row contains the critical values for 10 degrees of freedom and the second row for 11 degrees of freedom (d.o.f.). Thus, the broadcasting rules give the same result of calling `isf` twice:

```
>>> stats.t.isf([0.1, 0.05, 0.01], 10)
array([ 1.37218364,  1.81246112,  2.76376946])
>>> stats.t.isf([0.1, 0.05, 0.01], 11)
array([ 1.36343032,  1.79588482,  2.71807918])
```

If the array with probabilities, i.e., [0.1, 0.05, 0.01] and the array of degrees of freedom i.e., [10, 11, 12], have the same array shape, then element-wise matching is used. As an example, we can obtain the 10% tail for 10 d.o.f., the 5% tail for 11 d.o.f. and the 1% tail for 12 d.o.f. by calling

```
>>> stats.t.isf([0.1, 0.05, 0.01], [10, 11, 12])
array([ 1.37218364,  1.79588482,  2.68099799])
```

Specific points for discrete distributions

Discrete distributions have mostly the same basic methods as the continuous distributions. However `pdf` is replaced by the probability mass function `pmf`, no estimation methods, such as `fit`, are available, and `scale` is not a valid keyword parameter. The location parameter, keyword `loc`, can still be used to shift the distribution.

The computation of the cdf requires some extra attention. In the case of continuous distribution, the cumulative distribution function is, in most standard cases, strictly monotonic increasing in the bounds (a,b) and has, therefore, a unique inverse. The cdf of a discrete distribution, however, is a step function, hence the inverse cdf, i.e., the percent point function, requires a different definition:

```
ppf(q) = min{x : cdf(x) >= q, x integer}
```

For further info, see the docs [here](#).

We can look at the hypergeometric distribution as an example

```
>>> from scipy.stats import hypergeom
>>> [M, n, N] = [20, 7, 12]
```

If we use the cdf at some integer points and then evaluate the ppf at those cdf values, we get the initial integers back, for example

```
>>> x = np.arange(4)*2
>>> x
array([0, 2, 4, 6])
>>> prb = hypergeom.cdf(x, M, n, N)
>>> prb
array([ 1.03199174e-04,  5.21155831e-02,  6.08359133e-01,
        9.89783282e-01])
>>> hypergeom.ppf(prb, M, n, N)
array([ 0.,  2.,  4.,  6.])
```

If we use values that are not at the kinks of the cdf step function, we get the next higher integer back:

```
>>> hypergeom.ppf(prb + 1e-8, M, n, N)
array([ 1.,  3.,  5.,  7.])
>>> hypergeom.ppf(prb - 1e-8, M, n, N)
array([ 0.,  2.,  4.,  6.])
```

Fitting distributions

The main additional methods of the not frozen distribution are related to the estimation of distribution parameters:

- *fit*: *maximum likelihood estimation of distribution parameters, including location* and scale
- `fit_loc_scale`: estimation of location and scale when shape parameters are given
- `nnlf`: negative log likelihood function
- `expect`: calculate the expectation of a function against the pdf or pmf

Performance issues and cautionary remarks

The performance of the individual methods, in terms of speed, varies widely by distribution and method. The results of a method are obtained in one of two ways: either by explicit calculation, or by a generic algorithm that is independent of the specific distribution.

Explicit calculation, on the one hand, requires that the method is directly specified for the given distribution, either through analytic formulas or through special functions in `scipy.special` or `numpy.random` for `rvs`. These are usually relatively fast calculations.

The generic methods, on the other hand, are used if the distribution does not specify any explicit calculation. To define a distribution, only one of pdf or cdf is necessary; all other methods can be derived using numeric integration and root finding. However, these indirect methods can be *very* slow. As an example, `rgn = stats.gausshyper.rvs(0.5, 2, 2, 2, size=100)` creates random variables in a very indirect way and takes about 19 seconds for 100 random variables on my computer, while one million random variables from the standard normal or from the t distribution take just above one second.

Remaining issues

The distributions in `scipy.stats` have recently been corrected and improved and gained a considerable test suite; however, a few issues remain:

- The distributions have been tested over some range of parameters; however, in some corner ranges, a few incorrect results may remain.
- The maximum likelihood estimation in *fit* does not work with default starting parameters for all distributions and the user needs to supply good starting parameters. Also, for some distribution using a maximum likelihood estimator might inherently not be the best choice.

Building specific distributions

The next examples shows how to build your own distributions. Further examples show the usage of the distributions and some statistical tests.

Making a continuous distribution, i.e., subclassing `rv_continuous`

Making continuous distributions is fairly simple.

```
>>> from scipy import stats
>>> class deterministic_gen(stats.rv_continuous):
...     def _cdf(self, x):
...         return np.where(x < 0, 0., 1.)
...     def _stats(self):
...         return 0., 0., 0., 0.
```

```
>>> deterministic = deterministic_gen(name="deterministic")
>>> deterministic.cdf(np.arange(-3, 3, 0.5))
array([ 0.,  0.,  0.,  0.,  0.,  0.,  1.,  1.,  1.,  1.,  1.,  1.])
```

Interestingly, the pdf is now computed automatically:

```
>>> deterministic.pdf(np.arange(-3, 3, 0.5))
array([ 0.00000000e+00,  0.00000000e+00,  0.00000000e+00,
        0.00000000e+00,  0.00000000e+00,  0.00000000e+00,
        5.83333333e+04,  4.16333634e-12,  4.16333634e-12,
        4.16333634e-12,  4.16333634e-12,  4.16333634e-12])
```

Be aware of the performance issues mentioned in *Performance issues and cautionary remarks*. The computation of unspecified common methods can become very slow, since only general methods are called, which, by their very nature, cannot use any specific information about the distribution. Thus, as a cautionary example:

```
>>> from scipy.integrate import quad
>>> quad(deterministic.pdf, -1e-1, 1e-1)
(4.163336342344337e-13, 0.0)
```

But this is not correct: the integral over this pdf should be 1. Let's make the integration interval smaller:

```
>>> quad(deterministic.pdf, -1e-3, 1e-3) # warning removed
(1.000076872229173, 0.0010625571718182458)
```

This looks better. However, the problem originated from the fact that the pdf is not specified in the class definition of the deterministic distribution.

Subclassing `rv_discrete`

In the following, we use `stats.rv_discrete` to generate a discrete distribution that has the probabilities of the truncated normal for the intervals centered around the integers.

General info

From the docstring of `rv_discrete`, `help(stats.rv_discrete)`,

“You can construct an arbitrary discrete rv where $P\{X=x_k\} = p_k$ by passing to the `rv_discrete` initialization method (through the `values=` keyword) a tuple of sequences (x_k, p_k) which describes only those values of X (x_k) that occur with nonzero probability (p_k).”

Next to this, there are some further requirements for this approach to work:

- The keyword `name` is required.
- The support points of the distribution x_k have to be integers.
- The number of significant digits (decimals) needs to be specified.

In fact, if the last two requirements are not satisfied, an exception may be raised or the resulting numbers may be incorrect.

An example

Let's do the work. First:

```
>>> npoints = 20 # number of integer support points of the distribution_
    ↪minus 1
>>> npointsh = npoints // 2
>>> npointsf = float(npoints)
```

(continues on next page)

(continued from previous page)

```

>>> nbound = 4 # bounds for the truncated normal
>>> normbound = (1+1/npointsf) * nbound # actual bounds of truncated normal
>>> grid = np.arange(-npointsh, npointsh+2, 1) # integer grid
>>> gridlimitsnorm = (grid-0.5) / npointsh * nbound # bin limits for the
    ↪truncnorm
>>> gridlimits = grid - 0.5 # used later in the analysis
>>> grid = grid[:-1]
>>> probs = np.diff(stats.truncnorm.cdf(gridlimitsnorm, -normbound,
    ↪normbound))
>>> gridint = grid

```

And, finally, we can subclass `rv_discrete`:

```

>>> normdiscrete = stats.rv_discrete(values=(gridint,
...     np.round(probs, decimals=7)), name='normdiscrete')

```

Now that we have defined the distribution, we have access to all common methods of discrete distributions.

```

>>> print('mean = %6.4f, variance = %6.4f, skew = %6.4f, kurtosis = %6.4f' %
...     normdiscrete.stats(moments='mvsk'))
mean = -0.0000, variance = 6.3302, skew = 0.0000, kurtosis = -0.0076

```

```

>>> nd_std = np.sqrt(normdiscrete.stats(moments='v'))

```

Testing the implementation

Let's generate a random sample and compare observed frequencies with the probabilities.

```



>>> n_sample = 500
>>> np.random.seed(87655678) # fix the seed for replicability
>>> rvs = normdiscrete.rvs(size=n_sample)
>>> f, l = np.histogram(rvs, bins=gridlimits)
>>> sfreq = np.vstack([gridint, f, probs*n_sample]).T
>>> print(sfreq)
[[-1.00000000e+01  0.00000000e+00  2.95019349e-02]
 [-9.00000000e+00  0.00000000e+00  1.32294142e-01]
 [-8.00000000e+00  0.00000000e+00  5.06497902e-01]
 [-7.00000000e+00  2.00000000e+00  1.65568919e+00]
 [-6.00000000e+00  1.00000000e+00  4.62125309e+00]
 [-5.00000000e+00  9.00000000e+00  1.10137298e+01]
 [-4.00000000e+00  2.60000000e+01  2.24137683e+01]
 [-3.00000000e+00  3.70000000e+01  3.89503370e+01]
 [-2.00000000e+00  5.10000000e+01  5.78004747e+01]
 [-1.00000000e+00  7.10000000e+01  7.32455414e+01]
 [ 0.00000000e+00  7.40000000e+01  7.92618251e+01]
 [ 1.00000000e+00  8.90000000e+01  7.32455414e+01]
 [ 2.00000000e+00  5.50000000e+01  5.78004747e+01]
 [ 3.00000000e+00  5.00000000e+01  3.89503370e+01]
 [ 4.00000000e+00  1.70000000e+01  2.24137683e+01]
 [ 5.00000000e+00  1.10000000e+01  1.10137298e+01]
 [ 6.00000000e+00  4.00000000e+00  4.62125309e+00]
 [ 7.00000000e+00  3.00000000e+00  1.65568919e+00]
 [ 8.00000000e+00  0.00000000e+00  5.06497902e-01]

```

(continues on next page)

(continued from previous page)

```
[ 9.00000000e+00  0.00000000e+00  1.32294142e-01]
[ 1.00000000e+01  0.00000000e+00  2.95019349e-02]]
```



Next, we can test whether our sample was generated by our norm-discrete distribution. This also verifies whether the random numbers were generated correctly.

The chi-square test requires that there are a minimum number of observations in each bin. We combine the tail bins into larger bins so that they contain enough observations.

```
>>> f2 = np.hstack([f[:5].sum(), f[5:-5], f[-5:].sum()])
>>> p2 = np.hstack([probs[:5].sum(), probs[5:-5], probs[-5:].sum()])
>>> ch2, pval = stats.chisquare(f2, p2*n_sample)
```

```
>>> print('chisquare for normdiscrete: chi2 = %6.3f pvalue = %6.4f' % (ch2,
↳pval))
chisquare for normdiscrete: chi2 = 12.466 pvalue = 0.4090
```

The pvalue in this case is high, so we can be quite confident that our random sample was actually generated by the distribution.

Analysing one sample

First, we create some random variables. We set a seed so that in each run we get identical results to look at. As an example we take a sample from the Student t distribution:

```
>>> np.random.seed(282629734)
>>> x = stats.t.rvs(10, size=1000)
```

Here, we set the required shape parameter of the t distribution, which in statistics corresponds to the degrees of freedom, to 10. Using `size=1000` means that our sample consists of 1000 independently drawn (pseudo) random numbers. Since we did not specify the keyword arguments `loc` and `scale`, those are set to their default values zero and one.

Descriptive statistics

`x` is a numpy array, and we have direct access to all array methods, e.g.,

```
>>> print(x.min()) # equivalent to np.min(x)
-3.78975572422
>>> print(x.max()) # equivalent to np.max(x)
5.26327732981
>>> print(x.mean()) # equivalent to np.mean(x)
0.0140610663985
>>> print(x.var()) # equivalent to np.var(x)
1.28899386208
```

How do the sample properties compare to their theoretical counterparts?

```
>>> m, v, s, k = stats.t.stats(10, moments='mvsk')
>>> n, (smin, smax), sm, sv, ss, sk = stats.describe(x)
```

```
>>> sstr = '%-14s mean = %6.4f, variance = %6.4f, skew = %6.4f, kurtosis =
↳%6.4f'
>>> print(sstr % ('distribution:', m, v, s, k))
distribution: mean = 0.0000, variance = 1.2500, skew = 0.0000, kurtosis = 1.
↳0000
>>> print(sstr % ('sample:', sm, sv, ss, sk))
sample: mean = 0.0141, variance = 1.2903, skew = 0.2165, kurtosis = 1.
↳0556
```

Note: `stats.describe` uses the unbiased estimator for the variance, while `np.var` is the biased estimator.

For our sample the sample statistics differ a by a small amount from their theoretical counterparts.

T-test and KS-test

We can use the t-test to test whether the mean of our sample differs in a statistically significant way from the theoretical expectation.

```
>>> print('t-statistic = %6.3f pvalue = %6.4f' % stats.ttest_1samp(x, m))
t-statistic = 0.391 pvalue = 0.6955
```

The pvalue is 0.7, this means that with an alpha error of, for example, 10%, we cannot reject the hypothesis that the sample mean is equal to zero, the expectation of the standard t-distribution.

As an exercise, we can calculate our ttest also directly without using the provided function, which should give us the same answer, and so it does:

```
>>> tt = (sm-m)/np.sqrt(sv/float(n)) # t-statistic for mean
>>> pval = stats.t.sf(np.abs(tt), n-1)*2 # two-sided pvalue = Prob(abs(t)>tt)
>>> print('t-statistic = %6.3f pvalue = %6.4f' % (tt, pval))
t-statistic = 0.391 pvalue = 0.6955
```

The Kolmogorov-Smirnov test can be used to test the hypothesis that the sample comes from the standard t-distribution

```
>>> print('KS-statistic D = %6.3f pvalue = %6.4f' % stats.kstest(x, 't', (10,
->)))
KS-statistic D = 0.016 pvalue = 0.9571
```

Again, the p-value is high enough that we cannot reject the hypothesis that the random sample really is distributed according to the t-distribution. In real applications, we don't know what the underlying distribution is. If we perform the Kolmogorov-Smirnov test of our sample against the standard normal distribution, then we also cannot reject the hypothesis that our sample was generated by the normal distribution given that, in this example, the p-value is almost 40%.

```
>>> print('KS-statistic D = %6.3f pvalue = %6.4f' % stats.kstest(x, 'norm'))
KS-statistic D = 0.028 pvalue = 0.3918
```

However, the standard normal distribution has a variance of 1, while our sample has a variance of 1.29. If we standardize our sample and test it against the normal distribution, then the p-value is again large enough that we cannot reject the hypothesis that the sample came from the normal distribution.

```
>>> d, pval = stats.kstest((x-x.mean())/x.std(), 'norm')
>>> print('KS-statistic D = %6.3f pvalue = %6.4f' % (d, pval))
KS-statistic D = 0.032 pvalue = 0.2397
```

Note: The Kolmogorov-Smirnov test assumes that we test against a distribution with given parameters, since, in the last case, we estimated mean and variance, this assumption is violated and the distribution of the test statistic, on which the p-value is based, is not correct.

Tails of the distribution

Finally, we can check the upper tail of the distribution. We can use the percent point function `ppf`, which is the inverse of the cdf function, to obtain the critical values, or, more directly, we can use the inverse of the survival function

```
>>> crit01, crit05, crit10 = stats.t.ppf([1-0.01, 1-0.05, 1-0.10], 10)
>>> print('critical values from ppf at 1%, 5% and 10% %8.4f %8.4f %8.4f'
->% (crit01, crit05, crit10))
critical values from ppf at 1%, 5% and 10% 2.7638 1.8125 1.3722
```

(continues on next page)

(continued from previous page)

```
>>> print('critical values from isf at 1%%, 5%% and 10%% %8.4f %8.4f %8.4f'
↳ tuple(stats.t.isf([0.01,0.05,0.10],10))
critical values from isf at 1%, 5% and 10% 2.7638 1.8125 1.3722
```

```
>>> freq01 = np.sum(x>crit01) / float(n) * 100
>>> freq05 = np.sum(x>crit05) / float(n) * 100
>>> freq10 = np.sum(x>crit10) / float(n) * 100
>>> print('sample %%-frequency at 1%%, 5%% and 10%% tail %8.4f %8.4f %8.4f'
↳ (freq01, freq05, freq10))
sample %-frequency at 1%, 5% and 10% tail 1.4000 5.8000 10.5000
```

In all three cases, our sample has more weight in the top tail than the underlying distribution. We can briefly check a larger sample to see if we get a closer match. In this case, the empirical frequency is quite close to the theoretical probability, but if we repeat this several times, the fluctuations are still pretty large.

```
>>> freq05l = np.sum(stats.t.rvs(10, size=10000) > crit05) / 10000.0 * 100
>>> print('larger sample %%-frequency at 5%% tail %8.4f' % freq05l)
larger sample %-frequency at 5% tail 4.8000
```

We can also compare it with the tail of the normal distribution, which has less weight in the tails:

```
>>> print('tail prob. of normal at 1%%, 5%% and 10%% %8.4f %8.4f %8.4f' %
... tuple(stats.norm.sf([crit01, crit05, crit10])*100))
tail prob. of normal at 1%, 5% and 10% 0.2857 3.4957 8.5003
```

The chisquare test can be used to test whether for a finite number of bins, the observed frequencies differ significantly from the probabilities of the hypothesized distribution.

```
>>> quantiles = [0.0, 0.01, 0.05, 0.1, 1-0.10, 1-0.05, 1-0.01, 1.0]
>>> crit = stats.t.ppf(quantiles, 10)
>>> crit
array([-inf, -2.76376946, -1.81246112, -1.37218364, 1.37218364,
       1.81246112, 2.76376946, inf])
>>> n_sample = x.size
>>> freqcount = np.histogram(x, bins=crit)[0]
>>> tprob = np.diff(quantiles)
>>> nprob = np.diff(stats.norm.cdf(crit))
>>> tch, tpval = stats.chisquare(freqcount, tprob*n_sample)
>>> nch, npval = stats.chisquare(freqcount, nprob*n_sample)
>>> print('chisquare for t: chi2 = %6.2f pvalue = %6.4f' % (tch, tpval))
chisquare for t: chi2 = 2.30 pvalue = 0.8901
>>> print('chisquare for normal: chi2 = %6.2f pvalue = %6.4f' % (nch, npval))
chisquare for normal: chi2 = 64.60 pvalue = 0.0000
```

We see that the standard normal distribution is clearly rejected, while the standard t-distribution cannot be rejected. Since the variance of our sample differs from both standard distributions, we can again redo the test taking the estimate for scale and location into account.

The fit method of the distributions can be used to estimate the parameters of the distribution, and the test is repeated using probabilities of the estimated distribution.

```
>>> tdof, tloc, tscale = stats.t.fit(x)
>>> nloc, nscale = stats.norm.fit(x)
```

(continues on next page)

(continued from previous page)

```

>>> tprob = np.diff(stats.t.cdf(crit, tdof, loc=tloc, scale=tscale))
>>> nprob = np.diff(stats.norm.cdf(crit, loc=nloc, scale=nscale))
>>> tch, tpval = stats.chisquare(freqcount, tprob*n_sample)
>>> nch, npval = stats.chisquare(freqcount, nprob*n_sample)
>>> print('chisquare for t:      chi2 = %6.2f pvalue = %6.4f' % (tch, tpval))
chisquare for t:      chi2 =  1.58 pvalue = 0.9542
>>> print('chisquare for normal: chi2 = %6.2f pvalue = %6.4f' % (nch, npval))
chisquare for normal: chi2 = 11.08 pvalue = 0.0858

```

Taking account of the estimated parameters, we can still reject the hypothesis that our sample came from a normal distribution (at the 5% level), but again, with a p-value of 0.95, we cannot reject the t-distribution.

Special tests for normal distributions

Since the normal distribution is the most common distribution in statistics, there are several additional functions available to test whether a sample could have been drawn from a normal distribution.

First, we can test if skew and kurtosis of our sample differ significantly from those of a normal distribution:

```

>>> print('normal skewtest teststat = %6.3f pvalue = %6.4f' % stats.
↳skewtest(x))
normal skewtest teststat =  2.785 pvalue = 0.0054
>>> print('normal kurtosistest teststat = %6.3f pvalue = %6.4f' % stats.
↳kurtosistest(x))
normal kurtosistest teststat =  4.757 pvalue = 0.0000

```

These two tests are combined in the normality test

```

>>> print('normaltest teststat = %6.3f pvalue = %6.4f' % stats.normaltest(x))
normaltest teststat = 30.379 pvalue = 0.0000

```

In all three tests, the p-values are very low and we can reject the hypothesis that the our sample has skew and kurtosis of the normal distribution.

Since skew and kurtosis of our sample are based on central moments, we get exactly the same results if we test the standardized sample:

```

>>> print('normaltest teststat = %6.3f pvalue = %6.4f' %
...       stats.normaltest((x-x.mean())/x.std()))
normaltest teststat = 30.379 pvalue = 0.0000

```

Because normality is rejected so strongly, we can check whether the normaltest gives reasonable results for other cases:

```

>>> print('normaltest teststat = %6.3f pvalue = %6.4f' %
...       stats.normaltest(stats.t.rvs(10, size=100)))
normaltest teststat =  4.698 pvalue = 0.0955
>>> print('normaltest teststat = %6.3f pvalue = %6.4f' %
...       stats.normaltest(stats.norm.rvs(size=1000)))
normaltest teststat =  0.613 pvalue = 0.7361

```

When testing for normality of a small sample of t-distributed observations and a large sample of normal-distributed observations, then in neither case can we reject the null hypothesis that the sample comes from a normal distribution. In the first case, this is because the test is not powerful enough to distinguish a t and a normally distributed random variable in a small sample.

Comparing two samples

In the following, we are given two samples, which can come either from the same or from different distribution, and we want to test whether these samples have the same statistical properties.

Comparing means

Test with sample with identical means:

```
>>> rvs1 = stats.norm.rvs(loc=5, scale=10, size=500)
>>> rvs2 = stats.norm.rvs(loc=5, scale=10, size=500)
>>> stats.ttest_ind(rvs1, rvs2)
Ttest_indResult(statistic=-0.5489036175088705, pvalue=0.5831943748663959)
```

Test with sample with different means:

```
>>> rvs3 = stats.norm.rvs(loc=8, scale=10, size=500)
>>> stats.ttest_ind(rvs1, rvs3)
Ttest_indResult(statistic=-4.533414290175026, pvalue=6.507128186389019e-06)
```

Kolmogorov-Smirnov test for two samples `ks_2samp`

For the example, where both samples are drawn from the same distribution, we cannot reject the null hypothesis, since the pvalue is high

```
>>> stats.ks_2samp(rvs1, rvs2)
KstestResult(statistic=0.026, pvalue=0.9959527565364388)
```

In the second example, with different location, i.e., means, we can reject the null hypothesis, since the pvalue is below 1%

```
>>> stats.ks_2samp(rvs1, rvs3)
KstestResult(statistic=0.114, pvalue=0.00299005061044668)
```

Kernel density estimation

A common task in statistics is to estimate the probability density function (PDF) of a random variable from a set of data samples. This task is called density estimation. The most well-known tool to do this is the histogram. A histogram is a useful tool for visualization (mainly because everyone understands it), but doesn't use the available data very efficiently. Kernel density estimation (KDE) is a more efficient tool for the same task. The *gaussian_kde* estimator can be used to estimate the PDF of univariate as well as multivariate data. It works best if the data is unimodal.

Univariate estimation

We start with a minimal amount of data in order to see how *gaussian_kde* works and what the different options for bandwidth selection do. The data sampled from the PDF are shown as blue dashes at the bottom of the figure (this is called a rug plot):


```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
```

```
>>> x1 = np.array([-7, -5, 1, 4, 5], dtype=np.float64)
>>> kde1 = stats.gaussian_kde(x1)
>>> kde2 = stats.gaussian_kde(x1, bw_method='silverman')
```

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
```

```
>>> ax.plot(x1, np.zeros(x1.shape), 'b+', ms=20) # rug plot
>>> x_eval = np.linspace(-10, 10, num=200)
>>> ax.plot(x_eval, kde1(x_eval), 'k-', label="Scott's Rule")
>>> ax.plot(x_eval, kde2(x_eval), 'r-', label="Silverman's Rule")
```

```
>>> plt.show()
```



We see that there is very little difference between Scott's Rule and Silverman's Rule, and that the bandwidth selection with a limited amount of data is probably a bit too wide. We can define our own bandwidth function to get a less smoothed-out result.

```
>>> def my_kde_bandwidth(obj, fac=1./5):
...     """We use Scott's Rule, multiplied by a constant factor."""
...     return np.power(obj.n, -1./(obj.d+4)) * fac
```


```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
```

```
>>> ax.plot(x1, np.zeros(x1.shape), 'b+', ms=20) # rug plot
>>> kde3 = stats.gaussian_kde(x1, bw_method=my_kde_bandwidth)
>>> ax.plot(x_eval, kde3(x_eval), 'g-', label="With smaller BW")
```

```
>>> plt.show()
```

We see that if we set bandwidth to be very narrow, the obtained estimate for the probability density function (PDF) is simply the sum of Gaussians around each data point.

We now take a more realistic example and look at the difference between the two available bandwidth selection rules. Those rules are known to work well for (close to) normal distributions, but even for unimodal distributions that are quite strongly non-normal they work reasonably well. As a non-normal distribution we take a Student's T distribution with 5 degrees of freedom.



```

import numpy as np
import matplotlib.pyplot as plt
from scipy import stats

np.random.seed(12456)
x1 = np.random.normal(size=200) # random data, normal distribution
xs = np.linspace(x1.min()-1, x1.max()+1, 200)

kde1 = stats.gaussian_kde(x1)
kde2 = stats.gaussian_kde(x1, bw_method='silverman')

fig = plt.figure(figsize=(8, 6))

ax1 = fig.add_subplot(211)
ax1.plot(x1, np.zeros(x1.shape), 'b+', ms=12) # rug plot
ax1.plot(xs, kde1(xs), 'k-', label="Scott's Rule")
ax1.plot(xs, kde2(xs), 'b-', label="Silverman's Rule")
ax1.plot(xs, stats.norm.pdf(xs), 'r--', label="True PDF")

ax1.set_xlabel('x')
ax1.set_ylabel('Density')
ax1.set_title("Normal (top) and Student's T_{df=5} (bottom) distributions")
ax1.legend(loc=1)

x2 = stats.t.rvs(5, size=200) # random data, T distribution
xs = np.linspace(x2.min() - 1, x2.max() + 1, 200)

kde3 = stats.gaussian_kde(x2)
kde4 = stats.gaussian_kde(x2, bw_method='silverman')

ax2 = fig.add_subplot(212)
ax2.plot(x2, np.zeros(x2.shape), 'b+', ms=12) # rug plot

```

(continues on next page)

(continued from previous page)


```

ax2.plot(xs, kde3(xs), 'k-', label="Scott's Rule")
ax2.plot(xs, kde4(xs), 'b-', label="Silverman's Rule")
ax2.plot(xs, stats.t.pdf(xs, 5), 'r--', label="True PDF")

ax2.set_xlabel('x')
ax2.set_ylabel('Density')

plt.show()

```



We now take a look at a bimodal distribution with one wider and one narrower Gaussian feature. We expect that this will be a more difficult density to approximate, due to the different bandwidths required to accurately resolve each feature.

```
>>> from functools import partial
```

```

>>> loc1, scale1, size1 = (-2, 1, 175)
>>> loc2, scale2, size2 = (2, 0.2, 50)
>>> x2 = np.concatenate([np.random.normal(loc=loc1, scale=scale1, size=size1),
...                       np.random.normal(loc=loc2, scale=scale2,
... size=size2)])

```

```
>>> x_eval = np.linspace(x2.min() - 1, x2.max() + 1, 500)
```

```
>>> kde = stats.gaussian_kde(x2)
>>> kde2 = stats.gaussian_kde(x2, bw_method='silverman')
>>> kde3 = stats.gaussian_kde(x2, bw_method=partial(my_kde_bandwidth, fac=0.
↳2))
>>> kde4 = stats.gaussian_kde(x2, bw_method=partial(my_kde_bandwidth, fac=0.
↳5))
```

```
>>> pdf = stats.norm.pdf
>>> bimodal_pdf = pdf(x_eval, loc=loc1, scale=scale1) * float(size1) / x2.
↳size + \
...         pdf(x_eval, loc=loc2, scale=scale2) * float(size2) / x2.size
```

```
>>> fig = plt.figure(figsize=(8, 6))
>>> ax = fig.add_subplot(111)
```

```
>>> ax.plot(x2, np.zeros(x2.shape), 'b+', ms=12)
>>> ax.plot(x_eval, kde(x_eval), 'k-', label="Scott's Rule")
>>> ax.plot(x_eval, kde2(x_eval), 'b-', label="Silverman's Rule")
>>> ax.plot(x_eval, kde3(x_eval), 'g-', label="Scott * 0.2")
>>> ax.plot(x_eval, kde4(x_eval), 'c-', label="Scott * 0.5")
>>> ax.plot(x_eval, bimodal_pdf, 'r--', label="Actual PDF")
```

```
>>> ax.set_xlim([x_eval.min(), x_eval.max()])
>>> ax.legend(loc=2)
>>> ax.set_xlabel('x')
>>> ax.set_ylabel('Density')
>>> plt.show()
```

As expected, the KDE is not as close to the true PDF as we would like due to the different characteristic size of the two features of the bimodal distribution. By halving the default bandwidth (Scott * 0.5), we can do somewhat better, while using a factor 5 smaller bandwidth than the default doesn't smooth enough. What we really need, though, in this case, is a non-uniform (adaptive) bandwidth.


Multivariate estimation

With `gaussian_kde` we can perform multivariate, as well as univariate estimation. We demonstrate the bivariate case. First, we generate some random data with a model in which the two variates are correlated.

```
>>> def measure(n):
...     """Measurement model, return two coupled measurements."""
...     m1 = np.random.normal(size=n)
...     m2 = np.random.normal(scale=0.5, size=n)
...     return m1+m2, m1-m2
```

```
>>> m1, m2 = measure(2000)
>>> xmin = m1.min()
>>> xmax = m1.max()
>>> ymin = m2.min()
>>> ymax = m2.max()
```

Then we apply the KDE to the data:



```
>>> X, Y = np.mgrid[xmin:xmax:100j, ymin:ymax:100j]
>>> positions = np.vstack([X.ravel(), Y.ravel()])
>>> values = np.vstack([m1, m2])
>>> kernel = stats.gaussian_kde(values)
>>> Z = np.reshape(kernel.evaluate(positions).T, X.shape)
```


Finally, we plot the estimated bivariate distribution as a colormap and plot the individual data points on top.

```
>>> fig = plt.figure(figsize=(8, 6))
>>> ax = fig.add_subplot(111)
```

```
>>> ax.imshow(np.rot90(Z), cmap=plt.cm.gist_earth_r,
...           extent=[xmin, xmax, ymin, ymax])
>>> ax.plot(m1, m2, 'k.', markersize=2)
```

```
>>> ax.set_xlim([xmin, xmax])
>>> ax.set_ylim([ymin, ymax])
```

```
>>> plt.show()
```



Multiscale Graph Correlation (MGC)

With `multiscale_graphcorr`, we can test for independence on high dimensional and nonlinear data. Before we start, let's import some useful packages:

```
>>> import numpy as np
>>> import matplotlib.pyplot as plt; plt.style.use('classic')
>>> from scipy.stats import multiscale_graphcorr
```

Let's use a custom plotting function to plot the data relationship:


```
>>> def mgc_plot(x, y, sim_name, mgc_dict=None, only_viz=False,
...             only_mgc=False):
...     """Plot sim and MGC-plot"""
...     if not only_mgc:
...         # simulation
...         plt.figure(figsize=(8, 8))
...         ax = plt.gca()
...         ax.set_title(sim_name + " Simulation", fontsize=20)
...         ax.scatter(x, y)
...         ax.set_xlabel('X', fontsize=15)
...         ax.set_ylabel('Y', fontsize=15)
...         ax.axis('equal')
...         ax.tick_params(axis="x", labelsz=15)
...         ax.tick_params(axis="y", labelsz=15)
...         plt.show()
...     if not only_viz:
...         # local correlation map
...         plt.figure(figsize=(8,8))
...         ax = plt.gca()
...         mgc_map = mgc_dict["mgc_map"]
...         # draw heatmap
...         ax.set_title("Local Correlation Map", fontsize=20)
...         im = ax.imshow(mgc_map, cmap='YlGnBu')
...         # colorbar
...         cbar = ax.figure.colorbar(im, ax=ax)
...         cbar.ax.set_ylabel("", rotation=-90, va="bottom")
...         ax.invert_yaxis()
...         # Turn spines off and create white grid.
...         for edge, spine in ax.spines.items():
...             spine.set_visible(False)
...         # optimal scale
...         opt_scale = mgc_dict["opt_scale"]
...         ax.scatter(opt_scale[0], opt_scale[1],
...                   marker='X', s=200, color='red')
...         # other formatting
...         ax.tick_params(bottom="off", left="off")
...         ax.set_xlabel('#Neighbors for X', fontsize=15)
...         ax.set_ylabel('#Neighbors for Y', fontsize=15)
...         ax.tick_params(axis="x", labelsz=15)
...         ax.tick_params(axis="y", labelsz=15)
...         ax.set_xlim(0, 100)
...         ax.set_ylim(0, 100)
...         plt.show()
```

Let's look at some linear data first:

```
>>> np.random.seed(12345678)
>>> x = np.linspace(-1, 1, num=100)
>>> y = x + 0.3 * np.random.random(x.size)
```


The simulation relationship can be plotted below:

```
>>> mgc_plot(x, y, "Linear", only_viz=True)
```



Now, we can see the test statistic, p-value, and MGC map visualized below. The optimal scale is shown on the map as a red "x":

```
>>> stat, pvalue, mgc_dict = multiscale_graphcorr(x, y)
>>> print("MGC test statistic: ", round(stat, 1))
MGC test statistic: 1.0
>>> print("P-value: ", round(pvalue, 1))
P-value: 0.0
>>> mgc_plot(x, y, "Linear", mgc_dict, only_mgc=True)
```




It is clear from here, that MGC is able to determine a relationship between the input data matrices because the p-value is very low and the MGC test statistic is relatively high. The MGC-map indicates a **strongly linear relationship**. Intuitively, this is because having more neighbors will help in identifying a linear relationship between x and y . The optimal scale in this case is **equivalent to the global scale**, marked by a red spot on the map.

The same can be done for nonlinear data sets. The following x and y arrays are derived from a nonlinear simulation:

```
>>> np.random.seed(12345678)
>>> unif = np.array(np.random.uniform(0, 5, size=100))
>>> x = unif * np.cos(np.pi * unif)
>>> y = unif * np.sin(np.pi * unif) + 0.4 * np.random.random(x.size)
```


The simulation relationship can be plotted below:

```
>>> mgc_plot(x, y, "Spiral", only_viz=True)
```



Now, we can see the test statistic, p-value, and MGC map visualized below. The optimal scale is shown on the map as a red "x":


```
>>> stat, pvalue, mgc_dict = multiscale_graphcorr(x, y)
>>> print("MGC test statistic: ", round(stat, 1))
MGC test statistic: 0.2
>>> print("P-value: ", round(pvalue, 1))
P-value: 0.0
>>> mgc_plot(x, y, "Spiral", mgc_dict, only_mgc=True)
```



It is clear from here, that MGC is able to determine a relationship again because the p-value is very low and the MGC test statistic is relatively high. The MGC-map indicates a **strongly nonlinear relationship**. The optimal scale in this case is **equivalent to the local scale**, marked by a red spot on the map.

4.1.13 Multidimensional image processing (`scipy.ndimage`)

Introduction

Image processing and analysis are generally seen as operations on 2-D arrays of values. There are, however, a number of fields where images of higher dimensionality must be analyzed. Good examples of these are medical imaging and biological imaging. `numpy` is suited very well for this type of applications due to its inherent multidimensional nature. The `scipy.ndimage` package provides a number of general image processing and analysis functions that are designed to operate with arrays of arbitrary dimensionality. The package currently includes: functions for linear and non-linear filtering, binary morphology, B-spline interpolation, and object measurements.

Properties shared by all functions

All functions share some common properties. Notably, all functions allow the specification of an output array with the `output` argument. With this argument, you can specify an array that will be changed in-place with the result with the operation. In this case, the result is not returned. Usually, using the `output` argument is more efficient, since an existing array is used to store the result.

The type of arrays returned is dependent on the type of operation, but it is, in most cases, equal to the type of the input. If, however, the `output` argument is used, the type of the result is equal to the type of the specified output argument. If no output argument is given, it is still possible to specify what the result of the output should be. This is done by simply assigning the desired `numpy` type object to the output argument. For example:

```
>>> from scipy.ndimage import correlate
>>> correlate(np.arange(10), [1, 2.5])
array([ 0,  2,  6,  9, 13, 16, 20, 23, 27, 30])
>>> correlate(np.arange(10), [1, 2.5], output=np.float64)
array([ 0. ,  2.5,  6. ,  9.5, 13. , 16.5, 20. , 23.5, 27. , 30.5])
```

Filter functions

The functions described in this section all perform some type of spatial filtering of the input array: the elements in the output are some function of the values in the neighborhood of the corresponding input element. We refer to this neighborhood of elements as the filter kernel, which is often rectangular in shape but may also have an arbitrary footprint. Many of the functions described below allow you to define the footprint of the kernel by passing a mask through the `footprint` parameter. For example, a cross-shaped kernel can be defined as follows:

```
>>> footprint = np.array([[0, 1, 0], [1, 1, 1], [0, 1, 0]])
>>> footprint
array([[0, 1, 0],
       [1, 1, 1],
       [0, 1, 0]])
```

Usually, the origin of the kernel is at the center calculated by dividing the dimensions of the kernel shape by two. For instance, the origin of a 1-D kernel of length three is at the second element. Take, for example, the correlation of a 1-D array with a filter of length 3 consisting of ones:

```
>>> from scipy.ndimage import correlate1d
>>> a = [0, 0, 0, 1, 0, 0, 0]
>>> correlate1d(a, [1, 1, 1])
array([0, 0, 1, 1, 1, 0, 0])
```

Sometimes, it is convenient to choose a different origin for the kernel. For this reason, most functions support the *origin* parameter, which gives the origin of the filter relative to its center. For example:

```
>>> a = [0, 0, 0, 1, 0, 0, 0]
>>> correlate1d(a, [1, 1, 1], origin = -1)
array([0, 1, 1, 1, 0, 0, 0])
```

The effect is a shift of the result towards the left. This feature will not be needed very often, but it may be useful, especially for filters that have an even size. A good example is the calculation of backward and forward differences:

```
>>> a = [0, 0, 1, 1, 1, 0, 0]
>>> correlate1d(a, [-1, 1]) # backward difference
array([ 0,  0,  1,  0,  0, -1,  0])
>>> correlate1d(a, [-1, 1], origin = -1) # forward difference
array([ 0,  1,  0,  0, -1,  0,  0])
```

We could also have calculated the forward difference as follows:

```
>>> correlate1d(a, [0, -1, 1])
array([ 0,  1,  0,  0, -1,  0,  0])
```

However, using the *origin* parameter instead of a larger kernel is more efficient. For multidimensional kernels, *origin* can be a number, in which case the origin is assumed to be equal along all axes, or a sequence giving the origin along each axis.

Since the output elements are a function of elements in the neighborhood of the input elements, the borders of the array need to be dealt with appropriately by providing the values outside the borders. This is done by assuming that the arrays are extended beyond their boundaries according to certain boundary conditions. In the functions described below, the boundary conditions can be selected using the *mode* parameter, which must be a string with the name of the boundary condition. The following boundary conditions are currently supported:

mode	description	example
"nearest"	use the value at the boundary	[1 2 3]->[1 1 2 3 3]
"wrap"	periodically replicate the array	[1 2 3]->[3 1 2 3 1]
"reflect"	reflect the array at the boundary	[1 2 3]->[1 1 2 3 3]
"mirror"	mirror the array at the boundary	[1 2 3]->[2 1 2 3 2]
"constant"	use a constant value, default is 0.0	[1 2 3]->[0 1 2 3 0]

The following synonyms are also supported for consistency with the interpolation routines:

mode	description
"grid-constant"	equivalent to "constant"*
"grid-mirror"	equivalent to "reflect"
"grid-wrap"	equivalent to "wrap"

* "grid-constant" and "constant" are equivalent for filtering operations, but have different behavior in interpolation functions. For API consistency, the filtering functions accept either name.

The "constant" mode is special since it needs an additional parameter to specify the constant value that should be used.

Note that modes mirror and reflect differ only in whether the sample at the boundary is repeated upon reflection. For mode mirror, the point of symmetry is exactly at the final sample, so that value is not repeated. This mode is also known as whole-sample symmetric since the point of symmetry falls on the final sample. Similarly, reflect is often referred to as half-sample symmetric as the point of symmetry is half a sample beyond the array boundary.

Note: The easiest way to implement such boundary conditions would be to copy the data to a larger array and extend the data at the borders according to the boundary conditions. For large arrays and large filter kernels, this would be very memory consuming, and the functions described below, therefore, use a different approach that does not require allocating large temporary buffers.

Correlation and convolution

- The `correlate1d` function calculates a 1-D correlation along the given axis. The lines of the array along the given axis are correlated with the given *weights*. The *weights* parameter must be a 1-D sequence of numbers.
- The function `correlate` implements multidimensional correlation of the input array with a given kernel.
- The `convolve1d` function calculates a 1-D convolution along the given axis. The lines of the array along the given axis are convoluted with the given *weights*. The *weights* parameter must be a 1-D sequence of numbers.
- The function `convolve` implements multidimensional convolution of the input array with a given kernel.

Note: A convolution is essentially a correlation after mirroring the kernel. As a result, the *origin* parameter behaves differently than in the case of a correlation: the results is shifted in the opposite direction.

Smoothing filters

- The `gaussian_filter1d` function implements a 1-D Gaussian filter. The standard deviation of the Gaussian filter is passed through the parameter *sigma*. Setting *order* = 0 corresponds to convolution with a Gaussian kernel. An order of 1, 2, or 3 corresponds to convolution with the first, second, or third derivatives of a Gaussian. Higher-order derivatives are not implemented.
- The `gaussian_filter` function implements a multidimensional Gaussian filter. The standard deviations of the Gaussian filter along each axis are passed through the parameter *sigma* as a sequence of numbers. If *sigma* is not a sequence but a single number, the standard deviation of the filter is equal along all directions. The order of the filter can be specified separately for each axis. An order of 0 corresponds to convolution with a Gaussian kernel. An order of 1, 2, or 3 corresponds to convolution with the first, second, or third derivatives of a Gaussian. Higher-order derivatives are not implemented. The *order* parameter must be a number, to specify the same order for all axes, or a sequence of numbers to specify a different order for each axis.

Note: The multidimensional filter is implemented as a sequence of 1-D Gaussian filters. The intermediate arrays are stored in the same data type as the output. Therefore, for output types with a lower precision, the results may be imprecise because intermediate results may be stored with insufficient precision. This can be prevented by specifying a more precise output type.

- The `uniform_filter1d` function calculates a 1-D uniform filter of the given *size* along the given axis.
- The `uniform_filter` implements a multidimensional uniform filter. The sizes of the uniform filter are given for each axis as a sequence of integers by the *size* parameter. If *size* is not a sequence, but a single number, the sizes along all axes are assumed to be equal.

Note: The multidimensional filter is implemented as a sequence of 1-D uniform filters. The intermediate arrays are stored in the same data type as the output. Therefore, for output types with a lower precision, the results may be imprecise because intermediate results may be stored with insufficient precision. This can be prevented by specifying a more precise output type.

Filters based on order statistics

- The `minimum_filter1d` function calculates a 1-D minimum filter of the given *size* along the given axis.
- The `maximum_filter1d` function calculates a 1-D maximum filter of the given *size* along the given axis.
- The `minimum_filter` function calculates a multidimensional minimum filter. Either the sizes of a rectangular kernel or the footprint of the kernel must be provided. The *size* parameter, if provided, must be a sequence of sizes or a single number, in which case the size of the filter is assumed to be equal along each axis. The *footprint*, if provided, must be an array that defines the shape of the kernel by its non-zero elements.
- The `maximum_filter` function calculates a multidimensional maximum filter. Either the sizes of a rectangular kernel or the footprint of the kernel must be provided. The *size* parameter, if provided, must be a sequence of sizes or a single number, in which case the size of the filter is assumed to be equal along each axis. The *footprint*, if provided, must be an array that defines the shape of the kernel by its non-zero elements.
- The `rank_filter` function calculates a multidimensional rank filter. The *rank* may be less than zero, i.e., *rank* = -1 indicates the largest element. Either the sizes of a rectangular kernel or the footprint of the kernel must be provided. The *size* parameter, if provided, must be a sequence of sizes or a single number, in which case the size of the filter is assumed to be equal along each axis. The *footprint*, if provided, must be an array that defines the shape of the kernel by its non-zero elements.
- The `percentile_filter` function calculates a multidimensional percentile filter. The *percentile* may be less than zero, i.e., *percentile* = -20 equals *percentile* = 80. Either the sizes of a rectangular kernel or the footprint of the kernel must be provided. The *size* parameter, if provided, must be a sequence of sizes or a single number, in which case the size of the filter is assumed to be equal along each axis. The *footprint*, if provided, must be an array that defines the shape of the kernel by its non-zero elements.
- The `median_filter` function calculates a multidimensional median filter. Either the sizes of a rectangular kernel or the footprint of the kernel must be provided. The *size* parameter, if provided, must be a sequence of sizes or a single number, in which case the size of the filter is assumed to be equal along each axis. The *footprint* if provided, must be an array that defines the shape of the kernel by its non-zero elements.

Derivatives

Derivative filters can be constructed in several ways. The function `gaussian_filter1d`, described in *Smoothing filters*, can be used to calculate derivatives along a given axis using the *order* parameter. Other derivative filters are the Prewitt and Sobel filters:

- The `prewitt` function calculates a derivative along the given axis.
- The `sobel` function calculates a derivative along the given axis.

The Laplace filter is calculated by the sum of the second derivatives along all axes. Thus, different Laplace filters can be constructed using different second-derivative functions. Therefore, we provide a general function that takes a function argument to calculate the second derivative along a given direction.

- The function `generic_laplace` calculates a Laplace filter using the function passed through `derivative2` to calculate second derivatives. The function `derivative2` should have the following signature

```
derivative2(input, axis, output, mode, cval, *extra_arguments, **extra_
→keywords)
```

It should calculate the second derivative along the dimension *axis*. If *output* is not `None`, it should use that for the output and return `None`, otherwise it should return the result. *mode*, *cval* have the usual meaning.

The *extra_arguments* and *extra_keywords* arguments can be used to pass a tuple of extra arguments and a dictionary of named arguments that are passed to `derivative2` at each call.

For example

```

>>> def d2(input, axis, output, mode, cval):
...     return correlate1d(input, [1, -2, 1], axis, output, mode, cval, 0)
...
>>> a = np.zeros((5, 5))
>>> a[2, 2] = 1
>>> from scipy.ndimage import generic_laplace
>>> generic_laplace(a, d2)
array([[ 0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  1., -4.,  1.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.]])

```

To demonstrate the use of the *extra_arguments* argument, we could do

```

>>> def d2(input, axis, output, mode, cval, weights):
...     return correlate1d(input, weights, axis, output, mode, cval, 0,)
...
>>> a = np.zeros((5, 5))
>>> a[2, 2] = 1
>>> generic_laplace(a, d2, extra_arguments = ([1, -2, 1],))
array([[ 0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  1., -4.,  1.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.]])

```

or

```

>>> generic_laplace(a, d2, extra_keywords = {'weights': [1, -2, 1]})
array([[ 0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  1., -4.,  1.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.]])

```

The following two functions are implemented using *generic_laplace* by providing appropriate functions for the second-derivative function:

- The function *laplace* calculates the Laplace using discrete differentiation for the second derivative (i.e., convolution with $[1, -2, 1]$).
- The function *gaussian_laplace* calculates the Laplace filter using *gaussian_filter* to calculate the second derivatives. The standard deviations of the Gaussian filter along each axis are passed through the parameter *sigma* as a sequence or numbers. If *sigma* is not a sequence but a single number, the standard deviation of the filter is equal along all directions.

The gradient magnitude is defined as the square root of the sum of the squares of the gradients in all directions. Similar to the generic Laplace function, there is a *generic_gradient_magnitude* function that calculates the gradient magnitude of an array.

- The function *generic_gradient_magnitude* calculates a gradient magnitude using the function passed through *derivative* to calculate first derivatives. The function *derivative* should have the following signature

```
derivative(input, axis, output, mode, cval, *extra_arguments, **extra_
→keywords)
```

It should calculate the derivative along the dimension *axis*. If *output* is not `None`, it should use that for the output and return `None`, otherwise it should return the result. *mode*, *cval* have the usual meaning.

The *extra_arguments* and *extra_keywords* arguments can be used to pass a tuple of extra arguments and a dictionary of named arguments that are passed to *derivative* at each call.

For example, the *sobel* function fits the required signature

```
>>> a = np.zeros((5, 5))
>>> a[2, 2] = 1
>>> from scipy.ndimage import sobel, generic_gradient_magnitude
>>> generic_gradient_magnitude(a, sobel)
array([[ 0.          ,  0.          ,  0.          ,  0.          ,  0.          ],
       [ 0.          ,  1.41421356,  2.          ,  1.41421356,  0.          ],
       [ 0.          ,  2.          ,  0.          ,  2.          ,  0.          ],
       [ 0.          ,  1.41421356,  2.          ,  1.41421356,  0.          ],
       [ 0.          ,  0.          ,  0.          ,  0.          ,  0.          ]])
```

See the documentation of *generic_laplace* for examples of using the *extra_arguments* and *extra_keywords* arguments.

The *sobel* and *prewitt* functions fit the required signature and can, therefore, be used directly with *generic_gradient_magnitude*.

- The function *gaussian_gradient_magnitude* calculates the gradient magnitude using *gaussian_filter* to calculate the first derivatives. The standard deviations of the Gaussian filter along each axis are passed through the parameter *sigma* as a sequence or numbers. If *sigma* is not a sequence but a single number, the standard deviation of the filter is equal along all directions.

Generic filter functions

To implement filter functions, generic functions can be used that accept a callable object that implements the filtering operation. The iteration over the input and output arrays is handled by these generic functions, along with such details as the implementation of the boundary conditions. Only a callable object implementing a callback function that does the actual filtering work must be provided. The callback function can also be written in C and passed using a `PyCapsule` (see *Extending scipy.ndimage in C* for more information).

- The *generic_filter1d* function implements a generic 1-D filter function, where the actual filtering operation must be supplied as a python function (or other callable object). The *generic_filter1d* function iterates over the lines of an array and calls *function* at each line. The arguments that are passed to *function* are 1-D arrays of the `numpy.float64` type. The first contains the values of the current line. It is extended at the beginning and the end, according to the *filter_size* and *origin* arguments. The second array should be modified in-place to provide the output values of the line. For example, consider a correlation along one dimension:

```
>>> a = np.arange(12).reshape(3,4)
>>> correlate1d(a, [1, 2, 3])
array([[ 3,  8, 14, 17],
       [27, 32, 38, 41],
       [51, 56, 62, 65]])
```

The same operation can be implemented using *generic_filter1d*, as follows:

```

>>> def fnc(iline, oline):
...     oline[...] = iline[:-2] + 2 * iline[1:-1] + 3 * iline[2:]
...
>>> from scipy.ndimage import generic_filter1d
>>> generic_filter1d(a, fnc, 3)
array([[ 3,  8, 14, 17],
       [27, 32, 38, 41],
       [51, 56, 62, 65]])

```

Here, the origin of the kernel was (by default) assumed to be in the middle of the filter of length 3. Therefore, each input line had been extended by one value at the beginning and at the end, before the function was called.

Optionally, extra arguments can be defined and passed to the filter function. The *extra_arguments* and *extra_keywords* arguments can be used to pass a tuple of extra arguments and/or a dictionary of named arguments that are passed to derivative at each call. For example, we can pass the parameters of our filter as an argument

```

>>> def fnc(iline, oline, a, b):
...     oline[...] = iline[:-2] + a * iline[1:-1] + b * iline[2:]
...
>>> generic_filter1d(a, fnc, 3, extra_arguments = (2, 3))
array([[ 3,  8, 14, 17],
       [27, 32, 38, 41],
       [51, 56, 62, 65]])

```

or

```

>>> generic_filter1d(a, fnc, 3, extra_keywords = {'a':2, 'b':3})
array([[ 3,  8, 14, 17],
       [27, 32, 38, 41],
       [51, 56, 62, 65]])

```

- The *generic_filter* function implements a generic filter function, where the actual filtering operation must be supplied as a python function (or other callable object). The *generic_filter* function iterates over the array and calls *function* at each element. The argument of *function* is a 1-D array of the `numpy.float64` type that contains the values around the current element that are within the footprint of the filter. The function should return a single value that can be converted to a double precision number. For example, consider a correlation:

```

>>> a = np.arange(12).reshape(3,4)
>>> correlate(a, [[1, 0], [0, 3]])
array([[ 0,  3,  7, 11],
       [12, 15, 19, 23],
       [28, 31, 35, 39]])

```

The same operation can be implemented using *generic_filter*, as follows:

```

>>> def fnc(buffer):
...     return (buffer * np.array([1, 3])).sum()
...
>>> from scipy.ndimage import generic_filter
>>> generic_filter(a, fnc, footprint = [[1, 0], [0, 1]])
array([[ 0,  3,  7, 11],
       [12, 15, 19, 23],
       [28, 31, 35, 39]])

```


Here, a kernel footprint was specified that contains only two elements. Therefore, the filter function receives a buffer of length equal to two, which was multiplied with the proper weights and the result summed.

When calling `generic_filter`, either the sizes of a rectangular kernel or the footprint of the kernel must be provided. The `size` parameter, if provided, must be a sequence of sizes or a single number, in which case the size of the filter is assumed to be equal along each axis. The `footprint`, if provided, must be an array that defines the shape of the kernel by its non-zero elements.

Optionally, extra arguments can be defined and passed to the filter function. The `extra_arguments` and `extra_keywords` arguments can be used to pass a tuple of extra arguments and/or a dictionary of named arguments that are passed to derivative at each call. For example, we can pass the parameters of our filter as an argument

```
>>> def fnc(buffer, weights):
...     weights = np.asarray(weights)
...     return (buffer * weights).sum()
...
>>> generic_filter(a, fnc, footprint = [[1, 0], [0, 1]], extra_arguments=
↳ ([1, 3],))
array([[ 0,  3,  7, 11],
       [12, 15, 19, 23],
       [28, 31, 35, 39]])
```

or

```
>>> generic_filter(a, fnc, footprint = [[1, 0], [0, 1]], extra_keywords= {
↳ 'weights': [1, 3]})
array([[ 0,  3,  7, 11],
       [12, 15, 19, 23],
       [28, 31, 35, 39]])
```

These functions iterate over the lines or elements starting at the last axis, i.e., the last index changes the fastest. This order of iteration is guaranteed for the case that it is important to adapt the filter depending on spatial location. Here is an example of using a class that implements the filter and keeps track of the current coordinates while iterating. It performs the same filter operation as described above for `generic_filter`, but additionally prints the current coordinates:

```
>>> a = np.arange(12).reshape(3,4)
>>>
>>> class fnc_class:
...     def __init__(self, shape):
...         # store the shape:
...         self.shape = shape
...         # initialize the coordinates:
...         self.coordinates = [0] * len(shape)
...
...     def filter(self, buffer):
...         result = (buffer * np.array([1, 3])).sum()
...         print(self.coordinates)
...         # calculate the next coordinates:
...         axes = list(range(len(self.shape)))
...         axes.reverse()
...         for jj in axes:
...             if self.coordinates[jj] < self.shape[jj] - 1:
...                 self.coordinates[jj] += 1
...                 break
...         else:
```

(continues on next page)

(continued from previous page)

```

...         self.coordinates[jj] = 0
...     return result
...
>>> fnc = fnc_class(shape = (3,4))
>>> generic_filter(a, fnc.filter, footprint = [[1, 0], [0, 1]])
[0, 0]
[0, 1]
[0, 2]
[0, 3]
[1, 0]
[1, 1]
[1, 2]
[1, 3]
[2, 0]
[2, 1]
[2, 2]
[2, 3]
array([[ 0,  3,  7, 11],
       [12, 15, 19, 23],
       [28, 31, 35, 39]])

```

For the `generic_filter1d` function, the same approach works, except that this function does not iterate over the axis that is being filtered. The example for `generic_filter1d` then becomes this:

```

>>> a = np.arange(12).reshape(3,4)
>>>
>>> class fnc1d_class:
...     def __init__(self, shape, axis = -1):
...         # store the filter axis:
...         self.axis = axis
...         # store the shape:
...         self.shape = shape
...         # initialize the coordinates:
...         self.coordinates = [0] * len(shape)
...
...     def filter(self, iline, oline):
...         oline[...] = iline[:-2] + 2 * iline[1:-1] + 3 * iline[2:]
...         print(self.coordinates)
...         # calculate the next coordinates:
...         axes = list(range(len(self.shape)))
...         # skip the filter axis:
...         del axes[self.axis]
...         axes.reverse()
...         for jj in axes:
...             if self.coordinates[jj] < self.shape[jj] - 1:
...                 self.coordinates[jj] += 1
...                 break
...             else:
...                 self.coordinates[jj] = 0
...
>>> fnc = fnc1d_class(shape = (3,4))
>>> generic_filter1d(a, fnc.filter, 3)

```

(continues on next page)

(continued from previous page)

```
[0, 0]
[1, 0]
[2, 0]
array([[ 3,  8, 14, 17],
       [27, 32, 38, 41],
       [51, 56, 62, 65]])
```

Fourier domain filters

The functions described in this section perform filtering operations in the Fourier domain. Thus, the input array of such a function should be compatible with an inverse Fourier transform function, such as the functions from the `numpy.fft` module. We, therefore, have to deal with arrays that may be the result of a real or a complex Fourier transform. In the case of a real Fourier transform, only half of the of the symmetric complex transform is stored. Additionally, it needs to be known what the length of the axis was that was transformed by the real fft. The functions described here provide a parameter *n* that, in the case of a real transform, must be equal to the length of the real transform axis before transformation. If this parameter is less than zero, it is assumed that the input array was the result of a complex Fourier transform. The parameter *axis* can be used to indicate along which axis the real transform was executed.

- The `fourier_shift` function multiplies the input array with the multidimensional Fourier transform of a shift operation for the given shift. The *shift* parameter is a sequence of shifts for each dimension or a single value for all dimensions.
- The `fourier_gaussian` function multiplies the input array with the multidimensional Fourier transform of a Gaussian filter with given standard deviations *sigma*. The *sigma* parameter is a sequence of values for each dimension or a single value for all dimensions.
- The `fourier_uniform` function multiplies the input array with the multidimensional Fourier transform of a uniform filter with given sizes *size*. The *size* parameter is a sequence of values for each dimension or a single value for all dimensions.
- The `fourier_ellipsoid` function multiplies the input array with the multidimensional Fourier transform of an elliptically-shaped filter with given sizes *size*. The *size* parameter is a sequence of values for each dimension or a single value for all dimensions. This function is only implemented for dimensions 1, 2, and 3.

Interpolation functions

This section describes various interpolation functions that are based on B-spline theory. A good introduction to B-splines can be found in¹ with detailed algorithms for image interpolation given in⁵.

Spline pre-filters

Interpolation using splines of an order larger than 1 requires a pre-filtering step. The interpolation functions described in section *Interpolation functions* apply pre-filtering by calling `spline_filter`, but they can be instructed not to do this by setting the *prefilter* keyword equal to `False`. This is useful if more than one interpolation operation is done on the same array. In this case, it is more efficient to do the pre-filtering only once and use a pre-filtered array as the input of the interpolation functions. The following two functions implement the pre-filtering:

- The `spline_filter1d` function calculates a 1-D spline filter along the given axis. An output array can optionally be provided. The order of the spline must be larger than 1 and less than 6.
- The `spline_filter` function calculates a multidimensional spline filter.


¹ M. Unser, "Splines: A Perfect Fit for Signal and Image Processing," IEEE Signal Processing Magazine, vol. 16, no. 6, pp. 22-38, November 1999.

⁵ T. Briand and P. Monasse, "Theory and Practice of Image B-Spline Interpolation", Image Processing On Line, 8, pp. 99-141, 2018. <https://doi.org/10.5201/ipol.2018.221>


Note: The multidimensional filter is implemented as a sequence of 1-D spline filters. The intermediate arrays are stored in the same data type as the output. Therefore, if an output with a limited precision is requested, the results may be imprecise because intermediate results may be stored with insufficient precision. This can be prevented by specifying a output type of high precision.

Interpolation boundary handling

The interpolation functions all employ spline interpolation to effect some type of geometric transformation of the input array. This requires a mapping of the output coordinates to the input coordinates, and therefore, the possibility arises that input values outside the boundaries may be needed. This problem is solved in the same way as described in *Filter functions* for the multidimensional filter functions. Therefore, these functions all support a *mode* parameter that determines how the boundaries are handled, and a *cval* parameter that gives a constant value in case that the ‘constant’ mode is used. The behavior of all modes, including at non-integer locations is illustrated below. Note the boundaries are not handled the same for all modes; *reflect* (aka *grid-mirror*) and *grid-wrap* involve symmetry or repetition about a point that is half way between image samples (dashed vertical lines) while modes *mirror* and *wrap* treat the image as if it’s extent ends exactly at the first and last sample point rather than 0.5 samples past it.



The coordinates of image samples fall on integer sampling locations in the range from 0 to $\text{shape}[i] - 1$ along each axis, i . The figure below illustrates the interpolation of a point at location (3.7, 3.3) within an image of shape (7, 7). For an interpolation of order n , $n + 1$ samples are involved along each axis. The filled circles illustrate the sampling locations involved in the interpolation of the value at the location of the red x.



Interpolation functions

- The `geometric_transform` function applies an arbitrary geometric transform to the input. The given *mapping* function is called at each point in the output to find the corresponding coordinates in the input. *mapping* must be a callable object that accepts a tuple of length equal to the output array rank and returns the corresponding input coordinates as a tuple of length equal to the input array rank. The output shape and output type can optionally be provided. If not given, they are equal to the input shape and type.

For example:

```
>>> a = np.arange(12).reshape(4,3).astype(np.float64)
>>> def shift_func(output_coordinates):
...     return (output_coordinates[0] - 0.5, output_coordinates[1] - 0.5)
...
>>> from scipy.ndimage import geometric_transform
>>> geometric_transform(a, shift_func)
array([[ 0.    ,  0.    ,  0.    ],
       [ 0.    ,  1.3625,  2.7375],
       [ 0.    ,  4.8125,  6.1875],
       [ 0.    ,  8.2625,  9.6375]])
```

Optionally, extra arguments can be defined and passed to the filter function. The *extra_arguments* and *extra_keywords* arguments can be used to pass a tuple of extra arguments and/or a dictionary of named arguments that are passed to derivative at each call. For example, we can pass the shifts in our example as arguments

```
>>> def shift_func(output_coordinates, s0, s1):
...     return (output_coordinates[0] - s0, output_coordinates[1] - s1)
...
>>> geometric_transform(a, shift_func, extra_arguments = (0.5, 0.5))
array([[ 0.    ,  0.    ,  0.    ],
       [ 0.    ,  1.3625,  2.7375],
       [ 0.    ,  4.8125,  6.1875],
       [ 0.    ,  8.2625,  9.6375]])
```

or

```
>>> geometric_transform(a, shift_func, extra_keywords = {'s0': 0.5, 's1':_
→0.5})
array([[ 0.    ,  0.    ,  0.    ],
       [ 0.    ,  1.3625,  2.7375],
       [ 0.    ,  4.8125,  6.1875],
       [ 0.    ,  8.2625,  9.6375]])
```

Note: The mapping function can also be written in C and passed using a `scipy.LowLevelCallable`. See [Extending scipy.ndimage in C](#) for more information.

- The function `map_coordinates` applies an arbitrary coordinate transformation using the given array of coordinates. The shape of the output is derived from that of the coordinate array by dropping the first axis. The parameter `coordinates` is used to find for each point in the output the corresponding coordinates in the input. The values of `coordinates` along the first axis are the coordinates in the input array at which the output value is found. (See also the `numarray.coordinates` function.) Since the coordinates may be non-integer coordinates, the value of the input at these coordinates is determined by spline interpolation of the requested order.

Here is an example that interpolates a 2D array at (0.5, 0.5) and (1, 2):

```
>>> a = np.arange(12).reshape(4,3).astype(np.float64)
>>> a
array([[ 0.,  1.,  2.],
       [ 3.,  4.,  5.],
       [ 6.,  7.,  8.],
       [ 9., 10., 11.]])
>>> from scipy.ndimage import map_coordinates
>>> map_coordinates(a, [[0.5, 2], [0.5, 1]])
array([ 1.3625,  7.])
```

- The `affine_transform` function applies an affine transformation to the input array. The given transformation `matrix` and `offset` are used to find for each point in the output the corresponding coordinates in the input. The value of the input at the calculated coordinates is determined by spline interpolation of the requested order. The transformation `matrix` must be 2-D or can also be given as a 1-D sequence or array. In the latter case, it is assumed that the matrix is diagonal. A more efficient interpolation algorithm is then applied that exploits the separability of the problem. The output shape and output type can optionally be provided. If not given, they are equal to the input shape and type.
- The `shift` function returns a shifted version of the input, using spline interpolation of the requested `order`.
- The `zoom` function returns a rescaled version of the input, using spline interpolation of the requested `order`.
- The `rotate` function returns the input array rotated in the plane defined by the two axes given by the parameter `axes`, using spline interpolation of the requested `order`. The angle must be given in degrees. If `reshape` is true, then the size of the output array is adapted to contain the rotated input.

Morphology

Binary morphology

- The `generate_binary_structure` functions generates a binary structuring element for use in binary morphology operations. The *rank* of the structure must be provided. The size of the structure that is returned is equal to three in each direction. The value of each element is equal to one if the square of the Euclidean distance from the element to the center is less than or equal to *connectivity*. For instance, 2-D 4-connected and 8-connected structures are generated as follows:

```
>>> from scipy.ndimage import generate_binary_structure
>>> generate_binary_structure(2, 1)
array([[False,  True,  False],
       [ True,  True,  True],
       [False,  True,  False]], dtype=bool)
>>> generate_binary_structure(2, 2)
array([[ True,  True,  True],
       [ True,  True,  True],
       [ True,  True,  True]], dtype=bool)
```

Most binary morphology functions can be expressed in terms of the basic operations erosion and dilation.

- The `binary_erosion` function implements binary erosion of arrays of arbitrary rank with the given structuring element. The origin parameter controls the placement of the structuring element, as described in *Filter functions*. If no structuring element is provided, an element with connectivity equal to one is generated using `generate_binary_structure`. The *border_value* parameter gives the value of the array outside boundaries. The erosion is repeated *iterations* times. If *iterations* is less than one, the erosion is repeated until the result does not change anymore. If a *mask* array is given, only those elements with a true value at the corresponding mask element are modified at each iteration.
- The `binary_dilation` function implements binary dilation of arrays of arbitrary rank with the given structuring element. The origin parameter controls the placement of the structuring element, as described in *Filter functions*. If no structuring element is provided, an element with connectivity equal to one is generated using `generate_binary_structure`. The *border_value* parameter gives the value of the array outside boundaries. The dilation is repeated *iterations* times. If *iterations* is less than one, the dilation is repeated until the result does not change anymore. If a *mask* array is given, only those elements with a true value at the corresponding mask element are modified at each iteration.

Here is an example of using `binary_dilation` to find all elements that touch the border, by repeatedly dilating an empty array from the border using the data array as the mask:

```
>>> struct = np.array([[0, 1, 0], [1, 1, 1], [0, 1, 0]])
>>> a = np.array([[1, 0, 0, 0, 0], [1, 1, 0, 1, 0], [0, 0, 1, 1, 0], [0, 0, 0, 0, 0]])
>>> a
array([[1, 0, 0, 0, 0],
       [1, 1, 0, 1, 0],
       [0, 0, 1, 1, 0],
       [0, 0, 0, 0, 0]])
>>> from scipy.ndimage import binary_dilation
>>> binary_dilation(np.zeros(a.shape), struct, -1, a, border_value=1)
array([[ True, False, False, False, False],
       [ True,  True, False, False, False],
       [False, False, False, False, False],
       [False, False, False, False, False]], dtype=bool)
```

The `binary_erosion` and `binary_dilation` functions both have an *iterations* parameter, which allows the ero-

sion or dilation to be repeated a number of times. Repeating an erosion or a dilation with a given structure n times is equivalent to an erosion or a dilation with a structure that is $n-1$ times dilated with itself. A function is provided that allows the calculation of a structure that is dilated a number of times with itself:

- The `iterate_structure` function returns a structure by dilation of the input structure $iteration - 1$ times with itself.

For instance:

```
>>> struct = generate_binary_structure(2, 1)
>>> struct
array([[False,  True, False],
       [ True,  True,  True],
       [False,  True, False]], dtype=bool)
>>> from scipy.ndimage import iterate_structure
>>> iterate_structure(struct, 2)
array([[False, False,  True, False, False],
       [False,  True,  True,  True, False],
       [ True,  True,  True,  True,  True],
       [False,  True,  True,  True, False],
       [False, False,  True, False, False]], dtype=bool)
```

If the origin of the original structure is equal to 0, then it is also equal to 0 for the iterated structure. If not, the origin must also be adapted if the equivalent of the `*iterations*` erosions or dilations must be achieved with the iterated structure. The adapted origin is simply obtained by multiplying with the number of iterations. For convenience, the `:func:`iterate_structure`` also returns the adapted origin if the `*origin*` parameter is not `None``:

```
.. code:: python

>>> iterate_structure(struct, 2, -1)
(array([[False, False,  True, False, False],
       [False,  True,  True,  True, False],
       [ True,  True,  True,  True,  True],
       [False,  True,  True,  True, False],
       [False, False,  True, False, False]], dtype=bool), [-2, -2])
```

Other morphology operations can be defined in terms of erosion and dilation. The following functions provide a few of these operations for convenience:

- The `binary_opening` function implements binary opening of arrays of arbitrary rank with the given structuring element. Binary opening is equivalent to a binary erosion followed by a binary dilation with the same structuring element. The origin parameter controls the placement of the structuring element, as described in *Filter functions*. If no structuring element is provided, an element with connectivity equal to one is generated using `generate_binary_structure`. The `iterations` parameter gives the number of erosions that is performed followed by the same number of dilations.
- The `binary_closing` function implements binary closing of arrays of arbitrary rank with the given structuring element. Binary closing is equivalent to a binary dilation followed by a binary erosion with the same structuring element. The origin parameter controls the placement of the structuring element, as described in *Filter functions*. If no structuring element is provided, an element with connectivity equal to one is generated using `generate_binary_structure`. The `iterations` parameter gives the number of dilations that is performed followed by the same number of erosions.

- The `binary_fill_holes` function is used to close holes in objects in a binary image, where the `structure` defines the connectivity of the holes. The `origin` parameter controls the placement of the structuring element, as described in *Filter functions*. If no structuring element is provided, an element with connectivity equal to one is generated using `generate_binary_structure`.
- The `binary_hit_or_miss` function implements a binary hit-or-miss transform of arrays of arbitrary rank with the given structuring elements. The hit-or-miss transform is calculated by erosion of the input with the first structure, erosion of the logical *not* of the input with the second structure, followed by the logical *and* of these two erosions. The `origin` parameters control the placement of the structuring elements, as described in *Filter functions*. If `origin2` equals `None`, it is set equal to the `origin1` parameter. If the first structuring element is not provided, a structuring element with connectivity equal to one is generated using `generate_binary_structure`. If `structure2` is not provided, it is set equal to the logical *not* of `structure1`.

Grey-scale morphology

Grey-scale morphology operations are the equivalents of binary morphology operations that operate on arrays with arbitrary values. Below, we describe the grey-scale equivalents of erosion, dilation, opening and closing. These operations are implemented in a similar fashion as the filters described in *Filter functions*, and we refer to this section for the description of filter kernels and footprints, and the handling of array borders. The grey-scale morphology operations optionally take a `structure` parameter that gives the values of the structuring element. If this parameter is not given, the structuring element is assumed to be flat with a value equal to zero. The shape of the structure can optionally be defined by the `footprint` parameter. If this parameter is not given, the structure is assumed to be rectangular, with sizes equal to the dimensions of the `structure` array, or by the `size` parameter if `structure` is not given. The `size` parameter is only used if both `structure` and `footprint` are not given, in which case the structuring element is assumed to be rectangular and flat with the dimensions given by `size`. The `size` parameter, if provided, must be a sequence of sizes or a single number in which case the size of the filter is assumed to be equal along each axis. The `footprint` parameter, if provided, must be an array that defines the shape of the kernel by its non-zero elements.

Similarly to binary erosion and dilation, there are operations for grey-scale erosion and dilation:

- The `grey_erosion` function calculates a multidimensional grey-scale erosion.
- The `grey_dilation` function calculates a multidimensional grey-scale dilation.

Grey-scale opening and closing operations can be defined similarly to their binary counterparts:

- The `grey_opening` function implements grey-scale opening of arrays of arbitrary rank. Grey-scale opening is equivalent to a grey-scale erosion followed by a grey-scale dilation.
- The `grey_closing` function implements grey-scale closing of arrays of arbitrary rank. Grey-scale opening is equivalent to a grey-scale dilation followed by a grey-scale erosion.
- The `morphological_gradient` function implements a grey-scale morphological gradient of arrays of arbitrary rank. The grey-scale morphological gradient is equal to the difference of a grey-scale dilation and a grey-scale erosion.
- The `morphological_laplace` function implements a grey-scale morphological laplace of arrays of arbitrary rank. The grey-scale morphological laplace is equal to the sum of a grey-scale dilation and a grey-scale erosion minus twice the input.
- The `white_tophat` function implements a white top-hat filter of arrays of arbitrary rank. The white top-hat is equal to the difference of the input and a grey-scale opening.
- The `black_tophat` function implements a black top-hat filter of arrays of arbitrary rank. The black top-hat is equal to the difference of a grey-scale closing and the input.

Distance transforms

Distance transforms are used to calculate the minimum distance from each element of an object to the background. The following functions implement distance transforms for three different distance metrics: Euclidean, city block, and chessboard distances.

- The function `distance_transform_cdt` uses a chamfer type algorithm to calculate the distance transform of the input, by replacing each object element (defined by values larger than zero) with the shortest distance to the background (all non-object elements). The structure determines the type of chamfering that is done. If the structure is equal to 'cityblock', a structure is generated using `generate_binary_structure` with a squared distance equal to 1. If the structure is equal to 'chessboard', a structure is generated using `generate_binary_structure` with a squared distance equal to the rank of the array. These choices correspond to the common interpretations of the city block and the chessboard distance metrics in two dimensions.

In addition to the distance transform, the feature transform can be calculated. In this case, the index of the closest background element is returned along the first axis of the result. The `return_distances`, and `return_indices` flags can be used to indicate if the distance transform, the feature transform, or both must be returned.

The `distances` and `indices` arguments can be used to give optional output arrays that must be of the correct size and type (both `numpy.int32`). The basics of the algorithm used to implement this function are described in².

- The function `distance_transform_edt` calculates the exact Euclidean distance transform of the input, by replacing each object element (defined by values larger than zero) with the shortest Euclidean distance to the background (all non-object elements).

In addition to the distance transform, the feature transform can be calculated. In this case, the index of the closest background element is returned along the first axis of the result. The `return_distances` and `return_indices` flags can be used to indicate if the distance transform, the feature transform, or both must be returned.

Optionally, the sampling along each axis can be given by the `sampling` parameter, which should be a sequence of length equal to the input rank, or a single number in which the sampling is assumed to be equal along all axes.

The `distances` and `indices` arguments can be used to give optional output arrays that must be of the correct size and type (`numpy.float64` and `numpy.int32`). The algorithm used to implement this function is described in³.

- The function `distance_transform_bf` uses a brute-force algorithm to calculate the distance transform of the input, by replacing each object element (defined by values larger than zero) with the shortest distance to the background (all non-object elements). The metric must be one of "euclidean", "cityblock", or "chessboard".

In addition to the distance transform, the feature transform can be calculated. In this case, the index of the closest background element is returned along the first axis of the result. The `return_distances` and `return_indices` flags can be used to indicate if the distance transform, the feature transform, or both must be returned.

Optionally, the sampling along each axis can be given by the `sampling` parameter, which should be a sequence of length equal to the input rank, or a single number in which the sampling is assumed to be equal along all axes. This parameter is only used in the case of the Euclidean distance transform.

The `distances` and `indices` arguments can be used to give optional output arrays that must be of the correct size and type (`numpy.float64` and `numpy.int32`).

Note: This function uses a slow brute-force algorithm, the function `distance_transform_cdt` can be used to more efficiently calculate city block and chessboard distance transforms. The function `distance_transform_edt` can be used to more efficiently calculate the exact Euclidean distance transform.

² G. Borgefors, "Distance transformations in arbitrary dimensions.", *Computer Vision, Graphics, and Image Processing*, 27:321-345, 1984.

³ C. R. Maurer, Jr., R. Qi, and V. Raghavan, "A linear time algorithm for computing exact euclidean distance transforms of binary images in arbitrary dimensions. *IEEE Trans. PAMI* 25, 265-270, 2003.

Segmentation and labeling

Segmentation is the process of separating objects of interest from the background. The most simple approach is, probably, intensity thresholding, which is easily done with `numpy` functions:

```
>>> a = np.array([[1,2,2,1,1,0],
...               [0,2,3,1,2,0],
...               [1,1,1,3,3,2],
...               [1,1,1,1,2,1]])
>>> np.where(a > 1, 1, 0)
array([[0, 1, 1, 0, 0, 0],
       [0, 1, 1, 0, 1, 0],
       [0, 0, 0, 1, 1, 1],
       [0, 0, 0, 0, 1, 0]])
```

The result is a binary image, in which the individual objects still need to be identified and labeled. The function `label` generates an array where each object is assigned a unique number:

- The `label` function generates an array where the objects in the input are labeled with an integer index. It returns a tuple consisting of the array of object labels and the number of objects found, unless the `output` parameter is given, in which case only the number of objects is returned. The connectivity of the objects is defined by a structuring element. For instance, in 2D using a 4-connected structuring element gives:

```
>>> a = np.array([[0,1,1,0,0,0], [0,1,1,0,1,0], [0,0,0,1,1,1], [0,0,0,0,1,
→0]])
>>> s = [[0, 1, 0], [1,1,1], [0,1,0]]
>>> from scipy.ndimage import label
>>> label(a, s)
(array([[0, 1, 1, 0, 0, 0],
       [0, 1, 1, 0, 2, 0],
       [0, 0, 0, 2, 2, 2],
       [0, 0, 0, 0, 2, 0]]), 2)
```

These two objects are not connected because there is no way in which we can place the structuring element, such that it overlaps with both objects. However, an 8-connected structuring element results in only a single object:

```
>>> a = np.array([[0,1,1,0,0,0], [0,1,1,0,1,0], [0,0,0,1,1,1], [0,0,0,0,1,
→0]])
>>> s = [[1,1,1], [1,1,1], [1,1,1]]
>>> label(a, s)[0]
array([[0, 1, 1, 0, 0, 0],
       [0, 1, 1, 0, 1, 0],
       [0, 0, 0, 1, 1, 1],
       [0, 0, 0, 0, 1, 0]])
```

If no structuring element is provided, one is generated by calling `generate_binary_structure` (see *Binary morphology*) using a connectivity of one (which in 2D is the 4-connected structure of the first example). The input can be of any type, any value not equal to zero is taken to be part of an object. This is useful if you need to ‘re-label’ an array of object indices, for instance, after removing unwanted objects. Just apply the `label` function again to the index array. For instance:

```
>>> l, n = label([1, 0, 1, 0, 1])
>>> l
array([1, 0, 2, 0, 3])
```

(continues on next page)

(continued from previous page)

```

>>> l = np.where(l != 2, 1, 0)
>>> l
array([1, 0, 0, 0, 3])
>>> label(l)[0]
array([1, 0, 0, 0, 2])

```

Note: The structuring element used by `label` is assumed to be symmetric.

There is a large number of other approaches for segmentation, for instance, from an estimation of the borders of the objects that can be obtained by derivative filters. One such approach is watershed segmentation. The function `watershed_ift` generates an array where each object is assigned a unique label, from an array that localizes the object borders, generated, for instance, by a gradient magnitude filter. It uses an array containing initial markers for the objects:

- The `watershed_ift` function applies a watershed from markers algorithm, using an Iterative Forest Transform, as described in⁴.
- The inputs of this function are the array to which the transform is applied, and an array of markers that designate the objects by a unique label, where any non-zero value is a marker. For instance:

```

>>> input = np.array([[0, 0, 0, 0, 0, 0, 0],
...                  [0, 1, 1, 1, 1, 1, 0],
...                  [0, 1, 0, 0, 0, 1, 0],
...                  [0, 1, 0, 0, 0, 1, 0],
...                  [0, 1, 0, 0, 0, 1, 0],
...                  [0, 1, 1, 1, 1, 1, 0],
...                  [0, 0, 0, 0, 0, 0, 0]], np.uint8)
>>> markers = np.array([[1, 0, 0, 0, 0, 0, 0],
...                    [0, 0, 0, 0, 0, 0, 0],
...                    [0, 0, 0, 0, 0, 0, 0],
...                    [0, 0, 0, 2, 0, 0, 0],
...                    [0, 0, 0, 0, 0, 0, 0],
...                    [0, 0, 0, 0, 0, 0, 0],
...                    [0, 0, 0, 0, 0, 0, 0]], np.int8)
>>> from scipy.ndimage import watershed_ift
>>> watershed_ift(input, markers)
array([[1, 1, 1, 1, 1, 1, 1],
       [1, 1, 2, 2, 2, 1, 1],
       [1, 2, 2, 2, 2, 2, 1],
       [1, 2, 2, 2, 2, 2, 1],
       [1, 2, 2, 2, 2, 2, 1],
       [1, 1, 2, 2, 2, 1, 1],
       [1, 1, 1, 1, 1, 1, 1]], dtype=int8)

```

Here, two markers were used to designate an object (*marker* = 2) and the background (*marker* = 1). The order in which these are processed is arbitrary: moving the marker for the background to the lower-right corner of the array yields a different result:

```

>>> markers = np.array([[0, 0, 0, 0, 0, 0, 0],
...                    [0, 0, 0, 0, 0, 0, 0],

```

(continues on next page)

⁴ P. Felkel, R. Wegenkittl, and M. Bruckschwaiger, "Implementation and Complexity of the Watershed-from-Markers Algorithm Computed as a Minimal Cost Forest.", Eurographics 2001, pp. C:26-35.

(continued from previous page)

```

...           [0, 0, 0, 0, 0, 0, 0],
...           [0, 0, 0, 2, 0, 0, 0],
...           [0, 0, 0, 0, 0, 0, 0],
...           [0, 0, 0, 0, 0, 0, 0],
...           [0, 0, 0, 0, 0, 0, 1]], np.int8)
>>> watershed_ift(input, markers)
array([[1, 1, 1, 1, 1, 1, 1],
       [1, 1, 1, 1, 1, 1, 1],
       [1, 1, 2, 2, 2, 1, 1],
       [1, 1, 2, 2, 2, 1, 1],
       [1, 1, 2, 2, 2, 1, 1],
       [1, 1, 1, 1, 1, 1, 1],
       [1, 1, 1, 1, 1, 1, 1]], dtype=int8)

```

The result is that the object (*marker* = 2) is smaller because the second marker was processed earlier. This may not be the desired effect if the first marker was supposed to designate a background object. Therefore, *watershed_ift* treats markers with a negative value explicitly as background markers and processes them after the normal markers. For instance, replacing the first marker by a negative marker gives a result similar to the first example:

```

>>> markers = np.array([[0, 0, 0, 0, 0, 0, 0],
...                     [0, 0, 0, 0, 0, 0, 0],
...                     [0, 0, 0, 0, 0, 0, 0],
...                     [0, 0, 0, 2, 0, 0, 0],
...                     [0, 0, 0, 0, 0, 0, 0],
...                     [0, 0, 0, 0, 0, 0, 0],
...                     [0, 0, 0, 0, 0, 0, -1]], np.int8)
>>> watershed_ift(input, markers)
array([[ -1,  -1,  -1,  -1,  -1,  -1,  -1],
       [-1, -1,  2,  2,  2, -1, -1],
       [-1,  2,  2,  2,  2,  2, -1],
       [-1,  2,  2,  2,  2,  2, -1],
       [-1,  2,  2,  2,  2,  2, -1],
       [-1, -1,  2,  2,  2, -1, -1],
       [-1, -1, -1, -1, -1, -1, -1]], dtype=int8)

```

The connectivity of the objects is defined by a structuring element. If no structuring element is provided, one is generated by calling *generate_binary_structure* (see *Binary morphology*) using a connectivity of one (which in 2D is a 4-connected structure.) For example, using an 8-connected structure with the last example yields a different object:

```

>>> watershed_ift(input, markers,
...               structure = [[1,1,1], [1,1,1], [1,1,1]])
array([[ -1,  -1,  -1,  -1,  -1,  -1,  -1],
       [-1,  2,  2,  2,  2,  2, -1],
       [-1,  2,  2,  2,  2,  2, -1],
       [-1,  2,  2,  2,  2,  2, -1],
       [-1,  2,  2,  2,  2,  2, -1],
       [-1,  2,  2,  2,  2,  2, -1],
       [-1, -1, -1, -1, -1, -1, -1]], dtype=int8)

```

Note: The implementation of *watershed_ift* limits the data types of the input to `numpy.uint8` and

```
numpy.uint16.
```

Object measurements

Given an array of labeled objects, the properties of the individual objects can be measured. The `find_objects` function can be used to generate a list of slices that for each object, give the smallest sub-array that fully contains the object:

- The `find_objects` function finds all objects in a labeled array and returns a list of slices that correspond to the smallest regions in the array that contains the object.

For instance:

```
>>> a = np.array([[0, 1, 1, 0, 0, 0], [0, 1, 1, 0, 1, 0], [0, 0, 0, 1, 1, 1], [0, 0, 0, 0, 1,
→0]])
>>> l, n = label(a)
>>> from scipy.ndimage import find_objects
>>> f = find_objects(l)
>>> a[f[0]]
array([[1, 1],
       [1, 1]])
>>> a[f[1]]
array([[0, 1, 0],
       [1, 1, 1],
       [0, 1, 0]])
```

The function `find_objects` returns slices for all objects, unless the `max_label` parameter is larger than zero, in which case only the first `max_label` objects are returned. If an index is missing in the `label` array, `None` is returned instead of a slice. For example:

```
>>> from scipy.ndimage import find_objects
>>> find_objects([1, 0, 3, 4], max_label = 3)
[(slice(0, 1, None),), None, (slice(2, 3, None),)]
```

The list of slices generated by `find_objects` is useful to find the position and dimensions of the objects in the array, but can also be used to perform measurements on the individual objects. Say, we want to find the sum of the intensities of an object in image:

```
>>> image = np.arange(4 * 6).reshape(4, 6)
>>> mask = np.array([[0, 1, 1, 0, 0, 0], [0, 1, 1, 0, 1, 0], [0, 0, 0, 1, 1, 1], [0, 0, 0, 0, 1, 0]])
>>> labels = label(mask)[0]
>>> slices = find_objects(labels)
```

Then we can calculate the sum of the elements in the second object:

```
>>> np.where(labels[slices[1]] == 2, image[slices[1]], 0).sum()
80
```

That is, however, not particularly efficient and may also be more complicated for other types of measurements. Therefore, a few measurements functions are defined that accept the array of object labels and the index of the object to be measured. For instance, calculating the sum of the intensities can be done by:

```
>>> from scipy.ndimage import sum as ndi_sum
>>> ndi_sum(image, labels, 2)
80
```

For large arrays and small objects, it is more efficient to call the measurement functions after slicing the array:

```
>>> ndi_sum(image[slices[1]], labels[slices[1]], 2)
80
```

Alternatively, we can do the measurements for a number of labels with a single function call, returning a list of results. For instance, to measure the sum of the values of the background and the second object in our example, we give a list of labels:

```
>>> ndi_sum(image, labels, [0, 2])
array([178.0, 80.0])
```

The measurement functions described below all support the *index* parameter to indicate which object(s) should be measured. The default value of *index* is `None`. This indicates that all elements where the label is larger than zero should be treated as a single object and measured. Thus, in this case the *labels* array is treated as a mask defined by the elements that are larger than zero. If *index* is a number or a sequence of numbers it gives the labels of the objects that are measured. If *index* is a sequence, a list of the results is returned. Functions that return more than one result return their result as a tuple if *index* is a single number, or as a tuple of lists if *index* is a sequence.

- The `sum` function calculates the sum of the elements of the object with label(s) given by *index*, using the *labels* array for the object labels. If *index* is `None`, all elements with a non-zero label value are treated as a single object. If *label* is `None`, all elements of *input* are used in the calculation.
- The `mean` function calculates the mean of the elements of the object with label(s) given by *index*, using the *labels* array for the object labels. If *index* is `None`, all elements with a non-zero label value are treated as a single object. If *label* is `None`, all elements of *input* are used in the calculation.
- The `variance` function calculates the variance of the elements of the object with label(s) given by *index*, using the *labels* array for the object labels. If *index* is `None`, all elements with a non-zero label value are treated as a single object. If *label* is `None`, all elements of *input* are used in the calculation.
- The `standard_deviation` function calculates the standard deviation of the elements of the object with label(s) given by *index*, using the *labels* array for the object labels. If *index* is `None`, all elements with a non-zero label value are treated as a single object. If *label* is `None`, all elements of *input* are used in the calculation.
- The `minimum` function calculates the minimum of the elements of the object with label(s) given by *index*, using the *labels* array for the object labels. If *index* is `None`, all elements with a non-zero label value are treated as a single object. If *label* is `None`, all elements of *input* are used in the calculation.
- The `maximum` function calculates the maximum of the elements of the object with label(s) given by *index*, using the *labels* array for the object labels. If *index* is `None`, all elements with a non-zero label value are treated as a single object. If *label* is `None`, all elements of *input* are used in the calculation.
- The `minimum_position` function calculates the position of the minimum of the elements of the object with label(s) given by *index*, using the *labels* array for the object labels. If *index* is `None`, all elements with a non-zero label value are treated as a single object. If *label* is `None`, all elements of *input* are used in the calculation.
- The `maximum_position` function calculates the position of the maximum of the elements of the object with label(s) given by *index*, using the *labels* array for the object labels. If *index* is `None`, all elements with a non-zero label value are treated as a single object. If *label* is `None`, all elements of *input* are used in the calculation.
- The `extrema` function calculates the minimum, the maximum, and their positions, of the elements of the object with label(s) given by *index*, using the *labels* array for the object labels. If *index* is `None`, all elements with a non-zero label value are treated as a single object. If *label* is `None`, all elements of *input* are used in the calculation. The

result is a tuple giving the minimum, the maximum, the position of the minimum, and the position of the maximum. The result is the same as a tuple formed by the results of the functions *minimum*, *maximum*, *minimum_position*, and *maximum_position* that are described above.

- The *center_of_mass* function calculates the center of mass of the object with label(s) given by *index*, using the *labels* array for the object labels. If *index* is `None`, all elements with a non-zero label value are treated as a single object. If *label* is `None`, all elements of *input* are used in the calculation.
- The *histogram* function calculates a histogram of the object with label(s) given by *index*, using the *labels* array for the object labels. If *index* is `None`, all elements with a non-zero label value are treated as a single object. If *label* is `None`, all elements of *input* are used in the calculation. Histograms are defined by their minimum (*min*), maximum (*max*), and the number of bins (*bins*). They are returned as 1-D arrays of type `numpy.int32`.

Extending `scipy.ndimage` in C

A few functions in *scipy.ndimage* take a callback argument. This can be either a python function or a *scipy.LowLevelCallable* containing a pointer to a C function. Using a C function will generally be more efficient, since it avoids the overhead of calling a python function on many elements of an array. To use a C function, you must write a C extension that contains the callback function and a Python function that returns a *scipy.LowLevelCallable* containing a pointer to the callback.

An example of a function that supports callbacks is *geometric_transform*, which accepts a callback function that defines a mapping from all output coordinates to corresponding coordinates in the input array. Consider the following python example, which uses *geometric_transform* to implement a shift function.

```
from scipy import ndimage

def transform(output_coordinates, shift):
    input_coordinates = output_coordinates[0] - shift, output_coordinates[1] -
    ↪ shift
    return input_coordinates

im = np.arange(12).reshape(4, 3).astype(np.float64)
shift = 0.5
print(ndimage.geometric_transform(im, transform, extra_arguments=(shift,)))
```

We can also implement the callback function with the following C code:

```
/* example.c */

#include <Python.h>
#include <numpy/np_common.h>

static int
_transform(npyp_intp *output_coordinates, double *input_coordinates,
          int output_rank, int input_rank, void *user_data)
{
    npyp_intp i;
    double shift = *(double *)user_data;

    for (i = 0; i < input_rank; i++) {
        input_coordinates[i] = output_coordinates[i] - shift;
    }
    return 1;
}
```

(continues on next page)

(continued from previous page)

```

}

static char *transform_signature = "int (numpy_intp *, double *, int, int, void_
↳*) ";

static PyObject *
py_get_transform(PyObject *obj, PyObject *args)
{
    if (!PyArg_ParseTuple(args, "")) return NULL;
    return PyCapsule_New(_transform, transform_signature, NULL);
}

static PyMethodDef ExampleMethods[] = {
    {"get_transform", (PyCFunction)py_get_transform, METH_VARARGS, ""},
    {NULL, NULL, 0, NULL}
};

/* Initialize the module */
static struct PyModuleDef example = {
    PyModuleDef_HEAD_INIT,
    "example",
    NULL,
    -1,
    ExampleMethods,
    NULL,
    NULL,
    NULL,
    NULL
};

PyMODINIT_FUNC
PyInit_example(void)
{
    return PyModule_Create(&example);
}

```

More information on writing Python extension modules can be found [here](#). If the C code is in the file `example.c`, then it can be compiled with the following `setup.py`,

```

from distutils.core import setup, Extension
import numpy

shift = Extension('example',
                  ['example.c'],
                  include_dirs=[numpy.get_include()])

setup(name='example',
      ext_modules=[shift])

```

and now running the script

```

import ctypes
import numpy as np
from scipy import ndimage, LowLevelCallable

from example import get_transform

shift = 0.5

user_data = ctypes.c_double(shift)
ptr = ctypes.cast(ctypes.pointer(user_data), ctypes.c_void_p)
callback = LowLevelCallable(get_transform(), ptr)
im = np.arange(12).reshape(4, 3).astype(np.float64)
print(ndimage.geometric_transform(im, callback))

```

produces the same result as the original python script.

In the C version, `_transform` is the callback function and the parameters `output_coordinates` and `input_coordinates` play the same role as they do in the python version, while `output_rank` and `input_rank` provide the equivalents of `len(output_coordinates)` and `len(input_coordinates)`. The variable `shift` is passed through `user_data` instead of `extra_arguments`. Finally, the C callback function returns an integer status, which is one upon success and zero otherwise.

The function `py_transform` wraps the callback function in a `PyCapsule`. The main steps are:

- Initialize a `PyCapsule`. The first argument is a pointer to the callback function.
- The second argument is the function signature, which must match exactly the one expected by `ndimage`.
- Above, we used `scipy.LowLevelCallable` to specify `user_data` that we generated with `ctypes`.

A different approach would be to supply the data in the capsule context, that can be set by `PyCapsule_SetContext` and omit specifying `user_data` in `scipy.LowLevelCallable`. However, in this approach we would need to deal with allocation/freeing of the data — freeing the data after the capsule has been destroyed can be done by specifying a non-NULL callback function in the third argument of `PyCapsule_New`.

C callback functions for `ndimage` all follow this scheme. The next section lists the `ndimage` functions that accept a C callback function and gives the prototype of the function.

See also:

The functions that support low-level callback arguments are:

`generic_filter`, `generic_filter1d`, `geometric_transform`

Below, we show alternative ways to write the code, using `Numba`, `Cython`, `ctypes`, or `ffi` instead of writing wrapper code in C.

Numba

Numba provides a way to write low-level functions easily in Python. We can write the above using Numba as:

```

# example.py
import numpy as np
import ctypes
from scipy import ndimage, LowLevelCallable
from numba import cfunc, types, carray

```

(continues on next page)

(continued from previous page)

```

@cfunc(types.intc(types.CPointer(types.intp),
                    types.CPointer(types.double),
                    types.intc,
                    types.intc,
                    types.voidptr))
def transform(output_coordinates_ptr, input_coordinates_ptr,
              output_rank, input_rank, user_data):
    input_coordinates = carray(input_coordinates_ptr, (input_rank,))
    output_coordinates = carray(output_coordinates_ptr, (output_rank,))
    shift = carray(user_data, (1,), types.double)[0]

    for i in range(input_rank):
        input_coordinates[i] = output_coordinates[i] - shift

    return 1

shift = 0.5

# Then call the function
user_data = ctypes.c_double(shift)
ptr = ctypes.cast(ctypes.pointer(user_data), ctypes.c_void_p)
callback = LowLevelCallable(transform.ctypes, ptr)

im = np.arange(12).reshape(4, 3).astype(np.float64)
print(ndimage.geometric_transform(im, callback))

```

Cython

Functionally the same code as above can be written in Cython with somewhat less boilerplate as follows:

```

# example.pyx

from numpy cimport npy_intp as intp

cdef api int transform(intp *output_coordinates, double *input_coordinates,
                      int output_rank, int input_rank, void *user_data):
    cdef intp i
    cdef double shift = (<double *>user_data)[0]

    for i in range(input_rank):
        input_coordinates[i] = output_coordinates[i] - shift

    return 1

```

```

# script.py

import ctypes
import numpy as np
from scipy import ndimage, LowLevelCallable

import example

```

(continues on next page)

(continued from previous page)

```

shift = 0.5

user_data = ctypes.c_double(shift)
ptr = ctypes.cast(ctypes.pointer(user_data), ctypes.c_void_p)
callback = LowLevelCallable.from_cython(example, "transform", ptr)
im = np.arange(12).reshape(4, 3).astype(np.float64)
print(ndimage.geometric_transform(im, callback))

```

ctypes

With `ctypes`, you can interface with a C function residing in a shared library (DLL). First, we need to write the shared library, which we do in C — this example is for Linux/OSX:

```

/*
   example.c
   Needs to be compiled with "gcc -std=c99 -shared -fPIC -o example.so example.
   →C"
   or similar
*/

#include <stdint.h>

int
_transform(intptr_t *output_coordinates, double *input_coordinates,
           int output_rank, int input_rank, void *user_data)
{
    int i;
    double shift = *(double *)user_data;

    for (i = 0; i < input_rank; i++) {
        input_coordinates[i] = output_coordinates[i] - shift;
    }
    return 1;
}

```

The Python code calling the library is:

```

import os
import numpy as np
from scipy import ndimage, LowLevelCallable
import ctypes

# Construct the FFI object, and copy/paste the function declaration
ffi = ctypes.CDLL()
ffi.cdef("""
int _transform(intptr_t *output_coordinates, double *input_coordinates,
               int output_rank, int input_rank, void *user_data);
""")

# Open library
lib = ffi.dlopen(os.path.abspath("example.so"))

```

(continues on next page)

(continued from previous page)

```
# Do the function call
user_data = ffi.new('double *', 0.5)
callback = LowLevelCallable(lib._transform, user_data)
im = np.arange(12).reshape(4, 3).astype(np.float64)
print(ndimage.geometric_transform(im, callback))
```

You can find more information in the [cffi](#) documentation.

ctypes

With *ctypes*, the C code and the compilation of the so/DLL is as for *cffi* above. The Python code is different:

```
# script.py

import os
import ctypes
import numpy as np
from scipy import ndimage, LowLevelCallable

lib = ctypes.CDLL(os.path.abspath('example.so'))

shift = 0.5

user_data = ctypes.c_double(shift)
ptr = ctypes.cast(ctypes.pointer(user_data), ctypes.c_void_p)

# Ctypes has no built-in intptr type, so override the signature
# instead of trying to get it via ctypes
callback = LowLevelCallable(lib._transform, ptr,
    "int _transform(intptr_t *, double *, int, int, void *)")

# Perform the call
im = np.arange(12).reshape(4, 3).astype(np.float64)
print(ndimage.geometric_transform(im, callback))
```

You can find more information in the [ctypes](#) documentation.

References

4.1.14 File IO ([scipy.io](#))

See also:

NumPy IO routines

MATLAB files

<code>loadmat(file_name[, mdict, appendmat])</code>	Load MATLAB file.
<code>savemat(file_name, mdict[, appendmat, ...])</code>	Save a dictionary of names and arrays into a MATLAB-style .mat file.
<code>whosmat(file_name[, appendmat])</code>	List variables inside a MATLAB file.

The basic functions

We'll start by importing `scipy.io` and calling it `sio` for convenience:

```
>>> import scipy.io as sio
```

If you are using IPython, try tab-completing on `sio`. Among the many options, you will find:

```
sio.loadmat
sio.savemat
sio.whosmat
```

These are the high-level functions you will most likely use when working with MATLAB files. You'll also find:

```
sio.matlab
```

This is the package from which `loadmat`, `savemat`, and `whosmat` are imported. Within `sio.matlab`, you will find the `mio` module. This module contains the machinery that `loadmat` and `savemat` use. From time to time you may find yourself re-using this machinery.

How do I start?

You may have a .mat file that you want to read into SciPy. Or, you want to pass some variables from SciPy / NumPy into MATLAB.

To save us using a MATLAB license, let's start in [Octave](#). Octave has MATLAB-compatible save and load functions. Start Octave (`octave` at the command line for me):

```
octave:1> a = 1:12
a =
    1    2    3    4    5    6    7    8    9   10   11   12

octave:2> a = reshape(a, [1 3 4])
a =

ans(:,:,1) =
    1    2    3

ans(:,:,2) =
    4    5    6

ans(:,:,3) =
    7    8    9
```

(continues on next page)

(continued from previous page)

```
ans(:, :, 4) =
    10    11    12

octave:3> save -6 octave_a.mat a % MATLAB 6 compatible
octave:4> ls octave_a.mat
octave_a.mat
```

Now, to Python:

```
>>> mat_contents = sio.loadmat('octave_a.mat')
>>> mat_contents
{'a': array([[[ 1.,  4.,  7., 10.],
              [ 2.,  5.,  8., 11.],
              [ 3.,  6.,  9., 12.]])],
 '__version__': '1.0',
 '__header__': 'MATLAB 5.0 MAT-file, written by
Octave 3.6.3, 2013-02-17 21:02:11 UTC',
 '__globals__': []}
>>> oct_a = mat_contents['a']
>>> oct_a
array([[[ 1.,  4.,  7., 10.],
         [ 2.,  5.,  8., 11.],
         [ 3.,  6.,  9., 12.]])])
>>> oct_a.shape
(1, 3, 4)
```

Now let's try the other way round:

```
>>> import numpy as np
>>> vect = np.arange(10)
>>> vect.shape
(10,)
>>> sio.savemat('np_vector.mat', {'vect':vect})
```

Then back to Octave:

```
octave:8> load np_vector.mat
octave:9> vect
vect =

    0    1    2    3    4    5    6    7    8    9

octave:10> size(vect)
ans =

    1   10
```

If you want to inspect the contents of a MATLAB file without reading the data into memory, use the `whosmat` command:

```
>>> sio.whosmat('octave_a.mat')
[('a', (1, 3, 4), 'double')]
```

`whosmat` returns a list of tuples, one for each array (or other object) in the file. Each tuple contains the name, shape and data type of the array.

MATLAB structs

MATLAB structs are a little bit like Python dicts, except the field names must be strings. Any MATLAB object can be a value of a field. As for all objects in MATLAB, structs are, in fact, arrays of structs, where a single struct is an array of shape (1, 1).

```
octave:11> my_struct = struct('field1', 1, 'field2', 2)
my_struct =
{
  field1 = 1
  field2 = 2
}

octave:12> save -6 octave_struct.mat my_struct
```

We can load this in Python:

```
>>> mat_contents = sio.loadmat('octave_struct.mat')
>>> mat_contents
{'my_struct': array([[1.0], [2.0]]),
  dtype=[('field1', 'O'), ('field2', 'O')], '__version__': '1.0', '__
↳header__': 'MATLAB 5.0 MAT-file, written by Octave 3.6.3, 2013-02-17_
↳21:23:14 UTC', '__globals__': []}
>>> oct_struct = mat_contents['my_struct']
>>> oct_struct.shape
(1, 1)
>>> val = oct_struct[0,0]
>>> val
([1.0], [2.0])
>>> val['field1']
array([1.])
>>> val['field2']
array([2.])
>>> val.dtype
dtype([('field1', 'O'), ('field2', 'O')])
```

In the SciPy versions from 0.12.0, MATLAB structs come back as NumPy structured arrays, with fields named for the struct fields. You can see the field names in the `dtype` output above. Note also:

```
>>> val = oct_struct[0,0]
```

and:

```
octave:13> size(my_struct)
ans =
    1    1
```

So, in MATLAB, the struct array must be at least 2-D, and we replicate that when we read into SciPy. If you want all length 1 dimensions squeezed out, try this:


```
>>> mat_contents = sio.loadmat('octave_struct.mat', squeeze_me=True)
>>> oct_struct = mat_contents['my_struct']
>>> oct_struct.shape
()
```

Sometimes, it's more convenient to load the MATLAB structs as Python objects rather than NumPy structured arrays - it can make the access syntax in Python a bit more similar to that in MATLAB. In order to do this, use the `struct_as_record=False` parameter setting to `loadmat`.

```
>>> mat_contents = sio.loadmat('octave_struct.mat', struct_as_record=False)
>>> oct_struct = mat_contents['my_struct']
>>> oct_struct[0,0].field1
array([[ 1.]])
```

`struct_as_record=False` works nicely with `squeeze_me`:

```
>>> mat_contents = sio.loadmat('octave_struct.mat', struct_as_record=False,
↳ squeeze_me=True)
>>> oct_struct = mat_contents['my_struct']
>>> oct_struct.shape # but no - it's a scalar
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
AttributeError: 'mat_struct' object has no attribute 'shape'
>>> type(oct_struct)
<class 'scipy.io.matlab.mio5_params.mat_struct'>
>>> oct_struct.field1
1.0
```

Saving struct arrays can be done in various ways. One simple method is to use dicts:

```
>>> a_dict = {'field1': 0.5, 'field2': 'a string'}
>>> sio.savemat('saved_struct.mat', {'a_dict': a_dict})
```

loaded as:

```
octave:21> load saved_struct
octave:22> a_dict
a_dict =

  scalar structure containing the fields:

   field2 = a string
   field1 = 0.50000
```

You can also save structs back again to MATLAB (or Octave in our case) like this:

```
>>> dt = [('f1', 'f8'), ('f2', 'S10')]
>>> arr = np.zeros((2,), dtype=dt)
>>> arr
array([(0.0, ''), (0.0, '')],
      dtype=[('f1', '<f8'), ('f2', 'S10')])
>>> arr[0]['f1'] = 0.5
>>> arr[0]['f2'] = 'python'
>>> arr[1]['f1'] = 99
```

(continues on next page)

(continued from previous page)

```
>>> arr[1]['f2'] = 'not perl'
>>> sio.savemat('np_struct_arr.mat', {'arr': arr})
```

MATLAB cell arrays

Cell arrays in MATLAB are rather like Python lists, in the sense that the elements in the arrays can contain any type of MATLAB object. In fact, they are most similar to NumPy object arrays, and that is how we load them into NumPy.

```
octave:14> my_cells = {1, [2, 3]}
my_cells =
{
  [1,1] = 1
  [1,2] =
      2   3
}

octave:15> save -6 octave_cells.mat my_cells
```

Back to Python:

```
>>> mat_contents = sio.loadmat('octave_cells.mat')
>>> oct_cells = mat_contents['my_cells']
>>> print(oct_cells.dtype)
object
>>> val = oct_cells[0,0]
>>> val
array([[ 1.]])
>>> print(val.dtype)
float64
```

Saving to a MATLAB cell array just involves making a NumPy object array:

```
>>> obj_arr = np.zeros((2,), dtype=np.object)
>>> obj_arr[0] = 1
>>> obj_arr[1] = 'a string'
>>> obj_arr
array([1, 'a string'], dtype=object)
>>> sio.savemat('np_cells.mat', {'obj_arr':obj_arr})
```

```
octave:16> load np_cells.mat
octave:17> obj_arr
obj_arr =
{
  [1,1] = 1
  [2,1] = a string
}
```

IDL files

<code>readsav(file_name[, idict, python_dict, ...])</code>	Read an IDL .sav file.
--	------------------------

Matrix Market files

<code>mminfo(source)</code>	Return size and storage parameters from Matrix Market file-like 'source'.
<code>mmread(source)</code>	Reads the contents of a Matrix Market file-like 'source' into a matrix.
<code>mmwrite(target, a[, comment, field, ...])</code>	Writes the sparse or dense array <i>a</i> to Matrix Market file-like <i>target</i> .

Wav sound files (`scipy.io.wavfile`)

<code>read(filename[, mmap])</code>	Open a WAV file.
<code>write(filename, rate, data)</code>	Write a NumPy array as a WAV file.

Arff files (`scipy.io.arff`)

<code>loadarff(f)</code>	Read an arff file.
--------------------------	--------------------

Netcdf

<code>netcdf_file(filename[, mode, mmap, version, ...])</code>	A file object for NetCDF data.
--	--------------------------------

Allows reading of NetCDF files (version of `pupynere` package)

DEVELOPER DOCUMENTATION

If you're interested in contributing to SciPy, start here:

5.1 SciPy Code of Conduct

5.1.1 Introduction

This code of conduct applies to all spaces managed by the SciPy project, including all public and private mailing lists, issue trackers, wikis, blogs, Twitter, and any other communication channel used by our community. The SciPy project does not organize in-person events, however, events related to our community should have a code of conduct similar in spirit to this one.

This code of conduct should be honored by everyone who participates in the SciPy community formally or informally, or claims any affiliation with the project, in any project-related activities, and, especially, when representing the project, in any role.

This code is neither exhaustive nor complete. It serves to distill our common understanding of a collaborative, shared environment and goals. Please try to follow this code in spirit as much as in letter, to create a friendly and productive environment that enriches the surrounding community.

5.1.2 Specific guidelines

We strive to:

1. Be open. We invite anyone to participate in our community. We prefer to use public methods of communication for project-related messages, unless discussing something sensitive. This applies to messages for help or project-related support, too; not only is a public-support request much more likely to result in an answer to a question, it also ensures that any inadvertent mistakes in answering are more easily detected and corrected.
2. Be empathetic, welcoming, friendly, and patient. We work together to resolve conflict, and assume good intentions. We may all experience some frustration from time to time, but we do not allow frustration to turn into a personal attack. A community where people feel uncomfortable or threatened is not a productive one.
3. Be collaborative. Our work will be used by other people, and in turn we will depend on the work of others. When we make something for the benefit of the project, we are willing to explain to others how it works, so that they can build on the work to make it even better. Any decision we make will affect users and colleagues, and we take those consequences seriously when making decisions.
4. Be inquisitive. Nobody knows everything! Asking questions early avoids many problems later, so we encourage questions, although we may direct them to the appropriate forum. We will try hard to be responsive and helpful.

5. Be careful in the words that we choose. We are careful and respectful in our communication and we take responsibility for our own speech. Be kind to others. Do not insult or put down other participants. We will not accept harassment or other exclusionary behavior, such as:
 - Violent threats or language directed against another person.
 - Sexist, racist, or otherwise discriminatory jokes and language.
 - Posting sexually explicit or violent material.
 - Posting (or threatening to post) other people’s personally identifying information (“doxing”).
 - Sharing private content, such as emails sent privately or non-publicly, or unlogged forums, such as IRC channel history, without the sender’s consent.
 - Personal insults, especially those using racist or sexist terms.
 - Unwelcome sexual attention.
 - Excessive profanity. Please avoid swearwords; people differ greatly in their sensitivity to swearing.
 - Repeated harassment of others. In general, if someone asks you to stop, then stop.
 - Advocating for, or encouraging, any of the above behavior.

5.1.3 Diversity statement

The SciPy project welcomes and encourages participation by everyone. We are committed to being a community that everyone enjoys being part of. Although we may not always be able to accommodate each individual’s preferences, we try our best to treat everyone kindly.

No matter how you identify yourself or how others perceive you: we welcome you. Though no list can hope to be comprehensive, we explicitly honor diversity in: age, culture, ethnicity, genotype, gender identity or expression, language, national origin, neurotype, phenotype, political beliefs, profession, race, religion, sexual orientation, socioeconomic status, subculture and technical ability, to the extent that these do not conflict with this code of conduct.

Though we welcome people fluent in all languages, SciPy development is conducted in English.

Standards for behavior in the SciPy community are detailed in the Code of Conduct above. Participants in our community should uphold these standards in all their interactions and help others to do so as well (see next section).

5.1.4 Reporting guidelines

We know that it is painfully common for internet communication to start at or devolve into obvious and flagrant abuse. We also recognize that sometimes people may have a bad day, or be unaware of some of the guidelines in this Code of Conduct. Please keep this in mind when deciding on how to respond to a breach of this Code.

For clearly intentional breaches, report those to the Code of Conduct committee (see below). For possibly unintentional breaches, you may reply to the person and point out this Code of Conduct (either in public or in private, whatever is most appropriate). If you would prefer not to do that, please feel free to report to the Code of Conduct committee directly, or ask the committee for advice, in confidence.

You can report issues to the SciPy Code of Conduct Committee, at scipy-conduct@googlegroups.com. Currently, the committee consists of:

- Stefan van der Walt
- Nathaniel J. Smith
- Ralf Gommers

If your report involves any members of the committee, or if they feel they have a conflict of interest in handling it, then they will recuse themselves from considering your report. Alternatively, if, for any reason, you feel uncomfortable making a report to the committee, then you can also contact:

- Chair of the SciPy Steering Committee: Ralf Gommers, or
- Senior NumFOCUS staff: conduct@numfocus.org

5.1.5 Incident reporting resolution & Code of Conduct enforcement

This section summarizes the most important points, more details can be found in [CoC_reporting_manual](#).

We will investigate and respond to all complaints. The SciPy Code of Conduct Committee and the SciPy Steering Committee (if involved) will protect the identity of the reporter, and treat the content of complaints as confidential (unless the reporter agrees otherwise).

In case of severe and obvious breaches, e.g., personal threat or violent, sexist or racist language, we will immediately disconnect the originator from SciPy communication channels; please see the manual for details.

In cases not involving clear severe and obvious breaches of this code of conduct, the process for acting on any received code of conduct violation report will be:

1. acknowledgement that the report has been received
2. reasonable discussion/feedback
3. mediation (if feedback didn't help, and only if both reporter and reportee agree to this)
4. enforcement via transparent decision (see [CoC_resolutions](#)) by the Code of Conduct Committee

The committee will respond to any report as soon as possible, and at most within 72 hours.

5.1.6 Endnotes

We are thankful to the groups behind the following documents, from which we drew content and inspiration:

- [The Apache Foundation Code of Conduct](#)
- [The Contributor Covenant](#)
- [Jupyter Code of Conduct](#)
- [Open Source Guides - Code of Conduct](#)

5.2 Ways to Contribute

This document aims to give an overview of the ways to contribute to SciPy. It tries to answer commonly asked questions and provide some insight into how the community process works in practice. Readers who are familiar with the SciPy community and are experienced Python coders may want to jump straight to the [SciPy contributor guide](#).

There are a lot of ways you can contribute:

- Contributing new code
- Fixing bugs, improving documentation, and other maintenance work
- Reviewing open pull requests
- Triaging issues

- Working on the scipy.org website
- Answering questions and participating on the [scipy-dev](#) and [scipy-user mailing lists](#).

5.2.1 Contributing new code

If you have been working with the scientific Python toolstack for a while, you probably have some code lying around of which you think “this could be useful for others too”. Perhaps it’s a good idea then to contribute it to SciPy or another open source project. The first question to ask is then, where does this code belong? That question is hard to answer here, so we start with a more specific one: *what code is suitable for putting into SciPy?* Almost all of the new code added to SciPy has in common that it’s potentially useful in multiple scientific domains and it fits in the scope of existing SciPy subpackages (see [Deciding on new features](#)). In principle new subpackages can be added too, but this is far less common. For code that is specific to a single application, there may be an existing project that can use the code. Some SciKits ([scikit-learn](#), [scikit-image](#), [statsmodels](#), etc.) are good examples here; they have a narrower focus and because of that more domain-specific code than SciPy.

Now if you have code that you would like to see included in SciPy, how do you go about it? After checking that your code can be distributed in SciPy under a compatible license (see [License Considerations](#)), the first step is to discuss on the [scipy-dev mailing list](#). All new features, as well as changes to existing code, are discussed and decided on there. You can, and probably should, already start this discussion before your code is finished. Remember that in order to be added to SciPy your code will need to be reviewed by someone else, so try to find someone willing to review your work while you’re at it.

Assuming the outcome of the discussion on the mailing list is positive and you have a function or piece of code that does what you need it to do, what next? Before code is added to SciPy, it at least has to have good documentation, unit tests, benchmarks, and correct code style.

1. *Unit tests*

In principle you should aim to create unit tests that exercise all the code that you are adding. This gives some degree of confidence that your code runs correctly, also on Python versions and hardware or OSes that you don’t have available yourself. An extensive description of how to write unit tests is given in [Testing Guidelines](#), and [Running SciPy Tests Locally](#) documents how to run them.

2. *Benchmarks*

Unit tests check for correct functionality; benchmarks measure code performance. Not all existing SciPy code has benchmarks, but it should: as SciPy grows it is increasingly important to monitor execution times in order to catch unexpected regressions. More information about writing and running benchmarks is available in [Benchmarking SciPy with airspeed velocity](#).

3. *Documentation*

Clear and complete documentation is essential in order for users to be able to find and understand the code. Documentation for individual functions and classes – which includes at least a basic description, type and meaning of all parameters and returns values, and usage examples in `doctest` format – is put in docstrings. Those docstrings can be read within the interpreter, and are compiled into a reference guide in html and pdf format. Higher-level documentation for key (areas of) functionality is provided in tutorial format and/or in module docstrings. A guide on how to write documentation is given in [A Guide to NumPy Documentation](#), and [Rendering Documentation with Sphinx](#) explains how to preview the documentation as it will appear online.

4. *Code style*

Uniformity of style in which code is written is important to others trying to understand the code. SciPy follows the standard Python guidelines for code style, [PEP8](#). In order to check that your code conforms to PEP8, you can use the [pep8 package](#) style checker. Most IDEs and text editors have settings that can help you follow PEP8, for example by translating tabs by four spaces. Using [pyflakes](#) to check your code is also a good idea. More information is available in [PEP8 and SciPy](#).

A *checklist*, including these and other requirements, is available at the end of the example *Development workflow*.

Another question you may have is: *where exactly do I put my code?* To answer this, it is useful to understand how the SciPy public API (application programming interface) is defined. For most modules the API is two levels deep, which means your new function should appear as `scipy.subpackage.my_new_func`. `my_new_func` can be put in an existing or new file under `/scipy/<subpackage>/`, its name is added to the `__all__` list in that file (which lists all public functions in the file), and those public functions are then imported in `/scipy/<subpackage>/__init__.py`. Any private functions/classes should have a leading underscore (`_`) in their name. A more detailed description of what the public API of SciPy is, is given in *SciPy API*.

Once you think your code is ready for inclusion in SciPy, you can send a pull request (PR) on Github. We won't go into the details of how to work with git here, this is described well in [git-development](#) and on the [Github help pages](#). When you send the PR for a new feature, be sure to also mention this on the `scipy-dev` mailing list. This can prompt interested people to help review your PR. Assuming that you already got positive feedback before on the general idea of your code/feature, the purpose of the code review is to ensure that the code is correct, efficient and meets the requirements outlined above. In many cases the code review happens relatively quickly, but it's possible that it stalls. If you have addressed all feedback already given, it's perfectly fine to ask on the mailing list again for review (after a reasonable amount of time, say a couple of weeks, has passed). Once the review is completed, the PR is merged into the "master" branch of SciPy.

The above describes the requirements and process for adding code to SciPy. It doesn't yet answer the question though how decisions are made exactly. The basic answer is: decisions are made by consensus, by everyone who chooses to participate in the discussion on the mailing list. This includes developers, other users and yourself. Aiming for consensus in the discussion is important – SciPy is a project by and for the scientific Python community. In those rare cases that agreement cannot be reached, the maintainers of the module in question can decide the issue.

License Considerations

I based my code on existing Matlab/R/... code I found online, is this OK?

It depends. SciPy is distributed under a BSD license, so if the code that you based your code on is also BSD licensed or has a BSD-compatible license (e.g. MIT, PSF) then it's OK. Code which is GPL or Apache licensed, has no clear license, requires citation or is free for academic use only can't be included in SciPy. Therefore if you copied existing code with such a license or made a direct translation to Python of it, your code can't be included. If you're unsure, please ask on the `scipy-dev` [mailing list](#).

Why is SciPy under the BSD license and not, say, the GPL?

Like Python, SciPy uses a "permissive" open source license, which allows proprietary re-use. While this allows companies to use and modify the software without giving anything back, it is felt that the larger user base results in more contributions overall, and companies often publish their modifications anyway, without being required to. See John Hunter's [BSD pitch](#).

For more information about SciPy's license, see [Licensing](#).

5.2.2 Maintaining existing code

The previous section talked specifically about adding new functionality to SciPy. A large part of that discussion also applies to maintenance of existing code. Maintenance means fixing bugs, improving code quality, documenting existing functionality better, adding missing unit tests, adding performance benchmarks, keeping build scripts up-to-date, etc. The [SciPy issue list](#) contains all reported bugs, build/documentation issues, etc. Fixing issues helps improve the overall quality of SciPy, and is also a good way of getting familiar with the project. You may also want to fix a bug because you ran into it and need the function in question to work correctly.

The discussion on code style and unit testing above applies equally to bug fixes. It is usually best to start by writing a unit test that shows the problem, i.e. it should pass but doesn't. Once you have that, you can fix the code so that the test does pass. That should be enough to send a PR for this issue. Unlike when adding new code, discussing this on the mailing list may not be necessary - if the old behavior of the code is clearly incorrect, no one will object to having it fixed. It may

be necessary to add some warning or deprecation message for the changed behavior. This should be part of the review process.

Note: Pull requests that *only* change code style, e.g. fixing some PEP8 issues in a file, are discouraged. Such PRs are often not worth cluttering the git annotate history, and take reviewer time that may be better spent in other ways. Code style cleanups of code that is touched as part of a functional change are fine however.

5.2.3 Reviewing pull requests

Reviewing open pull requests (PRs) is very welcome, and a valuable way to help increase the speed at which the project moves forward. If you have specific knowledge/experience in a particular area (say “optimization algorithms” or “special functions”) then reviewing PRs in that area is especially valuable - sometimes PRs with technical code have to wait for a long time to get merged due to a shortage of appropriate reviewers.

We encourage everyone to get involved in the review process; it’s also a great way to get familiar with the code base. Reviewers should ask themselves some or all of the following questions:

- Was this change adequately discussed (relevant for new features and changes in existing behavior)?
- Is the feature scientifically sound? Algorithms may be known to work based on literature; otherwise, closer look at correctness is valuable.
- Is the intended behavior clear under all conditions (e.g. unexpected inputs like empty arrays or nan/inf values)?
- Does the code meet the quality, test and documentation expectation outline under *Contributing new code?*

If we do not know you yet, consider introducing yourself.

5.2.4 Other ways to contribute

There are many ways to contribute other than writing code.

Triaging issues (investigating bug reports for validity and possible actions to take) is also a useful activity. SciPy has many hundreds of open issues; closing invalid ones and correctly labeling valid ones (ideally with some first thoughts in a comment) allows prioritizing maintenance work and finding related issues easily when working on an existing function or subpackage.

Participating in discussions on the `scipy-user` and `scipy-dev` [mailing lists](#) is a contribution in itself. Everyone who writes to those lists with a problem or an idea would like to get responses, and writing such responses makes the project and community function better and appear more welcoming.

The scipy.org website contains a lot of information on both SciPy the project and SciPy the community, and it can always use a new pair of hands. The sources for the website live in their own separate repo: <https://github.com/scipy/scipy.org>

5.2.5 Getting started

Thanks for your interest in contributing to SciPy! If you’re interested in contributing code, we hope you’ll continue on to the *SciPy contributor guide* for details on how to set up your development environment, implement your improvements, and submit your first PR!

5.3 SciPy contributor guide

This guide is designed to help you quickly find the information you need about SciPy development after you've reviewed the introductory material in *Ways to Contribute*. If you're new to this and want to start coding ASAP, you've found the right place.

- *Development environment* - how to set up and maintain a development environment, including installing compilers and SciPy dependencies, creating a personal fork of the SciPy repository on GitHub, using git to manage a local repository with development branches, performing an in-place build of SciPy, and creating a virtual environment that adds this development version of SciPy to the Python path
- *Editing SciPy* - how to edit SciPy Python code, with tips on finding which module contains SciPy functionality to be edited, adding new modules to SciPy, and complying with PEP8 style standards
- *Unit tests* - how to write and run unit tests for SciPy with the pytest framework
- *Documentation* - how to write reStructuredText documentation that complies with docstring standards, build documentation locally with Sphinx, and view documentation built during continuous integration checks
- *Benchmarks* - how to benchmark code with airspeed velocity
- *Compiled code* - how to add fast, compiled code to SciPy

5.3.1 Development environment

- quickstart-pip presents an overview of setting up the development environment using pip on Linux
- *Development environment quickstart guide (macOS)* presents a step-by-step process for setting up a convenient SciPy development environment in macOS
- *Development environment quickstart guide (Ubuntu)* presents a step-by-step process for setting up a convenient SciPy development environment in Ubuntu
- build-windows presents a step-by-step process for building SciPy on Windows
- quickstart-docker presents a step-by-step process for building SciPy using Docker; if you have trouble with the instructions above, this may be your best option
- building may have some helpful hints if you need to deviate from the guides above
- recommended-development-setup includes additional notes about the development setup; all of this information is contained elsewhere, but it is retained as a legacy document

5.3.2 Editing SciPy

- *Development workflow* lays out what to do after your development environment is set up
- *SciPy Development Workflow* is a five-minute video example of fixing a bug and submitting a pull request
- *PEP8 and SciPy* gives some tips for ensuring that your code is PEP8 compliant
- *git-development* is a guide to using `git`, the distributed version-control system used to manage the changes made to SciPy code from around the world
- *SciPy API* contains some important notes about how SciPy code is organized and documents the structure of the SciPy API; if you are going to import other SciPy code, read this first
- *reviewing-prs* explains how to review another author's SciPy code locally
- *NumPy Distutils - Users Guide* - check this out before adding any new files to SciPy

- *Adding New Methods, Functions, and Classes* has information on how to add new methods, functions and classes
- *SciPy Core Developer Guide* has background information including how decisions are made and how a release is prepared; it's geared toward *Core Developers*, but contains useful information for all contributors

5.3.3 Unit tests

- *Testing Guidelines* is the definitive guide to writing unit tests of SciPy code
- *Running SciPy Tests Locally* documents `runtests.py`, a convenient script for building SciPy and running tests locally

5.3.4 Documentation

- *A Guide to NumPy Documentation* contains everything you need to know about writing docstrings, which are rendered to produce HTML documentation using *Sphinx*
- *Rendering Documentation with Sphinx* it's important to check how changes to the documentation render before merging a PR; this document explains how you can do that

5.3.5 Benchmarks

- *Benchmarking SciPy with airspeed velocity* explains how to add benchmarks to SciPy using *airspeed velocity*

5.3.6 Compiled code

- *Adding Cython to SciPy* extending and compiling Python code with *Cython* can significantly improve its performance; this document helps you get started
- *other-languages* discusses the use of C, C++, and Fortran code in SciPy
- *Public Cython APIs* on guidelines on exposing public Cython APIs

To get an overview of where help or new features are desired or planned, see the roadmap:

5.4 SciPy Roadmap

This roadmap page contains only the most important ideas and needs for SciPy going forward. For a more detailed roadmap, including per-subpackage status, many more ideas, API stability and more, see *Detailed SciPy Roadmap*.

5.4.1 Support for distributed arrays and GPU arrays

NumPy has split its API from its execution engine with `__array_function__` and `__array_ufunc__`. This will enable parts of SciPy to accept distributed arrays (e.g. `dask.array.Array`) and GPU arrays (e.g. `cupy.ndarray`) that implement the `ndarray` interface. At the moment it is not yet clear which algorithms will work out of the box, and if there are significant performance gains when they do. We want to create a map of which parts of the SciPy API work, and improve support over time.

In addition to making use of NumPy protocols like `__array_function__`, we can make use of these protocols in SciPy as well. That will make it possible to (re)implement SciPy functions like, e.g., those in `scipy.signal` for Dask

or GPU arrays (see NEP 18 - use outside of NumPy). NumPy's features in this areas are still evolving, see e.g. NEP 37 - A dispatch protocol for NumPy-like modules, and SciPy is an important "client" for those features.

5.4.2 Performance improvements

Speed improvements, lower memory usage and the ability to parallelize algorithms are beneficial to most science domains and use cases. We have established an API design pattern for multiprocessing - using the `workers` keyword - that can be adopted in many more functions.

Enabling the use of an accelerator like Pythran, possibly via Transonic, and making it easier for users to use Numba's `@njit` in their code that relies on SciPy functionality would unlock a lot of performance gain. That needs a strategy though, all solutions are still maturing (see for example [this overview](#)).

Finally, many individual functions can be optimized for performance. `scipy.optimize` and `scipy.interpolate` functions are particularly often requested in this respect.

5.4.3 Statistics enhancements

The `scipy.stats` enhancements listed in the *Detailed SciPy Roadmap* are of particularly high importance to the project.

- Improve the options for fitting a probability distribution to data.
- Expand the set of hypothesis tests. In particular, include all the basic variations of analysis of variance.
- Add confidence intervals for all statistical tests.

5.4.4 Support for more hardware platforms

SciPy now has continuous integration for ARM64 (or `aarch64`) and POWER8/9 (or `ppc64le`), and binaries are available via [Miniforge](#). Wheels on PyPI for these platforms are now also possible (with the `manylinux2014` standard), and requests for those are becoming more frequent.

Additionally, having IBM Z (or `s390x`) in CI is now possible with TravisCI but not yet done - and `manylinux2014` wheels for that platform are also possible then. Finally, resolving open AIX build issues would help users.

5.4.5 Implement sparse arrays in addition to sparse matrices

The sparse matrix formats are mostly feature-complete, however the main issue is that they act like `numpy.matrix` (which will be deprecated in NumPy at some point). What we want is sparse *arrays* that act like `numpy.ndarray`. This is being worked on in <https://github.com/pydata/sparse>, which is quite far along. The tentative plan is:

- Start depending on `pydata/sparse` once it's feature-complete enough (it still needs a CSC/CSR equivalent) and okay performance-wise.
- Indicate in the documentation that for new code users should prefer `pydata/sparse` over sparse matrices.
- When NumPy deprecates `numpy.matrix`, vendor that or maintain it as a stand-alone package.

5.5 Detailed SciPy Roadmap

Most of this roadmap is intended to provide a high-level view on what is most needed per SciPy submodule in terms of new functionality, bug fixes, etc. Besides important “business as usual” changes, it contains ideas for major new features - those are marked as such, and are expected to take significant dedicated effort. Things not mentioned in this roadmap are not necessarily unimportant or out of scope, however we (the SciPy developers) want to provide to our users and contributors a clear picture of where SciPy is going and where help is needed most.

Note: This is the detailed roadmap. A very high-level overview with only the most important ideas is *SciPy Roadmap*.

5.5.1 General

This roadmap will be evolving together with SciPy. Updates can be submitted as pull requests. For large or disruptive changes you may want to discuss those first on the `scipy-dev` mailing list.

API changes

In general, we want to evolve the API to remove known warts as much as possible, *however as much as possible without breaking backwards compatibility*.

Also, it should be made (even) more clear what is public and what is private in SciPy. Everything private should be named starting with an underscore as much as possible.

Test coverage

Test coverage of code added in the last few years is quite good, and we aim for a high coverage for all new code that is added. However, there is still a significant amount of old code for which coverage is poor. Bringing that up to the current standard is probably not realistic, but we should plug the biggest holes.

Besides coverage there is also the issue of correctness - older code may have a few tests that provide decent statement coverage, but that doesn't necessarily say much about whether the code does what it says on the box. Therefore code review of some parts of the code (`stats`, `signal` and `ndimage` in particular) is necessary.

Documentation

The documentation is in good shape. Expanding of current docstrings and putting them in the standard NumPy format should continue, so the number of reST errors and glitches in the html docs decreases. Most modules also have a tutorial in the reference guide that is a good introduction, however there are a few missing or incomplete tutorials - this should be fixed.

Benchmarks

The `asv`-based benchmark system is in reasonable shape. It is quite easy to add new benchmarks, however running the benchmarks is not very intuitive. Making this easier is a priority. In addition, we should run them in our CI (gh-8779 is an ongoing attempt at this).

Use of Cython

Regarding Cython code:

- It's not clear how much functionality can be Cythonized without making the `.so` files too large. This needs measuring.
- Cython's old syntax for using NumPy arrays should be removed and replaced with Cython memoryviews.

Windows build issues

SciPy critically relies on Fortran code. This is still problematic on Windows. There are currently only two options: using Intel Fortran, or using MSVC + gfortran. The former is expensive, while the latter works (it's what we use for releases) but is quite hard to do correctly. For allowing contributors and end users to reliably build SciPy on Windows, using the Flang compiler looks like the best way forward long-term.

Continuous integration

Continuous integration is in good shape, it currently covers the Windows, macOS and Linux, ARM64 and ppc64le platforms, as well as a range of versions of our dependencies and building release quality wheels.

Size of binaries

SciPy binaries are quite large (e.g. an unzipped manylinux wheel for 1.4.1 is 91 MB), and this can be problematic - for example for use in AWS Lambda, which has a 250 MB size limit. We aim to keep binary size as low as possible; when adding new compiled extensions, this needs checking. Stripping of debug symbols in `multibuild` can likely be improved (see [this issue](#)).

5.5.2 Modules

cluster

This module is in good shape.

constants

This module is basically done, low-maintenance and without open issues.

fft

This module is in good shape.

integrate

Needed for ODE solvers:

- Documentation is pretty bad, needs fixing
- A new ODE solver interface (`solve_ivp`) was added in SciPy 1.0.0. In the future we can consider (soft-)deprecating the older API.

The numerical integration functions are in good shape. Support for integrating complex-valued functions and integrating multiple intervals (see [gh-3325](#)) could be added.

interpolate

Ideas for new features:

- Spline fitting routines with better user control.
- Transparent tensor-product splines.
- NURBS support.
- Mesh refinement and coarsening of B-splines and corresponding tensor products.

io

wavfile:

- PCM float will be supported, for anything else use `audiolab` or other specialized libraries.
- Raise errors instead of warnings if data not understood.

Other sub-modules (`matlab`, `netcdf`, `idl`, `harwell-boeing`, `arff`, `matrix market`) are in good shape.

linalg

`scipy.linalg` is in good shape.

Needed:

- Reduce duplication of functions with `numpy.linalg`, make APIs consistent.
- `get_lapack_funcs` should always use `flapack`
- Wrap more LAPACK functions
- One too many funcs for LU decomposition, remove one

Ideas for new features:

- Add type-generic wrappers in the Cython BLAS and LAPACK
- Make many of the linear algebra routines into `gufuncs`

BLAS and LAPACK

The Python and Cython interfaces to BLAS and LAPACK in `scipy.linalg` are one of the most important things that SciPy provides. In general `scipy.linalg` is in good shape, however we can make a number of improvements:

1. Library support. Our released wheels now ship with OpenBLAS, which is currently the only feasible performant option (ATLAS is too slow, MKL cannot be the default due to licensing issues, Accelerate support is dropped because Apple doesn't update Accelerate anymore). OpenBLAS isn't very stable though, sometimes its releases break things and it has issues with threading (currently the only issue for using SciPy with PyPy3). We need at the very least better support for debugging OpenBLAS issues, and better documentation on how to build SciPy with it. An option is to use BLIS for a BLAS interface (see [numpy gh-7372](#)).
2. Support for newer LAPACK features. In SciPy 1.2.0 we increased the minimum supported version of LAPACK to 3.4.0. Now that we dropped Python 2.7, we can increase that version further (MKL + Python 2.7 was the blocker for >3.4.0 previously) and start adding support for new features in LAPACK.

misc

`scipy.misc` will be removed as a public module. Most functions in it have been moved to another submodule or deprecated. The few that are left:

- `info, who` : these are NumPy functions
- `derivative, central_diff_weight` : remove, possibly replacing them with more extensive functionality for numerical differentiation.

ndimage

Underlying `ndimage` is a powerful interpolation engine. Users come with an expectation of one of two models: a pixel model with $(1, 1)$ elements having centers $(0.5, 0.5)$, or a data point model, where values are defined at points on a grid. Over time, we've become convinced that the data point model is better defined and easier to implement, but this should be clearly communicated in the documentation.

More importantly, still, SciPy implements one *variant* of this data point model, where datapoints at any two extremes of an axis share a spatial location under *periodic wrapping* mode. E.g., in a 1D array, you would have `x[0]` and `x[-1]` co-located. A very common use-case, however, is for signals to be periodic, with equal spacing between the first and last element along an axis (instead of zero spacing). Wrapping modes for this use-case were added in [gh-8537](#), next the interpolation routines should be updated to use those modes. This should address several issues, including [gh-1323](#), [gh-1903](#), [gh-2045](#) and [gh-2640](#).

The morphology interface needs to be standardized:

- binary dilation/erosion/opening/closing take a "structure" argument, whereas their grey equivalent take size (has to be a tuple, not a scalar), footprint, or structure.
- a scalar should be acceptable for size, equivalent to providing that same value for each axis.
- for binary dilation/erosion/opening/closing, the structuring element is optional, whereas it's mandatory for grey. Grey morphology operations should get the same default.
- other filters should also take that default value where possible.

odr

This module is in reasonable shape, although it could use a bit more maintenance. No major plans or wishes here.

optimize

Overall this module is in good shape. Two good global optimizers were added in 1.2.0; large-scale optimizers is still a gap that could be filled. Other things that are needed:

- Many ideas for additional functionality (e.g. integer constraints, sparse matrix support, performance improvements) in `linprog`, see [gh-9269](#).
- Add functionality to the benchmark suite to compare results more easily (e.g. with summary plots).
- deprecate the `fmin_*` functions in the documentation, `minimize` is preferred.
- `scipy.optimize` has an extensive set of benchmarks for accuracy and speed of the global optimizers. That has allowed adding new optimizers (`shgo` and `dual_annealing`) with significantly better performance than the existing ones. The `optimize` benchmark system itself is slow and hard to use however; we need to make it faster and make it easier to compare performance of optimizers via plotting performance profiles.

signal

Convolution and correlation: (Relevant functions are `convolve`, `correlate`, `fftconvolve`, `convolve2d`, `correlate2d`, and `sepfir2d`.) Eliminate the overlap with `ndimage` (and elsewhere). From `numpy`, `scipy.signal` and `scipy.ndimage` (and anywhere else we find them), pick the “best of class” for 1-D, 2-D and n-d convolution and correlation, put the implementation somewhere, and use that consistently throughout SciPy.

B-splines: (Relevant functions are `bspline`, `cubic`, `quadratic`, `gauss_spline`, `cspline1d`, `qspline1d`, `cspline2d`, `qspline2d`, `cspline1d_eval`, and `spline_filter`.) Move the good stuff to `interpolate` (with appropriate API changes to match how things are done in `interpolate`), and eliminate any duplication.

Filter design: merge `firwin` and `firwin2` so `firwin2` can be removed.

Continuous-Time Linear Systems: remove `lsim2`, `impulse2`, `step2`. The `lsim`, `impulse` and `step` functions now “just work” for any input system. Further improve the performance of `ltisys` (fewer internal transformations between different representations). Fill gaps in `lti` system conversion functions.

Second Order Sections: Make SOS filtering equally capable as existing methods. This includes `ltisys` objects, an *lfilter* equivalent, and numerically stable conversions to and from other filter representations. SOS filters could be considered as the default filtering method for `ltisys` objects, for their numerical stability.

Wavelets: what’s there now doesn’t make much sense. Continuous wavelets only at the moment - decide whether to completely rewrite or remove them. Discrete wavelet transforms are out of scope (PyWavelets does a good job for those).

sparse

The sparse matrix formats are mostly feature-complete, however the main issue is that they act like `numpy.matrix` (which will be deprecated in NumPy at some point). What we want is sparse arrays, that act like `numpy.ndarray`. This is being worked on in <https://github.com/pydata/sparse>, which is quite far along. The tentative plan is:

- Start depending on `pydata/sparse` once it’s feature-complete enough (it still needs a CSC/CSR equivalent) and okay performance-wise.
- Add support for `pydata/sparse` to `scipy.sparse.linalg` (and perhaps to `scipy.sparse.csgraph` after that).
- Indicate in the documentation that for new code users should prefer `pydata/sparse` over sparse matrices.

- When NumPy deprecates `numpy.matrix`, vendor that or maintain it as a stand-alone package.

Regarding the different sparse matrix formats: there are a lot of them. These should be kept, but improvements/optimizations should go into CSR/CSC, which are the preferred formats. LIL may be the exception, it's inherently inefficient. It could be dropped if DOK is extended to support all the operations LIL currently provides.

sparse.csgraph

This module is in good shape.

sparse.linalg

Arpack is in good shape.

isolve:

- callback keyword is inconsistent
- tol keyword is broken, should be relative tol
- Fortran code not re-entrant (but we don't solve, maybe re-use from PyKrilov)

dsolve:

- add sparse Cholesky or incomplete Cholesky
- look at CHOLMOD

Ideas for new features:

- Wrappers for PROPACK for faster sparse SVD computation.

spatial

QHull wrappers are in good shape, as is `cKDTree`.

Needed:

- `KDTree` will be removed, and `cKDTree` will be renamed to `KDTree` in a backwards-compatible way.
- `distance_wrap.c` needs to be cleaned up (maybe rewrite in Cython).

special

Though there are still a lot of functions that need improvements in precision, probably the only show-stoppers are hypergeometric functions, parabolic cylinder functions, and spheroidal wave functions. Three possible ways to handle this:

1. Get good double-precision implementations. This is doable for parabolic cylinder functions (in progress). I think it's possible for hypergeometric functions, though maybe not in time. For spheroidal wavefunctions this is not possible with current theory.
2. Port Boost's arbitrary precision library and use it under the hood to get double precision accuracy. This might be necessary as a stopgap measure for hypergeometric functions; the idea of using arbitrary precision has been suggested before by @nmayorov and in [gh-5349](#). Likely necessary for spheroidal wave functions, this could be reused: <https://github.com/radelman/scattering>.
3. Add clear warnings to the documentation about the limits of the existing implementations.

stats

The `scipy.stats` subpackage aims to provide fundamental statistical methods as might be covered in standard statistics texts such as Johnson’s “Miller & Freund’s Probability and Statistics for Engineers”, Sokal & Rohlf’s “Biometry”, or Zar’s “Biostatistical Analysis”. It does not seek to duplicate the advanced functionality of downstream packages (e.g. StatsModels, LinearModels, PyMC3); instead, it can provide a solid foundation on which they can build. (Note that these are rough guidelines, not strict rules. “Advanced” is an ill-defined and subjective term, and “advanced” methods may also be included in SciPy, especially if no other widely used and well-supported package covers the topic. Also note that *some* duplication with downstream projects is inevitable and not necessarily a bad thing.)

The following improvements will help SciPy better serve this role.

- Add fundamental and widely used hypothesis tests:
 - Alexander-Govern test
 - Somers’ D
 - Kendall’s tau-c
 - Page’s L-test
 - Tukey-Kramer test
 - Dunnett’s test
 - the various types of analysis of variance (ANOVA):
 - * two-way ANOVA (single replicate, uniform number of replicates, variable number of replicates)
 - * multiway ANOVA (i.e. generalize two-way ANOVA)
 - * nested ANOVA
 - * analysis of covariance (ANCOVA)
- Where appropriate, include confidence intervals for the statistic in the results of any statistical test.
- Add additional tools for meta-analysis; currently we have just `combine_pvalues`.
- Enhance the `fit` method of the continuous probability distributions:
 - Expand the options for fitting to include:
 - * method of moments
 - * maximal product spacings
 - * method of L-moments / probability weighted moments
 - Include measures of goodness-of-fit in the results
 - Handle censored data
- Implement additional widely used continuous and discrete probability distributions:
 - noncentral hypergeometric distribution (both Fisher’s and Wallenius’)
 - negative hypergeometric distribution
 - multivariate hypergeometric distribution
 - multivariate t distribution
 - mixture distributions

- Improve the core calculations provided by SciPy's probability distributions so they can robustly handle wide ranges of parameter values. Specifically, replace many of the PDF and CDF methods from the Fortran library CDFLIB used in `scipy.special` with better code, perhaps ported from the Boost C++ library.

In addition, we should:

- Continue work on making the function signatures of `stats` and `stats.mstats` more consistent, and add tests to ensure that that remains the case.
- Return `Bunch` objects from functions that now return many values, and for functions for which extra return values are desired (see [gh-3665](#)).
- Improve statistical tests (p-value calculation, alternative hypothesis), for example implement an exact two-sided KS test (see [gh-8341](#)) or a one-sided Wilcoxon test (see [gh-9046](#)).
- Address the various issues regarding `stats.mannwhitneyu`, and pick up the stalled PR in [gh-4933](#).

5.6 Toolchain Roadmap

The use of the SciPy library requires (or optionally depends upon) several other libraries in order to operate, the main dependencies being Python and NumPy. It requires a larger collection of libraries and tools in order to build the library or to build the documentation.

Of course, the tooling and libraries are themselves not static. This document aims to provide a guide as to how SciPy's use of these dynamic dependencies will proceed over time.

SciPy aims to be compatible with a number of releases of its dependent libraries and tools. Forcing the user base to other components for upgrade for every release would greatly diminish the value of SciPy. However, maintaining backwards compatibility with very old tooling/libraries imposes limitations on which newer functionalities and capabilities can be incorporated. SciPy takes a somewhat conservative approach, maintaining compatibility with several major releases of Python and NumPy on the major platforms. (That may in and of itself impose further restrictions. See the C Compilers section for an example.)

- First and foremost, SciPy is a Python project, hence it requires a Python environment.
- BLAS and LAPACK numerical libraries need to be installed.
- Compilers for C, C++, Cython, and Fortran code are needed.
- The Python environment needs the NumPy package to be installed.
- Testing requires the `pytest` Python package.
- Building the documentation requires the `matplotlib`, `Sphinx` packages, as well as a LaTeX installation.

The tooling used to build CPython has some implications for the tooling used in building SciPy. It also has implications for the examples used in the documentation (e.g., docstrings for functions), as these examples can only use functionality present in all supported configurations.

5.6.1 Building SciPy

Python Versions

SciPy is compatible with several versions of Python. When dropping support for older Python versions, SciPy takes guidance from NEP 29¹⁰. Python 2.7 support was dropped for SciPy releases numbered 1.3 and above but is still available in release 1.2.x, which is a long-term support release^{1, 2}.

Date	Pythons supported
2018	Py2.7, Py3.4+ (SciPy 1.2.x is the last release to support Python 2.7)
2019	Py3.5+ (but Py2.7-specific code not removed)
2020	Py3.6+ (removal of Py2.7-specific code permitted)

NumPy

SciPy depends on NumPy but releases of SciPy are not tied to releases of NumPy. SciPy attempts to be compatible with at least the 4 previous releases of NumPy. In particular, SciPy cannot rely on features of just the latest NumPy, but needs to be written using what is common in all of those 4 releases.^{1, 3}

The table shows the NumPy versions suitable for each major Python version (for SciPy 1.3.x unless otherwise stated).

Python	Minimum NumPy version	Maximum NumPy version
2.7 (SciPy 1.2)	1.8.2	1.16.x
3.5 (SciPy 1.4)	1.13.3	1.18.x
3.6 (SciPy 1.5)	1.14.5	1.19.x
3.7	1.16.5	>= 1.20.x
3.8	1.17.3	>= 1.20.x
3.9	1.19.3	>= 1.20.x

C Compilers

SciPy is compatible with most modern C compilers (in particular `clang`). However, CPython on Windows is built with specific versions of the Microsoft Visual C++ compiler^{7, 8, 9}, as is the corresponding build of SciPy. This has implications for the C language standards that can be supported⁶. Starting from MS Visual Studio 16.8, C11/C17 is supported¹¹ (without the C11 optional features¹² like atomics, threading, VLAs & complex types), though Windows builds of CPython have not yet upgraded this far.

CPython	MS Visual C++	C Standard
2.7, 3.0, 3.1, 3.2	9.0	C90
3.3, 3.4	10.0	C90 & some of C99
3.5, 3.6	14.0	C90 & most of C99
3.7, 3.8, 3.9	15.7	C90 & most of C99

¹⁰ https://numpy.org/neps/nep-0029-deprecation_policy.html

¹ <https://docs.scipy.org/doc/scipy/reference/release.1.2.0.html>

² <https://python3statement.org>

³ <https://docs.scipy.org/doc/numpy/release.html>

⁷ <https://pythondev.readthedocs.io/windows.html#python-and-visual-studio-version-matrix>

⁸ https://en.wikipedia.org/wiki/Microsoft_Visual_C%2B%2B#Internal_version_numbering

⁹ <https://wiki.python.org/moin/WindowsCompilers>

⁶ <https://blogs.msdn.microsoft.com/vcblog/2013/07/19/c99-library-support-in-visual-studio-2013/>

¹¹ <https://devblogs.microsoft.com/cppblog/c11-and-c17-standard-support-arriving-in-msvc/>

¹² https://en.wikipedia.org/wiki/C11_%28C_standard_revision%29#Optional_features

C and C++ Language Standards

C and C++ language standards for SciPy are generally guidelines rather than official decisions. This is particularly true of attempting to predict adoption timelines for newer standards.

Date	C Standard
<= 2018	C90
2019	C90 for old code, may consider C99 for new
2020	C99
2020	C++11
2021	C++14, C++17
?	C11, C17
?	C++20

The use of MS Visual Studio 9.0 (which doesn't have support C99) to build Python2.7 has meant that C code in SciPy has had to conform to the earlier C90 standard for the language and standard library. With the dropping of Python 2.7 for SciPy 1.3.x, the C90 restriction is no longer imposed by compilers. For GCC version < 5, an explicit `-std=c99` may have to be added by the user if C99 features are used in SciPy code. *Note: even though C99 has been a standard for 20 years, experience has shown that not all features are supported equally well across all platforms.*

C17 (occasionally called C18) is a bug fix for C11, so C11 may be skipped entirely. Microsoft has taken very long to achieve conformance to C99/C11/C17, but as soon as CPython is built with Visual Studio 16.8 or newer (see above), it will be possible to use C17 (though optional C11 features like atomics & threading are so far not supported in MSVC).

In practice, the C++ feature set that can be used is limited by the availability in the MS VisualStudio versions that SciPy needs to support. Since dropping support for Python 2.7, C++11 can be used universally, and since dropping support for Python 3.6, the same is true also for C++14 & C++17. This is because the oldest still required version of MS Visual Studio (Visual Studio 15.7 <-> MSVC 19.14, see⁸) has effectively full support, see⁴. Compiler support for C++20 is still under heavy development.

Note: Developer Note: Some C99 features would be useful for scientific programming, in particular better support of IEEE 754⁵. SciPy has a small include file `scipy/_lib/_c99compat.h` which provides access to a few functions. Use in conjunction with `<numpy/npymath.h>`.

Feature	Workaround
<code>isnan()</code> , <code>isinf()</code> , <code>isfinite()</code>	Use <code>sc_isnan()</code> , <code>sc_isinf()</code> , <code>sc_isfinite()</code>
NAN	Use <code>NPY_NAN</code> (it is <i>almost</i> equivalent)
inline functions	Make static functions and place in an include <code>.h</code> file
mid-block variable declarations	Declare variables at the top of the block

⁴ https://en.cppreference.com/w/cpp/compiler_support

⁵ https://en.wikipedia.org/wiki/IEEE_754-1985

Fortran Compilers

Generally, any well-maintained compiler is likely suitable and can be used to build SciPy.

Tool	Version
gfortran	>= 4.8.0
ifort	A recent version
flang	A recent version

Cython Compiler

SciPy always requires a recent Cython compiler.

Tool	Tool Version	SciPy version
Cython	>= 0.29.13	1.4.1
Cython	>= 0.29.18	1.5.0

Other Libraries

Any library conforming to the BLAS/LAPACK interface may be used. OpenBLAS, ATLAS, MKL, BLIS, and reference Netlib libraries are known to work.

Library	Minimum version
LAPACK	3.4.1
BLAS	A recent version of OpenBLAS, MKL or ATLAS. The Accelerate BLAS is no longer supported.

There are some additional optional dependencies.

Library	Version	URL
mpmath	Recent	http://mpmath.org/
scikit-umfpack	Recent	https://pypi.org/project/scikit-umfpack/

Moreover, Scipy supports interaction with other libraries. The test suite has additional compatibility tests that are run when these are installed:

Tool	Version	URL
pydata/sparse	Recent	https://github.com/pydata/sparse/

5.6.2 Testing and Benchmarking

Testing and benchmarking require recent versions of:

Tool	Version	URL
pytest	Recent	https://docs.pytest.org/en/latest/
asv (airspeed velocity)	Recent	https://asv.readthedocs.io/

5.6.3 Building the Documentation

Tool	Version
Sphinx	Whatever recent versions work. ≥ 2.0 .
numpydoc	Whatever recent versions work. $\geq 0.8.0$.
matplotlib	Generally suggest ≥ 2.0 .
LaTeX	A recent distribution, such as TeX Live 2016.

[The `numpydoc` package is also used, but that is currently packaged in `doc/sphinxext`.]

Note: Developer Note: The versions of `numpy` and `matplotlib` required have implications for the examples in Python docstrings. Examples must be able to be executed both in the environment used to build the documentation, as well as with any supported versions of `numpy/matplotlib` that a user may use with this release of SciPy.

5.6.4 Packaging

A Recent version of:

Tool	Version	URL
setuptools	Recent	https://pypi.org/project/setuptools/
wheel	Recent	https://pythonwheels.com
multibuild	Recent	https://github.com/matthew-brett/multibuild

Making a SciPy release and *Distributing* contain information on making and distributing a SciPy release.

5.6.5 References

For a more detailed look at how the SciPy project works:

5.7 SciPy Core Developer Guide

5.7.1 Decision making process

SciPy has a formal governance model, documented in *SciPy Project Governance*. The section below documents in an informal way what happens in practice for decision making about code and commit rights. The formal governance model is leading, the below is only provided for context.

Code

Any significant decisions on adding (or not adding) new features, breaking backwards compatibility or making other significant changes to the codebase should be made on the scipy-dev mailing list after a discussion (preferably with full consensus).

Any non-trivial change (where trivial means a typo, or a one-liner maintenance commit) has to go in through a pull request (PR). It has to be reviewed by another developer. In case review doesn't happen quickly enough and it is important that the PR is merged quickly, the submitter of the PR should send a message to mailing list saying he/she intends to merge that PR without review at time X for reason Y unless someone reviews it before then.

Changes and new additions should be tested. Untested code is broken code.

Commit rights

Who gets commit rights is decided by the SciPy Steering Council; changes in commit rights will then be announced on the scipy-dev mailing list.

5.8 Deciding on new features

The general decision rule to accept a proposed new feature has so far been conditional on:

1. The method is applicable in many fields and “generally agreed” to be useful,
2. It fits the topic of the submodule, and does not require extensive support frameworks to operate,
3. The implementation looks sound and unlikely to need much tweaking in the future (e.g., limited expected maintenance burden),
4. Someone wants to contribute it, and
5. Someone wants to review it.

The last criterion is often a sticking point for proposed features. Code cannot be merged until it has been thoroughly reviewed, and there is always a backlog of maintenance tasks that compete for reviewers' time. Ideally, contributors should line up a reviewer with suitable domain expertise before beginning work.

Although it's difficult to give hard rules on what “generally useful and generally agreed to work” means, it may help to weigh the following against each other:

- Is the method used/useful in different domains in practice? How much domain-specific background knowledge is needed to use it properly?
- Consider the code already in the module. Is what you are adding an omission? Does it solve a problem that you'd expect the module be able to solve? Does it supplement an existing feature in a significant way?
- Consider the equivalence class of similar methods / features usually expected. Among them, what would in principle be the minimal set so that there's not a glaring omission in the offered features remaining? How much stuff would that be? Does including a representative one of them cover most use cases? Would it in principle sound reasonable to include everything from the minimal set in the module?
- Is what you are adding something that is well understood in the literature? If not, how sure are you that it will turn out well? Does the method perform well compared to other similar ones?
- Note that the twice-a-year release cycle and backward-compatibility policy makes correcting things later on more difficult.

The scopes of the submodules also vary, so it's probably best to consider each as if it's a separate project - “numerical evaluation of special functions” is relatively well-defined, but “commonly needed optimization algorithms” less so.

5.8.1 Development on GitHub

SciPy development largely takes place on GitHub; this section describes the expected way of working for issues, pull requests and managing the main `scipy` repository.

Labels and Milestones

Each issue and pull request normally gets at least two labels: one for the topic or component (`scipy.stats`, `Documentation`, etc.), and one for the nature of the issue or pull request (`enhancement`, `maintenance`, `defect`, etc.). Other labels that may be added depending on the situation:

- `easy-fix`: for issues suitable to be tackled by new contributors.
- `needs-work`: for pull requests that have review comments that haven't been addressed.
- `needs-decision`: for issues or pull requests that need a decision.
- `needs-champion`: for pull requests that were not finished by the original author, but are worth resurrecting.
- `backport-candidate`: bugfixes that should be considered for backporting by the release manager.

A milestone is created for each version number for which a release is planned. Issues that need to be addressed and pull requests that need to be merged for a particular release should be set to the corresponding milestone. After a pull request is merged, its milestone (and that of the issue it closes) should be set to the next upcoming release - this makes it easy to get an overview of changes and to add a complete list of those to the release notes.

Pull request review workflow

When reviewing pull requests, please make use of pull request workflow features, see [pull-request-workflow-features](#).

Dealing with pull requests

- When merging contributions, a committer is responsible for ensuring that those meet the requirements outlined in [Contributing to SciPy](#). Also check that new features and backwards compatibility breaks were discussed on the `scipy-dev` mailing list.
- New code goes in via a pull request (PR).
- Merge new code with the green button. In case of merge conflicts, ask the PR submitter to rebase (this may require providing some git instructions).
- Backports and trivial additions to finish a PR (really trivial, like a typo or PEP8 fix) can be pushed directly.
- For PRs that add new features or are in some way complex, wait at least a day or two before merging it. That way, others get a chance to comment before the code goes in.
- Squashing commits or cleaning up commit messages of a PR that you consider too messy is OK. Make sure though to retain the original author name when doing this.
- Make sure that the labels and milestone on a merged PR are set correctly.
- When you want to reject a PR: if it's very obvious you can just close it and explain why, if not obvious then it's a good idea to first explain why you think the PR is not suitable for inclusion in SciPy and then let a second committer comment or close.

Backporting

All pull requests (whether they contain enhancements, bug fixes or something else), should be made against master. Only bug fixes are candidates for backporting to a maintenance branch. The backport strategy for SciPy is to (a) only backport fixes that are important, and (b) to only backport when it's reasonably sure that a new bugfix release on the relevant maintenance branch will be made. Typically, the developer who merges an important bugfix adds the `backport-candidate` label and pings the release manager, who decides on whether and when the backport is done. After the backport is completed, the `backport-candidate` label has to be removed again.

A good strategy for a backport pull request is to combine several master branch pull requests, to reduce the burden on continuous integration tests and to reduce the merge commit cluttering of maintenance branch history. It is generally best to have a single commit for each of the master branch pull requests represented in the backport pull request. This way, history is clear and can be reverted in a straightforward manner if needed.

Release notes

When a PR gets merged, consider if the changes need to be mentioned in the release notes. What needs mentioning: new features, backwards incompatible changes, deprecations, and “other changes” (anything else noteworthy enough, see older release notes for the kinds of things worth mentioning).

Release note entries are maintained on the wiki, (e.g. <https://github.com/scipy/scipy/wiki/Release-note-entries-for-SciPy-1.2.0>). The release manager will gather content from there and integrate it into the html docs. We use this mechanism to avoid merge conflicts that would happen if every PR touched the same file under `doc/release/` directly.

Changes can be monitored ([Atom feed](#)) and pulled (the wiki is a git repo: <https://github.com/scipy/scipy.wiki.git>).

Other

PR status page: When new commits get added to a pull request, GitHub doesn't send out any notifications. The `needs-work` label may not be justified anymore though. [This page](#) gives an overview of PRs that were updated, need review, need a decision, etc.

Cross-referencing: Cross-referencing issues and pull requests on GitHub is often useful. GitHub allows doing that by using `gh-xxxx` or `#xxxx` with `xxxx` the issue/PR number. The `gh-xxxx` format is strongly preferred, because it's clear that that is a GitHub link. Older issues contain `#xxxx` which is about Trac (what we used pre-GitHub) tickets.

PR naming convention: Pull requests, issues and commit messages usually start with a three-letter abbreviation like `ENH :` or `BUG :`. This is useful to quickly see what the nature of the commit/PR/issue is. For the full list of abbreviations, see [writing the commit message](#).

5.8.2 Licensing

SciPy is distributed under the [modified \(3-clause\) BSD license](#). All code, documentation and other files added to SciPy by contributors is licensed under this license, unless another license is explicitly specified in the source code. Contributors keep the copyright for code they wrote and submit for inclusion to SciPy.

Other licenses that are compatible with the modified BSD license that SciPy uses are 2-clause BSD, MIT and PSF. Incompatible licenses are GPL, Apache and custom licenses that require attribution/citation or prohibit use for commercial purposes.

PRs are often submitted with content copied or derived from unlicensed code. These contributions cannot be accepted for inclusion in SciPy unless the original code author is willing to (re)license his/her code under the modified BSD (or

compatible) license. If the original author agrees, add a comment saying so to the source files and forward the relevant communication to the `scipy-dev` mailing list.

Another common occurrence is for code to be translated or derived from code in R, Octave (both GPL-licensed) or a commercial application. Such code also cannot be included in SciPy. Simply implementing functionality with the same API as found in R/Octave/... is fine though, as long as the author doesn't look at the original incompatibly-licensed source code.

5.8.3 Version numbering

SciPy version numbering complies to [PEP 440](#). Released final versions, which are the only versions appearing on PyPI, are numbered `MAJOR.MINOR.MICRO` where:

- `MAJOR` is an integer indicating the major version. It changes very rarely; a change in `MAJOR` indicates large (possibly backwards-incompatible) changes.
- `MINOR` is an integer indicating the minor version. Minor versions are typically released twice a year and can contain new features, deprecations and bug-fixes.
- `MICRO` is an integer indicating a bug-fix version. Bug-fix versions are released when needed, typically one or two per minor version. They cannot contain new features or deprecations.

Released alpha, beta and rc (release candidate) versions are numbered like final versions but with postfixes `a#`, `b#` and `rc#` respectively, with `#` an integer. Development versions are postfixed with `.dev0+<git-commit-hash>`.

Examples of valid SciPy version strings are:

```
0.16.0
0.15.1
0.14.0a1
0.14.0b2
0.14.0rc1
0.17.0.dev0+ac53f09
```

An installed SciPy version contains these version identifiers:

```
scipy.__version__           # complete version string, including git commit_  
↳hash for dev versions  
scipy.version.short_version # string, only major.minor.micro  
scipy.version.version      # string, same as scipy.__version__  
scipy.version.full_version # string, same as scipy.__version__  
scipy.version.release      # bool, development or (alpha/beta/rc/final)_  
↳released version  
scipy.version.git_revision # string, git commit hash from which scipy was_  
↳built
```

5.8.4 Deprecations

There are various reasons for wanting to remove existing functionality: it's buggy, the API isn't understandable, it's superseded by functionality with better performance, it needs to be moved to another SciPy submodule, etc.

In general it's not a good idea to remove something without warning users about that removal first. Therefore this is what should be done before removing something from the public API:

1. Propose to deprecate the functionality on the `scipy-dev` mailing list and get agreement that that's OK.
2. Add a `DeprecationWarning` for it, which states that the functionality was deprecated, and in which release. For Cython APIs, see [Deprecating public Cython APIs](#) for the practical steps.
3. Mention the deprecation in the release notes for that release.
4. Wait till at least 6 months after the release date of the release that introduced the `DeprecationWarning` before removing the functionality.
5. Mention the removal of the functionality in the release notes.

The 6 months waiting period in practice usually means waiting two releases. When introducing the warning, also ensure that those warnings are filtered out when running the test suite so they don't pollute the output.

It's possible that there is reason to want to ignore this deprecation policy for a particular deprecation; this can always be discussed on the `scipy-dev` mailing list.

5.8.5 Distributing

Distributing Python packages is nontrivial - especially for a package with complex build requirements like SciPy - and subject to change. For an up-to-date overview of recommended tools and techniques, see the [Python Packaging User Guide](#). This document discusses some of the main issues and considerations for SciPy.

Dependencies

Dependencies are things that a user has to install in order to use (or build/test) a package. They usually cause trouble, especially if they're not optional. SciPy tries to keep its dependencies to a minimum; currently they are:

Unconditional run-time dependencies:

- [Numpy](#)

Conditional run-time dependencies:

- `nose` (to run the test suite)
- `asv` (to run the benchmarks)
- `matplotlib` (for some functions that can produce plots)
- `Pillow` (for image loading/saving)
- `scikits.umfpack` (optionally used in `sparse.linalg`)
- `mpmath` (for more extended tests in `special`)
- `pydata/sparse` (compatibility support in `scipy.sparse`)

Unconditional build-time dependencies:

- [Numpy](#)
- A BLAS and LAPACK implementation (reference BLAS/LAPACK, ATLAS, OpenBLAS, MKL, Accelerate are all known to work)

- (for development versions) [Cython](#)

Conditional build-time dependencies:

- [setuptools](#)
- [wheel](#) (`python setup.py bdist_wheel`)
- [Sphinx](#) (docs)
- [matplotlib](#) (docs)
- [LaTeX](#) (pdf docs)
- [Pillow](#) (docs)

Furthermore of course one needs C, C++ and Fortran compilers to build SciPy, but those we don't consider to be dependencies and are therefore not discussed here. For details, see <https://scipy.github.io/devdocs/building/>.

When a package provides useful functionality and it's proposed as a new dependency, consider also if it makes sense to vendor (i.e. ship a copy of it with `scipy`) the package instead. For example, `six` and `decorator` are vendored in `scipy._lib`.

The only dependency that is reported to `pip` is [Numpy](#), see `install_requires` in SciPy's main `setup.py`. The other dependencies aren't needed for SciPy to function correctly, and the one unconditional build dependency that `pip` knows how to install ([Cython](#)) we prefer to treat like a compiler rather than a Python package that `pip` is allowed to upgrade.

Issues with dependency handling

There are some serious issues with how Python packaging tools handle dependencies reported by projects. Because SciPy gets regular bug reports about this, we go in a bit of detail here.

SciPy only reports its dependency on NumPy via `install_requires` if NumPy isn't installed at all on a system. This will only change when there are either 32-bit and 64-bit Windows wheels for NumPy on PyPI or when `pip upgrade` becomes available (with sane behavior, unlike `pip install -U`, see [this PR](#)). For more details, see [this summary](#).

The situation with `setup_requires` is even worse; `pip` doesn't handle that keyword at all, while `setuptools` has issues ([here's a current one](#)) and invokes `easy_install` which comes with its own set of problems (note that SciPy doesn't support `easy_install` at all anymore; issues specific to it will be closed as "wontfix").

Supported Python and NumPy versions

The [Python](#) versions that SciPy supports are listed in the list of PyPI classifiers in `setup.py`, and mentioned in the release notes for each release. All newly released Python versions will be supported as soon as possible. The general policy on dropping support for a Python version is that (a) usage of that version has to be quite low (say <5% of users) and (b) the version isn't included in an active long-term support release of one of the main Linux distributions anymore. SciPy typically follows NumPy, which has a similar policy. The final decision on dropping support is always taken on the `scipy-dev` mailing list.

The lowest supported [Numpy](#) version for a SciPy version is mentioned in the release notes and is encoded in `scipy/__init__.py` and the `install_requires` field of `setup.py`. Typically the latest SciPy release supports 3 or 4 minor versions of NumPy. That may become more if the frequency of NumPy releases increases (it's about 1x/year at the time of writing). Support for a particular NumPy version is typically dropped if (a) that NumPy version is several years old, and (b) the maintenance cost of keeping support is starting to outweigh the benefits. The final decision on dropping support is always taken on the `scipy-dev` mailing list.

Supported versions of optional dependencies and compilers is less clearly documented, and also isn't tested well or at all by SciPy's Continuous Integration setup. Issues regarding this are dealt with as they come up in the issue tracker or mailing list.

Building binary installers

Note: This section is only about building SciPy binary installers to *distribute*. For info on building SciPy on the same machine as where it will be used, see [this scipy.org](https://www.scipy.org) page.

There are a number of things to take into consideration when building binaries and distributing them on PyPI or elsewhere.

General

- A binary is specific for a single Python version (because different Python versions aren't ABI-compatible, at least up to Python 3.4).
- Build against the lowest NumPy version that you need to support, then it will work for all NumPy versions with the same major version number (NumPy does maintain backwards ABI compatibility).

Windows

- The currently most easily available toolchain for building Python.org compatible binaries for SciPy is installing MSVC (see <https://wiki.python.org/moin/WindowsCompilers>) and mingw64-gfortran. Support for this configuration requires `numpy.distutils` from NumPy \geq 1.14.dev and a `gcc/gfortran`-compiled static `openblas.a`. This configuration is currently used in the Appveyor configuration for <https://github.com/MacPython/scipy-wheels>
- For 64-bit Windows installers built with a free toolchain, use the method documented at <https://github.com/numpy/numpy/wiki/Mingw-static-toolchain>. That method will likely be used for SciPy itself once it's clear that the maintenance of that toolchain is sustainable long-term. See the [MingwPy](#) project and [this thread](#) for details.
- The other way to produce 64-bit Windows installers is with `icc`, `ifort` plus MKL (or MSVC instead of `icc`). For Intel toolchain instructions see [this article](#) and for (partial) MSVC instructions see [this wiki page](#).
- Older SciPy releases contained a `.exe` “superpack” installer. Those contain 3 complete builds (no SSE, SSE2, SSE3), and were built with <https://github.com/numpy/numpy-vendor>. That build setup is known to not work well anymore and is no longer supported. It used `g77` instead of `gfortran`, due to complex DLL distribution issues (see [gh-2829](#)). Because the toolchain is no longer supported, `g77` support isn't needed anymore and SciPy can now include Fortran 90/95 code.

OS X

- To produce OS X wheels that work with various Python versions (from python.org, Homebrew, MacPython), use the build method provided by <https://github.com/MacPython/scipy-wheels>.
- DMG installers for the Python from python.org on OS X can still be produced by `tools/scipy-macosx-installer/`. SciPy doesn't distribute those installers anymore though, now that there are binary wheels on PyPi.

Linux

- PyPi-compatible Linux wheels can be produced via the [manylinux](#) project. The corresponding build setup for TravisCI for SciPy is set up in <https://github.com/MacPython/scipy-wheels>.

Other Linux build-setups result to PyPi incompatible wheels, which would need to be distributed via custom channels, e.g. in a [Wheelhouse](#), see at the [wheel](#) and [Wheelhouse](#) docs.

5.8.6 Making a SciPy release

At the highest level, this is what the release manager does to release a new SciPy version:

1. Propose a release schedule on the scipy-dev mailing list.
2. Create the maintenance branch for the release.
3. Tag the release.
4. Build all release artifacts (sources, installers, docs).
5. Upload the release artifacts.
6. Announce the release.
7. Port relevant changes to release notes and build scripts to master.

In this guide we attempt to describe in detail how to perform each of the above steps. In addition to those steps, which have to be performed by the release manager, here are descriptions of release-related activities and conventions of interest:

- *Backporting*
- *Labels and Milestones*
- *Version numbering*
- *Supported Python and NumPy versions*
- *Deprecations*

Proposing a release schedule

A typical release cycle looks like:

- Create the maintenance branch
- Release a beta version
- Release a “release candidate” (RC)
- If needed, release one or more new RCs
- Release the final version once there are no issues with the last release candidate

There’s usually at least one week between each of the above steps. Experience shows that a cycle takes between 4 and 8 weeks for a new minor version. Bug-fix versions don’t need a beta or RC, and can be done much quicker.

Ideally the final release is identical to the last RC, however there may be minor difference - it’s up to the release manager to judge the risk of that. Typically, if compiled code or complex pure Python code changes then a new RC is needed, while a simple bug-fix that’s backported from master doesn’t require a new RC.

To propose a schedule, send a list with estimated dates for branching and beta/rc/final releases to scipy-dev. In the same email, ask everyone to check if there are important issues/PRs that need to be included and aren’t tagged with the Milestone for the release or the “backport-candidate” label.

Creating the maintenance branch

Before branching, ensure that the release notes are updated as far as possible. Include the output of `tools/gh_lists.py` and `tools/authors.py` in the release notes.

Maintenance branches are named `maintenance/<major>.<minor>.x` (e.g. `0.19.x`). To create one, simply push a branch with the correct name to the `scipy` repo. Immediately after, push a commit where you increment the version number on the master branch and add release notes for that new version. Send an email to `scipy-dev` to let people know that you've done this.

Tagging a release

First ensure that you have set up GPG correctly. See <https://github.com/scipy/scipy/issues/4919> for a discussion of signing release tags, and <https://keyring.debian.org/creating-key.html> for instructions on creating a GPG key if you do not have one. Note that on some platforms it may be more suitable to use `gpg2` instead of `gpg` so that passwords may be stored by `gpg-agent` as discussed in <https://github.com/scipy/scipy/issues/10189>.

To make your key more readily identifiable as you, consider sending your key to public key servers, with a command such as:

```
gpg --send-keys <yourkeyid>
```

Check that all relevant commits are in the branch. In particular, check issues and PRs under the Milestone for the release (<https://github.com/scipy/scipy/milestones>), PRs labeled “backport-candidate”, and that the release notes are up-to-date and included in the html docs.

Then edit `setup.py` to get the correct version number (set `ISRELEASED = True`) and commit it with a message like `REL: set version to <version-number>`. Don't push this commit to the SciPy repo yet.

Finally tag the release locally with `git tag -s <v1.x.y>` (the `-s` ensures the tag is signed). If `gpg2` is preferred, then `git config --global gpg.program gpg2` may be appropriate. Continue with building release artifacts (next section). Only push the release commit to the `scipy` repo once you have built the `sdist`s and docs successfully. Then continue with building wheels. Only push the release tag to the repo once all wheels have been built successfully on TravisCI and Appveyor (if it fails, you have to move the tag otherwise - which is bad practice). Finally, after pushing the tag, also push a second commit which increments the version number and sets `ISRELEASED` to `False` again. This also applies with new release candidates, and for removing the `rc` affix when switching from release candidate to release proper.

Building release artifacts

Here is a complete list of artifacts created for a release:

- source archives (`.tar.gz`, `.zip` and `.tar.xz` for GitHub Releases, only `.tar.gz` is uploaded to PyPI)
- Binary wheels for Windows, Linux and OS X
- Documentation (html, pdf)
- A README file
- A Changelog file

Source archives, Changelog and README are built by running `paver release` in the repo root, and end up in `REPO_ROOT/release/`. Do this after you've created the signed tag locally. `paver release` will be sensitive to the version of Cython available in your build environment, so make sure your version matches the minimum requirements for the release. If this completes without issues, push the release commit (not the tag, see section above) to the `scipy` repo. If `pavement.py` is causing issues, it is also possible to simply use `python setup.py sdist` and perform the release notes task from `pavement.py` by hand.

To build wheels, push a commit to a branch used for the current release at <https://github.com/MacPython/scipy-wheels>. This triggers builds for all needed Python versions on TravisCI. Update and check the `.travis.yml` and `appveyor.yml` config files what commit to build, and what Python and NumPy are used for the builds (it needs to be the lowest supported NumPy version for each Python version). See the README file in the `scipy-wheels` repo for more details. Note that because several months may pass between SciPy releases, it is sometimes necessary to update the versions of the `gfortran-install` and `multibuild` submodules used for wheel builds. If the wheels builds reveal issues that need to be fixed with backports on the maintenance branch, you may remove the local tags (for example `git tag -d v1.2.0rc1`) and restart with tagging above on the new candidate commit.

The TravisCI and Appveyor builds run the tests from the built wheels and if they pass, upload the wheels to a container pointed to at <https://github.com/MacPython/scipy-wheels>. Once there are successful wheel builds, it is recommended to create a versioned branch in the `scipy-wheels` repo, which will for example be adjusted to point to different maintenance branch commits if there are multiple release candidates.

From there you can download them for uploading to PyPI. This can be done in an automated fashion using `tools/download-wheels.py`:

```
$ python tools/download-wheels.py 1.5.0rc1 -w REPO_ROOT/release/installers
```

The correct URL to use is shown in <https://github.com/MacPython/scipy-wheels> and should agree with the above one.

After this, we want to regenerate the README file, in order to have the MD5 and SHA256 checksums of the just downloaded wheels in it. Run:

```
$ paver write_release_and_log
```

Uploading release artifacts

For a release there are currently five places on the web to upload things to:

- PyPI (tarballs, wheels)
- Github releases (tarballs, release notes, Changelog)
- `scipy.org` (an announcement of the release)
- `docs.scipy.org` (html/pdf docs)

PyPI:

Upload first the wheels and then the sdist:

```
twine upload -s REPO_ROOT/release/installers/*.whl
twine upload -s REPO_ROOT/release/installers/scipy-1.x.y.tar.gz
```

If `gpg2` is preferred, then the above commands may also include `--sign-with gpg2`

Github Releases:

Use GUI on <https://github.com/scipy/scipy/releases> to create release and upload all release artifacts. At this stage, it is appropriate to push the tag and associate the new release (candidate) with this tag in the GUI. For example, `git push upstream v1.2.0rc1`, where `upstream` represents `scipy/scipy`. It is useful to check a previous release to determine exactly which artifacts should be included in the GUI upload process. Also, note that the release notes are not automatically populated into the release description on GitHub, and some manual reformatting to markdown can be quite helpful to match the formatting of previous releases on the site. We generally do not include Issue and Pull Request lists in these GUI descriptions.

scipy.org:

Sources for the site are in <https://github.com/scipy/scipy.org>. Update the News section in `www/index.rst` and then do `make upload USERNAME=yourusername`. This is only for proper releases, not release candidates.

docs.scipy.org:

First build the `scipy docs`, by running `make dist` in `scipy/doc/`. Verify that they look OK, then upload them to the doc server with `make upload USERNAME=rgommers RELEASE=0.19.0`. Note that SSH access to the doc server is needed; ask `@pv` (server admin) or `@rgommers` (can upload) if you don't have that.

The sources for the website itself are maintained in <https://github.com/scipy/docs.scipy.org/>. Add the new SciPy version in the table of releases in `index.rst`. Push that commit, then do `make upload USERNAME=yourusername`. This is only for proper releases, not release candidates.

Wrapping up

Send an email announcing the release to the following mailing lists:

- `scipy-dev`
- `numpy-discussion`
- `python-announce` (not for beta/rc releases)

For beta and rc versions, ask people in the email to test (run the `scipy tests` and test against their own code) and report issues on Github or `scipy-dev`.

After the final release is done, port relevant changes to release notes, build scripts, author name mapping in `tools/authors.py` and any other changes that were only made on the maintenance branch to master.

5.9 SciPy API Development Guide

5.9.1 A Design Specification for *nan_policy*

Many functions in `scipy.stats` have a parameter called `nan_policy` that determines how the function handles data that contains `nan`. In this section, we provide SciPy developer guidelines for how `nan_policy` is intended to be used, to ensure that as this parameter is added to new functions, we maintain a consistent API.

The basic API

The parameter `nan_policy` accepts three possible strings: `'omit'`, `'raise'` and `'propagate'`. The meanings are:

- `nan_policy='omit'`: Ignore occurrences of `nan` in the input. Do not generate a warning if the input contains `nan`. For example, for the simple case of a function that accepts a single array (and ignoring the possible use of `axis` for the moment):

```
func([1.0, 3.0, np.nan, 5.0], nan_policy='omit')
```

should behave the same as:

```
func([1.0, 3.0, 5.0])
```

More generally, `func(a, nan_policy='omit')` should behave the same as `func(a[~np.isnan(a)])`.

Unit tests for this property should be used to test functions that handle `nan_policy`.

For functions that accept two or more arguments but whose values are not related, the same idea applies to each input array. So:

```
func(a, b, nan_policy='omit')
```

should behave the same as:

```
func(a[~np.isnan(a)], b[~np.isnan(b)])
```

For inputs with *related* or *paired* values, the recommended behavior is to omit all the values for which any of the related values are nan. For a function with two related array inputs, this means:

```
y = func(a, b, nan_policy='omit')
```

should behave the same as:

```
hasnan = np.isnan(a) | np.isnan(b)  # Union of the isnan masks.
y = func(a[~hasnan], b[~hasnan])
```

The docstring for such a function should clearly state this behavior.

- `nan_policy='raise'`: Raise a `ValueError`.
- `nan_policy='propagate'`: Propagate the nan value to the output. Typically, this means just execute the function without checking for nan, but see

<https://github.com/scipy/scipy/issues/7818>

for an example where that might lead to unexpected output.

nan_policy combined with an axis parameter

There is nothing surprising here—the principle mentioned above still applies when the function has an `axis` parameter. Suppose, for example, `func` reduces a 1-d array to a scalar, and handles n-d arrays as a collection of 1-d arrays, with the `axis` parameter specifying the axis along which the reduction is to be applied. If, say:

```
func([1, 3, 4])      -> 10.0
func([2, -3, 8, 2]) ->  4.2
func([7, 8])        ->  9.5
func([])            -> -inf
```

then:

```
func([[ 1, nan,  3,  4],
      [ 2, -3,  8,  2],
      [nan,  7, nan,  8],
      [nan, nan, nan, nan]], nan_policy='omit', axis=-1)
```

must give the result:

```
np.array([10.0, 4.2, 9.5, -inf])
```

Edge cases

A function that implements the `nan_policy` parameter should gracefully handle the case where *all* the values in the input array(s) are `nan`. The basic principle described above still applies:

```
func([nan, nan, nan], nan_policy='omit')
```

should behave the same as:

```
func([])
```

In practice, when adding `nan_policy` to an existing function, it is not unusual to find that the function doesn't already handle this case in a well-defined manner, and some thought and design may have to be applied to ensure that it works. The correct behavior (whether that be to return `nan`, return some other value, raise an exception, or something else) will be determined on a case-by-case basis.

Why doesn't `nan_policy` also apply to `inf`?

Although we learn in grade school that “infinity is not a number”, the floating point values `nan` and `inf` are qualitatively different. The values `inf` and `-inf` act much more like regular floating point values than `nan`.

- One can compare `inf` to other floating point values and it behaves as expected, e.g. `3 < inf` is `True`.
- For the most part, arithmetic works “as expected” with `inf`, e.g. `inf + inf = inf`, `-2*inf = -inf`, `1/inf = 0`, etc.
- Many existing functions work “as expected” with `inf`: `np.log(inf) = inf`, `np.exp(-inf) = 0`, `np.array([1.0, -1.0, np.inf]).min() = -1.0`, etc.

So while `nan` almost always means “something went wrong” or “something is missing”, `inf` can in many cases be treated as a useful floating point value.

It is also consistent with the NumPy `nan` functions to not ignore `inf`:

```
>>> np.nanmax([1, 2, 3, np.inf, np.nan])
inf
>>> np.nansum([1, 2, 3, np.inf, np.nan])
inf
>>> np.nanmean([8, -np.inf, 9, 1, np.nan])
-inf
```

How *not* to implement `nan_policy`

In the past (and possibly currently), some `stats` functions handled `nan_policy` by using a masked array to mask the `nan` values, and then computing the result using the functions in the `mstats` subpackage. The problem with this approach is that the masked array code might convert `inf` to a masked value, which we don't want to do (see above). It also means that, if care is not taken, the return value will be a masked array, which will likely be a surprise to the user if they passed in regular arrays.

5.9.2 Adding vectorized ufuncs in `scipy.special`

Many of the functions in `special` are vectorized versions of scalar functions. The scalar functions are written by hand and the necessary loops for vectorization are generated automatically. This section discusses the steps necessary to add a new vectorized special function.

The first step in adding a new vectorized function is writing the corresponding scalar function. This can be done in Cython, C, C++, or Fortran. If starting from scratch then Cython should be preferred because the code is easier to maintain for developers only familiar with Python. If the primary code is in Fortran then it is necessary to write a C wrapper around the code; for examples of such wrappers see `specfun_wrappers.c`.

After implementing the scalar function, register the new function by adding an entry to `functions.json`. The docstring in `generate_ufuncs.py` explains the format. Also add documentation for the new function by adding an entry to `add_newdocs.py`; look in the file for examples.

When writing the parameters section of the documentation for ufuncs, the type of an argument should be `array_like`. Discussion of whether an argument can be e.g. real or complex-valued should be saved for the description. So for example, if we were to document the parameters for the Gamma function then it should look like this:

```
Parameters
-----
z : array_like
    Real or complex valued argument
```

When documenting the returns section, the type of the returned value should be `scalar` or `ndarray` since ufuncs return scalars when given scalars as arguments. Also keep in mind that providing a name for the return value is optional, and indeed is often not helpful for special functions. So for the Gamma function we might have something like this:

```
Returns
-----
scalar or ndarray
    Values of the Gamma function
```

5.10 SciPy Project Governance

The purpose of this document is to formalize the governance process used by the SciPy project in both ordinary and extraordinary situations, and to clarify how decisions are made and how the various elements of our community interact, including the relationship between open source collaborative development and work that may be funded by for-profit or non-profit entities.

5.10.1 The Project

The SciPy Project (The Project) is an open source software project. The goal of The Project is to develop open source software for scientific computing in Python, and, in particular, the `scipy` package. The Software developed by The Project is released under the BSD (or similar) open source license, developed openly and hosted on public GitHub repositories under the `scipy` GitHub organization.

The Project is developed by a team of distributed developers, called Contributors. Contributors are individuals who have contributed code, documentation, designs, or other work to the Project. Anyone can be a Contributor. Contributors can be affiliated with any legal entity or none. Contributors participate in the project by submitting, reviewing, and discussing GitHub Pull Requests and Issues and participating in open and public Project discussions on GitHub, mailing lists, and other channels. The foundation of Project participation is openness and transparency.

The Project Community consists of all Contributors and Users of the Project. Contributors work on behalf of and are responsible to the larger Project Community and we strive to keep the barrier between Contributors and Users as low as possible.

The Project is not a legal entity, nor does it currently have any formal relationships with legal entities.

5.10.2 Governance

This section describes the governance and leadership model of The Project.

The foundations of Project governance are:

- openness and transparency
- active contribution
- institutional neutrality

Traditionally, Project leadership was provided by a subset of Contributors, called Core Developers, whose active and consistent contributions have been recognized by their receiving “commit rights” to the Project GitHub repositories. In general, all Project decisions are made through consensus among the Core Developers with input from the Community.

While this approach has served us well, as the Project grows, we see a need for a more formal governance model. The SciPy Core Developers expressed a preference for a leadership model which includes a BDFL (Benevolent Dictator for Life). Therefore, moving forward The Project leadership will consist of a BDFL and Steering Council.

BDFL

The Project will have a BDFL (Benevolent Dictator for Life), who is currently Pauli Virtanen. As Dictator, the BDFL has the authority to make all final decisions for The Project. As Benevolent, the BDFL, in practice, chooses to defer that authority to the consensus of the community discussion channels and the Steering Council (see below). It is expected, and in the past has been the case, that the BDFL will only rarely assert his/her final authority. Because rarely used, we refer to BDFL’s final authority as a “special” or “overriding” vote. When it does occur, the BDFL override typically happens in situations where there is a deadlock in the Steering Council or if the Steering Council asks the BDFL to make a decision on a specific matter. To ensure the benevolence of the BDFL, The Project encourages others to fork the project if they disagree with the overall direction the BDFL is taking. The BDFL may delegate his/her authority on a particular decision or set of decisions to any other Council member at his/her discretion.

The BDFL can appoint his/her successor, but it is expected that the Steering Council would be consulted on this decision. If the BDFL is unable to appoint a successor, the Steering Council will make this decision - preferably by consensus, but if needed, by a majority vote.

Note that the BDFL can step down at any time, and acting in good faith, will also listen to serious calls to do so. Also note that the BDFL is more a role for fallback decision making rather than that of a director/CEO.

Steering Council

The Project will have a Steering Council that consists of Project Contributors who have produced contributions that are substantial in quality and quantity, and sustained over at least one year. The overall role of the Council is to ensure, through working with the BDFL and taking input from the Community, the long-term well-being of the project, both technically and as a community.

The Council will have a Chair, who is tasked with keeping the organizational aspects of the functioning of the Council and the Project on track. The Council will also appoint a Release Manager for the Project, who has final responsibility for one or more releases.

During the everyday project activities, Council Members participate in all discussions, code review, and other project activities as peers with all other Contributors and the Community. In these everyday activities, Council Members do not have any special power or privilege through their membership on the Council. However, it is expected that because of the quality and quantity of their contributions and their expert knowledge of the Project Software and Services, Council Members will provide useful guidance, both technical and in terms of project direction, to potentially less experienced contributors.

The Steering Council and its Members play a special role in certain situations. In particular, the Council may:

- Make decisions about the overall scope, vision, and direction of the project.
- Make decisions about strategic collaborations with other organizations or individuals.
- Make decisions about specific technical issues, features, bugs, and pull requests. They are the primary mechanism of guiding the code review process and merging pull requests.
- Make decisions about the Services that are run by The Project and manage those Services for the benefit of the Project and Community.
- Make decisions when regular community discussion does not produce consensus on an issue in a reasonable time frame.
- Update policy documents, such as this one.

Council membership

To become eligible for being a Steering Council Member, an individual must be a Project Contributor who has produced contributions that are substantial in quality and quantity, and sustained over at least one year. Potential Council Members are nominated by existing Council members and voted upon by the existing Council after asking if the potential Member is interested and willing to serve in that capacity. The Council will be initially formed from the set of existing Core Developers who, as of January 2017, have been significantly active over the last two years.

When considering potential Members, the Council will look at candidates with a comprehensive view of their contributions. This will include, but is not limited to, code, code review, infrastructure work, mailing list and chat participation, community help/building, education and outreach, design work, etc. We are deliberately not setting arbitrary quantitative metrics (like “100 commits in this repo”) to avoid encouraging behavior that plays to the metrics rather than the project’s overall well-being. We want to encourage a diverse array of backgrounds, viewpoints, and talents in our team, which is why we explicitly do not define code as the sole metric on which council membership will be evaluated.

If a Council Member becomes inactive in the project for a period of one year, they will be considered for removal from the Council. Before removal, inactive Member will be approached to see if they plan on returning to active participation. If not, they will be removed immediately upon a Council vote. If they plan on returning to active participation soon, they will be given a grace period of one year. If they don’t return to active participation within that time period they will be removed by vote of the Council without further grace period. All former Council Members can be considered for membership again at any time in the future, like any other Project Contributor. Retired Council Members will be listed on the project website, acknowledging the period during which they were active in the Council.

The Council reserves the right to eject current Members, other than the BDFL, if they are deemed to be actively harmful to the project’s well-being, and attempts at communication and conflict resolution have failed.

A list of current Steering Council Members is maintained at the page [governance-people](#).

Council Chair

The Chair will be appointed by the Steering Council. The Chair can stay on as long as he/she wants, but may step down at any time and will listen to serious calls to do so (similar to the BDFL role). The Chair will be responsible for:

- Starting a review of the technical direction of the project (as captured by the *SciPy Roadmap*) bi-yearly, around mid-April and mid-October.
- At the same times of the year, summarizing any relevant organizational updates and issues in the preceding period, and asking for feedback/suggestions on the mailing list.
- Ensuring the composition of the Steering Council stays current.
- Ensuring matters discussed in private by the Steering Council get summarized on the mailing list to keep the Community informed.
- Ensuring other important organizational documents (e.g., Code of Conduct, Fiscal Sponsorship Agreement) stay current after they are added.

Release Manager

The Release Manager has final responsibility for making a release. This includes:

- Proposing of and deciding on the timing of a release.
- Determining the content of a release in case there is no consensus on a particular change or feature.
- Creating the release and announcing it on the relevant public channels.

For more details on what those responsibilities look like in practice, see *Making a SciPy release*.

Conflict of interest

It is expected that the BDFL and Council Members will be employed at a wide range of companies, universities, and non-profit organizations. Because of this, it is possible that Members will have a conflict of interest. Such conflicts of interest include, but are not limited to:

- Financial interest, such as investments, employment or contracting work, outside of The Project that may influence their work on The Project.
- Access to proprietary information of their employer that could potentially leak into their work with the Project.

All members of the Council, BDFL included, shall disclose to the rest of the Council any conflict of interest they may have. Members with a conflict of interest in a particular issue may participate in Council discussions on that issue, but must recuse themselves from voting on the issue. If the BDFL has recused his/herself for a particular decision, the Council will appoint a substitute BDFL for that decision.

Private communications of the Council

Unless specifically required, all Council discussions and activities will be public and done in collaboration and discussion with the Project Contributors and Community. The Council will have a private mailing list that will be used sparingly and only when a specific matter requires privacy. When private communications and decisions are needed, the Council will do its best to summarize those to the Community after removing personal/private/sensitive information that should not be posted to the public internet.

Council decision making

If it becomes necessary for the Steering Council to produce a formal decision, then they will use a form of the [Apache Foundation voting process](#). This is a formalized version of consensus, in which +1 votes indicate agreement, -1 votes are vetoes (and must be accompanied with a rationale, as above), and one can also vote fractionally (e.g. -0.5, +0.5) if one wishes to express an opinion without registering a full veto. These numeric votes are also often used informally as a way of getting a general sense of people's feelings on some issue, and should not normally be taken as formal votes. A formal vote only occurs if explicitly declared, and if this does occur, then the vote should be held open for long enough to give all interested Council Members a chance to respond – at least one week.

In practice, we anticipate that for most Steering Council decisions (e.g., voting in new members) a more informal process will suffice.

5.10.3 Institutional Partners and funding

The Steering Council is the primary leadership for the project. No outside institution, individual, or legal entity has the ability to own, control, usurp, or influence the project other than by participating in the Project as Contributors and Council Members. However, because institutions can be an important funding mechanism for the project, it is important to formally acknowledge institutional participation in the project. These are Institutional Partners.

An Institutional Contributor is any individual Project Contributor who contributes to the project as part of their official duties at an Institutional Partner. Likewise, an Institutional Council Member is any Project Steering Council Member who contributes to the project as part of their official duties at an Institutional Partner.

With these definitions, an Institutional Partner is any recognized legal entity in any country that employs at least 1 Institutional Contributor or Institutional Council Member. Institutional Partners can be for-profit or non-profit entities.

Institutions become eligible to become an Institutional Partner by employing individuals who actively contribute to The Project as part of their official duties. To state this another way, the only way for a Partner to influence the project is by actively contributing to the open development of the project, in equal terms to any other member of the community of Contributors and Council Members. Merely using Project Software in institutional context does not allow an entity to become an Institutional Partner. Financial gifts do not enable an entity to become an Institutional Partner. Once an institution becomes eligible for Institutional Partnership, the Steering Council must nominate and approve the Partnership.

If, at some point, an existing Institutional Partner stops having any contributing employees, then a one year grace period commences. If, at the end of this one-year period, they continue not to have any contributing employees, then their Institutional Partnership will lapse, and resuming it will require going through the normal process for new Partnerships.

An Institutional Partner is free to pursue funding for their work on The Project through any legal means. This could involve a non-profit organization raising money from private foundations and donors or a for-profit company building proprietary products and services that leverage Project Software and Services. Funding acquired by Institutional Partners to work on The Project is called Institutional Funding. However, no funding obtained by an Institutional Partner can override the Steering Council. If a Partner has funding to do SciPy work and the Council decides to not pursue that work as a project, the Partner is free to pursue it on their own. However, in this situation, that part of the Partner's work will not be under the SciPy umbrella and cannot use the Project trademarks in any way that suggests a formal relationship.

Institutional Partner benefits are:

- acknowledgement on the SciPy website and in talks
- ability to acknowledge their own funding sources on the SciPy website and in talks
- ability to influence the project through the participation of their Council Member
- invitation of the Council Members to SciPy Developer Meetings

A list of current Institutional Partners is maintained at the page [governance-people](#).

5.10.4 Document history

<https://github.com/scipy/scipy/commits/master/doc/source/dev/governance/governance.rst>

5.10.5 Acknowledgements

Substantial portions of this document were adapted from the [Jupyter/IPython project's governance document](#) and [NumPy's governance document](#).

5.10.6 License

To the extent possible under law, the authors have waived all copyright and related or neighboring rights to the SciPy project governance document, as per the [CC-0 public domain dedication / license](#).

5.11 Development environment quickstart guide (macOS)

This quickstart guide will cover:

- setting up and maintaining a development environment, including installing compilers and SciPy build dependencies
- creating a personal fork of the SciPy repository on GitHub
- using git to manage a local repository with development branches
- performing an in-place build of SciPy
- creating a virtual environment that adds this development version of SciPy to the Python path

in macOS.

Its companion videos [Anaconda SciPy Dev: Part I \(macOS\)](#) and [Anaconda SciPy Dev: Part II \(macOS\)](#) show many of the steps being performed. This guide may diverge slightly from the videos over time, with the goal of keeping this guide the simplest, up-to-date procedure.

Note: This guide does not present the only way to set up a development environment; there are many valid choices of Python distribution, C/Fortran compiler, and installation options. The steps here can often be adapted for other choices, but we cannot provide documentation tailored for them.

This guide assumes that you are starting without an existing Python 3 installation. If you already have Python 3, you might want to uninstall it first to avoid ambiguity over which Python version is being used at the command line.

5.11.1 Building SciPy

Consider following along with the companion video [Anaconda SciPy Dev: Part I \(macOS\)](#)

1. Download, install, and test the latest release of the [Anaconda Distribution of Python](#). In addition to the latest version of Python 3, the Anaconda distribution includes dozens of the most popular Python packages for scientific computing, the Spyder integrated development environment (IDE), the `conda` package manager, and tools for managing virtual environments.
2. Install Apple Developer Tools. An easy way to do this is to [open a terminal window](#), enter the command `xcode-select --install`, and follow the prompts. Apple Developer Tools includes `git`, the software we need to download and manage the SciPy source code.

3. Browse to the [SciPy repository on GitHub](#) and create your own fork. You'll need to create a GitHub account if you don't already have one.
4. Browse to your fork. Your fork will have a URL like <https://github.com/mdhaber/scipy>, except with your GitHub username in place of "mdhaber".
5. Click on the big, green "Clone or download" button, and copy the ".git" URL to the clipboard. The URL will be the same as your fork's URL, except it will end in ".git".
6. Create a folder for the SciPy source code in a convenient place on your computer. [Navigate to it in the terminal](#).
7. Enter the command `git clone` followed by your fork's .git URL. Note that this creates in the terminal's working directory a `scipy` folder containing the SciPy source code.
8. In the terminal, navigate to the `scipy` root directory (e.g., `cd scipy`).
9. Install [Homebrew](#). Enter into the terminal `/usr/bin/ruby -e "$(curl -fsSL https://raw.githubusercontent.com/Homebrew/install/master/install)"` or follow the installation instructions listed on the [Homebrew website](#). Homebrew is a package manager for macOS that will help you download `gcc`, the software we will use to compile C, C++, and Fortran code included in SciPy.
10. Use Homebrew to install `gcc` by entering the command `brew install gcc`.
11. In the terminal, ensure that all of SciPy's build dependencies are up to date: `conda install pybind11`, then `conda update cython numpy pytest pybind11`.
12. (Optional) Check your present working directory by entering `pwd` at the terminal. You should be in the root `/scipy` directory, not in a directory ending `/scipy/scipy`.
13. Do an in-place build: enter `python3 setup.py build_ext --inplace`. This will compile the C, C++, and Fortran code that comes with SciPy. We installed `python3` with Anaconda. `setup.py` is a script in the root directory of SciPy, which is why you have to be in the SciPy root directory to call it. `build_ext` is a command defined in `setup.py`, and `--inplace` is an option we'll use to ensure that the compiling happens in the SciPy directory you already have rather than the default location for Python packages. By building in-place, you avoid having to re-build SciPy before you can test changes to the Python code.
14. Test the build: enter `python3 runtests.py -v`. `runtests.py` is another script in the SciPy root directory. It runs a suite of tests that make sure SciPy is working as it should, and `-v` activates the `--verbose` option to show all the test output.

If the tests were successful, you now have a working development build of SciPy! You could stop here, but you would only be able to use this development build from within the SciPy root directory. This would be inconvenient, for instance, if you wrote a script that performs an `import` of something you changed in SciPy but wanted to save it elsewhere on your computer. Without taking additional steps to add this version of SciPy to the `PYTHONPATH`, this script would `import` from the version of SciPy distributed with Anaconda rather than the development version you just built. (See [here](#) for much more information about how Python imports modules.)

5.11.2 Installing SciPy

Consider following along with the companion video [Anaconda SciPy Dev: Part II \(macOS\)](#)

Currently we have *two* versions of SciPy: the latest release as installed by Anaconda, and the development version we just built. Ideally, we'd like to be able to switch between the two as needed. [Virtual environments](#) can do just that. With a few keystrokes in the terminal or even the click of an icon, we can enable or disable our development version. Let's set that up.

1. In a terminal window, enter `conda list`. This shows a list of all the Python packages that came with the Anaconda distribution of Python. Note the latest released version of SciPy is among them; this is not the cutting-edge development version you just built and can modify.

2. Enter `conda create --name scipydev`. This tells `conda` to create a virtual environment named `scipydev`. Note that `scipydev` can be replaced by any name you'd like to refer to your virtual environment.
3. You're still in the base environment. Activate your new virtual environment by entering `conda activate scipydev`. If you're working with an old version of `conda`, you might need to type `source activate scipydev` instead (see [here](#)).
4. (Optional) Enter `conda list` again. Note that the new virtual environment has no packages installed. If you were to open a Python interpreter now, you wouldn't be able to import `numpy`, `scipy`, etc.
5. Enter `conda install cython numpy pytest spyder pybind11`. Note that we're only installing SciPy's build dependencies (and Spyder so we can use the IDE), but not SciPy itself.
6. Enter `conda develop /scipy`, where `scipy` is to be replaced with the full path of the SciPy root directory. This will allow us to import the development version of SciPy in Python regardless of Python's working directory. *Note: this step replace the steps shown in [Anaconda SciPy Dev: Part II \(macOS\)](#) that modify the `PYTHONPATH` environment variable when the `scipydev` virtual environment is activated. You can ignore that part of the video from 0:38 to 1:38; this is much simpler!*
7. In a new terminal window, test your setup. If you activate your virtual environment (e.g., `conda activate scipydev`) and run Python code that imports from SciPy, any changes you make to the SciPy code should be reflected when the code runs. After deactivating the virtual environment (`conda deactivate`), Python imports from the version of SciPy installed by Anaconda. You can also check which version of SciPy you're using by executing in Python:

```
import scipy
print(scipy.__version__)
```

If you have successfully imported a development version of SciPy, the word `dev` will appear in the output, e.g.:

```
1.4.0.dev0+be97f1a
```

5.12 Development environment quickstart guide (Ubuntu)

This quickstart guide will cover:

- setting up and maintaining a development environment, including installing compilers and SciPy build dependencies;
- creating a personal fork of the SciPy repository on GitHub;
- using git to manage a local repository with development branches;
- performing an in-place build of SciPy; and
- creating a virtual environment that adds this development version of SciPy to the Python path

in Ubuntu. (Tested on 16.04, 18.04, and 20.04). *Users running Windows can follow these instructions after setting up [Windows Subsystem for Linux](#) or an [Amazon EC2 instance with Ubuntu 20.04](#). However, the instructions for setting up a development environment with Docker may be more reliable.*

Note: This guide does not present the only way to set up a development environment; there are many valid choices of Python distribution, C/Fortran compiler, and installation options. The steps here can often be adapted for other choices, but we cannot provide documentation tailored for them.

This guide assumes that you are starting without an existing Python 3 installation. If you already have Python 3, you might want to uninstall it first to avoid ambiguity over which Python version is being used at the command line.

5.12.1 Building SciPy

1. Download, install, and test the latest release of the [Anaconda Distribution of Python](#). In addition to the latest version of Python 3, the Anaconda Distribution includes dozens of the most popular Python packages for scientific computing, the `conda` package manager, and tools for managing virtual environments.

If you're installing using the terminal, be sure to follow the "Next Steps" listed after the installer finishes. You might also need to restart your terminal window or enter `source ~/.bashrc` for all the changes to take effect.

2. (Optional) In a terminal window, enter `conda list`. This shows a list of all the Python packages that came with the Anaconda Distribution of Python. Note the latest released version of SciPy is among them; this is not the development version you are going to build and will be able to modify.

Ideally, we'd like to have both versions, and we'd like to be able to switch between the two as needed. [Virtual environments](#) can do just that. With a few keystrokes in the terminal or even the click of an icon, we can enable or disable our development version. Let's set that up.

Note: If `conda` is not a recognized command, try restarting your terminal. If it is still not recognized, please see "Should I add Anaconda to the macOS or Linux PATH?" in the [Anaconda FAQ](#).

3. Enter `conda create --name scipydev python=3.8 numpy pybind11 cython pytest gfortran_linux-64 gxx_linux-64 sphinx matplotlib mpy git`. This tells `conda` to create a virtual environment named `scipydev` (or another name that you prefer) with several packages.

- `numpy pybind11 cython pytest` are four packages that SciPy depends on.
- `gfortran_linux-64 gxx_linux-64` are compilers used to build SciPy's Fortran, C, and C++ source code.
- `sphinx` and `matplotlib` are required to render the SciPy documentation.
- `mpy` is a static type checker for Python. Consider using it.
- `git` is a version control system used to download and manage the SciPy source code.

Note that we're installing SciPy's build dependencies and some other software, but not SciPy itself.

Note: You could `conda create` an empty virtual environment first, then `conda install` the packages, but creating the virtual environment with all the packages you need is preferable to installing packages individually because it makes it easier for `conda` to solve the package dependencies optimally.

4. You're still in the base environment. Activate your new virtual environment by entering `conda activate scipydev`. If you're working with an old version of `conda`, you might need to type `source activate scipydev` instead (see [here](#)). Note that you'll need to have this virtual environment active whenever you want to work with the development version of SciPy.
5. Browse to the [SciPy repository on GitHub](#) and [create your own fork](#). You'll need to create a GitHub account if you don't already have one.
6. Browse to your fork. Your fork will have a URL like <https://github.com/mdhaber/scipy>, except with your GitHub username in place of "mdhaber".
7. Click the big, green "Clone or download" button, and copy the ".git" URL to the clipboard. The URL will be the same as your fork's URL, except it will end in ".git".
8. Create a folder for the SciPy source code in a convenient place on your computer. Navigate to it in the terminal.
9. Enter the command `git clone` followed by your fork's .git URL. Note that this creates in the terminal's working directory a `scipy` folder containing the SciPy source code.

10. In the terminal, navigate into the `scipy` root directory (e.g. `cd scipy`).
11. Do an in-place build: enter `python3 setup.py build_ext --inplace`. This will compile the C, C++, and Fortran code that comes with SciPy. We installed `python3` with Anaconda. `setup.py` is a script in the root directory of SciPy, which is why you have to be in the SciPy root directory to call it. `build_ext` is a command defined in `setup.py`, and `--inplace` is an option we'll use to ensure that the compiling happens in the SciPy directory you already have rather than the default location for Python packages. By building in-place, you avoid having to re-build SciPy before you can test changes to the Python code.
12. Test the build: enter `python3 runtests.py -v`. `runtests.py` is another script in the SciPy root directory. It runs a suite of tests that make sure SciPy is working as it should, and `-v` activates the `--verbose` option to show all the test output. If the tests are successful, you now have a working development build of SciPy! You could stop here, but you would only be able to use this development build when the Python working directory is the SciPy root directory.
13. Enter `conda develop .`, where `.` refers to the present directory. This will allow us to `import` the development version of SciPy in Python regardless of Python's working directory.
14. In a new terminal window, test your setup. If you activate your virtual environment (e.g. `conda activate scipydev`) and run Python code that imports from SciPy, any changes you make to the SciPy code should be reflected when the code runs. After deactivating the virtual environment (`conda deactivate`), Python imports from the version of SciPy installed by Anaconda. You can also check which version of SciPy you're using by executing in Python:

```
import scipy
print(scipy.__version__)
```

If you have successfully imported a development version of SciPy, the word `dev` will appear in the output, e.g.:

```
1.6.0.dev0+be97f1a
```

5.13 Development workflow

Note: consider watching [SciPy Development Workflow](#) before or after reading to see an example of fixing a bug and submitting a pull request.

In *Development environment quickstart guide (macOS)* or *Development environment quickstart guide (Ubuntu)*, you created your own fork (copy) of the SciPy repository, cloned the repository on your own machine, and built SciPy from this source code. Before getting started here, there are two other things you need to do just once before you start modifying SciPy.

1. In a terminal, introduce yourself to Git:

```
git config --global user.email you@yourdomain.com
git config --global user.name "Your Name"
```

This information credits you for your work, but note that it will become publicly available if you “push” your work to GitHub. See [Setting your commit email address in Git](#) for more information.

2. Navigate to the root directory of your local SciPy repository and enter:

```
git remote add upstream https://github.com/scipy/scipy.git
```

This associates the name `upstream` with the official SciPy repository located at <https://github.com/scipy/scipy.git>. Note that when you cloned your fork of the SciPy repository, Git already associated the name `origin` with your fork. The reason you need both of these “remotes” is that you will typically start with the latest version of

SciPy from the official repository `upstream`, make changes, “push” your changes to your fork of the repository `origin`, and then submit a “pull request” asking SciPy to “pull” your changes from your fork into the official repository.

5.13.1 Basic workflow

In short:

1. Start a new *feature branch* for each set of edits that you do. See *below*.
2. Hack away! See *below*.
3. When finished:
 - *Contributors*: push your feature branch to your own Github repo, and *create a pull request*.
 - *Core developers* If you want to push changes without further review, see the notes below.

This way of working helps to keep work well organized and the history as clear as possible.

See also:

There are many online tutorials to help you [learn git](#). For discussions of specific git workflows, see these discussions on [linux git workflow](#), and [ipython git workflow](#).

Making a new feature branch

First, navigate to the SciPy root directory in your terminal and fetch new commits from the `upstream` repository:

```
git fetch upstream
```

Then, create a new branch based on the `master` branch of the upstream repository:

```
git checkout -b my-new-feature upstream/master
```

Equivalently, you might want to keep the `master` branch of your own repository up to date and create a new branch based on that:

```
git checkout master
git rebase upstream/master
git checkout -b my-new-feature
```

In order, these commands

1. ensure that the `master` branch of your local repository is checked out,
2. apply all the latest changes from the `upstream/master` (main SciPy repository `master` branch) to your local `master` branch, and
3. create and check out a new branch (`-b`) based on your local `master` branch.

In any case, it’s important that your feature branch include the latest changes from the upstream `master` to help avoid [merge conflicts](#) when it’s time to submit a pull request.

It’s also a good idea to build this branch and run tests before continuing. Assuming you’ve followed [Development environment quickstart guide \(macOS\)](#) or [Development environment quickstart guide \(Ubuntu\)](#) to set up your development environment, you’ll need to activate your development virtual environment, perform an in-place build, and run tests:

```
conda activate name-of-your-virtual-environment
python setup.py build_ext --inplace
python runtests.py -v
```

Otherwise, see building, *Running SciPy Tests Locally* for more information.

The editing workflow

Overview

```
# hack hack
git status # Optional
git diff # Optional
git add modified_file
git commit
# push the branch to your own Github repo
git push origin my-new-feature
```

In more detail

1. Make some changes. When you feel that you've made a complete, working set of related changes, move on to the next steps.
2. Optional: Check which files have changed with `git status` (see [git status](#)). You'll see a listing like this one:

```
# On branch my-new-feature
# Changed but not updated:
#   (use "git add <file>..." to update what will be committed)
#   (use "git checkout -- <file>..." to discard changes in working_
→directory)
#
#   modified:   README
#
# Untracked files:
#   (use "git add <file>..." to include in what will be committed)
#
#   INSTALL
no changes added to commit (use "git add" and/or "git commit -a")
```

3. Optional: Compare the changes with the previous version using with `git diff` ([git diff](#)). This brings up a simple text browser interface that highlights the difference between your files and the previous version.
4. Add any relevant modified or new files using `git add modified_file` (see [git add](#)). This puts the files into a staging area, which is a queue of files that will be added to your next commit. Only add files that have related, complete changes. Leave files with unfinished changes for later commits.
5. To commit the staged files into the local copy of your repo, do `git commit`. At this point, a text editor will open up to allow you to write a commit message. Read the [commit message section](#) to be sure that you are writing a properly formatted and sufficiently detailed commit message. After saving your message and closing the editor, your commit will be saved. For trivial commits, a short commit message can be passed in through the command line using the `-m` flag. For example, `git commit -am "ENH: Some message"`.

In some cases, you will see this form of the commit command: `git commit -a`. The extra `-a` flag automatically commits all modified files and removes all deleted files. This can save you some typing of numerous `git add`

commands; however, it can add unwanted changes to a commit if you're not careful. For more information, see [why the -a flag?](#) - and the helpful use-case description in the [tangled working copy problem](#).

6. Push the changes to your forked repo on [github](#):

```
git push origin my-new-feature
```

For more information, see [git push](#).

Note: Assuming you have followed the instructions in these pages, git will create a default link to your [github](#) repo called `origin`. In git >= 1.7, you can ensure that the link to `origin` is permanently set by using the `--set-upstream` option:

```
git push --set-upstream origin my-new-feature
```

From now on, `git` will know that `my-new-feature` is related to the `my-new-feature` branch in your own [github](#) repo. Subsequent push calls are then simplified to the following:

```
git push
```

You have to use `--set-upstream` for each new branch that you create.

It may be the case that while you were working on your edits, new commits have been added to `upstream` that affect your work. In this case, follow the [rebasng-on-master](#) instructions to apply those changes to your branch.

Writing the commit message

Commit messages should be clear and follow a few basic rules. Example:

```
ENH: add functionality X to SciPy.<submodule>.
```

The first line of the commit message starts **with** a capitalized acronym (options listed below) indicating what **type** of commit this **is**. Then a blank line, then more text **if** needed. Lines shouldn't be longer than 72 characters. If the commit **is** related to a ticket, indicate that **with** "[See #3456](#)", "[See ticket 3456](#)", "[Closes #3456](#)", **or** similar.

Describing the motivation for a change, the nature of a bug for bug fixes or some details on what an enhancement does are also good to include in a commit message. Messages should be understandable without looking at the code changes. A commit message like `MAINT: fixed another one` is an example of what not to do; the reader has to go look for context elsewhere.

Standard acronyms to start the commit message with are:

```
API: an (incompatible) API change
BENCH: changes to the benchmark suite
BLD: change related to building SciPy
BUG: bug fix
DEP: deprecate something, or remove a deprecated object
DEV: development tool or utility
DOC: documentation
ENH: enhancement
MAINT: maintenance commit (refactoring, typos, etc.)
REV: revert an earlier commit
STY: style fix (whitespace, PEP8)
```

(continues on next page)

```
TST: addition or modification of tests
REL: related to releasing SciPy
```

Asking for your changes to be merged with the main repo

When you feel your work is finished, you can create a pull request (PR). Github has a nice help page that outlines the process for [filing pull requests](#).

If your changes involve modifications to the API or addition/modification of a function, you should initiate a code review. This involves sending an email to the [SciPy mailing list](#) with a link to your PR along with a description of and a motivation for your changes.

Checklist before submitting a PR

- Did you check that the code can be distributed under a BSD license? See [License Considerations](#).
- Are there unit tests with good code coverage? See [NumPy/SciPy Testing Guidelines](#).
- Do all unit tests pass locally? See [Running SciPy Tests Locally](#).
- Do all public function have docstrings including examples? See the [numpydoc docstring guide](#).
- Does the documentation render correctly? See [Rendering Documentation with Sphinx](#).
- Is the code style correct? See [PEP8 and SciPy](#).
- Are there benchmarks? See [Benchmarking SciPy with airspeed velocity](#).
- Is the commit message [formatted correctly](#)?
- Is the docstring of the new functionality tagged with `.. versionadded:: X.Y.Z` (where X.Y.Z is the version number of the next release? See the [updating, workers, and constraints](#) documentation of [differential_evolution](#), for example. You can get the next version number from the most recent release notes on the [wiki](#) or from the MAJOR and MINOR version number variables in `setup.py`.
- In case of larger additions, is there a tutorial or more extensive module-level description? Tutorial files are in `doc/source/tutorial`.
- If compiled code is added, is it integrated correctly via `setup.py`? See [Compiled code](#) for more information.

5.14 PEP8 and SciPy

All SciPy Python code should adhere to [PEP8](#) style guidelines. It's so important that some continuous integration tests on GitHub will fail due to certain PEP8 violations. Here are a few tips for ensuring PEP8 compliance before pushing your code:

- Many integrated development environments (IDEs) have options that automatically check for PEP8 compliance. In Spyder, for example, [enable Real-time code style analysis](#) in Tools → Preferences → Editor → Code Introspection/Analysis and “Automatically remove trailing spaces when saving files” in in Tools → Preferences → Editor → Advanced Settings. This can help you fix PEP8 issues as you write your code.
- You can also perform checks using the `flake8` tool. After installing `flake8`, navigate to the SciPy root directory in a console window and try:

```
flake8 scipy/optimize/linprog.py
```

The absence of output indicates that there are no PEP8 issues with the file. Unfortunately, there is also no output if you get the file path wrong:

```
flake8 scipy/optimize/linprog2.py
```

(`linprog2.py` doesn't exist.) To make sure you have the path right, consider introducing (and then removing) a small PEP8 issue in the target file, such as a line that is over 79 characters long.

- If you have existing code with a lot of PEP8 issues, consider using `autopep8` to automatically fix most of them.

5.15 Rendering Documentation with Sphinx

SciPy docstrings are rendered to html using `Sphinx`. Writing docstrings is covered in the [A Guide to NumPy Documentation](#); this document explains how to check that docstrings render properly.

For a video walkthrough, please see [Rendering SciPy Documentation with Sphinx](#).

5.15.1 Rendering Documentation Locally

To render the documentation on your own machine:

0. Ensure that you have a working SciPy *Development environment* active. You need to be able to import `scipy` regardless of Python's working directory; the `python setup.py develop` and `conda develop` commands from the *quickstart* guides make this possible.
1. Install `Sphinx` and `matplotlib`. For example, if you're using the Anaconda distribution of Python, enter in a terminal window `conda install sphinx matplotlib`.
2. In a terminal window, browse to the `scipy/doc` directory. Note the presence of the file `Makefile`.
3. Execute `git submodule update --init`. Some of the documentation theme files are not distributed with the main `scipy` repository; this keeps them up to date using `git submodules`.
4. Enter `make html-scipyorg`. If you have multiple version of Python on your path, you can choose which version to use by appending `PYTHON=python3.7` to this command, where `python3.7` is to be replaced with the name of the Python you use for SciPy development. This uses the [Make build automation tool](#) to execute the documentation build instructions from the `Makefile`. This can take a while the first time, but subsequent documentation builds are typically much faster.
5. View the documentation in `scipy/doc/build/html-scipyorg`. You can start with `index.html` and browse, or you can jump straight to the file you're interested in.

Note: Changes to certain documents do not take effect when Sphinx documentation is rebuilt. In this case, you can build from scratch by deleting the `scipy/doc/build` directory, then building again.

5.15.2 Checking Documentation on the Cloud

Once a PR is opened, you can check that documentation renders correctly on the cloud.

1. Log in to [GitHub](#).
2. Log in [CircleCI](#) using your GitHub account.
3. Back in GitHub, at the bottom of the PR, select "Show all Checks".
4. Next to "ci/circleci: build_docs artifact", select "Details".

5.16 Running SciPy Tests Locally

Basic test writing and execution from within the Python interpreter is documented in the [NumPy/SciPy Testing Guidelines](#). This page includes information about running tests from the command line using SciPy's `runtests.py`, which permits greater control. *Note: Before beginning, ensure that `pytest` is installed.*

To run all tests, navigate to the root SciPy directory at the command line and execute

```
python runtests.py -v
```

where `-v` activates the `--verbose` option. This builds SciPy (or updates an existing build) and runs the tests.

To run tests on a particular submodule, such as `optimize`, use the `--submodule` option:

```
python runtests.py -v -s optimize
```

To run a particular test module, such as `scipy/optimize/tests/test_linprog.py`, use the `--test` option:

```
python runtests.py -v -t scipy/optimize/tests/test_linprog.py
```

To run a test class, such as `TestLinprogIPDense` from `test_linprog.py`:

```
python runtests.py -v -t scipy/optimize/tests/test_linprog.  
↪py::TestLinprogIPDense
```

To run a particular test, such as `test_unknown_solver` from `test_linprog.py`:

```
python runtests.py -v -t scipy/optimize/tests/test_linprog.py::test_unknown_  
↪solver
```

For tests within a class, you need to specify the class name and the test name:

```
python runtests.py -v -t scipy/optimize/tests/test_linprog.  
↪py::TestLinprogIPDense::test_nontrivial_problem
```

Other useful options include:

- `--coverage` to generate a test coverage report in `scipy/build/coverage/index.html`. *Note: `pytest-cov` must be installed.*
- `--doc` to build the docs in `scipy/doc/build`. By default, docs are built only in the `html-scipyorg` format, but you can change this by appending the name of the desired format (e.g. `--doc latex`).
- `-n` or `--no-build` to prevent SciPy from updating the build before testing
- `-j` or `--parallel n` to engage `n` cores when building SciPy; e.g. `python runtests.py -j 4` engages four cores. As of [#10172](#) this also runs the tests on four cores if `pytest-xdist` is installed.
- `-m` or `--mode full` to run the full test suite, including slow tests. For example, `python runtests.py -m full`.
- `--` to send remaining command line arguments to `pytest` instead of `runtest.py`. For instance, while `-n` sent to `pytest.py` activates the `--no-build` option, `-n` sent to `pytest` runs the tests on multiple cores; e.g. `python runtests.py -- -n 4` runs tests using four cores. *Note: `pytest-xdist` must be installed for testing on multiple cores.*

Other options not documented here are listed in the main function of the source code for `runtests.py`. For much more information about `pytest`, see the [pytest documentation](#).

5.16.1 Tips:

If you built SciPy from source but are having trouble running tests after a change to the codebase, try deleting the `scipy/build` directory. This forces `runtest.py` to completely rebuild SciPy before performing tests.

There is an additional level of very slow tests (several minutes), which are disabled even when calling `python runtests.py -m full`. They can be enabled by setting the environment variable `SCIPY_XSLOW=1` before running the test suite.

5.17 Benchmarking SciPy with airspeed velocity

This document introduces benchmarking, including reviewing SciPy benchmark test results online, writing a benchmark test, and running it locally. For a video run-through of writing a test and running it locally, see [Benchmarking SciPy](#).

As written in the [airspeed velocity \(asv\)](#) documentation:

Airspeed velocity (asv) is a tool for benchmarking Python packages over their lifetime. Runtime, memory consumption, and even custom-computed values may be tracked. The results are displayed in an interactive web frontend that requires only a basic static webserver to host.

To see what this means, take a look at [airspeed velocity of an unladen scipy](#). Each plot summarizes the execution time of a particular test over the commit history of the project; that is, as each commit is merged, the benchmark test is run, its execution time is measured, and the elapsed time is plotted. In addition to tracking the performance of the code, a commit is *intended* to affect, running *all* benchmarks for each commit is helpful for identifying unintentional regressions: significant increases in the execution time of one or more benchmark tests. As SciPy is a web of interconnected code, the repercussions of a small change may not be immediately obvious to a contributor, so this benchmark suite makes it easier to detect regressions and identify the commit that caused them. When you contribute a substantial new feature - or notice a feature that doesn't already have a benchmark test - please consider writing benchmarks.

5.17.1 Writing benchmarks

The [Writing benchmarks](#) section of the [airspeed velocity](#) documentation is the definitive guide to writing benchmarks. Please see also the [SciPy benchmarks](#) readme.

To see how benchmarks are written, take a look at `scipy/benchmarks/benchmarks/optimize_linprog.py`. Each subclass of `Benchmark` defines a benchmark test. For example, the `KleeMinty` class defines a benchmark test based on the [Klee-Minty hypercube problem](#), a diabolical test of the simplex algorithm for linear programming. The class has four parts:

- `setup` prepares the benchmark to run. The execution time of this function is *not* counted in the benchmark results, so this is a good place to set up all variables that define the problem. In the `KleeMinty` example, this involves generating arrays `c`, `A_ub`, and `b_ub` corresponding with a Klee-Minty hypercube in `dims` dimensions and storing them as instance variables.
- `time_klee_minty` actually runs the benchmark test. This function executes after a `KleeMinty` object has been instantiated and `setup` has run, so it gets the arrays defining the problem from `self`. Note that the prefix `time` in the function name indicates to `asv` that the execution time of this function *is* to be counted in the benchmark results.
- `params` is a list of lists defining parameters of the test. Benchmarks are run for all possible combinations of these parameters. For example, the first time the benchmark is run, the first element of `methods` (`simplex`) is passed into `setup` and `time_klee_minty` as the first argument, `meth`, and the first element of `[3, 6, 9]` (3) is passed into `setup` and `time_klee_minty` as the second argument, `dims`. The next time the benchmark is run, `setup` and `time_klee_minty` are passed `revised simplex` and 6 as arguments, and so this continues until all combinations of parameters have been used.

- `param_names` is a list of human-readable names for each element of the `params` list. These are used for presenting results.

Results of this benchmark over the past few years are available by clicking on the [KleeMinty.time_lee_minty](#) link at [airspeed velocity of an unladen scipy](#). Note that each trace of the plot corresponds with a combination of benchmark parameters and environment settings (e.g., the Cython version), and that the visibility of the traces can be toggled using the control panel on the left.

5.17.2 Running benchmarks locally

Before beginning, ensure that [airspeed velocity](#) is installed.

After contributing new benchmarks, you should test them locally before submitting a pull request.

To run all benchmarks, navigate to the root SciPy directory at the command line and execute:

```
python runtests.py --bench
```

where `--bench` activates the benchmark suite instead of the test suite. This builds SciPy and runs the benchmarks. (Note: this could take a while. Benchmarks often take longer to run than unit tests, and each benchmark is run multiple times to measure the distribution in execution times.)

To run benchmarks from a particular benchmark module, such as `optimize_linprog.py`, simply append the filename without the extension:

```
python runtests.py --bench optimize_linprog
```

To run a benchmark defined in a class, such as `KleeMinty` from `optimize_linprog.py`:

```
python runtests.py --bench optimize_linprog.KleeMinty
```

To compare benchmark results between the active branch and another, such as `master`:

```
python runtests.py --bench-compare master optimize_linprog.KleeMinty
```

All of the commands above display the results in plain text in the console, and the results are not saved for comparison with future commits. For greater control, a graphical view, and to have results saved for future comparison, you can use the `asv` terminal command directly.

To use it, navigate to `scipy/benchmarks` in the console and then execute:

```
asv run
```

This command runs the whole benchmark suite and saves the results for comparison against future commits.

To run only a single benchmark, such as `KleeMinty` from `optimize_linprog.py`:

```
asv run --bench optimize_linprog.KleeMinty
```

One great feature of `asv` is that it can automatically run a benchmark not just for the current commit, but for every commit in a range. `linprog method='interior-point'` was merged into SciPy with commit `7fa17f2369e0e5ad055b23cc1a5ee079f9e8ca32`, so let's run the `KleeMinty` benchmark for 10 commits between then and now to track its performance over time:

```
asv run --bench optimize_linprog.KleeMinty --steps 10 7fa17f..
```

Note: This will take a while, because SciPy has to be rebuilt for each commit! For more information about specifying ranges of commits, see the [git revisions documentation](#).

To “publish” the results (prepare them to be viewed) and “preview” them in an interactive console:

```
asv publish
asv preview
```

ASV will report that it is running a server. Using any browser, you can review the results by navigating to <http://127.0.0.1:8080> (local machine, port 8080).

For much more information about the `asv` commands, see the [airspeed velocity Commands](#) documentation. (Tip: check out the `asv find` command and the `--quick`, `--skip-existing-commits`, and `--profile` options for `asv run`.)

5.18 Adding Cython to SciPy

As written on the [Cython website](#):

Cython is an optimising static compiler for both the Python programming language and the extended Cython programming language (based on Pyrex). It makes writing C extensions for Python as easy as Python itself.

If your code currently performs a lot of loops in Python, it might benefit from compilation with Cython. This document is intended to be a very brief introduction: just enough to see how to use Cython with SciPy. Once you have your code compiling, you can learn more about how to optimize it by reviewing the [Cython documentation](#).

There are only two things you need to do in order for SciPy compile your code with Cython:

1. Include your code in a file with a `.pyx` extension rather than a `.py` extension. All files with a `.pyx` extension are automatically converted by Cython to `.c` files when SciPy is built.
2. Add an extension from this `.c` file to the configuration of the subpackage in which your code lives. Typically, this is very easy: add a single, formulaic line to the subpackage’s `setup.py` file. Once added as an extension, the `.c` code will be compiled by your C compiler to machine code when SciPy is built.

5.18.1 Example

`scipy.optimize._linprog_rs.py` contains the implementation of the revised simplex method for `scipy.optimize.linprog`. The revised simplex method performs many elementary row operations on matrices, and so it was a natural candidate to be Cythonized.

Note that `scipy/optimize/_linprog_rs.py` imports the `BGLU` and `LU` classes from `._bglu_dense` exactly as if they were regular Python classes. But they’re not. `BGLU` and `LU` are Cython classes defined in `/scipy/optimize/_bglu_dense.pyx`. There is nothing about the way they are imported or used that suggests that they are written in Cython; the only way so far that we can tell they are Cython classes is that they are defined in a file with a `.pyx` extension.

Even in `/scipy/optimize/_bglu_dense.pyx`, most of the code resembles Python. The most notable differences are the presence of `cimport`, `cdef`, and [Cython decorators](#). None of these are strictly necessary. Without them, the pure Python code can still be compiled by Cython. The Cython language extensions are *just* tweaks to improve performance. This `.pyx` file is automatically converted to a `.c` file by Cython when SciPy is built.

The only thing left is to add an extension from this `.c` file using `numpy.distutils`. This takes just a single line in `scipy/optimize/setup.py`: `config.add_extension('_bglu_dense',`

`sources=['_bglu_dense.c']`), `_bglu_dense.c` is the source and `_bglu_dense` is the name of the extension (for consistency). When SciPy is built, `_bglu_dense.c` will be compiled to machine code, and we will be able to import the LU and BGLU classes from the extension `_bglu_dense`.

5.18.2 Exercise

See a video run-through of this exercise: [Cythonizing SciPy Code](#)

1. Update Cython and create a new branch (e.g., `git checkout -b cython_test`) in which to make some experimental changes to SciPy
2. Add some simple Python code in a `.py` file in the `/scipy/optimize` directory, say `/scipy/optimize/mypython.py`. For example:

```
def myfun():
    i = 1
    while i < 10000000:
        i += 1
    return i
```

3. Let's see how long this pure-Python loop takes so we can compare the performance of Cython. For example, in an IPython console in Spyder:

```
from scipy.optimize.mypython import myfun
%timeit myfun()
```

I get something like:

```
715 ms ± 10.7 ms per loop
```

4. Save your `.py` file to a `.pyx` file, e.g. `mycython.pyx`.
5. Build SciPy. Note that a `.c` file has been added to the `/scipy/optimize` directory.
6. Somewhere near similar lines, add an extension from your `.c` file to `/scipy/optimize/setup.py`. e.g.:

```
config.add_extension('_group_columns', sources=['_group_columns.c'],) #_
→was already here
config.add_extension('mycython', sources=['mycython.c'],) # this was new
config.add_extension('_bglu_dense', sources=['_bglu_dense.c']) # was_
→already there
```

7. Rebuild SciPy. Note that a `.so` file has been added to the `/scipy/optimize` directory.
8. Time it:

```
from scipy.optimize.mycython import myfun
%timeit myfun()
```

I get something like:

```
359 ms ± 6.98 ms per loop
```

Cython sped up the pure Python code by a factor of ~2.

9. That's not much of an improvement in the scheme of things. To see why, it helps to have Cython create an "annotated" version of our code to show bottlenecks. In a terminal window, call Cython on your `.pyx` file with the `-a` flag:

```
cython -a scipy/optimize/mycython.pyx
```

Note that this creates a new `.html` file in the `/scipy/optimize` directory. Open the `.html` file in any browser.

- The yellow-highlighted lines in the file indicate potential interaction between the compiled code and Python, which slows things down considerably. The intensity of the highlighting indicates the estimated severity of the interaction. In this case, much of the interaction can be avoided if we define the variable `i` as an integer so that Cython doesn't have to consider the possibility of it being a general Python object:

```
def myfun():
    cdef int i = 1 # our first line of Cython code
    while i < 10000000:
        i += 1
    return i
```

Recreating the annotated `.html` file shows that most of the Python interaction has disappeared.

- Rebuild SciPy, open an fresh IPython console, and `%timeit`:

```
from scipy.optimize.mycython import myfun
%timeit myfun()
```

I get something like: `68.6 ns ± 1.95 ns per loop`. The Cython code ran about 10 million times faster than the original Python code.

In this case, the compiler probably optimized away the loop, simply returning the final result. This sort of speedup is not typical for real code, but this exercise certainly illustrates the power of Cython when the alternative is many low-level operations in Python.

5.19 Public Cython APIs

As of Apr 2020, the following modules in SciPy expose functionality via a public `cdef` Cython API declarations:

- `scipy.linalg.cython_blas`
- `scipy.linalg.cython_lapack`
- `scipy.optimize.cython_optimize`
- `scipy.special.cython_special`

This uses Cython's [declaration sharing features](#), where shared `cdef` items are declared in `*.pxd` files that are distributed together with the corresponding DLL/SO files in binary SciPy installations.

5.19.1 Application Binary Interface

Using these features in SciPy however requires SciPy contributors to take additional care with regard to maintaining Application Binary Interface (ABI) stability. This is similar to developing libraries in C, and different from how backward compatibility works in pure Python.

The main difference to Python originates from the fact that the declarations in the header `.pxd` files are used when code written by users is *compiled*, but they must also match with what is available in SciPy when the user code is *imported*.

User code may be compiled with one version of SciPy, and the compiled binary (which uses the binary interface declared in the `.pxd` files) can be used with a different SciPy version installed on the system. If the interfaces are not compatible, either an exception is raised or runtime memory corruption and crash ensue.

At import time, Cython checks that signatures of functions in the installed SciPy SO/DLL file match the one in the `.pxd` file used by the user during compilation, and raises a Python exception if there is a mismatch. If the SciPy code is structured correctly (see below), this check is performed only for functions that are actually imported in the user code.

We rely on this feature to provide a runtime safety check, which makes it easier for the users to detect incompatible SciPy versions via Python exceptions, instead of hard-to-trace runtime crashes.

5.19.2 ABI stability aim

SciPy aims to maintain ABI stability in Cython code, in the following sense:

Binaries produced by compiling user source with one version of SciPy, are compatible with any other SciPy version with which the source code can be compiled.

Trying to use an incompatible version of SciPy at runtime will result in a Python exception at user module import time.

Trying to use an incompatible version of SciPy at compile time will result in a Cython error.

This means that users can use any compatible version of SciPy to compile binaries without having to pay attention to ABI, i.e.,

ABI compatibility = API compatibility

Cython API backward/forward compatibility will be handled with a similar deprecation/removal policy as for the Python API, see *Deprecations*.

5.19.3 Implementing ABI stability in SciPy

The following rules in development of Cython APIs in SciPy are necessary to maintain the ABI stability aim above:

- Adding new `cdef` declarations (functions, structs, types, etc.) **is allowed**.
- Removing `cdef` declarations **is allowed**, but **should follow** general deprecation/removal policy.
- `cdef` declarations of functions **may be changed**.

However, changes result in a backward incompatible API change which breaks any code using the changed signature, and **should follow** general deprecation/removal policy.

- `cdef` declarations of anything else (e.g. `struct`, `enum`, and types) are **final**. Once a declaration is exposed in the public Cython API in a released SciPy version, **it must not be changed**.

If changes are necessary, they need to be carried out by adding new declarations with different names, and removing old ones.

- `cdef` classes are **not allowed** in the public APIs (TBD: backward compatibility of `cdef` classes needs more research, but must not be allowed when we are not sure)
- For each public API module (as in `scipy.linalg.cython_blas`), use a single interface `.pxd` declaration file.

The public interface declaration file **should not** contain `cimport` statements. If it does, Cython's signature check will check all of the `cimported` functions, not only the ones that are used by user code, so that changing one of them breaks the whole API.

- If data structures are necessary, **prefer opaque structs** in the public API. The interface declarations should not contain any declarations of struct members. Allocation, freeing, and attribute access of data structures should be done with functions.

5.19.4 Deprecating public Cython APIs

To deprecate a public Cython API function, for example:

```
# scipy/something/foo.pxd
cdef public int somefunc()

# scipy/something/foo.pyx
cdef public int somefunc():
    return 42
```

you can add use the `scipy._lib.deprecation.deprecate_cython_api` function to do the deprecations at the end of the corresponding `.pyx` file:

```
# scipy/something/foo.pyx
cdef public int somefunc():
    return 42

from scipy._lib.deprecation import deprecate_cython_api
import scipy.something.foo as mod
deprecate_cython_api(mod, "somefunc", new_name="scipy.something.newfunc",
                    message="Deprecated in Scipy 1.5.0")
del deprecate_cython_api, mod
```

After this, Cython modules that `cimport somefunc`, will emit a *DeprecationWarning* at import time.

There is no way to deprecate Cython data structures and types. They can be however removed after all functions using them in the API are removed, having gone through the deprecation cycle.

Whole Cython modules can be deprecated similarly as Python modules, by emitting a *DeprecationWarning* on the top-level.

5.20 Adding New Methods, Functions, and Classes

While adding code to SciPy is in most cases quite straight forward, there are a few places where that is not the case. This document contains detailed information on some specific situations where it may not be clear from the outset what is involved in the task.

5.20.1 Adding A New Statistics Distribution

For hundreds of years statisticians, mathematicians and scientists have needed to understand, analyze and model data. This has led to a plethora of statistics distributions, many of which are related to others. Modeling of new types of data continues to give rise to new distributions, as does theoretical considerations being applied to new disciplines. SciPy models about a dozen discrete distributions *Discrete Statistical Distributions* and 100 continuous distributions *Continuous Statistical Distributions*.

To add a new distribution, a good reference is needed. SciPy typically uses [JKB] as its gold standard, with Wikipedia distributions articles often providing some extra details and/or graphical plots.

How to create a new continuous distribution

There are a few steps to be done to add a continuous distribution to SciPy. (Adding a discrete distribution is similar). We'll use the fictitious “Squirrel” distribution in the instructions below.

Before Implementation

1. See if `Squirrel` has already been implemented (that saves a lot of effort!)
 - It may have been implemented with a different name.
 - It may have been implemented with a different parameterization (shape parameters).
 - It may be a specialization of a more general family of distributions.

It is very common for multiple disciplines to discover/rediscover a distribution (or a specialization or different parameterization). There are a few existing SciPy distributions which are specializations of other distributions. E.g. The `scipy.stats.arcsine` distribution is a specialization of the `scipy.stats.beta` distribution. These duplications exist for (very!) historical and widespread usage reasons. At this time, adding new specializations/reparameterizations of existing distributions to SciPy is not supported, mainly due to the increase in user confusion resulting from such additions.

2. Create a [SciPy Issue on github](#), listing the distribution, references and reasons for its inclusion.

Implementation

1. Find an already existing distribution similar to `Squirrel`. Use its code as a template for `Squirrel`.
2. Read the docstring for class `rv_continuous` in `scipy/stats/_distn_infrastructure.py`.
3. Write the new code for class `squirrel_gen` and insert it into `scipy/stats/_continuous_distns.py`, which is in (mostly) alphabetical order by distribution name.
4. Does the distribution have infinite support? If not, left and/or right endpoints `a`, `b` need to be specified in the call to `squirrel_gen(name='squirrel', a=?, b=?)`.
5. If the support depends upon the shape parameters, `squirrel_gen._get_support()` needs to be implemented.
6. The default inherited `_argcheck()` implementation checks that the shape parameters are positive. Create a more appropriate implementation.
7. If `squirrel_gen.ppf()` is expensive to compute relative to `squirrel_gen.pdf()`, consider setting the `momtype` in the call to `squirrel_gen()`.
8. If `squirrel_gen.rvs()` is expensive to compute, consider implementing a specific `squirrel_gen._rvs()`.
9. Add the name to the listing in the docstring of `scipy/stats/_init__.py`.
10. Add the name and a good set of example shape parameters to the `distcont` list in `scipy/stats/_distr_params.py`. These shape parameters are used both for testing and automatic documentation generation.
11. Add a `TestSquirrel` class and any specific tests to `scipy/stats/tests/test_distributions.py`.
12. Run and pass(!) the tests.

After Implementation

1. Add a tutorial `doc/source/tutorial/stats/continuous_squirrel.rst`
2. Add it to the listing of continuous distributions in `doc/source/tutorial/stats/continuous.rst`.
3. Update the number of continuous distributions in the example code in `doc/source/tutorial/stats.rst`.
4. Build the documentation successfully.
5. Submit a PR.

References

API REFERENCE

The exact API of all functions and classes, as given by the docstrings. The API documents expected types and allowed features for all functions, and all parameters available for the algorithms.

6.1 Clustering package (`scipy.cluster`)

scipy.cluster.vq

Clustering algorithms are useful in information theory, target detection, communications, compression, and other areas. The *vq* module only supports vector quantization and the k-means algorithms.

scipy.cluster.hierarchy

The *hierarchy* module provides functions for hierarchical and agglomerative clustering. Its features include generating hierarchical clusters from distance matrices, calculating statistics on clusters, cutting linkages to generate flat clusters, and visualizing clusters with dendrograms.

6.2 K-means clustering and vector quantization (`scipy.cluster.vq`)

Provides routines for k-means clustering, generating code books from k-means models and quantizing vectors by comparing them with centroids in a code book.

<i>whiten</i> (obs[, check_finite])	Normalize a group of observations on a per feature basis.
<i>vq</i> (obs, code_book[, check_finite])	Assign codes from a code book to observations.
<i>kmeans</i> (obs, k_or_guess[, iter, thresh, ...])	Performs k-means on a set of observation vectors forming k clusters.
<i>kmeans2</i> (data, k[, iter, thresh, minit, ...])	Classify a set of observations into k clusters using the k-means algorithm.

6.2.1 `scipy.cluster.vq.whiten`

`scipy.cluster.vq.whiten` (*obs*, *check_finite=True*)

Normalize a group of observations on a per feature basis.

Before running k-means, it is beneficial to rescale each feature dimension of the observation set by its standard deviation (i.e. “whiten” it - as in “white noise” where each frequency has equal power). Each feature is divided by its standard deviation across all observations to give it unit variance.

Parameters

obs [ndarray] Each row of the array is an observation. The columns are the features seen during each observation.

```
>>> #          f0      f1      f2
>>> obs = [[ 1.,    1.,    1.], #o0
...        [ 2.,    2.,    2.], #o1
...        [ 3.,    3.,    3.], #o2
...        [ 4.,    4.,    4.]] #o3
```

check_finite

[bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs. Default: True

Returns

result [ndarray] Contains the values in *obs* scaled by the standard deviation of each column.

Examples

```
>>> from scipy.cluster.vq import whiten
>>> features = np.array([[1.9, 2.3, 1.7],
...                     [1.5, 2.5, 2.2],
...                     [0.8, 0.6, 1.7]])
>>> whiten(features)
array([[ 4.17944278,  2.69811351,  7.21248917],
       [ 3.29956009,  2.93273208,  9.33380951],
       [ 1.75976538,  0.7038557 ,  7.21248917]])
```

6.2.2 `scipy.cluster.vq.vq`

`scipy.cluster.vq.vq` (*obs*, *code_book*, *check_finite=True*)

Assign codes from a code book to observations.

Assigns a code from a code book to each observation. Each observation vector in the ‘M’ by ‘N’ *obs* array is compared with the centroids in the code book and assigned the code of the closest centroid.

The features in *obs* should have unit variance, which can be achieved by passing them through the `whiten` function. The code book can be created with the k-means algorithm or a different encoding algorithm.

Parameters

obs [ndarray] Each row of the ‘M’ x ‘N’ array is an observation. The columns are the “features” seen during each observation. The features must be whitened first using the `whiten` function or something equivalent.

code_book

[ndarray] The code book is usually generated using the k-means algorithm. Each row of the array holds a different code, and the columns are the features of the code.

```
>>> #           f0      f1      f2      f3
>>> code_book = [
...           [ 1.,  2.,  3.,  4.], #c0
...           [ 1.,  2.,  3.,  4.], #c1
...           [ 1.,  2.,  3.,  4.]] #c2
```

check_finite

[bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs. Default: True

Returns

code [ndarray] A length M array holding the code book index for each observation.
dist [ndarray] The distortion (distance) between the observation and its nearest code.

Examples

```
>>> from numpy import array
>>> from scipy.cluster.vq import vq
>>> code_book = array([[1., 1., 1.],
...                  [2., 2., 2.]])
>>> features = array([[ 1.9, 2.3, 1.7],
...                  [ 1.5, 2.5, 2.2],
...                  [ 0.8, 0.6, 1.7]])
>>> vq(features, code_book)
(array([1, 1, 0], 'i'), array([ 0.43588989,  0.73484692,  0.83066239]))
```

6.2.3 scipy.cluster.vq.kmeans

`scipy.cluster.vq.kmeans` (*obs*, *k_or_guess*, *iter=20*, *thresh=1e-05*, *check_finite=True*)

Performs k-means on a set of observation vectors forming k clusters.

The k-means algorithm adjusts the classification of the observations into clusters and updates the cluster centroids until the position of the centroids is stable over successive iterations. In this implementation of the algorithm, the stability of the centroids is determined by comparing the absolute value of the change in the average Euclidean distance between the observations and their corresponding centroids against a threshold. This yields a code book mapping centroids to codes and vice versa.

Parameters

obs [ndarray] Each row of the M by N array is an observation vector. The columns are the features seen during each observation. The features must be whitened first with the `whiten` function.

k_or_guess

[int or ndarray] The number of centroids to generate. A code is assigned to each centroid, which is also the row index of the centroid in the code_book matrix generated. The initial k centroids are chosen by randomly selecting observations from the observation matrix. Alternatively, passing a k by N array specifies the initial k centroids.

- iter** [int, optional] The number of times to run k-means, returning the codebook with the lowest distortion. This argument is ignored if initial centroids are specified with an array for the `k_or_guess` parameter. This parameter does not represent the number of iterations of the k-means algorithm.
- thresh** [float, optional] Terminates the k-means algorithm if the change in distortion since the last k-means iteration is less than or equal to threshold.
- check_finite** [bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs. Default: True

Returns

- codebook** [ndarray] A k by N array of k centroids. The ith centroid codebook[i] is represented with the code i. The centroids and codes generated represent the lowest distortion seen, not necessarily the globally minimal distortion.
- distortion** [float] The mean (non-squared) Euclidean distance between the observations passed and the centroids generated. Note the difference to the standard definition of distortion in the context of the k-means algorithm, which is the sum of the squared distances.

See also:

kmeans2

a different implementation of k-means clustering with more methods for generating initial centroids but without using a distortion change threshold as a stopping criterion.

whiten

must be called prior to passing an observation matrix to kmeans.

Examples

```
>>> from numpy import array
>>> from scipy.cluster.vq import vq, kmeans, whiten
>>> import matplotlib.pyplot as plt
>>> features = array([[ 1.9, 2.3],
...                  [ 1.5, 2.5],
...                  [ 0.8, 0.6],
...                  [ 0.4, 1.8],
...                  [ 0.1, 0.1],
...                  [ 0.2, 1.8],
...                  [ 2.0, 0.5],
...                  [ 0.3, 1.5],
...                  [ 1.0, 1.0]])
>>> whitened = whiten(features)
>>> book = np.array((whitened[0], whitened[2]))
>>> kmeans(whitened, book)
(array([[ 2.3110306 ,  2.86287398],          # random
        [ 0.93218041,  1.24398691]]), 0.85684700941625547)
```


```
>>> from numpy import random
>>> random.seed((1000, 2000))
>>> codes = 3
>>> kmeans(whitened, codes)
```

(continues on next page)

(continued from previous page)

```
(array([[ 2.3110306 ,  2.86287398],      # random
        [ 1.32544402,  0.65607529],
        [ 0.40782893,  2.02786907]]), 0.5196582527686241)
```

```
>>> # Create 50 datapoints in two clusters a and b
>>> pts = 50
>>> a = np.random.multivariate_normal([0, 0], [[4, 1], [1, 4]], size=pts)
>>> b = np.random.multivariate_normal([30, 10],
...                                  [[10, 2], [2, 1]],
...                                  size=pts)
>>> features = np.concatenate((a, b))
>>> # Whiten data
>>> whitened = whiten(features)
>>> # Find 2 clusters in the data
>>> codebook, distortion = kmeans(whitened, 2)
>>> # Plot whitened data and cluster centers in red
>>> plt.scatter(whitened[:, 0], whitened[:, 1])
>>> plt.scatter(codebook[:, 0], codebook[:, 1], c='r')
>>> plt.show()
```



6.2.4 scipy.cluster.vq.kmeans2

```
scipy.cluster.vq.kmeans2(data, k, iter=10, thresh=1e-05, minit='random', missing='warn',
                          check_finite=True)
```

Classify a set of observations into k clusters using the k-means algorithm.

The algorithm attempts to minimize the Euclidean distance between observations and centroids. Several initialization methods are included.

Parameters

data [ndarray] A 'M' by 'N' array of 'M' observations in 'N' dimensions or a length 'M' array of 'M' 1-D observations.

k	[int or ndarray] The number of clusters to form as well as the number of centroids to generate. If <i>minit</i> initialization string is 'matrix', or if a ndarray is given instead, it is interpreted as initial cluster to use instead.
iter	[int, optional] Number of iterations of the k-means algorithm to run. Note that this differs in meaning from the iters parameter to the kmeans function.
thresh	[float, optional] (not used yet)
minit	[str, optional] Method for initialization. Available methods are 'random', 'points', '++' and 'matrix': 'random': generate k centroids from a Gaussian with mean and variance estimated from the data. 'points': choose k observations (rows) at random from data for the initial centroids. '++': choose k observations accordingly to the kmeans++ method (careful seeding) 'matrix': interpret the k parameter as a k by M (or length k array for 1-D data) array of initial centroids.
missing	[str, optional] Method to deal with empty clusters. Available methods are 'warn' and 'raise': 'warn': give a warning and continue. 'raise': raise an ClusterError and terminate the algorithm.
check_finite	[bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs. Default: True

Returns

centroid	[ndarray] A 'k' by 'N' array of centroids found at the last iteration of k-means.
label	[ndarray] label[i] is the code or index of the centroid the ith observation is closest to.

See also:

kmeans

References

[1]

Examples

```
>>> from scipy.cluster.vq import kmeans2
>>> import matplotlib.pyplot as plt
```

Create z, an array with shape (100, 2) containing a mixture of samples from three multivariate normal distributions.

```
>>> np.random.seed(12345678)
>>> a = np.random.multivariate_normal([0, 6], [[2, 1], [1, 1.5]], size=45)
>>> b = np.random.multivariate_normal([2, 0], [[1, -1], [-1, 3]], size=30)
>>> c = np.random.multivariate_normal([6, 4], [[5, 0], [0, 1.2]], size=25)
>>> z = np.concatenate((a, b, c))
>>> np.random.shuffle(z)
```

Compute three clusters.


```
>>> centroid, label = kmeans2(z, 3, minit='points')
>>> centroid
array([[ -0.35770296,  5.31342524],
       [ 2.32210289, -0.50551972],
       [ 6.17653859,  4.16719247]])
```

How many points are in each cluster?

```
>>> counts = np.bincount(label)
>>> counts
array([52, 27, 21])
```

Plot the clusters.

```
>>> w0 = z[label == 0]
>>> w1 = z[label == 1]
>>> w2 = z[label == 2]
>>> plt.plot(w0[:, 0], w0[:, 1], 'o', alpha=0.5, label='cluster 0')
>>> plt.plot(w1[:, 0], w1[:, 1], 'd', alpha=0.5, label='cluster 1')
>>> plt.plot(w2[:, 0], w2[:, 1], 's', alpha=0.5, label='cluster 2')
>>> plt.plot(centroid[:, 0], centroid[:, 1], 'k*', label='centroids')
>>> plt.axis('equal')
>>> plt.legend(shadow=True)
>>> plt.show()
```



6.2.5 Background information

The k-means algorithm takes as input the number of clusters to generate, k , and a set of observation vectors to cluster. It returns a set of centroids, one for each of the k clusters. An observation vector is classified with the cluster number or centroid index of the centroid closest to it.

A vector v belongs to cluster i if it is closer to centroid i than any other centroid. If v belongs to i , we say centroid i is the dominating centroid of v . The k-means algorithm tries to minimize distortion, which is defined as the sum of the squared distances between each observation vector and its dominating centroid. The minimization is achieved by iteratively reclassifying the observations into clusters and recalculating the centroids until a configuration is reached in which the centroids are stable. One can also define a maximum number of iterations.

Since vector quantization is a natural application for k-means, information theory terminology is often used. The centroid index or cluster index is also referred to as a “code” and the table mapping codes to centroids and, vice versa, is often referred to as a “code book”. The result of k-means, a set of centroids, can be used to quantize vectors. Quantization aims to find an encoding of vectors that reduces the expected distortion.

All routines expect `obs` to be an M by N array, where the rows are the observation vectors. The codebook is a k by N array, where the i th row is the centroid of code word i . The observation vectors and centroids have the same feature dimension.

As an example, suppose we wish to compress a 24-bit color image (each pixel is represented by one byte for red, one for blue, and one for green) before sending it over the web. By using a smaller 8-bit encoding, we can reduce the amount of data by two thirds. Ideally, the colors for each of the 256 possible 8-bit encoding values should be chosen to minimize distortion of the color. Running k-means with $k=256$ generates a code book of 256 codes, which fills up all possible 8-bit sequences. Instead of sending a 3-byte value for each pixel, the 8-bit centroid index (or code word) of the dominating centroid is transmitted. The code book is also sent over the wire so each 8-bit code can be translated back to a 24-bit pixel value representation. If the image of interest was of an ocean, we would expect many 24-bit blues to be represented by 8-bit codes. If it was an image of a human face, more flesh-tone colors would be represented in the code book.

6.3 Hierarchical clustering (`scipy.cluster.hierarchy`)

These functions cut hierarchical clusterings into flat clusterings or find the roots of the forest formed by a cut by providing the flat cluster ids of each observation.

<code>fcluster(Z, t[, criterion, depth, R, monocrit])</code>	Form flat clusters from the hierarchical clustering defined by the given linkage matrix.
<code>fclusterdata(X, t[, criterion, metric, ...])</code>	Cluster observation data using a given metric.
<code>leaders(Z, T)</code>	Return the root nodes in a hierarchical clustering.

6.3.1 `scipy.cluster.hierarchy.fcluster`

`scipy.cluster.hierarchy.fcluster` (Z , t , *criteria='inconsistent'*, *depth=2*, *R=None*, *monocrit=None*)

Form flat clusters from the hierarchical clustering defined by the given linkage matrix.

Parameters

- Z** [ndarray] The hierarchical clustering encoded with the matrix returned by the `linkage` function.
- t** [scalar] **For criteria ‘inconsistent’, ‘distance’ or ‘monocrit’,** this is the threshold to apply when forming flat clusters.

For ‘maxclust’ or ‘maxclust_monocrit’ criteria,

this would be max number of clusters requested.

criterion [str, optional] The criterion to use in forming flat clusters. This can be any of the following values:

inconsistent :

If a cluster node and all its descendants have an inconsistent value less than or equal to t , then all its leaf descendants belong to the same flat cluster. When no non-singleton cluster meets this criterion, every node is assigned to its own cluster. (Default)

distance :

Forms flat clusters so that the original observations in each flat cluster have no greater a cophenetic distance than t .

maxclust :

Finds a minimum threshold r so that the cophenetic distance between any two original observations in the same flat cluster is no more than r and no more than t flat clusters are formed.

monocrit :

Forms a flat cluster from a cluster node c with index i when `monocrit[j] <= t`.

For example, to threshold on the maximum mean distance as computed in the inconsistency matrix R with a threshold of 0.8 do:

```
MR = maxRstat(Z, R, 3)
fcluster(Z, t=0.8, criterion='monocrit',
        ↪monocrit=MR)
```

maxclust_monocrit :

Forms a flat cluster from a non-singleton cluster node c when `monocrit[i] <= r` for all cluster indices i below and including c . r is minimized such that no more than t flat clusters are formed. `monocrit` must be monotonic. For example, to minimize the threshold t on maximum inconsistency values so that no more than 3 flat clusters are formed, do:

```
MI = maxinconsts(Z, R)
fcluster(Z, t=3, criterion='maxclust_monocrit',
        ↪monocrit=MI)
```

depth [int, optional] The maximum depth to perform the inconsistency calculation. It has no meaning for the other criteria. Default is 2.

R [ndarray, optional] The inconsistency matrix to use for the ‘inconsistent’ criterion. This matrix is computed if not provided.

monocrit [ndarray, optional] An array of length $n-1$. `monocrit[i]` is the statistics upon which non-singleton i is thresholded. The `monocrit` vector must be monotonic, i.e., given a node c with index i , for all node indices j corresponding to nodes below c , `monocrit[i] >= monocrit[j]`.

Returns

fcluster [ndarray] An array of length n . `T[i]` is the flat cluster number to which original observation i belongs.

See also:

[linkage](#)

for information about hierarchical clustering methods work.

Examples

```
>>> from scipy.cluster.hierarchy import ward, fcluster
>>> from scipy.spatial.distance import pdist
```

All cluster linkage methods - e.g., `scipy.cluster.hierarchy.ward` generate a linkage matrix `Z` as their output:

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

```
>>> Z = ward(pdist(X))
```

```
>>> Z
array([[ 0.      ,  1.      ,  1.      ,  2.      ],
       [ 3.      ,  4.      ,  1.      ,  2.      ],
       [ 6.      ,  7.      ,  1.      ,  2.      ],
       [ 9.      , 10.      ,  1.      ,  2.      ],
       [ 2.      , 12.      , 1.29099445,  3.      ],
       [ 5.      , 13.      , 1.29099445,  3.      ],
       [ 8.      , 14.      , 1.29099445,  3.      ],
       [11.      , 15.      , 1.29099445,  3.      ],
       [16.      , 17.      , 5.77350269,  6.      ],
       [18.      , 19.      , 5.77350269,  6.      ],
       [20.      , 21.      , 8.16496581, 12.      ]])
```

This matrix represents a dendrogram, where the first and second elements are the two clusters merged at each step, the third element is the distance between these clusters, and the fourth element is the size of the new cluster - the number of original data points included.

`scipy.cluster.hierarchy.fcluster` can be used to flatten the dendrogram, obtaining as a result an assignment of the original data points to single clusters.

This assignment mostly depends on a distance threshold t - the maximum inter-cluster distance allowed:

```
>>> fcluster(Z, t=0.9, criterion='distance')
array([ 1,  2,  3,  4,  5,  6,  7,  8,  9, 10, 11, 12], dtype=int32)
```

```
>>> fcluster(Z, t=1.1, criterion='distance')
array([1, 1, 2, 3, 3, 4, 5, 5, 6, 7, 7, 8], dtype=int32)
```

```
>>> fcluster(Z, t=3, criterion='distance')
array([1, 1, 1, 2, 2, 2, 3, 3, 3, 4, 4, 4], dtype=int32)
```

```
>>> fcluster(Z, t=9, criterion='distance')
array([1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1], dtype=int32)
```

In the first case, the threshold t is too small to allow any two samples in the data to form a cluster, so 12 different clusters are returned.

In the second case, the threshold is large enough to allow the first 4 points to be merged with their nearest neighbors. So, here, only 8 clusters are returned.

The third case, with a much higher threshold, allows for up to 8 data points to be connected - so 4 clusters are returned here.

Lastly, the threshold of the fourth case is large enough to allow for all data points to be merged together - so a single cluster is returned.

6.3.2 `scipy.cluster.hierarchy.fclusterdata`

`scipy.cluster.hierarchy.fclusterdata` (*X*, *t*, *criterion*='inconsistent', *metric*='euclidean', *depth*=2, *method*='single', *R*=None)

Cluster observation data using a given metric.

Clusters the original observations in the *n*-by-*m* data matrix *X* (*n* observations in *m* dimensions), using the euclidean distance metric to calculate distances between original observations, performs hierarchical clustering using the single linkage algorithm, and forms flat clusters using the inconsistency method with *t* as the cut-off threshold.

A 1-D array *T* of length *n* is returned. *T*[*i*] is the index of the flat cluster to which the original observation *i* belongs.

Parameters

X	[(N, M) ndarray] N by M data matrix with N observations in M dimensions.
t	[scalar] For criteria 'inconsistent', 'distance' or 'monocrit', this is the threshold to apply when forming flat clusters. For 'maxclust' or 'maxclust_monocrit' criteria, this would be max number of clusters requested.
criterion	[str, optional] Specifies the criterion for forming flat clusters. Valid values are 'inconsistent' (default), 'distance', or 'maxclust' cluster formation algorithms. See <i>fcluster</i> for descriptions.
metric	[str or function, optional] The distance metric for calculating pairwise distances. See <i>distance.pdist</i> for descriptions and linkage to verify compatibility with the linkage method.
depth	[int, optional] The maximum depth for the inconsistency calculation. See <i>inconsistent</i> for more information.
method	[str, optional] The linkage method to use (single, complete, average, weighted, median centroid, ward). See <i>linkage</i> for more information. Default is "single".
R	[ndarray, optional] The inconsistency matrix. It will be computed if necessary if it is not passed.

Returns

fclusterdata	[ndarray] A vector of length <i>n</i> . <i>T</i> [<i>i</i>] is the flat cluster number to which original observation <i>i</i> belongs.
---------------------	--

See also:

[*scipy.spatial.distance.pdist*](#)

pairwise distance metrics

Notes

This function is similar to the MATLAB function `clusterdata`.

Examples

```
>>> from scipy.cluster.hierarchy import fclusterdata
```

This is a convenience method that abstracts all the steps to perform in a typical SciPy's hierarchical clustering workflow.

- Transform the input data into a condensed matrix with `scipy.spatial.distance.pdist`.
- Apply a clustering method.
- Obtain flat clusters at a user defined distance threshold t using `scipy.cluster.hierarchy.fcluster`.

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

```
>>> fclusterdata(X, t=1)
array([3, 3, 3, 4, 4, 4, 2, 2, 2, 1, 1, 1], dtype=int32)
```

The output here (for the dataset X , distance threshold t , and the default settings) is four clusters with three data points each.

6.3.3 `scipy.cluster.hierarchy.leaders`

`scipy.cluster.hierarchy.leaders` (Z, T)

Return the root nodes in a hierarchical clustering.

Returns the root nodes in a hierarchical clustering corresponding to a cut defined by a flat cluster assignment vector T . See the `fcluster` function for more information on the format of T .

For each flat cluster j of the k flat clusters represented in the n -sized flat cluster assignment vector T , this function finds the lowest cluster node i in the linkage tree Z , such that:

- leaf descendants belong only to flat cluster j (i.e., $T[p] == j$ for all p in $S(i)$, where $S(i)$ is the set of leaf ids of descendant leaf nodes with cluster node i)
- there does not exist a leaf that is not a descendant with i that also belongs to cluster j (i.e., $T[q] != j$ for all q not in $S(i)$). If this condition is violated, T is not a valid cluster assignment vector, and an exception will be thrown.

Parameters

- | | |
|----------|---|
| Z | [ndarray] The hierarchical clustering encoded as a matrix. See <code>linkage</code> for more information. |
| T | [ndarray] The flat cluster assignment vector. |

Returns

- L** [ndarray] The leader linkage node id's stored as a k-element 1-D array, where k is the number of flat clusters found in T.
 $L[j]=i$ is the linkage cluster node id that is the leader of flat cluster with id $M[j]$. If $i < n$, i corresponds to an original observation, otherwise it corresponds to a non-singleton cluster.
- M** [ndarray] The leader linkage node id's stored as a k-element 1-D array, where k is the number of flat clusters found in T. This allows the set of flat cluster ids to be any arbitrary set of k integers.
 For example: if $L[3]=2$ and $M[3]=8$, the flat cluster with id 8's leader is linkage node 2.

See also:

fcluster

for the creation of flat cluster assignments.

Examples

```
>>> from scipy.cluster.hierarchy import ward, fcluster, leaders
>>> from scipy.spatial.distance import pdist
```

Given a linkage matrix Z - obtained after apply a clustering method to a dataset X - and a flat cluster assignment array T:

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

```
>>> Z = ward(pdist(X))
>>> Z
array([[ 0.         ,  1.         ,  1.         ,  2.         ],
       [ 3.         ,  4.         ,  1.         ,  2.         ],
       [ 6.         ,  7.         ,  1.         ,  2.         ],
       [ 9.         , 10.         ,  1.         ,  2.         ],
       [ 2.         , 12.         , 1.29099445,  3.         ],
       [ 5.         , 13.         , 1.29099445,  3.         ],
       [ 8.         , 14.         , 1.29099445,  3.         ],
       [11.         , 15.         , 1.29099445,  3.         ],
       [16.         , 17.         , 5.77350269,  6.         ],
       [18.         , 19.         , 5.77350269,  6.         ],
       [20.         , 21.         , 8.16496581, 12.         ]])
```

```
>>> T = fcluster(Z, 3, criterion='distance')
>>> T
array([1, 1, 1, 2, 2, 2, 3, 3, 3, 4, 4, 4], dtype=int32)
```

scipy.cluster.hierarchy.leaders returns the indices of the nodes in the dendrogram that are the leaders of each flat cluster:

```
>>> L, M = leaders(Z, T)
>>> L
array([16, 17, 18, 19], dtype=int32)
```

(remember that indices 0-11 point to the 12 data points in X, whereas indices 12-22 point to the 11 rows of Z)

`scipy.cluster.hierarchy.leaders` also returns the indices of the flat clusters in T:

```
>>> M
array([1, 2, 3, 4], dtype=int32)
```

These are routines for agglomerative clustering.

<code>linkage(y[, method, metric, optimal_ordering])</code>	Perform hierarchical/agglomerative clustering.
<code>single(y)</code>	Perform single/min/nearest linkage on the condensed distance matrix <i>y</i> .
<code>complete(y)</code>	Perform complete/max/farthest point linkage on a condensed distance matrix.
<code>average(y)</code>	Perform average/UPGMA linkage on a condensed distance matrix.
<code>weighted(y)</code>	Perform weighted/WPGMA linkage on the condensed distance matrix.
<code>centroid(y)</code>	Perform centroid/UPGMC linkage.
<code>median(y)</code>	Perform median/WPGMC linkage.
<code>ward(y)</code>	Perform Ward's linkage on a condensed distance matrix.

6.3.4 `scipy.cluster.hierarchy.linkage`

`scipy.cluster.hierarchy.linkage` (*y*, *method*='single', *metric*='euclidean', *optimal_ordering*=False)

Perform hierarchical/agglomerative clustering.

The input *y* may be either a 1-D condensed distance matrix or a 2-D array of observation vectors.

If *y* is a 1-D condensed distance matrix, then *y* must be a $\binom{n}{2}$ sized vector, where *n* is the number of original observations paired in the distance matrix. The behavior of this function is very similar to the MATLAB linkage function.

A $(n - 1)$ by 4 matrix *Z* is returned. At the *i*-th iteration, clusters with indices *Z*[*i*, 0] and *Z*[*i*, 1] are combined to form cluster *n + i*. A cluster with an index less than *n* corresponds to one of the *n* original observations. The distance between clusters *Z*[*i*, 0] and *Z*[*i*, 1] is given by *Z*[*i*, 2]. The fourth value *Z*[*i*, 3] represents the number of original observations in the newly formed cluster.

The following linkage methods are used to compute the distance $d(s, t)$ between two clusters *s* and *t*. The algorithm begins with a forest of clusters that have yet to be used in the hierarchy being formed. When two clusters *s* and *t* from this forest are combined into a single cluster *u*, *s* and *t* are removed from the forest, and *u* is added to the forest. When only one cluster remains in the forest, the algorithm stops, and this cluster becomes the root.

A distance matrix is maintained at each iteration. The *d*[*i*, *j*] entry corresponds to the distance between cluster *i* and *j* in the original forest.

At each iteration, the algorithm must update the distance matrix to reflect the distance of the newly formed cluster *u* with the remaining clusters in the forest.

Suppose there are $|u|$ original observations $u[0], \dots, u[|u| - 1]$ in cluster *u* and $|v|$ original objects $v[0], \dots, v[|v| - 1]$ in cluster *v*. Recall, *s* and *t* are combined to form cluster *u*. Let *v* be any remaining cluster in the forest that is not *u*.

The following are methods for calculating the distance between the newly formed cluster *u* and each *v*.

- `method='single'` assigns

$$d(u, v) = \min(\text{dist}(u[i], v[j]))$$

for all points i in cluster u and j in cluster v . This is also known as the Nearest Point Algorithm.

- `method='complete'` assigns

$$d(u, v) = \max(\text{dist}(u[i], v[j]))$$

for all points i in cluster u and j in cluster v . This is also known by the Farthest Point Algorithm or Voor Hees Algorithm.

- `method='average'` assigns

$$d(u, v) = \sum_{ij} \frac{d(u[i], v[j])}{(|u| * |v|)}$$

for all points i and j where $|u|$ and $|v|$ are the cardinalities of clusters u and v , respectively. This is also called the UPGMA algorithm.

- `method='weighted'` assigns

$$d(u, v) = (\text{dist}(s, v) + \text{dist}(t, v))/2$$

where cluster u was formed with cluster s and t and v is a remaining cluster in the forest (also called WPGMA).

- `method='centroid'` assigns

$$\text{dist}(s, t) = \|c_s - c_t\|_2$$

where c_s and c_t are the centroids of clusters s and t , respectively. When two clusters s and t are combined into a new cluster u , the new centroid is computed over all the original objects in clusters s and t . The distance then becomes the Euclidean distance between the centroid of u and the centroid of a remaining cluster v in the forest. This is also known as the UPGMC algorithm.

- `method='median'` assigns $d(s, t)$ like the `centroid` method. When two clusters s and t are combined into a new cluster u , the average of centroids s and t give the new centroid u . This is also known as the WPGMC algorithm.
- `method='ward'` uses the Ward variance minimization algorithm. The new entry $d(u, v)$ is computed as follows,

$$d(u, v) = \sqrt{\frac{|v| + |s|}{T} d(v, s)^2 + \frac{|v| + |t|}{T} d(v, t)^2 - \frac{|v|}{T} d(s, t)^2}$$

where u is the newly joined cluster consisting of clusters s and t , v is an unused cluster in the forest, $T = |v| + |s| + |t|$, and $|*|$ is the cardinality of its argument. This is also known as the incremental algorithm.

Warning: When the minimum distance pair in the forest is chosen, there may be two or more pairs with the same minimum distance. This implementation may choose a different minimum than the MATLAB version.

Parameters

- | | |
|---------------|--|
| y | [ndarray] A condensed distance matrix. A condensed distance matrix is a flat array containing the upper triangular of the distance matrix. This is the form that <code>pdist</code> returns. Alternatively, a collection of m observation vectors in n dimensions may be passed as an m by n array. All elements of the condensed distance matrix must be finite, i.e., no NaNs or infs. |
| method | [str, optional] The linkage algorithm to use. See the <code>Linkage Methods</code> section below for full descriptions. |
| metric | [str or function, optional] The distance metric to use in the case that <code>y</code> is a collection of observation vectors; ignored otherwise. See the <code>pdist</code> function for a list of valid distance metrics. A custom distance function can also be used. |

optimal_ordering

[bool, optional] If True, the linkage matrix will be reordered so that the distance between successive leaves is minimal. This results in a more intuitive tree structure when the data are visualized. defaults to False, because this algorithm can be slow, particularly on large datasets [2]. See also the *optimal_leaf_ordering* function.
New in version 1.0.0.

Returns

Z [ndarray] The hierarchical clustering encoded as a linkage matrix.

See also:

scipy.spatial.distance.pdist

pairwise distance metrics

Notes

1. For method 'single', an optimized algorithm based on minimum spanning tree is implemented. It has time complexity $O(n^2)$. For methods 'complete', 'average', 'weighted' and 'ward', an algorithm called nearest-neighbors chain is implemented. It also has time complexity $O(n^2)$. For other methods, a naive algorithm is implemented with $O(n^3)$ time complexity. All algorithms use $O(n^2)$ memory. Refer to [1] for details about the algorithms.
2. Methods 'centroid', 'median', and 'ward' are correctly defined only if Euclidean pairwise metric is used. If *y* is passed as precomputed pairwise distances, then it is the user's responsibility to assure that these distances are in fact Euclidean, otherwise the produced result will be incorrect.

References



[1], [2]

Examples

```
>>> from scipy.cluster.hierarchy import dendrogram, linkage
>>> from matplotlib import pyplot as plt
>>> X = [[i] for i in [2, 8, 0, 4, 1, 9, 9, 0]]
```

```
>>> Z = linkage(X, 'ward')
>>> fig = plt.figure(figsize=(25, 10))
>>> dn = dendrogram(Z)
```

```
>>> Z = linkage(X, 'single')
>>> fig = plt.figure(figsize=(25, 10))
>>> dn = dendrogram(Z)
>>> plt.show()
```

6.3.5 `scipy.cluster.hierarchy.single`

`scipy.cluster.hierarchy.single`(*y*)

Perform single/min/nearest linkage on the condensed distance matrix *y*.

Parameters

y [ndarray] The upper triangular of the distance matrix. The result of `pdist` is returned in this form.

Returns

Z [ndarray] The linkage matrix.

See also:

[`linkage`](#)

for advanced creation of hierarchical clusterings.

[`scipy.spatial.distance.pdist`](#)

pairwise distance metrics

Examples

```
>>> from scipy.cluster.hierarchy import single, fcluster
>>> from scipy.spatial.distance import pdist
```

First, we need a toy dataset to play with:

```
x x    x x
x      x

x      x
x x    x x
```

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

Then, we get a condensed distance matrix from this dataset:

```
>>> y = pdist(X)
```

Finally, we can perform the clustering:

```
>>> Z = single(y)
>>> Z
array([[ 0.,  1.,  1.,  2.],
       [ 2., 12.,  1.,  3.],
       [ 3.,  4.,  1.,  2.],
       [ 5., 14.,  1.,  3.],
       [ 6.,  7.,  1.,  2.],
       [ 8., 16.,  1.,  3.]])
```

(continues on next page)

(continued from previous page)

```
[ 9., 10., 1., 2.],
 [11., 18., 1., 3.],
 [13., 15., 2., 6.],
 [17., 20., 2., 9.],
 [19., 21., 2., 12.]])
```

The linkage matrix *Z* represents a dendrogram - see `scipy.cluster.hierarchy.linkage` for a detailed explanation of its contents.

We can use `scipy.cluster.hierarchy.fcluster` to see to which cluster each initial point would belong given a distance threshold:

```
>>> fcluster(Z, 0.9, criterion='distance')
array([ 7,  8,  9, 10, 11, 12,  4,  5,  6,  1,  2,  3], dtype=int32)
>>> fcluster(Z, 1, criterion='distance')
array([3, 3, 3, 4, 4, 4, 2, 2, 2, 1, 1, 1], dtype=int32)
>>> fcluster(Z, 2, criterion='distance')
array([1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1], dtype=int32)
```

Also, `scipy.cluster.hierarchy.dendrogram` can be used to generate a plot of the dendrogram.

6.3.6 `scipy.cluster.hierarchy.complete`

`scipy.cluster.hierarchy.complete`(*y*)

Perform complete/max/farthest point linkage on a condensed distance matrix.

Parameters

y [ndarray] The upper triangular of the distance matrix. The result of `pdist` is returned in this form.

Returns

Z [ndarray] A linkage matrix containing the hierarchical clustering. See the `linkage` function documentation for more information on its structure.

See also:

`linkage`

for advanced creation of hierarchical clusterings.

`scipy.spatial.distance.pdist`

pairwise distance metrics

Examples

```
>>> from scipy.cluster.hierarchy import complete, fcluster
>>> from scipy.spatial.distance import pdist
```

First, we need a toy dataset to play with:

```
x x    x x
x      x

x      x
x x    x x
```

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

Then, we get a condensed distance matrix from this dataset:

```
>>> y = pdist(X)
```

Finally, we can perform the clustering:

```
>>> Z = complete(y)
>>> Z
array([[ 0.          ,  1.          ,  1.          ,  2.          ],
       [ 3.          ,  4.          ,  1.          ,  2.          ],
       [ 6.          ,  7.          ,  1.          ,  2.          ],
       [ 9.          , 10.          ,  1.          ,  2.          ],
       [ 2.          , 12.          , 1.41421356,  3.          ],
       [ 5.          , 13.          , 1.41421356,  3.          ],
       [ 8.          , 14.          , 1.41421356,  3.          ],
       [11.          , 15.          , 1.41421356,  3.          ],
       [16.          , 17.          , 4.12310563,  6.          ],
       [18.          , 19.          , 4.12310563,  6.          ],
       [20.          , 21.          , 5.65685425, 12.          ]])
```

The linkage matrix `Z` represents a dendrogram - see [scipy.cluster.hierarchy.linkage](#) for a detailed explanation of its contents.

We can use [scipy.cluster.hierarchy.fcluster](#) to see to which cluster each initial point would belong given a distance threshold:

```
>>> fcluster(Z, 0.9, criterion='distance')
array([ 1,  2,  3,  4,  5,  6,  7,  8,  9, 10, 11, 12], dtype=int32)
>>> fcluster(Z, 1.5, criterion='distance')
array([1, 1, 1, 2, 2, 2, 3, 3, 3, 4, 4, 4], dtype=int32)
>>> fcluster(Z, 4.5, criterion='distance')
array([1, 1, 1, 1, 1, 1, 2, 2, 2, 2, 2, 2], dtype=int32)
>>> fcluster(Z, 6, criterion='distance')
array([1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1], dtype=int32)
```

Also, [scipy.cluster.hierarchy.dendrogram](#) can be used to generate a plot of the dendrogram.

6.3.7 `scipy.cluster.hierarchy.average`

`scipy.cluster.hierarchy.average` (*y*)

Perform average/UPGMA linkage on a condensed distance matrix.

Parameters

y [ndarray] The upper triangular of the distance matrix. The result of `pdist` is returned in this form.

Returns

Z [ndarray] A linkage matrix containing the hierarchical clustering. See [linkage](#) for more information on its structure.

See also:

[linkage](#)

for advanced creation of hierarchical clusterings.

[scipy.spatial.distance.pdist](#)

pairwise distance metrics

Examples

```
>>> from scipy.cluster.hierarchy import average, fcluster
>>> from scipy.spatial.distance import pdist
```

First, we need a toy dataset to play with:

```
x x    x x
x      x

x      x
x x    x x
```

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

Then, we get a condensed distance matrix from this dataset:

```
>>> y = pdist(X)
```

Finally, we can perform the clustering:

```
>>> Z = average(y)
>>> Z
array([[ 0.         ,  1.         ,  1.         ,  2.         ],
       [ 3.         ,  4.         ,  1.         ,  2.         ],
       [ 6.         ,  7.         ,  1.         ,  2.         ],
       [ 9.         , 10.         ,  1.         ,  2.         ],
       [ 2.         , 12.         ,  1.20710678,  3.         ]]
```

(continues on next page)

(continued from previous page)

```
[ 5.      , 13.      , 1.20710678, 3.      ],
[ 8.      , 14.      , 1.20710678, 3.      ],
[11.     , 15.     , 1.20710678, 3.      ],
[16.     , 17.     , 3.39675184, 6.      ],
[18.     , 19.     , 3.39675184, 6.      ],
[20.     , 21.     , 4.09206523, 12.     ]]
```

The linkage matrix *Z* represents a dendrogram - see `scipy.cluster.hierarchy.linkage` for a detailed explanation of its contents.

We can use `scipy.cluster.hierarchy.fcluster` to see to which cluster each initial point would belong given a distance threshold:

```
>>> fcluster(Z, 0.9, criterion='distance')
array([ 1,  2,  3,  4,  5,  6,  7,  8,  9, 10, 11, 12], dtype=int32)
>>> fcluster(Z, 1.5, criterion='distance')
array([1, 1, 1, 2, 2, 2, 3, 3, 3, 4, 4, 4], dtype=int32)
>>> fcluster(Z, 4, criterion='distance')
array([1, 1, 1, 1, 1, 1, 2, 2, 2, 2, 2, 2], dtype=int32)
>>> fcluster(Z, 6, criterion='distance')
array([1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1], dtype=int32)
```

Also, `scipy.cluster.hierarchy.dendrogram` can be used to generate a plot of the dendrogram.

6.3.8 `scipy.cluster.hierarchy.weighted`

`scipy.cluster.hierarchy.weighted`(*y*)

Perform weighted/WPGMA linkage on the condensed distance matrix.

See `linkage` for more information on the return structure and algorithm.

Parameters

y [ndarray] The upper triangular of the distance matrix. The result of `pdist` is returned in this form.

Returns

Z [ndarray] A linkage matrix containing the hierarchical clustering. See `linkage` for more information on its structure.

See also:

`linkage`

for advanced creation of hierarchical clusterings.

`scipy.spatial.distance.pdist`

pairwise distance metrics

Examples

```
>>> from scipy.cluster.hierarchy import weighted, fcluster
>>> from scipy.spatial.distance import pdist
```

First, we need a toy dataset to play with:

```
x x    x x
x      x

x      x
x x    x x
```

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

Then, we get a condensed distance matrix from this dataset:

```
>>> y = pdist(X)
```

Finally, we can perform the clustering:

```
>>> Z = weighted(y)
>>> Z
array([[ 0.          ,  1.          ,  1.          ,  2.          ],
       [ 6.          ,  7.          ,  1.          ,  2.          ],
       [ 3.          ,  4.          ,  1.          ,  2.          ],
       [ 9.          , 11.          ,  1.          ,  2.          ],
       [ 2.          , 12.          , 1.20710678,  3.          ],
       [ 8.          , 13.          , 1.20710678,  3.          ],
       [ 5.          , 14.          , 1.20710678,  3.          ],
       [10.          , 15.          , 1.20710678,  3.          ],
       [18.          , 19.          , 3.05595762,  6.          ],
       [16.          , 17.          , 3.32379407,  6.          ],
       [20.          , 21.          , 4.06357713, 12.          ]])
```

The linkage matrix `Z` represents a dendrogram - see `scipy.cluster.hierarchy.linkage` for a detailed explanation of its contents.

We can use `scipy.cluster.hierarchy.fcluster` to see to which cluster each initial point would belong given a distance threshold:

```
>>> fcluster(Z, 0.9, criterion='distance')
array([ 7,  8,  9,  1,  2,  3, 10, 11, 12,  4,  6,  5], dtype=int32)
>>> fcluster(Z, 1.5, criterion='distance')
array([3, 3, 3, 1, 1, 1, 4, 4, 4, 2, 2, 2], dtype=int32)
>>> fcluster(Z, 4, criterion='distance')
array([2, 2, 2, 1, 1, 1, 2, 2, 2, 1, 1, 1], dtype=int32)
>>> fcluster(Z, 6, criterion='distance')
array([1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1], dtype=int32)
```

Also, `scipy.cluster.hierarchy.dendrogram` can be used to generate a plot of the dendrogram.

6.3.9 `scipy.cluster.hierarchy.centroid`

`scipy.cluster.hierarchy.centroid`(*y*)

Perform centroid/UPGMC linkage.

See [linkage](#) for more information on the input matrix, return structure, and algorithm.

The following are common calling conventions:

1. `Z = centroid(y)`

Performs centroid/UPGMC linkage on the condensed distance matrix *y*.

2. `Z = centroid(X)`

Performs centroid/UPGMC linkage on the observation matrix *X* using Euclidean distance as the distance metric.

Parameters

y [ndarray] A condensed distance matrix. A condensed distance matrix is a flat array containing the upper triangular of the distance matrix. This is the form that `pdist` returns. Alternatively, a collection of *m* observation vectors in *n* dimensions may be passed as an *m* by *n* array.

Returns

Z [ndarray] A linkage matrix containing the hierarchical clustering. See the [linkage](#) function documentation for more information on its structure.

See also:

[linkage](#)

for advanced creation of hierarchical clusterings.

[scipy.spatial.distance.pdist](#)

pairwise distance metrics

Examples

```
>>> from scipy.cluster.hierarchy import centroid, fcluster
>>> from scipy.spatial.distance import pdist
```

First, we need a toy dataset to play with:

```
x x    x x
x      x

x      x
x x    x x
```

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

Then, we get a condensed distance matrix from this dataset:


```
>>> y = pdist(X)
```

Finally, we can perform the clustering:

```
>>> Z = centroid(y)
>>> Z
array([[ 0.          ,  1.          ,  1.          ,  2.          ],
       [ 3.          ,  4.          ,  1.          ,  2.          ],
       [ 9.          , 10.          ,  1.          ,  2.          ],
       [ 6.          ,  7.          ,  1.          ,  2.          ],
       [ 2.          , 12.          ,  1.11803399,  3.          ],
       [ 5.          , 13.          ,  1.11803399,  3.          ],
       [ 8.          , 15.          ,  1.11803399,  3.          ],
       [11.          , 14.          ,  1.11803399,  3.          ],
       [18.          , 19.          ,  3.33333333,  6.          ],
       [16.          , 17.          ,  3.33333333,  6.          ],
       [20.          , 21.          ,  3.33333333, 12.          ]])
```

The linkage matrix `Z` represents a dendrogram - see [scipy.cluster.hierarchy.linkage](#) for a detailed explanation of its contents.

We can use [scipy.cluster.hierarchy.fcluster](#) to see to which cluster each initial point would belong given a distance threshold:

```
>>> fcluster(Z, 0.9, criterion='distance')
array([ 7,  8,  9, 10, 11, 12,  1,  2,  3,  4,  5,  6], dtype=int32)
>>> fcluster(Z, 1.1, criterion='distance')
array([5,  5,  6,  7,  7,  8,  1,  1,  2,  3,  3,  4], dtype=int32)
>>> fcluster(Z, 2, criterion='distance')
array([3,  3,  3,  4,  4,  4,  1,  1,  1,  2,  2,  2], dtype=int32)
>>> fcluster(Z, 4, criterion='distance')
array([1,  1,  1,  1,  1,  1,  1,  1,  1,  1,  1,  1], dtype=int32)
```

Also, [scipy.cluster.hierarchy.dendrogram](#) can be used to generate a plot of the dendrogram.

6.3.10 scipy.cluster.hierarchy.median

`scipy.cluster.hierarchy.median`(`y`)

Perform median/WPGMC linkage.

See [linkage](#) for more information on the return structure and algorithm.

The following are common calling conventions:

1. `Z = median(y)`
Performs median/WPGMC linkage on the condensed distance matrix `y`. See [linkage](#) for more information on the return structure and algorithm.
2. `Z = median(X)`
Performs median/WPGMC linkage on the observation matrix `X` using Euclidean distance as the distance metric. See [linkage](#) for more information on the return structure and algorithm.

Parameters

`y` [ndarray] A condensed distance matrix. A condensed distance matrix is a flat array containing the upper triangular of the distance matrix. This is the form that `pdist` returns.

Alternatively, a collection of m observation vectors in n dimensions may be passed as an m by n array.

Returns

Z [ndarray] The hierarchical clustering encoded as a linkage matrix.

See also:

linkage

for advanced creation of hierarchical clusterings.

scipy.spatial.distance.pdist

pairwise distance metrics

Examples

```
>>> from scipy.cluster.hierarchy import median, fcluster
>>> from scipy.spatial.distance import pdist
```

First, we need a toy dataset to play with:

```
x x      x x
x         x

x         x
x x      x x
```

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

Then, we get a condensed distance matrix from this dataset:

```
>>> y = pdist(X)
```

Finally, we can perform the clustering:

```
>>> Z = median(y)
>>> Z
array([[ 0.          ,  1.          ,  1.          ,  2.          ],
       [ 3.          ,  4.          ,  1.          ,  2.          ],
       [ 9.          , 10.          ,  1.          ,  2.          ],
       [ 6.          ,  7.          ,  1.          ,  2.          ],
       [ 2.          , 12.          , 1.11803399,  3.          ],
       [ 5.          , 13.          , 1.11803399,  3.          ],
       [ 8.          , 15.          , 1.11803399,  3.          ],
       [11.          , 14.          , 1.11803399,  3.          ],
       [18.          , 19.          ,  3.          ,  6.          ],
       [16.          , 17.          ,  3.5         ,  6.          ],
       [20.          , 21.          ,  3.25        , 12.          ]])
```

The linkage matrix `Z` represents a dendrogram - see `scipy.cluster.hierarchy.linkage` for a detailed explanation of its contents.

We can use `scipy.cluster.hierarchy.fcluster` to see to which cluster each initial point would belong given a distance threshold:

```
>>> fcluster(Z, 0.9, criterion='distance')
array([ 7,  8,  9, 10, 11, 12,  1,  2,  3,  4,  5,  6], dtype=int32)
>>> fcluster(Z, 1.1, criterion='distance')
array([5,  5,  6,  7,  7,  8,  1,  1,  2,  3,  3,  4], dtype=int32)
>>> fcluster(Z, 2, criterion='distance')
array([3,  3,  3,  4,  4,  4,  1,  1,  1,  2,  2,  2], dtype=int32)
>>> fcluster(Z, 4, criterion='distance')
array([1,  1,  1,  1,  1,  1,  1,  1,  1,  1,  1,  1], dtype=int32)
```

Also, `scipy.cluster.hierarchy.dendrogram` can be used to generate a plot of the dendrogram.

6.3.11 `scipy.cluster.hierarchy.ward`

`scipy.cluster.hierarchy.ward`(`y`)

Perform Ward's linkage on a condensed distance matrix.

See `linkage` for more information on the return structure and algorithm.

The following are common calling conventions:

1. `Z = ward(y)` Performs Ward's linkage on the condensed distance matrix `y`.
2. `Z = ward(X)` Performs Ward's linkage on the observation matrix `X` using Euclidean distance as the distance metric.

Parameters

y [ndarray] A condensed distance matrix. A condensed distance matrix is a flat array containing the upper triangular of the distance matrix. This is the form that `pdist` returns. Alternatively, a collection of `m` observation vectors in `n` dimensions may be passed as an `m` by `n` array.

Returns

Z [ndarray] The hierarchical clustering encoded as a linkage matrix. See `linkage` for more information on the return structure and algorithm.

See also:

`linkage`

for advanced creation of hierarchical clusterings.

`scipy.spatial.distance.pdist`

pairwise distance metrics

Examples

```
>>> from scipy.cluster.hierarchy import ward, fcluster
>>> from scipy.spatial.distance import pdist
```

First, we need a toy dataset to play with:

```
x x    x x
x      x

x      x
x x    x x
```

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

Then, we get a condensed distance matrix from this dataset:

```
>>> y = pdist(X)
```

Finally, we can perform the clustering:

```
>>> Z = ward(y)
>>> Z
array([[ 0.          ,  1.          ,  1.          ,  2.          ],
       [ 3.          ,  4.          ,  1.          ,  2.          ],
       [ 6.          ,  7.          ,  1.          ,  2.          ],
       [ 9.          , 10.          ,  1.          ,  2.          ],
       [ 2.          , 12.          , 1.29099445,  3.          ],
       [ 5.          , 13.          , 1.29099445,  3.          ],
       [ 8.          , 14.          , 1.29099445,  3.          ],
       [11.         , 15.          , 1.29099445,  3.          ],
       [16.         , 17.          , 5.77350269,  6.          ],
       [18.         , 19.          , 5.77350269,  6.          ],
       [20.         , 21.          , 8.16496581, 12.          ]])
```

The linkage matrix `Z` represents a dendrogram - see `scipy.cluster.hierarchy.linkage` for a detailed explanation of its contents.

We can use `scipy.cluster.hierarchy.fcluster` to see to which cluster each initial point would belong given a distance threshold:

```
>>> fcluster(Z, 0.9, criterion='distance')
array([ 1,  2,  3,  4,  5,  6,  7,  8,  9, 10, 11, 12], dtype=int32)
>>> fcluster(Z, 1.1, criterion='distance')
array([1, 1, 2, 3, 3, 4, 5, 5, 6, 7, 7, 8], dtype=int32)
>>> fcluster(Z, 3, criterion='distance')
array([1, 1, 1, 2, 2, 2, 3, 3, 3, 4, 4, 4], dtype=int32)
>>> fcluster(Z, 9, criterion='distance')
array([1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1], dtype=int32)
```

Also, `scipy.cluster.hierarchy.dendrogram` can be used to generate a plot of the dendrogram.

These routines compute statistics on hierarchies.

<code>cophenet(Z[, Y])</code>	Calculate the cophenetic distances between each observation in the hierarchical clustering defined by the linkage <code>Z</code> .
<code>from_mlab_linkage(Z)</code>	Convert a linkage matrix generated by MATLAB(TM) to a new linkage matrix compatible with this module.
<code>inconsistent(Z[, d])</code>	Calculate inconsistency statistics on a linkage matrix.
<code>maxinconsts(Z, R)</code>	Return the maximum inconsistency coefficient for each non-singleton cluster and its children.
<code>maxdists(Z)</code>	Return the maximum distance between any non-singleton cluster.
<code>maxRstat(Z, R, i)</code>	Return the maximum statistic for each non-singleton cluster and its children.
<code>to_mlab_linkage(Z)</code>	Convert a linkage matrix to a MATLAB(TM) compatible one.

6.3.12 `scipy.cluster.hierarchy.cophenet`

`scipy.cluster.hierarchy.cophenet` (`Z`, `Y=None`)

Calculate the cophenetic distances between each observation in the hierarchical clustering defined by the linkage `Z`.

Suppose `p` and `q` are original observations in disjoint clusters `s` and `t`, respectively and `s` and `t` are joined by a direct parent cluster `u`. The cophenetic distance between observations `i` and `j` is simply the distance between clusters `s` and `t`.

Parameters

- Z** [ndarray] The hierarchical clustering encoded as an array (see `linkage` function).
- Y** [ndarray (optional)] Calculates the cophenetic correlation coefficient `c` of a hierarchical clustering defined by the linkage matrix `Z` of a set of n observations in m dimensions. `Y` is the condensed distance matrix from which `Z` was generated.

Returns

- c** [ndarray] The cophenetic correlation distance (if `Y` is passed).
- d** [ndarray] The cophenetic distance matrix in condensed form. The ij th entry is the cophenetic distance between original observations i and j .

See also:

`linkage`

for a description of what a linkage matrix is.

`scipy.spatial.distance.squareform`

transforming condensed matrices into square ones.

Examples

```
>>> from scipy.cluster.hierarchy import single, cophenet
>>> from scipy.spatial.distance import pdist, squareform
```

Given a dataset X and a linkage matrix Z , the cophenetic distance between two points of X is the distance between the largest two distinct clusters that each of the points:

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

X corresponds to this dataset

```
x x    x x
x      x

x      x
x x    x x
```

```
>>> Z = single(pdist(X))
>>> Z
array([[ 0.,  1.,  1.,  2.],
       [ 2., 12.,  1.,  3.],
       [ 3.,  4.,  1.,  2.],
       [ 5., 14.,  1.,  3.],
       [ 6.,  7.,  1.,  2.],
       [ 8., 16.,  1.,  3.],
       [ 9., 10.,  1.,  2.],
       [11., 18.,  1.,  3.],
       [13., 15.,  2.,  6.],
       [17., 20.,  2.,  9.],
       [19., 21.,  2., 12.]])
>>> cophenet(Z)
array([[1., 1., 2., 2., 2., 2., 2., 2., 2., 2., 2., 1., 2., 2., 2., 2., 2.,
       2., 2., 2., 2., 2., 2., 2., 2., 2., 2., 2., 1., 1., 2., 2.,
       2., 2., 2., 2., 1., 2., 2., 2., 2., 2., 2., 2., 2., 2., 2.,
       1., 1., 2., 2., 2., 1., 2., 2., 2., 2., 2., 2., 1., 1., 1.]])
```

The output of the `scipy.cluster.hierarchy.cophenet` method is represented in condensed form. We can use `scipy.spatial.distance.squareform` to see the output as a regular matrix (where each element ij denotes the cophenetic distance between each i, j pair of points in X):

```
>>> squareform(cophenet(Z))
array([[0., 1., 1., 2., 2., 2., 2., 2., 2., 2., 2., 2., 2., 2., 2., 2., 2.,
       1., 2., 2., 2., 2., 2., 2., 2., 2., 2., 2., 1., 1., 2., 2.,
       2., 2., 2., 2., 1., 2., 2., 2., 2., 2., 2., 2., 2., 2., 2.,
       2., 2., 2., 1., 0., 1., 2., 2., 2., 2., 2., 2., 2., 2.,
       2., 2., 2., 2., 2., 2., 0., 1., 1., 2., 2., 2., 2.,
       2., 2., 2., 2., 2., 2., 1., 0., 1., 2., 2., 2., 2., 2., 2., 2., 2.]])
```

(continues on next page)

(continued from previous page)

```
[2., 2., 2., 2., 2., 2., 1., 1., 0., 2., 2., 2.],
[2., 2., 2., 2., 2., 2., 2., 2., 2., 0., 1., 1.],
[2., 2., 2., 2., 2., 2., 2., 2., 2., 1., 0., 1.],
[2., 2., 2., 2., 2., 2., 2., 2., 2., 1., 1., 0.]]
```

In this example, the cophenetic distance between points on X that are very close (i.e., in the same corner) is 1. For other pairs of points is 2, because the points will be located in clusters at different corners - thus, the distance between these clusters will be larger.

6.3.13 `scipy.cluster.hierarchy.from_mlab_linkage`

`scipy.cluster.hierarchy.from_mlab_linkage` (Z)

Convert a linkage matrix generated by MATLAB(TM) to a new linkage matrix compatible with this module.

The conversion does two things:

- the indices are converted from $1 \dots N$ to $0 \dots (N-1)$ form, and
- a fourth column $Z[:, 3]$ is added where $Z[i, 3]$ represents the number of original observations (leaves) in the non-singleton cluster i .

This function is useful when loading in linkages from legacy data files generated by MATLAB.

Parameters

Z [ndarray] A linkage matrix generated by MATLAB(TM).

Returns

ZS [ndarray] A linkage matrix compatible with `scipy.cluster.hierarchy`.

See also:

linkage

for a description of what a linkage matrix is.

to_mlab_linkage

transform from SciPy to MATLAB format.

Examples

```
>>> import numpy as np
>>> from scipy.cluster.hierarchy import ward, from_mlab_linkage
```

Given a linkage matrix in MATLAB format mZ , we can use `scipy.cluster.hierarchy.from_mlab_linkage` to import it into SciPy format:

```
>>> mZ = np.array([[1, 2, 1], [4, 5, 1], [7, 8, 1],
...               [10, 11, 1], [3, 13, 1.29099445],
...               [6, 14, 1.29099445],
...               [9, 15, 1.29099445],
...               [12, 16, 1.29099445],
...               [17, 18, 5.77350269],
...               [19, 20, 5.77350269],
...               [21, 22, 8.16496581]])
```

```

>>> Z = from_mlab_linkage(mZ)
>>> Z
array([[ 0.          ,  1.          ,  1.          ,  2.          ],
       [ 3.          ,  4.          ,  1.          ,  2.          ],
       [ 6.          ,  7.          ,  1.          ,  2.          ],
       [ 9.          , 10.          ,  1.          ,  2.          ],
       [ 2.          , 12.          , 1.29099445,  3.          ],
       [ 5.          , 13.          , 1.29099445,  3.          ],
       [ 8.          , 14.          , 1.29099445,  3.          ],
       [11.          , 15.          , 1.29099445,  3.          ],
       [16.          , 17.          , 5.77350269,  6.          ],
       [18.          , 19.          , 5.77350269,  6.          ],
       [20.          , 21.          , 8.16496581, 12.          ]])

```

As expected, the linkage matrix `Z` returned includes an additional column counting the number of original samples in each cluster. Also, all cluster indices are reduced by 1 (MATLAB format uses 1-indexing, whereas SciPy uses 0-indexing).

6.3.14 `scipy.cluster.hierarchy.inconsistent`

`scipy.cluster.hierarchy.inconsistent` (`Z`, `d=2`)

Calculate inconsistency statistics on a linkage matrix.

Parameters

- Z** [ndarray] The $(n-1)$ by 4 matrix encoding the linkage (hierarchical clustering). See *linkage* documentation for more information on its form.
- d** [int, optional] The number of links up to d levels below each non-singleton cluster.

Returns

- R** [ndarray] A $(n-1)$ by 4 matrix where the i 'th row contains the link statistics for the non-singleton cluster i . The link statistics are computed over the link heights for links d levels below the cluster i . `R[i, 0]` and `R[i, 1]` are the mean and standard deviation of the link heights, respectively; `R[i, 2]` is the number of links included in the calculation; and `R[i, 3]` is the inconsistency coefficient,

$$\frac{Z[i, 2] - R[i, 0]}{R[i, 1]}$$

Notes

This function behaves similarly to the MATLAB(TM) `inconsistent` function.

Examples

```

>>> from scipy.cluster.hierarchy import inconsistent, linkage
>>> from matplotlib import pyplot as plt
>>> X = [[i] for i in [2, 8, 0, 4, 1, 9, 9, 0]]
>>> Z = linkage(X, 'ward')
>>> print(Z)
[[ 5.         6.         0.         2.         ]
 [ 2.         7.         0.         2.         ]
 [ 0.         4.         1.         2.         ]
 [ 1.         8.         1.15470054  3.         ]
 [ 9.         10.        2.12132034  4.         ]
 [ 3.         12.        4.11096096  5.         ]
 [11.         13.        14.07183949  8.         ]]
>>> inconsistent(Z)
array([[ 0.         , 0.         , 1.         , 0.         ],
       [ 0.         , 0.         , 1.         , 0.         ],
       [ 1.         , 0.         , 1.         , 0.         ],
       [ 0.57735027, 0.81649658, 2.         , 0.70710678],
       [ 1.04044011, 1.06123822, 3.         , 1.01850858],
       [ 3.11614065, 1.40688837, 2.         , 0.70710678],
       [ 6.44583366, 6.76770586, 3.         , 1.12682288]])

```

6.3.15 `scipy.cluster.hierarchy.maxinconsts`

`scipy.cluster.hierarchy.maxinconsts` (Z, R)

Return the maximum inconsistency coefficient for each non-singleton cluster and its children.

Parameters

- Z** [ndarray] The hierarchical clustering encoded as a matrix. See [linkage](#) for more information.
- R** [ndarray] The inconsistency matrix.

Returns

- MI** [ndarray] A monotonic $(n-1)$ -sized numpy array of doubles.

See also:

[linkage](#)

for a description of what a linkage matrix is.

[inconsistent](#)

for the creation of a inconsistency matrix.

Examples

```
>>> from scipy.cluster.hierarchy import median, inconsistent, maxinconsts
>>> from scipy.spatial.distance import pdist
```

Given a data set X , we can apply a clustering method to obtain a linkage matrix Z . `scipy.cluster.hierarchy.inconsistent` can be also used to obtain the inconsistency matrix R associated to this clustering process:

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

```
>>> Z = median(pdist(X))
>>> R = inconsistent(Z)
>>> Z
array([[ 0.          ,  1.          ,  1.          ,  2.          ],
       [ 3.          ,  4.          ,  1.          ,  2.          ],
       [ 9.          , 10.          ,  1.          ,  2.          ],
       [ 6.          ,  7.          ,  1.          ,  2.          ],
       [ 2.          , 12.          , 1.11803399,  3.          ],
       [ 5.          , 13.          , 1.11803399,  3.          ],
       [ 8.          , 15.          , 1.11803399,  3.          ],
       [11.          , 14.          , 1.11803399,  3.          ],
       [18.          , 19.          ,  3.          ,  6.          ],
       [16.          , 17.          ,  3.5         ,  6.          ],
       [20.          , 21.          ,  3.25        , 12.          ]])
>>> R
array([[1.          ,  0.          ,  1.          ,  0.          ],
       [1.          ,  0.          ,  1.          ,  0.          ],
       [1.          ,  0.          ,  1.          ,  0.          ],
       [1.          ,  0.          ,  1.          ,  0.          ],
       [1.05901699,  0.08346263,  2.          ,  0.70710678],
       [1.05901699,  0.08346263,  2.          ,  0.70710678],
       [1.05901699,  0.08346263,  2.          ,  0.70710678],
       [1.05901699,  0.08346263,  2.          ,  0.70710678],
       [1.74535599,  1.08655358,  3.          ,  1.15470054],
       [1.91202266,  1.37522872,  3.          ,  1.15470054],
       [3.25         ,  0.25         ,  3.          ,  0.          ]])
```

Here, `scipy.cluster.hierarchy.maxinconsts` can be used to compute the maximum value of the inconsistency statistic (the last column of R) for each non-singleton cluster and its children:

```
>>> maxinconsts(Z, R)
array([0.          ,  0.          ,  0.          ,  0.          ,  0.70710678,
       0.70710678,  0.70710678,  0.70710678,  1.15470054,  1.15470054,
       1.15470054])
```

6.3.16 `scipy.cluster.hierarchy.maxdists`

`scipy.cluster.hierarchy.maxdists` (*Z*)

Return the maximum distance between any non-singleton cluster.

Parameters

Z [ndarray] The hierarchical clustering encoded as a matrix. See `linkage` for more information.

Returns

maxdists [ndarray] A $(n-1)$ sized numpy array of doubles; `MD[i]` represents the maximum distance between any cluster (including singletons) below and including the node with index *i*. More specifically, `MD[i] = Z[Q(i)-n, 2].max()` where `Q(i)` is the set of all node indices below and including node *i*.

See also:

[`linkage`](#)

for a description of what a linkage matrix is.

[`is_monotonic`](#)

for testing for monotonicity of a linkage matrix.

Examples

```
>>> from scipy.cluster.hierarchy import median, maxdists
>>> from scipy.spatial.distance import pdist
```

Given a linkage matrix *Z*, `scipy.cluster.hierarchy.maxdists` computes for each new cluster generated (i.e., for each row of the linkage matrix) what is the maximum distance between any two child clusters.

Due to the nature of hierarchical clustering, in many cases this is going to be just the distance between the two child clusters that were merged to form the current one - that is, `Z[:,2]`.

However, for non-monotonic cluster assignments such as `scipy.cluster.hierarchy.median` clustering this is not always the case: There may be cluster formations where the distance between the two clusters merged is smaller than the distance between their children.

We can see this in an example:

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

```
>>> Z = median(pdist(X))
>>> Z
array([[ 0.          ,  1.          ,  1.          ,  2.          ],
       [ 3.          ,  4.          ,  1.          ,  2.          ],
       [ 9.          , 10.          ,  1.          ,  2.          ],
       [ 6.          ,  7.          ,  1.          ,  2.          ],
       [ 2.          , 12.          ,  1.11803399,  3.          ],
       [ 5.          , 13.          ,  1.11803399,  3.          ]]
```

(continues on next page)

(continued from previous page)

```

    [ 8.          , 15.          , 1.11803399, 3.          ],
    [11.          , 14.          , 1.11803399, 3.          ],
    [18.          , 19.          , 3.          , 6.          ],
    [16.          , 17.          , 3.5         , 6.          ],
    [20.          , 21.          , 3.25        , 12.         ]]
>>> maxdists(Z)
array([[1.          , 1.          , 1.          , 1.          , 1.11803399,
        1.11803399, 1.11803399, 3.          , 3.5         ,
        3.5         ]])

```

Note that while the distance between the two clusters merged when creating the last cluster is 3.25, there are two children (clusters 16 and 17) whose distance is larger (3.5). Thus, `scipy.cluster.hierarchy.maxdists` returns 3.5 in this case.

6.3.17 `scipy.cluster.hierarchy.maxRstat`

`scipy.cluster.hierarchy.maxRstat` (*Z*, *R*, *i*)

Return the maximum statistic for each non-singleton cluster and its children.

Parameters

- Z** [array_like] The hierarchical clustering encoded as a matrix. See [linkage](#) for more information.
- R** [array_like] The inconsistency matrix.
- i** [int] The column of *R* to use as the statistic.

Returns

- MR** [ndarray] Calculates the maximum statistic for the *i*'th column of the inconsistency matrix *R* for each non-singleton cluster node. `MR[j]` is the maximum over `R[Q(j)-n, i]`, where `Q(j)` the set of all node ids corresponding to nodes below and including *j*.

See also:

[linkage](#)

for a description of what a linkage matrix is.

[inconsistent](#)

for the creation of an inconsistency matrix.

Examples

```

>>> from scipy.cluster.hierarchy import median, inconsistent, maxRstat
>>> from scipy.spatial.distance import pdist

```

Given a data set *X*, we can apply a clustering method to obtain a linkage matrix *Z*. `scipy.cluster.hierarchy.inconsistent` can be also used to obtain the inconsistency matrix *R* associated to this clustering process:

```

>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]

```

```

>>> Z = median(pdist(X))
>>> R = inconsistent(Z)
>>> R
array([[1.          , 0.          , 1.          , 0.          ],
       [1.          , 0.          , 1.          , 0.          ],
       [1.          , 0.          , 1.          , 0.          ],
       [1.          , 0.          , 1.          , 0.          ],
       [1.05901699, 0.08346263, 2.          , 0.70710678],
       [1.05901699, 0.08346263, 2.          , 0.70710678],
       [1.05901699, 0.08346263, 2.          , 0.70710678],
       [1.05901699, 0.08346263, 2.          , 0.70710678],
       [1.74535599, 1.08655358, 3.          , 1.15470054],
       [1.91202266, 1.37522872, 3.          , 1.15470054],
       [3.25        , 0.25         , 3.          , 0.          ]])

```

`scipy.cluster.hierarchy.maxRstat` can be used to compute the maximum value of each column of `R`, for each non-singleton cluster and its children:

```

>>> maxRstat(Z, R, 0)
array([1.          , 1.          , 1.          , 1.          , 1.05901699,
       1.05901699, 1.05901699, 1.05901699, 1.74535599, 1.91202266,
       3.25         ])
>>> maxRstat(Z, R, 1)
array([0.          , 0.          , 0.          , 0.          , 0.08346263,
       0.08346263, 0.08346263, 0.08346263, 1.08655358, 1.37522872,
       1.37522872])
>>> maxRstat(Z, R, 3)
array([0.          , 0.          , 0.          , 0.          , 0.70710678,
       0.70710678, 0.70710678, 0.70710678, 1.15470054, 1.15470054,
       1.15470054])

```

6.3.18 `scipy.cluster.hierarchy.to_mlab_linkage`

`scipy.cluster.hierarchy.to_mlab_linkage` (*Z*)

Convert a linkage matrix to a MATLAB(TM) compatible one.

Converts a linkage matrix *Z* generated by the linkage function of this module to a MATLAB(TM) compatible one. The return linkage matrix has the last column removed and the cluster indices are converted to 1..N indexing.

Parameters

Z [ndarray] A linkage matrix generated by `scipy.cluster.hierarchy`.

Returns

`to_mlab_linkage`

[ndarray] A linkage matrix compatible with MATLAB(TM)'s hierarchical clustering functions.

The return linkage matrix has the last column removed and the cluster indices are converted to 1..N indexing.

See also:

[linkage](#)

for a description of what a linkage matrix is.

from_mlab_linkage

transform from Matlab to SciPy format.

Examples

```
>>> from scipy.cluster.hierarchy import ward, to_mlab_linkage
>>> from scipy.spatial.distance import pdist
```

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

```
>>> Z = ward(pdist(X))
>>> Z
array([[ 0.          ,  1.          ,  1.          ,  2.          ],
       [ 3.          ,  4.          ,  1.          ,  2.          ],
       [ 6.          ,  7.          ,  1.          ,  2.          ],
       [ 9.          , 10.          ,  1.          ,  2.          ],
       [ 2.          , 12.          , 1.29099445,  3.          ],
       [ 5.          , 13.          , 1.29099445,  3.          ],
       [ 8.          , 14.          , 1.29099445,  3.          ],
       [11.         , 15.          , 1.29099445,  3.          ],
       [16.         , 17.          , 5.77350269,  6.          ],
       [18.         , 19.          , 5.77350269,  6.          ],
       [20.         , 21.          , 8.16496581, 12.          ]])
```

After a linkage matrix Z has been created, we can use *scipy.cluster.hierarchy.to_mlab_linkage* to convert it into MATLAB format:

```
>>> mZ = to_mlab_linkage(Z)
>>> mZ
array([[ 1.          ,  2.          ,  1.          ],
       [ 4.          ,  5.          ,  1.          ],
       [ 7.          ,  8.          ,  1.          ],
       [10.         , 11.          ,  1.          ],
       [ 3.          , 13.          , 1.29099445],
       [ 6.          , 14.          , 1.29099445],
       [ 9.          , 15.          , 1.29099445],
       [12.         , 16.          , 1.29099445],
       [17.         , 18.          , 5.77350269],
       [19.         , 20.          , 5.77350269],
       [21.         , 22.          , 8.16496581]])
```

The new linkage matrix mZ uses 1-indexing for all the clusters (instead of 0-indexing). Also, the last column of the original linkage matrix has been dropped.

Routines for visualizing flat clusters.

<i>dendrogram</i> (Z[, p, truncate_mode, ...])	Plot the hierarchical clustering as a dendrogram.
--	---

6.3.19 `scipy.cluster.hierarchy.dendrogram`

```
scipy.cluster.hierarchy.dendrogram(Z, p=30, truncate_mode=None, color_threshold=None,
                                   get_leaves=True, orientation='top', labels=None,
                                   count_sort=False, distance_sort=False,
                                   show_leaf_counts=True, no_plot=False,
                                   no_labels=False, leaf_font_size=None,
                                   leaf_rotation=None, leaf_label_func=None,
                                   show_contracted=False, link_color_func=None, ax=None,
                                   above_threshold_color='C0')
```

Plot the hierarchical clustering as a dendrogram.

The dendrogram illustrates how each cluster is composed by drawing a U-shaped link between a non-singleton cluster and its children. The top of the U-link indicates a cluster merge. The two legs of the U-link indicate which clusters were merged. The length of the two legs of the U-link represents the distance between the child clusters. It is also the cophenetic distance between original observations in the two children clusters.

Parameters

- Z** [ndarray] The linkage matrix encoding the hierarchical clustering to render as a dendrogram. See the `linkage` function for more information on the format of `Z`.
- p** [int, optional] The `p` parameter for `truncate_mode`.
- truncate_mode** [str, optional] The dendrogram can be hard to read when the original observation matrix from which the linkage is derived is large. Truncation is used to condense the dendrogram. There are several modes:
- None** No truncation is performed (default). Note: `'none'` is an alias for `None` that's kept for backward compatibility.
 - 'lastp'** The last `p` non-singleton clusters formed in the linkage are the only non-leaf nodes in the linkage; they correspond to rows `Z[n-p-2:end]` in `Z`. All other non-singleton clusters are contracted into leaf nodes.
 - 'level'** No more than `p` levels of the dendrogram tree are displayed. A “level” includes all nodes with `p` merges from the last merge. Note: `'mtica'` is an alias for `'level'` that's kept for backward compatibility.
- color_threshold** [double, optional] For brevity, let t be the `color_threshold`. Colors all the descendent links below a cluster node k the same color if k is the first node below the cut threshold t . All links connecting nodes with distances greater than or equal to the threshold are colored with the default matplotlib color `'C0'`. If t is less than or equal to zero, all nodes are colored `'C0'`. If `color_threshold` is `None` or `'default'`, corresponding with MATLAB(TM) behavior, the threshold is set to $0.7 * \max(Z[:, 2])$.
- get_leaves** [bool, optional] Includes a list `R['leaves'] = H` in the result dictionary. For each i , `H[i] == j`, cluster node j appears in position i in the left-to-right traversal of the leaves, where $j < 2n - 1$ and $i < n$.
- orientation** [str, optional] The direction to plot the dendrogram, which can be any of the following strings:
- 'top'** Plots the root at the top, and plot descendent links going downwards. (default).
 - 'bottom'** Plots the root at the bottom, and plot descendent links going upwards.
 - 'left'** Plots the root at the left, and plot descendent links going right.
 - 'right'** Plots the root at the right, and plot descendent links going left.
- labels** [ndarray, optional] By default, `labels` is `None` so the index of the original observation is used to label the leaf nodes. Otherwise, this is an n -sized sequence, with $n == Z.shape[0] + 1$. The `labels[i]` value is the text to put under the i th leaf node only if it corresponds to an original observation and not a non-singleton cluster.

count_sort

[str or bool, optional] For each node n , the order (visually, from left-to-right) n 's two descendent links are plotted is determined by this parameter, which can be any of the following values:

False Nothing is done.

'ascending' or True

The child with the minimum number of original objects in its cluster is plotted first.

'descending'

The child with the maximum number of original objects in its cluster is plotted first.

Note, `distance_sort` and `count_sort` cannot both be True.

distance_sort

[str or bool, optional] For each node n , the order (visually, from left-to-right) n 's two descendent links are plotted is determined by this parameter, which can be any of the following values:

False Nothing is done.

'ascending' or True

The child with the minimum distance between its direct descendents is plotted first.

'descending'

The child with the maximum distance between its direct descendents is plotted first.

Note `distance_sort` and `count_sort` cannot both be True.

show_leaf_counts

[bool, optional] When True, leaf nodes representing $k > 1$ original observation are labeled with the number of observations they contain in parentheses.

no_plot

[bool, optional] When True, the final rendering is not performed. This is useful if only the data structures computed for the rendering are needed or if `matplotlib` is not available.

no_labels

[bool, optional] When True, no labels appear next to the leaf nodes in the rendering of the dendrogram.

leaf_rotation

[double, optional] Specifies the angle (in degrees) to rotate the leaf labels. When unspecified, the rotation is based on the number of nodes in the dendrogram (default is 0).

leaf_font_size

[int, optional] Specifies the font size (in points) of the leaf labels. When unspecified, the size based on the number of nodes in the dendrogram.

leaf_label_func

[lambda or function, optional] When `leaf_label_func` is a callable function, for each leaf with cluster index $k < 2n - 1$. The function is expected to return a string with the label for the leaf.

Indices $k < n$ correspond to original observations while indices $k \geq n$ correspond to non-singleton clusters.

For example, to label singletons with their node id and non-singletons with their id, count, and inconsistency coefficient, simply do:

```
# First define the leaf label function.
def llf(id):
    if id < n:
        return str(id)
    else:
        return "[%d %d %1.2f]" % (id, count, R[n-id,3])
# The text for the leaf nodes is going to be big so force
```

(continues on next page)

(continued from previous page)

```
# a rotation of 90 degrees.
dendrogram(Z, leaf_label_func=llf, leaf_rotation=90)
```

show_contracted

[bool, optional] When True the heights of non-singleton nodes contracted into a leaf node are plotted as crosses along the link connecting that leaf node. This really is only useful when truncation is used (see `truncate_mode` parameter).

link_color_func

[callable, optional] If given, `link_color_function` is called with each non-singleton id corresponding to each U-shaped link it will paint. The function is expected to return the color to paint the link, encoded as a matplotlib color string code. For example:

```
dendrogram(Z, link_color_func=lambda k: colors[k])
```

`colors` the direct links below each untruncated non-singleton node `k` using `colors[k]`.

ax

[matplotlib Axes instance, optional] If None and `no_plot` is not True, the dendrogram will be plotted on the current axes. Otherwise if `no_plot` is not True the dendrogram will be plotted on the given Axes instance. This can be useful if the dendrogram is part of a more complex figure.

above_threshold_color

[str, optional] This matplotlib color string sets the color of the links above the `color_threshold`. The default is 'C0'.

Returns**R**

[dict] A dictionary of data structures computed to render the dendrogram. Its has the following keys:

'color_list'

A list of color names. The k 'th element represents the color of the k 'th link.

'icoord' and 'dcoord'

Each of them is a list of lists. Let `icoord = [I1, I2, ..., Ip]` where $I_k = [xk1, xk2, xk3, xk4]$ and `dcoord = [D1, D2, ..., Dp]` where $D_k = [yk1, yk2, yk3, yk4]$, then the k 'th link painted is $(xk1, yk1) - (xk2, yk2) - (xk3, yk3) - (xk4, yk4)$.

'ivl'

A list of labels corresponding to the leaf nodes.

'leaves'

For each i , $H[i] == j$, cluster node j appears in position i in the left-to-right traversal of the leaves, where $j < 2n - 1$ and $i < n$. If j is less than n , the i -th leaf node corresponds to an original observation. Otherwise, it corresponds to a non-singleton cluster.

'leaves_color_list'

A list of color names. The k 'th element represents the color of the k 'th leaf.

See also:

[*linkage, set_link_color_palette*](#)

Notes

It is expected that the distances in $Z[:, 2]$ be monotonic, otherwise crossings appear in the dendrogram.

Examples


```
>>> from scipy.cluster import hierarchy
>>> import matplotlib.pyplot as plt
```

A very basic example:

```
>>> ytdist = np.array([662., 877., 255., 412., 996., 295., 468., 268.,
...                   400., 754., 564., 138., 219., 869., 669.])
>>> Z = hierarchy.linkage(ytdist, 'single')
>>> plt.figure()
>>> dn = hierarchy.dendrogram(Z)
```

Now, plot in given axes, improve the color scheme and use both vertical and horizontal orientations:

```
>>> hierarchy.set_link_color_palette(['m', 'c', 'y', 'k'])
>>> fig, axes = plt.subplots(1, 2, figsize=(8, 3))
>>> dn1 = hierarchy.dendrogram(Z, ax=axes[0], above_threshold_color='y',
...                             orientation='top')
>>> dn2 = hierarchy.dendrogram(Z, ax=axes[1],
...                             above_threshold_color='#bcdddc',
...                             orientation='right')
>>> hierarchy.set_link_color_palette(None) # reset to default after use
>>> plt.show()
```



These are data structures and routines for representing hierarchies as tree objects.

`ClusterNode(id[, left, right, dist, count])`

A tree node class for representing a cluster.

continues on next page

Table 6 – continued from previous page

<code>leaves_list(Z)</code>	Return a list of leaf node ids.
<code>to_tree(Z[, rd])</code>	Convert a linkage matrix into an easy-to-use tree object.
<code>cut_tree(Z[, n_clusters, height])</code>	Given a linkage matrix <i>Z</i> , return the cut tree.
<code>optimal_leaf_ordering(Z, y[, metric])</code>	Given a linkage matrix <i>Z</i> and distance, reorder the cut tree.

6.3.20 `scipy.cluster.hierarchy.ClusterNode`

class `scipy.cluster.hierarchy.ClusterNode` (*id*, *left=None*, *right=None*, *dist=0*, *count=1*)

A tree node class for representing a cluster.

Leaf nodes correspond to original observations, while non-leaf nodes correspond to non-singleton clusters.

The `to_tree` function converts a matrix returned by the linkage function into an easy-to-use tree representation.

All parameter names are also attributes.

Parameters

id	[int] The node id.
left	[ClusterNode instance, optional] The left child tree node.
right	[ClusterNode instance, optional] The right child tree node.
dist	[float, optional] Distance for this cluster in the linkage matrix.
count	[int, optional] The number of samples in this cluster.

See also:

`to_tree`

for converting a linkage matrix *Z* into a tree object.

Methods

<code>get_count(self)</code>	The number of leaf nodes (original observations) belonging to the cluster node <i>nd</i> .
<code>get_id(self)</code>	The identifier of the target node.
<code>get_left(self)</code>	Return a reference to the left child tree object.
<code>get_right(self)</code>	Return a reference to the right child tree object.
<code>is_leaf(self)</code>	Return True if the target node is a leaf.
<code>pre_order(self[, func])</code>	Perform pre-order traversal without recursive function calls.



`scipy.cluster.hierarchy.ClusterNode.get_count`

`ClusterNode.get_count` (*self*)

The number of leaf nodes (original observations) belonging to the cluster node *nd*. If the target node is a leaf, 1 is returned.

Returns

get_count [int] The number of leaf nodes below the target node.



scipy.cluster.hierarchy.ClusterNode.get_id

`ClusterNode.get_id(self)`

The identifier of the target node.

For $0 \leq i < n$, i corresponds to original observation i . For $n \leq i < 2n-1$, i corresponds to non-singleton cluster formed at iteration $i-n$.

Returns

id [int] The identifier of the target node.

scipy.cluster.hierarchy.ClusterNode.get_left

`ClusterNode.get_left(self)`

Return a reference to the left child tree object.

Returns

left [ClusterNode] The left child of the target node. If the node is a leaf, None is returned.

scipy.cluster.hierarchy.ClusterNode.get_right

`ClusterNode.get_right(self)`

Return a reference to the right child tree object.

Returns

right [ClusterNode] The left child of the target node. If the node is a leaf, None is returned.

scipy.cluster.hierarchy.ClusterNode.is_leaf

ClusterNode.**is_leaf** (*self*)

Return True if the target node is a leaf.

Returns

leafness [bool] True if the target node is a leaf node.

scipy.cluster.hierarchy.ClusterNode.pre_order

ClusterNode.**pre_order** (*self*, *func*=<function ClusterNode.<lambda> at 0x7f893a896dc0>)

Perform pre-order traversal without recursive function calls.

When a leaf node is first encountered, *func* is called with the leaf node as its argument, and its result is appended to the list.

For example, the statement:

```
ids = root.pre_order(lambda x: x.id)
```

returns a list of the node ids corresponding to the leaf nodes of the tree as they appear from left to right.

Parameters

func [function] Applied to each leaf ClusterNode object in the pre-order traversal. Given the *i*-th leaf node in the pre-order traversal *n*[*i*], the result of *func* (*n*[*i*]) is stored in *L*[*i*]. If not provided, the index of the original observation to which the node corresponds is used.

Returns

L [list] The pre-order traversal.

6.3.21 scipy.cluster.hierarchy.leaves_list

scipy.cluster.hierarchy.**leaves_list** (*Z*)

Return a list of leaf node ids.

The return corresponds to the observation vector index as it appears in the tree from left to right. *Z* is a linkage matrix.

Parameters

Z [ndarray] The hierarchical clustering encoded as a matrix. *Z* is a linkage matrix. See [linkage](#) for more information.

Returns

leaves_list [ndarray] The list of leaf node ids.

See also:

[dendrogram](#)

for information about dendrogram structure.

Examples

```
>>> from scipy.cluster.hierarchy import ward, dendrogram, leaves_list
>>> from scipy.spatial.distance import pdist
>>> from matplotlib import pyplot as plt
```


```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

```
>>> Z = ward(pdist(X))
```

The linkage matrix *Z* represents a dendrogram, that is, a tree that encodes the structure of the clustering performed. *scipy.cluster.hierarchy.leaves_list* shows the mapping between indices in the *X* dataset and leaves in the dendrogram:

```
>>> leaves_list(Z)
array([ 2,  0,  1,  5,  3,  4,  8,  6,  7, 11,  9, 10], dtype=int32)
```

```
>>> fig = plt.figure(figsize=(25, 10))
>>> dn = dendrogram(Z)
>>> plt.show()
```



6.3.22 `scipy.cluster.hierarchy.to_tree`

`scipy.cluster.hierarchy.to_tree` (*Z*, *rd=False*)

Convert a linkage matrix into an easy-to-use tree object.

The reference to the root *ClusterNode* object is returned (by default).

Each *ClusterNode* object has a *left*, *right*, *dist*, *id*, and *count* attribute. The *left* and *right* attributes point to *ClusterNode* objects that were combined to generate the cluster. If both are *None* then the *ClusterNode* object is a leaf node, its *count* must be 1, and its *distance* is meaningless but set to 0.

Note: This function is provided for the convenience of the library user. ClusterNodes are not used as input to any of the functions in this library.

Parameters

Z [ndarray] The linkage matrix in proper form (see the [linkage](#) function documentation).
rd [bool, optional] When False (default), a reference to the root `ClusterNode` object is returned. Otherwise, a tuple (`r`, `d`) is returned. `r` is a reference to the root node while `d` is a list of `ClusterNode` objects - one per original entry in the linkage matrix plus entries for all clustering steps. If a cluster id is less than the number of samples `n` in the data that the linkage matrix describes, then it corresponds to a singleton cluster (leaf node). See [linkage](#) for more information on the assignment of cluster ids to clusters.

Returns

tree [ClusterNode or tuple (ClusterNode, list of ClusterNode)] If `rd` is False, a `ClusterNode`. If `rd` is True, a list of length $2*n - 1$, with `n` the number of samples. See the description of `rd` above for more details.

See also:

[linkage](#), [is_valid_linkage](#), [ClusterNode](#)

Examples

```
>>> from scipy.cluster import hierarchy
>>> x = np.random.rand(10).reshape(5, 2)
>>> Z = hierarchy.linkage(x)
>>> hierarchy.to_tree(Z)
<scipy.cluster.hierarchy.ClusterNode object at ...
>>> rootnode, nodelist = hierarchy.to_tree(Z, rd=True)
>>> rootnode
<scipy.cluster.hierarchy.ClusterNode object at ...
>>> len(nodelist)
9
```

6.3.23 `scipy.cluster.hierarchy.cut_tree`

`scipy.cluster.hierarchy.cut_tree` (`Z`, `n_clusters=None`, `height=None`)

Given a linkage matrix `Z`, return the cut tree.

Parameters

Z [`scipy.cluster.linkage` array] The linkage matrix.
n_clusters [array_like, optional] Number of clusters in the tree at the cut point.
height [array_like, optional] The height at which to cut the tree. Only possible for ultrametric trees.

Returns

cutree [array] An array indicating group membership at each agglomeration step. I.e., for a full cut tree, in the first column each data point is in its own cluster. At the next step, two nodes are merged. Finally, all singleton and non-singleton clusters are in one group. If `n_clusters` or `height` are given, the columns correspond to the columns of `n_clusters` or `height`.

Examples

```

>>> from scipy import cluster
>>> np.random.seed(23)
>>> X = np.random.randn(50, 4)
>>> Z = cluster.hierarchy.ward(X)
>>> cutree = cluster.hierarchy.cut_tree(Z, n_clusters=[5, 10])
>>> cutree[:10]
array([[0, 0],
       [1, 1],
       [2, 2],
       [3, 3],
       [3, 4],
       [2, 2],
       [0, 0],
       [1, 5],
       [3, 6],
       [4, 7]])

```

6.3.24 `scipy.cluster.hierarchy.optimal_leaf_ordering`

`scipy.cluster.hierarchy.optimal_leaf_ordering` (*Z*, *y*, *metric*='euclidean')

Given a linkage matrix *Z* and distance, reorder the cut tree.

Parameters

- Z** [ndarray] The hierarchical clustering encoded as a linkage matrix. See *linkage* for more information on the return structure and algorithm.
- y** [ndarray] The condensed distance matrix from which *Z* was generated. Alternatively, a collection of *m* observation vectors in *n* dimensions may be passed as an *m* by *n* array.
- metric** [str or function, optional] The distance metric to use in the case that *y* is a collection of observation vectors; ignored otherwise. See the `pdist` function for a list of valid distance metrics. A custom distance function can also be used.

Returns

- Z_ordered** [ndarray] A copy of the linkage matrix *Z*, reordered to minimize the distance between adjacent leaves.

Examples

```

>>> from scipy.cluster import hierarchy
>>> np.random.seed(23)
>>> X = np.random.randn(10, 10)
>>> Z = hierarchy.ward(X)
>>> hierarchy.leaves_list(Z)
array([0, 5, 3, 9, 6, 8, 1, 4, 2, 7], dtype=int32)
>>> hierarchy.leaves_list(hierarchy.optimal_leaf_ordering(Z, X))
array([3, 9, 0, 5, 8, 2, 7, 4, 1, 6], dtype=int32)

```

These are predicates for checking the validity of linkage and inconsistency matrices as well as for checking isomorphism of two flat cluster assignments.

<code>is_valid_im(R[, warning, throw, name])</code>	Return True if the inconsistency matrix passed is valid.
<code>is_valid_linkage(Z[, warning, throw, name])</code>	Check the validity of a linkage matrix.
<code>is_isomorphic(T1, T2)</code>	Determine if two different cluster assignments are equivalent.
<code>is_monotonic(Z)</code>	Return True if the linkage passed is monotonic.
<code>correspond(Z, Y)</code>	Check for correspondence between linkage and condensed distance matrices.
<code>num_obs_linkage(Z)</code>	Return the number of original observations of the linkage matrix passed.

6.3.25 `scipy.cluster.hierarchy.is_valid_im`

`scipy.cluster.hierarchy.is_valid_im(R, warning=False, throw=False, name=None)`

Return True if the inconsistency matrix passed is valid.

It must be a n by 4 array of doubles. The standard deviations $R[:, 1]$ must be nonnegative. The link counts $R[:, 2]$ must be positive and no greater than $n - 1$.

Parameters

R	[ndarray] The inconsistency matrix to check for validity.
warning	[bool, optional] When True, issues a Python warning if the linkage matrix passed is invalid.
throw	[bool, optional] When True, throws a Python exception if the linkage matrix passed is invalid.
name	[str, optional] This string refers to the variable name of the invalid linkage matrix.

Returns

b	[bool] True if the inconsistency matrix is valid.
----------	---

See also:

`linkage`

for a description of what a linkage matrix is.

`inconsistent`

for the creation of a inconsistency matrix.

Examples

```
>>> from scipy.cluster.hierarchy import ward, inconsistent, is_valid_im
>>> from scipy.spatial.distance import pdist
```

Given a data set X , we can apply a clustering method to obtain a linkage matrix Z . `scipy.cluster.hierarchy.inconsistent` can be also used to obtain the inconsistency matrix R associated to this clustering process:

```
>>> X = [[0, 0], [0, 1], [1, 0],
...       [0, 4], [0, 3], [1, 4],
...       [4, 0], [3, 0], [4, 1],
...       [4, 4], [3, 4], [4, 3]]
```

```

>>> Z = ward(pdist(X))
>>> R = inconsistent(Z)
>>> Z
array([[ 0.          ,  1.          ,  1.          ,  2.          ],
       [ 3.          ,  4.          ,  1.          ,  2.          ],
       [ 6.          ,  7.          ,  1.          ,  2.          ],
       [ 9.          , 10.          ,  1.          ,  2.          ],
       [ 2.          , 12.          , 1.29099445,  3.          ],
       [ 5.          , 13.          , 1.29099445,  3.          ],
       [ 8.          , 14.          , 1.29099445,  3.          ],
       [11.          , 15.          , 1.29099445,  3.          ],
       [16.          , 17.          , 5.77350269,  6.          ],
       [18.          , 19.          , 5.77350269,  6.          ],
       [20.          , 21.          , 8.16496581, 12.          ]])

>>> R
array([[1.          ,  0.          ,  1.          ,  0.          ],
       [1.          ,  0.          ,  1.          ,  0.          ],
       [1.          ,  0.          ,  1.          ,  0.          ],
       [1.          ,  0.          ,  1.          ,  0.          ],
       [1.14549722,  0.20576415,  2.          ,  0.70710678],
       [1.14549722,  0.20576415,  2.          ,  0.70710678],
       [1.14549722,  0.20576415,  2.          ,  0.70710678],
       [1.14549722,  0.20576415,  2.          ,  0.70710678],
       [1.14549722,  0.20576415,  2.          ,  0.70710678],
       [2.78516386,  2.58797734,  3.          ,  1.15470054],
       [2.78516386,  2.58797734,  3.          ,  1.15470054],
       [6.57065706,  1.38071187,  3.          ,  1.15470054]])
    
```

Now we can use `scipy.cluster.hierarchy.is_valid_im` to verify that R is correct:

```

>>> is_valid_im(R)
True
    
```

However, if R is wrongly constructed (e.g., one of the standard deviations is set to a negative value), then the check will fail:

```

>>> R[-1,1] = R[-1,1] * -1
>>> is_valid_im(R)
False
    
```

6.3.26 `scipy.cluster.hierarchy.is_valid_linkage`

`scipy.cluster.hierarchy.is_valid_linkage` (*Z*, *warning=False*, *throw=False*, *name=None*)

Check the validity of a linkage matrix.

A linkage matrix is valid if it is a 2-D array (type double) with n rows and 4 columns. The first two columns must contain indices between 0 and $2n - 1$. For a given row i , the following two expressions have to hold:

$$0 \leq Z[i, 0] \leq i + n - 10 \leq Z[i, 1] \leq i + n - 1$$

I.e., a cluster cannot join another cluster unless the cluster being joined has been generated.

Parameters

Z [array_like] Linkage matrix.

warning [bool, optional] When True, issues a Python warning if the linkage matrix passed is invalid.
throw [bool, optional] When True, throws a Python exception if the linkage matrix passed is invalid.
name [str, optional] This string refers to the variable name of the invalid linkage matrix.

Returns

b [bool] True if the inconsistency matrix is valid.

See also:

linkage

for a description of what a linkage matrix is.

Examples

```
>>> from scipy.cluster.hierarchy import ward, is_valid_linkage
>>> from scipy.spatial.distance import pdist
```

All linkage matrices generated by the clustering methods in this module will be valid (i.e., they will have the appropriate dimensions and the two required expressions will hold for all the rows).

We can check this using `scipy.cluster.hierarchy.is_valid_linkage`:

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

```
>>> Z = ward(pdist(X))
>>> Z
array([[ 0.         ,  1.         ,  1.         ,  2.         ],
       [ 3.         ,  4.         ,  1.         ,  2.         ],
       [ 6.         ,  7.         ,  1.         ,  2.         ],
       [ 9.         , 10.         ,  1.         ,  2.         ],
       [ 2.         , 12.         , 1.29099445,  3.         ],
       [ 5.         , 13.         , 1.29099445,  3.         ],
       [ 8.         , 14.         , 1.29099445,  3.         ],
       [11.         , 15.         , 1.29099445,  3.         ],
       [16.         , 17.         , 5.77350269,  6.         ],
       [18.         , 19.         , 5.77350269,  6.         ],
       [20.         , 21.         , 8.16496581, 12.         ]])
>>> is_valid_linkage(Z)
True
```

However, if we create a linkage matrix in a wrong way - or if we modify a valid one in a way that any of the required expressions don't hold anymore, then the check will fail:

```
>>> Z[3][1] = 20      # the cluster number 20 is not defined at this point
>>> is_valid_linkage(Z)
False
```

6.3.27 `scipy.cluster.hierarchy.is_isomorphic`

`scipy.cluster.hierarchy.is_isomorphic` (*T1*, *T2*)

Determine if two different cluster assignments are equivalent.

Parameters

T1 [array_like] An assignment of singleton cluster ids to flat cluster ids.
T2 [array_like] An assignment of singleton cluster ids to flat cluster ids.

Returns

b [bool] Whether the flat cluster assignments *T1* and *T2* are equivalent.

See also:

[*linkage*](#)

for a description of what a linkage matrix is.

[*fcluster*](#)

for the creation of flat cluster assignments.

Examples

```
>>> from scipy.cluster.hierarchy import fcluster, is_isomorphic
>>> from scipy.cluster.hierarchy import single, complete
>>> from scipy.spatial.distance import pdist
```

Two flat cluster assignments can be isomorphic if they represent the same cluster assignment, with different labels.

For example, we can use the `scipy.cluster.hierarchy.single`: method and flatten the output to four clusters:

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

```
>>> Z = single(pdist(X))
>>> T = fcluster(Z, 1, criterion='distance')
>>> T
array([3, 3, 3, 4, 4, 4, 2, 2, 2, 1, 1, 1], dtype=int32)
```

We can then do the same using the `scipy.cluster.hierarchy.complete`: method:

```
>>> Z = complete(pdist(X))
>>> T_ = fcluster(Z, 1.5, criterion='distance')
>>> T_
array([1, 1, 1, 2, 2, 2, 3, 3, 3, 4, 4, 4], dtype=int32)
```

As we can see, in both cases we obtain four clusters and all the data points are distributed in the same way - the only thing that changes are the flat cluster labels (3 => 1, 4 =>2, 2 =>3 and 4 =>1), so both cluster assignments are isomorphic:

```
>>> is_isomorphic(T, T_)
True
```

6.3.28 `scipy.cluster.hierarchy.is_monotonic`

`scipy.cluster.hierarchy.is_monotonic(Z)`

Return True if the linkage passed is monotonic.

The linkage is monotonic if for every cluster s and t joined, the distance between them is no less than the distance between any previously joined clusters.

Parameters

Z [ndarray] The linkage matrix to check for monotonicity.

Returns

b [bool] A boolean indicating whether the linkage is monotonic.

See also:

[linkage](#)

for a description of what a linkage matrix is.

Examples

```
>>> from scipy.cluster.hierarchy import median, ward, is_monotonic
>>> from scipy.spatial.distance import pdist
```

By definition, some hierarchical clustering algorithms - such as `scipy.cluster.hierarchy.ward` - produce monotonic assignments of samples to clusters; however, this is not always true for other hierarchical methods - e.g. `scipy.cluster.hierarchy.median`.

Given a linkage matrix Z (as the result of a hierarchical clustering method) we can test programmatically whether it has the monotonicity property or not, using `scipy.cluster.hierarchy.is_monotonic`:

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

```
>>> Z = ward(pdist(X))
>>> Z
array([[ 0.          ,  1.          ,  1.          ,  2.          ],
       [ 3.          ,  4.          ,  1.          ,  2.          ],
       [ 6.          ,  7.          ,  1.          ,  2.          ],
       [ 9.          , 10.          ,  1.          ,  2.          ],
       [ 2.          , 12.          , 1.29099445,  3.          ],
       [ 5.          , 13.          , 1.29099445,  3.          ],
       [ 8.          , 14.          , 1.29099445,  3.          ],
       [11.         , 15.         , 1.29099445,  3.          ],
       [16.         , 17.         , 5.77350269,  6.          ],
       [18.         , 19.         , 5.77350269,  6.          ]]
```

(continues on next page)

(continued from previous page)

```

[20.          , 21.          , 8.16496581, 12.          ])
>>> is_monotonic(Z)
True

```

```

>>> Z = median(pdist(X))
>>> Z
array([[ 0.          ,  1.          ,  1.          ,  2.          ],
       [ 3.          ,  4.          ,  1.          ,  2.          ],
       [ 9.          , 10.          ,  1.          ,  2.          ],
       [ 6.          ,  7.          ,  1.          ,  2.          ],
       [ 2.          , 12.          , 1.11803399,  3.          ],
       [ 5.          , 13.          , 1.11803399,  3.          ],
       [ 8.          , 15.          , 1.11803399,  3.          ],
       [11.          , 14.          , 1.11803399,  3.          ],
       [18.          , 19.          ,  3.          ,  6.          ],
       [16.          , 17.          ,  3.5          ,  6.          ],
       [20.          , 21.          ,  3.25         , 12.          ]])
>>> is_monotonic(Z)
False

```

Note that this method is equivalent to just verifying that the distances in the third column of the linkage matrix appear in a monotonically increasing order.

6.3.29 `scipy.cluster.hierarchy.correspond`

`scipy.cluster.hierarchy.correspond`(Z, Y)

Check for correspondence between linkage and condensed distance matrices.

They must have the same number of original observations for the check to succeed.

This function is useful as a sanity check in algorithms that make extensive use of linkage and distance matrices that must correspond to the same set of original observations.

Parameters

Z [array_like] The linkage matrix to check for correspondence.
Y [array_like] The condensed distance matrix to check for correspondence.

Returns

b [bool] A boolean indicating whether the linkage matrix and distance matrix could possibly correspond to one another.

See also:

[*linkage*](#)

for a description of what a linkage matrix is.

Examples

```
>>> from scipy.cluster.hierarchy import ward, correspond
>>> from scipy.spatial.distance import pdist
```

This method can be used to check if a given linkage matrix Z has been obtained from the application of a cluster method over a dataset X :

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
>>> X_condensed = pdist(X)
>>> Z = ward(X_condensed)
```

Here, we can compare Z and X (in condensed form):

```
>>> correspond(Z, X_condensed)
True
```

6.3.30 `scipy.cluster.hierarchy.num_obs_linkage`

`scipy.cluster.hierarchy.num_obs_linkage` (Z)

Return the number of original observations of the linkage matrix passed.

Parameters

Z [ndarray] The linkage matrix on which to perform the operation.

Returns

n [int] The number of original observations in the linkage.

Examples

```
>>> from scipy.cluster.hierarchy import ward, num_obs_linkage
>>> from scipy.spatial.distance import pdist
```

```
>>> X = [[0, 0], [0, 1], [1, 0],
...      [0, 4], [0, 3], [1, 4],
...      [4, 0], [3, 0], [4, 1],
...      [4, 4], [3, 4], [4, 3]]
```

```
>>> Z = ward(pdist(X))
```

Z is a linkage matrix obtained after using the Ward clustering method with X , a dataset with 12 data points.

```
>>> num_obs_linkage(Z)
12
```

Utility routines for plotting:

<code>set_link_color_palette(palette)</code>	Set list of matplotlib color codes for use by dendrogram.
--	---

6.3.31 `scipy.cluster.hierarchy.set_link_color_palette`

`scipy.cluster.hierarchy.set_link_color_palette` (*palette*)

Set list of matplotlib color codes for use by dendrogram.

Note that this palette is global (i.e., setting it once changes the colors for all subsequent calls to `dendrogram`) and that it affects only the the colors below `color_threshold`.

Note that `dendrogram` also accepts a custom coloring function through its `link_color_func` keyword, which is more flexible and non-global.

Parameters

palette [list of str or None] A list of matplotlib color codes. The order of the color codes is the order in which the colors are cycled through when color thresholding in the dendrogram. If None, resets the palette to its default (which are matplotlib default colors C1 to C9).

Returns

None

See also:

[`dendrogram`](#)

Notes

Ability to reset the palette with None added in SciPy 0.17.0.

Examples

```
>>> from scipy.cluster import hierarchy
>>> ytdist = np.array([662., 877., 255., 412., 996., 295., 468., 268.,
...                   400., 754., 564., 138., 219., 869., 669.])
>>> Z = hierarchy.linkage(ytdist, 'single')
>>> dn = hierarchy.dendrogram(Z, no_plot=True)
>>> dn['color_list']
['C1', 'C0', 'C0', 'C0', 'C0']
>>> hierarchy.set_link_color_palette(['c', 'm', 'y', 'k'])
>>> dn = hierarchy.dendrogram(Z, no_plot=True, above_threshold_color='b')
>>> dn['color_list']
['c', 'b', 'b', 'b', 'b']
>>> dn = hierarchy.dendrogram(Z, no_plot=True, color_threshold=267,
...                           above_threshold_color='k')
>>> dn['color_list']
['c', 'm', 'm', 'k', 'k']
```

Now, reset the color palette to its default:

```
>>> hierarchy.set_link_color_palette(None)
```


Utility classes:

<code>DisjointSet(elements)</code>	Disjoint set data structure for incremental connectivity queries.
------------------------------------	---

6.3.32 `scipy.cluster.hierarchy.DisjointSet`

class `scipy.cluster.hierarchy.DisjointSet` (*elements=None*)
Disjoint set data structure for incremental connectivity queries.

Notes

This class implements the disjoint set [1], also known as the *union-find* or *merge-find* data structure. The *find* operation (implemented in `__getitem__`) implements the *path halving* variant. The *merge* method implements the *merge by size* variant.

References

[1]

Examples

```
>>> from scipy.cluster.hierarchy import DisjointSet
```

Initialize a disjoint set:

```
>>> disjoint_set = DisjointSet([1, 2, 3, 'a', 'b'])
```

Merge some subsets:

```
>>> disjoint_set.merge(1, 2)
True
>>> disjoint_set.merge(3, 'a')
True
>>> disjoint_set.merge('a', 'b')
True
>>> disjoint_set.merge('b', 'b')
False
```

Find root elements:

```
>>> disjoint_set[2]
1
>>> disjoint_set['b']
3
```

Test connectivity:

```
>>> disjoint_set.connected(1, 2)
True
>>> disjoint_set.connected(1, 'b')
False
```

List elements in disjoint set:

```
>>> list(disjoint_set)
[1, 2, 3, 'a', 'b']
```

Get the subset containing 'a':

```
>>> disjoint_set.subset('a')
{'a', 3, 'b'}
```

Get all subsets in the disjoint set:

```
>>> disjoint_set.subsets()
[{1, 2}, {'a', 3, 'b'}]
```

Attributes

n_subsets [int] The number of subsets.

Methods

<code>add(self, x)</code>	Add element x to disjoint set
<code>merge(self, x, y)</code>	Merge the subsets of x and y .
<code>connected(self, x, y)</code>	Test whether x and y are in the same subset.
<code>subset(self, x)</code>	Get the subset containing x .
<code>subsets(self)</code>	Get all the subsets in the disjoint set.
<code>__getitem__(self, x)</code>	Find the root element of x .

scipy.cluster.hierarchy.DisjointSet.add

`DisjointSet.add(self, x)`
Add element x to disjoint set

scipy.cluster.hierarchy.DisjointSet.merge

`DisjointSet.merge(self, x, y)`
Merge the subsets of x and y .

The smaller subset (the child) is merged into the larger subset (the parent). If the subsets are of equal size, the root element which was first inserted into the disjoint set is selected as the parent.

Parameters

x, y [hashable object] Elements to merge.

Returns

merged [bool] True if x and y were in disjoint sets, False otherwise.

scipy.cluster.hierarchy.DisjointSet.connected

`DisjointSet.connected` (*self*, *x*, *y*)

Test whether *x* and *y* are in the same subset.

Parameters

x, y [hashable object] Elements to test.

Returns

result [bool] True if *x* and *y* are in the same set, False otherwise.

scipy.cluster.hierarchy.DisjointSet.subset

`DisjointSet.subset` (*self*, *x*)

Get the subset containing *x*.

Parameters

x [hashable object] Input element.

Returns

result [set] Subset containing *x*.

scipy.cluster.hierarchy.DisjointSet.subsets

`DisjointSet.subsets` (*self*)

Get all the subsets in the disjoint set.

Returns

result [set] Subsets in the disjoint set.

scipy.cluster.hierarchy.DisjointSet.__getitem__

`DisjointSet.__getitem__` (*self*, *x*)

Find the root element of *x*.

Parameters

x [hashable object] Input element.

Returns

root [hashable object] Root element of *x*.

6.4 Constants (`scipy.constants`)

Physical and mathematical constants and units.

6.4.1 Mathematical constants

<code>pi</code>	Pi
<code>golden</code>	Golden ratio
<code>golden_ratio</code>	Golden ratio

6.4.2 Physical constants

<code>c</code>	speed of light in vacuum
<code>speed_of_light</code>	speed of light in vacuum
<code>mu_0</code>	the magnetic constant μ_0
<code>epsilon_0</code>	the electric constant (vacuum permittivity), ϵ_0
<code>h</code>	the Planck constant h
<code>Planck</code>	the Planck constant h
<code>hbar</code>	$\hbar = h/(2\pi)$
<code>G</code>	Newtonian constant of gravitation
<code>gravitational_constant</code>	Newtonian constant of gravitation
<code>g</code>	standard acceleration of gravity
<code>e</code>	elementary charge
<code>elementary_charge</code>	elementary charge
<code>R</code>	molar gas constant
<code>gas_constant</code>	molar gas constant
<code>alpha</code>	fine-structure constant
<code>fine_structure</code>	fine-structure constant
<code>N_A</code>	Avogadro constant
<code>Avogadro</code>	Avogadro constant
<code>k</code>	Boltzmann constant
<code>Boltzmann</code>	Boltzmann constant
<code>sigma</code>	Stefan-Boltzmann constant σ
<code>Stefan_Boltzmann</code>	Stefan-Boltzmann constant σ
<code>Wien</code>	Wien displacement law constant
<code>Rydberg</code>	Rydberg constant
<code>m_e</code>	electron mass
<code>electron_mass</code>	electron mass
<code>m_p</code>	proton mass
<code>proton_mass</code>	proton mass
<code>m_n</code>	neutron mass
<code>neutron_mass</code>	neutron mass

Constants database

In addition to the above variables, `scipy.constants` also contains the 2018 CODATA recommended values [CODATA2018] database containing more physical constants.

<code>value(key)</code>	Value in <code>physical_constants</code> indexed by key
<code>unit(key)</code>	Unit in <code>physical_constants</code> indexed by key
<code>precision(key)</code>	Relative precision in <code>physical_constants</code> indexed by key
<code>find([sub, disp])</code>	Return list of <code>physical_constant</code> keys containing a given string.
<code>ConstantWarning</code>	Accessing a constant no longer in current CODATA data set

`scipy.constants.value`

`scipy.constants.value` (*key*)
Value in `physical_constants` indexed by key

Parameters

key [Python string or unicode] Key in dictionary `physical_constants`

Returns

value [float] Value in `physical_constants` corresponding to *key*

Examples

```
>>> from scipy import constants
>>> constants.value(u'elementary charge')
1.602176634e-19
```

`scipy.constants.unit`

`scipy.constants.unit` (*key*)
Unit in `physical_constants` indexed by key

Parameters

key [Python string or unicode] Key in dictionary `physical_constants`

Returns

unit [Python string] Unit in `physical_constants` corresponding to *key*

Examples

```
>>> from scipy import constants
>>> constants.unit(u'proton mass')
'kg'
```

scipy.constants.precision

`scipy.constants.precision` (*key*)
Relative precision in `physical_constants` indexed by key

Parameters

key [Python string or unicode] Key in dictionary `physical_constants`

Returns

prec [float] Relative precision in `physical_constants` corresponding to *key*

Examples

```
>>> from scipy import constants
>>> constants.precision(u'proton mass')
5.1e-37
```

scipy.constants.find

`scipy.constants.find` (*sub=None, disp=False*)
Return list of `physical_constant` keys containing a given string.

Parameters

sub [str, unicode] Sub-string to search keys for. By default, return all keys.

disp [bool] If True, print the keys that are found and return None. Otherwise, return the list of keys without printing anything.

Returns

keys [list or None] If *disp* is False, the list of keys is returned. Otherwise, None is returned.

Examples

```
>>> from scipy.constants import find, physical_constants
```

Which keys in the `physical_constants` dictionary contain 'boltzmann'?

```
>>> find('boltzmann')
['Boltzmann constant',
 'Boltzmann constant in Hz/K',
 'Boltzmann constant in eV/K',
 'Boltzmann constant in inverse meter per kelvin',
 'Stefan-Boltzmann constant']
```

Get the constant called 'Boltzmann constant in Hz/K':

```
>>> physical_constants['Boltzmann constant in Hz/K']
(20836619120.0, 'Hz K^-1', 0.0)
```

Find constants with 'radius' in the key:

```

>>> find('radius')
['Bohr radius',
 'classical electron radius',
 'deuteron rms charge radius',
 'proton rms charge radius']
>>> physical_constants['classical electron radius']
(2.8179403262e-15, 'm', 1.3e-24)

```

scipy.constants.ConstantWarning

exception `scipy.constants.ConstantWarning`

Accessing a constant no longer in current CODATA data set

with_traceback()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

`scipy.constants.physical_constants`

Dictionary of physical constants, of the format `physical_constants[name] = (value, unit, uncertainty)`.

Available constants:

alpha particle mass	6.6446573357e-27 kg
alpha particle mass energy equivalent	5.9719201914e-10 J
alpha particle mass energy equivalent in MeV	3727.3794066 MeV
alpha particle mass in u	4.001506179127 u
alpha particle molar mass	0.0040015061777 kg mol ⁻¹
alpha particle relative atomic mass	4.001506179127
alpha particle-electron mass ratio	7294.29954142
alpha particle-proton mass ratio	3.97259969009
Angstrom star	1.00001495e-10 m
atomic mass constant	1.6605390666e-27 kg
atomic mass constant energy equivalent	1.4924180856e-10 J
atomic mass constant energy equivalent in MeV	931.49410242 MeV
atomic mass unit-electron volt relationship	931494102.42 eV
atomic mass unit-hartree relationship	34231776.874 E _h
atomic mass unit-hertz relationship	2.25234271871e+23 Hz
atomic mass unit-inverse meter relationship	751300661040000.0 m ⁻¹
atomic mass unit-joule relationship	1.4924180856e-10 J
atomic mass unit-kelvin relationship	10809540191600.0 K
atomic mass unit-kilogram relationship	1.6605390666e-27 kg
atomic unit of 1st hyperpolarizability	3.2063613061e-53 C ³ m ³ J ⁻²
atomic unit of 2nd hyperpolarizability	6.2353799905e-65 C ⁴ m ⁴ J ⁻³
atomic unit of action	1.054571817e-34 J s
atomic unit of charge	1.602176634e-19 C
atomic unit of charge density	1081202384570.0 C m ⁻³
atomic unit of current	0.00662361823751 A
atomic unit of electric dipole mom.	8.4783536255e-30 C m
atomic unit of electric field	514220674763.0 V m ⁻¹
atomic unit of electric field gradient	9.7173624292e+21 V m ⁻²
atomic unit of electric polarizability	1.64877727436e-41 C ² m ² J ⁻¹
atomic unit of electric potential	27.211386245988 V
atomic unit of electric quadrupole mom.	4.4865515246e-40 C m ²

continues on next page

Table 13 – continued from previous page

atomic unit of energy	4.3597447222071e-18 J
atomic unit of force	8.2387234983e-08 N
atomic unit of length	5.29177210903e-11 m
atomic unit of mag. dipole mom.	1.85480201566e-23 J T ⁻¹
atomic unit of mag. flux density	235051.756758 T
atomic unit of magnetizability	7.8910366008e-29 J T ⁻²
atomic unit of mass	9.1093837015e-31 kg
atomic unit of momentum	1.9928519141e-24 kg m s ⁻¹
atomic unit of permittivity	1.11265005545e-10 F m ⁻¹
atomic unit of time	2.4188843265857e-17 s
atomic unit of velocity	2187691.26364 m s ⁻¹
Avogadro constant	6.02214076e+23 mol ⁻¹
Bohr magneton	9.2740100783e-24 J T ⁻¹
Bohr magneton in eV/T	5.788381806e-05 eV T ⁻¹
Bohr magneton in Hz/T	13996244936.1 Hz T ⁻¹
Bohr magneton in inverse meter per tesla	46.686447783 m ⁻¹ T ⁻¹
Bohr magneton in K/T	0.67171381563 K T ⁻¹
Bohr radius	5.29177210903e-11 m
Boltzmann constant	1.380649e-23 J K ⁻¹
Boltzmann constant in eV/K	8.617333262e-05 eV K ⁻¹
Boltzmann constant in Hz/K	20836619120.0 Hz K ⁻¹
Boltzmann constant in inverse meter per kelvin	69.50348004 m ⁻¹ K ⁻¹
classical electron radius	2.8179403262e-15 m
Compton wavelength	2.42631023867e-12 m
conductance quantum	7.748091729e-05 S
conventional value of ampere-90	1.00000008887 A
conventional value of coulomb-90	1.00000008887 C
conventional value of farad-90	0.9999999822 F
conventional value of henry-90	1.00000001779 H
conventional value of Josephson constant	48359790000000.0 Hz V ⁻¹
conventional value of ohm-90	1.00000001779 ohm
conventional value of volt-90	1.00000010666 V
conventional value of von Klitzing constant	25812.807 ohm
conventional value of watt-90	1.00000019553 W
Cu x unit	1.00207697e-13 m
deuteron g factor	0.8574382338
deuteron mag. mom.	4.330735094e-27 J T ⁻¹
deuteron mag. mom. to Bohr magneton ratio	0.000466975457
deuteron mag. mom. to nuclear magneton ratio	0.8574382338
deuteron mass	3.3435837724e-27 kg
deuteron mass energy equivalent	3.00506323102e-10 J
deuteron mass energy equivalent in MeV	1875.61294257 MeV
deuteron mass in u	2.013553212745 u
deuteron molar mass	0.00201355321205 kg mol ⁻¹
deuteron relative atomic mass	2.013553212745
deuteron rms charge radius	2.12799e-15 m
deuteron-electron mag. mom. ratio	-0.000466434551
deuteron-electron mass ratio	3670.48296788
deuteron-neutron mag. mom. ratio	-0.44820653
deuteron-proton mag. mom. ratio	0.30701220939

continues on next page

Table 13 – continued from previous page

deuteron-proton mass ratio	1.99900750139
electron charge to mass quotient	-175882001076.0 C kg ⁻¹
electron g factor	-2.00231930436256
electron gyromag. ratio	176085963023.0 s ⁻¹ T ⁻¹
electron gyromag. ratio in MHz/T	28024.9514242 MHz T ⁻¹
electron mag. mom.	-9.2847647043e-24 J T ⁻¹
electron mag. mom. anomaly	0.00115965218128
electron mag. mom. to Bohr magneton ratio	-1.00115965218128
electron mag. mom. to nuclear magneton ratio	-1838.28197188
electron mass	9.1093837015e-31 kg
electron mass energy equivalent	8.1871057769e-14 J
electron mass energy equivalent in MeV	0.51099895 MeV
electron mass in u	0.000548579909065 u
electron molar mass	5.4857990888e-07 kg mol ⁻¹
electron relative atomic mass	0.000548579909065
electron to alpha particle mass ratio	0.0001370933554787
electron to shielded helion mag. mom. ratio	864.058257
electron to shielded proton mag. mom. ratio	-658.2275971
electron volt	1.602176634e-19 J
electron volt-atomic mass unit relationship	1.07354410233e-09 u
electron volt-hartree relationship	0.036749322175655 E _h
electron volt-hertz relationship	241798924200000.0 Hz
electron volt-inverse meter relationship	806554.3937 m ⁻¹
electron volt-joule relationship	1.602176634e-19 J
electron volt-kelvin relationship	11604.51812 K
electron volt-kilogram relationship	1.782661921e-36 kg
electron-deuteron mag. mom. ratio	-2143.9234915
electron-deuteron mass ratio	0.0002724437107462
electron-helion mass ratio	0.0001819543074573
electron-muon mag. mom. ratio	206.7669883
electron-muon mass ratio	0.00483633169
electron-neutron mag. mom. ratio	960.9205
electron-neutron mass ratio	0.00054386734424
electron-proton mag. mom. ratio	-658.21068789
electron-proton mass ratio	0.000544617021487
electron-tau mass ratio	0.000287585
electron-triton mass ratio	0.0001819200062251
elementary charge	1.602176634e-19 C
elementary charge over h-bar	1519267447000000.0 A J ⁻¹
Faraday constant	96485.33212 C mol ⁻¹
Fermi coupling constant	1.1663787e-05 GeV ⁻²
fine-structure constant	0.0072973525693
first radiation constant	3.741771852e-16 W m ²
first radiation constant for spectral radiance	1.191042972e-16 W m ² sr ⁻¹
Hartree energy	4.3597447222071e-18 J
Hartree energy in eV	27.211386245988 eV
hartree-atomic mass unit relationship	2.92126232205e-08 u
hartree-electron volt relationship	27.211386245988 eV
hartree-hertz relationship	6579683920502000.0 Hz
hartree-inverse meter relationship	21947463.13632 m ⁻¹

continues on next page

Table 13 – continued from previous page

hartree-joule relationship	4.3597447222071e-18 J
hartree-kelvin relationship	315775.02480407 K
hartree-kilogram relationship	4.8508702095432e-35 kg
helion g factor	-4.255250615
helion mag. mom.	-1.074617532e-26 J T ⁻¹
helion mag. mom. to Bohr magneton ratio	-0.001158740958
helion mag. mom. to nuclear magneton ratio	-2.127625307
helion mass	5.0064127796e-27 kg
helion mass energy equivalent	4.4995394125e-10 J
helion mass energy equivalent in MeV	2808.39160743 MeV
helion mass in u	3.014932247175 u
helion molar mass	0.00301493224613 kg mol ⁻¹
helion relative atomic mass	3.014932247175
helion shielding shift	5.996743e-05
helion-electron mass ratio	5495.88528007
helion-proton mass ratio	2.99315267167
hertz-atomic mass unit relationship	4.4398216652e-24 u
hertz-electron volt relationship	4.135667696e-15 eV
hertz-hartree relationship	1.519829846057e-16 E _h
hertz-inverse meter relationship	3.3356409519815204e-09 m ⁻¹
hertz-joule relationship	6.62607015e-34 J
hertz-kelvin relationship	4.799243073e-11 K
hertz-kilogram relationship	7.372497323e-51 kg
hyperfine transition frequency of Cs-133	9192631770.0 Hz
inverse fine-structure constant	137.035999084
inverse meter-atomic mass unit relationship	1.3310250501e-15 u
inverse meter-electron volt relationship	1.239841984e-06 eV
inverse meter-hartree relationship	4.556335252912e-08 E _h
inverse meter-hertz relationship	299792458.0 Hz
inverse meter-joule relationship	1.986445857e-25 J
inverse meter-kelvin relationship	0.01438776877 K
inverse meter-kilogram relationship	2.210219094e-42 kg
inverse of conductance quantum	12906.40372 ohm
Josephson constant	483597848400000.0 Hz V ⁻¹
joule-atomic mass unit relationship	6700535256.5 u
joule-electron volt relationship	6.241509074e+18 eV
joule-hartree relationship	2.2937122783963e+17 E _h
joule-hertz relationship	1.509190179e+33 Hz
joule-inverse meter relationship	5.034116567e+24 m ⁻¹
joule-kelvin relationship	7.242970516e+22 K
joule-kilogram relationship	1.1126500560536185e-17 kg
kelvin-atomic mass unit relationship	9.2510873014e-14 u
kelvin-electron volt relationship	8.617333262e-05 eV
kelvin-hartree relationship	3.1668115634556e-06 E _h
kelvin-hertz relationship	20836619120.0 Hz
kelvin-inverse meter relationship	69.50348004 m ⁻¹
kelvin-joule relationship	1.380649e-23 J
kelvin-kilogram relationship	1.536179187e-40 kg
kilogram-atomic mass unit relationship	6.0221407621e+26 u
kilogram-electron volt relationship	5.609588603e+35 eV

continues on next page

Table 13 – continued from previous page

kilogram-hartree relationship	2.0614857887409e+34 E _h
kilogram-hertz relationship	1.356392489e+50 Hz
kilogram-inverse meter relationship	4.524438335e+41 m ⁻¹
kilogram-joule relationship	8.987551787368176e+16 J
kilogram-kelvin relationship	6.50965726e+39 K
lattice parameter of silicon	5.431020511e-10 m
lattice spacing of ideal Si (220)	1.920155716e-10 m
Loschmidt constant (273.15 K, 100 kPa)	2.651645804e+25 m ⁻³
Loschmidt constant (273.15 K, 101.325 kPa)	2.686780111e+25 m ⁻³
luminous efficacy	683.0 lm W ⁻¹
mag. flux quantum	2.067833848e-15 Wb
Mo x unit	1.00209952e-13 m
molar gas constant	8.314462618 J mol ⁻¹ K ⁻¹
molar mass constant	0.0009999999965 kg mol ⁻¹
molar mass of carbon-12	0.011999999958 kg mol ⁻¹
molar Planck constant	3.990312712e-10 J Hz ⁻¹ mol ⁻¹
molar volume of ideal gas (273.15 K, 100 kPa)	0.02271095464 m ³ mol ⁻¹
molar volume of ideal gas (273.15 K, 101.325 kPa)	0.02241396954 m ³ mol ⁻¹
molar volume of silicon	1.205883199e-05 m ³ mol ⁻¹
muon Compton wavelength	1.17344411e-14 m
muon g factor	-2.0023318418
muon mag. mom.	-4.4904483e-26 J T ⁻¹
muon mag. mom. anomaly	0.00116592089
muon mag. mom. to Bohr magneton ratio	-0.00484197047
muon mag. mom. to nuclear magneton ratio	-8.89059703
muon mass	1.883531627e-28 kg
muon mass energy equivalent	1.692833804e-11 J
muon mass energy equivalent in MeV	105.6583755 MeV
muon mass in u	0.1134289259 u
muon molar mass	0.0001134289259 kg mol ⁻¹
muon-electron mass ratio	206.768283
muon-neutron mass ratio	0.112454517
muon-proton mag. mom. ratio	-3.183345142
muon-proton mass ratio	0.1126095264
muon-tau mass ratio	0.0594635
natural unit of action	1.054571817e-34 J s
natural unit of action in eV s	6.582119569e-16 eV s
natural unit of energy	8.1871057769e-14 J
natural unit of energy in MeV	0.51099895 MeV
natural unit of length	3.8615926796e-13 m
natural unit of mass	9.1093837015e-31 kg
natural unit of momentum	2.730924488e-22 kg m s ⁻¹
natural unit of momentum in MeV/c	0.5109989461 MeV/c
natural unit of time	1.28808866819e-21 s
natural unit of velocity	299792458.0 m s ⁻¹
neutron Compton wavelength	1.31959090581e-15 m
neutron g factor	-3.82608545
neutron gyromag. ratio	183247171.0 s ⁻¹ T ⁻¹
neutron gyromag. ratio in MHz/T	29.1646931 MHz T ⁻¹
neutron mag. mom.	-9.6623651e-27 J T ⁻¹

continues on next page

Table 13 – continued from previous page

neutron mag. mom. to Bohr magneton ratio	-0.00104187563
neutron mag. mom. to nuclear magneton ratio	-1.91304273
neutron mass	1.67492749804e-27 kg
neutron mass energy equivalent	1.50534976287e-10 J
neutron mass energy equivalent in MeV	939.56542052 MeV
neutron mass in u	1.00866491595 u
neutron molar mass	0.0010086649156 kg mol ⁻¹
neutron relative atomic mass	1.00866491595
neutron to shielded proton mag. mom. ratio	-0.68499694
neutron-electron mag. mom. ratio	0.00104066882
neutron-electron mass ratio	1838.68366173
neutron-muon mass ratio	8.89248406
neutron-proton mag. mom. ratio	-0.68497934
neutron-proton mass difference	2.30557435e-30 kg
neutron-proton mass difference energy equivalent	2.07214689e-13 J
neutron-proton mass difference energy equivalent in MeV	1.29333236 MeV
neutron-proton mass difference in u	0.00138844933 u
neutron-proton mass ratio	1.00137841931
neutron-tau mass ratio	0.528779
Newtonian constant of gravitation	6.6743e-11 m ³ kg ⁻¹ s ⁻²
Newtonian constant of gravitation over h-bar c	6.70883e-39 (GeV/c ²) ⁻²
nuclear magneton	5.0507837461e-27 J T ⁻¹
nuclear magneton in eV/T	3.15245125844e-08 eV T ⁻¹
nuclear magneton in inverse meter per tesla	0.0254262341353 m ⁻¹ T ⁻¹
nuclear magneton in K/T	0.00036582677756 K T ⁻¹
nuclear magneton in MHz/T	7.6225932291 MHz T ⁻¹
Planck constant	6.62607015e-34 J Hz ⁻¹
Planck constant in eV/Hz	4.135667696e-15 eV Hz ⁻¹
Planck length	1.616255e-35 m
Planck mass	2.176434e-08 kg
Planck mass energy equivalent in GeV	1.22089e+19 GeV
Planck temperature	1.416784e+32 K
Planck time	5.391247e-44 s
proton charge to mass quotient	95788331.56 C kg ⁻¹
proton Compton wavelength	1.32140985539e-15 m
proton g factor	5.5856946893
proton gyromag. ratio	267522187.44 s ⁻¹ T ⁻¹
proton gyromag. ratio in MHz/T	42.577478518 MHz T ⁻¹
proton mag. mom.	1.41060679736e-26 J T ⁻¹
proton mag. mom. to Bohr magneton ratio	0.0015210322023
proton mag. mom. to nuclear magneton ratio	2.79284734463
proton mag. shielding correction	2.5689e-05
proton mass	1.67262192369e-27 kg
proton mass energy equivalent	1.50327761598e-10 J
proton mass energy equivalent in MeV	938.27208816 MeV
proton mass in u	1.007276466621 u
proton molar mass	0.00100727646627 kg mol ⁻¹
proton relative atomic mass	1.007276466621
proton rms charge radius	8.414e-16 m
proton-electron mass ratio	1836.15267343

continues on next page

Table 13 – continued from previous page

proton-muon mass ratio	8.88024337
proton-neutron mag. mom. ratio	-1.45989805
proton-neutron mass ratio	0.99862347812
proton-tau mass ratio	0.528051
quantum of circulation	0.00036369475516 m ² s ⁻¹
quantum of circulation times 2	0.00072738951032 m ² s ⁻¹
reduced Compton wavelength	3.8615926796e-13 m
reduced muon Compton wavelength	1.867594306e-15 m
reduced neutron Compton wavelength	2.1001941552e-16 m
reduced Planck constant	1.054571817e-34 J s
reduced Planck constant in eV s	6.582119569e-16 eV s
reduced Planck constant times c in MeV fm	197.3269804 MeV fm
reduced proton Compton wavelength	2.10308910336e-16 m
reduced tau Compton wavelength	1.110538e-16 m
Rydberg constant	10973731.56816 m ⁻¹
Rydberg constant times c in Hz	3289841960250800.0 Hz
Rydberg constant times hc in eV	13.605693122994 eV
Rydberg constant times hc in J	2.1798723611035e-18 J
Sackur-Tetrode constant (1 K, 100 kPa)	-1.15170753706
Sackur-Tetrode constant (1 K, 101.325 kPa)	-1.16487052358
second radiation constant	0.01438776877 m K
shielded helion gyromag. ratio	203789456.9 s ⁻¹ T ⁻¹
shielded helion gyromag. ratio in MHz/T	32.43409942 MHz T ⁻¹
shielded helion mag. mom.	-1.07455309e-26 J T ⁻¹
shielded helion mag. mom. to Bohr magneton ratio	-0.001158671471
shielded helion mag. mom. to nuclear magneton ratio	-2.127497719
shielded helion to proton mag. mom. ratio	-0.7617665618
shielded helion to shielded proton mag. mom. ratio	-0.7617861313
shielded proton gyromag. ratio	267515315.1 s ⁻¹ T ⁻¹
shielded proton gyromag. ratio in MHz/T	42.57638474 MHz T ⁻¹
shielded proton mag. mom.	1.41057056e-26 J T ⁻¹
shielded proton mag. mom. to Bohr magneton ratio	0.001520993128
shielded proton mag. mom. to nuclear magneton ratio	2.792775599
shielding difference of d and p in HD	2.02e-08
shielding difference of t and p in HT	2.414e-08
speed of light in vacuum	299792458.0 m s ⁻¹
standard acceleration of gravity	9.80665 m s ⁻²
standard atmosphere	101325.0 Pa
standard-state pressure	100000.0 Pa
Stefan-Boltzmann constant	5.670374419e-08 W m ⁻² K ⁻⁴
tau Compton wavelength	6.97771e-16 m
tau energy equivalent	1776.86 MeV
tau mass	3.16754e-27 kg
tau mass energy equivalent	2.84684e-10 J
tau mass in u	1.90754 u
tau molar mass	0.00190754 kg mol ⁻¹
tau-electron mass ratio	3477.23
tau-muon mass ratio	16.817
tau-neutron mass ratio	1.89115
tau-proton mass ratio	1.89376

continues on next page

Table 13 – continued from previous page

Thomson cross section	6.6524587321e-29 m ²
triton g factor	5.957924931
triton mag. mom.	1.5046095202e-26 J T ⁻¹
triton mag. mom. to Bohr magneton ratio	0.0016223936651
triton mag. mom. to nuclear magneton ratio	2.9789624656
triton mass	5.0073567446e-27 kg
triton mass energy equivalent	4.500387806e-10 J
triton mass energy equivalent in MeV	2808.92113298 MeV
triton mass in u	3.01550071621 u
triton molar mass	0.00301550071517 kg mol ⁻¹
triton relative atomic mass	3.01550071621
triton to proton mag. mom. ratio	1.0666399191
triton-electron mass ratio	5496.92153573
triton-proton mass ratio	2.99371703414
unified atomic mass unit	1.6605390666e-27 kg
vacuum electric permittivity	8.8541878128e-12 F m ⁻¹
vacuum mag. permeability	1.25663706212e-06 N A ⁻²
von Klitzing constant	25812.80745 ohm
W to Z mass ratio	0.88153
weak mixing angle	0.2229
Wien frequency displacement law constant	58789257570.0 Hz K ⁻¹
Wien wavelength displacement law constant	0.002897771955 m K

6.4.3 Units

SI prefixes

yotta	10 ²⁴
zetta	10 ²¹
exa	10 ¹⁸
peta	10 ¹⁵
tera	10 ¹²
giga	10 ⁹
mega	10 ⁶
kilo	10 ³
hecto	10 ²
deka	10 ¹
deci	10 ⁻¹
centi	10 ⁻²
milli	10 ⁻³
micro	10 ⁻⁶
nano	10 ⁻⁹
pico	10 ⁻¹²
femto	10 ⁻¹⁵
atto	10 ⁻¹⁸
zepto	10 ⁻²¹

Binary prefixes

kibi	2^{10}
mebi	2^{20}
gibi	2^{30}
tebi	2^{40}
pebi	2^{50}
exbi	2^{60}
zebi	2^{70}
yobi	2^{80}

Mass

gram	10^{-3} kg
metric_ton	10^3 kg
grain	one grain in kg
lb	one pound (avoirdupois) in kg
pound	one pound (avoirdupois) in kg
blob	one inch version of a slug in kg (added in 1.0.0)
slinch	one inch version of a slug in kg (added in 1.0.0)
slug	one slug in kg (added in 1.0.0)
oz	one ounce in kg
ounce	one ounce in kg
stone	one stone in kg
grain	one grain in kg
long_ton	one long ton in kg
short_ton	one short ton in kg
troy_ounce	one Troy ounce in kg
troy_pound	one Troy pound in kg
carat	one carat in kg
m_u	atomic mass constant (in kg)
u	atomic mass constant (in kg)
atomic_mass	atomic mass constant (in kg)

Angle

degree	degree in radians
arcmin	arc minute in radians
arcminute	arc minute in radians
arcsec	arc second in radians
arcsecond	arc second in radians

Time

minute	one minute in seconds
hour	one hour in seconds
day	one day in seconds
week	one week in seconds
year	one year (365 days) in seconds
Julian_year	one Julian year (365.25 days) in seconds

Length

inch	one inch in meters
foot	one foot in meters
yard	one yard in meters
mile	one mile in meters
mil	one mil in meters
pt	one point in meters
point	one point in meters
survey_foot	one survey foot in meters
survey_mile	one survey mile in meters
nautical_mile	one nautical mile in meters
fermi	one Fermi in meters
angstrom	one Angstrom in meters
micron	one micron in meters
au	one astronomical unit in meters
astronomical_unit	one astronomical unit in meters
light_year	one light year in meters
parsec	one parsec in meters

Pressure

atm	standard atmosphere in pascals
atmosphere	standard atmosphere in pascals
bar	one bar in pascals
torr	one torr (mmHg) in pascals
mmHg	one torr (mmHg) in pascals
psi	one psi in pascals

Area

hectare	one hectare in square meters
acre	one acre in square meters

Volume

liter	one liter in cubic meters
litre	one liter in cubic meters
gallon	one gallon (US) in cubic meters
gallon_US	one gallon (US) in cubic meters
gallon_imp	one gallon (UK) in cubic meters
fluid_ounce	one fluid ounce (US) in cubic meters
fluid_ounce_US	one fluid ounce (US) in cubic meters
fluid_ounce_imp	one fluid ounce (UK) in cubic meters
bbl	one barrel in cubic meters
barrel	one barrel in cubic meters

Speed

kmh	kilometers per hour in meters per second
mph	miles per hour in meters per second
mach	one Mach (approx., at 15 C, 1 atm) in meters per second
speed_of_sound	one Mach (approx., at 15 C, 1 atm) in meters per second
knot	one knot in meters per second

Temperature

zero_Celsius	zero of Celsius scale in Kelvin
degree_Fahrenheit	one Fahrenheit (only differences) in Kelvins

`convert_temperature(val, old_scale, new_scale)` Convert from a temperature scale to another one among Celsius, Kelvin, Fahrenheit, and Rankine scales.

scipy.constants.convert_temperature

`scipy.constants.convert_temperature` (*val, old_scale, new_scale*)

Convert from a temperature scale to another one among Celsius, Kelvin, Fahrenheit, and Rankine scales.

Parameters

- val** [array_like] Value(s) of the temperature(s) to be converted expressed in the original scale.
- old_scale: str**
Specifies as a string the original scale from which the temperature value(s) will be converted. Supported scales are Celsius ('Celsius', 'celsius', 'C' or 'c'), Kelvin ('Kelvin', 'kelvin', 'K', 'k'), Fahrenheit ('Fahrenheit', 'fahrenheit', 'F' or 'f'), and Rankine ('Rankine', 'rankine', 'R', 'r').
- new_scale: str**

Specifies as a string the new scale to which the temperature value(s) will be converted. Supported scales are Celsius ('Celsius', 'celsius', 'C' or 'c'), Kelvin ('Kelvin', 'kelvin', 'K', 'k'), Fahrenheit ('Fahrenheit', 'fahrenheit', 'F' or 'f'), and Rankine ('Rankine', 'rankine', 'R', 'r').

Returns

res [float or array of floats] Value(s) of the converted temperature(s) expressed in the new scale.

Notes

New in version 0.18.0.

Examples

```
>>> from scipy.constants import convert_temperature
>>> convert_temperature(np.array([-40, 40]), 'Celsius', 'Kelvin')
array([ 233.15,  313.15])
```

Energy

eV	one electron volt in Joules
electron_volt	one electron volt in Joules
calorie	one calorie (thermochemical) in Joules
calorie_th	one calorie (thermochemical) in Joules
calorie_IT	one calorie (International Steam Table calorie, 1956) in Joules
erg	one erg in Joules
Btu	one British thermal unit (International Steam Table) in Joules
Btu_IT	one British thermal unit (International Steam Table) in Joules
Btu_th	one British thermal unit (thermochemical) in Joules
ton_TNT	one ton of TNT in Joules

Power

hp	one horsepower in watts
horsepower	one horsepower in watts

Force

dyn	one dyne in newtons
dyne	one dyne in newtons
lbf	one pound force in newtons
pound_force	one pound force in newtons
kgf	one kilogram force in newtons
kilogram_force	one kilogram force in newtons

Optics

<code>lambda2nu(lambda_)</code>	Convert wavelength to optical frequency
<code>nu2lambda(nu)</code>	Convert optical frequency to wavelength.

`scipy.constants.lambda2nu`

`scipy.constants.lambda2nu(lambda_)`
Convert wavelength to optical frequency

Parameters

lambda_ [array_like] Wavelength(s) to be converted.

Returns

nu [float or array of floats] Equivalent optical frequency.

Notes

Computes $\nu = c / \lambda$ where $c = 299792458.0$, i.e., the (vacuum) speed of light in meters/second.

Examples

```
>>> from scipy.constants import lambda2nu, speed_of_light
>>> lambda2nu(np.array([1, speed_of_light]))
array([ 2.99792458e+08,  1.00000000e+00])
```

`scipy.constants.nu2lambda`

`scipy.constants.nu2lambda(nu)`
Convert optical frequency to wavelength.

Parameters

nu [array_like] Optical frequency to be converted.

Returns

lambda [float or array of floats] Equivalent wavelength(s).

Notes

Computes $\lambda = c / \nu$ where $c = 299792458.0$, i.e., the (vacuum) speed of light in meters/second.

Examples

```
>>> from scipy.constants import nu2lambda, speed_of_light
>>> nu2lambda(np.array((1, speed_of_light)))
array([ 2.99792458e+08,  1.00000000e+00])
```

6.4.4 References

6.5 Discrete Fourier transforms (`scipy.fft`)

6.5.1 Fast Fourier Transforms (FFTs)

<code>fft(x[, n, axis, norm, overwrite_x, ...])</code>	Compute the 1-D discrete Fourier Transform.
<code>ifft(x[, n, axis, norm, overwrite_x, ...])</code>	Compute the 1-D inverse discrete Fourier Transform.
<code>fft2(x[, s, axes, norm, overwrite_x, ...])</code>	Compute the 2-D discrete Fourier Transform
<code>ifft2(x[, s, axes, norm, overwrite_x, ...])</code>	Compute the 2-D inverse discrete Fourier Transform.
<code>fftn(x[, s, axes, norm, overwrite_x, ...])</code>	Compute the N-D discrete Fourier Transform.
<code>ifftn(x[, s, axes, norm, overwrite_x, ...])</code>	Compute the N-D inverse discrete Fourier Transform.
<code>rfft(x[, n, axis, norm, overwrite_x, ...])</code>	Compute the 1-D discrete Fourier Transform for real input.
<code>irfft(x[, n, axis, norm, overwrite_x, ...])</code>	Computes the inverse of <code>rfft</code> .
<code>rfft2(x[, s, axes, norm, overwrite_x, ...])</code>	Compute the 2-D FFT of a real array.
<code>irfft2(x[, s, axes, norm, overwrite_x, ...])</code>	Computes the inverse of <code>rfft2</code>
<code>rfftn(x[, s, axes, norm, overwrite_x, ...])</code>	Compute the N-D discrete Fourier Transform for real input.
<code>irfftn(x[, s, axes, norm, overwrite_x, ...])</code>	Computes the inverse of <code>rfftn</code>
<code>hfft(x[, n, axis, norm, overwrite_x, ...])</code>	Compute the FFT of a signal that has Hermitian symmetry, i.e., a real spectrum.
<code>ihfft(x[, n, axis, norm, overwrite_x, ...])</code>	Compute the inverse FFT of a signal that has Hermitian symmetry.
<code>hfft2(x[, s, axes, norm, overwrite_x, ...])</code>	Compute the 2-D FFT of a Hermitian complex array.
<code>ihfft2(x[, s, axes, norm, overwrite_x, ...])</code>	Compute the 2-D inverse FFT of a real spectrum.
<code>hfftn(x[, s, axes, norm, overwrite_x, ...])</code>	Compute the N-D FFT of Hermitian symmetric complex input, i.e., a signal with a real spectrum.
<code>ihfftn(x[, s, axes, norm, overwrite_x, ...])</code>	Compute the N-D inverse discrete Fourier Transform for a real spectrum.

`scipy.fft.fft`

`scipy.fft.fft(x, n=None, axis=-1, norm=None, overwrite_x=False, workers=None, *, plan=None)`
 Compute the 1-D discrete Fourier Transform.

This function computes the 1-D n -point discrete Fourier Transform (DFT) with the efficient Fast Fourier Transform (FFT) algorithm [1].

Parameters

- x** [array_like] Input array, can be complex.
- n** [int, optional] Length of the transformed axis of the output. If n is smaller than the length of the input, the input is cropped. If it is larger, the input is padded with zeros. If n is not

given, the length of the input along the axis specified by *axis* is used.

axis [int, optional] Axis over which to compute the FFT. If not given, the last axis is used.

norm [{"backward", "ortho", "forward"}, optional] Normalization mode. Default is "backward", meaning no normalization on the forward transforms and scaling by $1/n$ on the *ifft*. "forward" instead applies the $1/n$ factor on the forward transform. For `norm="ortho"`, both directions are scaled by $1/\sqrt{n}$.
New in version 1.6.0: `norm={"forward", "backward"}` options were added

overwrite_x [bool, optional] If True, the contents of *x* can be destroyed; the default is False. See the notes below for more details.

workers [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See below for more details.

plan: object, optional
This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
New in version 1.5.0.

Returns

out [complex ndarray] The truncated or zero-padded input, transformed along the axis indicated by *axis*, or the last one if *axis* is not specified.

Raises**IndexError**

if *axes* is larger than the last axis of *x*.

See also:*ifft*

The inverse of *fft*.

fft2

The 2-D FFT.

fftn

The N-D FFT.

rfftn

The N-D FFT of real input.

fftfreq

Frequency bins for given FFT parameters.

next_fast_len

Size to pad input to for most efficient transforms

Notes

FFT (Fast Fourier Transform) refers to a way the discrete Fourier Transform (DFT) can be calculated efficiently, by using symmetries in the calculated terms. The symmetry is highest when n is a power of 2, and the transform is therefore most efficient for these sizes. For poorly factorizable sizes, `scipy.fft` uses Bluestein's algorithm [2] and so is never worse than $O(n \log n)$. Further performance improvements may be seen by zero-padding the input using `next_fast_len`.

If x is a 1d array, then the `fft` is equivalent to

```
y[k] = np.sum(x * np.exp(-2j * np.pi * k * np.arange(n)/n))
```

The frequency term $f=k/n$ is found at `y[k]`. At `y[n/2]` we reach the Nyquist frequency and wrap around to the negative-frequency terms. So, for an 8-point transform, the frequencies of the result are [0, 1, 2, 3, -4, -3, -2, -1]. To rearrange the `fft` output so that the zero-frequency component is centered, like [-4, -3, -2, -1, 0, 1, 2, 3], use `fftshift`.

Transforms can be done in single, double, or extended precision (long double) floating point. Half precision inputs will be converted to single precision and non-floating-point inputs will be converted to double precision.

If the data type of x is real, a “real FFT” algorithm is automatically used, which roughly halves the computation time. To increase efficiency a little further, use `rfft`, which does the same calculation, but only outputs half of the symmetrical spectrum. If the data are both real and symmetrical, the `dct` can again double the efficiency, by generating half of the spectrum from half of the signal.

When `overwrite_x=True` is specified, the memory referenced by x may be used by the implementation in any way. This may include reusing the memory for the result, but this is in no way guaranteed. You should not rely on the contents of x after the transform as this may change in future without warning.

The `workers` argument specifies the maximum number of parallel jobs to split the FFT computation into. This will execute independent 1-D FFTs within x . So, x must be at least 2-D and the non-transformed axes must be large enough to split into chunks. If x is too small, fewer jobs may be used than requested.

References

[1], [2]

Examples

```
>>> import scipy.fft
>>> scipy.fft.fft(np.exp(2j * np.pi * np.arange(8) / 8))
array([-2.33486982e-16+1.14423775e-17j,  8.00000000e+00-1.25557246e-15j,
        2.33486982e-16+2.33486982e-16j,  0.00000000e+00+1.22464680e-16j,
       -1.14423775e-17+2.33486982e-16j,  0.00000000e+00+5.20784380e-16j,
        1.14423775e-17+1.14423775e-17j,  0.00000000e+00+1.22464680e-16j])
```


In this example, real input has an FFT which is Hermitian, i.e., symmetric in the real part and anti-symmetric in the imaginary part:

```
>>> from scipy.fft import fft, fftfreq, fftshift
>>> import matplotlib.pyplot as plt
>>> t = np.arange(256)
>>> sp = fftshift(fft(np.sin(t)))
>>> freq = fftshift(fftfreq(t.shape[-1]))
```

(continues on next page)

(continued from previous page)

```
>>> plt.plot(freq, sp.real, freq, sp.imag)
[<matplotlib.lines.Line2D object at 0x...>, <matplotlib.lines.Line2D
  ↳object at 0x...>]
>>> plt.show()
```



scipy.fft.ifft

`scipy.fft.ifft(x, n=None, axis=-1, norm=None, overwrite_x=False, workers=None, *, plan=None)`

Compute the 1-D inverse discrete Fourier Transform.

This function computes the inverse of the 1-D n -point discrete Fourier transform computed by `fft`. In other words, `ifft(fft(x)) == x` to within numerical accuracy.

The input should be ordered in the same way as is returned by `fft`, i.e.,

- `x[0]` should contain the zero frequency term,
- `x[1:n//2]` should contain the positive-frequency terms,
- `x[n//2 + 1:]` should contain the negative-frequency terms, in increasing order starting from the most negative frequency.

For an even number of input points, `x[n//2]` represents the sum of the values at the positive and negative Nyquist frequencies, as the two are aliased together. See `fft` for details.

Parameters

x	[array_like] Input array, can be complex.
n	[int, optional] Length of the transformed axis of the output. If n is smaller than the length of the input, the input is cropped. If it is larger, the input is padded with zeros. If n is not given, the length of the input along the axis specified by <code>axis</code> is used. See notes about padding issues.
axis	[int, optional] Axis over which to compute the inverse DFT. If not given, the last axis is used.
norm	[{"backward", "ortho", "forward"}, optional] Normalization mode (see <code>fft</code>). Default is "backward".

overwrite_x

[bool, optional] If True, the contents of *x* can be destroyed; the default is False. See [fft](#) for more details.

workers

[int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See [fft](#) for more details.

plan: object, optional

This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.

New in version 1.5.0.

Returns**out**

[complex ndarray] The truncated or zero-padded input, transformed along the axis indicated by *axis*, or the last one if *axis* is not specified.

Raises**IndexError**

If *axes* is larger than the last axis of *x*.

See also:[fft](#)

The 1-D (forward) FFT, of which [ifft](#) is the inverse.

[ifft2](#)

The 2-D inverse FFT.

[ifftn](#)

The N-D inverse FFT.

Notes

If the input parameter *n* is larger than the size of the input, the input is padded by appending zeros at the end. Even though this is the common approach, it might lead to surprising results. If a different padding is desired, it must be performed before calling [ifft](#).

If *x* is a 1-D array, then the [ifft](#) is equivalent to

```
y[k] = np.sum(x * np.exp(2j * np.pi * k * np.arange(n)/n)) / len(x)
```

As with [fft](#), [ifft](#) has support for all floating point types and is optimized for real input.

Examples


```
>>> import scipy.fft
>>> scipy.fft.ifft([0, 4, 0, 0])
array([ 1.+0.j,  0.+1.j, -1.+0.j,  0.-1.j]) # may vary
```

Create and plot a band-limited signal with random phases:


```

>>> import matplotlib.pyplot as plt
>>> t = np.arange(400)
>>> n = np.zeros((400,), dtype=complex)
>>> n[40:60] = np.exp(1j*np.random.uniform(0, 2*np.pi, (20,)))
>>> s = scipy.fft.ifft(n)
>>> plt.plot(t, s.real, 'b-', t, s.imag, 'r--')
[<matplotlib.lines.Line2D object at ...>, <matplotlib.lines.Line2D object
  at ...>]
>>> plt.legend(('real', 'imaginary'))
<matplotlib.legend.Legend object at ...>
>>> plt.show()

```



scipy.fft.fft2

`scipy.fft.fft2(x, s=None, axes=-2, -1, norm=None, overwrite_x=False, workers=None, *, plan=None)`
 Compute the 2-D discrete Fourier Transform

This function computes the N-D discrete Fourier Transform over any axes in an M-D array by means of the Fast Fourier Transform (FFT). By default, the transform is computed over the last two axes of the input array, i.e., a 2-dimensional FFT.

Parameters

- x** [array_like] Input array, can be complex
- s** [sequence of ints, optional] Shape (length of each transformed axis) of the output (`s[0]` refers to axis 0, `s[1]` to axis 1, etc.). This corresponds to `n` for `fft(x, n)`. Along each axis, if the given shape is smaller than that of the input, the input is cropped. If it is larger, the input is padded with zeros. if `s` is not given, the shape of the input along the axes specified by `axes` is used.
- axes** [sequence of ints, optional] Axes over which to compute the FFT. If not given, the last two axes are used.
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see `fft`). Default is "backward".

overwrite_x

[bool, optional] If True, the contents of *x* can be destroyed; the default is False. See *fft* for more details.

workers

[int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See *fft* for more details.

plan: object, optional

This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.

New in version 1.5.0.

Returns

out

[complex ndarray] The truncated or zero-padded input, transformed along the axes indicated by *axes*, or the last two axes if *axes* is not given.

Raises

ValueError

If *s* and *axes* have different length, or *axes* not given and `len(s) != 2`.

IndexError

If an element of *axes* is larger than than the number of axes of *x*.

See also:

ifft2

The inverse 2-D FFT.

fft

The 1-D FFT.

fftn

The N-D FFT.

fftshift

Shifts zero-frequency terms to the center of the array. For 2-D input, swaps first and third quadrants, and second and fourth quadrants.

Notes

fft2 is just *fftn* with a different default for *axes*.

The output, analogously to *fft*, contains the term for zero frequency in the low-order corner of the transformed axes, the positive frequency terms in the first half of these axes, the term for the Nyquist frequency in the middle of the axes and the negative frequency terms in the second half of the axes, in order of decreasingly negative frequency.

See *fftn* for details and a plotting example, and *fft* for definitions and conventions used.

Examples

```
>>> import scipy.fft
>>> x = np.mgrid[:5, :5][0]
>>> scipy.fft.fft2(x)
array([[ 50. +0.j          ,  0. +0.j          ,  0. +0.j          , # may...
       ↪vary
        0. +0.j          ,  0. +0.j          ],
       [-12.5+17.20477401j,  0. +0.j          ,  0. +0.j          ,
        0. +0.j          ,  0. +0.j          ],
       [-12.5 +4.0614962j ,  0. +0.j          ,  0. +0.j          ,
        0. +0.j          ,  0. +0.j          ],
       [-12.5 -4.0614962j ,  0. +0.j          ,  0. +0.j          ,
        0. +0.j          ,  0. +0.j          ],
       [-12.5-17.20477401j,  0. +0.j          ,  0. +0.j          ,
        0. +0.j          ,  0. +0.j          ]])
```

scipy.fft.ifft2

`scipy.fft.ifft2(x, s=None, axes=-2, -1, norm=None, overwrite_x=False, workers=None, *, plan=None)`
 Compute the 2-D inverse discrete Fourier Transform.

This function computes the inverse of the 2-D discrete Fourier Transform over any number of axes in an M-D array by means of the Fast Fourier Transform (FFT). In other words, `ifft2(fft2(x)) == x` to within numerical accuracy. By default, the inverse transform is computed over the last two axes of the input array.

The input, analogously to `ifft`, should be ordered in the same way as is returned by `fft2`, i.e., it should have the term for zero frequency in the low-order corner of the two axes, the positive frequency terms in the first half of these axes, the term for the Nyquist frequency in the middle of the axes and the negative frequency terms in the second half of both axes, in order of decreasingly negative frequency.

Parameters

- x** [array_like] Input array, can be complex.
- s** [sequence of ints, optional] Shape (length of each axis) of the output (`s[0]` refers to axis 0, `s[1]` to axis 1, etc.). This corresponds to `n` for `ifft(x, n)`. Along each axis, if the given shape is smaller than that of the input, the input is cropped. If it is larger, the input is padded with zeros. if `s` is not given, the shape of the input along the axes specified by `axes` is used. See notes for issue on `ifft` zero padding.
- axes** [sequence of ints, optional] Axes over which to compute the FFT. If not given, the last two axes are used.
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see `fft`). Default is "backward".
- overwrite_x** [bool, optional] If True, the contents of `x` can be destroyed; the default is False. See `fft` for more details.
- workers** [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See `fft` for more details.
- plan: object, optional**
 This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
 New in version 1.5.0.

Returns

out [complex ndarray] The truncated or zero-padded input, transformed along the axes indicated by *axes*, or the last two axes if *axes* is not given.

Raises

ValueError

If *s* and *axes* have different length, or *axes* not given and $\text{len}(s) \neq 2$.

IndexError

If an element of *axes* is larger than than the number of axes of *x*.

See also:

fft2

The forward 2-D FFT, of which *ifft2* is the inverse.

ifftn

The inverse of the N-D FFT.

fft

The 1-D FFT.

ifft

The 1-D inverse FFT.

Notes

ifft2 is just *ifftn* with a different default for *axes*.

See *ifftn* for details and a plotting example, and *fft* for definition and conventions used.

Zero-padding, analogously with *ifft*, is performed by appending zeros to the input along the specified dimension. Although this is the common approach, it might lead to surprising results. If another form of zero padding is desired, it must be performed before *ifft2* is called.

Examples

```
>>> import scipy.fft
>>> x = 4 * np.eye(4)
>>> scipy.fft.ifft2(x)
array([[1.+0.j,  0.+0.j,  0.+0.j,  0.+0.j], # may vary
       [0.+0.j,  0.+0.j,  0.+0.j,  1.+0.j],
       [0.+0.j,  0.+0.j,  1.+0.j,  0.+0.j],
       [0.+0.j,  1.+0.j,  0.+0.j,  0.+0.j]])
```

scipy.fft.fftn

`scipy.fft.fftn(x, s=None, axes=None, norm=None, overwrite_x=False, workers=None, *, plan=None)`

Compute the N-D discrete Fourier Transform.

This function computes the N-D discrete Fourier Transform over any number of axes in an M-D array by means of the Fast Fourier Transform (FFT).

Parameters

- x** [array_like] Input array, can be complex.
- s** [sequence of ints, optional] Shape (length of each transformed axis) of the output (`s[0]` refers to axis 0, `s[1]` to axis 1, etc.). This corresponds to `n` for `fft(x, n)`. Along any axis, if the given shape is smaller than that of the input, the input is cropped. If it is larger, the input is padded with zeros. if `s` is not given, the shape of the input along the axes specified by `axes` is used.
- axes** [sequence of ints, optional] Axes over which to compute the FFT. If not given, the last `len(s)` axes are used, or all axes if `s` is also not specified.
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see `fft`). Default is "backward".
- overwrite_x** [bool, optional] If True, the contents of `x` can be destroyed; the default is False. See `fft` for more details.
- workers** [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See `fft` for more details.
- plan: object, optional**
This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
New in version 1.5.0.

Returns

- out** [complex ndarray] The truncated or zero-padded input, transformed along the axes indicated by `axes`, or by a combination of `s` and `x`, as explained in the parameters section above.

Raises

- ValueError**
If `s` and `axes` have different length.
- IndexError**
If an element of `axes` is larger than than the number of axes of `x`.

See also:***ifftn***

The inverse of `fftn`, the inverse N-D FFT.

fft

The 1-D FFT, with definitions and conventions used.

rfftn

The N-D FFT of real input.

fft2

The 2-D FFT.

fftshift

Shifts zero-frequency terms to centre of array.

Notes

The output, analogously to *fft*, contains the term for zero frequency in the low-order corner of all axes, the positive frequency terms in the first half of all axes, the term for the Nyquist frequency in the middle of all axes and the negative frequency terms in the second half of all axes, in order of decreasingly negative frequency.

Examples

```

>>> import scipy.fft
>>> x = np.mgrid[:3, :3, :3][0]
>>> scipy.fft.fftn(x, axes=(1, 2))
array([[ [ 0.+0.j,  0.+0.j,  0.+0.j], # may vary
         [ 0.+0.j,  0.+0.j,  0.+0.j],
         [ 0.+0.j,  0.+0.j,  0.+0.j]],
       [[ 9.+0.j,  0.+0.j,  0.+0.j],
         [ 0.+0.j,  0.+0.j,  0.+0.j],
         [ 0.+0.j,  0.+0.j,  0.+0.j]],
       [[18.+0.j,  0.+0.j,  0.+0.j],
         [ 0.+0.j,  0.+0.j,  0.+0.j],
         [ 0.+0.j,  0.+0.j,  0.+0.j]])
>>> scipy.fft.fftn(x, (2, 2), axes=(0, 1))
array([[ [ 2.+0.j,  2.+0.j,  2.+0.j], # may vary
         [ 0.+0.j,  0.+0.j,  0.+0.j]],
       [[-2.+0.j, -2.+0.j, -2.+0.j],
         [ 0.+0.j,  0.+0.j,  0.+0.j]])

```

```

>>> import matplotlib.pyplot as plt
>>> [X, Y] = np.meshgrid(2 * np.pi * np.arange(200) / 12,
...                      2 * np.pi * np.arange(200) / 34)
>>> S = np.sin(X) + np.cos(Y) + np.random.uniform(0, 1, X.shape)
>>> FS = scipy.fft.fftn(S)
>>> plt.imshow(np.log(np.abs(scipy.fft.fftshift(FS)**2)))
<matplotlib.image.AxesImage object at 0x...>
>>> plt.show()


```

scipy.fft.ifftn

`scipy.fft.ifftn(x, s=None, axes=None, norm=None, overwrite_x=False, workers=None, *, plan=None)`
Compute the N-D inverse discrete Fourier Transform.

This function computes the inverse of the N-D discrete Fourier Transform over any number of axes in an M-D array by means of the Fast Fourier Transform (FFT). In other words, `ifftn(fftn(x)) == x` to within numerical accuracy.

The input, analogously to *ifft*, should be ordered in the same way as is returned by *fftn*, i.e., it should have the term for zero frequency in all axes in the low-order corner, the positive frequency terms in the first half of all axes, the term for the Nyquist frequency in the middle of all axes and the negative frequency terms in the second half of all axes, in order of decreasingly negative frequency.



Parameters

- x** [array_like] Input array, can be complex.
- s** [sequence of ints, optional] Shape (length of each transformed axis) of the output ($s[0]$ refers to axis 0, $s[1]$ to axis 1, etc.). This corresponds to n for `ifft(x, n)`. Along any axis, if the given shape is smaller than that of the input, the input is cropped. If it is larger, the input is padded with zeros. If s is not given, the shape of the input along the axes specified by *axes* is used. See notes for issue on *ifft* zero padding.
- axes** [sequence of ints, optional] Axes over which to compute the IFFT. If not given, the last `len(s)` axes are used, or all axes if s is also not specified.
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see *fft*). Default is "backward".
- overwrite_x** [bool, optional] If True, the contents of x can be destroyed; the default is False. See *fft* for more details.
- workers** [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See *fft* for more details.
- plan: object, optional**
This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
New in version 1.5.0.

Returns

- out** [complex ndarray] The truncated or zero-padded input, transformed along the axes indicated by *axes*, or by a combination of s or x , as explained in the parameters section above.

Raises

- ValueError**
If s and *axes* have different length.
- IndexError**
If an element of *axes* is larger than than the number of axes of x .

See also:

fftn

The forward N-D FFT, of which `ifftn` is the inverse.

`ifft`

The 1-D inverse FFT.

`ifft2`

The 2-D inverse FFT.

`ifftshift`

Undoes `fftshift`, shifts zero-frequency terms to beginning of array.

Notes

Zero-padding, analogously with `ifft`, is performed by appending zeros to the input along the specified dimension. Although this is the common approach, it might lead to surprising results. If another form of zero padding is desired, it must be performed before `ifftn` is called.

Examples

```
>>> import scipy.fft
>>> x = np.eye(4)
>>> scipy.fft.ifftn(scipy.fft.fftn(x, axes=(0,)), axes=(1,))
array([[1.+0.j, 0.+0.j, 0.+0.j, 0.+0.j], # may vary
       [0.+0.j, 1.+0.j, 0.+0.j, 0.+0.j],
       [0.+0.j, 0.+0.j, 1.+0.j, 0.+0.j],
       [0.+0.j, 0.+0.j, 0.+0.j, 1.+0.j]])
```

Create and plot an image with band-limited frequency content:

```
>>> import matplotlib.pyplot as plt
>>> n = np.zeros((200,200), dtype=complex)
>>> n[60:80, 20:40] = np.exp(1j*np.random.uniform(0, 2*np.pi, (20, 20)))
>>> im = scipy.fft.ifftn(n).real
>>> plt.imshow(im)
<matplotlib.image.AxesImage object at 0x...>
>>> plt.show()
```

`scipy.fft.rfft`


`scipy.fft.rfft(x, n=None, axis=-1, norm=None, overwrite_x=False, workers=None, *, plan=None)`

Compute the 1-D discrete Fourier Transform for real input.

This function computes the 1-D n -point discrete Fourier Transform (DFT) of a real-valued array by means of an efficient algorithm called the Fast Fourier Transform (FFT).

Parameters

- | | |
|-------------|--|
| a | [array_like] Input array |
| n | [int, optional] Number of points along transformation axis in the input to use. If n is smaller than the length of the input, the input is cropped. If it is larger, the input is padded with zeros. If n is not given, the length of the input along the axis specified by <code>axis</code> is used. |
| axis | [int, optional] Axis over which to compute the FFT. If not given, the last axis is used. |



norm [{"backward", "ortho", "forward"}, optional] Normalization mode (see `fft`). Default is "backward".

overwrite_x [bool, optional] If True, the contents of `x` can be destroyed; the default is False. See `fft` for more details.

workers [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See `fft` for more details.

plan: object, optional
This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
New in version 1.5.0.

Returns

out [complex ndarray] The truncated or zero-padded input, transformed along the axis indicated by `axis`, or the last one if `axis` is not specified. If `n` is even, the length of the transformed axis is $(n/2) + 1$. If `n` is odd, the length is $(n+1) / 2$.

Raises

IndexError
If `axis` is larger than the last axis of `a`.

See also:

`irfft`

The inverse of `rfft`.

`fft`

The 1-D FFT of general (complex) input.

`fftn`

The N-D FFT.

`rfft2`

The 2-D FFT of real input.

rfftn

The N-D FFT of real input.

Notes

When the DFT is computed for purely real input, the output is Hermitian-symmetric, i.e., the negative frequency terms are just the complex conjugates of the corresponding positive-frequency terms, and the negative-frequency terms are therefore redundant. This function does not compute the negative frequency terms, and the length of the transformed axis of the output is therefore $n//2 + 1$.

When $X = \text{rfftn}(x)$ and fs is the sampling frequency, $X[0]$ contains the zero-frequency term $0*fs$, which is real due to Hermitian symmetry.

If n is even, $A[-1]$ contains the term representing both positive and negative Nyquist frequency ($+fs/2$ and $-fs/2$), and must also be purely real. If n is odd, there is no term at $fs/2$; $A[-1]$ contains the largest positive frequency ($fs/2*(n-1)/n$), and is complex in the general case.

If the input a contains an imaginary part, it is silently discarded.

Examples

```
>>> import scipy.fft
>>> scipy.fft.fft([0, 1, 0, 0])
array([ 1.+0.j,  0.-1.j, -1.+0.j,  0.+1.j]) # may vary
>>> scipy.fft.rfft([0, 1, 0, 0])
array([ 1.+0.j,  0.-1.j, -1.+0.j]) # may vary
```

Notice how the final element of the *fft* output is the complex conjugate of the second element, for real input. For *rfft*, this symmetry is exploited to compute only the non-negative frequency terms.

scipy.fft.irfft

`scipy.fft.irfft(x, n=None, axis=-1, norm=None, overwrite_x=False, workers=None, *, plan=None)`

Computes the inverse of *rfft*.

This function computes the inverse of the 1-D n -point discrete Fourier Transform of real input computed by *rfft*. In other words, `irfft(rfft(x), len(x)) == x` to within numerical accuracy. (See Notes below for why `len(a)` is necessary here.)

The input is expected to be in the form returned by *rfft*, i.e., the real zero-frequency term followed by the complex positive frequency terms in order of increasing frequency. Since the discrete Fourier Transform of real input is Hermitian-symmetric, the negative frequency terms are taken to be the complex conjugates of the corresponding positive frequency terms.

Parameters

x	[array_like] The input array.
n	[int, optional] Length of the transformed axis of the output. For n output points, $n//2+1$ input points are necessary. If the input is longer than this, it is cropped. If it is shorter than this, it is padded with zeros. If n is not given, it is taken to be $2 * (m-1)$, where m is the length of the input along the axis specified by <i>axis</i> .
axis	[int, optional] Axis over which to compute the inverse FFT. If not given, the last axis is used.
norm	["backward", "ortho", "forward"], optional] Normalization mode (see <i>fft</i>). Default is "backward".

overwrite_x

[bool, optional] If True, the contents of *x* can be destroyed; the default is False. See `fft` for more details.

workers

[int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See `fft` for more details.

plan: object, optional

This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.

New in version 1.5.0.

Returns**out**

[ndarray] The truncated or zero-padded input, transformed along the axis indicated by *axis*, or the last one if *axis* is not specified. The length of the transformed axis is *n*, or, if *n* is not given, $2 * (m - 1)$ where *m* is the length of the transformed axis of the input. To get an odd number of output points, *n* must be specified.

Raises**IndexError**

If *axis* is larger than the last axis of *x*.

See also:*rfft*

The 1-D FFT of real input, of which `irfft` is inverse.

fft

The 1-D FFT.

irfft2

The inverse of the 2-D FFT of real input.

irfftn

The inverse of the N-D FFT of real input.

Notes

Returns the real valued *n*-point inverse discrete Fourier transform of *x*, where *x* contains the non-negative frequency terms of a Hermitian-symmetric sequence. *n* is the length of the result, not the input.

If you specify an *n* such that *a* must be zero-padded or truncated, the extra/removed values will be added/removed at high frequencies. One can thus resample a series to *m* points via Fourier interpolation by: `a_resamp = irfft(rfft(a), m)`.

The default value of *n* assumes an even output length. By the Hermitian symmetry, the last imaginary component must be 0 and so is ignored. To avoid losing information, the correct length of the real input *must* be given.

Examples

```
>>> import scipy.fft
>>> scipy.fft.ifft([1, -1j, -1, 1j])
array([0.+0.j, 1.+0.j, 0.+0.j, 0.+0.j]) # may vary
>>> scipy.fft.irfft([1, -1j, -1])
array([0., 1., 0., 0.]
```

Notice how the last term in the input to the ordinary `ifft` is the complex conjugate of the second term, and the output has zero imaginary part everywhere. When calling `irfft`, the negative frequencies are not specified, and the output array is purely real.

scipy.fft.rfft2

`scipy.fft.rfft2(x, s=None, axes=-2, -1, norm=None, overwrite_x=False, workers=None, *, plan=None)`
 Compute the 2-D FFT of a real array.

Parameters

- x** [array] Input array, taken to be real.
- s** [sequence of ints, optional] Shape of the FFT.
- axes** [sequence of ints, optional] Axes over which to compute the FFT.
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see `fft`). Default is "backward".
- overwrite_x** [bool, optional] If True, the contents of `x` can be destroyed; the default is False. See `fft` for more details.
- workers** [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See `fft` for more details.
- plan: object, optional**
 This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
 New in version 1.5.0.

Returns

- out** [ndarray] The result of the real 2-D FFT.

See also:

`irfft2`

The inverse of the 2-D FFT of real input.

`rfft`

The 1-D FFT of real input.

`rfftn`

Compute the N-D discrete Fourier Transform for real input.

Notes

This is really just `rffftn` with different default behavior. For more details see `rffftn`.

scipy.fft.irfft2

```
scipy.fft.irfft2(x, s=None, axes=-2, -1, norm=None, overwrite_x=False, workers=None, *,
                 plan=None)
```

Computes the inverse of `rffft2`

Parameters

- x** [array_like] The input array
- s** [sequence of ints, optional] Shape of the real output to the inverse FFT.
- axes** [sequence of ints, optional] The axes over which to compute the inverse fft. Default is the last two axes.
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see `fft`). Default is "backward".
- overwrite_x** [bool, optional] If True, the contents of `x` can be destroyed; the default is False. See `fft` for more details.
- workers** [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See `fft` for more details.
- plan: object, optional**
This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
New in version 1.5.0.

Returns

- out** [ndarray] The result of the inverse real 2-D FFT.

See also:

`rffft2`

The 2-D FFT of real input.

`irfft`

The inverse of the 1-D FFT of real input.

`irfftn`

The inverse of the N-D FFT of real input.

Notes

This is really `irfftn` with different defaults. For more details see `irfftn`.

scipy.fft.rfftn`scipy.fft.rfftn(x, s=None, axes=None, norm=None, overwrite_x=False, workers=None, *, plan=None)`

Compute the N-D discrete Fourier Transform for real input.

This function computes the N-D discrete Fourier Transform over any number of axes in an M-D real array by means of the Fast Fourier Transform (FFT). By default, all axes are transformed, with the real transform performed over the last axis, while the remaining transforms are complex.

Parameters

- x** [array_like] Input array, taken to be real.
- s** [sequence of ints, optional] Shape (length along each transformed axis) to use from the input. (`s[0]` refers to axis 0, `s[1]` to axis 1, etc.). The final element of `s` corresponds to `n` for `rfftn(x, n)`, while for the remaining axes, it corresponds to `n` for `fft(x, n)`. Along any axis, if the given shape is smaller than that of the input, the input is cropped. If it is larger, the input is padded with zeros. If `s` is not given, the shape of the input along the axes specified by `axes` is used.
- axes** [sequence of ints, optional] Axes over which to compute the FFT. If not given, the last `len(s)` axes are used, or all axes if `s` is also not specified.
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see `fft`). Default is "backward".
- overwrite_x** [bool, optional] If True, the contents of `x` can be destroyed; the default is False. See `fft` for more details.
- workers** [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See `fft` for more details.
- plan: object, optional**
This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
New in version 1.5.0.

Returns

- out** [complex ndarray] The truncated or zero-padded input, transformed along the axes indicated by `axes`, or by a combination of `s` and `x`, as explained in the parameters section above. The length of the last axis transformed will be `s[-1] // 2 + 1`, while the remaining transformed axes will have lengths according to `s`, or unchanged from the input.

Raises

- ValueError**
If `s` and `axes` have different length.
- IndexError**
If an element of `axes` is larger than than the number of axes of `x`.

See also:***irfftn***The inverse of `rfftn`, i.e., the inverse of the N-D FFT of real input.***fft***

The 1-D FFT, with definitions and conventions used.

rfft

The 1-D FFT of real input.

fftn

The N-D FFT.

rffft2

The 2-D FFT of real input.

Notes

The transform for real input is performed over the last transformation axis, as by *rffft*, then the transform over the remaining axes is performed as by *fftn*. The order of the output is as for *rffft* for the final transformation axis, and as for *fftn* for the remaining transformation axes.

See *fft* for details, definitions and conventions used.

Examples

```
>>> import scipy.fft
>>> x = np.ones((2, 2, 2))
>>> scipy.fft.rfftn(x)
array([[ [8.+0.j,  0.+0.j], # may vary
         [0.+0.j,  0.+0.j]],
       [ [0.+0.j,  0.+0.j],
         [0.+0.j,  0.+0.j]])
```

```
>>> scipy.fft.rfftn(x, axes=(2, 0))
array([[ [4.+0.j,  0.+0.j], # may vary
         [4.+0.j,  0.+0.j]],
       [ [0.+0.j,  0.+0.j],
         [0.+0.j,  0.+0.j]])
```

scipy.fft.irfftn

`scipy.fft.irfftn(x, s=None, axes=None, norm=None, overwrite_x=False, workers=None, *, plan=None)`

Computes the inverse of *rfftn*

This function computes the inverse of the N-D discrete Fourier Transform for real input over any number of axes in an M-D array by means of the Fast Fourier Transform (FFT). In other words, `irfftn(rfftn(x), x.shape) == x` to within numerical accuracy. (The `a.shape` is necessary like `len(a)` is for *irfft*, and for the same reason.)

The input should be ordered in the same way as is returned by *rfftn*, i.e., as for *irfft* for the final transformation axis, and as for *ifftn* along all the other axes.

Parameters

- x** [array_like] Input array.
- s** [sequence of ints, optional] Shape (length of each transformed axis) of the output (`s[0]` refers to axis 0, `s[1]` to axis 1, etc.). `s` is also the number of input points used along this axis, except for the last axis, where `s[-1]//2+1` points of the input are used. Along any axis, if the shape indicated by `s` is smaller than that of the input, the input is cropped. If it is larger, the input is padded with zeros. If `s` is not given, the shape of the input along the axes specified by `axes` is used. Except for the last axis which is taken to be $2 * (m-1)$, where `m` is the length of the input along that axis.

axes [sequence of ints, optional] Axes over which to compute the inverse FFT. If not given, the last $len(s)$ axes are used, or all axes if s is also not specified.

norm [{"backward", "ortho", "forward"}, optional] Normalization mode (see *fft*). Default is "backward".

overwrite_x [bool, optional] If True, the contents of x can be destroyed; the default is False. See *fft* for more details.

workers [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See *fft* for more details.

plan: object, optional
 This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
 New in version 1.5.0.

Returns

out [ndarray] The truncated or zero-padded input, transformed along the axes indicated by *axes*, or by a combination of s or x , as explained in the parameters section above. The length of each transformed axis is as given by the corresponding element of s , or the length of the input in every axis except for the last one if s is not given. In the final transformed axis the length of the output when s is not given is $2 * (m-1)$, where m is the length of the final transformed axis of the input. To get an odd number of output points in the final axis, s must be specified.

Raises

ValueError
 If s and *axes* have different length.

IndexError
 If an element of *axes* is larger than than the number of axes of x .

See also:

rfftn

The forward N-D FFT of real input, of which *ifftn* is the inverse.

fft

The 1-D FFT, with definitions and conventions used.

irfft

The inverse of the 1-D FFT of real input.

irfft2

The inverse of the 2-D FFT of real input.

Notes

See *fft* for definitions and conventions used.

See *rfft* for definitions and conventions used for real input.

The default value of s assumes an even output length in the final transformation axis. When performing the final complex to real transformation, the Hermitian symmetry requires that the last imaginary component along that axis must be 0 and so it is ignored. To avoid losing information, the correct length of the real input *must* be given.

Examples

```
>>> import scipy.fft
>>> x = np.zeros((3, 2, 2))
>>> x[0, 0, 0] = 3 * 2 * 2
>>> scipy.fft.irfftn(x)
array([[ [1., 1.],
         [1., 1.]],
       [ [1., 1.],
         [1., 1.]],
       [ [1., 1.],
         [1., 1.]])
```

scipy.fft.hfft

`scipy.fft.hfft(x, n=None, axis=-1, norm=None, overwrite_x=False, workers=None, *, plan=None)`

Compute the FFT of a signal that has Hermitian symmetry, i.e., a real spectrum.

Parameters

- x** [array_like] The input array.
- n** [int, optional] Length of the transformed axis of the output. For n output points, $n//2 + 1$ input points are necessary. If the input is longer than this, it is cropped. If it is shorter than this, it is padded with zeros. If n is not given, it is taken to be $2 * (m-1)$, where m is the length of the input along the axis specified by *axis*.
- axis** [int, optional] Axis over which to compute the FFT. If not given, the last axis is used.
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see *fft*). Default is "backward".
- overwrite_x** [bool, optional] If True, the contents of *x* can be destroyed; the default is False. See *fft* for more details.
- workers** [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See *fft* for more details.
- plan: object, optional**
This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
New in version 1.5.0.

Returns

- out** [ndarray] The truncated or zero-padded input, transformed along the axis indicated by *axis*, or the last one if *axis* is not specified. The length of the transformed axis is n , or, if n is not given, $2 * m - 2$, where m is the length of the transformed axis of the input. To get an odd number of output points, n must be specified, for instance, as $2 * m - 1$ in the typical case,

Raises

- IndexError**
If *axis* is larger than the last axis of *a*.

See also:

rfft

Compute the 1-D FFT for real input.

`ihfft`

The inverse of `hfft`.

`hfftn`

Compute the N-D FFT of a Hermitian signal.

Notes

`hfft/ihfft` are a pair analogous to `rfft/irfft`, but for the opposite case: here the signal has Hermitian symmetry in the time domain and is real in the frequency domain. So, here, it's `hfft`, for which you must supply the length of the result if it is to be odd. * even: `ihfft(hfft(a, 2*len(a) - 2)) == a`, within roundoff error, * odd: `ihfft(hfft(a, 2*len(a) - 1)) == a`, within roundoff error.

Examples

```
>>> from scipy.fft import fft, hfft
>>> a = 2 * np.pi * np.arange(10) / 10
>>> signal = np.cos(a) + 3j * np.sin(3 * a)
>>> fft(signal).round(10)
array([-0.+0.j,  5.+0.j, -0.+0.j, 15.-0.j,  0.+0.j,  0.+0.j,
        -0.+0.j, -15.-0.j,  0.+0.j,  5.+0.j])
>>> hfft(signal[:6]).round(10) # Input first half of signal
array([ 0.,  5.,  0., 15., -0.,  0.,  0., -15., -0.,  5.])
>>> hfft(signal, 10) # Input entire signal and truncate
array([ 0.,  5.,  0., 15., -0.,  0.,  0., -15., -0.,  5.])
```

`scipy.fft.ihfft`

`scipy.fft.ihfft(x, n=None, axis=-1, norm=None, overwrite_x=False, workers=None, *, plan=None)`

Compute the inverse FFT of a signal that has Hermitian symmetry.

Parameters

- x** [array_like] Input array.
- n** [int, optional] Length of the inverse FFT, the number of points along transformation axis in the input to use. If *n* is smaller than the length of the input, the input is cropped. If it is larger, the input is padded with zeros. If *n* is not given, the length of the input along the axis specified by *axis* is used.
- axis** [int, optional] Axis over which to compute the inverse FFT. If not given, the last axis is used.
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see `fft`). Default is "backward".
- overwrite_x** [bool, optional] If True, the contents of *x* can be destroyed; the default is False. See `fft` for more details.
- workers** [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See `fft` for more details.
- plan: object, optional**
This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
New in version 1.5.0.

Returns

out [complex ndarray] The truncated or zero-padded input, transformed along the axis indicated by *axis*, or the last one if *axis* is not specified. The length of the transformed axis is $n//2 + 1$.

See also:

[hfft](#), [irfft](#)

Notes

hfft/ihfft are a pair analogous to *rfft/irfft*, but for the opposite case: here, the signal has Hermitian symmetry in the time domain and is real in the frequency domain. So, here, it's *hfft*, for which you must supply the length of the result if it is to be odd: * even: `ihfft(hfft(a, 2*len(a) - 2)) == a`, within roundoff error, * odd: `ihfft(hfft(a, 2*len(a) - 1)) == a`, within roundoff error.

Examples

```
>>> from scipy.fft import ifft, ihfft
>>> spectrum = np.array([ 15, -4, 0, -1, 0, -4])
>>> ifft(spectrum)
array([1.+0.j,  2.+0.j,  3.+0.j,  4.+0.j,  3.+0.j,  2.+0.j]) # may vary
>>> ihfft(spectrum)
array([ 1.-0.j,  2.-0.j,  3.-0.j,  4.-0.j]) # may vary
```

scipy.fft.hfft2

`scipy.fft.hfft2(x, s=None, axes=-2, -1, norm=None, overwrite_x=False, workers=None, *, plan=None)`

Compute the 2-D FFT of a Hermitian complex array.

Parameters

x [array] Input array, taken to be Hermitian complex.
s [sequence of ints, optional] Shape of the real output.
axes [sequence of ints, optional] Axes over which to compute the FFT.
norm [{"backward", "ortho", "forward"}, optional] Normalization mode (see [fft](#)). Default is "backward".
overwrite_x [bool, optional] If True, the contents of *x* can be destroyed; the default is False. See [fft](#) for more details.
workers [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See [fft](#) for more details.
plan: object, optional
 This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
 New in version 1.5.0.

Returns

out [ndarray] The real result of the 2-D Hermitian complex real FFT.

See also:

[hfftn](#)

Compute the N-D discrete Fourier Transform for Hermitian complex input.

Notes

This is really just `hfft` with different default behavior. For more details see `hfft`.

scipy.fft.ihfft2

```
scipy.fft.ihfft2(x, s=None, axes=-2, -1, norm=None, overwrite_x=False, workers=None, *,
                 plan=None)
```

Compute the 2-D inverse FFT of a real spectrum.

Parameters

- x** [array_like] The input array
- s** [sequence of ints, optional] Shape of the real input to the inverse FFT.
- axes** [sequence of ints, optional] The axes over which to compute the inverse fft. Default is the last two axes.
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see `fft`). Default is "backward".
- overwrite_x** [bool, optional] If True, the contents of `x` can be destroyed; the default is False. See `fft` for more details.
- workers** [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See `fft` for more details.
- plan: object, optional**
This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
New in version 1.5.0.

Returns

- out** [ndarray] The result of the inverse real 2-D FFT.

See also:

`ihfftn`

Compute the inverse of the N-D FFT of Hermitian input.

Notes

This is really `ihfftn` with different defaults. For more details see `ihfftn`.

scipy.fft.hfftn

```
scipy.fft.hfftn(x, s=None, axes=None, norm=None, overwrite_x=False, workers=None, *, plan=None)
```

Compute the N-D FFT of Hermitian symmetric complex input, i.e., a signal with a real spectrum.

This function computes the N-D discrete Fourier Transform for a Hermitian symmetric complex input over any number of axes in an M-D array by means of the Fast Fourier Transform (FFT). In other words, `ihfftn(hfftn(x, s)) == x` to within numerical accuracy. (`s` here is `x.shape` with `s[-1] = x.shape[-1] * 2 - 1`, this is necessary for the same reason `x.shape` would be necessary for `irfft`.)

Parameters

- x** [array_like] Input array.

- s** [sequence of ints, optional] Shape (length of each transformed axis) of the output (`s[0]` refers to axis 0, `s[1]` to axis 1, etc.). `s` is also the number of input points used along this axis, except for the last axis, where `s[-1] // 2 + 1` points of the input are used. Along any axis, if the shape indicated by `s` is smaller than that of the input, the input is cropped. If it is larger, the input is padded with zeros. If `s` is not given, the shape of the input along the axes specified by `axes` is used. Except for the last axis which is taken to be $2 * (m - 1)$ where `m` is the length of the input along that axis.
- axes** [sequence of ints, optional] Axes over which to compute the inverse FFT. If not given, the last `len(s)` axes are used, or all axes if `s` is also not specified.
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see `fft`). Default is "backward".
- overwrite_x** [bool, optional] If True, the contents of `x` can be destroyed; the default is False. See `fft` for more details.
- workers** [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See `fft` for more details.
- plan: object, optional**
This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
New in version 1.5.0.

Returns

- out** [ndarray] The truncated or zero-padded input, transformed along the axes indicated by `axes`, or by a combination of `s` or `x`, as explained in the parameters section above. The length of each transformed axis is as given by the corresponding element of `s`, or the length of the input in every axis except for the last one if `s` is not given. In the final transformed axis the length of the output when `s` is not given is $2 * (m - 1)$ where `m` is the length of the final transformed axis of the input. To get an odd number of output points in the final axis, `s` must be specified.

Raises

- ValueError**
If `s` and `axes` have different length.
- IndexError**
If an element of `axes` is larger than than the number of axes of `x`.

See also:**`ihfftn`**

The inverse N-D FFT with real spectrum. Inverse of `hfftn`.

`fft`

The 1-D FFT, with definitions and conventions used.

`rfft`

Forward FFT of real input.

Notes

For a 1-D signal x to have a real spectrum, it must satisfy the Hermitian property:

```
x[i] == np.conj(x[-i]) for all i
```

This generalizes into higher dimensions by reflecting over each axis in turn:

```
x[i, j, k, ...] == np.conj(x[-i, -j, -k, ...]) for all i, j, k, ...
```

This should not be confused with a Hermitian matrix, for which the transpose is its own conjugate:

```
x[i, j] == np.conj(x[j, i]) for all i, j
```

The default value of s assumes an even output length in the final transformation axis. When performing the final complex to real transformation, the Hermitian symmetry requires that the last imaginary component along that axis must be 0 and so it is ignored. To avoid losing information, the correct length of the real input *must* be given.

Examples

```
>>> import scipy.fft
>>> x = np.ones((3, 2, 2))
>>> scipy.fft.ihfftn(x)
array([[ [12.,  0.],
         [ 0.,  0.]],
       [[ 0.,  0.],
         [ 0.,  0.]],
       [[ 0.,  0.],
         [ 0.,  0.]])
```

scipy.fft.ihfftn

`scipy.fft.ihfftn(x, s=None, axes=None, norm=None, overwrite_x=False, workers=None, *, plan=None)`

Compute the N-D inverse discrete Fourier Transform for a real spectrum.

This function computes the N-D inverse discrete Fourier Transform over any number of axes in an M-D real array by means of the Fast Fourier Transform (FFT). By default, all axes are transformed, with the real transform performed over the last axis, while the remaining transforms are complex.

Parameters

- x** [array_like] Input array, taken to be real.
- s** [sequence of ints, optional] Shape (length along each transformed axis) to use from the input. ($s[0]$ refers to axis 0, $s[1]$ to axis 1, etc.). Along any axis, if the given shape is smaller than that of the input, the input is cropped. If it is larger, the input is padded with zeros. If s is not given, the shape of the input along the axes specified by *axes* is used.
- axes** [sequence of ints, optional] Axes over which to compute the FFT. If not given, the last $\text{len}(s)$ axes are used, or all axes if s is also not specified.
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see [fft](#)). Default is "backward".
- overwrite_x** [bool, optional] If True, the contents of x can be destroyed; the default is False. See [fft](#) for more details.

workers [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See [fft](#) for more details.

plan: object, optional

This argument is reserved for passing in a precomputed plan provided by downstream FFT vendors. It is currently not used in SciPy.
New in version 1.5.0.

Returns

out [complex ndarray] The truncated or zero-padded input, transformed along the axes indicated by *axes*, or by a combination of *s* and *x*, as explained in the parameters section above. The length of the last axis transformed will be $s[-1] // 2 + 1$, while the remaining transformed axes will have lengths according to *s*, or unchanged from the input.

Raises

ValueError

If *s* and *axes* have different length.

IndexError

If an element of *axes* is larger than than the number of axes of *x*.

See also:

[hfftn](#)

The forward N-D FFT of Hermitian input.

[hfft](#)

The 1-D FFT of Hermitian input.

[fft](#)

The 1-D FFT, with definitions and conventions used.

[fftn](#)

The N-D FFT.

[hfft2](#)

The 2-D FFT of Hermitian input.

Notes

The transform for real input is performed over the last transformation axis, as by [ihfft](#), then the transform over the remaining axes is performed as by [ifftn](#). The order of the output is the positive part of the Hermitian output signal, in the same format as [rfft](#).

Examples

```
>>> import scipy.fft
>>> x = np.ones((2, 2, 2))
>>> scipy.fft.ihfftn(x)
array([[ [1.+0.j, 0.+0.j], # may vary
         [0.+0.j, 0.+0.j]],
        [ [0.+0.j, 0.+0.j],
          [0.+0.j, 0.+0.j]])])
```

(continues on next page)

(continued from previous page)

```
>>> scipy.fft.ihfftn(x, axes=(2, 0))
array([[ [ [1.+0.j, 0.+0.j], # may vary
         [1.+0.j, 0.+0.j]],
        [ [0.+0.j, 0.+0.j],
         [0.+0.j, 0.+0.j]]])
```

6.5.2 Discrete Sin and Cosine Transforms (DST and DCT)

<code>dct(x[, type, n, axis, norm, overwrite_x, ...])</code>	Return the Discrete Cosine Transform of arbitrary type sequence <i>x</i> .
<code>idct(x[, type, n, axis, norm, overwrite_x, ...])</code>	Return the Inverse Discrete Cosine Transform of an arbitrary type sequence.
<code>dctn(x[, type, s, axes, norm, overwrite_x, ...])</code>	Return multidimensional Discrete Cosine Transform along the specified axes.
<code>idctn(x[, type, s, axes, norm, overwrite_x, ...])</code>	Return multidimensional Discrete Cosine Transform along the specified axes.
<code>dst(x[, type, n, axis, norm, overwrite_x, ...])</code>	Return the Discrete Sine Transform of arbitrary type sequence <i>x</i> .
<code>idst(x[, type, n, axis, norm, overwrite_x, ...])</code>	Return the Inverse Discrete Sine Transform of an arbitrary type sequence.
<code>dstn(x[, type, s, axes, norm, overwrite_x, ...])</code>	Return multidimensional Discrete Sine Transform along the specified axes.
<code>idstn(x[, type, s, axes, norm, overwrite_x, ...])</code>	Return multidimensional Discrete Sine Transform along the specified axes.

scipy.fft.dct

`scipy.fft.dct(x, type=2, n=None, axis=-1, norm=None, overwrite_x=False, workers=None)`

Return the Discrete Cosine Transform of arbitrary type sequence *x*.

Parameters

- x** [array_like] The input array.
- type** [{1, 2, 3, 4}, optional] Type of the DCT (see Notes). Default type is 2.
- n** [int, optional] Length of the transform. If $n < x.shape[axis]$, *x* is truncated. If $n > x.shape[axis]$, *x* is zero-padded. The default results in $n = x.shape[axis]$.
- axis** [int, optional] Axis along which the dct is computed; the default is over the last axis (i.e., `axis=-1`).
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see Notes). Default is "backward".
- overwrite_x** [bool, optional] If True, the contents of *x* can be destroyed; the default is False.
- workers** [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See `fft` for more details.

Returns

- y** [ndarray of real] The transformed input array.

See also:

idct

Inverse DCT

Notes

For a single dimension array x , `dct(x, norm='ortho')` is equal to MATLAB `dct(x)`.

For `norm="backward"`, there is no scaling on `dct` and the `idct` is scaled by $1/N$ where N is the “logical” size of the DCT. For `norm="forward"` the $1/N$ normalization is applied to the forward `dct` instead and the `idct` is unnormalized. For `norm='ortho'` both directions are scaled by the same factor of $1/\sqrt{N}$.

There are, theoretically, 8 types of the DCT, only the first 4 types are implemented in SciPy. The DCT generally refers to DCT type 2, and the Inverse DCT generally refers to DCT type 3.

Type I

There are several definitions of the DCT-I; we use the following (for `norm="backward"`)

$$y_k = x_0 + (-1)^k x_{N-1} + 2 \sum_{n=1}^{N-2} x_n \cos\left(\frac{\pi kn}{N-1}\right)$$

If `norm='ortho'`, $x[0]$ and $x[N-1]$ are multiplied by a scaling factor of $\sqrt{2}$, and $y[k]$ is multiplied by a scaling factor f

$$f = \begin{cases} \frac{1}{2} \sqrt{\frac{1}{N-1}} & \text{if } k = 0 \text{ or } N-1, \\ \frac{1}{2} \sqrt{\frac{2}{N-1}} & \text{otherwise} \end{cases}$$

Note: The DCT-I is only supported for input size > 1 .

Type II

There are several definitions of the DCT-II; we use the following (for `norm="backward"`)

$$y_k = 2 \sum_{n=0}^{N-1} x_n \cos\left(\frac{\pi k(2n+1)}{2N}\right)$$

If `norm="ortho"`, $y[k]$ is multiplied by a scaling factor f

$$f = \begin{cases} \sqrt{\frac{1}{4N}} & \text{if } k = 0, \\ \sqrt{\frac{1}{2N}} & \text{otherwise} \end{cases}$$

which makes the corresponding matrix of coefficients orthonormal ($O @ O.T = \text{np.eye}(N)$).

Type III

There are several definitions, we use the following (for `norm="backward"`)

$$y_k = x_0 + 2 \sum_{n=1}^{N-1} x_n \cos\left(\frac{\pi(2k+1)n}{2N}\right)$$

or, for `norm="ortho"`

$$y_k = \frac{x_0}{\sqrt{N}} + \sqrt{\frac{2}{N}} \sum_{n=1}^{N-1} x_n \cos\left(\frac{\pi(2k+1)n}{2N}\right)$$

The (unnormalized) DCT-III is the inverse of the (unnormalized) DCT-II, up to a factor $2N$. The orthonormalized DCT-III is exactly the inverse of the orthonormalized DCT-II.

Type IV

There are several definitions of the DCT-IV; we use the following (for `norm="backward"`)

$$y_k = 2 \sum_{n=0}^{N-1} x_n \cos\left(\frac{\pi(2k+1)(2n+1)}{4N}\right)$$

If `norm="ortho"`, $y[k]$ is multiplied by a scaling factor f

$$f = \frac{1}{\sqrt{2N}}$$

References

[1], [2]

Examples

The Type 1 DCT is equivalent to the FFT (though faster) for real, even-symmetrical inputs. The output is also real and even-symmetrical. Half of the FFT input is used to generate half of the FFT output:

```
>>> from scipy.fft import fft, dct
>>> fft(np.array([4., 3., 5., 10., 5., 3.])).real
array([ 30., -8., 6., -2., 6., -8.])
>>> dct(np.array([4., 3., 5., 10.]), 1)
array([ 30., -8., 6., -2.])
```

scipy.fft.idct

`scipy.fft.idct(x, type=2, n=None, axis=-1, norm=None, overwrite_x=False, workers=None)`

Return the Inverse Discrete Cosine Transform of an arbitrary type sequence.

Parameters

- x** [array_like] The input array.
- type** [{1, 2, 3, 4}, optional] Type of the DCT (see Notes). Default type is 2.
- n** [int, optional] Length of the transform. If $n < x.shape[axis]$, x is truncated. If $n > x.shape[axis]$, x is zero-padded. The default results in $n = x.shape[axis]$.
- axis** [int, optional] Axis along which the `idct` is computed; the default is over the last axis (i.e., `axis=-1`).
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see Notes). Default is "backward".
- overwrite_x** [bool, optional] If True, the contents of x can be destroyed; the default is False.
- workers** [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See `fft` for more details.

Returns

- idct** [ndarray of real] The transformed input array.

See also:

dct

Forward DCT

Notes

For a single dimension array x , `idct(x, norm='ortho')` is equal to MATLAB `idct(x)`.

The IDCT is the IDCT-II, which is the same as the normalized DCT-III.

The IDCT is equivalent to a normal DCT except for the normalization and type. DCT type 1 and 4 are their own inverse and DCTs 2 and 3 are each other's inverses.

Examples

The Type 1 DCT is equivalent to the DFT for real, even-symmetrical inputs. The output is also real and even-symmetrical. Half of the IFFT input is used to generate half of the IFFT output:

```
>>> from scipy.fft import ifft, idct
>>> ifft(np.array([ 30., -8., 6., -2., 6., -8.])).real
array([ 4., 3., 5., 10., 5., 3.])
>>> idct(np.array([ 30., -8., 6., -2.]), 1)
array([ 4., 3., 5., 10.]])
```

scipy.fft.dctn

`scipy.fft.dctn(x, type=2, s=None, axes=None, norm=None, overwrite_x=False, workers=None)`

Return multidimensional Discrete Cosine Transform along the specified axes.

Parameters

x	[array_like] The input array.
type	[[1, 2, 3, 4], optional] Type of the DCT (see Notes). Default type is 2.
s	[int or array_like of ints or None, optional] The shape of the result. If both <i>s</i> and <i>axes</i> (see below) are None, <i>s</i> is <code>x.shape</code> ; if <i>s</i> is None but <i>axes</i> is not None, then <i>s</i> is <code>scipy.take(x.shape, axes, axis=0)</code> . If <code>s[i] > x.shape[i]</code> , the <i>i</i> th dimension is padded with zeros. If <code>s[i] < x.shape[i]</code> , the <i>i</i> th dimension is truncated to length <code>s[i]</code> . If any element of <i>s</i> is -1, the size of the corresponding dimension of <i>x</i> is used.
axes	[int or array_like of ints or None, optional] Axes over which the DCT is computed. If not given, the last <code>len(s)</code> axes are used, or all axes if <i>s</i> is also not specified.
norm	[["backward", "ortho", "forward"], optional] Normalization mode (see Notes). Default is "backward".
overwrite_x	[bool, optional] If True, the contents of <i>x</i> can be destroyed; the default is False.
workers	[int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from <code>os.cpu_count()</code> . See <code>fft</code> for more details.

Returns

y [ndarray of real] The transformed input array.

See also:

idctn

Inverse multidimensional DCT

Notes

For full details of the DCT types and normalization modes, as well as references, see *dct*.

Examples

```
>>> from scipy.fft import dctn, idctn
>>> y = np.random.randn(16, 16)
>>> np.allclose(y, idctn(dctn(y)))
True
```

scipy.fft.idctn

`scipy.fft.idctn(x, type=2, s=None, axes=None, norm=None, overwrite_x=False, workers=None)`

Return multidimensional Discrete Cosine Transform along the specified axes.

Parameters

- | | |
|--------------------|---|
| x | [array_like] The input array. |
| type | [[1, 2, 3, 4], optional] Type of the DCT (see Notes). Default type is 2. |
| s | [int or array_like of ints or None, optional] The shape of the result. If both <i>s</i> and <i>axes</i> (see below) are None, <i>s</i> is <code>x.shape</code> ; if <i>s</i> is None but <i>axes</i> is not None, then <i>s</i> is <code>scipy.take(x.shape, axes, axis=0)</code> . If <code>s[i] > x.shape[i]</code> , the <i>i</i> th dimension is padded with zeros. If <code>s[i] < x.shape[i]</code> , the <i>i</i> th dimension is truncated to length <code>s[i]</code> . If any element of <i>s</i> is -1, the size of the corresponding dimension of <i>x</i> is used. |
| axes | [int or array_like of ints or None, optional] Axes over which the IDCT is computed. If not given, the last <code>len(s)</code> axes are used, or all axes if <i>s</i> is also not specified. |
| norm | [{"backward", "ortho", "forward"}, optional] Normalization mode (see Notes). Default is "backward". |
| overwrite_x | [bool, optional] If True, the contents of <i>x</i> can be destroyed; the default is False. |
| workers | [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from <code>os.cpu_count()</code> . See <i>fft</i> for more details. |

Returns

- | | |
|----------|--|
| y | [ndarray of real] The transformed input array. |
|----------|--|

See also:

dctn

multidimensional DCT

Notes

For full details of the IDCT types and normalization modes, as well as references, see *idct*.

Examples

```
>>> from scipy.fft import dctn, idctn
>>> y = np.random.randn(16, 16)
>>> np.allclose(y, idctn(dctn(y)))
True
```

scipy.fft.dst

`scipy.fft.dst` (*x*, *type*=2, *n*=None, *axis*=-1, *norm*=None, *overwrite_x*=False, *workers*=None)

Return the Discrete Sine Transform of arbitrary type sequence *x*.

Parameters

x	[array_like] The input array.
type	[[1, 2, 3, 4], optional] Type of the DST (see Notes). Default type is 2.
n	[int, optional] Length of the transform. If $n < x.shape[axis]$, <i>x</i> is truncated. If $n > x.shape[axis]$, <i>x</i> is zero-padded. The default results in $n = x.shape[axis]$.
axis	[int, optional] Axis along which the dst is computed; the default is over the last axis (i.e., <code>axis=-1</code>).
norm	["backward", "ortho", "forward"], optional] Normalization mode (see Notes). Default is "backward".
overwrite_x	[bool, optional] If True, the contents of <i>x</i> can be destroyed; the default is False.
workers	[int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from <code>os.cpu_count()</code> . See <code>fft</code> for more details.

Returns

dst	[ndarray of reals] The transformed input array.
------------	---

See also:

idst

Inverse DST

Notes

For a single dimension array *x*.

For `norm="backward"`, there is no scaling on the `dst` and the `idst` is scaled by $1/N$ where *N* is the “logical” size of the DST. For `norm='ortho'` both directions are scaled by the same factor $1/\sqrt{N}$.

There are, theoretically, 8 types of the DST for different combinations of even/odd boundary conditions and boundary off sets [1], only the first 4 types are implemented in SciPy.

Type I

There are several definitions of the DST-I; we use the following for `norm="backward"`. DST-I assumes the input is odd around $n = -1$ and $n = N$.

$$y_k = 2 \sum_{n=0}^{N-1} x_n \sin\left(\frac{\pi(k+1)(n+1)}{N+1}\right)$$

Note that the DST-I is only supported for input size > 1 . The (unnormalized) DST-I is its own inverse, up to a factor $2(N+1)$. The orthonormalized DST-I is exactly its own inverse.

Type II

There are several definitions of the DST-II; we use the following for `norm="backward"`. DST-II assumes the input is odd around $n = -1/2$ and $n = N - 1/2$; the output is odd around $k = -1$ and even around $k = N - 1$

$$y_k = 2 \sum_{n=0}^{N-1} x_n \sin \left(\frac{\pi(k+1)(2n+1)}{2N} \right)$$

if `norm='ortho'`, $y[k]$ is multiplied by a scaling factor f

$$f = \begin{cases} \sqrt{\frac{1}{4N}} & \text{if } k = 0, \\ \sqrt{\frac{1}{2N}} & \text{otherwise} \end{cases}$$

Type III

There are several definitions of the DST-III, we use the following (for `norm="backward"`). DST-III assumes the input is odd around $n = -1$ and even around $n = N - 1$

$$y_k = (-1)^k x_{N-1} + 2 \sum_{n=0}^{N-2} x_n \sin \left(\frac{\pi(2k+1)(n+1)}{2N} \right)$$

The (unnormalized) DST-III is the inverse of the (unnormalized) DST-II, up to a factor $2N$. The orthonormalized DST-III is exactly the inverse of the orthonormalized DST-II.

Type IV

There are several definitions of the DST-IV, we use the following (for `norm="backward"`). DST-IV assumes the input is odd around $n = -0.5$ and even around $n = N - 0.5$

$$y_k = 2 \sum_{n=0}^{N-1} x_n \sin \left(\frac{\pi(2k+1)(2n+1)}{4N} \right)$$

The (unnormalized) DST-IV is its own inverse, up to a factor $2N$. The orthonormalized DST-IV is exactly its own inverse.

References

[1]

scipy.fft.idst

`scipy.fft.idst(x, type=2, n=None, axis=-1, norm=None, overwrite_x=False, workers=None)`

Return the Inverse Discrete Sine Transform of an arbitrary type sequence.

Parameters

x	[array_like] The input array.
type	[[1, 2, 3, 4], optional] Type of the DST (see Notes). Default type is 2.
n	[int, optional] Length of the transform. If $n < x.shape[axis]$, x is truncated. If $n > x.shape[axis]$, x is zero-padded. The default results in $n = x.shape[axis]$.
axis	[int, optional] Axis along which the idst is computed; the default is over the last axis (i.e., <code>axis=-1</code>).
norm	["backward", "ortho", "forward"], optional] Normalization mode (see Notes). Default is "backward".

overwrite_x [bool, optional] If True, the contents of *x* can be destroyed; the default is False.

workers [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See [fft](#) for more details.

Returns

idst [ndarray of real] The transformed input array.

See also:

[dst](#)

Forward DST

Notes

The IDST is the IDST-II, which is the same as the normalized DST-III.

The IDST is equivalent to a normal DST except for the normalization and type. DST type 1 and 4 are their own inverse and DSTs 2 and 3 are each other's inverses.

scipy.fft.dstn

`scipy.fft.dstn(x, type=2, s=None, axes=None, norm=None, overwrite_x=False, workers=None)`

Return multidimensional Discrete Sine Transform along the specified axes.

Parameters

x [array_like] The input array.

type [{1, 2, 3, 4}, optional] Type of the DST (see Notes). Default type is 2.

s [int or array_like of ints or None, optional] The shape of the result. If both *s* and *axes* (see below) are None, *s* is `x.shape`; if *s* is None but *axes* is not None, then *s* is `scipy.take(x.shape, axes, axis=0)`. If `s[i] > x.shape[i]`, the *i*th dimension is padded with zeros. If `s[i] < x.shape[i]`, the *i*th dimension is truncated to length `s[i]`. If any element of *shape* is -1, the size of the corresponding dimension of *x* is used.

axes [int or array_like of ints or None, optional] Axes over which the DST is computed. If not given, the last `len(s)` axes are used, or all axes if *s* is also not specified.

norm [{"backward", "ortho", "forward"}, optional] Normalization mode (see Notes). Default is "backward".

overwrite_x [bool, optional] If True, the contents of *x* can be destroyed; the default is False.

workers [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See [fft](#) for more details.

Returns

y [ndarray of real] The transformed input array.

See also:

[idstn](#)

Inverse multidimensional DST

Notes

For full details of the DST types and normalization modes, as well as references, see [dst](#).

Examples

```

>>> from scipy.fft import dstn, idstn
>>> y = np.random.randn(16, 16)
>>> np.allclose(y, idstn(dstn(y)))
True

```

scipy.fft.idstn

`scipy.fft.idstn(x, type=2, s=None, axes=None, norm=None, overwrite_x=False, workers=None)`

Return multidimensional Discrete Sine Transform along the specified axes.

Parameters

- x** [array_like] The input array.
- type** [{1, 2, 3, 4}, optional] Type of the DST (see Notes). Default type is 2.
- s** [int or array_like of ints or None, optional] The shape of the result. If both *s* and *axes* (see below) are None, *s* is `x.shape`; if *s* is None but *axes* is not None, then *s* is `scipy.take(x.shape, axes, axis=0)`. If `s[i] > x.shape[i]`, the *i*th dimension is padded with zeros. If `s[i] < x.shape[i]`, the *i*th dimension is truncated to length `s[i]`. If any element of *s* is -1, the size of the corresponding dimension of *x* is used.
- axes** [int or array_like of ints or None, optional] Axes over which the IDST is computed. If not given, the last `len(s)` axes are used, or all axes if *s* is also not specified.
- norm** [{"backward", "ortho", "forward"}, optional] Normalization mode (see Notes). Default is "backward".
- overwrite_x** [bool, optional] If True, the contents of *x* can be destroyed; the default is False.
- workers** [int, optional] Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See [fft](#) for more details.

Returns

- y** [ndarray of real] The transformed input array.

See also:

[dstn](#)

multidimensional DST

Notes

For full details of the IDST types and normalization modes, as well as references, see [idst](#).

Examples

```
>>> from scipy.fft import dstn, idstn
>>> y = np.random.randn(16, 16)
>>> np.allclose(y, idstn(dstn(y)))
True
```

6.5.3 Helper functions

<code>fftshift(x[, axes])</code>	Shift the zero-frequency component to the center of the spectrum.
<code>ifftshift(x[, axes])</code>	The inverse of <code>fftshift</code> .
<code>fftfreq(n[, d])</code>	Return the Discrete Fourier Transform sample frequencies.
<code>rfftfreq(n[, d])</code>	Return the Discrete Fourier Transform sample frequencies (for usage with <code>rfft</code> , <code>irfft</code>).
<code>next_fast_len()</code>	Find the next fast size of input data to <code>fft</code> , for zero-padding, etc.
<code>set_workers(workers)</code>	Context manager for the default number of workers used in <code>scipy.fft</code>
<code>get_workers()</code>	Returns the default number of workers within the current context

scipy.fft.fftshift

`scipy.fft.fftshift(x, axes=None)`

Shift the zero-frequency component to the center of the spectrum.

This function swaps half-spaces for all axes listed (defaults to all). Note that `y[0]` is the Nyquist component only if `len(x)` is even.

Parameters

x [array_like] Input array.
axes [int or shape tuple, optional] Axes over which to shift. Default is None, which shifts all axes.

Returns

y [ndarray] The shifted array.

See also:

`ifftshift`

The inverse of `fftshift`.

Examples

```
>>> freqs = np.fft.fftfreq(10, 0.1)
>>> freqs
array([ 0.,  1.,  2., ..., -3., -2., -1.])
>>> np.fft.fftshift(freqs)
array([-5., -4., -3., -2., -1.,  0.,  1.,  2.,  3.,  4.])
```

Shift the zero-frequency component only along the second axis:

```
>>> freqs = np.fft.fftfreq(9, d=1./9).reshape(3, 3)
>>> freqs
array([[ 0.,  1.,  2.],
       [ 3.,  4., -4.],
       [-3., -2., -1.]])
>>> np.fft.fftshift(freqs, axes=(1,))
array([[ 2.,  0.,  1.],
       [-4.,  3.,  4.],
       [-1., -3., -2.]])
```

scipy.fft.ifftshift

`scipy.fft.ifftshift(x, axes=None)`

The inverse of `fftshift`. Although identical for even-length x , the functions differ by one sample for odd-length x .

Parameters

x [array_like] Input array.
axes [int or shape tuple, optional] Axes over which to calculate. Defaults to None, which shifts all axes.

Returns

y [ndarray] The shifted array.

See also:

`fftshift`

Shift zero-frequency component to the center of the spectrum.

Examples

```
>>> freqs = np.fft.fftfreq(9, d=1./9).reshape(3, 3)
>>> freqs
array([[ 0.,  1.,  2.],
       [ 3.,  4., -4.],
       [-3., -2., -1.]])
>>> np.fft.ifftshift(np.fft.fftshift(freqs))
array([[ 0.,  1.,  2.],
       [ 3.,  4., -4.],
       [-3., -2., -1.]])
```

scipy.fft.fftfreq

`scipy.fft.fftfreq(n, d=1.0)`

Return the Discrete Fourier Transform sample frequencies.

The returned float array f contains the frequency bin centers in cycles per unit of the sample spacing (with zero at the start). For instance, if the sample spacing is in seconds, then the frequency unit is cycles/second.

Given a window length n and a sample spacing d :

$f = [0, 1, \dots, n/2-1, -n/2, \dots, -1] / (d*n)$	if n is even
$f = [0, 1, \dots, (n-1)/2, -(n-1)/2, \dots, -1] / (d*n)$	if n is odd

Parameters

n [int] Window length.
d [scalar, optional] Sample spacing (inverse of the sampling rate). Defaults to 1.

Returns

f [ndarray] Array of length n containing the sample frequencies.

Examples

```
>>> signal = np.array([-2, 8, 6, 4, 1, 0, 3, 5], dtype=float)
>>> fourier = np.fft.fft(signal)
>>> n = signal.size
>>> timestep = 0.1
>>> freq = np.fft.fftfreq(n, d=timestep)
>>> freq
array([ 0. ,  1.25,  2.5 , ..., -3.75, -2.5 , -1.25])
```

scipy.fft.rfftfreq

`scipy.fft.rfftfreq(n, d=1.0)`

Return the Discrete Fourier Transform sample frequencies (for usage with rfft, irfft).

The returned float array f contains the frequency bin centers in cycles per unit of the sample spacing (with zero at the start). For instance, if the sample spacing is in seconds, then the frequency unit is cycles/second.

Given a window length n and a sample spacing d :

$f = [0, 1, \dots, n/2-1, n/2] / (d*n)$	if n is even
$f = [0, 1, \dots, (n-1)/2-1, (n-1)/2] / (d*n)$	if n is odd

Unlike `fftfreq` (but like `scipy.fftpack.rfftfreq`) the Nyquist frequency component is considered to be positive.

Parameters

n [int] Window length.
d [scalar, optional] Sample spacing (inverse of the sampling rate). Defaults to 1.

Returns

f [ndarray] Array of length $n//2 + 1$ containing the sample frequencies.

Examples

```
>>> signal = np.array([-2, 8, 6, 4, 1, 0, 3, 5, -3, 4], dtype=float)
>>> fourier = np.fft.rfft(signal)
>>> n = signal.size
>>> sample_rate = 100
>>> freq = np.fft.fftfreq(n, d=1./sample_rate)
>>> freq
array([ 0., 10., 20., ..., -30., -20., -10.])
>>> freq = np.fft.rfftfreq(n, d=1./sample_rate)
>>> freq
array([ 0., 10., 20., 30., 40., 50.])
```

scipy.fft.next_fast_len

`scipy.fft.next_fast_len()`

Find the next fast size of input data to `fft`, for zero-padding, etc.

SciPy's FFT algorithms gain their speed by a recursive divide and conquer strategy. This relies on efficient functions for small prime factors of the input length. Thus, the transforms are fastest when using composites of the prime factors handled by the `fft` implementation. If there are efficient functions for all radices $\leq n$, then the result will be a number $x \geq \text{target}$ with only prime factors $< n$. (Also known as n -smooth numbers)

Parameters

target	[int] Length to start searching from. Must be a positive integer.
real	[bool, optional] True if the FFT involves real input or output (e.g., <code>rfft</code> or <code>hfft</code> but not <code>fft</code>). Defaults to False.

Returns

out	[int] The smallest fast length greater than or equal to <code>target</code> .
------------	---

Notes

The result of this function may change in future as performance considerations change, for example, if new prime factors are added.

Calling `fft` or `ifft` with real input data performs an 'R2C' transform internally.

Examples

On a particular machine, an FFT of prime length takes 11.4 ms:

```
>>> from scipy import fft
>>> min_len = 93059 # prime length is worst case for speed
>>> a = np.random.randn(min_len)
>>> b = fft.fft(a)
```

Zero-padding to the next regular length reduces computation time to 1.6 ms, a speedup of 7.3 times:

```
>>> fft.next_fast_len(min_len, real=True)
93312
>>> b = fft.fft(a, 93312)
```

Rounding up to the next power of 2 is not optimal, taking 3.0 ms to compute; 1.9 times longer than the size given by `next_fast_len`:

```
>>> b = fft.fft(a, 131072)
```

scipy.fft.set_workers

`scipy.fft.set_workers` (*workers*)

Context manager for the default number of workers used in `scipy.fft`

Parameters

workers [int] The default number of workers to use

Examples

```
>>> from scipy import fft, signal
>>> x = np.random.randn(128, 64)
>>> with fft.set_workers(4):
...     y = signal.fftconvolve(x, x)
```

scipy.fft.get_workers

`scipy.fft.get_workers` ()

Returns the default number of workers within the current context

Examples

```
>>> from scipy import fft
>>> fft.get_workers()
1
>>> with fft.set_workers(4):
...     fft.get_workers()
4
```

6.5.4 Backend control

<code>set_backend</code> (backend[, coerce, only])	Context manager to set the backend within a fixed scope.
<code>skip_backend</code> (backend)	Context manager to skip a backend within a fixed scope.
<code>set_global_backend</code> (backend)	Sets the global fft backend
<code>register_backend</code> (backend)	Register a backend for permanent use.

scipy.fft.set_backend

`scipy.fft.set_backend(backend, coerce=False, only=False)`

Context manager to set the backend within a fixed scope.

Upon entering the `with` statement, the given backend will be added to the list of available backends with the highest priority. Upon exit, the backend is reset to the state before entering the scope.

Parameters

backend: {object, 'scipy'}

The backend to use. Can either be a `str` containing the name of a known backend {'scipy'} or an object that implements the `uarray` protocol.

coerce: bool, optional

Whether to allow expensive conversions for the `x` parameter. e.g., copying a NumPy array to the GPU for a CuPy backend. Implies `only`.

only: bool, optional

If `only` is `True` and this backend returns `NotImplemented`, then a `BackendNotImplementedError` will be raised immediately. Ignoring any lower priority backends.

Examples

```
>>> import scipy.fft as fft
>>> with fft.set_backend('scipy', only=True):
...     fft.fft([1]) # Always calls the scipy implementation
array([1.+0.j])
```

scipy.fft.skip_backend

`scipy.fft.skip_backend(backend)`

Context manager to skip a backend within a fixed scope.

Within the context of a `with` statement, the given backend will not be called. This covers backends registered both locally and globally. Upon exit, the backend will again be considered.

Parameters

backend: {object, 'scipy'}

The backend to skip. Can either be a `str` containing the name of a known backend {'scipy'} or an object that implements the `uarray` protocol.

Examples

```
>>> import scipy.fft as fft
>>> fft.fft([1]) # Calls default SciPy backend
array([1.+0.j])
>>> with fft.skip_backend('scipy'): # We explicitly skip the SciPy_
↳backend
...     fft.fft([1]) # leaving no implementation available
Traceback (most recent call last):
...
BackendNotImplementedError: No selected backends had an implementation ...
```

scipy.fft.set_global_backend

`scipy.fft.set_global_backend(backend)`

Sets the global fft backend

The global backend has higher priority than registered backends, but lower priority than context-specific backends set with `set_backend`.

Parameters

backend: {object, 'scipy'}

The backend to use. Can either be a `str` containing the name of a known backend {'scipy'} or an object that implements the `uarray` protocol.

Raises

ValueError: If the backend does not implement `numpy.scipy.fft`.

Notes

This will overwrite the previously set global backend, which, by default, is the SciPy implementation.

Examples

We can set the global fft backend:

```
>>> from scipy.fft import fft, set_global_backend
>>> set_global_backend("scipy") # Sets global backend. "scipy" is the
    → default backend.
>>> fft([1]) # Calls the global backend
array([1.+0.j])
```

scipy.fft.register_backend

`scipy.fft.register_backend(backend)`

Register a backend for permanent use.

Registered backends have the lowest priority and will be tried after the global backend.

Parameters

backend: {object, 'scipy'}

The backend to use. Can either be a `str` containing the name of a known backend {'scipy'} or an object that implements the `uarray` protocol.

Raises

ValueError: If the backend does not implement `numpy.scipy.fft`.

Examples

We can register a new fft backend:

```
>>> from scipy.fft import fft, register_backend, set_global_backend
>>> class NoopBackend: # Define an invalid Backend
...     __ua_domain__ = "numpy.scipy.fft"
...     def __ua_function__(self, func, args, kwargs):
...         return NotImplemented
>>> set_global_backend(NoopBackend()) # Set the invalid backend as global
>>> register_backend("scipy") # Register a new backend
>>> fft([1]) # The registered backend is called because the global_
↳backend returns `NotImplemented`
array([1.+0.j])
>>> set_global_backend("scipy") # Restore global backend to default
```

6.6 Legacy discrete Fourier transforms (`scipy.fftpack`)

Warning: This submodule is now considered legacy, new code should use `scipy.fft`.

6.6.1 Fast Fourier Transforms (FFTs)

<code>fft(x[, n, axis, overwrite_x])</code>	Return discrete Fourier transform of real or complex sequence.
<code>ifft(x[, n, axis, overwrite_x])</code>	Return discrete inverse Fourier transform of real or complex sequence.
<code>fft2(x[, shape, axes, overwrite_x])</code>	2-D discrete Fourier transform.
<code>ifft2(x[, shape, axes, overwrite_x])</code>	2-D discrete inverse Fourier transform of real or complex sequence.
<code>fftn(x[, shape, axes, overwrite_x])</code>	Return multidimensional discrete Fourier transform.
<code>ifftn(x[, shape, axes, overwrite_x])</code>	Return inverse multidimensional discrete Fourier transform.
<code>rfft(x[, n, axis, overwrite_x])</code>	Discrete Fourier transform of a real sequence.
<code>irfft(x[, n, axis, overwrite_x])</code>	Return inverse discrete Fourier transform of real sequence x .
<code>dct(x[, type, n, axis, norm, overwrite_x])</code>	Return the Discrete Cosine Transform of arbitrary type sequence x .
<code>idct(x[, type, n, axis, norm, overwrite_x])</code>	Return the Inverse Discrete Cosine Transform of an arbitrary type sequence.
<code>dctn(x[, type, shape, axes, norm, overwrite_x])</code>	Return multidimensional Discrete Cosine Transform along the specified axes.
<code>idctn(x[, type, shape, axes, norm, overwrite_x])</code>	Return multidimensional Discrete Cosine Transform along the specified axes.
<code>dst(x[, type, n, axis, norm, overwrite_x])</code>	Return the Discrete Sine Transform of arbitrary type sequence x .
<code>idst(x[, type, n, axis, norm, overwrite_x])</code>	Return the Inverse Discrete Sine Transform of an arbitrary type sequence.

continues on next page

Table 20 – continued from previous page

<code>dstn(x[, type, shape, axes, norm, overwrite_x])</code>	Return multidimensional Discrete Sine Transform along the specified axes.
<code>idstn(x[, type, shape, axes, norm, overwrite_x])</code>	Return multidimensional Discrete Sine Transform along the specified axes.

scipy.fftpack.fft

`scipy.fftpack.fft(x, n=None, axis=-1, overwrite_x=False)`

Return discrete Fourier transform of real or complex sequence.

The returned complex array contains $y(0), y(1), \dots, y(n-1)$, where

$$y(j) = (x * \exp(-2\pi i \sqrt{-1} * j * \text{np.arange}(n) / n)).\text{sum}()$$

Parameters

- x** [array_like] Array to Fourier transform.
- n** [int, optional] Length of the Fourier transform. If $n < x.\text{shape}[\text{axis}]$, x is truncated. If $n > x.\text{shape}[\text{axis}]$, x is zero-padded. The default results in $n = x.\text{shape}[\text{axis}]$.
- axis** [int, optional] Axis along which the fft's are computed; the default is over the last axis (i.e., $\text{axis}=-1$).
- overwrite_x** [bool, optional] If True, the contents of x can be destroyed; the default is False.

Returns

- z** [complex ndarray] with the elements:

<code>[y(0), y(1), ..., y(n/2), y(1-n/2), ..., y(-1)]</code>	if n is
<code>↪ even</code>	
<code>[y(0), y(1), ..., y((n-1)/2), y(-(n-1)/2), ..., y(-1)]</code>	if n is
<code>↪ odd</code>	

where:

<code>y(j) = sum[k=0..n-1] x[k] * exp(-sqrt(-1)*j*k* 2*pi/n), j</code>
<code>↪ = 0..n-1</code>

See also:***ifft***

Inverse FFT

rfft

FFT of a real sequence

Notes

The packing of the result is “standard”: If $A = \text{fft}(a, n)$, then $A[0]$ contains the zero-frequency term, $A[1:n/2]$ contains the positive-frequency terms, and $A[n/2:]$ contains the negative-frequency terms, in order of decreasingly negative frequency. So, for an 8-point transform, the frequencies of the result are $[0, 1, 2, 3, -4, -3, -2, -1]$. To rearrange the fft output so that the zero-frequency component is centered, like $[-4, -3, -2, -1, 0, 1, 2, 3]$, use `fftshift`.

Both single and double precision routines are implemented. Half precision inputs will be converted to single precision. Non-floating-point inputs will be converted to double precision. Long-double precision inputs are not supported.

This function is most efficient when n is a power of two, and least efficient when n is prime.

Note that if x is real-valued, then $A[j] == A[n-j].\text{conjugate}()$. If x is real-valued and n is even, then $A[n/2]$ is real.

If the data type of x is real, a “real FFT” algorithm is automatically used, which roughly halves the computation time. To increase efficiency a little further, use `rfft`, which does the same calculation, but only outputs half of the symmetrical spectrum. If the data is both real and symmetrical, the `dct` can again double the efficiency by generating half of the spectrum from half of the signal.

Examples

```
>>> from scipy.fftpack import fft, ifft
>>> x = np.arange(5)
>>> np.allclose(fft(ifft(x)), x, atol=1e-15) # within numerical accuracy.
True
```

scipy.fftpack.ifft

`scipy.fftpack.ifft(x, n=None, axis=-1, overwrite_x=False)`

Return discrete inverse Fourier transform of real or complex sequence.

The returned complex array contains $y(0), y(1), \dots, y(n-1)$, where

$$y(j) = (x * \exp(2\pi i \sqrt{-1} * j * \text{np.arange}(n) / n)).\text{mean}()$$

Parameters

- x** [array_like] Transformed data to invert.
- n** [int, optional] Length of the inverse Fourier transform. If $n < x.\text{shape}[\text{axis}]$, x is truncated. If $n > x.\text{shape}[\text{axis}]$, x is zero-padded. The default results in $n = x.\text{shape}[\text{axis}]$.
- axis** [int, optional] Axis along which the ifft's are computed; the default is over the last axis (i.e., $\text{axis}=-1$).
- overwrite_x** [bool, optional] If True, the contents of x can be destroyed; the default is False.

Returns

- ifft** [ndarray of floats] The inverse discrete Fourier transform.

See also:

`fft`

Forward FFT

Notes

Both single and double precision routines are implemented. Half precision inputs will be converted to single precision. Non-floating-point inputs will be converted to double precision. Long-double precision inputs are not supported.

This function is most efficient when n is a power of two, and least efficient when n is prime.

If the data type of x is real, a “real IFFT” algorithm is automatically used, which roughly halves the computation time.

Examples

```
>>> from scipy.fftpack import fft, ifft
>>> import numpy as np
>>> x = np.arange(5)
>>> np.allclose(ifft(fft(x)), x, atol=1e-15) # within numerical accuracy.
True
```

scipy.fftpack.fft2

`scipy.fftpack.fft2(x, shape=None, axes=-2, -1, overwrite_x=False)`
2-D discrete Fourier transform.

Return the 2-D discrete Fourier transform of the 2-D argument x .

See also:

[*fftn*](#)

for detailed information.

Examples

```
>>> from scipy.fftpack import fft2, ifft2
>>> y = np.mgrid[:5, :5][0]
>>> y
array([[0, 0, 0, 0, 0],
       [1, 1, 1, 1, 1],
       [2, 2, 2, 2, 2],
       [3, 3, 3, 3, 3],
       [4, 4, 4, 4, 4]])
>>> np.allclose(y, ifft2(fft2(y)))
True
```

scipy.fftpack.ifft2

`scipy.fftpack.ifft2(x, shape=None, axes=-2, -1, overwrite_x=False)`
 2-D discrete inverse Fourier transform of real or complex sequence.

Return inverse 2-D discrete Fourier transform of arbitrary type sequence *x*.

See *ifft* for more information.

See also:

fft2, ifft

Examples

```
>>> from scipy.fftpack import fft2, ifft2
>>> y = np.mgrid[:5, :5][0]
>>> y
array([[0, 0, 0, 0, 0],
       [1, 1, 1, 1, 1],
       [2, 2, 2, 2, 2],
       [3, 3, 3, 3, 3],
       [4, 4, 4, 4, 4]])
>>> np.allclose(y, fft2(ifft2(y)))
True
```

scipy.fftpack.fftn

`scipy.fftpack.fftn(x, shape=None, axes=None, overwrite_x=False)`
 Return multidimensional discrete Fourier transform.

The returned array contains:

$$y[j_1, \dots, j_d] = \sum_{k_1=0..n_1-1, \dots, k_d=0..n_d-1} x[k_1, \dots, k_d] * \prod_{i=1..d} \exp(-\sqrt{-1} * 2 * \pi / n_i * j_i * k_i)$$

where $d = \text{len}(x.\text{shape})$ and $n = x.\text{shape}$.

Parameters

- x** [array_like] The (N-D) array to transform.
- shape** [int or array_like of ints or None, optional] The shape of the result. If both *shape* and *axes* (see below) are None, *shape* is *x.shape*; if *shape* is None but *axes* is not None, then *shape* is `scipy.take(x.shape, axes, axis=0)`. If *shape*[*i*] > *x.shape*[*i*], the *i*th dimension is padded with zeros. If *shape*[*i*] < *x.shape*[*i*], the *i*th dimension is truncated to length *shape*[*i*]. If any element of *shape* is -1, the size of the corresponding dimension of *x* is used.
- axes** [int or array_like of ints or None, optional] The axes of *x* (*y* if *shape* is not None) along which the transform is applied. The default is over all axes.
- overwrite_x** [bool, optional] If True, the contents of *x* can be destroyed. Default is False.

Returns

- y** [complex-valued N-D NumPy array] The (N-D) DFT of the input array.

See also:[*ifftn*](#)**Notes**

If x is real-valued, then $y[\dots, j_i, \dots] == y[\dots, n_i - j_i, \dots].\text{conjugate}()$.

Both single and double precision routines are implemented. Half precision inputs will be converted to single precision. Non-floating-point inputs will be converted to double precision. Long-double precision inputs are not supported.

Examples

```
>>> from scipy.fftpack import fftn, ifftn
>>> y = (-np.arange(16), 8 - np.arange(16), np.arange(16))
>>> np.allclose(y, fftn(ifftn(y)))
True
```

scipy.fftpack.ifftn

`scipy.fftpack.ifftn(x, shape=None, axes=None, overwrite_x=False)`

Return inverse multidimensional discrete Fourier transform.

The sequence can be of an arbitrary type.

The returned array contains:

$$y[j_1, \dots, j_d] = 1/p * \sum[k_1=0..n_1-1, \dots, k_d=0..n_d-1] x[k_1, \dots, k_d] * \text{prod}[i=1..d] \exp(\text{sqrt}(-1)*2*\pi/n_i * j_i * k_i)$$

where $d = \text{len}(x.\text{shape})$, $n = x.\text{shape}$, and $p = \text{prod}[i=1..d] n_i$.

For description of parameters see [*fftn*](#).

See also:[*fftn*](#)

for detailed information.

Examples

```
>>> from scipy.fftpack import fftn, ifftn
>>> import numpy as np
>>> y = (-np.arange(16), 8 - np.arange(16), np.arange(16))
>>> np.allclose(y, ifftn(fftn(y)))
True
```

scipy.fftpack.rfft

`scipy.fftpack.rfft(x, n=None, axis=-1, overwrite_x=False)`

Discrete Fourier transform of a real sequence.

Parameters

- x** [array_like, real-valued] The data to transform.
- n** [int, optional] Defines the length of the Fourier transform. If *n* is not specified (the default) then $n = x.shape[axis]$. If $n < x.shape[axis]$, *x* is truncated, if $n > x.shape[axis]$, *x* is zero-padded.
- axis** [int, optional] The axis along which the transform is applied. The default is the last axis.
- overwrite_x** [bool, optional] If set to true, the contents of *x* can be overwritten. Default is False.

Returns

- z** [real ndarray] The returned real array contains:

<code>[y(0), Re(y(1)), Im(y(1)), ..., Re(y(n/2))]</code>	if <code>n</code>
<code>↪ is even</code>	
<code>[y(0), Re(y(1)), Im(y(1)), ..., Re(y(n/2)), Im(y(n/2))]</code>	if <code>n</code>
<code>↪ is odd</code>	

where:

<code>y(j) = sum[k=0..n-1] x[k] * exp(-sqrt(-1)*j*k*2*pi/n)</code>
<code>j = 0..n-1</code>

See also:

[*fft*](#), [*irfft*](#), [*scipy.fft.rfft*](#)

Notes

Within numerical accuracy, `y == rfft(irfft(y))`.

Both single and double precision routines are implemented. Half precision inputs will be converted to single precision. Non-floating-point inputs will be converted to double precision. Long-double precision inputs are not supported.

To get an output with a complex datatype, consider using the newer function [*scipy.fft.rfft*](#).

Examples

```
>>> from scipy.fftpack import fft, rfft
>>> a = [9, -9, 1, 3]
>>> fft(a)
array([ 4.+0.j,  8.+12.j, 16.+0.j,  8.-12.j])
>>> rfft(a)
array([ 4.,  8., 12., 16.]
```

scipy.fftpack.irfft

`scipy.fftpack.irfft(x, n=None, axis=-1, overwrite_x=False)`

Return inverse discrete Fourier transform of real sequence `x`.

The contents of `x` are interpreted as the output of the `rfft` function.

Parameters

- x** [array_like] Transformed data to invert.
- n** [int, optional] Length of the inverse Fourier transform. If $n < x.shape[axis]$, `x` is truncated. If $n > x.shape[axis]$, `x` is zero-padded. The default results in $n = x.shape[axis]$.
- axis** [int, optional] Axis along which the ifft's are computed; the default is over the last axis (i.e., `axis=-1`).
- overwrite_x** [bool, optional] If True, the contents of `x` can be destroyed; the default is False.

Returns

- irfft** [ndarray of floats] The inverse discrete Fourier transform.

See also:

`rfft`, `ifft`, `scipy.fft.irfft`

Notes

The returned real array contains:

$$[y(0), y(1), \dots, y(n-1)]$$

where for `n` is even:

$$y(j) = \frac{1}{n} \left(\sum_{k=1..n/2-1} (x[2*k-1] + \sqrt{-1} * x[2*k]) \right. \\ \left. * \exp(\sqrt{-1} * j * k * 2 * \pi / n) \right. \\ \left. + \text{c.c.} + x[0] + (-1)**(j) * x[n-1] \right)$$

and for `n` is odd:

$$y(j) = \frac{1}{n} \left(\sum_{k=1..(n-1)/2} (x[2*k-1] + \sqrt{-1} * x[2*k]) \right. \\ \left. * \exp(\sqrt{-1} * j * k * 2 * \pi / n) \right. \\ \left. + \text{c.c.} + x[0] \right)$$

c.c. denotes complex conjugate of preceding expression.

For details on input parameters, see `rfft`.

To process (conjugate-symmetric) frequency-domain data with a complex datatype, consider using the newer function `scipy.fft.irfft`.

Examples

```
>>> from scipy.fftpack import rfft, irfft
>>> a = [1.0, 2.0, 3.0, 4.0, 5.0]
>>> irfft(a)
array([ 2.6          , -3.16405192,  1.24398433, -1.14955713,  1.46962473])
>>> irfft(rfft(a))
array([1., 2., 3., 4., 5.]
```

scipy.fftpack.dct

`scipy.fftpack.dct` (*x*, *type*=2, *n*=None, *axis*=-1, *norm*=None, *overwrite_x*=False)

Return the Discrete Cosine Transform of arbitrary type sequence *x*.

Parameters

- x** [array_like] The input array.
- type** [{1, 2, 3, 4}, optional] Type of the DCT (see Notes). Default type is 2.
- n** [int, optional] Length of the transform. If $n < x.shape[axis]$, *x* is truncated. If $n > x.shape[axis]$, *x* is zero-padded. The default results in $n = x.shape[axis]$.
- axis** [int, optional] Axis along which the dct is computed; the default is over the last axis (i.e., *axis*=-1).
- norm** [{None, 'ortho'}, optional] Normalization mode (see Notes). Default is None.
- overwrite_x** [bool, optional] If True, the contents of *x* can be destroyed; the default is False.

Returns

- y** [ndarray of real] The transformed input array.

See also:

[*idct*](#)

Inverse DCT

Notes

For a single dimension array *x*, `dct(x, norm='ortho')` is equal to MATLAB `dct(x)`.

There are, theoretically, 8 types of the DCT, only the first 4 types are implemented in `scipy`. ‘The’ DCT generally refers to DCT type 2, and ‘the’ Inverse DCT generally refers to DCT type 3.

Type I

There are several definitions of the DCT-I; we use the following (for *norm*=None)

$$y_k = x_0 + (-1)^k x_{N-1} + 2 \sum_{n=1}^{N-2} x_n \cos\left(\frac{\pi kn}{N-1}\right)$$

If *norm*='ortho', *x*[0] and *x*[*N*-1] are multiplied by a scaling factor of $\sqrt{2}$, and *y*[*k*] is multiplied by a scaling factor *f*

$$f = \begin{cases} \frac{1}{2} \sqrt{\frac{1}{N-1}} & \text{if } k = 0 \text{ or } N - 1, \\ \frac{1}{2} \sqrt{\frac{2}{N-1}} & \text{otherwise} \end{cases}$$

New in version 1.2.0: Orthonormalization in DCT-I.

Note: The DCT-I is only supported for input size > 1 .

Type II

There are several definitions of the DCT-II; we use the following (for `norm=None`)

$$y_k = 2 \sum_{n=0}^{N-1} x_n \cos\left(\frac{\pi k(2n+1)}{2N}\right)$$

If `norm='ortho'`, $y[k]$ is multiplied by a scaling factor f

$$f = \begin{cases} \sqrt{\frac{1}{4N}} & \text{if } k = 0, \\ \sqrt{\frac{1}{2N}} & \text{otherwise} \end{cases}$$

which makes the corresponding matrix of coefficients orthonormal ($O @ O.T = \text{np.eye}(N)$).

Type III

There are several definitions, we use the following (for `norm=None`)

$$y_k = x_0 + 2 \sum_{n=1}^{N-1} x_n \cos\left(\frac{\pi(2k+1)n}{2N}\right)$$

or, for `norm='ortho'`

$$y_k = \frac{x_0}{\sqrt{N}} + \sqrt{\frac{2}{N}} \sum_{n=1}^{N-1} x_n \cos\left(\frac{\pi(2k+1)n}{2N}\right)$$

The (unnormalized) DCT-III is the inverse of the (unnormalized) DCT-II, up to a factor $2N$. The orthonormalized DCT-III is exactly the inverse of the orthonormalized DCT-II.

Type IV

There are several definitions of the DCT-IV; we use the following (for `norm=None`)

$$y_k = 2 \sum_{n=0}^{N-1} x_n \cos\left(\frac{\pi(2k+1)(2n+1)}{4N}\right)$$

If `norm='ortho'`, $y[k]$ is multiplied by a scaling factor f

$$f = \frac{1}{\sqrt{2N}}$$

New in version 1.2.0: Support for DCT-IV.

References

[1], [2]

Examples

The Type 1 DCT is equivalent to the FFT (though faster) for real, even-symmetrical inputs. The output is also real and even-symmetrical. Half of the FFT input is used to generate half of the FFT output:

```
>>> from scipy.fftpack import fft, dct
>>> fft(np.array([4., 3., 5., 10., 5., 3.])).real
array([ 30., -8.,  6., -2.,  6., -8.])
>>> dct(np.array([4., 3., 5., 10.]), 1)
array([ 30., -8.,  6., -2.])
```

scipy.fftpack.idct

`scipy.fftpack.idct(x, type=2, n=None, axis=-1, norm=None, overwrite_x=False)`

Return the Inverse Discrete Cosine Transform of an arbitrary type sequence.

Parameters

x	[array_like] The input array.
type	[[1, 2, 3, 4], optional] Type of the DCT (see Notes). Default type is 2.
n	[int, optional] Length of the transform. If $n < x.shape[axis]$, x is truncated. If $n > x.shape[axis]$, x is zero-padded. The default results in $n = x.shape[axis]$.
axis	[int, optional] Axis along which the idct is computed; the default is over the last axis (i.e., $axis=-1$).
norm	[[None, 'ortho'], optional] Normalization mode (see Notes). Default is None.
overwrite_x	[bool, optional] If True, the contents of x can be destroyed; the default is False.

Returns

idct	[ndarray of real] The transformed input array.
-------------	--

See also:

[*dct*](#)

Forward DCT

Notes

For a single dimension array x , `idct(x, norm='ortho')` is equal to `MATLAB idct(x)`.

'The' IDCT is the IDCT of type 2, which is the same as DCT of type 3.

IDCT of type 1 is the DCT of type 1, IDCT of type 2 is the DCT of type 3, and IDCT of type 3 is the DCT of type 2. IDCT of type 4 is the DCT of type 4. For the definition of these types, see [*dct*](#).

Examples

The Type 1 DCT is equivalent to the DFT for real, even-symmetrical inputs. The output is also real and even-symmetrical. Half of the IFFT input is used to generate half of the IFFT output:

```
>>> from scipy.fftpack import ifft, idct
>>> ifft(np.array([ 30., -8., 6., -2., 6., -8.])).real
array([ 4., 3., 5., 10., 5., 3.])
>>> idct(np.array([ 30., -8., 6., -2.]), 1) / 6
array([ 4., 3., 5., 10.])
```

scipy.fftpack.dctn

`scipy.fftpack.dctn(x, type=2, shape=None, axes=None, norm=None, overwrite_x=False)`

Return multidimensional Discrete Cosine Transform along the specified axes.

Parameters

x	[array_like] The input array.
type	[[1, 2, 3, 4], optional] Type of the DCT (see Notes). Default type is 2.
shape	[int or array_like of ints or None, optional] The shape of the result. If both <i>shape</i> and <i>axes</i> (see below) are None, <i>shape</i> is <i>x.shape</i> ; if <i>shape</i> is None but <i>axes</i> is not None, then <i>shape</i> is <code>scipy.take(x.shape, axes, axis=0)</code> . If <code>shape[i] > x.shape[i]</code> , the <i>i</i> th dimension is padded with zeros. If <code>shape[i] < x.shape[i]</code> , the <i>i</i> th dimension is truncated to length <code>shape[i]</code> . If any element of <i>shape</i> is -1, the size of the corresponding dimension of <i>x</i> is used.
axes	[int or array_like of ints or None, optional] Axes along which the DCT is computed. The default is over all axes.
norm	[[None, 'ortho'], optional] Normalization mode (see Notes). Default is None.
overwrite_x	[bool, optional] If True, the contents of <i>x</i> can be destroyed; the default is False.

Returns

y [ndarray of real] The transformed input array.

See also:

[*idctn*](#)

Inverse multidimensional DCT

Notes

For full details of the DCT types and normalization modes, as well as references, see [*dct*](#).

Examples

```
>>> from scipy.fftpack import dctn, idctn
>>> y = np.random.randn(16, 16)
>>> np.allclose(y, idctn(dctn(y, norm='ortho'), norm='ortho'))
True
```

scipy.fftpack.idctn

`scipy.fftpack.idctn(x, type=2, shape=None, axes=None, norm=None, overwrite_x=False)`

Return multidimensional Discrete Cosine Transform along the specified axes.

Parameters

x	[array_like] The input array.
type	[[1, 2, 3, 4], optional] Type of the DCT (see Notes). Default type is 2.
shape	[int or array_like of ints or None, optional] The shape of the result. If both <i>shape</i> and <i>axes</i> (see below) are None, <i>shape</i> is <code>x.shape</code> ; if <i>shape</i> is None but <i>axes</i> is not None, then <i>shape</i> is <code>scipy.take(x.shape, axes, axis=0)</code> . If <code>shape[i] > x.shape[i]</code> , the <i>i</i> th dimension is padded with zeros. If <code>shape[i] < x.shape[i]</code> , the <i>i</i> th dimension is truncated to length <code>shape[i]</code> . If any element of <i>shape</i> is -1, the size of the corresponding dimension of <i>x</i> is used.
axes	[int or array_like of ints or None, optional] Axes along which the IDCT is computed. The default is over all axes.
norm	[[None, 'ortho'], optional] Normalization mode (see Notes). Default is None.
overwrite_x	[bool, optional] If True, the contents of <i>x</i> can be destroyed; the default is False.

Returns

y [ndarray of real] The transformed input array.

See also:

[*dctn*](#)

multidimensional DCT

Notes

For full details of the IDCT types and normalization modes, as well as references, see [*idct*](#).

Examples

```
>>> from scipy.fftpack import dctn, idctn
>>> y = np.random.randn(16, 16)
>>> np.allclose(y, idctn(dctn(y, norm='ortho'), norm='ortho'))
True
```

scipy.fftpack.dst

`scipy.fftpack.dst(x, type=2, n=None, axis=-1, norm=None, overwrite_x=False)`

Return the Discrete Sine Transform of arbitrary type sequence `x`.

Parameters

x	[array_like] The input array.
type	[[1, 2, 3, 4], optional] Type of the DST (see Notes). Default type is 2.
n	[int, optional] Length of the transform. If $n < x.shape[axis]$, <code>x</code> is truncated. If $n > x.shape[axis]$, <code>x</code> is zero-padded. The default results in $n = x.shape[axis]$.
axis	[int, optional] Axis along which the dst is computed; the default is over the last axis (i.e., <code>axis=-1</code>).
norm	[[None, 'ortho'], optional] Normalization mode (see Notes). Default is None.
overwrite_x	[bool, optional] If True, the contents of <code>x</code> can be destroyed; the default is False.

Returns

dst [ndarray of reals] The transformed input array.

See also:*idst*

Inverse DST

Notes

For a single dimension array `x`.

There are, theoretically, 8 types of the DST for different combinations of even/odd boundary conditions and boundary off sets [1], only the first 4 types are implemented in scipy.

Type I

There are several definitions of the DST-I; we use the following for `norm=None`. DST-I assumes the input is odd around $n=-1$ and $n=N$.

$$y_k = 2 \sum_{n=0}^{N-1} x_n \sin\left(\frac{\pi(k+1)(n+1)}{N+1}\right)$$

Note that the DST-I is only supported for input size > 1 . The (unnormalized) DST-I is its own inverse, up to a factor $2(N+1)$. The orthonormalized DST-I is exactly its own inverse.

Type II

There are several definitions of the DST-II; we use the following for `norm=None`. DST-II assumes the input is odd around $n=-1/2$ and $n=N-1/2$; the output is odd around $k=-1$ and even around $k=N-1$

$$y_k = 2 \sum_{n=0}^{N-1} x_n \sin\left(\frac{\pi(k+1)(2n+1)}{2N}\right)$$

if `norm='ortho'`, `y[k]` is multiplied by a scaling factor f

$$f = \begin{cases} \sqrt{\frac{1}{4N}} & \text{if } k = 0, \\ \sqrt{\frac{1}{2N}} & \text{otherwise} \end{cases}$$

Type III

There are several definitions of the DST-III, we use the following (for `norm=None`). DST-III assumes the input is odd around $n=-1$ and even around $n=N-1$

$$y_k = (-1)^k x_{N-1} + 2 \sum_{n=0}^{N-2} x_n \sin\left(\frac{\pi(2k+1)(n+1)}{2N}\right)$$

The (unnormalized) DST-III is the inverse of the (unnormalized) DST-II, up to a factor $2N$. The orthonormalized DST-III is exactly the inverse of the orthonormalized DST-II.

New in version 0.11.0.

Type IV

There are several definitions of the DST-IV, we use the following (for `norm=None`). DST-IV assumes the input is odd around $n=-0.5$ and even around $n=N-0.5$

$$y_k = 2 \sum_{n=0}^{N-1} x_n \sin\left(\frac{\pi(2k+1)(2n+1)}{4N}\right)$$

The (unnormalized) DST-IV is its own inverse, up to a factor $2N$. The orthonormalized DST-IV is exactly its own inverse.

New in version 1.2.0: Support for DST-IV.

References

[1]

scipy.fftpack.idst

`scipy.fftpack.idst(x, type=2, n=None, axis=-1, norm=None, overwrite_x=False)`

Return the Inverse Discrete Sine Transform of an arbitrary type sequence.

Parameters

x	[array_like] The input array.
type	[[1, 2, 3, 4], optional] Type of the DST (see Notes). Default type is 2.
n	[int, optional] Length of the transform. If $n < x.shape[axis]$, x is truncated. If $n > x.shape[axis]$, x is zero-padded. The default results in $n = x.shape[axis]$.
axis	[int, optional] Axis along which the idst is computed; the default is over the last axis (i.e., $axis=-1$).
norm	[[None, 'ortho'], optional] Normalization mode (see Notes). Default is None.
overwrite_x	[bool, optional] If True, the contents of x can be destroyed; the default is False.

Returns

idst [ndarray of real] The transformed input array.

See also:

[dst](#)

Forward DST

Notes

'The' IDST is the IDST of type 2, which is the same as DST of type 3.

IDST of type 1 is the DST of type 1, IDST of type 2 is the DST of type 3, and IDST of type 3 is the DST of type 2. For the definition of these types, see [dst](#).

New in version 0.11.0.

scipy.fftpack.dstn

`scipy.fftpack.dstn(x, type=2, shape=None, axes=None, norm=None, overwrite_x=False)`

Return multidimensional Discrete Sine Transform along the specified axes.

Parameters

x	[array_like] The input array.
type	[[1, 2, 3, 4], optional] Type of the DST (see Notes). Default type is 2.
shape	[int or array_like of ints or None, optional] The shape of the result. If both <i>shape</i> and <i>axes</i> (see below) are None, <i>shape</i> is <code>x.shape</code> ; if <i>shape</i> is None but <i>axes</i> is not None, then <i>shape</i> is <code>scipy.take(x.shape, axes, axis=0)</code> . If <code>shape[i] > x.shape[i]</code> , the <i>i</i> th dimension is padded with zeros. If <code>shape[i] < x.shape[i]</code> , the <i>i</i> th dimension is truncated to length <code>shape[i]</code> . If any element of <i>shape</i> is -1, the size of the corresponding dimension of <i>x</i> is used.
axes	[int or array_like of ints or None, optional] Axes along which the DCT is computed. The default is over all axes.
norm	[[None, 'ortho'], optional] Normalization mode (see Notes). Default is None.
overwrite_x	[bool, optional] If True, the contents of <i>x</i> can be destroyed; the default is False.

Returns

y [ndarray of real] The transformed input array.

See also:

[idstn](#)

Inverse multidimensional DST

Notes

For full details of the DST types and normalization modes, as well as references, see [dst](#).

Examples

```
>>> from scipy.fftpack import dstn, idstn
>>> y = np.random.randn(16, 16)
>>> np.allclose(y, idstn(dstn(y, norm='ortho'), norm='ortho'))
True
```

scipy.fftpack.idstn

`scipy.fftpack.idstn(x, type=2, shape=None, axes=None, norm=None, overwrite_x=False)`
 Return multidimensional Discrete Sine Transform along the specified axes.

Parameters

x [array_like] The input array.
type [{1, 2, 3, 4}, optional] Type of the DST (see Notes). Default type is 2.
shape [int or array_like of ints or None, optional] The shape of the result. If both *shape* and *axes* (see below) are None, *shape* is `x.shape`; if *shape* is None but *axes* is not None, then *shape* is `scipy.take(x.shape, axes, axis=0)`. If `shape[i] > x.shape[i]`, the *i*th dimension is padded with zeros. If `shape[i] < x.shape[i]`, the *i*th dimension is truncated to length `shape[i]`. If any element of *shape* is -1, the size of the corresponding dimension of *x* is used.
axes [int or array_like of ints or None, optional] Axes along which the IDST is computed. The default is over all axes.
norm [{None, 'ortho'}, optional] Normalization mode (see Notes). Default is None.
overwrite_x [bool, optional] If True, the contents of *x* can be destroyed; the default is False.

Returns

y [ndarray of real] The transformed input array.

See also:

dstn

multidimensional DST

Notes

For full details of the IDST types and normalization modes, as well as references, see *idst*.

Examples

```
>>> from scipy.fftpack import dstn, idstn
>>> y = np.random.randn(16, 16)
>>> np.allclose(y, idstn(dstn(y, norm='ortho'), norm='ortho'))
True
```

6.6.2 Differential and pseudo-differential operators

<code>diff(x[, order, period, _cache])</code>	Return <i>k</i> th derivative (or integral) of a periodic sequence <i>x</i> .
<code>tilbert(x, h[, period, _cache])</code>	Return <i>h</i> -Tilbert transform of a periodic sequence <i>x</i> .
<code>itilbert(x, h[, period, _cache])</code>	Return inverse <i>h</i> -Tilbert transform of a periodic sequence <i>x</i> .
<code>hilbert(x[, _cache])</code>	Return Hilbert transform of a periodic sequence <i>x</i> .
<code>ihilbert(x)</code>	Return inverse Hilbert transform of a periodic sequence <i>x</i> .

continues on next page

Table 21 – continued from previous page

<code>cs_diff(x, a, b[, period, _cache])</code>	Return (a,b)-cosh/sinh pseudo-derivative of a periodic sequence.
<code>sc_diff(x, a, b[, period, _cache])</code>	Return (a,b)-sinh/cosh pseudo-derivative of a periodic sequence x.
<code>ss_diff(x, a, b[, period, _cache])</code>	Return (a,b)-sinh/sinh pseudo-derivative of a periodic sequence x.
<code>cc_diff(x, a, b[, period, _cache])</code>	Return (a,b)-cosh/cosh pseudo-derivative of a periodic sequence.
<code>shift(x, a[, period, _cache])</code>	Shift periodic sequence x by a: $y(u) = x(u+a)$.

scipy.fftpack.diff

`scipy.fftpack.diff(x, order=1, period=None, _cache={})`

Return kth derivative (or integral) of a periodic sequence x.

If x_j and y_j are Fourier coefficients of periodic functions x and y, respectively, then:

```
y_j = pow(sqrt(-1)*j*2*pi/period, order) * x_j
y_0 = 0 if order is not 0.
```

Parameters

- x** [array_like] Input array.
- order** [int, optional] The order of differentiation. Default order is 1. If order is negative, then integration is carried out under the assumption that $x_0 == 0$.
- period** [float, optional] The assumed period of the sequence. Default is 2π .

Notes

If $\text{sum}(x, \text{axis}=0) = 0$ then $\text{diff}(\text{diff}(x, k), -k) == x$ (within numerical accuracy).

For odd order and even $\text{len}(x)$, the Nyquist mode is taken zero.

scipy.fftpack.tilbert

`scipy.fftpack.tilbert(x, h, period=None, _cache={})`

Return h-Tilbert transform of a periodic sequence x.

If x_j and y_j are Fourier coefficients of periodic functions x and y, respectively, then:

```
y_j = sqrt(-1)*coth(j*h*2*pi/period) * x_j
y_0 = 0
```

Parameters

- x** [array_like] The input array to transform.
- h** [float] Defines the parameter of the Tilbert transform.
- period** [float, optional] The assumed period of the sequence. Default period is 2π .

Returns

- tilbert** [ndarray] The result of the transform.

Notes

If $\text{sum}(x, \text{axis}=0) == 0$ and $n = \text{len}(x)$ is odd, then $\text{tilbert}(\text{itilbert}(x)) == x$.

If $2 * \pi * h / \text{period}$ is approximately 10 or larger, then numerically $\text{tilbert} == \text{hilbert}$ (theoretically oo-Tilbert == Hilbert).

For even $\text{len}(x)$, the Nyquist mode of x is taken zero.

scipy.fftpack.itilbert

`scipy.fftpack.itilbert(x, h, period=None, _cache={})`

Return inverse h-Tilbert transform of a periodic sequence x .

If x_j and y_j are Fourier coefficients of periodic functions x and y , respectively, then:

$$\begin{aligned} y_j &= -\sqrt{-1} * \tanh(j * h * 2 * \pi / \text{period}) * x_j \\ y_0 &= 0 \end{aligned}$$

For more details, see [tilbert](#).

scipy.fftpack.hilbert

`scipy.fftpack.hilbert(x, _cache={})`

Return Hilbert transform of a periodic sequence x .

If x_j and y_j are Fourier coefficients of periodic functions x and y , respectively, then:

$$\begin{aligned} y_j &= \sqrt{-1} * \text{sign}(j) * x_j \\ y_0 &= 0 \end{aligned}$$

Parameters

- x** [array_like] The input array, should be periodic.
- _cache** [dict, optional] Dictionary that contains the kernel used to do a convolution with.

Returns

- y** [ndarray] The transformed input.

See also:

[scipy.signal.hilbert](#)

Compute the analytic signal, using the Hilbert transform.

Notes

If `sum(x, axis=0) == 0` then `hilbert(ihilbert(x)) == x`.

For even `len(x)`, the Nyquist mode of `x` is taken zero.

The sign of the returned transform does not have a factor `-1` that is more often than not found in the definition of the Hilbert transform. Note also that `scipy.signal.hilbert` does have an extra `-1` factor compared to this function.

scipy.fftpack.ihilbert

`scipy.fftpack.ihilbert(x)`

Return inverse Hilbert transform of a periodic sequence `x`.

If `x_j` and `y_j` are Fourier coefficients of periodic functions `x` and `y`, respectively, then:

$$\begin{aligned} y_j &= -\sqrt{-1} * \text{sign}(j) * x_j \\ y_0 &= 0 \end{aligned}$$

scipy.fftpack.cs_diff

`scipy.fftpack.cs_diff(x, a, b, period=None, _cache={})`

Return (a,b)-cosh/sinh pseudo-derivative of a periodic sequence.

If `x_j` and `y_j` are Fourier coefficients of periodic functions `x` and `y`, respectively, then:

$$\begin{aligned} y_j &= -\sqrt{-1} * \cosh(j*a*2*\pi/\text{period}) / \sinh(j*b*2*\pi/\text{period}) * x_j \\ y_0 &= 0 \end{aligned}$$

Parameters

- x** [array_like] The array to take the pseudo-derivative from.
- a, b** [float] Defines the parameters of the cosh/sinh pseudo-differential operator.
- period** [float, optional] The period of the sequence. Default period is $2*\pi$.

Returns

- cs_diff** [ndarray] Pseudo-derivative of periodic sequence `x`.

Notes

For even `len(x)`, the Nyquist mode of `x` is taken as zero.

scipy.fftpack.sc_diff

`scipy.fftpack.sc_diff(x, a, b, period=None, _cache={})`

Return (a,b)-sinh/cosh pseudo-derivative of a periodic sequence `x`.

If `x_j` and `y_j` are Fourier coefficients of periodic functions `x` and `y`, respectively, then:

$$\begin{aligned} y_j &= \sqrt{-1} * \sinh(j*a*2*\pi/\text{period}) / \cosh(j*b*2*\pi/\text{period}) * x_j \\ y_0 &= 0 \end{aligned}$$

Parameters

x [array_like] Input array.
a,b [float] Defines the parameters of the sinh/cosh pseudo-differential operator.
period [float, optional] The period of the sequence x. Default is 2*pi.

Notes

`sc_diff(cs_diff(x, a, b), b, a) == x` For even `len(x)`, the Nyquist mode of x is taken as zero.

scipy.fftpack.ss_diff

`scipy.fftpack.ss_diff(x, a, b, period=None, _cache={})`

Return (a,b)-sinh/sinh pseudo-derivative of a periodic sequence x.

If `x_j` and `y_j` are Fourier coefficients of periodic functions x and y, respectively, then:

$$y_j = \sinh(j*a*2*pi/period) / \sinh(j*b*2*pi/period) * x_j$$

$$y_0 = a/b * x_0$$

Parameters

x [array_like] The array to take the pseudo-derivative from.
a,b Defines the parameters of the sinh/sinh pseudo-differential operator.
period [float, optional] The period of the sequence x. Default is 2*pi.

Notes

`ss_diff(ss_diff(x, a, b), b, a) == x`

scipy.fftpack.cc_diff

`scipy.fftpack.cc_diff(x, a, b, period=None, _cache={})`

Return (a,b)-cosh/cosh pseudo-derivative of a periodic sequence.

If `x_j` and `y_j` are Fourier coefficients of periodic functions x and y, respectively, then:

$$y_j = \cosh(j*a*2*pi/period) / \cosh(j*b*2*pi/period) * x_j$$

Parameters

x [array_like] The array to take the pseudo-derivative from.
a,b [float] Defines the parameters of the sinh/sinh pseudo-differential operator.
period [float, optional] The period of the sequence x. Default is 2*pi.

Returns

cc_diff [ndarray] Pseudo-derivative of periodic sequence x.

Notes

```
cc_diff(cc_diff(x, a, b), b, a) == x
```

scipy.fftpack.shift

```
scipy.fftpack.shift(x, a, period=None, _cache={})
```

Shift periodic sequence x by a : $y(u) = x(u+a)$.

If x_j and y_j are Fourier coefficients of periodic functions x and y , respectively, then:

$$y_j = \exp(j*a*2*pi/period*sqrt(-1)) * x_j$$

Parameters

- x** [array_like] The array to take the pseudo-derivative from.
- a** [float] Defines the parameters of the sinh/sinh pseudo-differential
- period** [float, optional] The period of the sequences x and y . Default period is $2*pi$.

6.6.3 Helper functions

<code>fftshift(x[, axes])</code>	Shift the zero-frequency component to the center of the spectrum.
<code>ifftshift(x[, axes])</code>	The inverse of <code>fftshift</code> .
<code>fftfreq(n[, d])</code>	Return the Discrete Fourier Transform sample frequencies.
<code>rfftfreq(n[, d])</code>	DFT sample frequencies (for usage with <code>rfft</code> , <code>irfft</code>).
<code>next_fast_len(target)</code>	Find the next fast size of input data to <code>fft</code> , for zero-padding, etc.

scipy.fftpack.fftshift

```
scipy.fftpack.fftshift(x, axes=None)
```

Shift the zero-frequency component to the center of the spectrum.

This function swaps half-spaces for all axes listed (defaults to all). Note that $y[0]$ is the Nyquist component only if $\text{len}(x)$ is even.

Parameters

- x** [array_like] Input array.
- axes** [int or shape tuple, optional] Axes over which to shift. Default is `None`, which shifts all axes.

Returns

- y** [ndarray] The shifted array.

See also:

`ifftshift`

The inverse of `fftshift`.

Examples

```
>>> freqs = np.fft.fftfreq(10, 0.1)
>>> freqs
array([ 0.,  1.,  2., ..., -3., -2., -1.])
>>> np.fft.fftshift(freqs)
array([-5., -4., -3., -2., -1.,  0.,  1.,  2.,  3.,  4.])
```

Shift the zero-frequency component only along the second axis:

```
>>> freqs = np.fft.fftfreq(9, d=1./9).reshape(3, 3)
>>> freqs
array([[ 0.,  1.,  2.],
       [ 3.,  4., -4.],
       [-3., -2., -1.]])
>>> np.fft.fftshift(freqs, axes=(1,))
array([[ 2.,  0.,  1.],
       [-4.,  3.,  4.],
       [-1., -3., -2.]])
```

scipy.fftpack.ifftshift

`scipy.fftpack.ifftshift(x, axes=None)`

The inverse of `fftshift`. Although identical for even-length x , the functions differ by one sample for odd-length x .

Parameters

x [array_like] Input array.
axes [int or shape tuple, optional] Axes over which to calculate. Defaults to None, which shifts all axes.

Returns

y [ndarray] The shifted array.

See also:

`fftshift`

Shift zero-frequency component to the center of the spectrum.

Examples

```
>>> freqs = np.fft.fftfreq(9, d=1./9).reshape(3, 3)
>>> freqs
array([[ 0.,  1.,  2.],
       [ 3.,  4., -4.],
       [-3., -2., -1.]])
>>> np.fft.ifftshift(np.fft.fftshift(freqs))
array([[ 0.,  1.,  2.],
       [ 3.,  4., -4.],
       [-3., -2., -1.]])
```

scipy.fftpack.fftfreq`scipy.fftpack.fftfreq(n, d=1.0)`

Return the Discrete Fourier Transform sample frequencies.

The returned float array f contains the frequency bin centers in cycles per unit of the sample spacing (with zero at the start). For instance, if the sample spacing is in seconds, then the frequency unit is cycles/second.

Given a window length n and a sample spacing d :

```
f = [0, 1, ..., n/2-1, -n/2, ..., -1] / (d*n)   if n is even
f = [0, 1, ..., (n-1)/2, -(n-1)/2, ..., -1] / (d*n)   if n is odd
```

Parameters

n [int] Window length.
d [scalar, optional] Sample spacing (inverse of the sampling rate). Defaults to 1.

Returns

f [ndarray] Array of length n containing the sample frequencies.

Examples

```
>>> signal = np.array([-2, 8, 6, 4, 1, 0, 3, 5], dtype=float)
>>> fourier = np.fft.fft(signal)
>>> n = signal.size
>>> timestep = 0.1
>>> freq = np.fft.fftfreq(n, d=timestep)
>>> freq
array([ 0. ,  1.25,  2.5 , ..., -3.75, -2.5 , -1.25])
```

scipy.fftpack.rfftfreq`scipy.fftpack.rfftfreq(n, d=1.0)`

DFT sample frequencies (for usage with rfft, irfft).

The returned float array contains the frequency bins in cycles/unit (with zero at the start) given a window length n and a sample spacing d :

```
f = [0, 1, 1, 2, 2, ..., n/2-1, n/2-1, n/2] / (d*n)   if n is even
f = [0, 1, 1, 2, 2, ..., n/2-1, n/2-1, n/2, n/2] / (d*n)   if n is odd
```

Parameters

n [int] Window length.
d [scalar, optional] Sample spacing. Default is 1.

Returns

out [ndarray] The array of length n , containing the sample frequencies.

Examples

```
>>> from scipy import fftpack
>>> sig = np.array([-2, 8, 6, 4, 1, 0, 3, 5], dtype=float)
>>> sig_fft = fftpack.rffft(sig)
>>> n = sig_fft.size
>>> timestep = 0.1
>>> freq = fftpack.rfftfreq(n, d=timestep)
>>> freq
array([ 0.   ,  1.25,  1.25,  2.5  ,  2.5  ,  3.75,  3.75,  5.   ])
```

scipy.fftpack.next_fast_len

`scipy.fftpack.next_fast_len(target)`

Find the next fast size of input data to *fft*, for zero-padding, etc.

SciPy's FFTPACK has efficient functions for radix {2, 3, 4, 5}, so this returns the next composite of the prime factors 2, 3, and 5 which is greater than or equal to *target*. (These are also known as 5-smooth numbers, regular numbers, or Hamming numbers.)

Parameters

target [int] Length to start searching from. Must be a positive integer.

Returns

out [int] The first 5-smooth number greater than or equal to *target*.

Notes

New in version 0.18.0.

Examples

On a particular machine, an FFT of prime length takes 133 ms:

```
>>> from scipy import fftpack
>>> min_len = 10007 # prime length is worst case for speed
>>> a = np.random.randn(min_len)
>>> b = fftpack.fft(a)
```

Zero-padding to the next 5-smooth length reduces computation time to 211 us, a speedup of 630 times:

```
>>> fftpack.helper.next_fast_len(min_len)
10125
>>> b = fftpack.fft(a, 10125)
```

Rounding up to the next power of 2 is not optimal, taking 367 us to compute, 1.7 times as long as the 5-smooth size:

```
>>> b = fftpack.fft(a, 16384)
```

Note that `fftshift`, `ifftshift` and `fftfreq` are numpy functions exposed by `fftpack`; importing them from `numpy` should be preferred.

6.6.4 Convolutions (`scipy.fftpack.convolve`)

<code>convolve(x,omega,[swap_real_imag,overwrite_x])</code>	Wrapper for <code>convolve</code> .
<code>convolve_z(x,omega_real,omega_imag,[overwrite_x])</code>	Wrapper for <code>convolve_z</code> .
<code>init_convolution_kernel(...)</code>	Wrapper for <code>init_convolution_kernel</code> .
<code>destroy_convolve_cache()</code>	

`scipy.fftpack.convolve.convolve`

`scipy.fftpack.convolve.convolve(x, omega[, swap_real_imag, overwrite_x])`
 Wrapper for `convolve`.

Parameters

x [input rank-1 array('d') with bounds (n)]
omega [input rank-1 array('d') with bounds (n)]

Returns

y [rank-1 array('d') with bounds (n) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
swap_real_imag [input int, optional] Default: 0

`scipy.fftpack.convolve.convolve_z`

`scipy.fftpack.convolve.convolve_z(x, omega_real, omega_imag[, overwrite_x])`
 Wrapper for `convolve_z`.

Parameters

x [input rank-1 array('d') with bounds (n)]
omega_real [input rank-1 array('d') with bounds (n)]
omega_imag [input rank-1 array('d') with bounds (n)]

Returns

y [rank-1 array('d') with bounds (n) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0

scipy.fftpack.convolve.init_convolution_kernel

`scipy.fftpack.convolve.init_convolution_kernel` (*n*, *kernel_func*[, *d*, *zero_nyquist*, *kernel_func_extra_args*])

Wrapper for `init_convolution_kernel`.

Parameters

n [input int]
kernel_func [call-back function]

Returns

omega [rank-1 array('d') with bounds (n)]

Other Parameters

d [input int, optional] Default: 0
kernel_func_extra_args [input tuple, optional] Default: ()
zero_nyquist [input int, optional] Default: `d%2`

Notes

Call-back functions:

```
def kernel_func(k): return kernel_func
Required arguments:
  k : input int
Return objects:
  kernel_func : float
```

scipy.fftpack.convolve.destroy_convolve_cache

`scipy.fftpack.convolve.destroy_convolve_cache` ()

6.7 Integration and ODEs (`scipy.integrate`)

6.7.1 Integrating functions, given function object

<code>quad</code> (func, a, b[, args, full_output, ...])	Compute a definite integral.
<code>quad_vec</code> (f, a, b[, epsabs, epsrel, norm, ...])	Adaptive integration of a vector-valued function.
<code>dblquad</code> (func, a, b, gfun, hfun[, args, ...])	Compute a double integral.
<code>tplquad</code> (func, a, b, gfun, hfun, qfun, rfun)	Compute a triple (definite) integral.
<code>nquad</code> (func, ranges[, args, opts, full_output])	Integration over multiple variables.
<code>fixed_quad</code> (func, a, b[, args, n])	Compute a definite integral using fixed-order Gaussian quadrature.
<code>quadrature</code> (func, a, b[, args, tol, rtol, ...])	Compute a definite integral using fixed-tolerance Gaussian quadrature.

continues on next page

Table 24 – continued from previous page

<code>romberg(function, a, b[, args, tol, rtol, ...])</code>	Romberg integration of a callable function or method.
<code>quad_explain([output])</code>	Print extra information about <code>integrate.quad()</code> parameters and returns.
<code>newton_cotes(m[, equal])</code>	Return weights and error coefficient for Newton-Cotes integration.
<code>IntegrationWarning</code>	Warning on issues during integration.
<code>AccuracyWarning</code>	

scipy.integrate.quad

`scipy.integrate.quad` (*func*, *a*, *b*, *args*=(), *full_output*=0, *epsabs*=1.49e-08, *epsrel*=1.49e-08, *limit*=50, *points*=None, *weight*=None, *wvar*=None, *wopts*=None, *maxpl*=50, *limlst*=50)
 Compute a definite integral.

Integrate *func* from *a* to *b* (possibly infinite interval) using a technique from the Fortran library QUADPACK.

Parameters

func [[function, `scipy.LowLevelCallable`]] A Python function or method to integrate. If *func* takes many arguments, it is integrated along the axis corresponding to the first argument. If the user desires improved integration performance, then *f* may be a `scipy.LowLevelCallable` with one of the signatures:

```
double func(double x)
double func(double x, void *user_data)
double func(int n, double *xx)
double func(int n, double *xx, void *user_data)
```

The *user_data* is the data contained in the `scipy.LowLevelCallable`. In the call forms with *xx*, *n* is the length of the *xx* array which contains `xx[0] == x` and the rest of the items are numbers contained in the *args* argument of `quad`.

In addition, certain ctypes call signatures are supported for backward compatibility, but those should not be used in new code.

a [float] Lower limit of integration (use `-numpy.inf` for -infinity).

b [float] Upper limit of integration (use `numpy.inf` for +infinity).

args [tuple, optional] Extra arguments to pass to *func*.

full_output [int, optional] Non-zero to return a dictionary of integration information. If non-zero, warning messages are also suppressed and the message is appended to the output tuple.

Returns

y [float] The integral of *func* from *a* to *b*.

abserr [float] An estimate of the absolute error in the result.

infodict [dict] A dictionary containing additional information. Run `scipy.integrate.quad_explain()` for more information.

message A convergence message.

explain Appended only with 'cos' or 'sin' weighting and infinite integration limits, it contains an explanation of the codes in `infodict['ierlst']`

Other Parameters

epsabs [float or int, optional] Absolute error tolerance. Default is 1.49e-8. *quad* tries to obtain an accuracy of `abs(i-result) <= max(epsabs, epsrel*abs(i))` where *i* = integral of *func* from *a* to *b*, and *result* is the numerical approximation. See *epsrel* below.

epsrel	[float or int, optional] Relative error tolerance. Default is 1.49e-8. If <code>epsabs <= 0</code> , <code>epsrel</code> must be greater than both <code>5e-29</code> and <code>50 * (machine epsilon)</code> . See <code>epsabs</code> above.
limit	[float or int, optional] An upper bound on the number of subintervals used in the adaptive algorithm.
points	[(sequence of floats,ints), optional] A sequence of break points in the bounded integration interval where local difficulties of the integrand may occur (e.g., singularities, discontinuities). The sequence does not have to be sorted. Note that this option cannot be used in conjunction with <code>weight</code> .
weight	[float or int, optional] String indicating weighting function. Full explanation for this and the remaining arguments can be found below.
wvar	[optional] Variables for use with weighting functions.
wopts	[optional] Optional input for reusing Chebyshev moments.
maxp1	[float or int, optional] An upper bound on the number of Chebyshev moments.
limlst	[int, optional] Upper bound on the number of cycles (≥ 3) for use with a sinusoidal weighting and an infinite end-point.

See also:

dblquad

double integral

tplquad

triple integral

nquad

n-dimensional integrals (uses *quad* recursively)

fixed_quad

fixed-order Gaussian quadrature

quadrature

adaptive Gaussian quadrature

odeint

ODE integrator

ode

ODE integrator

simpson

integrator for sampled data

romb

integrator for sampled data

scipy.special

for coefficients and roots of orthogonal polynomials

Notes

Extra information for `quad()` inputs and outputs

If `full_output` is non-zero, then the third output argument (`infodict`) is a dictionary with entries as tabulated below. For infinite limits, the range is transformed to (0,1) and the optional outputs are given with respect to this transformed range. Let `M` be the input argument `limit` and let `K` be `infodict['last']`. The entries are:

'neval'

The number of function evaluations.

'last'

The number, `K`, of subintervals produced in the subdivision process.

'alist'

A rank-1 array of length `M`, the first `K` elements of which are the left end points of the subintervals in the partition of the integration range.

'blist'

A rank-1 array of length `M`, the first `K` elements of which are the right end points of the subintervals.

'rlist'

A rank-1 array of length `M`, the first `K` elements of which are the integral approximations on the subintervals.

'elist'

A rank-1 array of length `M`, the first `K` elements of which are the moduli of the absolute error estimates on the subintervals.

'iord'

A rank-1 integer array of length `M`, the first `L` elements of which are pointers to the error estimates over the subintervals with $L=K$ if $K \leq M/2+2$ or $L=M+1-K$ otherwise. Let `I` be the sequence `infodict['iord']` and let `E` be the sequence `infodict['elist']`. Then `E[I[1]], ..., E[I[L]]` forms a decreasing sequence.

If the input argument `points` is provided (i.e., it is not `None`), the following additional outputs are placed in the output dictionary. Assume the `points` sequence is of length `P`.

'pts'

A rank-1 array of length `P+2` containing the integration limits and the break points of the intervals in ascending order. This is an array giving the subintervals over which integration will occur.

'level'

A rank-1 integer array of length `M` ($=\text{limit}$), containing the subdivision levels of the subintervals, i.e., if `(aa,bb)` is a subinterval of `(pts[1], pts[2])` where `pts[0]` and `pts[2]` are adjacent elements of `infodict['pts']`, then `(aa,bb)` has level `l` if $|bb-aa| = |pts[2]-pts[1]| * 2^{**(-l)}$.

'ndin'

A rank-1 integer array of length `P+2`. After the first integration over the intervals `(pts[1], pts[2])`, the error estimates over some of the intervals may have been increased artificially in order to put their subdivision forward. This array has ones in slots corresponding to the subintervals for which this happens.

Weighting the integrand

The input variables, `weight` and `wvar`, are used to weight the integrand by a select list of functions. Different integration methods are used to compute the integral with these weighting functions, and these do not support specifying break points. The possible values of `weight` and the corresponding weighting functions are.

weight	Weight function used	wvar
'cos'	$\cos(w*x)$	wvar = w
'sin'	$\sin(w*x)$	wvar = w
'alg'	$g(x) = ((x-a)**\alpha)*((b-x)**\beta)$	wvar = (alpha, beta)
'alg-loga'	$g(x)*\log(x-a)$	wvar = (alpha, beta)
'alg-logb'	$g(x)*\log(b-x)$	wvar = (alpha, beta)
'alg-log'	$g(x)*\log(x-a)*\log(b-x)$	wvar = (alpha, beta)
'cauchy'	$1/(x-c)$	wvar = c

wvar holds the parameter w, (alpha, beta), or c depending on the weight selected. In these expressions, a and b are the integration limits.

For the 'cos' and 'sin' weighting, additional inputs and outputs are available.

For finite integration limits, the integration is performed using a Clenshaw-Curtis method which uses Chebyshev moments. For repeated calculations, these moments are saved in the output dictionary:

'momcom'

The maximum level of Chebyshev moments that have been computed, i.e., if `M_c` is `infodict['momcom']` then the moments have been computed for intervals of length $|b-a| * 2^{**(-l)}$, $l=0, 1, \dots, M_c$.

'nnlog'

A rank-1 integer array of length `M(=limit)`, containing the subdivision levels of the subintervals, i.e., an element of this array is equal to `l` if the corresponding subinterval is $|b-a| * 2^{**(-l)}$.

'chebmo'

A rank-2 array of shape `(25, maxp1)` containing the computed Chebyshev moments. These can be passed on to an integration over the same interval by passing this array as the second element of the sequence `wopst` and passing `infodict['momcom']` as the first element.

If one of the integration limits is infinite, then a Fourier integral is computed (assuming $w \neq 0$). If `full_output` is 1 and a numerical error is encountered, besides the error message attached to the output tuple, a dictionary is also appended to the output tuple which translates the error codes in the array `info['ierlst']` to English messages. The output information dictionary contains the following entries instead of 'last', 'alist', 'blist', 'rlist', and 'elist':

'lst'

The number of subintervals needed for the integration (call it `K_f`).

'rslst'

A rank-1 array of length `M_f=limlst`, whose first `K_f` elements contain the integral contribution over the interval $(a+(k-1)c, a+kc)$ where $c = (2*\text{floor}(|w|) + 1) * \text{pi} / |w|$ and $k=1, 2, \dots, K_f$.

'erlst'

A rank-1 array of length `M_f` containing the error estimate corresponding to the interval in the same position in `infodict['rslst']`.

'ierlst'

A rank-1 integer array of length `M_f` containing an error flag corresponding to the interval in the same position in `infodict['rslst']`. See the explanation dictionary (last entry in the output tuple) for the meaning of the codes.

Examples

Calculate $\int_0^4 x^2 dx$ and compare with an analytic result

```
>>> from scipy import integrate
>>> x2 = lambda x: x**2
>>> integrate.quad(x2, 0, 4)
(21.333333333333332, 2.3684757858670003e-13)
>>> print(4**3 / 3.) # analytical result
21.3333333333
```

Calculate $\int_0^\infty e^{-x} dx$

```
>>> invexp = lambda x: np.exp(-x)
>>> integrate.quad(invexp, 0, np.inf)
(1.0, 5.842605999138044e-11)
```

```
>>> f = lambda x,a : a*x
>>> y, err = integrate.quad(f, 0, 1, args=(1,))
>>> y
0.5
>>> y, err = integrate.quad(f, 0, 1, args=(3,))
>>> y
1.5
```

Calculate $\int_0^1 x^2 + y^2 dx$ with ctypes, holding y parameter as 1:

```
testlib.c =>
    double func(int n, double args[n]){
        return args[0]*args[0] + args[1]*args[1];}
compile to library testlib.*
```

```
from scipy import integrate
import ctypes
lib = ctypes.CDLL('/home/.../testlib.*') #use absolute path
lib.func.restype = ctypes.c_double
lib.func.argtypes = (ctypes.c_int,ctypes.c_double)
integrate.quad(lib.func,0,1, (1))
#(1.3333333333333333, 1.4802973661668752e-14)
print((1.0**3/3.0 + 1.0) - (0.0**3/3.0 + 0.0)) #Analytic result
# 1.3333333333333333
```

Be aware that pulse shapes and other sharp features as compared to the size of the integration interval may not be integrated correctly using this method. A simplified example of this limitation is integrating a y-axis reflected step function with many zero values within the integrals bounds.

```
>>> y = lambda x: 1 if x<=0 else 0
>>> integrate.quad(y, -1, 1)
(1.0, 1.1102230246251565e-14)
>>> integrate.quad(y, -1, 100)
(1.0000000002199108, 1.0189464580163188e-08)
>>> integrate.quad(y, -1, 10000)
(0.0, 0.0)
```

scipy.integrate.quad_vec

```
scipy.integrate.quad_vec(f, a, b, epsabs=1e-200, epsrel=1e-08, norm='2', cache_size=100000000.0,
                        limit=10000, workers=1, points=None, quadrature=None,
                        full_output=False)
```

Adaptive integration of a vector-valued function.

Parameters

f	[callable] Vector-valued function $f(x)$ to integrate.
a	[float] Initial point.
b	[float] Final point.
epsabs	[float, optional] Absolute tolerance.
epsrel	[float, optional] Relative tolerance.
norm	[{'max', '2'}, optional] Vector norm to use for error estimation.
cache_size	[int, optional] Number of bytes to use for memoization.
workers	[int or map-like callable, optional] If <i>workers</i> is an integer, part of the computation is done in parallel subdivided to this many tasks (using <code>multiprocessing.pool.Pool</code>). Supply <code>-1</code> to use all cores available to the Process. Alternatively, supply a map-like callable, such as <code>multiprocessing.pool.Pool.map</code> for evaluating the population in parallel. This evaluation is carried out as <code>workers(func, iterable)</code> .
points	[list, optional] List of additional breakpoints.
quadrature	[{'gk21', 'gk15', 'trapezoid'}, optional] Quadrature rule to use on subintervals. Options: 'gk21' (Gauss-Kronrod 21-point rule), 'gk15' (Gauss-Kronrod 15-point rule), 'trapezoid' (composite trapezoid rule). Default: 'gk21' for finite intervals and 'gk15' for (semi-)infinite intervals.
full_output	[bool, optional] Return an additional <code>info</code> dictionary.

Returns

res	[{float, array-like}] Estimate for the result												
err	[float] Error estimate for the result in the given norm												
info	[dict] Returned only when <code>full_output=True</code> . Info dictionary. Is an object with the attributes: <table> <tr> <td>success</td> <td>[bool] Whether integration reached target precision.</td> </tr> <tr> <td>status</td> <td>[int] Indicator for convergence, success (0), failure (1), and failure due to rounding error (2).</td> </tr> <tr> <td>neval</td> <td>[int] Number of function evaluations.</td> </tr> <tr> <td>intervals</td> <td>[ndarray, shape (num_intervals, 2)] Start and end points of subdivision intervals.</td> </tr> <tr> <td>integrals</td> <td>[ndarray, shape (num_intervals, ...)] Integral for each interval. Note that at most <code>cache_size</code> values are recorded, and the array may contain <i>nan</i> for missing items.</td> </tr> <tr> <td>errors</td> <td>[ndarray, shape (num_intervals,)] Estimated integration error for each interval.</td> </tr> </table>	success	[bool] Whether integration reached target precision.	status	[int] Indicator for convergence, success (0), failure (1), and failure due to rounding error (2).	neval	[int] Number of function evaluations.	intervals	[ndarray, shape (num_intervals, 2)] Start and end points of subdivision intervals.	integrals	[ndarray, shape (num_intervals, ...)] Integral for each interval. Note that at most <code>cache_size</code> values are recorded, and the array may contain <i>nan</i> for missing items.	errors	[ndarray, shape (num_intervals,)] Estimated integration error for each interval.
success	[bool] Whether integration reached target precision.												
status	[int] Indicator for convergence, success (0), failure (1), and failure due to rounding error (2).												
neval	[int] Number of function evaluations.												
intervals	[ndarray, shape (num_intervals, 2)] Start and end points of subdivision intervals.												
integrals	[ndarray, shape (num_intervals, ...)] Integral for each interval. Note that at most <code>cache_size</code> values are recorded, and the array may contain <i>nan</i> for missing items.												
errors	[ndarray, shape (num_intervals,)] Estimated integration error for each interval.												

Notes

The algorithm mainly follows the implementation of QUADPACK's DQAG* algorithms, implementing global error control and adaptive subdivision.

The algorithm here has some differences to the QUADPACK approach:

Instead of subdividing one interval at a time, the algorithm subdivides N intervals with largest errors at once. This enables (partial) parallelization of the integration.

The logic of subdividing “next largest” intervals first is then not implemented, and we rely on the above extension to avoid concentrating on “small” intervals only.

The Wynn epsilon table extrapolation is not used (QUADPACK uses it for infinite intervals). This is because the algorithm here is supposed to work on vector-valued functions, in an user-specified norm, and the extension of the epsilon algorithm to this case does not appear to be widely agreed. For max-norm, using elementwise Wynn epsilon could be possible, but we do not do this here with the hope that the epsilon extrapolation is mainly useful in special cases.

References

[1] R. Piessens, E. de Doncker, QUADPACK (1983).

Examples

We can compute integrations of a vector-valued function:

```
>>> from scipy.integrate import quad_vec
>>> import matplotlib.pyplot as plt
>>> alpha = np.linspace(0.0, 2.0, num=30)
>>> f = lambda x: x**alpha
>>> x0, x1 = 0, 2
>>> y, err = quad_vec(f, x0, x1)
>>> plt.plot(alpha, y)
>>> plt.xlabel(r"$\alpha$")
>>> plt.ylabel(r"$\int_{0}^{2} x^{\alpha} dx$")
>>> plt.show()
```

scipy.integrate.dblquad


`scipy.integrate.dblquad` (*func*, *a*, *b*, *gfun*, *hfun*, *args=()*, *epsabs=1.49e-08*, *epsrel=1.49e-08*)

Compute a double integral.

Return the double (definite) integral of *func*(*y*, *x*) from *x* = *a*..*b* and *y* = *gfun*(*x*)..*hfun*(*x*).

Parameters

func	[callable] A Python function or method of at least two variables: <i>y</i> must be the first argument and <i>x</i> the second argument.
a, b	[float] The limits of integration in <i>x</i> : $a < b$
gfun	[callable or float] The lower boundary curve in <i>y</i> which is a function taking a single floating point argument (<i>x</i>) and returning a floating point result or a float indicating a constant boundary curve.
hfun	[callable or float] The upper boundary curve in <i>y</i> (same requirements as <i>gfun</i>).
args	[sequence, optional] Extra arguments to pass to <i>func</i> .



- epsabs** [float, optional] Absolute tolerance passed directly to the inner 1-D quadrature integration. Default is 1.49e-8. *dblquad* tries to obtain an accuracy of $\text{abs}(i\text{-result}) \leq \max(\text{epsabs}, \text{epsrel} * \text{abs}(i))$ where i = inner integral of $\text{func}(y, x)$ from $g\text{fun}(x)$ to $h\text{fun}(x)$, and result is the numerical approximation. See *epsrel* below.
- epsrel** [float, optional] Relative tolerance of the inner 1-D integrals. Default is 1.49e-8. If $\text{epsabs} \leq 0$, *epsrel* must be greater than both $5e-29$ and $50 * (\text{machine epsilon})$. See *epsabs* above.

Returns

- y** [float] The resultant integral.
- abserr** [float] An estimate of the error.

See also:

quad

single integral

tplquad

triple integral

nquad

N-dimensional integrals

fixed_quad

fixed-order Gaussian quadrature

quadrature

adaptive Gaussian quadrature

odeint

ODE integrator

ode

ODE integrator

simpson

integrator for sampled data

romb

integrator for sampled data

scipy.special

for coefficients and roots of orthogonal polynomials

Examples

Compute the double integral of $x * y^{**2}$ over the box x ranging from 0 to 2 and y ranging from 0 to 1.

```
>>> from scipy import integrate
>>> f = lambda y, x: x*y**2
>>> integrate.dblquad(f, 0, 2, lambda x: 0, lambda x: 1)
(0.6666666666666667, 7.401486830834377e-15)
```

scipy.integrate.tplquad

`scipy.integrate.tplquad` (*func*, *a*, *b*, *gfun*, *hfun*, *qfun*, *rfunc*, *args=()*, *epsabs=1.49e-08*, *epsrel=1.49e-08*)

Compute a triple (definite) integral.

Return the triple integral of `func(z, y, x)` from `x = a..b`, `y = gfun(x)..hfun(x)`, and `z = qfun(x, y)..rfunc(x, y)`.

Parameters

func	[function] A Python function or method of at least three variables in the order (z, y, x).
a, b	[float] The limits of integration in x: $a < b$
gfun	[function or float] The lower boundary curve in y which is a function taking a single floating point argument (x) and returning a floating point result or a float indicating a constant boundary curve.
hfun	[function or float] The upper boundary curve in y (same requirements as <i>gfun</i>).
qfun	[function or float] The lower boundary surface in z. It must be a function that takes two floats in the order (x, y) and returns a float or a float indicating a constant boundary surface.
rfunc	[function or float] The upper boundary surface in z. (Same requirements as <i>qfun</i> .)
args	[tuple, optional] Extra arguments to pass to <i>func</i> .
epsabs	[float, optional] Absolute tolerance passed directly to the innermost 1-D quadrature integration. Default is 1.49e-8.
epsrel	[float, optional] Relative tolerance of the innermost 1-D integrals. Default is 1.49e-8.

Returns

y	[float] The resultant integral.
abserr	[float] An estimate of the error.

See also:

quad

Adaptive quadrature using QUADPACK

quadrature

Adaptive Gaussian quadrature

fixed_quad

Fixed-order Gaussian quadrature

dblquad

Double integrals

nquad

N-dimensional integrals

romb

Integrators for sampled data

simpson

Integrators for sampled data

ode

ODE integrators

odeint

ODE integrators

scipy.special

For coefficients and roots of orthogonal polynomials

Examples

Compute the triple integral of $x * y * z$, over x ranging from 1 to 2, y ranging from 2 to 3, z ranging from 0 to 1.

```
>>> from scipy import integrate
>>> f = lambda z, y, x: x*y*z
>>> integrate.tplquad(f, 1, 2, lambda x: 2, lambda x: 3,
...                  lambda x, y: 0, lambda x, y: 1)
(1.8750000000000002, 3.324644794257407e-14)
```

scipy.integrate.nquad

`scipy.integrate.nquad` (*func*, *ranges*, *args=None*, *opts=None*, *full_output=False*)

Integration over multiple variables.

Wraps *quad* to enable integration over multiple variables. Various options allow improved integration of discontinuous functions, as well as the use of weighted integration, and generally finer control of the integration process.

Parameters

func [{callable, `scipy.LowLevelCallable`}] The function to be integrated. Has arguments of $x_0, \dots, x_n, t_0, \dots, t_m$, where integration is carried out over x_0, \dots, x_n , which must be floats. Where t_0, \dots, t_m are extra arguments passed in *args*. Function signature should be `func(x0, x1, ..., xn, t0, t1, ..., tm)`. Integration is carried out in order. That is, integration over x_0 is the innermost integral, and x_n is the outermost.

If the user desires improved integration performance, then f may be a `scipy.LowLevelCallable` with one of the signatures:

```
double func(int n, double *xx)
double func(int n, double *xx, void *user_data)
```

where n is the number of variables and args. The `xx` array contains the coordinates and extra arguments. `user_data` is the data contained in the `scipy.LowLevelCallable`.

ranges [iterable object] Each element of `ranges` may be either a sequence of 2 numbers, or else a callable that returns such a sequence. `ranges[0]` corresponds to integration over x_0 , and so on. If an element of `ranges` is a callable, then it will be called with all of the integration arguments available, as well as any parametric arguments. e.g., if `func = f(x0, x1, x2, t0, t1)`, then `ranges[0]` may be defined as either `(a, b)` or else as `(a, b) = range0(x1, x2, t0, t1)`.

args [iterable object, optional] Additional arguments t_0, \dots, t_n , required by `func`, `ranges`, and `opts`.

opts [iterable object or dict, optional] Options to be passed to `quad`. May be empty, a dict, or a sequence of dicts or functions that return a dict. If empty, the default options from `scipy.integrate.quad` are used. If a dict, the same options are used for all levels of integration. If a sequence, then each element of the sequence corresponds to a particular integration. e.g., `opts[0]` corresponds to integration over x_0 , and so on. If a callable, the signature must be the same as for `ranges`. The available options together with their default values are:

- `epsabs = 1.49e-08`
- `epsrel = 1.49e-08`
- `limit = 50`
- `points = None`
- `weight = None`
- `wvar = None`
- `wopts = None`

For more information on these options, see `quad` and `quad_explain`.

full_output [bool, optional] Partial implementation of `full_output` from `scipy.integrate.quad`. The number of integrand function evaluations `neval` can be obtained by setting `full_output=True` when calling `nquad`.

Returns

result [float] The result of the integration.
abserr [float] The maximum of the estimates of the absolute error in the various integration results.
out_dict [dict, optional] A dict containing additional information on the integration.

See also:

`quad`

1-D numerical integration

`dblquad`, `tplquad`

double and triple integrals

`fixed_quad`

fixed-order Gaussian quadrature

`quadrature`

adaptive Gaussian quadrature

Examples

```

>>> from scipy import integrate
>>> func = lambda x0,x1,x2,x3 : x0**2 + x1*x2 - x3**3 + np.sin(x0) + (
...     1 if (x0-.2*x3-.5-.25*x1>0) else 0)
>>> def opts0(*args, **kwargs):
...     return {'points':[0.2*args[2] + 0.5 + 0.25*args[0]]}
>>> integrate.nquad(func, [[0,1], [-1,1], [.13,.8], [-.15,1]],
...                 opts=[opts0,{}, {}, {}], full_output=True)
(1.5267454070738633, 2.9437360001402324e-14, {'neval': 388962})

```

```

>>> scale = .1
>>> def func2(x0, x1, x2, x3, t0, t1):
...     return x0*x1*x3**2 + np.sin(x2) + 1 + (1 if x0+t1*x1-t0>0 else 0)
>>> def lim0(x1, x2, x3, t0, t1):
...     return [scale * (x1**2 + x2 + np.cos(x3)*t0*t1 + 1) - 1,
...             scale * (x1**2 + x2 + np.cos(x3)*t0*t1 + 1) + 1]
>>> def lim1(x2, x3, t0, t1):
...     return [scale * (t0*x2 + t1*x3) - 1,
...             scale * (t0*x2 + t1*x3) + 1]
>>> def lim2(x3, t0, t1):
...     return [scale * (x3 + t0**2*t1**3) - 1,
...             scale * (x3 + t0**2*t1**3) + 1]
>>> def lim3(t0, t1):
...     return [scale * (t0+t1) - 1, scale * (t0+t1) + 1]
>>> def opts0(x1, x2, x3, t0, t1):
...     return {'points' : [t0 - t1*x1]}
>>> def opts1(x2, x3, t0, t1):
...     return {}
>>> def opts2(x3, t0, t1):
...     return {}
>>> def opts3(t0, t1):
...     return {}
>>> integrate.nquad(func2, [lim0, lim1, lim2, lim3], args=(0,0),
...                 opts=[opts0, opts1, opts2, opts3])
(25.066666666666666, 2.7829590483937256e-13)

```

scipy.integrate.fixed_quad

`scipy.integrate.fixed_quad` (*func*, *a*, *b*, *args=()*, *n=5*)

Compute a definite integral using fixed-order Gaussian quadrature.

Integrate *func* from *a* to *b* using Gaussian quadrature of order *n*.

Parameters

func	[callable] A Python function or method to integrate (must accept vector inputs). If integrating a vector-valued function, the returned array must have shape <code>(..., len(x))</code> .
a	[float] Lower limit of integration.
b	[float] Upper limit of integration.
args	[tuple, optional] Extra arguments to pass to function, if any.
n	[int, optional] Order of quadrature integration. Default is 5.

Returns

val [float] Gaussian quadrature approximation to the integral
none [None] Statically returned value of None

See also:*quad*

adaptive quadrature using QUADPACK

dblquad

double integrals

tplquad

triple integrals

romberg

adaptive Romberg quadrature

quadrature

adaptive Gaussian quadrature

romb

integrators for sampled data

simpson

integrators for sampled data

cumulative_trapezoid

cumulative integration for sampled data

ode

ODE integrator

odeint

ODE integrator

Examples

```
>>> from scipy import integrate
>>> f = lambda x: x**8
>>> integrate.fixed_quad(f, 0.0, 1.0, n=4)
(0.1110884353741496, None)
>>> integrate.fixed_quad(f, 0.0, 1.0, n=5)
(0.11111111111111102, None)
>>> print(1/9.0) # analytical result
0.1111111111111111
```

```
>>> integrate.fixed_quad(np.cos, 0.0, np.pi/2, n=4)
(0.9999999771971152, None)
>>> integrate.fixed_quad(np.cos, 0.0, np.pi/2, n=5)
(1.000000000039565, None)
>>> np.sin(np.pi/2)-np.sin(0) # analytical result
1.0
```

scipy.integrate.quadrature

`scipy.integrate.quadrature` (*func*, *a*, *b*, *args=()*, *tol=1.49e-08*, *rtol=1.49e-08*, *maxiter=50*,
vec_func=True, *miniter=1*)

Compute a definite integral using fixed-tolerance Gaussian quadrature.

Integrate *func* from *a* to *b* using Gaussian quadrature with absolute tolerance *tol*.

Parameters

func	[function] A Python function or method to integrate.
a	[float] Lower limit of integration.
b	[float] Upper limit of integration.
args	[tuple, optional] Extra arguments to pass to function.
tol, rtol	[float, optional] Iteration stops when error between last two iterates is less than <i>tol</i> OR the relative change is less than <i>rtol</i> .
maxiter	[int, optional] Maximum order of Gaussian quadrature.
vec_func	[bool, optional] True or False if <i>func</i> handles arrays as arguments (is a “vector” function). Default is True.
miniter	[int, optional] Minimum order of Gaussian quadrature.

Returns

val	[float] Gaussian quadrature approximation (within tolerance) to integral.
err	[float] Difference between last two estimates of the integral.

See also:

romberg

adaptive Romberg quadrature

fixed_quad

fixed-order Gaussian quadrature

quad

adaptive quadrature using QUADPACK

dblquad

double integrals

tplquad

triple integrals

romb

integrator for sampled data

simpson

integrator for sampled data

cumulative_trapezoid

cumulative integration for sampled data

ode

ODE integrator

`odeint`

ODE integrator

Examples

```
>>> from scipy import integrate
>>> f = lambda x: x**8
>>> integrate.quadrature(f, 0.0, 1.0)
(0.111111111111111106, 4.163336342344337e-17)
>>> print(1/9.0) # analytical result
0.1111111111111111
```

```
>>> integrate.quadrature(np.cos, 0.0, np.pi/2)
(0.9999999999999536, 3.9611425250996035e-11)
>>> np.sin(np.pi/2)-np.sin(0) # analytical result
1.0
```

`scipy.integrate.romberg`

`scipy.integrate.romberg`(*function*, *a*, *b*, *args*=(), *tol*=1.48e-08, *rtol*=1.48e-08, *show*=False, *divmax*=10, *vec_func*=False)

Romberg integration of a callable function or method.

Returns the integral of *function* (a function of one variable) over the interval (*a*, *b*).

If *show* is 1, the triangular array of the intermediate results will be printed. If *vec_func* is True (default is False), then *function* is assumed to support vector arguments.

Parameters

function [callable] Function to be integrated.
a [float] Lower limit of integration.
b [float] Upper limit of integration.

Returns

results [float] Result of the integration.

Other Parameters

args [tuple, optional] Extra arguments to pass to function. Each element of *args* will be passed as a single argument to *func*. Default is to pass no extra arguments.
tol, rtol [float, optional] The desired absolute and relative tolerances. Defaults are 1.48e-8.
show [bool, optional] Whether to print the results. Default is False.
divmax [int, optional] Maximum order of extrapolation. Default is 10.
vec_func [bool, optional] Whether *func* handles arrays as arguments (i.e., whether it is a “vector” function). Default is False.

See also:

`fixed_quad`

Fixed-order Gaussian quadrature.

`quad`

Adaptive quadrature using QUADPACK.

dblquad

Double integrals.

tplquad

Triple integrals.

romb

Integrators for sampled data.

simpson

Integrators for sampled data.

cumulative_trapezoid

Cumulative integration for sampled data.

ode

ODE integrator.

odeint

ODE integrator.

References

[1]

Examples

Integrate a gaussian from 0 to 1 and compare to the error function.

```
>>> from scipy import integrate
>>> from scipy.special import erf
>>> gaussian = lambda x: 1/np.sqrt(np.pi) * np.exp(-x**2)
>>> result = integrate.romberg(gaussian, 0, 1, show=True)
Romberg integration of <function vfunc at ...> from [0, 1]
```

```
Steps  StepSize  Results
  1    1.000000  0.385872
  2    0.500000  0.412631  0.421551
  4    0.250000  0.419184  0.421368  0.421356
  8    0.125000  0.420810  0.421352  0.421350  0.421350
 16    0.062500  0.421215  0.421350  0.421350  0.421350  0.421350
 32    0.031250  0.421317  0.421350  0.421350  0.421350  0.421350  0.
→421350
```

The final result is 0.421350396475 after 33 function evaluations.

```
>>> print("%g %g" % (2*result, erf(1)))
0.842701 0.842701
```

scipy.integrate.quad_explain

`scipy.integrate.quad_explain` (*output*=<_io.TextIOWrapper *name*='<stdout>' *mode*='w'
encoding='utf-8'>)

Print extra information about `integrate.quad()` parameters and returns.

Parameters

output [instance with “write” method, optional] Information about `quad` is passed to `output.write()`. Default is `sys.stdout`.

Returns

None

Examples

We can show detailed information of the `integrate.quad` function in `stdout`:

```
>>> from scipy.integrate import quad_explain
>>> quad_explain()
```

scipy.integrate.newton_cotes

`scipy.integrate.newton_cotes` (*rn*, *equal*=0)

Return weights and error coefficient for Newton-Cotes integration.

Suppose we have (N+1) samples of *f* at the positions x_0, x_1, \dots, x_N . Then an N-point Newton-Cotes formula for the integral between x_0 and x_N is:

$$\int_{x_0}^{x_N} f(x)dx = \Delta x \sum_{i=0}^N a_i f(x_i) + B_N(\Delta x)^{N+2} f^{N+1}(\xi)$$

where $\xi \in [x_0, x_N]$ and $\Delta x = \frac{x_N - x_0}{N}$ is the average samples spacing.

If the samples are equally-spaced and N is even, then the error term is $B_N(\Delta x)^{N+3} f^{N+2}(\xi)$.

Parameters

rn [int] The integer order for equally-spaced data or the relative positions of the samples with the first sample at 0 and the last at N, where N+1 is the length of *rn*. N is the order of the Newton-Cotes integration.

equal [int, optional] Set to 1 to enforce equally spaced data.

Returns

an [ndarray] 1-D array of weights to apply to the function at the provided sample positions.

B [float] Error coefficient.

Notes

Normally, the Newton-Cotes rules are used on smaller integration regions and a composite rule is used to return the total integral.

Examples

Compute the integral of $\sin(x)$ in $[0, \pi]$:

```
>>> from scipy.integrate import newton_cotes
>>> def f(x):
...     return np.sin(x)
>>> a = 0
>>> b = np.pi
>>> exact = 2
>>> for N in [2, 4, 6, 8, 10]:
...     x = np.linspace(a, b, N + 1)
...     an, B = newton_cotes(N, 1)
...     dx = (b - a) / N
...     quad = dx * np.sum(an * f(x))
...     error = abs(quad - exact)
...     print('{:2d}   {:10.9f}   {:.5e}'.format(N, quad, error))
...
2   2.094395102   9.43951e-02
4   1.998570732   1.42927e-03
6   2.000017814   1.78136e-05
8   1.999999835   1.64725e-07
10  2.000000001   1.14677e-09
```

scipy.integrate.IntegrationWarning

exception `scipy.integrate.IntegrationWarning`

Warning on issues during integration.

with_traceback()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

scipy.integrate.AccuracyWarning

exception `scipy.integrate.AccuracyWarning`

with_traceback()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

6.7.2 Integrating functions, given fixed samples

<code>trapezoid(y[, x, dx, axis])</code>	Integrate along the given axis using the composite trapezoidal rule.
<code>cumulative_trapezoid(y[, x, dx, axis, initial])</code>	Cumulatively integrate $y(x)$ using the composite trapezoidal rule.
<code>simpson(y[, x, dx, axis, even])</code>	Integrate $y(x)$ using samples along the given axis and the composite Simpson's rule.
<code>romb(y[, dx, axis, show])</code>	Romberg integration using samples of a function.

scipy.integrate.trapezoid

`scipy.integrate.trapezoid(y, x=None, dx=1.0, axis=-1)`

Integrate along the given axis using the composite trapezoidal rule.

Integrate $y(x)$ along given axis.

Parameters

y	[array_like] Input array to integrate.
x	[array_like, optional] The sample points corresponding to the y values. If x is None, the sample points are assumed to be evenly spaced dx apart. The default is None.
dx	[scalar, optional] The spacing between sample points when x is None. The default is 1.
axis	[int, optional] The axis along which to integrate.

Returns

trapz	[float] Definite integral as approximated by trapezoidal rule.
--------------	--

See also:

[`numpy.cumsum`](#)

Notes

Image [2] illustrates trapezoidal rule – y -axis locations of points will be taken from y array, by default x -axis distances between points will be 1.0, alternatively they can be provided with x array or with dx scalar. Return value will be equal to combined area under the red lines.

References

[1], [2]

Examples

```

>>> np.trapz([1,2,3])
4.0
>>> np.trapz([1,2,3], x=[4,6,8])
8.0
>>> np.trapz([1,2,3], dx=2)
8.0
>>> a = np.arange(6).reshape(2, 3)
>>> a
array([[0, 1, 2],
       [3, 4, 5]])
>>> np.trapz(a, axis=0)
array([1.5, 2.5, 3.5])
>>> np.trapz(a, axis=1)
array([2., 8.])

```

scipy.integrate.cumulative_trapezoid

`scipy.integrate.cumulative_trapezoid` (*y*, *x=None*, *dx=1.0*, *axis=-1*, *initial=None*)

Cumulatively integrate $y(x)$ using the composite trapezoidal rule.

Parameters

- y** [array_like] Values to integrate.
- x** [array_like, optional] The coordinate to integrate along. If *None* (default), use spacing *dx* between consecutive elements in *y*.
- dx** [float, optional] Spacing between elements of *y*. Only used if *x* is *None*.
- axis** [int, optional] Specifies the axis to cumulate. Default is -1 (last axis).
- initial** [scalar, optional] If given, insert this value at the beginning of the returned result. Typically this value should be 0. Default is *None*, which means no value at $x[0]$ is returned and *res* has one element less than *y* along the axis of integration.

Returns

- res** [ndarray] The result of cumulative integration of *y* along *axis*. If *initial* is *None*, the shape is such that the axis of integration has one less value than *y*. If *initial* is given, the shape is equal to that of *y*.

See also:

numpy.cumsum, *numpy.cumprod*

quad

adaptive quadrature using QUADPACK

romberg

adaptive Romberg quadrature

quadrature

adaptive Gaussian quadrature

fixed_quad

fixed-order Gaussian quadrature

dblquad

double integrals

tplquad

triple integrals

romb

integrators for sampled data

ode

ODE integrators


odeint

ODE integrators

Examples

```
>>> from scipy import integrate
>>> import matplotlib.pyplot as plt
```

```
>>> x = np.linspace(-2, 2, num=20)
>>> y = x
>>> y_int = integrate.cumulative_trapezoid(y, x, initial=0)
>>> plt.plot(x, y_int, 'ro', x, y[0] + 0.5 * x**2, 'b-')
>>> plt.show()
```



scipy.integrate.simpson

`scipy.integrate.simpson` (*y*, *x=None*, *dx=1*, *axis=- 1*, *even='avg'*)

Integrate $y(x)$ using samples along the given axis and the composite Simpson's rule. If *x* is `None`, spacing of *dx* is assumed.

If there are an even number of samples, *N*, then there are an odd number of intervals (*N*-1), but Simpson's rule requires an even number of intervals. The parameter `'even'` controls how this is handled.

Parameters

y	[array_like] Array to be integrated.
x	[array_like, optional] If given, the points at which <i>y</i> is sampled.
dx	[int, optional] Spacing of integration points along axis of <i>x</i> . Only used when <i>x</i> is <code>None</code> . Default is 1.
axis	[int, optional] Axis along which to integrate. Default is the last axis.
even	[str {'avg', 'first', 'last'}, optional]
'avg'	[Average two results:1) use the first <i>N</i> -2 intervals with] a trapezoidal rule on the last interval and 2) use the last <i>N</i> -2 intervals with a trapezoidal rule on the first interval.
'first'	[Use Simpson's rule for the first <i>N</i> -2 intervals with] a trapezoidal rule on the last interval.
'last'	[Use Simpson's rule for the last <i>N</i> -2 intervals with a] trapezoidal rule on the first interval.

See also:

quad

adaptive quadrature using QUADPACK

romberg

adaptive Romberg quadrature

quadrature

adaptive Gaussian quadrature

fixed_quad

fixed-order Gaussian quadrature

dblquad

double integrals

tplquad

triple integrals

romb

integrators for sampled data

cumulative_trapezoid

cumulative integration for sampled data

ode

ODE integrators

`odeint`

ODE integrators

Notes

For an odd number of samples that are equally spaced the result is exact if the function is a polynomial of order 3 or less. If the samples are not equally spaced, then the result is exact only if the function is a polynomial of order 2 or less.

Examples

```
>>> from scipy import integrate
>>> x = np.arange(0, 10)
>>> y = np.arange(0, 10)
```

```
>>> integrate.simpson(y, x)
40.5
```

```
>>> y = np.power(x, 3)
>>> integrate.simpson(y, x)
1642.5
>>> integrate.quad(lambda x: x**3, 0, 9)[0]
1640.25
```

```
>>> integrate.simpson(y, x, even='first')
1644.5
```

`scipy.integrate.romb`

`scipy.integrate.romb`(*y*, *dx=1.0*, *axis=-1*, *show=False*)

Romberg integration using samples of a function.

Parameters

y	[array_like] A vector of $2^{*k} + 1$ equally-spaced samples of a function.
dx	[float, optional] The sample spacing. Default is 1.
axis	[int, optional] The axis along which to integrate. Default is -1 (last axis).
show	[bool, optional] When <i>y</i> is a single 1-D array, then if this argument is True print the table showing Richardson extrapolation from the samples. Default is False.

Returns

romb	[ndarray] The integrated result for <i>axis</i> .
-------------	---

See also:

`quad`

adaptive quadrature using QUADPACK

`romberg`

adaptive Romberg quadrature

quadrature

adaptive Gaussian quadrature

fixed_quad

fixed-order Gaussian quadrature

dblquad

double integrals

tplquad

triple integrals

simpson

integrators for sampled data

cumulative_trapezoid

cumulative integration for sampled data

ode

ODE integrators

odeint

ODE integrators

Examples

```
>>> from scipy import integrate
>>> x = np.arange(10, 14.25, 0.25)
>>> y = np.arange(3, 12)
```

```
>>> integrate.romb(y)
56.0
```

```
>>> y = np.sin(np.power(x, 2.5))
>>> integrate.romb(y)
-0.742561336672229
```

```
>>> integrate.romb(y, show=True)
Richardson Extrapolation Table for Romberg Integration
=====
-0.81576
4.63862  6.45674
-1.10581 -3.02062 -3.65245
-2.57379 -3.06311 -3.06595 -3.05664
-1.34093 -0.92997 -0.78776 -0.75160 -0.74256
=====
-0.742561336672229
```

See also:

[*scipy.special*](#) for orthogonal polynomials (*special*) for Gaussian quadrature roots and weights for other weighting factors and regions.

6.7.3 Solving initial value problems for ODE systems

The solvers are implemented as individual classes, which can be used directly (low-level usage) or through a convenience function.

<code>solve_ivp</code> (<i>fun</i> , <i>t_span</i> , <i>y0</i> [, <i>method</i> , <i>t_eval</i> , ...])	Solve an initial value problem for a system of ODEs.
<code>RK23</code> (<i>fun</i> , <i>t0</i> , <i>y0</i> , <i>t_bound</i> [, <i>max_step</i> , <i>rtol</i> , ...])	Explicit Runge-Kutta method of order 3(2).
<code>RK45</code> (<i>fun</i> , <i>t0</i> , <i>y0</i> , <i>t_bound</i> [, <i>max_step</i> , <i>rtol</i> , ...])	Explicit Runge-Kutta method of order 5(4).
<code>DOP853</code> (<i>fun</i> , <i>t0</i> , <i>y0</i> , <i>t_bound</i> [, <i>max_step</i> , ...])	Explicit Runge-Kutta method of order 8.
<code>Radau</code> (<i>fun</i> , <i>t0</i> , <i>y0</i> , <i>t_bound</i> [, <i>max_step</i> , ...])	Implicit Runge-Kutta method of Radau IIA family of order 5.
<code>BDF</code> (<i>fun</i> , <i>t0</i> , <i>y0</i> , <i>t_bound</i> [, <i>max_step</i> , <i>rtol</i> , ...])	Implicit method based on backward-differentiation formulas.
<code>LSODA</code> (<i>fun</i> , <i>t0</i> , <i>y0</i> , <i>t_bound</i> [, <i>first_step</i> , ...])	Adams/BDF method with automatic stiffness detection and switching.
<code>OdeSolver</code> (<i>fun</i> , <i>t0</i> , <i>y0</i> , <i>t_bound</i> , <i>vectorized</i>)	Base class for ODE solvers.
<code>DenseOutput</code> (<i>t_old</i> , <i>t</i>)	Base class for local interpolant over step made by an ODE solver.
<code>OdeSolution</code> (<i>ts</i> , <i>interpolants</i>)	Continuous ODE solution.

scipy.integrate.solve_ivp

`scipy.integrate.solve_ivp`(*fun*, *t_span*, *y0*, *method*='RK45', *t_eval*=None, *dense_output*=False, *events*=None, *vectorized*=False, *args*=None, ***options*)

Solve an initial value problem for a system of ODEs.

This function numerically integrates a system of ordinary differential equations given an initial value:

$$\begin{aligned} dy / dt &= f(t, y) \\ y(t_0) &= y_0 \end{aligned}$$

Here *t* is a 1-D independent variable (time), *y*(*t*) is an N-D vector-valued function (state), and an N-D vector-valued function *f*(*t*, *y*) determines the differential equations. The goal is to find *y*(*t*) approximately satisfying the differential equations, given an initial value *y*(*t*₀)=*y*₀.

Some of the solvers support integration in the complex domain, but note that for stiff ODE solvers, the right-hand side must be complex-differentiable (satisfy Cauchy-Riemann equations [11]). To solve a problem in the complex domain, pass *y0* with a complex data type. Another option always available is to rewrite your problem for real and imaginary parts separately.

Parameters

- fun** [callable] Right-hand side of the system. The calling signature is `fun(t, y)`. Here *t* is a scalar, and there are two options for the ndarray *y*: It can either have shape (n,); then *fun* must return array_like with shape (n,). Alternatively, it can have shape (n, k); then *fun* must return an array_like with shape (n, k), i.e., each column corresponds to a single column in *y*. The choice between the two options is determined by *vectorized* argument (see below). The vectorized implementation allows a faster approximation of the Jacobian by finite differences (required for stiff solvers).
- t_span** [2-tuple of floats] Interval of integration (*t0*, *tf*). The solver starts with *t*=*t0* and integrates until it reaches *t*=*tf*.
- y0** [array_like, shape (n,)] Initial state. For problems in the complex domain, pass *y0* with a complex data type (even if the initial value is purely real).
- method** [string or `OdeSolver`, optional] Integration method to use:

- ‘RK45’ (default): Explicit Runge-Kutta method of order 5(4) [1]. The error is controlled assuming accuracy of the fourth-order method, but steps are taken using the fifth-order accurate formula (local extrapolation is done). A quartic interpolation polynomial is used for the dense output [2]. Can be applied in the complex domain.
- ‘RK23’: Explicit Runge-Kutta method of order 3(2) [3]. The error is controlled assuming accuracy of the second-order method, but steps are taken using the third-order accurate formula (local extrapolation is done). A cubic Hermite polynomial is used for the dense output. Can be applied in the complex domain.
- ‘DOP853’: Explicit Runge-Kutta method of order 8 [13]. Python implementation of the “DOP853” algorithm originally written in Fortran [14]. A 7-th order interpolation polynomial accurate to 7-th order is used for the dense output. Can be applied in the complex domain.
- ‘Radau’: Implicit Runge-Kutta method of the Radau IIA family of order 5 [4]. The error is controlled with a third-order accurate embedded formula. A cubic polynomial which satisfies the collocation conditions is used for the dense output.
- ‘BDF’: Implicit multi-step variable-order (1 to 5) method based on a backward differentiation formula for the derivative approximation [5]. The implementation follows the one described in [6]. A quasi-constant step scheme is used and accuracy is enhanced using the NDF modification. Can be applied in the complex domain.
- ‘LSODA’: Adams/BDF method with automatic stiffness detection and switching [7], [8]. This is a wrapper of the Fortran solver from ODEPACK.

Explicit Runge-Kutta methods (‘RK23’, ‘RK45’, ‘DOP853’) should be used for non-stiff problems and implicit methods (‘Radau’, ‘BDF’) for stiff problems [9]. Among Runge-Kutta methods, ‘DOP853’ is recommended for solving with high precision (low values of *rtol* and *atol*).

If not sure, first try to run ‘RK45’. If it makes unusually many iterations, diverges, or fails, your problem is likely to be stiff and you should use ‘Radau’ or ‘BDF’. ‘LSODA’ can also be a good universal choice, but it might be somewhat less convenient to work with as it wraps old Fortran code.

You can also pass an arbitrary class derived from `OdeSolver` which implements the solver.

t_eval [array_like or None, optional] Times at which to store the computed solution, must be sorted and lie within *t_span*. If None (default), use points selected by the solver.

dense_output

[bool, optional] Whether to compute a continuous solution. Default is False.

events [callable, or list of callables, optional] Events to track. If None (default), no events will be tracked. Each event occurs at the zeros of a continuous function of time and state. Each function must have the signature `event(t, y)` and return a float. The solver will find an accurate value of *t* at which `event(t, y(t)) = 0` using a root-finding algorithm. By default, all zeros will be found. The solver looks for a sign change over each step, so if multiple zero crossings occur within one step, events may be missed. Additionally each *event* function might have the following attributes:

terminal: bool, optional

Whether to terminate integration if this event occurs. Implicitly False if not assigned.

direction: float, optional

Direction of a zero crossing. If *direction* is positive, *event* will only trigger when going from negative to positive, and vice versa if *direction* is negative. If 0, then either direction will trigger event. Implicitly 0 if not assigned.

You can assign attributes like `event.terminal = True` to any function in Python.

vectorized [bool, optional] Whether *fun* is implemented in a vectorized fashion. Default is False.

args [tuple, optional] Additional arguments to pass to the user-defined functions. If given, the additional arguments are passed to all user-defined functions. So if, for example, *fun* has the signature `fun(t, y, a, b, c)`, then *jac* (if given) and any event functions must have the same signature, and *args* must be a tuple of length 3.

- options** Options passed to a chosen solver. All options available for already implemented solvers are listed below.
- first_step** [float or None, optional] Initial step size. Default is *None* which means that the algorithm should choose.
- max_step** [float, optional] Maximum allowed step size. Default is `np.inf`, i.e., the step size is not bounded and determined solely by the solver.
- rtol, atol** [float or array_like, optional] Relative and absolute tolerances. The solver keeps the local error estimates less than $\text{atol} + \text{rtol} * \text{abs}(y)$. Here *rtol* controls a relative accuracy (number of correct digits). But if a component of *y* is approximately below *atol*, the error only needs to fall within the same *atol* threshold, and the number of correct digits is not guaranteed. If components of *y* have different scales, it might be beneficial to set different *atol* values for different components by passing array_like with shape (n,) for *atol*. Default values are 1e-3 for *rtol* and 1e-6 for *atol*.
- jac** [array_like, sparse_matrix, callable or None, optional] Jacobian matrix of the right-hand side of the system with respect to *y*, required by the ‘Radau’, ‘BDF’ and ‘LSODA’ method. The Jacobian matrix has shape (n, n) and its element (i, j) is equal to $d f_i / d y_j$. There are three ways to define the Jacobian:
- If array_like or sparse_matrix, the Jacobian is assumed to be constant. Not supported by ‘LSODA’.
 - If callable, the Jacobian is assumed to depend on both *t* and *y*; it will be called as `jac(t, y)`, as necessary. For ‘Radau’ and ‘BDF’ methods, the return value might be a sparse matrix.
 - If None (default), the Jacobian will be approximated by finite differences.
- It is generally recommended to provide the Jacobian rather than relying on a finite-difference approximation.
- jac_sparsity** [array_like, sparse matrix or None, optional] Defines a sparsity structure of the Jacobian matrix for a finite-difference approximation. Its shape must be (n, n). This argument is ignored if *jac* is not *None*. If the Jacobian has only few non-zero elements in *each* row, providing the sparsity structure will greatly speed up the computations [10]. A zero entry means that a corresponding element in the Jacobian is always zero. If None (default), the Jacobian is assumed to be dense. Not supported by ‘LSODA’, see *lband* and *uband* instead.
- lband, uband** [int or None, optional] Parameters defining the bandwidth of the Jacobian for the ‘LSODA’ method, i.e., `jac[i, j] != 0` only for $i - \text{lband} \leq j \leq i + \text{uband}$. Default is None. Setting these requires your *jac* routine to return the Jacobian in the packed format: the returned array must have *n* columns and `uband + lband + 1` rows in which Jacobian diagonals are written. Specifically `jac_packed[uband + i - j, j] = jac[i, j]`. The same format is used in `scipy.linalg.solve_banded` (check for an illustration). These parameters can be also used with *jac=None* to reduce the number of Jacobian elements estimated by finite differences.
- min_step** [float, optional] The minimum allowed step size for ‘LSODA’ method. By default *min_step* is zero.

Returns**Bunch object with the following fields defined:**

- t** [ndarray, shape (n_points,)] Time points.
- y** [ndarray, shape (n, n_points)] Values of the solution at *t*.
- sol** [*OdeSolution* or None] Found solution as *OdeSolution* instance; None if *dense_output* was set to False.
- t_events** [list of ndarray or None] Contains for each event type a list of arrays at which an event of that type event was detected. None if *events* was None.
- y_events** [list of ndarray or None] For each value of *t_events*, the corresponding value of the solution. None if *events* was None.

nfev	[int] Number of evaluations of the right-hand side.
njev	[int] Number of evaluations of the Jacobian.
nlu	[int] Number of LU decompositions.
status	[int] Reason for algorithm termination: <ul style="list-style-type: none"> • -1: Integration step failed. • 0: The solver successfully reached the end of <i>tspan</i>. • 1: A termination event occurred.
message	[string] Human-readable description of the termination reason.
success	[bool] True if the solver reached the interval end or a termination event occurred (<code>status >= 0</code>).

References

[1], [2], [3], [4], [5], [6], [7], [8], [9], [10], [11], [12], [13], [14]

Examples

Basic exponential decay showing automatically chosen time points.

```
>>> from scipy.integrate import solve_ivp
>>> def exponential_decay(t, y): return -0.5 * y
>>> sol = solve_ivp(exponential_decay, [0, 10], [2, 4, 8])
>>> print(sol.t)
[ 0.          0.11487653  1.26364188  3.06061781  4.81611105  6.57445806
 8.33328988 10.          ]
>>> print(sol.y)
[[2.          1.88836035  1.06327177  0.43319312  0.18017253  0.07483045
 0.03107158  0.01350781]
 [4.          3.7767207   2.12654355  0.86638624  0.36034507  0.14966091
 0.06214316  0.02701561]
 [8.          7.5534414   4.25308709  1.73277247  0.72069014  0.29932181
 0.12428631  0.05403123]]
```

Specifying points where the solution is desired.

```
>>> sol = solve_ivp(exponential_decay, [0, 10], [2, 4, 8],
...                 t_eval=[0, 1, 2, 4, 10])
>>> print(sol.t)
[ 0  1  2  4 10]
>>> print(sol.y)
[[2.          1.21305369  0.73534021  0.27066736  0.01350938]
 [4.          2.42610739  1.47068043  0.54133472  0.02701876]
 [8.          4.85221478  2.94136085  1.08266944  0.05403753]]
```

Cannon fired upward with terminal event upon impact. The terminal and direction fields of an event are applied by monkey patching a function. Here `y[0]` is position and `y[1]` is velocity. The projectile starts at position 0 with velocity +10. Note that the integration never reaches `t=100` because the event is terminal.

```
>>> def upward_cannon(t, y): return [y[1], -0.5]
>>> def hit_ground(t, y): return y[0]
>>> hit_ground.terminal = True
>>> hit_ground.direction = -1
```

(continues on next page)

(continued from previous page)

```

>>> sol = solve_ivp(upward_cannon, [0, 100], [0, 10], events=hit_ground)
>>> print(sol.t_events)
[array([40.])]
>>> print(sol.t)
[0.00000000e+00 9.99900010e-05 1.09989001e-03 1.10988901e-02
 1.11088891e-01 1.11098890e+00 1.11099890e+01 4.00000000e+01]

```

Use `dense_output` and `events` to find position, which is 100, at the apex of the cannonball's trajectory. Apex is not defined as terminal, so both apex and `hit_ground` are found. There is no information at $t=20$, so the `sol` attribute is used to evaluate the solution. The `sol` attribute is returned by setting `dense_output=True`. Alternatively, the `y_events` attribute can be used to access the solution at the time of the event.

```

>>> def apex(t, y): return y[1]
>>> sol = solve_ivp(upward_cannon, [0, 100], [0, 10],
...                 events=(hit_ground, apex), dense_output=True)
>>> print(sol.t_events)
[array([40.]), array([20.])]
>>> print(sol.t)
[0.00000000e+00 9.99900010e-05 1.09989001e-03 1.10988901e-02
 1.11088891e-01 1.11098890e+00 1.11099890e+01 4.00000000e+01]
>>> print(sol.sol(sol.t_events[1][0]))
[100.  0.]
>>> print(sol.y_events)
[array([[ -5.68434189e-14, -1.00000000e+01]]), array([[1.00000000e+02, 1.
→77635684e-15]])]

```

As an example of a system with additional parameters, we'll implement the Lotka-Volterra equations [12].

```

>>> def lotkavolterra(t, z, a, b, c, d):
...     x, y = z
...     return [a*x - b*x*y, -c*y + d*x*y]
...

```

We pass in the parameter values $a=1.5$, $b=1$, $c=3$ and $d=1$ with the `args` argument.

```

>>> sol = solve_ivp(lotkavolterra, [0, 15], [10, 5], args=(1.5, 1, 3, 1),
...                 dense_output=True)


```

Compute a dense solution and plot it.

```

>>> t = np.linspace(0, 15, 300)
>>> z = sol.sol(t)
>>> import matplotlib.pyplot as plt
>>> plt.plot(t, z.T)
>>> plt.xlabel('t')
>>> plt.legend(['x', 'y'], shadow=True)
>>> plt.title('Lotka-Volterra System')
>>> plt.show()

```



scipy.integrate.RK23

class `scipy.integrate.RK23` (*fun*, *t0*, *y0*, *t_bound*, *max_step=inf*, *rtol=0.001*, *atol=1e-06*, *vectorized=False*, *first_step=None*, ***extraneous*)

Explicit Runge-Kutta method of order 3(2).

This uses the Bogacki-Shampine pair of formulas [1]. The error is controlled assuming accuracy of the second-order method, but steps are taken using the third-order accurate formula (local extrapolation is done). A cubic Hermite polynomial is used for the dense output.

Can be applied in the complex domain.

Parameters

- fun** [callable] Right-hand side of the system. The calling signature is `fun(t, y)`. Here `t` is a scalar and there are two options for ndarray `y`. It can either have shape `(n,)`, then `fun` must return array_like with shape `(n,)`. Or alternatively it can have shape `(n, k)`, then `fun` must return array_like with shape `(n, k)`, i.e. each column corresponds to a single column in `y`. The choice between the two options is determined by `vectorized` argument (see below).
- t0** [float] Initial time.
- y0** [array_like, shape (n,)] Initial state.
- t_bound** [float] Boundary time - the integration won't continue beyond it. It also determines the direction of the integration.
- first_step** [float or None, optional] Initial step size. Default is `None` which means that the algorithm should choose.
- max_step** [float, optional] Maximum allowed step size. Default is `np.inf`, i.e., the step size is not bounded and determined solely by the solver.
- rtol, atol** [float and array_like, optional] Relative and absolute tolerances. The solver keeps the local error estimates less than `atol + rtol * abs(y)`. Here, `rtol` controls a relative accuracy (number of correct digits). But if a component of `y` is approximately below `atol`, the error only needs to fall within the same `atol` threshold, and the number of correct digits is not guaranteed. If components of `y` have different scales, it might be beneficial to set different `atol` values for different components by passing array_like with shape `(n,)` for `atol`. Default values are `1e-3` for `rtol` and `1e-6` for `atol`.
- vectorized** [bool, optional] Whether `fun` is implemented in a vectorized fashion. Default is `False`.

References

[1]

Attributes

n	[int] Number of equations.
status	[string] Current status of the solver: 'running', 'finished' or 'failed'.
t_bound	[float] Boundary time.
direction	[float] Integration direction: +1 or -1.
t	[float] Current time.
y	[ndarray] Current state.
t_old	[float] Previous time. None if no steps were made yet.
step_size	[float] Size of the last successful step. None if no steps were made yet.
nfev	[int] Number evaluations of the system's right-hand side.
njev	[int] Number of evaluations of the Jacobian. Is always 0 for this solver as it does not use the Jacobian.
nlu	[int] Number of LU decompositions. Is always 0 for this solver.

Methods

<code>dense_output(self)</code>	Compute a local interpolant over the last successful step.
<code>step(self)</code>	Perform one integration step.

scipy.integrate.RK23.dense_output

`RK23.dense_output(self)`

Compute a local interpolant over the last successful step.

Returns

sol [*DenseOutput*] Local interpolant over the last successful step.

scipy.integrate.RK23.step

`RK23.step(self)`

Perform one integration step.

Returns

message [string or None] Report from the solver. Typically a reason for a failure if `self.status` is 'failed' after the step was taken or None otherwise.

scipy.integrate.RK45

class `scipy.integrate.RK45` (*fun, t0, y0, t_bound, max_step=inf, rtol=0.001, atol=1e-06, vectorized=False, first_step=None, **extraneous*)

Explicit Runge-Kutta method of order 5(4).

This uses the Dormand-Prince pair of formulas [1]. The error is controlled assuming accuracy of the fourth-order method accuracy, but steps are taken using the fifth-order accurate formula (local extrapolation is done). A quartic interpolation polynomial is used for the dense output [2].

Can be applied in the complex domain.

Parameters

fun	[callable] Right-hand side of the system. The calling signature is <code>fun(t, y)</code> . Here <code>t</code> is a scalar, and there are two options for the ndarray <code>y</code> : It can either have shape <code>(n,)</code> ; then <code>fun</code> must return <code>array_like</code> with shape <code>(n,)</code> . Alternatively it can have shape <code>(n, k)</code> ; then <code>fun</code> must return an <code>array_like</code> with shape <code>(n, k)</code> , i.e., each column corresponds to a single column in <code>y</code> . The choice between the two options is determined by <i>vectorized</i> argument (see below).
t0	[float] Initial time.
y0	[array_like, shape (n,)] Initial state.
t_bound	[float] Boundary time - the integration won't continue beyond it. It also determines the direction of the integration.
first_step	[float or None, optional] Initial step size. Default is <code>None</code> which means that the algorithm should choose.
max_step	[float, optional] Maximum allowed step size. Default is <code>np.inf</code> , i.e., the step size is not bounded and determined solely by the solver.
rtol, atol	[float and array_like, optional] Relative and absolute tolerances. The solver keeps the local error estimates less than <code>atol + rtol * abs(y)</code> . Here <i>rtol</i> controls a relative accuracy (number of correct digits). But if a component of <code>y</code> is approximately below <i>atol</i> , the error only needs to fall within the same <i>atol</i> threshold, and the number of correct digits is not guaranteed. If components of <code>y</code> have different scales, it might be beneficial to set different <i>atol</i> values for different components by passing <code>array_like</code> with shape <code>(n,)</code> for <i>atol</i> . Default values are <code>1e-3</code> for <i>rtol</i> and <code>1e-6</code> for <i>atol</i> .
vectorized	[bool, optional] Whether <i>fun</i> is implemented in a vectorized fashion. Default is <code>False</code> .

References

[1], [2]

Attributes

n	[int] Number of equations.
status	[string] Current status of the solver: 'running', 'finished' or 'failed'.
t_bound	[float] Boundary time.
direction	[float] Integration direction: +1 or -1.
t	[float] Current time.
y	[ndarray] Current state.
t_old	[float] Previous time. <code>None</code> if no steps were made yet.
step_size	[float] Size of the last successful step. <code>None</code> if no steps were made yet.
nfev	[int] Number evaluations of the system's right-hand side.
njev	[int] Number of evaluations of the Jacobian. Is always 0 for this solver as it does not use the Jacobian.
nlu	[int] Number of LU decompositions. Is always 0 for this solver.

Methods

<code>dense_output(self)</code>	Compute a local interpolant over the last successful step.
<code>step(self)</code>	Perform one integration step.

scipy.integrate.RK45.dense_outputRK45.**dense_output** (*self*)

Compute a local interpolant over the last successful step.

Returns**sol** [*DenseOutput*] Local interpolant over the last successful step.**scipy.integrate.RK45.step**RK45.**step** (*self*)

Perform one integration step.

Returns**message** [string or None] Report from the solver. Typically a reason for a failure if *self.status* is 'failed' after the step was taken or None otherwise.**scipy.integrate.DOP853****class** `scipy.integrate.DOP853` (*fun*, *t0*, *y0*, *t_bound*, *max_step=inf*, *rtol=0.001*, *atol=1e-06*, *vectorized=False*, *first_step=None*, ***extraneous*)

Explicit Runge-Kutta method of order 8.

This is a Python implementation of "DOP853" algorithm originally written in Fortran [1], [2]. Note that this is not a literate translation, but the algorithmic core and coefficients are the same.

Can be applied in the complex domain.

Parameters

fun [callable] Right-hand side of the system. The calling signature is `fun(t, y)`. Here, `t` is a scalar, and there are two options for the ndarray `y`: It can either have shape `(n,)`; then `fun` must return array_like with shape `(n,)`. Alternatively it can have shape `(n, k)`; then `fun` must return an array_like with shape `(n, k)`, i.e. each column corresponds to a single column in `y`. The choice between the two options is determined by *vectorized* argument (see below).

t0 [float] Initial time.

y0 [array_like, shape (n,)] Initial state.

t_bound [float] Boundary time - the integration won't continue beyond it. It also determines the direction of the integration.

first_step [float or None, optional] Initial step size. Default is `None` which means that the algorithm should choose.

max_step [float, optional] Maximum allowed step size. Default is `np.inf`, i.e. the step size is not bounded and determined solely by the solver.

rtol, atol [float and array_like, optional] Relative and absolute tolerances. The solver keeps the local error estimates less than `atol + rtol * abs(y)`. Here *rtol* controls a relative accuracy (number of correct digits). But if a component of `y` is approximately below *atol*, the error only needs to fall within the same *atol* threshold, and the number of correct digits is not guaranteed. If components of `y` have different scales, it might be beneficial to set different *atol* values for different components by passing array_like with shape `(n,)` for *atol*. Default values are `1e-3` for *rtol* and `1e-6` for *atol*.

vectorized [bool, optional] Whether *fun* is implemented in a vectorized fashion. Default is `False`.

References

[1], [2]

Attributes

n	[int] Number of equations.
status	[string] Current status of the solver: 'running', 'finished' or 'failed'.
t_bound	[float] Boundary time.
direction	[float] Integration direction: +1 or -1.
t	[float] Current time.
y	[ndarray] Current state.
t_old	[float] Previous time. None if no steps were made yet.
step_size	[float] Size of the last successful step. None if no steps were made yet.
nfev	[int] Number evaluations of the system's right-hand side.
njev	[int] Number of evaluations of the Jacobian. Is always 0 for this solver as it does not use the Jacobian.
nlu	[int] Number of LU decompositions. Is always 0 for this solver.

Methods

<code>dense_output(self)</code>	Compute a local interpolant over the last successful step.
<code>step(self)</code>	Perform one integration step.

scipy.integrate.DOP853.dense_output

DOP853.**dense_output** (*self*)

Compute a local interpolant over the last successful step.

Returns

sol [*DenseOutput*] Local interpolant over the last successful step.

scipy.integrate.DOP853.step

DOP853.**step** (*self*)

Perform one integration step.

Returns

message [string or None] Report from the solver. Typically a reason for a failure if *self.status* is 'failed' after the step was taken or None otherwise.

scipy.integrate.Radau

class `scipy.integrate.Radau` (*fun, t0, y0, t_bound, max_step=inf, rtol=0.001, atol=1e-06, jac=None, jac_sparsity=None, vectorized=False, first_step=None, **extraneous*)

Implicit Runge-Kutta method of Radau IIA family of order 5.

The implementation follows [1]. The error is controlled with a third-order accurate embedded formula. A cubic polynomial which satisfies the collocation conditions is used for the dense output.

Parameters

fun [callable] Right-hand side of the system. The calling signature is `fun(t, y)`. Here `t` is a scalar, and there are two options for the ndarray `y`: It can either have shape `(n,)`; then `fun`

must return `array_like` with shape $(n,)$. Alternatively it can have shape (n, k) ; then `fun` must return an `array_like` with shape (n, k) , i.e., each column corresponds to a single column in `y`. The choice between the two options is determined by `vectorized` argument (see below). The vectorized implementation allows a faster approximation of the Jacobian by finite differences (required for this solver).

t0	[float] Initial time.
y0	[array_like, shape $(n,)$] Initial state.
t_bound	[float] Boundary time - the integration won't continue beyond it. It also determines the direction of the integration.
first_step	[float or None, optional] Initial step size. Default is <code>None</code> which means that the algorithm should choose.
max_step	[float, optional] Maximum allowed step size. Default is <code>np.inf</code> , i.e., the step size is not bounded and determined solely by the solver.
rtol, atol	[float and array_like, optional] Relative and absolute tolerances. The solver keeps the local error estimates less than $atol + rtol * abs(y)$. Here <code>rtol</code> controls a relative accuracy (number of correct digits). But if a component of <code>y</code> is approximately below <code>atol</code> , the error only needs to fall within the same <code>atol</code> threshold, and the number of correct digits is not guaranteed. If components of <code>y</code> have different scales, it might be beneficial to set different <code>atol</code> values for different components by passing <code>array_like</code> with shape $(n,)$ for <code>atol</code> . Default values are $1e-3$ for <code>rtol</code> and $1e-6$ for <code>atol</code> .
jac	[{None, array_like, sparse_matrix, callable}, optional] Jacobian matrix of the right-hand side of the system with respect to <code>y</code> , required by this method. The Jacobian matrix has shape (n, n) and its element (i, j) is equal to $d f_i / d y_j$. There are three ways to define the Jacobian: <ul style="list-style-type: none"> • If <code>array_like</code> or <code>sparse_matrix</code>, the Jacobian is assumed to be constant. • If callable, the Jacobian is assumed to depend on both <code>t</code> and <code>y</code>; it will be called as <code>jac(t, y)</code> as necessary. For the 'Radau' and 'BDF' methods, the return value might be a sparse matrix. • If <code>None</code> (default), the Jacobian will be approximated by finite differences. It is generally recommended to provide the Jacobian rather than relying on a finite-difference approximation.
jac_sparsity	[{None, array_like, sparse matrix}, optional] Defines a sparsity structure of the Jacobian matrix for a finite-difference approximation. Its shape must be (n, n) . This argument is ignored if <code>jac</code> is not <code>None</code> . If the Jacobian has only few non-zero elements in <i>each</i> row, providing the sparsity structure will greatly speed up the computations [2]. A zero entry means that a corresponding element in the Jacobian is always zero. If <code>None</code> (default), the Jacobian is assumed to be dense.
vectorized	[bool, optional] Whether <code>fun</code> is implemented in a vectorized fashion. Default is <code>False</code> .

References

[1], [2]

Attributes

n	[int] Number of equations.
status	[string] Current status of the solver: 'running', 'finished' or 'failed'.
t_bound	[float] Boundary time.
direction	[float] Integration direction: +1 or -1.
t	[float] Current time.
y	[ndarray] Current state.
t_old	[float] Previous time. <code>None</code> if no steps were made yet.
step_size	[float] Size of the last successful step. <code>None</code> if no steps were made yet.

nfev	[int] Number of evaluations of the right-hand side.
njev	[int] Number of evaluations of the Jacobian.
nlu	[int] Number of LU decompositions.

Methods

<code>dense_output(self)</code>	Compute a local interpolant over the last successful step.
<code>step(self)</code>	Perform one integration step.

scipy.integrate.Radau.dense_output

Radau.**dense_output** (*self*)

Compute a local interpolant over the last successful step.

Returns

sol [*DenseOutput*] Local interpolant over the last successful step.

scipy.integrate.Radau.step

Radau.**step** (*self*)

Perform one integration step.

Returns

message [string or None] Report from the solver. Typically a reason for a failure if *self.status* is 'failed' after the step was taken or None otherwise.

scipy.integrate.BDF

class `scipy.integrate.BDF` (*fun*, *t0*, *y0*, *t_bound*, *max_step=inf*, *rtol=0.001*, *atol=1e-06*, *jac=None*, *jac_sparsity=None*, *vectorized=False*, *first_step=None*, ***extraneous*)

Implicit method based on backward-differentiation formulas.

This is a variable order method with the order varying automatically from 1 to 5. The general framework of the BDF algorithm is described in [1]. This class implements a quasi-constant step size as explained in [2]. The error estimation strategy for the constant-step BDF is derived in [3]. An accuracy enhancement using modified formulas (NDF) [2] is also implemented.

Can be applied in the complex domain.

Parameters

fun	[callable] Right-hand side of the system. The calling signature is <code>fun(t, y)</code> . Here <code>t</code> is a scalar, and there are two options for the ndarray <code>y</code> : It can either have shape <code>(n,)</code> ; then <code>fun</code> must return <code>array_like</code> with shape <code>(n,)</code> . Alternatively it can have shape <code>(n, k)</code> ; then <code>fun</code> must return an <code>array_like</code> with shape <code>(n, k)</code> , i.e. each column corresponds to a single column in <code>y</code> . The choice between the two options is determined by <code>vectorized</code> argument (see below). The vectorized implementation allows a faster approximation of the Jacobian by finite differences (required for this solver).
t0	[float] Initial time.
y0	[array_like, shape (n,)] Initial state.
t_bound	[float] Boundary time - the integration won't continue beyond it. It also determines the direction of the integration.
first_step	[float or None, optional] Initial step size. Default is <code>None</code> which means that the algorithm should choose.

max_step	[float, optional] Maximum allowed step size. Default is <code>np.inf</code> , i.e., the step size is not bounded and determined solely by the solver.
rtol, atol	[float and array_like, optional] Relative and absolute tolerances. The solver keeps the local error estimates less than $\text{atol} + \text{rtol} * \text{abs}(y)$. Here <i>rtol</i> controls a relative accuracy (number of correct digits). But if a component of <i>y</i> is approximately below <i>atol</i> , the error only needs to fall within the same <i>atol</i> threshold, and the number of correct digits is not guaranteed. If components of <i>y</i> have different scales, it might be beneficial to set different <i>atol</i> values for different components by passing array_like with shape (n,) for <i>atol</i> . Default values are 1e-3 for <i>rtol</i> and 1e-6 for <i>atol</i> .
jac	[{None, array_like, sparse_matrix, callable}, optional] Jacobian matrix of the right-hand side of the system with respect to <i>y</i> , required by this method. The Jacobian matrix has shape (n, n) and its element (i, j) is equal to $d f_i / d y_j$. There are three ways to define the Jacobian: <ul style="list-style-type: none"> • If array_like or sparse_matrix, the Jacobian is assumed to be constant. • If callable, the Jacobian is assumed to depend on both <i>t</i> and <i>y</i>; it will be called as <code>jac(t, y)</code> as necessary. For the ‘Radau’ and ‘BDF’ methods, the return value might be a sparse matrix. • If None (default), the Jacobian will be approximated by finite differences. It is generally recommended to provide the Jacobian rather than relying on a finite-difference approximation.
jac_sparsity	[{None, array_like, sparse matrix}, optional] Defines a sparsity structure of the Jacobian matrix for a finite-difference approximation. Its shape must be (n, n). This argument is ignored if <i>jac</i> is not None. If the Jacobian has only few non-zero elements in <i>each</i> row, providing the sparsity structure will greatly speed up the computations [4]. A zero entry means that a corresponding element in the Jacobian is always zero. If None (default), the Jacobian is assumed to be dense.
vectorized	[bool, optional] Whether <i>fun</i> is implemented in a vectorized fashion. Default is False.

References

[1], [2], [3], [4]

Attributes

n	[int] Number of equations.
status	[string] Current status of the solver: ‘running’, ‘finished’ or ‘failed’.
t_bound	[float] Boundary time.
direction	[float] Integration direction: +1 or -1.
t	[float] Current time.
y	[ndarray] Current state.
t_old	[float] Previous time. None if no steps were made yet.
step_size	[float] Size of the last successful step. None if no steps were made yet.
nfev	[int] Number of evaluations of the right-hand side.
njev	[int] Number of evaluations of the Jacobian.
nlu	[int] Number of LU decompositions.

Methods

<code>dense_output(self)</code>	Compute a local interpolant over the last successful step.
<code>step(self)</code>	Perform one integration step.

scipy.integrate.BDF.dense_output

BDF.`dense_output` (*self*)

Compute a local interpolant over the last successful step.

Returns

sol [*DenseOutput*] Local interpolant over the last successful step.

scipy.integrate.BDF.step

BDF.`step` (*self*)

Perform one integration step.

Returns

message [string or None] Report from the solver. Typically a reason for a failure if *self.status* is 'failed' after the step was taken or None otherwise.

scipy.integrate.LSODA

class `scipy.integrate.LSODA` (*fun, t0, y0, t_bound, first_step=None, min_step=0.0, max_step=inf, rtol=0.001, atol=1e-06, jac=None, lband=None, uband=None, vectorized=False, **extraneous*)

Adams/BDF method with automatic stiffness detection and switching.

This is a wrapper to the Fortran solver from ODEPACK [1]. It switches automatically between the nonstiff Adams method and the stiff BDF method. The method was originally detailed in [2].

Parameters

fun [callable] Right-hand side of the system. The calling signature is `fun(t, y)`. Here `t` is a scalar, and there are two options for the ndarray `y`: It can either have shape `(n,)`; then `fun` must return `array_like` with shape `(n,)`. Alternatively it can have shape `(n, k)`; then `fun` must return an `array_like` with shape `(n, k)`, i.e. each column corresponds to a single column in `y`. The choice between the two options is determined by `vectorized` argument (see below). The vectorized implementation allows a faster approximation of the Jacobian by finite differences (required for this solver).

t0 [float] Initial time.

y0 [array_like, shape (n,)] Initial state.

t_bound [float] Boundary time - the integration won't continue beyond it. It also determines the direction of the integration.

first_step [float or None, optional] Initial step size. Default is `None` which means that the algorithm should choose.

min_step [float, optional] Minimum allowed step size. Default is `0.0`, i.e., the step size is not bounded and determined solely by the solver.

max_step [float, optional] Maximum allowed step size. Default is `np.inf`, i.e., the step size is not bounded and determined solely by the solver.

- rtol, atol** [float and array_like, optional] Relative and absolute tolerances. The solver keeps the local error estimates less than $\text{atol} + \text{rtol} * \text{abs}(y)$. Here *rtol* controls a relative accuracy (number of correct digits). But if a component of *y* is approximately below *atol*, the error only needs to fall within the same *atol* threshold, and the number of correct digits is not guaranteed. If components of *y* have different scales, it might be beneficial to set different *atol* values for different components by passing array_like with shape (n,) for *atol*. Default values are 1e-3 for *rtol* and 1e-6 for *atol*.
- jac** [None or callable, optional] Jacobian matrix of the right-hand side of the system with respect to *y*. The Jacobian matrix has shape (n, n) and its element (i, j) is equal to $d f_i / d y_j$. The function will be called as `jac(t, y)`. If None (default), the Jacobian will be approximated by finite differences. It is generally recommended to provide the Jacobian rather than relying on a finite-difference approximation.
- lband, uband** [int or None] Parameters defining the bandwidth of the Jacobian, i.e., `jac[i, j] != 0` only for $i - \text{lband} \leq j \leq i + \text{uband}$. Setting these requires your `jac` routine to return the Jacobian in the packed format: the returned array must have *n* columns and $\text{uband} + \text{lband} + 1$ rows in which Jacobian diagonals are written. Specifically `jac_packed[uband + i - j, j] = jac[i, j]`. The same format is used in `scipy.linalg.solve_banded` (check for an illustration). These parameters can be also used with `jac=None` to reduce the number of Jacobian elements estimated by finite differences.
- vectorized** [bool, optional] Whether *fun* is implemented in a vectorized fashion. A vectorized implementation offers no advantages for this solver. Default is False.

References

[1], [2]

Attributes

- n** [int] Number of equations.
- status** [string] Current status of the solver: 'running', 'finished' or 'failed'.
- t_bound** [float] Boundary time.
- direction** [float] Integration direction: +1 or -1.
- t** [float] Current time.
- y** [ndarray] Current state.
- t_old** [float] Previous time. None if no steps were made yet.
- nfev** [int] Number of evaluations of the right-hand side.
- njev** [int] Number of evaluations of the Jacobian.

Methods

<code>dense_output(self)</code>	Compute a local interpolant over the last successful step.
<code>step(self)</code>	Perform one integration step.

scipy.integrate.LSODA.dense_output

LSODA.**dense_output** (*self*)

Compute a local interpolant over the last successful step.

Returns

sol [*DenseOutput*] Local interpolant over the last successful step.

scipy.integrate.LSODA.step

LSODA.**step** (*self*)

Perform one integration step.

Returns

message [string or None] Report from the solver. Typically a reason for a failure if *self.status* is 'failed' after the step was taken or None otherwise.

scipy.integrate.OdeSolver

class scipy.integrate.**OdeSolver** (*fun, t0, y0, t_bound, vectorized, support_complex=False*)

Base class for ODE solvers.

In order to implement a new solver you need to follow the guidelines:

1. A constructor must accept parameters presented in the base class (listed below) along with any other parameters specific to a solver.
2. A constructor must accept arbitrary extraneous arguments ***extraneous*, but warn that these arguments are irrelevant using *common.warn_extraneous* function. Do not pass these arguments to the base class.
3. A solver must implement a private method *_step_impl(self)* which propagates a solver one step further. It must return tuple (*success, message*), where *success* is a boolean indicating whether a step was successful, and *message* is a string containing description of a failure if a step failed or None otherwise.
4. A solver must implement a private method *_dense_output_impl(self)*, which returns a *DenseOutput* object covering the last successful step.
5. A solver must have attributes listed below in Attributes section. Note that *t_old* and *step_size* are updated automatically.
6. Use *fun(self, t, y)* method for the system rhs evaluation, this way the number of function evaluations (*nfev*) will be tracked automatically.
7. For convenience, a base class provides *fun_single(self, t, y)* and *fun_vectorized(self, t, y)* for evaluating the rhs in non-vectorized and vectorized fashions respectively (regardless of how *fun* from the constructor is implemented). These calls don't increment *nfev*.
8. If a solver uses a Jacobian matrix and LU decompositions, it should track the number of Jacobian evaluations (*njev*) and the number of LU decompositions (*nlu*).
9. By convention, the function evaluations used to compute a finite difference approximation of the Jacobian should not be counted in *nfev*, thus use *fun_single(self, t, y)* or *fun_vectorized(self, t, y)* when computing a finite difference approximation of the Jacobian.

Parameters

fun [callable] Right-hand side of the system. The calling signature is *fun(t, y)*. Here *t* is a scalar and there are two options for ndarray *y*. It can either have shape (n,), then *fun* must return array_like with shape (n,). Or, alternatively, it can have shape (n, n_points), then *fun*

must return `array_like` with shape (n, n_points) (each column corresponds to a single column in y). The choice between the two options is determined by `vectorized` argument (see below).

t0 [float] Initial time.

y0 [array_like, shape (n,)] Initial state.

t_bound [float] Boundary time — the integration won't continue beyond it. It also determines the direction of the integration.

vectorized [bool] Whether `fun` is implemented in a vectorized fashion.

support_complex [bool, optional] Whether integration in a complex domain should be supported. Generally determined by a derived solver class capabilities. Default is `False`.

Attributes

n [int] Number of equations.

status [string] Current status of the solver: 'running', 'finished' or 'failed'.

t_bound [float] Boundary time.

direction [float] Integration direction: +1 or -1.

t [float] Current time.

y [ndarray] Current state.

t_old [float] Previous time. None if no steps were made yet.

step_size [float] Size of the last successful step. None if no steps were made yet.

nfev [int] Number of the system's rhs evaluations.

njev [int] Number of the Jacobian evaluations.

nlu [int] Number of LU decompositions.

Methods

<code>dense_output(self)</code>	Compute a local interpolant over the last successful step.
<code>step(self)</code>	Perform one integration step.

`scipy.integrate.OdeSolver.dense_output`

`OdeSolver.dense_output(self)`

Compute a local interpolant over the last successful step.

Returns

sol [`DenseOutput`] Local interpolant over the last successful step.

`scipy.integrate.OdeSolver.step`

`OdeSolver.step(self)`

Perform one integration step.

Returns

message [string or None] Report from the solver. Typically a reason for a failure if `self.status` is 'failed' after the step was taken or None otherwise.

scipy.integrate.DenseOutput

class `scipy.integrate.DenseOutput` (*t_{old}*, *t*)

Base class for local interpolant over step made by an ODE solver.

It interpolates between *t_{min}* and *t_{max}* (see Attributes below). Evaluation outside this interval is not forbidden, but the accuracy is not guaranteed.

Attributes

t_{min}, t_{max}
 [float] Time range of the interpolation.

Methods

<code>__call__(self, t)</code>	Evaluate the interpolant.
--------------------------------	---------------------------

scipy.integrate.DenseOutput.__call__

`DenseOutput.__call__(self, t)`

Evaluate the interpolant.

Parameters

t [float or array_like with shape (n_{points},)] Points to evaluate the solution at.

Returns

y [ndarray, shape (n,) or (n, n_{points})] Computed values. Shape depends on whether *t* was a scalar or a 1-D array.

scipy.integrate.OdeSolution

class `scipy.integrate.OdeSolution` (*ts*, *interpolants*)

Continuous ODE solution.

It is organized as a collection of *DenseOutput* objects which represent local interpolants. It provides an algorithm to select a right interpolant for each given point.

The interpolants cover the range between *t_{min}* and *t_{max}* (see Attributes below). Evaluation outside this interval is not forbidden, but the accuracy is not guaranteed.

When evaluating at a breakpoint (one of the values in *ts*) a segment with the lower index is selected.

Parameters

ts [array_like, shape (n_{segments} + 1,)] Time instants between which local interpolants are defined. Must be strictly increasing or decreasing (zero segment with two points is also allowed).

interpolants

[list of *DenseOutput* with n_{segments} elements] Local interpolants. An *i*-th interpolant is assumed to be defined between *ts*[*i*] and *ts*[*i* + 1].

Attributes

t_{min}, t_{max}
 [float] Time range of the interpolation.

Methods

<code>__call__(self, t)</code>	Evaluate the solution.
--------------------------------	------------------------

`scipy.integrate.OdeSolution.__call__`

`OdeSolution.__call__(self, t)`
Evaluate the solution.

Parameters

t [float or array_like with shape (n_points,)] Points to evaluate at.

Returns

y [ndarray, shape (n_states,) or (n_states, n_points)] Computed values. Shape depends on whether *t* is a scalar or a 1-D array.

Old API

These are the routines developed earlier for SciPy. They wrap older solvers implemented in Fortran (mostly ODEPACK). While the interface to them is not particularly convenient and certain features are missing compared to the new API, the solvers themselves are of good quality and work fast as compiled Fortran code. In some cases, it might be worth using this old API.

<code>odeint(func, y0, t[, args, Dfun, col_deriv, ...])</code>	Integrate a system of ordinary differential equations.
<code>ode(f[, jac])</code>	A generic interface class to numeric integrators.
<code>complex_ode(f[, jac])</code>	A wrapper of ode for complex systems.

`scipy.integrate.odeint`

`scipy.integrate.odeint` (*func*, *y0*, *t*, *args=()*, *Dfun=None*, *col_deriv=0*, *full_output=0*, *ml=None*, *mu=None*, *rtol=None*, *atol=None*, *tcrit=None*, *h0=0.0*, *hmax=0.0*, *hmin=0.0*, *ixpr=0*, *mxstep=0*, *mxhnil=0*, *mxordn=12*, *mxords=5*, *printmessg=0*, *tfirst=False*)

Integrate a system of ordinary differential equations.

Note: For new code, use `scipy.integrate.solve_ivp` to solve a differential equation.

Solve a system of ordinary differential equations using Isoda from the FORTRAN library odepack.

Solves the initial value problem for stiff or non-stiff systems of first order ode-s:

$$dy/dt = \text{func}(y, t, \dots) \quad [\text{or } \text{func}(t, y, \dots)]$$

where *y* can be a vector.

Note: By default, the required order of the first two arguments of *func* are in the opposite order of the arguments in the system definition function used by the `scipy.integrate.ode` class and the function `scipy.integrate.solve_ivp`. To use a function with the signature `func(t, y, ...)`, the argument *tfirst* must be set to True.

Parameters

func [callable(y, t, ...) or callable(t, y, ...)] Computes the derivative of y at t. If the signature is callable(t, y, ...), then the argument *tfirst* must be set True.

y0 [array] Initial condition on y (can be a vector).

t [array] A sequence of time points for which to solve for y. The initial value point should be the first element of this sequence. This sequence must be monotonically increasing or monotonically decreasing; repeated values are allowed.

args [tuple, optional] Extra arguments to pass to function.

Dfun [callable(y, t, ...) or callable(t, y, ...)] Gradient (Jacobian) of *func*. If the signature is callable(t, y, ...), then the argument *tfirst* must be set True.

col_deriv [bool, optional] True if *Dfun* defines derivatives down columns (faster), otherwise *Dfun* should define derivatives across rows.

full_output [bool, optional] True if to return a dictionary of optional outputs as the second output

printmessg [bool, optional] Whether to print the convergence message

tfirst: bool, optional
 If True, the first two arguments of *func* (and *Dfun*, if given) must t, y instead of the default y, t.
 New in version 1.1.0.

Returns

y [array, shape (len(t), len(y0))] Array containing the value of y for each desired time in t, with the initial value y0 in the first row.

infodict [dict, only returned if full_output == True] Dictionary containing additional output information

key	meaning
'hu'	vector of step sizes successfully used for each time step
'tcur'	vector with the value of t reached for each time step (will always be at least as large as the input times)
'tolsf'	vector of tolerance scale factors, greater than 1.0, computed when a request for too much accuracy was detected
'tsw'	value of t at the time of the last method switch (given for each time step)
'nst'	cumulative number of time steps
'nfe'	cumulative number of function evaluations for each time step
'nje'	cumulative number of jacobian evaluations for each time step
'nqu'	a vector of method orders for each successful step
'imxer'	index of the component of largest magnitude in the weighted local error vector (e / ewt) on an error return, -1 otherwise
'lenrw'	the length of the double work array required
'leniw'	the length of integer work array required
'mused'	a vector of method indicators for each successful time step: 1: adams (nonstiff), 2: bdf (stiff)

Other Parameters

ml, mu [int, optional] If either of these are not None or non-negative, then the Jacobian is assumed to be banded. These give the number of lower and upper non-zero diagonals in this banded matrix. For the banded case, *Dfun* should return a matrix whose rows contain the non-zero bands (starting with the lowest diagonal). Thus, the return matrix *jac* from *Dfun* should have shape (ml + mu + 1, len(y0)) when ml >=0 or mu >=0. The data in *jac* must be stored such that jac[i - j + mu, j] holds the derivative of the *i*th equation with respect to the *j*th state variable. If *col_deriv* is True, the transpose of this *jac* must be returned.

rtol, atol	[float, optional] The input parameters <i>rtol</i> and <i>atol</i> determine the error control performed by the solver. The solver will control the vector, <i>e</i> , of estimated local errors in <i>y</i> , according to an inequality of the form $\max\text{-norm of } (e / \text{ewt}) \leq 1$, where <i>ewt</i> is a vector of positive error weights computed as $\text{ewt} = \text{rtol} * \text{abs}(y) + \text{atol}$. <i>rtol</i> and <i>atol</i> can be either vectors the same length as <i>y</i> or scalars. Defaults to 1.49012e-8.
tcrit	[ndarray, optional] Vector of critical points (e.g., singularities) where integration care should be taken.
h0	[float, (0: solver-determined), optional] The step size to be attempted on the first step.
hmax	[float, (0: solver-determined), optional] The maximum absolute step size allowed.
hmin	[float, (0: solver-determined), optional] The minimum absolute step size allowed.
ixpr	[bool, optional] Whether to generate extra printing at method switches.
mxstep	[int, (0: solver-determined), optional] Maximum number of (internally defined) steps allowed for each integration point in <i>t</i> .
mxhnil	[int, (0: solver-determined), optional] Maximum number of messages printed.
mxordn	[int, (0: solver-determined), optional] Maximum order to be allowed for the non-stiff (Adams) method.
mxords	[int, (0: solver-determined), optional] Maximum order to be allowed for the stiff (BDF) method.

See also:

[*solve_ivp*](#)

solve an initial value problem for a system of ODEs

[*ode*](#)

a more object-oriented integrator based on VODE

[*quad*](#)

for finding the area under a curve

Examples

The second order differential equation for the angle *theta* of a pendulum acted on by gravity with friction can be written:

$$\text{theta}''(t) + b * \text{theta}'(t) + c * \sin(\text{theta}(t)) = 0$$

where *b* and *c* are positive constants, and a prime (') denotes a derivative. To solve this equation with *odeint*, we must first convert it to a system of first order equations. By defining the angular velocity $\omega(t) = \text{theta}'(t)$, we obtain the system:

$$\begin{aligned} \text{theta}'(t) &= \omega(t) \\ \omega'(t) &= -b * \omega(t) - c * \sin(\text{theta}(t)) \end{aligned}$$

Let *y* be the vector [*theta*, *omega*]. We implement this system in Python as:

```
>>> def pend(y, t, b, c):
...     theta, omega = y
...     dydt = [omega, -b*omega - c*np.sin(theta)]
...     return dydt
... 
```

We assume the constants are *b* = 0.25 and *c* = 5.0:

```
>>> b = 0.25
>>> c = 5.0
```

For initial conditions, we assume the pendulum is nearly vertical with $\theta(0) = \pi - 0.1$, and is initially at rest, so $\omega(0) = 0$. Then the vector of initial conditions is

```
>>> y0 = [np.pi - 0.1, 0.0]
```

We will generate a solution at 101 evenly spaced samples in the interval $0 \leq t \leq 10$. So our array of times is:


```
>>> t = np.linspace(0, 10, 101)
```

Call `odeint` to generate the solution. To pass the parameters b and c to `pend`, we give them to `odeint` using the `args` argument.

```
>>> from scipy.integrate import odeint
>>> sol = odeint(pend, y0, t, args=(b, c))
```

The solution is an array with shape (101, 2). The first column is $\theta(t)$, and the second is $\omega(t)$. The following code plots both components.

```
>>> import matplotlib.pyplot as plt
>>> plt.plot(t, sol[:, 0], 'b', label='theta(t)')
>>> plt.plot(t, sol[:, 1], 'g', label='omega(t)')
>>> plt.legend(loc='best')
>>> plt.xlabel('t')
>>> plt.grid()
>>> plt.show()
```



scipy.integrate.ode

class `scipy.integrate.ode` (*f*, *jac=None*)

A generic interface class to numeric integrators.

Solve an equation system $y'(t) = f(t, y)$ with (optional) `jac = df/dy`.

Note: The first two arguments of `f(t, y, ...)` are in the opposite order of the arguments in the system definition function used by `scipy.integrate.odeint`.

Parameters

- f** [callable `f(t, y, *f_args)`] Right-hand side of the differential equation. `t` is a scalar, `y.shape == (n,)`. `f_args` is set by calling `set_f_params(*args)`. `f` should return a scalar, array or list (not a tuple).
- jac** [callable `jac(t, y, *jac_args)`, optional] Jacobian of the right-hand side, `jac[i, j] = d f[i] / d y[j]`. `jac_args` is set by calling `set_jac_params(*args)`.

See also:

`odeint`

an integrator with a simpler interface based on lsoda from ODEPACK

`quad`

for finding the area under a curve

Notes

Available integrators are listed below. They can be selected using the `set_integrator` method.

“vode”

Real-valued Variable-coefficient Ordinary Differential Equation solver, with fixed-leading-coefficient implementation. It provides implicit Adams method (for non-stiff problems) and a method based on backward differentiation formulas (BDF) (for stiff problems).

Source: <http://www.netlib.org/ode/vode.f>

Warning: This integrator is not re-entrant. You cannot have two `ode` instances using the “vode” integrator at the same time.

This integrator accepts the following parameters in `set_integrator` method of the `ode` class:

- `atol` : float or sequence absolute tolerance for solution
- `rtol` : float or sequence relative tolerance for solution
- `lband` : None or int
- `uband` : None or int Jacobian band width, `jac[i,j] != 0` for `i-lband <= j <= i+uband`. Setting these requires your `jac` routine to return the jacobian in packed format, `jac_packed[i-j+uband, j] = jac[i,j]`. The dimension of the matrix must be `(lband+uband+1, len(y))`.
- `method`: ‘adams’ or ‘bdf’ Which solver to use, Adams (non-stiff) or BDF (stiff)
- `with_jacobian` : bool This option is only considered when the user has not supplied a Jacobian function and has not indicated (by setting either band) that the Jacobian is banded. In this case, `with_jacobian` specifies whether the iteration method of the ODE solver’s correction step is chord iteration with an internally generated full Jacobian or functional iteration with no Jacobian.
- `nsteps` : int Maximum number of (internally defined) steps allowed during one call to the solver.
- `first_step` : float
- `min_step` : float
- `max_step` : float Limits for the step sizes used by the integrator.

- `order` : int Maximum order used by the integrator, `order <= 12` for Adams, `<= 5` for BDF.

“zvode”

Complex-valued Variable-coefficient Ordinary Differential Equation solver, with fixed-leading-coefficient implementation. It provides implicit Adams method (for non-stiff problems) and a method based on backward differentiation formulas (BDF) (for stiff problems).

Source: <http://www.netlib.org/ode/zvode.f>

Warning: This integrator is not re-entrant. You cannot have two `ode` instances using the “zvode” integrator at the same time.

This integrator accepts the same parameters in `set_integrator` as the “vode” solver.

Note: When using ZVODE for a stiff system, it should only be used for the case in which the function `f` is analytic, that is, when each `f(i)` is an analytic function of each `y(j)`. Analyticity means that the partial derivative `df(i)/dy(j)` is a unique complex number, and this fact is critical in the way ZVODE solves the dense or banded linear systems that arise in the stiff case. For a complex stiff ODE system in which `f` is not analytic, ZVODE is likely to have convergence failures, and for this problem one should instead use DVODE on the equivalent real system (in the real and imaginary parts of `y`).

“lsoda”

Real-valued Variable-coefficient Ordinary Differential Equation solver, with fixed-leading-coefficient implementation. It provides automatic method switching between implicit Adams method (for non-stiff problems) and a method based on backward differentiation formulas (BDF) (for stiff problems).

Source: <http://www.netlib.org/odepack>

Warning: This integrator is not re-entrant. You cannot have two `ode` instances using the “lsoda” integrator at the same time.

This integrator accepts the following parameters in `set_integrator` method of the `ode` class:

- `atol` : float or sequence absolute tolerance for solution
- `rtol` : float or sequence relative tolerance for solution
- `lband` : None or int
- `uband` : None or int Jacobian band width, `jac[i,j] != 0` for `i-lband <= j <= i+uband`. Setting these requires your `jac` routine to return the jacobian in packed format, `jac_packed[i-j+uband, j] = jac[i,j]`.
- `with_jacobian` : bool *Not used*.
- `nsteps` : int Maximum number of (internally defined) steps allowed during one call to the solver.
- `first_step` : float
- `min_step` : float
- `max_step` : float Limits for the step sizes used by the integrator.
- `max_order_ns` : int Maximum order used in the nonstiff case (default 12).
- `max_order_s` : int Maximum order used in the stiff case (default 5).
- `max_hnil` : int Maximum number of messages reporting too small step size (`t + h = t`) (default 0)
- `ixpr` : int Whether to generate extra printing at method switches (default False).

“dopri5”

This is an explicit runge-kutta method of order (4)5 due to Dormand & Prince (with stepsize control and dense output).

Authors:

E. Hairer and G. Wanner Universite de Geneve, Dept. de Mathematiques CH-1211 Geneve 24, Switzerland e-mail: ernst.hairer@math.unige.ch, gerhard.wanner@math.unige.ch

This code is described in [HNW93].

This integrator accepts the following parameters in `set_integrator()` method of the `ode` class:

- `atol` : float or sequence absolute tolerance for solution
- `rtol` : float or sequence relative tolerance for solution
- `nsteps` : int Maximum number of (internally defined) steps allowed during one call to the solver.
- `first_step` : float
- `max_step` : float
- `safety` : float Safety factor on new step selection (default 0.9)
- `ifactor` : float
- `dfactor` : float Maximum factor to increase/decrease step size by in one step
- `beta` : float Beta parameter for stabilised step size control.
- `verbosity` : int Switch for printing messages (< 0 for no messages).

“dop853”

This is an explicit runge-kutta method of order 8(5,3) due to Dormand & Prince (with stepsize control and dense output).

Options and references the same as “dopri5”.

References

[HNW93]

Examples

A problem to integrate and the corresponding jacobian:

```
>>> from scipy.integrate import ode
>>>
>>> y0, t0 = [1.0j, 2.0], 0
>>>
>>> def f(t, y, arg1):
...     return [1j*arg1*y[0] + y[1], -arg1*y[1]**2]
>>> def jac(t, y, arg1):
...     return [[1j*arg1, 1], [0, -arg1*2*y[1]]]
```

The integration:

```
>>> r = ode(f, jac).set_integrator('zvode', method='bdf')
>>> r.set_initial_value(y0, t0).set_f_params(2.0).set_jac_params(2.0)
>>> t1 = 10
>>> dt = 1
>>> while r.successful() and r.t < t1:
...     print(r.t+dt, r.integrate(r.t+dt))
1 [-0.71038232+0.23749653j  0.40000271+0.j          ]
2.0 [0.19098503-0.52359246j  0.22222356+0.j          ]
3.0 [0.47153208+0.52701229j  0.15384681+0.j          ]
4.0 [-0.61905937+0.30726255j  0.11764744+0.j          ]
5.0 [0.02340997-0.61418799j  0.09523835+0.j          ]
6.0 [0.58643071+0.339819j    0.08000018+0.j          ]
7.0 [-0.52070105+0.44525141j  0.06896565+0.j          ]
8.0 [-0.15986733-0.61234476j  0.06060616+0.j          ]
```

(continues on next page)

(continued from previous page)

```
9.0 [0.64850462+0.15048982j 0.05405414+0.j ]
10.0 [-0.38404699+0.56382299j 0.04878055+0.j ]
```

Attributes

- t** [float] Current time.
- y** [ndarray] Current variable values.

Methods

<code>get_return_code(self)</code>	Extracts the return code for the integration to enable better control if the integration fails.
<code>integrate(self, t[, step, relax])</code>	Find $y=y(t)$, set y as an initial condition, and return y .
<code>set_f_params(self, *args)</code>	Set extra parameters for user-supplied function f .
<code>set_initial_value(self, y[, t])</code>	Set initial conditions $y(t) = y$.
<code>set_integrator(self, name, **integrator_params)</code>	Set integrator by name.
<code>set_jac_params(self, *args)</code>	Set extra parameters for user-supplied function jac .
<code>set_solout(self, solout)</code>	Set callable to be called at every successful integration step.
<code>successful(self)</code>	Check if integration was successful.

scipy.integrate.ode.get_return_code

`ode.get_return_code (self)`

Extracts the return code for the integration to enable better control if the integration fails.

In general, a return code > 0 implies success, while a return code < 0 implies failure.

Notes

This section describes possible return codes and their meaning, for available integrators that can be selected by `set_integrator` method.

“vode”

Return Code	Message
2	Integration successful.
-1	Excess work done on this call. (Perhaps wrong MF.)
-2	Excess accuracy requested. (Tolerances too small.)
-3	Illegal input detected. (See printed message.)
-4	Repeated error test failures. (Check all input.)
-5	Repeated convergence failures. (Perhaps bad Jacobian supplied or wrong choice of MF or tolerances.)
-6	Error weight became zero during problem. (Solution component i vanished, and ATOL or $ATOL(i) = 0$.)

“zvode”

Return Code	Message
2	Integration successful.
-1	Excess work done on this call. (Perhaps wrong MF.)
-2	Excess accuracy requested. (Tolerances too small.)
-3	Illegal input detected. (See printed message.)
-4	Repeated error test failures. (Check all input.)
-5	Repeated convergence failures. (Perhaps bad Jacobian supplied or wrong choice of MF or tolerances.)
-6	Error weight became zero during problem. (Solution component i vanished, and $ATOL$ or $ATOL(i) = 0.$)

“dopri5”

Return Code	Message
1	Integration successful.
2	Integration successful (interrupted by solout).
-1	Input is not consistent.
-2	Larger nsteps is needed.
-3	Step size becomes too small.
-4	Problem is probably stiff (interrupted).

“dop853”

Return Code	Message
1	Integration successful.
2	Integration successful (interrupted by solout).
-1	Input is not consistent.
-2	Larger nsteps is needed.
-3	Step size becomes too small.
-4	Problem is probably stiff (interrupted).

“lsoda”

Return Code	Message
2	Integration successful.
-1	Excess work done on this call (perhaps wrong Dfun type).
-2	Excess accuracy requested (tolerances too small).
-3	Illegal input detected (internal error).
-4	Repeated error test failures (internal error).
-5	Repeated convergence failures (perhaps bad Jacobian or tolerances).
-6	Error weight became zero during problem.
-7	Internal workspace insufficient to finish (internal error).

scipy.integrate.ode.integrate

`ode.integrate` (*self*, *t*, *step=False*, *relax=False*)

Find $y=y(t)$, set *y* as an initial condition, and return *y*.

Parameters

t	[float] The endpoint of the integration step.
step	[bool] If True, and if the integrator supports the step method, then perform a single integration step and return. This parameter is provided in order to expose internals of the implementation, and should not be changed from its default value in most cases.
relax	[bool] If True and if the integrator supports the run_relax method, then integrate until $t_1 \geq t$ and return. <code>relax</code> is not referenced if <code>step=True</code> . This parameter is provided in order to expose internals of the implementation, and should not be changed from its default value in most cases.

Returns

y	[float] The integrated value at <i>t</i>
----------	--

scipy.integrate.ode.set_f_params

`ode.set_f_params` (*self*, **args*)

Set extra parameters for user-supplied function *f*.

scipy.integrate.ode.set_initial_value

`ode.set_initial_value` (*self*, *y*, *t=0.0*)

Set initial conditions $y(t) = y$.

scipy.integrate.ode.set_integrator

`ode.set_integrator` (*self*, *name*, ***integrator_params*)

Set integrator by name.

Parameters

name	[str] Name of the integrator.
integrator_params	Additional parameters for the integrator.

scipy.integrate.ode.set_jac_params

`ode.set_jac_params` (*self*, **args*)

Set extra parameters for user-supplied function *jac*.

scipy.integrate.ode.set_solout`ode.set_solout` (*self*, *solout*)

Set callable to be called at every successful integration step.

Parameters

solout [callable] `solout(t, y)` is called at each internal integrator step, `t` is a scalar providing the current independent position `y` is the current solution `y.shape == (n,)` `solout` should return -1 to stop integration otherwise it should return None or 0

scipy.integrate.ode.successful`ode.successful` (*self*)

Check if integration was successful.

scipy.integrate.complex_ode**class** `scipy.integrate.complex_ode` (*f*, *jac=None*)A wrapper of `ode` for complex systems.

This functions similarly as `ode`, but re-maps a complex-valued equation system to a real-valued one before using the integrators.

Parameters

f [callable `f(t, y, *f_args)`] Rhs of the equation. `t` is a scalar, `y.shape == (n,)`. `f_args` is set by calling `set_f_params(*args)`.

jac [callable `jac(t, y, *jac_args)`] Jacobian of the rhs, `jac[i, j] = d f[i] / d y[j]`. `jac_args` is set by calling `set_f_params(*args)`.

ExamplesFor usage examples, see `ode`.**Attributes**

t [float] Current time.

y [ndarray] Current variable values.

Methods

<code>get_return_code</code> (<i>self</i>)	Extracts the return code for the integration to enable better control if the integration fails.
<code>integrate</code> (<i>self</i> , <i>t</i> [, <i>step</i> , <i>relax</i>])	Find <code>y=y(t)</code> , set <code>y</code> as an initial condition, and return <code>y</code> .
<code>set_f_params</code> (<i>self</i> , <i>*args</i>)	Set extra parameters for user-supplied function <code>f</code> .
<code>set_initial_value</code> (<i>self</i> , <i>y</i> [, <i>t</i>])	Set initial conditions <code>y(t) = y</code> .
<code>set_integrator</code> (<i>self</i> , <i>name</i> , <i>**integrator_params</i>)	Set integrator by name.
<code>set_jac_params</code> (<i>self</i> , <i>*args</i>)	Set extra parameters for user-supplied function <code>jac</code> .
<code>set_solout</code> (<i>self</i> , <i>solout</i>)	Set callable to be called at every successful integration step.
<code>successful</code> (<i>self</i>)	Check if integration was successful.

scipy.integrate.complex_ode.get_return_code

`complex_ode.get_return_code` (*self*)

Extracts the return code for the integration to enable better control if the integration fails.

In general, a return code > 0 implies success, while a return code < 0 implies failure.

Notes

This section describes possible return codes and their meaning, for available integrators that can be selected by `set_integrator` method.

“vode”

Return Code	Message
2	Integration successful.
-1	Excess work done on this call. (Perhaps wrong MF.)
-2	Excess accuracy requested. (Tolerances too small.)
-3	Illegal input detected. (See printed message.)
-4	Repeated error test failures. (Check all input.)
-5	Repeated convergence failures. (Perhaps bad Jacobian supplied or wrong choice of MF or tolerances.)
-6	Error weight became zero during problem. (Solution component <i>i</i> vanished, and ATOL or ATOL(<i>i</i>) = 0.)

“zvode”

Return Code	Message
2	Integration successful.
-1	Excess work done on this call. (Perhaps wrong MF.)
-2	Excess accuracy requested. (Tolerances too small.)
-3	Illegal input detected. (See printed message.)
-4	Repeated error test failures. (Check all input.)
-5	Repeated convergence failures. (Perhaps bad Jacobian supplied or wrong choice of MF or tolerances.)
-6	Error weight became zero during problem. (Solution component <i>i</i> vanished, and ATOL or ATOL(<i>i</i>) = 0.)

“dopri5”

Return Code	Message
1	Integration successful.
2	Integration successful (interrupted by solout).
-1	Input is not consistent.
-2	Larger nsteps is needed.
-3	Step size becomes too small.
-4	Problem is probably stiff (interrupted).

“dop853”

Return Code	Message
1	Integration successful.
2	Integration successful (interrupted by solout).
-1	Input is not consistent.
-2	Larger nsteps is needed.
-3	Step size becomes too small.
-4	Problem is probably stiff (interrupted).

“lsoda”

Return Code	Message
2	Integration successful.
-1	Excess work done on this call (perhaps wrong Dfun type).
-2	Excess accuracy requested (tolerances too small).
-3	Illegal input detected (internal error).
-4	Repeated error test failures (internal error).
-5	Repeated convergence failures (perhaps bad Jacobian or tolerances).
-6	Error weight became zero during problem.
-7	Internal workspace insufficient to finish (internal error).

scipy.integrate.complex_ode.integrate

`complex_ode.integrate` (*self*, *t*, *step=False*, *relax=False*)

Find $y=y(t)$, set *y* as an initial condition, and return *y*.

Parameters

t	[float] The endpoint of the integration step.
step	[bool] If True, and if the integrator supports the step method, then perform a single integration step and return. This parameter is provided in order to expose internals of the implementation, and should not be changed from its default value in most cases.
relax	[bool] If True and if the integrator supports the run_relax method, then integrate until $t_1 \geq t$ and return. <code>relax</code> is not referenced if <code>step=True</code> . This parameter is provided in order to expose internals of the implementation, and should not be changed from its default value in most cases.

Returns

y	[float] The integrated value at <i>t</i>
----------	--

scipy.integrate.complex_ode.set_f_params

`complex_ode.set_f_params` (*self*, **args*)

Set extra parameters for user-supplied function *f*.

scipy.integrate.complex_ode.set_initial_value

`complex_ode.set_initial_value` (*self*, *y*, *t=0.0*)
 Set initial conditions $y(t) = y$.

scipy.integrate.complex_ode.set_integrator

`complex_ode.set_integrator` (*self*, *name*, ***integrator_params*)
 Set integrator by name.

Parameters

name [str] Name of the integrator
integrator_params
 Additional parameters for the integrator.

scipy.integrate.complex_ode.set_jac_params

`complex_ode.set_jac_params` (*self*, **args*)
 Set extra parameters for user-supplied function *jac*.

scipy.integrate.complex_ode.set_solout

`complex_ode.set_solout` (*self*, *solout*)
 Set callable to be called at every successful integration step.

Parameters

solout [callable] `solout(t, y)` is called at each internal integrator step, *t* is a scalar providing the current independent position *y* is the current solution `y.shape == (n,)` *solout* should return -1 to stop integration otherwise it should return None or 0

scipy.integrate.complex_ode.successful

`complex_ode.successful` (*self*)
 Check if integration was successful.

6.7.4 Solving boundary value problems for ODE systems

<code>solve_bvp</code> (<i>fun</i> , <i>bc</i> , <i>x</i> , <i>y</i> [], <i>p</i> , <i>S</i> , <i>fun_jac</i> , ...)	Solve a boundary value problem for a system of ODEs.
---	--

scipy.integrate.solve_bvp

`scipy.integrate.solve_bvp` (*fun, bc, x, y, p=None, S=None, fun_jac=None, bc_jac=None, tol=0.001, max_nodes=1000, verbose=0, bc_tol=None*)

Solve a boundary value problem for a system of ODEs.

This function numerically solves a first order system of ODEs subject to two-point boundary conditions:

$$\begin{aligned} dy / dx &= f(x, y, p) + S * y / (x - a), \quad a \leq x \leq b \\ bc(y(a), y(b), p) &= 0 \end{aligned}$$

Here x is a 1-D independent variable, $y(x)$ is an N -D vector-valued function and p is a k -D vector of unknown parameters which is to be found along with $y(x)$. For the problem to be determined, there must be $n + k$ boundary conditions, i.e., bc must be an $(n + k)$ -D function.

The last singular term on the right-hand side of the system is optional. It is defined by an n -by- n matrix S , such that the solution must satisfy $S y(a) = 0$. This condition will be forced during iterations, so it must not contradict boundary conditions. See [2] for the explanation how this term is handled when solving BVPs numerically.

Problems in a complex domain can be solved as well. In this case, y and p are considered to be complex, and f and bc are assumed to be complex-valued functions, but x stays real. Note that f and bc must be complex differentiable (satisfy Cauchy-Riemann equations [4]), otherwise you should rewrite your problem for real and imaginary parts separately. To solve a problem in a complex domain, pass an initial guess for y with a complex data type (see below).

Parameters

- | | |
|----------------|--|
| fun | [callable] Right-hand side of the system. The calling signature is <code>fun(x, y)</code> , or <code>fun(x, y, p)</code> if parameters are present. All arguments are ndarray: x with shape $(m,)$, y with shape (n, m) , meaning that $y[:, i]$ corresponds to $x[i]$, and p with shape $(k,)$. The return value must be an array with shape (n, m) and with the same layout as y . |
| bc | [callable] Function evaluating residuals of the boundary conditions. The calling signature is <code>bc(ya, yb)</code> , or <code>bc(ya, yb, p)</code> if parameters are present. All arguments are ndarray: ya and yb with shape $(n,)$, and p with shape $(k,)$. The return value must be an array with shape $(n + k,)$. |
| x | [array_like, shape $(m,)$] Initial mesh. Must be a strictly increasing sequence of real numbers with $x[0]=a$ and $x[-1]=b$. |
| y | [array_like, shape (n, m)] Initial guess for the function values at the mesh nodes, i th column corresponds to $x[i]$. For problems in a complex domain pass y with a complex data type (even if the initial guess is purely real). |
| p | [array_like with shape $(k,)$ or None, optional] Initial guess for the unknown parameters. If None (default), it is assumed that the problem doesn't depend on any parameters. |
| S | [array_like with shape (n, n) or None] Matrix defining the singular term. If None (default), the problem is solved without the singular term. |
| fun_jac | [callable or None, optional] Function computing derivatives of f with respect to y and p . The calling signature is <code>fun_jac(x, y)</code> , or <code>fun_jac(x, y, p)</code> if parameters are present. The return must contain 1 or 2 elements in the following order: <ul style="list-style-type: none"> <code>df_dy</code>: array_like with shape (n, n, m), where an element (i, j, q) equals to $d f_i(x_q, y_q, p) / d (y_q)_j$. <code>df_dp</code>: array_like with shape (n, k, m), where an element (i, j, q) equals to $d f_i(x_q, y_q, p) / d p_j$. Here q numbers nodes at which x and y are defined, whereas i and j number vector components. If the problem is solved without unknown parameters, <code>df_dp</code> should not be returned. If <code>fun_jac</code> is None (default), the derivatives will be estimated by the forward finite differences. |
| bc_jac | [callable or None, optional] Function computing derivatives of bc with respect to ya, yb , and p . The calling signature is <code>bc_jac(ya, yb)</code> , or <code>bc_jac(ya, yb, p)</code> if parameters are present. The return must contain 2 or 3 elements in the following order: |

- `dbc_dya` : array_like with shape (n, n), where an element (i, j) equals to $d bc_i(ya, yb, p) / d ya_j$.
- `dbc_dyb` : array_like with shape (n, n), where an element (i, j) equals to $d bc_i(ya, yb, p) / d yb_j$.
- `dbc_dp` : array_like with shape (n, k), where an element (i, j) equals to $d bc_i(ya, yb, p) / d p_j$.

If the problem is solved without unknown parameters, `dbc_dp` should not be returned.

If `bc_jac` is None (default), the derivatives will be estimated by the forward finite differences. If `tol` is [float, optional] Desired tolerance of the solution. If we define $r = y' - f(x, y)$, where `y` is the found solution, then the solver tries to achieve on each mesh interval $norm(r / (1 + abs(f))) < tol$, where `norm` is estimated in a root mean squared sense (using a numerical quadrature formula). Default is 1e-3.

max_nodes

[int, optional] Maximum allowed number of the mesh nodes. If exceeded, the algorithm terminates. Default is 1000.

verbose

[[0, 1, 2], optional] Level of algorithm's verbosity:

- 0 (default) : work silently.
- 1 : display a termination report.
- 2 : display progress during iterations.

bc_tol

[float, optional] Desired absolute tolerance for the boundary condition residuals: `bc` value should satisfy $abs(bc) < bc_tol$ component-wise. Equals to `tol` by default. Up to 10 iterations are allowed to achieve this tolerance.

Returns

Bunch object with the following fields defined:

- sol** [PPoly] Found solution for `y` as `scipy.interpolate.PPoly` instance, a C1 continuous cubic spline.
- p** [ndarray or None, shape (k,)] Found parameters. None, if the parameters were not present in the problem.
- x** [ndarray, shape (m,)] Nodes of the final mesh.
- y** [ndarray, shape (n, m)] Solution values at the mesh nodes.
- yp** [ndarray, shape (n, m)] Solution derivatives at the mesh nodes.
- rms_residuals** [ndarray, shape (m - 1,)] RMS values of the relative residuals over each mesh interval (see the description of `tol` parameter).
- niter** [int] Number of completed iterations.
- status** [int] Reason for algorithm termination:
- 0: The algorithm converged to the desired accuracy.
 - 1: The maximum number of mesh nodes is exceeded.
 - 2: A singular Jacobian encountered when solving the collocation system.
- message** [string] Verbal description of the termination reason.
- success** [bool] True if the algorithm converged to the desired accuracy (`status=0`).

Notes

This function implements a 4th order collocation algorithm with the control of residuals similar to [1]. A collocation system is solved by a damped Newton method with an affine-invariant criterion function as described in [3].

Note that in [1] integral residuals are defined without normalization by interval lengths. So, their definition is different by a multiplier of $h*0.5$ (h is an interval length) from the definition used here.

New in version 0.18.0.

References

[1], [2], [3], [4]

Examples

In the first example, we solve Bratu's problem:

```
y'' + k * exp(y) = 0
y(0) = y(1) = 0
```

for $k = 1$.

We rewrite the equation as a first-order system and implement its right-hand side evaluation:

```
y1' = y2
y2' = -exp(y1)
```

```
>>> def fun(x, y):
...     return np.vstack((y[1], -np.exp(y[0])))
```

Implement evaluation of the boundary condition residuals:

```
>>> def bc(ya, yb):
...     return np.array([ya[0], yb[0]])
```

Define the initial mesh with 5 nodes:

```
>>> x = np.linspace(0, 1, 5)
```

This problem is known to have two solutions. To obtain both of them, we use two different initial guesses for y . We denote them by subscripts a and b.

```
>>> y_a = np.zeros((2, x.size))
>>> y_b = np.zeros((2, x.size))
>>> y_b[0] = 3
```

Now we are ready to run the solver.

```
>>> from scipy.integrate import solve_bvp
>>> res_a = solve_bvp(fun, bc, x, y_a)
>>> res_b = solve_bvp(fun, bc, x, y_b)
```


Let's plot the two found solutions. We take an advantage of having the solution in a spline form to produce a smooth plot.

```
>>> x_plot = np.linspace(0, 1, 100)
>>> y_plot_a = res_a.sol(x_plot)[0]
>>> y_plot_b = res_b.sol(x_plot)[0]
>>> import matplotlib.pyplot as plt
>>> plt.plot(x_plot, y_plot_a, label='y_a')
>>> plt.plot(x_plot, y_plot_b, label='y_b')
>>> plt.legend()
>>> plt.xlabel("x")
```

(continues on next page)

(continued from previous page)

```
>>> plt.ylabel("y")
>>> plt.show()
```



We see that the two solutions have similar shape, but differ in scale significantly.

In the second example, we solve a simple Sturm-Liouville problem:

```
y'' + k**2 * y = 0
y(0) = y(1) = 0
```

It is known that a non-trivial solution $y = A \cdot \sin(k \cdot x)$ is possible for $k = \pi \cdot n$, where n is an integer. To establish the normalization constant $A = 1$ we add a boundary condition:

```
y'(0) = k
```

Again, we rewrite our equation as a first-order system and implement its right-hand side evaluation:

```
y1' = y2
y2' = -k**2 * y1
```

```
>>> def fun(x, y, p):
...     k = p[0]
...     return np.vstack((y[1], -k**2 * y[0]))
```

Note that parameters p are passed as a vector (with one element in our case).

Implement the boundary conditions:

```
>>> def bc(ya, yb, p):
...     k = p[0]
...     return np.array([ya[0], yb[0], ya[1] - k])
```

Set up the initial mesh and guess for y . We aim to find the solution for $k = 2 \cdot \pi$, to achieve that we set values of y to approximately follow $\sin(2 \cdot \pi \cdot x)$:

```
>>> x = np.linspace(0, 1, 5)
>>> y = np.zeros((2, x.size))
>>> y[0, 1] = 1
>>> y[0, 3] = -1
```

Run the solver with 6 as an initial guess for k.


```
>>> sol = solve_bvp(fun, bc, x, y, p=[6])
```

We see that the found k is approximately correct:

```
>>> sol.p[0]
6.28329460046
```

And, finally, plot the solution to see the anticipated sinusoid:

```
>>> x_plot = np.linspace(0, 1, 100)
>>> y_plot = sol.sol(x_plot)[0]
>>> plt.plot(x_plot, y_plot)
>>> plt.xlabel("x")
>>> plt.ylabel("y")
>>> plt.show()
```



6.8 Interpolation (`scipy.interpolate`)

Sub-package for objects used in interpolation.

As listed below, this sub-package contains spline functions and classes, 1-D and multidimensional (univariate and multivariate) interpolation classes, Lagrange and Taylor polynomial interpolators, and wrappers for `FITPACK` and `DFITPACK` functions.

6.8.1 Univariate interpolation

<code>interp1d(x, y[, kind, axis, copy, ...])</code>	Interpolate a 1-D function.
<code>BarycentricInterpolator(xi[, yi, axis])</code>	The interpolating polynomial for a set of points
<code>KroghInterpolator(xi, yi[, axis])</code>	Interpolating polynomial for a set of points.
<code>barycentric_interpolate(xi, yi, x[, axis])</code>	Convenience function for polynomial interpolation.
<code>krogh_interpolate(xi, yi, x[, der, axis])</code>	Convenience function for polynomial interpolation.
<code>pchip_interpolate(xi, yi, x[, der, axis])</code>	Convenience function for pchip interpolation.
<code>CubicHermiteSpline(x, y, dydx[, axis, ...])</code>	Piecewise-cubic interpolator matching values and first derivatives.
<code>PchipInterpolator(x, y[, axis, extrapolate])</code>	PCHIP 1-D monotonic cubic interpolation.
<code>Akima1DInterpolator(x, y[, axis])</code>	Akima interpolator
<code>CubicSpline(x, y[, axis, bc_type, extrapolate])</code>	Cubic spline data interpolator.
<code>PPoly(c, x[, extrapolate, axis])</code>	Piecewise polynomial in terms of coefficients and break-points
<code>BPPoly(c, x[, extrapolate, axis])</code>	Piecewise polynomial in terms of coefficients and break-points.

scipy.interpolate.interp1d

class `scipy.interpolate.interp1d` (*x*, *y*, *kind*='linear', *axis*=- 1, *copy*=True, *bounds_error*=None, *fill_value*=nan, *assume_sorted*=False)

Interpolate a 1-D function.

x and *y* are arrays of values used to approximate some function $f: y = f(x)$. This class returns a function whose call method uses interpolation to find the value of new points.

Parameters

- x** [(N,) array_like] A 1-D array of real values.
- y** [(...,N,...) array_like] A N-D array of real values. The length of *y* along the interpolation axis must be equal to the length of *x*.
- kind** [str or int, optional] Specifies the kind of interpolation as a string or as an integer specifying the order of the spline interpolator to use. The string has to be one of 'linear', 'nearest', 'nearest-up', 'zero', 'slinear', 'quadratic', 'cubic', 'previous', or 'next'. 'zero', 'slinear', 'quadratic' and 'cubic' refer to a spline interpolation of zeroth, first, second or third order; 'previous' and 'next' simply return the previous or next value of the point; 'nearest-up' and 'nearest' differ when interpolating half-integers (e.g. 0.5, 1.5) in that 'nearest-up' rounds up and 'nearest' rounds down. Default is 'linear'.
- axis** [int, optional] Specifies the axis of *y* along which to interpolate. Interpolation defaults to the last axis of *y*.
- copy** [bool, optional] If True, the class makes internal copies of *x* and *y*. If False, references to *x* and *y* are used. The default is to copy.
- bounds_error** [bool, optional] If True, a ValueError is raised any time interpolation is attempted on a value outside of the range of *x* (where extrapolation is necessary). If False, out of bounds values are assigned *fill_value*. By default, an error is raised unless *fill_value*="extrapolate".
- fill_value** [array-like or (array-like, array_like) or "extrapolate", optional]
 - if a ndarray (or float), this value will be used to fill in for requested points outside of the data range. If not provided, then the default is NaN. The array-like must broadcast properly to the dimensions of the non-interpolation axes.

- If a two-element tuple, then the first element is used as a fill value for $x_{\text{new}} < x[0]$ and the second element is used for $x_{\text{new}} > x[-1]$. Anything that is not a 2-element tuple (e.g., list or ndarray, regardless of shape) is taken to be a single array-like argument meant to be used for both bounds as `below, above = fill_value, fill_value`. New in version 0.17.0.
- If “extrapolate”, then points outside the data range will be extrapolated. New in version 0.17.0.

assume_sorted

[bool, optional] If False, values of x can be in any order and they are sorted first. If True, x has to be an array of monotonically increasing values.

See also:

splrep, splev

Spline interpolation/smoothing based on FITPACK.

UnivariateSpline

An object-oriented wrapper of the FITPACK routines.

interp2d

2-D interpolation

Notes

Calling *interp1d* with NaNs present in input values results in undefined behaviour.

Input values x and y must be convertible to *float* values like *int* or *float*.

Examples


```
>>> import matplotlib.pyplot as plt
>>> from scipy import interpolate
>>> x = np.arange(0, 10)
>>> y = np.exp(-x/3.0)
>>> f = interpolate.interp1d(x, y)
```

```
>>> xnew = np.arange(0, 9, 0.1)
>>> ynew = f(xnew) # use interpolation function returned by `interp1d`
>>> plt.plot(x, y, 'o', xnew, ynew, '-')
>>> plt.show()
```

Attributes

fill_value

The fill value.



Methods

<code>__call__(self, x)</code>	Evaluate the interpolant
--------------------------------	--------------------------

`scipy.interpolate.interp1d.__call__`

`interp1d.__call__(self, x)`
 Evaluate the interpolant

Parameters

x [array_like] Points to evaluate the interpolant at.

Returns

y [array_like] Interpolated values. Shape is determined by replacing the interpolation axis in the original array with the shape of x.

Notes

Input values *x* must be convertible to *float* values like *int* or *float*.

`scipy.interpolate.BarycentricInterpolator`

class `scipy.interpolate.BarycentricInterpolator` (*xi, yi=None, axis=0*)

The interpolating polynomial for a set of points

Constructs a polynomial that passes through a given set of points. Allows evaluation of the polynomial, efficient changing of the y values to be interpolated, and updating by adding more x values. For reasons of numerical stability, this function does not compute the coefficients of the polynomial.

The values *yi* need to be provided before the function is evaluated, but none of the preprocessing depends on them, so rapid updates are possible.

Parameters

xi [array_like] 1-D array of x coordinates of the points the polynomial should pass through
yi [array_like, optional] The y coordinates of the points the polynomial should pass through. If None, the y values will be supplied later via the *set_y* method.
axis [int, optional] Axis in the *yi* array corresponding to the x-coordinate values.

Notes

Methods

<code>__call__(self, x)</code>	Evaluate the interpolating polynomial at the points <code>x</code>
<code>add_xi(self, xi[, yi])</code>	Add more <code>x</code> values to the set to be interpolated
<code>set_yi(self, yi[, axis])</code>	Update the <code>y</code> values to be interpolated

`scipy.interpolate.BarycentricInterpolator.__call__`

`BarycentricInterpolator.__call__(self, x)`
Evaluate the interpolating polynomial at the points `x`

Parameters

x [array_like] Points to evaluate the interpolant at.

Returns

y [array_like] Interpolated values. Shape is determined by replacing the interpolation axis in the original array with the shape of `x`.

Notes

Currently the code computes an outer product between `x` and the weights, that is, it constructs an intermediate array of size `N` by `len(x)`, where `N` is the degree of the polynomial.

`scipy.interpolate.BarycentricInterpolator.add_xi`

`BarycentricInterpolator.add_xi(self, xi, yi=None)`
Add more `x` values to the set to be interpolated

The barycentric interpolation algorithm allows easy updating by adding more points for the polynomial to pass through.

Parameters

xi [array_like] The `x` coordinates of the points that the polynomial should pass through.

yi [array_like, optional] The `y` coordinates of the points the polynomial should pass through. Should have shape `(xi.size, R)`; if `R > 1` then the polynomial is vector-valued. If `yi` is not given, the `y` values will be supplied later. `yi` should be given if and only if the interpolator has `y` values specified.

`scipy.interpolate.BarycentricInterpolator.set_yi`

`BarycentricInterpolator.set_yi(self, yi, axis=None)`
Update the `y` values to be interpolated

The barycentric interpolation algorithm requires the calculation of weights, but these depend only on the `xi`. The `yi` can be changed at any time.

Parameters

yi [array_like] The `y` coordinates of the points the polynomial should pass through. If `None`, the `y` values will be supplied later.

axis [int, optional] Axis in the `yi` array corresponding to the `x`-coordinate values.

scipy.interpolate.KroghInterpolator

class `scipy.interpolate.KroghInterpolator` (*xi, yi, axis=0*)

Interpolating polynomial for a set of points.

The polynomial passes through all the pairs (xi,yi). One may additionally specify a number of derivatives at each point xi; this is done by repeating the value xi and specifying the derivatives as successive yi values.

Allows evaluation of the polynomial and all its derivatives. For reasons of numerical stability, this function does not compute the coefficients of the polynomial, although they can be obtained by evaluating all the derivatives.

Parameters

xi	[array_like, length N] Known x-coordinates. Must be sorted in increasing order.
yi	[array_like] Known y-coordinates. When an xi occurs two or more times in a row, the corresponding yi's represent derivative values.
axis	[int, optional] Axis in the yi array corresponding to the x-coordinate values.

Notes

Be aware that the algorithms implemented here are not necessarily the most numerically stable known. Moreover, even in a world of exact computation, unless the x coordinates are chosen very carefully - Chebyshev zeros (e.g., $\cos(i\pi/n)$) are a good choice - polynomial interpolation itself is a very ill-conditioned process due to the Runge phenomenon. In general, even with well-chosen x values, degrees higher than about thirty cause problems with numerical instability in this code.

Based on [1].

References

[1]

Examples

To produce a polynomial that is zero at 0 and 1 and has derivative 2 at 0, call

```
>>> from scipy.interpolate import KroghInterpolator
>>> KroghInterpolator([0, 0, 1], [0, 2, 0])
```

This constructs the quadratic $2X^2-2X$. The derivative condition is indicated by the repeated zero in the xi array; the corresponding yi values are 0, the function value, and 2, the derivative value.

For another example, given xi, yi, and a derivative ypi for each point, appropriate arrays can be constructed as:

```
>>> xi = np.linspace(0, 1, 5)
>>> yi, ypi = np.random.rand(2, 5)
>>> xi_k, yi_k = np.repeat(xi, 2), np.ravel(np.dstack((yi, ypi)))
>>> KroghInterpolator(xi_k, yi_k)
```

To produce a vector-valued polynomial, supply a higher-dimensional array for yi:

```
>>> KroghInterpolator([0, 1], [[2, 3], [4, 5]])
```

This constructs a linear polynomial giving (2,3) at 0 and (4,5) at 1.

Attributes

dtype**Methods**

<code>__call__(self, x)</code>	Evaluate the interpolant
<code>derivative(self, x[, der])</code>	Evaluate one derivative of the polynomial at the point x
<code>derivatives(self, x[, der])</code>	Evaluate many derivatives of the polynomial at the point x

scipy.interpolate.KroghInterpolator.__call__

`KroghInterpolator.__call__(self, x)`
Evaluate the interpolant

Parameters

x [array_like] Points to evaluate the interpolant at.

Returns

y [array_like] Interpolated values. Shape is determined by replacing the interpolation axis in the original array with the shape of x.

Notes

Input values *x* must be convertible to *float* values like *int* or *float*.

scipy.interpolate.KroghInterpolator.derivative

`KroghInterpolator.derivative(self, x, der=1)`
Evaluate one derivative of the polynomial at the point x

Parameters

x [array_like] Point or points at which to evaluate the derivatives

der [integer, optional] Which derivative to extract. This number includes the function value as 0th derivative.

Returns

d [ndarray] Derivative interpolated at the x-points. Shape of d is determined by replacing the interpolation axis in the original array with the shape of x.

Notes

This is computed by evaluating all derivatives up to the desired one (using `self.derivatives()`) and then discarding the rest.

scipy.interpolate.KroghInterpolator.derivatives

`KroghInterpolator.derivatives` (*self*, *x*, *der=None*)

Evaluate many derivatives of the polynomial at the point *x*

Produce an array of all derivative values at the point *x*.

Parameters

x [array_like] Point or points at which to evaluate the derivatives
der [int or None, optional] How many derivatives to extract; None for all potentially nonzero derivatives (that is a number equal to the number of points). This number includes the function value as 0th derivative.

Returns

d [ndarray] Array with derivatives; *d*[*j*] contains the *j*th derivative. Shape of *d*[*j*] is determined by replacing the interpolation axis in the original array with the shape of *x*.

Examples

```
>>> from scipy.interpolate import KroghInterpolator
>>> KroghInterpolator([0,0,0],[1,2,3]).derivatives(0)
array([1.0,2.0,3.0])
>>> KroghInterpolator([0,0,0],[1,2,3]).derivatives([0,0])
array([[1.0,1.0],
       [2.0,2.0],
       [3.0,3.0]])
```

scipy.interpolate.barycentric_interpolate

`scipy.interpolate.barycentric_interpolate` (*xi*, *yi*, *x*, *axis=0*)

Convenience function for polynomial interpolation.

Constructs a polynomial that passes through a given set of points, then evaluates the polynomial. For reasons of numerical stability, this function does not compute the coefficients of the polynomial.

This function uses a “barycentric interpolation” method that treats the problem as a special case of rational function interpolation. This algorithm is quite stable, numerically, but even in a world of exact computation, unless the *x* coordinates are chosen very carefully - Chebyshev zeros (e.g., $\cos(i\pi/n)$) are a good choice - polynomial interpolation itself is a very ill-conditioned process due to the Runge phenomenon.

Parameters

xi [array_like] 1-D array of *x* coordinates of the points the polynomial should pass through
yi [array_like] The *y* coordinates of the points the polynomial should pass through.
x [scalar or array_like] Points to evaluate the interpolator at.
axis [int, optional] Axis in the *yi* array corresponding to the *x*-coordinate values.

Returns

y [scalar or array_like] Interpolated values. Shape is determined by replacing the interpolation axis in the original array with the shape of *x*.

See also:

BarycentricInterpolator

Bary centric interpolator


Notes

Construction of the interpolation weights is a relatively slow process. If you want to call this many times with the same x_i (but possibly varying y_i or x) you should use the class *BarycentricInterpolator*. This is what this function uses internally.

Examples

We can interpolate 2D observed data using barycentric interpolation:

```
>>> import matplotlib.pyplot as plt
>>> from scipy.interpolate import barycentric_interpolate
>>> x_observed = np.linspace(0.0, 10.0, 11)
>>> y_observed = np.sin(x_observed)
>>> x = np.linspace(min(x_observed), max(x_observed), num=100)
>>> y = barycentric_interpolate(x_observed, y_observed, x)
>>> plt.plot(x_observed, y_observed, "o", label="observation")
>>> plt.plot(x, y, label="barycentric interpolation")
>>> plt.legend()
>>> plt.show()
```



scipy.interpolate.krogh_interpolate

`scipy.interpolate.krogh_interpolate(xi, yi, x, der=0, axis=0)`

Convenience function for polynomial interpolation.

See *KroghInterpolator* for more details.

Parameters

- xi** [array_like] Known x-coordinates.
- yi** [array_like] Known y-coordinates, of shape $(xi.size, R)$. Interpreted as vectors of length R , or scalars if $R=1$.
- x** [array_like] Point or points at which to evaluate the derivatives.

- der** [int or list, optional] How many derivatives to extract; None for all potentially nonzero derivatives (that is a number equal to the number of points), or a list of derivatives to extract. This number includes the function value as 0th derivative.
- axis** [int, optional] Axis in the *yi* array corresponding to the *x*-coordinate values.

Returns

- d** [ndarray] If the interpolator's values are R-D then the returned array will be the number of derivatives by N by R. If *x* is a scalar, the middle dimension will be dropped; if the *yi* are scalars then the last dimension will be dropped.

See also:

KroghInterpolator

Krogh interpolator

Notes

Construction of the interpolating polynomial is a relatively expensive process. If you want to evaluate it repeatedly consider using the class *KroghInterpolator* (which is what this function uses).

Examples

We can interpolate 2D observed data using krogh interpolation:

```
>>> import matplotlib.pyplot as plt
>>> from scipy.interpolate import krogh_interpolate
>>> x_observed = np.linspace(0.0, 10.0, 11)
>>> y_observed = np.sin(x_observed)
>>> x = np.linspace(min(x_observed), max(x_observed), num=100)
>>> y = krogh_interpolate(x_observed, y_observed, x)
>>> plt.plot(x_observed, y_observed, "o", label="observation")
>>> plt.plot(x, y, label="krogh interpolation")
>>> plt.legend()
>>> plt.show()
```

scipy.interpolate.pchip_interpolate

`scipy.interpolate.pchip_interpolate(xi, yi, x, der=0, axis=0)`


Convenience function for pchip interpolation.

xi and *yi* are arrays of values used to approximate some function *f*, with $y_i = f(x_i)$. The interpolant uses monotonic cubic splines to find the value of new points *x* and the derivatives there.

See *scipy.interpolate.PchipInterpolator* for details.

Parameters

- xi** [array_like] A sorted list of *x*-coordinates, of length N.
- yi** [array_like] A 1-D array of real values. *yi*'s length along the interpolation axis must be equal to the length of *xi*. If N-D array, use *axis* parameter to select correct axis.
- x** [scalar or array_like] Of length M.
- der** [int or list, optional] Derivatives to extract. The 0th derivative can be included to return the function value.



axis [int, optional] Axis in the yi array corresponding to the x-coordinate values.

Returns

y [scalar or array_like] The result, of length R or length M or M by R,

See also:


PchipInterpolator

PCHIP 1-D monotonic cubic interpolator.

Examples

We can interpolate 2D observed data using pchip interpolation:

```
>>> import matplotlib.pyplot as plt
>>> from scipy.interpolate import pchip_interpolate
>>> x_observed = np.linspace(0.0, 10.0, 11)
>>> y_observed = np.sin(x_observed)
>>> x = np.linspace(min(x_observed), max(x_observed), num=100)
>>> y = pchip_interpolate(x_observed, y_observed, x)
>>> plt.plot(x_observed, y_observed, "o", label="observation")
>>> plt.plot(x, y, label="pchip interpolation")
>>> plt.legend()
>>> plt.show()
```



scipy.interpolate.CubicHermiteSpline

class `scipy.interpolate.CubicHermiteSpline` (*x*, *y*, *dydx*, *axis=0*, *extrapolate=None*)
 Piecewise-cubic interpolator matching values and first derivatives.

The result is represented as a *PPoly* instance.

Parameters

- x** [array_like, shape (n,)] 1-D array containing values of the independent variable. Values must be real, finite and in strictly increasing order.
- y** [array_like] Array containing values of the dependent variable. It can have arbitrary number of dimensions, but the length along *axis* (see below) must match the length of *x*. Values must be finite.
- dydx** [array_like] Array containing derivatives of the dependent variable. It can have arbitrary number of dimensions, but the length along *axis* (see below) must match the length of *x*. Values must be finite.
- axis** [int, optional] Axis along which *y* is assumed to be varying. Meaning that for $x[i]$ the corresponding values are `np.take(y, i, axis=axis)`. Default is 0.
- extrapolate** [{bool, 'periodic', None}, optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. If None (default), it is set to True.

See also:

Akima1DInterpolator

Akima 1D interpolator.

PchipInterpolator

PCHIP 1-D monotonic cubic interpolator.

CubicSpline

Cubic spline data interpolator.

PPoly

Piecewise polynomial in terms of coefficients and breakpoints

Notes

If you want to create a higher-order spline matching higher-order derivatives, use `BPoly.from_derivatives`.

References

[1]

Attributes

x	[ndarray, shape (n,)] Breakpoints. The same <code>x</code> which was passed to the constructor.
c	[ndarray, shape (4, n-1, ...)] Coefficients of the polynomials on each segment. The trailing dimensions match the dimensions of <code>y</code> , excluding <code>axis</code> . For example, if <code>y</code> is 1-D, then <code>c[k, i]</code> is a coefficient for $(x-x[i])^{(3-k)}$ on the segment between <code>x[i]</code> and <code>x[i+1]</code> .
axis	[int] Interpolation axis. The same axis which was passed to the constructor.

Methods

<code>__call__(self, x[, nu, extrapolate])</code>	Evaluate the piecewise polynomial or its derivative.
<code>derivative(self[, nu])</code>	Construct a new piecewise polynomial representing the derivative.
<code>antiderivative(self[, nu])</code>	Construct a new piecewise polynomial representing the antiderivative.
<code>integrate(self, a, b[, extrapolate])</code>	Compute a definite integral over a piecewise polynomial.
<code>roots(self[, discontinuity, extrapolate])</code>	Find real roots of the the piecewise polynomial.

scipy.interpolate.CubicHermiteSpline.__call__

`CubicHermiteSpline.__call__(self, x, nu=0, extrapolate=None)`

Evaluate the piecewise polynomial or its derivative.

Parameters

x	[array_like] Points to evaluate the interpolant at.
nu	[int, optional] Order of derivative to evaluate. Must be non-negative.
extrapolate	[{bool, 'periodic', None}, optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. If None (default), use <code>self.extrapolate</code> .

Returns

y	[array_like] Interpolated values. Shape is determined by replacing the interpolation axis in the original array with the shape of <code>x</code> .
----------	--

Notes

Derivatives are evaluated piecewise for each polynomial segment, even if the polynomial is not differentiable at the breakpoints. The polynomial intervals are considered half-open, $[a, b)$, except for the last interval which is closed $[a, b]$.

`scipy.interpolate.CubicHermiteSpline.derivative`

`CubicHermiteSpline.derivative` (*self*, *nu=1*)

Construct a new piecewise polynomial representing the derivative.

Parameters

nu [int, optional] Order of derivative to evaluate. Default is 1, i.e., compute the first derivative. If negative, the antiderivative is returned.

Returns

pp [PPoly] Piecewise polynomial of order $k_2 = k - n$ representing the derivative of this polynomial.

Notes

Derivatives are evaluated piecewise for each polynomial segment, even if the polynomial is not differentiable at the breakpoints. The polynomial intervals are considered half-open, $[a, b)$, except for the last interval which is closed $[a, b]$.

`scipy.interpolate.CubicHermiteSpline.antiderivative`

`CubicHermiteSpline.antiderivative` (*self*, *nu=1*)

Construct a new piecewise polynomial representing the antiderivative.

Antiderivative is also the indefinite integral of the function, and derivative is its inverse operation.

Parameters

nu [int, optional] Order of antiderivative to evaluate. Default is 1, i.e., compute the first integral. If negative, the derivative is returned.

Returns

pp [PPoly] Piecewise polynomial of order $k_2 = k + n$ representing the antiderivative of this polynomial.

Notes

The antiderivative returned by this function is continuous and continuously differentiable to order $n-1$, up to floating point rounding error.

If antiderivative is computed and `self.extrapolate='periodic'`, it will be set to `False` for the returned instance. This is done because the antiderivative is no longer periodic and its correct evaluation outside of the initially given x interval is difficult.

scipy.interpolate.CubicHermiteSpline.integrate

`CubicHermiteSpline.integrate` (*self*, *a*, *b*, *extrapolate=None*)

Compute a definite integral over a piecewise polynomial.

Parameters

- a** [float] Lower integration bound
- b** [float] Upper integration bound
- extrapolate** [{bool, 'periodic', None}, optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. If None (default), use *self.extrapolate*.

Returns

- ig** [array_like] Definite integral of the piecewise polynomial over [a, b]

scipy.interpolate.CubicHermiteSpline.roots

`CubicHermiteSpline.roots` (*self*, *discontinuity=True*, *extrapolate=None*)

Find real roots of the the piecewise polynomial.

Parameters

- discontinuity** [bool, optional] Whether to report sign changes across discontinuities at breakpoints as roots.
- extrapolate** [{bool, 'periodic', None}, optional] If bool, determines whether to return roots from the polynomial extrapolated based on first and last intervals, 'periodic' works the same as False. If None (default), use *self.extrapolate*.

Returns

- roots** [ndarray] Roots of the polynomial(s).
If the PPoly object describes multiple polynomials, the return value is an object array whose each element is an ndarray containing the roots.

See also:

[*PPoly.solve*](#)

scipy.interpolate.PchipInterpolator

class `scipy.interpolate.PchipInterpolator` (*x*, *y*, *axis=0*, *extrapolate=None*)

PCHIP 1-D monotonic cubic interpolation.

x and *y* are arrays of values used to approximate some function *f*, with $y = f(x)$. The interpolant uses monotonic cubic splines to find the value of new points. (PCHIP stands for Piecewise Cubic Hermite Interpolating Polynomial).

Parameters

- x** [ndarray] A 1-D array of monotonically increasing real values. *x* cannot include duplicate values (otherwise *f* is overspecified)
- y** [ndarray] A 1-D array of real values. *y*'s length along the interpolation axis must be equal to the length of *x*. If N-D array, use *axis* parameter to select correct axis.
- axis** [int, optional] Axis in the *y* array corresponding to the *x*-coordinate values.

extrapolate

[bool, optional] Whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs.

See also:

CubicHermiteSpline

Piecewise-cubic interpolator.

Akima1DInterpolator

Akima 1D interpolator.

CubicSpline

Cubic spline data interpolator.

PPoly

Piecewise polynomial in terms of coefficients and breakpoints.

Notes

The interpolator preserves monotonicity in the interpolation data and does not overshoot if the data is not smooth.

The first derivatives are guaranteed to be continuous, but the second derivatives may jump at x_k .

Determines the derivatives at the points x_k , f'_k , by using PCHIP algorithm [1].

Let $h_k = x_{k+1} - x_k$, and $d_k = (y_{k+1} - y_k)/h_k$ are the slopes at internal points x_k . If the signs of d_k and d_{k-1} are different or either of them equals zero, then $f'_k = 0$. Otherwise, it is given by the weighted harmonic mean

$$\frac{w_1 + w_2}{f'_k} = \frac{w_1}{d_{k-1}} + \frac{w_2}{d_k}$$

where $w_1 = 2h_k + h_{k-1}$ and $w_2 = h_k + 2h_{k-1}$.

The end slopes are set using a one-sided scheme [2].

References

[1], [2]

Attributes

- axis**
- c**
- extrapolate**
- x**

Methods

<code>__call__(self, x[, nu, extrapolate])</code>	Evaluate the piecewise polynomial or its derivative.
<code>derivative(self[, nu])</code>	Construct a new piecewise polynomial representing the derivative.
<code>antiderivative(self[, nu])</code>	Construct a new piecewise polynomial representing the antiderivative.
<code>roots(self[, discontinuity, extrapolate])</code>	Find real roots of the the piecewise polynomial.

scipy.interpolate.PchipInterpolator.__call__

`PchipInterpolator.__call__(self, x, nu=0, extrapolate=None)`

Evaluate the piecewise polynomial or its derivative.

Parameters

- x** [array_like] Points to evaluate the interpolant at.
- nu** [int, optional] Order of derivative to evaluate. Must be non-negative.
- extrapolate** [{bool, 'periodic', None}, optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. If None (default), use *self.extrapolate*.

Returns

- y** [array_like] Interpolated values. Shape is determined by replacing the interpolation axis in the original array with the shape of x.

Notes

Derivatives are evaluated piecewise for each polynomial segment, even if the polynomial is not differentiable at the breakpoints. The polynomial intervals are considered half-open, $[a, b)$, except for the last interval which is closed $[a, b]$.

scipy.interpolate.PchipInterpolator.derivative

`PchipInterpolator.derivative(self, nu=1)`

Construct a new piecewise polynomial representing the derivative.

Parameters

- nu** [int, optional] Order of derivative to evaluate. Default is 1, i.e., compute the first derivative. If negative, the antiderivative is returned.

Returns

- pp** [PPoly] Piecewise polynomial of order $k_2 = k - n$ representing the derivative of this polynomial.

Notes

Derivatives are evaluated piecewise for each polynomial segment, even if the polynomial is not differentiable at the breakpoints. The polynomial intervals are considered half-open, $[a, b)$, except for the last interval which is closed $[a, b]$.

`scipy.interpolate.PchipInterpolator.antiderivative`

`PchipInterpolator.antiderivative` (*self*, *nu=1*)

Construct a new piecewise polynomial representing the antiderivative.

Antiderivative is also the indefinite integral of the function, and derivative is its inverse operation.

Parameters

nu [int, optional] Order of antiderivative to evaluate. Default is 1, i.e., compute the first integral. If negative, the derivative is returned.

Returns

pp [PPoly] Piecewise polynomial of order $k_2 = k + n$ representing the antiderivative of this polynomial.

Notes

The antiderivative returned by this function is continuous and continuously differentiable to order $n-1$, up to floating point rounding error.

If antiderivative is computed and `self.extrapolate='periodic'`, it will be set to `False` for the returned instance. This is done because the antiderivative is no longer periodic and its correct evaluation outside of the initially given x interval is difficult.

`scipy.interpolate.PchipInterpolator.roots`

`PchipInterpolator.roots` (*self*, *discontinuity=True*, *extrapolate=None*)

Find real roots of the the piecewise polynomial.

Parameters

discontinuity

[bool, optional] Whether to report sign changes across discontinuities at breakpoints as roots.

extrapolate

[{bool, 'periodic', None}, optional] If bool, determines whether to return roots from the polynomial extrapolated based on first and last intervals, 'periodic' works the same as False. If None (default), use `self.extrapolate`.

Returns

roots [ndarray] Roots of the polynomial(s).
If the PPoly object describes multiple polynomials, the return value is an object array whose each element is an ndarray containing the roots.

See also:

[*PPoly.solve*](#)

scipy.interpolate.Akima1DInterpolator

class `scipy.interpolate.Akima1DInterpolator` (*x*, *y*, *axis=0*)

Akima interpolator

Fit piecewise cubic polynomials, given vectors *x* and *y*. The interpolation method by Akima uses a continuously differentiable sub-spline built from piecewise cubic polynomials. The resultant curve passes through the given data points and will appear smooth and natural.

Parameters

x	[ndarray, shape (m,)]	1-D array of monotonically increasing real values.
y	[ndarray, shape (m, ...)]	N-D array of real values. The length of <i>y</i> along the first axis must be equal to the length of <i>x</i> .
axis	[int, optional]	Specifies the axis of <i>y</i> along which to interpolate. Interpolation defaults to the first axis of <i>y</i> .

See also:

PchipInterpolator

PCHIP 1-D monotonic cubic interpolator.

CubicSpline

Cubic spline data interpolator.

PPoly

Piecewise polynomial in terms of coefficients and breakpoints

Notes

New in version 0.14.

Use only for precise data, as the fitted curve passes through the given points exactly. This routine is useful for plotting a pleasingly smooth curve through a few given points for purposes of plotting.

References

[1] *A new method of interpolation and smooth curve fitting based*

on local procedures. Hiroshi Akima, J. ACM, October 1970, 17(4), 589-602.

Attributes

axis
c
extrapolate
x

Methods

<code>__call__(self, x[, nu, extrapolate])</code>	Evaluate the piecewise polynomial or its derivative.
<code>derivative(self[, nu])</code>	Construct a new piecewise polynomial representing the derivative.
<code>antiderivative(self[, nu])</code>	Construct a new piecewise polynomial representing the antiderivative.
<code>roots(self[, discontinuity, extrapolate])</code>	Find real roots of the the piecewise polynomial.

scipy.interpolate.Akima1DInterpolator.__call__

`Akima1DInterpolator.__call__(self, x, nu=0, extrapolate=None)`

Evaluate the piecewise polynomial or its derivative.

Parameters

- x** [array_like] Points to evaluate the interpolant at.
- nu** [int, optional] Order of derivative to evaluate. Must be non-negative.
- extrapolate** [{bool, 'periodic', None}, optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. If None (default), use *self.extrapolate*.

Returns

- y** [array_like] Interpolated values. Shape is determined by replacing the interpolation axis in the original array with the shape of x.

Notes

Derivatives are evaluated piecewise for each polynomial segment, even if the polynomial is not differentiable at the breakpoints. The polynomial intervals are considered half-open, $[a, b)$, except for the last interval which is closed $[a, b]$.

scipy.interpolate.Akima1DInterpolator.derivative

`Akima1DInterpolator.derivative(self, nu=1)`

Construct a new piecewise polynomial representing the derivative.

Parameters

- nu** [int, optional] Order of derivative to evaluate. Default is 1, i.e., compute the first derivative. If negative, the antiderivative is returned.

Returns

- pp** [PPoly] Piecewise polynomial of order $k_2 = k - n$ representing the derivative of this polynomial.

Notes

Derivatives are evaluated piecewise for each polynomial segment, even if the polynomial is not differentiable at the breakpoints. The polynomial intervals are considered half-open, $[a, b)$, except for the last interval which is closed $[a, b]$.

`scipy.interpolate.Akima1DInterpolator.antiderivative`

`Akima1DInterpolator.antiderivative` (*self*, *nu=1*)

Construct a new piecewise polynomial representing the antiderivative.

Antiderivative is also the indefinite integral of the function, and derivative is its inverse operation.

Parameters

nu [int, optional] Order of antiderivative to evaluate. Default is 1, i.e., compute the first integral. If negative, the derivative is returned.

Returns

pp [PPoly] Piecewise polynomial of order $k_2 = k + n$ representing the antiderivative of this polynomial.

Notes

The antiderivative returned by this function is continuous and continuously differentiable to order $n-1$, up to floating point rounding error.

If antiderivative is computed and `self.extrapolate='periodic'`, it will be set to `False` for the returned instance. This is done because the antiderivative is no longer periodic and its correct evaluation outside of the initially given x interval is difficult.

`scipy.interpolate.Akima1DInterpolator.roots`

`Akima1DInterpolator.roots` (*self*, *discontinuity=True*, *extrapolate=None*)

Find real roots of the the piecewise polynomial.

Parameters

discontinuity

[bool, optional] Whether to report sign changes across discontinuities at breakpoints as roots.

extrapolate

[{bool, 'periodic', None}, optional] If bool, determines whether to return roots from the polynomial extrapolated based on first and last intervals, 'periodic' works the same as False. If None (default), use `self.extrapolate`.

Returns

roots [ndarray] Roots of the polynomial(s).
If the PPoly object describes multiple polynomials, the return value is an object array whose each element is an ndarray containing the roots.

See also:

[*PPoly.solve*](#)

scipy.interpolate.CubicSpline

class `scipy.interpolate.CubicSpline` (*x*, *y*, *axis*=0, *bc_type*='not-a-knot', *extrapolate*=None)
Cubic spline data interpolator.

Interpolate data with a piecewise cubic polynomial which is twice continuously differentiable [1]. The result is represented as a `PPoly` instance with breakpoints matching the given data.

Parameters

- x** [array_like, shape (n,)] 1-D array containing values of the independent variable. Values must be real, finite and in strictly increasing order.
- y** [array_like] Array containing values of the dependent variable. It can have arbitrary number of dimensions, but the length along *axis* (see below) must match the length of *x*. Values must be finite.
- axis** [int, optional] Axis along which *y* is assumed to be varying. Meaning that for *x*[*i*] the corresponding values are `np.take(y, i, axis=axis)`. Default is 0.
- bc_type** [string or 2-tuple, optional] Boundary condition type. Two additional equations, given by the boundary conditions, are required to determine all coefficients of polynomials on each segment [2].

If *bc_type* is a string, then the specified condition will be applied at both ends of a spline. Available conditions are:

- 'not-a-knot' (default): The first and second segment at a curve end are the same polynomial. It is a good default when there is no information on boundary conditions.
- 'periodic': The interpolated functions is assumed to be periodic of period $x[-1] - x[0]$. The first and last value of *y* must be identical: $y[0] == y[-1]$. This boundary condition will result in $y'[0] == y'[-1]$ and $y''[0] == y''[-1]$.
- 'clamped': The first derivative at curves ends are zero. Assuming a 1D *y*, *bc_type*=(1, 0.0), (1, 0.0)) is the same condition.
- 'natural': The second derivative at curve ends are zero. Assuming a 1D *y*, *bc_type*=(2, 0.0), (2, 0.0)) is the same condition.

If *bc_type* is a 2-tuple, the first and the second value will be applied at the curve start and end respectively. The tuple values can be one of the previously mentioned strings (except 'periodic') or a tuple (*order*, *deriv_values*) allowing to specify arbitrary derivatives at curve ends:

- *order*: the derivative order, 1 or 2.
- *deriv_value*: array_like containing derivative values, shape must be the same as *y*, excluding *axis* dimension. For example, if *y* is 1-D, then *deriv_value* must be a scalar. If *y* is 3-D with the shape (n0, n1, n2) and *axis*=2, then *deriv_value* must be 2-D and have the shape (n0, n1).

extrapolate

[[bool, 'periodic', None], optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. If None (default), *extrapolate* is set to 'periodic' for *bc_type*='periodic' and to True otherwise.

See also:

Akima1DInterpolator

Akima 1D interpolator.

PchipInterpolator

PCHIP 1-D monotonic cubic interpolator.

PPoly

Piecewise polynomial in terms of coefficients and breakpoints.

Notes

Parameters `bc_type` and `interpolate` work independently, i.e. the former controls only construction of a spline, and the latter only evaluation.

When a boundary condition is ‘not-a-knot’ and $n = 2$, it is replaced by a condition that the first derivative is equal to the linear interpolant slope. When both boundary conditions are ‘not-a-knot’ and $n = 3$, the solution is sought as a parabola passing through given points.

When ‘not-a-knot’ boundary conditions is applied to both ends, the resulting spline will be the same as returned by `splrep` (with `s=0`) and `InterpolatedUnivariateSpline`, but these two methods use a representation in B-spline basis.

New in version 0.18.0.

References

[1], [2]

Examples


In this example the cubic spline is used to interpolate a sampled sinusoid. You can see that the spline continuity property holds for the first and second derivatives and violates only for the third derivative.

```
>>> from scipy.interpolate import CubicSpline
>>> import matplotlib.pyplot as plt
>>> x = np.arange(10)
>>> y = np.sin(x)
>>> cs = CubicSpline(x, y)
>>> xs = np.arange(-0.5, 9.6, 0.1)
>>> fig, ax = plt.subplots(figsize=(6.5, 4))
>>> ax.plot(x, y, 'o', label='data')
>>> ax.plot(xs, np.sin(xs), label='true')
>>> ax.plot(xs, cs(xs), label="S")
>>> ax.plot(xs, cs(xs, 1), label="S'")
>>> ax.plot(xs, cs(xs, 2), label="S''")
>>> ax.plot(xs, cs(xs, 3), label="S'''")
>>> ax.set_xlim(-0.5, 9.5)
>>> ax.legend(loc='lower left', ncol=2)
>>> plt.show()
```

In the second example, the unit circle is interpolated with a spline. A periodic boundary condition is used. You can see that the first derivative values, $ds/dx=0$, $ds/dy=1$ at the periodic point $(1, 0)$ are correctly computed. Note that a circle cannot be exactly represented by a cubic spline. To increase precision, more breakpoints would be required.

```
>>> theta = 2 * np.pi * np.linspace(0, 1, 5)
>>> y = np.c_[np.cos(theta), np.sin(theta)]
>>> cs = CubicSpline(theta, y, bc_type='periodic')
>>> print("ds/dx={:.1f} ds/dy={:.1f}".format(cs(0, 1)[0], cs(0, 1)[1]))
ds/dx=0.0 ds/dy=1.0
>>> xs = 2 * np.pi * np.linspace(0, 1, 100)
```

(continues on next page)



(continued from previous page)


```
>>> fig, ax = plt.subplots(figsize=(6.5, 4))
>>> ax.plot(y[:, 0], y[:, 1], 'o', label='data')
>>> ax.plot(np.cos(xs), np.sin(xs), label='true')
>>> ax.plot(cs(xs)[:, 0], cs(xs)[:, 1], label='spline')
>>> ax.axes.set_aspect('equal')
>>> ax.legend(loc='center')
>>> plt.show()
```

The third example is the interpolation of a polynomial $y = x^3$ on the interval $0 \leq x \leq 1$. A cubic spline can represent this function exactly. To achieve that we need to specify values and first derivatives at endpoints of the interval. Note that $y' = 3 * x^2$ and thus $y'(0) = 0$ and $y'(1) = 3$.

```
>>> cs = CubicSpline([0, 1], [0, 1], bc_type=((1, 0), (1, 3)))
>>> x = np.linspace(0, 1)
>>> np.allclose(x**3, cs(x))
True
```

Attributes

- x** [ndarray, shape (n,)] Breakpoints. The same x which was passed to the constructor.
- c** [ndarray, shape (4, n-1, ...)] Coefficients of the polynomials on each segment. The trailing dimensions match the dimensions of y , excluding $axis$. For example, if y is 1-d, then $c[k, i]$ is a coefficient for $(x-x[i])^{(3-k)}$ on the segment between $x[i]$ and $x[i+1]$.
- axis** [int] Interpolation axis. The same axis which was passed to the constructor.



Methods

<code>__call__(self, x[, nu, extrapolate])</code>	Evaluate the piecewise polynomial or its derivative.
<code>derivative(self[, nu])</code>	Construct a new piecewise polynomial representing the derivative.
<code>antiderivative(self[, nu])</code>	Construct a new piecewise polynomial representing the antiderivative.
<code>integrate(self, a, b[, extrapolate])</code>	Compute a definite integral over a piecewise polynomial.
<code>roots(self[, discontinuity, extrapolate])</code>	Find real roots of the the piecewise polynomial.

scipy.interpolate.CubicSpline.__call__

`CubicSpline.__call__(self, x, nu=0, extrapolate=None)`

Evaluate the piecewise polynomial or its derivative.

Parameters

x [array_like] Points to evaluate the interpolant at.
nu [int, optional] Order of derivative to evaluate. Must be non-negative.
extrapolate [{bool, 'periodic', None}, optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. If None (default), use `self.extrapolate`.

Returns

y [array_like] Interpolated values. Shape is determined by replacing the interpolation axis in the original array with the shape of `x`.

Notes

6.8. Interpolation (`scipy.interpolate`)

851

Derivatives are evaluated piecewise for each polynomial segment, even if the polynomial is not differentiable at the breakpoints. The polynomial intervals are considered half-open, $[a, b)$, except for the last interval which is closed $[a, b]$.

Notes

Derivatives are evaluated piecewise for each polynomial segment, even if the polynomial is not differentiable at the breakpoints. The polynomial intervals are considered half-open, $[a, b)$, except for the last interval which is closed $[a, b]$.

`scipy.interpolate.CubicSpline.antiderivative`

`CubicSpline.antiderivative` (*self*, *nu=1*)

Construct a new piecewise polynomial representing the antiderivative.

Antiderivative is also the indefinite integral of the function, and derivative is its inverse operation.

Parameters

nu [int, optional] Order of antiderivative to evaluate. Default is 1, i.e., compute the first integral. If negative, the derivative is returned.

Returns

pp [PPoly] Piecewise polynomial of order $k_2 = k + n$ representing the antiderivative of this polynomial.

Notes

The antiderivative returned by this function is continuous and continuously differentiable to order $n-1$, up to floating point rounding error.

If antiderivative is computed and `self.extrapolate='periodic'`, it will be set to `False` for the returned instance. This is done because the antiderivative is no longer periodic and its correct evaluation outside of the initially given x interval is difficult.

`scipy.interpolate.CubicSpline.integrate`

`CubicSpline.integrate` (*self*, *a*, *b*, *extrapolate=None*)

Compute a definite integral over a piecewise polynomial.

Parameters

a [float] Lower integration bound

b [float] Upper integration bound

extrapolate [{bool, 'periodic', None}, optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. If None (default), use `self.extrapolate`.

Returns

ig [array_like] Definite integral of the piecewise polynomial over $[a, b]$

scipy.interpolate.CubicSpline.roots

`CubicSpline.roots` (*self*, *discontinuity=True*, *extrapolate=None*)

Find real roots of the the piecewise polynomial.

Parameters**discontinuity**

[bool, optional] Whether to report sign changes across discontinuities at breakpoints as roots.

extrapolate

[{bool, 'periodic', None}, optional] If bool, determines whether to return roots from the polynomial extrapolated based on first and last intervals, 'periodic' works the same as False. If None (default), use *self.extrapolate*.

Returns**roots**

[ndarray] Roots of the polynomial(s).

If the PPoly object describes multiple polynomials, the return value is an object array whose each element is an ndarray containing the roots.

See also:

PPoly.solve

scipy.interpolate.PPoly

class `scipy.interpolate.PPoly` (*c*, *x*, *extrapolate=None*, *axis=0*)

Piecewise polynomial in terms of coefficients and breakpoints

The polynomial between $x[i]$ and $x[i + 1]$ is written in the local power basis:

```
S = sum(c[m, i] * (xp - x[i])** (k-m) for m in range(k+1))
```

where k is the degree of the polynomial.

Parameters

c [ndarray, shape (k, m, ...)] Polynomial coefficients, order k and m intervals.

x [ndarray, shape (m+1,)] Polynomial breakpoints. Must be sorted in either increasing or decreasing order.

extrapolate

[bool or 'periodic', optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. Default is True.

axis [int, optional] Interpolation axis. Default is zero.

See also:

BPoly

piecewise polynomials in the Bernstein basis

Notes

High-order polynomials in the power basis can be numerically unstable. Precision problems can start to appear for orders larger than 20-30.

Attributes

x	[ndarray] Breakpoints.
c	[ndarray] Coefficients of the polynomials. They are reshaped to a 3-D array with the last dimension representing the trailing dimensions of the original coefficient array.
axis	[int] Interpolation axis.

Methods

<code>__call__(self, x[, nu, extrapolate])</code>	Evaluate the piecewise polynomial or its derivative.
<code>derivative(self[, nu])</code>	Construct a new piecewise polynomial representing the derivative.
<code>antiderivative(self[, nu])</code>	Construct a new piecewise polynomial representing the antiderivative.
<code>integrate(self, a, b[, extrapolate])</code>	Compute a definite integral over a piecewise polynomial.
<code>solve(self[, y, discontinuity, extrapolate])</code>	Find real solutions of the the equation $pp(x) == y$.
<code>roots(self[, discontinuity, extrapolate])</code>	Find real roots of the the piecewise polynomial.
<code>extend(self, c, x[, right])</code>	Add additional breakpoints and coefficients to the polynomial.
<code>from_spline(tck[, extrapolate])</code>	Construct a piecewise polynomial from a spline
<code>from_bernstein_basis(bp[, extrapolate])</code>	Construct a piecewise polynomial in the power basis from a polynomial in Bernstein basis.
<code>construct_fast(c, x[, extrapolate, axis])</code>	Construct the piecewise polynomial without making checks.

scipy.interpolate.PPoly.__call__

`PPoly.__call__(self, x, nu=0, extrapolate=None)`
 Evaluate the piecewise polynomial or its derivative.

Parameters

x	[array_like] Points to evaluate the interpolant at.
nu	[int, optional] Order of derivative to evaluate. Must be non-negative.
extrapolate	[{bool, 'periodic', None}, optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. If None (default), use <i>self.extrapolate</i> .

Returns

y	[array_like] Interpolated values. Shape is determined by replacing the interpolation axis in the original array with the shape of x.
----------	--

Notes

Derivatives are evaluated piecewise for each polynomial segment, even if the polynomial is not differentiable at the breakpoints. The polynomial intervals are considered half-open, $[a, b)$, except for the last interval which is closed $[a, b]$.

scipy.interpolate.PPoly.derivative

`PPoly.derivative` (*self*, *nu=1*)

Construct a new piecewise polynomial representing the derivative.

Parameters

nu [int, optional] Order of derivative to evaluate. Default is 1, i.e., compute the first derivative. If negative, the antiderivative is returned.

Returns

pp [PPoly] Piecewise polynomial of order $k_2 = k - n$ representing the derivative of this polynomial.

Notes

Derivatives are evaluated piecewise for each polynomial segment, even if the polynomial is not differentiable at the breakpoints. The polynomial intervals are considered half-open, $[a, b)$, except for the last interval which is closed $[a, b]$.

scipy.interpolate.PPoly.antiderivative

`PPoly.antiderivative` (*self*, *nu=1*)

Construct a new piecewise polynomial representing the antiderivative.

Antiderivative is also the indefinite integral of the function, and derivative is its inverse operation.

Parameters

nu [int, optional] Order of antiderivative to evaluate. Default is 1, i.e., compute the first integral. If negative, the derivative is returned.

Returns

pp [PPoly] Piecewise polynomial of order $k_2 = k + n$ representing the antiderivative of this polynomial.

Notes

The antiderivative returned by this function is continuous and continuously differentiable to order $n-1$, up to floating point rounding error.

If antiderivative is computed and `self.extrapolate='periodic'`, it will be set to `False` for the returned instance. This is done because the antiderivative is no longer periodic and its correct evaluation outside of the initially given x interval is difficult.

scipy.interpolate.PPoly.integrate`PPoly.integrate` (*self*, *a*, *b*, *extrapolate=None*)

Compute a definite integral over a piecewise polynomial.

Parameters**a** [float] Lower integration bound**b** [float] Upper integration bound**extrapolate**[bool, 'periodic', None], optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. If None (default), use *self.extrapolate*.**Returns****ig** [array_like] Definite integral of the piecewise polynomial over [a, b]**scipy.interpolate.PPoly.solve**`PPoly.solve` (*self*, *y=0.0*, *discontinuity=True*, *extrapolate=None*)Find real solutions of the the equation $pp(x) == y$.**Parameters****y** [float, optional] Right-hand side. Default is zero.**discontinuity**

[bool, optional] Whether to report sign changes across discontinuities at breakpoints as roots.

extrapolate[bool, 'periodic', None], optional] If bool, determines whether to return roots from the polynomial extrapolated based on first and last intervals, 'periodic' works the same as False. If None (default), use *self.extrapolate*.**Returns****roots** [ndarray] Roots of the polynomial(s).

If the PPoly object describes multiple polynomials, the return value is an object array whose each element is an ndarray containing the roots.

Notes

This routine works only on real-valued polynomials.

If the piecewise polynomial contains sections that are identically zero, the root list will contain the start point of the corresponding interval, followed by a `nan` value.If the polynomial is discontinuous across a breakpoint, and there is a sign change across the breakpoint, this is reported if the *discont* parameter is True.

Examples

Finding roots of $[x^2 - 1, (x - 1)^2]$ defined on intervals $[-2, 1], [1, 2]$:

```
>>> from scipy.interpolate import PPoly
>>> pp = PPoly(np.array([[1, -4, 3], [1, 0, 0]]).T, [-2, 1, 2])
>>> pp.solve()
array([-1., 1.]
```

scipy.interpolate.PPoly.roots

`PPoly.roots` (*self*, *discontinuity=True*, *extrapolate=None*)

Find real roots of the the piecewise polynomial.

Parameters

discontinuity

[bool, optional] Whether to report sign changes across discontinuities at breakpoints as roots.

extrapolate

[{bool, 'periodic', None}, optional] If bool, determines whether to return roots from the polynomial extrapolated based on first and last intervals, 'periodic' works the same as False. If None (default), use *self.extrapolate*.

Returns

roots

[ndarray] Roots of the polynomial(s).
If the PPoly object describes multiple polynomials, the return value is an object array whose each element is an ndarray containing the roots.

See also:

[`PPoly.solve`](#)

scipy.interpolate.PPoly.extend

`PPoly.extend` (*self*, *c*, *x*, *right=None*)

Add additional breakpoints and coefficients to the polynomial.

Parameters

c

[ndarray, size (k, m, ...)] Additional coefficients for polynomials in intervals. Note that the first additional interval will be formed using one of the *self.x* end points.

x

[ndarray, size (m,)] Additional breakpoints. Must be sorted in the same order as *self.x* and either to the right or to the left of the current breakpoints.

right

Deprecated argument. Has no effect.
Deprecated since version 0.19.

scipy.interpolate.PPoly.from_spline

`classmethod PPoly.from_spline` (*tck*, *extrapolate=None*)

Construct a piecewise polynomial from a spline

Parameters

tck

A spline, as returned by *splrep* or a BSpline object.

extrapolate

[bool or 'periodic', optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. Default is True.

scipy.interpolate.PPoly.from_bernstein_basis**classmethod** `PPoly.from_bernstein_basis` (*bp*, *extrapolate=None*)

Construct a piecewise polynomial in the power basis from a polynomial in Bernstein basis.

Parameters**bp** [BPoly] A Bernstein basis polynomial, as created by BPoly**extrapolate**

[bool or 'periodic', optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. Default is True.

scipy.interpolate.PPoly.construct_fast**classmethod** `PPoly.construct_fast` (*c*, *x*, *extrapolate=None*, *axis=0*)

Construct the piecewise polynomial without making checks.

Takes the same parameters as the constructor. Input arguments *c* and *x* must be arrays of the correct shape and type. The *c* array can only be of dtypes float and complex, and *x* array must have dtype float.**scipy.interpolate.BPoly****class** `scipy.interpolate.BPoly` (*c*, *x*, *extrapolate=None*, *axis=0*)

Piecewise polynomial in terms of coefficients and breakpoints.

The polynomial between $x[i]$ and $x[i + 1]$ is written in the Bernstein polynomial basis:

```
S = sum(c[a, i] * b(a, k; x) for a in range(k+1)),
```

where *k* is the degree of the polynomial, and:

```
b(a, k; x) = binom(k, a) * t**a * (1 - t)**(k - a),
```

with $t = (x - x[i]) / (x[i+1] - x[i])$ and `binom` is the binomial coefficient.**Parameters****c** [ndarray, shape (k, m, ...)] Polynomial coefficients, order *k* and *m* intervals**x** [ndarray, shape (m+1,)] Polynomial breakpoints. Must be sorted in either increasing or decreasing order.**extrapolate**

[bool, optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. Default is True.

axis [int, optional] Interpolation axis. Default is zero.**See also:****PPoly**

piecewise polynomials in the power basis

Notes

Properties of Bernstein polynomials are well documented in the literature, see for example [1] [2] [3].

References

[1], [2], [3]

Examples

```
>>> from scipy.interpolate import BPoly
>>> x = [0, 1]
>>> c = [[1], [2], [3]]
>>> bp = BPoly(c, x)
```

This creates a 2nd order polynomial

$$\begin{aligned}
 B(x) &= 1 \times b_{0,2}(x) + 2 \times b_{1,2}(x) + 3 \times b_{2,2}(x) \\
 &= 1 \times (1-x)^2 + 2 \times 2x(1-x) + 3 \times x^2
 \end{aligned}$$

Attributes

- x** [ndarray] Breakpoints.
- c** [ndarray] Coefficients of the polynomials. They are reshaped to a 3-D array with the last dimension representing the trailing dimensions of the original coefficient array.
- axis** [int] Interpolation axis.

Methods

<code>__call__(self, x[, nu, extrapolate])</code>	Evaluate the piecewise polynomial or its derivative.
<code>extend(self, c, x[, right])</code>	Add additional breakpoints and coefficients to the polynomial.
<code>derivative(self[, nu])</code>	Construct a new piecewise polynomial representing the derivative.
<code>antiderivative(self[, nu])</code>	Construct a new piecewise polynomial representing the antiderivative.
<code>integrate(self, a, b[, extrapolate])</code>	Compute a definite integral over a piecewise polynomial.
<code>construct_fast(c, x[, extrapolate, axis])</code>	Construct the piecewise polynomial without making checks.
<code>from_power_basis(pp[, extrapolate])</code>	Construct a piecewise polynomial in Bernstein basis from a power basis polynomial.
<code>from_derivatives(xi, yi[, orders, extrapolate])</code>	Construct a piecewise polynomial in the Bernstein basis, compatible with the specified values and derivatives at breakpoints.

scipy.interpolate.BPoly.__call__`BPoly.__call__(self, x, nu=0, extrapolate=None)`

Evaluate the piecewise polynomial or its derivative.

Parameters

- x** [array_like] Points to evaluate the interpolant at.
- nu** [int, optional] Order of derivative to evaluate. Must be non-negative.
- extrapolate** [{bool, 'periodic', None}, optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. If None (default), use *self.extrapolate*.

Returns

- y** [array_like] Interpolated values. Shape is determined by replacing the interpolation axis in the original array with the shape of *x*.

Notes

Derivatives are evaluated piecewise for each polynomial segment, even if the polynomial is not differentiable at the breakpoints. The polynomial intervals are considered half-open, $[a, b)$, except for the last interval which is closed $[a, b]$.

scipy.interpolate.BPoly.extend`BPoly.extend(self, c, x, right=None)`

Add additional breakpoints and coefficients to the polynomial.

Parameters

- c** [ndarray, size (k, m, ...)] Additional coefficients for polynomials in intervals. Note that the first additional interval will be formed using one of the `self.x` end points.
- x** [ndarray, size (m,)] Additional breakpoints. Must be sorted in the same order as `self.x` and either to the right or to the left of the current breakpoints.
- right** Deprecated argument. Has no effect. Deprecated since version 0.19.

scipy.interpolate.BPoly.derivative`BPoly.derivative(self, nu=1)`

Construct a new piecewise polynomial representing the derivative.

Parameters

- nu** [int, optional] Order of derivative to evaluate. Default is 1, i.e., compute the first derivative. If negative, the antiderivative is returned.

Returns

- bp** [BPoly] Piecewise polynomial of order $k - nu$ representing the derivative of this polynomial.

scipy.interpolate.BPoly.antiderivative`BPoly.antiderivative` (*self*, *nu=1*)

Construct a new piecewise polynomial representing the antiderivative.

*Parameters***nu** [int, optional] Order of antiderivative to evaluate. Default is 1, i.e., compute the first integral. If negative, the derivative is returned.*Returns***bp** [BPoly] Piecewise polynomial of order $k + nu$ representing the antiderivative of this polynomial.**Notes**

If antiderivative is computed and `self.extrapolate='periodic'`, it will be set to `False` for the returned instance. This is done because the antiderivative is no longer periodic and its correct evaluation outside of the initially given x interval is difficult.

scipy.interpolate.BPoly.integrate`BPoly.integrate` (*self*, *a*, *b*, *extrapolate=None*)

Compute a definite integral over a piecewise polynomial.

*Parameters***a** [float] Lower integration bound**b** [float] Upper integration bound**extrapolate**[bool, 'periodic', None], optional] Whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. If None (default), use `self.extrapolate`.*Returns***array_like** Definite integral of the piecewise polynomial over [a, b]**scipy.interpolate.BPoly.construct_fast**`classmethod BPoly.construct_fast` (*c*, *x*, *extrapolate=None*, *axis=0*)

Construct the piecewise polynomial without making checks.

Takes the same parameters as the constructor. Input arguments `c` and `x` must be arrays of the correct shape and type. The `c` array can only be of dtypes float and complex, and `x` array must have dtype float.

scipy.interpolate.BPoly.from_power_basis`classmethod BPoly.from_power_basis` (*pp*, *extrapolate=None*)

Construct a piecewise polynomial in Bernstein basis from a power basis polynomial.

*Parameters***pp** [PPoly] A piecewise polynomial in the power basis**extrapolate**[bool or 'periodic', optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. Default is `True`.

scipy.interpolate.BPoly.from_derivatives**classmethod** `BPoly.from_derivatives` (*xi, yi, orders=None, extrapolate=None*)

Construct a piecewise polynomial in the Bernstein basis, compatible with the specified values and derivatives at breakpoints.

Parameters

- xi** [array_like] sorted 1-D array of x-coordinates
- yi** [array_like or list of array_likes] `yi[i][j]` is the `j`'th derivative known at `xi[i]`
- orders** [None or int or array_like of ints. Default: None.] Specifies the degree of local polynomials. If not None, some derivatives are ignored.
- extrapolate** [bool or 'periodic', optional] If bool, determines whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. If 'periodic', periodic extrapolation is used. Default is True.

Notes

If `k` derivatives are specified at a breakpoint `x`, the constructed polynomial is exactly `k` times continuously differentiable at `x`, unless the `order` is provided explicitly. In the latter case, the smoothness of the polynomial at the breakpoint is controlled by the `order`.

Deduces the number of derivatives to match at each end from `order` and the number of derivatives available. If possible it uses the same number of derivatives from each end; if the number is odd it tries to take the extra one from `y2`. In any case if not enough derivatives are available at one end or another it draws enough to make up the total from the other end.

If the order is too high and not enough derivatives are available, an exception is raised.

Examples

```
>>> from scipy.interpolate import BPoly
>>> BPoly.from_derivatives([0, 1], [[1, 2], [3, 4]])
```

Creates a polynomial $f(x)$ of degree 3, defined on $[0, 1]$ such that $f(0) = 1$, $df/dx(0) = 2$, $f(1) = 3$, $df/dx(1) = 4$

```
>>> BPoly.from_derivatives([0, 1, 2], [[0, 1], [0], [2]])
```

Creates a piecewise polynomial $f(x)$, such that $f(0) = f(1) = 0$, $f(2) = 2$, and $df/dx(0) = 1$. Based on the number of derivatives provided, the order of the local polynomials is 2 on $[0, 1]$ and 1 on $[1, 2]$. Notice that no restriction is imposed on the derivatives at $x = 1$ and $x = 2$.

Indeed, the explicit form of the polynomial is:

$$f(x) = \begin{cases} x * (1 - x), & 0 \leq x < 1 \\ 2 * (x - 1), & 1 \leq x \leq 2 \end{cases}$$

So that $f'(1-0) = -1$ and $f'(1+0) = 2$

6.8.2 Multivariate interpolation

Unstructured data:

<code>griddata(points, values, xi[, method, ...])</code>	Interpolate unstructured D-D data.
<code>LinearNDInterpolator(points, values[, ...])</code>	Piecewise linear interpolant in N dimensions.
<code>NearestNDInterpolator(x, y)</code>	Nearest-neighbor interpolation in N dimensions.
<code>CloughTocher2DInterpolator(points, values[, tol])</code>	Piecewise cubic, C1 smooth, curvature-minimizing interpolant in 2D.
<code>Rbf(*args)</code>	A class for radial basis function interpolation of functions from N-D scattered data to an M-D domain.
<code>interp2d(x, y, z[, kind, copy, ...])</code>	Interpolate over a 2-D grid.

scipy.interpolate.griddata

`scipy.interpolate.griddata` (*points, values, xi, method='linear', fill_value=nan, rescale=False*)

Interpolate unstructured D-D data.

Parameters

points	[2-D ndarray of floats with shape (n, D), or length D tuple of 1-D ndarrays with shape (n,).] Data point coordinates.
values	[ndarray of float or complex, shape (n,)] Data values.
xi	[2-D ndarray of floats with shape (m, D), or length D tuple of ndarrays broadcastable to the same shape.] Points at which to interpolate data.
method	[{'linear', 'nearest', 'cubic'}, optional] Method of interpolation. One of <ul style="list-style-type: none"> nearest return the value at the data point closest to the point of interpolation. See NearestNDInterpolator for more details. linear tessellate the input point set to N-D simplices, and interpolate linearly on each simplex. See LinearNDInterpolator for more details. cubic (1-D) return the value determined from a cubic spline. cubic (2-D) return the value determined from a piecewise cubic, continuously differentiable (C1), and approximately curvature-minimizing polynomial surface. See CloughTocher2DInterpolator for more details.
fill_value	[float, optional] Value used to fill in for requested points outside of the convex hull of the input points. If not provided, then the default is <code>nan</code> . This option has no effect for the 'nearest' method.
rescale	[bool, optional] Rescale points to unit cube before performing interpolation. This is useful if some of the input dimensions have incommensurable units and differ by many orders of magnitude. New in version 0.14.0.

Returns

ndarray Array of interpolated values.

See also:

[LinearNDInterpolator](#)

Piecewise linear interpolant in N dimensions.

NearestNDInterpolator

Nearest-neighbor interpolation in N dimensions.

CloughTocher2DInterpolator

Piecewise cubic, C1 smooth, curvature-minimizing interpolant in 2D.

Notes

New in version 0.9.

Examples

Suppose we want to interpolate the 2-D function

```
>>> def func(x, y):
...     return x*(1-x)*np.cos(4*np.pi*x) * np.sin(4*np.pi*y**2)**2
```

on a grid in $[0, 1] \times [0, 1]$

```
>>> grid_x, grid_y = np.mgrid[0:1:100j, 0:1:200j]
```

but we only know its values at 1000 data points:


```
>>> points = np.random.rand(1000, 2)
>>> values = func(points[:,0], points[:,1])
```

This can be done with *griddata* – below we try out all of the interpolation methods:

```
>>> from scipy.interpolate import griddata
>>> grid_z0 = griddata(points, values, (grid_x, grid_y), method='nearest')
>>> grid_z1 = griddata(points, values, (grid_x, grid_y), method='linear')
>>> grid_z2 = griddata(points, values, (grid_x, grid_y), method='cubic')
```

One can see that the exact result is reproduced by all of the methods to some degree, but for this smooth function the piecewise cubic interpolant gives the best results:

```
>>> import matplotlib.pyplot as plt
>>> plt.subplot(221)
>>> plt.imshow(func(grid_x, grid_y).T, extent=(0,1,0,1), origin='lower')
>>> plt.plot(points[:,0], points[:,1], 'k.', ms=1)
>>> plt.title('Original')
>>> plt.subplot(222)
>>> plt.imshow(grid_z0.T, extent=(0,1,0,1), origin='lower')
>>> plt.title('Nearest')
>>> plt.subplot(223)
>>> plt.imshow(grid_z1.T, extent=(0,1,0,1), origin='lower')
>>> plt.title('Linear')
>>> plt.subplot(224)
>>> plt.imshow(grid_z2.T, extent=(0,1,0,1), origin='lower')
>>> plt.title('Cubic')
>>> plt.gcf().set_size_inches(6, 6)
>>> plt.show()
```



scipy.interpolate.LinearNDInterpolator

class `scipy.interpolate.LinearNDInterpolator` (*points*, *values*, *fill_value=np.nan*, *rescale=False*)

Piecewise linear interpolant in N dimensions.

New in version 0.9.

Parameters

points [ndarray of floats, shape (npoints, ndims); or Delaunay] Data point coordinates, or a pre-computed Delaunay triangulation.

values [ndarray of float or complex, shape (npoints, ...)] Data values.

fill_value [float, optional] Value used to fill in for requested points outside of the convex hull of the input points. If not provided, then the default is `nan`.

rescale [bool, optional] Rescale points to unit cube before performing interpolation. This is useful if some of the input dimensions have incommensurable units and differ by many orders of magnitude.

See also:

griddata

Interpolate unstructured D-D data.

NearestNDInterpolator

Nearest-neighbor interpolation in N dimensions.

CloughTocher2DInterpolator

Piecewise cubic, C1 smooth, curvature-minimizing interpolant in 2D.

Notes

The interpolant is constructed by triangulating the input data with Qhull [1], and on each triangle performing linear barycentric interpolation.

References

[1]

Examples

We can interpolate values on a 2D plane:

```
>>> from scipy.interpolate import LinearNDInterpolator
>>> import matplotlib.pyplot as plt
>>> np.random.seed(0)
>>> x = np.random.random(10) - 0.5
>>> y = np.random.random(10) - 0.5
>>> z = np.hypot(x, y)
>>> X = np.linspace(min(x), max(x))
>>> Y = np.linspace(min(y), max(y))
>>> X, Y = np.meshgrid(X, Y) # 2D grid for interpolation
>>> interp = LinearNDInterpolator(list(zip(x, y)), z)
```


(continues on next page)

(continued from previous page)

```

>>> Z = interp(X, Y)
>>> plt.pcolormesh(X, Y, Z, shading='auto')
>>> plt.plot(x, y, "ok", label="input point")
>>> plt.legend()
>>> plt.colorbar()
>>> plt.axis("equal")
>>> plt.show()

```



Methods

<code>__call__(xi)</code>	Evaluate interpolator at given points.
---------------------------	--

`scipy.interpolate.LinearNDInterpolator.__call__`

`LinearNDInterpolator.__call__(xi)`

Evaluate interpolator at given points.

Parameters

x1, x2, ... xn: array-like of float

Points where to interpolate data at. x1, x2, ... xn can be array-like of float with broadcastable shape. or x1 can be array-like of float with shape `(..., ndim)`

scipy.interpolate.NearestNDInterpolator

class `scipy.interpolate.NearestNDInterpolator` (*x*, *y*)

Nearest-neighbor interpolation in N dimensions.

New in version 0.9.

Parameters

- x** [(Npoints, Ndims) ndarray of floats] Data point coordinates.
- y** [(Npoints,) ndarray of float or complex] Data values.
- rescale** [boolean, optional] Rescale points to unit cube before performing interpolation. This is useful if some of the input dimensions have incommensurable units and differ by many orders of magnitude.
New in version 0.14.0.
- tree_options** [dict, optional] Options passed to the underlying `cKDTree`.
New in version 0.17.0.

See also:

griddata

Interpolate unstructured D-D data.

LinearNDInterpolator

Piecewise linear interpolant in N dimensions.

CloughTocher2DInterpolator

Piecewise cubic, C1 smooth, curvature-minimizing interpolant in 2D.

Notes

Uses `scipy.spatial.cKDTree`

Examples


We can interpolate values on a 2D plane:

```
>>> from scipy.interpolate import NearestNDInterpolator
>>> import matplotlib.pyplot as plt
>>> np.random.seed(0)
>>> x = np.random.random(10) - 0.5
>>> y = np.random.random(10) - 0.5
>>> z = np.hypot(x, y)
>>> X = np.linspace(min(x), max(x))
>>> Y = np.linspace(min(y), max(y))
>>> X, Y = np.meshgrid(X, Y) # 2D grid for interpolation
>>> interp = NearestNDInterpolator(list(zip(x, y)), z)
>>> Z = interp(X, Y)
>>> plt.pcolormesh(X, Y, Z, shading='auto')
>>> plt.plot(x, y, "ok", label="input point")
>>> plt.legend()
>>> plt.colorbar()
```

(continues on next page)

(continued from previous page)

```
>>> plt.axis("equal")
>>> plt.show()
```



Methods

<code>__call__(self, *args)</code>	Evaluate interpolator at given points.
------------------------------------	--

`scipy.interpolate.NearestNDInterpolator.__call__`

`NearestNDInterpolator.__call__(self, *args)`

Evaluate interpolator at given points.

Parameters

x1, x2, ... xn: array-like of float

Points where to interpolate data at. x1, x2, ... xn can be array-like of float with broadcastable shape. or x1 can be array-like of float with shape `(..., ndim)`

`scipy.interpolate.CloughTocher2DInterpolator`

class `scipy.interpolate.CloughTocher2DInterpolator` (*points, values, tol=1e-06*)

Piecewise cubic, C1 smooth, curvature-minimizing interpolant in 2D.

New in version 0.9.

Parameters

points	[ndarray of floats, shape (npoints, ndims); or Delaunay] Data point coordinates, or a pre-computed Delaunay triangulation.
values	[ndarray of float or complex, shape (npoints, ...)] Data values.
fill_value	[float, optional] Value used to fill in for requested points outside of the convex hull of the input points. If not provided, then the default is <code>nan</code> .
tol	[float, optional] Absolute/relative tolerance for gradient estimation.

maxiter [int, optional] Maximum number of iterations in gradient estimation.
rescale [bool, optional] Rescale points to unit cube before performing interpolation. This is useful if some of the input dimensions have incommensurable units and differ by many orders of magnitude.

See also:

griddata

Interpolate unstructured D-D data.

LinearNDInterpolator

Piecewise linear interpolant in N dimensions.

NearestNDInterpolator

Nearest-neighbor interpolation in N dimensions.

Notes

The interpolant is constructed by triangulating the input data with Qhull [1], and constructing a piecewise cubic interpolating Bezier polynomial on each triangle, using a Clough-Tocher scheme [CT]. The interpolant is guaranteed to be continuously differentiable.

The gradients of the interpolant are chosen so that the curvature of the interpolating surface is approximately minimized. The gradients necessary for this are estimated using the global algorithm described in [Nielson83] and [Renka84].


References

[1], [CT], [Nielson83], [Renka84]

Examples

We can interpolate values on a 2D plane:

```
>>> from scipy.interpolate import CloughTocher2DInterpolator
>>> import matplotlib.pyplot as plt
>>> np.random.seed(0)
>>> x = np.random.random(10) - 0.5
>>> y = np.random.random(10) - 0.5
>>> z = np.hypot(x, y)
>>> X = np.linspace(min(x), max(x))
>>> Y = np.linspace(min(y), max(y))
>>> X, Y = np.meshgrid(X, Y) # 2D grid for interpolation
>>> interp = CloughTocher2DInterpolator(list(zip(x, y)), z)
>>> Z = interp(X, Y)
>>> plt.pcolormesh(X, Y, Z, shading='auto')
>>> plt.plot(x, y, "ok", label="input point")
>>> plt.legend()
>>> plt.colorbar()
>>> plt.axis("equal")
>>> plt.show()
```



Methods

<code>__call__(xi)</code>	Evaluate interpolator at given points.
---------------------------	--

`scipy.interpolate.CloughTocher2DInterpolator.__call__`

`CloughTocher2DInterpolator.__call__(xi)`
 Evaluate interpolator at given points.

Parameters

x1, x2, ... xn: array-like of float

Points where to interpolate data at. `x1, x2, ... xn` can be array-like of float with broadcastable shape. or `x1` can be array-like of float with shape `(..., ndim)`

`scipy.interpolate.Rbf`

class `scipy.interpolate.Rbf(*args)`

A class for radial basis function interpolation of functions from N-D scattered data to an M-D domain.

Parameters

***args** [arrays] `x, y, z, ..., d`, where `x, y, z, ...` are the coordinates of the nodes and `d` is the array of values at the nodes

function [str or callable, optional] The radial basis function, based on the radius, `r`, given by the norm (default is Euclidean distance); the default is 'multiquadric':

```
'multiquadric': sqrt((r/self.epsilon)**2 + 1)
'inverse': 1.0/sqrt((r/self.epsilon)**2 + 1)
'gaussian': exp(-(r/self.epsilon)**2)
'linear': r
'cubic': r**3
'quintic': r**5
'thin_plate': r**2 * log(r)
```

If callable, then it must take 2 arguments (`self, r`). The `epsilon` parameter will be available as `self.epsilon`. Other keyword arguments passed in will be available as well.

epsilon [float, optional] Adjustable constant for gaussian or multiquadrics functions - defaults to `approx(0.1 * distance between nodes)` (which is a good start).

6.8. Interpolation (`scipy.interpolate`) 871

smooth [float, optional] Values greater than zero increase the smoothness of the approximation. 0 is for interpolation (default), the function will always go through the nodal points in this case.

norm [str, callable, optional] A function that returns the 'distance' between two points, with inputs

Examples

```
>>> from scipy.interpolate import Rbf
>>> x, y, z, d = np.random.rand(4, 50)
>>> rbf = Rbf(x, y, z, d) # radial basis function interpolator instance
>>> xi = yi = zi = np.linspace(0, 1, 20)
>>> di = rbf(xi, yi, zi) # interpolated values
>>> di.shape
(20,)
```

Attributes

N	[int] The number of data points (as determined by the input arrays).
di	[ndarray] The 1-D array of data values at each of the data coordinates <i>xi</i> .
xi	[ndarray] The 2-D array of data coordinates.
function	[str or callable] The radial basis function. See description under Parameters.
epsilon	[float] Parameter used by gaussian or multiquadrics functions. See Parameters.
smooth	[float] Smoothing parameter. See description under Parameters.
norm	[str or callable] The distance function. See description under Parameters.
mode	[str] Mode of the interpolation. See description under Parameters.
nodes	[ndarray] A 1-D array of node values for the interpolation.
A	[internal property, do not use]

Methods

<code>__call__(self, *args)</code>	Call self as a function.
------------------------------------	--------------------------

scipy.interpolate.Rbf.__call__

Rbf.`__call__(self, *args)`
 Call self as a function.

scipy.interpolate.interp2d

class `scipy.interpolate.interp2d(x, y, z, kind='linear', copy=True, bounds_error=False, fill_value=None)`

Interpolate over a 2-D grid.

x, *y* and *z* are arrays of values used to approximate some function $f: z = f(x, y)$. This class returns a function whose call method uses spline interpolation to find the value of new points.

If *x* and *y* represent a regular grid, consider using `RectBivariateSpline`.

Note that calling `interp2d` with NaNs present in input values results in undefined behaviour.

Parameters

x, y	[array_like] Arrays defining the data point coordinates. If the points lie on a regular grid, <i>x</i> can specify the column coordinates and <i>y</i> the row coordinates, for example:
-------------	---

```
>>> x = [0, 1, 2]; y = [0, 3]; z = [[1, 2, 3], [4, 5, 6]]
```

Otherwise, *x* and *y* must specify the full coordinates for each point, for example:

```
>>> x = [0, 1, 2, 0, 1, 2]; y = [0, 0, 0, 3, 3, 3]; z = [1, 2, 3, 4, 5,
↳ 6]
```

If x and y are multidimensional, they are flattened before use.

- z** [array_like] The values of the function to interpolate at the data points. If z is a multidimensional array, it is flattened before use. The length of a flattened z array is either $\text{len}(x)*\text{len}(y)$ if x and y specify the column and row coordinates or $\text{len}(z) == \text{len}(x) == \text{len}(y)$ if x and y specify coordinates for each point.
- kind** [{'linear', 'cubic', 'quintic'}, optional] The kind of spline interpolation to use. Default is 'linear'.
- copy** [bool, optional] If True, the class makes internal copies of x , y and z . If False, references may be used. The default is to copy.
- bounds_error** [bool, optional] If True, when interpolated values are requested outside of the domain of the input data (x,y), a `ValueError` is raised. If False, then *fill_value* is used.
- fill_value** [number, optional] If provided, the value to use for points outside of the interpolation domain. If omitted (None), values outside the domain are extrapolated via nearest-neighbor extrapolation.

See also:

RectBivariateSpline

Much faster 2-D interpolation if your input data is on a grid

bisplrep, bisplev

Spline interpolation based on FITPACK

BivariateSpline

a more recent wrapper of the FITPACK routines

interp1d

1-D version of this function

Notes

The minimum number of data points required along the interpolation axis is $(k+1)**2$, with $k=1$ for linear, $k=3$ for cubic and $k=5$ for quintic interpolation.

The interpolator is constructed by *bisplrep*, with a smoothing factor of 0. If more control over smoothing is needed, *bisplrep* should be used directly.


Examples

Construct a 2-D grid and interpolate on it:

```
>>> from scipy import interpolate
>>> x = np.arange(-5.01, 5.01, 0.25)
>>> y = np.arange(-5.01, 5.01, 0.25)
>>> xx, yy = np.meshgrid(x, y)
>>> z = np.sin(xx**2+yy**2)
>>> f = interpolate.interp2d(x, y, z, kind='cubic')
```

Now use the obtained interpolation function and plot the result:

```
>>> import matplotlib.pyplot as plt
>>> xnew = np.arange(-5.01, 5.01, 1e-2)
>>> ynew = np.arange(-5.01, 5.01, 1e-2)
>>> znew = f(xnew, ynew)
>>> plt.plot(x, z[0, :], 'ro-', xnew, znew[0, :], 'b-')
>>> plt.show()
```



Methods

<code>__call__(self, x, y[, dx, dy, assume_sorted])</code>	Interpolate the function.
--	---------------------------

scipy.interpolate.interp2d.__call__

`interp2d.__call__(self, x, y, dx=0, dy=0, assume_sorted=False)`

Interpolate the function.

Parameters

x [1-D array] x-coordinates of the mesh on which to interpolate.
y [1-D array] y-coordinates of the mesh on which to interpolate.
dx [int >= 0, < kx] Order of partial derivatives in x.
dy [int >= 0, < ky] Order of partial derivatives in y.
assume_sorted [bool, optional] If False, values of *x* and *y* can be in any order and they are sorted first. If True, *x* and *y* have to be arrays of monotonically increasing values.

Returns

z [2-D array with shape (len(y), len(x))] The interpolated values.

For data on a grid:

<code>interp(points, values, xi[, method, ...])</code>	Multidimensional interpolation on regular grids. continues on next page
--	--

Table 56 – continued from previous page

<i>RegularGridInterpolator</i> (points, values[, ...])	Interpolation on a regular grid in arbitrary dimensions
<i>RectBivariateSpline</i> (x, y, z[, bbox, kx, ky, s])	Bivariate spline approximation over a rectangular mesh.

scipy.interpolate.interpn

`scipy.interpolate.interpn` (points, values, xi, method='linear', bounds_error=True, fill_value=nan)

Multidimensional interpolation on regular grids.

Parameters

points	[tuple of ndarray of float, with shapes (m1,), ..., (mn,)] The points defining the regular grid in n dimensions.
values	[array_like, shape (m1, ..., mn, ...)] The data on the regular grid in n dimensions.
xi	[ndarray of shape (... , ndim)] The coordinates to sample the gridded data at
method	[str, optional] The method of interpolation to perform. Supported are “linear” and “nearest”, and “splinef2d”. “splinef2d” is only supported for 2-dimensional data.
bounds_error	[bool, optional] If True, when interpolated values are requested outside of the domain of the input data, a ValueError is raised. If False, then <i>fill_value</i> is used.
fill_value	[number, optional] If provided, the value to use for points outside of the interpolation domain. If None, values outside the domain are extrapolated. Extrapolation is not supported by method “splinef2d”.

Returns

values_x [ndarray, shape xi.shape[:-1] + values.shape[ndim:]] Interpolated values at input coordinates.

See also:

NearestNDInterpolator

Nearest neighbor interpolation on unstructured data in N dimensions

LinearNDInterpolator

Piecewise linear interpolant on unstructured data in N dimensions

RegularGridInterpolator

Linear and nearest-neighbor Interpolation on a regular grid in arbitrary dimensions

RectBivariateSpline

Bivariate spline approximation over a rectangular mesh

Notes

New in version 0.14.

Examples

Evaluate a simple example function on the points of a regular 3-D grid:

```
>>> from scipy.interpolate import interpn
>>> def value_func_3d(x, y, z):
...     return 2 * x + 3 * y - z
>>> x = np.linspace(0, 5)
>>> y = np.linspace(0, 5)
>>> z = np.linspace(0, 5)
>>> points = (x, y, z)
>>> values = value_func_3d(*np.meshgrid(*points))
```

Evaluate the interpolating function at a point

```
>>> point = np.array([2.21, 3.12, 1.15])
>>> print(interpn(points, values, point))
[11.72]
```

scipy.interpolate.RegularGridInterpolator

class `scipy.interpolate.RegularGridInterpolator` (*points*, *values*, *method='linear'*, *bounds_error=True*, *fill_value=nan*)

Interpolation on a regular grid in arbitrary dimensions

The data must be defined on a regular grid; the grid spacing however may be uneven. Linear and nearest-neighbor interpolation are supported. After setting up the interpolator object, the interpolation method (*linear* or *nearest*) may be chosen at each evaluation.

Parameters

- points** [tuple of ndarray of float, with shapes (m1,), ..., (mn,)] The points defining the regular grid in n dimensions.
- values** [array_like, shape (m1, ..., mn, ...)] The data on the regular grid in n dimensions.
- method** [str, optional] The method of interpolation to perform. Supported are “linear” and “nearest”. This parameter will become the default for the object’s `__call__` method. Default is “linear”.
- bounds_error** [bool, optional] If True, when interpolated values are requested outside of the domain of the input data, a `ValueError` is raised. If False, then *fill_value* is used.
- fill_value** [number, optional] If provided, the value to use for points outside of the interpolation domain. If None, values outside the domain are extrapolated.

See also:

[*NearestNDInterpolator*](#)

Nearest neighbor interpolation on unstructured data in N dimensions

[*LinearNDInterpolator*](#)

Piecewise linear interpolant on unstructured data in N dimensions

Notes

Contrary to `LinearNDInterpolator` and `NearestNDInterpolator`, this class avoids expensive triangulation of the input data by taking advantage of the regular grid structure.

If any of *points* have a dimension of size 1, linear interpolation will return an array of *nan* values. Nearest-neighbor interpolation will work as usual in this case.

New in version 0.14.

References

[1], [2], [3]

Examples

Evaluate a simple example function on the points of a 3-D grid:

```
>>> from scipy.interpolate import RegularGridInterpolator
>>> def f(x, y, z):
...     return 2 * x**3 + 3 * y**2 - z
>>> x = np.linspace(1, 4, 11)
>>> y = np.linspace(4, 7, 22)
>>> z = np.linspace(7, 9, 33)
>>> data = f(*np.meshgrid(x, y, z, indexing='ij', sparse=True))
```

`data` is now a 3-D array with `data[i,j,k] = f(x[i], y[j], z[k])`. Next, define an interpolating function from this data:

```
>>> my_interpolating_function = RegularGridInterpolator((x, y, z), data)
```

Evaluate the interpolating function at the two points $(x, y, z) = (2.1, 6.2, 8.3)$ and $(3.3, 5.2, 7.1)$:

```
>>> pts = np.array([[2.1, 6.2, 8.3], [3.3, 5.2, 7.1]])
>>> my_interpolating_function(pts)
array([ 125.80469388,  146.30069388])
```

which is indeed a close approximation to $[f(2.1, 6.2, 8.3), f(3.3, 5.2, 7.1)]$.

Methods

<code>__call__(self, xi[, method])</code>	Interpolation at coordinates
---	------------------------------

scipy.interpolate.RegularGridInterpolator.__call__

RegularGridInterpolator.__call__(self, xi, method=None)
 Interpolation at coordinates

Parameters

xi [ndarray of shape (... , ndim)] The coordinates to sample the gridded data at
method [str] The method of interpolation to perform. Supported are “linear” and “nearest”.

scipy.interpolate.RectBivariateSpline

class scipy.interpolate.RectBivariateSpline(x, y, z, bbox=[None, None, None, None], kx=3, ky=3, s=0)

Bivariate spline approximation over a rectangular mesh.

Can be used for both smoothing and interpolating data.

Parameters

x,y [array_like] 1-D arrays of coordinates in strictly ascending order.
z [array_like] 2-D array of data with shape (x.size,y.size).
bbox [array_like, optional] Sequence of length 4 specifying the boundary of the rectangular approximation domain. By default, bbox=[min(x), max(x), min(y), max(y)].
kx, ky [ints, optional] Degrees of the bivariate spline. Default is 3.
s [float, optional] Positive smoothing factor defined for estimation condition: $\sum((z[i] - f(x[i], y[i]))**2, axis=0) \leq s$ where f is a spline function. Default is s=0, which is for interpolation.

See also:

BivariateSpline

a base class for bivariate splines.

UnivariateSpline

a smooth univariate spline to fit a given set of data points.

SmoothBivariateSpline

a smoothing bivariate spline through the given points

LSQBivariateSpline

a bivariate spline using weighted least-squares fitting

RectSphereBivariateSpline

a bivariate spline over a rectangular mesh on a sphere

SmoothSphereBivariateSpline

a smoothing bivariate spline in spherical coordinates

LSQSphereBivariateSpline

a bivariate spline in spherical coordinates using weighted least-squares fitting

bisplrep

a function to find a bivariate B-spline representation of a surface

bisplev

a function to evaluate a bivariate B-spline and its derivatives

Methods

<code>__call__(self, x, y[, dx, dy, grid])</code>	Evaluate the spline or its derivatives at given positions.
<code>ev(self, xi, yi[, dx, dy])</code>	Evaluate the spline at points
<code>get_coeffs(self)</code>	Return spline coefficients.
<code>get_knots(self)</code>	Return a tuple (tx,ty) where tx,ty contain knots positions of the spline with respect to x-, y-variable, respectively.
<code>get_residual(self)</code>	Return weighted sum of squared residuals of the spline approximation: $\sum ((w[i]*(z[i]-s(x[i],y[i])))^2, axis=0)$
<code>integral(self, xa, xb, ya, yb)</code>	Evaluate the integral of the spline over area [xa,xb] x [ya,yb].

scipy.interpolate.RectBivariateSpline.__call__

`RectBivariateSpline.__call__(self, x, y, dx=0, dy=0, grid=True)`

Evaluate the spline or its derivatives at given positions.

Parameters

x, y	[array_like] Input coordinates. If <i>grid</i> is False, evaluate the spline at points $(x[i], y[i]), i=0, \dots, \text{len}(x)-1$. Standard Numpy broadcasting is obeyed. If <i>grid</i> is True: evaluate spline at the grid points defined by the coordinate arrays x, y. The arrays must be sorted to increasing order. Note that the axis ordering is inverted relative to the output of meshgrid.
dx	[int] Order of x-derivative New in version 0.14.0.
dy	[int] Order of y-derivative New in version 0.14.0.
grid	[bool] Whether to evaluate the results on a grid spanned by the input arrays, or at points specified by the input arrays. New in version 0.14.0.

scipy.interpolate.RectBivariateSpline.ev

`RectBivariateSpline.ev(self, xi, yi, dx=0, dy=0)`

Evaluate the spline at points

Returns the interpolated value at $(xi[i], yi[i]), i=0, \dots, \text{len}(xi)-1$.

Parameters

xi, yi	[array_like] Input coordinates. Standard Numpy broadcasting is obeyed.
dx	[int, optional] Order of x-derivative New in version 0.14.0.
dy	[int, optional] Order of y-derivative New in version 0.14.0.

scipy.interpolate.RectBivariateSpline.get_coeffs

RectBivariateSpline.**get_coeffs** (*self*)
 Return spline coefficients.

scipy.interpolate.RectBivariateSpline.get_knots

RectBivariateSpline.**get_knots** (*self*)
 Return a tuple (tx,ty) where tx,ty contain knots positions of the spline with respect to x-, y-variable, respectively. The position of interior and additional knots are given as t[k+1:-k-1] and t[:k+1]=b, t[-k-1:]=e, respectively.

scipy.interpolate.RectBivariateSpline.get_residual

RectBivariateSpline.**get_residual** (*self*)
 Return weighted sum of squared residuals of the spline approximation: $\sum ((w[i]*(z[i]-s(x[i],y[i])))**2,axis=0)$

scipy.interpolate.RectBivariateSpline.integral

RectBivariateSpline.**integral** (*self, xa, xb, ya, yb*)
 Evaluate the integral of the spline over area [xa,xb] x [ya,yb].

Parameters

xa, xb [float] The end-points of the x integration interval.
ya, yb [float] The end-points of the y integration interval.

Returns

integ [float] The value of the resulting integral.

See also:

[*scipy.ndimage.map_coordinates*](#)

Tensor product polynomials:

<i>NdPPoly</i> (c, x[, extrapolate])	Piecewise tensor product polynomial
--------------------------------------	-------------------------------------

scipy.interpolate.NdPPoly

class `scipy.interpolate.NdPPoly` (*c, x, extrapolate=None*)
 Piecewise tensor product polynomial

The value at point $x_p = (x', y', z', \dots)$ is evaluated by first computing the interval indices *i* such that:

```
x[0][i[0]] <= x' < x[0][i[0]+1]
x[1][i[1]] <= y' < x[1][i[1]+1]
...
```

and then computing:

```
S = sum(c[k0-m0-1, ..., kn-mn-1, i[0], ..., i[n]]
        * (xp[0] - x[0][i[0]])**m0
        * ...
        * (xp[n] - x[n][i[n]])**mn
        for m0 in range(k[0]+1)
```

(continues on next page)

(continued from previous page)

```

...
for mn in range(k[n]+1)

```

where $k[j]$ is the degree of the polynomial in dimension j . This representation is the piecewise multivariate power basis.

Parameters

- c** [ndarray, shape (k0, ..., kn, m0, ..., mn, ...)] Polynomial coefficients, with polynomial order k_j and m_j+1 intervals for each dimension j .
- x** [ndim-tuple of ndarrays, shapes (mj+1,)] Polynomial breakpoints for each dimension. These must be sorted in increasing order.
- extrapolate** [bool, optional] Whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs. Default: True.

See also:

PPoly

piecewise polynomials in 1D

Notes

High-order polynomials in the power basis can be numerically unstable.

Attributes

- x** [tuple of ndarrays] Breakpoints.
- c** [ndarray] Coefficients of the polynomials.

Methods

<code>__call__(self, x[, nu, extrapolate])</code>	Evaluate the piecewise polynomial or its derivative
<code>derivative(self, nu)</code>	Construct a new piecewise polynomial representing the derivative.
<code>antiderivative(self, nu)</code>	Construct a new piecewise polynomial representing the antiderivative.
<code>integrate(self, ranges[, extrapolate])</code>	Compute a definite integral over a piecewise polynomial.
<code>integrate_1d(self, a, b, axis[, extrapolate])</code>	Compute NdPPoly representation for one dimensional definite integral
<code>construct_fast(c, x[, extrapolate])</code>	Construct the piecewise polynomial without making checks.

scipy.interpolate.NdPPoly.__call__`NdPPoly.__call__(self, x, nu=None, extrapolate=None)`

Evaluate the piecewise polynomial or its derivative

Parameters

- x** [array-like] Points to evaluate the interpolant at.
- nu** [tuple, optional] Orders of derivatives to evaluate. Each must be non-negative.
- extrapolate** [bool, optional] Whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs.

Returns

- y** [array-like] Interpolated values. Shape is determined by replacing the interpolation axis in the original array with the shape of `x`.

Notes

Derivatives are evaluated piecewise for each polynomial segment, even if the polynomial is not differentiable at the breakpoints. The polynomial intervals are considered half-open, $[a, b)$, except for the last interval which is closed $[a, b]$.

scipy.interpolate.NdPPoly.derivative`NdPPoly.derivative(self, nu)`

Construct a new piecewise polynomial representing the derivative.

Parameters

- nu** [ndim-tuple of int] Order of derivatives to evaluate for each dimension. If negative, the antiderivative is returned.

Returns

- pp** [NdPPoly] Piecewise polynomial of orders $(k[0] - nu[0], \dots, k[n] - nu[n])$ representing the derivative of this polynomial.

Notes

Derivatives are evaluated piecewise for each polynomial segment, even if the polynomial is not differentiable at the breakpoints. The polynomial intervals in each dimension are considered half-open, $[a, b)$, except for the last interval which is closed $[a, b]$.

scipy.interpolate.NdPPoly.antiderivative`NdPPoly.antiderivative(self, nu)`

Construct a new piecewise polynomial representing the antiderivative.

Antiderivative is also the indefinite integral of the function, and derivative is its inverse operation.

Parameters

- nu** [ndim-tuple of int] Order of derivatives to evaluate for each dimension. If negative, the derivative is returned.

Returns

- pp** [PPoly] Piecewise polynomial of order $k_2 = k + n$ representing the antiderivative of this polynomial.

Notes

The antiderivative returned by this function is continuous and continuously differentiable to order $n-1$, up to floating point rounding error.

scipy.interpolate.NdPPoly.integrate

`NdPPoly.integrate` (*self*, *ranges*, *extrapolate=None*)

Compute a definite integral over a piecewise polynomial.

Parameters

ranges [ndim-tuple of 2-tuples float] Sequence of lower and upper bounds for each dimension, $[(a[0], b[0]), \dots, (a[ndim-1], b[ndim-1])]$

extrapolate [bool, optional] Whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs.

Returns

ig [array_like] Definite integral of the piecewise polynomial over $[a[0], b[0]] \times \dots \times [a[ndim-1], b[ndim-1]]$

scipy.interpolate.NdPPoly.integrate_1d

`NdPPoly.integrate_1d` (*self*, *a*, *b*, *axis*, *extrapolate=None*)

Compute NdPPoly representation for one dimensional definite integral

The result is a piecewise polynomial representing the integral:

$$p(y, z, \dots) = \int_a^b dx p(x, y, z, \dots)$$

where the dimension integrated over is specified with the *axis* parameter.

Parameters

a, b [float] Lower and upper bound for integration.

axis [int] Dimension over which to compute the 1-D integrals

extrapolate [bool, optional] Whether to extrapolate to out-of-bounds points based on first and last intervals, or to return NaNs.

Returns

ig [NdPPoly or array-like] Definite integral of the piecewise polynomial over $[a, b]$. If the polynomial was 1D, an array is returned, otherwise, an NdPPoly object.

scipy.interpolate.NdPPoly.construct_fast

`classmethod NdPPoly.construct_fast` (*c*, *x*, *extrapolate=None*)

Construct the piecewise polynomial without making checks.

Takes the same parameters as the constructor. Input arguments *c* and *x* must be arrays of the correct shape and type. The *c* array can only be of dtypes float and complex, and *x* array must have dtype float.

6.8.3 1-D Splines

<code>BSpline(t, c, k[, extrapolate, axis])</code>	Univariate spline in the B-spline basis.
<code>make_interp_spline(x, y[, k, t, bc_type, ...])</code>	Compute the (coefficients of) interpolating B-spline.
<code>make_lsq_spline(x, y, t[, k, w, axis, ...])</code>	Compute the (coefficients of) an LSQ B-spline.

scipy.interpolate.BSpline

class `scipy.interpolate.BSpline` (*t, c, k, extrapolate=True, axis=0*)
 Univariate spline in the B-spline basis.

$$S(x) = \sum_{j=0}^{n-1} c_j B_{j,k;t}(x)$$

where $B_{j,k;t}$ are B-spline basis functions of degree k and knots t .

Parameters

t	[ndarray, shape (n+k+1,)] knots
c	[ndarray, shape (>=n, ...)] spline coefficients
k	[int] B-spline degree
extrapolate	[bool or 'periodic', optional] whether to extrapolate beyond the base interval, $t[k] \dots t[n]$, or to return nans. If True, extrapolates the first and last polynomial pieces of b-spline functions active on the base interval. If 'periodic', periodic extrapolation is used. Default is True.
axis	[int, optional] Interpolation axis. Default is zero.

Notes

B-spline basis elements are defined via

$$B_{i,0}(x) = 1, \text{ if } t_i \leq x < t_{i+1}, \text{ otherwise } 0,$$

$$B_{i,k}(x) = \frac{x - t_i}{t_{i+k} - t_i} B_{i,k-1}(x) + \frac{t_{i+k+1} - x}{t_{i+k+1} - t_{i+1}} B_{i+1,k-1}(x)$$

Implementation details

- At least $k+1$ coefficients are required for a spline of degree k , so that $n \geq k+1$. Additional coefficients, $c[j]$ with $j > n$, are ignored.
- B-spline basis elements of degree k form a partition of unity on the *base interval*, $t[k] \leq x \leq t[n]$.

References

[1], [2]

Examples

Translating the recursive definition of B-splines into Python code, we have:

```
>>> def B(x, k, i, t):
...     if k == 0:
...         return 1.0 if t[i] <= x < t[i+1] else 0.0
...     if t[i+k] == t[i]:
...         c1 = 0.0
...     else:
...         c1 = (x - t[i]) / (t[i+k] - t[i]) * B(x, k-1, i, t)
...     if t[i+k+1] == t[i+1]:
...         c2 = 0.0
...     else:
...         c2 = (t[i+k+1] - x) / (t[i+k+1] - t[i+1]) * B(x, k-1, i+1, t)
...     return c1 + c2
```

```
>>> def bspline(x, t, c, k):
...     n = len(t) - k - 1
...     assert (n >= k+1) and (len(c) >= n)
...     return sum(c[i] * B(x, k, i, t) for i in range(n))
```

Note that this is an inefficient (if straightforward) way to evaluate B-splines — this spline class does it in an equivalent, but much more efficient way.

Here we construct a quadratic spline function on the base interval $2 \leq x \leq 4$ and compare with the naive way of evaluating the spline:


```
>>> from scipy.interpolate import BSpline
>>> k = 2
>>> t = [0, 1, 2, 3, 4, 5, 6]
>>> c = [-1, 2, 0, -1]
>>> spl = BSpline(t, c, k)
>>> spl(2.5)
array(1.375)
>>> bspline(2.5, t, c, k)
1.375
```

Note that outside of the base interval results differ. This is because *BSpline* extrapolates the first and last polynomial pieces of B-spline functions active on the base interval.

```
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots()
>>> xx = np.linspace(1.5, 4.5, 50)
>>> ax.plot(xx, [bspline(x, t, c, k) for x in xx], 'r-', lw=3, label=
↳ 'naive')
>>> ax.plot(xx, spl(xx), 'b-', lw=4, alpha=0.7, label='BSpline')
>>> ax.grid(True)
>>> ax.legend(loc='best')
>>> plt.show()
```

Attributes

t	[ndarray] knot vector
c	[ndarray] spline coefficients



k [int] spline degree
extrapolate [bool] If True, extrapolates the first and last polynomial pieces of b-spline functions active on the base interval.
axis [int] Interpolation axis.
tck [tuple] Equivalent to `(self.t, self.c, self.k)` (read-only).

Methods

<code>__call__(self, x[, nu, extrapolate])</code>	Evaluate a spline function.
<code>basis_element(t[, extrapolate])</code>	Return a B-spline basis element $B(x \mid t[0], \dots, t[k+1])$.
<code>derivative(self[, nu])</code>	Return a B-spline representing the derivative.
<code>antiderivative(self[, nu])</code>	Return a B-spline representing the antiderivative.
<code>integrate(self, a, b[, extrapolate])</code>	Compute a definite integral of the spline.
<code>construct_fast(t, c, k[, extrapolate, axis])</code>	Construct a spline without making checks.

`scipy.interpolate.BSpline.__call__`

`BSpline.__call__(self, x, nu=0, extrapolate=None)`

Evaluate a spline function.

Parameters

x [array_like] points to evaluate the spline at.

nu: int, optional
 derivative to evaluate (default is 0).

extrapolate [bool or 'periodic', optional] whether to extrapolate based on the first and last intervals or return nans. If 'periodic', periodic extrapolation is used. Default is `self.extrapolate`.

Returns

y [array_like] Shape is determined by replacing the interpolation axis in the coefficient array with the shape of `x`.

`scipy.interpolate.BSpline.basis_element`

886 `classmethod` `BSpline.basis_element(t, extrapolate=True)`
 Return a B-spline basis element $B(x \mid t[0], \dots, t[k+1])$.

Parameters

Notes

The degree of the B-spline, k , is inferred from the length of t as $\text{len}(t) - 2$. The knot vector is constructed by appending and prepending $k+1$ elements to internal knots t .

Examples


Construct a cubic B-spline:

```
>>> from scipy.interpolate import BSpline
>>> b = BSpline.basis_element([0, 1, 2, 3, 4])
>>> k = b.k
>>> b.t[k:-k]
array([ 0.,  1.,  2.,  3.,  4.])
>>> k
3
```

Construct a quadratic B-spline on $[0, 1, 1, 2]$, and compare to its explicit form:

```
>>> t = [-1, 0, 1, 1, 2]
>>> b = BSpline.basis_element(t[1:])
>>> def f(x):
...     return np.where(x < 1, x*x, (2. - x)**2)
```

```
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots()
>>> x = np.linspace(0, 2, 51)
>>> ax.plot(x, b(x), 'g', lw=3)
>>> ax.plot(x, f(x), 'r', lw=8, alpha=0.4)
>>> ax.grid(True)
>>> plt.show()
```



scipy.interpolate.BSpline.derivative`BSpline.derivative` (*self*, *nu=1*)

Return a B-spline representing the derivative.

Parameters**nu** [int, optional] Derivative order. Default is 1.**Returns****b** [BSpline object] A new instance representing the derivative.**See also:***splder*, *splantider***scipy.interpolate.BSpline.antiderivative**`BSpline.antiderivative` (*self*, *nu=1*)

Return a B-spline representing the antiderivative.

Parameters**nu** [int, optional] Antiderivative order. Default is 1.**Returns****b** [BSpline object] A new instance representing the antiderivative.**See also:***splder*, *splantider***Notes**

If antiderivative is computed and `self.extrapolate='periodic'`, it will be set to `False` for the returned instance. This is done because the antiderivative is no longer periodic and its correct evaluation outside of the initially given `x` interval is difficult.

scipy.interpolate.BSpline.integrate`BSpline.integrate` (*self*, *a*, *b*, *extrapolate=None*)

Compute a definite integral of the spline.

Parameters**a** [float] Lower limit of integration.**b** [float] Upper limit of integration.**extrapolate**[bool or 'periodic', optional] whether to extrapolate beyond the base interval, `t[k]` . . . `t[-k-1]`, or take the spline to be zero outside of the base interval. If 'periodic', periodic extrapolation is used. If `None` (default), use `self.extrapolate`.**Returns****I** [array_like] Definite integral of the spline over the interval `[a, b]`.

Examples


Construct the linear spline x if $x < 1$ else $2 - x$ on the base interval $[0, 2]$, and integrate it

```
>>> from scipy.interpolate import BSpline
>>> b = BSpline.basis_element([0, 1, 2])
>>> b.integrate(0, 1)
array(0.5)
```

If the integration limits are outside of the base interval, the result is controlled by the *extrapolate* parameter

```
>>> b.integrate(-1, 1)
array(0.0)
>>> b.integrate(-1, 1, extrapolate=False)
array(0.5)
```

```
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots()
>>> ax.grid(True)
>>> ax.axvline(0, c='r', lw=5, alpha=0.5) # base interval
>>> ax.axvline(2, c='r', lw=5, alpha=0.5)
>>> xx = [-1, 1, 2]
>>> ax.plot(xx, b(xx))
>>> plt.show()
```



scipy.interpolate.BSpline.construct_fast

classmethod BSpline.**construct_fast** (*t*, *c*, *k*, *extrapolate=True*, *axis=0*)
 Construct a spline without making checks.

Accepts same parameters as the regular constructor. Input arrays *t* and *c* must of correct shape and dtype.

scipy.interpolate.make_interp_spline

scipy.interpolate.**make_interp_spline** (*x*, *y*, *k=3*, *t=None*, *bc_type=None*, *axis=0*,
check_finite=True)

Compute the (coefficients of) interpolating B-spline.

Parameters

- x** [array_like, shape (n,)] Abscissas.
- y** [array_like, shape (n, ...)] Ordinates.
- k** [int, optional] B-spline degree. Default is cubic, k=3.
- t** [array_like, shape (nt + k + 1,), optional.] Knots. The number of knots needs to agree with the number of datapoints and the number of derivatives at the edges. Specifically, $nt - n$ must equal $\text{len}(\text{deriv}_l) + \text{len}(\text{deriv}_r)$.
- bc_type** [2-tuple or None] Boundary conditions. Default is None, which means choosing the boundary conditions automatically. Otherwise, it must be a length-two tuple where the first element sets the boundary conditions at $x[0]$ and the second element sets the boundary conditions at $x[-1]$. Each of these must be an iterable of pairs (*order*, *value*) which gives the values of derivatives of specified orders at the given edge of the interpolation interval. Alternatively, the following string aliases are recognized:
 - **"clamped": The first derivatives at the ends are zero. This is**
 equivalent to `bc_type=([(1, 0.0)], [(1, 0.0)])`.
 - **"natural": The second derivatives at ends are zero. This is equivalent to**
`bc_type=([(2, 0.0)], [(2, 0.0)])`.
 - **"not-a-knot" (default): The first and second segments are the same polynomial. This is equivalent to having** `bc_type=None`.
- axis** [int, optional] Interpolation axis. Default is 0.
- check_finite** [bool, optional] Whether to check that the input arrays contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs. Default is True.

Returns

- b** [a BSpline object of the degree *k* and with knots *t*.]

See also:

BSpline

base class representing the B-spline objects

CubicSpline

a cubic spline in the polynomial basis

make_lsq_spline

a similar factory function for spline fitting

UnivariateSpline

a wrapper over FITPACK spline fitting routines

splrep

a wrapper over FITPACK spline fitting routines

Examples

Use cubic interpolation on Chebyshev nodes:

```
>>> def cheb_nodes(N):
...     jj = 2.*np.arange(N) + 1
...     x = np.cos(np.pi * jj / 2 / N)[::-1]
...     return x
```

```
>>> x = cheb_nodes(20)
>>> y = np.sqrt(1 - x**2)
```

```
>>> from scipy.interpolate import BSpline, make_interp_spline
>>> b = make_interp_spline(x, y)
>>> np.allclose(b(x), y)
True
```

Note that the default is a cubic spline with a not-a-knot boundary condition

```
>>> b.k
3
```

Here we use a 'natural' spline, with zero 2nd derivatives at edges:

```
>>> l, r = [(2, 0.0)], [(2, 0.0)]
>>> b_n = make_interp_spline(x, y, bc_type=(l, r)) # or, bc_type="natural
↳"
>>> np.allclose(b_n(x), y)
True
>>> x0, x1 = x[0], x[-1]
>>> np.allclose([b_n(x0, 2), b_n(x1, 2)], [0, 0])
True
```

Interpolation of parametric curves is also supported. As an example, we compute a discretization of a snail curve in polar coordinates

```
>>> phi = np.linspace(0, 2.*np.pi, 40)
>>> r = 0.3 + np.cos(phi)
>>> x, y = r*np.cos(phi), r*np.sin(phi) # convert to Cartesian_
↳coordinates
```

Build an interpolating curve, parameterizing it by the angle


```
>>> from scipy.interpolate import make_interp_spline
>>> spl = make_interp_spline(phi, np.c_[x, y])
```

Evaluate the interpolant on a finer grid (note that we transpose the result to unpack it into a pair of x- and y-arrays)

```
>>> phi_new = np.linspace(0, 2.*np.pi, 100)
>>> x_new, y_new = spl(phi_new).T
```

Plot the result

```
>>> import matplotlib.pyplot as plt
>>> plt.plot(x, y, 'o')
>>> plt.plot(x_new, y_new, '-')
>>> plt.show()
```



scipy.interpolate.make_lsq_spline

`scipy.interpolate.make_lsq_spline(x, y, t, k=3, w=None, axis=0, check_finite=True)`
 Compute the (coefficients of) an LSQ B-spline.

The result is a linear combination

$$S(x) = \sum_j c_j B_j(x; t)$$

of the B-spline basis elements, $B_j(x; t)$, which minimizes

$$\sum_j (w_j \times (S(x_j) - y_j))^2$$

Parameters

- x** [array_like, shape (m,)] Abscissas.
- y** [array_like, shape (m, ...)] Ordinates.
- t** [array_like, shape (n + k + 1,)] Knots. Knots and data points must satisfy Schoenberg-Whitney conditions.
- k** [int, optional] B-spline degree. Default is cubic, k=3.
- w** [array_like, shape (n,), optional] Weights for spline fitting. Must be positive. If None, then weights are all equal. Default is None.
- axis** [int, optional] Interpolation axis. Default is zero.
- check_finite** [bool, optional] Whether to check that the input arrays contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs. Default is True.

Returns

b [a BSpline object of the degree k with knots t .]

See also:**BSpline**

base class representing the B-spline objects

make_interp_spline

a similar factory function for interpolating splines

LSQUnivariateSpline

a FITPACK-based spline fitting routine

splrep

a FITPACK-based fitting routine

Notes

The number of data points must be larger than the spline degree k .

Knots t must satisfy the Schoenberg-Whitney conditions, i.e., there must be a subset of data points $x[j]$ such that $t[j] < x[j] < t[j+k+1]$, for $j=0, 1, \dots, n-k-2$.

Examples

Generate some noisy data:

```
>>> x = np.linspace(-3, 3, 50)
>>> y = np.exp(-x**2) + 0.1 * np.random.randn(50)
```

Now fit a smoothing cubic spline with a pre-defined internal knots. Here we make the knot vector $(k+1)$ -regular by adding boundary knots:

```
>>> from scipy.interpolate import make_lsq_spline, BSpline
>>> t = [-1, 0, 1]
>>> k = 3
>>> t = np.r_[(x[0],) * (k+1),
...         t,
...         (x[-1],) * (k+1)]
>>> spl = make_lsq_spline(x, y, t, k)
```

For comparison, we also construct an interpolating spline for the same set of data:

```
>>> from scipy.interpolate import make_interp_spline
>>> spl_i = make_interp_spline(x, y)
```

Plot both:


```
>>> import matplotlib.pyplot as plt
>>> xs = np.linspace(-3, 3, 100)
>>> plt.plot(x, y, 'ro', ms=5)
```

(continues on next page)

(continued from previous page)

```

>>> plt.plot(xs, spl(xs), 'g-', lw=3, label='LSQ spline')
>>> plt.plot(xs, spl_i(xs), 'b-', lw=3, alpha=0.7, label='interp spline')
>>> plt.legend(loc='best')
>>> plt.show()
    
```



NaN handling: If the input arrays contain nan values, the result is not useful since the underlying spline fitting routines cannot deal with nan. A workaround is to use zero weights for not-a-number data points:

```

>>> y[8] = np.nan
>>> w = np.isnan(y)
>>> y[w] = 0.
>>> tck = make_lsq_spline(x, y, t, w=~w)
    
```

Notice the need to replace a nan by a numerical value (precise value does not matter as long as the corresponding weight is zero.)

Functional interface to FITPACK routines:

<code>splrep(x, y[, w, xb, xe, k, task, s, t, ...])</code>	Find the B-spline representation of a 1-D curve.
<code>splprep(x[, w, u, ub, ue, k, task, s, t, ...])</code>	Find the B-spline representation of an N-D curve.
<code>splev(x, tck[, der, ext])</code>	Evaluate a B-spline or its derivatives.
<code>splint(a, b, tck[, full_output])</code>	Evaluate the definite integral of a B-spline between two given points.
<code>sproot(tck[, mest])</code>	Find the roots of a cubic B-spline.
<code>spalde(x, tck)</code>	Evaluate all derivatives of a B-spline.
<code>splder(tck[, n])</code>	Compute the spline representation of the derivative of a given spline
<code>splantider(tck[, n])</code>	Compute the spline for the antiderivative (integral) of a given spline.
<code>insert(x, tck[, m, per])</code>	Insert knots into a B-spline.

scipy.interpolate.splprep

`scipy.interpolate.splprep(x, y, w=None, xb=None, xe=None, k=3, task=0, s=None, t=None, full_output=0, per=0, quiet=1)`

Find the B-spline representation of a 1-D curve.

Given the set of data points $(x[i], y[i])$ determine a smooth spline approximation of degree k on the interval $x_b \leq x \leq x_e$.

Parameters

x, y	[array_like] The data points defining a curve $y = f(x)$.
w	[array_like, optional] Strictly positive rank-1 array of weights the same length as x and y . The weights are used in computing the weighted least-squares spline fit. If the errors in the y values have standard-deviation given by the vector d , then w should be $1/d$. Default is <code>ones(len(x))</code> .
xb, xe	[float, optional] The interval to fit. If <code>None</code> , these default to $x[0]$ and $x[-1]$ respectively.
k	[int, optional] The degree of the spline fit. It is recommended to use cubic splines. Even values of k should be avoided especially with small s values. $1 \leq k \leq 5$
task	[{1, 0, -1}, optional] If <code>task==0</code> find t and c for a given smoothing factor, s . If <code>task==1</code> find t and c for another value of the smoothing factor, s . There must have been a previous call with <code>task=0</code> or <code>task=1</code> for the same set of data (t will be stored an used internally) If <code>task=-1</code> find the weighted least square spline for a given set of knots, t . These should be interior knots as knots on the ends will be added automatically.
s	[float, optional] A smoothing condition. The amount of smoothness is determined by satisfying the conditions: $\text{sum}((w * (y - g))**2, \text{axis}=0) \leq s$ where $g(x)$ is the smoothed interpolation of (x,y) . The user can use s to control the tradeoff between closeness and smoothness of fit. Larger s means more smoothing while smaller values of s indicate less smoothing. Recommended values of s depend on the weights, w . If the weights represent the inverse of the standard-deviation of y , then a good s value should be found in the range $(m - \sqrt{2*m}, m + \sqrt{2*m})$ where m is the number of datapoints in x , y , and w . default : $s = m - \sqrt{2*m}$ if weights are supplied. $s = 0.0$ (interpolating) if no weights are supplied.
t	[array_like, optional] The knots needed for <code>task=-1</code> . If given then <code>task</code> is automatically set to <code>-1</code> .
full_output	[bool, optional] If non-zero, then return optional outputs.
per	[bool, optional] If non-zero, data points are considered periodic with period $x[m-1] - x[0]$ and a smooth periodic spline approximation is returned. Values of $y[m-1]$ and $w[m-1]$ are not used.
quiet	[bool, optional] Non-zero to suppress messages. This parameter is deprecated; use standard Python warning filters instead.

Returns

tck	[tuple] A tuple (t,c,k) containing the vector of knots, the B-spline coefficients, and the degree of the spline.
fp	[array, optional] The weighted sum of squared residuals of the spline approximation.
ier	[int, optional] An integer flag about <code>splprep</code> success. Success is indicated if <code>ier<=0</code> . If <code>ier</code> in $[1,2,3]$ an error occurred but was not raised. Otherwise an error is raised.
msg	[str, optional] A message corresponding to the integer flag, <code>ier</code> .

See also:

UnivariateSpline, BivariateSpline
splprep, splev, sproot, spalde, splint
bisplrep, bisplev

*BSpline**make_interp_spline*

Notes

See *splev* for evaluation of the spline and its derivatives. Uses the FORTRAN routine *curfit* from FITPACK.

The user is responsible for assuring that the values of x are unique. Otherwise, *splrep* will not return sensible results.

If provided, knots t must satisfy the Schoenberg-Whitney conditions, i.e., there must be a subset of data points $x[j]$ such that $t[j] < x[j] < t[j+k+1]$, for $j=0, 1, \dots, n-k-2$.

This routine zero-pads the coefficients array c to have the same length as the array of knots t (the trailing $k + 1$ coefficients are ignored by the evaluation routines, *splev* and *BSpline*.) This is in contrast with *splprep*, which does not zero-pad the coefficients.

References

Based on algorithms described in [1], [2], [3], and [4]:

[1], [2], [3], [4]

Examples

You can interpolate 1-D points with a B-spline curve. Further examples are given in *in the tutorial*.

```
>>> import matplotlib.pyplot as plt
>>> from scipy.interpolate import splev, splrep
>>> x = np.linspace(0, 10, 10)
>>> y = np.sin(x)
>>> spl = splrep(x, y)
>>> x2 = np.linspace(0, 10, 200)
>>> y2 = splev(x2, spl)
>>> plt.plot(x, y, 'o', x2, y2)
>>> plt.show()
```

scipy.interpolate.splprep

`scipy.interpolate.splprep`($x, w=None, u=None, ub=None, ue=None, k=3, task=0, s=None, t=None, full_output=0, nest=None, per=0, quiet=1$)


Find the B-spline representation of an N-D curve.

Given a list of N rank-1 arrays, x , which represent a curve in N-D space parametrized by u , find a smooth approximating spline curve $g(u)$. Uses the FORTRAN routine *parcur* from FITPACK.

Parameters

x [array_like] A list of sample vector arrays representing the curve.

w [array_like, optional] Strictly positive rank-1 array of weights the same length as $x[0]$. The weights are used in computing the weighted least-squares spline fit. If the errors in the x values have standard-deviation given by the vector d , then w should be $1/d$. Default is `ones(len(x[0]))`.



- u** [array_like, optional] An array of parameter values. If not given, these values are calculated automatically as $M = \text{len}(x[0])$, where
- $$v[0] = 0$$
- $$v[i] = v[i-1] + \text{distance}(x[i], x[i-1])$$
- $$u[i] = v[i] / v[M-1]$$
- ub, ue** [int, optional] The end-points of the parameters interval. Defaults to $u[0]$ and $u[-1]$.
- k** [int, optional] Degree of the spline. Cubic splines are recommended. Even values of k should be avoided especially with a small s -value. $1 \leq k \leq 5$, default is 3.
- task** [int, optional] If $\text{task}=0$ (default), find t and c for a given smoothing factor, s . If $\text{task}=1$, find t and c for another value of the smoothing factor, s . There must have been a previous call with $\text{task}=0$ or $\text{task}=1$ for the same set of data. If $\text{task}=-1$ find the weighted least square spline for a given set of knots, t .
- s** [float, optional] A smoothing condition. The amount of smoothness is determined by satisfying the conditions: $\text{sum}(w * (y - g)**2, \text{axis}=0) \leq s$, where $g(x)$ is the smoothed interpolation of (x,y) . The user can use s to control the trade-off between closeness and smoothness of fit. Larger s means more smoothing while smaller values of s indicate less smoothing. Recommended values of s depend on the weights, w . If the weights represent the inverse of the standard-deviation of y , then a good s value should be found in the range $(m - \sqrt{2*m}, m + \sqrt{2*m})$, where m is the number of data points in x, y , and w .
- t** [int, optional] The knots needed for $\text{task}=-1$.
- full_output** [int, optional] If non-zero, then return optional outputs.
- nest** [int, optional] An over-estimate of the total number of knots of the spline to help in determining the storage space. By default $\text{nest}=m/2$. Always large enough is $\text{nest}=m+k+1$.
- per** [int, optional] If non-zero, data points are considered periodic with period $x[m-1] - x[0]$ and a smooth periodic spline approximation is returned. Values of $y[m-1]$ and $w[m-1]$ are not used.
- quiet** [int, optional] Non-zero to suppress messages. This parameter is deprecated; use standard Python warning filters instead.

Returns

- tkc** [tuple] (t,c,k) a tuple containing the vector of knots, the B-spline coefficients, and the degree of the spline.
- u** [array] An array of the values of the parameter.

fp	[float] The weighted sum of squared residuals of the spline approximation.
ier	[int] An integer flag about splprep success. Success is indicated if ier<=0. If ier in [1,2,3] an error occurred but was not raised. Otherwise an error is raised.
msg	[str] A message corresponding to the integer flag, ier.

See also:

splrep, splev, sproot, spalde, splint

bisplrep, bisplev

UnivariateSpline, BivariateSpline

BSpline

make_interp_spline

Notes

See *splev* for evaluation of the spline and its derivatives. The number of dimensions N must be smaller than 11.

The number of coefficients in the c array is $k+1$ less than the number of knots, $\text{len}(t)$. This is in contrast with *splrep*, which zero-pads the array of coefficients to have the same length as the array of knots. These additional coefficients are ignored by evaluation routines, *splev* and *BSpline*.

References

[1], [2], [3]

Examples

Generate a discretization of a limaçon curve in the polar coordinates:


```
>>> phi = np.linspace(0, 2.*np.pi, 40)
>>> r = 0.5 + np.cos(phi)           # polar coords
>>> x, y = r * np.cos(phi), r * np.sin(phi)   # convert to cartesian
```

And interpolate:

```
>>> from scipy.interpolate import splprep, splev
>>> tck, u = splprep([x, y], s=0)
>>> new_points = splev(u, tck)
```

Notice that (i) we force interpolation by using $s=0$, (ii) the parameterization, u , is generated automatically. Now plot the result:

```
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots()
>>> ax.plot(x, y, 'ro')
>>> ax.plot(new_points[0], new_points[1], 'r-')
>>> plt.show()
```



scipy.interpolate.splev

`scipy.interpolate.splev(x, tck, der=0, ext=0)`

Evaluate a B-spline or its derivatives.

Given the knots and coefficients of a B-spline representation, evaluate the value of the smoothing polynomial and its derivatives. This is a wrapper around the FORTRAN routines `splev` and `splder` of FITPACK.

Parameters

- x** [array_like] An array of points at which to return the value of the smoothed spline or its derivatives. If `tck` was returned from `splprep`, then the parameter values, `u` should be given.
- tck** [3-tuple or a BSpline object] If a tuple, then it should be a sequence of length 3 returned by `splprep` or `splprep` containing the knots, coefficients, and degree of the spline. (Also see Notes.)
- der** [int, optional] The order of derivative of the spline to compute (must be less than or equal to `k`, the degree of the spline).
- ext** [int, optional] Controls the value returned for elements of `x` not in the interval defined by the knot sequence.
- if `ext=0`, return the extrapolated value.
 - if `ext=1`, return 0
 - if `ext=2`, raise a `ValueError`
 - if `ext=3`, return the boundary value.
- The default value is 0.

Returns

- y** [ndarray or list of ndarrays] An array of values representing the spline function evaluated at the points in `x`. If `tck` was returned from `splprep`, then this is a list of arrays representing the curve in an N-D space.

See also:

`splprep`, `splrep`, `sproot`, `spalde`, `splint`

`bisplrep`, `bisplev`

BSpline

Notes

Manipulating the tck-tuples directly is not recommended. In new code, prefer using *BSpline* objects.

References

[1], [2], [3]

Examples

Examples are given *in the tutorial*.

scipy.interpolate.splint

`scipy.interpolate.splint` (*a, b, tck, full_output=0*)

Evaluate the definite integral of a B-spline between two given points.

Parameters

- a, b** [float] The end-points of the integration interval.
tck [tuple or a *BSpline* instance] If a tuple, then it should be a sequence of length 3, containing the vector of knots, the B-spline coefficients, and the degree of the spline (see *splev*).
full_output [int, optional] Non-zero to return optional output.

Returns

- integral** [float] The resulting integral.
wrk [ndarray] An array containing the integrals of the normalized B-splines defined on the set of knots. (Only returned if *full_output* is non-zero)

See also:

splprep, splrep, sproot, spalde, splev

bisplrep, bisplev

BSpline

Notes

splint silently assumes that the spline function is zero outside the data interval (*a, b*).

Manipulating the tck-tuples directly is not recommended. In new code, prefer using the *BSpline* objects.

References

[1], [2]

Examples

Examples are given *in the tutorial*.

scipy.interpolate.sproot

`scipy.interpolate.sproot` (*tck*, *mest=10*)

Find the roots of a cubic B-spline.

Given the knots (≥ 8) and coefficients of a cubic B-spline return the roots of the spline.

Parameters

- tck** [tuple or a BSpline object] If a tuple, then it should be a sequence of length 3, containing the vector of knots, the B-spline coefficients, and the degree of the spline. The number of knots must be ≥ 8 , and the degree must be 3. The knots must be a monotonically increasing sequence.
- mest** [int, optional] An estimate of the number of zeros (Default is 10).

Returns

- zeros** [ndarray] An array giving the roots of the spline.

See also:

splprep, *splrep*, *splint*, *spalde*, *splev*

bisplrep, *bisplev*

BSpline

Notes

Manipulating the *tck*-tuples directly is not recommended. In new code, prefer using the *BSpline* objects.

References

[1], [2], [3]

Examples

Examples are given *in the tutorial*.

scipy.interpolate.spalde

scipy.interpolate.**spalde**(*x*, *tck*)

Evaluate all derivatives of a B-spline.

Given the knots and coefficients of a cubic B-spline compute all derivatives up to order *k* at a point (or set of points).

Parameters

- x** [array_like] A point or a set of points at which to evaluate the derivatives. Note that $t(k) \leq x \leq t(n-k+1)$ must hold for each *x*.
- tck** [tuple] A tuple (*t*, *c*, *k*), containing the vector of knots, the B-spline coefficients, and the degree of the spline (see *splev*).

Returns

- results** [{ndarray, list of ndarrays}] An array (or a list of arrays) containing all derivatives up to order *k* inclusive for each point *x*.

See also:

splprep, *splrep*, *splint*, *sproot*, *splev*, *bisplrep*, *bisplev*

BSpline

References

[1], [2], [3]

Examples

Examples are given *in the tutorial*.

scipy.interpolate.splder

scipy.interpolate.**splder**(*tck*, *n=1*)

Compute the spline representation of the derivative of a given spline

Parameters

- tck** [BSpline instance or a tuple of (*t*, *c*, *k*)] Spline whose derivative to compute
- n** [int, optional] Order of derivative to evaluate. Default: 1

Returns

BSpline instance or tuple

Spline of order $k_2=k-n$ representing the derivative of the input spline. A tuple is returned iff the input argument *tck* is a tuple, otherwise a BSpline object is constructed and returned.

See also:

splantider, *splev*, *spalde*

BSpline

Notes

New in version 0.13.0.

Examples

This can be used for finding maxima of a curve:

```
>>> from scipy.interpolate import splrep, splder, sproot
>>> x = np.linspace(0, 10, 70)
>>> y = np.sin(x)
>>> spl = splrep(x, y, k=4)
```

Now, differentiate the spline and find the zeros of the derivative. (NB: `sproot` only works for order 3 splines, so we fit an order 4 spline):

```
>>> dspl = splder(spl)
>>> sproot(dspl) / np.pi
array([ 0.50000001,  1.5          ,  2.49999998])
```

This agrees well with roots $\pi/2 + n\pi$ of $\cos(x) = \sin'(x)$.

scipy.interpolate.splantider

`scipy.interpolate.splantider` (*tck*, *n=1*)

Compute the spline for the antiderivative (integral) of a given spline.

Parameters

tck [BSpline instance or a tuple of (t, c, k)] Spline whose antiderivative to compute
n [int, optional] Order of antiderivative to evaluate. Default: 1

Returns

BSpline instance or a tuple of (t2, c2, k2)

Spline of order $k2=k+n$ representing the antiderivative of the input spline. A tuple is returned iff the input argument *tck* is a tuple, otherwise a BSpline object is constructed and returned.

See also:

[*splder*](#), [*splev*](#), [*spalde*](#)

[*BSpline*](#)

Notes

The `splder` function is the inverse operation of this function. Namely, `splder(splantider(tck))` is identical to *tck*, modulo rounding error.

New in version 0.13.0.

Examples

```
>>> from scipy.interpolate import splprep, splder, splantider, splev
>>> x = np.linspace(0, np.pi/2, 70)
>>> y = 1 / np.sqrt(1 - 0.8*np.sin(x)**2)
>>> spl = splprep(x, y)
```

The derivative is the inverse operation of the antiderivative, although some floating point error accumulates:

```
>>> splev(1.7, spl), splev(1.7, splder(splantider(spl)))
(array(2.1565429877197317), array(2.1565429877201865))
```

Antiderivative can be used to evaluate definite integrals:

```
>>> ispl = splantider(spl)
>>> splev(np.pi/2, ispl) - splev(0, ispl)
2.2572053588768486
```

This is indeed an approximation to the complete elliptic integral $K(m) = \int_0^{\pi/2} [1 - m \sin^2 x]^{-1/2} dx$:

```
>>> from scipy.special import ellipk
>>> ellipk(0.8)
2.2572053268208538
```

scipy.interpolate.insert

`scipy.interpolate.insert(x, tck, m=1, per=0)`

Insert knots into a B-spline.

Given the knots and coefficients of a B-spline representation, create a new B-spline with a knot inserted m times at point x . This is a wrapper around the FORTRAN routine `insert` of FITPACK.

Parameters

- x (u)** [array_like] A 1-D point at which to insert a new knot(s). If `tck` was returned from `splprep`, then the parameter values, `u` should be given.
- tck** [a *BSpline* instance or a tuple] If tuple, then it is expected to be a tuple (t,c,k) containing the vector of knots, the B-spline coefficients, and the degree of the spline.
- m** [int, optional] The number of times to insert the given knot (its multiplicity). Default is 1.
- per** [int, optional] If non-zero, the input spline is considered periodic.

Returns

BSpline instance or a tuple

A new B-spline with knots `t`, coefficients `c`, and degree `k`. $t_{(k+1)} \leq x \leq t_{(n-k)}$, where `k` is the degree of the spline. In case of a periodic spline (`per != 0`) there must be either at least `k` interior knots `t(j)` satisfying $t_{(k+1)} < t_{(j)} \leq x$ or at least `k` interior knots `t(j)` satisfying $x \leq t_{(j)} < t_{(n-k)}$. A tuple is returned iff the input argument `tck` is a tuple, otherwise a *BSpline* object is constructed and returned.

Notes

Based on algorithms from [1] and [2].

Manipulating the tck-tuples directly is not recommended. In new code, prefer using the *BSpline* objects.

References

[1], [2]

Examples

You can insert knots into a B-spline.

```
>>> from scipy.interpolate import splrep, insert
>>> x = np.linspace(0, 10, 5)
>>> y = np.sin(x)
>>> tck = splrep(x, y)
>>> tck[0]
array([ 0.,  0.,  0.,  0.,  5., 10., 10., 10., 10.])
```

A knot is inserted:

```
>>> tck_inserted = insert(3, tck)
>>> tck_inserted[0]
array([ 0.,  0.,  0.,  0.,  3.,  5., 10., 10., 10., 10.])
```

Some knots are inserted:

```
>>> tck_inserted2 = insert(8, tck, m=3)
>>> tck_inserted2[0]
array([ 0.,  0.,  0.,  0.,  5.,  8.,  8.,  8., 10., 10., 10., 10.])
```

Object-oriented FITPACK interface:

<i>UnivariateSpline</i> (x, y[, w, bbox, k, s, ext, ...])	1-D smoothing spline fit to a given set of data points.
<i>InterpolatedUnivariateSpline</i> (x, y[, w, ...])	1-D interpolating spline for a given set of data points.
<i>LSQUnivariateSpline</i> (x, y, t[, w, bbox, k, ...])	1-D spline with explicit internal knots.

scipy.interpolate.UnivariateSpline

class `scipy.interpolate.UnivariateSpline`(x, y, w=None, bbox=[None, None], k=3, s=None, ext=0, check_finite=False)

1-D smoothing spline fit to a given set of data points.

Fits a spline $y = \text{spl}(x)$ of degree k to the provided x , y data. s specifies the number of knots by specifying a smoothing condition.

Parameters

- x** [(N,) array_like] 1-D array of independent input data. Must be increasing; must be strictly increasing if s is 0.
- y** [(N,) array_like] 1-D array of dependent input data, of the same length as x .

- w** [(N,) array_like, optional] Weights for spline fitting. Must be positive. If None (default), weights are all equal.
- bbox** [(2,) array_like, optional] 2-sequence specifying the boundary of the approximation interval. If None (default), `bbox=[x[0], x[-1]]`.
- k** [int, optional] Degree of the smoothing spline. Must be $1 \leq k \leq 5$. Default is $k = 3$, a cubic spline.
- s** [float or None, optional] Positive smoothing factor used to choose the number of knots. Number of knots will be increased until the smoothing condition is satisfied:

```
sum((w[i] * (y[i]-spl(x[i])))**2, axis=0) <= s
```

If None (default), $s = \text{len}(w)$ which should be a good value if $1/w[i]$ is an estimate of the standard deviation of $y[i]$. If 0, spline will interpolate through all data points.

- ext** [int or str, optional] Controls the extrapolation mode for elements not in the interval defined by the knot sequence.
- if `ext=0` or 'extrapolate', return the extrapolated value.
 - if `ext=1` or 'zeros', return 0
 - if `ext=2` or 'raise', raise a `ValueError`
 - if `ext=3` or 'const', return the boundary value.
- The default value is 0.

check_finite

[bool, optional] Whether to check that the input arrays contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination or non-sensical results) if the inputs do contain infinities or NaNs. Default is False.

See also:

BivariateSpline

a base class for bivariate splines.

SmoothBivariateSpline

a smoothing bivariate spline through the given points

LSQBivariateSpline

a bivariate spline using weighted least-squares fitting

RectSphereBivariateSpline

a bivariate spline over a rectangular mesh on a sphere

SmoothSphereBivariateSpline

a smoothing bivariate spline in spherical coordinates

LSQSphereBivariateSpline

a bivariate spline in spherical coordinates using weighted least-squares fitting

RectBivariateSpline

a bivariate spline over a rectangular mesh

InterpolatedUnivariateSpline

a interpolating univariate spline for a given set of data points.

bisplrep

a function to find a bivariate B-spline representation of a surface

bisplev

a function to evaluate a bivariate B-spline and its derivatives

splrep

a function to find the B-spline representation of a 1-D curve

splev

a function to evaluate a B-spline or its derivatives

sprout

a function to find the roots of a cubic B-spline

splint

a function to evaluate the definite integral of a B-spline between two given points

spalde

a function to evaluate all derivatives of a B-spline

Notes

The number of data points must be larger than the spline degree k .

NaN handling: If the input arrays contain nan values, the result is not useful, since the underlying spline fitting routines cannot deal with nan. A workaround is to use zero weights for not-a-number data points:

```
>>> from scipy.interpolate import UnivariateSpline
>>> x, y = np.array([1, 2, 3, 4]), np.array([1, np.nan, 3, 4])
>>> w = np.isnan(y)
>>> y[w] = 0.
>>> spl = UnivariateSpline(x, y, w=~w)
```

Notice the need to replace a nan by a numerical value (precise value does not matter as long as the corresponding weight is zero.)

Examples


```
>>> import matplotlib.pyplot as plt
>>> from scipy.interpolate import UnivariateSpline
>>> x = np.linspace(-3, 3, 50)
>>> y = np.exp(-x**2) + 0.1 * np.random.randn(50)
>>> plt.plot(x, y, 'ro', ms=5)
```

Use the default value for the smoothing parameter:

```
>>> spl = UnivariateSpline(x, y)
>>> xs = np.linspace(-3, 3, 1000)
>>> plt.plot(xs, spl(xs), 'g', lw=3)
```

Manually change the amount of smoothing:

```
>>> spl.set_smoothing_factor(0.5)
>>> plt.plot(xs, spl(xs), 'b', lw=3)
>>> plt.show()
```



Methods

<code>__call__(self, x[, nu, ext])</code>	Evaluate spline (or its nu-th derivative) at positions x.
<code>antiderivative(self[, n])</code>	Construct a new spline representing the antiderivative of this spline.
<code>derivative(self[, n])</code>	Construct a new spline representing the derivative of this spline.
<code>derivatives(self, x)</code>	Return all derivatives of the spline at the point x.
<code>get_coeffs(self)</code>	Return spline coefficients.
<code>get_knots(self)</code>	Return positions of interior knots of the spline.
<code>get_residual(self)</code>	Return weighted sum of squared residuals of the spline approximation.
<code>integral(self, a, b)</code>	Return definite integral of the spline between two given points.
<code>roots(self)</code>	Return the zeros of the spline.
<code>set_smoothing_factor(self, s)</code>	Continue spline computation with the given smoothing factor s and with the knots found at the last call.

scipy.interpolate.UnivariateSpline.__call__

UnivariateSpline.**__call__**(*self*, *x*, *nu=0*, *ext=None*)

Evaluate spline (or its *nu*-th derivative) at positions *x*.

Parameters

- x** [array_like] A 1-D array of points at which to return the value of the smoothed spline or its derivatives. Note: *x* can be unordered but the evaluation is more efficient if *x* is (partially) ordered.
- nu** [int] The order of derivative of the spline to compute.
- ext** [int] Controls the value returned for elements of *x* not in the interval defined by the knot sequence.
- if *ext*=0 or 'extrapolate', return the extrapolated value.
 - if *ext*=1 or 'zeros', return 0
 - if *ext*=2 or 'raise', raise a ValueError
 - if *ext*=3 or 'const', return the boundary value.
- The default value is 0, passed from the initialization of UnivariateSpline.

scipy.interpolate.UnivariateSpline.antiderivative

UnivariateSpline.**antiderivative**(*self*, *n=1*)

Construct a new spline representing the antiderivative of this spline.

Parameters

- n** [int, optional] Order of antiderivative to evaluate. Default: 1

Returns

- spline** [UnivariateSpline] Spline of order $k_2=k+n$ representing the antiderivative of this spline.

See also:

splantider, *derivative*

Notes

New in version 0.13.0.

Examples

```
>>> from scipy.interpolate import UnivariateSpline
>>> x = np.linspace(0, np.pi/2, 70)
>>> y = 1 / np.sqrt(1 - 0.8*np.sin(x)**2)
>>> spl = UnivariateSpline(x, y, s=0)
```

The derivative is the inverse operation of the antiderivative, although some floating point error accumulates:

```
>>> spl(1.7), spl.antiderivative().derivative()(1.7)
(array(2.1565429877197317), array(2.1565429877201865))
```

Antiderivative can be used to evaluate definite integrals:

```
>>> ispl = spl.antiderivative()
>>> ispl(np.pi/2) - ispl(0)
2.2572053588768486
```

This is indeed an approximation to the complete elliptic integral $K(m) = \int_0^{\pi/2} [1 - m \sin^2 x]^{-1/2} dx$:

```
>>> from scipy.special import ellipk
>>> ellipk(0.8)
2.2572053268208538
```

scipy.interpolate.UnivariateSpline.derivative

UnivariateSpline.**derivative** (*self*, *n=1*)

Construct a new spline representing the derivative of this spline.

Parameters

n [int, optional] Order of derivative to evaluate. Default: 1

Returns

spline [UnivariateSpline] Spline of order $k_2=k-n$ representing the derivative of this spline.

See also:

splder, *antiderivative*

Notes

New in version 0.13.0.

Examples

This can be used for finding maxima of a curve:

```
>>> from scipy.interpolate import UnivariateSpline
>>> x = np.linspace(0, 10, 70)
>>> y = np.sin(x)
>>> spl = UnivariateSpline(x, y, k=4, s=0)
```

Now, differentiate the spline and find the zeros of the derivative. (NB: *sproot* only works for order 3 splines, so we fit an order 4 spline):

```
>>> spl.derivative().roots() / np.pi
array([ 0.50000001,  1.5          ,  2.49999998])
```

This agrees well with roots $\pi/2 + n\pi$ of $\cos(x) = \sin'(x)$.

scipy.interpolate.UnivariateSpline.derivatives

UnivariateSpline.**derivatives** (*self*, *x*)

Return all derivatives of the spline at the point *x*.

Parameters

x [float] The point to evaluate the derivatives at.

Returns

der [ndarray, shape(k+1,)] Derivatives of the orders 0 to *k*.

Examples

```
>>> from scipy.interpolate import UnivariateSpline
>>> x = np.linspace(0, 3, 11)
>>> y = x**2
>>> spl = UnivariateSpline(x, y)
>>> spl.derivatives(1.5)
array([2.25, 3.0, 2.0, 0])
```

scipy.interpolate.UnivariateSpline.get_coeffs

`UnivariateSpline.get_coeffs` (*self*)
Return spline coefficients.

scipy.interpolate.UnivariateSpline.get_knots

`UnivariateSpline.get_knots` (*self*)
Return positions of interior knots of the spline.
Internally, the knot vector contains $2*k$ additional boundary knots.

scipy.interpolate.UnivariateSpline.get_residual

`UnivariateSpline.get_residual` (*self*)
Return weighted sum of squared residuals of the spline approximation.

This is equivalent to:

```
sum((w[i] * (y[i]-spl(x[i])))**2, axis=0)
```

scipy.interpolate.UnivariateSpline.integral

`UnivariateSpline.integral` (*self*, *a*, *b*)
Return definite integral of the spline between two given points.

Parameters

a [float] Lower limit of integration.
b [float] Upper limit of integration.

Returns

integral [float] The value of the definite integral of the spline between limits.

Examples

```
>>> from scipy.interpolate import UnivariateSpline
>>> x = np.linspace(0, 3, 11)
>>> y = x**2
>>> spl = UnivariateSpline(x, y)
>>> spl.integral(0, 3)
9.0
```

which agrees with $\int x^2 dx = x^3/3$ between the limits of 0 and 3.

A caveat is that this routine assumes the spline to be zero outside of the data limits:

```
>>> spl.integral(-1, 4)
9.0
>>> spl.integral(-1, 0)
0.0
```

scipy.interpolate.UnivariateSpline.roots

`UnivariateSpline.roots` (*self*)
Return the zeros of the spline.

Restriction: only cubic splines are supported by fitpack.

scipy.interpolate.UnivariateSpline.set_smoothing_factor

`UnivariateSpline.set_smoothing_factor` (*self*, *s*)

Continue spline computation with the given smoothing factor *s* and with the knots found at the last call.

This routine modifies the spline in place.

validate_input

scipy.interpolate.InterpolatedUnivariateSpline

class `scipy.interpolate.InterpolatedUnivariateSpline` (*x*, *y*, *w=None*, *bbox=[None, None]*, *k=3*, *ext=0*, *check_finite=False*)

1-D interpolating spline for a given set of data points.

Fits a spline $y = spl(x)$ of degree *k* to the provided *x*, *y* data. Spline function passes through all provided points. Equivalent to `UnivariateSpline` with *s=0*.

Parameters

- x** [(N,) array_like] Input dimension of data points – must be strictly increasing
- y** [(N,) array_like] input dimension of data points
- w** [(N,) array_like, optional] Weights for spline fitting. Must be positive. If None (default), weights are all equal.
- bbox** [(2,) array_like, optional] 2-sequence specifying the boundary of the approximation interval. If None (default), `bbox=x[x[0], x[-1]]`.
- k** [int, optional] Degree of the smoothing spline. Must be $1 \leq k \leq 5$.
- ext** [int or str, optional] Controls the extrapolation mode for elements not in the interval defined by the knot sequence.
 - if `ext=0` or 'extrapolate', return the extrapolated value.
 - if `ext=1` or 'zeros', return 0
 - if `ext=2` or 'raise', raise a `ValueError`
 - if `ext=3` or 'const', return the boundary value.
 The default value is 0.
- check_finite** [bool, optional] Whether to check that the input arrays contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination or non-sensical results) if the inputs do contain infinities or NaNs. Default is False.

See also:

[`UnivariateSpline`](#)

a smooth univariate spline to fit a given set of data points.

LSQUnivariateSpline

a spline for which knots are user-selected

SmoothBivariateSpline

a smoothing bivariate spline through the given points

LSQBivariateSpline

a bivariate spline using weighted least-squares fitting

splrep

a function to find the B-spline representation of a 1-D curve

splev

a function to evaluate a B-spline or its derivatives

sproot

a function to find the roots of a cubic B-spline

splint

a function to evaluate the definite integral of a B-spline between two given points

spalde

a function to evaluate all derivatives of a B-spline

Notes


The number of data points must be larger than the spline degree k .

Examples

```
>>> import matplotlib.pyplot as plt
>>> from scipy.interpolate import InterpolatedUnivariateSpline
>>> x = np.linspace(-3, 3, 50)
>>> y = np.exp(-x**2) + 0.1 * np.random.randn(50)
>>> spl = InterpolatedUnivariateSpline(x, y)
>>> plt.plot(x, y, 'ro', ms=5)
>>> xs = np.linspace(-3, 3, 1000)
>>> plt.plot(xs, spl(xs), 'g', lw=3, alpha=0.7)
>>> plt.show()
```

Notice that the `spl(x)` interpolates `y`:

```
>>> spl.get_residual()
0.0
```



Methods

<code>__call__(self, x[, nu, ext])</code>	Evaluate spline (or its nu-th derivative) at positions x.
<code>antiderivative(self[, n])</code>	Construct a new spline representing the antiderivative of this spline.
<code>derivative(self[, n])</code>	Construct a new spline representing the derivative of this spline.
<code>derivatives(self, x)</code>	Return all derivatives of the spline at the point x.
<code>get_coeffs(self)</code>	Return spline coefficients.
<code>get_knots(self)</code>	Return positions of interior knots of the spline.
<code>get_residual(self)</code>	Return weighted sum of squared residuals of the spline approximation.
<code>integral(self, a, b)</code>	Return definite integral of the spline between two given points.
<code>roots(self)</code>	Return the zeros of the spline.
<code>set_smoothing_factor(self, s)</code>	Continue spline computation with the given smoothing factor s and with the knots found at the last call.

scipy.interpolate.InterpolatedUnivariateSpline.__call__

`InterpolatedUnivariateSpline.__call__(self, x, nu=0, ext=None)`

Evaluate spline (or its nu-th derivative) at positions x.

Parameters

x	[array_like] A 1-D array of points at which to return the value of the smoothed spline or its derivatives. Note: x can be unordered but the evaluation is more efficient if x is (partially) ordered.
nu	[int] The order of derivative of the spline to compute.
ext	[int] Controls the value returned for elements of x not in the interval defined by the knot sequence. <ul style="list-style-type: none"> • if ext=0 or 'extrapolate', return the extrapolated value. • if ext=1 or 'zeros', return 0 • if ext=2 or 'raise', raise a ValueError • if ext=3 or 'const', return the boundary value. The default value is 0, passed from the initialization of UnivariateSpline.

`InterpolatedUnivariateSpline.antiderivative(self, n=1)`

Construct a new spline representing the antiderivative of this spline.

Notes

New in version 0.13.0.

Examples

```
>>> from scipy.interpolate import UnivariateSpline
>>> x = np.linspace(0, np.pi/2, 70)
>>> y = 1 / np.sqrt(1 - 0.8*np.sin(x)**2)
>>> spl = UnivariateSpline(x, y, s=0)
```

The derivative is the inverse operation of the antiderivative, although some floating point error accumulates:

```
>>> spl(1.7), spl.antiderivative().derivative()(1.7)
(array(2.1565429877197317), array(2.1565429877201865))
```

Antiderivative can be used to evaluate definite integrals:

```
>>> ispl = spl.antiderivative()
>>> ispl(np.pi/2) - ispl(0)
2.2572053588768486
```

This is indeed an approximation to the complete elliptic integral $K(m) = \int_0^{\pi/2} [1 - m \sin^2 x]^{-1/2} dx$:

```
>>> from scipy.special import ellipk
>>> ellipk(0.8)
2.2572053268208538
```

scipy.interpolate.InterpolatedUnivariateSpline.derivative

InterpolatedUnivariateSpline.**derivative** (*self*, *n=1*)

Construct a new spline representing the derivative of this spline.

Parameters

n [int, optional] Order of derivative to evaluate. Default: 1

Returns

spline [UnivariateSpline] Spline of order $k_2=k-n$ representing the derivative of this spline.

See also:

splder, *antiderivative*

Notes

New in version 0.13.0.

Examples

This can be used for finding maxima of a curve:

```
>>> from scipy.interpolate import UnivariateSpline
>>> x = np.linspace(0, 10, 70)
>>> y = np.sin(x)
>>> spl = UnivariateSpline(x, y, k=4, s=0)
```

Now, differentiate the spline and find the zeros of the derivative. (NB: `sroot` only works for order 3 splines, so we fit an order 4 spline):

```
>>> spl.derivative().roots() / np.pi
array([ 0.50000001,  1.5          ,  2.49999998])
```

This agrees well with roots $\pi/2 + n\pi$ of $\cos(x) = \sin'(x)$.

scipy.interpolate.InterpolatedUnivariateSpline.derivatives

`InterpolatedUnivariateSpline.derivatives` (*self*, *x*)

Return all derivatives of the spline at the point *x*.

Parameters

x [float] The point to evaluate the derivatives at.

Returns

der [ndarray, shape(k+1,)] Derivatives of the orders 0 to *k*.

Examples

```
>>> from scipy.interpolate import UnivariateSpline
>>> x = np.linspace(0, 3, 11)
>>> y = x**2
>>> spl = UnivariateSpline(x, y)
>>> spl.derivatives(1.5)
array([2.25, 3.0, 2.0, 0])
```

scipy.interpolate.InterpolatedUnivariateSpline.get_coeffs

`InterpolatedUnivariateSpline.get_coeffs` (*self*)

Return spline coefficients.

scipy.interpolate.InterpolatedUnivariateSpline.get_knots

`InterpolatedUnivariateSpline.get_knots` (*self*)

Return positions of interior knots of the spline.

Internally, the knot vector contains $2*k$ additional boundary knots.

scipy.interpolate.InterpolatedUnivariateSpline.get_residual

`InterpolatedUnivariateSpline.get_residual` (*self*)
Return weighted sum of squared residuals of the spline approximation.

This is equivalent to:

```
sum((w[i] * (y[i]-spl(x[i])))**2, axis=0)
```

scipy.interpolate.InterpolatedUnivariateSpline.integral

`InterpolatedUnivariateSpline.integral` (*self*, *a*, *b*)
Return definite integral of the spline between two given points.

Parameters

a [float] Lower limit of integration.
b [float] Upper limit of integration.

Returns

integral [float] The value of the definite integral of the spline between limits.

Examples

```
>>> from scipy.interpolate import UnivariateSpline
>>> x = np.linspace(0, 3, 11)
>>> y = x**2
>>> spl = UnivariateSpline(x, y)
>>> spl.integral(0, 3)
9.0
```

which agrees with $\int x^2 dx = x^3/3$ between the limits of 0 and 3.

A caveat is that this routine assumes the spline to be zero outside of the data limits:

```
>>> spl.integral(-1, 4)
9.0
>>> spl.integral(-1, 0)
0.0
```

scipy.interpolate.InterpolatedUnivariateSpline.roots

`InterpolatedUnivariateSpline.roots` (*self*)
Return the zeros of the spline.

Restriction: only cubic splines are supported by fitpack.

scipy.interpolate.InterpolatedUnivariateSpline.set_smoothing_factor

`InterpolatedUnivariateSpline.set_smoothing_factor` (*self*, *s*)

Continue spline computation with the given smoothing factor *s* and with the knots found at the last call.

This routine modifies the spline in place.

validate_input

scipy.interpolate.LSQUnivariateSpline

class `scipy.interpolate.LSQUnivariateSpline` (*x*, *y*, *t*, *w=None*, *bbox=[None, None]*, *k=3*, *ext=0*, *check_finite=False*)

1-D spline with explicit internal knots.

Fits a spline $y = \text{spl}(x)$ of degree *k* to the provided *x*, *y* data. *t* specifies the internal knots of the spline

Parameters

x [(N,) array_like] Input dimension of data points – must be increasing
y [(N,) array_like] Input dimension of data points
t [(M,) array_like] interior knots of the spline. Must be in ascending order and:

$\text{bbox}[0] < t[0] < \dots < t[-1] < \text{bbox}[-1]$

w [(N,) array_like, optional] weights for spline fitting. Must be positive. If None (default), weights are all equal.

bbox [(2,) array_like, optional] 2-sequence specifying the boundary of the approximation interval. If None (default), `bbox = [x[0], x[-1]]`.

k [int, optional] Degree of the smoothing spline. Must be $1 \leq k \leq 5$. Default is $k = 3$, a cubic spline.

ext [int or str, optional] Controls the extrapolation mode for elements not in the interval defined by the knot sequence.

- if `ext=0` or 'extrapolate', return the extrapolated value.
- if `ext=1` or 'zeros', return 0
- if `ext=2` or 'raise', raise a `ValueError`
- if `ext=3` or 'const', return the boundary value.

The default value is 0.

check_finite

[bool, optional] Whether to check that the input arrays contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination or non-sensical results) if the inputs do contain infinities or NaNs. Default is `False`.

Raises

ValueError

If the interior knots do not satisfy the Schoenberg-Whitney conditions

See also:

[UnivariateSpline](#)

a smooth univariate spline to fit a given set of data points.

[InterpolatedUnivariateSpline](#)

a interpolating univariate spline for a given set of data points.

splrep

a function to find the B-spline representation of a 1-D curve

splev

a function to evaluate a B-spline or its derivatives

sprout

a function to find the roots of a cubic B-spline

splint

a function to evaluate the definite integral of a B-spline between two given points

spalde

a function to evaluate all derivatives of a B-spline

Notes

The number of data points must be larger than the spline degree k .

Knots t must satisfy the Schoenberg-Whitney conditions, i.e., there must be a subset of data points $x[j]$ such that $t[j] < x[j] < t[j+k+1]$, for $j=0, 1, \dots, n-k-2$.

Examples

```
>>> from scipy.interpolate import LSQUnivariateSpline, UnivariateSpline
>>> import matplotlib.pyplot as plt
>>> x = np.linspace(-3, 3, 50)
>>> y = np.exp(-x**2) + 0.1 * np.random.randn(50)
```

Fit a smoothing spline with a pre-defined internal knots:

```
>>> t = [-1, 0, 1]
>>> spl = LSQUnivariateSpline(x, y, t)
```

```
>>> xs = np.linspace(-3, 3, 1000)
>>> plt.plot(x, y, 'ro', ms=5)
>>> plt.plot(xs, spl(xs), 'g-', lw=3)
>>> plt.show()
```


Check the knot vector:

```
>>> spl.get_knots()
array([-3., -1., 0., 1., 3.])
```

Constructing lsq spline using the knots from another spline:

```
>>> x = np.arange(10)
>>> s = UnivariateSpline(x, x, s=0)
>>> s.get_knots()
array([ 0., 2., 3., 4., 5., 6., 7., 9.])
>>> knt = s.get_knots()
>>> s1 = LSQUnivariateSpline(x, x, knt[1:-1]) # Chop 1st and last knot
```

(continues on next page)



(continued from previous page)

```
>>> s1.get_knots()
array([ 0.,  2.,  3.,  4.,  5.,  6.,  7.,  9.])
```

Methods

<code>__call__(self, x[, nu, ext])</code>	Evaluate spline (or its nu-th derivative) at positions x.
<code>antiderivative(self[, n])</code>	Construct a new spline representing the antiderivative of this spline.
<code>derivative(self[, n])</code>	Construct a new spline representing the derivative of this spline.
<code>derivatives(self, x)</code>	Return all derivatives of the spline at the point x.
<code>get_coeffs(self)</code>	Return spline coefficients.
<code>get_knots(self)</code>	Return positions of interior knots of the spline.
<code>get_residual(self)</code>	Return weighted sum of squared residuals of the spline approximation.
<code>integral(self, a, b)</code>	Return definite integral of the spline between two given points.
<code>roots(self)</code>	Return the zeros of the spline.
<code>set_smoothing_factor(self, s)</code>	Continue spline computation with the given smoothing factor s and with the knots found at the last call.

scipy.interpolate.LSQUnivariateSpline.__call__

`LSQUnivariateSpline.__call__(self, x, nu=0, ext=None)`

Evaluate spline (or its nu-th derivative) at positions x.

Parameters

- x** [array_like] A 1-D array of points at which to return the value of the smoothed spline or its derivatives. Note: x can be unordered but the evaluation is more efficient if x is (partially) ordered.
- nu** [int] The order of derivative of the spline to compute.
- ext** [int] Controls the value returned for elements of x not in the interval defined by the knot sequence.

• if ext=0 or 'extrapolate', return the extrapolated value
 • if ext=1 or 'zeros', return 0
 • if ext=2 or 'raise', raise a ValueError
 • if ext=3 or 'const', return the boundary value.
 The default value is 0, passed from the initialization of UnivariateSpline

splantider, derivative

Notes

New in version 0.13.0.

Examples

```
>>> from scipy.interpolate import UnivariateSpline
>>> x = np.linspace(0, np.pi/2, 70)
>>> y = 1 / np.sqrt(1 - 0.8*np.sin(x)**2)
>>> spl = UnivariateSpline(x, y, s=0)
```

The derivative is the inverse operation of the antiderivative, although some floating point error accumulates:

```
>>> spl(1.7), spl.antiderivative().derivative()(1.7)
(array(2.1565429877197317), array(2.1565429877201865))
```

Antiderivative can be used to evaluate definite integrals:

```
>>> ispl = spl.antiderivative()
>>> ispl(np.pi/2) - ispl(0)
2.2572053588768486
```

This is indeed an approximation to the complete elliptic integral $K(m) = \int_0^{\pi/2} [1 - m \sin^2 x]^{-1/2} dx$:

```
>>> from scipy.special import ellipk
>>> ellipk(0.8)
2.2572053268208538
```

scipy.interpolate.LSQUnivariateSpline.derivative

`LSQUnivariateSpline.derivative` (*self*, *n=1*)

Construct a new spline representing the derivative of this spline.

Parameters

n [int, optional] Order of derivative to evaluate. Default: 1

Returns

spline [UnivariateSpline] Spline of order $k_2=k-n$ representing the derivative of this spline.

See also:

splder, antiderivative

Notes

New in version 0.13.0.

Examples

This can be used for finding maxima of a curve:

```
>>> from scipy.interpolate import UnivariateSpline
>>> x = np.linspace(0, 10, 70)
>>> y = np.sin(x)
>>> spl = UnivariateSpline(x, y, k=4, s=0)
```

Now, differentiate the spline and find the zeros of the derivative. (NB: *sproot* only works for order 3 splines, so we fit an order 4 spline):

```
>>> spl.derivative().roots() / np.pi
array([ 0.50000001,  1.5          ,  2.49999998])
```

This agrees well with roots $\pi/2 + n\pi$ of $\cos(x) = \sin'(x)$.

scipy.interpolate.LSQUnivariateSpline.derivatives

`LSQUnivariateSpline.derivatives` (*self*, *x*)

Return all derivatives of the spline at the point *x*.

Parameters

x [float] The point to evaluate the derivatives at.

Returns

der [ndarray, shape(k+1,)] Derivatives of the orders 0 to k.

Examples

```
>>> from scipy.interpolate import UnivariateSpline
>>> x = np.linspace(0, 3, 11)
>>> y = x**2
>>> spl = UnivariateSpline(x, y)
>>> spl.derivatives(1.5)
array([2.25, 3.0, 2.0, 0])
```

scipy.interpolate.LSQUnivariateSpline.get_coeffs

`LSQUnivariateSpline.get_coeffs` (*self*)

Return spline coefficients.

scipy.interpolate.LSQUnivariateSpline.get_knots

LSQUnivariateSpline.**get_knots** (*self*)

Return positions of interior knots of the spline.

Internally, the knot vector contains $2*k$ additional boundary knots.

scipy.interpolate.LSQUnivariateSpline.get_residual

LSQUnivariateSpline.**get_residual** (*self*)

Return weighted sum of squared residuals of the spline approximation.

This is equivalent to:

```
sum((w[i] * (y[i]-spl(x[i])))**2, axis=0)
```

scipy.interpolate.LSQUnivariateSpline.integral

LSQUnivariateSpline.**integral** (*self*, *a*, *b*)

Return definite integral of the spline between two given points.

Parameters

a [float] Lower limit of integration.
b [float] Upper limit of integration.

Returns

integral [float] The value of the definite integral of the spline between limits.

Examples

```
>>> from scipy.interpolate import UnivariateSpline
>>> x = np.linspace(0, 3, 11)
>>> y = x**2
>>> spl = UnivariateSpline(x, y)
>>> spl.integral(0, 3)
9.0
```

which agrees with $\int x^2 dx = x^3/3$ between the limits of 0 and 3.

A caveat is that this routine assumes the spline to be zero outside of the data limits:

```
>>> spl.integral(-1, 4)
9.0
>>> spl.integral(-1, 0)
0.0
```

scipy.interpolate.LSQUnivariateSpline.roots

LSQUnivariateSpline.**roots** (*self*)

Return the zeros of the spline.

Restriction: only cubic splines are supported by fitpack.

scipy.interpolate.LSQUnivariateSpline.set_smoothing_factor

LSQUnivariateSpline.**set_smoothing_factor** (*self*, *s*)

Continue spline computation with the given smoothing factor *s* and with the knots found at the last call.

This routine modifies the spline in place.

validate_input

6.8.4 2-D Splines

For data on a grid:

<code>RectBivariateSpline(x, y, z[, bbox, kx, ky, s])</code>	Bivariate spline approximation over a rectangular mesh.
<code>RectSphereBivariateSpline(u, v, r[, s, ...])</code>	Bivariate spline approximation over a rectangular mesh on a sphere.

scipy.interpolate.RectSphereBivariateSpline

class scipy.interpolate.**RectSphereBivariateSpline** (*u*, *v*, *r*, *s=0.0*, *pole_continuity=False*,
pole_values=None,
pole_exact=False, *pole_flat=False*)

Bivariate spline approximation over a rectangular mesh on a sphere.

Can be used for smoothing data.

New in version 0.11.0.

Parameters

- u** [array_like] 1-D array of colatitude coordinates in strictly ascending order. Coordinates must be given in radians and lie within the interval $[0, \pi]$.
- v** [array_like] 1-D array of longitude coordinates in strictly ascending order. Coordinates must be given in radians. First element ($v[0]$) must lie within the interval $[-\pi, \pi]$. Last element ($v[-1]$) must satisfy $v[-1] \leq v[0] + 2\pi$.
- r** [array_like] 2-D array of data with shape $(u.size, v.size)$.
- s** [float, optional] Positive smoothing factor defined for estimation condition ($s=0$ is for interpolation).
- pole_continuity** [bool or (bool, bool), optional] Order of continuity at the poles $u=0$ (`pole_continuity[0]`) and $u=\pi$ (`pole_continuity[1]`). The order of continuity at the pole will be 1 or 0 when this is True or False, respectively. Defaults to False.
- pole_values** [float or (float, float), optional] Data values at the poles $u=0$ and $u=\pi$. Either the whole parameter or each individual element can be None. Defaults to None.
- pole_exact** [bool or (bool, bool), optional] Data value exactness at the poles $u=0$ and $u=\pi$. If True, the value is considered to be the right function value, and it will be fitted exactly. If False,

the value will be considered to be a data value just like the other data values. Defaults to False.

pole_flat [bool or (bool, bool), optional] For the poles at $u=0$ and $u=\pi$, specify whether or not the approximation has vanishing derivatives. Defaults to False.

See also:*BivariateSpline*

a base class for bivariate splines.

UnivariateSpline

a smooth univariate spline to fit a given set of data points.

SmoothBivariateSpline

a smoothing bivariate spline through the given points

LSQBivariateSpline

a bivariate spline using weighted least-squares fitting

SmoothSphereBivariateSpline

a smoothing bivariate spline in spherical coordinates

LSQSphereBivariateSpline

a bivariate spline in spherical coordinates using weighted least-squares fitting

RectBivariateSpline

a bivariate spline over a rectangular mesh.

bisplrep

a function to find a bivariate B-spline representation of a surface

bisplev

a function to evaluate a bivariate B-spline and its derivatives

Notes

Currently, only the smoothing spline approximation ($i_{\text{opt}}[0] = 0$ and $i_{\text{opt}}[0] = 1$ in the FITPACK routine) is supported. The exact least-squares spline approximation is not implemented yet.

When actually performing the interpolation, the requested v values must lie within the same length 2π interval that the original v values were chosen from.

For more information, see the [FITPACK](#) site about this function.

Examples

Suppose we have global data on a coarse grid

```
>>> lats = np.linspace(10, 170, 9) * np.pi / 180.
>>> lons = np.linspace(0, 350, 18) * np.pi / 180.
>>> data = np.dot(np.atleast_2d(90. - np.linspace(-80., 80., 18)).T,
...               np.atleast_2d(180. - np.abs(np.linspace(0., 350., 9)))).
↳T
```

We want to interpolate it to a global one-degree grid

```
>>> new_lats = np.linspace(1, 180, 180) * np.pi / 180
>>> new_lons = np.linspace(1, 360, 360) * np.pi / 180
>>> new_lats, new_lons = np.meshgrid(new_lats, new_lons)
```

We need to set up the interpolator object

```
>>> from scipy.interpolate import RectSphereBivariateSpline
>>> lut = RectSphereBivariateSpline(lats, lons, data)
```

Finally we interpolate the data. The *RectSphereBivariateSpline* object only takes 1-D arrays as input, therefore we need to do some reshaping.

```
>>> data_interp = lut.ev(new_lats.ravel(),
...                      new_lons.ravel()).reshape((360, 180)).T
```

Looking at the original and the interpolated data, one can see that the interpolant reproduces the original data very well:

```
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> ax1 = fig.add_subplot(211)
>>> ax1.imshow(data, interpolation='nearest')
>>> ax2 = fig.add_subplot(212)
>>> ax2.imshow(data_interp, interpolation='nearest')
>>> plt.show()
```


Choosing the optimal value of s can be a delicate task. Recommended values for s depend on the accuracy of the data values. If the user has an idea of the statistical errors on the data, she can also find a proper estimate for s . By assuming that, if she specifies the right s , the interpolator will use a spline $f(u, v)$ which exactly reproduces the function underlying the data, she can evaluate $\sum (r(i, j) - s(u(i), v(j)))^2$ to find a good estimate for this s . For example, if she knows that the statistical errors on her $r(i, j)$ -values are not greater than 0.1, she may expect that a good s should have a value not larger than $u.size * v.size * (0.1)^2$.

If nothing is known about the statistical error in $r(i, j)$, s must be determined by trial and error. The best is then to start with a very large value of s (to determine the least-squares polynomial and the corresponding upper bound $fp0$ for s) and then to progressively decrease the value of s (say by a factor 10 in the beginning, i.e. $s = fp0 / 10, fp0 / 100, \dots$ and more carefully as the approximation shows more detail) to obtain closer fits.

The interpolation results for different values of s give some insight into this process:

```
>>> fig2 = plt.figure()
>>> s = [3e9, 2e9, 1e9, 1e8]
```

(continues on next page)




(continued from previous page)

```

>>> for ii in range(len(s)):
...     lut = RectSphereBivariateSpline(lats, lons, data, s=s[ii])
...     data_interp = lut.ev(new_lats.ravel(),
...                           new_lons.ravel()).reshape((360, 180)).T
...     ax = fig2.add_subplot(2, 2, ii+1)
...     ax.imshow(data_interp, interpolation='nearest')
...     ax.set_title("s = %g" % s[ii])
>>> plt.show()

```



Methods

<code>__call__(self, theta, phi[, dtheta, dphi, grid])</code>	Evaluate the spline or its derivatives at given positions.
<code>ev(self, theta, phi[, dtheta, dphi])</code>	Evaluate the spline at points
<code>get_coeffs(self)</code>	Return spline coefficients.
<code>get_knots(self)</code>	Return a tuple (tx,ty) where tx,ty contain knots positions of the spline with respect to x-, y-variable, respectively.
<code>get_residual(self)</code>	Return weighted sum of squared residuals of the spline approximation: $\sum ((w[i]*(z[i]-s(x[i],y[i])))^2, axis=0)$

scipy.interpolate.RectSphereBivariateSpline.__call__

`RectSphereBivariateSpline.__call__(self, theta, phi, dtheta=0, dphi=0, grid=True)`

Evaluate the spline or its derivatives at given positions.

Parameters

- theta, phi** [array_like] Input coordinates.
If *grid* is False, evaluate the spline at points $(\text{theta}[i], \text{phi}[i])$, $i=0, \dots, \text{len}(x)-1$. Standard Numpy broadcasting is obeyed.
If *grid* is True: evaluate spline at the grid points defined by the coordinate arrays theta, phi. The arrays must be sorted to increasing order.
- dtheta** [int, optional] Order of theta-derivative
New in version 0.14.0.
- dphi** [int] Order of phi-derivative
New in version 0.14.0.
- grid** [bool] Whether to evaluate the results on a grid spanned by the input arrays, or at points specified by the input arrays.
New in version 0.14.0.

scipy.interpolate.RectSphereBivariateSpline.ev

`RectSphereBivariateSpline.ev(self, theta, phi, dtheta=0, dphi=0)`

Evaluate the spline at points

Returns the interpolated value at $(\text{theta}[i], \text{phi}[i])$, $i=0, \dots, \text{len}(\text{theta})-1$.

Parameters

- theta, phi** [array_like] Input coordinates. Standard Numpy broadcasting is obeyed.
- dtheta** [int, optional] Order of theta-derivative
New in version 0.14.0.
- dphi** [int, optional] Order of phi-derivative
New in version 0.14.0.

scipy.interpolate.RectSphereBivariateSpline.get_coeffs

`RectSphereBivariateSpline.get_coeffs` (*self*)
Return spline coefficients.

scipy.interpolate.RectSphereBivariateSpline.get_knots

`RectSphereBivariateSpline.get_knots` (*self*)
Return a tuple (tx,ty) where tx,ty contain knots positions of the spline with respect to x-, y-variable, respectively. The position of interior and additional knots are given as $t[k+1:-k-1]$ and $t[:k+1]=b$, $t[-k-1:]=e$, respectively.

scipy.interpolate.RectSphereBivariateSpline.get_residual

`RectSphereBivariateSpline.get_residual` (*self*)
Return weighted sum of squared residuals of the spline approximation: $\sum ((w[i]*(z[i]-s(x[i],y[i])))**2,axis=0)$

For unstructured data:

<code>BivariateSpline()</code>	Base class for bivariate splines.
<code>SmoothBivariateSpline(x, y, z[, w, bbox, ...])</code>	Smooth bivariate spline approximation.
<code>SmoothSphereBivariateSpline(theta, phi, r[, ...])</code>	Smooth bivariate spline approximation in spherical coordinates.
<code>LSQBivariateSpline(x, y, z, tx, ty[, w, ...])</code>	Weighted least-squares bivariate spline approximation.
<code>LSQSphereBivariateSpline(theta, phi, r, tt)</code>	Weighted least-squares bivariate spline approximation in spherical coordinates.

scipy.interpolate.BivariateSpline**class** `scipy.interpolate.BivariateSpline`

Base class for bivariate splines.

This describes a spline $s(x, y)$ of degrees k_x and k_y on the rectangle $[x_b, x_e] * [y_b, y_e]$ calculated from a given set of data points (x, y, z) .

This class is meant to be subclassed, not instantiated directly. To construct these splines, call either `SmoothBivariateSpline` or `LSQBivariateSpline` or `RectBivariateSpline`.

See also:

`UnivariateSpline`

a smooth univariate spline to fit a given set of data points.

`SmoothBivariateSpline`

a smoothing bivariate spline through the given points

`LSQBivariateSpline`

a bivariate spline using weighted least-squares fitting

`RectSphereBivariateSpline`

a bivariate spline over a rectangular mesh on a sphere

`SmoothSphereBivariateSpline`

a smoothing bivariate spline in spherical coordinates

LSQSphereBivariateSpline

a bivariate spline in spherical coordinates using weighted least-squares fitting

RectBivariateSpline

a bivariate spline over a rectangular mesh.

bisplrep

a function to find a bivariate B-spline representation of a surface

bisplev

a function to evaluate a bivariate B-spline and its derivatives

Methods

<code>__call__(self, x, y[, dx, dy, grid])</code>	Evaluate the spline or its derivatives at given positions.
<code>ev(self, xi, yi[, dx, dy])</code>	Evaluate the spline at points
<code>get_coeffs(self)</code>	Return spline coefficients.
<code>get_knots(self)</code>	Return a tuple (tx,ty) where tx,ty contain knots positions of the spline with respect to x-, y-variable, respectively.
<code>get_residual(self)</code>	Return weighted sum of squared residuals of the spline approximation: $\sum ((w[i]*(z[i]-s(x[i],y[i])))^2, axis=0)$
<code>integral(self, xa, xb, ya, yb)</code>	Evaluate the integral of the spline over area [xa,xb] x [ya,yb].

scipy.interpolate.BivariateSpline.__call__

`BivariateSpline.__call__(self, x, y, dx=0, dy=0, grid=True)`

Evaluate the spline or its derivatives at given positions.

Parameters

- x, y** [array_like] Input coordinates.
If *grid* is False, evaluate the spline at points $(x[i], y[i]), i=0, \dots, \text{len}(x)-1$. Standard Numpy broadcasting is obeyed.
If *grid* is True: evaluate spline at the grid points defined by the coordinate arrays x, y. The arrays must be sorted to increasing order.
Note that the axis ordering is inverted relative to the output of meshgrid.
- dx** [int] Order of x-derivative
New in version 0.14.0.
- dy** [int] Order of y-derivative
New in version 0.14.0.
- grid** [bool] Whether to evaluate the results on a grid spanned by the input arrays, or at points specified by the input arrays.
New in version 0.14.0.

scipy.interpolate.BivariateSpline.ev

`BivariateSpline.ev` (*self*, *xi*, *yi*, *dx=0*, *dy=0*)

Evaluate the spline at points

Returns the interpolated value at $(xi[i], yi[i]), i=0, \dots, len(xi)-1$.

Parameters

xi, yi [array_like] Input coordinates. Standard Numpy broadcasting is obeyed.
dx [int, optional] Order of x-derivative
 New in version 0.14.0.
dy [int, optional] Order of y-derivative
 New in version 0.14.0.

scipy.interpolate.BivariateSpline.get_coeffs

`BivariateSpline.get_coeffs` (*self*)

Return spline coefficients.

scipy.interpolate.BivariateSpline.get_knots

`BivariateSpline.get_knots` (*self*)

Return a tuple (tx,ty) where tx,ty contain knots positions of the spline with respect to x-, y-variable, respectively. The position of interior and additional knots are given as $t[k+1:-k-1]$ and $t[:k+1]=b, t[-k-1:]=e$, respectively.

scipy.interpolate.BivariateSpline.get_residual

`BivariateSpline.get_residual` (*self*)

Return weighted sum of squared residuals of the spline approximation: $\sum ((w[i]*(z[i]-s(x[i],y[i])))**2,axis=0)$

scipy.interpolate.BivariateSpline.integral

`BivariateSpline.integral` (*self*, *xa*, *xb*, *ya*, *yb*)

Evaluate the integral of the spline over area $[xa,xb] \times [ya,yb]$.

Parameters

xa, xb [float] The end-points of the x integration interval.
ya, yb [float] The end-points of the y integration interval.

Returns

integ [float] The value of the resulting integral.

scipy.interpolate.SmoothBivariateSpline

class `scipy.interpolate.SmoothBivariateSpline` (*x*, *y*, *z*, *w=None*, *bbox=[None, None, None, None]*, *kx=3*, *ky=3*, *s=None*, *eps=1e-16*)

Smooth bivariate spline approximation.

Parameters

x, y, z [array_like] 1-D sequences of data points (order is not important).
w [array_like, optional] Positive 1-D sequence of weights, of same length as *x*, *y* and *z*.
bbox [array_like, optional] Sequence of length 4 specifying the boundary of the rectangular approximation domain. By default, `bbox=[min(x), max(x), min(y), max(y)]`.
kx, ky [ints, optional] Degrees of the bivariate spline. Default is 3.

- s** [float, optional] Positive smoothing factor defined for estimation condition: $\text{sum}((w[i] * (z[i] - s(x[i], y[i]))) ** 2, \text{axis}=0) \leq s$ Default $s = \text{len}(w)$ which should be a good value if $1/w[i]$ is an estimate of the standard deviation of $z[i]$.
- eps** [float, optional] A threshold for determining the effective rank of an over-determined linear system of equations. *eps* should have a value within the open interval $(0, 1)$, the default is $1e-16$.

See also:

BivariateSpline

a base class for bivariate splines.

UnivariateSpline

a smooth univariate spline to fit a given set of data points.

LSQBivariateSpline

a bivariate spline using weighted least-squares fitting

RectSphereBivariateSpline

a bivariate spline over a rectangular mesh on a sphere

SmoothSphereBivariateSpline

a smoothing bivariate spline in spherical coordinates

LSQSphereBivariateSpline

a bivariate spline in spherical coordinates using weighted least-squares fitting

RectBivariateSpline

a bivariate spline over a rectangular mesh

bisplrep

a function to find a bivariate B-spline representation of a surface

bisplev

a function to evaluate a bivariate B-spline and its derivatives

Notes

The length of *x*, *y* and *z* should be at least $(k_x+1) * (k_y+1)$.

Methods

<code>__call__(self, x, y[, dx, dy, grid])</code>	Evaluate the spline or its derivatives at given positions.
<code>ev(self, xi, yi[, dx, dy])</code>	Evaluate the spline at points
<code>get_coeffs(self)</code>	Return spline coefficients.
<code>get_knots(self)</code>	Return a tuple (tx,ty) where tx,ty contain knots positions of the spline with respect to x-, y-variable, respectively.

continues on next page

Table 72 – continued from previous page

<code>get_residual(self)</code>	Return weighted sum of squared residuals of the spline approximation: $\text{sum}((w[i]*(z[i]-s(x[i],y[i])))**2,axis=0)$
<code>integral(self, xa, xb, ya, yb)</code>	Evaluate the integral of the spline over area [xa,xb] x [ya,yb].

scipy.interpolate.SmoothBivariateSpline.__call__

`SmoothBivariateSpline.__call__(self, x, y, dx=0, dy=0, grid=True)`

Evaluate the spline or its derivatives at given positions.

Parameters

x, y	[array_like] Input coordinates. If <i>grid</i> is False, evaluate the spline at points $(x[i], y[i])$, $i=0, \dots, \text{len}(x)-1$. Standard Numpy broadcasting is obeyed. If <i>grid</i> is True: evaluate spline at the grid points defined by the coordinate arrays x, y. The arrays must be sorted to increasing order. Note that the axis ordering is inverted relative to the output of meshgrid.
dx	[int] Order of x-derivative New in version 0.14.0.
dy	[int] Order of y-derivative New in version 0.14.0.
grid	[bool] Whether to evaluate the results on a grid spanned by the input arrays, or at points specified by the input arrays. New in version 0.14.0.

scipy.interpolate.SmoothBivariateSpline.ev

`SmoothBivariateSpline.ev(self, xi, yi, dx=0, dy=0)`

Evaluate the spline at points

Returns the interpolated value at $(xi[i], yi[i])$, $i=0, \dots, \text{len}(xi)-1$.

Parameters

xi, yi	[array_like] Input coordinates. Standard Numpy broadcasting is obeyed.
dx	[int, optional] Order of x-derivative New in version 0.14.0.
dy	[int, optional] Order of y-derivative New in version 0.14.0.

scipy.interpolate.SmoothBivariateSpline.get_coeffs

`SmoothBivariateSpline.get_coeffs(self)`

Return spline coefficients.

scipy.interpolate.SmoothBivariateSpline.get_knots

`SmoothBivariateSpline.get_knots(self)`

Return a tuple (tx,ty) where tx,ty contain knots positions of the spline with respect to x-, y-variable, respectively. The position of interior and additional knots are given as $t[k+1:-k-1]$ and $t[:k+1]=b, t[-k-1:]=e$, respectively.

scipy.interpolate.SmoothBivariateSpline.get_residual

SmoothBivariateSpline.**get_residual** (*self*)

Return weighted sum of squared residuals of the spline approximation: $\sum ((w[i]*(z[i]-s(x[i],y[i])))^2, axis=0)$

scipy.interpolate.SmoothBivariateSpline.integral

SmoothBivariateSpline.**integral** (*self*, *xa*, *xb*, *ya*, *yb*)

Evaluate the integral of the spline over area [xa,xb] x [ya,yb].

Parameters

xa, xb [float] The end-points of the x integration interval.
ya, yb [float] The end-points of the y integration interval.

Returns

integ [float] The value of the resulting integral.

scipy.interpolate.SmoothSphereBivariateSpline

class scipy.interpolate.**SmoothSphereBivariateSpline** (*theta*, *phi*, *r*, *w=None*, *s=0.0*, *eps=1e-16*)

Smooth bivariate spline approximation in spherical coordinates.

New in version 0.11.0.

Parameters

theta, phi, r

[array_like] 1-D sequences of data points (order is not important). Coordinates must be given in radians. Theta must lie within the interval $[0, \pi]$, and phi must lie within the interval $[0, 2\pi]$.

w [array_like, optional] Positive 1-D sequence of weights.

s [float, optional] Positive smoothing factor defined for estimation condition: $\sum ((w(i)*(r(i) - s(theta(i), phi(i))))^2, axis=0) \leq s$ Default $s=\text{len}(w)$ which should be a good value if $1/w[i]$ is an estimate of the standard deviation of $r[i]$.

eps [float, optional] A threshold for determining the effective rank of an over-determined linear system of equations. *eps* should have a value within the open interval $(0, 1)$, the default is $1e-16$.

See also:

[BivariateSpline](#)

a base class for bivariate splines.

[UnivariateSpline](#)

a smooth univariate spline to fit a given set of data points.

[SmoothBivariateSpline](#)

a smoothing bivariate spline through the given points

[LSQBivariateSpline](#)

a bivariate spline using weighted least-squares fitting

RectSphereBivariateSpline

a bivariate spline over a rectangular mesh on a sphere

LSQSphereBivariateSpline

a bivariate spline in spherical coordinates using weighted least-squares fitting

RectBivariateSpline

a bivariate spline over a rectangular mesh.

bisplrep

a function to find a bivariate B-spline representation of a surface

bisplev

a function to evaluate a bivariate B-spline and its derivatives

Notes

For more information, see the [FITPACK](#) site about this function.

Examples

Suppose we have global data on a coarse grid (the input data does not have to be on a grid):

```
>>> theta = np.linspace(0., np.pi, 7)
>>> phi = np.linspace(0., 2*np.pi, 9)
>>> data = np.empty((theta.shape[0], phi.shape[0]))
>>> data[:,0], data[0,:], data[-1,:] = 0., 0., 0.
>>> data[1:-1,1], data[1:-1,-1] = 1., 1.
>>> data[1,1:-1], data[-2,1:-1] = 1., 1.
>>> data[2:-2,2], data[2:-2,-2] = 2., 2.
>>> data[2,2:-2], data[-3,2:-2] = 2., 2.
>>> data[3,3:-2] = 3.
>>> data = np.roll(data, 4, 1)
```

We need to set up the interpolator object

```
>>> lats, lons = np.meshgrid(theta, phi)
>>> from scipy.interpolate import SmoothSphereBivariateSpline
>>> lut = SmoothSphereBivariateSpline(lats.ravel(), lons.ravel(),
...                                 data.T.ravel(), s=3.5)
```

As a first test, we'll see what the algorithm returns when run on the input coordinates

```
>>> data_orig = lut(theta, phi)
```


Finally we interpolate the data to a finer grid

```
>>> fine_lats = np.linspace(0., np.pi, 70)
>>> fine_lons = np.linspace(0., 2 * np.pi, 90)
```

```
>>> data_smth = lut(fine_lats, fine_lons)
```

```

>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> ax1 = fig.add_subplot(131)
>>> ax1.imshow(data, interpolation='nearest')
>>> ax2 = fig.add_subplot(132)
>>> ax2.imshow(data_orig, interpolation='nearest')
>>> ax3 = fig.add_subplot(133)
>>> ax3.imshow(data_smth, interpolation='nearest')
>>> plt.show()
    
```



Methods

<code>__call__(self, theta, phi[, dtheta, dphi, grid])</code>	Evaluate the spline or its derivatives at given positions.
<code>ev(self, theta, phi[, dtheta, dphi])</code>	Evaluate the spline at points
<code>get_coeffs(self)</code>	Return spline coefficients.
<code>get_knots(self)</code>	Return a tuple (tx,ty) where tx,ty contain knots positions of the spline with respect to x-, y-variable, respectively.
<code>get_residual(self)</code>	Return weighted sum of squared residuals of the spline approximation: $\text{sum}((w[i]*(z[i]-s(x[i],y[i])))**2,axis=0)$

scipy.interpolate.SmoothSphereBivariateSpline.__call__

`SmoothSphereBivariateSpline.__call__(self, theta, phi, dtheta=0, dphi=0, grid=True)`

Evaluate the spline or its derivatives at given positions.

Parameters

- theta, phi** [array_like] Input coordinates.
 If *grid* is False, evaluate the spline at points $(\text{theta}[i], \text{phi}[i])$, $i=0, \dots, \text{len}(x)-1$. Standard Numpy broadcasting is obeyed.
 If *grid* is True: evaluate spline at the grid points defined by the coordinate arrays *theta*, *phi*. The arrays must be sorted to increasing order.
- dtheta** [int, optional] Order of theta-derivative
 New in version 0.14.0.
- dphi** [int] Order of phi-derivative
 New in version 0.14.0.
- grid** [bool] Whether to evaluate the results on a grid spanned by the input arrays, or at points specified by the input arrays.
 New in version 0.14.0.

scipy.interpolate.SmoothSphereBivariateSpline.ev

`SmoothSphereBivariateSpline.ev(self, theta, phi, dtheta=0, dphi=0)`

Evaluate the spline at points

Returns the interpolated value at $(\text{theta}[i], \text{phi}[i])$, $i=0, \dots, \text{len}(\text{theta})-1$.

Parameters

- theta, phi** [array_like] Input coordinates. Standard Numpy broadcasting is obeyed.
- dtheta** [int, optional] Order of theta-derivative
 New in version 0.14.0.
- dphi** [int, optional] Order of phi-derivative
 New in version 0.14.0.

scipy.interpolate.SmoothSphereBivariateSpline.get_coeffs

`SmoothSphereBivariateSpline.get_coeffs(self)`

Return spline coefficients.

scipy.interpolate.SmoothSphereBivariateSpline.get_knots

`SmoothSphereBivariateSpline.get_knots(self)`

Return a tuple (tx,ty) where tx,ty contain knots positions of the spline with respect to x-, y-variable, respectively. The position of interior and additional knots are given as $t[k+1:-k-1]$ and $t[:k+1]=b$, $t[-k-1:]=e$, respectively.

scipy.interpolate.SmoothSphereBivariateSpline.get_residual

`SmoothSphereBivariateSpline.get_residual(self)`

Return weighted sum of squared residuals of the spline approximation: $\text{sum}((w[i]*(z[i]-s(x[i],y[i])))**2,axis=0)$

scipy.interpolate.LSQBivariateSpline

class `scipy.interpolate.LSQBivariateSpline` (*x*, *y*, *z*, *tx*, *ty*, *w=None*, *bbox=[None, None, None, None]*, *kx=3*, *ky=3*, *eps=None*)

Weighted least-squares bivariate spline approximation.

Parameters

x, y, z	[array_like] 1-D sequences of data points (order is not important).
tx, ty	[array_like] Strictly ordered 1-D sequences of knots coordinates.
w	[array_like, optional] Positive 1-D array of weights, of the same length as <i>x</i> , <i>y</i> and <i>z</i> .
bbox	[(4,) array_like, optional] Sequence of length 4 specifying the boundary of the rectangular approximation domain. By default, <code>bbox=[min(x, tx), max(x, tx), min(y, ty), max(y, ty)]</code> .
kx, ky	[ints, optional] Degrees of the bivariate spline. Default is 3.
eps	[float, optional] A threshold for determining the effective rank of an over-determined linear system of equations. <i>eps</i> should have a value within the open interval (0, 1), the default is 1e-16.

See also:

BivariateSpline

a base class for bivariate splines.

UnivariateSpline

a smooth univariate spline to fit a given set of data points.

SmoothBivariateSpline

a smoothing bivariate spline through the given points

RectSphereBivariateSpline

a bivariate spline over a rectangular mesh on a sphere

SmoothSphereBivariateSpline

a smoothing bivariate spline in spherical coordinates

LSQSphereBivariateSpline

a bivariate spline in spherical coordinates using weighted least-squares fitting

RectBivariateSpline

a bivariate spline over a rectangular mesh.

bisplrep

a function to find a bivariate B-spline representation of a surface

bisplev

a function to evaluate a bivariate B-spline and its derivatives

Notes

The length of x , y and z should be at least $(k_x+1) * (k_y+1)$.

Methods

<code>__call__(self, x, y[, dx, dy, grid])</code>	Evaluate the spline or its derivatives at given positions.
<code>ev(self, xi, yi[, dx, dy])</code>	Evaluate the spline at points
<code>get_coeffs(self)</code>	Return spline coefficients.
<code>get_knots(self)</code>	Return a tuple (tx,ty) where tx,ty contain knots positions of the spline with respect to x-, y-variable, respectively.
<code>get_residual(self)</code>	Return weighted sum of squared residuals of the spline approximation: $\sum ((w[i]*(z[i]-s(x[i],y[i])))^2, axis=0)$
<code>integral(self, xa, xb, ya, yb)</code>	Evaluate the integral of the spline over area [xa,xb] x [ya,yb].

scipy.interpolate.LSQBivariateSpline.__call__

`LSQBivariateSpline.__call__(self, x, y, dx=0, dy=0, grid=True)`

Evaluate the spline or its derivatives at given positions.

Parameters

x, y	[array_like] Input coordinates. If <i>grid</i> is False, evaluate the spline at points $(x[i], y[i]), i=0, \dots, \text{len}(x)-1$. Standard Numpy broadcasting is obeyed. If <i>grid</i> is True: evaluate spline at the grid points defined by the coordinate arrays x, y. The arrays must be sorted to increasing order. Note that the axis ordering is inverted relative to the output of meshgrid.
dx	[int] Order of x-derivative New in version 0.14.0.
dy	[int] Order of y-derivative New in version 0.14.0.
grid	[bool] Whether to evaluate the results on a grid spanned by the input arrays, or at points specified by the input arrays. New in version 0.14.0.

scipy.interpolate.LSQBivariateSpline.ev

`LSQBivariateSpline.ev(self, xi, yi, dx=0, dy=0)`

Evaluate the spline at points

Returns the interpolated value at $(xi[i], yi[i]), i=0, \dots, \text{len}(xi)-1$.

Parameters

xi, yi	[array_like] Input coordinates. Standard Numpy broadcasting is obeyed.
dx	[int, optional] Order of x-derivative New in version 0.14.0.
dy	[int, optional] Order of y-derivative New in version 0.14.0.

scipy.interpolate.LSQBivariateSpline.get_coeffs

LSQBivariateSpline.get_coeffs(*self*)
 Return spline coefficients.

scipy.interpolate.LSQBivariateSpline.get_knots

LSQBivariateSpline.get_knots(*self*)
 Return a tuple (tx,ty) where tx,ty contain knots positions of the spline with respect to x-, y-variable, respectively. The position of interior and additional knots are given as t[k+1:-k-1] and t[:k+1]=b, t[-k-1:]=e, respectively.

scipy.interpolate.LSQBivariateSpline.get_residual

LSQBivariateSpline.get_residual(*self*)
 Return weighted sum of squared residuals of the spline approximation: $\sum ((w[i]*(z[i]-s(x[i],y[i])))^2, \text{axis}=0)$

scipy.interpolate.LSQBivariateSpline.integral

LSQBivariateSpline.integral(*self*, *xa*, *xb*, *ya*, *yb*)
 Evaluate the integral of the spline over area [xa,xb] x [ya,yb].

Parameters

xa, xb [float] The end-points of the x integration interval.
ya, yb [float] The end-points of the y integration interval.

Returns

integ [float] The value of the resulting integral.

scipy.interpolate.LSQSphereBivariateSpline

class scipy.interpolate.LSQSphereBivariateSpline(*theta*, *phi*, *r*, *tt*, *tp*, *w=None*, *eps=1e-16*)

Weighted least-squares bivariate spline approximation in spherical coordinates.

Determines a smoothing bicubic spline according to a given set of knots in the *theta* and *phi* directions.

New in version 0.11.0.

Parameters

theta, phi, r [array_like] 1-D sequences of data points (order is not important). Coordinates must be given in radians. Theta must lie within the interval $[0, \pi]$, and phi must lie within the interval $[0, 2\pi]$.
tt, tp [array_like] Strictly ordered 1-D sequences of knots coordinates. Coordinates must satisfy $0 < tt[i] < \pi, 0 < tp[i] < 2*\pi$.
w [array_like, optional] Positive 1-D sequence of weights, of the same length as *theta*, *phi* and *r*.
eps [float, optional] A threshold for determining the effective rank of an over-determined linear system of equations. *eps* should have a value within the open interval $(0, 1)$, the default is $1e-16$.

See also:

BivariateSpline

a base class for bivariate splines.

UnivariateSpline

a smooth univariate spline to fit a given set of data points.

SmoothBivariateSpline

a smoothing bivariate spline through the given points

LSQBivariateSpline

a bivariate spline using weighted least-squares fitting

RectSphereBivariateSpline

a bivariate spline over a rectangular mesh on a sphere

SmoothSphereBivariateSpline

a smoothing bivariate spline in spherical coordinates

RectBivariateSpline

a bivariate spline over a rectangular mesh.

bisplrep

a function to find a bivariate B-spline representation of a surface

bisplev

a function to evaluate a bivariate B-spline and its derivatives

Notes

For more information, see the [FITPACK](#) site about this function.

Examples

Suppose we have global data on a coarse grid (the input data does not have to be on a grid):

```
>>> from scipy.interpolate import LSQSphereBivariateSpline
>>> import matplotlib.pyplot as plt
```

```
>>> theta = np.linspace(0, np.pi, num=7)
>>> phi = np.linspace(0, 2*np.pi, num=9)
>>> data = np.empty((theta.shape[0], phi.shape[0]))
>>> data[:,0], data[0,:], data[-1,:] = 0., 0., 0.
>>> data[1:-1,1], data[1:-1,-1] = 1., 1.
>>> data[1,1:-1], data[-2,1:-1] = 1., 1.
>>> data[2:-2,2], data[2:-2,-2] = 2., 2.
>>> data[2,2:-2], data[-3,2:-2] = 2., 2.
>>> data[3,3:-2] = 3.
>>> data = np.roll(data, 4, 1)
```

We need to set up the interpolator object. Here, we must also specify the coordinates of the knots to use.

```
>>> lats, lons = np.meshgrid(theta, phi)
>>> knotst, knotsp = theta.copy(), phi.copy()
>>> knotst[0] += .0001
```

(continues on next page)

(continued from previous page)

```
>>> knotst[-1] -= .0001
>>> knotsp[0] += .0001
>>> knotsp[-1] -= .0001
>>> lut = LSQSphereBivariateSpline(lats.ravel(), lons.ravel(),
...                               data.T.ravel(), knotst, knotsp)
```


As a first test, we'll see what the algorithm returns when run on the input coordinates

```
>>> data_orig = lut(theta, phi)
```

Finally we interpolate the data to a finer grid

```
>>> fine_lats = np.linspace(0., np.pi, 70)
>>> fine_lons = np.linspace(0., 2*np.pi, 90)
>>> data_lsq = lut(fine_lats, fine_lons)
```

```
>>> fig = plt.figure()
>>> ax1 = fig.add_subplot(131)
>>> ax1.imshow(data, interpolation='nearest')
>>> ax2 = fig.add_subplot(132)
>>> ax2.imshow(data_orig, interpolation='nearest')
>>> ax3 = fig.add_subplot(133)
>>> ax3.imshow(data_lsq, interpolation='nearest')
>>> plt.show()
```



Methods

<code>__call__(self, theta, phi[, dtheta, dphi, grid])</code>	Evaluate the spline or its derivatives at given positions.
<code>ev(self, theta, phi[, dtheta, dphi])</code>	Evaluate the spline at points
<code>get_coeffs(self)</code>	Return spline coefficients.
<code>get_knots(self)</code>	Return a tuple (tx,ty) where tx,ty contain knots positions of the spline with respect to x-, y-variable, respectively.
<code>get_residual(self)</code>	Return weighted sum of squared residuals of the spline approximation: $\sum ((w[i]*(z[i]-s(x[i],y[i])))^2, axis=0)$

`scipy.interpolate.LSQSphereBivariateSpline.__call__`

`LSQSphereBivariateSpline.__call__(self, theta, phi, dtheta=0, dphi=0, grid=True)`
Evaluate the spline or its derivatives at given positions.

Parameters

- theta, phi** [array_like] Input coordinates.
If *grid* is False, evaluate the spline at points $(\text{theta}[i], \text{phi}[i])$, $i=0, \dots, \text{len}(x)-1$. Standard Numpy broadcasting is obeyed.
If *grid* is True: evaluate spline at the grid points defined by the coordinate arrays theta, phi. The arrays must be sorted to increasing order.
- dtheta** [int, optional] Order of theta-derivative
New in version 0.14.0.
- dphi** [int] Order of phi-derivative
New in version 0.14.0.
- grid** [bool] Whether to evaluate the results on a grid spanned by the input arrays, or at points specified by the input arrays.
New in version 0.14.0.

`scipy.interpolate.LSQSphereBivariateSpline.ev`

`LSQSphereBivariateSpline.ev(self, theta, phi, dtheta=0, dphi=0)`
Evaluate the spline at points

Returns the interpolated value at $(\text{theta}[i], \text{phi}[i])$, $i=0, \dots, \text{len}(\text{theta})-1$.

Parameters

- theta, phi** [array_like] Input coordinates. Standard Numpy broadcasting is obeyed.
- dtheta** [int, optional] Order of theta-derivative
New in version 0.14.0.
- dphi** [int, optional] Order of phi-derivative
New in version 0.14.0.

scipy.interpolate.LSQSphereBivariateSpline.get_coeffs

LSQSphereBivariateSpline.get_coeffs (self)
 Return spline coefficients.

scipy.interpolate.LSQSphereBivariateSpline.get_knots

LSQSphereBivariateSpline.get_knots (self)
 Return a tuple (tx,ty) where tx,ty contain knots positions of the spline with respect to x-, y-variable, respectively. The position of interior and additional knots are given as t[k+1:-k-1] and t[:k+1]=b, t[-k-1:]=e, respectively.

scipy.interpolate.LSQSphereBivariateSpline.get_residual

LSQSphereBivariateSpline.get_residual (self)
 Return weighted sum of squared residuals of the spline approximation: $\sum ((w[i]*(z[i]-s(x[i],y[i])))^2,axis=0)$

Low-level interface to FITPACK functions:

<code>bisplrep(x, y, z[, w, xb, xe, yb, ye, kx, ...])</code>	Find a bivariate B-spline representation of a surface.
<code>bisplev(x, y, tck[, dx, dy])</code>	Evaluate a bivariate B-spline and its derivatives.

scipy.interpolate.bisplrep

scipy.interpolate.bisplrep (x, y, z, w=None, xb=None, xe=None, yb=None, ye=None, kx=3, ky=3, task=0, s=None, eps=1e-16, tx=None, ty=None, full_output=0, nvest=None, nyest=None, quiet=1)

Find a bivariate B-spline representation of a surface.

Given a set of data points (x[i], y[i], z[i]) representing a surface z=f(x,y), compute a B-spline representation of the surface. Based on the routine SURFIT from FITPACK.

Parameters

- x, y, z** [ndarray] Rank-1 arrays of data points.
- w** [ndarray, optional] Rank-1 array of weights. By default `w=np.ones(len(x))`.
- xb, xe** [float, optional] End points of approximation interval in x. By default `xb = x.min(), xe=x.max()`.
- yb, ye** [float, optional] End points of approximation interval in y. By default `yb=y.min(), ye = y.max()`.
- kx, ky** [int, optional] The degrees of the spline ($1 \leq kx, ky \leq 5$). Third order (`kx=ky=3`) is recommended.
- task** [int, optional] If `task=0`, find knots in x and y and coefficients for a given smoothing factor, s. If `task=1`, find knots and coefficients for another value of the smoothing factor, s. `bisplrep` must have been previously called with `task=0` or `task=1`. If `task=-1`, find coefficients for a given set of knots tx, ty.
- s** [float, optional] A non-negative smoothing factor. If weights correspond to the inverse of the standard-deviation of the errors in z, then a good s-value should be found in the range $(m-\sqrt{2*m}, m+\sqrt{2*m})$ where `m=len(x)`.
- eps** [float, optional] A threshold for determining the effective rank of an over-determined linear system of equations ($0 < eps < 1$). `eps` is not likely to need changing.
- tx, ty** [ndarray, optional] Rank-1 arrays of the knots of the spline for `task=-1`
- full_output** [int, optional] Non-zero to return optional outputs.

nxest, nyest [int, optional] Over-estimates of the total number of knots. If None then $nxest = \max(kx + \sqrt{m/2}, 2 * kx + 3)$, $nyest = \max(ky + \sqrt{m/2}, 2 * ky + 3)$.

quiet [int, optional] Non-zero to suppress printing of messages. This parameter is deprecated; use standard Python warning filters instead.

Returns

tck [array_like] A list [tx, ty, c, kx, ky] containing the knots (tx, ty) and coefficients (c) of the bivariate B-spline representation of the surface along with the degree of the spline.

fp [ndarray] The weighted sum of squared residuals of the spline approximation.

ier [int] An integer flag about splrep success. Success is indicated if $ier \leq 0$. If ier in [1,2,3] an error occurred but was not raised. Otherwise an error is raised.

msg [str] A message corresponding to the integer flag, ier .

See also:

splprep, splrep, splint, sproot, splev
UnivariateSpline, BivariateSpline

Notes

See *bisplev* to evaluate the value of the B-spline given its tck representation.

References

[1], [2], [3]

Examples

Examples are given *in the tutorial*.

scipy.interpolate.bisplev

`scipy.interpolate.bisplev(x, y, tck, dx=0, dy=0)`

Evaluate a bivariate B-spline and its derivatives.

Return a rank-2 array of spline function values (or spline derivative values) at points given by the cross-product of the rank-1 arrays x and y . In special cases, return an array or just a float if either x or y or both are floats. Based on BISPEV from FITPACK.

Parameters

x, y [ndarray] Rank-1 arrays specifying the domain over which to evaluate the spline or its derivative.

tck [tuple] A sequence of length 5 returned by *bisplrep* containing the knot locations, the coefficients, and the degree of the spline: [tx, ty, c, kx, ky].

dx, dy [int, optional] The orders of the partial derivatives in x and y respectively.

Returns

vals [ndarray] The B-spline or its derivative evaluated over the set formed by the cross-product of x and y .

See also:

splprep, splrep, splint, sproot, splev
UnivariateSpline, BivariateSpline

Notes

See *bisplrep* to generate the *tck* representation.

References

[1], [2], [3]

Examples

Examples are given *in the tutorial*.

6.8.5 Additional tools

<i>lagrange</i> (x, w)		Return a Lagrange interpolating polynomial.
<i>approximate_taylor_polynomial</i> (f, degree, ...)	x,	Estimate the Taylor polynomial of f at x by polynomial fitting.
<i>pade</i> (an, m[, n])		Return Pade approximation to a polynomial as the ratio of two polynomials.

scipy.interpolate.lagrange

`scipy.interpolate.lagrange` (x, w)

Return a Lagrange interpolating polynomial.

Given two 1-D arrays *x* and *w*, returns the Lagrange interpolating polynomial through the points (*x*, *w*).

Warning: This implementation is numerically unstable. Do not expect to be able to use more than about 20 points even if they are chosen optimally.

Parameters

x [array_like] *x* represents the x-coordinates of a set of datapoints.
w [array_like] *w* represents the y-coordinates of a set of datapoints, i.e., $f(x)$.

Returns

lagrange [numpy.poly1d instance] The Lagrange interpolating polynomial.

Examples

Interpolate $f(x) = x^3$ by 3 points.

```
>>> from scipy.interpolate import lagrange
>>> x = np.array([0, 1, 2])
>>> y = x**3
>>> poly = lagrange(x, y)
```

Since there are only 3 points, Lagrange polynomial has degree 2. Explicitly, it is given by

$$\begin{aligned} L(x) &= 1 \times \frac{x(x-2)}{-1} + 8 \times \frac{x(x-1)}{2} \\ &= x(-2 + 3x) \end{aligned}$$

```
>>> from numpy.polynomial.polynomial import Polynomial
>>> Polynomial(poly).coef
array([ 3., -2.,  0.]
```

scipy.interpolate.approximate_taylor_polynomial

`scipy.interpolate.approximate_taylor_polynomial` (*f*, *x*, *degree*, *scale*, *order=None*)

Estimate the Taylor polynomial of *f* at *x* by polynomial fitting.

Parameters

- | | |
|---------------|--|
| f | [callable] The function whose Taylor polynomial is sought. Should accept a vector of <i>x</i> values. |
| x | [scalar] The point at which the polynomial is to be evaluated. |
| degree | [int] The degree of the Taylor polynomial |
| scale | [scalar] The width of the interval to use to evaluate the Taylor polynomial. Function values spread over a range this wide are used to fit the polynomial. Must be chosen carefully. |
| order | [int or None, optional] The order of the polynomial to be used in the fitting; <i>f</i> will be evaluated <i>order</i> +1 times. If None, use <i>degree</i> . |

Returns

- | | |
|----------|---|
| p | [poly1d instance] The Taylor polynomial (translated to the origin, so that for example $p(0)=f(x)$). |
|----------|---|

Notes


The appropriate choice of “scale” is a trade-off; too large and the function differs from its Taylor polynomial too much to get a good answer, too small and round-off errors overwhelm the higher-order terms. The algorithm used becomes numerically unstable around order 30 even under ideal circumstances.

Choosing order somewhat larger than degree may improve the higher-order terms.

Examples

We can calculate Taylor approximation polynomials of sin function with various degrees:

```
>>> import matplotlib.pyplot as plt
>>> from scipy.interpolate import approximate_taylor_polynomial
>>> x = np.linspace(-10.0, 10.0, num=100)
>>> plt.plot(x, np.sin(x), label="sin curve")
>>> for degree in np.arange(1, 15, step=2):
...     sin_taylor = approximate_taylor_polynomial(np.sin, 0, degree, 1,
...                                               order=degree + 2)
...     plt.plot(x, sin_taylor(x), label=f"degree={degree}")
>>> plt.legend(bbox_to_anchor=(1.05, 1), loc='upper left',
...           borderaxespad=0.0, shadow=True)
>>> plt.tight_layout()
>>> plt.axis([-10, 10, -10, 10])
>>> plt.show()
```



scipy.interpolate.pade

`scipy.interpolate.pade` (*an*, *m*, *n=None*)

Return Pade approximation to a polynomial as the ratio of two polynomials.

Parameters

- an** [(N,) array_like] Taylor series coefficients.
- m** [int] The order of the returned approximating polynomial q .
- n** [int, optional] The order of the returned approximating polynomial p . By default, the order is $\text{len}(an) - m$.

Returns

- p, q** [Polynomial class] The Pade approximation of the polynomial defined by an is $p(x) / q(x)$.

Examples

```
>>> from scipy.interpolate import pade
>>> e_exp = [1.0, 1.0, 1.0/2.0, 1.0/6.0, 1.0/24.0, 1.0/120.0]
>>> p, q = pade(e_exp, 2)
```

```
>>> e_exp.reverse()
>>> e_poly = np.poly1d(e_exp)
```

Compare $e_poly(x)$ and the Pade approximation $p(x)/q(x)$

```
>>> e_poly(1)
2.7166666666666668
```

```
>>> p(1)/q(1)
2.7179487179487181
```

See also:

scipy.ndimage.map_coordinates, *scipy.ndimage.spline_filter*, *scipy.signal.resample*, *scipy.signal.bspline*, *scipy.signal.gauss_spline*, *scipy.signal.qspline1d*, *scipy.signal.cspline1d*, *scipy.signal.qspline1d_eval*, *scipy.signal.cspline1d_eval*, *scipy.signal.qspline2d*, *scipy.signal.cspline2d*.

pchip is an alias of *PchipInterpolator* for backward compatibility (should not be used in new code).

6.9 Input and output (`scipy.io`)

SciPy has many modules, classes, and functions available to read data from and write data to a variety of file formats.

See also:

NumPy IO routines

6.9.1 MATLAB® files

<i>loadmat</i> (file_name[, mdict, appendmat])	Load MATLAB file.
<i>savemat</i> (file_name, mdict[, appendmat, ...])	Save a dictionary of names and arrays into a MATLAB-style .mat file.
<i>whosmat</i> (file_name[, appendmat])	List variables inside a MATLAB file.

scipy.io.loadmat

`scipy.io.loadmat` (*file_name*, *mdict=None*, *appendmat=True*, ***kwargs*)
Load MATLAB file.

Parameters

- file_name** [str] Name of the mat file (do not need .mat extension if `appendmat==True`). Can also pass open file-like object.
- mdict** [dict, optional] Dictionary in which to insert matfile variables.
- appendmat** [bool, optional] True to append the .mat extension to the end of the given filename, if not already present.
- byte_order** [str or None, optional] None by default, implying byte order guessed from mat file. Otherwise can be one of ('native', '=', 'little', '<', 'BIG', '>').
- mat_dtype** [bool, optional] If True, return arrays in same dtype as would be loaded into MATLAB (instead of the dtype with which they are saved).
- squeeze_me** [bool, optional] Whether to squeeze unit matrix dimensions or not.
- chars_as_strings** [bool, optional] Whether to convert char arrays to string arrays.
- matlab_compatible** [bool, optional] Returns matrices as would be loaded by MATLAB (implies `squeeze_me=False`, `chars_as_strings=False`, `mat_dtype=True`, `struct_as_record=True`).
- struct_as_record** [bool, optional] Whether to load MATLAB structs as NumPy record arrays, or as old-style NumPy arrays with `dtype=object`. Setting this flag to False replicates the behavior of scipy version 0.7.x (returning NumPy object arrays). The default setting is True, because it allows easier round-trip load and save of MATLAB files.
- verify_compressed_data_integrity** [bool, optional] Whether the length of compressed sequences in the MATLAB file should be checked, to ensure that they are not longer than we expect. It is advisable to enable this (the default) because overlong compressed sequences in MATLAB files generally indicate that the files have experienced some sort of corruption.
- variable_names** [None or sequence] If None (the default) - read all variables in file. Otherwise, *variable_names* should be a sequence of strings, giving names of the MATLAB variables to read from the file. The reader will skip any variable with a name not in this sequence, possibly saving some read processing.
- simplify_cells** [False, optional] If True, return a simplified dict structure (which is useful if the mat file contains cell arrays). Note that this only affects the structure of the result and not its contents (which is identical for both output structures). If True, this automatically sets *struct_as_record* to False and *squeeze_me* to True, which is required to simplify cells.

Returns

- mat_dict** [dict] dictionary with variable names as keys, and loaded matrices as values.

Notes

v4 (Level 1.0), v6 and v7 to 7.2 matfiles are supported.

You will need an HDF5 Python library to read MATLAB 7.3 format mat files. Because SciPy does not supply one, we do not implement the HDF5 / 7.3 interface here.

Examples

```
>>> from os.path import dirname, join as pjoin
>>> import scipy.io as sio
```

Get the filename for an example .mat file from the tests/data directory.

```
>>> data_dir = pjoin(dirname(sio.__file__), 'matlab', 'tests', 'data')
>>> mat_fname = pjoin(data_dir, 'testdouble_7.4_GLNx86.mat')
```

Load the .mat file contents.

```
>>> mat_contents = sio.loadmat(mat_fname)
```

The result is a dictionary, one key/value pair for each variable:

```
>>> sorted(mat_contents.keys())
['_globals_', '__header__', '__version__', 'testdouble']
>>> mat_contents['testdouble']
array([[0.          , 0.78539816, 1.57079633, 2.35619449, 3.14159265,
        3.92699082, 4.71238898, 5.49778714, 6.28318531]])
```

By default SciPy reads MATLAB structs as structured NumPy arrays where the dtype fields are of type *object* and the names correspond to the MATLAB struct field names. This can be disabled by setting the optional argument `struct_as_record=False`.

Get the filename for an example .mat file that contains a MATLAB struct called `teststruct` and load the contents.

```
>>> matstruct_fname = pjoin(data_dir, 'teststruct_7.4_GLNx86.mat')
>>> matstruct_contents = sio.loadmat(matstruct_fname)
>>> teststruct = matstruct_contents['teststruct']
>>> teststruct.dtype
dtype([('stringfield', 'O'), ('doublefield', 'O'), ('complexfield', 'O')])
```

The size of the structured array is the size of the MATLAB struct, not the number of elements in any particular field. The shape defaults to 2-D unless the optional argument `squeeze_me=True`, in which case all length 1 dimensions are removed.

```
>>> teststruct.size
1
>>> teststruct.shape
(1, 1)
```

Get the 'stringfield' of the first element in the MATLAB struct.

```
>>> teststruct[0, 0]['stringfield']
array(['Rats live on no evil star.'],
      dtype='<U26')
```

Get the first element of the 'doublefield'.

```
>>> teststruct['doublefield'][0, 0]
array([[ 1.41421356,  2.71828183,  3.14159265]])
```

Load the MATLAB struct, squeezing out length 1 dimensions, and get the item from the 'complexfield'.

```
>>> matstruct_squeezed = sio.loadmat(matstruct_fname, squeeze_me=True)
>>> matstruct_squeezed['teststruct'].shape
()
>>> matstruct_squeezed['teststruct']['complexfield'].shape
()
>>> matstruct_squeezed['teststruct']['complexfield'].item()
array([ 1.41421356+1.41421356j,  2.71828183+2.71828183j,
        3.14159265+3.14159265j])
```

scipy.io.savemat

`scipy.io.savemat` (*file_name*, *mdict*, *appendmat=True*, *format='5'*, *long_field_names=False*, *do_compression=False*, *oned_as='row'*)

Save a dictionary of names and arrays into a MATLAB-style .mat file.

This saves the array objects in the given dictionary to a MATLAB- style .mat file.

Parameters

- file_name** [str or file-like object] Name of the .mat file (.mat extension not needed if `appendmat == True`). Can also pass open file_like object.
- mdict** [dict] Dictionary from which to save matfile variables.
- appendmat** [bool, optional] True (the default) to append the .mat extension to the end of the given file-name, if not already present.
- format** [{'5', '4'}, string, optional] '5' (the default) for MATLAB 5 and up (to 7.2), '4' for MATLAB 4 .mat files.
- long_field_names** [bool, optional] False (the default) - maximum field name length in a structure is 31 characters which is the documented maximum length. True - maximum field name length in a structure is 63 characters which works for MATLAB 7.6+.
- do_compression** [bool, optional] Whether or not to compress matrices on write. Default is False.
- oned_as** [{'row', 'column'}, optional] If 'column', write 1-D NumPy arrays as column vectors. If 'row', write 1-D NumPy arrays as row vectors.

Examples

```
>>> from scipy.io import savemat
>>> a = np.arange(20)
>>> mdic = {"a": a, "label": "experiment"}
>>> mdic
{'a': array([ 0,  1,  2,  3,  4,  5,  6,  7,  8,  9, 10, 11, 12, 13, 14,
             ↪15, 16,
             17, 18, 19]),
 'label': 'experiment'}
```

(continues on next page)

(continued from previous page)

```
'label': 'experiment'}
>>> savemat("matlab_matrix.mat", mdic)
```

scipy.io.whosmat

`scipy.io.whosmat` (*file_name*, *appendmat=True*, ***kwargs*)

List variables inside a MATLAB file.

Parameters

- file_name** [str] Name of the mat file (do not need .mat extension if `appendmat==True`) Can also pass open file-like object.
- appendmat** [bool, optional] True to append the .mat extension to the end of the given filename, if not already present.
- byte_order** [str or None, optional] None by default, implying byte order guessed from mat file. Otherwise can be one of ('native', '=', 'little', '<', 'BIG', '>').
- mat_dtype** [bool, optional] If True, return arrays in same dtype as would be loaded into MATLAB (instead of the dtype with which they are saved).
- squeeze_me** [bool, optional] Whether to squeeze unit matrix dimensions or not.
- chars_as_strings** [bool, optional] Whether to convert char arrays to string arrays.
- matlab_compatible** [bool, optional] Returns matrices as would be loaded by MATLAB (implies `squeeze_me=False`, `chars_as_strings=False`, `mat_dtype=True`, `struct_as_record=True`).
- struct_as_record** [bool, optional] Whether to load MATLAB structs as NumPy record arrays, or as old-style NumPy arrays with `dtype=object`. Setting this flag to False replicates the behavior of SciPy version 0.7.x (returning numpy object arrays). The default setting is True, because it allows easier round-trip load and save of MATLAB files.

Returns

- variables** [list of tuples] A list of tuples, where each tuple holds the matrix name (a string), its shape (tuple of ints), and its data class (a string). Possible data classes are: int8, uint8, int16, uint16, int32, uint32, int64, uint64, single, double, cell, struct, object, char, sparse, function, opaque, logical, unknown.

Notes

v4 (Level 1.0), v6 and v7 to 7.2 matfiles are supported.

You will need an HDF5 python library to read matlab 7.3 format mat files. Because SciPy does not supply one, we do not implement the HDF5 / 7.3 interface here.

New in version 0.12.0.

6.9.2 IDL® files

<code>readsav(file_name[, idict, python_dict, ...])</code>	Read an IDL .sav file.
--	------------------------

scipy.io.readsav

`scipy.io.readsav` (*file_name*, *idict=None*, *python_dict=False*, *uncompressed_file_name=None*, *verbose=False*)
 Read an IDL .sav file.

Parameters

- file_name** [str] Name of the IDL save file.
- idict** [dict, optional] Dictionary in which to insert .sav file variables.
- python_dict** [bool, optional] By default, the object return is not a Python dictionary, but a case-insensitive dictionary with item, attribute, and call access to variables. To get a standard Python dictionary, set this option to True.
- uncompressed_file_name** [str, optional] This option only has an effect for .sav files written with the /compress option. If a file name is specified, compressed .sav files are uncompressed to this file. Otherwise, readsav will use the `tempfile` module to determine a temporary filename automatically, and will remove the temporary file upon successfully reading it in.
- verbose** [bool, optional] Whether to print out information about the save file, including the records read, and available variables.

Returns

- idl_dict** [AttrDict or dict] If *python_dict* is set to False (default), this function returns a case-insensitive dictionary with item, attribute, and call access to variables. If *python_dict* is set to True, this function returns a Python dictionary with all variable names in lowercase. If *idict* was specified, then variables are written to the dictionary specified, and the updated dictionary is returned.

Examples

```
>>> from os.path import dirname, join as pjoin
>>> import scipy.io as sio
>>> from scipy.io import readsav
```

Get the filename for an example .sav file from the tests/data directory.

```
>>> data_dir = pjoin(dirname(sio.__file__), 'tests', 'data')
>>> sav_fname = pjoin(data_dir, 'array_float32_1d.sav')
```

Load the .sav file contents.

```
>>> sav_data = readsav(sav_fname)
```

Get keys of the .sav file contents.

```
>>> print(sav_data.keys())
dict_keys(['array1d'])
```

Access a content with a key.

```
>>> print(sav_data['array1d'])
[0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0.
 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0.
 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0.
 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0.
 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0.
 0. 0. 0.]
```

6.9.3 Matrix Market files

<code>mminfo(source)</code>	Return size and storage parameters from Matrix Market file-like 'source'.
<code>mmread(source)</code>	Reads the contents of a Matrix Market file-like 'source' into a matrix.
<code>mmwrite(target, a[, comment, field, ...])</code>	Writes the sparse or dense array <i>a</i> to Matrix Market file-like <i>target</i> .

scipy.io.mminfo

`scipy.io.mminfo(source)`

Return size and storage parameters from Matrix Market file-like 'source'.

Parameters

source [str or file-like] Matrix Market filename (extension .mtx) or open file-like object

Returns

rows [int] Number of matrix rows.
cols [int] Number of matrix columns.
entries [int] Number of non-zero entries of a sparse matrix or rows*cols for a dense matrix.
format [str] Either 'coordinate' or 'array'.
field [str] Either 'real', 'complex', 'pattern', or 'integer'.
symmetry [str] Either 'general', 'symmetric', 'skew-symmetric', or 'hermitian'.

scipy.io.mmread

`scipy.io.mmread(source)`

Reads the contents of a Matrix Market file-like 'source' into a matrix.

Parameters

source [str or file-like] Matrix Market filename (extensions .mtx, .mtz.gz) or open file-like object.

Returns

a [ndarray or coo_matrix] Dense or sparse matrix depending on the matrix format in the Matrix Market file.

scipy.io.mmwrite

`scipy.io.mmwrite` (*target*, *a*, *comment=""*, *field=None*, *precision=None*, *symmetry=None*)
 Writes the sparse or dense array *a* to Matrix Market file-like *target*.

Parameters

target [str or file-like] Matrix Market filename (extension .mtx) or open file-like object.
a [array like] Sparse or dense 2-D array.
comment [str, optional] Comments to be prepended to the Matrix Market file.
field [None or str, optional] Either 'real', 'complex', 'pattern', or 'integer'.
precision [None or int, optional] Number of digits to display for real or complex values.
symmetry [None or str, optional] Either 'general', 'symmetric', 'skew-symmetric', or 'hermitian'. If symmetry is None the symmetry type of 'a' is determined by its values.

6.9.4 Unformatted Fortran files

<code>FortranFile</code> (filename[, mode, header_dtype])	A file object for unformatted sequential files from Fortran code.
<code>FortranEOFError</code>	Indicates that the file ended properly.
<code>FortranFormattingError</code>	Indicates that the file ended mid-record.

scipy.io.FortranFile

class `scipy.io.FortranFile` (*filename*, *mode='r'*, *header_dtype=<class 'numpy.uint32'>*)
 A file object for unformatted sequential files from Fortran code.

Parameters

filename [file or str] Open file object or filename.
mode [{'r', 'w'}, optional] Read-write mode, default is 'r'.
header_dtype [dtype, optional] Data type of the header. Size and endianness must match the input/output file.

Notes

These files are broken up into records of unspecified types. The size of each record is given at the start (although the size of this header is not standard) and the data is written onto disk without any formatting. Fortran compilers supporting the BACKSPACE statement will write a second copy of the size to facilitate backwards seeking.

This class only supports files written with both sizes for the record. It also does not support the subrecords used in Intel and gfortran compilers for records which are greater than 2GB with a 4-byte header.

An example of an unformatted sequential file in Fortran would be written as:

```
OPEN(1, FILE=myfilename, FORM='unformatted')
WRITE(1) myvariable
```

Since this is a non-standard file format, whose contents depend on the compiler and the endianness of the machine, caution is advised. Files from gfortran 4.8.0 and gfortran 4.1.2 on x86_64 are known to work.

Consider using Fortran direct-access files or files from the newer Stream I/O, which can be easily read by `numpy.fromfile`.

Examples

To create an unformatted sequential Fortran file:

```
>>> from scipy.io import FortranFile
>>> f = FortranFile('test.unf', 'w')
>>> f.write_record(np.array([1,2,3,4,5], dtype=np.int32))
>>> f.write_record(np.linspace(0,1,20).reshape((5,4)).T)
>>> f.close()
```

To read this file:

```
>>> f = FortranFile('test.unf', 'r')
>>> print(f.read_ints(np.int32))
[1 2 3 4 5]
>>> print(f.read_reals(float).reshape((5,4), order="F"))
[[0.          0.05263158 0.10526316 0.15789474]
 [0.21052632 0.26315789 0.31578947 0.36842105]
 [0.42105263 0.47368421 0.52631579 0.57894737]
 [0.63157895 0.68421053 0.73684211 0.78947368]
 [0.84210526 0.89473684 0.94736842 1.          ]]
>>> f.close()
```

Or, in Fortran:

```
integer :: a(5), i
double precision :: b(5,4)
open(1, file='test.unf', form='unformatted')
read(1) a
read(1) b
close(1)
write(*,*) a
do i = 1, 5
    write(*,*) b(i,:)
end do
```

Methods

<code>close(self)</code>	Closes the file.
<code>read_ints(self[, dtype])</code>	Reads a record of a given type from the file, defaulting to an integer type (<code>INTEGER*4</code> in Fortran).
<code>read_reals(self[, dtype])</code>	Reads a record of a given type from the file, defaulting to a floating point number (<code>real*8</code> in Fortran).
<code>read_record(self, *dtypes, **kwargs)</code>	Reads a record of a given type from the file.
<code>write_record(self, *items)</code>	Write a record (including sizes) to the file.

scipy.io.FortranFile.close

FortranFile.**close** (*self*)

Closes the file. It is unsupported to call any other methods off this object after closing it. Note that this class supports the ‘with’ statement in modern versions of Python, to call this automatically

scipy.io.FortranFile.read_ints

FortranFile.**read_ints** (*self*, *dtype='i4'*)

Reads a record of a given type from the file, defaulting to an integer type (INTEGER*4 in Fortran).

Parameters

dtype [dtype, optional] Data type specifying the size and endness of the data.

Returns

data [ndarray] A 1-D array object.

See also:

[*read_reals*](#)

[*read_record*](#)

scipy.io.FortranFile.read_reals

FortranFile.**read_reals** (*self*, *dtype='f8'*)

Reads a record of a given type from the file, defaulting to a floating point number (real*8 in Fortran).

Parameters

dtype [dtype, optional] Data type specifying the size and endness of the data.

Returns

data [ndarray] A 1-D array object.

See also:

[*read_ints*](#)

[*read_record*](#)

scipy.io.FortranFile.read_record

FortranFile.**read_record** (*self*, **dtypes*, ***kwargs*)

Reads a record of a given type from the file.

Parameters

***dtypes** [dtypes, optional] Data type(s) specifying the size and endness of the data.

Returns

data [ndarray] A 1-D array object.

Raises

FortranEOFError

To signal that no further records are available

FortranFormattingError

To signal that the end of the file was encountered part-way through a record

See also:

`read_reals``read_ints`

Notes

If the record contains a multidimensional array, you can specify the size in the dtype. For example:

```
INTEGER var(5,4)
```

can be read with:

```
read_record('(4,5)i4').T
```

Note that this function does **not** assume the file data is in Fortran column major order, so you need to (i) swap the order of dimensions when reading and (ii) transpose the resulting array.

Alternatively, you can read the data as a 1-D array and handle the ordering yourself. For example:

```
read_record('i4').reshape(5, 4, order='F')
```

For records that contain several variables or mixed types (as opposed to single scalar or array types), give them as separate arguments:

```
double precision :: a
integer :: b
write(1) a, b

record = f.read_record('<f4', '<i4')
a = record[0] # first number
b = record[1] # second number
```

and if any of the variables are arrays, the shape can be specified as the third item in the relevant dtype:

```
double precision :: a
integer :: b(3,4)
write(1) a, b

record = f.read_record('<f4', np.dtype((<i4', (4, 3))))
a = record[0]
b = record[1].T
```

NumPy also supports a short syntax for this kind of type:

```
record = f.read_record('<f4', '(3,3)<i4')
```

scipy.io.FortranFile.write_record

FortranFile.**write_record** (*self*, **items*)

Write a record (including sizes) to the file.

Parameters

***items** [array_like] The data arrays to write.

Notes

Writes data items to a file:

```
write_record(a.T, b.T, c.T, ...)
write(1) a, b, c, ...
```

Note that data in multidimensional arrays is written in row-major order — to make them read correctly by Fortran programs, you need to transpose the arrays yourself when writing them.

scipy.io.FortranEOFError

exception `scipy.io.FortranEOFError`

Indicates that the file ended properly.

This error descends from `TypeError` because the code used to raise `TypeError` (and this was the only way to know that the file had ended) so users might have `except TypeError:`.

errno

POSIX exception code

filename

exception filename

filename2

second exception filename

strerror

exception strerror

with_traceback()

Exception.with_traceback(tb) – set `self.__traceback__` to `tb` and return `self`.

scipy.io.FortranFormattingError

exception `scipy.io.FortranFormattingError`

Indicates that the file ended mid-record.

Descends from `TypeError` for backward compatibility.

errno

POSIX exception code

filename

exception filename

filename2

second exception filename

strerrorexception `strerror`**with_traceback()**Exception.`with_traceback(tb)` – set `self.__traceback__` to `tb` and return self.

6.9.5 Netcdf

<code>netcdf_file(filename[, mode, mmap, version, ...])</code>	A file object for NetCDF data.
<code>netcdf_variable(data, typecode, size, shape, ...)</code>	A data object for netcdf files.

scipy.io.netcdf_file

class `scipy.io.netcdf_file` (*filename, mode='r', mmap=None, version=1, maskandscale=False*)

A file object for NetCDF data.

A `netcdf_file` object has two standard attributes: *dimensions* and *variables*. The values of both are dictionaries, mapping dimension names to their associated lengths and variable names to variables, respectively. Application programs should never modify these dictionaries.

All other attributes correspond to global attributes defined in the NetCDF file. Global file attributes are created by assigning to an attribute of the `netcdf_file` object.

Parameters

filename	[string or file-like] string -> filename
mode	[{'r', 'w', 'a'}, optional] read-write-append mode, default is 'r'
mmap	[None or bool, optional] Whether to mmap <i>filename</i> when reading. Default is True when <i>filename</i> is a file name, False when <i>filename</i> is a file-like object. Note that when mmap is in use, data arrays returned refer directly to the mmaped data on disk, and the file cannot be closed as long as references to it exist.
version	[{1, 2}, optional] version of netcdf to read / write, where 1 means <i>Classic format</i> and 2 means <i>64-bit offset format</i> . Default is 1. See here for more info.
maskandscale	[bool, optional] Whether to automatically scale and/or mask data based on attributes. Default is False.

Notes

The major advantage of this module over other modules is that it doesn't require the code to be linked to the NetCDF libraries. This module is derived from [pupynere](#).

NetCDF files are a self-describing binary data format. The file contains metadata that describes the dimensions and variables in the file. More details about NetCDF files can be found [here](#). There are three main sections to a NetCDF data structure:

1. Dimensions
2. Variables
3. Attributes

The dimensions section records the name and length of each dimension used by the variables. The variables would then indicate which dimensions it uses and any attributes such as data units, along with containing the data values for the variable. It is good practice to include a variable that is the same name as a dimension to provide the values

for that axes. Lastly, the attributes section would contain additional information such as the name of the file creator or the instrument used to collect the data.

When writing data to a NetCDF file, there is often the need to indicate the ‘record dimension’. A record dimension is the unbounded dimension for a variable. For example, a temperature variable may have dimensions of latitude, longitude and time. If one wants to add more temperature data to the NetCDF file as time progresses, then the temperature variable should have the time dimension flagged as the record dimension.

In addition, the NetCDF file header contains the position of the data in the file, so access can be done in an efficient manner without loading unnecessary data into memory. It uses the `mmap` module to create Numpy arrays mapped to the data on disk, for the same purpose.

Note that when `netcdf_file` is used to open a file with `mmap=True` (default for read-only), arrays returned by it refer to data directly on the disk. The file should not be closed, and cannot be cleanly closed when asked, if such arrays are alive. You may want to copy data arrays obtained from mmapmed Netcdf file if they are to be processed after the file is closed, see the example below.

Examples

To create a NetCDF file:

```
>>> from scipy.io import netcdf
>>> f = netcdf.netcdf_file('simple.nc', 'w')
>>> f.history = 'Created for a test'
>>> f.createDimension('time', 10)
>>> time = f.createVariable('time', 'i', ('time',))
>>> time[:] = np.arange(10)
>>> time.units = 'days since 2008-01-01'
>>> f.close()
```

Note the assignment of `arange(10)` to `time[:]`. Exposing the slice of the time variable allows for the data to be set in the object, rather than letting `arange(10)` overwrite the `time` variable.

To read the NetCDF file we just created:

```
>>> from scipy.io import netcdf
>>> f = netcdf.netcdf_file('simple.nc', 'r')
>>> print(f.history)
b'Created for a test'
>>> time = f.variables['time']
>>> print(time.units)
b'days since 2008-01-01'
>>> print(time.shape)
(10,)
>>> print(time[-1])
9
```

NetCDF files, when opened read-only, return arrays that refer directly to memory-mapped data on disk:

```
>>> data = time[:]
>>> data.base.base
<mmap.mmap object at 0x7fe753763180>
```

If the data is to be processed after the file is closed, it needs to be copied to main memory:

```
>>> data = time[:].copy()
>>> f.close()
>>> data.mean()
4.5
```

A NetCDF file can also be used as context manager:

```
>>> from scipy.io import netcdf
>>> with netcdf.netcdf_file('simple.nc', 'r') as f:
...     print(f.history)
b'Created for a test'
```

Methods

<i>close</i> (self)	Closes the NetCDF file.
<i>createDimension</i> (self, name, length)	Adds a dimension to the Dimension section of the NetCDF data structure.
<i>createVariable</i> (self, name, type, dimensions)	Create an empty variable for the <i>netcdf_file</i> object, specifying its data type and the dimensions it uses.
<i>flush</i> (self)	Perform a sync-to-disk flush if the <i>netcdf_file</i> object is in write mode.
<i>sync</i> (self)	Perform a sync-to-disk flush if the <i>netcdf_file</i> object is in write mode.

scipy.io.netcdf_file.close

netcdf_file.close (*self*)
Closes the NetCDF file.

scipy.io.netcdf_file.createDimension

netcdf_file.createDimension (*self*, *name*, *length*)
Adds a dimension to the Dimension section of the NetCDF data structure.

Note that this function merely adds a new dimension that the variables can reference. The values for the dimension, if desired, should be added as a variable using *createVariable*, referring to this dimension.

Parameters

name [str] Name of the dimension (Eg, 'lat' or 'time').
length [int] Length of the dimension.

See also:

createVariable

scipy.io.netcdf_file.createVariable`netcdf_file.createVariable` (*self*, *name*, *type*, *dimensions*)

Create an empty variable for the `netcdf_file` object, specifying its data type and the dimensions it uses.

Parameters

name [str] Name of the new variable.
type [dtype or str] Data type of the variable.
dimensions [sequence of str] List of the dimension names used by the variable, in the desired order.

Returns

variable [netcdf_variable] The newly created `netcdf_variable` object. This object has also been added to the `netcdf_file` object as well.

See also:

`createDimension`

Notes

Any dimensions to be used by the variable should already exist in the NetCDF data structure or should be created by `createDimension` prior to creating the NetCDF variable.

scipy.io.netcdf_file.flush`netcdf_file.flush` (*self*)

Perform a sync-to-disk flush if the `netcdf_file` object is in write mode.

See also:

`sync`

Identical function

scipy.io.netcdf_file.sync`netcdf_file.sync` (*self*)

Perform a sync-to-disk flush if the `netcdf_file` object is in write mode.

See also:

`sync`

Identical function

scipy.io.netcdf_variable

class `scipy.io.netcdf_variable` (*data*, *typecode*, *size*, *shape*, *dimensions*, *attributes=None*, *maskand-scale=False*)

A data object for netcdf files.

`netcdf_variable` objects are constructed by calling the method `netcdf_file.createVariable` on the `netcdf_file` object. `netcdf_variable` objects behave much like array objects defined in numpy, except that their data resides in a file. Data is read by indexing and written by assigning to an indexed subset; the entire array can be accessed by the index `[:]` or (for scalars) by using the methods `getValue` and `assignValue`. `netcdf_variable` objects also have attribute `shape` with the same meaning as for arrays, but the

shape cannot be modified. There is another read-only attribute *dimensions*, whose value is the tuple of dimension names.

All other attributes correspond to variable attributes defined in the NetCDF file. Variable attributes are created by assigning to an attribute of the *netcdf_variable* object.

Parameters

data	[array_like] The data array that holds the values for the variable. Typically, this is initialized as empty, but with the proper shape.
typecode	[dtype character code] Desired data-type for the data array.
size	[int] Desired element size for the data array.
shape	[sequence of ints] The shape of the array. This should match the lengths of the variable's dimensions.
dimensions	[sequence of strings] The names of the dimensions used by the variable. Must be in the same order of the dimension lengths given by <i>shape</i> .
attributes	[dict, optional] Attribute values (any type) keyed by string names. These attributes become attributes for the <i>netcdf_variable</i> object.
maskandscale	[bool, optional] Whether to automatically scale and/or mask data based on attributes. Default is False.

See also:

isrec, shape

Attributes

dimensions	[list of str] List of names of dimensions used by the variable object.
isrec, shape	Properties

Methods

<i>assignValue</i> (self, value)	Assign a scalar value to a <i>netcdf_variable</i> of length one.
<i>getValue</i> (self)	Retrieve a scalar value from a <i>netcdf_variable</i> of length one.
<i>itemsizes</i> (self)	Return the itemsize of the variable.
<i>typecode</i> (self)	Return the typecode of the variable.

scipy.io.netcdf_variable.assignValue

netcdf_variable.**assignValue** (*self*, *value*)

Assign a scalar value to a *netcdf_variable* of length one.

Parameters

value	[scalar] Scalar value (of compatible type) to assign to a length-one netcdf variable. This value will be written to file.
--------------	---

Raises

ValueError

If the input is not a scalar, or if the destination is not a length-one netcdf variable.

scipy.io.netcdf_variable.getValue

`netcdf_variable.getValue(self)`

Retrieve a scalar value from a *netcdf_variable* of length one.

Raises

ValueError

If the netcdf variable is an array of length greater than one, this exception will be raised.

scipy.io.netcdf_variable.itemsize

`netcdf_variable.itemsize(self)`

Return the itemsize of the variable.

Returns

itemsize [int] The element size of the variable (e.g., 8 for float64).

scipy.io.netcdf_variable.typecode

`netcdf_variable.typecode(self)`

Return the typecode of the variable.

Returns

typecode [char] The character typecode of the variable (e.g., 'i' for int).

<code>__getitem__</code>	
--------------------------	--

6.9.6 Harwell-Boeing files

<code>hb_read(path_or_open_file)</code>	Read HB-format file.
<code>hb_write(path_or_open_file, m[, hb_info])</code>	Write HB-format file.

scipy.io.hb_read

`scipy.io.hb_read(path_or_open_file)`

Read HB-format file.

Parameters

path_or_open_file

[path-like or file-like] If a file-like object, it is used as-is. Otherwise, it is opened before reading.

Returns

data [scipy.sparse.csc_matrix instance] The data read from the HB file as a sparse matrix.

Notes

At the moment not the full Harwell-Boeing format is supported. Supported features are:

- assembled, non-symmetric, real matrices
- integer for pointer/indices
- exponential format for float values, and int format

Examples

We can read and write a harwell-boeing format file:

```
>>> from scipy.io.harwell_boeing import hb_read, hb_write
>>> from scipy.sparse import csr_matrix, eye
>>> data = csr_matrix(eye(3)) # create a sparse matrix
>>> hb_write("data.hb", data) # write a hb file
>>> print(hb_read("data.hb")) # read a hb file
(0, 0)    1.0
(1, 1)    1.0
(2, 2)    1.0
```

scipy.io.hb_write

`scipy.io.hb_write` (*path_or_open_file*, *m*, *hb_info=None*)

Write HB-format file.

Parameters

path_or_open_file

[path-like or file-like] If a file-like object, it is used as-is. Otherwise, it is opened before writing.

m [sparse-matrix] the sparse matrix to write

hb_info [HBInfo] contains the meta-data for write

Returns

None

Notes

At the moment not the full Harwell-Boeing format is supported. Supported features are:

- assembled, non-symmetric, real matrices
- integer for pointer/indices
- exponential format for float values, and int format

Examples

We can read and write a harwell-boeing format file:

```
>>> from scipy.io.harwell_boeing import hb_read, hb_write
>>> from scipy.sparse import csr_matrix, eye
>>> data = csr_matrix(eye(3)) # create a sparse matrix
>>> hb_write("data.hb", data) # write a hb file
>>> print(hb_read("data.hb")) # read a hb file
(0, 0) 1.0
(1, 1) 1.0
(2, 2) 1.0
```

6.9.7 Wav sound files (`scipy.io.wavfile`)

<code>read(filename[, mmap])</code>	Open a WAV file.
<code>write(filename, rate, data)</code>	Write a NumPy array as a WAV file.
<code>WavFileWarning</code>	

`scipy.io.wavfile.read`

`scipy.io.wavfile.read(filename, mmap=False)`

Open a WAV file.

Return the sample rate (in samples/sec) and data from an LPCM WAV file.

Parameters

- filename** [string or open file handle] Input WAV file.
- mmap** [bool, optional] Whether to read data as memory-mapped (default: False). Not compatible with some bit depths; see Notes. Only to be used on real files. New in version 0.12.0.

Returns

- rate** [int] Sample rate of WAV file.
- data** [numpy array] Data read from WAV file. Data-type is determined from the file; see Notes. Data is 1-D for 1-channel WAV, or 2-D of shape (Nsamples, Nchannels) otherwise. If a file-like input without a C-like file descriptor (e.g., `io.BytesIO`) is passed, this will not be writeable.

Notes

Common data types: [1]

WAV format	Min	Max	NumPy dtype
32-bit floating-point	-1.0	+1.0	float32
32-bit integer PCM	-2147483648	+2147483647	int32
24-bit integer PCM	-2147483648	+2147483392	int32
16-bit integer PCM	-32768	+32767	int16
8-bit integer PCM	0	255	uint8

WAV files can specify arbitrary bit depth, and this function supports reading any integer PCM depth from 1 to 64 bits. Data is returned in the smallest compatible numpy int type, in left-justified format. 8-bit and lower is unsigned, while 9-bit and higher is signed.

For example, 24-bit data will be stored as int32, with the MSB of the 24-bit data stored at the MSB of the int32, and typically the least significant byte is 0x00. (However, if a file actually contains data past its specified bit depth, those bits will be read and output, too. [2])

This bit justification and sign matches WAV's native internal format, which allows memory mapping of WAV files that use 1, 2, 4, or 8 bytes per sample (so 24-bit files cannot be memory-mapped, but 32-bit can).

IEEE float PCM in 32- or 64-bit format is supported, with or without mmap. Values exceeding [-1, +1] are not clipped.

Non-linear PCM (mu-law, A-law) is not supported.

References

[1], [2]

Examples

```
>>> from os.path import dirname, join as pjoin
>>> from scipy.io import wavfile
>>> import scipy.io
```

Get the filename for an example .wav file from the tests/data directory.


```
>>> data_dir = pjoin(dirname(scipy.io.__file__), 'tests', 'data')
>>> wav_fname = pjoin(data_dir, 'test-44100Hz-2ch-32bit-float-be.wav')
```

Load the .wav file contents.

```
>>> samplerate, data = wavfile.read(wav_fname)
>>> print(f"number of channels = {data.shape[1]}")
number of channels = 2
>>> length = data.shape[0] / samplerate
>>> print(f"length = {length}s")
length = 0.01s
```

Plot the waveform.

```
>>> import matplotlib.pyplot as plt
>>> import numpy as np
>>> time = np.linspace(0., length, data.shape[0])
>>> plt.plot(time, data[:, 0], label="Left channel")
>>> plt.plot(time, data[:, 1], label="Right channel")
>>> plt.legend()
>>> plt.xlabel("Time [s]")
>>> plt.ylabel("Amplitude")
>>> plt.show()
```



scipy.io.wavfile.write

`scipy.io.wavfile.write` (*filename*, *rate*, *data*)

Write a NumPy array as a WAV file.

Parameters

- filename** [string or open file handle] Output wav file.
- rate** [int] The sample rate (in samples/sec).
- data** [ndarray] A 1-D or 2-D NumPy array of either integer or float data-type.

Notes

- Writes a simple uncompressed WAV file.
- To write multiple-channels, use a 2-D array of shape (Nsamples, Nchannels).
- The bits-per-sample and PCM/float will be determined by the data-type.

Common data types: [1]

WAV format	Min	Max	NumPy dtype
32-bit floating-point	-1.0	+1.0	float32
32-bit PCM	-2147483648	+2147483647	int32
16-bit PCM	-32768	+32767	int16
8-bit PCM	0	255	uint8

Note that 8-bit PCM is unsigned.

References

[1]

Examples

Create a 100Hz sine wave, sampled at 44100Hz. Write to 16-bit PCM, Mono.

```
>>> from scipy.io.wavfile import write
>>> samplerate = 44100; fs = 100
>>> t = np.linspace(0., 1., samplerate)
>>> amplitude = np.iinfo(np.int16).max
>>> data = amplitude * np.sin(2. * np.pi * fs * t)
>>> write("example.wav", samplerate, data.astype(np.int16))
```

scipy.io.wavfile.WavFileWarning

exception `scipy.io.wavfile.WavFileWarning`

`with_traceback()`

Exception.`with_traceback(tb)` – set `self.__traceback__` to `tb` and return `self`.

6.9.8 Arff files (`scipy.io.arff`)

<code>loadarff(f)</code>	Read an arff file.
<code>MetaData(rel, attr)</code>	Small container to keep useful information on a ARFF dataset.
<code>ArffError</code>	
<code>ParseArffError</code>	

scipy.io.arff.loadarff

`scipy.io.arff.loadarff(f)`

Read an arff file.

The data is returned as a record array, which can be accessed much like a dictionary of NumPy arrays. For example, if one of the attributes is called 'pressure', then its first 10 data points can be accessed from the `data` record array like so: `data['pressure'][0:10]`

Parameters

f [file-like or str] File-like object to read from, or filename to open.

Returns

data [record array] The data of the arff file, accessible by attribute names.

meta [`MetaData`] Contains information about the arff file such as name and type of attributes, the relation (name of the dataset), etc.

Raises

ParseArffError

This is raised if the given file is not ARFF-formatted.

NotImplementedError

The ARFF file has an attribute which is not supported yet.

Notes

This function should be able to read most arff files. Not implemented functionality include:

- date type attributes
- string type attributes

It can read files with numeric and nominal attributes. It cannot read files with sparse data ({} in the file). However, this function can read files with missing data (? in the file), representing the data points as NaNs.

Examples

```
>>> from scipy.io import arff
>>> from io import StringIO
>>> content = """
... @relation foo
... @attribute width  numeric
... @attribute height numeric
... @attribute color  {red,green,blue,yellow,black}
... @data
... 5.0,3.25,blue
... 4.5,3.75,green
... 3.0,4.00,red
... """
>>> f = StringIO(content)
>>> data, meta = arff.loadarff(f)
>>> data
array([(5.0, 3.25, 'blue'), (4.5, 3.75, 'green'), (3.0, 4.0, 'red')],
      dtype=[('width', '<f8'), ('height', '<f8'), ('color', '|S6')])
>>> meta
Dataset: foo
  width's type is numeric
  height's type is numeric
  color's type is nominal, range is ('red', 'green', 'blue', 'yellow',
  ↪ 'black')
```

scipy.io.arff.MetaData

class `scipy.io.arff.MetaData` (*rel*, *attr*)

Small container to keep useful information on a ARFF dataset.

Knows about attributes names and types.

Notes

Also maintains the list of attributes in order, i.e., doing for `i` in `meta`, where `meta` is an instance of `MetaData`, will return the different attribute names in the order they were defined.

Examples

```
data, meta = loadarff('iris.arff')
# This will print the attributes names of the iris.arff dataset
for i in meta:
    print(i)
# This works too
meta.names()
# Getting attribute type
types = meta.types()
```

Methods

<code>names(self)</code>	Return the list of attribute names.
<code>types(self)</code>	Return the list of attribute types.

`scipy.io.arff.MetaData.names`

`MetaData.names` (*self*)
Return the list of attribute names.

Returns

attrnames [list of str] The attribute names.

`scipy.io.arff.MetaData.types`

`MetaData.types` (*self*)
Return the list of attribute types.

Returns

attr_types [list of str] The attribute types.

`scipy.io.arff.ArffError`

exception `scipy.io.arff.ArffError`

errno
POSIX exception code

filename
exception filename

filename2
second exception filename

strerror
exception strerror

with_traceback()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

scipy.io.arff.ParseArffError

exception `scipy.io.arff.ParseArffError`

errno

POSIX exception code

filename

exception filename

filename2

second exception filename

strerror

exception strerror

with_traceback()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

6.10 Linear algebra (`scipy.linalg`)

Linear algebra functions.

See also:

`numpy.linalg` for more linear algebra functions. Note that although `scipy.linalg` imports most of them, identically named functions from `scipy.linalg` may offer more or slightly differing functionality.

6.10.1 Basics

<code>inv(a[, overwrite_a, check_finite])</code>	Compute the inverse of a matrix.
<code>solve(a, b[, sym_pos, lower, overwrite_a, ...])</code>	Solves the linear equation set $a * x = b$ for the unknown x for square a matrix.
<code>solve_banded(l_and_u, ab, b[, overwrite_ab, ...])</code>	Solve the equation $a x = b$ for x , assuming a is banded matrix.
<code>solveh_banded(ab, b[, overwrite_ab, ...])</code>	Solve equation $a x = b$.
<code>solve_circulant(c, b[, singular, tol, ...])</code>	Solve $C x = b$ for x , where C is a circulant matrix.
<code>solve_triangular(a, b[, trans, lower, ...])</code>	Solve the equation $a x = b$ for x , assuming a is a triangular matrix.
<code>solve_toeplitz(c_or_cr, b[, check_finite])</code>	Solve a Toeplitz system using Levinson Recursion
<code>matmul_toeplitz(c_or_cr, x[, check_finite, ...])</code>	Efficient Toeplitz Matrix-Matrix Multiplication using FFT
<code>det(a[, overwrite_a, check_finite])</code>	Compute the determinant of a matrix
<code>norm(a[, ord, axis, keepdims, check_finite])</code>	Matrix or vector norm.
<code>lstsq(a, b[, cond, overwrite_a, ...])</code>	Compute least-squares solution to equation $Ax = b$.
<code>pinv(a[, cond, rcond, return_rank, check_finite])</code>	Compute the (Moore-Penrose) pseudo-inverse of a matrix.

continues on next page

Table 90 – continued from previous page

<code>pinv2(a[, cond, rcond, return_rank, ...])</code>	Compute the (Moore-Penrose) pseudo-inverse of a matrix.
<code>pinvh(a[, cond, rcond, lower, return_rank, ...])</code>	Compute the (Moore-Penrose) pseudo-inverse of a Hermitian matrix.
<code>kron(a, b)</code>	Kronecker product.
<code>khatri_rao(a, b)</code>	Khatri-rao product
<code>tril(m[, k])</code>	Make a copy of a matrix with elements above the kth diagonal zeroed.
<code>triu(m[, k])</code>	Make a copy of a matrix with elements below the kth diagonal zeroed.
<code>orthogonal_procrustes(A, B[, check_finite])</code>	Compute the matrix solution of the orthogonal Procrustes problem.
<code>matrix_balance(A[, permute, scale, ...])</code>	Compute a diagonal similarity transformation for row/column balancing.
<code>subspace_angles(A, B)</code>	Compute the subspace angles between two matrices.
<code>LinAlgError</code>	Generic Python-exception-derived object raised by linalg functions.
<code>LinAlgWarning</code>	The warning emitted when a linear algebra related operation is close to fail conditions of the algorithm or loss of accuracy is expected.

scipy.linalg.inv

`scipy.linalg.inv(a, overwrite_a=False, check_finite=True)`

Compute the inverse of a matrix.

Parameters

a [array_like] Square matrix to be inverted.

overwrite_a [bool, optional] Discard data in *a* (may improve performance). Default is False.

check_finite [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

ainv [ndarray] Inverse of the matrix *a*.

Raises

LinAlgError
If *a* is singular.

ValueError
If *a* is not square, or not 2D.

Examples

```

>>> from scipy import linalg
>>> a = np.array([[1., 2.], [3., 4.]])
>>> linalg.inv(a)
array([[ -2. ,  1. ],
       [ 1.5, -0.5]])
>>> np.dot(a, linalg.inv(a))
array([[ 1.,  0.],
       [ 0.,  1.]])
    
```

scipy.linalg.solve

`scipy.linalg.solve`(*a*, *b*, *sym_pos=False*, *lower=False*, *overwrite_a=False*, *overwrite_b=False*, *debug=None*, *check_finite=True*, *assume_a='gen'*, *transposed=False*)

Solves the linear equation set $a * x = b$ for the unknown x for square a matrix.

If the data matrix is known to be a particular type then supplying the corresponding string to `assume_a` key chooses the dedicated solver. The available options are

generic matrix	'gen'
symmetric	'sym'
hermitian	'her'
positive definite	'pos'

If omitted, 'gen' is the default structure.

The datatype of the arrays define which solver is called regardless of the values. In other words, even when the complex array entries have precisely zero imaginary parts, the complex solver will be called based on the data type of the array.

Parameters

- a** [(N, N) array_like] Square input data
- b** [(N, NRHS) array_like] Input data for the right hand side.
- sym_pos** [bool, optional] Assume *a* is symmetric and positive definite. This key is deprecated and `assume_a = 'pos'` keyword is recommended instead. The functionality is the same. It will be removed in the future.
- lower** [bool, optional] If True, only the data contained in the lower triangle of *a*. Default is to use upper triangle. (ignored for 'gen')
- overwrite_a** [bool, optional] Allow overwriting data in *a* (may enhance performance). Default is False.
- overwrite_b** [bool, optional] Allow overwriting data in *b* (may enhance performance). Default is False.
- check_finite** [bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.
- assume_a** [str, optional] Valid entries are explained above.
- transposed: bool, optional**
If True, $a^T x = b$ for real matrices, raises *NotImplementedError* for complex matrices (only for True).

Returns

x [(N, NRHS) ndarray] The solution array.

Raises

- ValueError**
If size mismatches detected or input a is not square.
- LinAlgError**
If the matrix is singular.
- LinAlgWarning**
If an ill-conditioned input a is detected.
- NotImplementedError**
If transposed is True and input a is a complex matrix.

Notes

If the input *b* matrix is a 1-D array with *N* elements, when supplied together with an *N*×*N* input *a*, it is assumed as a valid column vector despite the apparent size mismatch. This is compatible with the `numpy.dot()` behavior and the returned result is still 1-D array.

The generic, symmetric, Hermitian and positive definite solutions are obtained via calling `?GESV`, `?SYSV`, `?HESV`, and `?POSV` routines of LAPACK respectively.

Examples

Given *a* and *b*, solve for *x*:

```
>>> a = np.array([[3, 2, 0], [1, -1, 0], [0, 5, 1]])
>>> b = np.array([2, 4, -1])
>>> from scipy import linalg
>>> x = linalg.solve(a, b)
>>> x
array([ 2., -2.,  9.])
>>> np.dot(a, x) == b
array([ True,  True,  True], dtype=bool)
```

scipy.linalg.solve_banded

`scipy.linalg.solve_banded(l_and_u, ab, b, overwrite_ab=False, overwrite_b=False, debug=None, check_finite=True)`

Solve the equation $a x = b$ for *x*, assuming *a* is banded matrix.

The matrix *a* is stored in *ab* using the matrix diagonal ordered form:

```
ab[u + i - j, j] == a[i, j]
```

Example of *ab* (shape of *a* is (6,6), *u*=1, *l*=2):

```
*      a01  a12  a23  a34  a45
a00  a11  a22  a33  a44  a55
a10  a21  a32  a43  a54  *
a20  a31  a42  a53  *   *
```

Parameters

(l, u) [(integer, integer)] Number of non-zero lower and upper diagonals
ab [(l + u + 1, M) array_like] Banded matrix
b [(M,) or (M, K) array_like] Right-hand side
overwrite_ab [bool, optional] Discard data in *ab* (may enhance performance)
overwrite_b [bool, optional] Discard data in *b* (may enhance performance)
check_finite [bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

x [(M,) or (M, K) ndarray] The solution to the system $a x = b$. Returned shape depends on the shape of *b*.

Examples

Solve the banded system $a x = b$, where:

```
a = [5  2 -1  0  0]
     [1  4  2 -1  0]
     [0  1  3  2 -1]
     [0  0  1  2  2]
     [0  0  0  1  1]
b = [0]
     [1]
     [2]
     [2]
     [3]
```

There is one nonzero diagonal below the main diagonal ($l = 1$), and two above ($u = 2$). The diagonal banded form of the matrix is:

```
ab = [* * -1 -1 -1]
      [* 2 2 2 2]
      [5 4 3 2 1]
      [1 1 1 1 *]
```

```
>>> from scipy.linalg import solve_banded
>>> ab = np.array([[0, 0, -1, -1, -1],
...               [0, 2, 2, 2, 2],
...               [5, 4, 3, 2, 1],
...               [1, 1, 1, 1, 0]])
>>> b = np.array([0, 1, 2, 2, 3])
>>> x = solve_banded((1, 2), ab, b)
>>> x
array([-2.37288136,  3.93220339, -4.          ,  4.3559322 , -1.3559322 ])
```

scipy.linalg.solveh_banded

`scipy.linalg.solveh_banded`(*ab*, *b*, *overwrite_ab=False*, *overwrite_b=False*, *lower=False*, *check_finite=True*)

Solve equation $a x = b$. *a* is Hermitian positive-definite banded matrix.

The matrix *a* is stored in *ab* either in lower diagonal or upper diagonal ordered form:

$ab[u + i - j, j] == a[i, j]$ (if upper form; $i \leq j$) $ab[i - j, j] == a[i, j]$ (if lower form; $i \geq j$)

Example of *ab* (shape of *a* is (6, 6), $u=2$):

```
upper form:
*   *   a02 a13 a24 a35
*   a01 a12 a23 a34 a45
a00 a11 a22 a33 a44 a55

lower form:
a00 a11 a22 a33 a44 a55
a10 a21 a32 a43 a54 *
a20 a31 a42 a53 *   *
```

Cells marked with * are not used.

Parameters

- ab** [(*u* + 1, *M*) array_like] Banded matrix
- b** [(*M*,) or (*M*, *K*) array_like] Right-hand side
- overwrite_ab** [bool, optional] Discard data in *ab* (may enhance performance)
- overwrite_b** [bool, optional] Discard data in *b* (may enhance performance)
- lower** [bool, optional] Is the matrix in the lower form. (Default is upper form)
- check_finite** [bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

- x** [(*M*,) or (*M*, *K*) ndarray] The solution to the system $a x = b$. Shape of return matches shape of *b*.

Examples

Solve the banded system $A x = b$, where:

```
A = [ 4  2 -1  0  0  0]
     [ 2  5  2 -1  0  0]
     [-1  2  6  2 -1  0]
     [ 0 -1  2  7  2 -1]
     [ 0  0 -1  2  8  2]
     [ 0  0  0 -1  2  9]

b = [1]
     [2]
     [2]
     [3]
     [3]
     [3]
```

```
>>> from scipy.linalg import solveh_banded
```

ab contains the main diagonal and the nonzero diagonals below the main diagonal. That is, we use the lower form:

```

>>> ab = np.array([[ 4,  5,  6,  7,  8,  9],
...                [ 2,  2,  2,  2,  2,  0],
...                [-1, -1, -1, -1,  0,  0]])
>>> b = np.array([1, 2, 2, 3, 3, 3])
>>> x = solveh_banded(ab, b, lower=True)
>>> x
array([ 0.03431373,  0.45938375,  0.05602241,  0.47759104,  0.17577031,
        0.34733894])
    
```

Solve the Hermitian banded system $Hx = b$, where:

```

      [ 8  2-1j  0  0 ]
H = [2+1j  5  1j  0 ]   b = [ 1 ]
      [ 0  -1j  9 -2-1j]   [1+1j]
      [ 0  0  -2+1j  6 ]   [1-2j]
                          [ 0 ]
    
```

In this example, we put the upper diagonals in the array *hb*:

```

>>> hb = np.array([[0, 2-1j, 1j, -2-1j],
...                [8,  5,  9,  6 ]])
>>> b = np.array([1, 1+1j, 1-2j, 0])
>>> x = solveh_banded(hb, b)
>>> x
array([ 0.07318536-0.02939412j,  0.11877624+0.17696461j,
        0.10077984-0.23035393j, -0.00479904-0.09358128j])
    
```

scipy.linalg.solve_circulant

`scipy.linalg.solve_circulant` (*c*, *b*, *singular*='raise', *tol*=None, *caxis*=-1, *baxis*=0, *outaxis*=0)
 Solve $Cx = b$ for x , where C is a circulant matrix.

C is the circulant matrix associated with the vector c .

The system is solved by doing division in Fourier space. The calculation is:

```
x = ifft(fft(b) / fft(c))
```

where *fft* and *ifft* are the fast Fourier transform and its inverse, respectively. For a large vector c , this is *much* faster than solving the system with the full circulant matrix.

Parameters

- c** [array_like] The coefficients of the circulant matrix.
- b** [array_like] Right-hand side matrix in $ax = b$.
- singular** [str, optional] This argument controls how a near singular circulant matrix is handled. If *singular* is “raise” and the circulant matrix is near singular, a `LinAlgError` is raised. If *singular* is “lstsq”, the least squares solution is returned. Default is “raise”.
- tol** [float, optional] If any eigenvalue of the circulant matrix has an absolute value that is less than or equal to *tol*, the matrix is considered to be near singular. If not given, *tol* is set to:

```
tol = abs_eigs.max() * abs_eigs.size * np.finfo(np.
↪float64).eps
```

- where *abs_eigs* is the array of absolute values of the eigenvalues of the circulant matrix.
- caxis** [int] When c has dimension greater than 1, it is viewed as a collection of circulant vectors. In this case, *caxis* is the axis of c that holds the vectors of circulant coefficients.

- basis** [int] When b has dimension greater than 1, it is viewed as a collection of vectors. In this case, *basis* is the axis of b that holds the right-hand side vectors.
- outaxis** [int] When c or b are multidimensional, the value returned by `solve_circulant` is multidimensional. In this case, *outaxis* is the axis of the result that holds the solution vectors.

Returns

- x** [ndarray] Solution to the system $Cx = b$.

Raises**LinAlgError**

If the circulant matrix associated with c is near singular.

See also:*circulant*

circulant matrix

Notes

For a 1-D vector c with length m , and an array b with shape (m, \dots) ,

```
solve_circulant(c, b)
```

returns the same result as

```
solve(circulant(c), b)
```

where `solve` and `circulant` are from `scipy.linalg`.

New in version 0.16.0.

Examples

```
>>> from scipy.linalg import solve_circulant, solve, circulant, lstsq
```

```
>>> c = np.array([2, 2, 4])
>>> b = np.array([1, 2, 3])
>>> solve_circulant(c, b)
array([ 0.75, -0.25,  0.25])
```

Compare that result to solving the system with `scipy.linalg.solve`:

```
>>> solve(circulant(c), b)
array([ 0.75, -0.25,  0.25])
```

A singular example:

```
>>> c = np.array([1, 1, 0, 0])
>>> b = np.array([1, 2, 3, 4])
```

Calling `solve_circulant(c, b)` will raise a `LinAlgError`. For the least square solution, use the option `singular='lstsq'`:

```
>>> solve_circulant(c, b, singular='lstsq')
array([ 0.25,  1.25,  2.25,  1.25])
```

Compare to `scipy.linalg.lstsq`:

```
>>> x, resid, rnk, s = lstsq(circulant(c), b)
>>> x
array([ 0.25,  1.25,  2.25,  1.25])
```

A broadcasting example:

Suppose we have the vectors of two circulant matrices stored in an array with shape (2, 5), and three b vectors stored in an array with shape (3, 5). For example,

```
>>> c = np.array([[1.5, 2, 3, 0, 0], [1, 1, 4, 3, 2]])
>>> b = np.arange(15).reshape(-1, 5)
```

We want to solve all combinations of circulant matrices and b vectors, with the result stored in an array with shape (2, 3, 5). When we disregard the axes of c and b that hold the vectors of coefficients, the shapes of the collections are (2,) and (3,), respectively, which are not compatible for broadcasting. To have a broadcast result with shape (2, 3), we add a trivial dimension to c : `c[:, np.newaxis, :]` has shape (2, 1, 5). The last dimension holds the coefficients of the circulant matrices, so when we call `solve_circulant`, we can use the default `caxis=-1`. The coefficients of the b vectors are in the last dimension of the array b , so we use `baxis=-1`. If we use the default `outaxis`, the result will have shape (5, 2, 3), so we'll use `outaxis=-1` to put the solution vectors in the last dimension.

```
>>> x = solve_circulant(c[:, np.newaxis, :], b, baxis=-1, outaxis=-1)
>>> x.shape
(2, 3, 5)
>>> np.set_printoptions(precision=3) # For compact output of numbers.
>>> x
array([[[-0.118,  0.22 ,  1.277, -0.142,  0.302],
        [ 0.651,  0.989,  2.046,  0.627,  1.072],
        [ 1.42 ,  1.758,  2.816,  1.396,  1.841]],
       [[ 0.401,  0.304,  0.694, -0.867,  0.377],
        [ 0.856,  0.758,  1.149, -0.412,  0.831],
        [ 1.31 ,  1.213,  1.603,  0.042,  1.286]]])
```

Check by solving one pair of c and b vectors (cf. `x[1, 1, :]`):

```
>>> solve_circulant(c[1], b[1, :])
array([ 0.856,  0.758,  1.149, -0.412,  0.831])
```

`scipy.linalg.solve_triangular`

`scipy.linalg.solve_triangular`(a , b , $trans=0$, $lower=False$, $unit_diagonal=False$, $overwrite_b=False$, $debug=None$, $check_finite=True$)

Solve the equation $ax = b$ for x , assuming a is a triangular matrix.

Parameters

- a** [(M, M) array_like] A triangular matrix
- b** [(M,) or (M, N) array_like] Right-hand side matrix in $ax = b$
- lower** [bool, optional] Use only data contained in the lower triangle of a . Default is to use upper triangle.
- trans** [{0, 1, 2, 'N', 'T', 'C'}, optional] Type of system to solve:

trans	system
0 or 'N'	$a x = b$
1 or 'T'	$a^T x = b$
2 or 'C'	$a^H x = b$

unit_diagonal

[bool, optional] If True, diagonal elements of a are assumed to be 1 and will not be referenced.

overwrite_b

[bool, optional] Allow overwriting data in b (may enhance performance)

check_finite

[bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

x [(M,) or (M, N) ndarray] Solution to the system $a x = b$. Shape of return matches b .

Raises**LinAlgError**

If a is singular

Notes

New in version 0.9.0.

Examples

Solve the lower triangular system $a x = b$, where:

```
a =  $\begin{bmatrix} 3 & 0 & 0 & 0 \\ 2 & 1 & 0 & 0 \\ 1 & 0 & 1 & 0 \\ 1 & 1 & 1 & 1 \end{bmatrix}$     b =  $\begin{bmatrix} 4 \\ 2 \\ 4 \\ 2 \end{bmatrix}$ 
```

```
>>> from scipy.linalg import solve_triangular
>>> a = np.array([[3, 0, 0, 0], [2, 1, 0, 0], [1, 0, 1, 0], [1, 1, 1, 1]])
>>> b = np.array([4, 2, 4, 2])
>>> x = solve_triangular(a, b, lower=True)
>>> x
array([ 1.33333333, -0.66666667,  2.66666667, -1.33333333])
>>> a.dot(x) # Check the result
array([ 4.,  2.,  4.,  2.]
```

scipy.linalg.solve_toeplitz

`scipy.linalg.solve_toeplitz(c_or_cr, b, check_finite=True)`

Solve a Toeplitz system using Levinson Recursion

The Toeplitz matrix has constant diagonals, with c as its first column and r as its first row. If r is not given, $r = \text{conjugate}(c)$ is assumed.

Parameters

- c_or_cr** [array_like or tuple of (array_like, array_like)] The vector c , or a tuple of arrays (c, r) . Whatever the actual shape of c , it will be converted to a 1-D array. If not supplied, $r = \text{conjugate}(c)$ is assumed; in this case, if $c[0]$ is real, the Toeplitz matrix is Hermitian. $r[0]$ is ignored; the first row of the Toeplitz matrix is $[c[0], r[1:]]$. Whatever the actual shape of r , it will be converted to a 1-D array.
- b** [(M,) or (M, K) array_like] Right-hand side in $T x = b$.
- check_finite** [bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (result entirely NaNs) if the inputs do contain infinities or NaNs.

Returns

- x** [(M,) or (M, K) ndarray] The solution to the system $T x = b$. Shape of return matches shape of b .

See also:

`toeplitz`

Toeplitz matrix

Notes

The solution is computed using Levinson-Durbin recursion, which is faster than generic least-squares methods, but can be less numerically stable.

Examples

Solve the Toeplitz system $T x = b$, where:

```
T = [ 1 -1 -2 -3]
     [ 3  1 -1 -2]
     [ 6  3  1 -1]
     [10  6  3  1]
b = [1]
     [2]
     [2]
     [5]
```

To specify the Toeplitz matrix, only the first column and the first row are needed.

```
>>> c = np.array([1, 3, 6, 10]) # First column of T
>>> r = np.array([1, -1, -2, -3]) # First row of T
>>> b = np.array([1, 2, 2, 5])
```

```
>>> from scipy.linalg import solve_toeplitz, toeplitz
>>> x = solve_toeplitz((c, r), b)
>>> x
array([ 1.66666667, -1.          , -2.66666667,  2.33333333])
```

Check the result by creating the full Toeplitz matrix and multiplying it by x . We should get b .

```
>>> T = toeplitz(c, r)
>>> T.dot(x)
array([ 1.,  2.,  2.,  5.]
```

scipy.linalg.matmul_toeplitz

`scipy.linalg.matmul_toeplitz(c_or_cr, x, check_finite=False, workers=None)`

Efficient Toeplitz Matrix-Matrix Multiplication using FFT

This function returns the matrix multiplication between a Toeplitz matrix and a dense matrix.

The Toeplitz matrix has constant diagonals, with c as its first column and r as its first row. If r is not given, $r == \text{conjugate}(c)$ is assumed.

Parameters

- c_or_cr** [array_like or tuple of (array_like, array_like)] The vector c , or a tuple of arrays (c , r). Whatever the actual shape of c , it will be converted to a 1-D array. If not supplied, $r = \text{conjugate}(c)$ is assumed; in this case, if $c[0]$ is real, the Toeplitz matrix is Hermitian. $r[0]$ is ignored; the first row of the Toeplitz matrix is $[c[0], r[1:]]$. Whatever the actual shape of r , it will be converted to a 1-D array.
- x** [(M,) or (M, K) array_like] Matrix with which to multiply.
- check_finite** [bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (result entirely NaNs) if the inputs do contain infinities or NaNs.
- workers** [int, optional] To pass to `scipy.fft.fft` and `scipy.fft.ifft`. Maximum number of workers to use for parallel computation. If negative, the value wraps around from `os.cpu_count()`. See `scipy.fft.fft` for more details.

Returns

- T @ x** [(M,) or (M, K) ndarray] The result of the matrix multiplication $T @ x$. Shape of return matches shape of x .

See also:

[`toeplitz`](#)

Toeplitz matrix

[`solve_toeplitz`](#)

Solve a Toeplitz system using Levinson Recursion

Notes

The Toeplitz matrix is embedded in a circulant matrix and the FFT is used to efficiently calculate the matrix-matrix product.

Because the computation is based on the FFT, integer inputs will result in floating point outputs. This is unlike NumPy's `matmul`, which preserves the data type of the input.

This is partly based on the implementation that can be found in [1], licensed under the MIT license. More information about the method can be found in reference [2]. References [3] and [4] have more reference implementations in Python.

New in version 1.6.0.

References

[1], [2], [3], [4]

Examples

Multiply the Toeplitz matrix T with matrix x :

```
T = [ 1 -1 -2 -3]      [1 10]
     [ 3  1 -1 -2]      x = [2 11]
     [ 6  3  1 -1]      [2 11]
     [10  6  3  1]      [5 19]
```

To specify the Toeplitz matrix, only the first column and the first row are needed.

```
>>> c = np.array([1, 3, 6, 10])    # First column of T
>>> r = np.array([1, -1, -2, -3])  # First row of T
>>> x = np.array([[1, 10], [2, 11], [2, 11], [5, 19]])
```

```
>>> from scipy.linalg import toeplitz, matmul_toeplitz
>>> matmul_toeplitz((c, r), x)
array([[ -20.,  -80.],
       [  -7.,   -8.],
       [   9.,   85.],
       [  33.,  218.]])
```

Check the result by creating the full Toeplitz matrix and multiplying it by x .

```
>>> toeplitz(c, r) @ x
array([[ -20,  -80],
       [  -7,   -8],
       [   9,   85],
       [  33,  218]])
```

The full matrix is never formed explicitly, so this routine is suitable for very large Toeplitz matrices.

```
>>> n = 1000000
>>> matmul_toeplitz([1] + [0]*(n-1), np.ones(n))
array([1., 1., 1., ..., 1., 1., 1.]])
```

scipy.linalg.det

`scipy.linalg.det` (*a*, *overwrite_a=False*, *check_finite=True*)

Compute the determinant of a matrix

The determinant of a square matrix is a value derived arithmetically from the coefficients of the matrix.

The determinant for a 3x3 matrix, for example, is computed as follows:

```

a   b   c
d   e   f = A
g   h   i

det(A) = a*e*i + b*f*g + c*d*h - c*e*g - b*d*i - a*f*h

```

Parameters

- a** [(M, M) array_like] A square matrix.
- overwrite_a** [bool, optional] Allow overwriting data in a (may enhance performance).
- check_finite** [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

- det** [float or complex] Determinant of *a*.

Notes

The determinant is computed via LU factorization, LAPACK routine `z/dgetrf`.

Examples

```

>>> from scipy import linalg
>>> a = np.array([[1,2,3], [4,5,6], [7,8,9]])
>>> linalg.det(a)
0.0
>>> a = np.array([[0,2,3], [4,5,6], [7,8,9]])
>>> linalg.det(a)
3.0

```

scipy.linalg.norm

`scipy.linalg.norm(a, ord=None, axis=None, keepdims=False, check_finite=True)`

Matrix or vector norm.

This function is able to return one of seven different matrix norms, or one of an infinite number of vector norms (described below), depending on the value of the `ord` parameter.

Parameters

- a** [(M,) or (M, N) array_like] Input array. If *axis* is `None`, *a* must be 1D or 2D.
- ord** [{non-zero int, inf, -inf, 'fro'}, optional] Order of the norm (see table under `Notes`). `inf` means NumPy's `inf` object
- axis** [{int, 2-tuple of ints, None}, optional] If *axis* is an integer, it specifies the axis of *a* along which to compute the vector norms. If *axis* is a 2-tuple, it specifies the axes that hold 2-D matrices, and the matrix norms of these matrices are computed. If *axis* is `None` then either a vector norm (when *a* is 1-D) or a matrix norm (when *a* is 2-D) is returned.

keepdims [bool, optional] If this is set to True, the axes which are normed over are left in the result as dimensions with size one. With this option the result will broadcast correctly against the original *a*.

check_finite [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

n [float or ndarray] Norm of the matrix or vector(s).

Notes

For values of `ord <= 0`, the result is, strictly speaking, not a mathematical ‘norm’, but it may still be useful for various numerical purposes.

The following norms can be calculated:

ord	norm for matrices	norm for vectors
None	Frobenius norm	2-norm
‘fro’	Frobenius norm	–
inf	max(sum(abs(x), axis=1))	max(abs(x))
-inf	min(sum(abs(x), axis=1))	min(abs(x))
0	–	sum(x != 0)
1	max(sum(abs(x), axis=0))	as below
-1	min(sum(abs(x), axis=0))	as below
2	2-norm (largest sing. value)	as below
-2	smallest singular value	as below
other	–	sum(abs(x)**ord)**(1./ord)

The Frobenius norm is given by [1]:

$$\|A\|_F = [\sum_{i,j} abs(a_{i,j})^2]^{1/2}$$

The `axis` and `keepdims` arguments are passed directly to `numpy.linalg.norm` and are only usable if they are supported by the version of `numpy` in use.

References

[1]

Examples

```
>>> from scipy.linalg import norm
>>> a = np.arange(9) - 4.0
>>> a
array([-4., -3., -2., -1.,  0.,  1.,  2.,  3.,  4.])
>>> b = a.reshape((3, 3))
>>> b
array([[ -4.,  -3.,  -2.],
       [ -1.,   0.,   1.],
       [  2.,   3.,   4.]])
```



```

>>> norm(a)
7.745966692414834
>>> norm(b)
7.745966692414834
>>> norm(b, 'fro')
7.745966692414834
>>> norm(a, np.inf)
4
>>> norm(b, np.inf)
9
>>> norm(a, -np.inf)
0
>>> norm(b, -np.inf)
2

```

```

>>> norm(a, 1)
20
>>> norm(b, 1)
7
>>> norm(a, -1)
-4.6566128774142013e-010
>>> norm(b, -1)
6
>>> norm(a, 2)
7.745966692414834
>>> norm(b, 2)
7.3484692283495345

```

```

>>> norm(a, -2)
0
>>> norm(b, -2)
1.8570331885190563e-016
>>> norm(a, 3)
5.8480354764257312
>>> norm(a, -3)
0

```

scipy.linalg.lstsq

`scipy.linalg.lstsq(a, b, cond=None, overwrite_a=False, overwrite_b=False, check_finite=True, lapack_driver=None)`

Compute least-squares solution to equation $Ax = b$.

Compute a vector x such that the 2-norm $\|b - Ax\|$ is minimized.

Parameters

- a** [(M, N) array_like] Left-hand side array
- b** [(M,) or (M, K) array_like] Right hand side array
- cond** [float, optional] Cutoff for ‘small’ singular values; used to determine effective rank of a . Singular values smaller than $\text{rcond} * \text{largest_singular_value}$ are considered zero.
- overwrite_a**

[bool, optional] Discard data in a (may enhance performance). Default is False.

overwrite_b
[bool, optional] Discard data in b (may enhance performance). Default is False.

check_finite
[bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

lapack_driver
[str, optional] Which LAPACK driver is used to solve the least-squares problem. Options are 'gelsd', 'gelsy', 'gelss'. Default ('gelsd') is a good choice. However, 'gelsy' can be slightly faster on many problems. 'gelss' was used historically. It is generally slow but uses less memory.
New in version 0.17.0.

Returns

x [(N,) or (N, K) ndarray] Least-squares solution. Return shape matches shape of b .

residues [(K,) ndarray or float] Square of the 2-norm for each column in $b - a x$, if $M > N$ and $\text{ndim}(A) == n$ (returns a scalar if b is 1-D). Otherwise a (0,-)-shaped array is returned.

rank [int] Effective rank of a .

s [(min(M, N),) ndarray or None] Singular values of a . The condition number of a is $\text{abs}(s[0] / s[-1])$.

Raises

LinAlgError
If computation does not converge.

ValueError
When parameters are not compatible.

See also:

[*scipy.optimize.nnls*](#)

linear least squares with non-negativity constraint

Notes

When 'gelsy' is used as a driver, *residues* is set to a (0,-)-shaped array and *s* is always None.

Examples

```
>>> from scipy.linalg import lstsq
>>> import matplotlib.pyplot as plt
```

Suppose we have the following data:

```
>>> x = np.array([1, 2.5, 3.5, 4, 5, 7, 8.5])
>>> y = np.array([0.3, 1.1, 1.5, 2.0, 3.2, 6.6, 8.6])
```

We want to fit a quadratic polynomial of the form $y = a + b*x**2$ to this data. We first form the “design matrix” M , with a constant column of 1s and a column containing $x**2$:


```
>>> M = x[:, np.newaxis]**[0, 2]
>>> M
array([[ 1.  ,  1.  ],
       [ 1.  ,  6.25],
       [ 1.  , 12.25],
       [ 1.  , 16.  ],
       [ 1.  , 25.  ],
       [ 1.  , 49.  ],
       [ 1.  , 72.25]])
```

We want to find the least-squares solution to $M \cdot \text{dot}(p) = y$, where p is a vector with length 2 that holds the parameters a and b .

```
>>> p, res, rnk, s = lstsq(M, y)
>>> p
array([ 0.20925829,  0.12013861])
```

Plot the data and the fitted curve.

```
>>> plt.plot(x, y, 'o', label='data')
>>> xx = np.linspace(0, 9, 101)
>>> yy = p[0] + p[1]*xx**2
>>> plt.plot(xx, yy, label='least squares fit, $y = a + bx^2$')
>>> plt.xlabel('x')
>>> plt.ylabel('y')
>>> plt.legend(framealpha=1, shadow=True)
>>> plt.grid(alpha=0.25)
>>> plt.show()
```



scipy.linalg.pinv

`scipy.linalg.pinv(a, cond=None, rcond=None, return_rank=False, check_finite=True)`

Compute the (Moore-Penrose) pseudo-inverse of a matrix.

Calculate a generalized inverse of a matrix using a least-squares solver.

Parameters

- a** [(M, N) array_like] Matrix to be pseudo-inverted.
- cond, rcond** [float, optional] Cutoff factor for 'small' singular values. In `lstsq`, singular values less than `cond*largest_singular_value` will be considered as zero. If both are omitted, the default value `max(M, N) * eps` is passed to `lstsq` where `eps` is the corresponding machine precision value of the datatype of `a`.
Changed in version 1.3.0: Previously the default cutoff value was just `eps` without the factor `max(M, N)`.
- return_rank** [bool, optional] if True, return the effective rank of the matrix
- check_finite** [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

- B** [(N, M) ndarray] The pseudo-inverse of matrix `a`.
- rank** [int] The effective rank of the matrix. Returned if `return_rank == True`

Raises

- LinAlgError**
If computation does not converge.

Examples

```
>>> from scipy import linalg
>>> a = np.random.randn(9, 6)
>>> B = linalg.pinv(a)
>>> np.allclose(a, np.dot(a, np.dot(B, a)))
True
>>> np.allclose(B, np.dot(B, np.dot(a, B)))
True
```

scipy.linalg.pinv2

`scipy.linalg.pinv2(a, cond=None, rcond=None, return_rank=False, check_finite=True)`

Compute the (Moore-Penrose) pseudo-inverse of a matrix.

Calculate a generalized inverse of a matrix using its singular-value decomposition and including all 'large' singular values.

Parameters

- a** [(M, N) array_like] Matrix to be pseudo-inverted.

cond, rcond

[float or None] Cutoff for ‘small’ singular values; singular values smaller than this value are considered as zero. If both are omitted, the default value $\max(M, N) * \text{largest_singular_value} * \text{eps}$ is used where `eps` is the machine precision value of the datatype of `a`.

Changed in version 1.3.0: Previously the default cutoff value was just $\text{eps} * f$ where `f` was $1e3$ for single precision and $1e6$ for double precision.

return_rank

[bool, optional] If True, return the effective rank of the matrix.

check_finite

[bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

B [(N, M) ndarray] The pseudo-inverse of matrix `a`.
rank [int] The effective rank of the matrix. Returned if `return_rank` is True.

Raises**LinAlgError**

If SVD computation does not converge.

Examples

```
>>> from scipy import linalg
>>> a = np.random.randn(9, 6)
>>> B = linalg.pinv2(a)
>>> np.allclose(a, np.dot(a, np.dot(B, a)))
True
>>> np.allclose(B, np.dot(B, np.dot(a, B)))
True
```

scipy.linalg.pinvh

`scipy.linalg.pinvh(a, cond=None, rcond=None, lower=True, return_rank=False, check_finite=True)`

Compute the (Moore-Penrose) pseudo-inverse of a Hermitian matrix.

Calculate a generalized inverse of a Hermitian or real symmetric matrix using its eigenvalue decomposition and including all eigenvalues with ‘large’ absolute value.

Parameters

a [(N, N) array_like] Real symmetric or complex hermetian matrix to be pseudo-inverted

cond, rcond

[float or None] Cutoff for ‘small’ singular values; singular values smaller than this value are considered as zero. If both are omitted, the default $\max(M, N) * \text{largest_eigenvalue} * \text{eps}$ is used where `eps` is the machine precision value of the datatype of `a`.

Changed in version 1.3.0: Previously the default cutoff value was just $\text{eps} * f$ where `f` was $1e3$ for single precision and $1e6$ for double precision.

lower [bool, optional] Whether the pertinent array data is taken from the lower or upper triangle of `a`. (Default: lower)

return_rank

[bool, optional] If True, return the effective rank of the matrix.

check_finite

[bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

B [(N, N) ndarray] The pseudo-inverse of matrix *a*.
rank [int] The effective rank of the matrix. Returned if *return_rank* is True.

Raises
LinAlgError

If eigenvalue does not converge

Examples

```
>>> from scipy.linalg import pinvh
>>> a = np.random.randn(9, 6)
>>> a = np.dot(a, a.T)
>>> B = pinvh(a)
>>> np.allclose(a, np.dot(a, np.dot(B, a)))
True
>>> np.allclose(B, np.dot(B, np.dot(a, B)))
True
```

scipy.linalg.kron

`scipy.linalg.kron(a, b)`

Kronecker product.

The result is the block matrix:

```
a[0,0]*b   a[0,1]*b   ... a[0,-1]*b
a[1,0]*b   a[1,1]*b   ... a[1,-1]*b
...
a[-1,0]*b  a[-1,1]*b  ... a[-1,-1]*b
```

Parameters

a [(M, N) ndarray] Input array
b [(P, Q) ndarray] Input array

Returns

A [(M*P, N*Q) ndarray] Kronecker product of *a* and *b*.

Examples

```
>>> from numpy import array
>>> from scipy.linalg import kron
>>> kron(array([[1,2],[3,4]]), array([[1,1,1]]))
array([[1, 1, 1, 2, 2, 2],
       [3, 3, 3, 4, 4, 4]])
```

scipy.linalg.khatri_rao

`scipy.linalg.khatri_rao(a, b)`

Khatri-rao product

A column-wise Kronecker product of two matrices

Parameters

- a: (n, k) array_like**
Input array
- b: (m, k) array_like**
Input array

Returns

- c: (n*m, k) ndarray**
Khatri-rao product of *a* and *b*.

See also:

kron

Kronecker product

Notes

The mathematical definition of the Khatri-Rao product is:

$$(A_{ij} \otimes B_{ij})_{ij}$$

which is the Kronecker product of every column of A and B, e.g.:

```
c = np.vstack([np.kron(a[:, k], b[:, k]) for k in range(b.shape[1])]).T
```

Examples

```
>>> from scipy import linalg
>>> a = np.array([[1, 2, 3], [4, 5, 6]])
>>> b = np.array([[3, 4, 5], [6, 7, 8], [2, 3, 9]])
>>> linalg.khatri_rao(a, b)
array([[ 3,  8, 15],
       [ 6, 14, 24],
       [ 2,  6, 27],
       [12, 20, 30],
```

(continues on next page)

(continued from previous page)

```
[24, 35, 48],  
 [ 8, 15, 54]])
```

scipy.linalg.tril

`scipy.linalg.tril(m, k=0)`

Make a copy of a matrix with elements above the k th diagonal zeroed.

Parameters

m [array_like] Matrix whose elements to return
k [int, optional] Diagonal above which to zero elements. $k == 0$ is the main diagonal, $k < 0$ subdiagonal and $k > 0$ superdiagonal.

Returns

tril [ndarray] Return is the same shape and type as m .

Examples

```
>>> from scipy.linalg import tril  
>>> tril([[1, 2, 3], [4, 5, 6], [7, 8, 9], [10, 11, 12]], -1)  
array([[ 0,  0,  0],  
       [ 4,  0,  0],  
       [ 7,  8,  0],  
       [10, 11, 12]])
```

scipy.linalg.triu

`scipy.linalg.triu(m, k=0)`

Make a copy of a matrix with elements below the k th diagonal zeroed.

Parameters

m [array_like] Matrix whose elements to return
k [int, optional] Diagonal below which to zero elements. $k == 0$ is the main diagonal, $k < 0$ subdiagonal and $k > 0$ superdiagonal.

Returns

triu [ndarray] Return matrix with zeroed elements below the k th diagonal and has same shape and type as m .

Examples

```
>>> from scipy.linalg import triu
>>> triu([[1, 2, 3], [4, 5, 6], [7, 8, 9], [10, 11, 12]], -1)
array([[ 1,  2,  3],
       [ 4,  5,  6],
       [ 0,  8,  9],
       [ 0,  0, 12]])
```

scipy.linalg.orthogonal_procrustes

`scipy.linalg.orthogonal_procrustes` (*A*, *B*, *check_finite=True*)

Compute the matrix solution of the orthogonal Procrustes problem.

Given matrices *A* and *B* of equal shape, find an orthogonal matrix *R* that most closely maps *A* to *B* using the algorithm given in [1].

Parameters

A [(M, N) array_like] Matrix to be mapped.

B [(M, N) array_like] Target matrix.

check_finite

[bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

R [(N, N) ndarray] The matrix solution of the orthogonal Procrustes problem. Minimizes the Frobenius norm of $(A @ R) - B$, subject to $R.T @ R = I$.

scale [float] Sum of the singular values of $A.T @ B$.

Raises

ValueError

If the input array shapes don't match or if *check_finite* is True and the arrays contain Inf or NaN.

Notes

Note that unlike higher level Procrustes analyses of spatial data, this function only uses orthogonal transformations like rotations and reflections, and it does not use scaling or translation.

New in version 0.15.0.

References

[1]

Examples

```
>>> from scipy.linalg import orthogonal_procrustes
>>> A = np.array([[ 2,  0,  1], [-2,  0,  0]])
```

Flip the order of columns and check for the anti-diagonal mapping

```
>>> R, sca = orthogonal_procrustes(A, np.fliplr(A))
>>> R
array([[ -5.34384992e-17,  0.00000000e+00,  1.00000000e+00],
       [ 0.00000000e+00,  1.00000000e+00,  0.00000000e+00],
       [ 1.00000000e+00,  0.00000000e+00, -7.85941422e-17]])
>>> sca
9.0
```

scipy.linalg.matrix_balance

`scipy.linalg.matrix_balance` (*A*, *permute=True*, *scale=True*, *separate=False*, *overwrite_a=False*)

Compute a diagonal similarity transformation for row/column balancing.

The balancing tries to equalize the row and column 1-norms by applying a similarity transformation such that the magnitude variation of the matrix entries is reflected to the scaling matrices.

Moreover, if enabled, the matrix is first permuted to isolate the upper triangular parts of the matrix and, again if scaling is also enabled, only the remaining subblocks are subjected to scaling.

The balanced matrix satisfies the following equality

$$B = T^{-1}AT$$

The scaling coefficients are approximated to the nearest power of 2 to avoid round-off errors.

Parameters

- A** [(n, n) array_like] Square data matrix for the balancing.
- permute** [bool, optional] The selector to define whether permutation of A is also performed prior to scaling.
- scale** [bool, optional] The selector to turn on and off the scaling. If False, the matrix will not be scaled.
- separate** [bool, optional] This switches from returning a full matrix of the transformation to a tuple of two separate 1-D permutation and scaling arrays.
- overwrite_a** [bool, optional] This is passed to xGEBAL directly. Essentially, overwrites the result to the data. It might increase the space efficiency. See LAPACK manual for details. This is False by default.

Returns

- B** [(n, n) ndarray] Balanced matrix
- T** [(n, n) ndarray] A possibly permuted diagonal matrix whose nonzero entries are integer powers of 2 to avoid numerical truncation errors.
- scale, perm** [(n,) ndarray] If `separate` keyword is set to True then instead of the array T above, the scaling and the permutation vectors are given separately as a tuple without allocating the full array T.

Notes

This algorithm is particularly useful for eigenvalue and matrix decompositions and in many cases it is already called by various LAPACK routines.

The algorithm is based on the well-known technique of [1] and has been modified to account for special cases. See [2] for details which have been implemented since LAPACK v3.5.0. Before this version there are corner cases where balancing can actually worsen the conditioning. See [3] for such examples.

The code is a wrapper around LAPACK's xGEBAL routine family for matrix balancing.

New in version 0.19.0.

References

[1], [2], [3]

Examples

```
>>> from scipy import linalg
>>> x = np.array([[1,2,0], [9,1,0.01], [1,2,10*np.pi]])
```

```
>>> y, permscale = linalg.matrix_balance(x)
>>> np.abs(x).sum(axis=0) / np.abs(x).sum(axis=1)
array([ 3.66666667,  0.4995005 ,  0.91312162])
```

```
>>> np.abs(y).sum(axis=0) / np.abs(y).sum(axis=1)
array([ 1.2          ,  1.27041742,  0.92658316]) # may vary
```

```
>>> permscale # only powers of 2 (0.5 == 2^(-1))
array([[ 0.5,  0. ,  0. ], # may vary
       [ 0. ,  1. ,  0. ],
       [ 0. ,  0. ,  1. ]])
```

scipy.linalg.subspace_angles

`scipy.linalg.subspace_angles` (*A*, *B*)

Compute the subspace angles between two matrices.

Parameters

A [(M, N) array_like] The first input array.
B [(M, K) array_like] The second input array.

Returns

angles [ndarray, shape (min(N, K),)] The subspace angles between the column spaces of *A* and *B* in descending order.

See also:

[orth](#)

[svd](#)

Notes

This computes the subspace angles according to the formula provided in [1]. For equivalence with MATLAB and Octave behavior, use `angles[0]`.

New in version 1.0.

References

[1]

Examples

An Hadamard matrix, which has orthogonal columns, so we expect that the subspace angle to be $\frac{\pi}{2}$:

```
>>> from scipy.linalg import hadamard, subspace_angles
>>> H = hadamard(4)
>>> print(H)
[[ 1  1  1  1]
 [ 1 -1  1 -1]
 [ 1  1 -1 -1]
 [ 1 -1 -1  1]]
>>> np.rad2deg(subspace_angles(H[:, :2], H[:, 2:]))
array([ 90.,  90.]
```

And the subspace angle of a matrix to itself should be zero:

```
>>> subspace_angles(H[:, :2], H[:, :2]) <= 2 * np.finfo(float).eps
array([ True,  True], dtype=bool)
```

The angles between non-orthogonal subspaces are in between these extremes:

```
>>> x = np.random.RandomState(0).randn(4, 3)
>>> np.rad2deg(subspace_angles(x[:, :2], x[:, [2]]))
array([ 55.832])
```

scipy.linalg.LinAlgError

exception `scipy.linalg.LinAlgError`

Generic Python-exception-derived object raised by linalg functions.

General purpose exception class, derived from Python's `Exception` class, programmatically raised in linalg functions when a Linear Algebra-related condition would prevent further correct execution of the function.

Parameters

None

Examples

```
>>> from numpy import linalg as LA
>>> LA.inv(np.zeros((2,2)))
Traceback (most recent call last):
  File "<stdin>", line 1, in <module>
  File "...linalg.py", line 350,
    in inv return wrap(solve(a, identity(a.shape[0], dtype=a.dtype)))
  File "...linalg.py", line 249,
    in solve
    raise LinAlgError('Singular matrix')
numpy.linalg.LinAlgError: Singular matrix
```

with_traceback()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

scipy.linalg.LinAlgWarning

exception `scipy.linalg.LinAlgWarning`

The warning emitted when a linear algebra related operation is close to fail conditions of the algorithm or loss of accuracy is expected.

with_traceback()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

6.10.2 Eigenvalue Problems

<code>eig(a[, b, left, right, overwrite_a, ...])</code>	Solve an ordinary or generalized eigenvalue problem of a square matrix.
<code>eigvals(a[, b, overwrite_a, check_finite, ...])</code>	Compute eigenvalues from an ordinary or generalized eigenvalue problem.
<code>eigh(a[, b, lower, eigvals_only, ...])</code>	Solve a standard or generalized eigenvalue problem for a complex Hermitian or real symmetric matrix.
<code>eigvalsh(a[, b, lower, overwrite_a, ...])</code>	Solves a standard or generalized eigenvalue problem for a complex Hermitian or real symmetric matrix.
<code>eig_banded(a_band[, lower, eigvals_only, ...])</code>	Solve real symmetric or complex Hermitian band matrix eigenvalue problem.
<code>eigvals_banded(a_band[, lower, ...])</code>	Solve real symmetric or complex Hermitian band matrix eigenvalue problem.
<code>eigh_tridiagonal(d, e[, eigvals_only, ...])</code>	Solve eigenvalue problem for a real symmetric tridiagonal matrix.
<code>eigvalsh_tridiagonal(d, e[, select, ...])</code>	Solve eigenvalue problem for a real symmetric tridiagonal matrix.

scipy.linalg.eig

`scipy.linalg.eig(a, b=None, left=False, right=True, overwrite_a=False, overwrite_b=False, check_finite=True, homogeneous_eigvals=False)`

Solve an ordinary or generalized eigenvalue problem of a square matrix.

Find eigenvalues w and right or left eigenvectors of a general matrix:

$\begin{aligned} a \quad vr[:,i] &= w[i] & b \quad vr[:,i] \\ a.H \quad vl[:,i] &= w[i].conj() & b.H \quad vl[:,i] \end{aligned}$

where $.H$ is the Hermitian conjugation.

Parameters

- a** [(M, M) array_like] A complex or real matrix whose eigenvalues and eigenvectors will be computed.
- b** [(M, M) array_like, optional] Right-hand side matrix in a generalized eigenvalue problem. Default is None, identity matrix is assumed.
- left** [bool, optional] Whether to calculate and return left eigenvectors. Default is False.
- right** [bool, optional] Whether to calculate and return right eigenvectors. Default is True.
- overwrite_a** [bool, optional] Whether to overwrite a ; may improve performance. Default is False.
- overwrite_b** [bool, optional] Whether to overwrite b ; may improve performance. Default is False.
- check_finite** [bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.
- homogeneous_eigvals** [bool, optional] If True, return the eigenvalues in homogeneous coordinates. In this case w is a (2, M) array so that:

$w[1,i] \quad a \quad vr[:,i] = w[0,i] \quad b \quad vr[:,i]$

Default is False.

Returns

- w** [(M,) or (2, M) double or complex ndarray] The eigenvalues, each repeated according to its multiplicity. The shape is (M,) unless `homogeneous_eigvals=True`.
- vl** [(M, M) double or complex ndarray] The normalized left eigenvector corresponding to the eigenvalue $w[i]$ is the column $vl[:,i]$. Only returned if `left=True`.
- vr** [(M, M) double or complex ndarray] The normalized right eigenvector corresponding to the eigenvalue $w[i]$ is the column $vr[:,i]$. Only returned if `right=True`.

Raises

LinAlgError

If eigenvalue computation does not converge.

See also:

[eigvals](#)

eigenvalues of general arrays

[eigh](#)

Eigenvalues and right eigenvectors for symmetric/Hermitian arrays.

`eig_banded`

eigenvalues and right eigenvectors for symmetric/Hermitian band matrices

`eigh_tridiagonal`

eigenvalues and right eigenvectors for symmetric/Hermitian tridiagonal matrices

Examples

```
>>> from scipy import linalg
>>> a = np.array([[0., -1.], [1., 0.]])
>>> linalg.eigvals(a)
array([0.+1.j, 0.-1.j])
```

```
>>> b = np.array([[0., 1.], [1., 1.]])
>>> linalg.eigvals(a, b)
array([ 1.+0.j, -1.+0.j])
```

```
>>> a = np.array([[3., 0., 0.], [0., 8., 0.], [0., 0., 7.]])
>>> linalg.eigvals(a, homogeneous_eigvals=True)
array([[3.+0.j, 8.+0.j, 7.+0.j],
       [1.+0.j, 1.+0.j, 1.+0.j]])
```

```
>>> a = np.array([[0., -1.], [1., 0.]])
>>> linalg.eigvals(a) == linalg.eig(a)[0]
array([ True,  True])
>>> linalg.eig(a, left=True, right=False)[1] # normalized left eigenvector
array([[ -0.70710678+0.j, -0.70710678-0.j ],
       [ -0.          +0.70710678j, -0.          -0.70710678j]])
>>> linalg.eig(a, left=False, right=True)[1] # normalized right_
→eigenvector
array([[ 0.70710678+0.j,  0.70710678-0.j ],
       [ 0.          -0.70710678j,  0.          +0.70710678j]])
```

`scipy.linalg.eigvals`

`scipy.linalg.eigvals` (*a*, *b=None*, *overwrite_a=False*, *check_finite=True*, *homogeneous_eigvals=False*)

Compute eigenvalues from an ordinary or generalized eigenvalue problem.

Find eigenvalues of a general matrix:

$$a \quad vr[:,i] = w[i] \quad b \quad vr[:,i]$$

Parameters

- a** [(M, M) array_like] A complex or real matrix whose eigenvalues and eigenvectors will be computed.
- b** [(M, M) array_like, optional] Right-hand side matrix in a generalized eigenvalue problem. If omitted, identity matrix is assumed.
- overwrite_a** [bool, optional] Whether to overwrite data in *a* (may improve performance)

check_finite

[bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

homogeneous_eigvals

[bool, optional] If True, return the eigenvalues in homogeneous coordinates. In this case w is a (2, M) array so that:

$$w[1,i] \ a \ v_r[:,i] = w[0,i] \ b \ v_r[:,i]$$

Default is False.

Returns

w [(M,) or (2, M) double or complex ndarray] The eigenvalues, each repeated according to its multiplicity but not in any specific order. The shape is (M,) unless `homogeneous_eigvals=True`.

Raises

LinAlgError

If eigenvalue computation does not converge

See also:

eig

eigenvalues and right eigenvectors of general arrays.

eigvalsh

eigenvalues of symmetric or Hermitian arrays

eigvals_banded

eigenvalues for symmetric/Hermitian band matrices

eigvalsh_tridiagonal

eigenvalues of symmetric/Hermitian tridiagonal matrices

Examples

```
>>> from scipy import linalg
>>> a = np.array([[0., -1.], [1., 0.]])
>>> linalg.eigvals(a)
array([0.+1.j, 0.-1.j])
```

```
>>> b = np.array([[0., 1.], [1., 1.]])
>>> linalg.eigvals(a, b)
array([ 1.+0.j, -1.+0.j])
```

```
>>> a = np.array([[3., 0., 0.], [0., 8., 0.], [0., 0., 7.]])
>>> linalg.eigvals(a, homogeneous_eigvals=True)
array([[3.+0.j, 8.+0.j, 7.+0.j],
       [1.+0.j, 1.+0.j, 1.+0.j]])
```


scipy.linalg.eigh

`scipy.linalg.eigh` (*a*, *b=None*, *lower=True*, *eigvals_only=False*, *overwrite_a=False*, *overwrite_b=False*, *turbo=True*, *eigvals=None*, *type=1*, *check_finite=True*, *subset_by_index=None*, *subset_by_value=None*, *driver=None*)

Solve a standard or generalized eigenvalue problem for a complex Hermitian or real symmetric matrix.

Find eigenvalues array *w* and optionally eigenvectors array *v* of array *a*, where *b* is positive definite such that for every eigenvalue λ (*i*-th entry of *w*) and its eigenvector *v_i* (*i*-th column of *v*) satisfies:

$$\begin{aligned} a @ v_i &= \lambda * b @ v_i \\ v_i.conj().T @ a @ v_i &= \lambda \\ v_i.conj().T @ b @ v_i &= 1 \end{aligned}$$

In the standard problem, *b* is assumed to be the identity matrix.

Parameters

- a** [(M, M) array_like] A complex Hermitian or real symmetric matrix whose eigenvalues and eigenvectors will be computed.
- b** [(M, M) array_like, optional] A complex Hermitian or real symmetric definite positive matrix in. If omitted, identity matrix is assumed.
- lower** [bool, optional] Whether the pertinent array data is taken from the lower or upper triangle of *a* and, if applicable, *b*. (Default: lower)
- eigvals_only** [bool, optional] Whether to calculate only eigenvalues and no eigenvectors. (Default: both are calculated)
- subset_by_index** [iterable, optional] If provided, this two-element iterable defines the start and the end indices of the desired eigenvalues (ascending order and 0-indexed). To return only the second smallest to fifth smallest eigenvalues, [1, 4] is used. [n-3, n-1] returns the largest three. Only available with “evr”, “evx”, and “gvx” drivers. The entries are directly converted to integers via `int()`.
- subset_by_value** [iterable, optional] If provided, this two-element iterable defines the half-open interval (*a*, *b*] that, if any, only the eigenvalues between these values are returned. Only available with “evr”, “evx”, and “gvx” drivers. Use `np.inf` for the unconstrained ends.
- driver: str, optional** Defines which LAPACK driver should be used. Valid options are “ev”, “evd”, “evr”, “evx” for standard problems and “gv”, “gvd”, “gvx” for generalized (where *b* is not None) problems. See the Notes section.
- type** [int, optional] For the generalized problems, this keyword specifies the problem type to be solved for *w* and *v* (only takes 1, 2, 3 as possible inputs):

$$\begin{aligned} 1 \Rightarrow & a @ v = w @ b @ v \\ 2 \Rightarrow & a @ b @ v = w @ v \\ 3 \Rightarrow & b @ a @ v = w @ v \end{aligned}$$

This keyword is ignored for standard problems.

- overwrite_a** [bool, optional] Whether to overwrite data in *a* (may improve performance). Default is False.
- overwrite_b** [bool, optional] Whether to overwrite data in *b* (may improve performance). Default is False.
- check_finite** [bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

- turbo** [bool, optional] *Deprecated since v1.5.0, use ``driver=gvd`` keyword instead.* Use divide and conquer algorithm (faster but expensive in memory, only for generalized eigenvalue problem and if full set of eigenvalues are requested.). Has no significant effect if eigenvectors are not requested.
- eigvals** [tuple (lo, hi), optional] *Deprecated since v1.5.0, use ``subset_by_index`` keyword instead.* Indexes of the smallest and largest (in ascending order) eigenvalues and corresponding eigenvectors to be returned: $0 \leq lo \leq hi \leq M-1$. If omitted, all eigenvalues and eigenvectors are returned.

Returns

- w** [(N,) ndarray] The N ($1 \leq N \leq M$) selected eigenvalues, in ascending order, each repeated according to its multiplicity.
- v** [(M, N) ndarray] (if `eigvals_only == False`)

Raises

LinAlgError

If eigenvalue computation does not converge, an error occurred, or b matrix is not definite positive. Note that if input matrices are not symmetric or Hermitian, no error will be reported but results will be wrong.

See also:

eigvalsh

eigenvalues of symmetric or Hermitian arrays

eig

eigenvalues and right eigenvectors for non-symmetric arrays

eigh_tridiagonal

eigenvalues and right eigenvectors for symmetric/Hermitian tridiagonal matrices

Notes

This function does not check the input array for being Hermitian/symmetric in order to allow for representing arrays with only their upper/lower triangular parts. Also, note that even though not taken into account, finiteness check applies to the whole array and unaffected by “lower” keyword.

This function uses LAPACK drivers for computations in all possible keyword combinations, prefixed with `sy` if arrays are real and `he` if complex, e.g., a float array with “evr” driver is solved via “syevr”, complex arrays with “gvx” driver problem is solved via “hegvx” etc.

As a brief summary, the slowest and the most robust driver is the classical `<sy/he>ev` which uses symmetric QR. `<sy/he>evr` is seen as the optimal choice for the most general cases. However, there are certain occasions that `<sy/he>evd` computes faster at the expense of more memory usage. `<sy/he>evx`, while still being faster than `<sy/he>ev`, often performs worse than the rest except when very few eigenvalues are requested for large arrays though there is still no performance guarantee.

For the generalized problem, normalization with respect to the given type argument:

```

type 1 and 3 :      v.conj().T @ a @ v = w
type 2       : inv(v).conj().T @ a @ inv(v) = w

type 1 or 2  :      v.conj().T @ b @ v = I
type 3       : v.conj().T @ inv(b) @ v = I

```

Examples

```
>>> from scipy.linalg import eigh
>>> A = np.array([[6, 3, 1, 5], [3, 0, 5, 1], [1, 5, 6, 2], [5, 1, 2, 2]])
>>> w, v = eigh(A)
>>> np.allclose(A @ v - v @ np.diag(w), np.zeros((4, 4)))
True
```

Request only the eigenvalues

```
>>> w = eigh(A, eigvals_only=True)
```

Request eigenvalues that are less than 10.

```
>>> A = np.array([[34, -4, -10, -7, 2],
...              [-4, 7, 2, 12, 0],
...              [-10, 2, 44, 2, -19],
...              [-7, 12, 2, 79, -34],
...              [2, 0, -19, -34, 29]])
>>> eigh(A, eigvals_only=True, subset_by_value=[-np.inf, 10])
array([6.69199443e-07, 9.11938152e+00])
```

Request the largest second eigenvalue and its eigenvector

```
>>> w, v = eigh(A, subset_by_index=[1, 1])
>>> w
array([9.11938152])
>>> v.shape # only a single column is returned
(5, 1)
```

scipy.linalg.eigvalsh

`scipy.linalg.eigvalsh(a, b=None, lower=True, overwrite_a=False, overwrite_b=False, turbo=True, eigvals=None, type=1, check_finite=True, subset_by_index=None, subset_by_value=None, driver=None)`

Solves a standard or generalized eigenvalue problem for a complex Hermitian or real symmetric matrix.

Find eigenvalues array `w` of array `a`, where `b` is positive definite such that for every eigenvalue λ (i -th entry of `w`) and its eigenvector v_i (i -th column of `v`) satisfies:

```
a @ vi = lambda * b @ vi
vi.conj().T @ a @ vi = lambda
vi.conj().T @ b @ vi = 1
```

In the standard problem, `b` is assumed to be the identity matrix.

Parameters

- a** [(M, M) array_like] A complex Hermitian or real symmetric matrix whose eigenvalues will be computed.
- b** [(M, M) array_like, optional] A complex Hermitian or real symmetric definite positive matrix in. If omitted, identity matrix is assumed.
- lower** [bool, optional] Whether the pertinent array data is taken from the lower or upper triangle of `a` and, if applicable, `b`. (Default: lower)

eigvals_only

[bool, optional] Whether to calculate only eigenvalues and no eigenvectors. (Default: both are calculated)

subset_by_index

[iterable, optional] If provided, this two-element iterable defines the start and the end indices of the desired eigenvalues (ascending order and 0-indexed). To return only the second smallest to fifth smallest eigenvalues, [1, 4] is used. [n-3, n-1] returns the largest three. Only available with “evr”, “evx”, and “gvx” drivers. The entries are directly converted to integers via `int()`.

subset_by_value

[iterable, optional] If provided, this two-element iterable defines the half-open interval (a, b] that, if any, only the eigenvalues between these values are returned. Only available with “evr”, “evx”, and “gvx” drivers. Use `np.inf` for the unconstrained ends.

driver: str, optional

Defines which LAPACK driver should be used. Valid options are “ev”, “evd”, “evr”, “evx” for standard problems and “gv”, “gvd”, “gvx” for generalized (where b is not None) problems. See the Notes section of `scipy.linalg.eigh`.

type

[int, optional] For the generalized problems, this keyword specifies the problem type to be solved for w and v (only takes 1, 2, 3 as possible inputs):

```
1 =>      a @ v = w @ b @ v
2 => a @ b @ v = w @ v
3 => b @ a @ v = w @ v
```

This keyword is ignored for standard problems.

overwrite_a

[bool, optional] Whether to overwrite data in a (may improve performance). Default is False.

overwrite_b

[bool, optional] Whether to overwrite data in b (may improve performance). Default is False.

check_finite

[bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

turbo

[bool, optional] *Deprecated by “driver=gvd” option.* Has no significant effect for eigenvalue computations since no eigenvectors are requested.
..Deprecated in v1.5.0

eigvals

[tuple (lo, hi), optional] *Deprecated by “subset_by_index” keyword.* Indexes of the smallest and largest (in ascending order) eigenvalues and corresponding eigenvectors to be returned: $0 \leq lo \leq hi \leq M-1$. If omitted, all eigenvalues and eigenvectors are returned.

Returns

w

[(N,) ndarray] The N ($1 \leq N \leq M$) selected eigenvalues, in ascending order, each repeated according to its multiplicity.

Raises

LinAlgError

If eigenvalue computation does not converge, an error occurred, or b matrix is not definite positive. Note that if input matrices are not symmetric or Hermitian, no error will be reported but results will be wrong.

See also:

[eigh](#)

eigenvalues and right eigenvectors for symmetric/Hermitian arrays

eigvals

eigenvalues of general arrays

eigvals_banded

eigenvalues for symmetric/Hermitian band matrices

eigvalsh_tridiagonal

eigenvalues of symmetric/Hermitian tridiagonal matrices

Notes

This function does not check the input array for being Hermitian/symmetric in order to allow for representing arrays with only their upper/lower triangular parts.

This function serves as a one-liner shorthand for `scipy.linalg.eigh` with the option `eigvals_only=True` to get the eigenvalues and not the eigenvectors. Here it is kept as a legacy convenience. It might be beneficial to use the main function to have full control and to be a bit more pythonic.

Examples

For more examples see `scipy.linalg.eigh`.

```
>>> from scipy.linalg import eigvalsh
>>> A = np.array([[6, 3, 1, 5], [3, 0, 5, 1], [1, 5, 6, 2], [5, 1, 2, 2]])
>>> w = eigvalsh(A)
>>> w
array([-3.74637491, -0.76263923,  6.08502336, 12.42399079])
```

`scipy.linalg.eig_banded`

`scipy.linalg.eig_banded`(*a_band*, *lower=False*, *eigvals_only=False*, *overwrite_a_band=False*, *select='a'*, *select_range=None*, *max_ev=0*, *check_finite=True*)

Solve real symmetric or complex Hermitian band matrix eigenvalue problem.

Find eigenvalues *w* and optionally right eigenvectors *v* of *a*:

```
a v[:,i] = w[i] v[:,i]
v.H v    = identity
```

The matrix *a* is stored in *a_band* either in lower diagonal or upper diagonal ordered form:

`a_band[u + i - j, j] == a[i,j]` (if upper form; $i \leq j$) `a_band[i - j, j] == a[i,j]` (if lower form; $i \geq j$)

where *u* is the number of bands above the diagonal.

Example of *a_band* (shape of *a* is (6,6), *u*=2):

```
upper form:
*   *   a02 a13 a24 a35
*   a01 a12 a23 a34 a45
a00 a11 a22 a33 a44 a55

lower form:
```

(continues on next page)

(continued from previous page)

a00	a11	a22	a33	a44	a55	
a10	a21	a32	a43	a54	*	
a20	a31	a42	a53	*	*	

Cells marked with * are not used.

Parameters

- a_band** [(u+1, M) array_like] The bands of the M by M matrix a.
- lower** [bool, optional] Is the matrix in the lower form. (Default is upper form)
- eigvals_only** [bool, optional] Compute only the eigenvalues and no eigenvectors. (Default: calculate also eigenvectors)
- overwrite_a_band** [bool, optional] Discard data in a_band (may enhance performance)
- select** [{'a', 'v', 'i'}, optional] Which eigenvalues to calculate

select	calculated
'a'	All eigenvalues
'v'	Eigenvalues in the interval (min, max]
'i'	Eigenvalues with indices min <= i <= max

- select_range** [(min, max), optional] Range of selected eigenvalues
- max_ev** [int, optional] For select=='v', maximum number of eigenvalues expected. For other values of select, has no meaning.
In doubt, leave this parameter untouched.
- check_finite** [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

- w** [(M,) ndarray] The eigenvalues, in ascending order, each repeated according to its multiplicity.
- v** [(M, M) float or complex ndarray] The normalized eigenvector corresponding to the eigenvalue w[i] is the column v[:,i].

Raises

- LinAlgError**
If eigenvalue computation does not converge.

See also:

eigvals_banded

eigenvalues for symmetric/Hermitian band matrices

eig

eigenvalues and right eigenvectors of general arrays.

eigh

eigenvalues and right eigenvectors for symmetric/Hermitian arrays

eigh_tridiagonal

eigenvalues and right eigenvectors for symmetric/Hermitian tridiagonal matrices

Examples

```

>>> from scipy.linalg import eig_banded
>>> A = np.array([[1, 5, 2, 0], [5, 2, 5, 2], [2, 5, 3, 5], [0, 2, 5, 4]])
>>> Ab = np.array([[1, 2, 3, 4], [5, 5, 5, 0], [2, 2, 0, 0]])
>>> w, v = eig_banded(Ab, lower=True)
>>> np.allclose(A @ v - v @ np.diag(w), np.zeros((4, 4)))
True
>>> w = eig_banded(Ab, lower=True, eigvals_only=True)
>>> w
array([-4.26200532, -2.22987175,  3.95222349, 12.53965359])

```

Request only the eigenvalues between [-3, 4]

```

>>> w, v = eig_banded(Ab, lower=True, select='v', select_range=[-3, 4])
>>> w
array([-2.22987175,  3.95222349])

```

`scipy.linalg.eigvals_banded`

`scipy.linalg.eigvals_banded`(*a_band*, *lower=False*, *overwrite_a_band=False*, *select='a'*, *select_range=None*, *check_finite=True*)

Solve real symmetric or complex Hermitian band matrix eigenvalue problem.

Find eigenvalues *w* of *a*:

```

a v[:,i] = w[i] v[:,i]
v.H v    = identity

```

The matrix *a* is stored in *a_band* either in lower diagonal or upper diagonal ordered form:

$a_band[u + i - j, j] == a[i,j]$ (if upper form; $i \leq j$) $a_band[i - j, j] == a[i,j]$ (if lower form; $i \geq j$)

where *u* is the number of bands above the diagonal.

Example of *a_band* (shape of *a* is (6,6), *u*=2):

```

upper form:
*   *   a02 a13 a24 a35
*   a01 a12 a23 a34 a45
a00 a11 a22 a33 a44 a55

lower form:
a00 a11 a22 a33 a44 a55
a10 a21 a32 a43 a54 *
a20 a31 a42 a53 *   *

```

Cells marked with * are not used.

Parameters

a_band [(*u*+1, *M*) array_like] The bands of the *M* by *M* matrix *a*.

lower [bool, optional] Is the matrix in the lower form. (Default is upper form)
overwrite_a_band [bool, optional] Discard data in a_band (may enhance performance)
select [{'a', 'v', 'i'}, optional] Which eigenvalues to calculate

select	calculated
'a'	All eigenvalues
'v'	Eigenvalues in the interval (min, max]
'i'	Eigenvalues with indices $\text{min} \leq i \leq \text{max}$

select_range [(min, max), optional] Range of selected eigenvalues

check_finite [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

w [(M,) ndarray] The eigenvalues, in ascending order, each repeated according to its multiplicity.

Raises

LinAlgError
 If eigenvalue computation does not converge.

See also:

[*eig_banded*](#)

eigenvalues and right eigenvectors for symmetric/Hermitian band matrices

[*eigvalsh_tridiagonal*](#)

eigenvalues of symmetric/Hermitian tridiagonal matrices

[*eigvals*](#)

eigenvalues of general arrays

[*eigh*](#)

eigenvalues and right eigenvectors for symmetric/Hermitian arrays

[*eig*](#)

eigenvalues and right eigenvectors for non-symmetric arrays

Examples

```
>>> from scipy.linalg import eigvals_banded
>>> A = np.array([[1, 5, 2, 0], [5, 2, 5, 2], [2, 5, 3, 5], [0, 2, 5, 4]])
>>> Ab = np.array([[1, 2, 3, 4], [5, 5, 5, 0], [2, 2, 0, 0]])
>>> w = eigvals_banded(Ab, lower=True)
>>> w
array([-4.26200532, -2.22987175,  3.95222349, 12.53965359])
```


scipy.linalg.eigh_tridiagonal

```
scipy.linalg.eigh_tridiagonal(d, e, eigvals_only=False, select='a', select_range=None,
                             check_finite=True, tol=0.0, lapack_driver='auto')
```

Solve eigenvalue problem for a real symmetric tridiagonal matrix.

Find eigenvalues w and optionally right eigenvectors v of a :

$$\begin{aligned} a v[:,i] &= w[i] v[:,i] \\ v.H v &= \text{identity} \end{aligned}$$

For a real symmetric matrix a with diagonal elements d and off-diagonal elements e .

Parameters

- d** [ndarray, shape (ndim,)] The diagonal elements of the array.
e [ndarray, shape (ndim-1,)] The off-diagonal elements of the array.
select [{'a', 'v', 'i'}, optional] Which eigenvalues to calculate

select	calculated
'a'	All eigenvalues
'v'	Eigenvalues in the interval (min, max]
'i'	Eigenvalues with indices $\min \leq i \leq \max$

select_range

[(min, max), optional] Range of selected eigenvalues

check_finite

[bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

tol

[float] The absolute tolerance to which each eigenvalue is required (only used when 'stebz' is the *lapack_driver*). An eigenvalue (or cluster) is considered to have converged if it lies in an interval of this width. If ≤ 0 . (default), the value $\text{eps} * |a|$ is used where eps is the machine precision, and $|a|$ is the 1-norm of the matrix a .

lapack_driver

[str] LAPACK function to use, can be 'auto', 'stemr', 'stebz', 'sterf', or 'stev'. When 'auto' (default), it will use 'stemr' if *select*='a' and 'stebz' otherwise. When 'stebz' is used to find the eigenvalues and *eigvals_only*=False, then a second LAPACK call (to ?STEIN) is used to find the corresponding eigenvectors. 'sterf' can only be used when *eigvals_only*=True and *select*='a'. 'stev' can only be used when *select*='a'.

Returns

- w** [(M,) ndarray] The eigenvalues, in ascending order, each repeated according to its multiplicity.
v [(M, M) ndarray] The normalized eigenvector corresponding to the eigenvalue $w[i]$ is the column $v[:, i]$.

Raises**LinAlgError**

If eigenvalue computation does not converge.

See also:

[eigvalsh_tridiagonal](#)

eigenvalues of symmetric/Hermitian tridiagonal matrices

eig

eigenvalues and right eigenvectors for non-symmetric arrays

eigh

eigenvalues and right eigenvectors for symmetric/Hermitian arrays

eig_banded

eigenvalues and right eigenvectors for symmetric/Hermitian band matrices

Notes

This function makes use of LAPACK S/DSTEMR routines.

Examples

```
>>> from scipy.linalg import eigh_tridiagonal
>>> d = 3*np.ones(4)
>>> e = -1*np.ones(3)
>>> w, v = eigh_tridiagonal(d, e)
>>> A = np.diag(d) + np.diag(e, k=1) + np.diag(e, k=-1)
>>> np.allclose(A @ v - v @ np.diag(w), np.zeros((4, 4)))
True
```

scipy.linalg.eigvalsh_tridiagonal

`scipy.linalg.eigvalsh_tridiagonal(d, e, select='a', select_range=None, check_finite=True, tol=0.0, lapack_driver='auto')`

Solve eigenvalue problem for a real symmetric tridiagonal matrix.

Find eigenvalues w of a :

```
a v[:,i] = w[i] v[:,i]
v.H v = identity
```

For a real symmetric matrix a with diagonal elements d and off-diagonal elements e .

Parameters

- d** [ndarray, shape (ndim,)] The diagonal elements of the array.
- e** [ndarray, shape (ndim-1,)] The off-diagonal elements of the array.
- select** [{'a', 'v', 'i'}, optional] Which eigenvalues to calculate

select	calculated
'a'	All eigenvalues
'v'	Eigenvalues in the interval (min, max]
'i'	Eigenvalues with indices $\min \leq i \leq \max$

select_range

[(min, max), optional] Range of selected eigenvalues

check_finite

[bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

tol [float] The absolute tolerance to which each eigenvalue is required (only used when `lapack_driver='stebz'`). An eigenvalue (or cluster) is considered to have converged if it lies in an interval of this width. If ≤ 0 . (default), the value $\text{eps} * |a|$ is used where eps is the machine precision, and $|a|$ is the 1-norm of the matrix a .

lapack_driver

[str] LAPACK function to use, can be 'auto', 'stemr', 'stebz', 'sterf', or 'stev'. When 'auto' (default), it will use 'stemr' if `select='a'` and 'stebz' otherwise. 'sterf' and 'stev' can only be used when `select='a'`.

Returns

w [(M,) ndarray] The eigenvalues, in ascending order, each repeated according to its multiplicity.

Raises**LinAlgError**

If eigenvalue computation does not converge.

See also:*eigh_tridiagonal*

eigenvalues and right eigenvectors for symmetric/Hermitian tridiagonal matrices

Examples

```
>>> from scipy.linalg import eigvalsh_tridiagonal, eigvalsh
>>> d = 3*np.ones(4)
>>> e = -1*np.ones(3)
>>> w = eigvalsh_tridiagonal(d, e)
>>> A = np.diag(d) + np.diag(e, k=1) + np.diag(e, k=-1)
>>> w2 = eigvalsh(A) # Verify with other eigenvalue routines
>>> np.allclose(w - w2, np.zeros(4))
True
```

6.10.3 Decompositions

<code>lu(a[, permute_l, overwrite_a, check_finite])</code>	Compute pivoted LU decomposition of a matrix.
<code>lu_factor(a[, overwrite_a, check_finite])</code>	Compute pivoted LU decomposition of a matrix.
<code>lu_solve(lu_and_piv, b[, trans, ...])</code>	Solve an equation system, $ax = b$, given the LU factorization of a
<code>svd(a[, full_matrices, compute_uv, ...])</code>	Singular Value Decomposition.
<code>svdvals(a[, overwrite_a, check_finite])</code>	Compute singular values of a matrix.
<code>diagsvd(s, M, N)</code>	Construct the sigma matrix in SVD from singular values and size M, N .
<code>orth(A[, rcond])</code>	Construct an orthonormal basis for the range of A using SVD
<code>null_space(A[, rcond])</code>	Construct an orthonormal basis for the null space of A using SVD
<code>ldl(A[, lower, hermitian, overwrite_a, ...])</code>	Computes the LDLt or Bunch-Kaufman factorization of a symmetric/ hermitian matrix.

continues on next page

Table 92 – continued from previous page

<code>cholesky(a[, lower, overwrite_a, check_finite])</code>	Compute the Cholesky decomposition of a matrix.
<code>cholesky_banded(ab[, overwrite_ab, lower, ...])</code>	Cholesky decompose a banded Hermitian positive-definite matrix
<code>cho_factor(a[, lower, overwrite_a, check_finite])</code>	Compute the Cholesky decomposition of a matrix, to use in <code>cho_solve</code>
<code>cho_solve(c_and_lower, b[, overwrite_b, ...])</code>	Solve the linear equations $Ax = b$, given the Cholesky factorization of A .
<code>cho_solve_banded(cb_and_lower, b[, ...])</code>	Solve the linear equations $Ax = b$, given the Cholesky factorization of the banded Hermitian A .
<code>polar(a[, side])</code>	Compute the polar decomposition.
<code>qr(a[, overwrite_a, lwork, mode, pivoting, ...])</code>	Compute QR decomposition of a matrix.
<code>qr_multiply(a, c[, mode, pivoting, ...])</code>	Calculate the QR decomposition and multiply Q with a matrix.
<code>qr_update(Q, R, u, v[, overwrite_qruv, ...])</code>	Rank- k QR update
<code>qr_delete(Q, R, k, int p=1[, which, ...])</code>	QR downdate on row or column deletions
<code>qr_insert(Q, R, u, k[, which, rcond, ...])</code>	QR update on row or column insertions
<code>rq(a[, overwrite_a, lwork, mode, check_finite])</code>	Compute RQ decomposition of a matrix.
<code>qz(A, B[, output, lwork, sort, overwrite_a, ...])</code>	QZ decomposition for generalized eigenvalues of a pair of matrices.
<code>ordqz(A, B[, sort, output, overwrite_a, ...])</code>	QZ decomposition for a pair of matrices with reordering.
<code>schur(a[, output, lwork, overwrite_a, sort, ...])</code>	Compute Schur decomposition of a matrix.
<code>rsf2csf(T, Z[, check_finite])</code>	Convert real Schur form to complex Schur form.
<code>hessenberg(a[, calc_q, overwrite_a, ...])</code>	Compute Hessenberg form of a matrix.
<code>cdf2rdf(w, v)</code>	Converts complex eigenvalues w and eigenvectors v to real eigenvalues in a block diagonal form $w_{\mathbb{R}}$ and the associated real eigenvectors $v_{\mathbb{R}}$, such that.
<code>cssin(X[, p, q, separate, swap_sign, ...])</code>	Compute the cosine-sine (CS) decomposition of an orthogonal/unitary matrix.

scipy.linalg.lu

`scipy.linalg.lu(a, permute_l=False, overwrite_a=False, check_finite=True)`

Compute pivoted LU decomposition of a matrix.

The decomposition is:

$$A = P L U$$

where P is a permutation matrix, L lower triangular with unit diagonal elements, and U upper triangular.

Parameters

- a** [(M, N) array_like] Array to decompose
- permute_l** [bool, optional] Perform the multiplication $P*L$ (Default: do not permute)
- overwrite_a** [bool, optional] Whether to overwrite data in a (may improve performance)
- check_finite** [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

(If `permute_l == False`)

p [(M, M) ndarray] Permutation matrix
l [(M, K) ndarray] Lower triangular or trapezoidal matrix with unit diagonal. $K = \min(M, N)$
u [(K, N) ndarray] Upper triangular or trapezoidal matrix
(If permute_l == True)
pl [(M, K) ndarray] Permuted L matrix. $K = \min(M, N)$
u [(K, N) ndarray] Upper triangular or trapezoidal matrix

Notes

This is a LU factorization routine written for SciPy.

Examples

```

>>> from scipy.linalg import lu
>>> A = np.array([[2, 5, 8, 7], [5, 2, 2, 8], [7, 5, 6, 6], [5, 4, 4, 8]])
>>> p, l, u = lu(A)
>>> np.allclose(A - p @ l @ u, np.zeros((4, 4)))
True

```

scipy.linalg.lu_factor

`scipy.linalg.lu_factor(a, overwrite_a=False, check_finite=True)`

Compute pivoted LU decomposition of a matrix.

The decomposition is:

$$A = P L U$$

where P is a permutation matrix, L lower triangular with unit diagonal elements, and U upper triangular.

Parameters

a [(M, M) array_like] Matrix to decompose
overwrite_a [bool, optional] Whether to overwrite data in A (may increase performance)
check_finite [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

lu [(N, N) ndarray] Matrix containing U in its upper triangle, and L in its lower triangle. The unit diagonal elements of L are not stored.
piv [(N,) ndarray] Pivot indices representing the permutation matrix P: row i of matrix was interchanged with row piv[i].

See also:

[lu_solve](#)

solve an equation system using the LU factorization of a matrix

Notes

This is a wrapper to the *GETRF routines from LAPACK.

Examples

```
>>> from scipy.linalg import lu_factor
>>> A = np.array([[2, 5, 8, 7], [5, 2, 2, 8], [7, 5, 6, 6], [5, 4, 4, 8]])
>>> lu, piv = lu_factor(A)
>>> piv
array([2, 2, 3, 3], dtype=int32)
```

Convert LAPACK's `piv` array to NumPy index and test the permutation

```
>>> piv_py = [2, 0, 3, 1]
>>> L, U = np.tril(lu, k=-1) + np.eye(4), np.triu(lu)
>>> np.allclose(A[piv_py] - L @ U, np.zeros((4, 4)))
True
```

scipy.linalg.lu_solve

`scipy.linalg.lu_solve` (*lu_and_piv*, *b*, *trans=0*, *overwrite_b=False*, *check_finite=True*)

Solve an equation system, $a x = b$, given the LU factorization of *a*

Parameters

- (lu, piv)** Factorization of the coefficient matrix *a*, as given by `lu_factor`
- b** [array] Right-hand side
- trans** [{0, 1, 2}, optional] Type of system to solve:

trans	system
0	$a x = b$
1	$a^T x = b$
2	$a^H x = b$

overwrite_b

[bool, optional] Whether to overwrite data in *b* (may increase performance)

check_finite

[bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

- x** [array] Solution to the system

See also:

`lu_factor`

LU factorize a matrix

Examples

```
>>> from scipy.linalg import lu_factor, lu_solve
>>> A = np.array([[2, 5, 8, 7], [5, 2, 2, 8], [7, 5, 6, 6], [5, 4, 4, 8]])
>>> b = np.array([1, 1, 1, 1])
>>> lu, piv = lu_factor(A)
>>> x = lu_solve((lu, piv), b)
>>> np.allclose(A @ x - b, np.zeros((4,)))
True
```

scipy.linalg.svd

`scipy.linalg.svd(a, full_matrices=True, compute_uv=True, overwrite_a=False, check_finite=True, lapack_driver='gesdd')`
Singular Value Decomposition.

Factorizes the matrix a into two unitary matrices U and Vh , and a 1-D array s of singular values (real, non-negative) such that $a == U @ S @ Vh$, where S is a suitably shaped matrix of zeros with main diagonal s .

Parameters

- a** [(M, N) array_like] Matrix to decompose.
- full_matrices** [bool, optional] If True (default), U and Vh are of shape (M, M) , (N, N) . If False, the shapes are (M, K) and (K, N) , where $K = \min(M, N)$.
- compute_uv** [bool, optional] Whether to compute also U and Vh in addition to s . Default is True.
- overwrite_a** [bool, optional] Whether to overwrite a ; may improve performance. Default is False.
- check_finite** [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.
- lapack_driver** [{'gesdd', 'gesvd'}, optional] Whether to use the more efficient divide-and-conquer approach ('gesdd') or general rectangular approach ('gesvd') to compute the SVD. MATLAB and Octave use the 'gesvd' approach. Default is 'gesdd'.
New in version 0.18.

Returns

- U** [ndarray] Unitary matrix having left singular vectors as columns. Of shape (M, M) or (M, K) , depending on *full_matrices*.
- s** [ndarray] The singular values, sorted in non-increasing order. Of shape $(K,)$, with $K = \min(M, N)$.
- Vh** [ndarray] Unitary matrix having right singular vectors as rows. Of shape (N, N) or (K, N) depending on *full_matrices*.

For compute_uv=False, only s is returned.

Raises

- LinAlgError**
If SVD computation does not converge.

See also:

svdvals

Compute singular values of a matrix.

diagsvd

Construct the Sigma matrix, given the vector *s*.

Examples

```
>>> from scipy import linalg
>>> m, n = 9, 6
>>> a = np.random.randn(m, n) + 1.j*np.random.randn(m, n)
>>> U, s, Vh = linalg.svd(a)
>>> U.shape, s.shape, Vh.shape
((9, 9), (6,), (6, 6))
```

Reconstruct the original matrix from the decomposition:

```
>>> sigma = np.zeros((m, n))
>>> for i in range(min(m, n)):
...     sigma[i, i] = s[i]
>>> a1 = np.dot(U, np.dot(sigma, Vh))
>>> np.allclose(a, a1)
True
```

Alternatively, use `full_matrices=False` (notice that the shape of *U* is then (m, n) instead of (m, m)):

```
>>> U, s, Vh = linalg.svd(a, full_matrices=False)
>>> U.shape, s.shape, Vh.shape
((9, 6), (6,), (6, 6))
>>> S = np.diag(s)
>>> np.allclose(a, np.dot(U, np.dot(S, Vh)))
True
```

```
>>> s2 = linalg.svd(a, compute_uv=False)
>>> np.allclose(s, s2)
True
```

scipy.linalg.svdvals

`scipy.linalg.svdvals` (*a*, *overwrite_a=False*, *check_finite=True*)

Compute singular values of a matrix.

Parameters

a [(M, N) array_like] Matrix to decompose.

overwrite_a [bool, optional] Whether to overwrite *a*; may improve performance. Default is False.

check_finite [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

s [(min(M, N),) ndarray] The singular values, sorted in decreasing order.

Raises

LinAlgError

If SVD computation does not converge.

See also:

svd

Compute the full singular value decomposition of a matrix.

diagsvd

Construct the Sigma matrix, given the vector *s*.

Notes

`svdvals(a)` only differs from `svd(a, compute_uv=False)` by its handling of the edge case of empty *a*, where it returns an empty sequence:

```
>>> a = np.empty((0, 2))
>>> from scipy.linalg import svdvals
>>> svdvals(a)
array([], dtype=float64)
```

Examples

```
>>> from scipy.linalg import svdvals
>>> m = np.array([[1.0, 0.0],
...              [2.0, 3.0],
...              [1.0, 1.0],
...              [0.0, 2.0],
...              [1.0, 0.0]])
>>> svdvals(m)
array([ 4.28091555,  1.63516424])
```

We can verify the maximum singular value of *m* by computing the maximum length of *m.dot(u)* over all the unit vectors *u* in the (x,y) plane. We approximate “all” the unit vectors with a large sample. Because of linearity, we only need the unit vectors with angles in [0, pi].

```
>>> t = np.linspace(0, np.pi, 2000)
>>> u = np.array([np.cos(t), np.sin(t)])
>>> np.linalg.norm(m.dot(u), axis=0).max()
4.2809152422538475
```

p is a projection matrix with rank 1. With exact arithmetic, its singular values would be [1, 0, 0, 0].

```
>>> v = np.array([0.1, 0.3, 0.9, 0.3])
>>> p = np.outer(v, v)
>>> svdvals(p)
array([ 1.00000000e+00,  2.02021698e-17,  1.56692500e-17,
        8.15115104e-34])
```

The singular values of an orthogonal matrix are all 1. Here, we create a random orthogonal matrix by using the `rvs()` method of `scipy.stats.ortho_group`.

```
>>> from scipy.stats import ortho_group
>>> np.random.seed(123)
>>> orth = ortho_group.rvs(4)
>>> svdvals(orth)
array([ 1.,  1.,  1.,  1.]
```

scipy.linalg.diagsvd

`scipy.linalg.diagsvd`(*s*, *M*, *N*)

Construct the sigma matrix in SVD from singular values and size *M*, *N*.

Parameters

s	[(<i>M</i> ,) or (<i>N</i> ,) array_like] Singular values
M	[int] Size of the matrix whose singular values are <i>s</i> .
N	[int] Size of the matrix whose singular values are <i>s</i> .

Returns

S	[(<i>M</i> , <i>N</i>) ndarray] The S-matrix in the singular value decomposition
----------	--

See also:

[*svd*](#)

Singular value decomposition of a matrix

[*svdvals*](#)

Compute singular values of a matrix.

Examples

```
>>> from scipy.linalg import diagsvd
>>> vals = np.array([1, 2, 3]) # The array representing the computed svd
>>> diagsvd(vals, 3, 4)
array([[1, 0, 0, 0],
       [0, 2, 0, 0],
       [0, 0, 3, 0]])
>>> diagsvd(vals, 4, 3)
array([[1, 0, 0],
       [0, 2, 0],
       [0, 0, 3],
       [0, 0, 0]])
```

scipy.linalg.orth

`scipy.linalg.orth(A, rcond=None)`

Construct an orthonormal basis for the range of A using SVD

Parameters

A	[(M, N) array_like] Input array
rcond	[float, optional] Relative condition number. Singular values s smaller than $rcond * \max(s)$ are considered zero. Default: floating point $\epsilon * \max(M,N)$.

Returns

Q	[(M, K) ndarray] Orthonormal basis for the range of A. K = effective rank of A, as determined by rcond
----------	--

See also:

[*svd*](#)

Singular value decomposition of a matrix

[*null_space*](#)

Matrix null space

Examples

```
>>> from scipy.linalg import orth
>>> A = np.array([[2, 0, 0], [0, 5, 0]]) # rank 2 array
>>> orth(A)
array([[0., 1.],
       [1., 0.]])
>>> orth(A.T)
array([[0., 1.],
       [1., 0.],
       [0., 0.]])
```

scipy.linalg.null_space

`scipy.linalg.null_space(A, rcond=None)`

Construct an orthonormal basis for the null space of A using SVD

Parameters

A	[(M, N) array_like] Input array
rcond	[float, optional] Relative condition number. Singular values s smaller than $rcond * \max(s)$ are considered zero. Default: floating point $\epsilon * \max(M,N)$.

Returns

Z	[(N, K) ndarray] Orthonormal basis for the null space of A. K = dimension of effective null space, as determined by rcond
----------	---

See also:

[*svd*](#)

Singular value decomposition of a matrix

orth

Matrix range

Examples

1-D null space:

```
>>> from scipy.linalg import null_space
>>> A = np.array([[1, 1], [1, 1]])
>>> ns = null_space(A)
>>> ns * np.sign(ns[0,0]) # Remove the sign ambiguity of the vector
array([[ 0.70710678],
       [-0.70710678]])
```

2-D null space:

```
>>> B = np.random.rand(3, 5)
>>> Z = null_space(B)
>>> Z.shape
(5, 2)
>>> np.allclose(B.dot(Z), 0)
True
```

The basis vectors are orthonormal (up to rounding error):

```
>>> Z.T.dot(Z)
array([[ 1.00000000e+00,   6.92087741e-17],
       [  6.92087741e-17,   1.00000000e+00]])
```

scipy.linalg.ldl`scipy.linalg.ldl` (*A*, *lower=True*, *hermitian=True*, *overwrite_a=False*, *check_finite=True*)

Computes the LDLt or Bunch-Kaufman factorization of a symmetric/ hermitian matrix.

This function returns a block diagonal matrix *D* consisting blocks of size at most 2x2 and also a possibly permuted unit lower triangular matrix *L* such that the factorization $A = L D L^H$ or $A = L D L^T$ holds. If *lower* is *False* then (again possibly permuted) upper triangular matrices are returned as outer factors.

The permutation array can be used to triangularize the outer factors simply by a row shuffle, i.e., `lu[perm, :]` is an upper/lower triangular matrix. This is also equivalent to multiplication with a permutation matrix `P.dot(lu)`, where *P* is a column-permuted identity matrix `I[:, perm]`.

Depending on the value of the boolean *lower*, only upper or lower triangular part of the input array is referenced. Hence, a triangular matrix on entry would give the same result as if the full matrix is supplied.

Parameters

- a** [array_like] Square input array
- lower** [bool, optional] This switches between the lower and upper triangular outer factors of the factorization. Lower triangular (*lower=True*) is the default.
- hermitian** [bool, optional] For complex-valued arrays, this defines whether $a = a.conj().T$ or $a = a.T$ is assumed. For real-valued arrays, this switch has no effect.
- overwrite_a** [bool, optional] Allow overwriting data in *a* (may enhance performance). The default is *False*.

check_finite

[bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

lu [ndarray] The (possibly) permuted upper/lower triangular outer factor of the factorization.
d [ndarray] The block diagonal multiplier of the factorization.
perm [ndarray] The row-permutation index array that brings lu into triangular form.

Raises**ValueError**

If input array is not square.

ComplexWarning

If a complex-valued array with nonzero imaginary parts on the diagonal is given and hermitian is set to True.

See also:

[*cholesky*](#), [*lu*](#)

Notes

This function uses ?SYTRF routines for symmetric matrices and ?HETRF routines for Hermitian matrices from LAPACK. See [1] for the algorithm details.

Depending on the `lower` keyword value, only lower or upper triangular part of the input array is referenced. Moreover, this keyword also defines the structure of the outer factors of the factorization.

New in version 1.1.0.

References

[1]

Examples

Given an upper triangular array *a* that represents the full symmetric array with its entries, obtain *l*, 'd' and the permutation vector *perm*:

```
>>> import numpy as np
>>> from scipy.linalg import ldL
>>> a = np.array([[2, -1, 3], [0, 2, 0], [0, 0, 1]])
>>> lu, d, perm = ldL(a, lower=0) # Use the upper part
>>> lu
array([[ 0. ,  0. ,  1. ],
       [ 0. ,  1. , -0.5],
       [ 1. ,  1. ,  1.5]])
>>> d
array([[ -5. ,  0. ,  0. ],
       [ 0. ,  1.5,  0. ],
       [ 0. ,  0. ,  2. ]])
```

(continues on next page)

(continued from previous page)

```

>>> perm
array([2, 1, 0])
>>> lu[perm, :]
array([[ 1. ,  1. ,  1.5],
       [ 0. ,  1. , -0.5],
       [ 0. ,  0. ,  1. ]])
>>> lu.dot(d).dot(lu.T)
array([[ 2., -1.,  3.],
       [-1.,  2.,  0.],
       [ 3.,  0.,  1.]])

```

scipy.linalg.cholesky

`scipy.linalg.cholesky` (*a*, *lower=False*, *overwrite_a=False*, *check_finite=True*)

Compute the Cholesky decomposition of a matrix.

Returns the Cholesky decomposition, $A = LL^*$ or $A = U^*U$ of a Hermitian positive-definite matrix *A*.

Parameters

- a** [(M, M) array_like] Matrix to be decomposed
- lower** [bool, optional] Whether to compute the upper- or lower-triangular Cholesky factorization. Default is upper-triangular.
- overwrite_a** [bool, optional] Whether to overwrite data in *a* (may improve performance).
- check_finite** [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

- c** [(M, M) ndarray] Upper- or lower-triangular Cholesky factor of *a*.

Raises

- LinAlgError** [if decomposition fails.]

Examples

```

>>> from scipy.linalg import cholesky
>>> a = np.array([[1, -2j], [2j, 5]])
>>> L = cholesky(a, lower=True)
>>> L
array([[ 1.+0.j,  0.+0.j],
       [ 0.+2.j,  1.+0.j]])
>>> L @ L.T.conj()
array([[ 1.+0.j,  0.-2.j],
       [ 0.+2.j,  5.+0.j]])

```

scipy.linalg.cholesky_banded

`scipy.linalg.cholesky_banded` (*ab*, *overwrite_ab=False*, *lower=False*, *check_finite=True*)

Cholesky decompose a banded Hermitian positive-definite matrix

The matrix *a* is stored in *ab* either in lower-diagonal or upper-diagonal ordered form:

```
ab[u + i - j, j] == a[i, j]      (if upper form; i <= j)
ab[    i - j, j] == a[i, j]      (if lower form; i >= j)
```

Example of *ab* (shape of *a* is (6,6), *u*=2):

```
upper form:
*   *   a02 a13 a24 a35
*   a01 a12 a23 a34 a45
a00 a11 a22 a33 a44 a55

lower form:
a00 a11 a22 a33 a44 a55
a10 a21 a32 a43 a54 *
a20 a31 a42 a53 *   *
```

Parameters

ab [(*u* + 1, *M*) array_like] Banded matrix

overwrite_ab [bool, optional] Discard data in *ab* (may enhance performance)

lower [bool, optional] Is the matrix in the lower form. (Default is upper form)

check_finite [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

c [(*u* + 1, *M*) ndarray] Cholesky factorization of *a*, in the same banded format as *ab*

See also:

`cho_solve_banded`

Solve a linear set equations, given the Cholesky factorization of a banded Hermitian.

Examples

```
>>> from scipy.linalg import cholesky_banded
>>> from numpy import allclose, zeros, diag
>>> Ab = np.array([[0, 0, 1j, 2, 3j], [0, -1, -2, 3, 4], [9, 8, 7, 6, 9]])
>>> A = np.diag(Ab[0, 2:], k=2) + np.diag(Ab[1, 1:], k=1)
>>> A = A + A.conj().T + np.diag(Ab[2, :])
>>> c = cholesky_banded(Ab)
>>> C = np.diag(c[0, 2:], k=2) + np.diag(c[1, 1:], k=1) + np.diag(c[2, :])
>>> np.allclose(C.conj().T @ C - A, np.zeros((5, 5)))
True
```

scipy.linalg.cho_factor

`scipy.linalg.cho_factor` (*a*, *lower=False*, *overwrite_a=False*, *check_finite=True*)

Compute the Cholesky decomposition of a matrix, to use in `cho_solve`

Returns a matrix containing the Cholesky decomposition, $A = L L^*$ or $A = U^* U$ of a Hermitian positive-definite matrix *a*. The return value can be directly used as the first parameter to `cho_solve`.

Warning: The returned matrix also contains random data in the entries not used by the Cholesky decomposition. If you need to zero these entries, use the function `cholesky` instead.

Parameters

- a** [(M, M) array_like] Matrix to be decomposed
- lower** [bool, optional] Whether to compute the upper or lower triangular Cholesky factorization (Default: upper-triangular)
- overwrite_a** [bool, optional] Whether to overwrite data in *a* (may improve performance)
- check_finite** [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

- c** [(M, M) ndarray] Matrix whose upper or lower triangle contains the Cholesky factor of *a*. Other parts of the matrix contain random data.
- lower** [bool] Flag indicating whether the factor is in the lower or upper triangle

Raises

- LinAlgError**
Raised if decomposition fails.

See also:

[`cho_solve`](#)

Solve a linear set equations using the Cholesky factorization of a matrix.

Examples

```
>>> from scipy.linalg import cho_factor
>>> A = np.array([[9, 3, 1, 5], [3, 7, 5, 1], [1, 5, 9, 2], [5, 1, 2, 6]])
>>> c, low = cho_factor(A)
>>> c
array([[3.         , 1.         , 0.33333333, 1.66666667],
       [3.         , 2.44948974, 1.90515869, -0.27216553],
       [1.         , 5.         , 2.29330749, 0.8559528 ],
       [5.         , 1.         , 2.         , 1.55418563]])
>>> np.allclose(np.triu(c).T @ np.triu(c) - A, np.zeros((4, 4)))
True
```


scipy.linalg.cho_solve

`scipy.linalg.cho_solve(c_and_lower, b, overwrite_b=False, check_finite=True)`

Solve the linear equations $Ax = b$, given the Cholesky factorization of A .

Parameters

- (c, lower)** [tuple, (array, bool)] Cholesky factorization of a , as given by `cho_factor`
- b** [array] Right-hand side
- overwrite_b** [bool, optional] Whether to overwrite data in b (may improve performance)
- check_finite** [bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

- x** [array] The solution to the system $Ax = b$

See also:

[cho_factor](#)

Cholesky factorization of a matrix

Examples

```
>>> from scipy.linalg import cho_factor, cho_solve
>>> A = np.array([[9, 3, 1, 5], [3, 7, 5, 1], [1, 5, 9, 2], [5, 1, 2, 6]])
>>> c, low = cho_factor(A)
>>> x = cho_solve((c, low), [1, 1, 1, 1])
>>> np.allclose(A @ x - [1, 1, 1, 1], np.zeros(4))
True
```

scipy.linalg.cho_solve_banded

`scipy.linalg.cho_solve_banded(cb_and_lower, b, overwrite_b=False, check_finite=True)`

Solve the linear equations $Ax = b$, given the Cholesky factorization of the banded Hermitian A .

Parameters

- (cb, lower)** [tuple, (ndarray, bool)] cb is the Cholesky factorization of A , as given by `cholesky_banded`. $lower$ must be the same value that was given to `cholesky_banded`.
- b** [array_like] Right-hand side
- overwrite_b** [bool, optional] If True, the function will overwrite the values in b .
- check_finite** [bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

- x** [array] The solution to the system $Ax = b$

See also:

cholesky_banded

Cholesky factorization of a banded matrix

Notes

New in version 0.8.0.

Examples

```
>>> from scipy.linalg import cholesky_banded, cho_solve_banded
>>> Ab = np.array([[0, 0, 1j, 2, 3j], [0, -1, -2, 3, 4], [9, 8, 7, 6, 9]])
>>> A = np.diag(Ab[0,2:], k=2) + np.diag(Ab[1,1:], k=1)
>>> A = A + A.conj().T + np.diag(Ab[2, :])
>>> c = cholesky_banded(Ab)
>>> x = cho_solve_banded((c, False), np.ones(5))
>>> np.allclose(A @ x - np.ones(5), np.zeros(5))
True
```

scipy.linalg.polar

`scipy.linalg.polar(a, side='right')`

Compute the polar decomposition.

Returns the factors of the polar decomposition [1] u and p such that $a = up$ (if *side* is “right”) or $a = pu$ (if *side* is “left”), where p is positive semidefinite. Depending on the shape of a , either the rows or columns of u are orthonormal. When a is a square array, u is a square unitary array. When a is not square, the “canonical polar decomposition” [2] is computed.

Parameters

a [(m, n) array_like] The array to be factored.
side [{'left', 'right'}, optional] Determines whether a right or left polar decomposition is computed. If *side* is “right”, then $a = up$. If *side* is “left”, then $a = pu$. The default is “right”.

Returns

u [(m, n) ndarray] If a is square, then u is unitary. If $m > n$, then the columns of a are orthonormal, and if $m < n$, then the rows of u are orthonormal.
p [ndarray] p is Hermitian positive semidefinite. If a is nonsingular, p is positive definite. The shape of p is (n, n) or (m, m), depending on whether *side* is “right” or “left”, respectively.

References

[1], [2]

Examples

```

>>> from scipy.linalg import polar
>>> a = np.array([[1, -1], [2, 4]])
>>> u, p = polar(a)
>>> u
array([[ 0.85749293, -0.51449576],
       [ 0.51449576,  0.85749293]])
>>> p
array([[ 1.88648444,  1.2004901 ],
       [ 1.2004901 ,  3.94446746]])

```

A non-square example, with $m < n$:

```

>>> b = np.array([[0.5, 1, 2], [1.5, 3, 4]])
>>> u, p = polar(b)
>>> u
array([[ -0.21196618, -0.42393237,  0.88054056],
       [ 0.39378971,  0.78757942,  0.4739708 ]])
>>> p
array([[ 0.48470147,  0.96940295,  1.15122648],
       [ 0.96940295,  1.9388059 ,  2.30245295],
       [ 1.15122648,  2.30245295,  3.65696431]])
>>> u.dot(p)    # Verify the decomposition.
array([[ 0.5,  1. ,  2. ],
       [ 1.5,  3. ,  4. ]])
>>> u.dot(u.T)  # The rows of u are orthonormal.
array([[ 1.00000000e+00, -2.07353665e-17],
       [-2.07353665e-17,  1.00000000e+00]])

```

Another non-square example, with $m > n$:

```

>>> c = b.T
>>> u, p = polar(c)
>>> u
array([[ -0.21196618,  0.39378971],
       [-0.42393237,  0.78757942],
       [ 0.88054056,  0.4739708 ]])
>>> p
array([[ 1.23116567,  1.93241587],
       [ 1.93241587,  4.84930602]])
>>> u.dot(p)    # Verify the decomposition.
array([[ 0.5,  1.5],
       [ 1. ,  3. ],
       [ 2. ,  4. ]])
>>> u.T.dot(u)  # The columns of u are orthonormal.
array([[ 1.00000000e+00, -1.26363763e-16],
       [-1.26363763e-16,  1.00000000e+00]])

```

scipy.linalg.qr

`scipy.linalg.qr(a, overwrite_a=False, lwork=None, mode='full', pivoting=False, check_finite=True)`

Compute QR decomposition of a matrix.

Calculate the decomposition $A = Q R$ where Q is unitary/orthogonal and R upper triangular.

Parameters

- a** [(M, N) array_like] Matrix to be decomposed
- overwrite_a** [bool, optional] Whether data in *a* is overwritten (may improve performance if *overwrite_a* is set to True by reusing the existing input data structure rather than creating a new one.)
- lwork** [int, optional] Work array size, `lwork >= a.shape[1]`. If None or -1, an optimal size is computed.
- mode** [{'full', 'r', 'economic', 'raw'}, optional] Determines what information is to be returned: either both Q and R ('full', default), only R ('r') or both Q and R but computed in economy-size ('economic', see Notes). The final option 'raw' (added in SciPy 0.11) makes the function return two matrices (Q , τ) in the internal format used by LAPACK.
- pivoting** [bool, optional] Whether or not factorization should include pivoting for rank-revealing qr decomposition. If `pivoting`, compute the decomposition $A P = Q R$ as above, but where P is chosen such that the diagonal of R is non-increasing.
- check_finite** [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

- Q** [float or complex ndarray] Of shape (M, M), or (M, K) for `mode='economic'`. Not returned if `mode='r'`.
- R** [float or complex ndarray] Of shape (M, N), or (K, N) for `mode='economic'`. $K = \min(M, N)$.
- P** [int ndarray] Of shape (N,) for `pivoting=True`. Not returned if `pivoting=False`.

Raises

- LinAlgError**
Raised if decomposition fails

Notes

This is an interface to the LAPACK routines `dgeqrf`, `zgeqrf`, `dorgqr`, `zungqr`, `dgeqp3`, and `zgeqp3`.

If `mode=economic`, the shapes of Q and R are (M, K) and (K, N) instead of (M,M) and (M,N), with $K=\min(M, N)$.

Examples

```
>>> from scipy import linalg
>>> a = np.random.randn(9, 6)
```

```
>>> q, r = linalg.qr(a)
>>> np.allclose(a, np.dot(q, r))
True
>>> q.shape, r.shape
((9, 9), (9, 6))
```

```
>>> r2 = linalg.qr(a, mode='r')
>>> np.allclose(r, r2)
True
```

```
>>> q3, r3 = linalg.qr(a, mode='economic')
>>> q3.shape, r3.shape
((9, 6), (6, 6))
```

```
>>> q4, r4, p4 = linalg.qr(a, pivoting=True)
>>> d = np.abs(np.diag(r4))
>>> np.all(d[1:] <= d[:-1])
True
>>> np.allclose(a[:, p4], np.dot(q4, r4))
True
>>> q4.shape, r4.shape, p4.shape
((9, 9), (9, 6), (6,))
```

```
>>> q5, r5, p5 = linalg.qr(a, mode='economic', pivoting=True)
>>> q5.shape, r5.shape, p5.shape
((9, 6), (6, 6), (6,))
```

scipy.linalg.qr_multiply

`scipy.linalg.qr_multiply(a, c, mode='right', pivoting=False, conjugate=False, overwrite_a=False, overwrite_c=False)`

Calculate the QR decomposition and multiply Q with a matrix.

Calculate the decomposition $A = QR$ where Q is unitary/orthogonal and R upper triangular. Multiply Q with a vector or a matrix c.

Parameters

- a** [(M, N), array_like] Input array
- c** [array_like] Input array to be multiplied by q.
- mode** [{'left', 'right'}, optional] Q @ c is returned if mode is 'left', c @ Q is returned if mode is 'right'. The shape of c must be appropriate for the matrix multiplications, if mode is 'left', $\min(a.shape) == c.shape[0]$, if mode is 'right', $a.shape[0] == c.shape[1]$.
- pivoting** [bool, optional] Whether or not factorization should include pivoting for rank-revealing qr decomposition, see the documentation of qr.
- conjugate** [bool, optional] Whether Q should be complex-conjugated. This might be faster than explicit conjugation.

overwrite_a

[bool, optional] Whether data in a is overwritten (may improve performance)

overwrite_c

[bool, optional] Whether data in c is overwritten (may improve performance). If this is used, c must be big enough to keep the result, i.e. `c.shape[0] = a.shape[0]` if mode is 'left'.

Returns

CQ [ndarray] The product of Q and c.
R [(K, N), ndarray] R array of the resulting QR factorization where $K = \min(M, N)$.
P [(N,) ndarray] Integer pivot array. Only returned when `pivoting=True`.

Raises
LinAlgError

Raised if QR decomposition fails.

Notes

This is an interface to the LAPACK routines `?GEQRF`, `?ORMQR`, `?UNMQR`, and `?GEQP3`.

New in version 0.11.0.

Examples

```
>>> from scipy.linalg import qr_multiply, qr
>>> A = np.array([[1, 3, 3], [2, 3, 2], [2, 3, 3], [1, 3, 2]])
>>> qc, r1, piv1 = qr_multiply(A, 2*np.eye(4), pivoting=1)
>>> qc
array([[ -1.,  1., -1.],
       [ -1., -1.,  1.],
       [ -1., -1., -1.],
       [ -1.,  1.,  1.]])
>>> r1
array([[ -6., -3., -5.          ],
       [  0., -1., -1.11022302e-16],
       [  0.,  0., -1.          ]])
>>> piv1
array([1, 0, 2], dtype=int32)
>>> q2, r2, piv2 = qr(A, mode='economic', pivoting=1)
>>> np.allclose(2*q2 - qc, np.zeros((4, 3)))
True
```

scipy.linalg.qr_update

`scipy.linalg.qr_update` (*Q*, *R*, *u*, *v*, *overwrite_qruv=False*, *check_finite=True*)

Rank-k QR update

If $A = QR$ is the QR factorization of A, return the QR factorization of $A + uv^*T$ for real A or $A + uv^*H$ for complex A.

Parameters

Q [(M, M) or (M, N) array_like] Unitary/orthogonal matrix from the qr decomposition of A.
R [(M, N) or (N, N) array_like] Upper triangular matrix from the qr decomposition of A.

u [(M,) or (M, k) array_like] Left update vector
v [(N,) or (N, k) array_like] Right update vector
overwrite_qruv [bool, optional] If True, consume Q, R, u, and v, if possible, while performing the update, otherwise make copies as necessary. Defaults to False.
check_finite [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs. Default is True.

Returns

Q1 [ndarray] Updated unitary/orthogonal factor
R1 [ndarray] Updated upper triangular factor

See also:

[qr](#), [qr_multiply](#), [qr_delete](#), [qr_insert](#)

Notes

This routine does not guarantee that the diagonal entries of $R1$ are real or positive.

New in version 0.16.0.

References

[1], [2], [3]

Examples

```
>>> from scipy import linalg
>>> a = np.array([[ 3., -2., -2.],
...              [ 6., -9., -3.],
...              [-3., 10.,  1.],
...              [ 6., -7.,  4.],
...              [ 7.,  8., -6.]])
>>> q, r = linalg.qr(a)
```

Given this q, r decomposition, perform a rank 1 update.

```
>>> u = np.array([7., -2., 4., 3., 5.])
>>> v = np.array([1., 3., -5.])
>>> q_up, r_up = linalg.qr_update(q, r, u, v, False)
>>> q_up
array([[ 0.54073807,  0.18645997,  0.81707661, -0.02136616,  0.06902409],
...      # may vary (signs)
...      [ 0.21629523, -0.63257324,  0.06567893,  0.34125904, -0.65749222],
...      [ 0.05407381,  0.64757787, -0.12781284, -0.20031219, -0.72198188],
...      [ 0.48666426, -0.30466718, -0.27487277, -0.77079214,  0.0256951 ],
...      [ 0.64888568,  0.23001   , -0.4859845 ,  0.49883891,  0.20253783]])
>>> r_up
array([[ 18.49324201,  24.11691794, -44.98940746],
...      # may vary (signs)
```

(continues on next page)

(continued from previous page)

```
[ 0.          , 31.95894662, -27.40998201],
 [ 0.          , 0.          , -9.25451794],
 [ 0.          , 0.          , 0.          ],
 [ 0.          , 0.          , 0.          ]])
```

The update is equivalent, but faster than the following.

```
>>> a_up = a + np.outer(u, v)
>>> q_direct, r_direct = linalg.qr(a_up)
```

Check that we have equivalent results:

```
>>> np.allclose(np.dot(q_up, r_up), a_up)
True
```

And the updated Q is still unitary:

```
>>> np.allclose(np.dot(q_up.T, q_up), np.eye(5))
True
```

Updating economic (reduced, thin) decompositions is also possible:

```
>>> qe, re = linalg.qr(a, mode='economic')
>>> qe_up, re_up = linalg.qr_update(qe, re, u, v, False)
>>> qe_up
array([[ 0.54073807,  0.18645997,  0.81707661], # may vary (signs)
       [ 0.21629523, -0.63257324,  0.06567893],
       [ 0.05407381,  0.64757787, -0.12781284],
       [ 0.48666426, -0.30466718, -0.27487277],
       [ 0.64888568,  0.23001    , -0.4859845 ]])
>>> re_up
array([[ 18.49324201,  24.11691794, -44.98940746], # may vary (signs)
       [ 0.          , 31.95894662, -27.40998201],
       [ 0.          , 0.          , -9.25451794]])
>>> np.allclose(np.dot(qe_up, re_up), a_up)
True
>>> np.allclose(np.dot(qe_up.T, qe_up), np.eye(3))
True
```

Similarly to the above, perform a rank 2 update.

```
>>> u2 = np.array([[ 7., -1.],
...               [-2.,  4.],
...               [ 4.,  2.],
...               [ 3., -6.],
...               [ 5.,  3.]])
>>> v2 = np.array([[ 1.,  2.],
...               [ 3.,  4.],
...               [-5.,  2.]])
>>> q_up2, r_up2 = linalg.qr_update(q, r, u2, v2, False)
>>> q_up2
array([[ -0.33626508, -0.03477253,  0.61956287, -0.64352987, -0.29618884],
...     ↪ # may vary (signs)
```

(continues on next page)

(continued from previous page)

```

    [-0.50439762,  0.58319694, -0.43010077, -0.33395279,  0.33008064],
    [-0.21016568, -0.63123106,  0.0582249 , -0.13675572,  0.73163206],
    [ 0.12609941,  0.49694436,  0.64590024,  0.31191919,  0.47187344],
    [-0.75659643, -0.11517748,  0.10284903,  0.5986227 , -0.21299983]])
>>> r_up2
array([[ -23.79075451, -41.1084062 ,  24.71548348], # may vary (signs)
       [  0.          , -33.83931057,  11.02226551],
       [  0.          ,  0.          ,  48.91476811],
       [  0.          ,  0.          ,  0.          ],
       [  0.          ,  0.          ,  0.          ]])

```

This update is also a valid qr decomposition of $A + U V^* T$.

```

>>> a_up2 = a + np.dot(u2, v2.T)
>>> np.allclose(a_up2, np.dot(q_up2, r_up2))
True
>>> np.allclose(np.dot(q_up2.T, q_up2), np.eye(5))
True

```

scipy.linalg.qr_delete

`scipy.linalg.qr_delete` ($Q, R, k, \text{int } p=1, \text{which}='row', \text{overwrite_qr}=False, \text{check_finite}=True$)
QR downdate on row or column deletions

If $A = Q R$ is the QR factorization of A , return the QR factorization of A where p rows or columns have been removed starting at row or column k .

Parameters

Q [(M, M) or (M, N) array_like] Unitary/orthogonal matrix from QR decomposition.

R [(M, N) or (N, N) array_like] Upper triangular matrix from QR decomposition.

k [int] Index of the first row or column to delete.

p [int, optional] Number of rows or columns to delete, defaults to 1.

which: {'row', 'col'}, optional

Determines if rows or columns will be deleted, defaults to 'row'

overwrite_qr

[bool, optional] If True, consume Q and R, overwriting their contents with their downdated versions, and returning appropriately sized views. Defaults to False.

check_finite

[bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs. Default is True.

Returns

Q1 [ndarray] Updated unitary/orthogonal factor

R1 [ndarray] Updated upper triangular factor

See also:

[qr](#), [qr_multiply](#), [qr_insert](#), [qr_update](#)

Notes

This routine does not guarantee that the diagonal entries of R1 are positive.

New in version 0.16.0.

References

[1], [2], [3]

Examples

```

>>> from scipy import linalg
>>> a = np.array([[ 3., -2., -2.],
...              [ 6., -9., -3.],
...              [-3., 10.,  1.],
...              [ 6., -7.,  4.],
...              [ 7.,  8., -6.]])
>>> q, r = linalg.qr(a)

```

Given this QR decomposition, update q and r when 2 rows are removed.

```

>>> q1, r1 = linalg.qr_delete(q, r, 2, 2, 'row', False)
>>> q1
array([[ 0.30942637,  0.15347579,  0.93845645], # may vary (signs)
       [ 0.61885275,  0.71680171, -0.32127338],
       [ 0.72199487, -0.68017681, -0.12681844]])
>>> r1
array([[ 9.69535971, -0.4125685 , -6.80738023], # may vary (signs)
       [ 0.          , -12.19958144,  1.62370412],
       [ 0.          ,  0.          , -0.15218213]])

```

The update is equivalent, but faster than the following.

```

>>> a1 = np.delete(a, slice(2,4), 0)
>>> a1
array([[ 3., -2., -2.],
       [ 6., -9., -3.],
       [ 7.,  8., -6.]])
>>> q_direct, r_direct = linalg.qr(a1)

```

Check that we have equivalent results:

```

>>> np.dot(q1, r1)
array([[ 3., -2., -2.],
       [ 6., -9., -3.],
       [ 7.,  8., -6.]])
>>> np.allclose(np.dot(q1, r1), a1)
True

```

And the updated Q is still unitary:

```
>>> np.allclose(np.dot(q1.T, q1), np.eye(3))
True
```

scipy.linalg.qr_insert

`scipy.linalg.qr_insert(Q, R, u, k, which='row', rcond=None, overwrite_qru=False, check_finite=True)`

QR update on row or column insertions

If $A = QR$ is the QR factorization of A , return the QR factorization of A where rows or columns have been inserted starting at row or column k .

Parameters

Q [(M, M) array_like] Unitary/orthogonal matrix from the QR decomposition of A .

R [(M, N) array_like] Upper triangular matrix from the QR decomposition of A .

u [(N,), (p, N), (M,), or (M, p) array_like] Rows or columns to insert

k [int] Index before which u is to be inserted.

which: {'row', 'col'}, optional

Determines if rows or columns will be inserted, defaults to 'row'

rcond [float] Lower bound on the reciprocal condition number of Q augmented with $u/||u||$. Only used when updating economic mode (thin, (M,N) (N,N)) decompositions. If None, machine precision is used. Defaults to None.

overwrite_qru

[bool, optional] If True, consume Q , R , and u , if possible, while performing the update, otherwise make copies as necessary. Defaults to False.

check_finite

[bool, optional] Whether to check that the input matrices contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs. Default is True.

Returns

Q1 [ndarray] Updated unitary/orthogonal factor

R1 [ndarray] Updated upper triangular factor

Raises

LinAlgError :

If updating a (M,N) (N,N) factorization and the reciprocal condition number of Q augmented with $u/||u||$ is smaller than `rcond`.

See also:

[qr](#), [qr_multiply](#), [qr_delete](#), [qr_update](#)

Notes

This routine does not guarantee that the diagonal entries of R1 are positive.

New in version 0.16.0.

References

[1], [2], [3]

Examples

```
>>> from scipy import linalg
>>> a = np.array([[ 3., -2., -2.],
...              [ 6., -7.,  4.],
...              [ 7.,  8., -6.]])
>>> q, r = linalg.qr(a)
```

Given this QR decomposition, update q and r when 2 rows are inserted.

```
>>> u = np.array([[ 6., -9., -3.],
...              [-3., 10.,  1.]])
>>> q1, r1 = linalg.qr_insert(q, r, u, 2, 'row')
>>> q1
array([[ -0.25445668,  0.02246245,  0.18146236, -0.72798806,  0.60979671],
...     # may vary (signs)
...     [-0.50891336,  0.23226178, -0.82836478, -0.02837033, -0.00828114],
...     [-0.50891336,  0.35715302,  0.38937158,  0.58110733,  0.35235345],
...     [ 0.25445668, -0.52202743, -0.32165498,  0.36263239,  0.65404509],
...     [-0.59373225, -0.73856549,  0.16065817, -0.0063658 , -0.27595554]])
>>> r1
array([[ -11.78982612,   6.44623587,   3.81685018], # may vary (signs)
...     [  0.          , -16.01393278,   3.72202865],
...     [  0.          ,  0.          , -6.13010256],
...     [  0.          ,  0.          ,  0.          ],
...     [  0.          ,  0.          ,  0.          ]])
```

The update is equivalent, but faster than the following.

```
>>> a1 = np.insert(a, 2, u, 0)
>>> a1
array([[ 3., -2., -2.],
...     [ 6., -7.,  4.],
...     [ 6., -9., -3.],
...     [-3., 10.,  1.],
...     [ 7.,  8., -6.]])
>>> q_direct, r_direct = linalg.qr(a1)
```

Check that we have equivalent results:

```
>>> np.dot(q1, r1)
array([[ 3., -2., -2.],
```

(continues on next page)

(continued from previous page)

```
[ 6., -7.,  4.],
 [ 6., -9., -3.],
 [-3., 10.,  1.],
 [ 7.,  8., -6.]])
```

```
>>> np.allclose(np.dot(q1, r1), a1)
True
```

And the updated Q is still unitary:

```
>>> np.allclose(np.dot(q1.T, q1), np.eye(5))
True
```

scipy.linalg.rq

`scipy.linalg.rq(a, overwrite_a=False, lwork=None, mode='full', check_finite=True)`

Compute RQ decomposition of a matrix.

Calculate the decomposition $A = R Q$ where Q is unitary/orthogonal and R upper triangular.

Parameters

- a** [(M, N) array_like] Matrix to be decomposed
- overwrite_a** [bool, optional] Whether data in a is overwritten (may improve performance)
- lwork** [int, optional] Work array size, `lwork >= a.shape[1]`. If None or -1, an optimal size is computed.
- mode** [{'full', 'r', 'economic'}, optional] Determines what information is to be returned: either both Q and R ('full', default), only R ('r') or both Q and R but computed in economy-size ('economic', see Notes).
- check_finite** [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

- R** [float or complex ndarray] Of shape (M, N) or (M, K) for `mode='economic'`. $K = \min(M, N)$.
- Q** [float or complex ndarray] Of shape (N, N) or (K, N) for `mode='economic'`. Not returned if `mode='r'`.

Raises

- LinAlgError**
If decomposition fails.

Notes

This is an interface to the LAPACK routines sgerqf, dgerqf, cgerqf, zgerqf, sorgrq, dorgrq, cungrq and zungrq.

If `mode=economic`, the shapes of Q and R are (K, N) and (M, K) instead of (N,N) and (M,N), with $K=\min(M, N)$.

Examples

```
>>> from scipy import linalg
>>> a = np.random.randn(6, 9)
>>> r, q = linalg.rq(a)
>>> np.allclose(a, r @ q)
True
>>> r.shape, q.shape
((6, 9), (9, 9))
>>> r2 = linalg.rq(a, mode='r')
>>> np.allclose(r, r2)
True
>>> r3, q3 = linalg.rq(a, mode='economic')
>>> r3.shape, q3.shape
((6, 6), (6, 9))
```

scipy.linalg.qz

`scipy.linalg.qz(A, B, output='real', lwork=None, sort=None, overwrite_a=False, overwrite_b=False, check_finite=True)`

QZ decomposition for generalized eigenvalues of a pair of matrices.

The QZ, or generalized Schur, decomposition for a pair of N x N nonsymmetric matrices (A,B) is:

$$(A, B) = (Q*AA*Z', Q*BB*Z')$$

where AA, BB is in generalized Schur form if BB is upper-triangular with non-negative diagonal and AA is upper-triangular, or for real QZ decomposition (`output='real'`) block upper triangular with 1x1 and 2x2 blocks. In this case, the 1x1 blocks correspond to real generalized eigenvalues and 2x2 blocks are 'standardized' by making the corresponding elements of BB have the form:

$$\begin{bmatrix} a & 0 \\ 0 & b \end{bmatrix}$$

and the pair of corresponding 2x2 blocks in AA and BB will have a complex conjugate pair of generalized eigenvalues. If (`output='complex'`) or A and B are complex matrices, Z' denotes the conjugate-transpose of Z. Q and Z are unitary matrices.

Parameters

- A** [(N, N) array_like] 2-D array to decompose
- B** [(N, N) array_like] 2-D array to decompose
- output** [{'real', 'complex'}, optional] Construct the real or complex QZ decomposition for real matrices. Default is 'real'.
- lwork** [int, optional] Work array size. If None or -1, it is automatically computed.

sort `[[None, callable, 'lhp', 'rhp', 'iuc', 'ouc'], optional]` NOTE: THIS INPUT IS DISABLED FOR NOW. Use `ordqz` instead.

Specifies whether the upper eigenvalues should be sorted. A callable may be passed that, given a eigenvalue, returns a boolean denoting whether the eigenvalue should be sorted to the top-left (True). For real matrix pairs, the sort function takes three real arguments (`alphan`, `alpha`, `beta`). The eigenvalue $x = (\text{alphan} + \text{alpha}i)/\text{beta}$. For complex matrix pairs or `output='complex'`, the sort function takes two complex arguments (`alpha`, `beta`). The eigenvalue $x = (\text{alpha}/\text{beta})$. Alternatively, string parameters may be used:

- 'lhp' Left-hand plane ($x.\text{real} < 0.0$)
- 'rhp' Right-hand plane ($x.\text{real} > 0.0$)
- 'iuc' Inside the unit circle ($x*x.\text{conjugate()} < 1.0$)
- 'ouc' Outside the unit circle ($x*x.\text{conjugate()} > 1.0$)

Defaults to None (no sorting).

overwrite_a `[bool, optional]` Whether to overwrite data in a (may improve performance)

overwrite_b `[bool, optional]` Whether to overwrite data in b (may improve performance)

check_finite `[bool, optional]` If true checks the elements of *A* and *B* are finite numbers. If false does no checking and passes matrix through to underlying algorithm.

Returns

AA `[(N, N) ndarray]` Generalized Schur form of *A*.

BB `[(N, N) ndarray]` Generalized Schur form of *B*.

Q `[(N, N) ndarray]` The left Schur vectors.

Z `[(N, N) ndarray]` The right Schur vectors.

See also:

[*ordqz*](#)**Notes**

Q is transposed versus the equivalent function in Matlab.

New in version 0.11.0.

Examples

```
>>> from scipy import linalg
>>> np.random.seed(1234)
>>> A = np.arange(9).reshape((3, 3))
>>> B = np.random.randn(3, 3)
```

```
>>> AA, BB, Q, Z = linalg.qz(A, B)
>>> AA
array([[ -13.40928183,  -4.62471562,   1.09215523],
       [  0.          ,   0.          ,   1.22805978],
       [  0.          ,   0.          ,   0.31973817]])
>>> BB
array([[ 0.33362547, -1.37393632,  0.02179805],
```

(continues on next page)

(continued from previous page)

```

    [ 0.          ,  1.68144922,  0.74683866],
    [ 0.          ,  0.          ,  0.9258294  ]])
>>> Q
array([[ 0.14134727, -0.97562773,  0.16784365],
       [ 0.49835904, -0.07636948, -0.86360059],
       [ 0.85537081,  0.20571399,  0.47541828]])
>>> Z
array([[ -0.24900855, -0.51772687,  0.81850696],
       [ -0.79813178,  0.58842606,  0.12938478],
       [ -0.54861681, -0.6210585 , -0.55973739]])

```

scipy.linalg.ordqz

`scipy.linalg.ordqz(A, B, sort='lhp', output='real', overwrite_a=False, overwrite_b=False, check_finite=True)`

QZ decomposition for a pair of matrices with reordering.

New in version 0.17.0.

Parameters

- A** [(N, N) array_like] 2-D array to decompose
- B** [(N, N) array_like] 2-D array to decompose
- sort** [{callable, 'lhp', 'rhp', 'iuc', 'ouc'}, optional] Specifies whether the upper eigenvalues should be sorted. A callable may be passed that, given an ordered pair (`alpha`, `beta`) representing the eigenvalue $x = (\text{alpha}/\text{beta})$, returns a boolean denoting whether the eigenvalue should be sorted to the top-left (`True`). For the real matrix pairs `beta` is real while `alpha` can be complex, and for complex matrix pairs both `alpha` and `beta` can be complex. The callable must be able to accept a NumPy array. Alternatively, string parameters may be used:
- 'lhp' Left-hand plane ($x.\text{real} < 0.0$)
 - 'rhp' Right-hand plane ($x.\text{real} > 0.0$)
 - 'iuc' Inside the unit circle ($x * x.\text{conjugate}() < 1.0$)
 - 'ouc' Outside the unit circle ($x * x.\text{conjugate}() > 1.0$)
- With the predefined sorting functions, an infinite eigenvalue (i.e., `alpha != 0` and `beta = 0`) is considered to lie in neither the left-hand nor the right-hand plane, but it is considered to lie outside the unit circle. For the eigenvalue $(\text{alpha}, \text{beta}) = (0, 0)$, the predefined sorting functions all return `False`.
- output** [str {'real','complex'}, optional] Construct the real or complex QZ decomposition for real matrices. Default is 'real'.
- overwrite_a** [bool, optional] If `True`, the contents of `A` are overwritten.
- overwrite_b** [bool, optional] If `True`, the contents of `B` are overwritten.
- check_finite** [bool, optional] If `true` checks the elements of `A` and `B` are finite numbers. If `false` does no checking and passes matrix through to underlying algorithm.

Returns

- AA** [(N, N) ndarray] Generalized Schur form of `A`.
- BB** [(N, N) ndarray] Generalized Schur form of `B`.
- alpha** [(N,) ndarray] $\text{alpha} = \text{alphar} + \text{alphai} * 1j$. See notes.
- beta** [(N,) ndarray] See notes.

Q [(N, N) ndarray] The left Schur vectors.
Z [(N, N) ndarray] The right Schur vectors.

See also:

[qz](#)

Notes

On exit, $(\text{ALPHAR}(j) + \text{ALPHAI}(j)*i)/\text{BETA}(j)$, $j=1, \dots, N$, will be the generalized eigenvalues. $\text{ALPHAR}(j) + \text{ALPHAI}(j)*i$ and $\text{BETA}(j)$, $j=1, \dots, N$ are the diagonals of the complex Schur form (S,T) that would result if the 2-by-2 diagonal blocks of the real generalized Schur form of (A,B) were further reduced to triangular form using complex unitary transformations. If $\text{ALPHAI}(j)$ is zero, then the j th eigenvalue is real; if positive, then the j th and $(j+1)$ st eigenvalues are a complex conjugate pair, with $\text{ALPHAI}(j+1)$ negative.

Examples

```
>>> from scipy.linalg import ordqz
>>> A = np.array([[2, 5, 8, 7], [5, 2, 2, 8], [7, 5, 6, 6], [5, 4, 4, 8]])
>>> B = np.array([[0, 6, 0, 0], [5, 0, 2, 1], [5, 2, 6, 6], [4, 7, 7, 7]])
>>> AA, BB, alpha, beta, Q, Z = ordqz(A, B, sort='lhp')
```

Since we have sorted for left half plane eigenvalues, negatives come first

```
>>> (alpha/beta).real < 0
array([ True,  True, False, False], dtype=bool)
```

scipy.linalg.schur

`scipy.linalg.schur` (*a*, *output='real'*, *lwork=None*, *overwrite_a=False*, *sort=None*, *check_finite=True*)
 Compute Schur decomposition of a matrix.

The Schur decomposition is:

$$A = Z T Z^H$$

where Z is unitary and T is either upper-triangular, or for real Schur decomposition (*output='real'*), quasi-upper triangular. In the quasi-triangular form, 2x2 blocks describing complex-valued eigenvalue pairs may extrude from the diagonal.

Parameters

a [(M, M) array_like] Matrix to decompose
output [{'real', 'complex'}, optional] Construct the real or complex Schur decomposition (for real matrices).
lwork [int, optional] Work array size. If None or -1, it is automatically computed.
overwrite_a [bool, optional] Whether to overwrite data in *a* (may improve performance).
sort [None, callable, 'lhp', 'rhp', 'iuc', 'ouc'], optional] Specifies whether the upper eigenvalues should be sorted. A callable may be passed that, given a eigenvalue, returns a boolean denoting whether the eigenvalue should be sorted to the top-left (True). Alternatively, string parameters may be used:

```
'lhp' Left-hand plane (x.real < 0.0)
'rhs' Right-hand plane (x.real > 0.0)
'iuc' Inside the unit circle (x*x.conjugate() <= 1.0)
'ouc' Outside the unit circle (x*x.conjugate() > 1.0)
```

Defaults to None (no sorting).

check_finite

[bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

T [(M, M) ndarray] Schur form of A. It is real-valued for the real Schur decomposition.
Z [(M, M) ndarray] An unitary Schur transformation matrix for A. It is real-valued for the real Schur decomposition.
sdim [int] If and only if sorting was requested, a third return value will contain the number of eigenvalues satisfying the sort condition.

Raises

LinAlgError

Error raised under three conditions:

1. The algorithm failed due to a failure of the QR algorithm to compute all eigenvalues.
2. If eigenvalue sorting was requested, the eigenvalues could not be reordered due to a failure to separate eigenvalues, usually because of poor conditioning.
3. If eigenvalue sorting was requested, roundoff errors caused the leading eigenvalues to no longer satisfy the sorting condition.

See also:

rsf2csf

Convert real Schur form to complex Schur form

Examples

```
>>> from scipy.linalg import schur, eigvals
>>> A = np.array([[0, 2, 2], [0, 1, 2], [1, 0, 1]])
>>> T, Z = schur(A)
>>> T
array([[ 2.65896708,  1.42440458, -1.92933439],
       [ 0.          , -0.32948354, -0.49063704],
       [ 0.          ,  1.31178921, -0.32948354]])
>>> Z
array([[0.72711591, -0.60156188,  0.33079564],
       [0.52839428,  0.79801892,  0.28976765],
       [0.43829436,  0.03590414, -0.89811411]])
```

```
>>> T2, Z2 = schur(A, output='complex')
>>> T2
array([[ 2.65896708, -1.22839825+1.32378589j,  0.42590089+1.51937378j],
       [ 0.          , -0.32948354+0.80225456j, -0.59877807+0.56192146j],
       [ 0.          ,  0.          , -0.32948354-0.80225456j]])
```

(continues on next page)

(continued from previous page)

```
>>> eigvals(T2)
array([2.65896708, -0.32948354+0.80225456j, -0.32948354-0.80225456j])
```

An arbitrary custom eig-sorting condition, having positive imaginary part, which is satisfied by only one eigenvalue

```
>>> T3, Z3, sdim = schur(A, output='complex', sort=lambda x: x.imag > 0)
>>> sdim
1
```

scipy.linalg.rsfc2csf

`scipy.linalg.rsfc2csf(T, Z, check_finite=True)`

Convert real Schur form to complex Schur form.

Convert a quasi-diagonal real-valued Schur form to the upper-triangular complex-valued Schur form.

Parameters

T [(M, M) array_like] Real Schur form of the original array

Z [(M, M) array_like] Schur transformation matrix

check_finite

[bool, optional] Whether to check that the input arrays contain only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

T [(M, M) ndarray] Complex Schur form of the original array

Z [(M, M) ndarray] Schur transformation matrix corresponding to the complex form

See also:

schur

Schur decomposition of an array

Examples

```
>>> from scipy.linalg import schur, rsfc2csf
>>> A = np.array([[0, 2, 2], [0, 1, 2], [1, 0, 1]])
>>> T, Z = schur(A)
>>> T
array([[ 2.65896708,  1.42440458, -1.92933439],
       [ 0.          , -0.32948354, -0.49063704],
       [ 0.          ,  1.31178921, -0.32948354]])
>>> Z
array([[0.72711591, -0.60156188, 0.33079564],
       [0.52839428, 0.79801892, 0.28976765],
       [0.43829436, 0.03590414, -0.89811411]])
>>> T2, Z2 = rsfc2csf(T, Z)
>>> T2
array([[2.65896708+0.j, -1.64592781+0.743164187j, -1.21516887+1.
↪00660462j],
```

(continues on next page)

(continued from previous page)

```

    [0.+0.j , -0.32948354+8.02254558e-01j, -0.82115218-2.77555756e-
    ↪17j],
    [0.+0.j , 0.+0.j, -0.32948354-0.802254558j]])
>>> z2
array([[0.72711591+0.j, 0.28220393-0.31385693j, 0.51319638-0.17258824j],
       [0.52839428+0.j, 0.24720268+0.41635578j, -0.68079517-0.15118243j],
       [0.43829436+0.j, -0.76618703+0.01873251j, -0.03063006+0.
    ↪46857912j]])

```

scipy.linalg.hessenberg

`scipy.linalg.hessenberg(a, calc_q=False, overwrite_a=False, check_finite=True)`

Compute Hessenberg form of a matrix.

The Hessenberg decomposition is:

$$A = Q H Q^H$$

where Q is unitary/orthogonal and H has only zero elements below the first sub-diagonal.

Parameters

- a** [(M, M) array_like] Matrix to bring into Hessenberg form.
- calc_q** [bool, optional] Whether to compute the transformation matrix. Default is False.
- overwrite_a** [bool, optional] Whether to overwrite a ; may improve performance. Default is False.
- check_finite** [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

- H** [(M, M) ndarray] Hessenberg form of a .
- Q** [(M, M) ndarray] Unitary/orthogonal similarity transformation matrix $A = Q H Q^H$. Only returned if `calc_q=True`.

Examples

```

>>> from scipy.linalg import hessenberg
>>> A = np.array([[2, 5, 8, 7], [5, 2, 2, 8], [7, 5, 6, 6], [5, 4, 4, 8]])
>>> H, Q = hessenberg(A, calc_q=True)
>>> H
array([[ 2.          , -11.65843866,  1.42005301,  0.25349066],
       [-9.94987437,  14.53535354, -5.31022304,  2.43081618],
       [ 0.          , -1.83299243,  0.38969961, -0.51527034],
       [ 0.          ,  0.          , -3.83189513,  1.07494686]])
>>> np.allclose(Q @ H @ Q.conj().T - A, np.zeros((4, 4)))
True

```

scipy.linalg.cdf2rdf

`scipy.linalg.cdf2rdf(w, v)`

Converts complex eigenvalues w and eigenvectors v to real eigenvalues in a block diagonal form w_r and the associated real eigenvectors v_r , such that:

$$v_r @ w_r = X @ v_r$$

continues to hold, where X is the original array for which w and v are the eigenvalues and eigenvectors.

New in version 1.1.0.

Parameters

- w** [(..., M) array_like] Complex or real eigenvalues, an array or stack of arrays
Conjugate pairs must not be interleaved, else the wrong result will be produced. So $[1+1j, 1, 1-1j]$ will give a correct result, but $[1+1j, 2+1j, 1-1j, 2-1j]$ will not.
- v** [(..., M, M) array_like] Complex or real eigenvectors, a square array or stack of square arrays.

Returns

- wr** [(..., M, M) ndarray] Real diagonal block form of eigenvalues
- vr** [(..., M, M) ndarray] Real eigenvectors associated with w_r

See also:

eig

Eigenvalues and right eigenvectors for non-symmetric arrays

rsf2csf

Convert real Schur form to complex Schur form

Notes

w, v must be the eigenstructure for some *real* matrix X . For example, obtained by $w, v = \text{scipy.linalg.eig}(X)$ or $w, v = \text{numpy.linalg.eig}(X)$ in which case X can also represent stacked arrays.

New in version 1.1.0.

Examples

```
>>> X = np.array([[1, 2, 3], [0, 4, 5], [0, -5, 4]])
>>> X
array([[ 1,  2,  3],
       [ 0,  4,  5],
       [ 0, -5,  4]])
```

```
>>> from scipy import linalg
>>> w, v = linalg.eig(X)
>>> w
array([ 1.+0.j,  4.+5.j,  4.-5.j])
>>> v
array([[ 1.00000+0.j,  -0.01906-0.40016j,  -0.01906+0.40016j],
```

(continues on next page)

(continued from previous page)

```
[ 0.00000+0.j      ,  0.00000-0.64788j,  0.00000+0.64788j],
 [ 0.00000+0.j      ,  0.64788+0.j      ,  0.64788-0.j      ]])
```

```
>>> wr, vr = linalg.cdf2rdf(w, v)
>>> wr
array([[ 1.,  0.,  0.],
       [ 0.,  4.,  5.],
       [ 0., -5.,  4.]])
>>> vr
array([[ 1.      ,  0.40016, -0.01906],
       [ 0.      ,  0.64788,  0.      ],
       [ 0.      ,  0.      ,  0.64788]])
```

```
>>> vr @ wr
array([[ 1.      ,  1.69593,  1.9246 ],
       [ 0.      ,  2.59153,  3.23942],
       [ 0.      , -3.23942,  2.59153]])
>>> X @ vr
array([[ 1.      ,  1.69593,  1.9246 ],
       [ 0.      ,  2.59153,  3.23942],
       [ 0.      , -3.23942,  2.59153]])
```

scipy.linalg.cossin

`scipy.linalg.cossin(X, p=None, q=None, separate=False, swap_sign=False, compute_u=True, compute_vh=True)`

Compute the cosine-sine (CS) decomposition of an orthogonal/unitary matrix.

X is an (m, m) orthogonal/unitary matrix, partitioned as the following where upper left block has the shape of (p, q):

$$\begin{bmatrix} X_{11} & X_{12} \\ X_{21} & X_{22} \end{bmatrix} = \begin{bmatrix} U_1 & \\ & U_2 \end{bmatrix} \begin{bmatrix} I & 0 & 0 & | & 0 & 0 & 0 \\ 0 & C & 0 & | & 0 & -S & 0 \\ 0 & 0 & 0 & | & 0 & 0 & -I \\ \hline 0 & 0 & 0 & | & I & 0 & 0 \\ 0 & S & 0 & | & 0 & C & 0 \\ 0 & 0 & I & | & 0 & 0 & 0 \end{bmatrix} \begin{bmatrix} V_1 & \\ & V_2 \end{bmatrix}^*$$

U1, U2, V1, V2 are square orthogonal/unitary matrices of dimensions (p, p), (m-p, m-p), (q, q), and (m-q, m-q) respectively, and C and S are (r, r) nonnegative diagonal matrices satisfying C² + S² = I where r = min(p, m-p, q, m-q).

Moreover, the rank of the identity matrices are min(p, q) - r, min(p, m - q) - r, min(m - p, q) - r, and min(m - p, m - q) - r respectively.

X can be supplied either by itself and block specifications p, q or its subblocks in an iterable from which the shapes would be derived. See the examples below.

Parameters

- X** [array_like, iterable] complex unitary or real orthogonal matrix to be decomposed, or iterable of subblocks X11, X12, X21, X22, when p, q are omitted.
- p** [int, optional] Number of rows of the upper left block X11, used only when X is given as an array.
- q** [int, optional] Number of columns of the upper left block X11, used only when X is given as an array.
- separate** [bool, optional] if True, the low level components are returned instead of the matrix factors, i.e. (u1, u2), theta, (v1h, v2h) instead of u, cs, vh.
- swap_sign** [bool, optional] if True, the -S, -I block will be the bottom left, otherwise (by default) they will be in the upper right block.
- compute_u** [bool, optional] if False, u won't be computed and an empty array is returned.
- compute_vh** [bool, optional] if False, vh won't be computed and an empty array is returned.

Returns

- u** [ndarray] When compute_u=True, contains the block diagonal orthogonal/unitary matrix consisting of the blocks U1 (p x p) and U2 (m-p x m-p) orthogonal/unitary matrices. If separate=True, this contains the tuple of (U1, U2).
- cs** [ndarray]
The cosine-sine factor with the structure described above.
If separate=True, this contains the theta array containing the angles in radians.
- vh** [ndarray] When compute_vh=True, contains the block diagonal orthogonal/unitary matrix consisting of the blocks V1H (q x q) and V2H (m-q x m-q) orthogonal/unitary matrices. If separate=True, this contains the tuple of (V1H, V2H).

References

[1]

Examples

```
>>> from scipy.linalg import cossin
>>> from scipy.stats import unitary_group
>>> x = unitary_group.rvs(4)
>>> u, cs, vdh = cossin(x, p=2, q=2)
>>> np.allclose(x, u @ cs @ vdh)
True
```

Same can be entered via subblocks without the need of p and q. Also let's skip the computation of u

```
>>> ue, cs, vdh = cossin((x[:2, :2], x[:2, 2:], x[2:, :2], x[2:, 2:]),
...                      compute_u=False)
>>> print(ue)
[]
>>> np.allclose(x, u @ cs @ vdh)
True
```

See also:

[*scipy.linalg.interpolative*](#) – Interpolative matrix decompositions

6.10.4 Matrix Functions

<code>expm(A)</code>	Compute the matrix exponential using Pade approximation.
<code>logm(A[, disp])</code>	Compute matrix logarithm.
<code>cosm(A)</code>	Compute the matrix cosine.
<code>sinm(A)</code>	Compute the matrix sine.
<code>tanm(A)</code>	Compute the matrix tangent.
<code>coshm(A)</code>	Compute the hyperbolic matrix cosine.
<code>sinhm(A)</code>	Compute the hyperbolic matrix sine.
<code>tanhm(A)</code>	Compute the hyperbolic matrix tangent.
<code>signm(A[, disp])</code>	Matrix sign function.
<code>sqrtn(A[, disp, blocksize])</code>	Matrix square root.
<code>funm(A, func[, disp])</code>	Evaluate a matrix function specified by a callable.
<code>expm_frechet(A, E[, method, compute_expm, ...])</code>	Frechet derivative of the matrix exponential of A in the direction E.
<code>expm_cond(A[, check_finite])</code>	Relative condition number of the matrix exponential in the Frobenius norm.
<code>fractional_matrix_power(A, t)</code>	Compute the fractional power of a matrix.

scipy.linalg.expm

`scipy.linalg.expm(A)`

Compute the matrix exponential using Pade approximation.

Parameters

A [(N, N) array_like or sparse matrix] Matrix to be exponentiated.

Returns

expm [(N, N) ndarray] Matrix exponential of A.

References

[1]

Examples

```
>>> from scipy.linalg import expm, sinm, cosm
```

Matrix version of the formula $\exp(0) = 1$:

```
>>> expm(np.zeros((2,2)))
array([[ 1.,  0.],
       [ 0.,  1.]])
```

Euler's identity ($\exp(i*\theta) = \cos(\theta) + i*\sin(\theta)$) applied to a matrix:


```

>>> a = np.array([[1.0, 2.0], [-1.0, 3.0]])
>>> expm(1j*a)
array([[ 0.42645930+1.89217551j, -2.13721484-0.97811252j],
       [ 1.06860742+0.48905626j, -1.71075555+0.91406299j]])
>>> cosm(a) + 1j*sinm(a)
array([[ 0.42645930+1.89217551j, -2.13721484-0.97811252j],
       [ 1.06860742+0.48905626j, -1.71075555+0.91406299j]])

```

scipy.linalg.logm

scipy.linalg.**logm**(A, disp=True)

Compute matrix logarithm.

The matrix logarithm is the inverse of expm: $\text{expm}(\text{logm}(A)) == A$

Parameters

A [(N, N) array_like] Matrix whose logarithm to evaluate
disp [bool, optional] Print warning if error in the result is estimated large instead of returning estimated error. (Default: True)

Returns

logm [(N, N) ndarray] Matrix logarithm of A
errest [float] (if disp == False)
 1-norm of the estimated error, $\|\text{err}\|_1 / \|A\|_1$

References

[1], [2], [3]

Examples

```

>>> from scipy.linalg import logm, expm
>>> a = np.array([[1.0, 3.0], [1.0, 4.0]])
>>> b = logm(a)
>>> b
array([[ -1.02571087,  2.05142174],
       [ 0.68380725,  1.02571087]])
>>> expm(b)          # Verify expm(logm(a)) returns a
array([[ 1.,  3.],
       [ 1.,  4.]])

```

scipy.linalg.cosm`scipy.linalg.cosm(A)`

Compute the matrix cosine.

This routine uses `expm` to compute the matrix exponentials.**Parameters****A** [(N, N) array_like] Input array**Returns****cosm** [(N, N) ndarray] Matrix cosine of A**Examples**

```
>>> from scipy.linalg import expm, sinm, cosm
```

Euler's identity ($\exp(i*\theta) = \cos(\theta) + i*\sin(\theta)$) applied to a matrix:

```
>>> a = np.array([[1.0, 2.0], [-1.0, 3.0]])
>>> expm(1j*a)
array([[ 0.42645930+1.89217551j, -2.13721484-0.97811252j],
       [ 1.06860742+0.48905626j, -1.71075555+0.91406299j]])
>>> cosm(a) + 1j*sinm(a)
array([[ 0.42645930+1.89217551j, -2.13721484-0.97811252j],
       [ 1.06860742+0.48905626j, -1.71075555+0.91406299j]])
```

scipy.linalg.sinm`scipy.linalg.sinm(A)`

Compute the matrix sine.

This routine uses `expm` to compute the matrix exponentials.**Parameters****A** [(N, N) array_like] Input array.**Returns****sinm** [(N, N) ndarray] Matrix sine of A**Examples**

```
>>> from scipy.linalg import expm, sinm, cosm
```

Euler's identity ($\exp(i*\theta) = \cos(\theta) + i*\sin(\theta)$) applied to a matrix:

```
>>> a = np.array([[1.0, 2.0], [-1.0, 3.0]])
>>> expm(1j*a)
array([[ 0.42645930+1.89217551j, -2.13721484-0.97811252j],
       [ 1.06860742+0.48905626j, -1.71075555+0.91406299j]])
>>> cosm(a) + 1j*sinm(a)
```

(continues on next page)

(continued from previous page)

```
array([[ 0.42645930+1.89217551j, -2.13721484-0.97811252j],
       [ 1.06860742+0.48905626j, -1.71075555+0.91406299j]])
```

scipy.linalg.tanm`scipy.linalg.tanm(A)`

Compute the matrix tangent.

This routine uses `expm` to compute the matrix exponentials.*Parameters***A** [(N, N) array_like] Input array.*Returns***tanm** [(N, N) ndarray] Matrix tangent of *A***Examples**

```
>>> from scipy.linalg import tanm, sinm, cosm
>>> a = np.array([[1.0, 3.0], [1.0, 4.0]])
>>> t = tanm(a)
>>> t
array([[ -2.00876993,  -8.41880636],
       [ -2.80626879, -10.42757629]])
```

Verify `tanm(a) = sinm(a).dot(inv(cosm(a)))`

```
>>> s = sinm(a)
>>> c = cosm(a)
>>> s.dot(np.linalg.inv(c))
array([[ -2.00876993,  -8.41880636],
       [ -2.80626879, -10.42757629]])
```

scipy.linalg.coshm`scipy.linalg.coshm(A)`

Compute the hyperbolic matrix cosine.

This routine uses `expm` to compute the matrix exponentials.*Parameters***A** [(N, N) array_like] Input array.*Returns***coshm** [(N, N) ndarray] Hyperbolic matrix cosine of *A*

Examples

```
>>> from scipy.linalg import tanhm, sinhm, coshm
>>> a = np.array([[1.0, 3.0], [1.0, 4.0]])
>>> c = coshm(a)
>>> c
array([[ 11.24592233,  38.76236492],
       [ 12.92078831,  50.00828725]])
```

Verify $\tanhm(a) = \sinhm(a) \cdot \text{inv}(\text{coshm}(a))$

```
>>> t = tanhm(a)
>>> s = sinhm(a)
>>> t - s.dot(np.linalg.inv(c))
array([[ 2.72004641e-15,  4.55191440e-15],
       [ 0.00000000e+00, -5.55111512e-16]])
```

scipy.linalg.sinhm

`scipy.linalg.sinhm(A)`

Compute the hyperbolic matrix sine.

This routine uses `expm` to compute the matrix exponentials.

Parameters

A [(N, N) array_like] Input array.

Returns

sinhm [(N, N) ndarray] Hyperbolic matrix sine of *A*

Examples

```
>>> from scipy.linalg import tanhm, sinhm, coshm
>>> a = np.array([[1.0, 3.0], [1.0, 4.0]])
>>> s = sinhm(a)
>>> s
array([[ 10.57300653,  39.28826594],
       [ 13.09608865,  49.86127247]])
```

Verify $\tanhm(a) = \sinhm(a) \cdot \text{inv}(\text{coshm}(a))$

```
>>> t = tanhm(a)
>>> c = coshm(a)
>>> t - s.dot(np.linalg.inv(c))
array([[ 2.72004641e-15,  4.55191440e-15],
       [ 0.00000000e+00, -5.55111512e-16]])
```

scipy.linalg.tanhm`scipy.linalg.tanhm(A)`

Compute the hyperbolic matrix tangent.

This routine uses `expm` to compute the matrix exponentials.**Parameters****A** [(N, N) array_like] Input array**Returns****tanhm** [(N, N) ndarray] Hyperbolic matrix tangent of *A***Examples**

```
>>> from scipy.linalg import tanhm, sinhm, coshm
>>> a = np.array([[1.0, 3.0], [1.0, 4.0]])
>>> t = tanhm(a)
>>> t
array([[ 0.3428582 ,  0.51987926],
       [ 0.17329309,  0.86273746]])
```

Verify `tanhm(a) = sinhm(a).dot(inv(coshm(a)))`

```
>>> s = sinhm(a)
>>> c = coshm(a)
>>> t - s.dot(np.linalg.inv(c))
array([[ 2.72004641e-15,  4.55191440e-15],
       [ 0.00000000e+00, -5.55111512e-16]])
```

scipy.linalg.signm`scipy.linalg.signm(A, disp=True)`

Matrix sign function.

Extension of the scalar `sign(x)` to matrices.**Parameters****A** [(N, N) array_like] Matrix at which to evaluate the sign function**disp** [bool, optional] Print warning if error in the result is estimated large instead of returning estimated error. (Default: True)**Returns****signm** [(N, N) ndarray] Value of the sign function at *A***errest** [float] (if `disp == False`)1-norm of the estimated error, `||err||1 / ||A||1`

Examples

```
>>> from scipy.linalg import signm, eigvals
>>> a = [[1,2,3], [1,2,1], [1,1,1]]
>>> eigvals(a)
array([ 4.12488542+0.j, -0.76155718+0.j,  0.63667176+0.j])
>>> eigvals(signm(a))
array([-1.+0.j,  1.+0.j,  1.+0.j])
```

scipy.linalg.sqrtm

`scipy.linalg.sqrtm` (*A*, *disp=True*, *blocksize=64*)

Matrix square root.

Parameters

A	[(N, N) array_like] Matrix whose square root to evaluate
disp	[bool, optional] Print warning if error in the result is estimated large instead of returning estimated error. (Default: True)
blocksize	[integer, optional] If the blocksize is not degenerate with respect to the size of the input array, then use a blocked algorithm. (Default: 64)

Returns

sqrtm	[(N, N) ndarray] Value of the sqrt function at <i>A</i>
errest	[float] (if <i>disp</i> == False) Frobenius norm of the estimated error, $\ err\ _F / \ A\ _F$

References

[1]

Examples

```
>>> from scipy.linalg import sqrtm
>>> a = np.array([[1.0, 3.0], [1.0, 4.0]])
>>> r = sqrtm(a)
>>> r
array([[ 0.75592895,  1.13389342],
       [ 0.37796447,  1.88982237]])
>>> r.dot(r)
array([[ 1.,  3.],
       [ 1.,  4.]])
```

scipy.linalg.funm

`scipy.linalg.funm(A, func, disp=True)`

Evaluate a matrix function specified by a callable.

Returns the value of matrix-valued function f at A . The function f is an extension of the scalar-valued function $func$ to matrices.

Parameters

A	[(N, N) array_like] Matrix at which to evaluate the function
func	[callable] Callable object that evaluates a scalar function f . Must be vectorized (eg. using <code>vectorize</code>).
disp	[bool, optional] Print warning if error in the result is estimated large instead of returning estimated error. (Default: True)

Returns

funm	[(N, N) ndarray] Value of the matrix function specified by <code>func</code> evaluated at A
errest	[float] (if <code>disp == False</code>) 1-norm of the estimated error, $\ lerr\ _1 / \ A\ _1$

Notes

This function implements the general algorithm based on Schur decomposition (Algorithm 9.1.1. in [1]).

If the input matrix is known to be diagonalizable, then relying on the eigendecomposition is likely to be faster. For example, if your matrix is Hermitian, you can do

```
>>> from scipy.linalg import eigh
>>> def funm_herm(a, func, check_finite=False):
...     w, v = eigh(a, check_finite=check_finite)
...     ## if you further know that your matrix is positive semidefinite,
...     ## you can optionally guard against precision errors by doing
...     # w = np.maximum(w, 0)
...     w = func(w)
...     return (v * w).dot(v.conj()).T
```

References

[1]

Examples

```
>>> from scipy.linalg import funm
>>> a = np.array([[1.0, 3.0], [1.0, 4.0]])
>>> funm(a, lambda x: x*x)
array([[ 4., 15.],
       [ 5., 19.]])
>>> a.dot(a)
array([[ 4., 15.],
       [ 5., 19.]])
```

scipy.linalg.expm_frechet

`scipy.linalg.expm_frechet` (*A*, *E*, *method=None*, *compute_expm=True*, *check_finite=True*)
Frechet derivative of the matrix exponential of *A* in the direction *E*.

Parameters

- A** [(N, N) array_like] Matrix of which to take the matrix exponential.
E [(N, N) array_like] Matrix direction in which to take the Frechet derivative.
method [str, optional] Choice of algorithm. Should be one of
- *SPS* (default)
 - *blockEnlarge*
- compute_expm** [bool, optional] Whether to compute also *expm_A* in addition to *expm_frechet_AE*. Default is True.
check_finite [bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

- expm_A** [ndarray] Matrix exponential of *A*.
expm_frechet_AE [ndarray] Frechet derivative of the matrix exponential of *A* in the direction *E*.
For **compute_expm = False**, only *expm_frechet_AE* is returned.

See also:

expm

Compute the exponential of a matrix.

Notes

This section describes the available implementations that can be selected by the *method* parameter. The default method is *SPS*.

Method *blockEnlarge* is a naive algorithm.

Method *SPS* is Scaling-Pade-Squaring [1]. It is a sophisticated implementation which should take only about 3/8 as much time as the naive implementation. The asymptotics are the same.

New in version 0.13.0.

References

[1]

Examples

```
>>> import scipy.linalg
>>> A = np.random.randn(3, 3)
>>> E = np.random.randn(3, 3)
>>> expm_A, expm_frechet_AE = scipy.linalg.expm_frechet(A, E)
>>> expm_A.shape, expm_frechet_AE.shape
((3, 3), (3, 3))
```

```
>>> import scipy.linalg
>>> A = np.random.randn(3, 3)
>>> E = np.random.randn(3, 3)
>>> expm_A, expm_frechet_AE = scipy.linalg.expm_frechet(A, E)
>>> M = np.zeros((6, 6))
>>> M[:3, :3] = A; M[:3, 3:] = E; M[3:, 3:] = A
>>> expm_M = scipy.linalg.expm(M)
>>> np.allclose(expm_A, expm_M[:3, :3])
True
>>> np.allclose(expm_frechet_AE, expm_M[:3, 3:])
True
```

scipy.linalg.expm_cond

`scipy.linalg.expm_cond(A, check_finite=True)`

Relative condition number of the matrix exponential in the Frobenius norm.

Parameters

A [2-D array_like] Square input matrix with shape (N, N).

check_finite

[bool, optional] Whether to check that the input matrix contains only finite numbers. Disabling may give a performance gain, but may result in problems (crashes, non-termination) if the inputs do contain infinities or NaNs.

Returns

kappa [float] The relative condition number of the matrix exponential in the Frobenius norm

See also:

[expm](#)

Compute the exponential of a matrix.

[expm_frechet](#)

Compute the Frechet derivative of the matrix exponential.

Notes

A faster estimate for the condition number in the 1-norm has been published but is not yet implemented in SciPy.
New in version 0.14.0.

Examples

```
>>> from scipy.linalg import expm_cond
>>> A = np.array([[ -0.3,  0.2,  0.6], [ 0.6,  0.3, -0.1], [-0.7,  1.2,  0.9]])
>>> k = expm_cond(A)
>>> k
1.7787805864469866
```

scipy.linalg.fractional_matrix_power

`scipy.linalg.fractional_matrix_power(A, t)`

Compute the fractional power of a matrix.

Proceeds according to the discussion in section (6) of [1].

Parameters

A [(N, N) array_like] Matrix whose fractional power to evaluate.
t [float] Fractional power.

Returns

X [(N, N) array_like] The fractional power of the matrix.

References

[1]

Examples

```
>>> from scipy.linalg import fractional_matrix_power
>>> a = np.array([[1.0, 3.0], [1.0, 4.0]])
>>> b = fractional_matrix_power(a, 0.5)
>>> b
array([[ 0.75592895,  1.13389342],
       [ 0.37796447,  1.88982237]])
>>> np.dot(b, b)      # Verify square root
array([[ 1.,  3.],
       [ 1.,  4.]])
```

6.10.5 Matrix Equation Solvers

<code>solve_sylvester(a, b, q)</code>	Computes a solution (X) to the Sylvester equation $AX + XB = Q$.
<code>solve_continuous_are(a, b, q, r[, e, s, ...])</code>	Solves the continuous-time algebraic Riccati equation (CARE).
<code>solve_discrete_are(a, b, q, r[, e, s, balanced])</code>	Solves the discrete-time algebraic Riccati equation (DARE).
<code>solve_continuous_lyapunov(a, q)</code>	Solves the continuous Lyapunov equation $AX + XA^H = -Q$.
<code>solve_discrete_lyapunov(a, q[, method])</code>	Solves the discrete Lyapunov equation $AXA^H - X + Q = 0$.

scipy.linalg.solve_sylvester

`scipy.linalg.solve_sylvester(a, b, q)`

Computes a solution (X) to the Sylvester equation $AX + XB = Q$.

Parameters

a [(M, M) array_like] Leading matrix of the Sylvester equation
b [(N, N) array_like] Trailing matrix of the Sylvester equation
q [(M, N) array_like] Right-hand side

Returns

x [(M, N) ndarray] The solution to the Sylvester equation.

Raises

LinAlgError
 If solution was not found

Notes

Computes a solution to the Sylvester matrix equation via the Bartels- Stewart algorithm. The A and B matrices first undergo Schur decompositions. The resulting matrices are used to construct an alternative Sylvester equation $(RY + YS^T = F)$ where the R and S matrices are in quasi-triangular form (or, when R, S or F are complex, triangular form). The simplified equation is then solved using *TRSYL from LAPACK directly.

New in version 0.11.0.

Examples

Given a , b , and q solve for x :

```
>>> from scipy import linalg
>>> a = np.array([[ -3,  -2,  0], [-1,  -1,  3], [ 3,  -5,  -1]])
>>> b = np.array([[1]])
>>> q = np.array([[1], [2], [3]])
>>> x = linalg.solve_sylvester(a, b, q)
>>> x
array([[ 0.0625],
```

(continues on next page)

(continued from previous page)

```

    [-0.5625],
    [ 0.6875]])
>>> np.allclose(a.dot(x) + x.dot(b), q)
True

```

scipy.linalg.solve_continuous_are

`scipy.linalg.solve_continuous_are` (*a*, *b*, *q*, *r*, *e=None*, *s=None*, *balanced=True*)

Solves the continuous-time algebraic Riccati equation (CARE).

The CARE is defined as

$$XA + A^H X - XBR^{-1}B^H X + Q = 0$$

The limitations for a solution to exist are :

- All eigenvalues of *A* on the right half plane, should be controllable.
- The associated hamiltonian pencil (See Notes), should have eigenvalues sufficiently away from the imaginary axis.

Moreover, if *e* or *s* is not precisely *None*, then the generalized version of CARE

$$E^H XA + A^H XE - (E^H XB + S)R^{-1}(B^H XE + S^H) + Q = 0$$

is solved. When omitted, *e* is assumed to be the identity and *s* is assumed to be the zero matrix with sizes compatible with *a* and *b*, respectively.

Parameters

- a** [(M, M) array_like] Square matrix
- b** [(M, N) array_like] Input
- q** [(M, M) array_like] Input
- r** [(N, N) array_like] Nonsingular square matrix
- e** [(M, M) array_like, optional] Nonsingular square matrix
- s** [(M, N) array_like, optional] Input
- balanced** [bool, optional] The boolean that indicates whether a balancing step is performed on the data. The default is set to True.

Returns

- x** [(M, M) ndarray] Solution to the continuous-time algebraic Riccati equation.

Raises

LinAlgError

For cases where the stable subspace of the pencil could not be isolated. See Notes section and the references for details.

See also:

[solve_discrete_are](#)

Solves the discrete-time algebraic Riccati equation

Notes

The equation is solved by forming the extended hamiltonian matrix pencil, as described in [1], $H - \lambda J$ given by the block matrices

$$\begin{bmatrix} A & 0 & B \\ -Q & -A^H & -S \\ S^H & B^H & R \end{bmatrix} - \lambda * \begin{bmatrix} E & 0 & 0 \\ 0 & E^H & 0 \\ 0 & 0 & 0 \end{bmatrix}$$

and using a QZ decomposition method.

In this algorithm, the fail conditions are linked to the symmetry of the product $U_2 U_1^{-1}$ and condition number of U_1 . Here, U is the $2m$ -by- m matrix that holds the eigenvectors spanning the stable subspace with $2-m$ rows and partitioned into two m -row matrices. See [1] and [2] for more details.

In order to improve the QZ decomposition accuracy, the pencil goes through a balancing step where the sum of absolute values of H and J entries (after removing the diagonal entries of the sum) is balanced following the recipe given in [3].

New in version 0.11.0.

References

[1], [2], [3]

Examples

Given a , b , q , and r solve for x :

```
>>> from scipy import linalg
>>> a = np.array([[4, 3], [-4.5, -3.5]])
>>> b = np.array([[1], [-1]])
>>> q = np.array([[9, 6], [6, 4.]])
>>> r = 1
>>> x = linalg.solve_continuous_are(a, b, q, r)
>>> x
array([[ 21.72792206,  14.48528137],
       [ 14.48528137,   9.65685425]])
>>> np.allclose(a.T.dot(x) + x.dot(a) - x.dot(b).dot(b.T).dot(x), -q)
True
```

scipy.linalg.solve_discrete_are

`scipy.linalg.solve_discrete_are(a, b, q, r, e=None, s=None, balanced=True)`

Solves the discrete-time algebraic Riccati equation (DARE).

The DARE is defined as

$$A^H X A - X - (A^H X B)(R + B^H X B)^{-1}(B^H X A) + Q = 0$$

The limitations for a solution to exist are :

- All eigenvalues of A outside the unit disc, should be controllable.
- The associated symplectic pencil (See Notes), should have eigenvalues sufficiently away from the unit circle.

Moreover, if e and s are not both precisely `None`, then the generalized version of DARE

$$A^H X A - E^H X E - (A^H X B + S)(R + B^H X B)^{-1}(B^H X A + S^H) + Q = 0$$

is solved. When omitted, e is assumed to be the identity and s is assumed to be the zero matrix.

Parameters

- a** [(M, M) array_like] Square matrix
- b** [(M, N) array_like] Input
- q** [(M, M) array_like] Input
- r** [(N, N) array_like] Square matrix
- e** [(M, M) array_like, optional] Nonsingular square matrix
- s** [(M, N) array_like, optional] Input
- balanced** [bool] The boolean that indicates whether a balancing step is performed on the data. The default is set to `True`.

Returns

- x** [(M, M) ndarray] Solution to the discrete algebraic Riccati equation.

Raises

LinAlgError

For cases where the stable subspace of the pencil could not be isolated. See Notes section and the references for details.

See also:

[*`solve_continuous_are`*](#)

Solves the continuous algebraic Riccati equation

Notes

The equation is solved by forming the extended symplectic matrix pencil, as described in [1], $H - \lambda J$ given by the block matrices

$\begin{bmatrix} A & 0 & B \\ -Q & E^H & -S \\ S^H & 0 & R \end{bmatrix} - \lambda * \begin{bmatrix} E & 0 & B \\ 0 & A^H & 0 \\ 0 & -B^H & 0 \end{bmatrix}$
--

and using a QZ decomposition method.

In this algorithm, the fail conditions are linked to the symmetry of the product $U_2 U_1^{-1}$ and condition number of U_1 . Here, U is the $2m$ -by- m matrix that holds the eigenvectors spanning the stable subspace with 2 - m rows and partitioned into two m -row matrices. See [1] and [2] for more details.

In order to improve the QZ decomposition accuracy, the pencil goes through a balancing step where the sum of absolute values of H and J rows/cols (after removing the diagonal entries) is balanced following the recipe given in [3]. If the data has small numerical noise, balancing may amplify their effects and some clean up is required.

New in version 0.11.0.

References

[1], [2], [3]

Examples

Given a , b , q , and r solve for x :

```
>>> from scipy import linalg as la
>>> a = np.array([[0, 1], [0, -1]])
>>> b = np.array([[1, 0], [2, 1]])
>>> q = np.array([[-4, -4], [-4, 7]])
>>> r = np.array([[9, 3], [3, 1]])
>>> x = la.solve_discrete_are(a, b, q, r)
>>> x
array([[ -4.,  -4.],
       [ -4.,   7.]])
>>> R = la.solve(r + b.T.dot(x).dot(b), b.T.dot(x).dot(a))
>>> np.allclose(a.T.dot(x).dot(a) - x - a.T.dot(x).dot(b).dot(R), -q)
True
```

scipy.linalg.solve_continuous_lyapunov

`scipy.linalg.solve_continuous_lyapunov(a, q)`
Solves the continuous Lyapunov equation $AX + XA^H = Q$.

Uses the Bartels-Stewart algorithm to find X .

Parameters

a [array_like] A square matrix
q [array_like] Right-hand side square matrix

Returns

x [ndarray] Solution to the continuous Lyapunov equation

See also:

solve_discrete_lyapunov

computes the solution to the discrete-time Lyapunov equation

solve_sylvester

computes the solution to the Sylvester equation

Notes

The continuous Lyapunov equation is a special form of the Sylvester equation, hence this solver relies on LAPACK routine ?TRSYL.

New in version 0.11.0.

Examples

Given a and q solve for x :

```
>>> from scipy import linalg
>>> a = np.array([[ -3,  -2,  0], [-1,  -1,  0], [ 0,  -5, -1]])
>>> b = np.array([2,  4, -1])
>>> q = np.eye(3)
>>> x = linalg.solve_continuous_lyapunov(a, q)
>>> x
array([[ -0.75 ,  0.875 , -3.75  ],
       [  0.875 , -1.375 ,  5.3125],
       [ -3.75  ,  5.3125, -27.0625]])
>>> np.allclose(a.dot(x) + x.dot(a.T), q)
True
```

`scipy.linalg.solve_discrete_lyapunov`

`scipy.linalg.solve_discrete_lyapunov(a, q, method=None)`

Solves the discrete Lyapunov equation $AXA^H - X + Q = 0$.

Parameters

- a, q** [(M, M) array_like] Square matrices corresponding to A and Q in the equation above respectively. Must have the same shape.
- method** [{'direct', 'bilinear'}, optional] Type of solver. If not given, chosen to be `direct` if M is less than 10 and `bilinear` otherwise.

Returns

- x** [ndarray] Solution to the discrete Lyapunov equation

See also:

`solve_continuous_lyapunov`

computes the solution to the continuous-time Lyapunov equation

Notes

This section describes the available solvers that can be selected by the ‘method’ parameter. The default method is *direct* if M is less than 10 and *bilinear* otherwise.

Method *direct* uses a direct analytical solution to the discrete Lyapunov equation. The algorithm is given in, for example, [1]. However, it requires the linear solution of a system with dimension M^2 so that performance degrades rapidly for even moderately sized matrices.

Method *bilinear* uses a bilinear transformation to convert the discrete Lyapunov equation to a continuous Lyapunov equation ($BX + XB' = -C$) where $B = (A - I)(A + I)^{-1}$ and $C = 2(A' + I)^{-1}Q(A + I)^{-1}$. The continuous equation can be efficiently solved since it is a special case of a Sylvester equation. The transformation algorithm is from Popov (1964) as described in [2].

New in version 0.11.0.

References

[1], [2]

Examples

Given a and q solve for x :

```
>>> from scipy import linalg
>>> a = np.array([[0.2, 0.5],[0.7, -0.9]])
>>> q = np.eye(2)
>>> x = linalg.solve_discrete_lyapunov(a, q)
>>> x
array([[ 0.70872893,  1.43518822],
       [ 1.43518822, -2.4266315 ]])
>>> np.allclose(a.dot(x).dot(a.T)-x, -q)
True
```

6.10.6 Sketches and Random Projections

```
clarkson_woodruff_transform(input_matrix, "
...)
```

`scipy.linalg.clarkson_woodruff_transform`

`scipy.linalg.clarkson_woodruff_transform` (*input_matrix*, *sketch_size*, *seed=None*)

” Applies a Clarkson-Woodruff Transform/sketch to the input matrix.

Given an input_matrix A of size (n, d) , compute a matrix A' of size $(\text{sketch_size}, d)$ so that

$$\|Ax\| \approx \|A'x\|$$

with high probability via the Clarkson-Woodruff Transform, otherwise known as the CountSketch matrix.

Parameters

input_matrix: array_like

Input matrix, of shape (n, d) .

sketch_size: int

Number of rows for the sketch.

seed

[None or int or `numpy.random.RandomState` instance, optional] This parameter defines the `RandomState` object to use for drawing random variates. If None (or `np.random`), the global `np.random` state is used. If integer, it is used to seed the local `RandomState` instance. Default is None.

Returns

A' [array_like] Sketch of the input matrix A, of size $(\text{sketch_size}, d)$.

Notes

To make the statement

$$\|Ax\| \approx \|A'x\|$$

precise, observe the following result which is adapted from the proof of Theorem 14 of [2] via Markov's Inequality. If we have a sketch size `sketch_size=k` which is at least

$$k \geq \frac{2}{\epsilon^2 \delta}$$

Then for any fixed vector x ,

$$\|Ax\| = (1 \pm \epsilon)\|A'x\|$$

with probability at least one minus delta.

This implementation takes advantage of sparsity: computing a sketch takes time proportional to `A.nnz`. Data A which is in `scipy.sparse.csc_matrix` format gives the quickest computation time for sparse input.

```
>>> from scipy import linalg
>>> from scipy import sparse
>>> n_rows, n_columns, density, sketch_n_rows = 15000, 100, 0.01, 200
>>> A = sparse.rand(n_rows, n_columns, density=density, format='csc')
>>> B = sparse.rand(n_rows, n_columns, density=density, format='csr')
>>> C = sparse.rand(n_rows, n_columns, density=density, format='coo')
>>> D = np.random.randn(n_rows, n_columns)
>>> SA = linalg.clarkson_woodruff_transform(A, sketch_n_rows) # fastest
>>> SB = linalg.clarkson_woodruff_transform(B, sketch_n_rows) # fast
>>> SC = linalg.clarkson_woodruff_transform(C, sketch_n_rows) # slower
>>> SD = linalg.clarkson_woodruff_transform(D, sketch_n_rows) # slowest
```

That said, this method does perform well on dense inputs, just slower on a relative scale.

References

[1], [2]

Examples

Given a big dense matrix A:

```
>>> from scipy import linalg
>>> n_rows, n_columns, sketch_n_rows = 15000, 100, 200
>>> A = np.random.randn(n_rows, n_columns)
>>> sketch = linalg.clarkson_woodruff_transform(A, sketch_n_rows)
>>> sketch.shape
(200, 100)
>>> norm_A = np.linalg.norm(A)
>>> norm_sketch = np.linalg.norm(sketch)
```

Now with high probability, the true norm `norm_A` is close to the sketched norm `norm_sketch` in absolute value.

Similarly, applying our sketch preserves the solution to a linear regression of $\min \|Ax - b\|$.

```
>>> from scipy import linalg
>>> n_rows, n_columns, sketch_n_rows = 15000, 100, 200
>>> A = np.random.randn(n_rows, n_columns)
>>> b = np.random.randn(n_rows)
>>> x = np.linalg.lstsq(A, b, rcond=None)
>>> Ab = np.hstack((A, b.reshape(-1,1)))
>>> SAb = linalg.clarkson_woodruff_transform(Ab, sketch_n_rows)
>>> SA, Sb = SAb[:, :-1], SAb[:, -1]
>>> x_sketched = np.linalg.lstsq(SA, Sb, rcond=None)
```

As with the matrix norm example, `np.linalg.norm(A @ x - b)` is close to `np.linalg.norm(A @ x_sketched - b)` with high probability.

6.10.7 Special Matrices

<code>block_diag(*arrs)</code>	Create a block diagonal matrix from provided arrays.
<code>circulant(c)</code>	Construct a circulant matrix.
<code>companion(a)</code>	Create a companion matrix.
<code>convolution_matrix(a, n[, mode])</code>	Construct a convolution matrix.
<code>dft(n[, scale])</code>	Discrete Fourier transform matrix.
<code>fiedler(a)</code>	Returns a symmetric Fiedler matrix
<code>fiedler_companion(a)</code>	Returns a Fiedler companion matrix
<code>hadamard(n[, dtype])</code>	Construct an Hadamard matrix.
<code>hankel(c[, r])</code>	Construct a Hankel matrix.
<code>helmert(n[, full])</code>	Create an Helmert matrix of order <i>n</i> .
<code>hilbert(n)</code>	Create a Hilbert matrix of order <i>n</i> .
<code>invhilbert(n[, exact])</code>	Compute the inverse of the Hilbert matrix of order <i>n</i> .
<code>leslie(f, s)</code>	Create a Leslie matrix.
<code>pascal(n[, kind, exact])</code>	Returns the <i>n</i> x <i>n</i> Pascal matrix.
<code>invpascal(n[, kind, exact])</code>	Returns the inverse of the <i>n</i> x <i>n</i> Pascal matrix.

continues on next page

Table 96 – continued from previous page

<code>toeplitz(c[, r])</code>	Construct a Toeplitz matrix.
<code>tri(N[, M, k, dtype])</code>	Construct (N, M) matrix filled with ones at and below the kth diagonal.

scipy.linalg.block_diag

`scipy.linalg.block_diag(*arrs)`

Create a block diagonal matrix from provided arrays.

Given the inputs *A*, *B* and *C*, the output will have these arrays arranged on the diagonal:

```
[A, 0, 0],
[0, B, 0],
[0, 0, C]]
```

Parameters

A, B, C, ...

[array_like, up to 2-D] Input arrays. A 1-D array or array_like sequence of length *n* is treated as a 2-D array with shape $(1, n)$.

Returns

D

[ndarray] Array with *A*, *B*, *C*, ... on the diagonal. *D* has the same dtype as *A*.

Notes

If all the input arrays are square, the output is known as a block diagonal matrix.

Empty sequences (i.e., array-likes of zero size) will not be ignored. Noteworthy, both `[]` and `[[]]` are treated as matrices with shape $(1, 0)$.

Examples

```
>>> from scipy.linalg import block_diag
>>> A = [[1, 0],
...      [0, 1]]
>>> B = [[3, 4, 5],
...      [6, 7, 8]]
>>> C = [[7]]
>>> P = np.zeros((2, 0), dtype='int32')
>>> block_diag(A, B, C)
array([[1, 0, 0, 0, 0, 0],
       [0, 1, 0, 0, 0, 0],
       [0, 0, 3, 4, 5, 0],
       [0, 0, 6, 7, 8, 0],
       [0, 0, 0, 0, 0, 7]])
>>> block_diag(A, P, B, C)
array([[1, 0, 0, 0, 0, 0],
       [0, 1, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0],
```

(continues on next page)

(continued from previous page)

```

    [0, 0, 0, 0, 0, 0],
    [0, 0, 3, 4, 5, 0],
    [0, 0, 6, 7, 8, 0],
    [0, 0, 0, 0, 0, 7]])
>>> block_diag(1.0, [2, 3], [[4, 5], [6, 7]])
array([[ 1.,  0.,  0.,  0.,  0.],
       [ 0.,  2.,  3.,  0.,  0.],
       [ 0.,  0.,  0.,  4.,  5.],
       [ 0.,  0.,  0.,  6.,  7.]])

```

scipy.linalg.circulant

scipy.linalg.**circulant**(*c*)

Construct a circulant matrix.

Parameters

c [(N,) array_like] 1-D array, the first column of the matrix.

Returns

A [(N, N) ndarray] A circulant matrix whose first column is *c*.

See also:

toeplitz

Toeplitz matrix

hankel

Hankel matrix

solve_circulant

Solve a circulant system.

Notes

New in version 0.8.0.

Examples

```

>>> from scipy.linalg import circulant
>>> circulant([1, 2, 3])
array([[1, 3, 2],
       [2, 1, 3],
       [3, 2, 1]])

```

scipy.linalg.companion

`scipy.linalg.companion(a)`

Create a companion matrix.

Create the companion matrix [1] associated with the polynomial whose coefficients are given in *a*.

Parameters

a [(N,) array_like] 1-D array of polynomial coefficients. The length of *a* must be at least two, and *a*[0] must not be zero.

Returns

c [(N-1, N-1) ndarray] The first row of *c* is $-a[1:] / a[0]$, and the first sub-diagonal is all ones. The data-type of the array is the same as the data-type of $1.0 * a[0]$.

Raises

ValueError

If any of the following are true: a) *a*.ndim != 1; b) *a*.size < 2; c) *a*[0] == 0.

Notes

New in version 0.8.0.

References

[1]

Examples

```
>>> from scipy.linalg import companion
>>> companion([1, -10, 31, -30])
array([[ 10., -31.,  30.],
       [  1.,   0.,   0.],
       [  0.,   1.,   0.]])
```

scipy.linalg.convolution_matrix

`scipy.linalg.convolution_matrix(a, n, mode='full')`

Construct a convolution matrix.

Constructs the Toeplitz matrix representing one-dimensional convolution [1]. See the notes below for details.

Parameters

a [(m,) array_like] The 1-D array to convolve.
n [int] The number of columns in the resulting matrix. It gives the length of the input to be convolved with *a*. This is analogous to the length of *v* in `numpy.convolve(a, v)`.
mode [str] This is analogous to *mode* in `numpy.convolve(v, a, mode)`. It must be one of ('full', 'valid', 'same'). See below for how *mode* determines the shape of the result.

Returns

A [(k, n) ndarray] The convolution matrix whose row count *k* depends on *mode*:

```

=====
mode      k
=====
'full'    m + n - 1
'same'    max(m, n)
'valid'   max(m, n) - min(m, n) + 1
=====

```

See also:***toeplitz***

Toeplitz matrix

Notes

The code:

```
A = convolution_matrix(a, n, mode)
```

creates a Toeplitz matrix A such that $A @ v$ is equivalent to using `convolve(a, v, mode)`. The returned array always has n columns. The number of rows depends on the specified *mode*, as explained above.

In the default ‘full’ mode, the entries of A are given by:

```
A[i, j] == (a[i-j] if (0 <= (i-j) < m) else 0)
```

where $m = \text{len}(a)$. Suppose, for example, the input array is $[x, y, z]$. The convolution matrix has the form:

```

[x, 0, 0, ..., 0, 0]
[y, x, 0, ..., 0, 0]
[z, y, x, ..., 0, 0]
...
[0, 0, 0, ..., x, 0]
[0, 0, 0, ..., y, x]
[0, 0, 0, ..., z, y]
[0, 0, 0, ..., 0, z]

```

In ‘valid’ mode, the entries of A are given by:

```
A[i, j] == (a[i-j+m-1] if (0 <= (i-j+m-1) < m) else 0)
```

This corresponds to a matrix whose rows are the subset of those from the ‘full’ case where all the coefficients in a are contained in the row. For input $[x, y, z]$, this array looks like:

```

[z, y, x, 0, 0, ..., 0, 0, 0]
[0, z, y, x, 0, ..., 0, 0, 0]
[0, 0, z, y, x, ..., 0, 0, 0]
...
[0, 0, 0, 0, 0, ..., x, 0, 0]
[0, 0, 0, 0, 0, ..., y, x, 0]
[0, 0, 0, 0, 0, ..., z, y, x]

```

In the ‘same’ mode, the entries of A are given by:

```
d = (m - 1) // 2
A[i, j] == (a[i-j+d] if (0 <= (i-j+d) < m) else 0)
```

The typical application of the ‘same’ mode is when one has a signal of length n (with n greater than $\text{len}(a)$), and the desired output is a filtered signal that is still of length n .

For input $[x, y, z]$, this array looks like:

```
[y, x, 0, 0, ..., 0, 0, 0]
[z, y, x, 0, ..., 0, 0, 0]
[0, z, y, x, ..., 0, 0, 0]
[0, 0, z, y, ..., 0, 0, 0]
...
[0, 0, 0, 0, ..., y, x, 0]
[0, 0, 0, 0, ..., z, y, x]
[0, 0, 0, 0, ..., 0, z, y]
```

New in version 1.5.0.

References

[1]

Examples

```
>>> from scipy.linalg import convolution_matrix
>>> A = convolution_matrix([-1, 4, -2], 5, mode='same')
>>> A
array([[ 4, -1,  0,  0,  0],
       [-2,  4, -1,  0,  0],
       [ 0, -2,  4, -1,  0],
       [ 0,  0, -2,  4, -1],
       [ 0,  0,  0, -2,  4]])
```

Compare multiplication by A with the use of `numpy.convolve`.

```
>>> x = np.array([1, 2, 0, -3, 0.5])
>>> A @ x
array([ 2. ,  6. , -1. , -12.5,  8. ])
```

Verify that $A @ x$ produced the same result as applying the convolution function.

```
>>> np.convolve([-1, 4, -2], x, mode='same')
array([ 2. ,  6. , -1. , -12.5,  8. ])
```

For comparison to the case `mode='same'` shown above, here are the matrices produced by `mode='full'` and `mode='valid'` for the same coefficients and size.

```
>>> convolution_matrix([-1, 4, -2], 5, mode='full')
array([[ -1,  0,  0,  0,  0],
       [  4, -1,  0,  0,  0],
       [ -2,  4, -1,  0,  0],
```

(continues on next page)

(continued from previous page)

```
[ 0, -2,  4, -1,  0],
 [ 0,  0, -2,  4, -1],
 [ 0,  0,  0, -2,  4],
 [ 0,  0,  0,  0, -2]])
```

```
>>> convolution_matrix([-1, 4, -2], 5, mode='valid')
array([[ -2,  4, -1,  0,  0],
       [ 0, -2,  4, -1,  0],
       [ 0,  0, -2,  4, -1]])
```

scipy.linalg.dft

`scipy.linalg.dft` (*n*, *scale=None*)

Discrete Fourier transform matrix.

Create the matrix that computes the discrete Fourier transform of a sequence [1]. The *n*th primitive root of unity used to generate the matrix is $\exp(-2\pi i/n)$, where $i = \sqrt{-1}$.

Parameters

n [int] Size the matrix to create.

scale [str, optional] Must be `None`, `'sqrtn'`, or `'n'`. If *scale* is `'sqrtn'`, the matrix is divided by \sqrt{n} . If *scale* is `'n'`, the matrix is divided by *n*. If *scale* is `None` (the default), the matrix is not normalized, and the return value is simply the Vandermonde matrix of the roots of unity.

Returns

m [(n, n) ndarray] The DFT matrix.

Notes

When *scale* is `None`, multiplying a vector by the matrix returned by `dft` is mathematically equivalent to (but much less efficient than) the calculation performed by `scipy.fft.fft`.

New in version 0.14.0.

References

[1]

Examples

```
>>> from scipy.linalg import dft
>>> np.set_printoptions(precision=2, suppress=True) # for compact output
>>> m = dft(5)
>>> m
array([[ 1. +0.j ,  1. +0.j ,  1. +0.j ,  1. +0.j ,  1. +0.j ],
       [ 1. +0.j ,  0.31-0.95j, -0.81-0.59j, -0.81+0.59j,  0.31+0.95j],
       [ 1. +0.j , -0.81-0.59j,  0.31+0.95j,  0.31-0.95j, -0.81+0.59j],
       [ 1. +0.j , -0.81+0.59j,  0.31-0.95j,  0.31+0.95j, -0.81-0.59j],
       [ 1. +0.j ,  0.31+0.95j, -0.81+0.59j, -0.81-0.59j,  0.31-0.95j]])
```

(continues on next page)

(continued from previous page)

```
>>> x = np.array([1, 2, 3, 0, 3])
>>> m @ x # Compute the DFT of x
array([ 9. +0.j , 0.12-0.81j, -2.12+3.44j, -2.12-3.44j, 0.12+0.81j])
```

Verify that $m @ x$ is the same as `fft(x)`.

```
>>> from scipy.fft import fft
>>> fft(x) # Same result as m @ x
array([ 9. +0.j , 0.12-0.81j, -2.12+3.44j, -2.12-3.44j, 0.12+0.81j])
```

scipy.linalg.fiedler

`scipy.linalg.fiedler(a)`

Returns a symmetric Fiedler matrix

Given an sequence of numbers a , Fiedler matrices have the structure $F[i, j] = np.abs(a[i] - a[j])$, and hence zero diagonals and nonnegative entries. A Fiedler matrix has a dominant positive eigenvalue and other eigenvalues are negative. Although not valid generally, for certain inputs, the inverse and the determinant can be derived explicitly as given in [1].

Parameters

a [(n,) array_like] coefficient array

Returns

F [(n, n) ndarray]

See also:

[*circulant*](#), [*toeplitz*](#)

Notes

New in version 1.3.0.

References

[1]

Examples

```
>>> from scipy.linalg import det, inv, fiedler
>>> a = [1, 4, 12, 45, 77]
>>> n = len(a)
>>> A = fiedler(a)
>>> A
array([[ 0,  3, 11, 44, 76],
       [ 3,  0,  8, 41, 73],
       [11,  8,  0, 33, 65],
       [44, 41, 33,  0, 32],
       [76, 73, 65, 32,  0]])
```

The explicit formulas for determinant and inverse seem to hold only for monotonically increasing/decreasing arrays. Note the tridiagonal structure and the corners.

```
>>> Ai = inv(A)
>>> Ai[np.abs(Ai) < 1e-12] = 0. # cleanup the numerical noise for display
>>> Ai
array([[ -0.16008772,  0.16666667,  0.          ,  0.          ,  0.00657895],
       [ 0.16666667, -0.22916667,  0.0625      ,  0.          ,  0.          ],
       [ 0.          ,  0.0625      , -0.07765152,  0.01515152,  0.          ],
       [ 0.          ,  0.          ,  0.01515152, -0.03077652,  0.015625  ],
       [ 0.00657895,  0.          ,  0.          ,  0.015625  , -0.00904605]])
>>> det(A)
15409151.999999998
>>> (-1)**(n-1) * 2**(n-2) * np.diff(a).prod() * (a[-1] - a[0])
15409152
```

scipy.linalg.fiedler_companion

`scipy.linalg.fiedler_companion(a)`

Returns a Fiedler companion matrix

Given a polynomial coefficient array `a`, this function forms a pentadiagonal matrix with a special structure whose eigenvalues coincides with the roots of `a`.

Parameters

a [(N,) array_like] 1-D array of polynomial coefficients in descending order with a nonzero leading coefficient. For $N < 2$, an empty array is returned.

Returns

c [(N-1, N-1) ndarray] Resulting companion matrix

See also:

[*companion*](#)

Notes

Similar to [*companion*](#) the leading coefficient should be nonzero. In the case the leading coefficient is not 1, other coefficients are rescaled before the array generation. To avoid numerical issues, it is best to provide a monic polynomial.

New in version 1.3.0.

References

[1]

Examples

```
>>> from scipy.linalg import fiedler_companion, eigvals
>>> p = np.poly(np.arange(1, 9, 2)) # [1., -16., 86., -176., 105.]
>>> fc = fiedler_companion(p)
>>> fc
array([[ 16., -86.,  1.,  0.],
       [  1.,  0.,  0.,  0.],
       [  0., 176.,  0., -105.],
       [  0.,  1.,  0.,  0.]])
>>> eigvals(fc)
array([7.+0.j, 5.+0.j, 3.+0.j, 1.+0.j])
```

scipy.linalg.hadamard

`scipy.linalg.hadamard` (n , *dtype*=<class 'int'>)

Construct an Hadamard matrix.

Constructs an n -by- n Hadamard matrix, using Sylvester's construction. n must be a power of 2.

Parameters

n [int] The order of the matrix. n must be a power of 2.
dtype [dtype, optional] The data type of the array to be constructed.

Returns

H [(n, n) ndarray] The Hadamard matrix.

Notes

New in version 0.8.0.

Examples

```
>>> from scipy.linalg import hadamard
>>> hadamard(2, dtype=complex)
array([[ 1.+0.j,  1.+0.j],
       [ 1.+0.j, -1.-0.j]])
>>> hadamard(4)
array([[ 1,  1,  1,  1],
       [ 1, -1,  1, -1],
       [ 1,  1, -1, -1],
       [ 1, -1, -1,  1]])
```

scipy.linalg.hankel`scipy.linalg.hankel` (*c*, *r=None*)

Construct a Hankel matrix.

The Hankel matrix has constant anti-diagonals, with *c* as its first column and *r* as its last row. If *r* is not given, then *r = zeros_like(c)* is assumed.

Parameters

- c** [array_like] First column of the matrix. Whatever the actual shape of *c*, it will be converted to a 1-D array.
- r** [array_like, optional] Last row of the matrix. If None, *r = zeros_like(c)* is assumed. *r*[0] is ignored; the last row of the returned matrix is [*c*[-1], *r*[1:]]. Whatever the actual shape of *r*, it will be converted to a 1-D array.

Returns

- A** [(len(*c*), len(*r*)) ndarray] The Hankel matrix. Dtype is the same as (*c*[0] + *r*[0]).dtype.

See also:[*toeplitz*](#)

Toeplitz matrix

[*circulant*](#)

circulant matrix

Examples

```
>>> from scipy.linalg import hankel
>>> hankel([1, 17, 99])
array([[ 1, 17, 99],
       [17, 99,  0],
       [99,  0,  0]])
>>> hankel([1, 2, 3, 4], [4, 7, 7, 8, 9])
array([[1, 2, 3, 4, 7],
       [2, 3, 4, 7, 7],
       [3, 4, 7, 7, 8],
       [4, 7, 7, 8, 9]])
```

scipy.linalg.helmert`scipy.linalg.helmert` (*n*, *full=False*)Create an Helmert matrix of order *n*.

This has applications in statistics, compositional or simplicial analysis, and in Aitchison geometry.

Parameters

- n** [int] The size of the array to create.
- full** [bool, optional] If True the (n, n) ndarray will be returned. Otherwise the submatrix that does not include the first row will be returned. Default: False.

Returns

M [ndarray] The Helmert matrix. The shape is (n, n) or (n-1, n) depending on the *full* argument.

Examples

```
>>> from scipy.linalg import helmert
>>> helmert(5, full=True)
array([[ 0.4472136 ,  0.4472136 ,  0.4472136 ,  0.4472136 ,  0.4472136 ],
       [ 0.70710678, -0.70710678,  0.          ,  0.          ,  0.          ],
       [ 0.40824829,  0.40824829, -0.81649658,  0.          ,  0.          ],
       [ 0.28867513,  0.28867513,  0.28867513, -0.8660254 ,  0.          ],
       [ 0.2236068 ,  0.2236068 ,  0.2236068 ,  0.2236068 , -0.89442719]])
```

scipy.linalg.hilbert

scipy.linalg.**hilbert** (*n*)

Create a Hilbert matrix of order *n*.

Returns the *n* by *n* array with entries $h[i,j] = 1 / (i + j + 1)$.

Parameters

n [int] The size of the array to create.

Returns

h [(n, n) ndarray] The Hilbert matrix.

See also:

invhilbert

Compute the inverse of a Hilbert matrix.

Notes

New in version 0.10.0.

Examples

```
>>> from scipy.linalg import hilbert
>>> hilbert(3)
array([[ 1.          ,  0.5          ,  0.33333333],
       [ 0.5          ,  0.33333333,  0.25          ],
       [ 0.33333333,  0.25          ,  0.2           ]])
```

scipy.linalg.invhilbert

`scipy.linalg.invhilbert` (*n*, *exact=False*)

Compute the inverse of the Hilbert matrix of order *n*.

The entries in the inverse of a Hilbert matrix are integers. When *n* is greater than 14, some entries in the inverse exceed the upper limit of 64 bit integers. The *exact* argument provides two options for dealing with these large integers.

Parameters

n [int] The order of the Hilbert matrix.
exact [bool, optional] If False, the data type of the array that is returned is `np.float64`, and the array is an approximation of the inverse. If True, the array is the exact integer inverse array. To represent the exact inverse when *n* > 14, the returned array is an object array of long integers. For *n* ≤ 14, the exact inverse is returned as an array with data type `np.int64`.

Returns

invh [(*n*, *n*) ndarray] The data type of the array is `np.float64` if *exact* is False. If *exact* is True, the data type is either `np.int64` (for *n* ≤ 14) or object (for *n* > 14). In the latter case, the objects in the array will be long integers.

See also:

[*hilbert*](#)

Create a Hilbert matrix.

Notes

New in version 0.10.0.

Examples

```
>>> from scipy.linalg import invhilbert
>>> invhilbert(4)
array([[ 16., -120., 240., -140.],
       [-120., 1200., -2700., 1680.],
       [ 240., -2700., 6480., -4200.],
       [-140., 1680., -4200., 2800.]])
>>> invhilbert(4, exact=True)
array([[ 16, -120, 240, -140],
       [-120, 1200, -2700, 1680],
       [ 240, -2700, 6480, -4200],
       [-140, 1680, -4200, 2800]], dtype=int64)
>>> invhilbert(16) [7,7]
4.2475099528537506e+19
>>> invhilbert(16, exact=True) [7,7]
42475099528537378560
```

scipy.linalg.leslie

`scipy.linalg.leslie` (*f*, *s*)

Create a Leslie matrix.

Given the length *n* array of fecundity coefficients *f* and the length *n*-1 array of survival coefficients *s*, return the associated Leslie matrix.

Parameters

- f** [(N,) array_like] The “fecundity” coefficients.
s [(N-1,) array_like] The “survival” coefficients, has to be 1-D. The length of *s* must be one less than the length of *f*, and it must be at least 1.

Returns

- L** [(N, N) ndarray] The array is zero except for the first row, which is *f*, and the first sub-diagonal, which is *s*. The data-type of the array will be the data-type of $f[0] + s[0]$.

Notes

New in version 0.8.0.

The Leslie matrix is used to model discrete-time, age-structured population growth [1] [2]. In a population with *n* age classes, two sets of parameters define a Leslie matrix: the *n* “fecundity coefficients”, which give the number of offspring per-capita produced by each age class, and the *n* - 1 “survival coefficients”, which give the per-capita survival rate of each age class.

References

[1], [2]

Examples

```
>>> from scipy.linalg import leslie
>>> leslie([0.1, 2.0, 1.0, 0.1], [0.2, 0.8, 0.7])
array([[ 0.1,  2. ,  1. ,  0.1],
       [ 0.2,  0. ,  0. ,  0. ],
       [ 0. ,  0.8,  0. ,  0. ],
       [ 0. ,  0. ,  0.7,  0. ]])
```

scipy.linalg.pascal

`scipy.linalg.pascal` (*n*, *kind*='symmetric', *exact*=True)

Returns the *n* x *n* Pascal matrix.

The Pascal matrix is a matrix containing the binomial coefficients as its elements.

Parameters

- n** [int] The size of the matrix to create; that is, the result is an *n* x *n* matrix.
kind [str, optional] Must be one of ‘symmetric’, ‘lower’, or ‘upper’. Default is ‘symmetric’.

exact [bool, optional] If *exact* is True, the result is either an array of type `numpy.uint64` (if $n < 35$) or an object array of Python long integers. If *exact* is False, the coefficients in the matrix are computed using `scipy.special.comb` with *exact=False*. The result will be a floating point array, and the values in the array will not be the exact coefficients, but this version is much faster than *exact=True*.

Returns

p [(n, n) ndarray] The Pascal matrix.

See also:

invpascal

Notes

See https://en.wikipedia.org/wiki/Pascal_matrix for more information about Pascal matrices.

New in version 0.11.0.

Examples

```
>>> from scipy.linalg import pascal
>>> pascal(4)
array([[ 1,  1,  1,  1],
       [ 1,  2,  3,  4],
       [ 1,  3,  6, 10],
       [ 1,  4, 10, 20]], dtype=uint64)
>>> pascal(4, kind='lower')
array([[1, 0, 0, 0],
       [1, 1, 0, 0],
       [1, 2, 1, 0],
       [1, 3, 3, 1]], dtype=uint64)
>>> pascal(50)[-1, -1]
25477612258980856902730428600
>>> from scipy.special import comb
>>> comb(98, 49, exact=True)
25477612258980856902730428600
```

scipy.linalg.invpascal

`scipy.linalg.invpascal` (*n*, *kind*='symmetric', *exact*=True)

Returns the inverse of the $n \times n$ Pascal matrix.

The Pascal matrix is a matrix containing the binomial coefficients as its elements.

Parameters

n [int] The size of the matrix to create; that is, the result is an $n \times n$ matrix.

kind [str, optional] Must be one of 'symmetric', 'lower', or 'upper'. Default is 'symmetric'.

exact [bool, optional] If *exact* is True, the result is either an array of type `numpy.int64` (if $n \leq 35$) or an object array of Python integers. If *exact* is False, the coefficients in the matrix are computed using `scipy.special.comb` with *exact=False*. The result will be a floating point array, and for large *n*, the values in the array will not be the exact coefficients.

Returns**invp** [(n, n) ndarray] The inverse of the Pascal matrix.

See also:

*pascal***Notes**

New in version 0.16.0.

References

[1], [2]

Examples

```
>>> from scipy.linalg import invpascal, pascal
>>> invp = invpascal(5)
>>> invp
array([[ 5, -10, 10, -5,  1],
       [-10, 30, -35, 19, -4],
       [ 10, -35, 46, -27,  6],
       [ -5, 19, -27, 17, -4],
       [  1, -4,  6, -4,  1]])
```

```
>>> p = pascal(5)
>>> p.dot(invp)
array([[ 1.,  0.,  0.,  0.,  0.],
       [ 0.,  1.,  0.,  0.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  0.,  0.,  1.,  0.],
       [ 0.,  0.,  0.,  0.,  1.]])
```

An example of the use of *kind* and *exact*:

```
>>> invpascal(5, kind='lower', exact=False)
array([[ 1., -0.,  0., -0.,  0.],
       [-1.,  1., -0.,  0., -0.],
       [ 1., -2.,  1., -0.,  0.],
       [-1.,  3., -3.,  1., -0.],
       [ 1., -4.,  6., -4.,  1.]])
```

scipy.linalg toeplitz

`scipy.linalg.toeplitz(c, r=None)`

Construct a Toeplitz matrix.

The Toeplitz matrix has constant diagonals, with `c` as its first column and `r` as its first row. If `r` is not given, `r == conjugate(c)` is assumed.

Parameters

- c** [array_like] First column of the matrix. Whatever the actual shape of `c`, it will be converted to a 1-D array.
- r** [array_like, optional] First row of the matrix. If `None`, `r = conjugate(c)` is assumed; in this case, if `c[0]` is real, the result is a Hermitian matrix. `r[0]` is ignored; the first row of the returned matrix is `[c[0], r[1:]]`. Whatever the actual shape of `r`, it will be converted to a 1-D array.

Returns

- A** [(len(c), len(r)) ndarray] The Toeplitz matrix. Dtype is the same as `(c[0] + r[0]).dtype`.

See also:

circulant

circulant matrix

hankel

Hankel matrix

solve_toeplitz

Solve a Toeplitz system.

Notes

The behavior when `c` or `r` is a scalar, or when `c` is complex and `r` is `None`, was changed in version 0.8.0. The behavior in previous versions was undocumented and is no longer supported.

Examples

```
>>> from scipy.linalg import toeplitz
>>> toeplitz([1,2,3], [1,4,5,6])
array([[1, 4, 5, 6],
       [2, 1, 4, 5],
       [3, 2, 1, 4]])
>>> toeplitz([1.0, 2+3j, 4-1j])
array([[ 1.+0.j,  2.-3.j,  4.+1.j],
       [ 2.+3.j,  1.+0.j,  2.-3.j],
       [ 4.-1.j,  2.+3.j,  1.+0.j]])
```

scipy.linalg.tri

`scipy.linalg.tri` (*N*, *M=None*, *k=0*, *dtype=None*)

Construct (*N*, *M*) matrix filled with ones at and below the *k*th diagonal.

The matrix has $A[i,j] == 1$ for $i \leq j + k$

Parameters

- N** [int] The size of the first dimension of the matrix.
- M** [int or None, optional] The size of the second dimension of the matrix. If *M* is None, *M* = *N* is assumed.
- k** [int, optional] Number of subdiagonal below which matrix is filled with ones. *k* = 0 is the main diagonal, *k* < 0 subdiagonal and *k* > 0 superdiagonal.
- dtype** [dtype, optional] Data type of the matrix.

Returns

- tri** [(*N*, *M*) ndarray] Tri matrix.

Examples

```
>>> from scipy.linalg import tri
>>> tri(3, 5, 2, dtype=int)
array([[1, 1, 1, 0, 0],
       [1, 1, 1, 1, 0],
       [1, 1, 1, 1, 1]])
>>> tri(3, 5, -1, dtype=int)
array([[0, 0, 0, 0, 0],
       [1, 0, 0, 0, 0],
       [1, 1, 0, 0, 0]])
```

6.10.8 Low-level routines

<code>get_blas_funcs</code> (names[, arrays, dtype, ilp64])	Return available BLAS function objects from names.
<code>get_lapack_funcs</code> (names[, arrays, dtype, ilp64])	Return available LAPACK function objects from names.
<code>find_best_blas_type</code> ([arrays, dtype])	Find best-matching BLAS/LAPACK type.

scipy.linalg.get_blas_funcs

`scipy.linalg.get_blas_funcs` (*names*, *arrays=()*, *dtype=None*, *ilp64=False*)

Return available BLAS function objects from names.

Arrays are used to determine the optimal prefix of BLAS routines.

Parameters

- names** [str or sequence of str] Name(s) of BLAS functions without type prefix.
- arrays** [sequence of ndarrays, optional] Arrays can be given to determine optimal prefix of BLAS routines. If not given, double-precision routines will be used, otherwise the most generic type in arrays will be used.
- dtype** [str or dtype, optional] Data-type specifier. Not used if *arrays* is non-empty.

ilp64 [{True, False, 'preferred'}, optional] Whether to return ILP64 routine variant. Choosing 'preferred' returns ILP64 routine if available, and otherwise the 32-bit routine. Default: False

Returns

funcs [list] List containing the found function(s).

Notes

This routine automatically chooses between Fortran/C interfaces. Fortran code is used whenever possible for arrays with column major order. In all other cases, C code is preferred.

In BLAS, the naming convention is that all functions start with a type prefix, which depends on the type of the principal matrix. These can be one of {'s', 'd', 'c', 'z'} for the NumPy types {float32, float64, complex64, complex128} respectively. The code and the dtype are stored in attributes *typecode* and *dtype* of the returned functions.

Examples

```
>>> import scipy.linalg as LA
>>> a = np.random.rand(3,2)
>>> x_gemv = LA.get_blas_funcs('gemv', (a,))
>>> x_gemv.typecode
'd'
>>> x_gemv = LA.get_blas_funcs('gemv', (a*1j,))
>>> x_gemv.typecode
'z'
```

scipy.linalg.get_lapack_funcs

`scipy.linalg.get_lapack_funcs` (*names*, *arrays*=(), *dtype*=None, *ilp64*=False)

Return available LAPACK function objects from names.

Arrays are used to determine the optimal prefix of LAPACK routines.

Parameters

names [str or sequence of str] Name(s) of LAPACK functions without type prefix.

arrays [sequence of ndarrays, optional] Arrays can be given to determine optimal prefix of LAPACK routines. If not given, double-precision routines will be used, otherwise the most generic type in arrays will be used.

dtype [str or dtype, optional] Data-type specifier. Not used if *arrays* is non-empty.

ilp64 [{True, False, 'preferred'}, optional] Whether to return ILP64 routine variant. Choosing 'preferred' returns ILP64 routine if available, and otherwise the 32-bit routine. Default: False

Returns

funcs [list] List containing the found function(s).

Notes

This routine automatically chooses between Fortran/C interfaces. Fortran code is used whenever possible for arrays with column major order. In all other cases, C code is preferred.

In LAPACK, the naming convention is that all functions start with a type prefix, which depends on the type of the principal matrix. These can be one of {'s', 'd', 'c', 'z'} for the NumPy types {float32, float64, complex64, complex128} respectively, and are stored in attribute `typecode` of the returned functions.

Examples

Suppose we would like to use `?lange` routine which computes the selected norm of an array. We pass our array in order to get the correct `'lange'` flavor.

```
>>> import scipy.linalg as LA
>>> a = np.random.rand(3,2)
>>> x_lange = LA.get_lapack_funcs('lange', (a,))
>>> x_lange.typecode
'd'
>>> x_lange = LA.get_lapack_funcs('lange', (a*1j,))
>>> x_lange.typecode
'z'
```

Several LAPACK routines work best when its internal WORK array has the optimal size (big enough for fast computation and small enough to avoid waste of memory). This size is determined also by a dedicated query to the function which is often wrapped as a standalone function and commonly denoted as `###_lwork`. Below is an example for `?sysv`

```
>>> import scipy.linalg as LA
>>> a = np.random.rand(1000,1000)
>>> b = np.random.rand(1000,1)*1j
>>> # We pick up zsysv and zsysv_lwork due to b array
... xsysv, xlwork = LA.get_lapack_funcs(('sysv', 'sysv_lwork'), (a, b))
>>> opt_lwork, _ = xlwork(a.shape[0]) # returns a complex for 'z' prefix
>>> udut, ipiv, x, info = xsysv(a, b, lwork=int(opt_lwork.real))
```

scipy.linalg.find_best_blas_type

`scipy.linalg.find_best_blas_type` (*arrays*=(), *dtype*=None)
Find best-matching BLAS/LAPACK type.

Arrays are used to determine the optimal prefix of BLAS routines.

Parameters

- arrays** [sequence of ndarrays, optional] Arrays can be given to determine optimal prefix of BLAS routines. If not given, double-precision routines will be used, otherwise the most generic type in arrays will be used.
- dtype** [str or dtype, optional] Data-type specifier. Not used if *arrays* is non-empty.

Returns

- prefix** [str] BLAS/LAPACK prefix character.
- dtype** [dtype] Inferred Numpy data type.

prefer_fortran

[bool] Whether to prefer Fortran order routines over C order.

Examples

```

>>> import scipy.linalg.blas as bla
>>> a = np.random.rand(10,15)
>>> b = np.asfortranarray(a) # Change the memory layout order
>>> bla.find_best_blas_type((a,))
('d', dtype('float64'), False)
>>> bla.find_best_blas_type((a*1j,))
('z', dtype('complex128'), False)
>>> bla.find_best_blas_type((b,))
('d', dtype('float64'), True)

```

See also:*scipy.linalg.blas* – Low-level BLAS functions*scipy.linalg.lapack* – Low-level LAPACK functions*scipy.linalg.cython_blas* – Low-level BLAS functions for Cython*scipy.linalg.cython_lapack* – Low-level LAPACK functions for Cython

6.11 Low-level BLAS functions (*scipy.linalg.blas*)

This module contains low-level functions from the BLAS library.

New in version 0.12.0.

Note: The common `overwrite_<>` option in many routines, allows the input arrays to be overwritten to avoid extra memory allocation. However this requires the array to satisfy two conditions which are memory order and the data type to match exactly the order and the type expected by the routine.

As an example, if you pass a double precision float array to any `S . . .` routine which expects single precision arguments, `f2py` will create an intermediate array to match the argument types and overwriting will be performed on that intermediate array.

Similarly, if a C-contiguous array is passed, `f2py` will pass a FORTRAN-contiguous array internally. Please make sure that these details are satisfied. More information can be found in the `f2py` documentation.

Warning: These functions do little to no error checking. It is possible to cause crashes by mis-using them, so prefer using the higher-level routines in *scipy.linalg*.

6.11.1 Finding functions

<code>get_blas_funcs(names[, arrays, dtype, ilp64])</code>	Return available BLAS function objects from names.
<code>find_best_blas_type([arrays, dtype])</code>	Find best-matching BLAS/LAPACK type.

scipy.linalg.blas.get_blas_funcs

`scipy.linalg.blas.get_blas_funcs` (*names*, *arrays*=(), *dtype*=None, *ilp64*=False)

Return available BLAS function objects from names.

Arrays are used to determine the optimal prefix of BLAS routines.

Parameters

names	[str or sequence of str] Name(s) of BLAS functions without type prefix.
arrays	[sequence of ndarrays, optional] Arrays can be given to determine optimal prefix of BLAS routines. If not given, double-precision routines will be used, otherwise the most generic type in arrays will be used.
dtype	[str or dtype, optional] Data-type specifier. Not used if <i>arrays</i> is non-empty.
ilp64	[[True, False, 'preferred'], optional] Whether to return ILP64 routine variant. Choosing 'preferred' returns ILP64 routine if available, and otherwise the 32-bit routine. Default: False

Returns

funcs	[list] List containing the found function(s).
--------------	---

Notes

This routine automatically chooses between Fortran/C interfaces. Fortran code is used whenever possible for arrays with column major order. In all other cases, C code is preferred.

In BLAS, the naming convention is that all functions start with a type prefix, which depends on the type of the principal matrix. These can be one of {'s', 'd', 'c', 'z'} for the NumPy types {float32, float64, complex64, complex128} respectively. The code and the dtype are stored in attributes *typecode* and *dtype* of the returned functions.

Examples

```
>>> import scipy.linalg as LA
>>> a = np.random.rand(3, 2)
>>> x_gemv = LA.get_blas_funcs('gemv', (a,))
>>> x_gemv.typecode
'd'
>>> x_gemv = LA.get_blas_funcs('gemv', (a*1j,))
>>> x_gemv.typecode
'z'
```


scipy.linalg.blas.find_best_blas_type

`scipy.linalg.blas.find_best_blas_type` (*arrays=()*, *dtype=None*)

Find best-matching BLAS/LAPACK type.

Arrays are used to determine the optimal prefix of BLAS routines.

Parameters

- arrays** [sequence of ndarrays, optional] Arrays can be given to determine optimal prefix of BLAS routines. If not given, double-precision routines will be used, otherwise the most generic type in arrays will be used.
- dtype** [str or dtype, optional] Data-type specifier. Not used if *arrays* is non-empty.

Returns

- prefix** [str] BLAS/LAPACK prefix character.
- dtype** [dtype] Inferred Numpy data type.
- prefer_fortran** [bool] Whether to prefer Fortran order routines over C order.

Examples

```
>>> import scipy.linalg.blas as bla
>>> a = np.random.rand(10,15)
>>> b = np.asfortranarray(a) # Change the memory layout order
>>> bla.find_best_blas_type((a,))
('d', dtype('float64'), False)
>>> bla.find_best_blas_type((a*1j,))
('z', dtype('complex128'), False)
>>> bla.find_best_blas_type((b,))
('d', dtype('float64'), True)
```

6.11.2 BLAS Level 1 functions

<code>caxpy(x,y,[n,a,offx,incx,offy,incy])</code>	Wrapper for <code>caxpy</code> .
<code>ccopy(x,y,[n,offx,incx,offy,incy])</code>	Wrapper for <code>ccopy</code> .
<code>cdotc(x,y,[n,offx,incx,offy,incy])</code>	Wrapper for <code>cdotc</code> .
<code>cdotu(x,y,[n,offx,incx,offy,incy])</code>	Wrapper for <code>cdotu</code> .
<code>crotg(a,b)</code>	Wrapper for <code>crotg</code> .
<code>cscal(a,x,[n,offx,incx])</code>	Wrapper for <code>cscal</code> .
<code>csrot(...)</code>	Wrapper for <code>csrot</code> .
<code>csscal(a,x,[n,offx,incx,overwrite_x])</code>	Wrapper for <code>csscal</code> .
<code>cswap(x,y,[n,offx,incx,offy,incy])</code>	Wrapper for <code>cswap</code> .
<code>dasum(x,[n,offx,incx])</code>	Wrapper for <code>dasum</code> .
<code>daxpy(x,y,[n,a,offx,incx,offy,incy])</code>	Wrapper for <code>daxpy</code> .
<code>dcopy(x,y,[n,offx,incx,offy,incy])</code>	Wrapper for <code>dcopy</code> .
<code>ddot(x,y,[n,offx,incx,offy,incy])</code>	Wrapper for <code>ddot</code> .
<code>dnrm2(x,[n,offx,incx])</code>	Wrapper for <code>dnrm2</code> .
<code>drot(...)</code>	Wrapper for <code>drot</code> .
<code>drotg(a,b)</code>	Wrapper for <code>drotg</code> .

continues on next page

Table 99 – continued from previous page

<i>drotm(...)</i>	Wrapper for <code>drotm</code> .
<i>drotmg(d1,d2,x1,y1)</i>	Wrapper for <code>drotmg</code> .
<i>dscal(a,x,[n,offx,incx])</i>	Wrapper for <code>dscal</code> .
<i>dswap(x,y,[n,offx,incx,offy,incy])</i>	Wrapper for <code>dswap</code> .
<i>dzasum(x,[n,offx,incx])</i>	Wrapper for <code>dzasum</code> .
<i>dznrm2(x,[n,offx,incx])</i>	Wrapper for <code>dznrm2</code> .
<i>icamax(x,[n,offx,incx])</i>	Wrapper for <code>icamax</code> .
<i>idamax(x,[n,offx,incx])</i>	Wrapper for <code>idamax</code> .
<i>isamax(x,[n,offx,incx])</i>	Wrapper for <code>isamax</code> .
<i>izamax(x,[n,offx,incx])</i>	Wrapper for <code>izamax</code> .
<i>sasum(x,[n,offx,incx])</i>	Wrapper for <code>sasum</code> .
<i>saxpy(x,y,[n,a,offx,incx,offy,incy])</i>	Wrapper for <code>saxpy</code> .
<i>scasum(x,[n,offx,incx])</i>	Wrapper for <code>scasum</code> .
<i>scnrm2(x,[n,offx,incx])</i>	Wrapper for <code>scnrm2</code> .
<i>scopy(x,y,[n,offx,incx,offy,incy])</i>	Wrapper for <code>scopy</code> .
<i>sdot(x,y,[n,offx,incx,offy,incy])</i>	Wrapper for <code>sdot</code> .
<i>snrm2(x,[n,offx,incx])</i>	Wrapper for <code>snrm2</code> .
<i>srot(...)</i>	Wrapper for <code>srot</code> .
<i>srotg(a,b)</i>	Wrapper for <code>srotg</code> .
<i>srotm(...)</i>	Wrapper for <code>srotm</code> .
<i>srotmg(d1,d2,x1,y1)</i>	Wrapper for <code>srotmg</code> .
<i>sscal(a,x,[n,offx,incx])</i>	Wrapper for <code>sscal</code> .
<i>sswap(x,y,[n,offx,incx,offy,incy])</i>	Wrapper for <code>sswap</code> .
<i>zaxpy(x,y,[n,a,offx,incx,offy,incy])</i>	Wrapper for <code>zaxpy</code> .
<i>zcopy(x,y,[n,offx,incx,offy,incy])</i>	Wrapper for <code>zcopy</code> .
<i>zdotc(x,y,[n,offx,incx,offy,incy])</i>	Wrapper for <code>zdotc</code> .
<i>zdotu(x,y,[n,offx,incx,offy,incy])</i>	Wrapper for <code>zdotu</code> .
<i>zdrot(...)</i>	Wrapper for <code>zdrot</code> .
<i>zdscal(a,x,[n,offx,incx,overwrite_x])</i>	Wrapper for <code>zdscal</code> .
<i>zrotg(a,b)</i>	Wrapper for <code>zrotg</code> .
<i>zscal(a,x,[n,offx,incx])</i>	Wrapper for <code>zscal</code> .
<i>zswap(x,y,[n,offx,incx,offy,incy])</i>	Wrapper for <code>zswap</code> .

scipy.linalg.blas.caxpy

`scipy.linalg.blas.caxpy(x, y[, n, a, offx, incx, offy, incy]) = <fortran object>`

Wrapper for `caxpy`.

Parameters

x [input rank-1 array('F') with bounds (*)]
y [input rank-1 array('F') with bounds (*)]

Returns

z [rank-1 array('F') with bounds (*) and y storage]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$
a [input complex, optional] Default: (1.0, 0.0)
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0

incy [input int, optional] Default: 1

scipy.linalg.blas.ccopy

`scipy.linalg.blas.ccopy(x, y[, n, offx, incx, offy, incy]) = <fortran object>`

Wrapper for `ccopy`.

Parameters

x [input rank-1 array('F') with bounds (*)]
y [input rank-1 array('F') with bounds (*)]

Returns

y [rank-1 array('F') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.blas.cdotc

`scipy.linalg.blas.cdotc(x, y[, n, offx, incx, offy, incy]) = <fortran cdotc>`

Wrapper for `cdotc`.

Parameters

x [input rank-1 array('F') with bounds (*)]
y [input rank-1 array('F') with bounds (*)]

Returns

xy [complex]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.blas.cdotu

`scipy.linalg.blas.cdotu(x, y[, n, offx, incx, offy, incy]) = <fortran cdotu>`

Wrapper for `cdotu`.

Parameters

x [input rank-1 array('F') with bounds (*)]
y [input rank-1 array('F') with bounds (*)]

Returns

xy [complex]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.blas.crotg

`scipy.linalg.blas.crotg(a, b) = <fortran object>`
 Wrapper for `crotg`.

Parameters

a [input complex]
b [input complex]

Returns

c [complex]
s [complex]

scipy.linalg.blas.cscal

`scipy.linalg.blas.cscal(a, x[, n, offx, incx]) = <fortran object>`
 Wrapper for `cscal`.

Parameters

a [input complex]
x [input rank-1 array('F') with bounds (*)]

Returns

x [rank-1 array('F') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1

scipy.linalg.blas.csrot

`scipy.linalg.blas.csrot(x, y, c, s[, n, offx, incx, offy, incy, overwrite_x, overwrite_y]) = <fortran object>`

Wrapper for `csrot`.

Parameters

x [input rank-1 array('F') with bounds (*)]
y [input rank-1 array('F') with bounds (*)]
c [input float]
s [input float]

Returns

x [rank-1 array('F') with bounds (*)]

y [rank-1 array('F') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-1-offx)/abs(incx)+1
overwrite_x [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
overwrite_y [input int, optional] Default: 0
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.blas.csscal

`scipy.linalg.blas.csscal(a, x[, n, offx, incx, overwrite_x]) = <fortran object>`
 Wrapper for `csscal`.

Parameters

a [input float]
x [input rank-1 array('F') with bounds (*)]

Returns

x [rank-1 array('F') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)
overwrite_x [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1

scipy.linalg.blas.cswap

`scipy.linalg.blas.cswap(x, y[, n, offx, incx, offy, incy]) = <fortran object>`
 Wrapper for `cswap`.

Parameters

x [input rank-1 array('F') with bounds (*)]
y [input rank-1 array('F') with bounds (*)]

Returns

x [rank-1 array('F') with bounds (*)]
y [rank-1 array('F') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.blas.dasum

`scipy.linalg.blas.dasum(x[, n, offx, incx]) = <fortran dasum>`
 Wrapper for dasum.

Parameters

x [input rank-1 array('d') with bounds (*)]

Returns

s [float]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

scipy.linalg.blas.daxpy

`scipy.linalg.blas.daxpy(x, y[, n, a, offx, incx, offy, incy]) = <fortran object>`
 Wrapper for daxpy.

Parameters

x [input rank-1 array('d') with bounds (*)]

y [input rank-1 array('d') with bounds (*)]

Returns

z [rank-1 array('d') with bounds (*) and y storage]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)

a [input float, optional] Default: 1.0

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

offy [input int, optional] Default: 0

incy [input int, optional] Default: 1

scipy.linalg.blas.dcopy

`scipy.linalg.blas.dcopy(x, y[, n, offx, incx, offy, incy]) = <fortran object>`
 Wrapper for dcopy.

Parameters

x [input rank-1 array('d') with bounds (*)]

y [input rank-1 array('d') with bounds (*)]

Returns

y [rank-1 array('d') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.blas.ddot

`scipy.linalg.blas.ddot(x, y[, n, offx, incx, offy, incy]) = <fortran ddot>`
 Wrapper for `ddot`.

Parameters

x [input rank-1 array('d') with bounds (*)]
y [input rank-1 array('d') with bounds (*)]

Returns

xy [float]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.blas.dnorm2

`scipy.linalg.blas.dnorm2(x[, n, offx, incx]) = <fortran dnorm2>`
 Wrapper for `dnrm2`.

Parameters

x [input rank-1 array('d') with bounds (*)]

Returns

n2 [float]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1

scipy.linalg.blas.drot

`scipy.linalg.blas.drot(x, y, c, s[, n, offx, incx, offy, incy, overwrite_x, overwrite_y]) = <fortran object>`

Wrapper for `drot`.

Parameters

x [input rank-1 array('d') with bounds (*)]
y [input rank-1 array('d') with bounds (*)]
c [input float]
s [input float]

Returns

x [rank-1 array('d') with bounds (*)]
y [rank-1 array('d') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-1-offx)/abs(incx)+1
overwrite_x [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
overwrite_y [input int, optional] Default: 0
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.blas.drotg

`scipy.linalg.blas.drotg(a, b) = <fortran object>`
 Wrapper for drotg.

Parameters

a [input float]
b [input float]

Returns

c [float]
s [float]

scipy.linalg.blas.drotm

`scipy.linalg.blas.drotm(x, y, param[, n, offx, incx, offy, incy, overwrite_x, overwrite_y]) = <fortran object>`

Wrapper for drotm.

Parameters

x [input rank-1 array('d') with bounds (*)]
y [input rank-1 array('d') with bounds (*)]
param [input rank-1 array('d') with bounds (5)]

Returns

x [rank-1 array('d') with bounds (*)]
y [rank-1 array('d') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)
overwrite_x [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
overwrite_y [input int, optional] Default: 0
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.blas.drotmg

`scipy.linalg.blas.drotmg(d1, d2, x1, y1) = <fortran object>`
 Wrapper for `drotmg`.

Parameters

d1 [input float]
d2 [input float]
x1 [input float]
y1 [input float]

Returns

param [rank-1 array('d') with bounds (5)]

scipy.linalg.blas.dscal

`scipy.linalg.blas.dscal(a, x[, n, offx, incx]) = <fortran object>`
 Wrapper for `dscal`.

Parameters

a [input float]
x [input rank-1 array('d') with bounds (*)]

Returns

x [rank-1 array('d') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1

scipy.linalg.blas.dswap

`scipy.linalg.blas.dswap(x, y[, n, offx, incx, offy, incy]) = <fortran object>`
 Wrapper for `dswap`.

Parameters

x [input rank-1 array('d') with bounds (*)]
y [input rank-1 array('d') with bounds (*)]

Returns

x [rank-1 array('d') with bounds (*)]
y [rank-1 array('d') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.blas.dzasum

`scipy.linalg.blas.dzasum(x[, n, offx, incx]) = <fortran dzasum>`
Wrapper for `dzasum`.

Parameters

x [input rank-1 array('D') with bounds (*)]

Returns

s [float]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

scipy.linalg.blas.dznrm2

`scipy.linalg.blas.dznrm2(x[, n, offx, incx]) = <fortran dznrm2>`
Wrapper for `dznrm2`.

Parameters

x [input rank-1 array('D') with bounds (*)]

Returns

n2 [float]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

scipy.linalg.blas.icamax

`scipy.linalg.blas.icamax(x[, n, offx, incx]) = <fortran object>`
Wrapper for `icamax`.

Parameters

x [input rank-1 array('F') with bounds (*)]

Returns

k [int]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

scipy.linalg.blas.idamax

`scipy.linalg.blas.idamax(x[, n, offx, incx]) = <fortran object>`
 Wrapper for idamax.

Parameters

x [input rank-1 array('d') with bounds (*)]

Returns

k [int]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

scipy.linalg.blas.isamax

`scipy.linalg.blas.isamax(x[, n, offx, incx]) = <fortran object>`
 Wrapper for isamax.

Parameters

x [input rank-1 array('f') with bounds (*)]

Returns

k [int]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

scipy.linalg.blas.izamax

`scipy.linalg.blas.izamax(x[, n, offx, incx]) = <fortran object>`
 Wrapper for izamax.

Parameters

x [input rank-1 array('D') with bounds (*)]

Returns

k [int]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

scipy.linalg.blas.sasum

`scipy.linalg.blas.sasum(x[, n, offx, incx]) = <fortran sasum>`
Wrapper for `sasum`.

Parameters

x [input rank-1 array('f') with bounds (*)]

Returns

s [float]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

scipy.linalg.blas.saxpy

`scipy.linalg.blas.saxpy(x, y[, n, a, offx, incx, offy, incy]) = <fortran object>`
Wrapper for `saxpy`.

Parameters

x [input rank-1 array('f') with bounds (*)]

y [input rank-1 array('f') with bounds (*)]

Returns

z [rank-1 array('f') with bounds (*) and y storage]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$

a [input float, optional] Default: 1.0

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

offy [input int, optional] Default: 0

incy [input int, optional] Default: 1

scipy.linalg.blas.scasum

`scipy.linalg.blas.scasum(x[, n, offx, incx]) = <fortran scasum>`
Wrapper for `scasum`.

Parameters

x [input rank-1 array('F') with bounds (*)]

Returns

s [float]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

scipy.linalg.blas.scnrm2

`scipy.linalg.blas.scnrm2(x[, n, offx, incx]) = <fortran scnrm2>`
 Wrapper for `scnrm2`.

Parameters

x [input rank-1 array('F') with bounds (*)]

Returns

n2 [float]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

scipy.linalg.blas.scopy

`scipy.linalg.blas.scopy(x, y[, n, offx, incx, offy, incy]) = <fortran object>`
 Wrapper for `scopy`.

Parameters

x [input rank-1 array('f') with bounds (*)]

y [input rank-1 array('f') with bounds (*)]

Returns

y [rank-1 array('f') with bounds (*)]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

offy [input int, optional] Default: 0

incy [input int, optional] Default: 1

scipy.linalg.blas.sdot

`scipy.linalg.blas.sdot(x, y[, n, offx, incx, offy, incy]) = <fortran sdot>`
 Wrapper for `sdot`.

Parameters

x [input rank-1 array('f') with bounds (*)]

y [input rank-1 array('f') with bounds (*)]

Returns

xy [float]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

offy [input int, optional] Default: 0

incy [input int, optional] Default: 1

scipy.linalg.blas.snrnm2

`scipy.linalg.blas.snrnm2(x[, n, offx, incx]) = <fortran snrm2>`

Wrapper for `snrm2`.

Parameters

x [input rank-1 array('f') with bounds (*)]

Returns

n2 [float]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

scipy.linalg.blas.srot

`scipy.linalg.blas.srot(x, y, c, s[, n, offx, incx, offy, incy, overwrite_x, overwrite_y]) = <fortran object>`

Wrapper for `srot`.

Parameters

x [input rank-1 array('f') with bounds (*)]

y [input rank-1 array('f') with bounds (*)]

c [input float]

s [input float]

Returns

x [rank-1 array('f') with bounds (*)]

y [rank-1 array('f') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-1-offx)/abs(incx)+1

overwrite_x [input int, optional] Default: 0

offx [input int, optional] Default: 0

incx [input int, optional] Default: 1

overwrite_y [input int, optional] Default: 0

offy [input int, optional] Default: 0

incy [input int, optional] Default: 1

scipy.linalg.blas.srotg

`scipy.linalg.blas.srotg(a, b) = <fortran object>`
 Wrapper for `srotg`.

Parameters

a [input float]
b [input float]

Returns

c [float]
s [float]

scipy.linalg.blas.srotm

`scipy.linalg.blas.srotm(x, y, param[, n, offx, incx, offy, incy, overwrite_x, overwrite_y]) = <fortran object>`
 Wrapper for `srotm`.

Parameters

x [input rank-1 array('f') with bounds (*)]
y [input rank-1 array('f') with bounds (*)]
param [input rank-1 array('f') with bounds (5)]

Returns

x [rank-1 array('f') with bounds (*)]
y [rank-1 array('f') with bounds (*)]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$
overwrite_x [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
overwrite_y [input int, optional] Default: 0
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.blas.srotmg

`scipy.linalg.blas.srotmg(d1, d2, x1, y1) = <fortran object>`
 Wrapper for `srotmg`.

Parameters

d1 [input float]
d2 [input float]
x1 [input float]
y1 [input float]

Returns

param [rank-1 array('f') with bounds (5)]

scipy.linalg.blas.sscal

`scipy.linalg.blas.sscal(a, x[, n, offx, incx]) = <fortran object>`
 Wrapper for `sscal`.

Parameters

a [input float]
x [input rank-1 array('f') with bounds (*)]

Returns

x [rank-1 array('f') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1

scipy.linalg.blas.sswap

`scipy.linalg.blas.sswap(x, y[, n, offx, incx, offy, incy]) = <fortran object>`
 Wrapper for `sswap`.

Parameters

x [input rank-1 array('f') with bounds (*)]
y [input rank-1 array('f') with bounds (*)]

Returns

x [rank-1 array('f') with bounds (*)]
y [rank-1 array('f') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.blas.zaxpy

`scipy.linalg.blas.zaxpy(x, y[, n, a, offx, incx, offy, incy]) = <fortran object>`
 Wrapper for `zaxpy`.

Parameters

x [input rank-1 array('D') with bounds (*)]
y [input rank-1 array('D') with bounds (*)]

Returns

z [rank-1 array('D') with bounds (*) and y storage]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)
a [input complex, optional] Default: (1.0, 0.0)

offx	[input int, optional] Default: 0
incx	[input int, optional] Default: 1
offy	[input int, optional] Default: 0
incy	[input int, optional] Default: 1

scipy.linalg.blas.zcopy

`scipy.linalg.blas.zcopy(x, y[, n, offx, incx, offy, incy]) = <fortran object>`
 Wrapper for `zcopy`.

Parameters

x	[input rank-1 array('D') with bounds (*)]
y	[input rank-1 array('D') with bounds (*)]

Returns

y	[rank-1 array('D') with bounds (*)]
----------	-------------------------------------

Other Parameters

n	[input int, optional] Default: (len(x)-offx)/abs(incx)
offx	[input int, optional] Default: 0
incx	[input int, optional] Default: 1
offy	[input int, optional] Default: 0
incy	[input int, optional] Default: 1

scipy.linalg.blas.zdotc

`scipy.linalg.blas.zdotc(x, y[, n, offx, incx, offy, incy]) = <fortran zdotc>`
 Wrapper for `zdotc`.

Parameters

x	[input rank-1 array('D') with bounds (*)]
y	[input rank-1 array('D') with bounds (*)]

Returns

xy	[complex]
-----------	-----------

Other Parameters

n	[input int, optional] Default: (len(x)-offx)/abs(incx)
offx	[input int, optional] Default: 0
incx	[input int, optional] Default: 1
offy	[input int, optional] Default: 0
incy	[input int, optional] Default: 1

scipy.linalg.blas.zdotu

`scipy.linalg.blas.zdotu(x, y[, n, offx, incx, offy, incy]) = <fortran zdotu>`
 Wrapper for `zdotu`.

Parameters

x [input rank-1 array('D') with bounds (*)]
y [input rank-1 array('D') with bounds (*)]

Returns

xy [complex]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.blas.zdrot

`scipy.linalg.blas.zdrot(x, y, c, s[, n, offx, incx, offy, incy, overwrite_x, overwrite_y]) = <fortran object>`

Wrapper for `zdrot`.

Parameters

x [input rank-1 array('D') with bounds (*)]
y [input rank-1 array('D') with bounds (*)]
c [input float]
s [input float]

Returns

x [rank-1 array('D') with bounds (*)]
y [rank-1 array('D') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-1-offx)/abs(incx)+1
overwrite_x [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
overwrite_y [input int, optional] Default: 0
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.blas.zdscal

`scipy.linalg.blas.zdscal(a, x[, n, offx, incx, overwrite_x]) = <fortran object>`
 Wrapper for `zdscal`.

Parameters

a [input float]
x [input rank-1 array('D') with bounds (*)]

Returns

x [rank-1 array('D') with bounds (*)]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$
overwrite_x [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1

scipy.linalg.blas.zrotg

`scipy.linalg.blas.zrotg(a, b) = <fortran object>`
 Wrapper for `zrotg`.

Parameters

a [input complex]
b [input complex]

Returns

c [complex]
s [complex]

scipy.linalg.blas.zscal

`scipy.linalg.blas.zscal(a, x[, n, offx, incx]) = <fortran object>`
 Wrapper for `zscal`.

Parameters

a [input complex]
x [input rank-1 array('D') with bounds (*)]

Returns

x [rank-1 array('D') with bounds (*)]

Other Parameters

n [input int, optional] Default: $(\text{len}(x) - \text{offx}) / \text{abs}(\text{incx})$
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1

scipy.linalg.blas.zswap

`scipy.linalg.blas.zswap(x, y[, n, offx, incx, offy, incy]) = <fortran object>`
 Wrapper for zswap.

Parameters

x [input rank-1 array('D') with bounds (*)]
y [input rank-1 array('D') with bounds (*)]

Returns

x [rank-1 array('D') with bounds (*)]
y [rank-1 array('D') with bounds (*)]

Other Parameters

n [input int, optional] Default: (len(x)-offx)/abs(incx)
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

6.11.3 BLAS Level 2 functions

<code>sgbmv(...)</code>	Wrapper for <code>sgbmv</code> .
<code>sgemv(...)</code>	Wrapper for <code>sgemv</code> .
<code>sger(...)</code>	Wrapper for <code>sger</code> .
<code>ssbmv(...)</code>	Wrapper for <code>ssbmv</code> .
<code>sspr(n,alpha,x,ap,[incx,offx,lower,overwrite_ap])</code>	Wrapper for <code>sspr</code> .
<code>sspr2(...)</code>	Wrapper for <code>sspr2</code> .
<code>ssymv(...)</code>	Wrapper for <code>ssymv</code> .
<code>ssyr(alpha,x,[lower,incx,offx,n,a,overwrite_a])</code>	Wrapper for <code>ssyr</code> .
<code>ssyr2(...)</code>	Wrapper for <code>ssyr2</code> .
<code>stbmv(...)</code>	Wrapper for <code>stbmv</code> .
<code>stpsv(...)</code>	Wrapper for <code>stpsv</code> .
<code>strmv(...)</code>	Wrapper for <code>strmv</code> .
<code>strsv(...)</code>	Wrapper for <code>strsv</code> .
<code>dgbmv(...)</code>	Wrapper for <code>dgbmv</code> .
<code>dgemv(...)</code>	Wrapper for <code>dgemv</code> .
<code>dger(...)</code>	Wrapper for <code>dger</code> .
<code>dsbmv(...)</code>	Wrapper for <code>dsbmv</code> .
<code>dspr(n,alpha,x,ap,[incx,offx,lower,overwrite_ap])</code>	Wrapper for <code>dspr</code> .
<code>dspr2(...)</code>	Wrapper for <code>dspr2</code> .
<code>dsymv(...)</code>	Wrapper for <code>dsymv</code> .
<code>dsyr(alpha,x,[lower,incx,offx,n,a,overwrite_a])</code>	Wrapper for <code>dsyr</code> .
<code>dsyr2(...)</code>	Wrapper for <code>dsyr2</code> .
<code>dtbmv(...)</code>	Wrapper for <code>dtbmv</code> .
<code>dtpsiv(...)</code>	Wrapper for <code>dtpsiv</code> .
<code>dtrmv(...)</code>	Wrapper for <code>dtrmv</code> .
<code>dtrsv(...)</code>	Wrapper for <code>dtrsv</code> .
<code>cgbmv(...)</code>	Wrapper for <code>cgbmv</code> .
<code>cgemv(...)</code>	Wrapper for <code>cgemv</code> .

continues on next page

Table 100 – continued from previous page

<code>cgerc(...)</code>	Wrapper for <code>cgerc</code> .
<code>cgeru(...)</code>	Wrapper for <code>cgeru</code> .
<code>chbmv(...)</code>	Wrapper for <code>chbmv</code> .
<code>chemv(...)</code>	Wrapper for <code>chemv</code> .
<code>cher(alpha,x,[lower,incx,offx,n,a,overwrite_a])</code>	Wrapper for <code>cher</code> .
<code>cher2(...)</code>	Wrapper for <code>cher2</code> .
<code>chpmv(...)</code>	Wrapper for <code>chpmv</code> .
<code>chpr(n,alpha,x,ap,[incx,offx,lower,overwrite_ap])</code>	Wrapper for <code>chpr</code> .
<code>chpr2(...)</code>	Wrapper for <code>chpr2</code> .
<code>ctbmv(...)</code>	Wrapper for <code>ctbmv</code> .
<code>ctbsv(...)</code>	Wrapper for <code>ctbsv</code> .
<code>ctpmv(...)</code>	Wrapper for <code>ctpmv</code> .
<code>ctpsv(...)</code>	Wrapper for <code>ctpsv</code> .
<code>ctrmv(...)</code>	Wrapper for <code>ctrmv</code> .
<code>ctrsv(...)</code>	Wrapper for <code>ctrsv</code> .
<code>csyr(alpha,x,[lower,incx,offx,n,a,overwrite_a])</code>	Wrapper for <code>csyr</code> .
<code>zgbmv(...)</code>	Wrapper for <code>zgbmv</code> .
<code>zgemv(...)</code>	Wrapper for <code>zgemv</code> .
<code>zgerc(...)</code>	Wrapper for <code>zgerc</code> .
<code>zgeru(...)</code>	Wrapper for <code>zgeru</code> .
<code>zhbmv(...)</code>	Wrapper for <code>zhbmv</code> .
<code>zhemv(...)</code>	Wrapper for <code>zhemv</code> .
<code>zher(alpha,x,[lower,incx,offx,n,a,overwrite_a])</code>	Wrapper for <code>zher</code> .
<code>zher2(...)</code>	Wrapper for <code>zher2</code> .
<code>zhpmv(...)</code>	Wrapper for <code>zhpmv</code> .
<code>zhpr(n,alpha,x,ap,[incx,offx,lower,overwrite_ap])</code>	Wrapper for <code>zhpr</code> .
<code>zhpr2(...)</code>	Wrapper for <code>zhpr2</code> .
<code>ztbmv(...)</code>	Wrapper for <code>ztbmv</code> .
<code>ztbsv(...)</code>	Wrapper for <code>ztbsv</code> .
<code>ztpmv(...)</code>	Wrapper for <code>ztpmv</code> .
<code>ztrmv(...)</code>	Wrapper for <code>ztrmv</code> .
<code>ztrsv(...)</code>	Wrapper for <code>ztrsv</code> .
<code>zsyr(alpha,x,[lower,incx,offx,n,a,overwrite_a])</code>	Wrapper for <code>zsyr</code> .

scipy.linalg.blas.sgbmv

`scipy.linalg.blas.sgbmv` (*m*, *n*, *kl*, *ku*, *alpha*, *a*, *x*[, *incx*, *offx*, *beta*, *y*, *incy*, *offy*, *trans*, *overwrite_y*])
= <fortran object>

Wrapper for `sgbmv`.

Parameters

m	[input int]
n	[input int]
kl	[input int]
ku	[input int]
alpha	[input float]
a	[input rank-2 array('f') with bounds (lda,n)]
x	[input rank-1 array('f') with bounds (*)]

Returns

yout	[rank-1 array('f') with bounds (ly) and y storage]
-------------	--

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
beta [input float, optional] Default: 0.0
y [input rank-1 array('f') with bounds (ly)]
overwrite_y
[input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
trans [input int, optional] Default: 0

scipy.linalg.blas.sgemv

`scipy.linalg.blas.sgemv(alpha, a, x[, beta, y, offx, incx, offy, incy, trans, overwrite_y]) = <fortran object>`

Wrapper for `sgemv`.

Parameters

alpha [input float]
a [input rank-2 array('f') with bounds (m,n)]
x [input rank-1 array('f') with bounds (*)]

Returns

y [rank-1 array('f') with bounds (ly)]

Other Parameters

beta [input float, optional] Default: 0.0
y [input rank-1 array('f') with bounds (ly)]
overwrite_y
[input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1
trans [input int, optional] Default: 0

scipy.linalg.blas.sger

`scipy.linalg.blas.sger(alpha, x, y[, incx, incy, a, overwrite_x, overwrite_y, overwrite_a]) = <fortran object>`

Wrapper for `sger`.

Parameters

alpha [input float]
x [input rank-1 array('f') with bounds (m)]
y [input rank-1 array('f') with bounds (n)]

Returns

a [rank-2 array('f') with bounds (m,n)]

Other Parameters

overwrite_x [input int, optional] Default: 1
incx [input int, optional] Default: 1
overwrite_y [input int, optional] Default: 1
incy [input int, optional] Default: 1
a [input rank-2 array('f') with bounds (m,n), optional] Default: 0.0
overwrite_a [input int, optional] Default: 0

scipy.linalg.blas.ssbmv

`scipy.linalg.blas.ssbmv(k, alpha, a, x[, incx, offx, beta, y, incy, offy, lower, overwrite_y]) = <fortran object>`

Wrapper for `ssbmv`.

Parameters

k [input int]
alpha [input float]
a [input rank-2 array('f') with bounds (lda,n)]
x [input rank-1 array('f') with bounds (*)]

Returns

yout [rank-1 array('f') with bounds (ly) and y storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
beta [input float, optional] Default: 0.0
y [input rank-1 array('f') with bounds (ly)]
overwrite_y [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.sspr

`scipy.linalg.blas.sspr(n, alpha, x, ap[, incx, offx, lower, overwrite_ap]) = <fortran object>`

Wrapper for `sspr`.

Parameters

n [input int]
alpha [input float]
x [input rank-1 array('f') with bounds (*)]
ap [input rank-1 array('f') with bounds (*)]

Returns

apu [rank-1 array('f') with bounds (*) and ap storage]

Other Parameters

incx [input int, optional] Default: 1

offx [input int, optional] Default: 0
overwrite_ap [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.sspr2

scipy.linalg.blas.**sspr2**(*n*, *alpha*, *x*, *y*, *ap*[, *incx*, *offx*, *incy*, *offy*, *lower*, *overwrite_ap*]) =
 <fortran object>

Wrapper for `sspr2`.

Parameters

n [input int]
alpha [input float]
x [input rank-1 array('f') with bounds (*)]
y [input rank-1 array('f') with bounds (*)]
ap [input rank-1 array('f') with bounds (*)]

Returns

apu [rank-1 array('f') with bounds (*) and ap storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
overwrite_ap [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.ssymv

scipy.linalg.blas.**ssymv**(*alpha*, *a*, *x*[, *beta*, *y*, *offx*, *incx*, *offy*, *incy*, *lower*, *overwrite_y*]) =
 <fortran object>

Wrapper for `ssymv`.

Parameters

alpha [input float]
a [input rank-2 array('f') with bounds (n,n)]
x [input rank-1 array('f') with bounds (*)]

Returns

y [rank-1 array('f') with bounds (ly)]

Other Parameters

beta [input float, optional] Default: 0.0
y [input rank-1 array('f') with bounds (ly)]
overwrite_y [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0

incy [input int, optional] Default: 1
lower [input int, optional] Default: 0

scipy.linalg.blas.ssyrr

`scipy.linalg.blas.ssyrr` (*alpha*, *x*[, *lower*, *incx*, *offx*, *n*, *a*, *overwrite_a*]) = <fortran object>
 Wrapper for `ssyr`.

Parameters

alpha [input float]
x [input rank-1 array('f') with bounds (*)]

Returns

a [rank-2 array('f') with bounds (n,n)]

Other Parameters

lower [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
n [input int, optional] Default: (len(x)-1-offx)/abs(incx)+1
a [input rank-2 array('f') with bounds (n,n)]
overwrite_a [input int, optional] Default: 0

scipy.linalg.blas.ssyrr2

`scipy.linalg.blas.ssyrr2` (*alpha*, *x*, *y*[, *lower*, *incx*, *offx*, *incy*, *offy*, *n*, *a*, *overwrite_a*]) = <fortran object>
 Wrapper for `ssyrr2`.

Parameters

alpha [input float]
x [input rank-1 array('f') with bounds (*)]
y [input rank-1 array('f') with bounds (*)]

Returns

a [rank-2 array('f') with bounds (n,n)]

Other Parameters

lower [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
n [input int, optional] Default: ((len(x)-1-offx)/abs(incx)+1 <=(len(y)-1-offy)/abs(incy)+1 ?(len(x)-1-offx)/abs(incx)+1 :(len(y)-1-offy)/abs(incy)+1)
a [input rank-2 array('f') with bounds (n,n)]
overwrite_a [input int, optional] Default: 0

scipy.linalg.blas.stbmv

`scipy.linalg.blas.stbmv(k, a, x[, incx, offx, lower, trans, diag, overwrite_x]) = <fortran object>`

Wrapper for `stbmv`.

Parameters

k [input int]
a [input rank-2 array('f') with bounds (lda,n)]
x [input rank-1 array('f') with bounds (*)]

Returns

xout [rank-1 array('f') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.stpsv

`scipy.linalg.blas.stpsv(n, ap, x[, incx, offx, lower, trans, diag, overwrite_x]) = <fortran object>`

Wrapper for `stpsv`.

Parameters

n [input int]
ap [input rank-1 array('f') with bounds (*)]
x [input rank-1 array('f') with bounds (*)]

Returns

xout [rank-1 array('f') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.strmv

`scipy.linalg.blas.strmv(a, x[, offx, incx, lower, trans, diag, overwrite_x]) = <fortran object>`
 Wrapper for `strmv`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]
x [input rank-1 array('f') with bounds (*)]

Returns

x [rank-1 array('f') with bounds (*)]

Other Parameters

overwrite_x [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.strsv

`scipy.linalg.blas.strsv(a, x[, incx, offx, lower, trans, diag, overwrite_x]) = <fortran object>`
 Wrapper for `strsv`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]
x [input rank-1 array('f') with bounds (*)]

Returns

xout [rank-1 array('f') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.dgbmv

`scipy.linalg.blas.dgbmv(m, n, kl, ku, alpha, a, x[, incx, offx, beta, y, incy, offy, trans, overwrite_y]) = <fortran object>`

Wrapper for `dgbmv`.

Parameters

m [input int]
n [input int]
kl [input int]

ku [input int]
alpha [input float]
a [input rank-2 array('d') with bounds (lda,n)]
x [input rank-1 array('d') with bounds (*)]

Returns

yout [rank-1 array('d') with bounds (ly) and y storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
beta [input float, optional] Default: 0.0
y [input rank-1 array('d') with bounds (ly)]
overwrite_y
 [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
trans [input int, optional] Default: 0

scipy.linalg.blas.dgemv

`scipy.linalg.blas.dgemv(alpha, a, x[, beta, y, offx, incx, offy, incy, trans, overwrite_y]) = <fortran object>`

Wrapper for dgemv.

Parameters

alpha [input float]
a [input rank-2 array('d') with bounds (m,n)]
x [input rank-1 array('d') with bounds (*)]

Returns

y [rank-1 array('d') with bounds (ly)]

Other Parameters

beta [input float, optional] Default: 0.0
y [input rank-1 array('d') with bounds (ly)]
overwrite_y
 [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1
trans [input int, optional] Default: 0

scipy.linalg.blas.dger

`scipy.linalg.blas.dger(alpha, x, y[, incx, incy, a, overwrite_x, overwrite_y, overwrite_a]) =`
<fortran object>

Wrapper for `dger`.

Parameters

alpha [input float]
x [input rank-1 array('d') with bounds (m)]
y [input rank-1 array('d') with bounds (n)]

Returns

a [rank-2 array('d') with bounds (m,n)]

Other Parameters

overwrite_x
[input int, optional] Default: 1
incx [input int, optional] Default: 1
overwrite_y
[input int, optional] Default: 1
incy [input int, optional] Default: 1
a [input rank-2 array('d') with bounds (m,n), optional] Default: 0.0
overwrite_a
[input int, optional] Default: 0

scipy.linalg.blas.dsmbv

`scipy.linalg.blas.dsmbv(k, alpha, a, x[, incx, offx, beta, y, incy, offy, lower, overwrite_y]) =`
<fortran object>

Wrapper for `dsmbv`.

Parameters

k [input int]
alpha [input float]
a [input rank-2 array('d') with bounds (lda,n)]
x [input rank-1 array('d') with bounds (*)]

Returns

yout [rank-1 array('d') with bounds (ly) and y storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
beta [input float, optional] Default: 0.0
y [input rank-1 array('d') with bounds (ly)]
overwrite_y
[input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.dspr

`scipy.linalg.blas.dspr` (*n*, *alpha*, *x*, *ap*[, *incx*, *offx*, *lower*, *overwrite_ap*]) = **<fortran object>**
Wrapper for dspr.

Parameters

n [input int]
alpha [input float]
x [input rank-1 array('d') with bounds (*)]
ap [input rank-1 array('d') with bounds (*)]

Returns

apu [rank-1 array('d') with bounds (*) and ap storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
overwrite_ap [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.dspr2

`scipy.linalg.blas.dspr2` (*n*, *alpha*, *x*, *y*, *ap*[, *incx*, *offx*, *incy*, *offy*, *lower*, *overwrite_ap*]) = **<fortran object>**

Wrapper for dspr2.

Parameters

n [input int]
alpha [input float]
x [input rank-1 array('d') with bounds (*)]
y [input rank-1 array('d') with bounds (*)]
ap [input rank-1 array('d') with bounds (*)]

Returns

apu [rank-1 array('d') with bounds (*) and ap storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
overwrite_ap [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.dsymv

`scipy.linalg.blas.dsymv(alpha, a, x[, beta, y, offx, incx, offy, incy, lower, overwrite_y]) = <fortran object>`

Wrapper for `dsymv`.

Parameters

alpha [input float]
a [input rank-2 array('d') with bounds (n,n)]
x [input rank-1 array('d') with bounds (*)]

Returns

y [rank-1 array('d') with bounds (ly)]

Other Parameters

beta [input float, optional] Default: 0.0
y [input rank-1 array('d') with bounds (ly)]
overwrite_y [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1
lower [input int, optional] Default: 0

scipy.linalg.blas.dsyr

`scipy.linalg.blas.dsyr(alpha, x[, lower, incx, offx, n, a, overwrite_a]) = <fortran object>`

Wrapper for `dsyr`.

Parameters

alpha [input float]
x [input rank-1 array('d') with bounds (*)]

Returns

a [rank-2 array('d') with bounds (n,n)]

Other Parameters

lower [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
n [input int, optional] Default: (len(x)-1-offx)/abs(incx)+1
a [input rank-2 array('d') with bounds (n,n)]
overwrite_a [input int, optional] Default: 0

scipy.linalg.blas.dsyr2

`scipy.linalg.blas.dsyr2(alpha, x, y[, lower, incx, offx, incy, offy, n, a, overwrite_a]) = <fortran object>`

Wrapper for dsyr2.

Parameters

alpha [input float]
x [input rank-1 array('d') with bounds (*)]
y [input rank-1 array('d') with bounds (*)]

Returns

a [rank-2 array('d') with bounds (n,n)]

Other Parameters

lower [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
n [input int, optional] Default: ((len(x)-1-offx)/abs(incx)+1 <=(len(y)-1-offy)/abs(incy)+1 ?(len(x)-1-offx)/abs(incx)+1 :(len(y)-1-offy)/abs(incy)+1)
a [input rank-2 array('d') with bounds (n,n)]
overwrite_a [input int, optional] Default: 0

scipy.linalg.blas.dtbmv

`scipy.linalg.blas.dtbmv(k, a, x[, incx, offx, lower, trans, diag, overwrite_x]) = <fortran object>`

Wrapper for dtbmv.

Parameters

k [input int]
a [input rank-2 array('d') with bounds (lda,n)]
x [input rank-1 array('d') with bounds (*)]

Returns

xout [rank-1 array('d') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.dtpsv

`scipy.linalg.blas.dtpsv` (n, ap, x [, $incx, offx, lower, trans, diag, overwrite_x$]) = **<fortran object>**

Wrapper for `dtpsv`.

Parameters

n [input int]
ap [input rank-1 array('d') with bounds (*)]
x [input rank-1 array('d') with bounds (*)]

Returns

xout [rank-1 array('d') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.dtrmv

`scipy.linalg.blas.dtrmv` (a, x [, $offx, incx, lower, trans, diag, overwrite_x$]) = **<fortran object>**

Wrapper for `dtrmv`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
x [input rank-1 array('d') with bounds (*)]

Returns

x [rank-1 array('d') with bounds (*)]

Other Parameters

overwrite_x [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.dtrsv

`scipy.linalg.blas.dtrsv(a, x[, incx, offx, lower, trans, diag, overwrite_x]) = <fortran object>`
 Wrapper for `dtrsv`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
x [input rank-1 array('d') with bounds (*)]

Returns

xout [rank-1 array('d') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.cgbmv

`scipy.linalg.blas.cgbmv(m, n, kl, ku, alpha, a, x[, incx, offx, beta, y, incy, offy, trans, overwrite_y])`
 = <fortran object>

Wrapper for `cgbmv`.

Parameters

m [input int]
n [input int]
kl [input int]
ku [input int]
alpha [input complex]
a [input rank-2 array('F') with bounds (lda,n)]
x [input rank-1 array('F') with bounds (*)]

Returns

yout [rank-1 array('F') with bounds (ly) and y storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
beta [input complex, optional] Default: (0.0, 0.0)
y [input rank-1 array('F') with bounds (ly)]
overwrite_y [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
trans [input int, optional] Default: 0

scipy.linalg.blas.cgemv

`scipy.linalg.blas.cgemv(alpha, a, x[, beta, y, offx, incx, offy, incy, trans, overwrite_y]) =`
<fortran object>

Wrapper for `cgemv`.

Parameters

alpha [input complex]
a [input rank-2 array('F') with bounds (m,n)]
x [input rank-1 array('F') with bounds (*)]

Returns

y [rank-1 array('F') with bounds (ly)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)
y [input rank-1 array('F') with bounds (ly)]
overwrite_y
 [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1
trans [input int, optional] Default: 0

scipy.linalg.blas.cgerc

`scipy.linalg.blas.cgerc(alpha, x, y[, incx, incy, a, overwrite_x, overwrite_y, overwrite_a]) =`
<fortran object>

Wrapper for `cgerc`.

Parameters

alpha [input complex]
x [input rank-1 array('F') with bounds (m)]
y [input rank-1 array('F') with bounds (n)]

Returns

a [rank-2 array('F') with bounds (m,n)]

Other Parameters

overwrite_x
 [input int, optional] Default: 1
incx [input int, optional] Default: 1
overwrite_y
 [input int, optional] Default: 1
incy [input int, optional] Default: 1
a [input rank-2 array('F') with bounds (m,n), optional] Default: (0.0,0.0)
overwrite_a
 [input int, optional] Default: 0

scipy.linalg.blas.cgeru

scipy.linalg.blas.cgeru(alpha, x, y[, incx, incy, a, overwrite_x, overwrite_y, overwrite_a]) = **<fortran object>**

Wrapper for cgeru.

Parameters

alpha [input complex]
x [input rank-1 array('F') with bounds (m)]
y [input rank-1 array('F') with bounds (n)]

Returns

a [rank-2 array('F') with bounds (m,n)]

Other Parameters

overwrite_x [input int, optional] Default: 1
incx [input int, optional] Default: 1
overwrite_y [input int, optional] Default: 1
incy [input int, optional] Default: 1
a [input rank-2 array('F') with bounds (m,n), optional] Default: (0.0,0.0)
overwrite_a [input int, optional] Default: 0

scipy.linalg.blas.chbmv

scipy.linalg.blas.chbmv(k, alpha, a, x[, incx, offx, beta, y, incy, offy, lower, overwrite_y]) = **<fortran object>**

Wrapper for chbmv.

Parameters

k [input int]
alpha [input complex]
a [input rank-2 array('F') with bounds (lda,n)]
x [input rank-1 array('F') with bounds (*)]

Returns

yout [rank-1 array('F') with bounds (ly) and y storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
beta [input complex, optional] Default: (0.0, 0.0)
y [input rank-1 array('F') with bounds (ly)]
overwrite_y [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.chemv

`scipy.linalg.blas.chemv(alpha, a, x[, beta, y, offx, incx, offy, incy, lower, overwrite_y]) = <fortran object>`

Wrapper for chemv.

Parameters

alpha [input complex]
a [input rank-2 array('F') with bounds (n,n)]
x [input rank-1 array('F') with bounds (*)]

Returns

y [rank-1 array('F') with bounds (ly)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)
y [input rank-1 array('F') with bounds (ly)]
overwrite_y [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1
lower [input int, optional] Default: 0

scipy.linalg.blas.cher

`scipy.linalg.blas.cher(alpha, x[, lower, incx, offx, n, a, overwrite_a]) = <fortran object>`

Wrapper for cher.

Parameters

alpha [input complex]
x [input rank-1 array('F') with bounds (*)]

Returns

a [rank-2 array('F') with bounds (n,n)]

Other Parameters

lower [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
n [input int, optional] Default: (len(x)-1-offx)/abs(incx)+1
a [input rank-2 array('F') with bounds (n,n)]
overwrite_a [input int, optional] Default: 0

scipy.linalg.blas.cher2

scipy.linalg.blas.**cher2** (*alpha*, *x*, *y*[, *lower*, *incx*, *offx*, *incy*, *offy*, *n*, *a*, *overwrite_a*]) = **<fortran object>**

Wrapper for cher2.

Parameters

alpha [input complex]
x [input rank-1 array('F') with bounds (*)]
y [input rank-1 array('F') with bounds (*)]

Returns

a [rank-2 array('F') with bounds (n,n)]

Other Parameters

lower [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
n [input int, optional] Default: ((len(x)-1-offx)/abs(incx)+1 <=(len(y)-1-offy)/abs(incy)+1 ?(len(x)-1-offx)/abs(incx)+1 :(len(y)-1-offy)/abs(incy)+1)
a [input rank-2 array('F') with bounds (n,n)]
overwrite_a [input int, optional] Default: 0

scipy.linalg.blas.chpmv

scipy.linalg.blas.**chpmv** (*n*, *alpha*, *ap*, *x*[, *incx*, *offx*, *beta*, *y*, *incy*, *offy*, *lower*, *overwrite_y*]) = **<fortran object>**

Wrapper for chpmv.

Parameters

n [input int]
alpha [input complex]
ap [input rank-1 array('F') with bounds (*)]
x [input rank-1 array('F') with bounds (*)]

Returns

yout [rank-1 array('F') with bounds (ly) and y storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
beta [input complex, optional] Default: (0.0, 0.0)
y [input rank-1 array('F') with bounds (ly)]
overwrite_y [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.chpr

`scipy.linalg.blas.chpr` (*n*, *alpha*, *x*, *ap*[, *incx*, *offx*, *lower*, *overwrite_ap*]) = <fortran object>
 Wrapper for `chpr`.

Parameters

n [input int]
alpha [input float]
x [input rank-1 array('F') with bounds (*)]
ap [input rank-1 array('F') with bounds (*)]

Returns

apu [rank-1 array('F') with bounds (*) and ap storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
overwrite_ap [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.chpr2

`scipy.linalg.blas.chpr2` (*n*, *alpha*, *x*, *y*, *ap*[, *incx*, *offx*, *incy*, *offy*, *lower*, *overwrite_ap*]) =
 <fortran object>

Wrapper for `chpr2`.

Parameters

n [input int]
alpha [input complex]
x [input rank-1 array('F') with bounds (*)]
y [input rank-1 array('F') with bounds (*)]
ap [input rank-1 array('F') with bounds (*)]

Returns

apu [rank-1 array('F') with bounds (*) and ap storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
overwrite_ap [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.ctbmv

`scipy.linalg.blas.ctbmv(k, a, x[, incx, offx, lower, trans, diag, overwrite_x]) = <fortran object>`

Wrapper for `ctbmv`.

Parameters

k [input int]
a [input rank-2 array('F') with bounds (lda,n)]
x [input rank-1 array('F') with bounds (*)]

Returns

xout [rank-1 array('F') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.ctbsv

`scipy.linalg.blas.ctbsv(k, a, x[, incx, offx, lower, trans, diag, overwrite_x]) = <fortran object>`

Wrapper for `ctbsv`.

Parameters

k [input int]
a [input rank-2 array('F') with bounds (lda,n)]
x [input rank-1 array('F') with bounds (*)]

Returns

xout [rank-1 array('F') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.ctpmv

`scipy.linalg.blas.ctpmv` (n, ap, x [, $incx, offx, lower, trans, diag, overwrite_x$]) = <fortran object>

Wrapper for `ctpmv`.

Parameters

n [input int]
ap [input rank-1 array('F') with bounds (*)]
x [input rank-1 array('F') with bounds (*)]

Returns

xout [rank-1 array('F') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.ctpsv

`scipy.linalg.blas.ctpsv` (n, ap, x [, $incx, offx, lower, trans, diag, overwrite_x$]) = <fortran object>

Wrapper for `ctpsv`.

Parameters

n [input int]
ap [input rank-1 array('F') with bounds (*)]
x [input rank-1 array('F') with bounds (*)]

Returns

xout [rank-1 array('F') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.ctrmv

`scipy.linalg.blas.ctrmv(a, x[, offx, incx, lower, trans, diag, overwrite_x]) = <fortran object>`
Wrapper for `ctrmv`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
x [input rank-1 array('F') with bounds (*)]

Returns

x [rank-1 array('F') with bounds (*)]

Other Parameters

overwrite_x [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.ctrsv

`scipy.linalg.blas.ctrsv(a, x[, incx, offx, lower, trans, diag, overwrite_x]) = <fortran object>`
Wrapper for `ctrsv`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
x [input rank-1 array('F') with bounds (*)]

Returns

xout [rank-1 array('F') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.csyr

`scipy.linalg.blas.csyr(alpha, x[, lower, incx, offx, n, a, overwrite_a]) = <fortran object>`
Wrapper for `csyr`.

Parameters

alpha [input complex]
x [input rank-1 array('F') with bounds (*)]

Returns

a [rank-2 array('F') with bounds (n,n)]

Other Parameters

lower [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
n [input int, optional] Default: (len(x)-1-offx)/abs(incx)+1
a [input rank-2 array('F') with bounds (n,n)]
overwrite_a [input int, optional] Default: 0

scipy.linalg.blas.zgbmv

`scipy.linalg.blas.zgbmv(m, n, kl, ku, alpha, a, x[, incx, offx, beta, y, incy, offy, trans, overwrite_y])`
 = **<fortran object>**

Wrapper for zgbmv.

Parameters

m [input int]
n [input int]
kl [input int]
ku [input int]
alpha [input complex]
a [input rank-2 array('D') with bounds (lda,n)]
x [input rank-1 array('D') with bounds (*)]

Returns

yout [rank-1 array('D') with bounds (ly) and y storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
beta [input complex, optional] Default: (0.0, 0.0)
y [input rank-1 array('D') with bounds (ly)]
overwrite_y [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
trans [input int, optional] Default: 0

scipy.linalg.blas.zgemv

`scipy.linalg.blas.zgemv(alpha, a, x[, beta, y, offx, incx, offy, incy, trans, overwrite_y])`
 = **<fortran object>**

Wrapper for zgemv.

Parameters

alpha [input complex]
a [input rank-2 array('D') with bounds (m,n)]
x [input rank-1 array('D') with bounds (*)]

Returns

y [rank-1 array('D') with bounds (ly)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)
y [input rank-1 array('D') with bounds (ly)]
overwrite_y [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1
trans [input int, optional] Default: 0

scipy.linalg.blas.zgerc

`scipy.linalg.blas.zgerc(alpha, x, y[, incx, incy, a, overwrite_x, overwrite_y, overwrite_a]) = <fortran object>`

Wrapper for zgerc.

Parameters

alpha [input complex]
x [input rank-1 array('D') with bounds (m)]
y [input rank-1 array('D') with bounds (n)]

Returns

a [rank-2 array('D') with bounds (m,n)]

Other Parameters

overwrite_x [input int, optional] Default: 1
incx [input int, optional] Default: 1
overwrite_y [input int, optional] Default: 1
incy [input int, optional] Default: 1
a [input rank-2 array('D') with bounds (m,n), optional] Default: (0.0,0.0)
overwrite_a [input int, optional] Default: 0

scipy.linalg.blas.zgeru

`scipy.linalg.blas.zgeru(alpha, x, y[, incx, incy, a, overwrite_x, overwrite_y, overwrite_a]) = <fortran object>`

Wrapper for zgeru.

Parameters

alpha [input complex]
x [input rank-1 array('D') with bounds (m)]
y [input rank-1 array('D') with bounds (n)]

Returns

a [rank-2 array('D') with bounds (m,n)]

Other Parameters

overwrite_x [input int, optional] Default: 1
incx [input int, optional] Default: 1
overwrite_y [input int, optional] Default: 1
incy [input int, optional] Default: 1
a [input rank-2 array('D') with bounds (m,n), optional] Default: (0.0,0.0)
overwrite_a [input int, optional] Default: 0

scipy.linalg.blas.zhbmw

`scipy.linalg.blas.zhbmw(k, alpha, a, x[, incx, offx, beta, y, incy, offy, lower, overwrite_y]) =`
<fortran object>

Wrapper for zhbmw.

Parameters

k [input int]
alpha [input complex]
a [input rank-2 array('D') with bounds (lda,n)]
x [input rank-1 array('D') with bounds (*)]

Returns

yout [rank-1 array('D') with bounds (ly) and y storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
beta [input complex, optional] Default: (0.0, 0.0)
y [input rank-1 array('D') with bounds (ly)]
overwrite_y [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.zhemv

`scipy.linalg.blas.zhemv(alpha, a, x[, beta, y, offx, incx, offy, incy, lower, overwrite_y]) =`
<fortran object>

Wrapper for zhemv.

Parameters

alpha [input complex]
a [input rank-2 array('D') with bounds (n,n)]
x [input rank-1 array('D') with bounds (*)]

Returns

y [rank-1 array('D') with bounds (ly)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)

y [input rank-1 array('D') with bounds (ly)]
overwrite_y [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1
lower [input int, optional] Default: 0

scipy.linalg.blas.zher

`scipy.linalg.blas.zher(alpha, x[, lower, incx, offx, n, a, overwrite_a]) = <fortran object>`
 Wrapper for zher.

Parameters

alpha [input complex]
x [input rank-1 array('D') with bounds (*)]

Returns

a [rank-2 array('D') with bounds (n,n)]

Other Parameters

lower [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
n [input int, optional] Default: (len(x)-1-offx)/abs(incx)+1
a [input rank-2 array('D') with bounds (n,n)]
overwrite_a [input int, optional] Default: 0

scipy.linalg.blas.zher2

`scipy.linalg.blas.zher2(alpha, x, y[, lower, incx, offx, incy, offy, n, a, overwrite_a]) = <fortran object>`

Wrapper for zher2.

Parameters

alpha [input complex]
x [input rank-1 array('D') with bounds (*)]
y [input rank-1 array('D') with bounds (*)]

Returns

a [rank-2 array('D') with bounds (n,n)]

Other Parameters

lower [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
n [input int, optional] Default: ((len(x)-1-offx)/abs(incx)+1 <=(len(y)-1-offy)/abs(incy)+1 ?(len(x)-1-offx)/abs(incx)+1 :(len(y)-1-offy)/abs(incy)+1)

a [input rank-2 array('D') with bounds (n,n)]
overwrite_a [input int, optional] Default: 0

scipy.linalg.blas.zhpmv

`scipy.linalg.blas.zhpmv(n, alpha, ap, x[, incx, offx, beta, y, incy, offy, lower, overwrite_y]) = <fortran object>`

Wrapper for zhpmv.

Parameters

n [input int]
alpha [input complex]
ap [input rank-1 array('D') with bounds (*)]
x [input rank-1 array('D') with bounds (*)]

Returns

yout [rank-1 array('D') with bounds (ly) and y storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
beta [input complex, optional] Default: (0.0, 0.0)
y [input rank-1 array('D') with bounds (ly)]
overwrite_y [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.zhpr

`scipy.linalg.blas.zhpr(n, alpha, x, ap[, incx, offx, lower, overwrite_ap]) = <fortran object>`

Wrapper for zhpr.

Parameters

n [input int]
alpha [input float]
x [input rank-1 array('D') with bounds (*)]
ap [input rank-1 array('D') with bounds (*)]

Returns

apu [rank-1 array('D') with bounds (*) and ap storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
overwrite_ap [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.zhpr2

`scipy.linalg.blas.zhpr2(n, alpha, x, y, ap[, incx, offx, incy, offy, lower, overwrite_ap]) = <fortran object>`

Wrapper for zhpr2.

Parameters

n [input int]
alpha [input complex]
x [input rank-1 array('D') with bounds (*)]
y [input rank-1 array('D') with bounds (*)]
ap [input rank-1 array('D') with bounds (*)]

Returns

apu [rank-1 array('D') with bounds (*) and ap storage]

Other Parameters

incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
incy [input int, optional] Default: 1
offy [input int, optional] Default: 0
overwrite_ap [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.ztbmv

`scipy.linalg.blas.ztbmv(k, a, x[, incx, offx, lower, trans, diag, overwrite_x]) = <fortran object>`

Wrapper for ztbmv.

Parameters

k [input int]
a [input rank-2 array('D') with bounds (lda,n)]
x [input rank-1 array('D') with bounds (*)]

Returns

xout [rank-1 array('D') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.ztbsv

`scipy.linalg.blas.ztbsv(k, a, x[, incx, offx, lower, trans, diag, overwrite_x]) = <fortran object>`

Wrapper for `ztbsv`.

Parameters

k [input int]
a [input rank-2 array('D') with bounds (lda,n)]
x [input rank-1 array('D') with bounds (*)]

Returns

xout [rank-1 array('D') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.ztpmv

`scipy.linalg.blas.ztpmv(n, ap, x[, incx, offx, lower, trans, diag, overwrite_x]) = <fortran object>`

Wrapper for `ztpmv`.

Parameters

n [input int]
ap [input rank-1 array('D') with bounds (*)]
x [input rank-1 array('D') with bounds (*)]

Returns

xout [rank-1 array('D') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.ztrmv

`scipy.linalg.blas.ztrmv(a, x[, offx, incx, lower, trans, diag, overwrite_x]) = <fortran object>`
Wrapper for `ztrmv`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
x [input rank-1 array('D') with bounds (*)]

Returns

x [rank-1 array('D') with bounds (*)]

Other Parameters

overwrite_x [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.ztrsv

`scipy.linalg.blas.ztrsv(a, x[, incx, offx, lower, trans, diag, overwrite_x]) = <fortran object>`
Wrapper for `ztrsv`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
x [input rank-1 array('D') with bounds (*)]

Returns

xout [rank-1 array('D') with bounds (*) and x storage]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.zsyr

`scipy.linalg.blas.zsyr(alpha, x[, lower, incx, offx, n, a, overwrite_a]) = <fortran object>`
Wrapper for `zsyr`.

Parameters

alpha [input complex]
x [input rank-1 array('D') with bounds (*)]

Returns

a [rank-2 array('D') with bounds (n,n)]

Other Parameters

lower [input int, optional] Default: 0
incx [input int, optional] Default: 1
offx [input int, optional] Default: 0
n [input int, optional] Default: (len(x)-1-offx)/abs(incx)+1
a [input rank-2 array('D') with bounds (n,n)]
overwrite_a [input int, optional] Default: 0

6.11.4 BLAS Level 3 functions

<i>sgemm(...)</i>	Wrapper for <i>sgemm</i> .
<i>ssymm(alpha,a,b,[beta,c,side,lower,overwrite_c])</i>	Wrapper for <i>ssymm</i> .
<i>ssyr2k(...)</i>	Wrapper for <i>ssyr2k</i> .
<i>ssyrk(alpha,a,[beta,c,trans,lower,overwrite_c])</i>	Wrapper for <i>ssyrk</i> .
<i>strmm(...)</i>	Wrapper for <i>strmm</i> .
<i>strsm(...)</i>	Wrapper for <i>strsm</i> .
<i>dgemm(...)</i>	Wrapper for <i>dgemm</i> .
<i>dsymm(alpha,a,b,[beta,c,side,lower,overwrite_c])</i>	Wrapper for <i>dsymm</i> .
<i>dsyr2k(...)</i>	Wrapper for <i>dsyr2k</i> .
<i>dsyrk(alpha,a,[beta,c,trans,lower,overwrite_c])</i>	Wrapper for <i>dsyrk</i> .
<i>dtrmm(...)</i>	Wrapper for <i>dtrmm</i> .
<i>dtrsm(...)</i>	Wrapper for <i>dtrsm</i> .
<i>cgemm(...)</i>	Wrapper for <i>cgemm</i> .
<i>chemm(alpha,a,b,[beta,c,side,lower,overwrite_c])</i>	Wrapper for <i>chemm</i> .
<i>cher2k(...)</i>	Wrapper for <i>cher2k</i> .
<i>cherk(alpha,a,[beta,c,trans,lower,overwrite_c])</i>	Wrapper for <i>cherk</i> .
<i>csymm(alpha,a,b,[beta,c,side,lower,overwrite_c])</i>	Wrapper for <i>csymm</i> .
<i>csyr2k(...)</i>	Wrapper for <i>csyr2k</i> .
<i>csyrk(alpha,a,[beta,c,trans,lower,overwrite_c])</i>	Wrapper for <i>csyrk</i> .
<i>ctrmm(...)</i>	Wrapper for <i>ctrmm</i> .
<i>ctrsm(...)</i>	Wrapper for <i>ctrsm</i> .
<i>zgemm(...)</i>	Wrapper for <i>zgemm</i> .
<i>zhemm(alpha,a,b,[beta,c,side,lower,overwrite_c])</i>	Wrapper for <i>zhemm</i> .
<i>zher2k(...)</i>	Wrapper for <i>zher2k</i> .
<i>zherk(alpha,a,[beta,c,trans,lower,overwrite_c])</i>	Wrapper for <i>zherk</i> .
<i>zsymm(alpha,a,b,[beta,c,side,lower,overwrite_c])</i>	Wrapper for <i>zsymm</i> .
<i>zsyr2k(...)</i>	Wrapper for <i>zsyr2k</i> .
<i>zsyrk(alpha,a,[beta,c,trans,lower,overwrite_c])</i>	Wrapper for <i>zsyrk</i> .
<i>ztrmm(...)</i>	Wrapper for <i>ztrmm</i> .
<i>ztrsm(...)</i>	Wrapper for <i>ztrsm</i> .

scipy.linalg.blas.sgemmm

`scipy.linalg.blas.sgemmm(alpha, a, b[, beta, c, trans_a, trans_b, overwrite_c]) = <fortran object>`

Wrapper for `sgemm`.

Parameters

alpha [input float]
a [input rank-2 array('f') with bounds (lda,ka)]
b [input rank-2 array('f') with bounds (ldb,kb)]

Returns

c [rank-2 array('f') with bounds (m,n)]

Other Parameters

beta [input float, optional] Default: 0.0
c [input rank-2 array('f') with bounds (m,n)]
overwrite_c [input int, optional] Default: 0
trans_a [input int, optional] Default: 0
trans_b [input int, optional] Default: 0

scipy.linalg.blas.ssymm

`scipy.linalg.blas.ssymm(alpha, a, b[, beta, c, side, lower, overwrite_c]) = <fortran object>`

Wrapper for `ssymm`.

Parameters

alpha [input float]
a [input rank-2 array('f') with bounds (lda,ka)]
b [input rank-2 array('f') with bounds (ldb,kb)]

Returns

c [rank-2 array('f') with bounds (m,n)]

Other Parameters

beta [input float, optional] Default: 0.0
c [input rank-2 array('f') with bounds (m,n)]
overwrite_c [input int, optional] Default: 0
side [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.ssy2k

`scipy.linalg.blas.ssy2k(alpha, a, b[, beta, c, trans, lower, overwrite_c]) = <fortran object>`
 Wrapper for `ssyr2k`.

Parameters

alpha [input float]
a [input rank-2 array('f') with bounds (lda,ka)]
b [input rank-2 array('f') with bounds (ldb,kb)]

Returns

c [rank-2 array('f') with bounds (n,n)]

Other Parameters

beta [input float, optional] Default: 0.0
c [input rank-2 array('f') with bounds (n,n)]
overwrite_c [input int, optional] Default: 0
trans [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.ssy2k

`scipy.linalg.blas.ssy2k(alpha, a[, beta, c, trans, lower, overwrite_c]) = <fortran object>`
 Wrapper for `ssyrk`.

Parameters

alpha [input float]
a [input rank-2 array('f') with bounds (lda,ka)]

Returns

c [rank-2 array('f') with bounds (n,n)]

Other Parameters

beta [input float, optional] Default: 0.0
c [input rank-2 array('f') with bounds (n,n)]
overwrite_c [input int, optional] Default: 0
trans [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.strmm

`scipy.linalg.blas.strmm(alpha, a, b[, side, lower, trans_a, diag, overwrite_b]) = <fortran object>`

Wrapper for `strmm`.

Parameters

alpha [input float]
a [input rank-2 array('f') with bounds (lda,k)]
b [input rank-2 array('f') with bounds (ldb,n)]

Returns

b [rank-2 array('f') with bounds (ldb,n)]

Other Parameters

overwrite_b [input int, optional] Default: 0
side [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans_a [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.strsm

`scipy.linalg.blas.strsm(alpha, a, b[, side, lower, trans_a, diag, overwrite_b]) = <fortran object>`

Wrapper for `strsm`.

Parameters

alpha [input float]
a [input rank-2 array('f') with bounds (lda,*)]
b [input rank-2 array('f') with bounds (ldb,n)]

Returns

x [rank-2 array('f') with bounds (ldb,n) and b storage]

Other Parameters

overwrite_b [input int, optional] Default: 0
side [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans_a [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.dgemm

`scipy.linalg.blas.dgemm(alpha, a, b[, beta, c, trans_a, trans_b, overwrite_c]) = <fortran object>`

Wrapper for `dgemm`.

Parameters

alpha [input float]
a [input rank-2 array('d') with bounds (lda,ka)]
b [input rank-2 array('d') with bounds (ldb,kb)]

Returns

c [rank-2 array('d') with bounds (m,n)]

Other Parameters

beta [input float, optional] Default: 0.0
c [input rank-2 array('d') with bounds (m,n)]
overwrite_c [input int, optional] Default: 0

trans_a [input int, optional] Default: 0
trans_b [input int, optional] Default: 0

scipy.linalg.blas.dsymm

`scipy.linalg.blas.dsymm(alpha, a, b[, beta, c, side, lower, overwrite_c]) = <fortran object>`
 Wrapper for dsymm.

Parameters

alpha [input float]
a [input rank-2 array('d') with bounds (lda,ka)]
b [input rank-2 array('d') with bounds (ldb,kb)]

Returns

c [rank-2 array('d') with bounds (m,n)]

Other Parameters

beta [input float, optional] Default: 0.0
c [input rank-2 array('d') with bounds (m,n)]
overwrite_c
 [input int, optional] Default: 0
side [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.dsyr2k

`scipy.linalg.blas.dsyr2k(alpha, a, b[, beta, c, trans, lower, overwrite_c]) = <fortran object>`
 Wrapper for dsyr2k.

Parameters

alpha [input float]
a [input rank-2 array('d') with bounds (lda,ka)]
b [input rank-2 array('d') with bounds (ldb,kb)]

Returns

c [rank-2 array('d') with bounds (n,n)]

Other Parameters

beta [input float, optional] Default: 0.0
c [input rank-2 array('d') with bounds (n,n)]
overwrite_c
 [input int, optional] Default: 0
trans [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.dsyrk

`scipy.linalg.blas.dsyrk(alpha, a[, beta, c, trans, lower, overwrite_c]) = <fortran object>`
 Wrapper for dsyrk.

Parameters

alpha [input float]
a [input rank-2 array('d') with bounds (lda,ka)]

Returns

c [rank-2 array('d') with bounds (n,n)]

Other Parameters

beta [input float, optional] Default: 0.0
c [input rank-2 array('d') with bounds (n,n)]
overwrite_c [input int, optional] Default: 0
trans [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.dtrmm

`scipy.linalg.blas.dtrmm(alpha, a, b[, side, lower, trans_a, diag, overwrite_b]) = <fortran object>`
 Wrapper for dtrmm.

Parameters

alpha [input float]
a [input rank-2 array('d') with bounds (lda,k)]
b [input rank-2 array('d') with bounds (ldb,n)]

Returns

b [rank-2 array('d') with bounds (ldb,n)]

Other Parameters

overwrite_b [input int, optional] Default: 0
side [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans_a [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.dtrsm

`scipy.linalg.blas.dtrsm(alpha, a, b[, side, lower, trans_a, diag, overwrite_b]) = <fortran object>`
 Wrapper for dtrsm.

Parameters

alpha [input float]
a [input rank-2 array('d') with bounds (lda,*)]
b [input rank-2 array('d') with bounds (ldb,n)]

Returns

x [rank-2 array('d') with bounds (ldb,n) and b storage]

Other Parameters

overwrite_b [input int, optional] Default: 0
side [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans_a [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.cgemm

`scipy.linalg.blas.cgemm(alpha, a, b[, beta, c, trans_a, trans_b, overwrite_c]) = <fortran object>`

Wrapper for cgemv.

Parameters

alpha [input complex]
a [input rank-2 array('F') with bounds (lda,ka)]
b [input rank-2 array('F') with bounds (ldb,kb)]

Returns

c [rank-2 array('F') with bounds (m,n)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)
c [input rank-2 array('F') with bounds (m,n)]
overwrite_c [input int, optional] Default: 0
trans_a [input int, optional] Default: 0
trans_b [input int, optional] Default: 0

scipy.linalg.blas.chemm

`scipy.linalg.blas.chemm(alpha, a, b[, beta, c, side, lower, overwrite_c]) = <fortran object>`

Wrapper for chemm.

Parameters

alpha [input complex]
a [input rank-2 array('F') with bounds (lda,ka)]
b [input rank-2 array('F') with bounds (ldb,kb)]

Returns

c [rank-2 array('F') with bounds (m,n)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)
c [input rank-2 array('F') with bounds (m,n)]
overwrite_c [input int, optional] Default: 0
side [input int, optional] Default: 0

lower [input int, optional] Default: 0

scipy.linalg.blas.cher2k

`scipy.linalg.blas.cher2k(alpha, a, b[, beta, c, trans, lower, overwrite_c]) = <fortran object>`
 Wrapper for `cher2k`.

Parameters

alpha [input complex]
a [input rank-2 array('F') with bounds (lda,ka)]
b [input rank-2 array('F') with bounds (ldb,kb)]

Returns

c [rank-2 array('F') with bounds (n,n)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)
c [input rank-2 array('F') with bounds (n,n)]
overwrite_c [input int, optional] Default: 0
trans [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.cherk

`scipy.linalg.blas.cherk(alpha, a[, beta, c, trans, lower, overwrite_c]) = <fortran object>`
 Wrapper for `cherk`.

Parameters

alpha [input complex]
a [input rank-2 array('F') with bounds (lda,ka)]

Returns

c [rank-2 array('F') with bounds (n,n)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)
c [input rank-2 array('F') with bounds (n,n)]
overwrite_c [input int, optional] Default: 0
trans [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.csymm

`scipy.linalg.blas.csymm` (*alpha*, *a*, *b*[, *beta*, *c*, *side*, *lower*, *overwrite_c*]) = <fortran object>
 Wrapper for `csymm`.

Parameters

alpha [input complex]
a [input rank-2 array('F') with bounds (lda,ka)]
b [input rank-2 array('F') with bounds (ldb,kb)]

Returns

c [rank-2 array('F') with bounds (m,n)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)
c [input rank-2 array('F') with bounds (m,n)]
overwrite_c [input int, optional] Default: 0
side [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.csyr2k

`scipy.linalg.blas.csyr2k` (*alpha*, *a*, *b*[, *beta*, *c*, *trans*, *lower*, *overwrite_c*]) = <fortran object>
 Wrapper for `csyr2k`.

Parameters

alpha [input complex]
a [input rank-2 array('F') with bounds (lda,ka)]
b [input rank-2 array('F') with bounds (ldb,kb)]

Returns

c [rank-2 array('F') with bounds (n,n)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)
c [input rank-2 array('F') with bounds (n,n)]
overwrite_c [input int, optional] Default: 0
trans [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.csyrk

`scipy.linalg.blas.csyrk` (*alpha*, *a*[, *beta*, *c*, *trans*, *lower*, *overwrite_c*]) = <fortran object>
 Wrapper for `csyrk`.

Parameters

alpha [input complex]
a [input rank-2 array('F') with bounds (lda,ka)]

Returns

c [rank-2 array('F') with bounds (n,n)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)
c [input rank-2 array('F') with bounds (n,n)]
overwrite_c [input int, optional] Default: 0
trans [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.ctrmm

`scipy.linalg.blas.ctrmm(alpha, a, b[, side, lower, trans_a, diag, overwrite_b]) = <fortran object>`

Wrapper for `ctrmm`.

Parameters

alpha [input complex]
a [input rank-2 array('F') with bounds (lda,k)]
b [input rank-2 array('F') with bounds (ldb,n)]

Returns

b [rank-2 array('F') with bounds (ldb,n)]

Other Parameters

overwrite_b [input int, optional] Default: 0
side [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans_a [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.ctrsm

`scipy.linalg.blas.ctrsm(alpha, a, b[, side, lower, trans_a, diag, overwrite_b]) = <fortran object>`

Wrapper for `ctrsm`.

Parameters

alpha [input complex]
a [input rank-2 array('F') with bounds (lda,*)]
b [input rank-2 array('F') with bounds (ldb,n)]

Returns

x [rank-2 array('F') with bounds (ldb,n) and b storage]

Other Parameters

overwrite_b [input int, optional] Default: 0
side [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans_a [input int, optional] Default: 0

diag [input int, optional] Default: 0

scipy.linalg.blas.zgemm

`scipy.linalg.blas.zgemm(alpha, a, b[, beta, c, trans_a, trans_b, overwrite_c]) = <fortran object>`

Wrapper for zgemv.

Parameters

alpha [input complex]
a [input rank-2 array('D') with bounds (lda,ka)]
b [input rank-2 array('D') with bounds (ldb,kb)]

Returns

c [rank-2 array('D') with bounds (m,n)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)
c [input rank-2 array('D') with bounds (m,n)]
overwrite_c [input int, optional] Default: 0
trans_a [input int, optional] Default: 0
trans_b [input int, optional] Default: 0

scipy.linalg.blas.zhemm

`scipy.linalg.blas.zhemm(alpha, a, b[, beta, c, side, lower, overwrite_c]) = <fortran object>`

Wrapper for zhemv.

Parameters

alpha [input complex]
a [input rank-2 array('D') with bounds (lda,ka)]
b [input rank-2 array('D') with bounds (ldb,kb)]

Returns

c [rank-2 array('D') with bounds (m,n)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)
c [input rank-2 array('D') with bounds (m,n)]
overwrite_c [input int, optional] Default: 0
side [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.zher2k

`scipy.linalg.blas.zher2k` (*alpha*, *a*, *b*[, *beta*, *c*, *trans*, *lower*, *overwrite_c*]) = <fortran object>
 Wrapper for zher2k.

Parameters

alpha [input complex]
a [input rank-2 array('D') with bounds (lda,ka)]
b [input rank-2 array('D') with bounds (ldb,kb)]

Returns

c [rank-2 array('D') with bounds (n,n)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)
c [input rank-2 array('D') with bounds (n,n)]
overwrite_c [input int, optional] Default: 0
trans [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.zherk

`scipy.linalg.blas.zherk` (*alpha*, *a*[, *beta*, *c*, *trans*, *lower*, *overwrite_c*]) = <fortran object>
 Wrapper for zherk.

Parameters

alpha [input complex]
a [input rank-2 array('D') with bounds (lda,ka)]

Returns

c [rank-2 array('D') with bounds (n,n)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)
c [input rank-2 array('D') with bounds (n,n)]
overwrite_c [input int, optional] Default: 0
trans [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.blas.zsymm

`scipy.linalg.blas.zsymm` (*alpha*, *a*, *b*[, *beta*, *c*, *side*, *lower*, *overwrite_c*]) = <fortran object>
 Wrapper for zsymm.

Parameters

alpha [input complex]
a [input rank-2 array('D') with bounds (lda,ka)]
b [input rank-2 array('D') with bounds (ldb,kb)]

Returns

c [rank-2 array('D') with bounds (m,n)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)

c [input rank-2 array('D') with bounds (m,n)]

overwrite_c

[input int, optional] Default: 0

side [input int, optional] Default: 0

lower [input int, optional] Default: 0

scipy.linalg.blas.zsyr2k

`scipy.linalg.blas.zsyr2k(alpha, a, b[, beta, c, trans, lower, overwrite_c]) = <fortran object>`
 Wrapper for zsyr2k.

Parameters

alpha [input complex]

a [input rank-2 array('D') with bounds (lda,ka)]

b [input rank-2 array('D') with bounds (ldb,kb)]

Returns

c [rank-2 array('D') with bounds (n,n)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)

c [input rank-2 array('D') with bounds (n,n)]

overwrite_c

[input int, optional] Default: 0

trans [input int, optional] Default: 0

lower [input int, optional] Default: 0

scipy.linalg.blas.zsyrk

`scipy.linalg.blas.zsyrk(alpha, a[, beta, c, trans, lower, overwrite_c]) = <fortran object>`
 Wrapper for zsyrk.

Parameters

alpha [input complex]

a [input rank-2 array('D') with bounds (lda,ka)]

Returns

c [rank-2 array('D') with bounds (n,n)]

Other Parameters

beta [input complex, optional] Default: (0.0, 0.0)

c [input rank-2 array('D') with bounds (n,n)]

overwrite_c

[input int, optional] Default: 0

trans [input int, optional] Default: 0

lower [input int, optional] Default: 0

scipy.linalg.blas.ztrmm

`scipy.linalg.blas.ztrmm(alpha, a, b[, side, lower, trans_a, diag, overwrite_b]) = <fortran object>`

Wrapper for `ztrmm`.

Parameters

alpha [input complex]
a [input rank-2 array('D') with bounds (lda,k)]
b [input rank-2 array('D') with bounds (ldb,n)]

Returns

b [rank-2 array('D') with bounds (ldb,n)]

Other Parameters

overwrite_b
 [input int, optional] Default: 0
side [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans_a [input int, optional] Default: 0
diag [input int, optional] Default: 0

scipy.linalg.blas.ztrsm

`scipy.linalg.blas.ztrsm(alpha, a, b[, side, lower, trans_a, diag, overwrite_b]) = <fortran object>`

Wrapper for `ztrsm`.

Parameters

alpha [input complex]
a [input rank-2 array('D') with bounds (lda,*)]
b [input rank-2 array('D') with bounds (ldb,n)]

Returns

x [rank-2 array('D') with bounds (ldb,n) and b storage]

Other Parameters

overwrite_b
 [input int, optional] Default: 0
side [input int, optional] Default: 0
lower [input int, optional] Default: 0
trans_a [input int, optional] Default: 0
diag [input int, optional] Default: 0

6.12 Low-level LAPACK functions (`scipy.linalg.lapack`)

This module contains low-level functions from the LAPACK library.

The **gegv* family of routines have been removed from LAPACK 3.6.0 and have been deprecated in SciPy 0.17.0. They will be removed in a future release.

New in version 0.12.0.

Note: The common `overwrite_<>` option in many routines, allows the input arrays to be overwritten to avoid extra memory allocation. However this requires the array to satisfy two conditions which are memory order and the data type to match exactly the order and the type expected by the routine.

As an example, if you pass a double precision float array to any `S . . .` routine which expects single precision arguments, `f2py` will create an intermediate array to match the argument types and overwriting will be performed on that intermediate array.

Similarly, if a C-contiguous array is passed, `f2py` will pass a FORTRAN-contiguous array internally. Please make sure that these details are satisfied. More information can be found in the `f2py` documentation.

Warning: These functions do little to no error checking. It is possible to cause crashes by mis-using them, so prefer using the higher-level routines in `scipy.linalg`.

6.12.1 Finding functions

`get_lapack_funcs`(names[, arrays, dtype, ilp64]) Return available LAPACK function objects from names.

`scipy.linalg.lapack.get_lapack_funcs`

`scipy.linalg.lapack.get_lapack_funcs` (names, arrays=(), dtype=None, ilp64=False)

Return available LAPACK function objects from names.

Arrays are used to determine the optimal prefix of LAPACK routines.

Parameters

names	[str or sequence of str] Name(s) of LAPACK functions without type prefix.
arrays	[sequence of ndarrays, optional] Arrays can be given to determine optimal prefix of LAPACK routines. If not given, double-precision routines will be used, otherwise the most generic type in arrays will be used.
dtype	[str or dtype, optional] Data-type specifier. Not used if <i>arrays</i> is non-empty.
ilp64	[[True, False, 'preferred'], optional] Whether to return ILP64 routine variant. Choosing 'preferred' returns ILP64 routine if available, and otherwise the 32-bit routine. Default: False

Returns

funcs	[list] List containing the found function(s).
--------------	---

Notes

This routine automatically chooses between Fortran/C interfaces. Fortran code is used whenever possible for arrays with column major order. In all other cases, C code is preferred.

In LAPACK, the naming convention is that all functions start with a type prefix, which depends on the type of the principal matrix. These can be one of {'s', 'd', 'c', 'z'} for the NumPy types {float32, float64, complex64, complex128} respectively, and are stored in attribute `typecode` of the returned functions.

Examples

Suppose we would like to use `?lange` routine which computes the selected norm of an array. We pass our array in order to get the correct `'lange'` flavor.

```
>>> import scipy.linalg as LA
>>> a = np.random.rand(3,2)
>>> x_lange = LA.get_lapack_funcs('lange', (a,))
>>> x_lange.typecode
'd'
>>> x_lange = LA.get_lapack_funcs('lange', (a*1j,))
>>> x_lange.typecode
'z'
```

Several LAPACK routines work best when its internal `WORK` array has the optimal size (big enough for fast computation and small enough to avoid waste of memory). This size is determined also by a dedicated query to the function which is often wrapped as a standalone function and commonly denoted as `###_lwork`. Below is an example for `?sysv`

```
>>> import scipy.linalg as LA
>>> a = np.random.rand(1000,1000)
>>> b = np.random.rand(1000,1)*1j
>>> # We pick up zsysv and zsysv_lwork due to b array
... xsysv, xlwork = LA.get_lapack_funcs(('sysv', 'sysv_lwork'), (a, b))
>>> opt_lwork, _ = xlwork(a.shape[0]) # returns a complex for 'z' prefix
>>> udut, ipiv, x, info = xsysv(a, b, lwork=int(opt_lwork.real))
```

6.12.2 All functions

<code>sgbsv(kl,ku,ab,b,[overwrite_ab,overwrite_b])</code>	Wrapper for <code>sgbsv</code> .
<code>dgbsv(kl,ku,ab,b,[overwrite_ab,overwrite_b])</code>	Wrapper for <code>dgbsv</code> .
<code>cgbsv(kl,ku,ab,b,[overwrite_ab,overwrite_b])</code>	Wrapper for <code>cgbsv</code> .
<code>zgbsv(kl,ku,ab,b,[overwrite_ab,overwrite_b])</code>	Wrapper for <code>zgbsv</code> .
<code>sgbtrf(ab,kl,ku,[m,n,ldab,overwrite_ab])</code>	Wrapper for <code>sgbtrf</code> .
<code>dgbtrf(ab,kl,ku,[m,n,ldab,overwrite_ab])</code>	Wrapper for <code>dgbtrf</code> .
<code>cgbtrf(ab,kl,ku,[m,n,ldab,overwrite_ab])</code>	Wrapper for <code>cgbtrf</code> .
<code>zgbtrf(ab,kl,ku,[m,n,ldab,overwrite_ab])</code>	Wrapper for <code>zgbtrf</code> .
<code>sgbtrs(...)</code>	Wrapper for <code>sgbtrs</code> .
<code>dgbtrs(...)</code>	Wrapper for <code>dgbtrs</code> .
<code>cgbtrs(...)</code>	Wrapper for <code>cgbtrs</code> .
<code>zgbtrs(...)</code>	Wrapper for <code>zgbtrs</code> .

continues on next page

Table 103 – continued from previous page

<code>sgebal(a,[scale,permute,overwrite_a])</code>	Wrapper for <code>sgebal</code> .
<code>dgebal(a,[scale,permute,overwrite_a])</code>	Wrapper for <code>dgebal</code> .
<code>cgebal(a,[scale,permute,overwrite_a])</code>	Wrapper for <code>cgebal</code> .
<code>zgebal(a,[scale,permute,overwrite_a])</code>	Wrapper for <code>zgebal</code> .
<code>sgecon(a,anorm,[norm])</code>	Wrapper for <code>sgecon</code> .
<code>dgecon(a,anorm,[norm])</code>	Wrapper for <code>dgecon</code> .
<code>cgecon(a,anorm,[norm])</code>	Wrapper for <code>cgecon</code> .
<code>zgecon(a,anorm,[norm])</code>	Wrapper for <code>zgecon</code> .
<code>sgeequ(a)</code>	Wrapper for <code>sgeequ</code> .
<code>dgeequ(a)</code>	Wrapper for <code>dgeequ</code> .
<code>cgeequ(a)</code>	Wrapper for <code>cgeequ</code> .
<code>zgeequ(a)</code>	Wrapper for <code>zgeequ</code> .
<code>sgeequb(a)</code>	Wrapper for <code>sgeequb</code> .
<code>dgeequb(a)</code>	Wrapper for <code>dgeequb</code> .
<code>cgeequb(a)</code>	Wrapper for <code>cgeequb</code> .
<code>zgeequb(a)</code>	Wrapper for <code>zgeequb</code> .
<code>sgees(...)</code>	Wrapper for <code>sgees</code> .
<code>dgees(...)</code>	Wrapper for <code>dgees</code> .
<code>cgees(...)</code>	Wrapper for <code>cgees</code> .
<code>zgees(...)</code>	Wrapper for <code>zgees</code> .
<code>sgeev(...)</code>	Wrapper for <code>sgeev</code> .
<code>dgeev(...)</code>	Wrapper for <code>dgeev</code> .
<code>cgeev(...)</code>	Wrapper for <code>cgeev</code> .
<code>zgeev(...)</code>	Wrapper for <code>zgeev</code> .
<code>sgeev_lwork(n,[compute_vl,compute_vr])</code>	Wrapper for <code>sgeev_lwork</code> .
<code>dgeev_lwork(n,[compute_vl,compute_vr])</code>	Wrapper for <code>dgeev_lwork</code> .
<code>cgeev_lwork(n,[compute_vl,compute_vr])</code>	Wrapper for <code>cgeev_lwork</code> .
<code>zgeev_lwork(n,[compute_vl,compute_vr])</code>	Wrapper for <code>zgeev_lwork</code> .
<code>sgegv(*args, **kwargs)</code>	<code>sgegv</code> is deprecated! The <code>*gegv</code> family of routines has been deprecated in LAPACK 3.6.0 in favor of the <code>*ggev</code> family of routines.
<code>dgegv(*args, **kwargs)</code>	<code>dgegv</code> is deprecated! The <code>*gegv</code> family of routines has been deprecated in LAPACK 3.6.0 in favor of the <code>*ggev</code> family of routines.
<code>cgegv(*args, **kwargs)</code>	<code>cgegv</code> is deprecated! The <code>*gegv</code> family of routines has been deprecated in LAPACK 3.6.0 in favor of the <code>*ggev</code> family of routines.
<code>zgegv(*args, **kwargs)</code>	<code>zgegv</code> is deprecated! The <code>*gegv</code> family of routines has been deprecated in LAPACK 3.6.0 in favor of the <code>*ggev</code> family of routines.
<code>sgehrd(a,[lo,hi,lwork,overwrite_a])</code>	Wrapper for <code>sgehrd</code> .
<code>dgehrd(a,[lo,hi,lwork,overwrite_a])</code>	Wrapper for <code>dgehrd</code> .
<code>cgehrd(a,[lo,hi,lwork,overwrite_a])</code>	Wrapper for <code>cgehrd</code> .
<code>zgehrd(a,[lo,hi,lwork,overwrite_a])</code>	Wrapper for <code>zgehrd</code> .
<code>sgehrd_lwork(n,[lo,hi])</code>	Wrapper for <code>sgehrd_lwork</code> .
<code>dgehrd_lwork(n,[lo,hi])</code>	Wrapper for <code>dgehrd_lwork</code> .
<code>cgehrd_lwork(n,[lo,hi])</code>	Wrapper for <code>cgehrd_lwork</code> .
<code>zgehrd_lwork(n,[lo,hi])</code>	Wrapper for <code>zgehrd_lwork</code> .
<code>sgejsv(...)</code>	Wrapper for <code>sgejsv</code> .
<code>dgejsv(...)</code>	Wrapper for <code>dgejsv</code> .
<code>sgels(a,b,[trans,lwork,overwrite_a,overwrite_b])</code>	Wrapper for <code>sgels</code> .

continues on next page

Table 103 – continued from previous page

<i>dgels</i> (a,b,[trans,lwork,overwrite_a,overwrite_b])	Wrapper for <i>dgels</i> .
<i>cgels</i> (a,b,[trans,lwork,overwrite_a,overwrite_b])	Wrapper for <i>cgels</i> .
<i>zgels</i> (a,b,[trans,lwork,overwrite_a,overwrite_b])	Wrapper for <i>zgels</i> .
<i>sgels_lwork</i> (m,n,nrhs,[trans])	Wrapper for <i>sgels_lwork</i> .
<i>dgels_lwork</i> (m,n,nrhs,[trans])	Wrapper for <i>dgels_lwork</i> .
<i>cgels_lwork</i> (m,n,nrhs,[trans])	Wrapper for <i>cgels_lwork</i> .
<i>zgels_lwork</i> (m,n,nrhs,[trans])	Wrapper for <i>zgels_lwork</i> .
<i>sgelsd</i> (...)	Wrapper for <i>sgelsd</i> .
<i>dgelsd</i> (...)	Wrapper for <i>dgelsd</i> .
<i>cgelsd</i> (...)	Wrapper for <i>cgelsd</i> .
<i>zgelsd</i> (...)	Wrapper for <i>zgelsd</i> .
<i>sgelsd_lwork</i> (m,n,nrhs,[cond,lwork])	Wrapper for <i>sgelsd_lwork</i> .
<i>dgelsd_lwork</i> (m,n,nrhs,[cond,lwork])	Wrapper for <i>dgelsd_lwork</i> .
<i>cgelsd_lwork</i> (m,n,nrhs,[cond,lwork])	Wrapper for <i>cgelsd_lwork</i> .
<i>zgelsd_lwork</i> (m,n,nrhs,[cond,lwork])	Wrapper for <i>zgelsd_lwork</i> .
<i>sgelss</i> (a,b,[cond,lwork,overwrite_a,overwrite_b])	Wrapper for <i>sgelss</i> .
<i>dgelss</i> (a,b,[cond,lwork,overwrite_a,overwrite_b])	Wrapper for <i>dgelss</i> .
<i>cgelss</i> (a,b,[cond,lwork,overwrite_a,overwrite_b])	Wrapper for <i>cgelss</i> .
<i>zgelss</i> (a,b,[cond,lwork,overwrite_a,overwrite_b])	Wrapper for <i>zgelss</i> .
<i>sgelss_lwork</i> (m,n,nrhs,[cond,lwork])	Wrapper for <i>sgelss_lwork</i> .
<i>dgelss_lwork</i> (m,n,nrhs,[cond,lwork])	Wrapper for <i>dgelss_lwork</i> .
<i>cgelss_lwork</i> (m,n,nrhs,[cond,lwork])	Wrapper for <i>cgelss_lwork</i> .
<i>zgelss_lwork</i> (m,n,nrhs,[cond,lwork])	Wrapper for <i>zgelss_lwork</i> .
<i>sgelsy</i> (...)	Wrapper for <i>sgelsy</i> .
<i>dgelsy</i> (...)	Wrapper for <i>dgelsy</i> .
<i>cgelsy</i> (...)	Wrapper for <i>cgelsy</i> .
<i>zgelsy</i> (...)	Wrapper for <i>zgelsy</i> .
<i>sgelsy_lwork</i> (m,n,nrhs,cond,[lwork])	Wrapper for <i>sgelsy_lwork</i> .
<i>dgelsy_lwork</i> (m,n,nrhs,cond,[lwork])	Wrapper for <i>dgelsy_lwork</i> .
<i>cgelsy_lwork</i> (m,n,nrhs,cond,[lwork])	Wrapper for <i>cgelsy_lwork</i> .
<i>zgelsy_lwork</i> (m,n,nrhs,cond,[lwork])	Wrapper for <i>zgelsy_lwork</i> .
<i>sgeqp3</i> (a,[lwork,overwrite_a])	Wrapper for <i>sgeqp3</i> .
<i>dgeqp3</i> (a,[lwork,overwrite_a])	Wrapper for <i>dgeqp3</i> .
<i>cgeqp3</i> (a,[lwork,overwrite_a])	Wrapper for <i>cgeqp3</i> .
<i>zgeqp3</i> (a,[lwork,overwrite_a])	Wrapper for <i>zgeqp3</i> .
<i>sgeqrf</i> (a,[lwork,overwrite_a])	Wrapper for <i>sgeqrf</i> .
<i>dgeqrf</i> (a,[lwork,overwrite_a])	Wrapper for <i>dgeqrf</i> .
<i>cgeqrf</i> (a,[lwork,overwrite_a])	Wrapper for <i>cgeqrf</i> .
<i>zgeqrf</i> (a,[lwork,overwrite_a])	Wrapper for <i>zgeqrf</i> .
<i>sgeqrf_lwork</i> (m,n)	Wrapper for <i>sgeqrf_lwork</i> .
<i>dgeqrf_lwork</i> (m,n)	Wrapper for <i>dgeqrf_lwork</i> .
<i>cgeqrf_lwork</i> (m,n)	Wrapper for <i>cgeqrf_lwork</i> .
<i>zgeqrf_lwork</i> (m,n)	Wrapper for <i>zgeqrf_lwork</i> .
<i>sgeqrfp</i> (a,[lwork,overwrite_a])	Wrapper for <i>sgeqrfp</i> .
<i>dgeqrfp</i> (a,[lwork,overwrite_a])	Wrapper for <i>dgeqrfp</i> .
<i>cgeqrfp</i> (a,[lwork,overwrite_a])	Wrapper for <i>cgeqrfp</i> .
<i>zgeqrfp</i> (a,[lwork,overwrite_a])	Wrapper for <i>zgeqrfp</i> .
<i>sgeqrfp_lwork</i> (m,n)	Wrapper for <i>sgeqrfp_lwork</i> .
<i>dgeqrfp_lwork</i> (m,n)	Wrapper for <i>dgeqrfp_lwork</i> .
<i>cgeqrfp_lwork</i> (m,n)	Wrapper for <i>cgeqrfp_lwork</i> .

continues on next page

Table 103 – continued from previous page

<i>zgeqrfp_lwork</i> (m,n)	Wrapper for <i>zgeqrfp_lwork</i> .
<i>sgerqf</i> (a,[lwork,overwrite_a])	Wrapper for <i>sgerqf</i> .
<i>dgerqf</i> (a,[lwork,overwrite_a])	Wrapper for <i>dgerqf</i> .
<i>cgerqf</i> (a,[lwork,overwrite_a])	Wrapper for <i>cgerqf</i> .
<i>zgerqf</i> (a,[lwork,overwrite_a])	Wrapper for <i>zgerqf</i> .
<i>sgesdd</i> (...)	Wrapper for <i>sgesdd</i> .
<i>dgesdd</i> (...)	Wrapper for <i>dgesdd</i> .
<i>cgesdd</i> (...)	Wrapper for <i>cgesdd</i> .
<i>zgesdd</i> (...)	Wrapper for <i>zgesdd</i> .
<i>sgesdd_lwork</i> (m,n,[compute_uv,full_matrices])	Wrapper for <i>sgesdd_lwork</i> .
<i>dgesdd_lwork</i> (m,n,[compute_uv,full_matrices])	Wrapper for <i>dgesdd_lwork</i> .
<i>cgesdd_lwork</i> (m,n,[compute_uv,full_matrices])	Wrapper for <i>cgesdd_lwork</i> .
<i>zgesdd_lwork</i> (m,n,[compute_uv,full_matrices])	Wrapper for <i>zgesdd_lwork</i> .
<i>sgesv</i> (a,b,[overwrite_a,overwrite_b])	Wrapper for <i>sgesv</i> .
<i>dgesv</i> (a,b,[overwrite_a,overwrite_b])	Wrapper for <i>dgesv</i> .
<i>cgesv</i> (a,b,[overwrite_a,overwrite_b])	Wrapper for <i>cgesv</i> .
<i>zgesv</i> (a,b,[overwrite_a,overwrite_b])	Wrapper for <i>zgesv</i> .
<i>sgesvd</i> (...)	Wrapper for <i>sgesvd</i> .
<i>dgesvd</i> (...)	Wrapper for <i>dgesvd</i> .
<i>cgesvd</i> (...)	Wrapper for <i>cgesvd</i> .
<i>zgesvd</i> (...)	Wrapper for <i>zgesvd</i> .
<i>sgesvd_lwork</i> (m,n,[compute_uv,full_matrices])	Wrapper for <i>sgesvd_lwork</i> .
<i>dgesvd_lwork</i> (m,n,[compute_uv,full_matrices])	Wrapper for <i>dgesvd_lwork</i> .
<i>cgesvd_lwork</i> (m,n,[compute_uv,full_matrices])	Wrapper for <i>cgesvd_lwork</i> .
<i>zgesvd_lwork</i> (m,n,[compute_uv,full_matrices])	Wrapper for <i>zgesvd_lwork</i> .
<i>sgesvx</i> (...)	Wrapper for <i>sgesvx</i> .
<i>dgesvx</i> (...)	Wrapper for <i>dgesvx</i> .
<i>cgesvx</i> (...)	Wrapper for <i>cgesvx</i> .
<i>zgesvx</i> (...)	Wrapper for <i>zgesvx</i> .
<i>sgetrf</i> (a,[overwrite_a])	Wrapper for <i>sgetrf</i> .
<i>dgetrf</i> (a,[overwrite_a])	Wrapper for <i>dgetrf</i> .
<i>cgetrf</i> (a,[overwrite_a])	Wrapper for <i>cgetrf</i> .
<i>zgetrf</i> (a,[overwrite_a])	Wrapper for <i>zgetrf</i> .
<i>sgetc2</i> (a,[overwrite_a])	Wrapper for <i>sgetc2</i> .
<i>dgetc2</i> (a,[overwrite_a])	Wrapper for <i>dgetc2</i> .
<i>cgetc2</i> (a,[overwrite_a])	Wrapper for <i>cgetc2</i> .
<i>zgetc2</i> (a,[overwrite_a])	Wrapper for <i>zgetc2</i> .
<i>sgetri</i> (lu,piv,[lwork,overwrite_lu])	Wrapper for <i>sgetri</i> .
<i>dgetri</i> (lu,piv,[lwork,overwrite_lu])	Wrapper for <i>dgetri</i> .
<i>cgetri</i> (lu,piv,[lwork,overwrite_lu])	Wrapper for <i>cgetri</i> .
<i>zgetri</i> (lu,piv,[lwork,overwrite_lu])	Wrapper for <i>zgetri</i> .
<i>sgetri_lwork</i> (n)	Wrapper for <i>sgetri_lwork</i> .
<i>dgetri_lwork</i> (n)	Wrapper for <i>dgetri_lwork</i> .
<i>cgetri_lwork</i> (n)	Wrapper for <i>cgetri_lwork</i> .
<i>zgetri_lwork</i> (n)	Wrapper for <i>zgetri_lwork</i> .
<i>sgetrs</i> (lu,piv,b,[trans,overwrite_b])	Wrapper for <i>sgetrs</i> .
<i>dgetrs</i> (lu,piv,b,[trans,overwrite_b])	Wrapper for <i>dgetrs</i> .
<i>cgetrs</i> (lu,piv,b,[trans,overwrite_b])	Wrapper for <i>cgetrs</i> .
<i>zgetrs</i> (lu,piv,b,[trans,overwrite_b])	Wrapper for <i>zgetrs</i> .
<i>sgesc2</i> (lu,rhs,ipiv,jpiv,[overwrite_rhs])	Wrapper for <i>sgesc2</i> .

continues on next page

Table 103 – continued from previous page

<i>dgesc2</i> (lu,rhs,ipiv,jpiv,[overwrite_rhs])	Wrapper for <i>dgesc2</i> .
<i>cgesc2</i> (lu,rhs,ipiv,jpiv,[overwrite_rhs])	Wrapper for <i>cgesc2</i> .
<i>zgesc2</i> (lu,rhs,ipiv,jpiv,[overwrite_rhs])	Wrapper for <i>zgesc2</i> .
<i>sgges</i> (...)	Wrapper for <i>sgges</i> .
<i>dgges</i> (...)	Wrapper for <i>dgges</i> .
<i>cgges</i> (...)	Wrapper for <i>cgges</i> .
<i>zgges</i> (...)	Wrapper for <i>zgges</i> .
<i>sggev</i> (...)	Wrapper for <i>sggev</i> .
<i>dggev</i> (...)	Wrapper for <i>dggev</i> .
<i>cggev</i> (...)	Wrapper for <i>cggev</i> .
<i>zggev</i> (...)	Wrapper for <i>zggev</i> .
<i>sgglse</i> (...)	Wrapper for <i>sgglse</i> .
<i>dggls</i> (...)	Wrapper for <i>dggls</i> .
<i>cgglse</i> (...)	Wrapper for <i>cgglse</i> .
<i>zggls</i> (...)	Wrapper for <i>zggls</i> .
<i>sgglse_lwork</i> (m,n,p)	Wrapper for <i>sgglse_lwork</i> .
<i>dggls_lwork</i> (m,n,p)	Wrapper for <i>dggls_lwork</i> .
<i>cgglse_lwork</i> (m,n,p)	Wrapper for <i>cgglse_lwork</i> .
<i>zggls_lwork</i> (m,n,p)	Wrapper for <i>zggls_lwork</i> .
<i>sgtsv</i> (...)	Wrapper for <i>sgtsv</i> .
<i>dgtsv</i> (...)	Wrapper for <i>dgtsv</i> .
<i>cgtsv</i> (...)	Wrapper for <i>cgtsv</i> .
<i>zgtsv</i> (...)	Wrapper for <i>zgtsv</i> .
<i>sgtsvx</i> (...)	Wrapper for <i>sgtsvx</i> .
<i>dgtsvx</i> (...)	Wrapper for <i>dgtsvx</i> .
<i>cgtsvx</i> (...)	Wrapper for <i>cgtsvx</i> .
<i>zgtsvx</i> (...)	Wrapper for <i>zgtsvx</i> .
<i>chbevd</i> (...)	Wrapper for <i>chbevd</i> .
<i>zhbevd</i> (...)	Wrapper for <i>zhbevd</i> .
<i>chbev</i> (...)	Wrapper for <i>chbev</i> .
<i>zhbev</i> (...)	Wrapper for <i>zhbev</i> .
<i>checon</i> (a,ipiv,anorm,[lower])	Wrapper for <i>checon</i> .
<i>zhecon</i> (a,ipiv,anorm,[lower])	Wrapper for <i>zhecon</i> .
<i>cheequb</i> (a,[lower])	Wrapper for <i>cheequb</i> .
<i>zheequb</i> (a,[lower])	Wrapper for <i>zheequb</i> .
<i>cheev</i> (a,[compute_v,lower,lwork,overwrite_a])	Wrapper for <i>cheev</i> .
<i>zheev</i> (a,[compute_v,lower,lwork,overwrite_a])	Wrapper for <i>zheev</i> .
<i>cheev_lwork</i> (n,[lower])	Wrapper for <i>cheev_lwork</i> .
<i>zheev_lwork</i> (n,[lower])	Wrapper for <i>zheev_lwork</i> .
<i>cheevd</i> (...)	Wrapper for <i>cheevd</i> .
<i>zheevd</i> (...)	Wrapper for <i>zheevd</i> .
<i>cheevd_lwork</i> (n,[compute_v,lower])	Wrapper for <i>cheevd_lwork</i> .
<i>zheevd_lwork</i> (n,[compute_v,lower])	Wrapper for <i>zheevd_lwork</i> .
<i>cheevr</i> (...)	Wrapper for <i>cheevr</i> .
<i>zheevr</i> (...)	Wrapper for <i>zheevr</i> .
<i>cheevr_lwork</i> (n,[lower])	Wrapper for <i>cheevr_lwork</i> .
<i>zheevr_lwork</i> (n,[lower])	Wrapper for <i>zheevr_lwork</i> .
<i>cheevx</i> (...)	Wrapper for <i>cheevx</i> .
<i>zheevx</i> (...)	Wrapper for <i>zheevx</i> .
<i>cheevx_lwork</i> (n,[lower])	Wrapper for <i>cheevx_lwork</i> .

continues on next page

Table 103 – continued from previous page

<i>zheevx_lwork</i> (n,[lower])	Wrapper for <i>zheevx_lwork</i> .
<i>chegst</i> (a,b,[itype,lower,overwrite_a])	Wrapper for <i>chegst</i> .
<i>zhegst</i> (a,b,[itype,lower,overwrite_a])	Wrapper for <i>zhegst</i> .
<i>chegv</i> (...)	Wrapper for <i>chegv</i> .
<i>zhegv</i> (...)	Wrapper for <i>zhegv</i> .
<i>chegv_lwork</i> (n,[uplo])	Wrapper for <i>chegv_lwork</i> .
<i>zhegv_lwork</i> (n,[uplo])	Wrapper for <i>zhegv_lwork</i> .
<i>chegvd</i> (...)	Wrapper for <i>chegvd</i> .
<i>zhegvd</i> (...)	Wrapper for <i>zhegvd</i> .
<i>chegvx</i> (...)	Wrapper for <i>chegvx</i> .
<i>zhegvx</i> (...)	Wrapper for <i>zhegvx</i> .
<i>chegvx_lwork</i> (n,[uplo])	Wrapper for <i>chegvx_lwork</i> .
<i>zhegvx_lwork</i> (n,[uplo])	Wrapper for <i>zhegvx_lwork</i> .
<i>chesv</i> (a,b,[lwork,lower,overwrite_a,overwrite_b])	Wrapper for <i>chesv</i> .
<i>zhesv</i> (a,b,[lwork,lower,overwrite_a,overwrite_b])	Wrapper for <i>zhesv</i> .
<i>chesv_lwork</i> (n,[lower])	Wrapper for <i>chesv_lwork</i> .
<i>zhesv_lwork</i> (n,[lower])	Wrapper for <i>zhesv_lwork</i> .
<i>chesvx</i> (...)	Wrapper for <i>chesvx</i> .
<i>zhesvx</i> (...)	Wrapper for <i>zhesvx</i> .
<i>chesvx_lwork</i> (n,[lower])	Wrapper for <i>chesvx_lwork</i> .
<i>zhesvx_lwork</i> (n,[lower])	Wrapper for <i>zhesvx_lwork</i> .
<i>chetrd</i> (a,[lower,lwork,overwrite_a])	Wrapper for <i>chetrd</i> .
<i>zhetrd</i> (a,[lower,lwork,overwrite_a])	Wrapper for <i>zhetrd</i> .
<i>chetrd_lwork</i> (n,[lower])	Wrapper for <i>chetrd_lwork</i> .
<i>zhetrd_lwork</i> (n,[lower])	Wrapper for <i>zhetrd_lwork</i> .
<i>chetrf</i> (a,[lower,lwork,overwrite_a])	Wrapper for <i>chetrf</i> .
<i>zhetrf</i> (a,[lower,lwork,overwrite_a])	Wrapper for <i>zhetrf</i> .
<i>chetrf_lwork</i> (n,[lower])	Wrapper for <i>chetrf_lwork</i> .
<i>zhetrf_lwork</i> (n,[lower])	Wrapper for <i>zhetrf_lwork</i> .
<i>chfrk</i> (...)	Wrapper for <i>chfrk</i> .
<i>zhfrk</i> (...)	Wrapper for <i>zhfrk</i> .
<i>slamch</i> (cmach)	Wrapper for <i>slamch</i> .
<i>dlamch</i> (cmach)	Wrapper for <i>dlamch</i> .
<i>slange</i> (norm,a)	Wrapper for <i>slange</i> .
<i>dlange</i> (norm,a)	Wrapper for <i>dlange</i> .
<i>clange</i> (norm,a)	Wrapper for <i>clange</i> .
<i>zlange</i> (norm,a)	Wrapper for <i>zlange</i> .
<i>slarf</i> (v,tau,c,work,[side,incv,overwrite_c])	Wrapper for <i>slarf</i> .
<i>dlarf</i> (v,tau,c,work,[side,incv,overwrite_c])	Wrapper for <i>dlarf</i> .
<i>clarf</i> (v,tau,c,work,[side,incv,overwrite_c])	Wrapper for <i>clarf</i> .
<i>zlarf</i> (v,tau,c,work,[side,incv,overwrite_c])	Wrapper for <i>zlarf</i> .
<i>slarfg</i> (n,alpha,x,[incx,overwrite_x])	Wrapper for <i>slarfg</i> .
<i>dlarfg</i> (n,alpha,x,[incx,overwrite_x])	Wrapper for <i>dlarfg</i> .
<i>clarfg</i> (n,alpha,x,[incx,overwrite_x])	Wrapper for <i>clarfg</i> .
<i>zlarfg</i> (n,alpha,x,[incx,overwrite_x])	Wrapper for <i>zlarfg</i> .
<i>slartg</i> (f,g)	Wrapper for <i>slartg</i> .
<i>dlartg</i> (f,g)	Wrapper for <i>dlartg</i> .
<i>clartg</i> (f,g)	Wrapper for <i>clartg</i> .
<i>zartg</i> (f,g)	Wrapper for <i>zartg</i> .
<i>slasd4</i> (i,d,z,[rho])	Wrapper for <i>slasd4</i> .

continues on next page

Table 103 – continued from previous page

<i>dlasd4</i> (i,d,z,[rho])	Wrapper for <i>dlasd4</i> .
<i>slaswp</i> (a,piv,[k1,k2,off,inc,overwrite_a])	Wrapper for <i>slaswp</i> .
<i>dlaswp</i> (a,piv,[k1,k2,off,inc,overwrite_a])	Wrapper for <i>dlaswp</i> .
<i>claswp</i> (a,piv,[k1,k2,off,inc,overwrite_a])	Wrapper for <i>claswp</i> .
<i>zlaswp</i> (a,piv,[k1,k2,off,inc,overwrite_a])	Wrapper for <i>zlaswp</i> .
<i>slauum</i> (c,[lower,overwrite_c])	Wrapper for <i>slauum</i> .
<i>dlauum</i> (c,[lower,overwrite_c])	Wrapper for <i>dlauum</i> .
<i>clauum</i> (c,[lower,overwrite_c])	Wrapper for <i>clauum</i> .
<i>zlauum</i> (c,[lower,overwrite_c])	Wrapper for <i>zlauum</i> .
<i>sorcsd</i> (...)	Wrapper for <i>sorcsd</i> .
<i>dorcsd</i> (...)	Wrapper for <i>dorcsd</i> .
<i>sorcsd_lwork</i> (m,p,q)	Wrapper for <i>sorcsd_lwork</i> .
<i>dorcsd_lwork</i> (m,p,q)	Wrapper for <i>dorcsd_lwork</i> .
<i>sorghr</i> (a,tau,[lo,hi,lwork,overwrite_a])	Wrapper for <i>sorghr</i> .
<i>dorghr</i> (a,tau,[lo,hi,lwork,overwrite_a])	Wrapper for <i>dorghr</i> .
<i>sorghr_lwork</i> (n,[lo,hi])	Wrapper for <i>sorghr_lwork</i> .
<i>dorghr_lwork</i> (n,[lo,hi])	Wrapper for <i>dorghr_lwork</i> .
<i>sorgqr</i> (a,tau,[lwork,overwrite_a])	Wrapper for <i>sorgqr</i> .
<i>dorgqr</i> (a,tau,[lwork,overwrite_a])	Wrapper for <i>dorgqr</i> .
<i>sorgqrq</i> (a,tau,[lwork,overwrite_a])	Wrapper for <i>sorgqrq</i> .
<i>dorgqrq</i> (a,tau,[lwork,overwrite_a])	Wrapper for <i>dorgqrq</i> .
<i>sormqr</i> (side,trans,a,tau,c,lwork,[overwrite_c])	Wrapper for <i>sormqr</i> .
<i>dormqr</i> (side,trans,a,tau,c,lwork,[overwrite_c])	Wrapper for <i>dormqr</i> .
<i>sormrz</i> (a,tau,c,[side,trans,lwork,overwrite_c])	Wrapper for <i>sormrz</i> .
<i>dormrz</i> (a,tau,c,[side,trans,lwork,overwrite_c])	Wrapper for <i>dormrz</i> .
<i>sormrz_lwork</i> (m,n,[side,trans])	Wrapper for <i>sormrz_lwork</i> .
<i>dormrz_lwork</i> (m,n,[side,trans])	Wrapper for <i>dormrz_lwork</i> .
<i>spbsv</i> (ab,b,[lower,ldab,overwrite_ab,overwrite_b])	Wrapper for <i>spbsv</i> .
<i>dpbsv</i> (ab,b,[lower,ldab,overwrite_ab,overwrite_b])	Wrapper for <i>dpbsv</i> .
<i>cpbsv</i> (ab,b,[lower,ldab,overwrite_ab,overwrite_b])	Wrapper for <i>cpbsv</i> .
<i>zpbsv</i> (ab,b,[lower,ldab,overwrite_ab,overwrite_b])	Wrapper for <i>zpbsv</i> .
<i>spbtrf</i> (ab,[lower,ldab,overwrite_ab])	Wrapper for <i>spbtrf</i> .
<i>dpbtrf</i> (ab,[lower,ldab,overwrite_ab])	Wrapper for <i>dpbtrf</i> .
<i>cpbtrf</i> (ab,[lower,ldab,overwrite_ab])	Wrapper for <i>cpbtrf</i> .
<i>zpbtrf</i> (ab,[lower,ldab,overwrite_ab])	Wrapper for <i>zpbtrf</i> .
<i>spbtrs</i> (ab,b,[lower,ldab,overwrite_b])	Wrapper for <i>spbtrs</i> .
<i>dpbtrs</i> (ab,b,[lower,ldab,overwrite_b])	Wrapper for <i>dpbtrs</i> .
<i>cpbtrs</i> (ab,b,[lower,ldab,overwrite_b])	Wrapper for <i>cpbtrs</i> .
<i>zpbtrs</i> (ab,b,[lower,ldab,overwrite_b])	Wrapper for <i>zpbtrs</i> .
<i>spfturf</i> (n,a,[transr,uplo,overwrite_a])	Wrapper for <i>spfturf</i> .
<i>dpfturf</i> (n,a,[transr,uplo,overwrite_a])	Wrapper for <i>dpfturf</i> .
<i>cpfturf</i> (n,a,[transr,uplo,overwrite_a])	Wrapper for <i>cpfturf</i> .
<i>zpftrf</i> (n,a,[transr,uplo,overwrite_a])	Wrapper for <i>zpftrf</i> .
<i>spfttri</i> (n,a,[transr,uplo,overwrite_a])	Wrapper for <i>spfttri</i> .
<i>dpfttri</i> (n,a,[transr,uplo,overwrite_a])	Wrapper for <i>dpfttri</i> .
<i>cpfttri</i> (n,a,[transr,uplo,overwrite_a])	Wrapper for <i>cpfttri</i> .
<i>zpftri</i> (n,a,[transr,uplo,overwrite_a])	Wrapper for <i>zpftri</i> .
<i>spfttrs</i> (n,a,b,[transr,uplo,overwrite_b])	Wrapper for <i>spfttrs</i> .
<i>dpfttrs</i> (n,a,b,[transr,uplo,overwrite_b])	Wrapper for <i>dpfttrs</i> .
<i>cpfttrs</i> (n,a,b,[transr,uplo,overwrite_b])	Wrapper for <i>cpfttrs</i> .

continues on next page

Table 103 – continued from previous page

<i>zpftrs</i> (n,a,b,[transr,uplo,overwrite_b])	Wrapper for <i>zpftrs</i> .
<i>spocon</i> (a,anorm,[uplo])	Wrapper for <i>spocon</i> .
<i>dpocon</i> (a,anorm,[uplo])	Wrapper for <i>dpocon</i> .
<i>cpocon</i> (a,anorm,[uplo])	Wrapper for <i>cpocon</i> .
<i>zpocon</i> (a,anorm,[uplo])	Wrapper for <i>zpocon</i> .
<i>spstrf</i> (a,[tol,lower,overwrite_a])	Wrapper for <i>spstrf</i> .
<i>dpstrf</i> (a,[tol,lower,overwrite_a])	Wrapper for <i>dpstrf</i> .
<i>cpstrf</i> (a,[tol,lower,overwrite_a])	Wrapper for <i>cpstrf</i> .
<i>zpstrf</i> (a,[tol,lower,overwrite_a])	Wrapper for <i>zpstrf</i> .
<i>spstf2</i> (a,[tol,lower,overwrite_a])	Wrapper for <i>spstf2</i> .
<i>dpstf2</i> (a,[tol,lower,overwrite_a])	Wrapper for <i>dpstf2</i> .
<i>cpstf2</i> (a,[tol,lower,overwrite_a])	Wrapper for <i>cpstf2</i> .
<i>zpstf2</i> (a,[tol,lower,overwrite_a])	Wrapper for <i>zpstf2</i> .
<i>sposv</i> (a,b,[lower,overwrite_a,overwrite_b])	Wrapper for <i>sposv</i> .
<i>dposv</i> (a,b,[lower,overwrite_a,overwrite_b])	Wrapper for <i>dposv</i> .
<i>cpovs</i> (a,b,[lower,overwrite_a,overwrite_b])	Wrapper for <i>cpovs</i> .
<i>zposv</i> (a,b,[lower,overwrite_a,overwrite_b])	Wrapper for <i>zposv</i> .
<i>sposvx</i> (...)	Wrapper for <i>sposvx</i> .
<i>dposvx</i> (...)	Wrapper for <i>dposvx</i> .
<i>cpovsx</i> (...)	Wrapper for <i>cpovsx</i> .
<i>zposvx</i> (...)	Wrapper for <i>zposvx</i> .
<i>spotrf</i> (a,[lower,clean,overwrite_a])	Wrapper for <i>spotrf</i> .
<i>dpotrf</i> (a,[lower,clean,overwrite_a])	Wrapper for <i>dpotrf</i> .
<i>cpotrf</i> (a,[lower,clean,overwrite_a])	Wrapper for <i>cpotrf</i> .
<i>zpotrf</i> (a,[lower,clean,overwrite_a])	Wrapper for <i>zpotrf</i> .
<i>spotri</i> (c,[lower,overwrite_c])	Wrapper for <i>spotri</i> .
<i>dpotri</i> (c,[lower,overwrite_c])	Wrapper for <i>dpotri</i> .
<i>cpotri</i> (c,[lower,overwrite_c])	Wrapper for <i>cpotri</i> .
<i>zpotri</i> (c,[lower,overwrite_c])	Wrapper for <i>zpotri</i> .
<i>spotrs</i> (c,b,[lower,overwrite_b])	Wrapper for <i>spotrs</i> .
<i>dpotrs</i> (c,b,[lower,overwrite_b])	Wrapper for <i>dpotrs</i> .
<i>cpotrs</i> (c,b,[lower,overwrite_b])	Wrapper for <i>cpotrs</i> .
<i>zpotrs</i> (c,b,[lower,overwrite_b])	Wrapper for <i>zpotrs</i> .
<i>sppcon</i> (n,ap,anorm,[lower])	Wrapper for <i>sppcon</i> .
<i>dppcon</i> (n,ap,anorm,[lower])	Wrapper for <i>dppcon</i> .
<i>cppcon</i> (n,ap,anorm,[lower])	Wrapper for <i>cppcon</i> .
<i>zppcon</i> (n,ap,anorm,[lower])	Wrapper for <i>zppcon</i> .
<i>sppsv</i> (n,ap,b,[lower,overwrite_b])	Wrapper for <i>sppsv</i> .
<i>dppsv</i> (n,ap,b,[lower,overwrite_b])	Wrapper for <i>dppsv</i> .
<i>cppsv</i> (n,ap,b,[lower,overwrite_b])	Wrapper for <i>cppsv</i> .
<i>zppsv</i> (n,ap,b,[lower,overwrite_b])	Wrapper for <i>zppsv</i> .
<i>spptrf</i> (n,ap,[lower,overwrite_ap])	Wrapper for <i>spptrf</i> .
<i>dpptrf</i> (n,ap,[lower,overwrite_ap])	Wrapper for <i>dpptrf</i> .
<i>cpptrf</i> (n,ap,[lower,overwrite_ap])	Wrapper for <i>cpptrf</i> .
<i>zpptrf</i> (n,ap,[lower,overwrite_ap])	Wrapper for <i>zpptrf</i> .
<i>spptri</i> (n,ap,[lower,overwrite_ap])	Wrapper for <i>spptri</i> .
<i>dpptri</i> (n,ap,[lower,overwrite_ap])	Wrapper for <i>dpptri</i> .
<i>cpptri</i> (n,ap,[lower,overwrite_ap])	Wrapper for <i>cpptri</i> .
<i>zpptri</i> (n,ap,[lower,overwrite_ap])	Wrapper for <i>zpptri</i> .
<i>spptrs</i> (n,ap,b,[lower,overwrite_b])	Wrapper for <i>spptrs</i> .

continues on next page

Table 103 – continued from previous page

<i>dpptrs</i> (n,ap,b,[lower,overwrite_b])	Wrapper for <i>dpptrs</i> .
<i>cpptrs</i> (n,ap,b,[lower,overwrite_b])	Wrapper for <i>cpptrs</i> .
<i>zpptrs</i> (n,ap,b,[lower,overwrite_b])	Wrapper for <i>zpptrs</i> .
<i>sptsv</i> (...)	Wrapper for <i>sptsv</i> .
<i>dptsv</i> (...)	Wrapper for <i>dptsv</i> .
<i>cptsv</i> (...)	Wrapper for <i>cptsv</i> .
<i>zptsv</i> (...)	Wrapper for <i>zptsv</i> .
<i>sptsvx</i> (d,e,b,[fact,df,ef])	Wrapper for <i>sptsvx</i> .
<i>dptsvx</i> (d,e,b,[fact,df,ef])	Wrapper for <i>dptsvx</i> .
<i>cptsvx</i> (d,e,b,[fact,df,ef])	Wrapper for <i>cptsvx</i> .
<i>zptsvx</i> (d,e,b,[fact,df,ef])	Wrapper for <i>zptsvx</i> .
<i>spttrf</i> (d,e,[overwrite_d,overwrite_e])	Wrapper for <i>spttrf</i> .
<i>dpttrf</i> (d,e,[overwrite_d,overwrite_e])	Wrapper for <i>dpttrf</i> .
<i>cpttrf</i> (d,e,[overwrite_d,overwrite_e])	Wrapper for <i>cpttrf</i> .
<i>zpttrf</i> (d,e,[overwrite_d,overwrite_e])	Wrapper for <i>zpttrf</i> .
<i>spttrs</i> (d,e,b,[overwrite_b])	Wrapper for <i>spttrs</i> .
<i>dpttrs</i> (d,e,b,[overwrite_b])	Wrapper for <i>dpttrs</i> .
<i>cpttrs</i> (d,e,b,[lower,overwrite_b])	Wrapper for <i>cpttrs</i> .
<i>zpttrs</i> (d,e,b,[lower,overwrite_b])	Wrapper for <i>zpttrs</i> .
<i>spteqr</i> (...)	Wrapper for <i>spteqr</i> .
<i>dpteqr</i> (...)	Wrapper for <i>dpteqr</i> .
<i>cppteqr</i> (...)	Wrapper for <i>cppteqr</i> .
<i>zpteqr</i> (...)	Wrapper for <i>zpteqr</i> .
<i>crot</i> (...)	Wrapper for <i>crot</i> .
<i>zrot</i> (...)	Wrapper for <i>zrot</i> .
<i>ssbev</i> (ab,[compute_v,lower,ldab,overwrite_ab])	Wrapper for <i>ssbev</i> .
<i>dsbev</i> (ab,[compute_v,lower,ldab,overwrite_ab])	Wrapper for <i>dsbev</i> .
<i>ssbevd</i> (...)	Wrapper for <i>ssbevd</i> .
<i>dsbevd</i> (...)	Wrapper for <i>dsbevd</i> .
<i>ssbevz</i> (...)	Wrapper for <i>ssbevz</i> .
<i>dsbevz</i> (...)	Wrapper for <i>dsbevz</i> .
<i>ssfrk</i> (...)	Wrapper for <i>ssfrk</i> .
<i>dsfrk</i> (...)	Wrapper for <i>dsfrk</i> .
<i>sstebz</i> (d,e,range,vl,vu,il,iu,tol,order)	Wrapper for <i>sstebz</i> .
<i>dstebz</i> (d,e,range,vl,vu,il,iu,tol,order)	Wrapper for <i>dstebz</i> .
<i>sstein</i> (d,e,w,iblock,isplit)	Wrapper for <i>sstein</i> .
<i>dstein</i> (d,e,w,iblock,isplit)	Wrapper for <i>dstein</i> .
<i>sstemr</i> (...)	Wrapper for <i>sstemr</i> .
<i>dstemr</i> (...)	Wrapper for <i>dstemr</i> .
<i>sstemr_lwork</i> (...)	Wrapper for <i>sstemr_lwork</i> .
<i>dstemr_lwork</i> (...)	Wrapper for <i>dstemr_lwork</i> .
<i>ssterf</i> (d,e,[overwrite_d,overwrite_e])	Wrapper for <i>ssterf</i> .
<i>dsterf</i> (d,e,[overwrite_d,overwrite_e])	Wrapper for <i>dsterf</i> .
<i>sstev</i> (d,e,[compute_v,overwrite_d,overwrite_e])	Wrapper for <i>sstev</i> .
<i>dstev</i> (d,e,[compute_v,overwrite_d,overwrite_e])	Wrapper for <i>dstev</i> .
<i>ssycon</i> (a,ipiv,anorm,[lower])	Wrapper for <i>ssycon</i> .
<i>dsycon</i> (a,ipiv,anorm,[lower])	Wrapper for <i>dsycon</i> .
<i>csycon</i> (a,ipiv,anorm,[lower])	Wrapper for <i>csycon</i> .
<i>zsycon</i> (a,ipiv,anorm,[lower])	Wrapper for <i>zsycon</i> .
<i>ssyconv</i> (a,ipiv,[lower,way,overwrite_a])	Wrapper for <i>ssyconv</i> .

continues on next page

Table 103 – continued from previous page

<i>dsyconv</i> (a,ipiv,[lower,way,overwrite_a])	Wrapper for <i>dsyconv</i> .
<i>csyconv</i> (a,ipiv,[lower,way,overwrite_a])	Wrapper for <i>csyconv</i> .
<i>zsyconv</i> (a,ipiv,[lower,way,overwrite_a])	Wrapper for <i>zsyconv</i> .
<i>ssyequb</i> (a,[lower])	Wrapper for <i>ssyequb</i> .
<i>dsyequb</i> (a,[lower])	Wrapper for <i>dsyequb</i> .
<i>csyequb</i> (a,[lower])	Wrapper for <i>csyequb</i> .
<i>zsyequb</i> (a,[lower])	Wrapper for <i>zsyequb</i> .
<i>ssyev</i> (a,[compute_v,lower,lwork,overwrite_a])	Wrapper for <i>ssyev</i> .
<i>dsyev</i> (a,[compute_v,lower,lwork,overwrite_a])	Wrapper for <i>dsyev</i> .
<i>ssyev_lwork</i> (n,[lower])	Wrapper for <i>ssyev_lwork</i> .
<i>dsyev_lwork</i> (n,[lower])	Wrapper for <i>dsyev_lwork</i> .
<i>ssyevd</i> (...)	Wrapper for <i>ssyevd</i> .
<i>dsyevd</i> (...)	Wrapper for <i>dsyevd</i> .
<i>ssyevd_lwork</i> (n,[compute_v,lower])	Wrapper for <i>ssyevd_lwork</i> .
<i>dsyevd_lwork</i> (n,[compute_v,lower])	Wrapper for <i>dsyevd_lwork</i> .
<i>ssyevr</i> (...)	Wrapper for <i>ssyevr</i> .
<i>dsyevr</i> (...)	Wrapper for <i>dsyevr</i> .
<i>ssyevr_lwork</i> (n,[lower])	Wrapper for <i>ssyevr_lwork</i> .
<i>dsyevr_lwork</i> (n,[lower])	Wrapper for <i>dsyevr_lwork</i> .
<i>ssyevx</i> (...)	Wrapper for <i>ssyevx</i> .
<i>dsyevx</i> (...)	Wrapper for <i>dsyevx</i> .
<i>ssyevx_lwork</i> (n,[lower])	Wrapper for <i>ssyevx_lwork</i> .
<i>dsyevx_lwork</i> (n,[lower])	Wrapper for <i>dsyevx_lwork</i> .
<i>ssygst</i> (a,b,[itype,lower,overwrite_a])	Wrapper for <i>ssygst</i> .
<i>dsygst</i> (a,b,[itype,lower,overwrite_a])	Wrapper for <i>dsygst</i> .
<i>ssygv</i> (...)	Wrapper for <i>ssygv</i> .
<i>dsygv</i> (...)	Wrapper for <i>dsygv</i> .
<i>ssygv_lwork</i> (n,[uplo])	Wrapper for <i>ssygv_lwork</i> .
<i>dsygv_lwork</i> (n,[uplo])	Wrapper for <i>dsygv_lwork</i> .
<i>ssygvd</i> (...)	Wrapper for <i>ssygvd</i> .
<i>dsygvd</i> (...)	Wrapper for <i>dsygvd</i> .
<i>ssygvx</i> (...)	Wrapper for <i>ssygvx</i> .
<i>dsygvx</i> (...)	Wrapper for <i>dsygvx</i> .
<i>ssygvx_lwork</i> (n,[uplo])	Wrapper for <i>ssygvx_lwork</i> .
<i>dsygvx_lwork</i> (n,[uplo])	Wrapper for <i>dsygvx_lwork</i> .
<i>ssysv</i> (a,b,[lwork,lower,overwrite_a,overwrite_b])	Wrapper for <i>ssysv</i> .
<i>dsysv</i> (a,b,[lwork,lower,overwrite_a,overwrite_b])	Wrapper for <i>dsysv</i> .
<i>csysv</i> (a,b,[lwork,lower,overwrite_a,overwrite_b])	Wrapper for <i>csysv</i> .
<i>zsysv</i> (a,b,[lwork,lower,overwrite_a,overwrite_b])	Wrapper for <i>zsysv</i> .
<i>ssysv_lwork</i> (n,[lower])	Wrapper for <i>ssysv_lwork</i> .
<i>dsysv_lwork</i> (n,[lower])	Wrapper for <i>dsysv_lwork</i> .
<i>csysv_lwork</i> (n,[lower])	Wrapper for <i>csysv_lwork</i> .
<i>zsysv_lwork</i> (n,[lower])	Wrapper for <i>zsysv_lwork</i> .
<i>ssysvx</i> (...)	Wrapper for <i>ssysvx</i> .
<i>dsysvx</i> (...)	Wrapper for <i>dsysvx</i> .
<i>csysvx</i> (...)	Wrapper for <i>csysvx</i> .
<i>zsysvx</i> (...)	Wrapper for <i>zsysvx</i> .
<i>ssysvx_lwork</i> (n,[lower])	Wrapper for <i>ssysvx_lwork</i> .
<i>dsysvx_lwork</i> (n,[lower])	Wrapper for <i>dsysvx_lwork</i> .
<i>csysvx_lwork</i> (n,[lower])	Wrapper for <i>csysvx_lwork</i> .

continues on next page

Table 103 – continued from previous page

<i>zsysvx_lwork</i> (n,[lower])	Wrapper for <i>zsysvx_lwork</i> .
<i>ssytf2</i> (a,[lower,overwrite_a])	Wrapper for <i>ssytf2</i> .
<i>dsytf2</i> (a,[lower,overwrite_a])	Wrapper for <i>dsytf2</i> .
<i>csytf2</i> (a,[lower,overwrite_a])	Wrapper for <i>csytf2</i> .
<i>zsytf2</i> (a,[lower,overwrite_a])	Wrapper for <i>zsytf2</i> .
<i>ssytrd</i> (a,[lower,lwork,overwrite_a])	Wrapper for <i>ssytrd</i> .
<i>dsytrd</i> (a,[lower,lwork,overwrite_a])	Wrapper for <i>dsytrd</i> .
<i>ssytrd_lwork</i> (n,[lower])	Wrapper for <i>ssytrd_lwork</i> .
<i>dsytrd_lwork</i> (n,[lower])	Wrapper for <i>dsytrd_lwork</i> .
<i>ssytrf</i> (a,[lower,lwork,overwrite_a])	Wrapper for <i>ssytrf</i> .
<i>dsytrf</i> (a,[lower,lwork,overwrite_a])	Wrapper for <i>dsytrf</i> .
<i>csytrf</i> (a,[lower,lwork,overwrite_a])	Wrapper for <i>csytrf</i> .
<i>zsytrf</i> (a,[lower,lwork,overwrite_a])	Wrapper for <i>zsytrf</i> .
<i>ssytrf_lwork</i> (n,[lower])	Wrapper for <i>ssytrf_lwork</i> .
<i>dsytrf_lwork</i> (n,[lower])	Wrapper for <i>dsytrf_lwork</i> .
<i>csytrf_lwork</i> (n,[lower])	Wrapper for <i>csytrf_lwork</i> .
<i>zsytrf_lwork</i> (n,[lower])	Wrapper for <i>zsytrf_lwork</i> .
<i>stbtrs</i> (ab,b,[uplo,trans,diag,overwrite_b])	Wrapper for <i>stbtrs</i> .
<i>dtbtrs</i> (ab,b,[uplo,trans,diag,overwrite_b])	Wrapper for <i>dtbtrs</i> .
<i>ctbtrs</i> (ab,b,[uplo,trans,diag,overwrite_b])	Wrapper for <i>ctbtrs</i> .
<i>ztbtrs</i> (ab,b,[uplo,trans,diag,overwrite_b])	Wrapper for <i>ztbtrs</i> .
<i>stfsm</i> (...)	Wrapper for <i>stfsm</i> .
<i>dtfsm</i> (...)	Wrapper for <i>dtfsm</i> .
<i>ctfsm</i> (...)	Wrapper for <i>ctfsm</i> .
<i>ztfsm</i> (...)	Wrapper for <i>ztfsm</i> .
<i>stfttp</i> (n,arf,[transr,uplo])	Wrapper for <i>stfttp</i> .
<i>dtfttp</i> (n,arf,[transr,uplo])	Wrapper for <i>dtfttp</i> .
<i>ctfttp</i> (n,arf,[transr,uplo])	Wrapper for <i>ctfttp</i> .
<i>zftttp</i> (n,arf,[transr,uplo])	Wrapper for <i>zftttp</i> .
<i>stfttr</i> (n,arf,[transr,uplo])	Wrapper for <i>stfttr</i> .
<i>dtfttr</i> (n,arf,[transr,uplo])	Wrapper for <i>dtfttr</i> .
<i>ctfttr</i> (n,arf,[transr,uplo])	Wrapper for <i>ctfttr</i> .
<i>zftttr</i> (n,arf,[transr,uplo])	Wrapper for <i>zftttr</i> .
<i>stgsen</i> (...)	Wrapper for <i>stgsen</i> .
<i>dtgsen</i> (...)	Wrapper for <i>dtgsen</i> .
<i>ctgsen</i> (...)	Wrapper for <i>ctgsen</i> .
<i>ztdgsen</i> (...)	Wrapper for <i>ztdgsen</i> .
<i>stpttf</i> (n,ap,[transr,uplo])	Wrapper for <i>stpttf</i> .
<i>dtpttf</i> (n,ap,[transr,uplo])	Wrapper for <i>dtpttf</i> .
<i>ctpttf</i> (n,ap,[transr,uplo])	Wrapper for <i>ctpttf</i> .
<i>ztdpttf</i> (n,ap,[transr,uplo])	Wrapper for <i>ztdpttf</i> .
<i>stpttr</i> (n,ap,[uplo])	Wrapper for <i>stpttr</i> .
<i>dtpttr</i> (n,ap,[uplo])	Wrapper for <i>dtpttr</i> .
<i>ctpttr</i> (n,ap,[uplo])	Wrapper for <i>ctpttr</i> .
<i>ztdpttr</i> (n,ap,[uplo])	Wrapper for <i>ztdpttr</i> .
<i>strsyl</i> (a,b,c,[trana,tranb,isgn,overwrite_c])	Wrapper for <i>strsyl</i> .
<i>dtrsyl</i> (a,b,c,[trana,tranb,isgn,overwrite_c])	Wrapper for <i>dtrsyl</i> .
<i>ctrsyl</i> (a,b,c,[trana,tranb,isgn,overwrite_c])	Wrapper for <i>ctrsyl</i> .
<i>ztrrsyl</i> (a,b,c,[trana,tranb,isgn,overwrite_c])	Wrapper for <i>ztrrsyl</i> .
<i>strtri</i> (c,[lower,unitdiag,overwrite_c])	Wrapper for <i>strtri</i> .

continues on next page

Table 103 – continued from previous page

<i>dtrtri</i> (c,[lower,unitdiag,overwrite_c])	Wrapper for <i>dtrtri</i> .
<i>ctrtri</i> (c,[lower,unitdiag,overwrite_c])	Wrapper for <i>ctrtri</i> .
<i>ztrtri</i> (c,[lower,unitdiag,overwrite_c])	Wrapper for <i>ztrtri</i> .
<i>strtrs</i> (...)	Wrapper for <i>strtrs</i> .
<i>dtrtrs</i> (...)	Wrapper for <i>dtrtrs</i> .
<i>ctrtrs</i> (...)	Wrapper for <i>ctrtrs</i> .
<i>ztrtrs</i> (...)	Wrapper for <i>ztrtrs</i> .
<i>strttf</i> (a,[transr,uplo])	Wrapper for <i>strttf</i> .
<i>dtrttf</i> (a,[transr,uplo])	Wrapper for <i>dtrttf</i> .
<i>ctrttf</i> (a,[transr,uplo])	Wrapper for <i>ctrttf</i> .
<i>ztrttf</i> (a,[transr,uplo])	Wrapper for <i>ztrttf</i> .
<i>strttp</i> (a,[uplo])	Wrapper for <i>strttp</i> .
<i>dtrttp</i> (a,[uplo])	Wrapper for <i>dtrttp</i> .
<i>ctrttp</i> (a,[uplo])	Wrapper for <i>ctrttp</i> .
<i>ztrttp</i> (a,[uplo])	Wrapper for <i>ztrttp</i> .
<i>stzrzf</i> (a,[lwork,overwrite_a])	Wrapper for <i>stzrzf</i> .
<i>dtzrzf</i> (a,[lwork,overwrite_a])	Wrapper for <i>dtzrzf</i> .
<i>ctzrzf</i> (a,[lwork,overwrite_a])	Wrapper for <i>ctzrzf</i> .
<i>ztzrzf</i> (a,[lwork,overwrite_a])	Wrapper for <i>ztzrzf</i> .
<i>stzrzf_lwork</i> (m,n)	Wrapper for <i>stzrzf_lwork</i> .
<i>dtzrzf_lwork</i> (m,n)	Wrapper for <i>dtzrzf_lwork</i> .
<i>ctzrzf_lwork</i> (m,n)	Wrapper for <i>ctzrzf_lwork</i> .
<i>ztzrzf_lwork</i> (m,n)	Wrapper for <i>ztzrzf_lwork</i> .
<i>cunghr</i> (a,tau,[lo,hi,lwork,overwrite_a])	Wrapper for <i>cunghr</i> .
<i>zunghr</i> (a,tau,[lo,hi,lwork,overwrite_a])	Wrapper for <i>zunghr</i> .
<i>cunghr_lwork</i> (n,[lo,hi])	Wrapper for <i>cunghr_lwork</i> .
<i>zunghr_lwork</i> (n,[lo,hi])	Wrapper for <i>zunghr_lwork</i> .
<i>cungqr</i> (a,tau,[lwork,overwrite_a])	Wrapper for <i>cungqr</i> .
<i>zungqr</i> (a,tau,[lwork,overwrite_a])	Wrapper for <i>zungqr</i> .
<i>cungrq</i> (a,tau,[lwork,overwrite_a])	Wrapper for <i>cungrq</i> .
<i>zungrq</i> (a,tau,[lwork,overwrite_a])	Wrapper for <i>zungrq</i> .
<i>cunmqr</i> (side,trans,a,tau,c,lwork,[overwrite_c])	Wrapper for <i>cunmqr</i> .
<i>zunmqr</i> (side,trans,a,tau,c,lwork,[overwrite_c])	Wrapper for <i>zunmqr</i> .
<i>sgeqrt</i> (nb,a,[overwrite_a])	Wrapper for <i>sgeqrt</i> .
<i>dgeqrt</i> (nb,a,[overwrite_a])	Wrapper for <i>dgeqrt</i> .
<i>cgeqrt</i> (nb,a,[overwrite_a])	Wrapper for <i>cgeqrt</i> .
<i>zgeqrt</i> (nb,a,[overwrite_a])	Wrapper for <i>zgeqrt</i> .
<i>sgemqrt</i> (v,t,c,[side,trans,overwrite_c])	Wrapper for <i>sgemqrt</i> .
<i>dgemqrt</i> (v,t,c,[side,trans,overwrite_c])	Wrapper for <i>dgemqrt</i> .
<i>cgemqrt</i> (v,t,c,[side,trans,overwrite_c])	Wrapper for <i>cgemqrt</i> .
<i>zgemqrt</i> (v,t,c,[side,trans,overwrite_c])	Wrapper for <i>zgemqrt</i> .
<i>sgttrf</i> (...)	Wrapper for <i>sgttrf</i> .
<i>dgttrf</i> (...)	Wrapper for <i>dgttrf</i> .
<i>cgttrf</i> (...)	Wrapper for <i>cgttrf</i> .
<i>zgttrf</i> (...)	Wrapper for <i>zgttrf</i> .
<i>sgttrs</i> (dl,d,du,du2,ipiv,b,[trans,overwrite_b])	Wrapper for <i>sgttrs</i> .
<i>dgttrs</i> (dl,d,du,du2,ipiv,b,[trans,overwrite_b])	Wrapper for <i>dgttrs</i> .
<i>cgttrs</i> (dl,d,du,du2,ipiv,b,[trans,overwrite_b])	Wrapper for <i>cgttrs</i> .
<i>zgttrs</i> (dl,d,du,du2,ipiv,b,[trans,overwrite_b])	Wrapper for <i>zgttrs</i> .
<i>stpqrt</i> (l,nb,a,b,[overwrite_a,overwrite_b])	Wrapper for <i>stpqrt</i> .

continues on next page

Table 103 – continued from previous page

<code>dtppqrt(l,nb,a,b,[overwrite_a,overwrite_b])</code>	Wrapper for <code>dtppqrt</code> .
<code>ctppqrt(l,nb,a,b,[overwrite_a,overwrite_b])</code>	Wrapper for <code>ctppqrt</code> .
<code>ztpqrt(l,nb,a,b,[overwrite_a,overwrite_b])</code>	Wrapper for <code>ztpqrt</code> .
<code>stppmqrt(...)</code>	Wrapper for <code>stppmqrt</code> .
<code>dtpmqrt(...)</code>	Wrapper for <code>dtpmqrt</code> .
<code>ctpmqrt(...)</code>	Wrapper for <code>ctpmqrt</code> .
<code>ztpmqrt(...)</code>	Wrapper for <code>ztpmqrt</code> .
<code>cuncsd(...)</code>	Wrapper for <code>cuncsd</code> .
<code>zuncsd(...)</code>	Wrapper for <code>zuncsd</code> .
<code>cuncsd_lwork(m,p,q)</code>	Wrapper for <code>cuncsd_lwork</code> .
<code>zuncsd_lwork(m,p,q)</code>	Wrapper for <code>zuncsd_lwork</code> .
<code>cunmrz(a,tau,c,[side,trans,lwork,overwrite_c])</code>	Wrapper for <code>cunmrz</code> .
<code>zunmrz(a,tau,c,[side,trans,lwork,overwrite_c])</code>	Wrapper for <code>zunmrz</code> .
<code>cunmrz_lwork(m,n,[side,trans])</code>	Wrapper for <code>cunmrz_lwork</code> .
<code>zunmrz_lwork(m,n,[side,trans])</code>	Wrapper for <code>zunmrz_lwork</code> .
<code>ilaver()</code>	Wrapper for <code>ilaver</code> .

scipy.linalg.lapack.sgbsv

`scipy.linalg.lapack.sgbsv(kl, ku, ab, b[, overwrite_ab, overwrite_b]) = <fortran object>`
 Wrapper for `sgbsv`.

Parameters

kl [input int]
ku [input int]
ab [input rank-2 array('f') with bounds (2*kl+ku+1,n)]
b [input rank-2 array('f') with bounds (n,nrhs)]

Returns

lub [rank-2 array('f') with bounds (2*kl+ku+1,n) and ab storage]
piv [rank-1 array('i') with bounds (n)]
x [rank-2 array('f') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_ab
 [input int, optional] Default: 0
overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.dgbsv

`scipy.linalg.lapack.dgbsv(kl, ku, ab, b[, overwrite_ab, overwrite_b]) = <fortran object>`
 Wrapper for `dgbsv`.

Parameters

kl [input int]
ku [input int]
ab [input rank-2 array('d') with bounds (2*kl+ku+1,n)]
b [input rank-2 array('d') with bounds (n,nrhs)]

Returns

lub [rank-2 array('d') with bounds (2*kl+ku+1,n) and ab storage]
piv [rank-1 array('i') with bounds (n)]
x [rank-2 array('d') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_ab
[input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.cgbsv

`scipy.linalg.lapack.cgbsv(kl, ku, ab, b[, overwrite_ab, overwrite_b]) = <fortran object>`
Wrapper for cgbsv.

Parameters

kl [input int]
ku [input int]
ab [input rank-2 array('F') with bounds (2*kl+ku+1,n)]
b [input rank-2 array('F') with bounds (n,nrhs)]

Returns

lub [rank-2 array('F') with bounds (2*kl+ku+1,n) and ab storage]
piv [rank-1 array('i') with bounds (n)]
x [rank-2 array('F') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_ab
[input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.zgbsv

`scipy.linalg.lapack.zgbsv(kl, ku, ab, b[, overwrite_ab, overwrite_b]) = <fortran object>`
Wrapper for zgbsv.

Parameters

kl [input int]
ku [input int]
ab [input rank-2 array('D') with bounds (2*kl+ku+1,n)]
b [input rank-2 array('D') with bounds (n,nrhs)]

Returns

lub [rank-2 array('D') with bounds (2*kl+ku+1,n) and ab storage]
piv [rank-1 array('i') with bounds (n)]
x [rank-2 array('D') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_ab
 [input int, optional] Default: 0

overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.sgbtrf

`scipy.linalg.lapack.sgbtrf(ab, kl, ku[, m, n, ldab, overwrite_ab]) = <fortran object>`
 Wrapper for sgbtrf.

Parameters

ab [input rank-2 array('f') with bounds (ldab,n)]

kl [input int]

ku [input int]

Returns

lu [rank-2 array('f') with bounds (ldab,n) and ab storage]

ipiv [rank-1 array('i') with bounds (MIN(m,n))]

info [int]

Other Parameters

m [input int, optional] Default: shape(ab,1)

n [input int, optional] Default: shape(ab,1)

overwrite_ab
 [input int, optional] Default: 0

ldab [input int, optional] Default: max(shape(ab,0),1)

scipy.linalg.lapack.dgbtrf

`scipy.linalg.lapack.dgbtrf(ab, kl, ku[, m, n, ldab, overwrite_ab]) = <fortran object>`
 Wrapper for dgbtrf.

Parameters

ab [input rank-2 array('d') with bounds (ldab,n)]

kl [input int]

ku [input int]

Returns

lu [rank-2 array('d') with bounds (ldab,n) and ab storage]

ipiv [rank-1 array('i') with bounds (MIN(m,n))]

info [int]

Other Parameters

m [input int, optional] Default: shape(ab,1)

n [input int, optional] Default: shape(ab,1)

overwrite_ab
 [input int, optional] Default: 0

ldab [input int, optional] Default: max(shape(ab,0),1)

scipy.linalg.lapack.cgbtrf

`scipy.linalg.lapack.cgbtrf(ab, kl, ku[, m, n, ldab, overwrite_ab]) = <fortran object>`
 Wrapper for `cgbtrf`.

Parameters

ab [input rank-2 array('F') with bounds (ldab,n)]
kl [input int]
ku [input int]

Returns

lu [rank-2 array('F') with bounds (ldab,n) and ab storage]
ipiv [rank-1 array('i') with bounds (MIN(m,n))]
info [int]

Other Parameters

m [input int, optional] Default: `shape(ab,1)`
n [input int, optional] Default: `shape(ab,1)`
overwrite_ab [input int, optional] Default: 0
ldab [input int, optional] Default: `max(shape(ab,0),1)`

scipy.linalg.lapack.zgbtrf

`scipy.linalg.lapack.zgbtrf(ab, kl, ku[, m, n, ldab, overwrite_ab]) = <fortran object>`
 Wrapper for `zgbtrf`.

Parameters

ab [input rank-2 array('D') with bounds (ldab,n)]
kl [input int]
ku [input int]

Returns

lu [rank-2 array('D') with bounds (ldab,n) and ab storage]
ipiv [rank-1 array('i') with bounds (MIN(m,n))]
info [int]

Other Parameters

m [input int, optional] Default: `shape(ab,1)`
n [input int, optional] Default: `shape(ab,1)`
overwrite_ab [input int, optional] Default: 0
ldab [input int, optional] Default: `max(shape(ab,0),1)`

scipy.linalg.lapack.sgbtrs

`scipy.linalg.lapack.sgbtrs` (*ab, kl, ku, b, ipiv*[, *trans, n, ldab, ldb, overwrite_b*]) = **<fortran object>**

Wrapper for `sgbtrs`.

Parameters

ab [input rank-2 array('f') with bounds (ldab,n)]
kl [input int]
ku [input int]
b [input rank-2 array('f') with bounds (ldb,nrhs)]
ipiv [input rank-1 array('i') with bounds (n)]

Returns

x [rank-2 array('f') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

overwrite_b [input int, optional] Default: 0
trans [input int, optional] Default: 0
n [input int, optional] Default: shape(ab,1)
ldab [input int, optional] Default: shape(ab,0)
ldb [input int, optional] Default: shape(b,0)

scipy.linalg.lapack.dgbtrs

`scipy.linalg.lapack.dgbtrs` (*ab, kl, ku, b, ipiv*[, *trans, n, ldab, ldb, overwrite_b*]) = **<fortran object>**

Wrapper for `dgbtrs`.

Parameters

ab [input rank-2 array('d') with bounds (ldab,n)]
kl [input int]
ku [input int]
b [input rank-2 array('d') with bounds (ldb,nrhs)]
ipiv [input rank-1 array('i') with bounds (n)]

Returns

x [rank-2 array('d') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

overwrite_b [input int, optional] Default: 0
trans [input int, optional] Default: 0
n [input int, optional] Default: shape(ab,1)
ldab [input int, optional] Default: shape(ab,0)
ldb [input int, optional] Default: shape(b,0)

scipy.linalg.lapack.cgbtrs

`scipy.linalg.lapack.cgbtrs` (*ab, kl, ku, b, ipiv*[, *trans, n, ldab, ldb, overwrite_b*]) = **<fortran object>**

Wrapper for `cgbtrs`.

Parameters

ab [input rank-2 array('F') with bounds (ldab,n)]
kl [input int]
ku [input int]
b [input rank-2 array('F') with bounds (ldb,nrhs)]
ipiv [input rank-1 array('i') with bounds (n)]

Returns

x [rank-2 array('F') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

overwrite_b [input int, optional] Default: 0
trans [input int, optional] Default: 0
n [input int, optional] Default: shape(ab,1)
ldab [input int, optional] Default: shape(ab,0)
ldb [input int, optional] Default: shape(b,0)

scipy.linalg.lapack.zgbtrs

`scipy.linalg.lapack.zgbtrs` (*ab, kl, ku, b, ipiv*[, *trans, n, ldab, ldb, overwrite_b*]) = **<fortran object>**

Wrapper for `zgbtrs`.

Parameters

ab [input rank-2 array('D') with bounds (ldab,n)]
kl [input int]
ku [input int]
b [input rank-2 array('D') with bounds (ldb,nrhs)]
ipiv [input rank-1 array('i') with bounds (n)]

Returns

x [rank-2 array('D') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

overwrite_b [input int, optional] Default: 0
trans [input int, optional] Default: 0
n [input int, optional] Default: shape(ab,1)
ldab [input int, optional] Default: shape(ab,0)
ldb [input int, optional] Default: shape(b,0)

scipy.linalg.lapack.sgebal

`scipy.linalg.lapack.sgebal` (a [, *scale*, *permute*, *overwrite_a*]) = <fortran object>
 Wrapper for sgebal.

Parameters

a [input rank-2 array('f') with bounds (m,n)]

Returns

ba [rank-2 array('f') with bounds (m,n) and a storage]

lo [int]

hi [int]

pivscale [rank-1 array('f') with bounds (n)]

info [int]

Other Parameters

scale [input int, optional] Default: 0

permute [input int, optional] Default: 0

overwrite_a
 [input int, optional] Default: 0

scipy.linalg.lapack.dgebal

`scipy.linalg.lapack.dgebal` (a [, *scale*, *permute*, *overwrite_a*]) = <fortran object>
 Wrapper for dgebal.

Parameters

a [input rank-2 array('d') with bounds (m,n)]

Returns

ba [rank-2 array('d') with bounds (m,n) and a storage]

lo [int]

hi [int]

pivscale [rank-1 array('d') with bounds (n)]

info [int]

Other Parameters

scale [input int, optional] Default: 0

permute [input int, optional] Default: 0

overwrite_a
 [input int, optional] Default: 0

scipy.linalg.lapack.cgebal

`scipy.linalg.lapack.cgebal` (a [, *scale*, *permute*, *overwrite_a*]) = <fortran object>
 Wrapper for cgebal.

Parameters

a [input rank-2 array('F') with bounds (m,n)]

Returns

ba [rank-2 array('F') with bounds (m,n) and a storage]

lo [int]
hi [int]
pivscale [rank-1 array('f') with bounds (n)]
info [int]

Other Parameters

scale [input int, optional] Default: 0
permute [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0

scipy.linalg.lapack.zgebal

`scipy.linalg.lapack.zgebal(a[, scale, permute, overwrite_a]) = <fortran object>`
 Wrapper for zgebal.

Parameters

a [input rank-2 array('D') with bounds (m,n)]

Returns

ba [rank-2 array('D') with bounds (m,n) and a storage]
lo [int]
hi [int]
pivscale [rank-1 array('d') with bounds (n)]
info [int]

Other Parameters

scale [input int, optional] Default: 0
permute [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0

scipy.linalg.lapack.sgecon

`scipy.linalg.lapack.sgecon(a, anorm[, norm]) = <fortran object>`
 Wrapper for sgecon.

Parameters

a [input rank-2 array('f') with bounds (n,n)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

norm [input string(len=1), optional] Default: '1'

scipy.linalg.lapack.dgecon

`scipy.linalg.lapack.dgecon(a, anorm[, norm]) = <fortran object>`
Wrapper for `dgecon`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

norm [input string(len=1), optional] Default: '1'

scipy.linalg.lapack.cgecon

`scipy.linalg.lapack.cgecon(a, anorm[, norm]) = <fortran object>`
Wrapper for `cgecon`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

norm [input string(len=1), optional] Default: '1'

scipy.linalg.lapack.zgecon

`scipy.linalg.lapack.zgecon(a, anorm[, norm]) = <fortran object>`
Wrapper for `zgecon`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

norm [input string(len=1), optional] Default: '1'

scipy.linalg.lapack.sgeequ

`scipy.linalg.lapack.sgeequ(a) = <fortran object>`
 Wrapper for `sgeequ`.

Parameters

a [input rank-2 array('f') with bounds (m,n)]

Returns

r [rank-1 array('f') with bounds (m)]
c [rank-1 array('f') with bounds (n)]
rowcnd [float]
colcnd [float]
amax [float]
info [int]

scipy.linalg.lapack.dgeequ

`scipy.linalg.lapack.dgeequ(a) = <fortran object>`
 Wrapper for `dgeequ`.

Parameters

a [input rank-2 array('d') with bounds (m,n)]

Returns

r [rank-1 array('d') with bounds (m)]
c [rank-1 array('d') with bounds (n)]
rowcnd [float]
colcnd [float]
amax [float]
info [int]

scipy.linalg.lapack.cgeequ

`scipy.linalg.lapack.cgeequ(a) = <fortran object>`
 Wrapper for `cgeequ`.

Parameters

a [input rank-2 array('F') with bounds (m,n)]

Returns

r [rank-1 array('f') with bounds (m)]
c [rank-1 array('f') with bounds (n)]
rowcnd [float]
colcnd [float]
amax [float]
info [int]

scipy.linalg.lapack.zgseequ

`scipy.linalg.lapack.zgseequ(a) = <fortran object>`
Wrapper for zgseequ.

Parameters

a [input rank-2 array('D') with bounds (m,n)]

Returns

r [rank-1 array('d') with bounds (m)]
c [rank-1 array('d') with bounds (n)]
rowcnd [float]
colcnd [float]
amax [float]
info [int]

scipy.linalg.lapack.sgseequb

`scipy.linalg.lapack.sgseequb(a) = <fortran object>`
Wrapper for sgseequb.

Parameters

a [input rank-2 array('f') with bounds (m,n)]

Returns

r [rank-1 array('f') with bounds (m)]
c [rank-1 array('f') with bounds (n)]
rowcnd [float]
colcnd [float]
amax [float]
info [int]

scipy.linalg.lapack.dgseequb

`scipy.linalg.lapack.dgseequb(a) = <fortran object>`
Wrapper for dgseequb.

Parameters

a [input rank-2 array('d') with bounds (m,n)]

Returns

r [rank-1 array('d') with bounds (m)]
c [rank-1 array('d') with bounds (n)]
rowcnd [float]
colcnd [float]
amax [float]
info [int]

scipy.linalg.lapack.cgeequb

`scipy.linalg.lapack.cgeequb(a) = <fortran object>`
 Wrapper for `cgeequb`.

Parameters

a [input rank-2 array('F') with bounds (m,n)]

Returns

r [rank-1 array('f') with bounds (m)]
c [rank-1 array('f') with bounds (n)]
rowcnd [float]
colcnd [float]
amax [float]
info [int]

scipy.linalg.lapack.zgeequb

`scipy.linalg.lapack.zgeequb(a) = <fortran object>`
 Wrapper for `zgeequb`.

Parameters

a [input rank-2 array('D') with bounds (m,n)]

Returns

r [rank-1 array('d') with bounds (m)]
c [rank-1 array('d') with bounds (n)]
rowcnd [float]
colcnd [float]
amax [float]
info [int]

scipy.linalg.lapack.sgees

`scipy.linalg.lapack.sgees(sselect, a[, compute_v, sort_t, lwork, sselect_extra_args, overwrite_a]) = <fortran object>`

Wrapper for `sgees`.

Parameters

sselect [call-back function]
a [input rank-2 array('f') with bounds (n,n)]

Returns

t [rank-2 array('f') with bounds (n,n) and a storage]
sdim [int]
wr [rank-1 array('f') with bounds (n)]
wi [rank-1 array('f') with bounds (n)]
vs [rank-2 array('f') with bounds (ldvs,n)]
work [rank-1 array('f') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

compute_v [input int, optional] Default: 1
sort_t [input int, optional] Default: 0
sselect_extra_args [input tuple, optional] Default: ()
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)

Notes

Call-back functions:

```
def sselect(arg1, arg2): return sselect
Required arguments:
  arg1 : input float
  arg2 : input float
Return objects:
  sselect : int
```

scipy.linalg.lapack.dgees

scipy.linalg.lapack.dgees(*dselect*, *a*[, *compute_v*, *sort_t*, *lwork*, *dselect_extra_args*, *overwrite_a*]) = **<fortran object>**

Wrapper for dgees.

Parameters

dselect [call-back function]
a [input rank-2 array('d') with bounds (n,n)]

Returns

t [rank-2 array('d') with bounds (n,n) and a storage]
sdim [int]
wr [rank-1 array('d') with bounds (n)]
wi [rank-1 array('d') with bounds (n)]
vs [rank-2 array('d') with bounds (ldvs,n)]
work [rank-1 array('d') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

compute_v [input int, optional] Default: 1
sort_t [input int, optional] Default: 0
dselect_extra_args [input tuple, optional] Default: ()
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)

Notes

Call-back functions:

```
def dselect(arg1, arg2): return dselect
Required arguments:
  arg1 : input float
  arg2 : input float
Return objects:
  dselect : int
```

scipy.linalg.lapack.cgees

```
scipy.linalg.lapack.cgees(cselect, a[, compute_v, sort_t, lwork, cselect_extra_args, overwrite_a]) =
    <fortran object>
```

Wrapper for cgees.

Parameters

cselect [call-back function]
a [input rank-2 array('F') with bounds (n,n)]

Returns

t [rank-2 array('F') with bounds (n,n) and a storage]
sdim [int]
w [rank-1 array('F') with bounds (n)]
vs [rank-2 array('F') with bounds (ldvs,n)]
work [rank-1 array('F') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

compute_v [input int, optional] Default: 1
sort_t [input int, optional] Default: 0
cselect_extra_args [input tuple, optional] Default: ()
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)

Notes

Call-back functions:

```
def cselect(arg): return cselect
Required arguments:
  arg : input complex
Return objects:
  cselect : int
```

scipy.linalg.lapack.zgees

`scipy.linalg.lapack.zgees` (`zselect`, `a`[, `compute_v`, `sort_t`, `lwork`, `zselect_extra_args`, `overwrite_a`]) = **<fortran object>**

Wrapper for `zgees`.

Parameters

zselect [call-back function]
a [input rank-2 array('D') with bounds (n,n)]

Returns

t [rank-2 array('D') with bounds (n,n) and a storage]
sdim [int]
w [rank-1 array('D') with bounds (n)]
vs [rank-2 array('D') with bounds (ldvs,n)]
work [rank-1 array('D') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

compute_v [input int, optional] Default: 1
sort_t [input int, optional] Default: 0
zselect_extra_args [input tuple, optional] Default: ()
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)

Notes

Call-back functions:

```
def zselect(arg): return zselect
Required arguments:
  arg : input complex
Return objects:
  zselect : int
```

scipy.linalg.lapack.sgeev

`scipy.linalg.lapack.sgeev` (`a`[, `compute_vl`, `compute_vr`, `lwork`, `overwrite_a`]) = **<fortran object>**

Wrapper for `sgeev`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]

Returns

wr [rank-1 array('f') with bounds (n)]
wi [rank-1 array('f') with bounds (n)]
vl [rank-2 array('f') with bounds (ldvl,n)]
vr [rank-2 array('f') with bounds (ldvr,n)]

info [int]

Other Parameters

compute_vl
[input int, optional] Default: 1

compute_vr
[input int, optional] Default: 1

overwrite_a
[input int, optional] Default: 0

lwork [input int, optional] Default: $\max(4*n, 1)$

scipy.linalg.lapack.dgeev

`scipy.linalg.lapack.dgeev(a[, compute_vl, compute_vr, lwork, overwrite_a]) = <fortran object>`

Wrapper for `dgeev`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]

Returns

wr [rank-1 array('d') with bounds (n)]

wi [rank-1 array('d') with bounds (n)]

vl [rank-2 array('d') with bounds (ldvl,n)]

vr [rank-2 array('d') with bounds (ldvr,n)]

info [int]

Other Parameters

compute_vl
[input int, optional] Default: 1

compute_vr
[input int, optional] Default: 1

overwrite_a
[input int, optional] Default: 0

lwork [input int, optional] Default: $\max(4*n, 1)$

scipy.linalg.lapack.cgeev

`scipy.linalg.lapack.cgeev(a[, compute_vl, compute_vr, lwork, overwrite_a]) = <fortran object>`

Wrapper for `cgeev`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]

Returns

w [rank-1 array('F') with bounds (n)]

vl [rank-2 array('F') with bounds (ldvl,n)]

vr [rank-2 array('F') with bounds (ldvr,n)]

info [int]

Other Parameters

compute_vl [input int, optional] Default: 1
compute_vr [input int, optional] Default: 1
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(2*n,1)

scipy.linalg.lapack.zgeev

scipy.linalg.lapack.**zgeev** (*a*[, *compute_vl*, *compute_vr*, *lwork*, *overwrite_a*]) = <fortran object>

Wrapper for zgeev.

Parameters

a [input rank-2 array('D') with bounds (n,n)]

Returns

w [rank-1 array('D') with bounds (n)]
vl [rank-2 array('D') with bounds (ldvl,n)]
vr [rank-2 array('D') with bounds (ldvr,n)]
info [int]

Other Parameters

compute_vl [input int, optional] Default: 1
compute_vr [input int, optional] Default: 1
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(2*n,1)

scipy.linalg.lapack.sgeev_lwork

scipy.linalg.lapack.**sgeev_lwork** (*n*[, *compute_vl*, *compute_vr*]) = <fortran object>

Wrapper for sgeev_lwork.

Parameters

n [input int]

Returns

work [float]
info [int]

Other Parameters

compute_vl [input int, optional] Default: 1
compute_vr [input int, optional] Default: 1

scipy.linalg.lapack.dgeev_lwork

`scipy.linalg.lapack.dgeev_lwork` (n [, *compute_vl*, *compute_vr*]) = <fortran object>
 Wrapper for `dgeev_lwork`.

Parameters

n [input int]

Returns

work [float]

info [int]

Other Parameters

compute_vl
 [input int, optional] Default: 1

compute_vr
 [input int, optional] Default: 1

scipy.linalg.lapack.cgeev_lwork

`scipy.linalg.lapack.cgeev_lwork` (n [, *compute_vl*, *compute_vr*]) = <fortran object>
 Wrapper for `cgeev_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

compute_vl
 [input int, optional] Default: 1

compute_vr
 [input int, optional] Default: 1

scipy.linalg.lapack.zgeev_lwork

`scipy.linalg.lapack.zgeev_lwork` (n [, *compute_vl*, *compute_vr*]) = <fortran object>
 Wrapper for `zgeev_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

compute_vl
 [input int, optional] Default: 1

compute_vr
 [input int, optional] Default: 1

scipy.linalg.lapack.sgegv

`scipy.linalg.lapack.sgegv(*args, **kwargs)`

sgegv is deprecated! The *gegv* family of routines has been deprecated in LAPACK 3.6.0 in favor of the *ggev* family of routines. The corresponding wrappers will be removed from SciPy in a future release.

`alphar, alphai, beta, vl, vr, info = sgegv(a, b, [compute_vl, compute_vr, lwork, overwrite_a, overwrite_b])`

Wrapper for *sgegv*.

Parameters

a [input rank-2 array('f') with bounds (n,n)]
b [input rank-2 array('f') with bounds (n,n)]

Returns

alphar [rank-1 array('f') with bounds (n)]
alphai [rank-1 array('f') with bounds (n)]
beta [rank-1 array('f') with bounds (n)]
vl [rank-2 array('f') with bounds (ldvl,n)]
vr [rank-2 array('f') with bounds (ldvr,n)]
info [int]

Other Parameters

compute_vl
 [input int, optional] Default: 1
compute_vr
 [input int, optional] Default: 1
overwrite_a
 [input int, optional] Default: 0
overwrite_b
 [input int, optional] Default: 0
lwork
 [input int, optional] Default: max(8*n,1)

scipy.linalg.lapack.dgegv

`scipy.linalg.lapack.dgegv(*args, **kwargs)`

dgegv is deprecated! The *gegv* family of routines has been deprecated in LAPACK 3.6.0 in favor of the *ggev* family of routines. The corresponding wrappers will be removed from SciPy in a future release.

`alphar, alphai, beta, vl, vr, info = dgegv(a, b, [compute_vl, compute_vr, lwork, overwrite_a, overwrite_b])`

Wrapper for *dgegv*.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
b [input rank-2 array('d') with bounds (n,n)]

Returns

alphar [rank-1 array('d') with bounds (n)]
alphai [rank-1 array('d') with bounds (n)]
beta [rank-1 array('d') with bounds (n)]

vl [rank-2 array('d') with bounds (ldv1,n)]
vr [rank-2 array('d') with bounds (ldvr,n)]
info [int]

Other Parameters

compute_vl
[input int, optional] Default: 1
compute_vr
[input int, optional] Default: 1
overwrite_a
[input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0
lwork [input int, optional] Default: max(8*n,1)

scipy.linalg.lapack.cgegv

`scipy.linalg.lapack.cgegv` (*args, **kws)

cgegv is deprecated! The **gegv* family of routines has been deprecated in LAPACK 3.6.0 in favor of the **ggeev* family of routines. The corresponding wrappers will be removed from SciPy in a future release.

alpha,beta,vl,vr,info = cgegv(a,b,[compute_vl,compute_vr,lwork,overwrite_a,overwrite_b])

Wrapper for *cgegv*.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
b [input rank-2 array('F') with bounds (n,n)]

Returns

alpha [rank-1 array('F') with bounds (n)]
beta [rank-1 array('F') with bounds (n)]
vl [rank-2 array('F') with bounds (ldv1,n)]
vr [rank-2 array('F') with bounds (ldvr,n)]
info [int]

Other Parameters

compute_vl
[input int, optional] Default: 1
compute_vr
[input int, optional] Default: 1
overwrite_a
[input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0
lwork [input int, optional] Default: max(2*n,1)

scipy.linalg.lapack.zgegv`scipy.linalg.lapack.zgegv(*args, **kws)`

zgegv is deprecated! The **gegv* family of routines has been deprecated in LAPACK 3.6.0 in favor of the **ggev* family of routines. The corresponding wrappers will be removed from SciPy in a future release.

`alpha,beta,vl,vr,info = zgegv(a,b,[compute_vl,compute_vr,lwork,overwrite_a,overwrite_b])`

Wrapper for *zgegv*.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (n,n)]

Returns

alpha [rank-1 array('D') with bounds (n)]
beta [rank-1 array('D') with bounds (n)]
vl [rank-2 array('D') with bounds (ldvl,n)]
vr [rank-2 array('D') with bounds (ldvr,n)]
info [int]

Other Parameters

compute_vl [input int, optional] Default: 1
compute_vr [input int, optional] Default: 1
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(2*n,1)

scipy.linalg.lapack.sgehrd`scipy.linalg.lapack.sgehrd(a[, lo, hi, lwork, overwrite_a]) = <fortran object>`

Wrapper for *sgehrd*.

Parameters

a [input rank-2 array('f') with bounds (n,n)]

Returns

ht [rank-2 array('f') with bounds (n,n) and a storage]
tau [rank-1 array('f') with bounds (n - 1)]
info [int]

Other Parameters

lo [input int, optional] Default: 0
hi [input int, optional] Default: n-1
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: MAX(n,1)

scipy.linalg.lapack.dgehrd

`scipy.linalg.lapack.dgehrd(a[, lo, hi, lwork, overwrite_a]) = <fortran object>`
 Wrapper for dgehrd.

Parameters

a [input rank-2 array('d') with bounds (n,n)]

Returns

ht [rank-2 array('d') with bounds (n,n) and a storage]

tau [rank-1 array('d') with bounds (n - 1)]

info [int]

Other Parameters

lo [input int, optional] Default: 0

hi [input int, optional] Default: n-1

overwrite_a [input int, optional] Default: 0

lwork [input int, optional] Default: MAX(n,1)

scipy.linalg.lapack.cgehrd

`scipy.linalg.lapack.cgehrd(a[, lo, hi, lwork, overwrite_a]) = <fortran object>`
 Wrapper for cgehrd.

Parameters

a [input rank-2 array('F') with bounds (n,n)]

Returns

ht [rank-2 array('F') with bounds (n,n) and a storage]

tau [rank-1 array('F') with bounds (n - 1)]

info [int]

Other Parameters

lo [input int, optional] Default: 0

hi [input int, optional] Default: n-1

overwrite_a [input int, optional] Default: 0

lwork [input int, optional] Default: MAX(n,1)

scipy.linalg.lapack.zgehrd

`scipy.linalg.lapack.zgehrd(a[, lo, hi, lwork, overwrite_a]) = <fortran object>`
 Wrapper for zgehrd.

Parameters

a [input rank-2 array('D') with bounds (n,n)]

Returns

ht [rank-2 array('D') with bounds (n,n) and a storage]

tau [rank-1 array('D') with bounds (n - 1)]

info [int]

Other Parameters

lo [input int, optional] Default: 0
hi [input int, optional] Default: n-1
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: MAX(n,1)

scipy.linalg.lapack.sgehrd_lwork

`scipy.linalg.lapack.sgehrd_lwork(n[, lo, hi]) = <fortran object>`
 Wrapper for `sgehrd_lwork`.

Parameters

n [input int]

Returns

work [float]
info [int]

Other Parameters

lo [input int, optional] Default: 0
hi [input int, optional] Default: n-1

scipy.linalg.lapack.dgehrd_lwork

`scipy.linalg.lapack.dgehrd_lwork(n[, lo, hi]) = <fortran object>`
 Wrapper for `dgehrd_lwork`.

Parameters

n [input int]

Returns

work [float]
info [int]

Other Parameters

lo [input int, optional] Default: 0
hi [input int, optional] Default: n-1

scipy.linalg.lapack.cgehrd_lwork

`scipy.linalg.lapack.cgehrd_lwork(n[, lo, hi]) = <fortran object>`
 Wrapper for `cgehrd_lwork`.

Parameters

n [input int]

Returns

work [complex]
info [int]

Other Parameters

lo [input int, optional] Default: 0
hi [input int, optional] Default: n-1

scipy.linalg.lapack.zgehrd_lwork

`scipy.linalg.lapack.zgehrd_lwork(n[, lo, hi]) = <fortran object>`
 Wrapper for `zgehrd_lwork`.

Parameters

n [input int]

Returns

work [complex]
info [int]

Other Parameters

lo [input int, optional] Default: 0
hi [input int, optional] Default: n-1

scipy.linalg.lapack.sgejsv

`scipy.linalg.lapack.sgejsv(a[, joba, jobu, jobv, jobr, jobt, jobp, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `sgejsv`.

Parameters

a [input rank-2 array('f') with bounds (lda,n)]

Returns

sva [rank-1 array('f') with bounds (n)]
u [rank-2 array('f') with bounds (((jobt == 0)&&(jobu == 3)?0:m),((jobt == 0)&&(jobu == 3)?0:(jobu == 1?m:n)))]
v [rank-2 array('f') with bounds (((jobv == 0)&&(jobv == 3)?0:ldv),((jobt == 0)&&(jobv == 3)?0:n))]
workout [rank-1 array('f') with bounds (7)]
iworkout [rank-1 array('i') with bounds (3)]
info [int]

Other Parameters

joba [input int, optional] Default: 4
jobu [input int, optional] Default: 0
jobv [input int, optional] Default: 0
jobr [input int, optional] Default: 1
jobt [input int, optional] Default: 0
jobp [input int, optional] Default: 1
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: $\max(6*n+2*n*n, \max(2*m+n, \max(4*n+n*n, \max(2*n+n*n+6, 7))))$

scipy.linalg.lapack.dgejsv

`scipy.linalg.lapack.dgejsv(a[, joba, jobu, jobv, jobr, jobt, jobp, lwork, overwrite_a]) = <fortran object>`

Wrapper for `dgejsv`.

Parameters

a [input rank-2 array('d') with bounds (lda,n)]

Returns

sva [rank-1 array('d') with bounds (n)]

u [rank-2 array('d') with bounds (((jobt == 0)&&(jobu == 3)?0:m),((jobt == 0)&&(jobu == 3)?0:(jobu == 1?m:n)))]

v [rank-2 array('d') with bounds (((jobt == 0)&&(jobv == 3)?0:ldv),((jobt == 0)&&(jobv == 3)?0:n))]

workout [rank-1 array('d') with bounds (7)]

iworkout [rank-1 array('i') with bounds (3)]

info [int]

Other Parameters

joba [input int, optional] Default: 4

jobu [input int, optional] Default: 0

jobv [input int, optional] Default: 0

jobr [input int, optional] Default: 1

jobt [input int, optional] Default: 0

jobp [input int, optional] Default: 1

overwrite_a [input int, optional] Default: 0

lwork [input int, optional] Default: $\max(6*n+2*n*n, \max(2*m+n, \max(4*n+n*n, \max(2*n+n*n+6, 7))))$

scipy.linalg.lapack.sgels

`scipy.linalg.lapack.sgels(a, b[, trans, lwork, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `sgels`.

Parameters

a [input rank-2 array('f') with bounds (m,n)]

b [input rank-2 array('f') with bounds (MAX(m,n),nrhs)]

Returns

lqr [rank-2 array('f') with bounds (m,n) and a storage]

x [rank-2 array('f') with bounds (MAX(m,n),nrhs) and b storage]

info [int]

Other Parameters

trans [input string(len=1), optional] Default: 'N'

overwrite_a [input int, optional] Default: 0

overwrite_b [input int, optional] Default: 0

lwork [input int, optional] Default: $\text{MAX}(\text{MIN}(m,n)+\text{MAX}(\text{MIN}(m,n),nrhs),1)$

scipy.linalg.lapack.dgels

`scipy.linalg.lapack.dgels(a, b[, trans, lwork, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for dgels.

Parameters

a [input rank-2 array('d') with bounds (m,n)]
b [input rank-2 array('d') with bounds (MAX(m,n),nrhs)]

Returns

lqr [rank-2 array('d') with bounds (m,n) and a storage]
x [rank-2 array('d') with bounds (MAX(m,n),nrhs) and b storage]
info [int]

Other Parameters

trans [input string(len=1), optional] Default: 'N'
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: MAX(MIN(m,n)+MAX(MIN(m,n),nrhs),1)

scipy.linalg.lapack.cgels

`scipy.linalg.lapack.cgels(a, b[, trans, lwork, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for cgels.

Parameters

a [input rank-2 array('F') with bounds (m,n)]
b [input rank-2 array('F') with bounds (MAX(m,n),nrhs)]

Returns

lqr [rank-2 array('F') with bounds (m,n) and a storage]
x [rank-2 array('F') with bounds (MAX(m,n),nrhs) and b storage]
info [int]

Other Parameters

trans [input string(len=1), optional] Default: 'N'
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: MAX(MIN(m,n)+MAX(MIN(m,n),nrhs),1)

scipy.linalg.lapack.zgels

`scipy.linalg.lapack.zgels(a, b[, trans, lwork, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for zgels.

Parameters

a [input rank-2 array('D') with bounds (m,n)]
b [input rank-2 array('D') with bounds (MAX(m,n),nrhs)]

Returns

lqr [rank-2 array('D') with bounds (m,n) and a storage]
x [rank-2 array('D') with bounds (MAX(m,n),nrhs) and b storage]
info [int]

Other Parameters

trans [input string(len=1), optional] Default: 'N'
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: MAX(MIN(m,n)+MAX(MIN(m,n),nrhs),1)

scipy.linalg.lapack.sgels_lwork

`scipy.linalg.lapack.sgels_lwork(m, n, nrhs[, trans]) = <fortran object>`

Wrapper for sgels_lwork.

Parameters

m [input int]
n [input int]
nrhs [input int]

Returns

work [float]
info [int]

Other Parameters

trans [input string(len=1), optional] Default: 'N'

scipy.linalg.lapack.dgels_lwork

`scipy.linalg.lapack.dgels_lwork(m, n, nrhs[, trans]) = <fortran object>`

Wrapper for dgels_lwork.

Parameters

m [input int]
n [input int]
nrhs [input int]

Returns

work [float]

info [int]

Other Parameters

trans [input string(len=1), optional] Default: 'N'

scipy.linalg.lapack.cgels_lwork

`scipy.linalg.lapack.cgels_lwork(m, n, nrhs[, trans]) = <fortran object>`
 Wrapper for `cgels_lwork`.

Parameters

m [input int]

n [input int]

nrhs [input int]

Returns

work [complex]

info [int]

Other Parameters

trans [input string(len=1), optional] Default: 'N'

scipy.linalg.lapack.zgels_lwork

`scipy.linalg.lapack.zgels_lwork(m, n, nrhs[, trans]) = <fortran object>`
 Wrapper for `zgels_lwork`.

Parameters

m [input int]

n [input int]

nrhs [input int]

Returns

work [complex]

info [int]

Other Parameters

trans [input string(len=1), optional] Default: 'N'

scipy.linalg.lapack.sgelsd

`scipy.linalg.lapack.sgelsd(a, b, lwork, size_iwork[, cond, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `sgelsd`.

Parameters

a [input rank-2 array('f') with bounds (m,n)]

b [input rank-2 array('f') with bounds (maxmn,nrhs)]

lwork [input int]

size_iwork [input int]

Returns

x [rank-2 array('f') with bounds (maxmn,nrhs) and b storage]
s [rank-1 array('f') with bounds (minmn)]
rank [int]
info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0
cond [input float, optional] Default: -1.0

scipy.linalg.lapack.dgelsd

`scipy.linalg.lapack.dgelsd(a, b, lwork, size_iwork[, cond, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for dgelsd.

Parameters

a [input rank-2 array('d') with bounds (m,n)]
b [input rank-2 array('d') with bounds (maxmn,nrhs)]
lwork [input int]
size_iwork [input int]

Returns

x [rank-2 array('d') with bounds (maxmn,nrhs) and b storage]
s [rank-1 array('d') with bounds (minmn)]
rank [int]
info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0
cond [input float, optional] Default: -1.0

scipy.linalg.lapack.cgelsd

`scipy.linalg.lapack.cgelsd(a, b, lwork, size_rwork, size_iwork[, cond, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for cgelsd.

Parameters

a [input rank-2 array('F') with bounds (m,n)]
b [input rank-2 array('F') with bounds (maxmn,nrhs)]
lwork [input int]
size_rwork [input int]
size_iwork [input int]

Returns

x [rank-2 array('F') with bounds (maxmn,nrhs) and b storage]
s [rank-1 array('f') with bounds (minmn)]
rank [int]
info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0
cond [input float, optional] Default: -1.0

scipy.linalg.lapack.zgelsd

`scipy.linalg.lapack.zgelsd(a, b, lwork, size_rwork, size_iwork[, cond, overwrite_a, overwrite_b])`
= <fortran object>

Wrapper for zgelsd.

Parameters

a [input rank-2 array('D') with bounds (m,n)]
b [input rank-2 array('D') with bounds (maxmn,nrhs)]
lwork [input int]
size_rwork
[input int]
size_iwork [input int]

Returns

x [rank-2 array('D') with bounds (maxmn,nrhs) and b storage]
s [rank-1 array('d') with bounds (minmn)]
rank [int]
info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0
cond [input float, optional] Default: -1.0

scipy.linalg.lapack.sgelsd_lwork

`scipy.linalg.lapack.sgelsd_lwork(m, n, nrhs[, cond, lwork])` = <fortran object>

Wrapper for sgelsd_lwork.

Parameters

m [input int]
n [input int]
nrhs [input int]

Returns

work [float]
iwork [int]

info [int]

Other Parameters

cond [input float, optional] Default: -1.0
lwork [input int, optional] Default: -1

scipy.linalg.lapack.dgelsd_lwork

`scipy.linalg.lapack.dgelsd_lwork(m, n, nrhs[, cond, lwork]) = <fortran object>`
 Wrapper for dgelsd_lwork.

Parameters

m [input int]
n [input int]
nrhs [input int]

Returns

work [float]
iwork [int]
info [int]

Other Parameters

cond [input float, optional] Default: -1.0
lwork [input int, optional] Default: -1

scipy.linalg.lapack.cgelsd_lwork

`scipy.linalg.lapack.cgelsd_lwork(m, n, nrhs[, cond, lwork]) = <fortran object>`
 Wrapper for cgelsd_lwork.

Parameters

m [input int]
n [input int]
nrhs [input int]

Returns

work [complex]
rwork [float]
iwork [int]
info [int]

Other Parameters

cond [input float, optional] Default: -1.0
lwork [input int, optional] Default: -1

scipy.linalg.lapack.zgelsd_lwork

`scipy.linalg.lapack.zgelsd_lwork(m, n, nrhs[, cond, lwork]) = <fortran object>`
 Wrapper for `zgelsd_lwork`.

Parameters

m [input int]
n [input int]
nrhs [input int]

Returns

work [complex]
rwork [float]
iwork [int]
info [int]

Other Parameters

cond [input float, optional] Default: -1.0
lwork [input int, optional] Default: -1

scipy.linalg.lapack.sgelss

`scipy.linalg.lapack.sgelss(a, b[, cond, lwork, overwrite_a, overwrite_b]) = <fortran object>`
 Wrapper for `sgelss`.

Parameters

a [input rank-2 array('f') with bounds (m,n)]
b [input rank-2 array('f') with bounds (maxmn,nrhs)]

Returns

v [rank-2 array('f') with bounds (m,n) and a storage]
x [rank-2 array('f') with bounds (maxmn,nrhs) and b storage]
s [rank-1 array('f') with bounds (minmn)]
rank [int]
work [rank-1 array('f') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
cond [input float, optional] Default: -1.0
lwork [input int, optional] Default: $\max(3*\text{minmn} + \text{MAX}(2*\text{minmn}, \text{MAX}(\text{maxmn}, \text{nrhs})), 1)$

scipy.linalg.lapack.dgelss

`scipy.linalg.lapack.dgelss(a, b[, cond, lwork, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `dgelss`.

Parameters

a [input rank-2 array('d') with bounds (m,n)]
b [input rank-2 array('d') with bounds (maxmn,nrhs)]

Returns

v [rank-2 array('d') with bounds (m,n) and a storage]
x [rank-2 array('d') with bounds (maxmn,nrhs) and b storage]
s [rank-1 array('d') with bounds (minmn)]
rank [int]
work [rank-1 array('d') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
cond [input float, optional] Default: -1.0
lwork [input int, optional] Default: $\max(3*\text{minmn} + \text{MAX}(2*\text{minmn}, \text{MAX}(\text{maxmn}, \text{nrhs})), 1)$

scipy.linalg.lapack.cgelss

`scipy.linalg.lapack.cgelss(a, b[, cond, lwork, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `cgelss`.

Parameters

a [input rank-2 array('F') with bounds (m,n)]
b [input rank-2 array('F') with bounds (maxmn,nrhs)]

Returns

v [rank-2 array('F') with bounds (m,n) and a storage]
x [rank-2 array('F') with bounds (maxmn,nrhs) and b storage]
s [rank-1 array('f') with bounds (minmn)]
rank [int]
work [rank-1 array('F') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
cond [input float, optional] Default: -1.0
lwork [input int, optional] Default: $\max(2*\text{minmn} + \text{MAX}(\text{maxmn}, \text{nrhs}), 1)$

scipy.linalg.lapack.zgelss

`scipy.linalg.lapack.zgelss(a, b[, cond, lwork, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `zgelss`.

Parameters

a [input rank-2 array('D') with bounds (m,n)]
b [input rank-2 array('D') with bounds (maxmn,nrhs)]

Returns

v [rank-2 array('D') with bounds (m,n) and a storage]
x [rank-2 array('D') with bounds (maxmn,nrhs) and b storage]
s [rank-1 array('d') with bounds (minmn)]
rank [int]
work [rank-1 array('D') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
cond [input float, optional] Default: -1.0
lwork [input int, optional] Default: $\max(2*\minmn + \text{MAX}(\text{maxmn}, \text{nrhs}), 1)$

scipy.linalg.lapack.sgelss_lwork

`scipy.linalg.lapack.sgelss_lwork(m, n, nrhs[, cond, lwork]) = <fortran object>`

Wrapper for `sgelss_lwork`.

Parameters

m [input int]
n [input int]
nrhs [input int]

Returns

work [float]
info [int]

Other Parameters

cond [input float, optional] Default: -1.0
lwork [input int, optional] Default: -1

scipy.linalg.lapack.dgelss_lwork

`scipy.linalg.lapack.dgelss_lwork(m, n, nrhs[, cond, lwork]) = <fortran object>`
 Wrapper for `dgelss_lwork`.

Parameters

m [input int]
n [input int]
nrhs [input int]

Returns

work [float]
info [int]

Other Parameters

cond [input float, optional] Default: -1.0
lwork [input int, optional] Default: -1

scipy.linalg.lapack.cgelss_lwork

`scipy.linalg.lapack.cgelss_lwork(m, n, nrhs[, cond, lwork]) = <fortran object>`
 Wrapper for `cgelss_lwork`.

Parameters

m [input int]
n [input int]
nrhs [input int]

Returns

work [complex]
info [int]

Other Parameters

cond [input float, optional] Default: -1.0
lwork [input int, optional] Default: -1

scipy.linalg.lapack.zgelss_lwork

`scipy.linalg.lapack.zgelss_lwork(m, n, nrhs[, cond, lwork]) = <fortran object>`
 Wrapper for `zgelss_lwork`.

Parameters

m [input int]
n [input int]
nrhs [input int]

Returns

work [complex]
info [int]

Other Parameters

cond [input float, optional] Default: -1.0

lwork [input int, optional] Default: -1

scipy.linalg.lapack.sgelsy

`scipy.linalg.lapack.sgelsy(a, b, jptv, cond, lwork[, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `sgelsy`.

Parameters

a [input rank-2 array('f') with bounds (m,n)]
b [input rank-2 array('f') with bounds (maxmn,nrhs)]
jptv [input rank-1 array('i') with bounds (n)]
cond [input float]
lwork [input int]

Returns

v [rank-2 array('f') with bounds (m,n) and a storage]
x [rank-2 array('f') with bounds (maxmn,nrhs) and b storage]
j [rank-1 array('i') with bounds (n) and jptv storage]
rank [int]
info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.dgelsy

`scipy.linalg.lapack.dgelsy(a, b, jptv, cond, lwork[, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `dgelsy`.

Parameters

a [input rank-2 array('d') with bounds (m,n)]
b [input rank-2 array('d') with bounds (maxmn,nrhs)]
jptv [input rank-1 array('i') with bounds (n)]
cond [input float]
lwork [input int]

Returns

v [rank-2 array('d') with bounds (m,n) and a storage]
x [rank-2 array('d') with bounds (maxmn,nrhs) and b storage]
j [rank-1 array('i') with bounds (n) and jptv storage]
rank [int]
info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.cgelsy

`scipy.linalg.lapack.cgelsy(a, b, jptv, cond, lwork[, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for cgelsy.

Parameters

a [input rank-2 array('F') with bounds (m,n)]
b [input rank-2 array('F') with bounds (maxmn,nrhs)]
jptv [input rank-1 array('i') with bounds (n)]
cond [input float]
lwork [input int]

Returns

v [rank-2 array('F') with bounds (m,n) and a storage]
x [rank-2 array('F') with bounds (maxmn,nrhs) and b storage]
j [rank-1 array('i') with bounds (n) and jptv storage]
rank [int]
info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0
overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.zgelsy

`scipy.linalg.lapack.zgelsy(a, b, jptv, cond, lwork[, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for zgelsy.

Parameters

a [input rank-2 array('D') with bounds (m,n)]
b [input rank-2 array('D') with bounds (maxmn,nrhs)]
jptv [input rank-1 array('i') with bounds (n)]
cond [input float]
lwork [input int]

Returns

v [rank-2 array('D') with bounds (m,n) and a storage]
x [rank-2 array('D') with bounds (maxmn,nrhs) and b storage]
j [rank-1 array('i') with bounds (n) and jptv storage]
rank [int]
info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.sgelsy_lwork

`scipy.linalg.lapack.sgelsy_lwork(m, n, nrhs, cond[, lwork]) = <fortran object>`
Wrapper for `sgelsy_lwork`.

Parameters

m [input int]
n [input int]
nrhs [input int]
cond [input float]

Returns

work [float]
info [int]

Other Parameters

lwork [input int, optional] Default: -1

scipy.linalg.lapack.dgelsy_lwork

`scipy.linalg.lapack.dgelsy_lwork(m, n, nrhs, cond[, lwork]) = <fortran object>`
Wrapper for `dgelsy_lwork`.

Parameters

m [input int]
n [input int]
nrhs [input int]
cond [input float]

Returns

work [float]
info [int]

Other Parameters

lwork [input int, optional] Default: -1

scipy.linalg.lapack.cgelsy_lwork

`scipy.linalg.lapack.cgelsy_lwork(m, n, nrhs, cond[, lwork]) = <fortran object>`
Wrapper for `cgelsy_lwork`.

Parameters

m [input int]
n [input int]
nrhs [input int]
cond [input float]

Returns

work [complex]
info [int]

Other Parameters

lwork [input int, optional] Default: -1

scipy.linalg.lapack.zgelsy_lwork

`scipy.linalg.lapack.zgelsy_lwork(m, n, nrhs, cond[, lwork]) = <fortran object>`
 Wrapper for zgelsy_lwork.

Parameters

m [input int]
n [input int]
nrhs [input int]
cond [input float]

Returns

work [complex]
info [int]

Other Parameters

lwork [input int, optional] Default: -1

scipy.linalg.lapack.sgeqp3

`scipy.linalg.lapack.sgeqp3(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for sgeqp3.

Parameters

a [input rank-2 array('f') with bounds (m,n)]

Returns

qr [rank-2 array('f') with bounds (m,n) and a storage]
jpvt [rank-1 array('i') with bounds (n)]
tau [rank-1 array('f') with bounds (MIN(m,n))]
work [rank-1 array('f') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*(n+1),1)

scipy.linalg.lapack.dgeqp3

`scipy.linalg.lapack.dgeqp3(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for dgeqp3.

Parameters

a [input rank-2 array('d') with bounds (m,n)]

Returns

qr [rank-2 array('d') with bounds (m,n) and a storage]

jpvt [rank-1 array('i') with bounds (n)]

tau [rank-1 array('d') with bounds (MIN(m,n))]

work [rank-1 array('d') with bounds (MAX(lwork,1))]

info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

lwork [input int, optional] Default: max(3*(n+1),1)

scipy.linalg.lapack.cgeqp3

`scipy.linalg.lapack.cgeqp3(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for cgeqp3.

Parameters

a [input rank-2 array('F') with bounds (m,n)]

Returns

qr [rank-2 array('F') with bounds (m,n) and a storage]

jpvt [rank-1 array('i') with bounds (n)]

tau [rank-1 array('F') with bounds (MIN(m,n))]

work [rank-1 array('F') with bounds (MAX(lwork,1))]

info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

lwork [input int, optional] Default: max(3*(n+1),1)

scipy.linalg.lapack.zgeqp3

`scipy.linalg.lapack.zgeqp3(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for zgeqp3.

Parameters

a [input rank-2 array('D') with bounds (m,n)]

Returns

qr [rank-2 array('D') with bounds (m,n) and a storage]

jpvt [rank-1 array('i') with bounds (n)]

tau [rank-1 array('D') with bounds (MIN(m,n))]

work [rank-1 array('D') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*(n+1),1)

scipy.linalg.lapack.sgeqrf

`scipy.linalg.lapack.sgeqrf(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for sgeqrf.

Parameters

a [input rank-2 array('f') with bounds (m,n)]

Returns

qr [rank-2 array('f') with bounds (m,n) and a storage]
tau [rank-1 array('f') with bounds (MIN(m,n))]
work [rank-1 array('f') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)

scipy.linalg.lapack.dgeqrf

`scipy.linalg.lapack.dgeqrf(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for dgeqrf.

Parameters

a [input rank-2 array('d') with bounds (m,n)]

Returns

qr [rank-2 array('d') with bounds (m,n) and a storage]
tau [rank-1 array('d') with bounds (MIN(m,n))]
work [rank-1 array('d') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)

scipy.linalg.lapack.cgeqrf

`scipy.linalg.lapack.cgeqrf(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `cgeqrf`.

Parameters

a [input rank-2 array('F') with bounds (m,n)]

Returns

qr [rank-2 array('F') with bounds (m,n) and a storage]
tau [rank-1 array('F') with bounds (MIN(m,n))]
work [rank-1 array('F') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)

scipy.linalg.lapack.zgeqrf

`scipy.linalg.lapack.zgeqrf(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `zgeqrf`.

Parameters

a [input rank-2 array('D') with bounds (m,n)]

Returns

qr [rank-2 array('D') with bounds (m,n) and a storage]
tau [rank-1 array('D') with bounds (MIN(m,n))]
work [rank-1 array('D') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)

scipy.linalg.lapack.sgeqrf_lwork

`scipy.linalg.lapack.sgeqrf_lwork(m, n) = <fortran object>`
 Wrapper for `sgeqrf_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [float]
info [int]

scipy.linalg.lapack.dgeqrf_lwork

`scipy.linalg.lapack.dgeqrf_lwork(m, n) = <fortran object>`
 Wrapper for `dgeqrf_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [float]
info [int]

scipy.linalg.lapack.cgeqrf_lwork

`scipy.linalg.lapack.cgeqrf_lwork(m, n) = <fortran object>`
 Wrapper for `cgeqrf_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [complex]
info [int]

scipy.linalg.lapack.zgeqrf_lwork

`scipy.linalg.lapack.zgeqrf_lwork(m, n) = <fortran object>`
 Wrapper for `zgeqrf_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [complex]
info [int]

scipy.linalg.lapack.sgeqrfp

`scipy.linalg.lapack.sgeqrfp(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `sgeqrfp`.

Parameters

a [input rank-2 array('f') with bounds (m,n)]

Returns

qr [rank-2 array('f') with bounds (m,n) and a storage]
tau [rank-1 array('f') with bounds (MIN(m,n))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: MAX(1, n)

scipy.linalg.lapack.dgeqrfp

`scipy.linalg.lapack.dgeqrfp(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for dgeqrfp.

Parameters

a [input rank-2 array('d') with bounds (m,n)]

Returns

qr [rank-2 array('d') with bounds (m,n) and a storage]
tau [rank-1 array('d') with bounds (MIN(m,n))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: MAX(1, n)

scipy.linalg.lapack.cgeqrfp

`scipy.linalg.lapack.cgeqrfp(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for cgeqrfp.

Parameters

a [input rank-2 array('F') with bounds (m,n)]

Returns

qr [rank-2 array('F') with bounds (m,n) and a storage]
tau [rank-1 array('F') with bounds (MIN(m,n))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: MAX(1, n)

scipy.linalg.lapack.zgeqrfp

`scipy.linalg.lapack.zgeqrfp(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `zgeqrfp`.

Parameters

a [input rank-2 array('D') with bounds (m,n)]

Returns

qr [rank-2 array('D') with bounds (m,n) and a storage]

tau [rank-1 array('D') with bounds (MIN(m,n))]

info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0

lwork [input int, optional] Default: MAX(1, n)

scipy.linalg.lapack.sgeqrfp_lwork

`scipy.linalg.lapack.sgeqrfp_lwork(m, n) = <fortran object>`
 Wrapper for `sgeqrfp_lwork`.

Parameters

m [input int]

n [input int]

Returns

work [float]

info [int]

scipy.linalg.lapack.dgeqrfp_lwork

`scipy.linalg.lapack.dgeqrfp_lwork(m, n) = <fortran object>`
 Wrapper for `dgeqrfp_lwork`.

Parameters

m [input int]

n [input int]

Returns

work [float]

info [int]

scipy.linalg.lapack.cgeqrfp_lwork

`scipy.linalg.lapack.cgeqrfp_lwork(m, n) = <fortran object>`
 Wrapper for `cgeqrfp_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [complex]
info [int]

scipy.linalg.lapack.zgeqrfp_lwork

`scipy.linalg.lapack.zgeqrfp_lwork(m, n) = <fortran object>`
 Wrapper for `zgeqrfp_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [complex]
info [int]

scipy.linalg.lapack.sgerqf

`scipy.linalg.lapack.sgerqf(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `sgerqf`.

Parameters

a [input rank-2 array('f') with bounds (m,n)]

Returns

qr [rank-2 array('f') with bounds (m,n) and a storage]
tau [rank-1 array('f') with bounds (MIN(m,n))]
work [rank-1 array('f') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*m,1)

scipy.linalg.lapack.dgerqf

`scipy.linalg.lapack.dgerqf(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `dgerqf`.

Parameters

a [input rank-2 array('d') with bounds (m,n)]

Returns

qr [rank-2 array('d') with bounds (m,n) and a storage]
tau [rank-1 array('d') with bounds (MIN(m,n))]
work [rank-1 array('d') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*m,1)

scipy.linalg.lapack.cgerqf

`scipy.linalg.lapack.cgerqf(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `cgerqf`.

Parameters

a [input rank-2 array('F') with bounds (m,n)]

Returns

qr [rank-2 array('F') with bounds (m,n) and a storage]
tau [rank-1 array('F') with bounds (MIN(m,n))]
work [rank-1 array('F') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*m,1)

scipy.linalg.lapack.zgerqf

`scipy.linalg.lapack.zgerqf(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `zgerqf`.

Parameters

a [input rank-2 array('D') with bounds (m,n)]

Returns

qr [rank-2 array('D') with bounds (m,n) and a storage]
tau [rank-1 array('D') with bounds (MIN(m,n))]
work [rank-1 array('D') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

lwork
[input int, optional] Default: max(3*m,1)

scipy.linalg.lapack.sgesdd

`scipy.linalg.lapack.sgesdd(a[, compute_uv, full_matrices, lwork, overwrite_a]) = <fortran object>`

Wrapper for sgesdd.

Parameters

a
[input rank-2 array('f') with bounds (m,n)]

Returns

u
[rank-2 array('f') with bounds (u0,u1)]

s
[rank-1 array('f') with bounds (minmn)]

vt
[rank-2 array('f') with bounds (vt0,vt1)]

info
[int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

compute_uv
[input int, optional] Default: 1

full_matrices
[input int, optional] Default: 1

lwork
[input int, optional] Default: max((compute_uv?4*minmn*minmn+MAX(m,n)+9*minmn:MAX(14*minmn+

scipy.linalg.lapack.dgesdd

`scipy.linalg.lapack.dgesdd(a[, compute_uv, full_matrices, lwork, overwrite_a]) = <fortran object>`

Wrapper for dgesdd.

Parameters

a
[input rank-2 array('d') with bounds (m,n)]

Returns

u
[rank-2 array('d') with bounds (u0,u1)]

s
[rank-1 array('d') with bounds (minmn)]

vt
[rank-2 array('d') with bounds (vt0,vt1)]

info
[int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

compute_uv
[input int, optional] Default: 1

full_matrices
[input int, optional] Default: 1

lwork
[input int, optional] Default: max((compute_uv?4*minmn*minmn+MAX(m,n)+9*minmn:MAX(14*minmn+

scipy.linalg.lapack.cgesdd

`scipy.linalg.lapack.cgesdd(a[, compute_uv, full_matrices, lwork, overwrite_a]) = <fortran object>`

Wrapper for `cgesdd`.

Parameters

a [input rank-2 array('F') with bounds (m,n)]

Returns

u [rank-2 array('F') with bounds (u0,u1)]

s [rank-1 array('f') with bounds (minmn)]

vt [rank-2 array('F') with bounds (vt0,vt1)]

info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

compute_uv
[input int, optional] Default: 1

full_matrices
[input int, optional] Default: 1

lwork [input int, optional] Default: $\max((\text{compute_uv} ? 2 * \text{minmn} * \text{minmn} + \text{MAX}(m,n) + 2 * \text{minmn} : 2 * \text{minmn} + \text{MAX}(m,n))$

scipy.linalg.lapack.zgesdd

`scipy.linalg.lapack.zgesdd(a[, compute_uv, full_matrices, lwork, overwrite_a]) = <fortran object>`

Wrapper for `zgesdd`.

Parameters

a [input rank-2 array('D') with bounds (m,n)]

Returns

u [rank-2 array('D') with bounds (u0,u1)]

s [rank-1 array('d') with bounds (minmn)]

vt [rank-2 array('D') with bounds (vt0,vt1)]

info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

compute_uv
[input int, optional] Default: 1

full_matrices
[input int, optional] Default: 1

lwork [input int, optional] Default: $\max((\text{compute_uv} ? 2 * \text{minmn} * \text{minmn} + \text{MAX}(m,n) + 2 * \text{minmn} : 2 * \text{minmn} + \text{MAX}(m,n))$

scipy.linalg.lapack.sgesdd_lwork

`scipy.linalg.lapack.sgesdd_lwork(m, n[, compute_uv, full_matrices]) = <fortran object>`

Wrapper for `sgesdd_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [float]
info [int]

Other Parameters

compute_uv
 [input int, optional] Default: 1
full_matrices
 [input int, optional] Default: 1

scipy.linalg.lapack.dgesdd_lwork

`scipy.linalg.lapack.dgesdd_lwork(m, n[, compute_uv, full_matrices]) = <fortran object>`

Wrapper for `dgesdd_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [float]
info [int]

Other Parameters

compute_uv
 [input int, optional] Default: 1
full_matrices
 [input int, optional] Default: 1

scipy.linalg.lapack.cgesdd_lwork

`scipy.linalg.lapack.cgesdd_lwork(m, n[, compute_uv, full_matrices]) = <fortran object>`

Wrapper for `cgesdd_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [complex]

info [int]

Other Parameters

compute_uv
[input int, optional] Default: 1

full_matrices
[input int, optional] Default: 1

scipy.linalg.lapack.zgesdd_lwork

`scipy.linalg.lapack.zgesdd_lwork(m, n[, compute_uv, full_matrices]) = <fortran object>`

Wrapper for zgesdd_lwork.

Parameters

m [input int]

n [input int]

Returns

work [complex]

info [int]

Other Parameters

compute_uv
[input int, optional] Default: 1

full_matrices
[input int, optional] Default: 1

scipy.linalg.lapack.sgesv

`scipy.linalg.lapack.sgesv(a, b[, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for sgesv.

Parameters

a [input rank-2 array('f') with bounds (n,n)]

b [input rank-2 array('f') with bounds (n,nrhs)]

Returns

lu [rank-2 array('f') with bounds (n,n) and a storage]

piv [rank-1 array('i') with bounds (n)]

x [rank-2 array('f') with bounds (n,nrhs) and b storage]

info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.dgesv

`scipy.linalg.lapack.dgesv(a, b[, overwrite_a, overwrite_b]) = <fortran object>`
 Wrapper for `dgesv`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
b [input rank-2 array('d') with bounds (n,nrhs)]

Returns

lu [rank-2 array('d') with bounds (n,n) and a storage]
piv [rank-1 array('i') with bounds (n)]
x [rank-2 array('d') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0
overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.cgesv

`scipy.linalg.lapack.cgesv(a, b[, overwrite_a, overwrite_b]) = <fortran object>`
 Wrapper for `cgesv`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
b [input rank-2 array('F') with bounds (n,nrhs)]

Returns

lu [rank-2 array('F') with bounds (n,n) and a storage]
piv [rank-1 array('i') with bounds (n)]
x [rank-2 array('F') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0
overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.zgesv

`scipy.linalg.lapack.zgesv(a, b[, overwrite_a, overwrite_b]) = <fortran object>`
 Wrapper for `zgesv`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (n,nrhs)]

Returns

lu [rank-2 array('D') with bounds (n,n) and a storage]
piv [rank-1 array('i') with bounds (n)]
x [rank-2 array('D') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.sgesvd

`scipy.linalg.lapack.sgesvd(a[, compute_uv, full_matrices, lwork, overwrite_a]) = <fortran object>`

Wrapper for sgesvd.

Parameters

a [input rank-2 array('f') with bounds (m,n)]

Returns

u [rank-2 array('f') with bounds (u0,u1)]
s [rank-1 array('f') with bounds (minmn)]
vt [rank-2 array('f') with bounds (vt0,vt1)]
info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0
compute_uv
[input int, optional] Default: 1
full_matrices
[input int, optional] Default: 1
lwork [input int, optional] Default: max(MAX(3*minmn+MAX(m,n),5*minmn),1)

scipy.linalg.lapack.dgesvd

`scipy.linalg.lapack.dgesvd(a[, compute_uv, full_matrices, lwork, overwrite_a]) = <fortran object>`

Wrapper for dgesvd.

Parameters

a [input rank-2 array('d') with bounds (m,n)]

Returns

u [rank-2 array('d') with bounds (u0,u1)]
s [rank-1 array('d') with bounds (minmn)]
vt [rank-2 array('d') with bounds (vt0,vt1)]
info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

compute_uv
 [input int, optional] Default: 1

full_matrices
 [input int, optional] Default: 1

lwork
 [input int, optional] Default: $\max(\text{MAX}(3*\text{minmn}+\text{MAX}(m,n),5*\text{minmn}),1)$

scipy.linalg.lapack.cgesvd

`scipy.linalg.lapack.cgesvd(a[, compute_uv, full_matrices, lwork, overwrite_a]) = <fortran object>`

Wrapper for `cgesvd`.

Parameters

a [input rank-2 array('F') with bounds (m,n)]

Returns

u [rank-2 array('F') with bounds (u0,u1)]
s [rank-1 array('f') with bounds (minmn)]
vt [rank-2 array('F') with bounds (vt0,vt1)]
info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

compute_uv
 [input int, optional] Default: 1

full_matrices
 [input int, optional] Default: 1

lwork
 [input int, optional] Default: $\text{MAX}(2*\text{minmn}+\text{MAX}(m,n),1)$

scipy.linalg.lapack.zgesvd

`scipy.linalg.lapack.zgesvd(a[, compute_uv, full_matrices, lwork, overwrite_a]) = <fortran object>`

Wrapper for `zgesvd`.

Parameters

a [input rank-2 array('D') with bounds (m,n)]

Returns

u [rank-2 array('D') with bounds (u0,u1)]
s [rank-1 array('d') with bounds (minmn)]
vt [rank-2 array('D') with bounds (vt0,vt1)]
info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

compute_uv
 [input int, optional] Default: 1

full_matrices [input int, optional] Default: 1
lwork [input int, optional] Default: MAX(2*minmn+MAX(m,n),1)

scipy.linalg.lapack.sgesvd_lwork

scipy.linalg.lapack.**sgesvd_lwork**(*m*, *n*[, *compute_uv*, *full_matrices*]) = <fortran object>

Wrapper for sgesvd_lwork.

Parameters

m [input int]
n [input int]

Returns

work [float]
info [int]

Other Parameters

compute_uv [input int, optional] Default: 1
full_matrices [input int, optional] Default: 1

scipy.linalg.lapack.dgesvd_lwork

scipy.linalg.lapack.**dgesvd_lwork**(*m*, *n*[, *compute_uv*, *full_matrices*]) = <fortran object>

Wrapper for dgesvd_lwork.

Parameters

m [input int]
n [input int]

Returns

work [float]
info [int]

Other Parameters

compute_uv [input int, optional] Default: 1
full_matrices [input int, optional] Default: 1

scipy.linalg.lapack.cgesvd_lwork

`scipy.linalg.lapack.cgesvd_lwork(m, n[, compute_uv, full_matrices]) = <fortran object>`

Wrapper for `cgesvd_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [complex]
info [int]

Other Parameters

compute_uv
 [input int, optional] Default: 1
full_matrices
 [input int, optional] Default: 1

scipy.linalg.lapack.zgesvd_lwork

`scipy.linalg.lapack.zgesvd_lwork(m, n[, compute_uv, full_matrices]) = <fortran object>`

Wrapper for `zgesvd_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [complex]
info [int]

Other Parameters

compute_uv
 [input int, optional] Default: 1
full_matrices
 [input int, optional] Default: 1

scipy.linalg.lapack.sgesvx

`scipy.linalg.lapack.sgesvx(a, b[, fact, trans, af, ipiv, equed, r, c, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `sgesvx`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]
b [input rank-2 array('f') with bounds (n,nrhs)]

Returns

as [rank-2 array('f') with bounds (n,n) and a storage]

lu [rank-2 array('f') with bounds (n,n) and af storage]
ipiv [rank-1 array('i') with bounds (n)]
equed [string(len=1)]
rs [rank-1 array('f') with bounds (n) and r storage]
cs [rank-1 array('f') with bounds (n) and c storage]
bs [rank-2 array('f') with bounds (n,nrhs) and b storage]
x [rank-2 array('f') with bounds (n,nrhs)]
rcond [float]
ferr [rank-1 array('f') with bounds (nrhs)]
berr [rank-1 array('f') with bounds (nrhs)]
info [int]

Other Parameters

fact [input string(len=1), optional] Default: 'E'
trans [input string(len=1), optional] Default: 'N'
overwrite_a
 [input int, optional] Default: 0
af [input rank-2 array('f') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]
equed [input string(len=1), optional] Default: 'B'
r [input rank-1 array('f') with bounds (n)]
c [input rank-1 array('f') with bounds (n)]
overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.dgesvx

`scipy.linalg.lapack.dgesvx(a, b[, fact, trans, af, ipiv, equed, r, c, overwrite_a, overwrite_b]) =`
<fortran object>

Wrapper for dgesvx.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
b [input rank-2 array('d') with bounds (n,nrhs)]

Returns

as [rank-2 array('d') with bounds (n,n) and a storage]
lu [rank-2 array('d') with bounds (n,n) and af storage]
ipiv [rank-1 array('i') with bounds (n)]
equed [string(len=1)]
rs [rank-1 array('d') with bounds (n) and r storage]
cs [rank-1 array('d') with bounds (n) and c storage]
bs [rank-2 array('d') with bounds (n,nrhs) and b storage]
x [rank-2 array('d') with bounds (n,nrhs)]
rcond [float]
ferr [rank-1 array('d') with bounds (nrhs)]
berr [rank-1 array('d') with bounds (nrhs)]
info [int]

Other Parameters

fact [input string(len=1), optional] Default: 'E'
trans [input string(len=1), optional] Default: 'N'

overwrite_a
 [input int, optional] Default: 0

af
 [input rank-2 array('d') with bounds (n,n)]

ipiv
 [input rank-1 array('i') with bounds (n)]

equed
 [input string(len=1), optional] Default: 'B'

r
 [input rank-1 array('d') with bounds (n)]

c
 [input rank-1 array('d') with bounds (n)]

overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.cgesvx

`scipy.linalg.lapack.cgesvx(a, b[, fact, trans, af, ipiv, equed, r, c, overwrite_a, overwrite_b]) =`
<fortran object>

Wrapper for `cgesvx`.

Parameters

a
 [input rank-2 array('F') with bounds (n,n)]

b
 [input rank-2 array('F') with bounds (n,nrhs)]

Returns

as
 [rank-2 array('F') with bounds (n,n) and a storage]

lu
 [rank-2 array('F') with bounds (n,n) and af storage]

ipiv
 [rank-1 array('i') with bounds (n)]

equed
 [string(len=1)]

rs
 [rank-1 array('f') with bounds (n) and r storage]

cs
 [rank-1 array('f') with bounds (n) and c storage]

bs
 [rank-2 array('F') with bounds (n,nrhs) and b storage]

x
 [rank-2 array('F') with bounds (n,nrhs)]

rcond
 [float]

ferr
 [rank-1 array('f') with bounds (nrhs)]

berr
 [rank-1 array('f') with bounds (nrhs)]

info
 [int]

Other Parameters

fact
 [input string(len=1), optional] Default: 'E'

trans
 [input string(len=1), optional] Default: 'N'

overwrite_a
 [input int, optional] Default: 0

af
 [input rank-2 array('F') with bounds (n,n)]

ipiv
 [input rank-1 array('i') with bounds (n)]

equed
 [input string(len=1), optional] Default: 'B'

r
 [input rank-1 array('f') with bounds (n)]

c
 [input rank-1 array('f') with bounds (n)]

overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.zgesvx

`scipy.linalg.lapack.zgesvx(a, b[, fact, trans, af, ipiv, equed, r, c, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `zgesvx`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (n,nrhs)]

Returns

as [rank-2 array('D') with bounds (n,n) and a storage]
lu [rank-2 array('D') with bounds (n,n) and af storage]
ipiv [rank-1 array('i') with bounds (n)]
equed [string(len=1)]
rs [rank-1 array('d') with bounds (n) and r storage]
cs [rank-1 array('d') with bounds (n) and c storage]
bs [rank-2 array('D') with bounds (n,nrhs) and b storage]
x [rank-2 array('D') with bounds (n,nrhs)]
rcond [float]
ferr [rank-1 array('d') with bounds (nrhs)]
berr [rank-1 array('d') with bounds (nrhs)]
info [int]

Other Parameters

fact [input string(len=1), optional] Default: 'E'
trans [input string(len=1), optional] Default: 'N'
overwrite_a [input int, optional] Default: 0
af [input rank-2 array('D') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]
equed [input string(len=1), optional] Default: 'B'
r [input rank-1 array('d') with bounds (n)]
c [input rank-1 array('d') with bounds (n)]
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.sgetrf

`scipy.linalg.lapack.sgetrf(a[, overwrite_a]) = <fortran object>`

Wrapper for `sgetrf`.

Parameters

a [input rank-2 array('f') with bounds (m,n)]

Returns

lu [rank-2 array('f') with bounds (m,n) and a storage]
piv [rank-1 array('i') with bounds (MIN(m,n))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0

scipy.linalg.lapack.dgetrf

`scipy.linalg.lapack.dgetrf(a[, overwrite_a]) = <fortran object>`
 Wrapper for `dgetrf`.

Parameters

a [input rank-2 array('d') with bounds (m,n)]

Returns

lu [rank-2 array('d') with bounds (m,n) and a storage]

piv [rank-1 array('i') with bounds (MIN(m,n))]

info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

scipy.linalg.lapack.cgetrf

`scipy.linalg.lapack.cgetrf(a[, overwrite_a]) = <fortran object>`
 Wrapper for `cgetrf`.

Parameters

a [input rank-2 array('F') with bounds (m,n)]

Returns

lu [rank-2 array('F') with bounds (m,n) and a storage]

piv [rank-1 array('i') with bounds (MIN(m,n))]

info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

scipy.linalg.lapack.zgetrf

`scipy.linalg.lapack.zgetrf(a[, overwrite_a]) = <fortran object>`
 Wrapper for `zgetrf`.

Parameters

a [input rank-2 array('D') with bounds (m,n)]

Returns

lu [rank-2 array('D') with bounds (m,n) and a storage]

piv [rank-1 array('i') with bounds (MIN(m,n))]

info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

scipy.linalg.lapack.sgetc2

`scipy.linalg.lapack.sgetc2(a[, overwrite_a]) = <fortran object>`
 Wrapper for `sgetc2`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]

Returns

lu [rank-2 array('f') with bounds (n,n) and a storage]
ipiv [rank-1 array('i') with bounds (n)]
jpiv [rank-1 array('i') with bounds (n)]
info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

scipy.linalg.lapack.dgetc2

`scipy.linalg.lapack.dgetc2(a[, overwrite_a]) = <fortran object>`
 Wrapper for `dgetc2`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]

Returns

lu [rank-2 array('d') with bounds (n,n) and a storage]
ipiv [rank-1 array('i') with bounds (n)]
jpiv [rank-1 array('i') with bounds (n)]
info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

scipy.linalg.lapack.cgetc2

`scipy.linalg.lapack.cgetc2(a[, overwrite_a]) = <fortran object>`
 Wrapper for `cgetc2`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]

Returns

lu [rank-2 array('F') with bounds (n,n) and a storage]
ipiv [rank-1 array('i') with bounds (n)]
jpiv [rank-1 array('i') with bounds (n)]
info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

scipy.linalg.lapack.zgetc2

`scipy.linalg.lapack.zgetc2(a[, overwrite_a]) = <fortran object>`
Wrapper for `zgetc2`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]

Returns

lu [rank-2 array('D') with bounds (n,n) and a storage]
ipiv [rank-1 array('i') with bounds (n)]
jpiv [rank-1 array('i') with bounds (n)]
info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

scipy.linalg.lapack.sgetri

`scipy.linalg.lapack.sgetri(lu, piv[, lwork, overwrite_lu]) = <fortran object>`
Wrapper for `sgetri`.

Parameters

lu [input rank-2 array('f') with bounds (n,n)]
piv [input rank-1 array('i') with bounds (n)]

Returns

inv_a [rank-2 array('f') with bounds (n,n) and lu storage]
info [int]

Other Parameters

overwrite_lu
[input int, optional] Default: 0
lwork [input int, optional] Default: $\max(3*n, 1)$

scipy.linalg.lapack.dgetri

`scipy.linalg.lapack.dgetri(lu, piv[, lwork, overwrite_lu]) = <fortran object>`
Wrapper for `dgetri`.

Parameters

lu [input rank-2 array('d') with bounds (n,n)]
piv [input rank-1 array('i') with bounds (n)]

Returns

inv_a [rank-2 array('d') with bounds (n,n) and lu storage]
info [int]

Other Parameters

overwrite_lu [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)

scipy.linalg.lapack.cgetri

`scipy.linalg.lapack.cgetri (lu, piv[, lwork, overwrite_lu]) = <fortran object>`
Wrapper for `cgetri`.

Parameters

lu [input rank-2 array('F') with bounds (n,n)]
piv [input rank-1 array('i') with bounds (n)]

Returns

inv_a [rank-2 array('F') with bounds (n,n) and lu storage]
info [int]

Other Parameters

overwrite_lu [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)

scipy.linalg.lapack.zgetri

`scipy.linalg.lapack.zgetri (lu, piv[, lwork, overwrite_lu]) = <fortran object>`
Wrapper for `zgetri`.

Parameters

lu [input rank-2 array('D') with bounds (n,n)]
piv [input rank-1 array('i') with bounds (n)]

Returns

inv_a [rank-2 array('D') with bounds (n,n) and lu storage]
info [int]

Other Parameters

overwrite_lu [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)

scipy.linalg.lapack.sgetri_lwork

`scipy.linalg.lapack.sgetri_lwork(n) = <fortran object>`
 Wrapper for `sgetri_lwork`.

Parameters

n [input int]

Returns

work [float]

info [int]

scipy.linalg.lapack.dgetri_lwork

`scipy.linalg.lapack.dgetri_lwork(n) = <fortran object>`
 Wrapper for `dgetri_lwork`.

Parameters

n [input int]

Returns

work [float]

info [int]

scipy.linalg.lapack.cgetri_lwork

`scipy.linalg.lapack.cgetri_lwork(n) = <fortran object>`
 Wrapper for `cgetri_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

scipy.linalg.lapack.zgetri_lwork

`scipy.linalg.lapack.zgetri_lwork(n) = <fortran object>`
 Wrapper for `zgetri_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

scipy.linalg.lapack.sgetrs

`scipy.linalg.lapack.sgetrs (lu, piv, b[, trans, overwrite_b]) = <fortran object>`
Wrapper for `sgetrs`.

Parameters

lu [input rank-2 array('f') with bounds (n,n)]
piv [input rank-1 array('i') with bounds (n)]
b [input rank-2 array('f') with bounds (n,nrhs)]

Returns

x [rank-2 array('f') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_b [input int, optional] Default: 0
trans [input int, optional] Default: 0

scipy.linalg.lapack.dgetrs

`scipy.linalg.lapack.dgetrs (lu, piv, b[, trans, overwrite_b]) = <fortran object>`
Wrapper for `dgetrs`.

Parameters

lu [input rank-2 array('d') with bounds (n,n)]
piv [input rank-1 array('i') with bounds (n)]
b [input rank-2 array('d') with bounds (n,nrhs)]

Returns

x [rank-2 array('d') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_b [input int, optional] Default: 0
trans [input int, optional] Default: 0

scipy.linalg.lapack.cgetrs

`scipy.linalg.lapack.cgetrs (lu, piv, b[, trans, overwrite_b]) = <fortran object>`
Wrapper for `cgetrs`.

Parameters

lu [input rank-2 array('F') with bounds (n,n)]
piv [input rank-1 array('i') with bounds (n)]
b [input rank-2 array('F') with bounds (n,nrhs)]

Returns

x [rank-2 array('F') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_b
[input int, optional] Default: 0

trans
[input int, optional] Default: 0

scipy.linalg.lapack.zgetrs

`scipy.linalg.lapack.zgetrs (lu, piv, b[, trans, overwrite_b]) = <fortran object>`
Wrapper for `zgetrs`.

Parameters

lu
[input rank-2 array('D') with bounds (n,n)]

piv
[input rank-1 array('i') with bounds (n)]

b
[input rank-2 array('D') with bounds (n,nrhs)]

Returns

x
[rank-2 array('D') with bounds (n,nrhs) and b storage]

info
[int]

Other Parameters

overwrite_b
[input int, optional] Default: 0

trans
[input int, optional] Default: 0

scipy.linalg.lapack.sgesc2

`scipy.linalg.lapack.sgesc2 (lu, rhs, ipiv, jpiv[, overwrite_rhs]) = <fortran object>`
Wrapper for `sgesc2`.

Parameters

lu
[input rank-2 array('f') with bounds (n,n)]

rhs
[input rank-1 array('f') with bounds (n)]

ipiv
[input rank-1 array('i') with bounds (n)]

jpiv
[input rank-1 array('i') with bounds (n)]

Returns

x
[rank-1 array('f') with bounds (n) and rhs storage]

scale
[float]

Other Parameters

overwrite_rhs
[input int, optional] Default: 0

scipy.linalg.lapack.dgesc2

`scipy.linalg.lapack.dgesc2 (lu, rhs, ipiv, jpiv[, overwrite_rhs]) = <fortran object>`
 Wrapper for dgesc2.

Parameters

lu [input rank-2 array('d') with bounds (n,n)]
rhs [input rank-1 array('d') with bounds (n)]
ipiv [input rank-1 array('i') with bounds (n)]
jpiv [input rank-1 array('i') with bounds (n)]

Returns

x [rank-1 array('d') with bounds (n) and rhs storage]
scale [float]

Other Parameters

overwrite_rhs
 [input int, optional] Default: 0

scipy.linalg.lapack.cgesc2

`scipy.linalg.lapack.cgesc2 (lu, rhs, ipiv, jpiv[, overwrite_rhs]) = <fortran object>`
 Wrapper for cgesc2.

Parameters

lu [input rank-2 array('F') with bounds (n,n)]
rhs [input rank-1 array('F') with bounds (n)]
ipiv [input rank-1 array('i') with bounds (n)]
jpiv [input rank-1 array('i') with bounds (n)]

Returns

x [rank-1 array('F') with bounds (n) and rhs storage]
scale [float]

Other Parameters

overwrite_rhs
 [input int, optional] Default: 0

scipy.linalg.lapack.zgesc2

`scipy.linalg.lapack.zgesc2 (lu, rhs, ipiv, jpiv[, overwrite_rhs]) = <fortran object>`
 Wrapper for zgesc2.

Parameters

lu [input rank-2 array('D') with bounds (n,n)]
rhs [input rank-1 array('D') with bounds (n)]
ipiv [input rank-1 array('i') with bounds (n)]
jpiv [input rank-1 array('i') with bounds (n)]

Returns

x [rank-1 array('D') with bounds (n) and rhs storage]
scale [float]

Other Parameters

overwrite_rhs
[input int, optional] Default: 0

scipy.linalg.lapack.sgges

`scipy.linalg.lapack.sgges` (*sselect*, *a*, *b*[, *jobvsl*, *jobvsr*, *sort_t*, *ldvsl*, *ldvsr*, *lwork*, *sselect_extra_args*, *overwrite_a*, *overwrite_b*]) = **<fortran object>**

Wrapper for sgges.

Parameters

sselect [call-back function]
a [input rank-2 array('f') with bounds (lda,n)]
b [input rank-2 array('f') with bounds (ldb,n)]

Returns

a [rank-2 array('f') with bounds (lda,n)]
b [rank-2 array('f') with bounds (ldb,n)]
sdim [int]
alphar [rank-1 array('f') with bounds (n)]
alphai [rank-1 array('f') with bounds (n)]
beta [rank-1 array('f') with bounds (n)]
vsl [rank-2 array('f') with bounds (ldvsl,n)]
vsr [rank-2 array('f') with bounds (ldvsr,n)]
work [rank-1 array('f') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

jobvsl [input int, optional] Default: 1
jobvsr [input int, optional] Default: 1
sort_t [input int, optional] Default: 0
sselect_extra_args
[input tuple, optional] Default: ()
overwrite_a
[input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0
ldvsl [input int, optional] Default: ((jobvsl==1)?n:1)
ldvsr [input int, optional] Default: ((jobvsr==1)?n:1)
lwork [input int, optional] Default: max(8*n+16,1)

Notes

Call-back functions:

```
def sselect(alphar, alphai, beta): return sselect
Required arguments:
  alphar : input float
  alphai : input float
  beta   : input float
Return objects:
  sselect : int
```

scipy.linalg.lapack.dgges

`scipy.linalg.lapack.dgges` (*dselect*, *a*, *b*[, *jobvsl*, *jobvsr*, *sort_t*, *ldvsl*, *ldvsr*, *lwork*, *dselect_extra_args*, *overwrite_a*, *overwrite_b*]) = **<fortran object>**

Wrapper for dgges.

Parameters

dselect [call-back function]
a [input rank-2 array('d') with bounds (lda,n)]
b [input rank-2 array('d') with bounds (ldb,n)]

Returns

a [rank-2 array('d') with bounds (lda,n)]
b [rank-2 array('d') with bounds (ldb,n)]
sdim [int]
alphar [rank-1 array('d') with bounds (n)]
alphai [rank-1 array('d') with bounds (n)]
beta [rank-1 array('d') with bounds (n)]
vsl [rank-2 array('d') with bounds (ldvsl,n)]
vsr [rank-2 array('d') with bounds (ldvsr,n)]
work [rank-1 array('d') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

jobvsl [input int, optional] Default: 1
jobvsr [input int, optional] Default: 1
sort_t [input int, optional] Default: 0
dselect_extra_args [input tuple, optional] Default: ()
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
ldvsl [input int, optional] Default: ((jobvsl==1)?n:1)
ldvsr [input int, optional] Default: ((jobvsr==1)?n:1)
lwork [input int, optional] Default: max(8*n+16,1)

Notes

Call-back functions:

```
def dselect(alphar, alphai, beta): return dselect
Required arguments:
  alphar : input float
  alphai : input float
  beta   : input float
Return objects:
  dselect : int
```

scipy.linalg.lapack.cgges

`scipy.linalg.lapack.cgges` (*cselect*, *a*, *b*[, *jobvsl*, *jobvsr*, *sort_t*, *ldvsl*, *ldvsr*, *lwork*, *cselect_extra_args*, *overwrite_a*, *overwrite_b*]) = **<fortran object>**

Wrapper for cgges.

Parameters

cselect [call-back function]
a [input rank-2 array('F') with bounds (lda,n)]
b [input rank-2 array('F') with bounds (ldb,n)]

Returns

a [rank-2 array('F') with bounds (lda,n)]
b [rank-2 array('F') with bounds (ldb,n)]
sdim [int]
alpha [rank-1 array('F') with bounds (n)]
beta [rank-1 array('F') with bounds (n)]
vsl [rank-2 array('F') with bounds (ldvsl,n)]
vsr [rank-2 array('F') with bounds (ldvsr,n)]
work [rank-1 array('F') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

jobvsl [input int, optional] Default: 1
jobvsr [input int, optional] Default: 1
sort_t [input int, optional] Default: 0
cselect_extra_args
 [input tuple, optional] Default: ()
overwrite_a
 [input int, optional] Default: 0
overwrite_b
 [input int, optional] Default: 0
ldvsl [input int, optional] Default: ((jobvsl==1)?n:1)
ldvsr [input int, optional] Default: ((jobvsr==1)?n:1)
lwork [input int, optional] Default: max(2*n,1)

Notes

Call-back functions:

```
def cselect(alpha,beta): return cselect
Required arguments:
  alpha : input complex
  beta  : input complex
Return objects:
  cselect : int
```

scipy.linalg.lapack.zgges

`scipy.linalg.lapack.zgges` (*zselect*, *a*, *b*[, *jobvsl*, *jobvsr*, *sort_t*, *ldvsl*, *ldvsr*, *lwork*, *zselect_extra_args*, *overwrite_a*, *overwrite_b*]) = <fortran object>

Wrapper for zgges.

Parameters

zselect [call-back function]
a [input rank-2 array('D') with bounds (lda,n)]
b [input rank-2 array('D') with bounds (ldb,n)]

Returns

a [rank-2 array('D') with bounds (lda,n)]
b [rank-2 array('D') with bounds (ldb,n)]
sdim [int]
alpha [rank-1 array('D') with bounds (n)]
beta [rank-1 array('D') with bounds (n)]
vsl [rank-2 array('D') with bounds (ldvsl,n)]
vsr [rank-2 array('D') with bounds (ldvsr,n)]
work [rank-1 array('D') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

jobvsl [input int, optional] Default: 1
jobvsr [input int, optional] Default: 1
sort_t [input int, optional] Default: 0
zselect_extra_args [input tuple, optional] Default: ()
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
ldvsl [input int, optional] Default: ((jobvsl==1)?n:1)
ldvsr [input int, optional] Default: ((jobvsr==1)?n:1)
lwork [input int, optional] Default: max(2*n,1)

Notes

Call-back functions:

```
def zselect(alpha,beta): return zselect
Required arguments:
  alpha : input complex
  beta  : input complex
Return objects:
  zselect : int
```

scipy.linalg.lapack.sggev

`scipy.linalg.lapack.sggev(a, b[, compute_vl, compute_vr, lwork, overwrite_a, overwrite_b]) =`
<fortran object>

Wrapper for `sggev`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]
b [input rank-2 array('f') with bounds (n,n)]

Returns

alphar [rank-1 array('f') with bounds (n)]
alphai [rank-1 array('f') with bounds (n)]
beta [rank-1 array('f') with bounds (n)]
vl [rank-2 array('f') with bounds (ldvl,n)]
vr [rank-2 array('f') with bounds (ldvr,n)]
work [rank-1 array('f') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

compute_vl [input int, optional] Default: 1
compute_vr [input int, optional] Default: 1
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(8*n,1)

scipy.linalg.lapack.dggeev

`scipy.linalg.lapack.dggeev(a, b[, compute_vl, compute_vr, lwork, overwrite_a, overwrite_b]) =`
<fortran object>

Wrapper for `dggeev`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
b [input rank-2 array('d') with bounds (n,n)]

Returns

alphar [rank-1 array('d') with bounds (n)]
alphai [rank-1 array('d') with bounds (n)]
beta [rank-1 array('d') with bounds (n)]
vl [rank-2 array('d') with bounds (ldvl,n)]
vr [rank-2 array('d') with bounds (ldvr,n)]
work [rank-1 array('d') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

compute_vl [input int, optional] Default: 1

compute_vr [input int, optional] Default: 1
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(8*n,1)

scipy.linalg.lapack.cggev

scipy.linalg.lapack.**cggev**(*a*, *b*[, *compute_vl*, *compute_vr*, *lwork*, *overwrite_a*, *overwrite_b*]) =
 <fortran object>

Wrapper for cggev.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
b [input rank-2 array('F') with bounds (n,n)]

Returns

alpha [rank-1 array('F') with bounds (n)]
beta [rank-1 array('F') with bounds (n)]
vl [rank-2 array('F') with bounds (ldvl,n)]
vr [rank-2 array('F') with bounds (ldvr,n)]
work [rank-1 array('F') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

compute_vl [input int, optional] Default: 1
compute_vr [input int, optional] Default: 1
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(2*n,1)

scipy.linalg.lapack.zggev

scipy.linalg.lapack.**zggev**(*a*, *b*[, *compute_vl*, *compute_vr*, *lwork*, *overwrite_a*, *overwrite_b*]) =
 <fortran object>

Wrapper for zggev.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (n,n)]

Returns

alpha [rank-1 array('D') with bounds (n)]
beta [rank-1 array('D') with bounds (n)]
vl [rank-2 array('D') with bounds (ldvl,n)]
vr [rank-2 array('D') with bounds (ldvr,n)]

work [rank-1 array('D') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

compute_vl
[input int, optional] Default: 1
compute_vr
[input int, optional] Default: 1
overwrite_a
[input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0
lwork [input int, optional] Default: max(2*n,1)

scipy.linalg.lapack.sggls

`scipy.linalg.lapack.sggls` (*a*, *b*, *c*, *d*[, *lwork*, *overwrite_a*, *overwrite_b*, *overwrite_c*, *overwrite_d*])
= <fortran object>

Wrapper for sggls.

Parameters

a [input rank-2 array('f') with bounds (m,n)]
b [input rank-2 array('f') with bounds (p,n)]
c [input rank-1 array('f') with bounds (m)]
d [input rank-1 array('f') with bounds (p)]

Returns

t [rank-2 array('f') with bounds (m,n) and a storage]
r [rank-2 array('f') with bounds (p,n) and b storage]
res [rank-1 array('f') with bounds (m) and c storage]
x [rank-1 array('f') with bounds (n)]
info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0
overwrite_c
[input int, optional] Default: 0
overwrite_d
[input int, optional] Default: 0
lwork [input int, optional] Default: max(m+n+p,1)

scipy.linalg.lapack.dgglse

`scipy.linalg.lapack.dgglse` (*a*, *b*, *c*, *d*[, *lwork*, *overwrite_a*, *overwrite_b*, *overwrite_c*, *overwrite_d*])
 = <fortran object>

Wrapper for dgglse.

Parameters

a [input rank-2 array('d') with bounds (m,n)]
b [input rank-2 array('d') with bounds (p,n)]
c [input rank-1 array('d') with bounds (m)]
d [input rank-1 array('d') with bounds (p)]

Returns

t [rank-2 array('d') with bounds (m,n) and a storage]
r [rank-2 array('d') with bounds (p,n) and b storage]
res [rank-1 array('d') with bounds (m) and c storage]
x [rank-1 array('d') with bounds (n)]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
overwrite_c [input int, optional] Default: 0
overwrite_d [input int, optional] Default: 0
lwork [input int, optional] Default: max(m+n+p,1)

scipy.linalg.lapack.cgglse

`scipy.linalg.lapack.cgglse` (*a*, *b*, *c*, *d*[, *lwork*, *overwrite_a*, *overwrite_b*, *overwrite_c*, *overwrite_d*])
 = <fortran object>

Wrapper for cgglse.

Parameters

a [input rank-2 array('F') with bounds (m,n)]
b [input rank-2 array('F') with bounds (p,n)]
c [input rank-1 array('F') with bounds (m)]
d [input rank-1 array('F') with bounds (p)]

Returns

t [rank-2 array('F') with bounds (m,n) and a storage]
r [rank-2 array('F') with bounds (p,n) and b storage]
res [rank-1 array('F') with bounds (m) and c storage]
x [rank-1 array('F') with bounds (n)]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0

overwrite_b [input int, optional] Default: 0
overwrite_c [input int, optional] Default: 0
overwrite_d [input int, optional] Default: 0
lwork [input int, optional] Default: max(m+n+p,1)

scipy.linalg.lapack.zgglse

`scipy.linalg.lapack.zgglse(a, b, c, d[, lwork, overwrite_a, overwrite_b, overwrite_c, overwrite_d])`
 = <fortran object>

Wrapper for zgglse.

Parameters

a [input rank-2 array('D') with bounds (m,n)]
b [input rank-2 array('D') with bounds (p,n)]
c [input rank-1 array('D') with bounds (m)]
d [input rank-1 array('D') with bounds (p)]

Returns

t [rank-2 array('D') with bounds (m,n) and a storage]
r [rank-2 array('D') with bounds (p,n) and b storage]
res [rank-1 array('D') with bounds (m) and c storage]
x [rank-1 array('D') with bounds (n)]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
overwrite_c [input int, optional] Default: 0
overwrite_d [input int, optional] Default: 0
lwork [input int, optional] Default: max(m+n+p,1)

scipy.linalg.lapack.sgglse_lwork

`scipy.linalg.lapack.sgglse_lwork(m, n, p) = <fortran object>`

Wrapper for sgglse_lwork.

Parameters

m [input int]
n [input int]
p [input int]

Returns

work [float]
info [int]

scipy.linalg.lapack.dgglse_lwork

`scipy.linalg.lapack.dgglse_lwork(m, n, p) = <fortran object>`
Wrapper for `dgglse_lwork`.

Parameters

m	[input int]
n	[input int]
p	[input int]

Returns

work	[float]
info	[int]

scipy.linalg.lapack.cgglse_lwork

`scipy.linalg.lapack.cgglse_lwork(m, n, p) = <fortran object>`
Wrapper for `cgglse_lwork`.

Parameters

m	[input int]
n	[input int]
p	[input int]

Returns

work	[complex]
info	[int]

scipy.linalg.lapack.zgglse_lwork

`scipy.linalg.lapack.zgglse_lwork(m, n, p) = <fortran object>`
Wrapper for `zgglse_lwork`.

Parameters

m	[input int]
n	[input int]
p	[input int]

Returns

work	[complex]
info	[int]

scipy.linalg.lapack.sgtsv

`scipy.linalg.lapack.sgtsv` (*dl*, *d*, *du*, *b*[, *overwrite_dl*, *overwrite_d*, *overwrite_du*, *overwrite_b*]) =
 <fortran object>

Wrapper for `sgtsv`.

Parameters

dl [input rank-1 array('f') with bounds (n - 1)]
d [input rank-1 array('f') with bounds (n)]
du [input rank-1 array('f') with bounds (n - 1)]
b [input rank-2 array('f') with bounds (n,nrhs)]

Returns

du2 [rank-1 array('f') with bounds (n - 1) and dl storage]
d [rank-1 array('f') with bounds (n)]
du [rank-1 array('f') with bounds (n - 1)]
x [rank-2 array('f') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_dl
 [input int, optional] Default: 0
overwrite_d
 [input int, optional] Default: 0
overwrite_du
 [input int, optional] Default: 0
overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.dgtsv

`scipy.linalg.lapack.dgtsv` (*dl*, *d*, *du*, *b*[, *overwrite_dl*, *overwrite_d*, *overwrite_du*, *overwrite_b*]) =
 <fortran object>

Wrapper for `dgtsv`.

Parameters

dl [input rank-1 array('d') with bounds (n - 1)]
d [input rank-1 array('d') with bounds (n)]
du [input rank-1 array('d') with bounds (n - 1)]
b [input rank-2 array('d') with bounds (n,nrhs)]

Returns

du2 [rank-1 array('d') with bounds (n - 1) and dl storage]
d [rank-1 array('d') with bounds (n)]
du [rank-1 array('d') with bounds (n - 1)]
x [rank-2 array('d') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_dl
 [input int, optional] Default: 0
overwrite_d
 [input int, optional] Default: 0

overwrite_du
 [input int, optional] Default: 0

overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.cgtsv

`scipy.linalg.lapack.cgtsv` (*dl, d, du, b* [, *overwrite_dl, overwrite_d, overwrite_du, overwrite_b*]) =
 <fortran object>

Wrapper for `cgtsv`.

Parameters

dl [input rank-1 array('F') with bounds (n - 1)]
d [input rank-1 array('F') with bounds (n)]
du [input rank-1 array('F') with bounds (n - 1)]
b [input rank-2 array('F') with bounds (n,nrhs)]

Returns

du2 [rank-1 array('F') with bounds (n - 1) and dl storage]
d [rank-1 array('F') with bounds (n)]
du [rank-1 array('F') with bounds (n - 1)]
x [rank-2 array('F') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_dl
 [input int, optional] Default: 0

overwrite_d
 [input int, optional] Default: 0

overwrite_du
 [input int, optional] Default: 0

overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.zgtsv

`scipy.linalg.lapack.zgtsv` (*dl, d, du, b* [, *overwrite_dl, overwrite_d, overwrite_du, overwrite_b*]) =
 <fortran object>

Wrapper for `zgtsv`.

Parameters

dl [input rank-1 array('D') with bounds (n - 1)]
d [input rank-1 array('D') with bounds (n)]
du [input rank-1 array('D') with bounds (n - 1)]
b [input rank-2 array('D') with bounds (n,nrhs)]

Returns

du2 [rank-1 array('D') with bounds (n - 1) and dl storage]
d [rank-1 array('D') with bounds (n)]
du [rank-1 array('D') with bounds (n - 1)]
x [rank-2 array('D') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_dl	[input int, optional] Default: 0
overwrite_d	[input int, optional] Default: 0
overwrite_du	[input int, optional] Default: 0
overwrite_b	[input int, optional] Default: 0

scipy.linalg.lapack.sgtsvx

`scipy.linalg.lapack.sgtsvx` (*dl, d, du, b*[, *fact, trans, dlf, df, duf, du2, ipiv*]) = **<fortran object>**

Wrapper for `sgtsvx`.

Parameters

dl	[input rank-1 array('f') with bounds (MAX(0, n-1))]
d	[input rank-1 array('f') with bounds (n)]
du	[input rank-1 array('f') with bounds (MAX(0, n-1))]
b	[input rank-2 array('f') with bounds (ldb,nrhs)]

Returns

dlf	[rank-1 array('f') with bounds (MAX(0,n-1))]
df	[rank-1 array('f') with bounds (n)]
duf	[rank-1 array('f') with bounds (MAX(0,n-1))]
du2	[rank-1 array('f') with bounds (MAX(0,n-2))]
ipiv	[rank-1 array('i') with bounds (n)]
x	[rank-2 array('f') with bounds (ldx,nrhs)]
rcond	[float]
ferr	[rank-1 array('f') with bounds (nrhs)]
berr	[rank-1 array('f') with bounds (nrhs)]
info	[int]

Other Parameters

fact	[input string(len=1), optional] Default: 'N'
trans	[input string(len=1), optional] Default: 'N'
dlf	[input rank-1 array('f') with bounds (MAX(0,n-1))]
df	[input rank-1 array('f') with bounds (n)]
duf	[input rank-1 array('f') with bounds (MAX(0,n-1))]
du2	[input rank-1 array('f') with bounds (MAX(0,n-2))]
ipiv	[input rank-1 array('i') with bounds (n)]

scipy.linalg.lapack.dgtsvx

`scipy.linalg.lapack.dgtsvx` (*dl, d, du, b*[, *fact, trans, dlf, df, duf, du2, ipiv*]) = <fortran object>

Wrapper for `dgtsvx`.

Parameters

dl [input rank-1 array('d') with bounds (MAX(0, n-1))]
d [input rank-1 array('d') with bounds (n)]
du [input rank-1 array('d') with bounds (MAX(0, n-1))]
b [input rank-2 array('d') with bounds (ldb,nrhs)]

Returns

dlf [rank-1 array('d') with bounds (MAX(0,n-1))]
df [rank-1 array('d') with bounds (n)]
duf [rank-1 array('d') with bounds (MAX(0,n-1))]
du2 [rank-1 array('d') with bounds (MAX(0,n-2))]
ipiv [rank-1 array('i') with bounds (n)]
x [rank-2 array('d') with bounds (ldx,nrhs)]
rcond [float]
ferr [rank-1 array('d') with bounds (nrhs)]
berr [rank-1 array('d') with bounds (nrhs)]
info [int]

Other Parameters

fact [input string(len=1), optional] Default: 'N'
trans [input string(len=1), optional] Default: 'N'
dlf [input rank-1 array('d') with bounds (MAX(0,n-1))]
df [input rank-1 array('d') with bounds (n)]
duf [input rank-1 array('d') with bounds (MAX(0,n-1))]
du2 [input rank-1 array('d') with bounds (MAX(0,n-2))]
ipiv [input rank-1 array('i') with bounds (n)]

scipy.linalg.lapack.cgtsvx

`scipy.linalg.lapack.cgtsvx` (*dl, d, du, b*[, *fact, trans, dlf, df, duf, du2, ipiv*]) = <fortran object>

Wrapper for `cgtsvx`.

Parameters

dl [input rank-1 array('F') with bounds (MAX(0, n-1))]
d [input rank-1 array('F') with bounds (n)]
du [input rank-1 array('F') with bounds (MAX(0, n-1))]
b [input rank-2 array('F') with bounds (ldb,nrhs)]

Returns

dlf [rank-1 array('F') with bounds (MAX(0,n-1))]
df [rank-1 array('F') with bounds (n)]
duf [rank-1 array('F') with bounds (MAX(0,n-1))]
du2 [rank-1 array('F') with bounds (MAX(0,n-2))]
ipiv [rank-1 array('i') with bounds (n)]
x [rank-2 array('F') with bounds (ldx,nrhs)]
rcond [float]

ferr	[rank-1 array('f') with bounds (nrhs)]
berr	[rank-1 array('f') with bounds (nrhs)]
info	[int]

Other Parameters

fact	[input string(len=1), optional] Default: 'N'
trans	[input string(len=1), optional] Default: 'N'
dlf	[input rank-1 array('F') with bounds (MAX(0,n-1))]
df	[input rank-1 array('F') with bounds (n)]
duf	[input rank-1 array('F') with bounds (MAX(0,n-1))]
du2	[input rank-1 array('F') with bounds (MAX(0,n-2))]
ipiv	[input rank-1 array('i') with bounds (n)]

scipy.linalg.lapack.zgtsvx

`scipy.linalg.lapack.zgtsvx` (*dl, d, du, b*[, *fact, trans, dlf, df, duf, du2, ipiv*]) = <fortran object>

Wrapper for `zgtsvx`.

Parameters

dl	[input rank-1 array('D') with bounds (MAX(0, n-1))]
d	[input rank-1 array('D') with bounds (n)]
du	[input rank-1 array('D') with bounds (MAX(0, n-1))]
b	[input rank-2 array('D') with bounds (ldb,nrhs)]

Returns

dlf	[rank-1 array('D') with bounds (MAX(0,n-1))]
df	[rank-1 array('D') with bounds (n)]
duf	[rank-1 array('D') with bounds (MAX(0,n-1))]
du2	[rank-1 array('D') with bounds (MAX(0,n-2))]
ipiv	[rank-1 array('i') with bounds (n)]
x	[rank-2 array('D') with bounds (ldx,nrhs)]
rcond	[float]
ferr	[rank-1 array('d') with bounds (nrhs)]
berr	[rank-1 array('d') with bounds (nrhs)]
info	[int]

Other Parameters

fact	[input string(len=1), optional] Default: 'N'
trans	[input string(len=1), optional] Default: 'N'
dlf	[input rank-1 array('D') with bounds (MAX(0,n-1))]
df	[input rank-1 array('D') with bounds (n)]
duf	[input rank-1 array('D') with bounds (MAX(0,n-1))]
du2	[input rank-1 array('D') with bounds (MAX(0,n-2))]
ipiv	[input rank-1 array('i') with bounds (n)]

scipy.linalg.lapack.chbevd

`scipy.linalg.lapack.chbevd(ab[, compute_v, lower, ldab, lrwork, liwork, overwrite_ab]) =`
<fortran object>

Wrapper for chbevd.

Parameters

ab [input rank-2 array('F') with bounds (ldab,n)]

Returns

w [rank-1 array('f') with bounds (n)]
z [rank-2 array('F') with bounds (ldz,ldz)]
info [int]

Other Parameters

overwrite_ab [input int, optional] Default: 1
compute_v [input int, optional] Default: 1
lower [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)
lrwork [input int, optional] Default: (compute_v?1+5*n+2*n*n:n)
liwork [input int, optional] Default: (compute_v?3+5*n:1)

scipy.linalg.lapack.zhbevd

`scipy.linalg.lapack.zhbevd(ab[, compute_v, lower, ldab, lrwork, liwork, overwrite_ab]) =`
<fortran object>

Wrapper for zhbevd.

Parameters

ab [input rank-2 array('D') with bounds (ldab,n)]

Returns

w [rank-1 array('d') with bounds (n)]
z [rank-2 array('D') with bounds (ldz,ldz)]
info [int]

Other Parameters

overwrite_ab [input int, optional] Default: 1
compute_v [input int, optional] Default: 1
lower [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)
lrwork [input int, optional] Default: (compute_v?1+5*n+2*n*n:n)
liwork [input int, optional] Default: (compute_v?3+5*n:1)

scipy.linalg.lapack.chbev

`scipy.linalg.lapack.chbev`(*ab*, *vl*, *vu*, *il*, *iu*[, *ldab*, *compute_v*, *range*, *lower*, *abstol*, *mmax*, *overwrite_ab*]) = <fortran object>

Wrapper for `chbev`.

Parameters

ab [input rank-2 array('F') with bounds (ldab,n)]
vl [input float]
vu [input float]
il [input int]
iu [input int]

Returns

w [rank-1 array('f') with bounds (n)]
z [rank-2 array('F') with bounds (ldz,mmax)]
m [int]
ifail [rank-1 array('i') with bounds ((compute_v?n:1))]
info [int]

Other Parameters

overwrite_ab
 [input int, optional] Default: 1
ldab [input int, optional] Default: shape(ab,0)
compute_v
 [input int, optional] Default: 1
range [input int, optional] Default: 0
lower [input int, optional] Default: 0
abstol [input float, optional] Default: 0.0
mmax [input int, optional] Default: (compute_v?(range==2?(iu-il+1):n):1)

scipy.linalg.lapack.zhbev

`scipy.linalg.lapack.zhbev`(*ab*, *vl*, *vu*, *il*, *iu*[, *ldab*, *compute_v*, *range*, *lower*, *abstol*, *mmax*, *overwrite_ab*]) = <fortran object>

Wrapper for `zhbev`.

Parameters

ab [input rank-2 array('D') with bounds (ldab,n)]
vl [input float]
vu [input float]
il [input int]
iu [input int]

Returns

w [rank-1 array('d') with bounds (n)]
z [rank-2 array('D') with bounds (ldz,mmax)]
m [int]
ifail [rank-1 array('i') with bounds ((compute_v?n:1))]
info [int]

Other Parameters

overwrite_ab [input int, optional] Default: 1
ldab [input int, optional] Default: shape(ab,0)
compute_v [input int, optional] Default: 1
range [input int, optional] Default: 0
lower [input int, optional] Default: 0
abstol [input float, optional] Default: 0.0
mmax [input int, optional] Default: (compute_v?(range==2?(iu-il+1):n):1)

scipy.linalg.lapack.checon

`scipy.linalg.lapack.checon(a, ipiv, anorm[, lower]) = <fortran object>`
 Wrapper for checon.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zhecon

`scipy.linalg.lapack.zhecon(a, ipiv, anorm[, lower]) = <fortran object>`
 Wrapper for zhecon.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.cheequb

`scipy.linalg.lapack.cheequb(a[, lower]) = <fortran object>`
 Wrapper for cheequb.

Parameters

a [input rank-2 array('F') with bounds (lda,n)]

Returns

s [rank-1 array('f') with bounds (n)]

scond [float]

amax [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zheequb

`scipy.linalg.lapack.zheequb(a[, lower]) = <fortran object>`
 Wrapper for zheequb.

Parameters

a [input rank-2 array('D') with bounds (lda,n)]

Returns

s [rank-1 array('d') with bounds (n)]

scond [float]

amax [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.cheev

`scipy.linalg.lapack.cheev(a[, compute_v, lower, lwork, overwrite_a]) = <fortran object>`
 Wrapper for cheev.

Parameters

a [input rank-2 array('F') with bounds (n,n)]

Returns

w [rank-1 array('f') with bounds (n)]

v [rank-2 array('F') with bounds (n,n) and a storage]

info [int]

Other Parameters**compute_v**

[input int, optional] Default: 1

lower [input int, optional] Default: 0

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(2*n-1,1)

scipy.linalg.lapack.zheev

`scipy.linalg.lapack.zheev(a[, compute_v, lower, lwork, overwrite_a]) = <fortran object>`
 Wrapper for zheev.

Parameters

a [input rank-2 array('D') with bounds (n,n)]

Returns

w [rank-1 array('d') with bounds (n)]
v [rank-2 array('D') with bounds (n,n) and a storage]
info [int]

Other Parameters

compute_v [input int, optional] Default: 1
lower [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(2*n-1,1)

scipy.linalg.lapack.cheev_lwork

`scipy.linalg.lapack.cheev_lwork(n[, lower]) = <fortran object>`
 Wrapper for cheev_lwork.

Parameters

n [input int]

Returns

work [complex]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zheev_lwork

`scipy.linalg.lapack.zheev_lwork(n[, lower]) = <fortran object>`
 Wrapper for zheev_lwork.

Parameters

n [input int]

Returns

work [complex]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.cheevd

```
scipy.linalg.lapack.cheevd(a[, compute_v, lower, lwork, liwork, lrwork, overwrite_a]) =
    <fortran object>
```

Wrapper for cheevd.

Parameters

a [input rank-2 array('F') with bounds (n,n)]

Returns

w [rank-1 array('f') with bounds (n)]
v [rank-2 array('F') with bounds (n,n) and a storage]
info [int]

Other Parameters

compute_v [input int, optional] Default: 1
lower [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max((compute_v?2*n+n*n:n+1),1)
liwork [input int, optional] Default: (compute_v?3+5*n:1)
lrwork [input int, optional] Default: (compute_v?1+5*n+2*n*n:n)

scipy.linalg.lapack.zheevd

```
scipy.linalg.lapack.zheevd(a[, compute_v, lower, lwork, liwork, lrwork, overwrite_a]) =
    <fortran object>
```

Wrapper for zheevd.

Parameters

a [input rank-2 array('D') with bounds (n,n)]

Returns

w [rank-1 array('d') with bounds (n)]
v [rank-2 array('D') with bounds (n,n) and a storage]
info [int]

Other Parameters

compute_v [input int, optional] Default: 1
lower [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max((compute_v?2*n+n*n:n+1),1)
liwork [input int, optional] Default: (compute_v?3+5*n:1)
lrwork [input int, optional] Default: (compute_v?1+5*n+2*n*n:n)

scipy.linalg.lapack.cheevd_lwork

`scipy.linalg.lapack.cheevd_lwork` (n [, *compute_v*, *lower*]) = <fortran object>
 Wrapper for `cheevd_lwork`.

Parameters

n [input int]

Returns

work [complex]

iwork [int]

rwork [float]

info [int]

Other Parameters

compute_v [input int, optional] Default: 1

lower [input int, optional] Default: 0

scipy.linalg.lapack.zheevd_lwork

`scipy.linalg.lapack.zheevd_lwork` (n [, *compute_v*, *lower*]) = <fortran object>
 Wrapper for `zheevd_lwork`.

Parameters

n [input int]

Returns

work [complex]

iwork [int]

rwork [float]

info [int]

Other Parameters

compute_v [input int, optional] Default: 1

lower [input int, optional] Default: 0

scipy.linalg.lapack.cheevr

`scipy.linalg.lapack.cheevr` (a [, *compute_v*, *range*, *lower*, *vl*, *vu*, *il*, *iu*, *abstol*, *lwork*, *lrwork*, *liwork*, *overwrite_a*]) = <fortran object>

Wrapper for `cheevr`.

Parameters

a [input rank-2 array('F') with bounds (n, n)]

Returns

w [rank-1 array('f') with bounds (n)]

z [rank-2 array('F') with bounds ((compute_v?MAX(0,n):0), (compute_v?(*range=='I'?iu-il+1:MAX(1,n)):0))]]

m [int]

isuppz [rank-1 array('i') with bounds (2*max(1, n))]

info [int]

Other Parameters

compute_v [input int, optional] Default 1

range [input string(len=1), optional] Default 'A'

lower [input int, optional] Default 0

overwrite_a [input int, optional] Default 0

vl [input float, optional] Default 0.0

vu [input float, optional] Default 1.0

il [input int, optional] Default 1

iu [input int, optional] Default n

abstol [input float, optional] Default 0.0

lwork [input int, optional] Default max(2*n, 1)

lrwork [input int, optional] Default max(24*n, 1)

liwork [input int, optional] Default max(1, 10*n)

scipy.linalg.lapack.zheevr

`scipy.linalg.lapack.zheevr` (*a*[, *compute_v*, *range*, *lower*, *vl*, *vu*, *il*, *iu*, *abstol*, *lwork*, *lrwork*, *liwork*, *overwrite_a*]) = <fortran object>

Wrapper for zheevr.

Parameters

a [input rank-2 array('D') with bounds (n, n)]

Returns

w [rank-1 array('d') with bounds (n)]

z [rank-2 array('D') with bounds ((compute_v?MAX(0, n):0), (compute_v?(*range=='I'?iu-il+1:MAX(1, n)):0))]

m [int]

isuppz [rank-1 array('i') with bounds (2*max(1, n))]

info [int]

Other Parameters

compute_v [input int, optional] Default 1

range [input string(len=1), optional] Default 'A'

lower [input int, optional] Default 0

overwrite_a [input int, optional] Default 0

vl [input float, optional] Default 0.0

vu [input float, optional] Default 1.0

il [input int, optional] Default 1

iu [input int, optional] Default n

abstol [input float, optional] Default 0.0

lwork [input int, optional] Default max(2*n, 1)

lrwork [input int, optional] Default max(24*n, 1)

liwork [input int, optional] Default max(1, 10*n)

scipy.linalg.lapack.cheevr_lwork

`scipy.linalg.lapack.cheevr_lwork(n[, lower]) = <fortran object>`
 Wrapper for `cheevr_lwork`.

Parameters

n [input int]

Returns

work [complex]
rwork [float]
iwork [int]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zheevr_lwork

`scipy.linalg.lapack.zheevr_lwork(n[, lower]) = <fortran object>`
 Wrapper for `zheevr_lwork`.

Parameters

n [input int]

Returns

work [complex]
rwork [float]
iwork [int]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.cheevx

`scipy.linalg.lapack.cheevx(a[, compute_v, range, lower, vl, vu, il, iu, abstol, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `cheevx`.

Parameters

a [input rank-2 array('F') with bounds (n, n)]

Returns

w [rank-1 array('f') with bounds (n)]
z [rank-2 array('F') with bounds ((compute_v*n), (compute_v?(*range=='I'?iu-il+1:MAX(1,n)):0))]
m [int]
ifail [rank-1 array('i') with bounds (compute_v*n)]
info [int]

Other Parameters

compute_v [input int, optional] Default 1
range [input string(len=1), optional] Default 'A'
lower [input int, optional] Default 0
overwrite_a
 [input int, optional] Default 0
vl [input float, optional] Default 0.0
vu [input float, optional] Default 1.0
il [input int, optional] Default 1
iu [input int, optional] Default n
abstol [input float, optional] Default 0.0
lwork [input int, optional] Default $\max(2*n, 1)$

scipy.linalg.lapack.zheevx

`scipy.linalg.lapack.zheevx(a[, compute_v, range, lower, vl, vu, il, iu, abstol, lwork, overwrite_a])`
 = <fortran object>

Wrapper for zheevx.

Parameters

a [input rank-2 array('D') with bounds (n, n)]

Returns

w [rank-1 array('d') with bounds (n)]
z [rank-2 array('D') with bounds ((compute_v*n), (compute_v?(*range=='I'? iu-il+1:MAX(1,n)):0))]

m [int]
ifail [rank-1 array('i') with bounds (compute_v*n)]
info [int]

Other Parameters

compute_v [input int, optional] Default 1
range [input string(len=1), optional] Default 'A'
lower [input int, optional] Default 0
overwrite_a
 [input int, optional] Default 0
vl [input float, optional] Default 0.0
vu [input float, optional] Default 1.0
il [input int, optional] Default 1
iu [input int, optional] Default n
abstol [input float, optional] Default 0.0
lwork [input int, optional] Default $\max(2*n, 1)$

scipy.linalg.lapack.cheevx_lwork

`scipy.linalg.lapack.cheevx_lwork(n[, lower]) = <fortran object>`
 Wrapper for `cheevx_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zheevx_lwork

`scipy.linalg.lapack.zheevx_lwork(n[, lower]) = <fortran object>`
 Wrapper for `zheevx_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.chegst

`scipy.linalg.lapack.chegst(a, b[, itype, lower, overwrite_a]) = <fortran object>`
 Wrapper for `chegst`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]

b [input rank-2 array('F') with bounds (n,n)]

Returns

c [rank-2 array('F') with bounds (n,n) and a storage]

info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0

itype [input int, optional] Default: 1

lower [input int, optional] Default: 0

scipy.linalg.lapack.zhegst

`scipy.linalg.lapack.zhegst` (*a*, *b*[, *itype*, *lower*, *overwrite_a*]) = <fortran object>
 Wrapper for zhegst.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (n,n)]

Returns

c [rank-2 array('D') with bounds (n,n) and a storage]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
itype [input int, optional] Default: 1
lower [input int, optional] Default: 0

scipy.linalg.lapack.chegv

`scipy.linalg.lapack.chegv` (*a*, *b*[, *itype*, *jobz*, *uplo*, *lwork*, *overwrite_a*, *overwrite_b*]) = <fortran object>
 Wrapper for chegv.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
b [input rank-2 array('F') with bounds (n,n)]

Returns

w [rank-1 array('f') with bounds (n)]
v [rank-2 array('F') with bounds (n,n) and a storage]
info [int]

Other Parameters

itype [input int, optional] Default: 1
jobz [input string(len=1), optional] Default: 'V'
uplo [input string(len=1), optional] Default: 'L'
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(2*n-1,1)

scipy.linalg.lapack.zhegv

`scipy.linalg.lapack.zhegv(a, b[, itype, jobz, uplo, lwork, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for zhegv.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (n,n)]

Returns

w [rank-1 array('d') with bounds (n)]
v [rank-2 array('D') with bounds (n,n) and a storage]
info [int]

Other Parameters

itype [input int, optional] Default: 1
jobz [input string(len=1), optional] Default: 'V'
uplo [input string(len=1), optional] Default: 'L'
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(2*n-1,1)

scipy.linalg.lapack.chegv_lwork

`scipy.linalg.lapack.chegv_lwork(n[, uplo]) = <fortran object>`

Wrapper for chegv_lwork.

Parameters

n [input int]

Returns

work [complex]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'L'

scipy.linalg.lapack.zhegv_lwork

`scipy.linalg.lapack.zhegv_lwork(n[, uplo]) = <fortran object>`

Wrapper for zhegv_lwork.

Parameters

n [input int]

Returns

work [complex]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'L'

scipy.linalg.lapack.chegvd

`scipy.linalg.lapack.chegvd(a, b[, itype, jobz, uplo, lwork, lrwork, liwork, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `chegvd`.

Parameters

a [input rank-2 array('F') with bounds (n, n)]
b [input rank-2 array('F') with bounds (n, n)]

Returns

w [rank-1 array('f') with bounds (n)]
v [rank-2 array('F') with bounds (n, n) with a storage]
info [int]

Other Parameters

itype [input int, optional] Default 1
jobz [input string(len=1), optional] Default 'V'
uplo [input string(len=1), optional] Default 'L'
overwrite_a [input int, optional] Default 0
overwrite_b [input int, optional] Default 0
lwork [input int, optional] Default $(*jobz == 'N' ? n + 1 : n * (n + 2))$
lrwork [input int, optional] Default $\max(*jobz == 'N' ? n : 2 * n * n + 5 * n + 1, 1)$
liwork [input int, optional] Default $(*jobz == 'N' ? 1 : 5 * n + 3)$

scipy.linalg.lapack.zhegvd

`scipy.linalg.lapack.zhegvd(a, b[, itype, jobz, uplo, lwork, lrwork, liwork, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `zhegvd`.

Parameters

a [input rank-2 array('D') with bounds (n, n)]
b [input rank-2 array('D') with bounds (n, n)]

Returns

w [rank-1 array('d') with bounds (n)]
v [rank-2 array('D') with bounds (n, n) with a storage]
info [int]

Other Parameters

itype [input int, optional] Default 1
jobz [input string(len=1), optional] Default 'V'
uplo [input string(len=1), optional] Default 'L'
overwrite_a [input int, optional] Default 0

overwrite_b [input int, optional] Default 0
lwork [input int, optional] Default $(*jobz=='N'?n+1:n*(n+2))$
lrwork [input int, optional] Default $\max(*jobz=='N'?n:2*n*n+5*n+1), 1)$
liwork [input int, optional] Default $(*jobz=='N'?1:5*n+3)$

scipy.linalg.lapack.chegvx

`scipy.linalg.lapack.chegvx` (*a*, *b*[, *itype*, *jobz*, *range*, *uplo*, *vl*, *vu*, *il*, *iu*, *abstol*, *lwork*, *overwrite_a*, *overwrite_b*]) = <fortran object>

Wrapper for `chegvx`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
b [input rank-2 array('F') with bounds (n,n)]

Returns

w [rank-1 array('f') with bounds (n)]
z [rank-2 array('F') with bounds ((*jobz*[0]=='V'?MAX(0,n):0),(*jobz*[0]=='V'?(*range*[0]=='T'?*iu*-*il*+1:MAX(1,n)):0))]
m [int]
ifail [rank-1 array('i') with bounds ((*jobz*[0]=='N'?0:n))]
info [int]

Other Parameters

itype [input int, optional] Default: 1
jobz [input string(len=1), optional] Default: 'V'
range [input string(len=1), optional] Default: 'A'
uplo [input string(len=1), optional] Default: 'L'
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
vl [input float, optional] Default: 0.0
vu [input float, optional] Default: 1.0
il [input int, optional] Default: 1
iu [input int, optional] Default: n
abstol [input float, optional] Default: 0.0
lwork [input int, optional] Default: $\max(2*n,1)$

scipy.linalg.lapack.zhegvx

`scipy.linalg.lapack.zhegvx` (*a*, *b*[, *itype*, *jobz*, *range*, *uplo*, *vl*, *vu*, *il*, *iu*, *abstol*, *lwork*, *overwrite_a*, *overwrite_b*]) = <fortran object>

Wrapper for `zhegvx`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (n,n)]

Returns

w [rank-1 array('d') with bounds (n)]

z [rank-2 array('D') with bounds ((jobz[0]=='V'?MAX(0,n):0),(jobz[0]=='V'?((range[0]=='I'?iu-il+1:MAX(1,n)):0)))]

m [int]

ifail [rank-1 array('i') with bounds ((jobz[0]=='N'?0:n))]

info [int]

Other Parameters

itype [input int, optional] Default: 1

jobz [input string(len=1), optional] Default: 'V'

range [input string(len=1), optional] Default: 'A'

uplo [input string(len=1), optional] Default: 'L'

overwrite_a
[input int, optional] Default: 0

overwrite_b
[input int, optional] Default: 0

vl [input float, optional] Default: 0.0

vu [input float, optional] Default: 1.0

il [input int, optional] Default: 1

iu [input int, optional] Default: n

abstol [input float, optional] Default: 0.0

lwork [input int, optional] Default: max(2*n,1)

scipy.linalg.lapack.chegvx_lwork

`scipy.linalg.lapack.chegvx_lwork(n[, uplo]) = <fortran object>`
Wrapper for `chegvx_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'L'

scipy.linalg.lapack.zhegvx_lwork

`scipy.linalg.lapack.zhegvx_lwork(n[, uplo]) = <fortran object>`
Wrapper for `zhegvx_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'L'

scipy.linalg.lapack.chesv

`scipy.linalg.lapack.chesv(a, b[, lwork, lower, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `chesv`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
b [input rank-2 array('F') with bounds (n,nrhs)]

Returns

uduh [rank-2 array('F') with bounds (n,n) and a storage]
ipiv [rank-1 array('i') with bounds (n)]
x [rank-2 array('F') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(n,1)
lower [input int, optional] Default: 0

scipy.linalg.lapack.zhesv

`scipy.linalg.lapack.zhesv(a, b[, lwork, lower, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `zhesv`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (n,nrhs)]

Returns

uduh [rank-2 array('D') with bounds (n,n) and a storage]
ipiv [rank-1 array('i') with bounds (n)]
x [rank-2 array('D') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(n,1)
lower [input int, optional] Default: 0

scipy.linalg.lapack.chesv_lwork

`scipy.linalg.lapack.chesv_lwork` (n [, $lower$]) = <fortran object>
 Wrapper for `chesv_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zhesv_lwork

`scipy.linalg.lapack.zhesv_lwork` (n [, $lower$]) = <fortran object>
 Wrapper for `zhesv_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.chesvx

`scipy.linalg.lapack.chesvx` (a , b [, af , $ipiv$, $lwork$, $factored$, $lower$, $overwrite_a$, $overwrite_b$]) =
 <fortran object>

Wrapper for `chesvx`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]

b [input rank-2 array('F') with bounds (n,nrhs)]

Returns

uduh [rank-2 array('F') with bounds (n,n) and af storage]

ipiv [rank-1 array('i') with bounds (n)]

x [rank-2 array('F') with bounds (n,nrhs)]

rcond [float]

ferr [rank-1 array('f') with bounds (nrhs)]

berr [rank-1 array('f') with bounds (nrhs)]

info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

af [input rank-2 array('F') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(2*n,1)
factored [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.zhesvx

`scipy.linalg.lapack.zhesvx(a, b[, af, ipiv, lwork, factored, lower, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for zhesvx.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (n,nrhs)]

Returns

uduh [rank-2 array('D') with bounds (n,n) and af storage]
ipiv [rank-1 array('i') with bounds (n)]
x [rank-2 array('D') with bounds (n,nrhs)]
rcond [float]
ferr [rank-1 array('d') with bounds (nrhs)]
berr [rank-1 array('d') with bounds (nrhs)]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
af [input rank-2 array('D') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(2*n,1)
factored [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.chesvx_lwork

`scipy.linalg.lapack.chesvx_lwork(n[, lower]) = <fortran object>`

Wrapper for chesvx_lwork.

Parameters

n [input int]

Returns

work [complex]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zhesvx_lwork

`scipy.linalg.lapack.zhesvx_lwork(n[, lower]) = <fortran object>`
 Wrapper for `zhesvx_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.chetrd

`scipy.linalg.lapack.chetrd(a[, lower, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `chetrd`.

Parameters

a [input rank-2 array('F') with bounds (lda,n)]

Returns

c [rank-2 array('F') with bounds (lda,n) and a storage]

d [rank-1 array('f') with bounds (n)]

e [rank-1 array('f') with bounds (n - 1)]

tau [rank-1 array('F') with bounds (n - 1)]

info [int]

Other Parameters

lower [input int, optional] Default: 0

overwrite_a [input int, optional] Default: 0

lwork [input int, optional] Default: MAX(n,1)

scipy.linalg.lapack.zhetrd

`scipy.linalg.lapack.zhetrd(a[, lower, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `zhetrd`.

Parameters

a [input rank-2 array('D') with bounds (lda,n)]

Returns

c [rank-2 array('D') with bounds (lda,n) and a storage]

d [rank-1 array('d') with bounds (n)]

e [rank-1 array('d') with bounds (n - 1)]

tau [rank-1 array('D') with bounds (n - 1)]

info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: MAX(n,1)

scipy.linalg.lapack.chetrd_lwork

`scipy.linalg.lapack.chetrd_lwork(n[, lower]) = <fortran object>`
 Wrapper for `chetrd_lwork`.

Parameters

n [input int]

Returns

work [complex]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zhetrd_lwork

`scipy.linalg.lapack.zhetrd_lwork(n[, lower]) = <fortran object>`
 Wrapper for `zhetrd_lwork`.

Parameters

n [input int]

Returns

work [complex]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.chetrf

`scipy.linalg.lapack.chetrf(a[, lower, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `chetrf`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]

Returns

ldu [rank-2 array('F') with bounds (n,n) and a storage]
ipiv [rank-1 array('i') with bounds (n)]
info [int]

Other Parameters

lower [input int, optional] Default: 0

overwrite_a
 [input int, optional] Default: 0
lwork [input int, optional] Default: max(n,1)

scipy.linalg.lapack.zhetrf

`scipy.linalg.lapack.zhetrf(a[, lower, lwork, overwrite_a]) = <fortran object>`
 Wrapper for zhetrf.

Parameters

a [input rank-2 array('D') with bounds (n,n)]

Returns

ldu [rank-2 array('D') with bounds (n,n) and a storage]
ipiv [rank-1 array('i') with bounds (n)]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_a
 [input int, optional] Default: 0
lwork [input int, optional] Default: max(n,1)

scipy.linalg.lapack.chetrf_lwork

`scipy.linalg.lapack.chetrf_lwork(n[, lower]) = <fortran object>`
 Wrapper for chetrf_lwork.

Parameters

n [input int]

Returns

work [complex]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zhetrf_lwork

`scipy.linalg.lapack.zhetrf_lwork(n[, lower]) = <fortran object>`
 Wrapper for zhetrf_lwork.

Parameters

n [input int]

Returns

work [complex]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.chfrk

scipy.linalg.lapack.**chfrk** (*n, k, alpha, a, beta, c*[, *transr, uplo, trans, overwrite_c*]) = <fortran object>

Wrapper for chfrk.

Parameters

n [input int]
k [input int]
alpha [input float]
a [input rank-2 array('F') with bounds (lda,ka)]
beta [input float]
c [input rank-1 array('F') with bounds (nt)]

Returns

cout [rank-1 array('F') with bounds (nt) and c storage]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
trans [input string(len=1), optional] Default: 'N'
overwrite_c [input int, optional] Default: 0

scipy.linalg.lapack.zhfrk

scipy.linalg.lapack.**zhfrk** (*n, k, alpha, a, beta, c*[, *transr, uplo, trans, overwrite_c*]) = <fortran object>

Wrapper for zhfrk.

Parameters

n [input int]
k [input int]
alpha [input float]
a [input rank-2 array('D') with bounds (lda,ka)]
beta [input float]
c [input rank-1 array('D') with bounds (nt)]

Returns

cout [rank-1 array('D') with bounds (nt) and c storage]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
trans [input string(len=1), optional] Default: 'N'
overwrite_c [input int, optional] Default: 0

scipy.linalg.lapack.slamch

`scipy.linalg.lapack.slamch` (*cmach*) = <fortran slamch>
 Wrapper for slamch.

Parameters

cmach [input string(len=1)]

Returns

slamch [float]

scipy.linalg.lapack.dlamch

`scipy.linalg.lapack.dlamch` (*cmach*) = <fortran dlamch>
 Wrapper for dlamch.

Parameters

cmach [input string(len=1)]

Returns

dlamch [float]

scipy.linalg.lapack.slange

`scipy.linalg.lapack.slange` (*norm, a*) = <fortran slange>
 Wrapper for slange.

Parameters

norm [input string(len=1)]

a [input rank-2 array('f') with bounds (m,n)]

Returns

n2 [float]

scipy.linalg.lapack.dlange

`scipy.linalg.lapack.dlange` (*norm, a*) = <fortran dlange>
 Wrapper for dlange.

Parameters

norm [input string(len=1)]

a [input rank-2 array('d') with bounds (m,n)]

Returns

n2 [float]

scipy.linalg.lapack.clange

`scipy.linalg.lapack.clange` (*norm, a*) = <fortran clange>
 Wrapper for `clange`.

Parameters

norm [input string(len=1)]
a [input rank-2 array('F') with bounds (m,n)]

Returns

n2 [float]

scipy.linalg.lapack.zlange

`scipy.linalg.lapack.zlange` (*norm, a*) = <fortran zlange>
 Wrapper for `zlange`.

Parameters

norm [input string(len=1)]
a [input rank-2 array('D') with bounds (m,n)]

Returns

n2 [float]

scipy.linalg.lapack.slarf

`scipy.linalg.lapack.slarf` (*v, tau, c, work[, side, incv, overwrite_c]*) = <fortran object>
 Wrapper for `slarf`.

Parameters

v [input rank-1 array('f') with bounds ((side[0]=='L'?(1 + (m-1)*abs(incv)):(1 + (n-1)*abs(incv))))]
tau [input float]
c [input rank-2 array('f') with bounds (m,n)]
work [input rank-1 array('f') with bounds (lwork)]

Returns

c [rank-2 array('f') with bounds (m,n)]

Other Parameters

side [input string(len=1), optional] Default: 'L'
incv [input int, optional] Default: 1
overwrite_c [input int, optional] Default: 0

scipy.linalg.lapack.dlarf

`scipy.linalg.lapack.dlarf(v, tau, c, work[, side, incv, overwrite_c]) = <fortran object>`
 Wrapper for `dlarf`.

Parameters

- v** [input rank-1 array('d') with bounds ((side[0]=='L'?(1 + (m-1)*abs(incv)):(1 + (n-1)*abs(incv))))]
- tau** [input float]
- c** [input rank-2 array('d') with bounds (m,n)]
- work** [input rank-1 array('d') with bounds (lwork)]

Returns

- c** [rank-2 array('d') with bounds (m,n)]

Other Parameters

- side** [input string(len=1), optional] Default: 'L'
- incv** [input int, optional] Default: 1
- overwrite_c** [input int, optional] Default: 0

scipy.linalg.lapack.clarf

`scipy.linalg.lapack.clarf(v, tau, c, work[, side, incv, overwrite_c]) = <fortran object>`
 Wrapper for `clarf`.

Parameters

- v** [input rank-1 array('F') with bounds ((side[0]=='L'?(1 + (m-1)*abs(incv)):(1 + (n-1)*abs(incv))))]
- tau** [input complex]
- c** [input rank-2 array('F') with bounds (m,n)]
- work** [input rank-1 array('F') with bounds (lwork)]

Returns

- c** [rank-2 array('F') with bounds (m,n)]

Other Parameters

- side** [input string(len=1), optional] Default: 'L'
- incv** [input int, optional] Default: 1
- overwrite_c** [input int, optional] Default: 0

scipy.linalg.lapack.zlarf

`scipy.linalg.lapack.zlarf(v, tau, c, work[, side, incv, overwrite_c]) = <fortran object>`
 Wrapper for `zlarf`.

Parameters

- v** [input rank-1 array('D') with bounds ((side[0]=='L'?(1 + (m-1)*abs(incv)):(1 + (n-1)*abs(incv))))]
- tau** [input complex]
- c** [input rank-2 array('D') with bounds (m,n)]

work [input rank-1 array('D') with bounds (lwork)]

Returns

c [rank-2 array('D') with bounds (m,n)]

Other Parameters

side [input string(len=1), optional] Default: 'L'

incv [input int, optional] Default: 1

overwrite_c
[input int, optional] Default: 0

scipy.linalg.lapack.slarfg

`scipy.linalg.lapack.slarfg(n, alpha, x[, incx, overwrite_x]) = <fortran object>`
 Wrapper for slarfg.

Parameters

n [input int]
alpha [input float]
x [input rank-1 array('f') with bounds (lx)]

Returns

alpha [float]
x [rank-1 array('f') with bounds (lx)]
tau [float]

Other Parameters

overwrite_x
[input int, optional] Default: 0
incx [input int, optional] Default: 1

scipy.linalg.lapack.dlarfg

`scipy.linalg.lapack.dlarfg(n, alpha, x[, incx, overwrite_x]) = <fortran object>`
 Wrapper for dlarfg.

Parameters

n [input int]
alpha [input float]
x [input rank-1 array('d') with bounds (lx)]

Returns

alpha [float]
x [rank-1 array('d') with bounds (lx)]
tau [float]

Other Parameters

overwrite_x
[input int, optional] Default: 0
incx [input int, optional] Default: 1

scipy.linalg.lapack.clarfg

`scipy.linalg.lapack.clarfg(n, alpha, x[, incx, overwrite_x]) = <fortran object>`
 Wrapper for clarfg.

Parameters

n [input int]
alpha [input complex]
x [input rank-1 array('F') with bounds (lx)]

Returns

alpha [complex]
x [rank-1 array('F') with bounds (lx)]
tau [complex]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1

scipy.linalg.lapack.zlarfg

`scipy.linalg.lapack.zlarfg(n, alpha, x[, incx, overwrite_x]) = <fortran object>`
 Wrapper for zlarfg.

Parameters

n [input int]
alpha [input complex]
x [input rank-1 array('D') with bounds (lx)]

Returns

alpha [complex]
x [rank-1 array('D') with bounds (lx)]
tau [complex]

Other Parameters

overwrite_x [input int, optional] Default: 0
incx [input int, optional] Default: 1

scipy.linalg.lapack.slartg

`scipy.linalg.lapack.slartg(f, g) = <fortran object>`
 Wrapper for slartg.

Parameters

f [input float]
g [input float]

Returns

cs [float]
sn [float]

r [float]

scipy.linalg.lapack.dlartg

`scipy.linalg.lapack.dlartg(f, g) = <fortran object>`
Wrapper for dlartg.

Parameters

f [input float]
g [input float]

Returns

cs [float]
sn [float]
r [float]

scipy.linalg.lapack.clartg

`scipy.linalg.lapack.clartg(f, g) = <fortran object>`
Wrapper for clartg.

Parameters

f [input complex]
g [input complex]

Returns

cs [float]
sn [complex]
r [complex]

scipy.linalg.lapack.zlartg

`scipy.linalg.lapack.zlartg(f, g) = <fortran object>`
Wrapper for zlartg.

Parameters

f [input complex]
g [input complex]

Returns

cs [float]
sn [complex]
r [complex]

scipy.linalg.lapack.slasd4

`scipy.linalg.lapack.slasd4` (*i*, *d*, *z*[, *rho*]) = <fortran object>
 Wrapper for slasd4.

Parameters

i [input int]
d [input rank-1 array('f') with bounds (n)]
z [input rank-1 array('f') with bounds (n)]

Returns

delta [rank-1 array('f') with bounds (n)]
sigma [float]
work [rank-1 array('f') with bounds (n)]
info [int]

Other Parameters

rho [input float, optional] Default: 1.0

scipy.linalg.lapack.dlasd4

`scipy.linalg.lapack.dlasd4` (*i*, *d*, *z*[, *rho*]) = <fortran object>
 Wrapper for dlasd4.

Parameters

i [input int]
d [input rank-1 array('d') with bounds (n)]
z [input rank-1 array('d') with bounds (n)]

Returns

delta [rank-1 array('d') with bounds (n)]
sigma [float]
work [rank-1 array('d') with bounds (n)]
info [int]

Other Parameters

rho [input float, optional] Default: 1.0

scipy.linalg.lapack.slaswp

`scipy.linalg.lapack.slaswp` (*a*, *piv*[, *k1*, *k2*, *off*, *inc*, *overwrite_a*]) = <fortran object>
 Wrapper for slaswp.

Parameters

a [input rank-2 array('f') with bounds (nrows,n)]
piv [input rank-1 array('i') with bounds (npiv)]

Returns

a [rank-2 array('f') with bounds (nrows,n)]

Other Parameters

overwrite_a [input int, optional] Default: 0
k1 [input int, optional] Default: 0
k2 [input int, optional] Default: npiv-1
off [input int, optional] Default: 0
inc [input int, optional] Default: 1

scipy.linalg.lapack.dlaswp

`scipy.linalg.lapack.dlaswp(a, piv[, k1, k2, off, inc, overwrite_a]) = <fortran object>`
 Wrapper for dlaswp.

Parameters

a [input rank-2 array('d') with bounds (nrows,n)]
piv [input rank-1 array('i') with bounds (npiv)]

Returns

a [rank-2 array('d') with bounds (nrows,n)]

Other Parameters

overwrite_a [input int, optional] Default: 0
k1 [input int, optional] Default: 0
k2 [input int, optional] Default: npiv-1
off [input int, optional] Default: 0
inc [input int, optional] Default: 1

scipy.linalg.lapack.claswp

`scipy.linalg.lapack.claswp(a, piv[, k1, k2, off, inc, overwrite_a]) = <fortran object>`
 Wrapper for claswp.

Parameters

a [input rank-2 array('F') with bounds (nrows,n)]
piv [input rank-1 array('i') with bounds (npiv)]

Returns

a [rank-2 array('F') with bounds (nrows,n)]

Other Parameters

overwrite_a [input int, optional] Default: 0
k1 [input int, optional] Default: 0
k2 [input int, optional] Default: npiv-1
off [input int, optional] Default: 0
inc [input int, optional] Default: 1

scipy.linalg.lapack.zlaswp

`scipy.linalg.lapack.zlaswp(a, piv[, k1, k2, off, inc, overwrite_a]) = <fortran object>`
 Wrapper for `zlaswp`.

Parameters

a [input rank-2 array('D') with bounds (nrows,n)]
piv [input rank-1 array('i') with bounds (npiv)]

Returns

a [rank-2 array('D') with bounds (nrows,n)]

Other Parameters

overwrite_a [input int, optional] Default: 0
k1 [input int, optional] Default: 0
k2 [input int, optional] Default: npiv-1
off [input int, optional] Default: 0
inc [input int, optional] Default: 1

scipy.linalg.lapack.slauum

`scipy.linalg.lapack.slauum(c[, lower, overwrite_c]) = <fortran object>`
 Wrapper for `slauum`.

Parameters

c [input rank-2 array('f') with bounds (n,n)]

Returns

a [rank-2 array('f') with bounds (n,n) and c storage]
info [int]

Other Parameters

overwrite_c [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.dlauum

`scipy.linalg.lapack.dlauum(c[, lower, overwrite_c]) = <fortran object>`
 Wrapper for `dlauum`.

Parameters

c [input rank-2 array('d') with bounds (n,n)]

Returns

a [rank-2 array('d') with bounds (n,n) and c storage]
info [int]

Other Parameters

overwrite_c [input int, optional] Default: 0

lower [input int, optional] Default: 0

scipy.linalg.lapack.clauum

`scipy.linalg.lapack.clauum(c[, lower, overwrite_c]) = <fortran object>`

Wrapper for clauum.

Parameters

c [input rank-2 array('F') with bounds (n,n)]

Returns

a [rank-2 array('F') with bounds (n,n) and c storage]

info [int]

Other Parameters

overwrite_c [input int, optional] Default: 0

lower [input int, optional] Default: 0

scipy.linalg.lapack.zlauum

`scipy.linalg.lapack.zlauum(c[, lower, overwrite_c]) = <fortran object>`

Wrapper for zlauum.

Parameters

c [input rank-2 array('D') with bounds (n,n)]

Returns

a [rank-2 array('D') with bounds (n,n) and c storage]

info [int]

Other Parameters

overwrite_c [input int, optional] Default: 0

lower [input int, optional] Default: 0

scipy.linalg.lapack.sorcscd

`scipy.linalg.lapack.sorcscd(x11, x12, x21, x22[, compute_u1, compute_u2, compute_v1t, compute_v2t, trans, signs, lwork, overwrite_x11, overwrite_x12, overwrite_x21, overwrite_x22]) = <fortran object>`

Wrapper for sorcscd.

Parameters

x11 [input rank-2 array('f') with bounds (p,q)]

x12 [input rank-2 array('f') with bounds (p,mmq)]

x21 [input rank-2 array('f') with bounds (mmp,q)]

x22 [input rank-2 array('f') with bounds (mmp,mmq)]

Returns

cs11 [rank-2 array('f') with bounds (p,q) and x11 storage]

cs12	[rank-2 array('f') with bounds (p,mmq) and x12 storage]
cs21	[rank-2 array('f') with bounds (mmp,q) and x21 storage]
cs22	[rank-2 array('f') with bounds (mmp,mmq) and x22 storage]
theta	[rank-1 array('f') with bounds (min(min(p,mmp),min(q,mmq)))]
u1	[rank-2 array('f') with bounds ((compute_u1?p:0),(compute_u1?p:0))]
u2	[rank-2 array('f') with bounds ((compute_u2?mmp:0),(compute_u2?mmp:0))]
v1t	[rank-2 array('f') with bounds ((compute_v1t?q:0),(compute_v1t?q:0))]
v2t	[rank-2 array('f') with bounds ((compute_v2t?mmq:0),(compute_v2t?mmq:0))]
info	[int]

Other Parameters

compute_u1	[input int, optional] Default: 1
compute_u2	[input int, optional] Default: 1
compute_v1t	[input int, optional] Default: 1
compute_v2t	[input int, optional] Default: 1
trans	[input int, optional] Default: 0
signs	[input int, optional] Default: 0
overwrite_x11	[input int, optional] Default: 0
overwrite_x12	[input int, optional] Default: 0
overwrite_x21	[input int, optional] Default: 0
overwrite_x22	[input int, optional] Default: 0
lwork	[input int, optional] Default: $2+2*m+5*MAX(1,q-1)+4*MAX(1,q)+8*q$

scipy.linalg.lapack.dorcscd

`scipy.linalg.lapack.dorcscd(x11, x12, x21, x22[, compute_u1, compute_u2, compute_v1t, compute_v2t, trans, signs, lwork, overwrite_x11, overwrite_x12, overwrite_x21, overwrite_x22]) = <fortran object>`

Wrapper for `dorcscd`.

Parameters

x11	[input rank-2 array('d') with bounds (p,q)]
x12	[input rank-2 array('d') with bounds (p,mmq)]
x21	[input rank-2 array('d') with bounds (mmp,q)]
x22	[input rank-2 array('d') with bounds (mmp,mmq)]

Returns

cs11	[rank-2 array('d') with bounds (p,q) and x11 storage]
cs12	[rank-2 array('d') with bounds (p,mmq) and x12 storage]
cs21	[rank-2 array('d') with bounds (mmp,q) and x21 storage]
cs22	[rank-2 array('d') with bounds (mmp,mmq) and x22 storage]
theta	[rank-1 array('d') with bounds (min(min(p,mmp),min(q,mmq)))]
u1	[rank-2 array('d') with bounds ((compute_u1?p:0),(compute_u1?p:0))]
u2	[rank-2 array('d') with bounds ((compute_u2?mmp:0),(compute_u2?mmp:0))]
v1t	[rank-2 array('d') with bounds ((compute_v1t?q:0),(compute_v1t?q:0))]

v2t [rank-2 array('d') with bounds ((compute_v2t?mmq:0),(compute_v2t?mmq:0))]
info [int]

Other Parameters

compute_u1 [input int, optional] Default: 1
compute_u2 [input int, optional] Default: 1
compute_v1t [input int, optional] Default: 1
compute_v2t [input int, optional] Default: 1
trans [input int, optional] Default: 0
signs [input int, optional] Default: 0
overwrite_x11 [input int, optional] Default: 0
overwrite_x12 [input int, optional] Default: 0
overwrite_x21 [input int, optional] Default: 0
overwrite_x22 [input int, optional] Default: 0
lwork [input int, optional] Default: $2+2*m+5*MAX(1,q-1)+4*MAX(1,q)+8*q$

scipy.linalg.lapack.sorcsd_lwork

`scipy.linalg.lapack.sorcsd_lwork(m, p, q) = <fortran object>`
 Wrapper for sorcsd_lwork.

Parameters

m [input int]
p [input int]
q [input int]

Returns

work [float]
info [int]

scipy.linalg.lapack.dorcsd_lwork

`scipy.linalg.lapack.dorcsd_lwork(m, p, q) = <fortran object>`
 Wrapper for dorcsd_lwork.

Parameters

m [input int]
p [input int]
q [input int]

Returns

work [float]
info [int]

scipy.linalg.lapack.sorghr

`scipy.linalg.lapack.sorghr` (*a*, *tau*[, *lo*, *hi*, *lwork*, *overwrite_a*]) = <fortran object>
 Wrapper for `sorghr`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]
tau [input rank-1 array('f') with bounds (n - 1)]

Returns

ht [rank-2 array('f') with bounds (n,n) and a storage]
info [int]

Other Parameters

lo [input int, optional] Default: 0
hi [input int, optional] Default: n-1
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(hi-lo,1)

scipy.linalg.lapack.dorghr

`scipy.linalg.lapack.dorghr` (*a*, *tau*[, *lo*, *hi*, *lwork*, *overwrite_a*]) = <fortran object>
 Wrapper for `dorghr`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
tau [input rank-1 array('d') with bounds (n - 1)]

Returns

ht [rank-2 array('d') with bounds (n,n) and a storage]
info [int]

Other Parameters

lo [input int, optional] Default: 0
hi [input int, optional] Default: n-1
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(hi-lo,1)

scipy.linalg.lapack.sorghr_lwork

`scipy.linalg.lapack.sorghr_lwork` (*n*[, *lo*, *hi*]) = <fortran object>
 Wrapper for `sorghr_lwork`.

Parameters

n [input int]

Returns

work [float]
info [int]

Other Parameters

lo [input int, optional] Default: 0
hi [input int, optional] Default: n-1

scipy.linalg.lapack.dorghr_lwork

`scipy.linalg.lapack.dorghr_lwork(n[, lo, hi]) = <fortran object>`
 Wrapper for `dorghr_lwork`.

Parameters

n [input int]

Returns

work [float]
info [int]

Other Parameters

lo [input int, optional] Default: 0
hi [input int, optional] Default: n-1

scipy.linalg.lapack.sorgqr

`scipy.linalg.lapack.sorgqr(a, tau[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `sorgqr`.

Parameters

a [input rank-2 array('f') with bounds (m,n)]
tau [input rank-1 array('f') with bounds (k)]

Returns

q [rank-2 array('f') with bounds (m,n) and a storage]
work [rank-1 array('f') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)

scipy.linalg.lapack.dorgqr

`scipy.linalg.lapack.dorgqr(a, tau[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `dorgqr`.

Parameters

a [input rank-2 array('d') with bounds (m,n)]
tau [input rank-1 array('d') with bounds (k)]

Returns

q [rank-2 array('d') with bounds (m,n) and a storage]
work [rank-1 array('d') with bounds (MAX(lwork,1))]

info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

lwork [input int, optional] Default: max(3*n,1)

scipy.linalg.lapack.sorgrq

`scipy.linalg.lapack.sorgrq(a, tau[, lwork, overwrite_a]) = <fortran object>`
Wrapper for sorgrq.

Parameters

a [input rank-2 array('f') with bounds (m,n)]

tau [input rank-1 array('f') with bounds (k)]

Returns

q [rank-2 array('f') with bounds (m,n) and a storage]

work [rank-1 array('f') with bounds (MAX(lwork,1))]

info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

lwork [input int, optional] Default: max(3*m,1)

scipy.linalg.lapack.dorgrq

`scipy.linalg.lapack.dorgrq(a, tau[, lwork, overwrite_a]) = <fortran object>`
Wrapper for dorgrq.

Parameters

a [input rank-2 array('d') with bounds (m,n)]

tau [input rank-1 array('d') with bounds (k)]

Returns

q [rank-2 array('d') with bounds (m,n) and a storage]

work [rank-1 array('d') with bounds (MAX(lwork,1))]

info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

lwork [input int, optional] Default: max(3*m,1)

scipy.linalg.lapack.sormqr

`scipy.linalg.lapack.sormqr` (*side, trans, a, tau, c, lwork*[, *overwrite_c*]) = <fortran object>
Wrapper for sormqr.

Parameters

side [input string(len=1)]
trans [input string(len=1)]
a [input rank-2 array('f') with bounds (lda,k)]
tau [input rank-1 array('f') with bounds (k)]
c [input rank-2 array('f') with bounds (ldc,n)]
lwork [input int]

Returns

cq [rank-2 array('f') with bounds (ldc,n) and c storage]
work [rank-1 array('f') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_c
[input int, optional] Default: 0

scipy.linalg.lapack.dormqr

`scipy.linalg.lapack.dormqr` (*side, trans, a, tau, c, lwork*[, *overwrite_c*]) = <fortran object>
Wrapper for dormqr.

Parameters

side [input string(len=1)]
trans [input string(len=1)]
a [input rank-2 array('d') with bounds (lda,k)]
tau [input rank-1 array('d') with bounds (k)]
c [input rank-2 array('d') with bounds (ldc,n)]
lwork [input int]

Returns

cq [rank-2 array('d') with bounds (ldc,n) and c storage]
work [rank-1 array('d') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_c
[input int, optional] Default: 0

scipy.linalg.lapack.sormrz

`scipy.linalg.lapack.sormrz` (*a*, *tau*, *c*[, *side*, *trans*, *lwork*, *overwrite_c*]) = <fortran object>
 Wrapper for `sormrz`.

Parameters

a [input rank-2 array('f') with bounds (k,nt)]
tau [input rank-1 array('f') with bounds (k)]
c [input rank-2 array('f') with bounds (m,n)]

Returns

cq [rank-2 array('f') with bounds (m,n) and c storage]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'
overwrite_c [input int, optional] Default: 0
lwork [input int, optional] Default: MAX((side[0]=='L'?n:m),1)

scipy.linalg.lapack.dormrz

`scipy.linalg.lapack.dormrz` (*a*, *tau*, *c*[, *side*, *trans*, *lwork*, *overwrite_c*]) = <fortran object>
 Wrapper for `dormrz`.

Parameters

a [input rank-2 array('d') with bounds (k,nt)]
tau [input rank-1 array('d') with bounds (k)]
c [input rank-2 array('d') with bounds (m,n)]

Returns

cq [rank-2 array('d') with bounds (m,n) and c storage]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'
overwrite_c [input int, optional] Default: 0
lwork [input int, optional] Default: MAX((side[0]=='L'?n:m),1)

scipy.linalg.lapack.sormrz_lwork

`scipy.linalg.lapack.sormrz_lwork` (*m*, *n*[, *side*, *trans*]) = <fortran object>
 Wrapper for `sormrz_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [float]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'

scipy.linalg.lapack.dormrz_lwork

`scipy.linalg.lapack.dormrz_lwork(m, n[, side, trans]) = <fortran object>`
 Wrapper for `dormrz_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [float]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'

scipy.linalg.lapack.spbsv

`scipy.linalg.lapack.spbsv(ab, b[, lower, ldab, overwrite_ab, overwrite_b]) = <fortran object>`

Wrapper for `spbsv`.

Parameters

ab [input rank-2 array('f') with bounds (ldab,n)]
b [input rank-2 array('f') with bounds (ldb,nrhs)]

Returns

c [rank-2 array('f') with bounds (ldab,n) and ab storage]
x [rank-2 array('f') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ab [input int, optional] Default: 0
ldab [input int, optional] Default: `shape(ab,0)`
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.dpbsv

`scipy.linalg.lapack.dpbsv(ab, b[, lower, ldab, overwrite_ab, overwrite_b]) = <fortran object>`

Wrapper for dpbsv.

Parameters

ab [input rank-2 array('d') with bounds (ldab,n)]
b [input rank-2 array('d') with bounds (ldb,nrhs)]

Returns

c [rank-2 array('d') with bounds (ldab,n) and ab storage]
x [rank-2 array('d') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ab [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.cpbsv

`scipy.linalg.lapack.cpbsv(ab, b[, lower, ldab, overwrite_ab, overwrite_b]) = <fortran object>`

Wrapper for cpbsv.

Parameters

ab [input rank-2 array('F') with bounds (ldab,n)]
b [input rank-2 array('F') with bounds (ldb,nrhs)]

Returns

c [rank-2 array('F') with bounds (ldab,n) and ab storage]
x [rank-2 array('F') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ab [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.zpbsv

`scipy.linalg.lapack.zpbsv(ab, b[, lower, ldab, overwrite_ab, overwrite_b]) = <fortran object>`

Wrapper for zpbsv.

Parameters

ab [input rank-2 array('D') with bounds (ldab,n)]
b [input rank-2 array('D') with bounds (ldb,nrhs)]

Returns

c [rank-2 array('D') with bounds (ldab,n) and ab storage]
x [rank-2 array('D') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ab [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.spbtrf

`scipy.linalg.lapack.spbtrf(ab[, lower, ldab, overwrite_ab]) = <fortran object>`

Wrapper for spbtrf.

Parameters

ab [input rank-2 array('f') with bounds (ldab,n)]

Returns

c [rank-2 array('f') with bounds (ldab,n) and ab storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ab [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)

scipy.linalg.lapack.dpbtrf

`scipy.linalg.lapack.dpbtrf(ab[, lower, ldab, overwrite_ab]) = <fortran object>`

Wrapper for dpbtrf.

Parameters

ab [input rank-2 array('d') with bounds (ldab,n)]

Returns

c [rank-2 array('d') with bounds (ldab,n) and ab storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ab [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)

scipy.linalg.lapack.cpbtrf

`scipy.linalg.lapack.cpbtrf(ab[, lower, ldab, overwrite_ab]) = <fortran object>`
 Wrapper for `cpbtrf`.

Parameters

ab [input rank-2 array('F') with bounds (ldab,n)]

Returns

c [rank-2 array('F') with bounds (ldab,n) and ab storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ab [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)

scipy.linalg.lapack.zpbtrf

`scipy.linalg.lapack.zpbtrf(ab[, lower, ldab, overwrite_ab]) = <fortran object>`
 Wrapper for `zpbtrf`.

Parameters

ab [input rank-2 array('D') with bounds (ldab,n)]

Returns

c [rank-2 array('D') with bounds (ldab,n) and ab storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ab [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)

scipy.linalg.lapack.spbtrs

`scipy.linalg.lapack.spbtrs` (*ab*, *b*[, *lower*, *ldab*, *overwrite_b*]) = <fortran object>
 Wrapper for `spbtrs`.

Parameters

ab [input rank-2 array('f') with bounds (ldab,n)]
b [input rank-2 array('f') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('f') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.dpbtrs

`scipy.linalg.lapack.dpbtrs` (*ab*, *b*[, *lower*, *ldab*, *overwrite_b*]) = <fortran object>
 Wrapper for `dpbtrs`.

Parameters

ab [input rank-2 array('d') with bounds (ldab,n)]
b [input rank-2 array('d') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('d') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.cpbtrs

`scipy.linalg.lapack.cpbtrs` (*ab*, *b*[, *lower*, *ldab*, *overwrite_b*]) = <fortran object>
 Wrapper for `cpbtrs`.

Parameters

ab [input rank-2 array('F') with bounds (ldab,n)]
b [input rank-2 array('F') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('F') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)
overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.zpbtrs

`scipy.linalg.lapack.zpbtrs(ab, b[, lower, ldab, overwrite_b]) = <fortran object>`
 Wrapper for `zpbtrs`.

Parameters

ab [input rank-2 array('D') with bounds (ldab,n)]
b [input rank-2 array('D') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('D') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)
overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.spftrf

`scipy.linalg.lapack.spftrf(n, a[, transr, uplo, overwrite_a]) = <fortran object>`
 Wrapper for `spftrf`.

Parameters

n [input int]
a [input rank-1 array('f') with bounds (nt)]

Returns

achol [rank-1 array('f') with bounds (nt) and a storage]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
overwrite_a
[input int, optional] Default: 0

scipy.linalg.lapack.dpftf

`scipy.linalg.lapack.dpftf(n, a[, transr, uplo, overwrite_a]) = <fortran object>`
 Wrapper for `dpftf`.

Parameters

n [input int]
a [input rank-1 array('d') with bounds (nt)]

Returns

achol [rank-1 array('d') with bounds (nt) and a storage]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
overwrite_a [input int, optional] Default: 0

scipy.linalg.lapack.cpftrf

`scipy.linalg.lapack.cpftrf(n, a[, transr, uplo, overwrite_a]) = <fortran object>`
 Wrapper for `cpftrf`.

Parameters

n [input int]
a [input rank-1 array('F') with bounds (nt)]

Returns

achol [rank-1 array('F') with bounds (nt) and a storage]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
overwrite_a [input int, optional] Default: 0

scipy.linalg.lapack.zpftrf

`scipy.linalg.lapack.zpftrf(n, a[, transr, uplo, overwrite_a]) = <fortran object>`
 Wrapper for `zpftrf`.

Parameters

n [input int]
a [input rank-1 array('D') with bounds (nt)]

Returns

achol [rank-1 array('D') with bounds (nt) and a storage]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
overwrite_a
[input int, optional] Default: 0

scipy.linalg.lapack.spftri

`scipy.linalg.lapack.spftri` (*n*, *a*[, *transr*, *uplo*, *overwrite_a*]) = <fortran object>
 Wrapper for `spftri`.

Parameters

n [input int]
a [input rank-1 array('f') with bounds (nt)]

Returns

ainv [rank-1 array('f') with bounds (nt) and a storage]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
overwrite_a
[input int, optional] Default: 0

scipy.linalg.lapack.dpftri

`scipy.linalg.lapack.dpftri` (*n*, *a*[, *transr*, *uplo*, *overwrite_a*]) = <fortran object>
 Wrapper for `dpftri`.

Parameters

n [input int]
a [input rank-1 array('d') with bounds (nt)]

Returns

ainv [rank-1 array('d') with bounds (nt) and a storage]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
overwrite_a
[input int, optional] Default: 0

scipy.linalg.lapack.cpftri

`scipy.linalg.lapack.cpftri` (n, a [, *transr*, *uplo*, *overwrite_a*]) = <fortran object>
 Wrapper for `cpftri`.

Parameters

n [input int]
a [input rank-1 array('F') with bounds (nt)]

Returns

ainv [rank-1 array('F') with bounds (nt) and a storage]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
overwrite_a [input int, optional] Default: 0

scipy.linalg.lapack.zpftri

`scipy.linalg.lapack.zpftri` (n, a [, *transr*, *uplo*, *overwrite_a*]) = <fortran object>
 Wrapper for `zpftri`.

Parameters

n [input int]
a [input rank-1 array('D') with bounds (nt)]

Returns

ainv [rank-1 array('D') with bounds (nt) and a storage]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
overwrite_a [input int, optional] Default: 0

scipy.linalg.lapack.spftrs

`scipy.linalg.lapack.spftrs` (n, a, b [, *transr*, *uplo*, *overwrite_b*]) = <fortran object>
 Wrapper for `spftrs`.

Parameters

n [input int]
a [input rank-1 array('f') with bounds (nt)]
b [input rank-2 array('f') with bounds (ldb,nhrs)]

Returns

x [rank-2 array('f') with bounds (ldb,nhrs) and b storage]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.dpftsr

`scipy.linalg.lapack.dpftsr(n, a, b[, transr, uplo, overwrite_b]) = <fortran object>`
 Wrapper for `dpftsr`.

Parameters

n [input int]
a [input rank-1 array('d') with bounds (nt)]
b [input rank-2 array('d') with bounds (ldb,nhrs)]

Returns

x [rank-2 array('d') with bounds (ldb,nhrs) and b storage]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.cpftrs

`scipy.linalg.lapack.cpftrs(n, a, b[, transr, uplo, overwrite_b]) = <fortran object>`
 Wrapper for `cpftrs`.

Parameters

n [input int]
a [input rank-1 array('F') with bounds (nt)]
b [input rank-2 array('F') with bounds (ldb,nhrs)]

Returns

x [rank-2 array('F') with bounds (ldb,nhrs) and b storage]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.zpfttrs

`scipy.linalg.lapack.zpfttrs` (*n*, *a*, *b*[, *transr*, *uplo*, *overwrite_b*]) = <fortran object>
 Wrapper for zpfttrs.

Parameters

n [input int]
a [input rank-1 array('D') with bounds (nt)]
b [input rank-2 array('D') with bounds (ldb,nhrs)]

Returns

x [rank-2 array('D') with bounds (ldb,nhrs) and b storage]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.spocon

`scipy.linalg.lapack.spocon` (*a*, *anorm*[, *uplo*]) = <fortran object>
 Wrapper for spocon.

Parameters

a [input rank-2 array('f') with bounds (n,n)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.dpocon

`scipy.linalg.lapack.dpocon` (*a*, *anorm*[, *uplo*]) = <fortran object>
 Wrapper for dpocon.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.cpocon

`scipy.linalg.lapack.cpocon(a, anorm[, uplo]) = <fortran object>`
 Wrapper for cpocon.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.zpocon

`scipy.linalg.lapack.zpocon(a, anorm[, uplo]) = <fortran object>`
 Wrapper for zpocon.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.spstrf

`scipy.linalg.lapack.spstrf(a[, tol, lower, overwrite_a]) = <fortran object>`
 Wrapper for spstrf.

Parameters

a [input rank-2 array('f') with bounds (n,n)]

Returns

c [rank-2 array('f') with bounds (n,n) and a storage]
piv [rank-1 array('i') with bounds (n)]
rank_c [int]
info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0
tol [input float, optional] Default: -1.0
lower [input int, optional] Default: 0

scipy.linalg.lapack.dpstrf

`scipy.linalg.lapack.dpstrf(a[, tol, lower, overwrite_a]) = <fortran object>`
 Wrapper for `dpstrf`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]

Returns

c [rank-2 array('d') with bounds (n,n) and a storage]

piv [rank-1 array('i') with bounds (n)]

rank_c [int]

info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0

tol [input float, optional] Default: -1.0

lower [input int, optional] Default: 0

scipy.linalg.lapack.cpstrf

`scipy.linalg.lapack.cpstrf(a[, tol, lower, overwrite_a]) = <fortran object>`
 Wrapper for `cpstrf`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]

Returns

c [rank-2 array('F') with bounds (n,n) and a storage]

piv [rank-1 array('i') with bounds (n)]

rank_c [int]

info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0

tol [input float, optional] Default: -1.0

lower [input int, optional] Default: 0

scipy.linalg.lapack.zpstrf

`scipy.linalg.lapack.zpstrf(a[, tol, lower, overwrite_a]) = <fortran object>`
 Wrapper for `zpstrf`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]

Returns

c [rank-2 array('D') with bounds (n,n) and a storage]

piv [rank-1 array('i') with bounds (n)]

rank_c [int]

info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
tol [input float, optional] Default: -1.0
lower [input int, optional] Default: 0

scipy.linalg.lapack.spstf2

`scipy.linalg.lapack.spstf2(a[, tol, lower, overwrite_a]) = <fortran object>`
 Wrapper for `spstf2`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]

Returns

c [rank-2 array('f') with bounds (n,n) and a storage]
piv [rank-1 array('i') with bounds (n)]
rank_c [int]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
tol [input float, optional] Default: -1.0
lower [input int, optional] Default: 0

scipy.linalg.lapack.dpstf2

`scipy.linalg.lapack.dpstf2(a[, tol, lower, overwrite_a]) = <fortran object>`
 Wrapper for `dpstf2`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]

Returns

c [rank-2 array('d') with bounds (n,n) and a storage]
piv [rank-1 array('i') with bounds (n)]
rank_c [int]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
tol [input float, optional] Default: -1.0
lower [input int, optional] Default: 0

scipy.linalg.lapack.cpstf2

`scipy.linalg.lapack.cpstf2(a[, tol, lower, overwrite_a]) = <fortran object>`
 Wrapper for `cpstf2`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]

Returns

c [rank-2 array('F') with bounds (n,n) and a storage]

piv [rank-1 array('i') with bounds (n)]

rank_c [int]

info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0

tol [input float, optional] Default: -1.0

lower [input int, optional] Default: 0

scipy.linalg.lapack.zpstf2

`scipy.linalg.lapack.zpstf2(a[, tol, lower, overwrite_a]) = <fortran object>`
 Wrapper for `zpstf2`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]

Returns

c [rank-2 array('D') with bounds (n,n) and a storage]

piv [rank-1 array('i') with bounds (n)]

rank_c [int]

info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0

tol [input float, optional] Default: -1.0

lower [input int, optional] Default: 0

scipy.linalg.lapack.sposv

`scipy.linalg.lapack.sposv(a, b[, lower, overwrite_a, overwrite_b]) = <fortran object>`
 Wrapper for `sposv`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]

b [input rank-2 array('f') with bounds (n,nrhs)]

Returns

c [rank-2 array('f') with bounds (n,n) and a storage]

x [rank-2 array('f') with bounds (n,nrhs) and b storage]

info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

overwrite_b
[input int, optional] Default: 0

lower [input int, optional] Default: 0

scipy.linalg.lapack.dposv

`scipy.linalg.lapack.dposv(a, b[, lower, overwrite_a, overwrite_b]) = <fortran object>`
Wrapper for `dposv`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]

b [input rank-2 array('d') with bounds (n,nrhs)]

Returns

c [rank-2 array('d') with bounds (n,n) and a storage]

x [rank-2 array('d') with bounds (n,nrhs) and b storage]

info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

overwrite_b
[input int, optional] Default: 0

lower [input int, optional] Default: 0

scipy.linalg.lapack.cposv

`scipy.linalg.lapack.cposv(a, b[, lower, overwrite_a, overwrite_b]) = <fortran object>`
Wrapper for `cpovs`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]

b [input rank-2 array('F') with bounds (n,nrhs)]

Returns

c [rank-2 array('F') with bounds (n,n) and a storage]

x [rank-2 array('F') with bounds (n,nrhs) and b storage]

info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

overwrite_b
[input int, optional] Default: 0

lower [input int, optional] Default: 0

scipy.linalg.lapack.zposv

`scipy.linalg.lapack.zposv(a, b[, lower, overwrite_a, overwrite_b]) = <fortran object>`
 Wrapper for `zposv`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (n,nrhs)]

Returns

c [rank-2 array('D') with bounds (n,n) and a storage]
x [rank-2 array('D') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.sposvx

`scipy.linalg.lapack.sposvx(a, b[, fact, af, equed, s, lower, overwrite_a, overwrite_b]) = <fortran object>`
 Wrapper for `sposvx`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]
b [input rank-2 array('f') with bounds (n,nrhs)]

Returns

a_s [rank-2 array('f') with bounds (n,n) and a storage]
lu [rank-2 array('f') with bounds (n,n) and af storage]
equed [string(len=1)]
s [rank-1 array('f') with bounds (n)]
b_s [rank-2 array('f') with bounds (n,nrhs) and b storage]
x [rank-2 array('f') with bounds (n,nrhs)]
rcond [float]
ferr [rank-1 array('f') with bounds (nrhs)]
berr [rank-1 array('f') with bounds (nrhs)]
info [int]

Other Parameters

fact [input string(len=1), optional] Default: 'E'
overwrite_a [input int, optional] Default: 0
af [input rank-2 array('f') with bounds (n,n)]
equed [input string(len=1), optional] Default: 'Y'
s [input rank-1 array('f') with bounds (n)]
overwrite_b [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.dposvx

`scipy.linalg.lapack.dposvx(a, b[, fact, af, equed, s, lower, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `dposvx`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
b [input rank-2 array('d') with bounds (n,nrhs)]

Returns

a_s [rank-2 array('d') with bounds (n,n) and a storage]
lu [rank-2 array('d') with bounds (n,n) and af storage]
equed [string(len=1)]
s [rank-1 array('d') with bounds (n)]
b_s [rank-2 array('d') with bounds (n,nrhs) and b storage]
x [rank-2 array('d') with bounds (n,nrhs)]
rcond [float]
ferr [rank-1 array('d') with bounds (nrhs)]
berr [rank-1 array('d') with bounds (nrhs)]
info [int]

Other Parameters

fact [input string(len=1), optional] Default: 'E'
overwrite_a [input int, optional] Default: 0
af [input rank-2 array('d') with bounds (n,n)]
equed [input string(len=1), optional] Default: 'Y'
s [input rank-1 array('d') with bounds (n)]
overwrite_b [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.cposvx

`scipy.linalg.lapack.cposvx(a, b[, fact, af, equed, s, lower, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `cpovsx`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
b [input rank-2 array('F') with bounds (n,nrhs)]

Returns

a_s [rank-2 array('F') with bounds (n,n) and a storage]
lu [rank-2 array('F') with bounds (n,n) and af storage]
equed [string(len=1)]
s [rank-1 array('f') with bounds (n)]
b_s [rank-2 array('F') with bounds (n,nrhs) and b storage]
x [rank-2 array('F') with bounds (n,nrhs)]
rcond [float]
ferr [rank-1 array('f') with bounds (nrhs)]
berr [rank-1 array('f') with bounds (nrhs)]

info [int]

Other Parameters

fact [input string(len=1), optional] Default: 'E'
overwrite_a [input int, optional] Default: 0
af [input rank-2 array('F') with bounds (n,n)]
equed [input string(len=1), optional] Default: 'Y'
s [input rank-1 array('f') with bounds (n)]
overwrite_b [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.zposvx

`scipy.linalg.lapack.zposvx(a, b[, fact, af, equed, s, lower, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for zposvx.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (n,nrhs)]

Returns

a_s [rank-2 array('D') with bounds (n,n) and a storage]
lu [rank-2 array('D') with bounds (n,n) and af storage]
equed [string(len=1)]
s [rank-1 array('d') with bounds (n)]
b_s [rank-2 array('D') with bounds (n,nrhs) and b storage]
x [rank-2 array('D') with bounds (n,nrhs)]
rcond [float]
ferr [rank-1 array('d') with bounds (nrhs)]
berr [rank-1 array('d') with bounds (nrhs)]
info [int]

Other Parameters

fact [input string(len=1), optional] Default: 'E'
overwrite_a [input int, optional] Default: 0
af [input rank-2 array('D') with bounds (n,n)]
equed [input string(len=1), optional] Default: 'Y'
s [input rank-1 array('d') with bounds (n)]
overwrite_b [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.spotrf

`scipy.linalg.lapack.spotrf(a[, lower, clean, overwrite_a]) = <fortran object>`
 Wrapper for `spotrf`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]

Returns

c [rank-2 array('f') with bounds (n,n) and a storage]

info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0

lower [input int, optional] Default: 0

clean [input int, optional] Default: 1

scipy.linalg.lapack.dpotrf

`scipy.linalg.lapack.dpotrf(a[, lower, clean, overwrite_a]) = <fortran object>`
 Wrapper for `dpotrf`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]

Returns

c [rank-2 array('d') with bounds (n,n) and a storage]

info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0

lower [input int, optional] Default: 0

clean [input int, optional] Default: 1

scipy.linalg.lapack.cpotrf

`scipy.linalg.lapack.cpotrf(a[, lower, clean, overwrite_a]) = <fortran object>`
 Wrapper for `cpotrf`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]

Returns

c [rank-2 array('F') with bounds (n,n) and a storage]

info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0

lower [input int, optional] Default: 0

clean [input int, optional] Default: 1

scipy.linalg.lapack.zpotrf

`scipy.linalg.lapack.zpotrf(a[, lower, clean, overwrite_a]) = <fortran object>`

Wrapper for `zpotrf`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]

Returns

c [rank-2 array('D') with bounds (n,n) and a storage]

info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0

lower [input int, optional] Default: 0

clean [input int, optional] Default: 1

scipy.linalg.lapack.spotri

`scipy.linalg.lapack.spotri(c[, lower, overwrite_c]) = <fortran object>`

Wrapper for `spotri`.

Parameters

c [input rank-2 array('f') with bounds (n,n)]

Returns

inv_a [rank-2 array('f') with bounds (n,n) and c storage]

info [int]

Other Parameters

overwrite_c [input int, optional] Default: 0

lower [input int, optional] Default: 0

scipy.linalg.lapack.dpotri

`scipy.linalg.lapack.dpotri(c[, lower, overwrite_c]) = <fortran object>`

Wrapper for `dpotri`.

Parameters

c [input rank-2 array('d') with bounds (n,n)]

Returns

inv_a [rank-2 array('d') with bounds (n,n) and c storage]

info [int]

Other Parameters

overwrite_c
 [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.cpotri

`scipy.linalg.lapack.cpotri(c[, lower, overwrite_c]) = <fortran object>`
 Wrapper for `cpotri`.

Parameters

c [input rank-2 array('F') with bounds (n,n)]

Returns

inv_a [rank-2 array('F') with bounds (n,n) and c storage]
info [int]

Other Parameters

overwrite_c
 [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.zpotri

`scipy.linalg.lapack.zpotri(c[, lower, overwrite_c]) = <fortran object>`
 Wrapper for `zpotri`.

Parameters

c [input rank-2 array('D') with bounds (n,n)]

Returns

inv_a [rank-2 array('D') with bounds (n,n) and c storage]
info [int]

Other Parameters

overwrite_c
 [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.spotrs

`scipy.linalg.lapack.spotrs(c, b[, lower, overwrite_b]) = <fortran object>`
 Wrapper for `spotrs`.

Parameters

c [input rank-2 array('f') with bounds (n,n)]
b [input rank-2 array('f') with bounds (n,nrhs)]

Returns

x [rank-2 array('f') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_b [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.dpotrs

`scipy.linalg.lapack.dpotrs(c, b[, lower, overwrite_b]) = <fortran object>`
 Wrapper for `dpotrs`.

Parameters

c [input rank-2 array('d') with bounds (n,n)]
b [input rank-2 array('d') with bounds (n,nrhs)]

Returns

x [rank-2 array('d') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_b [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.cpotrs

`scipy.linalg.lapack.cpotrs(c, b[, lower, overwrite_b]) = <fortran object>`
 Wrapper for `cpotrs`.

Parameters

c [input rank-2 array('F') with bounds (n,n)]
b [input rank-2 array('F') with bounds (n,nrhs)]

Returns

x [rank-2 array('F') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_b [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.zpotrs

`scipy.linalg.lapack.zpotrs(c, b[, lower, overwrite_b]) = <fortran object>`
 Wrapper for `zpotrs`.

Parameters

c [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (n,nrhs)]

Returns

x [rank-2 array('D') with bounds (n,nrhs) and b storage]

info [int]

Other Parameters

overwrite_b
[input int, optional] Default: 0

lower [input int, optional] Default: 0

scipy.linalg.lapack.sppcon

`scipy.linalg.lapack.sppcon(n, ap, anorm[, lower]) = <fortran object>`
Wrapper for sppcon.

Parameters

n [input int]

ap [input rank-1 array('f') with bounds (L)]

anorm [input float]

Returns

rcond [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.dppcon

`scipy.linalg.lapack.dppcon(n, ap, anorm[, lower]) = <fortran object>`
Wrapper for dppcon.

Parameters

n [input int]

ap [input rank-1 array('d') with bounds (L)]

anorm [input float]

Returns

rcond [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.cppcon

`scipy.linalg.lapack.cppcon(n, ap, anorm[, lower]) = <fortran object>`
Wrapper for cppcon.

Parameters

n [input int]

ap [input rank-1 array('F') with bounds (L)]

anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zppcon

`scipy.linalg.lapack.zppcon` (*n*, *ap*, *anorm*[, *lower*]) = <fortran object>
 Wrapper for zppcon.

Parameters

n [input int]
ap [input rank-1 array('D') with bounds (L)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.sppsv

`scipy.linalg.lapack.sppsv` (*n*, *ap*, *b*[, *lower*, *overwrite_b*]) = <fortran object>
 Wrapper for sppsv.

Parameters

n [input int]
ap [input rank-1 array('f') with bounds (L)]
b [input rank-2 array('f') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('f') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.dppsv

`scipy.linalg.lapack.dppsv(n, ap, b[, lower, overwrite_b]) = <fortran object>`
 Wrapper for dppsv.

Parameters

n [input int]
ap [input rank-1 array('d') with bounds (L)]
b [input rank-2 array('d') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('d') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.cppsv

`scipy.linalg.lapack.cppsv(n, ap, b[, lower, overwrite_b]) = <fortran object>`
 Wrapper for cppsv.

Parameters

n [input int]
ap [input rank-1 array('F') with bounds (L)]
b [input rank-2 array('F') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('F') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.zppsv

`scipy.linalg.lapack.zppsv(n, ap, b[, lower, overwrite_b]) = <fortran object>`
 Wrapper for zppsv.

Parameters

n [input int]
ap [input rank-1 array('D') with bounds (L)]
b [input rank-2 array('D') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('D') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.spptrf

`scipy.linalg.lapack.spptrf(n, ap[, lower, overwrite_ap]) = <fortran object>`
 Wrapper for `spptrf`.

Parameters

n [input int]
ap [input rank-1 array('f') with bounds (L)]

Returns

ul [rank-1 array('f') with bounds (L) and ap storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ap [input int, optional] Default: 0

scipy.linalg.lapack.dpptrf

`scipy.linalg.lapack.dpptrf(n, ap[, lower, overwrite_ap]) = <fortran object>`
 Wrapper for `dpptrf`.

Parameters

n [input int]
ap [input rank-1 array('d') with bounds (L)]

Returns

ul [rank-1 array('d') with bounds (L) and ap storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ap [input int, optional] Default: 0

scipy.linalg.lapack.cpptrf

`scipy.linalg.lapack.cpptrf` (n , ap [, $lower$, $overwrite_ap$]) = <fortran object>
 Wrapper for `cpptrf`.

Parameters

n [input int]
ap [input rank-1 array('F') with bounds (L)]

Returns

ul [rank-1 array('F') with bounds (L) and ap storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ap [input int, optional] Default: 0

scipy.linalg.lapack.zpptrf

`scipy.linalg.lapack.zpptrf` (n , ap [, $lower$, $overwrite_ap$]) = <fortran object>
 Wrapper for `zpptrf`.

Parameters

n [input int]
ap [input rank-1 array('D') with bounds (L)]

Returns

ul [rank-1 array('D') with bounds (L) and ap storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ap [input int, optional] Default: 0

scipy.linalg.lapack.spptri

`scipy.linalg.lapack.spptri` (n , ap [, $lower$, $overwrite_ap$]) = <fortran object>
 Wrapper for `spptri`.

Parameters

n [input int]
ap [input rank-1 array('f') with bounds (L)]

Returns

uli [rank-1 array('f') with bounds (L) and ap storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0

overwrite_ap
 [input int, optional] Default: 0

scipy.linalg.lapack.dpptri

`scipy.linalg.lapack.dpptri` (*n*, *ap*[, *lower*, *overwrite_ap*]) = <fortran object>
 Wrapper for `dpptri`.

Parameters

n [input int]
ap [input rank-1 array('d') with bounds (L)]

Returns

uli [rank-1 array('d') with bounds (L) and ap storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ap
 [input int, optional] Default: 0

scipy.linalg.lapack.cpptri

`scipy.linalg.lapack.cpptri` (*n*, *ap*[, *lower*, *overwrite_ap*]) = <fortran object>
 Wrapper for `cpptri`.

Parameters

n [input int]
ap [input rank-1 array('F') with bounds (L)]

Returns

uli [rank-1 array('F') with bounds (L) and ap storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ap
 [input int, optional] Default: 0

scipy.linalg.lapack.zpptri

`scipy.linalg.lapack.zpptri` (*n*, *ap*[, *lower*, *overwrite_ap*]) = <fortran object>
 Wrapper for `zpptri`.

Parameters

n [input int]
ap [input rank-1 array('D') with bounds (L)]

Returns

uli [rank-1 array('D') with bounds (L) and ap storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_ap
[input int, optional] Default: 0

scipy.linalg.lapack.spptrs

`scipy.linalg.lapack.spptrs(n, ap, b[, lower, overwrite_b]) = <fortran object>`
 Wrapper for `spptrs`.

Parameters

n [input int]
ap [input rank-1 array('f') with bounds (L)]
b [input rank-2 array('f') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('f') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.dpptrs

`scipy.linalg.lapack.dpptrs(n, ap, b[, lower, overwrite_b]) = <fortran object>`
 Wrapper for `dpptrs`.

Parameters

n [input int]
ap [input rank-1 array('d') with bounds (L)]
b [input rank-2 array('d') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('d') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.cpptrs

`scipy.linalg.lapack.cpptrs` (*n*, *ap*, *b*[, *lower*, *overwrite_b*]) = <fortran object>
 Wrapper for `cpptrs`.

Parameters

n [input int]
ap [input rank-1 array('F') with bounds (L)]
b [input rank-2 array('F') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('F') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.zpptrs

`scipy.linalg.lapack.zpptrs` (*n*, *ap*, *b*[, *lower*, *overwrite_b*]) = <fortran object>
 Wrapper for `zpptrs`.

Parameters

n [input int]
ap [input rank-1 array('D') with bounds (L)]
b [input rank-2 array('D') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('D') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.sptsv

`scipy.linalg.lapack.sptsv` (*d*, *e*, *b*[, *overwrite_d*, *overwrite_e*, *overwrite_b*]) = <fortran object>
 Wrapper for `sptsv`.

Parameters

d [input rank-1 array('f') with bounds (n)]
e [input rank-1 array('f') with bounds (n - 1)]
b [input rank-2 array('f') with bounds (n,nrhs)]

Returns

d [rank-1 array('f') with bounds (n)]
du [rank-1 array('f') with bounds (n - 1) and e storage]

x [rank-2 array('f') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_d
 [input int, optional] Default: 0
overwrite_e
 [input int, optional] Default: 0
overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.dptsv

`scipy.linalg.lapack.dptsv(d, e, b[, overwrite_d, overwrite_e, overwrite_b]) = <fortran object>`

Wrapper for `dptsv`.

Parameters

d [input rank-1 array('d') with bounds (n)]
e [input rank-1 array('d') with bounds (n - 1)]
b [input rank-2 array('d') with bounds (n,nrhs)]

Returns

d [rank-1 array('d') with bounds (n)]
du [rank-1 array('d') with bounds (n - 1) and e storage]
x [rank-2 array('d') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_d
 [input int, optional] Default: 0
overwrite_e
 [input int, optional] Default: 0
overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.cptsv

`scipy.linalg.lapack.cptsv(d, e, b[, overwrite_d, overwrite_e, overwrite_b]) = <fortran object>`

Wrapper for `cptsv`.

Parameters

d [input rank-1 array('f') with bounds (n)]
e [input rank-1 array('F') with bounds (n - 1)]
b [input rank-2 array('F') with bounds (n,nrhs)]

Returns

d [rank-1 array('f') with bounds (n)]
du [rank-1 array('F') with bounds (n - 1) and e storage]
x [rank-2 array('F') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

- overwrite_d**
[input int, optional] Default: 0
- overwrite_e**
[input int, optional] Default: 0
- overwrite_b**
[input int, optional] Default: 0

scipy.linalg.lapack.zptsv

`scipy.linalg.lapack.zptsv(d, e, b[, overwrite_d, overwrite_e, overwrite_b]) = <fortran object>`

Wrapper for `zptsv`.

Parameters

- d** [input rank-1 array('d') with bounds (n)]
- e** [input rank-1 array('D') with bounds (n - 1)]
- b** [input rank-2 array('D') with bounds (n,nrhs)]

Returns

- d** [rank-1 array('d') with bounds (n)]
- du** [rank-1 array('D') with bounds (n - 1) and e storage]
- x** [rank-2 array('D') with bounds (n,nrhs) and b storage]
- info** [int]

Other Parameters

- overwrite_d**
[input int, optional] Default: 0
- overwrite_e**
[input int, optional] Default: 0
- overwrite_b**
[input int, optional] Default: 0

scipy.linalg.lapack.sptsvx

`scipy.linalg.lapack.sptsvx(d, e, b[, fact, df, ef]) = <fortran object>`

Wrapper for `sptsvx`.

Parameters

- d** [input rank-1 array('f') with bounds (n)]
- e** [input rank-1 array('f') with bounds (max(0, n-1))]
- b** [input rank-2 array('f') with bounds (ldb,nrhs)]

Returns

- df** [rank-1 array('f') with bounds (n)]
- ef** [rank-1 array('f') with bounds (max(0, n-1))]
- x** [rank-2 array('f') with bounds (ldx,nrhs)]
- rcond** [float]
- ferr** [rank-1 array('f') with bounds (nrhs)]
- berr** [rank-1 array('f') with bounds (nrhs)]
- info** [int]

Other Parameters

fact	[input string(len=1), optional] Default: 'N'
df	[input rank-1 array('f') with bounds (n)]
ef	[input rank-1 array('f') with bounds (max(0, n-1))]

scipy.linalg.lapack.dptsvx

`scipy.linalg.lapack.dptsvx(d, e, b[, fact, df, ef]) = <fortran object>`
 Wrapper for `dptsvx`.

Parameters

d	[input rank-1 array('d') with bounds (n)]
e	[input rank-1 array('d') with bounds (max(0, n-1))]
b	[input rank-2 array('d') with bounds (ldb,nrhs)]

Returns

df	[rank-1 array('d') with bounds (n)]
ef	[rank-1 array('d') with bounds (max(0, n-1))]
x	[rank-2 array('d') with bounds (ldx,nrhs)]
rcond	[float]
ferr	[rank-1 array('d') with bounds (nrhs)]
berr	[rank-1 array('d') with bounds (nrhs)]
info	[int]

Other Parameters

fact	[input string(len=1), optional] Default: 'N'
df	[input rank-1 array('d') with bounds (n)]
ef	[input rank-1 array('d') with bounds (max(0, n-1))]

scipy.linalg.lapack.cptsvx

`scipy.linalg.lapack.cptsvx(d, e, b[, fact, df, ef]) = <fortran object>`
 Wrapper for `cptsvx`.

Parameters

d	[input rank-1 array('f') with bounds (n)]
e	[input rank-1 array('F') with bounds (max(0, n-1))]
b	[input rank-2 array('F') with bounds (ldb,nrhs)]

Returns

df	[rank-1 array('f') with bounds (n)]
ef	[rank-1 array('F') with bounds (max(0, n-1))]
x	[rank-2 array('F') with bounds (ldx,nrhs)]
rcond	[float]
ferr	[rank-1 array('f') with bounds (nrhs)]
berr	[rank-1 array('f') with bounds (nrhs)]
info	[int]

Other Parameters

fact	[input string(len=1), optional] Default: 'N'
df	[input rank-1 array('f') with bounds (n)]

ef [input rank-1 array('F') with bounds (max(0, n-1))]

scipy.linalg.lapack.zptsvx

`scipy.linalg.lapack.zptsvx(d, e, b[, fact, df, ef]) = <fortran object>`

Wrapper for `zptsvx`.

Parameters

d [input rank-1 array('d') with bounds (n)]
e [input rank-1 array('D') with bounds (max(0, n-1))]
b [input rank-2 array('D') with bounds (ldb,nrhs)]

Returns

df [rank-1 array('d') with bounds (n)]
ef [rank-1 array('D') with bounds (max(0, n-1))]
x [rank-2 array('D') with bounds (ldx,nrhs)]
rcond [float]
ferr [rank-1 array('d') with bounds (nrhs)]
berr [rank-1 array('d') with bounds (nrhs)]
info [int]

Other Parameters

fact [input string(len=1), optional] Default: 'N'
df [input rank-1 array('d') with bounds (n)]
ef [input rank-1 array('D') with bounds (max(0, n-1))]

scipy.linalg.lapack.spttrf

`scipy.linalg.lapack.spttrf(d, e[, overwrite_d, overwrite_e]) = <fortran object>`

Wrapper for `spttrf`.

Parameters

d [input rank-1 array('f') with bounds (n)]
e [input rank-1 array('f') with bounds ((n>0?n-1:0))]

Returns

d [rank-1 array('f') with bounds (n)]
e [rank-1 array('f') with bounds ((n>0?n-1:0))]
info [int]

Other Parameters

overwrite_d
 [input int, optional] Default: 0
overwrite_e
 [input int, optional] Default: 0

scipy.linalg.lapack.dpttrf

`scipy.linalg.lapack.dpttrf(d, e[, overwrite_d, overwrite_e]) = <fortran object>`
 Wrapper for `dpttrf`.

Parameters

d [input rank-1 array('d') with bounds (n)]
e [input rank-1 array('d') with bounds ((n>0?n-1:0))]

Returns

d [rank-1 array('d') with bounds (n)]
e [rank-1 array('d') with bounds ((n>0?n-1:0))]
info [int]

Other Parameters

overwrite_d
 [input int, optional] Default: 0
overwrite_e
 [input int, optional] Default: 0

scipy.linalg.lapack.cpttrf

`scipy.linalg.lapack.cpttrf(d, e[, overwrite_d, overwrite_e]) = <fortran object>`
 Wrapper for `cpttrf`.

Parameters

d [input rank-1 array('f') with bounds (n)]
e [input rank-1 array('F') with bounds ((n>0?n-1:0))]

Returns

d [rank-1 array('f') with bounds (n)]
e [rank-1 array('F') with bounds ((n>0?n-1:0))]
info [int]

Other Parameters

overwrite_d
 [input int, optional] Default: 0
overwrite_e
 [input int, optional] Default: 0

scipy.linalg.lapack.zpttrf

`scipy.linalg.lapack.zpttrf(d, e[, overwrite_d, overwrite_e]) = <fortran object>`
 Wrapper for `zpttrf`.

Parameters

d [input rank-1 array('d') with bounds (n)]
e [input rank-1 array('D') with bounds ((n>0?n-1:0))]

Returns

d [rank-1 array('d') with bounds (n)]
e [rank-1 array('D') with bounds ((n>0?n-1:0))]

info [int]

Other Parameters

overwrite_d
[input int, optional] Default: 0

overwrite_e
[input int, optional] Default: 0

scipy.linalg.lapack.spttrs

`scipy.linalg.lapack.spttrs(d, e, b[, overwrite_b]) = <fortran object>`
 Wrapper for `spttrs`.

Parameters

d [input rank-1 array('f') with bounds (n)]
e [input rank-1 array('f') with bounds ((n>0?n-1:0))]
b [input rank-2 array('f') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('f') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.dpttrs

`scipy.linalg.lapack.dpttrs(d, e, b[, overwrite_b]) = <fortran object>`
 Wrapper for `dpttrs`.

Parameters

d [input rank-1 array('d') with bounds (n)]
e [input rank-1 array('d') with bounds ((n>0?n-1:0))]
b [input rank-2 array('d') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('d') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.cpttrs

`scipy.linalg.lapack.cpttrs(d, e, b[, lower, overwrite_b]) = <fortran object>`
 Wrapper for `cpttrs`.

Parameters

d [input rank-1 array('f') with bounds (n)]
e [input rank-1 array('F') with bounds ((n>0?n-1:0))]
b [input rank-2 array('F') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('F') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.zpttrs

`scipy.linalg.lapack.zpttrs(d, e, b[, lower, overwrite_b]) = <fortran object>`
 Wrapper for `zpttrs`.

Parameters

d [input rank-1 array('d') with bounds (n)]
e [input rank-1 array('D') with bounds ((n>0?n-1:0))]
b [input rank-2 array('D') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('D') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.spteqr

`scipy.linalg.lapack.spteqr(d, e, z[, compute_z, overwrite_d, overwrite_e, overwrite_z]) = <fortran object>`

Wrapper for `spteqr`.

Parameters

d [input rank-1 array('f') with bounds (n)]
e [input rank-1 array('f') with bounds ((n>0?n-1:0))]
z [input rank-2 array('f') with bounds ((compute_z==0?shape(z, 0):max(1,n)),(compute_z==0?shape(z, 1):n))]

Returns

d [rank-1 array('f') with bounds (n)]

e [rank-1 array('f') with bounds ((n>0?n-1:0))]
z [rank-2 array('f') with bounds ((compute_z==0?shape(z, 0):max(1,n)),(compute_z==0?shape(z, 1):n))]
info [int]

Other Parameters

compute_z [input int, optional] Default: 0
overwrite_d [input int, optional] Default: 0
overwrite_e [input int, optional] Default: 0
overwrite_z [input int, optional] Default: 0

scipy.linalg.lapack.dpteqr

`scipy.linalg.lapack.dpteqr(d, e, z[, compute_z, overwrite_d, overwrite_e, overwrite_z]) = <fortran object>`

Wrapper for dpteqr.

Parameters

d [input rank-1 array('d') with bounds (n)]
e [input rank-1 array('d') with bounds ((n>0?n-1:0))]
z [input rank-2 array('d') with bounds ((compute_z==0?shape(z, 0):max(1,n)),(compute_z==0?shape(z, 1):n))]

Returns

d [rank-1 array('d') with bounds (n)]
e [rank-1 array('d') with bounds ((n>0?n-1:0))]
z [rank-2 array('d') with bounds ((compute_z==0?shape(z, 0):max(1,n)),(compute_z==0?shape(z, 1):n))]
info [int]

Other Parameters

compute_z [input int, optional] Default: 0
overwrite_d [input int, optional] Default: 0
overwrite_e [input int, optional] Default: 0
overwrite_z [input int, optional] Default: 0

scipy.linalg.lapack.cpteqr

`scipy.linalg.lapack.cpteqr(d, e, z[, compute_z, overwrite_d, overwrite_e, overwrite_z]) =`
<fortran object>

Wrapper for `cpteqr`.

Parameters

d [input rank-1 array('f') with bounds (n)]
e [input rank-1 array('f') with bounds ((n>0?n-1:0))]
z [input rank-2 array('F') with bounds ((compute_z==0?shape(z, 0):max(1,n)),(compute_z==0?shape(z, 1):n))]

Returns

d [rank-1 array('f') with bounds (n)]
e [rank-1 array('f') with bounds ((n>0?n-1:0))]
z [rank-2 array('F') with bounds ((compute_z==0?shape(z, 0):max(1,n)),(compute_z==0?shape(z, 1):n))]
info [int]

Other Parameters

compute_z [input int, optional] Default: 0
overwrite_d [input int, optional] Default: 0
overwrite_e [input int, optional] Default: 0
overwrite_z [input int, optional] Default: 0

scipy.linalg.lapack.zpteqr

`scipy.linalg.lapack.zpteqr(d, e, z[, compute_z, overwrite_d, overwrite_e, overwrite_z]) =`
<fortran object>

Wrapper for `zpteqr`.

Parameters

d [input rank-1 array('d') with bounds (n)]
e [input rank-1 array('d') with bounds ((n>0?n-1:0))]
z [input rank-2 array('D') with bounds ((compute_z==0?shape(z, 0):max(1,n)),(compute_z==0?shape(z, 1):n))]

Returns

d [rank-1 array('d') with bounds (n)]
e [rank-1 array('d') with bounds ((n>0?n-1:0))]
z [rank-2 array('D') with bounds ((compute_z==0?shape(z, 0):max(1,n)),(compute_z==0?shape(z, 1):n))]
info [int]

Other Parameters

compute_z [input int, optional] Default: 0
overwrite_d [input int, optional] Default: 0

overwrite_e
 [input int, optional] Default: 0

overwrite_z
 [input int, optional] Default: 0

scipy.linalg.lapack.crot

`scipy.linalg.lapack.crot(x, y, c, s[, n, offx, incx, offy, incy, overwrite_x, overwrite_y]) =`
<fortran object>

Wrapper for `crot`.

Parameters

x [input rank-1 array('F') with bounds (lx)]
y [input rank-1 array('F') with bounds (ly)]
c [input float]
s [input complex]

Returns

x [rank-1 array('F') with bounds (lx)]
y [rank-1 array('F') with bounds (ly)]

Other Parameters

n [input int, optional] Default: (lx-1-offx)/abs(incx)+1
overwrite_x [input int, optional] Default: 0
offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
overwrite_y [input int, optional] Default: 0
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.lapack.zrot

`scipy.linalg.lapack.zrot(x, y, c, s[, n, offx, incx, offy, incy, overwrite_x, overwrite_y]) =`
<fortran object>

Wrapper for `zrot`.

Parameters

x [input rank-1 array('D') with bounds (lx)]
y [input rank-1 array('D') with bounds (ly)]
c [input float]
s [input complex]

Returns

x [rank-1 array('D') with bounds (lx)]
y [rank-1 array('D') with bounds (ly)]

Other Parameters

n [input int, optional] Default: (lx-1-offx)/abs(incx)+1
overwrite_x [input int, optional] Default: 0

offx [input int, optional] Default: 0
incx [input int, optional] Default: 1
overwrite_y [input int, optional] Default: 0
offy [input int, optional] Default: 0
incy [input int, optional] Default: 1

scipy.linalg.lapack.ssbev

`scipy.linalg.lapack.ssbev(ab[, compute_v, lower, ldab, overwrite_ab]) = <fortran object>`
 Wrapper for `ssbev`.

Parameters

ab [input rank-2 array('f') with bounds (ldab,n)]

Returns

w [rank-1 array('f') with bounds (n)]
z [rank-2 array('f') with bounds (ldz,ldz)]
info [int]

Other Parameters

overwrite_ab [input int, optional] Default: 1
compute_v [input int, optional] Default: 1
lower [input int, optional] Default: 0
ldab [input int, optional] Default: `shape(ab,0)`

scipy.linalg.lapack.dsbev

`scipy.linalg.lapack.dsbev(ab[, compute_v, lower, ldab, overwrite_ab]) = <fortran object>`
 Wrapper for `dsbev`.

Parameters

ab [input rank-2 array('d') with bounds (ldab,n)]

Returns

w [rank-1 array('d') with bounds (n)]
z [rank-2 array('d') with bounds (ldz,ldz)]
info [int]

Other Parameters

overwrite_ab [input int, optional] Default: 1
compute_v [input int, optional] Default: 1
lower [input int, optional] Default: 0
ldab [input int, optional] Default: `shape(ab,0)`

scipy.linalg.lapack.ssbevd

scipy.linalg.lapack.**ssbevd**(*ab*[, *compute_v*, *lower*, *ldab*, *liwork*, *overwrite_ab*]) = <fortran object>

Wrapper for ssbevd.

Parameters

ab [input rank-2 array('f') with bounds (ldab,n)]

Returns

w [rank-1 array('f') with bounds (n)]
z [rank-2 array('f') with bounds (ldz,ldz)]
info [int]

Other Parameters

overwrite_ab [input int, optional] Default: 1
compute_v [input int, optional] Default: 1
lower [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)
liwork [input int, optional] Default: (compute_v?3+5*n:1)

scipy.linalg.lapack.dsbevd

scipy.linalg.lapack.**dsbevd**(*ab*[, *compute_v*, *lower*, *ldab*, *liwork*, *overwrite_ab*]) = <fortran object>

Wrapper for dsbevd.

Parameters

ab [input rank-2 array('d') with bounds (ldab,n)]

Returns

w [rank-1 array('d') with bounds (n)]
z [rank-2 array('d') with bounds (ldz,ldz)]
info [int]

Other Parameters

overwrite_ab [input int, optional] Default: 1
compute_v [input int, optional] Default: 1
lower [input int, optional] Default: 0
ldab [input int, optional] Default: shape(ab,0)
liwork [input int, optional] Default: (compute_v?3+5*n:1)

scipy.linalg.lapack.ssbevx

`scipy.linalg.lapack.ssbevx` (*ab*, *vl*, *vu*, *il*, *iu*[, *ldab*, *compute_v*, *range*, *lower*, *abstol*, *mmax*, *overwrite_ab*]) = **<fortran object>**

Wrapper for `ssbevx`.

Parameters

ab [input rank-2 array('f') with bounds (ldab,n)]
vl [input float]
vu [input float]
il [input int]
iu [input int]

Returns

w [rank-1 array('f') with bounds (n)]
z [rank-2 array('f') with bounds (ldz,mmax)]
m [int]
ifail [rank-1 array('i') with bounds ((compute_v?n:1))]
info [int]

Other Parameters

overwrite_ab
 [input int, optional] Default: 1
ldab [input int, optional] Default: shape(ab,0)
compute_v
 [input int, optional] Default: 1
range [input int, optional] Default: 0
lower [input int, optional] Default: 0
abstol [input float, optional] Default: 0.0
mmax [input int, optional] Default: (compute_v?(range==2?(iu-il+1):n):1)

scipy.linalg.lapack.dsbevx

`scipy.linalg.lapack.dsbevx` (*ab*, *vl*, *vu*, *il*, *iu*[, *ldab*, *compute_v*, *range*, *lower*, *abstol*, *mmax*, *overwrite_ab*]) = **<fortran object>**

Wrapper for `dsbevx`.

Parameters

ab [input rank-2 array('d') with bounds (ldab,n)]
vl [input float]
vu [input float]
il [input int]
iu [input int]

Returns

w [rank-1 array('d') with bounds (n)]
z [rank-2 array('d') with bounds (ldz,mmax)]
m [int]
ifail [rank-1 array('i') with bounds ((compute_v?n:1))]
info [int]

Other Parameters

overwrite_ab [input int, optional] Default: 1
ldab [input int, optional] Default: shape(ab,0)
compute_v [input int, optional] Default: 1
range [input int, optional] Default: 0
lower [input int, optional] Default: 0
abstol [input float, optional] Default: 0.0
mmax [input int, optional] Default: (compute_v?(range==2?(iu-il+1):n):1)

scipy.linalg.lapack.ssfrk

`scipy.linalg.lapack.ssfrk` (*n*, *k*, *alpha*, *a*, *beta*, *c*[, *transr*, *uplo*, *trans*, *overwrite_c*]) = <fortran object>

Wrapper for `ssfrk`.

Parameters

n [input int]
k [input int]
alpha [input float]
a [input rank-2 array('f') with bounds (lda,ka)]
beta [input float]
c [input rank-1 array('f') with bounds (nt)]

Returns

cout [rank-1 array('f') with bounds (nt) and c storage]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
trans [input string(len=1), optional] Default: 'N'
overwrite_c [input int, optional] Default: 0

scipy.linalg.lapack.dsfrk

`scipy.linalg.lapack.dsfrk` (*n*, *k*, *alpha*, *a*, *beta*, *c*[, *transr*, *uplo*, *trans*, *overwrite_c*]) = <fortran object>

Wrapper for `dsfrk`.

Parameters

n [input int]
k [input int]
alpha [input float]
a [input rank-2 array('d') with bounds (lda,ka)]
beta [input float]
c [input rank-1 array('d') with bounds (nt)]

Returns

cout [rank-1 array('d') with bounds (nt) and c storage]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'
trans [input string(len=1), optional] Default: 'N'
overwrite_c
 [input int, optional] Default: 0

scipy.linalg.lapack.sstebz

`scipy.linalg.lapack.sstebz(d, e, range, vl, vu, il, iu, tol, order) = <fortran object>`
 Wrapper for `sstebz`.

Parameters

d [input rank-1 array('f') with bounds (n)]
e [input rank-1 array('f') with bounds (n - 1)]
range [input int]
vl [input float]
vu [input float]
il [input int]
iu [input int]
tol [input float]
order [input string(len=1)]

Returns

m [int]
w [rank-1 array('f') with bounds (n)]
iblock [rank-1 array('i') with bounds (n)]
isplit [rank-1 array('i') with bounds (n)]
info [int]

scipy.linalg.lapack.dstebz

`scipy.linalg.lapack.dstebz(d, e, range, vl, vu, il, iu, tol, order) = <fortran object>`
 Wrapper for `dstebz`.

Parameters

d [input rank-1 array('d') with bounds (n)]
e [input rank-1 array('d') with bounds (n - 1)]
range [input int]
vl [input float]
vu [input float]
il [input int]
iu [input int]
tol [input float]
order [input string(len=1)]

Returns

m [int]
w [rank-1 array('d') with bounds (n)]
iblock [rank-1 array('i') with bounds (n)]
isplit [rank-1 array('i') with bounds (n)]
info [int]

scipy.linalg.lapack.sstein

`scipy.linalg.lapack.sstein(d, e, w, iblock, isplit) = <fortran object>`
 Wrapper for `sstein`.

Parameters

d [input rank-1 array('f') with bounds (n)]
e [input rank-1 array('f') with bounds (n - 1)]
w [input rank-1 array('f') with bounds (m)]
iblock [input rank-1 array('i') with bounds (n)]
isplit [input rank-1 array('i') with bounds (n)]

Returns

z [rank-2 array('f') with bounds (ldz,m)]
info [int]

scipy.linalg.lapack.dstein

`scipy.linalg.lapack.dstein(d, e, w, iblock, isplit) = <fortran object>`
 Wrapper for `dstein`.

Parameters

d [input rank-1 array('d') with bounds (n)]
e [input rank-1 array('d') with bounds (n - 1)]
w [input rank-1 array('d') with bounds (m)]
iblock [input rank-1 array('i') with bounds (n)]
isplit [input rank-1 array('i') with bounds (n)]

Returns

z [rank-2 array('d') with bounds (ldz,m)]
info [int]

scipy.linalg.lapack.sstemr

`scipy.linalg.lapack.sstemr(d, e, range, vl, vu, il, iu[, compute_v, lwork, liwork, overwrite_d]) = <fortran object>`

Wrapper for `sstemr`.

Parameters

d [input rank-1 array('f') with bounds (n)]
e [input rank-1 array('f') with bounds (n)]
range [input int]
vl [input float]
vu [input float]
il [input int]
iu [input int]

Returns

m [int]
w [rank-1 array('f') with bounds (n)]
z [rank-2 array('f') with bounds (n,n)]
info [int]

Other Parameters

overwrite_d	[input int, optional] Default: 0
compute_v	[input int, optional] Default: 1
lwork	[input int, optional] Default: $\max((\text{compute_v}?18*n:12*n),1)$
liwork	[input int, optional] Default: $(\text{compute_v}?10*n:8*n)$

scipy.linalg.lapack.dstemr

`scipy.linalg.lapack.dstemr` (*d*, *e*, *range*, *vl*, *vu*, *il*, *iu*[, *compute_v*, *lwork*, *liwork*, *overwrite_d*]) = **<fortran object>**

Wrapper for `dstemr`.

Parameters

d	[input rank-1 array('d') with bounds (n)]
e	[input rank-1 array('d') with bounds (n)]
range	[input int]
vl	[input float]
vu	[input float]
il	[input int]
iu	[input int]

Returns

m	[int]
w	[rank-1 array('d') with bounds (n)]
z	[rank-2 array('d') with bounds (n,n)]
info	[int]

Other Parameters

overwrite_d	[input int, optional] Default: 0
compute_v	[input int, optional] Default: 1
lwork	[input int, optional] Default: $\max((\text{compute_v}?18*n:12*n),1)$
liwork	[input int, optional] Default: $(\text{compute_v}?10*n:8*n)$

scipy.linalg.lapack.sstemr_lwork

`scipy.linalg.lapack.sstemr_lwork` (*d*, *e*, *range*, *vl*, *vu*, *il*, *iu*[, *compute_v*, *overwrite_d*, *overwrite_e*]) = **<fortran object>**

Wrapper for `sstemr_lwork`.

Parameters

d	[input rank-1 array('f') with bounds (n)]
e	[input rank-1 array('f') with bounds (n)]
range	[input int]
vl	[input float]
vu	[input float]
il	[input int]
iu	[input int]

Returns

work [float]
iwork [int]
info [int]

Other Parameters

overwrite_d
 [input int, optional] Default: 0
overwrite_e
 [input int, optional] Default: 0
compute_v
 [input int, optional] Default: 1

scipy.linalg.lapack.dstemr_lwork

`scipy.linalg.lapack.dstemr_lwork(d, e, range, vl, vu, il, iu[, compute_v, overwrite_d, overwrite_e]) = <fortran object>`

Wrapper for `dstemr_lwork`.

Parameters

d [input rank-1 array('d') with bounds (n)]
e [input rank-1 array('d') with bounds (n)]
range [input int]
vl [input float]
vu [input float]
il [input int]
iu [input int]

Returns

work [float]
iwork [int]
info [int]

Other Parameters

overwrite_d
 [input int, optional] Default: 0
overwrite_e
 [input int, optional] Default: 0
compute_v
 [input int, optional] Default: 1

scipy.linalg.lapack.ssterf

`scipy.linalg.lapack.ssterf(d, e[, overwrite_d, overwrite_e]) = <fortran object>`

Wrapper for `ssterf`.

Parameters

d [input rank-1 array('f') with bounds (n)]
e [input rank-1 array('f') with bounds (n - 1)]

Returns

vals [rank-1 array('f') with bounds (n) and d storage]

info [int]

Other Parameters

overwrite_d
[input int, optional] Default: 0

overwrite_e
[input int, optional] Default: 0

scipy.linalg.lapack.dsterf

`scipy.linalg.lapack.dsterf(d, e[, overwrite_d, overwrite_e]) = <fortran object>`
Wrapper for dsterf.

Parameters

d [input rank-1 array('d') with bounds (n)]

e [input rank-1 array('d') with bounds (n - 1)]

Returns

vals [rank-1 array('d') with bounds (n) and d storage]

info [int]

Other Parameters

overwrite_d
[input int, optional] Default: 0

overwrite_e
[input int, optional] Default: 0

scipy.linalg.lapack.sstev

`scipy.linalg.lapack.sstev(d, e[, compute_v, overwrite_d, overwrite_e]) = <fortran object>`
Wrapper for sstev.

Parameters

d [input rank-1 array('f') with bounds (n)]

e [input rank-1 array('f') with bounds (MAX(n-1,1))]

Returns

vals [rank-1 array('f') with bounds (n) and d storage]

z [rank-2 array('f') with bounds (ldz,(compute_v?n:1))]

info [int]

Other Parameters

overwrite_d
[input int, optional] Default: 0

overwrite_e
[input int, optional] Default: 0

compute_v
[input int, optional] Default: 1

scipy.linalg.lapack.dstev

`scipy.linalg.lapack.dstev(d, e[, compute_v, overwrite_d, overwrite_e]) = <fortran object>`
 Wrapper for dstev.

Parameters

d [input rank-1 array('d') with bounds (n)]
e [input rank-1 array('d') with bounds (MAX(n-1,1))]

Returns

vals [rank-1 array('d') with bounds (n) and d storage]
z [rank-2 array('d') with bounds (ldz,(compute_v?n:1))]
info [int]

Other Parameters

overwrite_d [input int, optional] Default: 0
overwrite_e [input int, optional] Default: 0
compute_v [input int, optional] Default: 1

scipy.linalg.lapack.ssycon

`scipy.linalg.lapack.ssycon(a, ipiv, anorm[, lower]) = <fortran object>`
 Wrapper for ssycon.

Parameters

a [input rank-2 array('f') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.dsycon

`scipy.linalg.lapack.dsycon(a, ipiv, anorm[, lower]) = <fortran object>`
 Wrapper for dsycon.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.csycon

`scipy.linalg.lapack.csycon(a, ipiv, anorm[, lower]) = <fortran object>`
 Wrapper for `csycon`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zsycon

`scipy.linalg.lapack.zsycon(a, ipiv, anorm[, lower]) = <fortran object>`
 Wrapper for `zsycon`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]
anorm [input float]

Returns

rcond [float]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.ssyconv

`scipy.linalg.lapack.ssyconv(a, ipiv[, lower, way, overwrite_a]) = <fortran object>`
 Wrapper for `ssyconv`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]

Returns

a [rank-2 array('f') with bounds (n,n)]
e [rank-1 array('f') with bounds (n)]
info [int]

Other Parameters

lower [input int, optional] Default: 0
way [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0

scipy.linalg.lapack.dsyconv

`scipy.linalg.lapack.dsyconv(a, ipiv[, lower, way, overwrite_a]) = <fortran object>`
 Wrapper for dsyconv.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]

Returns

a [rank-2 array('d') with bounds (n,n)]
e [rank-1 array('d') with bounds (n)]
info [int]

Other Parameters

lower [input int, optional] Default: 0
way [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0

scipy.linalg.lapack.csyconv

`scipy.linalg.lapack.csyconv(a, ipiv[, lower, way, overwrite_a]) = <fortran object>`
 Wrapper for csyconv.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]

Returns

a [rank-2 array('F') with bounds (n,n)]
e [rank-1 array('F') with bounds (n)]
info [int]

Other Parameters

lower [input int, optional] Default: 0
way [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0

scipy.linalg.lapack.zsyconv

`scipy.linalg.lapack.zsyconv(a, ipiv[, lower, way, overwrite_a]) = <fortran object>`
 Wrapper for zsyconv.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]

Returns

a [rank-2 array('D') with bounds (n,n)]
e [rank-1 array('D') with bounds (n)]
info [int]

Other Parameters

lower [input int, optional] Default: 0
way [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0

scipy.linalg.lapack.ssyequb

`scipy.linalg.lapack.ssyequb(a[, lower]) = <fortran object>`
 Wrapper for ssyequb.

Parameters

a [input rank-2 array('f') with bounds (lda,n)]

Returns

s [rank-1 array('f') with bounds (n)]
scond [float]
amax [float]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.dsyequb

`scipy.linalg.lapack.dsyequb(a[, lower]) = <fortran object>`
 Wrapper for dsyequb.

Parameters

a [input rank-2 array('d') with bounds (lda,n)]

Returns

s [rank-1 array('d') with bounds (n)]
scond [float]
amax [float]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.csyequb

`scipy.linalg.lapack.csyequb(a[, lower]) = <fortran object>`

Wrapper for `csyequb`.

Parameters

a [input rank-2 array('F') with bounds (lda,n)]

Returns

s [rank-1 array('f') with bounds (n)]

scond [float]

amax [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zsyequb

`scipy.linalg.lapack.zsyequb(a[, lower]) = <fortran object>`

Wrapper for `zsyequb`.

Parameters

a [input rank-2 array('D') with bounds (lda,n)]

Returns

s [rank-1 array('d') with bounds (n)]

scond [float]

amax [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.ssyev

`scipy.linalg.lapack.ssyev(a[, compute_v, lower, lwork, overwrite_a]) = <fortran object>`

Wrapper for `ssyev`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]

Returns

w [rank-1 array('f') with bounds (n)]

v [rank-2 array('f') with bounds (n,n) and a storage]

info [int]

Other Parameters

compute_v [input int, optional] Default: 1
lower [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: $\max(3*n-1,1)$

scipy.linalg.lapack.dsyev

`scipy.linalg.lapack.dsyev(a[, compute_v, lower, lwork, overwrite_a]) = <fortran object>`
 Wrapper for dsyev.

Parameters

a [input rank-2 array('d') with bounds (n,n)]

Returns

w [rank-1 array('d') with bounds (n)]
v [rank-2 array('d') with bounds (n,n) and a storage]
info [int]

Other Parameters

compute_v [input int, optional] Default: 1
lower [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: $\max(3*n-1,1)$

scipy.linalg.lapack.ssyev_lwork

`scipy.linalg.lapack.ssyev_lwork(n[, lower]) = <fortran object>`
 Wrapper for ssyev_lwork.

Parameters

n [input int]

Returns

work [float]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.dsyevalwork

`scipy.linalg.lapack.dsyevalwork(n[, lower]) = <fortran object>`
Wrapper for `dsyevalwork`.

Parameters

n [input int]

Returns

work [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.ssyevd

`scipy.linalg.lapack.ssyevd(a[, compute_v, lower, lwork, liwork, overwrite_a]) = <fortran object>`

Wrapper for `ssyevd`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]

Returns

w [rank-1 array('f') with bounds (n)]

v [rank-2 array('f') with bounds (n,n) and a storage]

info [int]

Other Parameters**compute_v**

[input int, optional] Default: 1

lower [input int, optional] Default: 0

overwrite_a

[input int, optional] Default: 0

lwork [input int, optional] Default: $\max((\text{compute_v}?1+6*n+2*n*n:2*n+1),1)$

liwork [input int, optional] Default: $(\text{compute_v}?3+5*n:1)$

scipy.linalg.lapack.dsyevd

`scipy.linalg.lapack.dsyevd(a[, compute_v, lower, lwork, liwork, overwrite_a]) = <fortran object>`

Wrapper for `dsyevd`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]

Returns

w [rank-1 array('d') with bounds (n)]

v [rank-2 array('d') with bounds (n,n) and a storage]

info [int]

Other Parameters

compute_v [input int, optional] Default: 1
lower [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: $\max((\text{compute_v} ? 1 + 6 * n + 2 * n * n : 2 * n + 1), 1)$
liwork [input int, optional] Default: $(\text{compute_v} ? 3 + 5 * n : 1)$

scipy.linalg.lapack.ssyevd_lwork

`scipy.linalg.lapack.ssyevd_lwork(n[, compute_v, lower]) = <fortran object>`
 Wrapper for `ssyevd_lwork`.

Parameters

n [input int]

Returns

work [float]

iwork [int]

info [int]

Other Parameters

compute_v [input int, optional] Default: 1
lower [input int, optional] Default: 0

scipy.linalg.lapack.dsyevd_lwork

`scipy.linalg.lapack.dsyevd_lwork(n[, compute_v, lower]) = <fortran object>`
 Wrapper for `dsyevd_lwork`.

Parameters

n [input int]

Returns

work [float]

iwork [int]

info [int]

Other Parameters

compute_v [input int, optional] Default: 1
lower [input int, optional] Default: 0

scipy.linalg.lapack.ssyevr

scipy.linalg.lapack.**ssyevr** (*a* [, *compute_v*, *range*, *lower*, *vl*, *vu*, *il*, *iu*, *abstol*, *lwork*, *liwork*, *overwrite_a*]) = <fortran object>

Wrapper for `ssyevr`.

Parameters

a [input rank-2 array('f') with bounds (n, n)]

Returns

w [rank-1 array('f') with bounds (n)]

z [rank-2 array('f') with bounds ((compute_v?MAX(0, n):0), (compute_v?(*range=='I'?iu-il+1:MAX(1, n)):0))]]

m [int]

isuppz [rank-1 array('i') with bounds ((compute_v?(2*(*range=='A' || (*range=='I' && iu-il+1==n)?n:0)):0))]]

info [int]

Other Parameters

compute_v

[input int, optional] Default 1

range [input string(len=1), optional] Default 'A'

lower [input int, optional] Default 0

overwrite_a

[input int, optional] Default 0

vl [input float, optional] Default 0.0

vu [input float, optional] Default 1.0

il [input int, optional] Default 1

iu [input int, optional] Default n

abstol [input float, optional] Default 0.0

lwork [input int, optional] Default max(26*n, 1)

liwork [input int, optional] Default max(1, 10*n)

scipy.linalg.lapack.dsyevr

scipy.linalg.lapack.**dsyevr** (*a* [, *compute_v*, *range*, *lower*, *vl*, *vu*, *il*, *iu*, *abstol*, *lwork*, *liwork*, *overwrite_a*]) = <fortran object>

Wrapper for `dsyevr`.

Parameters

a [input rank-2 array('d') with bounds (n, n)]

Returns

w [rank-1 array('d') with bounds (n)]

z [rank-2 array('d') with bounds ((compute_v?MAX(0, n):0), (compute_v?(*range=='I'?iu-il+1:MAX(1, n)):0))]]

m [int]

isuppz [rank-1 array('i') with bounds ((compute_v?(2*(*range=='A' || (*range=='I' && iu-il+1==n)?n:0)):0))]]

info [int]

Other Parameters

compute_v [input int, optional] Default 1
range [input string(len=1), optional] Default 'A'
lower [input int, optional] Default 0
overwrite_a [input int, optional] Default 0
vl [input float, optional] Default 0.0
vu [input float, optional] Default 1.0
il [input int, optional] Default 1
iu [input int, optional] Default n
abstol [input float, optional] Default 0.0
lwork [input int, optional] Default $\max(26*n, 1)$
liwork [input int, optional] Default $\max(1, 10*n)$

scipy.linalg.lapack.ssyevr_lwork

`scipy.linalg.lapack.ssyevr_lwork(n[, lower]) = <fortran object>`
 Wrapper for `ssyevr_lwork`.

Parameters

n [input int]

Returns

work [float]

iwork [int]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.dsyevr_lwork

`scipy.linalg.lapack.dsyevr_lwork(n[, lower]) = <fortran object>`
 Wrapper for `dsyevr_lwork`.

Parameters

n [input int]

Returns

work [float]

iwork [int]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.ssyevx

```
scipy.linalg.lapack.ssyevx(a[, compute_v, range, lower, vl, vu, il, iu, abstol, lwork, overwrite_a])
                        = <fortran object>
```

Wrapper for `ssyevx`.

Parameters

a [input rank-2 array('f') with bounds (n, n)]

Returns

w [rank-1 array('f') with bounds (n)]

z [rank-2 array('f') with bounds ((compute_v?MAX(0, n):0), (compute_v?(*range=='I'?iu-il+1:MAX(1, n)):0))]

m [int]

ifail [rank-1 array('i') with bounds ((compute_v?n:0))]

info [int]

Other Parameters**compute_v**

[input int, optional] Default 1

range [input string(len=1), optional] Default 'A'

lower [input int, optional] Default 0

overwrite_a

[input int, optional] Default 0

vl [input float, optional] Default 0.0

vu [input float, optional] Default 1.0

il [input int, optional] Default 1

iu [input int, optional] Default n

abstol [input float, optional] Default 0.0

lwork [input int, optional] Default max(8*n, 1)

scipy.linalg.lapack.dsyevx

```
scipy.linalg.lapack.dsyevx(a[, compute_v, range, lower, vl, vu, il, iu, abstol, lwork, overwrite_a])
                        = <fortran object>
```

Wrapper for `dsyevx`.

Parameters

a [input rank-2 array('d') with bounds (n, n)]

Returns

w [rank-1 array('d') with bounds (n)]

z [rank-2 array('d') with bounds ((compute_v?MAX(0, n):0), (compute_v?(*range=='I'?iu-il+1:MAX(1, n)):0))]

m [int]

ifail [rank-1 array('i') with bounds ((compute_v?n:0))]

info [int]

Other Parameters**compute_v**

[input int, optional] Default 1

range [input string(len=1), optional] Default 'A'

lower [input int, optional] Default 0

overwrite_a [input int, optional] Default 0
vl [input float, optional] Default 0.0
vu [input float, optional] Default 1.0
il [input int, optional] Default 1
iu [input int, optional] Default n
abstol [input float, optional] Default 0.0
lwork [input int, optional] Default $\max(8*n, 1)$

scipy.linalg.lapack.ssyevx_lwork

`scipy.linalg.lapack.ssyevx_lwork(n[, lower]) = <fortran object>`
 Wrapper for `ssyevx_lwork`.

Parameters

n [input int]

Returns

work [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.dsyevx_lwork

`scipy.linalg.lapack.dsyevx_lwork(n[, lower]) = <fortran object>`
 Wrapper for `dsyevx_lwork`.

Parameters

n [input int]

Returns

work [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.ssygst

`scipy.linalg.lapack.ssygst(a, b[, itype, lower, overwrite_a]) = <fortran object>`
 Wrapper for `ssygst`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]

b [input rank-2 array('f') with bounds (n,n)]

Returns

c [rank-2 array('f') with bounds (n,n) and a storage]

info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
itype [input int, optional] Default: 1
lower [input int, optional] Default: 0

scipy.linalg.lapack.dsygst

`scipy.linalg.lapack.dsygst(a, b[, itype, lower, overwrite_a]) = <fortran object>`
 Wrapper for dsygst.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
b [input rank-2 array('d') with bounds (n,n)]

Returns

c [rank-2 array('d') with bounds (n,n) and a storage]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
itype [input int, optional] Default: 1
lower [input int, optional] Default: 0

scipy.linalg.lapack.ssygv

`scipy.linalg.lapack.ssygv(a, b[, itype, jobz, uplo, lwork, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for ssygv.

Parameters

a [input rank-2 array('f') with bounds (n,n)]
b [input rank-2 array('f') with bounds (n,n)]

Returns

w [rank-1 array('f') with bounds (n)]
v [rank-2 array('f') with bounds (n,n) and a storage]
info [int]

Other Parameters

itype [input int, optional] Default: 1
jobz [input string(len=1), optional] Default: 'V'
uplo [input string(len=1), optional] Default: 'L'
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n-1,1)

scipy.linalg.lapack.dsygv

`scipy.linalg.lapack.dsygv(a, b[, itype, jobz, uplo, lwork, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for dsygv.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
b [input rank-2 array('d') with bounds (n,n)]

Returns

w [rank-1 array('d') with bounds (n)]
v [rank-2 array('d') with bounds (n,n) and a storage]
info [int]

Other Parameters

itype [input int, optional] Default: 1
jobz [input string(len=1), optional] Default: 'V'
uplo [input string(len=1), optional] Default: 'L'
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n-1,1)

scipy.linalg.lapack.ssygv_lwork

`scipy.linalg.lapack.ssygv_lwork(n[, uplo]) = <fortran object>`

Wrapper for ssygv_lwork.

Parameters

n [input int]

Returns

work [float]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'L'

scipy.linalg.lapack.dsygv_lwork

`scipy.linalg.lapack.dsygv_lwork(n[, uplo]) = <fortran object>`

Wrapper for dsygv_lwork.

Parameters

n [input int]

Returns

work [float]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'L'

scipy.linalg.lapack.ssygv

`scipy.linalg.lapack.ssygv(a, b[, itype, jobz, uplo, lwork, liwork, overwrite_a, overwrite_b]) =`
<fortran object>

Wrapper for ssygv.

Parameters

a [input rank-2 array('f') with bounds (n, n)]
b [input rank-2 array('f') with bounds (n, n)]

Returns

w [rank-1 array('f') with bounds (n)]
v [rank-2 array('f') with bounds (n, n) with a storage]
info [int]

Other Parameters

itype [input int, optional] Default 1
jobz [input string(len=1), optional] Default 'V'
uplo [input string(len=1), optional] Default 'L'
overwrite_a [input int, optional] Default 0
overwrite_b [input int, optional] Default 0
lwork [input int, optional] Default (*jobz=='N'?2*n+1:1+6*n+2*n*n)
liwork [input int, optional] Default (*jobz=='N'?1:5*n+3)

scipy.linalg.lapack.dsygv

`scipy.linalg.lapack.dsygv(a, b[, itype, jobz, uplo, lwork, liwork, overwrite_a, overwrite_b]) =`
<fortran object>

Wrapper for dsygv.

Parameters

a [input rank-2 array('d') with bounds (n, n)]
b [input rank-2 array('d') with bounds (n, n)]

Returns

w [rank-1 array('d') with bounds (n)]
v [rank-2 array('d') with bounds (n, n) with a storage]
info [int]

Other Parameters

itype [input int, optional] Default 1
jobz [input string(len=1), optional] Default 'V'
uplo [input string(len=1), optional] Default 'L'
overwrite_a [input int, optional] Default 0
overwrite_b [input int, optional] Default 0

lwork [input int, optional] Default (*jobz=='N'?2*n+1:1+6*n+2*n*n)
liwork [input int, optional] Default (*jobz=='N'?1:5*n+3)

scipy.linalg.lapack.ssygvx

scipy.linalg.lapack.**ssygvx**(*a*, *b*[, *itype*, *jobz*, *range*, *uplo*, *vl*, *vu*, *il*, *iu*, *abstol*, *lwork*, *overwrite_a*, *overwrite_b*]) = <fortran object>

Wrapper for ssygvx.

Parameters

a [input rank-2 array('f') with bounds (n,n)]
b [input rank-2 array('f') with bounds (n,n)]

Returns

w [rank-1 array('f') with bounds (n)]
z [rank-2 array('f') with bounds ((jobz[0]=='V'?MAX(0,n):0),(jobz[0]=='V'?((range[0]=='I'?iu-il+1:MAX(1,n)):0)))]
m [int]
ifail [rank-1 array('i') with bounds ((jobz[0]=='N'?0:n))]
info [int]

Other Parameters

itype [input int, optional] Default: 1
jobz [input string(len=1), optional] Default: 'V'
range [input string(len=1), optional] Default: 'A'
uplo [input string(len=1), optional] Default: 'L'
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
vl [input float, optional] Default: 0.0
vu [input float, optional] Default: 1.0
il [input int, optional] Default: 1
iu [input int, optional] Default: n
abstol [input float, optional] Default: 0.0
lwork [input int, optional] Default: max(8*n,1)

scipy.linalg.lapack.dsygvx

scipy.linalg.lapack.**dsygvx**(*a*, *b*[, *itype*, *jobz*, *range*, *uplo*, *vl*, *vu*, *il*, *iu*, *abstol*, *lwork*, *overwrite_a*, *overwrite_b*]) = <fortran object>

Wrapper for dsygvx.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
b [input rank-2 array('d') with bounds (n,n)]

Returns

w [rank-1 array('d') with bounds (n)]
z [rank-2 array('d') with bounds ((jobz[0]=='V'?MAX(0,n):0),(jobz[0]=='V'?((range[0]=='I'?iu-il+1:MAX(1,n)):0)))]
m [int]

ifail [rank-1 array('i') with bounds ((jobz[0]=='N'?0:n))]
info [int]

Other Parameters

itype [input int, optional] Default: 1
jobz [input string(len=1), optional] Default: 'V'
range [input string(len=1), optional] Default: 'A'
uplo [input string(len=1), optional] Default: 'L'
overwrite_a
[input int, optional] Default: 0
overwrite_b
[input int, optional] Default: 0
vl [input float, optional] Default: 0.0
vu [input float, optional] Default: 1.0
il [input int, optional] Default: 1
iu [input int, optional] Default: n
abstol [input float, optional] Default: 0.0
lwork [input int, optional] Default: max(8*n,1)

scipy.linalg.lapack.ssygvx_lwork

`scipy.linalg.lapack.ssygvx_lwork(n[, uplo]) = <fortran object>`
 Wrapper for `ssygvx_lwork`.

Parameters

n [input int]

Returns

work [float]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'L'

scipy.linalg.lapack.dsygvx_lwork

`scipy.linalg.lapack.dsygvx_lwork(n[, uplo]) = <fortran object>`
 Wrapper for `dsygvx_lwork`.

Parameters

n [input int]

Returns

work [float]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'L'

scipy.linalg.lapack.ssysv

`scipy.linalg.lapack.ssysv(a, b[, lwork, lower, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `ssysv`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]
b [input rank-2 array('f') with bounds (n,nrhs)]

Returns

udut [rank-2 array('f') with bounds (n,n) and a storage]
ipiv [rank-1 array('i') with bounds (n)]
x [rank-2 array('f') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(n,1)
lower [input int, optional] Default: 0

scipy.linalg.lapack.dsysv

`scipy.linalg.lapack.dsysv(a, b[, lwork, lower, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `dsysv`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
b [input rank-2 array('d') with bounds (n,nrhs)]

Returns

udut [rank-2 array('d') with bounds (n,n) and a storage]
ipiv [rank-1 array('i') with bounds (n)]
x [rank-2 array('d') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(n,1)
lower [input int, optional] Default: 0

scipy.linalg.lapack.csysv

`scipy.linalg.lapack.csysv(a, b[, lwork, lower, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `csysv`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
b [input rank-2 array('F') with bounds (n,nrhs)]

Returns

udut [rank-2 array('F') with bounds (n,n) and a storage]
ipiv [rank-1 array('i') with bounds (n)]
x [rank-2 array('F') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(n,1)
lower [input int, optional] Default: 0

scipy.linalg.lapack.zsysv

`scipy.linalg.lapack.zsysv(a, b[, lwork, lower, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `zsysv`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (n,nrhs)]

Returns

udut [rank-2 array('D') with bounds (n,n) and a storage]
ipiv [rank-1 array('i') with bounds (n)]
x [rank-2 array('D') with bounds (n,nrhs) and b storage]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(n,1)
lower [input int, optional] Default: 0

scipy.linalg.lapack.ssysv_lwork

`scipy.linalg.lapack.ssysv_lwork` (n [, $lower$]) = <fortran object>
 Wrapper for `ssysv_lwork`.

Parameters

n [input int]

Returns

work [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.dsysv_lwork

`scipy.linalg.lapack.dsysv_lwork` (n [, $lower$]) = <fortran object>
 Wrapper for `dsysv_lwork`.

Parameters

n [input int]

Returns

work [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.csysv_lwork

`scipy.linalg.lapack.csysv_lwork` (n [, $lower$]) = <fortran object>
 Wrapper for `csysv_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zsysv_lwork

`scipy.linalg.lapack.zsysv_lwork(n[, lower]) = <fortran object>`
 Wrapper for `zsysv_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.ssysvx

`scipy.linalg.lapack.ssysvx(a, b[, af, ipiv, lwork, factored, lower, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `ssysvx`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]

b [input rank-2 array('f') with bounds (n,nrhs)]

Returns

a_s [rank-2 array('f') with bounds (n,n) and a storage]

udut [rank-2 array('f') with bounds (n,n) and af storage]

ipiv [rank-1 array('i') with bounds (n)]

b_s [rank-2 array('f') with bounds (n,nrhs) and b storage]

x [rank-2 array('f') with bounds (n,nrhs)]

rcond [float]

ferr [rank-1 array('f') with bounds (nrhs)]

berr [rank-1 array('f') with bounds (nrhs)]

info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0

af [input rank-2 array('f') with bounds (n,n)]

ipiv [input rank-1 array('i') with bounds (n)]

overwrite_b [input int, optional] Default: 0

lwork [input int, optional] Default: $\max(3*n, 1)$

factored [input int, optional] Default: 0

lower [input int, optional] Default: 0

scipy.linalg.lapack.dsysvx

`scipy.linalg.lapack.dsysvx(a, b[, af, ipiv, lwork, factored, lower, overwrite_a, overwrite_b]) =`
<fortran object>

Wrapper for `dsysvx`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]
b [input rank-2 array('d') with bounds (n,nrhs)]

Returns

a_s [rank-2 array('d') with bounds (n,n) and a storage]
udut [rank-2 array('d') with bounds (n,n) and af storage]
ipiv [rank-1 array('i') with bounds (n)]
b_s [rank-2 array('d') with bounds (n,nrhs) and b storage]
x [rank-2 array('d') with bounds (n,nrhs)]
rcond [float]
ferr [rank-1 array('d') with bounds (nrhs)]
berr [rank-1 array('d') with bounds (nrhs)]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
af [input rank-2 array('d') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: $\max(3*n, 1)$
factored [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.csysvx

`scipy.linalg.lapack.csysvx(a, b[, af, ipiv, lwork, factored, lower, overwrite_a, overwrite_b]) =`
<fortran object>

Wrapper for `csysvx`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
b [input rank-2 array('F') with bounds (n,nrhs)]

Returns

a_s [rank-2 array('F') with bounds (n,n) and a storage]
udut [rank-2 array('F') with bounds (n,n) and af storage]
ipiv [rank-1 array('i') with bounds (n)]
b_s [rank-2 array('F') with bounds (n,nrhs) and b storage]
x [rank-2 array('F') with bounds (n,nrhs)]
rcond [float]
ferr [rank-1 array('f') with bounds (nrhs)]
berr [rank-1 array('f') with bounds (nrhs)]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
af [input rank-2 array('F') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)
factored [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.zsysvx

`scipy.linalg.lapack.zsysvx(a, b[, af, ipiv, lwork, factored, lower, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for `zsysvx`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (n,nrhs)]

Returns

a_s [rank-2 array('D') with bounds (n,n) and a storage]
udut [rank-2 array('D') with bounds (n,n) and af storage]
ipiv [rank-1 array('i') with bounds (n)]
b_s [rank-2 array('D') with bounds (n,nrhs) and b storage]
x [rank-2 array('D') with bounds (n,nrhs)]
rcond [float]
ferr [rank-1 array('d') with bounds (nrhs)]
berr [rank-1 array('d') with bounds (nrhs)]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
af [input rank-2 array('D') with bounds (n,n)]
ipiv [input rank-1 array('i') with bounds (n)]
overwrite_b [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)
factored [input int, optional] Default: 0
lower [input int, optional] Default: 0

scipy.linalg.lapack.ssysvx_lwork

`scipy.linalg.lapack.ssysvx_lwork(n[, lower]) = <fortran object>`
 Wrapper for `ssysvx_lwork`.

Parameters

n [input int]

Returns

work [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.dsysvx_lwork

`scipy.linalg.lapack.dsysvx_lwork(n[, lower]) = <fortran object>`
 Wrapper for `dsysvx_lwork`.

Parameters

n [input int]

Returns

work [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.csysvx_lwork

`scipy.linalg.lapack.csysvx_lwork(n[, lower]) = <fortran object>`
 Wrapper for `csysvx_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zsysvx_lwork

`scipy.linalg.lapack.zsysvx_lwork(n[, lower]) = <fortran object>`
 Wrapper for `zsysvx_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.ssytff2

`scipy.linalg.lapack.ssytff2(a[, lower, overwrite_a]) = <fortran object>`
 Wrapper for `ssytff2`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]

Returns

ldu [rank-2 array('f') with bounds (n,n) and a storage]

ipiv [rank-1 array('i') with bounds (n)]

info [int]

Other Parameters

lower [input int, optional] Default: 0

overwrite_a [input int, optional] Default: 0

scipy.linalg.lapack.dsytff2

`scipy.linalg.lapack.dsytff2(a[, lower, overwrite_a]) = <fortran object>`
 Wrapper for `dsytff2`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]

Returns

ldu [rank-2 array('d') with bounds (n,n) and a storage]

ipiv [rank-1 array('i') with bounds (n)]

info [int]

Other Parameters

lower [input int, optional] Default: 0

overwrite_a [input int, optional] Default: 0

scipy.linalg.lapack.csytff2

`scipy.linalg.lapack.csytff2(a[, lower, overwrite_a]) = <fortran object>`
 Wrapper for `csytff2`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]

Returns

ldu [rank-2 array('F') with bounds (n,n) and a storage]

ipiv [rank-1 array('i') with bounds (n)]

info [int]

Other Parameters

lower [input int, optional] Default: 0

overwrite_a
[input int, optional] Default: 0

scipy.linalg.lapack.zsytf2

`scipy.linalg.lapack.zsytf2(a[, lower, overwrite_a]) = <fortran object>`
Wrapper for `zsytf2`.

Parameters

a [input rank-2 array('D') with bounds (n,n)]

Returns

ldu [rank-2 array('D') with bounds (n,n) and a storage]

ipiv [rank-1 array('i') with bounds (n)]

info [int]

Other Parameters

lower [input int, optional] Default: 0

overwrite_a
[input int, optional] Default: 0

scipy.linalg.lapack.ssytrd

`scipy.linalg.lapack.ssytrd(a[, lower, lwork, overwrite_a]) = <fortran object>`
Wrapper for `ssytrd`.

Parameters

a [input rank-2 array('f') with bounds (lda,n)]

Returns

c [rank-2 array('f') with bounds (lda,n) and a storage]

d [rank-1 array('f') with bounds (n)]

e [rank-1 array('f') with bounds (n - 1)]

tau [rank-1 array('f') with bounds (n - 1)]

info [int]

Other Parameters

lower [input int, optional] Default: 0

overwrite_a
[input int, optional] Default: 0

lwork [input int, optional] Default: MAX(n,1)

scipy.linalg.lapack.dsytrd

`scipy.linalg.lapack.dsytrd(a[, lower, lwork, overwrite_a]) = <fortran object>`
Wrapper for `dsytrd`.

Parameters

a [input rank-2 array('d') with bounds (lda,n)]

Returns

c [rank-2 array('d') with bounds (lda,n) and a storage]

d [rank-1 array('d') with bounds (n)]

e [rank-1 array('d') with bounds (n - 1)]

tau [rank-1 array('d') with bounds (n - 1)]

info [int]

Other Parameters

lower [input int, optional] Default: 0

overwrite_a [input int, optional] Default: 0

lwork [input int, optional] Default: MAX(n,1)

scipy.linalg.lapack.ssytrd_lwork

`scipy.linalg.lapack.ssytrd_lwork(n[, lower]) = <fortran object>`
Wrapper for `ssytrd_lwork`.

Parameters

n [input int]

Returns

work [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.dsytrd_lwork

`scipy.linalg.lapack.dsytrd_lwork(n[, lower]) = <fortran object>`
Wrapper for `dsytrd_lwork`.

Parameters

n [input int]

Returns

work [float]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.ssytrf

`scipy.linalg.lapack.ssytrf(a[, lower, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `ssytrf`.

Parameters

a [input rank-2 array('f') with bounds (n,n)]

Returns

ldu [rank-2 array('f') with bounds (n,n) and a storage]

ipiv [rank-1 array('i') with bounds (n)]

info [int]

Other Parameters

lower [input int, optional] Default: 0

overwrite_a [input int, optional] Default: 0

lwork [input int, optional] Default: max(n,1)

scipy.linalg.lapack.dsytrf

`scipy.linalg.lapack.dsytrf(a[, lower, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `dsytrf`.

Parameters

a [input rank-2 array('d') with bounds (n,n)]

Returns

ldu [rank-2 array('d') with bounds (n,n) and a storage]

ipiv [rank-1 array('i') with bounds (n)]

info [int]

Other Parameters

lower [input int, optional] Default: 0

overwrite_a [input int, optional] Default: 0

lwork [input int, optional] Default: max(n,1)

scipy.linalg.lapack.csytrf

`scipy.linalg.lapack.csytrf(a[, lower, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `csytrf`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]

Returns

ldu [rank-2 array('F') with bounds (n,n) and a storage]

ipiv [rank-1 array('i') with bounds (n)]

info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(n,1)

scipy.linalg.lapack.zsytrf

`scipy.linalg.lapack.zsytrf(a[, lower, lwork, overwrite_a]) = <fortran object>`
 Wrapper for zsytrf.

Parameters

a [input rank-2 array('D') with bounds (n,n)]

Returns

ldu [rank-2 array('D') with bounds (n,n) and a storage]
ipiv [rank-1 array('i') with bounds (n)]
info [int]

Other Parameters

lower [input int, optional] Default: 0
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(n,1)

scipy.linalg.lapack.ssytrf_lwork

`scipy.linalg.lapack.ssytrf_lwork(n[, lower]) = <fortran object>`
 Wrapper for ssytrf_lwork.

Parameters

n [input int]

Returns

work [float]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.dsytrf_lwork

`scipy.linalg.lapack.dsytrf_lwork(n[, lower]) = <fortran object>`
 Wrapper for dsytrf_lwork.

Parameters

n [input int]

Returns

work [float]
info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.csytrf_lwork

`scipy.linalg.lapack.csytrf_lwork(n[, lower]) = <fortran object>`

Wrapper for `csytrf_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.zsytrf_lwork

`scipy.linalg.lapack.zsytrf_lwork(n[, lower]) = <fortran object>`

Wrapper for `zsytrf_lwork`.

Parameters

n [input int]

Returns

work [complex]

info [int]

Other Parameters

lower [input int, optional] Default: 0

scipy.linalg.lapack.stbtrs

`scipy.linalg.lapack.stbtrs(ab, b[, uplo, trans, diag, overwrite_b]) = <fortran object>`

Wrapper for `stbtrs`.

Parameters

ab [input rank-2 array('f') with bounds (ldab,n)]

b [input rank-2 array('f') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('f') with bounds (ldb,nrhs) and b storage]

info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'

trans [input string(len=1), optional] Default: 'N'

diag [input string(len=1), optional] Default: 'N'

overwrite_b
[input int, optional] Default: 0

scipy.linalg.lapack.dtbtrs

`scipy.linalg.lapack.dtbtrs` (*ab*, *b*[, *uplo*, *trans*, *diag*, *overwrite_b*]) = <fortran object>
 Wrapper for `dtbtrs`.

Parameters

ab [input rank-2 array('d') with bounds (ldab,n)]
b [input rank-2 array('d') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('d') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'
trans [input string(len=1), optional] Default: 'N'
diag [input string(len=1), optional] Default: 'N'
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.ctbtrs

`scipy.linalg.lapack.ctbtrs` (*ab*, *b*[, *uplo*, *trans*, *diag*, *overwrite_b*]) = <fortran object>
 Wrapper for `ctbtrs`.

Parameters

ab [input rank-2 array('F') with bounds (ldab,n)]
b [input rank-2 array('F') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('F') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'
trans [input string(len=1), optional] Default: 'N'
diag [input string(len=1), optional] Default: 'N'
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.ztbtrs

`scipy.linalg.lapack.ztbtrs` (*ab*, *b*[, *uplo*, *trans*, *diag*, *overwrite_b*]) = <fortran object>
 Wrapper for `ztbtrs`.

Parameters

ab [input rank-2 array('D') with bounds (ldab,n)]
b [input rank-2 array('D') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('D') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

uplo	[input string(len=1), optional] Default: 'U'
trans	[input string(len=1), optional] Default: 'N'
diag	[input string(len=1), optional] Default: 'N'
overwrite_b	[input int, optional] Default: 0

scipy.linalg.lapack.stfsm

`scipy.linalg.lapack.stfsm(alpha, a, b[, transr, side, uplo, trans, diag, overwrite_b]) = <fortran object>`

Wrapper for `stfsm`.

Parameters

alpha	[input float]
a	[input rank-1 array('f') with bounds (nt)]
b	[input rank-2 array('f') with bounds (m,n)]

Returns

x	[rank-2 array('f') with bounds (m,n) and b storage]
----------	---

Other Parameters

transr	[input string(len=1), optional] Default: 'N'
side	[input string(len=1), optional] Default: 'L'
uplo	[input string(len=1), optional] Default: 'U'
trans	[input string(len=1), optional] Default: 'N'
diag	[input string(len=1), optional] Default: 'N'
overwrite_b	[input int, optional] Default: 0

scipy.linalg.lapack.dtfsm

`scipy.linalg.lapack.dtfsm(alpha, a, b[, transr, side, uplo, trans, diag, overwrite_b]) = <fortran object>`

Wrapper for `dtfsm`.

Parameters

alpha	[input float]
a	[input rank-1 array('d') with bounds (nt)]
b	[input rank-2 array('d') with bounds (m,n)]

Returns

x	[rank-2 array('d') with bounds (m,n) and b storage]
----------	---

Other Parameters

transr	[input string(len=1), optional] Default: 'N'
side	[input string(len=1), optional] Default: 'L'
uplo	[input string(len=1), optional] Default: 'U'
trans	[input string(len=1), optional] Default: 'N'
diag	[input string(len=1), optional] Default: 'N'
overwrite_b	[input int, optional] Default: 0

scipy.linalg.lapack.ctfsm

`scipy.linalg.lapack.ctfsm(alpha, a, b[, transr, side, uplo, trans, diag, overwrite_b]) = <fortran object>`

Wrapper for `ctfsm`.

Parameters

alpha [input complex]
a [input rank-1 array('F') with bounds (nt)]
b [input rank-2 array('F') with bounds (m,n)]

Returns

x [rank-2 array('F') with bounds (m,n) and b storage]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
side [input string(len=1), optional] Default: 'L'
uplo [input string(len=1), optional] Default: 'U'
trans [input string(len=1), optional] Default: 'N'
diag [input string(len=1), optional] Default: 'N'
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.ztfsm

`scipy.linalg.lapack.ztfsm(alpha, a, b[, transr, side, uplo, trans, diag, overwrite_b]) = <fortran object>`

Wrapper for `ztfsm`.

Parameters

alpha [input complex]
a [input rank-1 array('D') with bounds (nt)]
b [input rank-2 array('D') with bounds (m,n)]

Returns

x [rank-2 array('D') with bounds (m,n) and b storage]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
side [input string(len=1), optional] Default: 'L'
uplo [input string(len=1), optional] Default: 'U'
trans [input string(len=1), optional] Default: 'N'
diag [input string(len=1), optional] Default: 'N'
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.stfttp

`scipy.linalg.lapack.stfttp` (*n*, *arf*[, *transr*, *uplo*]) = <fortran object>
 Wrapper for `stfttp`.

Parameters

n [input int]
arf [input rank-1 array('f') with bounds (nt)]

Returns

ap [rank-1 array('f') with bounds (nt)]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.dfttp

`scipy.linalg.lapack.dfttp` (*n*, *arf*[, *transr*, *uplo*]) = <fortran object>
 Wrapper for `dfttp`.

Parameters

n [input int]
arf [input rank-1 array('d') with bounds (nt)]

Returns

ap [rank-1 array('d') with bounds (nt)]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.ctfttp

`scipy.linalg.lapack.ctfttp` (*n*, *arf*[, *transr*, *uplo*]) = <fortran object>
 Wrapper for `ctfttp`.

Parameters

n [input int]
arf [input rank-1 array('F') with bounds (nt)]

Returns

ap [rank-1 array('F') with bounds (nt)]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.zfttp

`scipy.linalg.lapack.zfttp` (*n*, *arf*[, *transr*, *uplo*]) = <fortran object>
 Wrapper for `zfttp`.

Parameters

n [input int]
arf [input rank-1 array('D') with bounds (nt)]

Returns

ap [rank-1 array('D') with bounds (nt)]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.stftr

`scipy.linalg.lapack.stftr` (*n*, *arf*[, *transr*, *uplo*]) = <fortran object>
 Wrapper for `stftr`.

Parameters

n [input int]
arf [input rank-1 array('f') with bounds (nt)]

Returns

a [rank-2 array('f') with bounds (lda,n)]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.dfttr

`scipy.linalg.lapack.dfttr` (*n*, *arf*[, *transr*, *uplo*]) = <fortran object>
 Wrapper for `dfttr`.

Parameters

n [input int]
arf [input rank-1 array('d') with bounds (nt)]

Returns

a [rank-2 array('d') with bounds (lda,n)]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.ctfttr

`scipy.linalg.lapack.ctfttr` (*n*, *arf*[, *transr*, *uplo*]) = <fortran object>
 Wrapper for `ctfttr`.

Parameters

n [input int]
arf [input rank-1 array('F') with bounds (nt)]

Returns

a [rank-2 array('F') with bounds (lda,n)]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.ztfttr

`scipy.linalg.lapack.ztfttr` (*n*, *arf*[, *transr*, *uplo*]) = <fortran object>
 Wrapper for `ztfttr`.

Parameters

n [input int]
arf [input rank-1 array('D') with bounds (nt)]

Returns

a [rank-2 array('D') with bounds (lda,n)]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.stgsen

`scipy.linalg.lapack.stgsen` (*select*, *a*, *b*, *q*, *z*[, *lwork*, *liwork*, *overwrite_a*, *overwrite_b*, *overwrite_q*, *overwrite_z*]) = <fortran object>
 Wrapper for `stgsen`.

Parameters

select [input rank-1 array('i') with bounds (n)]
a [input rank-2 array('f') with bounds (lda,n)]
b [input rank-2 array('f') with bounds (ldb,n)]
q [input rank-2 array('f') with bounds (ldq,n)]
z [input rank-2 array('f') with bounds (ldz,n)]

Returns

a [rank-2 array('f') with bounds (lda,n)]
b [rank-2 array('f') with bounds (ldb,n)]
alphar [rank-1 array('f') with bounds (n)]
alphai [rank-1 array('f') with bounds (n)]

beta	[rank-1 array('f') with bounds (n)]
q	[rank-2 array('f') with bounds (ldq,n)]
z	[rank-2 array('f') with bounds (ldz,n)]
m	[int]
pl	[float]
pr	[float]
dif	[rank-1 array('f') with bounds (2)]
work	[rank-1 array('f') with bounds (MAX(lwork,1))]
iwork	[rank-1 array('i') with bounds (MAX(1,liwork))]
info	[int]

Other Parameters

overwrite_a	[input int, optional] Default: 0
overwrite_b	[input int, optional] Default: 0
overwrite_q	[input int, optional] Default: 0
overwrite_z	[input int, optional] Default: 0
lwork	[input int, optional] Default: max(MAX(4*n+16,2*m*(n-m)),1)
liwork	[input int, optional] Default: n+6

scipy.linalg.lapack.dtgsen

`scipy.linalg.lapack.dtgsen` (*select*, *a*, *b*, *q*, *z*[, *lwork*, *liwork*, *overwrite_a*, *overwrite_b*, *overwrite_q*, *overwrite_z*]) = **<fortran object>**

Wrapper for dtgsen.

Parameters

select	[input rank-1 array('i') with bounds (n)]
a	[input rank-2 array('d') with bounds (lda,n)]
b	[input rank-2 array('d') with bounds (ldb,n)]
q	[input rank-2 array('d') with bounds (ldq,n)]
z	[input rank-2 array('d') with bounds (ldz,n)]

Returns

a	[rank-2 array('d') with bounds (lda,n)]
b	[rank-2 array('d') with bounds (ldb,n)]
alphar	[rank-1 array('d') with bounds (n)]
alphai	[rank-1 array('d') with bounds (n)]
beta	[rank-1 array('d') with bounds (n)]
q	[rank-2 array('d') with bounds (ldq,n)]
z	[rank-2 array('d') with bounds (ldz,n)]
m	[int]
pl	[float]
pr	[float]
dif	[rank-1 array('d') with bounds (2)]
work	[rank-1 array('d') with bounds (MAX(lwork,1))]
iwork	[rank-1 array('i') with bounds (MAX(1,liwork))]
info	[int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
overwrite_q [input int, optional] Default: 0
overwrite_z [input int, optional] Default: 0
lwork [input int, optional] Default: $\max(\text{MAX}(4*n+16, 2*m*(n-m)), 1)$
liwork [input int, optional] Default: $n+6$

scipy.linalg.lapack.ctgsen

`scipy.linalg.lapack.ctgsen` (*select*, *a*, *b*, *q*, *z*[, *lwork*, *liwork*, *overwrite_a*, *overwrite_b*, *overwrite_q*, *overwrite_z*]) = <fortran object>

Wrapper for ctgsen.

Parameters

select [input rank-1 array('i') with bounds (n)]
a [input rank-2 array('F') with bounds (lda,n)]
b [input rank-2 array('F') with bounds (ldb,n)]
q [input rank-2 array('F') with bounds (ldq,n)]
z [input rank-2 array('F') with bounds (ldz,n)]

Returns

a [rank-2 array('F') with bounds (lda,n)]
b [rank-2 array('F') with bounds (ldb,n)]
alpha [rank-1 array('F') with bounds (n)]
beta [rank-1 array('F') with bounds (n)]
q [rank-2 array('F') with bounds (ldq,n)]
z [rank-2 array('F') with bounds (ldz,n)]
m [int]
pl [float]
pr [float]
dif [rank-1 array('f') with bounds (2)]
work [rank-1 array('F') with bounds (MAX(lwork,1))]
iwork [rank-1 array('i') with bounds (MAX(1,liwork))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
overwrite_q [input int, optional] Default: 0
overwrite_z [input int, optional] Default: 0
lwork [input int, optional] Default: $\max(2*m*(n-m), 1)$
liwork [input int, optional] Default: $n+2$

scipy.linalg.lapack.ztgsen

`scipy.linalg.lapack.ztgsen` (*select*, *a*, *b*, *q*, *z*[, *lwork*, *liwork*, *overwrite_a*, *overwrite_b*, *overwrite_q*, *overwrite_z*]) = <fortran object>

Wrapper for `ztgsen`.

Parameters

select [input rank-1 array('i') with bounds (n)]
a [input rank-2 array('D') with bounds (lda,n)]
b [input rank-2 array('D') with bounds (ldb,n)]
q [input rank-2 array('D') with bounds (ldq,n)]
z [input rank-2 array('D') with bounds (ldz,n)]

Returns

a [rank-2 array('D') with bounds (lda,n)]
b [rank-2 array('D') with bounds (ldb,n)]
alpha [rank-1 array('D') with bounds (n)]
beta [rank-1 array('D') with bounds (n)]
q [rank-2 array('D') with bounds (ldq,n)]
z [rank-2 array('D') with bounds (ldz,n)]
m [int]
pl [float]
pr [float]
dif [rank-1 array('d') with bounds (2)]
work [rank-1 array('D') with bounds (MAX(lwork,1))]
iwork [rank-1 array('i') with bounds (MAX(1,liwork))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0
overwrite_q [input int, optional] Default: 0
overwrite_z [input int, optional] Default: 0
lwork [input int, optional] Default: $\max(2*m*(n-m), 1)$
liwork [input int, optional] Default: $n+2$

scipy.linalg.lapack.stpttf

`scipy.linalg.lapack.stpttf` (*n*, *ap*[, *transr*, *uplo*]) = <fortran object>

Wrapper for `stpttf`.

Parameters

n [input int]
ap [input rank-1 array('f') with bounds (nt)]

Returns

arf [rank-1 array('f') with bounds (nt)]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.dtpdff

`scipy.linalg.lapack.dtpdff(n, ap[, transr, uplo]) = <fortran object>`
 Wrapper for dtpdff.

Parameters

n [input int]
ap [input rank-1 array('d') with bounds (nt)]

Returns

arf [rank-1 array('d') with bounds (nt)]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.ctpdff

`scipy.linalg.lapack.ctpdff(n, ap[, transr, uplo]) = <fortran object>`
 Wrapper for ctpdff.

Parameters

n [input int]
ap [input rank-1 array('F') with bounds (nt)]

Returns

arf [rank-1 array('F') with bounds (nt)]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.ztpdff

`scipy.linalg.lapack.ztpdff(n, ap[, transr, uplo]) = <fortran object>`
 Wrapper for ztpdff.

Parameters

n [input int]
ap [input rank-1 array('D') with bounds (nt)]

Returns

arf [rank-1 array('D') with bounds (nt)]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.stpttr

`scipy.linalg.lapack.stpttr(n, ap[, uplo]) = <fortran object>`
 Wrapper for `stpttr`.

Parameters

n [input int]
ap [input rank-1 array('f') with bounds (nt)]

Returns

a [rank-2 array('f') with bounds (n,n)]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.dtptr

`scipy.linalg.lapack.dtptr(n, ap[, uplo]) = <fortran object>`
 Wrapper for `dtptr`.

Parameters

n [input int]
ap [input rank-1 array('d') with bounds (nt)]

Returns

a [rank-2 array('d') with bounds (n,n)]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.ctptr

`scipy.linalg.lapack.ctptr(n, ap[, uplo]) = <fortran object>`
 Wrapper for `ctptr`.

Parameters

n [input int]
ap [input rank-1 array('F') with bounds (nt)]

Returns

a [rank-2 array('F') with bounds (n,n)]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.ztptrr

`scipy.linalg.lapack.ztptrr` (*n*, *ap*[, *uplo*]) = <fortran object>
 Wrapper for `ztptrr`.

Parameters

n [input int]
ap [input rank-1 array('D') with bounds (n)]

Returns

a [rank-2 array('D') with bounds (n,n)]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.strsyl

`scipy.linalg.lapack.strsyl` (*a*, *b*, *c*[, *trana*, *tranb*, *isgn*, *overwrite_c*]) = <fortran object>
 Wrapper for `strsyl`.

Parameters

a [input rank-2 array('f') with bounds (m,m)]
b [input rank-2 array('f') with bounds (n,n)]
c [input rank-2 array('f') with bounds (m,n)]

Returns

x [rank-2 array('f') with bounds (m,n) and c storage]
scale [float]
info [int]

Other Parameters

trana [input string(len=1), optional] Default: 'N'
tranb [input string(len=1), optional] Default: 'N'
isgn [input int, optional] Default: 1
overwrite_c [input int, optional] Default: 0

scipy.linalg.lapack.dtrsyl

`scipy.linalg.lapack.dtrsyl` (*a*, *b*, *c*[, *trana*, *tranb*, *isgn*, *overwrite_c*]) = <fortran object>
 Wrapper for `dtrsyl`.

Parameters

a [input rank-2 array('d') with bounds (m,m)]
b [input rank-2 array('d') with bounds (n,n)]
c [input rank-2 array('d') with bounds (m,n)]

Returns

x [rank-2 array('d') with bounds (m,n) and c storage]
scale [float]
info [int]

Other Parameters

trana [input string(len=1), optional] Default: 'N'
tranb [input string(len=1), optional] Default: 'N'
isgn [input int, optional] Default: 1
overwrite_c [input int, optional] Default: 0

scipy.linalg.lapack.ctrsyl

`scipy.linalg.lapack.ctrsyl(a, b, c[, trana, tranb, isgn, overwrite_c]) = <fortran object>`
 Wrapper for ctrsyl.

Parameters

a [input rank-2 array('F') with bounds (m,m)]
b [input rank-2 array('F') with bounds (n,n)]
c [input rank-2 array('F') with bounds (m,n)]

Returns

x [rank-2 array('F') with bounds (m,n) and c storage]
scale [float]
info [int]

Other Parameters

trana [input string(len=1), optional] Default: 'N'
tranb [input string(len=1), optional] Default: 'N'
isgn [input int, optional] Default: 1
overwrite_c [input int, optional] Default: 0

scipy.linalg.lapack.ztrsyl

`scipy.linalg.lapack.ztrsyl(a, b, c[, trana, tranb, isgn, overwrite_c]) = <fortran object>`
 Wrapper for ztrsyl.

Parameters

a [input rank-2 array('D') with bounds (m,m)]
b [input rank-2 array('D') with bounds (n,n)]
c [input rank-2 array('D') with bounds (m,n)]

Returns

x [rank-2 array('D') with bounds (m,n) and c storage]
scale [float]
info [int]

Other Parameters

trana [input string(len=1), optional] Default: 'N'
tranb [input string(len=1), optional] Default: 'N'
isgn [input int, optional] Default: 1
overwrite_c [input int, optional] Default: 0

scipy.linalg.lapack.strtri

`scipy.linalg.lapack.strtri(c[, lower, unitdiag, overwrite_c]) = <fortran object>`
 Wrapper for `strtri`.

Parameters

c [input rank-2 array('f') with bounds (n,n)]

Returns

inv_c [rank-2 array('f') with bounds (n,n) and c storage]

info [int]

Other Parameters

overwrite_c [input int, optional] Default: 0

lower [input int, optional] Default: 0

unitdiag [input int, optional] Default: 0

scipy.linalg.lapack.dtrtri

`scipy.linalg.lapack.dtrtri(c[, lower, unitdiag, overwrite_c]) = <fortran object>`
 Wrapper for `dtrtri`.

Parameters

c [input rank-2 array('d') with bounds (n,n)]

Returns

inv_c [rank-2 array('d') with bounds (n,n) and c storage]

info [int]

Other Parameters

overwrite_c [input int, optional] Default: 0

lower [input int, optional] Default: 0

unitdiag [input int, optional] Default: 0

scipy.linalg.lapack.ctrtri

`scipy.linalg.lapack.ctrtri(c[, lower, unitdiag, overwrite_c]) = <fortran object>`
 Wrapper for `ctrtri`.

Parameters

c [input rank-2 array('F') with bounds (n,n)]

Returns

inv_c [rank-2 array('F') with bounds (n,n) and c storage]

info [int]

Other Parameters

overwrite_c [input int, optional] Default: 0

lower [input int, optional] Default: 0

unitdiag [input int, optional] Default: 0

scipy.linalg.lapack.ztrtri

`scipy.linalg.lapack.ztrtri(c[, lower, unitdiag, overwrite_c]) = <fortran object>`

Wrapper for `ztrtri`.

Parameters

c [input rank-2 array('D') with bounds (n,n)]

Returns

inv_c [rank-2 array('D') with bounds (n,n) and c storage]

info [int]

Other Parameters

overwrite_c [input int, optional] Default: 0

lower [input int, optional] Default: 0

unitdiag [input int, optional] Default: 0

scipy.linalg.lapack.strtrs

`scipy.linalg.lapack.strtrs(a, b[, lower, trans, unitdiag, lda, overwrite_b]) = <fortran object>`

Wrapper for `strtrs`.

Parameters

a [input rank-2 array('f') with bounds (lda,n)]

b [input rank-2 array('f') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('f') with bounds (ldb,nrhs) and b storage]

info [int]

Other Parameters

lower [input int, optional] Default: 0

trans [input int, optional] Default: 0

unitdiag [input int, optional] Default: 0

lda [input int, optional] Default: `shape(a,0)`

overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.dtrtrs

`scipy.linalg.lapack.dtrtrs(a, b[, lower, trans, unitdiag, lda, overwrite_b]) = <fortran object>`

Wrapper for `dtrtrs`.

Parameters

a [input rank-2 array('d') with bounds (lda,n)]
b [input rank-2 array('d') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('d') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
unitdiag [input int, optional] Default: 0
lda [input int, optional] Default: shape(a,0)
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.ctrtrs

`scipy.linalg.lapack.ctrtrs(a, b[, lower, trans, unitdiag, lda, overwrite_b]) = <fortran object>`

Wrapper for `ctrtrs`.

Parameters

a [input rank-2 array('F') with bounds (lda,n)]
b [input rank-2 array('F') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('F') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
unitdiag [input int, optional] Default: 0
lda [input int, optional] Default: shape(a,0)
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.ztrtrs

`scipy.linalg.lapack.ztrtrs(a, b[, lower, trans, unitdiag, lda, overwrite_b]) = <fortran object>`

Wrapper for `ztrtrs`.

Parameters

a [input rank-2 array('D') with bounds (lda,n)]
b [input rank-2 array('D') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('D') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

lower [input int, optional] Default: 0
trans [input int, optional] Default: 0
unitdiag [input int, optional] Default: 0
lda [input int, optional] Default: shape(a,0)
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.strttf

`scipy.linalg.lapack.strttf(a[, transr, uplo]) = <fortran object>`

Wrapper for `strttf`.

Parameters

a [input rank-2 array('f') with bounds (lda,n)]

Returns

arf [rank-1 array('f') with bounds (n*(n+1)/2)]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'
uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.dtrttf

`scipy.linalg.lapack.dtrttf(a[, transr, uplo]) = <fortran object>`

Wrapper for `dtrttf`.

Parameters

a [input rank-2 array('d') with bounds (lda,n)]

Returns

arf [rank-1 array('d') with bounds (n*(n+1)/2)]
info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.ctrfff

`scipy.linalg.lapack.ctrfff(a[, transr, uplo]) = <fortran object>`
 Wrapper for `ctrfff`.

Parameters

a [input rank-2 array('F') with bounds (lda,n)]

Returns

arf [rank-1 array('F') with bounds (n*(n+1)/2)]

info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.ztrfff

`scipy.linalg.lapack.ztrfff(a[, transr, uplo]) = <fortran object>`
 Wrapper for `ztrfff`.

Parameters

a [input rank-2 array('D') with bounds (lda,n)]

Returns

arf [rank-1 array('D') with bounds (n*(n+1)/2)]

info [int]

Other Parameters

transr [input string(len=1), optional] Default: 'N'

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.strttp

`scipy.linalg.lapack.strttp(a[, uplo]) = <fortran object>`
 Wrapper for `strttp`.

Parameters

a [input rank-2 array('f') with bounds (lda,n)]

Returns

ap [rank-1 array('f') with bounds (n*(n+1)/2)]

info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.dtrttp

`scipy.linalg.lapack.dtrttp(a[, uplo]) = <fortran object>`
 Wrapper for `dtrttp`.

Parameters

a [input rank-2 array('d') with bounds (lda,n)]

Returns

ap [rank-1 array('d') with bounds (n*(n+1)/2)]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.ctrttp

`scipy.linalg.lapack.ctrttp(a[, uplo]) = <fortran object>`
 Wrapper for `ctrttp`.

Parameters

a [input rank-2 array('F') with bounds (lda,n)]

Returns

ap [rank-1 array('F') with bounds (n*(n+1)/2)]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.ztrttp

`scipy.linalg.lapack.ztrttp(a[, uplo]) = <fortran object>`
 Wrapper for `ztrttp`.

Parameters

a [input rank-2 array('D') with bounds (lda,n)]

Returns

ap [rank-1 array('D') with bounds (n*(n+1)/2)]
info [int]

Other Parameters

uplo [input string(len=1), optional] Default: 'U'

scipy.linalg.lapack.stzrzf

`scipy.linalg.lapack.stzrzf(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `stzrzf`.

Parameters

a [input rank-2 array('f') with bounds (m,n)]

Returns

rz [rank-2 array('f') with bounds (m,n) and a storage]

tau [rank-1 array('f') with bounds (m)]

info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

lwork [input int, optional] Default: MAX(m,1)

scipy.linalg.lapack.dtzrzf

`scipy.linalg.lapack.dtzrzf(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `dtzrzf`.

Parameters

a [input rank-2 array('d') with bounds (m,n)]

Returns

rz [rank-2 array('d') with bounds (m,n) and a storage]

tau [rank-1 array('d') with bounds (m)]

info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

lwork [input int, optional] Default: MAX(m,1)

scipy.linalg.lapack.ctzrzf

`scipy.linalg.lapack.ctzrzf(a[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `ctzrzf`.

Parameters

a [input rank-2 array('F') with bounds (m,n)]

Returns

rz [rank-2 array('F') with bounds (m,n) and a storage]

tau [rank-1 array('F') with bounds (m)]

info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

lwork [input int, optional] Default: MAX(m,1)

scipy.linalg.lapack.ztzzrf

`scipy.linalg.lapack.ztzzrf(a[, lwork, overwrite_a]) = <fortran object>`

Wrapper for `ztzzrf`.

Parameters

a [input rank-2 array('D') with bounds (m,n)]

Returns

rz [rank-2 array('D') with bounds (m,n) and a storage]

tau [rank-1 array('D') with bounds (m)]

info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0

lwork [input int, optional] Default: MAX(m,1)

scipy.linalg.lapack.stzzrf_lwork

`scipy.linalg.lapack.stzzrf_lwork(m, n) = <fortran object>`

Wrapper for `stzzrf_lwork`.

Parameters

m [input int]

n [input int]

Returns

work [float]

info [int]

scipy.linalg.lapack.dtzzrf_lwork

`scipy.linalg.lapack.dtzzrf_lwork(m, n) = <fortran object>`

Wrapper for `dtzzrf_lwork`.

Parameters

m [input int]

n [input int]

Returns

work [float]

info [int]

scipy.linalg.lapack.ctzrzf_lwork

`scipy.linalg.lapack.ctzrzf_lwork(m, n) = <fortran object>`
 Wrapper for `ctzrzf_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [complex]
info [int]

scipy.linalg.lapack.ztzrzf_lwork

`scipy.linalg.lapack.ztzrzf_lwork(m, n) = <fortran object>`
 Wrapper for `ztzrzf_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [complex]
info [int]

scipy.linalg.lapack.cunghr

`scipy.linalg.lapack.cunghr(a, tau[, lo, hi, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `cunghr`.

Parameters

a [input rank-2 array('F') with bounds (n,n)]
tau [input rank-1 array('F') with bounds (n - 1)]

Returns

ht [rank-2 array('F') with bounds (n,n) and a storage]
info [int]

Other Parameters

lo [input int, optional] Default: 0
hi [input int, optional] Default: n-1
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(hi-lo,1)

scipy.linalg.lapack.zunghr

`scipy.linalg.lapack.zunghr(a, tau[, lo, hi, lwork, overwrite_a]) = <fortran object>`
 Wrapper for zunghr.

Parameters

a [input rank-2 array('D') with bounds (n,n)]
tau [input rank-1 array('D') with bounds (n - 1)]

Returns

ht [rank-2 array('D') with bounds (n,n) and a storage]
info [int]

Other Parameters

lo [input int, optional] Default: 0
hi [input int, optional] Default: n-1
overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(hi-lo,1)

scipy.linalg.lapack.cunghr_lwork

`scipy.linalg.lapack.cunghr_lwork(n[, lo, hi]) = <fortran object>`
 Wrapper for cunghr_lwork.

Parameters

n [input int]

Returns

work [complex]
info [int]

Other Parameters

lo [input int, optional] Default: 0
hi [input int, optional] Default: n-1

scipy.linalg.lapack.zunghr_lwork

`scipy.linalg.lapack.zunghr_lwork(n[, lo, hi]) = <fortran object>`
 Wrapper for zunghr_lwork.

Parameters

n [input int]

Returns

work [complex]
info [int]

Other Parameters

lo [input int, optional] Default: 0
hi [input int, optional] Default: n-1

scipy.linalg.lapack.cungqr

`scipy.linalg.lapack.cungqr(a, tau[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `cungqr`.

Parameters

a [input rank-2 array('F') with bounds (m,n)]
tau [input rank-1 array('F') with bounds (k)]

Returns

q [rank-2 array('F') with bounds (m,n) and a storage]
work [rank-1 array('F') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)

scipy.linalg.lapack.zungqr

`scipy.linalg.lapack.zungqr(a, tau[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `zungqr`.

Parameters

a [input rank-2 array('D') with bounds (m,n)]
tau [input rank-1 array('D') with bounds (k)]

Returns

q [rank-2 array('D') with bounds (m,n) and a storage]
work [rank-1 array('D') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
lwork [input int, optional] Default: max(3*n,1)

scipy.linalg.lapack.cungrq

`scipy.linalg.lapack.cungrq(a, tau[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for `cungrq`.

Parameters

a [input rank-2 array('F') with bounds (m,n)]
tau [input rank-1 array('F') with bounds (k)]

Returns

q [rank-2 array('F') with bounds (m,n) and a storage]
work [rank-1 array('F') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0
lwork
 [input int, optional] Default: max(3*m,1)

scipy.linalg.lapack.zungqr

`scipy.linalg.lapack.zungqr(a, tau[, lwork, overwrite_a]) = <fortran object>`
 Wrapper for zungqr.

Parameters

a
 [input rank-2 array('D') with bounds (m,n)]
tau
 [input rank-1 array('D') with bounds (k)]

Returns

q
 [rank-2 array('D') with bounds (m,n) and a storage]
work
 [rank-1 array('D') with bounds (MAX(lwork,1))]
info
 [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0
lwork
 [input int, optional] Default: max(3*m,1)

scipy.linalg.lapack.cunmqr

`scipy.linalg.lapack.cunmqr(side, trans, a, tau, c, lwork[, overwrite_c]) = <fortran object>`
 Wrapper for cunmqr.

Parameters

side
 [input string(len=1)]
trans
 [input string(len=1)]
a
 [input rank-2 array('F') with bounds (lda,k)]
tau
 [input rank-1 array('F') with bounds (k)]
c
 [input rank-2 array('F') with bounds (ldc,n)]
lwork
 [input int]

Returns

cq
 [rank-2 array('F') with bounds (ldc,n) and c storage]
work
 [rank-1 array('F') with bounds (MAX(lwork,1))]
info
 [int]

Other Parameters

overwrite_c
 [input int, optional] Default: 0

scipy.linalg.lapack.zunmqr

`scipy.linalg.lapack.zunmqr` (*side*, *trans*, *a*, *tau*, *c*, *lwork*[, *overwrite_c*]) = <fortran object>
 Wrapper for `zunmqr`.

Parameters

side [input string(len=1)]
trans [input string(len=1)]
a [input rank-2 array('D') with bounds (lda,k)]
tau [input rank-1 array('D') with bounds (k)]
c [input rank-2 array('D') with bounds (ldc,n)]
lwork [input int]

Returns

cq [rank-2 array('D') with bounds (ldc,n) and c storage]
work [rank-1 array('D') with bounds (MAX(lwork,1))]
info [int]

Other Parameters

overwrite_c
 [input int, optional] Default: 0

scipy.linalg.lapack.sgeqrt

`scipy.linalg.lapack.sgeqrt` (*nb*, *a*[, *overwrite_a*]) = <fortran object>
 Wrapper for `sgeqrt`.

Parameters

nb [input int]
a [input rank-2 array('f') with bounds (m,n)]

Returns

a [rank-2 array('f') with bounds (m,n)]
t [rank-2 array('f') with bounds (nb,MIN(m,n))]
info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0

scipy.linalg.lapack.dgeqrt

`scipy.linalg.lapack.dgeqrt` (*nb*, *a*[, *overwrite_a*]) = <fortran object>
 Wrapper for `dgeqrt`.

Parameters

nb [input int]
a [input rank-2 array('d') with bounds (m,n)]

Returns

a [rank-2 array('d') with bounds (m,n)]
t [rank-2 array('d') with bounds (nb,MIN(m,n))]

info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

scipy.linalg.lapack.cgeqrt

`scipy.linalg.lapack.cgeqrt` (*nb*, *a*[, *overwrite_a*]) = <fortran object>
Wrapper for `cgeqrt`.

Parameters

nb [input int]
a [input rank-2 array('F') with bounds (m,n)]

Returns

a [rank-2 array('F') with bounds (m,n)]
t [rank-2 array('F') with bounds (nb,MIN(m,n))]
info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

scipy.linalg.lapack.zgeqrt

`scipy.linalg.lapack.zgeqrt` (*nb*, *a*[, *overwrite_a*]) = <fortran object>
Wrapper for `zgeqrt`.

Parameters

nb [input int]
a [input rank-2 array('D') with bounds (m,n)]

Returns

a [rank-2 array('D') with bounds (m,n)]
t [rank-2 array('D') with bounds (nb,MIN(m,n))]
info [int]

Other Parameters

overwrite_a
[input int, optional] Default: 0

scipy.linalg.lapack.sgemqrt

`scipy.linalg.lapack.sgemqrt` (*v*, *t*, *c* [, *side*, *trans*, *overwrite_c*]) = <fortran object>
 Wrapper for `sgemqrt`.

Parameters

v [input rank-2 array('f') with bounds ((side[0]=='L'?m:n),k)]
t [input rank-2 array('f') with bounds (nb,k)]
c [input rank-2 array('f') with bounds (m,n)]

Returns

c [rank-2 array('f') with bounds (m,n)]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'
overwrite_c [input int, optional] Default: 0

scipy.linalg.lapack.dgemqrt

`scipy.linalg.lapack.dgemqrt` (*v*, *t*, *c* [, *side*, *trans*, *overwrite_c*]) = <fortran object>
 Wrapper for `dgemqrt`.

Parameters

v [input rank-2 array('d') with bounds ((side[0]=='L'?m:n),k)]
t [input rank-2 array('d') with bounds (nb,k)]
c [input rank-2 array('d') with bounds (m,n)]

Returns

c [rank-2 array('d') with bounds (m,n)]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'
overwrite_c [input int, optional] Default: 0

scipy.linalg.lapack.cgemqrt

`scipy.linalg.lapack.cgemqrt` (*v*, *t*, *c* [, *side*, *trans*, *overwrite_c*]) = <fortran object>
 Wrapper for `cgemqrt`.

Parameters

v [input rank-2 array('F') with bounds ((side[0]=='L'?m:n),k)]
t [input rank-2 array('F') with bounds (nb,k)]
c [input rank-2 array('F') with bounds (m,n)]

Returns

c [rank-2 array('F') with bounds (m,n)]

info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'
overwrite_c
 [input int, optional] Default: 0

scipy.linalg.lapack.zgemqrt

`scipy.linalg.lapack.zgemqrt(v, t, c[, side, trans, overwrite_c]) = <fortran object>`
 Wrapper for zgemqrt.

Parameters

v [input rank-2 array('D') with bounds ((side[0]=='L'?m:n),k)]
t [input rank-2 array('D') with bounds (nb,k)]
c [input rank-2 array('D') with bounds (m,n)]

Returns

c [rank-2 array('D') with bounds (m,n)]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'
overwrite_c
 [input int, optional] Default: 0

scipy.linalg.lapack.sgttrf

`scipy.linalg.lapack.sgttrf(dl, d, du[, overwrite_dl, overwrite_d, overwrite_du]) = <fortran object>`

Wrapper for sgttrf.

Parameters

dl [input rank-1 array('f') with bounds (n - 1)]
d [input rank-1 array('f') with bounds (n)]
du [input rank-1 array('f') with bounds (n - 1)]

Returns

dl [rank-1 array('f') with bounds (n - 1)]
d [rank-1 array('f') with bounds (n)]
du [rank-1 array('f') with bounds (n - 1)]
du2 [rank-1 array('f') with bounds (n - 2)]
ipiv [rank-1 array('i') with bounds (n)]
info [int]

Other Parameters

overwrite_dl
 [input int, optional] Default: 0
overwrite_d
 [input int, optional] Default: 0

overwrite_du
[input int, optional] Default: 0

scipy.linalg.lapack.dgtrf

`scipy.linalg.lapack.dgtrf` (*dl*, *d*, *du*[, *overwrite_dl*, *overwrite_d*, *overwrite_du*]) = <fortran object>

Wrapper for `dgtrf`.

Parameters

dl [input rank-1 array('d') with bounds (n - 1)]
d [input rank-1 array('d') with bounds (n)]
du [input rank-1 array('d') with bounds (n - 1)]

Returns

dl [rank-1 array('d') with bounds (n - 1)]
d [rank-1 array('d') with bounds (n)]
du [rank-1 array('d') with bounds (n - 1)]
du2 [rank-1 array('d') with bounds (n - 2)]
ipiv [rank-1 array('i') with bounds (n)]
info [int]

Other Parameters

overwrite_dl
[input int, optional] Default: 0
overwrite_d
[input int, optional] Default: 0
overwrite_du
[input int, optional] Default: 0

scipy.linalg.lapack.cgtrf

`scipy.linalg.lapack.cgtrf` (*dl*, *d*, *du*[, *overwrite_dl*, *overwrite_d*, *overwrite_du*]) = <fortran object>

Wrapper for `cgtrf`.

Parameters

dl [input rank-1 array('F') with bounds (n - 1)]
d [input rank-1 array('F') with bounds (n)]
du [input rank-1 array('F') with bounds (n - 1)]

Returns

dl [rank-1 array('F') with bounds (n - 1)]
d [rank-1 array('F') with bounds (n)]
du [rank-1 array('F') with bounds (n - 1)]
du2 [rank-1 array('F') with bounds (n - 2)]
ipiv [rank-1 array('i') with bounds (n)]
info [int]

Other Parameters

overwrite_dl
[input int, optional] Default: 0

overwrite_d
 [input int, optional] Default: 0
overwrite_du
 [input int, optional] Default: 0

scipy.linalg.lapack.zgttrf

`scipy.linalg.lapack.zgttrf (dl, d, du[, overwrite_dl, overwrite_d, overwrite_du]) = <fortran object>`

Wrapper for `zgttrf`.

Parameters

dl [input rank-1 array('D') with bounds (n - 1)]
d [input rank-1 array('D') with bounds (n)]
du [input rank-1 array('D') with bounds (n - 1)]

Returns

dl [rank-1 array('D') with bounds (n - 1)]
d [rank-1 array('D') with bounds (n)]
du [rank-1 array('D') with bounds (n - 1)]
du2 [rank-1 array('D') with bounds (n - 2)]
ipiv [rank-1 array('i') with bounds (n)]
info [int]

Other Parameters

overwrite_dl
 [input int, optional] Default: 0
overwrite_d
 [input int, optional] Default: 0
overwrite_du
 [input int, optional] Default: 0

scipy.linalg.lapack.sgttrs

`scipy.linalg.lapack.sgttrs (dl, d, du, du2, ipiv, b[, trans, overwrite_b]) = <fortran object>`

Wrapper for `sgttrs`.

Parameters

dl [input rank-1 array('f') with bounds (n - 1)]
d [input rank-1 array('f') with bounds (n)]
du [input rank-1 array('f') with bounds (n - 1)]
du2 [input rank-1 array('f') with bounds (n - 2)]
ipiv [input rank-1 array('i') with bounds (n)]
b [input rank-2 array('f') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('f') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

trans [input string(len=1), optional] Default: 'N'

overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.dgtrfs

`scipy.linalg.lapack.dgtrfs` (*dl, d, du, du2, ipiv, b*[, *trans, overwrite_b*]) = <fortran object>
 Wrapper for dgtrfs.

Parameters

dl [input rank-1 array('d') with bounds (n - 1)]
d [input rank-1 array('d') with bounds (n)]
du [input rank-1 array('d') with bounds (n - 1)]
du2 [input rank-1 array('d') with bounds (n - 2)]
ipiv [input rank-1 array('i') with bounds (n)]
b [input rank-2 array('d') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('d') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

trans [input string(len=1), optional] Default: 'N'
overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.cgtrfs

`scipy.linalg.lapack.cgtrfs` (*dl, d, du, du2, ipiv, b*[, *trans, overwrite_b*]) = <fortran object>
 Wrapper for cgtrfs.

Parameters

dl [input rank-1 array('F') with bounds (n - 1)]
d [input rank-1 array('F') with bounds (n)]
du [input rank-1 array('F') with bounds (n - 1)]
du2 [input rank-1 array('F') with bounds (n - 2)]
ipiv [input rank-1 array('i') with bounds (n)]
b [input rank-2 array('F') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('F') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

trans [input string(len=1), optional] Default: 'N'
overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.zgttrs

`scipy.linalg.lapack.zgttrs (dl, d, du, du2, ipiv, b[, trans, overwrite_b]) = <fortran object>`
 Wrapper for `zgttrs`.

Parameters

dl [input rank-1 array('D') with bounds (n - 1)]
d [input rank-1 array('D') with bounds (n)]
du [input rank-1 array('D') with bounds (n - 1)]
du2 [input rank-1 array('D') with bounds (n - 2)]
ipiv [input rank-1 array('i') with bounds (n)]
b [input rank-2 array('D') with bounds (ldb,nrhs)]

Returns

x [rank-2 array('D') with bounds (ldb,nrhs) and b storage]
info [int]

Other Parameters

trans [input string(len=1), optional] Default: 'N'
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.stpqrt

`scipy.linalg.lapack.stpqrt (l, nb, a, b[, overwrite_a, overwrite_b]) = <fortran object>`
 Wrapper for `stpqrt`.

Parameters

l [input int]
nb [input int]
a [input rank-2 array('f') with bounds (n,n)]
b [input rank-2 array('f') with bounds (m,n)]

Returns

a [rank-2 array('f') with bounds (n,n)]
b [rank-2 array('f') with bounds (m,n)]
t [rank-2 array('f') with bounds (nb,n)]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.dtpqrt

`scipy.linalg.lapack.dtpqrt` (*l*, *nb*, *a*, *b*[, *overwrite_a*, *overwrite_b*]) = <fortran object>
 Wrapper for dtpqrt.

Parameters

l [input int]
nb [input int]
a [input rank-2 array('d') with bounds (n,n)]
b [input rank-2 array('d') with bounds (m,n)]

Returns

a [rank-2 array('d') with bounds (n,n)]
b [rank-2 array('d') with bounds (m,n)]
t [rank-2 array('d') with bounds (nb,n)]
info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0
overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.ctpqrt

`scipy.linalg.lapack.ctpqrt` (*l*, *nb*, *a*, *b*[, *overwrite_a*, *overwrite_b*]) = <fortran object>
 Wrapper for ctpqrt.

Parameters

l [input int]
nb [input int]
a [input rank-2 array('F') with bounds (n,n)]
b [input rank-2 array('F') with bounds (m,n)]

Returns

a [rank-2 array('F') with bounds (n,n)]
b [rank-2 array('F') with bounds (m,n)]
t [rank-2 array('F') with bounds (nb,n)]
info [int]

Other Parameters

overwrite_a
 [input int, optional] Default: 0
overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.ztpqrt

`scipy.linalg.lapack.ztpqrt` (*l*, *nb*, *a*, *b*[, *overwrite_a*, *overwrite_b*]) = <fortran object>
 Wrapper for `ztpqrt`.

Parameters

l [input int]
nb [input int]
a [input rank-2 array('D') with bounds (n,n)]
b [input rank-2 array('D') with bounds (m,n)]

Returns

a [rank-2 array('D') with bounds (n,n)]
b [rank-2 array('D') with bounds (m,n)]
t [rank-2 array('D') with bounds (nb,n)]
info [int]

Other Parameters

overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.stpmqrt

`scipy.linalg.lapack.stpmqrt` (*l*, *v*, *t*, *a*, *b*[, *side*, *trans*, *overwrite_a*, *overwrite_b*]) = <fortran object>
 Wrapper for `stpmqrt`.

Parameters

l [input int]
v [input rank-2 array('f') with bounds ((side[0]=='L'?m:n),k)]
t [input rank-2 array('f') with bounds (nb,k)]
a [input rank-2 array('f') with bounds ((side[0]=='L'?k:m),(side[0]=='L'?n:k))]
b [input rank-2 array('f') with bounds (m,n)]

Returns

a [rank-2 array('f') with bounds ((side[0]=='L'?k:m),(side[0]=='L'?n:k))]
b [rank-2 array('f') with bounds (m,n)]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.dtpmqrt

`scipy.linalg.lapack.dtpmqrt` (*l, v, t, a, b* [, *side, trans, overwrite_a, overwrite_b*]) = **<fortran object>**

Wrapper for `dtpmqrt`.

Parameters

l [input int]
v [input rank-2 array('d') with bounds ((side[0]=='L'?m:n),k)]
t [input rank-2 array('d') with bounds (nb,k)]
a [input rank-2 array('d') with bounds ((side[0]=='L'?k:m),(side[0]=='L'?n:k))]
b [input rank-2 array('d') with bounds (m,n)]

Returns

a [rank-2 array('d') with bounds ((side[0]=='L'?k:m),(side[0]=='L'?n:k))]
b [rank-2 array('d') with bounds (m,n)]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'
overwrite_a
 [input int, optional] Default: 0
overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.ctpmqrt

`scipy.linalg.lapack.ctpmqrt` (*l, v, t, a, b* [, *side, trans, overwrite_a, overwrite_b*]) = **<fortran object>**

Wrapper for `ctpmqrt`.

Parameters

l [input int]
v [input rank-2 array('F') with bounds ((side[0]=='L'?m:n),k)]
t [input rank-2 array('F') with bounds (nb,k)]
a [input rank-2 array('F') with bounds ((side[0]=='L'?k:m),(side[0]=='L'?n:k))]
b [input rank-2 array('F') with bounds (m,n)]

Returns

a [rank-2 array('F') with bounds ((side[0]=='L'?k:m),(side[0]=='L'?n:k))]
b [rank-2 array('F') with bounds (m,n)]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'
overwrite_a
 [input int, optional] Default: 0
overwrite_b
 [input int, optional] Default: 0

scipy.linalg.lapack.ztpmqrt

`scipy.linalg.lapack.ztpmqrt(l, v, t, a, b[, side, trans, overwrite_a, overwrite_b]) = <fortran object>`

Wrapper for ztpmqrt.

Parameters

l [input int]
v [input rank-2 array('D') with bounds ((side[0]=='L'?m:n),k)]
t [input rank-2 array('D') with bounds (nb,k)]
a [input rank-2 array('D') with bounds ((side[0]=='L'?k:m),(side[0]=='L'?n:k))]
b [input rank-2 array('D') with bounds (m,n)]

Returns

a [rank-2 array('D') with bounds ((side[0]=='L'?k:m),(side[0]=='L'?n:k))]
b [rank-2 array('D') with bounds (m,n)]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'
overwrite_a [input int, optional] Default: 0
overwrite_b [input int, optional] Default: 0

scipy.linalg.lapack.cuncsd

`scipy.linalg.lapack.cuncsd(x11, x12, x21, x22[, compute_u1, compute_u2, compute_v1t, compute_v2t, trans, signs, lwork, lrwork, overwrite_x11, overwrite_x12, overwrite_x21, overwrite_x22]) = <fortran object>`

Wrapper for cuncsd.

Parameters

x11 [input rank-2 array('F') with bounds (p,q)]
x12 [input rank-2 array('F') with bounds (p,mmq)]
x21 [input rank-2 array('F') with bounds (mmp,q)]
x22 [input rank-2 array('F') with bounds (mmp,mmq)]

Returns

cs11 [rank-2 array('F') with bounds (p,q) and x11 storage]
cs12 [rank-2 array('F') with bounds (p,mmq) and x12 storage]
cs21 [rank-2 array('F') with bounds (mmp,q) and x21 storage]
cs22 [rank-2 array('F') with bounds (mmp,mmq) and x22 storage]
theta [rank-1 array('f') with bounds (min(min(p,mmp),min(q,mmq)))]
u1 [rank-2 array('F') with bounds ((compute_u1?p:0),(compute_u1?p:0))]
u2 [rank-2 array('F') with bounds ((compute_u2?mmp:0),(compute_u2?mmp:0))]
v1t [rank-2 array('F') with bounds ((compute_v1t?q:0),(compute_v1t?q:0))]
v2t [rank-2 array('F') with bounds ((compute_v2t?mmq:0),(compute_v2t?mmq:0))]
info [int]

Other Parameters

compute_u1 [input int, optional] Default: 1
compute_u2 [input int, optional] Default: 1
compute_v1t [input int, optional] Default: 1
compute_v2t [input int, optional] Default: 1
trans [input int, optional] Default: 0
signs [input int, optional] Default: 0
overwrite_x11 [input int, optional] Default: 0
overwrite_x12 [input int, optional] Default: 0
overwrite_x21 [input int, optional] Default: 0
overwrite_x22 [input int, optional] Default: 0
lwork [input int, optional] Default: $2*m + \text{MAX}(1, \text{MAX}(\text{mmp}, \text{mmq})) + 1$
lrwork [input int, optional] Default: $5*\text{MAX}(1, q-1) + 4*\text{MAX}(1, q) + 8*q + 1$

scipy.linalg.lapack.zuncsd

`scipy.linalg.lapack.zuncsd(x11, x12, x21, x22[, compute_u1, compute_u2, compute_v1t, compute_v2t, trans, signs, lwork, lrwork, overwrite_x11, overwrite_x12, overwrite_x21, overwrite_x22]) = <fortran object>`

Wrapper for zuncsd.

Parameters

x11 [input rank-2 array('D') with bounds (p,q)]
x12 [input rank-2 array('D') with bounds (p,mmq)]
x21 [input rank-2 array('D') with bounds (mmp,q)]
x22 [input rank-2 array('D') with bounds (mmp,mmq)]

Returns

cs11 [rank-2 array('D') with bounds (p,q) and x11 storage]
cs12 [rank-2 array('D') with bounds (p,mmq) and x12 storage]
cs21 [rank-2 array('D') with bounds (mmp,q) and x21 storage]
cs22 [rank-2 array('D') with bounds (mmp,mmq) and x22 storage]
theta [rank-1 array('d') with bounds (min(min(p,mmp),min(q,mmq)))]
u1 [rank-2 array('D') with bounds ((compute_u1?p:0),(compute_u1?p:0))]
u2 [rank-2 array('D') with bounds ((compute_u2?mmp:0),(compute_u2?mmp:0))]
v1t [rank-2 array('D') with bounds ((compute_v1t?q:0),(compute_v1t?q:0))]
v2t [rank-2 array('D') with bounds ((compute_v2t?mmq:0),(compute_v2t?mmq:0))]
info [int]

Other Parameters

compute_u1 [input int, optional] Default: 1
compute_u2 [input int, optional] Default: 1
compute_v1t [input int, optional] Default: 1

compute_v2t [input int, optional] Default: 1
trans [input int, optional] Default: 0
signs [input int, optional] Default: 0
overwrite_x11 [input int, optional] Default: 0
overwrite_x12 [input int, optional] Default: 0
overwrite_x21 [input int, optional] Default: 0
overwrite_x22 [input int, optional] Default: 0
lwork [input int, optional] Default: $2*m + \text{MAX}(1, \text{MAX}(\text{mmp}, \text{mmq})) + 1$
lrwork [input int, optional] Default: $5*\text{MAX}(1, q-1) + 4*\text{MAX}(1, q) + 8*q + 1$

scipy.linalg.lapack.cuncsd_lwork

`scipy.linalg.lapack.cuncsd_lwork(m, p, q) = <fortran object>`
 Wrapper for `cuncsd_lwork`.

Parameters

m [input int]
p [input int]
q [input int]

Returns

work [complex]
rwork [float]
info [int]

scipy.linalg.lapack.zuncsd_lwork

`scipy.linalg.lapack.zuncsd_lwork(m, p, q) = <fortran object>`
 Wrapper for `zuncsd_lwork`.

Parameters

m [input int]
p [input int]
q [input int]

Returns

work [complex]
rwork [float]
info [int]

scipy.linalg.lapack.cunmrz

`scipy.linalg.lapack.cunmrz` (*a*, *tau*, *c*[, *side*, *trans*, *lwork*, *overwrite_c*]) = <fortran object>
 Wrapper for `cunmrz`.

Parameters

a [input rank-2 array('F') with bounds (k,nt)]
tau [input rank-1 array('F') with bounds (k)]
c [input rank-2 array('F') with bounds (m,n)]

Returns

cq [rank-2 array('F') with bounds (m,n) and c storage]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'
overwrite_c [input int, optional] Default: 0
lwork [input int, optional] Default: MAX((side[0]=='L'?n:m),1)

scipy.linalg.lapack.zunmrz

`scipy.linalg.lapack.zunmrz` (*a*, *tau*, *c*[, *side*, *trans*, *lwork*, *overwrite_c*]) = <fortran object>
 Wrapper for `zunmrz`.

Parameters

a [input rank-2 array('D') with bounds (k,nt)]
tau [input rank-1 array('D') with bounds (k)]
c [input rank-2 array('D') with bounds (m,n)]

Returns

cq [rank-2 array('D') with bounds (m,n) and c storage]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'
overwrite_c [input int, optional] Default: 0
lwork [input int, optional] Default: MAX((side[0]=='L'?n:m),1)

scipy.linalg.lapack.cunmrz_lwork

`scipy.linalg.lapack.cunmrz_lwork` (*m*, *n*[, *side*, *trans*]) = <fortran object>
 Wrapper for `cunmrz_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [complex]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'

scipy.linalg.lapack.zunmrz_lwork

`scipy.linalg.lapack.zunmrz_lwork(m, n[, side, trans]) = <fortran object>`
 Wrapper for `zunmrz_lwork`.

Parameters

m [input int]
n [input int]

Returns

work [complex]
info [int]

Other Parameters

side [input string(len=1), optional] Default: 'L'
trans [input string(len=1), optional] Default: 'N'

scipy.linalg.lapack.ilaver

`scipy.linalg.lapack.ilaver = <fortran object>`
 Wrapper for `ilaver`.

Returns

major [int]
minor [int]
patch [int]

6.13 BLAS Functions for Cython

Usable from Cython via:

```
cimport scipy.linalg.cython_blas
```

These wrappers do not check for alignment of arrays. Alignment should be checked before these wrappers are used.

Raw function pointers (Fortran-style pointer arguments):

- `caxpy`
- `ccopy`
- `cdotc`
- `cdotu`
- `cgbmv`

- cgemm
- cgemv
- cgerc
- cgeru
- chbmv
- chemm
- chemv
- cher
- cher2
- cher2k
- cherk
- chpmv
- chpr
- chpr2
- crotg
- cscal
- csrot
- csscal
- cswap
- csymm
- csyr2k
- csyrk
- ctbmv
- ctbsv
- ctpmv
- ctpsv
- ctrmm
- ctrmv
- ctrsm
- ctrsv
- dasum
- daxpy
- dcabs1
- dcopy
- ddot
- dgbmv

- dgemm
- dgemv
- dger
- dnrm2
- drot
- drotg
- drotm
- drotmg
- dsbmv
- dscal
- dsdot
- dspmv
- dspr
- dspr2
- dswap
- dsymm
- dsymv
- dsyr
- dsyr2
- dsyr2k
- dsyrk
- dtbmv
- dtbsv
- dtpmv
- dtpsv
- dtrmm
- dtrmv
- dtrsm
- dtrsv
- dzasum
- dznrm2
- icamax
- idamax
- isamax
- izamax
- lsame

- sasum
- saxpy
- scasum
- scnrm2
- scopy
- sdot
- sdsdot
- sgbmv
- sgemm
- sgemv
- sger
- snrm2
- srot
- srotg
- srotm
- srotmg
- ssbmv
- sscal
- sspmv
- sspr
- sspr2
- sswap
- ssymm
- ssymv
- ssyr
- ssyr2
- ssyr2k
- ssyrk
- stbmv
- stbsv
- stpmv
- stpsv
- strmm
- strmv
- strsm
- strsv

- zaxpy
- zcopy
- zdotc
- zdotu
- zdrot
- zdscal
- zgbmv
- zgemm
- zgemv
- zgerc
- zgeru
- zhbmv
- zhemm
- zhemv
- zher
- zher2
- zher2k
- zherk
- zhpmv
- zhpr
- zhpr2
- zrotg
- zscal
- zswap
- zsymm
- zsyr2k
- zsyrk
- ztbmv
- ztbsv
- ztpmv
- ztpsv
- ztrmm
- ztrmv
- ztrsm
- ztrsv

6.14 LAPACK functions for Cython

Usable from Cython via:

```
cimport scipy.linalg.cython_lapack
```

This module provides Cython-level wrappers for all primary routines included in LAPACK 3.4.0 except for `zcgesev` since its interface is not consistent from LAPACK 3.4.0 to 3.6.0. It also provides some of the fixed-api auxiliary routines.

These wrappers do not check for alignment of arrays. Alignment should be checked before these wrappers are used.

Raw function pointers (Fortran-style pointer arguments):

- `cbbcscd`
- `cbdsqr`
- `cgbbrd`
- `gbcon`
- `cgbequ`
- `cgbequb`
- `cgbrfs`
- `cgbsv`
- `cgbsvx`
- `cgbt2`
- `cgbtrf`
- `cgbtrs`
- `cgebak`
- `cgebal`
- `cgebd2`
- `cgebrd`
- `cgecon`
- `cgeequ`
- `cgeequb`
- `cgees`
- `cgeesx`
- `cgeev`
- `cgeevx`
- `cgehd2`
- `cgehrd`
- `cgelq2`
- `cgelqf`
- `cgels`

- `cgelsd`
- `cgelss`
- `cgelsy`
- `cgemqrt`
- `cgeql2`
- `cgeqlf`
- `cgeqp3`
- `cgeqr2`
- `cgeqr2p`
- `cgeqrf`
- `cgeqrfp`
- `cgeqrt`
- `cgeqrt2`
- `cgeqrt3`
- `cgerfs`
- `cgerq2`
- `cgerqf`
- `cgesc2`
- `cgesdd`
- `cgesv`
- `cgesvd`
- `cgesvx`
- `cgetc2`
- `cgetf2`
- `cgetrf`
- `cgetri`
- `cgetrs`
- `cggbak`
- `cggbal`
- `cgges`
- `cggesx`
- `cggev`
- `cggevx`
- `cgglm`
- `cgghrd`
- `cgglse`

- `eggqrf`
- `cggrqf`
- `cgicon`
- `cgtrfs`
- `cgtsv`
- `cgtsvx`
- `cgtrf`
- `cgtrfs`
- `cgts2`
- `chbev`
- `chbevd`
- `chbevz`
- `chbgst`
- `chbgv`
- `chbgvd`
- `chbgvx`
- `chbtrd`
- `checon`
- `cheequb`
- `cheev`
- `cheevd`
- `cheevr`
- `cheevz`
- `chegs2`
- `chegst`
- `chegv`
- `chegvd`
- `chegvx`
- `cherfs`
- `chesv`
- `chesvx`
- `cheswapr`
- `chetd2`
- `chetf2`
- `chetrd`
- `chetrf`

- chetri
- chetri2
- chetri2x
- chetrs
- chetrs2
- chfirk
- chgeqz
- chla_transtype
- chpcon
- chpev
- chpevd
- chpevx
- chpgst
- chpgv
- chpgvd
- chpgvx
- chprfs
- chpsv
- chpsvx
- chptrd
- chptrf
- chptri
- chptrs
- chsein
- chseqr
- clabrd
- clacgv
- clacn2
- clacon
- clacp2
- clacpy
- clacrm
- clact
- cladiv
- claed0
- claed7

- `claed8`
- `claein`
- `claesy`
- `claev2`
- `clag2z`
- `clags2`
- `clagtm`
- `clahef`
- `clahqr`
- `clahr2`
- `claic1`
- `clals0`
- `clalsa`
- `clalsd`
- `clangb`
- `clangc`
- `clangt`
- `clanhb`
- `clanhe`
- `clanhf`
- `clanhp`
- `clanhs`
- `clanht`
- `clansb`
- `clansp`
- `clansy`
- `clantb`
- `clantp`
- `clantr`
- `clapll`
- `clapmr`
- `clapmt`
- `claqgb`
- `claqge`
- `claqhb`
- `claqhe`

- `claqhp`
- `claqp2`
- `claqps`
- `claqr0`
- `claqr1`
- `claqr2`
- `claqr3`
- `claqr4`
- `claqr5`
- `claqsb`
- `claqsp`
- `claqsy`
- `clar1v`
- `clar2v`
- `clarcn`
- `clarf`
- `clarfb`
- `clarfg`
- `clarfgp`
- `clarft`
- `clarfx`
- `clargv`
- `clarnv`
- `clarrv`
- `clartg`
- `clartv`
- `clarz`
- `clarzb`
- `clarzt`
- `clascl`
- `claset`
- `clasr`
- `classq`
- `claswp`
- `clasyf`
- `clatbs`

- clatdf
- clatps
- clatrd
- clatrs
- clatz
- clauu2
- clauum
- cpbcon
- cpbequ
- cpbrfs
- cpbstf
- cpbsv
- cpbsvx
- cpbtf2
- cpbtrf
- cpbtrs
- cpftrf
- cpftri
- cpftrs
- cpocon
- cpoequ
- cpoequb
- cporfs
- cposv
- cposvx
- cpotf2
- cpotrf
- cpotri
- cpotrs
- cppcon
- cppequ
- cprfs
- cppsv
- cppsvx
- cpptrf
- cpptri

- `cpptrs`
- `cpstf2`
- `cpstrf`
- `cptcon`
- `cpteqr`
- `cptrfs`
- `cptsv`
- `cptsvx`
- `cptrfs`
- `cptrfs`
- `cpts2`
- `crot`
- `cspcon`
- `cspmv`
- `cspr`
- `csprfs`
- `cspsv`
- `cspsvx`
- `csprtf`
- `csptri`
- `csptrs`
- `csrsl`
- `cstedc`
- `cstegr`
- `cstein`
- `cstemr`
- `csteqr`
- `csycon`
- `csyconv`
- `csyequb`
- `csymv`
- `csyr`
- `csyrfs`
- `csysv`
- `csysvx`
- `csyswapr`

- csytf2
- csytrf
- csytri
- csytri2
- csytri2x
- csytrs
- csytrs2
- ctbcon
- ctbrfs
- ctbtrs
- ctfsm
- cfttri
- cfttp
- cfttr
- ctgevc
- ctgex2
- ctgexc
- ctgsen
- ctgsja
- ctgsna
- ctgsy2
- ctgsyl
- ctpcon
- ctpmqrt
- ctpqrt
- ctpqrt2
- ctprfb
- ctprfs
- ctptri
- ctptrs
- ctpddf
- ctpdtr
- ctrcon
- ctrevc
- ctrex
- ctrfs

- `ctrsen`
- `ctrсна`
- `ctrsyl`
- `ctrti2`
- `ctrtri`
- `ctrtrs`
- `ctrttf`
- `ctrttp`
- `ctzrzf`
- `cunbdb`
- `cuncsd`
- `cung2l`
- `cung2r`
- `cungbr`
- `cunghr`
- `cungl2`
- `cunglq`
- `cungql`
- `cungqr`
- `cungr2`
- `cungrq`
- `cungrt`
- `cunm2l`
- `cunm2r`
- `cunmbr`
- `cunmhr`
- `cunml2`
- `cunmlq`
- `cunmql`
- `cunmqr`
- `cunmr2`
- `cunmr3`
- `cunmrq`
- `cunmrz`
- `cunmtr`
- `cupgtr`

- cupmtr
- dbbcsd
- dbdsdc
- dbdsqr
- ddisna
- dgbbbrd
- dgbccon
- dgbequ
- dgbequb
- dgbrfs
- dgbsv
- dgbsvx
- dgbtf2
- dgbrtf
- dgbrtrs
- dgebak
- dgebal
- dgebd2
- dgebrd
- dgecon
- dgeequ
- dgeequb
- dgees
- dgeesx
- dgeev
- dgeevx
- dgehd2
- dgehrd
- dgejsv
- dgelq2
- dgelqf
- dgels
- dgelsd
- dgelss
- dgelsy
- dgemqrt

- `dgeql2`
- `dgeqlf`
- `dgeqp3`
- `dgeqr2`
- `dgeqr2p`
- `dgeqrf`
- `dgeqrfp`
- `dgeqrt`
- `dgeqrt2`
- `dgeqrt3`
- `dgerfs`
- `dgerq2`
- `dgerqf`
- `dgesc2`
- `dgesdd`
- `dgesv`
- `dgesvd`
- `dgesvj`
- `dgesvx`
- `dgetc2`
- `dgetf2`
- `dgetrf`
- `dgetri`
- `dgetrs`
- `dggbak`
- `dggbal`
- `dgges`
- `dggesx`
- `dggev`
- `dggevx`
- `dggglm`
- `dgghrd`
- `dggls`
- `dggqrf`
- `dggrqf`
- `dgsvj0`

- dgsvj1
- dgtcon
- dgtrfs
- dgtsv
- dgtsvx
- dgtrf
- dgtrfs
- dgts2
- dhgeqz
- dhsein
- dhseqr
- disnan
- dlabad
- dlabrd
- dlacn2
- dlacon
- dlacpy
- dladiv
- dlae2
- dlaebz
- dlaed0
- dlaed1
- dlaed2
- dlaed3
- dlaed4
- dlaed5
- dlaed6
- dlaed7
- dlaed8
- dlaed9
- dlaeda
- dlaein
- dlaev2
- dlaexc
- dlag2
- dlag2s

- dlags2
- dlagtf
- dlagtm
- dlagts
- dlagv2
- dlahqr
- dlahr2
- dlaic1
- dlaln2
- dlals0
- dlalsa
- dlalsd
- dlamch
- dlamrg
- dlaneg
- dlangb
- dlange
- dlangt
- dlanhs
- dlansb
- dlansf
- dlansp
- dlanst
- dlansy
- dlantb
- dlantp
- dlantr
- dlanv2
- dlapll
- dlapmr
- dlapmt
- dlapy2
- dlapy3
- dlaqgb
- dlaqge
- dlaqp2

- dlaqps
- dlaqr0
- dlaqr1
- dlaqr2
- dlaqr3
- dlaqr4
- dlaqr5
- dlaqsb
- dlaqsp
- dlaqsy
- dlaqtr
- dlar1v
- dlar2v
- dlarf
- dlarfb
- dlarfg
- dlarfgp
- dlarft
- dlarfx
- dlargv
- dlarnv
- dlarra
- dlarrb
- dlarrc
- dlarrd
- dlarre
- dlarrf
- dlarrj
- dlarrk
- dlarrl
- dlarrv
- dlartg
- dlartgp
- dlartgs
- dlartv
- dlaruv

- `dlarz`
- `dlarzb`
- `dlarzt`
- `dlas2`
- `dlascl`
- `dlasd0`
- `dlasd1`
- `dlasd2`
- `dlasd3`
- `dlasd4`
- `dlasd5`
- `dlasd6`
- `dlasd7`
- `dlasd8`
- `dlasda`
- `dlasdq`
- `dlasdt`
- `dlaset`
- `dlasq1`
- `dlasq2`
- `dlasq3`
- `dlasq4`
- `dlasq6`
- `dlasr`
- `dlasrt`
- `dlasq`
- `dlasv2`
- `dlaswp`
- `dlasy2`
- `dlasyf`
- `dlat2s`
- `dlatbs`
- `dlatdf`
- `dlatps`
- `dlatrd`
- `dlatrs`

- dlatrz
- dlauu2
- dlauum
- dopgtr
- dopmtr
- dorbdb
- dorcsd
- dorg2l
- dorg2r
- dorgbr
- dorghr
- dorgl2
- dorglq
- dorgql
- dorgqr
- dorgr2
- dorgrq
- dorgrt
- dorm2l
- dorm2r
- dormbr
- dormhr
- dorml2
- dormlq
- dormql
- dormqr
- dormr2
- dormr3
- dormrq
- dormrz
- dormtr
- dpbcon
- dpbequ
- dpbrfs
- dpbstf
- dpbsv

- `dpbsvx`
- `dpbtf2`
- `dpbtrf`
- `dpbtrs`
- `dpftrf`
- `dpftri`
- `dpftrs`
- `dpocon`
- `dpoequ`
- `dpoequb`
- `dporfs`
- `dposv`
- `dposvx`
- `dpotf2`
- `dpotrf`
- `dpotri`
- `dpotrs`
- `dppcon`
- `dppequ`
- `dpprfs`
- `dppsv`
- `dppsvx`
- `dpptrf`
- `dpptri`
- `dpptrs`
- `dpstf2`
- `dpstrf`
- `dptcon`
- `dpteqr`
- `dptrfs`
- `dptsv`
- `dptsvx`
- `dptrfs`
- `dpttrs`
- `dptts2`
- `drscl`

- dsbev
- dsbevd
- dsbevx
- dsbgst
- dsbgv
- dsbgvd
- dsbgvx
- dsbtrd
- dsfrk
- dsgesv
- dspcon
- dspev
- dspevd
- dspevx
- dspgst
- dspgv
- dspgvd
- dspgvx
- dsposv
- dsprfs
- dspsv
- dspsvx
- dsptrd
- dsptrf
- dsptri
- dsptrs
- dstebz
- dstedc
- dstegr
- dstein
- dstemr
- dsteqr
- dsterf
- dstev
- dstevd
- dstevr

- `dstevx`
- `dsycon`
- `dsyconv`
- `dsyequb`
- `dsyev`
- `dsyevd`
- `dsyevr`
- `dsyevx`
- `dsygs2`
- `dsygst`
- `dsygv`
- `dsygvd`
- `dsygvx`
- `dsyrfs`
- `dsysv`
- `dsysvx`
- `dsyswapr`
- `dsytd2`
- `dsytf2`
- `dsytrd`
- `dsytrf`
- `dsytri`
- `dsytri2`
- `dsytri2x`
- `dsytrs`
- `dsytrs2`
- `dtbcon`
- `dtbrfs`
- `dtbtrs`
- `dtfsm`
- `dtftri`
- `dtfttp`
- `dtfttr`
- `dtgevc`
- `dtgex2`
- `dtgexc`

- dtgsen
- dtgsja
- dtgsna
- dtgsy2
- dtgsyl
- dtpcon
- dtpmqrt
- dtpqrt
- dtpqrt2
- dtprfb
- dtprfs
- dtptri
- dtprts
- dtpttf
- dtptrr
- dtrcon
- dtrevc
- dtrexc
- dtrrfs
- dtrsen
- dtrsna
- dtrsyl
- dtrti2
- dtrtri
- dtrtrs
- dtrttf
- dtrttp
- dtzrzf
- dzsum1
- icmax1
- ieeeck
- ilaclc
- ilaclr
- iladiag
- iladlc
- iladlr

- ilaprec
- ilasc
- ilaslr
- ilatrans
- ilauplo
- ilaver
- ilazlc
- ilazlr
- izmax1
- sbbcscd
- sbdsdc
- sbdsqr
- scsum1
- sdisna
- sgbbcd
- sgbcon
- sgbequ
- sgbequb
- sgbrfs
- sgbsv
- sgbsvx
- sgbt2
- sgbrf
- sgbrs
- sgebak
- sgebal
- sgebd2
- sgebrd
- sgecon
- sgeequ
- sgeequb
- sgees
- sgeesx
- sgeev
- sgeevx
- sgehd2

- sgehrd
- sgejsv
- sgelq2
- sgelqf
- sgels
- sgelsd
- sgelss
- sgelsy
- sgemqrt
- sgeql2
- sgeqlf
- sgeqp3
- sgeqr2
- sgeqr2p
- sgeqrf
- sgeqrfp
- sgeqrt
- sgeqrt2
- sgeqrt3
- sgerfs
- sgerq2
- sgerqf
- sgesc2
- sgesdd
- sgesv
- sgesvd
- sgesvj
- sgesvx
- sgetc2
- sgetf2
- sgetrf
- sgetri
- sgetrs
- sgbak
- sgbal
- sgges

- `sggesx`
- `sggev`
- `sggevx`
- `sgglm`
- `sgghrd`
- `sgglse`
- `sggqrf`
- `sggrqf`
- `sgsvj0`
- `sgsvj1`
- `sgtcon`
- `sgtrfs`
- `sgtsv`
- `sgtsvx`
- `sgttrf`
- `sgttrs`
- `sgtts2`
- `shgeqz`
- `shsein`
- `shseqr`
- `slabad`
- `slabrd`
- `slacn2`
- `slacon`
- `slacpy`
- `sladiv`
- `slae2`
- `slaebz`
- `slaed0`
- `slaed1`
- `slaed2`
- `slaed3`
- `slaed4`
- `slaed5`
- `slaed6`
- `slaed7`

- slaed8
- slaed9
- slaeda
- slaein
- slaev2
- slaexc
- slag2
- slag2d
- slags2
- slagtf
- slagtm
- slagts
- slagv2
- slahqr
- slahr2
- slaic1
- slaln2
- slals0
- slalsa
- slalsd
- slamch
- slamrg
- slangb
- slange
- slangt
- slanhs
- slansb
- slansf
- slansp
- slanst
- slansy
- slantb
- slantp
- slantr
- slanv2
- slapll

- `slapmr`
- `slapmt`
- `slapy2`
- `slapy3`
- `slaqgb`
- `slaqge`
- `slaqp2`
- `slaqps`
- `slaqr0`
- `slaqr1`
- `slaqr2`
- `slaqr3`
- `slaqr4`
- `slaqr5`
- `slaqsb`
- `slaqsp`
- `slaqsy`
- `slaqtr`
- `slar1v`
- `slar2v`
- `slarf`
- `slarfb`
- `slarfg`
- `slarfgp`
- `slarft`
- `slarfx`
- `slargv`
- `slarnv`
- `slarra`
- `slarrb`
- `slarrc`
- `slarrd`
- `slarre`
- `slarrf`
- `slarrj`
- `slarrk`

- slarr
- slarrv
- slartg
- slartgp
- slartgs
- slartv
- slaruv
- slarz
- slarzb
- slarzt
- slas2
- slascl
- slasd0
- slasd1
- slasd2
- slasd3
- slasd4
- slasd5
- slasd6
- slasd7
- slasd8
- slasda
- slasdq
- slasdt
- slaset
- slasq1
- slasq2
- slasq3
- slasq4
- slasq6
- slasr
- slasrt
- slasq
- slasv2
- slaswp
- slasy2

- slasyf
- slatbs
- slatdf
- slatps
- slatrd
- slatrs
- slatz
- slauu2
- slauum
- sopgtr
- sopmtr
- sorbdb
- sorcsd
- sorg2l
- sorg2r
- sorgbr
- sorgbr
- sorgl2
- sorglq
- sorgql
- sorgqr
- sorg2
- sorgqr
- sorgtr
- sorm2l
- sorm2r
- sormbr
- sormhr
- sorml2
- sormlq
- sormql
- sormqr
- sormr2
- sormr3
- sormrq
- sormrz

- sormtr
- spbcon
- spbequ
- spbrfs
- spbstf
- spbsv
- spbsvx
- spbtf2
- spbtrf
- spbtrs
- spftrf
- spftri
- spftrs
- spocon
- spoequ
- spoequb
- sporfs
- sposv
- sposvx
- spotf2
- spotrf
- spotri
- spotrs
- sppcon
- sppequ
- spprfs
- sppsv
- sppsvx
- spptrf
- spptri
- spptrs
- spstf2
- spstrf
- sptcon
- spteqr
- spttrfs

- `sptsv`
- `sptsvx`
- `spttrf`
- `spttrs`
- `sptts2`
- `srscl`
- `ssbev`
- `ssbevd`
- `ssbevx`
- `ssbgst`
- `ssbgv`
- `ssbgvd`
- `ssbgvx`
- `ssbtrd`
- `ssfrk`
- `sspcon`
- `sspev`
- `sspevd`
- `sspevx`
- `sspgst`
- `sspgv`
- `sspgvd`
- `sspgvx`
- `ssprfs`
- `sspsv`
- `sspsvx`
- `ssptrd`
- `ssptrf`
- `ssptri`
- `ssptrs`
- `sstebz`
- `sstedc`
- `sstegr`
- `sstein`
- `sstemr`
- `ssteqr`

- ssterf
- sstev
- sstevd
- sstevr
- sstevx
- ssycon
- ssyconv
- ssyequb
- ssyev
- ssyevd
- ssyevr
- ssyevx
- ssygs2
- ssygst
- ssygv
- ssygvd
- ssygvx
- ssyrfs
- ssysv
- ssysvx
- ssyswapr
- ssytd2
- ssytf2
- ssytrd
- ssytrf
- ssytri
- ssytri2
- ssytri2x
- ssytrs
- ssytrs2
- stbcon
- stbrfs
- stbtrs
- stfsm
- stftri
- stfttp

- stfttr
- stgevc
- stgex2
- stgexc
- stgsen
- stgsja
- stgsna
- stgsy2
- stgsyl
- stpcon
- stpmqrt
- stpqrt
- stpqrt2
- stprfb
- stprfs
- stptri
- stptrs
- stpttf
- stpttr
- strcon
- strevc
- strexc
- strrfs
- strsen
- strsna
- strsyl
- strti2
- strtri
- strtrs
- strttf
- strttp
- stzrzf
- xerbla_array
- zbbcsd
- zbdsqr
- zcgesv

- zcposv
- zdrscl
- zgbbbrd
- zgbcon
- zgbequ
- zgbequb
- zgbrfs
- zgbsv
- zgbsvx
- zgbtf2
- zgbtrf
- zgbtrs
- zgebak
- zgebal
- zgebd2
- zgebrd
- zgecon
- zgeequ
- zgeequb
- zgees
- zgeesx
- zgeev
- zgeevx
- zgehd2
- zgehrd
- zgelq2
- zgelqf
- zgels
- zgelsd
- zgelss
- zgelsy
- zgemqrt
- zgeql2
- zgeqlf
- zgeqp3
- zgeqr2

- `zgeqr2p`
- `zgeqrf`
- `zgeqrfp`
- `zgeqrt`
- `zgeqrt2`
- `zgeqrt3`
- `zgerfs`
- `zgerq2`
- `zgerqf`
- `zgesc2`
- `zgesdd`
- `zgesv`
- `zgesvd`
- `zgesvx`
- `zgetc2`
- `zgetf2`
- `zgetrf`
- `zgetri`
- `zgetrs`
- `zgbak`
- `zgbal`
- `zgges`
- `zggesx`
- `zggev`
- `zggevz`
- `zggglm`
- `zgghrd`
- `zggls`
- `zggqrf`
- `zggqrqf`
- `zgtcon`
- `zgttrfs`
- `zgtsv`
- `zgtsvx`
- `zgttrf`
- `zgttrs`

- zgtts2
- zhbev
- zhbevd
- zhbevz
- zhbgs
- zhbgsz
- zhbgsd
- zhbgsz
- zhbtrd
- zhecon
- zheequb
- zheev
- zheevd
- zheevr
- zheevz
- zhegs2
- zhegst
- zhegv
- zhegvd
- zhegvz
- zherfs
- zhesv
- zhesvz
- zheswapr
- zhetd2
- zhetf2
- zhetrd
- zhetrf
- zhetri
- zhetri2
- zhetri2x
- zhetrs
- zhetrs2
- zhfrk
- zhgeqz
- zhpcon

- zhpev
- zhpevd
- zhpevx
- zhpgst
- zhpgv
- zhpgvd
- zhpgvx
- zhprfs
- zhpsv
- zhpsvx
- zhptrd
- zhptrf
- zhptri
- zhptrs
- zhsein
- zhseqr
- zlabrd
- zlacgv
- zlacn2
- zlacon
- zlap2
- zlapy
- zlacrm
- zlact
- zladiv
- zlaed0
- zlaed7
- zlaed8
- zlaein
- zlaesy
- zlaev2
- zlag2c
- zlags2
- zlagtm
- zlahef
- zlahqr

- zlahr2
- zlaic1
- zlals0
- zlalsa
- zlalsd
- zlangb
- zlange
- zlangt
- zlanhb
- zlanhe
- zlanhf
- zlanhp
- zlanhs
- zlanht
- zlansb
- zlansp
- zlansy
- zlantb
- zlantp
- zlantr
- zlapll
- zlapmr
- zlapmt
- zlaqgb
- zlaqge
- zlaqhb
- zlaqhe
- zlaqhp
- zlaqp2
- zlaqps
- zlaqr0
- zlaqr1
- zlaqr2
- zlaqr3
- zlaqr4
- zlaqr5

- zlaqsb
- zlaqsp
- zlaqsy
- zlar1v
- zlar2v
- zlarcml
- zlarf
- zlarfb
- zlarfg
- zlarfgp
- zlarft
- zlarfx
- zlargv
- zlarnv
- zlarrv
- zlarg
- zlargv
- zlarz
- zlarzb
- zlarzt
- zlascl
- zlaset
- zlasr
- zlassq
- zlaswp
- zlasyf
- zlat2c
- zlatbs
- zlatdf
- zlatps
- zlatrd
- zlatrs
- zlatrz
- zlauu2
- zlauum
- zpbcon

- `zpbequ`
- `zpbrfs`
- `zpbstf`
- `zpbsv`
- `zpbsvx`
- `zpbtf2`
- `zpbtrf`
- `zpbtrs`
- `zpftrf`
- `zpftri`
- `zpftrs`
- `zpocon`
- `zpoequ`
- `zpoequb`
- `zporfs`
- `zposv`
- `zposvx`
- `zpotf2`
- `zpotrf`
- `zpotri`
- `zpotrs`
- `zppcon`
- `zppequ`
- `zpprfs`
- `zppsv`
- `zppsvx`
- `zpptrf`
- `zpptri`
- `zpptrs`
- `zpstf2`
- `zpstrf`
- `zptcon`
- `zpteqr`
- `zptrfs`
- `zptsv`
- `zptsvx`

- `zpttrf`
- `zpttrs`
- `zpts2`
- `zrot`
- `zspcon`
- `zspmv`
- `zspr`
- `zsprfs`
- `zpsv`
- `zpsvx`
- `zsptf`
- `zsptri`
- `zsptrs`
- `zstedc`
- `zstegr`
- `zstein`
- `zstemr`
- `zsteqr`
- `zsycon`
- `zsyconv`
- `zsyequb`
- `zsymv`
- `zsyr`
- `zsyrf`
- `zsysv`
- `zsysvx`
- `zsyswapr`
- `zsytf2`
- `zsytrf`
- `zsytri`
- `zsytri2`
- `zsytri2x`
- `zsytrs`
- `zsytrs2`
- `ztbcon`
- `ztbrfs`

- zbtrs
- ztfsm
- ztftri
- zfttp
- zfttr
- ztgevc
- ztgex2
- ztgexc
- ztgsen
- ztgsja
- ztgsna
- ztgsy2
- ztgsyl
- ztpcon
- ztpmqrt
- ztpqrt
- ztpqrt2
- ztprfb
- ztprfs
- ztptri
- ztptrs
- zpttf
- zpttr
- ztrcon
- ztrevc
- ztrexc
- ztrfs
- ztrsen
- ztrsna
- ztrsyl
- zrti2
- zrtri
- zrtrs
- zrtrf
- zrtrtp
- ztrzf

- zunbdb
- zuncsd
- zung2l
- zung2r
- zungbr
- zunghr
- zungl2
- zunglq
- zungql
- zungqr
- zungr2
- zungrq
- zungtr
- zunm2l
- zunm2r
- zunmbr
- zunmhr
- zunml2
- zunmlq
- zunmql
- zunmqr
- zunmr2
- zunmr3
- zunmrq
- zunmrz
- zunmtr
- zupgtr
- zupmtr

6.15 Interpolative matrix decomposition (`scipy.linalg.interpolative`)

New in version 0.13.

An interpolative decomposition (ID) of a matrix $A \in \mathbb{C}^{m \times n}$ of rank $k \leq \min\{m, n\}$ is a factorization

$$A\Pi = \begin{bmatrix} A\Pi_1 & A\Pi_2 \end{bmatrix} = A\Pi_1 \begin{bmatrix} I & T \end{bmatrix},$$

where $\Pi = [\Pi_1, \Pi_2]$ is a permutation matrix with $\Pi_1 \in \{0, 1\}^{n \times k}$, i.e., $A\Pi_2 = A\Pi_1 T$. This can equivalently be written as $A = BP$, where $B = A\Pi_1$ and $P = [I, T]\Pi^T$ are the *skeleton* and *interpolation matrices*, respectively.

If A does not have exact rank k , then there exists an approximation in the form of an ID such that $A = BP + E$, where $\|E\| \sim \sigma_{k+1}$ is on the order of the $(k + 1)$ -th largest singular value of A . Note that σ_{k+1} is the best possible error for a rank- k approximation and, in fact, is achieved by the singular value decomposition (SVD) $A \approx USV^*$, where $U \in \mathbb{C}^{m \times k}$ and $V \in \mathbb{C}^{n \times k}$ have orthonormal columns and $S = \text{diag}(\sigma_i) \in \mathbb{C}^{k \times k}$ is diagonal with nonnegative entries. The principal advantages of using an ID over an SVD are that:

- it is cheaper to construct;
- it preserves the structure of A ; and
- it is more efficient to compute with in light of the identity submatrix of P .

6.15.1 Routines

Main functionality:

<code>interp_decomp(A, eps_or_k[, rand])</code>	Compute ID of a matrix.
<code>reconstruct_matrix_from_id(B, idx, proj)</code>	Reconstruct matrix from its ID.
<code>reconstruct_interp_matrix(idx, proj)</code>	Reconstruct interpolation matrix from ID.
<code>reconstruct_skel_matrix(A, k, idx)</code>	Reconstruct skeleton matrix from ID.
<code>id_to_svd(B, idx, proj)</code>	Convert ID to SVD.
<code>svd(A, eps_or_k[, rand])</code>	Compute SVD of a matrix via an ID.
<code>estimate_spectral_norm(A[, its])</code>	Estimate spectral norm of a matrix by the randomized power method.
<code>estimate_spectral_norm_diff(A, B[, its])</code>	Estimate spectral norm of the difference of two matrices by the randomized power method.
<code>estimate_rank(A, eps)</code>	Estimate matrix rank to a specified relative precision using randomized methods.

scipy.linalg.interpolative.interp_decomp

`scipy.linalg.interpolative.interp_decomp(A, eps_or_k, rand=True)`

Compute ID of a matrix.

An ID of a matrix A is a factorization defined by a rank k , a column index array idx , and interpolation coefficients $proj$ such that:

```
numpy.dot(A[:, idx[:k]], proj) = A[:, idx[k:]]
```

The original matrix can then be reconstructed as:

```
numpy.hstack([A[:, idx[:k]],
              numpy.dot(A[:, idx[:k]], proj)]
             )[:, numpy.argsort(idx)]
```

or via the routine `reconstruct_matrix_from_id`. This can equivalently be written as:

```
numpy.dot(A[:, idx[:k]],
          numpy.hstack([numpy.eye(k), proj])
          )[:, np.argsort(idx)]
```

in terms of the skeleton and interpolation matrices:

```
B = A[:,idx[:k]]
```

and:

```
P = numpy.hstack([numpy.eye(k), proj])[:,np.argsort(idx)]
```

respectively. See also [reconstruct_interp_matrix](#) and [reconstruct_skel_matrix](#).

The ID can be computed to any relative precision or rank (depending on the value of *eps_or_k*). If a precision is specified (*eps_or_k* < 1), then this function has the output signature:

```
k, idx, proj = interp_decomp(A, eps_or_k)
```

Otherwise, if a rank is specified (*eps_or_k* >= 1), then the output signature is:

```
idx, proj = interp_decomp(A, eps_or_k)
```

Parameters

- A** [[numpy.ndarray](#) or [scipy.sparse.linalg.LinearOperator](#) with *rmatvec*] Matrix to be factored
- eps_or_k** [float or int] Relative error (if *eps_or_k* < 1) or rank (if *eps_or_k* >= 1) of approximation.
- rand** [bool, optional] Whether to use random sampling if *A* is of type [numpy.ndarray](#) (randomized algorithms are always used if *A* is of type [scipy.sparse.linalg.LinearOperator](#)).

Returns

- k** [int] Rank required to achieve specified relative precision if *eps_or_k* < 1.
- idx** [[numpy.ndarray](#)] Column index array.
- proj** [[numpy.ndarray](#)] Interpolation coefficients.

scipy.linalg.interpolative.reconstruct_matrix_from_id

`scipy.linalg.interpolative.reconstruct_matrix_from_id(B, idx, proj)`
 Reconstruct matrix from its ID.

A matrix *A* with skeleton matrix *B* and ID indices and coefficients *idx* and *proj*, respectively, can be reconstructed as:

```
numpy.hstack([B, numpy.dot(B, proj)])[:,numpy.argsort(idx)]
```

See also [reconstruct_interp_matrix](#) and [reconstruct_skel_matrix](#).

Parameters

- B** [[numpy.ndarray](#)] Skeleton matrix.
- idx** [[numpy.ndarray](#)] Column index array.
- proj** [[numpy.ndarray](#)] Interpolation coefficients.

Returns

- [numpy.ndarray](#)**
 Reconstructed matrix.

scipy.linalg.interpolative.reconstruct_interp_matrix

`scipy.linalg.interpolative.reconstruct_interp_matrix` (*idx*, *proj*)

Reconstruct interpolation matrix from ID.

The interpolation matrix can be reconstructed from the ID indices and coefficients *idx* and *proj*, respectively, as:

```
P = numpy.hstack([numpy.eye(proj.shape[0]), proj])[ :, numpy.argsort(idx) ]
```

The original matrix can then be reconstructed from its skeleton matrix *B* via:

```
numpy.dot(B, P)
```

See also [reconstruct_matrix_from_id](#) and [reconstruct_skel_matrix](#).

Parameters

idx [numpy.ndarray] Column index array.
proj [numpy.ndarray] Interpolation coefficients.

Returns

numpy.ndarray
 Interpolation matrix.

scipy.linalg.interpolative.reconstruct_skel_matrix

`scipy.linalg.interpolative.reconstruct_skel_matrix` (*A*, *k*, *idx*)

Reconstruct skeleton matrix from ID.

The skeleton matrix can be reconstructed from the original matrix *A* and its ID rank and indices *k* and *idx*, respectively, as:

```
B = A[:, idx[:k]]
```

The original matrix can then be reconstructed via:

```
numpy.hstack([B, numpy.dot(B, proj)])[ :, numpy.argsort(idx) ]
```

See also [reconstruct_matrix_from_id](#) and [reconstruct_interp_matrix](#).

Parameters

A [numpy.ndarray] Original matrix.
k [int] Rank of ID.
idx [numpy.ndarray] Column index array.

Returns

numpy.ndarray
 Skeleton matrix.

scipy.linalg.interpolative.id_to_svd

`scipy.linalg.interpolative.id_to_svd(B, idx, proj)`
 Convert ID to SVD.

The SVD reconstruction of a matrix with skeleton matrix B and ID indices and coefficients idx and $proj$, respectively, is:

```
U, S, V = id_to_svd(B, idx, proj)
A = numpy.dot(U, numpy.dot(numpy.diag(S), V.conj().T))
```

See also [svd](#).

Parameters

B [numpy.ndarray] Skeleton matrix.
idx [numpy.ndarray] Column index array.
proj [numpy.ndarray] Interpolation coefficients.

Returns

U [numpy.ndarray] Left singular vectors.
S [numpy.ndarray] Singular values.
V [numpy.ndarray] Right singular vectors.

scipy.linalg.interpolative.svd

`scipy.linalg.interpolative.svd(A, eps_or_k, rand=True)`
 Compute SVD of a matrix via an ID.

An SVD of a matrix A is a factorization:

```
A = numpy.dot(U, numpy.dot(numpy.diag(S), V.conj().T))
```

where U and V have orthonormal columns and S is nonnegative.

The SVD can be computed to any relative precision or rank (depending on the value of eps_or_k).

See also [interp_decomp](#) and [id_to_svd](#).

Parameters

A [numpy.ndarray or scipy.sparse.linalg.LinearOperator] Matrix to be factored, given as either a `numpy.ndarray` or a `scipy.sparse.linalg.LinearOperator` with the `matvec` and `rmatvec` methods (to apply the matrix and its adjoint).
eps_or_k [float or int] Relative error (if $eps_or_k < 1$) or rank (if $eps_or_k \geq 1$) of approximation.
rand [bool, optional] Whether to use random sampling if A is of type `numpy.ndarray` (randomized algorithms are always used if A is of type `scipy.sparse.linalg.LinearOperator`).

Returns

U [numpy.ndarray] Left singular vectors.
S [numpy.ndarray] Singular values.
V [numpy.ndarray] Right singular vectors.

scipy.linalg.interpolative.estimate_spectral_norm

`scipy.linalg.interpolative.estimate_spectral_norm(A, its=20)`

Estimate spectral norm of a matrix by the randomized power method.

Parameters

- A** [`scipy.sparse.linalg.LinearOperator`] Matrix given as a `scipy.sparse.linalg.LinearOperator` with the `matvec` and `rmatvec` methods (to apply the matrix and its adjoint).
- its** [int, optional] Number of power method iterations.

Returns

- float** Spectral norm estimate.

scipy.linalg.interpolative.estimate_spectral_norm_diff

`scipy.linalg.interpolative.estimate_spectral_norm_diff(A, B, its=20)`

Estimate spectral norm of the difference of two matrices by the randomized power method.

Parameters

- A** [`scipy.sparse.linalg.LinearOperator`] First matrix given as a `scipy.sparse.linalg.LinearOperator` with the `matvec` and `rmatvec` methods (to apply the matrix and its adjoint).
- B** [`scipy.sparse.linalg.LinearOperator`] Second matrix given as a `scipy.sparse.linalg.LinearOperator` with the `matvec` and `rmatvec` methods (to apply the matrix and its adjoint).
- its** [int, optional] Number of power method iterations.

Returns

- float** Spectral norm estimate of matrix difference.

scipy.linalg.interpolative.estimate_rank

`scipy.linalg.interpolative.estimate_rank(A, eps)`

Estimate matrix rank to a specified relative precision using randomized methods.

The matrix *A* can be given as either a `numpy.ndarray` or a `scipy.sparse.linalg.LinearOperator`, with different algorithms used for each case. If *A* is of type `numpy.ndarray`, then the output rank is typically about 8 higher than the actual numerical rank.

Parameters

- A** [`numpy.ndarray` or `scipy.sparse.linalg.LinearOperator`] Matrix whose rank is to be estimated, given as either a `numpy.ndarray` or a `scipy.sparse.linalg.LinearOperator` with the `rmatvec` method (to apply the matrix adjoint).
- eps** [float] Relative error for numerical rank definition.

Returns

- int** Estimated matrix rank.

Support functions:

<code>seed([seed])</code>	Seed the internal random number generator used in this ID package.
<code>rand(*shape)</code>	Generate standard uniform pseudorandom numbers via a very efficient lagged Fibonacci method.

scipy.linalg.interpolative.seed

`scipy.linalg.interpolative.seed` (*seed=None*)

Seed the internal random number generator used in this ID package.

The generator is a lagged Fibonacci method with 55-element internal state.

Parameters

seed [int, sequence, 'default', optional] If 'default', the random seed is reset to a default value. If *seed* is a sequence containing 55 floating-point numbers in range [0,1], these are used to set the internal state of the generator. If the value is an integer, the internal state is obtained from `numpy.random.RandomState` (MT19937) with the integer used as the initial seed. If *seed* is omitted (None), `numpy.random.rand` is used to initialize the generator.

scipy.linalg.interpolative.rand

`scipy.linalg.interpolative.rand` (**shape*)

Generate standard uniform pseudorandom numbers via a very efficient lagged Fibonacci method.

This routine is used for all random number generation in this package and can affect ID and SVD results.

Parameters

shape Shape of output array

6.15.2 References

This module uses the ID software package [R5a82238cdab4-1] by Martinsson, Rokhlin, Shkolnisky, and Tygert, which is a Fortran library for computing IDs using various algorithms, including the rank-revealing QR approach of [R5a82238cdab4-2] and the more recent randomized methods described in [R5a82238cdab4-3], [R5a82238cdab4-4], and [R5a82238cdab4-5]. This module exposes its functionality in a way convenient for Python users. Note that this module does not add any functionality beyond that of organizing a simpler and more consistent interface.

We advise the user to consult also the [documentation for the ID package](#).

6.15.3 Tutorial

Initializing

The first step is to import `scipy.linalg.interpolative` by issuing the command:

```
>>> import scipy.linalg.interpolative as sli
```

Now let's build a matrix. For this, we consider a Hilbert matrix, which is well know to have low rank:

```
>>> from scipy.linalg import hilbert
>>> n = 1000
>>> A = hilbert(n)
```

We can also do this explicitly via:

```
>>> import numpy as np
>>> n = 1000
>>> A = np.empty((n, n), order='F')
>>> for j in range(n):
>>>     for i in range(m):
>>>         A[i,j] = 1. / (i + j + 1)
```

Note the use of the flag `order='F'` in `numpy.empty`. This instantiates the matrix in Fortran-contiguous order and is important for avoiding data copying when passing to the backend.

We then define multiplication routines for the matrix by regarding it as a `scipy.sparse.linalg.LinearOperator`:

```
>>> from scipy.sparse.linalg import aslinearoperator
>>> L = aslinearoperator(A)
```

This automatically sets up methods describing the action of the matrix and its adjoint on a vector.

Computing an ID

We have several choices of algorithm to compute an ID. These fall largely according to two dichotomies:

1. how the matrix is represented, i.e., via its entries or via its action on a vector; and
2. whether to approximate it to a fixed relative precision or to a fixed rank.

We step through each choice in turn below.

In all cases, the ID is represented by three parameters:

1. a rank `k`;
2. an index array `idx`; and
3. interpolation coefficients `proj`.

The ID is specified by the relation `np.dot(A[:,idx[:k]], proj) == A[:,idx[k:]]`.

From matrix entries

We first consider a matrix given in terms of its entries.

To compute an ID to a fixed precision, type:

```
>>> k, idx, proj = sli.interp_decomp(A, eps)
```

where `eps < 1` is the desired precision.

To compute an ID to a fixed rank, use:

```
>>> idx, proj = sli.interp_decomp(A, k)
```

where $k \geq 1$ is the desired rank.

Both algorithms use random sampling and are usually faster than the corresponding older, deterministic algorithms, which can be accessed via the commands:

```
>>> k, idx, proj = sli.interp_decomp(A, eps, rand=False)
```

and:

```
>>> idx, proj = sli.interp_decomp(A, k, rand=False)
```

respectively.

From matrix action

Now consider a matrix given in terms of its action on a vector as a *scipy.sparse.linalg.LinearOperator*.

To compute an ID to a fixed precision, type:

```
>>> k, idx, proj = sli.interp_decomp(L, eps)
```

To compute an ID to a fixed rank, use:

```
>>> idx, proj = sli.interp_decomp(L, k)
```

These algorithms are randomized.

Reconstructing an ID

The ID routines above do not output the skeleton and interpolation matrices explicitly but instead return the relevant information in a more compact (and sometimes more useful) form. To build these matrices, write:

```
>>> B = sli.reconstruct_skel_matrix(A, k, idx)
```

for the skeleton matrix and:

```
>>> P = sli.reconstruct_interp_matrix(idx, proj)
```

for the interpolation matrix. The ID approximation can then be computed as:

```
>>> C = np.dot(B, P)
```

This can also be constructed directly using:

```
>>> C = sli.reconstruct_matrix_from_id(B, idx, proj)
```

without having to first compute P.

Alternatively, this can be done explicitly as well using:

```
>>> B = A[:,idx[:k]]
>>> P = np.hstack([np.eye(k), proj])[ :, np.argsort(idx) ]
>>> C = np.dot(B, P)
```

Computing an SVD

An ID can be converted to an SVD via the command:

```
>>> U, S, V = sli.id_to_svd(B, idx, proj)
```

The SVD approximation is then:

```
>>> C = np.dot(U, np.dot(np.diag(S), np.dot(V.conj().T)))
```

The SVD can also be computed “fresh” by combining both the ID and conversion steps into one command. Following the various ID algorithms above, there are correspondingly various SVD algorithms that one can employ.

From matrix entries

We consider first SVD algorithms for a matrix given in terms of its entries.

To compute an SVD to a fixed precision, type:

```
>>> U, S, V = sli.svd(A, eps)
```

To compute an SVD to a fixed rank, use:

```
>>> U, S, V = sli.svd(A, k)
```

Both algorithms use random sampling; for the deterministic versions, issue the keyword `rand=False` as above.

From matrix action

Now consider a matrix given in terms of its action on a vector.

To compute an SVD to a fixed precision, type:

```
>>> U, S, V = sli.svd(L, eps)
```

To compute an SVD to a fixed rank, use:

```
>>> U, S, V = sli.svd(L, k)
```

Utility routines

Several utility routines are also available.

To estimate the spectral norm of a matrix, use:

```
>>> snorm = sli.estimate_spectral_norm(A)
```

This algorithm is based on the randomized power method and thus requires only matrix-vector products. The number of iterations to take can be set using the keyword `its` (default: `its=20`). The matrix is interpreted as a `scipy.sparse.linalg.LinearOperator`, but it is also valid to supply it as a `numpy.ndarray`, in which case it is trivially converted using `scipy.sparse.linalg.aslinearoperator`.

The same algorithm can also estimate the spectral norm of the difference of two matrices `A1` and `A2` as follows:

```
>>> diff = sli.estimate_spectral_norm_diff(A1, A2)
```

This is often useful for checking the accuracy of a matrix approximation.

Some routines in `scipy.linalg.interpolative` require estimating the rank of a matrix as well. This can be done with either:

```
>>> k = sli.estimate_rank(A, eps)
```

or:

```
>>> k = sli.estimate_rank(L, eps)
```

depending on the representation. The parameter `eps` controls the definition of the numerical rank.

Finally, the random number generation required for all randomized routines can be controlled via `scipy.linalg.interpolative.seed`. To reset the seed values to their original values, use:

```
>>> sli.seed('default')
```

To specify the seed values, use:

```
>>> sli.seed(s)
```

where `s` must be an integer or array of 55 floats. If an integer, the array of floats is obtained by using `numpy.random.rand` with the given integer seed.

To simply generate some random numbers, type:

```
>>> sli.rand(n)
```

where `n` is the number of random numbers to generate.

Remarks

The above functions all automatically detect the appropriate interface and work with both real and complex data types, passing input arguments to the proper backend routine.

6.16 Miscellaneous routines (`scipy.misc`)

Various utilities that don't have another home.

<code>ascent()</code>	Get an 8-bit grayscale bit-depth, 512 x 512 derived image for easy use in demos
<code>central_diff_weights(Np[, ndiv])</code>	Return weights for an <code>Np</code> -point central derivative.
<code>derivative(func, x0[, dx, n, args, order])</code>	Find the <code>n</code> th derivative of a function at a point.
<code>face([gray])</code>	Get a 1024 x 768, color image of a raccoon face.
<code>electrocardiogram()</code>	Load an electrocardiogram as an example for a 1-D signal.

6.16.1 `scipy.misc.ascent`

`scipy.misc.ascent()`

Get an 8-bit grayscale bit-depth, 512 x 512 derived image for easy use in demos

The image is derived from `accent-to-the-top.jpg` at <http://www.public-domain-image.com/people-public-domain-images-pictures/>

Parameters

None


Returns

`ascent` [ndarray] convenient image to use for testing and demonstration

Examples

```
>>> import scipy.misc
>>> ascent = scipy.misc.ascent()
>>> ascent.shape
(512, 512)
>>> ascent.max()
255
```

```
>>> import matplotlib.pyplot as plt
>>> plt.gray()
>>> plt.imshow(ascent)
>>> plt.show()
```



6.16.2 scipy.misc.central_diff_weights

`scipy.misc.central_diff_weights` (*Np*, *ndiv=1*)

Return weights for an *Np*-point central derivative.

Assumes equally-spaced function points.

If weights are in the vector *w*, then derivative is $w[0] * f(x-h_0*dx) + \dots + w[-1] * f(x+h_0*dx)$

Parameters

Np [int] Number of points for the central derivative.
ndiv [int, optional] Number of divisions. Default is 1.

Returns

w [ndarray] Weights for an *Np*-point central derivative. Its size is *Np*.

Notes

Can be inaccurate for a large number of points.

References

[1]

Examples

We can calculate a derivative value of a function.

```
>>> from scipy.misc import central_diff_weights
>>> def f(x):
...     return 2 * x**2 + 3
>>> x = 3.0 # derivative point
>>> h = 0.1 # differential step
>>> Np = 3 # point number for central derivative
>>> weights = central_diff_weights(Np) # weights for first derivative
>>> vals = [f(x + (i - Np/2) * h) for i in range(Np)]
>>> sum(w * v for (w, v) in zip(weights, vals))/h
11.799999999999998
```

This value is close to the analytical solution: $f'(x) = 4x$, so $f'(3) = 12$

6.16.3 scipy.misc.derivative

`scipy.misc.derivative` (*func*, *x0*, *dx=1.0*, *n=1*, *args=()*, *order=3*)

Find the *n*th derivative of a function at a point.

Given a function, use a central difference formula with spacing *dx* to compute the *n*th derivative at *x0*.

Parameters

func [function] Input function.
x0 [float] The point at which the *n*th derivative is found.
dx [float, optional] Spacing.

n [int, optional] Order of the derivative. Default is 1.
args [tuple, optional] Arguments
order [int, optional] Number of points to use, must be odd.

Notes

Decreasing the step size too small can result in round-off error.

Examples

```
>>> from scipy.misc import derivative
>>> def f(x):
...     return x**3 + x**2
>>> derivative(f, 1.0, dx=1e-6)
4.9999999999217337
```

6.16.4 scipy.misc.face

`scipy.misc.face` (*gray=False*)

Get a 1024 x 768, color image of a raccoon face.

raccoon-procyon-lotor.jpg at <http://www.public-domain-image.com>

Parameters

gray [bool, optional] If True return 8-bit grey-scale image, otherwise return a color image

Returns

face [ndarray] image of a racoon face

Examples

```
>>> import scipy.misc
>>> face = scipy.misc.face()
>>> face.shape
(768, 1024, 3)
>>> face.max()
255
>>> face.dtype
dtype('uint8')
```

```
>>> import matplotlib.pyplot as plt
>>> plt.gray()
>>> plt.imshow(face)
>>> plt.show()
```



6.16.5 `scipy.misc.electrocardiogram`

`scipy.misc.electrocardiogram()`

Load an electrocardiogram as an example for a 1-D signal.

The returned signal is a 5 minute long electrocardiogram (ECG), a medical recording of the heart's electrical activity, sampled at 360 Hz.

Returns

ecg [ndarray] The electrocardiogram in millivolt (mV) sampled at 360 Hz.

Notes

The provided signal is an excerpt (19:35 to 24:35) from the [record 208](#) (lead MLII) provided by the MIT-BIH Arrhythmia Database [1] on PhysioNet [2]. The excerpt includes noise induced artifacts, typical heartbeats as well as pathological changes.

New in version 1.1.0.

References


[1], [2]

Examples

```
>>> from scipy.misc import electrocardiogram
>>> ecg = electrocardiogram()
>>> ecg
array([-0.245, -0.215, -0.185, ..., -0.405, -0.395, -0.385])
>>> ecg.shape, ecg.mean(), ecg.std()
((108000,), -0.16510875, 0.5992473991177294)
```

As stated the signal features several areas with a different morphology. E.g., the first few seconds show the electrical activity of a heart in normal sinus rhythm as seen below.

```
>>> import matplotlib.pyplot as plt
>>> fs = 360
>>> time = np.arange(ecg.size) / fs
>>> plt.plot(time, ecg)
>>> plt.xlabel("time in s")
>>> plt.ylabel("ECG in mV")
>>> plt.xlim(9, 10.2)
>>> plt.ylim(-1, 1.5)
>>> plt.show()
```





After second 16, however, the first premature ventricular contractions, also called extrasystoles, appear. These have a different morphology compared to typical heartbeats. The difference can easily be observed in the following plot.

```
>>> plt.plot(time, ecg)
>>> plt.xlabel("time in s")
>>> plt.ylabel("ECG in mV")
>>> plt.xlim(46.5, 50)
>>> plt.ylim(-2, 1.5)
>>> plt.show()
```

At several points large artifacts disturb the recording, e.g.:

```
>>> plt.plot(time, ecg)
>>> plt.xlabel("time in s")
>>> plt.ylabel("ECG in mV")
>>> plt.xlim(207, 215)
>>> plt.ylim(-2, 3.5)
>>> plt.show()
```


Finally, examining the power spectrum reveals that most of the biosignal is made up of lower frequencies. At 60 Hz the noise induced by the mains electricity can be clearly observed.



```

>>> from scipy.signal import welch
>>> f, Pxx = welch(ecg, fs=fs, nperseg=2048, scaling="spectrum")
>>> plt.semilogy(f, Pxx)
>>> plt.xlabel("Frequency in Hz")
>>> plt.ylabel("Power spectrum of the ECG in mV**2")
>>> plt.xlim(f[[0, -1]])
>>> plt.show()

```



6.17 Multidimensional image processing (`scipy.ndimage`)

This package contains various functions for multidimensional image processing.

6.17.1 Filters

<code>convolve(input, weights[, output, mode, ...])</code>	Multidimensional convolution.
<code>convolve1d(input, weights[, axis, output, ...])</code>	Calculate a 1-D convolution along the given axis.
<code>correlate(input, weights[, output, mode, ...])</code>	Multidimensional correlation.
<code>correlate1d(input, weights[, axis, output, ...])</code>	Calculate a 1-D correlation along the given axis.
<code>gaussian_filter(input, sigma[, order, ...])</code>	Multidimensional Gaussian filter.
<code>gaussian_filter1d(input, sigma[, axis, ...])</code>	1-D Gaussian filter.
<code>gaussian_gradient_magnitude(input, sigma[, ...])</code>	Multidimensional gradient magnitude using Gaussian derivatives.
<code>gaussian_laplace(input, sigma[, output, ...])</code>	Multidimensional Laplace filter using Gaussian second derivatives.
<code>generic_filter(input, function[, size, ...])</code>	Calculate a multidimensional filter using the given function.
<code>generic_filter1d(input, function, filter_size)</code>	Calculate a 1-D filter along the given axis.
<code>generic_gradient_magnitude(input, derivative)</code>	Gradient magnitude using a provided gradient function.

continues on next page

Table 107 – continued from previous page

<code>generic_laplace(input, derivative2[, ...])</code>	N-D Laplace filter using a provided second derivative function.
<code>laplace(input[, output, mode, cval])</code>	N-D Laplace filter based on approximate second derivatives.
<code>maximum_filter(input[, size, footprint, ...])</code>	Calculate a multidimensional maximum filter.
<code>maximum_filter1d(input, size[, axis, ...])</code>	Calculate a 1-D maximum filter along the given axis.
<code>median_filter(input[, size, footprint, ...])</code>	Calculate a multidimensional median filter.
<code>minimum_filter(input[, size, footprint, ...])</code>	Calculate a multidimensional minimum filter.
<code>minimum_filter1d(input, size[, axis, ...])</code>	Calculate a 1-D minimum filter along the given axis.
<code>percentile_filter(input, percentile[, size, ...])</code>	Calculate a multidimensional percentile filter.
<code>prewitt(input[, axis, output, mode, cval])</code>	Calculate a Prewitt filter.
<code>rank_filter(input, rank[, size, footprint, ...])</code>	Calculate a multidimensional rank filter.
<code>sobel(input[, axis, output, mode, cval])</code>	Calculate a Sobel filter.
<code>uniform_filter(input[, size, output, mode, ...])</code>	Multidimensional uniform filter.
<code>uniform_filter1d(input, size[, axis, ...])</code>	Calculate a 1-D uniform filter along the given axis.

scipy.ndimage.convolve

`scipy.ndimage.convolve` (*input*, *weights*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)
 Multidimensional convolution.

The array is convolved with the given kernel.

Parameters

input	[array_like] The input array.
weights	[array_like] Array of weights, same number of dimensions as input
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the input array is extended beyond its boundaries. Default is 'reflect'. Behavior for each valid value is as follows: 'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric. 'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. 'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel. 'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric. 'wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge. For consistency with the interpolation functions, the following mode names can also be used: 'grid-mirror' This is a synonym for 'reflect'. 'grid-constant' This is a synonym for 'constant'. 'grid-wrap' This is a synonym for 'wrap'.
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0

origin [int or sequence, optional] Controls the placement of the filter on the input array's pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right. By passing a sequence of origins with length equal to the number of dimensions of the input array, different shifts can be specified along each axis.

Returns

result [ndarray] The result of convolution of *input* with *weights*.

See also:

`correlate`

Correlate an image with a kernel.

Notes

Each value in result is $C_i = \sum_j I_{i+k-j} W_j$, where W is the *weights* kernel, j is the N-D spatial index over W , I is the *input* and k is the coordinate of the center of W , specified by *origin* in the input parameters.

Examples

Perhaps the simplest case to understand is `mode='constant'`, `cval=0.0`, because in this case borders (i.e., where the *weights* kernel, centered on any one value, extends beyond an edge of *input*) are treated as zeros.

```
>>> a = np.array([[1, 2, 0, 0],
...              [5, 3, 0, 4],
...              [0, 0, 0, 7],
...              [9, 3, 0, 0]])
>>> k = np.array([[1, 1, 1], [1, 1, 0], [1, 0, 0]])
>>> from scipy import ndimage
>>> ndimage.convolve(a, k, mode='constant', cval=0.0)
array([[11, 10, 7, 4],
       [10, 3, 11, 11],
       [15, 12, 14, 7],
       [12, 3, 7, 0]])
```

Setting `cval=1.0` is equivalent to padding the outer edge of *input* with 1.0's (and then extracting only the original region of the result).

```
>>> ndimage.convolve(a, k, mode='constant', cval=1.0)
array([[13, 11, 8, 7],
       [11, 3, 11, 14],
       [16, 12, 14, 10],
       [15, 6, 10, 5]])
```

With `mode='reflect'` (the default), outer values are reflected at the edge of *input* to fill in missing values.

```
>>> b = np.array([[2, 0, 0],
...              [1, 0, 0],
...              [0, 0, 0]])
>>> k = np.array([[0, 1, 0], [0, 1, 0], [0, 1, 0]])
>>> ndimage.convolve(b, k, mode='reflect')
```

(continues on next page)

(continued from previous page)

```
array([[5, 0, 0],
       [3, 0, 0],
       [1, 0, 0]])
```

This includes diagonally at the corners.

```
>>> k = np.array([[1, 0, 0], [0, 1, 0], [0, 0, 1]])
>>> ndimage.convolve(b, k)
array([[4, 2, 0],
       [3, 2, 0],
       [1, 1, 0]])
```

With `mode='nearest'`, the single nearest value in to an edge in *input* is repeated as many times as needed to match the overlapping *weights*.

```
>>> c = np.array([[2, 0, 1],
...               [1, 0, 0],
...               [0, 0, 0]])
>>> k = np.array([[0, 1, 0],
...               [0, 1, 0],
...               [0, 1, 0],
...               [0, 1, 0]])
>>> ndimage.convolve(c, k, mode='nearest')
array([[7, 0, 3],
       [5, 0, 2],
       [3, 0, 1]])
```

scipy.ndimage.convolve1d

`scipy.ndimage.convolve1d(input, weights, axis=-1, output=None, mode='reflect', cval=0.0, origin=0)`

Calculate a 1-D convolution along the given axis.

The lines of the array along the given axis are convolved with the given weights.

Parameters

input	[array_like] The input array.
weights	[ndarray] 1-D sequence of numbers.
axis	[int, optional] The axis of <i>input</i> along which to calculate. Default is -1.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the input array is extended beyond its boundaries. Default is 'reflect'. Behavior for each valid value is as follows: <ul style="list-style-type: none"> 'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric. 'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. 'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel.

‘mirror’ (*d c b | a b c d | c b a*)

The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.

‘wrap’ (*a b c d | a b c d | a b c d*)

The input is extended by wrapping around to the opposite edge.

For consistency with the interpolation functions, the following mode names can also be used:

‘grid-mirror’

This is a synonym for ‘reflect’.

‘grid-constant’

This is a synonym for ‘constant’.

‘grid-wrap’

This is a synonym for ‘wrap’.

cval [scalar, optional] Value to fill past edges of input if *mode* is ‘constant’. Default is 0.0.

origin [int, optional] Controls the placement of the filter on the input array’s pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right.

Returns

convolve1d

[ndarray] Convolved array with same shape as input

Examples

```
>>> from scipy.ndimage import convolve1d
>>> convolve1d([2, 8, 0, 4, 1, 9, 9, 0], weights=[1, 3])
array([14, 24, 4, 13, 12, 36, 27, 0])
```

scipy.ndimage.correlate

`scipy.ndimage.correlate` (*input, weights, output=None, mode='reflect', cval=0.0, origin=0*)
Multidimensional correlation.

The array is correlated with the given kernel.

Parameters

input [array_like] The input array.

weights [ndarray] array of weights, same number of dimensions as input

output [array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.

mode [{‘reflect’, ‘constant’, ‘nearest’, ‘mirror’, ‘wrap’}, optional] The *mode* parameter determines how the input array is extended beyond its boundaries. Default is ‘reflect’. Behavior for each valid value is as follows:

‘reflect’ (*d c b a | a b c d | d c b a*)

The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.

‘constant’ (*k k k k | a b c d | k k k k*)

The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter.

‘nearest’ (*a a a a | a b c d | d d d d*)

The input is extended by replicating the last pixel.

‘mirror’ (*d c b | a b c d | c b a*)

The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.

‘wrap’ (*a b c d | a b c d | a b c d*)

The input is extended by wrapping around to the opposite edge.

For consistency with the interpolation functions, the following mode names can also be used:

‘grid-mirror’

This is a synonym for ‘reflect’.

‘grid-constant’

This is a synonym for ‘constant’.

‘grid-wrap’

This is a synonym for ‘wrap’.

cval [scalar, optional] Value to fill past edges of input if *mode* is ‘constant’. Default is 0.0.

origin [int or sequence, optional] Controls the placement of the filter on the input array’s pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right. By passing a sequence of origins with length equal to the number of dimensions of the input array, different shifts can be specified along each axis.

Returns

result [ndarray] The result of correlation of *input* with *weights*.

See also:

[convolve](#)

Convolve an image with a kernel.

Examples

Correlation is the process of moving a filter mask often referred to as kernel over the image and computing the sum of products at each location.

```
>>> from scipy.ndimage import correlate
>>> input_img = np.arange(25).reshape(5,5)
>>> print(input_img)
[[ 0  1  2  3  4]
 [ 5  6  7  8  9]
 [10 11 12 13 14]
 [15 16 17 18 19]
 [20 21 22 23 24]]
```

Define a kernel (weights) for correlation. In this example, it is for sum of center and up, down, left and right next elements.

```
>>> weights = [[0, 1, 0],
...           [1, 1, 1],
...           [0, 1, 0]]
```

We can calculate a correlation result: For example, element $[2, 2]$ is $7 + 11 + 12 + 13 + 17 = 60$.

```
>>> correlate(input_img, weights)
array([[ 6, 10, 15, 20, 24],
       [26, 30, 35, 40, 44],
```

(continues on next page)

(continued from previous page)

```
[ 51,  55,  60,  65,  69],
 [ 76,  80,  85,  90,  94],
 [ 96, 100, 105, 110, 114]])
```

scipy.ndimage.correlate1d

`scipy.ndimage.correlate1d` (*input*, *weights*, *axis=-1*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)
Calculate a 1-D correlation along the given axis.

The lines of the array along the given axis are correlated with the given weights.

Parameters

input	[array_like] The input array.
weights	[array] 1-D sequence of numbers.
axis	[int, optional] The axis of <i>input</i> along which to calculate. Default is -1.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as <i>input</i> will be created.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the input array is extended beyond its boundaries. Default is 'reflect'. Behavior for each valid value is as follows: 'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric. 'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. 'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel. 'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric. 'wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge. For consistency with the interpolation functions, the following mode names can also be used: 'grid-mirror' This is a synonym for 'reflect'. 'grid-constant' This is a synonym for 'constant'. 'grid-wrap' This is a synonym for 'wrap'.
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
origin	[int, optional] Controls the placement of the filter on the input array's pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right.

Examples

```
>>> from scipy.ndimage import correlate1d
>>> correlate1d([2, 8, 0, 4, 1, 9, 9, 0], weights=[1, 3])
array([ 8, 26,  8, 12,  7, 28, 36,  9])
```

scipy.ndimage.gaussian_filter

`scipy.ndimage.gaussian_filter` (*input*, *sigma*, *order=0*, *output=None*, *mode='reflect'*, *cval=0.0*, *truncate=4.0*)

Multidimensional Gaussian filter.

Parameters

input	[array_like] The input array.
sigma	[scalar or sequence of scalars] Standard deviation for Gaussian kernel. The standard deviations of the Gaussian filter are given for each axis as a sequence, or as a single number, in which case it is equal for all axes.
order	[int or sequence of ints, optional] The order of the filter along each axis is given as a sequence of integers, or as a single number. An order of 0 corresponds to convolution with a Gaussian kernel. A positive order corresponds to convolution with that derivative of a Gaussian.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
mode	[str or sequence, optional] The <i>mode</i> parameter determines how the input array is extended when the filter overlaps a border. By passing a sequence of modes with length equal to the number of dimensions of the input array, different modes can be specified along each axis. Default value is 'reflect'. The valid values and their behavior is as follows: 'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric. 'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. 'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel. 'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric. 'wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge. For consistency with the interpolation functions, the following mode names can also be used: 'grid-constant' This is a synonym for 'constant'. 'grid-mirror' This is a synonym for 'reflect'. 'grid-wrap' This is a synonym for 'wrap'.
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
truncate	[float] Truncate the filter at this many standard deviations. Default is 4.0.

Returns

gaussian_filter	[ndarray] Returned array of same shape as <i>input</i> .
------------------------	--

Notes

The multidimensional filter is implemented as a sequence of 1-D convolution filters. The intermediate arrays are stored in the same data type as the output. Therefore, for output types with a limited precision, the results may be imprecise because intermediate results may be stored with insufficient precision.

Examples

```
>>> from scipy.ndimage import gaussian_filter
>>> a = np.arange(50, step=2).reshape((5,5))
>>> a
array([[ 0,  2,  4,  6,  8],
       [10, 12, 14, 16, 18],
       [20, 22, 24, 26, 28],
       [30, 32, 34, 36, 38],
       [40, 42, 44, 46, 48]])
>>> gaussian_filter(a, sigma=1)
array([[ 4,  6,  8,  9, 11],
       [10, 12, 14, 15, 17],
       [20, 22, 24, 25, 27],
       [29, 31, 33, 34, 36],
       [35, 37, 39, 40, 42]])
```

```
>>> from scipy import misc
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> plt.gray() # show the filtered result in grayscale
>>> ax1 = fig.add_subplot(121) # left side
>>> ax2 = fig.add_subplot(122) # right side
>>> ascent = misc.ascent()
>>> result = gaussian_filter(ascent, sigma=5)
>>> ax1.imshow(ascent)
>>> ax2.imshow(result)
>>> plt.show()
```


scipy.ndimage.gaussian_filter1d

`scipy.ndimage.gaussian_filter1d`(*input*, *sigma*, *axis=-1*, *order=0*, *output=None*, *mode='reflect'*, *cval=0.0*, *truncate=4.0*)

1-D Gaussian filter.

Parameters

input	[array_like] The input array.
sigma	[scalar] standard deviation for Gaussian kernel
axis	[int, optional] The axis of <i>input</i> along which to calculate. Default is -1.
order	[int, optional] An order of 0 corresponds to convolution with a Gaussian kernel. A positive order corresponds to convolution with that derivative of a Gaussian.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the input array is extended beyond its boundaries. Default is 'reflect'. Behavior for each valid value is as follows:



‘reflect’ (*d c b a | a b c d | d c b a*)

The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.

‘constant’ (*k k k k | a b c d | k k k k*)

The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter.

‘nearest’ (*a a a a | a b c d | d d d d*)

The input is extended by replicating the last pixel.

‘mirror’ (*d c b | a b c d | c b a*)

The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.

‘wrap’ (*a b c d | a b c d | a b c d*)

The input is extended by wrapping around to the opposite edge.

For consistency with the interpolation functions, the following mode names can also be used:

‘grid-mirror’

This is a synonym for ‘reflect’.

‘grid-constant’

This is a synonym for ‘constant’.

‘grid-wrap’

This is a synonym for ‘wrap’.

cval [scalar, optional] Value to fill past edges of input if *mode* is ‘constant’. Default is 0.0.

truncate [float, optional] Truncate the filter at this many standard deviations. Default is 4.0.

Returns


gaussian_filter1d
[ndarray]

Examples

```

>>> from scipy.ndimage import gaussian_filter1d
>>> gaussian_filter1d([1.0, 2.0, 3.0, 4.0, 5.0], 1)
array([ 1.42704095,  2.06782203,  3.          ,  3.93217797,  4.57295905])
>>> gaussian_filter1d([1.0, 2.0, 3.0, 4.0, 5.0], 4)
array([ 2.91948343,  2.95023502,  3.          ,  3.04976498,  3.08051657])
>>> import matplotlib.pyplot as plt
>>> np.random.seed(280490)
>>> x = np.random.randn(101).cumsum()
>>> y3 = gaussian_filter1d(x, 3)
>>> y6 = gaussian_filter1d(x, 6)
>>> plt.plot(x, 'k', label='original data')
>>> plt.plot(y3, '--', label='filtered, sigma=3')
>>> plt.plot(y6, ':', label='filtered, sigma=6')
>>> plt.legend()
>>> plt.grid()
>>> plt.show()

```

**scipy.ndimage.gaussian_gradient_magnitude**

`scipy.ndimage.gaussian_gradient_magnitude` (*input*, *sigma*, *output=None*, *mode='reflect'*, *cval=0.0*, ***kwargs*)

Multidimensional gradient magnitude using Gaussian derivatives.

Parameters

input	[array_like] The input array.
sigma	[scalar or sequence of scalars] The standard deviations of the Gaussian filter are given for each axis as a sequence, or as a single number, in which case it is equal for all axes.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
mode	[str or sequence, optional] The <i>mode</i> parameter determines how the input array is extended when the filter overlaps a border. By passing a sequence of modes with length equal to the

number of dimensions of the input array, different modes can be specified along each axis. Default value is 'reflect'. The valid values and their behavior is as follows:

'reflect' (*d c b a | a b c d | d c b a*)

The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.

'constant' (*k k k k | a b c d | k k k k*)

The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter.

'nearest' (*a a a a | a b c d | d d d d*)

The input is extended by replicating the last pixel.

'mirror' (*d c b | a b c d | c b a*)

The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.

'wrap' (*a b c d | a b c d | a b c d*)

The input is extended by wrapping around to the opposite edge.

For consistency with the interpolation functions, the following mode names can also be used:

'grid-constant'

This is a synonym for 'constant'.

'grid-mirror'

This is a synonym for 'reflect'.

'grid-wrap'

This is a synonym for 'wrap'.

cval [scalar, optional] Value to fill past edges of input if *mode* is 'constant'. Default is 0.0.

Extra keyword arguments will be passed to `gaussian_filter()`.


Returns

gaussian_gradient_magnitude

[ndarray] Filtered array. Has the same shape as *input*.

Examples

```
>>> from scipy import ndimage, misc
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> plt.gray() # show the filtered result in grayscale
>>> ax1 = fig.add_subplot(121) # left side
>>> ax2 = fig.add_subplot(122) # right side
>>> ascent = misc.ascent()
>>> result = ndimage.gaussian_gradient_magnitude(ascent, sigma=5)
>>> ax1.imshow(ascent)
>>> ax2.imshow(result)
>>> plt.show()
```



scipy.ndimage.gaussian_laplace

`scipy.ndimage.gaussian_laplace` (*input*, *sigma*, *output=None*, *mode='reflect'*, *cval=0.0*, ***kwargs*)
 Multidimensional Laplace filter using Gaussian second derivatives.

Parameters

- input** [array_like] The input array.
 - sigma** [scalar or sequence of scalars] The standard deviations of the Gaussian filter are given for each axis as a sequence, or as a single number, in which case it is equal for all axes.
 - output** [array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
 - mode** [str or sequence, optional] The *mode* parameter determines how the input array is extended when the filter overlaps a border. By passing a sequence of modes with length equal to the number of dimensions of the input array, different modes can be specified along each axis. Default value is 'reflect'. The valid values and their behavior is as follows:
 - 'reflect'** (*d c b a | a b c d | d c b a*)
 The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.
 - 'constant'** (*k k k k | a b c d | k k k k*)
 The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter.
 - 'nearest'** (*a a a a | a b c d | d d d d*)
 The input is extended by replicating the last pixel.
 - 'mirror'** (*d c b | a b c d | c b a*)
 The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.
 - 'wrap'** (*a b c d | a b c d | a b c d*)
 The input is extended by wrapping around to the opposite edge.
- For consistency with the interpolation functions, the following mode names can also be used:
- 'grid-constant'**
 This is a synonym for 'constant'.
 - 'grid-mirror'**
 This is a synonym for 'reflect'.

‘grid-wrap’

This is a synonym for ‘wrap’.

cval [scalar, optional] Value to fill past edges of input if *mode* is ‘constant’. Default is 0.0.
Extra keyword arguments will be passed to `gaussian_filter()`.


Examples

```
>>> from scipy import ndimage, misc
>>> import matplotlib.pyplot as plt
>>> ascent = misc.ascent()
```

```
>>> fig = plt.figure()
>>> plt.gray() # show the filtered result in grayscale
>>> ax1 = fig.add_subplot(121) # left side
>>> ax2 = fig.add_subplot(122) # right side
```

```
>>> result = ndimage.gaussian_laplace(ascent, sigma=1)
>>> ax1.imshow(result)
```

```
>>> result = ndimage.gaussian_laplace(ascent, sigma=3)
>>> ax2.imshow(result)
>>> plt.show()
```



scipy.ndimage.generic_filter

```
scipy.ndimage.generic_filter(input, function, size=None, footprint=None, output=None,
                             mode='reflect', cval=0.0, origin=0, extra_arguments=(),
                             extra_keywords=None)
```

Calculate a multidimensional filter using the given function.

At each element the provided function is called. The input values within the filter footprint at that element are passed to the function as a 1-D array of double values.

Parameters

input	[array_like] The input array.
function	[{callable, scipy.LowLevelCallable}] Function to apply at each element.
size	[scalar or tuple, optional] See footprint, below. Ignored if footprint is given.
footprint	[array, optional] Either <i>size</i> or <i>footprint</i> must be defined. <i>size</i> gives the shape that is taken from the input array, at every element position, to define the input to the filter function. <i>footprint</i> is a boolean array that specifies (implicitly) a shape, but also which of the elements within this shape will get passed to the filter function. Thus <i>size</i> =(<i>n,m</i>) is equivalent to <i>footprint</i> = <code>np.ones((n,m))</code> . We adjust <i>size</i> to the number of dimensions of the input array, so that, if the input array is shape (10,10,10), and <i>size</i> is 2, then the actual size used is (2,2,2). When <i>footprint</i> is given, <i>size</i> is ignored.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the input array is extended beyond its boundaries. Default is 'reflect'. Behavior for each valid value is as follows: 'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric. 'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. 'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel. 'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric. 'wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge. For consistency with the interpolation functions, the following mode names can also be used: 'grid-mirror' This is a synonym for 'reflect'. 'grid-constant' This is a synonym for 'constant'. 'grid-wrap' This is a synonym for 'wrap'.
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
origin	[int or sequence, optional] Controls the placement of the filter on the input array's pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right. By passing a sequence of origins with length equal to the number of dimensions of the input array, different shifts can be specified along each axis.
extra_arguments	[sequence, optional] Sequence of extra positional arguments to pass to passed function.

extra_keywords

[dict, optional] dict of extra keyword arguments to pass to passed function.

Notes

This function also accepts low-level callback functions with one of the following signatures and wrapped in `scipy.LowLevelCallable`:

```
int callback(double *buffer, npy_intp filter_size,
             double *return_value, void *user_data)
int callback(double *buffer, intptr_t filter_size,
             double *return_value, void *user_data)
```

The calling function iterates over the elements of the input and output arrays, calling the callback function at each element. The elements within the footprint of the filter at the current element are passed through the `buffer` parameter, and the number of elements within the footprint through `filter_size`. The calculated value is returned in `return_value`. `user_data` is the data pointer provided to `scipy.LowLevelCallable` as-is.

The callback function must return an integer error status that is zero if something went wrong and one otherwise. If an error occurs, you should normally set the python error status with an informative message before returning, otherwise a default error message is set by the calling function.

In addition, some other low-level function pointer specifications are accepted, but these are for backward compatibility only and should not be used in new code.

scipy.ndimage.generic_filter1d

`scipy.ndimage.generic_filter1d` (*input*, *function*, *filter_size*, *axis=-1*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*, *extra_arguments=()*, *extra_keywords=None*)

Calculate a 1-D filter along the given axis.

`generic_filter1d` iterates over the lines of the array, calling the given function at each line. The arguments of the line are the input line, and the output line. The input and output lines are 1-D double arrays. The input line is extended appropriately according to the filter size and origin. The output line must be modified in-place with the result.

Parameters

- input** [array_like] The input array.
- function** [{callable, `scipy.LowLevelCallable`}] Function to apply along given axis.
- filter_size** [scalar] Length of the filter.
- axis** [int, optional] The axis of *input* along which to calculate. Default is -1.
- output** [array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
- mode** [{‘reflect’, ‘constant’, ‘nearest’, ‘mirror’, ‘wrap’}, optional] The *mode* parameter determines how the input array is extended beyond its boundaries. Default is ‘reflect’. Behavior for each valid value is as follows:
 - ‘reflect’** (*d c b a | a b c d | d c b a*)
The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.
 - ‘constant’** (*k k k k | a b c d | k k k k*)
The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter.

‘nearest’ (*a a a a | a b c d | d d d d*)

The input is extended by replicating the last pixel.

‘mirror’ (*d c b | a b c d | c b a*)

The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.

‘wrap’ (*a b c d | a b c d | a b c d*)

The input is extended by wrapping around to the opposite edge.

For consistency with the interpolation functions, the following mode names can also be used:

‘grid-mirror’

This is a synonym for ‘reflect’.

‘grid-constant’

This is a synonym for ‘constant’.

‘grid-wrap’

This is a synonym for ‘wrap’.

cval [scalar, optional] Value to fill past edges of input if *mode* is ‘constant’. Default is 0.0.

origin [int, optional] Controls the placement of the filter on the input array’s pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right.

extra_arguments

[sequence, optional] Sequence of extra positional arguments to pass to passed function.

extra_keywords

[dict, optional] dict of extra keyword arguments to pass to passed function.

Notes

This function also accepts low-level callback functions with one of the following signatures and wrapped in *scipy.LowLevelCallable*:

```
int function(double *input_line, npy_intp input_length,
             double *output_line, npy_intp output_length,
             void *user_data)
int function(double *input_line, intptr_t input_length,
             double *output_line, intptr_t output_length,
             void *user_data)
```

The calling function iterates over the lines of the input and output arrays, calling the callback function at each line. The current line is extended according to the border conditions set by the calling function, and the result is copied into the array that is passed through *input_line*. The length of the input line (after extension) is passed through *input_length*. The callback function should apply the filter and store the result in the array passed through *output_line*. The length of the output line is passed through *output_length*. *user_data* is the data pointer provided to *scipy.LowLevelCallable* as-is.

The callback function must return an integer error status that is zero if something went wrong and one otherwise. If an error occurs, you should normally set the python error status with an informative message before returning, otherwise a default error message is set by the calling function.

In addition, some other low-level function pointer specifications are accepted, but these are for backward compatibility only and should not be used in new code.

scipy.ndimage.generic_gradient_magnitude

`scipy.ndimage.generic_gradient_magnitude` (*input*, *derivative*, *output=None*, *mode='reflect'*,
cval=0.0, *extra_arguments=()*, *extra_keywords=None*)

Gradient magnitude using a provided gradient function.

Parameters

input [array_like] The input array.
derivative [callable] Callable with the following signature:

```
derivative(input, axis, output, mode, cval,
           *extra_arguments, **extra_keywords)
```

See *extra_arguments*, *extra_keywords* below. *derivative* can assume that *input* and *output* are ndarrays. Note that the output from *derivative* is modified inplace; be careful to copy important inputs before returning them.

output [array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.

mode [str or sequence, optional] The *mode* parameter determines how the input array is extended when the filter overlaps a border. By passing a sequence of modes with length equal to the number of dimensions of the input array, different modes can be specified along each axis. Default value is 'reflect'. The valid values and their behavior is as follows:

'reflect' (*d c b a | a b c d | d c b a*)

The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.

'constant' (*k k k k | a b c d | k k k k*)

The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter.

'nearest' (*a a a a | a b c d | d d d d*)

The input is extended by replicating the last pixel.

'mirror' (*d c b | a b c d | c b a*)

The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.

'wrap' (*a b c d | a b c d | a b c d*)

The input is extended by wrapping around to the opposite edge.

For consistency with the interpolation functions, the following mode names can also be used:

'grid-constant'

This is a synonym for 'constant'.

'grid-mirror'

This is a synonym for 'reflect'.

'grid-wrap'

This is a synonym for 'wrap'.

cval [scalar, optional] Value to fill past edges of input if *mode* is 'constant'. Default is 0.0.

extra_keywords

[dict, optional] dict of extra keyword arguments to pass to passed function.

extra_arguments

[sequence, optional] Sequence of extra positional arguments to pass to passed function.

scipy.ndimage.generic_laplace

`scipy.ndimage.generic_laplace` (*input*, *derivative2*, *output=None*, *mode='reflect'*, *cval=0.0*, *extra_arguments=()*, *extra_keywords=None*)

N-D Laplace filter using a provided second derivative function.

Parameters

input [array_like] The input array.

derivative2

[callable] Callable with the following signature:

```
derivative2(input, axis, output, mode, cval,
            *extra_arguments, **extra_keywords)
```

See *extra_arguments*, *extra_keywords* below.

output [array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.

mode [str or sequence, optional] The *mode* parameter determines how the input array is extended when the filter overlaps a border. By passing a sequence of modes with length equal to the number of dimensions of the input array, different modes can be specified along each axis. Default value is 'reflect'. The valid values and their behavior is as follows:

'reflect' (*d c b a | a b c d | d c b a*)

The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.

'constant' (*k k k k | a b c d | k k k k*)

The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter.

'nearest' (*a a a a | a b c d | d d d d*)

The input is extended by replicating the last pixel.

'mirror' (*d c b | a b c d | c b a*)

The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.

'wrap' (*a b c d | a b c d | a b c d*)

The input is extended by wrapping around to the opposite edge.

For consistency with the interpolation functions, the following mode names can also be used:

'grid-constant'

This is a synonym for 'constant'.

'grid-mirror'

This is a synonym for 'reflect'.

'grid-wrap'

This is a synonym for 'wrap'.

cval [scalar, optional] Value to fill past edges of input if *mode* is 'constant'. Default is 0.0.

extra_keywords

[dict, optional] dict of extra keyword arguments to pass to passed function.

extra_arguments

[sequence, optional] Sequence of extra positional arguments to pass to passed function.

scipy.ndimage.laplace

`scipy.ndimage.laplace` (*input*, *output=None*, *mode='reflect'*, *cval=0.0*)


N-D Laplace filter based on approximate second derivatives.

Parameters

input	[array_like] The input array.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
mode	[str or sequence, optional] The <i>mode</i> parameter determines how the input array is extended when the filter overlaps a border. By passing a sequence of modes with length equal to the number of dimensions of the input array, different modes can be specified along each axis. Default value is 'reflect'. The valid values and their behavior is as follows: 'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric. 'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. 'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel. 'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric. 'wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge. For consistency with the interpolation functions, the following mode names can also be used: 'grid-constant' This is a synonym for 'constant'. 'grid-mirror' This is a synonym for 'reflect'. 'grid-wrap' This is a synonym for 'wrap'.
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.

Examples

```
>>> from scipy import ndimage, misc
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> plt.gray() # show the filtered result in grayscale
>>> ax1 = fig.add_subplot(121) # left side
>>> ax2 = fig.add_subplot(122) # right side
>>> ascent = misc.ascent()
>>> result = ndimage.laplace(ascent)
>>> ax1.imshow(ascent)
>>> ax2.imshow(result)
>>> plt.show()
```



scipy.ndimage.maximum_filter

`scipy.ndimage.maximum_filter` (*input*, *size=None*, *footprint=None*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Calculate a multidimensional maximum filter.

Parameters

- input** [array_like] The input array.
- size** [scalar or tuple, optional] See footprint, below. Ignored if footprint is given.
- footprint** [array, optional] Either *size* or *footprint* must be defined. *size* gives the shape that is taken from the input array, at every element position, to define the input to the filter function. *footprint* is a boolean array that specifies (implicitly) a shape, but also which of the elements within this shape will get passed to the filter function. Thus *size*=(*n*,*m*) is equivalent to *footprint*=`np.ones((n,m))`. We adjust *size* to the number of dimensions of the input array, so that, if the input array is shape (10,10,10), and *size* is 2, then the actual size used is (2,2,2). When *footprint* is given, *size* is ignored.
- output** [array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
- mode** [str or sequence, optional] The *mode* parameter determines how the input array is extended when the filter overlaps a border. By passing a sequence of modes with length equal to the number of dimensions of the input array, different modes can be specified along each axis. Default value is 'reflect'. The valid values and their behavior is as follows:
 - 'reflect'** (*d c b a | a b c d | d c b a*)
The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.
 - 'constant'** (*k k k k | a b c d | k k k k*)
The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter.
 - 'nearest'** (*a a a a | a b c d | d d d d*)
The input is extended by replicating the last pixel.
 - 'mirror'** (*d c b | a b c d | c b a*)
The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.
 - 'wrap'** (*a b c d | a b c d | a b c d*)

The input is extended by wrapping around to the opposite edge.
For consistency with the interpolation functions, the following mode names can also be used:

‘grid-constant’

This is a synonym for ‘constant’.

‘grid-mirror’

This is a synonym for ‘reflect’.

‘grid-wrap’

This is a synonym for ‘wrap’.

cval [scalar, optional] Value to fill past edges of input if *mode* is ‘constant’. Default is 0.0.
origin [int or sequence, optional] Controls the placement of the filter on the input array’s pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right. By passing a sequence of origins with length equal to the number of dimensions of the input array, different shifts can be specified along each axis.

Returns

maximum_filter

[ndarray] Filtered array. Has the same shape as *input*.

Notes

A sequence of modes (one per axis) is only supported when the footprint is separable. Otherwise, a single mode string must be provided.

Examples

```
>>> from scipy import ndimage, misc
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> plt.gray() # show the filtered result in grayscale
>>> ax1 = fig.add_subplot(121) # left side
>>> ax2 = fig.add_subplot(122) # right side
>>> ascent = misc.ascent()
>>> result = ndimage.maximum_filter(ascent, size=20)
>>> ax1.imshow(ascent)
>>> ax2.imshow(result)
>>> plt.show()
```

scipy.ndimage.maximum_filter1d


`scipy.ndimage.maximum_filter1d(input, size, axis=-1, output=None, mode='reflect', cval=0.0, origin=0)`

Calculate a 1-D maximum filter along the given axis.

The lines of the array along the given axis are filtered with a maximum filter of given size.

Parameters

input [array_like] The input array.
size [int] Length along which to calculate the 1-D maximum.
axis [int, optional] The axis of *input* along which to calculate. Default is -1.
output [array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.



mode [{‘reflect’, ‘constant’, ‘nearest’, ‘mirror’, ‘wrap’}, optional] The *mode* parameter determines how the input array is extended beyond its boundaries. Default is ‘reflect’. Behavior for each valid value is as follows:

‘reflect’ (*d c b a | a b c d | d c b a*)

The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.

‘constant’ (*k k k k | a b c d | k k k k*)

The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter.

‘nearest’ (*a a a a | a b c d | d d d d*)

The input is extended by replicating the last pixel.

‘mirror’ (*d c b | a b c d | c b a*)

The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.

‘wrap’ (*a b c d | a b c d | a b c d*)

The input is extended by wrapping around to the opposite edge.

For consistency with the interpolation functions, the following mode names can also be used:

‘grid-mirror’

This is a synonym for ‘reflect’.

‘grid-constant’

This is a synonym for ‘constant’.

‘grid-wrap’

This is a synonym for ‘wrap’.

cval [scalar, optional] Value to fill past edges of input if *mode* is ‘constant’. Default is 0.0.

origin [int, optional] Controls the placement of the filter on the input array’s pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right.

Returns

maximum1d

[ndarray, None] Maximum-filtered array with same shape as input. None if *output* is not None

Notes

This function implements the MAXLIST algorithm [1], as described by Richard Harter [2], and has a guaranteed $O(n)$ performance, n being the *input* length, regardless of filter size.

References

[1], [2]

Examples

```
>>> from scipy.ndimage import maximum_filter1d
>>> maximum_filter1d([2, 8, 0, 4, 1, 9, 9, 0], size=3)
array([8, 8, 8, 4, 9, 9, 9, 9])
```

scipy.ndimage.median_filter

`scipy.ndimage.median_filter`(*input*, *size=None*, *footprint=None*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Calculate a multidimensional median filter.

Parameters

- input** [array_like] The input array.
- size** [scalar or tuple, optional] See footprint, below. Ignored if footprint is given.
- footprint** [array, optional] Either *size* or *footprint* must be defined. *size* gives the shape that is taken from the input array, at every element position, to define the input to the filter function. *footprint* is a boolean array that specifies (implicitly) a shape, but also which of the elements within this shape will get passed to the filter function. Thus *size*=(*n*,*m*) is equivalent to *footprint*=`np.ones((n,m))`. We adjust *size* to the number of dimensions of the input array, so that, if the input array is shape (10,10,10), and *size* is 2, then the actual size used is (2,2,2). When *footprint* is given, *size* is ignored.
- output** [array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
- mode** [{"reflect", "constant", "nearest", "mirror", "wrap"}, optional] The *mode* parameter determines how the input array is extended beyond its boundaries. Default is 'reflect'. Behavior for each valid value is as follows:
 - 'reflect'** (*d c b a | a b c d | d c b a*)
The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.
 - 'constant'** (*k k k k | a b c d | k k k k*)
The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter.
 - 'nearest'** (*a a a a | a b c d | d d d d*)
The input is extended by replicating the last pixel.
 - 'mirror'** (*d c b | a b c d | c b a*)
The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.
 - 'wrap'** (*a b c d | a b c d | a b c d*)
The input is extended by wrapping around to the opposite edge.

For consistency with the interpolation functions, the following mode names can also be used:

‘grid-mirror’

This is a synonym for ‘reflect’.

‘grid-constant’

This is a synonym for ‘constant’.

‘grid-wrap’

This is a synonym for ‘wrap’.

cval

[scalar, optional] Value to fill past edges of input if *mode* is ‘constant’. Default is 0.0.

origin


[int or sequence, optional] Controls the placement of the filter on the input array’s pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right. By passing a sequence of origins with length equal to the number of dimensions of the input array, different shifts can be specified along each axis.

Returns**median_filter**

[ndarray] Filtered array. Has the same shape as *input*.

Examples

```
>>> from scipy import ndimage, misc
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> plt.gray() # show the filtered result in grayscale
>>> ax1 = fig.add_subplot(121) # left side
>>> ax2 = fig.add_subplot(122) # right side
>>> ascent = misc.ascent()
>>> result = ndimage.median_filter(ascent, size=20)
>>> ax1.imshow(ascent)
>>> ax2.imshow(result)
>>> plt.show()
```



scipy.ndimage.minimum_filter

`scipy.ndimage.minimum_filter` (*input*, *size=None*, *footprint=None*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Calculate a multidimensional minimum filter.

Parameters

input	[array_like] The input array.
size	[scalar or tuple, optional] See footprint, below. Ignored if footprint is given.
footprint	[array, optional] Either <i>size</i> or <i>footprint</i> must be defined. <i>size</i> gives the shape that is taken from the input array, at every element position, to define the input to the filter function. <i>footprint</i> is a boolean array that specifies (implicitly) a shape, but also which of the elements within this shape will get passed to the filter function. Thus <i>size</i> =(<i>n,m</i>) is equivalent to <i>footprint</i> = <code>np.ones((n,m))</code> . We adjust <i>size</i> to the number of dimensions of the input array, so that, if the input array is shape (10,10,10), and <i>size</i> is 2, then the actual size used is (2,2,2). When <i>footprint</i> is given, <i>size</i> is ignored.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
mode	[str or sequence, optional] The <i>mode</i> parameter determines how the input array is extended when the filter overlaps a border. By passing a sequence of modes with length equal to the number of dimensions of the input array, different modes can be specified along each axis. Default value is 'reflect'. The valid values and their behavior is as follows: 'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric. 'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. 'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel. 'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric. 'wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge. For consistency with the interpolation functions, the following mode names can also be used: 'grid-constant' This is a synonym for 'constant'. 'grid-mirror' This is a synonym for 'reflect'. 'grid-wrap' This is a synonym for 'wrap'.
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
origin	[int or sequence, optional] Controls the placement of the filter on the input array's pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right. By passing a sequence of origins with length equal to the number of dimensions of the input array, different shifts can be specified along each axis.

Returns


minimum_filter
[ndarray] Filtered array. Has the same shape as *input*.

Notes

A sequence of modes (one per axis) is only supported when the footprint is separable. Otherwise, a single mode string must be provided.

Examples

```
>>> from scipy import ndimage, misc
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> plt.gray() # show the filtered result in grayscale
>>> ax1 = fig.add_subplot(121) # left side
>>> ax2 = fig.add_subplot(122) # right side
>>> ascent = misc.ascent()
>>> result = ndimage.minimum_filter(ascent, size=20)
>>> ax1.imshow(ascent)
>>> ax2.imshow(result)
>>> plt.show()
```



scipy.ndimage.minimum_filter1d

`scipy.ndimage.minimum_filter1d` (*input*, *size*, *axis=-1*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Calculate a 1-D minimum filter along the given axis.

The lines of the array along the given axis are filtered with a minimum filter of given size.

Parameters

input	[array_like] The input array.
size	[int] length along which to calculate 1D minimum
axis	[int, optional] The axis of <i>input</i> along which to calculate. Default is -1.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.

mode	<p>[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the input array is extended beyond its boundaries. Default is 'reflect'. Behavior for each valid value is as follows:</p> <p>'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.</p> <p>'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter.</p> <p>'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel.</p> <p>'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.</p> <p>'wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge.</p> <p>For consistency with the interpolation functions, the following mode names can also be used:</p> <p>'grid-mirror' This is a synonym for 'reflect'.</p> <p>'grid-constant' This is a synonym for 'constant'.</p> <p>'grid-wrap' This is a synonym for 'wrap'.</p>
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
origin	[int, optional] Controls the placement of the filter on the input array's pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right.

Notes

This function implements the MINLIST algorithm [1], as described by Richard Harter [2], and has a guaranteed $O(n)$ performance, n being the *input* length, regardless of filter size.

References

[1], [2]

Examples

```
>>> from scipy.ndimage import minimum_filter1d
>>> minimum_filter1d([2, 8, 0, 4, 1, 9, 9, 0], size=3)
array([2, 0, 0, 0, 1, 1, 0, 0])
```

scipy.ndimage.percentile_filter

`scipy.ndimage.percentile_filter`(*input*, *percentile*, *size=None*, *footprint=None*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Calculate a multidimensional percentile filter.

Parameters

- input** [array_like] The input array.
- percentile** [scalar] The percentile parameter may be less than zero, i.e., percentile = -20 equals percentile = 80
- size** [scalar or tuple, optional] See footprint, below. Ignored if footprint is given.
- footprint** [array, optional] Either *size* or *footprint* must be defined. *size* gives the shape that is taken from the input array, at every element position, to define the input to the filter function. *footprint* is a boolean array that specifies (implicitly) a shape, but also which of the elements within this shape will get passed to the filter function. Thus *size*=(*n*,*m*) is equivalent to *footprint*=`np.ones((n,m))`. We adjust *size* to the number of dimensions of the input array, so that, if the input array is shape (10,10,10), and *size* is 2, then the actual size used is (2,2,2). When *footprint* is given, *size* is ignored.
- output** [array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
- mode** [{`'reflect'`, `'constant'`, `'nearest'`, `'mirror'`, `'wrap'`}, optional] The *mode* parameter determines how the input array is extended beyond its boundaries. Default is `'reflect'`. Behavior for each valid value is as follows:
- 'reflect'** (*d c b a | a b c d | d c b a*)
The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.
- 'constant'** (*k k k k | a b c d | k k k k*)
The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter.
- 'nearest'** (*a a a a | a b c d | d d d d*)
The input is extended by replicating the last pixel.
- 'mirror'** (*d c b | a b c d | c b a*)
The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.
- 'wrap'** (*a b c d | a b c d | a b c d*)
The input is extended by wrapping around to the opposite edge.
- For consistency with the interpolation functions, the following mode names can also be used:
- 'grid-mirror'**
This is a synonym for `'reflect'`.
- 'grid-constant'**
This is a synonym for `'constant'`.
- 'grid-wrap'**
This is a synonym for `'wrap'`.
- cval** [scalar, optional] Value to fill past edges of input if *mode* is `'constant'`. Default is 0.0.
- origin** [int or sequence, optional] Controls the placement of the filter on the input array's pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right. By passing a sequence of origins with length equal to the number of dimensions of the input array, different shifts can be specified along each axis.


Returns

- percentile_filter**
[ndarray] Filtered array. Has the same shape as *input*.

Examples

```

>>> from scipy import ndimage, misc
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> plt.gray() # show the filtered result in grayscale
>>> ax1 = fig.add_subplot(121) # left side
>>> ax2 = fig.add_subplot(122) # right side
>>> ascent = misc.ascent()
>>> result = ndimage.percentile_filter(ascent, percentile=20, size=20)
>>> ax1.imshow(ascent)
>>> ax2.imshow(result)
>>> plt.show()
    
```



scipy.ndimage.prewitt

`scipy.ndimage.prewitt` (*input*, *axis=-1*, *output=None*, *mode='reflect'*, *cval=0.0*)

Calculate a Prewitt filter.

Parameters

- input** [array_like] The input array.
- axis** [int, optional] The axis of *input* along which to calculate. Default is -1.
- output** [array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
- mode** [str or sequence, optional] The *mode* parameter determines how the input array is extended when the filter overlaps a border. By passing a sequence of modes with length equal to the number of dimensions of the input array, different modes can be specified along each axis. Default value is 'reflect'. The valid values and their behavior is as follows:
 - 'reflect' (*d c b a | a b c d | d c b a*)
The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.
 - 'constant' (*k k k k | a b c d | k k k k*)

The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter.

‘nearest’ (*a a a a | a b c d | d d d d*)

The input is extended by replicating the last pixel.

‘mirror’ (*d c b | a b c d | c b a*)

The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.

‘wrap’ (*a b c d | a b c d | a b c d*)

The input is extended by wrapping around to the opposite edge.

For consistency with the interpolation functions, the following mode names can also be used:

‘grid-constant’

This is a synonym for ‘constant’.

‘grid-mirror’

This is a synonym for ‘reflect’.


‘grid-wrap’

This is a synonym for ‘wrap’.

cval [scalar, optional] Value to fill past edges of input if *mode* is ‘constant’. Default is 0.0.

Examples

```
>>> from scipy import ndimage, misc
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> plt.gray() # show the filtered result in grayscale
>>> ax1 = fig.add_subplot(121) # left side
>>> ax2 = fig.add_subplot(122) # right side
>>> ascent = misc.ascent()
>>> result = ndimage.prewitt(ascent)
>>> ax1.imshow(ascent)
>>> ax2.imshow(result)
>>> plt.show()
```



scipy.ndimage.rank_filter

`scipy.ndimage.rank_filter` (*input*, *rank*, *size=None*, *footprint=None*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Calculate a multidimensional rank filter.

Parameters

input	[array_like] The input array.
rank	[int] The rank parameter may be less than zero, i.e., <code>rank = -1</code> indicates the largest element.
size	[scalar or tuple, optional] See <code>footprint</code> , below. Ignored if <code>footprint</code> is given.
footprint	[array, optional] Either <i>size</i> or <i>footprint</i> must be defined. <i>size</i> gives the shape that is taken from the input array, at every element position, to define the input to the filter function. <i>footprint</i> is a boolean array that specifies (implicitly) a shape, but also which of the elements within this shape will get passed to the filter function. Thus <code>size=(n,m)</code> is equivalent to <code>footprint=np.ones((n,m))</code> . We adjust <i>size</i> to the number of dimensions of the input array, so that, if the input array is shape (10,10,10), and <i>size</i> is 2, then the actual size used is (2,2,2). When <i>footprint</i> is given, <i>size</i> is ignored.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the input array is extended beyond its boundaries. Default is 'reflect'. Behavior for each valid value is as follows: 'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric. 'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. 'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel. 'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric. 'wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge. For consistency with the interpolation functions, the following mode names can also be used: 'grid-mirror' This is a synonym for 'reflect'. 'grid-constant' This is a synonym for 'constant'. 'grid-wrap' This is a synonym for 'wrap'.
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
origin	[int or sequence, optional] Controls the placement of the filter on the input array's pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right. By passing a sequence of origins with length equal to the number of dimensions of the input array, different shifts can be specified along each axis.

Returns


rank_filter	[ndarray] Filtered array. Has the same shape as <i>input</i> .
--------------------	--

Examples

```

>>> from scipy import ndimage, misc
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> plt.gray() # show the filtered result in grayscale
>>> ax1 = fig.add_subplot(121) # left side
>>> ax2 = fig.add_subplot(122) # right side
>>> ascent = misc.ascent()
>>> result = ndimage.rank_filter(ascent, rank=42, size=20)
>>> ax1.imshow(ascent)
>>> ax2.imshow(result)
>>> plt.show()

```

**scipy.ndimage.sobel**

`scipy.ndimage.sobel` (*input*, *axis=-1*, *output=None*, *mode='reflect'*, *cval=0.0*)

Calculate a Sobel filter.

Parameters

- input** [array_like] The input array.
- axis** [int, optional] The axis of *input* along which to calculate. Default is -1.
- output** [array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
- mode** [str or sequence, optional] The *mode* parameter determines how the input array is extended when the filter overlaps a border. By passing a sequence of modes with length equal to the number of dimensions of the input array, different modes can be specified along each axis. Default value is 'reflect'. The valid values and their behavior is as follows:
 - 'reflect' (*d c b a | a b c d | d c b a*)
The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.
 - 'constant' (*k k k k | a b c d | k k k k*)

The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter.

‘nearest’ (*a a a a | a b c d | d d d d*)

The input is extended by replicating the last pixel.

‘mirror’ (*d c b | a b c d | c b a*)

The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.

‘wrap’ (*a b c d | a b c d | a b c d*)

The input is extended by wrapping around to the opposite edge.

For consistency with the interpolation functions, the following mode names can also be used:

‘grid-constant’

This is a synonym for ‘constant’.

‘grid-mirror’

This is a synonym for ‘reflect’.


‘grid-wrap’

This is a synonym for ‘wrap’.

cval [scalar, optional] Value to fill past edges of input if *mode* is ‘constant’. Default is 0.0.

Examples

```
>>> from scipy import ndimage, misc
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> plt.gray() # show the filtered result in grayscale
>>> ax1 = fig.add_subplot(121) # left side
>>> ax2 = fig.add_subplot(122) # right side
>>> ascent = misc.ascent()
>>> result = ndimage.sobel(ascent)
>>> ax1.imshow(ascent)
>>> ax2.imshow(result)
>>> plt.show()
```



scipy.ndimage.uniform_filter

`scipy.ndimage.uniform_filter` (*input*, *size=3*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)
Multidimensional uniform filter.

Parameters

input	[array_like] The input array.
size	[int or sequence of ints, optional] The sizes of the uniform filter are given for each axis as a sequence, or as a single number, in which case the size is equal for all axes.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
mode	[str or sequence, optional] The <i>mode</i> parameter determines how the input array is extended when the filter overlaps a border. By passing a sequence of modes with length equal to the number of dimensions of the input array, different modes can be specified along each axis. Default value is 'reflect'. The valid values and their behavior is as follows: 'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric. 'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. 'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel. 'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric. 'wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge. For consistency with the interpolation functions, the following mode names can also be used: 'grid-constant' This is a synonym for 'constant'. 'grid-mirror' This is a synonym for 'reflect'. 'grid-wrap' This is a synonym for 'wrap'.
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
origin	[int or sequence, optional] Controls the placement of the filter on the input array's pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right. By passing a sequence of origins with length equal to the number of dimensions of the input array, different shifts can be specified along each axis.

Returns


uniform_filter	[ndarray] Filtered array. Has the same shape as <i>input</i> .
-----------------------	--

Notes

The multidimensional filter is implemented as a sequence of 1-D uniform filters. The intermediate arrays are stored in the same data type as the output. Therefore, for output types with a limited precision, the results may be imprecise because intermediate results may be stored with insufficient precision.

Examples

```
>>> from scipy import ndimage, misc
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> plt.gray() # show the filtered result in grayscale
>>> ax1 = fig.add_subplot(121) # left side
>>> ax2 = fig.add_subplot(122) # right side
>>> ascent = misc.ascent()
>>> result = ndimage.uniform_filter(ascent, size=20)
>>> ax1.imshow(ascent)
>>> ax2.imshow(result)
>>> plt.show()
```



scipy.ndimage.uniform_filter1d

`scipy.ndimage.uniform_filter1d` (*input*, *size*, *axis=-1*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Calculate a 1-D uniform filter along the given axis.

The lines of the array along the given axis are filtered with a uniform filter of given size.

Parameters

input	[array_like] The input array.
size	[int] length of uniform filter
axis	[int, optional] The axis of <i>input</i> along which to calculate. Default is -1.

output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
mode	<p>[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the input array is extended beyond its boundaries. Default is 'reflect'. Behavior for each valid value is as follows:</p> <p>'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.</p> <p>'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter.</p> <p>'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel.</p> <p>'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.</p> <p>'wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge.</p> <p>For consistency with the interpolation functions, the following mode names can also be used:</p> <p>'grid-mirror' This is a synonym for 'reflect'.</p> <p>'grid-constant' This is a synonym for 'constant'.</p> <p>'grid-wrap' This is a synonym for 'wrap'.</p>
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
origin	[int, optional] Controls the placement of the filter on the input array's pixels. A value of 0 (the default) centers the filter over the pixel, with positive values shifting the filter to the left, and negative ones to the right.

Examples

```
>>> from scipy.ndimage import uniform_filter1d
>>> uniform_filter1d([2, 8, 0, 4, 1, 9, 9, 0], size=3)
array([4, 3, 4, 1, 4, 6, 6, 3])
```

6.17.2 Fourier filters

<i>fourier_ellipsoid</i> (input, size[, n, axis, output])	Multidimensional ellipsoid Fourier filter.
<i>fourier_gaussian</i> (input, sigma[, n, axis, output])	Multidimensional Gaussian fourier filter.
<i>fourier_shift</i> (input, shift[, n, axis, output])	Multidimensional Fourier shift filter.
<i>fourier_uniform</i> (input, size[, n, axis, output])	Multidimensional uniform fourier filter.

scipy.ndimage.fourier_ellipsoid

`scipy.ndimage.fourier_ellipsoid` (*input*, *size*, *n=-1*, *axis=-1*, *output=None*)
Multidimensional ellipsoid Fourier filter.

The array is multiplied with the fourier transform of a ellipsoid of given sizes.

Parameters

input	[array_like] The input array.
size	[float or sequence] The size of the box used for filtering. If a float, <i>size</i> is the same for all axes. If a sequence, <i>size</i> has to contain one value for each axis.
n	[int, optional] If <i>n</i> is negative (default), then the input is assumed to be the result of a complex fft. If <i>n</i> is larger than or equal to zero, the input is assumed to be the result of a real fft, and <i>n</i> gives the length of the array before transformation along the real transform direction.
axis	[int, optional] The axis of the real transform.
output	[ndarray, optional] If given, the result of filtering the input is placed in this array. None is returned in this case.

Returns

fourier_ellipsoid	[ndarray] The filtered input.
--------------------------	-------------------------------

Notes

This function is implemented for arrays of rank 1, 2, or 3.

Examples

```
>>> from scipy import ndimage, misc
>>> import numpy.fft
>>> import matplotlib.pyplot as plt
>>> fig, (ax1, ax2) = plt.subplots(1, 2)
>>> plt.gray() # show the filtered result in grayscale
>>> ascent = misc.ascent()
>>> input_ = numpy.fft.fft2(ascent)
>>> result = ndimage.fourier_ellipsoid(input_, size=20)
>>> result = numpy.fft.ifft2(result)
>>> ax1.imshow(ascent)
>>> ax2.imshow(result.real) # the imaginary part is an artifact
>>> plt.show()
```


scipy.ndimage.fourier_gaussian

`scipy.ndimage.fourier_gaussian` (*input*, *sigma*, *n=-1*, *axis=-1*, *output=None*)
Multidimensional Gaussian fourier filter.

The array is multiplied with the fourier transform of a Gaussian kernel.

Parameters

input	[array_like] The input array.
sigma	[float or sequence] The sigma of the Gaussian kernel. If a float, <i>sigma</i> is the same for all axes. If a sequence, <i>sigma</i> has to contain one value for each axis.




- n** [int, optional] If *n* is negative (default), then the input is assumed to be the result of a complex fft. If *n* is larger than or equal to zero, the input is assumed to be the result of a real fft, and *n* gives the length of the array before transformation along the real transform direction.
- axis** [int, optional] The axis of the real transform.
- output** [ndarray, optional] If given, the result of filtering the input is placed in this array. None is returned in this case.

Returns

- fourier_gaussian**
[ndarray] The filtered input.

Examples

```
>>> from scipy import ndimage, misc
>>> import numpy.fft
>>> import matplotlib.pyplot as plt
>>> fig, (ax1, ax2) = plt.subplots(1, 2)
>>> plt.gray() # show the filtered result in grayscale
>>> ascent = misc.ascent()
>>> input_ = numpy.fft.fft2(ascent)
>>> result = ndimage.fourier_gaussian(input_, sigma=4)
>>> result = numpy.fft.ifft2(result)
>>> ax1.imshow(ascent)
>>> ax2.imshow(result.real) # the imaginary part is an artifact
>>> plt.show()
```



scipy.ndimage.fourier_shift

`scipy.ndimage.fourier_shift` (*input*, *shift*, *n=-1*, *axis=-1*, *output=None*)

Multidimensional Fourier shift filter.

The array is multiplied with the Fourier transform of a shift operation.

Parameters

input	[array_like] The input array.
shift	[float or sequence] The size of the box used for filtering. If a float, <i>shift</i> is the same for all axes. If a sequence, <i>shift</i> has to contain one value for each axis.
n	[int, optional] If <i>n</i> is negative (default), then the input is assumed to be the result of a complex fft. If <i>n</i> is larger than or equal to zero, the input is assumed to be the result of a real fft, and <i>n</i> gives the length of the array before transformation along the real transform direction.
axis	[int, optional] The axis of the real transform.
output	[ndarray, optional] If given, the result of shifting the input is placed in this array. None is returned in this case.

Returns

fourier_shift	[ndarray] The shifted input.
----------------------	------------------------------

Examples

```
>>> from scipy import ndimage, misc
>>> import matplotlib.pyplot as plt
>>> import numpy.fft
>>> fig, (ax1, ax2) = plt.subplots(1, 2)
>>> plt.gray() # show the filtered result in grayscale
>>> ascent = misc.ascent()
>>> input_ = numpy.fft.fft2(ascent)
>>> result = ndimage.fourier_shift(input_, shift=200)
>>> result = numpy.fft.ifft2(result)
```


(continues on next page)

(continued from previous page)

```

>>> ax1.imshow(ascent)
>>> ax2.imshow(result.real) # the imaginary part is an artifact
>>> plt.show()

```



scipy.ndimage.fourier_uniform

`scipy.ndimage.fourier_uniform` (*input*, *size*, *n=-1*, *axis=-1*, *output=None*)
 Multidimensional uniform fourier filter.

The array is multiplied with the Fourier transform of a box of given size.

Parameters

input	[array_like] The input array.
size	[float or sequence] The size of the box used for filtering. If a float, <i>size</i> is the same for all axes. If a sequence, <i>size</i> has to contain one value for each axis.
n	[int, optional] If <i>n</i> is negative (default), then the input is assumed to be the result of a complex fft. If <i>n</i> is larger than or equal to zero, the input is assumed to be the result of a real fft, and <i>n</i> gives the length of the array before transformation along the real transform direction.
axis	[int, optional] The axis of the real transform.
output	[ndarray, optional] If given, the result of filtering the input is placed in this array. None is returned in this case.


Returns

fourier_uniform	[ndarray] The filtered input.
------------------------	-------------------------------

Examples

```

>>> from scipy import ndimage, misc
>>> import numpy.fft
>>> import matplotlib.pyplot as plt
>>> fig, (ax1, ax2) = plt.subplots(1, 2)
>>> plt.gray() # show the filtered result in grayscale
>>> ascent = misc.ascent()
>>> input_ = numpy.fft.fft2(ascent)
>>> result = ndimage.fourier_uniform(input_, size=20)
>>> result = numpy.fft.ifft2(result)
>>> ax1.imshow(ascent)
>>> ax2.imshow(result.real) # the imaginary part is an artifact
>>> plt.show()
    
```



6.17.3 Interpolation

<code>affine_transform(input, matrix[, offset, ...])</code>	Apply an affine transformation.
<code>geometric_transform(input, mapping[, ...])</code>	Apply an arbitrary geometric transform.
<code>map_coordinates(input, coordinates[, ...])</code>	Map the input array to new coordinates by interpolation.
<code>rotate(input, angle[, axes, reshape, ...])</code>	Rotate an array.
<code>shift(input, shift[, output, order, mode, ...])</code>	Shift an array.
<code>spline_filter(input[, order, output, mode])</code>	Multidimensional spline filter.
<code>spline_filter1d(input[, order, axis, ...])</code>	Calculate a 1-D spline filter along the given axis.
<code>zoom(input, zoom[, output, order, mode, ...])</code>	Zoom an array.

scipy.ndimage.affine_transform

`scipy.ndimage.affine_transform` (*input*, *matrix*, *offset=0.0*, *output_shape=None*, *output=None*, *order=3*, *mode='constant'*, *cval=0.0*, *prefilter=True*)

Apply an affine transformation.

Given an output image pixel index vector *o*, the pixel value is determined from the input image at position `np.dot(matrix, o) + offset`.

This does ‘pull’ (or ‘backward’) resampling, transforming the output space to the input to locate data. Affine transformations are often described in the ‘push’ (or ‘forward’) direction, transforming input to output. If you have a matrix for the ‘push’ transformation, use its inverse (`numpy.linalg.inv`) in this function.

Parameters

input	[array_like] The input array.
matrix	[ndarray] The inverse coordinate transformation matrix, mapping output coordinates to input coordinates. If <i>ndim</i> is the number of dimensions of <i>input</i> , the given matrix must have one of the following shapes: <ul style="list-style-type: none"> <code>(ndim, ndim)</code>: the linear transformation matrix for each output coordinate. <code>(ndim,)</code>: assume that the 2-D transformation matrix is diagonal, with the diagonal specified by the given value. A more efficient algorithm is then used that exploits the separability of the problem. <code>(ndim + 1, ndim + 1)</code>: assume that the transformation is specified using homogeneous coordinates [1]. In this case, any value passed to <i>offset</i> is ignored. <code>(ndim, ndim + 1)</code>: as above, but the bottom row of a homogeneous transformation matrix is always <code>[0, 0, ..., 1]</code>, and may be omitted.
offset	[float or sequence, optional] The offset into the array where the transform is applied. If a float, <i>offset</i> is the same for each axis. If a sequence, <i>offset</i> should contain one value for each axis.
output_shape	[tuple of ints, optional] Shape tuple.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as <i>input</i> will be created.
order	[int, optional] The order of the spline interpolation, default is 3. The order has to be in the range 0-5.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the input array is extended beyond its boundaries. Default is ‘constant’. Behavior for each valid value is as follows (see additional plots and details on <i>boundary modes</i>): <p>‘reflect’ (<i>d c b a a b c d d c b a</i>)</p> <p>The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.</p> <p>‘grid-mirror’</p> <p>This is a synonym for ‘reflect’.</p> <p>‘constant’ (<i>k k k k a b c d k k k k</i>)</p> <p>The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. No interpolation is performed beyond the edges of the input.</p> <p>‘grid-constant’ (<i>k k k k a b c d k k k k</i>)</p> <p>The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. Interpolation occurs for samples outside the input’s extent as well.</p> <p>‘nearest’ (<i>a a a a a b c d d d d d</i>)</p> <p>The input is extended by replicating the last pixel.</p>

‘mirror’ (*d c b | a b c d | c b a*)

The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.

‘grid-wrap’ (*a b c d | a b c d | a b c d*)

The input is extended by wrapping around to the opposite edge.

‘wrap’ (*d b c d | a b c d | b c a b*)

The input is extended by wrapping around to the opposite edge, but in a way such that the last point and initial point exactly overlap. In this case it is not well defined which sample will be chosen at the point of overlap.

cval [scalar, optional] Value to fill past edges of input if *mode* is ‘constant’. Default is 0.0.

prefilter [bool, optional] Determines if the input array is prefiltered with `spline_filter` before interpolation. The default is True, which will create a temporary `float64` array of filtered values if *order* > 1. If setting this to False, the output will be slightly blurred if *order* > 1, unless the input is prefiltered, i.e. it is the result of calling `spline_filter` on the original input.

Returns

affine_transform

[ndarray] The transformed input.

Notes

The given matrix and offset are used to find for each point in the output the corresponding coordinates in the input by an affine transformation. The value of the input at those coordinates is determined by spline interpolation of the requested order. Points outside the boundaries of the input are filled according to the given mode.

Changed in version 0.18.0: Previously, the exact interpretation of the affine transformation depended on whether the matrix was supplied as a 1-D or a 2-D array. If a 1-D array was supplied to the matrix parameter, the output pixel value at index *o* was determined from the input image at position `matrix * (o + offset)`.

For complex-valued *input*, this function transforms the real and imaginary components independently.

New in version 1.6.0: Complex-valued support added.

References

[1]

scipy.ndimage.geometric_transform

`scipy.ndimage.geometric_transform`(*input*, *mapping*, *output_shape=None*, *output=None*, *order=3*, *mode='constant'*, *cval=0.0*, *prefilter=True*, *extra_arguments=()*, *extra_keywords={}*)

Apply an arbitrary geometric transform.

The given mapping function is used to find, for each point in the output, the corresponding coordinates in the input. The value of the input at those coordinates is determined by spline interpolation of the requested order.

Parameters

input [array_like] The input array.

mapping [{callable, `scipy.LowLevelCallable`}] A callable object that accepts a tuple of length equal to the output array rank, and returns the corresponding input coordinates as a tuple of length equal to the input array rank.

output_shape	[tuple of ints, optional] Shape tuple.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
order	[int, optional] The order of the spline interpolation, default is 3. The order has to be in the range 0-5.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the input array is extended beyond its boundaries. Default is 'constant'. Behavior for each valid value is as follows (see additional plots and details on <i>boundary modes</i>): <ul style="list-style-type: none"> 'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric. 'grid-mirror' This is a synonym for 'reflect'. 'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. No interpolation is performed beyond the edges of the input. 'grid-constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. Interpolation occurs for samples outside the input's extent as well. 'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel. 'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric. 'grid-wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge. 'wrap' (<i>d b c d a b c d b c a b</i>) The input is extended by wrapping around to the opposite edge, but in a way such that the last point and initial point exactly overlap. In this case it is not well defined which sample will be chosen at the point of overlap.
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
prefilter	[bool, optional] Determines if the input array is prefiltered with <i>spline_filter</i> before interpolation. The default is True, which will create a temporary <i>float64</i> array of filtered values if <i>order</i> > 1. If setting this to False, the output will be slightly blurred if <i>order</i> > 1, unless the input is prefiltered, i.e. it is the result of calling <i>spline_filter</i> on the original input.
extra_arguments	[tuple, optional] Extra arguments passed to <i>mapping</i> .
extra_keywords	[dict, optional] Extra keywords passed to <i>mapping</i> .

Returns

output [ndarray] The filtered input.

See also:

map_coordinates, *affine_transform*, *spline_filter1d*

Notes

This function also accepts low-level callback functions with one the following signatures and wrapped in `scipy.LowLevelCallable`:

```
int mapping(numpy_intp *output_coordinates, double *input_coordinates,
            int output_rank, int input_rank, void *user_data)
int mapping(intptr_t *output_coordinates, double *input_coordinates,
            int output_rank, int input_rank, void *user_data)
```

The calling function iterates over the elements of the output array, calling the callback function at each element. The coordinates of the current output element are passed through `output_coordinates`. The callback function must return the coordinates at which the input must be interpolated in `input_coordinates`. The rank of the input and output arrays are given by `input_rank` and `output_rank` respectively. `user_data` is the data pointer provided to `scipy.LowLevelCallable` as-is.

The callback function must return an integer error status that is zero if something went wrong and one otherwise. If an error occurs, you should normally set the Python error status with an informative message before returning, otherwise a default error message is set by the calling function.

In addition, some other low-level function pointer specifications are accepted, but these are for backward compatibility only and should not be used in new code.

For complex-valued *input*, this function transforms the real and imaginary components independently.

New in version 1.6.0: Complex-valued support added.

Examples

```
>>> import numpy as np
>>> from scipy.ndimage import geometric_transform
>>> a = np.arange(12.).reshape((4, 3))
>>> def shift_func(output_coords):
...     return (output_coords[0] - 0.5, output_coords[1] - 0.5)
...
>>> geometric_transform(a, shift_func)
array([[ 0.   ,  0.   ,  0.   ],
       [ 0.   ,  1.362,  2.738],
       [ 0.   ,  4.812,  6.187],
       [ 0.   ,  8.263,  9.637]])
```

```
>>> b = [1, 2, 3, 4, 5]
>>> def shift_func(output_coords):
...     return (output_coords[0] - 3,)
...
>>> geometric_transform(b, shift_func, mode='constant')
array([0, 0, 0, 1, 2])
>>> geometric_transform(b, shift_func, mode='nearest')
array([1, 1, 1, 1, 2])
>>> geometric_transform(b, shift_func, mode='reflect')
array([3, 2, 1, 1, 2])
>>> geometric_transform(b, shift_func, mode='wrap')
array([2, 3, 4, 1, 2])
```

scipy.ndimage.map_coordinates

`scipy.ndimage.map_coordinates` (*input*, *coordinates*, *output=None*, *order=3*, *mode='constant'*, *cval=0.0*, *prefilter=True*)

Map the input array to new coordinates by interpolation.

The array of coordinates is used to find, for each point in the output, the corresponding coordinates in the input. The value of the input at those coordinates is determined by spline interpolation of the requested order.

The shape of the output is derived from that of the coordinate array by dropping the first axis. The values of the array along the first axis are the coordinates in the input array at which the output value is found.

Parameters

input	[array_like] The input array.
coordinates	[array_like] The coordinates at which <i>input</i> is evaluated.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as <i>input</i> will be created.
order	[int, optional] The order of the spline interpolation, default is 3. The order has to be in the range 0-5.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the input array is extended beyond its boundaries. Default is 'constant'. Behavior for each valid value is as follows (see additional plots and details on <i>boundary modes</i>): <ul style="list-style-type: none"> 'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric. 'grid-mirror' This is a synonym for 'reflect'. 'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. No interpolation is performed beyond the edges of the input. 'grid-constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. Interpolation occurs for samples outside the input's extent as well. 'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel. 'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric. 'grid-wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge. 'wrap' (<i>d b c d a b c d b c a b</i>) The input is extended by wrapping around to the opposite edge, but in a way such that the last point and initial point exactly overlap. In this case it is not well defined which sample will be chosen at the point of overlap.
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
prefilter	[bool, optional] Determines if the input array is prefiltered with <i>spline_filter</i> before interpolation. The default is True, which will create a temporary <i>float64</i> array of filtered values if <i>order</i> > 1. If setting this to False, the output will be slightly blurred if <i>order</i> > 1, unless the input is prefiltered, i.e. it is the result of calling <i>spline_filter</i> on the original input.

Returns

map_coordinates

[ndarray] The result of transforming the input. The shape of the output is derived from that of *coordinates* by dropping the first axis.

See also:

spline_filter, *geometric_transform*, *scipy.interpolate*

Notes

For complex-valued *input*, this function maps the real and imaginary components independently.

New in version 1.6.0: Complex-valued support added.

Examples

```
>>> from scipy import ndimage
>>> a = np.arange(12.).reshape((4, 3))
>>> a
array([[ 0.,  1.,  2.],
       [ 3.,  4.,  5.],
       [ 6.,  7.,  8.],
       [ 9., 10., 11.]])
>>> ndimage.map_coordinates(a, [[0.5, 2], [0.5, 1]], order=1)
array([ 2.,  7.]])
```

Above, the interpolated value of `a[0.5, 0.5]` gives `output[0]`, while `a[2, 1]` is `output[1]`.

```
>>> inds = np.array([[0.5, 2], [0.5, 4]])
>>> ndimage.map_coordinates(a, inds, order=1, cval=-33.3)
array([ 2. , -33.3])
>>> ndimage.map_coordinates(a, inds, order=1, mode='nearest')
array([ 2.,  8.])
>>> ndimage.map_coordinates(a, inds, order=1, cval=0, output=bool)
array([ True, False], dtype=bool)
```

scipy.ndimage.rotate

`scipy.ndimage.rotate` (*input*, *angle*, *axes=1, 0*, *reshape=True*, *output=None*, *order=3*, *mode='constant'*, *cval=0.0*, *prefilter=True*)

Rotate an array.

The array is rotated in the plane defined by the two axes given by the *axes* parameter using spline interpolation of the requested order.

Parameters

input	[array_like] The input array.
angle	[float] The rotation angle in degrees.
axes	[tuple of 2 ints, optional] The two axes that define the plane of rotation. Default is the first two axes.
reshape	[bool, optional] If <i>reshape</i> is true, the output shape is adapted so that the input array is contained completely in the output. Default is True.

output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
order	[int, optional] The order of the spline interpolation, default is 3. The order has to be in the range 0-5.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the input array is extended beyond its boundaries. Default is 'constant'. Behavior for each valid value is as follows (see additional plots and details on boundary modes): 'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric. 'grid-mirror' This is a synonym for 'reflect'. 'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. No interpolation is performed beyond the edges of the input. 'grid-constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. Interpolation occurs for samples outside the input's extent as well. 'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel. 'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric. 'grid-wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge. 'wrap' (<i>d b c d a b c d b c a b</i>) The input is extended by wrapping around to the opposite edge, but in a way such that the last point and initial point exactly overlap. In this case it is not well defined which sample will be chosen at the point of overlap.
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
prefilter	[bool, optional] Determines if the input array is prefiltered with spline_filter before interpolation. The default is True, which will create a temporary <i>float64</i> array of filtered values if <i>order</i> > 1. If setting this to False, the output will be slightly blurred if <i>order</i> > 1, unless the input is prefiltered, i.e. it is the result of calling spline_filter on the original input.

Returns

rotate [ndarray] The rotated input.

Notes

For complex-valued *input*, this function rotates the real and imaginary components independently.



New in version 1.6.0: Complex-valued support added.

Examples

```

>>> from scipy import ndimage, misc
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure(figsize=(10, 3))
>>> ax1, ax2, ax3 = fig.subplots(1, 3)
>>> img = misc.ascent()
>>> img_45 = ndimage.rotate(img, 45, reshape=False)
>>> full_img_45 = ndimage.rotate(img, 45, reshape=True)
>>> ax1.imshow(img, cmap='gray')
>>> ax1.set_axis_off()
>>> ax2.imshow(img_45, cmap='gray')
>>> ax2.set_axis_off()
>>> ax3.imshow(full_img_45, cmap='gray')
>>> ax3.set_axis_off()
>>> fig.set_tight_layout(True)
>>> plt.show()

```



```

>>> print(img.shape)
(512, 512)
>>> print(img_45.shape)
(512, 512)
>>> print(full_img_45.shape)
(724, 724)

```

scipy.ndimage.shift

`scipy.ndimage.shift` (*input, shift, output=None, order=3, mode='constant', cval=0.0, prefilter=True*)
Shift an array.

The array is shifted using spline interpolation of the requested order. Points outside the boundaries of the input are filled according to the given mode.

Parameters

- input** [array_like] The input array.
- shift** [float or sequence] The shift along the axes. If a float, *shift* is the same for each axis. If a sequence, *shift* should contain one value for each axis.
- output** [array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.

order	[int, optional] The order of the spline interpolation, default is 3. The order has to be in the range 0-5.
mode	<p>[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the input array is extended beyond its boundaries. Default is 'constant'. Behavior for each valid value is as follows (see additional plots and details on <i>boundary modes</i>):</p> <p>'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.</p> <p>'grid-mirror' This is a synonym for 'reflect'.</p> <p>'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. No interpolation is performed beyond the edges of the input.</p> <p>'grid-constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. Interpolation occurs for samples outside the input's extent as well.</p> <p>'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel.</p> <p>'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.</p> <p>'grid-wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge.</p> <p>'wrap' (<i>d b c d a b c d b c a b</i>) The input is extended by wrapping around to the opposite edge, but in a way such that the last point and initial point exactly overlap. In this case it is not well defined which sample will be chosen at the point of overlap.</p>
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
prefilter	[bool, optional] Determines if the input array is prefiltered with <i>spline_filter</i> before interpolation. The default is True, which will create a temporary <i>float64</i> array of filtered values if <i>order</i> > 1. If setting this to False, the output will be slightly blurred if <i>order</i> > 1, unless the input is prefiltered, i.e. it is the result of calling <i>spline_filter</i> on the original input.
Returns	
shift	[ndarray] The shifted input.

Notes

For complex-valued *input*, this function shifts the real and imaginary components independently.

New in version 1.6.0: Complex-valued support added.

scipy.ndimage.spline_filter

`scipy.ndimage.spline_filter` (*input*, *order*=3, *output*=<class 'numpy.float64'>, *mode*='mirror')

Multidimensional spline filter.

For more details, see [*spline_filter1d*](#).

See also:

[*spline_filter1d*](#)

Calculate a 1-D spline filter along the given axis.

Notes

The multidimensional filter is implemented as a sequence of 1-D spline filters. The intermediate arrays are stored in the same data type as the output. Therefore, for output types with a limited precision, the results may be imprecise because intermediate results may be stored with insufficient precision.

For complex-valued *input*, this function processes the real and imaginary components independently.

New in version 1.6.0: Complex-valued support added.

Examples

We can filter an image using multidimensional splines:

```
>>> from scipy.ndimage import spline_filter
>>> import matplotlib.pyplot as plt
>>> orig_img = np.eye(20) # create an image
>>> orig_img[10, :] = 1.0
>>> sp_filter = spline_filter(orig_img, order=3)
>>> f, ax = plt.subplots(1, 2, sharex=True)
>>> for ind, data in enumerate([[orig_img, "original image"],
...                             [sp_filter, "spline filter"]]):
...     ax[ind].imshow(data[0], cmap='gray_r')
...     ax[ind].set_title(data[1])
>>> plt.tight_layout()
>>> plt.show()
```

scipy.ndimage.spline_filter1d


`scipy.ndimage.spline_filter1d` (*input*, *order*=3, *axis*=-1, *output*=<class 'numpy.float64'>, *mode*='mirror')

Calculate a 1-D spline filter along the given axis.

The lines of the array along the given axis are filtered by a spline filter. The order of the spline must be ≥ 2 and ≤ 5 .

Parameters

input	[array_like] The input array.
order	[int, optional] The order of the spline, default is 3.
axis	[int, optional] The axis along which the spline filter is applied. Default is the last axis.
output	[ndarray or dtype, optional] The array in which to place the output, or the dtype of the returned array. Default is <code>numpy.float64</code> .



- mode** [{"reflect", "constant", "nearest", "mirror", "wrap"}], optional] The *mode* parameter determines how the input array is extended beyond its boundaries. Default is 'mirror'. Behavior for each valid value is as follows (see additional plots and details on *boundary modes*):
- 'reflect'** (*d c b a | a b c d | d c b a*)
The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric.
 - 'grid-mirror'**
This is a synonym for 'reflect'.
 - 'constant'** (*k k k k | a b c d | k k k k*)
The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter. No interpolation is performed beyond the edges of the input.
 - 'grid-constant'** (*k k k k | a b c d | k k k k*)
The input is extended by filling all values beyond the edge with the same constant value, defined by the *cval* parameter. Interpolation occurs for samples outside the input's extent as well.
 - 'nearest'** (*a a a a | a b c d | d d d d*)
The input is extended by replicating the last pixel.
 - 'mirror'** (*d c b | a b c d | c b a*)
The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric.
 - 'grid-wrap'** (*a b c d | a b c d | a b c d*)
The input is extended by wrapping around to the opposite edge.
 - 'wrap'** (*d b c d | a b c d | b c a b*)
The input is extended by wrapping around to the opposite edge, but in a way such that the last point and initial point exactly overlap. In this case it is not well defined which sample will be chosen at the point of overlap.

Returns**spline_filter1d**

[ndarray] The filtered input.

See also:

spline_filter

Multidimensional spline filter.

Notes

All functions in `ndimage.interpolation` do spline interpolation of the input image. If using B-splines of *order* > 1, the input image values have to be converted to B-spline coefficients first, which is done by applying this 1-D filter sequentially along all axes of the input. All functions that require B-spline coefficients will automatically filter their inputs, a behavior controllable with the *prefilter* keyword argument. For functions that accept a *mode* parameter, the result will only be correct if it matches the *mode* used when filtering.


For complex-valued *input*, this function processes the real and imaginary components independently.

New in version 1.6.0: Complex-valued support added.

Examples

We can filter an image using 1-D spline along the given axis:

```
>>> from scipy.ndimage import spline_filter1d
>>> import matplotlib.pyplot as plt
>>> orig_img = np.eye(20) # create an image
>>> orig_img[10, :] = 1.0
>>> sp_filter_axis_0 = spline_filter1d(orig_img, axis=0)
>>> sp_filter_axis_1 = spline_filter1d(orig_img, axis=1)
>>> f, ax = plt.subplots(1, 3, sharex=True)
>>> for ind, data in enumerate([[orig_img, "original image"],
...                             [sp_filter_axis_0, "spline filter (axis=0)"],
...                             [sp_filter_axis_1, "spline filter (axis=1)"]]):
...     ax[ind].imshow(data[0], cmap='gray_r')
...     ax[ind].set_title(data[1])
>>> plt.tight_layout()
>>> plt.show()
```



scipy.ndimage.zoom


`scipy.ndimage.zoom` (*input*, *zoom*, *output=None*, *order=3*, *mode='constant'*, *cval=0.0*, *prefilter=True*, *, *grid_mode=False*)

Zoom an array.

The array is zoomed using spline interpolation of the requested order.

Parameters

input	[array_like] The input array.
zoom	[float or sequence] The zoom factor along the axes. If a float, <i>zoom</i> is the same for each axis. If a sequence, <i>zoom</i> should contain one value for each axis.
output	[array or dtype, optional] The array in which to place the output, or the dtype of the returned array. By default an array of the same dtype as input will be created.
order	[int, optional] The order of the spline interpolation, default is 3. The order has to be in the range 0-5.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the input array is extended beyond its boundaries. Default is 'constant'. Behavior for each valid value is as follows (see additional plots and details on <i>boundary modes</i>): 'reflect' (<i>d c b a a b c d d c b a</i>) The input is extended by reflecting about the edge of the last pixel. This mode is also sometimes referred to as half-sample symmetric. 'grid-mirror' This is a synonym for 'reflect'. 'constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. No interpolation is performed beyond the edges of the input. 'grid-constant' (<i>k k k k a b c d k k k k</i>) The input is extended by filling all values beyond the edge with the same constant value, defined by the <i>cval</i> parameter. Interpolation occurs for samples outside the input's extent as well. 'nearest' (<i>a a a a a b c d d d d d</i>) The input is extended by replicating the last pixel. 'mirror' (<i>d c b a b c d c b a</i>) The input is extended by reflecting about the center of the last pixel. This mode is also sometimes referred to as whole-sample symmetric. 'grid-wrap' (<i>a b c d a b c d a b c d</i>) The input is extended by wrapping around to the opposite edge. 'wrap' (<i>d b c d a b c d b c a b</i>) The input is extended by wrapping around to the opposite edge, but in a way such that the last point and initial point exactly overlap. In this case it is not well defined which sample will be chosen at the point of overlap.
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
prefilter	[bool, optional] Determines if the input array is prefiltered with <i>spline_filter</i> before interpolation. The default is True, which will create a temporary <i>float64</i> array of filtered values if <i>order</i> > 1. If setting this to False, the output will be slightly blurred if <i>order</i> > 1, unless the input is prefiltered, i.e. it is the result of calling <i>spline_filter</i> on the original input.
grid_mode	[bool, optional] If False, the distance from the pixel centers is zoomed. Otherwise, the distance including the full pixel extent is used. For example, a 1d signal of length 5 is considered to have length 4 when <i>grid_mode</i> is False, but length 5 when <i>grid_mode</i> is True. See the following visual illustration:



The starting point of the arrow in the diagram above corresponds to coordinate location 0 in each mode.

Returns

zoom [ndarray] The zoomed input.

Notes

For complex-valued *input*, this function zooms the real and imaginary components independently.

New in version 1.6.0: Complex-valued support added.

Examples

```


>>> from scipy import ndimage, misc
>>> import matplotlib.pyplot as plt

```

```

>>> fig = plt.figure()
>>> ax1 = fig.add_subplot(121) # left side
>>> ax2 = fig.add_subplot(122) # right side
>>> ascent = misc.ascent()
>>> result = ndimage.zoom(ascent, 3.0)
>>> ax1.imshow(ascent, vmin=0, vmax=255)
>>> ax2.imshow(result, vmin=0, vmax=255)
>>> plt.show()

```



```
>>> print (ascent.shape)
(512, 512)
```

```
>>> print (result.shape)
(1536, 1536)
```

6.17.4 Measurements

<code>center_of_mass(input[, labels, index])</code>	Calculate the center of mass of the values of an array at labels.
<code>extrema(input[, labels, index])</code>	Calculate the minimums and maximums of the values of an array at labels, along with their positions.
<code>find_objects(input[, max_label])</code>	Find objects in a labeled array.
<code>histogram(input, min, max, bins[, labels, index])</code>	Calculate the histogram of the values of an array, optionally at labels.
<code>label(input[, structure, output])</code>	Label features in an array.
<code>labeled_comprehension(input, labels, index, ...)</code>	Roughly equivalent to <code>[func(input[labels == i]) for i in index]</code> .
<code>maximum(input[, labels, index])</code>	Calculate the maximum of the values of an array over labeled regions.
<code>maximum_position(input[, labels, index])</code>	Find the positions of the maximums of the values of an array at labels.
<code>mean(input[, labels, index])</code>	Calculate the mean of the values of an array at labels.
<code>median(input[, labels, index])</code>	Calculate the median of the values of an array over labeled regions.
<code>minimum(input[, labels, index])</code>	Calculate the minimum of the values of an array over labeled regions.
<code>minimum_position(input[, labels, index])</code>	Find the positions of the minimums of the values of an array at labels.
<code>standard_deviation(input[, labels, index])</code>	Calculate the standard deviation of the values of an N-D image array, optionally at specified sub-regions.
<code>sum_labels(input[, labels, index])</code>	Calculate the sum of the values of the array.
<code>variance(input[, labels, index])</code>	Calculate the variance of the values of an N-D image array, optionally at specified sub-regions.
<code>watershed_ift(input, markers[, structure, ...])</code>	Apply watershed from markers using image foresting transform algorithm.

scipy.ndimage.center_of_mass

`scipy.ndimage.center_of_mass` (*input*, *labels=None*, *index=None*)

Calculate the center of mass of the values of an array at labels.

Parameters

input	[ndarray] Data from which to calculate center-of-mass. The masses can either be positive or negative.
labels	[ndarray, optional] Labels for objects in <i>input</i> , as generated by <i>ndimage.label</i> . Only used with <i>index</i> . Dimensions must be the same as <i>input</i> .
index	[int or sequence of ints, optional] Labels for which to calculate centers-of-mass. If not specified, all labels greater than zero are used. Only used with <i>labels</i> .

Returns**center_of_mass**

[tuple, or list of tuples] Coordinates of centers-of-mass.

Examples

```
>>> a = np.array([[0, 0, 0, 0],
...               [0, 1, 1, 0],
...               [0, 1, 1, 0],
...               [0, 1, 1, 0]])
>>> from scipy import ndimage
>>> ndimage.measurements.center_of_mass(a)
(2.0, 1.5)
```

Calculation of multiple objects in an image

```
>>> b = np.array([[0, 1, 1, 0],
...               [0, 1, 0, 0],
...               [0, 0, 0, 0],
...               [0, 0, 1, 1],
...               [0, 0, 1, 1]])
>>> lbl = ndimage.label(b)[0]
>>> ndimage.measurements.center_of_mass(b, lbl, [1, 2])
[(0.33333333333333331, 1.3333333333333333), (3.5, 2.5)]
```

Negative masses are also accepted, which can occur for example when bias is removed from measured data due to random noise.

```
>>> c = np.array([[-1, 0, 0, 0],
...               [0, -1, -1, 0],
...               [0, 1, -1, 0],
...               [0, 1, 1, 0]])
>>> ndimage.measurements.center_of_mass(c)
(-4.0, 1.0)
```

If there are division by zero issues, the function does not raise an error but rather issues a RuntimeWarning before returning inf and/or NaN.

```
>>> d = np.array([-1, 1])
>>> ndimage.measurements.center_of_mass(d)
(inf,)
```

scipy.ndimage.extrema

`scipy.ndimage.extrema` (*input*, *labels=None*, *index=None*)

Calculate the minimums and maximums of the values of an array at labels, along with their positions.

Parameters

input	[ndarray] N-D image data to process.
labels	[ndarray, optional] Labels of features in input. If not None, must be same shape as <i>input</i> .
index	[int or sequence of ints, optional] Labels to include in output. If None (default), all values where non-zero <i>labels</i> are used.

Returns**minimums, maximums**

[int or ndarray] Values of minimums and maximums in each feature.

min_positions, max_positions

[tuple or list of tuples] Each tuple gives the N-D coordinates of the corresponding minimum or maximum.

See also:

maximum, minimum, maximum_position, minimum_position, center_of_mass

Examples

```
>>> a = np.array([[1, 2, 0, 0],
...              [5, 3, 0, 4],
...              [0, 0, 0, 7],
...              [9, 3, 0, 0]])
>>> from scipy import ndimage
>>> ndimage.extrema(a)
(0, 9, (0, 2), (3, 0))
```

Features to process can be specified using *labels* and *index*:

```
>>> lbl, nlbl = ndimage.label(a)
>>> ndimage.extrema(a, lbl, index=np.arange(1, nlbl+1))
(array([1, 4, 3]),
 array([5, 7, 9]),
 [(0, 0), (1, 3), (3, 1)],
 [(1, 0), (2, 3), (3, 0)])
```

If no index is given, non-zero *labels* are processed:

```
>>> ndimage.extrema(a, lbl)
(1, 9, (0, 0), (3, 0))
```

scipy.ndimage.find_objects

`scipy.ndimage.find_objects` (*input*, *max_label=0*)

Find objects in a labeled array.

Parameters

input [ndarray of ints] Array containing objects defined by different labels. Labels with value 0 are ignored.

max_label [int, optional] Maximum label to be searched for in *input*. If *max_label* is not given, the positions of all objects are returned.

Returns**object_slices**

[list of tuples] A list of tuples, with each tuple containing N slices (with N the dimension of the input array). Slices correspond to the minimal parallelepiped that contains the object. If a number is missing, None is returned instead of a slice.

See also:

[*label*](#), [*center_of_mass*](#)

Notes

This function is very useful for isolating a volume of interest inside a 3-D array, that cannot be “seen through”.

Examples

```
>>> from scipy import ndimage
>>> a = np.zeros((6,6), dtype=int)
>>> a[2:4, 2:4] = 1
>>> a[4, 4] = 1
>>> a[:2, :3] = 2
>>> a[0, 5] = 3
>>> a
array([[2, 2, 2, 0, 0, 3],
       [2, 2, 2, 0, 0, 0],
       [0, 0, 1, 1, 0, 0],
       [0, 0, 1, 1, 0, 0],
       [0, 0, 0, 0, 1, 0],
       [0, 0, 0, 0, 0, 0]])
>>> ndimage.find_objects(a)
[(slice(2, 5, None), slice(2, 5, None)), (slice(0, 2, None), slice(0, 3, None)), (slice(0, 1, None), slice(5, 6, None))]
>>> ndimage.find_objects(a, max_label=2)
[(slice(2, 5, None), slice(2, 5, None)), (slice(0, 2, None), slice(0, 3, None))]
>>> ndimage.find_objects(a == 1, max_label=2)
[(slice(2, 5, None), slice(2, 5, None)), None]
```

```
>>> loc = ndimage.find_objects(a)[0]
>>> a[loc]
array([[1, 1, 0],
       [1, 1, 0],
       [0, 0, 1]])
```

scipy.ndimage.histogram

`scipy.ndimage.histogram` (*input*, *min*, *max*, *bins*, *labels=None*, *index=None*)

Calculate the histogram of the values of an array, optionally at labels.

Histogram calculates the frequency of values in an array within bins determined by *min*, *max*, and *bins*. The *labels* and *index* keywords can limit the scope of the histogram to specified sub-regions within the array.

Parameters

input	[array_like] Data for which to calculate histogram.
min, max	[int] Minimum and maximum values of range of histogram bins.
bins	[int] Number of bins.
labels	[array_like, optional] Labels for objects in <i>input</i> . If not None, must be same shape as <i>input</i> .

index [int or sequence of ints, optional] Label or labels for which to calculate histogram. If None, all values where label is greater than zero are used

Returns

hist [ndarray] Histogram counts.

Examples

```
>>> a = np.array([[ 0.    ,  0.2146,  0.5962,  0.    ],
...              [ 0.    ,  0.7778,  0.    ,  0.    ],
...              [ 0.    ,  0.    ,  0.    ,  0.    ],
...              [ 0.    ,  0.    ,  0.7181,  0.2787],
...              [ 0.    ,  0.    ,  0.6573,  0.3094]])
>>> from scipy import ndimage
>>> ndimage.measurements.histogram(a, 0, 1, 10)
array([13,  0,  2,  1,  0,  1,  1,  2,  0,  0])
```

With labels and no indices, non-zero elements are counted:

```
>>> lbl, nlbl = ndimage.label(a)
>>> ndimage.measurements.histogram(a, 0, 1, 10, lbl)
array([0, 0, 2, 1, 0, 1, 1, 2, 0, 0])
```

Indices can be used to count only certain objects:

```
>>> ndimage.measurements.histogram(a, 0, 1, 10, lbl, 2)
array([0, 0, 1, 1, 0, 0, 1, 1, 0, 0])
```

scipy.ndimage.label

`scipy.ndimage.label` (*input*, *structure=None*, *output=None*)

Label features in an array.

Parameters

input [array_like] An array-like object to be labeled. Any non-zero values in *input* are counted as features and zero values are considered the background.

structure [array_like, optional] A structuring element that defines feature connections. *structure* must be centrosymmetric (see Notes). If no structuring element is provided, one is automatically generated with a squared connectivity equal to one. That is, for a 2-D *input* array, the default structuring element is:

```
[[0, 1, 0],
 [1, 1, 1],
 [0, 1, 0]]
```

output [(None, data-type, array_like), optional] If *output* is a data type, it specifies the type of the resulting labeled feature array. If *output* is an array-like object, then *output* will be updated with the labeled features from this function. This function can operate in-place, by passing *output=**input*. Note that the output must be able to store the largest label, or this function will raise an Exception.

Returns

label [ndarray or int] An integer ndarray where each unique feature in *input* has a unique label in the returned array.

num_features [int] How many objects were found.
 If *output* is None, this function returns a tuple of (*labeled_array*, *num_features*).
 If *output* is a ndarray, then it will be updated with values in *labeled_array* and only *num_features* will be returned by this function.

See also:

find_objects

generate a list of slices for the labeled features (or objects); useful for finding features' position or dimensions

Notes

A centrosymmetric matrix is a matrix that is symmetric about the center. See [1] for more information.

The *structure* matrix must be centrosymmetric to ensure two-way connections. For instance, if the *structure* matrix is not centrosymmetric and is defined as:

```
[ [0, 1, 0],
  [1, 1, 0],
  [0, 0, 0]]
```

and the *input* is:

```
[ [1, 2],
  [0, 3]]
```

then the structure matrix would indicate the entry 2 in the input is connected to 1, but 1 is not connected to 2.

References

[1]

Examples

Create an image with some features, then label it using the default (cross-shaped) structuring element:

```
>>> from scipy.ndimage import label, generate_binary_structure
>>> a = np.array([[0, 0, 1, 1, 0, 0],
...              [0, 0, 0, 1, 0, 0],
...              [1, 1, 0, 0, 1, 0],
...              [0, 0, 0, 1, 0, 0]])
>>> labeled_array, num_features = label(a)
```

Each of the 4 features are labeled with a different integer:

```
>>> num_features
4
>>> labeled_array
array([[0, 0, 1, 1, 0, 0],
```

(continues on next page)

(continued from previous page)

```
[0, 0, 0, 1, 0, 0],
 [2, 2, 0, 0, 3, 0],
 [0, 0, 0, 4, 0, 0]]
```

Generate a structuring element that will consider features connected even if they touch diagonally:

```
>>> s = generate_binary_structure(2, 2)
```

or,

```
>>> s = [[1, 1, 1],
...       [1, 1, 1],
...       [1, 1, 1]]
```

Label the image using the new structuring element:

```
>>> labeled_array, num_features = label(a, structure=s)
```

Show the 2 labeled features (note that features 1, 3, and 4 from above are now considered a single feature):

```
>>> num_features
2
>>> labeled_array
array([[0, 0, 1, 1, 0, 0],
       [0, 0, 0, 1, 0, 0],
       [2, 2, 0, 0, 1, 0],
       [0, 0, 0, 1, 0, 0]])
```

scipy.ndimage.labeled_comprehension

`scipy.ndimage.labeled_comprehension` (*input*, *labels*, *index*, *func*, *out_dtype*, *default*, *pass_positions=False*)

Roughly equivalent to `[func(input[labels == i]) for i in index]`.

Sequentially applies an arbitrary function (that works on `array_like` input) to subsets of an N-D image array specified by *labels* and *index*. The option exists to provide the function with positional parameters as the second argument.

Parameters

input	[array_like] Data from which to select <i>labels</i> to process.
labels	[array_like or None] Labels to objects in <i>input</i> . If not None, array must be same shape as <i>input</i> . If None, <i>func</i> is applied to raveled <i>input</i> .
index	[int, sequence of ints or None] Subset of <i>labels</i> to which to apply <i>func</i> . If a scalar, a single value is returned. If None, <i>func</i> is applied to all non-zero values of <i>labels</i> .
func	[callable] Python function to apply to <i>labels</i> from <i>input</i> .
out_dtype	[dtype] Dtype to use for <i>result</i> .
default	[int, float or None] Default return value when a element of <i>index</i> does not exist in <i>labels</i> .
pass_positions	[bool, optional] If True, pass linear indices to <i>func</i> as a second argument. Default is False.

Returns

result [ndarray] Result of applying *func* to each of *labels* to *input* in *index*.

Examples

```
>>> a = np.array([[1, 2, 0, 0],
...              [5, 3, 0, 4],
...              [0, 0, 0, 7],
...              [9, 3, 0, 0]])
>>> from scipy import ndimage
>>> lbl, nlbl = ndimage.label(a)
>>> lbls = np.arange(1, nlbl+1)
>>> ndimage.labeled_comprehension(a, lbl, lbls, np.mean, float, 0)
array([ 2.75,  5.5 ,  6.  ])
```

Falling back to *default*:

```
>>> lbls = np.arange(1, nlbl+2)
>>> ndimage.labeled_comprehension(a, lbl, lbls, np.mean, float, -1)
array([ 2.75,  5.5 ,  6.  , -1.  ])
```

Passing positions:

```
>>> def fn(val, pos):
...     print("fn says: %s : %s" % (val, pos))
...     return (val.sum()) if (pos.sum() % 2 == 0) else (-val.sum())
...
>>> ndimage.labeled_comprehension(a, lbl, lbls, fn, float, 0, True)
fn says: [1 2 5 3] : [0 1 4 5]
fn says: [4 7] : [ 7 11]
fn says: [9 3] : [12 13]
array([ 11.,  11., -12.,  0.] )
```

scipy.ndimage.maximum

`scipy.ndimage.maximum` (*input*, *labels=None*, *index=None*)

Calculate the maximum of the values of an array over labeled regions.

Parameters

- input** [array_like] Array_like of values. For each region specified by *labels*, the maximal values of *input* over the region is computed.
- labels** [array_like, optional] An array of integers marking different regions over which the maximum value of *input* is to be computed. *labels* must have the same shape as *input*. If *labels* is not specified, the maximum over the whole array is returned.
- index** [array_like, optional] A list of region labels that are taken into account for computing the maxima. If *index* is *None*, the maximum over all elements where *labels* is non-zero is returned.

Returns

- output** [float or list of floats] List of maxima of *input* over the regions determined by *labels* and whose index is in *index*. If *index* or *labels* are not specified, a float is returned: the maximal value of *input* if *labels* is *None*, and the maximal value of elements where *labels* is greater than zero if *index* is *None*.

See also:

*label, minimum, median, maximum_position, extrema, sum, mean, variance
standard_deviation*

Notes

The function returns a Python list and not a NumPy array, use *np.array* to convert the list to an array.

Examples

```
>>> a = np.arange(16).reshape((4,4))
>>> a
array([[ 0,  1,  2,  3],
       [ 4,  5,  6,  7],
       [ 8,  9, 10, 11],
       [12, 13, 14, 15]])
>>> labels = np.zeros_like(a)
>>> labels[:2,:2] = 1
>>> labels[2:, 1:3] = 2
>>> labels
array([[1, 1, 0, 0],
       [1, 1, 0, 0],
       [0, 2, 2, 0],
       [0, 2, 2, 0]])
>>> from scipy import ndimage
>>> ndimage.maximum(a)
15.0
>>> ndimage.maximum(a, labels=labels, index=[1,2])
[5.0, 14.0]
>>> ndimage.maximum(a, labels=labels)
14.0
```

```
>>> b = np.array([[1, 2, 0, 0],
...              [5, 3, 0, 4],
...              [0, 0, 0, 7],
...              [9, 3, 0, 0]])
>>> labels, labels_nb = ndimage.label(b)
>>> labels
array([[1, 1, 0, 0],
       [1, 1, 0, 2],
       [0, 0, 0, 2],
       [3, 3, 0, 0]])
>>> ndimage.maximum(b, labels=labels, index=np.arange(1, labels_nb + 1))
[5.0, 7.0, 9.0]
```

scipy.ndimage.maximum_position

`scipy.ndimage.maximum_position` (*input*, *labels=None*, *index=None*)

Find the positions of the maximums of the values of an array at labels.

For each region specified by *labels*, the position of the maximum value of *input* within the region is returned.

Parameters

input	[array_like] Array_like of values.
labels	[array_like, optional] An array of integers marking different regions over which the position of the maximum value of <i>input</i> is to be computed. <i>labels</i> must have the same shape as <i>input</i> . If <i>labels</i> is not specified, the location of the first maximum over the whole array is returned. The <i>labels</i> argument only works when <i>index</i> is specified.
index	[array_like, optional] A list of region labels that are taken into account for finding the location of the maxima. If <i>index</i> is None, the first maximum over all elements where <i>labels</i> is non-zero is returned. The <i>index</i> argument only works when <i>labels</i> is specified.

Returns

output	[list of tuples of ints] List of tuples of ints that specify the location of maxima of <i>input</i> over the regions determined by <i>labels</i> and whose index is in <i>index</i> . If <i>index</i> or <i>labels</i> are not specified, a tuple of ints is returned specifying the location of the first maximal value of <i>input</i> .
---------------	--

See also:

label, *minimum*, *median*, *maximum_position*, *extrema*, *sum*, *mean*, *variance*
standard_deviation

Examples

```
>>> from scipy import ndimage
>>> a = np.array([[1, 2, 0, 0],
...              [5, 3, 0, 4],
...              [0, 0, 0, 7],
...              [9, 3, 0, 0]])
>>> ndimage.maximum_position(a)
(3, 0)
```

Features to process can be specified using *labels* and *index*:

```
>>> lbl = np.array([[0, 1, 2, 3],
...                 [0, 1, 2, 3],
...                 [0, 1, 2, 3],
...                 [0, 1, 2, 3]])
>>> ndimage.maximum_position(a, lbl, 1)
(1, 1)
```

If no index is given, non-zero *labels* are processed:

```
>>> ndimage.maximum_position(a, lbl)
(2, 3)
```

If there are no maxima, the position of the first element is returned:


```
>>> ndimage.maximum_position(a, lbl, 2)
(0, 2)
```

scipy.ndimage.mean

`scipy.ndimage.mean` (*input*, *labels=None*, *index=None*)

Calculate the mean of the values of an array at labels.

Parameters

- input** [array_like] Array on which to compute the mean of elements over distinct regions.
- labels** [array_like, optional] Array of labels of same shape, or broadcastable to the same shape as *input*. All elements sharing the same label form one region over which the mean of the elements is computed.
- index** [int or sequence of ints, optional] Labels of the objects over which the mean is to be computed. Default is None, in which case the mean for all values where label is greater than 0 is calculated.

Returns

- out** [list] Sequence of same length as *index*, with the mean of the different regions labeled by the labels in *index*.

See also:

[variance](#), [standard_deviation](#), [minimum](#), [maximum](#), [sum](#), [label](#)

Examples

```
>>> from scipy import ndimage
>>> a = np.arange(25).reshape((5,5))
>>> labels = np.zeros_like(a)
>>> labels[3:5,3:5] = 1
>>> index = np.unique(labels)
>>> labels
array([[0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0],
       [0, 0, 0, 1, 1],
       [0, 0, 0, 1, 1]])
>>> index
array([0, 1])
>>> ndimage.mean(a, labels=labels, index=index)
[10.285714285714286, 21.0]
```

scipy.ndimage.median

`scipy.ndimage.median` (*input*, *labels=None*, *index=None*)

Calculate the median of the values of an array over labeled regions.

Parameters

- input** [array_like] Array_like of values. For each region specified by *labels*, the median value of *input* over the region is computed.
- labels** [array_like, optional] An array_like of integers marking different regions over which the median value of *input* is to be computed. *labels* must have the same shape as *input*. If *labels* is not specified, the median over the whole array is returned.
- index** [array_like, optional] A list of region labels that are taken into account for computing the medians. If *index* is *None*, the median over all elements where *labels* is non-zero is returned.

Returns

- median** [float or list of floats] List of medians of *input* over the regions determined by *labels* and whose index is in *index*. If *index* or *labels* are not specified, a float is returned: the median value of *input* if *labels* is *None*, and the median value of elements where *labels* is greater than zero if *index* is *None*.

See also:

[*label*](#), [*minimum*](#), [*maximum*](#), [*extrema*](#), [*sum*](#), [*mean*](#), [*variance*](#), [*standard_deviation*](#)

Notes

The function returns a Python list and not a NumPy array, use *np.array* to convert the list to an array.

Examples

```
>>> from scipy import ndimage
>>> a = np.array([[1, 2, 0, 1],
...              [5, 3, 0, 4],
...              [0, 0, 0, 7],
...              [9, 3, 0, 0]])
>>> labels, labels_nb = ndimage.label(a)
>>> labels
array([[1, 1, 0, 2],
       [1, 1, 0, 2],
       [0, 0, 0, 2],
       [3, 3, 0, 0]])
>>> ndimage.median(a, labels=labels, index=np.arange(1, labels_nb + 1))
[2.5, 4.0, 6.0]
>>> ndimage.median(a)
1.0
>>> ndimage.median(a, labels=labels)
3.0
```

scipy.ndimage.minimum

`scipy.ndimage.minimum` (*input*, *labels=None*, *index=None*)

Calculate the minimum of the values of an array over labeled regions.

Parameters

- input** [array_like] Array_like of values. For each region specified by *labels*, the minimal values of *input* over the region is computed.
- labels** [array_like, optional] An array_like of integers marking different regions over which the minimum value of *input* is to be computed. *labels* must have the same shape as *input*. If *labels* is not specified, the minimum over the whole array is returned.
- index** [array_like, optional] A list of region labels that are taken into account for computing the minima. If *index* is *None*, the minimum over all elements where *labels* is non-zero is returned.

Returns

- minimum** [float or list of floats] List of minima of *input* over the regions determined by *labels* and whose index is in *index*. If *index* or *labels* are not specified, a float is returned: the minimal value of *input* if *labels* is *None*, and the minimal value of elements where *labels* is greater than zero if *index* is *None*.

See also:

[label](#), [maximum](#), [median](#), [minimum_position](#), [extrema](#), [sum](#), [mean](#), [variance](#)
[standard_deviation](#)

Notes

The function returns a Python list and not a NumPy array, use *np.array* to convert the list to an array.

Examples

```
>>> from scipy import ndimage
>>> a = np.array([[1, 2, 0, 0],
...              [5, 3, 0, 4],
...              [0, 0, 0, 7],
...              [9, 3, 0, 0]])
>>> labels, labels_nb = ndimage.label(a)
>>> labels
array([[1, 1, 0, 0],
       [1, 1, 0, 2],
       [0, 0, 0, 2],
       [3, 3, 0, 0]])
>>> ndimage.minimum(a, labels=labels, index=np.arange(1, labels_nb + 1))
[1.0, 4.0, 3.0]
>>> ndimage.minimum(a)
0.0
>>> ndimage.minimum(a, labels=labels)
1.0
```

scipy.ndimage.minimum_position

`scipy.ndimage.minimum_position` (*input*, *labels=None*, *index=None*)

Find the positions of the minimums of the values of an array at labels.

Parameters

input	[array_like] Array_like of values.
labels	[array_like, optional] An array of integers marking different regions over which the position of the minimum value of <i>input</i> is to be computed. <i>labels</i> must have the same shape as <i>input</i> . If <i>labels</i> is not specified, the location of the first minimum over the whole array is returned. The <i>labels</i> argument only works when <i>index</i> is specified.
index	[array_like, optional] A list of region labels that are taken into account for finding the location of the minima. If <i>index</i> is None, the first minimum over all elements where <i>labels</i> is non-zero is returned. The <i>index</i> argument only works when <i>labels</i> is specified.

Returns

output	[list of tuples of ints] Tuple of ints or list of tuples of ints that specify the location of minima of <i>input</i> over the regions determined by <i>labels</i> and whose index is in <i>index</i> . If <i>index</i> or <i>labels</i> are not specified, a tuple of ints is returned specifying the location of the first minimal value of <i>input</i> .
---------------	---

See also:

[label](#), [minimum](#), [median](#), [maximum_position](#), [extrema](#), [sum](#), [mean](#), [variance](#)
[standard_deviation](#)

Examples

```
>>> a = np.array([[10, 20, 30],
...              [40, 80, 100],
...              [1, 100, 200]])
>>> b = np.array([[1, 2, 0, 1],
...              [5, 3, 0, 4],
...              [0, 0, 0, 7],
...              [9, 3, 0, 0]])
```

```
>>> from scipy import ndimage
```

```
>>> ndimage.minimum_position(a)
(2, 0)
>>> ndimage.minimum_position(b)
(0, 2)
```

Features to process can be specified using *labels* and *index*:

```
>>> label, pos = ndimage.label(a)
>>> ndimage.minimum_position(a, label, index=np.arange(1, pos+1))
[(2, 0)]
```

```
>>> label, pos = ndimage.label(b)
>>> ndimage.minimum_position(b, label, index=np.arange(1, pos+1))
[(0, 0), (0, 3), (3, 1)]
```

scipy.ndimage.standard_deviation

`scipy.ndimage.standard_deviation` (*input*, *labels=None*, *index=None*)

Calculate the standard deviation of the values of an N-D image array, optionally at specified sub-regions.

Parameters

input [array_like] N-D image data to process.
labels [array_like, optional] Labels to identify sub-regions in *input*. If not None, must be same shape as *input*.
index [int or sequence of ints, optional] *labels* to include in output. If None (default), all values where *labels* is non-zero are used.

Returns

standard_deviation

[float or ndarray] Values of standard deviation, for each sub-region if *labels* and *index* are specified.

See also:

[label](#), [variance](#), [maximum](#), [minimum](#), [extrema](#)

Examples

```
>>> a = np.array([[1, 2, 0, 0],
...              [5, 3, 0, 4],
...              [0, 0, 0, 7],
...              [9, 3, 0, 0]])
>>> from scipy import ndimage
>>> ndimage.standard_deviation(a)
2.7585095613392387
```

Features to process can be specified using *labels* and *index*:

```
>>> lbl, nlbl = ndimage.label(a)
>>> ndimage.standard_deviation(a, lbl, index=np.arange(1, nlbl+1))
array([ 1.479,  1.5  ,  3.   ])
```

If no *index* is given, non-zero *labels* are processed:

```
>>> ndimage.standard_deviation(a, lbl)
2.4874685927665499
```

scipy.ndimage.sum_labels

`scipy.ndimage.sum_labels` (*input*, *labels=None*, *index=None*)

Calculate the sum of the values of the array.

Parameters

input	[array_like] Values of <i>input</i> inside the regions defined by <i>labels</i> are summed together.
labels	[array_like of ints, optional] Assign labels to the values of the array. Has to have the same shape as <i>input</i> .
index	[array_like, optional] A single label number or a sequence of label numbers of the objects to be measured.

Returns

sum	[ndarray or scalar] An array of the sums of values of <i>input</i> inside the regions defined by <i>labels</i> with the same shape as <i>index</i> . If 'index' is None or scalar, a scalar is returned.
------------	--

See also:

[mean](#), [median](#)

Examples

```
>>> from scipy import ndimage
>>> input = [0, 1, 2, 3]
>>> labels = [1, 1, 2, 2]
>>> ndimage.sum(input, labels, index=[1, 2])
[1.0, 5.0]
>>> ndimage.sum(input, labels, index=1)
1
>>> ndimage.sum(input, labels)
6
```

scipy.ndimage.variance

`scipy.ndimage.variance` (*input*, *labels=None*, *index=None*)

Calculate the variance of the values of an N-D image array, optionally at specified sub-regions.

Parameters

input	[array_like] Nd-image data to process.
labels	[array_like, optional] Labels defining sub-regions in <i>input</i> . If not None, must be same shape as <i>input</i> .
index	[int or sequence of ints, optional] <i>labels</i> to include in output. If None (default), all values where <i>labels</i> is non-zero are used.

Returns

variance	[float or ndarray] Values of variance, for each sub-region if <i>labels</i> and <i>index</i> are specified.
-----------------	---

See also:

[label](#), [standard_deviation](#), [maximum](#), [minimum](#), [extrema](#)

Examples

```
>>> a = np.array([[1, 2, 0, 0],
...               [5, 3, 0, 4],
...               [0, 0, 0, 7],
...               [9, 3, 0, 0]])
>>> from scipy import ndimage
>>> ndimage.variance(a)
7.609375
```

Features to process can be specified using *labels* and *index*:

```
>>> lbl, nlbl = ndimage.label(a)
>>> ndimage.variance(a, lbl, index=np.arange(1, nlbl+1))
array([ 2.1875,  2.25  ,  9.    ])
```

If no index is given, all non-zero *labels* are processed:

```
>>> ndimage.variance(a, lbl)
6.1875
```

scipy.ndimage.watershed_ift

`scipy.ndimage.watershed_ift` (*input*, *markers*, *structure=None*, *output=None*)

Apply watershed from markers using image foresting transform algorithm.

Parameters

- input** [array_like] Input.
- markers** [array_like] Markers are points within each watershed that form the beginning of the process. Negative markers are considered background markers which are processed after the other markers.
- structure** [structure element, optional] A structuring element defining the connectivity of the object can be provided. If None, an element is generated with a squared connectivity equal to one.
- output** [ndarray, optional] An output array can optionally be provided. The same shape as input.

Returns

- watershed_ift** [ndarray] Output. Same shape as *input*.

References

[1]

6.17.5 Morphology

<code>binary_closing(input[, structure, ...])</code>	Multidimensional binary closing with the given structuring element.
<code>binary_dilation(input[, structure, ...])</code>	Multidimensional binary dilation with the given structuring element.
<code>binary_erosion(input[, structure, ...])</code>	Multidimensional binary erosion with a given structuring element.
<code>binary_fill_holes(input[, structure, ...])</code>	Fill the holes in binary objects.
<code>binary_hit_or_miss(input[, structure1, ...])</code>	Multidimensional binary hit-or-miss transform.
<code>binary_opening(input[, structure, ...])</code>	Multidimensional binary opening with the given structuring element.
<code>binary_propagation(input[, structure, mask, ...])</code>	Multidimensional binary propagation with the given structuring element.
<code>black_tophat(input[, size, footprint, ...])</code>	Multidimensional black tophat filter.
<code>distance_transform_bf(input[, metric, ...])</code>	Distance transform function by a brute force algorithm.
<code>distance_transform_cdt(input[, metric, ...])</code>	Distance transform for chamfer type of transforms.
<code>distance_transform_edt(input[, sampling, ...])</code>	Exact Euclidean distance transform.
<code>generate_binary_structure(rank, connectivity)</code>	Generate a binary structure for binary morphological operations.
<code>grey_closing(input[, size, footprint, ...])</code>	Multidimensional grayscale closing.
<code>grey_dilation(input[, size, footprint, ...])</code>	Calculate a greyscale dilation, using either a structuring element, or a footprint corresponding to a flat structuring element.
<code>grey_erosion(input[, size, footprint, ...])</code>	Calculate a greyscale erosion, using either a structuring element, or a footprint corresponding to a flat structuring element.
<code>grey_opening(input[, size, footprint, ...])</code>	Multidimensional grayscale opening.
<code>iterate_structure(structure, iterations[, ...])</code>	Iterate a structure by dilating it with itself.
<code>morphological_gradient(input[, size, ...])</code>	Multidimensional morphological gradient.
<code>morphological_laplace(input[, size, ...])</code>	Multidimensional morphological laplace.
<code>white_tophat(input[, size, footprint, ...])</code>	Multidimensional white tophat filter.

scipy.ndimage.binary_closing

`scipy.ndimage.binary_closing(input, structure=None, iterations=1, output=None, origin=0, mask=None, border_value=0, brute_force=False)`

Multidimensional binary closing with the given structuring element.

The *closing* of an input image by a structuring element is the *erosion* of the *dilation* of the image by the structuring element.

Parameters

- input** [array_like] Binary array_like to be closed. Non-zero (True) elements form the subset to be closed.
- structure** [array_like, optional] Structuring element used for the closing. Non-zero elements are considered True. If no structuring element is provided an element is generated with a square connectivity equal to one (i.e., only nearest neighbors are connected to the center, diagonally-connected elements are not considered neighbors).
- iterations** [int, optional] The dilation step of the closing, then the erosion step are each repeated *iterations* times (one, by default). If iterations is less than 1, each operations is repeated until the result does not change anymore. Only an integer of iterations is accepted.

output [ndarray, optional] Array of the same shape as input, into which the output is placed. By default, a new array is created.

origin [int or tuple of ints, optional] Placement of the filter, by default 0.

mask [array_like, optional] If a mask is given, only those elements with a True value at the corresponding mask element are modified at each iteration.
New in version 1.1.0.

border_value [int (cast to 0 or 1), optional] Value at the border in the output array.
New in version 1.1.0.

brute_force [boolean, optional] Memory condition: if False, only the pixels whose value was changed in the last iteration are tracked as candidates to be updated in the current iteration; if true all pixels are considered as candidates for update, regardless of what happened in the previous iteration. False by default.
New in version 1.1.0.

Returns

binary_closing [ndarray of bools] Closing of the input by the structuring element.

See also:

[*grey_closing*](#), [*binary_opening*](#), [*binary_dilation*](#), [*binary_erosion*](#)
[*generate_binary_structure*](#)

Notes

Closing [1] is a mathematical morphology operation [2] that consists in the succession of a dilation and an erosion of the input with the same structuring element. Closing therefore fills holes smaller than the structuring element.

Together with *opening* ([*binary_opening*](#)), closing can be used for noise removal.

References

[1], [2]

Examples

```
>>> from scipy import ndimage
>>> a = np.zeros((5,5), dtype=int)
>>> a[1:-1, 1:-1] = 1; a[2,2] = 0
>>> a
array([[0, 0, 0, 0, 0],
       [0, 1, 1, 1, 0],
       [0, 1, 0, 1, 0],
       [0, 1, 1, 1, 0],
       [0, 0, 0, 0, 0]])
>>> # Closing removes small holes
>>> ndimage.binary_closing(a).astype(int)
array([[0, 0, 0, 0, 0],
       [0, 1, 1, 1, 0],
```

(continues on next page)

(continued from previous page)

```

    [0, 1, 1, 1, 0],
    [0, 1, 1, 1, 0],
    [0, 0, 0, 0, 0]])
>>> # Closing is the erosion of the dilation of the input
>>> ndimage.binary_dilation(a).astype(int)
array([[0, 1, 1, 1, 0],
       [1, 1, 1, 1, 1],
       [1, 1, 1, 1, 1],
       [1, 1, 1, 1, 1],
       [0, 1, 1, 1, 0]])
>>> ndimage.binary_erosion(ndimage.binary_dilation(a)).astype(int)
array([[0, 0, 0, 0, 0],
       [0, 1, 1, 1, 0],
       [0, 1, 1, 1, 0],
       [0, 1, 1, 1, 0],
       [0, 0, 0, 0, 0]])

```

```

>>> a = np.zeros((7,7), dtype=int)
>>> a[1:6, 2:5] = 1; a[1:3,3] = 0
>>> a
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 0, 1, 0, 1, 0, 0],
       [0, 0, 1, 0, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 0, 0, 0, 0, 0]])
>>> # In addition to removing holes, closing can also
>>> # coarsen boundaries with fine hollows.
>>> ndimage.binary_closing(a).astype(int)
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 0, 1, 0, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 0, 0, 0, 0, 0]])
>>> ndimage.binary_closing(a, structure=np.ones((2,2))).astype(int)
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 0, 0, 0, 0, 0]])

```

scipy.ndimage.binary_dilation

`scipy.ndimage.binary_dilation` (*input, structure=None, iterations=1, mask=None, output=None, border_value=0, origin=0, brute_force=False*)

Multidimensional binary dilation with the given structuring element.

Parameters

- input** [array_like] Binary array_like to be dilated. Non-zero (True) elements form the subset to be dilated.
- structure** [array_like, optional] Structuring element used for the dilation. Non-zero elements are considered True. If no structuring element is provided an element is generated with a square connectivity equal to one.
- iterations** [int, optional] The dilation is repeated *iterations* times (one, by default). If iterations is less than 1, the dilation is repeated until the result does not change anymore. Only an integer of iterations is accepted.
- mask** [array_like, optional] If a mask is given, only those elements with a True value at the corresponding mask element are modified at each iteration.
- output** [ndarray, optional] Array of the same shape as input, into which the output is placed. By default, a new array is created.
- border_value** [int (cast to 0 or 1), optional] Value at the border in the output array.
- origin** [int or tuple of ints, optional] Placement of the filter, by default 0.
- brute_force** [boolean, optional] Memory condition: if False, only the pixels whose value was changed in the last iteration are tracked as candidates to be updated (dilated) in the current iteration; if True all pixels are considered as candidates for dilation, regardless of what happened in the previous iteration. False by default.

Returns

- binary_dilation** [ndarray of bools] Dilation of the input by the structuring element.

See also:

*[grey_dilation](#), [binary_erosion](#), [binary_closing](#), [binary_opening](#)
[generate_binary_structure](#)*

Notes

Dilation [1] is a mathematical morphology operation [2] that uses a structuring element for expanding the shapes in an image. The binary dilation of an image by a structuring element is the locus of the points covered by the structuring element, when its center lies within the non-zero points of the image.

References

[1], [2]

Examples

```

>>> from scipy import ndimage
>>> a = np.zeros((5, 5))
>>> a[2, 2] = 1
>>> a
array([[ 0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.]])
>>> ndimage.binary_dilation(a)
array([[False, False, False, False, False],
       [False, False,  True, False, False],
       [False,  True,  True,  True, False],
       [False, False,  True, False, False],
       [False, False, False, False, False]], dtype=bool)
>>> ndimage.binary_dilation(a).astype(a.dtype)
array([[ 0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  1.,  1.,  1.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.]])
>>> # 3x3 structuring element with connectivity 1, used by default
>>> struct1 = ndimage.generate_binary_structure(2, 1)
>>> struct1
array([[False,  True, False],
       [ True,  True,  True],
       [False,  True, False]], dtype=bool)
>>> # 3x3 structuring element with connectivity 2
>>> struct2 = ndimage.generate_binary_structure(2, 2)
>>> struct2
array([[ True,  True,  True],
       [ True,  True,  True],
       [ True,  True,  True]], dtype=bool)
>>> ndimage.binary_dilation(a, structure=struct1).astype(a.dtype)
array([[ 0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  1.,  1.,  1.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.]])
>>> ndimage.binary_dilation(a, structure=struct2).astype(a.dtype)
array([[ 0.,  0.,  0.,  0.,  0.],
       [ 0.,  1.,  1.,  1.,  0.],
       [ 0.,  1.,  1.,  1.,  0.],
       [ 0.,  1.,  1.,  1.,  0.],
       [ 0.,  0.,  0.,  0.,  0.]])
>>> ndimage.binary_dilation(a, structure=struct1, \

```

(continues on next page)

(continued from previous page)

```

... iterations=2).astype(a.dtype)
array([[ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  1.,  1.,  1.,  0.],
       [ 1.,  1.,  1.,  1.,  1.],
       [ 0.,  1.,  1.,  1.,  0.],
       [ 0.,  0.,  1.,  0.,  0.]])

```

scipy.ndimage.binary_erosion

`scipy.ndimage.binary_erosion` (*input*, *structure=None*, *iterations=1*, *mask=None*, *output=None*, *border_value=0*, *origin=0*, *brute_force=False*)

Multidimensional binary erosion with a given structuring element.

Binary erosion is a mathematical morphology operation used for image processing.

Parameters

- input** [array_like] Binary image to be eroded. Non-zero (True) elements form the subset to be eroded.
- structure** [array_like, optional] Structuring element used for the erosion. Non-zero elements are considered True. If no structuring element is provided, an element is generated with a square connectivity equal to one.
- iterations** [int, optional] The erosion is repeated *iterations* times (one, by default). If iterations is less than 1, the erosion is repeated until the result does not change anymore.
- mask** [array_like, optional] If a mask is given, only those elements with a True value at the corresponding mask element are modified at each iteration.
- output** [ndarray, optional] Array of the same shape as input, into which the output is placed. By default, a new array is created.
- border_value** [int (cast to 0 or 1), optional] Value at the border in the output array.
- origin** [int or tuple of ints, optional] Placement of the filter, by default 0.
- brute_force** [boolean, optional] Memory condition: if False, only the pixels whose value was changed in the last iteration are tracked as candidates to be updated (eroded) in the current iteration; if True all pixels are considered as candidates for erosion, regardless of what happened in the previous iteration. False by default.

Returns

- binary_erosion** [ndarray of bools] Erosion of the input by the structuring element.

See also:

[*grey_erosion*](#), [*binary_dilation*](#), [*binary_closing*](#), [*binary_opening*](#)
[*generate_binary_structure*](#)

Notes

Erosion [1] is a mathematical morphology operation [2] that uses a structuring element for shrinking the shapes in an image. The binary erosion of an image by a structuring element is the locus of the points where a superimposition of the structuring element centered on the point is entirely contained in the set of non-zero elements of the image.

References

[1], [2]

Examples

```
>>> from scipy import ndimage
>>> a = np.zeros((7,7), dtype=int)
>>> a[1:6, 2:5] = 1
>>> a
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 0, 0, 0, 0, 0]])
>>> ndimage.binary_erosion(a).astype(a.dtype)
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 1, 0, 0, 0],
       [0, 0, 0, 1, 0, 0, 0],
       [0, 0, 0, 1, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0]])
>>> #Erosion removes objects smaller than the structure
>>> ndimage.binary_erosion(a, structure=np.ones((5,5))).astype(a.dtype)
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0]])
```

scipy.ndimage.binary_fill_holes

`scipy.ndimage.binary_fill_holes` (*input*, *structure=None*, *output=None*, *origin=0*)
Fill the holes in binary objects.

Parameters

input [array_like] N-D binary array with holes to be filled
structure [array_like, optional] Structuring element used in the computation; large-size elements make computations faster but may miss holes separated from the background by thin regions. The

default element (with a square connectivity equal to one) yields the intuitive result where all holes in the input have been filled.

output [ndarray, optional] Array of the same shape as input, into which the output is placed. By default, a new array is created.

origin [int, tuple of ints, optional] Position of the structuring element.

Returns

out [ndarray] Transformation of the initial image *input* where holes have been filled.

See also:

[*binary_dilation*](#), [*binary_propagation*](#), [*label*](#)

Notes

The algorithm used in this function consists in invading the complementary of the shapes in *input* from the outer boundary of the image, using binary dilations. Holes are not connected to the boundary and are therefore not invaded. The result is the complementary subset of the invaded region.

References

[1]

Examples

```
>>> from scipy import ndimage
>>> a = np.zeros((5, 5), dtype=int)
>>> a[1:4, 1:4] = 1
>>> a[2,2] = 0
>>> a
array([[0, 0, 0, 0, 0],
       [0, 1, 1, 1, 0],
       [0, 1, 0, 1, 0],
       [0, 1, 1, 1, 0],
       [0, 0, 0, 0, 0]])
>>> ndimage.binary_fill_holes(a).astype(int)
array([[0, 0, 0, 0, 0],
       [0, 1, 1, 1, 0],
       [0, 1, 1, 1, 0],
       [0, 1, 1, 1, 0],
       [0, 0, 0, 0, 0]])
>>> # Too big structuring element
>>> ndimage.binary_fill_holes(a, structure=np.ones((5,5))).astype(int)
array([[0, 0, 0, 0, 0],
       [0, 1, 1, 1, 0],
       [0, 1, 0, 1, 0],
       [0, 1, 1, 1, 0],
       [0, 0, 0, 0, 0]])
```

scipy.ndimage.binary_hit_or_miss

`scipy.ndimage.binary_hit_or_miss` (*input*, *structure1*=None, *structure2*=None, *output*=None, *origin1*=0, *origin2*=None)

Multidimensional binary hit-or-miss transform.

The hit-or-miss transform finds the locations of a given pattern inside the input image.

Parameters

- input** [array_like (cast to booleans)] Binary image where a pattern is to be detected.
- structure1** [array_like (cast to booleans), optional] Part of the structuring element to be fitted to the foreground (non-zero elements) of *input*. If no value is provided, a structure of square connectivity 1 is chosen.
- structure2** [array_like (cast to booleans), optional] Second part of the structuring element that has to miss completely the foreground. If no value is provided, the complementary of *structure1* is taken.
- output** [ndarray, optional] Array of the same shape as input, into which the output is placed. By default, a new array is created.
- origin1** [int or tuple of ints, optional] Placement of the first part of the structuring element *structure1*, by default 0 for a centered structure.
- origin2** [int or tuple of ints, optional] Placement of the second part of the structuring element *structure2*, by default 0 for a centered structure. If a value is provided for *origin1* and not for *origin2*, then *origin2* is set to *origin1*.

Returns

- binary_hit_or_miss** [ndarray] Hit-or-miss transform of *input* with the given structuring element (*structure1*, *structure2*).

See also:

[*binary_erosion*](#)

References

[1]

Examples

```
>>> from scipy import ndimage
>>> a = np.zeros((7,7), dtype=int)
>>> a[1, 1] = 1; a[2:4, 2:4] = 1; a[4:6, 4:6] = 1
>>> a
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 1, 0, 0, 0, 0, 0],
       [0, 0, 1, 1, 0, 0, 0],
       [0, 0, 1, 1, 0, 0, 0],
       [0, 0, 0, 0, 1, 1, 0],
       [0, 0, 0, 0, 1, 1, 0],
       [0, 0, 0, 0, 0, 0, 0]])
>>> structure1 = np.array([[1, 0, 0], [0, 1, 1], [0, 1, 1]])
>>> structure1
```

(continues on next page)

(continued from previous page)

```

array([[1, 0, 0],
       [0, 1, 1],
       [0, 1, 1]])
>>> # Find the matches of structure1 in the array a
>>> ndimage.binary_hit_or_miss(a, structure1=structure1).astype(int)
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 1, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 1, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0]])
>>> # Change the origin of the filter
>>> # origin1=1 is equivalent to origin1=(1,1) here
>>> ndimage.binary_hit_or_miss(a, structure1=structure1, \
... origin1=1).astype(int)
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 1, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 1, 0],
       [0, 0, 0, 0, 0, 0, 0]])

```

scipy.ndimage.binary_opening

`scipy.ndimage.binary_opening` (*input*, *structure=None*, *iterations=1*, *output=None*, *origin=0*, *mask=None*, *border_value=0*, *brute_force=False*)

Multidimensional binary opening with the given structuring element.

The *opening* of an input image by a structuring element is the *dilation* of the *erosion* of the image by the structuring element.

Parameters

- input** [array_like] Binary array_like to be opened. Non-zero (True) elements form the subset to be opened.
- structure** [array_like, optional] Structuring element used for the opening. Non-zero elements are considered True. If no structuring element is provided an element is generated with a square connectivity equal to one (i.e., only nearest neighbors are connected to the center, diagonally-connected elements are not considered neighbors).
- iterations** [int, optional] The erosion step of the opening, then the dilation step are each repeated *iterations* times (one, by default). If *iterations* is less than 1, each operation is repeated until the result does not change anymore. Only an integer of iterations is accepted.
- output** [ndarray, optional] Array of the same shape as input, into which the output is placed. By default, a new array is created.
- origin** [int or tuple of ints, optional] Placement of the filter, by default 0.
- mask** [array_like, optional] If a mask is given, only those elements with a True value at the corresponding mask element are modified at each iteration.
New in version 1.1.0.
- border_value** [int (cast to 0 or 1), optional] Value at the border in the output array.
New in version 1.1.0.

brute_force

[boolean, optional] Memory condition: if False, only the pixels whose value was changed in the last iteration are tracked as candidates to be updated in the current iteration; if true all pixels are considered as candidates for update, regardless of what happened in the previous iteration. False by default.

New in version 1.1.0.

Returns**binary_opening**

[ndarray of bools] Opening of the input by the structuring element.

See also:

grey_opening, *binary_closing*, *binary_erosion*, *binary_dilation*
generate_binary_structure

Notes

Opening [1] is a mathematical morphology operation [2] that consists in the succession of an erosion and a dilation of the input with the same structuring element. Opening, therefore, removes objects smaller than the structuring element.

Together with *closing* (*binary_closing*), opening can be used for noise removal.

References

[1], [2]

Examples

```
>>> from scipy import ndimage
>>> a = np.zeros((5,5), dtype=int)
>>> a[1:4, 1:4] = 1; a[4, 4] = 1
>>> a
array([[0, 0, 0, 0, 0],
       [0, 1, 1, 1, 0],
       [0, 1, 1, 1, 0],
       [0, 1, 1, 1, 0],
       [0, 0, 0, 0, 1]])
>>> # Opening removes small objects
>>> ndimage.binary_opening(a, structure=np.ones((3,3))).astype(int)
array([[0, 0, 0, 0, 0],
       [0, 1, 1, 1, 0],
       [0, 1, 1, 1, 0],
       [0, 1, 1, 1, 0],
       [0, 0, 0, 0, 0]])
>>> # Opening can also smooth corners
>>> ndimage.binary_opening(a).astype(int)
array([[0, 0, 0, 0, 0],
       [0, 0, 1, 0, 0],
       [0, 1, 1, 1, 0],
```

(continues on next page)

(continued from previous page)

```

    [0, 0, 1, 0, 0],
    [0, 0, 0, 0, 0]])
>>> # Opening is the dilation of the erosion of the input
>>> ndimage.binary_erosion(a).astype(int)
array([[0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0],
       [0, 0, 1, 0, 0],
       [0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0]])
>>> ndimage.binary_dilation(ndimage.binary_erosion(a)).astype(int)
array([[0, 0, 0, 0, 0],
       [0, 0, 1, 0, 0],
       [0, 1, 1, 1, 0],
       [0, 0, 1, 0, 0],
       [0, 0, 0, 0, 0]])

```

scipy.ndimage.binary_propagation

`scipy.ndimage.binary_propagation` (*input*, *structure=None*, *mask=None*, *output=None*, *border_value=0*, *origin=0*)
 Multidimensional binary propagation with the given structuring element.

Parameters

- input** [array_like] Binary image to be propagated inside *mask*.
- structure** [array_like, optional] Structuring element used in the successive dilations. The output may depend on the structuring element, especially if *mask* has several connex components. If no structuring element is provided, an element is generated with a squared connectivity equal to one.
- mask** [array_like, optional] Binary mask defining the region into which *input* is allowed to propagate.
- output** [ndarray, optional] Array of the same shape as *input*, into which the output is placed. By default, a new array is created.
- border_value** [int (cast to 0 or 1), optional] Value at the border in the output array.
- origin** [int or tuple of ints, optional] Placement of the filter, by default 0.

Returns

- binary_propagation** [ndarray] Binary propagation of *input* inside *mask*.

Notes

This function is functionally equivalent to calling `binary_dilation` with the number of iterations less than one: iterative dilation until the result does not change anymore.

The succession of an erosion and propagation inside the original image can be used instead of an *opening* for deleting small objects while keeping the contours of larger objects untouched.

References

[1], [2]

Examples

```

>>> from scipy import ndimage
>>> input = np.zeros((8, 8), dtype=int)
>>> input[2, 2] = 1
>>> mask = np.zeros((8, 8), dtype=int)
>>> mask[1:4, 1:4] = mask[4, 4] = mask[6:8, 6:8] = 1
>>> input
array([[0, 0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0, 0],
       [0, 0, 1, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0, 0]])
>>> mask
array([[0, 0, 0, 0, 0, 0, 0, 0],
       [0, 1, 1, 1, 0, 0, 0, 0],
       [0, 1, 1, 1, 0, 0, 0, 0],
       [0, 1, 1, 1, 0, 0, 0, 0],
       [0, 0, 0, 0, 1, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 1, 1],
       [0, 0, 0, 0, 0, 0, 1, 1]])
>>> ndimage.binary_propagation(input, mask=mask).astype(int)
array([[0, 0, 0, 0, 0, 0, 0, 0],
       [0, 1, 1, 1, 0, 0, 0, 0],
       [0, 1, 1, 1, 0, 0, 0, 0],
       [0, 1, 1, 1, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0, 0]])
>>> ndimage.binary_propagation(input, mask=mask, \
... structure=np.ones((3,3)).astype(int))
array([[0, 0, 0, 0, 0, 0, 0, 0],
       [0, 1, 1, 1, 0, 0, 0, 0],
       [0, 1, 1, 1, 0, 0, 0, 0],
       [0, 1, 1, 1, 0, 0, 0, 0],
       [0, 0, 0, 0, 1, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0, 0]])

```

```

>>> # Comparison between opening and erosion+propagation
>>> a = np.zeros((6,6), dtype=int)
>>> a[2:5, 2:5] = 1; a[0, 0] = 1; a[5, 5] = 1

```

(continues on next page)

(continued from previous page)

```

>>> a
array([[1, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0],
       [0, 0, 1, 1, 1, 0],
       [0, 0, 1, 1, 1, 0],
       [0, 0, 1, 1, 1, 0],
       [0, 0, 0, 0, 0, 1]])
>>> ndimage.binary_opening(a).astype(int)
array([[0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0],
       [0, 0, 0, 1, 0, 0],
       [0, 0, 1, 1, 1, 0],
       [0, 0, 0, 1, 0, 0],
       [0, 0, 0, 0, 0, 0]])
>>> b = ndimage.binary_erosion(a)
>>> b.astype(int)
array([[0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0],
       [0, 0, 0, 1, 0, 0],
       [0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0]])
>>> ndimage.binary_propagation(b, mask=a).astype(int)
array([[0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0],
       [0, 0, 1, 1, 1, 0],
       [0, 0, 1, 1, 1, 0],
       [0, 0, 1, 1, 1, 0],
       [0, 0, 0, 0, 0, 0]])

```

scipy.ndimage.black_tophat

`scipy.ndimage.black_tophat` (*input*, *size=None*, *footprint=None*, *structure=None*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Multidimensional black tophat filter.

Parameters

input	[array_like] Input.
size	[tuple of ints, optional] Shape of a flat and full structuring element used for the filter. Optional if <i>footprint</i> or <i>structure</i> is provided.
footprint	[array of ints, optional] Positions of non-infinite elements of a flat structuring element used for the black tophat filter.
structure	[array of ints, optional] Structuring element used for the filter. <i>structure</i> may be a non-flat structuring element.
output	[array, optional] An array used for storing the output of the filter may be provided.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the array borders are handled, where <i>cval</i> is the value when mode is equal to 'constant'. Default is 'reflect'
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
origin	[scalar, optional] The <i>origin</i> parameter controls the placement of the filter. Default 0

Returns

black_tophat

[ndarray] Result of the filter of *input* with *structure*.

See also:

white_tophat, *grey_opening*, *grey_closing*

scipy.ndimage.distance_transform_bf

```
scipy.ndimage.distance_transform_bf(input, metric='euclidean', sampling=None,
                                   return_distances=True, return_indices=False,
                                   distances=None, indices=None)
```

Distance transform function by a brute force algorithm.

This function calculates the distance transform of the *input*, by replacing each foreground (non-zero) element, with its shortest distance to the background (any zero-valued element).

In addition to the distance transform, the feature transform can be calculated. In this case the index of the closest background element to each foreground element is returned in a separate array.

Parameters

input [array_like] Input

metric [{‘euclidean’, ‘taxicab’, ‘chessboard’}, optional] ‘cityblock’ and ‘manhattan’ are also valid, and map to ‘taxicab’. The default is ‘euclidean’.

sampling [float, or sequence of float, optional] This parameter is only used when *metric* is ‘euclidean’. Spacing of elements along each dimension. If a sequence, must be of length equal to the input rank; if a single number, this is used for all axes. If not specified, a grid spacing of unity is implied.

return_distances [bool, optional] Whether to calculate the distance transform. Default is True.

return_indices [bool, optional] Whether to calculate the feature transform. Default is False.

distances [ndarray, optional] An output array to store the calculated distance transform, instead of returning it. This parameter is only used when *return_distances* is True. It must be the same shape as *input*, and of type float64 if *metric* is ‘euclidean’, uint32 otherwise.

indices [int32 ndarray, optional] An output array to store the calculated feature transform, instead of returning it. Its shape must be $(input.ndim,) + input.shape$.

Returns

distances [ndarray, optional] The calculated distance transform. Returned only when *return_distances* is True and *distances* is not supplied. It will have the same shape as the input array.

indices [int32 ndarray, optional] The calculated feature transform. It has an input-shaped array for each dimension of the input. See *distance_transform_edt* documentation for an example. Returned only when *return_indices* is True and *indices* is not supplied.

Notes

This function employs a slow brute force algorithm, see also the function `distance_transform_cdt` for more efficient taxicab and chessboard algorithms.

scipy.ndimage.distance_transform_cdt

`scipy.ndimage.distance_transform_cdt` (*input*, *metric*='chessboard', *return_distances*=True, *return_indices*=False, *distances*=None, *indices*=None)

Distance transform for chamfer type of transforms.

In addition to the distance transform, the feature transform can be calculated. In this case the index of the closest background element to each foreground element is returned in a separate array.

Parameters

input	[array_like] Input
metric	[{'chessboard', 'taxicab'} or array_like, optional] The <i>metric</i> determines the type of chamfering that is done. If the <i>metric</i> is equal to 'taxicab' a structure is generated using <code>generate_binary_structure</code> with a squared distance equal to 1. If the <i>metric</i> is equal to 'chessboard', a <i>metric</i> is generated using <code>generate_binary_structure</code> with a squared distance equal to the dimensionality of the array. These choices correspond to the common interpretations of the 'taxicab' and the 'chessboard' distance metrics in two dimensions. A custom metric may be provided, in the form of a matrix where each dimension has a length of three. 'cityblock' and 'manhattan' are also valid, and map to 'taxicab'. The default is 'chessboard'.
return_distances	[bool, optional] Whether to calculate the distance transform. Default is True.
return_indices	[bool, optional] Whether to calculate the feature transform. Default is False.
distances	[int32 ndarray, optional] An output array to store the calculated distance transform, instead of returning it. This parameter is only used when <i>return_distances</i> is True. It must be the same shape as <i>input</i> .
indices	[int32 ndarray, optional] An output array to store the calculated feature transform, instead of returning it. Its shape must be $(input.ndim,) + input.shape$.

Returns

distances	[int32 ndarray, optional] The calculated distance transform. Returned only when <i>return_distances</i> is True, and <i>distances</i> is not supplied. It will have the same shape as the input array.
indices	[int32 ndarray, optional] The calculated feature transform. It has an input-shaped array for each dimension of the input. See <code>distance_transform_edt</code> documentation for an example. Returned only when <i>return_indices</i> is True, and <i>indices</i> is not supplied.

scipy.ndimage.distance_transform_edt

`scipy.ndimage.distance_transform_edt` (*input*, *sampling*=None, *return_distances*=True, *return_indices*=False, *distances*=None, *indices*=None)

Exact Euclidean distance transform.

In addition to the distance transform, the feature transform can be calculated. In this case the index of the closest background element to each foreground element is returned in a separate array.

Parameters

input	[array_like] Input data to transform. Can be any type but will be converted into binary: 1 wherever input equates to True, 0 elsewhere.
--------------	---

- sampling** [float, or sequence of float, optional] Spacing of elements along each dimension. If a sequence, must be of length equal to the input rank; if a single number, this is used for all axes. If not specified, a grid spacing of unity is implied.
- return_distances** [bool, optional] Whether to calculate the distance transform. Default is True.
- return_indices** [bool, optional] Whether to calculate the feature transform. Default is False.
- distances** [float64 ndarray, optional] An output array to store the calculated distance transform, instead of returning it. This parameter is only used when *return_distances* is True. It must be the same shape as *input*.
- indices** [int32 ndarray, optional] An output array to store the calculated feature transform, instead of returning it. Its shape must be $(input.ndim,) + input.shape$.

Returns

- distances** [float64 ndarray, optional] The calculated distance transform. Returned only when *return_distances* is True and *distances* is not supplied. It will have the same shape as the input array.
- indices** [int32 ndarray, optional] The calculated feature transform. It has an input-shaped array for each dimension of the input. See example below. Returned only when *return_indices* is True and *indices* is not supplied.

Notes

The Euclidean distance transform gives values of the Euclidean distance:

$$y_i = \sqrt{\sum_i^n (x[i] - b[i])^2}$$

where $b[i]$ is the background point (value 0) with the smallest Euclidean distance to input points $x[i]$, and n is the number of dimensions.

Examples

```
>>> from scipy import ndimage
>>> a = np.array([[0,1,1,1,1],
...              [0,0,1,1,1],
...              [0,1,1,1,1],
...              [0,1,1,1,0],
...              [0,1,1,0,0]])
>>> ndimage.distance_transform_edt(a)
array([[ 0.    ,  1.    ,  1.4142,  2.2361,  3.    ],
       [ 0.    ,  0.    ,  1.    ,  2.    ,  2.    ],
       [ 0.    ,  1.    ,  1.4142,  1.4142,  1.    ],
       [ 0.    ,  1.    ,  1.4142,  1.    ,  0.    ],
       [ 0.    ,  1.    ,  1.    ,  0.    ,  0.    ]])
```

With a sampling of 2 units along x, 1 along y:

```
>>> ndimage.distance_transform_edt(a, sampling=[2,1])
array([[ 0.    ,  1.    ,  2.    ,  2.8284,  3.6056],
       [ 0.    ,  0.    ,  1.    ,  2.    ,  3.    ],
```

(continues on next page)

(continued from previous page)

```
[ 0.    ,  1.    ,  2.    ,  2.2361,  2.    ],
 [ 0.    ,  1.    ,  2.    ,  1.    ,  0.    ],
 [ 0.    ,  1.    ,  1.    ,  0.    ,  0.    ]])
```

Asking for indices as well:

```
>>> edt, inds = ndimage.distance_transform_edt(a, return_indices=True)
>>> inds
array([[0, 0, 1, 1, 3],
       [1, 1, 1, 1, 3],
       [2, 2, 1, 3, 3],
       [3, 3, 4, 4, 3],
       [4, 4, 4, 4, 4]],
      [[0, 0, 1, 1, 4],
       [0, 1, 1, 1, 4],
       [0, 0, 1, 4, 4],
       [0, 0, 3, 3, 4],
       [0, 0, 3, 3, 4]])
```

With arrays provided for inplace outputs:

```
>>> indices = np.zeros((np.ndim(a),) + a.shape, dtype=np.int32)
>>> ndimage.distance_transform_edt(a, return_indices=True,
↳ indices=indices)
array([[ 0.    ,  1.    ,  1.4142,  2.2361,  3.    ],
       [ 0.    ,  0.    ,  1.    ,  2.    ,  2.    ],
       [ 0.    ,  1.    ,  1.4142,  1.4142,  1.    ],
       [ 0.    ,  1.    ,  1.4142,  1.    ,  0.    ],
       [ 0.    ,  1.    ,  1.    ,  0.    ,  0.    ]])
>>> indices
array([[0, 0, 1, 1, 3],
       [1, 1, 1, 1, 3],
       [2, 2, 1, 3, 3],
       [3, 3, 4, 4, 3],
       [4, 4, 4, 4, 4]],
      [[0, 0, 1, 1, 4],
       [0, 1, 1, 1, 4],
       [0, 0, 1, 4, 4],
       [0, 0, 3, 3, 4],
       [0, 0, 3, 3, 4]])
```

scipy.ndimage.generate_binary_structure

`scipy.ndimage.generate_binary_structure` (*rank, connectivity*)

Generate a binary structure for binary morphological operations.

Parameters

rank [int] Number of dimensions of the array to which the structuring element will be applied, as returned by `np.ndim`.

connectivity

[int] *connectivity* determines which elements of the output array belong to the structure, i.e., are considered as neighbors of the central element. Elements up to a squared distance of

connectivity from the center are considered neighbors. *connectivity* may range from 1 (no diagonal elements are neighbors) to *rank* (all elements are neighbors).

Returns

output [ndarray of bools] Structuring element which may be used for binary morphological operations, with *rank* dimensions and all dimensions equal to 3.

See also:

[*iterate_structure*](#), [*binary_dilation*](#), [*binary_erosion*](#)

Notes

[*generate_binary_structure*](#) can only create structuring elements with dimensions equal to 3, i.e., minimal dimensions. For larger structuring elements, that are useful e.g., for eroding large objects, one may either use [*iterate_structure*](#), or create directly custom arrays with numpy functions such as `numpy.ones`.

Examples

```
>>> from scipy import ndimage
>>> struct = ndimage.generate_binary_structure(2, 1)
>>> struct
array([[False,  True, False],
       [ True,  True,  True],
       [False,  True, False]], dtype=bool)
>>> a = np.zeros((5,5))
>>> a[2, 2] = 1
>>> a
array([[ 0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.]])
>>> b = ndimage.binary_dilation(a, structure=struct).astype(a.dtype)
>>> b
array([[ 0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  1.,  1.,  1.,  0.],
       [ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  0.,  0.,  0.,  0.]])
>>> ndimage.binary_dilation(b, structure=struct).astype(a.dtype)
array([[ 0.,  0.,  1.,  0.,  0.],
       [ 0.,  1.,  1.,  1.,  0.],
       [ 1.,  1.,  1.,  1.,  1.],
       [ 0.,  1.,  1.,  1.,  0.],
       [ 0.,  0.,  1.,  0.,  0.]])
>>> struct = ndimage.generate_binary_structure(2, 2)
>>> struct
array([[ True,  True,  True],
       [ True,  True,  True],
       [ True,  True,  True]], dtype=bool)
>>> struct = ndimage.generate_binary_structure(3, 1)
```

(continues on next page)

(continued from previous page)

```
>>> struct # no diagonal elements
array([[False, False, False],
       [False, True, False],
       [False, False, False]],
       [[False, True, False],
        [ True, True, True],
        [False, True, False]],
       [[False, False, False],
        [False, True, False],
        [False, False, False]]], dtype=bool)
```

scipy.ndimage.grey_closing

`scipy.ndimage.grey_closing` (*input*, *size=None*, *footprint=None*, *structure=None*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Multidimensional grayscale closing.

A grayscale closing consists in the succession of a grayscale dilation, and a grayscale erosion.

Parameters

input	[array_like] Array over which the grayscale closing is to be computed.
size	[tuple of ints] Shape of a flat and full structuring element used for the grayscale closing. Optional if <i>footprint</i> or <i>structure</i> is provided.
footprint	[array of ints, optional] Positions of non-infinite elements of a flat structuring element used for the grayscale closing.
structure	[array of ints, optional] Structuring element used for the grayscale closing. <i>structure</i> may be a non-flat structuring element.
output	[array, optional] An array used for storing the output of the closing may be provided.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the array borders are handled, where <i>cval</i> is the value when mode is equal to 'constant'. Default is 'reflect'
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
origin	[scalar, optional] The <i>origin</i> parameter controls the placement of the filter. Default 0

Returns

grey_closing
[ndarray] Result of the grayscale closing of *input* with *structure*.

See also:

binary_closing, *grey_dilation*, *grey_erosion*, *grey_opening*
generate_binary_structure

Notes

The action of a grayscale closing with a flat structuring element amounts to smoothen deep local minima, whereas binary closing fills small holes.

References

[1]

Examples

```
>>> from scipy import ndimage
>>> a = np.arange(36).reshape((6,6))
>>> a[3,3] = 0
>>> a
array([[ 0,  1,  2,  3,  4,  5],
       [ 6,  7,  8,  9, 10, 11],
       [12, 13, 14, 15, 16, 17],
       [18, 19, 20,  0, 22, 23],
       [24, 25, 26, 27, 28, 29],
       [30, 31, 32, 33, 34, 35]])
>>> ndimage.grey_closing(a, size=(3,3))
array([[ 7,  7,  8,  9, 10, 11],
       [ 7,  7,  8,  9, 10, 11],
       [13, 13, 14, 15, 16, 17],
       [19, 19, 20, 20, 22, 23],
       [25, 25, 26, 27, 28, 29],
       [31, 31, 32, 33, 34, 35]])
>>> # Note that the local minimum a[3,3] has disappeared
```

scipy.ndimage.grey_dilation

`scipy.ndimage.grey_dilation` (*input*, *size=None*, *footprint=None*, *structure=None*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Calculate a grayscale dilation, using either a structuring element, or a footprint corresponding to a flat structuring element.

Grayscale dilation is a mathematical morphology operation. For the simple case of a full and flat structuring element, it can be viewed as a maximum filter over a sliding window.

Parameters

input	[array_like] Array over which the grayscale dilation is to be computed.
size	[tuple of ints] Shape of a flat and full structuring element used for the grayscale dilation. Optional if <i>footprint</i> or <i>structure</i> is provided.
footprint	[array of ints, optional] Positions of non-infinite elements of a flat structuring element used for the grayscale dilation. Non-zero values give the set of neighbors of the center over which the maximum is chosen.
structure	[array of ints, optional] Structuring element used for the grayscale dilation. <i>structure</i> may be a non-flat structuring element.
output	[array, optional] An array used for storing the output of the dilation may be provided.

mode [{"reflect", "constant", "nearest", "mirror", "wrap"}, optional] The *mode* parameter determines how the array borders are handled, where *cval* is the value when mode is equal to 'constant'. Default is 'reflect'

cval [scalar, optional] Value to fill past edges of input if *mode* is 'constant'. Default is 0.0.

origin [scalar, optional] The *origin* parameter controls the placement of the filter. Default 0

Returns

grey_dilation
[ndarray] Grayscale dilation of *input*.

See also:

binary_dilation, grey_erosion, grey_closing, grey_opening
generate_binary_structure, maximum_filter

Notes

The grayscale dilation of an image input by a structuring element *s* defined over a domain *E* is given by:

$$(\text{input}+s)(x) = \max \{ \text{input}(y) + s(x-y), \text{ for } y \text{ in } E \}$$

In particular, for structuring elements defined as $s(y) = 0$ for y in E , the grayscale dilation computes the maximum of the input image inside a sliding window defined by E .

Grayscale dilation [1] is a *mathematical morphology* operation [2].

References

[1], [2]

Examples

```
>>> from scipy import ndimage
>>> a = np.zeros((7,7), dtype=int)
>>> a[2:5, 2:5] = 1
>>> a[4,4] = 2; a[2,3] = 3
>>> a
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 1, 3, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 2, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0]])
>>> ndimage.grey_dilation(a, size=(3,3))
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 1, 3, 3, 3, 1, 0],
       [0, 1, 3, 3, 3, 1, 0],
       [0, 1, 3, 3, 3, 2, 0],
       [0, 1, 1, 2, 2, 2, 0],
       [0, 1, 1, 2, 2, 2, 0],
       [0, 0, 0, 0, 0, 0, 0]])
```

(continues on next page)

(continued from previous page)

```

>>> ndimage.grey_dilation(a, footprint=np.ones((3,3)))
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 1, 3, 3, 3, 1, 0],
       [0, 1, 3, 3, 3, 1, 0],
       [0, 1, 3, 3, 3, 2, 0],
       [0, 1, 1, 2, 2, 2, 0],
       [0, 1, 1, 2, 2, 2, 0],
       [0, 0, 0, 0, 0, 0, 0]])
>>> s = ndimage.generate_binary_structure(2,1)
>>> s
array([[False,  True, False],
       [ True,  True,  True],
       [False,  True, False]], dtype=bool)
>>> ndimage.grey_dilation(a, footprint=s)
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 0, 1, 3, 1, 0, 0],
       [0, 1, 3, 3, 3, 1, 0],
       [0, 1, 1, 3, 2, 1, 0],
       [0, 1, 1, 2, 2, 2, 0],
       [0, 0, 1, 1, 2, 0, 0],
       [0, 0, 0, 0, 0, 0, 0]])
>>> ndimage.grey_dilation(a, size=(3,3), structure=np.ones((3,3)))
array([[1, 1, 1, 1, 1, 1, 1],
       [1, 2, 4, 4, 4, 2, 1],
       [1, 2, 4, 4, 4, 2, 1],
       [1, 2, 4, 4, 4, 3, 1],
       [1, 2, 2, 3, 3, 3, 1],
       [1, 2, 2, 3, 3, 3, 1],
       [1, 1, 1, 1, 1, 1, 1]])

```

scipy.ndimage.grey_erosion

`scipy.ndimage.grey_erosion` (*input*, *size=None*, *footprint=None*, *structure=None*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Calculate a grayscale erosion, using either a structuring element, or a footprint corresponding to a flat structuring element.

Grayscale erosion is a mathematical morphology operation. For the simple case of a full and flat structuring element, it can be viewed as a minimum filter over a sliding window.

Parameters

input	[array_like] Array over which the grayscale erosion is to be computed.
size	[tuple of ints] Shape of a flat and full structuring element used for the grayscale erosion. Optional if <i>footprint</i> or <i>structure</i> is provided.
footprint	[array of ints, optional] Positions of non-infinite elements of a flat structuring element used for the grayscale erosion. Non-zero values give the set of neighbors of the center over which the minimum is chosen.
structure	[array of ints, optional] Structuring element used for the grayscale erosion. <i>structure</i> may be a non-flat structuring element.
output	[array, optional] An array used for storing the output of the erosion may be provided.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the array borders are handled, where <i>cval</i> is the value when mode is equal to 'constant'.

Default is 'reflect'
cval [scalar, optional] Value to fill past edges of input if *mode* is 'constant'. Default is 0.0.
origin [scalar, optional] The *origin* parameter controls the placement of the filter. Default 0

Returns

output [ndarray] Grayscale erosion of *input*.

See also:

[binary_erosion](#), [grey_dilation](#), [grey_opening](#), [grey_closing](#)
[generate_binary_structure](#), [minimum_filter](#)

Notes

The grayscale erosion of an image input by a structuring element s defined over a domain E is given by:

$$(\text{input}+s)(x) = \min \{ \text{input}(y) - s(x-y), \text{for } y \text{ in } E \}$$

In particular, for structuring elements defined as $s(y) = 0$ for y in E , the grayscale erosion computes the minimum of the input image inside a sliding window defined by E .

Grayscale erosion [1] is a *mathematical morphology* operation [2].

References

[1], [2]

Examples

```
>>> from scipy import ndimage
>>> a = np.zeros((7,7), dtype=int)
>>> a[1:6, 1:6] = 3
>>> a[4,4] = 2; a[2,3] = 1
>>> a
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 3, 3, 3, 3, 3, 0],
       [0, 3, 3, 1, 3, 3, 0],
       [0, 3, 3, 3, 3, 3, 0],
       [0, 3, 3, 3, 2, 3, 0],
       [0, 3, 3, 3, 3, 3, 0],
       [0, 0, 0, 0, 0, 0, 0]])
>>> ndimage.grey_erosion(a, size=(3,3))
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 3, 2, 2, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0]])
>>> footprint = ndimage.generate_binary_structure(2, 1)
>>> footprint
array([[False,  True,  False],
```

(continues on next page)

(continued from previous page)

```

    [ True,  True,  True],
    [False,  True, False]], dtype=bool)
>>> # Diagonally-connected elements are not considered neighbors
>>> ndimage.grey_erosion(a, size=(3,3), footprint=footprint)
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 3, 1, 2, 0, 0],
       [0, 0, 3, 2, 2, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0]])

```

scipy.ndimage.grey_opening

`scipy.ndimage.grey_opening` (*input*, *size=None*, *footprint=None*, *structure=None*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Multidimensional grayscale opening.

A grayscale opening consists in the succession of a grayscale erosion, and a grayscale dilation.

Parameters

input	[array_like] Array over which the grayscale opening is to be computed.
size	[tuple of ints] Shape of a flat and full structuring element used for the grayscale opening. Optional if <i>footprint</i> or <i>structure</i> is provided.
footprint	[array of ints, optional] Positions of non-infinite elements of a flat structuring element used for the grayscale opening.
structure	[array of ints, optional] Structuring element used for the grayscale opening. <i>structure</i> may be a non-flat structuring element.
output	[array, optional] An array used for storing the output of the opening may be provided.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the array borders are handled, where <i>cval</i> is the value when mode is equal to 'constant'. Default is 'reflect'
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
origin	[scalar, optional] The <i>origin</i> parameter controls the placement of the filter. Default 0

Returns

grey_opening
[ndarray] Result of the grayscale opening of *input* with *structure*.

See also:

binary_opening, *grey_dilation*, *grey_erosion*, *grey_closing*
generate_binary_structure

Notes

The action of a grayscale opening with a flat structuring element amounts to smoothen high local maxima, whereas binary opening erases small objects.

References

[1]

Examples

```
>>> from scipy import ndimage
>>> a = np.arange(36).reshape((6,6))
>>> a[3, 3] = 50
>>> a
array([[ 0,  1,  2,  3,  4,  5],
       [ 6,  7,  8,  9, 10, 11],
       [12, 13, 14, 15, 16, 17],
       [18, 19, 20, 50, 22, 23],
       [24, 25, 26, 27, 28, 29],
       [30, 31, 32, 33, 34, 35]])
>>> ndimage.grey_opening(a, size=(3,3))
array([[ 0,  1,  2,  3,  4,  4],
       [ 6,  7,  8,  9, 10, 10],
       [12, 13, 14, 15, 16, 16],
       [18, 19, 20, 22, 22, 22],
       [24, 25, 26, 27, 28, 28],
       [24, 25, 26, 27, 28, 28]])
>>> # Note that the local maximum a[3,3] has disappeared
```

scipy.ndimage.iterate_structure

`scipy.ndimage.iterate_structure` (*structure*, *iterations*, *origin=None*)

Iterate a structure by dilating it with itself.

Parameters

structure [array_like] Structuring element (an array of bools, for example), to be dilated with itself.
iterations [int] number of dilations performed on the structure with itself
origin [optional] If origin is None, only the iterated structure is returned. If not, a tuple of the iterated structure and the modified origin is returned.

Returns

iterate_structure
 [ndarray of bools] A new structuring element obtained by dilating *structure* (*iterations* - 1) times with itself.

See also:

[*generate_binary_structure*](#)

Examples

```

>>> from scipy import ndimage
>>> struct = ndimage.generate_binary_structure(2, 1)
>>> struct.astype(int)
array([[0, 1, 0],
       [1, 1, 1],
       [0, 1, 0]])
>>> ndimage.iterate_structure(struct, 2).astype(int)
array([[0, 0, 1, 0, 0],
       [0, 1, 1, 1, 0],
       [1, 1, 1, 1, 1],
       [0, 1, 1, 1, 0],
       [0, 0, 1, 0, 0]])
>>> ndimage.iterate_structure(struct, 3).astype(int)
array([[0, 0, 0, 1, 0, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 1, 1, 1, 1, 1, 0],
       [1, 1, 1, 1, 1, 1, 1],
       [0, 1, 1, 1, 1, 1, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 0, 1, 0, 0, 0]])

```

scipy.ndimage.morphological_gradient

`scipy.ndimage.morphological_gradient` (*input*, *size=None*, *footprint=None*, *structure=None*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Multidimensional morphological gradient.

The morphological gradient is calculated as the difference between a dilation and an erosion of the input with a given structuring element.

Parameters

input	[array_like] Array over which to compute the morphological gradient.
size	[tuple of ints] Shape of a flat and full structuring element used for the mathematical morphology operations. Optional if <i>footprint</i> or <i>structure</i> is provided. A larger <i>size</i> yields a more blurred gradient.
footprint	[array of ints, optional] Positions of non-infinite elements of a flat structuring element used for the morphology operations. Larger footprints give a more blurred morphological gradient.
structure	[array of ints, optional] Structuring element used for the morphology operations. <i>structure</i> may be a non-flat structuring element.
output	[array, optional] An array used for storing the output of the morphological gradient may be provided.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the array borders are handled, where <i>cval</i> is the value when mode is equal to 'constant'. Default is 'reflect'
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
origin	[scalar, optional] The <i>origin</i> parameter controls the placement of the filter. Default 0

Returns**morphological_gradient**

[ndarray] Morphological gradient of *input*.

See also:

grey_dilation, grey_erosion, gaussian_gradient_magnitude

Notes

For a flat structuring element, the morphological gradient computed at a given point corresponds to the maximal difference between elements of the input among the elements covered by the structuring element centered on the point.

References

[1]

Examples

```
>>> from scipy import ndimage
>>> a = np.zeros((7,7), dtype=int)
>>> a[2:5, 2:5] = 1
>>> ndimage.morphological_gradient(a, size=(3,3))
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 1, 1, 1, 1, 1, 0],
       [0, 1, 1, 1, 1, 1, 0],
       [0, 1, 1, 0, 1, 1, 0],
       [0, 1, 1, 1, 1, 1, 0],
       [0, 1, 1, 1, 1, 1, 0],
       [0, 0, 0, 0, 0, 0, 0]])
>>> # The morphological gradient is computed as the difference
>>> # between a dilation and an erosion
>>> ndimage.grey_dilation(a, size=(3,3)) -\
... ndimage.grey_erosion(a, size=(3,3))
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 1, 1, 1, 1, 1, 0],
       [0, 1, 1, 1, 1, 1, 0],
       [0, 1, 1, 0, 1, 1, 0],
       [0, 1, 1, 1, 1, 1, 0],
       [0, 1, 1, 1, 1, 1, 0],
       [0, 0, 0, 0, 0, 0, 0]])
>>> a = np.zeros((7,7), dtype=int)
>>> a[2:5, 2:5] = 1
>>> a[4,4] = 2; a[2,3] = 3
>>> a
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 1, 3, 1, 0, 0],
       [0, 0, 1, 1, 1, 0, 0],
       [0, 0, 1, 1, 2, 0, 0],
       [0, 0, 0, 0, 0, 0, 0],
       [0, 0, 0, 0, 0, 0, 0]])
>>> ndimage.morphological_gradient(a, size=(3,3))
```

(continues on next page)

(continued from previous page)

```
array([[0, 0, 0, 0, 0, 0, 0],
       [0, 1, 3, 3, 3, 1, 0],
       [0, 1, 3, 3, 3, 1, 0],
       [0, 1, 3, 2, 3, 2, 0],
       [0, 1, 1, 2, 2, 2, 0],
       [0, 1, 1, 2, 2, 2, 0],
       [0, 0, 0, 0, 0, 0, 0]])
```

scipy.ndimage.morphological_laplace

`scipy.ndimage.morphological_laplace` (*input*, *size=None*, *footprint=None*, *structure=None*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Multidimensional morphological laplace.

Parameters

input	[array_like] Input.
size	[int or sequence of ints, optional] See <i>structure</i> .
footprint	[bool or ndarray, optional] See <i>structure</i> .
structure	[structure, optional] Either <i>size</i> , <i>footprint</i> , or the <i>structure</i> must be provided.
output	[ndarray, optional] An output array can optionally be provided.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The mode parameter determines how the array borders are handled. For 'constant' mode, values beyond borders are set to be <i>cval</i> . Default is 'reflect'.
cval	[scalar, optional] Value to fill past edges of input if mode is 'constant'. Default is 0.0
origin	[origin, optional] The origin parameter controls the placement of the filter.

Returns

morphological_laplace
[ndarray] Output

scipy.ndimage.white_tophat

`scipy.ndimage.white_tophat` (*input*, *size=None*, *footprint=None*, *structure=None*, *output=None*, *mode='reflect'*, *cval=0.0*, *origin=0*)

Multidimensional white tophat filter.

Parameters

input	[array_like] Input.
size	[tuple of ints] Shape of a flat and full structuring element used for the filter. Optional if <i>footprint</i> or <i>structure</i> is provided.
footprint	[array of ints, optional] Positions of elements of a flat structuring element used for the white tophat filter.
structure	[array of ints, optional] Structuring element used for the filter. <i>structure</i> may be a non-flat structuring element.
output	[array, optional] An array used for storing the output of the filter may be provided.
mode	[{'reflect', 'constant', 'nearest', 'mirror', 'wrap'}, optional] The <i>mode</i> parameter determines how the array borders are handled, where <i>cval</i> is the value when mode is equal to 'constant'. Default is 'reflect'
cval	[scalar, optional] Value to fill past edges of input if <i>mode</i> is 'constant'. Default is 0.0.
origin	[scalar, optional] The <i>origin</i> parameter controls the placement of the filter. Default is 0.

Returns**output** [ndarray] Result of the filter of *input* with *structure*.

See also:

black_tophat

6.18 Orthogonal distance regression (`scipy.odr`)

6.18.1 Package Content

<i>Data</i> (<i>x</i> [, <i>y</i> , <i>we</i> , <i>wd</i> , <i>fix</i> , <i>meta</i>])	The data to fit.
<i>RealData</i> (<i>x</i> [, <i>y</i> , <i>sx</i> , <i>sy</i> , <i>covx</i> , <i>covy</i> , <i>fix</i> , <i>meta</i>])	The data, with weightings as actual standard deviations and/or covariances.
<i>Model</i> (<i>fcn</i> [, <i>fjacb</i> , <i>fjacd</i> , <i>extra_args</i> , ...])	The Model class stores information about the function you wish to fit.
<i>ODR</i> (<i>data</i> , <i>model</i> [, <i>beta0</i> , <i>delta0</i> , <i>ifixb</i> , ...])	The ODR class gathers all information and coordinates the running of the main fitting routine.
<i>Output</i> (<i>output</i>)	The Output class stores the output of an ODR run.
<i>odr</i> (<i>fcn</i> , <i>beta0</i> , <i>y</i> , <i>x</i> [, <i>we</i> , <i>wd</i> , <i>fjacb</i> , ...])	Low-level function for ODR.
<i>OdrWarning</i>	Warning indicating that the data passed into ODR will cause problems when passed into 'odr' that the user should be aware of.
<i>OdrError</i>	Exception indicating an error in fitting.
<i>OdrStop</i>	Exception stopping fitting.
<i>polynomial</i> (<i>order</i>)	Factory function for a general polynomial model.
<i>exponential</i>	Exponential model
<i>multilinear</i>	Arbitrary-dimensional linear model
<i>unilinear</i>	Univariate linear model
<i>quadratic</i>	Quadratic model

`scipy.odr.Data`

class `scipy.odr.Data` (*x*, *y=None*, *we=None*, *wd=None*, *fix=None*, *meta={}*)

The data to fit.

Parameters

x [array_like] Observed data for the independent variable of the regression

y [array_like, optional] If array-like, observed data for the dependent variable of the regression. A scalar input implies that the model to be used on the data is implicit.

we [array_like, optional] If *we* is a scalar, then that value is used for all data points (and all dimensions of the response variable). If *we* is a rank-1 array of length *q* (the dimensionality of the response variable), then this vector is the diagonal of the covariant weighting matrix for all data points. If *we* is a rank-1 array of length *n* (the number of data points), then the *i*'th element is the weight for the *i*'th response variable observation (single-dimensional only). If *we* is a rank-2 array of shape (*q*, *q*), then this is the full covariant weighting matrix broadcast to each observation. If *we* is a rank-2 array of shape (*q*, *n*), then *we*[:,*i*] is the diagonal of the covariant weighting matrix for the *i*'th observation. If *we* is a rank-3 array of shape (*q*, *q*, *n*),

then $wel[:, :, i]$ is the full specification of the covariant weighting matrix for each observation. If the fit is implicit, then only a positive scalar value is used.

wd [array_like, optional] If wd is a scalar, then that value is used for all data points (and all dimensions of the input variable). If $wd = 0$, then the covariant weighting matrix for each observation is set to the identity matrix (so each dimension of each observation has the same weight). If wd is a rank-1 array of length m (the dimensionality of the input variable), then this vector is the diagonal of the covariant weighting matrix for all data points. If wd is a rank-1 array of length n (the number of data points), then the i 'th element is the weight for the i th input variable observation (single-dimensional only). If wd is a rank-2 array of shape (m, m) , then this is the full covariant weighting matrix broadcast to each observation. If wd is a rank-2 array of shape (m, n) , then $wd[:, i]$ is the diagonal of the covariant weighting matrix for the i th observation. If wd is a rank-3 array of shape (m, m, n) , then $wd[:, :, i]$ is the full specification of the covariant weighting matrix for each observation.

fix [array_like of ints, optional] The fix argument is the same as $ifix$ in the class ODR. It is an array of integers with the same shape as $data.x$ that determines which input observations are treated as fixed. One can use a sequence of length m (the dimensionality of the input observations) to fix some dimensions for all observations. A value of 0 fixes the observation, a value > 0 makes it free.

meta [dict, optional] Free-form dictionary for metadata.

Notes

Each argument is attached to the member of the instance of the same name. The structures of x and y are described in the Model class docstring. If y is an integer, then the Data instance can only be used to fit with implicit models where the dimensionality of the response is equal to the specified value of y .

The w argument weights the effect a deviation in the response variable has on the fit. The wd argument weights the effect a deviation in the input variable has on the fit. To handle multidimensional inputs and responses easily, the structure of these arguments has the n 'th dimensional axis first. These arguments heavily use the structured arguments feature of ODRPACK to conveniently and flexibly support all options. See the ODRPACK User's Guide for a full explanation of how these weights are used in the algorithm. Basically, a higher value of the weight for a particular data point makes a deviation at that point more detrimental to the fit.

Methods

<code>set_meta(self, **kwargs)</code>	Update the metadata dictionary with the keywords and data provided by keywords.
---------------------------------------	---

scipy.odr.Data.set_meta

`Data.set_meta(self, **kwargs)`
 Update the metadata dictionary with the keywords and data provided by keywords.

Examples

```
data.set_meta(lab="Ph 7; Lab 26", title="Ag110 + Ag108 Decay")
```

scipy.odr.RealData

```
class scipy.odr.RealData(x, y=None, sx=None, sy=None, covx=None, covy=None, fix=None,
                           meta={})
```

The data, with weightings as actual standard deviations and/or covariances.

Parameters

x	[array_like] Observed data for the independent variable of the regression
y	[array_like, optional] If array-like, observed data for the dependent variable of the regression. A scalar input implies that the model to be used on the data is implicit.
sx	[array_like, optional] Standard deviations of <i>x</i> . <i>sx</i> are standard deviations of <i>x</i> and are converted to weights by dividing 1.0 by their squares.
sy	[array_like, optional] Standard deviations of <i>y</i> . <i>sy</i> are standard deviations of <i>y</i> and are converted to weights by dividing 1.0 by their squares.
covx	[array_like, optional] Covariance of <i>x</i> <i>covx</i> is an array of covariance matrices of <i>x</i> and are converted to weights by performing a matrix inversion on each observation's covariance matrix.
covy	[array_like, optional] Covariance of <i>y</i> <i>covy</i> is an array of covariance matrices and are converted to weights by performing a matrix inversion on each observation's covariance matrix.
fix	[array_like, optional] The argument and member <i>fix</i> is the same as <i>Data.fix</i> and <i>ODR.ifix</i> : It is an array of integers with the same shape as <i>x</i> that determines which input observations are treated as fixed. One can use a sequence of length <i>m</i> (the dimensionality of the input observations) to fix some dimensions for all observations. A value of 0 fixes the observation, a value > 0 makes it free.
meta	[dict, optional] Free-form dictionary for metadata.

Notes

The weights *wd* and *we* are computed from provided values as follows:

sx and *sy* are converted to weights by dividing 1.0 by their squares. For example, `wd = 1./numpy.power(`sx`, 2)`.

covx and *covy* are arrays of covariance matrices and are converted to weights by performing a matrix inversion on each observation's covariance matrix. For example, `we[i] = numpy.linalg.inv(covy[i])`.

These arguments follow the same structured argument conventions as *wd* and *we* only restricted by their natures: *sx* and *sy* can't be rank-3, but *covx* and *covy* can be.

Only set *either* *sx* or *covx* (not both). Setting both will raise an exception. Same with *sy* and *covy*.

Methods

<code>set_meta(self, **kwargs)</code>	Update the metadata dictionary with the keywords and data provided by keywords.
---------------------------------------	---

scipy.odr.RealData.set_meta

`RealData.set_meta(self, **kwargs)`

Update the metadata dictionary with the keywords and data provided by keywords.

Examples

```
data.set_meta(lab="Ph 7; Lab 26", title="Ag110 + Ag108 Decay")
```

scipy.odr.Model

class `scipy.odr.Model` (*fcn*, *fjacb*=None, *fjacd*=None, *extra_args*=None, *estimate*=None, *implicit*=0, *meta*=None)

The Model class stores information about the function you wish to fit.

It stores the function itself, at the least, and optionally stores functions which compute the Jacobians used during fitting. Also, one can provide a function that will provide reasonable starting values for the fit parameters possibly given the set of data.

Parameters

fcn	[function] <code>fcn(beta, x) -> y</code>
fjacb	[function] Jacobian of <code>fcn</code> wrt the fit parameters <code>beta</code> . <code>fjacb(beta, x) -> @f_i(x,B)/@B_j</code>
fjacd	[function] Jacobian of <code>fcn</code> wrt the (possibly multidimensional) input variable. <code>fjacd(beta, x) -> @f_i(x,B)/@x_j</code>
extra_args	[tuple, optional] If specified, <i>extra_args</i> should be a tuple of extra arguments to pass to <i>fcn</i> , <i>fjacb</i> , and <i>fjacd</i> . Each will be called by <code>apply(fcn, (beta, x) + extra_args)</code>
estimate	[array_like of rank-1] Provides estimates of the fit parameters from the data <code>estimate(data) -> estbeta</code>
implicit	[boolean] If TRUE, specifies that the model is implicit; i.e. <code>fcn(beta, x) ≈ 0</code> and there is no <code>y</code> data to fit against
meta	[dict, optional] freeform dictionary of metadata for the model

Notes

Note that the *fcn*, *fjacb*, and *fjacd* operate on NumPy arrays and return a NumPy array. The *estimate* object takes an instance of the Data class.

Here are the rules for the shapes of the argument and return arrays of the callback functions:

x if the input data is single-dimensional, then `x` is rank-1 array; i.e., `x = array([1, 2, 3, ...])`; `x.shape = (n,)` If the input data is multi-dimensional, then `x` is a rank-2 array; i.e., `x = array([[1, 2, ...], [2, 4, ...]])`; `x.shape = (m, n)`. In all cases, it has the same shape as the input data array passed to *odr*. *m* is the dimensionality of the input data, *n* is the number of observations.

y if the response variable is single-dimensional, then y is a rank-1 array, i.e., $y = \text{array}([2, 4, \dots])$; $y.\text{shape} = (n,)$. If the response variable is multi-dimensional, then y is a rank-2 array, i.e., $y = \text{array}([[2, 4, \dots], [3, 6, \dots]])$; $y.\text{shape} = (q, n)$ where q is the dimensionality of the response variable.

beta

rank-1 array of length p where p is the number of parameters; i.e. $\text{beta} = \text{array}([B_1, B_2, \dots, B_p])$

fjacb

if the response variable is multi-dimensional, then the return array's shape is (q, p, n) such that $\text{fjacb}(x, \text{beta})[l, k, i] = d f_l(X, B) / d B_k$ evaluated at the i th data point. If $q == 1$, then the return array is only rank-2 and with shape (p, n) .

fjacd

as with `fjacb`, only the return array's shape is (q, m, n) such that $\text{fjacd}(x, \text{beta})[l, j, i] = d f_l(X, B) / d X_j$ at the i th data point. If $q == 1$, then the return array's shape is (m, n) . If $m == 1$, the shape is (q, n) . If $m == q == 1$, the shape is $(n,)$.

Methods

<code>set_meta(self, **kwargs)</code>	Update the metadata dictionary with the keywords and data provided here.
---------------------------------------	--

scipy.odr.Model.set_meta

`Model.set_meta(self, **kwargs)`

Update the metadata dictionary with the keywords and data provided here.

Examples

```
set_meta(name="Exponential", equation="y = a exp(b x) + c")
```

scipy.odr.ODR

```
class scipy.odr.ODR(data, model, beta0=None, delta0=None, ifxb=None, ifxx=None, job=None,
                    iprint=None, errfile=None, rptfile=None, ndigit=None, taufac=None, sstol=None,
                    partol=None, maxit=None, stpb=None, stpd=None, sclb=None, scld=None,
                    work=None, iwork=None, overwrite=False)
```

The ODR class gathers all information and coordinates the running of the main fitting routine.

Members of instances of the ODR class have the same names as the arguments to the initialization routine.

Parameters

data [Data class instance] instance of the Data class
model [Model class instance] instance of the Model class

Other Parameters

beta0 [array_like of rank-1] a rank-1 sequence of initial parameter values. Optional if model provides an "estimate" function to estimate these values.
delta0 [array_like of floats of rank-1, optional] a (double-precision) float array to hold the initial values of the errors in the input variables. Must be same shape as `data.x`

ifixb	[array_like of ints of rank-1, optional] sequence of integers with the same length as beta0 that determines which parameters are held fixed. A value of 0 fixes the parameter, a value > 0 makes the parameter free.
ifixx	[array_like of ints with same shape as data.x, optional] an array of integers with the same shape as data.x that determines which input observations are treated as fixed. One can use a sequence of length m (the dimensionality of the input observations) to fix some dimensions for all observations. A value of 0 fixes the observation, a value > 0 makes it free.
job	[int, optional] an integer telling ODRPACK what tasks to perform. See p. 31 of the ODRPACK User's Guide if you absolutely must set the value here. Use the method set_job post-initialization for a more readable interface.
iprint	[int, optional] an integer telling ODRPACK what to print. See pp. 33-34 of the ODRPACK User's Guide if you absolutely must set the value here. Use the method set_iprint post-initialization for a more readable interface.
errfile	[str, optional] string with the filename to print ODRPACK errors to. If the file already exists, an error will be thrown. The <i>overwrite</i> argument can be used to prevent this. <i>Do Not Open This File Yourself!</i>
rptfile	[str, optional] string with the filename to print ODRPACK summaries to. If the file already exists, an error will be thrown. The <i>overwrite</i> argument can be used to prevent this. <i>Do Not Open This File Yourself!</i>
ndigit	[int, optional] integer specifying the number of reliable digits in the computation of the function.
taufac	[float, optional] float specifying the initial trust region. The default value is 1. The initial trust region is equal to taufac times the length of the first computed Gauss-Newton step. taufac must be less than 1.
sstol	[float, optional] float specifying the tolerance for convergence based on the relative change in the sum-of-squares. The default value is $\text{eps}^{**}(1/2)$ where eps is the smallest value such that $1 + \text{eps} > 1$ for double precision computation on the machine. sstol must be less than 1.
partol	[float, optional] float specifying the tolerance for convergence based on the relative change in the estimated parameters. The default value is $\text{eps}^{**}(2/3)$ for explicit models and $\text{eps}^{**}(1/3)$ for implicit models. partol must be less than 1.
maxit	[int, optional] integer specifying the maximum number of iterations to perform. For first runs, maxit is the total number of iterations performed and defaults to 50. For restarts, maxit is the number of additional iterations to perform and defaults to 10.
stpb	[array_like, optional] sequence ($\text{len}(\text{stpb}) == \text{len}(\text{beta0})$) of relative step sizes to compute finite difference derivatives wrt the parameters.
stpd	[optional] array ($\text{stpd.shape} == \text{data.x.shape}$ or $\text{stpd.shape} == (m,)$) of relative step sizes to compute finite difference derivatives wrt the input variable errors. If stpd is a rank-1 array with length m (the dimensionality of the input variable), then the values are broadcast to all observations.
sclb	[array_like, optional] sequence ($\text{len}(\text{stpb}) == \text{len}(\text{beta0})$) of scaling factors for the parameters. The purpose of these scaling factors are to scale all of the parameters to around unity. Normally appropriate scaling factors are computed if this argument is not specified. Specify them yourself if the automatic procedure goes awry.
scl d	[array_like, optional] array ($\text{scl d.shape} == \text{data.x.shape}$ or $\text{scl d.shape} == (m,)$) of scaling factors for the <i>errors</i> in the input variables. Again, these factors are automatically computed if you do not provide them. If $\text{scl d.shape} == (m,)$, then the scaling factors are broadcast to all observations.
work	[ndarray, optional] array to hold the double-valued working data for ODRPACK. When restarting, takes the value of self.output.work.
iwork	[ndarray, optional] array to hold the integer-valued working data for ODRPACK. When restarting, takes the value of self.output.iwork.
overwrite	[bool, optional] If it is True, output files defined by <i>errfile</i> and <i>rptfile</i> are overwritten. The default is False.

Attributes

data	[Data] The data for this fit
model	[Model] The model used in fit
output	[Output] An instance of the Output class containing all of the returned data from an invocation of <code>ODR.run()</code> or <code>ODR.restart()</code>

Methods

<code>restart(self[, iter])</code>	Restarts the run with <code>iter</code> more iterations.
<code>run(self)</code>	Run the fitting routine with all of the information given and with <code>full_output=1</code> .
<code>set_iprint(self[, init, so_init, iter, ...])</code>	Set the <code>iprint</code> parameter for the printing of computation reports.
<code>set_job(self[, fit_type, deriv, var_calc, ...])</code>	Sets the “job” parameter in a hopefully comprehensible way.

scipy.odr.ODR.restart

`ODR.restart` (*self*, *iter=None*)

Restarts the run with `iter` more iterations.

Parameters

iter [int, optional] ODRPACK’s default for the number of new iterations is 10.

Returns

output [Output instance] This object is also assigned to the attribute `.output`.

scipy.odr.ODR.run

`ODR.run` (*self*)

Run the fitting routine with all of the information given and with `full_output=1`.

Returns

output [Output instance] This object is also assigned to the attribute `.output`.

scipy.odr.ODR.set_iprint

`ODR.set_iprint` (*self*, *init=None*, *so_init=None*, *iter=None*, *so_iter=None*, *iter_step=None*, *final=None*, *so_final=None*)

Set the `iprint` parameter for the printing of computation reports.

If any of the arguments are specified here, then they are set in the `iprint` member. If `iprint` is not set manually or with this method, then ODRPACK defaults to no printing. If no filename is specified with the member `rptfile`, then ODRPACK prints to stdout. One can tell ODRPACK to print to stdout in addition to the specified filename by setting the `so_*` arguments to this function, but one cannot specify to print to stdout but not a file since one can do that by not specifying a `rptfile` filename.

There are three reports: initialization, iteration, and final reports. They are represented by the arguments `init`, `iter`, and `final` respectively. The permissible values are 0, 1, and 2 representing “no report”, “short report”, and “long report” respectively.

The argument `iter_step` ($0 \leq \text{iter_step} \leq 9$) specifies how often to make the iteration report; the report will be made for every `iter_step`’th iteration starting with iteration one. If `iter_step == 0`, then no iteration report is made, regardless of the other arguments.

If the `rptfile` is `None`, then any `so_*` arguments supplied will raise an exception.

scipy.odr.ODR.set_job

`ODR.set_job(self, fit_type=None, deriv=None, var_calc=None, del_init=None, restart=None)`

Sets the “job” parameter in a hopefully comprehensible way.

If an argument is not specified, then the value is left as is. The default value from class initialization is for all of these options set to 0.

Parameters

fit_type	<ul style="list-style-type: none"> [[0, 1, 2] int] 0 -> explicit ODR 1 -> implicit ODR 2 -> ordinary least-squares
deriv	<ul style="list-style-type: none"> [[0, 1, 2, 3] int] 0 -> forward finite differences 1 -> central finite differences 2 -> user-supplied derivatives (Jacobians) with results checked by ODRPACK 3 -> user-supplied derivatives, no checking
var_calc	<ul style="list-style-type: none"> [[0, 1, 2] int] 0 -> calculate asymptotic covariance matrix and fit parameter uncertainties (<code>V_B</code>, <code>s_B</code>) using derivatives recomputed at the final solution 1 -> calculate <code>V_B</code> and <code>s_B</code> using derivatives from last iteration 2 -> do not calculate <code>V_B</code> and <code>s_B</code>
del_init	<ul style="list-style-type: none"> [[0, 1] int] 0 -> initial input variable offsets set to 0 1 -> initial offsets provided by user in variable “work”
restart	<ul style="list-style-type: none"> [[0, 1] int] 0 -> fit is not a restart 1 -> fit is a restart

Notes

The permissible values are different from those given on pg. 31 of the ODRPACK User’s Guide only in that one cannot specify numbers greater than the last value for each variable.

If one does not supply functions to compute the Jacobians, the fitting procedure will change `deriv` to 0, finite differences, as a default. To initialize the input variable offsets by yourself, set `del_init` to 1 and put the offsets into the “work” variable correctly.

scipy.odr.Output

`class scipy.odr.Output(output)`

The Output class stores the output of an ODR run.

Notes

Takes one argument for initialization, the return value from the function `odr`. The attributes listed as “optional” above are only present if `odr` was run with `full_output=1`.

Attributes

beta	[ndarray] Estimated parameter values, of shape (q,).
sd_beta	[ndarray] Standard deviations of the estimated parameters, of shape (p,).
cov_beta	[ndarray] Covariance matrix of the estimated parameters, of shape (p,p).
delta	[ndarray, optional] Array of estimated errors in input variables, of same shape as <i>x</i> .
eps	[ndarray, optional] Array of estimated errors in response variables, of same shape as <i>y</i> .
xplus	[ndarray, optional] Array of $x + \text{delta}$.
y	[ndarray, optional] Array $y = \text{fcn}(x + \text{delta})$.
res_var	[float, optional] Residual variance.
sum_square	[float, optional] Sum of squares error.
sum_square_delta	[float, optional] Sum of squares of delta error.
sum_square_eps	[float, optional] Sum of squares of eps error.
inv_condnum	[float, optional] Inverse condition number (cf. ODRPACK UG p. 77).
rel_error	[float, optional] Relative error in function values computed within <code>fcn</code> .
work	[ndarray, optional] Final work array.
work_ind	[dict, optional] Indices into work for drawing out values (cf. ODRPACK UG p. 83).
info	[int, optional] Reason for returning, as output by ODRPACK (cf. ODRPACK UG p. 38).
stopreason	[list of str, optional] <i>info</i> interpreted into English.

Methods

<code>pprint(self)</code>	Pretty-print important results.
---------------------------	---------------------------------

scipy.odr.Output.pprint

Output `.pprint` (*self*)
 Pretty-print important results.

scipy.odr.odr

`scipy.odr.odr` (*fcn*, *beta0*, *y*, *x*, *we=None*, *wd=None*, *fjacb=None*, *fjacd=None*, *extra_args=None*, *ifixx=None*, *ifixb=None*, *job=0*, *iprint=0*, *errfile=None*, *rptfile=None*, *ndigit=0*, *taufac=0.0*, *sstol=- 1.0*, *partol=- 1.0*, *maxit=- 1*, *stpb=None*, *stpd=None*, *sclb=None*, *scll=None*, *work=None*, *iwork=None*, *full_output=0*)

Low-level function for ODR.

See also:

ODR

The ODR class gathers all information and coordinates the running of the main fitting routine.

Model

The `Model` class stores information about the function you wish to fit.

Data

The data to fit.

RealData

Data with weights as actual std. dev.s and/or covariances.

Notes

This is a function performing the same operation as the `ODR`, `Model`, and `Data` classes together. The parameters of this function are explained in the class documentation.

scipy.odr.OdrWarning

exception `scipy.odr.OdrWarning`

Warning indicating that the data passed into ODR will cause problems when passed into 'odr' that the user should be aware of.

with_traceback ()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

scipy.odr.OdrError

exception `scipy.odr.OdrError`

Exception indicating an error in fitting.

This is raised by `odr` if an error occurs during fitting.

with_traceback ()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

scipy.odr.OdrStop

exception `scipy.odr.OdrStop`

Exception stopping fitting.

You can raise this exception in your objective function to tell `odr` to stop fitting.

with_traceback ()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

scipy.odr.polynomial

`scipy.odr.polynomial` (*order*)

Factory function for a general polynomial model.

Parameters

order [int or sequence] If an integer, it becomes the order of the polynomial to fit. If a sequence of numbers, then these are the explicit powers in the polynomial. A constant term (power 0) is always included, so don't include 0. Thus, `polynomial(n)` is equivalent to `polynomial(range(1, n+1))`.


Returns**polynomial**

[Model instance] Model instance.

Examples

We can fit an input data using orthogonal distance regression (ODR) with a polynomial model:

```
>>> import matplotlib.pyplot as plt
>>> from scipy import odr
>>> x = np.linspace(0.0, 5.0)
>>> y = np.sin(x)
>>> poly_model = odr.polynomial(3) # using third order polynomial model
>>> data = odr.Data(x, y)
>>> odr_obj = odr.ODR(data, poly_model)
>>> output = odr_obj.run() # running ODR fitting
>>> poly = np.poly1d(output.beta[:, :-1])
>>> poly_y = poly(x)
>>> plt.plot(x, y, label="input data")
>>> plt.plot(x, poly_y, label="polynomial ODR")
>>> plt.legend()
>>> plt.show()
```



scipy.odr.exponential

`scipy.odr.exponential` = <scipy.odr.models._ExponentialModel object>
Exponential model

This model is defined by $y = \beta_0 + e^{\beta_1 x}$

Examples

We can calculate orthogonal distance regression with an exponential model:

```
>>> from scipy import odr
>>> x = np.linspace(0.0, 5.0)
>>> y = -10.0 + np.exp(0.5*x)
>>> data = odr.Data(x, y)
>>> odr_obj = odr.ODR(data, odr.exponential)
>>> output = odr_obj.run()
>>> print(output.beta)
[-10.    0.5]
```

scipy.odr.multilinear

`scipy.odr.multilinear` = <scipy.odr.models._MultilinearModel object>
Arbitrary-dimensional linear model

This model is defined by $y = \beta_0 + \sum_{i=1}^m \beta_i x_i$

Examples

We can calculate orthogonal distance regression with an arbitrary dimensional linear model:

```
>>> from scipy import odr
>>> x = np.linspace(0.0, 5.0)
>>> y = 10.0 + 5.0 * x
>>> data = odr.Data(x, y)
>>> odr_obj = odr.ODR(data, odr.multilinear)
>>> output = odr_obj.run()
>>> print(output.beta)
[10.  5.]
```

scipy.odr.unilinear

`scipy.odr.unilinear` = <scipy.odr.models._UnilinearModel object>
Univariate linear model

This model is defined by $y = \beta_0 x + \beta_1$

Examples

We can calculate orthogonal distance regression with an unilinear model:

```
>>> from scipy import odr
>>> x = np.linspace(0.0, 5.0)
>>> y = 1.0 * x + 2.0
>>> data = odr.Data(x, y)
>>> odr_obj = odr.ODR(data, odr.unilinear)
>>> output = odr_obj.run()
>>> print(output.beta)
[1. 2.]
```

scipy.odr.quadratic

`scipy.odr.quadratic` = <scipy.odr.models._QuadraticModel object>
Quadratic model

This model is defined by $y = \beta_0 x^2 + \beta_1 x + \beta_2$

Examples

We can calculate orthogonal distance regression with a quadratic model:

```
>>> from scipy import odr
>>> x = np.linspace(0.0, 5.0)
>>> y = 1.0 * x ** 2 + 2.0 * x + 3.0
>>> data = odr.Data(x, y)
>>> odr_obj = odr.ODR(data, odr.quadratic)
>>> output = odr_obj.run()
>>> print(output.beta)
[1. 2. 3.]
```

6.18.2 Usage information

Introduction

Why Orthogonal Distance Regression (ODR)? Sometimes one has measurement errors in the explanatory (a.k.a., “independent”) variable(s), not just the response (a.k.a., “dependent”) variable(s). Ordinary Least Squares (OLS) fitting procedures treat the data for explanatory variables as fixed, i.e., not subject to error of any kind. Furthermore, OLS procedures require that the response variables be an explicit function of the explanatory variables; sometimes making the equation explicit is impractical and/or introduces errors. ODR can handle both of these cases with ease, and can even reduce to the OLS case if that is sufficient for the problem.

ODRPACK is a FORTRAN-77 library for performing ODR with possibly non-linear fitting functions. It uses a modified trust-region Levenberg-Marquardt-type algorithm [1] to estimate the function parameters. The fitting functions are provided by Python functions operating on NumPy arrays. The required derivatives may be provided by Python functions as well, or may be estimated numerically. ODRPACK can do explicit or implicit ODR fits, or it can do OLS. Input and output variables may be multidimensional. Weights can be provided to account for different variances of the observations, and even covariances between dimensions of the variables.

The `scipy.odr` package offers an object-oriented interface to ODRPACK, in addition to the low-level `odr` function.

Additional background information about ODRPACK can be found in the [ODRPACK User's Guide](#), reading which is recommended.

Basic usage

1. Define the function you want to fit against.:

```
def f(B, x):
    '''Linear function y = m*x + b'''
    # B is a vector of the parameters.
    # x is an array of the current x values.
    # x is in the same format as the x passed to Data or RealData.
    #
    # Return an array in the same format as y passed to Data or RealData.
    return B[0]*x + B[1]
```

2. Create a Model.:

```
linear = Model(f)
```

3. Create a Data or RealData instance.:

```
mydata = Data(x, y, wd=1./power(sx,2), we=1./power(sy,2))
```

or, when the actual covariances are known:

```
mydata = RealData(x, y, sx=sx, sy=sy)
```

4. Instantiate ODR with your data, model and initial parameter estimate.:

```
myodr = ODR(mydata, linear, beta0=[1., 2.])
```

5. Run the fit.:

```
myoutput = myodr.run()
```

6. Examine output.:

```
myoutput.pprint()
```

References

6.19 Optimization and root finding (`scipy.optimize`)

SciPy `optimize` provides functions for minimizing (or maximizing) objective functions, possibly subject to constraints. It includes solvers for nonlinear problems (with support for both local and global optimization algorithms), linear programming, constrained and nonlinear least-squares, root finding, and curve fitting.

Common functions and objects, shared across different solvers, are:

<code>show_options([solver, method, disp])</code>	Show documentation for additional options of optimization solvers.
<code>OptimizeResult</code>	Represents the optimization result.
<code>OptimizeWarning</code>	

6.19.1 `scipy.optimize.show_options`

`scipy.optimize.show_options` (*solver=None, method=None, disp=True*)

Show documentation for additional options of optimization solvers.

These are method-specific options that can be supplied through the `options` dict.

Parameters

- solver** [str] Type of optimization solver. One of ‘minimize’, ‘minimize_scalar’, ‘root’, ‘root_scalar’, ‘linprog’, or ‘quadratic_assignment’.
- method** [str, optional] If not given, shows all methods of the specified solver. Otherwise, show only the options for the specified method. Valid values corresponds to methods’ names of respective solver (e.g., ‘BFGS’ for ‘minimize’).
- disp** [bool, optional] Whether to print the result rather than returning it.

Returns

- text** Either None (for `disp=True`) or the text string (`disp=False`)

Notes

The solver-specific methods are:

`scipy.optimize.minimize`

- *Nelder-Mead*
- *Powell*
- *CG*
- *BFGS*
- *Newton-CG*
- *L-BFGS-B*
- *TNC*
- *COBYLA*
- *SLSQP*
- *dogleg*
- *trust-ncg*

`scipy.optimize.root`

- *hybr*
- *lm*
- *broyden1*
- *broyden2*

- *anderson*
- *linearmixing*
- *diagbroyden*
- *excitingmixing*
- *krylov*
- *df-sane*

`scipy.optimize.minimize_scalar`

- *brent*
- *golden*
- *bounded*

`scipy.optimize.root_scalar`

- *bisect*
- *brentq*
- *brenth*
- *ridder*
- *toms748*
- *newton*
- *secant*
- *halley*

`scipy.optimize.linprog`

- *simplex*
- *interior-point*
- *revised simplex*
- *highs*
- *highs-ds*
- *highs-ipm*

`scipy.optimize.quadratic_assignment`

- *faq*
- *2opt*

Examples

We can print documentations of a solver in stdout:

```
>>> from scipy.optimize import show_options
>>> show_options(solver="minimize")
...
```

Specifying a method is possible:

```
>>> show_options(solver="minimize", method="Nelder-Mead")
...
```

We can also get the documentations as a string:

```
>>> show_options(solver="minimize", method="Nelder-Mead", disp=False)
Minimization of scalar function of one or more variables using the ...
```

6.19.2 scipy.optimize.OptimizeResult

class `scipy.optimize.OptimizeResult`

Represents the optimization result.

Notes

There may be additional attributes not listed above depending of the specific solver. Since this class is essentially a subclass of dict with attribute accessors, one can see which attributes are available using the `keys()` method.

Attributes

x	[ndarray] The solution of the optimization.
success	[bool] Whether or not the optimizer exited successfully.
status	[int] Termination status of the optimizer. Its value depends on the underlying solver. Refer to <i>message</i> for details.
message	[str] Description of the cause of the termination.
fun, jac, hess: ndarray	Values of objective function, its Jacobian and its Hessian (if available). The Hessians may be approximations, see the documentation of the function in question.
hess_inv	[object] Inverse of the objective function's Hessian; may be an approximation. Not available for all solvers. The type of this attribute may be either <code>np.ndarray</code> or <code>scipy.sparse.linalg.LinearOperator</code> .
nfev, njev, nhev	[int] Number of evaluations of the objective functions and of its Jacobian and Hessian.
nit	[int] Number of iterations performed by the optimizer.
maxcv	[float] The maximum constraint violation.

Methods

<code>__getitem__()</code>	<code>x.__getitem__(y) <==> x[y]</code>
<code>__len__(self, /)</code>	Return <code>len(self)</code> .
<code>clear()</code>	
<code>copy()</code>	
<code>fromkeys(iterable[, value])</code>	Create a new dictionary with keys from iterable and values set to value.
<code>get(self, key[, default])</code>	Return the value for key if key is in the dictionary, else default.
<code>items()</code>	
<code>keys()</code>	
<code>pop()</code>	If key is not found, d is returned if given, otherwise <code>KeyError</code> is raised
<code>popitem(self, /)</code>	Remove and return a (key, value) pair as a 2-tuple.
<code>setdefault(self, key[, default])</code>	Insert key with a value of default if key is not in the dictionary.
<code>update()</code>	If E is present and has a <code>.keys()</code> method, then does: for k in E: <code>D[k] = E[k]</code> If E is present and lacks a <code>.keys()</code> method, then does: for k, v in E: <code>D[k] = v</code> In either case, this is followed by: for k in F: <code>D[k] = F[k]</code>
<code>values()</code>	

scipy.optimize.OptimizeResult.__getitem__

`OptimizeResult.__getitem__()`
`x.__getitem__(y) <==> x[y]`

scipy.optimize.OptimizeResult.__len__

`OptimizeResult.__len__(self, /)`
 Return `len(self)`.

scipy.optimize.OptimizeResult.clear

`OptimizeResult.clear()`

scipy.optimize.OptimizeResult.copy

`OptimizeResult.copy()`

scipy.optimize.OptimizeResult.fromkeys

`OptimizeResult.fromkeys` (*iterable, value=None, /*)
 Create a new dictionary with keys from iterable and values set to value.

scipy.optimize.OptimizeResult.get

`OptimizeResult.get` (*self, key, default=None, /*)
 Return the value for key if key is in the dictionary, else default.

scipy.optimize.OptimizeResult.items

`OptimizeResult.items` ()

scipy.optimize.OptimizeResult.keys

`OptimizeResult.keys` ()

scipy.optimize.OptimizeResult.pop

`OptimizeResult.pop` ()
 If key is not found, d is returned if given, otherwise `KeyError` is raised

scipy.optimize.OptimizeResult.popitem

`OptimizeResult.popitem` (*self, /*)
 Remove and return a (key, value) pair as a 2-tuple.
 Pairs are returned in LIFO (last-in, first-out) order. Raises `KeyError` if the dict is empty.

scipy.optimize.OptimizeResult.setdefault

`OptimizeResult.setdefault` (*self, key, default=None, /*)
 Insert key with a value of default if key is not in the dictionary.
 Return the value for key if key is in the dictionary, else default.

scipy.optimize.OptimizeResult.update

`OptimizeResult.update` ()
 If E is present and has a `.keys()` method, then does: for k in E: D[k] = E[k] If E is present and lacks a `.keys()` method, then does: for k, v in E: D[k] = v In either case, this is followed by: for k in F: D[k] = F[k]

scipy.optimize.OptimizeResult.values

OptimizeResult.values()

6.19.3 scipy.optimize.OptimizeWarning

exception scipy.optimize.OptimizeWarning

with_traceback()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

6.19.4 Optimization

Scalar functions optimization

<i>minimize_scalar</i> (fun[, bracket, bounds, ...])	Minimization of scalar function of one variable.
--	--

scipy.optimize.minimize_scalar

scipy.optimize.minimize_scalar(*fun*, *bracket=None*, *bounds=None*, *args=()*, *method='brent'*, *tol=None*, *options=None*)

Minimization of scalar function of one variable.

Parameters

fun	[callable] Objective function. Scalar function, must return a scalar.				
bracket	[sequence, optional] For methods 'brent' and 'golden', <i>bracket</i> defines the bracketing interval and can either have three items (<i>a</i> , <i>b</i> , <i>c</i>) so that $a < b < c$ and $\text{fun}(b) < \text{fun}(a)$, $\text{fun}(c)$ or two items <i>a</i> and <i>c</i> which are assumed to be a starting interval for a downhill bracket search (see <i>bracket</i>); it doesn't always mean that the obtained solution will satisfy $a \leq x \leq c$.				
bounds	[sequence, optional] For method 'bounded', <i>bounds</i> is mandatory and must have two items corresponding to the optimization bounds.				
args	[tuple, optional] Extra arguments passed to the objective function.				
method	[str or callable, optional] Type of solver. Should be one of: <ul style="list-style-type: none"> • 'Brent' (see here) • 'Bounded' (see here) • 'Golden' (see here) • custom - a callable object (added in version 0.14.0), see below 				
tol	[float, optional] Tolerance for termination. For detailed control, use solver-specific options.				
options	[dict, optional] A dictionary of solver options. <table style="border: none; margin-left: 20px;"> <tr> <td style="vertical-align: top; padding-right: 10px;">maxiter</td> <td>[int] Maximum number of iterations to perform.</td> </tr> <tr> <td style="vertical-align: top; padding-right: 10px;">disp</td> <td>[bool] Set to True to print convergence messages.</td> </tr> </table> See <i>show_options</i> for solver-specific options.	maxiter	[int] Maximum number of iterations to perform.	disp	[bool] Set to True to print convergence messages.
maxiter	[int] Maximum number of iterations to perform.				
disp	[bool] Set to True to print convergence messages.				

Returns

res	[OptimizeResult] The optimization result represented as a <code>OptimizeResult</code> object. Important attributes are: <i>x</i> the solution array, <i>success</i> a Boolean flag indicating if the optimizer exited successfully and <i>message</i> which describes the cause of the termination. See <i>OptimizeResult</i> for a description of other attributes.
------------	--

See also:

minimize

Interface to minimization algorithms for scalar multivariate functions

show_options

Additional options accepted by the solvers

Notes

This section describes the available solvers that can be selected by the ‘method’ parameter. The default method is *Brent*.

Method *Brent* uses Brent’s algorithm to find a local minimum. The algorithm uses inverse parabolic interpolation when possible to speed up convergence of the golden section method.

Method *Golden* uses the golden section search technique. It uses analog of the bisection method to decrease the bracketed interval. It is usually preferable to use the *Brent* method.

Method *Bounded* can perform bounded minimization. It uses the Brent method to find a local minimum in the interval $x_1 < x_{opt} < x_2$.

Custom minimizers

It may be useful to pass a custom minimization method, for example when using some library frontend to `minimize_scalar`. You can simply pass a callable as the `method` parameter.

The callable is called as `method(fun, args, **kwargs, **options)` where `kwargs` corresponds to any other parameters passed to `minimize` (such as `bracket`, `tol`, etc.), except the `options` dict, which has its contents also passed as `method` parameters pair by pair. The method shall return an *OptimizeResult* object.

The provided `method` callable must be able to accept (and possibly ignore) arbitrary parameters; the set of parameters accepted by `minimize` may expand in future versions and then these parameters will be passed to the method. You can find an example in the `scipy.optimize` tutorial.

New in version 0.11.0.

Examples

Consider the problem of minimizing the following function.

```
>>> def f(x):
...     return (x - 2) * x * (x + 2)**2
```

Using the *Brent* method, we find the local minimum as:

```
>>> from scipy.optimize import minimize_scalar
>>> res = minimize_scalar(f)
>>> res.x
1.28077640403
```

Using the *Bounded* method, we find a local minimum with specified bounds as:

```
>>> res = minimize_scalar(f, bounds=(-3, -1), method='bounded')
>>> res.x
-2.0000002026
```

The `minimize_scalar` function supports the following methods:

minimize_scalar(method='brent')

`scipy.optimize.minimize_scalar` (*fun*, *args=()*, *method='brent'*, *tol=None*, *options={'func': None, 'brack': None, 'xtol': 1.48e-08, 'maxiter': 500}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.minimize_scalar`

Options

maxiter [int] Maximum number of iterations to perform.
xtol [float] Relative error in solution *xopt* acceptable for convergence.

Notes

Uses inverse parabolic interpolation when possible to speed up convergence of golden section method.

minimize_scalar(method='bounded')

`scipy.optimize.minimize_scalar` (*fun*, *bounds=None*, *args=()*, *method='bounded'*, *tol=None*, *options={'func': None, 'xatol': 1e-05, 'maxiter': 500, 'disp': 0}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.minimize_scalar`

Options

maxiter [int] Maximum number of iterations to perform.
disp: int, optional

If non-zero, print messages.

0 : no message printing. 1 : non-convergence notification messages only. 2 : print a message on convergence too. 3 : print iteration results.

xatol [float] Absolute error in solution *xopt* acceptable for convergence.

minimize_scalar(method='golden')

`scipy.optimize.minimize_scalar` (*fun*, *args=()*, *method='golden'*, *tol=None*, *options={'func': None, 'brack': None, 'xtol': 1.4901161193847656e-08, 'maxiter': 5000}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.minimize_scalar`

Options

maxiter [int] Maximum number of iterations to perform.
xtol [float] Relative error in solution *xopt* acceptable for convergence.

Local (multivariate) optimization

<code>minimize</code> (<code>fun</code> , <code>x0</code> [, <code>args</code> , <code>method</code> , <code>jac</code> , <code>hess</code> , ...])	Minimization of scalar function of one or more variables.
--	---

scipy.optimize.minimize

`scipy.optimize.minimize`(`fun`, `x0`, `args=()`, `method=None`, `jac=None`, `hess=None`, `hessp=None`, `bounds=None`, `constraints=()`, `tol=None`, `callback=None`, `options=None`)
 Minimization of scalar function of one or more variables.

Parameters

fun	[callable] The objective function to be minimized. <code>fun(x, *args) -> float</code> where <code>x</code> is an 1-D array with shape <code>(n,)</code> and <code>args</code> is a tuple of the fixed parameters needed to completely specify the function.
x0	[ndarray, shape <code>(n,)</code>] Initial guess. Array of real elements of size <code>(n,)</code> , where ‘n’ is the number of independent variables.
args	[tuple, optional] Extra arguments passed to the objective function and its derivatives (<code>fun</code> , <code>jac</code> and <code>hess</code> functions).
method	[str or callable, optional] Type of solver. Should be one of <ul style="list-style-type: none"> • ‘Nelder-Mead’ (see here) • ‘Powell’ (see here) • ‘CG’ (see here) • ‘BFGS’ (see here) • ‘Newton-CG’ (see here) • ‘L-BFGS-B’ (see here) • ‘TNC’ (see here) • ‘COBYLA’ (see here) • ‘SLSQP’ (see here) • ‘trust-constr’ (see here) • ‘dogleg’ (see here) • ‘trust-ncg’ (see here) • ‘trust-exact’ (see here) • ‘trust-krylov’ (see here) • custom - a callable object (added in version 0.14.0), see below for description. If not given, chosen to be one of BFGS, L-BFGS-B, SLSQP, depending if the problem has constraints or bounds.
jac	[[callable, ‘2-point’, ‘3-point’, ‘cs’, bool], optional] Method for computing the gradient vector. Only for CG, BFGS, Newton-CG, L-BFGS-B, TNC, SLSQP, dogleg, trust-ncg, trust-krylov, trust-exact and trust-constr. If it is a callable, it should be a function that returns the gradient vector: <code>jac(x, *args) -> array_like, shape (n,)</code> where <code>x</code> is an array with shape <code>(n,)</code> and <code>args</code> is a tuple with the fixed parameters. If <code>jac</code> is a Boolean and is True, <code>fun</code> is assumed to return and objective and gradient as an <code>(f, g)</code> tuple. Methods ‘Newton-CG’, ‘trust-ncg’, ‘dogleg’, ‘trust-exact’, and ‘trust-krylov’ require that either a callable be supplied, or that <code>fun</code> return the objective and gradient. If None or False, the gradient will be estimated using 2-point finite difference estimation with an absolute step size. Alternatively, the keywords {‘2-point’, ‘3-point’, ‘cs’} can be used to select a finite difference scheme for numerical estimation of the gradient with a relative step size. These finite difference schemes obey any specified <code>bounds</code> .
hess	[[callable, ‘2-point’, ‘3-point’, ‘cs’, HessianUpdateStrategy], optional] Method for computing the Hessian matrix. Only for Newton-CG, dogleg, trust-ncg, trust-krylov, trust-exact and trust-constr. If it is callable, it should return the Hessian matrix:

`hess(x, *args) -> {LinearOperator, spmatrix, array}, (n, n)`
 where `x` is a `(n,)` ndarray and `args` is a tuple with the fixed parameters. `LinearOperator` and sparse matrix returns are allowed only for 'trust-constr' method. Alternatively, the keywords {'2-point', '3-point', 'cs'} select a finite difference scheme for numerical estimation. Or, objects implementing `HessianUpdateStrategy` interface can be used to approximate the Hessian. Available quasi-Newton methods implementing this interface are:

- `BFGS`;
- `SR1`.

Whenever the gradient is estimated via finite-differences, the Hessian cannot be estimated with options {'2-point', '3-point', 'cs'} and needs to be estimated using one of the quasi-Newton strategies. Finite-difference options {'2-point', '3-point', 'cs'} and `HessianUpdateStrategy` are available only for 'trust-constr' method.

hessp [callable, optional] Hessian of objective function times an arbitrary vector `p`. Only for Newton-CG, trust-ncg, trust-krylov, trust-constr. Only one of `hessp` or `hess` needs to be given. If `hess` is provided, then `hessp` will be ignored. `hessp` must compute the Hessian times an arbitrary vector:

`hessp(x, p, *args) -> ndarray shape (n,)`

where `x` is a `(n,)` ndarray, `p` is an arbitrary vector with dimension `(n,)` and `args` is a tuple with the fixed parameters.

bounds [sequence or `Bounds`, optional] Bounds on variables for L-BFGS-B, TNC, SLSQP, Powell, and trust-constr methods. There are two ways to specify the bounds:

1. Instance of `Bounds` class.
2. Sequence of `(min, max)` pairs for each element in `x`. None is used to specify no bound.

constraints [{Constraint, dict} or List of {Constraint, dict}, optional] Constraints definition (only for COBYLA, SLSQP and trust-constr). Constraints for 'trust-constr' are defined as a single object or a list of objects specifying constraints to the optimization problem. Available constraints are:

- `LinearConstraint`
- `NonlinearConstraint`

Constraints for COBYLA, SLSQP are defined as a list of dictionaries. Each dictionary with fields:

type [str] Constraint type: 'eq' for equality, 'ineq' for inequality.
fun [callable] The function defining the constraint.
jac [callable, optional] The Jacobian of `fun` (only for SLSQP).
args [sequence, optional] Extra arguments to be passed to the function and Jacobian.

Equality constraint means that the constraint function result is to be zero whereas inequality means that it is to be non-negative. Note that COBYLA only supports inequality constraints.

tol [float, optional] Tolerance for termination. For detailed control, use solver-specific options.

options [dict, optional] A dictionary of solver options. All methods accept the following generic options:

maxiter [int] Maximum number of iterations to perform. Depending on the method each iteration may use several function evaluations.

disp [bool] Set to True to print convergence messages.

For method-specific options, see `show_options`.

callback [callable, optional] Called after each iteration. For 'trust-constr' it is a callable with the signature:

`callback(xk, OptimizeResult state) -> bool`

where `xk` is the current parameter vector. and `state` is an `OptimizeResult` object, with the same fields as the ones from the return. If `callback` returns True the algorithm execution is terminated. For all the other methods, the signature is:

`callback(xk)`

where `xk` is the current parameter vector.

Returns

res [OptimizeResult] The optimization result represented as a `OptimizeResult` object. Important attributes are: `x` the solution array, `success` a Boolean flag indicating if the optimizer exited successfully and `message` which describes the cause of the termination. See `OptimizeResult` for a description of other attributes.

See also:**`minimize_scalar`**

Interface to minimization algorithms for scalar univariate functions

`show_options`

Additional options accepted by the solvers

Notes

This section describes the available solvers that can be selected by the ‘method’ parameter. The default method is *BFGS*.

Unconstrained minimization

Method *Nelder-Mead* uses the Simplex algorithm [1], [2]. This algorithm is robust in many applications. However, if numerical computation of derivative can be trusted, other algorithms using the first and/or second derivatives information might be preferred for their better performance in general.

Method *CG* uses a nonlinear conjugate gradient algorithm by Polak and Ribiere, a variant of the Fletcher-Reeves method described in [5] pp.120-122. Only the first derivatives are used.

Method *BFGS* uses the quasi-Newton method of Broyden, Fletcher, Goldfarb, and Shanno (BFGS) [5] pp. 136. It uses the first derivatives only. BFGS has proven good performance even for non-smooth optimizations. This method also returns an approximation of the Hessian inverse, stored as *hess_inv* in the `OptimizeResult` object.

Method *Newton-CG* uses a Newton-CG algorithm [5] pp. 168 (also known as the truncated Newton method). It uses a CG method to compute the search direction. See also *TNC* method for a box-constrained minimization with a similar algorithm. Suitable for large-scale problems.

Method *dogleg* uses the dog-leg trust-region algorithm [5] for unconstrained minimization. This algorithm requires the gradient and Hessian; furthermore the Hessian is required to be positive definite.

Method *trust-ncg* uses the Newton conjugate gradient trust-region algorithm [5] for unconstrained minimization. This algorithm requires the gradient and either the Hessian or a function that computes the product of the Hessian with a given vector. Suitable for large-scale problems.

Method *trust-krylov* uses the Newton GLTR trust-region algorithm [14], [15] for unconstrained minimization. This algorithm requires the gradient and either the Hessian or a function that computes the product of the Hessian with a given vector. Suitable for large-scale problems. On indefinite problems it requires usually less iterations than the *trust-ncg* method and is recommended for medium and large-scale problems.

Method *trust-exact* is a trust-region method for unconstrained minimization in which quadratic subproblems are solved almost exactly [13]. This algorithm requires the gradient and the Hessian (which is *not* required to be positive definite). It is, in many situations, the Newton method to converge in fewer iteration and the most recommended for small and medium-size problems.

Bound-Constrained minimization

Method *L-BFGS-B* uses the L-BFGS-B algorithm [6], [7] for bound constrained minimization.

Method *Powell* is a modification of Powell’s method [3], [4] which is a conjugate direction method. It performs sequential one-dimensional minimizations along each vector of the directions set (*direc* field in *options* and *info*),

which is updated at each iteration of the main minimization loop. The function need not be differentiable, and no derivatives are taken. If bounds are not provided, then an unbounded line search will be used. If bounds are provided and the initial guess is within the bounds, then every function evaluation throughout the minimization procedure will be within the bounds. If bounds are provided, the initial guess is outside the bounds, and *direc* is full rank (default has full rank), then some function evaluations during the first iteration may be outside the bounds, but every function evaluation after the first iteration will be within the bounds. If *direc* is not full rank, then some parameters may not be optimized and the solution is not guaranteed to be within the bounds.

Method *TNC* uses a truncated Newton algorithm [5], [8] to minimize a function with variables subject to bounds. This algorithm uses gradient information; it is also called Newton Conjugate-Gradient. It differs from the *Newton-CG* method described above as it wraps a C implementation and allows each variable to be given upper and lower bounds.

Constrained Minimization

Method *COBYLA* uses the Constrained Optimization BY Linear Approximation (COBYLA) method [9], [10], [11]. The algorithm is based on linear approximations to the objective function and each constraint. The method wraps a FORTRAN implementation of the algorithm. The constraints functions 'fun' may return either a single number or an array or list of numbers.

Method *SLSQP* uses Sequential Least Squares Programming to minimize a function of several variables with any combination of bounds, equality and inequality constraints. The method wraps the SLSQP Optimization subroutine originally implemented by Dieter Kraft [12]. Note that the wrapper handles infinite values in bounds by converting them into large floating values.

Method *trust-constr* is a trust-region algorithm for constrained optimization. It switches between two implementations depending on the problem definition. It is the most versatile constrained minimization algorithm implemented in SciPy and the most appropriate for large-scale problems. For equality constrained problems it is an implementation of Byrd-Omojokun Trust-Region SQP method described in [17] and in [5], p. 549. When inequality constraints are imposed as well, it switches to the trust-region interior point method described in [16]. This interior point algorithm, in turn, solves inequality constraints by introducing slack variables and solving a sequence of equality-constrained barrier problems for progressively smaller values of the barrier parameter. The previously described equality constrained SQP method is used to solve the subproblems with increasing levels of accuracy as the iterate gets closer to a solution.

Finite-Difference Options

For Method *trust-constr* the gradient and the Hessian may be approximated using three finite-difference schemes: {'2-point', '3-point', 'cs'}. The scheme 'cs' is, potentially, the most accurate but it requires the function to correctly handles complex inputs and to be differentiable in the complex plane. The scheme '3-point' is more accurate than '2-point' but requires twice as many operations.

Custom minimizers

It may be useful to pass a custom minimization method, for example when using a frontend to this method such as `scipy.optimize.basinhopping` or a different library. You can simply pass a callable as the `method` parameter.

The callable is called as `method(fun, x0, args, **kwargs, **options)` where `kwargs` corresponds to any other parameters passed to `minimize` (such as `callback`, `hess`, etc.), except the `options` dict, which has its contents also passed as `method` parameters pair by pair. Also, if `jac` has been passed as a bool type, `jac` and `fun` are mangled so that `fun` returns just the function values and `jac` is converted to a function returning the Jacobian. The method shall return an `OptimizeResult` object.

The provided `method` callable must be able to accept (and possibly ignore) arbitrary parameters; the set of parameters accepted by `minimize` may expand in future versions and then these parameters will be passed to the method. You can find an example in the `scipy.optimize` tutorial.

New in version 0.11.0.

References

[1], [2], [3], [4], [5], [6], [7], [8], [9], [10], [11], [12], [13], [14], [15], [16], [17]

Examples

Let us consider the problem of minimizing the Rosenbrock function. This function (and its respective derivatives) is implemented in `rosen` (resp. `rosen_der`, `rosen_hess`) in the `scipy.optimize`.

```
>>> from scipy.optimize import minimize, rosen, rosen_der
```

A simple application of the *Nelder-Mead* method is:

```
>>> x0 = [1.3, 0.7, 0.8, 1.9, 1.2]
>>> res = minimize(rosen, x0, method='Nelder-Mead', tol=1e-6)
>>> res.x
array([ 1.,  1.,  1.,  1.,  1.])
```

Now using the *BFGS* algorithm, using the first derivative and a few options:

```
>>> res = minimize(rosen, x0, method='BFGS', jac=rosen_der,
...               options={'gtol': 1e-6, 'disp': True})
Optimization terminated successfully.
    Current function value: 0.000000
    Iterations: 26
    Function evaluations: 31
    Gradient evaluations: 31
>>> res.x
array([ 1.,  1.,  1.,  1.,  1.])
>>> print(res.message)
Optimization terminated successfully.
>>> res.hess_inv
array([[ 0.00749589,  0.01255155,  0.02396251,  0.04750988,  0.09495377],
       # may vary
       [ 0.01255155,  0.02510441,  0.04794055,  0.09502834,  0.18996269],
       [ 0.02396251,  0.04794055,  0.09631614,  0.19092151,  0.38165151],
       [ 0.04750988,  0.09502834,  0.19092151,  0.38341252,  0.7664427 ],
       [ 0.09495377,  0.18996269,  0.38165151,  0.7664427,  1.53713523]])
```

Next, consider a minimization problem with several constraints (namely Example 16.4 from [5]). The objective function is:

```
>>> fun = lambda x: (x[0] - 1)**2 + (x[1] - 2.5)**2
```

There are three constraints defined as:

```
>>> cons = ({'type': 'ineq', 'fun': lambda x: x[0] - 2 * x[1] + 2},
...        {'type': 'ineq', 'fun': lambda x: -x[0] - 2 * x[1] + 6},
...        {'type': 'ineq', 'fun': lambda x: -x[0] + 2 * x[1] + 2})
```

And variables must be positive, hence the following bounds:

```
>>> bnds = ((0, None), (0, None))
```

The optimization problem is solved using the SLSQP method as:

```
>>> res = minimize(fun, (2, 0), method='SLSQP', bounds=bnds,
...               constraints=cons)
```

It should converge to the theoretical solution (1.4,1.7).

The `minimize` function supports the following methods:

minimize(method='Nelder-Mead')

```
scipy.optimize.minimize (fun, x0, args=(), method='Nelder-Mead', tol=None, callback=None, options={'func': None, 'maxiter': None, 'maxfev': None, 'disp': False, 'return_all': False, 'initial_simplex': None, 'xatol': 0.0001, 'fatol': 0.0001, 'adaptive': False})
```

Minimization of scalar function of one or more variables using the Nelder-Mead algorithm.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.minimize`

Options

- disp** [bool] Set to True to print convergence messages.
- maxiter, maxfev** [int] Maximum allowed number of iterations and function evaluations. Will default to $N*200$, where N is the number of variables, if neither `maxiter` or `maxfev` is set. If both `maxiter` and `maxfev` are set, minimization will stop at the first reached.
- return_all** [bool, optional] Set to True to return a list of the best solution at each of the iterations.
- initial_simplex** [array_like of shape (N + 1, N)] Initial simplex. If given, overrides `x0`. `initial_simplex[j, :]` should contain the coordinates of the j th vertex of the $N+1$ vertices in the simplex, where N is the dimension.
- xatol** [float, optional] Absolute error in `xopt` between iterations that is acceptable for convergence.
- fatol** [number, optional] Absolute error in `func(xopt)` between iterations that is acceptable for convergence.
- adaptive** [bool, optional] Adapt algorithm parameters to dimensionality of problem. Useful for high-dimensional minimization [1].

References

[1]

minimize(method='Powell')

```
scipy.optimize.minimize (fun, x0, args=(), method='Powell', bounds=None, tol=None, callback=None, options={'func': None, 'xtol': 0.0001, 'ftol': 0.0001, 'maxiter': None, 'maxfev': None, 'disp': False, 'direc': None, 'return_all': False})
```

Minimization of scalar function of one or more variables using the modified Powell algorithm.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.minimize`

Options

- disp** [bool] Set to True to print convergence messages.
- xtol** [float] Relative error in solution `xopt` acceptable for convergence.

ftol [float] Relative error in `fun(xopt)` acceptable for convergence.

maxiter, maxfev [int] Maximum allowed number of iterations and function evaluations. Will default to $N*1000$, where N is the number of variables, if neither `maxiter` or `maxfev` is set. If both `maxiter` and `maxfev` are set, minimization will stop at the first reached.

direc [ndarray] Initial set of direction vectors for the Powell method.

return_all [bool, optional] Set to True to return a list of the best solution at each of the iterations.

bounds [*Bounds*] If bounds are not provided, then an unbounded line search will be used. If bounds are provided and the initial guess is within the bounds, then every function evaluation throughout the minimization procedure will be within the bounds. If bounds are provided, the initial guess is outside the bounds, and `direc` is full rank (or left to default), then some function evaluations during the first iteration may be outside the bounds, but every function evaluation after the first iteration will be within the bounds. If `direc` is not full rank, then some parameters may not be optimized and the solution is not guaranteed to be within the bounds.

return_all [bool, optional] Set to True to return a list of the best solution at each of the iterations.

minimize(method='CG')

`scipy.optimize.minimize` (*fun*, *x0*, *args=()*, *method='CG'*, *jac=None*, *tol=None*, *callback=None*, *options={'gtol': 1e-05, 'norm': inf, 'eps': 1.4901161193847656e-08, 'maxiter': None, 'disp': False, 'return_all': False, 'finite_diff_rel_step': None}*)

Minimization of scalar function of one or more variables using the conjugate gradient algorithm.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.minimize`

Options

disp [bool] Set to True to print convergence messages.

maxiter [int] Maximum number of iterations to perform.

gtol [float] Gradient norm must be less than `gtol` before successful termination.

norm [float] Order of norm (Inf is max, -Inf is min).

eps [float or ndarray] If `jac` is `None` the absolute step size used for numerical approximation of the jacobian via forward differences.

return_all [bool, optional] Set to True to return a list of the best solution at each of the iterations.

finite_diff_rel_step [None or array_like, optional] If `jac` in [`'2-point'`, `'3-point'`, `'cs'`] the relative step size to use for numerical approximation of the jacobian. The absolute step size is computed as $h = \text{rel_step} * \text{sign}(x0) * \max(1, \text{abs}(x0))$, possibly adjusted to fit into the bounds. For `method='3-point'` the sign of `h` is ignored. If `None` (default) then step is selected automatically.

minimize(method='BFGS')

`scipy.optimize.minimize` (*fun*, *x0*, *args=()*, *method='BFGS'*, *jac=None*, *tol=None*, *callback=None*, *options={'gtol': 1e-05, 'norm': inf, 'eps': 1.4901161193847656e-08, 'maxiter': None, 'disp': False, 'return_all': False, 'finite_diff_rel_step': None}*)

Minimization of scalar function of one or more variables using the BFGS algorithm.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.minimize`

Options

disp [bool] Set to True to print convergence messages.

maxiter [int] Maximum number of iterations to perform.
gtol [float] Gradient norm must be less than *gtol* before successful termination.
norm [float] Order of norm (Inf is max, -Inf is min).
eps [float or ndarray] If *jac* is *None* the absolute step size used for numerical approximation of the jacobian via forward differences.
return_all [bool, optional] Set to True to return a list of the best solution at each of the iterations.
finite_diff_rel_step [None or array_like, optional] If *jac* in [*2-point*, *3-point*, *cs*] the relative step size to use for numerical approximation of the jacobian. The absolute step size is computed as $h = \text{rel_step} * \text{sign}(x_0) * \max(1, \text{abs}(x_0))$, possibly adjusted to fit into the bounds. For *method='3-point'* the sign of *h* is ignored. If *None* (default) then step is selected automatically.

minimize(method='Newton-CG')

```

scipy.optimize.minimize(fun, x0, args=(), method='Newton-CG', jac=None, hess=None,
                        hessp=None, tol=None, callback=None, options={'xtol': 1e-05, 'eps':
                        1.4901161193847656e-08, 'maxiter': None, 'disp': False, 'return_all':
                        False})
    
```

Minimization of scalar function of one or more variables using the Newton-CG algorithm.

Note that the *jac* parameter (Jacobian) is required.

See also:

For documentation for the rest of the parameters, see [scipy.optimize.minimize](#)

Options

disp [bool] Set to True to print convergence messages.
xtol [float] Average relative error in solution *xopt* acceptable for convergence.
maxiter [int] Maximum number of iterations to perform.
eps [float or ndarray] If *hessp* is approximated, use this value for the step size.
return_all [bool, optional] Set to True to return a list of the best solution at each of the iterations.

minimize(method='L-BFGS-B')

```

scipy.optimize.minimize(fun, x0, args=(), method='L-BFGS-B', jac=None, bounds=None,
                        tol=None, callback=None, options={'disp': None, 'maxcor': 10, 'ftol':
                        2.220446049250313e-09, 'gtol': 1e-05, 'eps': 1e-08, 'maxfun': 15000,
                        'maxiter': 15000, 'iprint': -1, 'maxls': 20, 'finite_diff_rel_step': None})
    
```

Minimize a scalar function of one or more variables using the L-BFGS-B algorithm.

See also:

For documentation for the rest of the parameters, see [scipy.optimize.minimize](#)

Options

disp [None or int] If *disp* is *None* (the default), then the supplied version of *iprint* is used. If *disp* is not *None*, then it overrides the supplied version of *iprint* with the behaviour you outlined.
maxcor [int] The maximum number of variable metric corrections used to define the limited memory matrix. (The limited memory BFGS method does not store the full hessian but uses this many terms in an approximation to it.)
ftol [float] The iteration stops when $(f^k - f^{k+1}) / \max\{|f^k|, |f^{k+1}|, 1\} \leq \text{ftol}$.
gtol [float] The iteration will stop when $\max\{|\text{proj } g_i | i = 1, \dots, n\} \leq \text{gtol}$ where *pg_i* is the *i*-th component of the projected gradient.

eps	[float or ndarray] If <i>jac</i> is <i>None</i> the absolute step size used for numerical approximation of the jacobian via forward differences.
maxfun	[int] Maximum number of function evaluations.
maxiter	[int] Maximum number of iterations.
iprint	[int, optional] Controls the frequency of output. <code>iprint < 0</code> means no output; <code>iprint = 0</code> print only one line at the last iteration; <code>0 < iprint < 99</code> print also <code>f</code> and <code> proj g </code> every <code>iprint</code> iterations; <code>iprint = 99</code> print details of every iteration except <code>n</code> -vectors; <code>iprint = 100</code> print also the changes of active set and final <code>x</code> ; <code>iprint > 100</code> print details of every iteration including <code>x</code> and <code>g</code> .
callback	[callable, optional] Called after each iteration, as <code>callback(xk)</code> , where <code>xk</code> is the current parameter vector.
maxls	[int, optional] Maximum number of line search steps (per iteration). Default is 20.
finite_diff_rel_step	[None or array_like, optional] If <i>jac</i> in [<i>'2-point'</i> , <i>'3-point'</i> , <i>'cs'</i>] the relative step size to use for numerical approximation of the jacobian. The absolute step size is computed as <code>h = rel_step * sign(x0) * max(1, abs(x0))</code> , possibly adjusted to fit into the bounds. For <code>method='3-point'</code> the sign of <i>h</i> is ignored. If <i>None</i> (default) then step is selected automatically.

Notes

The option *ftol* is exposed via the `scipy.optimize.minimize` interface, but calling `scipy.optimize.fmin_l_bfgs_b` directly exposes *factr*. The relationship between the two is `ftol = factr * numpy.finfo(float).eps`. I.e., *factr* multiplies the default machine floating-point precision to arrive at *ftol*.

minimize(method='TNC')

```
scipy.optimize.minimize(fun, x0, args=(), method='TNC', jac=None, bounds=None, tol=None,
                       callback=None, options={'eps': 1e-08, 'scale': None, 'offset': None, 'mesg_num':
                                               None, 'maxCGit': -1, 'maxiter': None, 'eta': -1, 'stepmx': 0, 'accuracy': 0,
                                               'minfev': 0, 'ftol': -1, 'xtol': -1, 'gtol': -1, 'rescale': -1, 'disp': False,
                                               'finite_diff_rel_step': None, 'maxfun': None})
```

Minimize a scalar function of one or more variables using a truncated Newton (TNC) algorithm.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.minimize`

Options

eps	[float or ndarray] If <i>jac</i> is <i>None</i> the absolute step size used for numerical approximation of the jacobian via forward differences.
scale	[list of floats] Scaling factors to apply to each variable. If <i>None</i> , the factors are up-low for interval bounded variables and <code>1+ x </code> fo the others. Defaults to <i>None</i> .
offset	[float] Value to subtract from each variable. If <i>None</i> , the offsets are <code>(up+low)/2</code> for interval bounded variables and <code>x</code> for the others.
disp	[bool] Set to <i>True</i> to print convergence messages.
maxCGit	[int] Maximum number of <code>hessian*vector</code> evaluations per main iteration. If <code>maxCGit == 0</code> , the direction chosen is <code>-gradient</code> if <code>maxCGit < 0</code> , <code>maxCGit</code> is set to <code>max(1, min(50, n/2))</code> . Defaults to <code>-1</code> .
maxiter	[int, optional] Maximum number of function evaluations. This keyword is deprecated in favor of <i>maxfun</i> . Only if <i>maxfun</i> is <i>None</i> is this keyword used.
eta	[float] Severity of the line search. If <code>< 0</code> or <code>> 1</code> , set to <code>0.25</code> . Defaults to <code>-1</code> .
stepmx	[float] Maximum step for the line search. May be increased during call. If too small, it will be set to <code>10.0</code> . Defaults to <code>0</code> .

accuracy	[float] Relative precision for finite difference calculations. If \leq machine_precision, set to $\sqrt{\text{machine_precision}}$. Defaults to 0.
minfev	[float] Minimum function value estimate. Defaults to 0.
ftol	[float] Precision goal for the value of f in the stopping criterion. If $\text{ftol} < 0.0$, ftol is set to 0.0 defaults to -1.
xtol	[float] Precision goal for the value of x in the stopping criterion (after applying x scaling factors). If $\text{xtol} < 0.0$, xtol is set to $\sqrt{\text{machine_precision}}$. Defaults to -1.
gtol	[float] Precision goal for the value of the projected gradient in the stopping criterion (after applying x scaling factors). If $\text{gtol} < 0.0$, gtol is set to $1e-2 * \sqrt{\text{accuracy}}$. Setting it to 0.0 is not recommended. Defaults to -1.
rescale	[float] Scaling factor (in log10) used to trigger f value rescaling. If 0, rescale at each iteration. If a large value, never rescale. If < 0 , rescale is set to 1.3.
finite_diff_rel_step	[None or array_like, optional] If <i>jac</i> in ['2-point', '3-point', 'cs'] the relative step size to use for numerical approximation of the jacobian. The absolute step size is computed as $h = \text{rel_step} * \text{sign}(x_0) * \max(1, \text{abs}(x_0))$, possibly adjusted to fit into the bounds. For <i>method</i> ='3-point' the sign of <i>h</i> is ignored. If None (default) then step is selected automatically.
maxfun	[int] Maximum number of function evaluations. If None, <i>maxfun</i> is set to $\max(100, 10 * \text{len}(x_0))$. Defaults to None.

minimize(method='COBYLA')

```
scipy.optimize.minimize(fun, x0, args=(), method='COBYLA', constraints=(), tol=None, callback=None, options={'rhobeg': 1.0, 'maxiter': 1000, 'disp': False, 'catol': 0.0002})
```

Minimize a scalar function of one or more variables using the Constrained Optimization BY Linear Approximation (COBYLA) algorithm.

See also:

For documentation for the rest of the parameters, see [scipy.optimize.minimize](#)

Options

rhobeg	[float] Reasonable initial changes to the variables.
tol	[float] Final accuracy in the optimization (not precisely guaranteed). This is a lower bound on the size of the trust region.
disp	[bool] Set to True to print convergence messages. If False, <i>verbosity</i> is ignored as set to 0.
maxiter	[int] Maximum number of function evaluations.
catol	[float] Tolerance (absolute) for constraint violations

minimize(method='SLSQP')

```
scipy.optimize.minimize(fun, x0, args=(), method='SLSQP', jac=None, bounds=None, constraints=(), tol=None, callback=None, options={'func': None, 'maxiter': 100, 'ftol': 1e-06, 'iprint': 1, 'disp': False, 'eps': 1.4901161193847656e-08, 'finite_diff_rel_step': None})
```

Minimize a scalar function of one or more variables using Sequential Least Squares Programming (SLSQP).

See also:

For documentation for the rest of the parameters, see [scipy.optimize.minimize](#)

Options

ftol	[float] Precision goal for the value of f in the stopping criterion.
eps	[float] Step size used for numerical approximation of the Jacobian.

disp [bool] Set to True to print convergence messages. If False, *verbosity* is ignored and set to 0.

maxiter [int] Maximum number of iterations.

finite_diff_rel_step
 [None or array_like, optional] If *jac* in ['2-point', '3-point', 'cs'] the relative step size to use for numerical approximation of *jac*. The absolute step size is computed as $h = \text{rel_step} * \text{sign}(x_0) * \max(1, \text{abs}(x_0))$, possibly adjusted to fit into the bounds. For *method*='3-point' the sign of *h* is ignored. If None (default) then step is selected automatically.

minimize(method='trust-constr')

```
scipy.optimize.minimize(fun, x0, args=(), method='trust-constr', hess=None, hessp=None,
                        bounds=None, constraints=(), tol=None, callback=None, options={'grad':
                        None, 'xtol': 1e-08, 'gtol': 1e-08, 'barrier_tol': 1e-08, 'sparse_jacobian':
                        None, 'maxiter': 1000, 'verbose': 0, 'finite_diff_rel_step': None, 'initial_constr_penalty':
                        1.0, 'initial_tr_radius': 1.0, 'initial_barrier_parameter':
                        0.1, 'initial_barrier_tolerance': 0.1, 'factorization_method': None, 'disp':
                        False})
```

Minimize a scalar function subject to constraints.

Parameters

gtol [float, optional] Tolerance for termination by the norm of the Lagrangian gradient. The algorithm will terminate when both the infinity norm (i.e., max abs value) of the Lagrangian gradient and the constraint violation are smaller than *gtol*. Default is 1e-8.

xtol [float, optional] Tolerance for termination by the change of the independent variable. The algorithm will terminate when *tr_radius* < *xtol*, where *tr_radius* is the radius of the trust region used in the algorithm. Default is 1e-8.

barrier_tol
 [float, optional] Threshold on the barrier parameter for the algorithm termination. When inequality constraints are present, the algorithm will terminate only when the barrier parameter is less than *barrier_tol*. Default is 1e-8.

sparse_jacobian
 [{bool, None}, optional] Determines how to represent Jacobians of the constraints. If bool, then Jacobians of all the constraints will be converted to the corresponding format. If None (default), then Jacobians won't be converted, but the algorithm can proceed only if they all have the same format.

initial_tr_radius: float, optional

Initial trust radius. The trust radius gives the maximum distance between solution points in consecutive iterations. It reflects the trust the algorithm puts in the local approximation of the optimization problem. For an accurate local approximation the trust-region should be large and for an approximation valid only close to the current point it should be a small one. The trust radius is automatically updated throughout the optimization process, with *initial_tr_radius* being its initial value. Default is 1 (recommended in [1], p. 19).

initial_constr_penalty

[float, optional] Initial constraints penalty parameter. The penalty parameter is used for balancing the requirements of decreasing the objective function and satisfying the constraints. It is used for defining the merit function: $\text{merit_function}(x) = \text{fun}(x) + \text{constr_penalty} * \text{constr_norm_l2}(x)$, where $\text{constr_norm_l2}(x)$ is the l2 norm of a vector containing all the constraints. The merit function is used for accepting or rejecting trial points and *constr_penalty* weights the two conflicting goals of reducing objective function and constraints. The penalty is automatically updated throughout the optimization process, with *initial_constr_penalty* being its initial value. Default is 1 (recommended in [1], p 19).

initial_barrier_parameter, initial_barrier_tolerance: float, optional

Initial barrier parameter and initial tolerance for the barrier subproblem. Both are used only when inequality constraints are present. For dealing with optimization problems $\min_x f(x)$ subject to inequality constraints $c(x) \leq 0$ the algorithm introduces slack variables, solving the problem $\min_{(x,s)} f(x) + \text{barrier_parameter} * \sum(\ln(s))$ subject to the equality constraints $c(x) + s = 0$ instead of the original problem. This subproblem is solved for decreasing values of `barrier_parameter` and with decreasing tolerances for the termination, starting with `initial_barrier_parameter` for the barrier parameter and `initial_barrier_tolerance` for the barrier tolerance. Default is 0.1 for both values (recommended in [1] p. 19). Also note that `barrier_parameter` and `barrier_tolerance` are updated with the same prefactor.

factorization_method

[string or None, optional] Method to factorize the Jacobian of the constraints. Use None (default) for the auto selection or one of:

- 'NormalEquation' (requires scikit-sparse)
- 'AugmentedSystem'
- 'QRFactorization'
- 'SVDFactorization'

The methods 'NormalEquation' and 'AugmentedSystem' can be used only with sparse constraints. The projections required by the algorithm will be computed using, respectively, the the normal equation and the augmented system approaches explained in [1]. 'NormalEquation' computes the Cholesky factorization of $A^T A$ and 'AugmentedSystem' performs the LU factorization of an augmented system. They usually provide similar results. 'AugmentedSystem' is used by default for sparse matrices.

The methods 'QRFactorization' and 'SVDFactorization' can be used only with dense constraints. They compute the required projections using, respectively, QR and SVD factorizations. The 'SVDFactorization' method can cope with Jacobian matrices with deficient row rank and will be used whenever other factorization methods fail (which may imply the conversion of sparse matrices to a dense format when required). By default, 'QRFactorization' is used for dense matrices.

finite_diff_rel_step

[None or array_like, optional] Relative step size for the finite difference approximation.

maxiter [int, optional] Maximum number of algorithm iterations. Default is 1000.

verbose [{0, 1, 2}, optional] Level of algorithm's verbosity:

- 0 (default) : work silently.
- 1 : display a termination report.
- 2 : display progress during iterations.
- 3 : display progress during iterations (more complete report).

disp [bool, optional] If True (default), then `verbose` will be set to 1 if it was 0.

Returns

OptimizeResult with the fields documented below. Note the following:

1. All values corresponding to the constraints are ordered as they were passed to the solver. And values corresponding to *bounds* constraints are put *after* other constraints.
2. All numbers of function, Jacobian or Hessian evaluations correspond to numbers of actual Python function calls. It means, for example, that if a Jacobian is estimated by finite differences, then the number of Jacobian evaluations will be zero and the number of function evaluations will be incremented by all calls during the finite difference estimation.

x [ndarray, shape (n,)] Solution found.

optimality [float] Infinity norm of the Lagrangian gradient at the solution.

constr_violation

[float] Maximum constraint violation at the solution.

fun [float] Objective function at the solution.

grad [ndarray, shape (n,)] Gradient of the objective function at the solution.

lagrangian_grad	[ndarray, shape (n,)] Gradient of the Lagrangian function at the solution.
nit	[int] Total number of iterations.
nfev	[integer] Number of the objective function evaluations.
njev	[integer] Number of the objective function gradient evaluations.
nhev	[integer] Number of the objective function Hessian evaluations.
cg_niter	[int] Total number of the conjugate gradient method iterations.
method	[{'equality_constrained_sqp', 'tr_interior_point'}] Optimization method used.
constr	[list of ndarray] List of constraint values at the solution.
jac	[list of {ndarray, sparse matrix}] List of the Jacobian matrices of the constraints at the solution.
v	[list of ndarray] List of the Lagrange multipliers for the constraints at the solution. For an inequality constraint a positive multiplier means that the upper bound is active, a negative multiplier means that the lower bound is active and if a multiplier is zero it means the constraint is not active.
constr_nfev	[list of int] Number of constraint evaluations for each of the constraints.
constr_njev	[list of int] Number of Jacobian matrix evaluations for each of the constraints.
constr_nhev	[list of int] Number of Hessian evaluations for each of the constraints.
tr_radius	[float] Radius of the trust region at the last iteration.
constr_penalty	[float] Penalty parameter at the last iteration, see <i>initial_constr_penalty</i> .
barrier_tolerance	[float] Tolerance for the barrier subproblem at the last iteration. Only for problems with inequality constraints.
barrier_parameter	[float] Barrier parameter at the last iteration. Only for problems with inequality constraints.
execution_time	[float] Total execution time.
message	[str] Termination message.
status	[{0, 1, 2, 3}] Termination status: <ul style="list-style-type: none"> • 0 : The maximum number of function evaluations is exceeded. • 1 : <i>gtol</i> termination condition is satisfied. • 2 : <i>xtol</i> termination condition is satisfied. • 3 : <i>callback</i> function requested termination.
cg_stop_cond	[int] Reason for CG subproblem termination at the last iteration: <ul style="list-style-type: none"> • 0 : CG subproblem not evaluated. • 1 : Iteration limit was reached. • 2 : Reached the trust-region boundary. • 3 : Negative curvature detected. • 4 : Tolerance was satisfied.

References

[1]

`minimize(method='dogleg')`

`scipy.optimize.minimize` (*fun*, *x0*, *args=()*, *method='dogleg'*, *jac=None*, *hess=None*, *tol=None*, *callback=None*, *options={}*)

Minimization of scalar function of one or more variables using the dog-leg trust-region algorithm.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.minimize`

Options

initial_trust_radius

[float] Initial trust-region radius.

max_trust_radius

[float] Maximum value of the trust-region radius. No steps that are longer than this value will be proposed.

eta [float] Trust region related acceptance stringency for proposed steps.

gtol [float] Gradient norm must be less than *gtol* before successful termination.

`minimize(method='trust-ncg')`

`scipy.optimize.minimize` (*fun*, *x0*, *args=()*, *method='trust-ncg'*, *jac=None*, *hess=None*, *hessp=None*, *tol=None*, *callback=None*, *options={}*)

Minimization of scalar function of one or more variables using the Newton conjugate gradient trust-region algorithm.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.minimize`

Options

initial_trust_radius

[float] Initial trust-region radius.

max_trust_radius

[float] Maximum value of the trust-region radius. No steps that are longer than this value will be proposed.

eta [float] Trust region related acceptance stringency for proposed steps.

gtol [float] Gradient norm must be less than *gtol* before successful termination.

`minimize(method='trust-krylov')`

`scipy.optimize.minimize` (*fun*, *x0*, *args=()*, *method='trust-krylov'*, *jac=None*, *hess=None*, *hessp=None*, *tol=None*, *callback=None*, *options={'inexact': True}*)

Minimization of a scalar function of one or more variables using a nearly exact trust-region algorithm that only requires matrix vector products with the hessian matrix.

New in version 1.0.0.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.minimize`

Options

inexact [bool, optional] Accuracy to solve subproblems. If True requires less nonlinear iterations, but more vector products.

minimize(method='trust-exact')

`scipy.optimize.minimize` (*fun*, *x0*, *args=()*, *method='trust-exact'*, *jac=None*, *hess=None*, *tol=None*, *callback=None*, *options={}*)

Minimization of scalar function of one or more variables using a nearly exact trust-region algorithm.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.minimize`

Options

initial_tr_radius

[float] Initial trust-region radius.

max_tr_radius

[float] Maximum value of the trust-region radius. No steps that are longer than this value will be proposed.

eta

[float] Trust region related acceptance stringency for proposed steps.

gtol

[float] Gradient norm must be less than `gtol` before successful termination.

Constraints are passed to `minimize` function as a single object or as a list of objects from the following classes:

<code>NonlinearConstraint</code> (<i>fun</i> , <i>lb</i> , <i>ub</i> [, <i>jac</i> , ...])	Nonlinear constraint on the variables.
<code>LinearConstraint</code> (<i>A</i> , <i>lb</i> , <i>ub</i> [, <i>keep_feasible</i>])	Linear constraint on the variables.

scipy.optimize.NonlinearConstraint

```
class scipy.optimize.NonlinearConstraint(fun, lb, ub, jac='2-point',
                                         hess=<scipy.optimize._hessian_update_strategy.BFGS
                                         object>, keep_feasible=False, finite_diff_rel_step=None,
                                         finite_diff_jac_sparsity=None)
```

Nonlinear constraint on the variables.

The constraint has the general inequality form:

$$lb \leq fun(x) \leq ub$$

Here the vector of independent variables *x* is passed as ndarray of shape (n,) and *fun* returns a vector with *m* components.

It is possible to use equal bounds to represent an equality constraint or infinite bounds to represent a one-sided constraint.

Parameters

fun [callable] The function defining the constraint. The signature is `fun(x) -> array_like, shape (m,)`.

lb, ub [array_like] Lower and upper bounds on the constraint. Each array must have the shape (m,) or be a scalar, in the latter case a bound will be the same for all components of the constraint. Use `np.inf` with an appropriate sign to specify a one-sided constraint. Set components of *lb* and *ub* equal to represent an equality constraint. Note that you can mix constraints of different types: interval, one-sided or equality, by setting different components of *lb* and *ub* as necessary.

- jac** [{callable, '2-point', '3-point', 'cs'}, optional] Method of computing the Jacobian matrix (an m -by- n matrix, where element (i, j) is the partial derivative of $f[i]$ with respect to $x[j]$). The keywords {'2-point', '3-point', 'cs'} select a finite difference scheme for the numerical estimation. A callable must have the following signature: `jac(x) -> {ndarray, sparse matrix}, shape (m, n)`. Default is '2-point'.
- hess** [{callable, '2-point', '3-point', 'cs', HessianUpdateStrategy, None}, optional] Method for computing the Hessian matrix. The keywords {'2-point', '3-point', 'cs'} select a finite difference scheme for numerical estimation. Alternatively, objects implementing `HessianUpdateStrategy` interface can be used to approximate the Hessian. Currently available implementations are:
- *BFGS* (default option)
 - *SR1*
- A callable must return the Hessian matrix of `dot(fun, v)` and must have the following signature: `hess(x, v) -> {LinearOperator, sparse matrix, array_like}, shape (n, n)`. Here v is ndarray with shape $(m,)$ containing Lagrange multipliers.
- keep_feasible** [array_like of bool, optional] Whether to keep the constraint components feasible throughout iterations. A single value set this property for all components. Default is False. Has no effect for equality constraints.
- finite_diff_rel_step: None or array_like, optional**
Relative step size for the finite difference approximation. Default is None, which will select a reasonable value automatically depending on a finite difference scheme.
- finite_diff_jac_sparsity: {None, array_like, sparse matrix}, optional**
Defines the sparsity structure of the Jacobian matrix for finite difference estimation, its shape must be (m, n) . If the Jacobian has only few non-zero elements in *each* row, providing the sparsity structure will greatly speed up the computations. A zero entry means that a corresponding element in the Jacobian is identically zero. If provided, forces the use of 'lsmr' trust-region solver. If None (default) then dense differencing will be used.

Notes

Finite difference schemes {'2-point', '3-point', 'cs'} may be used for approximating either the Jacobian or the Hessian. We, however, do not allow its use for approximating both simultaneously. Hence whenever the Jacobian is estimated via finite-differences, we require the Hessian to be estimated using one of the quasi-Newton strategies.

The scheme 'cs' is potentially the most accurate, but requires the function to correctly handles complex inputs and be analytically continuable to the complex plane. The scheme '3-point' is more accurate than '2-point' but requires twice as many operations.

Examples

Constrain $x[0] < \sin(x[1]) + 1.9$

```
>>> from scipy.optimize import NonlinearConstraint
>>> con = lambda x: x[0] - np.sin(x[1])
>>> nlc = NonlinearConstraint(con, -np.inf, 1.9)
```

scipy.optimize.LinearConstraint

class `scipy.optimize.LinearConstraint` (*A, lb, ub, keep_feasible=False*)

Linear constraint on the variables.

The constraint has the general inequality form:

$$lb \leq A \cdot x \leq ub$$

Here the vector of independent variables *x* is passed as ndarray of shape (n,) and the matrix *A* has shape (m, n).

It is possible to use equal bounds to represent an equality constraint or infinite bounds to represent a one-sided constraint.

Parameters

- A** [{array_like, sparse matrix}, shape (m, n)] Matrix defining the constraint.
- lb, ub** [array_like] Lower and upper bounds on the constraint. Each array must have the shape (m,) or be a scalar, in the latter case a bound will be the same for all components of the constraint. Use `np.inf` with an appropriate sign to specify a one-sided constraint. Set components of *lb* and *ub* equal to represent an equality constraint. Note that you can mix constraints of different types: interval, one-sided or equality, by setting different components of *lb* and *ub* as necessary.
- keep_feasible** [array_like of bool, optional] Whether to keep the constraint components feasible throughout iterations. A single value set this property for all components. Default is False. Has no effect for equality constraints.

Simple bound constraints are handled separately and there is a special class for them:

<code>Bounds(lb, ub[, keep_feasible])</code>	Bounds constraint on the variables.
--	-------------------------------------

scipy.optimize.Bounds

class `scipy.optimize.Bounds` (*lb, ub, keep_feasible=False*)

Bounds constraint on the variables.

The constraint has the general inequality form:

$$lb \leq x \leq ub$$

It is possible to use equal bounds to represent an equality constraint or infinite bounds to represent a one-sided constraint.

Parameters

- lb, ub** [array_like, optional] Lower and upper bounds on independent variables. Each array must have the same size as *x* or be a scalar, in which case a bound will be the same for all the variables. Set components of *lb* and *ub* equal to fix a variable. Use `np.inf` with an appropriate sign to disable bounds on all or some variables. Note that you can mix constraints of different types: interval, one-sided or equality, by setting different components of *lb* and *ub* as necessary.
- keep_feasible** [array_like of bool, optional] Whether to keep the constraint components feasible throughout iterations. A single value set this property for all components. Default is False. Has no effect for equality constraints.

Quasi-Newton strategies implementing `HessianUpdateStrategy` interface can be used to approximate the Hessian in `minimize` function (available only for the 'trust-constr' method). Available quasi-Newton methods implementing this

interface are:

<code>BFGS(exception_strategy, min_curvature, ...)</code>	Broyden-Fletcher-Goldfarb-Shanno (BFGS) Hessian update strategy.
<code>SR1([min_denominator, init_scale])</code>	Symmetric-rank-1 Hessian update strategy.

scipy.optimize.BFGS

class `scipy.optimize.BFGS` (*exception_strategy*='skip_update', *min_curvature*=None, *init_scale*='auto')
 Broyden-Fletcher-Goldfarb-Shanno (BFGS) Hessian update strategy.

Parameters

exception_strategy

[['skip_update', 'damp_update'], optional] Define how to proceed when the curvature condition is violated. Set it to 'skip_update' to just skip the update. Or, alternatively, set it to 'damp_update' to interpolate between the actual BFGS result and the unmodified matrix. Both exceptions strategies are explained in [1], p.536-537.

min_curvature

[float] This number, scaled by a normalization factor, defines the minimum curvature $\text{dot}(\text{delta_grad}, \text{delta_x})$ allowed to go unaffected by the exception strategy. By default is equal to $1e-8$ when `exception_strategy = 'skip_update'` and equal to 0.2 when `exception_strategy = 'damp_update'`.

init_scale

[[float, 'auto']] Matrix scale at first iteration. At the first iteration the Hessian matrix or its inverse will be initialized with `init_scale*np.eye(n)`, where `n` is the problem dimension. Set it to 'auto' in order to use an automatic heuristic for choosing the initial scale. The heuristic is described in [1], p.143. By default uses 'auto'.

Notes

The update is based on the description in [1], p.140.

References

[1]

Methods

<code>dot(self, p)</code>	Compute the product of the internal matrix with the given vector.
<code>get_matrix(self)</code>	Return the current internal matrix.
<code>initialize(self, n, approx_type)</code>	Initialize internal matrix.
<code>update(self, delta_x, delta_grad)</code>	Update internal matrix.

scipy.optimize.BFGS.dot**BFGS.dot** (*self*, *p*)

Compute the product of the internal matrix with the given vector.

Parameters**p** [array_like] 1-D array representing a vector.**Returns****Hp** [array] 1-D represents the result of multiplying the approximation matrix by vector *p*.**scipy.optimize.BFGS.get_matrix****BFGS.get_matrix** (*self*)

Return the current internal matrix.

Returns**M** [ndarray, shape (n, n)] Dense matrix containing either the Hessian or its inverse (depending on how *approx_type* was defined).**scipy.optimize.BFGS.initialize****BFGS.initialize** (*self*, *n*, *approx_type*)

Initialize internal matrix.

Allocate internal memory for storing and updating the Hessian or its inverse.

Parameters**n** [int] Problem dimension.**approx_type**

[{'hess', 'inv_hess'}] Selects either the Hessian or the inverse Hessian. When set to 'hess' the Hessian will be stored and updated. When set to 'inv_hess' its inverse will be used instead.

scipy.optimize.BFGS.update**BFGS.update** (*self*, *delta_x*, *delta_grad*)

Update internal matrix.

Update Hessian matrix or its inverse (depending on how 'approx_type' is defined) using information about the last evaluated points.

Parameters**delta_x** [ndarray] The difference between two points the gradient function have been evaluated at: $\text{delta_x} = \text{x2} - \text{x1}$.**delta_grad**[ndarray] The difference between the gradients: $\text{delta_grad} = \text{grad}(\text{x2}) - \text{grad}(\text{x1})$.

scipy.optimize.SR1

class `scipy.optimize.SR1` (*min_denominator=1e-08, init_scale='auto'*)
 Symmetric-rank-1 Hessian update strategy.

Parameters

min_denominator

[float] This number, scaled by a normalization factor, defines the minimum denominator magnitude allowed in the update. When the condition is violated we skip the update. By default uses $1e-8$.

init_scale

[{float, 'auto'}, optional] Matrix scale at first iteration. At the first iteration the Hessian matrix or its inverse will be initialized with `init_scale*np.eye(n)`, where `n` is the problem dimension. Set it to 'auto' in order to use an automatic heuristic for choosing the initial scale. The heuristic is described in [1], p.143. By default uses 'auto'.

Notes

The update is based on the description in [1], p.144-146.

References

[1]

Methods

<code>dot(self, p)</code>	Compute the product of the internal matrix with the given vector.
<code>get_matrix(self)</code>	Return the current internal matrix.
<code>initialize(self, n, approx_type)</code>	Initialize internal matrix.
<code>update(self, delta_x, delta_grad)</code>	Update internal matrix.

scipy.optimize.SR1.dot

`SR1.dot` (*self, p*)
 Compute the product of the internal matrix with the given vector.

Parameters

p [array_like] 1-D array representing a vector.

Returns

Hp [array] 1-D represents the result of multiplying the approximation matrix by vector `p`.

scipy.optimize.SR1.get_matrix**SR1.get_matrix** (*self*)

Return the current internal matrix.

Returns**M** [ndarray, shape (n, n)] Dense matrix containing either the Hessian or its inverse (depending on how *approx_type* was defined).**scipy.optimize.SR1.initialize****SR1.initialize** (*self*, *n*, *approx_type*)

Initialize internal matrix.

Allocate internal memory for storing and updating the Hessian or its inverse.

Parameters**n** [int] Problem dimension.**approx_type**

[{'hess', 'inv_hess'}] Selects either the Hessian or the inverse Hessian. When set to 'hess' the Hessian will be stored and updated. When set to 'inv_hess' its inverse will be used instead.

scipy.optimize.SR1.update**SR1.update** (*self*, *delta_x*, *delta_grad*)

Update internal matrix.

Update Hessian matrix or its inverse (depending on how 'approx_type' is defined) using information about the last evaluated points.

Parameters**delta_x** [ndarray] The difference between two points the gradient function have been evaluated at: $\text{delta_x} = \text{x2} - \text{x1}$.**delta_grad**[ndarray] The difference between the gradients: $\text{delta_grad} = \text{grad}(\text{x2}) - \text{grad}(\text{x1})$.**Global optimization**

<i>basinhopping</i> (func, x0[, niter, T, stepsize, ...])	Find the global minimum of a function using the basin-hopping algorithm
<i>brute</i> (func, ranges[, args, Ns, full_output, ...])	Minimize a function over a given range by brute force.
<i>differential_evolution</i> (func, bounds[, args, ...])	Finds the global minimum of a multivariate function.
<i>shgo</i> (func, bounds[, args, constraints, n, ...])	Finds the global minimum of a function using SHG optimization.
<i>dual_annealing</i> (func, bounds[, args, ...])	Find the global minimum of a function using Dual Annealing.

scipy.optimize.basinhopping

`scipy.optimize.basinhopping` (*func*, *x0*, *niter*=100, *T*=1.0, *stepsize*=0.5, *minimizer_kwargs*=None, *take_step*=None, *accept_test*=None, *callback*=None, *interval*=50, *disp*=False, *niter_success*=None, *seed*=None)

Find the global minimum of a function using the basin-hopping algorithm

Basin-hopping is a two-phase method that combines a global stepping algorithm with local minimization at each step. Designed to mimic the natural process of energy minimization of clusters of atoms, it works well for similar problems with “funnel-like, but rugged” energy landscapes [5].

As the step-taking, step acceptance, and minimization methods are all customizable, this function can also be used to implement other two-phase methods.

Parameters

func	[callable <i>f</i> (<i>x</i> , * <i>args</i>)] Function to be optimized. <i>args</i> can be passed as an optional item in the dict <i>minimizer_kwargs</i>				
x0	[array_like] Initial guess.				
niter	[integer, optional] The number of basin-hopping iterations. There will be a total of <i>niter</i> + 1 runs of the local minimizer.				
T	[float, optional] The “temperature” parameter for the accept or reject criterion. Higher “temperatures” mean that larger jumps in function value will be accepted. For best results <i>T</i> should be comparable to the separation (in function value) between local minima.				
stepsize	[float, optional] Maximum step size for use in the random displacement.				
minimizer_kwargs	[dict, optional] Extra keyword arguments to be passed to the local minimizer <code>scipy.optimize.minimize()</code> Some important options could be: <table> <tr> <td>method</td> <td>[str] The minimization method (e.g. "L-BFGS-B")</td> </tr> <tr> <td>args</td> <td>[tuple] Extra arguments passed to the objective function (<i>func</i>) and its derivatives (Jacobian, Hessian).</td> </tr> </table>	method	[str] The minimization method (e.g. "L-BFGS-B")	args	[tuple] Extra arguments passed to the objective function (<i>func</i>) and its derivatives (Jacobian, Hessian).
method	[str] The minimization method (e.g. "L-BFGS-B")				
args	[tuple] Extra arguments passed to the objective function (<i>func</i>) and its derivatives (Jacobian, Hessian).				
take_step	[callable <i>take_step</i> (<i>x</i>), optional] Replace the default step-taking routine with this routine. The default step-taking routine is a random displacement of the coordinates, but other step-taking algorithms may be better for some systems. <i>take_step</i> can optionally have the attribute <i>take_step.stepsize</i> . If this attribute exists, then <code>basinhopping</code> will adjust <i>take_step.stepsize</i> in order to try to optimize the global minimum search.				
accept_test	[callable, <i>accept_test</i> (<i>f_new</i> = <i>f_new</i> , <i>x_new</i> = <i>x_new</i> , <i>f_old</i> = <i>fold</i> , <i>x_old</i> = <i>x_old</i>), optional] Define a test which will be used to judge whether or not to accept the step. This will be used in addition to the Metropolis test based on “temperature” <i>T</i> . The acceptable return values are True, False, or "force accept". If any of the tests return False then the step is rejected. If the latter, then this will override any other tests in order to accept the step. This can be used, for example, to forcefully escape from a local minimum that <code>basinhopping</code> is trapped in.				
callback	[callable, <i>callback</i> (<i>x</i> , <i>f</i> , <i>accept</i>), optional] A callback function which will be called for all minima found. <i>x</i> and <i>f</i> are the coordinates and function value of the trial minimum, and <i>accept</i> is whether or not that minimum was accepted. This can be used, for example, to save the lowest <i>N</i> minima found. Also, <i>callback</i> can be used to specify a user defined stop criterion by optionally returning True to stop the <code>basinhopping</code> routine.				
interval	[integer, optional] interval for how often to update the <i>stepsize</i>				
disp	[bool, optional] Set to True to print status messages				
niter_success	[integer, optional] Stop the run if the global minimum candidate remains the same for this number of iterations.				
seed	[[int, <i>RandomState</i> , <i>Generator</i>], optional] If <i>seed</i> is not specified the <i>RandomState</i> singleton is used. If <i>seed</i> is an int, a new <i>RandomState</i> instance is used, seeded with <i>seed</i> . If <i>seed</i> is already a <i>RandomState</i> or <i>Generator</i> instance, then that object is used. Specify <i>seed</i>				

for repeatable minimizations. The random numbers generated with this seed only affect the default Metropolis *accept_test* and the default *take_step*. If you supply your own *take_step* and *accept_test*, and these functions use random number generation, then those functions are responsible for the state of their random number generator.

Returns

res [OptimizeResult] The optimization result represented as a `OptimizeResult` object. Important attributes are: `x` the solution array, `fun` the value of the function at the solution, and `message` which describes the cause of the termination. The `OptimizeResult` object returned by the selected minimizer at the lowest minimum is also contained within this object and can be accessed through the `lowest_optimization_result` attribute. See `OptimizeResult` for a description of other attributes.

See also:

`minimize`

The local minimization function called once for each basinhopping step. `minimizer_kwargs` is passed to this routine.

Notes

Basin-hopping is a stochastic algorithm which attempts to find the global minimum of a smooth scalar function of one or more variables [1] [2] [3] [4]. The algorithm in its current form was described by David Wales and Jonathan Doye [2] <http://www-wales.ch.cam.ac.uk/>.

The algorithm is iterative with each cycle composed of the following features

- 1) random perturbation of the coordinates
- 2) local minimization
- 3) accept or reject the new coordinates based on the minimized function value

The acceptance test used here is the Metropolis criterion of standard Monte Carlo algorithms, although there are many other possibilities [3].

This global minimization method has been shown to be extremely efficient for a wide variety of problems in physics and chemistry. It is particularly useful when the function has many minima separated by large barriers. See the Cambridge Cluster Database <http://www-wales.ch.cam.ac.uk/CCD.html> for databases of molecular systems that have been optimized primarily using basin-hopping. This database includes minimization problems exceeding 300 degrees of freedom.

See the free software program GMIN (<http://www-wales.ch.cam.ac.uk/GMIN>) for a Fortran implementation of basin-hopping. This implementation has many different variations of the procedure described above, including more advanced step taking algorithms and alternate acceptance criterion.

For stochastic global optimization there is no way to determine if the true global minimum has actually been found. Instead, as a consistency check, the algorithm can be run from a number of different random starting points to ensure the lowest minimum found in each example has converged to the global minimum. For this reason, `basinhopping` will by default simply run for the number of iterations `niter` and return the lowest minimum found. It is left to the user to ensure that this is in fact the global minimum.

Choosing `stepsize`: This is a crucial parameter in `basinhopping` and depends on the problem being solved. The step is chosen uniformly in the region from `x0-stepsize` to `x0+stepsize`, in each dimension. Ideally, it should be comparable to the typical separation (in argument values) between local minima of the function being optimized. `basinhopping` will, by default, adjust `stepsize` to find an optimal value, but this may take many iterations. You will get quicker results if you set a sensible initial value for `stepsize`.

Choosing T: The parameter T is the “temperature” used in the Metropolis criterion. Basinhopping steps are always accepted if $\text{func}(x_{\text{new}}) < \text{func}(x_{\text{old}})$. Otherwise, they are accepted with probability:

$$\exp(-(\text{func}(x_{\text{new}}) - \text{func}(x_{\text{old}})) / T)$$

So, for best results, T should to be comparable to the typical difference (in function values) between local minima. (The height of “walls” between local minima is irrelevant.)

If T is 0, the algorithm becomes Monotonic Basin-Hopping, in which all steps that increase energy are rejected.

New in version 0.12.0.

References

[1], [2], [3], [4], [5]

Examples

The following example is a 1-D minimization problem, with many local minima superimposed on a parabola.

```
>>> from scipy.optimize import basinhopping
>>> func = lambda x: np.cos(14.5 * x - 0.3) + (x + 0.2) * x
>>> x0=[1.]
```

Basinhopping, internally, uses a local minimization algorithm. We will use the parameter `minimizer_kwargs` to tell basinhopping which algorithm to use and how to set up that minimizer. This parameter will be passed to `scipy.optimize.minimize()`.

```
>>> minimizer_kwargs = {"method": "BFGS"}
>>> ret = basinhopping(func, x0, minimizer_kwargs=minimizer_kwargs,
...                   niter=200)
>>> print("global minimum: x = %.4f, f(x0) = %.4f" % (ret.x, ret.fun))
global minimum: x = -0.1951, f(x0) = -1.0009
```

Next consider a 2-D minimization problem. Also, this time, we will use gradient information to significantly speed up the search.

```
>>> def func2d(x):
...     f = np.cos(14.5 * x[0] - 0.3) + (x[1] + 0.2) * x[1] + (x[0] +
...                                                         0.2) * x[0]
...     df = np.zeros(2)
...     df[0] = -14.5 * np.sin(14.5 * x[0] - 0.3) + 2. * x[0] + 0.2
...     df[1] = 2. * x[1] + 0.2
...     return f, df
```

We’ll also use a different local minimization algorithm. Also, we must tell the minimizer that our function returns both energy and gradient (Jacobian).

```
>>> minimizer_kwargs = {"method": "L-BFGS-B", "jac": True}
>>> x0 = [1.0, 1.0]
>>> ret = basinhopping(func2d, x0, minimizer_kwargs=minimizer_kwargs,
...                   niter=200)
>>> print("global minimum: x = [%.4f, %.4f], f(x0) = %.4f" % (ret.x[0],
...                                                         ret.x[1],
...                                                         ret.fun))
```

(continues on next page)

(continued from previous page)

```

...                                     ret.fun))
global minimum: x = [-0.1951, -0.1000], f(x0) = -1.0109

```

Here is an example using a custom step-taking routine. Imagine you want the first coordinate to take larger steps than the rest of the coordinates. This can be implemented like so:

```

>>> class MyTakeStep(object):
...     def __init__(self, stepsize=0.5):
...         self.stepsize = stepsize
...     def __call__(self, x):
...         s = self.stepsize
...         x[0] += np.random.uniform(-2.*s, 2.*s)
...         x[1:] += np.random.uniform(-s, s, x[1:].shape)
...         return x

```

Since `MyTakeStep.stepsize` exists `basinhopping` will adjust the magnitude of `stepsize` to optimize the search. We'll use the same 2-D function as before

```

>>> mytakestep = MyTakeStep()
>>> ret = basinhopping(func2d, x0, minimizer_kwargs=minimizer_kwargs,
...                   niter=200, take_step=mytakestep)
>>> print("global minimum: x = [%.4f, %.4f], f(x0) = %.4f" % (ret.x[0],
...                                                         ret.x[1],
...                                                         ret.fun))
global minimum: x = [-0.1951, -0.1000], f(x0) = -1.0109

```

Now, let's do an example using a custom callback function which prints the value of every minimum found

```

>>> def print_fun(x, f, accepted):
...     print("at minimum %.4f accepted %d" % (f, int(accepted)))

```

We'll run it for only 10 `basinhopping` steps this time.

```

>>> np.random.seed(1)
>>> ret = basinhopping(func2d, x0, minimizer_kwargs=minimizer_kwargs,
...                   niter=10, callback=print_fun)
at minimum 0.4159 accepted 1
at minimum 0.4159 accepted 1
at minimum -0.9073 accepted 1
at minimum -0.1021 accepted 1
at minimum -0.1021 accepted 1
at minimum 0.9102 accepted 1
at minimum 0.9102 accepted 1
at minimum 2.2945 accepted 0
at minimum -0.1021 accepted 1
at minimum -1.0109 accepted 1
at minimum -1.0109 accepted 1

```

The minimum at `-1.0109` is actually the global minimum, found already on the 8th iteration.

Now let's implement bounds on the problem using a custom `accept_test`:

```

>>> class MyBounds(object):
...     def __init__(self, xmax=[1.1,1.1], xmin=[-1.1,-1.1] ):

```

(continues on next page)

(continued from previous page)

```

...     self.xmax = np.array(xmax)
...     self.xmin = np.array(xmin)
...     def __call__(self, **kwargs):
...         x = kwargs["x_new"]
...         tmax = bool(np.all(x <= self.xmax))
...         tmin = bool(np.all(x >= self.xmin))
...         return tmax and tmin

```

```

>>> mybounds = MyBounds()
>>> ret = basinhopping(func2d, x0, minimizer_kwargs=minimizer_kwargs,
...                   niter=10, accept_test=mybounds)

```

scipy.optimize.brute

`scipy.optimize.brute` (*func*, *ranges*, *args=()*, *Ns=20*, *full_output=0*, *finish=<function fmin at 0x7f893983df70>*, *disp=False*, *workers=1*)

Minimize a function over a given range by brute force.

Uses the “brute force” method, i.e., computes the function’s value at each point of a multidimensional grid of points, to find the global minimum of the function.

The function is evaluated everywhere in the range with the datatype of the first call to the function, as enforced by the `vectorize` NumPy function. The value and type of the function evaluation returned when `full_output=True` are affected in addition by the `finish` argument (see Notes).

The brute force approach is inefficient because the number of grid points increases exponentially - the number of grid points to evaluate is $N_s \times \text{len}(x)$. Consequently, even with coarse grid spacing, even moderately sized problems can take a long time to run, and/or run into memory limitations.

Parameters

func	[callable] The objective function to be minimized. Must be in the form $f(x, *args)$, where x is the argument in the form of a 1-D array and $args$ is a tuple of any additional fixed parameters needed to completely specify the function.
ranges	[tuple] Each component of the <i>ranges</i> tuple must be either a “slice object” or a range tuple of the form $(low, high)$. The program uses these to create the grid of points on which the objective function will be computed. See <i>Note 2</i> for more detail.
args	[tuple, optional] Any additional fixed parameters needed to completely specify the function.
Ns	[int, optional] Number of grid points along the axes, if not otherwise specified. See <i>Note 2</i> .
full_output	[bool, optional] If True, return the evaluation grid and the objective function’s values on it.
finish	[callable, optional] An optimization function that is called with the result of brute force minimization as initial guess. <i>finish</i> should take <i>func</i> and the initial guess as positional arguments, and take <i>args</i> as keyword arguments. It may additionally take <i>full_output</i> and/or <i>disp</i> as keyword arguments. Use None if no “polishing” function is to be used. See Notes for more details.
disp	[bool, optional] Set to True to print convergence messages from the <i>finish</i> callable.
workers	[int or map-like callable, optional] If <i>workers</i> is an int the grid is subdivided into <i>workers</i> sections and evaluated in parallel (uses <code>multiprocessing.Pool</code>). Supply <i>-1</i> to use all cores available to the Process. Alternatively supply a map-like callable, such as <code>multiprocessing.Pool.map</code> for evaluating the grid in parallel. This evaluation is carried out as <code>workers(func, iterable)</code> . Requires that <i>func</i> be pickleable. New in version 1.3.0.

Returns

x0	[ndarray] A 1-D array containing the coordinates of a point at which the objective function had its minimum value. (See <i>Note 1</i> for which point is returned.)
fval	[float] Function value at the point <i>x0</i> . (Returned when <i>full_output</i> is True.)
grid	[tuple] Representation of the evaluation grid. It has the same length as <i>x0</i> . (Returned when <i>full_output</i> is True.)
Jout	[ndarray] Function values at each point of the evaluation grid, i.e., $J_{out} = func(*grid)$. (Returned when <i>full_output</i> is True.)

See also:

basinhopping, *differential_evolution*

Notes

Note 1: The program finds the gridpoint at which the lowest value of the objective function occurs. If *finish* is None, that is the point returned. When the global minimum occurs within (or not very far outside) the grid’s boundaries, and the grid is fine enough, that point will be in the neighborhood of the global minimum.

However, users often employ some other optimization program to “polish” the gridpoint values, i.e., to seek a more precise (local) minimum near *brute*’s best gridpoint. The *brute* function’s *finish* option provides a convenient way to do that. Any polishing program used must take *brute*’s output as its initial guess as a positional argument, and take *brute*’s input values for *args* as keyword arguments, otherwise an error will be raised. It may additionally take *full_output* and/or *disp* as keyword arguments.

brute assumes that the *finish* function returns either an *OptimizeResult* object or a tuple in the form: (xmin, Jmin, ..., statuscode), where xmin is the minimizing value of the argument, Jmin is the minimum value of the objective function, “...” may be some other returned values (which are not used by *brute*), and statuscode is the status code of the *finish* program.

Note that when *finish* is not None, the values returned are those of the *finish* program, *not* the gridpoint ones. Consequently, while *brute* confines its search to the input grid points, the *finish* program’s results usually will not coincide with any gridpoint, and may fall outside the grid’s boundary. Thus, if a minimum only needs to be found over the provided grid points, make sure to pass in *finish=None*.

Note 2: The grid of points is a *numpy.mgrid* object. For *brute* the *ranges* and *Ns* inputs have the following effect. Each component of the *ranges* tuple can be either a slice object or a two-tuple giving a range of values, such as (0, 5). If the component is a slice object, *brute* uses it directly. If the component is a two-tuple range, *brute* internally converts it to a slice object that interpolates *Ns* points from its low-value to its high-value, inclusive.

Examples

We illustrate the use of *brute* to seek the global minimum of a function of two variables that is given as the sum of a positive-definite quadratic and two deep “Gaussian-shaped” craters. Specifically, define the objective function *f* as the sum of three other functions, $f = f_1 + f_2 + f_3$. We suppose each of these has a signature (z, *params), where $z = (x, y)$, and *params* and the functions are as defined below.

```
>>> params = (2, 3, 7, 8, 9, 10, 44, -1, 2, 26, 1, -2, 0.5)
>>> def f1(z, *params):
...     x, y = z
...     a, b, c, d, e, f, g, h, i, j, k, l, scale = params
...     return (a * x**2 + b * x * y + c * y**2 + d*x + e*y + f)
```

```
>>> def f2(z, *params):
...     x, y = z
...     a, b, c, d, e, f, g, h, i, j, k, l, scale = params
...     return (-g*np.exp(-((x-h)**2 + (y-i)**2) / scale))
```

```
>>> def f3(z, *params):
...     x, y = z
...     a, b, c, d, e, f, g, h, i, j, k, l, scale = params
...     return (-j*np.exp(-((x-k)**2 + (y-l)**2) / scale))
```

```
>>> def f(z, *params):
...     return f1(z, *params) + f2(z, *params) + f3(z, *params)
```

Thus, the objective function may have local minima near the minimum of each of the three functions of which it is composed. To use `fmin` to polish its gridpoint result, we may then continue as follows:

```
>>> rranges = (slice(-4, 4, 0.25), slice(-4, 4, 0.25))
>>> from scipy import optimize
>>> resbrute = optimize.brute(f, rranges, args=params, full_output=True,
...                           finish=optimize.fmin)
...
>>> resbrute[0] # global minimum
array([-1.05665192,  1.80834843])
>>> resbrute[1] # function value at global minimum
-3.4085818767
```

Note that if `finish` had been set to `None`, we would have gotten the gridpoint `[-1.0 1.75]` where the rounded function value is `-2.892`.

scipy.optimize.differential_evolution

`scipy.optimize.differential_evolution` (*func*, *bounds*, *args=()*, *strategy='best1bin'*, *maxiter=1000*, *popsiz=15*, *tol=0.01*, *mutation=0.5*, *1*, *recombination=0.7*, *seed=None*, *callback=None*, *disp=False*, *polish=True*, *init='latinhypercube'*, *atol=0*, *updating='immediate'*, *workers=1*, *constraints=()*)

Finds the global minimum of a multivariate function.

Differential Evolution is stochastic in nature (does not use gradient methods) to find the minimum, and can search large areas of candidate space, but often requires larger numbers of function evaluations than conventional gradient-based techniques.

The algorithm is due to Storn and Price [1].

Parameters

- func** [callable] The objective function to be minimized. Must be in the form `f(x, *args)`, where `x` is the argument in the form of a 1-D array and `args` is a tuple of any additional fixed parameters needed to completely specify the function.
- bounds** [sequence or `Bounds`, optional] Bounds for variables. There are two ways to specify the bounds: 1. Instance of `Bounds` class. 2. `(min, max)` pairs for each element in `x`, defining the finite lower and upper bounds for the optimizing argument of `func`. It is required to have `len(bounds) == len(x)`. `len(bounds)` is used to determine the number of parameters in `x`.
- args** [tuple, optional] Any additional fixed parameters needed to completely specify the objective function.
- strategy** [str, optional] The differential evolution strategy to use. Should be one of:

- 'best1bin'
- 'best1exp'
- 'rand1exp'
- 'randtobest1exp'
- 'currenttobest1exp'
- 'best2exp'
- 'rand2exp'
- 'randtobest1bin'
- 'currenttobest1bin'
- 'best2bin'
- 'rand2bin'
- 'rand1bin'

The default is 'best1bin'.

maxiter	[int, optional] The maximum number of generations over which the entire population is evolved. The maximum number of function evaluations (with no polishing) is: $(\text{maxiter} + 1) * \text{popsize} * \text{len}(x)$
popsize	[int, optional] A multiplier for setting the total population size. The population has $\text{popsize} * \text{len}(x)$ individuals (unless the initial population is supplied via the <i>init</i> keyword).
tol	[float, optional] Relative tolerance for convergence, the solving stops when $\text{np.std}(\text{pop}) \leq \text{atol} + \text{tol} * \text{np.abs}(\text{np.mean}(\text{population_energies}))$, where <i>atol</i> and <i>tol</i> are the absolute and relative tolerance respectively.
mutation	[float or tuple(float, float), optional] The mutation constant. In the literature this is also known as differential weight, being denoted by <i>F</i> . If specified as a float it should be in the range [0, 2]. If specified as a tuple (<i>min</i> , <i>max</i>) dithering is employed. Dithering randomly changes the mutation constant on a generation by generation basis. The mutation constant for that generation is taken from $U[\text{min}, \text{max}]$. Dithering can help speed convergence significantly. Increasing the mutation constant increases the search radius, but will slow down convergence.
recombination	[float, optional] The recombination constant, should be in the range [0, 1]. In the literature this is also known as the crossover probability, being denoted by <i>CR</i> . Increasing this value allows a larger number of mutants to progress into the next generation, but at the risk of population stability.
seed	[{int, <i>RandomState</i> , <i>Generator</i> }, optional] If <i>seed</i> is not specified the <i>RandomState</i> singleton is used. If <i>seed</i> is an int, a new <i>RandomState</i> instance is used, seeded with <i>seed</i> . If <i>seed</i> is already a <i>RandomState</i> or a <i>Generator</i> instance, then that object is used. Specify <i>seed</i> for repeatable minimizations.
disp	[bool, optional] Prints the evaluated <i>func</i> at every iteration.
callback	[callable, <i>callback(xk, convergence=val)</i> , optional] A function to follow the progress of the minimization. <i>xk</i> is the current value of <i>x0</i> . <i>val</i> represents the fractional value of the population convergence. When <i>val</i> is greater than one the function halts. If <i>callback</i> returns <i>True</i> , then the minimization is halted (any polishing is still carried out).
polish	[bool, optional] If <i>True</i> (default), then <i>scipy.optimize.minimize</i> with the <i>L-BFGS-B</i> method is used to polish the best population member at the end, which can improve the minimization slightly. If a constrained problem is being studied then the <i>trust-constr</i> method is used instead.
init	[str or array-like, optional] Specify which type of population initialization is performed. Should be one of: <ul style="list-style-type: none"> • 'latinhypercube' • 'random' • array specifying the initial population. The array should have shape $(M, \text{len}(x))$, where <i>M</i> is the total population size and $\text{len}(x)$ is the number of parameters. <i>init</i> is clipped to <i>bounds</i> before use.

The default is 'latinhypercube'. Latin Hypercube sampling tries to maximize coverage of the available parameter space. 'random' initializes the population randomly - this has the drawback that clustering can occur, preventing the whole of parameter space being covered. Use of an array to specify a population subset could be used, for example, to create a tight bunch of initial guesses in an location where the solution is known to exist, thereby reducing time for convergence.

- atol** [float, optional] Absolute tolerance for convergence, the solving stops when `np.std(pop) <= atol + tol * np.abs(np.mean(population_energies))`, where `atol` and `tol` are the absolute and relative tolerance respectively.
- updating** [{'immediate', 'deferred'}, optional] If 'immediate', the best solution vector is continuously updated within a single generation [4]. This can lead to faster convergence as trial vectors can take advantage of continuous improvements in the best solution. With 'deferred', the best solution vector is updated once per generation. Only 'deferred' is compatible with parallelization, and the `workers` keyword can over-ride this option. New in version 1.2.0.
- workers** [int or map-like callable, optional] If `workers` is an int the population is subdivided into `workers` sections and evaluated in parallel (uses `multiprocessing.Pool`). Supply -1 to use all available CPU cores. Alternatively supply a map-like callable, such as `multiprocessing.Pool.map` for evaluating the population in parallel. This evaluation is carried out as `workers(func, iterable)`. This option will override the `updating` keyword to `updating='deferred'` if `workers != 1`. Requires that `func` be pickleable. New in version 1.2.0.
- constraints** [{NonLinearConstraint, LinearConstraint, Bounds}] Constraints on the solver, over and above those applied by the `bounds` kwd. Uses the approach by Lampinen [5]. New in version 1.4.0.

Returns

- res** [OptimizeResult] The optimization result represented as a `OptimizeResult` object. Important attributes are: `x` the solution array, `success` a Boolean flag indicating if the optimizer exited successfully and `message` which describes the cause of the termination. See `OptimizeResult` for a description of other attributes. If `polish` was employed, and a lower minimum was obtained by the polishing, then `OptimizeResult` also contains the `jac` attribute. If the eventual solution does not satisfy the applied constraints `success` will be `False`.

Notes

Differential evolution is a stochastic population based method that is useful for global optimization problems. At each pass through the population the algorithm mutates each candidate solution by mixing with other candidate solutions to create a trial candidate. There are several strategies [2] for creating trial candidates, which suit some problems more than others. The 'best1bin' strategy is a good starting point for many systems. In this strategy two members of the population are randomly chosen. Their difference is used to mutate the best member (the 'best' in 'best1bin'), b_0 , so far:

$$b' = b_0 + mutation * (population[rand0] - population[rand1])$$

A trial vector is then constructed. Starting with a randomly chosen i th parameter the trial is sequentially filled (in modulo) with parameters from b' or the original candidate. The choice of whether to use b' or the original candidate is made with a binomial distribution (the 'bin' in 'best1bin') - a random number in $[0, 1)$ is generated. If this number is less than the `recombination` constant then the parameter is loaded from b' , otherwise it is loaded from the original candidate. The final parameter is always loaded from b' . Once the trial candidate is built its fitness is assessed. If the trial is better than the original candidate then it takes its place. If it is also better than the

best overall candidate it also replaces that. To improve your chances of finding a global minimum use higher *popsiz*e values, with higher *mutation* and (dithering), but lower *recombination* values. This has the effect of widening the search radius, but slowing convergence. By default the best solution vector is updated continuously within a single iteration (`updating='immediate'`). This is a modification [4] of the original differential evolution algorithm which can lead to faster convergence as trial vectors can immediately benefit from improved solutions. To use the original Storn and Price behaviour, updating the best solution once per iteration, set `updating='deferred'`.

New in version 0.15.0.

References

[1], [2], [3], [4], [5]

Examples

Let us consider the problem of minimizing the Rosenbrock function. This function is implemented in `rosen` in `scipy.optimize`.

```
>>> from scipy.optimize import rosen, differential_evolution
>>> bounds = [(0,2), (0, 2), (0, 2), (0, 2), (0, 2)]
>>> result = differential_evolution(rosen, bounds)
>>> result.x, result.fun
(array([1., 1., 1., 1., 1.]), 1.9216496320061384e-19)
```

Now repeat, but with parallelization.

```
>>> bounds = [(0,2), (0, 2), (0, 2), (0, 2), (0, 2)]
>>> result = differential_evolution(rosen, bounds, updating='deferred',
...                               workers=2)
>>> result.x, result.fun
(array([1., 1., 1., 1., 1.]), 1.9216496320061384e-19)
```

Let's try and do a constrained minimization

```
>>> from scipy.optimize import NonlinearConstraint, Bounds
>>> def constr_f(x):
...     return np.array(x[0] + x[1])
>>>
>>> # the sum of x[0] and x[1] must be less than 1.9
>>> nlc = NonlinearConstraint(constr_f, -np.inf, 1.9)
>>> # specify limits using a `Bounds` object.
>>> bounds = Bounds([0., 0.], [2., 2.])
>>> result = differential_evolution(rosen, bounds, constraints=(nlc),
...                               seed=1)
>>> result.x, result.fun
(array([0.96633867, 0.93363577]), 0.0011361355854792312)
```

Next find the minimum of the Ackley function (https://en.wikipedia.org/wiki/Test_functions_for_optimization).

```
>>> from scipy.optimize import differential_evolution
>>> import numpy as np
>>> def ackley(x):
...     arg1 = -0.2 * np.sqrt(0.5 * (x[0] ** 2 + x[1] ** 2))
```

(continues on next page)

(continued from previous page)

```

...     arg2 = 0.5 * (np.cos(2. * np.pi * x[0]) + np.cos(2. * np.pi *
    ↪x[1]))
...     return -20. * np.exp(arg1) - np.exp(arg2) + 20. + np.e
>>> bounds = [(-5, 5), (-5, 5)]
>>> result = differential_evolution(ackley, bounds)
>>> result.x, result.fun
(array([ 0.,  0.]), 4.4408920985006262e-16)
    
```

scipy.optimize.shgo

`scipy.optimize.shgo` (*func*, *bounds*, *args=()*, *constraints=None*, *n=100*, *iters=1*, *callback=None*, *minimizer_kwargs=None*, *options=None*, *sampling_method='simplicial'*)

Finds the global minimum of a function using SHG optimization.

SHGO stands for “simplicial homology global optimization”.

Parameters

- func** [callable] The objective function to be minimized. Must be in the form $f(x, *args)$, where x is the argument in the form of a 1-D array and $args$ is a tuple of any additional fixed parameters needed to completely specify the function.
- bounds** [sequence] Bounds for variables. (min, max) pairs for each element in x , defining the lower and upper bounds for the optimizing argument of *func*. It is required to have $len(bounds) == len(x)$. $len(bounds)$ is used to determine the number of parameters in x . Use `None` for one of `min` or `max` when there is no bound in that direction. By default bounds are `(None, None)`.
- args** [tuple, optional] Any additional fixed parameters needed to completely specify the objective function.
- constraints** [dict or sequence of dict, optional] Constraints definition. Function(s) R^{*n} in the form:

```

g(x) >= 0 applied as g : R^n -> R^m
h(x) == 0 applied as h : R^n -> R^p
    
```

Each constraint is defined in a dictionary with fields:

- type** [str] Constraint type: ‘eq’ for equality, ‘ineq’ for inequality.
- fun** [callable] The function defining the constraint.
- jac** [callable, optional] The Jacobian of *fun* (only for SLSQP).
- args** [sequence, optional] Extra arguments to be passed to the function and Jacobian.

Equality constraint means that the constraint function result is to be zero whereas inequality means that it is to be non-negative. Note that COBYLA only supports inequality constraints.

Note: Only the COBYLA and SLSQP local minimize methods currently support constraint arguments. If the `constraints` sequence used in the local optimization problem is not defined in `minimizer_kwargs` and a constrained method is used then the global constraints will be used. (Defining a `constraints` sequence in `minimizer_kwargs` means that `constraints` will not be added so if equality constraints and so forth need to be added then the inequality functions in `constraints` need to be added to `minimizer_kwargs` too).

- n** [int, optional] Number of sampling points used in the construction of the simplicial complex. Note that this argument is only used for `sobol` and other arbitrary *sampling_methods*.
- iters** [int, optional] Number of iterations used in the construction of the simplicial complex.

- callback** [callable, optional] Called after each iteration, as `callback(xk)`, where `xk` is the current parameter vector.
- minimizer_kwargs** [dict, optional] Extra keyword arguments to be passed to the minimizer `scipy.optimize.minimize`. Some important options could be:
- **method** [str] The minimization method (e.g. SLSQP).
 - **args** [tuple] Extra arguments passed to the objective function (`func`) and its derivatives (Jacobian, Hessian).
 - **options** [dict, optional] Note that by default the tolerance is specified as `{ftol: 1e-12}`
- options** [dict, optional] A dictionary of solver options. Many of the options specified for the global routine are also passed to the `scipy.optimize.minimize` routine. The options that are also passed to the local routine are marked with “(L)”.
Stopping criteria, the algorithm will terminate if any of the specified criteria are met. However, the default algorithm does not require any to be specified:
- **maxfev** [int (L)] Maximum number of function evaluations in the feasible domain. (Note only methods that support this option will terminate the routine at precisely exact specified value. Otherwise the criterion will only terminate during a global iteration)
 - **f_min** Specify the minimum objective function value, if it is known.
 - **f_tol** [float] Precision goal for the value of `f` in the stopping criterion. Note that the global routine will also terminate if a sampling point in the global routine is within this tolerance.
 - **maxiter** [int] Maximum number of iterations to perform.
 - **maxev** [int] Maximum number of sampling evaluations to perform (includes searching in infeasible points).
 - **maxtime** [float] Maximum processing runtime allowed
 - **minhgrd** [int] Minimum homology group rank differential. The homology group of the objective function is calculated (approximately) during every iteration. The rank of this group has a one-to-one correspondence with the number of locally convex subdomains in the objective function (after adequate sampling points each of these subdomains contain a unique global minimum). If the difference in the `hgr` is 0 between iterations for `maxhgrd` specified iterations the algorithm will terminate.
- Objective function knowledge:
- **symmetry** [bool] Specify True if the objective function contains symmetric variables. The search space (and therefore performance) is decreased by $O(n!)$.
 - **jac** [bool or callable, optional] Jacobian (gradient) of objective function. Only for CG, BFGS, Newton-CG, L-BFGS-B, TNC, SLSQP, dogleg, trust-ncg. If `jac` is a boolean and is True, `fun` is assumed to return the gradient along with the objective function. If False, the gradient will be estimated numerically. `jac` can also be a callable returning the gradient of the objective. In this case, it must accept the same arguments as `fun`. (Passed to `scipy.optimize.minimize` automatically)
 - **hess, hessp** [callable, optional] Hessian (matrix of second-order derivatives) of objective function or Hessian of objective function times an arbitrary vector `p`. Only for Newton-CG, dogleg, trust-ncg. Only one of `hessp` or `hess` needs to be given. If `hess` is provided, then `hessp` will be ignored. If neither `hess` nor `hessp` is provided, then the Hessian product will be approximated using finite differences on `jac`. `hessp` must compute the Hessian times an arbitrary vector. (Passed to `scipy.optimize.minimize` automatically)
- Algorithm settings:
- **minimize_every_iter**

[bool] If True then promising global sampling points will be passed to a local minimization routine every iteration. If False then only the final minimizer pool will be run. Defaults to False.

- **local_iter** [int] Only evaluate a few of the best minimizer pool candidates every iteration. If False all potential points are passed to the local minimization routine.

- **infty_constraints: bool**

If True then any sampling points generated which are outside will the feasible domain will be saved and given an objective function value of `inf`. If False then these points will be discarded. Using this functionality could lead to higher performance with respect to function evaluations before the global minimum is found, specifying False will use less memory at the cost of a slight decrease in performance. Defaults to True.

Feedback:

- **disp** [bool (L)] Set to True to print convergence messages.

sampling_method

[str or function, optional] Current built in sampling method options are `sobol` and `simplicial`. The default `simplicial` uses less memory and provides the theoretical guarantee of convergence to the global minimum in finite time. The `sobol` method is faster in terms of sampling point generation at the cost of higher memory resources and the loss of guaranteed convergence. It is more appropriate for most “easier” problems where the convergence is relatively fast. User defined sampling functions must accept two arguments of `n` sampling points of dimension `dim` per call and output an array of sampling points with shape `n x dim`.

Returns

res [OptimizeResult] The optimization result represented as a `OptimizeResult` object. Important attributes are: `x` the solution array corresponding to the global minimum, `fun` the function output at the global solution, `x1` an ordered list of local minima solutions, `fun1` the function output at the corresponding local solutions, `success` a Boolean flag indicating if the optimizer exited successfully, `message` which describes the cause of the termination, `nfev` the total number of objective function evaluations including the sampling calls, `nlfev` the total number of objective function evaluations culminating from all local search optimizations, `nit` number of iterations performed by the global routine.

Notes

Global optimization using simplicial homology global optimization [1]. Appropriate for solving general purpose NLP and blackbox optimization problems to global optimality (low-dimensional problems).

In general, the optimization problems are of the form:

```
minimize f(x) subject to
g_i(x) >= 0, i = 1, ..., m
h_j(x) = 0, j = 1, ..., p
```

where x is a vector of one or more variables. $f(x)$ is the objective function $\mathbb{R}^n \rightarrow \mathbb{R}$, $g_i(x)$ are the inequality constraints, and $h_j(x)$ are the equality constraints.

Optionally, the lower and upper bounds for each element in x can also be specified using the `bounds` argument.

While most of the theoretical advantages of SHGO are only proven for when $f(x)$ is a Lipschitz smooth function, the algorithm is also proven to converge to the global optimum for the more general case where $f(x)$ is non-continuous, non-convex and non-smooth, if the default sampling method is used [1].

The local search method may be specified using the `minimizer_kwargs` parameter which is passed on to `scipy.optimize.minimize`. By default, the SLSQP method is used. In general, it is recommended to use the SLSQP or COBYLA local minimization if inequality constraints are defined for the problem since the other methods do not use constraints.

The `sobol` method points are generated using the Sobol (1967) [2] sequence. The primitive polynomials and various sets of initial direction numbers for generating Sobol sequences is provided by [3] by Frances Kuo and Stephen Joe. The original program `sobol.cc` (MIT) is available and described at <https://web.maths.unsw.edu.au/~fkuo/sobol/> translated to Python 3 by Carl Sandrock 2016-03-31.

References

[1], [2], [3], [4], [5]

Examples

First consider the problem of minimizing the Rosenbrock function, `rosen`:

```
>>> from scipy.optimize import rosen, shgo
>>> bounds = [(0,2), (0, 2), (0, 2), (0, 2), (0, 2)]
>>> result = shgo(rosen, bounds)
>>> result.x, result.fun
(array([ 1.,  1.,  1.,  1.,  1.]), 2.9203923741900809e-18)
```

Note that bounds determine the dimensionality of the objective function and is therefore a required input, however you can specify empty bounds using `None` or objects like `np.inf` which will be converted to large float numbers.

```
>>> bounds = [(None, None), ]*4
>>> result = shgo(rosen, bounds)
>>> result.x
array([ 0.99999851,  0.99999704,  0.99999411,  0.9999882 ])
```

Next, we consider the Eggholder function, a problem with several local minima and one global minimum. We will demonstrate the use of arguments and the capabilities of `shgo`. (https://en.wikipedia.org/wiki/Test_functions_for_optimization)

```
>>> def eggholder(x):
...     return -(x[1] + 47.0)
...           * np.sin(np.sqrt(abs(x[0]/2.0 + (x[1] + 47.0))))
...           - x[0] * np.sin(np.sqrt(abs(x[0] - (x[1] + 47.0))))
...           )
...
>>> bounds = [(-512, 512), (-512, 512)]
```

`shgo` has two built-in low discrepancy sampling sequences. First, we will input 30 initial sampling points of the Sobol sequence:

```
>>> result = shgo(eggholder, bounds, n=30, sampling_method='sobol')
>>> result.x, result.fun
(array([ 512.          ,  404.23180542]), -959.64066272085051)
```

`shgo` also has a return for any other local minima that was found, these can be called using:

```
>>> result.xl
array([[ 512.          , 404.23180542],
       [ 283.07593402, -487.12566542],
       [-294.66820039, -462.01964031],
       [-105.87688985, 423.15324143],
       [-242.97923629, 274.38032063],
       [-506.25823477,  6.3131022 ],
       [-408.71981195, -156.10117154],
       [ 150.23210485, 301.31378508],
       [  91.00922754, -391.28375925],
       [ 202.8966344 , -269.38042147],
       [ 361.66625957, -106.96490692],
       [-219.40615102, -244.06022436],
       [ 151.59603137, -100.61082677]])
```

```
>>> result.funl
array([-959.64066272, -718.16745962, -704.80659592, -565.99778097,
       -559.78685655, -557.36868733, -507.87385942, -493.96051115 ,
       -426.48799655, -421.15571437, -419.31194957, -410.98477763,
       -202.53912972])
```

These results are useful in applications where there are many global minima and the values of other global minima are desired or where the local minima can provide insight into the system (for example morphologies in physical chemistry [5]).

If we want to find a larger number of local minima, we can increase the number of sampling points or the number of iterations. We'll increase the number of sampling points to 60 and the number of iterations from the default of 1 to 5. This gives us $60 \times 5 = 300$ initial sampling points.

```
>>> result_2 = shgo(eggholder, bounds, n=60, iters=5, sampling_method=
    ↪ 'sobol')
>>> len(result.xl), len(result_2.xl)
(13, 39)
```

Note the difference between, e.g., $n=180$, $iters=1$ and $n=60$, $iters=3$. In the first case the promising points contained in the minimiser pool is processed only once. In the latter case it is processed every 60 sampling points for a total of 3 times.

To demonstrate solving problems with non-linear constraints consider the following example from Hock and Schittkowski problem 73 (cattle-feed) [4]:

```
minimize: f = 24.55 * x_1 + 26.75 * x_2 + 39 * x_3 + 40.50 * x_4
subject to: 2.3 * x_1 + 5.6 * x_2 + 11.1 * x_3 + 1.3 * x_4 - 5      >= 0,
           12 * x_1 + 11.9 * x_2 + 41.8 * x_3 + 52.1 * x_4 - 21
           -1.645 * sqrt(0.28 * x_1**2 + 0.19 * x_2**2 +
                        20.5 * x_3**2 + 0.62 * x_4**2)              >= 0,
           x_1 + x_2 + x_3 + x_4 - 1                               == 0,
           1 >= x_i >= 0 for all i
```

The approximate answer given in [4] is:

```
f([0.6355216, -0.12e-11, 0.3127019, 0.05177655]) = 29.894378
```

```
>>> def f(x): # (cattle-feed)
...     return 24.55*x[0] + 26.75*x[1] + 39*x[2] + 40.50*x[3]
...
>>> def g1(x):
...     return 2.3*x[0] + 5.6*x[1] + 11.1*x[2] + 1.3*x[3] - 5 # >=0
...
>>> def g2(x):
...     return (12*x[0] + 11.9*x[1] + 41.8*x[2] + 52.1*x[3] - 21
...             - 1.645 * np.sqrt(0.28*x[0]**2 + 0.19*x[1]**2
...                                 + 20.5*x[2]**2 + 0.62*x[3]**2)
...             ) # >=0
...
>>> def h1(x):
...     return x[0] + x[1] + x[2] + x[3] - 1 # == 0
...
>>> cons = ({'type': 'ineq', 'fun': g1},
...          {'type': 'ineq', 'fun': g2},
...          {'type': 'eq', 'fun': h1})
>>> bounds = [(0, 1.0),]*4
>>> res = shgo(f, bounds, iters=3, constraints=cons)
>>> res
  fun: 29.894378159142136
  fun1: array([29.89437816])
  message: 'Optimization terminated successfully.'
  nfev: 114
  nit: 3
  nlfev: 35
  nlhev: 0
  nljev: 5
  success: True
  x: array([6.35521569e-01, 1.13700270e-13, 3.12701881e-01, 5.
↪17765506e-02])
  x1: array([6.35521569e-01, 1.13700270e-13, 3.12701881e-01, 5.
↪17765506e-02])
```

```
>>> g1(res.x), g2(res.x), h1(res.x)
(-5.0626169922907138e-14, -2.9594104944408173e-12, 0.0)
```

scipy.optimize.dual_annealing

`scipy.optimize.dual_annealing` (*func*, *bounds*, *args=()*, *maxiter=1000*, *local_search_options={}*, *initial_temp=5230.0*, *restart_temp_ratio=2e-05*, *visit=2.62*, *accept=-5.0*, *maxfun=10000000.0*, *seed=None*, *no_local_search=False*, *callback=None*, *x0=None*)

Find the global minimum of a function using Dual Annealing.

Parameters

func [callable] The objective function to be minimized. Must be in the form $f(x, *args)$, where x is the argument in the form of a 1-D array and $args$ is a tuple of any additional fixed parameters needed to completely specify the function.

bounds	[sequence, shape (n, 2)] Bounds for variables. (min, max) pairs for each element in <i>x</i> , defining bounds for the objective function parameter.
args	[tuple, optional] Any additional fixed parameters needed to completely specify the objective function.
maxiter	[int, optional] The maximum number of global search iterations. Default value is 1000.
local_search_options	[dict, optional] Extra keyword arguments to be passed to the local minimizer (<i>minimize</i>). Some important options could be: <i>method</i> for the minimizer method to use and <i>args</i> for objective function additional arguments.
initial_temp	[float, optional] The initial temperature, use higher values to facilitates a wider search of the energy landscape, allowing <i>dual_annealing</i> to escape local minima that it is trapped in. Default value is 5230. Range is (0.01, 5.e4].
restart_temp_ratio	[float, optional] During the annealing process, temperature is decreasing, when it reaches <i>initial_temp * restart_temp_ratio</i> , the reannealing process is triggered. Default value of the ratio is 2e-5. Range is (0, 1).
visit	[float, optional] Parameter for visiting distribution. Default value is 2.62. Higher values give the visiting distribution a heavier tail, this makes the algorithm jump to a more distant region. The value range is (0, 3].
accept	[float, optional] Parameter for acceptance distribution. It is used to control the probability of acceptance. The lower the acceptance parameter, the smaller the probability of acceptance. Default value is -5.0 with a range (-1e4, -5].
maxfun	[int, optional] Soft limit for the number of objective function calls. If the algorithm is in the middle of a local search, this number will be exceeded, the algorithm will stop just after the local search is done. Default value is 1e7.
seed	[[int, <i>RandomState</i> , <i>Generator</i>], optional] If <i>seed</i> is not specified the <i>RandomState</i> singleton is used. If <i>seed</i> is an int, a new <i>RandomState</i> instance is used, seeded with <i>seed</i> . If <i>seed</i> is already a <i>RandomState</i> or <i>Generator</i> instance, then that instance is used. Specify <i>seed</i> for repeatable minimizations. The random numbers generated with this seed only affect the visiting distribution function and new coordinates generation.
no_local_search	[bool, optional] If <i>no_local_search</i> is set to True, a traditional Generalized Simulated Annealing will be performed with no local search strategy applied.
callback	[callable, optional] A callback function with signature <i>callback(x, f, context)</i> , which will be called for all minima found. <i>x</i> and <i>f</i> are the coordinates and function value of the latest minimum found, and <i>context</i> has value in [0, 1, 2], with the following meaning: <ul style="list-style-type: none"> • 0: minimum detected in the annealing process. • 1: detection occurred in the local search process. • 2: detection done in the dual annealing process. If the callback implementation returns True, the algorithm will stop.
x0	[ndarray, shape(n,), optional] Coordinates of a single N-D starting point.
Returns	
res	[<i>OptimizeResult</i>] The optimization result represented as a <i>OptimizeResult</i> object. Important attributes are: <i>x</i> the solution array, <i>fun</i> the value of the function at the solution, and <i>message</i> which describes the cause of the termination. See <i>OptimizeResult</i> for a description of other attributes.

Notes

This function implements the Dual Annealing optimization. This stochastic approach derived from [3] combines the generalization of CSA (Classical Simulated Annealing) and FSA (Fast Simulated Annealing) [1] [2] coupled to a strategy for applying a local search on accepted locations [4]. An alternative implementation of this same algorithm is described in [5] and benchmarks are presented in [6]. This approach introduces an advanced method to refine the solution found by the generalized annealing process. This algorithm uses a distorted Cauchy-Lorentz visiting distribution, with its shape controlled by the parameter q_v

$$g_{q_v}(\Delta x(t)) \propto \frac{[T_{q_v}(t)]^{-\frac{D}{3-q_v}}}{\left[1 + (q_v - 1) \frac{(\Delta x(t))^2}{[T_{q_v}(t)]^{3-q_v}}\right]^{\frac{1}{q_v-1} + \frac{D-1}{2}}}$$

Where t is the artificial time. This visiting distribution is used to generate a trial jump distance $\Delta x(t)$ of variable $x(t)$ under artificial temperature $T_{q_v}(t)$.

From the starting point, after calling the visiting distribution function, the acceptance probability is computed as follows:

$$p_{q_a} = \min \{1, [1 - (1 - q_a)\beta\Delta E]^{-\frac{1}{1-q_a}}\}$$

Where q_a is a acceptance parameter. For $q_a < 1$, zero acceptance probability is assigned to the cases where

$$[1 - (1 - q_a)\beta\Delta E] < 0$$

The artificial temperature $T_{q_v}(t)$ is decreased according to

$$T_{q_v}(t) = T_{q_v}(1) \frac{2^{q_v-1} - 1}{(1+t)^{q_v-1} - 1}$$

Where q_v is the visiting parameter.

New in version 1.2.0.

References

[1], [2], [3], [4], [5], [6]

Examples

The following example is a 10-D problem, with many local minima. The function involved is called Rastrigin (https://en.wikipedia.org/wiki/Rastrigin_function)

```
>>> from scipy.optimize import dual_annealing
>>> func = lambda x: np.sum(x*x - 10*np.cos(2*np.pi*x)) + 10*np.size(x)
>>> lw = [-5.12] * 10
>>> up = [5.12] * 10
>>> ret = dual_annealing(func, bounds=list(zip(lw, up)), seed=1234)
>>> ret.x
array([-4.26437714e-09, -3.91699361e-09, -1.86149218e-09, -3.97165720e-09,
       -6.29151648e-09, -6.53145322e-09, -3.93616815e-09, -6.55623025e-09,
       -6.05775280e-09, -5.00668935e-09]) # may vary
>>> ret.fun
0.000000
```

6.19.5 Least-squares and curve fitting

Nonlinear least-squares

<code>least_squares</code> (<i>fun</i> , <i>x0</i> [, <i>jac</i> , <i>bounds</i> , ...])	Solve a nonlinear least-squares problem with bounds on the variables.
---	---

scipy.optimize.least_squares

`scipy.optimize.least_squares` (*fun*, *x0*, *jac*='2-point', *bounds*=(- *inf*, *inf*, *method*='trf', *ftol*=1e-08, *xtol*=1e-08, *gtol*=1e-08, *x_scale*=1.0, *loss*='linear', *f_scale*=1.0, *diff_step*=None, *tr_solver*=None, *tr_options*={}, *jac_sparsity*=None, *max_nfev*=None, *verbose*=0, *args*=(), *kwargs*={})

Solve a nonlinear least-squares problem with bounds on the variables.

Given the residuals $f(x)$ (an m -D real function of n real variables) and the loss function $\rho(s)$ (a scalar function), `least_squares` finds a local minimum of the cost function $F(x)$:

```
minimize F(x) = 0.5 * sum(rho(f_i(x)**2), i = 0, ..., m - 1)
subject to lb <= x <= ub
```

The purpose of the loss function $\rho(s)$ is to reduce the influence of outliers on the solution.

Parameters

- | | |
|---------------|--|
| fun | [callable] Function which computes the vector of residuals, with the signature <code>fun(x, *args, **kwargs)</code> , i.e., the minimization proceeds with respect to its first argument. The argument x passed to this function is an ndarray of shape (n) (never a scalar, even for $n=1$). It must allocate and return a 1-D array_like of shape (m) , or a scalar. If the argument x is complex or the function <code>fun</code> returns complex residuals, it must be wrapped in a real function of real arguments, as shown at the end of the Examples section. |
| x0 | [array_like with shape (n) or float] Initial guess on independent variables. If float, it will be treated as a 1-D array with one element. |
| jac | [{'2-point', '3-point', 'cs', callable}, optional] Method of computing the Jacobian matrix (an m -by- n matrix, where element (i, j) is the partial derivative of $f[i]$ with respect to $x[j]$). The keywords select a finite difference scheme for numerical estimation. The scheme '3-point' is more accurate, but requires twice as many operations as '2-point' (default). The scheme 'cs' uses complex steps, and while potentially the most accurate, it is applicable only when <code>fun</code> correctly handles complex inputs and can be analytically continued to the complex plane. Method 'lm' always uses the '2-point' scheme. If callable, it is used as <code>jac(x, *args, **kwargs)</code> and should return a good approximation (or the exact value) for the Jacobian as an array_like (<code>np.atleast_2d</code> is applied), a sparse matrix (<code>csr_matrix</code> preferred for performance) or a <code>scipy.sparse.linalg.LinearOperator</code> . |
| bounds | [2-tuple of array_like, optional] Lower and upper bounds on independent variables. Defaults to no bounds. Each array must match the size of <code>x0</code> or be a scalar, in the latter case a bound will be the same for all variables. Use <code>np.inf</code> with an appropriate sign to disable bounds on all or some variables. |
| method | [{'trf', 'dogbox', 'lm'}, optional] Algorithm to perform minimization. <ul style="list-style-type: none"> 'trf': Trust Region Reflective algorithm, particularly suitable for large sparse problems with bounds. Generally robust method. 'dogbox': dogleg algorithm with rectangular trust regions, typical use case is small problems with bounds. Not recommended for problems with rank-deficient Jacobian. 'lm': Levenberg-Marquardt algorithm as implemented in MINPACK. Doesn't handle bounds and sparse Jacobians. Usually the most efficient method for small unconstrained problems. |

Default is 'trf'. See Notes for more information.

ftol [float or None, optional] Tolerance for termination by the change of the cost function. Default is 1e-8. The optimization process is stopped when $dF < ftol * F$, and there was an adequate agreement between a local quadratic model and the true model in the last step. If None and 'method' is not 'lm', the termination by this condition is disabled. If 'method' is 'lm', this tolerance must be higher than machine epsilon.

xtol [float or None, optional] Tolerance for termination by the change of the independent variables. Default is 1e-8. The exact condition depends on the *method* used:

- For 'trf' and 'dogbox': $norm(dx) < xtol * (xtol + norm(x))$.
- For 'lm': $Delta < xtol * norm(xs)$, where *Delta* is a trust-region radius and *xs* is the value of *x* scaled according to *x_scale* parameter (see below).

If None and 'method' is not 'lm', the termination by this condition is disabled. If 'method' is 'lm', this tolerance must be higher than machine epsilon.

gtol [float or None, optional] Tolerance for termination by the norm of the gradient. Default is 1e-8. The exact condition depends on a *method* used:

- For 'trf': $norm(g_scaled, ord=np.inf) < gtol$, where *g_scaled* is the value of the gradient scaled to account for the presence of the bounds [STIR].
- For 'dogbox': $norm(g_free, ord=np.inf) < gtol$, where *g_free* is the gradient with respect to the variables which are not in the optimal state on the boundary.
- For 'lm': the maximum absolute value of the cosine of angles between columns of the Jacobian and the residual vector is less than *gtol*, or the residual vector is zero.

If None and 'method' is not 'lm', the termination by this condition is disabled. If 'method' is 'lm', this tolerance must be higher than machine epsilon.

x_scale [array_like or 'jac', optional] Characteristic scale of each variable. Setting *x_scale* is equivalent to reformulating the problem in scaled variables $xs = x / x_scale$. An alternative view is that the size of a trust region along *j*th dimension is proportional to $x_scale[j]$. Improved convergence may be achieved by setting *x_scale* such that a step of a given size along any of the scaled variables has a similar effect on the cost function. If set to 'jac', the scale is iteratively updated using the inverse norms of the columns of the Jacobian matrix (as described in [JJMore]).

loss [str or callable, optional] Determines the loss function. The following keyword values are allowed:

- 'linear' (default): $\rho(z) = z$. Gives a standard least-squares problem.
- 'soft_l1': $\rho(z) = 2 * ((1 + z)**0.5 - 1)$. The smooth approximation of l1 (absolute value) loss. Usually a good choice for robust least squares.
- 'huber': $\rho(z) = z$ if $z \leq 1$ else $2*z**0.5 - 1$. Works similarly to 'soft_l1'.
- 'cauchy': $\rho(z) = \ln(1 + z)$. Severely weakens outliers influence, but may cause difficulties in optimization process.
- 'arctan': $\rho(z) = \arctan(z)$. Limits a maximum loss on a single residual, has properties similar to 'cauchy'.

If callable, it must take a 1-D ndarray $z=f**2$ and return an array_like with shape (3, m) where row 0 contains function values, row 1 contains first derivatives and row 2 contains second derivatives. Method 'lm' supports only 'linear' loss.

f_scale [float, optional] Value of soft margin between inlier and outlier residuals, default is 1.0. The loss function is evaluated as follows $\rho_-(f**2) = C**2 * \rho(f**2 / C**2)$, where *C* is *f_scale*, and ρ is determined by *loss* parameter. This parameter has no effect with *loss*='linear', but for other *loss* values it is of crucial importance.

max_nfev [None or int, optional] Maximum number of function evaluations before the termination. If None (default), the value is chosen automatically:

- For 'trf' and 'dogbox': $100 * n$.
- For 'lm': $100 * n$ if *jac* is callable and $100 * n * (n + 1)$ otherwise (because 'lm' counts function calls in Jacobian estimation).

- diff_step** [None or array_like, optional] Determines the relative step size for the finite difference approximation of the Jacobian. The actual step is computed as $x * \text{diff_step}$. If None (default), then *diff_step* is taken to be a conventional “optimal” power of machine epsilon for the finite difference scheme used [NR].
- tr_solver** [{None, ‘exact’, ‘lsmr’}, optional] Method for solving trust-region subproblems, relevant only for ‘trf’ and ‘dogbox’ methods.
- ‘exact’ is suitable for not very large problems with dense Jacobian matrices. The computational complexity per iteration is comparable to a singular value decomposition of the Jacobian matrix.
 - ‘lsmr’ is suitable for problems with sparse and large Jacobian matrices. It uses the iterative procedure `scipy.sparse.linalg.lsmr` for finding a solution of a linear least-squares problem and only requires matrix-vector product evaluations.
- If None (default), the solver is chosen based on the type of Jacobian returned on the first iteration.
- tr_options** [dict, optional] Keyword options passed to trust-region solver.
- `tr_solver='exact'`: *tr_options* are ignored.
 - `tr_solver='lsmr'`: options for `scipy.sparse.linalg.lsmr`. Additionally, `method='trf'` supports ‘regularize’ option (bool, default is True), which adds a regularization term to the normal equation, which improves convergence if the Jacobian is rank-deficient [Byrd] (eq. 3.4).
- jac_sparsity** [{None, array_like, sparse matrix}, optional] Defines the sparsity structure of the Jacobian matrix for finite difference estimation, its shape must be (m, n). If the Jacobian has only few non-zero elements in *each* row, providing the sparsity structure will greatly speed up the computations [Curtis]. A zero entry means that a corresponding element in the Jacobian is identically zero. If provided, forces the use of ‘lsmr’ trust-region solver. If None (default), then dense differencing will be used. Has no effect for ‘lm’ method.
- verbose** [{0, 1, 2}, optional] Level of algorithm’s verbosity:
- 0 (default) : work silently.
 - 1 : display a termination report.
 - 2 : display progress during iterations (not supported by ‘lm’ method).
- args, kwargs** [tuple and dict, optional] Additional arguments passed to *fun* and *jac*. Both empty by default. The calling signature is `fun(x, *args, **kwargs)` and the same for *jac*.

Returns

- result** [OptimizeResult] *OptimizeResult* with the following fields defined:
- x** [ndarray, shape (n,)] Solution found.
- cost** [float] Value of the cost function at the solution.
- fun** [ndarray, shape (m,)] Vector of residuals at the solution.
- jac** [ndarray, sparse matrix or LinearOperator, shape (m, n)] Modified Jacobian matrix at the solution, in the sense that $J^T J$ is a Gauss-Newton approximation of the Hessian of the cost function. The type is the same as the one used by the algorithm.
- grad** [ndarray, shape (m,)] Gradient of the cost function at the solution.
- optimality** [float] First-order optimality measure. In unconstrained problems, it is always the uniform norm of the gradient. In constrained problems, it is the quantity which was compared with *gtol* during iterations.
- active_mask** [ndarray of int, shape (n,)] Each component shows whether a corresponding constraint is active (that is, whether a variable is at the bound):
- 0 : a constraint is not active.
 - -1 : a lower bound is active.
 - 1 : an upper bound is active.

	Might be somewhat arbitrary for ‘trf’ method as it generates a sequence of strictly feasible iterates and <i>active_mask</i> is determined within a tolerance threshold.
nfev	[int] Number of function evaluations done. Methods ‘trf’ and ‘dogbox’ do not count function calls for numerical Jacobian approximation, as opposed to ‘lm’ method.
njev	[int or None] Number of Jacobian evaluations done. If numerical Jacobian approximation is used in ‘lm’ method, it is set to None.
status	[int] The reason for algorithm termination: <ul style="list-style-type: none"> • -1 : improper input parameters status returned from MINPACK. • 0 : the maximum number of function evaluations is exceeded. • 1 : <i>gtol</i> termination condition is satisfied. • 2 : <i>ftol</i> termination condition is satisfied. • 3 : <i>xtol</i> termination condition is satisfied. • 4 : Both <i>ftol</i> and <i>xtol</i> termination conditions are satisfied.
message	[str] Verbal description of the termination reason.
success	[bool] True if one of the convergence criteria is satisfied (<i>status</i> > 0).

See also:

leastsq

A legacy wrapper for the MINPACK implementation of the Levenberg-Marquadt algorithm.

curve_fit

Least-squares minimization applied to a curve-fitting problem.

Notes

Method ‘lm’ (Levenberg-Marquardt) calls a wrapper over least-squares algorithms implemented in MINPACK (lmdr, lmdif). It runs the Levenberg-Marquardt algorithm formulated as a trust-region type algorithm. The implementation is based on paper [JJMore], it is very robust and efficient with a lot of smart tricks. It should be your first choice for unconstrained problems. Note that it doesn’t support bounds. Also, it doesn’t work when $m < n$.

Method ‘trf’ (Trust Region Reflective) is motivated by the process of solving a system of equations, which constitute the first-order optimality condition for a bound-constrained minimization problem as formulated in [STIR]. The algorithm iteratively solves trust-region subproblems augmented by a special diagonal quadratic term and with trust-region shape determined by the distance from the bounds and the direction of the gradient. This enhancements help to avoid making steps directly into bounds and efficiently explore the whole space of variables. To further improve convergence, the algorithm considers search directions reflected from the bounds. To obey theoretical requirements, the algorithm keeps iterates strictly feasible. With dense Jacobians trust-region subproblems are solved by an exact method very similar to the one described in [JJMore] (and implemented in MINPACK). The difference from the MINPACK implementation is that a singular value decomposition of a Jacobian matrix is done once per iteration, instead of a QR decomposition and series of Givens rotation eliminations. For large sparse Jacobians a 2-D subspace approach of solving trust-region subproblems is used [STIR], [Byrd]. The subspace is spanned by a scaled gradient and an approximate Gauss-Newton solution delivered by `scipy.sparse.linalg.lsmr`. When no constraints are imposed the algorithm is very similar to MINPACK and has generally comparable performance. The algorithm works quite robust in unbounded and bounded problems, thus it is chosen as a default algorithm.

Method ‘dogbox’ operates in a trust-region framework, but considers rectangular trust regions as opposed to conventional ellipsoids [Voglis]. The intersection of a current trust region and initial bounds is again rectangular, so on each iteration a quadratic minimization problem subject to bound constraints is solved approximately by Powell’s dogleg method [NumOpt]. The required Gauss-Newton step can be computed exactly for dense Jacobians or approximately by `scipy.sparse.linalg.lsmr` for large sparse Jacobians. The algorithm is likely to exhibit

slow convergence when the rank of Jacobian is less than the number of variables. The algorithm often outperforms ‘trf’ in bounded problems with a small number of variables.

Robust loss functions are implemented as described in [BA]. The idea is to modify a residual vector and a Jacobian matrix on each iteration such that computed gradient and Gauss-Newton Hessian approximation match the true gradient and Hessian approximation of the cost function. Then the algorithm proceeds in a normal way, i.e., robust loss functions are implemented as a simple wrapper over standard least-squares algorithms.

New in version 0.17.0.

References

[STIR], [NR], [Byrd], [Curtis], [JJMore], [Voglis], [NumOpt], [BA]

Examples

In this example we find a minimum of the Rosenbrock function without bounds on independent variables.

```
>>> def fun_rosenbrock(x):
...     return np.array([10 * (x[1] - x[0]**2), (1 - x[0])])
```

Notice that we only provide the vector of the residuals. The algorithm constructs the cost function as a sum of squares of the residuals, which gives the Rosenbrock function. The exact minimum is at $x = [1.0, 1.0]$.

```
>>> from scipy.optimize import least_squares
>>> x0_rosenbrock = np.array([2, 2])
>>> res_1 = least_squares(fun_rosenbrock, x0_rosenbrock)
>>> res_1.x
array([ 1.,  1.])
>>> res_1.cost
9.8669242910846867e-30
>>> res_1.optimality
8.8928864934219529e-14
```

We now constrain the variables, in such a way that the previous solution becomes infeasible. Specifically, we require that $x[1] \geq 1.5$, and $x[0]$ left unconstrained. To this end, we specify the *bounds* parameter to *least_squares* in the form `bounds=(-np.inf, 1.5], np.inf)`.

We also provide the analytic Jacobian:

```
>>> def jac_rosenbrock(x):
...     return np.array([
...         [-20 * x[0], 10],
...         [-1, 0]])
```

Putting this all together, we see that the new solution lies on the bound:

```
>>> res_2 = least_squares(fun_rosenbrock, x0_rosenbrock, jac_rosenbrock,
...                       bounds=(-np.inf, 1.5], np.inf))
>>> res_2.x
array([ 1.22437075,  1.5         ])
>>> res_2.cost
0.025213093946805685
```

(continues on next page)

(continued from previous page)

```

>>> a = 0.5
>>> b = 2.0
>>> c = -1
>>> t_min = 0
>>> t_max = 10
>>> n_points = 15
...
>>> t_train = np.linspace(t_min, t_max, n_points)
>>> y_train = gen_data(t_train, a, b, c, noise=0.1, n_outliers=3)

```

Define function for computing residuals and initial estimate of parameters.

```

>>> def fun(x, t, y):
...     return x[0] + x[1] * np.exp(x[2] * t) - y
...
>>> x0 = np.array([1.0, 1.0, 0.0])

```

Compute a standard least-squares solution:

```

>>> res_lsq = least_squares(fun, x0, args=(t_train, y_train))

```

Now compute two solutions with two different robust loss functions. The parameter *f_scale* is set to 0.1, meaning that inlier residuals should not significantly exceed 0.1 (the noise level used).

```

>>> res_soft_l1 = least_squares(fun, x0, loss='soft_l1', f_scale=0.1,
...                             args=(t_train, y_train))
>>> res_log = least_squares(fun, x0, loss='cauchy', f_scale=0.1,
...                          args=(t_train, y_train))

```


And, finally, plot all the curves. We see that by selecting an appropriate *loss* we can get estimates close to optimal even in the presence of strong outliers. But keep in mind that generally it is recommended to try 'soft_l1' or 'huber' losses first (if at all necessary) as the other two options may cause difficulties in optimization process.

```

>>> t_test = np.linspace(t_min, t_max, n_points * 10)
>>> y_true = gen_data(t_test, a, b, c)
>>> y_lsq = gen_data(t_test, *res_lsq.x)
>>> y_soft_l1 = gen_data(t_test, *res_soft_l1.x)
>>> y_log = gen_data(t_test, *res_log.x)
...
>>> import matplotlib.pyplot as plt
>>> plt.plot(t_train, y_train, 'o')
>>> plt.plot(t_test, y_true, 'k', linewidth=2, label='true')
>>> plt.plot(t_test, y_lsq, label='linear loss')
>>> plt.plot(t_test, y_soft_l1, label='soft_l1 loss')
>>> plt.plot(t_test, y_log, label='cauchy loss')
>>> plt.xlabel("t")
>>> plt.ylabel("y")
>>> plt.legend()
>>> plt.show()

```

In the next example, we show how complex-valued residual functions of complex variables can be optimized with `least_squares()`. Consider the following function:



```
>>> def f(z):
...     return z - (0.5 + 0.5j)
```

We wrap it into a function of real variables that returns real residuals by simply handling the real and imaginary parts as independent variables:

```
>>> def f_wrap(x):
...     fx = f(x[0] + 1j*x[1])
...     return np.array([fx.real, fx.imag])
```

Thus, instead of the original m -D complex function of n complex variables we optimize a $2m$ -D real function of $2n$ real variables:

```
>>> from scipy.optimize import least_squares
>>> res_wrapped = least_squares(f_wrap, (0.1, 0.1), bounds=([0, 0], [1, 1]))
>>> z = res_wrapped.x[0] + res_wrapped.x[1]*1j
>>> z
(0.49999999999925893+0.49999999999925893j)
```

Linear least-squares

<code>nls(A, b[, maxiter])</code>	Solve $\operatorname{argmin}_x Ax - b _2$ for $x \geq 0$.
<code>lsq_linear(A, b[, bounds, method, tol, ...])</code>	Solve a linear least-squares problem with bounds on the variables.

scipy.optimize.nls

`scipy.optimize.nls(A, b, maxiter=None)`

Solve $\operatorname{argmin}_x ||Ax - b||_2$ for $x \geq 0$. This is a wrapper for a FORTRAN non-negative least squares solver.

Parameters

A [ndarray] Matrix A as shown above.

b [ndarray] Right-hand side vector.

6.19. Optimization and root finding (scipy.optimize)

maxiter: int, optional

Maximum number of iterations, optional. Default is $3 * A.shape[1]$.

Returns

Notes

The FORTRAN code was published in the book below. The algorithm is an active set method. It solves the KKT (Karush-Kuhn-Tucker) conditions for the non-negative least squares problem.

References

Lawson C., Hanson R.J., (1987) Solving Least Squares Problems, SIAM

Examples

```
>>> from scipy.optimize import nnls
...
>>> A = np.array([[1, 0], [1, 0], [0, 1]])
>>> b = np.array([2, 1, 1])
>>> nnls(A, b)
(array([1.5, 1. ]), 0.7071067811865475)
```

```
>>> b = np.array([-1, -1, -1])
>>> nnls(A, b)
(array([0., 0.]), 1.7320508075688772)
```

scipy.optimize.lsqr_linear

`scipy.optimize.lsqr_linear`(*A*, *b*, *bounds*=(-*inf*, *inf*), *method*='trf', *tol*=1e-10, *lsq_solver*=None, *lsqr_tol*=None, *max_iter*=None, *verbose*=0)

Solve a linear least-squares problem with bounds on the variables.

Given a *m*-by-*n* design matrix *A* and a target vector *b* with *m* elements, *lsqr_linear* solves the following optimization problem:

```
minimize 0.5 * ||A x - b||**2
subject to lb <= x <= ub
```

This optimization problem is convex, hence a found minimum (if iterations have converged) is guaranteed to be global.

Parameters

- | | |
|---------------|--|
| A | [array_like, sparse matrix of LinearOperator, shape (m, n)] Design matrix. Can be <code>scipy.sparse.linalg.LinearOperator</code> . |
| b | [array_like, shape (m,)] Target vector. |
| bounds | [2-tuple of array_like, optional] Lower and upper bounds on independent variables. Defaults to no bounds. Each array must have shape (n,) or be a scalar, in the latter case a bound will be the same for all variables. Use <code>np.inf</code> with an appropriate sign to disable bounds on all or some variables. |
| method | ['trf' or 'bvls', optional] Method to perform minimization. <ul style="list-style-type: none"> 'trf': Trust Region Reflective algorithm adapted for a linear least-squares problem. This is an interior-point-like method and the required number of iterations is weakly correlated with the number of variables. 'bvls': Bounded-variable least-squares algorithm. This is an active set method, which requires the number of iterations comparable to the number of variables. Can't be used when <i>A</i> is sparse or LinearOperator. Default is 'trf'. |

- tol** [float, optional] Tolerance parameter. The algorithm terminates if a relative change of the cost function is less than *tol* on the last iteration. Additionally, the first-order optimality measure is considered:
- `method='trf'` terminates if the uniform norm of the gradient, scaled to account for the presence of the bounds, is less than *tol*.
 - `method='bvl's'` terminates if Karush-Kuhn-Tucker conditions are satisfied within *tol* tolerance.
- lsq_solver** [{None, 'exact', 'lsmr'}, optional] Method of solving unbounded least-squares problems throughout iterations:
- 'exact': Use dense QR or SVD decomposition approach. Can't be used when *A* is sparse or LinearOperator.
 - 'lsmr': Use `scipy.sparse.linalg.lsmr` iterative procedure which requires only matrix-vector product evaluations. Can't be used with `method='bvl's'`.
- If None (default), the solver is chosen based on type of *A*.
- lsmr_tol** [None, float or 'auto', optional] Tolerance parameters 'atol' and 'btol' for `scipy.sparse.linalg.lsmr`. If None (default), it is set to $1e-2 * tol$. If 'auto', the tolerance will be adjusted based on the optimality of the current iterate, which can speed up the optimization process, but is not always reliable.
- max_iter** [None or int, optional] Maximum number of iterations before termination. If None (default), it is set to 100 for `method='trf'` or to the number of variables for `method='bvl's'` (not counting iterations for 'bvl's' initialization).
- verbose** [{0, 1, 2}, optional] Level of algorithm's verbosity:
- 0 : work silently (default).
 - 1 : display a termination report.
 - 2 : display progress during iterations.

Returns**OptimizeResult with the following fields defined:**

- x** [ndarray, shape (n,)] Solution found.
- cost** [float] Value of the cost function at the solution.
- fun** [ndarray, shape (m,)] Vector of residuals at the solution.
- optimality** [float] First-order optimality measure. The exact meaning depends on *method*, refer to the description of *tol* parameter.
- active_mask** [ndarray of int, shape (n,)] Each component shows whether a corresponding constraint is active (that is, whether a variable is at the bound):
- 0 : a constraint is not active.
 - -1 : a lower bound is active.
 - 1 : an upper bound is active.
- Might be somewhat arbitrary for the *trf* method as it generates a sequence of strictly feasible iterates and *active_mask* is determined within a tolerance threshold.
- nit** [int] Number of iterations. Zero if the unconstrained solution is optimal.
- status** [int] Reason for algorithm termination:
- -1 : the algorithm was not able to make progress on the last iteration.
 - 0 : the maximum number of iterations is exceeded.
 - 1 : the first-order optimality measure is less than *tol*.
 - 2 : the relative change of the cost function is less than *tol*.
 - 3 : the unconstrained solution is optimal.
- message** [str] Verbal description of the termination reason.
- success** [bool] True if one of the convergence criteria is satisfied (*status* > 0).

See also:

[nnls](#)

Linear least squares with non-negativity constraint.

least_squares

Nonlinear least squares with bounds on the variables.

Notes

The algorithm first computes the unconstrained least-squares solution by `numpy.linalg.lstsq` or `scipy.sparse.linalg.lsmr` depending on `lsq_solver`. This solution is returned as optimal if it lies within the bounds.

Method ‘trf’ runs the adaptation of the algorithm described in [STIR] for a linear least-squares problem. The iterations are essentially the same as in the nonlinear least-squares algorithm, but as the quadratic function model is always accurate, we don’t need to track or modify the radius of a trust region. The line search (backtracking) is used as a safety net when a selected step does not decrease the cost function. Read more detailed description of the algorithm in `scipy.optimize.least_squares`.

Method ‘bvls’ runs a Python implementation of the algorithm described in [BVLS]. The algorithm maintains active and free sets of variables, on each iteration chooses a new variable to move from the active set to the free set and then solves the unconstrained least-squares problem on free variables. This algorithm is guaranteed to give an accurate solution eventually, but may require up to n iterations for a problem with n variables. Additionally, an ad-hoc initialization procedure is implemented, that determines which variables to set free or active initially. It takes some number of iterations before actual BVLS starts, but can significantly reduce the number of further iterations.

References

[STIR], [BVLS]

Examples

In this example, a problem with a large sparse matrix and bounds on the variables is solved.

```
>>> from scipy.sparse import rand
>>> from scipy.optimize import lsq_linear
...
>>> np.random.seed(0)
...
>>> m = 20000
>>> n = 10000
...
>>> A = rand(m, n, density=1e-4)
>>> b = np.random.randn(m)
...
>>> lb = np.random.randn(n)
>>> ub = lb + 1
...
>>> res = lsq_linear(A, b, bounds=(lb, ub), lsqr_tol='auto', verbose=1)
# may vary
The relative change of the cost function is less than `tol`.
Number of iterations 16, initial cost 1.5039e+04, final cost 1.1112e+04,
first-order optimality 4.66e-08.
```

Curve fitting

<code>curve_fit(f, xdata, ydata[, p0, sigma, ...])</code>	Use non-linear least squares to fit a function, <i>f</i> , to data.
---	---

scipy.optimize.curve_fit

```
scipy.optimize.curve_fit(f, xdata, ydata, p0=None, sigma=None, absolute_sigma=False,
                        check_finite=True, bounds=(-inf, inf), method=None, jac=None, **kwargs)
```

Use non-linear least squares to fit a function, *f*, to data.

Assumes $ydata = f(xdata, *params) + \text{eps}$.

Parameters

- | | |
|-----------------------|--|
| f | [callable] The model function, $f(x, \dots)$. It must take the independent variable as the first argument and the parameters to fit as separate remaining arguments. |
| xdata | [array_like or object] The independent variable where the data is measured. Should usually be an <i>M</i> -length sequence or an (<i>k</i> , <i>M</i>)-shaped array for functions with <i>k</i> predictors, but can actually be any object. |
| ydata | [array_like] The dependent data, a length <i>M</i> array - nominally $f(xdata, \dots)$. |
| p0 | [array_like, optional] Initial guess for the parameters (length <i>N</i>). If <i>None</i> , then the initial values will all be 1 (if the number of parameters for the function can be determined using introspection, otherwise a <code>ValueError</code> is raised). |
| sigma | [<i>None</i> or <i>M</i> -length sequence or <i>M</i> × <i>M</i> array, optional] Determines the uncertainty in <i>ydata</i> . If we define residuals as $r = ydata - f(xdata, *popt)$, then the interpretation of <i>sigma</i> depends on its number of dimensions: <ul style="list-style-type: none"> • A 1-D <i>sigma</i> should contain values of standard deviations of errors in <i>ydata</i>. In this case, the optimized function is $chisq = \text{sum}((r / \text{sigma}) ** 2)$. • A 2-D <i>sigma</i> should contain the covariance matrix of errors in <i>ydata</i>. In this case, the optimized function is $chisq = r.T @ \text{inv}(\text{sigma}) @ r$. New in version 0.19.
<i>None</i> (default) is equivalent of 1-D <i>sigma</i> filled with ones. |
| absolute_sigma | [bool, optional] If <i>True</i> , <i>sigma</i> is used in an absolute sense and the estimated parameter covariance <i>pcov</i> reflects these absolute values.
If <i>False</i> (default), only the relative magnitudes of the <i>sigma</i> values matter. The returned parameter covariance matrix <i>pcov</i> is based on scaling <i>sigma</i> by a constant factor. This constant is set by demanding that the reduced <i>chisq</i> for the optimal parameters <i>popt</i> when using the <i>scaled sigma</i> equals unity. In other words, <i>sigma</i> is scaled to match the sample variance of the residuals after the fit. Default is <i>False</i> . Mathematically, $pcov(\text{absolute_sigma}=\text{False}) = pcov(\text{absolute_sigma}=\text{True}) * chisq(popt) / (M-N)$ |
| check_finite | [bool, optional] If <i>True</i> , check that the input arrays do not contain nans or infs, and raise a <code>ValueError</code> if they do. Setting this parameter to <i>False</i> may silently produce nonsensical results if the input arrays do contain nans. Default is <i>True</i> . |
| bounds | [2-tuple of array_like, optional] Lower and upper bounds on parameters. Defaults to no bounds. Each element of the tuple must be either an array with the length equal to the number of parameters, or a scalar (in which case the bound is taken to be the same for all parameters). Use <code>np.inf</code> with an appropriate sign to disable bounds on all or some parameters.
New in version 0.17. |
| method | [{'lm', 'trf', 'dogbox'}, optional] Method to use for optimization. See least_squares for more details. Default is 'lm' for unconstrained problems and 'trf' if <i>bounds</i> are provided. |

The method 'lm' won't work when the number of observations is less than the number of variables, use 'trf' or 'dogbox' in this case.

New in version 0.17.

jac [callable, string or None, optional] Function with signature `jac(x, ...)` which computes the Jacobian matrix of the model function with respect to parameters as a dense array_like structure. It will be scaled according to provided *sigma*. If None (default), the Jacobian will be estimated numerically. String keywords for 'trf' and 'dogbox' methods can be used to select a finite difference scheme, see *least_squares*.

New in version 0.18.

kwargs Keyword arguments passed to *leastsq* for `method='lm'` or *least_squares* otherwise.

Returns

popt [array] Optimal values for the parameters so that the sum of the squared residuals of $f(xdata, *popt) - ydata$ is minimized.

pcov [2-D array] The estimated covariance of `popt`. The diagonals provide the variance of the parameter estimate. To compute one standard deviation errors on the parameters use `perr = np.sqrt(np.diag(pcov))`.

How the *sigma* parameter affects the estimated covariance depends on *absolute_sigma* argument, as described above.

If the Jacobian matrix at the solution doesn't have a full rank, then 'lm' method returns a matrix filled with `np.inf`, on the other hand 'trf' and 'dogbox' methods use Moore-Penrose pseudoinverse to compute the covariance matrix.

Raises

ValueError

if either *ydata* or *xdata* contain NaNs, or if incompatible options are used.

RuntimeError

if the least-squares minimization fails.

OptimizeWarning

if covariance of the parameters can not be estimated.

See also:

least_squares

Minimize the sum of squares of nonlinear functions.

scipy.stats.linregress

Calculate a linear least squares regression for two sets of measurements.

Notes

With `method='lm'`, the algorithm uses the Levenberg-Marquardt algorithm through *leastsq*. Note that this algorithm can only deal with unconstrained problems.

Box constraints can be handled by methods 'trf' and 'dogbox'. Refer to the docstring of *least_squares* for more information.

Examples

```
>>> import matplotlib.pyplot as plt
>>> from scipy.optimize import curve_fit
```

```
>>> def func(x, a, b, c):
...     return a * np.exp(-b * x) + c
```

Define the data to be fit with some noise:

```
>>> xdata = np.linspace(0, 4, 50)
>>> y = func(xdata, 2.5, 1.3, 0.5)
>>> np.random.seed(1729)
>>> y_noise = 0.2 * np.random.normal(size=xdata.size)
>>> ydata = y + y_noise
>>> plt.plot(xdata, ydata, 'b-', label='data')
```

Fit for the parameters *a*, *b*, *c* of the function *func*:

```
>>> popt, pcov = curve_fit(func, xdata, ydata)
>>> popt
array([ 2.55423706,  1.35190947,  0.47450618])
>>> plt.plot(xdata, func(xdata, *popt), 'r-',
...         label='fit: a=%5.3f, b=%5.3f, c=%5.3f' % tuple(popt))
```

Constrain the optimization to the region of $0 \leq a \leq 3$, $0 \leq b \leq 1$ and $0 \leq c \leq 0.5$:

```
>>> popt, pcov = curve_fit(func, xdata, ydata, bounds=(0, [3., 1., 0.5]))
>>> popt
array([ 2.43708906,  1.         ,  0.35015434])
>>> plt.plot(xdata, func(xdata, *popt), 'g--',
...         label='fit: a=%5.3f, b=%5.3f, c=%5.3f' % tuple(popt))
```

```
>>> plt.xlabel('x')
>>> plt.ylabel('y')
>>> plt.legend()
>>> plt.show()
```

6.19.6 Root finding

Scalar functions

<code>root_scalar(f[, args, method, bracket, ...])</code>	Find a root of a scalar function.
<code>brentq(f, a, b[, args, xtol, rtol, maxiter, ...])</code>	Find a root of a function in a bracketing interval using Brent's method.
<code>brenth(f, a, b[, args, xtol, rtol, maxiter, ...])</code>	Find a root of a function in a bracketing interval using Brent's method with hyperbolic extrapolation.
<code>ridder(f, a, b[, args, xtol, rtol, maxiter, ...])</code>	Find a root of a function in an interval using Ridder's method.
<code>bisect(f, a, b[, args, xtol, rtol, maxiter, ...])</code>	Find root of a function within an interval using bisection.

continues on next page

Table 131 – continued from previous page

<code>newton(func, x0[, fprime, args, tol, ...])</code>	Find a zero of a real or complex function using the Newton-Raphson (or secant or Halley’s) method.
<code>toms748(f, a, b[, args, k, xtol, rtol, ...])</code>	Find a zero using TOMS Algorithm 748 method.
<code>RootResults(root, iterations, ...)</code>	Represents the root finding result.

scipy.optimize.root_scalar

`scipy.optimize.root_scalar` (*f*, *args*=(), *method*=None, *bracket*=None, *fprime*=None, *fprime2*=None, *x0*=None, *x1*=None, *xtol*=None, *rtol*=None, *maxiter*=None, *options*=None)

Find a root of a scalar function.

Parameters

- f** [callable] A function to find a root of.
- args** [tuple, optional] Extra arguments passed to the objective function and its derivative(s).
- method** [str, optional] Type of solver. Should be one of
 - ‘bisect’ ([see here](#))
 - ‘brentq’ ([see here](#))
 - ‘brenth’ ([see here](#))
 - ‘ridder’ ([see here](#))
 - ‘toms748’ ([see here](#))
 - ‘newton’ ([see here](#))
 - ‘secant’ ([see here](#))
 - ‘halley’ ([see here](#))
- bracket:** A sequence of 2 floats, optional
An interval bracketing a root. $f(x, *args)$ must have different signs at the two endpoints.
- x0** [float, optional] Initial guess.
- x1** [float, optional] A second guess.
- fprime** [bool or callable, optional] If *fprime* is a boolean and is True, *f* is assumed to return the value of the objective function and of the derivative. *fprime* can also be a callable returning the derivative of *f*. In this case, it must accept the same arguments as *f*.
- fprime2** [bool or callable, optional] If *fprime2* is a boolean and is True, *f* is assumed to return the value of the objective function and of the first and second derivatives. *fprime2* can also be a callable returning the second derivative of *f*. In this case, it must accept the same arguments as *f*.
- xtol** [float, optional] Tolerance (absolute) for termination.
- rtol** [float, optional] Tolerance (relative) for termination.
- maxiter** [int, optional] Maximum number of iterations.
- options** [dict, optional] A dictionary of solver options. E.g., *k*, see `show_options()` for details.

Returns

- sol** [RootResults] The solution represented as a `RootResults` object. Important attributes are: `root` the solution, `converged` a boolean flag indicating if the algorithm exited successfully and `flag` which describes the cause of the termination. See `RootResults` for a description of other attributes.


See also:

`show_options`

Additional options accepted by the solvers

`root`

Find a root of a vector function.



Notes

This section describes the available solvers that can be selected by the 'method' parameter.

The default is to use the best method available for the situation presented. If a bracket is provided, it may use one of the bracketing methods. If a derivative and an initial value are specified, it may select one of the derivative-based methods. If no method is judged applicable, it will raise an Exception.

Examples

Find the root of a simple cubic

```
>>> from scipy import optimize
>>> def f(x):
...     return (x**3 - 1) # only one real root at x = 1
```

```
>>> def fprime(x):
...     return 3*x**2
```

The `brentq` method takes as input a bracket

```
>>> sol = optimize.root_scalar(f, bracket=[0, 3], method='brentq')
>>> sol.root, sol.iterations, sol.function_calls
(1.0, 10, 11)
```

The `newton` method takes as input a single point and uses the derivative(s)

```
>>> sol = optimize.root_scalar(f, x0=0.2, fprime=fprime, method='newton')
>>> sol.root, sol.iterations, sol.function_calls
(1.0, 11, 22)
```

The function can provide the value and derivative(s) in a single call.

```
>>> def f_p_pp(x):
...     return (x**3 - 1), 3*x**2, 6*x
```

```
>>> sol = optimize.root_scalar(f_p_pp, x0=0.2, fprime=True, method='newton
↳')
>>> sol.root, sol.iterations, sol.function_calls
(1.0, 11, 11)
```

```
>>> sol = optimize.root_scalar(f_p_pp, x0=0.2, fprime=True, fprime2=True,
↳method='halley')
>>> sol.root, sol.iterations, sol.function_calls
(1.0, 7, 8)
```

scipy.optimize.brentq

`scipy.optimize.brentq(f, a, b, args=(), xtol=2e-12, rtol=8.881784197001252e-16, maxiter=100, full_output=False, disp=True)`

Find a root of a function in a bracketing interval using Brent's method.

Uses the classic Brent's method to find a zero of the function f on the sign changing interval $[a, b]$. Generally considered the best of the rootfinding routines here. It is a safe version of the secant method that uses inverse quadratic extrapolation. Brent's method combines root bracketing, interval bisection, and inverse quadratic interpolation. It is sometimes known as the van Wijngaarden-Dekker-Brent method. Brent (1973) claims convergence is guaranteed for functions computable within $[a, b]$.

[Brent1973] provides the classic description of the algorithm. Another description can be found in a recent edition of Numerical Recipes, including [PressEtal1992]. A third description is at <http://mathworld.wolfram.com/BrentsMethod.html>. It should be easy to understand the algorithm just by reading our code. Our code diverges a bit from standard presentations: we choose a different formula for the extrapolation step.

Parameters

- f** [function] Python function returning a number. The function f must be continuous, and $f(a)$ and $f(b)$ must have opposite signs.
- a** [scalar] One end of the bracketing interval $[a, b]$.
- b** [scalar] The other end of the bracketing interval $[a, b]$.
- xtol** [number, optional] The computed root x_0 will satisfy `np.allclose(x, x0, atol=xtol, rtol=rtol)`, where x is the exact root. The parameter must be nonnegative. For nice functions, Brent's method will often satisfy the above condition with $xtol/2$ and $rtol/2$. [Brent1973]
- rtol** [number, optional] The computed root x_0 will satisfy `np.allclose(x, x0, atol=xtol, rtol=rtol)`, where x is the exact root. The parameter cannot be smaller than its default value of $4 * np.finfo(float).eps$. For nice functions, Brent's method will often satisfy the above condition with $xtol/2$ and $rtol/2$. [Brent1973]
- maxiter** [int, optional] If convergence is not achieved in *maxiter* iterations, an error is raised. Must be ≥ 0 .
- args** [tuple, optional] Containing extra arguments for the function f . f is called by `apply(f, (x)+args)`.
- full_output** [bool, optional] If *full_output* is False, the root is returned. If *full_output* is True, the return value is (x, r) , where x is the root, and r is a *RootResults* object.
- disp** [bool, optional] If True, raise `RuntimeError` if the algorithm didn't converge. Otherwise, the convergence status is recorded in any *RootResults* return object.

Returns

x0 [float] Zero of f between a and b .
r [`RootResults` (present if `full_output = True`)] Object containing information about the convergence. In particular, `r.converged` is `True` if the routine converged.

Notes

f must be continuous. $f(a)$ and $f(b)$ must have opposite signs.

Related functions fall into several classes:

multivariate local optimizers

`fmin`, `fmin_powell`, `fmin_cg`, `fmin_bfgs`, `fmin_ncg`

nonlinear least squares minimizer

`leastsq`

constrained multivariate optimizers

`fmin_l_bfgs_b`, `fmin_tnc`, `fmin_cobyla`

global optimizers

`basinhopping`, `brute`, `differential_evolution`

local scalar minimizers

`fminbound`, `brent`, `golden`, `bracket`

N-D root-finding

`fsolve`

1-D root-finding

`brenth`, `ridder`, `bisect`, `newton`

scalar fixed-point finder

`fixed_point`

References

[Brent1973], [PressEtal1992]

Examples

```
>>> def f(x):
...     return (x**2 - 1)
```

```
>>> from scipy import optimize
```

```
>>> root = optimize.brentq(f, -2, 0)
>>> root
-1.0
```

```
>>> root = optimize.brentq(f, 0, 2)
>>> root
1.0
```

scipy.optimize.brenth

`scipy.optimize.brenth(f, a, b, args=(), xtol=2e-12, rtol=8.881784197001252e-16, maxiter=100, full_output=False, disp=True)`

Find a root of a function in a bracketing interval using Brent's method with hyperbolic extrapolation.

A variation on the classic Brent routine to find a zero of the function f between the arguments a and b that uses hyperbolic extrapolation instead of inverse quadratic extrapolation. There was a paper back in the 1980's ... $f(a)$ and $f(b)$ cannot have the same signs. Generally, on a par with the `brent` routine, but not as heavily tested. It is a safe version of the secant method that uses hyperbolic extrapolation. The version here is by Chuck Harris.

Parameters

- f** [function] Python function returning a number. f must be continuous, and $f(a)$ and $f(b)$ must have opposite signs.
- a** [scalar] One end of the bracketing interval $[a,b]$.
- b** [scalar] The other end of the bracketing interval $[a,b]$.
- xtol** [number, optional] The computed root x_0 will satisfy `np.allclose(x, x0, atol=xtol, rtol=rtol)`, where x is the exact root. The parameter must be nonnegative. As with `brentq`, for nice functions the method will often satisfy the above condition with $xtol/2$ and $rtol/2$.
- rtol** [number, optional] The computed root x_0 will satisfy `np.allclose(x, x0, atol=xtol, rtol=rtol)`, where x is the exact root. The parameter cannot be smaller than its default value of $4 * \text{np.finfo(float)}.eps$. As with `brentq`, for nice functions the method will often satisfy the above condition with $xtol/2$ and $rtol/2$.
- maxiter** [int, optional] If convergence is not achieved in *maxiter* iterations, an error is raised. Must be ≥ 0 .
- args** [tuple, optional] Containing extra arguments for the function f . f is called by `apply(f, (x)+args)`.
- full_output** [bool, optional] If *full_output* is False, the root is returned. If *full_output* is True, the return value is (x, r) , where x is the root, and r is a `RootResults` object.
- disp** [bool, optional] If True, raise `RuntimeError` if the algorithm didn't converge. Otherwise, the convergence status is recorded in any `RootResults` return object.

Returns

- x0** [float] Zero of f between a and b .
- r** [`RootResults` (present if `full_output = True`)] Object containing information about the convergence. In particular, `r.converged` is True if the routine converged.

See also:

[`fmin`](#), [`fmin_powell`](#), [`fmin_cg`](#)

[`fmin_bfgs`](#), [`fmin_ncg`](#)

multivariate local optimizers

[`leastsq`](#)

nonlinear least squares minimizer

[`fmin_l_bfgs_b`](#), [`fmin_tnc`](#), [`fmin_cobyla`](#)

constrained multivariate optimizers

basinhopping, differential_evolution, brute

global optimizers

fminbound, brent, golden, bracket

local scalar minimizers

fsolve

N-D root-finding

brentq, brentb, ridder, bisect, newton

1-D root-finding

fixed_point

scalar fixed-point finder

Examples

```
>>> def f(x):
...     return (x**2 - 1)
```

```
>>> from scipy import optimize
```

```
>>> root = optimize.brentq(f, -2, 0)
>>> root
-1.0
```

```
>>> root = optimize.brentq(f, 0, 2)
>>> root
1.0
```

scipy.optimize.ridder

`scipy.optimize.ridder(f, a, b, args=(), xtol=2e-12, rtol=8.881784197001252e-16, maxiter=100, full_output=False, disp=True)`

Find a root of a function in an interval using Ridder's method.

Parameters

f	[function] Python function returning a number. <i>f</i> must be continuous, and <i>f</i> (<i>a</i>) and <i>f</i> (<i>b</i>) must have opposite signs.
a	[scalar] One end of the bracketing interval [<i>a</i> , <i>b</i>].
b	[scalar] The other end of the bracketing interval [<i>a</i> , <i>b</i>].
xtol	[number, optional] The computed root <i>x0</i> will satisfy <code>np.allclose(x, x0, atol=xtol, rtol=rtol)</code> , where <i>x</i> is the exact root. The parameter must be non-negative.
rtol	[number, optional] The computed root <i>x0</i> will satisfy <code>np.allclose(x, x0, atol=xtol, rtol=rtol)</code> , where <i>x</i> is the exact root. The parameter cannot be smaller than its default value of <code>4*np.finfo(float).eps</code> .
maxiter	[int, optional] If convergence is not achieved in <i>maxiter</i> iterations, an error is raised. Must be ≥ 0 .
args	[tuple, optional] Containing extra arguments for the function <i>f</i> . <i>f</i> is called by <code>apply(f, (x)+args)</code> .

full_output

[bool, optional] If *full_output* is False, the root is returned. If *full_output* is True, the return value is (x, r) , where x is the root, and r is a *RootResults* object.

disp

[bool, optional] If True, raise RuntimeError if the algorithm didn't converge. Otherwise, the convergence status is recorded in any *RootResults* return object.

Returns

x0 [float] Zero of f between a and b .

r [*RootResults* (present if `full_output = True`)] Object containing information about the convergence. In particular, `r.converged` is True if the routine converged.

See also:

brentq, *brenth*, *bisect*, *newton*

1-D root-finding

fixed_point

scalar fixed-point finder

Notes

Uses [Ridders1979] method to find a zero of the function f between the arguments a and b . Ridders' method is faster than bisection, but not generally as fast as the Brent routines. [Ridders1979] provides the classic description and source of the algorithm. A description can also be found in any recent edition of Numerical Recipes.

The routine used here diverges slightly from standard presentations in order to be a bit more careful of tolerance.

References

[Ridders1979]

Examples

```
>>> def f(x):  
...     return (x**2 - 1)
```

```
>>> from scipy import optimize
```

```
>>> root = optimize.ridder(f, 0, 2)  
>>> root  
1.0
```

```
>>> root = optimize.ridder(f, -2, 0)  
>>> root  
-1.0
```

scipy.optimize.bisect

`scipy.optimize.bisect` (*f*, *a*, *b*, *args*=(), *xtol*= $2e-12$, *rtol*= $8.881784197001252e-16$, *maxiter*=100, *full_output*=False, *disp*=True)

Find root of a function within an interval using bisection.

Basic bisection routine to find a zero of the function *f* between the arguments *a* and *b*. *f*(*a*) and *f*(*b*) cannot have the same signs. Slow but sure.

Parameters

- f** [function] Python function returning a number. *f* must be continuous, and *f*(*a*) and *f*(*b*) must have opposite signs.
- a** [scalar] One end of the bracketing interval [*a*,*b*].
- b** [scalar] The other end of the bracketing interval [*a*,*b*].
- xtol** [number, optional] The computed root *x0* will satisfy `np.allclose(x, x0, atol=xtol, rtol=rtol)`, where *x* is the exact root. The parameter must be non-negative.
- rtol** [number, optional] The computed root *x0* will satisfy `np.allclose(x, x0, atol=xtol, rtol=rtol)`, where *x* is the exact root. The parameter cannot be smaller than its default value of `4*np.finfo(float).eps`.
- maxiter** [int, optional] If convergence is not achieved in *maxiter* iterations, an error is raised. Must be ≥ 0 .
- args** [tuple, optional] Containing extra arguments for the function *f*. *f* is called by `apply(f, (x)+args)`.
- full_output** [bool, optional] If *full_output* is False, the root is returned. If *full_output* is True, the return value is (*x*, *r*), where *x* is the root, and *r* is a *RootResults* object.
- disp** [bool, optional] If True, raise `RuntimeError` if the algorithm didn't converge. Otherwise, the convergence status is recorded in a *RootResults* return object.

Returns

- x0** [float] Zero of *f* between *a* and *b*.
- r** [*RootResults* (present if *full_output* = True)] Object containing information about the convergence. In particular, *r*.*converged* is True if the routine converged.

See also:

brentq, *brenth*, *bisect*, *newton*

fixed_point

scalar fixed-point finder

fsolve

n-dimensional root-finding

Examples

```
>>> def f(x):
...     return (x**2 - 1)
```

```
>>> from scipy import optimize
```

```
>>> root = optimize.bisect(f, 0, 2)
>>> root
1.0
```

```
>>> root = optimize.bisect(f, -2, 0)
>>> root
-1.0
```

scipy.optimize.newton

`scipy.optimize.newton` (*func*, *x0*, *fprime=None*, *args=()*, *tol=1.48e-08*, *maxiter=50*, *fprime2=None*, *x1=None*, *rtol=0.0*, *full_output=False*, *disp=True*)

Find a zero of a real or complex function using the Newton-Raphson (or secant or Halley's) method.

Find a zero of the function *func* given a nearby starting point *x0*. The Newton-Raphson method is used if the derivative *fprime* of *func* is provided, otherwise the secant method is used. If the second order derivative *fprime2* of *func* is also provided, then Halley's method is used.

If *x0* is a sequence with more than one item, then *newton* returns an array, and *func* must be vectorized and return a sequence or array of the same shape as its first argument. If *fprime* or *fprime2* is given, then its return must also have the same shape.

Parameters

func	[callable] The function whose zero is wanted. It must be a function of a single variable of the form $f(x, a, b, c, \dots)$, where a, b, c, \dots are extra arguments that can be passed in the <i>args</i> parameter.
x0	[float, sequence, or ndarray] An initial estimate of the zero that should be somewhere near the actual zero. If not scalar, then <i>func</i> must be vectorized and return a sequence or array of the same shape as its first argument.
fprime	[callable, optional] The derivative of the function when available and convenient. If it is None (default), then the secant method is used.
args	[tuple, optional] Extra arguments to be used in the function call.
tol	[float, optional] The allowable error of the zero value. If <i>func</i> is complex-valued, a larger <i>tol</i> is recommended as both the real and imaginary parts of x contribute to $ x - x_0 $.
maxiter	[int, optional] Maximum number of iterations.
fprime2	[callable, optional] The second order derivative of the function when available and convenient. If it is None (default), then the normal Newton-Raphson or the secant method is used. If it is not None, then Halley's method is used.
x1	[float, optional] Another estimate of the zero that should be somewhere near the actual zero. Used if <i>fprime</i> is not provided.
rtol	[float, optional] Tolerance (relative) for termination.
full_output	[bool, optional] If <i>full_output</i> is False (default), the root is returned. If True and <i>x0</i> is scalar, the return value is (x, r) , where x is the root and r is a <i>RootResults</i> object. If True and <i>x0</i> is non-scalar, the return value is $(x, converged, zero_der)$ (see Returns section for details).

disp [bool, optional] If True, raise a `RuntimeError` if the algorithm didn't converge, with the error message containing the number of iterations and current function value. Otherwise, the convergence status is recorded in a `RootResults` return object. Ignored if `x0` is not scalar. *Note: this has little to do with displaying, however, the ``disp`` keyword cannot be renamed for backwards compatibility.*

Returns

root [float, sequence, or ndarray] Estimated location where function is zero.

r [`RootResults`, optional] Present if `full_output=True` and `x0` is scalar. Object containing information about the convergence. In particular, `r.converged` is True if the routine converged.

converged [ndarray of bool, optional] Present if `full_output=True` and `x0` is non-scalar. For vector functions, indicates which elements converged successfully.

zero_der [ndarray of bool, optional] Present if `full_output=True` and `x0` is non-scalar. For vector functions, indicates which elements had a zero derivative.

See also:

[`brentq`](#), [`brenth`](#), [`ridder`](#), [`bisect`](#)

[`fsolve`](#)

find zeros in N dimensions.

Notes

The convergence rate of the Newton-Raphson method is quadratic, the Halley method is cubic, and the secant method is sub-quadratic. This means that if the function is well-behaved the actual error in the estimated zero after the n th iteration is approximately the square (cube for Halley) of the error after the $(n-1)$ th step. However, the stopping criterion used here is the step size and there is no guarantee that a zero has been found. Consequently, the result should be verified. Safer algorithms are `brentq`, `brenth`, `ridder`, and `bisect`, but they all require that the root first be bracketed in an interval where the function changes sign. The `brentq` algorithm is recommended for general use in one dimensional problems when such an interval has been found.

When `newton` is used with arrays, it is best suited for the following types of problems:

- The initial guesses, `x0`, are all relatively the same distance from the roots.
- Some or all of the extra arguments, `args`, are also arrays so that a class of similar problems can be solved together.
- The size of the initial guesses, `x0`, is larger than $O(100)$ elements. Otherwise, a naive loop may perform as well or better than a vector.

Examples

```
>>> from scipy import optimize
>>> import matplotlib.pyplot as plt
```

```
>>> def f(x):
...     return (x**3 - 1) # only one real root at x = 1
```

`fprime` is not provided, use the secant method:

```

>>> root = optimize.newton(f, 1.5)
>>> root
1.00000000000000016
>>> root = optimize.newton(f, 1.5, fprime2=lambda x: 6 * x)
>>> root
1.00000000000000016

```

Only `fprime` is provided, use the Newton-Raphson method:

```

>>> root = optimize.newton(f, 1.5, fprime=lambda x: 3 * x**2)
>>> root
1.0

```

Both `fprime2` and `fprime` are provided, use Halley's method:

```

>>> root = optimize.newton(f, 1.5, fprime=lambda x: 3 * x**2,
...                          fprime2=lambda x: 6 * x)
>>> root
1.0

```

When we want to find zeros for a set of related starting values and/or function parameters, we can provide both of those as an array of inputs:

```

>>> f = lambda x, a: x**3 - a
>>> fder = lambda x, a: 3 * x**2
>>> np.random.seed(4321)
>>> x = np.random.randn(100)
>>> a = np.arange(-50, 50)
>>> vec_res = optimize.newton(f, x, fprime=fder, args=(a, ))

```

The above is the equivalent of solving for each value in (x, a) separately in a for-loop, just faster:

```

>>> loop_res = [optimize.newton(f, x0, fprime=fder, args=(a0,))
...              for x0, a0 in zip(x, a)]
>>> np.allclose(vec_res, loop_res)
True


```

Plot the results found for all values of `a`:

```

>>> analytical_result = np.sign(a) * np.abs(a)**(1/3)
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> ax.plot(a, analytical_result, 'o')
>>> ax.plot(a, vec_res, '.')
>>> ax.set_xlabel('$a$')
>>> ax.set_ylabel('$x$ where $f(x, a)=0$')
>>> plt.show()

```



scipy.optimize.toms748

`scipy.optimize.toms748` (*f*, *a*, *b*, *args*=(), *k*=1, *xtol*=2e-12, *rtol*=8.881784197001252e-16, *maxiter*=100, *full_output*=False, *disp*=True)

Find a zero using TOMS Algorithm 748 method.

Implements the Algorithm 748 method of Alefeld, Potro and Shi to find a zero of the function *f* on the interval [*a*, *b*], where *f*(*a*) and *f*(*b*) must have opposite signs.

It uses a mixture of inverse cubic interpolation and “Newton-quadratic” steps. [APS1995].

Parameters

- f** [function] Python function returning a scalar. The function *f* must be continuous, and *f*(*a*) and *f*(*b*) have opposite signs.
- a** [scalar,] lower boundary of the search interval
- b** [scalar,] upper boundary of the search interval
- args** [tuple, optional] containing extra arguments for the function *f*. *f* is called by `f(x, *args)`.
- k** [int, optional] The number of Newton quadratic steps to perform each iteration. *k* >= 1.
- xtol** [scalar, optional] The computed root *x*₀ will satisfy `np.allclose(x, x0, atol=xtol, rtol=rtol)`, where *x* is the exact root. The parameter must be non-negative.
- rtol** [scalar, optional] The computed root *x*₀ will satisfy `np.allclose(x, x0, atol=xtol, rtol=rtol)`, where *x* is the exact root.
- maxiter** [int, optional] If convergence is not achieved in *maxiter* iterations, an error is raised. Must be >= 0.
- full_output** [bool, optional] If *full_output* is False, the root is returned. If *full_output* is True, the return value is (*x*, *r*), where *x* is the root, and *r* is a `RootResults` object.
- disp** [bool, optional] If True, raise `RuntimeError` if the algorithm didn’t converge. Otherwise, the convergence status is recorded in the `RootResults` return object.

Returns

- x0** [float] Approximate Zero of *f*
- r** [`RootResults` (present if `full_output = True`)] Object containing information about the convergence. In particular, `r.converged` is True if the routine converged.

See also:

brentq, brentk, ridder, bisect, newton

fsolve

find zeroes in N dimensions.

Notes

f must be continuous. Algorithm 748 with $k=2$ is asymptotically the most efficient algorithm known for finding roots of a four times continuously differentiable function. In contrast with Brent's algorithm, which may only decrease the length of the enclosing bracket on the last step, Algorithm 748 decreases it each iteration with the same asymptotic efficiency as it finds the root.

For easy statement of efficiency indices, assume that f has 4 continuous derivatives. For $k=1$, the convergence order is at least 2.7, and with about asymptotically 2 function evaluations per iteration, the efficiency index is approximately 1.65. For $k=2$, the order is about 4.6 with asymptotically 3 function evaluations per iteration, and the efficiency index 1.66. For higher values of k , the efficiency index approaches the k th root of $(3k-2)$, hence $k=1$ or $k=2$ are usually appropriate.

References

[APS1995]

Examples

```
>>> def f(x):
...     return (x**3 - 1) # only one real root at x = 1
```

```
>>> from scipy import optimize
>>> root, results = optimize.toms748(f, 0, 2, full_output=True)
>>> root
1.0
>>> results
   converged: True
      flag: 'converged'
function_calls: 11
  iterations: 5
         root: 1.0
```

scipy.optimize.RootResults

class `scipy.optimize.RootResults` (*root, iterations, function_calls, flag*)

Represents the root finding result.

Attributes

root	[float] Estimated root location.
iterations	[int] Number of iterations needed to find the root.
function_calls	[int] Number of times the function was called.
converged	[bool] True if the routine converged.
flag	[str] Description of the cause of termination.

The `root_scalar` function supports the following methods:

`root_scalar(method='brentq')`

`scipy.optimize.root_scalar` (*args=()*, *method='brentq'*, *x0=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.root_scalar`

Options

args [tuple, optional] Extra arguments passed to the objective function.
xtol [float, optional] Tolerance (absolute) for termination.
rtol [float, optional] Tolerance (relative) for termination.
maxiter [int, optional] Maximum number of iterations.
options: dict, optional
 Specifies any method-specific options not covered above

`root_scalar(method='brenth')`

`scipy.optimize.root_scalar` (*args=()*, *method='brenth'*, *x0=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.root_scalar`

Options

args [tuple, optional] Extra arguments passed to the objective function.
xtol [float, optional] Tolerance (absolute) for termination.
rtol [float, optional] Tolerance (relative) for termination.
maxiter [int, optional] Maximum number of iterations.
options: dict, optional
 Specifies any method-specific options not covered above.

`root_scalar(method='bisect')`

`scipy.optimize.root_scalar` (*args=()*, *method='bisect'*, *x0=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.root_scalar`

Options

args [tuple, optional] Extra arguments passed to the objective function.
xtol [float, optional] Tolerance (absolute) for termination.
rtol [float, optional] Tolerance (relative) for termination.
maxiter [int, optional] Maximum number of iterations.
options: dict, optional
 Specifies any method-specific options not covered above.

`root_scalar(method='ridder')`

`scipy.optimize.root_scalar` (*args=()*, *method='ridder'*, *x0=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.root_scalar`

Options

- args** [tuple, optional] Extra arguments passed to the objective function.
- xtol** [float, optional] Tolerance (absolute) for termination.
- rtol** [float, optional] Tolerance (relative) for termination.
- maxiter** [int, optional] Maximum number of iterations.
- options: dict, optional**
Specifies any method-specific options not covered above.

`root_scalar(method='newton')`

`scipy.optimize.root_scalar` (*args=()*, *method='newton'*, *x0=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.root_scalar`

Options

- args** [tuple, optional] Extra arguments passed to the objective function and its derivative.
- xtol** [float, optional] Tolerance (absolute) for termination.
- rtol** [float, optional] Tolerance (relative) for termination.
- maxiter** [int, optional] Maximum number of iterations.
- x0** [float, required] Initial guess.
- fprime** [bool or callable, optional] If *fprime* is a boolean and is True, *f* is assumed to return the value of derivative along with the objective function. *fprime* can also be a callable returning the derivative of *f*. In this case, it must accept the same arguments as *f*.
- options: dict, optional**
Specifies any method-specific options not covered above.

`root_scalar(method='toms748')`

`scipy.optimize.root_scalar` (*args=()*, *method='toms748'*, *x0=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.root_scalar`

Options

- args** [tuple, optional] Extra arguments passed to the objective function.
- xtol** [float, optional] Tolerance (absolute) for termination.
- rtol** [float, optional] Tolerance (relative) for termination.
- maxiter** [int, optional] Maximum number of iterations.
- options: dict, optional**
Specifies any method-specific options not covered above.

root_scalar(method='secant')

`scipy.optimize.root_scalar` (*args=()*, *method='secant'*, *x0=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.root_scalar`

Options

args	[tuple, optional] Extra arguments passed to the objective function.
xtol	[float, optional] Tolerance (absolute) for termination.
rtol	[float, optional] Tolerance (relative) for termination.
maxiter	[int, optional] Maximum number of iterations.
x0	[float, required] Initial guess.
x1	[float, required] A second guess.
options: dict, optional	Specifies any method-specific options not covered above.

root_scalar(method='halley')

`scipy.optimize.root_scalar` (*args=()*, *method='halley'*, *x0=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.root_scalar`

Options

args	[tuple, optional] Extra arguments passed to the objective function and its derivatives.
xtol	[float, optional] Tolerance (absolute) for termination.
rtol	[float, optional] Tolerance (relative) for termination.
maxiter	[int, optional] Maximum number of iterations.
x0	[float, required] Initial guess.
fprime	[bool or callable, required] If <i>fprime</i> is a boolean and is True, <i>f</i> is assumed to return the value of derivative along with the objective function. <i>fprime</i> can also be a callable returning the derivative of <i>f</i> . In this case, it must accept the same arguments as <i>f</i> .
fprime2	[bool or callable, required] If <i>fprime2</i> is a boolean and is True, <i>f</i> is assumed to return the value of 1st and 2nd derivatives along with the objective function. <i>fprime2</i> can also be a callable returning the 2nd derivative of <i>f</i> . In this case, it must accept the same arguments as <i>f</i> .
options: dict, optional	Specifies any method-specific options not covered above.

The table below lists situations and appropriate methods, along with *asymptotic* convergence rates per iteration (and per function evaluation) for successful convergence to a simple root(*). Bisection is the slowest of them all, adding one bit of accuracy for each function evaluation, but is guaranteed to converge. The other bracketing methods all (eventually) increase the number of accurate bits by about 50% for every function evaluation. The derivative-based methods, all built on *newton*, can converge quite quickly if the initial value is close to the root. They can also be applied to functions defined on (a subset of) the complex plane.

Domain of f	Bracket?	Derivatives?		Solvers	Convergence	
		<i>fprime</i>	<i>fprime2</i>		Guaranteed?	Rate(s)(*)
<i>R</i>	Yes	N/A	N/A	<ul style="list-style-type: none"> • bisection • brentq • brenth • ridder • toms748 	<ul style="list-style-type: none"> • Yes • Yes • Yes • Yes • Yes 	<ul style="list-style-type: none"> • 1 “Linear” • ≥ 1, ≤ 1.62 • ≥ 1, ≤ 1.62 • 2.0 (1.41) • 2.7 (1.65)
<i>R</i> or <i>C</i>	No	No	No	secant	No	1.62 (1.62)
<i>R</i> or <i>C</i>	No	Yes	No	newton	No	2.00 (1.41)
<i>R</i> or <i>C</i>	No	Yes	Yes	halley	No	3.00 (1.44)

See also:

`scipy.optimize.cython_optimize` – Typed Cython versions of zeros functions

Fixed point finding:

<code>fixed_point(func, x0[, args, xtol, maxiter, ...])</code>	Find a fixed point of the function.
--	-------------------------------------

scipy.optimize.fixed_point

`scipy.optimize.fixed_point` (*func*, *x0*, *args*=(*...*), *xtol*=1e-08, *maxiter*=500, *method*='del2')

Find a fixed point of the function.

Given a function of one or more variables and a starting point, find a fixed point of the function: i.e., where `func(x0) == x0`.

Parameters

- func** [function] Function to evaluate.
- x0** [array_like] Fixed point of function.
- args** [tuple, optional] Extra arguments to *func*.
- xtol** [float, optional] Convergence tolerance, defaults to 1e-08.
- maxiter** [int, optional] Maximum number of iterations, defaults to 500.
- method** [{"del2", "iteration"}, optional] Method of finding the fixed-point, defaults to “del2”, which uses Steffensen’s Method with Aitken’s $De1^2$ convergence acceleration [1]. The “iteration” method simply iterates the function until convergence is detected, without attempting to accelerate the convergence.

References

[1]

Examples

```
>>> from scipy import optimize
>>> def func(x, c1, c2):
...     return np.sqrt(c1/(x+c2))
>>> c1 = np.array([10, 12.])
>>> c2 = np.array([3, 5.])
>>> optimize.fixed_point(func, [1.2, 1.3], args=(c1, c2))
array([ 1.4920333 ,  1.37228132])
```

Multidimensional

<code>root(fun, x0[, args, method, jac, tol, ...])</code>	Find a root of a vector function.
---	-----------------------------------

scipy.optimize.root

`scipy.optimize.root` (*fun*, *x0*, *args*=(), *method*='hybr', *jac*=None, *tol*=None, *callback*=None, *options*=None)

Find a root of a vector function.

Parameters

fun	[callable] A vector function to find a root of.
x0	[ndarray] Initial guess.
args	[tuple, optional] Extra arguments passed to the objective function and its Jacobian.
method	[str, optional] Type of solver. Should be one of <ul style="list-style-type: none"> • 'hybr' (see here) • 'lm' (see here) • 'broyden1' (see here) • 'broyden2' (see here) • 'anderson' (see here) • 'linearmixing' (see here) • 'diagbroyden' (see here) • 'excitingmixing' (see here) • 'krylov' (see here) • 'df-sane' (see here)
jac	[bool or callable, optional] If <i>jac</i> is a Boolean and is True, <i>fun</i> is assumed to return the value of Jacobian along with the objective function. If False, the Jacobian will be estimated numerically. <i>jac</i> can also be a callable returning the Jacobian of <i>fun</i> . In this case, it must accept the same arguments as <i>fun</i> .
tol	[float, optional] Tolerance for termination. For detailed control, use solver-specific options.
callback	[function, optional] Optional callback function. It is called on every iteration as <code>callback(x, f)</code> where <i>x</i> is the current solution and <i>f</i> the corresponding residual. For all methods but 'hybr' and 'lm'.
options	[dict, optional] A dictionary of solver options. E.g., <i>xtol</i> or <i>maxiter</i> , see <code>show_options()</code> for details.

Returns

sol [OptimizeResult] The solution represented as a `OptimizeResult` object. Important attributes are: `x` the solution array, `success` a Boolean flag indicating if the algorithm exited successfully and `message` which describes the cause of the termination. See `OptimizeResult` for a description of other attributes.

See also:

`show_options`

Additional options accepted by the solvers

Notes

This section describes the available solvers that can be selected by the ‘method’ parameter. The default method is *hybr*.

Method *hybr* uses a modification of the Powell hybrid method as implemented in MINPACK [1].

Method *lm* solves the system of nonlinear equations in a least squares sense using a modification of the Levenberg-Marquardt algorithm as implemented in MINPACK [1].

Method *df-sane* is a derivative-free spectral method. [3]

Methods *broyden1*, *broyden2*, *anderson*, *linearmixing*, *diagbroyden*, *excitingmixing*, *krylov* are inexact Newton methods, with backtracking or full line searches [2]. Each method corresponds to a particular Jacobian approximations. See *nonlin* for details.

- Method *broyden1* uses Broyden’s first Jacobian approximation, it is known as Broyden’s good method.
- Method *broyden2* uses Broyden’s second Jacobian approximation, it is known as Broyden’s bad method.
- Method *anderson* uses (extended) Anderson mixing.
- Method *Krylov* uses Krylov approximation for inverse Jacobian. It is suitable for large-scale problem.
- Method *diagbroyden* uses diagonal Broyden Jacobian approximation.
- Method *linearmixing* uses a scalar Jacobian approximation.
- Method *excitingmixing* uses a tuned diagonal Jacobian approximation.

Warning: The algorithms implemented for methods *diagbroyden*, *linearmixing* and *excitingmixing* may be useful for specific problems, but whether they will work may depend strongly on the problem.

New in version 0.11.0.

References

[1], [2], [3]

Examples

The following functions define a system of nonlinear equations and its jacobian.

```
>>> def fun(x):
...     return [x[0] + 0.5 * (x[0] - x[1])**3 - 1.0,
...            0.5 * (x[1] - x[0])**3 + x[1]]
```

```
>>> def jac(x):
...     return np.array([[1 + 1.5 * (x[0] - x[1])**2,
...                      -1.5 * (x[0] - x[1])**2],
...                     [-1.5 * (x[1] - x[0])**2,
...                      1 + 1.5 * (x[1] - x[0])**2]])
```

A solution can be obtained as follows.

```
>>> from scipy import optimize
>>> sol = optimize.root(fun, [0, 0], jac=jac, method='hybr')
>>> sol.x
array([ 0.8411639,  0.1588361])
```

The `root` function supports the following methods:

`root(method='hybr')`

`scipy.optimize.root` (*fun*, *x0*, *args=()*, *method='hybr'*, *jac=None*, *tol=None*, *callback=None*, *options={'func': None, 'col_deriv': 0, 'xtol': 1.49012e-08, 'maxfev': 0, 'band': None, 'eps': None, 'factor': 100, 'diag': None}*)

Find the roots of a multivariate function using MINPACK's `hybrd` and `hybrj` routines (modified Powell method).

See also:

For documentation for the rest of the parameters, see `scipy.optimize.root`

Options

- col_deriv** [bool] Specify whether the Jacobian function computes derivatives down the columns (faster, because there is no transpose operation).
- xtol** [float] The calculation will terminate if the relative error between two consecutive iterates is at most *xtol*.
- maxfev** [int] The maximum number of calls to the function. If zero, then $100 * (N+1)$ is the maximum where N is the number of elements in *x0*.
- band** [tuple] If set to a two-sequence containing the number of sub- and super-diagonals within the band of the Jacobi matrix, the Jacobi matrix is considered banded (only for `fprime=None`).
- eps** [float] A suitable step length for the forward-difference approximation of the Jacobian (for `fprime=None`). If *eps* is less than the machine precision, it is assumed that the relative errors in the functions are of the order of the machine precision.
- factor** [float] A parameter determining the initial step bound (`factor * ||diag * x||`). Should be in the interval $(0.1, 100)$.
- diag** [sequence] N positive entries that serve as a scale factors for the variables.

root(method='lm')

`scipy.optimize.root` (*fun*, *x0*, *args=()*, *method='lm'*, *jac=None*, *tol=None*, *callback=None*, *options={'col_deriv': 0, 'xtol': 1.49012e-08, 'ftol': 1.49012e-08, 'gtol': 0.0, 'maxiter': 0, 'eps': 0.0, 'factor': 100, 'diag': None}*)

Solve for least squares with Levenberg-Marquardt

See also:

For documentation for the rest of the parameters, see [scipy.optimize.root](#)

Options

col_deriv	[bool] non-zero to specify that the Jacobian function computes derivatives down the columns (faster, because there is no transpose operation).
ftol	[float] Relative error desired in the sum of squares.
xtol	[float] Relative error desired in the approximate solution.
gtol	[float] Orthogonality desired between the function vector and the columns of the Jacobian.
maxiter	[int] The maximum number of calls to the function. If zero, then 100*(N+1) is the maximum where N is the number of elements in <i>x0</i> .
epsfcn	[float] A suitable step length for the forward-difference approximation of the Jacobian (for <i>Dfun=None</i>). If <i>epsfcn</i> is less than the machine precision, it is assumed that the relative errors in the functions are of the order of the machine precision.
factor	[float] A parameter determining the initial step bound (<i>factor</i> * diag * x). Should be in interval (0.1, 100).
diag	[sequence] N positive entries that serve as a scale factors for the variables.

root(method='broyden1')

`scipy.optimize.root` (*fun*, *x0*, *args=()*, *method='broyden1'*, *tol=None*, *callback=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see [scipy.optimize.root](#)

Options

nit	[int, optional] Number of iterations to make. If omitted (default), make as many as required to meet tolerances.
disp	[bool, optional] Print status to stdout on every iteration.
maxiter	[int, optional] Maximum number of iterations to make. If more are needed to meet convergence, <i>NoConvergence</i> is raised.
ftol	[float, optional] Relative tolerance for the residual. If omitted, not used.
fatol	[float, optional] Absolute tolerance (in max-norm) for the residual. If omitted, default is 6e-6.
xtol	[float, optional] Relative minimum step size. If omitted, not used.
xatol	[float, optional] Absolute minimum step size, as determined from the Jacobian approximation. If the step size is smaller than this, optimization is terminated as successful. If omitted, not used.
tol_norm	[function(vector) -> scalar, optional] Norm to use in convergence check. Default is the maximum norm.
line_search	[{None, 'armijo' (default), 'wolfe'}, optional] Which type of a line search to use to determine the step size in the direction given by the Jacobian approximation. Defaults to 'armijo'.
jac_options	[dict, optional] Options for the respective Jacobian approximation.

alpha [float, optional] Initial guess for the Jacobian is $(-1/\text{alpha})$.

reduction_method [str or tuple, optional] Method used in ensuring that the rank of the Broyden matrix stays low. Can either be a string giving the name of the method, or a tuple of the form `(method, param1, param2, ...)` that gives the name of the method and values for additional parameters.

Methods available:

- **restart** Drop all matrix columns. Has no extra parameters.
- **simple** Drop oldest matrix column. Has no extra parameters.
- **svd** Keep only the most significant SVD components.
Extra parameters:
– **to_retain** Number of SVD components to retain when rank reduction is done. Default is `max_rank - 2`.

max_rank [int, optional] Maximum rank for the Broyden matrix. Default is infinity (i.e., no rank reduction).

`root(method='broyden2')`

`scipy.optimize.root` (*fun*, *x0*, *args=()*, *method='broyden2'*, *tol=None*, *callback=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.root`

Options

nit [int, optional] Number of iterations to make. If omitted (default), make as many as required to meet tolerances.

disp [bool, optional] Print status to stdout on every iteration.

maxiter [int, optional] Maximum number of iterations to make. If more are needed to meet convergence, *NoConvergence* is raised.

ftol [float, optional] Relative tolerance for the residual. If omitted, not used.

fatol [float, optional] Absolute tolerance (in max-norm) for the residual. If omitted, default is $6e-6$.

xtol [float, optional] Relative minimum step size. If omitted, not used.

xatol [float, optional] Absolute minimum step size, as determined from the Jacobian approximation. If the step size is smaller than this, optimization is terminated as successful. If omitted, not used.

tol_norm [function(vector) -> scalar, optional] Norm to use in convergence check. Default is the maximum norm.

line_search [{None, 'armijo' (default), 'wolfe'}, optional] Which type of a line search to use to determine the step size in the direction given by the Jacobian approximation. Defaults to 'armijo'.

jac_options [dict, optional] Options for the respective Jacobian approximation.

alpha [float, optional] Initial guess for the Jacobian is $(-1/\text{alpha})$.

reduction_method [str or tuple, optional] Method used in ensuring that the rank of the Broyden matrix stays low. Can either be a string giving the name of the method, or a tuple of the form `(method, param1, param2, ...)` that gives the name of the method and values for additional parameters.

Methods available:

- **restart** Drop all matrix columns. Has no extra parameters.
- **simple** Drop oldest matrix column. Has no extra parameters.
- **svd** Keep only the most significant SVD components.

Extra parameters:

- **to_retain**

Number of SVD components to retain when rank reduction is done. Default is `max_rank - 2`.

max_rank [int, optional] Maximum rank for the Broyden matrix. Default is infinity (i.e., no rank reduction).

`root(method='anderson')`

`scipy.optimize.root` (*fun*, *x0*, *args=()*, *method='anderson'*, *tol=None*, *callback=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.root`

Options

- nit** [int, optional] Number of iterations to make. If omitted (default), make as many as required to meet tolerances.
- disp** [bool, optional] Print status to stdout on every iteration.
- maxiter** [int, optional] Maximum number of iterations to make. If more are needed to meet convergence, *NoConvergence* is raised.
- ftol** [float, optional] Relative tolerance for the residual. If omitted, not used.
- fatol** [float, optional] Absolute tolerance (in max-norm) for the residual. If omitted, default is $6e-6$.
- xtol** [float, optional] Relative minimum step size. If omitted, not used.
- xatol** [float, optional] Absolute minimum step size, as determined from the Jacobian approximation. If the step size is smaller than this, optimization is terminated as successful. If omitted, not used.
- tol_norm** [function(vector) -> scalar, optional] Norm to use in convergence check. Default is the maximum norm.
- line_search** [{None, 'armijo' (default), 'wolfe'}, optional] Which type of a line search to use to determine the step size in the direction given by the Jacobian approximation. Defaults to 'armijo'.
- jac_options** [dict, optional] Options for the respective Jacobian approximation.
 - alpha** [float, optional] Initial guess for the Jacobian is $(-1/\alpha)$.
 - M** [float, optional] Number of previous vectors to retain. Defaults to 5.
 - w0** [float, optional] Regularization parameter for numerical stability. Compared to unity, good values of the order of 0.01.

root(method='linearmixing')

`scipy.optimize.root` (*fun*, *x0*, *args=()*, *method='linearmixing'*, *tol=None*, *callback=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.root`

Options

nit	[int, optional] Number of iterations to make. If omitted (default), make as many as required to meet tolerances.
disp	[bool, optional] Print status to stdout on every iteration.
maxiter	[int, optional] Maximum number of iterations to make. If more are needed to meet convergence, <i>NoConvergence</i> is raised.
ftol	[float, optional] Relative tolerance for the residual. If omitted, not used.
fatol	[float, optional] Absolute tolerance (in max-norm) for the residual. If omitted, default is 6e-6.
xtol	[float, optional] Relative minimum step size. If omitted, not used.
xatol	[float, optional] Absolute minimum step size, as determined from the Jacobian approximation. If the step size is smaller than this, optimization is terminated as successful. If omitted, not used.
tol_norm	[function(vector) -> scalar, optional] Norm to use in convergence check. Default is the maximum norm.
line_search	[{None, 'armijo' (default), 'wolfe'}, optional] Which type of a line search to use to determine the step size in the direction given by the Jacobian approximation. Defaults to 'armijo'.
jac_options	[dict, optional] Options for the respective Jacobian approximation.
alpha	[float, optional] initial guess for the jacobian is (-1/alpha).

root(method='diagbroyden')

`scipy.optimize.root` (*fun*, *x0*, *args=()*, *method='diagbroyden'*, *tol=None*, *callback=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see `scipy.optimize.root`

Options

nit	[int, optional] Number of iterations to make. If omitted (default), make as many as required to meet tolerances.
disp	[bool, optional] Print status to stdout on every iteration.
maxiter	[int, optional] Maximum number of iterations to make. If more are needed to meet convergence, <i>NoConvergence</i> is raised.
ftol	[float, optional] Relative tolerance for the residual. If omitted, not used.
fatol	[float, optional] Absolute tolerance (in max-norm) for the residual. If omitted, default is 6e-6.
xtol	[float, optional] Relative minimum step size. If omitted, not used.
xatol	[float, optional] Absolute minimum step size, as determined from the Jacobian approximation. If the step size is smaller than this, optimization is terminated as successful. If omitted, not used.
tol_norm	[function(vector) -> scalar, optional] Norm to use in convergence check. Default is the maximum norm.

line_search

[{None, 'armijo' (default), 'wolfe'}, optional] Which type of a line search to use to determine the step size in the direction given by the Jacobian approximation. Defaults to 'armijo'.

jac_options

[dict, optional] Options for the respective Jacobian approximation.

alpha [float, optional] initial guess for the jacobian is (-1/alpha).

root(method='excitingmixing')

`scipy.optimize.root` (*fun*, *x0*, *args=()*, *method='excitingmixing'*, *tol=None*, *callback=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see [scipy.optimize.root](#)

Options

nit [int, optional] Number of iterations to make. If omitted (default), make as many as required to meet tolerances.

disp [bool, optional] Print status to stdout on every iteration.

maxiter [int, optional] Maximum number of iterations to make. If more are needed to meet convergence, *NoConvergence* is raised.

ftol [float, optional] Relative tolerance for the residual. If omitted, not used.

fatol [float, optional] Absolute tolerance (in max-norm) for the residual. If omitted, default is 6e-6.

xtol [float, optional] Relative minimum step size. If omitted, not used.

xatol [float, optional] Absolute minimum step size, as determined from the Jacobian approximation. If the step size is smaller than this, optimization is terminated as successful. If omitted, not used.

tol_norm [function(vector) -> scalar, optional] Norm to use in convergence check. Default is the maximum norm.

line_search

[{None, 'armijo' (default), 'wolfe'}, optional] Which type of a line search to use to determine the step size in the direction given by the Jacobian approximation. Defaults to 'armijo'.

jac_options

[dict, optional] Options for the respective Jacobian approximation.

alpha [float, optional] Initial Jacobian approximation is (-1/alpha).

alphamax [float, optional] The entries of the diagonal Jacobian are kept in the range [alpha, alphamax].

root(method='krylov')

`scipy.optimize.root` (*fun*, *x0*, *args=()*, *method='krylov'*, *tol=None*, *callback=None*, *options={}*)

See also:

For documentation for the rest of the parameters, see [scipy.optimize.root](#)

Options

nit [int, optional] Number of iterations to make. If omitted (default), make as many as required to meet tolerances.

disp [bool, optional] Print status to stdout on every iteration.

maxiter [int, optional] Maximum number of iterations to make. If more are needed to meet convergence, *NoConvergence* is raised.

ftol [float, optional] Relative tolerance for the residual. If omitted, not used.

fatol	[float, optional] Absolute tolerance (in max-norm) for the residual. If omitted, default is 6e-6.
xtol	[float, optional] Relative minimum step size. If omitted, not used.
xatol	[float, optional] Absolute minimum step size, as determined from the Jacobian approximation. If the step size is smaller than this, optimization is terminated as successful. If omitted, not used.
tol_norm	[function(vector) -> scalar, optional] Norm to use in convergence check. Default is the maximum norm.
line_search	[[None, 'armijo' (default), 'wolfe'], optional] Which type of a line search to use to determine the step size in the direction given by the Jacobian approximation. Defaults to 'armijo'.
jac_options	[dict, optional] Options for the respective Jacobian approximation.
rdiff	[float, optional] Relative step size to use in numerical differentiation.
method	[[{'lgmres', 'gmres', 'bigstab', 'cgs', 'minres'} or function] Krylov method to use to approximate the Jacobian. Can be a string, or a function implementing the same interface as the iterative solvers in <code>scipy.sparse.linalg</code> . The default is <code>scipy.sparse.linalg.lgmres</code> .
inner_M	[LinearOperator or InverseJacobian] Preconditioner for the inner Krylov iteration. Note that you can use also inverse Jacobians as (adaptive) preconditioners. For example,
	<pre>>>> jac = BroydenFirst() >>> kjac = KrylovJacobian(inner_M=jac.inverse).</pre>
	If the preconditioner has a method named 'update', it will be called as <code>update(x, f)</code> after each nonlinear step, with <code>x</code> giving the current point, and <code>f</code> the current function value.
inner_tol, inner_maxiter, ...	Parameters to pass on to the "inner" Krylov solver. See <code>scipy.sparse.linalg.gmres</code> for details.
outer_k	[int, optional] Size of the subspace kept across LGMRES nonlinear iterations. See <code>scipy.sparse.linalg.lgmres</code> for details.

root(method='df-sane')

```
scipy.optimize.root(fun, x0, args=(), method='df-sane', tol=None, callback=None, options={'func':
None, 'fiol': 1e-08, 'fatol': 1e-300, 'maxfev': 1000, 'fnorm': None, 'disp': False, 'M':
10, 'eta_strategy': None, 'sigma_eps': 1e-10, 'sigma_0': 1.0, 'line_search': 'cruz'})
```

Solve nonlinear equation with the DF-SANE method

See also:

For documentation for the rest of the parameters, see `scipy.optimize.root`

Options

ftol	[float, optional] Relative norm tolerance.
fatol	[float, optional] Absolute norm tolerance. Algorithm terminates when $ \text{func}(x) < \text{fatol} + \text{ftol} \text{func}(x_0) $.
fnorm	[callable, optional] Norm to use in the convergence check. If None, 2-norm is used.
maxfev	[int, optional] Maximum number of function evaluations.
disp	[bool, optional] Whether to print convergence process to stdout.
eta_strategy	[callable, optional] Choice of the <code>eta_k</code> parameter, which gives slack for growth of $ F ^{**2}$. Called as <code>eta_k = eta_strategy(k, x, F)</code> with <code>k</code> the iteration

number, x the current iterate and F the current residual. Should satisfy $\text{eta}_k > 0$ and $\text{sum}(\text{eta}, k=0..inf) < inf$. Default: $\|F\|**2 / (1 + k)**2$.

sigma_eps [float, optional] The spectral coefficient is constrained to $\text{sigma_eps} < \text{sigma} < 1/\text{sigma_eps}$. Default: 1e-10

sigma_0 [float, optional] Initial spectral coefficient. Default: 1.0

M [int, optional] Number of iterates to include in the nonmonotonic line search. Default: 10

line_search [{'cruz', 'cheng'}] Type of line search to employ. 'cruz' is the original one defined in [Martinez & Raydan. Math. Comp. 75, 1429 (2006)], 'cheng' is a modified search defined in [Cheng & Li. IMA J. Numer. Anal. 29, 814 (2009)]. Default: 'cruz'

References

[1], [2], [3]

6.19.7 Linear programming

<code>linprog(c[, A_ub, b_ub, A_eq, b_eq, bounds, ...])</code>	Linear programming: minimize a linear objective function subject to linear equality and inequality constraints.
--	---

scipy.optimize.linprog

`scipy.optimize.linprog(c, A_ub=None, b_ub=None, A_eq=None, b_eq=None, bounds=None, method='interior-point', callback=None, options=None, x0=None)`

Linear programming: minimize a linear objective function subject to linear equality and inequality constraints.

Linear programming solves problems of the following form:

$$\begin{aligned} \min_x \quad & c^T x \\ \text{such that} \quad & A_{ub}x \leq b_{ub}, \\ & A_{eq}x = b_{eq}, \\ & l \leq x \leq u, \end{aligned}$$

where x is a vector of decision variables; c , b_{ub} , b_{eq} , l , and u are vectors; and A_{ub} and A_{eq} are matrices.

Alternatively, that's:

minimize:

$c @ x$

such that:

$A_ub @ x \leq b_ub$
 $A_eq @ x == b_eq$
 $lb \leq x \leq ub$

Note that by default $lb = 0$ and $ub = None$ unless specified with `bounds`.

Parameters

c [1-D array] The coefficients of the linear objective function to be minimized.

A_ub	[2-D array, optional] The inequality constraint matrix. Each row of <code>A_ub</code> specifies the coefficients of a linear inequality constraint on <code>x</code> .																		
b_ub	[1-D array, optional] The inequality constraint vector. Each element represents an upper bound on the corresponding value of <code>A_ub @ x</code> .																		
A_eq	[2-D array, optional] The equality constraint matrix. Each row of <code>A_eq</code> specifies the coefficients of a linear equality constraint on <code>x</code> .																		
b_eq	[1-D array, optional] The equality constraint vector. Each element of <code>A_eq @ x</code> must equal the corresponding element of <code>b_eq</code> .																		
bounds	[sequence, optional] A sequence of <code>(min, max)</code> pairs for each element in <code>x</code> , defining the minimum and maximum values of that decision variable. Use <code>None</code> to indicate that there is no bound. By default, bounds are <code>(0, None)</code> (all decision variables are non-negative). If a single tuple <code>(min, max)</code> is provided, then <code>min</code> and <code>max</code> will serve as bounds for all decision variables.																		
method	[str, optional] The algorithm used to solve the standard form problem. <i>'highs-ds'</i> , <i>'highs-ipm'</i> , <i>'highs'</i> , <i>'interior-point'</i> (default), <i>'revised simplex'</i> , and <i>'simplex'</i> (legacy) are supported.																		
callback	[callable, optional] If a callback function is provided, it will be called at least once per iteration of the algorithm. The callback function must accept a single <code>scipy.optimize.OptimizeResult</code> consisting of the following fields: <table border="0" style="margin-left: 20px;"> <tr> <td>x</td> <td>[1-D array] The current solution vector.</td> </tr> <tr> <td>fun</td> <td>[float] The current value of the objective function <code>c @ x</code>.</td> </tr> <tr> <td>success</td> <td>[bool] <code>True</code> when the algorithm has completed successfully.</td> </tr> <tr> <td>slack</td> <td>[1-D array] The (nominally positive) values of the slack, <code>b_ub - A_ub @ x</code>.</td> </tr> <tr> <td>con</td> <td>[1-D array] The (nominally zero) residuals of the equality constraints, <code>b_eq - A_eq @ x</code>.</td> </tr> <tr> <td>phase</td> <td>[int] The phase of the algorithm being executed.</td> </tr> <tr> <td>status</td> <td>[int] An integer representing the status of the algorithm. 0 : Optimization proceeding nominally. 1 : Iteration limit reached. 2 : Problem appears to be infeasible. 3 : Problem appears to be unbounded. 4 : Numerical difficulties encountered.</td> </tr> <tr> <td>nit</td> <td>[int] The current iteration number.</td> </tr> <tr> <td>message</td> <td>[str] A string descriptor of the algorithm status.</td> </tr> </table>	x	[1-D array] The current solution vector.	fun	[float] The current value of the objective function <code>c @ x</code> .	success	[bool] <code>True</code> when the algorithm has completed successfully.	slack	[1-D array] The (nominally positive) values of the slack, <code>b_ub - A_ub @ x</code> .	con	[1-D array] The (nominally zero) residuals of the equality constraints, <code>b_eq - A_eq @ x</code> .	phase	[int] The phase of the algorithm being executed.	status	[int] An integer representing the status of the algorithm. 0 : Optimization proceeding nominally. 1 : Iteration limit reached. 2 : Problem appears to be infeasible. 3 : Problem appears to be unbounded. 4 : Numerical difficulties encountered.	nit	[int] The current iteration number.	message	[str] A string descriptor of the algorithm status.
x	[1-D array] The current solution vector.																		
fun	[float] The current value of the objective function <code>c @ x</code> .																		
success	[bool] <code>True</code> when the algorithm has completed successfully.																		
slack	[1-D array] The (nominally positive) values of the slack, <code>b_ub - A_ub @ x</code> .																		
con	[1-D array] The (nominally zero) residuals of the equality constraints, <code>b_eq - A_eq @ x</code> .																		
phase	[int] The phase of the algorithm being executed.																		
status	[int] An integer representing the status of the algorithm. 0 : Optimization proceeding nominally. 1 : Iteration limit reached. 2 : Problem appears to be infeasible. 3 : Problem appears to be unbounded. 4 : Numerical difficulties encountered.																		
nit	[int] The current iteration number.																		
message	[str] A string descriptor of the algorithm status.																		
options	<p>Callback functions are not currently supported by the HiGHS methods.</p> <p>[dict, optional] A dictionary of solver options. All methods accept the following options:</p> <table border="0" style="margin-left: 20px;"> <tr> <td>maxiter</td> <td>[int] Maximum number of iterations to perform. Default: see method-specific documentation.</td> </tr> <tr> <td>disp</td> <td>[bool] Set to <code>True</code> to print convergence messages. Default: <code>False</code>.</td> </tr> <tr> <td>presolve</td> <td>[bool] Set to <code>False</code> to disable automatic presolve. Default: <code>True</code>.</td> </tr> </table> <p>All methods except the HiGHS solvers also accept:</p> <table border="0" style="margin-left: 20px;"> <tr> <td>tol</td> <td>[float] A tolerance which determines when a residual is “close enough” to zero to be considered exactly zero.</td> </tr> <tr> <td>autoscale</td> <td>[bool] Set to <code>True</code> to automatically perform equilibration. Consider using this option if the numerical values in the constraints are separated by several orders of magnitude. Default: <code>False</code>.</td> </tr> <tr> <td>rr</td> <td>[bool] Set to <code>False</code> to disable automatic redundancy removal. Default: <code>True</code>.</td> </tr> </table> <p>rr_method</p> <p>[string] Method used to identify and remove redundant rows from the equality constraint matrix after presolve. For problems with dense input, the available methods for redundancy removal are:</p> <p>“SVD”: Repeatedly performs singular value decomposition on the matrix, detecting redundant rows based on nonzeros in the left singular</p>	maxiter	[int] Maximum number of iterations to perform. Default: see method-specific documentation.	disp	[bool] Set to <code>True</code> to print convergence messages. Default: <code>False</code> .	presolve	[bool] Set to <code>False</code> to disable automatic presolve. Default: <code>True</code> .	tol	[float] A tolerance which determines when a residual is “close enough” to zero to be considered exactly zero.	autoscale	[bool] Set to <code>True</code> to automatically perform equilibration. Consider using this option if the numerical values in the constraints are separated by several orders of magnitude. Default: <code>False</code> .	rr	[bool] Set to <code>False</code> to disable automatic redundancy removal. Default: <code>True</code> .						
maxiter	[int] Maximum number of iterations to perform. Default: see method-specific documentation.																		
disp	[bool] Set to <code>True</code> to print convergence messages. Default: <code>False</code> .																		
presolve	[bool] Set to <code>False</code> to disable automatic presolve. Default: <code>True</code> .																		
tol	[float] A tolerance which determines when a residual is “close enough” to zero to be considered exactly zero.																		
autoscale	[bool] Set to <code>True</code> to automatically perform equilibration. Consider using this option if the numerical values in the constraints are separated by several orders of magnitude. Default: <code>False</code> .																		
rr	[bool] Set to <code>False</code> to disable automatic redundancy removal. Default: <code>True</code> .																		

vectors that correspond with zero singular values. May be fast when the matrix is nearly full rank.

“pivot”: Uses the algorithm presented in [5] to identify redundant rows.

“ID”: Uses a randomized interpolative decomposition. Identifies columns of the matrix transpose not used in a full-rank interpolative decomposition of the matrix.

None: Uses “svd” if the matrix is nearly full rank, that is, the difference between the matrix rank and the number of rows is less than five. If not, uses “pivot”. The behavior of this default is subject to change without prior notice.

Default: None. For problems with sparse input, this option is ignored, and the pivot-based algorithm presented in [5] is used.

For method-specific options, see `show_options('linprog')`.

x0 [1-D array, optional] Guess values of the decision variables, which will be refined by the optimization algorithm. This argument is currently used only by the ‘revised simplex’ method, and can only be used if *x0* represents a basic feasible solution.

Returns

res [OptimizeResult] A `scipy.optimize.OptimizeResult` consisting of the fields:

x [1-D array] The values of the decision variables that minimizes the objective function while satisfying the constraints.

fun [float] The optimal value of the objective function $c @ x$.

slack [1-D array] The (nominally positive) values of the slack variables, $b_{ub} - A_{ub} @ x$.

con [1-D array] The (nominally zero) residuals of the equality constraints, $b_{eq} - A_{eq} @ x$.

success [bool] True when the algorithm succeeds in finding an optimal solution.

status [int] An integer representing the exit status of the algorithm.

0 : Optimization terminated successfully.
 1 : Iteration limit reached.
 2 : Problem appears to be infeasible.
 3 : Problem appears to be unbounded.
 4 : Numerical difficulties encountered.

nit [int] The total number of iterations performed in all phases.

message [str] A string descriptor of the exit status of the algorithm.

See also:

`show_options`

Additional options accepted by the solvers.

Notes

This section describes the available solvers that can be selected by the ‘method’ parameter.

highs-ds and *highs-ipm* are interfaces to the HiGHS simplex and interior-point method solvers [13], respectively. *highs* chooses between the two automatically. These are the fastest linear programming solvers in SciPy, especially for large, sparse problems; which of these two is faster is problem-dependent. *interior-point* is the default as it was the fastest and most robust method before the recent addition of the HiGHS solvers. *revised simplex* is more accurate than interior-point for the problems it solves. *simplex* is the legacy method and is included for backwards compatibility and educational purposes.

Method *highs-ds* is a wrapper of the C++ high performance dual revised simplex implementation (HSOL) [13], [14]. Method *highs-ipm* is a wrapper of a C++ implementation of an interior-point method [13]; it features a

crossover routine, so it is as accurate as a simplex solver. Method *highs* chooses between the two automatically. For new code involving *linprog*, we recommend explicitly choosing one of these three method values.

New in version 1.5.0.

Method *interior-point* uses the primal-dual path following algorithm as outlined in [4]. This algorithm supports sparse constraint matrices and is typically faster than the simplex methods, especially for large, sparse problems. Note, however, that the solution returned may be slightly less accurate than those of the simplex methods and will not, in general, correspond with a vertex of the polytope defined by the constraints.

New in version 1.0.0.

Method *revised simplex* uses the revised simplex method as described in [9], except that a factorization [11] of the basis matrix, rather than its inverse, is efficiently maintained and used to solve the linear systems at each iteration of the algorithm.

New in version 1.3.0.

Method *simplex* uses a traditional, full-tableau implementation of Dantzig's simplex algorithm [1], [2] (*not* the Nelder-Mead simplex). This algorithm is included for backwards compatibility and educational purposes.

New in version 0.15.0.

Before applying *interior-point*, *revised simplex*, or *simplex*, a presolve procedure based on [8] attempts to identify trivial infeasibilities, trivial unboundedness, and potential problem simplifications. Specifically, it checks for:

- rows of zeros in `A_eq` or `A_ub`, representing trivial constraints;
- columns of zeros in `A_eq` and `A_ub`, representing unconstrained variables;
- column singletons in `A_eq`, representing fixed variables; and
- column singletons in `A_ub`, representing simple bounds.

If presolve reveals that the problem is unbounded (e.g. an unconstrained and unbounded variable has negative cost) or infeasible (e.g., a row of zeros in `A_eq` corresponds with a nonzero in `b_eq`), the solver terminates with the appropriate status code. Note that presolve terminates as soon as any sign of unboundedness is detected; consequently, a problem may be reported as unbounded when in reality the problem is infeasible (but infeasibility has not been detected yet). Therefore, if it is important to know whether the problem is actually infeasible, solve the problem again with option `presolve=False`.

If neither infeasibility nor unboundedness are detected in a single pass of the presolve, bounds are tightened where possible and fixed variables are removed from the problem. Then, linearly dependent rows of the `A_eq` matrix are removed, (unless they represent an infeasibility) to avoid numerical difficulties in the primary solve routine. Note that rows that are nearly linearly dependent (within a prescribed tolerance) may also be removed, which can change the optimal solution in rare cases. If this is a concern, eliminate redundancy from your problem formulation and run with option `rr=False` or `presolve=False`.

Several potential improvements can be made here: additional presolve checks outlined in [8] should be implemented, the presolve routine should be run multiple times (until no further simplifications can be made), and more of the efficiency improvements from [5] should be implemented in the redundancy removal routines.

After presolve, the problem is transformed to standard form by converting the (tightened) simple bounds to upper bound constraints, introducing non-negative slack variables for inequality constraints, and expressing unbounded variables as the difference between two non-negative variables. Optionally, the problem is automatically scaled via equilibration [12]. The selected algorithm solves the standard form problem, and a postprocessing routine converts the result to a solution to the original problem.

References

[1], [2], [3], [4], [5], [6], [7], [8], [9], [10], [11], [12], [13], [14]

Examples

Consider the following problem:

$$\begin{aligned} \min_{x_0, x_1} \quad & -x_0 + 4x_1 \\ \text{such that} \quad & -3x_0 + x_1 \leq 6, \\ & -x_0 - 2x_1 \geq -4, \\ & x_1 \geq -3. \end{aligned}$$

The problem is not presented in the form accepted by `linprog`. This is easily remedied by converting the “greater than” inequality constraint to a “less than” inequality constraint by multiplying both sides by a factor of -1 . Note also that the last constraint is really the simple bound $-3 \leq x_1 \leq \infty$. Finally, since there are no bounds on x_0 , we must explicitly specify the bounds $-\infty \leq x_0 \leq \infty$, as the default is for variables to be non-negative. After collecting coefficients into arrays and tuples, the input for this problem is:

```
>>> c = [-1, 4]
>>> A = [[-3, 1], [1, 2]]
>>> b = [6, 4]
>>> x0_bounds = (None, None)
>>> x1_bounds = (-3, None)
>>> from scipy.optimize import linprog
>>> res = linprog(c, A_ub=A, b_ub=b, bounds=[x0_bounds, x1_bounds])
```

Note that the default method for `linprog` is ‘interior-point’, which is approximate by nature.

```
>>> print(res)
con: array([], dtype=float64)
fun: -21.99999984082494 # may vary
message: 'Optimization terminated successfully.'
nit: 6 # may vary
slack: array([3.89999997e+01, 8.46872439e-08] # may vary
status: 0
success: True
x: array([ 9.99999989, -2.99999999]) # may vary
```

If you need greater accuracy, try ‘revised simplex’.

```
>>> res = linprog(c, A_ub=A, b_ub=b, bounds=[x0_bounds, x1_bounds],
↳method='revised simplex')
>>> print(res)
con: array([], dtype=float64)
fun: -22.0 # may vary
message: 'Optimization terminated successfully.'
nit: 1 # may vary
slack: array([39., 0.]) # may vary
status: 0
success: True
x: array([10., -3.]) # may vary
```

The `linprog` function supports the following methods:

linprog(method='simplex')

```
scipy.optimize.linprog(c, A_ub=None, b_ub=None, A_eq=None, b_eq=None, bounds=None,
                      method='simplex', callback=None, options={'maxiter': 5000, 'disp': False, 'pre-
                      solve': True, 'tol': 1e-12, 'autoscale': False, 'rr': True, 'bland': False}, x0=None)
```

Linear programming: minimize a linear objective function subject to linear equality and inequality constraints using the tableau-based simplex method.

Linear programming solves problems of the following form:

$$\begin{aligned} \min_x \quad & c^T x \\ \text{such that} \quad & A_{ub}x \leq b_{ub}, \\ & A_{eq}x = b_{eq}, \\ & l \leq x \leq u, \end{aligned}$$

where x is a vector of decision variables; c , b_{ub} , b_{eq} , l , and u are vectors; and A_{ub} and A_{eq} are matrices.

Alternatively, that's:

minimize:

```
c @ x
```

such that:

```
A_ub @ x <= b_ub
A_eq @ x == b_eq
lb <= x <= ub
```

Note that by default `lb = 0` and `ub = None` unless specified with `bounds`.

Parameters

- c** [1-D array] The coefficients of the linear objective function to be minimized.
- A_ub** [2-D array, optional] The inequality constraint matrix. Each row of `A_ub` specifies the coefficients of a linear inequality constraint on x .
- b_ub** [1-D array, optional] The inequality constraint vector. Each element represents an upper bound on the corresponding value of `A_ub @ x`.
- A_eq** [2-D array, optional] The equality constraint matrix. Each row of `A_eq` specifies the coefficients of a linear equality constraint on x .
- b_eq** [1-D array, optional] The equality constraint vector. Each element of `A_eq @ x` must equal the corresponding element of `b_eq`.
- bounds** [sequence, optional] A sequence of (\min, \max) pairs for each element in x , defining the minimum and maximum values of that decision variable. Use `None` to indicate that there is no bound. By default, bounds are $(0, \text{None})$ (all decision variables are non-negative). If a single tuple (\min, \max) is provided, then `min` and `max` will serve as bounds for all decision variables.
- method** [str] This is the method-specific documentation for 'simplex'. *'highs'*, *'highs-ds'*, *'highs-ipm'*, *'interior-point'* (default), and *'revised simplex'* are also available.
- callback** [callable, optional] Callback function to be executed once per iteration.

Returns

- res** [OptimizeResult] A `scipy.optimize.OptimizeResult` consisting of the fields:
 - x** [1-D array] The values of the decision variables that minimizes the objective function while satisfying the constraints.
 - fun** [float] The optimal value of the objective function `c @ x`.

slack	[1-D array] The (nominally positive) values of the slack variables, $b_{ub} - A_{ub} @ x$.
con	[1-D array] The (nominally zero) residuals of the equality constraints, $b_{eq} - A_{eq} @ x$.
success	[bool] <code>True</code> when the algorithm succeeds in finding an optimal solution.
status	[int] An integer representing the exit status of the algorithm. 0 : Optimization terminated successfully. 1 : Iteration limit reached. 2 : Problem appears to be infeasible. 3 : Problem appears to be unbounded. 4 : Numerical difficulties encountered.
message	[str] A string descriptor of the exit status of the algorithm.
nit	[int] The total number of iterations performed in all phases.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.linprog`

Options

maxiter	[int (default: 5000)] The maximum number of iterations to perform in either phase.
disp	[bool (default: <code>False</code>)] Set to <code>True</code> if indicators of optimization status are to be printed to the console each iteration.
presolve	[bool (default: <code>True</code>)] Presolve attempts to identify trivial infeasibilities, identify trivial unboundedness, and simplify the problem before sending it to the main solver. It is generally recommended to keep the default setting <code>True</code> ; set to <code>False</code> if presolve is to be disabled.
tol	[float (default: <code>1e-12</code>)] The tolerance which determines when a solution is “close enough” to zero in Phase 1 to be considered a basic feasible solution or close enough to positive to serve as an optimal solution.
autoscale	[bool (default: <code>False</code>)] Set to <code>True</code> to automatically perform equilibration. Consider using this option if the numerical values in the constraints are separated by several orders of magnitude.
rr	[bool (default: <code>True</code>)] Set to <code>False</code> to disable automatic redundancy removal.
bland	[bool] If <code>True</code> , use Bland’s anti-cycling rule [3] to choose pivots to prevent cycling. If <code>False</code> , choose pivots which should lead to a converged solution more quickly. The latter method is subject to cycling (non-convergence) in rare instances.
unknown_options	[dict] Optional arguments not used by this particular solver. If <code>unknown_options</code> is non-empty a warning is issued listing all unused options.

References

[1], [2], [3]

linprog(method='interior-point')

```
scipy.optimize.linprog(c, A_ub=None, b_ub=None, A_eq=None, b_eq=None, bounds=None,
                       method='interior-point', callback=None, options={'maxiter': 1000, 'disp': False,
                               'presolve': True, 'tol': 1e-08, 'autoscale': False, 'rr': True, 'alpha0': 0.99995,
                               'beta': 0.1, 'sparse': False, 'lstsq': False, 'sym_pos': True, 'cholesky': True, 'pc':
                               True, 'ip': False, 'permc_spec': 'MMD_AT_PLUS_A'}, x0=None)
```

Linear programming: minimize a linear objective function subject to linear equality and inequality constraints using the interior-point method of [4].

Linear programming solves problems of the following form:

$$\begin{aligned} \min_x \quad & c^T x \\ \text{such that} \quad & A_{ub}x \leq b_{ub}, \\ & A_{eq}x = b_{eq}, \\ & l \leq x \leq u, \end{aligned}$$

where x is a vector of decision variables; c , b_{ub} , b_{eq} , l , and u are vectors; and A_{ub} and A_{eq} are matrices.

Alternatively, that's:

minimize:

```
c @ x
```

such that:

```
A_ub @ x <= b_ub
A_eq @ x == b_eq
lb <= x <= ub
```

Note that by default `lb = 0` and `ub = None` unless specified with bounds.

Parameters

- c** [1-D array] The coefficients of the linear objective function to be minimized.
- A_ub** [2-D array, optional] The inequality constraint matrix. Each row of `A_ub` specifies the coefficients of a linear inequality constraint on x .
- b_ub** [1-D array, optional] The inequality constraint vector. Each element represents an upper bound on the corresponding value of `A_ub @ x`.
- A_eq** [2-D array, optional] The equality constraint matrix. Each row of `A_eq` specifies the coefficients of a linear equality constraint on x .
- b_eq** [1-D array, optional] The equality constraint vector. Each element of `A_eq @ x` must equal the corresponding element of `b_eq`.
- bounds** [sequence, optional] A sequence of `(min, max)` pairs for each element in x , defining the minimum and maximum values of that decision variable. Use `None` to indicate that there is no bound. By default, bounds are `(0, None)` (all decision variables are non-negative). If a single tuple `(min, max)` is provided, then `min` and `max` will serve as bounds for all decision variables.
- method** [str] This is the method-specific documentation for 'interior-point'. *'highs'*, *'highs-ds'*, *'highs-ipm'*, *'revised simplex'*, and *'simplex'* (legacy) are also available.
- callback** [callable, optional] Callback function to be executed once per iteration.

Returns

- res** [OptimizeResult] A `scipy.optimize.OptimizeResult` consisting of the fields:
 - x** [1-D array] The values of the decision variables that minimizes the objective function while satisfying the constraints.
 - fun** [float] The optimal value of the objective function `c @ x`.
 - slack** [1-D array] The (nominally positive) values of the slack variables, `b_ub - A_ub @ x`.
 - con** [1-D array] The (nominally zero) residuals of the equality constraints, `b_eq - A_eq @ x`.
 - success** [bool] `True` when the algorithm succeeds in finding an optimal solution.
 - status** [int] An integer representing the exit status of the algorithm.
 - 0 : Optimization terminated successfully.
 - 1 : Iteration limit reached.

2 : Problem appears to be infeasible.
 3 : Problem appears to be unbounded.
 4 : Numerical difficulties encountered.
message [str] A string descriptor of the exit status of the algorithm.
nit [int] The total number of iterations performed in all phases.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.linprog`

Options

maxiter [int (default: 1000)] The maximum number of iterations of the algorithm.

disp [bool (default: False)] Set to `True` if indicators of optimization status are to be printed to the console each iteration.

presolve [bool (default: True)] Presolve attempts to identify trivial infeasibilities, identify trivial unboundedness, and simplify the problem before sending it to the main solver. It is generally recommended to keep the default setting `True`; set to `False` if presolve is to be disabled.

tol [float (default: 1e-8)] Termination tolerance to be used for all termination criteria; see [4] Section 4.5.

autoscale [bool (default: False)] Set to `True` to automatically perform equilibration. Consider using this option if the numerical values in the constraints are separated by several orders of magnitude.

rr [bool (default: True)] Set to `False` to disable automatic redundancy removal.

alpha0 [float (default: 0.99995)] The maximal step size for Mehrota's predictor-corrector search direction; see β_3 of [4] Table 8.1.

beta [float (default: 0.1)] The desired reduction of the path parameter μ (see [6]) when Mehrota's predictor-corrector is not in use (uncommon).

sparse [bool (default: False)] Set to `True` if the problem is to be treated as sparse after presolve. If either `A_eq` or `A_ub` is a sparse matrix, this option will automatically be set `True`, and the problem will be treated as sparse even during presolve. If your constraint matrices contain mostly zeros and the problem is not very small (less than about 100 constraints or variables), consider setting `True` or providing `A_eq` and `A_ub` as sparse matrices.

lstsq [bool (default: False)] Set to `True` if the problem is expected to be very poorly conditioned. This should always be left `False` unless severe numerical difficulties are encountered. Leave this at the default unless you receive a warning message suggesting otherwise.

sym_pos [bool (default: True)] Leave `True` if the problem is expected to yield a well conditioned symmetric positive definite normal equation matrix (almost always). Leave this at the default unless you receive a warning message suggesting otherwise.

cholesky [bool (default: True)] Set to `True` if the normal equations are to be solved by explicit Cholesky decomposition followed by explicit forward/backward substitution. This is typically faster for problems that are numerically well-behaved.

pc [bool (default: True)] Leave `True` if the predictor-corrector method of Mehrota is to be used. This is almost always (if not always) beneficial.

ip [bool (default: False)] Set to `True` if the improved initial point suggestion due to [4] Section 4.3 is desired. Whether this is beneficial or not depends on the problem.

permc_spec [str (default: 'MMD_AT_PLUS_A')] (Has effect only with `sparse = True`, `lstsq = False`, `sym_pos = True`, and no SuiteSparse.) A matrix is factorized in each iteration of the algorithm. This option specifies how to permute the columns of the matrix for sparsity preservation. Acceptable values are:

- `NATURAL`: natural ordering.
- `MMD_ATA`: minimum degree ordering on the structure of $A^T A$.
- `MMD_AT_PLUS_A`: minimum degree ordering on the structure of $A^T + A$.
- `COLAMD`: approximate minimum degree column ordering.

This option can impact the convergence of the interior point algorithm; test different values to determine which performs best for your problem. For more information, refer to `scipy.sparse.linalg.splu`.

unknown_options

[dict] Optional arguments not used by this particular solver. If *unknown_options* is non-empty a warning is issued listing all unused options.

Notes

This method implements the algorithm outlined in [4] with ideas from [8] and a structure inspired by the simpler methods of [6].

The primal-dual path following method begins with initial ‘guesses’ of the primal and dual variables of the standard form problem and iteratively attempts to solve the (nonlinear) Karush-Kuhn-Tucker conditions for the problem with a gradually reduced logarithmic barrier term added to the objective. This particular implementation uses a homogeneous self-dual formulation, which provides certificates of infeasibility or unboundedness where applicable.

The default initial point for the primal and dual variables is that defined in [4] Section 4.4 Equation 8.22. Optionally (by setting initial point option `ip=True`), an alternate (potentially improved) starting point can be calculated according to the additional recommendations of [4] Section 4.4.

A search direction is calculated using the predictor-corrector method (single correction) proposed by Mehrota and detailed in [4] Section 4.1. (A potential improvement would be to implement the method of multiple corrections described in [4] Section 4.2.) In practice, this is accomplished by solving the normal equations, [4] Section 5.1 Equations 8.31 and 8.32, derived from the Newton equations [4] Section 5 Equations 8.25 (compare to [4] Section 4 Equations 8.6-8.8). The advantage of solving the normal equations rather than 8.25 directly is that the matrices involved are symmetric positive definite, so Cholesky decomposition can be used rather than the more expensive LU factorization.

With default options, the solver used to perform the factorization depends on third-party software availability and the conditioning of the problem.

For dense problems, solvers are tried in the following order:

1. `scipy.linalg.cho_factor`
2. `scipy.linalg.solve` with option `sym_pos=True`
3. `scipy.linalg.solve` with option `sym_pos=False`
4. `scipy.linalg.lstsq`

For sparse problems:

1. `sksparse.cholmod.cholesky` (if `scikit-sparse` and `SuiteSparse` are installed)
2. `scipy.sparse.linalg.factorized` (if `scikit-umfpack` and `SuiteSparse` are installed)
3. `scipy.sparse.linalg.splu` (which uses SuperLU distributed with SciPy)
4. `scipy.sparse.linalg.lsqr`

If the solver fails for any reason, successively more robust (but slower) solvers are attempted in the order indicated. Attempting, failing, and re-starting factorization can be time consuming, so if the problem is numerically challenging, options can be set to bypass solvers that are failing. Setting `cholesky=False` skips to solver 2, `sym_pos=False` skips to solver 3, and `lstsq=True` skips to solver 4 for both sparse and dense problems.

Potential improvements for combatting issues associated with dense columns in otherwise sparse problems are outlined in [4] Section 5.3 and [10] Section 4.1-4.2; the latter also discusses the alleviation of accuracy issues associated with the substitution approach to free variables.

After calculating the search direction, the maximum possible step size that does not activate the non-negativity constraints is calculated, and the smaller of this step size and unity is applied (as in [4] Section 4.1.) [4] Section 4.3 suggests improvements for choosing the step size.

The new point is tested according to the termination conditions of [4] Section 4.5. The same tolerance, which can be set using the `tol` option, is used for all checks. (A potential improvement would be to expose the different tolerances to be set independently.) If optimality, unboundedness, or infeasibility is detected, the solve procedure terminates; otherwise it repeats.

Whereas the top level `linprog` module expects a problem of form:

Minimize:

```
c @ x
```

Subject to:

```
A_ub @ x <= b_ub
A_eq @ x == b_eq
lb <= x <= ub
```

where `lb = 0` and `ub = None` unless set in `bounds`. The problem is automatically converted to the form:

Minimize:

```
c @ x
```

Subject to:

```
A @ x == b
x >= 0
```

for solution. That is, the original problem contains equality, upper-bound and variable constraints whereas the method specific solver requires equality constraints and variable non-negativity. `linprog` converts the original problem to standard form by converting the simple bounds to upper bound constraints, introducing non-negative slack variables for inequality constraints, and expressing unbounded variables as the difference between two non-negative variables. The problem is converted back to the original form before results are reported.

References

[4], [6], [8], [9], [10]

`linprog(method='revised simplex')`

```
scipy.optimize.linprog(c, A_ub=None, b_ub=None, A_eq=None, b_eq=None, bounds=None,
                       method='revised_simplex', callback=None, options={'maxiter': 5000, 'disp':
                       False, 'presolve': True, 'tol': 1e-12, 'autoscale': False, 'rr': True, 'maxupdate':
                       10, 'mast': False, 'pivot': 'mrc'}, x0=None)
```

Linear programming: minimize a linear objective function subject to linear equality and inequality constraints using the revised simplex method.

Linear programming solves problems of the following form:

$$\begin{aligned} & \min_x c^T x \\ & \text{such that } A_{ub}x \leq b_{ub}, \\ & \quad A_{eq}x = b_{eq}, \\ & \quad l \leq x \leq u, \end{aligned}$$

where x is a vector of decision variables; c , b_{ub} , b_{eq} , l , and u are vectors; and A_{ub} and A_{eq} are matrices.

Alternatively, that's:

minimize:

```
c @ x
```

such that:

```
A_ub @ x <= b_ub
A_eq @ x == b_eq
lb <= x <= ub
```

Note that by default `lb = 0` and `ub = None` unless specified with bounds.

Parameters

c	[1-D array] The coefficients of the linear objective function to be minimized.
A_ub	[2-D array, optional] The inequality constraint matrix. Each row of <code>A_ub</code> specifies the coefficients of a linear inequality constraint on <code>x</code> .
b_ub	[1-D array, optional] The inequality constraint vector. Each element represents an upper bound on the corresponding value of <code>A_ub @ x</code> .
A_eq	[2-D array, optional] The equality constraint matrix. Each row of <code>A_eq</code> specifies the coefficients of a linear equality constraint on <code>x</code> .
b_eq	[1-D array, optional] The equality constraint vector. Each element of <code>A_eq @ x</code> must equal the corresponding element of <code>b_eq</code> .
bounds	[sequence, optional] A sequence of (<code>min</code> , <code>max</code>) pairs for each element in <code>x</code> , defining the minimum and maximum values of that decision variable. Use <code>None</code> to indicate that there is no bound. By default, bounds are (<code>0</code> , <code>None</code>) (all decision variables are non-negative). If a single tuple (<code>min</code> , <code>max</code>) is provided, then <code>min</code> and <code>max</code> will serve as bounds for all decision variables.
method	[str] This is the method-specific documentation for 'revised simplex'. <i>'highs'</i> , <i>'highs-ds'</i> , <i>'highs-ipm'</i> , <i>'interior-point'</i> (default), and <i>'simplex'</i> (legacy) are also available.
callback	[callable, optional] Callback function to be executed once per iteration.
x0	[1-D array, optional] Guess values of the decision variables, which will be refined by the optimization algorithm. This argument is currently used only by the 'revised simplex' method, and can only be used if <code>x0</code> represents a basic feasible solution.

Returns

res	[OptimizeResult] A <code>scipy.optimize.OptimizeResult</code> consisting of the fields:
x	[1-D array] The values of the decision variables that minimizes the objective function while satisfying the constraints.
fun	[float] The optimal value of the objective function <code>c @ x</code> .
slack	[1-D array] The (nominally positive) values of the slack variables, <code>b_ub - A_ub @ x</code> .
con	[1-D array] The (nominally zero) residuals of the equality constraints, <code>b_eq - A_eq @ x</code> .
success	[bool] <code>True</code> when the algorithm succeeds in finding an optimal solution.

status	[int] An integer representing the exit status of the algorithm. 0 : Optimization terminated successfully. 1 : Iteration limit reached. 2 : Problem appears to be infeasible. 3 : Problem appears to be unbounded. 4 : Numerical difficulties encountered. 5 : Problem has no constraints; turn presolve on. 6 : Invalid guess provided.
message	[str] A string descriptor of the exit status of the algorithm.
nit	[int] The total number of iterations performed in all phases.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.linprog`

Options

maxiter	[int (default: 5000)] The maximum number of iterations to perform in either phase.
disp	[bool (default: False)] Set to <code>True</code> if indicators of optimization status are to be printed to the console each iteration.
presolve	[bool (default: True)] Presolve attempts to identify trivial infeasibilities, identify trivial unboundedness, and simplify the problem before sending it to the main solver. It is generally recommended to keep the default setting <code>True</code> ; set to <code>False</code> if presolve is to be disabled.
tol	[float (default: 1e-12)] The tolerance which determines when a solution is “close enough” to zero in Phase 1 to be considered a basic feasible solution or close enough to positive to serve as an optimal solution.
autoscale	[bool (default: False)] Set to <code>True</code> to automatically perform equilibration. Consider using this option if the numerical values in the constraints are separated by several orders of magnitude.
rr	[bool (default: True)] Set to <code>False</code> to disable automatic redundancy removal.
maxupdate	[int (default: 10)] The maximum number of updates performed on the LU factorization. After this many updates is reached, the basis matrix is factorized from scratch.
mast	[bool (default: False)] Minimize Amortized Solve Time. If enabled, the average time to solve a linear system using the basis factorization is measured. Typically, the average solve time will decrease with each successive solve after initial factorization, as factorization takes much more time than the solve operation (and updates). Eventually, however, the updated factorization becomes sufficiently complex that the average solve time begins to increase. When this is detected, the basis is refactorized from scratch. Enable this option to maximize speed at the risk of nondeterministic behavior. Ignored if <code>maxupdate</code> is 0.
pivot	[“mrc” or “bland” (default: “mrc”)] Pivot rule: Minimum Reduced Cost (“mrc”) or Bland’s rule (“bland”). Choose Bland’s rule if iteration limit is reached and cycling is suspected.
unknown_options	[dict] Optional arguments not used by this particular solver. If <code>unknown_options</code> is non-empty a warning is issued listing all unused options.

Notes

Method *revised simplex* uses the revised simplex method as described in [9], except that a factorization [11] of the basis matrix, rather than its inverse, is efficiently maintained and used to solve the linear systems at each iteration of the algorithm.

References

[9], [11]

linprog(method='highs-ipm')

```
scipy.optimize.linprog(c, A_ub=None, b_ub=None, A_eq=None, b_eq=None, bounds=None,
                      method='highs-ipm', callback=None, options={'maxiter': None, 'disp': False,
                      'presolve': True, 'time_limit': None, 'dual_feasibility_tolerance': None,
                      'primal_feasibility_tolerance': None, 'ipm_optimality_tolerance': None},
                      x0=None)
```

Linear programming: minimize a linear objective function subject to linear equality and inequality constraints using the HiGHS interior point solver.

Linear programming solves problems of the following form:

$$\begin{aligned} \min_x \quad & c^T x \\ \text{such that} \quad & A_{ub}x \leq b_{ub}, \\ & A_{eq}x = b_{eq}, \\ & l \leq x \leq u, \end{aligned}$$

where x is a vector of decision variables; c , b_{ub} , b_{eq} , l , and u are vectors; and A_{ub} and A_{eq} are matrices.

Alternatively, that's:

minimize:

```
c @ x
```

such that:

```
A_ub @ x <= b_ub
A_eq @ x == b_eq
lb <= x <= ub
```

Note that by default $lb = 0$ and $ub = None$ unless specified with `bounds`.

Parameters

- c** [1-D array] The coefficients of the linear objective function to be minimized.
- A_ub** [2-D array, optional] The inequality constraint matrix. Each row of `A_ub` specifies the coefficients of a linear inequality constraint on x .
- b_ub** [1-D array, optional] The inequality constraint vector. Each element represents an upper bound on the corresponding value of `A_ub @ x`.
- A_eq** [2-D array, optional] The equality constraint matrix. Each row of `A_eq` specifies the coefficients of a linear equality constraint on x .
- b_eq** [1-D array, optional] The equality constraint vector. Each element of `A_eq @ x` must equal the corresponding element of `b_eq`.

- bounds** [sequence, optional] A sequence of (*min*, *max*) pairs for each element in *x*, defining the minimum and maximum values of that decision variable. Use *None* to indicate that there is no bound. By default, bounds are (*0*, *None*) (all decision variables are non-negative). If a single tuple (*min*, *max*) is provided, then *min* and *max* will serve as bounds for all decision variables.
- method** [str] This is the method-specific documentation for 'highs-ipm'. *'highs-ipm'*, *'highs-ds'*, *'interior-point'* (default), *'revised simplex'*, and *'simplex'* (legacy) are also available.

Returns

- res** [OptimizeResult] A *scipy.optimize.OptimizeResult* consisting of the fields:
- x** [1D array] The values of the decision variables that minimizes the objective function while satisfying the constraints.
- fun** [float] The optimal value of the objective function $c @ x$.
- slack** [1D array] The (nominally positive) values of the slack, $b_{ub} - A_{ub} @ x$.
- con** [1D array] The (nominally zero) residuals of the equality constraints, $b_{eq} - A_{eq} @ x$.
- success** [bool] *True* when the algorithm succeeds in finding an optimal solution.
- status** [int] An integer representing the exit status of the algorithm.
 0 : Optimization terminated successfully.
 1 : Iteration or time limit reached.
 2 : Problem appears to be infeasible.
 3 : Problem appears to be unbounded.
 4 : The HiGHS solver ran into a problem.
- message** [str] A string descriptor of the exit status of the algorithm.
- nit** [int] The total number of iterations performed. For the HiGHS interior-point method, this does not include crossover iterations.
- crossover_nit** [int] The number of primal/dual pushes performed during the crossover routine for the HiGHS interior-point method.

See also:

For documentation for the rest of the parameters, see *scipy.optimize.linprog*

Options

- maxiter** [int] The maximum number of iterations to perform in either phase. For *'highs-ipm'*, this does not include the number of crossover iterations. Default is the largest possible value for an *int* on the platform.
- disp** [bool (default: *False*)] Set to *True* if indicators of optimization status are to be printed to the console during optimization.
- presolve** [bool (default: *True*)] Presolve attempts to identify trivial infeasibilities, identify trivial unboundedness, and simplify the problem before sending it to the main solver. It is generally recommended to keep the default setting *True*; set to *False* if presolve is to be disabled.
- time_limit** [float] The maximum time in seconds allotted to solve the problem; default is the largest possible value for a *double* on the platform.
- dual_feasibility_tolerance** [double (default: $1e-07$)] The minimum of this and *primal_feasibility_tolerance* is used for the feasibility tolerance of *'highs-ipm'*.
- primal_feasibility_tolerance** [double (default: $1e-07$)] The minimum of this and *dual_feasibility_tolerance* is used for the feasibility tolerance of *'highs-ipm'*.
- ipm_optimality_tolerance** [double (default: $1e-08$)] Optimality tolerance for *'highs-ipm'*. Minimum allowable value is $1e-12$.

unknown_options

[dict] Optional arguments not used by this particular solver. If `unknown_options` is non-empty, a warning is issued listing all unused options.

Notes

Method `'highs-ipm'` is a wrapper of a C++ implementation of an interior-point method [13]; it features a crossover routine, so it is as accurate as a simplex solver. Method `'highs-ds'` is a wrapper of the C++ high performance dual revised simplex implementation (HSOL) [13], [14]. Method `'highs'` chooses between the two automatically. For new code involving `linprog`, we recommend explicitly choosing one of these three method values instead of `'interior-point'` (default), `'revised simplex'`, and `'simplex'` (legacy).

References

[13], [14]

linprog(method='highs-ds')

```
scipy.optimize.linprog(c, A_ub=None, b_ub=None, A_eq=None, b_eq=None, bounds=None,
                       method='highs-ds', callback=None, options={'maxiter': None, 'disp': False,
                       'presolve': True, 'time_limit': None, 'dual_feasibility_tolerance': None, 'primal_feasibility_tolerance': None, 'simplex_dual_edge_weight_strategy': None},
                       x0=None)
```

Linear programming: minimize a linear objective function subject to linear equality and inequality constraints using the HiGHS dual simplex solver.

Linear programming solves problems of the following form:

$$\begin{aligned} \min_x \quad & c^T x \\ \text{such that} \quad & A_{ub}x \leq b_{ub}, \\ & A_{eq}x = b_{eq}, \\ & l \leq x \leq u, \end{aligned}$$

where x is a vector of decision variables; c , b_{ub} , b_{eq} , l , and u are vectors; and A_{ub} and A_{eq} are matrices.

Alternatively, that's:

minimize:

```
c @ x
```

such that:

```
A_ub @ x <= b_ub
A_eq @ x == b_eq
lb <= x <= ub
```

Note that by default `lb = 0` and `ub = None` unless specified with `bounds`.

Parameters

c [1-D array] The coefficients of the linear objective function to be minimized.
A_ub [2-D array, optional] The inequality constraint matrix. Each row of `A_ub` specifies the coefficients of a linear inequality constraint on x .

b_ub	[1-D array, optional] The inequality constraint vector. Each element represents an upper bound on the corresponding value of $A_ub @ x$.
A_eq	[2-D array, optional] The equality constraint matrix. Each row of A_eq specifies the coefficients of a linear equality constraint on x .
b_eq	[1-D array, optional] The equality constraint vector. Each element of $A_eq @ x$ must equal the corresponding element of b_eq .
bounds	[sequence, optional] A sequence of (min, max) pairs for each element in x , defining the minimum and maximum values of that decision variable. Use <code>None</code> to indicate that there is no bound. By default, bounds are $(0, None)$ (all decision variables are non-negative). If a single tuple (min, max) is provided, then <code>min</code> and <code>max</code> will serve as bounds for all decision variables.
method	[str] This is the method-specific documentation for 'highs-ds'. <i>'highs'</i> , <i>'highs-ipm'</i> , <i>'interior-point'</i> (default), <i>'revised simplex'</i> , and <i>'simplex'</i> (legacy) are also available.

Returns

res	[OptimizeResult] A <code>scipy.optimize.OptimizeResult</code> consisting of the fields:
x	[1D array] The values of the decision variables that minimizes the objective function while satisfying the constraints.
fun	[float] The optimal value of the objective function $c @ x$.
slack	[1D array] The (nominally positive) values of the slack, $b_ub - A_ub @ x$.
con	[1D array] The (nominally zero) residuals of the equality constraints, $b_eq - A_eq @ x$.
success	[bool] <code>True</code> when the algorithm succeeds in finding an optimal solution.
status	[int] An integer representing the exit status of the algorithm. 0 : Optimization terminated successfully. 1 : Iteration or time limit reached. 2 : Problem appears to be infeasible. 3 : Problem appears to be unbounded. 4 : The HiGHS solver ran into a problem.
message	[str] A string descriptor of the exit status of the algorithm.
nit	[int] The total number of iterations performed. This includes iterations in all phases.
crossover_nit	[int] This is always 0 for the HiGHS simplex method. For the HiGHS interior-point method, this is the number of primal/dual pushes performed during the crossover routine.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.linprog`

Options

maxiter	[int] The maximum number of iterations to perform in either phase. Default is the largest possible value for an <code>int</code> on the platform.
disp	[bool (default: <code>False</code>)] Set to <code>True</code> if indicators of optimization status are to be printed to the console during optimization.
presolve	[bool (default: <code>True</code>)] Presolve attempts to identify trivial infeasibilities, identify trivial unboundedness, and simplify the problem before sending it to the main solver. It is generally recommended to keep the default setting <code>True</code> ; set to <code>False</code> if presolve is to be disabled.
time_limit	[float] The maximum time in seconds allotted to solve the problem; default is the largest possible value for a <code>double</code> on the platform.
dual_feasibility_tolerance	[double (default: <code>1e-07</code>)] Dual feasibility tolerance for <i>'highs-ds'</i> .

primal_feasibility_tolerance

[double (default: 1e-07)] Primal feasibility tolerance for *'highs-ds'*.

simplex_dual_edge_weight_strategy

[str (default: None)] Strategy for simplex dual edge weights. The default, None, automatically selects one of the following.

'dantzig' uses Dantzig's original strategy of choosing the most negative reduced cost.

'devex' uses the strategy described in [15].

steepest uses the exact steepest edge strategy as described in [16].

'steepest-devex' begins with the exact steepest edge strategy until the computation is too costly or inexact and then switches to the devex method.

Currently, None always selects 'steepest-devex', but this may change as new options become available.

unknown_options

[dict] Optional arguments not used by this particular solver. If unknown_options is non-empty, a warning is issued listing all unused options.

Notes

Method *'highs-ds'* is a wrapper of the C++ high performance dual revised simplex implementation (HSOL) [13], [14]. Method *'highs-ipm'* is a wrapper of a C++ implementation of an interior-point method [13]; it features a crossover routine, so it is as accurate as a simplex solver. Method *'highs'* chooses between the two automatically. For new code involving *linprog*, we recommend explicitly choosing one of these three method values instead of *'interior-point'* (default), *'revised simplex'*, and *'simplex'* (legacy).

References

[13], [14], [15], [16]

linprog(method='highs')

```
scipy.optimize.linprog(c, A_ub=None, b_ub=None, A_eq=None, b_eq=None, bounds=None,
                       method='highs', callback=None, options={'maxiter': None, 'disp': False, 'pre-
                       solve': True, 'time_limit': None, 'dual_feasibility_tolerance': None, 'pri-
                       mal_feasibility_tolerance': None, 'ipm_optimality_tolerance': None, 'sim-
                       plex_dual_edge_weight_strategy': None}, x0=None)
```

Linear programming: minimize a linear objective function subject to linear equality and inequality constraints using one of the HiGHS solvers.

Linear programming solves problems of the following form:

$$\begin{aligned} \min_x \quad & c^T x \\ \text{such that} \quad & A_{ub}x \leq b_{ub}, \\ & A_{eq}x = b_{eq}, \\ & l \leq x \leq u, \end{aligned}$$

where x is a vector of decision variables; c , b_{ub} , b_{eq} , l , and u are vectors; and A_{ub} and A_{eq} are matrices.

Alternatively, that's:

minimize:

$c @ x$

such that:

```
A_ub @ x <= b_ub
A_eq @ x == b_eq
lb <= x <= ub
```

Note that by default `lb = 0` and `ub = None` unless specified with `bounds`.

Parameters

- c** [1-D array] The coefficients of the linear objective function to be minimized.
- A_ub** [2-D array, optional] The inequality constraint matrix. Each row of `A_ub` specifies the coefficients of a linear inequality constraint on `x`.
- b_ub** [1-D array, optional] The inequality constraint vector. Each element represents an upper bound on the corresponding value of `A_ub @ x`.
- A_eq** [2-D array, optional] The equality constraint matrix. Each row of `A_eq` specifies the coefficients of a linear equality constraint on `x`.
- b_eq** [1-D array, optional] The equality constraint vector. Each element of `A_eq @ x` must equal the corresponding element of `b_eq`.
- bounds** [sequence, optional] A sequence of `(min, max)` pairs for each element in `x`, defining the minimum and maximum values of that decision variable. Use `None` to indicate that there is no bound. By default, bounds are `(0, None)` (all decision variables are non-negative). If a single tuple `(min, max)` is provided, then `min` and `max` will serve as bounds for all decision variables.
- method** [str] This is the method-specific documentation for 'highs', which chooses automatically between 'highs-ds' and 'highs-ipm'. 'interior-point' (default), 'revised simplex', and 'simplex' (legacy) are also available.

Returns

- res** [OptimizeResult] A `scipy.optimize.OptimizeResult` consisting of the fields:
 - x** [1D array] The values of the decision variables that minimizes the objective function while satisfying the constraints.
 - fun** [float] The optimal value of the objective function `c @ x`.
 - slack** [1D array] The (nominally positive) values of the slack, `b_ub - A_ub @ x`.
 - con** [1D array] The (nominally zero) residuals of the equality constraints, `b_eq - A_eq @ x`.
 - success** [bool] `True` when the algorithm succeeds in finding an optimal solution.
 - status** [int] An integer representing the exit status of the algorithm.
 - 0 : Optimization terminated successfully.
 - 1 : Iteration or time limit reached.
 - 2 : Problem appears to be infeasible.
 - 3 : Problem appears to be unbounded.
 - 4 : The HiGHS solver ran into a problem.
 - message** [str] A string descriptor of the exit status of the algorithm.
 - nit** [int] The total number of iterations performed. For the HiGHS simplex method, this includes iterations in all phases. For the HiGHS interior-point method, this does not include crossover iterations.
 - crossover_nit** [int] The number of primal/dual pushes performed during the crossover routine for the HiGHS interior-point method. This is 0 for the HiGHS simplex method.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.linprog`

Options

maxiter	[int] The maximum number of iterations to perform in either phase. For <i>'highs-ipm'</i> , this does not include the number of crossover iterations. Default is the largest possible value for an <code>int</code> on the platform.
disp	[bool (default: <code>False</code>)] Set to <code>True</code> if indicators of optimization status are to be printed to the console during optimization.
presolve	[bool (default: <code>True</code>)] Presolve attempts to identify trivial infeasibilities, identify trivial unboundedness, and simplify the problem before sending it to the main solver. It is generally recommended to keep the default setting <code>True</code> ; set to <code>False</code> if presolve is to be disabled.
time_limit	[float] The maximum time in seconds allotted to solve the problem; default is the largest possible value for a <code>double</code> on the platform.
dual_feasibility_tolerance	[double (default: <code>1e-07</code>)] Dual feasibility tolerance for <i>'highs-ds'</i> . The minimum of this and <code>primal_feasibility_tolerance</code> is used for the feasibility tolerance of <i>'highs-ipm'</i> .
primal_feasibility_tolerance	[double (default: <code>1e-07</code>)] Primal feasibility tolerance for <i>'highs-ds'</i> . The minimum of this and <code>dual_feasibility_tolerance</code> is used for the feasibility tolerance of <i>'highs-ipm'</i> .
ipm_optimality_tolerance	[double (default: <code>1e-08</code>)] Optimality tolerance for <i>'highs-ipm'</i> . Minimum allowable value is <code>1e-12</code> .
simplex_dual_edge_weight_strategy	[str (default: <code>None</code>)] Strategy for simplex dual edge weights. The default, <code>None</code> , automatically selects one of the following. <i>'dantzig'</i> uses Dantzig's original strategy of choosing the most negative reduced cost. <i>'devex'</i> uses the strategy described in [15]. <i>steepest</i> uses the exact steepest edge strategy as described in [16]. <i>'steepest-devex'</i> begins with the exact steepest edge strategy until the computation is too costly or inexact and then switches to the <i>devex</i> method. Currently, <code>None</code> always selects <i>'steepest-devex'</i> , but this may change as new options become available.
unknown_options	[dict] Optional arguments not used by this particular solver. If <code>unknown_options</code> is non-empty, a warning is issued listing all unused options.

Notes

Method *'highs-ds'* is a wrapper of the C++ high performance dual revised simplex implementation (HSOL) [13], [14]. Method *'highs-ipm'* is a wrapper of a C++ implementation of an interior-point method [13]; it features a crossover routine, so it is as accurate as a simplex solver. Method *'highs'* chooses between the two automatically. For new code involving *linprog*, we recommend explicitly choosing one of these three method values instead of *'interior-point'* (default), *'revised simplex'*, and *'simplex'* (legacy).

References

[13], [14], [15], [16]

The simplex, interior-point, and revised simplex methods support callback functions, such as:

<code>linprog_verbose_callback(res)</code>	A sample callback function demonstrating the <i>linprog</i> callback interface.
--	---

scipy.optimize.linprog_verbose_callback

`scipy.optimize.linprog_verbose_callback` (*res*)

A sample callback function demonstrating the linprog callback interface. This callback produces detailed output to `sys.stdout` before each iteration and after the final iteration of the simplex algorithm.

Parameters

res	[A <code>scipy.optimize.OptimizeResult</code> consisting of the following fields:]
x	[1-D array] The independent variable vector which optimizes the linear programming problem.
fun	[float] Value of the objective function.
success	[bool] True if the algorithm succeeded in finding an optimal solution.
slack	[1-D array] The values of the slack variables. Each slack variable corresponds to an inequality constraint. If the slack is zero, then the corresponding constraint is active.
con	[1-D array] The (nominally zero) residuals of the equality constraints, that is, $b - A_{eq} @ x$
phase	[int] The phase of the optimization being executed. In phase 1 a basic feasible solution is sought and the T has an additional row representing an alternate objective function.
status	[int] An integer representing the exit status of the optimization: <div style="border: 1px solid black; padding: 5px; margin-top: 5px;"> <p>0 : Optimization terminated successfully 1 : Iteration limit reached 2 : Problem appears to be infeasible 3 : Problem appears to be unbounded 4 : Serious numerical difficulties encountered</p> </div>
nit	[int] The number of iterations performed.
message	[str] A string descriptor of the exit status of the optimization.

6.19.8 Assignment problems

<code>linear_sum_assignment(cost_matrix[, maximize])</code>	Solve the linear sum assignment problem.
<code>quadratic_assignment(A, B[, method, options])</code>	Approximates solution to the quadratic assignment problem and the graph matching problem.

scipy.optimize.linear_sum_assignment

`scipy.optimize.linear_sum_assignment` (*cost_matrix*, *maximize=False*)

Solve the linear sum assignment problem.

The linear sum assignment problem is also known as minimum weight matching in bipartite graphs. A problem instance is described by a matrix *C*, where each $C[i,j]$ is the cost of matching vertex *i* of the first partite set (a “worker”) and vertex *j* of the second set (a “job”). The goal is to find a complete assignment of workers to jobs of minimal cost.

Formally, let *X* be a boolean matrix where $X[i, j] = 1$ iff row *i* is assigned to column *j*. Then the optimal assignment has cost

$$\min \sum_i \sum_j C_{i,j} X_{i,j}$$

where, in the case where the matrix X is square, each row is assigned to exactly one column, and each column to exactly one row.

This function can also solve a generalization of the classic assignment problem where the cost matrix is rectangular. If it has more rows than columns, then not every row needs to be assigned to a column, and vice versa.

The problem is also solved for sparse inputs in `scipy.sparse.csgraph.min_weight_full_bipartite_matching` which may perform better if the input is sparse, or for certain classes of problems, such as uniformly distributed costs.

Parameters

cost_matrix

[array] The cost matrix of the bipartite graph.

maximize [bool (default: False)] Calculates a maximum weight matching if true.

Returns

row_ind, col_ind

[array] An array of row indices and one of corresponding column indices giving the optimal assignment. The cost of the assignment can be computed as `cost_matrix[row_ind, col_ind].sum()`. The row indices will be sorted; in the case of a square cost matrix they will be equal to `numpy.arange(cost_matrix.shape[0])`.

Notes

New in version 0.17.0.

References

1. https://en.wikipedia.org/wiki/Assignment_problem
2. DF Crouse. On implementing 2D rectangular assignment algorithms. *IEEE Transactions on Aerospace and Electronic Systems*, 52(4):1679-1696, August 2016, DOI:10.1109/TAES.2016.140952

Examples

```
>>> cost = np.array([[4, 1, 3], [2, 0, 5], [3, 2, 2]])
>>> from scipy.optimize import linear_sum_assignment
>>> row_ind, col_ind = linear_sum_assignment(cost)
>>> col_ind
array([1, 0, 2])
>>> cost[row_ind, col_ind].sum()
5
```

scipy.optimize.quadratic_assignment

`scipy.optimize.quadratic_assignment` (*A*, *B*, *method*='faq', *options*=None)

Approximates solution to the quadratic assignment problem and the graph matching problem.

Quadratic assignment solves problems of the following form:

$$\begin{aligned} \min_P \quad & \text{trace}(A^T P B P^T) \\ \text{s.t.} \quad & P \in \mathcal{P} \end{aligned}$$

where \mathcal{P} is the set of all permutation matrices, and *A* and *B* are square matrices.

Graph matching tries to *maximize* the same objective function. This algorithm can be thought of as finding the alignment of the nodes of two graphs that minimizes the number of induced edge disagreements, or, in the case of weighted graphs, the sum of squared edge weight differences.

Note that the quadratic assignment problem is NP-hard. The results given here are approximations and are not guaranteed to be optimal.

Parameters

A	[2-D array, square] The square matrix <i>A</i> in the objective function above.
B	[2-D array, square] The square matrix <i>B</i> in the objective function above.
method	[str in {'faq', '2opt'}] (default: 'faq') The algorithm used to solve the problem. 'faq' (default) and '2opt' are available.
options	[dict, optional] A dictionary of solver options. All solvers support the following: <ul style="list-style-type: none"> maximize [bool (default: False)] Maximizes the objective function if True. partial_match [2-D array of integers, optional (default: None)] Fixes part of the matching. Also known as a "seed" [2]. Each row of <i>partial_match</i> specifies a pair of matched nodes: node <i>partial_match</i>[<i>i</i>, 0] of <i>A</i> is matched to node <i>partial_match</i>[<i>i</i>, 1] of <i>B</i>. The array has shape (<i>m</i>, 2), where <i>m</i> is not greater than the number of nodes, <i>n</i>. rng [int, <i>RandomState</i>, <i>Generator</i> or None, optional (default: None)] Accepts an integer as a seed for the random generator or a <i>RandomState</i> or <i>Generator</i> object. If None (default), uses global <code>numpy.random</code> random state. For method-specific options, see <code>show_options('quadratic_assignment')</code>.

Returns

res	[OptimizeResult] <i>OptimizeResult</i> containing the following fields. <ul style="list-style-type: none"> col_ind [1-D array] Column indices corresponding to the best permutation found of the nodes of <i>B</i>. fun [float] The objective value of the solution. nit [int] The number of iterations performed during optimization.
------------	--

Notes

The default method 'faq' uses the Fast Approximate QAP algorithm [1]; it typically offers the best combination of speed and accuracy. Method '2opt' can be computationally expensive, but may be a useful alternative, or it can be used to refine the solution returned by another method.

References

[1], [2], [3]

Examples

```
>>> import numpy as np
>>> from scipy.optimize import quadratic_assignment
>>> A = np.array([[0, 80, 150, 170], [80, 0, 130, 100],
...              [150, 130, 0, 120], [170, 100, 120, 0]])
>>> B = np.array([[0, 5, 2, 7], [0, 0, 3, 8],
...              [0, 0, 0, 3], [0, 0, 0, 0]])
>>> res = quadratic_assignment(A, B)
>>> print(res)
col_ind: array([0, 3, 2, 1])
fun: 3260
nit: 9
```

To see the relationship between the returned `col_ind` and `fun`, use `col_ind` to form the best permutation matrix found, then evaluate the objective function $f(P) = \text{trace}(A^T P B P^T)$.

```
>>> perm = res['col_ind']
>>> P = np.eye(len(A), dtype=int)[perm]
>>> fun = np.trace(A.T @ P @ B @ P.T)
>>> print(fun)
3260
```

Alternatively, to avoid constructing the permutation matrix explicitly, directly permute the rows and columns of the distance matrix.

```
>>> fun = np.trace(A.T @ B[perm][:, perm])
>>> print(fun)
3260
```

Although not guaranteed in general, `quadratic_assignment` happens to have found the globally optimal solution.

```
>>> from itertools import permutations
>>> perm_opt, fun_opt = None, np.inf
>>> for perm in permutations([0, 1, 2, 3]):
...     perm = np.array(perm)
...     fun = np.trace(A.T @ B[perm][:, perm])
...     if fun < fun_opt:
...         fun_opt, perm_opt = fun, perm
>>> print(np.array_equal(perm_opt, res['col_ind']))
True
```

Here is an example for which the default method, `'faq'`, does not find the global optimum.

```
>>> A = np.array([[0, 5, 8, 6], [5, 0, 5, 1],
...              [8, 5, 0, 2], [6, 1, 2, 0]])
>>> B = np.array([[0, 1, 8, 4], [1, 0, 5, 2],
...              [8, 5, 0, 5], [4, 2, 5, 0]])
```

(continues on next page)

(continued from previous page)

```
>>> res = quadratic_assignment(A, B)
>>> print(res)
col_ind: array([1, 0, 3, 2])
fun: 178
nit: 13
```

If accuracy is important, consider using `'2opt'` to refine the solution.

```
>>> guess = np.array([np.arange(len(A)), res.col_ind]).T
>>> res = quadratic_assignment(A, B, method="2opt",
...                           options = {'partial_guess': guess})
>>> print(res)
col_ind: array([1, 2, 3, 0])
fun: 176
nit: 17
```

The `quadratic_assignment` function supports the following methods:

`quadratic_assignment(method='faq')`

`scipy.optimize.quadratic_assignment` (*A*, *B*, *method*='faq', *options*={'maximize': *False*, 'partial_match': *None*, 'rng': *None*, 'P0': 'barycenter', 'shuffle_input': *False*, 'maxiter': 30, 'tol': 0.03})

Solve the quadratic assignment problem (approximately).

This function solves the Quadratic Assignment Problem (QAP) and the Graph Matching Problem (GMP) using the Fast Approximate QAP Algorithm (FAQ) [1].

Quadratic assignment solves problems of the following form:

$$\begin{aligned} \min_P \quad & \text{trace}(A^T P B P^T) \\ \text{s.t.} \quad & P \in \mathcal{P} \end{aligned}$$

where \mathcal{P} is the set of all permutation matrices, and *A* and *B* are square matrices.

Graph matching tries to *maximize* the same objective function. This algorithm can be thought of as finding the alignment of the nodes of two graphs that minimizes the number of induced edge disagreements, or, in the case of weighted graphs, the sum of squared edge weight differences.

Note that the quadratic assignment problem is NP-hard. The results given here are approximations and are not guaranteed to be optimal.

Parameters

A [2-D array, square] The square matrix *A* in the objective function above.
B [2-D array, square] The square matrix *B* in the objective function above.
method [str in {'faq', '2opt'} (default: 'faq')] The algorithm used to solve the problem. This is the method-specific documentation for 'faq'. `'2opt'` is also available.

Returns

res [OptimizeResult] *OptimizeResult* containing the following fields.
col_ind [1-D array] Column indices corresponding to the best permutation found of the nodes of *B*.
fun [float] The objective value of the solution.
nit [int] The number of Frank-Wolfe iterations performed.

See also:

For documentation for the rest of the parameters, see `scipy.optimize.quadratic_assignment`

Options

maximize [bool (default: False)] Maximizes the objective function if True.

partial_match

[2-D array of integers, optional (default: None)] Fixes part of the matching. Also known as a “seed” [2].

Each row of `partial_match` specifies a pair of matched nodes: node `partial_match[i, 0]` of A is matched to node `partial_match[i, 1]` of B . The array has shape $(m, 2)$, where m is not greater than the number of nodes, n .

rng [int, `RandomState`, `Generator` or None, optional (default: None)] Accepts an integer as a seed for the random generator or a `RandomState` or `Generator` object. If None (default), uses global `numpy.random` random state.

P0 [2-D array, “barycenter”, or “randomized” (default: “barycenter”)] Initial position. Must be a doubly-stochastic matrix [3].

If the initial position is an array, it must be a doubly stochastic matrix of size $m' \times m'$ where $m' = n - m$.

If “barycenter” (default), the initial position is the barycenter of the Birkhoff polytope (the space of doubly stochastic matrices). This is a $m' \times m'$ matrix with all entries equal to $1/m'$.

If “randomized” the initial search position is $P_0 = (J+K)/2$, where J is the barycenter and K is a random doubly stochastic matrix.

shuffle_input

[bool (default: False)] Set to `True` to resolve degenerate gradients randomly. For non-degenerate gradients this option has no effect.

maxiter [int, positive (default: 30)] Integer specifying the max number of Frank-Wolfe iterations performed.

tol [float (default: 0.03)] Tolerance for termination. Frank-Wolfe iteration terminates when $\frac{\|P_i - P_{i+1}\|_F}{\sqrt{m'}} \leq tol$, where i is the iteration number.

Notes

The algorithm may be sensitive to the initial permutation matrix (or search “position”) due to the possibility of several local minima within the feasible region. A barycenter initialization is more likely to result in a better solution than a single random initialization. However, calling `quadratic_assignment` several times with different random initializations may result in a better optimum at the cost of longer total execution time.

References

[1], [2], [3]

Examples

As mentioned above, a barycenter initialization often results in a better solution than a single random initialization.

```
>>> np.random.seed(0)
>>> n = 15
>>> A = np.random.rand(n, n)
>>> B = np.random.rand(n, n)
>>> res = quadratic_assignment(A, B) # FAQ is default method
>>> print(res.fun)
46.871483385480545
```

```
>>> options = {"P0": "randomized"} # use randomized initialization
>>> res = quadratic_assignment(A, B, options=options)
>>> print(res.fun)
47.224831071310625 # may vary
```

However, consider running from several randomized initializations and keeping the best result.

```
>>> res = min([quadratic_assignment(A, B, options=options)
...           for i in range(30)], key=lambda x: x.fun)
>>> print(res.fun)
46.671852533681516 # may vary
```

The ‘2-opt’ method can be used to further refine the results.

```
>>> options = {"partial_guess": np.array([np.arange(n), res.col_ind]).T}
>>> res = quadratic_assignment(A, B, method="2opt", options=options)
>>> print(res.fun)
46.47160735721583 # may vary
```

quadratic_assignment(method='2opt')

`scipy.optimize.quadratic_assignment` (*A*, *B*, *method*='2opt', *options*={'maximize': *False*, 'rng': *None*, 'partial_match': *None*, 'partial_guess': *None*})

Solve the quadratic assignment problem (approximately).

This function solves the Quadratic Assignment Problem (QAP) and the Graph Matching Problem (GMP) using the 2-opt algorithm [1].

Quadratic assignment solves problems of the following form:

$$\begin{aligned} \min_P \quad & \text{trace}(A^T P B P^T) \\ \text{s.t.} \quad & P \in \mathcal{P} \end{aligned}$$

where \mathcal{P} is the set of all permutation matrices, and *A* and *B* are square matrices.

Graph matching tries to *maximize* the same objective function. This algorithm can be thought of as finding the alignment of the nodes of two graphs that minimizes the number of induced edge disagreements, or, in the case of weighted graphs, the sum of squared edge weight differences.

Note that the quadratic assignment problem is NP-hard. The results given here are approximations and are not guaranteed to be optimal.

Parameters

A	[2-D array, square] The square matrix A in the objective function above.
B	[2-D array, square] The square matrix B in the objective function above.
method	[str in {'faq', '2opt'} (default: 'faq')] The algorithm used to solve the problem. This is the method-specific documentation for '2opt'. <i>faq</i> is also available.

Returns

res	[OptimizeResult] <i>OptimizeResult</i> containing the following fields.
col_ind	[1-D array] Column indices corresponding to the best permutation found of the nodes of B .
fun	[float] The objective value of the solution.
nit	[int] The number of iterations performed during optimization.

See also:

For documentation for the rest of the parameters, see [*scipy.optimize.quadratic_assignment*](#)

Options

maximize	[bool (default: False)] Maximizes the objective function if True.
rng	[int, <i>RandomState</i> , <i>Generator</i> or None, optional (default: None)] Accepts an integer as a seed for the random generator or a <i>RandomState</i> or <i>Generator</i> object. If None (default), uses global <i>numpy.random</i> random state.
partial_match	[2-D array of integers, optional (default: None)] Fixes part of the matching. Also known as a “seed” [2]. Each row of <i>partial_match</i> specifies a pair of matched nodes: node <code>partial_match[i, 0]</code> of A is matched to node <code>partial_match[i, 1]</code> of B . The array has shape $(m, 2)$, where m is not greater than the number of nodes, n .
partial_guess	[2-D array of integers, optional (default: None)] A guess for the matching between the two matrices. Unlike <i>partial_match</i> , <i>partial_guess</i> does not fix the indices; they are still free to be optimized. Each row of <i>partial_guess</i> specifies a pair of matched nodes: node <code>partial_guess[i, 0]</code> of A is matched to node <code>partial_guess[i, 1]</code> of B . The array has shape $(m, 2)$, where m is not greater than the number of nodes, n .

Notes

This is a greedy algorithm that works similarly to bubble sort: beginning with an initial permutation, it iteratively swaps pairs of indices to improve the objective function until no such improvements are possible.

References

[1], [2]

6.19.9 Utilities

Finite-difference approximation

<code>approx_fprime(xk, f, epsilon, *args)</code>	Finite-difference approximation of the gradient of a scalar function.
<code>check_grad(func, grad, x0, *args, **kwargs)</code>	Check the correctness of a gradient function by comparing it against a (forward) finite-difference approximation of the gradient.

scipy.optimize.approx_fprime

`scipy.optimize.approx_fprime(xk, f, epsilon, *args)`

Finite-difference approximation of the gradient of a scalar function.

Parameters

- xk** [array_like] The coordinate vector at which to determine the gradient of f .
- f** [callable] The function of which to determine the gradient (partial derivatives). Should take xk as first argument, other arguments to f can be supplied in `*args`. Should return a scalar, the value of the function at xk .
- epsilon** [array_like] Increment to xk to use for determining the function gradient. If a scalar, uses the same finite difference delta for all partial derivatives. If an array, should contain one value per element of xk .
- *args** [args, optional] Any other arguments that are to be passed to f .

Returns

- grad** [ndarray] The partial derivatives of f to xk .

See also:

`check_grad`

Check correctness of gradient function against `approx_fprime`.

Notes

The function gradient is determined by the forward finite difference formula:

$$f'[i] = \frac{f(xk[i] + \epsilon[i]) - f(xk[i])}{\epsilon[i]}$$

The main use of `approx_fprime` is in scalar function optimizers like `fmin_bfgs`, to determine numerically the Jacobian of a function.

Examples

```
>>> from scipy import optimize
>>> def func(x, c0, c1):
...     "Coordinate vector `x` should be an array of size two."
...     return c0 * x[0]**2 + c1*x[1]**2
```

```
>>> x = np.ones(2)
>>> c0, c1 = (1, 200)
>>> eps = np.sqrt(np.finfo(float).eps)
>>> optimize.approx_fprime(x, func, [eps, np.sqrt(200) * eps], c0, c1)
array([ 2.          , 400.00004198])
```

scipy.optimize.check_grad

`scipy.optimize.check_grad(func, grad, x0, *args, **kwargs)`

Check the correctness of a gradient function by comparing it against a (forward) finite-difference approximation of the gradient.

Parameters

func	[callable func(x0, *args)] Function whose derivative is to be checked.
grad	[callable grad(x0, *args)] Gradient of <i>func</i> .
x0	[ndarray] Points to check <i>grad</i> against forward difference approximation of <i>grad</i> using <i>func</i> .
args	[*args, optional] Extra arguments passed to <i>func</i> and <i>grad</i> .
epsilon	[float, optional] Step size used for the finite difference approximation. It defaults to <code>sqrt(np.finfo(float).eps)</code> , which is approximately 1.49e-08.

Returns

err	[float] The square root of the sum of squares (i.e., the 2-norm) of the difference between <code>grad(x0, *args)</code> and the finite difference approximation of <i>grad</i> using <i>func</i> at the points <i>x0</i> .
------------	--

See also:

[*approx_fprime*](#)

Examples

```
>>> def func(x):
...     return x[0]**2 - 0.5 * x[1]**3
>>> def grad(x):
...     return [2 * x[0], -1.5 * x[1]**2]
>>> from scipy.optimize import check_grad
>>> check_grad(func, grad, [1.5, -1.5])
2.9802322387695312e-08
```

Line search

<code>bracket(func[, xa, xb, args, grow_limit, ...])</code>	Bracket the minimum of the function.
<code>line_search(f, myfprime, xk, pk[, gfk, ...])</code>	Find alpha that satisfies strong Wolfe conditions.

scipy.optimize.bracket

`scipy.optimize.bracket` (*func*, *xa=0.0*, *xb=1.0*, *args=()*, *grow_limit=110.0*, *maxiter=1000*)

Bracket the minimum of the function.

Given a function and distinct initial points, search in the downhill direction (as defined by the initial points) and return new points *xa*, *xb*, *xc* that bracket the minimum of the function $f(xa) > f(xb) < f(xc)$. It doesn't always mean that obtained solution will satisfy $xa \leq x \leq xb$.

Parameters

func	[callable $f(x, *args)$] Objective function to minimize.
xa, xb	[float, optional] Bracketing interval. Defaults <i>xa</i> to 0.0, and <i>xb</i> to 1.0.
args	[tuple, optional] Additional arguments (if present), passed to <i>func</i> .
grow_limit	[float, optional] Maximum grow limit. Defaults to 110.0
maxiter	[int, optional] Maximum number of iterations to perform. Defaults to 1000.


Returns

xa, xb, xc	[float] Bracket.
fa, fb, fc	[float] Objective function values in bracket.
funcalls	[int] Number of function evaluations made.

Examples

This function can find a downward convex region of a function:

```
>>> import matplotlib.pyplot as plt
>>> from scipy.optimize import bracket
>>> def f(x):
...     return 10*x**2 + 3*x + 5
>>> x = np.linspace(-2, 2)
>>> y = f(x)
>>> init_xa, init_xb = 0, 1
>>> xa, xb, xc, fa, fb, fc, funcalls = bracket(f, xa=init_xa, xb=init_xb)
>>> plt.axvline(x=init_xa, color="k", linestyle="--")
>>> plt.axvline(x=init_xb, color="k", linestyle="--")
>>> plt.plot(x, y, "-k")
>>> plt.plot(xa, fa, "bx")
>>> plt.plot(xb, fb, "rx")
>>> plt.plot(xc, fc, "bx")
>>> plt.show()
```

scipy.optimize.line_search

`scipy.optimize.line_search`(*f*, *myfprime*, *xk*, *pk*, *gfk=None*, *old_fval=None*, *old_old_fval=None*, *args=()*, *c1=0.0001*, *c2=0.9*, *amax=None*, *extra_condition=None*, *maxiter=10*)

Find alpha that satisfies strong Wolfe conditions.

Parameters

- f** [callable $f(x, *args)$] Objective function.
- myfprime** [callable $f'(x, *args)$] Objective function gradient.
- xk** [ndarray] Starting point.
- pk** [ndarray] Search direction.
- gfk** [ndarray, optional] Gradient value for $x=xk$ (xk being the current parameter estimate). Will be recomputed if omitted.
- old_fval** [float, optional] Function value for $x=xk$. Will be recomputed if omitted.
- old_old_fval** [float, optional] Function value for the point preceding $x=xk$.
- args** [tuple, optional] Additional arguments passed to objective function.
- c1** [float, optional] Parameter for Armijo condition rule.
- c2** [float, optional] Parameter for curvature condition rule.
- amax** [float, optional] Maximum step size
- extra_condition** [callable, optional] A callable of the form `extra_condition(alpha, x, f, g)` returning a boolean. Arguments are the proposed step `alpha` and the corresponding `x`, `f` and `g` values. The line search accepts the value of `alpha` only if this callable returns `True`. If the callable returns `False` for the step length, the algorithm will continue with new iterates. The callable is only called for iterates satisfying the strong Wolfe conditions.
- maxiter** [int, optional] Maximum number of iterations to perform.

Returns

- alpha** [float or None] Alpha for which $x_{\text{new}} = x_0 + \text{alpha} * pk$, or None if the line search algorithm did not converge.
- fc** [int] Number of function evaluations made.
- gc** [int] Number of gradient evaluations made.

new_fval [float or None] New function value $f(x_{\text{new}}) = f(x_0 + \alpha p_k)$, or None if the line search algorithm did not converge.

old_fval [float] Old function value $f(x_0)$.

new_slope [float or None] The local slope along the search direction at the new value $\langle \text{myfprime}(x_{\text{new}}), p_k \rangle$, or None if the line search algorithm did not converge.

Notes

Uses the line search algorithm to enforce strong Wolfe conditions. See Wright and Nocedal, ‘Numerical Optimization’, 1999, pp. 59-61.

Examples

```
>>> from scipy.optimize import line_search
```

A objective function and its gradient are defined.

```
>>> def obj_func(x):
...     return x[0]**2 + (x[1])**2
>>> def obj_grad(x):
...     return [2*x[0], 2*x[1]]
```

We can find alpha that satisfies strong Wolfe conditions.

```
>>> start_point = np.array([1.8, 1.7])
>>> search_gradient = np.array([-1.0, -1.0])
>>> line_search(obj_func, obj_grad, start_point, search_gradient)
(1.0, 2, 1, 1.1300000000000001, 6.13, [1.6, 1.4])
```

Hessian approximation

<i>LbfgsInvHessProduct</i> (*args, **kwargs)	Linear operator for the L-BFGS approximate inverse Hessian.
<i>HessianUpdateStrategy</i> ()	Interface for implementing Hessian update strategies.

scipy.optimize.LbfgsInvHessProduct

class `scipy.optimize.LbfgsInvHessProduct` (*args, **kwargs)

Linear operator for the L-BFGS approximate inverse Hessian.

This operator computes the product of a vector with the approximate inverse of the Hessian of the objective function, using the L-BFGS limited memory approximation to the inverse Hessian, accumulated during the optimization.

Objects of this class implement the `scipy.sparse.linalg.LinearOperator` interface.

Parameters

sk [array_like, shape=(n_corr, n)] Array of *n_corr* most recent updates to the solution vector. (See [1]).

yk [array_like, shape=(n_corr, n)] Array of *n_corr* most recent updates to the gradient. (See [1]).

References

[1]

Attributes

H	Hermitian adjoint.
T	Transpose this linear operator.

Methods

<code>__call__(self, x)</code>	Call self as a function.
<code>adjoint(self)</code>	Hermitian adjoint.
<code>dot(self, x)</code>	Matrix-matrix or matrix-vector multiplication.
<code>matmat(self, X)</code>	Matrix-matrix multiplication.
<code>matvec(self, x)</code>	Matrix-vector multiplication.
<code>rmatmat(self, X)</code>	Adjoint matrix-matrix multiplication.
<code>rmatvec(self, x)</code>	Adjoint matrix-vector multiplication.
<code>todense(self)</code>	Return a dense array representation of this operator.
<code>transpose(self)</code>	Transpose this linear operator.

`scipy.optimize.LbfgsInvHessProduct.__call__`

`LbfgsInvHessProduct.__call__(self, x)`
Call self as a function.

`scipy.optimize.LbfgsInvHessProduct.adjoint`

`LbfgsInvHessProduct.adjoint(self)`
Hermitian adjoint.

Returns the Hermitian adjoint of `self`, aka the Hermitian conjugate or Hermitian transpose. For a complex matrix, the Hermitian adjoint is equal to the conjugate transpose.

Can be abbreviated `self.H` instead of `self.adjoint()`.

Returns

A_H [LinearOperator] Hermitian adjoint of `self`.

`scipy.optimize.LbfgsInvHessProduct.dot`

`LbfgsInvHessProduct.dot(self, x)`
Matrix-matrix or matrix-vector multiplication.

Parameters

x [array_like] 1-d or 2-d array, representing a vector or matrix.

Returns

Ax [array] 1-d or 2-d array (depending on the shape of `x`) that represents the result of applying this linear operator on `x`.

scipy.optimize.LbfgsInvHessProduct.matmat

LbfgsInvHessProduct.**matmat** (*self*, *X*)

Matrix-matrix multiplication.

Performs the operation $y=A*X$ where *A* is an *MxN* linear operator and *X* dense *N*K* matrix or ndarray.

Parameters

X [*{matrix, ndarray}*] An array with shape (*N,K*).

Returns

Y [*{matrix, ndarray}*] A matrix or ndarray with shape (*M,K*) depending on the type of the *X* argument.

Notes

This matmat wraps any user-specified matmat routine or overridden `_matmat` method to ensure that *y* has the correct type.

scipy.optimize.LbfgsInvHessProduct.matvec

LbfgsInvHessProduct.**matvec** (*self*, *x*)

Matrix-vector multiplication.

Performs the operation $y=A*x$ where *A* is an *MxN* linear operator and *x* is a column vector or 1-d array.

Parameters

x [*{matrix, ndarray}*] An array with shape (*N,*) or (*N,1*).

Returns

y [*{matrix, ndarray}*] A matrix or ndarray with shape (*M,*) or (*M,1*) depending on the type and shape of the *x* argument.

Notes

This matvec wraps the user-specified matvec routine or overridden `_matvec` method to ensure that *y* has the correct shape and type.

scipy.optimize.LbfgsInvHessProduct.rmatmat

LbfgsInvHessProduct.**rmatmat** (*self*, *X*)

Adjoint matrix-matrix multiplication.

Performs the operation $y = A^H * x$ where *A* is an *MxN* linear operator and *x* is a column vector or 1-d array, or 2-d array. The default implementation defers to the adjoint.

Parameters

X [*{matrix, ndarray}*] A matrix or 2D array.

Returns

Y [*{matrix, ndarray}*] A matrix or 2D array depending on the type of the input.

Notes

This `rmatmat` wraps the user-specified `rmatmat` routine.

`scipy.optimize.LbfgsInvHessProduct.rmatvec`

`LbfgsInvHessProduct.rmatvec` (*self*, *x*)

Adjoint matrix-vector multiplication.

Performs the operation $y = A^H * x$ where A is an $M \times N$ linear operator and x is a column vector or 1-d array.

Parameters

x [matrix, ndarray] An array with shape $(M,)$ or $(M,1)$.

Returns

y [matrix, ndarray] A matrix or ndarray with shape $(N,)$ or $(N,1)$ depending on the type and shape of the x argument.

Notes

This `rmatvec` wraps the user-specified `rmatvec` routine or overridden `_rmatvec` method to ensure that y has the correct shape and type.

`scipy.optimize.LbfgsInvHessProduct.todense`

`LbfgsInvHessProduct.todense` (*self*)

Return a dense array representation of this operator.

Returns

arr [ndarray, shape=(n, n)] An array with the same shape and containing the same data represented by this *LinearOperator*.

`scipy.optimize.LbfgsInvHessProduct.transpose`

`LbfgsInvHessProduct.t.transpose` (*self*)

Transpose this linear operator.

Returns a `LinearOperator` that represents the transpose of this one. Can be abbreviated `self.T` instead of `self.transpose()`.

<code>__mul__</code>	
----------------------	--

scipy.optimize.HessianUpdateStrategy

class `scipy.optimize.HessianUpdateStrategy`

Interface for implementing Hessian update strategies.

Many optimization methods make use of Hessian (or inverse Hessian) approximations, such as the quasi-Newton methods BFGS, SR1, L-BFGS. Some of these approximations, however, do not actually need to store the entire matrix or can compute the internal matrix product with a given vector in a very efficiently manner. This class serves as an abstract interface between the optimization algorithm and the quasi-Newton update strategies, giving freedom of implementation to store and update the internal matrix as efficiently as possible. Different choices of initialization and update procedure will result in different quasi-Newton strategies.

Four methods should be implemented in derived classes: `initialize`, `update`, `dot` and `get_matrix`.

Notes

Any instance of a class that implements this interface, can be accepted by the method `minimize` and used by the compatible solvers to approximate the Hessian (or inverse Hessian) used by the optimization algorithms.

Methods

<code>dot(self, p)</code>	Compute the product of the internal matrix with the given vector.
<code>get_matrix(self)</code>	Return current internal matrix.
<code>initialize(self, n, approx_type)</code>	Initialize internal matrix.
<code>update(self, delta_x, delta_grad)</code>	Update internal matrix.

scipy.optimize.HessianUpdateStrategy.dot

`HessianUpdateStrategy.dot(self, p)`

Compute the product of the internal matrix with the given vector.

Parameters

p [array_like] 1-D array representing a vector.

Returns

Hp [array] 1-D represents the result of multiplying the approximation matrix by vector `p`.

scipy.optimize.HessianUpdateStrategy.get_matrix

`HessianUpdateStrategy.get_matrix(self)`

Return current internal matrix.

Returns

H [ndarray, shape (n, n)] Dense matrix containing either the Hessian or its inverse (depending on how 'approx_type' is defined).

scipy.optimize.HessianUpdateStrategy.initialize

`HessianUpdateStrategy.initialize` (*self*, *n*, *approx_type*)

Initialize internal matrix.

Allocate internal memory for storing and updating the Hessian or its inverse.

Parameters

- n** [int] Problem dimension.
- approx_type** [{"hess", "inv_hess"}] Selects either the Hessian or the inverse Hessian. When set to 'hess' the Hessian will be stored and updated. When set to 'inv_hess' its inverse will be used instead.

scipy.optimize.HessianUpdateStrategy.update

`HessianUpdateStrategy.update` (*self*, *delta_x*, *delta_grad*)

Update internal matrix.

Update Hessian matrix or its inverse (depending on how 'approx_type' is defined) using information about the last evaluated points.

Parameters

- delta_x** [ndarray] The difference between two points the gradient function have been evaluated at: $\text{delta_x} = \text{x2} - \text{x1}$.
- delta_grad** [ndarray] The difference between the gradients: $\text{delta_grad} = \text{grad}(\text{x2}) - \text{grad}(\text{x1})$.

Benchmark problems

<code>rosen(x)</code>	The Rosenbrock function.
<code>rosen_der(x)</code>	The derivative (i.e.
<code>rosen_hess(x)</code>	The Hessian matrix of the Rosenbrock function.
<code>rosen_hess_prod(x, p)</code>	Product of the Hessian matrix of the Rosenbrock function with a vector.

scipy.optimize.rosen

`scipy.optimize.rosen` (*x*)

The Rosenbrock function.

The function computed is:

```
sum(100.0 * (x[1:] - x[:-1])**2.0)**2.0 + (1 - x[:-1])**2.0
```

Parameters

- x** [array_like] 1-D array of points at which the Rosenbrock function is to be computed.

Returns

- f** [float] The value of the Rosenbrock function.

See also:


[`rosen_der`](#), [`rosen_hess`](#), [`rosen_hess_prod`](#)

Examples

```
>>> from scipy.optimize import rosen
>>> X = 0.1 * np.arange(10)
>>> rosen(X)
76.56
```

For higher-dimensional input `rosen` broadcasts. In the following example, we use this to plot a 2D landscape. Note that `rosen_hess` does not broadcast in this manner.

```
>>> import matplotlib.pyplot as plt
>>> from mpl_toolkits.mplot3d import Axes3D
>>> x = np.linspace(-1, 1, 50)
>>> X, Y = np.meshgrid(x, x)
>>> ax = plt.subplot(111, projection='3d')
>>> ax.plot_surface(X, Y, rosen([X, Y]))
>>> plt.show()
```



`scipy.optimize.rosen_der`

`scipy.optimize.rosen_der(x)`

The derivative (i.e. gradient) of the Rosenbrock function.

Parameters

x [array_like] 1-D array of points at which the derivative is to be computed.

Returns

rosen_der [(N,) ndarray] The gradient of the Rosenbrock function at *x*.

See also:

rosen, rosen_hess, rosen_hess_prod

Examples

```
>>> from scipy.optimize import rosen_der
>>> X = 0.1 * np.arange(9)
>>> rosen_der(X)
array([-2. , 10.6, 15.6, 13.4,  6.4, -3. , -12.4, -19.4, 62. ])
```

scipy.optimize.rosen_hess

scipy.optimize.**rosen_hess**(*x*)

The Hessian matrix of the Rosenbrock function.

Parameters

x [array_like] 1-D array of points at which the Hessian matrix is to be computed.

Returns

rosen_hess
[ndarray] The Hessian matrix of the Rosenbrock function at *x*.

See also:

rosen, rosen_der, rosen_hess_prod

Examples

```
>>> from scipy.optimize import rosen_hess
>>> X = 0.1 * np.arange(4)
>>> rosen_hess(X)
array([[ -38.,   0.,   0.,   0.],
       [   0., 134., -40.,   0.],
       [   0., -40., 130., -80.],
       [   0.,   0., -80., 200.]])
```

scipy.optimize.rosen_hess_prod

scipy.optimize.**rosen_hess_prod**(*x, p*)

Product of the Hessian matrix of the Rosenbrock function with a vector.

Parameters

x [array_like] 1-D array of points at which the Hessian matrix is to be computed.

p [array_like] 1-D array, the vector to be multiplied by the Hessian matrix.

Returns

rosen_hess_prod
[ndarray] The Hessian matrix of the Rosenbrock function at *x* multiplied by the vector *p*.

See also:

rosen, rosen_der, rosen_hess

Examples

```
>>> from scipy.optimize import rosen_hess_prod
>>> X = 0.1 * np.arange(9)
>>> p = 0.5 * np.arange(9)
>>> rosen_hess_prod(X, p)
array([-0., 27., -10., -95., -192., -265., -278., -195., -180.]
```

6.19.10 Legacy functions

The functions below are not recommended for use in new scripts; all of these methods are accessible via a newer, more consistent interfaces, provided by the interfaces above.

Optimization

General-purpose multivariate methods:

<code>fmin(func, x0[, args, xtol, ftol, maxiter, ...])</code>	Minimize a function using the downhill simplex algorithm.
<code>fmin_powell(func, x0[, args, xtol, ftol, ...])</code>	Minimize a function using modified Powell's method.
<code>fmin_cg(f, x0[, fprime, args, gtol, norm, ...])</code>	Minimize a function using a nonlinear conjugate gradient algorithm.
<code>fmin_bfgs(f, x0[, fprime, args, gtol, norm, ...])</code>	Minimize a function using the BFGS algorithm.
<code>fmin_ncg(f, x0, fprime[, fhess_p, fhess, ...])</code>	Unconstrained minimization of a function using the Newton-CG method.

scipy.optimize.fmin

`scipy.optimize.fmin(func, x0, args=(), xtol=0.0001, ftol=0.0001, maxiter=None, maxfun=None, full_output=0, disp=1, retall=0, callback=None, initial_simplex=None)`

Minimize a function using the downhill simplex algorithm.

This algorithm only uses function values, not derivatives or second derivatives.

Parameters

func	[callable func(x,*args)] The objective function to be minimized.
x0	[ndarray] Initial guess.
args	[tuple, optional] Extra arguments passed to func, i.e., $f(x, *args)$.
xtol	[float, optional] Absolute error in x_{opt} between iterations that is acceptable for convergence.
ftol	[number, optional] Absolute error in $func(x_{opt})$ between iterations that is acceptable for convergence.
maxiter	[int, optional] Maximum number of iterations to perform.
maxfun	[number, optional] Maximum number of function evaluations to make.
full_output	[bool, optional] Set to True if <code>fopt</code> and <code>warnflag</code> outputs are desired.
disp	[bool, optional] Set to True to print convergence messages.
retall	[bool, optional] Set to True to return list of solutions at each iteration.
callback	[callable, optional] Called after each iteration, as <code>callback(xk)</code> , where <code>xk</code> is the current parameter vector.
initial_simplex	

[array_like of shape (N + 1, N), optional] Initial simplex. If given, overrides `x0`. `initial_simplex[j, :]` should contain the coordinates of the `j`th vertex of the `N+1` vertices in the simplex, where `N` is the dimension.

Returns

xopt [ndarray] Parameter that minimizes function.
fopt [float] Value of function at minimum: `fopt = func(xopt)`.
iter [int] Number of iterations performed.
funcalls [int] Number of function calls made.
warnflag [int] 1 : Maximum number of function evaluations made. 2 : Maximum number of iterations reached.
allvecs [list] Solution at each iteration.

See also:

`minimize`

Interface to minimization algorithms for multivariate functions. See the ‘Nelder-Mead’ *method* in particular.

Notes

Uses a Nelder-Mead simplex algorithm to find the minimum of function of one or more variables.

This algorithm has a long history of successful use in applications. But it will usually be slower than an algorithm that uses first or second derivative information. In practice, it can have poor performance in high-dimensional problems and is not robust to minimizing complicated functions. Additionally, there currently is no complete theory describing when the algorithm will successfully converge to the minimum, or how fast it will if it does. Both the `ftol` and `xtol` criteria must be met for convergence.

References

[1], [2]

Examples

```
>>> def f(x):
...     return x**2
```

```
>>> from scipy import optimize
```

```
>>> minimum = optimize.fmin(f, 1)
Optimization terminated successfully.
      Current function value: 0.000000
      Iterations: 17
      Function evaluations: 34
>>> minimum[0]
-8.8817841970012523e-16
```

scipy.optimize.fmin_powell

`scipy.optimize.fmin_powell` (*func*, *x0*, *args=()*, *xtol=0.0001*, *ftol=0.0001*, *maxiter=None*, *maxfun=None*, *full_output=0*, *disp=1*, *retall=0*, *callback=None*, *direc=None*)

Minimize a function using modified Powell's method.

This method only uses function values, not derivatives.

Parameters

func	[callable f(x,*args)] Objective function to be minimized.
x0	[ndarray] Initial guess.
args	[tuple, optional] Extra arguments passed to func.
xtol	[float, optional] Line-search error tolerance.
ftol	[float, optional] Relative error in <code>func(xopt)</code> acceptable for convergence.
maxiter	[int, optional] Maximum number of iterations to perform.
maxfun	[int, optional] Maximum number of function evaluations to make.
full_output	[bool, optional] If True, <code>fopt</code> , <code>xi</code> , <code>direc</code> , <code>iter</code> , <code>funcalls</code> , and <code>warnflag</code> are returned.
disp	[bool, optional] If True, print convergence messages.
retall	[bool, optional] If True, return a list of the solution at each iteration.
callback	[callable, optional] An optional user-supplied function, called after each iteration. Called as <code>callback(xk)</code> , where <code>xk</code> is the current parameter vector.
direc	[ndarray, optional] Initial fitting step and parameter order set as an (N, N) array, where N is the number of fitting parameters in <code>x0</code> . Defaults to step size 1.0 fitting all parameters simultaneously (<code>np.ones((N, N))</code>). To prevent initial consideration of values in a step or to change initial step size, set to 0 or desired step size in the Jth position in the Mth block, where J is the position in <code>x0</code> and M is the desired evaluation step, with steps being evaluated in index order. Step size and ordering will change freely as minimization proceeds.

Returns

xopt	[ndarray] Parameter which minimizes <i>func</i> .
fopt	[number] Value of function at minimum: <code>fopt = func(xopt)</code> .
direc	[ndarray] Current direction set.
iter	[int] Number of iterations.
funcalls	[int] Number of function calls made.
warnflag	[int]
	Integer warning flag:
	1 : Maximum number of function evaluations. 2 : Maximum number of iterations. 3 : NaN result encountered. 4 : The result is out of the provided bounds.
allvecs	[list] List of solutions at each iteration.

See also:

minimize

Interface to unconstrained minimization algorithms for multivariate functions. See the 'Powell' method in particular.

Notes

Uses a modification of Powell's method to find the minimum of a function of N variables. Powell's method is a conjugate direction method.

The algorithm has two loops. The outer loop merely iterates over the inner loop. The inner loop minimizes over each current direction in the direction set. At the end of the inner loop, if certain conditions are met, the direction that gave the largest decrease is dropped and replaced with the difference between the current estimated x and the estimated x from the beginning of the inner-loop.

The technical conditions for replacing the direction of greatest increase amount to checking that

1. No further gain can be made along the direction of greatest increase from that iteration.
2. The direction of greatest increase accounted for a large sufficient fraction of the decrease in the function value from that iteration of the inner loop.

References

Powell M.J.D. (1964) An efficient method for finding the minimum of a function of several variables without calculating derivatives, *Computer Journal*, 7 (2):155-162.

Press W., Teukolsky S.A., Vetterling W.T., and Flannery B.P.: *Numerical Recipes* (any edition), Cambridge University Press

Examples

```
>>> def f(x):
...     return x**2
```

```
>>> from scipy import optimize
```

```
>>> minimum = optimize.fmin_powell(f, -1)
Optimization terminated successfully.
    Current function value: 0.000000
    Iterations: 2
    Function evaluations: 18
>>> minimum
array(0.0)
```

scipy.optimize.fmin_cg

```
scipy.optimize.fmin_cg(f, x0, fprime=None, args=(), gtol=1e-05, norm=inf,
                       epsilon=1.4901161193847656e-08, maxiter=None, full_output=0, disp=1,
                       retall=0, callback=None)
```

Minimize a function using a nonlinear conjugate gradient algorithm.

Parameters

- | | |
|-----------|---|
| f | [callable, $f(x, *args)$] Objective function to be minimized. Here x must be a 1-D array of the variables that are to be changed in the search for a minimum, and $args$ are the other (fixed) parameters of f . |
| x0 | [ndarray] A user-supplied initial estimate of x_{opt} , the optimal value of x . It must be a 1-D array of values. |

fprime	[callable, <code>fprime(x, *args)</code> , optional] A function that returns the gradient of f at x . Here x and $args$ are as described above for f . The returned value must be a 1-D array. Defaults to None, in which case the gradient is approximated numerically (see <i>epsilon</i> , below).
args	[tuple, optional] Parameter values passed to f and $fprime$. Must be supplied whenever additional fixed parameters are needed to completely specify the functions f and $fprime$.
gtol	[float, optional] Stop when the norm of the gradient is less than <i>gtol</i> .
norm	[float, optional] Order to use for the norm of the gradient (<code>-np.Inf</code> is min, <code>np.Inf</code> is max).
epsilon	[float or ndarray, optional] Step size(s) to use when $fprime$ is approximated numerically. Can be a scalar or a 1-D array. Defaults to <code>sqrt(eps)</code> , with <code>eps</code> the floating point machine precision. Usually <code>sqrt(eps)</code> is about $1.5e-8$.
maxiter	[int, optional] Maximum number of iterations to perform. Default is <code>200 * len(x0)</code> .
full_output	[bool, optional] If True, return <i>fopt</i> , <i>func_calls</i> , <i>grad_calls</i> , and <i>warnflag</i> in addition to <i>xopt</i> . See the Returns section below for additional information on optional return values.
disp	[bool, optional] If True, return a convergence message, followed by <i>xopt</i> .
retall	[bool, optional] If True, add to the returned values the results of each iteration.
callback	[callable, optional] An optional user-supplied function, called after each iteration. Called as <code>callback(xk)</code> , where xk is the current value of $x0$.

Returns

xopt	[ndarray] Parameters which minimize f , i.e., $f(xopt) == fopt$.
fopt	[float, optional] Minimum value found, $f(xopt)$. Only returned if <i>full_output</i> is True.
func_calls	[int, optional] The number of function calls made. Only returned if <i>full_output</i> is True.
grad_calls	[int, optional] The number of gradient calls made. Only returned if <i>full_output</i> is True.
warnflag	[int, optional] Integer value with warning status, only returned if <i>full_output</i> is True. 0 : Success. 1 : The maximum number of iterations was exceeded. 2 [Gradient and/or function calls were not changing. May indicate] that precision was lost, i.e., the routine did not converge. 3 : NaN result encountered.
allvecs	[list of ndarray, optional] List of arrays, containing the results at each iteration. Only returned if <i>retall</i> is True.

See also:

minimize

common interface to all `scipy.optimize` algorithms for unconstrained and constrained minimization of multivariate functions. It provides an alternative way to call `fmin_cg`, by specifying `method='CG'`.

Notes

This conjugate gradient algorithm is based on that of Polak and Ribiere [1].

Conjugate gradient methods tend to work better when:

1. f has a unique global minimizing point, and no local minima or other stationary points,
2. f is, at least locally, reasonably well approximated by a quadratic function of the variables,
3. f is continuous and has a continuous gradient,
4. $fprime$ is not too large, e.g., has a norm less than 1000,
5. The initial guess, $x0$, is reasonably close to f 's global minimizing point, *xopt*.

References

[1]

Examples

Example 1: seek the minimum value of the expression $a*u**2 + b*u*v + c*v**2 + d*u + e*v + f$ for given values of the parameters and an initial guess $(u, v) = (0, 0)$.

```
>>> args = (2, 3, 7, 8, 9, 10) # parameter values
>>> def f(x, *args):
...     u, v = x
...     a, b, c, d, e, f = args
...     return a*u**2 + b*u*v + c*v**2 + d*u + e*v + f
>>> def gradf(x, *args):
...     u, v = x
...     a, b, c, d, e, f = args
...     gu = 2*a*u + b*v + d # u-component of the gradient
...     gv = b*u + 2*c*v + e # v-component of the gradient
...     return np.asarray((gu, gv))
>>> x0 = np.asarray((0, 0)) # Initial guess.
>>> from scipy import optimize
>>> res1 = optimize.fmin_cg(f, x0, fprime=gradf, args=args)
Optimization terminated successfully.
    Current function value: 1.617021
    Iterations: 4
    Function evaluations: 8
    Gradient evaluations: 8
>>> res1
array([-1.80851064, -0.25531915])
```

Example 2: solve the same problem using the `minimize` function. (This `myopts` dictionary shows all of the available options, although in practice only non-default values would be needed. The returned value will be a dictionary.)

```
>>> opts = {'maxiter' : None, # default value.
...        'disp' : True, # non-default value.
...        'gtol' : 1e-5, # default value.
...        'norm' : np.inf, # default value.
...        'eps' : 1.4901161193847656e-08} # default value.
>>> res2 = optimize.minimize(f, x0, jac=gradf, args=args,
...                          method='CG', options=opts)
Optimization terminated successfully.
    Current function value: 1.617021
    Iterations: 4
    Function evaluations: 8
    Gradient evaluations: 8
>>> res2.x # minimum found
array([-1.80851064, -0.25531915])
```

scipy.optimize.fmin_bfgs

`scipy.optimize.fmin_bfgs` (*f*, *x0*, *fprime=None*, *args=()*, *gtol=1e-05*, *norm=inf*, *epsilon=1.4901161193847656e-08*, *maxiter=None*, *full_output=0*, *disp=1*, *retall=0*, *callback=None*)

Minimize a function using the BFGS algorithm.

Parameters

f	[callable f(x,*args)] Objective function to be minimized.
x0	[ndarray] Initial guess.
fprime	[callable f'(x,*args), optional] Gradient of f.
args	[tuple, optional] Extra arguments passed to f and fprime.
gtol	[float, optional] Gradient norm must be less than gtol before successful termination.
norm	[float, optional] Order of norm (Inf is max, -Inf is min)
epsilon	[int or ndarray, optional] If fprime is approximated, use this value for the step size.
callback	[callable, optional] An optional user-supplied function to call after each iteration. Called as callback(xk), where xk is the current parameter vector.
maxiter	[int, optional] Maximum number of iterations to perform.
full_output	[bool, optional] If True, return fopt, func_calls, grad_calls, and warnflag in addition to xopt.
disp	[bool, optional] Print convergence message if True.
retall	[bool, optional] Return a list of results at each iteration if True.

Returns

xopt	[ndarray] Parameters which minimize f, i.e., $f(xopt) == fopt$.
fopt	[float] Minimum value.
gopt	[ndarray] Value of gradient at minimum, $f'(xopt)$, which should be near 0.
Bopt	[ndarray] Value of $1/f''(xopt)$, i.e., the inverse Hessian matrix.
func_calls	[int] Number of function_calls made.
grad_calls	[int] Number of gradient calls made.
warnflag	[integer] 1 : Maximum number of iterations exceeded. 2 : Gradient and/or function calls not changing. 3 : NaN result encountered.
allvecs	[list] The value of xopt at each iteration. Only returned if retall is True.

See also:

[minimize](#)

Interface to minimization algorithms for multivariate functions. See the ‘BFGS’ *method* in particular.

Notes

Optimize the function, *f*, whose gradient is given by *fprime* using the quasi-Newton method of Broyden, Fletcher, Goldfarb, and Shanno (BFGS)

References

Wright, and Nocedal ‘Numerical Optimization’, 1999, p. 198.

scipy.optimize.fmin_ncg

`scipy.optimize.fmin_ncg`(*f*, *x0*, *fprime*, *fhess_p=None*, *fhess=None*, *args=()*, *avextol=1e-05*, *epsilon=1.4901161193847656e-08*, *maxiter=None*, *full_output=0*, *disp=1*, *retall=0*, *callback=None*)

Unconstrained minimization of a function using the Newton-CG method.

Parameters

f	[callable <i>f</i> (<i>x</i> , * <i>args</i>)] Objective function to be minimized.
x0	[ndarray] Initial guess.
fprime	[callable <i>f'</i> (<i>x</i> , * <i>args</i>)] Gradient of <i>f</i> .
fhess_p	[callable <i>fhess_p</i> (<i>x</i> , <i>p</i> , * <i>args</i>), optional] Function which computes the Hessian of <i>f</i> times an arbitrary vector, <i>p</i> .
fhess	[callable <i>fhess</i> (<i>x</i> , * <i>args</i>), optional] Function to compute the Hessian matrix of <i>f</i> .
args	[tuple, optional] Extra arguments passed to <i>f</i> , <i>fprime</i> , <i>fhess_p</i> , and <i>fhess</i> (the same set of extra arguments is supplied to all of these functions).
epsilon	[float or ndarray, optional] If <i>fhess</i> is approximated, use this value for the step size.
callback	[callable, optional] An optional user-supplied function which is called after each iteration. Called as <code>callback(xk)</code> , where <i>xk</i> is the current parameter vector.
avextol	[float, optional] Convergence is assumed when the average relative error in the minimizer falls below this amount.
maxiter	[int, optional] Maximum number of iterations to perform.
full_output	[bool, optional] If True, return the optional outputs.
disp	[bool, optional] If True, print convergence message.
retall	[bool, optional] If True, return a list of results at each iteration.

Returns

xopt	[ndarray] Parameters which minimize <i>f</i> , i.e., $f(x_{opt}) = f_{opt}$.
fopt	[float] Value of the function at <i>xopt</i> , i.e., $f_{opt} = f(x_{opt})$.
fcalls	[int] Number of function calls made.
gcalls	[int] Number of gradient calls made.
hcalls	[int] Number of Hessian calls made.
warnflag	[int] Warnings generated by the algorithm. 1 : Maximum number of iterations exceeded. 2 : Line search failure (precision loss). 3 : NaN result encountered.
allvecs	[list] The result at each iteration, if <i>retall</i> is True (see below).

See also:

`minimize`

Interface to minimization algorithms for multivariate functions. See the ‘Newton-CG’ *method* in particular.

Notes

Only one of *fhess_p* or *fhess* need to be given. If *fhess* is provided, then *fhess_p* will be ignored. If neither *fhess* nor *fhess_p* is provided, then the hessian product will be approximated using finite differences on *fprime*. *fhess_p* must compute the hessian times an arbitrary vector. If it is not given, finite-differences on *fprime* are used to compute it.

Newton-CG methods are also called truncated Newton methods. This function differs from `scipy.optimize.fmin_tnc` because

1. *scipy.optimize.fmin_ncg* is written purely in Python using NumPy and `scipy.optimize.fmin_tnc` calls a C function.
2. *scipy.optimize.fmin_ncg* is only for unconstrained minimization while `scipy.optimize.fmin_tnc` is for unconstrained minimization or box constrained minimization. (Box constraints give lower and upper bounds for each variable separately.)

References

Wright & Nocedal, 'Numerical Optimization', 1999, p. 140.

Constrained multivariate methods:

<code>fmin_l_bfgs_b</code> (<i>func</i> , <i>x0</i> [, <i>fprime</i> , <i>args</i> , ...])	Minimize a function <i>func</i> using the L-BFGS-B algorithm.
<code>fmin_tnc</code> (<i>func</i> , <i>x0</i> [, <i>fprime</i> , <i>args</i> , ...])	Minimize a function with variables subject to bounds, using gradient information in a truncated Newton algorithm.
<code>fmin_cobyla</code> (<i>func</i> , <i>x0</i> , <i>cons</i> [, <i>args</i> , ...])	Minimize a function using the Constrained Optimization By Linear Approximation (COBYLA) method.
<code>fmin_slsqp</code> (<i>func</i> , <i>x0</i> [, <i>eqcons</i> , <i>f_eqcons</i> , ...])	Minimize a function using Sequential Least Squares Programming

`scipy.optimize.fmin_l_bfgs_b`

`scipy.optimize.fmin_l_bfgs_b`(*func*, *x0*, *fprime*=None, *args*=(), *approx_grad*=0, *bounds*=None, *m*=10, *factr*=10000000.0, *pgtol*=1e-05, *epsilon*=1e-08, *iprint*=-1, *maxfun*=15000, *maxiter*=15000, *disp*=None, *callback*=None, *maxls*=20)

Minimize a function *func* using the L-BFGS-B algorithm.

Parameters

- func** [callable f(x,*args)] Function to minimize.
- x0** [ndarray] Initial guess.
- fprime** [callable fprime(x,*args), optional] The gradient of *func*. If None, then *func* returns the function value and the gradient ($f, g = func(x, *args)$), unless *approx_grad* is True in which case *func* returns only *f*.
- args** [sequence, optional] Arguments to pass to *func* and *fprime*.
- approx_grad** [bool, optional] Whether to approximate the gradient numerically (in which case *func* returns only the function value).
- bounds** [list, optional] (*min*, *max*) pairs for each element in *x*, defining the bounds on that parameter. Use None or $+\infty$ for one of *min* or *max* when there is no bound in that direction.
- m** [int, optional] The maximum number of variable metric corrections used to define the limited memory matrix. (The limited memory BFGS method does not store the full hessian but uses this many terms in an approximation to it.)

factr	[float, optional] The iteration stops when $(f^k - f^{k+1}) / \max\{ f^k , f^{k+1} , 1\} \leq \text{factr} * \text{eps}$, where <i>eps</i> is the machine precision, which is automatically generated by the code. Typical values for <i>factr</i> are: 1e12 for low accuracy; 1e7 for moderate accuracy; 10.0 for extremely high accuracy. See Notes for relationship to <i>ftol</i> , which is exposed (instead of <i>factr</i>) by the <code>scipy.optimize.minimize</code> interface to L-BFGS-B.
pgtol	[float, optional] The iteration will stop when $\max\{ \text{proj } g_i \mid i = 1, \dots, n\} \leq \text{pgtol}$ where <i>pg_i</i> is the <i>i</i> -th component of the projected gradient.
epsilon	[float, optional] Step size used when <i>approx_grad</i> is True, for numerically calculating the gradient
iprint	[int, optional] Controls the frequency of output. <i>iprint</i> < 0 means no output; <i>iprint</i> = 0 print only one line at the last iteration; 0 < <i>iprint</i> < 99 print also <i>f</i> and $ \text{proj } g $ every <i>iprint</i> iterations; <i>iprint</i> = 99 print details of every iteration except <i>n</i> -vectors; <i>iprint</i> = 100 print also the changes of active set and final <i>x</i> ; <i>iprint</i> > 100 print details of every iteration including <i>x</i> and <i>g</i> .
disp	[int, optional] If zero, then no output. If a positive number, then this over-rides <i>iprint</i> (i.e., <i>iprint</i> gets the value of <i>disp</i>).
maxfun	[int, optional] Maximum number of function evaluations.
maxiter	[int, optional] Maximum number of iterations.
callback	[callable, optional] Called after each iteration, as <code>callback(xk)</code> , where <i>xk</i> is the current parameter vector.
maxls	[int, optional] Maximum number of line search steps (per iteration). Default is 20.

Returns

x	[array_like] Estimated position of the minimum.
f	[float] Value of <i>func</i> at the minimum.
d	[dict] Information dictionary. <ul style="list-style-type: none"> • <code>d['warnflag']</code> is <ul style="list-style-type: none"> – 0 if converged, – 1 if too many function evaluations or too many iterations, – 2 if stopped for another reason, given in <code>d['task']</code> • <code>d['grad']</code> is the gradient at the minimum (should be 0 ish) • <code>d['funcalls']</code> is the number of function calls made. • <code>d['nit']</code> is the number of iterations.

See also:***minimize***

Interface to minimization algorithms for multivariate functions. See the ‘L-BFGS-B’ *method* in particular. Note that the *ftol* option is made available via that interface, while *factr* is provided via this interface, where *factr* is the factor multiplying the default machine floating-point precision to arrive at *ftol*: `ftol = factr * numpy.finfo(float).eps`.

Notes

License of L-BFGS-B (FORTRAN code):

The version included here (in fortran code) is 3.0 (released April 25, 2011). It was written by Ciyou Zhu, Richard Byrd, and Jorge Nocedal <nocedal@ece.nwu.edu>. It carries the following condition for use:

This software is freely available, but we expect that all publications describing work using this software, or all commercial products using it, quote at least one of the references given below. This software is released under the BSD License.

References

- R. H. Byrd, P. Lu and J. Nocedal. A Limited Memory Algorithm for Bound Constrained Optimization, (1995), SIAM Journal on Scientific and Statistical Computing, 16, 5, pp. 1190-1208.
- C. Zhu, R. H. Byrd and J. Nocedal. L-BFGS-B: Algorithm 778: L-BFGS-B, FORTRAN routines for large scale bound constrained optimization (1997), ACM Transactions on Mathematical Software, 23, 4, pp. 550 - 560.
- J.L. Morales and J. Nocedal. L-BFGS-B: Remark on Algorithm 778: L-BFGS-B, FORTRAN routines for large scale bound constrained optimization (2011), ACM Transactions on Mathematical Software, 38, 1.

scipy.optimize.fmin_tnc

`scipy.optimize.fmin_tnc` (*func*, *x0*, *fprime=None*, *args=()*, *approx_grad=0*, *bounds=None*, *epsilon=1e-08*, *scale=None*, *offset=None*, *messages=15*, *maxCGit=-1*, *maxfun=None*, *eta=-1*, *stepmx=0*, *accuracy=0*, *fmin=0*, *ftol=-1*, *xtol=-1*, *pgtol=-1*, *rescale=-1*, *disp=None*, *callback=None*)

Minimize a function with variables subject to bounds, using gradient information in a truncated Newton algorithm. This method wraps a C implementation of the algorithm.

Parameters

- func** [callable `func(x, *args)`] Function to minimize. Must do one of:
1. Return `f` and `g`, where `f` is the value of the function and `g` its gradient (a list of floats).
 2. Return the function value but supply gradient function separately as `fprime`.
 3. Return the function value and set `approx_grad=True`.
- If the function returns `None`, the minimization is aborted.
- x0** [array_like] Initial estimate of minimum.
- fprime** [callable `fprime(x, *args)`, optional] Gradient of `func`. If `None`, then either `func` must return the function value and the gradient (`f, g = func(x, *args)`) or `approx_grad` must be `True`.
- args** [tuple, optional] Arguments to pass to function.
- approx_grad** [bool, optional] If `true`, approximate the gradient numerically.
- bounds** [list, optional] (min, max) pairs for each element in `x0`, defining the bounds on that parameter. Use `None` or `+/-inf` for one of min or max when there is no bound in that direction.
- epsilon** [float, optional] Used if `approx_grad` is `True`. The stepsize in a finite difference approximation for `fprime`.
- scale** [array_like, optional] Scaling factors to apply to each variable. If `None`, the factors are `up` for interval bounded variables and `1+|x|` for the others. Defaults to `None`.
- offset** [array_like, optional] Value to subtract from each variable. If `None`, the offsets are `(up+low)/2` for interval bounded variables and `x` for the others.
- messages** [int, optional] Bit mask used to select messages display during minimization values defined in the `MSG` dict. Defaults to `MGS_ALL`.
- disp** [int, optional] Integer interface to messages. 0 = no message, 5 = all messages
- maxCGit** [int, optional] Maximum number of hessian*vector evaluations per main iteration. If `maxCGit == 0`, the direction chosen is -gradient if `maxCGit < 0`, `maxCGit` is set to `max(1, min(50, n/2))`. Defaults to -1.
- maxfun** [int, optional] Maximum number of function evaluation. If `None`, `maxfun` is set to `max(100, 10*len(x0))`. Defaults to `None`.
- eta** [float, optional] Severity of the line search. If `< 0` or `> 1`, set to 0.25. Defaults to -1.
- stepmx** [float, optional] Maximum step for the line search. May be increased during call. If too small, it will be set to 10.0. Defaults to 0.
- accuracy** [float, optional] Relative precision for finite difference calculations. If `<= machine_precision`, set to `sqrt(machine_precision)`. Defaults to 0.

fmin	[float, optional] Minimum function value estimate. Defaults to 0.
ftol	[float, optional] Precision goal for the value of f in the stopping criterion. If ftol < 0.0, ftol is set to 0.0 defaults to -1.
xtol	[float, optional] Precision goal for the value of x in the stopping criterion (after applying x scaling factors). If xtol < 0.0, xtol is set to sqrt(machine_precision). Defaults to -1.
pgtol	[float, optional] Precision goal for the value of the projected gradient in the stopping criterion (after applying x scaling factors). If pgtol < 0.0, pgtol is set to 1e-2 * sqrt(accuracy). Setting it to 0.0 is not recommended. Defaults to -1.
rescale	[float, optional] Scaling factor (in log10) used to trigger f value rescaling. If 0, rescale at each iteration. If a large value, never rescale. If < 0, rescale is set to 1.3.
callback	[callable, optional] Called after each iteration, as callback(xk), where xk is the current parameter vector.

Returns

x	[ndarray] The solution.
nfeval	[int] The number of function evaluations.
rc	[int] Return code, see below

See also:***minimize***

Interface to minimization algorithms for multivariate functions. See the “TNC” *method* in particular.

Notes

The underlying algorithm is truncated Newton, also called Newton Conjugate-Gradient. This method differs from `scipy.optimize.fmin_ncg` in that

1. it wraps a C implementation of the algorithm
2. it allows each variable to be given an upper and lower bound.

The algorithm incorporates the bound constraints by determining the descent direction as in an unconstrained truncated Newton, but never taking a step-size large enough to leave the space of feasible x’s. The algorithm keeps track of a set of currently active constraints, and ignores them when computing the minimum allowable step size. (The x’s associated with the active constraint are kept fixed.) If the maximum allowable step size is zero then a new constraint is added. At the end of each iteration one of the constraints may be deemed no longer active and removed. A constraint is considered no longer active is if it is currently active but the gradient for that variable points inward from the constraint. The specific constraint removed is the one associated with the variable of largest index whose constraint is no longer active.

Return codes are defined as follows:

```
-1 : Infeasible (lower bound > upper bound)
 0 : Local minimum reached (|pg| ~= 0)
 1 : Converged (|f_n-f_(n-1)| ~= 0)
 2 : Converged (|x_n-x_(n-1)| ~= 0)
 3 : Max. number of function evaluations reached
 4 : Linear search failed
 5 : All lower bounds are equal to the upper bounds
 6 : Unable to progress
 7 : User requested end of minimization
```

References

Wright S., Nocedal J. (2006), ‘Numerical Optimization’

Nash S.G. (1984), “Newton-Type Minimization Via the Lanczos Method”, SIAM Journal of Numerical Analysis 21, pp. 770-778

scipy.optimize.fmin_cobyla

`scipy.optimize.fmin_cobyla` (*func*, *x0*, *cons*, *args=()*, *consargs=None*, *rhobeg=1.0*, *rhoend=0.0001*, *maxfun=1000*, *disp=None*, *catol=0.0002*)

Minimize a function using the Constrained Optimization By Linear Approximation (COBYLA) method. This method wraps a FORTRAN implementation of the algorithm.

Parameters

func	[callable] Function to minimize. In the form <code>func(x, *args)</code> .
x0	[ndarray] Initial guess.
cons	[sequence] Constraint functions; must all be ≥ 0 (a single function if only 1 constraint). Each function takes the parameters <i>x</i> as its first argument, and it can return either a single number or an array or list of numbers.
args	[tuple, optional] Extra arguments to pass to function.
consargs	[tuple, optional] Extra arguments to pass to constraint functions (default of <code>None</code> means use same extra arguments as those passed to <code>func</code>). Use <code>()</code> for no extra arguments.
rhobeg	[float, optional] Reasonable initial changes to the variables.
rhoend	[float, optional] Final accuracy in the optimization (not precisely guaranteed). This is a lower bound on the size of the trust region.
disp	[{0, 1, 2, 3}, optional] Controls the frequency of output; 0 implies no output.
maxfun	[int, optional] Maximum number of function evaluations.
catol	[float, optional] Absolute tolerance for constraint violations.

Returns

x [ndarray] The argument that minimises *f*.

See also:

`minimize`

Interface to minimization algorithms for multivariate functions. See the ‘COBYLA’ *method* in particular.

Notes

This algorithm is based on linear approximations to the objective function and each constraint. We briefly describe the algorithm.

Suppose the function is being minimized over *k* variables. At the *j*th iteration the algorithm has *k*+1 points $v_1, \dots, v_{(k+1)}$, an approximate solution x_j , and a radius RHO_j . (i.e., linear plus a constant) approximations to the objective function and constraint functions such that their function values agree with the linear approximation on the *k*+1 points $v_1, \dots, v_{(k+1)}$. This gives a linear program to solve (where the linear approximations of the constraint functions are constrained to be non-negative).

However, the linear approximations are likely only good approximations near the current simplex, so the linear program is given the further requirement that the solution, which will become $x_{(j+1)}$, must be within RHO_j from x_j . RHO_j only decreases, never increases. The initial RHO_j is *rhobeg* and the final RHO_j is *rhoend*. In this way COBYLA’s iterations behave like a trust region algorithm.

Additionally, the linear program may be inconsistent, or the approximation may give poor improvement. For details about how these issues are resolved, as well as how the points v_i are updated, refer to the source code or the references below.

References

Powell M.J.D. (1994), “A direct search optimization method that models the objective and constraint functions by linear interpolation.”, in *Advances in Optimization and Numerical Analysis*, eds. S. Gomez and J-P Hennart, Kluwer Academic (Dordrecht), pp. 51-67

Powell M.J.D. (1998), “Direct search algorithms for optimization calculations”, *Acta Numerica* 7, 287-336

Powell M.J.D. (2007), “A view of algorithms for optimization without derivatives”, Cambridge University Technical Report DAMTP 2007/NA03

Examples

Minimize the objective function $f(x,y) = x*y$ subject to the constraints $x**2 + y**2 < 1$ and $y > 0$:

```
>>> def objective(x):
...     return x[0]*x[1]
...
>>> def constr1(x):
...     return 1 - (x[0]**2 + x[1]**2)
...
>>> def constr2(x):
...     return x[1]
...
>>> from scipy.optimize import fmin_cobyla
>>> fmin_cobyla(objective, [0.0, 0.1], [constr1, constr2], rhoend=1e-7)
array([-0.70710685,  0.70710671])
```

The exact solution is $(-\sqrt{2}/2, \sqrt{2}/2)$.

scipy.optimize.fmin_slsqp

`scipy.optimize.fmin_slsqp` (*func*, *x0*, *eqcons*=(), *f_eqcons*=None, *ieqcons*=(), *f_ieqcons*=None, *bounds*=(), *fprime*=None, *fprime_eqcons*=None, *fprime_ieqcons*=None, *args*=(), *iter*=100, *acc*=1e-06, *iprint*=1, *disp*=None, *full_output*=0, *epsilon*=1.4901161193847656e-08, *callback*=None)

Minimize a function using Sequential Least Squares Programming

Python interface function for the SLSQP Optimization subroutine originally implemented by Dieter Kraft.

Parameters

func	[callable $f(x,*args)$] Objective function. Must return a scalar.
x0	[1-D ndarray of float] Initial guess for the independent variable(s).
eqcons	[list, optional] A list of functions of length n such that $eqcons[j](x,*args) == 0.0$ in a successfully optimized problem.
f_eqcons	[callable $f(x,*args)$, optional] Returns a 1-D array in which each element must equal 0.0 in a successfully optimized problem. If <code>f_eqcons</code> is specified, <code>eqcons</code> is ignored.
ieqcons	[list, optional] A list of functions of length n such that $ieqcons[j](x,*args) >= 0.0$ in a successfully optimized problem.

- f_ieqcons** [callable $f(x, *args)$, optional] Returns a 1-D ndarray in which each element must be greater or equal to 0.0 in a successfully optimized problem. If `f_ieqcons` is specified, `ieqcons` is ignored.
- bounds** [list, optional] A list of tuples specifying the lower and upper bound for each independent variable [(x10, xu0), (x11, xu1), ...] Infinite values will be interpreted as large floating values.
- fprime** [callable $f(x, *args)$, optional] A function that evaluates the partial derivatives of `func`.
- fprime_eqcons** [callable $f(x, *args)$, optional] A function of the form $f(x, *args)$ that returns the m by n array of equality constraint normals. If not provided, the normals will be approximated. The array returned by `fprime_eqcons` should be sized as (`len(eqcons)`, `len(x0)`).
- fprime_ineqcons** [callable $f(x, *args)$, optional] A function of the form $f(x, *args)$ that returns the m by n array of inequality constraint normals. If not provided, the normals will be approximated. The array returned by `fprime_ineqcons` should be sized as (`len(ieqcons)`, `len(x0)`).
- args** [sequence, optional] Additional arguments passed to `func` and `fprime`.
- iter** [int, optional] The maximum number of iterations.
- acc** [float, optional] Requested accuracy.
- iprint** [int, optional] The verbosity of `fmin_slsqp` :
- `iprint <= 0` : Silent operation
 - `iprint == 1` : Print summary upon completion (default)
 - `iprint >= 2` : Print status of each iterate and summary
- disp** [int, optional] Overrides the `iprint` interface (preferred).
- full_output** [bool, optional] If `False`, return only the minimizer of `func` (default). Otherwise, output final objective function and summary information.
- epsilon** [float, optional] The step size for finite-difference derivative estimates.
- callback** [callable, optional] Called after each iteration, as `callback(x)`, where `x` is the current parameter vector.

Returns

- out** [ndarray of float] The final minimizer of `func`.
- fx** [ndarray of float, if `full_output` is `true`] The final value of the objective function.
- its** [int, if `full_output` is `true`] The number of iterations.
- imode** [int, if `full_output` is `true`] The exit mode from the optimizer (see below).
- smode** [string, if `full_output` is `true`] Message describing the exit mode from the optimizer.

See also:

minimize

Interface to minimization algorithms for multivariate functions. See the ‘SLSQP’ *method* in particular.

Notes

Exit modes are defined as follows

```

-1 : Gradient evaluation required (g & a)
0  : Optimization terminated successfully
1  : Function evaluation required (f & c)
2  : More equality constraints than independent variables
3  : More than 3*n iterations in LSQ subproblem
4  : Inequality constraints incompatible
5  : Singular matrix E in LSQ subproblem
6  : Singular matrix C in LSQ subproblem
```

(continues on next page)

(continued from previous page)

```

7 : Rank-deficient equality constraint subproblem HFTI
8 : Positive directional derivative for linesearch
9 : Iteration limit reached

```

Examples

Examples are given *in the tutorial*.

Univariate (scalar) minimization methods:

<code>fminbound</code> (func, x1, x2[, args, xtol, ...])	Bounded minimization for scalar functions.
<code>brent</code> (func[, args, brack, tol, full_output, ...])	Given a function of one variable and a possible bracket, return the local minimum of the function isolated to a fractional precision of tol.
<code>golden</code> (func[, args, brack, tol, ...])	Return the minimum of a function of one variable using golden section method.

scipy.optimize.fminbound

`scipy.optimize.fminbound` (func, x1, x2, args=(), xtol=1e-05, maxfun=500, full_output=0, disp=1)

Bounded minimization for scalar functions.

Parameters

func [callable f(x,*args)] Objective function to be minimized (must accept and return scalars).
x1, x2 [float or array scalar] The optimization bounds.
args [tuple, optional] Extra arguments passed to function.
xtol [float, optional] The convergence tolerance.
maxfun [int, optional] Maximum number of function evaluations allowed.
full_output [bool, optional] If True, return optional outputs.
disp [int, optional]
If non-zero, print messages.
 0 : no message printing. 1 : non-convergence notification messages only. 2 : print a message on convergence too. 3 : print iteration results.

Returns

xopt [ndarray] Parameters (over given interval) which minimize the objective function.
fval [number] The function value at the minimum point.
ierr [int] An error flag (0 if converged, 1 if maximum number of function calls reached).
numfunc [int] The number of function calls made.

See also:

`minimize_scalar`

Interface to minimization algorithms for scalar univariate functions. See the 'Bounded' *method* in particular.

Notes

Finds a local minimizer of the scalar function *func* in the interval $x_1 < x_{opt} < x_2$ using Brent's method. (See *brent* for auto-bracketing.)

Examples

fminbound finds the minimum of the function in the given range. The following examples illustrate the same

```
>>> def f(x):
...     return x**2
```

```
>>> from scipy import optimize
```

```
>>> minimum = optimize.fminbound(f, -1, 2)
>>> minimum
0.0
>>> minimum = optimize.fminbound(f, 1, 2)
>>> minimum
1.0000059608609866
```

scipy.optimize.brent

`scipy.optimize.brent` (*func*, *args*=(), *brack*=None, *tol*=1.48e-08, *full_output*=0, *maxiter*=500)

Given a function of one variable and a possible bracket, return the local minimum of the function isolated to a fractional precision of *tol*.

Parameters

func	[callable f(x,*args)] Objective function.
args	[tuple, optional] Additional arguments (if present).
brack	[tuple, optional] Either a triple (xa,xb,xc) where $x_a < x_b < x_c$ and $\text{func}(x_b) < \text{func}(x_a)$, $\text{func}(x_c)$ or a pair (xa,xb) which are used as a starting interval for a downhill bracket search (see <i>bracket</i>). Providing the pair (xa,xb) does not always mean the obtained solution will satisfy $x_a \leq x \leq x_b$.
tol	[float, optional] Stop if between iteration change is less than <i>tol</i> .
full_output	[bool, optional] If True, return all output args (xmin, fval, iter, funcalls).
maxiter	[int, optional] Maximum number of iterations in solution.

Returns

xmin	[ndarray] Optimum point.
fval	[float] Optimum value.
iter	[int] Number of iterations.
funcalls	[int] Number of objective function evaluations made.

See also:

minimize_scalar

Interface to minimization algorithms for scalar univariate functions. See the 'Brent' *method* in particular.

Notes

Uses inverse parabolic interpolation when possible to speed up convergence of golden section method.

Does not ensure that the minimum lies in the range specified by *brack*. See *fminbound*.

Examples

We illustrate the behaviour of the function when *brack* is of size 2 and 3 respectively. In the case where *brack* is of the form (xa,xb), we can see for the given values, the output need not necessarily lie in the range (xa,xb).

```
>>> def f(x):
...     return x**2
```

```
>>> from scipy import optimize
```

```
>>> minimum = optimize.brent(f, brack=(1, 2))
>>> minimum
0.0
>>> minimum = optimize.brent(f, brack=(-1, 0.5, 2))
>>> minimum
-2.7755575615628914e-17
```

scipy.optimize.golden

`scipy.optimize.golden` (*func*, *args*=(), *brack*=None, *tol*=1.4901161193847656e-08, *full_output*=0, *maxiter*=5000)

Return the minimum of a function of one variable using golden section method.

Given a function of one variable and a possible bracketing interval, return the minimum of the function isolated to a fractional precision of *tol*.

Parameters

func	[callable func(x,*args)] Objective function to minimize.
args	[tuple, optional] Additional arguments (if present), passed to func.
brack	[tuple, optional] Triple (a,b,c), where (a<b<c) and func(b) < func(a),func(c). If bracket consists of two numbers (a, c), then they are assumed to be a starting interval for a downhill bracket search (see <i>bracket</i>); it doesn't always mean that obtained solution will satisfy a<=x<=c.
tol	[float, optional] x tolerance stop criterion
full_output	[bool, optional] If True, return optional outputs.
maxiter	[int] Maximum number of iterations to perform.

See also:

minimize_scalar

Interface to minimization algorithms for scalar univariate functions. See the 'Golden' *method* in particular.

Notes

Uses analog of bisection method to decrease the bracketed interval.

Examples

We illustrate the behaviour of the function when *brack* is of size 2 and 3, respectively. In the case where *brack* is of the form (xa,xb), we can see for the given values, the output need not necessarily lie in the range (xa, xb).

```
>>> def f(x):  
...     return x**2
```

```
>>> from scipy import optimize
```

```
>>> minimum = optimize.golden(f, brack=(1, 2))  
>>> minimum  
1.5717277788484873e-162  
>>> minimum = optimize.golden(f, brack=(-1, 0.5, 2))  
>>> minimum  
-1.5717277788484873e-162
```

Least-squares

<code>leastsq(func, x0[, args, Dfun, full_output, ...])</code>	Minimize the sum of squares of a set of equations.
--	--

scipy.optimize.leastsq

`scipy.optimize.leastsq` (*func*, *x0*, *args=()*, *Dfun=None*, *full_output=0*, *col_deriv=0*, *ftol=1.49012e-08*, *xtol=1.49012e-08*, *gtol=0.0*, *maxfev=0*, *epsfcn=None*, *factor=100*, *diag=None*)

Minimize the sum of squares of a set of equations.

```
x = arg min(sum(func(y)**2, axis=0))  
      y
```

Parameters

- | | |
|--------------------|--|
| func | [callable] Should take at least one (possibly length N vector) argument and returns M floating point numbers. It must not return NaNs or fitting might fail. |
| x0 | [ndarray] The starting estimate for the minimization. |
| args | [tuple, optional] Any extra arguments to func are placed in this tuple. |
| Dfun | [callable, optional] A function or method to compute the Jacobian of func with derivatives across the rows. If this is None, the Jacobian will be estimated. |
| full_output | [bool, optional] non-zero to return all optional outputs. |
| col_deriv | [bool, optional] non-zero to specify that the Jacobian function computes derivatives down the columns (faster, because there is no transpose operation). |
| ftol | [float, optional] Relative error desired in the sum of squares. |
| xtol | [float, optional] Relative error desired in the approximate solution. |
| gtol | [float, optional] Orthogonality desired between the function vector and the columns of the Jacobian. |

maxfev	[int, optional] The maximum number of calls to the function. If <i>Dfun</i> is provided, then the default <i>maxfev</i> is $100*(N+1)$ where <i>N</i> is the number of elements in <i>x0</i> , otherwise the default <i>maxfev</i> is $200*(N+1)$.
epsfcn	[float, optional] A variable used in determining a suitable step length for the forward-difference approximation of the Jacobian (for <i>Dfun</i> =None). Normally the actual step length will be $\sqrt{\text{epsfcn}}*x$. If <i>epsfcn</i> is less than the machine precision, it is assumed that the relative errors are of the order of the machine precision.
factor	[float, optional] A parameter determining the initial step bound ($\text{factor} * \text{diag} * x $). Should be in interval $(0.1, 100)$.
diag	[sequence, optional] <i>N</i> positive entries that serve as a scale factors for the variables.

Returns

x	[ndarray] The solution (or the result of the last iteration for an unsuccessful call).										
cov_x	[ndarray] The inverse of the Hessian. <i>fjac</i> and <i>ipvt</i> are used to construct an estimate of the Hessian. A value of None indicates a singular matrix, which means the curvature in parameters <i>x</i> is numerically flat. To obtain the covariance matrix of the parameters <i>x</i> , <i>cov_x</i> must be multiplied by the variance of the residuals – see <i>curve_fit</i> .										
infodict	[dict] a dictionary of optional outputs with the keys: <table> <tr> <td>nfev</td> <td>The number of function calls</td> </tr> <tr> <td>fvec</td> <td>The function evaluated at the output</td> </tr> <tr> <td>fjac</td> <td>A permutation of the R matrix of a QR factorization of the final approximate Jacobian matrix, stored column wise. Together with <i>ipvt</i>, the covariance of the estimate can be approximated.</td> </tr> <tr> <td>ipvt</td> <td>An integer array of length <i>N</i> which defines a permutation matrix, <i>p</i>, such that $\text{fjac} * p = q * r$, where <i>r</i> is upper triangular with diagonal elements of nonincreasing magnitude. Column <i>j</i> of <i>p</i> is column <i>ipvt</i>(<i>j</i>) of the identity matrix.</td> </tr> <tr> <td>qtqf</td> <td>The vector $(\text{transpose}(q) * \text{fvec})$.</td> </tr> </table>	nfev	The number of function calls	fvec	The function evaluated at the output	fjac	A permutation of the R matrix of a QR factorization of the final approximate Jacobian matrix, stored column wise. Together with <i>ipvt</i> , the covariance of the estimate can be approximated.	ipvt	An integer array of length <i>N</i> which defines a permutation matrix, <i>p</i> , such that $\text{fjac} * p = q * r$, where <i>r</i> is upper triangular with diagonal elements of nonincreasing magnitude. Column <i>j</i> of <i>p</i> is column <i>ipvt</i> (<i>j</i>) of the identity matrix.	qtqf	The vector $(\text{transpose}(q) * \text{fvec})$.
nfev	The number of function calls										
fvec	The function evaluated at the output										
fjac	A permutation of the R matrix of a QR factorization of the final approximate Jacobian matrix, stored column wise. Together with <i>ipvt</i> , the covariance of the estimate can be approximated.										
ipvt	An integer array of length <i>N</i> which defines a permutation matrix, <i>p</i> , such that $\text{fjac} * p = q * r$, where <i>r</i> is upper triangular with diagonal elements of nonincreasing magnitude. Column <i>j</i> of <i>p</i> is column <i>ipvt</i> (<i>j</i>) of the identity matrix.										
qtqf	The vector $(\text{transpose}(q) * \text{fvec})$.										
mesg	[str] A string message giving information about the cause of failure.										
ier	[int] An integer flag. If it is equal to 1, 2, 3 or 4, the solution was found. Otherwise, the solution was not found. In either case, the optional output variable ‘mesg’ gives more information.										

See also:[*least_squares*](#)

Newer interface to solve nonlinear least-squares problems with bounds on the variables. See `method='lm'` in particular.

Notes

“leastsq” is a wrapper around MINPACK’s *lmdif* and *lmdqr* algorithms.

cov_x is a Jacobian approximation to the Hessian of the least squares objective function. This approximation assumes that the objective function is based on the difference between some observed target data (*ydata*) and a (non-linear) function of the parameters $f(xdata, params)$

```
func(params) = ydata - f(xdata, params)
```

so that the objective function is

```
min sum((ydata - f(xdata, params))**2, axis=0)
params
```

The solution, *x*, is always a 1-D array, regardless of the shape of *x0*, or whether *x0* is a scalar.

Examples

```
>>> from scipy.optimize import leastsq
>>> def func(x):
...     return 2*(x-3)**2+1
>>> leastsq(func, 0)
(array([2.99999999]), 1)
```

Root finding

General nonlinear solvers:

<code>fsolve(func, x0[, args, fprime, ...])</code>	Find the roots of a function.
<code>broyden1(F, xin[, iter, alpha, ...])</code>	Find a root of a function, using Broyden's first Jacobian approximation.
<code>broyden2(F, xin[, iter, alpha, ...])</code>	Find a root of a function, using Broyden's second Jacobian approximation.

scipy.optimize.fsolve

`scipy.optimize.fsolve` (*func*, *x0*, *args*=(), *fprime*=None, *full_output*=0, *col_deriv*=0, *xtol*=1.49012e-08, *maxfev*=0, *band*=None, *epsfcn*=None, *factor*=100, *diag*=None)

Find the roots of a function.

Return the roots of the (non-linear) equations defined by $\text{func}(x) = 0$ given a starting estimate.

Parameters

func	[callable $f(x, *args)$] A function that takes at least one (possibly vector) argument, and returns a value of the same length.
x0	[ndarray] The starting estimate for the roots of $\text{func}(x) = 0$.
args	[tuple, optional] Any extra arguments to <i>func</i> .
fprime	[callable $f(x, *args)$, optional] A function to compute the Jacobian of <i>func</i> with derivatives across the rows. By default, the Jacobian will be estimated.
full_output	[bool, optional] If True, return optional outputs.
col_deriv	[bool, optional] Specify whether the Jacobian function computes derivatives down the columns (faster, because there is no transpose operation).
xtol	[float, optional] The calculation will terminate if the relative error between two consecutive iterates is at most <i>xtol</i> .
maxfev	[int, optional] The maximum number of calls to the function. If zero, then $100 * (N+1)$ is the maximum where <i>N</i> is the number of elements in <i>x0</i> .
band	[tuple, optional] If set to a two-sequence containing the number of sub- and super-diagonals within the band of the Jacobi matrix, the Jacobi matrix is considered banded (only for <i>fprime</i> =None).
epsfcn	[float, optional] A suitable step length for the forward-difference approximation of the Jacobian (for <i>fprime</i> =None). If <i>epsfcn</i> is less than the machine precision, it is assumed that the relative errors in the functions are of the order of the machine precision.
factor	[float, optional] A parameter determining the initial step bound ($\text{factor} * \text{diag} * x $). Should be in the interval (0.1, 100).
diag	[sequence, optional] <i>N</i> positive entries that serve as a scale factors for the variables.

Returns

x	[ndarray] The solution (or the result of the last iteration for an unsuccessful call).
----------	--

infodict	[dict] A dictionary of optional outputs with the keys: nfev number of function calls njev number of Jacobian calls fvec function evaluated at the output fjac the orthogonal matrix, q , produced by the QR factorization of the final approximate Jacobian matrix, stored column wise r upper triangular matrix produced by QR factorization of the same matrix qtf the vector $(\text{transpose}(q) * \text{fvec})$
ier	[int] An integer flag. Set to 1 if a solution was found, otherwise refer to <i>mesg</i> for more information.
mesg	[str] If no solution is found, <i>mesg</i> details the cause of failure.

See also:

[*root*](#)

Interface to root finding algorithms for multivariate functions. See the `method='hybr'` in particular.

Notes

`fsolve` is a wrapper around MINPACK's `hybrd` and `hybrj` algorithms.

Examples

Find a solution to the system of equations: $x_0 \cdot \cos(x_1) = 4$, $x_1 \cdot x_0 - x_1 = 5$.

```
>>> from scipy.optimize import fsolve
>>> def func(x):
...     return [x[0] * np.cos(x[1]) - 4,
...             x[1] * x[0] - x[1] - 5]
>>> root = fsolve(func, [1, 1])
>>> root
array([6.50409711, 0.90841421])
>>> np.isclose(func(root), [0.0, 0.0]) # func(root) should be almost 0.0.
array([ True,  True])
```

scipy.optimize.broyden1

`scipy.optimize.broyden1` (*F*, *xin*, *iter=None*, *alpha=None*, *reduction_method='restart'*, *max_rank=None*, *verbose=False*, *maxiter=None*, *f_tol=None*, *f_rtol=None*, *x_tol=None*, *x_rtol=None*, *tol_norm=None*, *line_search='armijo'*, *callback=None*, ***kw*)

Find a root of a function, using Broyden's first Jacobian approximation.

This method is also known as "Broyden's good method".

Parameters

F	[function(x) -> f] Function whose root to find; should take and return an array-like object.
xin	[array_like] Initial guess for the solution
alpha	[float, optional] Initial guess for the Jacobian is $(-1/\text{alpha})$.
reduction_method	[str or tuple, optional] Method used in ensuring that the rank of the Broyden matrix stays low. Can either be a string giving the name of the method, or a tuple of the form $(\text{method}, \text{param1}, \text{param2}, \dots)$ that gives the name of the method and values for additional parameters.

Methods available:

- `restart`: drop all matrix columns. Has no extra parameters.
- `simple`: drop oldest matrix column. Has no extra parameters.
- `svd`: keep only the most significant SVD components. Takes an extra parameter, `to_retain`, which determines the number of SVD components to retain when rank reduction is done. Default is `max_rank - 2`.

max_rank	[int, optional] Maximum rank for the Broyden matrix. Default is infinity (i.e., no rank reduction).
iter	[int, optional] Number of iterations to make. If omitted (default), make as many as required to meet tolerances.
verbose	[bool, optional] Print status to stdout on every iteration.
maxiter	[int, optional] Maximum number of iterations to make. If more are needed to meet convergence, <i>NoConvergence</i> is raised.
f_tol	[float, optional] Absolute tolerance (in max-norm) for the residual. If omitted, default is 6e-6.
f_rtol	[float, optional] Relative tolerance for the residual. If omitted, not used.
x_tol	[float, optional] Absolute minimum step size, as determined from the Jacobian approximation. If the step size is smaller than this, optimization is terminated as successful. If omitted, not used.
x_rtol	[float, optional] Relative minimum step size. If omitted, not used.
tol_norm	[function(vector) -> scalar, optional] Norm to use in convergence check. Default is the maximum norm.
line_search	[{None, 'armijo' (default), 'wolfe'}, optional] Which type of a line search to use to determine the step size in the direction given by the Jacobian approximation. Defaults to 'armijo'.
callback	[function, optional] Optional callback function. It is called on every iteration as <code>callback(x, f)</code> where x is the current solution and f the corresponding residual.

Returns

sol [ndarray] An array (of similar array type as x_0) containing the final solution.

Raises

NoConvergence

When a solution was not found.

See also:

root

Interface to root finding algorithms for multivariate functions. See `method='broyden1'` in particular.

Notes

This algorithm implements the inverse Jacobian Quasi-Newton update

$$H_+ = H + (dx - Hdf)dx^\dagger H / (dx^\dagger Hdf)$$

which corresponds to Broyden's first Jacobian update

$$J_+ = J + (df - Jdx)dx^\dagger / dx^\dagger dx$$

References

[1]

Examples

The following functions define a system of nonlinear equations

```
>>> def fun(x):
...     return [x[0] + 0.5 * (x[0] - x[1])**3 - 1.0,
...            0.5 * (x[1] - x[0])**3 + x[1]]
```

A solution can be obtained as follows.

```
>>> from scipy import optimize
>>> sol = optimize.broyden1(fun, [0, 0])
>>> sol
array([0.84116396, 0.15883641])
```

scipy.optimize.broyden2

`scipy.optimize.broyden2` (*F*, *xin*, *iter=None*, *alpha=None*, *reduction_method='restart'*, *max_rank=None*, *verbose=False*, *maxiter=None*, *f_tol=None*, *f_rtol=None*, *x_tol=None*, *x_rtol=None*, *tol_norm=None*, *line_search='armijo'*, *callback=None*, ***kw*)

Find a root of a function, using Broyden's second Jacobian approximation.

This method is also known as "Broyden's bad method".

Parameters

F	[function(x) -> f] Function whose root to find; should take and return an array-like object.
xin	[array_like] Initial guess for the solution
alpha	[float, optional] Initial guess for the Jacobian is $(-1/\alpha)$.
reduction_method	[str or tuple, optional] Method used in ensuring that the rank of the Broyden matrix stays low. Can either be a string giving the name of the method, or a tuple of the form (method, param1, param2, ...) that gives the name of the method and values for additional parameters. Methods available: <ul style="list-style-type: none"> • <code>restart</code>: drop all matrix columns. Has no extra parameters. • <code>simple</code>: drop oldest matrix column. Has no extra parameters. • <code>svd</code>: keep only the most significant SVD components. Takes an extra parameter, <code>to_retain</code>, which determines the number of SVD components to retain when rank reduction is done. Default is <code>max_rank - 2</code>.
max_rank	[int, optional] Maximum rank for the Broyden matrix. Default is infinity (i.e., no rank reduction).
iter	[int, optional] Number of iterations to make. If omitted (default), make as many as required to meet tolerances.
verbose	[bool, optional] Print status to stdout on every iteration.
maxiter	[int, optional] Maximum number of iterations to make. If more are needed to meet convergence, <i>NoConvergence</i> is raised.
f_tol	[float, optional] Absolute tolerance (in max-norm) for the residual. If omitted, default is 6e-6.
f_rtol	[float, optional] Relative tolerance for the residual. If omitted, not used.

- x_tol** [float, optional] Absolute minimum step size, as determined from the Jacobian approximation. If the step size is smaller than this, optimization is terminated as successful. If omitted, not used.
- x_rtol** [float, optional] Relative minimum step size. If omitted, not used.
- tol_norm** [function(vector) -> scalar, optional] Norm to use in convergence check. Default is the maximum norm.
- line_search** [{None, 'armijo' (default), 'wolfe'}, optional] Which type of a line search to use to determine the step size in the direction given by the Jacobian approximation. Defaults to 'armijo'.
- callback** [function, optional] Optional callback function. It is called on every iteration as `callback(x, f)` where x is the current solution and f the corresponding residual.

Returns

- sol** [ndarray] An array (of similar array type as x_0) containing the final solution.

Raises

- NoConvergence**
When a solution was not found.

See also:

[root](#)

Interface to root finding algorithms for multivariate functions. See `method='broyden2'` in particular.

Notes

This algorithm implements the inverse Jacobian Quasi-Newton update

$$H_+ = H + (dx - Hdf)df^\dagger / (df^\dagger df)$$

corresponding to Broyden's second method.

References

[1]

Examples

The following functions define a system of nonlinear equations

```
>>> def fun(x):
...     return [x[0] + 0.5 * (x[0] - x[1])**3 - 1.0,
...            0.5 * (x[1] - x[0])**3 + x[1]]
```

A solution can be obtained as follows.

```
>>> from scipy import optimize
>>> sol = optimize.broyden2(fun, [0, 0])
>>> sol
array([0.84116365, 0.15883529])
```

Large-scale nonlinear solvers:

<code>newton_krylov(F, xin[, iter, rdiff, method, ...])</code>	Find a root of a function, using Krylov approximation for inverse Jacobian.
<code>anderson(F, xin[, iter, alpha, w0, M, ...])</code>	Find a root of a function, using (extended) Anderson mixing.

scipy.optimize.newton_krylov

`scipy.optimize.newton_krylov(F, xin, iter=None, rdiff=None, method='lgmres', inner_maxiter=20, inner_M=None, outer_k=10, verbose=False, maxiter=None, f_tol=None, f_rtol=None, x_tol=None, x_rtol=None, tol_norm=None, line_search='armijo', callback=None, **kw)`

Find a root of a function, using Krylov approximation for inverse Jacobian.

This method is suitable for solving large-scale problems.

Parameters

F	[function(x) -> f] Function whose root to find; should take and return an array-like object.
xin	[array_like] Initial guess for the solution
rdiff	[float, optional] Relative step size to use in numerical differentiation.
method	[{'lgmres', 'gmres', 'bicgstab', 'cgs', 'minres'} or function] Krylov method to use to approximate the Jacobian. Can be a string, or a function implementing the same interface as the iterative solvers in <code>scipy.sparse.linalg</code> . The default is <code>scipy.sparse.linalg.lgmres</code> .
inner_maxiter	[int, optional] Parameter to pass to the “inner” Krylov solver: maximum number of iterations. Iteration will stop after maxiter steps even if the specified tolerance has not been achieved.
inner_M	[LinearOperator or InverseJacobian] Preconditioner for the inner Krylov iteration. Note that you can use also inverse Jacobians as (adaptive) preconditioners. For example,
	<pre> >>> from scipy.optimize.nonlin import BroydenFirst, ↵ ↵KrylovJacobian >>> from scipy.optimize.nonlin import InverseJacobian >>> jac = BroydenFirst() >>> kjac = KrylovJacobian(inner_M=InverseJacobian(jac)) </pre>
	If the preconditioner has a method named ‘update’, it will be called as <code>update(x, f)</code> after each nonlinear step, with <code>x</code> giving the current point, and <code>f</code> the current function value.
outer_k	[int, optional] Size of the subspace kept across LGMRES nonlinear iterations. See <code>scipy.sparse.linalg.lgmres</code> for details.
inner_kwargs	[kwargs] Keyword parameters for the “inner” Krylov solver (defined with <code>method</code>). Parameter names must start with the <code>inner_</code> prefix which will be stripped before passing on the inner method. See, e.g., <code>scipy.sparse.linalg.gmres</code> for details.
iter	[int, optional] Number of iterations to make. If omitted (default), make as many as required to meet tolerances.
verbose	[bool, optional] Print status to stdout on every iteration.
maxiter	[int, optional] Maximum number of iterations to make. If more are needed to meet convergence, <code>NoConvergence</code> is raised.
f_tol	[float, optional] Absolute tolerance (in max-norm) for the residual. If omitted, default is 6e-6.
f_rtol	[float, optional] Relative tolerance for the residual. If omitted, not used.
x_tol	[float, optional] Absolute minimum step size, as determined from the Jacobian approximation. If the step size is smaller than this, optimization is terminated as successful. If omitted, not used.
x_rtol	[float, optional] Relative minimum step size. If omitted, not used.

tol_norm [function(vector) -> scalar, optional] Norm to use in convergence check. Default is the maximum norm.

line_search [{None, 'armijo' (default), 'wolfe'}, optional] Which type of a line search to use to determine the step size in the direction given by the Jacobian approximation. Defaults to 'armijo'.

callback [function, optional] Optional callback function. It is called on every iteration as `callback(x, f)` where x is the current solution and f the corresponding residual.

Returns

sol [ndarray] An array (of similar array type as x_0) containing the final solution.

Raises

NoConvergence

When a solution was not found.

See also:

root

Interface to root finding algorithms for multivariate functions. See `method='krylov'` in particular.

scipy.sparse.linalg.gmres

scipy.sparse.linalg.lgmres

Notes

This function implements a Newton-Krylov solver. The basic idea is to compute the inverse of the Jacobian with an iterative Krylov method. These methods require only evaluating the Jacobian-vector products, which are conveniently approximated by a finite difference:

$$Jv \approx (f(x + \omega * v/|v|) - f(x))/\omega$$

Due to the use of iterative matrix inverses, these methods can deal with large nonlinear problems.

SciPy's *scipy.sparse.linalg* module offers a selection of Krylov solvers to choose from. The default here is *lgmres*, which is a variant of restarted GMRES iteration that reuses some of the information obtained in the previous Newton steps to invert Jacobians in subsequent steps.

For a review on Newton-Krylov methods, see for example [1], and for the LGMRES sparse inverse method, see [2].

References

[1], [2]

Examples

The following functions define a system of nonlinear equations

```
>>> def fun(x):
...     return [x[0] + 0.5 * x[1] - 1.0,
...            0.5 * (x[1] - x[0]) ** 2]
```

A solution can be obtained as follows.

```
>>> from scipy import optimize
>>> sol = optimize.newton_krylov(fun, [0, 0])
>>> sol
array([0.66731771, 0.66536458])
```

scipy.optimize.anderson

`scipy.optimize.anderson`(*F*, *xin*, *iter=None*, *alpha=None*, *w0=0.01*, *M=5*, *verbose=False*, *maxiter=None*, *f_tol=None*, *f_rtol=None*, *x_tol=None*, *x_rtol=None*, *tol_norm=None*, *line_search='armijo'*, *callback=None*, ***kw*)

Find a root of a function, using (extended) Anderson mixing.

The Jacobian is formed by for a ‘best’ solution in the space spanned by last *M* vectors. As a result, only a *MxM* matrix inversions and *MxN* multiplications are required. [Ey]

Parameters

F	[function(x) -> f] Function whose root to find; should take and return an array-like object.
xin	[array_like] Initial guess for the solution
alpha	[float, optional] Initial guess for the Jacobian is (-1/alpha).
M	[float, optional] Number of previous vectors to retain. Defaults to 5.
w0	[float, optional] Regularization parameter for numerical stability. Compared to unity, good values of the order of 0.01.
iter	[int, optional] Number of iterations to make. If omitted (default), make as many as required to meet tolerances.
verbose	[bool, optional] Print status to stdout on every iteration.
maxiter	[int, optional] Maximum number of iterations to make. If more are needed to meet convergence, <i>NoConvergence</i> is raised.
f_tol	[float, optional] Absolute tolerance (in max-norm) for the residual. If omitted, default is 6e-6.
f_rtol	[float, optional] Relative tolerance for the residual. If omitted, not used.
x_tol	[float, optional] Absolute minimum step size, as determined from the Jacobian approximation. If the step size is smaller than this, optimization is terminated as successful. If omitted, not used.
x_rtol	[float, optional] Relative minimum step size. If omitted, not used.
tol_norm	[function(vector) -> scalar, optional] Norm to use in convergence check. Default is the maximum norm.
line_search	[{None, ‘armijo’ (default), ‘wolfe’}, optional] Which type of a line search to use to determine the step size in the direction given by the Jacobian approximation. Defaults to ‘armijo’.
callback	[function, optional] Optional callback function. It is called on every iteration as <code>callback(x, f)</code> where <i>x</i> is the current solution and <i>f</i> the corresponding residual.

Returns

sol [ndarray] An array (of similar array type as *x0*) containing the final solution.

Raises

NoConvergence

When a solution was not found.

See also:

root

Interface to root finding algorithms for multivariate functions. See `method='anderson'` in particular.

References

[Ey]

Examples

The following functions define a system of nonlinear equations

```
>>> def fun(x) :
...     return [x[0] + 0.5 * (x[0] - x[1])**3 - 1.0,
...             0.5 * (x[1] - x[0])**3 + x[1]]
```

A solution can be obtained as follows.

```
>>> from scipy import optimize
>>> sol = optimize.anderson(fun, [0, 0])
>>> sol
array([0.84116588, 0.15883789])
```

Simple iteration solvers:

<code>excitingmixing(F, xin[, iter, alpha, ...])</code>	Find a root of a function, using a tuned diagonal Jacobian approximation.
<code>linearmixing(F, xin[, iter, alpha, verbose, ...])</code>	Find a root of a function, using a scalar Jacobian approximation.
<code>diagbroyden(F, xin[, iter, alpha, verbose, ...])</code>	Find a root of a function, using diagonal Broyden Jacobian approximation.

scipy.optimize.excitingmixing

`scipy.optimize.excitingmixing(F, xin, iter=None, alpha=None, alphamax=1.0, verbose=False, maxiter=None, f_tol=None, f_rtol=None, x_tol=None, x_rtol=None, tol_norm=None, line_search='armijo', callback=None, **kw)`

Find a root of a function, using a tuned diagonal Jacobian approximation.

The Jacobian matrix is diagonal and is tuned on each iteration.

Warning: This algorithm may be useful for specific problems, but whether it will work may depend strongly on the problem.

Parameters

F [function(x) -> f] Function whose root to find; should take and return an array-like object.

xin	[array_like] Initial guess for the solution
alpha	[float, optional] Initial Jacobian approximation is $(-1/\text{alpha})$.
alphamax	[float, optional] The entries of the diagonal Jacobian are kept in the range $[\text{alpha}, \text{alphamax}]$.
iter	[int, optional] Number of iterations to make. If omitted (default), make as many as required to meet tolerances.
verbose	[bool, optional] Print status to stdout on every iteration.
maxiter	[int, optional] Maximum number of iterations to make. If more are needed to meet convergence, <i>NoConvergence</i> is raised.
f_tol	[float, optional] Absolute tolerance (in max-norm) for the residual. If omitted, default is $6e-6$.
f_rtol	[float, optional] Relative tolerance for the residual. If omitted, not used.
x_tol	[float, optional] Absolute minimum step size, as determined from the Jacobian approximation. If the step size is smaller than this, optimization is terminated as successful. If omitted, not used.
x_rtol	[float, optional] Relative minimum step size. If omitted, not used.
tol_norm	[function(vector) -> scalar, optional] Norm to use in convergence check. Default is the maximum norm.
line_search	[{None, 'armijo' (default), 'wolfe'}, optional] Which type of a line search to use to determine the step size in the direction given by the Jacobian approximation. Defaults to 'armijo'.
callback	[function, optional] Optional callback function. It is called on every iteration as <code>callback(x, f)</code> where x is the current solution and f the corresponding residual.

Returns

sol [ndarray] An array (of similar array type as x_0) containing the final solution.

Raises**NoConvergence**

When a solution was not found.

See also:*root*

Interface to root finding algorithms for multivariate functions. See `method='excitingmixing'` in particular.

scipy.optimize.linarmixing

`scipy.optimize.linarmixing`(F , xin , $iter=None$, $alpha=None$, $verbose=False$, $maxiter=None$, $f_tol=None$, $f_rtol=None$, $x_tol=None$, $x_rtol=None$, $tol_norm=None$, $line_search='armijo'$, $callback=None$, $**kw$)

Find a root of a function, using a scalar Jacobian approximation.

Warning: This algorithm may be useful for specific problems, but whether it will work may depend strongly on the problem.

Parameters

F	[function(x) -> f] Function whose root to find; should take and return an array-like object.
xin	[array_like] Initial guess for the solution
alpha	[float, optional] The Jacobian approximation is $(-1/\text{alpha})$.

iter	[int, optional] Number of iterations to make. If omitted (default), make as many as required to meet tolerances.
verbose	[bool, optional] Print status to stdout on every iteration.
maxiter	[int, optional] Maximum number of iterations to make. If more are needed to meet convergence, <i>NoConvergence</i> is raised.
f_tol	[float, optional] Absolute tolerance (in max-norm) for the residual. If omitted, default is 6e-6.
f_rtol	[float, optional] Relative tolerance for the residual. If omitted, not used.
x_tol	[float, optional] Absolute minimum step size, as determined from the Jacobian approximation. If the step size is smaller than this, optimization is terminated as successful. If omitted, not used.
x_rtol	[float, optional] Relative minimum step size. If omitted, not used.
tol_norm	[function(vector) -> scalar, optional] Norm to use in convergence check. Default is the maximum norm.
line_search	[{None, 'armijo' (default), 'wolfe'}, optional] Which type of a line search to use to determine the step size in the direction given by the Jacobian approximation. Defaults to 'armijo'.
callback	[function, optional] Optional callback function. It is called on every iteration as <code>callback(x, f)</code> where <i>x</i> is the current solution and <i>f</i> the corresponding residual.

Returns

sol [ndarray] An array (of similar array type as *x0*) containing the final solution.

Raises

NoConvergence
When a solution was not found.

See also:

root

Interface to root finding algorithms for multivariate functions. See `method=='linear mixing'` in particular.

scipy.optimize.diagbroyden

`scipy.optimize.diagbroyden` (*F*, *xin*, *iter=None*, *alpha=None*, *verbose=False*, *maxiter=None*, *f_tol=None*, *f_rtol=None*, *x_tol=None*, *x_rtol=None*, *tol_norm=None*, *line_search='armijo'*, *callback=None*, ***kw*)

Find a root of a function, using diagonal Broyden Jacobian approximation.

The Jacobian approximation is derived from previous iterations, by retaining only the diagonal of Broyden matrices.

Warning: This algorithm may be useful for specific problems, but whether it will work may depend strongly on the problem.

Parameters

F	[function(x) -> f] Function whose root to find; should take and return an array-like object.
xin	[array_like] Initial guess for the solution
alpha	[float, optional] Initial guess for the Jacobian is (-1/alpha).
iter	[int, optional] Number of iterations to make. If omitted (default), make as many as required to meet tolerances.
verbose	[bool, optional] Print status to stdout on every iteration.

maxiter	[int, optional] Maximum number of iterations to make. If more are needed to meet convergence, <i>NoConvergence</i> is raised.
f_tol	[float, optional] Absolute tolerance (in max-norm) for the residual. If omitted, default is 6e-6.
f_rtol	[float, optional] Relative tolerance for the residual. If omitted, not used.
x_tol	[float, optional] Absolute minimum step size, as determined from the Jacobian approximation. If the step size is smaller than this, optimization is terminated as successful. If omitted, not used.
x_rtol	[float, optional] Relative minimum step size. If omitted, not used.
tol_norm	[function(vector) -> scalar, optional] Norm to use in convergence check. Default is the maximum norm.
line_search	[{None, 'armijo' (default), 'wolfe'}, optional] Which type of a line search to use to determine the step size in the direction given by the Jacobian approximation. Defaults to 'armijo'.
callback	[function, optional] Optional callback function. It is called on every iteration as <code>callback(x, f)</code> where <i>x</i> is the current solution and <i>f</i> the corresponding residual.

Returns

sol [ndarray] An array (of similar array type as *x0*) containing the final solution.

Raises**NoConvergence**

When a solution was not found.

See also:*root*

Interface to root finding algorithms for multivariate functions. See `method=='diagbroyden'` in particular.

Examples

The following functions define a system of nonlinear equations

```
>>> def fun(x):
...     return [x[0] + 0.5 * (x[0] - x[1])**3 - 1.0,
...            0.5 * (x[1] - x[0])**3 + x[1]]
```

A solution can be obtained as follows.

```
>>> from scipy import optimize
>>> sol = optimize.diagbroyden(fun, [0, 0])
>>> sol
array([0.84116403, 0.15883384])
```

Additional information on the nonlinear solvers

6.20 Nonlinear solvers

This is a collection of general-purpose nonlinear multidimensional solvers. These solvers find x for which $F(x) = 0$. Both x and F can be multidimensional.

6.20.1 Routines

Large-scale nonlinear solvers:

<code>newton_krylov(F, xin[, iter, rdiff, method, ...])</code>	Find a root of a function, using Krylov approximation for inverse Jacobian.
<code>anderson(F, xin[, iter, alpha, w0, M, ...])</code>	Find a root of a function, using (extended) Anderson mixing.

General nonlinear solvers:

<code>broyden1(F, xin[, iter, alpha, ...])</code>	Find a root of a function, using Broyden's first Jacobian approximation.
<code>broyden2(F, xin[, iter, alpha, ...])</code>	Find a root of a function, using Broyden's second Jacobian approximation.

Simple iterations:

<code>excitingmixing(F, xin[, iter, alpha, ...])</code>	Find a root of a function, using a tuned diagonal Jacobian approximation.
<code>linearmixing(F, xin[, iter, alpha, verbose, ...])</code>	Find a root of a function, using a scalar Jacobian approximation.
<code>diagbroyden(F, xin[, iter, alpha, verbose, ...])</code>	Find a root of a function, using diagonal Broyden Jacobian approximation.

6.20.2 Examples

Small problem

```
>>> def F(x):
...     return np.cos(x) + x[:, :-1] - [1, 2, 3, 4]
>>> import scipy.optimize
>>> x = scipy.optimize.broyden1(F, [1, 1, 1, 1], f_tol=1e-14)
>>> x
array([ 4.04674914,  3.91158389,  2.71791677,  1.61756251])
>>> np.cos(x) + x[:, :-1]
array([ 1.,  2.,  3.,  4.]
```

Large problem

Suppose that we needed to solve the following integrodifferential equation on the square $[0, 1] \times [0, 1]$:

$$\nabla^2 P = 10 \left(\int_0^1 \int_0^1 \cosh(P) dx dy \right)^2$$

with $P(x, 1) = 1$ and $P = 0$ elsewhere on the boundary of the square.

The solution can be found using the `newton_krylov` solver:

```
import numpy as np
from scipy.optimize import newton_krylov
from numpy import cosh, zeros_like, mgrid, zeros

# parameters
nx, ny = 75, 75
hx, hy = 1./(nx-1), 1./(ny-1)

P_left, P_right = 0, 0
P_top, P_bottom = 1, 0

def residual(P):
    d2x = zeros_like(P)
    d2y = zeros_like(P)

    d2x[1:-1] = (P[2:] - 2*P[1:-1] + P[:-2]) / hx/hx
    d2x[0] = (P[1] - 2*P[0] + P_left) / hx/hx
    d2x[-1] = (P_right - 2*P[-1] + P[-2]) / hx/hx

    d2y[:,1:-1] = (P[:,2:] - 2*P[:,1:-1] + P[:, :-2]) / hy/hy
    d2y[:,0] = (P[:,1] - 2*P[:,0] + P_bottom) / hy/hy
    d2y[:, -1] = (P_top - 2*P[:, -1] + P[:, -2]) / hy/hy

    return d2x + d2y - 10*cosh(P).mean()**2

# solve
guess = zeros((nx, ny), float)
sol = newton_krylov(residual, guess, method='lgmres', verbose=1)
print('Residual: %g' % abs(residual(sol)).max())


# visualize
import matplotlib.pyplot as plt
x, y = mgrid[0:1:(nx*1j), 0:1:(ny*1j)]
plt.pcolormesh(x, y, sol, shading='gouraud')
plt.colorbar()
plt.show()
```

6.21 Cython optimize zeros API

The underlying C functions for the following root finders can be accessed directly using Cython:

- `bisect`
- `ridder`
- `brenth`
- `brentq`

The Cython API for the zeros functions is similar except there is no `disp` argument. Import the zeros functions using `import from scipy.optimize.cython_optimize`.



```
from scipy.optimize.cython_optimize cimport bisect, ridder, brentq, brenth
```

6.21.1 Callback signature

The zeros functions in `cython_optimize` expect a callback that takes a double for the scalar independent variable as the 1st argument and a user defined struct with any extra parameters as the 2nd argument.

```
double (*callback_type)(double, void*)
```

6.21.2 Examples

Usage of `cython_optimize` requires Cython to write callbacks that are compiled into C. For more information on compiling Cython, see the [Cython Documentation](#).

These are the basic steps:

1. Create a Cython `.pyx` file, for example: `myexample.pyx`.
2. Import the desired root finder from `cython_optimize`.
3. Write the callback function, and call the selected zeros function passing the callback, any extra arguments, and the other solver parameters.

```
from scipy.optimize.cython_optimize cimport brentq

# import math from Cython
from libc cimport math

myargs = {'C0': 1.0, 'C1': 0.7} # a dictionary of extra arguments
XLO, XHI = 0.5, 1.0 # lower and upper search boundaries
XTOL, RTOL, MITR = 1e-3, 1e-3, 10 # other solver parameters
```

(continues on next page)

(continued from previous page)

```

# user-defined struct for extra parameters
ctypedef struct test_params:
    double C0
    double C1

# user-defined callback
cdef double f(double x, void *args):
    cdef test_params *myargs = <test_params *> args
    return myargs.C0 - math.exp(-(x - myargs.C1))

# Cython wrapper function
cdef double brentq_wrapper_example(dict args, double xa, double xb,
                                   double xt看, double rtol, int mitr):
    # Cython automatically casts dictionary to struct
    cdef test_params myargs = args
    return brentq(
        f, xa, xb, <test_params *> &myargs, xt看, rtol, mitr, NULL)

# Python function
def brentq_example(args=myargs, xa=XLO, xb=XHI, xt看=XTOL, rtol=RTOL,
                  mitr=MITR):
    '''Calls Cython wrapper from Python.'''
    return brentq_wrapper_example(args, xa, xb, xt看, rtol, mitr)

```

- If you want to call your function from Python, create a Cython wrapper, and a Python function that calls the wrapper, or use `cpdef`. Then, in Python, you can import and run the example.

```

from myexample import brentq_example

x = brentq_example()
# 0.6999942848231314

```

- Create a Cython `.pxd` file if you need to export any Cython functions.

6.21.3 Full output

The functions in `cython_optimize` can also copy the full output from the solver to a C struct that is passed as its last argument. If you don't want the full output, just pass `NULL`. The full output struct must be type `zeros_full_output`, which is defined in `scipy.optimize.cython_optimize` with the following fields:

- `int funcalls`: number of function calls
- `int iterations`: number of iterations
- `int error_num`: error number
- `double root`: root of function

The root is copied by `cython_optimize` to the full output struct. An error number of -1 means a sign error, -2 means a convergence error, and 0 means the solver converged. Continuing from the previous example:

```

from scipy.optimize.cython_optimize cimport zeros_full_output

# cython brentq solver with full output
cdef brent_full_output brentq_full_output_wrapper_example(
    dict args, double xa, double xb, double xtol, double rtol,
    int mitr):
    cdef test_params myargs = args
    cdef zeros_full_output my_full_output
    # use my_full_output instead of NULL
    brentq(f, xa, xb, &myargs, xtol, rtol, mitr, &my_full_output)
    return my_full_output

# Python function
def brent_full_output_example(args=myargs, xa=XLO, xb=XHI, xtol=XTOL,
    rtol=RTOL, mitr=MITR):
    '''Returns full output'''
    return brentq_full_output_wrapper_example(args, xa, xb, xtol, rtol,
        mitr)

result = brent_full_output_example()
# {'error_num': 0,
#   'funcalls': 6,
#   'iterations': 5,
#   'root': 0.6999942848231314}

```

6.22 Signal processing (`scipy.signal`)

6.22.1 Convolution

<code>convolve(in1, in2[, mode, method])</code>	Convolve two N-dimensional arrays.
<code>correlate(in1, in2[, mode, method])</code>	Cross-correlate two N-dimensional arrays.
<code>fftconvolve(in1, in2[, mode, axes])</code>	Convolve two N-dimensional arrays using FFT.
<code>oaconvolve(in1, in2[, mode, axes])</code>	Convolve two N-dimensional arrays using the overlap-add method.
<code>convolve2d(in1, in2[, mode, boundary, fillvalue])</code>	Convolve two 2-dimensional arrays.
<code>correlate2d(in1, in2[, mode, boundary, ...])</code>	Cross-correlate two 2-dimensional arrays.
<code>sepfir2d(input, hrow, hcol)</code>	Convolve with a 2-D separable FIR filter.
<code>choose_conv_method(in1, in2[, mode, measure])</code>	Find the fastest convolution/correlation method.
<code>correlation_lags(in1_len, in2_len[, mode])</code>	Calculates the lag / displacement indices array for 1D cross-correlation.

scipy.signal.convolve

`scipy.signal.convolve` (*in1*, *in2*, *mode*='full', *method*='auto')

Convolve two N-dimensional arrays.

Convolve *in1* and *in2*, with the output size determined by the *mode* argument.

Parameters

in1	[array_like] First input.
in2	[array_like] Second input. Should have the same number of dimensions as <i>in1</i> .
mode	[str {'full', 'valid', 'same'}, optional] A string indicating the size of the output: <ul style="list-style-type: none"> full The output is the full discrete linear convolution of the inputs. (Default) valid The output consists only of those elements that do not rely on the zero-padding. In 'valid' mode, either <i>in1</i> or <i>in2</i> must be at least as large as the other in every dimension. same The output is the same size as <i>in1</i>, centered with respect to the 'full' output.
method	[str {'auto', 'direct', 'fft'}, optional] A string indicating which method to use to calculate the convolution. <ul style="list-style-type: none"> direct The convolution is determined directly from sums, the definition of convolution. fft The Fourier Transform is used to perform the convolution by calling <code>fftconvolve</code>. auto Automatically chooses direct or Fourier method based on an estimate of which is faster (default). See Notes for more detail. New in version 0.19.0.

Returns

convolve [array] An N-dimensional array containing a subset of the discrete linear convolution of *in1* with *in2*.

See also:**`numpy.polymul`**

performs polynomial multiplication (same operation, but also accepts poly1d objects)

`choose_conv_method`

chooses the fastest appropriate convolution method

`fftconvolve`

Always uses the FFT method.

`oaconvolve`

Uses the overlap-add method to do convolution, which is generally faster when the input arrays are large and significantly different in size.

Notes


By default, `convolve` and `correlate` use `method='auto'`, which calls `choose_conv_method` to choose the fastest method using pre-computed values (`choose_conv_method` can also measure real-world timing with a keyword argument). Because `fftconvolve` relies on floating point numbers, there are certain constraints that may force `method=direct` (more detail in `choose_conv_method` docstring).

Examples

Smooth a square pulse using a Hann window:

```
>>> from scipy import signal
>>> sig = np.repeat([0., 1., 0.], 100)
>>> win = signal.windows.hann(50)
>>> filtered = signal.convolve(sig, win, mode='same') / sum(win)
```

```
>>> import matplotlib.pyplot as plt
>>> fig, (ax_orig, ax_win, ax_filt) = plt.subplots(3, 1, sharex=True)
>>> ax_orig.plot(sig)
>>> ax_orig.set_title('Original pulse')
>>> ax_orig.margins(0, 0.1)
>>> ax_win.plot(win)
>>> ax_win.set_title('Filter impulse response')
>>> ax_win.margins(0, 0.1)
>>> ax_filt.plot(filtered)
>>> ax_filt.set_title('Filtered signal')
>>> ax_filt.margins(0, 0.1)
>>> fig.tight_layout()
>>> fig.show()
```



scipy.signal.correlate

`scipy.signal.correlate` (*in1*, *in2*, *mode*='full', *method*='auto')

Cross-correlate two N-dimensional arrays.

Cross-correlate *in1* and *in2*, with the output size determined by the *mode* argument.

Parameters

in1	[array_like] First input.
in2	[array_like] Second input. Should have the same number of dimensions as <i>in1</i> .
mode	[str {'full', 'valid', 'same'}, optional] A string indicating the size of the output: <ul style="list-style-type: none"> full The output is the full discrete linear cross-correlation of the inputs. (Default) valid The output consists only of those elements that do not rely on the zero-padding. In 'valid' mode, either <i>in1</i> or <i>in2</i> must be at least as large as the other in every dimension. same The output is the same size as <i>in1</i>, centered with respect to the 'full' output.
method	[str {'auto', 'direct', 'fft'}, optional] A string indicating which method to use to calculate the correlation. <ul style="list-style-type: none"> direct The correlation is determined directly from sums, the definition of correlation. fft The Fast Fourier Transform is used to perform the correlation more quickly (only available for numerical arrays.) auto Automatically chooses direct or Fourier method based on an estimate of which is faster (default). See convolve Notes for more detail. New in version 0.19.0.

Returns

correlate [array] An N-dimensional array containing a subset of the discrete linear cross-correlation of *in1* with *in2*.

See also:

[choose_conv_method](#)

contains more documentation on *method*.

[correlation_lags](#)

calculates the lag / displacement indices array for 1D cross-correlation.

Notes

The correlation *z* of two d-dimensional arrays *x* and *y* is defined as:

```
z[... , k, ...] = sum[... , i_1, ...] x[... , i_1, ...] * conj(y[... , i_1 - k, ...])
```

This way, if *x* and *y* are 1-D arrays and `z = correlate(x, y, 'full')` then

$$z[k] = (x * y)(k - N + 1) = \sum_{l=0}^{|x|-1} x_l y_{l-k+N-1}^*$$

for $k = 0, 1, \dots, |x| + |y| - 2$

where $|x|$ is the length of *x*, $N = \max(|x|, |y|)$, and y_m is 0 when *m* is outside the range of *y*.

`method='fft'` only works for numerical arrays as it relies on [fftconvolve](#). In certain cases (i.e., arrays of objects or when rounding integers can lose precision), `method='direct'` is always used.

When using “same” mode with even-length inputs, the outputs of `correlate` and `correlate2d` differ: There is a 1-index offset between them.


Examples

Implement a matched filter using cross-correlation, to recover a signal that has passed through a noisy channel.

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt

>>> sig = np.repeat([0., 1., 1., 0., 1., 0., 0., 1.], 128)
>>> sig_noise = sig + np.random.randn(len(sig))
>>> corr = signal.correlate(sig_noise, np.ones(128), mode='same') / 128

>>> clock = np.arange(64, len(sig), 128)
>>> fig, (ax_orig, ax_noise, ax_corr) = plt.subplots(3, 1, sharex=True)
>>> ax_orig.plot(sig)
>>> ax_orig.plot(clock, sig[clock], 'ro')
>>> ax_orig.set_title('Original signal')
>>> ax_noise.plot(sig_noise)
>>> ax_noise.set_title('Signal with noise')
>>> ax_corr.plot(corr)
>>> ax_corr.plot(clock, corr[clock], 'ro')
>>> ax_corr.axhline(0.5, ls=':')
>>> ax_corr.set_title('Cross-correlated with rectangular pulse')
>>> ax_orig.margins(0, 0.1)
>>> fig.tight_layout()
>>> plt.show()
```



Compute the cross-correlation of a noisy signal with the original signal.

```
>>> x = np.arange(128) / 128
>>> sig = np.sin(2 * np.pi * x)
```

(continues on next page)


(continued from previous page)

```

>>> sig_noise = sig + np.random.randn(len(sig))
>>> corr = signal.correlate(sig_noise, sig)
>>> lags = signal.correlation_lags(len(sig), len(sig_noise))
>>> corr /= np.max(corr)

>>> fig, (ax_orig, ax_noise, ax_corr) = plt.subplots(3, 1, figsize=(4.8, 4.8))
>>> ax_orig.plot(sig)
>>> ax_orig.set_title('Original signal')
>>> ax_orig.set_xlabel('Sample Number')
>>> ax_noise.plot(sig_noise)
>>> ax_noise.set_title('Signal with noise')
>>> ax_noise.set_xlabel('Sample Number')
>>> ax_corr.plot(lags, corr)
>>> ax_corr.set_title('Cross-correlated signal')
>>> ax_corr.set_xlabel('Lag')
>>> ax_orig.margins(0, 0.1)
>>> ax_noise.margins(0, 0.1)
>>> ax_corr.margins(0, 0.1)
>>> fig.tight_layout()
>>> plt.show()

```



scipy.signal.fftconvolve

`scipy.signal.fftconvolve` (*in1*, *in2*, *mode*='full', *axes*=None)

Convolve two N-dimensional arrays using FFT.

Convolve *in1* and *in2* using the fast Fourier transform method, with the output size determined by the *mode* argument.

This is generally much faster than `convolve` for large arrays ($n > \sim 500$), but can be slower when only a few output values are needed, and can only output float arrays (int or object array inputs will be cast to float).

As of v0.19, `convolve` automatically chooses this method or the direct method based on an estimation of which is faster.

Parameters

in1	[array_like] First input.
in2	[array_like] Second input. Should have the same number of dimensions as <i>in1</i> .
mode	[str {'full', 'valid', 'same'}, optional] A string indicating the size of the output:
full	The output is the full discrete linear convolution of the inputs. (Default)
valid	The output consists only of those elements that do not rely on the zero-padding. In 'valid' mode, either <i>in1</i> or <i>in2</i> must be at least as large as the other in every dimension.
same	The output is the same size as <i>in1</i> , centered with respect to the 'full' output.
axes	[int or array_like of ints or None, optional] Axes over which to compute the convolution. The default is over all axes.

Returns

out	[array] An N-dimensional array containing a subset of the discrete linear convolution of <i>in1</i> with <i>in2</i> .
------------	---

See also:**`convolve`**

Uses the direct convolution or FFT convolution algorithm depending on which is faster.

`oaconvolve`

Uses the overlap-add method to do convolution, which is generally faster when the input arrays are large and significantly different in size.

Examples

Autocorrelation of white noise is an impulse.

```
>>> from scipy import signal
>>> sig = np.random.randn(1000)
>>> autocorr = signal.fftconvolve(sig, sig[::-1], mode='full')
```

```
>>> import matplotlib.pyplot as plt
>>> fig, (ax_orig, ax_mag) = plt.subplots(2, 1)
>>> ax_orig.plot(sig)
>>> ax_orig.set_title('White noise')
>>> ax_mag.plot(np.arange(-len(sig)+1, len(sig)), autocorr)
>>> ax_mag.set_title('Autocorrelation')
```

(continues on next page)


(continued from previous page)

```
>>> fig.tight_layout()
>>> fig.show()
```

Gaussian blur implemented using FFT convolution. Notice the dark borders around the image, due to the zero-padding beyond its boundaries. The `convolve2d` function allows for other types of image boundaries, but is far slower.

```
>>> from scipy import misc
>>> face = misc.face(gray=True)
>>> kernel = np.outer(signal.windows.gaussian(70, 8),
...                  signal.windows.gaussian(70, 8))
>>> blurred = signal.fftconvolve(face, kernel, mode='same')
```


```
>>> fig, (ax_orig, ax_kernel, ax_blurred) = plt.subplots(3, 1,
...                                                    figsize=(6, 15))
>>> ax_orig.imshow(face, cmap='gray')
>>> ax_orig.set_title('Original')
>>> ax_orig.set_axis_off()
>>> ax_kernel.imshow(kernel, cmap='gray')
>>> ax_kernel.set_title('Gaussian kernel')
>>> ax_kernel.set_axis_off()
>>> ax_blurred.imshow(blurred, cmap='gray')
>>> ax_blurred.set_title('Blurred')
>>> ax_blurred.set_axis_off()
>>> fig.show()
```



Original



Gaussian kernel



Blurred



scipy.signal.oaconvolve

`scipy.signal.oaconvolve` (*in1*, *in2*, *mode*='full', *axes*=None)

Convolve two N-dimensional arrays using the overlap-add method.

Convolve *in1* and *in2* using the overlap-add method, with the output size determined by the *mode* argument.

This is generally much faster than `convolve` for large arrays ($n > \sim 500$), and generally much faster than `fftconvolve` when one array is much larger than the other, but can be slower when only a few output values are needed or when the arrays are very similar in shape, and can only output float arrays (int or object array inputs will be cast to float).

Parameters

in1	[array_like] First input.
in2	[array_like] Second input. Should have the same number of dimensions as <i>in1</i> .
mode	[str {'full', 'valid', 'same'}, optional] A string indicating the size of the output: full The output is the full discrete linear convolution of the inputs. (Default) valid The output consists only of those elements that do not rely on the zero-padding. In 'valid' mode, either <i>in1</i> or <i>in2</i> must be at least as large as the other in every dimension. same The output is the same size as <i>in1</i> , centered with respect to the 'full' output.
axes	[int or array_like of ints or None, optional] Axes over which to compute the convolution. The default is over all axes.

Returns

out	[array] An N-dimensional array containing a subset of the discrete linear convolution of <i>in1</i> with <i>in2</i> .
------------	---

See also:

`convolve`

Uses the direct convolution or FFT convolution algorithm depending on which is faster.

`fftconvolve`

An implementation of convolution using FFT.

Notes

New in version 1.4.0.

References


[1], [2]

Examples

Convolve a 100,000 sample signal with a 512-sample filter.

```
>>> from scipy import signal
>>> sig = np.random.randn(100000)
>>> filt = signal.firwin(512, 0.01)
>>> fsig = signal.oaconvolve(sig, filt)
```

```
>>> import matplotlib.pyplot as plt
>>> fig, (ax_orig, ax_mag) = plt.subplots(2, 1)
>>> ax_orig.plot(sig)
>>> ax_orig.set_title('White noise')
>>> ax_mag.plot(fsig)
>>> ax_mag.set_title('Filtered noise')
>>> fig.tight_layout()
>>> fig.show()
```



scipy.signal.convolve2d

`scipy.signal.convolve2d(in1, in2, mode='full', boundary='fill', fillvalue=0)`

Convolve two 2-dimensional arrays.

Convolve *in1* and *in2* with output size determined by *mode*, and boundary conditions determined by *boundary* and *fillvalue*.

Parameters

in1	[array_like] First input.
in2	[array_like] Second input. Should have the same number of dimensions as <i>in1</i> .
mode	[str {'full', 'valid', 'same'}, optional] A string indicating the size of the output:
full	The output is the full discrete linear convolution of the inputs. (Default)
valid	The output consists only of those elements that do not rely on the zero-padding. In 'valid' mode, either <i>in1</i> or <i>in2</i> must be at least as large as the other in every dimension.

boundary **same** The output is the same size as *in1*, centered with respect to the 'full' output.
 [str {'fill', 'wrap', 'symm'}, optional] A flag indicating how to handle boundaries:
fill pad input arrays with fillvalue. (default)
wrap circular boundary conditions.
symm symmetrical boundary conditions.
fillvalue [scalar, optional] Value to fill pad input arrays with. Default is 0.

Returns

out [ndarray] A 2-dimensional array containing a subset of the discrete linear convolution of *in1* with *in2*.

Examples

Compute the gradient of an image by 2D convolution with a complex Scharr operator. (Horizontal operator is real, vertical is imaginary.) Use symmetric boundary condition to avoid creating edges at the image boundaries.

```
>>> from scipy import signal
>>> from scipy import misc
>>> ascent = misc.ascent()
>>> scharr = np.array([[ -3-3j, 0-10j,  +3 -3j],
...                   [-10+0j, 0+ 0j, +10 +0j],
...                   [ -3+3j, 0+10j,  +3 +3j]]) # Gx + j*Gy
>>> grad = signal.convolve2d(ascent, scharr, boundary='symm', mode='same')
```

```
>>> import matplotlib.pyplot as plt
>>> fig, (ax_orig, ax_mag, ax_ang) = plt.subplots(3, 1, figsize=(6, 15))
>>> ax_orig.imshow(ascent, cmap='gray')
>>> ax_orig.set_title('Original')
>>> ax_orig.set_axis_off()
>>> ax_mag.imshow(np.absolute(grad), cmap='gray')
>>> ax_mag.set_title('Gradient magnitude')
>>> ax_mag.set_axis_off()
>>> ax_ang.imshow(np.angle(grad), cmap='hsv') # hsv is cyclic, like angles
>>> ax_ang.set_title('Gradient orientation')
>>> ax_ang.set_axis_off()
>>> fig.show()
```

scipy.signal.correlate2d

`scipy.signal.correlate2d(in1, in2, mode='full', boundary='fill', fillvalue=0)`

Cross-correlate two 2-dimensional arrays.

Cross correlate *in1* and *in2* with output size determined by *mode*, and boundary conditions determined by *boundary* and *fillvalue*.

Parameters

in1 [array_like] First input.
in2 [array_like] Second input. Should have the same number of dimensions as *in1*.
mode [str {'full', 'valid', 'same'}, optional] A string indicating the size of the output:
full The output is the full discrete linear cross-correlation of the inputs. (Default)


Original



Gradient magnitude



Gradient orientation



valid	The output consists only of those elements that do not rely on the zero-padding. In ‘valid’ mode, either <i>in1</i> or <i>in2</i> must be at least as large as the other in every dimension.
same	The output is the same size as <i>in1</i> , centered with respect to the ‘full’ output.
boundary	[str {‘fill’, ‘wrap’, ‘symm’}, optional] A flag indicating how to handle boundaries:
fill	pad input arrays with fillvalue. (default)
wrap	circular boundary conditions.
symm	symmetrical boundary conditions.
fillvalue	[scalar, optional] Value to fill pad input arrays with. Default is 0.

Returns**correlate2d**

[ndarray] A 2-dimensional array containing a subset of the discrete linear cross-correlation of *in1* with *in2*.

Notes

When using “same” mode with even-length inputs, the outputs of *correlate* and *correlate2d* differ: There is a 1-index offset between them.

Examples

Use 2D cross-correlation to find the location of a template in a noisy image:

```
>>> from scipy import signal
>>> from scipy import misc
>>> face = misc.face(gray=True) - misc.face(gray=True).mean()
>>> template = np.copy(face[300:365, 670:750]) # right eye
>>> template -= template.mean()
>>> face = face + np.random.randn(*face.shape) * 50 # add noise
>>> corr = signal.correlate2d(face, template, boundary='symm', mode='same
↳')
>>> y, x = np.unravel_index(np.argmax(corr), corr.shape) # find the match
```

```
>>> import matplotlib.pyplot as plt
>>> fig, (ax_orig, ax_template, ax_corr) = plt.subplots(3, 1,
...                                                figsize=(6, 15))
>>> ax_orig.imshow(face, cmap='gray')
>>> ax_orig.set_title('Original')
>>> ax_orig.set_axis_off()
>>> ax_template.imshow(template, cmap='gray')
>>> ax_template.set_title('Template')
>>> ax_template.set_axis_off()
>>> ax_corr.imshow(corr, cmap='gray')
>>> ax_corr.set_title('Cross-correlation')
>>> ax_corr.set_axis_off()
>>> ax_orig.plot(x, y, 'ro')
>>> fig.show()
```


Original



Template



Cross-correlation



scipy.signal.sepfir2d

`scipy.signal.sepfir2d(input, hrow, hcol)`

Convolve with a 2-D separable FIR filter.

Convolve the rank-2 input array with the separable filter defined by the rank-1 arrays `hrow`, and `hcol`. Mirror symmetric boundary conditions are assumed. This function can be used to find an image given its B-spline representation.

Parameters

input	[ndarray] The input signal. Must be a rank-2 array.
hrow	[ndarray] A rank-1 array defining the row direction of the filter. Must be odd-length
hcol	[ndarray] A rank-1 array defining the column direction of the filter. Must be odd-length

Returns

output	[ndarray] The filtered signal.
---------------	--------------------------------

Examples

Examples are given *in the tutorial*.

scipy.signal.choose_conv_method

`scipy.signal.choose_conv_method(in1, in2, mode='full', measure=False)`

Find the fastest convolution/correlation method.

This primarily exists to be called during the `method='auto'` option in `convolve` and `correlate`. It can also be used to determine the value of `method` for many different convolutions of the same dtype/shape. In addition, it supports timing the convolution to adapt the value of `method` to a particular set of inputs and/or hardware.

Parameters

in1	[array_like] The first argument passed into the convolution function.
in2	[array_like] The second argument passed into the convolution function.
mode	[str {'full', 'valid', 'same'}, optional] A string indicating the size of the output: full The output is the full discrete linear convolution of the inputs. (Default) valid The output consists only of those elements that do not rely on the zero-padding. same The output is the same size as <code>in1</code> , centered with respect to the 'full' output.
measure	[bool, optional] If True, run and time the convolution of <code>in1</code> and <code>in2</code> with both methods and return the fastest. If False (default), predict the fastest method using precomputed values.

Returns

method	[str] A string indicating which convolution method is fastest, either 'direct' or 'fft'
times	[dict, optional] A dictionary containing the times (in seconds) needed for each method. This value is only returned if <code>measure=True</code> .

See also:

[`convolve`](#)

[`correlate`](#)

Notes

Generally, this method is 99% accurate for 2D signals and 85% accurate for 1D signals for randomly chosen input sizes. For precision, use `measure=True` to find the fastest method by timing the convolution. This can be used to avoid the minimal overhead of finding the fastest `method` later, or to adapt the value of `method` to a particular set of inputs.

Experiments were run on an Amazon EC2 r5a.2xlarge machine to test this function. These experiments measured the ratio between the time required when using `method='auto'` and the time required for the fastest method (i.e., `ratio = time_auto / min(time_fft, time_direct)`). In these experiments, we found:

- There is a 95% chance of this ratio being less than 1.5 for 1D signals and a 99% chance of being less than 2.5 for 2D signals.
- The ratio was always less than 2.5/5 for 1D/2D signals respectively.
- This function is most inaccurate for 1D convolutions that take between 1 and 10 milliseconds with `method='direct'`. A good proxy for this (at least in our experiments) is `1e6 <= in1.size * in2.size <= 1e7`.

The 2D results almost certainly generalize to 3D/4D/etc because the implementation is the same (the 1D implementation is different).

All the numbers above are specific to the EC2 machine. However, we did find that this function generalizes fairly decently across hardware. The speed tests were of similar quality (and even slightly better) than the same tests performed on the machine to tune this function's numbers (a mid-2014 15-inch MacBook Pro with 16GB RAM and a 2.5GHz Intel i7 processor).

There are cases when `fftconvolve` supports the inputs but this function returns `direct` (e.g., to protect against floating point integer precision).

New in version 0.19.

Examples

Estimate the fastest method for a given input:

```
>>> from scipy import signal
>>> img = np.random.rand(32, 32)
>>> filter = np.random.rand(8, 8)
>>> method = signal.choose_conv_method(img, filter, mode='same')
>>> method
'fft'
```

This can then be applied to other arrays of the same dtype and shape:

```
>>> img2 = np.random.rand(32, 32)
>>> filter2 = np.random.rand(8, 8)
>>> corr2 = signal.correlate(img2, filter2, mode='same', method=method)
>>> conv2 = signal.convolve(img2, filter2, mode='same', method=method)
```

The output of this function (`method`) works with `correlate` and `convolve`.

scipy.signal.correlation_lags

`scipy.signal.correlation_lags(in1_len, in2_len, mode='full')`

Calculates the lag / displacement indices array for 1D cross-correlation.

Parameters

in1_size [int] First input size.
in2_size [int] Second input size.
mode [str {'full', 'valid', 'same'}, optional] A string indicating the size of the output. See the documentation `correlate` for more information.

Returns

lags [array] Returns an array containing cross-correlation lag/displacement indices. Indices can be indexed with the `np.argmax` of the correlation to return the lag/displacement.

See also:

`correlate`

Compute the N-dimensional cross-correlation.

Notes

Cross-correlation for continuous functions f and g is defined as:

$$(f \star g)(\tau) \triangleq \int_{t_0}^{t_0+T} \overline{f(t)}g(t + \tau) dt$$

Where τ is defined as the displacement, also known as the lag.

Cross correlation for discrete functions f and g is defined as:

$$(f \star g)[n] \triangleq \sum_{-\infty}^{\infty} \overline{f[m]}g[m + n]$$

Where n is the lag.

Examples

Cross-correlation of a signal with its time-delayed self.

```
>>> from scipy import signal
>>> rng = np.random.RandomState(0)
>>> x = rng.standard_normal(1000)
>>> y = np.concatenate([rng.standard_normal(100), x])
>>> correlation = signal.correlate(x, y, mode="full")
>>> lags = signal.correlation_lags(x.size, y.size, mode="full")
>>> lag = lags[np.argmax(correlation)]
```

6.22.2 B-splines

<code>bspline(x, n)</code>	B-spline basis function of order n.
<code>cubic(x)</code>	A cubic B-spline.
<code>quadratic(x)</code>	A quadratic B-spline.
<code>gauss_spline(x, n)</code>	Gaussian approximation to B-spline basis function of order n.
<code>cspline1d(signal[, lamb])</code>	Compute cubic spline coefficients for rank-1 array.
<code>qspline1d(signal[, lamb])</code>	Compute quadratic spline coefficients for rank-1 array.
<code>cspline2d(input[, lambda, precision])</code>	Coefficients for 2-D cubic (3rd order) B-spline.
<code>qspline2d(input[, lambda, precision])</code>	Coefficients for 2-D quadratic (2nd order) B-spline:
<code>cspline1d_eval(cj, newx[, dx, x0])</code>	Evaluate a cubic spline at the new set of points.
<code>qspline1d_eval(cj, newx[, dx, x0])</code>	Evaluate a quadratic spline at the new set of points.
<code>spline_filter(lin[, lmbda])</code>	Smoothing spline (cubic) filtering of a rank-2 array.

scipy.signal.bspline

`scipy.signal.bspline(x, n)`
 B-spline basis function of order n.

Parameters

x [array like] a knot vector
n [int] The order of the spline. Must be non-negative, i.e., $n \geq 0$

Returns

res [ndarray] B-spline basis function values

See also:

`cubic`

A cubic B-spline.

`quadratic`

A quadratic B-spline.

Notes

Uses `numpy.piecewise` and automatic function-generator.

Examples

We can calculate B-Spline basis function of several orders:

```
>>> from scipy.signal import bspline, cubic, quadratic
>>> bspline(0.0, 1)
1
```

```
>>> knots = [-1.0, 0.0, -1.0]
>>> bspline(knots, 2)
array([0.125, 0.75, 0.125])
```



```
>>> np.array_equal(bspline(knots, 2), quadratic(knots))
True
```

```
>>> np.array_equal(bspline(knots, 3), cubic(knots))
True
```

scipy.signal.cubic

`scipy.signal.cubic(x)`

A cubic B-spline.

This is a special case of *bspline*, and equivalent to `bspline(x, 3)`.

Parameters

x [array like] a knot vector

Returns

res [ndarray] Cubic B-spline basis function values

See also:

bspline

B-spline basis function of order n

quadratic

A quadratic B-spline.

Examples

We can calculate B-Spline basis function of several orders:

```
>>> from scipy.signal import bspline, cubic, quadratic
>>> bspline(0.0, 1)
1
```

```
>>> knots = [-1.0, 0.0, -1.0]
>>> bspline(knots, 2)
array([0.125, 0.75, 0.125])
```

```
>>> np.array_equal(bspline(knots, 2), quadratic(knots))
True
```

```
>>> np.array_equal(bspline(knots, 3), cubic(knots))
True
```

scipy.signal.quadratic

`scipy.signal.quadratic(x)`

A quadratic B-spline.

This is a special case of `bspline`, and equivalent to `bspline(x, 2)`.

Parameters

x [array like] a knot vector

Returns

res [ndarray] Quadratic B-spline basis function values

See also:

`bspline`

B-spline basis function of order n

`cubic`

A cubic B-spline.

Examples

We can calculate B-Spline basis function of several orders:

```
>>> from scipy.signal import bspline, cubic, quadratic
>>> bspline(0.0, 1)
1
```

```
>>> knots = [-1.0, 0.0, -1.0]
>>> bspline(knots, 2)
array([0.125, 0.75, 0.125])
```

```
>>> np.array_equal(bspline(knots, 2), quadratic(knots))
True
```

```
>>> np.array_equal(bspline(knots, 3), cubic(knots))
True
```

scipy.signal.gauss_spline

`scipy.signal.gauss_spline(x, n)`

Gaussian approximation to B-spline basis function of order n.

Parameters

x [array] a knot vector

n [int] The order of the spline. Must be non-negative, i.e., $n \geq 0$

Returns

res [ndarray] B-spline basis function values approximated by a zero-mean Gaussian function.

Notes

The B-spline basis function can be approximated well by a zero-mean Gaussian function with standard-deviation equal to $\sigma = (n + 1)/12$ for large n :

$$\frac{1}{\sqrt{2\pi\sigma^2}} \exp\left(-\frac{x^2}{2\sigma^2}\right)$$

References

[1], [2]

Examples

We can calculate B-Spline basis functions approximated by a gaussian distribution:

```
>>> from scipy.signal import gauss_spline, bspline
>>> knots = np.array([-1.0, 0.0, -1.0])
>>> gauss_spline(knots, 3)
array([0.15418033, 0.6909883, 0.15418033]) # may vary
```

```
>>> bspline(knots, 3)
array([0.16666667, 0.66666667, 0.16666667]) # may vary
```

scipy.signal.cspline1d

`scipy.signal.cspline1d` (*signal*, *lamb=0.0*)

Compute cubic spline coefficients for rank-1 array.

Find the cubic spline coefficients for a 1-D signal assuming mirror-symmetric boundary conditions. To obtain the signal back from the spline representation mirror-symmetric-convolve these coefficients with a length 3 FIR window [1.0, 4.0, 1.0]/ 6.0 .

Parameters

signal [ndarray] A rank-1 array representing samples of a signal.
lamb [float, optional] Smoothing coefficient, default is 0.0.

Returns

c [ndarray] Cubic spline coefficients.

See also:


`cspline1d_eval`

Evaluate a cubic spline at the new set of points.

Examples

We can filter a signal to reduce and smooth out high-frequency noise with a cubic spline:

```
>>> import matplotlib.pyplot as plt
>>> from scipy.signal import cspline1d, cspline1d_eval
>>> sig = np.repeat([0., 1., 0.], 100)
>>> sig += np.random.randn(len(sig))*0.05 # add noise
>>> time = np.linspace(0, len(sig))
>>> filtered = cspline1d_eval(cspline1d(sig), time)
>>> plt.plot(sig, label="signal")
>>> plt.plot(time, filtered, label="filtered")
>>> plt.legend()
>>> plt.show()
```



scipy.signal.qspline1d

`scipy.signal.qspline1d` (*signal*, *lamb=0.0*)

Compute quadratic spline coefficients for rank-1 array.

Parameters

signal [ndarray] A rank-1 array representing samples of a signal.
lamb [float, optional] Smoothing coefficient (must be zero for now).

Returns

c [ndarray] Quadratic spline coefficients.

See also:

`qspline1d_eval`

Evaluate a quadratic spline at the new set of points.


Notes

Find the quadratic spline coefficients for a 1-D signal assuming mirror-symmetric boundary conditions. To obtain the signal back from the spline representation mirror-symmetric-convolve these coefficients with a length 3 FIR window $[1.0, 6.0, 1.0]/8.0$.

Examples

We can filter a signal to reduce and smooth out high-frequency noise with a quadratic spline:

```
>>> import matplotlib.pyplot as plt
>>> from scipy.signal import qspline1d, qspline1d_eval
>>> sig = np.repeat([0., 1., 0.], 100)
>>> sig += np.random.randn(len(sig))*0.05 # add noise
>>> time = np.linspace(0, len(sig))
>>> filtered = qspline1d_eval(qspline1d(sig), time)
>>> plt.plot(sig, label="signal")
>>> plt.plot(time, filtered, label="filtered")
>>> plt.legend()
>>> plt.show()
```



scipy.signal.cspline2d

`scipy.signal.cspline2d` (*input*, *lambda*=0.0, *precision*=-1.0)
Coefficients for 2-D cubic (3rd order) B-spline.

Return the third-order B-spline coefficients over a regularly spaced input grid for the two-dimensional input image.

Parameters

input	[ndarray] The input signal.
lambda	[float] Specifies the amount of smoothing in the transfer function.
precision	[float] Specifies the precision for computing the infinite sum needed to apply mirror-symmetric boundary conditions.

Returns

output [ndarray] The filtered signal.

Examples

Examples are given *in the tutorial*.

scipy.signal.qspline2d

`scipy.signal.qspline2d` (*input*, *lambda=0.0*, *precision=-1.0*)

Coefficients for 2-D quadratic (2nd order) B-spline:

Return the second-order B-spline coefficients over a regularly spaced input grid for the two-dimensional input image.

Parameters

input [ndarray] The input signal.

lambda [float] Specifies the amount of smoothing in the transfer function.

precision [float] Specifies the precision for computing the infinite sum needed to apply mirror- symmetric boundary conditions.

Returns

output [ndarray] The filtered signal.

Examples

Examples are given *in the tutorial*.

scipy.signal.cspline1d_eval

`scipy.signal.cspline1d_eval` (*cj*, *newx*, *dx=1.0*, *x0=0*)

Evaluate a cubic spline at the new set of points.

dx is the old sample-spacing while *x0* was the old origin. In other-words the old-sample points (knot-points) for which the *cj* represent spline coefficients were at equally-spaced points of:

$$\text{oldx} = x0 + j * dx \quad j=0 \dots N-1, \text{ with } N=\text{len}(cj)$$

Edges are handled using mirror-symmetric boundary conditions.

Parameters

cj [ndarray] cubic spline coefficients

newx [ndarray] New set of points.

dx [float, optional] Old sample-spacing, the default value is 1.0.

x0 [int, optional] Old origin, the default value is 0.

Returns

res [ndarray] Evaluated a cubic spline points.

See also:


cspline1d

Compute cubic spline coefficients for rank-1 array.

Examples

We can filter a signal to reduce and smooth out high-frequency noise with a cubic spline:

```
>>> import matplotlib.pyplot as plt
>>> from scipy.signal import cspline1d, cspline1d_eval
>>> sig = np.repeat([0., 1., 0.], 100)
>>> sig += np.random.randn(len(sig))*0.05 # add noise
>>> time = np.linspace(0, len(sig))
>>> filtered = cspline1d_eval(cspline1d(sig), time)
>>> plt.plot(sig, label="signal")
>>> plt.plot(time, filtered, label="filtered")
>>> plt.legend()
>>> plt.show()
```



scipy.signal.qspline1d_eval

`scipy.signal.qspline1d_eval` (*cj*, *newx*, *dx=1.0*, *x0=0*)

Evaluate a quadratic spline at the new set of points.

Parameters

cj	[ndarray] Quadratic spline coefficients
newx	[ndarray] New set of points.
dx	[float, optional] Old sample-spacing, the default value is 1.0.
x0	[int, optional] Old origin, the default value is 0.

Returns

res	[ndarray] Evaluated a quadratic spline points.
------------	--

See also:

`qspline1d`

Compute quadratic spline coefficients for rank-1 array.

Notes

dx is the old sample-spacing while x_0 was the old origin. In other-words the old-sample points (knot-points) for which the c_j represent spline coefficients were at equally-spaced points of:


```
oldx = x0 + j*dx   j=0...N-1, with N=len(cj)
```

Edges are handled using mirror-symmetric boundary conditions.

Examples

We can filter a signal to reduce and smooth out high-frequency noise with a quadratic spline:

```
>>> import matplotlib.pyplot as plt
>>> from scipy.signal import qspline1d, qspline1d_eval
>>> sig = np.repeat([0., 1., 0.], 100)
>>> sig += np.random.randn(len(sig))*0.05 # add noise
>>> time = np.linspace(0, len(sig))
>>> filtered = qspline1d_eval(qspline1d(sig), time)
>>> plt.plot(sig, label="signal")
>>> plt.plot(time, filtered, label="filtered")
>>> plt.legend()
>>> plt.show()
```



scipy.signal.spline_filter

`scipy.signal.spline_filter` (*Iin*, *lmbda*=5.0)
Smoothing spline (cubic) filtering of a rank-2 array.

Filter an input data set, *Iin*, using a (cubic) smoothing spline of fall-off *lmbda*.

Parameters

Iin [array like] input data set
lmbda [float, optional] spline smoothing fall-off value, default is 5.0.


Returns

res [ndarray] filtered input data

Examples

We can filter an multi dimensional signal (ex: 2D image) using cubic B-spline filter:

```
>>> from scipy.signal import spline_filter
>>> import matplotlib.pyplot as plt
>>> orig_img = np.eye(20) # create an image
>>> orig_img[10, :] = 1.0
>>> sp_filter = spline_filter(orig_img, lmbda=0.1)
>>> f, ax = plt.subplots(1, 2, sharex=True)
>>> for ind, data in enumerate([[orig_img, "original image"],
...                             [sp_filter, "spline filter"]]):
...     ax[ind].imshow(data[0], cmap='gray_r')
...     ax[ind].set_title(data[1])
>>> plt.tight_layout()
>>> plt.show()
```



6.22.3 Filtering

<code>order_filter(a, domain, rank)</code>	Perform an order filter on an N-D array.
<code>medfilt(volume[, kernel_size])</code>	Perform a median filter on an N-dimensional array.
<code>medfilt2d(input[, kernel_size])</code>	Median filter a 2-dimensional array.
<code>wiener(im[, mysize, noise])</code>	Perform a Wiener filter on an N-dimensional array.
<code>symiirorder1(input, c0, z1[, precision])</code>	Implement a smoothing IIR filter with mirror-symmetric boundary conditions using a cascade of first-order sections.
<code>symiirorder2(input, r, omega[, precision])</code>	Implement a smoothing IIR filter with mirror-symmetric boundary conditions using a cascade of second-order sections.
<code>lfiltfilt(b, a, x[, axis, zi])</code>	Filter data along one-dimension with an IIR or FIR filter.
<code>lfiltic(b, a, y[, x])</code>	Construct initial conditions for <code>lfiltfilt</code> given input and output vectors.
<code>lfiltfilt_zi(b, a)</code>	Construct initial conditions for <code>lfiltfilt</code> for step response steady-state.
<code>filtfilt(b, a, x[, axis, padtype, padlen, ...])</code>	Apply a digital filter forward and backward to a signal.
<code>savgol_filter(x, window_length, polyorder[, ...])</code>	Apply a Savitzky-Golay filter to an array.
<code>deconvolve(signal, divisor)</code>	Deconvolves <code>divisor</code> out of <code>signal</code> using inverse filtering.
<code>sosfilt(sos, x[, axis, zi])</code>	Filter data along one dimension using cascaded second-order sections.
<code>sosfilt_zi(sos)</code>	Construct initial conditions for <code>sosfilt</code> for step response steady-state.
<code>sosfiltfilt(sos, x[, axis, padtype, padlen])</code>	A forward-backward digital filter using cascaded second-order sections.
<code>hilbert(x[, N, axis])</code>	Compute the analytic signal, using the Hilbert transform.
<code>hilbert2(x[, N])</code>	Compute the '2-D' analytic signal of <code>x</code>
<code>decimate(x, q[, n, ftype, axis, zero_phase])</code>	Downsample the signal after applying an anti-aliasing filter.
<code>detrend(data[, axis, type, bp, overwrite_data])</code>	Remove linear trend along <code>axis</code> from <code>data</code> .
<code>resample(x, num[, t, axis, window, domain])</code>	Resample <code>x</code> to <code>num</code> samples using Fourier method along the given <code>axis</code> .
<code>resample_poly(x, up, down[, axis, window, ...])</code>	Resample <code>x</code> along the given <code>axis</code> using polyphase filtering.
<code>upfirdn(h, x[, up, down, axis, mode, cval])</code>	Upsample, FIR filter, and downsample.

scipy.signal.order_filter

`scipy.signal.order_filter(a, domain, rank)`

Perform an order filter on an N-D array.

Perform an order filter on the array `in`. The `domain` argument acts as a mask centered over each pixel. The non-zero elements of `domain` are used to select elements surrounding each input pixel which are placed in a list. The list is sorted, and the output for that pixel is the element corresponding to `rank` in the sorted list.

Parameters

a	[ndarray] The N-dimensional input array.
domain	[array_like] A mask array with the same number of dimensions as <code>a</code> . Each dimension should have an odd number of elements.
rank	[int] A non-negative integer which selects the element from the sorted list (0 corresponds to the smallest element, 1 is the next smallest element, etc.).

Returns

out [ndarray] The results of the order filter in an array with the same shape as *a*.

Examples

```
>>> from scipy import signal
>>> x = np.arange(25).reshape(5, 5)
>>> domain = np.identity(3)
>>> x
array([[ 0,  1,  2,  3,  4],
       [ 5,  6,  7,  8,  9],
       [10, 11, 12, 13, 14],
       [15, 16, 17, 18, 19],
       [20, 21, 22, 23, 24]])
>>> signal.order_filter(x, domain, 0)
array([[ 0.,  0.,  0.,  0.,  0.],
       [ 0.,  0.,  1.,  2.,  0.],
       [ 0.,  5.,  6.,  7.,  0.],
       [ 0., 10., 11., 12.,  0.],
       [ 0.,  0.,  0.,  0.,  0.]])
>>> signal.order_filter(x, domain, 2)
array([[ 6.,  7.,  8.,  9.,  4.],
       [11., 12., 13., 14.,  9.],
       [16., 17., 18., 19., 14.],
       [21., 22., 23., 24., 19.],
       [20., 21., 22., 23., 24.]])
```

scipy.signal.medfilt

`scipy.signal.medfilt` (*volume*, *kernel_size=None*)

Perform a median filter on an N-dimensional array.

Apply a median filter to the input array using a local window-size given by *kernel_size*. The array will automatically be zero-padded.

Parameters

volume [array_like] An N-dimensional input array.

kernel_size [array_like, optional] A scalar or an N-length list giving the size of the median filter window in each dimension. Elements of *kernel_size* should be odd. If *kernel_size* is a scalar, then this scalar is used as the size in each dimension. Default size is 3 for each dimension.

Returns

out [ndarray] An array the same size as input containing the median filtered result.

Warns**UserWarning**

If array size is smaller than kernel size along any dimension

See also:

[`scipy.ndimage.median_filter`](#)

Notes

The more general function `scipy.ndimage.median_filter` has a more efficient implementation of a median filter and therefore runs much faster.

scipy.signal.medfilt2d

`scipy.signal.medfilt2d` (*input*, *kernel_size*=3)

Median filter a 2-dimensional array.

Apply a median filter to the *input* array using a local window-size given by *kernel_size* (must be odd). The array is zero-padded automatically.

Parameters

input [array_like] A 2-dimensional input array.

kernel_size [array_like, optional] A scalar or a list of length 2, giving the size of the median filter window in each dimension. Elements of *kernel_size* should be odd. If *kernel_size* is a scalar, then this scalar is used as the size in each dimension. Default is a kernel of size (3, 3).

Returns

out [ndarray] An array the same size as input containing the median filtered result.

See also:

[`scipy.ndimage.median_filter`](#)

Notes

The more general function `scipy.ndimage.median_filter` has a more efficient implementation of a median filter and therefore runs much faster.

scipy.signal.wiener

`scipy.signal.wiener` (*im*, *mysize*=None, *noise*=None)

Perform a Wiener filter on an N-dimensional array.

Apply a Wiener filter to the N-dimensional array *im*.

Parameters

im [ndarray] An N-dimensional array.

mysize [int or array_like, optional] A scalar or an N-length list giving the size of the Wiener filter window in each dimension. Elements of *mysize* should be odd. If *mysize* is a scalar, then this scalar is used as the size in each dimension.

noise [float, optional] The noise-power to use. If None, then noise is estimated as the average of the local variance of the input.

Returns

out [ndarray] Wiener filtered result with the same shape as *im*.

Notes


This implementation is similar to `wiener2` in Matlab/Octave. For more details see [1]

References

[1]

Examples

```
>>> from scipy.misc import face
>>> from scipy.signal.signaltools import wiener
>>> import matplotlib.pyplot as plt
>>> import numpy as np
>>> img = np.random.random((40, 40))    #Create a random image
>>> filtered_img = wiener(img, (5, 5))  #Filter the image
>>> f, (plot1, plot2) = plt.subplots(1, 2)
>>> plot1.imshow(img)
>>> plot2.imshow(filtered_img)
>>> plt.show()
```



`scipy.signal.symiirorder1`

`scipy.signal.symiirorder1` (*input*, *c0*, *z1*, *precision=-1.0*)

Implement a smoothing IIR filter with mirror-symmetric boundary conditions using a cascade of first-order sections. The second section uses a reversed sequence. This implements a system with the following transfer function and mirror-symmetric boundary conditions:

$$H(z) = \frac{c_0}{(1 - z_1/z)(1 - z_1 z)}$$

The resulting signal will have mirror symmetric boundary conditions as well.

Parameters

- input** [ndarray] The input signal.
- c0, z1** [scalar] Parameters in the transfer function.
- precision** : Specifies the precision for calculating initial conditions of the recursive filter based on mirror-symmetric input.

Returns

- output** [ndarray] The filtered signal.

scipy.signal.symiirorder2

`scipy.signal.symiirorder2` (*input, r, omega, precision=- 1.0*)

Implement a smoothing IIR filter with mirror-symmetric boundary conditions using a cascade of second-order sections. The second section uses a reversed sequence. This implements the following transfer function:

$$H(z) = \frac{cs^2}{(1 - a2/z - a3/z^2) (1 - a2 z - a3 z^2)}$$

where:

$$\begin{aligned} a2 &= (2 r \cos \omega) \\ a3 &= - r^2 \\ cs &= 1 - 2 r \cos \omega + r^2 \end{aligned}$$

Parameters

- input** [ndarray] The input signal.
- r, omega** [float] Parameters in the transfer function.
- precision** [float] Specifies the precision for calculating initial conditions of the recursive filter based on mirror-symmetric input.

Returns

- output** [ndarray] The filtered signal.

scipy.signal.lfilter

`scipy.signal.lfilter` (*b, a, x, axis=- 1, zi=None*)

Filter data along one-dimension with an IIR or FIR filter.

Filter a data sequence, *x*, using a digital filter. This works for many fundamental data types (including Object type). The filter is a direct form II transposed implementation of the standard difference equation (see Notes).

The function `sosfilt` (and filter design using `output='sos'`) should be preferred over `lfilter` for most filtering tasks, as second-order sections have fewer numerical problems.

Parameters

- b** [array_like] The numerator coefficient vector in a 1-D sequence.
- a** [array_like] The denominator coefficient vector in a 1-D sequence. If `a[0]` is not 1, then both *a* and *b* are normalized by `a[0]`.
- x** [array_like] An N-dimensional input array.

axis [int, optional] The axis of the input data array along which to apply the linear filter. The filter is applied to each subarray along this axis. Default is -1.

zi [array_like, optional] Initial conditions for the filter delays. It is a vector (or array of vectors for an N-dimensional input) of length $\max(\text{len}(a), \text{len}(b)) - 1$. If *zi* is None or is not given then initial rest is assumed. See *lfiltic* for more information.

Returns

y [array] The output of the digital filter.

zf [array, optional] If *zi* is None, this is not returned, otherwise, *zf* holds the final filter delay values.

See also:*lfiltic*

Construct initial conditions for *lfilter*.

lfilter_zi

Compute initial state (steady state of step response) for *lfilter*.

filtfilt

A forward-backward filter, to obtain a filter with linear phase.

savgol_filter

A Savitzky-Golay filter.

sosfilt

Filter data using cascaded second-order sections.

sosfiltfilt

A forward-backward filter using second-order sections.

Notes

The filter function is implemented as a direct II transposed structure. This means that the filter implements:

$$a[0]*y[n] = b[0]*x[n] + b[1]*x[n-1] + \dots + b[M]*x[n-M] \\ - a[1]*y[n-1] - \dots - a[N]*y[n-N]$$

where *M* is the degree of the numerator, *N* is the degree of the denominator, and *n* is the sample number. It is implemented using the following difference equations (assuming *M* = *N*):

$$a[0]*y[n] = b[0] * x[n] + d[0][n-1] \\ d[0][n] = b[1] * x[n] - a[1] * y[n] + d[1][n-1] \\ d[1][n] = b[2] * x[n] - a[2] * y[n] + d[2][n-1] \\ \dots \\ d[N-2][n] = b[N-1]*x[n] - a[N-1]*y[n] + d[N-1][n-1] \\ d[N-1][n] = b[N] * x[n] - a[N] * y[n]$$

where *d* are the state variables.

The rational transfer function describing this filter in the z-transform domain is:

$$Y(z) = \frac{b[0] + b[1]z^{-1} + \dots + b[M]z^{-M}}{a[0] + a[1]z^{-1} + \dots + a[N]z^{-N}} X(z)$$

Examples

Generate a noisy signal to be filtered:

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
>>> t = np.linspace(-1, 1, 201)
>>> x = (np.sin(2*np.pi*0.75*t*(1-t) + 2.1) +
...      0.1*np.sin(2*np.pi*1.25*t + 1) +
...      0.18*np.cos(2*np.pi*3.85*t))
>>> xn = x + np.random.randn(len(t)) * 0.08
```

Create an order 3 lowpass butterworth filter:

```
>>> b, a = signal.butter(3, 0.05)
```

Apply the filter to xn. Use lfilter_zi to choose the initial condition of the filter:

```
>>> zi = signal.lfilter_zi(b, a)
>>> z, _ = signal.lfilter(b, a, xn, zi=zi*xn[0])
```

Apply the filter again, to have a result filtered at an order the same as filtfilt:


```
>>> z2, _ = signal.lfilter(b, a, z, zi=zi*z[0])
```

Use filtfilt to apply the filter:

```
>>> y = signal.filtfilt(b, a, xn)
```

Plot the original signal and the various filtered versions:

```
>>> plt.figure
>>> plt.plot(t, xn, 'b', alpha=0.75)
>>> plt.plot(t, z, 'r--', t, z2, 'r', t, y, 'k')
>>> plt.legend(('noisy signal', 'lfilter, once', 'lfilter, twice',
...          'filtfilt'), loc='best')
>>> plt.grid(True)
>>> plt.show()
```

scipy.signal.lfiltic

`scipy.signal.lfiltic` (*b*, *a*, *y*, *x=None*)

Construct initial conditions for `lfilter` given input and output vectors.

Given a linear filter (*b*, *a*) and initial conditions on the output *y* and the input *x*, return the initial conditions on the state vector *zi* which is used by `lfilter` to generate the output given the input.

Parameters

- b** [array_like] Linear filter term.
- a** [array_like] Linear filter term.
- y** [array_like] Initial conditions.
If $N = \text{len}(a) - 1$, then $y = \{y[-1], y[-2], \dots, y[-N]\}$.
If *y* is too short, it is padded with zeros.
- x** [array_like, optional] Initial conditions.
If $M = \text{len}(b) - 1$, then $x = \{x[-1], x[-2], \dots, x[-M]\}$.
If *x* is not given, its initial conditions are assumed zero.
If *x* is too short, it is padded with zeros.

Returns

- zi** [ndarray] The state vector $z_i = \{z_{-0}[-1], z_{-1}[-1], \dots, z_{-K-1}[-1]\}$, where $K = \max(M, N)$.

See also:

`lfilter`, `lfilter_zi`

scipy.signal.lfilter_zi

`scipy.signal.lfilter_zi(b, a)`

Construct initial conditions for `lfilter` for step response steady-state.

Compute an initial state `zi` for the `lfilter` function that corresponds to the steady state of the step response.

A typical use of this function is to set the initial state so that the output of the filter starts at the same value as the first element of the signal to be filtered.

Parameters

b, a [array_like (1-D)] The IIR filter coefficients. See `lfilter` for more information.

Returns

zi [1-D ndarray] The initial state for the filter.

See also:

`lfilter`, `lfiltic`, `filtfilt`

Notes

A linear filter with order m has a state space representation (A, B, C, D) , for which the output y of the filter can be expressed as:

$$\begin{aligned} z(n+1) &= A*z(n) + B*x(n) \\ y(n) &= C*z(n) + D*x(n) \end{aligned}$$

where $z(n)$ is a vector of length m , A has shape (m, m) , B has shape $(m, 1)$, C has shape $(1, m)$ and D has shape $(1, 1)$ (assuming $x(n)$ is a scalar). `lfilter_zi` solves:

$$zi = A*zi + B$$

In other words, it finds the initial condition for which the response to an input of all ones is a constant.

Given the filter coefficients a and b , the state space matrices for the transposed direct form II implementation of the linear filter, which is the implementation used by `scipy.signal.lfilter`, are:

$$\begin{aligned} A &= \text{scipy.linalg.companion}(a).T \\ B &= b[1:] - a[1:]*b[0] \end{aligned}$$

assuming $a[0]$ is 1.0; if $a[0]$ is not 1, a and b are first divided by $a[0]$.

Examples

The following code creates a lowpass Butterworth filter. Then it applies that filter to an array whose values are all 1.0; the output is also all 1.0, as expected for a lowpass filter. If the `zi` argument of `lfilter` had not been given, the output would have shown the transient signal.

```
>>> from numpy import array, ones
>>> from scipy.signal import lfilter, lfilter_zi, butter
>>> b, a = butter(5, 0.25)
>>> zi = lfilter_zi(b, a)
>>> y, zo = lfilter(b, a, ones(10), zi=zi)
```

(continues on next page)

(continued from previous page)

```
>>> y
array([1., 1., 1., 1., 1., 1., 1., 1., 1., 1.])
```

Another example:

```
>>> x = array([0.5, 0.5, 0.5, 0.0, 0.0, 0.0, 0.0])
>>> y, zf = lfilter(b, a, x, zi=zi*x[0])
>>> y
array([ 0.5          ,  0.5          ,  0.5          ,  0.49836039,  0.48610528,
        0.44399389,  0.35505241])
```

Note that the *zi* argument to `lfilter` was computed using `lfilter_zi` and scaled by `x[0]`. Then the output `y` has no transient until the input drops from 0.5 to 0.0.

scipy.signal.filtfilt

`scipy.signal.filtfilt` (*b, a, x, axis=-1, padtype='odd', padlen=None, method='pad', irlen=None*)

Apply a digital filter forward and backward to a signal.

This function applies a linear digital filter twice, once forward and once backwards. The combined filter has zero phase and a filter order twice that of the original.

The function provides options for handling the edges of the signal.

The function `sosfiltfilt` (and filter design using `output='sos'`) should be preferred over `filtfilt` for most filtering tasks, as second-order sections have fewer numerical problems.

Parameters

b	[(N,) array_like] The numerator coefficient vector of the filter.
a	[(N,) array_like] The denominator coefficient vector of the filter. If <code>a[0]</code> is not 1, then both <i>a</i> and <i>b</i> are normalized by <code>a[0]</code> .
x	[array_like] The array of data to be filtered.
axis	[int, optional] The axis of <i>x</i> to which the filter is applied. Default is -1.
padtype	[str or None, optional] Must be 'odd', 'even', 'constant', or None. This determines the type of extension to use for the padded signal to which the filter is applied. If <i>padtype</i> is None, no padding is used. The default is 'odd'.
padlen	[int or None, optional] The number of elements by which to extend <i>x</i> at both ends of <i>axis</i> before applying the filter. This value must be less than <code>x.shape[axis] - 1</code> . <code>padlen=0</code> implies no padding. The default value is <code>3 * max(len(a), len(b))</code> .
method	[str, optional] Determines the method for handling the edges of the signal, either "pad" or "gust". When <i>method</i> is "pad", the signal is padded; the type of padding is determined by <i>padtype</i> and <i>padlen</i> , and <i>irlen</i> is ignored. When <i>method</i> is "gust", Gustafsson's method is used, and <i>padtype</i> and <i>padlen</i> are ignored.
irlen	[int or None, optional] When <i>method</i> is "gust", <i>irlen</i> specifies the length of the impulse response of the filter. If <i>irlen</i> is None, no part of the impulse response is ignored. For a long signal, specifying <i>irlen</i> can significantly improve the performance of the filter.

Returns

y [ndarray] The filtered output with the same shape as *x*.

See also:

`sosfiltfilt`, `lfilter_zi`, `lfilter`, `lfiltic`, `savgol_filter`, `sosfilt`

Notes

When *method* is “pad”, the function pads the data along the given axis in one of three ways: odd, even or constant. The odd and even extensions have the corresponding symmetry about the end point of the data. The constant extension extends the data with the values at the end points. On both the forward and backward passes, the initial condition of the filter is found by using *lfilter_zi* and scaling it by the end point of the extended data.

When *method* is “gust”, Gustafsson’s method [1] is used. Initial conditions are chosen for the forward and backward passes so that the forward-backward filter gives the same result as the backward-forward filter.

The option to use Gustafsson’s method was added in *scipy* version 0.16.0.

References

[1]

Examples

The examples will use several functions from *scipy.signal*.

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

First we create a one second signal that is the sum of two pure sine waves, with frequencies 5 Hz and 250 Hz, sampled at 2000 Hz.

```
>>> t = np.linspace(0, 1.0, 2001)
>>> xlow = np.sin(2 * np.pi * 5 * t)
>>> xhigh = np.sin(2 * np.pi * 250 * t)
>>> x = xlow + xhigh
```

Now create a lowpass Butterworth filter with a cutoff of 0.125 times the Nyquist frequency, or 125 Hz, and apply it to *x* with *filtfilt*. The result should be approximately *xlow*, with no phase shift.

```
>>> b, a = signal.butter(8, 0.125)
>>> y = signal.filtfilt(b, a, x, padlen=150)
>>> np.abs(y - xlow).max()
9.1086182074789912e-06
```

We get a fairly clean result for this artificial example because the odd extension is exact, and with the moderately long padding, the filter’s transients have dissipated by the time the actual data is reached. In general, transient effects at the edges are unavoidable.

The following example demonstrates the option *method="gust"*.

First, create a filter.


```
>>> b, a = signal.ellip(4, 0.01, 120, 0.125) # Filter to be applied.
>>> np.random.seed(123456)
```

sig is a random input signal to be filtered.

```
>>> n = 60
>>> sig = np.random.randn(n)**3 + 3*np.random.randn(n).cumsum()
```

Apply `filtfilt` to `sig`, once using the Gustafsson method, and once using padding, and plot the results for comparison.

```
>>> fgust = signal.filtfilt(b, a, sig, method="gust")
>>> fpad = signal.filtfilt(b, a, sig, padlen=50)
>>> plt.plot(sig, 'k-', label='input')
>>> plt.plot(fgust, 'b-', linewidth=4, label='gust')
>>> plt.plot(fpad, 'c-', linewidth=1.5, label='pad')
>>> plt.legend(loc='best')
>>> plt.show()
```



The `irlen` argument can be used to improve the performance of Gustafsson's method.

Estimate the impulse response length of the filter.

```
>>> z, p, k = signal.tf2zpk(b, a)
>>> eps = 1e-9
>>> r = np.max(np.abs(p))
>>> approx_impulse_len = int(np.ceil(np.log(eps) / np.log(r)))
>>> approx_impulse_len
137
```

Apply the filter to a longer signal, with and without the `irlen` argument. The difference between `y1` and `y2` is small. For long signals, using `irlen` gives a significant performance improvement.

```
>>> x = np.random.randn(5000)
>>> y1 = signal.filtfilt(b, a, x, method='gust')
>>> y2 = signal.filtfilt(b, a, x, method='gust', irlen=approx_impulse_len)
>>> print(np.max(np.abs(y1 - y2)))
1.80056858312e-10
```

scipy.signal.savgol_filter

```
scipy.signal.savgol_filter(x, window_length, polyorder, deriv=0, delta=1.0, axis=-1,
                           mode='interp', cval=0.0)
```

Apply a Savitzky-Golay filter to an array.

This is a 1-D filter. If *x* has dimension greater than 1, *axis* determines the axis along which the filter is applied.

Parameters

- x** [array_like] The data to be filtered. If *x* is not a single or double precision floating point array, it will be converted to type `numpy.float64` before filtering.
- window_length** [int] The length of the filter window (i.e., the number of coefficients). *window_length* must be a positive odd integer. If *mode* is 'interp', *window_length* must be less than or equal to the size of *x*.
- polyorder** [int] The order of the polynomial used to fit the samples. *polyorder* must be less than *window_length*.
- deriv** [int, optional] The order of the derivative to compute. This must be a nonnegative integer. The default is 0, which means to filter the data without differentiating.
- delta** [float, optional] The spacing of the samples to which the filter will be applied. This is only used if *deriv* > 0. Default is 1.0.
- axis** [int, optional] The axis of the array *x* along which the filter is to be applied. Default is -1.
- mode** [str, optional] Must be 'mirror', 'constant', 'nearest', 'wrap' or 'interp'. This determines the type of extension to use for the padded signal to which the filter is applied. When *mode* is 'constant', the padding value is given by *cval*. See the Notes for more details on 'mirror', 'constant', 'wrap', and 'nearest'. When the 'interp' mode is selected (the default), no extension is used. Instead, a degree *polyorder* polynomial is fit to the last *window_length* // 2 output values of the edges, and this polynomial is used to evaluate the last *window_length* // 2 output values.
- cval** [scalar, optional] Value to fill past the edges of the input if *mode* is 'constant'. Default is 0.0.

Returns

- y** [ndarray, same shape as *x*] The filtered data.

See also:

[*savgol_coeffs*](#)

Notes

Details on the *mode* options:

'mirror':

Repeats the values at the edges in reverse order. The value closest to the edge is not included.

'nearest':

The extension contains the nearest input value.

'constant':

The extension contains the value given by the *cval* argument.

'wrap':

The extension contains the values from the other end of the array.

For example, if the input is [1, 2, 3, 4, 5, 6, 7, 8], and *window_length* is 7, the following shows the extended data for the various *mode* options (assuming *cval* is 0):

mode	Ext			Input								Ext		
	4	3	2	1	2	3	4	5	6	7	8	7	6	5
'mirror'	4	3	2	1	2	3	4	5	6	7	8	7	6	5
'nearest'	1	1	1	1	2	3	4	5	6	7	8	8	8	8
'constant'	0	0	0	1	2	3	4	5	6	7	8	0	0	0
'wrap'	6	7	8	1	2	3	4	5	6	7	8	1	2	3

New in version 0.14.0.

Examples

```
>>> from scipy.signal import savgol_filter
>>> np.set_printoptions(precision=2) # For compact display.
>>> x = np.array([2, 2, 5, 2, 1, 0, 1, 4, 9])
```

Filter with a window length of 5 and a degree 2 polynomial. Use the defaults for all other parameters.

```
>>> savgol_filter(x, 5, 2)
array([1.66, 3.17, 3.54, 2.86, 0.66, 0.17, 1. , 4. , 9. ])
```

Note that the last five values in `x` are samples of a parabola, so when `mode='interp'` (the default) is used with `polyorder=2`, the last three values are unchanged. Compare that to, for example, `mode='nearest'`:

```
>>> savgol_filter(x, 5, 2, mode='nearest')
array([1.74, 3.03, 3.54, 2.86, 0.66, 0.17, 1. , 4.6 , 7.97])
```

scipy.signal.deconvolve

`scipy.signal.deconvolve` (*signal, divisor*)

Deconvolves divisor out of signal using inverse filtering.

Returns the quotient and remainder such that `signal = convolve(divisor, quotient) + remainder`

Parameters

signal [array_like] Signal data, typically a recorded signal
divisor [array_like] Divisor data, typically an impulse response or filter that was applied to the original signal

Returns

quotient [ndarray] Quotient, typically the recovered original signal
remainder [ndarray] Remainder

See also:

`numpy.polydiv`

performs polynomial division (same operation, but also accepts `poly1d` objects)

Examples

Deconvolve a signal that's been filtered:

```
>>> from scipy import signal
>>> original = [0, 1, 0, 0, 1, 1, 0, 0]
>>> impulse_response = [2, 1]
>>> recorded = signal.convolve(impulse_response, original)
>>> recorded
array([0, 2, 1, 0, 2, 3, 1, 0, 0])
>>> recovered, remainder = signal.deconvolve(recorded, impulse_response)
>>> recovered
array([ 0.,  1.,  0.,  0.,  1.,  1.,  0.,  0.])
```

scipy.signal.sosfilt

`scipy.signal.sosfilt` (*sos*, *x*, *axis=-1*, *zi=None*)

Filter data along one dimension using cascaded second-order sections.

Filter a data sequence, *x*, using a digital IIR filter defined by *sos*.

Parameters

sos	[array_like] Array of second-order filter coefficients, must have shape (<i>n_sections</i> , 6). Each row corresponds to a second-order section, with the first three columns providing the numerator coefficients and the last three providing the denominator coefficients.
x	[array_like] An N-dimensional input array.
axis	[int, optional] The axis of the input data array along which to apply the linear filter. The filter is applied to each subarray along this axis. Default is -1.
zi	[array_like, optional] Initial conditions for the cascaded filter delays. It is a (at least 2D) vector of shape (<i>n_sections</i> , ..., 2, ...), where ..., 2, ... denotes the shape of <i>x</i> , but with <i>x.shape[axis]</i> replaced by 2. If <i>zi</i> is None or is not given then initial rest (i.e. all zeros) is assumed. Note that these initial conditions are <i>not</i> the same as the initial conditions given by <code>lfiltic</code> or <code>lfilter_zi</code> .

Returns

y	[ndarray] The output of the digital filter.
zf	[ndarray, optional] If <i>zi</i> is None, this is not returned, otherwise, <i>zf</i> holds the final filter delay values.

See also:

[zpk2sos](#), [sos2zpk](#), [sosfilt_zi](#), [sosfiltfilt](#), [sosfreqz](#)

Notes


The filter function is implemented as a series of second-order filters with direct-form II transposed structure. It is designed to minimize numerical precision errors for high-order filters.

New in version 0.16.0.

Examples

Plot a 13th-order filter's impulse response using both `lfilter` and `sosfilt`, showing the instability that results from trying to do a 13th-order filter in a single stage (the numerical error pushes some poles outside of the unit circle):

```
>>> import matplotlib.pyplot as plt
>>> from scipy import signal
>>> b, a = signal.ellip(13, 0.009, 80, 0.05, output='ba')
>>> sos = signal.ellip(13, 0.009, 80, 0.05, output='sos')
>>> x = signal.unit_impulse(700)
>>> y_tf = signal.lfilter(b, a, x)
>>> y_sos = signal.sosfilt(sos, x)
>>> plt.plot(y_tf, 'r', label='TF')
>>> plt.plot(y_sos, 'k', label='SOS')
>>> plt.legend(loc='best')
>>> plt.show()
```



scipy.signal.sosfilt_zi

`scipy.signal.sosfilt_zi(sos)`

Construct initial conditions for `sosfilt` for step response steady-state.

Compute an initial state `zi` for the `sosfilt` function that corresponds to the steady state of the step response.

A typical use of this function is to set the initial state so that the output of the filter starts at the same value as the first element of the signal to be filtered.

Parameters

sos [array_like] Array of second-order filter coefficients, must have shape $(n_sections, 6)$. See `sosfilt` for the SOS filter format specification.

Returns

zi [ndarray] Initial conditions suitable for use with `sosfilt`, shape $(n_sections, 2)$.

See also:

sosfilt, *zpk2sos*

Notes

New in version 0.16.0.


Examples

Filter a rectangular pulse that begins at time 0, with and without the use of the *zi* argument of *scipy.signal.sosfilt*.

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> sos = signal.butter(9, 0.125, output='sos')
>>> zi = signal.sosfilt_zi(sos)
>>> x = (np.arange(250) < 100).astype(int)
>>> f1 = signal.sosfilt(sos, x)
>>> f2, zo = signal.sosfilt(sos, x, zi=zi)
```

```
>>> plt.plot(x, 'k--', label='x')
>>> plt.plot(f1, 'b', alpha=0.5, linewidth=2, label='filtered')
>>> plt.plot(f2, 'g', alpha=0.25, linewidth=4, label='filtered with zi')
>>> plt.legend(loc='best')
>>> plt.show()
```



scipy.signal.sosfiltfilt

`scipy.signal.sosfiltfilt` (*sos*, *x*, *axis=-1*, *padtype='odd'*, *padlen=None*)

A forward-backward digital filter using cascaded second-order sections.

See `filtfilt` for more complete information about this method.

Parameters

sos	[array_like] Array of second-order filter coefficients, must have shape $(n_sections, 6)$. Each row corresponds to a second-order section, with the first three columns providing the numerator coefficients and the last three providing the denominator coefficients.
x	[array_like] The array of data to be filtered.
axis	[int, optional] The axis of <i>x</i> to which the filter is applied. Default is -1.
padtype	[str or None, optional] Must be 'odd', 'even', 'constant', or None. This determines the type of extension to use for the padded signal to which the filter is applied. If <i>padtype</i> is None, no padding is used. The default is 'odd'.
padlen	[int or None, optional] The number of elements by which to extend <i>x</i> at both ends of <i>axis</i> before applying the filter. This value must be less than $x.shape[axis] - 1$. <i>padlen</i> =0 implies no padding. The default value is:

```
3 * (2 * len(sos) + 1 - min((sos[:, 2] == 0).sum(),
                             (sos[:, 5] == 0).sum()))
```

The extra subtraction at the end attempts to compensate for poles and zeros at the origin (e.g. for odd-order filters) to yield equivalent estimates of *padlen* to those of `filtfilt` for second-order section filters built with `scipy.signal` functions.

Returns

y [ndarray] The filtered output with the same shape as *x*.

See also:

`filtfilt`, `sosfilt`, `sosfilt_zi`, `sosfreqz`

Notes

New in version 0.18.0.

Examples

```
>>> from scipy.signal import sosfiltfilt, butter
>>> import matplotlib.pyplot as plt
```

Create an interesting signal to filter.

```
>>> n = 201
>>> t = np.linspace(0, 1, n)
>>> np.random.seed(123)
>>> x = 1 + (t < 0.5) - 0.25*t**2 + 0.05*np.random.randn(n)
```

Create a lowpass Butterworth filter, and use it to filter *x*.


```
>>> sos = butter(4, 0.125, output='sos')
>>> y = sosfiltfilt(sos, x)
```

For comparison, apply an 8th order filter using `sosfilt`. The filter is initialized using the mean of the first four values of x .

```
>>> from scipy.signal import sosfilt, sosfilt_zi
>>> sos8 = butter(8, 0.125, output='sos')
>>> zi = x[:4].mean() * sosfilt_zi(sos8)
>>> y2, zo = sosfilt(sos8, x, zi=zi)
```

Plot the results. Note that the phase of y matches the input, while $y2$ has a significant phase delay.

```
>>> plt.plot(t, x, alpha=0.5, label='x(t)')
>>> plt.plot(t, y, label='y(t)')
>>> plt.plot(t, y2, label='y2(t)')
>>> plt.legend(framealpha=1, shadow=True)
>>> plt.grid(alpha=0.25)
>>> plt.xlabel('t')
>>> plt.show()
```



scipy.signal.hilbert

`scipy.signal.hilbert` (x , $N=None$, $axis=-1$)

Compute the analytic signal, using the Hilbert transform.

The transformation is done along the last axis by default.

Parameters

x [array_like] Signal data. Must be real.
N [int, optional] Number of Fourier components. Default: `x.shape[axis]`
axis [int, optional] Axis along which to do the transformation. Default: -1.

Returns

xa [ndarray] Analytic signal of x , of each 1-D array along $axis$

Notes

The analytic signal $x_a(t)$ of signal $x(t)$ is:

$$x_a = F^{-1}(F(x)2U) = x + iy$$

where F is the Fourier transform, U the unit step function, and y the Hilbert transform of x . [1]

In other words, the negative half of the frequency spectrum is zeroed out, turning the real-valued signal into a complex signal. The Hilbert transformed signal can be obtained from `np.imag(hilbert(x))`, and the original signal from `np.real(hilbert(x))`.

References

[1], [2], [3]

Examples

In this example we use the Hilbert transform to determine the amplitude envelope and instantaneous frequency of an amplitude-modulated signal.

```
>>> import numpy as np
>>> import matplotlib.pyplot as plt
>>> from scipy.signal import hilbert, chirp
```

```
>>> duration = 1.0
>>> fs = 400.0
>>> samples = int(fs*duration)
>>> t = np.arange(samples) / fs
```

We create a chirp of which the frequency increases from 20 Hz to 100 Hz and apply an amplitude modulation.

```
>>> signal = chirp(t, 20.0, t[-1], 100.0)
>>> signal *= (1.0 + 0.5 * np.sin(2.0*np.pi*3.0*t) )
```

The amplitude envelope is given by magnitude of the analytic signal. The instantaneous frequency can be obtained by differentiating the instantaneous phase in respect to time. The instantaneous phase corresponds to the phase angle of the analytic signal.


```
>>> analytic_signal = hilbert(signal)
>>> amplitude_envelope = np.abs(analytic_signal)
>>> instantaneous_phase = np.unwrap(np.angle(analytic_signal))
>>> instantaneous_frequency = (np.diff(instantaneous_phase) /
...                             (2.0*np.pi) * fs)
```

```
>>> fig = plt.figure()
>>> ax0 = fig.add_subplot(211)
>>> ax0.plot(t, signal, label='signal')
>>> ax0.plot(t, amplitude_envelope, label='envelope')
>>> ax0.set_xlabel("time in seconds")
>>> ax0.legend()
>>> ax1 = fig.add_subplot(212)
```

(continues on next page)

(continued from previous page)

```
>>> ax1.plot(t[1:], instantaneous_frequency)
>>> ax1.set_xlabel("time in seconds")
>>> ax1.set_ylim(0.0, 120.0)
```



scipy.signal.hilbert2

`scipy.signal.hilbert2` (*x*, *N=None*)

Compute the '2-D' analytic signal of *x*

Parameters

x [array_like] 2-D signal data.
N [int or tuple of two ints, optional] Number of Fourier components. Default is `x.shape`

Returns

xa [ndarray] Analytic signal of *x* taken along axes (0,1).

References

[1]

scipy.signal.decimate

`scipy.signal.decimate` (*x*, *q*, *n=None*, *ftype='iir'*, *axis=-1*, *zero_phase=True*)

Downsample the signal after applying an anti-aliasing filter.

By default, an order 8 Chebyshev type I filter is used. A 30 point FIR filter with Hamming window is used if *ftype* is 'fir'.

Parameters

x [array_like] The signal to be downsampled, as an N-dimensional array.

q	[int] The downsampling factor. When using IIR downsampling, it is recommended to call <code>decimate</code> multiple times for downsampling factors higher than 13.
n	[int, optional] The order of the filter (1 less than the length for 'fir'). Defaults to 8 for 'iir' and 20 times the downsampling factor for 'fir'.
ftype	[str {'iir', 'fir'} or <code>dlti</code> instance, optional] If 'iir' or 'fir', specifies the type of lowpass filter. If an instance of an <code>dlti</code> object, uses that object to filter before downsampling.
axis	[int, optional] The axis along which to decimate.
zero_phase	[bool, optional] Prevent phase shift by filtering with <code>filtfilt</code> instead of <code>lfilter</code> when using an IIR filter, and shifting the outputs back by the filter's group delay when using an FIR filter. The default value of <code>True</code> is recommended, since a phase shift is generally not desired. New in version 0.18.0.

Returns

y	[ndarray] The down-sampled signal.
----------	------------------------------------

See also:**`resample`**

Resample up or down using the FFT method.

`resample_poly`

Resample using polyphase filtering and an FIR filter.

Notes

The `zero_phase` keyword was added in 0.18.0. The possibility to use instances of `dlti` as `ftype` was added in 0.18.0.

`scipy.signal.detrend`

`scipy.signal.detrend` (*data*, *axis=-1*, *type='linear'*, *bp=0*, *overwrite_data=False*)

Remove linear trend along axis from data.

Parameters

data	[array_like] The input data.
axis	[int, optional] The axis along which to detrend the data. By default this is the last axis (-1).
type	[{'linear', 'constant'}, optional] The type of detrending. If <code>type == 'linear'</code> (default), the result of a linear least-squares fit to <i>data</i> is subtracted from <i>data</i> . If <code>type == 'constant'</code> , only the mean of <i>data</i> is subtracted.
bp	[array_like of ints, optional] A sequence of break points. If given, an individual linear fit is performed for each part of <i>data</i> between two break points. Break points are specified as indices into <i>data</i> . This parameter only has an effect when <code>type == 'linear'</code> .
overwrite_data	[bool, optional] If <code>True</code> , perform in place detrending and avoid a copy. Default is <code>False</code>

Returns

ret	[ndarray] The detrended input data.
------------	-------------------------------------

Examples

```

>>> from scipy import signal
>>> randgen = np.random.RandomState(9)
>>> npoints = 1000
>>> noise = randgen.randn(npoints)
>>> x = 3 + 2*np.linspace(0, 1, npoints) + noise
>>> (signal.detrend(x) - noise).max() < 0.01
True

```

scipy.signal.resample

`scipy.signal.resample(x, num, t=None, axis=0, window=None, domain='time')`

Resample x to num samples using Fourier method along the given axis.

The resampled signal starts at the same value as x but is sampled with a spacing of $\text{len}(x) / num * (\text{spacing of } x)$. Because a Fourier method is used, the signal is assumed to be periodic.

Parameters

x	[array_like] The data to be resampled.
num	[int] The number of samples in the resampled signal.
t	[array_like, optional] If t is given, it is assumed to be the equally spaced sample positions associated with the signal data in x .
axis	[int, optional] The axis of x that is resampled. Default is 0.
window	[array_like, callable, string, float, or tuple, optional] Specifies the window applied to the signal in the Fourier domain. See below for details.
domain	[string, optional] A string indicating the domain of the input x : <code>time</code> Consider the input x as time-domain (Default), <code>freq</code> Consider the input x as frequency-domain.

Returns

resampled_x or (**resampled_x**, **resampled_t**)

Either the resampled array, or, if t was given, a tuple containing the resampled array and the corresponding resampled positions.

See also:

[*decimate*](#)

Downsample the signal after applying an FIR or IIR filter.

[*resample_poly*](#)

Resample using polyphase filtering and an FIR filter.

Notes

The argument *window* controls a Fourier-domain window that tapers the Fourier spectrum before zero-padding to alleviate ringing in the resampled values for sampled signals you didn't intend to be interpreted as band-limited.

If *window* is a function, then it is called with a vector of inputs indicating the frequency bins (i.e. `fft-freq(x.shape[axis])`).

If *window* is an array of the same length as $x.\text{shape}[\text{axis}]$ it is assumed to be the window to be applied directly in the Fourier domain (with dc and low-frequency first).

For any other type of *window*, the function `scipy.signal.get_window` is called to generate the window.

The first sample of the returned vector is the same as the first sample of the input vector. The spacing between samples is changed from dx to $dx * \text{len}(x) / \text{num}$.

If t is not None, then it is used solely to calculate the resampled positions *resampled_t*

As noted, *resample* uses FFT transformations, which can be very slow if the number of input or output samples is large and prime; see `scipy.fft.fft`.


Examples

Note that the end of the resampled data rises to meet the first sample of the next cycle:

```
>>> from scipy import signal
```

```
>>> x = np.linspace(0, 10, 20, endpoint=False)
>>> y = np.cos(-x**2/6.0)
>>> f = signal.resample(y, 100)
>>> xnew = np.linspace(0, 10, 100, endpoint=False)
```

```
>>> import matplotlib.pyplot as plt
>>> plt.plot(x, y, 'go-', xnew, f, 'b-', 10, y[0], 'ro')
>>> plt.legend(['data', 'resampled'], loc='best')
>>> plt.show()
```



scipy.signal.resample_poly

`scipy.signal.resample_poly(x, up, down, axis=0, window='kaiser', 5.0, padtype='constant', cval=None)`

Resample x along the given axis using polyphase filtering.

The signal x is upsampled by the factor up , a zero-phase low-pass FIR filter is applied, and then it is downsampled by the factor $down$. The resulting sample rate is $up / down$ times the original sample rate. By default, values beyond the boundary of the signal are assumed to be zero during the filtering step.

Parameters

x	[array_like] The data to be resampled.
up	[int] The upsampling factor.
down	[int] The downsampling factor.
axis	[int, optional] The axis of x that is resampled. Default is 0.
window	[string, tuple, or array_like, optional] Desired window to use to design the low-pass filter, or the FIR filter coefficients to employ. See below for details.
padtype	[string, optional] <i>constant</i> , <i>line</i> , <i>mean</i> , <i>median</i> , <i>maximum</i> , <i>minimum</i> or any of the other signal extension modes supported by <code>scipy.signal.upfirdn</code> . Changes assumptions on values beyond the boundary. If <i>constant</i> , assumed to be <i>cval</i> (default zero). If <i>line</i> assumed to continue a linear trend defined by the first and last points. <i>mean</i> , <i>median</i> , <i>maximum</i> and <i>minimum</i> work as in <code>np.pad</code> and assume that the values beyond the boundary are the mean, median, maximum or minimum respectively of the array along the axis. New in version 1.4.0.
cval	[float, optional] Value to use if <i>padtype</i> ='constant'. Default is zero. New in version 1.4.0.

Returns

resampled_x	[array] The resampled array.
--------------------	------------------------------

See also:

decimate

Downsample the signal after applying an FIR or IIR filter.

resample

Resample up or down using the FFT method.

Notes

This polyphase method will likely be faster than the Fourier method in `scipy.signal.resample` when the number of samples is large and prime, or when the number of samples is large and up and $down$ share a large greatest common denominator. The length of the FIR filter used will depend on $\max(up, down) // \gcd(up, down)$, and the number of operations during polyphase filtering will depend on the filter length and $down$ (see `scipy.signal.upfirdn` for details).

The argument *window* specifies the FIR low-pass filter design.

If *window* is an array_like it is assumed to be the FIR filter coefficients. Note that the FIR filter is applied after the upsampling step, so it should be designed to operate on a signal at a sampling frequency higher than the original by a factor of $up/\gcd(up, down)$. This function's output will be centered with respect to this array, so it is best to pass a symmetric filter with an odd number of samples if, as is usually the case, a zero-phase filter is desired.

For any other type of *window*, the functions `scipy.signal.get_window` and `scipy.signal.firwin` are called to generate the appropriate filter coefficients.

The first sample of the returned vector is the same as the first sample of the input vector. The spacing between samples is changed from `dx` to `dx * down / float(up)`.


Examples

By default, the end of the resampled data rises to meet the first sample of the next cycle for the FFT method, and gets closer to zero for the polyphase method:

```
>>> from scipy import signal
```

```
>>> x = np.linspace(0, 10, 20, endpoint=False)
>>> y = np.cos(-x**2/6.0)
>>> f_fft = signal.resample(y, 100)
>>> f_poly = signal.resample_poly(y, 100, 20)
>>> xnew = np.linspace(0, 10, 100, endpoint=False)
```

```
>>> import matplotlib.pyplot as plt
>>> plt.plot(xnew, f_fft, 'b.-', xnew, f_poly, 'r.-')
>>> plt.plot(x, y, 'ko-')
>>> plt.plot(10, y[0], 'bo', 10, 0., 'ro') # boundaries
>>> plt.legend(['resample', 'resamp_poly', 'data'], loc='best')
>>> plt.show()
```



This default behaviour can be changed by using the `padtype` option:

```
>>> import numpy as np
>>> from scipy import signal
```

```
>>> N = 5
>>> x = np.linspace(0, 1, N, endpoint=False)
```

(continues on next page)

(continued from previous page)

```

>>> y = 2 + x**2 - 1.7*np.sin(x) + .2*np.cos(11*x)
>>> y2 = 1 + x**3 + 0.1*np.sin(x) + .1*np.cos(11*x)
>>> Y = np.stack([y, y2], axis=-1)
>>> up = 4
>>> xr = np.linspace(0, 1, N*up, endpoint=False)

```

```


>>> y2 = signal.resample_poly(Y, up, 1, padtype='constant')
>>> y3 = signal.resample_poly(Y, up, 1, padtype='mean')
>>> y4 = signal.resample_poly(Y, up, 1, padtype='line')

```

```

>>> import matplotlib.pyplot as plt
>>> for i in [0,1]:
...     plt.figure()
...     plt.plot(xr, y4[:,i], 'g.', label='line')
...     plt.plot(xr, y3[:,i], 'y.', label='mean')
...     plt.plot(xr, y2[:,i], 'r.', label='constant')
...     plt.plot(x, Y[:,i], 'k-')
...     plt.legend()
>>> plt.show()

```




scipy.signal.upfirdn

`scipy.signal.upfirdn(h, x, up=1, down=1, axis=-1, mode='constant', cval=0)`
Upsample, FIR filter, and downsample.

Parameters

- h** [array_like] 1-D FIR (finite-impulse response) filter coefficients.
- x** [array_like] Input signal array.
- up** [int, optional] Upsampling rate. Default is 1.
- down** [int, optional] Downsampling rate. Default is 1.
- axis** [int, optional] The axis of the input data array along which to apply the linear filter. The filter is applied to each subarray along this axis. Default is -1.



- mode** [str, optional] The signal extension mode to use. The set {"constant", "symmetric", "reflect", "edge", "wrap"} correspond to modes provided by `numpy.pad`. "smooth" implements a smooth extension by extending based on the slope of the last 2 points at each end of the array. "antireflect" and "antisymmetric" are anti-symmetric versions of "reflect" and "symmetric". The mode "line" extends the signal based on a linear trend defined by the first and last points along the axis.
New in version 1.4.0.
- cval** [float, optional] The constant value to use when `mode == "constant"`.
New in version 1.4.0.

Returns

- y** [ndarray] The output signal array. Dimensions will be the same as *x* except for along *axis*, which will change size according to the *h*, *up*, and *down* parameters.

Notes

The algorithm is an implementation of the block diagram shown on page 129 of the Vaidyanathan text [1] (Figure 4.3-8d).

The direct approach of upsampling by factor of *P* with zero insertion, FIR filtering of length *N*, and downsampling by factor of *Q* is $O(N*Q)$ per output sample. The polyphase implementation used here is $O(N/P)$.

New in version 0.18.

References

[1]

Examples

Simple operations:

```
>>> from scipy.signal import upfirdn
>>> upfirdn([1, 1, 1], [1, 1, 1]) # FIR filter
array([ 1.,  2.,  3.,  2.,  1.])
>>> upfirdn([1], [1, 2, 3], 3) # upsampling with zeros insertion
array([ 1.,  0.,  0.,  2.,  0.,  0.,  3.,  0.,  0.])
>>> upfirdn([1, 1, 1], [1, 2, 3], 3) # upsampling with sample-and-hold
array([ 1.,  1.,  1.,  2.,  2.,  2.,  3.,  3.,  3.])
>>> upfirdn([.5, 1, .5], [1, 1, 1], 2) # linear interpolation
array([ 0.5,  1.,  1.,  1.,  1.,  1.,  0.5,  0. ])
>>> upfirdn([1], np.arange(10), 1, 3) # decimation by 3
array([ 0.,  3.,  6.,  9.])
>>> upfirdn([.5, 1, .5], np.arange(10), 2, 3) # linear interp, rate 2/3
array([ 0.,  1.,  2.5,  4.,  5.5,  7.,  8.5,  0. ])
```

Apply a single filter to multiple signals:

```
>>> x = np.reshape(np.arange(8), (4, 2))
>>> x
array([[0, 1],
       [2, 3],
       [4, 5],
       [6, 7]])
```

Apply along the last dimension of x:

```
>>> h = [1, 1]
>>> upfirdn(h, x, 2)
array([[ 0.,  0.,  1.,  1.],
       [ 2.,  2.,  3.,  3.],
       [ 4.,  4.,  5.,  5.],
       [ 6.,  6.,  7.,  7.]])
```

Apply along the 0th dimension of x:

```
>>> upfirdn(h, x, 2, axis=0)
array([[ 0.,  1.],
       [ 0.,  1.],
       [ 2.,  3.],
       [ 2.,  3.],
       [ 4.,  5.],
       [ 4.,  5.],
       [ 6.,  7.],
       [ 6.,  7.]])
```

6.22.4 Filter design

<code>bilinear(b, a[, fs])</code>	Return a digital IIR filter from an analog one using a bilinear transform.
<code>bilinear_zpk(z, p, k, fs)</code>	Return a digital IIR filter from an analog one using a bilinear transform.
<code>findfreqs(num, den, N[, kind])</code>	Find array of frequencies for computing the response of an analog filter.
<code>firls(numtaps, bands, desired[, weight, nyq, fs])</code>	FIR filter design using least-squares error minimization.
<code>firwin(numtaps, cutoff[, width, window, ...])</code>	FIR filter design using the window method.
<code>firwin2(numtaps, freq, gain[, nfreqs, ...])</code>	FIR filter design using the window method.
<code>freqs(b, a[, worN, plot])</code>	Compute frequency response of analog filter.
<code>freqs_zpk(z, p, k[, worN])</code>	Compute frequency response of analog filter.
<code>freqz(b[, a, worN, whole, plot, fs, ...])</code>	Compute the frequency response of a digital filter.
<code>freqz_zpk(z, p, k[, worN, whole, fs])</code>	Compute the frequency response of a digital filter in ZPK form.
<code>sosfreqz(sos[, worN, whole, fs])</code>	Compute the frequency response of a digital filter in SOS format.
<code>gammatone(freq, ftype[, order, numtaps, fs])</code>	Gammatone filter design.
<code>group_delay(system[, w, whole, fs])</code>	Compute the group delay of a digital filter.
<code>iirdesign(wp, ws, gpass, gstop[, analog, ...])</code>	Complete IIR digital and analog filter design.
<code>iirfilter(N, Wn[, rp, rs, btype, analog, ...])</code>	IIR digital and analog filter design given order and critical points.
<code>kaiser_atten(numtaps, width)</code>	Compute the attenuation of a Kaiser FIR filter.
<code>kaiser_beta(a)</code>	Compute the Kaiser parameter <i>beta</i> , given the attenuation <i>a</i> .
<code>kaiserord(ripple, width)</code>	Determine the filter window parameters for the Kaiser window method.
<code>minimum_phase(h[, method, n_fft])</code>	Convert a linear-phase FIR filter to minimum phase
<code>savgol_coeffs(window_length, polyorder[, ...])</code>	Compute the coefficients for a 1-D Savitzky-Golay FIR filter.
<code>remez(numtaps, bands, desired[, weight, Hz, ...])</code>	Calculate the minimax optimal filter using the Remez exchange algorithm.
<code>unique_roots(p[, tol, rtype])</code>	Determine unique roots and their multiplicities from a list of roots.
<code>residue(b, a[, tol, rtype])</code>	Compute partial-fraction expansion of $b(s) / a(s)$.
<code>residuez(b, a[, tol, rtype])</code>	Compute partial-fraction expansion of $b(z) / a(z)$.
<code>invres(r, p, k[, tol, rtype])</code>	Compute $b(s)$ and $a(s)$ from partial fraction expansion.
<code>invresz(r, p, k[, tol, rtype])</code>	Compute $b(z)$ and $a(z)$ from partial fraction expansion.
<code>BadCoefficients</code>	Warning about badly conditioned filter coefficients

scipy.signal.bilinear

`scipy.signal.bilinear(b, a, fs=1.0)`

Return a digital IIR filter from an analog one using a bilinear transform.

Transform a set of poles and zeros from the analog s -plane to the digital z -plane using Tustin's method, which substitutes $(z-1) / (z+1)$ for s , maintaining the shape of the frequency response.

Parameters

b [array_like] Numerator of the analog filter transfer function.

a [array_like] Denominator of the analog filter transfer function.
fs [float] Sample rate, as ordinary frequency (e.g., hertz). No prewarping is done in this function.

Returns

z [ndarray] Numerator of the transformed digital filter transfer function.
p [ndarray] Denominator of the transformed digital filter transfer function.

See also:

lp2lp, *lp2hp*, *lp2bp*, *lp2bs*
bilinear_zpk

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> fs = 100
>>> bf = 2 * np.pi * np.array([7, 13])
>>> filts = signal.lti(*signal.butter(4, bf, btype='bandpass',
...                               analog=True))
>>> filtz = signal.lti(*signal.bilinear(filts.num, filts.den, fs))
>>> wz, hz = signal.freqz(filtz.num, filtz.den)
>>> ws, hs = signal.freqs(filts.num, filts.den, worN=fs*wz)
```

```
>>> plt.semilogx(wz*fs/(2*np.pi), 20*np.log10(np.abs(hz).clip(1e-15)),
...             label=r'$|H_z(e^{j \omega})|$')
>>> plt.semilogx(wz*fs/(2*np.pi), 20*np.log10(np.abs(hs).clip(1e-15)),
...             label=r'$|H(j \omega)|$')
>>> plt.legend()
>>> plt.xlabel('Frequency [Hz]')
>>> plt.ylabel('Magnitude [dB]')
>>> plt.grid()
```

scipy.signal.bilinear_zpk

`scipy.signal.bilinear_zpk(z, p, k, fs)`


Return a digital IIR filter from an analog one using a bilinear transform.

Transform a set of poles and zeros from the analog s-plane to the digital z-plane using Tustin’s method, which substitutes $(z-1) / (z+1)$ for s , maintaining the shape of the frequency response.

Parameters

z [array_like] Zeros of the analog filter transfer function.
p [array_like] Poles of the analog filter transfer function.
k [float] System gain of the analog filter transfer function.
fs [float] Sample rate, as ordinary frequency (e.g., hertz). No prewarping is done in this function.

Returns



z [ndarray] Zeros of the transformed digital filter transfer function.
p [ndarray] Poles of the transformed digital filter transfer function.
k [float] System gain of the transformed digital filter.

See also:

lp2lp_zpk, *lp2hp_zpk*, *lp2bp_zpk*, *lp2bs_zpk*
bilinear

Notes

New in version 1.1.0.

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> fs = 100
>>> bf = 2 * np.pi * np.array([7, 13])
>>> filts = signal.lti(*signal.butter(4, bf, btype='bandpass',
↳ analog=True,
...                               output='zpk'))
>>> filtz = signal.lti(*signal.bilinear_zpk(filts.zeros, filts.poles,
...                                       filts.gain, fs))
>>> wz, hz = signal.freqz_zpk(filtz.zeros, filtz.poles, filtz.gain)
>>> ws, hs = signal.freqs_zpk(filts.zeros, filts.poles, filts.gain,
...                           worN=fs*wz)
>>> plt.semilogx(wz*fs/(2*np.pi), 20*np.log10(np.abs(hz).clip(1e-15)),
...             label=r'$|H_z(e^{j \omega})|$')
>>> plt.semilogx(wz*fs/(2*np.pi), 20*np.log10(np.abs(hs).clip(1e-15)),
```


(continues on next page)

(continued from previous page)

```

...          label=r'$|H(j \omega)|$')
>>> plt.legend()
>>> plt.xlabel('Frequency [Hz]')
>>> plt.ylabel('Magnitude [dB]')
>>> plt.grid()

```



scipy.signal.findfreqs

`scipy.signal.findfreqs` (*num, den, N, kind='ba'*)

Find array of frequencies for computing the response of an analog filter.

Parameters

- num, den** [array_like, 1-D] The polynomial coefficients of the numerator and denominator of the transfer function of the filter or LTI system, where the coefficients are ordered from highest to lowest degree. Or, the roots of the transfer function numerator and denominator (i.e., zeroes and poles).
- N** [int] The length of the array to be computed.
- kind** [str {'ba', 'zp'}, optional] Specifies whether the numerator and denominator are specified by their polynomial coefficients ('ba'), or their roots ('zp').

Returns

- w** [(N,) ndarray] A 1-D array of frequencies, logarithmically spaced.

Examples

Find a set of nine frequencies that span the “interesting part” of the frequency response for the filter with the transfer function

$$H(s) = s / (s^2 + 8s + 25)$$

```
>>> from scipy import signal
>>> signal.findfreqs([1, 0], [1, 8, 25], N=9)
array([[ 1.00000000e-02,  3.16227766e-02,  1.00000000e-01,
         3.16227766e-01,  1.00000000e+00,  3.16227766e+00,
         1.00000000e+01,  3.16227766e+01,  1.00000000e+02]])
```

scipy.signal.firls

`scipy.signal.firls` (*numtaps*, *bands*, *desired*, *weight=None*, *nyq=None*, *fs=None*)

FIR filter design using least-squares error minimization.

Calculate the filter coefficients for the linear-phase finite impulse response (FIR) filter which has the best approximation to the desired frequency response described by *bands* and *desired* in the least squares sense (i.e., the integral of the weighted mean-squared error within the specified bands is minimized).

Parameters

- numtaps** [int] The number of taps in the FIR filter. *numtaps* must be odd.
- bands** [array_like] A monotonic nondecreasing sequence containing the band edges in Hz. All elements must be non-negative and less than or equal to the Nyquist frequency given by *nyq*.
- desired** [array_like] A sequence the same size as *bands* containing the desired gain at the start and end point of each band.
- weight** [array_like, optional] A relative weighting to give to each band region when solving the least squares problem. *weight* has to be half the size of *bands*.
- nyq** [float, optional] *Deprecated. Use 'fs' instead.* Nyquist frequency. Each frequency in *bands* must be between 0 and *nyq* (inclusive). Default is 1.
- fs** [float, optional] The sampling frequency of the signal. Each frequency in *bands* must be between 0 and $f_s/2$ (inclusive). Default is 2.

Returns

- coeffs** [ndarray] Coefficients of the optimal (in a least squares sense) FIR filter.

See also:

[*firwin*](#)

[*firwin2*](#)

[*minimum_phase*](#)

[*remez*](#)

Notes

This implementation follows the algorithm given in [1]. As noted there, least squares design has multiple advantages:

1. Optimal in a least-squares sense.
2. Simple, non-iterative method.
3. The general solution can be obtained by solving a linear system of equations.
4. Allows the use of a frequency dependent weighting function.

This function constructs a Type I linear phase FIR filter, which contains an odd number of *coeffs* satisfying for $n < numtaps$:

$$coeffs(n) = coeffs(numtaps - 1 - n)$$

The odd number of coefficients and filter symmetry avoid boundary conditions that could otherwise occur at the Nyquist and 0 frequencies (e.g., for Type II, III, or IV variants).

New in version 0.18.

References

[1]

Examples

We want to construct a band-pass filter. Note that the behavior in the frequency ranges between our stop bands and pass bands is unspecified, and thus may overshoot depending on the parameters of our filter:

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
>>> fig, axs = plt.subplots(2)
>>> fs = 10.0 # Hz
>>> desired = (0, 0, 1, 1, 0, 0)
>>> for bi, bands in enumerate(((0, 1, 2, 3, 4, 5), (0, 1, 2, 4, 4.5, 5))):
...     fir_firls = signal.firls(73, bands, desired, fs=fs)
...     fir_remez = signal.remez(73, bands, desired[:,2], fs=fs)
...     fir_firwin2 = signal.firwin2(73, bands, desired, fs=fs)
...     hs = list()
...     ax = axs[bi]
...     for fir in (fir_firls, fir_remez, fir_firwin2):
...         freq, response = signal.freqz(fir)
...         hs.append(ax.semilogy(0.5*fs*freq/np.pi, np.abs(response))[0])
...     for band, gains in zip(zip(bands[:,2], bands[1:,2]),
...                             zip(desired[:,2], desired[1:,2])):
...         ax.semilogy(band, np.maximum(gains, 1e-7), 'k--', linewidth=2)
...     if bi == 0:
...         ax.legend(hs, ('firls', 'remez', 'firwin2'),
...                     loc='lower center', frameon=False)
...     else:
...         ax.set_xlabel('Frequency (Hz)')
...     ax.grid(True)
```


(continues on next page)

(continued from previous page)

```

...     ax.set(title='Band-pass %d-%d Hz' % bands[2:4], ylabel='Magnitude
...     ↓')
...
>>> fig.tight_layout()
>>> plt.show()

```



scipy.signal.firwin

`scipy.signal.firwin` (*numtaps*, *cutoff*, *width=None*, *window='hamming'*, *pass_zero=True*, *scale=True*, *nyq=None*, *fs=None*)

FIR filter design using the window method.

This function computes the coefficients of a finite impulse response filter. The filter will have linear phase; it will be Type I if *numtaps* is odd and Type II if *numtaps* is even.

Type II filters always have zero response at the Nyquist frequency, so a `ValueError` exception is raised if `firwin` is called with *numtaps* even and having a passband whose right end is at the Nyquist frequency.

Parameters

- numtaps** [int] Length of the filter (number of coefficients, i.e. the filter order + 1). *numtaps* must be odd if a passband includes the Nyquist frequency.
- cutoff** [float or 1-D array_like] Cutoff frequency of filter (expressed in the same units as *fs*) OR an array of cutoff frequencies (that is, band edges). In the latter case, the frequencies in *cutoff* should be positive and monotonically increasing between 0 and *fs*/2. The values 0 and *fs*/2 must not be included in *cutoff*.
- width** [float or None, optional] If *width* is not None, then assume it is the approximate width of the transition region (expressed in the same units as *fs*) for use in Kaiser FIR filter design. In this case, the *window* argument is ignored.
- window** [string or tuple of string and parameter values, optional] Desired window to use. See `scipy.signal.get_window` for a list of windows and required parameters.
- pass_zero** [{True, False, 'bandpass', 'lowpass', 'highpass', 'bandstop'}, optional] If True, the gain at the frequency 0 (i.e., the “DC gain”) is 1. If False, the DC gain is 0. Can also be a string argument for the desired filter type (equivalent to *btype* in IIR design functions).

scale [bool, optional] New in version 1.3.0: Support for string arguments. Set to True to scale the coefficients so that the frequency response is exactly unity at a certain frequency. That frequency is either:

- 0 (DC) if the first passband starts at 0 (i.e. `pass_zero` is True)
- $f_s/2$ (the Nyquist frequency) if the first passband ends at $f_s/2$ (i.e the filter is a single band highpass filter); center of first passband otherwise

nyq [float, optional] *Deprecated. Use `fs` instead.* This is the Nyquist frequency. Each frequency in `cutoff` must be between 0 and `nyq`. Default is 1.

fs [float, optional] The sampling frequency of the signal. Each frequency in `cutoff` must be between 0 and $f_s/2$. Default is 2.

Returns

h [(numtaps,) ndarray] Coefficients of length `numtaps` FIR filter.

Raises**ValueError**

If any value in `cutoff` is less than or equal to 0 or greater than or equal to $f_s/2$, if the values in `cutoff` are not strictly monotonically increasing, or if `numtaps` is even but a passband includes the Nyquist frequency.

See also:

[`firwin2`](#)

[`firls`](#)

[`minimum_phase`](#)

[`remez`](#)

Examples

Low-pass from 0 to `f`:

```
>>> from scipy import signal
>>> numtaps = 3
>>> f = 0.1
>>> signal.firwin(numtaps, f)
array([ 0.06799017,  0.86401967,  0.06799017])
```

Use a specific window function:

```
>>> signal.firwin(numtaps, f, window='nuttall')
array([ 3.56607041e-04,  9.99286786e-01,  3.56607041e-04])
```

High-pass ('stop' from 0 to `f`):

```
>>> signal.firwin(numtaps, f, pass_zero=False)
array([-0.00859313,  0.98281375, -0.00859313])
```

Band-pass:

```
>>> f1, f2 = 0.1, 0.2
>>> signal.firwin(numtaps, [f1, f2], pass_zero=False)
array([ 0.06301614,  0.88770441,  0.06301614])
```

Band-stop:

```
>>> signal.firwin(numtaps, [f1, f2])
array([-0.00801395,  1.0160279 , -0.00801395])
```

Multi-band (passbands are [0, f1], [f2, f3] and [f4, 1]):

```
>>> f3, f4 = 0.3, 0.4
>>> signal.firwin(numtaps, [f1, f2, f3, f4])
array([-0.01376344,  1.02752689, -0.01376344])
```

Multi-band (passbands are [f1, f2] and [f3,f4]):

```
>>> signal.firwin(numtaps, [f1, f2, f3, f4], pass_zero=False)
array([ 0.04890915,  0.91284326,  0.04890915])
```

scipy.signal.firwin2

`scipy.signal.firwin2` (*numtaps*, *freq*, *gain*, *nfreqs*=None, *window*='hamming', *nyq*=None, *antisymmetric*=False, *fs*=None)

FIR filter design using the window method.

From the given frequencies *freq* and corresponding gains *gain*, this function constructs an FIR filter with linear phase and (approximately) the given frequency response.

Parameters

numtaps	[int] The number of taps in the FIR filter. <i>numtaps</i> must be less than <i>nfreqs</i> .
freq	[array_like, 1-D] The frequency sampling points. Typically 0.0 to 1.0 with 1.0 being Nyquist. The Nyquist frequency is half <i>fs</i> . The values in <i>freq</i> must be nondecreasing. A value can be repeated once to implement a discontinuity. The first value in <i>freq</i> must be 0, and the last value must be $f_s/2$. Values 0 and $f_s/2$ must not be repeated.
gain	[array_like] The filter gains at the frequency sampling points. Certain constraints to gain values, depending on the filter type, are applied, see Notes for details.
nfreqs	[int, optional] The size of the interpolation mesh used to construct the filter. For most efficient behavior, this should be a power of 2 plus 1 (e.g, 129, 257, etc). The default is one more than the smallest power of 2 that is not less than <i>numtaps</i> . <i>nfreqs</i> must be greater than <i>numtaps</i> .
window	[string or (string, float) or float, or None, optional] Window function to use. Default is "hamming". See <code>scipy.signal.get_window</code> for the complete list of possible values. If None, no window function is applied.
nyq	[float, optional] <i>Deprecated. Use `fs` instead.</i> This is the Nyquist frequency. Each frequency in <i>freq</i> must be between 0 and <i>nyq</i> . Default is 1.
antisymmetric	[bool, optional] Whether resulting impulse response is symmetric/antisymmetric. See Notes for more details.
fs	[float, optional] The sampling frequency of the signal. Each frequency in <i>cutoff</i> must be between 0 and $f_s/2$. Default is 2.

Returns

taps [ndarray] The filter coefficients of the FIR filter, as a 1-D array of length *numtaps*.

See also:

[`firls`](#)

[`firwin`](#)

*minimum_phase**remez*

Notes

From the given set of frequencies and gains, the desired response is constructed in the frequency domain. The inverse FFT is applied to the desired response to create the associated convolution kernel, and the first *numtaps* coefficients of this kernel, scaled by *window*, are returned.

The FIR filter will have linear phase. The type of filter is determined by the value of ‘numtaps’ and *antisymmetric* flag. There are four possible combinations:

- odd *numtaps*, *antisymmetric* is False, type I filter is produced
- even *numtaps*, *antisymmetric* is False, type II filter is produced
- odd *numtaps*, *antisymmetric* is True, type III filter is produced
- even *numtaps*, *antisymmetric* is True, type IV filter is produced

Magnitude response of all but type I filters are subjects to following constraints:

- type II – zero at the Nyquist frequency
- type III – zero at zero and Nyquist frequencies
- type IV – zero at zero frequency

New in version 0.9.0.

References

[1], [2]

Examples

A lowpass FIR filter with a response that is 1 on [0.0, 0.5], and that decreases linearly on [0.5, 1.0] from 1 to 0:

```
>>> from scipy import signal
>>> taps = signal.firwin2(150, [0.0, 0.5, 1.0], [1.0, 1.0, 0.0])
>>> print(taps[72:78])
[-0.02286961 -0.06362756 0.57310236 0.57310236 -0.06362756 -0.02286961]
```

scipy.signal.freqs

`scipy.signal.freqs` (*b*, *a*, *worN=200*, *plot=None*)

Compute frequency response of analog filter.

Given the M-order numerator *b* and N-order denominator *a* of an analog filter, compute its frequency response:

$$H(w) = \frac{b[0] * (jw)^{**M} + b[1] * (jw)^{** (M-1)} + \dots + b[M]}{a[0] * (jw)^{**N} + a[1] * (jw)^{** (N-1)} + \dots + a[N]}$$

Parameters

b [array_like] Numerator of a linear filter.
a [array_like] Denominator of a linear filter.
worN [{None, int, array_like}, optional] If None, then compute at 200 frequencies around the interesting parts of the response curve (determined by pole-zero locations). If a single integer, then compute at that many frequencies. Otherwise, compute the response at the angular frequencies (e.g., rad/s) given in *worN*.
plot [callable, optional] A callable that takes two arguments. If given, the return parameters *w* and *h* are passed to plot. Useful for plotting the frequency response inside *freqs*.

Returns

w [ndarray] The angular frequencies at which *h* was computed.
h [ndarray] The frequency response.

See also:*freqz*

Compute the frequency response of a digital filter.

Notes

Using Matplotlib's "plot" function as the callable for *plot* produces unexpected results, this plots the real part of the complex transfer function, not the magnitude. Try `lambda w, h: plot(w, abs(h))`.

Examples

```
>>> from scipy.signal import freqs, iirfilter
```

```
>>> b, a = iirfilter(4, [1, 10], 1, 60, analog=True, ftype='cheby1')
```

```
>>> w, h = freqs(b, a, worN=np.logspace(-1, 2, 1000))
```

```
>>> import matplotlib.pyplot as plt
>>> plt.semilogx(w, 20 * np.log10(abs(h)))
>>> plt.xlabel('Frequency')
>>> plt.ylabel('Amplitude response [dB]')
>>> plt.grid()
>>> plt.show()
```

scipy.signal.freqs_zpk


`scipy.signal.freqs_zpk(z, p, k, worN=200)`

Compute frequency response of analog filter.

Given the zeros *z*, poles *p*, and gain *k* of a filter, compute its frequency response:

$$H(w) = k * \frac{(jw-z[0]) * (jw-z[1]) * \dots * (jw-z[-1])}{(jw-p[0]) * (jw-p[1]) * \dots * (jw-p[-1])}$$

Parameters



z [array_like] Zeros of a linear filter
p [array_like] Poles of a linear filter
k [scalar] Gain of a linear filter
worN [{None, int, array_like}, optional] If None, then compute at 200 frequencies around the interesting parts of the response curve (determined by pole-zero locations). If a single integer, then compute at that many frequencies. Otherwise, compute the response at the angular frequencies (e.g., rad/s) given in *worN*.

Returns

w [ndarray] The angular frequencies at which *h* was computed.
h [ndarray] The frequency response.

See also:

freqs

Compute the frequency response of an analog filter in TF form

freqz

Compute the frequency response of a digital filter in TF form

freqz_zpk

Compute the frequency response of a digital filter in ZPK form

Notes

New in version 0.19.0.


Examples

```
>>> from scipy.signal import freqs_zpk, iirfilter
```

```
>>> z, p, k = iirfilter(4, [1, 10], 1, 60, analog=True, ftype='cheby1',
...                    output='zpk')
```

```
>>> w, h = freqs_zpk(z, p, k, worN=np.logspace(-1, 2, 1000))
```

```
>>> import matplotlib.pyplot as plt
>>> plt.semilogx(w, 20 * np.log10(abs(h)))
>>> plt.xlabel('Frequency')
>>> plt.ylabel('Amplitude response [dB]')
>>> plt.grid()
>>> plt.show()
```



scipy.signal.freqz

`scipy.signal.freqz(b, a=1, worN=512, whole=False, plot=None, fs=6.283185307179586, include_nyquist=False)`

Compute the frequency response of a digital filter.

Given the M-order numerator b and N-order denominator a of a digital filter, compute its frequency response:

$$H(e^{j\omega}) = \frac{b[0] + b[1]e^{-j\omega} + \dots + b[M]e^{-j\omega M}}{1 + a[1]e^{-j\omega} + \dots + a[N]e^{-j\omega N}}$$

(continues on next page)

(continued from previous page)

$$A(e^{j\omega}) = a[0] + a[1]e^{-j\omega} + \dots + a[N]e^{-j\omega N}$$

Parameters

- b** [array_like] Numerator of a linear filter. If *b* has dimension greater than 1, it is assumed that the coefficients are stored in the first dimension, and *b*.shape[1:], *a*.shape[1:], and the shape of the frequencies array must be compatible for broadcasting.
- a** [array_like] Denominator of a linear filter. If *b* has dimension greater than 1, it is assumed that the coefficients are stored in the first dimension, and *b*.shape[1:], *a*.shape[1:], and the shape of the frequencies array must be compatible for broadcasting.
- worN** [{None, int, array_like}, optional] If a single integer, then compute at that many frequencies (default is N=512). This is a convenient alternative to:

```
np.linspace(0, fs if whole else fs/2, N, endpoint=include_
↪nyquist)
```

Using a number that is fast for FFT computations can result in faster computations (see Notes).

If an array_like, compute the response at the frequencies given. These are in the same units as *fs*.

- whole** [bool, optional] Normally, frequencies are computed from 0 to the Nyquist frequency, *fs*/2 (upper-half of unit-circle). If *whole* is True, compute frequencies from 0 to *fs*. Ignored if *worN* is array_like.
- plot** [callable] A callable that takes two arguments. If given, the return parameters *w* and *h* are passed to plot. Useful for plotting the frequency response inside *freqz*.
- fs** [float, optional] The sampling frequency of the digital system. Defaults to 2*pi radians/sample (so *w* is from 0 to pi).
New in version 1.2.0.
- include_nyquist** [bool, optional] If *whole* is False and *worN* is an integer, setting *include_nyquist* to True will include the last frequency (Nyquist frequency) and is otherwise ignored.
New in version 1.5.0.

Returns

- w** [ndarray] The frequencies at which *h* was computed, in the same units as *fs*. By default, *w* is normalized to the range [0, pi) (radians/sample).
- h** [ndarray] The frequency response, as complex numbers.

See also:

freqz_zpk
sosfreqz

Notes

Using Matplotlib's `matplotlib.pyplot.plot` function as the callable for `plot` produces unexpected results, as this plots the real part of the complex transfer function, not the magnitude. Try `lambda w, h: plot(w, np.abs(h))`.

A direct computation via (R)FFT is used to compute the frequency response when the following conditions are met:

1. An integer value is given for `worN`.
2. `worN` is fast to compute via FFT (i.e., `next_fast_len(worN)` equals `worN`).
3. The denominator coefficients are a single value (`a.shape[0] == 1`).
4. `worN` is at least as long as the numerator coefficients (`worN >= b.shape[0]`).
5. If `b.ndim > 1`, then `b.shape[-1] == 1`.

For long FIR filters, the FFT approach can have lower error and be much faster than the equivalent direct polynomial calculation.

Examples

```
>>> from scipy import signal
>>> b = signal.firwin(80, 0.5, window=('kaiser', 8))
>>> w, h = signal.freqz(b)
```

```
>>> import matplotlib.pyplot as plt
>>> fig, ax1 = plt.subplots()
>>> ax1.set_title('Digital filter frequency response')
```

```
>>> ax1.plot(w, 20 * np.log10(abs(h)), 'b')
>>> ax1.set_ylabel('Amplitude [dB]', color='b')
>>> ax1.set_xlabel('Frequency [rad/sample]')
```


```
>>> ax2 = ax1.twinx()
>>> angles = np.unwrap(np.angle(h))
>>> ax2.plot(w, angles, 'g')
>>> ax2.set_ylabel('Angle (radians)', color='g')
>>> ax2.grid()
>>> ax2.axis('tight')
>>> plt.show()
```

Broadcasting Examples

Suppose we have two FIR filters whose coefficients are stored in the rows of an array with shape (2, 25). For this demonstration, we'll use random data:

```
>>> np.random.seed(42)
>>> b = np.random.rand(2, 25)
```

To compute the frequency response for these two filters with one call to `freqz`, we must pass in `b.T`, because `freqz` expects the first axis to hold the coefficients. We must then extend the shape with a trivial dimension of length 1 to allow broadcasting with the array of frequencies. That is, we pass in `b.T[..., np.newaxis]`, which has shape (25, 2, 1):



```
>>> w, h = signal.freqz(b.T[..., np.newaxis], worN=1024)
>>> w.shape
(1024,)
>>> h.shape
(2, 1024)
```

Now, suppose we have two transfer functions, with the same numerator coefficients $b = [0.5, 0.5]$. The coefficients for the two denominators are stored in the first dimension of the 2-D array a :

```
a = [ 1  1 ]
     [-0.25, -0.5 ]
```

```
>>> b = np.array([0.5, 0.5])
>>> a = np.array([[1, 1], [-0.25, -0.5]])
```

Only a is more than 1-D. To make it compatible for broadcasting with the frequencies, we extend it with a trivial dimension in the call to `freqz`:

```
>>> w, h = signal.freqz(b, a[..., np.newaxis], worN=1024)
>>> w.shape
(1024,)
>>> h.shape
(2, 1024)
```

scipy.signal.freqz_zpk

`scipy.signal.freqz_zpk(z, p, k, worN=512, whole=False, fs=6.283185307179586)`

Compute the frequency response of a digital filter in ZPK form.

Given the Zeros, Poles and Gain of a digital filter, compute its frequency response:

$$H(z) = k \prod_i (z - Z[i]) / \prod_j (z - P[j])$$

where k is the *gain*, Z are the *zeros* and P are the *poles*.

Parameters

z	[array_like] Zeroes of a linear filter
p	[array_like] Poles of a linear filter
k	[scalar] Gain of a linear filter
worN	[{None, int, array_like}, optional] If a single integer, then compute at that many frequencies (default is N=512). If an array_like, compute the response at the frequencies given. These are in the same units as <i>fs</i> .
whole	[bool, optional] Normally, frequencies are computed from 0 to the Nyquist frequency, $fs/2$ (upper-half of unit-circle). If <i>whole</i> is True, compute frequencies from 0 to fs . Ignored if <i>w</i> is array_like.
fs	[float, optional] The sampling frequency of the digital system. Defaults to $2*\pi$ radians/sample (so <i>w</i> is from 0 to π). New in version 1.2.0.

Returns

w	[ndarray] The frequencies at which <i>h</i> was computed, in the same units as <i>fs</i> . By default, <i>w</i> is normalized to the range $[0, \pi)$ (radians/sample).
h	[ndarray] The frequency response, as complex numbers.

See also:*freqs*

Compute the frequency response of an analog filter in TF form

freqs_zpk

Compute the frequency response of an analog filter in ZPK form

freqz

Compute the frequency response of a digital filter in TF form

Notes

New in version 0.19.0.

Examples

Design a 4th-order digital Butterworth filter with cut-off of 100 Hz in a system with sample rate of 1000 Hz, and plot the frequency response:


```
>>> from scipy import signal
>>> z, p, k = signal.butter(4, 100, output='zpk', fs=1000)
>>> w, h = signal.freqz_zpk(z, p, k, fs=1000)
```

```
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> ax1 = fig.add_subplot(1, 1, 1)
>>> ax1.set_title('Digital filter frequency response')
```

```
>>> ax1.plot(w, 20 * np.log10(abs(h)), 'b')
>>> ax1.set_ylabel('Amplitude [dB]', color='b')
>>> ax1.set_xlabel('Frequency [Hz]')
>>> ax1.grid()
```

```
>>> ax2 = ax1.twinx()
>>> angles = np.unwrap(np.angle(h))
>>> ax2.plot(w, angles, 'g')
>>> ax2.set_ylabel('Angle [radians]', color='g')
```

```
>>> plt.axis('tight')
>>> plt.show()
```



scipy.signal.sosfreqz

`scipy.signal.sosfreqz(sos, worN=512, whole=False, fs=6.283185307179586)`

Compute the frequency response of a digital filter in SOS format.

Given *sos*, an array with shape (n, 6) of second order sections of a digital filter, compute the frequency response of the system function:

$$H(z) = \frac{B_0(z)}{A_0(z)} * \frac{B_1(z)}{A_1(z)} * \dots * \frac{B_{n-1}(z)}{A_{n-1}(z)}$$

for $z = \exp(\omega * 1j)$, where $B\{k\}(z)$ and $A\{k\}(z)$ are numerator and denominator of the transfer function of the k -th second order section.

Parameters

- sos** [array_like] Array of second-order filter coefficients, must have shape (n_sections, 6). Each row corresponds to a second-order section, with the first three columns providing the numerator coefficients and the last three providing the denominator coefficients.
- worN** [{None, int, array_like}, optional] If a single integer, then compute at that many frequencies (default is N=512). Using a number that is fast for FFT computations can result in faster computations (see Notes of *freqz*).
If an array_like, compute the response at the frequencies given (must be 1-D). These are in the same units as *fs*.
- whole** [bool, optional] Normally, frequencies are computed from 0 to the Nyquist frequency, $fs/2$ (upper-half of unit-circle). If *whole* is True, compute frequencies from 0 to fs .
- fs** [float, optional] The sampling frequency of the digital system. Defaults to $2 * \pi$ radians/sample (so w is from 0 to π).
New in version 1.2.0.

Returns

- w** [ndarray] The frequencies at which *h* was computed, in the same units as *fs*. By default, *w* is normalized to the range $[0, \pi)$ (radians/sample).
- h** [ndarray] The frequency response, as complex numbers.

See also:

[*freqz*](#), [*sosfilt*](#)

Notes

New in version 0.19.0.

Examples

Design a 15th-order bandpass filter in SOS format.


```
>>> from scipy import signal
>>> sos = signal.ellip(15, 0.5, 60, (0.2, 0.4), btype='bandpass',
...                       output='sos')
```

Compute the frequency response at 1500 points from DC to Nyquist.

```
>>> w, h = signal.sosfreqz(sos, worN=1500)
```

Plot the response.

```
>>> import matplotlib.pyplot as plt
>>> plt.subplot(2, 1, 1)
>>> db = 20*np.log10(np.maximum(np.abs(h), 1e-5))
>>> plt.plot(w/np.pi, db)
>>> plt.ylim(-75, 5)
>>> plt.grid(True)
>>> plt.yticks([0, -20, -40, -60])
>>> plt.ylabel('Gain [dB]')
>>> plt.title('Frequency Response')
>>> plt.subplot(2, 1, 2)
>>> plt.plot(w/np.pi, np.angle(h))
>>> plt.grid(True)
>>> plt.yticks([-np.pi, -0.5*np.pi, 0, 0.5*np.pi, np.pi],
...           [r'$-\pi$', r'$-\pi/2$', '0', r'$\pi/2$', r'$\pi$'])
>>> plt.ylabel('Phase [rad]')
>>> plt.xlabel('Normalized frequency (1.0 = Nyquist)')
>>> plt.show()
```



If the same filter is implemented as a single transfer function, numerical error corrupts the frequency response:

```
>>> b, a = signal.ellip(15, 0.5, 60, (0.2, 0.4), btype='bandpass',
...                   output='ba')
>>> w, h = signal.freqz(b, a, worN=1500)
>>> plt.subplot(2, 1, 1)
>>> db = 20*np.log10(np.maximum(np.abs(h), 1e-5))
>>> plt.plot(w/np.pi, db)
>>> plt.ylim(-75, 5)
>>> plt.grid(True)
>>> plt.yticks([0, -20, -40, -60])
>>> plt.ylabel('Gain [dB]')
```


(continues on next page)

(continued from previous page)

```

>>> plt.title('Frequency Response')
>>> plt.subplot(2, 1, 2)
>>> plt.plot(w/np.pi, np.angle(h))
>>> plt.grid(True)
>>> plt.yticks([-np.pi, -0.5*np.pi, 0, 0.5*np.pi, np.pi],
...           [r'$-\pi$', r'$-\pi/2$', '0', r'$\pi/2$', r'$\pi$'])
>>> plt.ylabel('Phase [rad]')
>>> plt.xlabel('Normalized frequency (1.0 = Nyquist)')
>>> plt.show()

```



scipy.signal.gammatone

`scipy.signal.gammatone` (*freq*, *ftype*, *order=None*, *numtaps=None*, *fs=None*)
 Gammatone filter design.

This function computes the coefficients of an FIR or IIR gammatone digital filter [1].

Parameters

- freq** [float] Center frequency of the filter (expressed in the same units as *fs*).
- ftype** [{'fir', 'iir'}] The type of filter the function generates. If 'fir', the function will generate an Nth order FIR gammatone filter. If 'iir', the function will generate an 8th order digital IIR filter, modeled as as 4th order gammatone filter.
- order** [int, optional] The order of the filter. Only used when *ftype*='fir'. Default is 4 to model the human auditory system. Must be between 0 and 24.
- numtaps** [int, optional] Length of the filter. Only used when *ftype*='fir'. Default is $fs \cdot 0.015$ if *fs* is greater than 1000, 15 if *fs* is less than or equal to 1000.
- fs** [float, optional] The sampling frequency of the signal. *freq* must be between 0 and $fs/2$. Default is 2.

Returns

- b, a** [ndarray, ndarray] Numerator (b) and denominator (a) polynomials of the filter.

Raises

ValueError

If *freq* is less than or equal to 0 or greater than or equal to $fs/2$, if *ftype* is not 'fir' or 'iir', if *order* is less than or equal to 0 or greater than 24 when *ftype*='fir'

See also:

[*`firwin`*](#)

[*`iirfilter`*](#)

References

[1]

Examples


16-sample 4th order FIR Gammatone filter centered at 440 Hz

```
>>> from scipy import signal
>>> signal.gammatone(440, 'fir', numtaps=16, fs=16000)
(array([ 0.00000000e+00,  2.22196719e-07,  1.64942101e-06,  4.99298227e-
↪06,
        1.01993969e-05,  1.63125770e-05,  2.14648940e-05,  2.29947263e-05,
        1.76776931e-05,  2.04980537e-06, -2.72062858e-05, -7.28455299e-05,
        -1.36651076e-04, -2.19066855e-04, -3.18905076e-04, -4.33156712e-04]),
 [1.0])
```

IIR Gammatone filter centered at 440 Hz

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> b, a = signal.gammatone(440, 'iir', fs=16000)
>>> w, h = signal.freqz(b, a)
>>> plt.plot(w / ((2 * np.pi) / 16000), 20 * np.log10(abs(h)))
>>> plt.xscale('log')
>>> plt.title('Gammatone filter frequency response')
>>> plt.xlabel('Frequency')
>>> plt.ylabel('Amplitude [dB]')
>>> plt.margins(0, 0.1)
>>> plt.grid(which='both', axis='both')
>>> plt.axvline(440, color='green') # cutoff frequency
>>> plt.show()
```



scipy.signal.group_delay

`scipy.signal.group_delay` (*system*, *w*=512, *whole*=False, *fs*=6.283185307179586)

Compute the group delay of a digital filter.

The group delay measures by how many samples amplitude envelopes of various spectral components of a signal are delayed by a filter. It is formally defined as the derivative of continuous (unwrapped) phase:

$$D(\omega) = - \frac{d}{d\omega} \arg H(e^{j\omega})$$

Parameters

- system** [tuple of array_like (b, a)] Numerator and denominator coefficients of a filter transfer function.
- w** [{None, int, array_like}, optional] If a single integer, then compute at that many frequencies (default is N=512).
If an array_like, compute the delay at the frequencies given. These are in the same units as *fs*.
- whole** [bool, optional] Normally, frequencies are computed from 0 to the Nyquist frequency, *fs*/2 (upper-half of unit-circle). If *whole* is True, compute frequencies from 0 to *fs*. Ignored if *w* is array_like.
- fs** [float, optional] The sampling frequency of the digital system. Defaults to 2*pi radians/sample (so *w* is from 0 to pi).
New in version 1.2.0.

Returns

- w** [ndarray] The frequencies at which group delay was computed, in the same units as *fs*. By default, *w* is normalized to the range [0, pi) (radians/sample).
- gd** [ndarray] The group delay.

See also:

[*freqz*](#)

Frequency response of a digital filter

Notes

The similar function in MATLAB is called *grpdelay*.

If the transfer function $H(z)$ has zeros or poles on the unit circle, the group delay at corresponding frequencies is undefined. When such a case arises the warning is raised and the group delay is set to 0 at those frequencies.

For the details of numerical computation of the group delay refer to [1].

New in version 0.16.0.


References

[1]

Examples

```
>>> from scipy import signal
>>> b, a = signal.iirdesign(0.1, 0.3, 5, 50, ftype='cheby1')
>>> w, gd = signal.group_delay((b, a))
```

```
>>> import matplotlib.pyplot as plt
>>> plt.title('Digital filter group delay')
>>> plt.plot(w, gd)
>>> plt.ylabel('Group delay [samples]')
>>> plt.xlabel('Frequency [rad/sample]')
>>> plt.show()
```



scipy.signal.iirdesign

`scipy.signal.iirdesign` (*wp*, *ws*, *gpass*, *gstop*, *analog=False*, *ftype='ellip'*, *output='ba'*, *fs=None*)

Complete IIR digital and analog filter design.

Given passband and stopband frequencies and gains, construct an analog or digital IIR filter of minimum order for a given basic type. Return the output in numerator, denominator ('ba'), pole-zero ('zpk') or second order sections ('sos') form.

Parameters

wp, ws	[float or array like, shape (2,)] Passband and stopband edge frequencies. Possible values are scalars (for lowpass and highpass filters) or ranges (for bandpass and bandstop filters). For digital filters, these are in the same units as <i>fs</i> . By default, <i>fs</i> is 2 half-cycles/sample, so these are normalized from 0 to 1, where 1 is the Nyquist frequency. For example: <ul style="list-style-type: none"> • Lowpass: <i>wp</i> = 0.2, <i>ws</i> = 0.3 • Highpass: <i>wp</i> = 0.3, <i>ws</i> = 0.2 • Bandpass: <i>wp</i> = [0.2, 0.5], <i>ws</i> = [0.1, 0.6] • Bandstop: <i>wp</i> = [0.1, 0.6], <i>ws</i> = [0.2, 0.5] For analog filters, <i>wp</i> and <i>ws</i> are angular frequencies (e.g., rad/s). Note, that for bandpass and bandstop filters passband must lie strictly inside stopband or vice versa.
gpass	[float] The maximum loss in the passband (dB).
gstop	[float] The minimum attenuation in the stopband (dB).
analog	[bool, optional] When True, return an analog filter, otherwise a digital filter is returned.
ftype	[str, optional] The type of IIR filter to design: <ul style="list-style-type: none"> • Butterworth : 'butter' • Chebyshev I : 'cheby1' • Chebyshev II : 'cheby2' • Cauer/elliptic: 'ellip' • Bessel/Thomson: 'bessel'
output	[['ba', 'zpk', 'sos'], optional] Filter form of the output: <ul style="list-style-type: none"> • second-order sections (recommended) : 'sos' • numerator/denominator (default) : 'ba' • pole-zero : 'zpk' In general the second-order sections ('sos') form is recommended because inferring the coefficients for the numerator/denominator form ('ba') suffers from numerical instabilities. For reasons of backward compatibility the default form is the numerator/denominator form ('ba'), where the 'b' and the 'a' in 'ba' refer to the commonly used names of the coefficients used. Note: Using the second-order sections form ('sos') is sometimes associated with additional computational costs: for data-intense use cases it is therefore recommended to also investigate the numerator/denominator form ('ba').
fs	[float, optional] The sampling frequency of the digital system. New in version 1.2.0.

Returns

b, a	[ndarray, ndarray] Numerator (<i>b</i>) and denominator (<i>a</i>) polynomials of the IIR filter. Only returned if <code>output='ba'</code> .
z, p, k	[ndarray, ndarray, float] Zeros, poles, and system gain of the IIR filter transfer function. Only returned if <code>output='zpk'</code> .
sos	[ndarray] Second-order sections representation of the IIR filter. Only returned if <code>output=='sos'</code> .

See also:

[*butter*](#)

Filter design using order and critical points

cheby1, cheby2, ellip,essel

buttord

Find order and critical points from passband and stopband spec

cheb1ord, cheb2ord, ellipord

iirfilter

General filter design using order and critical frequencies

Notes

The 'sos' output parameter was added in 0.16.0.


Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
>>> import matplotlib.ticker
```

```
>>> wp = 0.2
>>> ws = 0.3
>>> gpass = 1
>>> gstop = 40
```

```
>>> system = signal.iirdesign(wp, ws, gpass, gstop)
>>> w, h = signal.freqz(*system)
```

```
>>> fig, ax1 = plt.subplots()
>>> ax1.set_title('Digital filter frequency response')
>>> ax1.plot(w, 20 * np.log10(abs(h)), 'b')
>>> ax1.set_ylabel('Amplitude [dB]', color='b')
>>> ax1.set_xlabel('Frequency [rad/sample]')
>>> ax1.grid()
>>> ax1.set_ylim([-120, 20])
>>> ax2 = ax1.twinx()
>>> angles = np.unwrap(np.angle(h))
>>> ax2.plot(w, angles, 'g')
>>> ax2.set_ylabel('Angle (radians)', color='g')
>>> ax2.grid()
>>> ax2.axis('tight')
>>> ax2.set_ylim([-6, 1])
>>> nticks = 8
>>> ax1.yaxis.set_major_locator(matplotlib.ticker.LinearLocator(nticks))
>>> ax2.yaxis.set_major_locator(matplotlib.ticker.LinearLocator(nticks))
```

scipy.signal.iirfilter

`scipy.signal.iirfilter` (*N*, *Wn*, *rp=None*, *rs=None*, *btype='band'*, *analog=False*, *ftype='butter'*, *output='ba'*, *fs=None*)

IIR digital and analog filter design given order and critical points.

Design an *N*th-order digital or analog filter and return the filter coefficients.

Parameters

N	[int] The order of the filter.
Wn	[array_like] A scalar or length-2 sequence giving the critical frequencies. For digital filters, <i>Wn</i> are in the same units as <i>fs</i> . By default, <i>fs</i> is 2 half-cycles/sample, so these are normalized from 0 to 1, where 1 is the Nyquist frequency. (<i>Wn</i> is thus in half-cycles / sample.) For analog filters, <i>Wn</i> is an angular frequency (e.g., rad/s).
rp	[float, optional] For Chebyshev and elliptic filters, provides the maximum ripple in the pass-band. (dB)
rs	[float, optional] For Chebyshev and elliptic filters, provides the minimum attenuation in the stop band. (dB)
btype	[{'bandpass', 'lowpass', 'highpass', 'bandstop'}, optional] The type of filter. Default is 'bandpass'.
analog	[bool, optional] When True, return an analog filter, otherwise a digital filter is returned.
ftype	[str, optional] The type of IIR filter to design: <ul style="list-style-type: none"> • Butterworth : 'butter' • Chebyshev I : 'cheby1' • Chebyshev II : 'cheby2' • Cauer/elliptic: 'ellip' • Bessel/Thomson: 'bessel'
output	[{'ba', 'zpk', 'sos'}, optional] Filter form of the output: <ul style="list-style-type: none"> • second-order sections (recommended): 'sos' • numerator/denominator (default) : 'ba' • pole-zero : 'zpk'

In general the second-order sections ('sos') form is recommended because inferring the coefficients for the numerator/denominator form ('ba') suffers from numerical instabilities. For

reasons of backward compatibility the default form is the numerator/denominator form ('ba'), where the 'b' and the 'a' in 'ba' refer to the commonly used names of the coefficients used.

Note: Using the second-order sections form ('sos') is sometimes associated with additional computational costs: for data-intense use cases it is therefore recommended to also investigate the numerator/denominator form ('ba').

fs [float, optional] The sampling frequency of the digital system.
New in version 1.2.0.

Returns

b, a [ndarray, ndarray] Numerator (*b*) and denominator (*a*) polynomials of the IIR filter. Only returned if `output='ba'`.

z, p, k [ndarray, ndarray, float] Zeros, poles, and system gain of the IIR filter transfer function. Only returned if `output='zpk'`.

sos [ndarray] Second-order sections representation of the IIR filter. Only returned if `output=='sos'`.

See also:

butter

Filter design using order and critical points

cheby1, cheby2, ellip, bessel

buttord

Find order and critical points from passband and stopband spec

cheb1ord, cheb2ord, ellipord

iirdesign

General filter design using passband and stopband spec

Notes

The 'sos' output parameter was added in 0.16.0.

Examples

Generate a 17th-order Chebyshev II analog bandpass filter from 50 Hz to 200 Hz and plot the frequency response:


```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt

>>> b, a = signal.iirfilter(17, [2*np.pi*50, 2*np.pi*200], rs=60,
...                          btype='band', analog=True, ftype='cheby2')
>>> w, h = signal.freqs(b, a, 1000)
>>> fig = plt.figure()
>>> ax = fig.add_subplot(1, 1, 1)
>>> ax.semilogx(w / (2*np.pi), 20 * np.log10(np.maximum(abs(h), 1e-5)))
>>> ax.set_title('Chebyshev Type II bandpass frequency response')
>>> ax.set_xlabel('Frequency [Hz]')
>>> ax.set_ylabel('Amplitude [dB]')
>>> ax.axis((10, 1000, -100, 10))
```

(continues on next page)

(continued from previous page)

```
>>> ax.grid(which='both', axis='both')
>>> plt.show()
```



Create a digital filter with the same properties, in a system with sampling rate of 2000 Hz, and plot the frequency response. (Second-order sections implementation is required to ensure stability of a filter of this order):

```
>>> sos = signal.iirfilter(17, [50, 200], rs=60, btype='band',
...                       analog=False, ftype='cheby2', fs=2000,
...                       output='sos')
>>> w, h = signal.sosfreqz(sos, 2000, fs=2000)
>>> fig = plt.figure()
>>> ax = fig.add_subplot(1, 1, 1)
>>> ax.semilogx(w, 20 * np.log10(np.maximum(abs(h), 1e-5)))
>>> ax.set_title('Chebyshev Type II bandpass frequency response')
>>> ax.set_xlabel('Frequency [Hz]')
>>> ax.set_ylabel('Amplitude [dB]')
>>> ax.axis((10, 1000, -100, 10))
>>> ax.grid(which='both', axis='both')
>>> plt.show()
```

scipy.signal.kaiser_atten

`scipy.signal.kaiser_atten(numtaps, width)`


Compute the attenuation of a Kaiser FIR filter.

Given the number of taps N and the transition width $width$, compute the attenuation a in dB, given by Kaiser's formula:

$$a = 2.285 * (N - 1) * \pi * width + 7.95$$

Parameters

numtaps [int] The number of taps in the FIR filter.



width [float] The desired width of the transition region between passband and stopband (or, in general, at any discontinuity) for the filter, expressed as a fraction of the Nyquist frequency.

Returns

a [float] The attenuation of the ripple, in dB.

See also:

[*kaiserord*](#), [*kaiser_beta*](#)

Examples

Suppose we want to design a FIR filter using the Kaiser window method that will have 211 taps and a transition width of 9 Hz for a signal that is sampled at 480 Hz. Expressed as a fraction of the Nyquist frequency, the width is $9/(0.5*480) = 0.0375$. The approximate attenuation (in dB) is computed as follows:

```
>>> from scipy.signal import kaiser_atten
>>> kaiser_atten(211, 0.0375)
64.48099630593983
```

scipy.signal.kaiser_beta

`scipy.signal.kaiser_beta(a)`

Compute the Kaiser parameter *beta*, given the attenuation *a*.

Parameters

a [float] The desired attenuation in the stopband and maximum ripple in the passband, in dB. This should be a *positive* number.

Returns

beta [float] The *beta* parameter to be used in the formula for a Kaiser window.

References

Oppenheim, Schafer, “Discrete-Time Signal Processing”, p.475-476.

Examples

Suppose we want to design a lowpass filter, with 65 dB attenuation in the stop band. The Kaiser window parameter to be used in the window method is computed by `kaiser_beta(65)`:

```
>>> from scipy.signal import kaiser_beta
>>> kaiser_beta(65)
6.20426
```

scipy.signal.kaiserord

`scipy.signal.kaiserord` (*ripple*, *width*)

Determine the filter window parameters for the Kaiser window method.

The parameters returned by this function are generally used to create a finite impulse response filter using the window method, with either `firwin` or `firwin2`.

Parameters

ripple [float] Upper bound for the deviation (in dB) of the magnitude of the filter’s frequency response from that of the desired filter (not including frequencies in any transition intervals). That is, if w is the frequency expressed as a fraction of the Nyquist frequency, $A(w)$ is the actual frequency response of the filter and $D(w)$ is the desired frequency response, the design requirement is that:

$$\text{abs}(A(w) - D(w)) < 10^{**(-\text{ripple}/20)}$$

for $0 \leq w \leq 1$ and w not in a transition interval.

width [float] Width of transition region, normalized so that 1 corresponds to π radians / sample. That is, the frequency is expressed as a fraction of the Nyquist frequency.

Returns

numtaps [int] The length of the Kaiser window.
beta [float] The beta parameter for the Kaiser window.

See also:

[`kaiser_beta`](#), [`kaiser_atten`](#)

Notes

There are several ways to obtain the Kaiser window:

- `signal.windows.kaiser(numtaps, beta, sym=True)`
- `signal.get_window(beta, numtaps)`
- `signal.get_window('kaiser', beta), numtaps)`

The empirical equations discovered by Kaiser are used.

References

Oppenheim, Schafer, “Discrete-Time Signal Processing”, pp.475-476.

Examples

We will use the Kaiser window method to design a lowpass FIR filter for a signal that is sampled at 1000 Hz.

We want at least 65 dB rejection in the stop band, and in the pass band the gain should vary no more than 0.5%.

We want a cutoff frequency of 175 Hz, with a transition between the pass band and the stop band of 24 Hz. That is, in the band [0, 163], the gain varies no more than 0.5%, and in the band [187, 500], the signal is attenuated by at least 65 dB.

```
>>> from scipy.signal import kaiserord, firwin, freqz
>>> import matplotlib.pyplot as plt
>>> fs = 1000.0
>>> cutoff = 175
>>> width = 24
```

The Kaiser method accepts just a single parameter to control the pass band ripple and the stop band rejection, so we use the more restrictive of the two. In this case, the pass band ripple is 0.005, or 46.02 dB, so we will use 65 dB as the design parameter.

Use `kaiserord` to determine the length of the filter and the parameter for the Kaiser window.

```
>>> numtaps, beta = kaiserord(65, width/(0.5*fs))
>>> numtaps
167
>>> beta
6.20426
```

Use `firwin` to create the FIR filter.

```
>>> taps = firwin(numtaps, cutoff, window=('kaiser', beta),
...               scale=False, nyq=0.5*fs)
```

Compute the frequency response of the filter. `w` is the array of frequencies, and `h` is the corresponding complex array of frequency responses.

```
>>> w, h = freqz(taps, worN=8000)
>>> w *= 0.5*fs/np.pi # Convert w to Hz.
```

Compute the deviation of the magnitude of the filter’s response from that of the ideal lowpass filter. Values in the transition region are set to `nan`, so they won’t appear in the plot.


```
>>> ideal = w < cutoff # The "ideal" frequency response.
>>> deviation = np.abs(np.abs(h) - ideal)
>>> deviation[(w > cutoff - 0.5*width) & (w < cutoff + 0.5*width)] = np.
↳nan
```

Plot the deviation. A close look at the left end of the stop band shows that the requirement for 65 dB attenuation is violated in the first lobe by about 0.125 dB. This is not unusual for the Kaiser window method.

```

>>> plt.plot(w, 20*np.log10(np.abs(deviation)))
>>> plt.xlim(0, 0.5*fs)
>>> plt.ylim(-90, -60)
>>> plt.grid(alpha=0.25)
>>> plt.axhline(-65, color='r', ls='--', alpha=0.3)
>>> plt.xlabel('Frequency (Hz)')
>>> plt.ylabel('Deviation from ideal (dB)')
>>> plt.title('Lowpass Filter Frequency Response')
>>> plt.show()

```



scipy.signal.minimum_phase

`scipy.signal.minimum_phase` (*h*, *method*='homomorphic', *n_fft*=None)

Convert a linear-phase FIR filter to minimum phase

Parameters

- h** [array] Linear-phase FIR filter coefficients.
- method** [{'hilbert', 'homomorphic'}] The method to use:
'homomorphic' (default)
 This method [4] [5] works best with filters with an odd number of taps, and the resulting minimum phase filter will have a magnitude response that approximates the square root of the the original filter's magnitude response.
'hilbert'
 This method [1] is designed to be used with equiripple filters (e.g., from *remez*) with unity or zero gain regions.
- n_fft** [int] The number of points to use for the FFT. Should be at least a few times larger than the signal length (see Notes).

Returns

- h_minimum**
 [array] The minimum-phase version of the filter, with length $(\text{length}(h) + 1) // 2$.

See also:

`firwin`
`firwin2`
`remez`

Notes

Both the Hilbert [1] or homomorphic [4] [5] methods require selection of an FFT length to estimate the complex cepstrum of the filter.

In the case of the Hilbert method, the deviation from the ideal spectrum `epsilon` is related to the number of stopband zeros `n_stop` and FFT length `n_fft` as:

```
epsilon = 2. * n_stop / n_fft
```

For example, with 100 stopband zeros and a FFT length of 2048, `epsilon = 0.0976`. If we conservatively assume that the number of stopband zeros is one less than the filter length, we can take the FFT length to be the next power of 2 that satisfies `epsilon=0.01` as:

```
n_fft = 2 ** int(np.ceil(np.log2(2 * (len(h) - 1) / 0.01)))
```

This gives reasonable results for both the Hilbert and homomorphic methods, and gives the value used when `n_fft=None`.

Alternative implementations exist for creating minimum-phase filters, including zero inversion [2] and spectral factorization [3] [4]. For more information, see:

<http://dspguru.com/dsp/howtos/how-to-design-minimum-phase-fir-filters>

References

[1], [2], [3], [4], [5]

Examples

Create an optimal linear-phase filter, then convert it to minimum phase:

```
>>> from scipy.signal import remez, minimum_phase, freqz, group_delay
>>> import matplotlib.pyplot as plt
>>> freq = [0, 0.2, 0.3, 1.0]
>>> desired = [1, 0]
>>> h_linear = remez(151, freq, desired, Hz=2.)
```

Convert it to minimum phase:

```
>>> h_min_hom = minimum_phase(h_linear, method='homomorphic')
>>> h_min_hil = minimum_phase(h_linear, method='hilbert')
```

Compare the three filters:

```
>>> fig, axs = plt.subplots(4, figsize=(4, 8))
>>> for h, style, color in zip((h_linear, h_min_hom, h_min_hil),
...                           ('-', '-', '--'), ('k', 'r', 'c')):
```

(continues on next page)

(continued from previous page)

```

...     w, H = freqz(h)
...     w, gd = group_delay((h, 1))
...     w /= np.pi
...     axs[0].plot(h, color=color, linestyle=style)
...     axs[1].plot(w, np.abs(H), color=color, linestyle=style)
...     axs[2].plot(w, 20 * np.log10(np.abs(H)), color=color, ↵
↵linestyle=style)
...     axs[3].plot(w, gd, color=color, linestyle=style)
>>> for ax in axs:
...     ax.grid(True, color='0.5')
...     ax.fill_between(freq[1:3], *ax.get_ylim(), color='#ffeeaa', ↵
↵zorder=1)
>>> axs[0].set(xlim=[0, len(h_linear) - 1], ylabel='Amplitude', xlabel=
↵'Samples')
>>> axs[1].legend(['Linear', 'Min-Hom', 'Min-Hil'], title='Phase')
>>> for ax, ylim in zip(axs[1:], ([0, 1.1], [-150, 10], [-60, 60])):
...     ax.set(xlim=[0, 1], ylim=ylim, xlabel='Frequency')
>>> axs[1].set(ylabel='Magnitude')
>>> axs[2].set(ylabel='Magnitude (dB)')
>>> axs[3].set(ylabel='Group delay')
>>> plt.tight_layout()

```

scipy.signal.savgol_coeffs

`scipy.signal.savgol_coeffs` (*window_length*, *polyorder*, *deriv=0*, *delta=1.0*, *pos=None*, *use='conv'*)
 Compute the coefficients for a 1-D Savitzky-Golay FIR filter.

Parameters

window_length

[int] The length of the filter window (i.e., the number of coefficients). *window_length* must be an odd positive integer.

polyorder

[int] The order of the polynomial used to fit the samples. *polyorder* must be less than *window_length*.

deriv

[int, optional] The order of the derivative to compute. This must be a nonnegative integer. The default is 0, which means to filter the data without differentiating.

delta

[float, optional] The spacing of the samples to which the filter will be applied. This is only used if *deriv* > 0.

pos

[int or None, optional] If *pos* is not None, it specifies evaluation position within the window. The default is the middle of the window.

use

[str, optional] Either 'conv' or 'dot'. This argument chooses the order of the coefficients. The default is 'conv', which means that the coefficients are ordered to be used in a convolution. With *use='dot'*, the order is reversed, so the filter is applied by dotting the coefficients with the data set.


Returns

coeffs

[1-D ndarray] The filter coefficients.

See also:

[`savgol_filter`](#)



Notes

New in version 0.14.0.

References

A. Savitzky, M. J. E. Golay, Smoothing and Differentiation of Data by Simplified Least Squares Procedures. Analytical Chemistry, 1964, 36 (8), pp 1627-1639.

Examples

```
>>> from scipy.signal import savgol_coeffs
>>> savgol_coeffs(5, 2)
array([-0.08571429,  0.34285714,  0.48571429,  0.34285714, -0.08571429])
>>> savgol_coeffs(5, 2, deriv=1)
array([ 2.00000000e-01,  1.00000000e-01,  2.07548111e-16, -1.00000000e-01,
        -2.00000000e-01])
```

Note that use='dot' simply reverses the coefficients.

```
>>> savgol_coeffs(5, 2, pos=3)
array([ 0.25714286,  0.37142857,  0.34285714,  0.17142857, -0.14285714])
>>> savgol_coeffs(5, 2, pos=3, use='dot')
array([-0.14285714,  0.17142857,  0.34285714,  0.37142857,  0.25714286])
```

x contains data from the parabola $x = t^2$, sampled at $t = -1, 0, 1, 2, 3$. c holds the coefficients that will compute the derivative at the last position. When dotted with x the result should be 6.

```
>>> x = np.array([1, 0, 1, 4, 9])
>>> c = savgol_coeffs(5, 2, pos=4, deriv=1, use='dot')
>>> c.dot(x)
6.0
```

scipy.signal.remez

`scipy.signal.remez` (*numtaps*, *bands*, *desired*, *weight=None*, *Hz=None*, *type='bandpass'*, *maxiter=25*, *grid_density=16*, *fs=None*)

Calculate the minimax optimal filter using the Remez exchange algorithm.

Calculate the filter-coefficients for the finite impulse response (FIR) filter whose transfer function minimizes the maximum error between the desired gain and the realized gain in the specified frequency bands using the Remez exchange algorithm.

Parameters

- numtaps** [int] The desired number of taps in the filter. The number of taps is the number of terms in the filter, or the filter order plus one.
- bands** [array_like] A monotonic sequence containing the band edges. All elements must be non-negative and less than half the sampling frequency as given by *fs*.
- desired** [array_like] A sequence half the size of *bands* containing the desired gain in each of the specified bands.
- weight** [array_like, optional] A relative weighting to give to each band region. The length of *weight* has to be half the length of *bands*.

Hz [scalar, optional] *Deprecated. Use 'fs' instead.* The sampling frequency in Hz. Default is 1.
type [{‘bandpass’, ‘differentiator’, ‘hilbert’}, optional] The type of filter:

- ‘bandpass’: flat response in bands. This is the default.
- ‘differentiator’: frequency proportional response in bands.
- ‘hilbert’ [filter with odd symmetry, that is, type III] (for even order) or type IV (for odd order) linear phase filters.

maxiter [int, optional] Maximum number of iterations of the algorithm. Default is 25.
grid_density [int, optional] Grid density. The dense grid used in `remez` is of size $(\text{numtaps} + 1) * \text{grid_density}$. Default is 16.
fs [float, optional] The sampling frequency of the signal. Default is 1.

Returns

out [ndarray] A rank-1 array containing the coefficients of the optimal (in a minimax sense) filter.

See also:

`firls`

`firwin`

`firwin2`

`minimum_phase`

References

[1], [2]

Examples

In these examples `remez` gets used creating a bandpass, bandstop, lowpass and highpass filter. The used parameters are the filter order, an array with according frequency boundaries, the desired attenuation values and the sampling frequency. Using `freqz` the corresponding frequency response gets calculated and plotted.

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> def plot_response(fs, w, h, title):
...     "Utility function to plot response functions"
...     fig = plt.figure()
...     ax = fig.add_subplot(111)
...     ax.plot(0.5*fs*w/np.pi, 20*np.log10(np.abs(h)))
...     ax.set_ylim(-40, 5)
...     ax.set_xlim(0, 0.5*fs)
...     ax.grid(True)
...     ax.set_xlabel('Frequency (Hz)')
...     ax.set_ylabel('Gain (dB)')
...     ax.set_title(title)
```

This example shows a steep low pass transition according to the small transition width and high filter order:

```

>>> fs = 22050.0      # Sample rate, Hz
>>> cutoff = 8000.0   # Desired cutoff frequency, Hz
>>> trans_width = 100 # Width of transition from pass band to stop band,
→Hz
>>> numtaps = 400     # Size of the FIR filter.
>>> taps = signal.remez(numtaps, [0, cutoff, cutoff + trans_width, 0.
→5*fs], [1, 0], Hz=fs)
>>> w, h = signal.freqz(taps, [1], worN=2000)
>>> plot_response(fs, w, h, "Low-pass Filter")

```

This example shows a high pass filter:

```

>>> fs = 22050.0      # Sample rate, Hz
>>> cutoff = 2000.0   # Desired cutoff frequency, Hz
>>> trans_width = 250 # Width of transition from pass band to stop band,
→Hz
>>> numtaps = 125     # Size of the FIR filter.
>>> taps = signal.remez(numtaps, [0, cutoff - trans_width, cutoff, 0.
→5*fs],
...                    [0, 1], Hz=fs)
>>> w, h = signal.freqz(taps, [1], worN=2000)
>>> plot_response(fs, w, h, "High-pass Filter")

```

For a signal sampled with 22 kHz a bandpass filter with a pass band of 2-5 kHz gets calculated using the Remez algorithm. The transition width is 260 Hz and the filter order 10:

```

>>> fs = 22000.0      # Sample rate, Hz
>>> band = [2000, 5000] # Desired pass band, Hz
>>> trans_width = 260  # Width of transition from pass band to stop
→band, Hz
>>> numtaps = 10      # Size of the FIR filter.
>>> edges = [0, band[0] - trans_width, band[0], band[1],
...         band[1] + trans_width, 0.5*fs]
>>> taps = signal.remez(numtaps, edges, [0, 1, 0], Hz=fs)
>>> w, h = signal.freqz(taps, [1], worN=2000)
>>> plot_response(fs, w, h, "Band-pass Filter")

```

It can be seen that for this bandpass filter, the low order leads to higher ripple and less steep transitions. There is very low attenuation in the stop band and little overshoot in the pass band. Of course the desired gain can be better approximated with a higher filter order.



The next example shows a bandstop filter. Because of the high filter order the transition is quite steep:

```

>>> fs = 20000.0      # Sample rate, Hz
>>> band = [6000, 8000] # Desired stop band, Hz
>>> trans_width = 200  # Width of transition from pass band to stop
→band, Hz
>>> numtaps = 175     # Size of the FIR filter.
>>> edges = [0, band[0] - trans_width, band[0], band[1], band[1] + trans_
→width, 0.5*fs]
>>> taps = signal.remez(numtaps, edges, [1, 0, 1], Hz=fs)
>>> w, h = signal.freqz(taps, [1], worN=2000)
>>> plot_response(fs, w, h, "Band-stop Filter")

```

```
>>> plt.show()
```





scipy.signal.unique_roots

`scipy.signal.unique_roots` (p , $tol=0.001$, $rtype='min'$)

Determine unique roots and their multiplicities from a list of roots.

Parameters

- p** [array_like] The list of roots.
- tol** [float, optional] The tolerance for two roots to be considered equal in terms of the distance between them. Default is $1e-3$. Refer to Notes about the details on roots grouping.
- rtype** [{'max', 'maximum', 'min', 'minimum', 'avg', 'mean'}, optional] How to determine the returned root if multiple roots are within tol of each other.



- ‘max’, ‘maximum’: pick the maximum of those roots
- ‘min’, ‘minimum’: pick the minimum of those roots
- ‘avg’, ‘mean’: take the average of those roots

When finding minimum or maximum among complex roots they are compared first by the real part and then by the imaginary part.

Returns

unique [ndarray] The list of unique roots.
multiplicity [ndarray] The multiplicity of each root.

Notes

If we have 3 roots a, b and c, such that a is close to b and b is close to c (distance is less than *tol*), then it doesn't necessarily mean that a is close to c. It means that roots grouping is not unique. In this function we use “greedy” grouping going through the roots in the order they are given in the input *p*.

This utility function is not specific to roots but can be used for any sequence of values for which uniqueness and multiplicity has to be determined. For a more general routine, see `numpy.unique`.

Examples

```
>>> from scipy import signal
>>> vals = [0, 1.3, 1.31, 2.8, 1.25, 2.2, 10.3]
>>> uniq, mult = signal.unique_roots(vals, tol=2e-2, rtype='avg')
```

Check which roots have multiplicity larger than 1:

```
>>> uniq[mult > 1]
array([ 1.305])
```

scipy.signal.residue

`scipy.signal.residue` (*b, a, tol=0.001, rtype='avg'*)

Compute partial-fraction expansion of *b(s) / a(s)*.

If *M* is the degree of numerator *b* and *N* the degree of denominator *a*:

$$H(s) = \frac{b(s)}{a(s)} = \frac{b[0] s^{(M)} + b[1] s^{(M-1)} + \dots + b[M]}{a[0] s^{(N)} + a[1] s^{(N-1)} + \dots + a[N]}$$

then the partial-fraction expansion *H(s)* is defined as:

$$= \frac{r[0]}{(s-p[0])} + \frac{r[1]}{(s-p[1])} + \dots + \frac{r[-1]}{(s-p[-1])} + k(s)$$

If there are any repeated roots (closer together than *tol*), then *H(s)* has terms like:

$$\frac{r[i]}{(s-p[i])} + \frac{r[i+1]}{(s-p[i])**2} + \dots + \frac{r[i+n-1]}{(s-p[i])**n}$$

This function is used for polynomials in positive powers of s or z , such as analog filters or digital filters in controls engineering. For negative powers of z (typical for digital filters in DSP), use `residuez`.

See Notes for details about the algorithm.

Parameters

- b** [array_like] Numerator polynomial coefficients.
- a** [array_like] Denominator polynomial coefficients.
- tol** [float, optional] The tolerance for two roots to be considered equal in terms of the distance between them. Default is 1e-3. See `unique_roots` for further details.
- rtype** [{'avg', 'min', 'max'}, optional] Method for computing a root to represent a group of identical roots. Default is 'avg'. See `unique_roots` for further details.

Returns

- r** [ndarray] Residues corresponding to the poles. For repeated poles, the residues are ordered to correspond to ascending by power fractions.
- p** [ndarray] Poles ordered by magnitude in ascending order.
- k** [ndarray] Coefficients of the direct polynomial term.

See also:

`invres`, `residuez`, `numpy.poly`, `unique_roots`

Notes

The “deflation through subtraction” algorithm is used for computations — method 6 in [1].

The form of partial fraction expansion depends on poles multiplicity in the exact mathematical sense. However there is no way to exactly determine multiplicity of roots of a polynomial in numerical computing. Thus you should think of the result of `residue` with given `tol` as partial fraction expansion computed for the denominator composed of the computed poles with empirically determined multiplicity. The choice of `tol` can drastically change the result if there are close poles.

References

[1]

scipy.signal.residuez

`scipy.signal.residuez(b, a, tol=0.001, rtype='avg')`

Compute partial-fraction expansion of $b(z) / a(z)$.

If M is the degree of numerator b and N the degree of denominator a :

$$H(z) = \frac{b(z)}{a(z)} = \frac{b[0] + b[1] z^{*-1} + \dots + b[M] z^{*-M}}{a[0] + a[1] z^{*-1} + \dots + a[N] z^{*-N}}$$

then the partial-fraction expansion $H(z)$ is defined as:

$$= \frac{r[0]}{(1-p[0]z^{**(-1)})} + \dots + \frac{r[-1]}{(1-p[-1]z^{**(-1)})} + k[0] + k[1]z^{**(-1)} \dots$$

If there are any repeated roots (closer than *tol*), then the partial fraction expansion has terms like:

$$\frac{r[i]}{(1-p[i]z^{**(-1)})} + \frac{r[i+1]}{(1-p[i]z^{**(-1)})^{**2}} + \dots + \frac{r[i+n-1]}{(1-p[i]z^{**(-1)})^{**n}}$$

This function is used for polynomials in negative powers of *z*, such as digital filters in DSP. For positive powers, use *residue*.

See Notes of *residue* for details about the algorithm.

Parameters

- b** [array_like] Numerator polynomial coefficients.
- a** [array_like] Denominator polynomial coefficients.
- tol** [float, optional] The tolerance for two roots to be considered equal in terms of the distance between them. Default is 1e-3. See *unique_roots* for further details.
- rtype** [{'avg', 'min', 'max'}, optional] Method for computing a root to represent a group of identical roots. Default is 'avg'. See *unique_roots* for further details.

Returns

- r** [ndarray] Residues corresponding to the poles. For repeated poles, the residues are ordered to correspond to ascending by power fractions.
- p** [ndarray] Poles ordered by magnitude in ascending order.
- k** [ndarray] Coefficients of the direct polynomial term.

See also:

invresz, *residue*, *unique_roots*

scipy.signal.invres

`scipy.signal.invres(r, p, k, tol=0.001, rtype='avg')`

Compute b(s) and a(s) from partial fraction expansion.

If *M* is the degree of numerator *b* and *N* the degree of denominator *a*:

$$H(s) = \frac{b(s)}{a(s)} = \frac{b[0] s^{** (M)} + b[1] s^{** (M-1)} + \dots + b[M]}{a[0] s^{** (N)} + a[1] s^{** (N-1)} + \dots + a[N]}$$

then the partial-fraction expansion H(s) is defined as:

$$= \frac{r[0]}{(s-p[0])} + \frac{r[1]}{(s-p[1])} + \dots + \frac{r[-1]}{(s-p[-1])} + k(s)$$

If there are any repeated roots (closer together than *tol*), then H(s) has terms like:

$$\frac{r[i]}{(s-p[i])} + \frac{r[i+1]}{(s-p[i])^{**2}} + \dots + \frac{r[i+n-1]}{(s-p[i])^{**n}}$$

This function is used for polynomials in positive powers of s or z , such as analog filters or digital filters in controls engineering. For negative powers of z (typical for digital filters in DSP), use `invresz`.

Parameters

- r** [array_like] Residues corresponding to the poles. For repeated poles, the residues must be ordered to correspond to ascending by power fractions.
- p** [array_like] Poles. Equal poles must be adjacent.
- k** [array_like] Coefficients of the direct polynomial term.
- tol** [float, optional] The tolerance for two roots to be considered equal in terms of the distance between them. Default is 1e-3. See `unique_roots` for further details.
- rtype** [{'avg', 'min', 'max'}, optional] Method for computing a root to represent a group of identical roots. Default is 'avg'. See `unique_roots` for further details.

Returns

- b** [ndarray] Numerator polynomial coefficients.
- a** [ndarray] Denominator polynomial coefficients.

See also:

`residue`, `invresz`, `unique_roots`

scipy.signal.invresz

`scipy.signal.invresz(r, p, k, tol=0.001, rtype='avg')`

Compute $b(z)$ and $a(z)$ from partial fraction expansion.

If M is the degree of numerator b and N the degree of denominator a :

$$H(z) = \frac{b(z)}{a(z)} = \frac{b[0] + b[1]z^{-1} + \dots + b[M]z^{-M}}{a[0] + a[1]z^{-1} + \dots + a[N]z^{-N}}$$

then the partial-fraction expansion $H(z)$ is defined as:

$$= \frac{r[0]}{(1-p[0]z^{-1})} + \dots + \frac{r[-1]}{(1-p[-1]z^{-1})} + k[0] + k[1]z^{-1} \dots$$

If there are any repeated roots (closer than tol), then the partial fraction expansion has terms like:

$$\frac{r[i]}{(1-p[i]z^{-1})} + \frac{r[i+1]}{(1-p[i]z^{-1})^{*2}} + \dots + \frac{r[i+n-1]}{(1-p[i]z^{-1})^{*n}}$$

This function is used for polynomials in negative powers of z , such as digital filters in DSP. For positive powers, use `invres`.

Parameters

- r** [array_like] Residues corresponding to the poles. For repeated poles, the residues must be ordered to correspond to ascending by power fractions.
- p** [array_like] Poles. Equal poles must be adjacent.
- k** [array_like] Coefficients of the direct polynomial term.
- tol** [float, optional] The tolerance for two roots to be considered equal in terms of the distance between them. Default is 1e-3. See `unique_roots` for further details.

rtype [({'avg', 'min', 'max'}, optional)] Method for computing a root to represent a group of identical roots. Default is 'avg'. See *unique_roots* for further details.

Returns

b [ndarray] Numerator polynomial coefficients.
a [ndarray] Denominator polynomial coefficients.

See also:

residuez, unique_roots, invres

scipy.signal.BadCoefficients

exception `scipy.signal.BadCoefficients`

Warning about badly conditioned filter coefficients

with_traceback ()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

Lower-level filter design functions:

<i>abcd_normalize</i> ([A, B, C, D])	Check state-space matrices and ensure they are 2-D.
<i>band_stop_obj</i> (wp, ind, passb, stopb, gpass, ...)	Band Stop Objective Function for order minimization.
<i>besselap</i> (N[, norm])	Return (z,p,k) for analog prototype of an Nth-order Bessel filter.
<i>buttap</i> (N)	Return (z,p,k) for analog prototype of Nth-order Butterworth filter.
<i>cheb1ap</i> (N, rp)	Return (z,p,k) for Nth-order Chebyshev type I analog low-pass filter.
<i>cheb2ap</i> (N, rs)	Return (z,p,k) for Nth-order Chebyshev type I analog low-pass filter.
<i>cmplx_sort</i> (p)	Sort roots based on magnitude.
<i>ellipap</i> (N, rp, rs)	Return (z,p,k) of Nth-order elliptic analog lowpass filter.
<i>lp2bp</i> (b, a[, wo, bw])	Transform a lowpass filter prototype to a bandpass filter.
<i>lp2bp_zpk</i> (z, p, k[, wo, bw])	Transform a lowpass filter prototype to a bandpass filter.
<i>lp2bs</i> (b, a[, wo, bw])	Transform a lowpass filter prototype to a bandstop filter.
<i>lp2bs_zpk</i> (z, p, k[, wo, bw])	Transform a lowpass filter prototype to a bandstop filter.
<i>lp2hp</i> (b, a[, wo])	Transform a lowpass filter prototype to a highpass filter.
<i>lp2hp_zpk</i> (z, p, k[, wo])	Transform a lowpass filter prototype to a highpass filter.
<i>lp2lp</i> (b, a[, wo])	Transform a lowpass filter prototype to a different frequency.
<i>lp2lp_zpk</i> (z, p, k[, wo])	Transform a lowpass filter prototype to a different frequency.
<i>normalize</i> (b, a)	Normalize numerator/denominator of a continuous-time transfer function.

scipy.signal.abcd_normalize

`scipy.signal.abcd_normalize` (*A=None, B=None, C=None, D=None*)

Check state-space matrices and ensure they are 2-D.

If enough information on the system is provided, that is, enough properly-shaped arrays are passed to the function, the missing ones are built from this information, ensuring the correct number of rows and columns. Otherwise a `ValueError` is raised.

Parameters

A, B, C, D [array_like, optional] State-space matrices. All of them are `None` (missing) by default. See `ss2tf` for format.

Returns

A, B, C, D [array] Properly shaped state-space matrices.

Raises**ValueError**

If not enough information on the system was provided.

scipy.signal.band_stop_obj

`scipy.signal.band_stop_obj` (*wp, ind, passb, stopb, gpass, gstop, type*)

Band Stop Objective Function for order minimization.

Returns the non-integer order for an analog band stop filter.

Parameters

wp [scalar] Edge of passband *passb*.
ind [int, {0, 1}] Index specifying which *passb* edge to vary (0 or 1).
passb [ndarray] Two element sequence of fixed passband edges.
stopb [ndarray] Two element sequence of fixed stopband edges.
gstop [float] Amount of attenuation in stopband in dB.
gpass [float] Amount of ripple in the passband in dB.
type [{"butter", "cheby", "ellip"}] Type of filter.

Returns

n [scalar] Filter order (possibly non-integer).

scipy.signal.besselap

`scipy.signal.besselap` (*N, norm='phase'*)

Return (z,p,k) for analog prototype of an Nth-order Bessel filter.

Parameters

N [int] The order of the filter.
norm [{"phase", "delay", "mag"}, optional] Frequency normalization:
phase The filter is normalized such that the phase response reaches its midpoint at an angular (e.g., rad/s) cutoff frequency of 1. This happens for both low-pass and high-pass filters, so this is the “phase-matched” case. [6]
 The magnitude response asymptotes are the same as a Butterworth filter of the same order with a cutoff of Wn .
 This is the default, and matches MATLAB’s implementation.

delay The filter is normalized such that the group delay in the passband is 1 (e.g., 1 second). This is the “natural” type obtained by solving Bessel polynomials

mag The filter is normalized such that the gain magnitude is -3 dB at angular frequency 1. This is called “frequency normalization” by Bond. [1]

New in version 0.18.0.

Returns

z [ndarray] Zeros of the transfer function. Is always an empty array.

p [ndarray] Poles of the transfer function.

k [scalar] Gain of the transfer function. For phase-normalized, this is always 1.

See also:

bessel

Filter design function using this prototype

Notes

To find the pole locations, approximate starting points are generated [2] for the zeros of the ordinary Bessel polynomial [3], then the Aberth-Ehrlich method [4] [5] is used on the $K_v(x)$ Bessel function to calculate more accurate zeros, and these locations are then inverted about the unit circle.

References

[1], [2], [3], [4], [5], [6]

scipy.signal.buttap

`scipy.signal.buttap` (*N*)
 Return (z,p,k) for analog prototype of Nth-order Butterworth filter.
 The filter will have an angular (e.g., rad/s) cutoff frequency of 1.

See also:

butter

Filter design function using this prototype

scipy.signal.cheb1ap

`scipy.signal.cheb1ap` (*N*, *rp*)
 Return (z,p,k) for Nth-order Chebyshev type I analog lowpass filter.
 The returned filter prototype has *rp* decibels of ripple in the passband.
 The filter’s angular (e.g. rad/s) cutoff frequency is normalized to 1, defined as the point at which the gain first drops below $-rp$.

See also:

cheby1

Filter design function using this prototype

scipy.signal.cheb2ap

`scipy.signal.cheb2ap` (N, rs)

Return (z,p,k) for Nth-order Chebyshev type I analog lowpass filter.

The returned filter prototype has rs decibels of ripple in the stopband.

The filter's angular (e.g. rad/s) cutoff frequency is normalized to 1, defined as the point at which the gain first reaches $-rs$.

See also:

[*cheby2*](#)

Filter design function using this prototype

scipy.signal.cmplx_sort

`scipy.signal.cmplx_sort` (p)

Sort roots based on magnitude.

Parameters

p [array_like] The roots to sort, as a 1-D array.

Returns

p_sorted [ndarray] Sorted roots.
indx [ndarray] Array of indices needed to sort the input p .

Examples

```

>>> from scipy import signal
>>> vals = [1, 4, 1+1.j, 3]
>>> p_sorted, indx = signal.cmplx_sort(vals)
>>> p_sorted
array([1.+0.j, 1.+1.j, 3.+0.j, 4.+0.j])
>>> indx
array([0, 2, 3, 1])

```

scipy.signal.ellipap

`scipy.signal.ellipap` (N, rp, rs)

Return (z,p,k) of Nth-order elliptic analog lowpass filter.

The filter is a normalized prototype that has rp decibels of ripple in the passband and a stopband rs decibels down.

The filter's angular (e.g., rad/s) cutoff frequency is normalized to 1, defined as the point at which the gain first drops below $-rp$.

See also:

[*ellip*](#)

Filter design function using this prototype

References

[1]

scipy.signal.lp2bp

`scipy.signal.lp2bp(b, a, wo=1.0, bw=1.0)`

Transform a lowpass filter prototype to a bandpass filter.

Return an analog band-pass filter with center frequency wo and bandwidth bw from an analog low-pass filter prototype with unity cutoff frequency, in transfer function ('ba') representation.

Parameters

b	[array_like] Numerator polynomial coefficients.
a	[array_like] Denominator polynomial coefficients.
wo	[float] Desired passband center, as angular frequency (e.g., rad/s). Defaults to no change.
bw	[float] Desired passband width, as angular frequency (e.g., rad/s). Defaults to 1.

Returns

b	[array_like] Numerator polynomial coefficients of the transformed band-pass filter.
a	[array_like] Denominator polynomial coefficients of the transformed band-pass filter.

See also:

[lp2lp](#), [lp2hp](#), [lp2bs](#), [bilinear](#)

[lp2bp_zpk](#)

Notes

This is derived from the s-plane substitution

$$s \rightarrow \frac{s^2 + \omega_0^2}{s \cdot BW}$$

This is the “wideband” transformation, producing a passband with geometric (log frequency) symmetry about wo .

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```


```
>>> lp = signal.lti([1.0], [1.0, 1.0])
>>> bp = signal.lti(*signal.lp2bp(lp.num, lp.den))
>>> w, mag_lp, p_lp = lp.bode()
>>> w, mag_bp, p_bp = bp.bode(w)
```

```
>>> plt.plot(w, mag_lp, label='Lowpass')
>>> plt.plot(w, mag_bp, label='Bandpass')
>>> plt.semilogx()
>>> plt.grid()
>>> plt.xlabel('Frequency [rad/s]')
```

(continues on next page)

(continued from previous page)

```
>>> plt.ylabel('Magnitude [dB]')
>>> plt.legend()
```



scipy.signal.lp2bp_zpk

`scipy.signal.lp2bp_zpk` (*z*, *p*, *k*, *wo*=1.0, *bw*=1.0)

Transform a lowpass filter prototype to a bandpass filter.

Return an analog band-pass filter with center frequency *wo* and bandwidth *bw* from an analog low-pass filter prototype with unity cutoff frequency, using zeros, poles, and gain ('zpk') representation.

Parameters

z	[array_like] Zeros of the analog filter transfer function.
p	[array_like] Poles of the analog filter transfer function.
k	[float] System gain of the analog filter transfer function.
wo	[float] Desired passband center, as angular frequency (e.g., rad/s). Defaults to no change.
bw	[float] Desired passband width, as angular frequency (e.g., rad/s). Defaults to 1.

Returns

z	[ndarray] Zeros of the transformed band-pass filter transfer function.
p	[ndarray] Poles of the transformed band-pass filter transfer function.
k	[float] System gain of the transformed band-pass filter.

See also:

[`lp2lp_zpk`](#), [`lp2hp_zpk`](#), [`lp2bs_zpk`](#), [`bilinear`](#)

[`lp2bp`](#)

Notes

This is derived from the s-plane substitution

$$s \rightarrow \frac{s^2 + \omega_0^2}{s \cdot BW}$$

This is the “wideband” transformation, producing a passband with geometric (log frequency) symmetry about ω_0 .
New in version 1.1.0.

scipy.signal.lp2bs

`scipy.signal.lp2bs` (*b*, *a*, *wo*=1.0, *bw*=1.0)

Transform a lowpass filter prototype to a bandstop filter.

Return an analog band-stop filter with center frequency *wo* and bandwidth *bw* from an analog low-pass filter prototype with unity cutoff frequency, in transfer function (‘ba’) representation.

Parameters

b	[array_like] Numerator polynomial coefficients.
a	[array_like] Denominator polynomial coefficients.
wo	[float] Desired stopband center, as angular frequency (e.g., rad/s). Defaults to no change.
bw	[float] Desired stopband width, as angular frequency (e.g., rad/s). Defaults to 1.

Returns

b	[array_like] Numerator polynomial coefficients of the transformed band-stop filter.
a	[array_like] Denominator polynomial coefficients of the transformed band-stop filter.

See also:

lp2lp, *lp2hp*, *lp2bp*, *bilinear*
lp2bs_zpk

Notes

This is derived from the s-plane substitution

$$s \rightarrow \frac{s \cdot BW}{s^2 + \omega_0^2}$$

This is the “wideband” transformation, producing a stopband with geometric (log frequency) symmetry about ω_0 .

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> lp = signal.lti([1.0], [1.0, 1.5])
>>> bs = signal.lti(*signal.lp2bs(lp.num, lp.den))
>>> w, mag_lp, p_lp = lp.bode()
>>> w, mag_bs, p_bs = bs.bode(w)
>>> plt.plot(w, mag_lp, label='Lowpass')
```


(continues on next page)

(continued from previous page)

```

>>> plt.plot(w, mag_bs, label='Bandstop')
>>> plt.semilogx()
>>> plt.grid()
>>> plt.xlabel('Frequency [rad/s]')
>>> plt.ylabel('Magnitude [dB]')
>>> plt.legend()

```



scipy.signal.lp2bs_zpk

`scipy.signal.lp2bs_zpk` ($z, p, k, wo=1.0, bw=1.0$)

Transform a lowpass filter prototype to a bandstop filter.

Return an analog band-stop filter with center frequency wo and stopband width bw from an analog low-pass filter prototype with unity cutoff frequency, using zeros, poles, and gain ('zpk') representation.

Parameters

z	[array_like] Zeros of the analog filter transfer function.
p	[array_like] Poles of the analog filter transfer function.
k	[float] System gain of the analog filter transfer function.
wo	[float] Desired stopband center, as angular frequency (e.g., rad/s). Defaults to no change.
bw	[float] Desired stopband width, as angular frequency (e.g., rad/s). Defaults to 1.

Returns

z	[ndarray] Zeros of the transformed band-stop filter transfer function.
p	[ndarray] Poles of the transformed band-stop filter transfer function.
k	[float] System gain of the transformed band-stop filter.

See also:

[`lp2lp_zpk`](#), [`lp2hp_zpk`](#), [`lp2bp_zpk`](#), [`bilinear`](#)

[`lp2bs`](#)

Notes

This is derived from the s-plane substitution

$$s \rightarrow \frac{s \cdot BW}{s^2 + \omega_0^2}$$

This is the “wideband” transformation, producing a stopband with geometric (log frequency) symmetry about ω_0 .

New in version 1.1.0.

scipy.signal.lp2hp

`scipy.signal.lp2hp(b, a, wo=1.0)`

Transform a lowpass filter prototype to a highpass filter.

Return an analog high-pass filter with cutoff frequency ω_0 from an analog low-pass filter prototype with unity cutoff frequency, in transfer function (‘ba’) representation.

Parameters

- b** [array_like] Numerator polynomial coefficients.
- a** [array_like] Denominator polynomial coefficients.
- wo** [float] Desired cutoff, as angular frequency (e.g., rad/s). Defaults to no change.

Returns

- b** [array_like] Numerator polynomial coefficients of the transformed high-pass filter.
- a** [array_like] Denominator polynomial coefficients of the transformed high-pass filter.

See also:

[*lp2lp*](#), [*lp2bp*](#), [*lp2bs*](#), [*bilinear*](#)

[*lp2hp_zpk*](#)

Notes

This is derived from the s-plane substitution

$$s \rightarrow \frac{\omega_0}{s}$$

This maintains symmetry of the lowpass and highpass responses on a logarithmic scale.

Examples


```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> lp = signal.lti([1.0], [1.0, 1.0])
>>> hp = signal.lti(*signal.lp2hp(lp.num, lp.den))
>>> w, mag_lp, p_lp = lp.bode()
>>> w, mag_hp, p_hp = hp.bode(w)
```

```

>>> plt.plot(w, mag_lp, label='Lowpass')
>>> plt.plot(w, mag_hp, label='Highpass')
>>> plt.semilogx()
>>> plt.grid()
>>> plt.xlabel('Frequency [rad/s]')
>>> plt.ylabel('Magnitude [dB]')
>>> plt.legend()

```



scipy.signal.lp2hp_zpk

`scipy.signal.lp2hp_zpk(z, p, k, wo=1.0)`

Transform a lowpass filter prototype to a highpass filter.

Return an analog high-pass filter with cutoff frequency ω_0 from an analog low-pass filter prototype with unity cutoff frequency, using zeros, poles, and gain ('zpk') representation.

Parameters

- z** [array_like] Zeros of the analog filter transfer function.
- p** [array_like] Poles of the analog filter transfer function.
- k** [float] System gain of the analog filter transfer function.
- wo** [float] Desired cutoff, as angular frequency (e.g., rad/s). Defaults to no change.

Returns

- z** [ndarray] Zeros of the transformed high-pass filter transfer function.
- p** [ndarray] Poles of the transformed high-pass filter transfer function.
- k** [float] System gain of the transformed high-pass filter.

See also:

[`lp2lp_zpk`](#), [`lp2bp_zpk`](#), [`lp2bs_zpk`](#), [`bilinear`](#)
[`lp2hp`](#)

Notes

This is derived from the s-plane substitution

$$s \rightarrow \frac{\omega_0}{s}$$

This maintains symmetry of the lowpass and highpass responses on a logarithmic scale.

New in version 1.1.0.

scipy.signal.lp2lp

`scipy.signal.lp2lp(b, a, wo=1.0)`

Transform a lowpass filter prototype to a different frequency.

Return an analog low-pass filter with cutoff frequency *wo* from an analog low-pass filter prototype with unity cutoff frequency, in transfer function ('ba') representation.

Parameters

- b** [array_like] Numerator polynomial coefficients.
- a** [array_like] Denominator polynomial coefficients.
- wo** [float] Desired cutoff, as angular frequency (e.g. rad/s). Defaults to no change.

Returns

- b** [array_like] Numerator polynomial coefficients of the transformed low-pass filter.
- a** [array_like] Denominator polynomial coefficients of the transformed low-pass filter.

See also:

[*lp2hp*](#), [*lp2bp*](#), [*lp2bs*](#), [*bilinear*](#)
[*lp2lp_zpk*](#)

Notes

This is derived from the s-plane substitution

$$s \rightarrow \frac{s}{\omega_0}$$

Examples


```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> lp = signal.lti([1.0], [1.0, 1.0])
>>> lp2 = signal.lti(*signal.lp2lp(lp.num, lp.den, 2))
>>> w, mag_lp, p_lp = lp.bode()
>>> w, mag_lp2, p_lp2 = lp2.bode(w)
```

```

>>> plt.plot(w, mag_lp, label='Lowpass')
>>> plt.plot(w, mag_lp2, label='Transformed Lowpass')
>>> plt.semilogx()
>>> plt.grid()
>>> plt.xlabel('Frequency [rad/s]')
>>> plt.ylabel('Magnitude [dB]')
>>> plt.legend()

```



scipy.signal.lp2lp_zpk

`scipy.signal.lp2lp_zpk(z, p, k, wo=1.0)`

Transform a lowpass filter prototype to a different frequency.

Return an analog low-pass filter with cutoff frequency ω_0 from an analog low-pass filter prototype with unity cutoff frequency, using zeros, poles, and gain ('zpk') representation.

Parameters

- z** [array_like] Zeros of the analog filter transfer function.
- p** [array_like] Poles of the analog filter transfer function.
- k** [float] System gain of the analog filter transfer function.
- wo** [float] Desired cutoff, as angular frequency (e.g., rad/s). Defaults to no change.

Returns

- z** [ndarray] Zeros of the transformed low-pass filter transfer function.
- p** [ndarray] Poles of the transformed low-pass filter transfer function.
- k** [float] System gain of the transformed low-pass filter.

See also:

[`lp2hp_zpk`](#), [`lp2bp_zpk`](#), [`lp2bs_zpk`](#), [`bilinear`](#)
[`lp2lp`](#)

Notes

This is derived from the s-plane substitution

$$s \rightarrow \frac{s}{\omega_0}$$

New in version 1.1.0.

scipy.signal.normalize

`scipy.signal.normalize(b, a)`

Normalize numerator/denominator of a continuous-time transfer function.

If values of *b* are too close to 0, they are removed. In that case, a `BadCoefficients` warning is emitted.

Parameters

b: array_like

Numerator of the transfer function. Can be a 2-D array to normalize multiple transfer functions.

a: array_like

Denominator of the transfer function. At most 1-D.

Returns

num: array

The numerator of the normalized transfer function. At least a 1-D array. A 2-D array if the input *num* is a 2-D array.

den: 1-D array

The denominator of the normalized transfer function.

Notes

Coefficients for both the numerator and denominator should be specified in descending exponent order (e.g., $s^2 + 3s + 5$ would be represented as `[1, 3, 5]`).

6.22.5 Matlab-style IIR filter design

<code>butter(N, Wn[, btype, analog, output, fs])</code>	Butterworth digital and analog filter design.
<code>buttord(wp, ws, gpass, gstop[, analog, fs])</code>	Butterworth filter order selection.
<code>cheby1(N, rp, Wn[, btype, analog, output, fs])</code>	Chebyshev type I digital and analog filter design.
<code>cheb1ord(wp, ws, gpass, gstop[, analog, fs])</code>	Chebyshev type I filter order selection.
<code>cheby2(N, rs, Wn[, btype, analog, output, fs])</code>	Chebyshev type II digital and analog filter design.
<code>cheb2ord(wp, ws, gpass, gstop[, analog, fs])</code>	Chebyshev type II filter order selection.
<code>ellip(N, rp, rs, Wn[, btype, analog, output, fs])</code>	Elliptic (Cauer) digital and analog filter design.
<code>ellipord(wp, ws, gpass, gstop[, analog, fs])</code>	Elliptic (Cauer) filter order selection.
<code>bessel(N, Wn[, btype, analog, output, norm, fs])</code>	Bessel/Thomson digital and analog filter design.
<code>iirnotch(w0, Q[, fs])</code>	Design second-order IIR notch digital filter.
<code>iirpeak(w0, Q[, fs])</code>	Design second-order IIR peak (resonant) digital filter.
<code>iircomb(w0, Q[, ftype, fs])</code>	Design IIR notching or peaking digital comb filter.

scipy.signal.butter

`scipy.signal.butter` (*N*, *Wn*, *btype*='low', *analog*=False, *output*='ba', *fs*=None)

Butterworth digital and analog filter design.

Design an Nth-order digital or analog Butterworth filter and return the filter coefficients.

Parameters

N	[int] The order of the filter.
Wn	[array_like] The critical frequency or frequencies. For lowpass and highpass filters, <i>Wn</i> is a scalar; for bandpass and bandstop filters, <i>Wn</i> is a length-2 sequence. For a Butterworth filter, this is the point at which the gain drops to $1/\sqrt{2}$ that of the passband (the “-3 dB point”). For digital filters, <i>Wn</i> are in the same units as <i>fs</i> . By default, <i>fs</i> is 2 half-cycles/sample, so these are normalized from 0 to 1, where 1 is the Nyquist frequency. (<i>Wn</i> is thus in half-cycles / sample.) For analog filters, <i>Wn</i> is an angular frequency (e.g. rad/s).
btype	[{'lowpass', 'highpass', 'bandpass', 'bandstop'}, optional] The type of filter. Default is 'lowpass'.
analog	[bool, optional] When True, return an analog filter, otherwise a digital filter is returned.
output	[{'ba', 'zpk', 'sos'}, optional] Type of output: numerator/denominator ('ba'), pole-zero ('zpk'), or second-order sections ('sos'). Default is 'ba' for backwards compatibility, but 'sos' should be used for general-purpose filtering.
fs	[float, optional] The sampling frequency of the digital system. New in version 1.2.0.

Returns

b, a	[ndarray, ndarray] Numerator (<i>b</i>) and denominator (<i>a</i>) polynomials of the IIR filter. Only returned if <i>output</i> ='ba'.
z, p, k	[ndarray, ndarray, float] Zeros, poles, and system gain of the IIR filter transfer function. Only returned if <i>output</i> ='zpk'.
sos	[ndarray] Second-order sections representation of the IIR filter. Only returned if <i>output</i> ='sos'.

See also:

[*buttor*](#), [*buttap*](#)

Notes

The Butterworth filter has maximally flat frequency response in the passband.

The 'sos' output parameter was added in 0.16.0.


If the transfer function form $[b, a]$ is requested, numerical problems can occur since the conversion between roots and the polynomial coefficients is a numerically sensitive operation, even for $N \geq 4$. It is recommended to work with the SOS representation.

Examples

Design an analog filter and plot its frequency response, showing the critical points:

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt

>>> b, a = signal.butter(4, 100, 'low', analog=True)
>>> w, h = signal.freqs(b, a)
>>> plt.semilogx(w, 20 * np.log10(abs(h)))
>>> plt.title('Butterworth filter frequency response')
>>> plt.xlabel('Frequency [radians / second]')
>>> plt.ylabel('Amplitude [dB]')
>>> plt.margins(0, 0.1)
>>> plt.grid(which='both', axis='both')
>>> plt.axvline(100, color='green') # cutoff frequency
>>> plt.show()
```



Generate a signal made up of 10 Hz and 20 Hz, sampled at 1 kHz

```
>>> t = np.linspace(0, 1, 1000, False) # 1 second
>>> sig = np.sin(2*np.pi*10*t) + np.sin(2*np.pi*20*t)
>>> fig, (ax1, ax2) = plt.subplots(2, 1, sharex=True)
>>> ax1.plot(t, sig)
>>> ax1.set_title('10 Hz and 20 Hz sinusoids')
>>> ax1.axis([0, 1, -2, 2])
```

Design a digital high-pass filter at 15 Hz to remove the 10 Hz tone, and apply it to the signal. (It's recommended to use second-order sections format when filtering, to avoid numerical error with transfer function (ba) format):

```
>>> sos = signal.butter(10, 15, 'hp', fs=1000, output='sos')
>>> filtered = signal.sosfilt(sos, sig)
>>> ax2.plot(t, filtered)
>>> ax2.set_title('After 15 Hz high-pass filter')
```


(continues on next page)

(continued from previous page)

```

>>> ax2.axis([0, 1, -2, 2])
>>> ax2.set_xlabel('Time [seconds]')
>>> plt.tight_layout()
>>> plt.show()

```



scipy.signal.buttord

`scipy.signal.buttord` (*wp*, *ws*, *gpass*, *gstop*, *analog=False*, *fs=None*)

Butterworth filter order selection.

Return the order of the lowest order digital or analog Butterworth filter that loses no more than *gpass* dB in the passband and has at least *gstop* dB attenuation in the stopband.

Parameters

wp, ws [float] Passband and stopband edge frequencies.
 For digital filters, these are in the same units as *fs*. By default, *fs* is 2 half-cycles/sample, so these are normalized from 0 to 1, where 1 is the Nyquist frequency. (*wp* and *ws* are thus in half-cycles / sample.) For example:

- Lowpass: *wp* = 0.2, *ws* = 0.3
- Highpass: *wp* = 0.3, *ws* = 0.2
- Bandpass: *wp* = [0.2, 0.5], *ws* = [0.1, 0.6]
- Bandstop: *wp* = [0.1, 0.6], *ws* = [0.2, 0.5]

For analog filters, *wp* and *ws* are angular frequencies (e.g., rad/s).

gpass [float] The maximum loss in the passband (dB).

gstop [float] The minimum attenuation in the stopband (dB).

analog [bool, optional] When True, return an analog filter, otherwise a digital filter is returned.

fs [float, optional] The sampling frequency of the digital system.
 New in version 1.2.0.

Returns

ord [int] The lowest order for a Butterworth filter which meets specs.

wn [ndarray or float] The Butterworth natural frequency (i.e. the “3dB frequency”). Should be used with `butter` to give filter results. If `fs` is specified, this is in the same units, and `fs` must also be passed to `butter`.

See also:

`butter`

Filter design using order and critical points

`cheb1ord`

Find order and critical points from passband and stopband spec

`cheb2ord`, `ellipord`

`iirfilter`

General filter design using order and critical frequencies

`iirdesign`

General filter design using passband and stopband spec

Examples

Design an analog bandpass filter with passband within 3 dB from 20 to 50 rad/s, while rejecting at least -40 dB below 14 and above 60 rad/s. Plot its frequency response, showing the passband and stopband constraints in gray.

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt

>>> N, Wn = signal.buttord([20, 50], [14, 60], 3, 40, True)
>>> b, a = signal.butter(N, Wn, 'band', True)
>>> w, h = signal.freqs(b, a, np.logspace(1, 2, 500))
>>> plt.semilogx(w, 20 * np.log10(abs(h)))
>>> plt.title('Butterworth bandpass filter fit to constraints')
>>> plt.xlabel('Frequency [radians / second]')
>>> plt.ylabel('Amplitude [dB]')
>>> plt.grid(which='both', axis='both')
>>> plt.fill([1, 14, 14, 1], [-40, -40, 99, 99], '0.9', lw=0) # stop
>>> plt.fill([20, 20, 50, 50], [-99, -3, -3, -99], '0.9', lw=0) # pass
>>> plt.fill([60, 60, 1e9, 1e9], [99, -40, -40, 99], '0.9', lw=0) # stop
>>> plt.axis([10, 100, -60, 3])
>>> plt.show()
```

scipy.signal.cheby1

`scipy.signal.cheby1` (*N*, *rp*, *Wn*, *btype*='low', *analog*=False, *output*='ba', *fs*=None)


Chebyshev type I digital and analog filter design.

Design an Nth-order digital or analog Chebyshev type I filter and return the filter coefficients.

Parameters

N [int] The order of the filter.

rp [float] The maximum ripple allowed below unity gain in the passband. Specified in decibels, as a positive number.



- Wn** [array_like] A scalar or length-2 sequence giving the critical frequencies. For Type I filters, this is the point in the transition band at which the gain first drops below $-rp$. For digital filters, Wn are in the same units as fs . By default, fs is 2 half-cycles/sample, so these are normalized from 0 to 1, where 1 is the Nyquist frequency. (Wn is thus in half-cycles / sample.)
For analog filters, Wn is an angular frequency (e.g., rad/s).
- btype** [{‘lowpass’, ‘highpass’, ‘bandpass’, ‘bandstop’}, optional] The type of filter. Default is ‘lowpass’.
- analog** [bool, optional] When True, return an analog filter, otherwise a digital filter is returned.
- output** [{‘ba’, ‘zpk’, ‘sos’}, optional] Type of output: numerator/denominator (‘ba’), pole-zero (‘zpk’), or second-order sections (‘sos’). Default is ‘ba’ for backwards compatibility, but ‘sos’ should be used for general-purpose filtering.
- fs** [float, optional] The sampling frequency of the digital system.
New in version 1.2.0.

Returns

- b, a** [ndarray, ndarray] Numerator (b) and denominator (a) polynomials of the IIR filter. Only returned if `output='ba'`.
- z, p, k** [ndarray, ndarray, float] Zeros, poles, and system gain of the IIR filter transfer function. Only returned if `output='zpk'`.
- sos** [ndarray] Second-order sections representation of the IIR filter. Only returned if `output=='sos'`.

See also:

[*cheb1ord*](#), [*cheb1ap*](#)

Notes

The Chebyshev type I filter maximizes the rate of cutoff between the frequency response's passband and stopband, at the expense of ripple in the passband and increased ringing in the step response.

Type I filters roll off faster than Type II (*cheby2*), but Type II filters do not have any ripple in the passband.

The equiripple passband has N maxima or minima (for example, a 5th-order filter has 3 maxima and 2 minima). Consequently, the DC gain is unity for odd-order filters, or $-r_p$ dB for even-order filters.


The 'sos' output parameter was added in 0.16.0.

Examples

Design an analog filter and plot its frequency response, showing the critical points:

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt

>>> b, a = signal.cheby1(4, 5, 100, 'low', analog=True)
>>> w, h = signal.freqs(b, a)
>>> plt.semilogx(w, 20 * np.log10(abs(h)))
>>> plt.title('Chebyshev Type I frequency response (rp=5)')
>>> plt.xlabel('Frequency [radians / second]')
>>> plt.ylabel('Amplitude [dB]')
>>> plt.margins(0, 0.1)
>>> plt.grid(which='both', axis='both')
>>> plt.axvline(100, color='green') # cutoff frequency
>>> plt.axhline(-5, color='green') # rp
>>> plt.show()
```



Generate a signal made up of 10 Hz and 20 Hz, sampled at 1 kHz

```

>>> t = np.linspace(0, 1, 1000, False) # 1 second
>>> sig = np.sin(2*np.pi*10*t) + np.sin(2*np.pi*20*t)
>>> fig, (ax1, ax2) = plt.subplots(2, 1, sharex=True)
>>> ax1.plot(t, sig)
>>> ax1.set_title('10 Hz and 20 Hz sinusoids')
>>> ax1.axis([0, 1, -2, 2])


```

Design a digital high-pass filter at 15 Hz to remove the 10 Hz tone, and apply it to the signal. (It's recommended to use second-order sections format when filtering, to avoid numerical error with transfer function (ba) format):

```

>>> sos = signal.cheby1(10, 1, 15, 'hp', fs=1000, output='sos')
>>> filtered = signal.sosfilt(sos, sig)
>>> ax2.plot(t, filtered)
>>> ax2.set_title('After 15 Hz high-pass filter')
>>> ax2.axis([0, 1, -2, 2])
>>> ax2.set_xlabel('Time [seconds]')
>>> plt.tight_layout()
>>> plt.show()

```



scipy.signal.cheb1ord

`scipy.signal.cheb1ord`(*wp*, *ws*, *gpass*, *gstop*, *analog=False*, *fs=None*)

Chebyshev type I filter order selection.

Return the order of the lowest order digital or analog Chebyshev Type I filter that loses no more than *gpass* dB in the passband and has at least *gstop* dB attenuation in the stopband.

Parameters

- wp, ws** [float] Passband and stopband edge frequencies.
 For digital filters, these are in the same units as *fs*. By default, *fs* is 2 half-cycles/sample, so these are normalized from 0 to 1, where 1 is the Nyquist frequency. (*wp* and *ws* are thus in half-cycles / sample.) For example:
- Lowpass: *wp* = 0.2, *ws* = 0.3

- Highpass: $w_p = 0.3$, $w_s = 0.2$
- Bandpass: $w_p = [0.2, 0.5]$, $w_s = [0.1, 0.6]$
- Bandstop: $w_p = [0.1, 0.6]$, $w_s = [0.2, 0.5]$

For analog filters, w_p and w_s are angular frequencies (e.g., rad/s).

gpass	[float] The maximum loss in the passband (dB).
gstop	[float] The minimum attenuation in the stopband (dB).
analog	[bool, optional] When True, return an analog filter, otherwise a digital filter is returned.
fs	[float, optional] The sampling frequency of the digital system. New in version 1.2.0.

Returns

ord	[int] The lowest order for a Chebyshev type I filter that meets specs.
wn	[ndarray or float] The Chebyshev natural frequency (the “3dB frequency”) for use with <code>cheby1</code> to give filter results. If f_s is specified, this is in the same units, and f_s must also be passed to <code>cheby1</code> .

See also:

`cheby1`

Filter design using order and critical points

`buttord`

Find order and critical points from passband and stopband spec

`cheb2ord`, `ellipord`

`iirfilter`

General filter design using order and critical frequencies

`iirdesign`


General filter design using passband and stopband spec

Examples

Design a digital lowpass filter such that the passband is within 3 dB up to $0.2 \cdot (f_s/2)$, while rejecting at least -40 dB above $0.3 \cdot (f_s/2)$. Plot its frequency response, showing the passband and stopband constraints in gray.

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> N, Wn = signal.cheb1ord(0.2, 0.3, 3, 40)
>>> b, a = signal.cheby1(N, 3, Wn, 'low')
>>> w, h = signal.freqz(b, a)
>>> plt.semilogx(w / np.pi, 20 * np.log10(abs(h)))
>>> plt.title('Chebyshev I lowpass filter fit to constraints')
>>> plt.xlabel('Normalized frequency')
>>> plt.ylabel('Amplitude [dB]')
>>> plt.grid(which='both', axis='both')
>>> plt.fill([.01, 0.2, 0.2, .01], [-3, -3, -99, -99], '0.9', lw=0) # stop
>>> plt.fill([0.3, 0.3, 2, 2], [9, -40, -40, 9], '0.9', lw=0) # pass
>>> plt.axis([0.08, 1, -60, 3])
>>> plt.show()
```

scipy.signal.cheby2

`scipy.signal.cheby2` (*N*, *rs*, *Wn*, *btype*='low', *analog*=False, *output*='ba', *fs*=None)

Chebyshev type II digital and analog filter design.

Design an Nth-order digital or analog Chebyshev type II filter and return the filter coefficients.

Parameters

N	[int] The order of the filter.
rs	[float] The minimum attenuation required in the stop band. Specified in decibels, as a positive number.
Wn	[array_like] A scalar or length-2 sequence giving the critical frequencies. For Type II filters, this is the point in the transition band at which the gain first reaches <i>-rs</i> . For digital filters, <i>Wn</i> are in the same units as <i>fs</i> . By default, <i>fs</i> is 2 half-cycles/sample, so these are normalized from 0 to 1, where 1 is the Nyquist frequency. (<i>Wn</i> is thus in half-cycles / sample.) For analog filters, <i>Wn</i> is an angular frequency (e.g., rad/s).
btype	[{'lowpass', 'highpass', 'bandpass', 'bandstop'}, optional] The type of filter. Default is 'lowpass'.
analog	[bool, optional] When True, return an analog filter, otherwise a digital filter is returned.
output	[{'ba', 'zpk', 'sos'}, optional] Type of output: numerator/denominator ('ba'), pole-zero ('zpk'), or second-order sections ('sos'). Default is 'ba' for backwards compatibility, but 'sos' should be used for general-purpose filtering.
fs	[float, optional] The sampling frequency of the digital system. New in version 1.2.0.

Returns

b, a	[ndarray, ndarray] Numerator (<i>b</i>) and denominator (<i>a</i>) polynomials of the IIR filter. Only returned if <i>output</i> ='ba'.
z, p, k	[ndarray, ndarray, float] Zeros, poles, and system gain of the IIR filter transfer function. Only returned if <i>output</i> ='zpk'.
sos	[ndarray] Second-order sections representation of the IIR filter. Only returned if <i>output</i> ='sos'.

See also:

cheb2ord, *cheb2ap*

Notes

The Chebyshev type II filter maximizes the rate of cutoff between the frequency response's passband and stopband, at the expense of ripple in the stopband and increased ringing in the step response.

Type II filters do not roll off as fast as Type I (*cheby1*).


The 'sos' output parameter was added in 0.16.0.

Examples

Design an analog filter and plot its frequency response, showing the critical points:

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> b, a = signal.cheby2(4, 40, 100, 'low', analog=True)
>>> w, h = signal.freqs(b, a)
>>> plt.semilogx(w, 20 * np.log10(abs(h)))
>>> plt.title('Chebyshev Type II frequency response (rs=40)')
>>> plt.xlabel('Frequency [radians / second]')
>>> plt.ylabel('Amplitude [dB]')
>>> plt.margins(0, 0.1)
>>> plt.grid(which='both', axis='both')
>>> plt.axvline(100, color='green') # cutoff frequency
>>> plt.axhline(-40, color='green') # rs
>>> plt.show()
```



Generate a signal made up of 10 Hz and 20 Hz, sampled at 1 kHz

```

>>> t = np.linspace(0, 1, 1000, False) # 1 second
>>> sig = np.sin(2*np.pi*10*t) + np.sin(2*np.pi*20*t)
>>> fig, (ax1, ax2) = plt.subplots(2, 1, sharex=True)
>>> ax1.plot(t, sig)
>>> ax1.set_title('10 Hz and 20 Hz sinusoids')
>>> ax1.axis([0, 1, -2, 2])


```

Design a digital high-pass filter at 17 Hz to remove the 10 Hz tone, and apply it to the signal. (It's recommended to use second-order sections format when filtering, to avoid numerical error with transfer function (ba) format):

```

>>> sos = signal.cheby2(12, 20, 17, 'hp', fs=1000, output='sos')
>>> filtered = signal.sosfilt(sos, sig)
>>> ax2.plot(t, filtered)
>>> ax2.set_title('After 17 Hz high-pass filter')
>>> ax2.axis([0, 1, -2, 2])
>>> ax2.set_xlabel('Time [seconds]')
>>> plt.show()

```



scipy.signal.cheb2ord

`scipy.signal.cheb2ord` (*wp*, *ws*, *gpass*, *gstop*, *analog=False*, *fs=None*)
Chebyshev type II filter order selection.

Return the order of the lowest order digital or analog Chebyshev Type II filter that loses no more than *gpass* dB in the passband and has at least *gstop* dB attenuation in the stopband.

Parameters

- wp, ws** [float] Passband and stopband edge frequencies.
For digital filters, these are in the same units as *fs*. By default, *fs* is 2 half-cycles/sample, so these are normalized from 0 to 1, where 1 is the Nyquist frequency. (*wp* and *ws* are thus in half-cycles / sample.) For example:
- Lowpass: *wp* = 0.2, *ws* = 0.3
 - Highpass: *wp* = 0.3, *ws* = 0.2

- Bandpass: $w_p = [0.2, 0.5]$, $w_s = [0.1, 0.6]$
 - Bandstop: $w_p = [0.1, 0.6]$, $w_s = [0.2, 0.5]$
- For analog filters, w_p and w_s are angular frequencies (e.g., rad/s).

gpass [float] The maximum loss in the passband (dB).
gstop [float] The minimum attenuation in the stopband (dB).
analog [bool, optional] When True, return an analog filter, otherwise a digital filter is returned.
fs [float, optional] The sampling frequency of the digital system.
 New in version 1.2.0.

Returns

ord [int] The lowest order for a Chebyshev type II filter that meets specs.
wn [ndarray or float] The Chebyshev natural frequency (the “3dB frequency”) for use with `cheby2` to give filter results. If f_s is specified, this is in the same units, and f_s must also be passed to `cheby2`.

See also:

`cheby2`

Filter design using order and critical points

`buttord`

Find order and critical points from passband and stopband spec

`cheblord`, `ellipord`

`iirfilter`

General filter design using order and critical frequencies

`iirdesign`


General filter design using passband and stopband spec

Examples

Design a digital bandstop filter which rejects -60 dB from $0.2 \cdot (f_s/2)$ to $0.5 \cdot (f_s/2)$, while staying within 3 dB below $0.1 \cdot (f_s/2)$ or above $0.6 \cdot (f_s/2)$. Plot its frequency response, showing the passband and stopband constraints in gray.

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt

>>> N, Wn = signal.cheb2ord([0.1, 0.6], [0.2, 0.5], 3, 60)
>>> b, a = signal.cheby2(N, 60, Wn, 'stop')
>>> w, h = signal.freqz(b, a)
>>> plt.semilogx(w / np.pi, 20 * np.log10(abs(h)))
>>> plt.title('Chebyshev II bandstop filter fit to constraints')
>>> plt.xlabel('Normalized frequency')
>>> plt.ylabel('Amplitude [dB]')
>>> plt.grid(which='both', axis='both')
>>> plt.fill([.01, .1, .1, .01], [-3, -3, -99, -99], '0.9', lw=0) # stop
>>> plt.fill([.2, .2, .5, .5], [ 9, -60, -60,  9], '0.9', lw=0) # pass
>>> plt.fill([.6, .6, 2, 2], [-99, -3, -3, -99], '0.9', lw=0) # stop
>>> plt.axis([0.06, 1, -80, 3])
>>> plt.show()
```



scipy.signal.ellip

`scipy.signal.ellip` (*N*, *rp*, *rs*, *Wn*, *btype*='low', *analog*=False, *output*='ba', *fs*=None)
 Elliptic (Cauer) digital and analog filter design.

Design an Nth-order digital or analog elliptic filter and return the filter coefficients.

Parameters

N	[int] The order of the filter.
rp	[float] The maximum ripple allowed below unity gain in the passband. Specified in decibels, as a positive number.
rs	[float] The minimum attenuation required in the stop band. Specified in decibels, as a positive number.
Wn	[array_like] A scalar or length-2 sequence giving the critical frequencies. For elliptic filters, this is the point in the transition band at which the gain first drops below <i>-rp</i> . For digital filters, <i>Wn</i> are in the same units as <i>fs</i> . By default, <i>fs</i> is 2 half-cycles/sample, so these are normalized from 0 to 1, where 1 is the Nyquist frequency. (<i>Wn</i> is thus in half-cycles / sample.) For analog filters, <i>Wn</i> is an angular frequency (e.g., rad/s).
btype	[{'lowpass', 'highpass', 'bandpass', 'bandstop'}, optional] The type of filter. Default is 'lowpass'.
analog	[bool, optional] When True, return an analog filter, otherwise a digital filter is returned.
output	[{'ba', 'zpk', 'sos'}, optional] Type of output: numerator/denominator ('ba'), pole-zero ('zpk'), or second-order sections ('sos'). Default is 'ba' for backwards compatibility, but 'sos' should be used for general-purpose filtering.
fs	[float, optional] The sampling frequency of the digital system. New in version 1.2.0.

Returns

b, a	[ndarray, ndarray] Numerator (<i>b</i>) and denominator (<i>a</i>) polynomials of the IIR filter. Only returned if <code>output='ba'</code> .
z, p, k	[ndarray, ndarray, float] Zeros, poles, and system gain of the IIR filter transfer function. Only returned if <code>output='zpk'</code> .
sos	[ndarray] Second-order sections representation of the IIR filter. Only returned if <code>output=='sos'</code> .

See also:

ellipord, *ellipap*

Notes

Also known as Causer or Zolotarev filters, the elliptical filter maximizes the rate of transition between the frequency response's passband and stopband, at the expense of ripple in both, and increased ringing in the step response.

As *rp* approaches 0, the elliptical filter becomes a Chebyshev type II filter (*cheby2*). As *rs* approaches 0, it becomes a Chebyshev type I filter (*cheby1*). As both approach 0, it becomes a Butterworth filter (*butter*).

The equiripple passband has *N* maxima or minima (for example, a 5th-order filter has 3 maxima and 2 minima). Consequently, the DC gain is unity for odd-order filters, or -*rp* dB for even-order filters.

The 'sos' output parameter was added in 0.16.0.

Examples

Design an analog filter and plot its frequency response, showing the critical points:

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt

>>> b, a = signal.ellip(4, 5, 40, 100, 'low', analog=True)
>>> w, h = signal.freqs(b, a)
>>> plt.semilogx(w, 20 * np.log10(abs(h)))
>>> plt.title('Elliptic filter frequency response (rp=5, rs=40)')
>>> plt.xlabel('Frequency [radians / second]')
>>> plt.ylabel('Amplitude [dB]')
>>> plt.margins(0, 0.1)
>>> plt.grid(which='both', axis='both')
>>> plt.axvline(100, color='green') # cutoff frequency
>>> plt.axhline(-40, color='green') # rs
>>> plt.axhline(-5, color='green') # rp
>>> plt.show()
```


Generate a signal made up of 10 Hz and 20 Hz, sampled at 1 kHz

```
>>> t = np.linspace(0, 1, 1000, False) # 1 second
>>> sig = np.sin(2*np.pi*10*t) + np.sin(2*np.pi*20*t)
>>> fig, (ax1, ax2) = plt.subplots(2, 1, sharex=True)
>>> ax1.plot(t, sig)
>>> ax1.set_title('10 Hz and 20 Hz sinusoids')
>>> ax1.axis([0, 1, -2, 2])
```

Design a digital high-pass filter at 17 Hz to remove the 10 Hz tone, and apply it to the signal. (It's recommended to use second-order sections format when filtering, to avoid numerical error with transfer function (ba) format):


```
>>> sos = signal.ellip(8, 1, 100, 17, 'hp', fs=1000, output='sos')
>>> filtered = signal.sosfilt(sos, sig)
>>> ax2.plot(t, filtered)
>>> ax2.set_title('After 17 Hz high-pass filter')
```

(continues on next page)



(continued from previous page)

```
>>> ax2.axis([0, 1, -2, 2])
>>> ax2.set_xlabel('Time [seconds]')
>>> plt.tight_layout()
>>> plt.show()
```



scipy.signal.ellipord`scipy.signal.ellipord` (*wp*, *ws*, *gpass*, *gstop*, *analog=False*, *fs=None*)

Elliptic (Cauer) filter order selection.

Return the order of the lowest order digital or analog elliptic filter that loses no more than *gpass* dB in the passband and has at least *gstop* dB attenuation in the stopband.

Parameters

wp, ws	[float] Passband and stopband edge frequencies. For digital filters, these are in the same units as <i>fs</i> . By default, <i>fs</i> is 2 half-cycles/sample, so these are normalized from 0 to 1, where 1 is the Nyquist frequency. (<i>wp</i> and <i>ws</i> are thus in half-cycles / sample.) For example: <ul style="list-style-type: none">• Lowpass: <i>wp</i> = 0.2, <i>ws</i> = 0.3• Highpass: <i>wp</i> = 0.3, <i>ws</i> = 0.2• Bandpass: <i>wp</i> = [0.2, 0.5], <i>ws</i> = [0.1, 0.6]• Bandstop: <i>wp</i> = [0.1, 0.6], <i>ws</i> = [0.2, 0.5] For analog filters, <i>wp</i> and <i>ws</i> are angular frequencies (e.g., rad/s).
gpass	[float] The maximum loss in the passband (dB).
gstop	[float] The minimum attenuation in the stopband (dB).
analog	[bool, optional] When True, return an analog filter, otherwise a digital filter is returned.
fs	[float, optional] The sampling frequency of the digital system. New in version 1.2.0.

Returns

ord	[int] The lowest order for an Elliptic (Cauer) filter that meets specs.
wn	[ndarray or float] The Chebyshev natural frequency (the “3dB frequency”) for use with <code>ellip</code> to give filter results. If <i>fs</i> is specified, this is in the same units, and <i>fs</i> must also be passed to <code>ellip</code> .

See also:**`ellip`**

Filter design using order and critical points

`buttord`

Find order and critical points from passband and stopband spec

`cheb1ord`, `cheb2ord`**`iirfilter`**

General filter design using order and critical frequencies

`iirdesign`


General filter design using passband and stopband spec

Examples

Design an analog highpass filter such that the passband is within 3 dB above 30 rad/s, while rejecting -60 dB at 10 rad/s. Plot its frequency response, showing the passband and stopband constraints in gray.

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> N, Wn = signal.ellipord(30, 10, 3, 60, True)
>>> b, a = signal.ellip(N, 3, 60, Wn, 'high', True)
>>> w, h = signal.freqs(b, a, np.logspace(0, 3, 500))
>>> plt.semilogx(w, 20 * np.log10(abs(h)))
>>> plt.title('Elliptical highpass filter fit to constraints')
>>> plt.xlabel('Frequency [radians / second]')
>>> plt.ylabel('Amplitude [dB]')
>>> plt.grid(which='both', axis='both')
>>> plt.fill([.1, 10, 10, .1], [1e4, 1e4, -60, -60], '0.9', lw=0) # stop
>>> plt.fill([30, 30, 1e9, 1e9], [-99, -3, -3, -99], '0.9', lw=0) # pass
>>> plt.axis([1, 300, -80, 3])
>>> plt.show()
```



scipy.signal.bessel

`scipy.signal.bessel` (*N*, *Wn*, *btype*='low', *analog*=False, *output*='ba', *norm*='phase', *fs*=None)
Bessel/Thomson digital and analog filter design.

Design an Nth-order digital or analog Bessel filter and return the filter coefficients.

Parameters

- N** [int] The order of the filter.
- Wn** [array_like] A scalar or length-2 sequence giving the critical frequencies (defined by the *norm* parameter). For analog filters, *Wn* is an angular frequency (e.g., rad/s).

For digital filters, Wn are in the same units as fs . By default, fs is 2 half-cycles/sample, so these are normalized from 0 to 1, where 1 is the Nyquist frequency. (Wn is thus in half-cycles / sample.)

btype	[[‘lowpass’, ‘highpass’, ‘bandpass’, ‘bandstop’], optional] The type of filter. Default is ‘lowpass’.						
analog	[bool, optional] When True, return an analog filter, otherwise a digital filter is returned. (See Notes.)						
output	[[‘ba’, ‘zpk’, ‘sos’], optional] Type of output: numerator/denominator (‘ba’), pole-zero (‘zpk’), or second-order sections (‘sos’). Default is ‘ba’.						
norm	[[‘phase’, ‘delay’, ‘mag’], optional] Critical frequency normalization: <table> <tr> <td>phase</td> <td>The filter is normalized such that the phase response reaches its midpoint at angular (e.g. rad/s) frequency Wn. This happens for both low-pass and high-pass filters, so this is the “phase-matched” case. The magnitude response asymptotes are the same as a Butterworth filter of the same order with a cutoff of Wn. This is the default, and matches MATLAB’s implementation.</td> </tr> <tr> <td>delay</td> <td>The filter is normalized such that the group delay in the passband is $1/Wn$ (e.g., seconds). This is the “natural” type obtained by solving Bessel polynomials.</td> </tr> <tr> <td>mag</td> <td>The filter is normalized such that the gain magnitude is -3 dB at angular frequency Wn.</td> </tr> </table>	phase	The filter is normalized such that the phase response reaches its midpoint at angular (e.g. rad/s) frequency Wn . This happens for both low-pass and high-pass filters, so this is the “phase-matched” case. The magnitude response asymptotes are the same as a Butterworth filter of the same order with a cutoff of Wn . This is the default, and matches MATLAB’s implementation.	delay	The filter is normalized such that the group delay in the passband is $1/Wn$ (e.g., seconds). This is the “natural” type obtained by solving Bessel polynomials.	mag	The filter is normalized such that the gain magnitude is -3 dB at angular frequency Wn .
phase	The filter is normalized such that the phase response reaches its midpoint at angular (e.g. rad/s) frequency Wn . This happens for both low-pass and high-pass filters, so this is the “phase-matched” case. The magnitude response asymptotes are the same as a Butterworth filter of the same order with a cutoff of Wn . This is the default, and matches MATLAB’s implementation.						
delay	The filter is normalized such that the group delay in the passband is $1/Wn$ (e.g., seconds). This is the “natural” type obtained by solving Bessel polynomials.						
mag	The filter is normalized such that the gain magnitude is -3 dB at angular frequency Wn .						
fs	[float, optional] The sampling frequency of the digital system. New in version 0.18.0. New in version 1.2.0.						

Returns

b, a	[ndarray, ndarray] Numerator (b) and denominator (a) polynomials of the IIR filter. Only returned if <code>output='ba'</code> .
z, p, k	[ndarray, ndarray, float] Zeros, poles, and system gain of the IIR filter transfer function. Only returned if <code>output='zpk'</code> .
sos	[ndarray] Second-order sections representation of the IIR filter. Only returned if <code>output=='sos'</code> .

Notes

Also known as a Thomson filter, the analog Bessel filter has maximally flat group delay and maximally linear phase response, with very little ringing in the step response. [1]

The Bessel is inherently an analog filter. This function generates digital Bessel filters using the bilinear transform, which does not preserve the phase response of the analog filter. As such, it is only approximately correct at frequencies below about $fs/4$. To get maximally-flat group delay at higher frequencies, the analog Bessel filter must be transformed using phase-preserving techniques.

See `besselap` for implementation details and references.

The `'sos'` output parameter was added in 0.16.0.

References


[1]

Examples

Plot the phase-normalized frequency response, showing the relationship to the Butterworth's cutoff frequency (green):

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> b, a = signal.butter(4, 100, 'low', analog=True)
>>> w, h = signal.freqs(b, a)
>>> plt.semilogx(w, 20 * np.log10(np.abs(h)), color='silver', ls='dashed')
>>> b, a = signal.bessel(4, 100, 'low', analog=True, norm='phase')
>>> w, h = signal.freqs(b, a)
>>> plt.semilogx(w, 20 * np.log10(np.abs(h)))
>>> plt.title('Bessel filter magnitude response (with Butterworth)')
>>> plt.xlabel('Frequency [radians / second]')
>>> plt.ylabel('Amplitude [dB]')
>>> plt.margins(0, 0.1)
>>> plt.grid(which='both', axis='both')
>>> plt.axvline(100, color='green') # cutoff frequency
>>> plt.show()
```



and the phase midpoint:

```
>>> plt.figure()
>>> plt.semilogx(w, np.unwrap(np.angle(h)))
>>> plt.axvline(100, color='green') # cutoff frequency
>>> plt.axhline(-np.pi, color='red') # phase midpoint
>>> plt.title('Bessel filter phase response')
```


(continues on next page)

(continued from previous page)

```

>>> plt.xlabel('Frequency [radians / second]')
>>> plt.ylabel('Phase [radians]')
>>> plt.margins(0, 0.1)
>>> plt.grid(which='both', axis='both')
>>> plt.show()

```



Plot the magnitude-normalized frequency response, showing the -3 dB cutoff:

```

>>> b, a = signal.bessel(3, 10, 'low', analog=True, norm='mag')
>>> w, h = signal.freqs(b, a)
>>> plt.semilogx(w, 20 * np.log10(np.abs(h)))
>>> plt.axhline(-3, color='red') # -3 dB magnitude
>>> plt.axvline(10, color='green') # cutoff frequency
>>> plt.title('Magnitude-normalized Bessel filter frequency response')
>>> plt.xlabel('Frequency [radians / second]')
>>> plt.ylabel('Amplitude [dB]')
>>> plt.margins(0, 0.1)
>>> plt.grid(which='both', axis='both')
>>> plt.show()



```

Plot the delay-normalized filter, showing the maximally-flat group delay at 0.1 seconds:

```

>>> b, a = signal.bessel(5, 1/0.1, 'low', analog=True, norm='delay')
>>> w, h = signal.freqs(b, a)
>>> plt.figure()
>>> plt.semilogx(w[1:], -np.diff(np.unwrap(np.angle(h)))/np.diff(w))
>>> plt.axhline(0.1, color='red') # 0.1 seconds group delay
>>> plt.title('Bessel filter group delay')
>>> plt.xlabel('Frequency [radians / second]')
>>> plt.ylabel('Group delay [seconds]')
>>> plt.margins(0, 0.1)
>>> plt.grid(which='both', axis='both')
>>> plt.show()

```



scipy.signal.iirnotch

`scipy.signal.iirnotch(w0, Q, fs=2.0)`

Design second-order IIR notch digital filter.

A notch filter is a band-stop filter with a narrow bandwidth (high quality factor). It rejects a narrow frequency band and leaves the rest of the spectrum little changed.

Parameters

w0	[float] Frequency to remove from a signal. If <i>fs</i> is specified, this is in the same units as <i>fs</i> . By default, it is a normalized scalar that must satisfy $0 < w0 < 1$, with $w0 = 1$ corresponding to half of the sampling frequency.
Q	[float] Quality factor. Dimensionless parameter that characterizes notch filter -3 dB bandwidth <i>bw</i> relative to its center frequency, $Q = w0/bw$.
fs	[float, optional] The sampling frequency of the digital system. New in version 1.2.0.

Returns

b, a [ndarray, ndarray] Numerator (b) and denominator (a) polynomials of the IIR filter.

See also:

iirpeak

Notes

New in version 0.19.0.

References

[1]

Examples

Design and plot filter to remove the 60 Hz component from a signal sampled at 200 Hz, using a quality factor $Q = 30$

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```


```
>>> fs = 200.0 # Sample frequency (Hz)
>>> f0 = 60.0 # Frequency to be removed from signal (Hz)
>>> Q = 30.0 # Quality factor
>>> # Design notch filter
>>> b, a = signal.iirnotch(f0, Q, fs)
```

```
>>> # Frequency response
>>> freq, h = signal.freqz(b, a, fs=fs)
>>> # Plot
>>> fig, ax = plt.subplots(2, 1, figsize=(8, 6))
>>> ax[0].plot(freq, 20*np.log10(abs(h)), color='blue')
```

(continues on next page)

(continued from previous page)

```
>>> ax[0].set_title("Frequency Response")
>>> ax[0].set_ylabel("Amplitude (dB)", color='blue')
>>> ax[0].set_xlim([0, 100])
>>> ax[0].set_ylim([-25, 10])
>>> ax[0].grid()
>>> ax[1].plot(freq, np.unwrap(np.angle(h))*180/np.pi, color='green')
>>> ax[1].set_ylabel("Angle (degrees)", color='green')
>>> ax[1].set_xlabel("Frequency (Hz)")
>>> ax[1].set_xlim([0, 100])
>>> ax[1].set_yticks([-90, -60, -30, 0, 30, 60, 90])
>>> ax[1].set_ylim([-90, 90])
>>> ax[1].grid()
>>> plt.show()
```



scipy.signal.iirpeak`scipy.signal.iirpeak(w0, Q, fs=2.0)`

Design second-order IIR peak (resonant) digital filter.

A peak filter is a band-pass filter with a narrow bandwidth (high quality factor). It rejects components outside a narrow frequency band.

Parameters

w0	[float] Frequency to be retained in a signal. If <i>fs</i> is specified, this is in the same units as <i>fs</i> . By default, it is a normalized scalar that must satisfy $0 < w0 < 1$, with $w0 = 1$ corresponding to half of the sampling frequency.
Q	[float] Quality factor. Dimensionless parameter that characterizes peak filter -3 dB bandwidth <i>bw</i> relative to its center frequency, $Q = w0/bw$.
fs	[float, optional] The sampling frequency of the digital system. New in version 1.2.0.

Returns**b, a** [ndarray, ndarray] Numerator (b) and denominator (a) polynomials of the IIR filter.**See also:***iirnotch***Notes**

New in version 0.19.0.

References

[1]

ExamplesDesign and plot filter to remove the frequencies other than the 300 Hz component from a signal sampled at 1000 Hz, using a quality factor $Q = 30$

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```


```
>>> fs = 1000.0 # Sample frequency (Hz)
>>> f0 = 300.0 # Frequency to be retained (Hz)
>>> Q = 30.0 # Quality factor
>>> # Design peak filter
>>> b, a = signal.iirpeak(f0, Q, fs)
```

```
>>> # Frequency response
>>> freq, h = signal.freqz(b, a, fs=fs)
>>> # Plot
>>> fig, ax = plt.subplots(2, 1, figsize=(8, 6))
>>> ax[0].plot(freq, 20*np.log10(np.maximum(abs(h), 1e-5)), color='blue')
```

(continues on next page)

(continued from previous page)

```
>>> ax[0].set_title("Frequency Response")
>>> ax[0].set_ylabel("Amplitude (dB)", color='blue')
>>> ax[0].set_xlim([0, 500])
>>> ax[0].set_ylim([-50, 10])
>>> ax[0].grid()
>>> ax[1].plot(freq, np.unwrap(np.angle(h))*180/np.pi, color='green')
>>> ax[1].set_ylabel("Angle (degrees)", color='green')
>>> ax[1].set_xlabel("Frequency (Hz)")
>>> ax[1].set_xlim([0, 500])
>>> ax[1].set_yticks([-90, -60, -30, 0, 30, 60, 90])
>>> ax[1].set_ylim([-90, 90])
>>> ax[1].grid()
>>> plt.show()
```



scipy.signal.iircomb`scipy.signal.iircomb(w0, Q, ftype='notch', fs=2.0)`

Design IIR notching or peaking digital comb filter.

A notching comb filter is a band-stop filter with a narrow bandwidth (high quality factor). It rejects a narrow frequency band and leaves the rest of the spectrum little changed.

A peaking comb filter is a band-pass filter with a narrow bandwidth (high quality factor). It rejects components outside a narrow frequency band.

Parameters

- w0** [float] Frequency to attenuate (notching) or boost (peaking). If *fs* is specified, this is in the same units as *fs*. By default, it is a normalized scalar that must satisfy $0 < w0 < 1$, with $w0 = 1$ corresponding to half of the sampling frequency.
- Q** [float] Quality factor. Dimensionless parameter that characterizes notch filter -3 dB bandwidth *bw* relative to its center frequency, $Q = w0/bw$.
- ftype** [{'notch', 'peak'}] The type of comb filter generated by the function. If 'notch', then it returns a filter with notches at frequencies $0, w0, 2 * w0$, etc. If 'peak', then it returns a filter with peaks at frequencies $0.5 * w0, 1.5 * w0, 2.5 * w0$, etc. Default is 'notch'.
- fs** [float, optional] The sampling frequency of the signal. Default is 2.0.

Returns

- b, a** [ndarray, ndarray] Numerator (b) and denominator (a) polynomials of the IIR filter.

Raises**ValueError**

If *w0* is less than or equal to 0 or greater than or equal to $fs/2$, if *fs* is not divisible by *w0*, if *ftype* is not 'notch' or 'peak'

See also:[*iirnotch*](#)[*iirpeak*](#)**Notes**

For implementation details, see [1]. The TF implementation of the comb filter is numerically stable even at higher orders due to the use of a single repeated pole, which won't suffer from precision loss.

References

[1]

Examples

Design and plot notching comb filter at 20 Hz for a signal sampled at 200 Hz, using quality factor $Q = 30$

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> fs = 200.0 # Sample frequency (Hz)
>>> f0 = 20.0 # Frequency to be removed from signal (Hz)
>>> Q = 30.0 # Quality factor
>>> # Design notching comb filter
>>> b, a = signal.iircomb(f0, Q, ftype='notch', fs=fs)
```


```
>>> # Frequency response
>>> freq, h = signal.freqz(b, a, fs=fs)
>>> response = abs(h)
>>> # To avoid divide by zero when graphing
>>> response[response == 0] = 1e-20
>>> # Plot
>>> fig, ax = plt.subplots(2, 1, figsize=(8, 6))
>>> ax[0].plot(freq, 20*np.log10(abs(response)), color='blue')
>>> ax[0].set_title("Frequency Response")
>>> ax[0].set_ylabel("Amplitude (dB)", color='blue')
>>> ax[0].set_xlim([0, 100])
>>> ax[0].set_ylim([-30, 10])
>>> ax[0].grid()
>>> ax[1].plot(freq, np.unwrap(np.angle(h))*180/np.pi, color='green')
>>> ax[1].set_ylabel("Angle (degrees)", color='green')
>>> ax[1].set_xlabel("Frequency (Hz)")
>>> ax[1].set_xlim([0, 100])
>>> ax[1].set_yticks([-90, -60, -30, 0, 30, 60, 90])
>>> ax[1].set_ylim([-90, 90])
>>> ax[1].grid()
>>> plt.show()
```

Design and plot peaking comb filter at 250 Hz for a signal sampled at 1000 Hz, using quality factor $Q = 30$

```
>>> fs = 1000.0 # Sample frequency (Hz)
>>> f0 = 250.0 # Frequency to be retained (Hz)
>>> Q = 30.0 # Quality factor
>>> # Design peaking filter
>>> b, a = signal.iircomb(f0, Q, ftype='peak', fs=fs)
```


```
>>> # Frequency response
>>> freq, h = signal.freqz(b, a, fs=fs)
>>> response = abs(h)
>>> # To avoid divide by zero when graphing
>>> response[response == 0] = 1e-20
>>> # Plot
>>> fig, ax = plt.subplots(2, 1, figsize=(8, 6))
>>> ax[0].plot(freq, 20*np.log10(np.maximum(abs(h), 1e-5)), color='blue')
>>> ax[0].set_title("Frequency Response")
>>> ax[0].set_ylabel("Amplitude (dB)", color='blue')
```

(continues on next page)



(continued from previous page)

```
>>> ax[0].set_xlim([0, 500])
>>> ax[0].set_ylim([-80, 10])
>>> ax[0].grid()
>>> ax[1].plot(freq, np.unwrap(np.angle(h))*180/np.pi, color='green')
>>> ax[1].set_ylabel("Angle (degrees)", color='green')
>>> ax[1].set_xlabel("Frequency (Hz)")
>>> ax[1].set_xlim([0, 500])
>>> ax[1].set_yticks([-90, -60, -30, 0, 30, 60, 90])
>>> ax[1].set_ylim([-90, 90])
>>> ax[1].grid()
>>> plt.show()
```



6.22.6 Continuous-time linear systems

<code>lti(*system)</code>	Continuous-time linear time invariant system base class.
<code>StateSpace(*system, **kwargs)</code>	Linear Time Invariant system in state-space form.
<code>TransferFunction(*system, **kwargs)</code>	Linear Time Invariant system class in transfer function form.
<code>ZerosPolesGain(*system, **kwargs)</code>	Linear Time Invariant system class in zeros, poles, gain form.
<code>lsim(system, U, T[, X0, interp])</code>	Simulate output of a continuous-time linear system.
<code>lsim2(system[, U, T, X0])</code>	Simulate output of a continuous-time linear system, by using the ODE solver <code>scipy.integrate.odeint</code> .
<code>impulse(system[, X0, T, N])</code>	Impulse response of continuous-time system.
<code>impulse2(system[, X0, T, N])</code>	Impulse response of a single-input, continuous-time linear system.
<code>step(system[, X0, T, N])</code>	Step response of continuous-time system.
<code>step2(system[, X0, T, N])</code>	Step response of continuous-time system.
<code>freqresp(system[, w, n])</code>	Calculate the frequency response of a continuous-time system.
<code>bode(system[, w, n])</code>	Calculate Bode magnitude and phase data of a continuous-time system.

scipy.signal.lti

class `scipy.signal.lti` (**system*)
Continuous-time linear time invariant system base class.

Parameters

- *system** [arguments] The `lti` class can be instantiated with either 2, 3 or 4 arguments. The following gives the number of arguments and the corresponding continuous-time subclass that is created:
- 2: `TransferFunction`: (numerator, denominator)
 - 3: `ZerosPolesGain`: (zeros, poles, gain)
 - 4: `StateSpace`: (A, B, C, D)
- Each argument can be an array or a sequence.

See also:

[`ZerosPolesGain`](#), [`StateSpace`](#), [`TransferFunction`](#), [`dlti`](#)

Notes

`lti` instances do not exist directly. Instead, `lti` creates an instance of one of its subclasses: `StateSpace`, `TransferFunction` or `ZerosPolesGain`.

If (numerator, denominator) is passed in for `*system`, coefficients for both the numerator and denominator should be specified in descending exponent order (e.g., $s^2 + 3s + 5$ would be represented as `[1, 3, 5]`).

Changing the value of properties that are not directly part of the current system representation (such as the zeros of a `StateSpace` system) is very inefficient and may lead to numerical inaccuracies. It is better to convert to the specific system representation first. For example, call `sys = sys.to_zpk()` before accessing/changing the zeros, poles or gain.

Examples

```
>>> from scipy import signal
```

```
>>> signal.lti(1, 2, 3, 4)
StateSpaceContinuous(
array([[1]]),
array([[2]]),
array([[3]]),
array([[4]]),
dt: None
)
```

```
>>> signal.lti([1, 2], [3, 4], 5)
ZerosPolesGainContinuous(
array([1, 2]),
array([3, 4]),
5,
dt: None
)
```

```
>>> signal.lti([3, 4], [1, 2])
TransferFunctionContinuous(
array([3., 4.]),
array([1., 2.]),
dt: None
)
```

Attributes

dt Return the sampling time of the system, *None* for *lti* systems.
poles Poles of the system.
zeros Zeros of the system.

Methods

<code>bode(self[, w, n])</code>	Calculate Bode magnitude and phase data of a continuous-time system.
<code>freqresp(self[, w, n])</code>	Calculate the frequency response of a continuous-time system.
<code>impulse(self[, X0, T, N])</code>	Return the impulse response of a continuous-time system.
<code>output(self, U, T[, X0])</code>	Return the response of a continuous-time system to input <i>U</i> .
<code>step(self[, X0, T, N])</code>	Return the step response of a continuous-time system.
<code>to_discrete(self, dt[, method, alpha])</code>	Return a discretized version of the current system.

scipy.signal.lti.bode

`lti.bode` (*self*, *w=None*, *n=100*)

Calculate Bode magnitude and phase data of a continuous-time system.


Returns a 3-tuple containing arrays of frequencies [rad/s], magnitude [dB] and phase [deg]. See *bode* for details.

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> sys = signal.TransferFunction([1], [1, 1])
>>> w, mag, phase = sys.bode()
```

```
>>> plt.figure()
>>> plt.semilogx(w, mag)      # Bode magnitude plot
>>> plt.figure()
>>> plt.semilogx(w, phase)   # Bode phase plot
>>> plt.show()
```




scipy.signal.lti.freqresp

`lti.freqresp` (*self*, *w=None*, *n=10000*)

Calculate the frequency response of a continuous-time system.

Returns a 2-tuple containing arrays of frequencies [rad/s] and complex magnitude. See *freqresp* for details.



scipy.signal.lti.impulse

`lti.impulse` (*self*, *X0=None*, *T=None*, *N=None*)

Return the impulse response of a continuous-time system. See *impulse* for details.

scipy.signal.lti.output

`lti.output` (*self*, *U*, *T*, *X0=None*)

Return the response of a continuous-time system to input *U*. See *lsim* for details.

scipy.signal.lti.step

`lti.step` (*self*, *X0=None*, *T=None*, *N=None*)

Return the step response of a continuous-time system. See *step* for details.

scipy.signal.lti.to_discrete

`lti.to_discrete` (*self*, *dt*, *method='zoh'*, *alpha=None*)

Return a discretized version of the current system.

Parameters: See *cont2discrete* for details.

Returns

sys: instance of *dlti*

scipy.signal.StateSpace

class `scipy.signal.StateSpace` (**system*, ***kwargs*)

Linear Time Invariant system in state-space form.

Represents the system as the continuous-time, first order differential equation $\dot{x} = Ax + Bu$ or the discrete-time difference equation $x[k + 1] = Ax[k] + Bu[k]$. *StateSpace* systems inherit additional functionality from the *lti*, respectively the *dlti* classes, depending on which system representation is used.

Parameters

***system:** arguments

The `StateSpace` class can be instantiated with 1 or 4 arguments. The following gives the number of input arguments and their interpretation:

- 1: `lti` or `dlti` system: (`StateSpace`, `TransferFunction` or `ZerosPolesGain`)
- 4: `array_like`: (A, B, C, D)

dt: float, optional

Sampling time [s] of the discrete-time systems. Defaults to `None` (continuous-time). Must be specified as a keyword argument, for example, `dt=0.1`.

See also:

`TransferFunction`, `ZerosPolesGain`, `lti`, `dlti`

`ss2zpk`, `ss2tf`, `zpk2sos`

Notes

Changing the value of properties that are not part of the `StateSpace` system representation (such as zeros or poles) is very inefficient and may lead to numerical inaccuracies. It is better to convert to the specific system representation first. For example, call `sys = sys.to_zpk()` before accessing/changing the zeros, poles or gain.

Examples

```
>>> from scipy import signal
```

```
>>> a = np.array([[0, 1], [0, 0]])
>>> b = np.array([[0], [1]])
>>> c = np.array([[1, 0]])
>>> d = np.array([[0]])
```

```
>>> sys = signal.StateSpace(a, b, c, d)
>>> print(sys)
StateSpaceContinuous(
array([[0, 1],
       [0, 0]]),
array([[0],
       [1]]),
array([[1, 0]]),
array([[0]]),
dt: None
)
```

```
>>> sys.to_discrete(0.1)
StateSpaceDiscrete(
array([[1. , 0.1],
       [0. , 1. ]]),
array([[0.005],
       [0.1  ]]),
array([[1, 0]]),
array([[0]]),
```

(continues on next page)

(continued from previous page)

```
dt: 0.1
)
```

```
>>> a = np.array([[1, 0.1], [0, 1]])
>>> b = np.array([[0.005], [0.1]])
```

```
>>> signal.StateSpace(a, b, c, d, dt=0.1)
StateSpaceDiscrete(
array([[1. , 0.1],
       [0. , 1. ]]),
array([[0.005],
       [0.1  ]]),
array([[1, 0]]),
array([[0]]),
dt: 0.1
)
```

Attributes

- A** State matrix of the *StateSpace* system.
- B** Input matrix of the *StateSpace* system.
- C** Output matrix of the *StateSpace* system.
- D** Feedthrough matrix of the *StateSpace* system.
- dt** Return the sampling time of the system, *None* for *lti* systems.
- poles** Poles of the system.
- zeros** Zeros of the system.

Methods

<code>__mul__(self, other)</code>	Post-multiply another system or a scalar
<code>to_ss(self)</code>	Return a copy of the current <i>StateSpace</i> system.
<code>to_tf(self, **kwargs)</code>	Convert system representation to <i>TransferFunction</i> .
<code>to_zpk(self, **kwargs)</code>	Convert system representation to <i>ZerosPolesGain</i> .

scipy.signal.StateSpace.__mul__

`StateSpace.__mul__(self, other)`
 Post-multiply another system or a scalar

Handles multiplication of systems in the sense of a frequency domain multiplication. That means, given two systems $E1(s)$ and $E2(s)$, their multiplication, $H(s) = E1(s) * E2(s)$, means that applying $H(s)$ to $U(s)$ is equivalent to first applying $E2(s)$, and then $E1(s)$.

Notes

For SISO systems the order of system application does not matter. However, for MIMO systems, where the two systems are matrices, the order above ensures standard Matrix multiplication rules apply.

scipy.signal.StateSpace.to_ss

`StateSpace.to_ss` (*self*)

Return a copy of the current *StateSpace* system.

Returns

`sys` [instance of *StateSpace*] The current system (copy)

scipy.signal.StateSpace.to_tf

`StateSpace.to_tf` (*self*, ****kwargs**)

Convert system representation to *TransferFunction*.

Parameters

kwargs [dict, optional] Additional keywords passed to *ss2zpk*

Returns

`sys` [instance of *TransferFunction*] Transfer function of the current system

scipy.signal.StateSpace.to_zpk

`StateSpace.to_zpk` (*self*, ****kwargs**)

Convert system representation to *ZerosPolesGain*.

Parameters

kwargs [dict, optional] Additional keywords passed to *ss2zpk*

Returns

`sys` [instance of *ZerosPolesGain*] Zeros, poles, gain representation of the current system

scipy.signal.TransferFunction

class `scipy.signal.TransferFunction` (*system, ****kwargs**)

Linear Time Invariant system class in transfer function form.

Represents the system as the continuous-time transfer function $H(s) = \sum_{i=0}^N b[N-i]s^i / \sum_{j=0}^M a[M-j]s^j$ or the discrete-time transfer function $H(z) = \sum_{i=0}^N b[N-i]z^i / \sum_{j=0}^M a[M-j]z^j$, where *b* are elements of the numerator *num*, *a* are elements of the denominator *den*, and $N == \text{len}(b) - 1$, $M == \text{len}(a) - 1$. *TransferFunction* systems inherit additional functionality from the *lti*, respectively the *dlti* classes, depending on which system representation is used.

Parameters

*system: arguments

The *TransferFunction* class can be instantiated with 1 or 2 arguments. The following gives the number of input arguments and their interpretation:

- 1: *lti* or *dlti* system: (*StateSpace*, *TransferFunction* or *ZerosPolesGain*)
- 2: *array_like*: (numerator, denominator)

dt: float, optional

Sampling time [s] of the discrete-time systems. Defaults to *None* (continuous-time). Must be specified as a keyword argument, for example, `dt=0.1`.

See also:

ZerosPolesGain, *StateSpace*, *lti*, *dlti*

tf2ss, *tf2zpk*, *tf2sos*

Notes

Changing the value of properties that are not part of the *TransferFunction* system representation (such as the *A*, *B*, *C*, *D* state-space matrices) is very inefficient and may lead to numerical inaccuracies. It is better to convert to the specific system representation first. For example, call `sys = sys.to_ss()` before accessing/changing the *A*, *B*, *C*, *D* system matrices.

If (numerator, denominator) is passed in for **system*, coefficients for both the numerator and denominator should be specified in descending exponent order (e.g. $s^2 + 3s + 5$ or $z^2 + 3z + 5$ would be represented as `[1, 3, 5]`)

Examples

Construct the transfer function:

$$H(s) = \frac{s^2 + 3s + 3}{s^2 + 2s + 1}$$

```
>>> from scipy import signal
```

```
>>> num = [1, 3, 3]
>>> den = [1, 2, 1]
```

```
>>> signal.TransferFunction(num, den)
TransferFunctionContinuous(
array([1., 3., 3.]),
array([1., 2., 1.]),
dt: None
)
```

Construct the transfer function with a sampling time of 0.1 seconds:

$$H(z) = \frac{z^2 + 3z + 3}{z^2 + 2z + 1}$$

```
>>> signal.TransferFunction(num, den, dt=0.1)
TransferFunctionDiscrete(
array([1., 3., 3.]),
array([1., 2., 1.]),
dt: 0.1
)
```

Attributes

den	Denominator of the <i>TransferFunction</i> system.
dt	Return the sampling time of the system, <i>None</i> for <i>lti</i> systems.
num	Numerator of the <i>TransferFunction</i> system.
poles	Poles of the system.
zeros	Zeros of the system.

Methods

<code>to_ss(self)</code>	Convert system representation to <i>StateSpace</i> .
<code>to_tf(self)</code>	Return a copy of the current <i>TransferFunction</i> system.
<code>to_zpk(self)</code>	Convert system representation to <i>ZerosPolesGain</i> .

scipy.signal.TransferFunction.to_ss

`TransferFunction.to_ss(self)`
 Convert system representation to *StateSpace*.

Returns

`sys` [instance of *StateSpace*] State space model of the current system

scipy.signal.TransferFunction.to_tf

`TransferFunction.to_tf(self)`
 Return a copy of the current *TransferFunction* system.

Returns

`sys` [instance of *TransferFunction*] The current system (copy)

scipy.signal.TransferFunction.to_zpk

`TransferFunction.to_zpk(self)`
 Convert system representation to *ZerosPolesGain*.

Returns

`sys` [instance of *ZerosPolesGain*] Zeros, poles, gain representation of the current system

scipy.signal.ZerosPolesGain

class `scipy.signal.ZerosPolesGain(*system, **kwargs)`
 Linear Time Invariant system class in zeros, poles, gain form.

Represents the system as the continuous- or discrete-time transfer function $H(s) = k \prod_i (s - z[i]) / \prod_j (s - p[j])$, where k is the gain, z are the zeros and p are the poles. *ZerosPolesGain* systems inherit additional functionality from the *lti*, respectively the *dlti* classes, depending on which system representation is used.

Parameters

- *system** [arguments] The *ZerosPolesGain* class can be instantiated with 1 or 3 arguments. The following gives the number of input arguments and their interpretation:
- 1: *lti* or *dlti* system: (*StateSpace*, *TransferFunction* or *ZerosPolesGain*)

- 3: array_like: (zeros, poles, gain)

dt: float, optional

Sampling time [s] of the discrete-time systems. Defaults to *None* (continuous-time). Must be specified as a keyword argument, for example, `dt=0.1`.

See also:

TransferFunction, *StateSpace*, *lti*, *dlti*
zpk2ss, *zpk2tf*, *zpk2sos*

Notes

Changing the value of properties that are not part of the *ZerosPolesGain* system representation (such as the *A*, *B*, *C*, *D* state-space matrices) is very inefficient and may lead to numerical inaccuracies. It is better to convert to the specific system representation first. For example, call `sys = sys.to_ss()` before accessing/changing the *A*, *B*, *C*, *D* system matrices.

Examples

```
>>> from scipy import signal
```

Transfer function: $H(s) = 5(s - 1)(s - 2) / (s - 3)(s - 4)$

```
>>> signal.ZerosPolesGain([1, 2], [3, 4], 5)
ZerosPolesGainContinuous(
array([1, 2]),
array([3, 4]),
5,
dt: None
)
```

Transfer function: $H(z) = 5(z - 1)(z - 2) / (z - 3)(z - 4)$

```
>>> signal.ZerosPolesGain([1, 2], [3, 4], 5, dt=0.1)
ZerosPolesGainDiscrete(
array([1, 2]),
array([3, 4]),
5,
dt: 0.1
)
```

Attributes

dt	Return the sampling time of the system, <i>None</i> for <i>lti</i> systems.
gain	Gain of the <i>ZerosPolesGain</i> system.
poles	Poles of the <i>ZerosPolesGain</i> system.
zeros	Zeros of the <i>ZerosPolesGain</i> system.

Methods

<code>to_ss(self)</code>	Convert system representation to <i>StateSpace</i> .
<code>to_tf(self)</code>	Convert system representation to <i>TransferFunction</i> .
<code>to_zpk(self)</code>	Return a copy of the current 'ZerosPolesGain' system.

`scipy.signal.ZerosPolesGain.to_ss`

`ZerosPolesGain.to_ss(self)`
 Convert system representation to *StateSpace*.

Returns

`sys` [instance of *StateSpace*] State space model of the current system

`scipy.signal.ZerosPolesGain.to_tf`

`ZerosPolesGain.to_tf(self)`
 Convert system representation to *TransferFunction*.

Returns

`sys` [instance of *TransferFunction*] Transfer function of the current system

`scipy.signal.ZerosPolesGain.to_zpk`

`ZerosPolesGain.to_zpk(self)`
 Return a copy of the current 'ZerosPolesGain' system.

Returns

`sys` [instance of *ZerosPolesGain*] The current system (copy)

`scipy.signal.lsim`

`scipy.signal.lsim(system, U, T, X0=None, interp=True)`
 Simulate output of a continuous-time linear system.

Parameters

- system** [an instance of the LTI class or a tuple describing the system.] The following gives the number of elements in the tuple and the interpretation:
 - 1: (instance of *lti*)
 - 2: (num, den)
 - 3: (zeros, poles, gain)
 - 4: (A, B, C, D)
- U** [array_like] An input array describing the input at each time *T* (interpolation is assumed between given times). If there are multiple inputs, then each column of the rank-2 array represents an input. If *U* = 0 or *None*, a zero input is used.
- T** [array_like] The time steps at which the input is defined and at which the output is desired. Must be nonnegative, increasing, and equally spaced.
- X0** [array_like, optional] The initial conditions on the state vector (zero by default).
- interp** [bool, optional] Whether to use linear (True, the default) or zero-order-hold (False) interpolation for the input array.

Returns

T [1D ndarray] Time values for the output.

yout [1D ndarray] System response.
xout [ndarray] Time evolution of the state vector.

Notes

If (num, den) is passed in for `system`, coefficients for both the numerator and denominator should be specified in descending exponent order (e.g. $s^2 + 3s + 5$ would be represented as `[1, 3, 5]`).

Examples

We'll use `lsim` to simulate an analog Bessel filter applied to a signal.

```
>>> from scipy.signal import bessel, lsim
>>> import matplotlib.pyplot as plt
```

Create a low-pass Bessel filter with a cutoff of 12 Hz.

```
>>> b, a = bessel(N=5, Wn=2*np.pi*12, btype='lowpass', analog=True)
```

Generate data to which the filter is applied.

```
>>> t = np.linspace(0, 1.25, 500, endpoint=False)
```

The input signal is the sum of three sinusoidal curves, with frequencies 4 Hz, 40 Hz, and 80 Hz. The filter should mostly eliminate the 40 Hz and 80 Hz components, leaving just the 4 Hz signal.

```
>>> u = (np.cos(2*np.pi*4*t) + 0.6*np.sin(2*np.pi*40*t) +
...      0.5*np.cos(2*np.pi*80*t))
```

Simulate the filter with `lsim`.

```
>>> tout, yout, xout = lsim((b, a), U=u, T=t)
```


Plot the result.

```
>>> plt.plot(t, u, 'r', alpha=0.5, linewidth=1, label='input')
>>> plt.plot(tout, yout, 'k', linewidth=1.5, label='output')
>>> plt.legend(loc='best', shadow=True, framealpha=1)
>>> plt.grid(alpha=0.3)
>>> plt.xlabel('t')
>>> plt.show()
```

In a second example, we simulate a double integrator $y'' = u$, with a constant input $u = 1$. We'll use the state space representation of the integrator.

```
>>> from scipy.signal import lti
>>> A = np.array([[0.0, 1.0], [0.0, 0.0]])
>>> B = np.array([[0.0], [1.0]])
>>> C = np.array([[1.0, 0.0]])
>>> D = 0.0
>>> system = lti(A, B, C, D)
```


`t` and `u` define the time and input signal for the system to be simulated.



```
>>> t = np.linspace(0, 5, num=50)
>>> u = np.ones_like(t)
```

Compute the simulation, and then plot y . As expected, the plot shows the curve $y = 0.5*t**2$.

```
>>> tout, y, x = lsim(system, u, t)
>>> plt.plot(t, y)
>>> plt.grid(alpha=0.3)
>>> plt.xlabel('t')
>>> plt.show()
```



scipy.signal.lsim2

`scipy.signal.lsim2` (*system*, *U=None*, *T=None*, *X0=None*, ***kwargs*)

Simulate output of a continuous-time linear system, by using the ODE solver `scipy.integrate.odeint`.

Parameters

system	[an instance of the <code>lti</code> class or a tuple describing the system.] The following gives the number of elements in the tuple and the interpretation: <ul style="list-style-type: none"> • 1: (instance of <code>lti</code>) • 2: (num, den) • 3: (zeros, poles, gain) • 4: (A, B, C, D)
U	[array_like (1D or 2D), optional] An input array describing the input at each time T. Linear interpolation is used between given times. If there are multiple inputs, then each column of the rank-2 array represents an input. If U is not given, the input is assumed to be zero.
T	[array_like (1D or 2D), optional] The time steps at which the input is defined and at which the output is desired. The default is 101 evenly spaced points on the interval [0,10.0].
X0	[array_like (1D), optional] The initial condition of the state vector. If X0 is not given, the initial conditions are assumed to be 0.
kwargs	[dict] Additional keyword arguments are passed on to the function <code>odeint</code> . See the notes below for more details.

Returns

T	[1D ndarray] The time values for the output.
yout	[ndarray] The response of the system.
xout	[ndarray] The time-evolution of the state-vector.

See also:

`lsim`

Notes

This function uses `scipy.integrate.odeint` to solve the system's differential equations. Additional keyword arguments given to `lsim2` are passed on to `odeint`. See the documentation for `scipy.integrate.odeint` for the full list of arguments.

If (num, den) is passed in for `system`, coefficients for both the numerator and denominator should be specified in descending exponent order (e.g. $s^2 + 3s + 5$ would be represented as [1, 3, 5]).

Examples

We'll use `lsim2` to simulate an analog Bessel filter applied to a signal.

```
>>> from scipy.signal import bessel, lsim2
>>> import matplotlib.pyplot as plt
```

Create a low-pass Bessel filter with a cutoff of 12 Hz.

```
>>> b, a = bessel(N=5, Wn=2*np.pi*12, btype='lowpass', analog=True)
```

Generate data to which the filter is applied.

```
>>> t = np.linspace(0, 1.25, 500, endpoint=False)
```

The input signal is the sum of three sinusoidal curves, with frequencies 4 Hz, 40 Hz, and 80 Hz. The filter should mostly eliminate the 40 Hz and 80 Hz components, leaving just the 4 Hz signal.


```
>>> u = (np.cos(2*np.pi*4*t) + 0.6*np.sin(2*np.pi*40*t) +
...      0.5*np.cos(2*np.pi*80*t))
```

Simulate the filter with `lsim2`.

```
>>> tout, yout, xout = lsim2((b, a), U=u, T=t)
```

Plot the result.

```
>>> plt.plot(t, u, 'r', alpha=0.5, linewidth=1, label='input')
>>> plt.plot(tout, yout, 'k', linewidth=1.5, label='output')
>>> plt.legend(loc='best', shadow=True, framealpha=1)
>>> plt.grid(alpha=0.3)
>>> plt.xlabel('t')
>>> plt.show()
```



In a second example, we simulate a double integrator $y'' = u$, with a constant input $u = 1$. We'll use the state space representation of the integrator.


```
>>> from scipy.signal import lti
>>> A = np.array([[0, 1], [0, 0]])
>>> B = np.array([[0], [1]])
>>> C = np.array([[1, 0]])
>>> D = 0
>>> system = lti(A, B, C, D)
```

t and u define the time and input signal for the system to be simulated.

```
>>> t = np.linspace(0, 5, num=50)
>>> u = np.ones_like(t)
```

Compute the simulation, and then plot y . As expected, the plot shows the curve $y = 0.5*t**2$.

```
>>> tout, y, x = lsim2(system, u, t)
>>> plt.plot(t, y)
>>> plt.grid(alpha=0.3)
>>> plt.xlabel('t')
>>> plt.show()
```



scipy.signal.impulse

`scipy.signal.impulse` (*system*, *X0=None*, *T=None*, *N=None*)

Impulse response of continuous-time system.

Parameters

- system** [an instance of the LTI class or a tuple of array_like] describing the system. The following gives the number of elements in the tuple and the interpretation:
- 1 (instance of `lti`)
 - 2 (num, den)
 - 3 (zeros, poles, gain)
 - 4 (A, B, C, D)
- X0** [array_like, optional] Initial state-vector. Defaults to zero.
- T** [array_like, optional] Time points. Computed if not given.
- N** [int, optional] The number of time points to compute (if *T* is not given).

Returns

- T** [ndarray] A 1-D array of time points.
- yout** [ndarray] A 1-D array containing the impulse response of the system (except for singularities at zero).


Notes

If (num, den) is passed in for `system`, coefficients for both the numerator and denominator should be specified in descending exponent order (e.g. $s^2 + 3s + 5$ would be represented as `[1, 3, 5]`).

Examples

Compute the impulse response of a second order system with a repeated root: $x''(t) + 2x'(t) + x(t) = u(t)$

```
>>> from scipy import signal
>>> system = ([1.0], [1.0, 2.0, 1.0])
>>> t, y = signal.impulse(system)
>>> import matplotlib.pyplot as plt
>>> plt.plot(t, y)
```



scipy.signal.impulse2

`scipy.signal.impulse2(system, X0=None, T=None, N=None, **kwargs)`

Impulse response of a single-input, continuous-time linear system.

Parameters

- | | |
|---------------|---|
| system | [an instance of the LTI class or a tuple of array_like] describing the system. The following gives the number of elements in the tuple and the interpretation: <ul style="list-style-type: none"> • 1 (instance of <code>lti</code>) • 2 (num, den) • 3 (zeros, poles, gain) • 4 (A, B, C, D) |
| X0 | [1-D array_like, optional] The initial condition of the state vector. Default: 0 (the zero vector). |
| T | [1-D array_like, optional] The time steps at which the input is defined and at which the output is desired. If <code>T</code> is not given, the function will generate a set of time samples automatically. |
| N | [int, optional] Number of time points to compute. Default: 100. |

kwargs [various types] Additional keyword arguments are passed on to the function `scipy.signal.lsim2`, which in turn passes them on to `scipy.integrate.odeint`; see the latter's documentation for information about these arguments.

Returns

T [ndarray] The time values for the output.
yout [ndarray] The output response of the system.

See also:

`impulse`, `lsim2`, `scipy.integrate.odeint`

Notes

The solution is generated by calling `scipy.signal.lsim2`, which uses the differential equation solver `scipy.integrate.odeint`.


If (num, den) is passed in for `system`, coefficients for both the numerator and denominator should be specified in descending exponent order (e.g. $s^2 + 3s + 5$ would be represented as [1, 3, 5]).

New in version 0.8.0.

Examples

Compute the impulse response of a second order system with a repeated root: $x''(t) + 2x'(t) + x(t) = u(t)$

```
>>> from scipy import signal
>>> system = ([1.0], [1.0, 2.0, 1.0])
>>> t, y = signal.impulse2(system)
>>> import matplotlib.pyplot as plt
>>> plt.plot(t, y)
```



scipy.signal.step

`scipy.signal.step` (*system*, *X0=None*, *T=None*, *N=None*)

Step response of continuous-time system.

Parameters

system	[an instance of the LTI class or a tuple of array_like] describing the system. The following gives the number of elements in the tuple and the interpretation: <ul style="list-style-type: none">• 1 (instance of <i>lti</i>)• 2 (num, den)• 3 (zeros, poles, gain)• 4 (A, B, C, D)
X0	[array_like, optional] Initial state-vector (default is zero).
T	[array_like, optional] Time points (computed if not given).
N	[int, optional] Number of time points to compute if <i>T</i> is not given.

Returns

T	[1D ndarray] Output time points.
yout	[1D ndarray] Step response of system.

See also:

[*scipy.signal.step2*](#)

Notes

If (num, den) is passed in for *system*, coefficients for both the numerator and denominator should be specified in descending exponent order (e.g. $s^2 + 3s + 5$ would be represented as [1, 3, 5]).

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
>>> lti = signal.lti([1.0], [1.0, 1.0])
>>> t, y = signal.step(lti)
>>> plt.plot(t, y)
>>> plt.xlabel('Time [s]')
>>> plt.ylabel('Amplitude')
>>> plt.title('Step response for 1. Order Lowpass')
>>> plt.grid()
```

scipy.signal.step2


`scipy.signal.step2` (*system*, *X0=None*, *T=None*, *N=None*, ***kwargs*)

Step response of continuous-time system.

This function is functionally the same as `scipy.signal.step`, but it uses the function `scipy.signal.lsim2` to compute the step response.

Parameters

system	[an instance of the LTI class or a tuple of array_like] describing the system. The following gives the number of elements in the tuple and the interpretation:
---------------	--



- 1 (instance of `lti`)
- 2 (num, den)
- 3 (zeros, poles, gain)
- 4 (A, B, C, D)

X0 [array_like, optional] Initial state-vector (default is zero).
T [array_like, optional] Time points (computed if not given).
N [int, optional] Number of time points to compute if *T* is not given.
kwargs [various types] Additional keyword arguments are passed on the function `scipy.signal.lsim2`, which in turn passes them on to `scipy.integrate.odeint`. See the documentation for `scipy.integrate.odeint` for information about these arguments.

Returns

T [1D ndarray] Output time points.
yout [1D ndarray] Step response of system.

See also:

`scipy.signal.step`

Notes

If (num, den) is passed in for `system`, coefficients for both the numerator and denominator should be specified in descending exponent order (e.g. $s^2 + 3s + 5$ would be represented as `[1, 3, 5]`).


New in version 0.8.0.

Examples

```

>>> from scipy import signal
>>> import matplotlib.pyplot as plt
>>> lti = signal.lti([1.0], [1.0, 1.0])
>>> t, y = signal.step2(lti)
>>> plt.plot(t, y)
>>> plt.xlabel('Time [s]')
>>> plt.ylabel('Amplitude')
>>> plt.title('Step response for 1. Order Lowpass')
>>> plt.grid()

```

**scipy.signal.freqresp**

`scipy.signal.freqresp` (*system*, *w=None*, *n=10000*)

Calculate the frequency response of a continuous-time system.

Parameters

- system** [an instance of the `lti` class or a tuple describing the system.] The following gives the number of elements in the tuple and the interpretation:
- 1 (instance of `lti`)
 - 2 (num, den)
 - 3 (zeros, poles, gain)
 - 4 (A, B, C, D)
- w** [array_like, optional] Array of frequencies (in rad/s). Magnitude and phase data is calculated for every value in this array. If not given, a reasonable set will be calculated.
- n** [int, optional] Number of frequency points to compute if *w* is not given. The *n* frequencies are logarithmically spaced in an interval chosen to include the influence of the poles and zeros of the system.

Returns

- w** [1D ndarray] Frequency array [rad/s]
- H** [1D ndarray] Array of complex magnitude values

Notes

If (num, den) is passed in for `system`, coefficients for both the numerator and denominator should be specified in descending exponent order (e.g. $s^2 + 3s + 5$ would be represented as `[1, 3, 5]`).

Examples

Generating the Nyquist plot of a transfer function


```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

Transfer function: $H(s) = 5 / (s-1)^3$

```
>>> s1 = signal.ZerosPolesGain([], [1, 1, 1], [5])
```

```
>>> w, H = signal.freqresp(s1)
```

```
>>> plt.figure()
>>> plt.plot(H.real, H.imag, "b")
>>> plt.plot(H.real, -H.imag, "r")
>>> plt.show()
```



scipy.signal.bode

`scipy.signal.bode` (*system*, *w=None*, *n=100*)

Calculate Bode magnitude and phase data of a continuous-time system.

Parameters

- system** [an instance of the LTI class or a tuple describing the system.] The following gives the number of elements in the tuple and the interpretation:
- 1 (instance of *lti*)
 - 2 (num, den)
 - 3 (zeros, poles, gain)
 - 4 (A, B, C, D)
- w** [array_like, optional] Array of frequencies (in rad/s). Magnitude and phase data is calculated for every value in this array. If not given a reasonable set will be calculated.
- n** [int, optional] Number of frequency points to compute if *w* is not given. The *n* frequencies are logarithmically spaced in an interval chosen to include the influence of the poles and zeros of the system.

Returns

- w** [1D ndarray] Frequency array [rad/s]
mag [1D ndarray] Magnitude array [dB]
phase [1D ndarray] Phase array [deg]

Notes

If (num, den) is passed in for *system*, coefficients for both the numerator and denominator should be specified in descending exponent order (e.g. $s^2 + 3s + 5$ would be represented as [1, 3, 5]).



New in version 0.11.0.

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> sys = signal.TransferFunction([1], [1, 1])
>>> w, mag, phase = signal.bode(sys)
```

```
>>> plt.figure()
>>> plt.semilogx(w, mag)      # Bode magnitude plot
>>> plt.figure()
>>> plt.semilogx(w, phase)   # Bode phase plot
>>> plt.show()
```



6.22.7 Discrete-time linear systems

<code>dlti(*system, **kwargs)</code>	Discrete-time linear time invariant system base class.
<code>StateSpace(*system, **kwargs)</code>	Linear Time Invariant system in state-space form.
<code>TransferFunction(*system, **kwargs)</code>	Linear Time Invariant system class in transfer function form.
<code>ZerosPolesGain(*system, **kwargs)</code>	Linear Time Invariant system class in zeros, poles, gain form.
<code>dlsim(system, u[, t, x0])</code>	Simulate output of a discrete-time linear system.
<code>dimpulse(system[, x0, t, n])</code>	Impulse response of discrete-time system.
<code>dstep(system[, x0, t, n])</code>	Step response of discrete-time system.
<code>dfreqresp(system[, w, n, whole])</code>	Calculate the frequency response of a discrete-time system.
<code>dbode(system[, w, n])</code>	Calculate Bode magnitude and phase data of a discrete-time system.

scipy.signal.dlti

class `scipy.signal.dlti` (**system, **kwargs*)
 Discrete-time linear time invariant system base class.

Parameters

***system: arguments**

The `dlti` class can be instantiated with either 2, 3 or 4 arguments. The following gives the number of arguments and the corresponding discrete-time subclass that is created:

- 2: `TransferFunction`: (numerator, denominator)
- 3: `ZerosPolesGain`: (zeros, poles, gain)
- 4: `StateSpace`: (A, B, C, D)

Each argument can be an array or a sequence.

dt: float, optional

Sampling time [s] of the discrete-time systems. Defaults to `True` (unspecified sampling time). Must be specified as a keyword argument, for example, `dt=0.1`.

See also:

`ZerosPolesGain`, `StateSpace`, `TransferFunction`, `lti`

Notes

`dlti` instances do not exist directly. Instead, `dlti` creates an instance of one of its subclasses: `StateSpace`, `TransferFunction` or `ZerosPolesGain`.

Changing the value of properties that are not directly part of the current system representation (such as the zeros of a `StateSpace` system) is very inefficient and may lead to numerical inaccuracies. It is better to convert to the specific system representation first. For example, call `sys = sys.to_zpk()` before accessing/changing the zeros, poles or gain.

If (numerator, denominator) is passed in for **system*, coefficients for both the numerator and denominator should be specified in descending exponent order (e.g., $z^2 + 3z + 5$ would be represented as `[1, 3, 5]`).

New in version 0.18.0.

Examples

```
>>> from scipy import signal
```

```
>>> signal.dlti(1, 2, 3, 4)
StateSpaceDiscrete(
array([[1]]),
array([[2]]),
array([[3]]),
array([[4]]),
dt: True
)
```

```
>>> signal.dlti(1, 2, 3, 4, dt=0.1)
StateSpaceDiscrete(
array([[1]]),
array([[2]]),
array([[3]]),
array([[4]]),
dt: 0.1
)
```

```
>>> signal.dlti([1, 2], [3, 4], 5, dt=0.1)
ZerosPolesGainDiscrete(
array([1, 2]),
array([3, 4]),
5,
dt: 0.1
)
```

```
>>> signal.dlti([3, 4], [1, 2], dt=0.1)
TransferFunctionDiscrete(
array([3., 4.]),
array([1., 2.]),
dt: 0.1
)
```

Attributes

dt	Return the sampling time of the system.
poles	Poles of the system.
zeros	Zeros of the system.

Methods

<code>bode(self[, w, n])</code>	Calculate Bode magnitude and phase data of a discrete-time system.
<code>freqresp(self[, w, n, whole])</code>	Calculate the frequency response of a discrete-time system.
<code>impulse(self[, x0, t, n])</code>	Return the impulse response of the discrete-time <i>dlti</i> system.
<code>output(self, u, t[, x0])</code>	Return the response of the discrete-time system to input <i>u</i> .
<code>step(self[, x0, t, n])</code>	Return the step response of the discrete-time <i>dlti</i> system.

scipy.signal.dlti.bode

`dlti.bode` (*self*, *w=None*, *n=100*)

Calculate Bode magnitude and phase data of a discrete-time system.

Returns a 3-tuple containing arrays of frequencies [rad/s], magnitude [dB] and phase [deg]. See *dbode* for details.

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

Transfer function: $H(z) = 1 / (z^2 + 2z + 3)$ with sampling time 0.5s

```
>>> sys = signal.TransferFunction([1], [1, 2, 3], dt=0.5)
```

Equivalent: `signal.dbode(sys)`

```
>>> w, mag, phase = sys.bode()
```



```
>>> plt.figure()
>>> plt.semilogx(w, mag)      # Bode magnitude plot
>>> plt.figure()
>>> plt.semilogx(w, phase)   # Bode phase plot
>>> plt.show()
```

scipy.signal.dlti.freqresp

`dlti.freqresp` (*self*, *w=None*, *n=10000*, *whole=False*)

Calculate the frequency response of a discrete-time system.

Returns a 2-tuple containing arrays of frequencies [rad/s] and complex magnitude. See *dfreqresp* for details.



scipy.signal.dlti.impulse`dlti.impulse` (*self*, *x0=None*, *t=None*, *n=None*)Return the impulse response of the discrete-time *dlti* system. See *dimpulse* for details.**scipy.signal.dlti.output**`dlti.output` (*self*, *u*, *t*, *x0=None*)Return the response of the discrete-time system to input *u*. See *dlsim* for details.**scipy.signal.dlti.step**`dlti.step` (*self*, *x0=None*, *t=None*, *n=None*)Return the step response of the discrete-time *dlti* system. See *dstep* for details.**scipy.signal.dlsim**`scipy.signal.dlsim` (*system*, *u*, *t=None*, *x0=None*)

Simulate output of a discrete-time linear system.

Parameters

- | | |
|---------------|---|
| system | [tuple of array_like or instance of <i>dlti</i>] A tuple describing the system. The following gives the number of elements in the tuple and the interpretation: <ul style="list-style-type: none">• 1: (instance of <i>dlti</i>)• 3: (num, den, dt)• 4: (zeros, poles, gain, dt)• 5: (A, B, C, D, dt) |
| u | [array_like] An input array describing the input at each time <i>t</i> (interpolation is assumed between given times). If there are multiple inputs, then each column of the rank-2 array represents an input. |
| t | [array_like, optional] The time steps at which the input is defined. If <i>t</i> is given, it must be the same length as <i>u</i> , and the final value in <i>t</i> determines the number of steps returned in the output. |
| x0 | [array_like, optional] The initial conditions on the state vector (zero by default). |

Returns

- | | |
|-------------|--|
| tout | [ndarray] Time values for the output, as a 1-D array. |
| yout | [ndarray] System response, as a 1-D array. |
| xout | [ndarray, optional] Time-evolution of the state-vector. Only generated if the input is a <i>StateSpace</i> system. |

See also:

lsim, *dstep*, *dimpulse*, *cont2discrete*

Examples

A simple integrator transfer function with a discrete time step of 1.0 could be implemented as:

```
>>> from scipy import signal
>>> tf = ([1.0,], [1.0, -1.0], 1.0)
>>> t_in = [0.0, 1.0, 2.0, 3.0]
>>> u = np.asarray([0.0, 0.0, 1.0, 1.0])
>>> t_out, y = signal.dlsim(tf, u, t=t_in)
>>> y.T
array([[ 0.,  0.,  0.,  1.]])
```

scipy.signal.dimpulse

`scipy.signal.dimpulse` (*system, x0=None, t=None, n=None*)

Impulse response of discrete-time system.

Parameters

system	[tuple of array_like or instance of <i>dlti</i>] A tuple describing the system. The following gives the number of elements in the tuple and the interpretation: <ul style="list-style-type: none"> • 1: (instance of <i>dlti</i>) • 3: (num, den, dt) • 4: (zeros, poles, gain, dt) • 5: (A, B, C, D, dt)
x0	[array_like, optional] Initial state-vector. Defaults to zero.
t	[array_like, optional] Time points. Computed if not given.
n	[int, optional] The number of time points to compute (if <i>t</i> is not given).

Returns

tout	[ndarray] Time values for the output, as a 1-D array.
yout	[tuple of ndarray] Impulse response of system. Each element of the tuple represents the output of the system based on an impulse in each input.


See also:

[*impulse*](#), [*dstep*](#), [*dlsim*](#), [*cont2discrete*](#)

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> butter = signal.dlti(*signal.butter(3, 0.5))
>>> t, y = signal.dimpulse(butter, n=25)
>>> plt.step(t, np.squeeze(y))
>>> plt.grid()
>>> plt.xlabel('n [samples]')
>>> plt.ylabel('Amplitude')
```



scipy.signal.dstep

`scipy.signal.dstep` (*system, x0=None, t=None, n=None*)

Step response of discrete-time system.

Parameters

- system** [tuple of array_like] A tuple describing the system. The following gives the number of elements in the tuple and the interpretation:
- 1: (instance of *dlti*)
 - 3: (num, den, dt)
 - 4: (zeros, poles, gain, dt)
 - 5: (A, B, C, D, dt)
- x0** [array_like, optional] Initial state-vector. Defaults to zero.
- t** [array_like, optional] Time points. Computed if not given.
- n** [int, optional] The number of time points to compute (if *t* is not given).

Returns

- tout** [ndarray] Output time points, as a 1-D array.
- yout** [tuple of ndarray] Step response of system. Each element of the tuple represents the output of the system based on a step response to each input.


See also:

step, dimpulse, dlsim, cont2discrete

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> butter = signal.dlti(*signal.butter(3, 0.5))
>>> t, y = signal.dstep(butter, n=25)
>>> plt.step(t, np.squeeze(y))
>>> plt.grid()
>>> plt.xlabel('n [samples]')
>>> plt.ylabel('Amplitude')
```

**scipy.signal.dfreqresp**

`scipy.signal.dfreqresp` (*system*, *w=None*, *n=10000*, *whole=False*)

Calculate the frequency response of a discrete-time system.

Parameters

- | | |
|---------------|--|
| system | [an instance of the <code>dlti</code> class or a tuple describing the system.] The following gives the number of elements in the tuple and the interpretation: <ul style="list-style-type: none"> • 1 (instance of <code>dlti</code>) • 2 (numerator, denominator, dt) • 3 (zeros, poles, gain, dt) • 4 (A, B, C, D, dt) |
| w | [array_like, optional] Array of frequencies (in radians/sample). Magnitude and phase data is calculated for every value in this array. If not given a reasonable set will be calculated. |
| n | [int, optional] Number of frequency points to compute if <i>w</i> is not given. The <i>n</i> frequencies are logarithmically spaced in an interval chosen to include the influence of the poles and zeros of the system. |
| whole | [bool, optional] Normally, if 'w' is not given, frequencies are computed from 0 to the Nyquist frequency, pi radians/sample (upper-half of unit-circle). If <i>whole</i> is True, compute frequencies from 0 to 2*pi radians/sample. |

Returns

w [1D ndarray] Frequency array [radians/sample]
H [1D ndarray] Array of complex magnitude values

Notes

If (num, den) is passed in for `system`, coefficients for both the numerator and denominator should be specified in descending exponent order (e.g. $z^2 + 3z + 5$ would be represented as `[1, 3, 5]`).

New in version 0.18.0.

Examples

Generating the Nyquist plot of a transfer function


```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

Transfer function: $H(z) = 1 / (z^2 + 2z + 3)$

```
>>> sys = signal.TransferFunction([1], [1, 2, 3], dt=0.05)
```

```
>>> w, H = signal.dfreqresp(sys)
```

```
>>> plt.figure()
>>> plt.plot(H.real, H.imag, "b")
>>> plt.plot(H.real, -H.imag, "r")
>>> plt.show()
```



scipy.signal.dbode

`scipy.signal.dbode` (*system*, *w=None*, *n=100*)

Calculate Bode magnitude and phase data of a discrete-time system.

Parameters

system	[an instance of the LTI class or a tuple describing the system.] The following gives the number of elements in the tuple and the interpretation: <ul style="list-style-type: none"> • 1 (instance of <i>dlti</i>) • 2 (num, den, dt) • 3 (zeros, poles, gain, dt) • 4 (A, B, C, D, dt)
w	[array_like, optional] Array of frequencies (in radians/sample). Magnitude and phase data is calculated for every value in this array. If not given a reasonable set will be calculated.
n	[int, optional] Number of frequency points to compute if <i>w</i> is not given. The <i>n</i> frequencies are logarithmically spaced in an interval chosen to include the influence of the poles and zeros of the system.

Returns

w	[1D ndarray] Frequency array [rad/time_unit]
mag	[1D ndarray] Magnitude array [dB]
phase	[1D ndarray] Phase array [deg]

Notes

If (num, den) is passed in for *system*, coefficients for both the numerator and denominator should be specified in descending exponent order (e.g. $z^2 + 3z + 5$ would be represented as [1, 3, 5]).

New in version 0.18.0.

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```



Transfer function: $H(z) = 1 / (z^2 + 2z + 3)$

```
>>> sys = signal.TransferFunction([1], [1, 2, 3], dt=0.05)
```

Equivalent: `sys.bode()`

```
>>> w, mag, phase = signal.dbode(sys)
```

```
>>> plt.figure()
>>> plt.semilogx(w, mag)      # Bode magnitude plot
>>> plt.figure()
>>> plt.semilogx(w, phase)   # Bode phase plot
>>> plt.show()
```



6.22.8 LTI representations

<code>tf2zpk(b, a)</code>	Return zero, pole, gain (z, p, k) representation from a numerator, denominator representation of a linear filter.
<code>tf2sos(b, a[, pairing])</code>	Return second-order sections from transfer function representation
<code>tf2ss(num, den)</code>	Transfer function to state-space representation.
<code>zpk2tf(z, p, k)</code>	Return polynomial transfer function representation from zeros and poles
<code>zpk2sos(z, p, k[, pairing])</code>	Return second-order sections from zeros, poles, and gain of a system
<code>zpk2ss(z, p, k)</code>	Zero-pole-gain representation to state-space representation
<code>ss2tf(A, B, C, D[, input])</code>	State-space to transfer function.
<code>ss2zpk(A, B, C, D[, input])</code>	State-space representation to zero-pole-gain representation.
<code>sos2zpk(sos)</code>	Return zeros, poles, and gain of a series of second-order sections
<code>sos2tf(sos)</code>	Return a single transfer function from a series of second-order sections
<code>cont2discrete(system, dt[, method, alpha])</code>	Transform a continuous to a discrete state-space system.
<code>place_poles(A, B, poles[, method, rtol, maxiter])</code>	Compute K such that eigenvalues (A - dot(B, K))=poles.

scipy.signal.tf2zpk

`scipy.signal.tf2zpk(b, a)`

Return zero, pole, gain (z, p, k) representation from a numerator, denominator representation of a linear filter.

Parameters

- b** [array_like] Numerator polynomial coefficients.
- a** [array_like] Denominator polynomial coefficients.

Returns

- z** [ndarray] Zeros of the transfer function.
- p** [ndarray] Poles of the transfer function.
- k** [float] System gain.

Notes

If some values of b are too close to 0, they are removed. In that case, a `BadCoefficients` warning is emitted.

The b and a arrays are interpreted as coefficients for positive, descending powers of the transfer function variable. So the inputs $b = [b_0, b_1, \dots, b_M]$ and $a = [a_0, a_1, \dots, a_N]$ can represent an analog filter of the form:

$$H(s) = \frac{b_0 s^M + b_1 s^{(M-1)} + \dots + b_M}{a_0 s^N + a_1 s^{(N-1)} + \dots + a_N}$$

or a discrete-time filter of the form:

$$H(z) = \frac{b_0 z^M + b_1 z^{(M-1)} + \dots + b_M}{a_0 z^N + a_1 z^{(N-1)} + \dots + a_N}$$

This “positive powers” form is found more commonly in controls engineering. If M and N are equal (which is true for all filters generated by the bilinear transform), then this happens to be equivalent to the “negative powers” discrete-time form preferred in DSP:

$$H(z) = \frac{b_0 + b_1 z^{-1} + \dots + b_M z^{-M}}{a_0 + a_1 z^{-1} + \dots + a_N z^{-N}}$$

Although this is true for common filters, remember that this is not true in the general case. If M and N are not equal, the discrete-time transfer function coefficients must first be converted to the “positive powers” form before finding the poles and zeros.

scipy.signal.tf2sos

`scipy.signal.tf2sos` (*b*, *a*, *pairing*='nearest')

Return second-order sections from transfer function representation

Parameters

- b** [array_like] Numerator polynomial coefficients.
- a** [array_like] Denominator polynomial coefficients.
- pairing** [{'nearest', 'keep_odd'}, optional] The method to use to combine pairs of poles and zeros into sections. See *zpk2sos*.

Returns

- sos** [ndarray] Array of second-order filter coefficients, with shape (n_sections, 6). See *sosfilt* for the SOS filter format specification.

See also:

zpk2sos, *sosfilt*

Notes

It is generally discouraged to convert from TF to SOS format, since doing so usually will not improve numerical precision errors. Instead, consider designing filters in ZPK format and converting directly to SOS. TF is converted to SOS by first converting to ZPK format, then converting ZPK to SOS.

New in version 0.16.0.

scipy.signal.tf2ss

`scipy.signal.tf2ss` (*num*, *den*)

Transfer function to state-space representation.

Parameters

- num, den** [array_like] Sequences representing the coefficients of the numerator and denominator polynomials, in order of descending degree. The denominator needs to be at least as long as the numerator.

Returns

- A, B, C, D** [ndarray] State space representation of the system, in controller canonical form.

Examples

Convert the transfer function:

$$H(s) = \frac{s^2 + 3s + 3}{s^2 + 2s + 1}$$

```
>>> num = [1, 3, 3]
>>> den = [1, 2, 1]
```

to the state-space representation:

$$\dot{\mathbf{x}}(t) = \begin{bmatrix} -2 & -1 \\ 1 & 0 \end{bmatrix} \mathbf{x}(t) + \begin{bmatrix} 1 \\ 0 \end{bmatrix} \mathbf{u}(t)$$

$$\mathbf{y}(t) = [1 \quad 2] \mathbf{x}(t) + [1] \mathbf{u}(t)$$

```
>>> from scipy.signal import tf2ss
>>> A, B, C, D = tf2ss(num, den)
>>> A
array([[ -2.,  -1.],
       [  1.,   0.]])
>>> B
array([[ 1.],
       [ 0.]])
>>> C
array([[ 1.,  2.]])
>>> D
array([[ 1.]])
```

scipy.signal.zpk2tf

`scipy.signal.zpk2tf` (*z*, *p*, *k*)

Return polynomial transfer function representation from zeros and poles

Parameters

- z** [array_like] Zeros of the transfer function.
- p** [array_like] Poles of the transfer function.
- k** [float] System gain.

Returns

- b** [ndarray] Numerator polynomial coefficients.
- a** [ndarray] Denominator polynomial coefficients.

scipy.signal.zpk2sos

`scipy.signal.zpk2sos` (*z, p, k, pairing='nearest'*)

Return second-order sections from zeros, poles, and gain of a system

Parameters

z	[array_like] Zeros of the transfer function.
p	[array_like] Poles of the transfer function.
k	[float] System gain.
pairing	[{'nearest', 'keep_odd'}, optional] The method to use to combine pairs of poles and zeros into sections. See Notes below.

Returns

sos	[ndarray] Array of second-order filter coefficients, with shape <code>(n_sections, 6)</code> . See <code>sosfilt</code> for the SOS filter format specification.
------------	--

See also:

[`sosfilt`](#)

Notes

The algorithm used to convert ZPK to SOS format is designed to minimize errors due to numerical precision issues. The pairing algorithm attempts to minimize the peak gain of each biquadratic section. This is done by pairing poles with the nearest zeros, starting with the poles closest to the unit circle.

Algorithms

The current algorithms are designed specifically for use with digital filters. (The output coefficients are not correct for analog filters.)

The steps in the `pairing='nearest'` and `pairing='keep_odd'` algorithms are mostly shared. The `nearest` algorithm attempts to minimize the peak gain, while `'keep_odd'` minimizes peak gain under the constraint that odd-order systems should retain one section as first order. The algorithm steps and are as follows:

As a pre-processing step, add poles or zeros to the origin as necessary to obtain the same number of poles and zeros for pairing. If `pairing == 'nearest'` and there are an odd number of poles, add an additional pole and a zero at the origin.

The following steps are then iterated over until no more poles or zeros remain:

1. Take the (next remaining) pole (complex or real) closest to the unit circle to begin a new filter section.
2. If the pole is real and there are no other remaining real poles¹, add the closest real zero to the section and leave it as a first order section. Note that after this step we are guaranteed to be left with an even number of real poles, complex poles, real zeros, and complex zeros for subsequent pairing iterations.
3. Else:
 1. If the pole is complex and the zero is the only remaining real zero*, then pair the pole with the *next* closest zero (guaranteed to be complex). This is necessary to ensure that there will be a real zero remaining to eventually create a first-order section (thus keeping the odd order).
 2. Else pair the pole with the closest remaining zero (complex or real).
 3. Proceed to complete the second-order section by adding another pole and zero to the current pole and zero in the section:

¹ This conditional can only be met for specific odd-order inputs with the `pairing == 'keep_odd'` method.

1. If the current pole and zero are both complex, add their conjugates.
2. Else if the pole is complex and the zero is real, add the conjugate pole and the next closest real zero.
3. Else if the pole is real and the zero is complex, add the conjugate zero and the real pole closest to those zeros.
4. Else (we must have a real pole and real zero) add the next real pole closest to the unit circle, and then add the real zero closest to that pole.

New in version 0.16.0.

Examples

Design a 6th order low-pass elliptic digital filter for a system with a sampling rate of 8000 Hz that has a pass-band corner frequency of 1000 Hz. The ripple in the pass-band should not exceed 0.087 dB, and the attenuation in the stop-band should be at least 90 dB.

In the following call to `signal.ellip`, we could use `output='sos'`, but for this example, we'll use `output='zpk'`, and then convert to SOS format with `zpk2sos`:

```
>>> from scipy import signal
>>> z, p, k = signal.ellip(6, 0.087, 90, 1000/(0.5*8000), output='zpk')
```

Now convert to SOS format.

```
>>> sos = signal.zpk2sos(z, p, k)
```

The coefficients of the numerators of the sections:

```
>>> sos[:, :3]
array([[ 0.0014154 ,  0.00248707,  0.0014154 ],
       [ 1.          ,  0.72965193,  1.          ],
       [ 1.          ,  0.17594966,  1.          ]])
```

The symmetry in the coefficients occurs because all the zeros are on the unit circle.

The coefficients of the denominators of the sections:

```
>>> sos[:, 3:]
array([[ 1.          , -1.32543251,  0.46989499],
       [ 1.          , -1.26117915,  0.6262586 ],
       [ 1.          , -1.25707217,  0.86199667]])
```

The next example shows the effect of the `pairing` option. We have a system with three poles and three zeros, so the SOS array will have shape (2, 6). The means there is, in effect, an extra pole and an extra zero at the origin in the SOS representation.

```
>>> z1 = np.array([-1, -0.5-0.5j, -0.5+0.5j])
>>> p1 = np.array([0.75, 0.8+0.1j, 0.8-0.1j])
```

With `pairing='nearest'` (the default), we obtain

```
>>> signal.zpk2sos(z1, p1, 1)
array([[ 1. ,  1. ,  0.5 ,  1. , -0.75,  0. ],
       [ 1. ,  1. ,  0. ,  1. , -1.6 ,  0.65]])
```

The first section has the zeros $\{-0.5-0.05j, -0.5+0.5j\}$ and the poles $\{0, 0.75\}$, and the second section has the zeros $\{-1, 0\}$ and poles $\{0.8+0.1j, 0.8-0.1j\}$. Note that the extra pole and zero at the origin have been assigned to different sections.

With `pairing='keep_odd'`, we obtain:

```
>>> signal.zpk2sos(z1, p1, 1, pairing='keep_odd')
array([[ 1. ,  1. ,  0. ,  1. , -0.75,  0. ],
       [ 1. ,  1. ,  0.5,  1. , -1.6 ,  0.65]])
```

The extra pole and zero at the origin are in the same section. The first section is, in effect, a first-order section.

scipy.signal.zpk2ss

`scipy.signal.zpk2ss(z, p, k)`

Zero-pole-gain representation to state-space representation

Parameters

z, p [sequence] Zeros and poles.
k [float] System gain.

Returns

A, B, C, D [ndarray] State space representation of the system, in controller canonical form.

scipy.signal.ss2tf

`scipy.signal.ss2tf(A, B, C, D, input=0)`

State-space to transfer function.

A, B, C, D defines a linear state-space system with p inputs, q outputs, and n state variables.

Parameters

A [array_like] State (or system) matrix of shape (n, n)
B [array_like] Input matrix of shape (n, p)
C [array_like] Output matrix of shape (q, n)
D [array_like] Feedthrough (or feedforward) matrix of shape (q, p)
input [int, optional] For multiple-input systems, the index of the input to use.

Returns

num [2-D ndarray] Numerator(s) of the resulting transfer function(s). *num* has one row for each of the system's outputs. Each row is a sequence representation of the numerator polynomial.
den [1-D ndarray] Denominator of the resulting transfer function(s). *den* is a sequence representation of the denominator polynomial.

Examples

Convert the state-space representation:

$$\dot{\mathbf{x}}(t) = \begin{bmatrix} -2 & -1 \\ 1 & 0 \end{bmatrix} \mathbf{x}(t) + \begin{bmatrix} 1 \\ 0 \end{bmatrix} \mathbf{u}(t)$$

$$\mathbf{y}(t) = \begin{bmatrix} 1 & 2 \end{bmatrix} \mathbf{x}(t) + \begin{bmatrix} 1 \end{bmatrix} \mathbf{u}(t)$$

```
>>> A = [[-2, -1], [1, 0]]
>>> B = [[1], [0]] # 2-D column vector
>>> C = [[1, 2]] # 2-D row vector
>>> D = 1
```

to the transfer function:

$$H(s) = \frac{s^2 + 3s + 3}{s^2 + 2s + 1}$$

```
>>> from scipy.signal import ss2tf
>>> ss2tf(A, B, C, D)
(array([[1., 3., 3.]]), array([ 1., 2., 1.]))
```

scipy.signal.ss2zpk

`scipy.signal.ss2zpk(A, B, C, D, input=0)`

State-space representation to zero-pole-gain representation.

A, B, C, D defines a linear state-space system with p inputs, q outputs, and n state variables.

Parameters

A	[array_like] State (or system) matrix of shape (n, n)
B	[array_like] Input matrix of shape (n, p)
C	[array_like] Output matrix of shape (q, n)
D	[array_like] Feedthrough (or feedforward) matrix of shape (q, p)
input	[int, optional] For multiple-input systems, the index of the input to use.

Returns

z, p	[sequence] Zeros and poles.
k	[float] System gain.

scipy.signal.sos2zpk

`scipy.signal.sos2zpk(sos)`

Return zeros, poles, and gain of a series of second-order sections

Parameters

sos	[array_like] Array of second-order filter coefficients, must have shape $(n_sections, 6)$. See <code>sosfilt</code> for the SOS filter format specification.
------------	--

Returns

z	[ndarray] Zeros of the transfer function.
----------	---

p [ndarray] Poles of the transfer function.
k [float] System gain.

Notes

The number of zeros and poles returned will be `n_sections * 2` even if some of these are (effectively) zero.
 New in version 0.16.0.

scipy.signal.sos2tf

`scipy.signal.sos2tf(sos)`

Return a single transfer function from a series of second-order sections

Parameters

sos [array_like] Array of second-order filter coefficients, must have shape `(n_sections, 6)`. See `sosfilt` for the SOS filter format specification.

Returns

b [ndarray] Numerator polynomial coefficients.
a [ndarray] Denominator polynomial coefficients.

Notes

New in version 0.16.0.

scipy.signal.cont2discrete

`scipy.signal.cont2discrete(system, dt, method='zoh', alpha=None)`

Transform a continuous to a discrete state-space system.

Parameters

system [a tuple describing the system or an instance of `lti`] The following gives the number of elements in the tuple and the interpretation:

- 1: (instance of `lti`)
- 2: (num, den)
- 3: (zeros, poles, gain)
- 4: (A, B, C, D)

dt [float] The discretization time step.

method [str, optional] Which method to use:

- `gbt`: generalized bilinear transformation
- `bilinear`: Tustin's approximation ("`gbt`" with `alpha=0.5`)
- `euler`: Euler (or forward differencing) method ("`gbt`" with `alpha=0`)
- `backward_diff`: Backwards differencing ("`gbt`" with `alpha=1.0`)
- `zoh`: zero-order hold (default)
- `foh`: first-order hold (*versionadded: 1.3.0*)
- `impulse`: equivalent impulse response (*versionadded: 1.3.0*)

alpha [float within [0, 1], optional] The generalized bilinear transformation weighting parameter, which should only be specified with `method="gbt"`, and is ignored otherwise

Returns

sysd [tuple containing the discrete system] Based on the input type, the output will be of the form

- (num, den, dt) for transfer function input
- (zeros, poles, gain, dt) for zeros-poles-gain input
- (A, B, C, D, dt) for state-space system input

Notes

By default, the routine uses a Zero-Order Hold (zoh) method to perform the transformation. Alternatively, a generalized bilinear transformation may be used, which includes the common Tustin's bilinear approximation, an Euler's method technique, or a backwards differencing technique.

The Zero-Order Hold (zoh) method is based on [1], the generalized bilinear approximation is based on [2] and [3], the First-Order Hold (foh) method is based on [4].

References

[1], [2], [3], [4]

scipy.signal.place_poles

`scipy.signal.place_poles(A, B, poles, method='YT', rtol=0.001, maxiter=30)`

Compute K such that eigenvalues $(A - \text{dot}(B, K)) = \text{poles}$.

K is the gain matrix such as the plant described by the linear system $AX + BU$ will have its closed-loop poles, i.e the eigenvalues $A - B * K$, as close as possible to those asked for in poles.

SISO, MISO and MIMO systems are supported.

Parameters

A, B [ndarray] State-space representation of linear system $AX + BU$.

poles [array_like] Desired real poles and/or complex conjugates poles. Complex poles are only supported with `method="YT"` (default).

method: {'YT', 'KNV0'}, optional
Which method to choose to find the gain matrix K . One of:

- 'YT': Yang Tits
- 'KNV0': Kautsky, Nichols, Van Dooren update method 0

See References and Notes for details on the algorithms.

rtol: float, optional
After each iteration the determinant of the eigenvectors of $A - B * K$ is compared to its previous value, when the relative error between these two values becomes lower than `rtol` the algorithm stops. Default is $1e-3$.

maxiter: int, optional
Maximum number of iterations to compute the gain matrix. Default is 30.

Returns

full_state_feedback

[Bunch object]

full_state_feedback is composed of:

gain_matrix

[1-D ndarray] The closed loop matrix K such as the eigenvalues of $A - BK$ are as close as possible to the requested poles.

computed_poles	[1-D ndarray] The poles corresponding to $A-BK$ sorted as first the real poles in increasing order, then the complex conjugates in lexicographic order.
requested_poles	[1-D ndarray] The poles the algorithm was asked to place sorted as above, they may differ from what was achieved.
X	[2-D ndarray] The transfer matrix such as $X * \text{diag}(\text{poles}) = (A - B*K) * X$ (see Notes)
rtol	[float] The relative tolerance achieved on $\det(X)$ (see Notes). <i>rtol</i> will be NaN if it is possible to solve the system $\text{diag}(\text{poles}) = (A - B*K)$, or 0 when the optimization algorithms can't do anything i.e when $B.\text{shape}[1] == 1$.
nb_iter	[int] The number of iterations performed before converging. <i>nb_iter</i> will be NaN if it is possible to solve the system $\text{diag}(\text{poles}) = (A - B*K)$, or 0 when the optimization algorithms can't do anything i.e when $B.\text{shape}[1] == 1$.

Notes

The Tits and Yang (YT), [2] paper is an update of the original Kautsky et al. (KNV) paper [1]. KNV relies on rank-1 updates to find the transfer matrix X such that $X * \text{diag}(\text{poles}) = (A - B*K) * X$, whereas YT uses rank-2 updates. This yields on average more robust solutions (see [2] pp 21-22), furthermore the YT algorithm supports complex poles whereas KNV does not in its original version. Only update method 0 proposed by KNV has been implemented here, hence the name 'KNV0'.

KNV extended to complex poles is used in Matlab's `place` function, YT is distributed under a non-free licence by Slicot under the name `robpole`. It is unclear and undocumented how KNV0 has been extended to complex poles (Tits and Yang claim on page 14 of their paper that their method can not be used to extend KNV to complex poles), therefore only YT supports them in this implementation.

As the solution to the problem of pole placement is not unique for MIMO systems, both methods start with a tentative transfer matrix which is altered in various way to increase its determinant. Both methods have been proven to converge to a stable solution, however depending on the way the initial transfer matrix is chosen they will converge to different solutions and therefore there is absolutely no guarantee that using 'KNV0' will yield results similar to Matlab's or any other implementation of these algorithms.

Using the default method 'YT' should be fine in most cases; 'KNV0' is only provided because it is needed by 'YT' in some specific cases. Furthermore 'YT' gives on average more robust results than 'KNV0' when $\text{abs}(\det(X))$ is used as a robustness indicator.

[2] is available as a technical report on the following URL: <https://hdl.handle.net/1903/5598>

References

[1], [2]

Examples

A simple example demonstrating real pole placement using both KNV and YT algorithms. This is example number 1 from section 4 of the reference KNV publication ([1]):

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt

>>> A = np.array([[ 1.380, -0.2077,  6.715, -5.676 ],
...              [-0.5814, -4.290,  0,      0.6750 ],
...              [ 1.067,  4.273, -6.654,  5.893 ],
...              [ 0.0480,  4.273,  1.343, -2.104 ]])
>>> B = np.array([[ 0,      5.679 ],
...              [ 1.136,  1.136 ],
...              [ 0,      0,      ],
...              [-3.146,  0      ]])
>>> P = np.array([-0.2, -0.5, -5.0566, -8.6659])
```

Now compute K with KNV method 0, with the default YT method and with the YT method while forcing 100 iterations of the algorithm and print some results after each call.

```
>>> fsf1 = signal.place_poles(A, B, P, method='KNV0')
>>> fsf1.gain_matrix
array([[ 0.20071427, -0.96665799,  0.24066128, -0.10279785],
       [ 0.50587268,  0.57779091,  0.51795763, -0.41991442]])
```

```
>>> fsf2 = signal.place_poles(A, B, P) # uses YT method
>>> fsf2.computed_poles
array([-8.6659, -5.0566, -0.5, -0.2 ])
```

```
>>> fsf3 = signal.place_poles(A, B, P, rtol=-1, maxiter=100)
>>> fsf3.X
array([[ 0.52072442+0.j, -0.08409372+0.j, -0.56847937+0.j,  0.74823657+0.
→j],
       [-0.04977751+0.j, -0.80872954+0.j,  0.13566234+0.j, -0.29322906+0.
→j],
       [-0.82266932+0.j, -0.19168026+0.j, -0.56348322+0.j, -0.43815060+0.
→j],
       [ 0.22267347+0.j,  0.54967577+0.j, -0.58387806+0.j, -0.40271926+0.
→j]])
```

The absolute value of the determinant of X is a good indicator to check the robustness of the results, both 'KNV0' and 'YT' aim at maximizing it. Below a comparison of the robustness of the results above:

```
>>> abs(np.linalg.det(fsf1.X)) < abs(np.linalg.det(fsf2.X))
True
>>> abs(np.linalg.det(fsf2.X)) < abs(np.linalg.det(fsf3.X))
True
```

Now a simple example for complex poles:

```
>>> A = np.array([[ 0,  7/3.,  0,  0 ],
...              [ 0,  0,  0,  7/9. ],
```

(continues on next page)

(continued from previous page)

```

...          [ 0,  0,  0,  0 ],
...          [ 0,  0,  0,  0 ]])
>>> B = np.array([[ 0,  0 ],
...              [ 0,  0 ],
...              [ 1,  0 ],
...              [ 0,  1 ]])
>>> P = np.array([-3, -1, -2-1j, -2+1j]) / 3.
>>> fsf = signal.place_poles(A, B, P, method='YT')


```

We can plot the desired and computed poles in the complex plane:

```

>>> t = np.linspace(0, 2*np.pi, 401)
>>> plt.plot(np.cos(t), np.sin(t), 'k--') # unit circle
>>> plt.plot(fsf.requested_poles.real, fsf.requested_poles.imag,
...         'wo', label='Desired')
>>> plt.plot(fsf.computed_poles.real, fsf.computed_poles.imag, 'bx',
...         label='Placed')
>>> plt.grid()
>>> plt.axis('image')
>>> plt.axis([-1.1, 1.1, -1.1, 1.1])
>>> plt.legend(bbox_to_anchor=(1.05, 1), loc=2, numpoints=1)

```



6.22.9 Waveforms

<code>chirp(t, f0, t1, f1[, method, phi, vertex_zero])</code>	Frequency-swept cosine generator.
<code>gausspulse(t[, fc, bw, bwr, tpr, retquad, ...])</code>	Return a Gaussian modulated sinusoid:
<code>max_len_seq(nbits[, state, length, taps])</code>	Maximum length sequence (MLS) generator.
<code>sawtooth(t[, width])</code>	Return a periodic sawtooth or triangle waveform.
<code>square(t[, duty])</code>	Return a periodic square-wave waveform.

continues on next page

Table 167 – continued from previous page

<code>sweep_poly(t, poly[, phi])</code>	Frequency-swept cosine generator, with a time-dependent frequency.
<code>unit_impulse(shape[, idx, dtype])</code>	Unit impulse signal (discrete delta function) or unit basis vector.

scipy.signal.chirp

`scipy.signal.chirp(t, f0, t1, f1, method='linear', phi=0, vertex_zero=True)`

Frequency-swept cosine generator.

In the following, ‘Hz’ should be interpreted as ‘cycles per unit’; there is no requirement here that the unit is one second. The important distinction is that the units of rotation are cycles, not radians. Likewise, t could be a measurement of space instead of time.

Parameters

t	[array_like] Times at which to evaluate the waveform.
f0	[float] Frequency (e.g. Hz) at time $t=0$.
t1	[float] Time at which $f1$ is specified.
f1	[float] Frequency (e.g. Hz) of the waveform at time $t1$.
method	[{'linear', 'quadratic', 'logarithmic', 'hyperbolic'}, optional] Kind of frequency sweep. If not given, <i>linear</i> is assumed. See Notes below for more details.
phi	[float, optional] Phase offset, in degrees. Default is 0.
vertex_zero	[bool, optional] This parameter is only used when <i>method</i> is ‘quadratic’. It determines whether the vertex of the parabola that is the graph of the frequency is at $t=0$ or $t=t1$.

Returns

y	[ndarray] A numpy array containing the signal evaluated at t with the requested time-varying frequency. More precisely, the function returns $\cos(\text{phase} + (\text{pi}/180) * \text{phi})$ where <i>phase</i> is the integral (from 0 to t) of $2 * \text{pi} * f(t)$. $f(t)$ is defined below.
----------	---

See also:

[`sweep_poly`](#)

Notes

There are four options for the *method*. The following formulas give the instantaneous frequency (in Hz) of the signal generated by *chirp()*. For convenience, the shorter names shown below may also be used.

linear, lin, li:

$$f(t) = f0 + (f1 - f0) * t / t1$$

quadratic, quad, q:

The graph of the frequency $f(t)$ is a parabola through $(0, f0)$ and $(t1, f1)$. By default, the vertex of the parabola is at $(0, f0)$. If *vertex_zero* is False, then the vertex is at $(t1, f1)$. The formula is:

if *vertex_zero* is True:

$$f(t) = f0 + (f1 - f0) * t**2 / t1**2$$

else:

$$f(t) = f1 - (f1 - f0) * (t1 - t)**2 / t1**2$$

To use a more general quadratic function, or an arbitrary polynomial, use the function `scipy.signal.sweep_poly`.

logarithmic, log, lo:

$$f(t) = f_0 * (f_1/f_0)**(t/t_1)$$

f_0 and f_1 must be nonzero and have the same sign.

This signal is also known as a geometric or exponential chirp.

hyperbolic, hyp:

$$f(t) = f_0*f_1*t_1 / ((f_0 - f_1)*t + f_1*t_1)$$

f_0 and f_1 must be nonzero.


Examples

The following will be used in the examples:

```
>>> from scipy.signal import chirp, spectrogram
>>> import matplotlib.pyplot as plt
```

For the first example, we'll plot the waveform for a linear chirp from 6 Hz to 1 Hz over 10 seconds:

```
>>> t = np.linspace(0, 10, 1500)
>>> w = chirp(t, f0=6, f1=1, t1=10, method='linear')
>>> plt.plot(t, w)
>>> plt.title("Linear Chirp, f(0)=6, f(10)=1")
>>> plt.xlabel('t (sec)')
>>> plt.show()
```



For the remaining examples, we'll use higher frequency ranges, and demonstrate the result using `scipy.signal.spectrogram`. We'll use a 4 second interval sampled at 7200 Hz.


```
>>> fs = 7200
>>> T = 4
>>> t = np.arange(0, int(T*fs)) / fs
```

We'll use this function to plot the spectrogram in each example.

```
>>> def plot_spectrogram(title, w, fs):
...     ff, tt, Sxx = spectrogram(w, fs=fs, nperseg=256, nfft=576)
...     plt.pcolormesh(tt, ff[:145], Sxx[:145], cmap='gray_r', shading=
→ 'gouraud')
...     plt.title(title)
...     plt.xlabel('t (sec)')
...     plt.ylabel('Frequency (Hz)')
...     plt.grid()
... 
```

Quadratic chirp from 1500 Hz to 250 Hz (vertex of the parabolic curve of the frequency is at $t=0$):

```
>>> w = chirp(t, f0=1500, f1=250, t1=T, method='quadratic')
>>> plot_spectrogram(f'Quadratic Chirp, f(0)=1500, f({T})=250', w, fs)
>>> plt.show()
```



Quadratic chirp from 1500 Hz to 250 Hz (vertex of the parabolic curve of the frequency is at $t=T$):



```
>>> w = chirp(t, f0=1500, f1=250, t1=T, method='quadratic',
...           vertex_zero=False)
>>> plot_spectrogram(f'Quadratic Chirp, f(0)=1500, f({T})=250\n' +
...                 '(vertex_zero=False)', w, fs)
>>> plt.show()
```


Logarithmic chirp from 1500 Hz to 250 Hz:

```
>>> w = chirp(t, f0=1500, f1=250, t1=T, method='logarithmic')
>>> plot_spectrogram(f'Logarithmic Chirp, f(0)=1500, f({T})=250', w, fs)
>>> plt.show()
```

Hyperbolic chirp from 1500 Hz to 250 Hz:

```
>>> w = chirp(t, f0=1500, f1=250, t1=T, method='hyperbolic')
>>> plot_spectrogram(f'Hyperbolic Chirp, f(0)=1500, f({T})=250', w, fs)
>>> plt.show()
```





scipy.signal.gausspulse

`scipy.signal.gausspulse` (t , $fc=1000$, $bw=0.5$, $bwr=-6$, $tpr=-60$, $retquad=False$, $retenv=False$)

Return a Gaussian modulated sinusoid:

$$\exp(-a t^2) \exp(1j*2*\pi*fc*t).$$

If `retquad` is True, then return the real and imaginary parts (in-phase and quadrature). If `retenv` is True, then return the envelope (unmodulated signal). Otherwise, return the real part of the modulated sinusoid.

Parameters

t	[ndarray or the string 'cutoff'] Input array.
fc	[float, optional] Center frequency (e.g. Hz). Default is 1000.
bw	[float, optional] Fractional bandwidth in frequency domain of pulse (e.g. Hz). Default is 0.5.
bwr	[float, optional] Reference level at which fractional bandwidth is calculated (dB). Default is -6.
tpr	[float, optional] If t is 'cutoff', then the function returns the cutoff time for when the pulse amplitude falls below tpr (in dB). Default is -60.
retquad	[bool, optional] If True, return the quadrature (imaginary) as well as the real part of the signal. Default is False.
retenv	[bool, optional] If True, return the envelope of the signal. Default is False.

Returns

yI	[ndarray] Real part of signal. Always returned.
yQ	[ndarray] Imaginary part of signal. Only returned if <code>retquad</code> is True.
yenv	[ndarray] Envelope of signal. Only returned if <code>retenv</code> is True.


See also:

`scipy.signal.morlet`

Examples

Plot real component, imaginary component, and envelope for a 5 Hz pulse, sampled at 100 Hz for 2 seconds:

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
>>> t = np.linspace(-1, 1, 2 * 100, endpoint=False)
>>> i, q, e = signal.gausspulse(t, fc=5, retquad=True, retenv=True)
>>> plt.plot(t, i, t, q, t, e, '--')
```



scipy.signal.max_len_seq

`scipy.signal.max_len_seq` (*nbits*, *state=None*, *length=None*, *taps=None*)

Maximum length sequence (MLS) generator.

Parameters

- nbits** [int] Number of bits to use. Length of the resulting sequence will be $(2^{**nbits}) - 1$. Note that generating long sequences (e.g., greater than `nbits == 16`) can take a long time.
- state** [array_like, optional] If array, must be of length `nbits`, and will be cast to binary (bool) representation. If `None`, a seed of ones will be used, producing a repeatable representation. If `state` is all zeros, an error is raised as this is invalid. Default: `None`.
- length** [int, optional] Number of samples to compute. If `None`, the entire length $(2^{**nbits}) - 1$ is computed.
- taps** [array_like, optional] Polynomial taps to use (e.g., `[7, 6, 1]` for an 8-bit sequence). If `None`, taps will be automatically selected (for up to `nbits == 32`).

Returns

- seq** [array] Resulting MLS sequence of 0's and 1's.
- state** [array] The final state of the shift register.

Notes

The algorithm for MLS generation is generically described in:

https://en.wikipedia.org/wiki/Maximum_length_sequence

The default values for taps are specifically taken from the first option listed for each value of `nbits` in:

http://www.newwaveinstruments.com/resources/articles/m_sequence_linear_feedback_shift_register_lfsr.htm

New in version 0.15.0.


Examples

MLS uses binary convention:

```
>>> from scipy.signal import max_len_seq
>>> max_len_seq(4)[0]
array([1, 1, 1, 1, 0, 1, 0, 1, 1, 0, 0, 1, 0, 0, 0], dtype=int8)
```

MLS has a white spectrum (except for DC):


```
>>> import matplotlib.pyplot as plt
>>> from numpy.fft import fft, ifft, fftshift, fftfreq
>>> seq = max_len_seq(6)[0]*2-1 # +1 and -1
>>> spec = fft(seq)
>>> N = len(seq)
>>> plt.plot(fftshift(fftfreq(N)), fftshift(np.abs(spec)), '.-')
>>> plt.margins(0.1, 0.1)
>>> plt.grid(True)
>>> plt.show()
```



Circular autocorrelation of MLS is an impulse:

```

>>> acorrirc = ifft(spec * np.conj(spec)).real
>>> plt.figure()
>>> plt.plot(np.arange(-N/2+1, N/2+1), fftshift(acorrirc), '.-')
>>> plt.margins(0.1, 0.1)
>>> plt.grid(True)
>>> plt.show()
    
```



Linear autocorrelation of MLS is approximately an impulse:

```

>>> acorr = np.correlate(seq, seq, 'full')
>>> plt.figure()
>>> plt.plot(np.arange(-N+1, N), acorr, '.-')
>>> plt.margins(0.1, 0.1)
>>> plt.grid(True)
>>> plt.show()
    
```

scipy.signal.sawtooth

`scipy.signal.sawtooth(t, width=1)`

Return a periodic sawtooth or triangle waveform.

The sawtooth waveform has a period 2π , rises from -1 to 1 on the interval 0 to $\text{width} \cdot 2\pi$, then drops from 1 to -1 on the interval $\text{width} \cdot 2\pi$ to 2π . *width* must be in the interval [0, 1].


Note that this is not band-limited. It produces an infinite number of harmonics, which are aliased back and forth across the frequency spectrum.

Parameters

t [array_like] Time.

width [array_like, optional] Width of the rising ramp as a proportion of the total cycle. Default is 1, producing a rising ramp, while 0 produces a falling ramp. *width* = 0.5 produces a triangle wave. If an array, causes wave shape to change over time, and must be the same length as t.

Returns




`y` [ndarray] Output array containing the sawtooth waveform.

Examples

A 5 Hz waveform sampled at 500 Hz for 1 second:

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
>>> t = np.linspace(0, 1, 500)
>>> plt.plot(t, signal.sawtooth(2 * np.pi * 5 * t))
```



scipy.signal.square

`scipy.signal.square(t, duty=0.5)`

Return a periodic square-wave waveform.

The square wave has a period 2π , has value $+1$ from 0 to $2\pi \cdot \text{duty}$ and -1 from $2\pi \cdot \text{duty}$ to 2π . *duty* must be in the interval $[0,1]$.

Note that this is not band-limited. It produces an infinite number of harmonics, which are aliased back and forth across the frequency spectrum.

Parameters

t	[array_like] The input time array.
duty	[array_like, optional] Duty cycle. Default is 0.5 (50% duty cycle). If an array, causes wave shape to change over time, and must be the same length as t.

Returns

y	[ndarray] Output array containing the square waveform.
----------	--

Examples

A 5 Hz waveform sampled at 500 Hz for 1 second:

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
>>> t = np.linspace(0, 1, 500, endpoint=False)
>>> plt.plot(t, signal.square(2 * np.pi * 5 * t))
>>> plt.ylim(-2, 2)
```

A pulse-width modulated sine wave:

```
>>> plt.figure()
>>> sig = np.sin(2 * np.pi * t)
>>> pwm = signal.square(2 * np.pi * 30 * t, duty=(sig + 1)/2)
>>> plt.subplot(2, 1, 1)
>>> plt.plot(t, sig)
>>> plt.subplot(2, 1, 2)
>>> plt.plot(t, pwm)
>>> plt.ylim(-1.5, 1.5)
```

scipy.signal.sweep_poly



`scipy.signal.sweep_poly(t, poly, phi=0)`

Frequency-swept cosine generator, with a time-dependent frequency.

This function generates a sinusoidal function whose instantaneous frequency varies with time. The frequency at time t is given by the polynomial *poly*.

Parameters

t	[ndarray] Times at which to evaluate the waveform.
poly	[1-D array_like or instance of <code>numpy.poly1d</code>] The desired frequency expressed as a polynomial. If <i>poly</i> is a list or ndarray of length n , then the elements of <i>poly</i> are the coefficients of the polynomial, and the instantaneous frequency is $f(t) = \text{poly}[0] \cdot t^{n-1} + \text{poly}[1] \cdot t^{n-2} + \dots + \text{poly}[n-1]$



If *poly* is an instance of `numpy.poly1d`, then the instantaneous frequency is

$$f(t) = \text{poly}(t)$$

phi [float, optional] Phase offset, in degrees, Default: 0.

Returns

sweep_poly

[ndarray] A numpy array containing the signal evaluated at *t* with the requested time-varying frequency. More precisely, the function returns $\cos(\text{phase} + (\pi/180) * \text{phi})$, where *phase* is the integral (from 0 to *t*) of $2 * \pi * f(t)$; *f(t)* is defined above.

See also:

[*chirp*](#)

Notes

New in version 0.8.0.

If *poly* is a list or ndarray of length *n*, then the elements of *poly* are the coefficients of the polynomial, and the instantaneous frequency is:

$$f(t) = \text{poly}[0]*t^{n-1} + \text{poly}[1]*t^{n-2} + \dots + \text{poly}[n-1]$$

If *poly* is an instance of `numpy.poly1d`, then the instantaneous frequency is:

$$f(t) = \text{poly}(t)$$

Finally, the output *s* is:

$$\cos(\text{phase} + (\pi/180) * \text{phi})$$

where *phase* is the integral from 0 to *t* of $2 * \pi * f(t)$, *f(t)* as defined above.

Examples

Compute the waveform with instantaneous frequency:

```
f(t) = 0.025*t**3 - 0.36*t**2 + 1.25*t + 2
```

over the interval $0 \leq t \leq 10$.

```
>>> from scipy.signal import sweep_poly
>>> p = np.poly1d([0.025, -0.36, 1.25, 2.0])
>>> t = np.linspace(0, 10, 5001)
>>> w = sweep_poly(t, p)
```


Plot it:

```
>>> import matplotlib.pyplot as plt
>>> plt.subplot(2, 1, 1)
>>> plt.plot(t, w)
>>> plt.title("Sweep Poly\nwith frequency " +
...          "$f(t) = 0.025t^3 - 0.36t^2 + 1.25t + 2$")
>>> plt.subplot(2, 1, 2)
>>> plt.plot(t, p(t), 'r', label='f(t)')
>>> plt.legend()
```

(continues on next page)

(continued from previous page)

```
>>> plt.xlabel('t')
>>> plt.tight_layout()
>>> plt.show()
```



scipy.signal.unit_impulse

`scipy.signal.unit_impulse` (*shape*, *idx=None*, *dtype=<class 'float'>*)

Unit impulse signal (discrete delta function) or unit basis vector.

Parameters

- shape** [int or tuple of int] Number of samples in the output (1-D), or a tuple that represents the shape of the output (N-D).
- idx** [None or int or tuple of int or 'mid', optional] Index at which the value is 1. If `None`, defaults to the 0th element. If `idx='mid'`, the impulse will be centered at `shape // 2` in all dimensions. If an int, the impulse will be at `idx` in all dimensions.
- dtype** [data-type, optional] The desired data-type for the array, e.g., `numpy.int8`. Default is `numpy.float64`.

Returns

- y** [ndarray] Output array containing an impulse signal.

Notes

The 1D case is also known as the Kronecker delta.

New in version 0.19.0.

Examples

An impulse at the 0th element ($\delta[n]$):

```
>>> from scipy import signal
>>> signal.unit_impulse(8)
array([ 1.,  0.,  0.,  0.,  0.,  0.,  0.,  0.]
```

Impulse offset by 2 samples ($\delta[n - 2]$):

```
>>> signal.unit_impulse(7, 2)
array([ 0.,  0.,  1.,  0.,  0.,  0.,  0.]
```

2-dimensional impulse, centered:

```
>>> signal.unit_impulse((3, 3), 'mid')
array([[ 0.,  0.,  0.],
       [ 0.,  1.,  0.],
       [ 0.,  0.,  0.]])
```

Impulse at (2, 2), using broadcasting:

```
>>> signal.unit_impulse((4, 4), 2)
array([[ 0.,  0.,  0.,  0.],
       [ 0.,  0.,  0.,  0.],
       [ 0.,  0.,  1.,  0.],
       [ 0.,  0.,  0.,  0.]])
```

Plot the impulse response of a 4th-order Butterworth lowpass filter:

```
>>> imp = signal.unit_impulse(100, 'mid')
>>> b, a = signal.butter(4, 0.2)
>>> response = signal.lfilter(b, a, imp)
```


```
>>> import matplotlib.pyplot as plt
>>> plt.plot(np.arange(-50, 50), imp)
>>> plt.plot(np.arange(-50, 50), response)
>>> plt.margins(0.1, 0.1)
>>> plt.xlabel('Time [samples]')
>>> plt.ylabel('Amplitude')
>>> plt.grid(True)
>>> plt.show()
```

6.22.10 Window functions

For window functions, see the `scipy.signal.windows` namespace.

In the `scipy.signal` namespace, there is a convenience function to obtain these windows by name:

<code>get_window(window, Nx[, fftbins])</code>	Return a window of a given length and type.
--	---



scipy.signal.get_window

`scipy.signal.get_window(window, Nx, fftbins=True)`

Return a window of a given length and type.

Parameters

- window** [string, float, or tuple] The type of window to create. See below for more details.
- Nx** [int] The number of samples in the window.
- fftbins** [bool, optional] If True (default), create a “periodic” window, ready to use with *ifftshift* and be multiplied by the result of an FFT (see also *fftfreq*). If False, create a “symmetric” window, for use in filter design.

Returns

- get_window** [ndarray] Returns a window of length *Nx* and type *window*

Notes

Window types:

- boxcar
- triang
- blackman
- hamming
- hann
- bartlett
- flattop
- parzen
- bohman

- blackmanharris
- nuttall
- barthann
- kaiser (needs beta)
- gaussian (needs standard deviation)
- general_gaussian (needs power, width)
- dpss (needs normalized half-bandwidth)
- chebwin (needs attenuation)
- exponential (needs center, decay scale)
- tukey (needs taper fraction)
- taylor (needs number of constant sidelobes, sidelobe level)

If the window requires no parameters, then *window* can be a string.

If the window requires parameters, then *window* must be a tuple with the first argument the string name of the window, and the next arguments the needed parameters.

If *window* is a floating point number, it is interpreted as the beta parameter of the *kaiser* window.

Each of the window types listed above is also the name of a function that can be called directly to create a window of that type.

Examples

```
>>> from scipy import signal
>>> signal.get_window('triang', 7)
array([ 0.125,  0.375,  0.625,  0.875,  0.875,  0.625,  0.375])
>>> signal.get_window(('kaiser', 4.0), 9)
array([ 0.08848053,  0.29425961,  0.56437221,  0.82160913,  0.97885093,
        0.97885093,  0.82160913,  0.56437221,  0.29425961])
>>> signal.get_window(('exponential', None, 1.), 9)
array([ 0.011109 ,  0.03019738,  0.082085 ,  0.22313016,  0.60653066,
        0.60653066,  0.22313016,  0.082085 ,  0.03019738])
>>> signal.get_window(4.0, 9)
array([ 0.08848053,  0.29425961,  0.56437221,  0.82160913,  0.97885093,
        0.97885093,  0.82160913,  0.56437221,  0.29425961])
```

6.22.11 Wavelets

<i>cascade</i> (hk[, J])	Return (x, phi, psi) at dyadic points $K/2^{**J}$ from filter coefficients.
<i>daub</i> (p)	The coefficients for the FIR low-pass filter producing Daubechies wavelets.
<i>morlet</i> (M[, w, s, complete])	Complex Morlet wavelet.
<i>qmf</i> (hk)	Return high-pass qmf filter from low-pass
<i>ricker</i> (points, a)	Return a Ricker wavelet, also known as the “Mexican hat wavelet”.

continues on next page

Table 169 – continued from previous page

<code>morlet2(M, s[, w])</code>	Complex Morlet wavelet, designed to work with <code>cwt</code> .
<code>cwt(data, wavelet, widths[, dtype])</code>	Continuous wavelet transform.

scipy.signal.cascade`scipy.signal.cascade(hk, J=7)`Return (x, phi, psi) at dyadic points $K/2^{**J}$ from filter coefficients.**Parameters**

- hk** [array_like] Coefficients of low-pass filter.
J [int, optional] Values will be computed at grid points $K/2^{**J}$. Default is 7.

Returns

- x** [ndarray] The dyadic points $K/2^{**J}$ for $K=0 \dots N * (2^{**J}) - 1$ where $\text{len}(hk) = \text{len}(gk) = N + 1$.
phi [ndarray] The scaling function $\text{phi}(x)$ at x : $\text{phi}(x) = \text{sum}(hk * \text{phi}(2x - k))$, where k is from 0 to N .
psi [ndarray, optional] The wavelet function $\text{psi}(x)$ at x : $\text{psi}(x) = \text{sum}(gk * \text{phi}(2x - k))$, where k is from 0 to N . *psi* is only returned if *gk* is not None.

Notes

The algorithm uses the vector cascade algorithm described by Strang and Nguyen in “Wavelets and Filter Banks”. It builds a dictionary of values and slices for quick reuse. Then inserts vectors into final vector at the end.

scipy.signal.daub`scipy.signal.daub(p)`

The coefficients for the FIR low-pass filter producing Daubechies wavelets.

 $p \geq 1$ gives the order of the zero at $f=1/2$. There are $2p$ filter coefficients.**Parameters**

- p** [int] Order of the zero at $f=1/2$, can have values from 1 to 34.

Returns

- daub** [ndarray] Return

scipy.signal.morlet`scipy.signal.morlet(M, w=5.0, s=1.0, complete=True)`

Complex Morlet wavelet.

Parameters

- M** [int] Length of the wavelet.
w [float, optional] Omega0. Default is 5
s [float, optional] Scaling factor, windowed from $-s * 2 * \pi$ to $+s * 2 * \pi$. Default is 1.
complete [bool, optional] Whether to use the complete or the standard version.

Returns

morlet [(M,) ndarray]

See also:

morlet2

Implementation of Morlet wavelet, compatible with *cwt*.

scipy.signal.gausspulse

Notes

The standard version:

```
pi**-0.25 * exp(1j*w*x) * exp(-0.5*(x**2))
```

This commonly used wavelet is often referred to simply as the Morlet wavelet. Note that this simplified version can cause admissibility problems at low values of w .

The complete version:

```
pi**-0.25 * (exp(1j*w*x) - exp(-0.5*(w**2))) * exp(-0.5*(x**2))
```

This version has a correction term to improve admissibility. For w greater than 5, the correction term is negligible.

Note that the energy of the return wavelet is not normalised according to s .

The fundamental frequency of this wavelet in Hz is given by $f = 2*s*w*r / M$ where r is the sampling rate.

Note: This function was created before *cwt* and is not compatible with it.

scipy.signal.qmf

`scipy.signal.qmf` (*hk*)

Return high-pass qmf filter from low-pass

Parameters

hk [array_like] Coefficients of high-pass filter.

scipy.signal.ricker

`scipy.signal.ricker` (*points, a*)

Return a Ricker wavelet, also known as the “Mexican hat wavelet”.

It models the function:

$$A * (1 - (x/a)**2) * exp(-0.5*(x/a)**2),$$

where $A = 2 / (\text{sqrt}(3*a) * (\text{pi}^{0.25}))$.

Parameters

points [int] Number of points in *vector*. Will be centered around 0.
a [scalar] Width parameter of the wavelet.


Returns

vector [(N,) ndarray] Array of length *points* in shape of ricker curve.

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> points = 100
>>> a = 4.0
>>> vec2 = signal.ricker(points, a)
>>> print(len(vec2))
100
>>> plt.plot(vec2)
>>> plt.show()
```



scipy.signal.morlet2

`scipy.signal.morlet2` ($M, s, w=5$)

Complex Morlet wavelet, designed to work with `cwt`.

Returns the complete version of morlet wavelet, normalised according to s :

$$\exp(1j*w*x/s) * \exp(-0.5*(x/s)**2) * \text{pi}^{**(-0.25)} * \text{sqrt}(1/s)$$

Parameters

M [int] Length of the wavelet.
s [float] Width parameter of the wavelet.
w [float, optional] Omega0. Default is 5

Returns

morlet [(M,) ndarray]

See also:

morlet

Implementation of Morlet wavelet, incompatible with *cwt*

Notes

New in version 1.4.0.

This function was designed to work with *cwt*. Because *morlet2* returns an array of complex numbers, the *dtype* argument of *cwt* should be set to *complex128* for best results.

Note the difference in implementation with *morlet*. The fundamental frequency of this wavelet in Hz is given by:

$$f = w * fs / (2 * s * np.pi)$$


where *fs* is the sampling rate and *s* is the wavelet width parameter. Similarly we can get the wavelet width parameter at *f*:

$$s = w * fs / (2 * f * np.pi)$$

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

```
>>> M = 100
>>> s = 4.0
>>> w = 2.0
>>> wavelet = signal.morlet2(M, s, w)
>>> plt.plot(abs(wavelet))
>>> plt.show()
```




This example shows basic use of *morlet2* with *cwt* in time-frequency analysis:


```

>>> from scipy import signal
>>> import matplotlib.pyplot as plt
>>> t, dt = np.linspace(0, 1, 200, retstep=True)
>>> fs = 1/dt
>>> w = 6.
>>> sig = np.cos(2*np.pi*(50 + 10*t)*t) + np.sin(40*np.pi*t)
>>> freq = np.linspace(1, fs/2, 100)
>>> widths = w*fs / (2*freq*np.pi)
>>> cwtm = signal.cwt(sig, signal.morlet2, widths, w=w)
>>> plt.pcolormesh(t, freq, np.abs(cwtm), cmap='viridis', shading='gouraud
→')
>>> plt.show()

```



scipy.signal.cwt

`scipy.signal.cwt` (*data*, *wavelet*, *widths*, *dtype=None*, ***kwargs*)

Continuous wavelet transform.

Performs a continuous wavelet transform on *data*, using the *wavelet* function. A CWT performs a convolution with *data* using the *wavelet* function, which is characterized by a width parameter and length parameter. The *wavelet* function is allowed to be complex.

Parameters

- data** [(N,) ndarray] data on which to perform the transform.
- wavelet** [function] Wavelet function, which should take 2 arguments. The first argument is the number of points that the returned vector will have (`len(wavelet(length,width)) == length`). The second is a width parameter, defining the size of the wavelet (e.g. standard deviation of a gaussian). See *ricker*, which satisfies these requirements.
- widths** [(M,) sequence] Widths to use for transform.
- dtype** [data-type, optional] The desired data type of output. Defaults to `float64` if the output of *wavelet* is real and `complex128` if it is complex.
New in version 1.4.0.

kwargs Keyword arguments passed to wavelet function.
New in version 1.4.0.

Returns

cwt: (M, N) ndarray
Will have shape of (len(widths), len(data)).

Notes

New in version 1.4.0.

For non-symmetric, complex-valued wavelets, the input signal is convolved with the time-reversed complex-conjugate of the wavelet data [1].

```
length = min(10 * width[ii], len(data))
cwt[ii,:] = signal.convolve(data, np.conj(wavelet(length, width[ii],
**kwargs))[:,::-1], mode='same')
```

References


[1]

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
>>> t = np.linspace(-1, 1, 200, endpoint=False)
>>> sig = np.cos(2 * np.pi * 7 * t) + signal.gausspulse(t - 0.4, fc=2)
>>> widths = np.arange(1, 31)
>>> cwtmatr = signal.cwt(sig, signal.ricker, widths)
>>> plt.imshow(cwtmatr, extent=[-1, 1, 1, 31], cmap='PRGn', aspect='auto',
...           vmax=abs(cwtmatr).max(), vmin=-abs(cwtmatr).max())
>>> plt.show()
```

6.22.12 Peak finding

<code>argrelemin(data[, axis, order, mode])</code>	Calculate the relative minima of <i>data</i> .
<code>argrelmax(data[, axis, order, mode])</code>	Calculate the relative maxima of <i>data</i> .
<code>argrelextrema(data, comparator[, axis, ...])</code>	Calculate the relative extrema of <i>data</i> .
<code>find_peaks(x[, height, threshold, distance, ...])</code>	Find peaks inside a signal based on peak properties.
<code>find_peaks_cwt(vector, widths[, wavelet, ...])</code>	Find peaks in a 1-D array with wavelet transformation.
<code>peak_prominences(x, peaks[, wlen])</code>	Calculate the prominence of each peak in a signal.
<code>peak_widths(x, peaks[, rel_height, ...])</code>	Calculate the width of each peak in a signal.



scipy.signal.argrelmin

`scipy.signal.argrelmin` (*data*, *axis=0*, *order=1*, *mode='clip'*)

Calculate the relative minima of *data*.

Parameters

- data** [ndarray] Array in which to find the relative minima.
- axis** [int, optional] Axis over which to select from *data*. Default is 0.
- order** [int, optional] How many points on each side to use for the comparison to consider `comparator(n, n+x)` to be True.
- mode** [str, optional] How the edges of the vector are treated. Available options are 'wrap' (wrap around) or 'clip' (treat overflow as the same as the last (or first) element). Default 'clip'. See `numpy.take`.

Returns

- extrema** [tuple of ndarrays] Indices of the minima in arrays of integers. `extrema[k]` is the array of indices of axis *k* of *data*. Note that the return value is a tuple even when *data* is 1-D.

See also:

[`argrelextrema`](#), [`argrelmax`](#), [`find_peaks`](#)

Notes

This function uses [`argrelextrema`](#) with `np.less` as comparator. Therefore, it requires a strict inequality on both sides of a value to consider it a minimum. This means flat minima (more than one sample wide) are not detected. In case of 1-D *data* [`find_peaks`](#) can be used to detect all local minima, including flat ones, by calling it with negated *data*.

New in version 0.11.0.

Examples

```
>>> from scipy.signal import argrelmin
>>> x = np.array([2, 1, 2, 3, 2, 0, 1, 0])
>>> argrelmin(x)
(array([1, 5]),)
>>> y = np.array([[1, 2, 1, 2],
...               [2, 2, 0, 0],
...               [5, 3, 4, 4]])
...
>>> argrelmin(y, axis=1)
(array([0, 2]), array([2, 1]))
```

scipy.signal.argrelmax

`scipy.signal.argrelmax` (*data*, *axis=0*, *order=1*, *mode='clip'*)

Calculate the relative maxima of *data*.

Parameters

- data** [ndarray] Array in which to find the relative maxima.
- axis** [int, optional] Axis over which to select from *data*. Default is 0.
- order** [int, optional] How many points on each side to use for the comparison to consider `comparator(n, n+x)` to be True.
- mode** [str, optional] How the edges of the vector are treated. Available options are 'wrap' (wrap around) or 'clip' (treat overflow as the same as the last (or first) element). Default 'clip'. See `numpy.take`.

Returns

- extrema** [tuple of ndarrays] Indices of the maxima in arrays of integers. `extrema[k]` is the array of indices of axis *k* of *data*. Note that the return value is a tuple even when *data* is 1-D.

See also:

[*argrelextrema*](#), [*argrelmin*](#), [*find_peaks*](#)

Notes

This function uses [*argrelextrema*](#) with `np.greater` as comparator. Therefore, it requires a strict inequality on both sides of a value to consider it a maximum. This means flat maxima (more than one sample wide) are not detected. In case of 1-D *data* [*find_peaks*](#) can be used to detect all local maxima, including flat ones.

New in version 0.11.0.

Examples

```

>>> from scipy.signal import argrelmax
>>> x = np.array([2, 1, 2, 3, 2, 0, 1, 0])
>>> argrelmax(x)
(array([3, 6]),)
>>> y = np.array([[1, 2, 1, 2],
...               [2, 2, 0, 0],
...               [5, 3, 4, 4]])
...
>>> argrelmax(y, axis=1)
(array([0]), array([1]))

```

scipy.signal.argrelextrema

`scipy.signal.argrelextrema` (*data*, *comparator*, *axis=0*, *order=1*, *mode='clip'*)

Calculate the relative extrema of *data*.

Parameters

- data** [ndarray] Array in which to find the relative extrema.
- comparator** [callable] Function to use to compare two data points. Should take two arrays as arguments.
- axis** [int, optional] Axis over which to select from *data*. Default is 0.
- order** [int, optional] How many points on each side to use for the comparison to consider `comparator(n, n+x)` to be True.
- mode** [str, optional] How the edges of the vector are treated. 'wrap' (wrap around) or 'clip' (treat overflow as the same as the last (or first) element). Default is 'clip'. See `numpy.take`.

Returns

- extrema** [tuple of ndarrays] Indices of the maxima in arrays of integers. `extrema[k]` is the array of indices of axis *k* of *data*. Note that the return value is a tuple even when *data* is 1-D.

See also:

[`argrelmin`](#), [`argrelmax`](#)

Notes

New in version 0.11.0.

Examples

```

>>> from scipy.signal import argrelextrema
>>> x = np.array([2, 1, 2, 3, 2, 0, 1, 0])
>>> argrelextrema(x, np.greater)
(array([3, 6]),)
>>> y = np.array([[1, 2, 1, 2],
...               [2, 2, 0, 0],
...               [5, 3, 4, 4]])
...

```

(continues on next page)

(continued from previous page)

```
>>> argrelextrema(y, np.less, axis=1)
(array([0, 2]), array([2, 1]))
```

scipy.signal.find_peaks

`scipy.signal.find_peaks` (*x*, *height=None*, *threshold=None*, *distance=None*, *prominence=None*, *width=None*, *wlen=None*, *rel_height=0.5*, *plateau_size=None*)

Find peaks inside a signal based on peak properties.

This function takes a 1-D array and finds all local maxima by simple comparison of neighboring values. Optionally, a subset of these peaks can be selected by specifying conditions for a peak's properties.

Parameters

- x** [sequence] A signal with peaks.
- height** [number or ndarray or sequence, optional] Required height of peaks. Either a number, `None`, an array matching *x* or a 2-element sequence of the former. The first element is always interpreted as the minimal and the second, if supplied, as the maximal required height.
- threshold** [number or ndarray or sequence, optional] Required threshold of peaks, the vertical distance to its neighboring samples. Either a number, `None`, an array matching *x* or a 2-element sequence of the former. The first element is always interpreted as the minimal and the second, if supplied, as the maximal required threshold.
- distance** [number, optional] Required minimal horizontal distance (≥ 1) in samples between neighbouring peaks. Smaller peaks are removed first until the condition is fulfilled for all remaining peaks.
- prominence** [number or ndarray or sequence, optional] Required prominence of peaks. Either a number, `None`, an array matching *x* or a 2-element sequence of the former. The first element is always interpreted as the minimal and the second, if supplied, as the maximal required prominence.
- width** [number or ndarray or sequence, optional] Required width of peaks in samples. Either a number, `None`, an array matching *x* or a 2-element sequence of the former. The first element is always interpreted as the minimal and the second, if supplied, as the maximal required width.
- wlen** [int, optional] Used for calculation of the peaks prominences, thus it is only used if one of the arguments *prominence* or *width* is given. See argument *wlen* in [peak_prominences](#) for a full description of its effects.
- rel_height** [float, optional] Used for calculation of the peaks width, thus it is only used if *width* is given. See argument *rel_height* in [peak_widths](#) for a full description of its effects.
- plateau_size** [number or ndarray or sequence, optional] Required size of the flat top of peaks in samples. Either a number, `None`, an array matching *x* or a 2-element sequence of the former. The first element is always interpreted as the minimal and the second, if supplied as the maximal required plateau size.
New in version 1.2.0.

Returns

- peaks** [ndarray] Indices of peaks in *x* that satisfy all given conditions.
- properties** [dict] A dictionary containing properties of the returned peaks which were calculated as intermediate results during evaluation of the specified conditions:
 - **'peak_heights'**
If *height* is given, the height of each peak in *x*.

- **‘left_thresholds’, ‘right_thresholds’**
If *threshold* is given, these keys contain a peaks vertical distance to its neighbouring samples.
- **‘prominences’, ‘right_bases’, ‘left_bases’**
If *prominence* is given, these keys are accessible. See [peak_prominences](#) for a description of their content.
- **‘width_heights’, ‘left_ips’, ‘right_ips’**
If *width* is given, these keys are accessible. See [peak_widths](#) for a description of their content.
- **‘plateau_sizes’, ‘left_edges’, ‘right_edges’**
If *plateau_size* is given, these keys are accessible and contain the indices of a peak’s edges (edges are still part of the plateau) and the calculated plateau sizes.
New in version 1.2.0.

To calculate and return properties without excluding peaks, provide the open interval `(None, None)` as a value to the appropriate argument (excluding *distance*).

Warns

PeakPropertyWarning

Raised if a peak’s properties have unexpected values (see [peak_prominences](#) and [peak_widths](#)).

Warning: This function may return unexpected results for data containing NaNs. To avoid this, NaNs should either be removed or replaced.

See also:

[find_peaks_cwt](#)

Find peaks using the wavelet transformation.

[peak_prominences](#)

Directly calculate the prominence of peaks.

[peak_widths](#)

Directly calculate the width of peaks.

Notes

In the context of this function, a peak or local maximum is defined as any sample whose two direct neighbours have a smaller amplitude. For flat peaks (more than one sample of equal amplitude wide) the index of the middle sample is returned (rounded down in case the number of samples is even). For noisy signals the peak locations can be off because the noise might change the position of local maxima. In those cases consider smoothing the signal before searching for peaks or use other peak finding and fitting methods (like [find_peaks_cwt](#)).

Some additional comments on specifying conditions:

- Almost all conditions (excluding *distance*) can be given as half-open or closed intervals, e.g., `1` or `(1, None)` defines the half-open interval $[1, \infty]$ while `(None, 1)` defines the interval $[-\infty, 1]$. The open interval `(None, None)` can be specified as well, which returns the matching properties without exclusion of peaks.
- The border is always included in the interval used to select valid peaks.


- For several conditions the interval borders can be specified with arrays matching x in shape which enables dynamic constrains based on the sample position.
- The conditions are evaluated in the following order: *plateau_size*, *height*, *threshold*, *distance*, *prominence*, *width*. In most cases this order is the fastest one because faster operations are applied first to reduce the number of peaks that need to be evaluated later.
- While indices in *peaks* are guaranteed to be at least *distance* samples apart, edges of flat peaks may be closer than the allowed *distance*.
- Use *wlen* to reduce the time it takes to evaluate the conditions for *prominence* or *width* if x is large or has many local maxima (see *peak_prominences*).

New in version 1.1.0.

Examples

To demonstrate this function's usage we use a signal x supplied with SciPy (see *scipy.misc.electrocardiogram*). Let's find all peaks (local maxima) in x whose amplitude lies above 0.

```
>>> import matplotlib.pyplot as plt
>>> from scipy.misc import electrocardiogram
>>> from scipy.signal import find_peaks
>>> x = electrocardiogram()[2000:4000]
>>> peaks, _ = find_peaks(x, height=0)
>>> plt.plot(x)
>>> plt.plot(peaks, x[peaks], "x")
>>> plt.plot(np.zeros_like(x), "--", color="gray")
>>> plt.show()
```



We can select peaks below 0 with `height=(None, 0)` or use arrays matching x in size to reflect a changing condition for different parts of the signal.

```
>>> border = np.sin(np.linspace(0, 3 * np.pi, x.size))
>>> peaks, _ = find_peaks(x, height=(-border, border))
```


(continues on next page)

(continued from previous page)

```

>>> plt.plot(x)
>>> plt.plot(-border, "--", color="gray")
>>> plt.plot(border, ":", color="gray")
>>> plt.plot(peaks, x[peaks], "x")
>>> plt.show()

```



Another useful condition for periodic signals can be given with the *distance* argument. In this case, we can easily select the positions of QRS complexes within the electrocardiogram (ECG) by demanding a distance of at least 150 samples.

```

>>> peaks, _ = find_peaks(x, distance=150)
>>> np.diff(peaks)
array([186, 180, 177, 171, 177, 169, 167, 164, 158, 162, 172])
>>> plt.plot(x)
>>> plt.plot(peaks, x[peaks], "x")
>>> plt.show()

```

Especially for noisy signals peaks can be easily grouped by their prominence (see [peak_prominences](#)). E.g., we can select all peaks except for the mentioned QRS complexes by limiting the allowed prominence to 0.6.

```

>>> peaks, properties = find_peaks(x, prominence=(None, 0.6))
>>> properties["prominences"].max()
0.5049999999999999
>>> plt.plot(x)
>>> plt.plot(peaks, x[peaks], "x")
>>> plt.show()

```



And, finally, let's examine a different section of the ECG which contains beat forms of different shape. To select only the atypical heart beats, we combine two conditions: a minimal prominence of 1 and width of at least 20 samples.

```

>>> x = electrocardiogram()[17000:18000]
>>> peaks, properties = find_peaks(x, prominence=1, width=20)

```

(continues on next page)




(continued from previous page)

```

>>> properties["prominences"], properties["widths"]
(array([1.495, 2.3  ]), array([36.93773946, 39.32723577]))
>>> plt.plot(x)
>>> plt.plot(peaks, x[peaks], "x")
>>> plt.vlines(x=peaks, ymin=x[peaks] - properties["prominences"],
...           ymax = x[peaks], color = "C1")
>>> plt.hlines(y=properties["width_heights"], xmin=properties["left_ips"],
...           xmax=properties["right_ips"], color = "C1")
>>> plt.show()

```



scipy.signal.find_peaks_cwt

`scipy.signal.find_peaks_cwt` (*vector*, *widths*, *wavelet=None*, *max_distances=None*, *gap_thresh=None*, *min_length=None*, *min_snr=1*, *noise_perc=10*, *window_size=None*)

Find peaks in a 1-D array with wavelet transformation.

The general approach is to smooth *vector* by convolving it with *wavelet(width)* for each width in *widths*. Relative maxima which appear at enough length scales, and with sufficiently high SNR, are accepted.

Parameters

- vector** [ndarray] 1-D array in which to find the peaks.
- widths** [sequence] 1-D array of widths to use for calculating the CWT matrix. In general, this range should cover the expected width of peaks of interest.
- wavelet** [callable, optional] Should take two parameters and return a 1-D array to convolve with *vector*. The first parameter determines the number of points of the returned wavelet array, the second parameter is the scale (*width*) of the wavelet. Should be normalized and symmetric. Default is the ricker wavelet.
- max_distances** [ndarray, optional] At each row, a ridge line is only connected if the relative max at row[n] is within `max_distances[n]` from the relative max at row[n+1]. Default value is `widths/4`.
- gap_thresh**

[float, optional] If a relative maximum is not found within *max_distances*, there will be a gap. A ridge line is discontinued if there are more than *gap_thresh* points without connecting a new relative maximum. Default is the first value of the widths array i.e. `widths[0]`.

min_length

[int, optional] Minimum length a ridge line needs to be acceptable. Default is `cwt.shape[0] / 4`, ie 1/4-th the number of widths.

min_snr

[float, optional] Minimum SNR ratio. Default 1. The signal is the value of the cwt matrix at the shortest length scale (`cwt[0, loc]`), the noise is the *noise_perc`th percentile of datapoints contained within a window of `window_size* around `cwt[0, loc]`.

noise_perc

[float, optional] When calculating the noise floor, percentile of data points examined below which to consider noise. Calculated using *stats.scoreatpercentile*. Default is 10.

window_size

[int, optional] Size of window to use to calculate noise floor. Default is `cwt.shape[1] / 20`.

Returns**peaks_indices**

[ndarray] Indices of the locations in the *vector* where peaks were found. The list is sorted.

See also:*cwt*

Continuous wavelet transform.

find_peaks

Find peaks inside a signal based on peak properties.

Notes

This approach was designed for finding sharp peaks among noisy data, however with proper parameter selection it should function well for different peak shapes.

The algorithm is as follows:

1. Perform a continuous wavelet transform on *vector*, for the supplied *widths*. This is a convolution of *vector* with *wavelet(width)* for each width in *widths*. See *cwt*.
2. Identify “ridge lines” in the cwt matrix. These are relative maxima at each row, connected across adjacent rows. See *identify_ridge_lines*
3. Filter the *ridge_lines* using *filter_ridge_lines*.

New in version 0.11.0.

References

[1]

Examples

```
>>> from scipy import signal
>>> xs = np.arange(0, np.pi, 0.05)
>>> data = np.sin(xs)
>>> peakind = signal.find_peaks_cwt(data, np.arange(1, 10))
>>> peakind, xs[peakind], data[peakind]
([32], array([ 1.6]), array([ 0.9995736]))
```

scipy.signal.peak_prominences

`scipy.signal.peak_prominences` (*x*, *peaks*, *wlen=None*)

Calculate the prominence of each peak in a signal.

The prominence of a peak measures how much a peak stands out from the surrounding baseline of the signal and is defined as the vertical distance between the peak and its lowest contour line.

Parameters

x [sequence] A signal with peaks.
peaks [sequence] Indices of peaks in *x*.
wlen [int, optional] A window length in samples that optionally limits the evaluated area for each peak to a subset of *x*. The peak is always placed in the middle of the window therefore the given length is rounded up to the next odd integer. This parameter can speed up the calculation (see Notes).

Returns

prominences [ndarray] The calculated prominences for each peak in *peaks*.
left_bases, right_bases [ndarray] The peaks' bases as indices in *x* to the left and right of each peak. The higher base of each pair is a peak's lowest contour line.

Raises

ValueError
 If a value in *peaks* is an invalid index for *x*.

Warns

PeakPropertyWarning
 For indices in *peaks* that don't point to valid local maxima in *x*, the returned prominence will be 0 and this warning is raised. This also happens if *wlen* is smaller than the plateau size of a peak.

Warning: This function may return unexpected results for data containing NaNs. To avoid this, NaNs should either be removed or replaced.

See also:

find_peaks

Find peaks inside a signal based on peak properties.

peak_widths

Calculate the width of peaks.

Notes

Strategy to compute a peak's prominence:

1. Extend a horizontal line from the current peak to the left and right until the line either reaches the window border (see *wlen*) or intersects the signal again at the slope of a higher peak. An intersection with a peak of the same height is ignored.
2. On each side find the minimal signal value within the interval defined above. These points are the peak's bases.
3. The higher one of the two bases marks the peak's lowest contour line. The prominence can then be calculated as the vertical difference between the peaks height itself and its lowest contour line.

Searching for the peak's bases can be slow for large x with periodic behavior because large chunks or even the full signal need to be evaluated for the first algorithmic step. This evaluation area can be limited with the parameter *wlen* which restricts the algorithm to a window around the current peak and can shorten the calculation time if the window length is short in relation to x . However, this may stop the algorithm from finding the true global contour line if the peak's true bases are outside this window. Instead, a higher contour line is found within the restricted window leading to a smaller calculated prominence. In practice, this is only relevant for the highest set of peaks in x . This behavior may even be used intentionally to calculate "local" prominences.

New in version 1.1.0.

References

[1]

Examples

```
>>> from scipy.signal import find_peaks, peak_prominences
>>> import matplotlib.pyplot as plt
```

Create a test signal with two overlaid harmonics

```
>>> x = np.linspace(0, 6 * np.pi, 1000)
>>> x = np.sin(x) + 0.6 * np.sin(2.6 * x)
```

Find all peaks and calculate prominences


```
>>> peaks, _ = find_peaks(x)
>>> prominences = peak_prominences(x, peaks)[0]
>>> prominences
array([1.24159486, 0.47840168, 0.28470524, 3.10716793, 0.284603 ,
       0.47822491, 2.48340261, 0.47822491])
```

Calculate the height of each peak's contour line and plot the results

```

>>> contour_heights = x[peaks] - prominences
>>> plt.plot(x)
>>> plt.plot(peaks, x[peaks], "x")
>>> plt.vlines(x=peaks, ymin=contour_heights, ymax=x[peaks])
>>> plt.show()

```




Let's evaluate a second example that demonstrates several edge cases for one peak at index 5.

```

>>> x = np.array([0, 1, 0, 3, 1, 3, 0, 4, 0])
>>> peaks = np.array([5])
>>> plt.plot(x)
>>> plt.plot(peaks, x[peaks], "x")
>>> plt.show()

```



```
>>> peak_prominences(x, peaks) # -> (prominences, left_bases, right_
    ↳bases)
(array([3.]), array([2]), array([6]))
```

Note how the peak at index 3 of the same height is not considered as a border while searching for the left base. Instead, two minima at 0 and 2 are found in which case the one closer to the evaluated peak is always chosen. On the right side, however, the base must be placed at 6 because the higher peak represents the right border to the evaluated area.

```
>>> peak_prominences(x, peaks, wlen=3.1)
(array([2.]), array([4]), array([6]))
```

Here, we restricted the algorithm to a window from 3 to 7 (the length is 5 samples because *wlen* was rounded up to the next odd integer). Thus, the only two candidates in the evaluated area are the two neighboring samples and a smaller prominence is calculated.

scipy.signal.peak_widths

`scipy.signal.peak_widths(x, peaks, rel_height=0.5, prominence_data=None, wlen=None)`
Calculate the width of each peak in a signal.

This function calculates the width of a peak in samples at a relative distance to the peak's height and prominence.

Parameters

- x** [sequence] A signal with peaks.
- peaks** [sequence] Indices of peaks in *x*.
- rel_height** [float, optional] Chooses the relative height at which the peak width is measured as a percentage of its prominence. 1.0 calculates the width of the peak at its lowest contour line while 0.5 evaluates at half the prominence height. Must be at least 0. See notes for further explanation.
- prominence_data** [tuple, optional] A tuple of three arrays matching the output of `peak_prominences` when called with the same arguments *x* and *peaks*. This data are calculated internally if not provided.
- wlen** [int, optional] A window length in samples passed to `peak_prominences` as an optional argument for internal calculation of `prominence_data`. This argument is ignored if `prominence_data` is given.

Returns

- widths** [ndarray] The widths for each peak in samples.
- width_heights** [ndarray] The height of the contour lines at which the *widths* were evaluated.
- left_ips, right_ips** [ndarray] Interpolated positions of left and right intersection points of a horizontal line at the respective evaluation height.

Raises

- ValueError** If `prominence_data` is supplied but doesn't satisfy the condition $0 \leq \text{left_base} \leq \text{peak} \leq \text{right_base} < x.\text{shape}[0]$ for each peak, has the wrong dtype, is not C-contiguous or does not have the same shape.

Warns

PeakPropertyWarning

Raised if any calculated width is 0. This may stem from the supplied *prominence_data* or if *rel_height* is set to 0.

Warning: This function may return unexpected results for data containing NaNs. To avoid this, NaNs should either be removed or replaced.

See also:

[*find_peaks*](#)

Find peaks inside a signal based on peak properties.

[*peak_prominences*](#)

Calculate the prominence of peaks.

Notes

The basic algorithm to calculate a peak's width is as follows:

- Calculate the evaluation height h_{eval} with the formula $h_{eval} = h_{Peak} - P \cdot R$, where h_{Peak} is the height of the peak itself, P is the peak's prominence and R a positive ratio specified with the argument *rel_height*.
- Draw a horizontal line at the evaluation height to both sides, starting at the peak's current vertical position until the lines either intersect a slope, the signal border or cross the vertical position of the peak's base (see [*peak_prominences*](#) for an definition). For the first case, intersection with the signal, the true intersection point is estimated with linear interpolation.
- Calculate the width as the horizontal distance between the chosen endpoints on both sides. As a consequence of this the maximal possible width for each peak is the horizontal distance between its bases.

As shown above to calculate a peak's width its prominence and bases must be known. You can supply these yourself with the argument *prominence_data*. Otherwise, they are internally calculated (see [*peak_prominences*](#)).

New in version 1.1.0.

Examples

```
>>> from scipy.signal import chirp, find_peaks, peak_widths
>>> import matplotlib.pyplot as plt
```

Create a test signal with two overlaid harmonics

```
>>> x = np.linspace(0, 6 * np.pi, 1000)
>>> x = np.sin(x) + 0.6 * np.sin(2.6 * x)
```

Find all peaks and calculate their widths at the relative height of 0.5 (contour line at half the prominence height) and 1 (at the lowest contour line at full prominence height).

```
>>> peaks, _ = find_peaks(x)
>>> results_half = peak_widths(x, peaks, rel_height=0.5)
>>> results_half[0] # widths
array([ 64.25172825,  41.29465463,  35.46943289, 104.71586081,
```

(continues on next page)

(continued from previous page)

```

35.46729324, 41.30429622, 181.93835853, 45.37078546])
>>> results_full = peak_widths(x, peaks, rel_height=1)
>>> results_full[0] # widths
array([181.9396084 , 72.99284945, 61.28657872, 373.84622694,
       61.78404617, 72.48822812, 253.09161876, 79.36860878])


```

Plot signal, peaks and contour lines at which the widths where calculated

```

>>> plt.plot(x)
>>> plt.plot(peaks, x[peaks], "x")
>>> plt.hlines(*results_half[1:], color="C2")
>>> plt.hlines(*results_full[1:], color="C3")
>>> plt.show()

```



6.22.13 Spectral analysis

<code>periodogram(x[, fs, window, nfft, detrend, ...])</code>	Estimate power spectral density using a periodogram.
<code>welch(x[, fs, window, nperseg, noverlap, ...])</code>	Estimate power spectral density using Welch's method.
<code>csd(x, y[, fs, window, nperseg, noverlap, ...])</code>	Estimate the cross power spectral density, P_{xy} , using Welch's method.
<code>coherence(x, y[, fs, window, nperseg, ...])</code>	Estimate the magnitude squared coherence estimate, C_{xy} , of discrete-time signals X and Y using Welch's method.
<code>spectrogram(x[, fs, window, nperseg, ...])</code>	Compute a spectrogram with consecutive Fourier transforms.
<code>lombscargle(x, y, freqs)</code>	Computes the Lomb-Scargle periodogram.
<code>vectorstrength(events, period)</code>	Determine the vector strength of the events corresponding to the given period.
<code>stft(x[, fs, window, nperseg, noverlap, ...])</code>	Compute the Short Time Fourier Transform (STFT).
<code>istft(Zxx[, fs, window, nperseg, noverlap, ...])</code>	Perform the inverse Short Time Fourier transform (iSTFT).

continues on next page

Table 171 – continued from previous page

<code>check_COLA(window, nperseg, noverlap[, toll])</code>	Check whether the Constant OverLap Add (COLA) constraint is met
<code>check_NOLA(window, nperseg, noverlap[, toll])</code>	Check whether the Nonzero Overlap Add (NOLA) constraint is met

scipy.signal.periodogram

`scipy.signal.periodogram(x, fs=1.0, window='boxcar', nfft=None, detrend='constant', return_onesided=True, scaling='density', axis=-1)`

Estimate power spectral density using a periodogram.

Parameters

x	[array_like] Time series of measurement values
fs	[float, optional] Sampling frequency of the <i>x</i> time series. Defaults to 1.0.
window	[str or tuple or array_like, optional] Desired window to use. If <i>window</i> is a string or tuple, it is passed to <code>get_window</code> to generate the window values, which are DFT-even by default. See <code>get_window</code> for a list of windows and required parameters. If <i>window</i> is array_like it will be used directly as the window and its length must be <i>nperseg</i> . Defaults to 'boxcar'.
nfft	[int, optional] Length of the FFT used. If <i>None</i> the length of <i>x</i> will be used.
detrend	[str or function or <i>False</i> , optional] Specifies how to detrend each segment. If <i>detrend</i> is a string, it is passed as the <i>type</i> argument to the <code>detrend</code> function. If it is a function, it takes a segment and returns a detrended segment. If <i>detrend</i> is <i>False</i> , no detrending is done. Defaults to 'constant'.
return_onesided	[bool, optional] If <i>True</i> , return a one-sided spectrum for real data. If <i>False</i> return a two-sided spectrum. Defaults to <i>True</i> , but for complex data, a two-sided spectrum is always returned.
scaling	[{ 'density', 'spectrum' }, optional] Selects between computing the power spectral density ('density') where <i>Pxx</i> has units of V^2/Hz and computing the power spectrum ('spectrum') where <i>Pxx</i> has units of V^2 , if <i>x</i> is measured in V and <i>fs</i> is measured in Hz. Defaults to 'density'
axis	[int, optional] Axis along which the periodogram is computed; the default is over the last axis (i.e. <code>axis=-1</code>).

Returns

f	[ndarray] Array of sample frequencies.
Pxx	[ndarray] Power spectral density or power spectrum of <i>x</i> .

See also:

welch

Estimate power spectral density using Welch's method

lombscargle

Lomb-Scargle periodogram for unevenly sampled data

Notes

New in version 0.12.0.

Examples


```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
>>> np.random.seed(1234)
```

Generate a test signal, a 2 Vrms sine wave at 1234 Hz, corrupted by 0.001 V²/Hz of white noise sampled at 10 kHz.

```
>>> fs = 10e3
>>> N = 1e5
>>> amp = 2*np.sqrt(2)
>>> freq = 1234.0
>>> noise_power = 0.001 * fs / 2
>>> time = np.arange(N) / fs
>>> x = amp*np.sin(2*np.pi*freq*time)
>>> x += np.random.normal(scale=np.sqrt(noise_power), size=time.shape)
```

Compute and plot the power spectral density.

```
>>> f, Pxx_den = signal.periodogram(x, fs)
>>> plt.semilogy(f, Pxx_den)
>>> plt.ylim([1e-7, 1e2])
>>> plt.xlabel('frequency [Hz]')
>>> plt.ylabel('PSD [V**2/Hz]')
>>> plt.show()
```




If we average the last half of the spectral density, to exclude the peak, we can recover the noise power on the signal.

```
>>> np.mean(Pxx_den[25000:])
0.00099728892368242854
```

Now compute and plot the power spectrum.

```
>>> f, Pxx_spec = signal.periodogram(x, fs, 'flattop', scaling='spectrum')
>>> plt.figure()
>>> plt.semilogy(f, np.sqrt(Pxx_spec))
>>> plt.ylim([1e-4, 1e1])
>>> plt.xlabel('frequency [Hz]')
>>> plt.ylabel('Linear spectrum [V RMS]')
>>> plt.show()
```



The peak height in the power spectrum is an estimate of the RMS amplitude.

```
>>> np.sqrt(Pxx_spec.max())
2.0077340678640727
```

scipy.signal.welch

`scipy.signal.welch(x, fs=1.0, window='hann', nperseg=None, noverlap=None, nfft=None, detrend='constant', return_onesided=True, scaling='density', axis=-1, average='mean')`

Estimate power spectral density using Welch's method.

Welch's method [1] computes an estimate of the power spectral density by dividing the data into overlapping segments, computing a modified periodogram for each segment and averaging the periodograms.

Parameters

x	[array_like] Time series of measurement values
fs	[float, optional] Sampling frequency of the <i>x</i> time series. Defaults to 1.0.
window	[str or tuple or array_like, optional] Desired window to use. If <i>window</i> is a string or tuple, it is passed to <code>get_window</code> to generate the window values, which are DFT-even by default. See <code>get_window</code> for a list of windows and required parameters. If <i>window</i> is array_like

it will be used directly as the window and its length must be `nperseg`. Defaults to a Hann window.

nperseg	[int, optional] Length of each segment. Defaults to <code>None</code> , but if <code>window</code> is <code>str</code> or <code>tuple</code> , is set to 256, and if <code>window</code> is <code>array_like</code> , is set to the length of the window.
noverlap	[int, optional] Number of points to overlap between segments. If <code>None</code> , <code>noverlap = nperseg // 2</code> . Defaults to <code>None</code> .
nfft	[int, optional] Length of the FFT used, if a zero padded FFT is desired. If <code>None</code> , the FFT length is <code>nperseg</code> . Defaults to <code>None</code> .
detrend	[str or function or <code>False</code> , optional] Specifies how to detrend each segment. If <code>detrend</code> is a string, it is passed as the <code>type</code> argument to the <code>detrend</code> function. If it is a function, it takes a segment and returns a detrended segment. If <code>detrend</code> is <code>False</code> , no detrending is done. Defaults to <code>'constant'</code> .
return_onesided	[bool, optional] If <code>True</code> , return a one-sided spectrum for real data. If <code>False</code> return a two-sided spectrum. Defaults to <code>True</code> , but for complex data, a two-sided spectrum is always returned.
scaling	[[<code>'density'</code> , <code>'spectrum'</code>], optional] Selects between computing the power spectral density (<code>'density'</code>) where P_{xx} has units of V^{**2}/Hz and computing the power spectrum (<code>'spectrum'</code>) where P_{xx} has units of V^{**2} , if x is measured in V and fs is measured in Hz . Defaults to <code>'density'</code>
axis	[int, optional] Axis along which the periodogram is computed; the default is over the last axis (i.e. <code>axis=-1</code>).
average	[[<code>'mean'</code> , <code>'median'</code>], optional] Method to use when averaging periodograms. Defaults to <code>'mean'</code> .

New in version 1.2.0.

Returns

f	[ndarray] Array of sample frequencies.
Pxx	[ndarray] Power spectral density or power spectrum of x .

See also:

[*periodogram*](#)

Simple, optionally modified periodogram

[*lombscargle*](#)

Lomb-Scargle periodogram for unevenly sampled data

Notes

An appropriate amount of overlap will depend on the choice of window and on your requirements. For the default Hann window an overlap of 50% is a reasonable trade off between accurately estimating the signal power, while not over counting any of the data. Narrower windows may require a larger overlap.

If `noverlap` is 0, this method is equivalent to Bartlett's method [2].

New in version 0.12.0.

References

[1], [2]

Examples


```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
>>> np.random.seed(1234)
```

Generate a test signal, a 2 Vrms sine wave at 1234 Hz, corrupted by 0.001 V**2/Hz of white noise sampled at 10 kHz.

```
>>> fs = 10e3
>>> N = 1e5
>>> amp = 2*np.sqrt(2)
>>> freq = 1234.0
>>> noise_power = 0.001 * fs / 2
>>> time = np.arange(N) / fs
>>> x = amp*np.sin(2*np.pi*freq*time)
>>> x += np.random.normal(scale=np.sqrt(noise_power), size=time.shape)
```

Compute and plot the power spectral density.

```
>>> f, Pxx_den = signal.welch(x, fs, nperseg=1024)
>>> plt.semilogy(f, Pxx_den)
>>> plt.ylim([0.5e-3, 1])
>>> plt.xlabel('frequency [Hz]')
>>> plt.ylabel('PSD [V**2/Hz]')
>>> plt.show()
```




If we average the last half of the spectral density, to exclude the peak, we can recover the noise power on the signal.

```
>>> np.mean(Pxx_den[256:])
0.0009924865443739191
```

Now compute and plot the power spectrum.

```
>>> f, Pxx_spec = signal.welch(x, fs, 'flattop', 1024, scaling='spectrum')
>>> plt.figure()
>>> plt.semilogy(f, np.sqrt(Pxx_spec))
>>> plt.xlabel('frequency [Hz]')
>>> plt.ylabel('Linear spectrum [V RMS]')
>>> plt.show()
```




The peak height in the power spectrum is an estimate of the RMS amplitude.

```
>>> np.sqrt(Pxx_spec.max())
2.0077340678640727
```

If we now introduce a discontinuity in the signal, by increasing the amplitude of a small portion of the signal by 50, we can see the corruption of the mean average power spectral density, but using a median average better estimates the normal behaviour.

```
>>> x[int(N//2):int(N//2)+10] *= 50.
>>> f, Pxx_den = signal.welch(x, fs, nperseg=1024)
>>> f_med, Pxx_den_med = signal.welch(x, fs, nperseg=1024, average='median
→')
>>> plt.semilogy(f, Pxx_den, label='mean')
>>> plt.semilogy(f_med, Pxx_den_med, label='median')
>>> plt.ylim([0.5e-3, 1])
>>> plt.xlabel('frequency [Hz]')
>>> plt.ylabel('PSD [V**2/Hz]')
>>> plt.legend()
>>> plt.show()
```

scipy.signal.csd

`scipy.signal.csd(x, y, fs=1.0, window='hann', nperseg=None, noverlap=None, nfft=None, detrend='constant', return_onesided=True, scaling='density', axis=-1, average='mean')`

Estimate the cross power spectral density, P_{xy} , using Welch's method.

Parameters

x	[array_like] Time series of measurement values
y	[array_like] Time series of measurement values
fs	[float, optional] Sampling frequency of the x and y time series. Defaults to 1.0.
window	[str or tuple or array_like, optional] Desired window to use. If <i>window</i> is a string or tuple, it is passed to <code>get_window</code> to generate the window values, which are DFT-even by default. See <code>get_window</code> for a list of windows and required parameters. If <i>window</i> is array_like it will be used directly as the window and its length must be <i>nperseg</i> . Defaults to a Hann window.
nperseg	[int, optional] Length of each segment. Defaults to <i>None</i> , but if <i>window</i> is str or tuple, is set to 256, and if <i>window</i> is array_like, is set to the length of the window.
noverlap: int, optional	Number of points to overlap between segments. If <i>None</i> , <code>noverlap = nperseg // 2</code> . Defaults to <i>None</i> .
nfft	[int, optional] Length of the FFT used, if a zero padded FFT is desired. If <i>None</i> , the FFT length is <i>nperseg</i> . Defaults to <i>None</i> .
detrend	[str or function or <i>False</i> , optional] Specifies how to detrend each segment. If <i>detrend</i> is a string, it is passed as the <i>type</i> argument to the <code>detrend</code> function. If it is a function, it takes a segment and returns a detrended segment. If <i>detrend</i> is <i>False</i> , no detrending is done. Defaults to 'constant'.
return_onesided	[bool, optional] If <i>True</i> , return a one-sided spectrum for real data. If <i>False</i> return a two-sided spectrum. Defaults to <i>True</i> , but for complex data, a two-sided spectrum is always returned.
scaling	[{ 'density', 'spectrum' }, optional] Selects between computing the cross spectral density ('density') where P_{xy} has units of V^{**2}/Hz and computing the cross spectrum ('spectrum') where P_{xy} has units of V^{**2} , if x and y are measured in V and fs is measured in Hz . Defaults to 'density'

axis [int, optional] Axis along which the CSD is computed for both inputs; the default is over the last axis (i.e. `axis=-1`).

average [{ 'mean', 'median' }, optional] Method to use when averaging periodograms. Defaults to 'mean'.
New in version 1.2.0.

Returns

f [ndarray] Array of sample frequencies.

Pxy [ndarray] Cross spectral density or cross power spectrum of x,y.

See also:

periodogram

Simple, optionally modified periodogram

lombscargle

Lomb-Scargle periodogram for unevenly sampled data

welch

Power spectral density by Welch's method. [Equivalent to `csd(x,x)`]

coherence

Magnitude squared coherence by Welch's method.

Notes

By convention, Pxy is computed with the conjugate FFT of X multiplied by the FFT of Y.

If the input series differ in length, the shorter series will be zero-padded to match.

An appropriate amount of overlap will depend on the choice of window and on your requirements. For the default Hann window an overlap of 50% is a reasonable trade off between accurately estimating the signal power, while not over counting any of the data. Narrower windows may require a larger overlap.

New in version 0.16.0.

References

[1], [2]

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

Generate two test signals with some common features.

```
>>> fs = 10e3
>>> N = 1e5
>>> amp = 20
>>> freq = 1234.0
>>> noise_power = 0.001 * fs / 2
```

(continues on next page)

(continued from previous page)

```

>>> time = np.arange(N) / fs
>>> b, a = signal.butter(2, 0.25, 'low')
>>> x = np.random.normal(scale=np.sqrt(noise_power), size=time.shape)
>>> y = signal.lfilter(b, a, x)
>>> x += amp*np.sin(2*np.pi*freq*time)
>>> y += np.random.normal(scale=0.1*np.sqrt(noise_power), size=time.shape)


```

Compute and plot the magnitude of the cross spectral density.

```

>>> f, Pxy = signal.csd(x, y, fs, nperseg=1024)
>>> plt.semilogy(f, np.abs(Pxy))
>>> plt.xlabel('frequency [Hz]')
>>> plt.ylabel('CSD [V**2/Hz]')
>>> plt.show()

```



scipy.signal.coherence

`scipy.signal.coherence` (*x*, *y*, *fs*=1.0, *window*='hann', *nperseg*=None, *noverlap*=None, *nfft*=None, *trend*='constant', *axis*=-1)

Estimate the magnitude squared coherence estimate, *Cxy*, of discrete-time signals *X* and *Y* using Welch's method.

$C_{xy} = \text{abs}(P_{xy}) ** 2 / (P_{xx} * P_{yy})$, where *Pxx* and *Pyy* are power spectral density estimates of *X* and *Y*, and *Pxy* is the cross spectral density estimate of *X* and *Y*.

Parameters

- x** [array_like] Time series of measurement values
- y** [array_like] Time series of measurement values
- fs** [float, optional] Sampling frequency of the *x* and *y* time series. Defaults to 1.0.
- window** [str or tuple or array_like, optional] Desired window to use. If *window* is a string or tuple, it is passed to `get_window` to generate the window values, which are DFT-even by default. See `get_window` for a list of windows and required parameters. If *window* is array_like it will be used directly as the window and its length must be *nperseg*. Defaults to a Hann window.

- nperseg** [int, optional] Length of each segment. Defaults to *None*, but if *window* is str or tuple, is set to 256, and if *window* is array_like, is set to the length of the window.
- noverlap: int, optional**
Number of points to overlap between segments. If *None*, `noverlap = nperseg // 2`. Defaults to *None*.
- nfft** [int, optional] Length of the FFT used, if a zero padded FFT is desired. If *None*, the FFT length is *nperseg*. Defaults to *None*.
- detrend** [str or function or *False*, optional] Specifies how to detrend each segment. If *detrend* is a string, it is passed as the *type* argument to the *detrend* function. If it is a function, it takes a segment and returns a detrended segment. If *detrend* is *False*, no detrending is done. Defaults to 'constant'.
- axis** [int, optional] Axis along which the coherence is computed for both inputs; the default is over the last axis (i.e. `axis=-1`).

Returns

- f** [ndarray] Array of sample frequencies.
- Cxy** [ndarray] Magnitude squared coherence of x and y.

See also:

periodogram

Simple, optionally modified periodogram

lombscargle

Lomb-Scargle periodogram for unevenly sampled data

welch

Power spectral density by Welch's method.

csd

Cross spectral density by Welch's method.

Notes

An appropriate amount of overlap will depend on the choice of window and on your requirements. For the default Hann window an overlap of 50% is a reasonable trade off between accurately estimating the signal power, while not over counting any of the data. Narrower windows may require a larger overlap.

New in version 0.16.0.

References

- [1], [2]

Examples


```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

Generate two test signals with some common features.

```
>>> fs = 10e3
>>> N = 1e5
>>> amp = 20
>>> freq = 1234.0
>>> noise_power = 0.001 * fs / 2
>>> time = np.arange(N) / fs
>>> b, a = signal.butter(2, 0.25, 'low')
>>> x = np.random.normal(scale=np.sqrt(noise_power), size=time.shape)
>>> y = signal.lfilter(b, a, x)
>>> x += amp*np.sin(2*np.pi*freq*time)
>>> y += np.random.normal(scale=0.1*np.sqrt(noise_power), size=time.shape)
```

Compute and plot the coherence.

```
>>> f, Cxy = signal.coherence(x, y, fs, nperseg=1024)
>>> plt.semilogy(f, Cxy)
>>> plt.xlabel('frequency [Hz]')
>>> plt.ylabel('Coherence')
>>> plt.show()
```



scipy.signal.spectrogram

```
scipy.signal.spectrogram(x, fs=1.0, window='tukey', 0.25, nperseg=None, noverlap=None, nfft=None,
                        detrend='constant', return_onesided=True, scaling='density', axis=-1,
                        mode='psd')
```

Compute a spectrogram with consecutive Fourier transforms.

Spectrograms can be used as a way of visualizing the change of a nonstationary signal's frequency content over time.

Parameters

x	[array_like] Time series of measurement values
fs	[float, optional] Sampling frequency of the <i>x</i> time series. Defaults to 1.0.
window	[str or tuple or array_like, optional] Desired window to use. If <i>window</i> is a string or tuple, it is passed to <code>get_window</code> to generate the window values, which are DFT-even by default. See <code>get_window</code> for a list of windows and required parameters. If <i>window</i> is array_like it will be used directly as the window and its length must be <i>nperseg</i> . Defaults to a Tukey window with shape parameter of 0.25.
nperseg	[int, optional] Length of each segment. Defaults to None, but if window is str or tuple, is set to 256, and if window is array_like, is set to the length of the window.
noverlap	[int, optional] Number of points to overlap between segments. If None, <code>noverlap = nperseg // 8</code> . Defaults to None.
nfft	[int, optional] Length of the FFT used, if a zero padded FFT is desired. If None, the FFT length is <i>nperseg</i> . Defaults to None.
detrend	[str or function or False, optional] Specifies how to detrend each segment. If <i>detrend</i> is a string, it is passed as the <i>type</i> argument to the <code>detrend</code> function. If it is a function, it takes a segment and returns a detrended segment. If <i>detrend</i> is False, no detrending is done. Defaults to 'constant'.
return_onesided	[bool, optional] If True, return a one-sided spectrum for real data. If False return a two-sided spectrum. Defaults to True, but for complex data, a two-sided spectrum is always returned.
scaling	[{ 'density', 'spectrum' }, optional] Selects between computing the power spectral density ('density') where <i>Sxx</i> has units of V**2/Hz and computing the power spectrum ('spectrum') where <i>Sxx</i> has units of V**2, if <i>x</i> is measured in V and <i>fs</i> is measured in Hz. Defaults to 'density'.
axis	[int, optional] Axis along which the spectrogram is computed; the default is over the last axis (i.e. <code>axis=-1</code>).
mode	[str, optional] Defines what kind of return values are expected. Options are ['psd', 'complex', 'magnitude', 'angle', 'phase']. 'complex' is equivalent to the output of <code>stft</code> with no padding or boundary extension. 'magnitude' returns the absolute magnitude of the STFT. 'angle' and 'phase' return the complex angle of the STFT, with and without unwrapping, respectively.

Returns

f	[ndarray] Array of sample frequencies.
t	[ndarray] Array of segment times.
Sxx	[ndarray] Spectrogram of <i>x</i> . By default, the last axis of <i>Sxx</i> corresponds to the segment times.

See also:

[`periodogram`](#)

Simple, optionally modified periodogram

[`lombscargle`](#)

Lomb-Scargle periodogram for unevenly sampled data

welch

Power spectral density by Welch's method.

csd

Cross spectral density by Welch's method.

Notes

An appropriate amount of overlap will depend on the choice of window and on your requirements. In contrast to `welch`'s method, where the entire data stream is averaged over, one may wish to use a smaller overlap (or perhaps none at all) when computing a spectrogram, to maintain some statistical independence between individual segments. It is for this reason that the default window is a Tukey window with 1/8th of a window's length overlap at each end.

New in version 0.16.0.

References

[1]

Examples

```
>>> from scipy import signal
>>> from scipy.fft import fftshift
>>> import matplotlib.pyplot as plt
```


Generate a test signal, a 2 Vrms sine wave whose frequency is slowly modulated around 3kHz, corrupted by white noise of exponentially decreasing magnitude sampled at 10 kHz.

```
>>> fs = 10e3
>>> N = 1e5
>>> amp = 2 * np.sqrt(2)
>>> noise_power = 0.01 * fs / 2
>>> time = np.arange(N) / float(fs)
>>> mod = 500*np.cos(2*np.pi*0.25*time)
>>> carrier = amp * np.sin(2*np.pi*3e3*time + mod)
>>> noise = np.random.normal(scale=np.sqrt(noise_power), size=time.shape)
>>> noise *= np.exp(-time/5)
>>> x = carrier + noise
```


Compute and plot the spectrogram.

```
>>> f, t, Sxx = signal.spectrogram(x, fs)
>>> plt.pcolormesh(t, f, Sxx, shading='gouraud')
>>> plt.ylabel('Frequency [Hz]')
>>> plt.xlabel('Time [sec]')
>>> plt.show()
```

Note, if using output that is not one sided, then use the following:



```
>>> f, t, Sxx = signal.spectrogram(x, fs, return_onesided=False)
>>> plt.pcolormesh(t, fftshift(f), fftshift(Sxx, axes=0), shading='gouraud
↳')
>>> plt.ylabel('Frequency [Hz]')
>>> plt.xlabel('Time [sec]')
>>> plt.show()
```



scipy.signal.lombscargle

`scipy.signal.lombscargle(x, y, freqs)`

Computes the Lomb-Scargle periodogram.

The Lomb-Scargle periodogram was developed by Lomb [1] and further extended by Scargle [2] to find, and test the significance of weak periodic signals with uneven temporal sampling.

When *normalize* is False (default) the computed periodogram is unnormalized, it takes the value $(A^{**2}) * N/4$ for a harmonic signal with amplitude A for sufficiently large N.

When *normalize* is True the computed periodogram is normalized by the residuals of the data around a constant reference model (at zero).

Input arrays should be 1-D and will be cast to float64.

Parameters

x	[array_like] Sample times.
y	[array_like] Measurement values.
freqs	[array_like] Angular frequencies for output periodogram.
precenter	[bool, optional] Pre-center measurement values by subtracting the mean.
normalize	[bool, optional] Compute normalized periodogram.

Returns

pgram [array_like] Lomb-Scargle periodogram.

Raises

ValueError
If the input arrays *x* and *y* do not have the same shape.

See also:***istft***

Inverse Short Time Fourier Transform

check_COLA

Check whether the Constant OverLap Add (COLA) constraint is met

welch

Power spectral density by Welch's method

spectrogram

Spectrogram by Welch's method

csd

Cross spectral density by Welch's method

Notes

This subroutine calculates the periodogram using a slightly modified algorithm due to Townsend [3] which allows the periodogram to be calculated using only a single pass through the input arrays for each frequency.

The algorithm running time scales roughly as $O(x * \text{freqs})$ or $O(N^2)$ for a large number of samples and frequencies.

References

[1], [2], [3]

Examples

```
>>> import matplotlib.pyplot as plt
```

First define some input parameters for the signal:

```
>>> A = 2.
>>> w = 1.
>>> phi = 0.5 * np.pi
>>> nin = 1000
>>> nout = 100000
>>> frac_points = 0.9 # Fraction of points to select
```

Randomly select a fraction of an array with timesteps:

```
>>> r = np.random.rand(nin)
>>> x = np.linspace(0.01, 10*np.pi, nin)
>>> x = x[r >= frac_points]
```

Plot a sine wave for the selected times:

```
>>> y = A * np.sin(w*x+phi)
```

Define the array of frequencies for which to compute the periodogram:

```
>>> f = np.linspace(0.01, 10, nout)
```

Calculate Lomb-Scargle periodogram:


```
>>> import scipy.signal as signal
>>> pgram = signal.lombscargle(x, y, f, normalize=True)
```

Now make a plot of the input data:

```
>>> plt.subplot(2, 1, 1)
>>> plt.plot(x, y, 'b+')
```

Then plot the normalized periodogram:

```
>>> plt.subplot(2, 1, 2)
>>> plt.plot(f, pgram)
>>> plt.show()
```



scipy.signal.vectorstrength

`scipy.signal.vectorstrength(events, period)`

Determine the vector strength of the events corresponding to the given period.

The vector strength is a measure of phase synchrony, how well the timing of the events is synchronized to a single period of a periodic signal.

If multiple periods are used, calculate the vector strength of each. This is called the “resonating vector strength”.

Parameters

- events** [1D array_like] An array of time points containing the timing of the events.
- period** [float or array_like] The period of the signal that the events should synchronize to. The period is in the same units as *events*. It can also be an array of periods, in which case the outputs are arrays of the same length.

Returns

- strength** [float or 1D array] The strength of the synchronization. 1.0 is perfect synchronization and 0.0 is no synchronization. If *period* is an array, this is also an array with each element containing the vector strength at the corresponding period.
- phase** [float or array] The phase that the events are most strongly synchronized to in radians. If *period* is an array, this is also an array with each element containing the phase for the corresponding period.

References

van Hemmen, JL, Longtin, A, and Vollmayr, AN. Testing resonating vector

strength: Auditory system, electric fish, and noise. Chaos 21, 047508 (2011); DOI:10.1063/1.3670512.

van Hemmen, JL. Vector strength after Goldberg, Brown, and von Mises:

biological and mathematical perspectives. Biol Cybern. 2013 Aug;107(4):385-96. DOI:10.1007/s00422-013-0561-7.

van Hemmen, JL and Vollmayr, AN. Resonating vector strength: what happens

when we vary the “probing” frequency while keeping the spike times fixed. Biol Cybern. 2013 Aug;107(4):491-94. DOI:10.1007/s00422-013-0560-8.

scipy.signal.stft

`scipy.signal.stft(x, fs=1.0, window='hann', nperseg=256, noverlap=None, nfft=None, detrend=False, return_onesided=True, boundary='zeros', padded=True, axis=-1)`

Compute the Short Time Fourier Transform (STFT).

STFTs can be used as a way of quantifying the change of a nonstationary signal’s frequency and phase content over time.

Parameters

x	[array_like] Time series of measurement values
fs	[float, optional] Sampling frequency of the <i>x</i> time series. Defaults to 1.0.
window	[str or tuple or array_like, optional] Desired window to use. If <i>window</i> is a string or tuple, it is passed to <code>get_window</code> to generate the window values, which are DFT-even by default. See <code>get_window</code> for a list of windows and required parameters. If <i>window</i> is array_like it will be used directly as the window and its length must be <i>nperseg</i> . Defaults to a Hann window.
nperseg	[int, optional] Length of each segment. Defaults to 256.
noverlap	[int, optional] Number of points to overlap between segments. If <i>None</i> , <code>noverlap = nperseg // 2</code> . Defaults to <i>None</i> . When specified, the COLA constraint must be met (see Notes below).
nfft	[int, optional] Length of the FFT used, if a zero padded FFT is desired. If <i>None</i> , the FFT length is <i>nperseg</i> . Defaults to <i>None</i> .
detrend	[str or function or <i>False</i> , optional] Specifies how to detrend each segment. If <i>detrend</i> is a string, it is passed as the <i>type</i> argument to the <code>detrend</code> function. If it is a function, it takes a segment and returns a detrended segment. If <i>detrend</i> is <i>False</i> , no detrending is done. Defaults to <i>False</i> .
return_onesided	[bool, optional] If <i>True</i> , return a one-sided spectrum for real data. If <i>False</i> return a two-sided spectrum. Defaults to <i>True</i> , but for complex data, a two-sided spectrum is always returned.
boundary	[str or <i>None</i> , optional] Specifies whether the input signal is extended at both ends, and how to generate the new values, in order to center the first windowed segment on the first input point. This has the benefit of enabling reconstruction of the first input point when the employed window function starts at zero. Valid options are [<i>'even'</i> , <i>'odd'</i> , <i>'constant'</i> , <i>'zeros'</i> , <i>None</i>]. Defaults to <i>'zeros'</i> , for zero padding extension. I.e. [1, 2, 3, 4] is extended to [0, 1, 2, 3, 4, 0] for <i>nperseg</i> =3.
padded	[bool, optional] Specifies whether the input signal is zero-padded at the end to make the signal fit exactly into an integer number of window segments, so that all of the signal is included in the output. Defaults to <i>True</i> . Padding occurs after boundary extension, if <i>boundary</i> is not <i>None</i> , and <i>padded</i> is <i>True</i> , as is the default.
axis	[int, optional] Axis along which the STFT is computed; the default is over the last axis (i.e. <code>axis=-1</code>).

Returns

f	[ndarray] Array of sample frequencies.
t	[ndarray] Array of segment times.
Zxx	[ndarray] STFT of <i>x</i> . By default, the last axis of <i>Zxx</i> corresponds to the segment times.

See also:

istft

Inverse Short Time Fourier Transform

check_COLA

Check whether the Constant OverLap Add (COLA) constraint is met

check_NOLA

Check whether the Nonzero Overlap Add (NOLA) constraint is met

welch

Power spectral density by Welch's method.

spectrogram

Spectrogram by Welch's method.

csd

Cross spectral density by Welch's method.

lombscargle

Lomb-Scargle periodogram for unevenly sampled data

Notes

In order to enable inversion of an STFT via the inverse STFT in *istft*, the signal windowing must obey the constraint of “Nonzero OverLap Add” (NOLA), and the input signal must have complete windowing coverage (i.e. $(x.shape[axis] - nperseg) \% (nperseg - noverlap) == 0$). The *padded* argument may be used to accomplish this.

Given a time-domain signal $x[n]$, a window $w[n]$, and a hop size $H = nperseg - noverlap$, the windowed frame at time index t is given by

$$x_t[n] = x[n]w[n - tH]$$

The overlap-add (OLA) reconstruction equation is given by

$$x[n] = \frac{\sum_t x_t[n]w[n - tH]}{\sum_t w^2[n - tH]}$$

The NOLA constraint ensures that every normalization term that appears in the denominator of the OLA reconstruction equation is nonzero. Whether a choice of *window*, *nperseg*, and *noverlap* satisfy this constraint can be tested with *check_NOLA*.

New in version 0.19.0.

References

[1], [2]

Examples


```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

Generate a test signal, a 2 Vrms sine wave whose frequency is slowly modulated around 3kHz, corrupted by white noise of exponentially decreasing magnitude sampled at 10 kHz.

```
>>> fs = 10e3
>>> N = 1e5
>>> amp = 2 * np.sqrt(2)
>>> noise_power = 0.01 * fs / 2
>>> time = np.arange(N) / float(fs)
>>> mod = 500*np.cos(2*np.pi*0.25*time)
>>> carrier = amp * np.sin(2*np.pi*3e3*time + mod)
>>> noise = np.random.normal(scale=np.sqrt(noise_power),
...                          size=time.shape)
>>> noise *= np.exp(-time/5)
>>> x = carrier + noise
```

Compute and plot the STFT's magnitude.

```
>>> f, t, Zxx = signal.stft(x, fs, nperseg=1000)
>>> plt.pcolormesh(t, f, np.abs(Zxx), vmin=0, vmax=amp, shading='gouraud')
>>> plt.title('STFT Magnitude')
>>> plt.ylabel('Frequency [Hz]')
>>> plt.xlabel('Time [sec]')
>>> plt.show()
```



scipy.signal.istft

`scipy.signal.istft` (*Zxx*, *fs=1.0*, *window='hann'*, *nperseg=None*, *noverlap=None*, *nfft=None*, *input_onesided=True*, *boundary=True*, *time_axis=-1*, *freq_axis=-2*)

Perform the inverse Short Time Fourier transform (iSTFT).

Parameters

Zxx	[array_like] STFT of the signal to be reconstructed. If a purely real array is passed, it will be cast to a complex data type.
fs	[float, optional] Sampling frequency of the time series. Defaults to 1.0.
window	[str or tuple or array_like, optional] Desired window to use. If <i>window</i> is a string or tuple, it is passed to <code>get_window</code> to generate the window values, which are DFT-even by default. See <code>get_window</code> for a list of windows and required parameters. If <i>window</i> is array_like it will be used directly as the window and its length must be <i>nperseg</i> . Defaults to a Hann window. Must match the window used to generate the STFT for faithful inversion.
nperseg	[int, optional] Number of data points corresponding to each STFT segment. This parameter must be specified if the number of data points per segment is odd, or if the STFT was padded via <code>nfft > nperseg</code> . If <i>None</i> , the value depends on the shape of <i>Zxx</i> and <i>input_onesided</i> . If <i>input_onesided</i> is <i>True</i> , <code>nperseg=2*(Zxx.shape[freq_axis] - 1)</code> . Otherwise, <code>nperseg=Zxx.shape[freq_axis]</code> . Defaults to <i>None</i> .
noverlap	[int, optional] Number of points to overlap between segments. If <i>None</i> , half of the segment length. Defaults to <i>None</i> . When specified, the COLA constraint must be met (see Notes below), and should match the parameter used to generate the STFT. Defaults to <i>None</i> .
nfft	[int, optional] Number of FFT points corresponding to each STFT segment. This parameter must be specified if the STFT was padded via <code>nfft > nperseg</code> . If <i>None</i> , the default values are the same as for <i>nperseg</i> , detailed above, with one exception: if <i>input_onesided</i> is <i>True</i> and <code>nperseg==2*Zxx.shape[freq_axis] - 1</code> , <i>nfft</i> also takes on that value. This case allows the proper inversion of an odd-length unpadded STFT using <code>nfft=None</code> . Defaults to <i>None</i> .
input_onesided	[bool, optional] If <i>True</i> , interpret the input array as one-sided FFTs, such as is returned by <code>stft</code> with <code>return_onesided=True</code> and <code>numpy.fft.rfft</code> . If <i>False</i> , interpret the input as a two-sided FFT. Defaults to <i>True</i> .
boundary	[bool, optional] Specifies whether the input signal was extended at its boundaries by supplying a non- <i>None</i> <i>boundary</i> argument to <code>stft</code> . Defaults to <i>True</i> .
time_axis	[int, optional] Where the time segments of the STFT is located; the default is the last axis (i.e. <code>axis=-1</code>).
freq_axis	[int, optional] Where the frequency axis of the STFT is located; the default is the penultimate axis (i.e. <code>axis=-2</code>).

Returns

t	[ndarray] Array of output data times.
x	[ndarray] iSTFT of <i>Zxx</i> .

See also:

`stft`

Short Time Fourier Transform

`check_COLA`

Check whether the Constant OverLap Add (COLA) constraint is met

`check_NOLA`

Check whether the Nonzero Overlap Add (NOLA) constraint is met

Notes

In order to enable inversion of an STFT via the inverse STFT with `istft`, the signal windowing must obey the constraint of “nonzero overlap add” (NOLA):

$$\sum_t w^2[n - tH] \neq 0$$

This ensures that the normalization factors that appear in the denominator of the overlap-add reconstruction equation

$$x[n] = \frac{\sum_t x_t[n]w[n - tH]}{\sum_t w^2[n - tH]}$$

are not zero. The NOLA constraint can be checked with the `check_NOLA` function.

An STFT which has been modified (via masking or otherwise) is not guaranteed to correspond to a exactly realizable signal. This function implements the iSTFT via the least-squares estimation algorithm detailed in [2], which produces a signal that minimizes the mean squared error between the STFT of the returned signal and the modified STFT.

New in version 0.19.0.

References

[1], [2]

Examples

```
>>> from scipy import signal
>>> import matplotlib.pyplot as plt
```

Generate a test signal, a 2 Vrms sine wave at 50Hz corrupted by 0.001 V**2/Hz of white noise sampled at 1024 Hz.

```
>>> fs = 1024
>>> N = 10*fs
>>> nperseg = 512
>>> amp = 2 * np.sqrt(2)
>>> noise_power = 0.001 * fs / 2
>>> time = np.arange(N) / float(fs)
>>> carrier = amp * np.sin(2*np.pi*50*time)
>>> noise = np.random.normal(scale=np.sqrt(noise_power),
...                          size=time.shape)
>>> x = carrier + noise
```

Compute the STFT, and plot its magnitude

```
>>> f, t, Zxx = signal.stft(x, fs=fs, nperseg=nperseg)
>>> plt.figure()
>>> plt.pcolormesh(t, f, np.abs(Zxx), vmin=0, vmax=amp, shading='gouraud')
>>> plt.ylim([f[1], f[-1]])
>>> plt.title('STFT Magnitude')
>>> plt.ylabel('Frequency [Hz]')
```


(continues on next page)

(continued from previous page)

```

>>> plt.xlabel('Time [sec]')
>>> plt.yscale('log')
>>> plt.show()

```



Zero the components that are 10% or less of the carrier magnitude, then convert back to a time series via inverse STFT

```

>>> Zxx = np.where(np.abs(Zxx) >= amp/10, Zxx, 0)
>>> _, xrec = signal.istft(Zxx, fs)

```

Compare the cleaned signal with the original and true carrier signals.

```

>>> plt.figure()
>>> plt.plot(time, x, time, xrec, time, carrier)
>>> plt.xlim([2, 2.1])
>>> plt.xlabel('Time [sec]')
>>> plt.ylabel('Signal')
>>> plt.legend(['Carrier + Noise', 'Filtered via STFT', 'True Carrier'])
>>> plt.show()



```

Note that the cleaned signal does not start as abruptly as the original, since some of the coefficients of the transient were also removed:

```

>>> plt.figure()
>>> plt.plot(time, x, time, xrec, time, carrier)
>>> plt.xlim([0, 0.1])
>>> plt.xlabel('Time [sec]')
>>> plt.ylabel('Signal')
>>> plt.legend(['Carrier + Noise', 'Filtered via STFT', 'True Carrier'])
>>> plt.show()

```



scipy.signal.check_COLA

`scipy.signal.check_COLA(window, nperseg, noverlap, tol=1e-10)`

Check whether the Constant OverLap Add (COLA) constraint is met

Parameters

- window** [str or tuple or array_like] Desired window to use. If *window* is a string or tuple, it is passed to `get_window` to generate the window values, which are DFT-even by default. See `get_window` for a list of windows and required parameters. If *window* is array_like it will be used directly as the window and its length must be `nperseg`.
- nperseg** [int] Length of each segment.
- noverlap** [int] Number of points to overlap between segments.
- tol** [float, optional] The allowed variance of a bin's weighted sum from the median bin sum.

Returns

- verdict** [bool] *True* if chosen combination satisfies COLA within *tol*, *False* otherwise

See also:

`check_NOLA`

Check whether the Nonzero Overlap Add (NOLA) constraint is met

`stft`

Short Time Fourier Transform

`istft`

Inverse Short Time Fourier Transform

Notes

In order to enable inversion of an STFT via the inverse STFT in `istft`, it is sufficient that the signal windowing obeys the constraint of “Constant OverLap Add” (COLA). This ensures that every point in the input data is equally weighted, thereby avoiding aliasing and allowing full reconstruction.

Some examples of windows that satisfy COLA:

- Rectangular window at overlap of 0, 1/2, 2/3, 3/4, ...
- Bartlett window at overlap of 1/2, 3/4, 5/6, ...
- Hann window at 1/2, 2/3, 3/4, ...
- Any Blackman family window at 2/3 overlap
- Any window with `noverlap = nperseg-1`

A very comprehensive list of other windows may be found in [2], wherein the COLA condition is satisfied when the “Amplitude Flatness” is unity.

New in version 0.19.0.

References

[1], [2]

Examples

```
>>> from scipy import signal
```

Confirm COLA condition for rectangular window of 75% (3/4) overlap:

```
>>> signal.check_COLA(signal.windows.boxcar(100), 100, 75)
True
```

COLA is not true for 25% (1/4) overlap, though:

```
>>> signal.check_COLA(signal.windows.boxcar(100), 100, 25)
False
```

“Symmetrical” Hann window (for filter design) is not COLA:

```
>>> signal.check_COLA(signal.windows.hann(120, sym=True), 120, 60)
False
```

“Periodic” or “DFT-even” Hann window (for FFT analysis) is COLA for overlap of 1/2, 2/3, 3/4, etc.:

```
>>> signal.check_COLA(signal.windows.hann(120, sym=False), 120, 60)
True
```

```
>>> signal.check_COLA(signal.windows.hann(120, sym=False), 120, 80)
True
```

```
>>> signal.check_COLA(signal.windows.hann(120, sym=False), 120, 90)
True
```

scipy.signal.check_NOLA

`scipy.signal.check_NOLA` (*window*, *nperseg*, *noverlap*, *tol=1e-10*)

Check whether the Nonzero Overlap Add (NOLA) constraint is met

Parameters

window	[str or tuple or array_like] Desired window to use. If <i>window</i> is a string or tuple, it is passed to <code>get_window</code> to generate the window values, which are DFT-even by default. See <code>get_window</code> for a list of windows and required parameters. If <i>window</i> is array_like it will be used directly as the window and its length must be <i>nperseg</i> .
nperseg	[int] Length of each segment.
noverlap	[int] Number of points to overlap between segments.
tol	[float, optional] The allowed variance of a bin’s weighted sum from the median bin sum.

Returns

verdict [bool] *True* if chosen combination satisfies the NOLA constraint within *tol*, *False* otherwise

See also:

check_COLA

Check whether the Constant OverLap Add (COLA) constraint is met

stft

Short Time Fourier Transform

istft

Inverse Short Time Fourier Transform

Notes

In order to enable inversion of an STFT via the inverse STFT in *istft*, the signal windowing must obey the constraint of “nonzero overlap add” (NOLA):

$$\sum_t w^2[n - tH] \neq 0$$

for all n , where w is the window function, t is the frame index, and H is the hop size ($H = nperseg - noverlap$).

This ensures that the normalization factors in the denominator of the overlap-add inversion equation are not zero. Only very pathological windows will fail the NOLA constraint.

New in version 1.2.0.

References

[1], [2]

Examples

```
>>> from scipy import signal
```

Confirm NOLA condition for rectangular window of 75% (3/4) overlap:

```
>>> signal.check_NOLA(signal.windows.boxcar(100), 100, 75)
True
```

NOLA is also true for 25% (1/4) overlap:

```
>>> signal.check_NOLA(signal.windows.boxcar(100), 100, 25)
True
```

“Symmetrical” Hann window (for filter design) is also NOLA:

```
>>> signal.check_NOLA(signal.windows.hann(120, sym=True), 120, 60)
True
```

As long as there is overlap, it takes quite a pathological window to fail NOLA:

```
>>> w = np.ones(64, dtype="float")
>>> w[::2] = 0
>>> signal.check_NOLA(w, 64, 32)
False
```

If there is not enough overlap, a window with zeros at the ends will not work:

```
>>> signal.check_NOLA(signal.windows.hann(64), 64, 0)
False
>>> signal.check_NOLA(signal.windows.hann(64), 64, 1)
False
>>> signal.check_NOLA(signal.windows.hann(64), 64, 2)
True
```

6.23 Sparse matrices (`scipy.sparse`)

SciPy 2-D sparse matrix package for numeric data.

6.23.1 Contents

Sparse matrix classes

<code>bsr_matrix</code> (arg1[, shape, dtype, copy, blocksize])	Block Sparse Row matrix
<code>coo_matrix</code> (arg1[, shape, dtype, copy])	A sparse matrix in COOrdinate format.
<code>csc_matrix</code> (arg1[, shape, dtype, copy])	Compressed Sparse Column matrix
<code>csr_matrix</code> (arg1[, shape, dtype, copy])	Compressed Sparse Row matrix
<code>dia_matrix</code> (arg1[, shape, dtype, copy])	Sparse matrix with DIAgonal storage
<code>dok_matrix</code> (arg1[, shape, dtype, copy])	Dictionary Of Keys based sparse matrix.
<code>lil_matrix</code> (arg1[, shape, dtype, copy])	Row-based list of lists sparse matrix
<code>spmatrix</code> ([maxprint])	This class provides a base class for all sparse matrices.

`scipy.sparse.bsr_matrix`

class `scipy.sparse.bsr_matrix` (*arg1, shape=None, dtype=None, copy=False, blocksize=None*)

Block Sparse Row matrix

This can be instantiated in several ways:

`bsr_matrix(D, [blocksize=(R,C)])`

where D is a dense matrix or 2-D ndarray.

`bsr_matrix(S, [blocksize=(R,C)])`

with another sparse matrix S (equivalent to `S.tobsr()`)

`bsr_matrix((M, N), [blocksize=(R,C), dtype])`

to construct an empty matrix with shape (M, N) dtype is optional, defaulting to dtype='d'.

`bsr_matrix((data, ij), [blocksize=(R,C), shape=(M, N)])`

where data and ij satisfy `a[ij[0, k], ij[1, k]] = data[k]`

`bsr_matrix((data, indices, indptr), [shape=(M, N)])`

is the standard BSR representation where the block column indices for row i are stored in `indices[indptr[i]:indptr[i+1]]` and their corresponding block values are stored in `data[indptr[i]:indptr[i+1]]`. If the shape parameter is not supplied, the matrix dimensions are inferred from the index arrays.

Notes

Sparse matrices can be used in arithmetic operations: they support addition, subtraction, multiplication, division, and matrix power.

Summary of BSR format

The Block Compressed Row (BSR) format is very similar to the Compressed Sparse Row (CSR) format. BSR is appropriate for sparse matrices with dense sub matrices like the last example below. Block matrices often arise in vector-valued finite element discretizations. In such cases, BSR is considerably more efficient than CSR and CSC for many sparse arithmetic operations.

Blocksize

The blocksize (R,C) must evenly divide the shape of the matrix (M,N). That is, R and C must satisfy the relationship $M \% R = 0$ and $N \% C = 0$.

If no blocksize is specified, a simple heuristic is applied to determine an appropriate blocksize.

Examples

```
>>> from scipy.sparse import bsr_matrix
>>> bsr_matrix((3, 4), dtype=np.int8).toarray()
array([[0, 0, 0, 0],
       [0, 0, 0, 0],
       [0, 0, 0, 0]], dtype=int8)
```

```
>>> row = np.array([0, 0, 1, 2, 2, 2])
>>> col = np.array([0, 2, 2, 0, 1, 2])
>>> data = np.array([1, 2, 3, 4, 5, 6])
>>> bsr_matrix((data, (row, col)), shape=(3, 3)).toarray()
array([[1, 0, 2],
       [0, 0, 3],
       [4, 5, 6]])
```

```
>>> indptr = np.array([0, 2, 3, 6])
>>> indices = np.array([0, 2, 2, 0, 1, 2])
>>> data = np.array([1, 2, 3, 4, 5, 6]).repeat(4).reshape(6, 2, 2)
>>> bsr_matrix((data, indices, indptr), shape=(6, 6)).toarray()
array([[1, 1, 0, 0, 2, 2],
       [1, 1, 0, 0, 2, 2],
       [0, 0, 0, 0, 3, 3],
       [0, 0, 0, 0, 3, 3],
       [4, 4, 5, 5, 6, 6],
       [4, 4, 5, 5, 6, 6]])
```

Attributes

dtype	[dtype] Data type of the matrix
shape	[2-tuple] Get shape of a matrix.
ndim	[int] Number of dimensions (this is always 2)
nnz	Number of stored values, including explicit zeros.
data	Data array of the matrix
indices	BSR format index array
indptr	BSR format index pointer array

blocksize Block size of the matrix
has_sorted_indices
 Determine whether the matrix has sorted indices

Methods

<code>__len__(self)</code>	
<code>__mul__(self, other)</code>	interpret other and call one of the following
<code>arcsin(self)</code>	Element-wise arcsin.
<code>arcsinh(self)</code>	Element-wise arcsinh.
<code>arctan(self)</code>	Element-wise arctan.
<code>arctanh(self)</code>	Element-wise arctanh.
<code>argmax(self[, axis, out])</code>	Return indices of maximum elements along an axis.
<code>argmin(self[, axis, out])</code>	Return indices of minimum elements along an axis.
<code>asformat(self, format[, copy])</code>	Return this matrix in the passed format.
<code>asfptype(self)</code>	Upcast matrix to a floating point format (if necessary)
<code>astype(self, dtype[, casting, copy])</code>	Cast the matrix elements to a specified type.
<code>ceil(self)</code>	Element-wise ceil.
<code>check_format(self[, full_check])</code>	check whether the matrix format is valid
<code>conj(self[, copy])</code>	Element-wise complex conjugation.
<code>conjugate(self[, copy])</code>	Element-wise complex conjugation.
<code>copy(self)</code>	Returns a copy of this matrix.
<code>count_nonzero(self)</code>	Number of non-zero entries, equivalent to
<code>deg2rad(self)</code>	Element-wise deg2rad.
<code>diagonal(self[, k])</code>	Returns the kth diagonal of the matrix.
<code>dot(self, other)</code>	Ordinary dot product
<code>eliminate_zeros(self)</code>	Remove zero elements in-place.
<code>expm1(self)</code>	Element-wise expm1.
<code>floor(self)</code>	Element-wise floor.
<code>getH(self)</code>	Return the Hermitian transpose of this matrix.
<code>get_shape(self)</code>	Get shape of a matrix.
<code>getcol(self, j)</code>	Returns a copy of column j of the matrix, as an (m x 1) sparse matrix (column vector).
<code>getformat(self)</code>	Format of a matrix representation as a string.
<code>getmaxprint(self)</code>	Maximum number of elements to display when printed.
<code>getnnz(self[, axis])</code>	Number of stored values, including explicit zeros.
<code>getrow(self, i)</code>	Returns a copy of row i of the matrix, as a (1 x n) sparse matrix (row vector).
<code>log1p(self)</code>	Element-wise log1p.
<code>matmat(*args, **kwds)</code>	<i>matmat</i> is deprecated! BSR matmat is deprecated in SciPy 0.19.0.
<code>matvec(*args, **kwds)</code>	<i>matvec</i> is deprecated! BSR matvec is deprecated in SciPy 0.19.0.
<code>max(self[, axis, out])</code>	Return the maximum of the matrix or maximum along an axis.
<code>maximum(self, other)</code>	Element-wise maximum between this and another matrix.
<code>mean(self[, axis, dtype, out])</code>	Compute the arithmetic mean along the specified axis.

continues on next page

Table 173 – continued from previous page

<code>min(self[, axis, out])</code>	Return the minimum of the matrix or maximum along an axis.
<code>minimum(self, other)</code>	Element-wise minimum between this and another matrix.
<code>multiply(self, other)</code>	Point-wise multiplication by another matrix, vector, or scalar.
<code>nonzero(self)</code>	nonzero indices
<code>power(self, n[, dtype])</code>	This function performs element-wise power.
<code>prune(self)</code>	Remove empty space after all non-zero elements.
<code>rad2deg(self)</code>	Element-wise rad2deg.
<code>reshape(self, shape[, order, copy])</code>	Gives a new shape to a sparse matrix without changing its data.
<code>resize(self, *shape)</code>	Resize the matrix in-place to dimensions given by shape
<code>rint(self)</code>	Element-wise rint.
<code>set_shape(self, shape)</code>	See <code>reshape</code> .
<code>setdiag(self, values[, k])</code>	Set diagonal or off-diagonal elements of the array.
<code>sign(self)</code>	Element-wise sign.
<code>sin(self)</code>	Element-wise sin.
<code>sinh(self)</code>	Element-wise sinh.
<code>sort_indices(self)</code>	Sort the indices of this matrix <i>in place</i>
<code>sorted_indices(self)</code>	Return a copy of this matrix with sorted indices
<code>sqrt(self)</code>	Element-wise sqrt.
<code>sum(self[, axis, dtype, out])</code>	Sum the matrix elements over a given axis.
<code>sum_duplicates(self)</code>	Eliminate duplicate matrix entries by adding them together
<code>tan(self)</code>	Element-wise tan.
<code>tanh(self)</code>	Element-wise tanh.
<code>toarray(self[, order, out])</code>	Return a dense ndarray representation of this matrix.
<code>tobsr(self[, blocksize, copy])</code>	Convert this matrix into Block Sparse Row Format.
<code>tocoo(self[, copy])</code>	Convert this matrix to COOrdinate format.
<code>tocsc(self[, copy])</code>	Convert this matrix to Compressed Sparse Column format.
<code>tocsr(self[, copy])</code>	Convert this matrix to Compressed Sparse Row format.
<code>todense(self[, order, out])</code>	Return a dense matrix representation of this matrix.
<code>todia(self[, copy])</code>	Convert this matrix to sparse DIAgonal format.
<code>todok(self[, copy])</code>	Convert this matrix to Dictionary Of Keys format.
<code>tolil(self[, copy])</code>	Convert this matrix to List of Lists format.
<code>transpose(self[, axes, copy])</code>	Reverses the dimensions of the sparse matrix.
<code>trunc(self)</code>	Element-wise trunc.

`scipy.sparse.bsr_matrix.__len__`

`bsr_matrix.__len__` (*self*)

`scipy.sparse.bsr_matrix.__mul__`

`bsr_matrix.__mul__` (*self*, *other*)

interpret other and call one of the following

`self._mul_scalar()` `self._mul_vector()` `self._mul_multivector()` `self._mul_sparse_matrix()`

`scipy.sparse.bsr_matrix.arcsin`

`bsr_matrix.arcsin` (*self*)

Element-wise arcsin.

See `numpy.arcsin` for more information.

`scipy.sparse.bsr_matrix.arcsinh`

`bsr_matrix.arcsinh` (*self*)

Element-wise arcsinh.

See `numpy.arcsinh` for more information.

`scipy.sparse.bsr_matrix.arctan`

`bsr_matrix.arctan` (*self*)

Element-wise arctan.

See `numpy.arctan` for more information.

`scipy.sparse.bsr_matrix.arctanh`

`bsr_matrix.arctanh` (*self*)

Element-wise arctanh.

See `numpy.arctanh` for more information.

`scipy.sparse.bsr_matrix.argmax`

`bsr_matrix.argmax` (*self*, *axis=None*, *out=None*)

Return indices of maximum elements along an axis.

Implicit zero elements are also taken into account. If there are several maximum values, the index of the first occurrence is returned.

Parameters

axis `[{-2, -1, 0, 1, None}, optional]` Axis along which the argmax is computed. If None (default), index of the maximum element in the flatten data is returned.

out [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

ind [numpy.matrix or int] Indices of maximum elements. If matrix, its size along *axis* is 1.

scipy.sparse.bsr_matrix.argmax

`bsr_matrix.argmax` (*self*, *axis=None*, *out=None*)

Return indices of minimum elements along an axis.

Implicit zero elements are also taken into account. If there are several minimum values, the index of the first occurrence is returned.

Parameters

axis [{-2, -1, 0, 1, None}, optional] Axis along which the argmin is computed. If None (default), index of the minimum element in the flatten data is returned.

out [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

ind [numpy.matrix or int] Indices of minimum elements. If matrix, its size along *axis* is 1.

scipy.sparse.bsr_matrix.asformat

`bsr_matrix.asformat` (*self*, *format*, *copy=False*)

Return this matrix in the passed format.

Parameters

format [{str, None}] The desired matrix format (“csr”, “csc”, “lil”, “dok”, “array”, ...) or None for no conversion.

copy [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

A [This matrix in the passed format.]

scipy.sparse.bsr_matrix.asfptype

`bsr_matrix.asfptype` (*self*)

Upcast matrix to a floating point format (if necessary)

scipy.sparse.bsr_matrix.astype

`bsr_matrix.astype` (*self*, *dtype*, *casting='unsafe'*, *copy=True*)

Cast the matrix elements to a specified type.

Parameters

dtype	[string or numpy dtype] Typecode or data-type to which to cast the data.
casting	[{'no', 'equiv', 'safe', 'same_kind', 'unsafe'}, optional] Controls what kind of data casting may occur. Defaults to 'unsafe' for backwards compatibility. 'no' means the data types should not be cast at all. 'equiv' means only byte-order changes are allowed. 'safe' means only casts which can preserve values are allowed. 'same_kind' means only safe casts or casts within a kind, like float64 to float32, are allowed. 'unsafe' means any data conversions may be done.
copy	[bool, optional] If <i>copy</i> is <i>False</i> , the result might share some memory with this matrix. If <i>copy</i> is <i>True</i> , it is guaranteed that the result and this matrix do not share any memory.

scipy.sparse.bsr_matrix.ceil

`bsr_matrix.ceil` (*self*)

Element-wise ceil.

See `numpy.ceil` for more information.

scipy.sparse.bsr_matrix.check_format

`bsr_matrix.check_format` (*self*, *full_check=True*)

check whether the matrix format is valid

Parameters:**full_check:**

True - rigorous check, O(N) operations : default False - basic check, O(1) operations

scipy.sparse.bsr_matrix.conj

`bsr_matrix.conj` (*self*, *copy=True*)

Element-wise complex conjugation.

If the matrix is of non-complex data type and *copy* is *False*, this method does nothing and the data is not copied.

Parameters

copy [bool, optional] If *True*, the result is guaranteed to not share data with self.

Returns

A [The element-wise complex conjugate.]

scipy.sparse.bsr_matrix.conjugate`bsr_matrix.conjugate` (*self*, *copy=True*)

Element-wise complex conjugation.

If the matrix is of non-complex data type and *copy* is `False`, this method does nothing and the data is not copied.

Parameters

copy [bool, optional] If `True`, the result is guaranteed to not share data with *self*.

Returns

A [The element-wise complex conjugate.]

scipy.sparse.bsr_matrix.copy`bsr_matrix.copy` (*self*)

Returns a copy of this matrix.

No data/indices will be shared between the returned value and current matrix.

scipy.sparse.bsr_matrix.count_nonzero`bsr_matrix.count_nonzero` (*self*)

Number of non-zero entries, equivalent to

`np.count_nonzero(a.toarray())`

Unlike `getnnz()` and the `nnz` property, which return the number of stored entries (the length of the data attribute), this method counts the actual number of non-zero entries in data.

scipy.sparse.bsr_matrix.deg2rad`bsr_matrix.deg2rad` (*self*)Element-wise `deg2rad`.

See `numpy.deg2rad` for more information.

scipy.sparse.bsr_matrix.diagonal`bsr_matrix.diagonal` (*self*, *k=0*)Returns the *k*th diagonal of the matrix.**Parameters**

k [int, optional] Which diagonal to get, corresponding to elements `a[i, i+k]`. Default: 0 (the main diagonal).
New in version 1.0.

See also:*numpy.diagonal*

Equivalent `numpy` function.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> A.diagonal()
array([1, 0, 5])
>>> A.diagonal(k=1)
array([2, 3])
```

scipy.sparse.bsr_matrix.dot

`bsr_matrix.dot` (*self*, *other*)
Ordinary dot product

Examples

```
>>> import numpy as np
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> v = np.array([1, 0, -1])
>>> A.dot(v)
array([ 1, -3, -1], dtype=int64)
```

scipy.sparse.bsr_matrix.eliminate_zeros

`bsr_matrix.eliminate_zeros` (*self*)
Remove zero elements in-place.

scipy.sparse.bsr_matrix.expm1

`bsr_matrix.expm1` (*self*)
Element-wise `expm1`.
See `numpy.expm1` for more information.

scipy.sparse.bsr_matrix.floor

`bsr_matrix.floor` (*self*)
Element-wise floor.
See `numpy.floor` for more information.

scipy.sparse.bsr_matrix.getH`bsr_matrix.getH(self)`

Return the Hermitian transpose of this matrix.

See also:*numpy.matrix.getH*NumPy's implementation of *getH* for matrices**scipy.sparse.bsr_matrix.get_shape**`bsr_matrix.get_shape(self)`

Get shape of a matrix.

scipy.sparse.bsr_matrix.getcol`bsr_matrix.getcol(self, j)`Returns a copy of column *j* of the matrix, as an (*m* x 1) sparse matrix (column vector).**scipy.sparse.bsr_matrix.getformat**`bsr_matrix.getformat(self)`

Format of a matrix representation as a string.

scipy.sparse.bsr_matrix.getmaxprint`bsr_matrix.getmaxprint(self)`

Maximum number of elements to display when printed.

scipy.sparse.bsr_matrix.getnnz`bsr_matrix.getnnz(self, axis=None)`

Number of stored values, including explicit zeros.

Parameters

axis	[None, 0, or 1] Select between the number of values across the whole matrix, in each column, or in each row.
-------------	--

See also:*count_nonzero*

Number of non-zero entries

scipy.sparse.bsr_matrix.getrow

`bsr_matrix.getrow` (*self*, *i*)

Returns a copy of row *i* of the matrix, as a (1 x n) sparse matrix (row vector).

scipy.sparse.bsr_matrix.log1p

`bsr_matrix.log1p` (*self*)

Element-wise log1p.

See `numpy.log1p` for more information.

scipy.sparse.bsr_matrix.matmat

`bsr_matrix.matmat` (**args*, ***kwargs*)

matmat is deprecated! BSR matmat is deprecated in SciPy 0.19.0. Use `*` operator instead.

Multiply this sparse matrix by other matrix.

scipy.sparse.bsr_matrix.matvec

`bsr_matrix.matvec` (**args*, ***kwargs*)

matvec is deprecated! BSR matvec is deprecated in SciPy 0.19.0. Use `*` operator instead.

Multiply matrix by vector.

scipy.sparse.bsr_matrix.max

`bsr_matrix.max` (*self*, *axis=None*, *out=None*)

Return the maximum of the matrix or maximum along an axis. This takes all elements into account, not just the non-zero ones.

Parameters

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the maximum over all the matrix elements, returning a scalar (i.e., *axis = None*).
- out** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

- amax** [`coo_matrix` or scalar] Maximum of *a*. If *axis* is None, the result is a scalar value. If *axis* is given, the result is a `sparse.coo_matrix` of dimension `a.ndim - 1`.

See also:

`min`

The minimum value of a sparse matrix along a given axis.

`numpy.matrix.max`

NumPy's implementation of 'max' for matrices

scipy.sparse.bsr_matrix.maximum`bsr_matrix.maximum(self, other)`

Element-wise maximum between this and another matrix.

scipy.sparse.bsr_matrix.mean`bsr_matrix.mean(self, axis=None, dtype=None, out=None)`

Compute the arithmetic mean along the specified axis.

Returns the average of the matrix elements. The average is taken over all elements in the matrix by default, otherwise over the specified axis. *float64* intermediate and return values are used for integer inputs.**Parameters**

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the mean is computed. The default is to compute the mean of all elements in the matrix (i.e., *axis = None*).
- dtype** [data-type, optional] Type to use in computing the mean. For integer inputs, the default is *float64*; for floating point inputs, it is the same as the input dtype. New in version 0.18.0.
- out** [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary. New in version 0.18.0.

Returns

- m** [np.matrix]

See also:[*numpy.matrix.mean*](#)

NumPy's implementation of 'mean' for matrices

scipy.sparse.bsr_matrix.min`bsr_matrix.min(self, axis=None, out=None)`

Return the minimum of the matrix or maximum along an axis. This takes all elements into account, not just the non-zero ones.

Parameters

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the minimum over all the matrix elements, returning a scalar (i.e., *axis = None*).
- out** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

- amin** [coo_matrix or scalar] Minimum of *a*. If *axis* is None, the result is a scalar value. If *axis* is given, the result is a sparse.coo_matrix of dimension `a.ndim - 1`.

See also:

max

The maximum value of a sparse matrix along a given axis.

numpy.matrix.min

NumPy's implementation of 'min' for matrices

scipy.sparse.bsr_matrix.minimum

`bsr_matrix.minimum(self, other)`

Element-wise minimum between this and another matrix.

scipy.sparse.bsr_matrix.multiply

`bsr_matrix.multiply(self, other)`

Point-wise multiplication by another matrix, vector, or scalar.

scipy.sparse.bsr_matrix.nonzero

`bsr_matrix.nonzero(self)`

nonzero indices

Returns a tuple of arrays (row,col) containing the indices of the non-zero elements of the matrix.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1,2,0],[0,0,3],[4,0,5]])
>>> A.nonzero()
(array([0, 0, 1, 2, 2]), array([0, 1, 2, 0, 2]))
```

scipy.sparse.bsr_matrix.power

`bsr_matrix.power(self, n, dtype=None)`

This function performs element-wise power.

Parameters

- n** [n is a scalar]
- dtype** [If dtype is not specified, the current dtype will be preserved.]

scipy.sparse.bsr_matrix.prune`bsr_matrix.prune` (*self*)

Remove empty space after all non-zero elements.

scipy.sparse.bsr_matrix.rad2deg`bsr_matrix.rad2deg` (*self*)

Element-wise rad2deg.

See `numpy.rad2deg` for more information.**scipy.sparse.bsr_matrix.reshape**`bsr_matrix.reshape` (*self*, *shape*, *order='C'*, *copy=False*)

Gives a new shape to a sparse matrix without changing its data.

Parameters

shape	[length-2 tuple of ints] The new shape should be compatible with the original shape.
order	[{'C', 'F'}, optional] Read the elements using this index order. 'C' means to read and write the elements using C-like index order; e.g., read entire first row, then second row, etc. 'F' means to read and write the elements using Fortran-like index order; e.g., read entire first column, then second column, etc.
copy	[bool, optional] Indicates whether or not attributes of self should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns**reshaped_matrix**[sparse matrix] A sparse matrix with the given `shape`, not necessarily of the same format as the current object.**See also:**`numpy.matrix.reshape`

NumPy's implementation of 'reshape' for matrices

scipy.sparse.bsr_matrix.resize`bsr_matrix.resize` (*self*, **shape*)Resize the matrix in-place to dimensions given by `shape`

Any elements that lie within the new shape will remain at the same indices, while non-zero elements lying outside the new shape are removed.

Parameters

shape	[(int, int)] number of rows and columns in the new matrix
--------------	---

Notes

The semantics are not identical to `numpy.ndarray.resize` or `numpy.resize`. Here, the same data will be maintained at each index before and after reshape, if that index is within the new bounds. In `numpy`, resizing maintains contiguity of the array, moving elements around in the logical matrix but not within a flattened representation.

We give no guarantees about whether the underlying data attributes (arrays, etc.) will be modified in place or replaced with new objects.

`scipy.sparse.bsr_matrix.rint`

`bsr_matrix.rint` (*self*)

Element-wise rint.

See `numpy.rint` for more information.

`scipy.sparse.bsr_matrix.set_shape`

`bsr_matrix.set_shape` (*self*, *shape*)

See `reshape`.

`scipy.sparse.bsr_matrix.setdiag`

`bsr_matrix.setdiag` (*self*, *values*, *k=0*)

Set diagonal or off-diagonal elements of the array.

Parameters

- | | |
|---------------|---|
| values | [array_like] New values of the diagonal elements.
Values may have any length. If the diagonal is longer than values, then the remaining diagonal entries will not be set. If values are longer than the diagonal, then the remaining values are ignored. |
| k | [int, optional] Which off-diagonal to set, corresponding to elements <code>a[i,i+k]</code> . Default: 0 (the main diagonal). |

`scipy.sparse.bsr_matrix.sign`

`bsr_matrix.sign` (*self*)

Element-wise sign.

See `numpy.sign` for more information.

scipy.sparse.bsr_matrix.sin`bsr_matrix.sin(self)`

Element-wise sin.

See `numpy.sin` for more information.**scipy.sparse.bsr_matrix.sinh**`bsr_matrix.sinh(self)`

Element-wise sinh.

See `numpy.sinh` for more information.**scipy.sparse.bsr_matrix.sort_indices**`bsr_matrix.sort_indices(self)`Sort the indices of this matrix *in place***scipy.sparse.bsr_matrix.sorted_indices**`bsr_matrix.sorted_indices(self)`

Return a copy of this matrix with sorted indices

scipy.sparse.bsr_matrix.sqrt`bsr_matrix.sqrt(self)`

Element-wise sqrt.

See `numpy.sqrt` for more information.**scipy.sparse.bsr_matrix.sum**`bsr_matrix.sum(self, axis=None, dtype=None, out=None)`

Sum the matrix elements over a given axis.

Parameters

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the sum of all the matrix elements, returning a scalar (i.e., *axis = None*).
- dtype** [dtype, optional] The type of the returned matrix and of the accumulator in which the elements are summed. The dtype of *a* is used by default unless *a* has an integer dtype of less precision than the default platform integer. In that case, if *a* is signed then the platform integer is used while if *a* is unsigned then an unsigned integer of the same precision as the platform integer is used.
New in version 0.18.0.
- out** [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns

sum_along_axis

[np.matrix] A matrix with the same shape as *self*, with the specified axis removed.

See also:

`numpy.matrix.sum`

NumPy's implementation of 'sum' for matrices

scipy.sparse.bsr_matrix.sum_duplicates

`bsr_matrix.sum_duplicates` (*self*)

Eliminate duplicate matrix entries by adding them together

The is an *in place* operation

scipy.sparse.bsr_matrix.tan

`bsr_matrix.tan` (*self*)

Element-wise tan.

See `numpy.tan` for more information.

scipy.sparse.bsr_matrix.tanh

`bsr_matrix.tanh` (*self*)

Element-wise tanh.

See `numpy.tanh` for more information.

scipy.sparse.bsr_matrix.toarray

`bsr_matrix.toarray` (*self*, *order=None*, *out=None*)

Return a dense ndarray representation of this matrix.

Parameters

- order** [{"C", "F"}, optional] Whether to store multidimensional data in C (row-major) or Fortran (column-major) order in memory. The default is 'None', indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the *out* argument.
- out** [ndarray, 2-D, optional] If specified, uses this array as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method. For most sparse types, *out* is required to be memory contiguous (either C or Fortran ordered).

Returns

- arr** [ndarray, 2-D] An array with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If *out* was passed, the same object is returned after being modified in-place to contain the appropriate values.

scipy.sparse.bsr_matrix.tobsr

`bsr_matrix.tobsr` (*self*, *blocksize=None*, *copy=False*)

Convert this matrix into Block Sparse Row Format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `bsr_matrix`.

If *blocksize=(R, C)* is provided, it will be used for determining block size of the `bsr_matrix`.

scipy.sparse.bsr_matrix.tocoo

`bsr_matrix.tocoo` (*self*, *copy=True*)

Convert this matrix to COOrdinate format.

When *copy=False* the data array will be shared between this matrix and the resultant `coo_matrix`.

scipy.sparse.bsr_matrix.tocsc

`bsr_matrix.tocsc` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Column format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `csc_matrix`.

scipy.sparse.bsr_matrix.tocsr

`bsr_matrix.tocsr` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Row format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `csr_matrix`.

scipy.sparse.bsr_matrix.todense

`bsr_matrix.todense` (*self*, *order=None*, *out=None*)

Return a dense matrix representation of this matrix.

Parameters

- order** [{"C", "F"}, optional] Whether to store multi-dimensional data in C (row-major) or Fortran (column-major) order in memory. The default is 'None', indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the *out* argument.
- out** [ndarray, 2-D, optional] If specified, uses this array (or `numpy.matrix`) as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method.

Returns

- arr** [numpy.matrix, 2-D] A NumPy matrix object with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If *out* was passed and was an array (rather than a `numpy.matrix`), it will be filled with the appropriate values and returned wrapped in a `numpy.matrix` object that shares the same memory.

scipy.sparse.bsr_matrix.todia

`bsr_matrix.todia` (*self*, *copy=False*)

Convert this matrix to sparse DIAgonal format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dia_matrix`.

scipy.sparse.bsr_matrix.todok

`bsr_matrix.todok` (*self*, *copy=False*)

Convert this matrix to Dictionary Of Keys format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dok_matrix`.

scipy.sparse.bsr_matrix.tolil

`bsr_matrix.tolil` (*self*, *copy=False*)

Convert this matrix to List of Lists format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `lil_matrix`.

scipy.sparse.bsr_matrix.transpose

`bsr_matrix.transpose` (*self*, *axes=None*, *copy=False*)

Reverses the dimensions of the sparse matrix.

Parameters

- axes** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value.
- copy** [bool, optional] Indicates whether or not attributes of *self* should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns

- p** [*self* with the dimensions reversed.]

See also:

[*numpy.matrix.transpose*](#)

NumPy's implementation of 'transpose' for matrices

scipy.sparse.bsr_matrix.trunc

`bsr_matrix.trunc` (*self*)

Element-wise trunc.

See [`numpy.trunc`](#) for more information.

<code>__getitem__</code>	
--------------------------	--

scipy.sparse.coo_matrix

class `scipy.sparse.coo_matrix` (*arg1*, *shape=None*, *dtype=None*, *copy=False*)

A sparse matrix in COOrdinate format.

Also known as the ‘ijv’ or ‘triplet’ format.

This can be instantiated in several ways:

coo_matrix(D)

with a dense matrix D

coo_matrix(S)

with another sparse matrix S (equivalent to `S.tocoo()`)

coo_matrix((M, N), [dtype])

to construct an empty matrix with shape (M, N) dtype is optional, defaulting to `dtype='d'`.

coo_matrix((data, (i, j)), [shape=(M, N)])

to construct from three arrays:

1. `data[:]` the entries of the matrix, in any order
2. `i[:]` the row indices of the matrix entries
3. `j[:]` the column indices of the matrix entries

Where $A[i[k], j[k]] = data[k]$. When shape is not specified, it is inferred from the index arrays

Notes

Sparse matrices can be used in arithmetic operations: they support addition, subtraction, multiplication, division, and matrix power.

Advantages of the COO format

- facilitates fast conversion among sparse formats
- permits duplicate entries (see example)
- very fast conversion to and from CSR/CSC formats

Disadvantages of the COO format

- **does not directly support:**
 - arithmetic operations
 - slicing

Intended Usage

- COO is a fast format for constructing sparse matrices
- Once a matrix has been constructed, convert to CSR or CSC format for fast arithmetic and matrix vector operations

- By default when converting to CSR or CSC format, duplicate (i,j) entries will be summed together. This facilitates efficient construction of finite element matrices and the like. (see example)

Examples

```
>>> # Constructing an empty matrix
>>> from scipy.sparse import coo_matrix
>>> coo_matrix((3, 4), dtype=np.int8).toarray()
array([[0, 0, 0, 0],
       [0, 0, 0, 0],
       [0, 0, 0, 0]], dtype=int8)
```

```
>>> # Constructing a matrix using ijv format
>>> row = np.array([0, 3, 1, 0])
>>> col = np.array([0, 3, 1, 2])
>>> data = np.array([4, 5, 7, 9])
>>> coo_matrix((data, (row, col)), shape=(4, 4)).toarray()
array([[4, 0, 9, 0],
       [0, 7, 0, 0],
       [0, 0, 0, 0],
       [0, 0, 0, 5]])
```

```
>>> # Constructing a matrix with duplicate indices
>>> row = np.array([0, 0, 1, 3, 1, 0, 0])
>>> col = np.array([0, 2, 1, 3, 1, 0, 0])
>>> data = np.array([1, 1, 1, 1, 1, 1, 1])
>>> coo = coo_matrix((data, (row, col)), shape=(4, 4))
>>> # Duplicate indices are maintained until implicitly or explicitly
    → summed
>>> np.max(coo.data)
1
>>> coo.toarray()
array([[3, 0, 1, 0],
       [0, 2, 0, 0],
       [0, 0, 0, 0],
       [0, 0, 0, 1]])
```

Attributes

dtype	[dtype] Data type of the matrix
shape	[2-tuple] Get shape of a matrix.
ndim	[int] Number of dimensions (this is always 2)
nnz	Number of stored values, including explicit zeros.
data	COO format data array of the matrix
row	COO format row index array of the matrix
col	COO format column index array of the matrix

Methods

<code>__len__(self)</code>	
<code>__mul__(self, other)</code>	interpret other and call one of the following
<code>arcsin(self)</code>	Element-wise arcsin.
<code>arcsinh(self)</code>	Element-wise arcsinh.
<code>arctan(self)</code>	Element-wise arctan.
<code>arctanh(self)</code>	Element-wise arctanh.
<code>argmax(self[, axis, out])</code>	Return indices of maximum elements along an axis.
<code>argmin(self[, axis, out])</code>	Return indices of minimum elements along an axis.
<code>asformat(self, format[, copy])</code>	Return this matrix in the passed format.
<code>asfptype(self)</code>	Upcast matrix to a floating point format (if necessary)
<code>astype(self, dtype[, casting, copy])</code>	Cast the matrix elements to a specified type.
<code>ceil(self)</code>	Element-wise ceil.
<code>conj(self[, copy])</code>	Element-wise complex conjugation.
<code>conjugate(self[, copy])</code>	Element-wise complex conjugation.
<code>copy(self)</code>	Returns a copy of this matrix.
<code>count_nonzero(self)</code>	Number of non-zero entries, equivalent to
<code>deg2rad(self)</code>	Element-wise deg2rad.
<code>diagonal(self[, k])</code>	Returns the kth diagonal of the matrix.
<code>dot(self, other)</code>	Ordinary dot product
<code>eliminate_zeros(self)</code>	Remove zero entries from the matrix
<code>expm1(self)</code>	Element-wise expm1.
<code>floor(self)</code>	Element-wise floor.
<code>getH(self)</code>	Return the Hermitian transpose of this matrix.
<code>get_shape(self)</code>	Get shape of a matrix.
<code>getcol(self, j)</code>	Returns a copy of column j of the matrix, as an (m x 1) sparse matrix (column vector).
<code>getformat(self)</code>	Format of a matrix representation as a string.
<code>getmaxprint(self)</code>	Maximum number of elements to display when printed.
<code>getnnz(self[, axis])</code>	Number of stored values, including explicit zeros.
<code>getrow(self, i)</code>	Returns a copy of row i of the matrix, as a (1 x n) sparse matrix (row vector).
<code>log1p(self)</code>	Element-wise log1p.
<code>max(self[, axis, out])</code>	Return the maximum of the matrix or maximum along an axis.
<code>maximum(self, other)</code>	Element-wise maximum between this and another matrix.
<code>mean(self[, axis, dtype, out])</code>	Compute the arithmetic mean along the specified axis.
<code>min(self[, axis, out])</code>	Return the minimum of the matrix or maximum along an axis.
<code>minimum(self, other)</code>	Element-wise minimum between this and another matrix.
<code>multiply(self, other)</code>	Point-wise multiplication by another matrix
<code>nonzero(self)</code>	nonzero indices
<code>power(self, n[, dtype])</code>	This function performs element-wise power.
<code>rad2deg(self)</code>	Element-wise rad2deg.
<code>reshape(self, shape[, order, copy])</code>	Gives a new shape to a sparse matrix without changing its data.

continues on next page

Table 174 – continued from previous page

<code>resize(self, *shape)</code>	Resize the matrix in-place to dimensions given by <code>shape</code>
<code>rint(self)</code>	Element-wise <code>rint</code> .
<code>set_shape(self, shape)</code>	See <code>reshape</code> .
<code>setdiag(self, values[, k])</code>	Set diagonal or off-diagonal elements of the array.
<code>sign(self)</code>	Element-wise <code>sign</code> .
<code>sin(self)</code>	Element-wise <code>sin</code> .
<code>sinh(self)</code>	Element-wise <code>sinh</code> .
<code>sqrt(self)</code>	Element-wise <code>sqrt</code> .
<code>sum(self[, axis, dtype, out])</code>	Sum the matrix elements over a given axis.
<code>sum_duplicates(self)</code>	Eliminate duplicate matrix entries by adding them together
<code>tan(self)</code>	Element-wise <code>tan</code> .
<code>tanh(self)</code>	Element-wise <code>tanh</code> .
<code>toarray(self[, order, out])</code>	See the docstring for <code>spmatrix.toarray</code> .
<code>tobsr(self[, blocksize, copy])</code>	Convert this matrix to Block Sparse Row format.
<code>tocoo(self[, copy])</code>	Convert this matrix to COOrdinate format.
<code>tocsc(self[, copy])</code>	Convert this matrix to Compressed Sparse Column format
<code>tocsr(self[, copy])</code>	Convert this matrix to Compressed Sparse Row format
<code>todense(self[, order, out])</code>	Return a dense matrix representation of this matrix.
<code>todia(self[, copy])</code>	Convert this matrix to sparse DIAgonal format.
<code>todok(self[, copy])</code>	Convert this matrix to Dictionary Of Keys format.
<code>tolil(self[, copy])</code>	Convert this matrix to List of Lists format.
<code>transpose(self[, axes, copy])</code>	Reverses the dimensions of the sparse matrix.
<code>trunc(self)</code>	Element-wise <code>trunc</code> .

scipy.sparse.coo_matrix.__len__

`coo_matrix.__len__(self)`

scipy.sparse.coo_matrix.__mul__

`coo_matrix.__mul__(self, other)`

interpret `other` and call one of the following

`self._mul_scalar()` `self._mul_vector()` `self._mul_multivector()` `self._mul_sparse_matrix()`

scipy.sparse.coo_matrix.arcsin

`coo_matrix.arcsin(self)`

Element-wise `arcsin`.

See `numpy.arcsin` for more information.

scipy.sparse.coo_matrix.arcsinh`coo_matrix.arcsinh` (*self*)

Element-wise arcsinh.

See `numpy.arcsinh` for more information.**scipy.sparse.coo_matrix.arctan**`coo_matrix.arctan` (*self*)

Element-wise arctan.

See `numpy.arctan` for more information.**scipy.sparse.coo_matrix.arctanh**`coo_matrix.arctanh` (*self*)

Element-wise arctanh.

See `numpy.arctanh` for more information.**scipy.sparse.coo_matrix.argmax**`coo_matrix.argmax` (*self*, *axis=None*, *out=None*)

Return indices of maximum elements along an axis.

Implicit zero elements are also taken into account. If there are several maximum values, the index of the first occurrence is returned.

Parameters

- axis** `[{-2, -1, 0, 1, None}, optional]` Axis along which the argmax is computed. If None (default), index of the maximum element in the flatten data is returned.
- out** `[None, optional]` This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

- ind** `[numpy.matrix or int]` Indices of maximum elements. If matrix, its size along *axis* is 1.

scipy.sparse.coo_matrix.argmin`coo_matrix.argmin` (*self*, *axis=None*, *out=None*)

Return indices of minimum elements along an axis.

Implicit zero elements are also taken into account. If there are several minimum values, the index of the first occurrence is returned.

Parameters

- axis** `[{-2, -1, 0, 1, None}, optional]` Axis along which the argmin is computed. If None (default), index of the minimum element in the flatten data is returned.
- out** `[None, optional]` This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

ind [numpy.matrix or int] Indices of minimum elements. If matrix, its size along *axis* is 1.

scipy.sparse.coo_matrix.asformat

`coo_matrix.asformat` (*self*, *format*, *copy=False*)

Return this matrix in the passed format.

Parameters

format [{str, None}] The desired matrix format (“csr”, “csc”, “lil”, “dok”, “array”, ...) or None for no conversion.
copy [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

A [This matrix in the passed format.]

scipy.sparse.coo_matrix.asfptype

`coo_matrix.asfptype` (*self*)

Upcast matrix to a floating point format (if necessary)

scipy.sparse.coo_matrix.astype

`coo_matrix.astype` (*self*, *dtype*, *casting='unsafe'*, *copy=True*)

Cast the matrix elements to a specified type.

Parameters

dtype [string or numpy dtype] Typecode or data-type to which to cast the data.
casting [{‘no’, ‘equiv’, ‘safe’, ‘same_kind’, ‘unsafe’}, optional] Controls what kind of data casting may occur. Defaults to ‘unsafe’ for backwards compatibility. ‘no’ means the data types should not be cast at all. ‘equiv’ means only byte-order changes are allowed. ‘safe’ means only casts which can preserve values are allowed. ‘same_kind’ means only safe casts or casts within a kind, like float64 to float32, are allowed. ‘unsafe’ means any data conversions may be done.
copy [bool, optional] If *copy* is *False*, the result might share some memory with this matrix. If *copy* is *True*, it is guaranteed that the result and this matrix do not share any memory.

scipy.sparse.coo_matrix.ceil

`coo_matrix.ceil` (*self*)

Element-wise ceil.

See `numpy.ceil` for more information.

scipy.sparse.coo_matrix.conj`coo_matrix.conj` (*self*, *copy=True*)

Element-wise complex conjugation.

If the matrix is of non-complex data type and *copy* is False, this method does nothing and the data is not copied.

Parameters

copy [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

A [The element-wise complex conjugate.]

scipy.sparse.coo_matrix.conjugate`coo_matrix.conjugate` (*self*, *copy=True*)

Element-wise complex conjugation.

If the matrix is of non-complex data type and *copy* is False, this method does nothing and the data is not copied.

Parameters

copy [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

A [The element-wise complex conjugate.]

scipy.sparse.coo_matrix.copy`coo_matrix.copy` (*self*)

Returns a copy of this matrix.

No data/indices will be shared between the returned value and current matrix.

scipy.sparse.coo_matrix.count_nonzero`coo_matrix.count_nonzero` (*self*)

Number of non-zero entries, equivalent to

`np.count_nonzero(a.toarray())`

Unlike `getnnz()` and the `nnz` property, which return the number of stored entries (the length of the data attribute), this method counts the actual number of non-zero entries in data.

scipy.sparse.coo_matrix.deg2rad`coo_matrix.deg2rad` (*self*)

Element-wise deg2rad.

See `numpy.deg2rad` for more information.**scipy.sparse.coo_matrix.diagonal**`coo_matrix.diagonal` (*self*, *k=0*)

Returns the kth diagonal of the matrix.

Parameters

k [int, optional] Which diagonal to get, corresponding to elements $a[i, i+k]$. Default: 0 (the main diagonal).
New in version 1.0.

See also:*numpy.diagonal*

Equivalent numpy function.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> A.diagonal()
array([1, 0, 5])
>>> A.diagonal(k=1)
array([2, 3])
```

scipy.sparse.coo_matrix.dot`coo_matrix.dot` (*self*, *other*)

Ordinary dot product

Examples

```
>>> import numpy as np
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> v = np.array([1, 0, -1])
>>> A.dot(v)
array([ 1, -3, -1], dtype=int64)
```


`scipy.sparse.coo_matrix.eliminate_zeros`

`coo_matrix.eliminate_zeros` (*self*)

Remove zero entries from the matrix

This is an *in place* operation

`scipy.sparse.coo_matrix.expm1`

`coo_matrix.expm1` (*self*)

Element-wise `expm1`.

See `numpy.expm1` for more information.

`scipy.sparse.coo_matrix.floor`

`coo_matrix.floor` (*self*)

Element-wise floor.

See `numpy.floor` for more information.

`scipy.sparse.coo_matrix.getH`

`coo_matrix.getH` (*self*)

Return the Hermitian transpose of this matrix.

See also:

`numpy.matrix.getH`

NumPy's implementation of `getH` for matrices

`scipy.sparse.coo_matrix.get_shape`

`coo_matrix.get_shape` (*self*)

Get shape of a matrix.

`scipy.sparse.coo_matrix.getcol`

`coo_matrix.getcol` (*self*, *j*)

Returns a copy of column *j* of the matrix, as an (*m* x 1) sparse matrix (column vector).

scipy.sparse.coo_matrix.getformat

`coo_matrix.getformat` (*self*)
Format of a matrix representation as a string.

scipy.sparse.coo_matrix.getmaxprint

`coo_matrix.getmaxprint` (*self*)
Maximum number of elements to display when printed.

scipy.sparse.coo_matrix.getnnz

`coo_matrix.getnnz` (*self*, *axis=None*)
Number of stored values, including explicit zeros.

Parameters

axis [None, 0, or 1] Select between the number of values across the whole matrix, in each column, or in each row.

See also:**`count_nonzero`**

Number of non-zero entries

scipy.sparse.coo_matrix.getrow

`coo_matrix.getrow` (*self*, *i*)
Returns a copy of row *i* of the matrix, as a (1 x n) sparse matrix (row vector).

scipy.sparse.coo_matrix.log1p

`coo_matrix.log1p` (*self*)
Element-wise log1p.
See `numpy.log1p` for more information.

scipy.sparse.coo_matrix.max

`coo_matrix.max` (*self*, *axis=None*, *out=None*)
Return the maximum of the matrix or maximum along an axis. This takes all elements into account, not just the non-zero ones.

Parameters

axis [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the maximum over all the matrix elements, returning a scalar (i.e., *axis = None*).

out [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

amax [coo_matrix or scalar] Maximum of *a*. If *axis* is None, the result is a scalar value. If *axis* is given, the result is a sparse.coo_matrix of dimension `a.ndim - 1`.

See also:*min*

The minimum value of a sparse matrix along a given axis.

numpy.matrix.max

NumPy's implementation of 'max' for matrices

scipy.sparse.coo_matrix.maximum

`coo_matrix.maximum` (*self*, *other*)

Element-wise maximum between this and another matrix.

scipy.sparse.coo_matrix.mean

`coo_matrix.mean` (*self*, *axis=None*, *dtype=None*, *out=None*)

Compute the arithmetic mean along the specified axis.

Returns the average of the matrix elements. The average is taken over all elements in the matrix by default, otherwise over the specified axis. *float64* intermediate and return values are used for integer inputs.

Parameters

axis [{-2, -1, 0, 1, None} optional] Axis along which the mean is computed. The default is to compute the mean of all elements in the matrix (i.e., *axis = None*).

dtype [data-type, optional] Type to use in computing the mean. For integer inputs, the default is *float64*; for floating point inputs, it is the same as the input dtype.
New in version 0.18.0.

out [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns

m [np.matrix]

See also:*numpy.matrix.mean*

NumPy's implementation of 'mean' for matrices

scipy.sparse.coo_matrix.min

`coo_matrix.min` (*self*, *axis=None*, *out=None*)

Return the minimum of the matrix or maximum along an axis. This takes all elements into account, not just the non-zero ones.

Parameters

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the minimum over all the matrix elements, returning a scalar (i.e., *axis = None*).
- out** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

- amin** [coo_matrix or scalar] Minimum of *a*. If *axis* is None, the result is a scalar value. If *axis* is given, the result is a `sparse.coo_matrix` of dimension `a.ndim - 1`.

See also:

max

The maximum value of a sparse matrix along a given axis.

numpy.matrix.min

NumPy's implementation of 'min' for matrices

scipy.sparse.coo_matrix.minimum

`coo_matrix.minimum` (*self*, *other*)

Element-wise minimum between this and another matrix.

scipy.sparse.coo_matrix.multiply

`coo_matrix.multiply` (*self*, *other*)

Point-wise multiplication by another matrix

scipy.sparse.coo_matrix.nonzero

`coo_matrix.nonzero` (*self*)

nonzero indices

Returns a tuple of arrays (row,col) containing the indices of the non-zero elements of the matrix.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> A.nonzero()
(array([0, 0, 1, 2, 2]), array([0, 1, 2, 0, 2]))
```

scipy.sparse.coo_matrix.power

`coo_matrix.power` (*self*, *n*, *dtype=None*)

This function performs element-wise power.

Parameters

n [n is a scalar]
dtype [If dtype is not specified, the current dtype will be preserved.]

scipy.sparse.coo_matrix.rad2deg

`coo_matrix.rad2deg` (*self*)

Element-wise rad2deg.

See `numpy.rad2deg` for more information.

scipy.sparse.coo_matrix.reshape

`coo_matrix.reshape` (*self*, *shape*, *order='C'*, *copy=False*)

Gives a new shape to a sparse matrix without changing its data.

Parameters

shape [length-2 tuple of ints] The new shape should be compatible with the original shape.
order [{'C', 'F'}, optional] Read the elements using this index order. 'C' means to read and write the elements using C-like index order; e.g., read entire first row, then second row, etc. 'F' means to read and write the elements using Fortran-like index order; e.g., read entire first column, then second column, etc.
copy [bool, optional] Indicates whether or not attributes of *self* should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns

reshaped_matrix
[sparse matrix] A sparse matrix with the given *shape*, not necessarily of the same format as the current object.

See also:

[`numpy.matrix.reshape`](#)

NumPy's implementation of 'reshape' for matrices

`scipy.sparse.coo_matrix.resize`

`coo_matrix.resize` (*self*, **shape*)

Resize the matrix in-place to dimensions given by *shape*

Any elements that lie within the new shape will remain at the same indices, while non-zero elements lying outside the new shape are removed.

Parameters

shape [(int, int)] number of rows and columns in the new matrix

Notes

The semantics are not identical to `numpy.ndarray.resize` or `numpy.resize`. Here, the same data will be maintained at each index before and after reshape, if that index is within the new bounds. In `numpy`, resizing maintains contiguity of the array, moving elements around in the logical matrix but not within a flattened representation.

We give no guarantees about whether the underlying data attributes (arrays, etc.) will be modified in place or replaced with new objects.

`scipy.sparse.coo_matrix.rint`

`coo_matrix.rint` (*self*)

Element-wise rint.

See `numpy rint` for more information.

`scipy.sparse.coo_matrix.set_shape`

`coo_matrix.set_shape` (*self*, *shape*)

See `reshape`.

`scipy.sparse.coo_matrix.setdiag`

`coo_matrix.setdiag` (*self*, *values*, *k=0*)

Set diagonal or off-diagonal elements of the array.

Parameters

values [array_like] New values of the diagonal elements.
Values may have any length. If the diagonal is longer than *values*, then the remaining diagonal entries will not be set. If *values* are longer than the diagonal, then the remaining values are ignored.
If a scalar value is given, all of the diagonal is set to it.

k [int, optional] Which off-diagonal to set, corresponding to elements `a[i,i+k]`. Default: 0 (the main diagonal).

scipy.sparse.coo_matrix.sign`coo_matrix.sign(self)`

Element-wise sign.

See `numpy.sign` for more information.**scipy.sparse.coo_matrix.sin**`coo_matrix.sin(self)`

Element-wise sin.

See `numpy.sin` for more information.**scipy.sparse.coo_matrix.sinh**`coo_matrix.sinh(self)`

Element-wise sinh.

See `numpy.sinh` for more information.**scipy.sparse.coo_matrix.sqrt**`coo_matrix.sqrt(self)`

Element-wise sqrt.

See `numpy.sqrt` for more information.**scipy.sparse.coo_matrix.sum**`coo_matrix.sum(self, axis=None, dtype=None, out=None)`

Sum the matrix elements over a given axis.

Parameters

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the sum of all the matrix elements, returning a scalar (i.e., *axis = None*).
- dtype** [dtype, optional] The type of the returned matrix and of the accumulator in which the elements are summed. The dtype of *a* is used by default unless *a* has an integer dtype of less precision than the default platform integer. In that case, if *a* is signed then the platform integer is used while if *a* is unsigned then an unsigned integer of the same precision as the platform integer is used.
New in version 0.18.0.
- out** [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns**sum_along_axis**[np.matrix] A matrix with the same shape as *self*, with the specified axis removed.

See also:

`numpy.matrix.sum`

NumPy's implementation of 'sum' for matrices

scipy.sparse.coo_matrix.sum_duplicates

`coo_matrix.sum_duplicates` (*self*)

Eliminate duplicate matrix entries by adding them together

This is an *in place* operation

scipy.sparse.coo_matrix.tan

`coo_matrix.tan` (*self*)

Element-wise tan.

See `numpy.tan` for more information.

scipy.sparse.coo_matrix.tanh

`coo_matrix.tanh` (*self*)

Element-wise tanh.

See `numpy.tanh` for more information.

scipy.sparse.coo_matrix.toarray

`coo_matrix.toarray` (*self*, *order=None*, *out=None*)

See the docstring for `spmatrix.toarray`.

scipy.sparse.coo_matrix.tobsr

`coo_matrix.tobsr` (*self*, *blocksize=None*, *copy=False*)

Convert this matrix to Block Sparse Row format.

With `copy=False`, the data/indices may be shared between this matrix and the resultant `bsr_matrix`.

When `blocksize=(R, C)` is provided, it will be used for construction of the `bsr_matrix`.

scipy.sparse.coo_matrix.tocoo

`coo_matrix.tocoo` (*self*, *copy=False*)

Convert this matrix to COOrdinate format.

With `copy=False`, the data/indices may be shared between this matrix and the resultant `coo_matrix`.

scipy.sparse.coo_matrix.tocsc`coo_matrix.tocsc` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Column format

Duplicate entries will be summed together.

Examples

```

>>> from numpy import array
>>> from scipy.sparse import coo_matrix
>>> row = array([0, 0, 1, 3, 1, 0, 0])
>>> col = array([0, 2, 1, 3, 1, 0, 0])
>>> data = array([1, 1, 1, 1, 1, 1, 1])
>>> A = coo_matrix((data, (row, col)), shape=(4, 4)).tocsc()
>>> A.toarray()
array([[3, 0, 1, 0],
       [0, 2, 0, 0],
       [0, 0, 0, 0],
       [0, 0, 0, 1]])

```

scipy.sparse.coo_matrix.tocsr`coo_matrix.tocsr` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Row format

Duplicate entries will be summed together.

Examples

```

>>> from numpy import array
>>> from scipy.sparse import coo_matrix
>>> row = array([0, 0, 1, 3, 1, 0, 0])
>>> col = array([0, 2, 1, 3, 1, 0, 0])
>>> data = array([1, 1, 1, 1, 1, 1, 1])
>>> A = coo_matrix((data, (row, col)), shape=(4, 4)).tocsr()
>>> A.toarray()
array([[3, 0, 1, 0],
       [0, 2, 0, 0],
       [0, 0, 0, 0],
       [0, 0, 0, 1]])

```

scipy.sparse.coo_matrix.todense

`coo_matrix.todense` (*self*, *order=None*, *out=None*)

Return a dense matrix representation of this matrix.

Parameters

- order** [{"C", "F"}, optional] Whether to store multi-dimensional data in C (row-major) or Fortran (column-major) order in memory. The default is 'None', indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the *out* argument.
- out** [ndarray, 2-D, optional] If specified, uses this array (or `numpy.matrix`) as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method.

Returns

- arr** [numpy.matrix, 2-D] A NumPy matrix object with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If *out* was passed and was an array (rather than a `numpy.matrix`), it will be filled with the appropriate values and returned wrapped in a `numpy.matrix` object that shares the same memory.

scipy.sparse.coo_matrix.todia

`coo_matrix.todia` (*self*, *copy=False*)

Convert this matrix to sparse DIAgonal format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dia_matrix`.

scipy.sparse.coo_matrix.todok

`coo_matrix.todok` (*self*, *copy=False*)

Convert this matrix to Dictionary Of Keys format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dok_matrix`.

scipy.sparse.coo_matrix.tolil

`coo_matrix.tolil` (*self*, *copy=False*)

Convert this matrix to List of Lists format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `lil_matrix`.

scipy.sparse.coo_matrix.transpose

`coo_matrix.transpose` (*self*, *axes=None*, *copy=False*)

Reverses the dimensions of the sparse matrix.

Parameters

- axes** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value.

copy [bool, optional] Indicates whether or not attributes of *self* should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns

p [*self* with the dimensions reversed.]

See also:

`numpy.matrix.transpose`

NumPy's implementation of 'transpose' for matrices

scipy.sparse.coo_matrix.trunc

`coo_matrix.trunc(self)`

Element-wise trunc.

See `numpy.trunc` for more information.

scipy.sparse.csc_matrix

class `scipy.sparse.csc_matrix` (*arg1*, *shape=None*, *dtype=None*, *copy=False*)

Compressed Sparse Column matrix

This can be instantiated in several ways:

`csc_matrix(D)`

with a dense matrix or rank-2 ndarray D

`csc_matrix(S)`

with another sparse matrix S (equivalent to S.tocsc())

`csc_matrix((M, N), [dtype])`

to construct an empty matrix with shape (M, N) dtype is optional, defaulting to dtype='d'.

`csc_matrix((data, (row_ind, col_ind)), [shape=(M, N)])`

where data, row_ind and col_ind satisfy the relationship `a[row_ind[k], col_ind[k]] = data[k]`.

`csc_matrix((data, indices, indptr), [shape=(M, N)])`

is the standard CSC representation where the row indices for column i are stored in `indices[indptr[i]:indptr[i+1]]` and their corresponding values are stored in `data[indptr[i]:indptr[i+1]]`. If the shape parameter is not supplied, the matrix dimensions are inferred from the index arrays.

Notes

Sparse matrices can be used in arithmetic operations: they support addition, subtraction, multiplication, division, and matrix power.

Advantages of the CSC format

- efficient arithmetic operations CSC + CSC, CSC * CSC, etc.
- efficient column slicing
- fast matrix vector products (CSR, BSR may be faster)

Disadvantages of the CSC format

- slow row slicing operations (consider CSR)
- changes to the sparsity structure are expensive (consider LIL or DOK)

Examples

```
>>> import numpy as np
>>> from scipy.sparse import csc_matrix
>>> csc_matrix((3, 4), dtype=np.int8).toarray()
array([[0, 0, 0, 0],
       [0, 0, 0, 0],
       [0, 0, 0, 0]], dtype=int8)
```

```
>>> row = np.array([0, 2, 2, 0, 1, 2])
>>> col = np.array([0, 0, 1, 2, 2, 2])
>>> data = np.array([1, 2, 3, 4, 5, 6])
>>> csc_matrix((data, (row, col)), shape=(3, 3)).toarray()
array([[1, 0, 4],
       [0, 0, 5],
       [2, 3, 6]])
```

```
>>> indptr = np.array([0, 2, 3, 6])
>>> indices = np.array([0, 2, 2, 0, 1, 2])
>>> data = np.array([1, 2, 3, 4, 5, 6])
>>> csc_matrix((data, indices, indptr), shape=(3, 3)).toarray()
array([[1, 0, 4],
       [0, 0, 5],
       [2, 3, 6]])
```

Attributes

dtype [dtype] Data type of the matrix
shape [2-tuple] Get shape of a matrix.
ndim [int] Number of dimensions (this is always 2)
nnz Number of stored values, including explicit zeros.
data Data array of the matrix
indices CSC format index array
indptr CSC format index pointer array
has_sorted_indices
 Determine whether the matrix has sorted indices

Methods

<code>__len__(self)</code>	
<code>__mul__(self, other)</code>	interpret other and call one of the following
<code>arcsin(self)</code>	Element-wise arcsin.
<code>arcsinh(self)</code>	Element-wise arcsinh.
<code>arctan(self)</code>	Element-wise arctan.
<code>arctanh(self)</code>	Element-wise arctanh.
<code>argmax(self[, axis, out])</code>	Return indices of maximum elements along an axis.

continues on next page

Table 175 – continued from previous page

<i>argmin</i> (self[, axis, out])	Return indices of minimum elements along an axis.
<i>asformat</i> (self, format[, copy])	Return this matrix in the passed format.
<i>asfptype</i> (self)	Upcast matrix to a floating point format (if necessary)
<i>astype</i> (self, dtype[, casting, copy])	Cast the matrix elements to a specified type.
<i>ceil</i> (self)	Element-wise ceil.
<i>check_format</i> (self[, full_check])	check whether the matrix format is valid
<i>conj</i> (self[, copy])	Element-wise complex conjugation.
<i>conjugate</i> (self[, copy])	Element-wise complex conjugation.
<i>copy</i> (self)	Returns a copy of this matrix.
<i>count_nonzero</i> (self)	Number of non-zero entries, equivalent to
<i>deg2rad</i> (self)	Element-wise deg2rad.
<i>diagonal</i> (self[, k])	Returns the kth diagonal of the matrix.
<i>dot</i> (self, other)	Ordinary dot product
<i>eliminate_zeros</i> (self)	Remove zero entries from the matrix
<i>expm1</i> (self)	Element-wise expm1.
<i>floor</i> (self)	Element-wise floor.
<i>getH</i> (self)	Return the Hermitian transpose of this matrix.
<i>get_shape</i> (self)	Get shape of a matrix.
<i>getcol</i> (self, i)	Returns a copy of column i of the matrix, as a (m x 1) CSC matrix (column vector).
<i>getformat</i> (self)	Format of a matrix representation as a string.
<i>getmaxprint</i> (self)	Maximum number of elements to display when printed.
<i>getnnz</i> (self[, axis])	Number of stored values, including explicit zeros.
<i>getrow</i> (self, i)	Returns a copy of row i of the matrix, as a (1 x n) CSR matrix (row vector).
<i>log1p</i> (self)	Element-wise log1p.
<i>max</i> (self[, axis, out])	Return the maximum of the matrix or maximum along an axis.
<i>maximum</i> (self, other)	Element-wise maximum between this and another matrix.
<i>mean</i> (self[, axis, dtype, out])	Compute the arithmetic mean along the specified axis.
<i>min</i> (self[, axis, out])	Return the minimum of the matrix or maximum along an axis.
<i>minimum</i> (self, other)	Element-wise minimum between this and another matrix.
<i>multiply</i> (self, other)	Point-wise multiplication by another matrix, vector, or scalar.
<i>nonzero</i> (self)	nonzero indices
<i>power</i> (self, n[, dtype])	This function performs element-wise power.
<i>prune</i> (self)	Remove empty space after all non-zero elements.
<i>rad2deg</i> (self)	Element-wise rad2deg.
<i>reshape</i> (self, shape[, order, copy])	Gives a new shape to a sparse matrix without changing its data.
<i>resize</i> (self, *shape)	Resize the matrix in-place to dimensions given by shape
<i>rint</i> (self)	Element-wise rint.
<i>set_shape</i> (self, shape)	See <i>reshape</i> .
<i>setdiag</i> (self, values[, k])	Set diagonal or off-diagonal elements of the array.
<i>sign</i> (self)	Element-wise sign.
<i>sin</i> (self)	Element-wise sin.

continues on next page

Table 175 – continued from previous page

<code>sinh(self)</code>	Element-wise sinh.
<code>sort_indices(self)</code>	Sort the indices of this matrix <i>in place</i>
<code>sorted_indices(self)</code>	Return a copy of this matrix with sorted indices
<code>sqrt(self)</code>	Element-wise sqrt.
<code>sum(self[, axis, dtype, out])</code>	Sum the matrix elements over a given axis.
<code>sum_duplicates(self)</code>	Eliminate duplicate matrix entries by adding them together
<code>tan(self)</code>	Element-wise tan.
<code>tanh(self)</code>	Element-wise tanh.
<code>toarray(self[, order, out])</code>	Return a dense ndarray representation of this matrix.
<code>tobsr(self[, blocksize, copy])</code>	Convert this matrix to Block Sparse Row format.
<code>tocoo(self[, copy])</code>	Convert this matrix to COOrdinate format.
<code>tocsc(self[, copy])</code>	Convert this matrix to Compressed Sparse Column format.
<code>tocsr(self[, copy])</code>	Convert this matrix to Compressed Sparse Row format.
<code>todense(self[, order, out])</code>	Return a dense matrix representation of this matrix.
<code>todia(self[, copy])</code>	Convert this matrix to sparse DIAgonal format.
<code>todok(self[, copy])</code>	Convert this matrix to Dictionary Of Keys format.
<code>tolil(self[, copy])</code>	Convert this matrix to List of Lists format.
<code>transpose(self[, axes, copy])</code>	Reverses the dimensions of the sparse matrix.
<code>trunc(self)</code>	Element-wise trunc.

scipy.sparse.csc_matrix.__len__

`csc_matrix.__len__(self)`

scipy.sparse.csc_matrix.__mul__

`csc_matrix.__mul__(self, other)`

interpret other and call one of the following

`self._mul_scalar()` `self._mul_vector()` `self._mul_multivector()` `self._mul_sparse_matrix()`

scipy.sparse.csc_matrix.arcsin

`csc_matrix.arcsin(self)`

Element-wise arcsin.

See `numpy.arcsin` for more information.

scipy.sparse.csc_matrix.arcsinh`csc_matrix.arcsinh` (*self*)

Element-wise arcsinh.

See `numpy.arcsinh` for more information.**scipy.sparse.csc_matrix.arctan**`csc_matrix.arctan` (*self*)

Element-wise arctan.

See `numpy.arctan` for more information.**scipy.sparse.csc_matrix.arctanh**`csc_matrix.arctanh` (*self*)

Element-wise arctanh.

See `numpy.arctanh` for more information.**scipy.sparse.csc_matrix.argmax**`csc_matrix.argmax` (*self*, *axis=None*, *out=None*)

Return indices of maximum elements along an axis.

Implicit zero elements are also taken into account. If there are several maximum values, the index of the first occurrence is returned.

Parameters

- axis** [{-2, -1, 0, 1, None}, optional] Axis along which the argmax is computed. If None (default), index of the maximum element in the flatten data is returned.
- out** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

- ind** [numpy.matrix or int] Indices of maximum elements. If matrix, its size along *axis* is 1.

scipy.sparse.csc_matrix.argmin`csc_matrix.argmin` (*self*, *axis=None*, *out=None*)

Return indices of minimum elements along an axis.

Implicit zero elements are also taken into account. If there are several minimum values, the index of the first occurrence is returned.

Parameters

- axis** [{-2, -1, 0, 1, None}, optional] Axis along which the argmin is computed. If None (default), index of the minimum element in the flatten data is returned.
- out** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

ind [numpy.matrix or int] Indices of minimum elements. If matrix, its size along *axis* is 1.

scipy.sparse.csc_matrix.asformat

`csc_matrix.asformat` (*self*, *format*, *copy=False*)

Return this matrix in the passed format.

Parameters

format [{str, None}] The desired matrix format (“csr”, “csc”, “lil”, “dok”, “array”, ...) or None for no conversion.
copy [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

A [This matrix in the passed format.]

scipy.sparse.csc_matrix.asfptype

`csc_matrix.asfptype` (*self*)

Upcast matrix to a floating point format (if necessary)

scipy.sparse.csc_matrix.astype

`csc_matrix.astype` (*self*, *dtype*, *casting='unsafe'*, *copy=True*)

Cast the matrix elements to a specified type.

Parameters

dtype [string or numpy dtype] Typecode or data-type to which to cast the data.
casting [{‘no’, ‘equiv’, ‘safe’, ‘same_kind’, ‘unsafe’}, optional] Controls what kind of data casting may occur. Defaults to ‘unsafe’ for backwards compatibility. ‘no’ means the data types should not be cast at all. ‘equiv’ means only byte-order changes are allowed. ‘safe’ means only casts which can preserve values are allowed. ‘same_kind’ means only safe casts or casts within a kind, like float64 to float32, are allowed. ‘unsafe’ means any data conversions may be done.
copy [bool, optional] If *copy* is *False*, the result might share some memory with this matrix. If *copy* is *True*, it is guaranteed that the result and this matrix do not share any memory.

scipy.sparse.csc_matrix.ceil

`csc_matrix.ceil` (*self*)

Element-wise ceil.

See `numpy.ceil` for more information.

scipy.sparse.csc_matrix.check_format

`csc_matrix.check_format` (*self*, *full_check=True*)
 check whether the matrix format is valid

Parameters

full_check [bool, optional] If *True*, rigorous check, O(N) operations. Otherwise basic check, O(1) operations (default *True*).

scipy.sparse.csc_matrix.conj

`csc_matrix.conj` (*self*, *copy=True*)
 Element-wise complex conjugation.

If the matrix is of non-complex data type and *copy* is *False*, this method does nothing and the data is not copied.

Parameters

copy [bool, optional] If *True*, the result is guaranteed to not share data with self.

Returns

A [The element-wise complex conjugate.]

scipy.sparse.csc_matrix.conjugate

`csc_matrix.conjugate` (*self*, *copy=True*)
 Element-wise complex conjugation.

If the matrix is of non-complex data type and *copy* is *False*, this method does nothing and the data is not copied.

Parameters

copy [bool, optional] If *True*, the result is guaranteed to not share data with self.

Returns

A [The element-wise complex conjugate.]

scipy.sparse.csc_matrix.copy

`csc_matrix.copy` (*self*)
 Returns a copy of this matrix.

No data/indices will be shared between the returned value and current matrix.

scipy.sparse.csc_matrix.count_nonzero

`csc_matrix.count_nonzero` (*self*)
Number of non-zero entries, equivalent to
`np.count_nonzero(a.toarray())`

Unlike `getnnz()` and the `nnz` property, which return the number of stored entries (the length of the data attribute), this method counts the actual number of non-zero entries in data.

scipy.sparse.csc_matrix.deg2rad

`csc_matrix.deg2rad` (*self*)
Element-wise `deg2rad`.
See `numpy.deg2rad` for more information.

scipy.sparse.csc_matrix.diagonal

`csc_matrix.diagonal` (*self*, *k=0*)
Returns the *k*th diagonal of the matrix.

Parameters

k [int, optional] Which diagonal to get, corresponding to elements `a[i, i+k]`. Default: 0 (the main diagonal).
New in version 1.0.

See also:

`numpy.diagonal`

Equivalent numpy function.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> A.diagonal()
array([1, 0, 5])
>>> A.diagonal(k=1)
array([2, 3])
```

scipy.sparse.csc_matrix.dot

`csc_matrix.dot` (*self*, *other*)
Ordinary dot product

Examples

```
>>> import numpy as np
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> v = np.array([1, 0, -1])
>>> A.dot(v)
array([ 1, -3, -1], dtype=int64)
```

scipy.sparse.csc_matrix.eliminate_zeros

`csc_matrix.eliminate_zeros` (*self*)
Remove zero entries from the matrix

This is an *in place* operation.

scipy.sparse.csc_matrix.expm1

`csc_matrix.expm1` (*self*)
Element-wise `expm1`.

See `numpy.expm1` for more information.

scipy.sparse.csc_matrix.floor

`csc_matrix.floor` (*self*)
Element-wise floor.

See `numpy.floor` for more information.

scipy.sparse.csc_matrix.getH

`csc_matrix.getH` (*self*)
Return the Hermitian transpose of this matrix.

See also:

`numpy.matrix.getH`

NumPy's implementation of `getH` for matrices

scipy.sparse.csc_matrix.get_shape

`csc_matrix.get_shape` (*self*)
Get shape of a matrix.

scipy.sparse.csc_matrix.getcol

`csc_matrix.getcol` (*self*, *i*)
Returns a copy of column *i* of the matrix, as a (m x 1) CSC matrix (column vector).

scipy.sparse.csc_matrix.getformat

`csc_matrix.getformat` (*self*)
Format of a matrix representation as a string.

scipy.sparse.csc_matrix.getmaxprint

`csc_matrix.getmaxprint` (*self*)
Maximum number of elements to display when printed.

scipy.sparse.csc_matrix.getnnz

`csc_matrix.getnnz` (*self*, *axis=None*)
Number of stored values, including explicit zeros.

Parameters

axis [None, 0, or 1] Select between the number of values across the whole matrix, in each column, or in each row.

See also:

[*count_nonzero*](#)

Number of non-zero entries

scipy.sparse.csc_matrix.getrow

`csc_matrix.getrow` (*self*, *i*)
Returns a copy of row *i* of the matrix, as a (1 x n) CSR matrix (row vector).

scipy.sparse.csc_matrix.log1p`csc_matrix.log1p` (*self*)

Element-wise log1p.

See `numpy.log1p` for more information.**scipy.sparse.csc_matrix.max**`csc_matrix.max` (*self*, *axis=None*, *out=None*)

Return the maximum of the matrix or maximum along an axis. This takes all elements into account, not just the non-zero ones.

Parameters

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the maximum over all the matrix elements, returning a scalar (i.e., *axis = None*).
- out** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

- amax** [coo_matrix or scalar] Maximum of *a*. If *axis* is None, the result is a scalar value. If *axis* is given, the result is a sparse.coo_matrix of dimension `a.ndim - 1`.

See also:***min***

The minimum value of a sparse matrix along a given axis.

numpy.matrix.max

NumPy's implementation of 'max' for matrices

scipy.sparse.csc_matrix.maximum`csc_matrix.maximum` (*self*, *other*)

Element-wise maximum between this and another matrix.

scipy.sparse.csc_matrix.mean`csc_matrix.mean` (*self*, *axis=None*, *dtype=None*, *out=None*)

Compute the arithmetic mean along the specified axis.

Returns the average of the matrix elements. The average is taken over all elements in the matrix by default, otherwise over the specified axis. *float64* intermediate and return values are used for integer inputs.**Parameters**

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the mean is computed. The default is to compute the mean of all elements in the matrix (i.e., *axis = None*).
- dtype** [data-type, optional] Type to use in computing the mean. For integer inputs, the default is *float64*; for floating point inputs, it is the same as the input dtype.
New in version 0.18.0.

out [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns

m [np.matrix]

See also:

[*numpy.matrix.mean*](#)

NumPy's implementation of 'mean' for matrices

scipy.sparse.csc_matrix.min

`csc_matrix.min` (*self*, *axis=None*, *out=None*)

Return the minimum of the matrix or maximum along an axis. This takes all elements into account, not just the non-zero ones.

Parameters

axis [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the minimum over all the matrix elements, returning a scalar (i.e., *axis = None*).

out [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

amin [coo_matrix or scalar] Minimum of *a*. If *axis* is None, the result is a scalar value. If *axis* is given, the result is a sparse.coo_matrix of dimension `a.ndim - 1`.

See also:

[*max*](#)

The maximum value of a sparse matrix along a given axis.

[*numpy.matrix.min*](#)

NumPy's implementation of 'min' for matrices

scipy.sparse.csc_matrix.minimum

`csc_matrix.minimum` (*self*, *other*)

Element-wise minimum between this and another matrix.

scipy.sparse.csc_matrix.multiply`csc_matrix.multiply` (*self*, *other*)

Point-wise multiplication by another matrix, vector, or scalar.

scipy.sparse.csc_matrix.nonzero`csc_matrix.nonzero` (*self*)

nonzero indices

Returns a tuple of arrays (row,col) containing the indices of the non-zero elements of the matrix.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> A.nonzero()
(array([0, 0, 1, 2, 2]), array([0, 1, 2, 0, 2]))
```

scipy.sparse.csc_matrix.power`csc_matrix.power` (*self*, *n*, *dtype=None*)

This function performs element-wise power.

Parameters

n	[n is a scalar]
dtype	[If dtype is not specified, the current dtype will be preserved.]

scipy.sparse.csc_matrix.prune`csc_matrix.prune` (*self*)

Remove empty space after all non-zero elements.

scipy.sparse.csc_matrix.rad2deg`csc_matrix.rad2deg` (*self*)

Element-wise rad2deg.

See `numpy.rad2deg` for more information.

scipy.sparse.csc_matrix.reshape`csc_matrix.reshape` (*self*, *shape*, *order='C'*, *copy=False*)

Gives a new shape to a sparse matrix without changing its data.

Parameters

shape	[length-2 tuple of ints] The new shape should be compatible with the original shape.
order	[{'C', 'F'}, optional] Read the elements using this index order. 'C' means to read and write the elements using C-like index order; e.g., read entire first row, then second row, etc. 'F' means to read and write the elements using Fortran-like index order; e.g., read entire first column, then second column, etc.
copy	[bool, optional] Indicates whether or not attributes of <i>self</i> should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns**reshaped_matrix**[sparse matrix] A sparse matrix with the given *shape*, not necessarily of the same format as the current object.**See also:***numpy.matrix.reshape*

NumPy's implementation of 'reshape' for matrices

scipy.sparse.csc_matrix.resize`csc_matrix.resize` (*self*, **shape*)Resize the matrix in-place to dimensions given by *shape*

Any elements that lie within the new shape will remain at the same indices, while non-zero elements lying outside the new shape are removed.

Parameters

shape	[(int, int)] number of rows and columns in the new matrix
--------------	---

Notes

The semantics are not identical to `numpy.ndarray.resize` or `numpy.resize`. Here, the same data will be maintained at each index before and after reshape, if that index is within the new bounds. In `numpy`, resizing maintains contiguity of the array, moving elements around in the logical matrix but not within a flattened representation.

We give no guarantees about whether the underlying data attributes (arrays, etc.) will be modified in place or replaced with new objects.

scipy.sparse.csc_matrix.rint`csc_matrix.rint` (*self*)

Element-wise rint.

See `numpy.rint` for more information.**scipy.sparse.csc_matrix.set_shape**`csc_matrix.set_shape` (*self*, *shape*)See `reshape`.**scipy.sparse.csc_matrix.setdiag**`csc_matrix.setdiag` (*self*, *values*, *k=0*)

Set diagonal or off-diagonal elements of the array.

Parameters

- values** [array_like] New values of the diagonal elements. Values may have any length. If the diagonal is longer than values, then the remaining diagonal entries will not be set. If values are longer than the diagonal, then the remaining values are ignored.
- k** [int, optional] Which off-diagonal to set, corresponding to elements $a[i,i+k]$. Default: 0 (the main diagonal).

scipy.sparse.csc_matrix.sign`csc_matrix.sign` (*self*)

Element-wise sign.

See `numpy.sign` for more information.**scipy.sparse.csc_matrix.sin**`csc_matrix.sin` (*self*)

Element-wise sin.

See `numpy.sin` for more information.**scipy.sparse.csc_matrix.sinh**`csc_matrix.sinh` (*self*)

Element-wise sinh.

See `numpy.sinh` for more information.

scipy.sparse.csc_matrix.sort_indices

`csc_matrix.sort_indices` (*self*)
Sort the indices of this matrix *in place*

scipy.sparse.csc_matrix.sorted_indices

`csc_matrix.sorted_indices` (*self*)
Return a copy of this matrix with sorted indices

scipy.sparse.csc_matrix.sqrt

`csc_matrix.sqrt` (*self*)
Element-wise sqrt.
See `numpy.sqrt` for more information.

scipy.sparse.csc_matrix.sum

`csc_matrix.sum` (*self*, *axis=None*, *dtype=None*, *out=None*)
Sum the matrix elements over a given axis.

Parameters

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the sum of all the matrix elements, returning a scalar (i.e., *axis = None*).
- dtype** [dtype, optional] The type of the returned matrix and of the accumulator in which the elements are summed. The dtype of *a* is used by default unless *a* has an integer dtype of less precision than the default platform integer. In that case, if *a* is signed then the platform integer is used while if *a* is unsigned then an unsigned integer of the same precision as the platform integer is used.
New in version 0.18.0.
- out** [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns

- sum_along_axis** [np.matrix] A matrix with the same shape as *self*, with the specified axis removed.

See also:

`numpy.matrix.sum`

NumPy's implementation of 'sum' for matrices

scipy.sparse.csc_matrix.sum_duplicates`csc_matrix.sum_duplicates` (*self*)

Eliminate duplicate matrix entries by adding them together

This is an *in place* operation.**scipy.sparse.csc_matrix.tan**`csc_matrix.tan` (*self*)

Element-wise tan.

See `numpy.tan` for more information.**scipy.sparse.csc_matrix.tanh**`csc_matrix.tanh` (*self*)

Element-wise tanh.

See `numpy.tanh` for more information.**scipy.sparse.csc_matrix.toarray**`csc_matrix.toarray` (*self*, *order=None*, *out=None*)

Return a dense ndarray representation of this matrix.

Parameters

- order** [{"C", "F"}, optional] Whether to store multidimensional data in C (row-major) or Fortran (column-major) order in memory. The default is 'None', indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the *out* argument.
- out** [ndarray, 2-D, optional] If specified, uses this array as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method. For most sparse types, *out* is required to be memory contiguous (either C or Fortran ordered).

Returns

- arr** [ndarray, 2-D] An array with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If *out* was passed, the same object is returned after being modified in-place to contain the appropriate values.

scipy.sparse.csc_matrix.tobsr`csc_matrix.tobsr` (*self*, *blocksize=None*, *copy=False*)

Convert this matrix to Block Sparse Row format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `bsr_matrix`.When *blocksize=(R, C)* is provided, it will be used for construction of the `bsr_matrix`.

scipy.sparse.csc_matrix.tocoo`csc_matrix.tocoo` (*self*, *copy=True*)

Convert this matrix to COOrdinate format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `coo_matrix`.**scipy.sparse.csc_matrix.tocsc**`csc_matrix.tocsc` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Column format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `csc_matrix`.**scipy.sparse.csc_matrix.tocsr**`csc_matrix.tocsr` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Row format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `csr_matrix`.**scipy.sparse.csc_matrix.todense**`csc_matrix.todense` (*self*, *order=None*, *out=None*)

Return a dense matrix representation of this matrix.

Parameters

- order** [{"C", "F"}, optional] Whether to store multi-dimensional data in C (row-major) or Fortran (column-major) order in memory. The default is 'None', indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the *out* argument.
- out** [ndarray, 2-D, optional] If specified, uses this array (or `numpy.matrix`) as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method.

Returns

- arr** [numpy.matrix, 2-D] A NumPy matrix object with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If *out* was passed and was an array (rather than a `numpy.matrix`), it will be filled with the appropriate values and returned wrapped in a `numpy.matrix` object that shares the same memory.

scipy.sparse.csc_matrix.todia`csc_matrix.todia` (*self*, *copy=False*)

Convert this matrix to sparse DIAgonal format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dia_matrix`.

scipy.sparse.csc_matrix.todok`csc_matrix.todok` (*self*, *copy=False*)

Convert this matrix to Dictionary Of Keys format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dok_matrix`.**scipy.sparse.csc_matrix.tolil**`csc_matrix.tolil` (*self*, *copy=False*)

Convert this matrix to List of Lists format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `lil_matrix`.**scipy.sparse.csc_matrix.transpose**`csc_matrix.transpose` (*self*, *axes=None*, *copy=False*)

Reverses the dimensions of the sparse matrix.

Parameters

- axes** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value.
- copy** [bool, optional] Indicates whether or not attributes of *self* should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns

- p** [*self* with the dimensions reversed.]

See also:***numpy.matrix.transpose***

NumPy's implementation of 'transpose' for matrices

scipy.sparse.csc_matrix.trunc`csc_matrix.trunc` (*self*)

Element-wise trunc.

See `numpy.trunc` for more information.

<code>__getitem__</code>	
--------------------------	--

scipy.sparse.csr_matrix

class `scipy.sparse.csr_matrix` (*arg1*, *shape=None*, *dtype=None*, *copy=False*)
Compressed Sparse Row matrix

This can be instantiated in several ways:

csr_matrix(D)

with a dense matrix or rank-2 ndarray D

csr_matrix(S)

with another sparse matrix S (equivalent to `S.tocsr()`)

csr_matrix((M, N), [dtype])

to construct an empty matrix with shape (M, N) dtype is optional, defaulting to `dtype='d'`.

csr_matrix((data, (row_ind, col_ind)), [shape=(M, N)])

where `data`, `row_ind` and `col_ind` satisfy the relationship `a[row_ind[k], col_ind[k]] = data[k]`.

csr_matrix((data, indices, indptr), [shape=(M, N)])

is the standard CSR representation where the column indices for row `i` are stored in `indices[indptr[i]:indptr[i+1]]` and their corresponding values are stored in `data[indptr[i]:indptr[i+1]]`. If the `shape` parameter is not supplied, the matrix dimensions are inferred from the index arrays.

Notes

Sparse matrices can be used in arithmetic operations: they support addition, subtraction, multiplication, division, and matrix power.

Advantages of the CSR format

- efficient arithmetic operations `CSR + CSR`, `CSR * CSR`, etc.
- efficient row slicing
- fast matrix vector products

Disadvantages of the CSR format

- slow column slicing operations (consider CSC)
- changes to the sparsity structure are expensive (consider LIL or DOK)

Examples

```
>>> import numpy as np
>>> from scipy.sparse import csr_matrix
>>> csr_matrix((3, 4), dtype=np.int8).toarray()
array([[0, 0, 0, 0],
       [0, 0, 0, 0],
       [0, 0, 0, 0]], dtype=int8)
```

```
>>> row = np.array([0, 0, 1, 2, 2, 2])
>>> col = np.array([0, 2, 2, 0, 1, 2])
>>> data = np.array([1, 2, 3, 4, 5, 6])
>>> csr_matrix((data, (row, col)), shape=(3, 3)).toarray()
array([[1, 0, 2],
       [0, 0, 3],
       [4, 5, 6]])
```

```
>>> indptr = np.array([0, 2, 3, 6])
>>> indices = np.array([0, 2, 2, 0, 1, 2])
>>> data = np.array([1, 2, 3, 4, 5, 6])
>>> csr_matrix((data, indices, indptr), shape=(3, 3)).toarray()
array([[1, 0, 2],
       [0, 0, 3],
       [4, 5, 6]])
```

Duplicate entries are summed together:

```
>>> row = np.array([0, 1, 2, 0])
>>> col = np.array([0, 1, 1, 0])
>>> data = np.array([1, 2, 4, 8])
>>> csr_matrix((data, (row, col)), shape=(3, 3)).toarray()
array([[9, 0, 0],
       [0, 2, 0],
       [0, 4, 0]])
```

As an example of how to construct a CSR matrix incrementally, the following snippet builds a term-document matrix from texts:

```
>>> docs = [["hello", "world", "hello"], ["goodbye", "cruel", "world"]]
>>> indptr = [0]
>>> indices = []
>>> data = []
>>> vocabulary = {}
>>> for d in docs:
...     for term in d:
...         index = vocabulary.setdefault(term, len(vocabulary))
...         indices.append(index)
...         data.append(1)
...     indptr.append(len(indices))
...
>>> csr_matrix((data, indices, indptr), dtype=int).toarray()
array([[2, 1, 0, 0],
       [0, 1, 1, 1]])
```

Attributes

dtype	[dtype] Data type of the matrix
shape	[2-tuple] Get shape of a matrix.
ndim	[int] Number of dimensions (this is always 2)
nnz	Number of stored values, including explicit zeros.
data	CSR format data array of the matrix
indices	CSR format index array of the matrix
indptr	CSR format index pointer array of the matrix
has_sorted_indices	Determine whether the matrix has sorted indices

Methods

<code>__len__(self)</code>	
<code>__mul__(self, other)</code>	interpret other and call one of the following
<code>arcsin(self)</code>	Element-wise arcsin.
<code>arcsinh(self)</code>	Element-wise arcsinh.
<code>arctan(self)</code>	Element-wise arctan.
<code>arctanh(self)</code>	Element-wise arctanh.
<code>argmax(self[, axis, out])</code>	Return indices of maximum elements along an axis.
<code>argmin(self[, axis, out])</code>	Return indices of minimum elements along an axis.
<code>asformat(self, format[, copy])</code>	Return this matrix in the passed format.
<code>asfptype(self)</code>	Upcast matrix to a floating point format (if necessary)
<code>astype(self, dtype[, casting, copy])</code>	Cast the matrix elements to a specified type.
<code>ceil(self)</code>	Element-wise ceil.
<code>check_format(self[, full_check])</code>	check whether the matrix format is valid
<code>conj(self[, copy])</code>	Element-wise complex conjugation.
<code>conjugate(self[, copy])</code>	Element-wise complex conjugation.
<code>copy(self)</code>	Returns a copy of this matrix.
<code>count_nonzero(self)</code>	Number of non-zero entries, equivalent to
<code>deg2rad(self)</code>	Element-wise deg2rad.
<code>diagonal(self[, k])</code>	Returns the kth diagonal of the matrix.
<code>dot(self, other)</code>	Ordinary dot product
<code>eliminate_zeros(self)</code>	Remove zero entries from the matrix
<code>expm1(self)</code>	Element-wise expm1.
<code>floor(self)</code>	Element-wise floor.
<code>getH(self)</code>	Return the Hermitian transpose of this matrix.
<code>get_shape(self)</code>	Get shape of a matrix.
<code>getcol(self, i)</code>	Returns a copy of column i of the matrix, as a (m x 1) CSR matrix (column vector).
<code>getformat(self)</code>	Format of a matrix representation as a string.
<code>getmaxprint(self)</code>	Maximum number of elements to display when printed.
<code>getnnz(self[, axis])</code>	Number of stored values, including explicit zeros.
<code>getrow(self, i)</code>	Returns a copy of row i of the matrix, as a (1 x n) CSR matrix (row vector).
<code>log1p(self)</code>	Element-wise log1p.
<code>max(self[, axis, out])</code>	Return the maximum of the matrix or maximum along an axis.

continues on next page

Table 176 – continued from previous page

<code>maximum(self, other)</code>	Element-wise maximum between this and another matrix.
<code>mean(self[, axis, dtype, out])</code>	Compute the arithmetic mean along the specified axis.
<code>min(self[, axis, out])</code>	Return the minimum of the matrix or maximum along an axis.
<code>minimum(self, other)</code>	Element-wise minimum between this and another matrix.
<code>multiply(self, other)</code>	Point-wise multiplication by another matrix, vector, or scalar.
<code>nonzero(self)</code>	nonzero indices
<code>power(self, n[, dtype])</code>	This function performs element-wise power.
<code>prune(self)</code>	Remove empty space after all non-zero elements.
<code>rad2deg(self)</code>	Element-wise rad2deg.
<code>reshape(self, shape[, order, copy])</code>	Gives a new shape to a sparse matrix without changing its data.
<code>resize(self, *shape)</code>	Resize the matrix in-place to dimensions given by shape
<code>rint(self)</code>	Element-wise rint.
<code>set_shape(self, shape)</code>	See <code>reshape</code> .
<code>setdiag(self, values[, k])</code>	Set diagonal or off-diagonal elements of the array.
<code>sign(self)</code>	Element-wise sign.
<code>sin(self)</code>	Element-wise sin.
<code>sinh(self)</code>	Element-wise sinh.
<code>sort_indices(self)</code>	Sort the indices of this matrix <i>in place</i>
<code>sorted_indices(self)</code>	Return a copy of this matrix with sorted indices
<code>sqrt(self)</code>	Element-wise sqrt.
<code>sum(self[, axis, dtype, out])</code>	Sum the matrix elements over a given axis.
<code>sum_duplicates(self)</code>	Eliminate duplicate matrix entries by adding them together
<code>tan(self)</code>	Element-wise tan.
<code>tanh(self)</code>	Element-wise tanh.
<code>toarray(self[, order, out])</code>	Return a dense ndarray representation of this matrix.
<code>tobsr(self[, blocksize, copy])</code>	Convert this matrix to Block Sparse Row format.
<code>tocoo(self[, copy])</code>	Convert this matrix to COOrdinate format.
<code>tocsc(self[, copy])</code>	Convert this matrix to Compressed Sparse Column format.
<code>tocsr(self[, copy])</code>	Convert this matrix to Compressed Sparse Row format.
<code>todense(self[, order, out])</code>	Return a dense matrix representation of this matrix.
<code>todia(self[, copy])</code>	Convert this matrix to sparse DIAGONAL format.
<code>todok(self[, copy])</code>	Convert this matrix to Dictionary Of Keys format.
<code>tolil(self[, copy])</code>	Convert this matrix to List of Lists format.
<code>transpose(self[, axes, copy])</code>	Reverses the dimensions of the sparse matrix.
<code>trunc(self)</code>	Element-wise trunc.

scipy.sparse.csr_matrix.__len__

`csr_matrix.__len__` (*self*)

scipy.sparse.csr_matrix.__mul__

`csr_matrix.__mul__` (*self*, *other*)

interpret other and call one of the following

`self._mul_scalar()` `self._mul_vector()` `self._mul_multivector()` `self._mul_sparse_matrix()`

scipy.sparse.csr_matrix.arcsin

`csr_matrix.arcsin` (*self*)

Element-wise arcsin.

See `numpy.arcsin` for more information.

scipy.sparse.csr_matrix.arcsinh

`csr_matrix.arcsinh` (*self*)

Element-wise arcsinh.

See `numpy.arcsinh` for more information.

scipy.sparse.csr_matrix.arctan

`csr_matrix.arctan` (*self*)

Element-wise arctan.

See `numpy.arctan` for more information.

scipy.sparse.csr_matrix.arctanh

`csr_matrix.arctanh` (*self*)

Element-wise arctanh.

See `numpy.arctanh` for more information.

scipy.sparse.csr_matrix.argmax

`csr_matrix.argmax` (*self*, *axis=None*, *out=None*)

Return indices of maximum elements along an axis.

Implicit zero elements are also taken into account. If there are several maximum values, the index of the first occurrence is returned.

Parameters

axis [{-2, -1, 0, 1, None}, optional] Axis along which the argmax is computed. If None (default), index of the maximum element in the flatten data is returned.

out [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

ind [numpy.matrix or int] Indices of maximum elements. If matrix, its size along *axis* is 1.

scipy.sparse.csr_matrix.argmax

`csr_matrix.argmax` (*self*, *axis=None*, *out=None*)

Return indices of minimum elements along an axis.

Implicit zero elements are also taken into account. If there are several minimum values, the index of the first occurrence is returned.

Parameters

axis [{-2, -1, 0, 1, None}, optional] Axis along which the argmin is computed. If None (default), index of the minimum element in the flatten data is returned.

out [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

ind [numpy.matrix or int] Indices of minimum elements. If matrix, its size along *axis* is 1.

scipy.sparse.csr_matrix.asformat

`csr_matrix.asformat` (*self*, *format*, *copy=False*)

Return this matrix in the passed format.

Parameters

format [{str, None}] The desired matrix format (“csr”, “csc”, “lil”, “dok”, “array”, ...) or None for no conversion.

copy [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

A [This matrix in the passed format.]

scipy.sparse.csr_matrix.asfptype

`csr_matrix.asfptype` (*self*)

Upcast matrix to a floating point format (if necessary)

scipy.sparse.csr_matrix.astype

`csr_matrix.astype` (*self*, *dtype*, *casting='unsafe'*, *copy=True*)

Cast the matrix elements to a specified type.

Parameters

- dtype** [string or numpy dtype] Typecode or data-type to which to cast the data.
- casting** [{‘no’, ‘equiv’, ‘safe’, ‘same_kind’, ‘unsafe’}, optional] Controls what kind of data casting may occur. Defaults to ‘unsafe’ for backwards compatibility. ‘no’ means the data types should not be cast at all. ‘equiv’ means only byte-order changes are allowed. ‘safe’ means only casts which can preserve values are allowed. ‘same_kind’ means only safe casts or casts within a kind, like float64 to float32, are allowed. ‘unsafe’ means any data conversions may be done.
- copy** [bool, optional] If *copy* is *False*, the result might share some memory with this matrix. If *copy* is *True*, it is guaranteed that the result and this matrix do not share any memory.

scipy.sparse.csr_matrix.ceil

`csr_matrix.ceil` (*self*)

Element-wise ceil.

See `numpy.ceil` for more information.

scipy.sparse.csr_matrix.check_format

`csr_matrix.check_format` (*self*, *full_check=True*)

check whether the matrix format is valid

Parameters

- full_check** [bool, optional] If *True*, rigorous check, O(N) operations. Otherwise basic check, O(1) operations (default *True*).

scipy.sparse.csr_matrix.conj

`csr_matrix.conj` (*self*, *copy=True*)

Element-wise complex conjugation.

If the matrix is of non-complex data type and *copy* is *False*, this method does nothing and the data is not copied.

Parameters

- copy** [bool, optional] If *True*, the result is guaranteed to not share data with self.

Returns

- A** [The element-wise complex conjugate.]

scipy.sparse.csr_matrix.conjugate`csr_matrix.conjugate` (*self*, *copy=True*)

Element-wise complex conjugation.

If the matrix is of non-complex data type and *copy* is `False`, this method does nothing and the data is not copied.

Parameters

copy [bool, optional] If `True`, the result is guaranteed to not share data with *self*.

Returns

A [The element-wise complex conjugate.]

scipy.sparse.csr_matrix.copy`csr_matrix.copy` (*self*)

Returns a copy of this matrix.

No data/indices will be shared between the returned value and current matrix.

scipy.sparse.csr_matrix.count_nonzero`csr_matrix.count_nonzero` (*self*)

Number of non-zero entries, equivalent to

`np.count_nonzero(a.toarray())`

Unlike `getnnz()` and the `nnz` property, which return the number of stored entries (the length of the data attribute), this method counts the actual number of non-zero entries in data.

scipy.sparse.csr_matrix.deg2rad`csr_matrix.deg2rad` (*self*)Element-wise `deg2rad`.

See `numpy.deg2rad` for more information.

scipy.sparse.csr_matrix.diagonal`csr_matrix.diagonal` (*self*, *k=0*)Returns the *k*th diagonal of the matrix.**Parameters**

k [int, optional] Which diagonal to get, corresponding to elements `a[i, i+k]`. Default: 0 (the main diagonal).
New in version 1.0.

See also:*numpy.diagonal*

Equivalent `numpy` function.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> A.diagonal()
array([1, 0, 5])
>>> A.diagonal(k=1)
array([2, 3])
```

scipy.sparse.csr_matrix.dot

`csr_matrix.dot` (*self*, *other*)
Ordinary dot product

Examples

```
>>> import numpy as np
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> v = np.array([1, 0, -1])
>>> A.dot(v)
array([ 1, -3, -1], dtype=int64)
```

scipy.sparse.csr_matrix.eliminate_zeros

`csr_matrix.eliminate_zeros` (*self*)
Remove zero entries from the matrix
This is an *in place* operation.

scipy.sparse.csr_matrix.expm1

`csr_matrix.expm1` (*self*)
Element-wise `expm1`.
See `numpy.expm1` for more information.

scipy.sparse.csr_matrix.floor

`csr_matrix.floor` (*self*)
Element-wise floor.
See `numpy.floor` for more information.

scipy.sparse.csr_matrix.getH`csr_matrix.getH(self)`

Return the Hermitian transpose of this matrix.

See also:*numpy.matrix.getH*NumPy's implementation of *getH* for matrices**scipy.sparse.csr_matrix.get_shape**`csr_matrix.get_shape(self)`

Get shape of a matrix.

scipy.sparse.csr_matrix.getcol`csr_matrix.getcol(self, i)`Returns a copy of column *i* of the matrix, as a (m x 1) CSR matrix (column vector).**scipy.sparse.csr_matrix.getformat**`csr_matrix.getformat(self)`

Format of a matrix representation as a string.

scipy.sparse.csr_matrix.getmaxprint`csr_matrix.getmaxprint(self)`

Maximum number of elements to display when printed.

scipy.sparse.csr_matrix.getnnz`csr_matrix.getnnz(self, axis=None)`

Number of stored values, including explicit zeros.

Parameters

axis	[None, 0, or 1] Select between the number of values across the whole matrix, in each column, or in each row.
-------------	--

See also:*count_nonzero*

Number of non-zero entries

scipy.sparse.csr_matrix.getrow`csr_matrix.getrow` (*self*, *i*)

Returns a copy of row *i* of the matrix, as a (1 x n) CSR matrix (row vector).

scipy.sparse.csr_matrix.log1p`csr_matrix.log1p` (*self*)

Element-wise log1p.

See `numpy.log1p` for more information.

scipy.sparse.csr_matrix.max`csr_matrix.max` (*self*, *axis=None*, *out=None*)

Return the maximum of the matrix or maximum along an axis. This takes all elements into account, not just the non-zero ones.

Parameters

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the maximum over all the matrix elements, returning a scalar (i.e., *axis = None*).
- out** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

- amax** [coo_matrix or scalar] Maximum of *a*. If *axis* is None, the result is a scalar value. If *axis* is given, the result is a sparse.coo_matrix of dimension `a.ndim - 1`.

See also:***min***

The minimum value of a sparse matrix along a given axis.

numpy.matrix.max

NumPy's implementation of 'max' for matrices

scipy.sparse.csr_matrix.maximum`csr_matrix.maximum` (*self*, *other*)

Element-wise maximum between this and another matrix.

scipy.sparse.csr_matrix.mean

`csr_matrix.mean` (*self*, *axis=None*, *dtype=None*, *out=None*)

Compute the arithmetic mean along the specified axis.

Returns the average of the matrix elements. The average is taken over all elements in the matrix by default, otherwise over the specified axis. *float64* intermediate and return values are used for integer inputs.

Parameters

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the mean is computed. The default is to compute the mean of all elements in the matrix (i.e., *axis = None*).
- dtype** [data-type, optional] Type to use in computing the mean. For integer inputs, the default is *float64*; for floating point inputs, it is the same as the input dtype.
New in version 0.18.0.
- out** [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns

- m** [np.matrix]

See also:

[*numpy.matrix.mean*](#)

NumPy's implementation of 'mean' for matrices

scipy.sparse.csr_matrix.min

`csr_matrix.min` (*self*, *axis=None*, *out=None*)

Return the minimum of the matrix or maximum along an axis. This takes all elements into account, not just the non-zero ones.

Parameters

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the minimum over all the matrix elements, returning a scalar (i.e., *axis = None*).
- out** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value, as this argument is not used.

Returns

- amin** [coo_matrix or scalar] Minimum of *a*. If *axis* is None, the result is a scalar value. If *axis* is given, the result is a `sparse.coo_matrix` of dimension `a.ndim - 1`.

See also:

[*max*](#)

The maximum value of a sparse matrix along a given axis.

[*numpy.matrix.min*](#)

NumPy's implementation of 'min' for matrices

scipy.sparse.csr_matrix.minimum`csr_matrix.minimum(self, other)`

Element-wise minimum between this and another matrix.

scipy.sparse.csr_matrix.multiply`csr_matrix.multiply(self, other)`

Point-wise multiplication by another matrix, vector, or scalar.

scipy.sparse.csr_matrix.nonzero`csr_matrix.nonzero(self)`

nonzero indices

Returns a tuple of arrays (row,col) containing the indices of the non-zero elements of the matrix.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> A.nonzero()
(array([0, 0, 1, 2, 2]), array([0, 1, 2, 0, 2]))
```

scipy.sparse.csr_matrix.power`csr_matrix.power(self, n, dtype=None)`

This function performs element-wise power.

Parameters

n	[n is a scalar]
dtype	[If dtype is not specified, the current dtype will be preserved.]

scipy.sparse.csr_matrix.prune`csr_matrix.prune(self)`

Remove empty space after all non-zero elements.

scipy.sparse.csr_matrix.rad2deg`csr_matrix.rad2deg(self)`

Element-wise rad2deg.

See `numpy.rad2deg` for more information.

scipy.sparse.csr_matrix.reshape

`csr_matrix.reshape` (*self*, *shape*, *order='C'*, *copy=False*)

Gives a new shape to a sparse matrix without changing its data.

Parameters

shape	[length-2 tuple of ints] The new shape should be compatible with the original shape.
order	[{'C', 'F'}, optional] Read the elements using this index order. 'C' means to read and write the elements using C-like index order; e.g., read entire first row, then second row, etc. 'F' means to read and write the elements using Fortran-like index order; e.g., read entire first column, then second column, etc.
copy	[bool, optional] Indicates whether or not attributes of <i>self</i> should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns**reshaped_matrix**

[sparse matrix] A sparse matrix with the given *shape*, not necessarily of the same format as the current object.

See also:

[*numpy.matrix.reshape*](#)

NumPy's implementation of 'reshape' for matrices

scipy.sparse.csr_matrix.resize

`csr_matrix.resize` (*self*, **shape*)

Resize the matrix in-place to dimensions given by *shape*

Any elements that lie within the new shape will remain at the same indices, while non-zero elements lying outside the new shape are removed.

Parameters

shape	[(int, int)] number of rows and columns in the new matrix
--------------	---

Notes

The semantics are not identical to [`numpy.ndarray.resize`](#) or [`numpy.resize`](#). Here, the same data will be maintained at each index before and after reshape, if that index is within the new bounds. In `numpy`, resizing maintains contiguity of the array, moving elements around in the logical matrix but not within a flattened representation.

We give no guarantees about whether the underlying data attributes (arrays, etc.) will be modified in place or replaced with new objects.

scipy.sparse.csr_matrix.rint`csr_matrix.rint` (*self*)

Element-wise rint.

See `numpy.rint` for more information.**scipy.sparse.csr_matrix.set_shape**`csr_matrix.set_shape` (*self*, *shape*)See `reshape`.**scipy.sparse.csr_matrix.setdiag**`csr_matrix.setdiag` (*self*, *values*, *k=0*)

Set diagonal or off-diagonal elements of the array.

Parameters

- values** [array_like] New values of the diagonal elements.
Values may have any length. If the diagonal is longer than values, then the remaining diagonal entries will not be set. If values are longer than the diagonal, then the remaining values are ignored.
- k** [int, optional] Which off-diagonal to set, corresponding to elements `a[i,i+k]`. Default: 0 (the main diagonal).

scipy.sparse.csr_matrix.sign`csr_matrix.sign` (*self*)

Element-wise sign.

See `numpy.sign` for more information.**scipy.sparse.csr_matrix.sin**`csr_matrix.sin` (*self*)

Element-wise sin.

See `numpy.sin` for more information.**scipy.sparse.csr_matrix.sinh**`csr_matrix.sinh` (*self*)

Element-wise sinh.

See `numpy.sinh` for more information.

scipy.sparse.csr_matrix.sort_indices

`csr_matrix.sort_indices` (*self*)
Sort the indices of this matrix *in place*

scipy.sparse.csr_matrix.sorted_indices

`csr_matrix.sorted_indices` (*self*)
Return a copy of this matrix with sorted indices

scipy.sparse.csr_matrix.sqrt

`csr_matrix.sqrt` (*self*)
Element-wise sqrt.
See `numpy.sqrt` for more information.

scipy.sparse.csr_matrix.sum

`csr_matrix.sum` (*self*, *axis=None*, *dtype=None*, *out=None*)
Sum the matrix elements over a given axis.

Parameters

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the sum of all the matrix elements, returning a scalar (i.e., *axis = None*).
- dtype** [dtype, optional] The type of the returned matrix and of the accumulator in which the elements are summed. The dtype of *a* is used by default unless *a* has an integer dtype of less precision than the default platform integer. In that case, if *a* is signed then the platform integer is used while if *a* is unsigned then an unsigned integer of the same precision as the platform integer is used.
New in version 0.18.0.
- out** [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns

- sum_along_axis** [np.matrix] A matrix with the same shape as *self*, with the specified axis removed.

See also:

`numpy.matrix.sum`

NumPy's implementation of 'sum' for matrices

`scipy.sparse.csr_matrix.sum_duplicates`

`csr_matrix.sum_duplicates` (*self*)

Eliminate duplicate matrix entries by adding them together

This is an *in place* operation.

`scipy.sparse.csr_matrix.tan`

`csr_matrix.tan` (*self*)

Element-wise tan.

See `numpy.tan` for more information.

`scipy.sparse.csr_matrix.tanh`

`csr_matrix.tanh` (*self*)

Element-wise tanh.

See `numpy.tanh` for more information.

`scipy.sparse.csr_matrix.toarray`

`csr_matrix.toarray` (*self*, *order=None*, *out=None*)

Return a dense ndarray representation of this matrix.

Parameters

- order** [{"C", "F"}, optional] Whether to store multidimensional data in C (row-major) or Fortran (column-major) order in memory. The default is 'None', indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the *out* argument.
- out** [ndarray, 2-D, optional] If specified, uses this array as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method. For most sparse types, *out* is required to be memory contiguous (either C or Fortran ordered).

Returns

- arr** [ndarray, 2-D] An array with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If *out* was passed, the same object is returned after being modified in-place to contain the appropriate values.

`scipy.sparse.csr_matrix.tobsr`

`csr_matrix.tobsr` (*self*, *blocksize=None*, *copy=True*)

Convert this matrix to Block Sparse Row format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `bsr_matrix`.

When *blocksize=(R, C)* is provided, it will be used for construction of the `bsr_matrix`.

scipy.sparse.csr_matrix.tocoo`csr_matrix.tocoo` (*self*, *copy=True*)

Convert this matrix to COOrdinate format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `coo_matrix`.**scipy.sparse.csr_matrix.tocsc**`csr_matrix.tocsc` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Column format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `csc_matrix`.**scipy.sparse.csr_matrix.tocsr**`csr_matrix.tocsr` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Row format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `csr_matrix`.**scipy.sparse.csr_matrix.todense**`csr_matrix.todense` (*self*, *order=None*, *out=None*)

Return a dense matrix representation of this matrix.

Parameters

- order** [{"C", "F"}, optional] Whether to store multi-dimensional data in C (row-major) or Fortran (column-major) order in memory. The default is 'None', indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the *out* argument.
- out** [ndarray, 2-D, optional] If specified, uses this array (or `numpy.matrix`) as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method.

Returns

- arr** [numpy.matrix, 2-D] A NumPy matrix object with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If *out* was passed and was an array (rather than a `numpy.matrix`), it will be filled with the appropriate values and returned wrapped in a `numpy.matrix` object that shares the same memory.

scipy.sparse.csr_matrix.todia`csr_matrix.todia` (*self*, *copy=False*)

Convert this matrix to sparse DIAGONal format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dia_matrix`.

scipy.sparse.csr_matrix.todok

`csr_matrix.todok` (*self*, *copy=False*)

Convert this matrix to Dictionary Of Keys format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dok_matrix`.

scipy.sparse.csr_matrix.tolil

`csr_matrix.tolil` (*self*, *copy=False*)

Convert this matrix to List of Lists format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `lil_matrix`.

scipy.sparse.csr_matrix.transpose

`csr_matrix.transpose` (*self*, *axes=None*, *copy=False*)

Reverses the dimensions of the sparse matrix.

Parameters

- axes** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value.
- copy** [bool, optional] Indicates whether or not attributes of *self* should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns

- p** [*self* with the dimensions reversed.]

See also:

[*numpy.matrix.transpose*](#)

NumPy's implementation of 'transpose' for matrices

scipy.sparse.csr_matrix.trunc

`csr_matrix.trunc` (*self*)

Element-wise trunc.

See [`numpy.trunc`](#) for more information.

<code>__getitem__</code>	
--------------------------	--

scipy.sparse.dia_matrix

class `scipy.sparse.dia_matrix` (*arg1*, *shape=None*, *dtype=None*, *copy=False*)
 Sparse matrix with DIAgonal storage

This can be instantiated in several ways:

dia_matrix(D)

with a dense matrix

dia_matrix(S)

with another sparse matrix S (equivalent to S.todia())

dia_matrix((M, N), [dtype])

to construct an empty matrix with shape (M, N), dtype is optional, defaulting to dtype='d'.

dia_matrix((data, offsets), shape=(M, N))

where the `data[k, :]` stores the diagonal entries for diagonal `offsets[k]` (See example below)

Notes

Sparse matrices can be used in arithmetic operations: they support addition, subtraction, multiplication, division, and matrix power.

Examples

```
>>> import numpy as np
>>> from scipy.sparse import dia_matrix
>>> dia_matrix((3, 4), dtype=np.int8).toarray()
array([[0, 0, 0, 0],
       [0, 0, 0, 0],
       [0, 0, 0, 0]], dtype=int8)
```

```
>>> data = np.array([[1, 2, 3, 4]]).repeat(3, axis=0)
>>> offsets = np.array([0, -1, 2])
>>> dia_matrix((data, offsets), shape=(4, 4)).toarray()
array([[1, 0, 3, 0],
       [1, 2, 0, 4],
       [0, 2, 3, 0],
       [0, 0, 3, 4]])
```

```
>>> from scipy.sparse import dia_matrix
>>> n = 10
>>> ex = np.ones(n)
>>> data = np.array([ex, 2 * ex, ex])
>>> offsets = np.array([-1, 0, 1])
>>> dia_matrix((data, offsets), shape=(n, n)).toarray()
array([[2., 1., 0., ..., 0., 0., 0.],
       [1., 2., 1., ..., 0., 0., 0.],
       [0., 1., 2., ..., 0., 0., 0.]])
```

(continues on next page)

(continued from previous page)

```

... ,
[0., 0., 0., ..., 2., 1., 0.],
[0., 0., 0., ..., 1., 2., 1.],
[0., 0., 0., ..., 0., 1., 2.]])

```

Attributes

- dtype** [dtype] Data type of the matrix
- shape** [2-tuple] Get shape of a matrix.
- ndim** [int] Number of dimensions (this is always 2)
- nnz** Number of stored values, including explicit zeros.
- data** DIA format data array of the matrix
- offsets** DIA format offset array of the matrix

Methods

<code>__len__(self)</code>	
<code>__mul__(self, other)</code>	interpret other and call one of the following
<code>arcsin(self)</code>	Element-wise arcsin.
<code>arcsinh(self)</code>	Element-wise arcsinh.
<code>arctan(self)</code>	Element-wise arctan.
<code>arctanh(self)</code>	Element-wise arctanh.
<code>asformat(self, format[, copy])</code>	Return this matrix in the passed format.
<code>asfptype(self)</code>	Upcast matrix to a floating point format (if necessary)
<code>astype(self, dtype[, casting, copy])</code>	Cast the matrix elements to a specified type.
<code>ceil(self)</code>	Element-wise ceil.
<code>conj(self[, copy])</code>	Element-wise complex conjugation.
<code>conjugate(self[, copy])</code>	Element-wise complex conjugation.
<code>copy(self)</code>	Returns a copy of this matrix.
<code>count_nonzero(self)</code>	Number of non-zero entries, equivalent to
<code>deg2rad(self)</code>	Element-wise deg2rad.
<code>diagonal(self[, k])</code>	Returns the kth diagonal of the matrix.
<code>dot(self, other)</code>	Ordinary dot product
<code>expm1(self)</code>	Element-wise expm1.
<code>floor(self)</code>	Element-wise floor.
<code>getH(self)</code>	Return the Hermitian transpose of this matrix.
<code>get_shape(self)</code>	Get shape of a matrix.
<code>getcol(self, j)</code>	Returns a copy of column j of the matrix, as an (m x 1) sparse matrix (column vector).
<code>getformat(self)</code>	Format of a matrix representation as a string.
<code>getmaxprint(self)</code>	Maximum number of elements to display when printed.
<code>getnnz(self[, axis])</code>	Number of stored values, including explicit zeros.
<code>getrow(self, i)</code>	Returns a copy of row i of the matrix, as a (1 x n) sparse matrix (row vector).
<code>log1p(self)</code>	Element-wise log1p.
<code>maximum(self, other)</code>	Element-wise maximum between this and another matrix.
<code>mean(self[, axis, dtype, out])</code>	Compute the arithmetic mean along the specified axis.

continues on next page

Table 177 – continued from previous page

<i>minimum</i> (self, other)	Element-wise minimum between this and another matrix.
<i>multiply</i> (self, other)	Point-wise multiplication by another matrix
<i>nonzero</i> (self)	nonzero indices
<i>power</i> (self, n[, dtype])	This function performs element-wise power.
<i>rad2deg</i> (self)	Element-wise rad2deg.
<i>reshape</i> (self, shape[, order, copy])	Gives a new shape to a sparse matrix without changing its data.
<i>resize</i> (self, *shape)	Resize the matrix in-place to dimensions given by shape
<i>rint</i> (self)	Element-wise rint.
<i>set_shape</i> (self, shape)	See <i>reshape</i> .
<i>setdiag</i> (self, values[, k])	Set diagonal or off-diagonal elements of the array.
<i>sign</i> (self)	Element-wise sign.
<i>sin</i> (self)	Element-wise sin.
<i>sinh</i> (self)	Element-wise sinh.
<i>sqrt</i> (self)	Element-wise sqrt.
<i>sum</i> (self[, axis, dtype, out])	Sum the matrix elements over a given axis.
<i>tan</i> (self)	Element-wise tan.
<i>tanh</i> (self)	Element-wise tanh.
<i>toarray</i> (self[, order, out])	Return a dense ndarray representation of this matrix.
<i>tobsr</i> (self[, blocksize, copy])	Convert this matrix to Block Sparse Row format.
<i>tocoo</i> (self[, copy])	Convert this matrix to COOrdinate format.
<i>tocsc</i> (self[, copy])	Convert this matrix to Compressed Sparse Column format.
<i>tocsr</i> (self[, copy])	Convert this matrix to Compressed Sparse Row format.
<i>todense</i> (self[, order, out])	Return a dense matrix representation of this matrix.
<i>todia</i> (self[, copy])	Convert this matrix to sparse DIAgonal format.
<i>todok</i> (self[, copy])	Convert this matrix to Dictionary Of Keys format.
<i>tolil</i> (self[, copy])	Convert this matrix to List of Lists format.
<i>transpose</i> (self[, axes, copy])	Reverses the dimensions of the sparse matrix.
<i>trunc</i> (self)	Element-wise trunc.

scipy.sparse.dia_matrix.__len__

`dia_matrix.__len__(self)`

scipy.sparse.dia_matrix.__mul__

`dia_matrix.__mul__(self, other)`

interpret other and call one of the following

`self._mul_scalar()` `self._mul_vector()` `self._mul_multivector()` `self._mul_sparse_matrix()`

scipy.sparse.dia_matrix.arcsin

`dia_matrix.arcsin` (*self*)

Element-wise arcsin.

See `numpy.arcsin` for more information.

scipy.sparse.dia_matrix.arcsinh

`dia_matrix.arcsinh` (*self*)

Element-wise arcsinh.

See `numpy.arcsinh` for more information.

scipy.sparse.dia_matrix.arctan

`dia_matrix.arctan` (*self*)

Element-wise arctan.

See `numpy.arctan` for more information.

scipy.sparse.dia_matrix.arctanh

`dia_matrix.arctanh` (*self*)

Element-wise arctanh.

See `numpy.arctanh` for more information.

scipy.sparse.dia_matrix.asformat

`dia_matrix.asformat` (*self*, *format*, *copy=False*)

Return this matrix in the passed format.

Parameters

- format** [{str, None}] The desired matrix format (“csr”, “csc”, “lil”, “dok”, “array”, ...) or None for no conversion.
- copy** [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

- A** [This matrix in the passed format.]

scipy.sparse.dia_matrix.asfptype

`dia_matrix.asfptype` (*self*)
Upcast matrix to a floating point format (if necessary)

scipy.sparse.dia_matrix.astype

`dia_matrix.astype` (*self*, *dtype*, *casting='unsafe'*, *copy=True*)
Cast the matrix elements to a specified type.

Parameters

dtype [string or numpy dtype] Typecode or data-type to which to cast the data.
casting [{‘no’, ‘equiv’, ‘safe’, ‘same_kind’, ‘unsafe’}, optional] Controls what kind of data casting may occur. Defaults to ‘unsafe’ for backwards compatibility. ‘no’ means the data types should not be cast at all. ‘equiv’ means only byte-order changes are allowed. ‘safe’ means only casts which can preserve values are allowed. ‘same_kind’ means only safe casts or casts within a kind, like float64 to float32, are allowed. ‘unsafe’ means any data conversions may be done.
copy [bool, optional] If *copy* is *False*, the result might share some memory with this matrix. If *copy* is *True*, it is guaranteed that the result and this matrix do not share any memory.

scipy.sparse.dia_matrix.ceil

`dia_matrix.ceil` (*self*)
Element-wise ceil.
See `numpy.ceil` for more information.

scipy.sparse.dia_matrix.conj

`dia_matrix.conj` (*self*, *copy=True*)
Element-wise complex conjugation.

If the matrix is of non-complex data type and *copy* is *False*, this method does nothing and the data is not copied.

Parameters

copy [bool, optional] If *True*, the result is guaranteed to not share data with self.

Returns

A [The element-wise complex conjugate.]

scipy.sparse.dia_matrix.conjugate`dia_matrix.conjugate` (*self*, *copy=True*)

Element-wise complex conjugation.

If the matrix is of non-complex data type and *copy* is `False`, this method does nothing and the data is not copied.

Parameters**copy** [bool, optional] If `True`, the result is guaranteed to not share data with *self*.**Returns****A** [The element-wise complex conjugate.]**scipy.sparse.dia_matrix.copy**`dia_matrix.copy` (*self*)

Returns a copy of this matrix.

No data/indices will be shared between the returned value and current matrix.

scipy.sparse.dia_matrix.count_nonzero`dia_matrix.count_nonzero` (*self*)

Number of non-zero entries, equivalent to

`np.count_nonzero(a.toarray())`

Unlike `getnnz()` and the `nnz` property, which return the number of stored entries (the length of the data attribute), this method counts the actual number of non-zero entries in data.

scipy.sparse.dia_matrix.deg2rad`dia_matrix.deg2rad` (*self*)Element-wise `deg2rad`.

See `numpy.deg2rad` for more information.

scipy.sparse.dia_matrix.diagonal`dia_matrix.diagonal` (*self*, *k=0*)Returns the *k*th diagonal of the matrix.**Parameters****k** [int, optional] Which diagonal to get, corresponding to elements `a[i, i+k]`. Default: 0 (the main diagonal).
New in version 1.0.**See also:**`numpy.diagonal`Equivalent `numpy` function.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> A.diagonal()
array([1, 0, 5])
>>> A.diagonal(k=1)
array([2, 3])
```

scipy.sparse.dia_matrix.dot

`dia_matrix.dot` (*self*, *other*)
Ordinary dot product

Examples

```
>>> import numpy as np
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> v = np.array([1, 0, -1])
>>> A.dot(v)
array([ 1, -3, -1], dtype=int64)
```

scipy.sparse.dia_matrix.expm1

`dia_matrix.expm1` (*self*)
Element-wise `expm1`.
See `numpy.expm1` for more information.

scipy.sparse.dia_matrix.floor

`dia_matrix.floor` (*self*)
Element-wise floor.
See `numpy.floor` for more information.

scipy.sparse.dia_matrix.getH

`dia_matrix.getH` (*self*)
Return the Hermitian transpose of this matrix.

See also:

`numpy.matrix.getH`

NumPy's implementation of `getH` for matrices

scipy.sparse.dia_matrix.get_shape

`dia_matrix.get_shape` (*self*)
Get shape of a matrix.

scipy.sparse.dia_matrix.getcol

`dia_matrix.getcol` (*self*, *j*)
Returns a copy of column *j* of the matrix, as an (m x 1) sparse matrix (column vector).

scipy.sparse.dia_matrix.getformat

`dia_matrix.getformat` (*self*)
Format of a matrix representation as a string.

scipy.sparse.dia_matrix.getmaxprint

`dia_matrix.getmaxprint` (*self*)
Maximum number of elements to display when printed.

scipy.sparse.dia_matrix.getnnz

`dia_matrix.getnnz` (*self*, *axis=None*)
Number of stored values, including explicit zeros.

Parameters

axis [None, 0, or 1] Select between the number of values across the whole matrix, in each column, or in each row.

See also:***count_nonzero***

Number of non-zero entries

scipy.sparse.dia_matrix.getrow

`dia_matrix.getrow` (*self*, *i*)
Returns a copy of row *i* of the matrix, as a (1 x n) sparse matrix (row vector).

scipy.sparse.dia_matrix.log1p`dia_matrix.log1p(self)`

Element-wise log1p.

See `numpy.log1p` for more information.**scipy.sparse.dia_matrix.maximum**`dia_matrix.maximum(self, other)`

Element-wise maximum between this and another matrix.

scipy.sparse.dia_matrix.mean`dia_matrix.mean(self, axis=None, dtype=None, out=None)`

Compute the arithmetic mean along the specified axis.

Returns the average of the matrix elements. The average is taken over all elements in the matrix by default, otherwise over the specified axis. *float64* intermediate and return values are used for integer inputs.**Parameters**

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the mean is computed. The default is to compute the mean of all elements in the matrix (i.e., *axis = None*).
- dtype** [data-type, optional] Type to use in computing the mean. For integer inputs, the default is *float64*; for floating point inputs, it is the same as the input dtype.
New in version 0.18.0.
- out** [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns

- m** [np.matrix]

See also:*numpy.matrix.mean*

NumPy's implementation of 'mean' for matrices

scipy.sparse.dia_matrix.minimum`dia_matrix.minimum(self, other)`

Element-wise minimum between this and another matrix.

scipy.sparse.dia_matrix.multiply

`dia_matrix.multiply` (*self*, *other*)
 Point-wise multiplication by another matrix

scipy.sparse.dia_matrix.nonzero

`dia_matrix.nonzero` (*self*)
 nonzero indices
 Returns a tuple of arrays (row,col) containing the indices of the non-zero elements of the matrix.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> A.nonzero()
(array([0, 0, 1, 2, 2]), array([0, 1, 2, 0, 2]))
```

scipy.sparse.dia_matrix.power

`dia_matrix.power` (*self*, *n*, *dtype=None*)
 This function performs element-wise power.

Parameters

n [n is a scalar]
dtype [If dtype is not specified, the current dtype will be preserved.]

scipy.sparse.dia_matrix.rad2deg

`dia_matrix.rad2deg` (*self*)
 Element-wise rad2deg.
 See `numpy.rad2deg` for more information.

scipy.sparse.dia_matrix.reshape

`dia_matrix.reshape` (*self*, *shape*, *order='C'*, *copy=False*)
 Gives a new shape to a sparse matrix without changing its data.

Parameters

shape [length-2 tuple of ints] The new shape should be compatible with the original shape.
order [{'C', 'F'}, optional] Read the elements using this index order. 'C' means to read and write the elements using C-like index order; e.g., read entire first row, then second row, etc. 'F' means to read and write the elements using Fortran-like index order; e.g., read entire first column, then second column, etc.
copy [bool, optional] Indicates whether or not attributes of self should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns**reshaped_matrix**

[sparse matrix] A sparse matrix with the given `shape`, not necessarily of the same format as the current object.

See also:

`numpy.matrix.reshape`

NumPy's implementation of 'reshape' for matrices

scipy.sparse.dia_matrix.resize

`dia_matrix.resize` (*self*, **shape*)

Resize the matrix in-place to dimensions given by `shape`

Any elements that lie within the new shape will remain at the same indices, while non-zero elements lying outside the new shape are removed.

Parameters

shape [(int, int)] number of rows and columns in the new matrix

Notes

The semantics are not identical to `numpy.ndarray.resize` or `numpy.resize`. Here, the same data will be maintained at each index before and after reshape, if that index is within the new bounds. In numpy, resizing maintains contiguity of the array, moving elements around in the logical matrix but not within a flattened representation.

We give no guarantees about whether the underlying data attributes (arrays, etc.) will be modified in place or replaced with new objects.

scipy.sparse.dia_matrix.rint

`dia_matrix.rint` (*self*)

Element-wise rint.

See `numpy.rint` for more information.

scipy.sparse.dia_matrix.set_shape

`dia_matrix.set_shape` (*self*, *shape*)

See `reshape`.

scipy.sparse.dia_matrix.setdiag`dia_matrix.setdiag` (*self*, *values*, *k=0*)

Set diagonal or off-diagonal elements of the array.

Parameters

- values** [array_like] New values of the diagonal elements.
Values may have any length. If the diagonal is longer than values, then the remaining diagonal entries will not be set. If values are longer than the diagonal, then the remaining values are ignored.
If a scalar value is given, all of the diagonal is set to it.
- k** [int, optional] Which off-diagonal to set, corresponding to elements $a[i,i+k]$. Default: 0 (the main diagonal).

scipy.sparse.dia_matrix.sign`dia_matrix.sign` (*self*)

Element-wise sign.

See `numpy.sign` for more information.**scipy.sparse.dia_matrix.sin**`dia_matrix.sin` (*self*)

Element-wise sin.

See `numpy.sin` for more information.**scipy.sparse.dia_matrix.sinh**`dia_matrix.sinh` (*self*)

Element-wise sinh.

See `numpy.sinh` for more information.**scipy.sparse.dia_matrix.sqrt**`dia_matrix.sqrt` (*self*)

Element-wise sqrt.

See `numpy.sqrt` for more information.

scipy.sparse.dia_matrix.sum

`dia_matrix.sum` (*self*, *axis=None*, *dtype=None*, *out=None*)

Sum the matrix elements over a given axis.

Parameters

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the sum of all the matrix elements, returning a scalar (i.e., *axis = None*).
- dtype** [dtype, optional] The type of the returned matrix and of the accumulator in which the elements are summed. The dtype of *a* is used by default unless *a* has an integer dtype of less precision than the default platform integer. In that case, if *a* is signed then the platform integer is used while if *a* is unsigned then an unsigned integer of the same precision as the platform integer is used.
New in version 0.18.0.
- out** [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns**sum_along_axis**

[np.matrix] A matrix with the same shape as *self*, with the specified axis removed.

See also:

[*numpy.matrix.sum*](#)

NumPy's implementation of 'sum' for matrices

scipy.sparse.dia_matrix.tan

`dia_matrix.tan` (*self*)

Element-wise tan.

See [`numpy.tan`](#) for more information.

scipy.sparse.dia_matrix.tanh

`dia_matrix.tanh` (*self*)

Element-wise tanh.

See [`numpy.tanh`](#) for more information.

scipy.sparse.dia_matrix.toarray

`dia_matrix.toarray` (*self*, *order=None*, *out=None*)

Return a dense ndarray representation of this matrix.

Parameters

- order** [{"C", "F"}, optional] Whether to store multidimensional data in C (row-major) or Fortran (column-major) order in memory. The default is 'None', indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the *out* argument.
- out** [ndarray, 2-D, optional] If specified, uses this array as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method. For most sparse types, *out* is required to be memory contiguous (either C or Fortran ordered).

Returns

- arr** [ndarray, 2-D] An array with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If *out* was passed, the same object is returned after being modified in-place to contain the appropriate values.

scipy.sparse.dia_matrix.tobsr

`dia_matrix.tobsr` (*self*, *blocksize=None*, *copy=False*)

Convert this matrix to Block Sparse Row format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `bsr_matrix`.

When *blocksize=(R, C)* is provided, it will be used for construction of the `bsr_matrix`.

scipy.sparse.dia_matrix.tocoo

`dia_matrix.tocoo` (*self*, *copy=False*)

Convert this matrix to COOrdinate format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `coo_matrix`.

scipy.sparse.dia_matrix.tocsc

`dia_matrix.tocsc` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Column format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `csc_matrix`.

scipy.sparse.dia_matrix.tocsr`dia_matrix.tocsr` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Row format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `csr_matrix`.**scipy.sparse.dia_matrix.todense**`dia_matrix.todense` (*self*, *order=None*, *out=None*)

Return a dense matrix representation of this matrix.

Parameters

- order** [{"C", "F"}, optional] Whether to store multi-dimensional data in C (row-major) or Fortran (column-major) order in memory. The default is 'None', indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the *out* argument.
- out** [ndarray, 2-D, optional] If specified, uses this array (or `numpy.matrix`) as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method.

Returns

- arr** [numpy.matrix, 2-D] A NumPy matrix object with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If *out* was passed and was an array (rather than a `numpy.matrix`), it will be filled with the appropriate values and returned wrapped in a `numpy.matrix` object that shares the same memory.

scipy.sparse.dia_matrix.todia`dia_matrix.todia` (*self*, *copy=False*)

Convert this matrix to sparse DIAGONAL format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dia_matrix`.**scipy.sparse.dia_matrix.todok**`dia_matrix.todok` (*self*, *copy=False*)

Convert this matrix to Dictionary Of Keys format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dok_matrix`.**scipy.sparse.dia_matrix.tolil**`dia_matrix.tolil` (*self*, *copy=False*)

Convert this matrix to List of Lists format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `lil_matrix`.

scipy.sparse.dia_matrix.transpose

`dia_matrix.transpose` (*self*, *axes=None*, *copy=False*)

Reverses the dimensions of the sparse matrix.

Parameters

- axes** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value.
- copy** [bool, optional] Indicates whether or not attributes of *self* should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns

- p** [*self* with the dimensions reversed.]

See also:

[*numpy.matrix.transpose*](#)

NumPy's implementation of 'transpose' for matrices

scipy.sparse.dia_matrix.trunc

`dia_matrix.trunc` (*self*)

Element-wise trunc.

See [`numpy.trunc`](#) for more information.

scipy.sparse.dok_matrix

class `scipy.sparse.dok_matrix` (*arg1*, *shape=None*, *dtype=None*, *copy=False*)

Dictionary Of Keys based sparse matrix.

This is an efficient structure for constructing sparse matrices incrementally.

This can be instantiated in several ways:

dok_matrix(D)

with a dense matrix, D

dok_matrix(S)

with a sparse matrix, S

dok_matrix((M,N), [dtype])

create the matrix with initial shape (M,N) dtype is optional, defaulting to dtype='d'

Notes

Sparse matrices can be used in arithmetic operations: they support addition, subtraction, multiplication, division, and matrix power.

Allows for efficient O(1) access of individual elements. Duplicates are not allowed. Can be efficiently converted to a `coo_matrix` once constructed.

Examples

```
>>> import numpy as np
>>> from scipy.sparse import dok_matrix
>>> S = dok_matrix((5, 5), dtype=np.float32)
>>> for i in range(5):
...     for j in range(5):
...         S[i, j] = i + j      # Update element
```

Attributes

dtype	[dtype] Data type of the matrix
shape	[2-tuple] Get shape of a matrix.
ndim	[int] Number of dimensions (this is always 2)
nnz	Number of stored values, including explicit zeros.

Methods

<code>__len__(self)</code>	Return <code>len(self)</code> .
<code>__mul__(self, other)</code>	interpret other and call one of the following
<code>asformat(self, format[, copy])</code>	Return this matrix in the passed format.
<code>asfptype(self)</code>	Upcast matrix to a floating point format (if necessary)
<code>astype(self, dtype[, casting, copy])</code>	Cast the matrix elements to a specified type.
<code>clear()</code>	
<code>conj(self[, copy])</code>	Element-wise complex conjugation.
<code>conjtransp(self)</code>	Return the conjugate transpose.
<code>conjugate(self[, copy])</code>	Element-wise complex conjugation.
<code>copy(self)</code>	Returns a copy of this matrix.
<code>count_nonzero(self)</code>	Number of non-zero entries, equivalent to
<code>diagonal(self[, k])</code>	Returns the kth diagonal of the matrix.
<code>dot(self, other)</code>	Ordinary dot product
<code>fromkeys(iterable[, value])</code>	Create a new dictionary with keys from iterable and values set to value.
<code>get(self, key[, default])</code>	This overrides the dict.get method, providing type checking but otherwise equivalent functionality.
<code>getH(self)</code>	Return the Hermitian transpose of this matrix.
<code>get_shape(self)</code>	Get shape of a matrix.
<code>getcol(self, j)</code>	Returns a copy of column j of the matrix, as an (m x 1) sparse matrix (column vector).
<code>getformat(self)</code>	Format of a matrix representation as a string.
<code>getmaxprint(self)</code>	Maximum number of elements to display when printed.

continues on next page

Table 178 – continued from previous page

<code>getnnz(self[, axis])</code>	Number of stored values, including explicit zeros.
<code>getrow(self, i)</code>	Returns a copy of row <i>i</i> of the matrix, as a (1 x n) sparse matrix (row vector).
<code>items()</code>	
<code>keys()</code>	
<code>maximum(self, other)</code>	Element-wise maximum between this and another matrix.
<code>mean(self[, axis, dtype, out])</code>	Compute the arithmetic mean along the specified axis.
<code>minimum(self, other)</code>	Element-wise minimum between this and another matrix.
<code>multiply(self, other)</code>	Point-wise multiplication by another matrix
<code>nonzero(self)</code>	nonzero indices
<code>pop()</code>	If key is not found, <i>d</i> is returned if given, otherwise <code>KeyError</code> is raised
<code>popitem(self, /)</code>	Remove and return a (key, value) pair as a 2-tuple.
<code>power(self, n[, dtype])</code>	Element-wise power.
<code>reshape(self, shape[, order, copy])</code>	Gives a new shape to a sparse matrix without changing its data.
<code>resize(self, *shape)</code>	Resize the matrix in-place to dimensions given by <i>shape</i>
<code>set_shape(self, shape)</code>	See reshape .
<code>setdefault(self, key[, default])</code>	Insert key with a value of <i>default</i> if key is not in the dictionary.
<code>setdiag(self, values[, k])</code>	Set diagonal or off-diagonal elements of the array.
<code>sum(self[, axis, dtype, out])</code>	Sum the matrix elements over a given axis.
<code>toarray(self[, order, out])</code>	Return a dense ndarray representation of this matrix.
<code>tobsr(self[, blocksize, copy])</code>	Convert this matrix to Block Sparse Row format.
<code>tocoo(self[, copy])</code>	Convert this matrix to COOrdinate format.
<code>tocsc(self[, copy])</code>	Convert this matrix to Compressed Sparse Column format.
<code>tocsr(self[, copy])</code>	Convert this matrix to Compressed Sparse Row format.
<code>todense(self[, order, out])</code>	Return a dense matrix representation of this matrix.
<code>todia(self[, copy])</code>	Convert this matrix to sparse DIAgonal format.
<code>todok(self[, copy])</code>	Convert this matrix to Dictionary Of Keys format.
<code>tolil(self[, copy])</code>	Convert this matrix to List of Lists format.
<code>transpose(self[, axes, copy])</code>	Reverses the dimensions of the sparse matrix.
<code>update(self, val)</code>	If <i>E</i> is present and has a <code>.keys()</code> method, then does: for <i>k</i> in <i>E</i> : $D[k] = E[k]$ If <i>E</i> is present and lacks a <code>.keys()</code> method, then does: for <i>k</i> , <i>v</i> in <i>E</i> : $D[k] = v$ In either case, this is followed by: for <i>k</i> in <i>F</i> : $D[k] = F[k]$
<code>values()</code>	

scipy.sparse.dok_matrix.__len__

`dok_matrix.__len__` (*self*)
Return len(*self*).

scipy.sparse.dok_matrix.__mul__

`dok_matrix.__mul__` (*self*, *other*)
interpret *other* and call one of the following
`self._mul_scalar()` `self._mul_vector()` `self._mul_multivector()` `self._mul_sparse_matrix()`

scipy.sparse.dok_matrix.asformat

`dok_matrix.asformat` (*self*, *format*, *copy=False*)
Return this matrix in the passed format.

Parameters

format [{str, None}] The desired matrix format (“csr”, “csc”, “lil”, “dok”, “array”, ...) or None for no conversion.
copy [bool, optional] If True, the result is guaranteed to not share data with *self*.

Returns

A [This matrix in the passed format.]

scipy.sparse.dok_matrix.asfptype

`dok_matrix.asfptype` (*self*)
Upcast matrix to a floating point format (if necessary)

scipy.sparse.dok_matrix.astype

`dok_matrix.astype` (*self*, *dtype*, *casting='unsafe'*, *copy=True*)
Cast the matrix elements to a specified type.

Parameters

dtype [string or numpy dtype] Typecode or data-type to which to cast the data.
casting [{‘no’, ‘equiv’, ‘safe’, ‘same_kind’, ‘unsafe’}, optional] Controls what kind of data casting may occur. Defaults to ‘unsafe’ for backwards compatibility. ‘no’ means the data types should not be cast at all. ‘equiv’ means only byte-order changes are allowed. ‘safe’ means only casts which can preserve values are allowed. ‘same_kind’ means only safe casts or casts within a kind, like float64 to float32, are allowed. ‘unsafe’ means any data conversions may be done.
copy [bool, optional] If *copy* is *False*, the result might share some memory with this matrix. If *copy* is *True*, it is guaranteed that the result and this matrix do not share any memory.

scipy.sparse.dok_matrix.clear`dok_matrix.clear()`**scipy.sparse.dok_matrix.conj**`dok_matrix.conj(self, copy=True)`
Element-wise complex conjugation.

If the matrix is of non-complex data type and `copy` is False, this method does nothing and the data is not copied.

Parameters

copy [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

A [The element-wise complex conjugate.]

scipy.sparse.dok_matrix.conjtransp`dok_matrix.conjtransp(self)`
Return the conjugate transpose.**scipy.sparse.dok_matrix.conjugate**`dok_matrix.conjugate(self, copy=True)`
Element-wise complex conjugation.

If the matrix is of non-complex data type and `copy` is False, this method does nothing and the data is not copied.

Parameters

copy [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

A [The element-wise complex conjugate.]

scipy.sparse.dok_matrix.copy`dok_matrix.copy(self)`
Returns a copy of this matrix.

No data/indices will be shared between the returned value and current matrix.

scipy.sparse.dok_matrix.count_nonzero`dok_matrix.count_nonzero` (*self*)

Number of non-zero entries, equivalent to

`np.count_nonzero(a.toarray())`

Unlike `getnnz()` and the `nnz` property, which return the number of stored entries (the length of the data attribute), this method counts the actual number of non-zero entries in data.

scipy.sparse.dok_matrix.diagonal`dok_matrix.diagonal` (*self*, *k=0*)Returns the *k*th diagonal of the matrix.**Parameters**

k [int, optional] Which diagonal to get, corresponding to elements `a[i, i+k]`. Default: 0 (the main diagonal).
New in version 1.0.

See also:*numpy.diagonal*

Equivalent numpy function.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> A.diagonal()
array([1, 0, 5])
>>> A.diagonal(k=1)
array([2, 3])
```

scipy.sparse.dok_matrix.dot`dok_matrix.dot` (*self*, *other*)

Ordinary dot product

Examples

```
>>> import numpy as np
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> v = np.array([1, 0, -1])
>>> A.dot(v)
array([ 1, -3, -1], dtype=int64)
```

scipy.sparse.dok_matrix.fromkeys

`dok_matrix.fromkeys` (*iterable*, *value=None*, /)
Create a new dictionary with keys from *iterable* and values set to *value*.

scipy.sparse.dok_matrix.get

`dok_matrix.get` (*self*, *key*, *default=0.0*)
This overrides the `dict.get` method, providing type checking but otherwise equivalent functionality.

scipy.sparse.dok_matrix.getH

`dok_matrix.getH` (*self*)
Return the Hermitian transpose of this matrix.

See also:

numpy.matrix.getH

NumPy's implementation of *getH* for matrices

scipy.sparse.dok_matrix.get_shape

`dok_matrix.get_shape` (*self*)
Get shape of a matrix.

scipy.sparse.dok_matrix.getcol

`dok_matrix.getcol` (*self*, *j*)
Returns a copy of column *j* of the matrix, as an (m x 1) sparse matrix (column vector).

scipy.sparse.dok_matrix.getformat

`dok_matrix.getformat` (*self*)
Format of a matrix representation as a string.

scipy.sparse.dok_matrix.getmaxprint

`dok_matrix.getmaxprint` (*self*)
Maximum number of elements to display when printed.

scipy.sparse.dok_matrix.getnnz

`dok_matrix.getnnz` (*self*, *axis=None*)

Number of stored values, including explicit zeros.

Parameters

axis [None, 0, or 1] Select between the number of values across the whole matrix, in each column, or in each row.

See also:*count_nonzero*

Number of non-zero entries

scipy.sparse.dok_matrix.getrow

`dok_matrix.getrow` (*self*, *i*)

Returns a copy of row *i* of the matrix, as a (1 x n) sparse matrix (row vector).

scipy.sparse.dok_matrix.items

`dok_matrix.items` ()

scipy.sparse.dok_matrix.keys

`dok_matrix.keys` ()

scipy.sparse.dok_matrix.maximum

`dok_matrix.maximum` (*self*, *other*)

Element-wise maximum between this and another matrix.

scipy.sparse.dok_matrix.mean

`dok_matrix.mean` (*self*, *axis=None*, *dtype=None*, *out=None*)

Compute the arithmetic mean along the specified axis.

Returns the average of the matrix elements. The average is taken over all elements in the matrix by default, otherwise over the specified axis. *float64* intermediate and return values are used for integer inputs.

Parameters

axis [{-2, -1, 0, 1, None} optional] Axis along which the mean is computed. The default is to compute the mean of all elements in the matrix (i.e., *axis = None*).

dtype [data-type, optional] Type to use in computing the mean. For integer inputs, the default is *float64*; for floating point inputs, it is the same as the input dtype.
New in version 0.18.0.

out [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns

m [np.matrix]

See also:

numpy.matrix.mean

NumPy's implementation of 'mean' for matrices

scipy.sparse.dok_matrix.minimum

`dok_matrix.minimum` (*self*, *other*)
Element-wise minimum between this and another matrix.

scipy.sparse.dok_matrix.multiply

`dok_matrix.multiply` (*self*, *other*)
Point-wise multiplication by another matrix

scipy.sparse.dok_matrix.nonzero

`dok_matrix.nonzero` (*self*)
nonzero indices
Returns a tuple of arrays (row,col) containing the indices of the non-zero elements of the matrix.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1,2,0],[0,0,3],[4,0,5]])
>>> A.nonzero()
(array([0, 0, 1, 2, 2]), array([0, 1, 2, 0, 2]))
```

scipy.sparse.dok_matrix.pop

`dok_matrix.pop` ()
If key is not found, d is returned if given, otherwise KeyError is raised

scipy.sparse.dok_matrix.popitem`dok_matrix.popitem` (*self*, /)

Remove and return a (key, value) pair as a 2-tuple.

Pairs are returned in LIFO (last-in, first-out) order. Raises `KeyError` if the dict is empty.**scipy.sparse.dok_matrix.power**`dok_matrix.power` (*self*, *n*, *dtype=None*)

Element-wise power.

scipy.sparse.dok_matrix.reshape`dok_matrix.reshape` (*self*, *shape*, *order='C'*, *copy=False*)

Gives a new shape to a sparse matrix without changing its data.

Parameters

shape	[length-2 tuple of ints] The new shape should be compatible with the original shape.
order	[{'C', 'F'}, optional] Read the elements using this index order. 'C' means to read and write the elements using C-like index order; e.g., read entire first row, then second row, etc. 'F' means to read and write the elements using Fortran-like index order; e.g., read entire first column, then second column, etc.
copy	[bool, optional] Indicates whether or not attributes of <i>self</i> should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns**reshaped_matrix**[sparse matrix] A sparse matrix with the given `shape`, not necessarily of the same format as the current object.**See also:**[`numpy.matrix.reshape`](#)

NumPy's implementation of 'reshape' for matrices

scipy.sparse.dok_matrix.resize`dok_matrix.resize` (*self*, **shape*)Resize the matrix in-place to dimensions given by `shape`

Any elements that lie within the new shape will remain at the same indices, while non-zero elements lying outside the new shape are removed.

Parameters

shape	[(int, int)] number of rows and columns in the new matrix
--------------	---

Notes

The semantics are not identical to `numpy.ndarray.resize` or `numpy.resize`. Here, the same data will be maintained at each index before and after reshape, if that index is within the new bounds. In `numpy`, resizing maintains contiguity of the array, moving elements around in the logical matrix but not within a flattened representation.

We give no guarantees about whether the underlying data attributes (arrays, etc.) will be modified in place or replaced with new objects.

`scipy.sparse.dok_matrix.set_shape`

`dok_matrix.set_shape` (*self*, *shape*)
 See *reshape*.

`scipy.sparse.dok_matrix.setdefault`

`dok_matrix.setdefault` (*self*, *key*, *default=None*, /)
 Insert key with a value of default if key is not in the dictionary.
 Return the value for key if key is in the dictionary, else default.

`scipy.sparse.dok_matrix.setdiag`

`dok_matrix.setdiag` (*self*, *values*, *k=0*)
 Set diagonal or off-diagonal elements of the array.

Parameters

- values** [array_like] New values of the diagonal elements.
 Values may have any length. If the diagonal is longer than values, then the remaining diagonal entries will not be set. If values are longer than the diagonal, then the remaining values are ignored.
- k** [int, optional] Which off-diagonal to set, corresponding to elements `a[i,i+k]`. Default: 0 (the main diagonal).

`scipy.sparse.dok_matrix.sum`

`dok_matrix.sum` (*self*, *axis=None*, *dtype=None*, *out=None*)
 Sum the matrix elements over a given axis.

Parameters

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the sum of all the matrix elements, returning a scalar (i.e., *axis = None*).
- dtype** [dtype, optional] The type of the returned matrix and of the accumulator in which the elements are summed. The dtype of *a* is used by default unless *a* has an integer dtype of less precision than the default platform integer. In that case, if *a* is signed then the platform integer is used while if *a* is unsigned then an unsigned integer of the same precision as the platform integer is used.
 New in version 0.18.0.

out [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns

sum_along_axis
[np.matrix] A matrix with the same shape as *self*, with the specified axis removed.

See also:

numpy.matrix.sum

NumPy's implementation of 'sum' for matrices

scipy.sparse.dok_matrix.toarray

`dok_matrix.toarray` (*self*, *order=None*, *out=None*)

Return a dense ndarray representation of this matrix.

Parameters

order [{'C', 'F'}, optional] Whether to store multidimensional data in C (row-major) or Fortran (column-major) order in memory. The default is 'None', indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the *out* argument.

out [ndarray, 2-D, optional] If specified, uses this array as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method. For most sparse types, *out* is required to be memory contiguous (either C or Fortran ordered).

Returns

arr [ndarray, 2-D] An array with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If *out* was passed, the same object is returned after being modified in-place to contain the appropriate values.

scipy.sparse.dok_matrix.tobsr

`dok_matrix.tobsr` (*self*, *blocksize=None*, *copy=False*)

Convert this matrix to Block Sparse Row format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant *bsr_matrix*.

When *blocksize=(R, C)* is provided, it will be used for construction of the *bsr_matrix*.

scipy.sparse.dok_matrix.tocoo

`dok_matrix.tocoo` (*self*, *copy=False*)

Convert this matrix to COOrdinate format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant *coo_matrix*.

`scipy.sparse.dok_matrix.tocsc`

`dok_matrix.tocsc` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Column format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `csc_matrix`.

`scipy.sparse.dok_matrix.tocsr`

`dok_matrix.tocsr` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Row format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `csr_matrix`.

`scipy.sparse.dok_matrix.todense`

`dok_matrix.todense` (*self*, *order=None*, *out=None*)

Return a dense matrix representation of this matrix.

Parameters

- order** [`'C'`, `'F'`], optional] Whether to store multi-dimensional data in C (row-major) or Fortran (column-major) order in memory. The default is `'None'`, indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the *out* argument.
- out** [`ndarray`, 2-D, optional] If specified, uses this array (or `numpy.matrix`) as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method.

Returns

- arr** [`numpy.matrix`, 2-D] A NumPy matrix object with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If *out* was passed and was an array (rather than a `numpy.matrix`), it will be filled with the appropriate values and returned wrapped in a `numpy.matrix` object that shares the same memory.

`scipy.sparse.dok_matrix.todia`

`dok_matrix.todia` (*self*, *copy=False*)

Convert this matrix to sparse DIAGONAL format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dia_matrix`.

`scipy.sparse.dok_matrix.todok`

`dok_matrix.todok` (*self*, *copy=False*)

Convert this matrix to Dictionary Of Keys format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dok_matrix`.

scipy.sparse.dok_matrix.tolil`dok_matrix.tolil` (*self*, *copy=False*)

Convert this matrix to List of Lists format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `lil_matrix`.**scipy.sparse.dok_matrix.transpose**`dok_matrix.transpose` (*self*, *axes=None*, *copy=False*)

Reverses the dimensions of the sparse matrix.

Parameters

- axes** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value.
- copy** [bool, optional] Indicates whether or not attributes of *self* should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns

- p** [*self* with the dimensions reversed.]

See also:[*numpy.matrix.transpose*](#)

NumPy's implementation of 'transpose' for matrices

scipy.sparse.dok_matrix.update`dok_matrix.update` (*self*, *val*)If *E* is present and has a `.keys()` method, then does: for *k* in *E*: *D*[*k*] = *E*[*k*] If *E* is present and lacks a `.keys()` method, then does: for *k*, *v* in *E*: *D*[*k*] = *v* In either case, this is followed by: for *k* in *F*: *D*[*k*] = *F*[*k*]**scipy.sparse.dok_matrix.values**`dok_matrix.values` ()

<code>__getitem__</code>	
--------------------------	--

scipy.sparse.lil_matrix**class** `scipy.sparse.lil_matrix` (*arg1*, *shape=None*, *dtype=None*, *copy=False*)

Row-based list of lists sparse matrix

This is a structure for constructing sparse matrices incrementally. Note that inserting a single item can take linear time in the worst case; to construct a matrix efficiently, make sure the items are pre-sorted by index, per row.

*This can be instantiated in several ways:***lil_matrix(D)**with a dense matrix or rank-2 ndarray *D*

`lil_matrix(S)`

with another sparse matrix `S` (equivalent to `S.tolil()`)

`lil_matrix((M, N), [dtype])`

to construct an empty matrix with shape `(M, N)` `dtype` is optional, defaulting to `dtype='d'`.

Notes

Sparse matrices can be used in arithmetic operations: they support addition, subtraction, multiplication, division, and matrix power.

Advantages of the LIL format

- supports flexible slicing
- changes to the matrix sparsity structure are efficient

Disadvantages of the LIL format

- arithmetic operations `LIL + LIL` are slow (consider `CSR` or `CSC`)
- slow column slicing (consider `CSC`)
- slow matrix vector products (consider `CSR` or `CSC`)

Intended Usage

- `LIL` is a convenient format for constructing sparse matrices
- once a matrix has been constructed, convert to `CSR` or `CSC` format for fast arithmetic and matrix vector operations
- consider using the `COO` format when constructing large matrices

Data Structure

- An array (`self.rows`) of rows, each of which is a sorted list of column indices of non-zero elements.
- The corresponding nonzero values are stored in similar fashion in `self.data`.

Attributes

<code>dtype</code>	[dtype] Data type of the matrix
<code>shape</code>	[2-tuple] Get shape of a matrix.
<code>ndim</code>	[int] Number of dimensions (this is always 2)
<code>nnz</code>	Number of stored values, including explicit zeros.
<code>data</code>	LIL format data array of the matrix
<code>rows</code>	LIL format row index array of the matrix

Methods

<code>__len__(self)</code>	
<code>__mul__(self, other)</code>	interpret other and call one of the following
<code>asformat(self, format[, copy])</code>	Return this matrix in the passed format.
<code>asfptype(self)</code>	Upcast matrix to a floating point format (if necessary)
<code>astype(self, dtype[, casting, copy])</code>	Cast the matrix elements to a specified type.
<code>conj(self[, copy])</code>	Element-wise complex conjugation.
<code>conjugate(self[, copy])</code>	Element-wise complex conjugation.
<code>copy(self)</code>	Returns a copy of this matrix.
<code>count_nonzero(self)</code>	Number of non-zero entries, equivalent to
<code>diagonal(self[, k])</code>	Returns the kth diagonal of the matrix.
<code>dot(self, other)</code>	Ordinary dot product
<code>getH(self)</code>	Return the Hermitian transpose of this matrix.
<code>get_shape(self)</code>	Get shape of a matrix.
<code>getcol(self, j)</code>	Returns a copy of column j of the matrix, as an (m x 1) sparse matrix (column vector).
<code>getformat(self)</code>	Format of a matrix representation as a string.
<code>getmaxprint(self)</code>	Maximum number of elements to display when printed.
<code>getnnz(self[, axis])</code>	Number of stored values, including explicit zeros.
<code>getrow(self, i)</code>	Returns a copy of the 'i'th row.
<code>getrowview(self, i)</code>	Returns a view of the 'i'th row (without copying).
<code>maximum(self, other)</code>	Element-wise maximum between this and another matrix.
<code>mean(self[, axis, dtype, out])</code>	Compute the arithmetic mean along the specified axis.
<code>minimum(self, other)</code>	Element-wise minimum between this and another matrix.
<code>multiply(self, other)</code>	Point-wise multiplication by another matrix
<code>nonzero(self)</code>	nonzero indices
<code>power(self, n[, dtype])</code>	Element-wise power.
<code>reshape(self, shape[, order, copy])</code>	Gives a new shape to a sparse matrix without changing its data.
<code>resize(self, *shape)</code>	Resize the matrix in-place to dimensions given by shape
<code>set_shape(self, shape)</code>	See <i>reshape</i> .
<code>setdiag(self, values[, k])</code>	Set diagonal or off-diagonal elements of the array.
<code>sum(self[, axis, dtype, out])</code>	Sum the matrix elements over a given axis.
<code>toarray(self[, order, out])</code>	Return a dense ndarray representation of this matrix.
<code>tobsr(self[, blocksize, copy])</code>	Convert this matrix to Block Sparse Row format.
<code>tocoo(self[, copy])</code>	Convert this matrix to COOrdinate format.
<code>tocsc(self[, copy])</code>	Convert this matrix to Compressed Sparse Column format.
<code>tocsr(self[, copy])</code>	Convert this matrix to Compressed Sparse Row format.
<code>todense(self[, order, out])</code>	Return a dense matrix representation of this matrix.
<code>todia(self[, copy])</code>	Convert this matrix to sparse DIAgonal format.
<code>todok(self[, copy])</code>	Convert this matrix to Dictionary Of Keys format.
<code>tolil(self[, copy])</code>	Convert this matrix to List of Lists format.
<code>transpose(self[, axes, copy])</code>	Reverses the dimensions of the sparse matrix.

scipy.sparse.lil_matrix.__len__

`lil_matrix.__len__(self)`

scipy.sparse.lil_matrix.__mul__

`lil_matrix.__mul__(self, other)`

interpret other and call one of the following

`self._mul_scalar()` `self._mul_vector()` `self._mul_multivector()` `self._mul_sparse_matrix()`

scipy.sparse.lil_matrix.asformat

`lil_matrix.asformat(self, format, copy=False)`

Return this matrix in the passed format.

Parameters

format [{str, None}] The desired matrix format (“csr”, “csc”, “lil”, “dok”, “array”, ...) or None for no conversion.

copy [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

A [This matrix in the passed format.]

scipy.sparse.lil_matrix.asfptype

`lil_matrix.asfptype(self)`

Upcast matrix to a floating point format (if necessary)

scipy.sparse.lil_matrix.astype

`lil_matrix.astype(self, dtype, casting='unsafe', copy=True)`

Cast the matrix elements to a specified type.

Parameters

dtype [string or numpy dtype] Typecode or data-type to which to cast the data.

casting [{'no', 'equiv', 'safe', 'same_kind', 'unsafe'}, optional] Controls what kind of data casting may occur. Defaults to ‘unsafe’ for backwards compatibility. ‘no’ means the data types should not be cast at all. ‘equiv’ means only byte-order changes are allowed. ‘safe’ means only casts which can preserve values are allowed. ‘same_kind’ means only safe casts or casts within a kind, like float64 to float32, are allowed. ‘unsafe’ means any data conversions may be done.

copy [bool, optional] If `copy` is False, the result might share some memory with this matrix. If `copy` is True, it is guaranteed that the result and this matrix do not share any memory.

scipy.sparse.lil_matrix.conj

`lil_matrix.conj` (*self*, *copy=True*)

Element-wise complex conjugation.

If the matrix is of non-complex data type and *copy* is False, this method does nothing and the data is not copied.

Parameters

copy [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

A [The element-wise complex conjugate.]

scipy.sparse.lil_matrix.conjugate

`lil_matrix.conjugate` (*self*, *copy=True*)

Element-wise complex conjugation.

If the matrix is of non-complex data type and *copy* is False, this method does nothing and the data is not copied.

Parameters

copy [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

A [The element-wise complex conjugate.]

scipy.sparse.lil_matrix.copy

`lil_matrix.copy` (*self*)

Returns a copy of this matrix.

No data/indices will be shared between the returned value and current matrix.

scipy.sparse.lil_matrix.count_nonzero

`lil_matrix.count_nonzero` (*self*)

Number of non-zero entries, equivalent to

`np.count_nonzero(a.toarray())`

Unlike `getnnz()` and the `nnz` property, which return the number of stored entries (the length of the data attribute), this method counts the actual number of non-zero entries in data.

scipy.sparse.lil_matrix.diagonal

`lil_matrix.diagonal` (*self*, *k=0*)
Returns the *k*th diagonal of the matrix.

Parameters

k [int, optional] Which diagonal to get, corresponding to elements $a[i, i+k]$. Default: 0 (the main diagonal).
New in version 1.0.

See also:

numpy.diagonal

Equivalent numpy function.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> A.diagonal()
array([1, 0, 5])
>>> A.diagonal(k=1)
array([2, 3])
```

scipy.sparse.lil_matrix.dot

`lil_matrix.dot` (*self*, *other*)
Ordinary dot product

Examples

```
>>> import numpy as np
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> v = np.array([1, 0, -1])
>>> A.dot(v)
array([ 1, -3, -1], dtype=int64)
```

scipy.sparse.lil_matrix.getH

`lil_matrix.getH` (*self*)
Return the Hermitian transpose of this matrix.

See also:

numpy.matrix.getH

NumPy's implementation of *getH* for matrices

scipy.sparse.lil_matrix.get_shape

`lil_matrix.get_shape` (*self*)
Get shape of a matrix.

scipy.sparse.lil_matrix.getcol

`lil_matrix.getcol` (*self*, *j*)
Returns a copy of column *j* of the matrix, as an (m x 1) sparse matrix (column vector).

scipy.sparse.lil_matrix.getformat

`lil_matrix.getformat` (*self*)
Format of a matrix representation as a string.

scipy.sparse.lil_matrix.getmaxprint

`lil_matrix.getmaxprint` (*self*)
Maximum number of elements to display when printed.

scipy.sparse.lil_matrix.getnnz

`lil_matrix.getnnz` (*self*, *axis=None*)
Number of stored values, including explicit zeros.

Parameters

axis [None, 0, or 1] Select between the number of values across the whole matrix, in each column, or in each row.

See also:*count_nonzero*

Number of non-zero entries

scipy.sparse.lil_matrix.getrow

`lil_matrix.getrow` (*self*, *i*)
Returns a copy of the *i*'th row.

scipy.sparse.lil_matrix.getrowview

`lil_matrix.getrowview` (*self*, *i*)
Returns a view of the *i*'th row (without copying).

scipy.sparse.lil_matrix.maximum

`lil_matrix.maximum` (*self*, *other*)
Element-wise maximum between this and another matrix.

scipy.sparse.lil_matrix.mean

`lil_matrix.mean` (*self*, *axis=None*, *dtype=None*, *out=None*)
Compute the arithmetic mean along the specified axis.

Returns the average of the matrix elements. The average is taken over all elements in the matrix by default, otherwise over the specified axis. *float64* intermediate and return values are used for integer inputs.

Parameters

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the mean is computed. The default is to compute the mean of all elements in the matrix (i.e., *axis = None*).
- dtype** [data-type, optional] Type to use in computing the mean. For integer inputs, the default is *float64*; for floating point inputs, it is the same as the input dtype.
New in version 0.18.0.
- out** [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns

- m** [np.matrix]

See also:

[*numpy.matrix.mean*](#)

NumPy's implementation of 'mean' for matrices

scipy.sparse.lil_matrix.minimum

`lil_matrix.minimum` (*self*, *other*)
Element-wise minimum between this and another matrix.

scipy.sparse.lil_matrix.multiply

`lil_matrix.multiply` (*self*, *other*)
Point-wise multiplication by another matrix

scipy.sparse.lil_matrix.nonzero

`lil_matrix.nonzero` (*self*)
nonzero indices
Returns a tuple of arrays (row,col) containing the indices of the non-zero elements of the matrix.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1,2,0],[0,0,3],[4,0,5]])
>>> A.nonzero()
(array([0, 0, 1, 2, 2]), array([0, 1, 2, 0, 2]))
```

scipy.sparse.lil_matrix.power

`lil_matrix.power` (*self*, *n*, *dtype=None*)
Element-wise power.

scipy.sparse.lil_matrix.reshape

`lil_matrix.reshape` (*self*, *shape*, *order='C'*, *copy=False*)
Gives a new shape to a sparse matrix without changing its data.

Parameters

shape	[length-2 tuple of ints] The new shape should be compatible with the original shape.
order	[{'C', 'F'}, optional] Read the elements using this index order. 'C' means to read and write the elements using C-like index order; e.g., read entire first row, then second row, etc. 'F' means to read and write the elements using Fortran-like index order; e.g., read entire first column, then second column, etc.
copy	[bool, optional] Indicates whether or not attributes of self should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns

reshaped_matrix	[sparse matrix] A sparse matrix with the given <i>shape</i> , not necessarily of the same format as the current object.
------------------------	---

See also:

[*numpy.matrix.reshape*](#)

NumPy's implementation of 'reshape' for matrices

scipy.sparse.lil_matrix.resize

`lil_matrix.resize` (*self*, **shape*)

Resize the matrix in-place to dimensions given by *shape*

Any elements that lie within the new shape will remain at the same indices, while non-zero elements lying outside the new shape are removed.

Parameters

shape [(int, int)] number of rows and columns in the new matrix

Notes

The semantics are not identical to `numpy.ndarray.resize` or `numpy.resize`. Here, the same data will be maintained at each index before and after reshape, if that index is within the new bounds. In `numpy`, resizing maintains contiguity of the array, moving elements around in the logical matrix but not within a flattened representation.

We give no guarantees about whether the underlying data attributes (arrays, etc.) will be modified in place or replaced with new objects.

scipy.sparse.lil_matrix.set_shape

`lil_matrix.set_shape` (*self*, *shape*)

See `reshape`.

scipy.sparse.lil_matrix.setdiag

`lil_matrix.setdiag` (*self*, *values*, *k=0*)

Set diagonal or off-diagonal elements of the array.

Parameters

values [array_like] New values of the diagonal elements. Values may have any length. If the diagonal is longer than values, then the remaining diagonal entries will not be set. If values are longer than the diagonal, then the remaining values are ignored.

k [int, optional] Which off-diagonal to set, corresponding to elements `a[i,i+k]`. Default: 0 (the main diagonal).

scipy.sparse.lil_matrix.sum

`lil_matrix.sum` (*self*, *axis=None*, *dtype=None*, *out=None*)

Sum the matrix elements over a given axis.

Parameters

axis [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the sum of all the matrix elements, returning a scalar (i.e., `axis = None`).

- dtype** [dtype, optional] The type of the returned matrix and of the accumulator in which the elements are summed. The dtype of *a* is used by default unless *a* has an integer dtype of less precision than the default platform integer. In that case, if *a* is signed then the platform integer is used while if *a* is unsigned then an unsigned integer of the same precision as the platform integer is used.
New in version 0.18.0.
- out** [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns**sum_along_axis**

[np.matrix] A matrix with the same shape as *self*, with the specified axis removed.

See also:

[*numpy.matrix.sum*](#)

NumPy's implementation of 'sum' for matrices

scipy.sparse.lil_matrix.toarray

`lil_matrix.toarray` (*self*, *order=None*, *out=None*)

Return a dense ndarray representation of this matrix.

Parameters

- order** [{'C', 'F'}, optional] Whether to store multidimensional data in C (row-major) or Fortran (column-major) order in memory. The default is 'None', indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the *out* argument.
- out** [ndarray, 2-D, optional] If specified, uses this array as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method. For most sparse types, *out* is required to be memory contiguous (either C or Fortran ordered).

Returns

- arr** [ndarray, 2-D] An array with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If *out* was passed, the same object is returned after being modified in-place to contain the appropriate values.

scipy.sparse.lil_matrix.tobsr

`lil_matrix.tobsr` (*self*, *blocksize=None*, *copy=False*)

Convert this matrix to Block Sparse Row format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant *bsr_matrix*.

When *blocksize=(R, C)* is provided, it will be used for construction of the *bsr_matrix*.

scipy.sparse.lil_matrix.tocoo

`lil_matrix.tocoo` (*self*, *copy=False*)

Convert this matrix to COOrdinate format.

With `copy=False`, the data/indices may be shared between this matrix and the resultant `coo_matrix`.

scipy.sparse.lil_matrix.tocsc

`lil_matrix.tocsc` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Column format.

With `copy=False`, the data/indices may be shared between this matrix and the resultant `csc_matrix`.

scipy.sparse.lil_matrix.tocsr

`lil_matrix.tocsr` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Row format.

With `copy=False`, the data/indices may be shared between this matrix and the resultant `csr_matrix`.

scipy.sparse.lil_matrix.todense

`lil_matrix.todense` (*self*, *order=None*, *out=None*)

Return a dense matrix representation of this matrix.

Parameters

- order** [{"C", "F"}, optional] Whether to store multi-dimensional data in C (row-major) or Fortran (column-major) order in memory. The default is 'None', indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the `out` argument.
- out** [ndarray, 2-D, optional] If specified, uses this array (or `numpy.matrix`) as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method.

Returns

- arr** [numpy.matrix, 2-D] A NumPy matrix object with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If `out` was passed and was an array (rather than a `numpy.matrix`), it will be filled with the appropriate values and returned wrapped in a `numpy.matrix` object that shares the same memory.

scipy.sparse.lil_matrix.todia

`lil_matrix.todia` (*self*, *copy=False*)

Convert this matrix to sparse DIAGONal format.

With `copy=False`, the data/indices may be shared between this matrix and the resultant `dia_matrix`.

scipy.sparse.lil_matrix.todok`lil_matrix.todok` (*self*, *copy=False*)

Convert this matrix to Dictionary Of Keys format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dok_matrix`.**scipy.sparse.lil_matrix.tolil**`lil_matrix.tolil` (*self*, *copy=False*)

Convert this matrix to List of Lists format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `lil_matrix`.**scipy.sparse.lil_matrix.transpose**`lil_matrix.transpose` (*self*, *axes=None*, *copy=False*)

Reverses the dimensions of the sparse matrix.

Parameters

- axes** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value.
- copy** [bool, optional] Indicates whether or not attributes of *self* should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns

- p** [*self* with the dimensions reversed.]

See also:***numpy.matrix.transpose***

NumPy's implementation of 'transpose' for matrices

<code>__getitem__</code>	
--------------------------	--

scipy.sparse.spmatrix**class** `scipy.sparse.spmatrix` (*maxprint=50*)

This class provides a base class for all sparse matrices. It cannot be instantiated. Most of the work is provided by subclasses.

Attributes

- nnz** Number of stored values, including explicit zeros.
- shape** Get shape of a matrix.

Methods

<code>__len__(self)</code>	
<code>__mul__(self, other)</code>	interpret other and call one of the following
<code>asformat(self, format[, copy])</code>	Return this matrix in the passed format.
<code>asfptype(self)</code>	Upcast matrix to a floating point format (if necessary)
<code>astype(self, dtype[, casting, copy])</code>	Cast the matrix elements to a specified type.
<code>conj(self[, copy])</code>	Element-wise complex conjugation.
<code>conjugate(self[, copy])</code>	Element-wise complex conjugation.
<code>copy(self)</code>	Returns a copy of this matrix.
<code>count_nonzero(self)</code>	Number of non-zero entries, equivalent to
<code>diagonal(self[, k])</code>	Returns the kth diagonal of the matrix.
<code>dot(self, other)</code>	Ordinary dot product
<code>getH(self)</code>	Return the Hermitian transpose of this matrix.
<code>get_shape(self)</code>	Get shape of a matrix.
<code>getcol(self, j)</code>	Returns a copy of column j of the matrix, as an (m x 1) sparse matrix (column vector).
<code>getformat(self)</code>	Format of a matrix representation as a string.
<code>getmaxprint(self)</code>	Maximum number of elements to display when printed.
<code>getnnz(self[, axis])</code>	Number of stored values, including explicit zeros.
<code>getrow(self, i)</code>	Returns a copy of row i of the matrix, as a (1 x n) sparse matrix (row vector).
<code>maximum(self, other)</code>	Element-wise maximum between this and another matrix.
<code>mean(self[, axis, dtype, out])</code>	Compute the arithmetic mean along the specified axis.
<code>minimum(self, other)</code>	Element-wise minimum between this and another matrix.
<code>multiply(self, other)</code>	Point-wise multiplication by another matrix
<code>nonzero(self)</code>	nonzero indices
<code>power(self, n[, dtype])</code>	Element-wise power.
<code>reshape(self, shape[, order, copy])</code>	Gives a new shape to a sparse matrix without changing its data.
<code>resize(self, shape)</code>	Resize the matrix in-place to dimensions given by shape
<code>set_shape(self, shape)</code>	See <code>reshape</code> .
<code>setdiag(self, values[, k])</code>	Set diagonal or off-diagonal elements of the array.
<code>sum(self[, axis, dtype, out])</code>	Sum the matrix elements over a given axis.
<code>toarray(self[, order, out])</code>	Return a dense ndarray representation of this matrix.
<code>tobsr(self[, blocksize, copy])</code>	Convert this matrix to Block Sparse Row format.
<code>tocoo(self[, copy])</code>	Convert this matrix to COOrdinate format.
<code>tocsc(self[, copy])</code>	Convert this matrix to Compressed Sparse Column format.
<code>tocsr(self[, copy])</code>	Convert this matrix to Compressed Sparse Row format.
<code>todense(self[, order, out])</code>	Return a dense matrix representation of this matrix.
<code>todia(self[, copy])</code>	Convert this matrix to sparse DIAgonal format.
<code>todok(self[, copy])</code>	Convert this matrix to Dictionary Of Keys format.
<code>tolil(self[, copy])</code>	Convert this matrix to List of Lists format.
<code>transpose(self[, axes, copy])</code>	Reverses the dimensions of the sparse matrix.

scipy.sparse.spmatrix.__len__

`spmatrix.__len__` (*self*)

scipy.sparse.spmatrix.__mul__

`spmatrix.__mul__` (*self*, *other*)

interpret *other* and call one of the following

`self._mul_scalar()` `self._mul_vector()` `self._mul_multivector()` `self._mul_sparse_matrix()`

scipy.sparse.spmatrix.asformat

`spmatrix.asformat` (*self*, *format*, *copy=False*)

Return this matrix in the passed format.

Parameters

format [{str, None}] The desired matrix format (“csr”, “csc”, “lil”, “dok”, “array”, ...) or None for no conversion.

copy [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

A [This matrix in the passed format.]

scipy.sparse.spmatrix.asfptype

`spmatrix.asfptype` (*self*)

Upcast matrix to a floating point format (if necessary)

scipy.sparse.spmatrix.astype

`spmatrix.astype` (*self*, *dtype*, *casting='unsafe'*, *copy=True*)

Cast the matrix elements to a specified type.

Parameters

dtype [string or numpy dtype] Typecode or data-type to which to cast the data.

casting [{'no', 'equiv', 'safe', 'same_kind', 'unsafe'}, optional] Controls what kind of data casting may occur. Defaults to ‘unsafe’ for backwards compatibility. ‘no’ means the data types should not be cast at all. ‘equiv’ means only byte-order changes are allowed. ‘safe’ means only casts which can preserve values are allowed. ‘same_kind’ means only safe casts or casts within a kind, like float64 to float32, are allowed. ‘unsafe’ means any data conversions may be done.

copy [bool, optional] If *copy* is False, the result might share some memory with this matrix. If *copy* is True, it is guaranteed that the result and this matrix do not share any memory.

scipy.sparse.spmatrix.conj

`spmatrix.conj` (*self*, *copy=True*)

Element-wise complex conjugation.

If the matrix is of non-complex data type and *copy* is False, this method does nothing and the data is not copied.

Parameters

copy [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

A [The element-wise complex conjugate.]

scipy.sparse.spmatrix.conjugate

`spmatrix.conjugate` (*self*, *copy=True*)

Element-wise complex conjugation.

If the matrix is of non-complex data type and *copy* is False, this method does nothing and the data is not copied.

Parameters

copy [bool, optional] If True, the result is guaranteed to not share data with self.

Returns

A [The element-wise complex conjugate.]

scipy.sparse.spmatrix.copy

`spmatrix.copy` (*self*)

Returns a copy of this matrix.

No data/indices will be shared between the returned value and current matrix.

scipy.sparse.spmatrix.count_nonzero

`spmatrix.count_nonzero` (*self*)

Number of non-zero entries, equivalent to

`np.count_nonzero(a.toarray())`

Unlike `getnnz()` and the `nnz` property, which return the number of stored entries (the length of the data attribute), this method counts the actual number of non-zero entries in data.

scipy.sparse.spmatrix.diagonal

`spmatrix.diagonal` (*self*, *k=0*)
Returns the *k*th diagonal of the matrix.

Parameters

k [int, optional] Which diagonal to get, corresponding to elements $a[i, i+k]$. Default: 0 (the main diagonal).
New in version 1.0.

See also:***numpy.diagonal***

Equivalent numpy function.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> A.diagonal()
array([1, 0, 5])
>>> A.diagonal(k=1)
array([2, 3])
```

scipy.sparse.spmatrix.dot

`spmatrix.dot` (*self*, *other*)
Ordinary dot product

Examples

```
>>> import numpy as np
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> v = np.array([1, 0, -1])
>>> A.dot(v)
array([ 1, -3, -1], dtype=int64)
```

scipy.sparse.spmatrix.getH

`spmatrix.getH` (*self*)
Return the Hermitian transpose of this matrix.

See also:***numpy.matrix.getH***

NumPy's implementation of *getH* for matrices

scipy.sparse.spmatrix.get_shape

`spmatrix.get_shape` (*self*)
Get shape of a matrix.

scipy.sparse.spmatrix.getcol

`spmatrix.getcol` (*self*, *j*)
Returns a copy of column *j* of the matrix, as an (m x 1) sparse matrix (column vector).

scipy.sparse.spmatrix.getformat

`spmatrix.getformat` (*self*)
Format of a matrix representation as a string.

scipy.sparse.spmatrix.getmaxprint

`spmatrix.getmaxprint` (*self*)
Maximum number of elements to display when printed.

scipy.sparse.spmatrix.getnnz

`spmatrix.getnnz` (*self*, *axis=None*)
Number of stored values, including explicit zeros.

Parameters

axis [None, 0, or 1] Select between the number of values across the whole matrix, in each column, or in each row.

See also:

count_nonzero

Number of non-zero entries

scipy.sparse.spmatrix.getrow

`spmatrix.getrow` (*self*, *i*)
Returns a copy of row *i* of the matrix, as a (1 x n) sparse matrix (row vector).

scipy.sparse.spmatrix.maximum`spmatrix.maximum` (*self*, *other*)

Element-wise maximum between this and another matrix.

scipy.sparse.spmatrix.mean`spmatrix.mean` (*self*, *axis=None*, *dtype=None*, *out=None*)

Compute the arithmetic mean along the specified axis.

Returns the average of the matrix elements. The average is taken over all elements in the matrix by default, otherwise over the specified axis. *float64* intermediate and return values are used for integer inputs.**Parameters**

- axis** [{-2, -1, 0, 1, None} optional] Axis along which the mean is computed. The default is to compute the mean of all elements in the matrix (i.e., *axis = None*).
- dtype** [data-type, optional] Type to use in computing the mean. For integer inputs, the default is *float64*; for floating point inputs, it is the same as the input dtype.
New in version 0.18.0.
- out** [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns

- m** [np.matrix]

See also:[*numpy.matrix.mean*](#)

NumPy's implementation of 'mean' for matrices

scipy.sparse.spmatrix.minimum`spmatrix.minimum` (*self*, *other*)

Element-wise minimum between this and another matrix.

scipy.sparse.spmatrix.multiply`spmatrix.multiply` (*self*, *other*)

Point-wise multiplication by another matrix

scipy.sparse.spmatrix.nonzero

`spmatrix.nonzero` (*self*)
nonzero indices

Returns a tuple of arrays (row,col) containing the indices of the non-zero elements of the matrix.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1,2,0],[0,0,3],[4,0,5]])
>>> A.nonzero()
(array([0, 0, 1, 2, 2]), array([0, 1, 2, 0, 2]))
```

scipy.sparse.spmatrix.power

`spmatrix.power` (*self*, *n*, *dtype=None*)
Element-wise power.

scipy.sparse.spmatrix.reshape

`spmatrix.reshape` (*self*, *shape*, *order='C'*, *copy=False*)
Gives a new shape to a sparse matrix without changing its data.

Parameters

shape	[length-2 tuple of ints] The new shape should be compatible with the original shape.
order	[{'C', 'F'}, optional] Read the elements using this index order. 'C' means to read and write the elements using C-like index order; e.g., read entire first row, then second row, etc. 'F' means to read and write the elements using Fortran-like index order; e.g., read entire first column, then second column, etc.
copy	[bool, optional] Indicates whether or not attributes of self should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns

reshaped_matrix	[sparse matrix] A sparse matrix with the given shape, not necessarily of the same format as the current object.
------------------------	---

See also:

[*numpy.matrix.reshape*](#)

NumPy's implementation of 'reshape' for matrices

scipy.sparse.spmatrix.resize`spmatrix.resize` (*self*, *shape*)Resize the matrix in-place to dimensions given by *shape*

Any elements that lie within the new shape will remain at the same indices, while non-zero elements lying outside the new shape are removed.

Parameters

shape [(int, int)] number of rows and columns in the new matrix

Notes

The semantics are not identical to `numpy.ndarray.resize` or `numpy.resize`. Here, the same data will be maintained at each index before and after reshape, if that index is within the new bounds. In `numpy`, resizing maintains contiguity of the array, moving elements around in the logical matrix but not within a flattened representation.

We give no guarantees about whether the underlying data attributes (arrays, etc.) will be modified in place or replaced with new objects.

scipy.sparse.spmatrix.set_shape`spmatrix.set_shape` (*self*, *shape*)See `reshape`.**scipy.sparse.spmatrix.setdiag**`spmatrix.setdiag` (*self*, *values*, *k=0*)

Set diagonal or off-diagonal elements of the array.

Parameters

values [array_like] New values of the diagonal elements. Values may have any length. If the diagonal is longer than values, then the remaining diagonal entries will not be set. If values are longer than the diagonal, then the remaining values are ignored.

k [int, optional] Which off-diagonal to set, corresponding to elements `a[i,i+k]`. Default: 0 (the main diagonal).

scipy.sparse.spmatrix.sum`spmatrix.sum` (*self*, *axis=None*, *dtype=None*, *out=None*)

Sum the matrix elements over a given axis.

Parameters

axis [{-2, -1, 0, 1, None} optional] Axis along which the sum is computed. The default is to compute the sum of all the matrix elements, returning a scalar (i.e., `axis = None`).

- dtype** [dtype, optional] The type of the returned matrix and of the accumulator in which the elements are summed. The dtype of *a* is used by default unless *a* has an integer dtype of less precision than the default platform integer. In that case, if *a* is signed then the platform integer is used while if *a* is unsigned then an unsigned integer of the same precision as the platform integer is used.
New in version 0.18.0.
- out** [np.matrix, optional] Alternative output matrix in which to place the result. It must have the same shape as the expected output, but the type of the output values will be cast if necessary.
New in version 0.18.0.

Returns

- sum_along_axis**
[np.matrix] A matrix with the same shape as *self*, with the specified axis removed.

See also:

[*numpy.matrix.sum*](#)

NumPy's implementation of 'sum' for matrices

scipy.sparse.spmatrix.toarray

`spmatrix.toarray` (*self*, *order=None*, *out=None*)
Return a dense ndarray representation of this matrix.

Parameters

- order** [{'C', 'F'}, optional] Whether to store multidimensional data in C (row-major) or Fortran (column-major) order in memory. The default is 'None', indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the *out* argument.
- out** [ndarray, 2-D, optional] If specified, uses this array as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method. For most sparse types, *out* is required to be memory contiguous (either C or Fortran ordered).

Returns

- arr** [ndarray, 2-D] An array with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If *out* was passed, the same object is returned after being modified in-place to contain the appropriate values.

scipy.sparse.spmatrix.tobsr

`spmatrix.tobsr` (*self*, *blocksize=None*, *copy=False*)
Convert this matrix to Block Sparse Row format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant *bsr_matrix*.

When *blocksize=(R, C)* is provided, it will be used for construction of the *bsr_matrix*.

scipy.sparse.spmatrix.tocoo`spmatrix.tocoo` (*self*, *copy=False*)

Convert this matrix to COOrdinate format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `coo_matrix`.**scipy.sparse.spmatrix.tocsc**`spmatrix.tocsc` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Column format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `csc_matrix`.**scipy.sparse.spmatrix.tocsr**`spmatrix.tocsr` (*self*, *copy=False*)

Convert this matrix to Compressed Sparse Row format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `csr_matrix`.**scipy.sparse.spmatrix.todense**`spmatrix.todense` (*self*, *order=None*, *out=None*)

Return a dense matrix representation of this matrix.

Parameters

- order** [{"C", "F"}, optional] Whether to store multi-dimensional data in C (row-major) or Fortran (column-major) order in memory. The default is 'None', indicating the NumPy default of C-ordered. Cannot be specified in conjunction with the *out* argument.
- out** [ndarray, 2-D, optional] If specified, uses this array (or `numpy.matrix`) as the output buffer instead of allocating a new array to return. The provided array must have the same shape and dtype as the sparse matrix on which you are calling the method.

Returns

- arr** [`numpy.matrix`, 2-D] A NumPy matrix object with the same shape and containing the same data represented by the sparse matrix, with the requested memory order. If *out* was passed and was an array (rather than a `numpy.matrix`), it will be filled with the appropriate values and returned wrapped in a `numpy.matrix` object that shares the same memory.

scipy.sparse.spmatrix.todia`spmatrix.todia` (*self*, *copy=False*)

Convert this matrix to sparse DIAgonal format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dia_matrix`.

scipy.sparse.spmatrix.todok

`spmatrix.todok` (*self*, *copy=False*)

Convert this matrix to Dictionary Of Keys format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `dok_matrix`.

scipy.sparse.spmatrix.tolil

`spmatrix.tolil` (*self*, *copy=False*)

Convert this matrix to List of Lists format.

With *copy=False*, the data/indices may be shared between this matrix and the resultant `lil_matrix`.

scipy.sparse.spmatrix.transpose

`spmatrix.transpose` (*self*, *axes=None*, *copy=False*)

Reverses the dimensions of the sparse matrix.

Parameters

- axes** [None, optional] This argument is in the signature *solely* for NumPy compatibility reasons. Do not pass in anything except for the default value.
- copy** [bool, optional] Indicates whether or not attributes of *self* should be copied whenever possible. The degree to which attributes are copied varies depending on the type of sparse matrix being used.

Returns

- p** [*self* with the dimensions reversed.]

See also:

numpy.matrix.transpose

NumPy's implementation of 'transpose' for matrices

Functions

Building sparse matrices:

<code>eye(m[, n, k, dtype, format])</code>	Sparse matrix with ones on diagonal
<code>identity(n[, dtype, format])</code>	Identity matrix in sparse format
<code>kron(A, B[, format])</code>	kronecker product of sparse matrices A and B
<code>kronsum(A, B[, format])</code>	kronecker sum of sparse matrices A and B
<code>diags(diagonals[, offsets, shape, format, dtype])</code>	Construct a sparse matrix from diagonals.
<code>spdiags(data, diags, m, n[, format])</code>	Return a sparse matrix from diagonals.
<code>block_diag(mats[, format, dtype])</code>	Build a block diagonal sparse matrix from provided matrices.
<code>tril(A[, k, format])</code>	Return the lower triangular portion of a matrix in sparse format
<code>triu(A[, k, format])</code>	Return the upper triangular portion of a matrix in sparse format

continues on next page

Table 181 – continued from previous page

<code>bmat(blocks[, format, dtype])</code>	Build a sparse matrix from sparse sub-blocks
<code>hstack(blocks[, format, dtype])</code>	Stack sparse matrices horizontally (column wise)
<code>vstack(blocks[, format, dtype])</code>	Stack sparse matrices vertically (row wise)
<code>rand(m, n[, density, format, dtype, ...])</code>	Generate a sparse matrix of the given shape and density with uniformly distributed values.
<code>random(m, n[, density, format, dtype, ...])</code>	Generate a sparse matrix of the given shape and density with randomly distributed values.

scipy.sparse.eye

`scipy.sparse.eye` (*m*, *n=None*, *k=0*, *dtype=<class 'float'>*, *format=None*)

Sparse matrix with ones on diagonal

Returns a sparse (*m* x *n*) matrix where the *k*th diagonal is all ones and everything else is zeros.

Parameters

- m** [int] Number of rows in the matrix.
- n** [int, optional] Number of columns. Default: *m*.
- k** [int, optional] Diagonal to place ones on. Default: 0 (main diagonal).
- dtype** [dtype, optional] Data type of the matrix.
- format** [str, optional] Sparse format of the result, e.g., `format="csr"`, etc.

Examples

```
>>> from scipy import sparse
>>> sparse.eye(3).toarray()
array([[ 1.,  0.,  0.],
       [ 0.,  1.,  0.],
       [ 0.,  0.,  1.]])
>>> sparse.eye(3, dtype=np.int8)
<3x3 sparse matrix of type '<class 'numpy.int8'>'
with 3 stored elements (1 diagonals) in DIAGONAL format>
```

scipy.sparse.identity

`scipy.sparse.identity` (*n*, *dtype='d'*, *format=None*)

Identity matrix in sparse format

Returns an identity matrix with shape (*n*,*n*) using a given sparse format and *dtype*.

Parameters

- n** [int] Shape of the identity matrix.
- dtype** [dtype, optional] Data type of the matrix
- format** [str, optional] Sparse format of the result, e.g., `format="csr"`, etc.

Examples

```
>>> from scipy.sparse import identity
>>> identity(3).toarray()
array([[ 1.,  0.,  0.],
       [ 0.,  1.,  0.],
       [ 0.,  0.,  1.]])
>>> identity(3, dtype='int8', format='dia')
<3x3 sparse matrix of type '<class 'numpy.int8'>'
  with 3 stored elements (1 diagonals) in DIAgonal format>
```

scipy.sparse.kron

`scipy.sparse.kron(A, B, format=None)`
 Kronecker product of sparse matrices A and B

Parameters

A [sparse or dense matrix] first matrix of the product
B [sparse or dense matrix] second matrix of the product
format [str, optional] format of the result (e.g. “csr”)

Returns

Kronecker product in a sparse matrix format

Examples

```
>>> from scipy import sparse
>>> A = sparse.csr_matrix(np.array([[0, 2], [5, 0]]))
>>> B = sparse.csr_matrix(np.array([[1, 2], [3, 4]]))
>>> sparse.kron(A, B).toarray()
array([[ 0,  0,  2,  4],
       [ 0,  0,  6,  8],
       [ 5, 10,  0,  0],
       [15, 20,  0,  0]])
```

```
>>> sparse.kron(A, [[1, 2], [3, 4]]).toarray()
array([[ 0,  0,  2,  4],
       [ 0,  0,  6,  8],
       [ 5, 10,  0,  0],
       [15, 20,  0,  0]])
```

scipy.sparse.kronsum

`scipy.sparse.kronsum(A, B, format=None)`
 Kronecker sum of sparse matrices A and B

Kronecker sum of two sparse matrices is a sum of two Kronecker products $\text{kron}(I_n, A) + \text{kron}(B, I_m)$ where A has shape (m,m) and B has shape (n,n) and I_m and I_n are identity matrices of shape (m,m) and (n,n), respectively.

Parameters

A square matrix
B square matrix
format [str] format of the result (e.g. “csr”)

Returns**kronecker sum in a sparse matrix format****scipy.sparse.diags**`scipy.sparse.diags` (*diagonals*, *offsets=0*, *shape=None*, *format=None*, *dtype=None*)

Construct a sparse matrix from diagonals.

Parameters**diagonals** [sequence of array_like] Sequence of arrays containing the matrix diagonals, corresponding to *offsets*.**offsets** [sequence of int or an int, optional]**Diagonals to set:**

- $k = 0$ the main diagonal (default)
- $k > 0$ the k th upper diagonal
- $k < 0$ the k th lower diagonal

shape [tuple of int, optional] Shape of the result. If omitted, a square matrix large enough to contain the diagonals is returned.**format** [{"dia", "csr", "csc", "lil", ...}, optional] Matrix format of the result. By default (*format=None*) an appropriate sparse matrix format is returned. This choice is subject to change.**dtype** [dtype, optional] Data type of the matrix.**See also:***spdiags*

construct matrix from diagonals

NotesThis function differs from *spdiags* in the way it handles off-diagonals.The result from *diags* is the sparse equivalent of:

```
np.diag(diagonals[0], offsets[0])
+ ...
+ np.diag(diagonals[k], offsets[k])
```

Repeated diagonal offsets are disallowed.

New in version 0.11.

Examples

```
>>> from scipy.sparse import diags
>>> diagonals = [[1, 2, 3, 4], [1, 2, 3], [1, 2]]
>>> diags(diagonals, [0, -1, 2]).toarray()
array([[1, 0, 1, 0],
       [1, 2, 0, 2],
       [0, 2, 3, 0],
       [0, 0, 3, 4]])
```

Broadcasting of scalars is supported (but *shape* needs to be specified):

```
>>> diags([1, -2, 1], [-1, 0, 1], shape=(4, 4)).toarray()
array([[ -2.,  1.,  0.,  0.],
       [  1., -2.,  1.,  0.],
       [  0.,  1., -2.,  1.],
       [  0.,  0.,  1., -2.]])
```

If only one diagonal is wanted (as in `numpy.diag`), the following works as well:

```
>>> diags([1, 2, 3], 1).toarray()
array([[ 0.,  1.,  0.,  0.],
       [ 0.,  0.,  2.,  0.],
       [ 0.,  0.,  0.,  3.],
       [ 0.,  0.,  0.,  0.]])
```

scipy.sparse.spdiags

`scipy.sparse.spdiags` (*data*, *diags*, *m*, *n*, *format=None*)

Return a sparse matrix from diagonals.

Parameters

data	[array_like] matrix diagonals stored row-wise
diags	[diagonals to set] <ul style="list-style-type: none"> • $k = 0$ the main diagonal • $k > 0$ the k-th upper diagonal • $k < 0$ the k-th lower diagonal
m, n	[int] shape of the result
format	[str, optional] Format of the result. By default (<i>format=None</i>) an appropriate sparse matrix format is returned. This choice is subject to change.

See also:

[*diags*](#)

more convenient form of this function

[*dia_matrix*](#)

the sparse DIAgonal format.

Examples

```
>>> from scipy.sparse import spdiags
>>> data = np.array([[1, 2, 3, 4], [1, 2, 3, 4], [1, 2, 3, 4]])
>>> diags = np.array([0, -1, 2])
>>> spdiags(data, diags, 4, 4).toarray()
array([[1, 0, 3, 0],
       [1, 2, 0, 4],
       [0, 2, 3, 0],
       [0, 0, 3, 4]])
```


scipy.sparse.block_diag`scipy.sparse.block_diag` (*mats*, *format=None*, *dtype=None*)

Build a block diagonal sparse matrix from provided matrices.

Parameters

- mats** [sequence of matrices] Input matrices.
- format** [str, optional] The sparse format of the result (e.g., “csr”). If not given, the matrix is returned in “coo” format.
- dtype** [dtype specifier, optional] The data-type of the output matrix. If not given, the dtype is determined from that of *blocks*.

Returns

- res** [sparse matrix]

See also:*bmat*, *diags***Notes**

New in version 0.11.0.

Examples

```
>>> from scipy.sparse import coo_matrix, block_diag
>>> A = coo_matrix([[1, 2], [3, 4]])
>>> B = coo_matrix([[5], [6]])
>>> C = coo_matrix([[7]])
>>> block_diag((A, B, C)).toarray()
array([[1, 2, 0, 0],
       [3, 4, 0, 0],
       [0, 0, 5, 0],
       [0, 0, 6, 0],
       [0, 0, 0, 7]])
```

scipy.sparse.tril`scipy.sparse.tril` (*A*, *k=0*, *format=None*)

Return the lower triangular portion of a matrix in sparse format

Returns the elements on or below the *k*-th diagonal of the matrix *A*.

- $k = 0$ corresponds to the main diagonal
- $k > 0$ is above the main diagonal
- $k < 0$ is below the main diagonal

Parameters

- A** [dense or sparse matrix] Matrix whose lower triangular portion is desired.
- k** [integer] The top-most diagonal of the lower triangle.
- format** [string] Sparse format of the result, e.g. `format="csr"`, etc.

Returns

L [sparse matrix] Lower triangular portion of A in sparse format.

See also:

`triu`

upper triangle in sparse format

Examples

```
>>> from scipy.sparse import csr_matrix, tril
>>> A = csr_matrix([[1, 2, 0, 0, 3], [4, 5, 0, 6, 7], [0, 0, 8, 9, 0]],
...                dtype='int32')
>>> A.toarray()
array([[1, 2, 0, 0, 3],
       [4, 5, 0, 6, 7],
       [0, 0, 8, 9, 0]])
>>> tril(A).toarray()
array([[1, 0, 0, 0, 0],
       [4, 5, 0, 0, 0],
       [0, 0, 8, 0, 0]])
>>> tril(A).nnz
4
>>> tril(A, k=1).toarray()
array([[1, 2, 0, 0, 0],
       [4, 5, 0, 0, 0],
       [0, 0, 8, 9, 0]])
>>> tril(A, k=-1).toarray()
array([[0, 0, 0, 0, 0],
       [4, 0, 0, 0, 0],
       [0, 0, 0, 0, 0]])
>>> tril(A, format='csc')
<3x5 sparse matrix of type '<class 'numpy.int32''>'
  with 4 stored elements in Compressed Sparse Column format>
```

scipy.sparse.triu

`scipy.sparse.triu(A, k=0, format=None)`

Return the upper triangular portion of a matrix in sparse format

Returns the elements on or above the k-th diagonal of the matrix A.

- $k = 0$ corresponds to the main diagonal
- $k > 0$ is above the main diagonal
- $k < 0$ is below the main diagonal

Parameters

A [dense or sparse matrix] Matrix whose upper triangular portion is desired.
k [integer] The bottom-most diagonal of the upper triangle.
format [string] Sparse format of the result, e.g. `format="csr"`, etc.

Returns

L [sparse matrix] Upper triangular portion of A in sparse format.

See also:

tril

lower triangle in sparse format

Examples

```
>>> from scipy.sparse import csr_matrix, triu
>>> A = csr_matrix([[1, 2, 0, 0, 3], [4, 5, 0, 6, 7], [0, 0, 8, 9, 0]],
...                dtype='int32')
>>> A.toarray()
array([[1, 2, 0, 0, 3],
       [4, 5, 0, 6, 7],
       [0, 0, 8, 9, 0]])
>>> triu(A).toarray()
array([[1, 2, 0, 0, 3],
       [0, 5, 0, 6, 7],
       [0, 0, 8, 9, 0]])
>>> triu(A).nnz
8
>>> triu(A, k=1).toarray()
array([[0, 2, 0, 0, 3],
       [0, 0, 0, 6, 7],
       [0, 0, 0, 9, 0]])
>>> triu(A, k=-1).toarray()
array([[1, 2, 0, 0, 3],
       [4, 5, 0, 6, 7],
       [0, 0, 8, 9, 0]])
>>> triu(A, format='csc')
<3x5 sparse matrix of type '<class 'numpy.int32''>'
  with 8 stored elements in Compressed Sparse Column format>
```

scipy.sparse.bmat

`scipy.sparse.bmat` (*blocks*, *format=None*, *dtype=None*)

Build a sparse matrix from sparse sub-blocks

Parameters

- blocks** [array_like] Grid of sparse matrices with compatible shapes. An entry of None implies an all-zero matrix.
- format** [{‘bsr’, ‘coo’, ‘csc’, ‘csr’, ‘dia’, ‘dok’, ‘lil’}, optional] The sparse format of the result (e.g. “csr”). By default an appropriate sparse matrix format is returned. This choice is subject to change.
- dtype** [dtype, optional] The data-type of the output matrix. If not given, the dtype is determined from that of *blocks*.

Returns

- bmat** [sparse matrix]

See also:

block_diag, *diags*

Examples

```
>>> from scipy.sparse import coo_matrix, bmat
>>> A = coo_matrix([[1, 2], [3, 4]])
>>> B = coo_matrix([[5], [6]])
>>> C = coo_matrix([[7]])
>>> bmat([[A, B], [None, C]]).toarray()
array([[1, 2, 5],
       [3, 4, 6],
       [0, 0, 7]])
```

```
>>> bmat([[A, None], [None, C]]).toarray()
array([[1, 2, 0],
       [3, 4, 0],
       [0, 0, 7]])
```

scipy.sparse.hstack

`scipy.sparse.hstack` (*blocks, format=None, dtype=None*)

Stack sparse matrices horizontally (column wise)

Parameters

- blocks** sequence of sparse matrices with compatible shapes
- format** [str] sparse format of the result (e.g., “csr”) by default an appropriate sparse matrix format is returned. This choice is subject to change.
- dtype** [dtype, optional] The data-type of the output matrix. If not given, the dtype is determined from that of *blocks*.

See also:

vstack

stack sparse matrices vertically (row wise)

Examples

```
>>> from scipy.sparse import coo_matrix, hstack
>>> A = coo_matrix([[1, 2], [3, 4]])
>>> B = coo_matrix([[5], [6]])
>>> hstack([A,B]).toarray()
array([[1, 2, 5],
       [3, 4, 6]])
```

scipy.sparse.vstack

`scipy.sparse.vstack` (*blocks, format=None, dtype=None*)

Stack sparse matrices vertically (row wise)

Parameters

- blocks** sequence of sparse matrices with compatible shapes
- format** [str, optional] sparse format of the result (e.g., “csr”) by default an appropriate sparse matrix format is returned. This choice is subject to change.

dtype [dtype, optional] The data-type of the output matrix. If not given, the dtype is determined from that of *blocks*.

See also:

hstack

stack sparse matrices horizontally (column wise)

Examples

```
>>> from scipy.sparse import coo_matrix, vstack
>>> A = coo_matrix([[1, 2], [3, 4]])
>>> B = coo_matrix([[5, 6]])
>>> vstack([A, B]).toarray()
array([[1, 2],
       [3, 4],
       [5, 6]])
```

scipy.sparse.rand

`scipy.sparse.rand(m, n, density=0.01, format='coo', dtype=None, random_state=None)`

Generate a sparse matrix of the given shape and density with uniformly distributed values.

Parameters

m, n [int] shape of the matrix

density [real, optional] density of the generated matrix: density equal to one means a full matrix, density of 0 means a matrix with no non-zero items.

format [str, optional] sparse matrix format.

dtype [dtype, optional] type of the returned matrix values.

random_state [{numpy.random.RandomState, int, np.random.Generator}, optional] Random number generator or random seed. If not given, the singleton `numpy.random` will be used.

Returns

res [sparse matrix]

See also:

scipy.sparse.random

Similar function that allows a user-specified random data source.

Notes

Only float types are supported for now.

Examples

```
>>> from scipy.sparse import rand
>>> matrix = rand(3, 4, density=0.25, format="csr", random_state=42)
>>> matrix
<3x4 sparse matrix of type '<class 'numpy.float64'>'
  with 3 stored elements in Compressed Sparse Row format>
>>> matrix.todense()
matrix([[0.05641158, 0.          , 0.          , 0.65088847],
        [0.          , 0.          , 0.          , 0.14286682],
        [0.          , 0.          , 0.          , 0.          ]])
```

scipy.sparse.random

`scipy.sparse.random(m, n, density=0.01, format='coo', dtype=None, random_state=None, data_rvs=None)`

Generate a sparse matrix of the given shape and density with randomly distributed values.

Parameters

- m, n** [int] shape of the matrix
- density** [real, optional] density of the generated matrix: density equal to one means a full matrix, density of 0 means a matrix with no non-zero items.
- format** [str, optional] sparse matrix format.
- dtype** [dtype, optional] type of the returned matrix values.
- random_state** [{numpy.random.RandomState, int}, optional] Random number generator or random seed. If not given, the singleton `numpy.random` will be used. This random state will be used for sampling the sparsity structure, but not necessarily for sampling the values of the structurally nonzero entries of the matrix.
- data_rvs** [callable, optional] Samples a requested number of random values. This function should take a single argument specifying the length of the ndarray that it will return. The structurally nonzero entries of the sparse random matrix will be taken from the array sampled by this function. By default, uniform $[0, 1)$ random values will be sampled using the same random state as is used for sampling the sparsity structure.

Returns

- res** [sparse matrix]

Notes

Only float types are supported for now.

Examples

```
>>> from scipy.sparse import random
>>> from scipy import stats
```

```
>>> class CustomRandomState(np.random.RandomState):
...     def randint(self, k):
...         i = np.random.randint(k)
...         return i - i % 2
```

(continues on next page)

(continued from previous page)

```

>>> np.random.seed(12345)
>>> rs = CustomRandomState()
>>> rvs = stats.poisson(25, loc=10).rvs
>>> S = random(3, 4, density=0.25, random_state=rs, data_rvs=rvs)
>>> S.A
array([[ 36.,   0.,  33.,   0.], # random
       [  0.,   0.,   0.,   0.],
       [  0.,   0.,  36.,   0.]])

```

```

>>> from scipy.sparse import random
>>> from scipy.stats import rv_continuous
>>> class CustomDistribution(rv_continuous):
...     def _rvs(self, size=None, random_state=None):
...         return random_state.randn(*size)
>>> X = CustomDistribution(seed=2906)
>>> Y = X() # get a frozen version of the distribution
>>> S = random(3, 4, density=0.25, random_state=2906, data_rvs=Y.rvs)
>>> S.A
array([[ 0.          ,  0.          ,  0.          ,  0.          ],
       [ 0.13569738,  1.9467163 , -0.81205367,  0.          ],
       [ 0.          ,  0.          ,  0.          ,  0.          ]])

```

Save and load sparse matrices:

<code>save_npz(file, matrix[, compressed])</code>	Save a sparse matrix to a file using <code>.npz</code> format.
<code>load_npz(file)</code>	Load a sparse matrix from a file using <code>.npz</code> format.

scipy.sparse.save_npz

`scipy.sparse.save_npz` (*file, matrix, compressed=True*)

Save a sparse matrix to a file using `.npz` format.

Parameters

- file** [str or file-like object] Either the file name (string) or an open file (file-like object) where the data will be saved. If file is a string, the `.npz` extension will be appended to the file name if it is not already there.
- matrix: spmatrix (format: ```csc```, ```csr```, ```bsr```, ```dia``` or ```coo```)**
The sparse matrix to save.
- compressed**
[bool, optional] Allow compressing the file. Default: True

See also:

`scipy.sparse.load_npz`

Load a sparse matrix from a file using `.npz` format.

`numpy.savez`

Save several arrays into a `.npz` archive.

`numpy.savez_compressed`

Save several arrays into a compressed `.npz` archive.

Examples

Store sparse matrix to disk, and load it again:

```
>>> import scipy.sparse
>>> sparse_matrix = scipy.sparse.csc_matrix(np.array([[0, 0, 3], [4, 0, 0]]))
>>> sparse_matrix
<2x3 sparse matrix of type '<class 'numpy.int64''>'
  with 2 stored elements in Compressed Sparse Column format>
>>> sparse_matrix.todense()
matrix([[0, 0, 3],
        [4, 0, 0]], dtype=int64)
```

```
>>> scipy.sparse.save_npz('/tmp/sparse_matrix.npz', sparse_matrix)
>>> sparse_matrix = scipy.sparse.load_npz('/tmp/sparse_matrix.npz')
```

```
>>> sparse_matrix
<2x3 sparse matrix of type '<class 'numpy.int64''>'
  with 2 stored elements in Compressed Sparse Column format>
>>> sparse_matrix.todense()
matrix([[0, 0, 3],
        [4, 0, 0]], dtype=int64)
```

scipy.sparse.load_npz

`scipy.sparse.load_npz(file)`

Load a sparse matrix from a file using `.npz` format.

Parameters

file [str or file-like object] Either the file name (string) or an open file (file-like object) where the data will be loaded.

Returns

result [csc_matrix, csr_matrix, bsr_matrix, dia_matrix or coo_matrix] A sparse matrix containing the loaded data.

Raises

IOError If the input file does not exist or cannot be read.

See also:

`scipy.sparse.save_npz`

Save a sparse matrix to a file using `.npz` format.

`numpy.load`

Load several arrays from a `.npz` archive.

Examples

Store sparse matrix to disk, and load it again:

```
>>> import scipy.sparse
>>> sparse_matrix = scipy.sparse.csc_matrix(np.array([[0, 0, 3], [4, 0, 0]]))
>>> sparse_matrix
<2x3 sparse matrix of type '<class 'numpy.int64''>'
  with 2 stored elements in Compressed Sparse Column format>
>>> sparse_matrix.todense()
matrix([[0, 0, 3],
        [4, 0, 0]], dtype=int64)
```

```
>>> scipy.sparse.save_npz('/tmp/sparse_matrix.npz', sparse_matrix)
>>> sparse_matrix = scipy.sparse.load_npz('/tmp/sparse_matrix.npz')
```

```
>>> sparse_matrix
<2x3 sparse matrix of type '<class 'numpy.int64''>'
  with 2 stored elements in Compressed Sparse Column format>
>>> sparse_matrix.todense()
matrix([[0, 0, 3],
        [4, 0, 0]], dtype=int64)
```

Sparse matrix tools:

<code>find(A)</code>	Return the indices and values of the nonzero elements of a matrix
----------------------	---

scipy.sparse.find

`scipy.sparse.find(A)`

Return the indices and values of the nonzero elements of a matrix

Parameters

A [dense or sparse matrix] Matrix whose nonzero elements are desired.

Returns

(I,J,V) [tuple of arrays] I,J, and V contain the row indices, column indices, and values of the nonzero matrix entries.

Examples

```
>>> from scipy.sparse import csr_matrix, find
>>> A = csr_matrix([[7.0, 8.0, 0], [0, 0, 9.0]])
>>> find(A)
(array([0, 0, 1], dtype=int32), array([0, 1, 2], dtype=int32), array([ 7.,
  → 8., 9.]))
```

Identifying sparse matrices:

<code>issparse(x)</code>	Is x of a sparse matrix type?
<code>isspmatrix(x)</code>	Is x of a sparse matrix type?
<code>isspmatrix_csc(x)</code>	Is x of csc_matrix type?
<code>isspmatrix_csr(x)</code>	Is x of csr_matrix type?
<code>isspmatrix_bsr(x)</code>	Is x of a bsr_matrix type?
<code>isspmatrix_lil(x)</code>	Is x of lil_matrix type?
<code>isspmatrix_dok(x)</code>	Is x of dok_matrix type?
<code>isspmatrix_coo(x)</code>	Is x of coo_matrix type?
<code>isspmatrix_dia(x)</code>	Is x of dia_matrix type?

scipy.sparse.issparse

`scipy.sparse.issparse(x)`
Is x of a sparse matrix type?

Parameters

x object to check for being a sparse matrix

Returns

bool True if x is a sparse matrix, False otherwise

Notes

`issparse` and `isspmatrix` are aliases for the same function.

Examples

```
>>> from scipy.sparse import csr_matrix, isspmatrix
>>> isspmatrix(csr_matrix([[5]]))
True
```

```
>>> from scipy.sparse import isspmatrix
>>> isspmatrix(5)
False
```

scipy.sparse.isspmatrix

`scipy.sparse.isspmatrix(x)`
Is x of a sparse matrix type?

Parameters

x object to check for being a sparse matrix

Returns

bool True if x is a sparse matrix, False otherwise

Notes

`issparse` and `isspmatrix` are aliases for the same function.

Examples

```
>>> from scipy.sparse import csr_matrix, isspmatrix
>>> isspmatrix(csr_matrix([[5]]))
True
```

```
>>> from scipy.sparse import isspmatrix
>>> isspmatrix(5)
False
```

`scipy.sparse.isspmatrix_csc`

`scipy.sparse.isspmatrix_csc(x)`
Is `x` of `csc_matrix` type?

Parameters

x object to check for being a csc matrix

Returns

bool True if `x` is a csc matrix, False otherwise

Examples

```
>>> from scipy.sparse import csc_matrix, isspmatrix_csc
>>> isspmatrix_csc(csc_matrix([[5]]))
True
```

```
>>> from scipy.sparse import csc_matrix, csr_matrix, isspmatrix_csc
>>> isspmatrix_csc(csr_matrix([[5]]))
False
```

`scipy.sparse.isspmatrix_csr`

`scipy.sparse.isspmatrix_csr(x)`
Is `x` of `csr_matrix` type?

Parameters

x object to check for being a csr matrix

Returns

bool True if `x` is a csr matrix, False otherwise

Examples

```
>>> from scipy.sparse import csr_matrix, isspmatrix_csr
>>> isspmatrix_csr(csr_matrix([[5]]))
True
```

```
>>> from scipy.sparse import csc_matrix, csr_matrix, isspmatrix_csc
>>> isspmatrix_csr(csc_matrix([[5]]))
False
```

scipy.sparse.isspmatrix_bsr

scipy.sparse.isspmatrix_bsr(x)

Is x of a bsr_matrix type?

Parameters

x object to check for being a bsr matrix

Returns

bool True if x is a bsr matrix, False otherwise

Examples

```
>>> from scipy.sparse import bsr_matrix, isspmatrix_bsr
>>> isspmatrix_bsr(bsr_matrix([[5]]))
True
```

```
>>> from scipy.sparse import bsr_matrix, csr_matrix, isspmatrix_bsr
>>> isspmatrix_bsr(csr_matrix([[5]]))
False
```

scipy.sparse.isspmatrix_lil

scipy.sparse.isspmatrix_lil(x)

Is x of lil_matrix type?

Parameters

x object to check for being a lil matrix

Returns

bool True if x is a lil matrix, False otherwise

Examples

```
>>> from scipy.sparse import lil_matrix, isspmatrix_lil
>>> isspmatrix_lil(lil_matrix([[5]]))
True
```

```
>>> from scipy.sparse import lil_matrix, csr_matrix, isspmatrix_lil
>>> isspmatrix_lil(csr_matrix([[5]]))
False
```

scipy.sparse.isspmatrix_dok

`scipy.sparse.isspmatrix_dok(x)`

Is `x` of `dok_matrix` type?

Parameters

x object to check for being a `dok_matrix`

Returns

bool True if `x` is a `dok_matrix`, False otherwise

Examples

```
>>> from scipy.sparse import dok_matrix, isspmatrix_dok
>>> isspmatrix_dok(dok_matrix([[5]]))
True
```

```
>>> from scipy.sparse import dok_matrix, csr_matrix, isspmatrix_dok
>>> isspmatrix_dok(csr_matrix([[5]]))
False
```

scipy.sparse.isspmatrix_coo

`scipy.sparse.isspmatrix_coo(x)`

Is `x` of `coo_matrix` type?

Parameters

x object to check for being a `coo_matrix`

Returns

bool True if `x` is a `coo_matrix`, False otherwise

Examples

```
>>> from scipy.sparse import coo_matrix, isspmatrix_coo
>>> isspmatrix_coo(coo_matrix([[5]]))
True
```

```
>>> from scipy.sparse import coo_matrix, csr_matrix, isspmatrix_coo
>>> isspmatrix_coo(csr_matrix([[5]]))
False
```

scipy.sparse.isspmatrix_dia

`scipy.sparse.isspmatrix_dia(x)`

Is x of `dia_matrix` type?

Parameters

x object to check for being a dia matrix

Returns

bool True if x is a dia matrix, False otherwise

Examples

```
>>> from scipy.sparse import dia_matrix, isspmatrix_dia
>>> isspmatrix_dia(dia_matrix([[5]]))
True
```

```
>>> from scipy.sparse import dia_matrix, csr_matrix, isspmatrix_dia
>>> isspmatrix_dia(csr_matrix([[5]]))
False
```

Submodules

<code>csgraph</code>	Compressed sparse graph routines (<code>scipy.sparse.csgraph</code>)
<code>linalg</code>	Sparse linear algebra (<code>scipy.sparse.linalg</code>)

Exceptions

<code>SparseEfficiencyWarning</code>
<code>SparseWarning</code>

scipy.sparse.SparseEfficiencyWarning

exception `scipy.sparse.SparseEfficiencyWarning`

`with_traceback()`

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

scipy.sparse.SparseWarning

exception `scipy.sparse.SparseWarning`

`with_traceback()`

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

6.23.2 Usage information

There are seven available sparse matrix types:

1. `csc_matrix`: Compressed Sparse Column format
2. `csr_matrix`: Compressed Sparse Row format
3. `bsr_matrix`: Block Sparse Row format
4. `lil_matrix`: List of Lists format
5. `dok_matrix`: Dictionary of Keys format
6. `coo_matrix`: COOrdinate format (aka IJV, triplet format)
7. `dia_matrix`: DIAgonal format

To construct a matrix efficiently, use either `dok_matrix` or `lil_matrix`. The `lil_matrix` class supports basic slicing and fancy indexing with a similar syntax to NumPy arrays. As illustrated below, the COO format may also be used to efficiently construct matrices. Despite their similarity to NumPy arrays, it is **strongly discouraged** to use NumPy functions directly on these matrices because NumPy may not properly convert them for computations, leading to unexpected (and incorrect) results. If you do want to apply a NumPy function to these matrices, first check if SciPy has its own implementation for the given sparse matrix class, or **convert the sparse matrix to a NumPy array** (e.g., using the `toarray()` method of the class) first before applying the method.

To perform manipulations such as multiplication or inversion, first convert the matrix to either CSC or CSR format. The `lil_matrix` format is row-based, so conversion to CSR is efficient, whereas conversion to CSC is less so.

All conversions among the CSR, CSC, and COO formats are efficient, linear-time operations.

Matrix vector product

To do a vector product between a sparse matrix and a vector simply use the matrix `dot` method, as described in its docstring:

```
>>> import numpy as np
>>> from scipy.sparse import csr_matrix
>>> A = csr_matrix([[1, 2, 0], [0, 0, 3], [4, 0, 5]])
>>> v = np.array([1, 0, -1])
>>> A.dot(v)
array([ 1, -3, -1], dtype=int64)
```

Warning: As of NumPy 1.7, *np.dot* is not aware of sparse matrices, therefore using it will result on unexpected results or errors. The corresponding dense array should be obtained first instead:

```
>>> np.dot(A.toarray(), v)
array([ 1, -3, -1], dtype=int64)
```

but then all the performance advantages would be lost.

The CSR format is specially suitable for fast matrix vector products.

Example 1

Construct a 1000x1000 `lil_matrix` and add some values to it:

```
>>> from scipy.sparse import lil_matrix
>>> from scipy.sparse.linalg import spsolve
>>> from numpy.linalg import solve, norm
>>> from numpy.random import rand
```

```
>>> A = lil_matrix((1000, 1000))
>>> A[0, :100] = rand(100)
>>> A[1, 100:200] = A[0, :100]
>>> A.setdiag(rand(1000))
```

Now convert it to CSR format and solve $Ax = b$ for x :

```
>>> A = A.tocsr()
>>> b = rand(1000)
>>> x = spsolve(A, b)
```

Convert it to a dense matrix and solve, and check that the result is the same:

```
>>> x_ = solve(A.toarray(), b)
```

Now we can compute norm of the error with:

```
>>> err = norm(x-x_)
>>> err < 1e-10
True
```

It should be small :)

Example 2

Construct a matrix in COO format:

```
>>> from scipy import sparse
>>> from numpy import array
>>> I = array([0, 3, 1, 0])
>>> J = array([0, 3, 1, 2])
>>> V = array([4, 5, 7, 9])
>>> A = sparse.coo_matrix((V, (I, J)), shape=(4, 4))
```


Notice that the indices do not need to be sorted.

Duplicate (i,j) entries are summed when converting to CSR or CSC.

```
>>> I = array([0, 0, 1, 3, 1, 0, 0])
>>> J = array([0, 2, 1, 3, 1, 0, 0])
>>> V = array([1, 1, 1, 1, 1, 1, 1])
>>> B = sparse.coo_matrix((V, (I, J)), shape=(4, 4)).tocsr()
```

This is useful for constructing finite-element stiffness and mass matrices.

Further details

CSR column indices are not necessarily sorted. Likewise for CSC row indices. Use the `.sorted_indices()` and `.sort_indices()` methods when sorted indices are required (e.g., when passing data to other libraries).

6.24 Sparse linear algebra (`scipy.sparse.linalg`)

6.24.1 Abstract linear operators

<code>LinearOperator(*args, **kwargs)</code>	Common interface for performing matrix vector products
<code>aslinearoperator(A)</code>	Return A as a LinearOperator.

`scipy.sparse.linalg.LinearOperator`

class `scipy.sparse.linalg.LinearOperator` (*args, **kwargs)

Common interface for performing matrix vector products

Many iterative methods (e.g. `cg`, `gmres`) do not need to know the individual entries of a matrix to solve a linear system $A*x=b$. Such solvers only require the computation of matrix vector products, $A*v$ where v is a dense vector. This class serves as an abstract interface between iterative solvers and matrix-like objects.

To construct a concrete `LinearOperator`, either pass appropriate callables to the constructor of this class, or subclass it.

A subclass must implement either one of the methods `_matvec` and `_matmat`, and the attributes/properties `shape` (pair of integers) and `dtype` (may be `None`). It may call the `__init__` on this class to have these attributes validated. Implementing `_matvec` automatically implements `_matmat` (using a naive algorithm) and vice-versa.

Optionally, a subclass may implement `_rmatvec` or `_adjoint` to implement the Hermitian adjoint (conjugate transpose). As with `_matvec` and `_matmat`, implementing either `_rmatvec` or `_adjoint` implements the other automatically. Implementing `_adjoint` is preferable; `_rmatvec` is mostly there for backwards compatibility.

Parameters

shape	[tuple] Matrix dimensions (M, N).
matvec	[callable f(v)] Returns returns $A * v$.
rmatvec	[callable f(v)] Returns $A^H * v$, where A^H is the conjugate transpose of A .
matmat	[callable f(V)] Returns $A * V$, where V is a dense matrix with dimensions (N, K).
dtype	[dtype] Data type of the matrix.
rmatmat	[callable f(V)] Returns $A^H * V$, where V is a dense matrix with dimensions (M, K).

See also:

aslinearoperator

Construct LinearOperators

Notes

The user-defined `matvec()` function must properly handle the case where `v` has shape `(N,)` as well as the `(N,1)` case. The shape of the return type is handled internally by `LinearOperator`.

`LinearOperator` instances can also be multiplied, added with each other and exponentiated, all lazily: the result of these operations is always a new, composite `LinearOperator`, that defers linear operations to the original operators and combines the results.

More details regarding how to subclass a `LinearOperator` and several examples of concrete `LinearOperator` instances can be found in the external project [PyLops](#).

Examples

```
>>> import numpy as np
>>> from scipy.sparse.linalg import LinearOperator
>>> def mv(v):
...     return np.array([2*v[0], 3*v[1]])
...
>>> A = LinearOperator((2,2), matvec=mv)
>>> A
<2x2 _CustomLinearOperator with dtype=float64>
>>> A.matvec(np.ones(2))
array([ 2.,  3.])
>>> A * np.ones(2)
array([ 2.,  3.])
```

Attributes

- args** [tuple] For linear operators describing products etc. of other linear operators, the operands of the binary operation.
- ndim** [int] Number of dimensions (this is always 2)

Methods

<code>__call__(self, x)</code>	Call self as a function.
<code>adjoint(self)</code>	Hermitian adjoint.
<code>dot(self, x)</code>	Matrix-matrix or matrix-vector multiplication.
<code>matmat(self, X)</code>	Matrix-matrix multiplication.
<code>matvec(self, x)</code>	Matrix-vector multiplication.
<code>rmatmat(self, X)</code>	Adjoint matrix-matrix multiplication.
<code>rmatvec(self, x)</code>	Adjoint matrix-vector multiplication.
<code>transpose(self)</code>	Transpose this linear operator.

scipy.sparse.linalg.LinearOperator.__call__

`LinearOperator.__call__(self, x)`
 Call self as a function.

scipy.sparse.linalg.LinearOperator.adjoint

`LinearOperator.adjoint(self)`
 Hermitian adjoint.

Returns the Hermitian adjoint of self, aka the Hermitian conjugate or Hermitian transpose. For a complex matrix, the Hermitian adjoint is equal to the conjugate transpose.

Can be abbreviated self.H instead of self.adjoint().

Returns

A_H [LinearOperator] Hermitian adjoint of self.

scipy.sparse.linalg.LinearOperator.dot

`LinearOperator.dot(self, x)`
 Matrix-matrix or matrix-vector multiplication.

Parameters

x [array_like] 1-d or 2-d array, representing a vector or matrix.

Returns

Ax [array] 1-d or 2-d array (depending on the shape of x) that represents the result of applying this linear operator on x.

scipy.sparse.linalg.LinearOperator.matmat

`LinearOperator.matmat(self, X)`
 Matrix-matrix multiplication.

Performs the operation $y=A*X$ where A is an $M \times N$ linear operator and X dense $N \times K$ matrix or ndarray.

Parameters

X [{matrix, ndarray}] An array with shape (N,K).

Returns

Y [{matrix, ndarray}] A matrix or ndarray with shape (M,K) depending on the type of the X argument.

Notes

This matmat wraps any user-specified matmat routine or overridden `_matmat` method to ensure that y has the correct type.

scipy.sparse.linalg.LinearOperator.matvec`LinearOperator.matvec` (*self*, *x*)

Matrix-vector multiplication.

Performs the operation $y=A*x$ where A is an $M \times N$ linear operator and x is a column vector or 1-d array.**Parameters****x** [{matrix, ndarray}] An array with shape (N,) or (N,1).**Returns****y** [{matrix, ndarray}] A matrix or ndarray with shape (M,) or (M,1) depending on the type and shape of the x argument.**Notes**This `matvec` wraps the user-specified `matvec` routine or overridden `_matvec` method to ensure that y has the correct shape and type.**scipy.sparse.linalg.LinearOperator.rmatmat**`LinearOperator.rmatmat` (*self*, *X*)

Adjoint matrix-matrix multiplication.

Performs the operation $y = A^H * x$ where A is an $M \times N$ linear operator and x is a column vector or 1-d array, or 2-d array. The default implementation defers to the adjoint.**Parameters****X** [{matrix, ndarray}] A matrix or 2D array.**Returns****Y** [{matrix, ndarray}] A matrix or 2D array depending on the type of the input.**Notes**This `rmatmat` wraps the user-specified `rmatmat` routine.**scipy.sparse.linalg.LinearOperator.rmatvec**`LinearOperator.rmatvec` (*self*, *x*)

Adjoint matrix-vector multiplication.

Performs the operation $y = A^H * x$ where A is an $M \times N$ linear operator and x is a column vector or 1-d array.**Parameters****x** [{matrix, ndarray}] An array with shape (M,) or (M,1).**Returns****y** [{matrix, ndarray}] A matrix or ndarray with shape (N,) or (N,1) depending on the type and shape of the x argument.

Notes

This `rmatvec` wraps the user-specified `rmatvec` routine or overridden `_rmatvec` method to ensure that `y` has the correct shape and type.

`scipy.sparse.linalg.LinearOperator.transpose`

`LinearOperator.transpose` (*self*)

Transpose this linear operator.

Returns a `LinearOperator` that represents the transpose of this one. Can be abbreviated `self.T` instead of `self.transpose()`.

<code>__mul__</code>	
----------------------	--

`scipy.sparse.linalg.aslinearoperator`

`scipy.sparse.linalg.aslinearoperator` (*A*)

Return *A* as a `LinearOperator`.

'A' may be any of the following types:

- `ndarray`
- `matrix`
- sparse matrix (e.g. `csr_matrix`, `lil_matrix`, etc.)
- `LinearOperator`
- An object with `.shape` and `.matvec` attributes

See the `LinearOperator` documentation for additional information.

Notes

If *'A'* has no `.dtype` attribute, the data type is determined by calling `LinearOperator.matvec` - set the `.dtype` attribute to prevent this call upon the linear operator creation.

Examples

```
>>> from scipy.sparse.linalg import aslinearoperator
>>> M = np.array([[1, 2, 3], [4, 5, 6]], dtype=np.int32)
>>> aslinearoperator(M)
<2x3 MatrixLinearOperator with dtype=int32>
```

6.24.2 Matrix Operations

<code>inv(A)</code>	Compute the inverse of a sparse matrix
<code>expm(A)</code>	Compute the matrix exponential using Pade approximation.
<code>expm_multiply(A, B[, start, stop, num, endpoint])</code>	Compute the action of the matrix exponential of A on B.

`scipy.sparse.linalg.inv`

`scipy.sparse.linalg.inv(A)`
Compute the inverse of a sparse matrix

Parameters

A [(M,M) ndarray or sparse matrix] square matrix to be inverted

Returns

Ainv [(M,M) ndarray or sparse matrix] inverse of A

Notes

This computes the sparse inverse of A. If the inverse of A is expected to be non-sparse, it will likely be faster to convert A to dense and use `scipy.linalg.inv`.

Examples

```
>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import inv
>>> A = csc_matrix([[1., 0.], [1., 2.]])
>>> Ainv = inv(A)
>>> Ainv
<2x2 sparse matrix of type '<class 'numpy.float64'>'
  with 3 stored elements in Compressed Sparse Column format>
>>> A.dot(Ainv)
<2x2 sparse matrix of type '<class 'numpy.float64'>'
  with 2 stored elements in Compressed Sparse Column format>
>>> A.dot(Ainv).todense()
matrix([[ 1.,  0.],
        [ 0.,  1.]])
```

New in version 0.12.0.

scipy.sparse.linalg.expm`scipy.sparse.linalg.expm(A)`

Compute the matrix exponential using Pade approximation.

Parameters**A** [(M,M) array_like or sparse matrix] 2D Array or Matrix (sparse or dense) to be exponentiated**Returns****expA** [(M,M) ndarray] Matrix exponential of A**Notes**

This is algorithm (6.1) which is a simplification of algorithm (5.1).

New in version 0.12.0.

References

[1]

Examples

```

>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import expm
>>> A = csc_matrix([[1, 0, 0], [0, 2, 0], [0, 0, 3]])
>>> A.todense()
matrix([[1, 0, 0],
        [0, 2, 0],
        [0, 0, 3]], dtype=int64)
>>> Aexp = expm(A)
>>> Aexp
<3x3 sparse matrix of type '<class 'numpy.float64''>'
  with 3 stored elements in Compressed Sparse Column format>
>>> Aexp.todense()
matrix([[ 2.71828183,  0.          ,  0.          ],
        [ 0.          ,  7.3890561 ,  0.          ],
        [ 0.          ,  0.          , 20.08553692]])

```

scipy.sparse.linalg.expm_multiply`scipy.sparse.linalg.expm_multiply(A, B, start=None, stop=None, num=None, endpoint=None)`

Compute the action of the matrix exponential of A on B.

Parameters

A [transposable linear operator] The operator whose exponential is of interest.
B [ndarray] The matrix or vector to be multiplied by the matrix exponential of A.
start [scalar, optional] The starting time point of the sequence.

stop [scalar, optional] The end time point of the sequence, unless *endpoint* is set to False. In that case, the sequence consists of all but the last of `num + 1` evenly spaced time points, so that *stop* is excluded. Note that the step size changes when *endpoint* is False.

num [int, optional] Number of time points to use.

endpoint [bool, optional] If True, *stop* is the last time point. Otherwise, it is not included.

Returns

expm_A_B
[ndarray] The result of the action $e^{t_k A} B$.

Notes

The optional arguments defining the sequence of evenly spaced time points are compatible with the arguments of `numpy.linspace`.

The output ndarray shape is somewhat complicated so I explain it here. The ndim of the output could be either 1, 2, or 3. It would be 1 if you are computing the expm action on a single vector at a single time point. It would be 2 if you are computing the expm action on a vector at multiple time points, or if you are computing the expm action on a matrix at a single time point. It would be 3 if you want the action on a matrix with multiple columns at multiple time points. If multiple time points are requested, `expm_A_B[0]` will always be the action of the expm at the first time point, regardless of whether the action is on a vector or a matrix.

References

[1], [2]

Examples

```
>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import expm, expm_multiply
>>> A = csc_matrix([[1, 0], [0, 1]])
>>> A.todense()
matrix([[1, 0],
        [0, 1]], dtype=int64)
>>> B = np.array([np.exp(-1.), np.exp(-2.)])
>>> B
array([ 0.36787944,  0.13533528])
>>> expm_multiply(A, B, start=1, stop=2, num=3, endpoint=True)
array([[ 1.          ,  0.36787944],
       [ 1.64872127,  0.60653066],
       [ 2.71828183,  1.          ]])
>>> expm(A).dot(B)                                     # Verify 1st timestep
array([ 1.          ,  0.36787944])
>>> expm(1.5*A).dot(B)                                 # Verify 2nd timestep
array([ 1.64872127,  0.60653066])
>>> expm(2*A).dot(B)                                  # Verify 3rd timestep
array([ 2.71828183,  1.          ])
```


6.24.3 Matrix norms

<code>norm(x[, ord, axis])</code>	Norm of a sparse matrix
<code>onenormest(A[, t, itmax, compute_v, compute_w])</code>	Compute a lower bound of the 1-norm of a sparse matrix.

`scipy.sparse.linalg.norm`

`scipy.sparse.linalg.norm(x, ord=None, axis=None)`

Norm of a sparse matrix

This function is able to return one of seven different matrix norms, depending on the value of the `ord` parameter.

Parameters

x	[a sparse matrix] Input sparse matrix.
ord	[{non-zero int, inf, -inf, 'fro'}, optional] Order of the norm (see table under Notes). <code>inf</code> means numpy's <i>inf</i> object.
axis	[{int, 2-tuple of ints, None}, optional] If <i>axis</i> is an integer, it specifies the axis of <i>x</i> along which to compute the vector norms. If <i>axis</i> is a 2-tuple, it specifies the axes that hold 2-D matrices, and the matrix norms of these matrices are computed. If <i>axis</i> is None then either a vector norm (when <i>x</i> is 1-D) or a matrix norm (when <i>x</i> is 2-D) is returned.

Returns

n	[float or ndarray]
----------	--------------------

Notes

Some of the `ord` are not implemented because some associated functions like, `_multi_svd_norm`, are not yet available for sparse matrix.

This docstring is modified based on `numpy.linalg.norm`. <https://github.com/numpy/numpy/blob/master/numpy/linalg/linalg.py>

The following norms can be calculated:

ord	norm for sparse matrices
None	Frobenius norm
'fro'	Frobenius norm
inf	<code>max(sum(abs(x), axis=1))</code>
-inf	<code>min(sum(abs(x), axis=1))</code>
0	<code>abs(x).sum(axis=axis)</code>
1	<code>max(sum(abs(x), axis=0))</code>
-1	<code>min(sum(abs(x), axis=0))</code>
2	Not implemented
-2	Not implemented
other	Not implemented

The Frobenius norm is given by [1]:

$$\|A\|_F = [\sum_{i,j} \text{abs}(a_{i,j})^2]^{1/2}$$

References

[1]

Examples

```
>>> from scipy.sparse import *
>>> import numpy as np
>>> from scipy.sparse.linalg import norm
>>> a = np.arange(9) - 4
>>> a
array([-4, -3, -2, -1, 0, 1, 2, 3, 4])
>>> b = a.reshape((3, 3))
>>> b
array([[ -4,  -3,  -2],
       [ -1,   0,   1],
       [  2,   3,   4]])
```

```
>>> b = csr_matrix(b)
>>> norm(b)
7.745966692414834
>>> norm(b, 'fro')
7.745966692414834
>>> norm(b, np.inf)
9
>>> norm(b, -np.inf)
2
>>> norm(b, 1)
7
>>> norm(b, -1)
6
```

scipy.sparse.linalg.onenormest

`scipy.sparse.linalg.onenormest` (A , $t=2$, $itmax=5$, $compute_v=False$, $compute_w=False$)

Compute a lower bound of the 1-norm of a sparse matrix.

Parameters

- A** [ndarray or other linear operator] A linear operator that can be transposed and that can produce matrix products.
- t** [int, optional] A positive parameter controlling the tradeoff between accuracy versus time and memory usage. Larger values take longer and use more memory but give more accurate output.
- itmax** [int, optional] Use at most this many iterations.
- compute_v** [bool, optional] Request a norm-maximizing linear operator input vector if True.
- compute_w** [bool, optional] Request a norm-maximizing linear operator output vector if True.

Returns

- est** [float] An underestimate of the 1-norm of the sparse matrix.

- v** [ndarray, optional] The vector such that $\|Av\|_1 == \text{est} * \|v\|_1$. It can be thought of as an input to the linear operator that gives an output with particularly large norm.
- w** [ndarray, optional] The vector Av which has relatively large 1-norm. It can be thought of as an output of the linear operator that is relatively large in norm compared to the input.

Notes

This is algorithm 2.4 of [1].

In [2] it is described as follows. “This algorithm typically requires the evaluation of about $4t$ matrix-vector products and almost invariably produces a norm estimate (which is, in fact, a lower bound on the norm) correct to within a factor 3.”

New in version 0.13.0.

References

[1], [2]

Examples

```
>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import onenormest
>>> A = csc_matrix([[1., 0., 0.], [5., 8., 2.], [0., -1., 0.]],
dtype=float)
>>> A.todense()
matrix([[ 1.,  0.,  0.],
        [ 5.,  8.,  2.],
        [ 0., -1.,  0.]])
>>> onenormest(A)
9.0
>>> np.linalg.norm(A.todense(), ord=1)
9.0
```

6.24.4 Solving linear problems

Direct methods for linear equation systems:

<code>spsolve(A, b[, permc_spec, use_umfpack])</code>	Solve the sparse linear system $Ax=b$, where b may be a vector or a matrix.
<code>spsolve_triangular(A, b[, lower, ...])</code>	Solve the equation $A x = b$ for x , assuming A is a triangular matrix.
<code>factorized(A)</code>	Return a function for solving a sparse linear system, with A pre-factorized.
<code>MatrixRankWarning</code>	
<code>use_solver(**kwargs)</code>	Select default sparse direct solver to be used.

scipy.sparse.linalg.spsolve

`scipy.sparse.linalg.spsolve` (*A*, *b*, *perm_spec=None*, *use_umfpack=True*)

Solve the sparse linear system $Ax=b$, where *b* may be a vector or a matrix.

Parameters

- A** [ndarray or sparse matrix] The square matrix *A* will be converted into CSC or CSR form
- b** [ndarray or sparse matrix] The matrix or vector representing the right hand side of the equation. If a vector, *b.shape* must be (*n*,) or (*n*, 1).
- perm_spec** [str, optional] How to permute the columns of the matrix for sparsity preservation. (default: 'COLAMD')
- NATURAL: natural ordering.
 - MMD_ATA: minimum degree ordering on the structure of $A^T A$.
 - MMD_AT_PLUS_A: minimum degree ordering on the structure of $A^T A + A$.
 - COLAMD: approximate minimum degree column ordering
- use_umfpack** [bool, optional] if True (default) then use umfpack for the solution. This is only referenced if *b* is a vector and `scikit-umfpack` is installed.

Returns

- x** [ndarray or sparse matrix] the solution of the sparse linear equation. If *b* is a vector, then *x* is a vector of size *A.shape*[1] If *b* is a matrix, then *x* is a matrix of size (*A.shape*[1], *b.shape*[1])

Notes

For solving the matrix expression $AX = B$, this solver assumes the resulting matrix *X* is sparse, as is often the case for very sparse inputs. If the resulting *X* is dense, the construction of this sparse result will be relatively expensive. In that case, consider converting *A* to a dense matrix and using `scipy.linalg.solve` or its variants.

Examples

```
>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import spsolve
>>> A = csc_matrix([[3, 2, 0], [1, -1, 0], [0, 5, 1]], dtype=float)
>>> B = csc_matrix([[2, 0], [-1, 0], [2, 0]], dtype=float)
>>> x = spsolve(A, B)
>>> np.allclose(A.dot(x).todense(), B.todense())
True
```

scipy.sparse.linalg.spsolve_triangular

`scipy.sparse.linalg.spsolve_triangular` (*A*, *b*, *lower=True*, *overwrite_A=False*, *overwrite_b=False*, *unit_diagonal=False*)

Solve the equation $A x = b$ for *x*, assuming *A* is a triangular matrix.

Parameters

- A** [(M, M) sparse matrix] A sparse square triangular matrix. Should be in CSR format.
- b** [(M,) or (M, N) array_like] Right-hand side matrix in $A x = b$
- lower** [bool, optional] Whether *A* is a lower or upper triangular matrix. Default is lower triangular matrix.

overwrite_A

[bool, optional] Allow changing A . The indices of A are going to be sorted and zero entries are going to be removed. Enabling gives a performance gain. Default is False.

overwrite_b

[bool, optional] Allow overwriting data in b . Enabling gives a performance gain. Default is False. If *overwrite_b* is True, it should be ensured that b has an appropriate dtype to be able to store the result.

unit_diagonal

[bool, optional] If True, diagonal elements of a are assumed to be 1 and will not be referenced.

New in version 1.4.0.

Returns

x [(M,) or (M, N) ndarray] Solution to the system $A x = b$. Shape of return matches shape of b .

Raises**LinAlgError**

If A is singular or not triangular.

ValueError

If shape of A or shape of b do not match the requirements.

Notes

New in version 0.19.0.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.linalg import spsolve_triangular
>>> A = csr_matrix([[3, 0, 0], [1, -1, 0], [2, 0, 1]], dtype=float)
>>> B = np.array([[2, 0], [-1, 0], [2, 0]], dtype=float)
>>> x = spsolve_triangular(A, B)
>>> np.allclose(A.dot(x), B)
True
```

scipy.sparse.linalg.factorized

`scipy.sparse.linalg.factorized(A)`

Return a function for solving a sparse linear system, with A pre-factorized.

Parameters

A [(N, N) array_like] Input.

Returns

solve [callable] To solve the linear system of equations given in A , the *solve* callable should be passed an ndarray of shape (N,).

Examples

```
>>> from scipy.sparse.linalg import factorized
>>> A = np.array([[ 3. ,  2. , -1. ],
...             [ 2. , -2. ,  4. ],
...             [-1. ,  0.5, -1. ]])
>>> solve = factorized(A) # Makes LU decomposition.
>>> rhs1 = np.array([1, -2, 0])
>>> solve(rhs1) # Uses the LU factors.
array([ 1., -2., -2.])
```

scipy.sparse.linalg.MatrixRankWarning

exception `scipy.sparse.linalg.MatrixRankWarning`

with_traceback()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

scipy.sparse.linalg.use_solver

`scipy.sparse.linalg.use_solver(**kwargs)`

Select default sparse direct solver to be used.

Parameters

useUmfpack

[bool, optional] Use UMFPACK over SuperLU. Has effect only if scikits.umfpack is installed. Default: True

assumeSortedIndices

[bool, optional] Allow UMFPACK to skip the step of sorting indices for a CSR/CSC matrix. Has effect only if useUmfpack is True and scikits.umfpack is installed. Default: False

Notes

The default sparse solver is umfpack when available (scikits.umfpack is installed). This can be changed by passing `useUmfpack = False`, which then causes the always present SuperLU based solver to be used.

Umfpack requires a CSR/CSC matrix to have sorted column/row indices. If sure that the matrix fulfills this, pass `assumeSortedIndices=True` to gain some speed.

Iterative methods for linear equation systems:

<code>bicg(A, b[, x0, tol, maxiter, M, callback, atol])</code>	Use BIConjugate Gradient iteration to solve $Ax = b$.
<code>bicgstab(A, b[, x0, tol, maxiter, M, ...])</code>	Use BIConjugate Gradient STABILized iteration to solve $Ax = b$.
<code>cg(A, b[, x0, tol, maxiter, M, callback, atol])</code>	Use Conjugate Gradient iteration to solve $Ax = b$.
<code>cgs(A, b[, x0, tol, maxiter, M, callback, atol])</code>	Use Conjugate Gradient Squared iteration to solve $Ax = b$.
<code>gmres(A, b[, x0, tol, restart, maxiter, M, ...])</code>	Use Generalized Minimal RESidual iteration to solve $Ax = b$.
<code>lgmres(A, b[, x0, tol, maxiter, M, ...])</code>	Solve a matrix equation using the LGMRES algorithm.

continues on next page

Table 192 – continued from previous page

<code>minres(A, b[, x0, shift, tol, maxiter, M, ...])</code>	Use MINimum RESidual iteration to solve $Ax=b$
<code>qmr(A, b[, x0, tol, maxiter, M1, M2, ...])</code>	Use Quasi-Minimal Residual iteration to solve $Ax = b$.
<code>gcrotmk(A, b[, x0, tol, maxiter, M, ...])</code>	Solve a matrix equation using flexible GCROT(m,k) algorithm.

scipy.sparse.linalg.bicg

`scipy.sparse.linalg.bicg(A, b, x0=None, tol=1e-05, maxiter=None, M=None, callback=None, atol=None)`

Use BIConjugate Gradient iteration to solve $Ax = b$.

Parameters

- A** `[{sparse matrix, dense matrix, LinearOperator}]` The real or complex N-by-N matrix of the linear system. Alternatively, A can be a linear operator which can produce Ax and $A^T x$ using, e.g., `scipy.sparse.linalg.LinearOperator`.
- b** `[{array, matrix}]` Right hand side of the linear system. Has shape (N,) or (N,1).

Returns

- x** `[{array, matrix}]` The converged solution.
- info** `[integer]`

Provides convergence information:

0 : successful exit >0 : convergence to tolerance not achieved, number of iterations <0 : illegal input or breakdown

Other Parameters

- x0** `[{array, matrix}]` Starting guess for the solution.
- tol, atol** `[float, optional]` Tolerances for convergence, `norm(residual) <= max(tol*norm(b), atol)`. The default for `atol` is 'legacy', which emulates a different legacy behavior.

Warning: The default value for `atol` will be changed in a future release. For future compatibility, specify `atol` explicitly.

- maxiter** `[integer]` Maximum number of iterations. Iteration will stop after `maxiter` steps even if the specified tolerance has not been achieved.
- M** `[{sparse matrix, dense matrix, LinearOperator}]` Preconditioner for A. The preconditioner should approximate the inverse of A. Effective preconditioning dramatically improves the rate of convergence, which implies that fewer iterations are needed to reach a given error tolerance.
- callback** `[function]` User-supplied function to call after each iteration. It is called as `callback(xk)`, where `xk` is the current solution vector.

Examples

```

>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import bicg
>>> A = csc_matrix([[3, 2, 0], [1, -1, 0], [0, 5, 1]], dtype=float)
>>> b = np.array([2, 4, -1], dtype=float)
>>> x, exitCode = bicg(A, b)
>>> print(exitCode)           # 0 indicates successful convergence
0
>>> np.allclose(A.dot(x), b)
True

```

scipy.sparse.linalg.bicgstab

`scipy.sparse.linalg.bicgstab` (*A*, *b*, *x0=None*, *tol=1e-05*, *maxiter=None*, *M=None*, *callback=None*, *atol=None*)

Use BIConjugate Gradient STABILized iteration to solve $Ax = b$.

Parameters

- A** [{sparse matrix, dense matrix, LinearOperator}] The real or complex N-by-N matrix of the linear system. Alternatively, A can be a linear operator which can produce Ax using, e.g., `scipy.sparse.linalg.LinearOperator`.
- b** [{array, matrix}] Right hand side of the linear system. Has shape (N,) or (N,1).

Returns

- x** [{array, matrix}] The converged solution.
- info** [integer]

Provides convergence information:

0 : successful exit >0 : convergence to tolerance not achieved, number of iterations <0 : illegal input or breakdown

Other Parameters

- x0** [{array, matrix}] Starting guess for the solution.
- tol, atol** [float, optional] Tolerances for convergence, $\text{norm}(\text{residual}) \leq \max(\text{tol} \cdot \text{norm}(b), \text{atol})$. The default for *atol* is 'legacy', which emulates a different legacy behavior.

Warning: The default value for *atol* will be changed in a future release. For future compatibility, specify *atol* explicitly.

- maxiter** [integer] Maximum number of iterations. Iteration will stop after *maxiter* steps even if the specified tolerance has not been achieved.
- M** [{sparse matrix, dense matrix, LinearOperator}] Preconditioner for A. The preconditioner should approximate the inverse of A. Effective preconditioning dramatically improves the rate of convergence, which implies that fewer iterations are needed to reach a given error tolerance.
- callback** [function] User-supplied function to call after each iteration. It is called as `callback(xk)`, where *xk* is the current solution vector.

scipy.sparse.linalg.cg

`scipy.sparse.linalg.cg`(*A*, *b*, *x0=None*, *tol=1e-05*, *maxiter=None*, *M=None*, *callback=None*,
atol=None)

Use Conjugate Gradient iteration to solve $Ax = b$.

Parameters

- A** [{sparse matrix, dense matrix, LinearOperator}] The real or complex N-by-N matrix of the linear system. A must represent a hermitian, positive definite matrix. Alternatively, A can be a linear operator which can produce Ax using, e.g., `scipy.sparse.linalg.LinearOperator`.
- b** [{array, matrix}] Right hand side of the linear system. Has shape (N,) or (N,1).

Returns

- x** [{array, matrix}] The converged solution.
- info** [integer]

Provides convergence information:

0 : successful exit >0 : convergence to tolerance not achieved, number of iterations <0 : illegal input or breakdown

Other Parameters

- x0** [{array, matrix}] Starting guess for the solution.
- tol, atol** [float, optional] Tolerances for convergence, $\text{norm}(\text{residual}) \leq \max(\text{tol} * \text{norm}(b), \text{atol})$. The default for *atol* is 'legacy', which emulates a different legacy behavior.

Warning: The default value for *atol* will be changed in a future release. For future compatibility, specify *atol* explicitly.

- maxiter** [integer] Maximum number of iterations. Iteration will stop after *maxiter* steps even if the specified tolerance has not been achieved.
- M** [{sparse matrix, dense matrix, LinearOperator}] Preconditioner for A. The preconditioner should approximate the inverse of A. Effective preconditioning dramatically improves the rate of convergence, which implies that fewer iterations are needed to reach a given error tolerance.
- callback** [function] User-supplied function to call after each iteration. It is called as `callback(xk)`, where *xk* is the current solution vector.

scipy.sparse.linalg.cgs

`scipy.sparse.linalg.cgs`(*A*, *b*, *x0=None*, *tol=1e-05*, *maxiter=None*, *M=None*, *callback=None*,
atol=None)

Use Conjugate Gradient Squared iteration to solve $Ax = b$.

Parameters

- A** [{sparse matrix, dense matrix, LinearOperator}] The real-valued N-by-N matrix of the linear system. Alternatively, A can be a linear operator which can produce Ax using, e.g., `scipy.sparse.linalg.LinearOperator`.
- b** [{array, matrix}] Right hand side of the linear system. Has shape (N,) or (N,1).

Returns

- x** [{array, matrix}] The converged solution.
- info** [integer]

Provides convergence information:

0 : successful exit >0 : convergence to tolerance not achieved, number of iterations <0 : illegal input or breakdown

Other Parameters

x0 [[array, matrix]] Starting guess for the solution.
tol, atol [float, optional] Tolerances for convergence, `norm(residual) <= max(tol*norm(b), atol)`. The default for `atol` is 'legacy', which emulates a different legacy behavior.

Warning: The default value for `atol` will be changed in a future release. For future compatibility, specify `atol` explicitly.

maxiter [integer] Maximum number of iterations. Iteration will stop after `maxiter` steps even if the specified tolerance has not been achieved.
M [{sparse matrix, dense matrix, LinearOperator}] Preconditioner for A. The preconditioner should approximate the inverse of A. Effective preconditioning dramatically improves the rate of convergence, which implies that fewer iterations are needed to reach a given error tolerance.
callback [function] User-supplied function to call after each iteration. It is called as `callback(xk)`, where `xk` is the current solution vector.

scipy.sparse.linalg.gmres

`scipy.sparse.linalg.gmres(A, b, x0=None, tol=1e-05, restart=None, maxiter=None, M=None, callback=None, restrt=None, atol=None, callback_type=None)`

Use Generalized Minimal RESidual iteration to solve $Ax = b$.

Parameters

A [{sparse matrix, dense matrix, LinearOperator}] The real or complex N-by-N matrix of the linear system. Alternatively, A can be a linear operator which can produce Ax using, e.g., `scipy.sparse.linalg.LinearOperator`.
b [[array, matrix]] Right hand side of the linear system. Has shape (N,) or (N,1).

Returns

x [[array, matrix]] The converged solution.
info [int]

Provides convergence information:

- 0 : successful exit
- >0 : convergence to tolerance not achieved, number of iterations
- <0 : illegal input or breakdown

Other Parameters

x0 [{array, matrix}] Starting guess for the solution (a vector of zeros by default).
tol, atol [float, optional] Tolerances for convergence, `norm(residual) <= max(tol*norm(b), atol)`. The default for `atol` is 'legacy', which emulates a different legacy behavior.

Warning: The default value for `atol` will be changed in a future release. For future compatibility, specify `atol` explicitly.

- restart** [int, optional] Number of iterations between restarts. Larger values increase iteration cost, but may be necessary for convergence. Default is 20.
- maxiter** [int, optional] Maximum number of iterations (restart cycles). Iteration will stop after max-iter steps even if the specified tolerance has not been achieved.
- M** [{sparse matrix, dense matrix, LinearOperator}] Inverse of the preconditioner of A. M should approximate the inverse of A and be easy to solve for (see Notes). Effective preconditioning dramatically improves the rate of convergence, which implies that fewer iterations are needed to reach a given error tolerance. By default, no preconditioner is used.
- callback** [function] User-supplied function to call after each iteration. It is called as `callback(args)`, where `args` are selected by `callback_type`.
- callback_type** [{'x', 'pr_norm', 'legacy'}, optional]
Callback function argument requested:
- `x`: current iterate (ndarray), called on every restart
 - `pr_norm`: relative (preconditioned) residual norm (float), called on every inner iteration
 - `legacy` (default): same as `pr_norm`, but also changes the meaning of 'maxiter' to count inner iterations instead of restart cycles.
- restrt** [int, optional] DEPRECATED - use `restart` instead.

See also:

[LinearOperator](#)

Notes

A preconditioner, P , is chosen such that P is close to A but easy to solve for. The preconditioner parameter required by this routine is $M = P^{-1}$. The inverse should preferably not be calculated explicitly. Rather, use the following template to produce M :

```
# Construct a linear operator that computes  $P^{-1} * x$ .
import scipy.sparse.linalg as spla
M_x = lambda x: spla.spsolve(P, x)
M = spla.LinearOperator((n, n), M_x)
```

Examples

```
>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import gmres
>>> A = csc_matrix([[3, 2, 0], [1, -1, 0], [0, 5, 1]], dtype=float)
>>> b = np.array([2, 4, -1], dtype=float)
>>> x, exitCode = gmres(A, b)
>>> print(exitCode)           # 0 indicates successful convergence
0
>>> np.allclose(A.dot(x), b)
True
```

scipy.sparse.linalg.lgmres

```
scipy.sparse.linalg.lgmres(A, b, x0=None, tol=1e-05, maxiter=1000, M=None, callback=None,
                           inner_m=30, outer_k=3, outer_v=None, store_outer_Av=True,
                           prepend_outer_v=False, atol=None)
```

Solve a matrix equation using the LGMRES algorithm.

The LGMRES algorithm [1] [2] is designed to avoid some problems in the convergence in restarted GMRES, and often converges in fewer iterations.

Parameters

- A** [{sparse matrix, dense matrix, LinearOperator}] The real or complex N-by-N matrix of the linear system. Alternatively, A can be a linear operator which can produce Ax using, e.g., `scipy.sparse.linalg.LinearOperator`.
- b** [{array, matrix}] Right hand side of the linear system. Has shape (N,) or (N,1).
- x0** [{array, matrix}] Starting guess for the solution.
- tol, atol** [float, optional] Tolerances for convergence, `norm(residual) <= max(tol*norm(b), atol)`. The default for `atol` is `tol`.

Warning: The default value for `atol` will be changed in a future release. For future compatibility, specify `atol` explicitly.

- maxiter** [int, optional] Maximum number of iterations. Iteration will stop after `maxiter` steps even if the specified tolerance has not been achieved.
- M** [{sparse matrix, dense matrix, LinearOperator}, optional] Preconditioner for A. The preconditioner should approximate the inverse of A. Effective preconditioning dramatically improves the rate of convergence, which implies that fewer iterations are needed to reach a given error tolerance.
- callback** [function, optional] User-supplied function to call after each iteration. It is called as `callback(xk)`, where `xk` is the current solution vector.
- inner_m** [int, optional] Number of inner GMRES iterations per each outer iteration.
- outer_k** [int, optional] Number of vectors to carry between inner GMRES iterations. According to [1], good values are in the range of 1...3. However, note that if you want to use the additional vectors to accelerate solving multiple similar problems, larger values may be beneficial.
- outer_v** [list of tuples, optional] List containing tuples (v, Av) of vectors and corresponding matrix-vector products, used to augment the Krylov subspace, and carried between inner GMRES iterations. The element `Av` can be `None` if the matrix-vector product should be re-evaluated. This parameter is modified in-place by `lgmres`, and can be used to pass “guess” vectors in and out of the algorithm when solving similar problems.
- store_outer_Av** [bool, optional] Whether LGMRES should store also $A*v$ in addition to vectors v in the `outer_v` list. Default is `True`.
- prepend_outer_v** [bool, optional] Whether to put `outer_v` augmentation vectors before Krylov iterates. In standard LGMRES, `prepend_outer_v=False`.

Returns

- x** [array or matrix] The converged solution.
- info** [int] Provides convergence information:
- 0 : successful exit
 - >0 : convergence to tolerance not achieved, number of iterations
 - <0 : illegal input or breakdown

Notes

The LGMRES algorithm [1] [2] is designed to avoid the slowing of convergence in restarted GMRES, due to alternating residual vectors. Typically, it often outperforms GMRES(m) of comparable memory requirements by some measure, or at least is not much worse.

Another advantage in this algorithm is that you can supply it with ‘guess’ vectors in the *outer_v* argument that augment the Krylov subspace. If the solution lies close to the span of these vectors, the algorithm converges faster. This can be useful if several very similar matrices need to be inverted one after another, such as in Newton-Krylov iteration where the Jacobian matrix often changes little in the nonlinear steps.

References

[1], [2]

Examples

```
>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import lgmres
>>> A = csc_matrix([[3, 2, 0], [1, -1, 0], [0, 5, 1]], dtype=float)
>>> b = np.array([2, 4, -1], dtype=float)
>>> x, exitCode = lgmres(A, b)
>>> print(exitCode)           # 0 indicates successful convergence
0
>>> np.allclose(A.dot(x), b)
True
```

scipy.sparse.linalg.minres

`scipy.sparse.linalg.minres` (*A*, *b*, *x0=None*, *shift=0.0*, *tol=1e-05*, *maxiter=None*, *M=None*, *callback=None*, *show=False*, *check=False*)

Use MINimum RESidual iteration to solve $Ax=b$

MINRES minimizes $\text{norm}(A*x - b)$ for a real symmetric matrix *A*. Unlike the Conjugate Gradient method, *A* can be indefinite or singular.

If *shift* $\neq 0$ then the method solves $(A - \text{shift}*I)x = b$

Parameters

- A** [{sparse matrix, dense matrix, LinearOperator}] The real symmetric N-by-N matrix of the linear system Alternatively, *A* can be a linear operator which can produce Ax using, e.g., `scipy.sparse.linalg.LinearOperator`.
- b** [{array, matrix}] Right hand side of the linear system. Has shape (N,) or (N,1).

Returns

- x** [{array, matrix}] The converged solution.
- info** [integer]

Provides convergence information:

0 : successful exit >0 : convergence to tolerance not achieved, number of iterations <0 : illegal input or breakdown

Other Parameters

x0	[{array, matrix}] Starting guess for the solution.
tol	[float] Tolerance to achieve. The algorithm terminates when the relative residual is below <i>tol</i> .
maxiter	[integer] Maximum number of iterations. Iteration will stop after maxiter steps even if the specified tolerance has not been achieved.
M	[{sparse matrix, dense matrix, LinearOperator}] Preconditioner for A. The preconditioner should approximate the inverse of A. Effective preconditioning dramatically improves the rate of convergence, which implies that fewer iterations are needed to reach a given error tolerance.
callback	[function] User-supplied function to call after each iteration. It is called as callback(xk), where xk is the current solution vector.

References

Solution of sparse indefinite systems of linear equations,

C. C. Paige and M. A. Saunders (1975), SIAM J. Numer. Anal. 12(4), pp. 617-629. <https://web.stanford.edu/group/SOL/software/minres/>

This file is a translation of the following MATLAB implementation:

<https://web.stanford.edu/group/SOL/software/minres/minres-matlab.zip>

Examples

```
>>> import numpy as np
>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import minres
>>> A = csc_matrix([[3, 2, 0], [1, -1, 0], [0, 5, 1]], dtype=float)
>>> A = A + A.T
>>> b = np.array([2, 4, -1], dtype=float)
>>> x, exitCode = minres(A, b)
>>> print(exitCode)           # 0 indicates successful convergence
0
>>> np.allclose(A.dot(x), b)
True
```

scipy.sparse.linalg.qmr

scipy.sparse.linalg.**qmr**(A, b, x0=None, tol=1e-05, maxiter=None, M1=None, M2=None, callback=None, atol=None)

Use Quasi-Minimal Residual iteration to solve $Ax = b$.

Parameters

A	[{sparse matrix, dense matrix, LinearOperator}] The real-valued N-by-N matrix of the linear system. Alternatively, A can be a linear operator which can produce Ax and $A^T x$ using, e.g., <code>scipy.sparse.linalg.LinearOperator</code> .
b	[{array, matrix}] Right hand side of the linear system. Has shape (N,) or (N,1).

Returns

x	[{array, matrix}] The converged solution.
info	[integer]

Provides convergence information:

0 : successful exit >0 : convergence to tolerance not achieved, number of iterations <0 : illegal input or breakdown

Other Parameters

x0 [[array, matrix]] Starting guess for the solution.
tol, atol [float, optional] Tolerances for convergence, $\text{norm}(\text{residual}) \leq \max(\text{tol} \cdot \text{norm}(b), \text{atol})$. The default for `atol` is 'legacy', which emulates a different legacy behavior.

Warning: The default value for `atol` will be changed in a future release. For future compatibility, specify `atol` explicitly.

maxiter [integer] Maximum number of iterations. Iteration will stop after `maxiter` steps even if the specified tolerance has not been achieved.
M1 [{sparse matrix, dense matrix, LinearOperator}] Left preconditioner for A.
M2 [{sparse matrix, dense matrix, LinearOperator}] Right preconditioner for A. Used together with the left preconditioner M1. The matrix $M1 * A * M2$ should have better conditioned than A alone.
callback [function] User-supplied function to call after each iteration. It is called as `callback(xk)`, where `xk` is the current solution vector.

See also:

[*LinearOperator*](#)

Examples

```
>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import qmr
>>> A = csc_matrix([[3, 2, 0], [1, -1, 0], [0, 5, 1]], dtype=float)
>>> b = np.array([2, 4, -1], dtype=float)
>>> x, exitCode = qmr(A, b)
>>> print(exitCode)           # 0 indicates successful convergence
0
>>> np.allclose(A.dot(x), b)
True
```

scipy.sparse.linalg.gcrotmk

`scipy.sparse.linalg.gcrotmk`(*A, b, x0=None, tol=1e-05, maxiter=1000, M=None, callback=None, m=20, k=None, CU=None, discard_C=False, truncate='oldest', atol=None*)

Solve a matrix equation using flexible GCROT(m,k) algorithm.

Parameters

A [{sparse matrix, dense matrix, LinearOperator}] The real or complex N-by-N matrix of the linear system. Alternatively, A can be a linear operator which can produce Ax using, e.g., `scipy.sparse.linalg.LinearOperator`.
b [[array, matrix]] Right hand side of the linear system. Has shape (N,) or (N,1).
x0 [[array, matrix]] Starting guess for the solution.

tol, atol [float, optional] Tolerances for convergence, $\text{norm}(\text{residual}) \leq \max(\text{tol} * \text{norm}(b), \text{atol})$. The default for `atol` is `tol`.

Warning: The default value for `atol` will be changed in a future release. For future compatibility, specify `atol` explicitly.

maxiter [int, optional] Maximum number of iterations. Iteration will stop after `maxiter` steps even if the specified tolerance has not been achieved.

M [{sparse matrix, dense matrix, LinearOperator}, optional] Preconditioner for A. The preconditioner should approximate the inverse of A. `gcrotmk` is a ‘flexible’ algorithm and the preconditioner can vary from iteration to iteration. Effective preconditioning dramatically improves the rate of convergence, which implies that fewer iterations are needed to reach a given error tolerance.

callback [function, optional] User-supplied function to call after each iteration. It is called as `callback(xk)`, where `xk` is the current solution vector.

m [int, optional] Number of inner FGMRES iterations per each outer iteration. Default: 20

k [int, optional] Number of vectors to carry between inner FGMRES iterations. According to [2], good values are around `m`.

CU [list of tuples, optional] List of tuples (c, u) which contain the columns of the matrices C and U in the GCROT(m,k) algorithm. For details, see [2]. The list given and vectors contained in it are modified in-place. If not given, start from empty matrices. The `c` elements in the tuples can be `None`, in which case the vectors are recomputed via $c = A u$ on start and orthogonalized as described in [3].

discard_C [bool, optional] Discard the C-vectors at the end. Useful if recycling Krylov subspaces for different linear systems.

truncate [{‘oldest’, ‘smallest’}, optional] Truncation scheme to use. Drop: oldest vectors, or vectors with smallest singular values using the scheme discussed in [1,2]. See [2] for detailed comparison. Default: ‘oldest’

Returns

x [array or matrix] The solution found.

info [int] Provides convergence information:

- 0 : successful exit
- >0 : convergence to tolerance not achieved, number of iterations

References

[1], [2], [3]

Iterative methods for least-squares problems:

<code>lsqr(A, b[, damp, atol, btol, conlim, ...])</code>	Find the least-squares solution to a large, sparse, linear system of equations.
<code>lsmr(A, b[, damp, atol, btol, conlim, ...])</code>	Iterative solver for least-squares problems.

scipy.sparse.linalg.lsqr

```
scipy.sparse.linalg.lsqr(A, b, damp=0.0, atol=1e-08, btol=1e-08, conlim=100000000.0,
                          iter_lim=None, show=False, calc_var=False, x0=None)
```

Find the least-squares solution to a large, sparse, linear system of equations.

The function solves $Ax = b$ or $\min \|Ax - b\|^2$ or $\min \|Ax - b\|^2 + d^2 \|x\|^2$.

The matrix A may be square or rectangular (over-determined or under-determined), and may have any rank.

1. Unsymmetric equations	--	solve	$Ax = b$
2. Linear least squares	--	solve	$Ax = b$ in the least-squares sense
3. Damped least squares	--	solve	$\begin{pmatrix} A \\ \text{damp} \cdot I \end{pmatrix} x = \begin{pmatrix} b \\ 0 \end{pmatrix}$ in the least-squares sense

Parameters

A	[[sparse matrix, ndarray, LinearOperator]] Representation of an m-by-n matrix. Alternatively, A can be a linear operator which can produce Ax and $A^T x$ using, e.g., <code>scipy.sparse.linalg.LinearOperator</code> .
b	[array_like, shape (m,)] Right-hand side vector b.
damp	[float] Damping coefficient.
atol, btol	[float, optional] Stopping tolerances. If both are $1.0e-9$ (say), the final residual norm should be accurate to about 9 digits. (The final x will usually have fewer correct digits, depending on $\text{cond}(A)$ and the size of damp .)
conlim	[float, optional] Another stopping tolerance. <code>lsqr</code> terminates if an estimate of $\text{cond}(A)$ exceeds <i>conlim</i> . For compatible systems $Ax = b$, <i>conlim</i> could be as large as $1.0e+12$ (say). For least-squares problems, <i>conlim</i> should be less than $1.0e+8$. Maximum precision can be obtained by setting $\text{atol} = \text{btol} = \text{conlim} = \text{zero}$, but the number of iterations may then be excessive.
iter_lim	[int, optional] Explicit limitation on number of iterations (for safety).
show	[bool, optional] Display an iteration log.
calc_var	[bool, optional] Whether to estimate diagonals of $(A^T A + \text{damp}^2 I)^{-1}$.
x0	[array_like, shape (n), optional] Initial guess of x , if None zeros are used. New in version 1.0.0.

Returns

x	[ndarray of float] The final solution.
istop	[int] Gives the reason for termination. 1 means x is an approximate solution to $Ax = b$. 2 means x approximately solves the least-squares problem.
itn	[int] Iteration number upon termination.
r1norm	[float] $\text{norm}(r)$, where $r = b - Ax$.
r2norm	[float] $\sqrt{\text{norm}(r)^2 + \text{damp}^2 * \text{norm}(x)^2}$. Equal to <i>r1norm</i> if $\text{damp} == 0$.
anorm	[float] Estimate of Frobenius norm of $A_{\text{bar}} = \begin{bmatrix} A \\ \text{damp} \cdot I \end{bmatrix}$.
acond	[float] Estimate of $\text{cond}(A_{\text{bar}})$.
arnorm	[float] Estimate of $\text{norm}(A^T r - \text{damp}^2 x)$.
xnorm	[float] $\text{norm}(x)$
var	[ndarray of float] If <i>calc_var</i> is True, estimates all diagonals of $(A^T A)^{-1}$ (if $\text{damp} == 0$) or more generally $(A^T A + \text{damp}^2 I)^{-1}$. This is well defined if A has full

column rank or $\text{damp} > 0$. (Not sure what var means if $\text{rank}(A) < n$ and $\text{damp} = 0$.)

Notes

LSQR uses an iterative method to approximate the solution. The number of iterations required to reach a certain accuracy depends strongly on the scaling of the problem. Poor scaling of the rows or columns of A should therefore be avoided where possible.

For example, in problem 1 the solution is unaltered by row-scaling. If a row of A is very small or large compared to the other rows of A , the corresponding row of $(A \ b)$ should be scaled up or down.

In problems 1 and 2, the solution x is easily recovered following column-scaling. Unless better information is known, the nonzero columns of A should be scaled so that they all have the same Euclidean norm (e.g., 1.0).

In problem 3, there is no freedom to re-scale if damp is nonzero. However, the value of damp should be assigned only after attention has been paid to the scaling of A .

The parameter damp is intended to help regularize ill-conditioned systems, by preventing the true solution from being very large. Another aid to regularization is provided by the parameter acon , which may be used to terminate iterations before the computed solution becomes very large.

If some initial estimate x_0 is known and if $\text{damp} == 0$, one could proceed as follows:

1. Compute a residual vector $r_0 = b - A*x_0$.
2. Use LSQR to solve the system $A*dx = r_0$.
3. Add the correction dx to obtain a final solution $x = x_0 + dx$.

This requires that x_0 be available before and after the call to LSQR. To judge the benefits, suppose LSQR takes k_1 iterations to solve $A*x = b$ and k_2 iterations to solve $A*dx = r_0$. If x_0 is “good”, $\text{norm}(r_0)$ will be smaller than $\text{norm}(b)$. If the same stopping tolerances atol and btol are used for each system, k_1 and k_2 will be similar, but the final solution $x_0 + dx$ should be more accurate. The only way to reduce the total work is to use a larger stopping tolerance for the second system. If some value btol is suitable for $A*x = b$, the larger value $\text{btol}*\text{norm}(b)/\text{norm}(r_0)$ should be suitable for $A*dx = r_0$.

Preconditioning is another way to reduce the number of iterations. If it is possible to solve a related system $M*x = b$ efficiently, where M approximates A in some helpful way (e.g. $M - A$ has low rank or its elements are small relative to those of A), LSQR may converge more rapidly on the system $A*M(\text{inverse})*z = b$, after which x can be recovered by solving $M*x = z$.

If A is symmetric, LSQR should not be used!

Alternatives are the symmetric conjugate-gradient method (`cg`) and/or `SYMMLQ`. `SYMMLQ` is an implementation of symmetric `cg` that applies to any symmetric A and will converge more rapidly than LSQR. If A is positive definite, there are other implementations of symmetric `cg` that require slightly less work per iteration than `SYMMLQ` (but will take the same number of iterations).

References

[1], [2], [3]

Examples

```
>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import lsqr
>>> A = csc_matrix([[1., 0.], [1., 1.], [0., 1.]], dtype=float)
```

The first example has the trivial solution $[0, 0]$

```
>>> b = np.array([0., 0., 0.], dtype=float)
>>> x, istop, itn, normr = lsqr(A, b)[:4]
The exact solution is x = 0
>>> istop
0
>>> x
array([ 0.,  0.]
```

The stopping code `istop=0` returned indicates that a vector of zeros was found as a solution. The returned solution `x` indeed contains $[0, 0]$. The next example has a non-trivial solution:

```
>>> b = np.array([1., 0., -1.], dtype=float)
>>> x, istop, itn, r1norm = lsqr(A, b)[:4]
>>> istop
1
>>> x
array([ 1., -1.])
>>> itn
1
>>> r1norm
4.440892098500627e-16
```

As indicated by `istop=1`, `lsqr` found a solution obeying the tolerance limits. The given solution $[1, -1]$ obviously solves the equation. The remaining return values include information about the number of iterations (`itn=1`) and the remaining difference of left and right side of the solved equation. The final example demonstrates the behavior in the case where there is no solution for the equation:

```
>>> b = np.array([1., 0.01, -1.], dtype=float)
>>> x, istop, itn, r1norm = lsqr(A, b)[:4]
>>> istop
2
>>> x
array([ 1.00333333, -0.99666667])
>>> A.dot(x)-b
array([ 0.00333333, -0.00333333,  0.00333333])
>>> r1norm
0.005773502691896255
```

`istop` indicates that the system is inconsistent and thus `x` is rather an approximate solution to the corresponding least-squares problem. `r1norm` contains the norm of the minimal residual that was found.

scipy.sparse.linalg.lsmr

`scipy.sparse.linalg.lsmr(A, b, damp=0.0, atol=1e-06, btol=1e-06, conlim=100000000.0, maxiter=None, show=False, x0=None)`

Iterative solver for least-squares problems.

`lsmr` solves the system of linear equations $Ax = b$. If the system is inconsistent, it solves the least-squares problem $\min ||b - Ax||_2$. A is a rectangular matrix of dimension m -by- n , where all cases are allowed: $m = n$, $m > n$, or $m < n$. b is a vector of length m . The matrix A may be dense or sparse (usually sparse).

Parameters

- A** `[{matrix, sparse matrix, ndarray, LinearOperator}]` Matrix A in the linear system. Alternatively, A can be a linear operator which can produce Ax and $A^H x$ using, e.g., `scipy.sparse.linalg.LinearOperator`.
- b** `[array_like, shape (m,)]` Vector b in the linear system.
- damp** `[float]` Damping factor for regularized least-squares. `lsmr` solves the regularized least-squares problem:

$$\min \begin{pmatrix} ||(b - (A) x)|| \\ ||(0) (damp*I) ||_2 \end{pmatrix}$$

- where `damp` is a scalar. If `damp` is `None` or `0`, the system is solved without regularization.
- atol, btol** `[float, optional]` Stopping tolerances. `lsmr` continues iterations until a certain backward error estimate is smaller than some quantity depending on `atol` and `btol`. Let $r = b - Ax$ be the residual vector for the current approximate solution x . If $Ax = b$ seems to be consistent, `lsmr` terminates when $\text{norm}(r) \leq \text{atol} * \text{norm}(A) * \text{norm}(x) + \text{btol} * \text{norm}(b)$. Otherwise, `lsmr` terminates when $\text{norm}(A^H r) \leq \text{atol} * \text{norm}(A) * \text{norm}(r)$. If both tolerances are $1.0e-6$ (say), the final $\text{norm}(r)$ should be accurate to about 6 digits. (The final x will usually have fewer correct digits, depending on $\text{cond}(A)$ and the size of LAMBDA .) If `atol` or `btol` is `None`, a default value of $1.0e-6$ will be used. Ideally, they should be estimates of the relative error in the entries of A and b respectively. For example, if the entries of A have 7 correct digits, set `atol = 1e-7`. This prevents the algorithm from doing unnecessary work beyond the uncertainty of the input data.
- conlim** `[float, optional]` `lsmr` terminates if an estimate of $\text{cond}(A)$ exceeds `conlim`. For compatible systems $Ax = b$, `conlim` could be as large as $1.0e+12$ (say). For least-squares problems, `conlim` should be less than $1.0e+8$. If `conlim` is `None`, the default value is $1e+8$. Maximum precision can be obtained by setting `atol = btol = conlim = 0`, but the number of iterations may then be excessive.
- maxiter** `[int, optional]` `lsmr` terminates if the number of iterations reaches `maxiter`. The default is `maxiter = min(m, n)`. For ill-conditioned systems, a larger value of `maxiter` may be needed.
- show** `[bool, optional]` Print iterations logs if `show=True`.
- x0** `[array_like, shape (n,), optional]` Initial guess of x , if `None` zeros are used. New in version 1.0.0.

Returns

- x** `[ndarray of float]` Least-square solution returned.
- istop** `[int]` `istop` gives the reason for stopping:

```
istop = 0 means x=0 is a solution. If x0 was given,
↪ then x=x0 is a
    solution.
    = 1 means x is an approximate solution to A*x = B,
    according to atol and btol.
```

(continues on next page)

(continued from previous page)

```

    = 2 means x approximately solves the least-squares_
↪problem
    according to atol.
    = 3 means COND(A) seems to be greater than CONLIM.
    = 4 is the same as 1 with atol = btol = eps_
↪(machine
    precision)
    = 5 is the same as 2 with atol = eps.
    = 6 is the same as 3 with CONLIM = 1/eps.
    = 7 means ITN reached maxiter before the other_
↪stopping
    conditions were satisfied.

```

itn [int] Number of iterations used.
normr [float] norm($b - Ax$)
normar [float] norm($A^H (b - Ax)$)
norma [float] norm(A)
conda [float] Condition number of A .
normx [float] norm(x)

Notes

New in version 0.11.0.

References

[1], [2]

Examples

```

>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import lsqr
>>> A = csc_matrix([[1., 0.], [1., 1.], [0., 1.]], dtype=float)

```

The first example has the trivial solution $[0, 0]$

```

>>> b = np.array([0., 0., 0.], dtype=float)
>>> x, istop, itn, normr = lsqr(A, b)[:4]
>>> istop
0
>>> x
array([ 0.,  0.])

```

The stopping code `istop=0` returned indicates that a vector of zeros was found as a solution. The returned solution x indeed contains $[0, 0]$. The next example has a non-trivial solution:

```

>>> b = np.array([1., 0., -1.], dtype=float)
>>> x, istop, itn, normr = lsqr(A, b)[:4]
>>> istop
1

```

(continues on next page)

(continued from previous page)

```
>>> x
array([ 1., -1.])
>>> itn
1
>>> normr
4.440892098500627e-16
```

As indicated by *istop=1*, *lsmr* found a solution obeying the tolerance limits. The given solution $[1., -1.]$ obviously solves the equation. The remaining return values include information about the number of iterations (*itm=1*) and the remaining difference of left and right side of the solved equation. The final example demonstrates the behavior in the case where there is no solution for the equation:

```
>>> b = np.array([1., 0.01, -1.], dtype=float)
>>> x, istop, itn, normr = lsqr(A, b)[:4]
>>> istop
2
>>> x
array([ 1.00333333, -0.99666667])
>>> A.dot(x)-b
array([ 0.00333333, -0.00333333,  0.00333333])
>>> normr
0.005773502691896255
```

istop indicates that the system is inconsistent and thus x is rather an approximate solution to the corresponding least-squares problem. *normr* contains the minimal distance that was found.

6.24.5 Matrix factorizations

Eigenvalue problems:

<code>eigs(A[, k, M, sigma, which, v0, ncv, ...])</code>	Find k eigenvalues and eigenvectors of the square matrix A .
<code>eigsh(A[, k, M, sigma, which, v0, ncv, ...])</code>	Find k eigenvalues and eigenvectors of the real symmetric square matrix or complex Hermitian matrix A .
<code>lobpcg(A, X[, B, M, Y, tol, maxiter, ...])</code>	Locally Optimal Block Preconditioned Conjugate Gradient Method (LOBPCG)

scipy.sparse.linalg.eigs

`scipy.sparse.linalg.eigs(A, k=6, M=None, sigma=None, which='LM', v0=None, ncv=None, maxiter=None, tol=0, return_eigenvectors=True, Minv=None, OPinv=None, OPpart=None)`

Find k eigenvalues and eigenvectors of the square matrix A .

Solves $A * x[i] = w[i] * x[i]$, the standard eigenvalue problem for $w[i]$ eigenvalues with corresponding eigenvectors $x[i]$.

If M is specified, solves $A * x[i] = w[i] * M * x[i]$, the generalized eigenvalue problem for $w[i]$ eigenvalues with corresponding eigenvectors $x[i]$

Parameters

A	[ndarray, sparse matrix or LinearOperator] An array, sparse matrix, or LinearOperator representing the operation $A * x$, where A is a real or complex square matrix.
k	[int, optional] The number of eigenvalues and eigenvectors desired. k must be smaller than $N-1$. It is not possible to compute all eigenvectors of a matrix.
M	[ndarray, sparse matrix or LinearOperator, optional] An array, sparse matrix, or LinearOperator representing the operation $M*x$ for the generalized eigenvalue problem $A * x = w * M * x.$ <p>M must represent a real symmetric matrix if A is real, and must represent a complex Hermitian matrix if A is complex. For best results, the data type of M should be the same as that of A. Additionally:</p> <ul style="list-style-type: none"> If σ is None, M is positive definite If σ is specified, M is positive semi-definite <p>If σ is None, <code>eigs</code> requires an operator to compute the solution of the linear equation $M * x = b$. This is done internally via a (sparse) LU decomposition for an explicit matrix M, or via an iterative solver for a general linear operator. Alternatively, the user can supply the matrix or operator <code>Minv</code>, which gives $x = Minv * b = M^{-1} * b$.</p>
sigma	[real or complex, optional] Find eigenvalues near σ using shift-invert mode. This requires an operator to compute the solution of the linear system $[A - \sigma * M] * x = b$, where M is the identity matrix if unspecified. This is computed internally via a (sparse) LU decomposition for explicit matrices A & M , or via an iterative solver if either A or M is a general linear operator. Alternatively, the user can supply the matrix or operator <code>OPinv</code> , which gives $x = OPinv * b = [A - \sigma * M]^{-1} * b$. For a real matrix A , shift-invert can either be done in imaginary mode or real mode, specified by the parameter <code>OPpart</code> ('r' or 'i'). Note that when σ is specified, the keyword 'which' (below) refers to the shifted eigenvalues $w'[i]$ where: <ul style="list-style-type: none"> If A is real and <code>OPpart == 'r'</code> (default), $w'[i] = 1/2 * [1/(w[i]-\sigma) + 1/(w[i]-\text{conj}(\sigma))].$ If A is real and <code>OPpart == 'i'</code>, $w'[i] = 1/2i * [1/(w[i]-\sigma) - 1/(w[i]-\text{conj}(\sigma))].$ If A is complex, $w'[i] = 1/(w[i]-\sigma)$.
v0	[ndarray, optional] Starting vector for iteration. Default: random
ncv	[int, optional] The number of Lanczos vectors generated ncv must be greater than k ; it is recommended that $ncv > 2*k$. Default: $\min(n, \max(2*k + 1, 20))$
which	[str, ['LM' 'SM' 'LR' 'SR' 'LI' 'SI'], optional] Which k eigenvectors and eigenvalues to find: <ul style="list-style-type: none"> 'LM' : largest magnitude 'SM' : smallest magnitude 'LR' : largest real part 'SR' : smallest real part 'LI' : largest imaginary part 'SI' : smallest imaginary part <p>When $\sigma \neq \text{None}$, 'which' refers to the shifted eigenvalues $w'[i]$ (see discussion in 'sigma', above). ARPACK is generally better at finding large values than small values. If small eigenvalues are desired, consider using shift-invert mode for better performance.</p>
maxiter	[int, optional] Maximum number of Arnoldi update iterations allowed Default: $n*10$
tol	[float, optional] Relative accuracy for eigenvalues (stopping criterion) The default value of 0 implies machine precision.
return_eigenvectors	[bool, optional] Return eigenvectors (True) in addition to eigenvalues
Minv	[ndarray, sparse matrix or LinearOperator, optional] See notes in <code>M</code> , above.
OPinv	[ndarray, sparse matrix or LinearOperator, optional] See notes in <code>sigma</code> , above.
OPpart	[{'r' or 'i'}, optional] See notes in <code>sigma</code> , above

Returns

w [ndarray] Array of k eigenvalues.
v [ndarray] An array of k eigenvectors. $v[:, i]$ is the eigenvector corresponding to the eigenvalue $w[i]$.

Raises

ArpackNoConvergence

When the requested convergence is not obtained. The currently converged eigenvalues and eigenvectors can be found as `eigenvalues` and `eigenvectors` attributes of the exception object.

See also:

eigsh

eigenvalues and eigenvectors for symmetric matrix A

svds

singular value decomposition for a matrix A

Notes

This function is a wrapper to the ARPACK [1] SNEUPD, DNEUPD, CNEUPD, ZNEUPD, functions which use the Implicitly Restarted Arnoldi Method to find the eigenvalues and eigenvectors [2].

References

[1], [2]

Examples

Find 6 eigenvectors of the identity matrix:

```
>>> from scipy.sparse.linalg import eigs
>>> id = np.eye(13)
>>> vals, vecs = eigs(id, k=6)
>>> vals
array([ 1.+0.j,  1.+0.j,  1.+0.j,  1.+0.j,  1.+0.j,  1.+0.j])
>>> vecs.shape
(13, 6)
```

scipy.sparse.linalg.eigsh

`scipy.sparse.linalg.eigsh`(A , $k=6$, $M=None$, $sigma=None$, $which='LM'$, $v0=None$, $ncv=None$, $maxiter=None$, $tol=0$, $return_eigenvectors=True$, $Minv=None$, $OPinv=None$, $mode='normal'$)

Find k eigenvalues and eigenvectors of the real symmetric square matrix or complex Hermitian matrix A .

Solves $A * x[i] = w[i] * x[i]$, the standard eigenvalue problem for $w[i]$ eigenvalues with corresponding eigenvectors $x[i]$.

If M is specified, solves $A * x[i] = w[i] * M * x[i]$, the generalized eigenvalue problem for $w[i]$ eigenvalues with corresponding eigenvectors $x[i]$.

Note that there is no specialized routine for the case when A is a complex Hermitian matrix. In this case, `eigsh()` will call `eigs()` and return the real parts of the eigenvalues thus obtained.

Parameters

- A** [ndarray, sparse matrix or LinearOperator] A square operator representing the operation $A * x$, where A is real symmetric or complex Hermitian. For buckling mode (see below) A must additionally be positive-definite.
- k** [int, optional] The number of eigenvalues and eigenvectors desired. k must be smaller than N . It is not possible to compute all eigenvectors of a matrix.

Returns

- w** [array] Array of k eigenvalues.
- v** [array] An array representing the k eigenvectors. The column $v[:, i]$ is the eigenvector corresponding to the eigenvalue $w[i]$.

Other Parameters

- M** [An $N \times N$ matrix, array, sparse matrix, or linear operator representing] the operation $M @ x$ for the generalized eigenvalue problem
 $A @ x = w * M @ x$.
 M must represent a real symmetric matrix if A is real, and must represent a complex Hermitian matrix if A is complex. For best results, the data type of M should be the same as that of A . Additionally:
 If σ is None, M is symmetric positive definite.
 If σ is specified, M is symmetric positive semi-definite.
 In buckling mode, M is symmetric indefinite.
- If σ is None, `eigsh` requires an operator to compute the solution of the linear equation $M @ x = b$. This is done internally via a (sparse) LU decomposition for an explicit matrix M , or via an iterative solver for a general linear operator. Alternatively, the user can supply the matrix or operator `Minv`, which gives $x = Minv @ b = M^{-1} @ b$.
- sigma** [real] Find eigenvalues near σ using shift-invert mode. This requires an operator to compute the solution of the linear system $[A - \sigma * M] x = b$, where M is the identity matrix if unspecified. This is computed internally via a (sparse) LU decomposition for explicit matrices A & M , or via an iterative solver if either A or M is a general linear operator. Alternatively, the user can supply the matrix or operator `OPinv`, which gives $x = OPinv @ b = [A - \sigma * M]^{-1} @ b$. Note that when σ is specified, the keyword 'which' refers to the shifted eigenvalues $w'[i]$ where:
 if `mode == 'normal'`, $w'[i] = 1 / (w[i] - \sigma)$.
 if `mode == 'cayley'`, $w'[i] = (w[i] + \sigma) / (w[i] - \sigma)$.
 if `mode == 'buckling'`, $w'[i] = w[i] / (w[i] - \sigma)$.
 (see further discussion in 'mode' below)
- v0** [ndarray, optional] Starting vector for iteration. Default: random
- ncv** [int, optional] The number of Lanczos vectors generated `ncv` must be greater than k and smaller than n ; it is recommended that `ncv > 2*k`. Default: $\min(n, \max(2*k + 1, 20))$
- which** [str ['LM' | 'SM' | 'LA' | 'SA' | 'BE']] If A is a complex Hermitian matrix, 'BE' is invalid. Which k eigenvectors and eigenvalues to find:
 'LM': Largest (in magnitude) eigenvalues.
 'SM': Smallest (in magnitude) eigenvalues.
 'LA': Largest (algebraic) eigenvalues.
 'SA': Smallest (algebraic) eigenvalues.
 'BE': Half ($k/2$) from each end of the spectrum.

When k is odd, return one more ($k/2+1$) from the high end. When $\sigma \neq \text{None}$, ‘which’ refers to the shifted eigenvalues $w'[i]$ (see discussion in ‘sigma’, above). ARPACK is generally better at finding large values than small values. If small eigenvalues are desired, consider using shift-invert mode for better performance.

maxiter [int, optional] Maximum number of Arnoldi update iterations allowed. Default: $n*10$

tol [float] Relative accuracy for eigenvalues (stopping criterion). The default value of 0 implies machine precision.

Minv [N x N matrix, array, sparse matrix, or LinearOperator] See notes in *M*, above.

OPinv [N x N matrix, array, sparse matrix, or LinearOperator] See notes in *sigma*, above.

return_eigenvectors [bool] Return eigenvectors (True) in addition to eigenvalues. This value determines the order in which eigenvalues are sorted. The sort order is also dependent on the *which* variable.

For which = ‘LM’ or ‘SA’:
 If *return_eigenvectors* is True, eigenvalues are sorted by algebraic value.
 If *return_eigenvectors* is False, eigenvalues are sorted by absolute value.

For which = ‘BE’ or ‘LA’:
 eigenvalues are always sorted by algebraic value.

For which = ‘SM’:
 If *return_eigenvectors* is True, eigenvalues are sorted by algebraic value.
 If *return_eigenvectors* is False, eigenvalues are sorted by decreasing absolute value.

mode [string [‘normal’ | ‘buckling’ | ‘cayley’]] Specify strategy to use for shift-invert mode. This argument applies only for real-valued *A* and $\sigma \neq \text{None}$. For shift-invert mode, ARPACK internally solves the eigenvalue problem $OP * x'[i] = w'[i] * B * x'[i]$ and transforms the resulting Ritz vectors $x'[i]$ and Ritz values $w'[i]$ into the desired eigenvectors and eigenvalues of the problem $A * x[i] = w[i] * M * x[i]$. The modes are as follows:

‘normal’: $OP = [A - \sigma * M]^{-1} @ M$, $B = M$, $w'[i] = 1 / (w[i] - \sigma)$

‘buckling’:
 $OP = [A - \sigma * M]^{-1} @ A$, $B = A$, $w'[i] = w[i] / (w[i] - \sigma)$

‘cayley’: $OP = [A - \sigma * M]^{-1} @ [A + \sigma * M]$, $B = M$, $w'[i] = (w[i] + \sigma) / (w[i] - \sigma)$

The choice of mode will affect which eigenvalues are selected by the keyword ‘which’, and can also impact the stability of convergence (see [2] for a discussion).

Raises

ArpackNoConvergence

When the requested convergence is not obtained.

The currently converged eigenvalues and eigenvectors can be found as *eigenvalues* and *eigenvectors* attributes of the exception object.

See also:

eigs

eigenvalues and eigenvectors for a general (nonsymmetric) matrix *A*

svds

singular value decomposition for a matrix *A*

Notes

This function is a wrapper to the ARPACK [1] SSEUPD and DSEUPD functions which use the Implicitly Restarted Lanczos Method to find the eigenvalues and eigenvectors [2].

References

[1], [2]

Examples

```
>>> from scipy.sparse.linalg import eigsh
>>> identity = np.eye(13)
>>> eigenvalues, eigenvectors = eigsh(identity, k=6)
>>> eigenvalues
array([1., 1., 1., 1., 1., 1.])
>>> eigenvectors.shape
(13, 6)
```

scipy.sparse.linalg.lobpcg

`scipy.sparse.linalg.lobpcg`(*A*, *X*, *B=None*, *M=None*, *Y=None*, *tol=None*, *maxiter=None*, *largest=True*, *verbosityLevel=0*, *retLambdaHistory=False*, *retResidualNormsHistory=False*)

Locally Optimal Block Preconditioned Conjugate Gradient Method (LOBPCG)

LOBPCG is a preconditioned eigensolver for large symmetric positive definite (SPD) generalized eigenproblems.

Parameters

- A** [[sparse matrix, dense matrix, LinearOperator]] The symmetric linear operator of the problem, usually a sparse matrix. Often called the “stiffness matrix”.
- X** [ndarray, float32 or float64] Initial approximation to the *k* eigenvectors (non-sparse). If *A* has `shape=(n, n)` then *X* should have `shape=(n, k)`.
- B** [[dense matrix, sparse matrix, LinearOperator], optional] The right hand side operator in a generalized eigenproblem. By default, `B = Identity`. Often called the “mass matrix”.
- M** [[dense matrix, sparse matrix, LinearOperator], optional] Preconditioner to *A*; by default `M = Identity`. *M* should approximate the inverse of *A*.
- Y** [ndarray, float32 or float64, optional] *n*-by-`sizeY` matrix of constraints (non-sparse), `sizeY < n`. The iterations will be performed in the *B*-orthogonal complement of the column-space of *Y*. *Y* must be full rank.
- tol** [scalar, optional] Solver tolerance (stopping criterion). The default is `tol=n*sqrt(eps)`.
- maxiter** [int, optional] Maximum number of iterations. The default is `maxiter = 20`.
- largest** [bool, optional] When True, solve for the largest eigenvalues, otherwise the smallest.
- verbosityLevel** [int, optional] Controls solver output. The default is `verbosityLevel=0`.
- retLambdaHistory** [bool, optional] Whether to return eigenvalue history. Default is False.
- retResidualNormsHistory** [bool, optional] Whether to return history of residual norms. Default is False.

Returns

w [ndarray] Array of k eigenvalues
v [ndarray] An array of k eigenvectors. v has the same shape as X .
lambdas [list of ndarray, optional] The eigenvalue history, if `retLambdaHistory` is True.
rnorms [list of ndarray, optional] The history of residual norms, if `retResidualNormsHistory` is True.

Notes

If both `retLambdaHistory` and `retResidualNormsHistory` are True, the return tuple has the following format (lambda, V, lambda history, residual norms history).

In the following n denotes the matrix size and m the number of required eigenvalues (smallest or largest).

The LOBPCG code internally solves eigenproblems of the size $3m$ on every iteration by calling the “standard” dense eigensolver, so if m is not small enough compared to n , it does not make sense to call the LOBPCG code, but rather one should use the “standard” eigensolver, e.g. `numpy` or `scipy` function in this case. If one calls the LOBPCG algorithm for $5m > n$, it will most likely break internally, so the code tries to call the standard function instead.

It is not that n should be large for the LOBPCG to work, but rather the ratio n / m should be large. If you call LOBPCG with $m=1$ and $n=10$, it works though n is small. The method is intended for extremely large n / m [4].

The convergence speed depends basically on two factors:

1. How well relatively separated the seeking eigenvalues are from the rest of the eigenvalues. One can try to vary m to make this better.
2. How well conditioned the problem is. This can be changed by using proper preconditioning. For example, a rod vibration test problem (under tests directory) is ill-conditioned for large n , so convergence will be slow, unless efficient preconditioning is used. For this specific problem, a good simple preconditioner function would be a linear solve for A , which is easy to code since A is tridiagonal.

References

[1], [2], [3], [4]

Examples

Solve $A x = \text{lambda } x$ with constraints and preconditioning.

```
>>> import numpy as np
>>> from scipy.sparse import spdiags, issparse
>>> from scipy.sparse.linalg import lobpcg, LinearOperator
>>> n = 100
>>> vals = np.arange(1, n + 1)
>>> A = spdiags(vals, 0, n, n)
>>> A.toarray()
array([[ 1.,  0.,  0., ...,  0.,  0.,  0.],
       [ 0.,  2.,  0., ...,  0.,  0.,  0.],
       [ 0.,  0.,  3., ...,  0.,  0.,  0.],
       ...,
       [ 0.,  0.,  0., ..., 98.,  0.,  0.],
       [ 0.,  0.,  0., ...,  0., 99.,  0.],
       [ 0.,  0.,  0., ...,  0.,  0., 100.]])
```

Constraints:

```
>>> Y = np.eye(n, 3)
```

Initial guess for eigenvectors, should have linearly independent columns. Column dimension = number of requested eigenvalues.

```
>>> X = np.random.rand(n, 3)
```

Preconditioner in the inverse of A in this example:

```
>>> invA = spdiags([1./vals], 0, n, n)
```

The preconditioner must be defined by a function:

```
>>> def precondition(x):
...     return invA @ x
```

The argument `x` of the preconditioner function is a matrix inside `lobpcg`, thus the use of matrix-matrix product `@`.

The preconditioner function is passed to `lobpcg` as a `LinearOperator`:

```
>>> M = LinearOperator(matvec=precond, matmat=precond,
...                    shape=(n, n), dtype=float)
```

Let us now solve the eigenvalue problem for the matrix A:

```
>>> eigenvalues, _ = lobpcg(A, X, Y=Y, M=M, largest=False)
>>> eigenvalues
array([4., 5., 6.]
```

Note that the vectors passed in `Y` are the eigenvectors of the 3 smallest eigenvalues. The results returned are orthogonal to those.

Singular values problems:

<code>svds(A[, k, ncv, tol, which, v0, maxiter, ...])</code>	Compute the largest or smallest <code>k</code> singular values/vectors for a sparse matrix.
--	---

scipy.sparse.linalg.svds

`scipy.sparse.linalg.svds` (`A`, `k=6`, `ncv=None`, `tol=0`, `which='LM'`, `v0=None`, `maxiter=None`, `return_singular_vectors=True`, `solver='arpack'`)

Compute the largest or smallest `k` singular values/vectors for a sparse matrix. The order of the singular values is not guaranteed.

Parameters

A	[[sparse matrix, LinearOperator]] Array to compute the SVD on, of shape (M, N)
k	[int, optional] Number of singular values and vectors to compute. Must be $1 \leq k < \min(A.shape)$.
ncv	[int, optional] The number of Lanczos vectors generated <code>ncv</code> must be greater than <code>k+1</code> and smaller than <code>n</code> ; it is recommended that <code>ncv > 2*k</code> Default: <code>min(n, max(2*k + 1, 20))</code>
tol	[float, optional] Tolerance for singular values. Zero (default) means machine precision.
which	[str, ['LM' 'SM'], optional] Which <code>k</code> singular values to find:

- ‘LM’ : largest singular values
 - ‘SM’ : smallest singular values
- New in version 0.12.0.
- v0** [ndarray, optional] Starting vector for iteration, of length $\min(A.\text{shape})$. Should be an (approximate) left singular vector if $N > M$ and a right singular vector otherwise. Default: random
- New in version 0.12.0.
- maxiter** [int, optional] Maximum number of iterations.
- New in version 0.12.0.
- return_singular_vectors** [bool or str, optional]
- True: return singular vectors (True) in addition to singular values.
- New in version 0.12.0.
- “u”: only return the u matrix, without computing vh (if $N > M$).
 - “vh”: only return the vh matrix, without computing u (if $N \leq M$).
- New in version 0.16.0.
- solver** [str, optional] Eigenvalue solver to use. Should be ‘arpack’ or ‘lobpcg’. Default: ‘arpack’

Returns

- u** [ndarray, shape=(M, k)] Unitary matrix having left singular vectors as columns. If *return_singular_vectors* is “vh”, this variable is not computed, and None is returned instead.
- s** [ndarray, shape=(k,)] The singular values.
- vt** [ndarray, shape=(k, N)] Unitary matrix having right singular vectors as rows. If *return_singular_vectors* is “u”, this variable is not computed, and None is returned instead.

Notes

This is a naive implementation using ARPACK or LOBPCG as an eigensolver on $A.H * A$ or $A * A.H$, depending on which one is more efficient.

Examples

```
>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import svds, eigs
>>> A = csc_matrix([[1, 0, 0], [5, 0, 2], [0, -1, 0], [0, 0, 3]], dtype=float)
>>> u, s, vt = svds(A, k=2)
>>> s
array([ 2.75193379,  5.6059665 ])
>>> np.sqrt(eigs(A.dot(A.T), k=2)[0]).real
array([ 5.6059665 ,  2.75193379])
```

Complete or incomplete LU factorizations

<i>splu</i> (A[, permc_spec, diag_pivot_thresh, ...])	Compute the LU decomposition of a sparse, square matrix.
<i>spilu</i> (A[, drop_tol, fill_factor, drop_rule, ...])	Compute an incomplete LU decomposition for a sparse, square matrix.
<i>SuperLU</i> ()	LU factorization of a sparse matrix.

scipy.sparse.linalg.splu

`scipy.sparse.linalg.splu` (*A*, *perm_spec=None*, *diag_pivot_thresh=None*, *relax=None*,
panel_size=None, *options={}*)

Compute the LU decomposition of a sparse, square matrix.

Parameters

- A** [sparse matrix] Sparse matrix to factorize. Should be in CSR or CSC format.
- perm_spec** [str, optional] How to permute the columns of the matrix for sparsity preservation. (default: 'COLAMD')
- NATURAL: natural ordering.
 - MMD_ATA: minimum degree ordering on the structure of $A^T A$.
 - MMD_AT_PLUS_A: minimum degree ordering on the structure of $A^T + A$.
 - COLAMD: approximate minimum degree column ordering
- diag_pivot_thresh** [float, optional] Threshold used for a diagonal entry to be an acceptable pivot. See SuperLU user's guide for details [1]
- relax** [int, optional] Expert option for customizing the degree of relaxing supernodes. See SuperLU user's guide for details [1]
- panel_size** [int, optional] Expert option for customizing the panel size. See SuperLU user's guide for details [1]
- options** [dict, optional] Dictionary containing additional expert options to SuperLU. See SuperLU user guide [1] (section 2.4 on the 'Options' argument) for more details. For example, you can specify `options=dict(Equil=False, IterRefine='SINGLE')` to turn equilibration off and perform a single iterative refinement.

Returns

- invA** [scipy.sparse.linalg.SuperLU] Object, which has a `solve` method.

See also:

spilu

incomplete LU decomposition

Notes

This function uses the SuperLU library.

References

[1]

Examples

```

>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import splu
>>> A = csc_matrix([[1., 0., 0.], [5., 0., 2.], [0., -1., 0.]],
->dtype=float)
>>> B = splu(A)
>>> x = np.array([1., 2., 3.], dtype=float)
>>> B.solve(x)
array([ 1. , -3. , -1.5])
>>> A.dot(B.solve(x))
array([ 1.,  2.,  3.])
>>> B.solve(A.dot(x))
array([ 1.,  2.,  3.])

```

scipy.sparse.linalg.spilu

`scipy.sparse.linalg.spilu` (*A*, *drop_tol=None*, *fill_factor=None*, *drop_rule=None*, *perm_spec=None*, *diag_pivot_thresh=None*, *relax=None*, *panel_size=None*, *options=None*)

Compute an incomplete LU decomposition for a sparse, square matrix.

The resulting object is an approximation to the inverse of *A*.

Parameters

- A** [(N, N) array_like] Sparse matrix to factorize
- drop_tol** [float, optional] Drop tolerance ($0 \leq \text{tol} \leq 1$) for an incomplete LU decomposition. (default: $1e-4$)
- fill_factor** [float, optional] Specifies the fill ratio upper bound (≥ 1.0) for ILU. (default: 10)
- drop_rule** [str, optional] Comma-separated string of drop rules to use. Available rules: `basic`, `provs`, `column`, `area`, `secondary`, `dynamic`, `interp`. (Default: `basic, area`) See SuperLU documentation for details.

Remaining other options

Same as for `splu`

Returns**invA_approx**

[`scipy.sparse.linalg.SuperLU`] Object, which has a `solve` method.

See also:

`splu`

complete LU decomposition

Notes

To improve the better approximation to the inverse, you may need to increase *fill_factor* AND decrease *drop_tol*. This function uses the SuperLU library.

Examples

```
>>> from scipy.sparse import csc_matrix
>>> from scipy.sparse.linalg import spilu
>>> A = csc_matrix([[1., 0., 0.], [5., 0., 2.], [0., -1., 0.]],
dtype=float)
>>> B = spilu(A)
>>> x = np.array([1., 2., 3.], dtype=float)
>>> B.solve(x)
array([ 1. , -3. , -1.5])
>>> A.dot(B.solve(x))
array([ 1.,  2.,  3.])
>>> B.solve(A.dot(x))
array([ 1.,  2.,  3.])
```

scipy.sparse.linalg.SuperLU

class `scipy.sparse.linalg.SuperLU`

LU factorization of a sparse matrix.

Factorization is represented as:

$$P_r * A * P_c = L * U$$

To construct these *SuperLU* objects, call the *splu* and *spilu* functions.

Notes

New in version 0.14.0.

Examples

The LU decomposition can be used to solve matrix equations. Consider:

```
>>> import numpy as np
>>> from scipy.sparse import csc_matrix, linalg as sla
>>> A = csc_matrix([[1, 2, 0, 4], [1, 0, 0, 1], [1, 0, 2, 1], [2, 2, 1, 0.]])
```

This can be solved for a given right-hand side:

```
>>> lu = sla.splu(A)
>>> b = np.array([1, 2, 3, 4])
>>> x = lu.solve(b)
>>> A.dot(x)
array([ 1.,  2.,  3.,  4.] )
```

The `lu` object also contains an explicit representation of the decomposition. The permutations are represented as mappings of indices:

```
>>> lu.perm_r
array([0, 2, 1, 3], dtype=int32)
>>> lu.perm_c
array([2, 0, 1, 3], dtype=int32)
```

The L and U factors are sparse matrices in CSC format:

```
>>> lu.L.A
array([[ 1. ,  0. ,  0. ,  0. ],
       [ 0. ,  1. ,  0. ,  0. ],
       [ 0. ,  0. ,  1. ,  0. ],
       [ 1. ,  0.5,  0.5,  1. ]])
>>> lu.U.A
array([[ 2.,  0.,  1.,  4.],
       [ 0.,  2.,  1.,  1.],
       [ 0.,  0.,  1.,  1.],
       [ 0.,  0.,  0., -5.]])
```

The permutation matrices can be constructed:

```
>>> Pr = csc_matrix((np.ones(4), (lu.perm_r, np.arange(4))))
>>> Pc = csc_matrix((np.ones(4), (np.arange(4), lu.perm_c)))
```

We can reassemble the original matrix:

```
>>> (Pr.T * (lu.L * lu.U) * Pc.T).A
array([[ 1.,  2.,  0.,  4.],
       [ 1.,  0.,  0.,  1.],
       [ 1.,  0.,  2.,  1.],
       [ 2.,  2.,  1.,  0.]])
```

Attributes

- shape** Shape of the original matrix as a tuple of ints.
- nnz** Number of nonzero elements in the matrix.
- perm_c** Permutation Pc represented as an array of indices.
- perm_r** Permutation Pr represented as an array of indices.
- L** Lower triangular factor with unit diagonal as a *scipy.sparse.csc_matrix*.
- U** Upper triangular factor as a *scipy.sparse.csc_matrix*.

Methods

<code>solve(rhs[, trans])</code>	Solves linear system of equations with one or several right-hand sides.
----------------------------------	---

scipy.sparse.linalg.SuperLU.solve

`SuperLU.solve` (*rhs* [, *trans*])

Solves linear system of equations with one or several right-hand sides.

Parameters

rhs [ndarray, shape (n,) or (n, k)] Right hand side(s) of equation
trans [{'N', 'T', 'H'}, optional] Type of system to solve:

'N'	:	A	*	x	==	rhs	(default)
'T'	:	A ^T	*	x	==	rhs	
'H'	:	A ^H	*	x	==	rhs	

i.e., normal, transposed, and hermitian conjugate.

Returns

x [ndarray, shape *rhs*.shape] Solution vector(s)

6.24.6 Exceptions

<code>ArpackNoConvergence</code> (<i>msg</i> , <i>eigenvalues</i> , ...)	ARPACK iteration did not converge
<code>ArpackError</code> (<i>info</i> [, <i>infodict</i>])	ARPACK error

scipy.sparse.linalg.ArpackNoConvergence

exception `scipy.sparse.linalg.ArpackNoConvergence` (*msg*, *eigenvalues*, *eigenvectors*)

ARPACK iteration did not converge

Attributes

eigenvalues
 [ndarray] Partial result. Converged eigenvalues.

eigenvectors
 [ndarray] Partial result. Converged eigenvectors.

with_traceback ()

Exception.with_traceback(*tb*) – set self.__traceback__ to *tb* and return self.

scipy.sparse.linalg.ArpackError

exception `scipy.sparse.linalg.ArpackError` (*info*, *infodict*={*c*: {- 9999: 'Could not build an Arnoldi factorization. IPARAM(5) returns the size of the current Arnoldi factorization. The user is advised to check that enough workspace and array storage has been allocated.', - 13: "NEV and WHICH = 'BE' are incompatible.", - 12: 'IPARAM(1) must be equal to 0 or 1.', - 11: "IPARAM(7) = 1 and BMAT = 'G' are incompatible.", - 10: 'IPARAM(7) must be 1,2,3.', - 9: 'Starting vector is zero.', - 8: 'Error return from LAPACK eigenvalue calculation;', - 7: 'Length of private work array WORKL is not sufficient.', - 6: "BMAT must be one of 'I' or 'G'.", - 5: " WHICH must be one of 'LM', 'SM', 'LR', 'SR', 'LI', 'SI'", - 4: 'The maximum number of Arnoldi update iterations allowed must be greater than zero.', - 3: 'NCV-NEV >= 2 and less than or equal to N.', - 2: 'NEV must be positive.', - 1: 'N must be positive.', 0: 'Normal exit.', 1: 'Maximum number of iterations taken. All possible eigenvalues of OP has been found. IPARAM(5) returns the number of wanted converged Ritz values.', 2: 'No longer an informational error. Deprecated starting with release 2 of ARPACK.', 3: 'No shifts could be applied during a cycle of the Implicitly restarted Arnoldi iteration. One possibility is to increase the size of NCV relative to NEV. '}, *d*: {- 9999: 'Could not build an Arnoldi factorization. IPARAM(5) returns the size of the current Arnoldi factorization. The user is advised to check that enough workspace and array storage has been allocated.', - 13: "NEV and WHICH = 'BE' are incompatible.", - 12: 'IPARAM(1) must be equal to 0 or 1.', - 11: "IPARAM(7) = 1 and BMAT = 'G' are incompatible.", - 10: 'IPARAM(7) must be 1,2,3,4.', - 9: 'Starting vector is zero.', - 8: 'Error return from LAPACK eigenvalue calculation;', - 7: 'Length of private work array WORKL is not sufficient.', - 6: "BMAT must be one of 'I' or 'G'.", - 5: " WHICH must be one of 'LM', 'SM', 'LR', 'SR', 'LI', 'SI'", - 4: 'The maximum number of Arnoldi update iterations allowed must be greater than zero.', - 3: 'NCV-NEV >= 2 and less than or equal to N.', - 2: 'NEV must be positive.', - 1: 'N must be positive.', 0: 'Normal exit.', 1: 'Maximum number of iterations taken. All possible eigenvalues of OP has been found. IPARAM(5) returns the number of wanted converged Ritz values.', 2: 'No longer an informational error. Deprecated starting with release 2 of ARPACK.', 3: 'No shifts could be applied during a cycle of the Implicitly restarted Arnoldi iteration. One possibility is to increase the size of NCV relative to NEV. '}, *s*: {- 9999: 'Could not build an Arnoldi factorization. IPARAM(5) returns the size of the current Arnoldi factorization. The user is advised to check that enough workspace and array storage has been allocated.', - 13: "NEV and WHICH = 'BE' are incompatible.", - 12: 'IPARAM(1) must be equal to 0 or 1.', - 11:

`with_traceback()`

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

6.25 Compressed sparse graph routines (`scipy.sparse.csgraph`)

Fast graph algorithms based on sparse matrix representations.

6.25.1 Contents

<code>connected_components(csgraph[, directed, ...])</code>	Analyze the connected components of a sparse graph
<code>laplacian(csgraph[, normed, return_diag, ...])</code>	Return the Laplacian matrix of a directed graph.
<code>shortest_path(csgraph[, method, directed, ...])</code>	Perform a shortest-path graph search on a positive directed or undirected graph.
<code>dijkstra(csgraph[, directed, indices, ...])</code>	Dijkstra algorithm using Fibonacci Heaps
<code>floyd_warshall(csgraph[, directed, ...])</code>	Compute the shortest path lengths using the Floyd-Warshall algorithm
<code>bellman_ford(csgraph[, directed, indices, ...])</code>	Compute the shortest path lengths using the Bellman-Ford algorithm.
<code>johnson(csgraph[, directed, indices, ...])</code>	Compute the shortest path lengths using Johnson's algorithm.
<code>breadth_first_order(csgraph, i_start[, ...])</code>	Return a breadth-first ordering starting with specified node.
<code>depth_first_order(csgraph, i_start[, ...])</code>	Return a depth-first ordering starting with specified node.
<code>breadth_first_tree(csgraph, i_start[, directed])</code>	Return the tree generated by a breadth-first search
<code>depth_first_tree(csgraph, i_start[, directed])</code>	Return a tree generated by a depth-first search.
<code>minimum_spanning_tree(csgraph[, overwrite])</code>	Return a minimum spanning tree of an undirected graph
<code>reverse_cuthill_mckee(graph[, symmetric_mode])</code>	Returns the permutation array that orders a sparse CSR or CSC matrix in Reverse-Cuthill McKee ordering.
<code>maximum_flow(csgraph, source, sink)</code>	Maximize the flow between two vertices in a graph.
<code>maximum_bipartite_matching(graph[, perm_type])</code>	Returns a matching of a bipartite graph whose cardinality is as least that of any given matching of the graph.
<code>min_weight_full_bipartite_matching(...[, ...])</code>	Returns the minimum weight full matching of a bipartite graph.
<code>structural_rank(graph)</code>	Compute the structural rank of a graph (matrix) with a given sparsity pattern.
<code>NegativeCycleError([message])</code>	

`scipy.sparse.csgraph.connected_components`

`scipy.sparse.csgraph.connected_components` (*csgraph*, *directed=True*, *connection='weak'*, *return_labels=True*)

Analyze the connected components of a sparse graph

New in version 0.11.0.

Parameters

csgraph [array_like or sparse matrix] The N x N matrix representing the compressed sparse graph. The input csgraph will be converted to csr format for the calculation.

- directed** [bool, optional] If True (default), then operate on a directed graph: only move from point *i* to point *j* along paths `csgraph[i, j]`. If False, then find the shortest path on an undirected graph: the algorithm can progress from point *i* to *j* along `csgraph[i, j]` or `csgraph[j, i]`.
- connection** [str, optional] ['weak'|'strong']. For directed graphs, the type of connection to use. Nodes *i* and *j* are strongly connected if a path exists both from *i* to *j* and from *j* to *i*. A directed graph is weakly connected if replacing all of its directed edges with undirected edges produces a connected (undirected) graph. If `directed == False`, this keyword is not referenced.
- return_labels** [bool, optional] If True (default), then return the labels for each of the connected components.

Returns

- n_components: int**
The number of connected components.
- labels: ndarray**
The length-N array of labels of the connected components.

References

[1]

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import connected_components
```

```
>>> graph = [
... [ 0, 1, 1, 0, 0 ],
... [ 0, 0, 1, 0, 0 ],
... [ 0, 0, 0, 0, 0 ],
... [ 0, 0, 0, 0, 1 ],
... [ 0, 0, 0, 0, 0 ]
... ]
>>> graph = csr_matrix(graph)
>>> print(graph)
(0, 1) 1
(0, 2) 1
(1, 2) 1
(3, 4) 1
```

```
>>> n_components, labels = connected_components(csgraph=graph,
->directed=False, return_labels=True)
>>> n_components
2
>>> labels
array([0, 0, 0, 1, 1], dtype=int32)
```

scipy.sparse.csgraph.laplacian

`scipy.sparse.csgraph.laplacian` (*csgraph*, *normed=False*, *return_diag=False*,
use_out_degree=False)

Return the Laplacian matrix of a directed graph.

Parameters

- csgraph** [array_like or sparse matrix, 2 dimensions] compressed-sparse graph, with shape (N, N).
- normed** [bool, optional] If True, then compute symmetric normalized Laplacian.
- return_diag** [bool, optional] If True, then also return an array related to vertex degrees.
- use_out_degree** [bool, optional] If True, then use out-degree instead of in-degree. This distinction matters only if the graph is asymmetric. Default: False.

Returns

- lap** [ndarray or sparse matrix] The $N \times N$ laplacian matrix of *csgraph*. It will be a NumPy array (dense) if the input was dense, or a sparse matrix otherwise.
- diag** [ndarray, optional] The length- N diagonal of the Laplacian matrix. For the normalized Laplacian, this is the array of square roots of vertex degrees or 1 if the degree is zero.

Notes

The Laplacian matrix of a graph is sometimes referred to as the “Kirchoff matrix” or the “admittance matrix”, and is useful in many parts of spectral graph theory. In particular, the eigen-decomposition of the laplacian matrix can give insight into many properties of the graph.

Examples

```
>>> from scipy.sparse import csgraph
>>> G = np.arange(5) * np.arange(5)[:, np.newaxis]
>>> G
array([[ 0,  0,  0,  0,  0],
       [ 0,  1,  2,  3,  4],
       [ 0,  2,  4,  6,  8],
       [ 0,  3,  6,  9, 12],
       [ 0,  4,  8, 12, 16]])
>>> csgraph.laplacian(G, normed=False)
array([[ 0,  0,  0,  0,  0],
       [ 0,  9, -2, -3, -4],
       [ 0, -2, 16, -6, -8],
       [ 0, -3, -6, 21, -12],
       [ 0, -4, -8, -12, 24]])
```


scipy.sparse.csgraph.shortest_path

`scipy.sparse.csgraph.shortest_path` (*csgraph*, *method='auto'*, *directed=True*, *return_predecessors=False*, *unweighted=False*, *overwrite=False*, *indices=None*)

Perform a shortest-path graph search on a positive directed or undirected graph.

New in version 0.11.0.

Parameters

- csgraph** [array, matrix, or sparse matrix, 2 dimensions] The $N \times N$ array of distances representing the input graph.
- method** [string ['auto'|'FW'|'D'], optional] Algorithm to use for shortest paths. Options are:
'auto' – (default) select the best among 'FW', 'D', 'BF', or 'J'
 based on the input data.
'FW' – Floyd-Warshall algorithm. Computational cost is
 approximately $O[N^3]$. The input csgraph will be converted to a dense representation.
'D' – Dijkstra's algorithm with Fibonacci heaps. Computational
 cost is approximately $O[N(N \cdot k + N \cdot \log(N))]$, where k is the average number of connected edges per node. The input csgraph will be converted to a csr representation.
'BF' – Bellman-Ford algorithm. This algorithm can be used when
 weights are negative. If a negative cycle is encountered, an error will be raised. Computational cost is approximately $O[N(N \cdot 2 \cdot k)]$, where k is the average number of connected edges per node. The input csgraph will be converted to a csr representation.
'J' – Johnson's algorithm. Like the Bellman-Ford algorithm,
 Johnson's algorithm is designed for use when the weights are negative. It combines the Bellman-Ford algorithm with Dijkstra's algorithm for faster computation.
- directed** [bool, optional] If True (default), then find the shortest path on a directed graph: only move from point i to point j along paths `csgraph[i, j]`. If False, then find the shortest path on an undirected graph: the algorithm can progress from point i to j along `csgraph[i, j]` or `csgraph[j, i]`
- return_predecessors** [bool, optional] If True, return the size (N, N) predecessor matrix
- unweighted** [bool, optional] If True, then find unweighted distances. That is, rather than finding the path between each point such that the sum of weights is minimized, find the path such that the number of edges is minimized.
- overwrite** [bool, optional] If True, overwrite `csgraph` with the result. This applies only if `method == 'FW'` and `csgraph` is a dense, c-ordered array with `dtype=float64`.
- indices** [array_like or int, optional] If specified, only compute the paths from the points at the given indices. Incompatible with `method == 'FW'`.

Returns

- dist_matrix** [ndarray] The $N \times N$ matrix of distances between graph nodes. `dist_matrix[i,j]` gives the shortest distance from point i to point j along the graph.
- predecessors** [ndarray] Returned only if `return_predecessors == True`. The $N \times N$ matrix of predecessors, which can be used to reconstruct the shortest paths. Row i of the predecessor matrix contains information on the shortest paths from point i : each entry `predecessors[i, j]` gives the index

of the previous node in the path from point i to point j . If no path exists between point i and j , then `predecessors[i, j] = -9999`

Raises

NegativeCycleError:

if there are negative cycles in the graph

Notes

As currently implemented, Dijkstra's algorithm and Johnson's algorithm do not work for graphs with direction-dependent distances when `directed == False`. i.e., if `csgraph[i,j]` and `csgraph[j,i]` are non-equal edges, `method='D'` may yield an incorrect result.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import shortest_path
```

```
>>> graph = [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [2, 0, 0, 3],
... [0, 0, 0, 0]
... ]
>>> graph = csr_matrix(graph)
>>> print(graph)
(0, 1) 1
(0, 2) 2
(1, 3) 1
(2, 0) 2
(2, 3) 3
```

```
>>> dist_matrix, predecessors = shortest_path(csgraph=graph,
↳ directed=False, indices=0, return_predecessors=True)
>>> dist_matrix
array([ 0.,  1.,  2.,  2.])
>>> predecessors
array([-9999,    0,    0,    1], dtype=int32)
```

scipy.sparse.csgraph.dijkstra

`scipy.sparse.csgraph.dijkstra` (*csgraph*, *directed=True*, *indices=None*, *return_predecessors=False*, *unweighted=False*, *limit=np.inf*, *min_only=False*)

Dijkstra algorithm using Fibonacci Heaps

New in version 0.11.0.

Parameters

csgraph [array, matrix, or sparse matrix, 2 dimensions] The $N \times N$ array of non-negative distances representing the input graph.

- directed** [bool, optional] If True (default), then find the shortest path on a directed graph: only move from point *i* to point *j* along paths `csgraph[i, j]` and from point *j* to *i* along paths `csgraph[j, i]`. If False, then find the shortest path on an undirected graph: the algorithm can progress from point *i* to *j* or *j* to *i* along either `csgraph[i, j]` or `csgraph[j, i]`.
- indices** [array_like or int, optional] if specified, only compute the paths from the points at the given indices.
- return_predecessors** [bool, optional] If True, return the size (N, N) predecessor matrix
- unweighted** [bool, optional] If True, then find unweighted distances. That is, rather than finding the path between each point such that the sum of weights is minimized, find the path such that the number of edges is minimized.
- limit** [float, optional] The maximum distance to calculate, must be ≥ 0 . Using a smaller limit will decrease computation time by aborting calculations between pairs that are separated by a distance $>$ limit. For such pairs, the distance will be equal to `np.inf` (i.e., not connected).
New in version 0.14.0.
- min_only** [bool, optional] If False (default), for every node in the graph, find the shortest path from every node in indices. If True, for every node in the graph, find the shortest path from any of the nodes in indices (which can be substantially faster).
New in version 1.3.0.

Returns

- dist_matrix** [ndarray, shape ([n_indices,]n_nodes,)] The matrix of distances between graph nodes. If `min_only=False`, `dist_matrix` has shape (n_indices, n_nodes) and `dist_matrix[i, j]` gives the shortest distance from point *i* to point *j* along the graph. If `min_only=True`, `dist_matrix` has shape (n_nodes,) and contains for a given node the shortest path to that node from any of the nodes in indices.
- predecessors** [ndarray, shape ([n_indices,]n_nodes,)] If `min_only=False`, this has shape (n_indices, n_nodes), otherwise it has shape (n_nodes,). Returned only if `return_predecessors == True`. The matrix of predecessors, which can be used to reconstruct the shortest paths. Row *i* of the predecessor matrix contains information on the shortest paths from point *i*: each entry `predecessors[i, j]` gives the index of the previous node in the path from point *i* to point *j*. If no path exists between point *i* and *j*, then `predecessors[i, j] = -9999`
- sources** [ndarray, shape (n_nodes,)] Returned only if `min_only=True` and `return_predecessors=True`. Contains the index of the source which had the shortest path to each target. If no path exists within the limit, this will contain -9999. The value at the indices passed will be equal to that index (i.e. the fastest way to reach node *i*, is to start on node *i*).

Notes

As currently implemented, Dijkstra's algorithm does not work for graphs with direction-dependent distances when `directed == False`. i.e., if `csgraph[i,j]` and `csgraph[j,i]` are not equal and both are nonzero, setting `directed=False` will not yield the correct result.

Also, this routine does not work for graphs with negative distances. Negative distances can lead to infinite cycles that must be handled by specialized algorithms such as Bellman-Ford's algorithm or Johnson's algorithm.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import dijkstra
```

```
>>> graph = [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [0, 0, 0, 3],
... [0, 0, 0, 0]
... ]
>>> graph = csr_matrix(graph)
>>> print(graph)
(0, 1)    1
(0, 2)    2
(1, 3)    1
(2, 3)    3
```

```
>>> dist_matrix, predecessors = dijkstra(csgraph=graph, directed=False,
↳ indices=0, return_predecessors=True)
>>> dist_matrix
array([ 0.,  1.,  2.,  2.])
>>> predecessors
array([-9999,    0,    0,    1], dtype=int32)
```

scipy.sparse.csgraph.floyd_warshall

`scipy.sparse.csgraph.floyd_warshall` (*csgraph*, *directed=True*, *return_predecessors=False*, *unweighted=False*, *overwrite=False*)

Compute the shortest path lengths using the Floyd-Warshall algorithm

New in version 0.11.0.

Parameters

- csgraph** [array, matrix, or sparse matrix, 2 dimensions] The N x N array of distances representing the input graph.
- directed** [bool, optional] If True (default), then find the shortest path on a directed graph: only move from point i to point j along paths `csgraph[i, j]`. If False, then find the shortest path on an undirected graph: the algorithm can progress from point i to j along `csgraph[i, j]` or `csgraph[j, i]`
- return_predecessors** [bool, optional] If True, return the size (N, N) predecessor matrix
- unweighted** [bool, optional] If True, then find unweighted distances. That is, rather than finding the path between each point such that the sum of weights is minimized, find the path such that the number of edges is minimized.
- overwrite** [bool, optional] If True, overwrite `csgraph` with the result. This applies only if `csgraph` is a dense, c-ordered array with `dtype=float64`.

Returns

- dist_matrix** [ndarray] The N x N matrix of distances between graph nodes. `dist_matrix[i,j]` gives the shortest distance from point i to point j along the graph.

predecessors

[ndarray] Returned only if `return_predecessors == True`. The $N \times N$ matrix of predecessors, which can be used to reconstruct the shortest paths. Row i of the predecessor matrix contains information on the shortest paths from point i : each entry `predecessors[i, j]` gives the index of the previous node in the path from point i to point j . If no path exists between point i and j , then `predecessors[i, j] = -9999`

Raises**NegativeCycleError:**

if there are negative cycles in the graph

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import floyd_warshall
```

```
>>> graph = [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [2, 0, 0, 3],
... [0, 0, 0, 0]
... ]
>>> graph = csr_matrix(graph)
>>> print(graph)
(0, 1) 1
(0, 2) 2
(1, 3) 1
(2, 0) 2
(2, 3) 3
```

```
>>> dist_matrix, predecessors = floyd_warshall(csgraph=graph,
->directed=False, return_predecessors=True)
>>> dist_matrix
array([[ 0.,  1.,  2.,  2.],
       [ 1.,  0.,  3.,  1.],
       [ 2.,  3.,  0.,  3.],
       [ 2.,  1.,  3.,  0.]])
>>> predecessors
array([[ -9999,  0,  0,  1],
       [  1, -9999,  0,  1],
       [  2,  0, -9999,  2],
       [  1,  3,  3, -9999]], dtype=int32)
```

scipy.sparse.csgraph.bellman_ford

`scipy.sparse.csgraph.bellman_ford` (*csgraph*, *directed=True*, *indices=None*, *return_predecessors=False*, *unweighted=False*)

Compute the shortest path lengths using the Bellman-Ford algorithm.

The Bellman-Ford algorithm can robustly deal with graphs with negative weights. If a negative cycle is detected, an error is raised. For graphs without negative edge weights, Dijkstra's algorithm may be faster.

New in version 0.11.0.

Parameters

- csgraph** [array, matrix, or sparse matrix, 2 dimensions] The N x N array of distances representing the input graph.
- directed** [bool, optional] If True (default), then find the shortest path on a directed graph: only move from point i to point j along paths `csgraph[i, j]`. If False, then find the shortest path on an undirected graph: the algorithm can progress from point i to j along `csgraph[i, j]` or `csgraph[j, i]`
- indices** [array_like or int, optional] if specified, only compute the paths from the points at the given indices.
- return_predecessors** [bool, optional] If True, return the size (N, N) predecessor matrix
- unweighted** [bool, optional] If True, then find unweighted distances. That is, rather than finding the path between each point such that the sum of weights is minimized, find the path such that the number of edges is minimized.

Returns

- dist_matrix** [ndarray] The N x N matrix of distances between graph nodes. `dist_matrix[i,j]` gives the shortest distance from point i to point j along the graph.
- predecessors** [ndarray] Returned only if `return_predecessors == True`. The N x N matrix of predecessors, which can be used to reconstruct the shortest paths. Row i of the predecessor matrix contains information on the shortest paths from point i: each entry `predecessors[i, j]` gives the index of the previous node in the path from point i to point j. If no path exists between point i and j, then `predecessors[i, j] = -9999`

Raises

- NegativeCycleError:**
if there are negative cycles in the graph

Notes

This routine is specially designed for graphs with negative edge weights. If all edge weights are positive, then Dijkstra's algorithm is a better choice.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import bellman_ford
```

```
>>> graph = [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [2, 0, 0, 3],
... [0, 0, 0, 0]
... ]
>>> graph = csr_matrix(graph)
>>> print(graph)
(0, 1) 1
(0, 2) 2
(1, 3) 1
(2, 0) 2
(2, 3) 3
```

```
>>> dist_matrix, predecessors = bellman_ford(csgraph=graph,
->directed=False, indices=0, return_predecessors=True)
>>> dist_matrix
array([ 0., 1., 2., 2.])
>>> predecessors
array([-9999, 0, 0, 1], dtype=int32)
```

scipy.sparse.csgraph.johnson

`scipy.sparse.csgraph.johnson` (*csgraph*, *directed=True*, *indices=None*, *return_predecessors=False*, *unweighted=False*)

Compute the shortest path lengths using Johnson's algorithm.

Johnson's algorithm combines the Bellman-Ford algorithm and Dijkstra's algorithm to quickly find shortest paths in a way that is robust to the presence of negative cycles. If a negative cycle is detected, an error is raised. For graphs without negative edge weights, dijkstra may be faster.

New in version 0.11.0.

Parameters

- csgraph** [array, matrix, or sparse matrix, 2 dimensions] The N x N array of distances representing the input graph.
- directed** [bool, optional] If True (default), then find the shortest path on a directed graph: only move from point i to point j along paths `csgraph[i, j]`. If False, then find the shortest path on an undirected graph: the algorithm can progress from point i to j along `csgraph[i, j]` or `csgraph[j, i]`
- indices** [array_like or int, optional] if specified, only compute the paths from the points at the given indices.
- return_predecessors** [bool, optional] If True, return the size (N, N) predecessor matrix
- unweighted** [bool, optional] If True, then find unweighted distances. That is, rather than finding the path between each point such that the sum of weights is minimized, find the path such that the number of edges is minimized.

Returns**dist_matrix**

[ndarray] The N x N matrix of distances between graph nodes. `dist_matrix[i,j]` gives the shortest distance from point `i` to point `j` along the graph.

predecessors

[ndarray] Returned only if `return_predecessors == True`. The N x N matrix of predecessors, which can be used to reconstruct the shortest paths. Row `i` of the predecessor matrix contains information on the shortest paths from point `i`: each entry `predecessors[i, j]` gives the index of the previous node in the path from point `i` to point `j`. If no path exists between point `i` and `j`, then `predecessors[i, j] = -9999`

Raises**NegativeCycleError:**

if there are negative cycles in the graph

Notes

This routine is specially designed for graphs with negative edge weights. If all edge weights are positive, then Dijkstra's algorithm is a better choice.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import johnson
```

```
>>> graph = [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [2, 0, 0, 3],
... [0, 0, 0, 0]
... ]
>>> graph = csr_matrix(graph)
>>> print(graph)
(0, 1)    1
(0, 2)    2
(1, 3)    1
(2, 0)    2
(2, 3)    3
```

```
>>> dist_matrix, predecessors = johnson(csgraph=graph, directed=False,
->indices=0, return_predecessors=True)
>>> dist_matrix
array([ 0.,  1.,  2.,  2.])
>>> predecessors
array([-9999,    0,    0,    1], dtype=int32)
```


scipy.sparse.csgraph.breadth_first_order

```
scipy.sparse.csgraph.breadth_first_order(csgraph, i_start, directed=True,
                                         return_predecessors=True)
```

Return a breadth-first ordering starting with specified node.

Note that a breadth-first order is not unique, but the tree which it generates is unique.

New in version 0.11.0.

Parameters

- csgraph** [array_like or sparse matrix] The $N \times N$ compressed sparse graph. The input csgraph will be converted to csr format for the calculation.
- i_start** [int] The index of starting node.
- directed** [bool, optional] If True (default), then operate on a directed graph: only move from point i to point j along paths $csgraph[i, j]$. If False, then find the shortest path on an undirected graph: the algorithm can progress from point i to j along $csgraph[i, j]$ or $csgraph[j, i]$.
- return_predecessors** [bool, optional] If True (default), then return the predecessor array (see below).

Returns

- node_array** [ndarray, one dimension] The breadth-first list of nodes, starting with specified node. The length of node_array is the number of nodes reachable from the specified node.
- predecessors** [ndarray, one dimension] Returned only if return_predecessors is True. The length- N list of predecessors of each node in a breadth-first tree. If node i is in the tree, then its parent is given by predecessors[i]. If node i is not in the tree (and for the parent node) then predecessors[i] = -9999.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import breadth_first_order
```

```
>>> graph = [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [2, 0, 0, 3],
... [0, 0, 0, 0]
... ]
>>> graph = csr_matrix(graph)
>>> print(graph)
(0, 1) 1
(0, 2) 2
(1, 3) 1
(2, 0) 2
(2, 3) 3
```

```
>>> breadth_first_order(graph, 0)
(array([0, 1, 2, 3], dtype=int32), array([-9999, 0, 0, 1],
    dtype=int32))
```

scipy.sparse.csgraph.depth_first_order

`scipy.sparse.csgraph.depth_first_order` (*csgraph*, *i_start*, *directed=True*, *return_predecessors=True*)

Return a depth-first ordering starting with specified node.

Note that a depth-first order is not unique. Furthermore, for graphs with cycles, the tree generated by a depth-first search is not unique either.

New in version 0.11.0.

Parameters

- csgraph** [array_like or sparse matrix] The N x N compressed sparse graph. The input csgraph will be converted to csr format for the calculation.
- i_start** [int] The index of starting node.
- directed** [bool, optional] If True (default), then operate on a directed graph: only move from point i to point j along paths `csgraph[i, j]`. If False, then find the shortest path on an undirected graph: the algorithm can progress from point i to j along `csgraph[i, j]` or `csgraph[j, i]`.
- return_predecessors** [bool, optional] If True (default), then return the predecessor array (see below).

Returns

- node_array** [ndarray, one dimension] The depth-first list of nodes, starting with specified node. The length of `node_array` is the number of nodes reachable from the specified node.
- predecessors** [ndarray, one dimension] Returned only if `return_predecessors` is True. The length-N list of predecessors of each node in a depth-first tree. If node i is in the tree, then its parent is given by `predecessors[i]`. If node i is not in the tree (and for the parent node) then `predecessors[i] = -9999`.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import depth_first_order
```

```
>>> graph = [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [2, 0, 0, 3],
... [0, 0, 0, 0]
... ]
>>> graph = csr_matrix(graph)
>>> print(graph)
(0, 1) 1
(0, 2) 2
(1, 3) 1
(2, 0) 2
(2, 3) 3
```

```
>>> depth_first_order(graph, 0)
(array([0, 1, 3, 2], dtype=int32), array([-9999, 0, 0, 1],
↳dtype=int32))
```

scipy.sparse.csgraph.breadth_first_tree

`scipy.sparse.csgraph.breadth_first_tree(csgraph, i_start, directed=True)`

Return the tree generated by a breadth-first search

Note that a breadth-first tree from a specified node is unique.

New in version 0.11.0.

Parameters


- csgraph** [array_like or sparse matrix] The N x N matrix representing the compressed sparse graph. The input csgraph will be converted to csr format for the calculation.
- i_start** [int] The index of starting node.
- directed** [bool, optional] If True (default), then operate on a directed graph: only move from point i to point j along paths `csgraph[i, j]`. If False, then find the shortest path on an undirected graph: the algorithm can progress from point i to j along `csgraph[i, j]` or `csgraph[j, i]`.

Returns

- cstree** [csr matrix] The N x N directed compressed-sparse representation of the breadth-first tree drawn from csgraph, starting at the specified node.

Examples

The following example shows the computation of a depth-first tree over a simple four-component graph, starting at node 0:



In compressed sparse representation, the solution looks like this:

```

>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import breadth_first_tree
>>> X = csr_matrix([[0, 8, 0, 3],
...                [0, 0, 2, 5],
...                [0, 0, 0, 6],
...                [0, 0, 0, 0]])
>>> Tcsr = breadth_first_tree(X, 0, directed=False)
>>> Tcsr.toarray().astype(int)
array([[0, 8, 0, 3],
       [0, 0, 2, 0],
       [0, 0, 0, 0],
       [0, 0, 0, 0]])

```

Note that the resulting graph is a Directed Acyclic Graph which spans the graph. A breadth-first tree from a given node is unique.

scipy.sparse.csgraph.depth_first_tree

`scipy.sparse.csgraph.depth_first_tree(csgraph, i_start, directed=True)`

Return a tree generated by a depth-first search.

Note that a tree generated by a depth-first search is not unique: it depends on the order that the children of each node are searched.

New in version 0.11.0.

Parameters


- csgraph** [array_like or sparse matrix] The $N \times N$ matrix representing the compressed sparse graph. The input csgraph will be converted to csr format for the calculation.
- i_start** [int] The index of starting node.
- directed** [bool, optional] If True (default), then operate on a directed graph: only move from point i to point j along paths $\text{csgraph}[i, j]$. If False, then find the shortest path on an undirected graph: the algorithm can progress from point i to j along $\text{csgraph}[i, j]$ or $\text{csgraph}[j, i]$.

Returns

- cstree** [csr matrix] The $N \times N$ directed compressed-sparse representation of the depth-first tree drawn from csgraph, starting at the specified node.

Examples

The following example shows the computation of a depth-first tree over a simple four-component graph, starting at node 0:



In compressed sparse representation, the solution looks like this:

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import depth_first_tree
>>> X = csr_matrix([[0, 8, 0, 3],
...                 [0, 0, 2, 5],
...                 [0, 0, 0, 6],
...                 [0, 0, 0, 0]])
>>> Tcsr = depth_first_tree(X, 0, directed=False)
>>> Tcsr.toarray().astype(int)
array([[0, 8, 0, 0],
       [0, 0, 2, 0],
       [0, 0, 0, 6],
       [0, 0, 0, 0]])
```

Note that the resulting graph is a Directed Acyclic Graph which spans the graph. Unlike a breadth-first tree, a depth-first tree of a given graph is not unique if the graph contains cycles. If the above solution had begun with the edge connecting nodes 0 and 3, the result would have been different.

scipy.sparse.csgraph.minimum_spanning_tree

`scipy.sparse.csgraph.minimum_spanning_tree` (*csgraph*, *overwrite=False*)

Return a minimum spanning tree of an undirected graph

A minimum spanning tree is a graph consisting of the subset of edges which together connect all connected nodes, while minimizing the total sum of weights on the edges. This is computed using the Kruskal algorithm.

New in version 0.11.0.

Parameters

- csgraph** [array_like or sparse matrix, 2 dimensions] The N x N matrix representing an undirected graph over N nodes (see notes below).
- overwrite** [bool, optional] if true, then parts of the input graph will be overwritten for efficiency.

Returns

- span_tree** [csr matrix] The N x N compressed-sparse representation of the undirected minimum spanning tree over the input (see notes below).


Notes

This routine uses undirected graphs as input and output. That is, if `graph[i, j]` and `graph[j, i]` are both zero, then nodes `i` and `j` do not have an edge connecting them. If either is nonzero, then the two are connected by the minimum nonzero value of the two.

This routine loses precision when users input a dense matrix. Small elements $< 1E-8$ of the dense matrix are rounded to zero. All users should input sparse matrices if possible to avoid it.

Examples

The following example shows the computation of a minimum spanning tree over a simple four-component graph:



It is easy to see from inspection that the minimum spanning tree involves removing the edges with weights 8 and 6. In compressed sparse representation, the solution looks like this:

```

>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import minimum_spanning_tree
>>> X = csr_matrix([[0, 8, 0, 3],
...                [0, 0, 2, 5],
...                [0, 0, 0, 6],
...                [0, 0, 0, 0]])
>>> Tcsr = minimum_spanning_tree(X)
>>> Tcsr.toarray().astype(int)
array([[0, 0, 0, 3],
       [0, 0, 2, 5],
       [0, 0, 0, 0],
       [0, 0, 0, 0]])

```

scipy.sparse.csgraph.reverse_cuthill_mckee

scipy.sparse.csgraph.**reverse_cuthill_mckee** (*graph*, *symmetric_mode=False*)

Returns the permutation array that orders a sparse CSR or CSC matrix in Reverse-Cuthill McKee ordering.

It is assumed by default, *symmetric_mode=False*, that the input matrix is not symmetric and works on the matrix $A+A.T$. If you are guaranteed that the matrix is symmetric in structure (values of matrix elements do not matter) then set *symmetric_mode=True*.

Parameters

graph [sparse matrix] Input sparse in CSC or CSR sparse matrix format.
symmetric_mode [bool, optional] Is input matrix guaranteed to be symmetric.

Returns

perm [ndarray] Array of permuted row and column indices.

Notes

New in version 0.15.0.

References

E. Cuthill and J. McKee, "Reducing the Bandwidth of Sparse Symmetric Matrices", ACM '69 Proceedings of the 1969 24th national conference, (1969).

Examples

```

>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import reverse_cuthill_mckee

>>> graph = [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [2, 0, 0, 3],
... [0, 0, 0, 0]

```

(continues on next page)

(continued from previous page)

```
... ]
>>> graph = csr_matrix(graph)
>>> print(graph)
(0, 1) 1
(0, 2) 2
(1, 3) 1
(2, 0) 2
(2, 3) 3
```

```
>>> reverse_cuthill_mckee(graph)
array([3, 2, 1, 0], dtype=int32)
```

scipy.sparse.csgraph.maximum_flow

`scipy.sparse.csgraph.maximum_flow` (*csgraph*, *source*, *sink*)

Maximize the flow between two vertices in a graph.

New in version 1.4.0.

Parameters

csgraph [csr_matrix] The square matrix representing a directed graph whose (i, j)'th entry is an integer representing the capacity of the edge between vertices i and j.

source [int] The source vertex from which the flow flows.

sink [int] The sink vertex to which the flow flows.

Returns

res [MaximumFlowResult] A maximum flow represented by a `MaximumFlowResult` which includes the value of the flow in `flow_value`, and the residual graph in `residual`.

Raises

TypeError:
if the input graph is not in CSR format.

ValueError:
if the capacity values are not integers, or the source or sink are out of bounds.

Notes

This solves the maximum flow problem on a given directed weighted graph: A flow associates to every edge a value, also called a flow, less than the capacity of the edge, so that for every vertex (apart from the source and the sink vertices), the total incoming flow is equal to the total outgoing flow. The value of a flow is the sum of the flow of all edges leaving the source vertex, and the maximum flow problem consists of finding a flow whose value is maximal.

By the max-flow min-cut theorem, the maximal value of the flow is also the total weight of the edges in a minimum cut.

To solve the problem, we use the Edmonds–Karp algorithm. [1] This particular implementation strives to exploit sparsity. Its time complexity is $O(VE^2)$ and its space complexity is $O(E)$.

The maximum flow problem is usually defined with real valued capacities, but we require that all capacities are integral to ensure convergence. When dealing with rational capacities, or capacities belonging to $x\mathbb{Q}$ for some fixed $x \in \mathbb{R}$, it is possible to reduce the problem to the integral case by scaling all capacities accordingly.

Solving a maximum-flow problem can be used for example for graph cuts optimization in computer vision [3].

References

[1], [2], [3]

Examples

Perhaps the simplest flow problem is that of a graph of only two vertices with an edge from source (0) to sink (1):

```
(0) --5--> (1)
```

Here, the maximum flow is simply the capacity of the edge:

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import maximum_flow
>>> graph = csr_matrix([[0, 5], [0, 0]])
>>> maximum_flow(graph, 0, 1).flow_value
5
```

If, on the other hand, there is a bottleneck between source and sink, that can reduce the maximum flow:

```
(0) --5--> (1) --3--> (2)
```

```
>>> graph = csr_matrix([[0, 5, 0], [0, 0, 3], [0, 0, 0]])
>>> maximum_flow(graph, 0, 2).flow_value
3
```

A less trivial example is given in [2], Chapter 26.1:

```
>>> graph = csr_matrix([[0, 16, 13, 0, 0, 0],
...                    [0, 10, 0, 12, 0, 0],
...                    [0, 4, 0, 0, 14, 0],
...                    [0, 0, 9, 0, 0, 20],
...                    [0, 0, 0, 7, 0, 4],
...                    [0, 0, 0, 0, 0, 0]])
>>> maximum_flow(graph, 0, 5).flow_value
23
```

It is possible to reduce the problem of finding a maximum matching in a bipartite graph to a maximum flow problem: Let $G = ((U, V), E)$ be a bipartite graph. Then, add to the graph a source vertex with edges to every vertex in U and a sink vertex with edges from every vertex in V . Finally, give every edge in the resulting graph a capacity of 1. Then, a maximum flow in the new graph gives a maximum matching in the original graph consisting of the edges in E whose flow is positive.

Assume that the edges are represented by a $|U| \times |V|$ matrix in CSR format whose (i, j) 'th entry is 1 if there is an edge from $i \in U$ to $j \in V$ and 0 otherwise; that is, the input is of the form required by `maximum_bipartite_matching`. Then the CSR representation of the graph constructed above contains this matrix as a block. Here's an example:

```
>>> graph = csr_matrix([[0, 1, 0, 1], [1, 0, 1, 0], [0, 1, 1, 0]])
>>> print(graph.toarray())
[[0 1 0 1]
 [1 0 1 0]
 [0 1 1 0]]
```

(continues on next page)

(continued from previous page)

```

>>> i, j = graph.shape
>>> n = graph.nnz
>>> indptr = np.concatenate([[0],
...                          graph.indptr + i,
...                          np.arange(n + i + 1, n + i + j + 1),
...                          [n + i + j]])
>>> indices = np.concatenate([np.arange(1, i + 1),
...                            graph.indices + i + 1,
...                            np.repeat(i + j + 1, j)])
>>> data = np.ones(n + i + j, dtype=int)
>>>
>>> graph_flow = csr_matrix((data, indices, indptr))
>>> print(graph_flow.toarray())
[[0 1 1 1 0 0 0 0 0]
 [0 0 0 0 0 1 0 1 0]
 [0 0 0 0 1 0 1 0 0]
 [0 0 0 0 0 1 1 0 0]
 [0 0 0 0 0 0 0 0 1]
 [0 0 0 0 0 0 0 0 1]
 [0 0 0 0 0 0 0 0 1]
 [0 0 0 0 0 0 0 0 1]
 [0 0 0 0 0 0 0 0 1]
 [0 0 0 0 0 0 0 0 0]]

```

At this point, we can find the maximum flow between the added sink and the added source and the desired matching can be obtained by restricting the residual graph to the block corresponding to the original graph:

```

>>> flow = maximum_flow(graph_flow, 0, i+j+1)
>>> matching = flow.residual[1:i+1, i+1:i+j+1]
>>> print(matching.toarray())
[[0 1 0 0]
 [1 0 0 0]
 [0 0 1 0]]

```

This tells us that the first, second, and third vertex in U are matched with the second, first, and third vertex in V respectively.

While this solves the maximum bipartite matching problem in general, note that algorithms specialized to that problem, such as *maximum_bipartite_matching*, will generally perform better.

This approach can also be used to solve various common generalizations of the maximum bipartite matching problem. If, for instance, some vertices can be matched with more than one other vertex, this may be handled by modifying the capacities of the new graph appropriately.

scipy.sparse.csgraph.maximum_bipartite_matching

`scipy.sparse.csgraph.maximum_bipartite_matching` (*graph*, *perm_type*='row')

Returns a matching of a bipartite graph whose cardinality is as least that of any given matching of the graph.

Parameters

graph [sparse matrix] Input sparse in CSR format whose rows represent one partition of the graph and whose columns represent the other partition. An edge between two vertices is indicated by the corresponding entry in the matrix existing in its sparse representation.

perm_type

[str, {'row', 'column'}] Which partition to return the matching in terms of: If 'row', the function produces an array whose length is the number of columns in the input, and whose j 'th element is the row matched to the j 'th column. Conversely, if perm_type is 'column', this returns the columns matched to each row.

Returns

perm [ndarray] A matching of the vertices in one of the two partitions. Unmatched vertices are represented by a -1 in the result.

Notes

This function implements the Hopcroft–Karp algorithm [1]. Its time complexity is $O(|E|\sqrt{|V|})$, and its space complexity is linear in the number of rows. In practice, this asymmetry between rows and columns means that it can be more efficient to transpose the input if it contains more columns than rows.

By König's theorem, the cardinality of the matching is also the number of vertices appearing in a minimum vertex cover of the graph.

Note that if the sparse representation contains explicit zeros, these are still counted as edges.

The implementation was changed in SciPy 1.4.0 to allow matching of general bipartite graphs, where previous versions would assume that a perfect matching existed. As such, code written against 1.4.0 will not necessarily work on older versions.

References

[1]

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import maximum_bipartite_matching
```

As a simple example, consider a bipartite graph in which the partitions contain 2 and 3 elements respectively. Suppose that one partition contains vertices labelled 0 and 1, and that the other partition contains vertices labelled A, B, and C. Suppose that there are edges connecting 0 and C, 1 and A, and 1 and B. This graph would then be represented by the following sparse matrix:

```
>>> graph = csr_matrix([[0, 0, 1], [1, 1, 0]])
```

Here, the 1s could be anything, as long as they end up being stored as elements in the sparse matrix. We can now calculate maximum matchings as follows:

```
>>> print(maximum_bipartite_matching(graph, perm_type='column'))
[2 0]
>>> print(maximum_bipartite_matching(graph, perm_type='row'))
[ 1 -1  0]
```

The first output tells us that 1 and 2 are matched with C and A respectively, and the second output tells us that A, B, and C are matched with 1, nothing, and 0 respectively.

Note that explicit zeros are still converted to edges. This means that a different way to represent the above graph is by using the CSR structure directly as follows:

```

>>> data = [0, 0, 0]
>>> indices = [2, 0, 1]
>>> indptr = [0, 1, 3]
>>> graph = csr_matrix((data, indices, indptr))
>>> print(maximum_bipartite_matching(graph, perm_type='column'))
[2 0]
>>> print(maximum_bipartite_matching(graph, perm_type='row'))
[ 1 -1  0]

```

When one or both of the partitions are empty, the matching is empty as well:

```

>>> graph = csr_matrix((2, 0))
>>> print(maximum_bipartite_matching(graph, perm_type='column'))
[-1 -1]
>>> print(maximum_bipartite_matching(graph, perm_type='row'))
[]

```

When the input matrix is square, and the graph is known to admit a perfect matching, i.e. a matching with the property that every vertex in the graph belongs to some edge in the matching, then one can view the output as the permutation of rows (or columns) turning the input matrix into one with the property that all diagonal elements are non-empty:

```

>>> a = [[0, 1, 2, 0], [1, 0, 0, 1], [2, 0, 0, 3], [0, 1, 3, 0]]
>>> graph = csr_matrix(a)
>>> perm = maximum_bipartite_matching(graph, perm_type='row')
>>> print(graph[perm].toarray())
[[1 0 0 1]
 [0 1 2 0]
 [0 1 3 0]
 [2 0 0 3]]

```

scipy.sparse.csgraph.min_weight_full_bipartite_matching

`scipy.sparse.csgraph.min_weight_full_bipartite_matching` (*biadjacency_matrix*, *maximize=False*)

Returns the minimum weight full matching of a bipartite graph.

New in version 1.6.0.

Parameters

biadjacency_matrix

[sparse matrix] Biadjacency matrix of the bipartite graph: A sparse matrix in CSR, CSC, or COO format whose rows represent one partition of the graph and whose columns represent the other partition. An edge between two vertices is indicated by the corresponding entry in the matrix, and the weight of the edge is given by the value of that entry. This should not be confused with the full adjacency matrix of the graph, as we only need the submatrix defining the bipartite structure.

maximize [bool (default: False)] Calculates a maximum weight matching if true.

Returns

row_ind, col_ind

[array] An array of row indices and one of corresponding column indices giving the optimal matching. The total weight of the matching can be computed as `graph[row_ind,`

`col_ind].sum()`. The row indices will be sorted; in the case of a square matrix they will be equal to `numpy.arange(graph.shape[0])`.

Notes

Let $G = ((U, V), E)$ be a weighted bipartite graph with non-zero weights $w : E \rightarrow \mathbb{R} \setminus \{0\}$. This function then produces a matching $M \subseteq E$ with cardinality

$$|M| = \min(|U|, |V|),$$

which minimizes the sum of the weights of the edges included in the matching, $\sum_{e \in M} w(e)$, or raises an error if no such matching exists.

When $|U| = |V|$, this is commonly referred to as a perfect matching; here, since we allow $|U|$ and $|V|$ to differ, we follow Karp [1] and refer to the matching as *full*.

This function implements the LAPJVsp algorithm [2], short for “Linear assignment problem, Jonker–Volgenant, sparse”.

The problem it solves is equivalent to the rectangular linear assignment problem. [3] As such, this function can be used to solve the same problems as `scipy.optimize.linear_sum_assignment`. That function may perform better when the input is dense, or for certain particular types of inputs, such as those for which the (i, j) ’th entry is the distance between two points in Euclidean space.

If no full matching exists, this function raises a `ValueError`. For determining the size of the largest matching in the graph, see `maximum_bipartite_matching`.

We require that weights are non-zero only to avoid issues with the handling of explicit zeros when converting between different sparse representations. Zero weights can be handled by adding a constant to all weights, so that the resulting matrix contains no zeros.

References

[1], [2], [3]

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import min_weight_full_bipartite_matching
```

Let us first consider an example in which all weights are equal:

```
>>> biadjacency_matrix = csr_matrix([[1, 1, 1], [1, 0, 0], [0, 1, 0]])
```

Here, all we get is a perfect matching of the graph:

```
>>> print(min_weight_full_bipartite_matching(biadjacency_matrix)[1])
[2 0 1]
```

That is, the first, second, and third rows are matched with the third, first, and second column respectively. Note that in this example, the 0 in the input matrix does *not* correspond to an edge with weight 0, but rather a pair of vertices not paired by an edge.

Note also that in this case, the output matches the result of applying `maximum_bipartite_matching`:

```
>>> from scipy.sparse.csgraph import maximum_bipartite_matching
>>> biadjacency = csr_matrix([[1, 1, 1], [1, 0, 0], [0, 1, 0]])
>>> print(maximum_bipartite_matching(biadjacency, perm_type='column'))
[2 0 1]
```

When multiple edges are available, the ones with lowest weights are preferred:

```
>>> biadjacency = csr_matrix([[3, 3, 6], [4, 3, 5], [10, 1, 8]])
>>> row_ind, col_ind = min_weight_full_bipartite_matching(biadjacency)
>>> print(col_ind)
[0 2 1]
```

The total weight in this case is $3 + 5 + 1 = 9$:

```
>>> print(biadjacency[row_ind, col_ind].sum())
9
```

When the matrix is not square, i.e. when the two partitions have different cardinalities, the matching is as large as the smaller of the two partitions:

```
>>> biadjacency = csr_matrix([[0, 1, 1], [0, 2, 3]])
>>> row_ind, col_ind = min_weight_full_bipartite_matching(biadjacency)
>>> print(row_ind, col_ind)
[0 1] [2 1]
>>> biadjacency = csr_matrix([[0, 1], [3, 1], [1, 4]])
>>> row_ind, col_ind = min_weight_full_bipartite_matching(biadjacency)
>>> print(row_ind, col_ind)
[0 2] [1 0]
```

When one or both of the partitions are empty, the matching is empty as well:

```
>>> biadjacency = csr_matrix((2, 0))
>>> row_ind, col_ind = min_weight_full_bipartite_matching(biadjacency)
>>> print(row_ind, col_ind)
[] []
```

In general, we will always reach the same sum of weights as if we had used `scipy.optimize.linear_sum_assignment` but note that for that one, missing edges are represented by a matrix entry of `float('inf')`. Let us generate a random sparse matrix with integer entries between 1 and 10:

```
>>> import numpy as np
>>> from scipy.sparse import random
>>> from scipy.optimize import linear_sum_assignment
>>> sparse = random(10, 10, random_state=42, density=.5, format='coo') * 10
>>> sparse.data = np.ceil(sparse.data)
>>> dense = sparse.toarray()
>>> dense = np.full(sparse.shape, np.inf)
>>> dense[sparse.row, sparse.col] = sparse.data
>>> sparse = sparse.tocsr()
>>> row_ind, col_ind = linear_sum_assignment(dense)
>>> print(dense[row_ind, col_ind].sum())
28.0
>>> row_ind, col_ind = min_weight_full_bipartite_matching(sparse)
```

(continues on next page)

(continued from previous page)

```
>>> print(sparse[row_ind, col_ind].sum())
28.0
```

scipy.sparse.csgraph.structural_rank

scipy.sparse.csgraph.**structural_rank**(*graph*)

Compute the structural rank of a graph (matrix) with a given sparsity pattern.

The structural rank of a matrix is the number of entries in the maximum transversal of the corresponding bipartite graph, and is an upper bound on the numerical rank of the matrix. A graph has full structural rank if it is possible to permute the elements to make the diagonal zero-free.

New in version 0.19.0.

Parameters

graph [sparse matrix] Input sparse matrix.

Returns

rank [int] The structural rank of the sparse graph.

References

[1], [2]

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import structural_rank
```

```
>>> graph = [
... [0, 1, 2, 0],
... [1, 0, 0, 1],
... [2, 0, 0, 3],
... [0, 1, 3, 0]
... ]
>>> graph = csr_matrix(graph)
>>> print(graph)
(0, 1) 1
(0, 2) 2
(1, 0) 1
(1, 3) 1
(2, 0) 2
(2, 3) 3
(3, 1) 1
(3, 2) 3
```

```
>>> structural_rank(graph)
4
```

scipy.sparse.csgraph.NegativeCycleError

exception `scipy.sparse.csgraph.NegativeCycleError` (*message=""*)

with_traceback()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

<code>construct_dist_matrix</code> (graph, predecessors[, ...])	Construct distance matrix from a predecessor matrix
<code>csgraph_from_dense</code> (graph[, null_value, ...])	Construct a CSR-format sparse graph from a dense matrix.
<code>csgraph_from_masked</code> (graph)	Construct a CSR-format graph from a masked array.
<code>csgraph_masked_from_dense</code> (graph[, ...])	Construct a masked array graph representation from a dense matrix.
<code>csgraph_to_dense</code> (csgraph[, null_value])	Convert a sparse graph representation to a dense representation
<code>csgraph_to_masked</code> (csgraph)	Convert a sparse graph representation to a masked array representation
<code>reconstruct_path</code> (csgraph, predecessors[, ...])	Construct a tree from a graph and a predecessor list.

scipy.sparse.csgraph.construct_dist_matrix

`scipy.sparse.csgraph.construct_dist_matrix` (*graph*, *predecessors*, *directed=True*, *null_value=np.inf*)

Construct distance matrix from a predecessor matrix

New in version 0.11.0.

Parameters

- graph** [array_like or sparse] The N x N matrix representation of a directed or undirected graph. If dense, then non-edges are indicated by zeros or infinities.
- predecessors** [array_like] The N x N matrix of predecessors of each node (see Notes below).
- directed** [bool, optional] If True (default), then operate on a directed graph: only move from point i to point j along paths `csgraph[i, j]`. If False, then operate on an undirected graph: the algorithm can progress from point i to j along `csgraph[i, j]` or `csgraph[j, i]`.
- null_value** [bool, optional] value to use for distances between unconnected nodes. Default is `np.inf`

Returns

- dist_matrix** [ndarray] The N x N matrix of distances between nodes along the path specified by the predecessor matrix. If no path exists, the distance is zero.

Notes

The predecessor matrix is of the form returned by `shortest_path`. Row i of the predecessor matrix contains information on the shortest paths from point i : each entry `predecessors[i, j]` gives the index of the previous node in the path from point i to point j . If no path exists between point i and j , then `predecessors[i, j] = -9999`

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import construct_dist_matrix
```

```
>>> graph = [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [0, 0, 0, 3],
... [0, 0, 0, 0]
... ]
>>> graph = csr_matrix(graph)
>>> print(graph)
(0, 1) 1
(0, 2) 2
(1, 3) 1
(2, 3) 3
```

```
>>> pred = np.array([[ -9999, 0, 0, 2],
... [1, -9999, 0, 1],
... [2, 0, -9999, 2],
... [1, 3, 3, -9999]]), dtype=np.int32)
```

```
>>> construct_dist_matrix(graph=graph, predecessors=pred, directed=False)
array([[ 0., 1., 2., 5.],
       [ 1., 0., 3., 1.],
       [ 2., 3., 0., 3.],
       [ 2., 1., 3., 0.]])
```

scipy.sparse.csgraph.csgraph_from_dense

`scipy.sparse.csgraph.csgraph_from_dense` (*graph*, *null_value=0*, *nan_null=True*, *infinity_null=True*)

Construct a CSR-format sparse graph from a dense matrix.

New in version 0.11.0.

Parameters

- graph** [array_like] Input graph. Shape should be (n_nodes, n_nodes).
- null_value** [float or None (optional)] Value that denotes non-edges in the graph. Default is zero.
- infinity_null** [bool] If True (default), then infinite entries (both positive and negative) are treated as null edges.
- nan_null** [bool] If True (default), then NaN entries are treated as non-edges

Returns

csgraph [csr_matrix] Compressed sparse representation of graph,

Examples

```
>>> from scipy.sparse.csgraph import csgraph_from_dense
```

```
>>> graph = [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [0, 0, 0, 3],
... [0, 0, 0, 0]
... ]
```

```
>>> csgraph_from_dense(graph)
<4x4 sparse matrix of type '<class 'numpy.float64''>'
with 4 stored elements in Compressed Sparse Row format>
```

scipy.sparse.csgraph.csgraph_from_masked

scipy.sparse.csgraph.**csgraph_from_masked**(*graph*)

Construct a CSR-format graph from a masked array.

New in version 0.11.0.

Parameters

graph [MaskedArray] Input graph. Shape should be (n_nodes, n_nodes).

Returns

csgraph [csr_matrix] Compressed sparse representation of graph,

Examples

```
>>> import numpy as np
>>> from scipy.sparse.csgraph import csgraph_from_masked
```

```
>>> graph_masked = np.ma.masked_array(data = [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [0, 0, 0, 3],
... [0, 0, 0, 0]
... ],
... mask=[[ True, False, False, True],
... [ True, True, True, False],
... [ True, True, True, False],
... [ True, True, True, True]],
... fill_value = 0)
```

```
>>> csgraph_from_masked(graph_masked)
<4x4 sparse matrix of type '<class 'numpy.float64''>'
with 4 stored elements in Compressed Sparse Row format>
```

scipy.sparse.csgraph.csgraph_masked_from_dense

`scipy.sparse.csgraph.csgraph_masked_from_dense` (*graph*, *null_value=0*, *nan_null=True*, *infinity_null=True*, *copy=True*)

Construct a masked array graph representation from a dense matrix.

New in version 0.11.0.

Parameters

- graph** [array_like] Input graph. Shape should be (n_nodes, n_nodes).
- null_value** [float or None (optional)] Value that denotes non-edges in the graph. Default is zero.
- infinity_null** [bool] If True (default), then infinite entries (both positive and negative) are treated as null edges.
- nan_null** [bool] If True (default), then NaN entries are treated as non-edges

Returns

- csgraph** [MaskedArray] masked array representation of graph

Examples

```
>>> from scipy.sparse.csgraph import csgraph_masked_from_dense
```

```
>>> graph = [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [0, 0, 0, 3],
... [0, 0, 0, 0]
... ]
```

```
>>> csgraph_masked_from_dense(graph)
masked_array(
  data=[[--, 1, 2, --],
        [--, --, --, 1],
        [--, --, --, 3],
        [--, --, --, --]],
  mask=[[ True, False, False,  True],
        [ True,  True,  True, False],
        [ True,  True,  True, False],
        [ True,  True,  True,  True]],
  fill_value=0)
```

scipy.sparse.csgraph.csgraph_to_dense

`scipy.sparse.csgraph.csgraph_to_dense` (*csgraph*, *null_value=0*)

Convert a sparse graph representation to a dense representation

New in version 0.11.0.

Parameters

- csgraph** [csr_matrix, csc_matrix, or lil_matrix] Sparse representation of a graph.

null_value [float, optional] The value used to indicate null edges in the dense representation. Default is 0.

Returns

graph [ndarray] The dense representation of the sparse graph.

Notes

For normal sparse graph representations, calling `csgraph_to_dense` with `null_value=0` produces an equivalent result to using dense format conversions in the main sparse package. When the sparse representations have repeated values, however, the results will differ. The tools in `scipy.sparse` will add repeating values to obtain a final value. This function will select the minimum among repeating values to obtain a final value. For example, here we'll create a two-node directed sparse graph with multiple edges from node 0 to node 1, of weights 2 and 3. This illustrates the difference in behavior:

```
>>> from scipy.sparse import csr_matrix, csgraph
>>> data = np.array([2, 3])
>>> indices = np.array([1, 1])
>>> indptr = np.array([0, 2, 2])
>>> M = csr_matrix((data, indices, indptr), shape=(2, 2))
>>> M.toarray()
array([[0, 5],
       [0, 0]])
>>> csgraph.csgraph_to_dense(M)
array([[0., 2.],
       [0., 0.]])
```

The reason for this difference is to allow a compressed sparse graph to represent multiple edges between any two nodes. As most sparse graph algorithms are concerned with the single lowest-cost edge between any two nodes, the default `scipy.sparse` behavior of summing multiple weights does not make sense in this context.

The other reason for using this routine is to allow for graphs with zero-weight edges. Let's look at the example of a two-node directed graph, connected by an edge of weight zero:

```
>>> from scipy.sparse import csr_matrix, csgraph
>>> data = np.array([0.0])
>>> indices = np.array([1])
>>> indptr = np.array([0, 1, 1])
>>> M = csr_matrix((data, indices, indptr), shape=(2, 2))
>>> M.toarray()
array([[0, 0],
       [0, 0]])
>>> csgraph.csgraph_to_dense(M, np.inf)
array([[ inf,  0.],
       [ inf,  inf]])
```

In the first case, the zero-weight edge gets lost in the dense representation. In the second case, we can choose a different null value and see the true form of the graph.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import csgraph_to_dense
```

```
>>> graph = csr_matrix( [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [0, 0, 0, 3],
... [0, 0, 0, 0]
... ])
>>> graph
<4x4 sparse matrix of type '<class 'numpy.int64''>'
  with 4 stored elements in Compressed Sparse Row format>
```

```
>>> csgraph_to_dense(graph)
array([[ 0.,  1.,  2.,  0.],
       [ 0.,  0.,  0.,  1.],
       [ 0.,  0.,  0.,  3.],
       [ 0.,  0.,  0.,  0.]])
```

scipy.sparse.csgraph.csgraph_to_masked

`scipy.sparse.csgraph.csgraph_to_masked(csgraph)`

Convert a sparse graph representation to a masked array representation

New in version 0.11.0.

Parameters

csgraph [csr_matrix, csc_matrix, or lil_matrix] Sparse representation of a graph.

Returns

graph [MaskedArray] The masked dense representation of the sparse graph.

Examples

```
>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import csgraph_to_masked
```

```
>>> graph = csr_matrix( [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [0, 0, 0, 3],
... [0, 0, 0, 0]
... ])
>>> graph
<4x4 sparse matrix of type '<class 'numpy.int64''>'
  with 4 stored elements in Compressed Sparse Row format>
```

```

>>> csgraph_to_masked(graph)
masked_array(
  data=[[--, 1.0, 2.0, --],
        [--, --, --, 1.0],
        [--, --, --, 3.0],
        [--, --, --, --]],
  mask=[[ True, False, False,  True],
        [ True,  True,  True, False],
        [ True,  True,  True, False],
        [ True,  True,  True,  True]],
  fill_value=1e+20)

```

scipy.sparse.csgraph.reconstruct_path

`scipy.sparse.csgraph.reconstruct_path` (*csgraph*, *predecessors*, *directed=True*)

Construct a tree from a graph and a predecessor list.

New in version 0.11.0.

Parameters

csgraph [array_like or sparse matrix] The N x N matrix representing the directed or undirected graph from which the predecessors are drawn.

predecessors [array_like, one dimension] The length-N array of indices of predecessors for the tree. The index of the parent of node *i* is given by `predecessors[i]`.

directed [bool, optional] If True (default), then operate on a directed graph: only move from point *i* to point *j* along paths `csgraph[i, j]`. If False, then operate on an undirected graph: the algorithm can progress from point *i* to *j* along `csgraph[i, j]` or `csgraph[j, i]`.

Returns

cstree [csr matrix] The N x N directed compressed-sparse representation of the tree drawn from `csgraph` which is encoded by the predecessor list.

Examples

```

>>> from scipy.sparse import csr_matrix
>>> from scipy.sparse.csgraph import reconstruct_path

```

```

>>> graph = [
... [0, 1, 2, 0],
... [0, 0, 0, 1],
... [0, 0, 0, 3],
... [0, 0, 0, 0]
... ]
>>> graph = csr_matrix(graph)
>>> print(graph)
(0, 1)    1
(0, 2)    2
(1, 3)    1
(2, 3)    3

```

```
>>> pred = np.array([-9999, 0, 0, 1], dtype=np.int32)
```

```
>>> cstree = reconstruct_path(csgraph=graph, predecessors=pred,
↳directed=False)
>>> cstree.todense()
matrix([[ 0.,  1.,  2.,  0.],
        [ 0.,  0.,  0.,  1.],
        [ 0.,  0.,  0.,  0.],
        [ 0.,  0.,  0.,  0.]])
```

6.25.2 Graph Representations

This module uses graphs which are stored in a matrix format. A graph with N nodes can be represented by an $(N \times N)$ adjacency matrix G . If there is a connection from node i to node j , then $G[i, j] = w$, where w is the weight of the connection. For nodes i and j which are not connected, the value depends on the representation:

- for dense array representations, non-edges are represented by $G[i, j] = 0$, infinity, or NaN.
- for dense masked representations (of type `np.ma.MaskedArray`), non-edges are represented by masked values. This can be useful when graphs with zero-weight edges are desired.
- for sparse array representations, non-edges are represented by non-entries in the matrix. This sort of sparse representation also allows for edges with zero weights.


As a concrete example, imagine that you would like to represent the following undirected graph:



This graph has three nodes, where node 0 and 1 are connected by an edge of weight 2, and nodes 0 and 2 are connected by an edge of weight 1. We can construct the dense, masked, and sparse representations as follows, keeping in mind that an undirected graph is represented by a symmetric matrix:

```
>>> G_dense = np.array([[0, 2, 1],
...                    [2, 0, 0],
...                    [1, 0, 0]])
>>> G_masked = np.ma.masked_values(G_dense, 0)
>>> from scipy.sparse import csr_matrix
>>> G_sparse = csr_matrix(G_dense)
```

This becomes more difficult when zero edges are significant. For example, consider the situation when we slightly modify the above graph:



(continues on next page)

(continued from previous page)

```

/      \
(2)      (1)

```

This is identical to the previous graph, except nodes 0 and 2 are connected by an edge of zero weight. In this case, the dense representation above leads to ambiguities: how can non-edges be represented if zero is a meaningful value? In this case, either a masked or sparse representation must be used to eliminate the ambiguity:

```

>>> G2_data = np.array([[np.inf, 2,      0      ],
...                    [2,      np.inf, np.inf],
...                    [0,      np.inf, np.inf]])
>>> G2_masked = np.ma.masked_invalid(G2_data)
>>> from scipy.sparse.csgraph import csgraph_from_dense
>>> # G2_sparse = csr_matrix(G2_data) would give the wrong result
>>> G2_sparse = csgraph_from_dense(G2_data, null_value=np.inf)
>>> G2_sparse.data
array([ 2.,  0.,  2.,  0.])

```

Here we have used a utility routine from the `csgraph` submodule in order to convert the dense representation to a sparse representation which can be understood by the algorithms in submodule. By viewing the data array, we can see that the zero values are explicitly encoded in the graph.

Directed vs. undirected

Matrices may represent either directed or undirected graphs. This is specified throughout the `csgraph` module by a boolean keyword. Graphs are assumed to be directed by default. In a directed graph, traversal from node i to node j can be accomplished over the edge $G[i, j]$, but not the edge $G[j, i]$. Consider the following dense graph:

```

>>> G_dense = np.array([[0, 1, 0],
...                    [2, 0, 3],
...                    [0, 4, 0]])

```

When `directed=True` we get the graph:

```

  ---1-->  ---3-->
(0)      (1)      (2)
<--2---  <--4---

```

In a non-directed graph, traversal from node i to node j can be accomplished over either $G[i, j]$ or $G[j, i]$. If both edges are not null, and the two have unequal weights, then the smaller of the two is used.

So for the same graph, when `directed=False` we get the graph:

```

(0) --1-- (1) --2-- (2)

```

Note that a symmetric matrix will represent an undirected graph, regardless of whether the ‘directed’ keyword is set to True or False. In this case, using `directed=True` generally leads to more efficient computation.

The routines in this module accept as input either `scipy.sparse` representations (`csr`, `csc`, or `lil` format), masked representations, or dense representations with non-edges indicated by zeros, infinities, and NaN entries.

6.26 Spatial algorithms and data structures (`scipy.spatial`)

6.26.1 Spatial transformations

These are contained in the `scipy.spatial.transform` submodule.

6.26.2 Nearest-neighbor queries

<code>KDTree</code> (data[, leafsize, compact_nodes, ...])	kd-tree for quick nearest-neighbor lookup
<code>cKDTree</code> (data[, leafsize, compact_nodes, ...])	kd-tree for quick nearest-neighbor lookup
<code>Rectangle</code> (maxes, mins)	Hyperrectangle class.

`scipy.spatial.KDTree`

class `scipy.spatial.KDTree`(data, leafsize=10, compact_nodes=True, copy_data=False, balanced_tree=True, boxsize=None)
kd-tree for quick nearest-neighbor lookup

This class provides an index into a set of k-dimensional points which can be used to rapidly look up the nearest neighbors of any point.

Parameters

- data** [array_like, shape (n,m)] The n data points of dimension m to be indexed. This array is not copied unless this is necessary to produce a contiguous array of doubles, and so modifying this data will result in bogus results. The data are also copied if the kd-tree is built with `copy_data=True`.
- leafsize** [positive int, optional] The number of points at which the algorithm switches over to brute-force. Default: 10.
- compact_nodes** [bool, optional] If True, the kd-tree is built to shrink the hyperrectangles to the actual data range. This usually gives a more compact tree that is robust against degenerated input data and gives faster queries at the expense of longer build time. Default: True.
- copy_data** [bool, optional] If True the data is always copied to protect the kd-tree against data corruption. Default: False.
- balanced_tree** [bool, optional] If True, the median is used to split the hyperrectangles instead of the midpoint. This usually gives a more compact tree and faster queries at the expense of longer build time. Default: True.
- boxsize** [array_like or scalar, optional] Apply a m-d toroidal topology to the KDTree.. The topology is generated by $x_i + n_i L_i$ where n_i are integers and L_i is the boxsize along i-th dimension. The input data shall be wrapped into $[0, L_i)$. A `ValueError` is raised if any of the data is outside of this bound.

Notes

The algorithm used is described in Maneewongvatana and Mount 1999. The general idea is that the kd-tree is a binary tree, each of whose nodes represents an axis-aligned hyperrectangle. Each node specifies an axis and splits the set of points based on whether their coordinate along that axis is greater than or less than a particular value.

During construction, the axis and splitting point are chosen by the “sliding midpoint” rule, which ensures that the cells do not all become long and thin.

The tree can be queried for the r closest neighbors of any given point (optionally returning only those within some maximum distance of the point). It can also be queried, with a substantial gain in efficiency, for the r approximate closest neighbors.

For large dimensions (20 is already large) do not expect this to run significantly faster than brute force. High-dimensional nearest-neighbor queries are a substantial open problem in computer science.

Attributes

data	[ndarray, shape (n,m)] The n data points of dimension m to be indexed. This array is not copied unless this is necessary to produce a contiguous array of doubles. The data are also copied if the kd-tree is built with <code>copy_data=True</code> .
leafsize	[positive int] The number of points at which the algorithm switches over to brute-force.
m	[int] The dimension of a single data-point.
n	[int] The number of data points.
maxes	[ndarray, shape (m,)] The maximum value in each dimension of the n data points.
mins	[ndarray, shape (m,)] The minimum value in each dimension of the n data points.
size	[int] The number of nodes in the tree.

Methods

<code>count_neighbors(self, other, r[, p, ...])</code>	Count how many nearby pairs can be formed.
<code>query(self, x[, k, eps, p, ...])</code>	Query the kd-tree for nearest neighbors
<code>query_ball_point(self, x, r[, p, eps, ...])</code>	Find all points within distance r of point(s) x .
<code>query_ball_tree(self, other, r[, p, eps])</code>	Find all pairs of points between <i>self</i> and <i>other</i> whose distance is at most r
<code>query_pairs(self, r[, p, eps, output_type])</code>	Find all pairs of points in <i>self</i> whose distance is at most r .
<code>sparse_distance_matrix(self, other, max_distance)</code>	Compute a sparse distance matrix

scipy.spatial.KDTree.count_neighbors

`KDTree.count_neighbors(self, other, r, p=2.0, weights=None, cumulative=True)`

Count how many nearby pairs can be formed.

Count the number of pairs (x_1, x_2) can be formed, with x_1 drawn from *self* and x_2 drawn from *other*, and where $\text{distance}(x_1, x_2, p) \leq r$.

Data points on *self* and *other* are optionally weighted by the `weights` argument. (See below)

This is adapted from the “two-point correlation” algorithm described by Gray and Moore [1]. See notes for further discussion.

Parameters

other [KDTree] The other tree to draw points from, can be the same tree as *self*.

- r** [float or one-dimensional array of floats] The radius to produce a count for. Multiple radii are searched with a single tree traversal. If the count is non-cumulative (`cumulative=False`), `r` defines the edges of the bins, and must be non-decreasing.
- p** [float, optional] $1 \leq p \leq \text{infinity}$. Which Minkowski p -norm to use. Default 2.0. A finite large p may cause a `ValueError` if overflow can occur.
- weights** [tuple, array_like, or None, optional] If None, the pair-counting is unweighted. If given as a tuple, `weights[0]` is the weights of points in `self`, and `weights[1]` is the weights of points in `other`; either can be None to indicate the points are unweighted. If given as an array_like, `weights` is the weights of points in `self` and `other`. For this to make sense, `self` and `other` must be the same tree. If `self` and `other` are two different trees, a `ValueError` is raised. Default: None
New in version 1.6.0.
- cumulative** [bool, optional] Whether the returned counts are cumulative. When `cumulative` is set to `False` the algorithm is optimized to work with a large number of bins (>10) specified by `r`. When `cumulative` is set to `True`, the algorithm is optimized to work with a small number of `r`. Default: `True`
New in version 1.6.0.

Returns

- result** [scalar or 1-D array] The number of pairs. For unweighted counts, the result is integer. For weighted counts, the result is float. If `cumulative` is `False`, `result[i]` contains the counts with $(-\text{inf} \text{ if } i == 0 \text{ else } r[i-1]) < R \leq r[i]$

Notes

Pair-counting is the basic operation used to calculate the two point correlation functions from a data set composed of position of objects.

Two point correlation function measures the clustering of objects and is widely used in cosmology to quantify the large scale structure in our Universe, but it may be useful for data analysis in other fields where self-similar assembly of objects also occur.

The Landy-Szalay estimator for the two point correlation function of D measures the clustering signal in D . [2]

For example, given the position of two sets of objects,

- objects D (data) contains the clustering signal, and
- objects R (random) that contains no signal,

$$\xi(r) = \frac{\langle D, D \rangle - 2f \langle D, R \rangle + f^2 \langle R, R \rangle}{f^2 \langle R, R \rangle},$$

where the brackets represents counting pairs between two data sets in a finite bin around r (distance), corresponding to setting `cumulative=False`, and $f = \text{float}(\text{len}(D)) / \text{float}(\text{len}(R))$ is the ratio between number of objects from data and random.

The algorithm implemented here is loosely based on the dual-tree algorithm described in [1]. We switch between two different pair-cumulation scheme depending on the setting of `cumulative`. The computing time of the method we use when for `cumulative == False` does not scale with the total number of bins. The algorithm for `cumulative == True` scales linearly with the number of bins, though it is slightly faster when only 1 or 2 bins are used. [5].

As an extension to the naive pair-counting, weighted pair-counting counts the product of weights instead of number of pairs. Weighted pair-counting is used to estimate marked correlation functions ([3], section 2.2), or to properly calculate the average of data per distance bin (e.g. [4], section 2.1 on redshift).

Examples

You can count neighbors number between two kd-trees within a distance:

```
>>> import numpy as np
>>> from scipy.spatial import KDTree
>>> np.random.seed(21701)
>>> points1 = np.random.random((5, 2))
>>> points2 = np.random.random((5, 2))
>>> kd_tree1 = KDTree(points1)
>>> kd_tree2 = KDTree(points2)
>>> kd_tree1.count_neighbors(kd_tree2, 0.2)
9
```

This number is same as the total pair number calculated by `query_ball_tree`:

```
>>> indexes = kd_tree1.query_ball_tree(kd_tree2, r=0.2)
>>> sum([len(i) for i in indexes])
9
```

scipy.spatial.KDTree.query

`KDTree.query` (*self*, *x*, *k=1*, *eps=0*, *p=2*, *distance_upper_bound=inf*, *workers=1*)

Query the kd-tree for nearest neighbors

Parameters

- x** [array_like, last dimension self.m] An array of points to query.
- k** [int or Sequence[int], optional] Either the number of nearest neighbors to return, or a list of the k-th nearest neighbors to return, starting from 1.
- eps** [nonnegative float, optional] Return approximate nearest neighbors; the kth returned value is guaranteed to be no further than (1+eps) times the distance to the real kth nearest neighbor.
- p** [float, 1<=p<=infinity, optional] Which Minkowski p-norm to use. 1 is the sum-of-absolute-values “Manhattan” distance 2 is the usual Euclidean distance infinity is the maximum-coordinate-difference distance A large, finite p may cause a ValueError if overflow can occur.
- distance_upper_bound** [nonnegative float, optional] Return only neighbors within this distance. This is used to prune tree searches, so if you are doing a series of nearest-neighbor queries, it may help to supply the distance to the nearest neighbor of the most recent point.
- workers** [int, optional] Number of workers to use for parallel processing. If -1 is given all CPU threads are used. Default: 1.
New in version 1.6.0.

Returns

- d** [float or array of floats] The distances to the nearest neighbors. If *x* has shape `tuple+(self.m,)`, then *d* has shape `tuple+(k,)`. When *k* == 1, the last dimension of the output is squeezed. Missing neighbors are indicated with infinite distances. Hits are sorted by distance (nearest first).

Deprecated since version 1.6.0: If `k=None`, then `d` is an object array of shape `tuple`, containing lists of distances. This behavior is deprecated and will be removed in SciPy 1.8.0, use `query_ball_point` instead.

`i` [integer or array of integers] The index of each neighbor in `self.data`. `i` is the same shape as `d`. Missing neighbors are indicated with `self.n`.

Examples

```
>>> import numpy as np
>>> from scipy.spatial import KDTree
>>> x, y = np.mgrid[0:5, 2:8]
>>> tree = KDTree(np.c_[x.ravel(), y.ravel()])
```

To query the nearest neighbours and return squeezed result, use

```
>>> dd, ii = tree.query([[0, 0], [2.1, 2.9]], k=1)
>>> print(dd, ii)
[2.          0.14142136] [ 0 13]
```

To query the nearest neighbours and return unsqueezed result, use

```
>>> dd, ii = tree.query([[0, 0], [2.1, 2.9]], k=[1])
>>> print(dd, ii)
[[2.          ]
 [0.14142136]] [[ 0]
 [13]]
```

To query the second nearest neighbours and return unsqueezed result, use

```
>>> dd, ii = tree.query([[0, 0], [2.1, 2.9]], k=[2])
>>> print(dd, ii)
[[2.23606798]
 [0.90553851]] [[ 6]
 [12]]
```

To query the first and second nearest neighbours, use

```
>>> dd, ii = tree.query([[0, 0], [2.1, 2.9]], k=2)
>>> print(dd, ii)
[[2.          2.23606798]
 [0.14142136 0.90553851]] [[ 0  6]
 [13 12]]
```

or, be more specific

```
>>> dd, ii = tree.query([[0, 0], [2.1, 2.9]], k=[1, 2])
>>> print(dd, ii)
[[2.          2.23606798]
 [0.14142136 0.90553851]] [[ 0  6]
 [13 12]]
```

scipy.spatial.KDTree.query_ball_point

`KDTree.query_ball_point` (*self*, *x*, *r*, *p=2.0*, *eps=0*, *workers=1*, *return_sorted=None*, *return_length=False*)

Find all points within distance *r* of point(s) *x*.

Parameters

- x** [array_like, shape tuple + (self.m,)] The point or points to search for neighbors of.
- r** [array_like, float] The radius of points to return, must broadcast to the length of *x*.
- p** [float, optional] Which Minkowski *p*-norm to use. Should be in the range [1, inf]. A finite large *p* may cause a `ValueError` if overflow can occur.
- eps** [nonnegative float, optional] Approximate search. Branches of the tree are not explored if their nearest points are further than $r / (1 + \text{eps})$, and branches are added in bulk if their furthest points are nearer than $r * (1 + \text{eps})$.
- workers** [int, optional] Number of jobs to schedule for parallel processing. If -1 is given all processors are used. Default: 1.
New in version 1.6.0.
- return_sorted** [bool, optional] Sorts returned indices if True and does not sort them if False. If None, does not sort single point queries, but does sort multi-point queries which was the behavior before this option was added.
New in version 1.6.0.
- return_length: bool, optional** Return the number of points inside the radius instead of a list of the indices.
New in version 1.6.0.

Returns

- results** [list or array of lists] If *x* is a single point, returns a list of the indices of the neighbors of *x*. If *x* is an array of points, returns an object array of shape tuple containing lists of neighbors.

Notes

If you have many points whose neighbors you want to find, you may save substantial amounts of time by putting them in a `KDTree` and using `query_ball_tree`.

Examples

```
>>> from scipy import spatial
>>> x, y = np.mgrid[0:5, 0:5]
>>> points = np.c_[x.ravel(), y.ravel()]
>>> tree = spatial.KDTree(points)
>>> sorted(tree.query_ball_point([2, 0], 1))
[5, 10, 11, 15]
```

Query multiple points and plot the results:

```
>>> import matplotlib.pyplot as plt
>>> points = np.asarray(points)
>>> plt.plot(points[:,0], points[:,1], '.')
>>> for results in tree.query_ball_point([2, 0], [3, 3], 1):
...     nearby_points = points[results]
```


(continues on next page)

(continued from previous page)

```

...     plt.plot(nearby_points[:,0], nearby_points[:,1], 'o')
>>> plt.margins(0.1, 0.1)
>>> plt.show()

```



scipy.spatial.KDTree.query_ball_tree

`KDTree.query_ball_tree` (*self*, *other*, *r*, *p*=2.0, *eps*=0)

Find all pairs of points between *self* and *other* whose distance is at most *r*

Parameters

- other** [KDTree instance] The tree containing points to search against.
- r** [float] The maximum distance, has to be positive.
- p** [float, optional] Which Minkowski norm to use. *p* has to meet the condition $1 \leq p \leq \text{infinity}$.
- eps** [float, optional] Approximate search. Branches of the tree are not explored if their nearest points are further than $r / (1 + \text{eps})$, and branches are added in bulk if their furthest points are nearer than $r * (1 + \text{eps})$. *eps* has to be non-negative.

Returns

- results** [list of lists] For each element `self.data[i]` of this tree, `results[i]` is a list of the indices of its neighbors in `other.data`.

Examples

You can search all pairs of points between two kd-trees within a distance:

```


>>> import matplotlib.pyplot as plt
>>> import numpy as np
>>> from scipy.spatial import KDTree
>>> np.random.seed(21701)
>>> points1 = np.random.random((15, 2))
>>> points2 = np.random.random((15, 2))

```

(continues on next page)

(continued from previous page)

```
>>> plt.figure(figsize=(6, 6))
>>> plt.plot(points1[:, 0], points1[:, 1], "xk", markersize=14)
>>> plt.plot(points2[:, 0], points2[:, 1], "og", markersize=14)
>>> kd_tree1 = KDTree(points1)
>>> kd_tree2 = KDTree(points2)
>>> indexes = kd_tree1.query_ball_tree(kd_tree2, r=0.2)
>>> for i in range(len(indexes)):
...     for j in indexes[i]:
...         plt.plot([points1[i, 0], points2[j, 0]],
...                   [points1[i, 1], points2[j, 1]], "-r")
>>> plt.show()
```



scipy.spatial.KDTree.query_pairs

KDTree.**query_pairs** (*self*, *r*, *p=2.0*, *eps=0*, *output_type='set'*)

Find all pairs of points in *self* whose distance is at most *r*.

Parameters

- r** [positive float] The maximum distance.
- p** [float, optional] Which Minkowski norm to use. *p* has to meet the condition $1 \leq p \leq \text{infinity}$.
- eps** [float, optional] Approximate search. Branches of the tree are not explored if their nearest points are further than $r / (1 + \text{eps})$, and branches are added in bulk if their furthest points are nearer than $r * (1 + \text{eps})$. *eps* has to be non-negative.
- output_type** [string, optional] Choose the output container, 'set' or 'ndarray'. Default: 'set'. New in version 1.6.0.

Returns

- results** [set or ndarray] Set of pairs (*i*, *j*), with $i < j$, for which the corresponding positions are close. If *output_type* is 'ndarray', an ndarray is returned instead of a set.

Examples

You can search all pairs of points in a kd-tree within a distance:

```
>>> import matplotlib.pyplot as plt
>>> import numpy as np
>>> from scipy.spatial import KDTree
>>> np.random.seed(21701)
>>> points = np.random.random((20, 2))
>>> plt.figure(figsize=(6, 6))
>>> plt.plot(points[:, 0], points[:, 1], "xk", markersize=14)
>>> kd_tree = KDTree(points)
>>> pairs = kd_tree.query_pairs(r=0.2)
>>> for (i, j) in pairs:
...     plt.plot([points[i, 0], points[j, 0]],
...              [points[i, 1], points[j, 1]], "-r")
>>> plt.show()
```

scipy.spatial.KDTree.sparse_distance_matrix


KDTree.**sparse_distance_matrix** (*self*, *other*, *max_distance*, *p=2.0*, *output_type='dok_matrix'*)

Compute a sparse distance matrix

Computes a distance matrix between two KDTrees, leaving as zero any distance greater than *max_distance*.

Parameters

- other** [KDTree]
- max_distance** [positive float]
- p** [float, $1 \leq p \leq \text{infinity}$] Which Minkowski *p*-norm to use. A finite large *p* may cause a ValueError if overflow can occur.
- output_type** [string, optional] Which container to use for output data. Options: 'dok_matrix', 'coo_matrix', 'dict', or 'ndarray'. Default: 'dok_matrix'. New in version 1.6.0.



Returns

result [dok_matrix, coo_matrix, dict or ndarray] Sparse matrix representing the results in “dictionary of keys” format. If a dict is returned the keys are (i,j) tuples of indices. If output_type is ‘ndarray’ a record array with fields ‘i’, ‘j’, and ‘v’ is returned,

Examples

You can compute a sparse distance matrix between two kd-trees:

```
>>> import numpy as np
>>> from scipy.spatial import KDTree
>>> np.random.seed(21701)
>>> points1 = np.random.random((5, 2))
>>> points2 = np.random.random((5, 2))
>>> kd_tree1 = KDTree(points1)
>>> kd_tree2 = KDTree(points2)
>>> sdm = kd_tree1.sparse_distance_matrix(kd_tree2, 0.3)
>>> sdm.toarray()
array([[0.20220215, 0.14538496, 0.,          0.10257199, 0.          ],
       [0.13491385, 0.27251306, 0.,          0.18793787, 0.          ],
       [0.19262396, 0.,          0.,          0.25795122, 0.          ],
       [0.14859639, 0.07076002, 0.,          0.04065851, 0.          ],
       [0.17308768, 0.,          0.,          0.24823138, 0.          ]])
```

You can check distances above the *max_distance* are zeros:

```
>>> from scipy.spatial import distance_matrix
>>> distance_matrix(points1, points2)
array([[0.20220215, 0.14538496, 0.43588092, 0.10257199, 0.4555495 ],
       [0.13491385, 0.27251306, 0.65944131, 0.18793787, 0.68184154],
       [0.19262396, 0.34121593, 0.72176889, 0.25795122, 0.74538858],
       [0.14859639, 0.07076002, 0.48505773, 0.04065851, 0.50043591],
       [0.17308768, 0.32837991, 0.72760803, 0.24823138, 0.75017239]])
```

innernode	
leafnode	
node	

scipy.spatial.cKDTree

class `scipy.spatial.cKDTree`(*data*, *leafsize=16*, *compact_nodes=True*, *copy_data=False*, *balanced_tree=True*, *boxsize=None*)
 kd-tree for quick nearest-neighbor lookup

This class provides an index into a set of k-dimensional points which can be used to rapidly look up the nearest neighbors of any point.

Parameters

data [array_like, shape (n,m)] The n data points of dimension m to be indexed. This array is not copied unless this is necessary to produce a contiguous array of doubles, and so modifying this data will result in bogus results. The data are also copied if the kd-tree is built with *copy_data=True*.

leafsize	[positive int, optional] The number of points at which the algorithm switches over to brute-force. Default: 16.
compact_nodes	[bool, optional] If True, the kd-tree is built to shrink the hyperrectangles to the actual data range. This usually gives a more compact tree that is robust against degenerated input data and gives faster queries at the expense of longer build time. Default: True.
copy_data	[bool, optional] If True the data is always copied to protect the kd-tree against data corruption. Default: False.
balanced_tree	[bool, optional] If True, the median is used to split the hyperrectangles instead of the midpoint. This usually gives a more compact tree and faster queries at the expense of longer build time. Default: True.
boxsize	[array_like or scalar, optional] Apply a m-d toroidal topology to the KDTree.. The topology is generated by $x_i + n_i L_i$ where n_i are integers and L_i is the boxsize along i-th dimension. The input data shall be wrapped into $[0, L_i)$. A ValueError is raised if any of the data is outside of this bound.

Notes

The algorithm used is described in Maneewongvatana and Mount 1999. The general idea is that the kd-tree is a binary tree, each of whose nodes represents an axis-aligned hyperrectangle. Each node specifies an axis and splits the set of points based on whether their coordinate along that axis is greater than or less than a particular value.

During construction, the axis and splitting point are chosen by the “sliding midpoint” rule, which ensures that the cells do not all become long and thin.

The tree can be queried for the r closest neighbors of any given point (optionally returning only those within some maximum distance of the point). It can also be queried, with a substantial gain in efficiency, for the r approximate closest neighbors.

For large dimensions (20 is already large) do not expect this to run significantly faster than brute force. High-dimensional nearest-neighbor queries are a substantial open problem in computer science.

Attributes

data	[ndarray, shape (n,m)] The n data points of dimension m to be indexed. This array is not copied unless this is necessary to produce a contiguous array of doubles. The data are also copied if the kd-tree is built with <i>copy_data=True</i> .
leafsize	[positive int] The number of points at which the algorithm switches over to brute-force.
m	[int] The dimension of a single data-point.
n	[int] The number of data points.
maxes	[ndarray, shape (m,)] The maximum value in each dimension of the n data points.
mins	[ndarray, shape (m,)] The minimum value in each dimension of the n data points.
tree	[object, class cKDTreeNode] This attribute exposes a Python view of the root node in the cKDTree object. A full Python view of the kd-tree is created dynamically on the first access. This attribute allows you to create your own query functions in Python.
size	[int] The number of nodes in the tree.

Methods

<code>count_neighbors(self, other, r[, p, ...])</code>	Count how many nearby pairs can be formed.
<code>query(self, x[, k, eps, p, ...])</code>	Query the kd-tree for nearest neighbors
<code>query_ball_point(self, x, r[, p, eps, ...])</code>	Find all points within distance <i>r</i> of point(s) <i>x</i> .
<code>query_ball_tree(self, other, r[, p, eps])</code>	Find all pairs of points between <i>self</i> and <i>other</i> whose distance is at most <i>r</i>
<code>query_pairs(self, r[, p, eps])</code>	Find all pairs of points in <i>self</i> whose distance is at most <i>r</i> .
<code>sparse_distance_matrix(self, other, max_distance)</code>	Compute a sparse distance matrix

scipy.spatial.cKDTree.count_neighbors

`cKDTree.count_neighbors` (*self*, *other*, *r*, *p=2.0*, *weights=None*, *cumulative=True*)

Count how many nearby pairs can be formed.

Count the number of pairs (*x1*, *x2*) can be formed, with *x1* drawn from *self* and *x2* drawn from *other*, and where `distance(x1, x2, p) <= r`.

Data points on *self* and *other* are optionally weighted by the *weights* argument. (See below)

This is adapted from the “two-point correlation” algorithm described by Gray and Moore [1]. See notes for further discussion.

Parameters

- other** [cKDTree instance] The other tree to draw points from, can be the same tree as *self*.
- r** [float or one-dimensional array of floats] The radius to produce a count for. Multiple radii are searched with a single tree traversal. If the count is non-cumulative (*cumulative=False*), *r* defines the edges of the bins, and must be non-decreasing.
- p** [float, optional] $1 \leq p \leq \infty$. Which Minkowski *p*-norm to use. Default 2.0. A finite large *p* may cause a `ValueError` if overflow can occur.
- weights** [tuple, array_like, or None, optional] If None, the pair-counting is unweighted. If given as a tuple, *weights*[0] is the weights of points in *self*, and *weights*[1] is the weights of points in *other*; either can be None to indicate the points are unweighted. If given as an array_like, *weights* is the weights of points in *self* and *other*. For this to make sense, *self* and *other* must be the same tree. If *self* and *other* are two different trees, a `ValueError` is raised. Default: None
- cumulative** [bool, optional] Whether the returned counts are cumulative. When *cumulative* is set to `False` the algorithm is optimized to work with a large number of bins (>10) specified by *r*. When *cumulative* is set to `True`, the algorithm is optimized to work with a small number of *r*. Default: `True`

Returns

- result** [scalar or 1-D array] The number of pairs. For unweighted counts, the result is integer. For weighted counts, the result is float. If *cumulative* is `False`, `result[i]` contains the counts with `(-inf if i == 0 else r[i-1]) < R <= r[i]`

Notes

Pair-counting is the basic operation used to calculate the two point correlation functions from a data set composed of position of objects.

Two point correlation function measures the clustering of objects and is widely used in cosmology to quantify the large scale structure in our Universe, but it may be useful for data analysis in other fields where self-similar assembly of objects also occur.

The Landy-Szalay estimator for the two point correlation function of D measures the clustering signal in D . [2]

For example, given the position of two sets of objects,

- objects D (data) contains the clustering signal, and
- objects R (random) that contains no signal,

$$\xi(r) = \frac{\langle D, D \rangle - 2f \langle D, R \rangle + f^2 \langle R, R \rangle}{f^2 \langle R, R \rangle},$$

where the brackets represents counting pairs between two data sets in a finite bin around r (distance), corresponding to setting `cumulative=False`, and $f = \text{float}(\text{len}(D)) / \text{float}(\text{len}(R))$ is the ratio between number of objects from data and random.

The algorithm implemented here is loosely based on the dual-tree algorithm described in [1]. We switch between two different pair-cumulation scheme depending on the setting of `cumulative`. The computing time of the method we use when for `cumulative == False` does not scale with the total number of bins. The algorithm for `cumulative == True` scales linearly with the number of bins, though it is slightly faster when only 1 or 2 bins are used. [5].

As an extension to the naive pair-counting, weighted pair-counting counts the product of weights instead of number of pairs. Weighted pair-counting is used to estimate marked correlation functions ([3], section 2.2), or to properly calculate the average of data per distance bin (e.g. [4], section 2.1 on redshift).

Examples

You can count neighbors number between two kd-trees within a distance:

```
>>> import numpy as np
>>> from scipy.spatial import cKDTree
>>> np.random.seed(21701)
>>> points1 = np.random.random((5, 2))
>>> points2 = np.random.random((5, 2))
>>> kd_tree1 = cKDTree(points1)
>>> kd_tree2 = cKDTree(points2)
>>> kd_tree1.count_neighbors(kd_tree2, 0.2)
9
```

This number is same as the total pair number calculated by `query_ball_tree`:

```
>>> indexes = kd_tree1.query_ball_tree(kd_tree2, r=0.2)
>>> sum([len(i) for i in indexes])
9
```

scipy.spatial.cKDTree.query

`cKDTree.query` (*self*, *x*, *k=1*, *eps=0*, *p=2*, *distance_upper_bound=np.inf*, *workers=1*)

Query the kd-tree for nearest neighbors

Parameters

- x** [array_like, last dimension *self.m*] An array of points to query.
- k** [list of integer or integer] The list of *k*-th nearest neighbors to return. If *k* is an integer it is treated as a list of [1, ... *k*] (`range(1, k+1)`). Note that the counting starts from 1.
- eps** [non-negative float] Return approximate nearest neighbors; the *k*-th returned value is guaranteed to be no further than $(1+eps)$ times the distance to the real *k*-th nearest neighbor.
- p** [float, $1 \leq p \leq \text{infinity}$] Which Minkowski *p*-norm to use. 1 is the sum-of-absolute-values “Manhattan” distance 2 is the usual Euclidean distance infinity is the maximum-coordinate-difference distance A finite large *p* may cause a `ValueError` if overflow can occur.
- distance_upper_bound** [nonnegative float] Return only neighbors within this distance. This is used to prune tree searches, so if you are doing a series of nearest-neighbor queries, it may help to supply the distance to the nearest neighbor of the most recent point.
- workers** [int, optional] Number of workers to use for parallel processing. If -1 is given all CPU threads are used. Default: 1.
- Changed in version 1.6.0: The “`n_jobs`” argument was renamed “`workers`”. The old name “`n_jobs`” is deprecated and will stop working in SciPy 1.8.0.

Returns

- d** [array of floats] The distances to the nearest neighbors. If *x* has shape `tuple+(self.m,)`, then *d* has shape `tuple+(k,)`. When *k* == 1, the last dimension of the output is squeezed. Missing neighbors are indicated with infinite distances.
- i** [ndarray of ints] The index of each neighbor in *self.data*. If *x* has shape `tuple+(self.m,)`, then *i* has shape `tuple+(k,)`. When *k* == 1, the last dimension of the output is squeezed. Missing neighbors are indicated with *self.n*.

Notes

If the KD-Tree is periodic, the position *x* is wrapped into the box.

When the input *k* is a list, a query for `arange(max(k))` is performed, but only columns that store the requested values of *k* are preserved. This is implemented in a manner that reduces memory usage.

Examples

```
>>> import numpy as np
>>> from scipy.spatial import cKDTree
>>> x, y = np.mgrid[0:5, 2:8]
>>> tree = cKDTree(np.c_[x.ravel(), y.ravel()])
```

To query the nearest neighbours and return squeezed result, use

```
>>> dd, ii = tree.query([[0, 0], [2.1, 2.9]], k=1)
>>> print(dd, ii)
[2.          0.14142136] [ 0 13]
```

To query the nearest neighbours and return unsqueezed result, use

```
>>> dd, ii = tree.query([[0, 0], [2.1, 2.9]], k=[1])
>>> print(dd, ii)
[[2.         ]
 [0.14142136]] [[ 0]
 [13]]
```

To query the second nearest neighbours and return unsqueezed result, use

```
>>> dd, ii = tree.query([[0, 0], [2.1, 2.9]], k=[2])
>>> print(dd, ii)
[[2.23606798]
 [0.90553851]] [[ 6]
 [12]]
```

To query the first and second nearest neighbours, use

```
>>> dd, ii = tree.query([[0, 0], [2.1, 2.9]], k=2)
>>> print(dd, ii)
[[2.         2.23606798]
 [0.14142136 0.90553851]] [[ 0  6]
 [13 12]]
```

or, be more specific

```
>>> dd, ii = tree.query([[0, 0], [2.1, 2.9]], k=[1, 2])
>>> print(dd, ii)
[[2.         2.23606798]
 [0.14142136 0.90553851]] [[ 0  6]
 [13 12]]
```

scipy.spatial.cKDTree.query_ball_point

`cKDTree.query_ball_point` (*self*, *x*, *r*, *p=2.0*, *eps=0*, *workers=1*, *return_sorted=None*, *return_length=False*)

Find all points within distance *r* of point(s) *x*.

Parameters

- x** [array_like, shape tuple + (self.m,)] The point or points to search for neighbors of.
- r** [array_like, float] The radius of points to return, shall broadcast to the length of *x*.
- p** [float, optional] Which Minkowski *p*-norm to use. Should be in the range [1, inf]. A finite large *p* may cause a `ValueError` if overflow can occur.
- eps** [nonnegative float, optional] Approximate search. Branches of the tree are not explored if their nearest points are further than $r / (1 + \text{eps})$, and branches are added in bulk if their furthest points are nearer than $r * (1 + \text{eps})$.
- workers** [int, optional] Number of jobs to schedule for parallel processing. If -1 is given all processors are used. Default: 1.
Changed in version 1.6.0: The “`n_jobs`” argument was renamed “`workers`”. The old name “`n_jobs`” is deprecated and will stop working in SciPy 1.8.0.
- return_sorted** [bool, optional] Sorts returned indices if True and does not sort them if False. If None, does not sort single point queries, but does sort multi-point queries which was the behavior before this option was added.
New in version 1.2.0.

return_length: bool, optional

Return the number of points inside the radius instead of a list of the indices. .. version-added:: 1.3.0

Returns

results [list or array of lists] If x is a single point, returns a list of the indices of the neighbors of x . If x is an array of points, returns an object array of shape tuple containing lists of neighbors.

Notes


If you have many points whose neighbors you want to find, you may save substantial amounts of time by putting them in a `cKDTree` and using `query_ball_tree`.

Examples

```
>>> from scipy import spatial
>>> x, y = np.mgrid[0:4, 0:4]
>>> points = np.c_[x.ravel(), y.ravel()]
>>> tree = spatial.cKDTree(points)
>>> tree.query_ball_point([2, 0], 1)
[4, 8, 9, 12]
```

Query multiple points and plot the results:

```
>>> import matplotlib.pyplot as plt
>>> points = np.asarray(points)
>>> plt.plot(points[:,0], points[:,1], '.')
>>> for results in tree.query_ball_point([2, 0], [3, 3]), 1):
...     nearby_points = points[results]
...     plt.plot(nearby_points[:,0], nearby_points[:,1], 'o')
>>> plt.margins(0.1, 0.1)
>>> plt.show()
```



scipy.spatial.cKDTree.query_ball_tree`cKDTree.query_ball_tree` (*self*, *other*, *r*, *p*=2.0, *eps*=0)Find all pairs of points between *self* and *other* whose distance is at most *r***Parameters**

- other** [cKDTree instance] The tree containing points to search against.
- r** [float] The maximum distance, has to be positive.
- p** [float, optional] Which Minkowski norm to use. *p* has to meet the condition $1 \leq p \leq \text{infinity}$. A finite large *p* may cause a `ValueError` if overflow can occur.
- eps** [float, optional] Approximate search. Branches of the tree are not explored if their nearest points are further than $r / (1 + \text{eps})$, and branches are added in bulk if their furthest points are nearer than $r * (1 + \text{eps})$. *eps* has to be non-negative.

Returns

- results** [list of lists] For each element `self.data[i]` of this tree, `results[i]` is a list of the indices of its neighbors in `other.data`.

Examples

You can search all pairs of points between two kd-trees within a distance:


```
>>> import matplotlib.pyplot as plt
>>> import numpy as np
>>> from scipy.spatial import cKDTree
>>> np.random.seed(21701)
>>> points1 = np.random.random((15, 2))
>>> points2 = np.random.random((15, 2))
>>> plt.figure(figsize=(6, 6))
>>> plt.plot(points1[:, 0], points1[:, 1], "xk", markersize=14)
>>> plt.plot(points2[:, 0], points2[:, 1], "og", markersize=14)
>>> kd_tree1 = cKDTree(points1)
>>> kd_tree2 = cKDTree(points2)
>>> indexes = kd_tree1.query_ball_tree(kd_tree2, r=0.2)
>>> for i in range(len(indexes)):
...     for j in indexes[i]:
...         plt.plot([points1[i, 0], points2[j, 0]],
...                 [points1[i, 1], points2[j, 1]], "-r")
>>> plt.show()
```

scipy.spatial.cKDTree.query_pairs`cKDTree.query_pairs` (*self*, *r*, *p*=2.0, *eps*=0)Find all pairs of points in *self* whose distance is at most *r*.**Parameters**

- r** [positive float] The maximum distance.
- p** [float, optional] Which Minkowski norm to use. *p* has to meet the condition $1 \leq p \leq \text{infinity}$. A finite large *p* may cause a `ValueError` if overflow can occur.
- eps** [float, optional] Approximate search. Branches of the tree are not explored if their nearest points are further than $r / (1 + \text{eps})$, and branches are added in bulk if their furthest points are nearer than $r * (1 + \text{eps})$. *eps* has to be non-negative.

output_type

[string, optional] Choose the output container, 'set' or 'ndarray'. Default: 'set'



Returns

results [set or ndarray] Set of pairs (i, j) , with $i < j$, for which the corresponding positions are close. If `output_type` is 'ndarray', an ndarray is returned instead of a set.

Examples

You can search all pairs of points in a kd-tree within a distance:

```
>>> import matplotlib.pyplot as plt
>>> import numpy as np
>>> from scipy.spatial import cKDTree
>>> np.random.seed(21701)
>>> points = np.random.random((20, 2))
>>> plt.figure(figsize=(6, 6))
>>> plt.plot(points[:, 0], points[:, 1], "xk", markersize=14)
>>> kd_tree = cKDTree(points)
>>> pairs = kd_tree.query_pairs(r=0.2)
>>> for (i, j) in pairs:
...     plt.plot([points[i, 0], points[j, 0]],
...             [points[i, 1], points[j, 1]], "-r")
>>> plt.show()
```

scipy.spatial.cKDTree.sparse_distance_matrix

`cKDTree.sparse_distance_matrix` (*self, other, max_distance, p=2.0*)

Compute a sparse distance matrix

Computes a distance matrix between two cKDTrees, leaving as zero any distance greater than `max_distance`.

Parameters

other [cKDTree]


max_distance [positive float]

p [float, $1 \leq p \leq \text{infinity}$] Which Minkowski p -norm to use. A finite large p may cause a `ValueError` if overflow can occur.

output_type [string, optional] Which container to use for output data. Options: 'dok_matrix', 'coo_matrix', 'dict', or 'ndarray'. Default: 'dok_matrix'.

Returns

result [dok_matrix, coo_matrix, dict or ndarray] Sparse matrix representing the results in "dictionary of keys" format. If a dict is returned the keys are (i, j) tuples of indices. If `output_type` is 'ndarray' a record array with fields 'i', 'j', and 'v' is returned,



Examples

You can compute a sparse distance matrix between two kd-trees:

```
>>> import numpy as np
>>> from scipy.spatial import cKDTree
>>> np.random.seed(21701)
>>> points1 = np.random.random((5, 2))
>>> points2 = np.random.random((5, 2))
>>> kd_tree1 = cKDTree(points1)
>>> kd_tree2 = cKDTree(points2)
>>> sdm = kd_tree1.sparse_distance_matrix(kd_tree2, 0.3)
>>> sdm.toarray()
array([[0.20220215, 0.14538496, 0.,          0.10257199, 0.          ],
       [0.13491385, 0.27251306, 0.,          0.18793787, 0.          ],
       [0.19262396, 0.,          0.,          0.25795122, 0.          ],
       [0.14859639, 0.07076002, 0.,          0.04065851, 0.          ],
       [0.17308768, 0.,          0.,          0.24823138, 0.          ]])
```

You can check distances above the *max_distance* are zeros:

```
>>> from scipy.spatial import distance_matrix
>>> distance_matrix(points1, points2)
array([[0.20220215, 0.14538496, 0.43588092, 0.10257199, 0.4555495 ],
       [0.13491385, 0.27251306, 0.65944131, 0.18793787, 0.68184154],
       [0.19262396, 0.34121593, 0.72176889, 0.25795122, 0.74538858],
       [0.14859639, 0.07076002, 0.48505773, 0.04065851, 0.50043591],
       [0.17308768, 0.32837991, 0.72760803, 0.24823138, 0.75017239]])
```

scipy.spatial.Rectangle

class `scipy.spatial.Rectangle` (*maxes, mins*)

Hyperrectangle class.

Represents a Cartesian product of intervals.

Methods

<code>max_distance_point(self, x[, p])</code>	Return the maximum distance between input and points in the hyperrectangle.
<code>max_distance_rectangle(self, other[, p])</code>	Compute the maximum distance between points in the two hyperrectangles.
<code>min_distance_point(self, x[, p])</code>	Return the minimum distance between input and points in the hyperrectangle.
<code>min_distance_rectangle(self, other[, p])</code>	Compute the minimum distance between points in the two hyperrectangles.
<code>split(self, d, split)</code>	Produce two hyperrectangles by splitting.
<code>volume(self)</code>	Total volume.

scipy.spatial.Rectangle.max_distance_point`Rectangle.max_distance_point` (*self*, *x*, *p=2.0*)

Return the maximum distance between input and points in the hyperrectangle.

Parameters

x [array_like] Input array.
p [float, optional] Input.

scipy.spatial.Rectangle.max_distance_rectangle`Rectangle.max_distance_rectangle` (*self*, *other*, *p=2.0*)

Compute the maximum distance between points in the two hyperrectangles.

Parameters

other [hyperrectangle] Input.
p [float, optional] Input.

scipy.spatial.Rectangle.min_distance_point`Rectangle.min_distance_point` (*self*, *x*, *p=2.0*)

Return the minimum distance between input and points in the hyperrectangle.

Parameters

x [array_like] Input.
p [float, optional] Input.

scipy.spatial.Rectangle.min_distance_rectangle`Rectangle.min_distance_rectangle` (*self*, *other*, *p=2.0*)

Compute the minimum distance between points in the two hyperrectangles.

Parameters

other [hyperrectangle] Input.
p [float] Input.

scipy.spatial.Rectangle.split`Rectangle.split` (*self*, *d*, *split*)

Produce two hyperrectangles by splitting.

In general, if you need to compute maximum and minimum distances to the children, it can be done more efficiently by updating the maximum and minimum distances to the parent.

Parameters

d [int] Axis to split hyperrectangle along.
split [float] Position along axis *d* to split at.

scipy.spatial.Rectangle.volume

`Rectangle.volume` (*self*)
Total volume.

Distance metrics are contained in the `scipy.spatial.distance` submodule.

6.26.3 Delaunay triangulation, convex hulls, and Voronoi diagrams

<code>Delaunay</code> (points[, furthest_site, ...])	Delaunay tessellation in N dimensions.
<code>ConvexHull</code> (points[, incremental, qhull_options])	Convex hulls in N dimensions.
<code>Voronoi</code> (points[, furthest_site, ...])	Voronoi diagrams in N dimensions.
<code>SphericalVoronoi</code> (points[, radius, center, ...])	Voronoi diagrams on the surface of a sphere.
<code>HalfspaceIntersection</code> (halfspaces, interior_point)	Halfspace intersections in N dimensions.

scipy.spatial.Delaunay

class `scipy.spatial.Delaunay` (*points*, *furthest_site=False*, *incremental=False*, *qhull_options=None*)
Delaunay tessellation in N dimensions.

New in version 0.9.

Parameters

points [ndarray of floats, shape (npoints, ndim)] Coordinates of points to triangulate

furthest_site [bool, optional] Whether to compute a furthest-site Delaunay triangulation. Default: False
New in version 0.12.0.

incremental [bool, optional] Allow adding new points incrementally. This takes up some additional resources.

qhull_options [str, optional] Additional options to pass to Qhull. See Qhull manual for details. Option “Qt” is always enabled. Default: “Qbb Qc Qz Qx Q12” for `ndim > 4` and “Qbb Qc Qz Q12” otherwise. Incremental mode omits “Qz”.
New in version 0.12.0.

Raises

QhullError
Raised when Qhull encounters an error condition, such as geometrical degeneracy when options to resolve are not enabled.

ValueError
Raised if an incompatible array is given as input.

Notes

The tessellation is computed using the Qhull library [Qhull library](#).

Note: Unless you pass in the Qhull option “QJ”, Qhull does not guarantee that each input point appears as a vertex in the Delaunay triangulation. Omitted points are listed in the *coplanar* attribute.


Examples

Triangulation of a set of points:

```
>>> points = np.array([[0, 0], [0, 1.1], [1, 0], [1, 1]])
>>> from scipy.spatial import Delaunay
>>> tri = Delaunay(points)
```

We can plot it:

```
>>> import matplotlib.pyplot as plt
>>> plt.triplot(points[:,0], points[:,1], tri.simplices)
>>> plt.plot(points[:,0], points[:,1], 'o')
>>> plt.show()
```



Point indices and coordinates for the two triangles forming the triangulation:

```
>>> tri.simplices
array([[2, 3, 0],
       [3, 1, 0]], dtype=int32) # may vary
```

Note that depending on how rounding errors go, the simplices may be in a different order than above.

```
>>> points[tri.simplices]
array([[1. , 0. ],
       [1. , 1. ]], dtype=float64) # may vary
```

(continues on next page)

(continued from previous page)

```
[ 1. ,  1. ],
 [ 0. ,  0. ]],
 [[ 1. ,  1. ],
 [ 0. ,  1.1],
 [ 0. ,  0. ]]])
```

Triangle 0 is the only neighbor of triangle 1, and it's opposite to vertex 1 of triangle 1:

```
>>> tri.neighbors[1]
array([-1,  0, -1], dtype=int32)
>>> points[tri.simplices[1,1]]
array([ 0. ,  1.1])
```

We can find out which triangle points are in:

```
>>> p = np.array([(0.1, 0.2), (1.5, 0.5), (0.5, 1.05)])
>>> tri.find_simplex(p)
array([ 1, -1,  1], dtype=int32)
```

The returned integers in the array are the indices of the simplex the corresponding point is in. If -1 is returned, the point is in no simplex. Be aware that the shortcut in the following example only works correctly for valid points as invalid points result in -1 which is itself a valid index for the last simplex in the list.

```
>>> p_valids = np.array([(0.1, 0.2), (0.5, 1.05)])
>>> tri.simplices[tri.find_simplex(p_valids)]
array([[3, 1, 0],
       [3, 1, 0]], dtype=int32) # may vary
```

We can also compute barycentric coordinates in triangle 1 for these points:

```
>>> b = tri.transform[1,:2].dot(np.transpose(p - tri.transform[1,2]))
>>> np.c_[np.transpose(b), 1 - b.sum(axis=0)]
array([[ 0.1      ,  0.09090909,  0.80909091],
       [ 1.5      , -0.90909091,  0.40909091],
       [ 0.5      ,  0.5       ,  0.         ]])
```

The coordinates for the first point are all positive, meaning it is indeed inside the triangle. The third point is on a vertex, hence its null third coordinate.

Attributes

- points** [ndarray of double, shape (npoints, ndim)] Coordinates of input points.
- simplices** [ndarray of ints, shape (nsimplex, ndim+1)] Indices of the points forming the simplices in the triangulation. For 2-D, the points are oriented counterclockwise.
- neighbors** [ndarray of ints, shape (nsimplex, ndim+1)] Indices of neighbor simplices for each simplex. The kth neighbor is opposite to the kth vertex. For simplices at the boundary, -1 denotes no neighbor.
- equations** [ndarray of double, shape (nsimplex, ndim+2)] [normal, offset] forming the hyperplane equation of the facet on the paraboloid (see [Qhull documentation](#) for more).
- paraboloid_scale, paraboloid_shift** [float] Scale and shift for the extra paraboloid dimension (see [Qhull documentation](#) for more).
- transform** [ndarray of double, shape (nsimplex, ndim+1, ndim)] Affine transform from x to the barycentric coordinates c .

- vertex_to_simplex** [ndarray of int, shape (npoints,)] Lookup array, from a vertex, to some simplex which it is a part of.
- convex_hull** [ndarray of int, shape (nfaces, ndim)] Vertices of facets forming the convex hull of the point set.
- coplanar** [ndarray of int, shape (ncoplanar, 3)] Indices of coplanar points and the corresponding indices of the nearest facet and the nearest vertex. Coplanar points are input points which were *not* included in the triangulation due to numerical precision issues.
If option “Qc” is not specified, this list is not computed.
New in version 0.12.0.
- vertices** Same as *simplices*, but deprecated.
- vertex_neighbor_vertices** [tuple of two ndarrays of int; (indptr, indices)] Neighboring vertices of vertices.
- furthest_site** True if this was a furthest site triangulation and False if not.
New in version 1.4.0.

Methods

<code>add_points(points[, restart])</code>	Process a set of additional new points.
<code>close()</code>	Finish incremental processing.
<code>find_simplex(self, xi[, brute-force, tol])</code>	Find the simplices containing the given points.
<code>lift_points(self, x)</code>	Lift points to the Qhull paraboloid.
<code>plane_distance(self, xi)</code>	Compute hyperplane distances to the point <i>xi</i> from all simplices.

scipy.spatial.Delaunay.add_points

Delaunay.**add_points** (*points*, *restart=False*)

Process a set of additional new points.

Parameters

- points** [ndarray] New points to add. The dimensionality should match that of the initial points.
- restart** [bool, optional] Whether to restart processing from scratch, rather than adding points incrementally.

Raises

QhullError

Raised when Qhull encounters an error condition, such as geometrical degeneracy when options to resolve are not enabled.

See also:

`close`

Notes

You need to specify `incremental=True` when constructing the object to be able to add points incrementally. Incremental addition of points is also not possible after `close` has been called.

`scipy.spatial.Delaunay.close`

`Delaunay.close()`

Finish incremental processing.

Call this to free resources taken up by Qhull, when using the incremental mode. After calling this, adding more points is no longer possible.

`scipy.spatial.Delaunay.find_simplex`

`Delaunay.find_simplex(self, xi, bruteforce=False, tol=None)`

Find the simplices containing the given points.

Parameters

tri	[DelaunayInfo] Delaunay triangulation
xi	[ndarray of double, shape (... , ndim)] Points to locate
bruteforce	[bool, optional] Whether to only perform a brute-force search
tol	[float, optional] Tolerance allowed in the inside-triangle check. Default is $100 * \text{eps}$.

Returns

i	[ndarray of int, same shape as <i>xi</i>] Indices of simplices containing each point. Points outside the triangulation get the value -1.
----------	---

Notes

This uses an algorithm adapted from Qhull's `qh_findbestfacet`, which makes use of the connection between a convex hull and a Delaunay triangulation. After finding the simplex closest to the point in $N+1$ dimensions, the algorithm falls back to directed search in N dimensions.

`scipy.spatial.Delaunay.lift_points`

`Delaunay.lift_points(self, x)`

Lift points to the Qhull paraboloid.

`scipy.spatial.Delaunay.plane_distance`

`Delaunay.plane_distance(self, xi)`

Compute hyperplane distances to the point *xi* from all simplices.

`scipy.spatial.ConvexHull`

class `scipy.spatial.ConvexHull` (*points, incremental=False, qhull_options=None*)

Convex hulls in N dimensions.

New in version 0.12.0.

Parameters

points	[ndarray of floats, shape (npoints, ndim)] Coordinates of points to construct a convex hull from
---------------	--

incremental

[bool, optional] Allow adding new points incrementally. This takes up some additional resources.

qhull_options

[str, optional] Additional options to pass to Qhull. See Qhull manual for details. (Default: "Qx" for ndim > 4 and "" otherwise) Option "Qt" is always enabled.

Raises

QhullError

Raised when Qhull encounters an error condition, such as geometrical degeneracy when options to resolve are not enabled.

ValueError

Raised if an incompatible array is given as input.

Notes

The convex hull is computed using the [Qhull library](#).

References

[Qhull]

Examples

Convex hull of a random set of points:

```
>>> from scipy.spatial import ConvexHull, convex_hull_plot_2d
>>> points = np.random.rand(30, 2) # 30 random points in 2-D
>>> hull = ConvexHull(points)
```

Plot it:

```
>>> import matplotlib.pyplot as plt
>>> plt.plot(points[:,0], points[:,1], 'o')
>>> for simplex in hull.simplices:
...     plt.plot(points[simplex, 0], points[simplex, 1], 'k-')
```

We could also have directly used the vertices of the hull, which for 2-D are guaranteed to be in counterclockwise order:


```
>>> plt.plot(points[hull.vertices,0], points[hull.vertices,1], 'r--', lw=2)
>>> plt.plot(points[hull.vertices[0],0], points[hull.vertices[0],1], 'ro')
>>> plt.show()
```

Facets visible from a point:

Create a square and add a point above the square.

```
>>> generators = np.array([[0.2, 0.2],
...                       [0.2, 0.4],
...                       [0.4, 0.4],
```

(continues on next page)



(continued from previous page)

```
...         [0.4, 0.2],
...         [0.3, 0.6]])
```

Call `ConvexHull` with the `QG` option. `QG4` means compute the portions of the hull not including point 4, indicating the facets that are visible from point 4.

```
>>> hull = ConvexHull(points=generators,
...                   qhull_options='QG4')
```


The “good” array indicates which facets are visible from point 4.

```
>>> print(hull.simplices)
[[1 0]
 [1 2]
 [3 0]
 [3 2]]
>>> print(hull.good)
[False True False False]
```

Now plot it, highlighting the visible facets.

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(1,1,1)
>>> for visible_facet in hull.simplices[hull.good]:
...     ax.plot(hull.points[visible_facet, 0],
...             hull.points[visible_facet, 1],
...             color='violet',
...             lw=6)
>>> convex_hull_plot_2d(hull, ax=ax)
<Figure size 640x480 with 1 Axes> # may vary
>>> plt.show()
```

Attributes



- points** [ndarray of double, shape (npoints, ndim)] Coordinates of input points.
- vertices** [ndarray of ints, shape (nvertices,)] Indices of points forming the vertices of the convex hull. For 2-D convex hulls, the vertices are in counterclockwise order. For other dimensions, they are in input order.
- simplices** [ndarray of ints, shape (nfacet, ndim)] Indices of points forming the simplicial facets of the convex hull.
- neighbors** [ndarray of ints, shape (nfacet, ndim)] Indices of neighbor facets for each facet. The kth neighbor is opposite to the kth vertex. -1 denotes no neighbor.
- equations** [ndarray of double, shape (nfacet, ndim+1)] [normal, offset] forming the hyperplane equation of the facet (see [Qhull documentation](#) for more).
- coplanar** [ndarray of int, shape (ncoplanar, 3)] Indices of coplanar points and the corresponding indices of the nearest facets and nearest vertex indices. Coplanar points are input points which were *not* included in the triangulation due to numerical precision issues.
If option “Qc” is not specified, this list is not computed.
- good** [ndarray of bool or None] A one-dimensional Boolean array indicating which facets are good. Used with options that compute good facets, e.g. QGn and QG-n. Good facets are defined as those that are visible (n) or invisible (-n) from point n, where n is the nth point in ‘points’. The ‘good’ attribute may be used as an index into ‘simplices’ to return the good (visible) facets: simplices[good]. A facet is visible from the outside of the hull only, and neither coplanarity nor degeneracy count as cases of visibility.
If a “QGn” or “QG-n” option is not specified, None is returned.
New in version 1.3.0.
- area** [float] Surface area of the convex hull when input dimension > 2. When input points are 2-dimensional, this is the perimeter of the convex hull.
New in version 0.17.0.
- volume** [float] Volume of the convex hull when input dimension > 2. When input points are 2-dimensional, this is the area of the convex hull.
New in version 0.17.0.

Methods

<code>add_points(points[, restart])</code>	Process a set of additional new points.
<code>close()</code>	Finish incremental processing.

`scipy.spatial.ConvexHull.add_points`

`ConvexHull.add_points(points, restart=False)`

Process a set of additional new points.

Parameters

points [ndarray] New points to add. The dimensionality should match that of the initial points.
restart [bool, optional] Whether to restart processing from scratch, rather than adding points incrementally.

Raises

QhullError

Raised when Qhull encounters an error condition, such as geometrical degeneracy when options to resolve are not enabled.

See also:

`close`

Notes

You need to specify `incremental=True` when constructing the object to be able to add points incrementally. Incremental addition of points is also not possible after `close` has been called.

`scipy.spatial.ConvexHull.close`

`ConvexHull.close()`

Finish incremental processing.

Call this to free resources taken up by Qhull, when using the incremental mode. After calling this, adding more points is no longer possible.

`scipy.spatial.Voronoi`

class `scipy.spatial.Voronoi(points, furthest_site=False, incremental=False, qhull_options=None)`

Voronoi diagrams in N dimensions.

New in version 0.12.0.

Parameters

points [ndarray of floats, shape (npoints, ndim)] Coordinates of points to construct a convex hull from
furthest_site [bool, optional] Whether to compute a furthest-site Voronoi diagram. Default: False
incremental [bool, optional] Allow adding new points incrementally. This takes up some additional resources.

qhull_options

[str, optional] Additional options to pass to Qhull. See Qhull manual for details. (Default: “Qbb Qc Qz Qx” for $\text{ndim} > 4$ and “Qbb Qc QZ” otherwise. Incremental mode omits “QZ”.)

Raises

QhullError

Raised when Qhull encounters an error condition, such as geometrical degeneracy when options to resolve are not enabled.

ValueError

Raised if an incompatible array is given as input.

Notes

The Voronoi diagram is computed using the [Qhull library](#).


Examples

Voronoi diagram for a set of point:

```
>>> points = np.array([[0, 0], [0, 1], [0, 2], [1, 0], [1, 1], [1, 2],
...                    [2, 0], [2, 1], [2, 2]])
>>> from scipy.spatial import Voronoi, voronoi_plot_2d
>>> vor = Voronoi(points)
```

Plot it:

```
>>> import matplotlib.pyplot as plt
>>> fig = voronoi_plot_2d(vor)
>>> plt.show()
```



The Voronoi vertices:


```
>>> vor.vertices
array([[0.5, 0.5],
       [0.5, 1.5],
       [1.5, 0.5],
       [1.5, 1.5]])
```

There is a single finite Voronoi region, and four finite Voronoi ridges:

```
>>> vor.regions
[[], [-1, 0], [-1, 1], [1, -1, 0], [3, -1, 2], [-1, 3], [-1, 2], [0, 1, 3,
→ 2], [2, -1, 0], [3, -1, 1]]
>>> vor.ridge_vertices
[[-1, 0], [-1, 0], [-1, 1], [-1, 1], [0, 1], [-1, 3], [-1, 2], [2, 3], [-
→ 1, 3], [-1, 2], [1, 3], [0, 2]]
```

The ridges are perpendicular between lines drawn between the following input points:

```
>>> vor.ridge_points
array([[0, 3],
       [0, 1],
       [2, 5],
       [2, 1],
       [1, 4],
       [7, 8],
       [7, 6],
       [7, 4],
       [8, 5],
       [6, 3],
       [4, 5],
       [4, 3]], dtype=int32)
```

Attributes

- points** [ndarray of double, shape (npoints, ndim)] Coordinates of input points.
- vertices** [ndarray of double, shape (nvertices, ndim)] Coordinates of the Voronoi vertices.
- ridge_points** [ndarray of ints, shape (nridges, 2)] Indices of the points between which each Voronoi ridge lies.
- ridge_vertices** [list of list of ints, shape (nridges, *)] Indices of the Voronoi vertices forming each Voronoi ridge.
- regions** [list of list of ints, shape (nregions, *)] Indices of the Voronoi vertices forming each Voronoi region. -1 indicates vertex outside the Voronoi diagram.
- point_region** [list of ints, shape (npoints)] Index of the Voronoi region for each input point. If qhull option “Qc” was not specified, the list will contain -1 for points that are not associated with a Voronoi region.
- furthest_site** True if this was a furthest site triangulation and False if not.
New in version 1.4.0.

Methods

<code>add_points(points[, restart])</code>	Process a set of additional new points.
<code>close()</code>	Finish incremental processing.

`scipy.spatial.Voronoi.add_points`

`Voronoi.add_points(points, restart=False)`

Process a set of additional new points.

Parameters

points [ndarray] New points to add. The dimensionality should match that of the initial points.
restart [bool, optional] Whether to restart processing from scratch, rather than adding points incrementally.

Raises

QhullError

Raised when Qhull encounters an error condition, such as geometrical degeneracy when options to resolve are not enabled.

See also:

`close`

Notes

You need to specify `incremental=True` when constructing the object to be able to add points incrementally. Incremental addition of points is also not possible after `close` has been called.

`scipy.spatial.Voronoi.close`

`Voronoi.close()`

Finish incremental processing.

Call this to free resources taken up by Qhull, when using the incremental mode. After calling this, adding more points is no longer possible.

`scipy.spatial.SphericalVoronoi`

class `scipy.spatial.SphericalVoronoi` (*points, radius=1, center=None, threshold=1e-06*)

Voronoi diagrams on the surface of a sphere.

New in version 0.18.0.

Parameters

points [ndarray of floats, shape (npoints, ndim)] Coordinates of points from which to construct a spherical Voronoi diagram.
radius [float, optional] Radius of the sphere (Default: 1)
center [ndarray of floats, shape (ndim,)] Center of sphere (Default: origin)
threshold [float] Threshold for detecting duplicate points and mismatches between points and sphere parameters. (Default: 1e-06)

Raises

ValueError

If there are duplicates in *points*. If the provided *radius* is not consistent with *points*.

See also:

Voronoi

Conventional Voronoi diagrams in N dimensions.

Notes

The spherical Voronoi diagram algorithm proceeds as follows. The Convex Hull of the input points (generators) is calculated, and is equivalent to their Delaunay triangulation on the surface of the sphere [Caroli]. The Convex Hull neighbour information is then used to order the Voronoi region vertices around each generator. The latter approach is substantially less sensitive to floating point issues than angle-based methods of Voronoi region vertex sorting.

Empirical assessment of spherical Voronoi algorithm performance suggests quadratic time complexity (loglinear is optimal, but algorithms are more challenging to implement).

References

[Caroli], [VanOosterom]

Examples

Do some imports and take some points on a cube:

```
>>> import matplotlib.pyplot as plt
>>> from scipy.spatial import SphericalVoronoi, geometric_slerp
>>> from mpl_toolkits.mplot3d import proj3d
>>> # set input data
>>> points = np.array([[0, 0, 1], [0, 0, -1], [1, 0, 0],
...                   [0, 1, 0], [0, -1, 0], [-1, 0, 0], ])
```

Calculate the spherical Voronoi diagram:

```
>>> radius = 1
>>> center = np.array([0, 0, 0])
>>> sv = SphericalVoronoi(points, radius, center)
```


Generate plot:

```
>>> # sort vertices (optional, helpful for plotting)
>>> sv.sort_vertices_of_regions()
>>> t_vals = np.linspace(0, 1, 2000)
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111, projection='3d')
>>> # plot the unit sphere for reference (optional)
>>> u = np.linspace(0, 2 * np.pi, 100)
>>> v = np.linspace(0, np.pi, 100)
>>> x = np.outer(np.cos(u), np.sin(v))
>>> y = np.outer(np.sin(u), np.sin(v))
>>> z = np.outer(np.ones(np.size(u)), np.cos(v))
```

(continues on next page)

(continued from previous page)

```
>>> ax.plot_surface(x, y, z, color='y', alpha=0.1)
>>> # plot generator points
>>> ax.scatter(points[:, 0], points[:, 1], points[:, 2], c='b')
>>> # plot Voronoi vertices
>>> ax.scatter(sv.vertices[:, 0], sv.vertices[:, 1], sv.vertices[:, 2],
...           c='g')
>>> # indicate Voronoi regions (as Euclidean polygons)
>>> for region in sv.regions:
...     n = len(region)
...     for i in range(n):
...         start = sv.vertices[region][i]
...         end = sv.vertices[region][(i + 1) % n]
...         result = geometric_slerp(start, end, t_vals)
...         ax.plot(result[..., 0],
...                 result[..., 1],
...                 result[..., 2],
...                 c='k')
>>> ax.azim = 10
>>> ax.elev = 40
>>> _ = ax.set_xticks([])
>>> _ = ax.set_yticks([])
>>> _ = ax.set_zticks([])
>>> fig.set_size_inches(4, 4)
>>> plt.show()
```



Attributes

points	[double array of shape (npoints, ndim)] the points in <i>ndim</i> dimensions to generate the Voronoi diagram from
radius	[double] radius of the sphere
center	[double array of shape (ndim,)] center of the sphere
vertices	[double array of shape (nvertices, ndim)] Voronoi vertices corresponding to points
regions	[list of list of integers of shape (npoints, _)] the n-th entry is a list consisting of the indices of the vertices belonging to the n-th point in points

Methods

<code>calculate_areas(self)</code>	Calculates the areas of the Voronoi regions.
------------------------------------	--

`scipy.spatial.SphericalVoronoi.calculate_areas`

`SphericalVoronoi.calculate_areas` (*self*)

Calculates the areas of the Voronoi regions.

For 2D point sets, the regions are circular arcs. The sum of the areas is $2 * \pi * radius$.

For 3D point sets, the regions are spherical polygons. The sum of the areas is $4 * \pi * radius**2$.

New in version 1.5.0.

Returns

areas [double array of shape (npoints,)] The areas of the Voronoi regions.

`scipy.spatial.HalfspaceIntersection`

class `scipy.spatial.HalfspaceIntersection` (*halfspaces*, *interior_point*, *incremental=False*, *qhull_options=None*)

Halfspace intersections in N dimensions.

New in version 0.19.0.

Parameters

halfspaces [ndarray of floats, shape (nineq, ndim+1)] Stacked Inequalities of the form $Ax + b \leq 0$ in format [A; b]

interior_point [ndarray of floats, shape (ndim,)] Point clearly inside the region defined by halfspaces. Also called a feasible point, it can be obtained by linear programming.

incremental [bool, optional] Allow adding new halfspaces incrementally. This takes up some additional resources.

qhull_options [str, optional] Additional options to pass to Qhull. See Qhull manual for details. (Default: "Qx" for $ndim > 4$ and "" otherwise) Option "H" is always enabled.

Raises

QhullError
Raised when Qhull encounters an error condition, such as geometrical degeneracy when options to resolve are not enabled.

ValueError
Raised if an incompatible array is given as input.

Notes

The intersections are computed using the [Qhull library](#). This reproduces the “qhalf” functionality of Qhull.

References

[Qhull], [1]

Examples

Halfspace intersection of planes forming some polygon

```
>>> from scipy.spatial import HalfspaceIntersection
>>> halfspaces = np.array([[ -1,  0.,  0.],
...                       [ 0., -1.,  0.],
...                       [ 2.,  1., -4.],
...                       [-0.5,  1., -2.]])
>>> feasible_point = np.array([0.5, 0.5])
>>> hs = HalfspaceIntersection(halfspaces, feasible_point)
```

Plot halfspaces as filled regions and intersection points:

```
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> ax = fig.add_subplot(1, 1, 1, aspect='equal')
>>> xlim, ylim = (-1, 3), (-1, 3)
>>> ax.set_xlim(xlim)
>>> ax.set_ylim(ylim)
>>> x = np.linspace(-1, 3, 100)
>>> symbols = ['-', '+', 'x', '*']
>>> signs = [0, 0, -1, -1]
>>> fmt = {"color": None, "edgecolor": "b", "alpha": 0.5}
>>> for h, sym, sign in zip(halfspaces, symbols, signs):
...     hlist = h.tolist()
...     fmt["hatch"] = sym
...     if h[1]== 0:
...         ax.axvline(-h[2]/h[0], label='{}x+{}y+{}=0'.format(*hlist))
...         xi = np.linspace(xlim[sign], -h[2]/h[0], 100)
...         ax.fill_between(xi, ylim[0], ylim[1], **fmt)
...     else:
...         ax.plot(x, (-h[2]-h[0]*x)/h[1], label='{}x+{}y+{}=0'.
→format(*hlist))
...         ax.fill_between(x, (-h[2]-h[0]*x)/h[1], ylim[sign], **fmt)
>>> x, y = zip(*hs.intersections)
>>> ax.plot(x, y, 'o', markersize=8)
```


By default, qhull does not provide with a way to compute an interior point. This can easily be computed using linear programming. Considering halfspaces of the form $Ax + b \leq 0$, solving the linear program:

$$\begin{aligned} & \max y \\ & \text{s.t. } Ax + y||A_i|| \leq -b \end{aligned}$$

With A_i being the rows of A, i.e. the normals to each plane.

Will yield a point x that is furthest inside the convex polyhedron. To be precise, it is the center of the largest hypersphere of radius y inscribed in the polyhedron. This point is called the Chebyshev center of the polyhedron (see [1] 4.3.1, pp148-149). The equations outputted by Qhull are always normalized.

```
>>> from scipy.optimize import linprog
>>> from matplotlib.patches import Circle
>>> norm_vector = np.reshape(np.linalg.norm(halfspaces[:, :-1], axis=1),
...                           (halfspaces.shape[0], 1))
>>> c = np.zeros((halfspaces.shape[1],))
>>> c[-1] = -1
>>> A = np.hstack((halfspaces[:, :-1], norm_vector))
>>> b = - halfspaces[:, -1:]
>>> res = linprog(c, A_ub=A, b_ub=b, bounds=(None, None))
>>> x = res.x[:-1]
>>> y = res.x[-1]
>>> circle = Circle(x, radius=y, alpha=0.3)
>>> ax.add_patch(circle)
>>> plt.legend(bbox_to_anchor=(1.6, 1.0))
>>> plt.show()
```



Attributes

halfspaces [ndarray of double, shape (nineq, ndim+1)] Input halfspaces.

interior_point :ndarray of floats, shape (ndim,)

Input interior point.

intersections

[ndarray of double, shape (ninter, ndim)] Intersections of all halfspaces.

dual_points

[ndarray of double, shape (nineq, ndim)] Dual points of the input halfspaces.

dual_facets

[list of lists of ints] Indices of points forming the (non necessarily simplicial) facets of the dual convex hull.

dual_vertices

[ndarray of ints, shape (nvertices,)] Indices of halfspaces forming the vertices of the dual convex hull. For 2-D convex hulls, the vertices are in counterclockwise order. For other dimensions, they are in input order.

dual_equations

[ndarray of double, shape (nfacet, ndim+1)] [normal, offset] forming the hyperplane equation of the dual facet (see [Qhull documentation](#) for more).

dual_area [float] Area of the dual convex hull

dual_volume [float] Volume of the dual convex hull

Methods

<code>add_halfspaces(halfspaces[, restart])</code>	Process a set of additional new halfspaces.
<code>close()</code>	Finish incremental processing.

scipy.spatial.HalfspaceIntersection.add_halfspaces

`HalfspaceIntersection.add_halfspaces(halfspaces, restart=False)`

Process a set of additional new halfspaces.

Parameters

halfspaces [ndarray] New halfspaces to add. The dimensionality should match that of the initial halfspaces.

restart [bool, optional] Whether to restart processing from scratch, rather than adding halfspaces incrementally.

Raises

QhullError

Raised when Qhull encounters an error condition, such as geometrical degeneracy when options to resolve are not enabled.

See also:

`close`

Notes

You need to specify `incremental=True` when constructing the object to be able to add halfspaces incrementally. Incremental addition of halfspaces is also not possible after `close` has been called.

scipy.spatial.HalfspaceIntersection.close

`HalfspaceIntersection.close()`

Finish incremental processing.

Call this to free resources taken up by Qhull, when using the incremental mode. After calling this, adding more points is no longer possible.

6.26.4 Plotting helpers

<code>delaunay_plot_2d(tri[, ax])</code>	Plot the given Delaunay triangulation in 2-D
<code>convex_hull_plot_2d(hull[, ax])</code>	Plot the given convex hull diagram in 2-D
<code>voronoi_plot_2d(vor[, ax])</code>	Plot the given Voronoi diagram in 2-D

`scipy.spatial.delaunay_plot_2d`

`scipy.spatial.delaunay_plot_2d` (*tri*, *ax=None*)

Plot the given Delaunay triangulation in 2-D

Parameters

tri [scipy.spatial.Delaunay instance] Triangulation to plot
ax [matplotlib.axes.Axes instance, optional] Axes to plot on

Returns

fig [matplotlib.figure.Figure instance] Figure for the plot

See also:

[Delaunay](#)

`matplotlib.pyplot.triplot`

Notes

Requires Matplotlib.

Examples


```
>>> import matplotlib.pyplot as plt
>>> from scipy.spatial import Delaunay, delaunay_plot_2d
```

The Delaunay triangulation of a set of random points:

```
>>> points = np.random.rand(30, 2)
>>> tri = Delaunay(points)
```

Plot it:

```
>>> _ = delaunay_plot_2d(tri)
>>> plt.show()
```



scipy.spatial.convex_hull_plot_2d

`scipy.spatial.convex_hull_plot_2d(hull, ax=None)`

Plot the given convex hull diagram in 2-D

Parameters

hull [scipy.spatial.ConvexHull instance] Convex hull to plot
ax [matplotlib.axes.Axes instance, optional] Axes to plot on

Returns

fig [matplotlib.figure.Figure instance] Figure for the plot

See also:

[*ConvexHull*](#)

Notes

Requires Matplotlib.

Examples


```
>>> import matplotlib.pyplot as plt
>>> from scipy.spatial import ConvexHull, convex_hull_plot_2d
```

The convex hull of a random set of points:

```
>>> points = np.random.rand(30, 2)
>>> hull = ConvexHull(points)
```

Plot it:

```
>>> _ = convex_hull_plot_2d(hull)
>>> plt.show()
```



scipy.spatial.voronoi_plot_2d

`scipy.spatial.voronoi_plot_2d(vor, ax=None, **kw)`
Plot the given Voronoi diagram in 2-D

Parameters

- vor** [scipy.spatial.Voronoi instance] Diagram to plot
- ax** [matplotlib.axes.Axes instance, optional] Axes to plot on
- show_points: bool, optional**
Add the Voronoi points to the plot.
- show_vertices**
[bool, optional] Add the Voronoi vertices to the plot.
- line_colors**
[string, optional] Specifies the line color for polygon boundaries
- line_width** [float, optional] Specifies the line width for polygon boundaries
- line_alpha: float, optional**
Specifies the line alpha for polygon boundaries
- point_size: float, optional**
Specifies the size of points

Returns

- fig** [matplotlib.figure.Figure instance] Figure for the plot

See also:

[Voronoi](#)

Notes

Requires Matplotlib.

Examples

Set of point:

```
>>> import matplotlib.pyplot as plt
>>> points = np.random.rand(10,2) #random
```

Voronoi diagram of the points:


```
>>> from scipy.spatial import Voronoi, voronoi_plot_2d
>>> vor = Voronoi(points)
```

using `voronoi_plot_2d` for visualisation:

```
>>> fig = voronoi_plot_2d(vor)
```


using `voronoi_plot_2d` for visualisation with enhancements:

```
>>> fig = voronoi_plot_2d(vor, show_vertices=False, line_colors='orange',
...                       line_width=2, line_alpha=0.6, point_size=2)
>>> plt.show()
```



See also:

Tutorial



6.26.5 Simplex representation

The simplices (triangles, tetrahedra, etc.) appearing in the Delaunay tessellation (N-D simplices), convex hull facets, and Voronoi ridges (N-1-D simplices) are represented in the following scheme:

```
tess = Delaunay(points)
hull = ConvexHull(points)
voro = Voronoi(points)

# coordinates of the jth vertex of the ith simplex
tess.points[tess.simplices[i, j], :]      # tessellation element
hull.points[hull.simplices[i, j], :]     # convex hull facet
voro.vertices[voro.ridge_vertices[i, j], :] # ridge between Voronoi cells
```

For Delaunay triangulations and convex hulls, the neighborhood structure of the simplices satisfies the condition: `tess.neighbors[i, j]` is the neighboring simplex of the `i`th simplex, opposite to the `j`-vertex. It is `-1` in case of no neighbor.

Convex hull facets also define a hyperplane equation:

```
(hull.equations[i, :-1] * coord).sum() + hull.equations[i, -1] == 0
```

Similar hyperplane equations for the Delaunay triangulation correspond to the convex hull facets on the corresponding N+1-D paraboloid.

The Delaunay triangulation objects offer a method for locating the simplex containing a given point, and barycentric coordinate computations.

Functions

<code>tsearch(tri, xi)</code>	Find simplices containing the given points.
<code>distance_matrix(x, y[, p, threshold])</code>	Compute the distance matrix.
<code>minkowski_distance(x, y[, p])</code>	Compute the L**p distance between two arrays.
<code>minkowski_distance_p(x, y[, p])</code>	Compute the pth power of the L**p distance between two arrays.
<code>procrustes(data1, data2)</code>	Procrustes analysis, a similarity test for two data sets.
<code>geometric_slerp(start, end, t[, toll])</code>	Geometric spherical linear interpolation.

scipy.spatial.tsearch

`scipy.spatial.tsearch` (*tri, xi*)

Find simplices containing the given points. This function does the same thing as `Delaunay.find_simplex`.

New in version 0.9.

See also:

`Delaunay.find_simplex`

Examples

```
>>> import numpy as np
>>> import matplotlib.pyplot as plt
>>> from scipy.spatial import Delaunay, delaunay_plot_2d, tsearch
```

The Delaunay triangulation of a set of random points:

```
>>> pts = np.random.rand(20, 2)
>>> tri = Delaunay(pts)
>>> _ = delaunay_plot_2d(tri)
```

Find the simplices containing a given set of points:

```
>>> loc = np.random.uniform(0.2, 0.8, (5, 2))
>>> s = tsearch(tri, loc)
>>> plt.triplot(pts[:, 0], pts[:, 1], tri.simplices[s], 'b-', mask=s==-1)
>>> plt.scatter(loc[:, 0], loc[:, 1], c='r', marker='x')
>>> plt.show()
```

scipy.spatial.distance_matrix


`scipy.spatial.distance_matrix` (*x, y, p=2, threshold=1000000*)

Compute the distance matrix.

Returns the matrix of all pair-wise distances.

Parameters

- x** [(M, K) array_like] Matrix of M vectors in K dimensions.
- y** [(N, K) array_like] Matrix of N vectors in K dimensions.
- p** [float, 1 <= p <= infinity] Which Minkowski p-norm to use.
- threshold** [positive int] If $M * N * K > threshold$, algorithm uses a Python loop instead of large temporary arrays.

**Returns**

result [(M, N) ndarray] Matrix containing the distance from every vector in *x* to every vector in *y*.

Examples

```
>>> from scipy.spatial import distance_matrix
>>> distance_matrix([[0,0],[0,1]], [[1,0],[1,1]])
array([[ 1.         ,  1.41421356],
       [ 1.41421356,  1.         ]])
```

scipy.spatial.minkowski_distance

`scipy.spatial.minkowski_distance(x, y, p=2)`

Compute the L^{**p} distance between two arrays.

Parameters

x [(M, K) array_like] Input array.
y [(N, K) array_like] Input array.
p [float, 1 <= p <= infinity] Which Minkowski p-norm to use.

Examples

```
>>> from scipy.spatial import minkowski_distance
>>> minkowski_distance([[0,0],[0,0]], [[1,1],[0,1]])
array([ 1.41421356,  1.         ])
```

scipy.spatial.minkowski_distance_p

`scipy.spatial.minkowski_distance_p(x, y, p=2)`

Compute the p th power of the L^{**p} distance between two arrays.

For efficiency, this function computes the L^{**p} distance but does not extract the p th root. If p is 1 or infinity, this is equal to the actual L^{**p} distance.

Parameters

x	[(M, K) array_like] Input array.
y	[(N, K) array_like] Input array.
p	[float, 1 <= p <= infinity] Which Minkowski p-norm to use.

Examples

```
>>> from scipy.spatial import minkowski_distance_p
>>> minkowski_distance_p([[0, 0], [0, 0]], [[1, 1], [0, 1]])
array([2, 1])
```

scipy.spatial.procrustes

`scipy.spatial.procrustes(data1, data2)`

Procrustes analysis, a similarity test for two data sets.

Each input matrix is a set of points or vectors (the rows of the matrix). The dimension of the space is the number of columns of each matrix. Given two identically sized matrices, procrustes standardizes both such that:

- $tr(AA^T) = 1$.
- Both sets of points are centered around the origin.

Procrustes ([1], [2]) then applies the optimal transform to the second matrix (including scaling/dilation, rotations, and reflections) to minimize $M^2 = \sum (data1 - data2)^2$, or the sum of the squares of the pointwise differences between the two input datasets.

This function was not designed to handle datasets with different numbers of datapoints (rows). If two data sets have different dimensionality (different number of columns), simply add columns of zeros to the smaller of the two.

Parameters

data1	[array_like] Matrix, n rows represent points in k (columns) space <i>data1</i> is the reference data, after it is standardised, the data from <i>data2</i> will be transformed to fit the pattern in <i>data1</i> (must have >1 unique points).
data2	[array_like] n rows of data in k space to be fit to <i>data1</i> . Must be the same shape (numrows, numcols) as <i>data1</i> (must have >1 unique points).

Returns

mtx1	[array_like] A standardized version of <i>data1</i> .
mtx2	[array_like] The orientation of <i>data2</i> that best fits <i>data1</i> . Centered, but not necessarily $tr(AA^T) = 1$.
disparity	[float] M^2 as defined above.

Raises

ValueError

If the input arrays are not two-dimensional. If the shape of the input arrays is different. If the input arrays have zero columns or zero rows.

See also:

`scipy.linalg.orthogonal_procrustes`

`scipy.spatial.distance.directed_hausdorff`

Another similarity test for two data sets

Notes

- The disparity should not depend on the order of the input matrices, but the output matrices will, as only the first output matrix is guaranteed to be scaled such that $\text{tr}(AA^T) = 1$.
- Duplicate data points are generally ok, duplicating a data point will increase its effect on the procrustes fit.
- The disparity scales as the number of points per input matrix.

References

[1], [2]

Examples

```
>>> from scipy.spatial import procrustes
```

The matrix `b` is a rotated, shifted, scaled and mirrored version of `a` here:

```
>>> a = np.array([[1, 3], [1, 2], [1, 1], [2, 1]], 'd')
>>> b = np.array([[4, -2], [4, -4], [4, -6], [2, -6]], 'd')
>>> mtx1, mtx2, disparity = procrustes(a, b)
>>> round(disparity)
0.0
```

`scipy.spatial.geometric_slerp`

`scipy.spatial.geometric_slerp` (*start, end, t, tol=1e-07*)

Geometric spherical linear interpolation.

The interpolation occurs along a unit-radius great circle arc in arbitrary dimensional space.

Parameters

- start** [(n_dimensions,) array-like] Single n-dimensional input coordinate in a 1-D array-like object. *n* must be greater than 1.
- end** [(n_dimensions,) array-like] Single n-dimensional input coordinate in a 1-D array-like object. *n* must be greater than 1.
- t: float or (n_points,) array-like**
A float or array-like of doubles representing interpolation parameters, with values required in the inclusive interval between 0 and 1. A common approach is to generate the array with `np.linspace(0, 1, n_pts)` for linearly spaced points. Ascending, descending, and scrambled orders are permitted.
- tol: float** The absolute tolerance for determining if the start and end coordinates are antipodes.

Returns

- result** [(t.size, D)] An array of doubles containing the interpolated spherical path and including start and end when 0 and 1 *t* are used. The interpolated values should correspond to the same sort order provided in the *t* array. The result may be 1-dimensional if *t* is a float.

Raises**ValueError**

If `start` and `end` are antipodes, not on the unit n-sphere, or for a variety of degenerate conditions.

See also:**`scipy.spatial.transform.Slerp`**

3-D Slerp that works with quaternions

Notes

The implementation is based on the mathematical formula provided in [1], and the first known presentation of this algorithm, derived from study of 4-D geometry, is credited to Glenn Davis in a footnote of the original quaternion Slerp publication by Ken Shoemake [2].

New in version 1.5.0.

References

[1], [2]

Examples


Interpolate four linearly-spaced values on the circumference of a circle spanning 90 degrees:

```
>>> from scipy.spatial import geometric_slerp
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> start = np.array([1, 0])
>>> end = np.array([0, 1])
>>> t_vals = np.linspace(0, 1, 4)
>>> result = geometric_slerp(start,
...                          end,
...                          t_vals)
```

The interpolated results should be at 30 degree intervals recognizable on the unit circle:

```
>>> ax.scatter(result[...,0], result[...,1], c='k')
>>> circle = plt.Circle((0, 0), 1, color='grey')
>>> ax.add_artist(circle)
>>> ax.set_aspect('equal')
>>> plt.show()
```

Attempting to interpolate between antipodes on a circle is ambiguous because there are two possible paths, and on a sphere there are infinite possible paths on the geodesic surface. Nonetheless, one of the ambiguous paths is returned along with a warning:



```
>>> opposite_pole = np.array([-1, 0])
>>> with np.testing.suppress_warnings() as sup:
...     sup.filter(UserWarning)
...     geometric_slerp(start,
...                       opposite_pole,
...                       t_vals)
array([[ 1.00000000e+00,  0.00000000e+00],
       [ 5.00000000e-01,  8.66025404e-01],
       [-5.00000000e-01,  8.66025404e-01],
       [-1.00000000e+00,  1.22464680e-16]])
```

Extend the original example to a sphere and plot interpolation points in 3D:

```
>>> from mpl_toolkits.mplot3d import proj3d
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111, projection='3d')
```

Plot the unit sphere for reference (optional):

```
>>> u = np.linspace(0, 2 * np.pi, 100)
>>> v = np.linspace(0, np.pi, 100)
>>> x = np.outer(np.cos(u), np.sin(v))
>>> y = np.outer(np.sin(u), np.sin(v))
>>> z = np.outer(np.ones(np.size(u)), np.cos(v))
>>> ax.plot_surface(x, y, z, color='y', alpha=0.1)
```

Interpolating over a larger number of points may provide the appearance of a smooth curve on the surface of the sphere, which is also useful for discretized integration calculations on a sphere surface:

```
>>> start = np.array([1, 0, 0])
>>> end = np.array([0, 0, 1])
>>> t_vals = np.linspace(0, 1, 200)
>>> result = geometric_slerp(start,
...                           end,
```


(continues on next page)

(continued from previous page)

```

...                               t_vals)
>>> ax.plot(result[... ,0],
...         result[... ,1],
...         result[... ,2],
...         c='k')
>>> plt.show()

```



6.27 Distance computations (`scipy.spatial.distance`)

6.27.1 Function reference

Distance matrix computation from a collection of raw observation vectors stored in a rectangular array.

<code><i>pdist</i>(X[, metric])</code>	Pairwise distances between observations in n-dimensional space.
<code><i>cdist</i>(XA, XB[, metric])</code>	Compute distance between each pair of the two collections of inputs.
<code><i>squareform</i>(X[, force, checks])</code>	Convert a vector-form distance vector to a square-form distance matrix, and vice-versa.
<code><i>directed_hausdorff</i>(u, v[, seed])</code>	Compute the directed Hausdorff distance between two N-D arrays.

scipy.spatial.distance.pdist

`scipy.spatial.distance.pdist` (*X*, *metric*='euclidean', *args, **kwargs)

Pairwise distances between observations in n-dimensional space.

See Notes for common calling conventions.

Parameters

X	[ndarray] An m by n array of m original observations in an n-dimensional space.
metric	[str or function, optional] The distance metric to use. The distance function can be 'braycurtis', 'canberra', 'chebyshev', 'cityblock', 'correlation', 'cosine', 'dice', 'euclidean', 'hamming', 'jaccard', 'jensenshannon', 'kulsinski', 'mahalanobis', 'matching', 'minkowski', 'rogerstanimoto', 'russellrao', 'seuclidean', 'sokalmichener', 'sokalsneath', 'sqeuclidean', 'yule'.
*args	[tuple. Deprecated.] Additional arguments should be passed as keyword arguments
**kwargs	[dict, optional] Extra arguments to <i>metric</i> : refer to each metric documentation for a list of all possible arguments. Some possible arguments: <i>p</i> : scalar The p-norm to apply for Minkowski, weighted and unweighted. Default: 2. <i>w</i> : ndarray The weight vector for metrics that support weights (e.g., Minkowski). <i>V</i> : ndarray The variance vector for standardized Euclidean. Default: <code>var(X, axis=0, ddof=1)</code> <i>VI</i> : ndarray The inverse of the covariance matrix for Mahalanobis. Default: <code>inv(cov(X.T)).T</code> <i>out</i> : ndarray. The output array If not None, condensed distance matrix Y is stored in this array. Note: metric independent, it will become a regular keyword arg in a future scipy version

Returns

Y	[ndarray] Returns a condensed distance matrix Y. For each <i>i</i> and <i>j</i> (where $i < j < m$), where <i>m</i> is the number of original observations. The metric <code>dist(u=X[i], v=X[j])</code> is computed and stored in entry $m * i + j - ((i + 2) * (i + 1)) // 2$.
----------	--

See also:

squareform

converts between condensed distance matrices and square distance matrices.

Notes

See `squareform` for information on how to calculate the index of this entry or to convert the condensed distance matrix to a redundant square matrix.

The following are common calling conventions.

1. `Y = pdist(X, 'euclidean')`

Computes the distance between *m* points using Euclidean distance (2-norm) as the distance metric between the points. The points are arranged as *m* n-dimensional row vectors in the matrix *X*.

2. `Y = pdist(X, 'minkowski', p=2.)`

Computes the distances using the Minkowski distance $\|u - v\|_p$ (p-norm) where $p \geq 1$.

3. `Y = pdist(X, 'cityblock')`

Computes the city block or Manhattan distance between the points.

4. `Y = pdist(X, 'seuclidean', V=None)`

Computes the standardized Euclidean distance. The standardized Euclidean distance between two n-vectors `u` and `v` is

$$\sqrt{\sum (u_i - v_i)^2 / V[x_i]}$$

`V` is the variance vector; `V[i]` is the variance computed over all the `i`'th components of the points. If not passed, it is automatically computed.

5. `Y = pdist(X, 'sqeuclidean')`

Computes the squared Euclidean distance $\|u - v\|_2^2$ between the vectors.

6. `Y = pdist(X, 'cosine')`

Computes the cosine distance between vectors `u` and `v`,

$$1 - \frac{u \cdot v}{\|u\|_2 \|v\|_2}$$

where $\|*\|_2$ is the 2-norm of its argument `*`, and $u \cdot v$ is the dot product of `u` and `v`.

7. `Y = pdist(X, 'correlation')`

Computes the correlation distance between vectors `u` and `v`. This is

$$1 - \frac{(u - \bar{u}) \cdot (v - \bar{v})}{\|(u - \bar{u})\|_2 \|(v - \bar{v})\|_2}$$

where \bar{v} is the mean of the elements of vector `v`, and $x \cdot y$ is the dot product of `x` and `y`.

8. `Y = pdist(X, 'hamming')`

Computes the normalized Hamming distance, or the proportion of those vector elements between two n-vectors `u` and `v` which disagree. To save memory, the matrix `X` can be of type boolean.

9. `Y = pdist(X, 'jaccard')`

Computes the Jaccard distance between the points. Given two vectors, `u` and `v`, the Jaccard distance is the proportion of those elements `u[i]` and `v[i]` that disagree.

10. `Y = pdist(X, 'chebyshev')`

Computes the Chebyshev distance between the points. The Chebyshev distance between two n-vectors `u` and `v` is the maximum norm-1 distance between their respective elements. More precisely, the distance is given by

$$d(u, v) = \max_i |u_i - v_i|$$

11. `Y = pdist(X, 'canberra')`

Computes the Canberra distance between the points. The Canberra distance between two points `u` and `v` is

$$d(u, v) = \sum_i \frac{|u_i - v_i|}{|u_i| + |v_i|}$$

12. `Y = pdist(X, 'braycurtis')`

Computes the Bray-Curtis distance between the points. The Bray-Curtis distance between two points `u` and `v` is

$$d(u, v) = \frac{\sum_i |u_i - v_i|}{\sum_i |u_i + v_i|}$$

13. `Y = pdist(X, 'mahalanobis', VI=None)`

Computes the Mahalanobis distance between the points. The Mahalanobis distance between two points u and v is $\sqrt{(u-v)(1/V)(u-v)^T}$ where $(1/V)$ (the `VI` variable) is the inverse covariance. If `VI` is not `None`, `VI` will be used as the inverse covariance matrix.

14. `Y = pdist(X, 'yule')`

Computes the Yule distance between each pair of boolean vectors. (see `yule` function documentation)

15. `Y = pdist(X, 'matching')`

Synonym for 'hamming'.

16. `Y = pdist(X, 'dice')`

Computes the Dice distance between each pair of boolean vectors. (see `dice` function documentation)

17. `Y = pdist(X, 'kulsinski')`

Computes the Kulsinski distance between each pair of boolean vectors. (see `kulsinski` function documentation)

18. `Y = pdist(X, 'rogerstanimoto')`

Computes the Rogers-Tanimoto distance between each pair of boolean vectors. (see `rogerstanimoto` function documentation)

19. `Y = pdist(X, 'russellrao')`

Computes the Russell-Rao distance between each pair of boolean vectors. (see `russellrao` function documentation)

20. `Y = pdist(X, 'sokalmichener')`

Computes the Sokal-Michener distance between each pair of boolean vectors. (see `sokalmichener` function documentation)

21. `Y = pdist(X, 'sokalsneath')`

Computes the Sokal-Sneath distance between each pair of boolean vectors. (see `sokalsneath` function documentation)

22. `Y = pdist(X, 'wminkowski', p=2, w=w)`

Computes the weighted Minkowski distance between each pair of vectors. (see `wminkowski` function documentation)

'wminkowski' is deprecated and will be removed in SciPy 1.8.0. Use 'minkowski' instead.

23. `Y = pdist(X, f)`

Computes the distance between all pairs of vectors in `X` using the user supplied 2-arity function `f`. For example, Euclidean distance between the vectors could be computed as follows:

```
dm = pdist(X, lambda u, v: np.sqrt(((u-v)**2).sum()))
```

Note that you should avoid passing a reference to one of the distance functions defined in this library. For example,:

```
dm = pdist(X, sokalsneath)
```

would calculate the pair-wise distances between the vectors in X using the Python function `sokalsneath`. This would result in `sokalsneath` being called $\binom{n}{2}$ times, which is inefficient. Instead, the optimized C version is more efficient, and we call it using the following syntax.:

```
dm = pdist(X, 'sokalsneath')
```

scipy.spatial.distance.cdist

`scipy.spatial.distance.cdist` ($XA, XB, metric='euclidean', *args, **kwargs$)

Compute distance between each pair of the two collections of inputs.

See Notes for common calling conventions.

Parameters

- XA** [ndarray] An m_A by n array of m_A original observations in an n -dimensional space. Inputs are converted to float type.
- XB** [ndarray] An m_B by n array of m_B original observations in an n -dimensional space. Inputs are converted to float type.
- metric** [str or callable, optional] The distance metric to use. If a string, the distance function can be 'braycurtis', 'canberra', 'chebyshev', 'cityblock', 'correlation', 'cosine', 'dice', 'euclidean', 'hamming', 'jaccard', 'jensenshannon', 'kulsinski', 'mahalanobis', 'matching', 'minkowski', 'rogerstanimoto', 'russellrao', 'seuclidean', 'sokalmichener', 'sokalsneath', 'sqeuclidean', 'wminkowski', 'yule'.
- *args** [tuple. Deprecated.] Additional arguments should be passed as keyword arguments
- **kwargs** [dict, optional] Extra arguments to *metric*: refer to each metric documentation for a list of all possible arguments.
Some possible arguments:
 - p** : scalar The p-norm to apply for Minkowski, weighted and unweighted. Default: 2.
 - w** : ndarray The weight vector for metrics that support weights (e.g., Minkowski).
 - V** : ndarray The variance vector for standardized Euclidean. Default: `var(vstack([XA, XB]), axis=0, ddof=1)`
 - VI** : ndarray The inverse of the covariance matrix for Mahalanobis. Default: `inv(cov(vstack([XA, XB].T))).T`
 - out** : ndarray The output array If not None, the distance matrix Y is stored in this array. Note: metric independent, it will become a regular keyword arg in a future scipy version

Returns

- Y** [ndarray] A m_A by m_B distance matrix is returned. For each i and j , the metric `dist(u=XA[i], v=XB[j])` is computed and stored in the ij th entry.

Raises

ValueError

An exception is thrown if XA and XB do not have the same number of columns.

Notes

The following are common calling conventions:

1. `Y = cdist(XA, XB, 'euclidean')`

Computes the distance between m points using Euclidean distance (2-norm) as the distance metric between the points. The points are arranged as m n -dimensional row vectors in the matrix X .

2. `Y = cdist(XA, XB, 'minkowski', p=2.)`

Computes the distances using the Minkowski distance $\|u - v\|_p$ (p -norm) where $p \geq 1$.

3. `Y = cdist(XA, XB, 'cityblock')`

Computes the city block or Manhattan distance between the points.

4. `Y = cdist(XA, XB, 'seuclidean', V=None)`

Computes the standardized Euclidean distance. The standardized Euclidean distance between two n -vectors u and v is

$$\sqrt{\sum (u_i - v_i)^2 / V[x_i]}.$$

V is the variance vector; $V[i]$ is the variance computed over all the i 'th components of the points. If not passed, it is automatically computed.

5. `Y = cdist(XA, XB, 'sqeuclidean')`

Computes the squared Euclidean distance $\|u - v\|_2^2$ between the vectors.

6. `Y = cdist(XA, XB, 'cosine')`

Computes the cosine distance between vectors u and v ,

$$1 - \frac{u \cdot v}{\|u\|_2 \|v\|_2}$$

where $\|* \|_2$ is the 2-norm of its argument $*$, and $u \cdot v$ is the dot product of u and v .

7. `Y = cdist(XA, XB, 'correlation')`

Computes the correlation distance between vectors u and v . This is

$$1 - \frac{(u - \bar{u}) \cdot (v - \bar{v})}{\|(u - \bar{u})\|_2 \|(v - \bar{v})\|_2}$$

where \bar{v} is the mean of the elements of vector v , and $x \cdot y$ is the dot product of x and y .

8. `Y = cdist(XA, XB, 'hamming')`

Computes the normalized Hamming distance, or the proportion of those vector elements between two n -vectors u and v which disagree. To save memory, the matrix X can be of type boolean.

9. `Y = cdist(XA, XB, 'jaccard')`

Computes the Jaccard distance between the points. Given two vectors, u and v , the Jaccard distance is the proportion of those elements $u[i]$ and $v[i]$ that disagree where at least one of them is non-zero.

10. `Y = cdist(XA, XB, 'chebyshev')`

Computes the Chebyshev distance between the points. The Chebyshev distance between two n -vectors u and v is the maximum norm-1 distance between their respective elements. More precisely, the distance is given by

$$d(u, v) = \max_i |u_i - v_i|.$$

11. `Y = cdist(XA, XB, 'canberra')`

Computes the Canberra distance between the points. The Canberra distance between two points u and v is

$$d(u, v) = \sum_i \frac{|u_i - v_i|}{|u_i| + |v_i|}.$$

12. `Y = cdist(XA, XB, 'braycurtis')`

Computes the Bray-Curtis distance between the points. The Bray-Curtis distance between two points u and v is

$$d(u, v) = \frac{\sum_i (|u_i - v_i|)}{\sum_i (|u_i + v_i|)}$$

13. `Y = cdist(XA, XB, 'mahalanobis', VI=None)`

Computes the Mahalanobis distance between the points. The Mahalanobis distance between two points u and v is $\sqrt{(u - v)(1/V)(u - v)^T}$ where $(1/V)$ (the `VI` variable) is the inverse covariance. If `VI` is not `None`, `VI` will be used as the inverse covariance matrix.

14. `Y = cdist(XA, XB, 'yule')`

Computes the Yule distance between the boolean vectors. (see [yule](#) function documentation)

15. `Y = cdist(XA, XB, 'matching')`

Synonym for 'hamming'.

16. `Y = cdist(XA, XB, 'dice')`

Computes the Dice distance between the boolean vectors. (see [dice](#) function documentation)

17. `Y = cdist(XA, XB, 'kulsinski')`

Computes the Kulsinski distance between the boolean vectors. (see [kulsinski](#) function documentation)

18. `Y = cdist(XA, XB, 'rogerstanimoto')`

Computes the Rogers-Tanimoto distance between the boolean vectors. (see [rogerstanimoto](#) function documentation)

19. `Y = cdist(XA, XB, 'russellrao')`

Computes the Russell-Rao distance between the boolean vectors. (see [russellrao](#) function documentation)

20. `Y = cdist(XA, XB, 'sokalmichener')`

Computes the Sokal-Michener distance between the boolean vectors. (see [sokalmichener](#) function documentation)

21. `Y = cdist(XA, XB, 'sokalsneath')`

Computes the Sokal-Sneath distance between the vectors. (see `sokalsneath` function documentation)

22. `Y = cdist(XA, XB, 'wminkowski', p=2., w=w)`

Computes the weighted Minkowski distance between the vectors. (see `wminkowski` function documentation)

'wminkowski' is deprecated and will be removed in SciPy 1.8.0. Use 'minkowski' instead.

23. `Y = cdist(XA, XB, f)`

Computes the distance between all pairs of vectors in X using the user supplied 2-arity function f. For example, Euclidean distance between the vectors could be computed as follows:

```
dm = cdist(XA, XB, lambda u, v: np.sqrt((u-v)**2).sum()))
```

Note that you should avoid passing a reference to one of the distance functions defined in this library. For example,:

```
dm = cdist(XA, XB, sokalsneath)
```

would calculate the pair-wise distances between the vectors in X using the Python function `sokalsneath`. This would result in `sokalsneath` being called $\binom{n}{2}$ times, which is inefficient. Instead, the optimized C version is more efficient, and we call it using the following syntax:

```
dm = cdist(XA, XB, 'sokalsneath')
```

Examples

Find the Euclidean distances between four 2-D coordinates:

```
>>> from scipy.spatial import distance
>>> coords = [(35.0456, -85.2672),
...           (35.1174, -89.9711),
...           (35.9728, -83.9422),
...           (36.1667, -86.7833)]
>>> distance.cdist(coords, coords, 'euclidean')
array([[ 0.         ,  4.7044,  1.6172,  1.8856],
       [ 4.7044,  0.         ,  6.0893,  3.3561],
       [ 1.6172,  6.0893,  0.         ,  2.8477],
       [ 1.8856,  3.3561,  2.8477,  0.         ]])
```

Find the Manhattan distance from a 3-D point to the corners of the unit cube:

```
>>> a = np.array([[0, 0, 0],
...               [0, 0, 1],
...               [0, 1, 0],
...               [0, 1, 1],
...               [1, 0, 0],
...               [1, 0, 1],
...               [1, 1, 0],
...               [1, 1, 1]])
>>> b = np.array([[ 0.1,  0.2,  0.4]])
>>> distance.cdist(a, b, 'cityblock')
array([[ 0.7],
```

(continues on next page)

(continued from previous page)

```
[ 0.9],
 [ 1.3],
 [ 1.5],
 [ 1.5],
 [ 1.7],
 [ 2.1],
 [ 2.3]])
```

scipy.spatial.distance.squareform

`scipy.spatial.distance.squareform(X, force='no', checks=True)`

Convert a vector-form distance vector to a square-form distance matrix, and vice-versa.

Parameters

X	[ndarray] Either a condensed or redundant distance matrix.
force	[str, optional] As with MATLAB(TM), if force is equal to 'tovector' or 'tomatrix', the input will be treated as a distance matrix or distance vector respectively.
checks	[bool, optional] If set to False, no checks will be made for matrix symmetry nor zero diagonals. This is useful if it is known that $X - X.T$ is small and $\text{diag}(X)$ is close to zero. These values are ignored any way so they do not disrupt the squareform transformation.

Returns

Y	[ndarray] If a condensed distance matrix is passed, a redundant one is returned, or if a redundant one is passed, a condensed distance matrix is returned.
----------	--

Notes

1. $v = \text{squareform}(X)$

Given a square n -by- n symmetric distance matrix X , $v = \text{squareform}(X)$ returns a $n * (n-1) / 2$ (i.e. binomial coefficient n choose 2) sized vector v where $v[\binom{n}{2} - \binom{n-i}{2} + (j-i-1)]$ is the distance between distinct points i and j . If X is non-square or asymmetric, an error is raised.

2. $X = \text{squareform}(v)$

Given a $n * (n-1) / 2$ sized vector v for some integer $n \geq 1$ encoding distances as described, $X = \text{squareform}(v)$ returns a n -by- n distance matrix X . The $X[i, j]$ and $X[j, i]$ values are set to $v[\binom{n}{2} - \binom{n-i}{2} + (j-i-1)]$ and all diagonal elements are zero.

In SciPy 0.19.0, `squareform` stopped casting all input types to float64, and started returning arrays of the same dtype as the input.

scipy.spatial.distance.directed_hausdorff

`scipy.spatial.distance.directed_hausdorff(u, v, seed=0)`

Compute the directed Hausdorff distance between two N-D arrays.

Distances between pairs are calculated using a Euclidean metric.

Parameters

u [(M,N) ndarray] Input array.
v [(O,N) ndarray] Input array.
seed [int or None] Local `numpy.random.RandomState` seed. Default is 0, a random shuffling of `u` and `v` that guarantees reproducibility.

Returns

d [double] The directed Hausdorff distance between arrays `u` and `v`,
index_1 [int] index of point contributing to Hausdorff pair in `u`
index_2 [int] index of point contributing to Hausdorff pair in `v`

Raises

ValueError
 An exception is thrown if `u` and `v` do not have the same number of columns.

See also:

[*scipy.spatial.procrustes*](#)

Another similarity test for two data sets

Notes

Uses the early break technique and the random sampling approach described by [1]. Although worst-case performance is $O(m * o)$ (as with the brute force algorithm), this is unlikely in practice as the input data would have to require the algorithm to explore every single point interaction, and after the algorithm shuffles the input points at that. The best case performance is $O(m)$, which is satisfied by selecting an inner loop distance that is less than `cmax` and leads to an early break as often as possible. The authors have formally shown that the average runtime is closer to $O(m)$.

New in version 0.19.0.

References

[1]

Examples

Find the directed Hausdorff distance between two 2-D arrays of coordinates:

```
>>> from scipy.spatial.distance import directed_hausdorff
>>> u = np.array([(1.0, 0.0),
...              (0.0, 1.0),
...              (-1.0, 0.0),
...              (0.0, -1.0)])
>>> v = np.array([(2.0, 0.0),
```

(continues on next page)

(continued from previous page)

```
...      (0.0, 2.0),
...      (-2.0, 0.0),
...      (0.0, -4.0)]])
```

```
>>> directed_hausdorff(u, v)[0]
2.23606797749979
>>> directed_hausdorff(v, u)[0]
3.0
```

Find the general (symmetric) Hausdorff distance between two 2-D arrays of coordinates:

```
>>> max(directed_hausdorff(u, v)[0], directed_hausdorff(v, u)[0])
3.0
```

Find the indices of the points that generate the Hausdorff distance (the Hausdorff pair):

```
>>> directed_hausdorff(v, u)[1:]
(3, 3)
```

Predicates for checking the validity of distance matrices, both condensed and redundant. Also contained in this module are functions for computing the number of observations in a distance matrix.

<code>is_valid_dm(D[, tol, throw, name, warning])</code>	Return True if input array is a valid distance matrix.
<code>is_valid_y(y[, warning, throw, name])</code>	Return True if the input array is a valid condensed distance matrix.
<code>num_obs_dm(d)</code>	Return the number of original observations that correspond to a square, redundant distance matrix.
<code>num_obs_y(Y)</code>	Return the number of original observations that correspond to a condensed distance matrix.

scipy.spatial.distance.is_valid_dm

`scipy.spatial.distance.is_valid_dm(D, tol=0.0, throw=False, name='D', warning=False)`

Return True if input array is a valid distance matrix.

Distance matrices must be 2-dimensional numpy arrays. They must have a zero-diagonal, and they must be symmetric.

Parameters

- D** [ndarray] The candidate object to test for validity.
- tol** [float, optional] The distance matrix should be symmetric. *tol* is the maximum difference between entries *i j* and *j i* for the distance metric to be considered symmetric.
- throw** [bool, optional] An exception is thrown if the distance matrix passed is not valid.
- name** [str, optional] The name of the variable to checked. This is useful if *throw* is set to True so the offending variable can be identified in the exception message when an exception is thrown.
- warning** [bool, optional] Instead of throwing an exception, a warning message is raised.

Returns

- valid** [bool] True if the variable *D* passed is a valid distance matrix.

Notes

Small numerical differences in D and $D.T$ and non-zerosness of the diagonal are ignored if they are within the tolerance specified by *tol*.

scipy.spatial.distance.is_valid_y

`scipy.spatial.distance.is_valid_y(y, warning=False, throw=False, name=None)`

Return True if the input array is a valid condensed distance matrix.

Condensed distance matrices must be 1-dimensional numpy arrays. Their length must be a binomial coefficient $\binom{n}{2}$ for some positive integer n .

Parameters

- y** [ndarray] The condensed distance matrix.
- warning** [bool, optional] Invokes a warning if the variable passed is not a valid condensed distance matrix. The warning message explains why the distance matrix is not valid. *name* is used when referencing the offending variable.
- throw** [bool, optional] Throws an exception if the variable passed is not a valid condensed distance matrix.
- name** [bool, optional] Used when referencing the offending variable in the warning or exception message.

scipy.spatial.distance.num_obs_dm

`scipy.spatial.distance.num_obs_dm(d)`

Return the number of original observations that correspond to a square, redundant distance matrix.

Parameters

- d** [ndarray] The target distance matrix.

Returns

- num_obs_dm** [int] The number of observations in the redundant distance matrix.

scipy.spatial.distance.num_obs_y

`scipy.spatial.distance.num_obs_y(Y)`

Return the number of original observations that correspond to a condensed distance matrix.

Parameters

- Y** [ndarray] Condensed distance matrix.

Returns

- n** [int] The number of observations in the condensed distance matrix *Y*.

Distance functions between two numeric vectors u and v . Computing distances over a large collection of vectors is inefficient for these functions. Use `pdist` for this purpose.

braycurtis($u, v[, w]$)

Compute the Bray-Curtis distance between two 1-D arrays.

continues on next page

Table 215 – continued from previous page

<code>canberra(u, v[, w])</code>	Compute the Canberra distance between two 1-D arrays.
<code>chebyshev(u, v[, w])</code>	Compute the Chebyshev distance.
<code>cityblock(u, v[, w])</code>	Compute the City Block (Manhattan) distance.
<code>correlation(u, v[, w, centered])</code>	Compute the correlation distance between two 1-D arrays.
<code>cosine(u, v[, w])</code>	Compute the Cosine distance between 1-D arrays.
<code>euclidean(u, v[, w])</code>	Computes the Euclidean distance between two 1-D arrays.
<code>jensenshannon(p, q[, base])</code>	Compute the Jensen-Shannon distance (metric) between two 1-D probability arrays.
<code>mahalanobis(u, v, VI)</code>	Compute the Mahalanobis distance between two 1-D arrays.
<code>minkowski(u, v[, p, w])</code>	Compute the Minkowski distance between two 1-D arrays.
<code>seuclidean(u, v, V)</code>	Return the standardized Euclidean distance between two 1-D arrays.
<code>squclidean(u, v[, w])</code>	Compute the squared Euclidean distance between two 1-D arrays.
<code>wminkowski(u, v, p, w)</code>	Compute the weighted Minkowski distance between two 1-D arrays.

scipy.spatial.distance.braycurtis

`scipy.spatial.distance.braycurtis(u, v, w=None)`

Compute the Bray-Curtis distance between two 1-D arrays.

Bray-Curtis distance is defined as

$$\sum |u_i - v_i| / \sum |u_i + v_i|$$

The Bray-Curtis distance is in the range [0, 1] if all coordinates are positive, and is undefined if the inputs are of length zero.

Parameters

- u** [(N,) array_like] Input array.
- v** [(N,) array_like] Input array.
- w** [(N,) array_like, optional] The weights for each value in *u* and *v*. Default is None, which gives each value a weight of 1.0

Returns

- braycurtis** [double] The Bray-Curtis distance between 1-D arrays *u* and *v*.

Examples

```
>>> from scipy.spatial import distance
>>> distance.braycurtis([1, 0, 0], [0, 1, 0])
1.0
>>> distance.braycurtis([1, 1, 0], [0, 1, 0])
0.33333333333333331
```


scipy.spatial.distance.canberra

`scipy.spatial.distance.canberra` ($u, v, w=None$)

Compute the Canberra distance between two 1-D arrays.

The Canberra distance is defined as

$$d(u, v) = \sum_i \frac{|u_i - v_i|}{|u_i| + |v_i|}.$$

Parameters

- u** [(N,) array_like] Input array.
- v** [(N,) array_like] Input array.
- w** [(N,) array_like, optional] The weights for each value in u and v . Default is `None`, which gives each value a weight of 1.0

Returns

- canberra** [double] The Canberra distance between vectors u and v .

Notes

When $u[i]$ and $v[i]$ are 0 for given i , then the fraction $0/0 = 0$ is used in the calculation.

Examples

```
>>> from scipy.spatial import distance
>>> distance.canberra([1, 0, 0], [0, 1, 0])
2.0
>>> distance.canberra([1, 1, 0], [0, 1, 0])
1.0
```

scipy.spatial.distance.chebyshev

`scipy.spatial.distance.chebyshev` ($u, v, w=None$)

Compute the Chebyshev distance.

Computes the Chebyshev distance between two 1-D arrays u and v , which is defined as

$$\max_i |u_i - v_i|.$$

Parameters

- u** [(N,) array_like] Input vector.
- v** [(N,) array_like] Input vector.
- w** [(N,) array_like, optional] Unused, as ‘max’ is a weightless operation. Here for API consistency.

Returns

- chebyshev** [double] The Chebyshev distance between vectors u and v .

Examples

```
>>> from scipy.spatial import distance
>>> distance.chebyshev([1, 0, 0], [0, 1, 0])
1
>>> distance.chebyshev([1, 1, 0], [0, 1, 0])
1
```

scipy.spatial.distance.cityblock

`scipy.spatial.distance.cityblock` (*u*, *v*, *w=None*)

Compute the City Block (Manhattan) distance.

Computes the Manhattan distance between two 1-D arrays *u* and *v*, which is defined as

$$\sum_i |u_i - v_i|.$$

Parameters

- u** [(N,) array_like] Input array.
- v** [(N,) array_like] Input array.
- w** [(N,) array_like, optional] The weights for each value in *u* and *v*. Default is None, which gives each value a weight of 1.0

Returns

- cityblock** [double] The City Block (Manhattan) distance between vectors *u* and *v*.

Examples

```
>>> from scipy.spatial import distance
>>> distance.cityblock([1, 0, 0], [0, 1, 0])
2
>>> distance.cityblock([1, 0, 0], [0, 2, 0])
3
>>> distance.cityblock([1, 0, 0], [1, 1, 0])
1
```

scipy.spatial.distance.correlation

`scipy.spatial.distance.correlation` (*u*, *v*, *w=None*, *centered=True*)

Compute the correlation distance between two 1-D arrays.

The correlation distance between *u* and *v*, is defined as

$$1 - \frac{(u - \bar{u}) \cdot (v - \bar{v})}{\| (u - \bar{u}) \|_2 \| (v - \bar{v}) \|_2}$$

where \bar{u} is the mean of the elements of *u* and $x \cdot y$ is the dot product of *x* and *y*.

Parameters

- u** [(N,) array_like] Input array.
- v** [(N,) array_like] Input array.

w [(N,) array_like, optional] The weights for each value in u and v . Default is None, which gives each value a weight of 1.0

centered [bool, optional] If True, u and v will be centered. Default is True.

Returns**correlation**

[double] The correlation distance between 1-D array u and v .

scipy.spatial.distance.cosine

`scipy.spatial.distance.cosine` (u , v , $w=None$)

Compute the Cosine distance between 1-D arrays.

The Cosine distance between u and v , is defined as

$$1 - \frac{u \cdot v}{\|u\|_2 \|v\|_2}$$

where $u \cdot v$ is the dot product of u and v .

Parameters

u [(N,) array_like] Input array.

v [(N,) array_like] Input array.

w [(N,) array_like, optional] The weights for each value in u and v . Default is None, which gives each value a weight of 1.0

Returns

cosine [double] The Cosine distance between vectors u and v .

Examples

```
>>> from scipy.spatial import distance
>>> distance.cosine([1, 0, 0], [0, 1, 0])
1.0
>>> distance.cosine([100, 0, 0], [0, 1, 0])
1.0
>>> distance.cosine([1, 1, 0], [0, 1, 0])
0.29289321881345254
```

scipy.spatial.distance.euclidean

`scipy.spatial.distance.euclidean` (u , v , $w=None$)

Computes the Euclidean distance between two 1-D arrays.

The Euclidean distance between 1-D arrays u and v , is defined as

$$\|u - v\|_2 \left(\sum (w_i |(u_i - v_i)|^2) \right)^{1/2}$$

Parameters

u [(N,) array_like] Input array.

v [(N,) array_like] Input array.

w [(N,) array_like, optional] The weights for each value in u and v . Default is None, which gives each value a weight of 1.0

Returns

euclidean [double] The Euclidean distance between vectors u and v .

Examples

```
>>> from scipy.spatial import distance
>>> distance.euclidean([1, 0, 0], [0, 1, 0])
1.4142135623730951
>>> distance.euclidean([1, 1, 0], [0, 1, 0])
1.0
```

scipy.spatial.distance.jensenshannon

`scipy.spatial.distance.jensenshannon` ($p, q, base=None$)

Compute the Jensen-Shannon distance (metric) between two 1-D probability arrays. This is the square root of the Jensen-Shannon divergence.

The Jensen-Shannon distance between two probability vectors p and q is defined as,

$$\sqrt{\frac{D(p \parallel m) + D(q \parallel m)}{2}}$$

where m is the pointwise mean of p and q and D is the Kullback-Leibler divergence.

This routine will normalize p and q if they don't sum to 1.0.

Parameters

p [(N,) array_like] left probability vector
q [(N,) array_like] right probability vector
base [double, optional] the base of the logarithm used to compute the output if not given, then the routine uses the default base of `scipy.stats.entropy`.

Returns

js [double] The Jensen-Shannon distance between p and q

New in version 1.2.0: ..

Examples

```
>>> from scipy.spatial import distance
>>> distance.jensenshannon([1.0, 0.0, 0.0], [0.0, 1.0, 0.0], 2.0)
1.0
>>> distance.jensenshannon([1.0, 0.0], [0.5, 0.5])
0.46450140402245893
>>> distance.jensenshannon([1.0, 0.0, 0.0], [1.0, 0.0, 0.0])
0.0
```

scipy.spatial.distance.mahalanobis

`scipy.spatial.distance.mahalanobis` (*u*, *v*, *VI*)

Compute the Mahalanobis distance between two 1-D arrays.

The Mahalanobis distance between 1-D arrays *u* and *v*, is defined as

$$\sqrt{(u - v)V^{-1}(u - v)^T}$$

where *V* is the covariance matrix. Note that the argument *VI* is the inverse of *V*.

Parameters

u [(N,) array_like] Input array.
v [(N,) array_like] Input array.
VI [ndarray] The inverse of the covariance matrix.

Returns

mahalanobis
 [double] The Mahalanobis distance between vectors *u* and *v*.

Examples

```
>>> from scipy.spatial import distance
>>> iv = [[1, 0.5, 0.5], [0.5, 1, 0.5], [0.5, 0.5, 1]]
>>> distance.mahalanobis([1, 0, 0], [0, 1, 0], iv)
1.0
>>> distance.mahalanobis([0, 2, 0], [0, 1, 0], iv)
1.0
>>> distance.mahalanobis([2, 0, 0], [0, 1, 0], iv)
1.7320508075688772
```

scipy.spatial.distance.minkowski

`scipy.spatial.distance.minkowski` (*u*, *v*, *p=2*, *w=None*)

Compute the Minkowski distance between two 1-D arrays.

The Minkowski distance between 1-D arrays *u* and *v*, is defined as

$$\|u - v\|_p = \left(\sum |u_i - v_i|^p \right)^{1/p}.$$

$$\left(\sum w_i (|u_i - v_i|^p) \right)^{1/p}.$$

Parameters

u [(N,) array_like] Input array.
v [(N,) array_like] Input array.
p [int] The order of the norm of the difference $\|u - v\|_p$.
w [(N,) array_like, optional] The weights for each value in *u* and *v*. Default is None, which gives each value a weight of 1.0

Returns

minkowski
 [double] The Minkowski distance between vectors *u* and *v*.

Examples

```
>>> from scipy.spatial import distance
>>> distance.minkowski([1, 0, 0], [0, 1, 0], 1)
2.0
>>> distance.minkowski([1, 0, 0], [0, 1, 0], 2)
1.4142135623730951
>>> distance.minkowski([1, 0, 0], [0, 1, 0], 3)
1.2599210498948732
>>> distance.minkowski([1, 1, 0], [0, 1, 0], 1)
1.0
>>> distance.minkowski([1, 1, 0], [0, 1, 0], 2)
1.0
>>> distance.minkowski([1, 1, 0], [0, 1, 0], 3)
1.0
```

scipy.spatial.distance.seuclidean

`scipy.spatial.distance.seuclidean` (u, v, V)

Return the standardized Euclidean distance between two 1-D arrays.

The standardized Euclidean distance between u and v .

Parameters

u [(N,) array_like] Input array.
v [(N,) array_like] Input array.
V [(N,) array_like] V is an 1-D array of component variances. It is usually computed among a larger collection vectors.

Returns

seuclidean [double] The standardized Euclidean distance between vectors u and v .

Examples

```
>>> from scipy.spatial import distance
>>> distance.seuclidean([1, 0, 0], [0, 1, 0], [0.1, 0.1, 0.1])
4.4721359549995796
>>> distance.seuclidean([1, 0, 0], [0, 1, 0], [1, 0.1, 0.1])
3.3166247903553998
>>> distance.seuclidean([1, 0, 0], [0, 1, 0], [10, 0.1, 0.1])
3.1780497164141406
```

scipy.spatial.distance.sqeuclidean

`scipy.spatial.distance.sqeuclidean` (*u*, *v*, *w=None*)

Compute the squared Euclidean distance between two 1-D arrays.

The squared Euclidean distance between *u* and *v* is defined as

$$\|u - v\|_2^2 \\ \left(\sum (w_i |u_i - v_i|^2) \right)$$

Parameters

- u** [(N,) array_like] Input array.
- v** [(N,) array_like] Input array.
- w** [(N,) array_like, optional] The weights for each value in *u* and *v*. Default is None, which gives each value a weight of 1.0

Returns

- sqeuclidean** [double] The squared Euclidean distance between vectors *u* and *v*.

Examples

```
>>> from scipy.spatial import distance
>>> distance.sqeuclidean([1, 0, 0], [0, 1, 0])
2.0
>>> distance.sqeuclidean([1, 1, 0], [0, 1, 0])
1.0
```

scipy.spatial.distance.wminkowski

`scipy.spatial.distance.wminkowski` (*u*, *v*, *p*, *w*)

Compute the weighted Minkowski distance between two 1-D arrays.

The weighted Minkowski distance between *u* and *v*, defined as

$$\left(\sum (|w_i(u_i - v_i)|^p) \right)^{1/p}.$$

Parameters

- u** [(N,) array_like] Input array.
- v** [(N,) array_like] Input array.
- p** [int] The order of the norm of the difference $\|u - v\|_p$.
- w** [(N,) array_like] The weight vector.

Returns

- wminkowski** [double] The weighted Minkowski distance between vectors *u* and *v*.

Notes

`wminkowski` is deprecated and will be removed in SciPy 1.8.0. Use `minkowski` with the `w` argument instead.

Examples

```
>>> from scipy.spatial import distance
>>> distance.wminkowski([1, 0, 0], [0, 1, 0], 1, np.ones(3))
2.0
>>> distance.wminkowski([1, 0, 0], [0, 1, 0], 2, np.ones(3))
1.4142135623730951
>>> distance.wminkowski([1, 0, 0], [0, 1, 0], 3, np.ones(3))
1.2599210498948732
>>> distance.wminkowski([1, 1, 0], [0, 1, 0], 1, np.ones(3))
1.0
>>> distance.wminkowski([1, 1, 0], [0, 1, 0], 2, np.ones(3))
1.0
>>> distance.wminkowski([1, 1, 0], [0, 1, 0], 3, np.ones(3))
1.0
```

Distance functions between two boolean vectors (representing sets) u and v . As in the case of numerical vectors, `pdist` is more efficient for computing the distances between all pairs.

<code>dice(u, v[, w])</code>	Compute the Dice dissimilarity between two boolean 1-D arrays.
<code>hamming(u, v[, w])</code>	Compute the Hamming distance between two 1-D arrays.
<code>jaccard(u, v[, w])</code>	Compute the Jaccard-Needham dissimilarity between two boolean 1-D arrays.
<code>kulsinski(u, v[, w])</code>	Compute the Kulsinski dissimilarity between two boolean 1-D arrays.
<code>rogerstanimoto(u, v[, w])</code>	Compute the Rogers-Tanimoto dissimilarity between two boolean 1-D arrays.
<code>russellrao(u, v[, w])</code>	Compute the Russell-Rao dissimilarity between two boolean 1-D arrays.
<code>sokalmichener(u, v[, w])</code>	Compute the Sokal-Michener dissimilarity between two boolean 1-D arrays.
<code>sokalsneath(u, v[, w])</code>	Compute the Sokal-Sneath dissimilarity between two boolean 1-D arrays.
<code>yule(u, v[, w])</code>	Compute the Yule dissimilarity between two boolean 1-D arrays.

scipy.spatial.distance.dice

`scipy.spatial.distance.dice(u, v, w=None)`

Compute the Dice dissimilarity between two boolean 1-D arrays.

The Dice dissimilarity between u and v , is

$$\frac{c_{TF} + c_{FT}}{2c_{TT} + c_{FT} + c_{TF}}$$

where c_{ij} is the number of occurrences of $u[k] = i$ and $v[k] = j$ for $k < n$.

Parameters

- u** [(N,) ndarray, bool] Input 1-D array.
- v** [(N,) ndarray, bool] Input 1-D array.
- w** [(N,) array_like, optional] The weights for each value in *u* and *v*. Default is None, which gives each value a weight of 1.0

Returns

- dice** [double] The Dice dissimilarity between 1-D arrays *u* and *v*.

Examples

```
>>> from scipy.spatial import distance
>>> distance.dice([1, 0, 0], [0, 1, 0])
1.0
>>> distance.dice([1, 0, 0], [1, 1, 0])
0.3333333333333333
>>> distance.dice([1, 0, 0], [2, 0, 0])
-0.3333333333333333
```

scipy.spatial.distance.hamming

`scipy.spatial.distance.hamming` (*u*, *v*, *w=None*)

Compute the Hamming distance between two 1-D arrays.

The Hamming distance between 1-D arrays *u* and *v*, is simply the proportion of disagreeing components in *u* and *v*. If *u* and *v* are boolean vectors, the Hamming distance is

$$\frac{c_{01} + c_{10}}{n}$$

where c_{ij} is the number of occurrences of $u[k] = i$ and $v[k] = j$ for $k < n$.

Parameters

- u** [(N,) array_like] Input array.
- v** [(N,) array_like] Input array.
- w** [(N,) array_like, optional] The weights for each value in *u* and *v*. Default is None, which gives each value a weight of 1.0

Returns

- hamming** [double] The Hamming distance between vectors *u* and *v*.

Examples

```
>>> from scipy.spatial import distance
>>> distance.hamming([1, 0, 0], [0, 1, 0])
0.6666666666666666
>>> distance.hamming([1, 0, 0], [1, 1, 0])
0.3333333333333333
>>> distance.hamming([1, 0, 0], [2, 0, 0])
0.3333333333333333
>>> distance.hamming([1, 0, 0], [3, 0, 0])
0.3333333333333333
```

scipy.spatial.distance.jaccard`scipy.spatial.distance.jaccard(u, v, w=None)`

Compute the Jaccard-Needham dissimilarity between two boolean 1-D arrays.

The Jaccard-Needham dissimilarity between 1-D boolean arrays u and v , is defined as

$$\frac{c_{TF} + c_{FT}}{c_{TT} + c_{FT} + c_{TF}}$$

where c_{ij} is the number of occurrences of $u[k] = i$ and $v[k] = j$ for $k < n$.**Parameters**

u [(N,) array_like, bool] Input array.
v [(N,) array_like, bool] Input array.
w [(N,) array_like, optional] The weights for each value in u and v . Default is None, which gives each value a weight of 1.0

Returns

jaccard [double] The Jaccard distance between vectors u and v .

NotesWhen both u and v lead to a $0/0$ division i.e. there is no overlap between the items in the vectors the returned distance is 0. See the Wikipedia page on the Jaccard index [1], and this paper [2].Changed in version 1.2.0: Previously, when u and v lead to a $0/0$ division, the function would return NaN. This was changed to return 0 instead.**References**

[1], [2]

Examples

```
>>> from scipy.spatial import distance
>>> distance.jaccard([1, 0, 0], [0, 1, 0])
1.0
>>> distance.jaccard([1, 0, 0], [1, 1, 0])
0.5
>>> distance.jaccard([1, 0, 0], [1, 2, 0])
0.5
>>> distance.jaccard([1, 0, 0], [1, 1, 1])
0.66666666666666663
```

scipy.spatial.distance.kulsinski

`scipy.spatial.distance.kulsinski` (*u*, *v*, *w=None*)

Compute the Kulsinski dissimilarity between two boolean 1-D arrays.

The Kulsinski dissimilarity between two boolean 1-D arrays *u* and *v*, is defined as

$$\frac{c_{TF} + c_{FT} - c_{TT} + n}{c_{FT} + c_{TF} + n}$$

where c_{ij} is the number of occurrences of $u[k] = i$ and $v[k] = j$ for $k < n$.

Parameters

- u** [(N,) array_like, bool] Input array.
- v** [(N,) array_like, bool] Input array.
- w** [(N,) array_like, optional] The weights for each value in *u* and *v*. Default is None, which gives each value a weight of 1.0

Returns

- kulsinski** [double] The Kulsinski distance between vectors *u* and *v*.

Examples

```
>>> from scipy.spatial import distance
>>> distance.kulsinski([1, 0, 0], [0, 1, 0])
1.0
>>> distance.kulsinski([1, 0, 0], [1, 1, 0])
0.75
>>> distance.kulsinski([1, 0, 0], [2, 1, 0])
0.33333333333333331
>>> distance.kulsinski([1, 0, 0], [3, 1, 0])
-0.5
```

scipy.spatial.distance.rogerstanimoto

`scipy.spatial.distance.rogerstanimoto` (*u*, *v*, *w=None*)

Compute the Rogers-Tanimoto dissimilarity between two boolean 1-D arrays.

The Rogers-Tanimoto dissimilarity between two boolean 1-D arrays *u* and *v*, is defined as

$$\frac{R}{c_{TT} + c_{FF} + R}$$

where c_{ij} is the number of occurrences of $u[k] = i$ and $v[k] = j$ for $k < n$ and $R = 2(c_{TF} + c_{FT})$.

Parameters

- u** [(N,) array_like, bool] Input array.
- v** [(N,) array_like, bool] Input array.
- w** [(N,) array_like, optional] The weights for each value in *u* and *v*. Default is None, which gives each value a weight of 1.0

Returns

- rogerstanimoto** [double] The Rogers-Tanimoto dissimilarity between vectors *u* and *v*.

Examples

```
>>> from scipy.spatial import distance
>>> distance.rogerstanimoto([1, 0, 0], [0, 1, 0])
0.8
>>> distance.rogerstanimoto([1, 0, 0], [1, 1, 0])
0.5
>>> distance.rogerstanimoto([1, 0, 0], [2, 0, 0])
-1.0
```

scipy.spatial.distance.russellrao

`scipy.spatial.distance.russellrao` (*u*, *v*, *w=None*)

Compute the Russell-Rao dissimilarity between two boolean 1-D arrays.

The Russell-Rao dissimilarity between two boolean 1-D arrays, *u* and *v*, is defined as

$$\frac{n - c_{TT}}{n}$$

where c_{ij} is the number of occurrences of $u[k] = i$ and $v[k] = j$ for $k < n$.

Parameters

- u** [(N,) array_like, bool] Input array.
- v** [(N,) array_like, bool] Input array.
- w** [(N,) array_like, optional] The weights for each value in *u* and *v*. Default is None, which gives each value a weight of 1.0

Returns

- russellrao** [double] The Russell-Rao dissimilarity between vectors *u* and *v*.

Examples

```
>>> from scipy.spatial import distance
>>> distance.russellrao([1, 0, 0], [0, 1, 0])
1.0
>>> distance.russellrao([1, 0, 0], [1, 1, 0])
0.6666666666666666
>>> distance.russellrao([1, 0, 0], [2, 0, 0])
0.3333333333333333
```

scipy.spatial.distance.sokalmichener

`scipy.spatial.distance.sokalmichener` (*u*, *v*, *w=None*)

Compute the Sokal-Michener dissimilarity between two boolean 1-D arrays.

The Sokal-Michener dissimilarity between boolean 1-D arrays *u* and *v*, is defined as

$$\frac{R}{S + R}$$

where c_{ij} is the number of occurrences of $u[k] = i$ and $v[k] = j$ for $k < n$, $R = 2 * (c_{TF} + c_{FT})$ and $S = c_{FF} + c_{TT}$.

Parameters

- u** [(N,) array_like, bool] Input array.
- v** [(N,) array_like, bool] Input array.
- w** [(N,) array_like, optional] The weights for each value in *u* and *v*. Default is None, which gives each value a weight of 1.0

Returns**sokalmichener**

[double] The Sokal-Michener dissimilarity between vectors *u* and *v*.

Examples

```
>>> from scipy.spatial import distance
>>> distance.sokalmichener([1, 0, 0], [0, 1, 0])
0.8
>>> distance.sokalmichener([1, 0, 0], [1, 1, 0])
0.5
>>> distance.sokalmichener([1, 0, 0], [2, 0, 0])
-1.0
```

scipy.spatial.distance.sokalsneath

`scipy.spatial.distance.sokalsneath(u, v, w=None)`

Compute the Sokal-Sneath dissimilarity between two boolean 1-D arrays.

The Sokal-Sneath dissimilarity between *u* and *v*,

$$\frac{R}{c_{TT} + R}$$

where c_{ij} is the number of occurrences of $u[k] = i$ and $v[k] = j$ for $k < n$ and $R = 2(c_{TF} + c_{FT})$.

Parameters

- u** [(N,) array_like, bool] Input array.
- v** [(N,) array_like, bool] Input array.
- w** [(N,) array_like, optional] The weights for each value in *u* and *v*. Default is None, which gives each value a weight of 1.0

Returns**sokalsneath**

[double] The Sokal-Sneath dissimilarity between vectors *u* and *v*.

Examples

```
>>> from scipy.spatial import distance
>>> distance.sokalsneath([1, 0, 0], [0, 1, 0])
1.0
>>> distance.sokalsneath([1, 0, 0], [1, 1, 0])
0.6666666666666666
>>> distance.sokalsneath([1, 0, 0], [2, 1, 0])
```

(continues on next page)

(continued from previous page)

```
0.0
>>> distance.sokalsneath([1, 0, 0], [3, 1, 0])
-2.0
```

scipy.spatial.distance.yule

`scipy.spatial.distance.yule` (*u*, *v*, *w=None*)

Compute the Yule dissimilarity between two boolean 1-D arrays.

The Yule dissimilarity is defined as

$$\frac{R}{c_{TT} * c_{FF} + \frac{R}{2}}$$

where c_{ij} is the number of occurrences of $u[k] = i$ and $v[k] = j$ for $k < n$ and $R = 2.0 * c_{TF} * c_{FT}$.

Parameters

- u** [(N,) array_like, bool] Input array.
- v** [(N,) array_like, bool] Input array.
- w** [(N,) array_like, optional] The weights for each value in *u* and *v*. Default is None, which gives each value a weight of 1.0

Returns

- yule** [double] The Yule dissimilarity between vectors *u* and *v*.

Examples

```
>>> from scipy.spatial import distance
>>> distance.yule([1, 0, 0], [0, 1, 0])
2.0
>>> distance.yule([1, 1, 0], [0, 1, 0])
0.0
```

hamming also operates over discrete numerical vectors.

6.28 Special functions (`scipy.special`)

Nearly all of the functions below are universal functions and follow broadcasting and automatic array-looping rules.

See also:

`scipy.special.cython_special` – Typed Cython versions of special functions

6.28.1 Error handling

Errors are handled by returning NaNs or other appropriate values. Some of the special function routines can emit warnings or raise exceptions when an error occurs. By default this is disabled; to query and control the current error handling state the following functions are provided.

<code>geterr()</code>	Get the current way of handling special-function errors.
<code>seterr()</code>	Set how special-function errors are handled.
<code>errstate(**kwargs)</code>	Context manager for special-function error handling.
<code>SpecialFunctionWarning</code>	Warning that can be emitted by special functions.
<code>SpecialFunctionError</code>	Exception that can be raised by special functions.

`scipy.special.geterr`

`scipy.special.geterr()`

Get the current way of handling special-function errors.

Returns

err [dict] A dictionary with keys “singular”, “underflow”, “overflow”, “slow”, “loss”, “no_result”, “domain”, “arg”, and “other”, whose values are from the strings “ignore”, “warn”, and “raise”. The keys represent possible special-function errors, and the values define how these errors are handled.

See also:

`seterr`

set how special-function errors are handled

`errstate`

context manager for special-function error handling

`numpy.geterr`

similar numpy function for floating-point errors

Notes

For complete documentation of the types of special-function errors and treatment options, see `seterr`.

Examples

By default all errors are ignored.

```
>>> import scipy.special as sc
>>> for key, value in sorted(sc.geterr().items()):
...     print("{}: {}".format(key, value))
...
arg: ignore
domain: ignore
loss: ignore
no_result: ignore
```

(continues on next page)

```

other: ignore
overflow: ignore
singular: ignore
slow: ignore
underflow: ignore

```

scipy.special.seterr

`scipy.special.seterr()`

Set how special-function errors are handled.

Parameters

- all** [{"ignore", "warn", "raise"}, optional] Set treatment for all type of special-function errors at once. The options are:
- 'ignore' Take no action when the error occurs
 - 'warn' Print a *SpecialFunctionWarning* when the error occurs (via the Python `warnings` module)
 - 'raise' Raise a *SpecialFunctionError* when the error occurs.
- The default is to not change the current behavior. If behaviors for additional categories of special-function errors are specified, then `all` is applied first, followed by the additional categories.
- singular** [{"ignore", "warn", "raise"}, optional] Treatment for singularities.
- underflow** [{"ignore", "warn", "raise"}, optional] Treatment for underflow.
- overflow** [{"ignore", "warn", "raise"}, optional] Treatment for overflow.
- slow** [{"ignore", "warn", "raise"}, optional] Treatment for slow convergence.
- loss** [{"ignore", "warn", "raise"}, optional] Treatment for loss of accuracy.
- no_result** [{"ignore", "warn", "raise"}, optional] Treatment for failing to find a result.
- domain** [{"ignore", "warn", "raise"}, optional] Treatment for an invalid argument to a function.
- arg** [{"ignore", "warn", "raise"}, optional] Treatment for an invalid parameter to a function.
- other** [{"ignore", "warn", "raise"}, optional] Treatment for an unknown error.

Returns

- olderr** [dict] Dictionary containing the old settings.

See also:

geterr

get the current way of handling special-function errors

errstate

context manager for special-function error handling

numpy.seterr

similar numpy function for floating-point errors

Examples

```
>>> import scipy.special as sc
>>> from pytest import raises
>>> sc.gammaln(0)
inf
>>> olderr = sc.seterr(singular='raise')
>>> with raises(sc.SpecialFunctionError):
...     sc.gammaln(0)
...
>>> _ = sc.seterr(**olderr)
```

We can also raise for every category except one.

```
>>> olderr = sc.seterr(all='raise', singular='ignore')
>>> sc.gammaln(0)
inf
>>> with raises(sc.SpecialFunctionError):
...     sc.spence(-1)
...
>>> _ = sc.seterr(**olderr)
```

scipy.special.errstate

class `scipy.special.errstate` (***kwargs*)

Context manager for special-function error handling.

Using an instance of `errstate` as a context manager allows statements in that context to execute with a known error handling behavior. Upon entering the context the error handling is set with `seterr`, and upon exiting it is restored to what it was before.

Parameters

kwargs [{all, singular, underflow, overflow, slow, loss, no_result, domain, arg, other}] Keyword arguments. The valid keywords are possible special-function errors. Each keyword should have a string value that defines the treatment for the particular type of error. Values must be 'ignore', 'warn', or 'other'. See `seterr` for details.

See also:

`geterr`

get the current way of handling special-function errors

`seterr`

set how special-function errors are handled

`numpy.errstate`

similar numpy function for floating-point errors

Examples

```
>>> import scipy.special as sc
>>> from pytest import raises
>>> sc.gammaln(0)
inf
>>> with sc.errstate(singular='raise'):
...     with raises(sc.SpecialFunctionError):
...         sc.gammaln(0)
...
>>> sc.gammaln(0)
inf
```

We can also raise on every category except one.

```
>>> with sc.errstate(all='raise', singular='ignore'):
...     sc.gammaln(0)
...     with raises(sc.SpecialFunctionError):
...         sc.spence(-1)
...
inf
```

scipy.special.SpecialFunctionWarning

exception `scipy.special.SpecialFunctionWarning`

Warning that can be emitted by special functions.

with_traceback()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

scipy.special.SpecialFunctionError

exception `scipy.special.SpecialFunctionError`

Exception that can be raised by special functions.

with_traceback()

Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

6.28.2 Available functions

Airy functions

<code>airy(z)</code>	Airy functions and their derivatives.
<code>airye(z)</code>	Exponentially scaled Airy functions and their derivatives.
<code>ai_zeros(nt)</code>	Compute nt zeros and values of the Airy function A_i and its derivative.
<code>bi_zeros(nt)</code>	Compute nt zeros and values of the Airy function B_i and its derivative.
<code>itairy(x)</code>	Integrals of Airy functions

scipy.special.airy

`scipy.special.airy(z) = <ufunc 'airy'>`

Airy functions and their derivatives.

Parameters

z [array_like] Real or complex argument.

Returns

Ai, Aip, Bi, Bip

[ndarrays] Airy functions Ai and Bi, and their derivatives Aip and Bip.

See also:

airy

exponentially scaled Airy functions.

Notes

The Airy functions Ai and Bi are two independent solutions of

$$y''(x) = xy(x).$$

For real z in $[-10, 10]$, the computation is carried out by calling the Cephes [1] *airy* routine, which uses power series summation for small z and rational minimax approximations for large z .

Outside this range, the AMOS [2] *zairy* and *zbiry* routines are employed. They are computed using power series for $|z| < 1$ and the following relations to modified Bessel functions for larger z (where $t \equiv 2z^{3/2}/3$):

$$\begin{aligned} Ai(z) &= \frac{1}{\pi\sqrt{3}} K_{1/3}(t) \\ Ai'(z) &= -\frac{z}{\pi\sqrt{3}} K_{2/3}(t) \\ Bi(z) &= \sqrt{\frac{z}{3}} (I_{-1/3}(t) + I_{1/3}(t)) \\ Bi'(z) &= \frac{z}{\sqrt{3}} (I_{-2/3}(t) + I_{2/3}(t)) \end{aligned}$$

References

[1], [2]

Examples

Compute the Airy functions on the interval $[-15, 5]$.


```
>>> from scipy import special
>>> x = np.linspace(-15, 5, 201)
>>> ai, aip, bi, bip = special.airy(x)
```

Plot Ai(x) and Bi(x).

```

>>> import matplotlib.pyplot as plt
>>> plt.plot(x, ai, 'r', label='Ai(x)')
>>> plt.plot(x, bi, 'b--', label='Bi(x)')
>>> plt.ylim(-0.5, 1.0)
>>> plt.grid()
>>> plt.legend(loc='upper left')
>>> plt.show()

```



scipy.special.airye

`scipy.special.airye(z) = <ufunc 'airye'>`

Exponentially scaled Airy functions and their derivatives.

Scaling:

```

eAi = Ai * exp(2.0/3.0*z*sqrt(z))
eAip = Aip * exp(2.0/3.0*z*sqrt(z))
eBi = Bi * exp(-abs(2.0/3.0*(z*sqrt(z)).real))
eBip = Bip * exp(-abs(2.0/3.0*(z*sqrt(z)).real))

```

Parameters

z [array_like] Real or complex argument.

Returns

eAi, eAip, eBi, eBip

[array_like] Exponentially scaled Airy functions eAi and eBi, and their derivatives eAip and eBip

See also:

[airy](#)

Notes

Wrapper for the AMOS [1] routines *zairy* and *zbiry*.


References

[1]

Examples

We can compute exponentially scaled Airy functions and their derivatives:

```
>>> from scipy.special import airye
>>> import matplotlib.pyplot as plt
>>> z = np.linspace(0, 50, 500)
>>> eAi, eAip, eBi, eBip = airye(z)
>>> f, ax = plt.subplots(2, 1, sharex=True)
>>> for ind, data in enumerate([[eAi, eAip, ["eAi", "eAip"]],
...                             [eBi, eBip, ["eBi", "eBip"]]]):
...     ax[ind].plot(z, data[0], "-r", z, data[1], "-b")
...     ax[ind].legend(data[2])
...     ax[ind].grid(True)
>>> plt.show()
```



We can compute these using usual non-scaled Airy functions by:

```
>>> from scipy.special import airy
>>> Ai, Aip, Bi, Bip = airy(z)
>>> np.allclose(eAi, Ai * np.exp(2.0 / 3.0 * z * np.sqrt(z)))
True
>>> np.allclose(eAip, Aip * np.exp(2.0 / 3.0 * z * np.sqrt(z)))
True
```

(continues on next page)

(continued from previous page)

```
>>> np.allclose(eBi, Bi * np.exp(-abs(np.real(2.0 / 3.0 * z * np.
→sqrt(z))))))
True
>>> np.allclose(eBip, Bip * np.exp(-abs(np.real(2.0 / 3.0 * z * np.
→sqrt(z))))))
True
```

Comparing non-scaled and exponentially scaled ones, the usual non-scaled function quickly underflows for large values, whereas the exponentially scaled function does not.

```
>>> airy(200)
(0.0, 0.0, nan, nan)
>>> airye(200)
(0.07501041684381093, -1.0609012305109042, 0.15003188417418148, 2.
→1215836725571093)
```

scipy.special.ai_zeros

`scipy.special.ai_zeros` (*nt*)

Compute *nt* zeros and values of the Airy function Ai and its derivative.

Computes the first *nt* zeros, *a*, of the Airy function $Ai(x)$; first *nt* zeros, *ap*, of the derivative of the Airy function $Ai'(x)$; the corresponding values $Ai(a')$; and the corresponding values $Ai'(a)$.

Parameters

nt [int] Number of zeros to compute

Returns

a [ndarray] First *nt* zeros of $Ai(x)$
ap [ndarray] First *nt* zeros of $Ai'(x)$
ai [ndarray] Values of $Ai(x)$ evaluated at first *nt* zeros of $Ai'(x)$
aip [ndarray] Values of $Ai'(x)$ evaluated at first *nt* zeros of $Ai(x)$

References

[1]

Examples

```
>>> from scipy import special
>>> a, ap, ai, aip = special.ai_zeros(3)
>>> a
array([-2.33810741, -4.08794944, -5.52055983])
>>> ap
array([-1.01879297, -3.24819758, -4.82009921])
>>> ai
array([ 0.53565666, -0.41901548,  0.38040647])
>>> aip
array([ 0.70121082, -0.80311137,  0.86520403])
```

scipy.special.bi_zeros`scipy.special.bi_zeros(nt)`Compute nt zeros and values of the Airy function Bi and its derivative.Computes the first nt zeros, b , of the Airy function $Bi(x)$; first nt zeros, b' , of the derivative of the Airy function $Bi'(x)$; the corresponding values $Bi(b')$; and the corresponding values $Bi'(b)$.**Parameters****nt** [int] Number of zeros to compute**Returns**

b [ndarray] First nt zeros of $Bi(x)$
bp [ndarray] First nt zeros of $Bi'(x)$
bi [ndarray] Values of $Bi(x)$ evaluated at first nt zeros of $Bi'(x)$
bip [ndarray] Values of $Bi'(x)$ evaluated at first nt zeros of $Bi(x)$

References

[1]

Examples

```
>>> from scipy import special
>>> b, bp, bi, bip = special.bi_zeros(3)
>>> b
array([-1.17371322, -3.2710933 , -4.83073784])
>>> bp
array([-2.29443968, -4.07315509, -5.51239573])
>>> bi
array([-0.45494438,  0.39652284, -0.36796916])
>>> bip
array([ 0.60195789, -0.76031014,  0.83699101])
```

scipy.special.itairy`scipy.special.itairy(x) = <ufunc 'itairy'>`

Integrals of Airy functions

Calculates the integrals of Airy functions from 0 to x .**Parameters****x: array_like**
Upper limit of integration (float).**Returns**

Apt Integral of $Ai(t)$ from 0 to x .
Bpt Integral of $Bi(t)$ from 0 to x .
Ant Integral of $Ai(-t)$ from 0 to x .
Bnt Integral of $Bi(-t)$ from 0 to x .

Notes

Wrapper for a Fortran routine created by Shanjie Zhang and Jianming Jin [1].

References

[1]

Elliptic functions and integrals

<code>ellipj(u, m)</code>	Jacobian elliptic functions
<code>ellipk(m)</code>	Complete elliptic integral of the first kind.
<code>ellipkm1(p)</code>	Complete elliptic integral of the first kind around $m = 1$
<code>ellipkinc(phi, m)</code>	Incomplete elliptic integral of the first kind
<code>ellipe(m)</code>	Complete elliptic integral of the second kind
<code>ellipeinc(phi, m)</code>	Incomplete elliptic integral of the second kind

scipy.special.ellipj

`scipy.special.ellipj(u, m) = <ufunc 'ellipj'>`
 Jacobian elliptic functions

Calculates the Jacobian elliptic functions of parameter m between 0 and 1, and real argument u .

Parameters

m [array_like] Parameter.
u [array_like] Argument.

Returns

sn, cn, dn, ph
 [ndarrays] The returned functions:

$sn(u|m), cn(u|m), dn(u|m)$

The value ph is such that if $u = ellipkinc(ph, m)$, then $sn(u|m) = sin(ph)$ and $cn(u|m) = cos(ph)$.

See also:

`ellipk`

Complete elliptic integral of the first kind

`ellipkinc`

Incomplete elliptic integral of the first kind

Notes

Wrapper for the Cephes [1] routine *ellpj*.

These functions are periodic, with quarter-period on the real axis equal to the complete elliptic integral *ellipk(m)*.

Relation to incomplete elliptic integral: If $u = \text{ellipkinc}(\phi, m)$, then $\text{sn}(u|m) = \sin(\phi)$, and $\text{cn}(u|m) = \cos(\phi)$. The ϕ is called the amplitude of u .

Computation is by means of the arithmetic-geometric mean algorithm, except when m is within $1e-9$ of 0 or 1. In the latter case with m close to 1, the approximation applies only for $\phi < \pi/2$.

References

[1]

scipy.special.ellipk

`scipy.special.ellipk(m) = <ufunc 'ellipk'>`
Complete elliptic integral of the first kind.

This function is defined as

$$K(m) = \int_0^{\pi/2} [1 - m \sin(t)^2]^{-1/2} dt$$

Parameters

m [array_like] The parameter of the elliptic integral.

Returns

K [array_like] Value of the elliptic integral.

See also:

ellipkm1

Complete elliptic integral of the first kind around $m = 1$

ellipkinc

Incomplete elliptic integral of the first kind

ellipe

Complete elliptic integral of the second kind

ellipeinc

Incomplete elliptic integral of the second kind

Notes

For more precision around point $m = 1$, use `ellipkm1`, which this function calls.

The parameterization in terms of m follows that of section 17.2 in [1]. Other parameterizations in terms of the complementary parameter $1 - m$, modular angle $\sin^2(\alpha) = m$, or modulus $k^2 = m$ are also used, so be careful that you choose the correct parameter.

References

[1]

scipy.special.ellipkm1

`scipy.special.ellipkm1(p) = <ufunc 'ellipkm1'>`

Complete elliptic integral of the first kind around $m = 1$

This function is defined as

$$K(p) = \int_0^{\pi/2} [1 - m \sin(t)^2]^{-1/2} dt$$

where $m = 1 - p$.

Parameters

p [array_like] Defines the parameter of the elliptic integral as $m = 1 - p$.

Returns

K [ndarray] Value of the elliptic integral.

See also:

`ellipk`

Complete elliptic integral of the first kind

`ellipkinc`

Incomplete elliptic integral of the first kind

`ellipe`

Complete elliptic integral of the second kind

`ellipeinc`

Incomplete elliptic integral of the second kind

Notes

Wrapper for the Cephes [1] routine `ellpk`.

For $p \leq 1$, computation uses the approximation,

$$K(p) \approx P(p) - \log(p)Q(p),$$

where P and Q are tenth-order polynomials. The argument p is used internally rather than m so that the logarithmic singularity at $m = 1$ will be shifted to the origin; this preserves maximum accuracy. For $p > 1$, the identity

$$K(p) = K(1/p) / \sqrt{p}$$

is used.

References

[1]

scipy.special.ellipkinc

`scipy.special.ellipkinc(phi, m) = <ufunc 'ellipkinc'>`

Incomplete elliptic integral of the first kind

This function is defined as

$$K(\phi, m) = \int_0^\phi [1 - m \sin(t)^2]^{-1/2} dt$$

This function is also called $F(\phi, m)$.

Parameters

phi [array_like] amplitude of the elliptic integral
m [array_like] parameter of the elliptic integral

Returns

K [ndarray] Value of the elliptic integral

See also:

[ellipkm1](#)

Complete elliptic integral of the first kind, near $m = 1$

[ellipk](#)

Complete elliptic integral of the first kind

[ellipe](#)

Complete elliptic integral of the second kind

[ellipeinc](#)

Incomplete elliptic integral of the second kind

Notes

Wrapper for the Cephes [1] routine *ellik*. The computation is carried out using the arithmetic-geometric mean algorithm.

The parameterization in terms of m follows that of section 17.2 in [2]. Other parameterizations in terms of the complementary parameter $1 - m$, modular angle $\sin^2(\alpha) = m$, or modulus $k^2 = m$ are also used, so be careful that you choose the correct parameter.

References

[1], [2]

scipy.special.ellipe

`scipy.special.ellipe(m) = <ufunc 'ellipe'>`

Complete elliptic integral of the second kind

This function is defined as

$$E(m) = \int_0^{\pi/2} [1 - m \sin(t)^2]^{1/2} dt$$

Parameters

m [array_like] Defines the parameter of the elliptic integral.

Returns

E [ndarray] Value of the elliptic integral.

See also:

[ellipkm1](#)

Complete elliptic integral of the first kind, near $m = 1$

[ellipk](#)

Complete elliptic integral of the first kind

[ellipkinc](#)

Incomplete elliptic integral of the first kind

[ellipeinc](#)

Incomplete elliptic integral of the second kind

Notes

Wrapper for the Cephes [1] routine *ellpe*.

For $m > 0$ the computation uses the approximation,

$$E(m) \approx P(1 - m) - (1 - m) \log(1 - m)Q(1 - m),$$

where P and Q are tenth-order polynomials. For $m < 0$, the relation

$$E(m) = E(m/(m - 1))\sqrt{1 - m}$$

is used.

The parameterization in terms of m follows that of section 17.2 in [2]. Other parameterizations in terms of the complementary parameter $1 - m$, modular angle $\sin^2(\alpha) = m$, or modulus $k^2 = m$ are also used, so be careful that you choose the correct parameter.

References

[1], [2]

Examples

This function is used in finding the circumference of an ellipse with semi-major axis a and semi-minor axis b .

```
>>> from scipy import special
```

```
>>> a = 3.5
>>> b = 2.1
>>> e_sq = 1.0 - b**2/a**2 # eccentricity squared
```

Then the circumference is found using the following:

```
>>> C = 4*a*special.ellipe(e_sq) # circumference formula
>>> C
17.868899204378693
```

When a and b are the same (meaning eccentricity is 0), this reduces to the circumference of a circle.

```
>>> 4*a*special.ellipe(0.0) # formula for ellipse with a = b
21.991148575128552
>>> 2*np.pi*a # formula for circle of radius a
21.991148575128552
```

scipy.special.ellipeinc

`scipy.special.ellipeinc(phi, m) = <ufunc 'ellipeinc'>`

Incomplete elliptic integral of the second kind

This function is defined as

$$E(\phi, m) = \int_0^{\phi} [1 - m \sin(t)^2]^{1/2} dt$$

Parameters

phi [array_like] amplitude of the elliptic integral.
m [array_like] parameter of the elliptic integral.

Returns

E [ndarray] Value of the elliptic integral.

See also:

`ellipkm1`

Complete elliptic integral of the first kind, near $m = 1$

`ellipk`

Complete elliptic integral of the first kind

`ellipkinc`

Incomplete elliptic integral of the first kind

ellipe

Complete elliptic integral of the second kind

Notes

Wrapper for the Cephes [1] routine *ellie*.

Computation uses arithmetic-geometric means algorithm.

The parameterization in terms of m follows that of section 17.2 in [2]. Other parameterizations in terms of the complementary parameter $1 - m$, modular angle $\sin^2(\alpha) = m$, or modulus $k^2 = m$ are also used, so be careful that you choose the correct parameter.

References

[1], [2]

Bessel functions

<i>jv(v, z)</i>	Bessel function of the first kind of real order and complex argument.
<i>jve(v, z)</i>	Exponentially scaled Bessel function of order v .
<i>yn(n, x)</i>	Bessel function of the second kind of integer order and real argument.
<i>yv(v, z)</i>	Bessel function of the second kind of real order and complex argument.
<i>yve(v, z)</i>	Exponentially scaled Bessel function of the second kind of real order.
<i>kn(n, x)</i>	Modified Bessel function of the second kind of integer order n
<i>kv(v, z)</i>	Modified Bessel function of the second kind of real order v
<i>kve(v, z)</i>	Exponentially scaled modified Bessel function of the second kind.
<i>iv(v, z)</i>	Modified Bessel function of the first kind of real order.
<i>ive(v, z)</i>	Exponentially scaled modified Bessel function of the first kind
<i>hankel1(v, z)</i>	Hankel function of the first kind
<i>hankel1e(v, z)</i>	Exponentially scaled Hankel function of the first kind
<i>hankel2(v, z)</i>	Hankel function of the second kind
<i>hankel2e(v, z)</i>	Exponentially scaled Hankel function of the second kind

scipy.special.jv

`scipy.special.jv(v, z) = <ufunc 'jv'>`

Bessel function of the first kind of real order and complex argument.

Parameters

v [array_like] Order (float).
z [array_like] Argument (float or complex).

Returns

J [ndarray] Value of the Bessel function, $J_v(z)$.

See also:

jve

J_v with leading exponential behavior stripped off.

spherical_jn

spherical Bessel functions.

Notes

For positive ν values, the computation is carried out using the AMOS [1] *zbesj* routine, which exploits the connection to the modified Bessel function I_ν ,

$$\begin{aligned} J_\nu(z) &= \exp(v\pi i/2) I_\nu(-iz) & (\Im z > 0) \\ J_\nu(z) &= \exp(-v\pi i/2) I_\nu(iz) & (\Im z < 0) \end{aligned}$$

For negative ν values the formula,

$$J_{-\nu}(z) = J_\nu(z) \cos(\pi\nu) - Y_\nu(z) \sin(\pi\nu)$$

is used, where $Y_\nu(z)$ is the Bessel function of the second kind, computed using the AMOS routine *zbesy*. Note that the second term is exactly zero for integer ν ; to improve accuracy the second term is explicitly omitted for ν values such that $\nu = \text{floor}(\nu)$.

Not to be confused with the spherical Bessel functions (see *spherical_jn*).

References

[1]

scipy.special.jve

`scipy.special.jve(v, z) = <ufunc 'jve'>`

Exponentially scaled Bessel function of order ν .

Defined as:

```
jve(v, z) = jv(v, z) * exp(-abs(z.imag))
```

Parameters

v [array_like] Order (float).
z [array_like] Argument (float or complex).

Returns

J [ndarray] Value of the exponentially scaled Bessel function.

Notes

For positive ν values, the computation is carried out using the AMOS [1] *zbesj* routine, which exploits the connection to the modified Bessel function I_ν ,

$$J_\nu(z) = \exp(\nu\pi i/2)I_\nu(-iz) \quad (\Im z > 0)$$

$$J_\nu(z) = \exp(-\nu\pi i/2)I_\nu(iz) \quad (\Im z < 0)$$

For negative ν values the formula,

$$J_{-\nu}(z) = J_\nu(z) \cos(\pi\nu) - Y_\nu(z) \sin(\pi\nu)$$

is used, where $Y_\nu(z)$ is the Bessel function of the second kind, computed using the AMOS routine *zbesy*. Note that the second term is exactly zero for integer ν ; to improve accuracy the second term is explicitly omitted for ν values such that $\nu = \text{floor}(\nu)$.

References

[1]

scipy.special.yn

`scipy.special.yn(n, x) = <ufunc 'yn'>`

Bessel function of the second kind of integer order and real argument.

Parameters

n [array_like] Order (integer).
z [array_like] Argument (float).

Returns

Y [ndarray] Value of the Bessel function, $Y_n(x)$.

See also:

yv

For real order and real or complex argument.

Notes

Wrapper for the Cephes [1] routine *yn*.

The function is evaluated by forward recurrence on n , starting with values computed by the Cephes routines *y0* and *y1*. If $n = 0$ or 1, the routine for *y0* or *y1* is called directly.

References

[1]

scipy.special.yv

`scipy.special.yv(v, z) = <ufunc 'yv'>`

Bessel function of the second kind of real order and complex argument.

Parameters

v [array_like] Order (float).
z [array_like] Argument (float or complex).

Returns

Y [ndarray] Value of the Bessel function of the second kind, $Y_\nu(x)$.

See also:

[yve](#)

Y_ν with leading exponential behavior stripped off.

Notes

For positive ν values, the computation is carried out using the AMOS [1] `zbesy` routine, which exploits the connection to the Hankel Bessel functions $H_\nu^{(1)}$ and $H_\nu^{(2)}$,

$$Y_\nu(z) = \frac{1}{2i}(H_\nu^{(1)} - H_\nu^{(2)}).$$

For negative ν values the formula,

$$Y_{-\nu}(z) = Y_\nu(z) \cos(\pi\nu) + J_\nu(z) \sin(\pi\nu)$$

is used, where $J_\nu(z)$ is the Bessel function of the first kind, computed using the AMOS routine `zbesj`. Note that the second term is exactly zero for integer ν ; to improve accuracy the second term is explicitly omitted for ν values such that $\nu = \text{floor}(\nu)$.

References

[1]

scipy.special.yve

`scipy.special.yve(v, z) = <ufunc 'yve'>`

Exponentially scaled Bessel function of the second kind of real order.

Returns the exponentially scaled Bessel function of the second kind of real order ν at complex z :

$$\text{yve}(v, z) = \text{yv}(v, z) * \exp(-\text{abs}(z.\text{imag}))$$

Parameters

v [array_like] Order (float).
z [array_like] Argument (float or complex).

Returns

Y [ndarray] Value of the exponentially scaled Bessel function.

Notes

For positive ν values, the computation is carried out using the AMOS [1] *zbesy* routine, which exploits the connection to the Hankel Bessel functions $H_\nu^{(1)}$ and $H_\nu^{(2)}$,

$$Y_\nu(z) = \frac{1}{2i}(H_\nu^{(1)} - H_\nu^{(2)}).$$

For negative ν values the formula,

$$Y_{-\nu}(z) = Y_\nu(z) \cos(\pi\nu) + J_\nu(z) \sin(\pi\nu)$$

is used, where $J_\nu(z)$ is the Bessel function of the first kind, computed using the AMOS routine *zbesj*. Note that the second term is exactly zero for integer ν ; to improve accuracy the second term is explicitly omitted for ν values such that $\nu = \text{floor}(\nu)$.

References

[1]

scipy.special.kn

`scipy.special.kn(n, x) = <ufunc 'kn'>`

Modified Bessel function of the second kind of integer order n

Returns the modified Bessel function of the second kind for integer order n at real z .

These are also sometimes called functions of the third kind, Basset functions, or Macdonald functions.

Parameters

n [array_like of int] Order of Bessel functions (floats will truncate with a warning)
z [array_like of float] Argument at which to evaluate the Bessel functions

Returns

out [ndarray] The results

See also:

[kv](#)

Same function, but accepts real order and complex argument

[kvp](#)

Derivative of this function

Notes

Wrapper for AMOS [1] routine *zbesk*. For a discussion of the algorithm used, see [2] and the references therein.


References

[1], [2]

Examples

Plot the function of several orders for real input:

```
>>> from scipy.special import kn
>>> import matplotlib.pyplot as plt
>>> x = np.linspace(0, 5, 1000)
>>> for N in range(6):
...     plt.plot(x, kn(N, x), label='$K_{%d}(x)$'.format(N))
>>> plt.ylim(0, 10)
>>> plt.legend()
>>> plt.title(r'Modified Bessel function of the second kind $K_n(x)$')
>>> plt.show()
```



Calculate for a single value at multiple orders:

```
>>> kn([4, 5, 6], 1)
array([ 44.23241585, 360.9605896 , 3653.83831186])
```

scipy.special.kv

`scipy.special.kv(v, z) = <ufunc 'kv'>`

Modified Bessel function of the second kind of real order ν

Returns the modified Bessel function of the second kind for real order ν at complex z .

These are also sometimes called functions of the third kind, Basset functions, or Macdonald functions. They are defined as those solutions of the modified Bessel equation for which,

$$K_\nu(x) \sim \sqrt{\pi/(2x)} \exp(-x)$$

as $x \rightarrow \infty$ [3].

Parameters

- v** [array_like of float] Order of Bessel functions
z [array_like of complex] Argument at which to evaluate the Bessel functions

Returns

- out** [ndarray] The results. Note that input must be of complex type to get complex output, e.g. `kv(3, -2+0j)` instead of `kv(3, -2)`.

See also:***kve***

This function with leading exponential behavior stripped off.

kvp

Derivative of this function

Notes

Wrapper for AMOS [1] routine *zbesk*. For a discussion of the algorithm used, see [2] and the references therein.

References

[1], [2], [3]


Examples

Plot the function of several orders for real input:

```
>>> from scipy.special import kv
>>> import matplotlib.pyplot as plt
>>> x = np.linspace(0, 5, 1000)
>>> for N in np.linspace(0, 6, 5):
...     plt.plot(x, kv(N, x), label='$K_{\{\{\}\}}(x)$'.format(N))
>>> plt.ylim(0, 10)
>>> plt.legend()
>>> plt.title(r'Modified Bessel function of the second kind $K_{\nu}(x)$')
>>> plt.show()
```

Calculate for a single value at multiple orders:

```
>>> kv([4, 4.5, 5], 1+2j)
array([ 0.1992+2.3892j,  2.3493+3.6j      ,  7.2827+3.8104j])
```



scipy.special.kve

`scipy.special.kve(v, z) = <ufunc 'kve'>`

Exponentially scaled modified Bessel function of the second kind.

Returns the exponentially scaled, modified Bessel function of the second kind (sometimes called the third kind) for real order ν at complex z :

$$\text{kve}(v, z) = \text{kv}(v, z) * \exp(z)$$

Parameters

- v** [array_like of float] Order of Bessel functions
- z** [array_like of complex] Argument at which to evaluate the Bessel functions

Returns

- out** [ndarray] The exponentially scaled modified Bessel function of the second kind.

Notes

Wrapper for AMOS [1] routine *zbesk*. For a discussion of the algorithm used, see [2] and the references therein.

References

[1], [2]

scipy.special.iv

`scipy.special.iv(v, z) = <ufunc 'iv'>`

Modified Bessel function of the first kind of real order.

Parameters

v [array_like] Order. If z is of real type and negative, v must be integer valued.
z [array_like of float or complex] Argument.

Returns

out [ndarray] Values of the modified Bessel function.

See also:

[kve](#)

This function with leading exponential behavior stripped off.

Notes

For real z and $v \in [-50, 50]$, the evaluation is carried out using Temme's method [1]. For larger orders, uniform asymptotic expansions are applied.

For complex z and positive v , the AMOS [2] *zbesi* routine is called. It uses a power series for small z , the asymptotic expansion for large $abs(z)$, the Miller algorithm normalized by the Wronskian and a Neumann series for intermediate magnitudes, and the uniform asymptotic expansions for $I_v(z)$ and $J_v(z)$ for large orders. Backward recurrence is used to generate sequences or reduce orders when necessary.

The calculations above are done in the right half plane and continued into the left half plane by the formula,

$$I_v(z \exp(\pm i\pi)) = \exp(\pm \pi v) I_v(z)$$

(valid when the real part of z is positive). For negative v , the formula

$$I_{-v}(z) = I_v(z) + \frac{2}{\pi} \sin(\pi v) K_v(z)$$

is used, where $K_v(z)$ is the modified Bessel function of the second kind, evaluated using the AMOS routine *zbesk*.

References

[1], [2]

scipy.special.ive

`scipy.special.ive(v, z) = <ufunc 'ive'>`

Exponentially scaled modified Bessel function of the first kind

Defined as:

```
ive(v, z) = iv(v, z) * exp(-abs(z.real))
```

Parameters

v [array_like of float] Order.
z [array_like of float or complex] Argument.

Returns

out [ndarray] Values of the exponentially scaled modified Bessel function.

Notes

For positive ν , the AMOS [1] *zbesi* routine is called. It uses a power series for small z , the asymptotic expansion for large $abs(z)$, the Miller algorithm normalized by the Wronskian and a Neumann series for intermediate magnitudes, and the uniform asymptotic expansions for $I_\nu(z)$ and $J_\nu(z)$ for large orders. Backward recurrence is used to generate sequences or reduce orders when necessary.

The calculations above are done in the right half plane and continued into the left half plane by the formula,

$$I_\nu(z \exp(\pm i\pi)) = \exp(\pm \pi\nu) I_\nu(z)$$

(valid when the real part of z is positive). For negative ν , the formula

$$I_{-\nu}(z) = I_\nu(z) + \frac{2}{\pi} \sin(\pi\nu) K_\nu(z)$$

is used, where $K_\nu(z)$ is the modified Bessel function of the second kind, evaluated using the AMOS routine *zbesk*.

References

[1]

scipy.special.hankel1

`scipy.special.hankel1`(ν, z) = `<ufunc 'hankel1'>`
Hankel function of the first kind

Parameters

ν [array_like] Order (float).
 z [array_like] Argument (float or complex).

Returns

out [Values of the Hankel function of the first kind.]

See also:

[hankel1e](#)

this function with leading exponential behavior stripped off.

Notes

A wrapper for the AMOS [1] routine *zbesh*, which carries out the computation using the relation,

$$H_\nu^{(1)}(z) = \frac{2}{i\pi} \exp(-i\pi\nu/2) K_\nu(z \exp(-i\pi/2))$$

where K_ν is the modified Bessel function of the second kind. For negative orders, the relation

$$H_{-\nu}^{(1)}(z) = H_\nu^{(1)}(z) \exp(i\pi\nu)$$

is used.

References

[1]

scipy.special.hankel1e

`scipy.special.hankel1e(v, z) = <ufunc 'hankel1e'>`

Exponentially scaled Hankel function of the first kind

Defined as:

$$\text{hankel1e}(v, z) = \text{hankel1}(v, z) * \exp(-1j * z)$$

Parameters

v [array_like] Order (float).
z [array_like] Argument (float or complex).

Returns

out [Values of the exponentially scaled Hankel function.]

Notes

A wrapper for the AMOS [1] routine *zbes*, which carries out the computation using the relation,

$$H_v^{(1)}(z) = \frac{2}{i\pi} \exp(-i\pi v/2) K_v(z \exp(-i\pi/2))$$

where K_v is the modified Bessel function of the second kind. For negative orders, the relation

$$H_{-v}^{(1)}(z) = H_v^{(1)}(z) \exp(i\pi v)$$

is used.

References

[1]

scipy.special.hankel2

`scipy.special.hankel2(v, z) = <ufunc 'hankel2'>`

Hankel function of the second kind

Parameters

v [array_like] Order (float).
z [array_like] Argument (float or complex).

Returns

out [Values of the Hankel function of the second kind.]

See also:

[hankel2e](#)

this function with leading exponential behavior stripped off.

Notes

A wrapper for the AMOS [1] routine *zbesh*, which carries out the computation using the relation,

$$H_v^{(2)}(z) = -\frac{2}{i\pi} \exp(i\pi v/2) K_v(z \exp(i\pi/2))$$

where K_v is the modified Bessel function of the second kind. For negative orders, the relation

$$H_{-v}^{(2)}(z) = H_v^{(2)}(z) \exp(-i\pi v)$$

is used.

References

[1]

scipy.special.hankel2e

`scipy.special.hankel2e(v, z) = <ufunc 'hankel2e'>`

Exponentially scaled Hankel function of the second kind

Defined as:

```
hankel2e(v, z) = hankel2(v, z) * exp(1j * z)
```

Parameters

v [array_like] Order (float).
z [array_like] Argument (float or complex).

Returns

out [Values of the exponentially scaled Hankel function of the second kind.]

Notes

A wrapper for the AMOS [1] routine *zbesh*, which carries out the computation using the relation,

$$H_v^{(2)}(z) = -\frac{2}{i\pi} \exp\left(\frac{i\pi v}{2}\right) K_v\left(z \exp\left(\frac{i\pi}{2}\right)\right)$$

where K_v is the modified Bessel function of the second kind. For negative orders, the relation

$$H_{-v}^{(2)}(z) = H_v^{(2)}(z) \exp(-i\pi v)$$

is used.

References

[1]

The following is not an universal function:

`lmbda(v, x)`

Jahnke-Emden Lambda function, `Lambdav(x)`.

scipy.special.lmbda

`scipy.special.lmbda(v, x)`

Jahnke-Emden Lambda function, `Lambdav(x)`.

This function is defined as [2],

$$\Lambda_v(x) = \Gamma(v + 1) \frac{J_v(x)}{(x/2)^v},$$

where Γ is the gamma function and J_v is the Bessel function of the first kind.

Parameters

- v** [float] Order of the Lambda function
- x** [float] Value at which to evaluate the function and derivatives

Returns

- vl** [ndarray] Values of `Lambda_vl(x)`, for $v_l = v - \text{int}(v)$, $v_l = 1 + v - \text{int}(v)$, ..., $v_l = v$.
- dl** [ndarray] Derivatives `Lambda_vl'(x)`, for $v_l = v - \text{int}(v)$, $v_l = 1 + v - \text{int}(v)$, ..., $v_l = v$.

References

[1], [2]

Zeros of Bessel functions

These are not universal functions:

<code>jnjnp_zeros(nt)</code>	Compute zeros of integer-order Bessel functions J_n and J_n' .
<code>jny_n_zeros(n, nt)</code>	Compute nt zeros of Bessel functions $J_n(x)$, $J_n'(x)$, $Y_n(x)$, and $Y_n'(x)$.
<code>jn_zeros(n, nt)</code>	Compute zeros of integer-order Bessel functions J_n .
<code>jnp_zeros(n, nt)</code>	Compute zeros of integer-order Bessel function derivatives J_n' .
<code>yn_zeros(n, nt)</code>	Compute zeros of integer-order Bessel function $Y_n(x)$.
<code>ynp_zeros(n, nt)</code>	Compute zeros of integer-order Bessel function derivatives $Y_n'(x)$.
<code>y0_zeros(nt[, complex])</code>	Compute nt zeros of Bessel function $Y_0(z)$, and derivative at each zero.
<code>y1_zeros(nt[, complex])</code>	Compute nt zeros of Bessel function $Y_1(z)$, and derivative at each zero.
<code>y1p_zeros(nt[, complex])</code>	Compute nt zeros of Bessel derivative $Y_1'(z)$, and value at each zero.

scipy.special.jnjnp_zeros`scipy.special.jnjnp_zeros` (*nt*)Compute zeros of integer-order Bessel functions J_n and J_n' .

Results are arranged in order of the magnitudes of the zeros.

Parameters**nt** [int] Number (≤ 1200) of zeros to compute**Returns****zo[l-1]** [ndarray] Value of the *l*th zero of $J_n(x)$ and $J_n'(x)$. Of length *nt*.**n[l-1]** [ndarray] Order of the $J_n(x)$ or $J_n'(x)$ associated with *l*th zero. Of length *nt*.**m[l-1]** [ndarray] Serial number of the zeros of $J_n(x)$ or $J_n'(x)$ associated with *l*th zero. Of length *nt*.**t[l-1]** [ndarray] 0 if *l*th zero in *zo* is zero of $J_n(x)$, 1 if it is a zero of $J_n'(x)$. Of length *nt*.

See also:

[*jn_zeros*](#), [*jnp_zeros*](#)

to get separated arrays of zeros.

References

[1]

scipy.special.jnyn_zeros`scipy.special.jnyn_zeros` (*n*, *nt*)Compute *nt* zeros of Bessel functions $J_n(x)$, $J_n'(x)$, $Y_n(x)$, and $Y_n'(x)$.Returns 4 arrays of length *nt*, corresponding to the first *nt* zeros of $J_n(x)$, $J_n'(x)$, $Y_n(x)$, and $Y_n'(x)$, respectively. The zeros are returned in ascending order.**Parameters****n** [int] Order of the Bessel functions**nt** [int] Number (≤ 1200) of zeros to compute**Returns****Jn** [ndarray] First *nt* zeros of J_n **Jnp** [ndarray] First *nt* zeros of J_n' **Yn** [ndarray] First *nt* zeros of Y_n **Ynp** [ndarray] First *nt* zeros of Y_n'

See also:

[*jn_zeros*](#), [*jnp_zeros*](#), [*yn_zeros*](#), [*ynp_zeros*](#)

References

[1]

scipy.special.jn_zeros

`scipy.special.jn_zeros(n, nt)`

Compute zeros of integer-order Bessel functions J_n .

Compute nt zeros of the Bessel functions $J_n(x)$ on the interval $(0, \infty)$. The zeros are returned in ascending order. Note that this interval excludes the zero at $x = 0$ that exists for $n > 0$.

Parameters

n [int] Order of Bessel function
nt [int] Number of zeros to return

Returns

ndarray First n zeros of the Bessel function.

See also:

[jv](#)

References

[1]

Examples

```
>>> import scipy.special as sc
```

We can check that we are getting approximations of the zeros by evaluating them with [jv](#).

```
>>> n = 1
>>> x = sc.jn_zeros(n, 3)
>>> x
array([ 3.83170597,  7.01558667, 10.17346814])
>>> sc.jv(n, x)
array([-0.00000000e+00,  1.72975330e-16,  2.89157291e-16])
```

Note that the zero at $x = 0$ for $n > 0$ is not included.

```
>>> sc.jv(1, 0)
0.0
```

scipy.special.jnp_zeros

`scipy.special.jnp_zeros` (*n*, *nt*)

Compute zeros of integer-order Bessel function derivatives J_n' .

Compute *nt* zeros of the functions $J_n'(x)$ on the interval $(0, \infty)$. The zeros are returned in ascending order. Note that this interval excludes the zero at $x = 0$ that exists for $n > 1$.

Parameters

n	[int] Order of Bessel function
nt	[int] Number of zeros to return

Returns

ndarray First *n* zeros of the Bessel function.

See also:

[jvp](#), [jv](#)

References

[1]

Examples

```
>>> import scipy.special as sc
```

We can check that we are getting approximations of the zeros by evaluating them with `jvp`.

```
>>> n = 2
>>> x = sc.jnp_zeros(n, 3)
>>> x
array([3.05423693, 6.70613319, 9.96946782])
>>> sc.jvp(n, x)
array([ 2.77555756e-17,  2.08166817e-16, -3.01841885e-16])
```

Note that the zero at $x = 0$ for $n > 1$ is not included.

```
>>> sc.jvp(n, 0)
0.0
```

scipy.special.yn_zeros

`scipy.special.yn_zeros` (*n*, *nt*)

Compute zeros of integer-order Bessel function $Y_n(x)$.

Compute *nt* zeros of the functions $Y_n(x)$ on the interval $(0, \infty)$. The zeros are returned in ascending order.

Parameters

n	[int] Order of Bessel function
nt	[int] Number of zeros to return

Returns

ndarray First n zeros of the Bessel function.

See also:

[yn](#), [yv](#)

References

[1]

Examples

```
>>> import scipy.special as sc
```

We can check that we are getting approximations of the zeros by evaluating them with [yn](#).

```
>>> n = 2
>>> x = sc.yn_zeros(n, 3)
>>> x
array([ 3.38424177,  6.79380751, 10.02347798])
>>> sc.yn(n, x)
array([-1.94289029e-16,  8.32667268e-17, -1.52655666e-16])
```

`scipy.special.ynp_zeros`

`scipy.special.ynp_zeros` (n, nt)

Compute zeros of integer-order Bessel function derivatives $Y_n'(x)$.

Compute nt zeros of the functions $Y_n'(x)$ on the interval $(0, \infty)$. The zeros are returned in ascending order.

Parameters

n	[int] Order of Bessel function
nt	[int] Number of zeros to return

See also:

[yvp](#)

References

[1]

Examples

```
>>> import scipy.special as sc
```

We can check that we are getting approximations of the zeros by evaluating them with `yvp`.

```
>>> n = 2
>>> x = sc.ynp_zeros(n, 3)
>>> x
array([ 5.00258293,  8.3507247 , 11.57419547])
>>> sc.yvp(n, x)
array([ 2.220444605e-16, -3.33066907e-16,  2.94902991e-16])
```

scipy.special.y0_zeros

`scipy.special.y0_zeros` (*nt*, *complex=False*)

Compute *nt* zeros of Bessel function $Y_0(z)$, and derivative at each zero.

The derivatives are given by $Y_0'(z_0) = -Y_1(z_0)$ at each zero z_0 .

Parameters

nt [int] Number of zeros to return

complex [bool, default False] Set to False to return only the real zeros; set to True to return only the complex zeros with negative real part and positive imaginary part. Note that the complex conjugates of the latter are also zeros of the function, but are not returned by this routine.

Returns

z0n [ndarray] Location of *nth* zero of $Y_0(z)$

y0pz0n [ndarray] Value of derivative $Y_0'(z_0)$ for *nth* zero

References

[1]

scipy.special.y1_zeros

`scipy.special.y1_zeros` (*nt*, *complex=False*)

Compute *nt* zeros of Bessel function $Y_1(z)$, and derivative at each zero.

The derivatives are given by $Y_1'(z_1) = Y_0(z_1)$ at each zero z_1 .

Parameters

nt [int] Number of zeros to return

complex [bool, default False] Set to False to return only the real zeros; set to True to return only the complex zeros with negative real part and positive imaginary part. Note that the complex conjugates of the latter are also zeros of the function, but are not returned by this routine.

Returns

z1n [ndarray] Location of *nth* zero of $Y_1(z)$

y1pz1n [ndarray] Value of derivative $Y_1'(z_1)$ for *nth* zero

References

[1]

scipy.special.y1p_zeros

`scipy.special.y1p_zeros` (*nt*, *complex=False*)

Compute *nt* zeros of Bessel derivative $Y_1'(z)$, and value at each zero.

The values are given by $Y_1(z_1)$ at each z_1 where $Y_1'(z_1)=0$.

Parameters

nt [int] Number of zeros to return
complex [bool, default False] Set to False to return only the real zeros; set to True to return only the complex zeros with negative real part and positive imaginary part. Note that the complex conjugates of the latter are also zeros of the function, but are not returned by this routine.

Returns

z1pn [ndarray] Location of *n*th zero of $Y_1'(z)$
y1z1pn [ndarray] Value of derivative $Y_1(z_1)$ for *n*th zero

References

[1]

Faster versions of common Bessel functions

$j_0(x)$	Bessel function of the first kind of order 0.
$j_1(x)$	Bessel function of the first kind of order 1.
$y_0(x)$	Bessel function of the second kind of order 0.
$y_1(x)$	Bessel function of the second kind of order 1.
$i_0(x)$	Modified Bessel function of order 0.
$i_0e(x)$	Exponentially scaled modified Bessel function of order 0.
$i_1(x)$	Modified Bessel function of order 1.
$i_1e(x)$	Exponentially scaled modified Bessel function of order 1.
$k_0(x)$	Modified Bessel function of the second kind of order 0, K_0 .
$k_0e(x)$	Exponentially scaled modified Bessel function K of order 0
$k_1(x)$	Modified Bessel function of the second kind of order 1, $K_1(x)$.
$k_1e(x)$	Exponentially scaled modified Bessel function K of order 1

scipy.special.j0

`scipy.special.j0(x) = <ufunc 'j0'>`

Bessel function of the first kind of order 0.

Parameters

x [array_like] Argument (float).

Returns

J [ndarray] Value of the Bessel function of the first kind of order 0 at x .

See also:

[*jv*](#)

Bessel function of real order and complex argument.

[*spherical_jn*](#)

spherical Bessel functions.

Notes

The domain is divided into the intervals $[0, 5]$ and $(5, \text{infinity})$. In the first interval the following rational approximation is used:

$$J_0(x) \approx (w - r_1^2)(w - r_2^2) \frac{P_3(w)}{Q_8(w)},$$

where $w = x^2$ and r_1, r_2 are the zeros of J_0 , and P_3 and Q_8 are polynomials of degrees 3 and 8, respectively.

In the second interval, the Hankel asymptotic expansion is employed with two rational functions of degree 6/6 and 7/7.

This function is a wrapper for the Cephes [1] routine *j0*. It should not be confused with the spherical Bessel functions (see [*spherical_jn*](#)).

References

[1]

scipy.special.j1

`scipy.special.j1(x) = <ufunc 'j1'>`

Bessel function of the first kind of order 1.

Parameters

x [array_like] Argument (float).

Returns

J [ndarray] Value of the Bessel function of the first kind of order 1 at x .

See also:

[*jv*](#)

spherical_jn

spherical Bessel functions.

Notes

The domain is divided into the intervals [0, 8] and (8, infinity). In the first interval a 24 term Chebyshev expansion is used. In the second, the asymptotic trigonometric representation is employed using two rational functions of degree 5/5.

This function is a wrapper for the Cephes [1] routine *j1*. It should not be confused with the spherical Bessel functions (see *spherical_jn*).

References

[1]

scipy.special.y0

`scipy.special.y0(x) = <ufunc 'y0'>`
Bessel function of the second kind of order 0.

Parameters

x [array_like] Argument (float).

Returns

Y [ndarray] Value of the Bessel function of the second kind of order 0 at *x*.

See also:

j0

yv

Notes

The domain is divided into the intervals [0, 5] and (5, infinity). In the first interval a rational approximation $R(x)$ is employed to compute,

$$Y_0(x) = R(x) + \frac{2 \log(x) J_0(x)}{\pi},$$

where J_0 is the Bessel function of the first kind of order 0.

In the second interval, the Hankel asymptotic expansion is employed with two rational functions of degree 6/6 and 7/7.

This function is a wrapper for the Cephes [1] routine *y0*.

References

[1]

scipy.special.y1

`scipy.special.y1(x) = <ufunc 'y1'>`
 Bessel function of the second kind of order 1.

Parameters

x [array_like] Argument (float).

Returns

Y [ndarray] Value of the Bessel function of the second kind of order 1 at x .

See also:

[*j1*](#)

[*yn*](#)

[*yv*](#)

Notes

The domain is divided into the intervals $[0, 8]$ and $(8, \infty)$. In the first interval a 25 term Chebyshev expansion is used, and computing J_1 (the Bessel function of the first kind) is required. In the second, the asymptotic trigonometric representation is employed using two rational functions of degree 5/5.

This function is a wrapper for the Cephes [1] routine `y1`.

References

[1]

scipy.special.i0

`scipy.special.i0(x) = <ufunc 'i0'>`
 Modified Bessel function of order 0.

Defined as,

$$I_0(x) = \sum_{k=0}^{\infty} \frac{(x^2/4)^k}{(k!)^2} = J_0(ix),$$

where J_0 is the Bessel function of the first kind of order 0.

Parameters

x [array_like] Argument (float)

Returns

I [ndarray] Value of the modified Bessel function of order 0 at x .

See also:[*iv*](#)[*i0e*](#)**Notes**

The range is partitioned into the two intervals [0, 8] and (8, infinity). Chebyshev polynomial expansions are employed in each interval.

This function is a wrapper for the Cephys [1] routine *i0*.

References

[1]

scipy.special.i0e

`scipy.special.i0e(x) = <ufunc 'i0e'>`

Exponentially scaled modified Bessel function of order 0.

Defined as:

```
i0e(x) = exp(-abs(x)) * i0(x) .
```

Parameters

x [array_like] Argument (float)

Returns

I [ndarray] Value of the exponentially scaled modified Bessel function of order 0 at *x*.

See also:[*iv*](#)[*i0*](#)**Notes**

The range is partitioned into the two intervals [0, 8] and (8, infinity). Chebyshev polynomial expansions are employed in each interval. The polynomial expansions used are the same as those in *i0*, but they are not multiplied by the dominant exponential factor.

This function is a wrapper for the Cephys [1] routine *i0e*.

References

[1]

scipy.special.i1

`scipy.special.i1(x) = <ufunc 'i1'>`

Modified Bessel function of order 1.

Defined as,

$$I_1(x) = \frac{1}{2}x \sum_{k=0}^{\infty} \frac{(x^2/4)^k}{k!(k+1)!} = -iJ_1(ix),$$

where J_1 is the Bessel function of the first kind of order 1.

Parameters

x [array_like] Argument (float)

Returns

I [ndarray] Value of the modified Bessel function of order 1 at x .

See also:

[`iv`](#)

[`i1e`](#)

Notes

The range is partitioned into the two intervals $[0, 8]$ and $(8, \text{infinity})$. Chebyshev polynomial expansions are employed in each interval.

This function is a wrapper for the Cephes [1] routine `i1`.

References

[1]

scipy.special.i1e

`scipy.special.i1e(x) = <ufunc 'i1e'>`

Exponentially scaled modified Bessel function of order 1.

Defined as:

```
i1e(x) = exp(-abs(x)) * i1(x)
```

Parameters

x [array_like] Argument (float)

Returns

I [ndarray] Value of the exponentially scaled modified Bessel function of order 1 at x .

See also:

iv

i1

Notes

The range is partitioned into the two intervals $[0, 8]$ and $(8, \text{infinity})$. Chebyshev polynomial expansions are employed in each interval. The polynomial expansions used are the same as those in *i1*, but they are not multiplied by the dominant exponential factor.

This function is a wrapper for the Cephes [1] routine *i1e*.

References

[1]

scipy.special.k0

`scipy.special.k0(x) = <ufunc 'k0'>`

Modified Bessel function of the second kind of order 0, K_0 .

This function is also sometimes referred to as the modified Bessel function of the third kind of order 0.

Parameters

x [array_like] Argument (float).

Returns

K [ndarray] Value of the modified Bessel function K_0 at x .

See also:

kv

k0e

Notes

The range is partitioned into the two intervals $[0, 2]$ and $(2, \text{infinity})$. Chebyshev polynomial expansions are employed in each interval.

This function is a wrapper for the Cephes [1] routine *k0*.

References

[1]

scipy.special.k0e

`scipy.special.k0e(x) = <ufunc 'k0e'>`

Exponentially scaled modified Bessel function K of order 0

Defined as:

$$k0e(x) = \exp(x) * k0(x).$$

Parameters

x [array_like] Argument (float)

Returns

K [ndarray] Value of the exponentially scaled modified Bessel function K of order 0 at x .

See also:

[kv](#)

[k0](#)

Notes

The range is partitioned into the two intervals $[0, 2]$ and $(2, \infty)$. Chebyshev polynomial expansions are employed in each interval.

This function is a wrapper for the Cephes [1] routine `k0e`.

References

[1]

scipy.special.k1

`scipy.special.k1(x) = <ufunc 'k1'>`

Modified Bessel function of the second kind of order 1, $K_1(x)$.

Parameters

x [array_like] Argument (float)

Returns

K [ndarray] Value of the modified Bessel function K of order 1 at x .

See also:

[kv](#)

[k1e](#)

Notes

The range is partitioned into the two intervals [0, 2] and (2, infinity). Chebyshev polynomial expansions are employed in each interval.

This function is a wrapper for the Cephys [1] routine *k1*.

References

[1]

scipy.special.k1e

`scipy.special.k1e(x) = <ufunc 'k1e'>`
Exponentially scaled modified Bessel function K of order 1

Defined as:

$$k1e(x) = \exp(x) * k1(x)$$

Parameters

x [array_like] Argument (float)

Returns

K [ndarray] Value of the exponentially scaled modified Bessel function K of order 1 at *x*.

See also:

[*kv*](#)

[*k1*](#)

Notes

The range is partitioned into the two intervals [0, 2] and (2, infinity). Chebyshev polynomial expansions are employed in each interval.

This function is a wrapper for the Cephys [1] routine *k1e*.

References

[1]

Integrals of Bessel functions

<code>itj0y0(x[, out])</code>	Integrals of Bessel functions of the first kind of order 0.
<code>it2j0y0(x[, out])</code>	Integrals related to Bessel functions of the first kind of order 0.
<code>iti0k0(x[, out])</code>	Integrals of modified Bessel functions of order 0.
<code>it2i0k0(x[, out])</code>	Integrals related to modified Bessel functions of order 0.
<code>besselpoly(a, lmb, nu[, out])</code>	Weighted integral of the Bessel function of the first kind.

scipy.special.itj0y0

`scipy.special.itj0y0(x, out=None) = <ufunc 'itj0y0'>`
Integrals of Bessel functions of the first kind of order 0.

Computes the integrals

$$\int_0^x J_0(t) dt$$

$$\int_0^x Y_0(t) dt.$$

For more on J_0 and Y_0 see [j0](#) and [y0](#).

Parameters

x [array_like] Values at which to evaluate the integrals.
out [tuple of ndarrays, optional] Optional output arrays for the function results.

Returns

ij0 [scalar or ndarray] The integral of [j0](#)
iy0 [scalar or ndarray] The integral of [y0](#)

scipy.special.it2j0y0

`scipy.special.it2j0y0(x, out=None) = <ufunc 'it2j0y0'>`
Integrals related to Bessel functions of the first kind of order 0.

Computes the integrals

$$\int_0^x \frac{1 - J_0(t)}{t} dt$$

$$\int_x^\infty \frac{Y_0(t)}{t} dt.$$

For more on J_0 and Y_0 see [j0](#) and [y0](#).

Parameters

x [array_like] Values at which to evaluate the integrals.
out [tuple of ndarrays, optional] Optional output arrays for the function results.

Returns

ij0 [scalar or ndarray] The integral for [j0](#)
iy0 [scalar or ndarray] The integral for [y0](#)

scipy.special.iti0k0

`scipy.special.iti0k0(x, out=None) = <ufunc 'iti0k0'>`

Integrals of modified Bessel functions of order 0.

Computes the integrals

$$\int_0^x I_0(t) dt$$

$$\int_0^x K_0(t) dt.$$

For more on I_0 and K_0 see [i0](#) and [k0](#).

Parameters

x [array_like] Values at which to evaluate the integrals.
out [tuple of ndarrays, optional] Optional output arrays for the function results.

Returns

ii0 [scalar or ndarray] The integral for [i0](#)
ik0 [scalar or ndarray] The integral for [k0](#)

scipy.special.it2i0k0

`scipy.special.it2i0k0(x, out=None) = <ufunc 'it2i0k0'>`

Integrals related to modified Bessel functions of order 0.

Computes the integrals

$$\int_0^x \frac{I_0(t) - 1}{t} dt$$

$$\int_x^\infty \frac{K_0(t)}{t} dt.$$

Parameters

x [array_like] Values at which to evaluate the integrals.
out [tuple of ndarrays, optional] Optional output arrays for the function results.

Returns

ii0 [scalar or ndarray] The integral for [i0](#)
ik0 [scalar or ndarray] The integral for [k0](#)

scipy.special.besselpoly

`scipy.special.besselpoly(a, lmb, nu, out=None) = <ufunc 'besselpoly'>`

Weighted integral of the Bessel function of the first kind.

Computes

$$\int_0^1 x^\lambda J_\nu(2ax) dx$$

where J_ν is a Bessel function and $\lambda = lmb, \nu = nu$.

Parameters

a	[array_like] Scale factor inside the Bessel function.
lmb	[array_like] Power of x
nu	[array_like] Order of the Bessel function.
out	[ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
Value of the integral.

Derivatives of Bessel functions

$jvp(v, z[, n])$	Compute derivatives of Bessel functions of the first kind.
$yvp(v, z[, n])$	Compute derivatives of Bessel functions of the second kind.
$kvp(v, z[, n])$	Compute n th derivative of real-order modified Bessel function $Kv(z)$
$ivp(v, z[, n])$	Compute derivatives of modified Bessel functions of the first kind.
$h1vp(v, z[, n])$	Compute n th derivative of Hankel function $H1v(z)$ with respect to z .
$h2vp(v, z[, n])$	Compute n th derivative of Hankel function $H2v(z)$ with respect to z .

scipy.special.jvp

`scipy.special.jvp(v, z, n=1)`

Compute derivatives of Bessel functions of the first kind.

Compute the n th derivative of the Bessel function J_ν with respect to z .

Parameters

v	[float] Order of Bessel function
z	[complex] Argument at which to evaluate the derivative; can be real or complex.
n	[int, default 1] Order of derivative

Returns

scalar or ndarray
Values of the derivative of the Bessel function.

Notes

The derivative is computed using the relation DLFM 10.6.7 [2].

References

[1], [2]

scipy.special.yvp

`scipy.special.yvp` ($v, z, n=1$)

Compute derivatives of Bessel functions of the second kind.

Compute the n th derivative of the Bessel function Y_ν with respect to z .

Parameters

v	[float] Order of Bessel function
z	[complex] Argument at which to evaluate the derivative
n	[int, default 1] Order of derivative

Returns

scalar or ndarray
nth derivative of the Bessel function.

Notes

The derivative is computed using the relation DLFM 10.6.7 [2].

References

[1], [2]

scipy.special.kvp

`scipy.special.kvp` ($v, z, n=1$)

Compute n th derivative of real-order modified Bessel function $K_\nu(z)$

$K_\nu(z)$ is the modified Bessel function of the second kind. Derivative is calculated with respect to z .

Parameters

v	[array_like of float] Order of Bessel function
z	[array_like of complex] Argument at which to evaluate the derivative
n	[int] Order of derivative. Default is first derivative.

Returns

out [ndarray] The results

Notes

The derivative is computed using the relation DLFM 10.29.5 [2].

References

[1], [2]

Examples

Calculate multiple values at order 5:

```
>>> from scipy.special import kvp
>>> kvp(5, (1, 2, 3+5j))
array([-1.84903536e+03+0.j          , -2.57735387e+01+0.j          ,
       -3.06627741e-02+0.08750845j])
```

Calculate for a single value at multiple orders:

```
>>> kvp((4, 4.5, 5), 1)
array([-184.0309, -568.9585, -1849.0354])
```

scipy.special.ivp

`scipy.special.ivp(v, z, n=1)`

Compute derivatives of modified Bessel functions of the first kind.

Compute the n th derivative of the modified Bessel function I_ν with respect to z .

Parameters

v	[array_like] Order of Bessel function
z	[array_like] Argument at which to evaluate the derivative; can be real or complex.
n	[int, default 1] Order of derivative

Returns

scalar or ndarray
 n th derivative of the modified Bessel function.

See also:

[`iv`](#)

Notes

The derivative is computed using the relation DLFM 10.29.5 [2].

References

[1], [2]

scipy.special.h1vp

`scipy.special.h1vp` ($v, z, n=1$)

Compute n th derivative of Hankel function $H_1v(z)$ with respect to z .

Parameters

v [array_like] Order of Hankel function
z [array_like] Argument at which to evaluate the derivative. Can be real or complex.
n [int, default 1] Order of derivative

Returns

scalar or ndarray
Values of the derivative of the Hankel function.

Notes

The derivative is computed using the relation DLFM 10.6.7 [2].

References

[1], [2]

scipy.special.h2vp

`scipy.special.h2vp` ($v, z, n=1$)

Compute n th derivative of Hankel function $H_2v(z)$ with respect to z .

Parameters

v [array_like] Order of Hankel function
z [array_like] Argument at which to evaluate the derivative. Can be real or complex.
n [int, default 1] Order of derivative

Returns

scalar or ndarray
Values of the derivative of the Hankel function.

Notes

The derivative is computed using the relation DLFM 10.6.7 [2].

References

[1], [2]

Spherical Bessel functions

<code>spherical_jn(n, z[, derivative])</code>	Spherical Bessel function of the first kind or its derivative.
<code>spherical_yn(n, z[, derivative])</code>	Spherical Bessel function of the second kind or its derivative.
<code>spherical_in(n, z[, derivative])</code>	Modified spherical Bessel function of the first kind or its derivative.
<code>spherical_kn(n, z[, derivative])</code>	Modified spherical Bessel function of the second kind or its derivative.

scipy.special.spherical_jn

`scipy.special.spherical_jn(n, z, derivative=False)`

Spherical Bessel function of the first kind or its derivative.

Defined as [1],

$$j_n(z) = \sqrt{\frac{\pi}{2z}} J_{n+1/2}(z),$$

where J_n is the Bessel function of the first kind.

Parameters

- n** [int, array_like] Order of the Bessel function ($n \geq 0$).
- z** [complex or float, array_like] Argument of the Bessel function.
- derivative** [bool, optional] If True, the value of the derivative (rather than the function itself) is returned.

Returns

- jn** [ndarray]

Notes

For real arguments greater than the order, the function is computed using the ascending recurrence [2]. For small real or complex arguments, the definitional relation to the cylindrical Bessel function of the first kind is used.

The derivative is computed using the relations [3],

$$j'_n(z) = j_{n-1}(z) - \frac{n+1}{z} j_n(z).$$

$$j'_0(z) = -j_1(z)$$

New in version 0.18.0.

References

[1], [2], [3]

scipy.special.spherical_yn

`scipy.special.spherical_yn` ($n, z, \text{derivative}=\text{False}$)
Spherical Bessel function of the second kind or its derivative.

Defined as [1],

$$y_n(z) = \sqrt{\frac{\pi}{2z}} Y_{n+1/2}(z),$$

where Y_n is the Bessel function of the second kind.

Parameters

n [int, array_like] Order of the Bessel function ($n \geq 0$).
z [complex or float, array_like] Argument of the Bessel function.
derivative [bool, optional] If True, the value of the derivative (rather than the function itself) is returned.

Returns

yn [ndarray]

Notes

For real arguments, the function is computed using the ascending recurrence [2]. For complex arguments, the definitional relation to the cylindrical Bessel function of the second kind is used.

The derivative is computed using the relations [3],

$$y'_n = y_{n-1} - \frac{n+1}{z} y_n.$$
$$y'_0 = -y_1$$

New in version 0.18.0.

References

[1], [2], [3]

scipy.special.spherical_in

`scipy.special.spherical_in` ($n, z, \text{derivative}=\text{False}$)
Modified spherical Bessel function of the first kind or its derivative.

Defined as [1],

$$i_n(z) = \sqrt{\frac{\pi}{2z}} I_{n+1/2}(z),$$

where I_n is the modified Bessel function of the first kind.

Parameters

n [int, array_like] Order of the Bessel function ($n \geq 0$).
z [complex or float, array_like] Argument of the Bessel function.
derivative [bool, optional] If True, the value of the derivative (rather than the function itself) is returned.

Returns

in [ndarray]

Notes

The function is computed using its definitional relation to the modified cylindrical Bessel function of the first kind.

The derivative is computed using the relations [2],

$$i'_n = i_{n-1} - \frac{n+1}{z} i_n.$$

$$i'_1 = i_0$$

New in version 0.18.0.

References

[1], [2]

scipy.special.spherical_kn

`scipy.special.spherical_kn` ($n, z, derivative=False$)

Modified spherical Bessel function of the second kind or its derivative.

Defined as [1],

$$k_n(z) = \sqrt{\frac{\pi}{2z}} K_{n+1/2}(z),$$

where K_n is the modified Bessel function of the second kind.

Parameters

n [int, array_like] Order of the Bessel function ($n \geq 0$).
z [complex or float, array_like] Argument of the Bessel function.
derivative [bool, optional] If True, the value of the derivative (rather than the function itself) is returned.

Returns

kn [ndarray]

Notes

The function is computed using its definitional relation to the modified cylindrical Bessel function of the second kind.

The derivative is computed using the relations [2],

$$k'_n = -k_{n-1} - \frac{n+1}{z} k_n.$$

$$k'_0 = -k_1$$

New in version 0.18.0.

References

[1], [2]

Riccati-Bessel functions

These are not universal functions:

<code>riccati_jn(n, x)</code>	Compute Riccati-Bessel function of the first kind and its derivative.
<code>riccati_yn(n, x)</code>	Compute Riccati-Bessel function of the second kind and its derivative.

scipy.special.riccati_jn

`scipy.special.riccati_jn(n, x)`

Compute Riccati-Bessel function of the first kind and its derivative.

The Riccati-Bessel function of the first kind is defined as $xj_n(x)$, where j_n is the spherical Bessel function of the first kind of order n .

This function computes the value and first derivative of the Riccati-Bessel function for all orders up to and including n .

Parameters

n [int] Maximum order of function to compute
x [float] Argument at which to evaluate

Returns

jn [ndarray] Value of $j_0(x), \dots, j_n(x)$
jnp [ndarray] First derivative $j_0'(x), \dots, j_n'(x)$

Notes

The computation is carried out via backward recurrence, using the relation DLMF 10.51.1 [2].

Wrapper for a Fortran routine created by Shanjie Zhang and Jianming Jin [1].

References

[1], [2]

scipy.special.riccati_yn

`scipy.special.riccati_yn(n, x)`

Compute Riccati-Bessel function of the second kind and its derivative.

The Riccati-Bessel function of the second kind is defined as $xy_n(x)$, where y_n is the spherical Bessel function of the second kind of order n .

This function computes the value and first derivative of the function for all orders up to and including n .

Parameters

n [int] Maximum order of function to compute
x [float] Argument at which to evaluate

Returns

yn [ndarray] Value of $y_0(x), \dots, y_n(x)$
ynp [ndarray] First derivative $y_0'(x), \dots, y_n'(x)$

Notes

The computation is carried out via ascending recurrence, using the relation DLMF 10.51.1 [2].

Wrapper for a Fortran routine created by Shanjie Zhang and Jianming Jin [1].

References

[1], [2]

Struve functions

<code>struve(v, x)</code>	Struve function.
<code>modstruve(v, x)</code>	Modified Struve function.
<code>itstruve0(x)</code>	Integral of the Struve function of order 0.
<code>it2struve0(x)</code>	Integral related to the Struve function of order 0.
<code>itmodstruve0(x)</code>	Integral of the modified Struve function of order 0.

scipy.special.struve

`scipy.special.struve(v, x) = <ufunc 'struve'>`

Struve function.

Return the value of the Struve function of order ν at x . The Struve function is defined as,

$$H_\nu(x) = (x/2)^{\nu+1} \sum_{n=0}^{\infty} \frac{(-1)^n (x/2)^{2n}}{\Gamma(n + \frac{3}{2})\Gamma(n + \nu + \frac{3}{2})},$$

where Γ is the gamma function.

Parameters

v [array_like] Order of the Struve function (float).
x [array_like] Argument of the Struve function (float; must be positive unless ν is an integer).

Returns

H [ndarray] Value of the Struve function of order ν at x .

See also:

`modstruve`

Notes

Three methods discussed in [1] are used to evaluate the Struve function:

- power series
- expansion in Bessel functions (if $|z| < |v| + 20$)
- asymptotic large- z expansion (if $z \geq 0.7v + 12$)

Rounding errors are estimated based on the largest terms in the sums, and the result associated with the smallest error is returned.

References

[1]

scipy.special.modstruve

`scipy.special.modstruve(v, x) = <ufunc 'modstruve'>`
Modified Struve function.

Return the value of the modified Struve function of order ν at x . The modified Struve function is defined as,

$$L_\nu(x) = -i \exp(-\pi\nu/2) H_\nu(ix),$$

where H_ν is the Struve function.

Parameters

- | | |
|----------|--|
| v | [array_like] Order of the modified Struve function (float). |
| x | [array_like] Argument of the Struve function (float; must be positive unless ν is an integer). |

Returns

- | | |
|----------|---|
| L | [ndarray] Value of the modified Struve function of order ν at x . |
|----------|---|

See also:

[*struve*](#)

Notes

Three methods discussed in [1] are used to evaluate the function:

- power series
- expansion in Bessel functions (if $|x| < |v| + 20$)
- asymptotic large- x expansion (if $x \geq 0.7v + 12$)

Rounding errors are estimated based on the largest terms in the sums, and the result associated with the smallest error is returned.

References

[1]

scipy.special.itstruve0

`scipy.special.itstruve0(x) = <ufunc 'itstruve0'>`
Integral of the Struve function of order 0.

$$I = \int_0^x H_0(t) dt$$

Parameters

x [array_like] Upper limit of integration (float).

Returns

I [ndarray] The integral of H_0 from 0 to x .

See also:

[struve](#)

Notes

Wrapper for a Fortran routine created by Shanjie Zhang and Jianming Jin [1].

References

[1]

scipy.special.it2struve0

`scipy.special.it2struve0(x) = <ufunc 'it2struve0'>`
Integral related to the Struve function of order 0.

Returns the integral,

$$\int_x^\infty \frac{H_0(t)}{t} dt$$

where H_0 is the Struve function of order 0.

Parameters

x [array_like] Lower limit of integration.

Returns

I [ndarray] The value of the integral.

See also:

[struve](#)

Notes

Wrapper for a Fortran routine created by Shanjie Zhang and Jianming Jin [1].

References

[1]

scipy.special.itmodstruve0

`scipy.special.itmodstruve0(x) = <ufunc 'itmodstruve0'>`
 Integral of the modified Struve function of order 0.

$$I = \int_0^x L_0(t) dt$$

Parameters

x [array_like] Upper limit of integration (float).

Returns

I [ndarray] The integral of L_0 from 0 to x .

Notes

Wrapper for a Fortran routine created by Shanjie Zhang and Jianming Jin [1].

References

[1]

Raw statistical functions

See also:

`scipy.stats`: Friendly versions of these functions.

<code>bdtr(k, n, p)</code>	Binomial distribution cumulative distribution function.
<code>bdtrc(k, n, p)</code>	Binomial distribution survival function.
<code>bdtri(k, n, y)</code>	Inverse function to <code>bdtr</code> with respect to p .
<code>bdtrik(y, n, p)</code>	Inverse function to <code>bdtr</code> with respect to k .
<code>bdtrin(k, y, p)</code>	Inverse function to <code>bdtr</code> with respect to n .
<code>btctr(a, b, x)</code>	Cumulative distribution function of the beta distribution.
<code>btctri(a, b, p)</code>	The p -th quantile of the beta distribution.
<code>btctria(p, b, x)</code>	Inverse of <code>btctr</code> with respect to a .
<code>btctrib(a, p, x)</code>	Inverse of <code>btctr</code> with respect to b .
<code>fdtr(dfn, dfd, x)</code>	F cumulative distribution function.
<code>fdtrc(dfn, dfd, x)</code>	F survival function.
<code>fdtri(dfn, dfd, p)</code>	The p -th quantile of the F-distribution.
<code>fdtridf(dfn, p, x)</code>	Inverse to <code>fdtr</code> vs <code>dfd</code>
<code>gdtr(a, b, x)</code>	Gamma distribution cumulative distribution function.

continues on next page

Table 229 – continued from previous page

<i>gdtrc</i> (a, b, x)	Gamma distribution survival function.
<i>gdtria</i> (p, b, x[, out])	Inverse of <i>gdttr</i> vs a.
<i>gdtrib</i> (a, p, x[, out])	Inverse of <i>gdttr</i> vs b.
<i>gdtrix</i> (a, b, p[, out])	Inverse of <i>gdttr</i> vs x.
<i>nbdtr</i> (k, n, p)	Negative binomial cumulative distribution function.
<i>nbdtrc</i> (k, n, p)	Negative binomial survival function.
<i>nbdtri</i> (k, n, y)	Inverse of <i>nbdtr</i> vs p.
<i>nbdtrik</i> (y, n, p)	Inverse of <i>nbdtr</i> vs k.
<i>nbdtrin</i> (k, y, p)	Inverse of <i>nbdtr</i> vs n.
<i>ncfdtr</i> (dfn, dfd, nc, f)	Cumulative distribution function of the non-central F distribution.
<i>ncfdtridfd</i> (dfn, p, nc, f)	Calculate degrees of freedom (denominator) for the non-central F-distribution.
<i>ncfdtridfn</i> (p, dfd, nc, f)	Calculate degrees of freedom (numerator) for the non-central F-distribution.
<i>ncfdtri</i> (dfn, dfd, nc, p)	Inverse with respect to <i>f</i> of the CDF of the non-central F distribution.
<i>ncfdtrinc</i> (dfn, dfd, p, f)	Calculate non-centrality parameter for non-central F distribution.
<i>nctdtr</i> (df, nc, t)	Cumulative distribution function of the non-central <i>t</i> distribution.
<i>nctdtridf</i> (p, nc, t)	Calculate degrees of freedom for non-central <i>t</i> distribution.
<i>nctdtrit</i> (df, nc, p)	Inverse cumulative distribution function of the non-central <i>t</i> distribution.
<i>nctdtrinc</i> (df, p, t)	Calculate non-centrality parameter for non-central <i>t</i> distribution.
<i>nrtrimn</i> (p, x, std)	Calculate mean of normal distribution given other params.
<i>nrtrisd</i> (p, x, mn)	Calculate standard deviation of normal distribution given other params.
<i>pdtr</i> (k, m[, out])	Poisson cumulative distribution function.
<i>pdtrc</i> (k, m)	Poisson survival function
<i>pdtri</i> (k, y)	Inverse to <i>pdtr</i> vs m
<i>pdtrik</i> (p, m)	Inverse to <i>pdtr</i> vs k
<i>stdtr</i> (df, t)	Student <i>t</i> distribution cumulative distribution function
<i>stdtridf</i> (p, t)	Inverse of <i>stdtr</i> vs df
<i>stdtrit</i> (df, p)	Inverse of <i>stdtr</i> vs <i>t</i>
<i>chdtr</i> (v, x[, out])	Chi square cumulative distribution function.
<i>chdtrc</i> (v, x[, out])	Chi square survival function.
<i>chdtri</i> (v, p[, out])	Inverse to <i>chdtrc</i> with respect to <i>x</i> .
<i>chdtriv</i> (p, x[, out])	Inverse to <i>chdtr</i> with respect to <i>v</i> .
<i>ndtr</i> (x)	Gaussian cumulative distribution function.
<i>log_ndtr</i> (x)	Logarithm of Gaussian cumulative distribution function.
<i>ndtri</i> (y)	Inverse of <i>ndtr</i> vs <i>x</i>
<i>chndtr</i> (x, df, nc)	Non-central chi square cumulative distribution function
<i>chndtridf</i> (x, p, nc)	Inverse to <i>chndtr</i> vs <i>df</i>
<i>chndtrinc</i> (x, df, p)	Inverse to <i>chndtr</i> vs <i>nc</i>
<i>chndtrix</i> (p, df, nc)	Inverse to <i>chndtr</i> vs <i>x</i>
<i>smirnov</i> (n, d)	Kolmogorov-Smirnov complementary cumulative distribution function

continues on next page

Table 229 – continued from previous page

<code>smirnovi(n, p)</code>	Inverse to <code>smirnov</code>
<code>kolmogorov(y)</code>	Complementary cumulative distribution (Survival Function) function of Kolmogorov distribution.
<code>kolmogi(p)</code>	Inverse Survival Function of Kolmogorov distribution
<code>tklmbda(x, lmbda)</code>	Tukey-Lambda cumulative distribution function
<code>logit(x)</code>	Logit ufunc for ndarrays.
<code>expit(x)</code>	Expit (a.k.a.
<code>boxcox(x, lmbda)</code>	Compute the Box-Cox transformation.
<code>boxcox1p(x, lmbda)</code>	Compute the Box-Cox transformation of $1 + x$.
<code>inv_boxcox(y, lmbda)</code>	Compute the inverse of the Box-Cox transformation.
<code>inv_boxcox1p(y, lmbda)</code>	Compute the inverse of the Box-Cox transformation.
<code>owens_t(h, a)</code>	Owen's T Function.

scipy.special.bdtr

`scipy.special.bdtr(k, n, p) = <ufunc 'bdtr'>`

Binomial distribution cumulative distribution function.

Sum of the terms 0 through $\text{floor}(k)$ of the Binomial probability density.

$$\text{bdtr}(k, n, p) = \sum_{j=0}^{\lfloor k \rfloor} \binom{n}{j} p^j (1-p)^{n-j}$$

Parameters

- k** [array_like] Number of successes (double), rounded down to the nearest integer.
- n** [array_like] Number of events (int).
- p** [array_like] Probability of success in a single event (float).

Returns

- y** [ndarray] Probability of $\text{floor}(k)$ or fewer successes in n independent events with success probabilities of p .

Notes

The terms are not summed directly; instead the regularized incomplete beta function is employed, according to the formula,

$$\text{bdtr}(k, n, p) = I_{1-p}(n - \lfloor k \rfloor, \lfloor k \rfloor + 1).$$

Wrapper for the Cephes [1] routine `bdtr`.

References

- [1]

scipy.special.bdtrc

`scipy.special.bdtrc(k, n, p) = <ufunc 'bdtrc'>`

Binomial distribution survival function.

Sum of the terms $\text{floor}(k) + 1$ through n of the binomial probability density,

$$\text{bdtrc}(k, n, p) = \sum_{j=\lfloor k \rfloor + 1}^n \binom{n}{j} p^j (1-p)^{n-j}$$

Parameters

- k** [array_like] Number of successes (double), rounded down to nearest integer.
- n** [array_like] Number of events (int)
- p** [array_like] Probability of success in a single event.

Returns

- y** [ndarray] Probability of $\text{floor}(k) + 1$ or more successes in n independent events with success probabilities of p .

See also:

[*bdtr*](#)

[*betainc*](#)

Notes

The terms are not summed directly; instead the regularized incomplete beta function is employed, according to the formula,

$$\text{bdtrc}(k, n, p) = I_p(\lfloor k \rfloor + 1, n - \lfloor k \rfloor).$$

Wrapper for the Cephes [1] routine *bdtrc*.

References

[1]

scipy.special.bdtri

`scipy.special.bdtri(k, n, y) = <ufunc 'bdtri'>`

Inverse function to *bdtr* with respect to p .

Finds the event probability p such that the sum of the terms 0 through k of the binomial probability density is equal to the given cumulative probability y .

Parameters

- k** [array_like] Number of successes (float), rounded down to the nearest integer.
- n** [array_like] Number of events (float)
- y** [array_like] Cumulative probability (probability of k or fewer successes in n events).

Returns

- p** [ndarray] The event probability such that $\text{bdtr}(\text{floor } k \text{ rfloor}, n, p) = y$.

See also:

bdtr

betaincinv

Notes

The computation is carried out using the inverse beta integral function and the relation,:

$$1 - p = \text{betaincinv}(n - k, k + 1, y).$$

Wrapper for the Cephes [1] routine *bdtri*.

References

[1]

scipy.special.bdtrik

`scipy.special.bdtrik(y, n, p) = <ufunc 'bdtrik'>`

Inverse function to *bdtr* with respect to *k*.

Finds the number of successes *k* such that the sum of the terms 0 through *k* of the Binomial probability density for *n* events with probability *p* is equal to the given cumulative probability *y*.

Parameters

y [array_like] Cumulative probability (probability of *k* or fewer successes in *n* events).
n [array_like] Number of events (float).
p [array_like] Success probability (float).

Returns

k [ndarray] The number of successes *k* such that $bdtr(k, n, p) = y$.

See also:

bdtr

Notes

Formula 26.5.24 of [1] is used to reduce the binomial distribution to the cumulative incomplete beta distribution.

Computation of *k* involves a search for a value that produces the desired value of *y*. The search relies on the monotonicity of *y* with *k*.

Wrapper for the CDFLIB [2] Fortran routine *cdfbin*.

References

[1], [2]

scipy.special.bdtrn

`scipy.special.bdtrn(k, y, p) = <ufunc 'bdtrn'>`

Inverse function to `bdtr` with respect to n .

Finds the number of events n such that the sum of the terms 0 through k of the Binomial probability density for events with probability p is equal to the given cumulative probability y .

Parameters

k [array_like] Number of successes (float).
y [array_like] Cumulative probability (probability of k or fewer successes in n events).
p [array_like] Success probability (float).

Returns

n [ndarray] The number of events n such that $bdtr(k, n, p) = y$.

See also:

`bdtr`

Notes

Formula 26.5.24 of [1] is used to reduce the binomial distribution to the cumulative incomplete beta distribution.

Computation of n involves a search for a value that produces the desired value of y . The search relies on the monotonicity of y with n .

Wrapper for the CDFLIB [2] Fortran routine `cdfbin`.

References

[1], [2]

scipy.special.btdtr

`scipy.special.btdtr(a, b, x) = <ufunc 'btdtr'>`

Cumulative distribution function of the beta distribution.

Returns the integral from zero to x of the beta probability density function,

$$I = \int_0^x \frac{\Gamma(a+b)}{\Gamma(a)\Gamma(b)} t^{a-1} (1-t)^{b-1} dt$$

where Γ is the gamma function.

Parameters

a [array_like] Shape parameter ($a > 0$).
b [array_like] Shape parameter ($b > 0$).
x [array_like] Upper limit of integration, in $[0, 1]$.

Returns

I [ndarray] Cumulative distribution function of the beta distribution with parameters a and b at x .

See also:

[*betainc*](#)

Notes

This function is identical to the incomplete beta integral function [*betainc*](#).

Wrapper for the Cephes [1] routine [*btdtr*](#).

References

[1]

`scipy.special.btdtri`

`scipy.special.btdtri(a, b, p) = <ufunc 'btdtri'>`

The p -th quantile of the beta distribution.

This function is the inverse of the beta cumulative distribution function, [*btdtr*](#), returning the value of x for which $btdtr(a, b, x) = p$, or

$$p = \int_0^x \frac{\Gamma(a+b)}{\Gamma(a)\Gamma(b)} t^{a-1} (1-t)^{b-1} dt$$

Parameters

- a** [array_like] Shape parameter ($a > 0$).
- b** [array_like] Shape parameter ($b > 0$).
- p** [array_like] Cumulative probability, in $[0, 1]$.

Returns

- x** [ndarray] The quantile corresponding to p .

See also:

[*betaincinv*](#)

[*btdtr*](#)

Notes

The value of x is found by interval halving or Newton iterations.

Wrapper for the Cephes [1] routine [*incbi*](#), which solves the equivalent problem of finding the inverse of the incomplete beta integral.

References

[1]

scipy.special.btdtria

`scipy.special.btdtria(p, b, x) = <ufunc 'btdtria'>`

Inverse of `btdtr` with respect to a .

This is the inverse of the beta cumulative distribution function, `btdtr`, considered as a function of a , returning the value of a for which $btdtr(a, b, x) = p$, or

$$p = \int_0^x \frac{\Gamma(a+b)}{\Gamma(a)\Gamma(b)} t^{a-1} (1-t)^{b-1} dt$$

Parameters

- p** [array_like] Cumulative probability, in [0, 1].
- b** [array_like] Shape parameter ($b > 0$).
- x** [array_like] The quantile, in [0, 1].

Returns

- a** [ndarray] The value of the shape parameter a such that $btdtr(a, b, x) = p$.

See also:

`btdtr`

Cumulative distribution function of the beta distribution.

`btdtri`

Inverse with respect to x .

`btdtrib`

Inverse with respect to b .

Notes

Wrapper for the CDFLIB [1] Fortran routine `cdfbet`.

The cumulative distribution function p is computed using a routine by DiDinato and Morris [2]. Computation of a involves a search for a value that produces the desired value of p . The search relies on the monotonicity of p with a .

References

[1], [2]

scipy.special.btdtrib

`scipy.special.btdtrib(a, p, x) = <ufunc 'btdtrib'>`

Inverse of `btdtr` with respect to b .

This is the inverse of the beta cumulative distribution function, `btdtr`, considered as a function of b , returning the value of b for which `btdtr(a, b, x) = p`, or

$$p = \int_0^x \frac{\Gamma(a+b)}{\Gamma(a)\Gamma(b)} t^{a-1} (1-t)^{b-1} dt$$

Parameters

- a** [array_like] Shape parameter ($a > 0$).
- p** [array_like] Cumulative probability, in $[0, 1]$.
- x** [array_like] The quantile, in $[0, 1]$.

Returns

- b** [ndarray] The value of the shape parameter b such that `btdtr(a, b, x) = p`.

See also:**`btdtr`**

Cumulative distribution function of the beta distribution.

`btdtri`

Inverse with respect to x .

`btdtria`

Inverse with respect to a .

Notes

Wrapper for the CDFLIB [1] Fortran routine `cdfbet`.

The cumulative distribution function p is computed using a routine by DiDinato and Morris [2]. Computation of b involves a search for a value that produces the desired value of p . The search relies on the monotonicity of p with b .

References

[1], [2]

scipy.special.fdttr

`scipy.special.fdttr(dfn, dfd, x) = <ufunc 'fdttr'>`

F cumulative distribution function.

Returns the value of the cumulative distribution function of the F-distribution, also known as Snedecor's F-distribution or the Fisher-Snedecor distribution.

The F-distribution with parameters d_n and d_d is the distribution of the random variable,

$$X = \frac{U_n/d_n}{U_d/d_d},$$

where U_n and U_d are random variables distributed χ^2 , with d_n and d_d degrees of freedom, respectively.

Parameters

dfn	[array_like] First parameter (positive float).
dfd	[array_like] Second parameter (positive float).
x	[array_like] Argument (nonnegative float).

Returns

y	[ndarray] The CDF of the F-distribution with parameters <i>dfn</i> and <i>dfd</i> at <i>x</i> .
----------	---

Notes

The regularized incomplete beta function is used, according to the formula,

$$F(d_n, d_d; x) = I_{x d_n / (d_d + x d_n)}(d_n/2, d_d/2).$$

Wrapper for the Cephes [1] routine *fdtr*.

References

[1]

scipy.special.fdtc

`scipy.special.fdtc(dfn, dfd, x) = <ufunc 'fdtrc'>`
F survival function.

Returns the complemented F-distribution function (the integral of the density from *x* to infinity).

Parameters

dfn	[array_like] First parameter (positive float).
dfd	[array_like] Second parameter (positive float).
x	[array_like] Argument (nonnegative float).

Returns

y	[ndarray] The complemented F-distribution function with parameters <i>dfn</i> and <i>dfd</i> at <i>x</i> .
----------	--

See also:

fdtr

Notes

The regularized incomplete beta function is used, according to the formula,

$$F(d_n, d_d; x) = I_{d_d / (d_d + x d_n)}(d_d/2, d_n/2).$$

Wrapper for the Cephes [1] routine *fdtrc*.

References

[1]

scipy.special.fdtri

`scipy.special.fdtri(dfn, dfd, p) = <ufunc 'fdtri'>`

The p -th quantile of the F-distribution.

This function is the inverse of the F-distribution CDF, `fdtr`, returning the x such that $fdtr(dfn, dfd, x) = p$.

Parameters

dfn [array_like] First parameter (positive float).
dfd [array_like] Second parameter (positive float).
p [array_like] Cumulative probability, in [0, 1].

Returns

x [ndarray] The quantile corresponding to p .

Notes

The computation is carried out using the relation to the inverse regularized beta function, $I_x^{-1}(a, b)$. Let $z = I_p^{-1}(d_d/2, d_n/2)$. Then,

$$x = \frac{d_d(1-z)}{d_n z}.$$

If p is such that $x < 0.5$, the following relation is used instead for improved stability: let $z' = I_{1-p}^{-1}(d_n/2, d_d/2)$. Then,

$$x = \frac{d_d z'}{d_n(1-z')}.$$

Wrapper for the Cephes [1] routine `fdtri`.

References

[1]

scipy.special.fdtridfd

`scipy.special.fdtridfd(dfn, p, x) = <ufunc 'fdtridfd'>`

Inverse to `fdtr` vs `dfd`

Finds the F density argument `dfd` such that `fdtr(dfn, dfd, x) == p`.

scipy.special.gdtr

`scipy.special.gdtr(a, b, x) = <ufunc 'gdtr'>`

Gamma distribution cumulative distribution function.

Returns the integral from zero to x of the gamma probability density function,

$$F = \int_0^x \frac{a^b}{\Gamma(b)} t^{b-1} e^{-at} dt,$$

where Γ is the gamma function.

Parameters

- a** [array_like] The rate parameter of the gamma distribution, sometimes denoted β (float). It is also the reciprocal of the scale parameter θ .
- b** [array_like] The shape parameter of the gamma distribution, sometimes denoted α (float).
- x** [array_like] The quantile (upper limit of integration; float).

Returns

- F** [ndarray] The CDF of the gamma distribution with parameters a and b evaluated at x .

See also:

[*gdtrc*](#)

1 - CDF of the gamma distribution.

Notes

The evaluation is carried out using the relation to the incomplete gamma integral (regularized gamma function).

Wrapper for the Cephes [1] routine *gdtcr*.

References

[1]

scipy.special.gdtrc

`scipy.special.gdtrc(a, b, x) = <ufunc 'gdtrc'>`

Gamma distribution survival function.

Integral from x to infinity of the gamma probability density function,

$$F = \int_x^{\infty} \frac{a^b}{\Gamma(b)} t^{b-1} e^{-at} dt,$$

where Γ is the gamma function.

Parameters

- a** [array_like] The rate parameter of the gamma distribution, sometimes denoted β (float). It is also the reciprocal of the scale parameter θ .
- b** [array_like] The shape parameter of the gamma distribution, sometimes denoted α (float).
- x** [array_like] The quantile (lower limit of integration; float).

Returns

- F** [ndarray] The survival function of the gamma distribution with parameters a and b evaluated at x .

See also:

[*gdtcr*](#), [*gdtcrx*](#)

Notes

The evaluation is carried out using the relation to the incomplete gamma integral (regularized gamma function).
Wrapper for the Cephes [1] routine *gdtrc*.

References

[1]

scipy.special.gdtria

`scipy.special.gdtria(p, b, x, out=None) = <ufunc 'gdtria'>`

Inverse of *gdtr* vs *a*.

Returns the inverse with respect to the parameter *a* of $p = \text{gdtr}(a, b, x)$, the cumulative distribution function of the gamma distribution.

Parameters

- p** [array_like] Probability values.
- b** [array_like] *b* parameter values of *gdtr*(*a*, *b*, *x*). *b* is the “shape” parameter of the gamma distribution.
- x** [array_like] Nonnegative real values, from the domain of the gamma distribution.
- out** [ndarray, optional] If a fourth argument is given, it must be a `numpy.ndarray` whose size matches the broadcast result of *a*, *b* and *x*. *out* is then the array returned by the function.

Returns

- a** [ndarray] Values of the *a* parameter such that $p = \text{gdtr}(a, b, x)$. $1/a$ is the “scale” parameter of the gamma distribution.

See also:

gdtr

CDF of the gamma distribution.

gdtrib

Inverse with respect to *b* of *gdtr*(*a*, *b*, *x*).

gdtrix

Inverse with respect to *x* of *gdtr*(*a*, *b*, *x*).

Notes

Wrapper for the CDFLIB [1] Fortran routine *cdfgam*.

The cumulative distribution function *p* is computed using a routine by DiDinato and Morris [2]. Computation of *a* involves a search for a value that produces the desired value of *p*. The search relies on the monotonicity of *p* with *a*.

References

[1], [2]

Examples

First evaluate `gdtr`.

```
>>> from scipy.special import gdtr, gdtria
>>> p = gdtr(1.2, 3.4, 5.6)
>>> print(p)
0.94378087442
```

Verify the inverse.

```
>>> gdtria(p, 3.4, 5.6)
1.2
```

scipy.special.gdtrib

`scipy.special.gdtrib(a, p, x, out=None) = <ufunc 'gdtrib'>`

Inverse of `gdtr` vs `b`.

Returns the inverse with respect to the parameter `b` of `p = gdtr(a, b, x)`, the cumulative distribution function of the gamma distribution.

Parameters

- a** [array_like] `a` parameter values of `gdtr(a, b, x)`. $1/a$ is the “scale” parameter of the gamma distribution.
- p** [array_like] Probability values.
- x** [array_like] Nonnegative real values, from the domain of the gamma distribution.
- out** [ndarray, optional] If a fourth argument is given, it must be a `numpy.ndarray` whose size matches the broadcast result of `a`, `b` and `x`. `out` is then the array returned by the function.

Returns

- b** [ndarray] Values of the `b` parameter such that `p = gdtr(a, b, x)`. `b` is the “shape” parameter of the gamma distribution.

See also:

`gdtr`

CDF of the gamma distribution.

`gdtria`

Inverse with respect to `a` of `gdtr(a, b, x)`.

`gdtrix`

Inverse with respect to `x` of `gdtr(a, b, x)`.

Notes

Wrapper for the CDFLIB [1] Fortran routine *cdfgam*.

The cumulative distribution function p is computed using a routine by DiDinato and Morris [2]. Computation of b involves a search for a value that produces the desired value of p . The search relies on the monotonicity of p with b .

References

[1], [2]

Examples

First evaluate *gdtr*.

```
>>> from scipy.special import gdtr, gdtrib
>>> p = gdtr(1.2, 3.4, 5.6)
>>> print(p)
0.94378087442
```

Verify the inverse.

```
>>> gdtrib(1.2, p, 5.6)
3.3999999999723882
```

scipy.special.gdtrix

`scipy.special.gdtrix(a, b, p, out=None) = <ufunc 'gdtrix'>`

Inverse of *gdtr* vs x .

Returns the inverse with respect to the parameter x of $p = \text{gdtr}(a, b, x)$, the cumulative distribution function of the gamma distribution. This is also known as the p th quantile of the distribution.

Parameters

- a** [array_like] a parameter values of $\text{gdtr}(a, b, x)$. $1/a$ is the “scale” parameter of the gamma distribution.
- b** [array_like] b parameter values of $\text{gdtr}(a, b, x)$. b is the “shape” parameter of the gamma distribution.
- p** [array_like] Probability values.
- out** [ndarray, optional] If a fourth argument is given, it must be a `numpy.ndarray` whose size matches the broadcast result of a , b and x . *out* is then the array returned by the function.

Returns

- x** [ndarray] Values of the x parameter such that $p = \text{gdtr}(a, b, x)$.

See also:

[*gdtr*](#)

CDF of the gamma distribution.

[*gdtria*](#)

Inverse with respect to a of $\text{gdtr}(a, b, x)$.

gdtrib

Inverse with respect to b of $gdr(a, b, x)$.

Notes

Wrapper for the CDFLIB [1] Fortran routine *cdfgam*.

The cumulative distribution function p is computed using a routine by DiDinato and Morris [2]. Computation of x involves a search for a value that produces the desired value of p . The search relies on the monotonicity of p with x .

References

[1], [2]

Examples

First evaluate *gdr*.

```
>>> from scipy.special import gdr, gdtrix
>>> p = gdr(1.2, 3.4, 5.6)
>>> print(p)
0.94378087442
```

Verify the inverse.

```
>>> gdtrix(1.2, 3.4, p)
5.5999999999999996
```

scipy.special.nbdtr

`scipy.special.nbdtr(k, n, p) = <ufunc 'nbdtr'>`

Negative binomial cumulative distribution function.

Returns the sum of the terms 0 through k of the negative binomial distribution probability mass function,

$$F = \sum_{j=0}^k \binom{n+j-1}{j} p^n (1-p)^j.$$

In a sequence of Bernoulli trials with individual success probabilities p , this is the probability that k or fewer failures precede the n th success.

Parameters

k [array_like] The maximum number of allowed failures (nonnegative int).
n [array_like] The target number of successes (positive int).
p [array_like] Probability of success in a single event (float).

Returns

F [ndarray] The probability of k or fewer failures before n successes in a sequence of events with individual success probability p .

See also:

nbdtrc

Notes

If floating point values are passed for k or n , they will be truncated to integers.

The terms are not summed directly; instead the regularized incomplete beta function is employed, according to the formula,

$$\text{nbdtr}(k, n, p) = I_p(n, k + 1).$$

Wrapper for the Cephes [1] routine `nbdtr`.

References

[1]

`scipy.special.nbdtrc`

`scipy.special.nbdtrc(k, n, p) = <ufunc 'nbdtrc'>`

Negative binomial survival function.

Returns the sum of the terms $k + 1$ to infinity of the negative binomial distribution probability mass function,

$$F = \sum_{j=k+1}^{\infty} \binom{n+j-1}{j} p^n (1-p)^j.$$

In a sequence of Bernoulli trials with individual success probabilities p , this is the probability that more than k failures precede the n th success.

Parameters

- k** [array_like] The maximum number of allowed failures (nonnegative int).
- n** [array_like] The target number of successes (positive int).
- p** [array_like] Probability of success in a single event (float).

Returns

- F** [ndarray] The probability of $k + 1$ or more failures before n successes in a sequence of events with individual success probability p .

Notes

If floating point values are passed for k or n , they will be truncated to integers.

The terms are not summed directly; instead the regularized incomplete beta function is employed, according to the formula,

$$\text{nbdtrc}(k, n, p) = I_{1-p}(k + 1, n).$$

Wrapper for the Cephes [1] routine `nbdtrc`.

References

[1]

scipy.special.nbdtri

`scipy.special.nbdtri(k, n, y) = <ufunc 'nbdtri'>`

Inverse of `nbdtr` vs p .

Returns the inverse with respect to the parameter p of $y = nbdtr(k, n, p)$, the negative binomial cumulative distribution function.

Parameters

k [array_like] The maximum number of allowed failures (nonnegative int).
n [array_like] The target number of successes (positive int).
y [array_like] The probability of k or fewer failures before n successes (float).

Returns

p [ndarray] Probability of success in a single event (float) such that $nbdtr(k, n, p) = y$.

See also:

`nbdtr`

Cumulative distribution function of the negative binomial.

`nbdtrik`

Inverse with respect to k of $nbdtr(k, n, p)$.

`nbdtrin`

Inverse with respect to n of $nbdtr(k, n, p)$.

Notes

Wrapper for the Cephes [1] routine `nbdtri`.

References

[1]

scipy.special.nbdtrik

`scipy.special.nbdtrik(y, n, p) = <ufunc 'nbdtrik'>`

Inverse of `nbdtr` vs k .

Returns the inverse with respect to the parameter k of $y = nbdtr(k, n, p)$, the negative binomial cumulative distribution function.

Parameters

y [array_like] The probability of k or fewer failures before n successes (float).
n [array_like] The target number of successes (positive int).
p [array_like] Probability of success in a single event (float).

Returns

k [ndarray] The maximum number of allowed failures such that $nbdtr(k, n, p) = y$.

See also:

nbdt

Cumulative distribution function of the negative binomial.

nbdt

Inverse with respect to p of $nbdt(k, n, p)$.

nbdt

Inverse with respect to n of $nbdt(k, n, p)$.

Notes

Wrapper for the CDFLIB [1] Fortran routine *cdfnbn*.

Formula 26.5.26 of [2],

$$\sum_{j=k+1}^{\infty} \binom{n+j-1}{j} p^n (1-p)^j = I_{1-p}(k+1, n),$$

is used to reduce calculation of the cumulative distribution function to that of a regularized incomplete beta I .

Computation of k involves a search for a value that produces the desired value of y . The search relies on the monotonicity of y with k .

References

[1], [2]

scipy.special.nbdtr

`scipy.special.nbdtr(k, y, p) = <ufunc 'nbdtr'>`

Inverse of *nbdt* vs n .

Returns the inverse with respect to the parameter n of $y = nbdt(k, n, p)$, the negative binomial cumulative distribution function.

Parameters

k [array_like] The maximum number of allowed failures (nonnegative int).
y [array_like] The probability of k or fewer failures before n successes (float).
p [array_like] Probability of success in a single event (float).

Returns

n [ndarray] The number of successes n such that $nbdt(k, n, p) = y$.

See also:

nbdt

Cumulative distribution function of the negative binomial.

nbdt

Inverse with respect to p of $nbdt(k, n, p)$.

nbdt

Inverse with respect to k of $nbdt(k, n, p)$.

Notes

Wrapper for the CDFLIB [1] Fortran routine *cdfnbn*.

Formula 26.5.26 of [2],

$$\sum_{j=k+1}^{\infty} \binom{n+j-1}{j} p^n (1-p)^j = I_{1-p}(k+1, n),$$

is used to reduce calculation of the cumulative distribution function to that of a regularized incomplete beta I .

Computation of n involves a search for a value that produces the desired value of y . The search relies on the monotonicity of y with n .

References

[1], [2]

scipy.special.ncfdtr

`scipy.special.ncfdtr(dfn, dfd, nc, f) = <ufunc 'ncfdtr'>`
Cumulative distribution function of the non-central F distribution.

The non-central F describes the distribution of,

$$Z = \frac{X/d_n}{Y/d_d}$$

where X and Y are independently distributed, with X distributed non-central χ^2 with noncentrality parameter nc and d_n degrees of freedom, and Y distributed χ^2 with d_d degrees of freedom.

Parameters

dfn	[array_like] Degrees of freedom of the numerator sum of squares. Range (0, inf).
dfd	[array_like] Degrees of freedom of the denominator sum of squares. Range (0, inf).
nc	[array_like] Noncentrality parameter. Should be in range (0, 1e4).
f	[array_like] Quantiles, i.e. the upper limit of integration.

Returns

cdf	[float or ndarray] The calculated CDF. If all inputs are scalar, the return will be a float. Otherwise it will be an array.
------------	---

See also:

ncfdtri

Quantile function; inverse of *ncfdtr* with respect to f .

ncfdtridfd

Inverse of *ncfdtr* with respect to dfd .

ncfdtridfn

Inverse of *ncfdtr* with respect to dfn .

ncfdtrinc

Inverse of *ncfdtr* with respect to nc .

Notes

Wrapper for the CDFLIB [1] Fortran routine *cdffnc*.

The cumulative distribution function is computed using Formula 26.6.20 of [2]:

$$F(d_n, d_d, n_c, f) = \sum_{j=0}^{\infty} e^{-n_c/2} \frac{(n_c/2)^j}{j!} I_x\left(\frac{d_n}{2} + j, \frac{d_d}{2}\right),$$

where I is the regularized incomplete beta function, and $x = fd_n/(fd_n + d_d)$.

The computation time required for this routine is proportional to the noncentrality parameter nc . Very large values of this parameter can consume immense computer resources. This is why the search range is bounded by 10,000.

References

[1], [2]

Examples

```
>>> from scipy import special
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
```

Plot the CDF of the non-central F distribution, for $nc=0$. Compare with the F-distribution from `scipy.stats`:

```
>>> x = np.linspace(-1, 8, num=500)
>>> dfn = 3
>>> dfd = 2
>>> ncf_stats = stats.f.cdf(x, dfn, dfd)
>>> ncf_special = special.ncfdtr(dfn, dfd, 0, x)
```

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> ax.plot(x, ncf_stats, 'b-', lw=3)
>>> ax.plot(x, ncf_special, 'r-')
>>> plt.show()
```

`scipy.special.ncfdtridfd`

`scipy.special.ncfdtridfd(dfn, p, nc, f) = <ufunc 'ncfdtridfd'>`

Calculate degrees of freedom (denominator) for the noncentral F-distribution.


This is the inverse with respect to dfd of `ncfdtr`. See `ncfdtr` for more details.

Parameters

dfn	[array_like] Degrees of freedom of the numerator sum of squares. Range (0, inf).
p	[array_like] Value of the cumulative distribution function. Must be in the range [0, 1].
nc	[array_like] Noncentrality parameter. Should be in range (0, 1e4).
f	[array_like] Quantiles, i.e., the upper limit of integration.

Returns

dfd	[float] Degrees of freedom of the denominator sum of squares.
------------	---



See also:

ncfdtr

CDF of the non-central F distribution.

ncfdtri

Quantile function; inverse of *ncfdtr* with respect to *f*.

ncfdtridfn

Inverse of *ncfdtr* with respect to *dfn*.

ncfdtrinc

Inverse of *ncfdtr* with respect to *nc*.

Notes

The value of the cumulative noncentral F distribution is not necessarily monotone in either degrees of freedom. There thus may be two values that provide a given CDF value. This routine assumes monotonicity and will find an arbitrary one of the two values.

Examples

```
>>> from scipy.special import ncfdtr, ncfdtridfd
```

Compute the CDF for several values of *dfd*:

```
>>> dfd = [1, 2, 3]
>>> p = ncfdtr(2, dfd, 0.25, 15)
>>> p
array([ 0.8097138 ,  0.93020416,  0.96787852])
```

Compute the inverse. We recover the values of *dfd*, as expected:

```
>>> ncfidtridf(2, p, 0.25, 15)
array([ 1.,  2.,  3.])
```

scipy.special.ncfdtridf

`scipy.special.ncfdtridf(p, dfd, nc, f) = <ufunc 'ncfdtridf'>`

Calculate degrees of freedom (numerator) for the noncentral F-distribution.

This is the inverse with respect to *dfn* of *ncfdtr*. See *ncfdtr* for more details.

Parameters

p [array_like] Value of the cumulative distribution function. Must be in the range [0, 1].
dfd [array_like] Degrees of freedom of the denominator sum of squares. Range (0, inf).
nc [array_like] Noncentrality parameter. Should be in range (0, 1e4).
f [float] Quantiles, i.e., the upper limit of integration.

Returns

dfn [float] Degrees of freedom of the numerator sum of squares.

See also:

ncfdtr

CDF of the non-central F distribution.

ncfdtri

Quantile function; inverse of *ncfdtr* with respect to *f*.

ncfdtridf

Inverse of *ncfdtr* with respect to *dfd*.

ncfdtrinc

Inverse of *ncfdtr* with respect to *nc*.

Notes

The value of the cumulative noncentral F distribution is not necessarily monotone in either degrees of freedom. There thus may be two values that provide a given CDF value. This routine assumes monotonicity and will find an arbitrary one of the two values.

Examples

```
>>> from scipy.special import ncfidtr, ncfidtridf
```

Compute the CDF for several values of *dfn*:

```
>>> dfn = [1, 2, 3]
>>> p = ncfidtr(dfn, 2, 0.25, 15)
>>> p
array([ 0.92562363,  0.93020416,  0.93188394])
```

Compute the inverse. We recover the values of *dfn*, as expected:

```
>>> ncfidtridf(p, 2, 0.25, 15)
array([ 1.,  2.,  3.])
```

scipy.special.ncfdtri

`scipy.special.ncfdtri(dfn, dfd, nc, p) = <ufunc 'ncfdtri'>`

Inverse with respect to f of the CDF of the non-central F distribution.

See `ncfdtr` for more details.

Parameters

dfn [array_like] Degrees of freedom of the numerator sum of squares. Range (0, inf).
dfd [array_like] Degrees of freedom of the denominator sum of squares. Range (0, inf).
nc [array_like] Noncentrality parameter. Should be in range (0, 1e4).
p [array_like] Value of the cumulative distribution function. Must be in the range [0, 1].

Returns

f [float] Quantiles, i.e., the upper limit of integration.

See also:

`ncfdtr`

CDF of the non-central F distribution.

`ncfdtridf`

Inverse of `ncfdtr` with respect to dfd .

`ncfdtridf`

Inverse of `ncfdtr` with respect to dfn .

`ncfdtrinc`

Inverse of `ncfdtr` with respect to nc .

Examples

```
>>> from scipy.special import ncfidtr, ncfidtri
```

Compute the CDF for several values of f :

```
>>> f = [0.5, 1, 1.5]
>>> p = ncfidtr(2, 3, 1.5, f)
>>> p
array([ 0.20782291,  0.36107392,  0.47345752])
```

Compute the inverse. We recover the values of f , as expected:

```
>>> ncfidtri(2, 3, 1.5, p)
array([ 0.5,  1. ,  1.5])
```

scipy.special.ncfdtrinc`scipy.special.ncfdtrinc(dfn, dfd, p, f) = <ufunc 'ncfdtrinc'>`

Calculate non-centrality parameter for non-central F distribution.

This is the inverse with respect to *nc* of `ncfdtr`. See `ncfdtr` for more details.**Parameters**

dfn	[array_like] Degrees of freedom of the numerator sum of squares. Range (0, inf).
dfd	[array_like] Degrees of freedom of the denominator sum of squares. Range (0, inf).
p	[array_like] Value of the cumulative distribution function. Must be in the range [0, 1].
f	[array_like] Quantiles, i.e., the upper limit of integration.

Returns

nc	[float] Noncentrality parameter.
-----------	----------------------------------

See also:`ncfdtr`

CDF of the non-central F distribution.

`ncfdtri`Quantile function; inverse of `ncfdtr` with respect to *f*.`ncfdtridfd`Inverse of `ncfdtr` with respect to *dfd*.`ncfdtridfn`Inverse of `ncfdtr` with respect to *dfn*.**Examples**

```
>>> from scipy.special import ncfdtr, ncfdtrinc
```

Compute the CDF for several values of *nc*:

```
>>> nc = [0.5, 1.5, 2.0]
>>> p = ncfdtr(2, 3, nc, 15)
>>> p
array([ 0.96309246,  0.94327955,  0.93304098])
```

Compute the inverse. We recover the values of *nc*, as expected:

```
>>> ncfdtrinc(2, 3, p, 15)
array([ 0.5,  1.5,  2. ])
```

scipy.special.nctdtr

`scipy.special.nctdtr(df, nc, t) = <ufunc 'nctdtr'>`
 Cumulative distribution function of the non-central t distribution.

Parameters

df [array_like] Degrees of freedom of the distribution. Should be in range (0, inf).
nc [array_like] Noncentrality parameter. Should be in range (-1e6, 1e6).
t [array_like] Quantiles, i.e., the upper limit of integration.

Returns

cdf [float or ndarray] The calculated CDF. If all inputs are scalar, the return will be a float. Otherwise, it will be an array.

See also:*nctdtrit*

Inverse CDF (iCDF) of the non-central t distribution.

nctdtridf

Calculate degrees of freedom, given CDF and iCDF values.

nctdtrinc

Calculate non-centrality parameter, given CDF iCDF values.


Examples

```
>>> from scipy import special
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
```

Plot the CDF of the non-central t distribution, for $nc=0$. Compare with the t -distribution from `scipy.stats`:

```
>>> x = np.linspace(-5, 5, num=500)
>>> df = 3
>>> nct_stats = stats.t.cdf(x, df)
>>> nct_special = special.nctdtr(df, 0, x)
```

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> ax.plot(x, nct_stats, 'b-', lw=3)
>>> ax.plot(x, nct_special, 'r-')
>>> plt.show()
```



scipy.special.nctdtridf

`scipy.special.nctdtridf(p, nc, t) = <ufunc 'nctdtridf'>`
 Calculate degrees of freedom for non-central t distribution.

See [nctdtr](#) for more details.

Parameters

p [array_like] CDF values, in range (0, 1].
nc [array_like] Noncentrality parameter. Should be in range (-1e6, 1e6).
t [array_like] Quantiles, i.e., the upper limit of integration.

scipy.special.nctdtrit

`scipy.special.nctdtrit(df, nc, p) = <ufunc 'nctdtrit'>`
 Inverse cumulative distribution function of the non-central t distribution.

See [nctdtr](#) for more details.

Parameters

df [array_like] Degrees of freedom of the distribution. Should be in range (0, inf).
nc [array_like] Noncentrality parameter. Should be in range (-1e6, 1e6).
p [array_like] CDF values, in range (0, 1].

scipy.special.nctdtrinc

`scipy.special.nctdtrinc(df, p, t) = <ufunc 'nctdtrinc'>`
 Calculate non-centrality parameter for non-central t distribution.

See [nctdtr](#) for more details.

Parameters

df [array_like] Degrees of freedom of the distribution. Should be in range (0, inf).
p [array_like] CDF values, in range (0, 1].
t [array_like] Quantiles, i.e., the upper limit of integration.

scipy.special.nrdtrimn

`scipy.special.nrdtrimn(p, x, std) = <ufunc 'nrdtrimn'>`

Calculate mean of normal distribution given other params.

Parameters

p	[array_like] CDF values, in range (0, 1].
x	[array_like] Quantiles, i.e. the upper limit of integration.
std	[array_like] Standard deviation.

Returns

mn	[float or ndarray] The mean of the normal distribution.
-----------	---

See also:

[*nrdtrimn*](#), [*ndtr*](#)

scipy.special.nrdtrisd

`scipy.special.nrdtrisd(p, x, mn) = <ufunc 'nrdtrisd'>`

Calculate standard deviation of normal distribution given other params.

Parameters

p	[array_like] CDF values, in range (0, 1].
x	[array_like] Quantiles, i.e. the upper limit of integration.
mn	[float or ndarray] The mean of the normal distribution.

Returns

std	[array_like] Standard deviation.
------------	----------------------------------

See also:

[*ndtr*](#)

scipy.special.pdtr

`scipy.special.pdtr(k, m, out=None) = <ufunc 'pdtr'>`

Poisson cumulative distribution function.

Defined as the probability that a Poisson-distributed random variable with event rate m is less than or equal to k . More concretely, this works out to be [1]

$$\exp(-m) \sum_{j=0}^{\lfloor k \rfloor} \frac{m^j}{j!}.$$

Parameters

k	[array_like] Nonnegative real argument
m	[array_like] Nonnegative real shape parameter
out	[ndarray] Optional output array for the function results

Returns

scalar or ndarray	Values of the Poisson cumulative distribution function
--------------------------	--

See also:

pdtrc

Poisson survival function

pdtrik

inverse of *pdtr* with respect to *k*

pdtri

inverse of *pdtr* with respect to *m*

References

[1]

Examples

```
>>> import scipy.special as sc
```

It is a cumulative distribution function, so it converges to 1 monotonically as *k* goes to infinity.

```
>>> sc.pdtr([1, 10, 100, np.inf], 1)
array([0.73575888, 0.99999999, 1.          , 1.          ])
```

It is discontinuous at integers and constant between integers.

```
>>> sc.pdtr([1, 1.5, 1.9, 2], 1)
array([0.73575888, 0.73575888, 0.73575888, 0.9196986 ])
```

scipy.special.pdtrc

`scipy.special.pdtrc(k, m) = <ufunc 'pdtrc'>`

Poisson survival function

Returns the sum of the terms from *k*+1 to infinity of the Poisson distribution: $\sum(\exp(-m) * m^{**j} / j!, j=k+1..inf)$ = `gammainc(k+1, m)`. Arguments must both be non-negative doubles.

scipy.special.pdtri

`scipy.special.pdtri(k, y) = <ufunc 'pdtri'>`

Inverse to *pdtr* vs *m*

Returns the Poisson variable *m* such that the sum from 0 to *k* of the Poisson density is equal to the given probability *y*: calculated by `gammaincinv(k+1, y)`. *k* must be a nonnegative integer and *y* between 0 and 1.

scipy.special.pdtrik

`scipy.special.pdtrik(p, m) = <ufunc 'pdtrik'>`

Inverse to *pdtr* vs *k*

Returns the quantile *k* such that `pdtr(k, m) = p`

scipy.special.stdtr

`scipy.special.stdtr(df, t) = <ufunc 'stdtr'>`
 Student t distribution cumulative distribution function

Returns the integral from minus infinity to t of the Student t distribution with $df > 0$ degrees of freedom:

```
gamma((df+1)/2)/(sqrt(df*pi)*gamma(df/2)) *
integral((1+x**2/df)**(-df/2-1/2), x=-inf..t)
```

scipy.special.stdtridf

`scipy.special.stdtridf(p, t) = <ufunc 'stdtridf'>`
 Inverse of `stdtr` vs df

Returns the argument df such that `stdtr(df, t)` is equal to p .

scipy.special.stdtrit

`scipy.special.stdtrit(df, p) = <ufunc 'stdtrit'>`
 Inverse of `stdtr` vs t

Returns the argument t such that `stdtr(df, t)` is equal to p .

scipy.special.chdtr

`scipy.special.chdtr(v, x, out=None) = <ufunc 'chdtr'>`
 Chi square cumulative distribution function.

Returns the area under the left tail (from 0 to x) of the Chi square probability density function with v degrees of freedom:

$$\frac{1}{2^{v/2}\Gamma(v/2)} \int_0^x t^{v/2-1} e^{-t/2} dt$$

Here Γ is the Gamma function; see [gamma](#). This integral can be expressed in terms of the regularized lower incomplete gamma function `gammainc` as `gammainc(v / 2, x / 2)`. [1]

Parameters

- v** [array_like] Degrees of freedom.
- x** [array_like] Upper bound of the integral.
- out** [ndarray, optional] Optional output array for the function results.

Returns

- scalar or ndarray**
 Values of the cumulative distribution function.

See also:

[chdtrc](#), [chdtri](#), [chdtriv](#), [gammainc](#)

References

[1]

Examples

```
>>> import scipy.special as sc
```

It can be expressed in terms of the regularized lower incomplete gamma function.

```
>>> v = 1
>>> x = np.arange(4)
>>> sc.chdtr(v, x)
array([0.          , 0.68268949, 0.84270079, 0.91673548])
>>> sc.gammainc(v / 2, x / 2)
array([0.          , 0.68268949, 0.84270079, 0.91673548])
```

scipy.special.chdtrc

`scipy.special.chdtrc(v, x, out=None) = <ufunc 'chdtrc'>`

Chi square survival function.

Returns the area under the right hand tail (from x to infinity) of the Chi square probability density function with v degrees of freedom:

$$\frac{1}{2^{v/2}\Gamma(v/2)} \int_x^\infty t^{v/2-1} e^{-t/2} dt$$

Here Γ is the Gamma function; see [gamma](#). This integral can be expressed in terms of the regularized upper incomplete gamma function [gammaincc](#) as `gammaincc(v / 2, x / 2)`. [1]

Parameters

v [array_like] Degrees of freedom.
x [array_like] Lower bound of the integral.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
Values of the survival function.

See also:

[chdtr](#), [chdtri](#), [chdtriv](#), [gammaincc](#)

References

[1]

Examples

```
>>> import scipy.special as sc
```

It can be expressed in terms of the regularized upper incomplete gamma function.

```
>>> v = 1
>>> x = np.arange(4)
>>> sc.chdtrc(v, x)
array([1.          , 0.31731051, 0.15729921, 0.08326452])
>>> sc.gammaincc(v / 2, x / 2)
array([1.          , 0.31731051, 0.15729921, 0.08326452])
```

scipy.special.chdtri

`scipy.special.chdtri(v, p, out=None) = <ufunc 'chdtri'>`

Inverse to *chdtrc* with respect to *x*.

Returns *x* such that `chdtrc(v, x) == p`.

Parameters

v [array_like] Degrees of freedom.
p [array_like] Probability.
out [ndarray, optional] Optional output array for the function results.

Returns

x [scalar or ndarray] Value so that the probability a Chi square random variable with *v* degrees of freedom is greater than *x* equals *p*.

See also:

chdtrc, *chdtr*, *chdtriv*

References

[1]

Examples

```
>>> import scipy.special as sc
```

It inverts *chdtrc*.

```
>>> v, p = 1, 0.3
>>> sc.chdtrc(v, sc.chdtri(v, p))
0.3
>>> x = 1
>>> sc.chdtri(v, sc.chdtrc(v, x))
1.0
```

scipy.special.chdtriv

`scipy.special.chdtriv(p, x, out=None) = <ufunc 'chdtriv'>`

Inverse to `chdtr` with respect to v .

Returns v such that `chdtr(v, x) == p`.

Parameters

p [array_like] Probability that the Chi square random variable is less than or equal to x .
x [array_like] Nonnegative input.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
 Degrees of freedom.

See also:

`chdtr`, `chdtrc`, `chdtri`

References

[1]

Examples

```
>>> import scipy.special as sc
```

It inverts `chdtr`.

```
>>> p, x = 0.5, 1
>>> sc.chdtr(sc.chdtriv(p, x), x)
0.50000000000202172
>>> v = 1
>>> sc.chdtriv(sc.chdtr(v, x), v)
1.0000000000000013
```

scipy.special.ndtr

`scipy.special.ndtr(x) = <ufunc 'ndtr'>`

Gaussian cumulative distribution function.

Returns the area under the standard Gaussian probability density function, integrated from minus infinity to x

$$\frac{1}{\sqrt{2\pi}} \int_{-\infty}^x \exp(-t^2/2) dt$$

Parameters

x [array_like, real or complex] Argument

Returns

ndarray The value of the normal CDF evaluated at x

See also:

erf
erfc
scipy.stats.norm
log_ndtr

scipy.special.log_ndtr

`scipy.special.log_ndtr(x) = <ufunc 'log_ndtr'>`
 Logarithm of Gaussian cumulative distribution function.

Returns the log of the area under the standard Gaussian probability density function, integrated from minus infinity to x :

$$\log(1/\sqrt{2\pi}) * \text{integral}(\exp(-t^2 / 2), t=-\text{inf}..x)$$

Parameters

x [array_like, real or complex] Argument

Returns

ndarray The value of the log of the normal CDF evaluated at x

See also:

erf
erfc
scipy.stats.norm
ndtr

scipy.special.ndtri

`scipy.special.ndtri(y) = <ufunc 'ndtri'>`
 Inverse of *ndtr* vs x

Returns the argument x for which the area under the Gaussian probability density function (integrated from minus infinity to x) is equal to y .

scipy.special.chndtr

`scipy.special.chndtr(x, df, nc) = <ufunc 'chndtr'>`
 Non-central chi square cumulative distribution function

scipy.special.chndtridf

`scipy.special.chndtridf(x, p, nc) = <ufunc 'chndtridf'>`
 Inverse to *chndtr* vs df

scipy.special.chndtrinc

`scipy.special.chndtrinc(x, df, p) = <ufunc 'chndtrinc'>`
Inverse to `chndtr` vs `nc`

scipy.special.chndtrix

`scipy.special.chndtrix(p, df, nc) = <ufunc 'chndtrix'>`
Inverse to `chndtr` vs `x`

scipy.special.smirnov

`scipy.special.smirnov(n, d) = <ufunc 'smirnov'>`
Kolmogorov-Smirnov complementary cumulative distribution function

Returns the exact Kolmogorov-Smirnov complementary cumulative distribution function, (aka the Survival Function) of D_n^+ (or D_n^-) for a one-sided test of equality between an empirical and a theoretical distribution. It is equal to the probability that the maximum difference between a theoretical distribution and an empirical one based on n samples is greater than d .

Parameters

n [int] Number of samples
d [float array_like] Deviation between the Empirical CDF (ECDF) and the target CDF.

Returns

float The value(s) of `smirnov(n, d)`, $\text{Prob}(D_n^+ \geq d)$ (Also $\text{Prob}(D_n^- \geq d)$)

See also:***smirnovi***

The Inverse Survival Function for the distribution

scipy.stats.ksone

Provides the functionality as a continuous distribution

kolmogorov, kolmogi

Functions for the two-sided distribution

Notes

`smirnov` is used by `stats.kstest` in the application of the Kolmogorov-Smirnov Goodness of Fit test. For historical reasons this function is exposed in `scipy.special`, but the recommended way to achieve the most accurate CDF/SF/PDF/PPF/ISF computations is to use the `stats.ksone` distribution.

Examples

```
>>> from scipy.special import smirnov
```

Show the probability of a gap at least as big as 0, 0.5 and 1.0 for a sample of size 5

```
>>> smirnov(5, [0, 0.5, 1.0])  
array([ 1.    ,  0.056 ,  0.    ])
```

Compare a sample of size 5 drawn from a source $N(0.5, 1)$ distribution against a target $N(0, 1)$ CDF.


```

>>> from scipy.stats import norm
>>> n = 5
>>> gendist = norm(0.5, 1)      # Normal distribution, mean 0.5, stddev 1
>>> np.random.seed(seed=233423) # Set the seed for reproducibility
>>> x = np.sort(gendist.rvs(size=n))
>>> x
array([-0.20946287,  0.71688765,  0.95164151,  1.44590852,  3.08880533])
>>> target = norm(0, 1)
>>> cdfs = target.cdf(x)
>>> cdfs
array([ 0.41704346,  0.76327829,  0.82936059,  0.92589857,  0.99899518])
# Construct the Empirical CDF and the K-S statistics (Dn+, Dn-, Dn)
>>> ecdfs = np.arange(n+1, dtype=float)/n
>>> cols = np.column_stack([x, ecdfs[1:], cdfs, cdfs - ecdfs[:n],
→ecdfs[1:] - cdfs])
>>> np.set_printoptions(precision=3)
>>> cols
array([[ -2.095e-01,  2.000e-01,  4.170e-01,  4.170e-01,  -2.170e-01],
       [  7.169e-01,  4.000e-01,  7.633e-01,  5.633e-01,  -3.633e-01],
       [  9.516e-01,  6.000e-01,  8.294e-01,  4.294e-01,  -2.294e-01],
       [  1.446e+00,  8.000e-01,  9.259e-01,  3.259e-01,  -1.259e-01],
       [  3.089e+00,  1.000e+00,  9.990e-01,  1.990e-01,  1.005e-03]])
>>> gaps = cols[:, -2:]
>>> Dnpm = np.max(gaps, axis=0)
>>> print('Dn-=%f, Dn+=%f' % (Dnpm[0], Dnpm[1]))
Dn-=0.563278, Dn+=0.001005
>>> probs = smirnov(n, Dnpm)
>>> print(chr(10).join(['For a sample of size %d drawn from a N(0, 1)
→distribution:' % n,
...   ' Smirnov n=%d: Prob(Dn- >= %f) = %.4f' % (n, Dnpm[0],
→probs[0]),
...   ' Smirnov n=%d: Prob(Dn+ >= %f) = %.4f' % (n, Dnpm[1],
→probs[1])]))
For a sample of size 5 drawn from a N(0, 1) distribution:
  Smirnov n=5: Prob(Dn- >= 0.563278) = 0.0250
  Smirnov n=5: Prob(Dn+ >= 0.001005) = 0.9990


```

Plot the Empirical CDF against the target N(0, 1) CDF

```

>>> import matplotlib.pyplot as plt
>>> plt.step(np.concatenate([[ -3], x]), ecdfs, where='post', label=
→'Empirical CDF')
>>> x3 = np.linspace(-3, 3, 100)
>>> plt.plot(x3, target.cdf(x3), label='CDF for N(0, 1)')
>>> plt.ylim([0, 1]); plt.grid(True); plt.legend();
# Add vertical lines marking Dn+ and Dn-
>>> iminus, iplus = np.argmax(gaps, axis=0)
>>> plt.vlines([x[iminus]], ecdfs[iminus], cdfs[iminus], color='r',
→linestyle='dashed', lw=4)
>>> plt.vlines([x[iplus]], cdfs[iplus], ecdfs[iplus+1], color='m',
→linestyle='dashed', lw=4)
>>> plt.show()

```



scipy.special.smirnovi

`scipy.special.smirnovi(n, p) = <ufunc 'smirnovi'>`

Inverse to `smirnov`

Returns d such that `smirnov(n, d) == p`, the critical value corresponding to p .

Parameters

n [int] Number of samples
p [float array_like] Probability

Returns

float The value(s) of `smirnovi(n, p)`, the critical values.

See also:

`smirnov`

The Survival Function (SF) for the distribution

`scipy.stats.kstest`

Provides the functionality as a continuous distribution

`kolmogorov`, `kolmogi`, `scipy.stats.kstwobign`

Functions for the two-sided distribution

Notes

smirnov is used by *stats.kstest* in the application of the Kolmogorov-Smirnov Goodness of Fit test. For historical reasons this function is exposed in *scipy.special*, but the recommended way to achieve the most accurate CDF/SF/PDF/PPF/ISF computations is to use the *stats.kstest* distribution.

scipy.special.kolmogorov

`scipy.special.kolmogorov(y) = <ufunc 'kolmogorov'>`

Complementary cumulative distribution (Survival Function) function of Kolmogorov distribution.

Returns the complementary cumulative distribution function of Kolmogorov's limiting distribution ($D_n \sqrt{n}$ as n goes to infinity) of a two-sided test for equality between an empirical and a theoretical distribution. It is equal to the (limit as $n \rightarrow \infty$ of the) probability that $\sqrt{n} \cdot \max \text{ absolute deviation} > y$.

Parameters

y [float array_like] Absolute deviation between the Empirical CDF (ECDF) and the target CDF, multiplied by \sqrt{n} .

Returns

float The value(s) of `kolmogorov(y)`

See also:

kolmogi

The Inverse Survival Function for the distribution

scipy.stats.kstwobign

Provides the functionality as a continuous distribution

smirnov, smirnovi

Functions for the one-sided distribution

Notes

kolmogorov is used by *stats.kstest* in the application of the Kolmogorov-Smirnov Goodness of Fit test. For historical reasons this function is exposed in *scipy.special*, but the recommended way to achieve the most accurate CDF/SF/PDF/PPF/ISF computations is to use the *stats.kstwobign* distribution.

Examples

Show the probability of a gap at least as big as 0, 0.5 and 1.0.

```
>>> from scipy.special import kolmogorov
>>> from scipy.stats import kstwobign
>>> kolmogorov([0, 0.5, 1.0])
array([ 1.          ,  0.96394524,  0.26999967])
```

Compare a sample of size 1000 drawn from a Laplace(0, 1) distribution against the target distribution, a Normal(0, 1) distribution.


```
>>> from scipy.stats import norm, laplace
>>> n = 1000
>>> np.random.seed(seed=233423)
>>> lap01 = laplace(0, 1)
>>> x = np.sort(lap01.rvs(n))
>>> np.mean(x), np.std(x)
(-0.083073685397609842, 1.3676426568399822)
```

Construct the Empirical CDF and the K-S statistic D_n .

```
>>> target = norm(0,1) # Normal mean 0, stddev 1
>>> cdfs = target.cdf(x)
>>> ecdfs = np.arange(n+1, dtype=float)/n
>>> gaps = np.column_stack([cdfs - ecdfs[:n], ecdfs[1:] - cdfs])
>>> Dn = np.max(gaps)
>>> Kn = np.sqrt(n) * Dn
>>> print('Dn=%f, sqrt(n)*Dn=%f' % (Dn, Kn))
Dn=0.058286, sqrt(n)*Dn=1.843153
>>> print(chr(10).join(['For a sample of size n drawn from a N(0, 1) ↵
↵distribution:',
... ' the approximate Kolmogorov probability that sqrt(n)*Dn>=%f is %f
↵' % (Kn, kolmogorov(Kn)),
... ' the approximate Kolmogorov probability that sqrt(n)*Dn<=%f is %f
↵' % (Kn, kstwobign.cdf(Kn))]))
For a sample of size n drawn from a N(0, 1) distribution:
the approximate Kolmogorov probability that sqrt(n)*Dn>=1.843153 is 0.
↵002240
the approximate Kolmogorov probability that sqrt(n)*Dn<=1.843153 is 0.
↵997760
```

Plot the Empirical CDF against the target $N(0, 1)$ CDF.

```
>>> import matplotlib.pyplot as plt
>>> plt.step(np.concatenate([[ -3], x]), ecdfs, where='post', label=
↵'Empirical CDF')
>>> x3 = np.linspace(-3, 3, 100)
>>> plt.plot(x3, target.cdf(x3), label='CDF for N(0, 1)')
>>> plt.ylim([0, 1]); plt.grid(True); plt.legend();
>>> # Add vertical lines marking Dn+ and Dn-
>>> iminus, iplus = np.argmax(gaps, axis=0)
>>> plt.vlines([x[iminus]], ecdfs[iminus], cdfs[iminus], color='r', ↵
↵linestyle='dashed', lw=4)
>>> plt.vlines([x[iplus]], cdfs[iplus], ecdfs[iplus+1], color='r', ↵
↵linestyle='dashed', lw=4)
>>> plt.show()
```



scipy.special.kolmogi

`scipy.special.kolmogi(p) = <ufunc 'kolmogi'>`
Inverse Survival Function of Kolmogorov distribution

It is the inverse function to *kolmogorov*. Returns y such that $\text{kolmogorov}(y) == p$.

Parameters

p [float array_like] Probability

Returns

float The value(s) of $\text{kolmogi}(p)$

See also:

kolmogorov

The Survival Function for the distribution

scipy.stats.kstwobign

Provides the functionality as a continuous distribution

smirnov, smirnovi

Functions for the one-sided distribution

Notes

kolmogorov is used by *stats.kstest* in the application of the Kolmogorov-Smirnov Goodness of Fit test. For historical reasons this function is exposed in *scipy.special*, but the recommended way to achieve the most accurate CDF/SF/PDF/PPF/ISF computations is to use the *stats.kstwobign* distribution.

Examples

```
>>> from scipy.special import kolmogi
>>> kolmogi([0, 0.1, 0.25, 0.5, 0.75, 0.9, 1.0])
array([          inf,  1.22384787,  1.01918472,  0.82757356,  0.67644769,
        0.57117327,  0.          ])
```

scipy.special.tklmbda

`scipy.special.tklmbda(x, lambda) = <ufunc 'tklmbda'>`
 Tukey-Lambda cumulative distribution function

scipy.special.logit

`scipy.special.logit(x) = <ufunc 'logit'>`
 Logit ufunc for ndarrays.

The logit function is defined as $\text{logit}(p) = \log(p/(1-p))$. Note that $\text{logit}(0) = -\text{inf}$, $\text{logit}(1) = \text{inf}$, and $\text{logit}(p)$ for $p < 0$ or $p > 1$ yields nan.

Parameters

x [ndarray] The ndarray to apply logit to element-wise.

Returns

out [ndarray] An ndarray of the same shape as x. Its entries are logit of the corresponding entry of x.

See also:

[`expit`](#)

Notes

As a ufunc logit takes a number of optional keyword arguments. For more information see [ufuncs](#)

New in version 0.10.0.

Examples

```
>>> from scipy.special import logit, expit
```

```
>>> logit([0, 0.25, 0.5, 0.75, 1])
array([          -inf, -1.09861229,  0.          ,  1.09861229,          inf])
```

`expit` is the inverse of `logit`:


```
>>> expit(logit([0.1, 0.75, 0.999]))
array([ 0.1 ,  0.75 ,  0.999])
```

Plot $\text{logit}(x)$ for x in $[0, 1]$:

```

>>> import matplotlib.pyplot as plt
>>> x = np.linspace(0, 1, 501)
>>> y = logit(x)
>>> plt.plot(x, y)
>>> plt.grid()
>>> plt.ylim(-6, 6)
>>> plt.xlabel('x')
>>> plt.title('logit(x)')
>>> plt.show()

```



scipy.special.expit

`scipy.special.expit(x)` = <ufunc 'expit'>

Expit (a.k.a. logistic sigmoid) ufunc for ndarrays.

The expit function, also known as the logistic sigmoid function, is defined as $\text{expit}(x) = 1 / (1 + \exp(-x))$. It is the inverse of the logit function.

Parameters

x [ndarray] The ndarray to apply expit to element-wise.

Returns

out [ndarray] An ndarray of the same shape as x. Its entries are `expit` of the corresponding entry of x.

See also:

[`logit`](#)

Notes

As a ufunc `expit` takes a number of optional keyword arguments. For more information see [ufuncs](#)

New in version 0.10.0.

Examples

```
>>> from scipy.special import expit, logit
```


```
>>> expit([-np.inf, -1.5, 0, 1.5, np.inf])
array([ 0.          ,  0.18242552,  0.5          ,  0.81757448,  1.          ])
```

`logit` is the inverse of `expit`:

```
>>> logit(expit([-2.5, 0, 3.1, 5.0]))
array([-2.5,  0. ,  3.1,  5. ])
```

Plot `expit(x)` for `x` in `[-6, 6]`:

```
>>> import matplotlib.pyplot as plt
>>> x = np.linspace(-6, 6, 121)
>>> y = expit(x)
>>> plt.plot(x, y)
>>> plt.grid()
>>> plt.xlim(-6, 6)
>>> plt.xlabel('x')
>>> plt.title('expit(x)')
>>> plt.show()
```



scipy.special.boxcox

`scipy.special.boxcox(x, lambda) = <ufunc 'boxcox'>`
 Compute the Box-Cox transformation.

The Box-Cox transformation is:

```
y = (x**lambda - 1) / lambda  if lambda != 0
    log(x)                    if lambda == 0
```

Returns *nan* if $x < 0$. Returns *-inf* if $x == 0$ and $lambda < 0$.

Parameters

x [array_like] Data to be transformed.
lambda [array_like] Power parameter of the Box-Cox transform.

Returns

y [array] Transformed data.

Notes

New in version 0.14.0.

Examples

```
>>> from scipy.special import boxcox
>>> boxcox([1, 4, 10], 2.5)
array([ 0.          , 12.4          , 126.09110641])
>>> boxcox(2, [0, 1, 2])
array([ 0.69314718, 1.          , 1.5          ])
```

scipy.special.boxcox1p

`scipy.special.boxcox1p(x, lambda) = <ufunc 'boxcox1p'>`
 Compute the Box-Cox transformation of $1 + x$.

The Box-Cox transformation computed by `boxcox1p` is:

```
y = ((1+x)**lambda - 1) / lambda  if lambda != 0
    log(1+x)                      if lambda == 0
```

Returns *nan* if $x < -1$. Returns *-inf* if $x == -1$ and $lambda < 0$.

Parameters

x [array_like] Data to be transformed.
lambda [array_like] Power parameter of the Box-Cox transform.

Returns

y [array] Transformed data.

Notes

New in version 0.14.0.

Examples

```
>>> from scipy.special import boxcox1p
>>> boxcox1p(1e-4, [0, 0.5, 1])
array([ 9.99950003e-05,  9.99975001e-05,  1.00000000e-04])
>>> boxcox1p([0.01, 0.1], 0.25)
array([ 0.00996272,  0.09645476])
```

scipy.special.inv_boxcox

`scipy.special.inv_boxcox(y, lambda) = <ufunc 'inv_boxcox'>`

Compute the inverse of the Box-Cox transformation.

Find x such that:

```
y = (x**lambda - 1) / lambda  if lambda != 0
    log(x)                    if lambda == 0
```

Parameters

y [array_like] Data to be transformed.
lambda [array_like] Power parameter of the Box-Cox transform.

Returns

x [array] Transformed data.

Notes

New in version 0.16.0.

Examples

```
>>> from scipy.special import boxcox, inv_boxcox
>>> y = boxcox([1, 4, 10], 2.5)
>>> inv_boxcox(y, 2.5)
array([1., 4., 10.]
```

scipy.special.inv_boxcox1p

`scipy.special.inv_boxcox1p(y, lambda) = <ufunc 'inv_boxcox1p'>`

Compute the inverse of the Box-Cox transformation.

Find x such that:

```
y = ((1+x)**lambda - 1) / lambda  if lambda != 0
    log(1+x)                       if lambda == 0
```

Parameters

y [array_like] Data to be transformed.
lmbda [array_like] Power parameter of the Box-Cox transform.

Returns

x [array] Transformed data.

Notes

New in version 0.16.0.

Examples

```
>>> from scipy.special import boxcox1p, inv_boxcox1p
>>> y = boxcox1p([1, 4, 10], 2.5)
>>> inv_boxcox1p(y, 2.5)
array([1., 4., 10.]
```

scipy.special.owens_t

`scipy.special.owens_t(h, a) = <ufunc 'owens_t'>`

Owen's T Function.

The function $T(h, a)$ gives the probability of the event $(X > h \text{ and } 0 < Y < a * X)$ where X and Y are independent standard normal random variables.

Parameters

h: array_like
Input value.
a: array_like
Input value.

Returns

t: scalar or ndarray
Probability of the event $(X > h \text{ and } 0 < Y < a * X)$, where X and Y are independent standard normal random variables.

References

[1]

Examples

```
>>> from scipy import special
>>> a = 3.5
>>> h = 0.78
>>> special.owens_t(h, a)
0.10877216734852274
```

Information Theory functions

<code>entr(x)</code>	Elementwise function for computing entropy.
<code>rel_entr(x, y[, out])</code>	Elementwise function for computing relative entropy.
<code>kl_div(x, y[, out])</code>	Elementwise function for computing Kullback-Leibler divergence.
<code>huber(delta, r)</code>	Huber loss function.
<code>pseudo_huber(delta, r)</code>	Pseudo-Huber loss function.

scipy.special.entr

`scipy.special.entr(x) = <ufunc 'entr'>`

Elementwise function for computing entropy.

$$\text{entr}(x) = \begin{cases} -x \log(x) & x > 0 \\ 0 & x = 0 \\ -\infty & \text{otherwise} \end{cases}$$

Parameters

x [ndarray] Input array.

Returns

res [ndarray] The value of the elementwise entropy function at the given points x .

See also:

`kl_div`, `rel_entr`

Notes

This function is concave.

New in version 0.15.0.

scipy.special.rel_entr

`scipy.special.rel_entr(x, y, out=None) = <ufunc 'rel_entr'>`

Elementwise function for computing relative entropy.

$$\text{rel_entr}(x, y) = \begin{cases} x \log(x/y) & x > 0, y > 0 \\ 0 & x = 0, y \geq 0 \\ \infty & \text{otherwise} \end{cases}$$

Parameters

x, y [array_like] Input arrays

out [ndarray, optional] Optional output array for the function results

Returns

scalar or ndarray
Relative entropy of the inputs

See also:

`entr`, `kl_div`

Notes

New in version 0.15.0.

This function is jointly convex in x and y .

The origin of this function is in convex programming; see [1]. Given two discrete probability distributions p_1, \dots, p_n and q_1, \dots, q_n , to get the relative entropy of statistics compute the sum

$$\sum_{i=1}^n \text{rel_entr}(p_i, q_i).$$

See [2] for details.

References

[1], [2]

scipy.special.kl_div

`scipy.special.kl_div(x, y, out=None)` = `<ufunc 'kl_div'>`
Elementwise function for computing Kullback-Leibler divergence.

$$\text{kl_div}(x, y) = \begin{cases} x \log(x/y) - x + y & x > 0, y > 0 \\ y & x = 0, y \geq 0 \\ \infty & \text{otherwise} \end{cases}$$

Parameters

x, y [array_like] Real arguments
out [ndarray, optional] Optional output array for the function results

Returns

scalar or ndarray
Values of the Kullback-Liebler divergence.

See also:

[`entr`](#), [`rel_entr`](#)

Notes

New in version 0.15.0.

This function is non-negative and is jointly convex in x and y .

The origin of this function is in convex programming; see [1] for details. This is why the the function contains the extra $-x + y$ terms over what might be expected from the Kullback-Leibler divergence. For a version of the function without the extra terms, see [`rel_entr`](#).

References

[1]

scipy.special.huber

`scipy.special.huber(delta, r) = <ufunc 'huber'>`
Huber loss function.

$$\text{huber}(\delta, r) = \begin{cases} \infty & \delta < 0 \\ \frac{1}{2}r^2 & 0 \leq \delta, |r| \leq \delta \\ \delta(|r| - \frac{1}{2}\delta) & \text{otherwise} \end{cases}$$

Parameters

delta [ndarray] Input array, indicating the quadratic vs. linear loss changepoint.
r [ndarray] Input array, possibly representing residuals.

Returns

res [ndarray] The computed Huber loss function values.

Notes

This function is convex in r .

New in version 0.15.0.

scipy.special.pseudo_huber

`scipy.special.pseudo_huber(delta, r) = <ufunc 'pseudo_huber'>`
Pseudo-Huber loss function.

$$\text{pseudo_huber}(\delta, r) = \delta^2 \left(\sqrt{1 + \left(\frac{r}{\delta}\right)^2} - 1 \right)$$

Parameters

delta [ndarray] Input array, indicating the soft quadratic vs. linear loss changepoint.
r [ndarray] Input array, possibly representing residuals.

Returns

res [ndarray] The computed Pseudo-Huber loss function values.

Notes

This function is convex in r .

New in version 0.15.0.

Gamma and related functions

<code>gamma(z)</code>	gamma function.
<code>gammaaln(x[, out])</code>	Logarithm of the absolute value of the gamma function.
<code>loggamma(z[, out])</code>	Principal branch of the logarithm of the gamma function.
<code>gamma_{sgn}(x)</code>	Sign of the gamma function.
<code>gamma_{inc}(a, x)</code>	Regularized lower incomplete gamma function.
<code>gamma_{inc}_{inv}(a, y)</code>	Inverse to the lower incomplete gamma function with respect to x .
<code>gamma_{inc}_{cc}(a, x)</code>	Regularized upper incomplete gamma function.
<code>gamma_{inc}_{cc}_{inv}(a, y)</code>	Inverse of the upper incomplete gamma function with respect to x .
<code>beta(a, b[, out])</code>	Beta function.
<code>betaln(a, b)</code>	Natural logarithm of absolute value of beta function.
<code>beta_{inc}(a, b, x[, out])</code>	Incomplete beta function.
<code>beta_{inc}_{inv}(a, b, y[, out])</code>	Inverse of the incomplete beta function.
<code>psi(z[, out])</code>	The digamma function.
<code>rgamma(z[, out])</code>	Reciprocal of the gamma function.
<code>polygamma(n, x)</code>	Polygamma functions.
<code>multigammaln(a, d)</code>	Returns the log of multivariate gamma, also sometimes called the generalized gamma.
<code>digamma(z[, out])</code>	The digamma function.
<code>poch(z, m)</code>	Pochhammer symbol.

scipy.special.gamma

`scipy.special.gamma(z) = <ufunc 'gamma'>`
gamma function.

The gamma function is defined as

$$\Gamma(z) = \int_0^{\infty} t^{z-1} e^{-t} dt$$

for $\Re(z) > 0$ and is extended to the rest of the complex plane by analytic continuation. See [dlmf] for more details.

Parameters

z [array_like] Real or complex valued argument

Returns

scalar or ndarray
Values of the gamma function

Notes

The gamma function is often referred to as the generalized factorial since $\Gamma(n+1) = n!$ for natural numbers n . More generally it satisfies the recurrence relation $\Gamma(z+1) = z \cdot \Gamma(z)$ for complex z , which, combined with the fact that $\Gamma(1) = 1$, implies the above identity for $z = n$.

References

[dlmf]

Examples

```
>>> from scipy.special import gamma, factorial
```

```
>>> gamma([0, 0.5, 1, 5])
array([          inf,  1.77245385,  1.          , 24.          ])
```

```
>>> z = 2.5 + 1j
>>> gamma(z)
(0.77476210455108352+0.70763120437959293j)
>>> gamma(z+1), z*gamma(z) # Recurrence property
((1.2292740569981171+2.5438401155000685j),
 (1.2292740569981158+2.5438401155000658j))
```

```
>>> gamma(0.5)**2 # gamma(0.5) = sqrt(pi)
3.1415926535897927
```

Plot $\gamma(x)$ for real x

```
>>> x = np.linspace(-3.5, 5.5, 2251)
>>> y = gamma(x)
```

```
>>> import matplotlib.pyplot as plt
>>> plt.plot(x, y, 'b', alpha=0.6, label='gamma(x)')
>>> k = np.arange(1, 7)
>>> plt.plot(k, factorial(k-1), 'k*', alpha=0.6,
...         label='(x-1)!, x = 1, 2, ...')
>>> plt.xlim(-3.5, 5.5)
>>> plt.ylim(-10, 25)
>>> plt.grid()
>>> plt.xlabel('x')
>>> plt.legend(loc='lower right')
>>> plt.show()
```

scipy.special.gammaln

`scipy.special.gammaln(x, out=None) = <ufunc 'gammaln'>`

Logarithm of the absolute value of the gamma function.


Defined as

$$\ln(|\Gamma(x)|)$$

where Γ is the gamma function. For more details on the gamma function, see [dlmf].

Parameters

x	[array_like] Real argument
out	[ndarray, optional] Optional output array for the function results

**Returns**

scalar or ndarray

Values of the log of the absolute value of gamma

See also:

*gamma*_{sgn}

sign of the gamma function

loggamma

principal branch of the logarithm of the gamma function

Notes

It is the same function as the Python standard library function `math.lgamma`.

When used in conjunction with *gamma*_{sgn}, this function is useful for working in logspace on the real axis without having to deal with complex numbers via the relation $\exp(\text{gamma} \ln(x)) = \text{gamma} \text{sgn}(x) * \text{gamma}(x)$.

For complex-valued log-gamma, use *loggamma* instead of *gamma*_{ln}.

References

[dlmf]

Examples

```
>>> import scipy.special as sc
```

It has two positive zeros.

```
>>> sc.gammaln([1, 2])
array([0., 0.]
```

It has poles at nonpositive integers.

```
>>> sc.gammaln([0, -1, -2, -3, -4])
array([inf, inf, inf, inf, inf])
```

It asymptotically approaches $x * \log(x)$ (Stirling's formula).

```
>>> x = np.array([1e10, 1e20, 1e40, 1e80])
>>> sc.gammaln(x)
array([2.20258509e+11, 4.50517019e+21, 9.11034037e+41, 1.83206807e+82])
>>> x * np.log(x)
array([2.30258509e+11, 4.60517019e+21, 9.21034037e+41, 1.84206807e+82])
```

scipy.special.loggamma

`scipy.special.loggamma(z, out=None) = <ufunc 'loggamma'>`

Principal branch of the logarithm of the gamma function.

Defined to be $\log(\Gamma(x))$ for $x > 0$ and extended to the complex plane by analytic continuation. The function has a single branch cut on the negative real axis.

New in version 0.18.0.

Parameters

z [array-like] Values in the complex plain at which to compute `loggamma`
out [ndarray, optional] Output array for computed values of `loggamma`

Returns

loggamma [ndarray] Values of `loggamma` at `z`.

See also:

`gammaln`

logarithm of the absolute value of the gamma function

`gamma_sgn`

sign of the gamma function

Notes

It is not generally true that $\log \Gamma(z) = \log(\Gamma(z))$, though the real parts of the functions do agree. The benefit of not defining `loggamma` as $\log(\Gamma(z))$ is that the latter function has a complicated branch cut structure whereas `loggamma` is analytic except for on the negative real axis.

The identities

$$\begin{aligned}\exp(\log \Gamma(z)) &= \Gamma(z) \\ \log \Gamma(z + 1) &= \log(z) + \log \Gamma(z)\end{aligned}$$

make `loggamma` useful for working in complex logspace.

On the real line `loggamma` is related to `gammaaln` via $\exp(\loggamma(x + 0j)) = \text{gamma} - \text{masgn}(x) * \exp(\text{gammaaln}(x))$, up to rounding error.

The implementation here is based on [hare1997].

References

[hare1997]

scipy.special.gammasgn

`scipy.special.gammasgn(x) = <ufunc 'gammasgn'>`

Sign of the gamma function.

It is defined as

$$\text{gammasgn}(x) = \begin{cases} +1 & \Gamma(x) > 0 \\ -1 & \Gamma(x) < 0 \end{cases}$$

where Γ is the gamma function; see `gamma`. This definition is complete since the gamma function is never zero; see the discussion after [dlmf].

Parameters

x [array_like] Real argument

Returns

scalar or ndarray
Sign of the gamma function

See also:

`gamma`

the gamma function

`gammaaln`

log of the absolute value of the gamma function

`loggamma`

analytic continuation of the log of the gamma function

Notes

The gamma function can be computed as `gammasgn(x) * np.exp(gammaln(x))`.

References

[dlmf]

Examples

```
>>> import scipy.special as sc
```

It is 1 for $x > 0$.

```
>>> sc.gammasgn([1, 2, 3, 4])
array([1., 1., 1., 1.] )
```

It alternates between -1 and 1 for negative integers.

```
>>> sc.gammasgn([-0.5, -1.5, -2.5, -3.5])
array([-1., 1., -1., 1.] )
```

It can be used to compute the gamma function.

```
>>> x = [1.5, 0.5, -0.5, -1.5]
>>> sc.gammasgn(x) * np.exp(sc.gammaln(x))
array([ 0.88622693,  1.77245385, -3.5449077 ,  2.3632718 ])
>>> sc.gamma(x)
array([ 0.88622693,  1.77245385, -3.5449077 ,  2.3632718 ])
```

scipy.special.gammainc

`scipy.special.gammainc(a, x) = <ufunc 'gammainc'>`

Regularized lower incomplete gamma function.

It is defined as

$$P(a, x) = \frac{1}{\Gamma(a)} \int_0^x t^{a-1} e^{-t} dt$$

for $a > 0$ and $x \geq 0$. See [dlmf] for details.

Parameters

a [array_like] Positive parameter
x [array_like] Nonnegative argument

Returns

scalar or ndarray

Values of the lower incomplete gamma function

See also:

[`gammaincc`](#)

regularized upper incomplete gamma function

gammaincinv

inverse of the regularized lower incomplete gamma function with respect to x

gammainccinv

inverse of the regularized upper incomplete gamma function with respect to x

Notes

The function satisfies the relation $\text{gammainc}(a, x) + \text{gammaincc}(a, x) = 1$ where *gammaincc* is the regularized upper incomplete gamma function.

The implementation largely follows that of [boost].

References

[dlmf], [boost]

Examples

```
>>> import scipy.special as sc
```

It is the CDF of the gamma distribution, so it starts at 0 and monotonically increases to 1.

```
>>> sc.gammainc(0.5, [0, 1, 10, 100])
array([0.          , 0.84270079, 0.99999226, 1.          ])
```

It is equal to one minus the upper incomplete gamma function.

```
>>> a, x = 0.5, 0.4
>>> sc.gammainc(a, x)
0.6289066304773024
>>> 1 - sc.gammaincc(a, x)
0.6289066304773024
```

scipy.special.gammaincinv

`scipy.special.gammaincinv(a, y) = <ufunc 'gammaincinv'>`

Inverse to the lower incomplete gamma function with respect to x .

Given an input y between 0 and 1, returns x such that $y = P(a, x)$. Here P is the regularized lower incomplete gamma function; see *gammainc*. This is well-defined because the lower incomplete gamma function is monotonic as can be seen from its definition in [dlmf].

Parameters

a [array_like] Positive parameter
y [array_like] Parameter between 0 and 1, inclusive

Returns

scalar or ndarray
 Values of the inverse of the lower incomplete gamma function

See also:

gammainc

regularized lower incomplete gamma function

gammaincc

regularized upper incomplete gamma function

gammainccinv

inverse of the regularized upper incomplete gamma function with respect to x

References

[dlmf]

Examples

```
>>> import scipy.special as sc
```

It starts at 0 and monotonically increases to infinity.

```
>>> sc.gammaincinv(0.5, [0, 0.1, 0.5, 1])
array([0.          , 0.00789539, 0.22746821,          inf])
```

It inverts the lower incomplete gamma function.

```
>>> a, x = 0.5, [0, 0.1, 0.5, 1]
>>> sc.gammainc(a, sc.gammaincinv(a, x))
array([0. , 0.1, 0.5, 1. ])
```

```
>>> a, x = 0.5, [0, 10, 25]
>>> sc.gammaincinv(a, sc.gammainc(a, x))
array([ 0.          , 10.          , 25.00001465])
```

scipy.special.gammaincc

`scipy.special.gammaincc(a, x) = <ufunc 'gammaincc'>`

Regularized upper incomplete gamma function.

It is defined as

$$Q(a, x) = \frac{1}{\Gamma(a)} \int_x^\infty t^{a-1} e^{-t} dt$$

for $a > 0$ and $x \geq 0$. See [dlmf] for details.

Parameters

a [array_like] Positive parameter
x [array_like] Nonnegative argument

Returns

scalar or ndarray
 Values of the upper incomplete gamma function

See also:

gammainc

regularized lower incomplete gamma function

gammaincinv

inverse of the regularized lower incomplete gamma function with respect to x

gammainccinv

inverse to of the regularized upper incomplete gamma function with respect to x

Notes

The function satisfies the relation $\text{gammainc}(a, x) + \text{gammaincc}(a, x) = 1$ where *gammainc* is the regularized lower incomplete gamma function.

The implementation largely follows that of [boost].

References

[dlmf], [boost]

Examples

```
>>> import scipy.special as sc
```

It is the survival function of the gamma distribution, so it starts at 1 and monotonically decreases to 0.

```
>>> sc.gammaincc(0.5, [0, 1, 10, 100, 1000])
array([1.00000000e+00, 1.57299207e-01, 7.74421643e-06, 2.08848758e-45,
       0.00000000e+00])
```

It is equal to one minus the lower incomplete gamma function.

```
>>> a, x = 0.5, 0.4
>>> sc.gammaincc(a, x)
0.37109336952269756
>>> 1 - sc.gammainc(a, x)
0.37109336952269756
```

scipy.special.gammainccinv

`scipy.special.gammainccinv(a, y) = <ufunc 'gammainccinv'>`

Inverse of the upper incomplete gamma function with respect to x

Given an input y between 0 and 1, returns x such that $y = Q(a, x)$. Here Q is the upper incomplete gamma function; see *gammaincc*. This is well-defined because the upper incomplete gamma function is monotonic as can be seen from its definition in [dlmf].

Parameters

a [array_like] Positive parameter
y [array_like] Argument between 0 and 1, inclusive

Returns

scalar or ndarray

Values of the inverse of the upper incomplete gamma function

See also:

`gammaincc`

regularized upper incomplete gamma function

`gammainc`

regularized lower incomplete gamma function

`gammaincinv`

inverse of the regularized lower incomplete gamma function with respect to x

References

[dlmf]

Examples

```
>>> import scipy.special as sc
```

It starts at infinity and monotonically decreases to 0.

```
>>> sc.gammainccinv(0.5, [0, 0.1, 0.5, 1])
array([          inf, 1.35277173, 0.22746821, 0.          ])
```

It inverts the upper incomplete gamma function.

```
>>> a, x = 0.5, [0, 0.1, 0.5, 1]
>>> sc.gammaincc(a, sc.gammainccinv(a, x))
array([0. , 0.1, 0.5, 1. ])
```

```
>>> a, x = 0.5, [0, 10, 50]
>>> sc.gammainccinv(a, sc.gammaincc(a, x))
array([ 0., 10., 50.] )
```

scipy.special.beta

`scipy.special.beta(a, b, out=None) = <ufunc 'beta'>`

Beta function.

This function is defined in [1] as

$$B(a, b) = \int_0^1 t^{a-1} (1-t)^{b-1} dt = \frac{\Gamma(a)\Gamma(b)}{\Gamma(a+b)},$$

where Γ is the gamma function.

Parameters

a, b [array-like] Real-valued arguments
out [ndarray, optional] Optional output array for the function result

Returns

scalar or ndarray

Value of the beta function

See also:*gamma*

the gamma function

betainc

the incomplete beta function

betaln

the natural logarithm of the absolute value of the beta function

References

[1]

Examples

```
>>> import scipy.special as sc
```

The beta function relates to the gamma function by the definition given above:

```
>>> sc.beta(2, 3)
0.08333333333333333
>>> sc.gamma(2)*sc.gamma(3)/sc.gamma(2 + 3)
0.08333333333333333
```

As this relationship demonstrates, the beta function is symmetric:

```
>>> sc.beta(1.7, 2.4)
0.16567527689031739
>>> sc.beta(2.4, 1.7)
0.16567527689031739
```

This function satisfies $B(1, b) = 1/b$:

```
>>> sc.beta(1, 4)
0.25
```

scipy.special.betaln

`scipy.special.betaln(a, b) = <ufunc 'betaln'>`

Natural logarithm of absolute value of beta function.

Computes $\ln(\text{abs}(\text{beta}(a, b)))$.

scipy.special.betainc

`scipy.special.betainc(a, b, x, out=None) = <ufunc 'betainc'>`
 Incomplete beta function.

Computes the incomplete beta function, defined as [1]:

$$I_x(a, b) = \frac{\Gamma(a+b)}{\Gamma(a)\Gamma(b)} \int_0^x t^{a-1}(1-t)^{b-1} dt,$$

for $0 \leq x \leq 1$.

Parameters

a, b [array-like] Positive, real-valued parameters
x [array-like] Real-valued such that $0 \leq x \leq 1$, the upper limit of integration
out [ndarray, optional] Optional output array for the function values

Returns

array-like Value of the incomplete beta function

See also:

beta

beta function

betaincinv

inverse of the incomplete beta function

Notes

The incomplete beta function is also sometimes defined without the *gamma* terms, in which case the above definition is the so-called regularized incomplete beta function. Under this definition, you can get the incomplete beta function by multiplying the result of the SciPy function by *beta*.

References

[1]

Examples

Let $B(a, b)$ be the *beta* function.

```
>>> import scipy.special as sc
```

The coefficient in terms of *gamma* is equal to $1/B(a, b)$. Also, when $x = 1$ the integral is equal to $B(a, b)$. Therefore, $I_{x=1}(a, b) = 1$ for any a, b .

```
>>> sc.betainc(0.2, 3.5, 1.0)
1.0
```

It satisfies $I_x(a, b) = x^a F(a, 1-b, a+1, x)/(aB(a, b))$, where F is the hypergeometric function *hyp2f1*:

```
>>> a, b, x = 1.4, 3.1, 0.5
>>> x**a * sc.hyp2f1(a, 1 - b, a + 1, x) / (a * sc.beta(a, b))
0.8148904036225295
>>> sc.betainc(a, b, x)
0.8148904036225296
```

This function satisfies the relationship $I_x(a, b) = 1 - I_{1-x}(b, a)$:

```
>>> sc.betainc(2.2, 3.1, 0.4)
0.49339638807619446
>>> 1 - sc.betainc(3.1, 2.2, 1 - 0.4)
0.49339638807619446
```

scipy.special.betaincinv

`scipy.special.betaincinv(a, b, y, out=None)` = <ufunc 'betaincinv'>
Inverse of the incomplete beta function.

Computes x such that:

$$y = I_x(a, b) = \frac{\Gamma(a+b)}{\Gamma(a)\Gamma(b)} \int_0^x t^{a-1}(1-t)^{b-1} dt,$$

where I_x is the normalized incomplete beta function `betainc` and Γ is the `gamma` function [1].

Parameters

a, b [array-like] Positive, real-valued parameters
y [array-like] Real-valued input
out [ndarray, optional] Optional output array for function values

Returns

array-like Value of the inverse of the incomplete beta function

See also:

`betainc`

incomplete beta function

`gamma`

gamma function

References

[1]

Examples

```
>>> import scipy.special as sc
```

This function is the inverse of *betainc* for fixed values of *a* and *b*.

```
>>> a, b = 1.2, 3.1
>>> y = sc.betainc(a, b, 0.2)
>>> sc.betaincinv(a, b, y)
0.2
>>>
>>> a, b = 7.5, 0.4
>>> x = sc.betaincinv(a, b, 0.5)
>>> sc.betainc(a, b, x)
0.5
```

scipy.special.psi

`scipy.special.psi(z, out=None) = <ufunc 'psi'>`

The digamma function.

The logarithmic derivative of the gamma function evaluated at *z*.

Parameters

z [array_like] Real or complex argument.
out [ndarray, optional] Array for the computed values of `psi`.

Returns

digamma [ndarray] Computed values of `psi`.

Notes

For large values not close to the negative real axis, `psi` is computed using the asymptotic series (5.11.2) from [1]. For small arguments not close to the negative real axis, the recurrence relation (5.5.2) from [1] is used until the argument is large enough to use the asymptotic series. For values close to the negative real axis, the reflection formula (5.5.4) from [1] is used first. Note that `psi` has a family of zeros on the negative real axis which occur between the poles at nonpositive integers. Around the zeros the reflection formula suffers from cancellation and the implementation loses precision. The sole positive zero and the first negative zero, however, are handled separately by precomputing series expansions using [2], so the function should maintain full accuracy around the origin.

References

[1], [2]

scipy.special.rgamma

`scipy.special.rgamma(z, out=None) = <ufunc 'rgamma'>`

Reciprocal of the gamma function.

Defined as $1/\Gamma(z)$, where Γ is the gamma function. For more on the gamma function see [gamma](#).

Parameters

z [array_like] Real or complex valued input
out [ndarray, optional] Optional output array for the function results

Returns

scalar or ndarray
 Function results

See also:

[gamma](#), [gammaaln](#), [loggamma](#)

Notes

The gamma function has no zeros and has simple poles at nonpositive integers, so *rgamma* is an entire function with zeros at the nonpositive integers. See the discussion in [dlmf] for more details.

References

[dlmf]

Examples

```
>>> import scipy.special as sc
```

It is the reciprocal of the gamma function.

```
>>> sc.rgamma([1, 2, 3, 4])
array([1.         , 1.         , 0.5         , 0.16666667])
>>> 1 / sc.gamma([1, 2, 3, 4])
array([1.         , 1.         , 0.5         , 0.16666667])
```

It is zero at nonpositive integers.

```
>>> sc.rgamma([0, -1, -2, -3])
array([0., 0., 0., 0.])
```

It rapidly underflows to zero along the positive real axis.

```
>>> sc.rgamma([10, 100, 179])
array([2.75573192e-006, 1.07151029e-156, 0.00000000e+000])
```

scipy.special.polygamma`scipy.special.polygamma` (*n*, *x*)

Polygamma functions.

Defined as $\psi^{(n)}(x)$ where ψ is the *digamma* function. See [dlmf] for details.**Parameters**

n [array_like] The order of the derivative of the digamma function; must be integral
x [array_like] Real valued input

Returns

ndarray Function results

See also:

[*digamma*](#)**References**[\[dlmf\]](#)**Examples**

```
>>> from scipy import special
>>> x = [2, 3, 25.5]
>>> special.polygamma(1, x)
array([ 0.64493407,  0.39493407,  0.03999467])
>>> special.polygamma(0, x) == special.psi(x)
array([ True,  True,  True], dtype=bool)
```

scipy.special.multigammaln`scipy.special.multigammaln` (*a*, *d*)

Returns the log of multivariate gamma, also sometimes called the generalized gamma.

Parameters

a [ndarray] The multivariate gamma is computed for each item of *a*.
d [int] The dimension of the space of integration.

Returns

res [ndarray] The values of the log multivariate gamma at the given points *a*.

NotesThe formal definition of the multivariate gamma of dimension *d* for a real *a* is

$$\Gamma_d(a) = \int_{A>0} e^{-tr(A)} |A|^{a-(d+1)/2} dA$$

with the condition $a > (d - 1)/2$, and $A > 0$ being the set of all the positive definite matrices of dimension *d*. Note that *a* is a scalar: the integrand only is multivariate, the argument is not (the function is defined over a subset of the real set).

This can be proven to be equal to the much friendlier equation

$$\Gamma_d(a) = \pi^{d(d-1)/4} \prod_{i=1}^d \Gamma(a - (i - 1)/2).$$

References

R. J. Muirhead, Aspects of multivariate statistical theory (Wiley Series in probability and mathematical statistics).

scipy.special.digamma

`scipy.special.digamma(z, out=None) = <ufunc 'psi'>`

The digamma function.

The logarithmic derivative of the gamma function evaluated at `z`.

Parameters

z [array_like] Real or complex argument.
out [ndarray, optional] Array for the computed values of `psi`.

Returns

digamma [ndarray] Computed values of `psi`.

Notes

For large values not close to the negative real axis, `psi` is computed using the asymptotic series (5.11.2) from [1]. For small arguments not close to the negative real axis, the recurrence relation (5.5.2) from [1] is used until the argument is large enough to use the asymptotic series. For values close to the negative real axis, the reflection formula (5.5.4) from [1] is used first. Note that `psi` has a family of zeros on the negative real axis which occur between the poles at nonpositive integers. Around the zeros the reflection formula suffers from cancellation and the implementation loses precision. The sole positive zero and the first negative zero, however, are handled separately by precomputing series expansions using [2], so the function should maintain full accuracy around the origin.

References

[1], [2]

scipy.special.poch

`scipy.special.poch(z, m) = <ufunc 'poch'>`

Pochhammer symbol.

The Pochhammer symbol (rising factorial) is defined as

$$(z)_m = \frac{\Gamma(z + m)}{\Gamma(z)}$$

For positive integer `m` it reads

$$(z)_m = z(z + 1)\dots(z + m - 1)$$

See [dlmf] for more details.

Parameters

z, m [array_like] Real-valued arguments.

Returns

scalar or ndarray
The value of the function.

References

[dlmf]

Examples

```
>>> import scipy.special as sc
```

It is 1 when m is 0.

```
>>> sc.poch([1, 2, 3, 4], 0)
array([1., 1., 1., 1.])
```

For z equal to 1 it reduces to the factorial function.

```
>>> sc.poch(1, 5)
120.0
>>> 1 * 2 * 3 * 4 * 5
120
```

It can be expressed in terms of the gamma function.

```
>>> z, m = 3.7, 2.1
>>> sc.poch(z, m)
20.529581933776953
>>> sc.gamma(z + m) / sc.gamma(z)
20.52958193377696
```

Error function and Fresnel integrals

<i>erf</i> (z)	Returns the error function of complex argument.
<i>erfc</i> (x[, out])	Complementary error function, $1 - \text{erf}(x)$.
<i>erfcx</i> (x[, out])	Scaled complementary error function, $\exp(x^2) * \text{erfc}(x)$.
<i>erfi</i> (z[, out])	Imaginary error function, $-i \text{erf}(i z)$.
<i>erfinv</i> (x, /[, out, where, casting, order, ...])	Inverse of the error function.
<i>erfcinv</i> (x, /[, out, where, casting, order, ...])	Inverse of the complementary error function.
<i>wofz</i> (z)	Faddeeva function
<i>dawson</i> (x)	Dawson's integral.
<i>fresnel</i> (z[, out])	Fresnel integrals.
<i>fresnel_zeros</i> (nt)	Compute nt complex zeros of sine and cosine Fresnel integrals S(z) and C(z).
<i>modfresnelp</i> (x)	Modified Fresnel positive integrals

continues on next page

Table 232 – continued from previous page

<code>modfresnelm(x)</code>	Modified Fresnel negative integrals
<code>voigt_profile(x, sigma, gamma[, out])</code>	Voigt profile.

scipy.special.erf

`scipy.special.erf(z) = <ufunc 'erf'>`

Returns the error function of complex argument.

It is defined as $2/\sqrt{\pi} \int_0^z \exp(-t^2) dt$.

Parameters

x [ndarray] Input array.

Returns

res [ndarray] The values of the error function at the given points *x*.

See also:

erfc, erfinv, erfcinv, wofz, erfcx, erfi

Notes

The cumulative of the unit normal distribution is given by $\Phi(z) = 1/2[1 + \text{erf}(z/\sqrt{2})]$.

References

[1], [2], [3]

Examples

```
>>> from scipy import special
>>> import matplotlib.pyplot as plt
>>> x = np.linspace(-3, 3)
>>> plt.plot(x, special.erf(x))
>>> plt.xlabel('$x$')
>>> plt.ylabel('$\text{erf}(x)$')
>>> plt.show()
```

scipy.special.erfc

`scipy.special.erfc(x, out=None) = <ufunc 'erfc'>`

Complementary error function, $1 - \text{erf}(x)$.

Parameters


x [array_like] Real or complex valued argument

out [ndarray, optional] Optional output array for the function results

Returns

scalar or ndarray
Values of the complementary error function

See also:



erf, erfi, erfcx, dawson, wofz

References

[1]

Examples

```
>>> from scipy import special
>>> import matplotlib.pyplot as plt
>>> x = np.linspace(-3, 3)
>>> plt.plot(x, special.erfc(x))
>>> plt.xlabel('$x$')
>>> plt.ylabel('$erfc(x)$')
>>> plt.show()
```

scipy.special.erfcx

`scipy.special.erfcx(x, out=None) = <ufunc 'erfcx'>`
Scaled complementary error function, $\exp(x^2) * \text{erfc}(x)$.

Parameters


x [array_like] Real or complex valued argument
out [ndarray, optional] Optional output array for the function results

Returns

scalar or ndarray
Values of the scaled complementary error function

See also:

erf, erfc, erfi, dawson, wofz



Notes

New in version 0.12.0.

References

[1]

Examples

```
>>> from scipy import special
>>> import matplotlib.pyplot as plt
>>> x = np.linspace(-3, 3)
>>> plt.plot(x, special.erfcx(x))
>>> plt.xlabel('$x$')
>>> plt.ylabel('$erfcx(x)$')
>>> plt.show()
```

scipy.special.erfi

`scipy.special.erfi(z, out=None) = <ufunc 'erfi'>`

Imaginary error function, $-i \operatorname{erf}(i z)$.


Parameters

z [array_like] Real or complex valued argument
out [ndarray, optional] Optional output array for the function results

Returns

scalar or ndarray
 Values of the imaginary error function

See also:



erf, erfc, erfcx, dawson, wofz

Notes

New in version 0.12.0.

References

[1]

Examples

```
>>> from scipy import special
>>> import matplotlib.pyplot as plt
>>> x = np.linspace(-3, 3)
>>> plt.plot(x, special.erfi(x))
>>> plt.xlabel('$x$')
>>> plt.ylabel('$erfi(x)$')
>>> plt.show()
```

scipy.special.erfinv


`scipy.special.erfinv(x, /, out=None, *, where=True, casting='same_kind', order='K', dtype=None, subok=True[, signature, extobj]) = <ufunc 'erfinv'>`

Inverse of the error function.

Computes the inverse of the error function.

In the complex domain, there is no unique complex number w satisfying $\text{erf}(w)=z$. This indicates a true inverse function would have multi-value. When the domain restricts to the real, $-1 < x < 1$, there is a unique real number satisfying $\text{erf}(\text{erfinv}(x)) = x$.

Parameters



y [ndarray] Argument at which to evaluate. Domain: $[-1, 1]$

Returns

erfinv [ndarray] The inverse of erf of y, element-wise)

See also:

erf

Error function of a complex argument

erfc

Complementary error function, $1 - \text{erf}(x)$

erfcinv

Inverse of the complementary error function

Examples

- 1) evaluating a float number

```
>>> from scipy import special
>>> special.erfinv(0.5)
0.4769362762044698
```

- 2) evaluating an ndarray

```
>>> from scipy import special
>>> y = np.linspace(-1.0, 1.0, num=10)
>>> special.erfinv(y)
array([      -inf, -0.86312307, -0.5407314 , -0.30457019, -0.0987901 ,
         0.0987901 ,  0.30457019,  0.5407314 ,  0.86312307,       inf])
```

scipy.special.erfcinv

`scipy.special.erfcinv(x, /, out=None, *, where=True, casting='same_kind', order='K', dtype=None, subok=True[, signature, extobj]) = <ufunc 'erfcinv'>`

Inverse of the complementary error function.

Computes the inverse of the complementary error function.

In the complex domain, there is no unique complex number w satisfying $\operatorname{erfc}(w)=z$. This indicates a true inverse function would have multi-value. When the domain restricts to the real, $0 < x < 2$, there is a unique real number satisfying $\operatorname{erfc}(\operatorname{erfcinv}(x)) = \operatorname{erfcinv}(\operatorname{erfc}(x))$.

It is related to inverse of the error function by $\operatorname{erfcinv}(1-x) = \operatorname{erfinv}(x)$

Parameters

y [ndarray] Argument at which to evaluate. Domain: [0, 2]

Returns

erfcinv [ndarray] The inverse of erfc of y , element-wise

See also:***erf***

Error function of a complex argument

erfc

Complementary error function, $1 - \operatorname{erf}(x)$

erfinv

Inverse of the error function

Examples

- 1) evaluating a float number

```
>>> from scipy import special
>>> special.erfcinv(0.5)
0.4769362762044698
```

- 2) evaluating an ndarray

```
>>> from scipy import special
>>> y = np.linspace(0.0, 2.0, num=11)
>>> special.erfcinv(y)
array([          inf,  0.9061938 ,  0.59511608,  0.37080716,  0.17914345,
        -0.          , -0.17914345, -0.37080716, -0.59511608, -0.9061938 ,
        -inf])
```

scipy.special.wofz

`scipy.special.wofz(z)` = <ufunc 'wofz'>

Faddeeva function

Returns the value of the Faddeeva function for complex argument:

```
exp(-z**2) * erfc(-i*z)
```

See also:

dawsn, erf, erfc, erfcx, erfi

References


[1]

Examples

```
>>> from scipy import special
>>> import matplotlib.pyplot as plt
```

```
>>> x = np.linspace(-3, 3)
>>> z = special.wofz(x)
```

```
>>> plt.plot(x, z.real, label='wofz(x).real')
>>> plt.plot(x, z.imag, label='wofz(x).imag')
>>> plt.xlabel('$x$')
>>> plt.legend(framealpha=1, shadow=True)
>>> plt.grid(alpha=0.25)
>>> plt.show()
```



scipy.special.dawsn

`scipy.special.dawsn(x)` = <ufunc 'dawsn'>
Dawson's integral.

Computes:

```
exp(-x**2) * integral(exp(t**2), t=0..x).
```

See also:


wofz, erf, erfc, erfcx, erfi

References

[1]

Examples

```
>>> from scipy import special
>>> import matplotlib.pyplot as plt
>>> x = np.linspace(-15, 15, num=1000)
>>> plt.plot(x, special.dawsn(x))
>>> plt.xlabel('$x$')
>>> plt.ylabel('$dawsn(x)$')
>>> plt.show()
```



scipy.special.fresnel

`scipy.special.fresnel(z, out=None) = <ufunc 'fresnel'>`
 Fresnel integrals.

The Fresnel integrals are defined as

$$S(z) = \int_0^z \sin(\pi t^2/2) dt$$

$$C(z) = \int_0^z \cos(\pi t^2/2) dt.$$

See [dlmf] for details.

Parameters

z [array_like] Real or complex valued argument
out [2-tuple of ndarrays, optional] Optional output arrays for the function results

Returns

S, C [2-tuple of scalar or ndarray] Values of the Fresnel integrals

See also:

fresnel_zeros

zeros of the Fresnel integrals

References

[dlmf]

Examples

```
>>> import scipy.special as sc
```

As z goes to infinity along the real axis, S and C converge to 0.5.

```
>>> S, C = sc.fresnel([0.1, 1, 10, 100, np.inf])
>>> S
array([0.00052359, 0.43825915, 0.46816998, 0.4968169 , 0.5       ])
>>> C
array([0.09999753, 0.7798934 , 0.49989869, 0.4999999 , 0.5       ])
```

They are related to the error function *erf*.

```
>>> z = np.array([1, 2, 3, 4])
>>> zeta = 0.5 * np.sqrt(np.pi) * (1 - 1j) * z
>>> S, C = sc.fresnel(z)
>>> C + 1j*S
array([0.7798934 +0.43825915j, 0.48825341+0.34341568j,
       0.60572079+0.496313j , 0.49842603+0.42051575j])
>>> 0.5 * (1 + 1j) * sc.erf(zeta)
array([0.7798934 +0.43825915j, 0.48825341+0.34341568j,
       0.60572079+0.496313j , 0.49842603+0.42051575j])
```

scipy.special.fresnel_zeros

`scipy.special.fresnel_zeros` (*nt*)

Compute *nt* complex zeros of sine and cosine Fresnel integrals $S(z)$ and $C(z)$.

References

[1]

scipy.special.modfresnelp

`scipy.special.modfresnelp` (*x*) = <ufunc 'modfresnelp'>

Modified Fresnel positive integrals

Returns

fp	Integral $F_+(x)$: $\text{integral}(\exp(1j*t*t), t=x..\text{inf})$
kp	Integral $K_+(x)$: $1/\text{sqrt}(\text{pi}) * \exp(-1j*(x*x+\text{pi}/4)) * \text{fp}$

scipy.special.modfresnelm

`scipy.special.modfresnelm` (*x*) = <ufunc 'modfresnelm'>

Modified Fresnel negative integrals

Returns

fm	Integral $F_-(x)$: $\text{integral}(\exp(-1j*t*t), t=x..\text{inf})$
km	Integral $K_-(x)$: $1/\text{sqrt}(\text{pi}) * \exp(1j*(x*x+\text{pi}/4)) * \text{fm}$

scipy.special.voigt_profile

`scipy.special.voigt_profile` (*x, sigma, gamma, out=None*) = <ufunc 'voigt_profile'>

Voigt profile.

The Voigt profile is a convolution of a 1-D Normal distribution with standard deviation *sigma* and a 1-D Cauchy distribution with half-width at half-maximum *gamma*.

If *sigma* = 0, PDF of Cauchy distribution is returned. Conversely, if *gamma* = 0, PDF of Normal distribution is returned. If *sigma* = *gamma* = 0, the return value is *Inf* for *x* = 0, and 0 for all other *x*.

Parameters

x	[array_like] Real argument
sigma	[array_like] The standard deviation of the Normal distribution part
gamma	[array_like] The half-width at half-maximum of the Cauchy distribution part
out	[ndarray, optional] Optional output array for the function values

Returns

scalar or ndarray
The Voigt profile at the given arguments

See also:

[*wofz*](#)

Faddeeva function

Notes

It can be expressed in terms of Faddeeva function

$$V(x; \sigma, \gamma) = \frac{\operatorname{Re}[w(z)]}{\sigma\sqrt{2\pi}},$$

$$z = \frac{x + i\gamma}{\sqrt{2}\sigma}$$

where $w(z)$ is the Faddeeva function.

References

[1]

These are not universal functions:

<code>erf_zeros(nt)</code>	Compute the first <code>nt</code> zero in the first quadrant, ordered by absolute value.
<code>fresnelc_zeros(nt)</code>	Compute <code>nt</code> complex zeros of cosine Fresnel integral $C(z)$.
<code>fresnels_zeros(nt)</code>	Compute <code>nt</code> complex zeros of sine Fresnel integral $S(z)$.

scipy.special.erf_zeros

`scipy.special.erf_zeros(nt)`

Compute the first `nt` zero in the first quadrant, ordered by absolute value.

Zeros in the other quadrants can be obtained by using the symmetries $\operatorname{erf}(-z) = -\operatorname{erf}(z)$ and $\operatorname{erf}(\operatorname{conj}(z)) = \operatorname{conj}(\operatorname{erf}(z))$.

Parameters

nt [int] The number of zeros to compute

Returns

The locations of the zeros of erf

[ndarray (complex)] Complex values at which zeros of $\operatorname{erf}(z)$

References

[1]

Examples

```
>>> from scipy import special
>>> special.erf_zeros(1)
array([1.45061616+1.880943j])
```

Check that erf is (close to) zero for the value returned by `erf_zeros`

```
>>> special.erf(special.erf_zeros(1))
array([4.95159469e-14-1.16407394e-16j])
```

scipy.special.fresnelc_zeros

`scipy.special.fresnelc_zeros` (*nt*)
 Compute *nt* complex zeros of cosine Fresnel integral C(z).

References

[1]

scipy.special.fresnels_zeros

`scipy.special.fresnels_zeros` (*nt*)
 Compute *nt* complex zeros of sine Fresnel integral S(z).

References

[1]

Legendre functions

<code>lpmv</code> (<i>m</i> , <i>v</i> , <i>x</i>)	Associated Legendre function of integer order and real degree.
<code>sph_harm</code> (<i>m</i> , <i>n</i> , <i>theta</i> , <i>phi</i>)	Compute spherical harmonics.

scipy.special.lpmv

`scipy.special.lpmv` (*m*, *v*, *x*) = `<ufunc 'lpmv'>`
 Associated Legendre function of integer order and real degree.

Defined as

$$P_v^m = (-1)^m (1 - x^2)^{m/2} \frac{d^m}{dx^m} P_v(x)$$

where

$$P_v = \sum_{k=0}^{\infty} \frac{(-v)_k (v+1)_k}{(k!)^2} \left(\frac{1-x}{2}\right)^k$$

is the Legendre function of the first kind. Here $(\cdot)_k$ is the Pochhammer symbol; see [poch](#).

Parameters

- m** [array_like] Order (int or float). If passed a float not equal to an integer the function returns NaN.
- v** [array_like] Degree (float).
- x** [array_like] Argument (float). Must have $|x| \leq 1$.

Returns

- pmv** [ndarray] Value of the associated Legendre function.

See also:

`lpmn`

Compute the associated Legendre function for all orders $0, \dots, m$ and degrees $0, \dots, n$.

clpmn

Compute the associated Legendre function at complex arguments.

Notes

Note that this implementation includes the Condon-Shortley phase.

References

[1]

scipy.special.sph_harm

`scipy.special.sph_harm(m, n, theta, phi) = <ufunc 'sph_harm'>`

Compute spherical harmonics.

The spherical harmonics are defined as

$$Y_n^m(\theta, \phi) = \sqrt{\frac{2n+1}{4\pi} \frac{(n-m)!}{(n+m)!}} e^{im\theta} P_n^m(\cos(\phi))$$

where P_n^m are the associated Legendre functions; see [lpmv](#).

Parameters

m	[array_like] Order of the harmonic (int); must have $ m \leq n$.
n	[array_like] Degree of the harmonic (int); must have $n \geq 0$. This is often denoted by l (lower case L) in descriptions of spherical harmonics.
theta	[array_like] Azimuthal (longitudinal) coordinate; must be in $[0, 2\pi]$.
phi	[array_like] Polar (colatitudinal) coordinate; must be in $[0, \pi]$.

Returns

y_mn	[complex float] The harmonic Y_n^m sampled at <code>theta</code> and <code>phi</code> .
-------------	---

Notes

There are different conventions for the meanings of the input arguments `theta` and `phi`. In SciPy `theta` is the azimuthal angle and `phi` is the polar angle. It is common to see the opposite convention, that is, `theta` as the polar angle and `phi` as the azimuthal angle.

Note that SciPy's spherical harmonics include the Condon-Shortley phase [2] because it is part of [lpmv](#).

With SciPy's conventions, the first several spherical harmonics are

$$\begin{aligned} Y_0^0(\theta, \phi) &= \frac{1}{2} \sqrt{\frac{1}{\pi}} \\ Y_1^{-1}(\theta, \phi) &= \frac{1}{2} \sqrt{\frac{3}{2\pi}} e^{-i\theta} \sin(\phi) \\ Y_1^0(\theta, \phi) &= \frac{1}{2} \sqrt{\frac{3}{\pi}} \cos(\phi) \\ Y_1^1(\theta, \phi) &= -\frac{1}{2} \sqrt{\frac{3}{2\pi}} e^{i\theta} \sin(\phi). \end{aligned}$$

References

[1], [2]

These are not universal functions:

<code>clpmn(m, n, z[, type])</code>	Associated Legendre function of the first kind for complex arguments.
<code>lpn(n, z)</code>	Legendre function of the first kind.
<code>lqn(n, z)</code>	Legendre function of the second kind.
<code>lpmn(m, n, z)</code>	Sequence of associated Legendre functions of the first kind.
<code>lqmn(m, n, z)</code>	Sequence of associated Legendre functions of the second kind.

scipy.special.clpmn

`scipy.special.clpmn(m, n, z, type=3)`

Associated Legendre function of the first kind for complex arguments.

Computes the associated Legendre function of the first kind of order m and degree n , $P_{mn}(z) = P_n^m(z)$, and its derivative, $P_{mn}'(z)$. Returns two arrays of size $(m+1, n+1)$ containing $P_{mn}(z)$ and $P_{mn}'(z)$ for all orders from $0 \dots m$ and degrees from $0 \dots n$.

Parameters

- m** [int] $|m| \leq n$; the order of the Legendre function.
- n** [int] where $n \geq 0$; the degree of the Legendre function. Often called l (lower case L) in descriptions of the associated Legendre function
- z** [float or complex] Input value.
- type** [int, optional] takes values 2 or 3 2: cut on the real axis $|x| > 1$ 3: cut on the real axis $-1 < x < 1$ (default)

Returns

- Pmn_z** [(m+1, n+1) array] Values for all orders $0 \dots m$ and degrees $0 \dots n$
- Pmn_d_z** [(m+1, n+1) array] Derivatives for all orders $0 \dots m$ and degrees $0 \dots n$

See also:

[lpmn](#)

associated Legendre functions of the first kind for real z

Notes

By default, i.e. for `type=3`, phase conventions are chosen according to [1] such that the function is analytic. The cut lies on the interval $(-1, 1)$. Approaching the cut from above or below in general yields a phase factor with respect to Ferrer's function of the first kind (cf. [lpmn](#)).

For `type=2` a cut at $|x| > 1$ is chosen. Approaching the real values on the interval $(-1, 1)$ in the complex plane yields Ferrer's function of the first kind.

References

[1], [2]

scipy.special.lpn

`scipy.special.lpn` (n, z)

Legendre function of the first kind.

Compute sequence of Legendre functions of the first kind (polynomials), $P_n(z)$ and derivatives for all degrees from 0 to n (inclusive).

See also `special.legendre` for polynomial class.

References

[1]

scipy.special.lqn

`scipy.special.lqn` (n, z)

Legendre function of the second kind.

Compute sequence of Legendre functions of the second kind, $Q_n(z)$ and derivatives for all degrees from 0 to n (inclusive).

References

[1]

scipy.special.lpmn

`scipy.special.lpmn` (m, n, z)

Sequence of associated Legendre functions of the first kind.

Computes the associated Legendre function of the first kind of order m and degree n , $P_m^n(z) = P_n^m(z)$, and its derivative, $P_m^n'(z)$. Returns two arrays of size $(m+1, n+1)$ containing $P_m^n(z)$ and $P_m^n'(z)$ for all orders from 0.. m and degrees from 0.. n .

This function takes a real argument z . For complex arguments z use `clpmn` instead.

Parameters

- m** [int] $|m| \leq n$; the order of the Legendre function.
- n** [int] where $n \geq 0$; the degree of the Legendre function. Often called l (lower case L) in descriptions of the associated Legendre function
- z** [float] Input value.

Returns

- Pmn_z** [($m+1, n+1$) array] Values for all orders 0.. m and degrees 0.. n
- Pmn_d_z** [($m+1, n+1$) array] Derivatives for all orders 0.. m and degrees 0.. n

See also:

`clpmn`

associated Legendre functions of the first kind for complex z

Notes

In the interval $(-1, 1)$, Ferrer's function of the first kind is returned. The phase convention used for the intervals $(1, \infty)$ and $(-\infty, -1)$ is such that the result is always real.

References

[1], [2]

scipy.special.lqmn

`scipy.special.lqmn(m, n, z)`

Sequence of associated Legendre functions of the second kind.

Computes the associated Legendre function of the second kind of order m and degree n , $Q_{mn}(z) = Q_n^m(z)$, and its derivative, $Q_{mn}'(z)$. Returns two arrays of size $(m+1, n+1)$ containing $Q_{mn}(z)$ and $Q_{mn}'(z)$ for all orders from $0..m$ and degrees from $0..n$.

Parameters

- m** [int] $|m| \leq n$; the order of the Legendre function.
- n** [int] where $n \geq 0$; the degree of the Legendre function. Often called l (lower case L) in descriptions of the associated Legendre function
- z** [complex] Input value.

Returns

- Qmn_z** [(m+1, n+1) array] Values for all orders $0..m$ and degrees $0..n$
- Qmn_d_z** [(m+1, n+1) array] Derivatives for all orders $0..m$ and degrees $0..n$

References

[1]

Ellipsoidal harmonics

<code>ellip_harm(h2, k2, n, p, s[, signm, signn])</code>	Ellipsoidal harmonic functions $E^p_n(l)$
<code>ellip_harm_2(h2, k2, n, p, s)</code>	Ellipsoidal harmonic functions $F^p_n(l)$
<code>ellip_normal(h2, k2, n, p)</code>	Ellipsoidal harmonic normalization constants γ^p_n

scipy.special.ellip_harm

`scipy.special.ellip_harm(h2, k2, n, p, s, signm=1, signn=1)`

Ellipsoidal harmonic functions $E^p_n(l)$

These are also known as Lamé functions of the first kind, and are solutions to the Lamé equation:

$$(s^2 - h^2)(s^2 - k^2)E''(s) + s(2s^2 - h^2 - k^2)E'(s) + (a - qs^2)E(s) = 0$$

where $q = (n + 1)n$ and a is the eigenvalue (not returned) corresponding to the solutions.

Parameters

- h2** [float] h^{*2}
- k2** [float] k^{*2} ; should be larger than h^{*2}

n [int] Degree
s [float] Coordinate
p [int] Order, can range between [1,2n+1]
signm [{1, -1}, optional] Sign of prefactor of functions. Can be +/-1. See Notes.
signn [{1, -1}, optional] Sign of prefactor of functions. Can be +/-1. See Notes.

Returns

E [float] the harmonic $E_n^p(s)$

See also:

[`ellip_harm_2`](#), [`ellip_normal`](#)

Notes

The geometric interpretation of the ellipsoidal functions is explained in [2], [3], [4]. The *signm* and *signn* arguments control the sign of prefactors for functions according to their type:

```
K : +1
L : signm
M : signn
N : signm*signn
```

New in version 0.15.0.

References

[1], [2], [3], [4]

Examples

```
>>> from scipy.special import ellip_harm
>>> w = ellip_harm(5, 8, 1, 1, 2.5)
>>> w
2.5
```

Check that the functions indeed are solutions to the Lamé equation:

```
>>> from scipy.interpolate import UnivariateSpline
>>> def eigenvalue(f, df, ddf):
...     r = ((s**2 - h**2)*(s**2 - k**2)*ddf + s*(2*s**2 - h**2 -
...     ↪ k**2)*df - n*(n+1)*s**2*f)/f
...     return -r.mean(), r.std()
>>> s = np.linspace(0.1, 10, 200)
>>> k, h, n, p = 8.0, 2.2, 3, 2
>>> E = ellip_harm(h**2, k**2, n, p, s)
>>> E_spl = UnivariateSpline(s, E)
>>> a, a_err = eigenvalue(E_spl(s), E_spl(s,1), E_spl(s,2))
>>> a, a_err
(583.44366156701483, 6.4580890640310646e-11)
```

scipy.special.ellip_harm_2

scipy.special.ellip_harm_2(h2, k2, n, p, s)

Ellipsoidal harmonic functions $F^p_n(l)$

These are also known as Lamé functions of the second kind, and are solutions to the Lamé equation:

$$(s^2 - h^2)(s^2 - k^2)F''(s) + s(2s^2 - h^2 - k^2)F'(s) + (a - qs^2)F(s) = 0$$

where $q = (n + 1)n$ and a is the eigenvalue (not returned) corresponding to the solutions.

Parameters

h2	[float] h^{**2}
k2	[float] k^{**2} ; should be larger than h^{**2}
n	[int] Degree.
p	[int] Order, can range between $[1, 2n+1]$.
s	[float] Coordinate

Returns

F	[float] The harmonic $F^p_n(s)$
----------	---------------------------------

See also:

[ellip_harm](#), [ellip_normal](#)

Notes

Lamé functions of the second kind are related to the functions of the first kind:

$$F^p_n(s) = (2n + 1)E^p_n(s) \int_0^{1/s} \frac{du}{(E^p_n(1/u))^2 \sqrt{(1 - u^2k^2)(1 - u^2h^2)}}$$

New in version 0.15.0.

Examples

```
>>> from scipy.special import ellip_harm_2
>>> w = ellip_harm_2(5, 8, 2, 1, 10)
>>> w
0.00108056853382
```

scipy.special.ellip_normal

scipy.special.ellip_normal(h2, k2, n, p)

Ellipsoidal harmonic normalization constants γ^p_n

The normalization constant is defined as

$$\gamma^p_n = 8 \int_0^h dx \int_h^k dy \frac{(y^2 - x^2)(E^p_n(y)E^p_n(x))^2}{\sqrt{(k^2 - y^2)(y^2 - h^2)(h^2 - x^2)(k^2 - x^2)}}$$

Parameters

h2	[float] h^{**2}
k2	[float] k^{**2} ; should be larger than h^{**2}
n	[int] Degree.

p [int] Order, can range between $[1, 2n+1]$.

Returns

gamma [float] The normalization constant γ_n^p

See also:

[`ellip_harm`](#), [`ellip_harm_2`](#)

Notes

New in version 0.15.0.

Examples

```
>>> from scipy.special import ellip_normal
>>> w = ellip_normal(5, 8, 3, 7)
>>> w
1723.38796997
```

Orthogonal polynomials

The following functions evaluate values of orthogonal polynomials:

<code>assoc_laguerre(x, n[, k])</code>	Compute the generalized (associated) Laguerre polynomial of degree n and order k .
<code>eval_legendre(n, x[, out])</code>	Evaluate Legendre polynomial at a point.
<code>eval_chebyt(n, x[, out])</code>	Evaluate Chebyshev polynomial of the first kind at a point.
<code>eval_chebyu(n, x[, out])</code>	Evaluate Chebyshev polynomial of the second kind at a point.
<code>eval_chebyc(n, x[, out])</code>	Evaluate Chebyshev polynomial of the first kind on $[-2, 2]$ at a point.
<code>eval_chebys(n, x[, out])</code>	Evaluate Chebyshev polynomial of the second kind on $[-2, 2]$ at a point.
<code>eval_jacobi(n, alpha, beta, x[, out])</code>	Evaluate Jacobi polynomial at a point.
<code>eval_laguerre(n, x[, out])</code>	Evaluate Laguerre polynomial at a point.
<code>eval_genlaguerre(n, alpha, x[, out])</code>	Evaluate generalized Laguerre polynomial at a point.
<code>eval_hermite(n, x[, out])</code>	Evaluate physicist's Hermite polynomial at a point.
<code>eval_hermitenorm(n, x[, out])</code>	Evaluate probabilist's (normalized) Hermite polynomial at a point.
<code>eval_gegenbauer(n, alpha, x[, out])</code>	Evaluate Gegenbauer polynomial at a point.
<code>eval_sh_legendre(n, x[, out])</code>	Evaluate shifted Legendre polynomial at a point.
<code>eval_sh_chebyt(n, x[, out])</code>	Evaluate shifted Chebyshev polynomial of the first kind at a point.
<code>eval_sh_chebyu(n, x[, out])</code>	Evaluate shifted Chebyshev polynomial of the second kind at a point.
<code>eval_sh_jacobi(n, p, q, x[, out])</code>	Evaluate shifted Jacobi polynomial at a point.

scipy.special.assoc_laguerre`scipy.special.assoc_laguerre(x, n, k=0.0)`Compute the generalized (associated) Laguerre polynomial of degree n and order k .The polynomial $L_n^{(k)}(x)$ is orthogonal over $[0, \infty)$, with weighting function $\exp(-x) * x^{**k}$ with $k > -1$.**Notes***assoc_laguerre* is a simple wrapper around *eval_genlaguerre*, with reversed argument order ($x, n, k=0.0$) \rightarrow (n, k, x).**scipy.special.eval_legendre**`scipy.special.eval_legendre(n, x, out=None) = <ufunc 'eval_legendre'>`

Evaluate Legendre polynomial at a point.

The Legendre polynomials can be defined via the Gauss hypergeometric function ${}_2F_1$ as

$$P_n(x) = {}_2F_1(-n, n + 1; 1; (1 - x)/2).$$

When n is an integer the result is a polynomial of degree n . See 22.5.49 in [AS] for details.**Parameters**

- n** [array_like] Degree of the polynomial. If not an integer, the result is determined via the relation to the Gauss hypergeometric function.
- x** [array_like] Points at which to evaluate the Legendre polynomial

Returns

- P** [ndarray] Values of the Legendre polynomial

See also:***roots_legendre***

roots and quadrature weights of Legendre polynomials

legendre

Legendre polynomial object

hyp2f1

Gauss hypergeometric function

numpy.polynomial.legendre.Legendre

Legendre series

References

[AS]

Examples

```
>>> from scipy.special import eval_legendre
```

Evaluate the zero-order Legendre polynomial at $x = 0$

```
>>> eval_legendre(0, 0)
1.0
```

Evaluate the first-order Legendre polynomial between -1 and 1

```
>>> import numpy as np
>>> X = np.linspace(-1, 1, 5) # Domain of Legendre polynomials
>>> eval_legendre(1, X)
array([-1. , -0.5,  0. ,  0.5,  1. ])
```

Evaluate Legendre polynomials of order 0 through 4 at $x = 0$

```
>>> N = range(0, 5)
>>> eval_legendre(N, 0)
array([ 1. ,  0. , -0.5 ,  0. ,  0.375])
```

Plot Legendre polynomials of order 0 through 4

```
>>> X = np.linspace(-1, 1)
```

```
>>> import matplotlib.pyplot as plt
>>> for n in range(0, 5):
...     y = eval_legendre(n, X)
...     plt.plot(X, y, label=r'$P_{%d}(x)$'.format(n))
```

```
>>> plt.title("Legendre Polynomials")
>>> plt.xlabel("x")
>>> plt.ylabel(r'$P_n(x)$')
>>> plt.legend(loc='lower right')
>>> plt.show()
```

scipy.special.eval_chebyt

`scipy.special.eval_chebyt(n, x, out=None)` = <ufunc 'eval_chebyt'>


Evaluate Chebyshev polynomial of the first kind at a point.

The Chebyshev polynomials of the first kind can be defined via the Gauss hypergeometric function ${}_2F_1$ as

$$T_n(x) = {}_2F_1(n, -n; 1/2; (1-x)/2).$$

When n is an integer the result is a polynomial of degree n . See 22.5.47 in [AS] for details.

Parameters



- n** [array_like] Degree of the polynomial. If not an integer, the result is determined via the relation to the Gauss hypergeometric function.
- x** [array_like] Points at which to evaluate the Chebyshev polynomial

Returns

- T** [ndarray] Values of the Chebyshev polynomial

See also:*roots_chebyt*

roots and quadrature weights of Chebyshev polynomials of the first kind

chebyu

Chebyshev polynomial object

eval_chebyu

evaluate Chebyshev polynomials of the second kind

hyp2f1

Gauss hypergeometric function

numpy.polynomial.chebyshev.Chebyshev

Chebyshev series

Notes

This routine is numerically stable for x in $[-1, 1]$ at least up to order 10000.

References

[AS]

scipy.special.eval_chebyu

`scipy.special.eval_chebyu(n, x, out=None) = <ufunc 'eval_chebyu'>`

Evaluate Chebyshev polynomial of the second kind at a point.

The Chebyshev polynomials of the second kind can be defined via the Gauss hypergeometric function ${}_2F_1$ as

$$U_n(x) = (n + 1) {}_2F_1(-n, n + 2; 3/2; (1 - x)/2).$$

When n is an integer the result is a polynomial of degree n . See 22.5.48 in [AS] for details.

Parameters

- n** [array_like] Degree of the polynomial. If not an integer, the result is determined via the relation to the Gauss hypergeometric function.
- x** [array_like] Points at which to evaluate the Chebyshev polynomial

Returns

- U** [ndarray] Values of the Chebyshev polynomial

See also:

roots_chebyu

roots and quadrature weights of Chebyshev polynomials of the second kind

chebyu

Chebyshev polynomial object

eval_chebyt

evaluate Chebyshev polynomials of the first kind

hyp2f1

Gauss hypergeometric function

References

[AS]

scipy.special.eval_chebyc

`scipy.special.eval_chebyc` (*n*, *x*, *out=None*) = <ufunc 'eval_chebyc'>
Evaluate Chebyshev polynomial of the first kind on [-2, 2] at a point.

These polynomials are defined as

$$C_n(x) = 2T_n(x/2)$$

where T_n is a Chebyshev polynomial of the first kind. See 22.5.11 in [AS] for details.

Parameters

- n** [array_like] Degree of the polynomial. If not an integer, the result is determined via the relation to `eval_chebyt`.
- x** [array_like] Points at which to evaluate the Chebyshev polynomial

Returns

- C** [ndarray] Values of the Chebyshev polynomial

See also:**`roots_chebyc`**

roots and quadrature weights of Chebyshev polynomials of the first kind on [-2, 2]

`chebyc`

Chebyshev polynomial object

`numpy.polynomial.chebyshev.Chebyshev`

Chebyshev series

`eval_chebyt`

evaluate Chebyshev polynomials of the first kind

References

[AS]

Examples

```
>>> import scipy.special as sc
```

They are a scaled version of the Chebyshev polynomials of the first kind.

```
>>> x = np.linspace(-2, 2, 6)
>>> sc.eval_chebyc(3, x)
array([-2.    ,  1.872,  1.136, -1.136, -1.872,  2.    ])
>>> 2 * sc.eval_chebyt(3, x / 2)
array([-2.    ,  1.872,  1.136, -1.136, -1.872,  2.    ])
```


scipy.special.eval_chebys

`scipy.special.eval_chebys(n, x, out=None) = <ufunc 'eval_chebys'>`
 Evaluate Chebyshev polynomial of the second kind on $[-2, 2]$ at a point.

These polynomials are defined as

$$S_n(x) = U_n(x/2)$$

where U_n is a Chebyshev polynomial of the second kind. See 22.5.13 in [AS] for details.

Parameters

- n** [array_like] Degree of the polynomial. If not an integer, the result is determined via the relation to `eval_chebyu`.
- x** [array_like] Points at which to evaluate the Chebyshev polynomial

Returns

- S** [ndarray] Values of the Chebyshev polynomial

See also:

`roots_chebys`

roots and quadrature weights of Chebyshev polynomials of the second kind on $[-2, 2]$

`chebys`

Chebyshev polynomial object

`eval_chebyu`

evaluate Chebyshev polynomials of the second kind

References

[AS]

Examples

```
>>> import scipy.special as sc
```

They are a scaled version of the Chebyshev polynomials of the second kind.

```
>>> x = np.linspace(-2, 2, 6)
>>> sc.eval_chebys(3, x)
array([-4.    ,  0.672,  0.736, -0.736, -0.672,  4.    ])
>>> sc.eval_chebyu(3, x / 2)
array([-4.    ,  0.672,  0.736, -0.736, -0.672,  4.    ])
```

scipy.special.eval_jacobi

`scipy.special.eval_jacobi` (*n*, *alpha*, *beta*, *x*, *out=None*) = <ufunc 'eval_jacobi'>
 Evaluate Jacobi polynomial at a point.

The Jacobi polynomials can be defined via the Gauss hypergeometric function ${}_2F_1$ as

$$P_n^{(\alpha,\beta)}(x) = \frac{(\alpha+1)_n}{\Gamma(n+1)} {}_2F_1(-n, 1+\alpha+\beta+n; \alpha+1; (1-x)/2)$$

where $(\cdot)_n$ is the Pochhammer symbol; see *poch*. When *n* is an integer the result is a polynomial of degree *n*. See 22.5.42 in [AS] for details.

Parameters

n	[array_like] Degree of the polynomial. If not an integer the result is determined via the relation to the Gauss hypergeometric function.
alpha	[array_like] Parameter
beta	[array_like] Parameter
x	[array_like] Points at which to evaluate the polynomial

Returns

P	[ndarray] Values of the Jacobi polynomial
----------	---

See also:

roots_jacobi

roots and quadrature weights of Jacobi polynomials

jacobi

Jacobi polynomial object

hyp2f1

Gauss hypergeometric function

References

[AS]

scipy.special.eval_laguerre

`scipy.special.eval_laguerre` (*n*, *x*, *out=None*) = <ufunc 'eval_laguerre'>
 Evaluate Laguerre polynomial at a point.

The Laguerre polynomials can be defined via the confluent hypergeometric function ${}_1F_1$ as

$$L_n(x) = {}_1F_1(-n, 1, x).$$

See 22.5.16 and 22.5.54 in [AS] for details. When *n* is an integer the result is a polynomial of degree *n*.

Parameters

n	[array_like] Degree of the polynomial. If not an integer the result is determined via the relation to the confluent hypergeometric function.
x	[array_like] Points at which to evaluate the Laguerre polynomial

Returns

L	[ndarray] Values of the Laguerre polynomial
----------	---

See also:***roots_laguerre***

roots and quadrature weights of Laguerre polynomials

laguerre

Laguerre polynomial object

numpy.polynomial.laguerre.Laguerre

Laguerre series

eval_genlaguerre

evaluate generalized Laguerre polynomials

References

[AS]

scipy.special.eval_genlaguerre

`scipy.special.eval_genlaguerre(n, alpha, x, out=None) = <ufunc 'eval_genlaguerre'>`
Evaluate generalized Laguerre polynomial at a point.

The generalized Laguerre polynomials can be defined via the confluent hypergeometric function ${}_1F_1$ as

$$L_n^{(\alpha)}(x) = \binom{n+\alpha}{n} {}_1F_1(-n, \alpha+1, x).$$

When n is an integer the result is a polynomial of degree n . See 22.5.54 in [AS] for details. The Laguerre polynomials are the special case where $\alpha = 0$.

Parameters

- n** [array_like] Degree of the polynomial. If not an integer, the result is determined via the relation to the confluent hypergeometric function.
- alpha** [array_like] Parameter; must have $\alpha > -1$
- x** [array_like] Points at which to evaluate the generalized Laguerre polynomial

Returns

- L** [ndarray] Values of the generalized Laguerre polynomial

See also:***roots_genlaguerre***

roots and quadrature weights of generalized Laguerre polynomials

genlaguerre

generalized Laguerre polynomial object

hyp1f1

confluent hypergeometric function

eval_laguerre

evaluate Laguerre polynomials

References

[AS]

scipy.special.eval_hermite

`scipy.special.eval_hermite(n, x, out=None) = <ufunc 'eval_hermite'>`

Evaluate physicist's Hermite polynomial at a point.

Defined by

$$H_n(x) = (-1)^n e^{x^2} \frac{d^n}{dx^n} e^{-x^2};$$

H_n is a polynomial of degree n . See 22.11.7 in [AS] for details.

Parameters

n [array_like] Degree of the polynomial
x [array_like] Points at which to evaluate the Hermite polynomial

Returns

H [ndarray] Values of the Hermite polynomial

See also:

`roots_hermite`

roots and quadrature weights of physicist's Hermite polynomials

`hermite`

physicist's Hermite polynomial object

`numpy.polynomial.hermite.Hermite`

Physicist's Hermite series

`eval_hermitenorm`

evaluate Probabilist's Hermite polynomials

References

[AS]

scipy.special.eval_hermitenorm

`scipy.special.eval_hermitenorm(n, x, out=None) = <ufunc 'eval_hermitenorm'>`

Evaluate probabilist's (normalized) Hermite polynomial at a point.

Defined by

$$He_n(x) = (-1)^n e^{x^2/2} \frac{d^n}{dx^n} e^{-x^2/2};$$

He_n is a polynomial of degree n . See 22.11.8 in [AS] for details.

Parameters

n [array_like] Degree of the polynomial
x [array_like] Points at which to evaluate the Hermite polynomial

Returns

He [ndarray] Values of the Hermite polynomial

See also:

roots_hermitenorm

roots and quadrature weights of probabilist's Hermite polynomials

hermitenorm

probabilist's Hermite polynomial object

numpy.polynomial.hermite_e.HermiteE

Probabilist's Hermite series

eval_hermite

evaluate physicist's Hermite polynomials

References

[AS]

scipy.special.eval_gegenbauer

`scipy.special.eval_gegenbauer(n, alpha, x, out=None) = <ufunc 'eval_gegenbauer'>`

Evaluate Gegenbauer polynomial at a point.

The Gegenbauer polynomials can be defined via the Gauss hypergeometric function ${}_2F_1$ as

$$C_n^{(\alpha)} = \frac{(2\alpha)_n}{\Gamma(n+1)} {}_2F_1(-n, 2\alpha+n; \alpha+1/2; (1-z)/2).$$

When n is an integer the result is a polynomial of degree n . See 22.5.46 in [AS] for details.

Parameters

n [array_like] Degree of the polynomial. If not an integer, the result is determined via the relation to the Gauss hypergeometric function.

alpha [array_like] Parameter

x [array_like] Points at which to evaluate the Gegenbauer polynomial

Returns

C [ndarray] Values of the Gegenbauer polynomial

See also:

roots_gegenbauer

roots and quadrature weights of Gegenbauer polynomials

gegenbauer

Gegenbauer polynomial object

hyp2f1

Gauss hypergeometric function

References

[AS]

scipy.special.eval_sh_legendre

`scipy.special.eval_sh_legendre(n, x, out=None) = <ufunc 'eval_sh_legendre'>`

Evaluate shifted Legendre polynomial at a point.

These polynomials are defined as

$$P_n^*(x) = P_n(2x - 1)$$

where P_n is a Legendre polynomial. See 2.2.11 in [AS] for details.

Parameters

- n** [array_like] Degree of the polynomial. If not an integer, the value is determined via the relation to `eval_legendre`.
- x** [array_like] Points at which to evaluate the shifted Legendre polynomial

Returns

- P** [ndarray] Values of the shifted Legendre polynomial

See also:

[roots_sh_legendre](#)

roots and quadrature weights of shifted Legendre polynomials

[sh_legendre](#)

shifted Legendre polynomial object

[eval_legendre](#)

evaluate Legendre polynomials

[numpy.polynomial.legendre.Legendre](#)

Legendre series

References

[AS]

scipy.special.eval_sh_chebyt

`scipy.special.eval_sh_chebyt(n, x, out=None) = <ufunc 'eval_sh_chebyt'>`

Evaluate shifted Chebyshev polynomial of the first kind at a point.

These polynomials are defined as

$$T_n^*(x) = T_n(2x - 1)$$

where T_n is a Chebyshev polynomial of the first kind. See 22.5.14 in [AS] for details.

Parameters

- n** [array_like] Degree of the polynomial. If not an integer, the result is determined via the relation to `eval_chebyt`.
- x** [array_like] Points at which to evaluate the shifted Chebyshev polynomial

Returns

T [ndarray] Values of the shifted Chebyshev polynomial

See also:*roots_sh_chebyt*

roots and quadrature weights of shifted Chebyshev polynomials of the first kind

sh_chebyt

shifted Chebyshev polynomial object

eval_chebyt

evaluate Chebyshev polynomials of the first kind

numpy.polynomial.chebyshev.Chebyshev

Chebyshev series

References

[AS]

scipy.special.eval_sh_chebyu

`scipy.special.eval_sh_chebyu(n, x, out=None) = <ufunc 'eval_sh_chebyu'>`

Evaluate shifted Chebyshev polynomial of the second kind at a point.

These polynomials are defined as

$$U_n^*(x) = U_n(2x - 1)$$

where U_n is a Chebyshev polynomial of the first kind. See 22.5.15 in [AS] for details.

Parameters

n [array_like] Degree of the polynomial. If not an integer, the result is determined via the relation to *eval_chebyu*.

x [array_like] Points at which to evaluate the shifted Chebyshev polynomial

Returns

U [ndarray] Values of the shifted Chebyshev polynomial

See also:*roots_sh_chebyu*

roots and quadrature weights of shifted Chebyshev polynomials of the second kind

sh_chebyu

shifted Chebyshev polynomial object

eval_chebyu

evaluate Chebyshev polynomials of the second kind

References

[AS]

scipy.special.eval_sh_jacobi

`scipy.special.eval_sh_jacobi(n, p, q, x, out=None) = <ufunc 'eval_sh_jacobi'>`
 Evaluate shifted Jacobi polynomial at a point.

Defined by

$$G_n^{(p,q)}(x) = \binom{2n+p-1}{n}^{-1} P_n^{(p-q, q-1)}(2x-1),$$

where $P_n^{(\cdot, \cdot)}$ is the n-th Jacobi polynomial. See 22.5.2 in [AS] for details.

Parameters

n [int] Degree of the polynomial. If not an integer, the result is determined via the relation to *binom* and *eval_jacobi*.
p [float] Parameter
q [float] Parameter

Returns

G [ndarray] Values of the shifted Jacobi polynomial.

See also:

roots_sh_jacobi

roots and quadrature weights of shifted Jacobi polynomials

sh_jacobi

shifted Jacobi polynomial object

eval_jacobi

evaluate Jacobi polynomials

References

[AS]

The following functions compute roots and quadrature weights for orthogonal polynomials:

<i>roots_legendre</i> (n[, mu])	Gauss-Legendre quadrature.
<i>roots_chebyt</i> (n[, mu])	Gauss-Chebyshev (first kind) quadrature.
<i>roots_chebyu</i> (n[, mu])	Gauss-Chebyshev (second kind) quadrature.
<i>roots_chebyc</i> (n[, mu])	Gauss-Chebyshev (first kind) quadrature.
<i>roots_chebys</i> (n[, mu])	Gauss-Chebyshev (second kind) quadrature.
<i>roots_jacobi</i> (n, alpha, beta[, mu])	Gauss-Jacobi quadrature.
<i>roots_laguerre</i> (n[, mu])	Gauss-Laguerre quadrature.
<i>roots_genlaguerre</i> (n, alpha[, mu])	Gauss-generalized Laguerre quadrature.
<i>roots_hermite</i> (n[, mu])	Gauss-Hermite (physicist's) quadrature.
<i>roots_hermitenorm</i> (n[, mu])	Gauss-Hermite (statistician's) quadrature.
<i>roots_gegenbauer</i> (n, alpha[, mu])	Gauss-Gegenbauer quadrature.

continues on next page

Table 238 – continued from previous page

<code>roots_sh_legendre(n[, mu])</code>	Gauss-Legendre (shifted) quadrature.
<code>roots_sh_chebyt(n[, mu])</code>	Gauss-Chebyshev (first kind, shifted) quadrature.
<code>roots_sh_chebyu(n[, mu])</code>	Gauss-Chebyshev (second kind, shifted) quadrature.
<code>roots_sh_jacobi(n, p1, q1[, mu])</code>	Gauss-Jacobi (shifted) quadrature.

scipy.special.roots_legendre

`scipy.special.roots_legendre` (*n*, *mu=False*)

Gauss-Legendre quadrature.

Compute the sample points and weights for Gauss-Legendre quadrature. The sample points are the roots of the *n*th degree Legendre polynomial $P_n(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[-1, 1]$ with weight function $w(x) = 1.0$. See 2.2.10 in [AS] for more details.

Parameters

n [int] quadrature order
mu [bool, optional] If True, return the sum of the weights, optional.

Returns

x [ndarray] Sample points
w [ndarray] Weights
mu [float] Sum of the weights

See also:

`scipy.integrate.quadrature`

`scipy.integrate.fixed_quad`

`numpy.polynomial.legendre.leggauss`

References

[AS]

scipy.special.roots_chebyt

`scipy.special.roots_chebyt` (*n*, *mu=False*)

Gauss-Chebyshev (first kind) quadrature.

Computes the sample points and weights for Gauss-Chebyshev quadrature. The sample points are the roots of the *n*th degree Chebyshev polynomial of the first kind, $T_n(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[-1, 1]$ with weight function $w(x) = 1/\sqrt{1 - x^2}$. See 22.2.4 in [AS] for more details.

Parameters

n [int] quadrature order
mu [bool, optional] If True, return the sum of the weights, optional.

Returns

x [ndarray] Sample points
w [ndarray] Weights
mu [float] Sum of the weights

See also:

scipy.integrate.quadrature
scipy.integrate.fixed_quad
numpy.polynomial.chebyshev.chebgauss

References

[AS]

scipy.special.roots_chebyu

`scipy.special.roots_chebyu` (*n*, *mu=False*)

Gauss-Chebyshev (second kind) quadrature.

Computes the sample points and weights for Gauss-Chebyshev quadrature. The sample points are the roots of the *n*th degree Chebyshev polynomial of the second kind, $U_n(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[-1, 1]$ with weight function $w(x) = \sqrt{1 - x^2}$. See 22.2.5 in [AS] for details.

Parameters

n [int] quadrature order
mu [bool, optional] If True, return the sum of the weights, optional.

Returns

x [ndarray] Sample points
w [ndarray] Weights
mu [float] Sum of the weights

See also:

scipy.integrate.quadrature
scipy.integrate.fixed_quad

References

[AS]

scipy.special.roots_chebyc

`scipy.special.roots_chebyc` (*n*, *mu=False*)

Gauss-Chebyshev (first kind) quadrature.

Compute the sample points and weights for Gauss-Chebyshev quadrature. The sample points are the roots of the *n*th degree Chebyshev polynomial of the first kind, $C_n(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[-2, 2]$ with weight function $w(x) = 1/\sqrt{1 - (x/2)^2}$. See 22.2.6 in [AS] for more details.

Parameters

n [int] quadrature order
mu [bool, optional] If True, return the sum of the weights, optional.

Returns

x [ndarray] Sample points
w [ndarray] Weights
mu [float] Sum of the weights

See also:

`scipy.integrate.quadrature`

`scipy.integrate.fixed_quad`

References

[AS]

scipy.special.roots_chebys

`scipy.special.roots_chebys` (*n*, *mu=False*)

Gauss-Chebyshev (second kind) quadrature.

Compute the sample points and weights for Gauss-Chebyshev quadrature. The sample points are the roots of the *n*th degree Chebyshev polynomial of the second kind, $S_n(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[-2, 2]$ with weight function $w(x) = \sqrt{1 - (x/2)^2}$. See 22.2.7 in [AS] for more details.

Parameters

n [int] quadrature order
mu [bool, optional] If True, return the sum of the weights, optional.

Returns

x [ndarray] Sample points
w [ndarray] Weights
mu [float] Sum of the weights

See also:

`scipy.integrate.quadrature`

`scipy.integrate.fixed_quad`

References

[AS]

scipy.special.roots_jacobi

`scipy.special.roots_jacobi` (*n*, *alpha*, *beta*, *mu=False*)

Gauss-Jacobi quadrature.

Compute the sample points and weights for Gauss-Jacobi quadrature. The sample points are the roots of the *n*th degree Jacobi polynomial, $P_n^{\alpha,\beta}(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[-1, 1]$ with weight function $w(x) = (1 - x)^\alpha(1 + x)^\beta$. See 22.2.1 in [AS] for details.

Parameters

n [int] quadrature order
alpha [float] alpha must be > -1
beta [float] beta must be > -1
mu [bool, optional] If True, return the sum of the weights, optional.

Returns

x	[ndarray] Sample points
w	[ndarray] Weights
mu	[float] Sum of the weights

See also:

scipy.integrate.quadrature

scipy.integrate.fixed_quad

References

[AS]

scipy.special.roots_laguerre

`scipy.special.roots_laguerre` (*n*, *mu=False*)
 Gauss-Laguerre quadrature.

Compute the sample points and weights for Gauss-Laguerre quadrature. The sample points are the roots of the *n*th degree Laguerre polynomial, $L_n(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[0, \infty]$ with weight function $w(x) = e^{-x}$. See 22.2.13 in [AS] for details.

Parameters

n	[int] quadrature order
mu	[bool, optional] If True, return the sum of the weights, optional.

Returns

x	[ndarray] Sample points
w	[ndarray] Weights
mu	[float] Sum of the weights

See also:

scipy.integrate.quadrature

scipy.integrate.fixed_quad

numpy.polynomial.laguerre.laggauss

References

[AS]

scipy.special.roots_genlaguerre

`scipy.special.roots_genlaguerre` (*n*, *alpha*, *mu=False*)
 Gauss-generalized Laguerre quadrature.

Compute the sample points and weights for Gauss-generalized Laguerre quadrature. The sample points are the roots of the *n*th degree generalized Laguerre polynomial, $L_n^\alpha(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[0, \infty]$ with weight function $w(x) = x^\alpha e^{-x}$. See 22.3.9 in [AS] for details.

Parameters

n	[int] quadrature order
alpha	[float] alpha must be > -1

mu [bool, optional] If True, return the sum of the weights, optional.

Returns

x [ndarray] Sample points
w [ndarray] Weights
mu [float] Sum of the weights

See also:

[*scipy.integrate.quadrature*](#)

[*scipy.integrate.fixed_quad*](#)

References

[AS]

scipy.special.roots_hermite

`scipy.special.roots_hermite` (*n*, *mu=False*)

Gauss-Hermite (physicist's) quadrature.

Compute the sample points and weights for Gauss-Hermite quadrature. The sample points are the roots of the *n*th degree Hermite polynomial, $H_n(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[-\infty, \infty]$ with weight function $w(x) = e^{-x^2}$. See 22.2.14 in [AS] for details.

Parameters

n [int] quadrature order
mu [bool, optional] If True, return the sum of the weights, optional.

Returns

x [ndarray] Sample points
w [ndarray] Weights
mu [float] Sum of the weights

See also:

[*scipy.integrate.quadrature*](#)

[*scipy.integrate.fixed_quad*](#)

[*numpy.polynomial.hermite.hermgauss*](#)

[*roots_hermitenorm*](#)

Notes

For small *n* up to 150 a modified version of the Golub-Welsch algorithm is used. Nodes are computed from the eigenvalue problem and improved by one step of a Newton iteration. The weights are computed from the well-known analytical formula.

For *n* larger than 150 an optimal asymptotic algorithm is applied which computes nodes and weights in a numerically stable manner. The algorithm has linear runtime making computation for very large *n* (several thousand or more) feasible.

References

[townsend.trogdon.olver-2014], [townsend.trogdon.olver-2015], [AS]

scipy.special.roots_hermitenorm

`scipy.special.roots_hermitenorm` (*n*, *mu=False*)

Gauss-Hermite (statistician's) quadrature.

Compute the sample points and weights for Gauss-Hermite quadrature. The sample points are the roots of the *n*th degree Hermite polynomial, $He_n(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[-\infty, \infty]$ with weight function $w(x) = e^{-x^2/2}$. See 22.2.15 in [AS] for more details.

Parameters

n [int] quadrature order
mu [bool, optional] If True, return the sum of the weights, optional.

Returns

x [ndarray] Sample points
w [ndarray] Weights
mu [float] Sum of the weights

See also:

[*scipy.integrate.quadrature*](#)

[*scipy.integrate.fixed_quad*](#)

[*numpy.polynomial.hermite_e.hermegauss*](#)

Notes

For small *n* up to 150 a modified version of the Golub-Welsch algorithm is used. Nodes are computed from the eigenvalue problem and improved by one step of a Newton iteration. The weights are computed from the well-known analytical formula.

For *n* larger than 150 an optimal asymptotic algorithm is used which computes nodes and weights in a numerical stable manner. The algorithm has linear runtime making computation for very large *n* (several thousand or more) feasible.

References

[AS]

scipy.special.roots_gegenbauer

`scipy.special.roots_gegenbauer` (*n*, *alpha*, *mu=False*)

Gauss-Gegenbauer quadrature.

Compute the sample points and weights for Gauss-Gegenbauer quadrature. The sample points are the roots of the *n*th degree Gegenbauer polynomial, $C_n^\alpha(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[-1, 1]$ with weight function $w(x) = (1 - x^2)^{\alpha-1/2}$. See 22.2.3 in [AS] for more details.

Parameters

n [int] quadrature order
alpha [float] alpha must be > -0.5
mu [bool, optional] If True, return the sum of the weights, optional.

Returns

x [ndarray] Sample points
w [ndarray] Weights
mu [float] Sum of the weights

See also:

scipy.integrate.quadrature

scipy.integrate.fixed_quad

References

[AS]

scipy.special.roots_sh_legendre

`scipy.special.roots_sh_legendre` (*n*, *mu=False*)

Gauss-Legendre (shifted) quadrature.

Compute the sample points and weights for Gauss-Legendre quadrature. The sample points are the roots of the *n*th degree shifted Legendre polynomial $P_n^*(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[0, 1]$ with weight function $w(x) = 1.0$. See 2.2.11 in [AS] for details.

Parameters

n [int] quadrature order
mu [bool, optional] If True, return the sum of the weights, optional.

Returns

x [ndarray] Sample points
w [ndarray] Weights
mu [float] Sum of the weights

See also:

scipy.integrate.quadrature

scipy.integrate.fixed_quad

References

[AS]

scipy.special.roots_sh_chebyt`scipy.special.roots_sh_chebyt` (*n*, *mu=False*)

Gauss-Chebyshev (first kind, shifted) quadrature.

Compute the sample points and weights for Gauss-Chebyshev quadrature. The sample points are the roots of the *n*th degree shifted Chebyshev polynomial of the first kind, $T_n(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[0, 1]$ with weight function $w(x) = 1/\sqrt{x - x^2}$. See 22.2.8 in [AS] for more details.

Parameters

n [int] quadrature order
mu [bool, optional] If True, return the sum of the weights, optional.

Returns

x [ndarray] Sample points
w [ndarray] Weights
mu [float] Sum of the weights

See also:

[*scipy.integrate.quadrature*](#)[*scipy.integrate.fixed_quad*](#)**References**

[AS]

scipy.special.roots_sh_chebyu`scipy.special.roots_sh_chebyu` (*n*, *mu=False*)

Gauss-Chebyshev (second kind, shifted) quadrature.

Computes the sample points and weights for Gauss-Chebyshev quadrature. The sample points are the roots of the *n*th degree shifted Chebyshev polynomial of the second kind, $U_n(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[0, 1]$ with weight function $w(x) = \sqrt{x - x^2}$. See 22.2.9 in [AS] for more details.

Parameters

n [int] quadrature order
mu [bool, optional] If True, return the sum of the weights, optional.

Returns

x [ndarray] Sample points
w [ndarray] Weights
mu [float] Sum of the weights

See also:

[*scipy.integrate.quadrature*](#)[*scipy.integrate.fixed_quad*](#)

References

[AS]

scipy.special.roots_sh_jacobi`scipy.special.roots_sh_jacobi` (*n*, *p1*, *q1*, *mu=False*)

Gauss-Jacobi (shifted) quadrature.

Compute the sample points and weights for Gauss-Jacobi (shifted) quadrature. The sample points are the roots of the *n*th degree shifted Jacobi polynomial, $G_n^{p,q}(x)$. These sample points and weights correctly integrate polynomials of degree $2n - 1$ or less over the interval $[0, 1]$ with weight function $w(x) = (1 - x)^{p-q}x^{q-1}$. See 22.2.2 in [AS] for details.

Parameters

n	[int] quadrature order
p1	[float] (<i>p1</i> - <i>q1</i>) must be > -1
q1	[float] <i>q1</i> must be > 0
mu	[bool, optional] If True, return the sum of the weights, optional.

Returns

x	[ndarray] Sample points
w	[ndarray] Weights
mu	[float] Sum of the weights

See also:

[*scipy.integrate.quadrature*](#)[*scipy.integrate.fixed_quad*](#)

References

[AS]

The functions below, in turn, return the polynomial coefficients in `orthopoly1d` objects, which function similarly as `numpy.poly1d`. The `orthopoly1d` class also has an attribute `weights`, which returns the roots, weights, and total weights for the appropriate form of Gaussian quadrature. These are returned in an $n \times 3$ array with roots in the first column, weights in the second column, and total weights in the final column. Note that `orthopoly1d` objects are converted to `poly1d` when doing arithmetic, and lose information of the original orthogonal polynomial.

<i>legendre</i>(<i>n</i>[, monic])	Legendre polynomial.
<i>chebyt</i>(<i>n</i>[, monic])	Chebyshev polynomial of the first kind.
<i>chebyu</i>(<i>n</i>[, monic])	Chebyshev polynomial of the second kind.
<i>chebyc</i>(<i>n</i>[, monic])	Chebyshev polynomial of the first kind on $[-2, 2]$.
<i>chebys</i>(<i>n</i>[, monic])	Chebyshev polynomial of the second kind on $[-2, 2]$.
<i>jacobi</i>(<i>n</i>, alpha, beta[, monic])	Jacobi polynomial.
<i>laguerre</i>(<i>n</i>[, monic])	Laguerre polynomial.
<i>genlaguerre</i>(<i>n</i>, alpha[, monic])	Generalized (associated) Laguerre polynomial.
<i>hermite</i>(<i>n</i>[, monic])	Physicist's Hermite polynomial.
<i>hermitenorm</i>(<i>n</i>[, monic])	Normalized (probabilist's) Hermite polynomial.
<i>gegenbauer</i>(<i>n</i>, alpha[, monic])	Gegenbauer (ultraspherical) polynomial.
<i>sh_legendre</i>(<i>n</i>[, monic])	Shifted Legendre polynomial.
<i>sh_chebyt</i>(<i>n</i>[, monic])	Shifted Chebyshev polynomial of the first kind.

continues on next page

Table 239 – continued from previous page

<code>sh_chebyu(n[, monic])</code>	Shifted Chebyshev polynomial of the second kind.
<code>sh_jacobi(n, p, q[, monic])</code>	Shifted Jacobi polynomial.

scipy.special.legendre

`scipy.special.legendre` (*n*, *monic=False*)

Legendre polynomial.

Defined to be the solution of

$$\frac{d}{dx} \left[(1 - x^2) \frac{d}{dx} P_n(x) \right] + n(n + 1)P_n(x) = 0;$$

$P_n(x)$ is a polynomial of degree n .

Parameters

- n** [int] Degree of the polynomial.
- monic** [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

- P** [orthopoly1d] Legendre polynomial.

Notes

The polynomials P_n are orthogonal over $[-1, 1]$ with weight function 1.

Examples

Generate the 3rd-order Legendre polynomial $1/2*(5x^3 + 0x^2 - 3x + 0)$:

```
>>> from scipy.special import legendre
>>> legendre(3)
poly1d([ 2.5,  0. , -1.5,  0. ])
```

scipy.special.chebyt

`scipy.special.chebyt` (*n*, *monic=False*)

Chebyshev polynomial of the first kind.

Defined to be the solution of

$$(1 - x^2) \frac{d^2}{dx^2} T_n - x \frac{d}{dx} T_n + n^2 T_n = 0;$$

T_n is a polynomial of degree n .

Parameters

- n** [int] Degree of the polynomial.
- monic** [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

- T** [orthopoly1d] Chebyshev polynomial of the first kind.

See also:

chebyu

Chebyshev polynomial of the second kind.

Notes

The polynomials T_n are orthogonal over $[-1, 1]$ with weight function $(1 - x^2)^{-1/2}$.

scipy.special.chebyu

`scipy.special.chebyu` (*n*, *monic=False*)

Chebyshev polynomial of the second kind.

Defined to be the solution of

$$(1 - x^2) \frac{d^2}{dx^2} U_n - 3x \frac{d}{dx} U_n + n(n + 2) U_n = 0;$$

U_n is a polynomial of degree n .

Parameters

- n** [int] Degree of the polynomial.
monic [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

- U** [orthopoly1d] Chebyshev polynomial of the second kind.

See also:

chebyt

Chebyshev polynomial of the first kind.

Notes

The polynomials U_n are orthogonal over $[-1, 1]$ with weight function $(1 - x^2)^{1/2}$.

scipy.special.chebyc

`scipy.special.chebyc` (*n*, *monic=False*)

Chebyshev polynomial of the first kind on $[-2, 2]$.

Defined as $C_n(x) = 2T_n(x/2)$, where T_n is the n th Chebychev polynomial of the first kind.

Parameters

- n** [int] Degree of the polynomial.
monic [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

- C** [orthopoly1d] Chebyshev polynomial of the first kind on $[-2, 2]$.

See also:

chebyt

Chebyshev polynomial of the first kind.

Notes

The polynomials $C_n(x)$ are orthogonal over $[-2, 2]$ with weight function $1/\sqrt{1 - (x/2)^2}$.

References

[1]

scipy.special.chebys

`scipy.special.chebys` (*n*, *monic=False*)

Chebyshev polynomial of the second kind on $[-2, 2]$.

Defined as $S_n(x) = U_n(x/2)$ where U_n is the *n*th Chebyshev polynomial of the second kind.

Parameters

n [int] Degree of the polynomial.
monic [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

S [orthopoly1d] Chebyshev polynomial of the second kind on $[-2, 2]$.

See also:

chebyu

Chebyshev polynomial of the second kind

Notes

The polynomials $S_n(x)$ are orthogonal over $[-2, 2]$ with weight function $\sqrt{1 - (x/2)^2}$.

References

[1]

scipy.special.jacobi

`scipy.special.jacobi` (*n*, *alpha*, *beta*, *monic=False*)

Jacobi polynomial.

Defined to be the solution of

$$(1 - x^2) \frac{d^2}{dx^2} P_n^{(\alpha, \beta)} + (\beta - \alpha - (\alpha + \beta + 2)x) \frac{d}{dx} P_n^{(\alpha, \beta)} + n(n + \alpha + \beta + 1) P_n^{(\alpha, \beta)} = 0$$

for $\alpha, \beta > -1$; $P_n^{(\alpha, \beta)}$ is a polynomial of degree *n*.

Parameters

n [int] Degree of the polynomial.
alpha [float] Parameter, must be greater than -1.
beta [float] Parameter, must be greater than -1.
monic [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

P [orthopoly1d] Jacobi polynomial.

Notes

For fixed α, β , the polynomials $P_n^{(\alpha, \beta)}$ are orthogonal over $[-1, 1]$ with weight function $(1-x)^\alpha(1+x)^\beta$.

scipy.special.laguerre

`scipy.special.laguerre` (n , *monic=False*)

Laguerre polynomial.

Defined to be the solution of

$$x \frac{d^2}{dx^2} L_n + (1-x) \frac{d}{dx} L_n + n L_n = 0;$$

L_n is a polynomial of degree n .

Parameters

- n** [int] Degree of the polynomial.
monic [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

- L** [orthopoly1d] Laguerre Polynomial.

Notes

The polynomials L_n are orthogonal over $[0, \infty)$ with weight function e^{-x} .

scipy.special.genlaguerre

`scipy.special.genlaguerre` (n , *alpha*, *monic=False*)

Generalized (associated) Laguerre polynomial.

Defined to be the solution of

$$x \frac{d^2}{dx^2} L_n^{(\alpha)} + (\alpha + 1 - x) \frac{d}{dx} L_n^{(\alpha)} + n L_n^{(\alpha)} = 0,$$

where $\alpha > -1$; $L_n^{(\alpha)}$ is a polynomial of degree n .

Parameters

- n** [int] Degree of the polynomial.
alpha [float] Parameter, must be greater than -1.
monic [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

- L** [orthopoly1d] Generalized Laguerre polynomial.

See also:

[laguerre](#)

Laguerre polynomial.

Notes

For fixed α , the polynomials $L_n^{(\alpha)}$ are orthogonal over $[0, \infty)$ with weight function $e^{-x}x^\alpha$.

The Laguerre polynomials are the special case where $\alpha = 0$.

scipy.special.hermite

`scipy.special.hermite` (n , *monic=False*)

Physicist's Hermite polynomial.

Defined by

$$H_n(x) = (-1)^n e^{x^2} \frac{d^n}{dx^n} e^{-x^2};$$

H_n is a polynomial of degree n .

Parameters

- n** [int] Degree of the polynomial.
monic [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

- H** [orthopoly1d] Hermite polynomial.

Notes

The polynomials H_n are orthogonal over $(-\infty, \infty)$ with weight function e^{-x^2} .

scipy.special.hermite norm

`scipy.special.hermite norm` (n , *monic=False*)

Normalized (probabilist's) Hermite polynomial.

Defined by

$$He_n(x) = (-1)^n e^{x^2/2} \frac{d^n}{dx^n} e^{-x^2/2};$$

He_n is a polynomial of degree n .

Parameters

- n** [int] Degree of the polynomial.
monic [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

- He** [orthopoly1d] Hermite polynomial.

Notes

The polynomials He_n are orthogonal over $(-\infty, \infty)$ with weight function $e^{-x^2/2}$.

scipy.special.gegenbauer

`scipy.special.gegenbauer` (n , $alpha$, $monic=False$)

Gegenbauer (ultraspherical) polynomial.

Defined to be the solution of

$$(1 - x^2) \frac{d^2}{dx^2} C_n^{(\alpha)} - (2\alpha + 1)x \frac{d}{dx} C_n^{(\alpha)} + n(n + 2\alpha) C_n^{(\alpha)} = 0$$

for $\alpha > -1/2$; $C_n^{(\alpha)}$ is a polynomial of degree n .

Parameters

- n** [int] Degree of the polynomial.
- monic** [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

- C** [orthopoly1d] Gegenbauer polynomial.

Notes

The polynomials $C_n^{(\alpha)}$ are orthogonal over $[-1, 1]$ with weight function $(1 - x^2)^{(\alpha-1/2)}$.

scipy.special.sh_legendre

`scipy.special.sh_legendre` (n , $monic=False$)

Shifted Legendre polynomial.

Defined as $P_n^*(x) = P_n(2x - 1)$ for P_n the n th Legendre polynomial.

Parameters

- n** [int] Degree of the polynomial.
- monic** [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

- P** [orthopoly1d] Shifted Legendre polynomial.

Notes

The polynomials P_n^* are orthogonal over $[0, 1]$ with weight function 1.

scipy.special.sh_chebyt

`scipy.special.sh_chebyt` (n , $monic=False$)

Shifted Chebyshev polynomial of the first kind.

Defined as $T_n^*(x) = T_n(2x - 1)$ for T_n the n th Chebyshev polynomial of the first kind.

Parameters

- n** [int] Degree of the polynomial.
- monic** [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

T [orthopoly1d] Shifted Chebyshev polynomial of the first kind.

Notes

The polynomials T_n^* are orthogonal over $[0, 1]$ with weight function $(x - x^2)^{-1/2}$.

scipy.special.sh_chebyu

`scipy.special.sh_chebyu` (n , *monic=False*)

Shifted Chebyshev polynomial of the second kind.

Defined as $U_n^*(x) = U_n(2x - 1)$ for U_n the n th Chebyshev polynomial of the second kind.

Parameters

n [int] Degree of the polynomial.
monic [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

U [orthopoly1d] Shifted Chebyshev polynomial of the second kind.

Notes

The polynomials U_n^* are orthogonal over $[0, 1]$ with weight function $(x - x^2)^{1/2}$.

scipy.special.sh_jacobi

`scipy.special.sh_jacobi` (n , p , q , *monic=False*)

Shifted Jacobi polynomial.

Defined by

$$G_n^{(p,q)}(x) = \binom{2n+p-1}{n}^{-1} P_n^{(p-q, q-1)}(2x-1),$$

where $P_n^{(\cdot, \cdot)}$ is the n th Jacobi polynomial.

Parameters

n [int] Degree of the polynomial.
p [float] Parameter, must have $p > q - 1$.
q [float] Parameter, must be greater than 0.
monic [bool, optional] If *True*, scale the leading coefficient to be 1. Default is *False*.

Returns

G [orthopoly1d] Shifted Jacobi polynomial.

Notes

For fixed p, q , the polynomials $G_n^{(p,q)}$ are orthogonal over $[0, 1]$ with weight function $(1 - x)^{p-q}x^{q-1}$.

Warning: Computing values of high-order polynomials (around `order > 20`) using polynomial coefficients is numerically unstable. To evaluate polynomial values, the `eval_*` functions should be used instead.

Hypergeometric functions

<code>hyp2f1(a, b, c, z)</code>	Gauss hypergeometric function ${}_2F_1(a, b; c; z)$
<code>hyp1f1(a, b, x[, out])</code>	Confluent hypergeometric function ${}_1F_1$.
<code>hyperu(a, b, x[, out])</code>	Confluent hypergeometric function U
<code>hyp0f1(v, z[, out])</code>	Confluent hypergeometric limit function ${}_0F_1$.

scipy.special.hyp2f1

`scipy.special.hyp2f1(a, b, c, z) = <ufunc 'hyp2f1'>`
Gauss hypergeometric function ${}_2F_1(a, b; c; z)$

Parameters

a, b, c [array_like] Arguments, should be real-valued.
z [array_like] Argument, real or complex.

Returns

hyp2f1 [scalar or ndarray] The values of the gaussian hypergeometric function.

See also:

`hyp0f1`

confluent hypergeometric limit function.

`hyp1f1`

Kummer's (confluent hypergeometric) function.

Notes

This function is defined for $|z| < 1$ as

$$\text{hyp2f1}(a, b, c, z) = \sum_{n=0}^{\infty} \frac{(a)_n (b)_n}{(c)_n} \frac{z^n}{n!},$$

and defined on the rest of the complex z -plane by analytic continuation [1]. Here $(\cdot)_n$ is the Pochhammer symbol; see `poch`. When n is an integer the result is a polynomial of degree n .

The implementation for complex values of z is described in [2].

References

[1], [2], [3]

Examples

```
>>> import scipy.special as sc
```

It has poles when c is a negative integer.

```
>>> sc.hyp2f1(1, 1, -2, 1)
inf
```

It is a polynomial when a or b is a negative integer.

```
>>> a, b, c = -1, 1, 1.5
>>> z = np.linspace(0, 1, 5)
>>> sc.hyp2f1(a, b, c, z)
array([1.          , 0.83333333, 0.66666667, 0.5          , 0.33333333])
>>> 1 + a * b * z / c
array([1.          , 0.83333333, 0.66666667, 0.5          , 0.33333333])
```

It is symmetric in a and b .

```
>>> a = np.linspace(0, 1, 5)
>>> b = np.linspace(0, 1, 5)
>>> sc.hyp2f1(a, b, 1, 0.5)
array([1.          , 1.03997334, 1.1803406 , 1.47074441, 2.          ])
>>> sc.hyp2f1(b, a, 1, 0.5)
array([1.          , 1.03997334, 1.1803406 , 1.47074441, 2.          ])
```

It contains many other functions as special cases.

```
>>> z = 0.5
>>> sc.hyp2f1(1, 1, 2, z)
1.3862943611198901
>>> -np.log(1 - z) / z
1.3862943611198906
```

```
>>> sc.hyp2f1(0.5, 1, 1.5, z**2)
1.098612288668109
>>> np.log((1 + z) / (1 - z)) / (2 * z)
1.0986122886681098
```

```
>>> sc.hyp2f1(0.5, 1, 1.5, -z**2)
0.9272952180016117
>>> np.arctan(z) / z
0.9272952180016123
```

scipy.special.hyp1f1

`scipy.special.hyp1f1(a, b, x, out=None)` = <ufunc 'hyp1f1'>
 Confluent hypergeometric function 1F1.

The confluent hypergeometric function is defined by the series

$${}_1F_1(a; b; x) = \sum_{k=0}^{\infty} \frac{(a)_k}{(b)_k k!} x^k.$$

See [dlmf] for more details. Here $(\cdot)_k$ is the Pochhammer symbol; see *poch*.

Parameters

a, b [array_like] Real parameters
x [array_like] Real or complex argument
out [ndarray, optional] Optional output array for the function results

Returns

scalar or ndarray
 Values of the confluent hypergeometric function

See also:

hyperu

another confluent hypergeometric function

hyp0f1

confluent hypergeometric limit function

hyp2f1

Gaussian hypergeometric function

References

[dlmf]

Examples

```
>>> import scipy.special as sc
```

It is one when x is zero:

```
>>> sc.hyp1f1(0.5, 0.5, 0)
1.0
```

It is singular when b is a nonpositive integer.

```
>>> sc.hyp1f1(0.5, -1, 0)
inf
```

It is a polynomial when a is a nonpositive integer.

```
>>> a, b, x = -1, 0.5, np.array([1.0, 2.0, 3.0, 4.0])
>>> sc.hyp1f1(a, b, x)
array([-1., -3., -5., -7.])
>>> 1 + (a / b) * x
array([-1., -3., -5., -7.])
```

It reduces to the exponential function when $a = b$.

```
>>> sc.hyp1f1(2, 2, [1, 2, 3, 4])
array([ 2.71828183,  7.3890561 , 20.08553692, 54.59815003])
>>> np.exp([1, 2, 3, 4])
array([ 2.71828183,  7.3890561 , 20.08553692, 54.59815003])
```

scipy.special.hyperu

`scipy.special.hyperu(a, b, x, out=None)` = <ufunc 'hyperu'>
Confluent hypergeometric function U

It is defined as the solution to the equation

$$x \frac{d^2 w}{dx^2} + (b - x) \frac{dw}{dx} - aw = 0$$

which satisfies the property

$$U(a, b, x) \sim x^{-a}$$

as $x \rightarrow \infty$. See [dlmf] for more details.

Parameters

a, b [array_like] Real-valued parameters
x [array_like] Real-valued argument
out [ndarray] Optional output array for the function values

Returns

scalar or ndarray
Values of U

References

[dlmf]

Examples

```
>>> import scipy.special as sc
```

It has a branch cut along the negative x axis.

```
>>> x = np.linspace(-0.1, -10, 5)
>>> sc.hyperu(1, 1, x)
array([nan, nan, nan, nan, nan])
```

It approaches zero as x goes to infinity.

```
>>> x = np.array([1, 10, 100])
>>> sc.hyperu(1, 1, x)
array([0.59634736, 0.09156333, 0.00990194])
```

It satisfies Kummer's transformation.

```
>>> a, b, x = 2, 1, 1
>>> sc.hyperu(a, b, x)
0.1926947246463881
>>> x**(1 - b) * sc.hyperu(a - b + 1, 2 - b, x)
0.1926947246463881
```

scipy.special.hyp0f1

`scipy.special.hyp0f1(v, z, out=None) = <ufunc 'hyp0f1'>`
 Confluent hypergeometric limit function 0F1.

Parameters

v [array_like] Real-valued parameter
z [array_like] Real- or complex-valued argument
out [ndarray, optional] Optional output array for the function results

Returns

scalar or ndarray
 The confluent hypergeometric limit function

Notes

This function is defined as:

$${}_0F_1(v, z) = \sum_{k=0}^{\infty} \frac{z^k}{(v)_k k!}.$$

It's also the limit as $q \rightarrow \infty$ of ${}_1F_1(q; v; z/q)$, and satisfies the differential equation $f''(z) + v f'(z) = f(z)$. See [1] for more information.

References

[1]

Examples

```
>>> import scipy.special as sc
```

It is one when z is zero.

```
>>> sc.hyp0f1(1, 0)
1.0
```

It is the limit of the confluent hypergeometric function as q goes to infinity.

```
>>> q = np.array([1, 10, 100, 1000])
>>> v = 1
>>> z = 1
>>> sc.hyp1f1(q, v, z / q)
array([2.71828183, 2.31481985, 2.28303778, 2.27992985])
>>> sc.hyp0f1(v, z)
2.2795853023360673
```

It is related to Bessel functions.

```
>>> n = 1
>>> x = np.linspace(0, 1, 5)
>>> sc.jv(n, x)
array([0.          , 0.12402598, 0.24226846, 0.3492436 , 0.44005059])
>>> (0.5 * x)**n / sc.factorial(n) * sc.hyp0f1(n + 1, -0.25 * x**2)
array([0.          , 0.12402598, 0.24226846, 0.3492436 , 0.44005059])
```

Parabolic cylinder functions

<code>pbdv(v, x)</code>	Parabolic cylinder function D
<code>pbvv(v, x)</code>	Parabolic cylinder function V
<code>pbwa(a, x)</code>	Parabolic cylinder function W.

scipy.special.pbdv

`scipy.special.pbdv(v, x) = <ufunc 'pbdv'>`
 Parabolic cylinder function D

Returns (d, dp) the parabolic cylinder function $Dv(x)$ in d and the derivative, $Dv'(x)$ in dp.

Returns

d Value of the function
dp Value of the derivative vs x

scipy.special.pbvv

`scipy.special.pbvv(v, x) = <ufunc 'pbvv'>`
 Parabolic cylinder function V

Returns the parabolic cylinder function $Vv(x)$ in v and the derivative, $Vv'(x)$ in vp.

Returns

v Value of the function
vp Value of the derivative vs x

scipy.special.pbwa

`scipy.special.pbwa(a, x) = <ufunc 'pbwa'>`
 Parabolic cylinder function W.

The function is a particular solution to the differential equation

$$y'' + \left(\frac{1}{4}x^2 - a\right)y = 0,$$

for a full definition see section 12.14 in [1].

Parameters

a [array_like] Real parameter
x [array_like] Real argument

Returns

w [scalar or ndarray] Value of the function
wp [scalar or ndarray] Value of the derivative in x

Notes

The function is a wrapper for a Fortran routine by Zhang and Jin [2]. The implementation is accurate only for $|a|, |x| < 5$ and returns NaN outside that range.

References

[1], [2]

These are not universal functions:

<code>pbdv_seq(v, x)</code>	Parabolic cylinder functions $Dv(x)$ and derivatives.
<code>pbvv_seq(v, x)</code>	Parabolic cylinder functions $Vv(x)$ and derivatives.
<code>pbdn_seq(n, z)</code>	Parabolic cylinder functions $Dn(z)$ and derivatives.

scipy.special.pbdv_seq

`scipy.special.pbdv_seq(v, x)`
 Parabolic cylinder functions $Dv(x)$ and derivatives.

Parameters

v [float] Order of the parabolic cylinder function
x [float] Value at which to evaluate the function and derivatives

Returns

dv [ndarray] Values of $D_{vi}(x)$, for $vi=v-int(v), vi=1+v-int(v), \dots, vi=v$.
dp [ndarray] Derivatives $D_{vi}'(x)$, for $vi=v-int(v), vi=1+v-int(v), \dots, vi=v$.

References

[1]

scipy.special.pbvv_seq

`scipy.special.pbvv_seq(v, x)`

Parabolic cylinder functions $V_v(x)$ and derivatives.

Parameters

v [float] Order of the parabolic cylinder function
x [float] Value at which to evaluate the function and derivatives

Returns

dv [ndarray] Values of $V_{v_i}(x)$, for $v_i=v-\text{int}(v)$, $v_i=1+v-\text{int}(v)$, ..., $v_i=v$.
dp [ndarray] Derivatives $V_{v_i}'(x)$, for $v_i=v-\text{int}(v)$, $v_i=1+v-\text{int}(v)$, ..., $v_i=v$.

References

[1]

scipy.special.pbdn_seq

`scipy.special.pbdn_seq(n, z)`

Parabolic cylinder functions $D_n(z)$ and derivatives.

Parameters

n [int] Order of the parabolic cylinder function
z [complex] Value at which to evaluate the function and derivatives

Returns

dv [ndarray] Values of $D_i(z)$, for $i=0, \dots, i=n$.
dp [ndarray] Derivatives $D_i'(z)$, for $i=0, \dots, i=n$.

References

[1]

Mathieu and related functions

<code>mathieu_a(m, q)</code>	Characteristic value of even Mathieu functions
<code>mathieu_b(m, q)</code>	Characteristic value of odd Mathieu functions

scipy.special.mathieu_a

`scipy.special.mathieu_a(m, q) = <ufunc 'mathieu_a'>`
 Characteristic value of even Mathieu functions

Returns the characteristic value for the even solution, $ce_m(z, q)$, of Mathieu's equation.

scipy.special.mathieu_b

`scipy.special.mathieu_b(m, q) = <ufunc 'mathieu_b'>`
 Characteristic value of odd Mathieu functions

Returns the characteristic value for the odd solution, $se_m(z, q)$, of Mathieu's equation.

These are not universal functions:

<code>mathieu_even_coef(m, q)</code>	Fourier coefficients for even Mathieu and modified Mathieu functions.
<code>mathieu_odd_coef(m, q)</code>	Fourier coefficients for even Mathieu and modified Mathieu functions.

scipy.special.mathieu_even_coef

`scipy.special.mathieu_even_coef(m, q)`
 Fourier coefficients for even Mathieu and modified Mathieu functions.

The Fourier series of the even solutions of the Mathieu differential equation are of the form

$$ce_{2n}(z, q) = \sum_{k=0}^{\infty} A_{(2n)}^{(2k)} \cos 2kz$$

$$ce_{2n+1}(z, q) = \sum_{k=0}^{\infty} A_{(2n+1)}^{(2k+1)} \cos(2k+1)z$$

This function returns the coefficients $A_{(2n)}^{(2k)}$ for even input $m=2n$, and the coefficients $A_{(2n+1)}^{(2k+1)}$ for odd input $m=2n+1$.

Parameters

m [int] Order of Mathieu functions. Must be non-negative.
q [float (>=0)] Parameter of Mathieu functions. Must be non-negative.

Returns

Ak [ndarray] Even or odd Fourier coefficients, corresponding to even or odd m .

References

[1], [2]

scipy.special.mathieu_odd_coef

`scipy.special.mathieu_odd_coef(m, q)`

Fourier coefficients for even Mathieu and modified Mathieu functions.

The Fourier series of the odd solutions of the Mathieu differential equation are of the form

$$se_{2n+1}(z, q) = \sum_{k=0}^{\infty} B_{(2n+1)}^{(2k+1)} \sin(2k+1)z$$

$$se_{2n+2}(z, q) = \sum_{k=0}^{\infty} B_{(2n+2)}^{(2k+2)} \sin(2k+2)z$$

This function returns the coefficients $B_{(2n+2)}^{(2k+2)}$ for even input $m=2n+2$, and the coefficients $B_{(2n+1)}^{(2k+1)}$ for odd input $m=2n+1$.

Parameters

- m** [int] Order of Mathieu functions. Must be non-negative.
- q** [float (>=0)] Parameter of Mathieu functions. Must be non-negative.

Returns

- Bk** [ndarray] Even or odd Fourier coefficients, corresponding to even or odd m.

References

[1]

The following return both function and first derivative:

<code>mathieu_cem(m, q, x)</code>	Even Mathieu function and its derivative
<code>mathieu_sem(m, q, x)</code>	Odd Mathieu function and its derivative
<code>mathieu_modcem1(m, q, x)</code>	Even modified Mathieu function of the first kind and its derivative
<code>mathieu_modcem2(m, q, x)</code>	Even modified Mathieu function of the second kind and its derivative
<code>mathieu_modsem1(m, q, x)</code>	Odd modified Mathieu function of the first kind and its derivative
<code>mathieu_modsem2(m, q, x)</code>	Odd modified Mathieu function of the second kind and its derivative

scipy.special.mathieu_cem

`scipy.special.mathieu_cem(m, q, x) = <ufunc 'mathieu_cem'>`

Even Mathieu function and its derivative

Returns the even Mathieu function, $ce_m(x, q)$, of order m and parameter q evaluated at x (given in degrees). Also returns the derivative with respect to x of $ce_m(x, q)$

Parameters

- m** Order of the function
- q** Parameter of the function
- x** Argument of the function, *given in degrees, not radians*

Returns

y	Value of the function
yp	Value of the derivative vs x

scipy.special.mathieu_sem

```
scipy.special.mathieu_sem(m, q, x) = <ufunc 'mathieu_sem'>
```

Odd Mathieu function and its derivative

Returns the odd Mathieu function, $se_m(x, q)$, of order m and parameter q evaluated at x (given in degrees). Also returns the derivative with respect to x of $se_m(x, q)$.

Parameters

m	Order of the function
q	Parameter of the function
x	Argument of the function, <i>given in degrees, not radians.</i>

Returns

y	Value of the function
yp	Value of the derivative vs x

scipy.special.mathieu_modcem1

```
scipy.special.mathieu_modcem1(m, q, x) = <ufunc 'mathieu_modcem1'>
```

Even modified Mathieu function of the first kind and its derivative

Evaluates the even modified Mathieu function of the first kind, $Mc1m(x, q)$, and its derivative at x for order m and parameter q .

Returns

y	Value of the function
yp	Value of the derivative vs x

scipy.special.mathieu_modcem2

```
scipy.special.mathieu_modcem2(m, q, x) = <ufunc 'mathieu_modcem2'>
```

Even modified Mathieu function of the second kind and its derivative

Evaluates the even modified Mathieu function of the second kind, $Mc2m(x, q)$, and its derivative at x (given in degrees) for order m and parameter q .

Returns

y	Value of the function
yp	Value of the derivative vs x

scipy.special.mathieu_modsem1

```
scipy.special.mathieu_modsem1(m, q, x) = <ufunc 'mathieu_modsem1'>
```

Odd modified Mathieu function of the first kind and its derivative

Evaluates the odd modified Mathieu function of the first kind, $Ms1m(x, q)$, and its derivative at x (given in degrees) for order m and parameter q .

Returns

y	Value of the function
yp	Value of the derivative vs x

scipy.special.mathieu_modsem2

`scipy.special.mathieu_modsem2(m, q, x) = <ufunc 'mathieu_modsem2'>`

Odd modified Mathieu function of the second kind and its derivative

Evaluates the odd modified Mathieu function of the second kind, $Ms_{2m}(x, q)$, and its derivative at x (given in degrees) for order m and parameter q .

Returns

y Value of the function
yp Value of the derivative vs x

Spheroidal wave functions

<code>pro_ang1(m, n, c, x)</code>	Prolate spheroidal angular function of the first kind and its derivative
<code>pro_rad1(m, n, c, x)</code>	Prolate spheroidal radial function of the first kind and its derivative
<code>pro_rad2(m, n, c, x)</code>	Prolate spheroidal radial function of the second kind and its derivative
<code>obl_ang1(m, n, c, x)</code>	Oblate spheroidal angular function of the first kind and its derivative
<code>obl_rad1(m, n, c, x)</code>	Oblate spheroidal radial function of the first kind and its derivative
<code>obl_rad2(m, n, c, x)</code>	Oblate spheroidal radial function of the second kind and its derivative.
<code>pro_cv(m, n, c)</code>	Characteristic value of prolate spheroidal function
<code>obl_cv(m, n, c)</code>	Characteristic value of oblate spheroidal function
<code>pro_cv_seq(m, n, c)</code>	Characteristic values for prolate spheroidal wave functions.
<code>obl_cv_seq(m, n, c)</code>	Characteristic values for oblate spheroidal wave functions.

scipy.special.pro_ang1

`scipy.special.pro_ang1(m, n, c, x) = <ufunc 'pro_ang1'>`

Prolate spheroidal angular function of the first kind and its derivative

Computes the prolate spheroidal angular function of the first kind and its derivative (with respect to x) for mode parameters $m \geq 0$ and $n \geq m$, spheroidal parameter c and $|x| < 1.0$.

Returns

s Value of the function
sp Value of the derivative vs x

scipy.special.pro_rad1

`scipy.special.pro_rad1(m, n, c, x) = <ufunc 'pro_rad1'>`

Prolate spheroidal radial function of the first kind and its derivative

Computes the prolate spheroidal radial function of the first kind and its derivative (with respect to x) for mode parameters $m \geq 0$ and $n \geq m$, spheroidal parameter c and $|x| < 1.0$.

Returns

s Value of the function
sp Value of the derivative vs x

scipy.special.pro_rad2

`scipy.special.pro_rad2(m, n, c, x) = <ufunc 'pro_rad2'>`

Prolate spheroidal radial function of the second kind and its derivative

Computes the prolate spheroidal radial function of the second kind and its derivative (with respect to x) for mode parameters $m \geq 0$ and $n \geq m$, spheroidal parameter c and $|x| < 1.0$.

Returns

s	Value of the function
sp	Value of the derivative vs x

scipy.special.obl_ang1

`scipy.special.obl_ang1(m, n, c, x) = <ufunc 'obl_ang1'>`

Oblate spheroidal angular function of the first kind and its derivative

Computes the oblate spheroidal angular function of the first kind and its derivative (with respect to x) for mode parameters $m \geq 0$ and $n \geq m$, spheroidal parameter c and $|x| < 1.0$.

Returns

s	Value of the function
sp	Value of the derivative vs x

scipy.special.obl_rad1

`scipy.special.obl_rad1(m, n, c, x) = <ufunc 'obl_rad1'>`

Oblate spheroidal radial function of the first kind and its derivative

Computes the oblate spheroidal radial function of the first kind and its derivative (with respect to x) for mode parameters $m \geq 0$ and $n \geq m$, spheroidal parameter c and $|x| < 1.0$.

Returns

s	Value of the function
sp	Value of the derivative vs x

scipy.special.obl_rad2

`scipy.special.obl_rad2(m, n, c, x) = <ufunc 'obl_rad2'>`

Oblate spheroidal radial function of the second kind and its derivative.

Computes the oblate spheroidal radial function of the second kind and its derivative (with respect to x) for mode parameters $m \geq 0$ and $n \geq m$, spheroidal parameter c and $|x| < 1.0$.

Returns

s	Value of the function
sp	Value of the derivative vs x

scipy.special.pro_cv

`scipy.special.pro_cv(m, n, c) = <ufunc 'pro_cv'>`

Characteristic value of prolate spheroidal function

Computes the characteristic value of prolate spheroidal wave functions of order m, n ($n \geq m$) and spheroidal parameter c .

scipy.special.obl_cv

`scipy.special.obl_cv(m, n, c) = <ufunc 'obl_cv'>`

Characteristic value of oblate spheroidal function

Computes the characteristic value of oblate spheroidal wave functions of order m, n ($n \geq m$) and spheroidal parameter c .

scipy.special.pro_cv_seq

`scipy.special.pro_cv_seq(m, n, c)`

Characteristic values for prolate spheroidal wave functions.

Compute a sequence of characteristic values for the prolate spheroidal wave functions for mode m and $n'=m..n$ and spheroidal parameter c .

References

[1]

scipy.special.obl_cv_seq

`scipy.special.obl_cv_seq(m, n, c)`

Characteristic values for oblate spheroidal wave functions.

Compute a sequence of characteristic values for the oblate spheroidal wave functions for mode m and $n'=m..n$ and spheroidal parameter c .

References

[1]

The following functions require pre-computed characteristic value:

<code>pro_ang1_cv(m, n, c, cv, x)</code>	Prolate spheroidal angular function <code>pro_ang1</code> for pre-computed characteristic value
<code>pro_rad1_cv(m, n, c, cv, x)</code>	Prolate spheroidal radial function <code>pro_rad1</code> for pre-computed characteristic value
<code>pro_rad2_cv(m, n, c, cv, x)</code>	Prolate spheroidal radial function <code>pro_rad2</code> for pre-computed characteristic value
<code>obl_ang1_cv(m, n, c, cv, x)</code>	Oblate spheroidal angular function <code>obl_ang1</code> for pre-computed characteristic value
<code>obl_rad1_cv(m, n, c, cv, x)</code>	Oblate spheroidal radial function <code>obl_rad1</code> for pre-computed characteristic value
<code>obl_rad2_cv(m, n, c, cv, x)</code>	Oblate spheroidal radial function <code>obl_rad2</code> for pre-computed characteristic value

scipy.special.pro_ang1_cv

`scipy.special.pro_ang1_cv(m, n, c, cv, x) = <ufunc 'pro_ang1_cv'>`

Prolate spheroidal angular function `pro_ang1` for precomputed characteristic value

Computes the prolate spheroidal angular function of the first kind and its derivative (with respect to x) for mode parameters $m \geq 0$ and $n \geq m$, spheroidal parameter c and $|x| < 1.0$. Requires pre-computed characteristic value.

Returns

s	Value of the function
sp	Value of the derivative vs x

scipy.special.pro_rad1_cv

`scipy.special.pro_rad1_cv(m, n, c, cv, x) = <ufunc 'pro_rad1_cv'>`

Prolate spheroidal radial function `pro_rad1` for precomputed characteristic value

Computes the prolate spheroidal radial function of the first kind and its derivative (with respect to x) for mode parameters $m \geq 0$ and $n \geq m$, spheroidal parameter c and $|x| < 1.0$. Requires pre-computed characteristic value.

Returns

s	Value of the function
sp	Value of the derivative vs x

scipy.special.pro_rad2_cv

`scipy.special.pro_rad2_cv(m, n, c, cv, x) = <ufunc 'pro_rad2_cv'>`

Prolate spheroidal radial function `pro_rad2` for precomputed characteristic value

Computes the prolate spheroidal radial function of the second kind and its derivative (with respect to x) for mode parameters $m \geq 0$ and $n \geq m$, spheroidal parameter c and $|x| < 1.0$. Requires pre-computed characteristic value.

Returns

s	Value of the function
sp	Value of the derivative vs x

scipy.special.obl_ang1_cv

`scipy.special.obl_ang1_cv(m, n, c, cv, x) = <ufunc 'obl_ang1_cv'>`

Oblate spheroidal angular function `obl_ang1` for precomputed characteristic value

Computes the oblate spheroidal angular function of the first kind and its derivative (with respect to x) for mode parameters $m \geq 0$ and $n \geq m$, spheroidal parameter c and $|x| < 1.0$. Requires pre-computed characteristic value.

Returns

s	Value of the function
sp	Value of the derivative vs x

scipy.special.obl_rad1_cv

`scipy.special.obl_rad1_cv(m, n, c, cv, x) = <ufunc 'obl_rad1_cv'>`

Oblate spheroidal radial function `obl_rad1` for precomputed characteristic value

Computes the oblate spheroidal radial function of the first kind and its derivative (with respect to x) for mode parameters $m \geq 0$ and $n \geq m$, spheroidal parameter c and $|x| < 1.0$. Requires pre-computed characteristic value.

Returns

s Value of the function
sp Value of the derivative vs x

scipy.special.obl_rad2_cv

`scipy.special.obl_rad2_cv(m, n, c, cv, x) = <ufunc 'obl_rad2_cv'>`

Oblate spheroidal radial function `obl_rad2` for precomputed characteristic value

Computes the oblate spheroidal radial function of the second kind and its derivative (with respect to x) for mode parameters $m \geq 0$ and $n \geq m$, spheroidal parameter c and $|x| < 1.0$. Requires pre-computed characteristic value.

Returns

s Value of the function
sp Value of the derivative vs x

Kelvin functions

<code>kelvin(x)</code>	Kelvin functions as complex numbers
<code>kelvin_zeros(nt)</code>	Compute nt zeros of all Kelvin functions.
<code>ber(x[, out])</code>	Kelvin function <code>ber</code> .
<code>bei(x[, out])</code>	Kelvin function <code>bei</code> .
<code>berp(x[, out])</code>	Derivative of the Kelvin function <code>ber</code> .
<code>beip(x[, out])</code>	Derivative of the Kelvin function <code>bei</code> .
<code>ker(x[, out])</code>	Kelvin function <code>ker</code> .
<code>kei(x[, out])</code>	Kelvin function <code>kei</code> .
<code>kerp(x[, out])</code>	Derivative of the Kelvin function <code>ker</code> .
<code>keip(x[, out])</code>	Derivative of the Kelvin function <code>kei</code> .

scipy.special.kelvin

`scipy.special.kelvin(x) = <ufunc 'kelvin'>`

Kelvin functions as complex numbers

Returns

Be, Ke, Bep, Kep

The tuple (Be, Ke, Bep, Kep) contains complex numbers representing the real and imaginary Kelvin functions and their derivatives evaluated at x . For example, `kelvin(x)[0].real = ber x` and `kelvin(x)[0].imag = bei x` with similar relationships for `ker` and `kei`.

scipy.special.kelvin_zeros

`scipy.special.kelvin_zeros` (*nt*)

Compute *nt* zeros of all Kelvin functions.

Returned in a length-8 tuple of arrays of length *nt*. The tuple contains the arrays of zeros of (ber, bei, ker, kei, ber', bei', ker', kei').

References

[1]

scipy.special.ber

`scipy.special.ber` (*x*, *out=None*) = <ufunc 'ber'>

Kelvin function ber.

Defined as

$$\text{ber}(x) = \Re[J_0(xe^{3\pi i/4})]$$

where J_0 is the Bessel function of the first kind of order zero (see [jv](#)). See [dlmf](#) for more details.

Parameters

x [array_like] Real argument.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
 Values of the Kelvin function.

See also:***bei***

the corresponding real part

berp

the derivative of bei

jv

Bessel function of the first kind

References

[dlmf]

Examples

It can be expressed using Bessel functions.

```
>>> import scipy.special as sc
>>> x = np.array([1.0, 2.0, 3.0, 4.0])
>>> sc.jv(0, x * np.exp(3 * np.pi * 1j / 4)).real
array([ 0.98438178,  0.75173418, -0.22138025, -2.56341656])
>>> sc.ber(x)
array([ 0.98438178,  0.75173418, -0.22138025, -2.56341656])
```

scipy.special.ber

`scipy.special.ber(x, out=None) = <ufunc 'ber'>`
Kelvin function ber.

Defined as

$$\text{ber}(x) = \Im[J_0(xe^{3\pi i/4})]$$

where J_0 is the Bessel function of the first kind of order zero (see [jv](#)). See [dlmf](#) for more details.

Parameters

x [array_like] Real argument.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
Values of the Kelvin function.

See also:

[ber](#)

the corresponding real part

[beip](#)

the derivative of ber

[jv](#)

Bessel function of the first kind

References

[\[dlmf\]](#)

Examples

It can be expressed using Bessel functions.

```
>>> import scipy.special as sc
>>> x = np.array([1.0, 2.0, 3.0, 4.0])
>>> sc.jv(0, x * np.exp(3 * np.pi * 1j / 4)).imag
array([0.24956604, 0.97229163, 1.93758679, 2.29269032])
>>> sc.bei(x)
array([0.24956604, 0.97229163, 1.93758679, 2.29269032])
```

scipy.special.berp

`scipy.special.berp(x, out=None) = <ufunc 'berp'>`

Derivative of the Kelvin function ber.

Parameters

x [array_like] Real argument.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
 The values of the derivative of ber.

See also:

[*ber*](#)

References

[dlmf]

scipy.special.beip

`scipy.special.beip(x, out=None) = <ufunc 'beip'>`

Derivative of the Kelvin function bei.

Parameters

x [array_like] Real argument.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
 The values of the derivative of bei.

See also:

[*bei*](#)

References

[dlmf]

scipy.special.ker

`scipy.special.ker(x, out=None) = <ufunc 'ker'>`

Kelvin function `ker`.

Defined as

$$\text{ker}(x) = \Re[K_0(xe^{\pi i/4})]$$

Where K_0 is the modified Bessel function of the second kind (see [kv](#)). See [dlmf] for more details.

Parameters

x [array_like] Real argument.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
Values of the Kelvin function.

See also:

[kei](#)

the corresponding imaginary part

[kerp](#)

the derivative of `ker`

[kv](#)

modified Bessel function of the second kind

References

[dlmf]

Examples

It can be expressed using the modified Bessel function of the second kind.

```
>>> import scipy.special as sc
>>> x = np.array([1.0, 2.0, 3.0, 4.0])
>>> sc.kv(0, x * np.exp(np.pi * 1j / 4)).real
array([ 0.28670621, -0.04166451, -0.06702923, -0.03617885])
>>> sc.ker(x)
array([ 0.28670621, -0.04166451, -0.06702923, -0.03617885])
```

scipy.special.kei

`scipy.special.kei(x, out=None) = <ufunc 'kei'>`
 Kelvin function kei.

Defined as

$$\text{kei}(x) = \Im[K_0(xe^{\pi i/4})]$$

where K_0 is the modified Bessel function of the second kind (see [kv](#)). See [dlmf](#) for more details.

Parameters

x [array_like] Real argument.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
 Values of the Kelvin function.

See also:

[ker](#)

the corresponding real part

[keip](#)

the derivative of kei

[kv](#)

modified Bessel function of the second kind

References

[dlmf](#)

Examples

It can be expressed using the modified Bessel function of the second kind.

```
>>> import scipy.special as sc
>>> x = np.array([1.0, 2.0, 3.0, 4.0])
>>> sc.kv(0, x * np.exp(np.pi * 1j / 4)).imag
array([-0.49499464, -0.20240007, -0.05112188,  0.0021984 ])
>>> sc.kei(x)
array([-0.49499464, -0.20240007, -0.05112188,  0.0021984 ])
```

scipy.special.kerp

`scipy.special.kerp(x, out=None) = <ufunc 'kerp'>`

Derivative of the Kelvin function ker.

Parameters

x [array_like] Real argument.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
 Values of the derivative of ker.

See also:

[*ker*](#)

References

[dlmf]

scipy.special.keip

`scipy.special.keip(x, out=None) = <ufunc 'keip'>`

Derivative of the Kelvin function kei.

Parameters

x [array_like] Real argument.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
 The values of the derivative of kei.

See also:

[*kei*](#)

References

[dlmf]

These are not universal functions:

<code>ber_zeros(nt)</code>	Compute nt zeros of the Kelvin function ber.
<code>bei_zeros(nt)</code>	Compute nt zeros of the Kelvin function bei.
<code>berp_zeros(nt)</code>	Compute nt zeros of the derivative of the Kelvin function ber.
<code>beip_zeros(nt)</code>	Compute nt zeros of the derivative of the Kelvin function bei.
<code>ker_zeros(nt)</code>	Compute nt zeros of the Kelvin function ker.
<code>kei_zeros(nt)</code>	Compute nt zeros of the Kelvin function kei.

continues on next page

Table 249 – continued from previous page

<code>kerp_zeros(nt)</code>	Compute nt zeros of the derivative of the Kelvin function <code>ker</code> .
<code>keip_zeros(nt)</code>	Compute nt zeros of the derivative of the Kelvin function <code>kei</code> .

scipy.special.ber_zeros`scipy.special.ber_zeros` (nt)Compute nt zeros of the Kelvin function `ber`.*Parameters***nt** [int] Number of zeros to compute. Must be positive.*Returns***ndarray** First nt zeros of the Kelvin function.

See also:

[*ber*](#)**References**

[1]

scipy.special.bei_zeros`scipy.special.bei_zeros` (nt)Compute nt zeros of the Kelvin function `bei`.*Parameters***nt** [int] Number of zeros to compute. Must be positive.*Returns***ndarray** First nt zeros of the Kelvin function.

See also:

[*bei*](#)**References**

[1]

scipy.special.berp_zeros`scipy.special.berp_zeros` (nt)Compute nt zeros of the derivative of the Kelvin function `ber`.*Parameters***nt** [int] Number of zeros to compute. Must be positive.*Returns***ndarray** First nt zeros of the derivative of the Kelvin function.

See also:

ber, berp

References

[1]

scipy.special.beip_zeros

`scipy.special.beip_zeros` (*nt*)

Compute *nt* zeros of the derivative of the Kelvin function *bei*.

Parameters

nt [int] Number of zeros to compute. Must be positive.

Returns

ndarray First *nt* zeros of the derivative of the Kelvin function.

See also:

bei, beip

References

[1]

scipy.special.ker_zeros

`scipy.special.ker_zeros` (*nt*)

Compute *nt* zeros of the Kelvin function *ker*.

Parameters

nt [int] Number of zeros to compute. Must be positive.

Returns

ndarray First *nt* zeros of the Kelvin function.

See also:

ker

References

[1]

scipy.special.kei_zeros`scipy.special.kei_zeros(nt)`Compute nt zeros of the Kelvin function `kei`.**Parameters****nt** [int] Number of zeros to compute. Must be positive.**Returns****ndarray** First nt zeros of the Kelvin function.**See also:**[*kei*](#)**References**

[1]

scipy.special.kerp_zeros`scipy.special.kerp_zeros(nt)`Compute nt zeros of the derivative of the Kelvin function `ker`.**Parameters****nt** [int] Number of zeros to compute. Must be positive.**Returns****ndarray** First nt zeros of the derivative of the Kelvin function.**See also:**[*ker, kerp*](#)**References**

[1]

scipy.special.keip_zeros`scipy.special.keip_zeros(nt)`Compute nt zeros of the derivative of the Kelvin function `kei`.**Parameters****nt** [int] Number of zeros to compute. Must be positive.**Returns****ndarray** First nt zeros of the derivative of the Kelvin function.**See also:**[*kei, keip*](#)

References

[1]

Combinatorics

<code>comb(N, k[, exact, repetition])</code>	The number of combinations of N things taken k at a time.
<code>perm(N, k[, exact])</code>	Permutations of N things taken k at a time, i.e., k-permutations of N.

scipy.special.comb

`scipy.special.comb(N, k, exact=False, repetition=False)`

The number of combinations of N things taken k at a time.

This is often expressed as “N choose k”.

Parameters

- N** [int, ndarray] Number of things.
- k** [int, ndarray] Number of elements taken.
- exact** [bool, optional] If *exact* is False, then floating point precision is used, otherwise exact long integer is computed.
- repetition** [bool, optional] If *repetition* is True, then the number of combinations with repetition is computed.

Returns

- val** [int, float, ndarray] The total number of combinations.

See also:

[binom](#)

Binomial coefficient ufunc

Notes

- Array arguments accepted only for `exact=False` case.
- If $N < 0$, or $k < 0$, then 0 is returned.
- If $k > N$ and `repetition=False`, then 0 is returned.

Examples

```
>>> from scipy.special import comb
>>> k = np.array([3, 4])
>>> n = np.array([10, 10])
>>> comb(n, k, exact=False)
array([ 120.,  210.])
>>> comb(10, 3, exact=True)
120
>>> comb(10, 3, exact=True, repetition=True)
220
```

scipy.special.perm

`scipy.special.perm(N, k, exact=False)`

Permutations of N things taken k at a time, i.e., k -permutations of N .

It's also known as “partial permutations”.

Parameters

N [int, ndarray] Number of things.
k [int, ndarray] Number of elements taken.
exact [bool, optional] If *exact* is False, then floating point precision is used, otherwise exact long integer is computed.

Returns

val [int, ndarray] The number of k -permutations of N .

Notes

- Array arguments accepted only for `exact=False` case.
- If $k > N$, $N < 0$, or $k < 0$, then a 0 is returned.

Examples

```
>>> from scipy.special import perm
>>> k = np.array([3, 4])
>>> n = np.array([10, 10])
>>> perm(n, k)
array([ 720., 5040.])
>>> perm(10, 3, exact=True)
720
```

Lambert W and related functions

`lambertw(z[, k, tol])`

Lambert W function.

`wrightomega(z[, out])`

Wright Omega function.

scipy.special.lambertw

`scipy.special.lambertw(z, k=0, tol=1e-08)`

Lambert W function.

The Lambert W function $W(z)$ is defined as the inverse function of $w * \exp(w)$. In other words, the value of $W(z)$ is such that $z = W(z) * \exp(W(z))$ for any complex number z .

The Lambert W function is a multivalued function with infinitely many branches. Each branch gives a separate solution of the equation $z = w \exp(w)$. Here, the branches are indexed by the integer k .

Parameters

z [array_like] Input argument.
k [int, optional] Branch index.
tol [float, optional] Evaluation tolerance.

Returns

`w` [array] `w` will have the same shape as `z`.

See also:

`wrightomega`

the Wright Omega function

Notes

All branches are supported by `lambertw`:

- `lambertw(z)` gives the principal solution (branch 0)
- `lambertw(z, k)` gives the solution on branch `k`

The Lambert W function has two partially real branches: the principal branch ($k = 0$) is real for real $z > -1/e$, and the $k = -1$ branch is real for $-1/e < z < 0$. All branches except $k = 0$ have a logarithmic singularity at $z = 0$.

Possible issues

The evaluation can become inaccurate very close to the branch point at $-1/e$. In some corner cases, `lambertw` might currently fail to converge, or can end up on the wrong branch.

Algorithm

Halley's iteration is used to invert $w * \exp(w)$, using a first-order asymptotic approximation ($O(\log(w))$ or $O(w)$) as the initial estimate.

The definition, implementation and choice of branches is based on [2].

References

[1], [2]

Examples

The Lambert W function is the inverse of $w \exp(w)$:

```
>>> from scipy.special import lambertw
>>> w = lambertw(1)
>>> w
(0.56714329040978384+0j)
>>> w * np.exp(w)
(1.0+0j)
```

Any branch gives a valid inverse:

```
>>> w = lambertw(1, k=3)
>>> w
(-2.8535817554090377+17.113535539412148j)
>>> w*np.exp(w)
(1.0000000000000002+1.609823385706477e-15j)
```

Applications to equation-solving

The Lambert W function may be used to solve various kinds of equations, such as finding the value of the infinite power tower $z^{z^{z^{\dots}}}$:

```
>>> def tower(z, n):
...     if n == 0:
...         return z
...     return z ** tower(z, n-1)
...
>>> tower(0.5, 100)
0.641185744504986
>>> -lambertw(-np.log(0.5)) / np.log(0.5)
(0.64118574450498589+0j)
```

scipy.special.wrightomega

`scipy.special.wrightomega(z, out=None) = <ufunc 'wrightomega'>`
Wright Omega function.

Defined as the solution to

$$\omega + \log(\omega) = z$$

where \log is the principal branch of the complex logarithm.

Parameters

z [array_like] Points at which to evaluate the Wright Omega function

Returns

omega [ndarray] Values of the Wright Omega function

See also:

lambertw

The Lambert W function

Notes

New in version 0.19.0.

The function can also be defined as

$$\omega(z) = W_{K(z)}(e^z)$$

where $K(z) = \lceil (\Im(z) - \pi)/(2\pi) \rceil$ is the unwinding number and W is the Lambert W function.

The implementation here is taken from [1].

References

[1]

Other special functions

<code>agm(a, b)</code>	Compute the arithmetic-geometric mean of a and b .
<code>bernoulli(n)</code>	Bernoulli numbers $B_0..B_n$ (inclusive).
<code>binom(n, k)</code>	Binomial coefficient
<code>diric(x, n)</code>	Periodic sinc function, also called the Dirichlet function.
<code>euler(n)</code>	Euler numbers $E(0), E(1), \dots, E(n)$.
<code>expn(n, x[, out])</code>	Generalized exponential integral E_n .
<code>exp1(z[, out])</code>	Exponential integral E_1 .
<code>expi(x[, out])</code>	Exponential integral E_i .
<code>factorial(n[, exact])</code>	The factorial of a number or array of numbers.
<code>factorial2(n[, exact])</code>	Double factorial.
<code>factorialk(n, k[, exact])</code>	Multifactorial of n of order k , $n(!\dots!)$.
<code>shichi(x[, out])</code>	Hyperbolic sine and cosine integrals.
<code>sici(x[, out])</code>	Sine and cosine integrals.
<code>softmax(x[, axis])</code>	Softmax function
<code>log_softmax(x[, axis])</code>	Logarithm of softmax function.
<code>spence(z[, out])</code>	Spence's function, also known as the dilogarithm.
<code>zeta(x[, q, out])</code>	Riemann or Hurwitz zeta function.
<code>zetac(x)</code>	Riemann zeta function minus 1.

scipy.special.agm

`scipy.special.agm(a, b) = <ufunc 'agm'>`

Compute the arithmetic-geometric mean of a and b .

Start with $a_0 = a$ and $b_0 = b$ and iteratively compute:

$$\begin{aligned} a_{\{n+1\}} &= (a_n + b_n) / 2 \\ b_{\{n+1\}} &= \text{sqrt}(a_n * b_n) \end{aligned}$$

a_n and b_n converge to the same limit as n increases; their common limit is $\text{agm}(a, b)$.

Parameters

a, b [array_like] Real values only. If the values are both negative, the result is negative. If one value is negative and the other is positive, *nan* is returned.

Returns

float The arithmetic-geometric mean of a and b .

Examples

```
>>> from scipy.special import agm
>>> a, b = 24.0, 6.0
>>> agm(a, b)
13.458171481725614
```

Compare that result to the iteration:

```
>>> while a != b:
...     a, b = (a + b)/2, np.sqrt(a*b)
...     print("a = %19.16f  b=%19.16f" % (a, b))
...
a = 15.000000000000000000  b=12.000000000000000000
a = 13.500000000000000000  b=13.4164078649987388
a = 13.4582039324993694  b=13.4581390309909850
a = 13.4581714817451772  b=13.4581714817060547
a = 13.4581714817256159  b=13.4581714817256159
```

When array-like arguments are given, broadcasting applies:

```
>>> a = np.array([[1.5], [3], [6]]) # a has shape (3, 1).
>>> b = np.array([6, 12, 24, 48]) # b has shape (4,).
>>> agm(a, b)
array([[ 3.36454287,  5.42363427,  9.05798751, 15.53650756],
       [ 4.37037309,  6.72908574, 10.84726853, 18.11597502],
       [ 6.          ,  8.74074619, 13.45817148, 21.69453707]])
```

scipy.special.bernoulli

`scipy.special.bernoulli` (n)
Bernoulli numbers B₀..B_n (inclusive).

References

[1]

scipy.special.binom

`scipy.special.binom` (n, k) = <ufunc 'binom'>
Binomial coefficient

See also:

comb

The number of combinations of N things taken k at a time.

scipy.special.diric`scipy.special.diric(x, n)`

Periodic sinc function, also called the Dirichlet function.

The Dirichlet function is defined as:

$$\text{diric}(x, n) = \frac{\sin(x * n/2)}{(n * \sin(x / 2))},$$
where n is a positive integer.**Parameters**

x [array_like] Input data
n [int] Integer defining the periodicity.

Returns

diric [ndarray]

Examples

```
>>> from scipy import special
>>> import matplotlib.pyplot as plt
```

```
>>> x = np.linspace(-8*np.pi, 8*np.pi, num=201)
>>> plt.figure(figsize=(8, 8));
>>> for idx, n in enumerate([2, 3, 4, 9]):
...     plt.subplot(2, 2, idx+1)
...     plt.plot(x, special.diric(x, n))
...     plt.title('diric, n={}'.format(n))
>>> plt.show()
```

The following example demonstrates that `diric` gives the magnitudes (modulo the sign and scaling) of the Fourier coefficients of a rectangular pulse.

Suppress output of values that are effectively 0:

```
>>> np.set_printoptions(suppress=True)
```


Create a signal x of length m with k ones:

```
>>> m = 8
>>> k = 3
>>> x = np.zeros(m)
>>> x[:k] = 1
```

Use the FFT to compute the Fourier transform of x , and inspect the magnitudes of the coefficients:

```
>>> np.abs(np.fft.fft(x))
array([ 3.          ,  2.41421356,  1.          ,  0.41421356,  1.          ,
        0.41421356,  1.          ,  2.41421356])
```

Now find the same values (up to sign) using `diric`. We multiply by k to account for the different scaling conventions of `numpy.fft.fft` and `diric`:



```
>>> theta = np.linspace(0, 2*np.pi, m, endpoint=False)
>>> k * special.diric(theta, k)
array([ 3.          ,  2.41421356,  1.          , -0.41421356, -1.          ,
        -0.41421356,  1.          ,  2.41421356])
```

scipy.special.euler

scipy.special.euler(*n*)

Euler numbers $E(0), E(1), \dots, E(n)$.

The Euler numbers [1] are also known as the secant numbers.

Because `euler(n)` returns floating point values, it does not give exact values for large n . The first inexact value is $E(22)$.

Parameters

n [int] The highest index of the Euler number to be returned.

Returns

ndarray The Euler numbers $[E(0), E(1), \dots, E(n)]$. The odd Euler numbers, which are all zero, are included.

References

[1], [2]

Examples

```
>>> from scipy.special import euler
>>> euler(6)
array([ 1.,  0., -1.,  0.,  5.,  0., -61.])
```

```
>>> euler(13).astype(np.int64)
array([  1,  0, -1,  0,  5,  0, -61,
        0, 1385,  0, -50521,  0, 2702765,  0])
```

```
>>> euler(22)[-1] # Exact value of E(22) is -69348874393137901.
-69348874393137976.0
```

scipy.special.expn

scipy.special.expn(*n, x, out=None*) = <ufunc 'expn'>

Generalized exponential integral E_n .

For integer $n \geq 0$ and real $x \geq 0$ the generalized exponential integral is defined as [dlmf]

$$E_n(x) = x^{n-1} \int_x^\infty \frac{e^{-t}}{t^n} dt.$$

Parameters

n: array_like
Non-negative integers

x: array_like
Real argument

out: ndarray, optional
Optional output array for the function results

Returns

scalar or ndarray
Values of the generalized exponential integral

See also:***exp1***

special case of E_n for $n = 1$

exp1

related to E_n when $n = 1$

References

[dlmf]

Examples

```
>>> import scipy.special as sc
```

Its domain is nonnegative n and x.

```
>>> sc.expn(-1, 1.0), sc.expn(1, -1.0)
(nan, nan)
```

It has a pole at $x = 0$ for $n = 1, 2$; for larger n it is equal to $1 / (n - 1)$.

```
>>> sc.expn([0, 1, 2, 3, 4], 0)
array([          inf,          inf, 1.          , 0.5          , 0.33333333])
```

For n equal to 0 it reduces to $\exp(-x) / x$.

```
>>> x = np.array([1, 2, 3, 4])
>>> sc.expn(0, x)
array([0.36787944, 0.06766764, 0.01659569, 0.00457891])
>>> np.exp(-x) / x
array([0.36787944, 0.06766764, 0.01659569, 0.00457891])
```

For n equal to 1 it reduces to *exp1*.

```
>>> sc.expn(1, x)
array([0.21938393, 0.04890051, 0.01304838, 0.00377935])
>>> sc.exp1(x)
array([0.21938393, 0.04890051, 0.01304838, 0.00377935])
```

scipy.special.exp1

`scipy.special.exp1(z, out=None)` = <ufunc 'exp1'>
Exponential integral E1.

For complex $z \neq 0$ the exponential integral can be defined as [1]

$$E_1(z) = \int_z^\infty \frac{e^{-t}}{t} dt,$$

where the path of the integral does not cross the negative real axis or pass through the origin.

Parameters

z: array_like
Real or complex argument.
out: ndarray, optional
Optional output array for the function results

Returns

scalar or ndarray
Values of the exponential integral E1

See also:***exp1***

exponential integral Ei

expn

generalization of E_1

Notes

For $x > 0$ it is related to the exponential integral Ei (see *exp1*) via the relation

$$E_1(x) = -Ei(-x).$$

References

[1]

Examples

```
>>> import scipy.special as sc
```

It has a pole at 0.

```
>>> sc.exp1(0)
inf
```

It has a branch cut on the negative real axis.

```
>>> sc.exp1(-1)
nan
>>> sc.exp1(complex(-1, 0))
(-1.8951178163559368-3.141592653589793j)
>>> sc.exp1(complex(-1, -0.0))
(-1.8951178163559368+3.141592653589793j)
```

It approaches 0 along the positive real axis.

```
>>> sc.exp1([1, 10, 100, 1000])
array([2.19383934e-01, 4.15696893e-06, 3.68359776e-46, 0.00000000e+00])
```

It is related to `exp1`.

```
>>> x = np.array([1, 2, 3, 4])
>>> sc.exp1(x)
array([0.21938393, 0.04890051, 0.01304838, 0.00377935])
>>> -sc.exp1(-x)
array([0.21938393, 0.04890051, 0.01304838, 0.00377935])
```

scipy.special.exp1

`scipy.special.exp1(x, out=None) = <ufunc 'exp1'>`
Exponential integral E_1 .

For real x , the exponential integral is defined as [1]

$$E_1(x) = \int_{-\infty}^x \frac{e^t}{t} dt.$$

For $x > 0$ the integral is understood as a Cauchy principle value.

It is extended to the complex plane by analytic continuation of the function on the interval $(0, \infty)$. The complex variant has a branch cut on the negative real axis.

Parameters

- x: array_like**
Real or complex valued argument
- out: ndarray, optional**
Optional output array for the function results

Returns

- scalar or ndarray**
Values of the exponential integral

See also:

`exp1`

Exponential integral E_1

`expn`

Generalized exponential integral E_n

Notes

The exponential integrals E_1 and Ei satisfy the relation

$$E_1(x) = -Ei(-x)$$

for $x > 0$.

References

[1]

Examples

```
>>> import scipy.special as sc
```

It is related to `exp1`.

```
>>> x = np.array([1, 2, 3, 4])
>>> -sc.expi(-x)
array([0.21938393, 0.04890051, 0.01304838, 0.00377935])
>>> sc.exp1(x)
array([0.21938393, 0.04890051, 0.01304838, 0.00377935])
```

The complex variant has a branch cut on the negative real axis.

```
>>> import scipy.special as sc
>>> sc.expi(-1 + 1e-12j)
(-0.21938393439552062+3.1415926535894254j)
>>> sc.expi(-1 - 1e-12j)
(-0.21938393439552062-3.1415926535894254j)
```

As the complex variant approaches the branch cut, the real parts approach the value of the real variant.

```
>>> sc.expi(-1)
-0.21938393439552062
```

The SciPy implementation returns the real variant for complex values on the branch cut.

```
>>> sc.expi(complex(-1, 0.0))
(-0.21938393439552062-0j)
>>> sc.expi(complex(-1, -0.0))
(-0.21938393439552062-0j)
```

scipy.special.factorial`scipy.special.factorial` (*n*, *exact=False*)

The factorial of a number or array of numbers.

The factorial of non-negative integer *n* is the product of all positive integers less than or equal to *n*:

$$n! = n * (n - 1) * (n - 2) * \dots * 1$$

Parameters

- n** [int or array_like of ints] Input values. If $n < 0$, the return value is 0.
- exact** [bool, optional] If True, calculate the answer exactly using long integer arithmetic. If False, result is approximated in floating point rapidly using the `gamma` function. Default is False.

Returns

- nf** [float or int or ndarray] Factorial of *n*, as integer or float depending on *exact*.

Notes

For arrays with `exact=True`, the factorial is computed only once, for the largest input, with each other result computed in the process. The output dtype is increased to `int64` or `object` if necessary.

With `exact=False` the factorial is approximated using the gamma function:

$$n! = \Gamma(n + 1)$$

Examples

```
>>> from scipy.special import factorial
>>> arr = np.array([3, 4, 5])
>>> factorial(arr, exact=False)
array([ 6., 24., 120.])
>>> factorial(arr, exact=True)
array([ 6, 24, 120])
>>> factorial(5, exact=True)
120
```

scipy.special.factorial2`scipy.special.factorial2` (*n*, *exact=False*)

Double factorial.

This is the factorial with every second value skipped. E.g., $7!! = 7 * 5 * 3 * 1$. It can be approximated numerically as:

$$\begin{aligned} n!! &= \text{special.gamma}(n/2+1) * 2^{**((m+1)/2)} / \text{sqrt}(\text{pi}) & n \text{ odd} \\ &= 2^{**(n/2)} * (n/2)! & n \text{ even} \end{aligned}$$

Parameters

- n** [int or array_like] Calculate $n!!$. Arrays are only supported with *exact* set to False. If $n < 0$, the return value is 0.
- exact** [bool, optional] The result can be approximated rapidly using the gamma-formula above (default). If *exact* is set to True, calculate the answer exactly using integer arithmetic.

Returns

nff [float or int] Double factorial of n , as an int or a float depending on *exact*.

Examples

```
>>> from scipy.special import factorial2
>>> factorial2(7, exact=False)
array(105.00000000000001)
>>> factorial2(7, exact=True)
105
```

scipy.special.factorialk

`scipy.special.factorialk` ($n, k, exact=True$)

Multifactorial of n of order k , $n(!!\dots!)$.

This is the multifactorial of n skipping k values. For example,

$$\text{factorialk}(17, 4) = 17!!!! = 17 * 13 * 9 * 5 * 1$$

In particular, for any integer n , we have

$$\text{factorialk}(n, 1) = \text{factorial}(n)$$

$$\text{factorialk}(n, 2) = \text{factorial2}(n)$$

Parameters

n [int] Calculate multifactorial. If $n < 0$, the return value is 0.
k [int] Order of multifactorial.
exact [bool, optional] If *exact* is set to `True`, calculate the answer exactly using integer arithmetic.

Returns

val [int] Multifactorial of n .

Raises

NotImplementedError
Raises when *exact* is `False`

Examples

```
>>> from scipy.special import factorialk
>>> factorialk(5, 1, exact=True)
120
>>> factorialk(5, 3, exact=True)
10
```


scipy.special.shichi

`scipy.special.shichi(x, out=None) = <ufunc 'shichi'>`
 Hyperbolic sine and cosine integrals.

The hyperbolic sine integral is

$$\int_0^x \frac{\sinh t}{t} dt$$

and the hyperbolic cosine integral is

$$\gamma + \log(x) + \int_0^x \frac{\cosh t - 1}{t} dt$$

where γ is Euler's constant and \log is the principle branch of the logarithm.

Parameters

x [array_like] Real or complex points at which to compute the hyperbolic sine and cosine integrals.

Returns

si [ndarray] Hyperbolic sine integral at x
ci [ndarray] Hyperbolic cosine integral at x

Notes

For real arguments with $x < 0$, `chi` is the real part of the hyperbolic cosine integral. For such points `chi(x)` and `chi(x + 0j)` differ by a factor of $1j\pi$.

For real arguments the function is computed by calling Cephes' [1] *shichi* routine. For complex arguments the algorithm is based on Mpmath's [2] *shi* and *chi* routines.

References

[1], [2]

scipy.special.sici

`scipy.special.sici(x, out=None) = <ufunc 'sici'>`
 Sine and cosine integrals.

The sine integral is

$$\int_0^x \frac{\sin t}{t} dt$$

and the cosine integral is

$$\gamma + \log(x) + \int_0^x \frac{\cos t - 1}{t} dt$$

where γ is Euler's constant and \log is the principle branch of the logarithm.

Parameters

x [array_like] Real or complex points at which to compute the sine and cosine integrals.

Returns

si [ndarray] Sine integral at x
ci [ndarray] Cosine integral at x

Notes

For real arguments with $x < 0$, `ci` is the real part of the cosine integral. For such points `ci(x)` and `ci(x + 0j)` differ by a factor of $1j\pi$.

For real arguments the function is computed by calling Cephes' [1] `sici` routine. For complex arguments the algorithm is based on Mpmath's [2] `si` and `ci` routines.

References

[1], [2]

scipy.special.softmax

`scipy.special.softmax(x, axis=None)`

Softmax function

The softmax function transforms each element of a collection by computing the exponential of each element divided by the sum of the exponentials of all the elements. That is, if `x` is a one-dimensional numpy array:

```
softmax(x) = np.exp(x) / sum(np.exp(x))
```

Parameters

x	[array_like] Input array.
axis	[int or tuple of ints, optional] Axis to compute values along. Default is None and softmax will be computed over the entire array <code>x</code> .

Returns

s	[ndarray] An array the same shape as <code>x</code> . The result will sum to 1 along the specified axis.
----------	--

Notes

The formula for the softmax function $\sigma(x)$ for a vector $x = \{x_0, x_1, \dots, x_{n-1}\}$ is

$$\sigma(x)_j = \frac{e^{x_j}}{\sum_k e^{x_k}}$$

The `softmax` function is the gradient of `logsumexp`.

New in version 1.2.0.

Examples

```
>>> from scipy.special import softmax
>>> np.set_printoptions(precision=5)
```

```
>>> x = np.array([[1, 0.5, 0.2, 3],
...              [1, -1, 7, 3],
...              [2, 12, 13, 3]])
...
...
...
...
```

Compute the softmax transformation over the entire array.

```
>>> m = softmax(x)
>>> m
array([[ 4.48309e-06,  2.71913e-06,  2.01438e-06,  3.31258e-05],
       [ 4.48309e-06,  6.06720e-07,  1.80861e-03,  3.31258e-05],
       [ 1.21863e-05,  2.68421e-01,  7.29644e-01,  3.31258e-05]])
```

```
>>> m.sum()
1.00000000000000002
```

Compute the softmax transformation along the first axis (i.e., the columns).

```
>>> m = softmax(x, axis=0)
```

```
>>> m
array([[ 2.11942e-01,  1.01300e-05,  2.75394e-06,  3.33333e-01],
       [ 2.11942e-01,  2.26030e-06,  2.47262e-03,  3.33333e-01],
       [ 5.76117e-01,  9.99988e-01,  9.97525e-01,  3.33333e-01]])
```

```
>>> m.sum(axis=0)
array([ 1.,  1.,  1.,  1.])
```

Compute the softmax transformation along the second axis (i.e., the rows).

```
>>> m = softmax(x, axis=1)
>>> m
array([[ 1.05877e-01,  6.42177e-02,  4.75736e-02,  7.82332e-01],
       [ 2.42746e-03,  3.28521e-04,  9.79307e-01,  1.79366e-02],
       [ 1.22094e-05,  2.68929e-01,  7.31025e-01,  3.31885e-05]])
```

```
>>> m.sum(axis=1)
array([ 1.,  1.,  1.])
```

scipy.special.log_softmax

`scipy.special.log_softmax(x, axis=None)`

Logarithm of softmax function:

```
log_softmax(x) = log(softmax(x))
```

Parameters

- x** [array_like] Input array.
- axis** [int or tuple of ints, optional] Axis to compute values along. Default is None and softmax will be computed over the entire array *x*.

Returns

- s** [ndarray or scalar] An array with the same shape as *x*. Exponential of the result will sum to 1 along the specified axis. If *x* is a scalar, a scalar is returned.

Notes

`log_softmax` is more accurate than `np.log(softmax(x))` with inputs that make `softmax` saturate (see examples below).

New in version 1.5.0.

Examples

```
>>> from scipy.special import log_softmax
>>> from scipy.special import softmax
>>> np.set_printoptions(precision=5)
```

```
>>> x = np.array([1000.0, 1.0])
```

```
>>> y = log_softmax(x)
>>> y
array([ 0., -999.] )
```

```
>>> with np.errstate(divide='ignore') :
...     y = np.log(softmax(x))
...
>>> y
array([ 0., -inf])
```

scipy.special.spence

`scipy.special.spence(z, out=None) = <ufunc 'spence'>`

Spence's function, also known as the dilogarithm.

It is defined to be

$$\int_0^z \frac{\log(t)}{1-t} dt$$

for complex z , where the contour of integration is taken to avoid the branch cut of the logarithm. Spence's function is analytic everywhere except the negative real axis where it has a branch cut.

Parameters

z [array_like] Points at which to evaluate Spence's function

Returns

s [ndarray] Computed values of Spence's function

Notes

There is a different convention which defines Spence's function by the integral

$$-\int_0^z \frac{\log(1-t)}{t} dt;$$

this is our `spence(1 - z)`.

scipy.special.zeta

`scipy.special.zeta` (*x*, *q=None*, *out=None*)

Riemann or Hurwitz zeta function.

Parameters

x [array_like of float] Input data, must be real
q [array_like of float, optional] Input data, must be real. Defaults to Riemann zeta.
out [ndarray, optional] Output array for the computed values.

Returns

out [array_like] Values of zeta(x).

See also:

[*zetac*](#)

Notes

The two-argument version is the Hurwitz zeta function

$$\zeta(x, q) = \sum_{k=0}^{\infty} \frac{1}{(k+q)^x};$$

see [dlmf] for details. The Riemann zeta function corresponds to the case when $q = 1$.

References

[dlmf]

Examples

```
>>> from scipy.special import zeta, polygamma, factorial
```

Some specific values:

```
>>> zeta(2), np.pi**2/6
(1.6449340668482266, 1.6449340668482264)
```

```
>>> zeta(4), np.pi**4/90
(1.0823232337111381, 1.082323233711138)
```

Relation to the *polygamma* function:

```
>>> m = 3
>>> x = 1.25
>>> polygamma(m, x)
array(2.782144009188397)
>>> (-1)**(m+1) * factorial(m) * zeta(m+1, x)
2.7821440091883969
```

scipy.special.zetac

`scipy.special.zetac(x)` = <ufunc 'zetac'>
Riemann zeta function minus 1.

This function is defined as

$$\zeta(x) = \sum_{k=2}^{\infty} 1/k^x,$$

where $x > 1$. For $x < 1$ the analytic continuation is computed. For more information on the Riemann zeta function, see [dlmf].

Parameters

x [array_like of float] Values at which to compute $\zeta(x) - 1$ (must be real).

Returns

out [array_like] Values of $\zeta(x) - 1$.

See also:

[zeta](#)

References

[dlmf]

Examples

```
>>> from scipy.special import zetac, zeta
```

Some special values:

```
>>> zetac(2), np.pi**2/6 - 1
(0.64493406684822641, 0.6449340668482264)
```

```
>>> zetac(-1), -1.0/12 - 1
(-1.0833333333333333, -1.0833333333333333)
```

Compare `zetac(x)` to `zeta(x) - 1` for large x :

```
>>> zetac(60), zeta(60) - 1
(8.673617380119933e-19, 0.0)
```

Convenience functions

<code>cbrt(x)</code>	Element-wise cube root of x .
<code>exp10(x)</code>	Compute 10^{**x} element-wise.
<code>exp2(x)</code>	Compute 2^{**x} element-wise.
<code>radian(d, m, s[, out])</code>	Convert from degrees to radians.
<code>cosdg(x[, out])</code>	Cosine of the angle x given in degrees.
<code>sindg(x[, out])</code>	Sine of the angle x given in degrees.
<code>tandg(x[, out])</code>	Tangent of angle x given in degrees.
<code>cotdg(x[, out])</code>	Cotangent of the angle x given in degrees.
<code>log1p(x[, out])</code>	Calculates $\log(1 + x)$ for use when x is near zero.
<code>expm1(x)</code>	Compute $\exp(x) - 1$.
<code>cosm1(x[, out])</code>	$\cos(x) - 1$ for use when x is near zero.
<code>round(x[, out])</code>	Round to the nearest integer.
<code>xlogy(x, y)</code>	Compute $x \cdot \log(y)$ so that the result is 0 if $x = 0$.
<code>xlog1py(x, y)</code>	Compute $x \cdot \log_{1p}(y)$ so that the result is 0 if $x = 0$.
<code>logsumexp(a[, axis, b, keepdims, return_sign])</code>	Compute the log of the sum of exponentials of input elements.
<code>exprel(x)</code>	Relative error exponential, $(\exp(x) - 1) / x$.
<code>sinc(x)</code>	Return the sinc function.

scipy.special.cbirt

`scipy.special.cbirt(x) = <ufunc 'cbirt'>`
Element-wise cube root of x .

Parameters

x [array_like] x must contain real numbers.

Returns

float The cube root of each value in x .

Examples

```
>>> from scipy.special import cbirt
```

```
>>> cbirt(8)
2.0
>>> cbirt([-8, -3, 0.125, 1.331])
array([-2.          , -1.44224957,  0.5          ,  1.1          ])
```

scipy.special.exp10

`scipy.special.exp10(x) = <ufunc 'exp10'>`
Compute 10^{**x} element-wise.

Parameters

x [array_like] x must contain real numbers.

Returns

float 10^{**x} , computed element-wise.

Examples

```
>>> from scipy.special import exp10
```

```
>>> exp10(3)
1000.0
>>> x = np.array([[ -1, -0.5, 0], [0.5, 1, 1.5]])
>>> exp10(x)
array([[ 0.1          ,  0.31622777,  1.          ],
       [ 3.16227766, 10.          , 31.6227766 ]])
```

scipy.special.exp2

`scipy.special.exp2(x) = <ufunc 'exp2'>`

Compute 2^{**x} element-wise.

Parameters

x [array_like] x must contain real numbers.

Returns

float 2^{**x} , computed element-wise.

Examples

```
>>> from scipy.special import exp2
```

```
>>> exp2(3)
8.0
>>> x = np.array([[ -1, -0.5, 0], [0.5, 1, 1.5]])
>>> exp2(x)
array([[ 0.5          ,  0.70710678,  1.          ],
       [ 1.41421356,  2.          ,  2.82842712]])
```

scipy.special.radians

`scipy.special.radians(d, m, s, out=None) = <ufunc 'radians'>`

Convert from degrees to radians.

Returns the angle given in (d)egrees, (m)inutes, and (s)econds in radians.

Parameters

d [array_like] Degrees, can be real-valued.
m [array_like] Minutes, can be real-valued.
s [array_like] Seconds, can be real-valued.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
 Values of the inputs in radians.

Examples

```
>>> import scipy.special as sc
```

There are many ways to specify an angle.

```
>>> sc.radian(90, 0, 0)
1.5707963267948966
>>> sc.radian(0, 60 * 90, 0)
1.5707963267948966
>>> sc.radian(0, 0, 60**2 * 90)
1.5707963267948966
```

The inputs can be real-valued.

```
>>> sc.radian(1.5, 0, 0)
0.02617993877991494
>>> sc.radian(1, 30, 0)
0.02617993877991494
```

scipy.special.cosdg

`scipy.special.cosdg(x, out=None) = <ufunc 'cosdg'>`

Cosine of the angle x given in degrees.

Parameters

x [array_like] Angle, given in degrees.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
 Cosine of the input.

See also:

[*sindg*](#), [*tandg*](#), [*cotdg*](#)

Examples

```
>>> import scipy.special as sc
```

It is more accurate than using cosine directly.

```
>>> x = 90 + 180 * np.arange(3)
>>> sc.cosdg(x)
array([-0.,  0., -0.])
>>> np.cos(x * np.pi / 180)
array([ 6.1232340e-17, -1.8369702e-16,  3.0616170e-16])
```

scipy.special.sindg

`scipy.special.sindg(x, out=None) = <ufunc 'sindg'>`
Sine of the angle x given in degrees.

Parameters

x [array_like] Angle, given in degrees.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
Sine at the input.

See also:

cosdg, tandg, cotdg

Examples

```
>>> import scipy.special as sc
```

It is more accurate than using sine directly.

```
>>> x = 180 * np.arange(3)
>>> sc.sindg(x)
array([ 0., -0.,  0.])
>>> np.sin(x * np.pi / 180)
array([ 0.0000000e+00,  1.2246468e-16, -2.4492936e-16])
```

scipy.special.tandg

`scipy.special.tandg(x, out=None) = <ufunc 'tandg'>`
Tangent of angle x given in degrees.

Parameters

x [array_like] Angle, given in degrees.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
Tangent at the input.

See also:

sindg, cosdg, cotdg

Examples

```
>>> import scipy.special as sc
```

It is more accurate than using tangent directly.

```
>>> x = 180 * np.arange(3)
>>> sc.tandg(x)
array([0., 0., 0.])
>>> np.tan(x * np.pi / 180)
array([ 0.0000000e+00, -1.2246468e-16, -2.4492936e-16])
```

scipy.special.cotdg

`scipy.special.cotdg(x, out=None) = <ufunc 'cotdg'>`

Cotangent of the angle x given in degrees.

Parameters

x [array_like] Angle, given in degrees.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
 Cotangent at the input.

See also:

[*sindg*](#), [*cosdg*](#), [*tandg*](#)

Examples

```
>>> import scipy.special as sc
```

It is more accurate than using cotangent directly.

```
>>> x = 90 + 180 * np.arange(3)
>>> sc.cotdg(x)
array([0., 0., 0.])
>>> 1 / np.tan(x * np.pi / 180)
array([6.1232340e-17, 1.8369702e-16, 3.0616170e-16])
```

scipy.special.log1p

`scipy.special.log1p(x, out=None) = <ufunc 'log1p'>`

Calculates $\log(1 + x)$ for use when x is near zero.

Parameters

x [array_like] Real or complex valued input.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
 Values of $\log(1 + x)$.

See also:

`expm1`, `cosm1`

Examples

```
>>> import scipy.special as sc
```

It is more accurate than using $\log(1 + x)$ directly for x near 0. Note that in the below example $1 + 1e-17 == 1$ to double precision.

```
>>> sc.log1p(1e-17)
1e-17
>>> np.log(1 + 1e-17)
0.0
```

scipy.special.expm1

`scipy.special.expm1(x) = <ufunc 'expm1'>`
 Compute $\exp(x) - 1$.

When x is near zero, $\exp(x)$ is near 1, so the numerical calculation of $\exp(x) - 1$ can suffer from catastrophic loss of precision. `expm1(x)` is implemented to avoid the loss of precision that occurs when x is near zero.

Parameters

x [array_like] x must contain real numbers.

Returns

float $\exp(x) - 1$ computed element-wise.

Examples

```
>>> from scipy.special import expm1
```

```
>>> expm1(1.0)
1.7182818284590451
>>> expm1([-0.2, -0.1, 0, 0.1, 0.2])
array([-0.18126925, -0.09516258, 0.          , 0.10517092, 0.22140276])
```

The exact value of $\exp(7.5e-13) - 1$ is:

```
7.5000000000028125000000007031250000001318...*10**-13.
```

Here is what `expm1(7.5e-13)` gives:

```
>>> expm1(7.5e-13)
7.5000000000028135e-13
```

Compare that to $\exp(7.5e-13) - 1$, where the subtraction results in a “catastrophic” loss of precision:

```
>>> np.exp(7.5e-13) - 1
7.5006667543675576e-13
```

scipy.special.cosm1

`scipy.special.cosm1(x, out=None) = <ufunc 'cosm1'>`
`cos(x) - 1` for use when x is near zero.

Parameters

x [array_like] Real valued argument.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
 Values of $\cos(x) - 1$.

See also:

[*expm1, log1p*](#)

Examples

```
>>> import scipy.special as sc
```

It is more accurate than computing $\cos(x) - 1$ directly for x around 0.

```
>>> x = 1e-30
>>> np.cos(x) - 1
0.0
>>> sc.cosm1(x)
-5.0000000000000005e-61
```

scipy.special.round

`scipy.special.round(x, out=None) = <ufunc 'round'>`
 Round to the nearest integer.

Returns the nearest integer to x . If x ends in 0.5 exactly, the nearest even integer is chosen.

Parameters

x [array_like] Real valued input.
out [ndarray, optional] Optional output array for the function results.

Returns

scalar or ndarray
 The nearest integers to the elements of x . The result is of floating type, not integer type.

Examples

```
>>> import scipy.special as sc
```

It rounds to even.

```
>>> sc.round([0.5, 1.5])
array([0., 2.])
```

scipy.special.xlogy

`scipy.special.xlogy(x, y) = <ufunc 'xlogy'>`
 Compute $x \cdot \log(y)$ so that the result is 0 if $x = 0$.

Parameters

x [array_like] Multiplier
y [array_like] Argument

Returns

z [array_like] Computed $x \cdot \log(y)$

Notes

New in version 0.13.0.

scipy.special.xlog1py

`scipy.special.xlog1py(x, y) = <ufunc 'xlog1py'>`
 Compute $x \cdot \log_1p(y)$ so that the result is 0 if $x = 0$.

Parameters

x [array_like] Multiplier
y [array_like] Argument

Returns

z [array_like] Computed $x \cdot \log_1p(y)$

Notes

New in version 0.13.0.

scipy.special.logsumexp

`scipy.special.logsumexp(a, axis=None, b=None, keepdims=False, return_sign=False)`
 Compute the log of the sum of exponentials of input elements.

Parameters

a [array_like] Input array.
axis [None or int or tuple of ints, optional] Axis or axes over which the sum is taken. By default *axis* is None, and all elements are summed.
 New in version 0.11.0.
keepdims [bool, optional] If this is set to True, the axes which are reduced are left in the result as dimensions with size one. With this option, the result will broadcast correctly against the original array.
 New in version 0.15.0.
b [array-like, optional] Scaling factor for $\exp(a)$ must be of the same shape as *a* or broadcastable to *a*. These values may be negative in order to implement subtraction.
 New in version 0.12.0.
return_sign [bool, optional] If this is set to True, the result will be a pair containing sign information; if False, results that are negative will be returned as NaN. Default is False (no sign information).
 New in version 0.16.0.

Returns

res [ndarray] The result, `np.log(np.sum(np.exp(a)))` calculated in a numerically more stable way. If *b* is given then `np.log(np.sum(b*np.exp(a)))` is returned.

sgn [ndarray] If `return_sign` is `True`, this will be an array of floating-point numbers matching `res` and `+1`, `0`, or `-1` depending on the sign of the result. If `False`, only one result is returned.

See also:

`numpy.logaddexp`, `numpy.logaddexp2`

Notes

NumPy has a `logaddexp` function which is very similar to `logsumexp`, but only handles two arguments. `logaddexp.reduce` is similar to this function, but may be less stable.

Examples

```
>>> from scipy.special import logsumexp
>>> a = np.arange(10)
>>> np.log(np.sum(np.exp(a)))
9.4586297444267107
>>> logsumexp(a)
9.4586297444267107
```

With weights

```
>>> a = np.arange(10)
>>> b = np.arange(10, 0, -1)
>>> logsumexp(a, b=b)
9.9170178533034665
>>> np.log(np.sum(b*np.exp(a)))
9.9170178533034647
```

Returning a sign flag

```
>>> logsumexp([1, 2], b=[1, -1], return_sign=True)
(1.5413248546129181, -1.0)
```

Notice that `logsumexp` does not directly support masked arrays. To use it on a masked array, convert the mask into zero weights:

```
>>> a = np.ma.array([np.log(2), 2, np.log(3)],
...                 mask=[False, True, False])
>>> b = (~a.mask).astype(int)
>>> logsumexp(a.data, b=b), np.log(5)
1.6094379124341005, 1.6094379124341005
```

scipy.special.exprel

`scipy.special.exprel(x) = <ufunc 'exprel'>`

Relative error exponential, $(\exp(x) - 1)/x$.

When x is near zero, $\exp(x)$ is near 1, so the numerical calculation of $\exp(x) - 1$ can suffer from catastrophic loss of precision. `exprel(x)` is implemented to avoid the loss of precision that occurs when x is near zero.

Parameters

x [ndarray] Input array. x must contain real numbers.

Returns

float $(\exp(x) - 1)/x$, computed element-wise.

See also:

[*expm1*](#)

Notes

New in version 0.17.0.

Examples

```
>>> from scipy.special import exprel
```

```
>>> exprel(0.01)
1.0050167084168056
>>> exprel([-0.25, -0.1, 0, 0.1, 0.25])
array([ 0.88479687,  0.95162582,  1.          ,  1.05170918,  1.13610167])
```

Compare `exprel(5e-9)` to the naive calculation. The exact value is `1.000000002500000000416...`

```
>>> exprel(5e-9)
1.0000000025
```

```
>>> (np.exp(5e-9) - 1)/5e-9
0.99999999392252903
```

scipy.special.sinc

`scipy.special.sinc(x)`

Return the sinc function.

The sinc function is $\sin(\pi x)/(\pi x)$.

Parameters

x [ndarray] Array (possibly multi-dimensional) of values for which to calculate `sinc(x)`.

Returns

out [ndarray] `sinc(x)`, which has the same shape as the input.

Notes

`sinc(0)` is the limit value 1.

The name `sinc` is short for “sine cardinal” or “sinus cardinalis”.

The `sinc` function is used in various signal processing applications, including in anti-aliasing, in the construction of a Lanczos resampling filter, and in interpolation.

For bandlimited interpolation of discrete-time signals, the ideal interpolation kernel is proportional to the `sinc` function.


References

[1], [2]

Examples

```
>>> import matplotlib.pyplot as plt
>>> x = np.linspace(-4, 4, 41)
>>> np.sinc(x)
array([-3.89804309e-17, -4.92362781e-02, -8.40918587e-02, # may vary
       -8.90384387e-02, -5.84680802e-02,  3.89804309e-17,
        6.68206631e-02,  1.16434881e-01,  1.26137788e-01,
        8.50444803e-02, -3.89804309e-17, -1.03943254e-01,
       -1.89206682e-01, -2.16236208e-01, -1.55914881e-01,
        3.89804309e-17,  2.33872321e-01,  5.04551152e-01,
        7.56826729e-01,  9.35489284e-01,  1.00000000e+00,
        9.35489284e-01,  7.56826729e-01,  5.04551152e-01,
        2.33872321e-01,  3.89804309e-17, -1.55914881e-01,
       -2.16236208e-01, -1.89206682e-01, -1.03943254e-01,
       -3.89804309e-17,  8.50444803e-02,  1.26137788e-01,
        1.16434881e-01,  6.68206631e-02,  3.89804309e-17,
       -5.84680802e-02, -8.90384387e-02, -8.40918587e-02,
       -4.92362781e-02, -3.89804309e-17])
```

```
>>> plt.plot(x, np.sinc(x))
[<matplotlib.lines.Line2D object at 0x...>]
>>> plt.title("Sinc Function")
Text(0.5, 1.0, 'Sinc Function')
>>> plt.ylabel("Amplitude")
Text(0, 0.5, 'Amplitude')
>>> plt.xlabel("X")
Text(0.5, 0, 'X')
>>> plt.show()
```



6.29 Statistical functions (`scipy.stats`)

This module contains a large number of probability distributions as well as a growing library of statistical functions.

Each univariate distribution is an instance of a subclass of `rv_continuous` (`rv_discrete` for discrete distributions):

<code>rv_continuous</code> ([momtype, a, b, xtol, ...])	A generic continuous random variable class meant for subclassing.
<code>rv_discrete</code> ([a, b, name, badvalue, ...])	A generic discrete random variable class meant for subclassing.
<code>rv_histogram</code> (histogram, *args, **kwargs)	Generates a distribution given by a histogram.

6.29.1 `scipy.stats.rv_continuous`

class `scipy.stats.rv_continuous` (*momtype=1, a=None, b=None, xtol=1e-14, badvalue=None, name=None, longname=None, shapes=None, extradoc=None, seed=None*)

A generic continuous random variable class meant for subclassing.

`rv_continuous` is a base class to construct specific distribution classes and instances for continuous random variables. It cannot be used directly as a distribution.

Parameters

momtype	[int, optional] The type of generic moment calculation to use: 0 for pdf, 1 (default) for ppf.
a	[float, optional] Lower bound of the support of the distribution, default is minus infinity.
b	[float, optional] Upper bound of the support of the distribution, default is plus infinity.
xtol	[float, optional] The tolerance for fixed point calculation for generic ppf.
badvalue	[float, optional] The value in a result arrays that indicates a value that for which some argument restriction is violated, default is <code>np.nan</code> .
name	[str, optional] The name of the instance. This string is used to construct the default example for distributions.
longname	[str, optional] This string is used as part of the first line of the docstring returned when a subclass has no docstring of its own. Note: <code>longname</code> exists for backwards compatibility, do not use for new subclasses.
shapes	[str, optional] The shape of the distribution. For example "m, n" for a distribution that takes two integers as the two shape arguments for all its methods. If not provided, shape parameters will be inferred from the signature of the private methods, <code>_pdf</code> and <code>_cdf</code> of the instance.
extradoc	[str, optional, deprecated] This string is used as the last part of the docstring returned when

Notes

Public methods of an instance of a distribution class (e.g., `pdf`, `cdf`) check their arguments and pass valid arguments to private, computational methods (`_pdf`, `_cdf`). For `pdf(x)`, `x` is valid if it is within the support of the distribution. Whether a shape parameter is valid is decided by an `_argcheck` method (which defaults to checking that its arguments are strictly positive.)

Subclassing

New random variables can be defined by subclassing the `rv_continuous` class and re-defining at least the `_pdf` or the `_cdf` method (normalized to location 0 and scale 1).

If positive argument checking is not correct for your RV then you will also need to re-define the `_argcheck` method.

For most of the `scipy.stats` distributions, the support interval doesn't depend on the shape parameters. `x` being in the support interval is equivalent to `self.a <= x <= self.b`. If either of the endpoints of the support do depend on the shape parameters, then i) the distribution must implement the `_get_support` method; and ii) those dependent endpoints must be omitted from the distribution's call to the `rv_continuous` initializer.

Correct, but potentially slow defaults exist for the remaining methods but for speed and/or accuracy you can override:

```
_logpdf, _cdf, _logcdf, _ppf, _rvs, _isf, _sf, _logsf
```

The default method `_rvs` relies on the inverse of the cdf, `_ppf`, applied to a uniform random variate. In order to generate random variates efficiently, either the default `_ppf` needs to be overwritten (e.g. if the inverse cdf can be expressed in an explicit form) or a sampling method needs to be implemented in a custom `_rvs` method.

If possible, you should override `_isf`, `_sf` or `_logsf`. The main reason would be to improve numerical accuracy: for example, the survival function `_sf` is computed as `1 - _cdf` which can result in loss of precision if `_cdf(x)` is close to one.

Methods that can be overwritten by subclasses

```
_rvs
_pdf
_cdf
_sf
_ppf
_isf
_stats
_munp
_entropy
_argcheck
_get_support
```

There are additional (internal and private) generic methods that can be useful for cross-checking and for debugging, but might work in all cases when directly called.

A note on `shapes`: subclasses need not specify them explicitly. In this case, `shapes` will be automatically deduced from the signatures of the overridden methods (`pdf`, `cdf` etc). If, for some reason, you prefer to avoid relying on introspection, you can specify `shapes` explicitly as an argument to the instance constructor.

Frozen Distributions

Normally, you must provide shape parameters (and, optionally, location and scale parameters to each call of a method of a distribution.

Alternatively, the object may be called (as a function) to fix the shape, location, and scale parameters returning a “frozen” continuous RV object:

`rv = generic(<shape(s)>, loc=0, scale=1)`

`rv_frozen` object with the same methods but holding the given shape, location, and scale fixed

Statistics

Statistics are computed using numerical integration by default. For speed you can redefine this using `_stats`:

- take shape parameters and return `mu, mu2, g1, g2`
- If you can’t compute one of these, return it as `None`
- Can also be defined with a keyword argument `moments`, which is a string composed of “m”, “v”, “s”, and/or “k”. Only the components appearing in string should be computed and returned in the order “m”, “v”, “s”, or “k” with missing values returned as `None`.

Alternatively, you can override `_munp`, which takes `n` and shape parameters and returns the `n`-th non-central moment of the distribution.

Examples

To create a new Gaussian distribution, we would do the following:

```
>>> from scipy.stats import rv_continuous
>>> class gaussian_gen(rv_continuous):
...     "Gaussian distribution"
...     def _pdf(self, x):
...         return np.exp(-x**2 / 2.) / np.sqrt(2.0 * np.pi)
>>> gaussian = gaussian_gen(name='gaussian')
```

`scipy.stats` distributions are *instances*, so here we subclass `rv_continuous` and create an instance. With this, we now have a fully functional distribution with all relevant methods automatically generated by the framework.

Note that above we defined a standard normal distribution, with zero mean and unit variance. Shifting and scaling of the distribution can be done by using `loc` and `scale` parameters: `gaussian.pdf(x, loc, scale)` essentially computes $y = (x - loc) / scale$ and `gaussian._pdf(y) / scale`.

Attributes

`random_state`

Get or set the `RandomState` object for generating random variates.

Methods

<code>rvs(self, *args, **kwargs)</code>	Random variates of given type.
<code>pdf(self, x, *args, **kwargs)</code>	Probability density function at <code>x</code> of the given RV.
<code>logpdf(self, x, *args, **kwargs)</code>	Log of the probability density function at <code>x</code> of the given RV.
<code>cdf(self, x, *args, **kwargs)</code>	Cumulative distribution function of the given RV.
<code>logcdf(self, x, *args, **kwargs)</code>	Log of the cumulative distribution function at <code>x</code> of the given RV.
<code>sf(self, x, *args, **kwargs)</code>	Survival function ($1 - cdf$) at <code>x</code> of the given RV.
<code>logsf(self, x, *args, **kwargs)</code>	Log of the survival function of the given RV.

continues on next page

Table 255 – continued from previous page

<code>ppf(self, q, *args, **kwargs)</code>	Percent point function (inverse of <code>cdf</code>) at <code>q</code> of the given RV.
<code>isf(self, q, *args, **kwargs)</code>	Inverse survival function (inverse of <code>sf</code>) at <code>q</code> of the given RV.
<code>moment(self, n, *args, **kwargs)</code>	<code>n</code> -th order non-central moment of distribution.
<code>stats(self, *args, **kwargs)</code>	Some statistics of the given RV.
<code>entropy(self, *args, **kwargs)</code>	Differential entropy of the RV.
<code>expect(self[, func, args, loc, scale, lb, ...])</code>	Calculate expected value of a function with respect to the distribution by numerical integration.
<code>median(self, *args, **kwargs)</code>	Median of the distribution.
<code>mean(self, *args, **kwargs)</code>	Mean of the distribution.
<code>std(self, *args, **kwargs)</code>	Standard deviation of the distribution.
<code>var(self, *args, **kwargs)</code>	Variance of the distribution.
<code>interval(self, alpha, *args, **kwargs)</code>	Confidence interval with equal areas around the median.
<code>__call__(self, *args, **kwargs)</code>	Freeze the distribution for the given arguments.
<code>fit(self, data, *args, **kwargs)</code>	Return MLEs for shape (if applicable), location, and scale parameters from data.
<code>fit_loc_scale(self, data, *args)</code>	Estimate loc and scale parameters from data using 1st and 2nd moments.
<code>nllf(self, theta, x)</code>	Return negative loglikelihood function.
<code>support(self, *args, **kwargs)</code>	Return the support of the distribution.

scipy.stats.rv_continuous.rvs

`rv_continuous.rvs(self, *args, **kwargs)`
Random variates of given type.

Parameters**arg1, arg2, arg3,...**

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).

loc [array_like, optional] Location parameter (default=0).

scale [array_like, optional] Scale parameter (default=1).

size [int or tuple of ints, optional] Defining number of random variates (default is 1).

random_state

[{None, int, `RandomState`, `Generator`}, optional] If `seed` is `None` the `RandomState` singleton is used. If `seed` is an int, a new `RandomState` instance is used, seeded with `seed`. If `seed` is already a `RandomState` or `Generator` instance, then that object is used. Default is `None`.

Returns

rvs [ndarray or scalar] Random variates of given `size`.

scipy.stats.rv_continuous.pdf

`rv_continuous.pdf` (*self*, *x*, **args*, ***kws*)
Probability density function at *x* of the given RV.

Parameters

x [array_like] quantiles
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

pdf [ndarray] Probability density function evaluated at *x*

scipy.stats.rv_continuous.logpdf

`rv_continuous.logpdf` (*self*, *x*, **args*, ***kws*)
Log of the probability density function at *x* of the given RV.

This uses a more numerically accurate calculation if available.

Parameters

x [array_like] quantiles
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

logpdf [array_like] Log of the probability density function evaluated at *x*

scipy.stats.rv_continuous.cdf

`rv_continuous.cdf` (*self*, *x*, **args*, ***kws*)
Cumulative distribution function of the given RV.

Parameters

x [array_like] quantiles
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

cdf [ndarray] Cumulative distribution function evaluated at *x*

scipy.stats.rv_continuous.logcdf

`rv_continuous.logcdf` (*self*, *x*, *args, **kwargs)

Log of the cumulative distribution function at *x* of the given RV.

Parameters

x [array_like] quantiles
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

logcdf [array_like] Log of the cumulative distribution function evaluated at *x*

scipy.stats.rv_continuous.sf

`rv_continuous.sf` (*self*, *x*, *args, **kwargs)

Survival function ($1 - cdf$) at *x* of the given RV.

Parameters

x [array_like] quantiles
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

sf [array_like] Survival function evaluated at *x*

scipy.stats.rv_continuous.logsf

`rv_continuous.logsf` (*self*, *x*, *args, **kwargs)

Log of the survival function of the given RV.

Returns the log of the “survival function,” defined as $(1 - cdf)$, evaluated at *x*.

Parameters

x [array_like] quantiles
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

logsf [ndarray] Log of the survival function evaluated at *x*.

scipy.stats.rv_continuous.ppf`rv_continuous.ppf` (*self*, *q*, **args*, ***kwargs*)Percent point function (inverse of *cdf*) at *q* of the given RV.**Parameters**

q [array_like] lower tail probability
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

x [array_like] quantile corresponding to the lower tail probability *q*.

scipy.stats.rv_continuous.isf`rv_continuous.isf` (*self*, *q*, **args*, ***kwargs*)Inverse survival function (inverse of *sf*) at *q* of the given RV.**Parameters**

q [array_like] upper tail probability
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

x [ndarray or scalar] Quantile corresponding to the upper tail probability *q*.

scipy.stats.rv_continuous.moment`rv_continuous.moment` (*self*, *n*, **args*, ***kwargs*)*n*-th order non-central moment of distribution.**Parameters**

n [int, *n* >= 1] Order of moment.
arg1, arg2, arg3,... [float] The shape parameter(s) for the distribution (see docstring of the instance object for more information).
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

scipy.stats.rv_continuous.stats

`rv_continuous.stats` (*self*, *args, **kwargs)

Some statistics of the given RV.

Parameters

arg1, arg2, arg3,...

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] location parameter (default=0)

scale [array_like, optional (continuous RVs only)] scale parameter (default=1)

moments [str, optional] composed of letters ['mvsk'] defining which moments to compute: 'm' = mean, 'v' = variance, 's' = (Fisher's) skew, 'k' = (Fisher's) kurtosis. (default is 'mv')

Returns

stats [sequence] of requested moments.

scipy.stats.rv_continuous.entropy

`rv_continuous.entropy` (*self*, *args, **kwargs)

Differential entropy of the RV.

Parameters

arg1, arg2, arg3,...

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).

loc [array_like, optional] Location parameter (default=0).

scale [array_like, optional (continuous distributions only).] Scale parameter (default=1).

Notes

Entropy is defined base e :

```
>>> drv = rv_discrete(values=((0, 1), (0.5, 0.5)))
>>> np.allclose(drv.entropy(), np.log(2.0))
True
```

scipy.stats.rv_continuous.expect

`rv_continuous.expect` (*self*, func=None, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwargs)

Calculate expected value of a function with respect to the distribution by numerical integration.

The expected value of a function $f(x)$ with respect to a distribution `dist` is defined as:

$$E[f(x)] = \int_{lb}^{ub} f(x) * dist.pdf(x),$$

where `ub` and `lb` are arguments and `x` has the `dist.pdf(x)` distribution. If the bounds `lb` and `ub` correspond to the support of the distribution, e.g. `[-inf, inf]` in the default case, then the integral is the unrestricted expectation of $f(x)$. Also, the function $f(x)$ may be defined such that $f(x)$ is 0 outside a finite interval in which case the expectation is calculated within the finite range `[lb, ub]`.

Parameters

func [callable, optional] Function for which integral is calculated. Takes only one argument. The default is the identity mapping $f(x) = x$.

args [tuple, optional] Shape parameters of the distribution.

loc [float, optional] Location parameter (default=0).

scale [float, optional] Scale parameter (default=1).

lb, ub [scalar, optional] Lower and upper bound for integration. Default is set to the support of the distribution.

conditional [bool, optional] If True, the integral is corrected by the conditional probability of the integration interval. The return value is the expectation of the function, conditional on being in the given interval. Default is False.

Additional keyword arguments are passed to the integration routine.

Returns

expect [float] The calculated expected value.

Notes

The integration behavior of this function is inherited from `scipy.integrate.quad`. Neither this function nor `scipy.integrate.quad` can verify whether the integral exists or is finite. For example `cauchy(0).mean()` returns `np.nan` and `cauchy(0).expect()` returns `0.0`.

The function is not vectorized.

Examples

To understand the effect of the bounds of integration consider

```
>>> from scipy.stats import expon
>>> expon(1).expect(lambda x: 1, lb=0.0, ub=2.0)
0.6321205588285578
```

This is close to

```
>>> expon(1).cdf(2.0) - expon(1).cdf(0.0)
0.6321205588285577
```

If `conditional=True`

```
>>> expon(1).expect(lambda x: 1, lb=0.0, ub=2.0, conditional=True)
1.0000000000000002
```

The slight deviation from 1 is due to numerical integration.

scipy.stats.rv_continuous.median

`rv_continuous.median` (*self*, *args, **kwargs)
Median of the distribution.

Parameters

arg1, arg2, arg3,...
[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] Location parameter, Default is 0.

scale [array_like, optional] Scale parameter, Default is 1.

Returns

median [float] The median of the distribution.

See also:

[*rv_discrete.ppf*](#)

Inverse of the CDF

scipy.stats.rv_continuous.mean

`rv_continuous.mean` (*self*, *args, **kwargs)
Mean of the distribution.

Parameters

arg1, arg2, arg3,...
[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] location parameter (default=0)

scale [array_like, optional] scale parameter (default=1)

Returns

mean [float] the mean of the distribution

scipy.stats.rv_continuous.std

`rv_continuous.std` (*self*, *args, **kwargs)
Standard deviation of the distribution.

Parameters

arg1, arg2, arg3,...
[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] location parameter (default=0)

scale [array_like, optional] scale parameter (default=1)

Returns

std [float] standard deviation of the distribution

scipy.stats.rv_continuous.var

`rv_continuous.var` (*self*, *args, **kwargs)
Variance of the distribution.

Parameters

arg1, arg2, arg3,...
[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] location parameter (default=0)

scale [array_like, optional] scale parameter (default=1)

Returns

var [float] the variance of the distribution

scipy.stats.rv_continuous.interval

`rv_continuous.interval` (*self*, *alpha*, *args, **kwargs)
Confidence interval with equal areas around the median.

Parameters

alpha [array_like of float] Probability that an rv will be drawn from the returned range. Each value should be in the range [0, 1].

arg1, arg2, ...
[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).

loc [array_like, optional] location parameter, Default is 0.

scale [array_like, optional] scale parameter, Default is 1.

Returns

a, b [ndarray of float] end-points of range that contain $100 * \alpha$ % of the rv's possible values.

scipy.stats.rv_continuous.__call__

`rv_continuous.__call__` (*self*, *args, **kwargs)
Freeze the distribution for the given arguments.

Parameters

arg1, arg2, arg3,...
[array_like] The shape parameter(s) for the distribution. Should include all the non-optional arguments, may include `loc` and `scale`.

Returns

rv_frozen [rv_frozen instance] The frozen distribution.

scipy.stats.rv_continuous.fit

`rv_continuous.fit` (*self*, *data*, **args*, ***kwargs*)

Return MLEs for shape (if applicable), location, and scale parameters from data.

MLE stands for Maximum Likelihood Estimate. Starting estimates for the fit are given by input arguments; for any arguments not provided with starting estimates, `self._fitstart(data)` is called to generate such.

One can hold some parameters fixed to specific values by passing in keyword arguments `f0`, `f1`, ..., `fn` (for shape parameters) and `floc` and `fscale` (for location and scale parameters, respectively).

Parameters

data [array_like] Data to use in calculating the MLEs.

arg1, arg2, arg3,...

[floats, optional] Starting value(s) for any shape-characterizing arguments (those not provided will be determined by a call to `_fitstart(data)`). No default value.

kwargs [floats, optional]

- *loc*: initial guess of the distribution's location parameter.
- *scale*: initial guess of the distribution's scale parameter.

Special keyword arguments are recognized as holding certain parameters fixed:

- `f0...fn` : hold respective shape parameters fixed. Alternatively, shape parameters to fix can be specified by name. For example, if `self.shapes == "a, b"`, `fa` and `fix_a` are equivalent to `f0`, and `fb` and `fix_b` are equivalent to `f1`.
- `floc` : hold location parameter fixed to specified value.
- `fscale` : hold scale parameter fixed to specified value.
- `optimizer` : The optimizer to use. The optimizer must take `func`, and starting position as the first two arguments, plus `args` (for extra arguments to pass to the function to be optimized) and `disp=0` to suppress output as keyword arguments.

Returns

mle_tuple [tuple of floats] MLEs for any shape parameters (if applicable), followed by those for location and scale. For most random variables, shape statistics will be returned, but there are exceptions (e.g. `norm`).

Notes

This fit is computed by maximizing a log-likelihood function, with penalty applied for samples outside of range of the distribution. The returned answer is not guaranteed to be the globally optimal MLE, it may only be locally optimal, or the optimization may fail altogether. If the data contain any of `np.nan`, `np.inf`, or `-np.inf`, the fit routine will throw a `RuntimeError`.

Examples

Generate some data to fit: draw random variates from the *beta* distribution

```
>>> from scipy.stats import beta
>>> a, b = 1., 2.
>>> x = beta.rvs(a, b, size=1000)
```

Now we can fit all four parameters (*a*, *b*, *loc* and *scale*):

```
>>> a1, b1, loc1, scale1 = beta.fit(x)
```

We can also use some prior knowledge about the dataset: let's keep `loc` and `scale` fixed:

```
>>> a1, b1, loc1, scale1 = beta.fit(x, floc=0, fscale=1)
>>> loc1, scale1
(0, 1)
```

We can also keep shape parameters fixed by using `f`-keywords. To keep the zero-th shape parameter `a` equal 1, use `f0=1` or, equivalently, `fa=1`:

```
>>> a1, b1, loc1, scale1 = beta.fit(x, fa=1, floc=0, fscale=1)
>>> a1
1
```

Not all distributions return estimates for the shape parameters. `norm` for example just returns estimates for location and scale:

```
>>> from scipy.stats import norm
>>> x = norm.rvs(a, b, size=1000, random_state=123)
>>> loc1, scale1 = norm.fit(x)
>>> loc1, scale1
(0.92087172783841631, 2.0015750750324668)
```

`scipy.stats.rv_continuous.fit_loc_scale`

`rv_continuous.fit_loc_scale` (*self*, *data*, **args*)

Estimate `loc` and `scale` parameters from data using 1st and 2nd moments.

Parameters

data [array_like] Data to fit.

arg1, arg2, arg3,...

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).

Returns

Lhat [float] Estimated location parameter for the data.

Shat [float] Estimated scale parameter for the data.

`scipy.stats.rv_continuous.nllf`

`rv_continuous.nllf` (*self*, *theta*, *x*)

Return negative loglikelihood function.

Notes

This is $-\text{sum}(\log \text{pdf}(x, \text{theta}), \text{axis}=0)$ where *theta* are the parameters (including `loc` and `scale`).

scipy.stats.rv_continuous.support

`rv_continuous.support` (*self*, *args, **kwargs)

Return the support of the distribution.

Parameters

arg1, arg2, ...

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).

loc [array_like, optional] location parameter, Default is 0.

scale [array_like, optional] scale parameter, Default is 1.

Returns

a, b [float] end-points of the distribution's support.

6.29.2 scipy.stats.rv_discrete

class `scipy.stats.rv_discrete` (*a=0, b=inf, name=None, badvalue=None, moment_tol=1e-08, values=None, inc=1, longname=None, shapes=None, extradoc=None, seed=None*)

A generic discrete random variable class meant for subclassing.

`rv_discrete` is a base class to construct specific distribution classes and instances for discrete random variables. It can also be used to construct an arbitrary distribution defined by a list of support points and corresponding probabilities.

Parameters

a [float, optional] Lower bound of the support of the distribution, default: 0

b [float, optional] Upper bound of the support of the distribution, default: plus infinity

moment_tol

[float, optional] The tolerance for the generic calculation of moments.

values [tuple of two array_like, optional] (x_k, p_k) where x_k are integers and p_k are the non-zero probabilities between 0 and 1 with $\sum(p_k) = 1$. x_k and p_k must have the same shape.

inc [integer, optional] Increment for the support of the distribution. Default is 1. (other values have not been tested)

badvalue [float, optional] The value in a result arrays that indicates a value that for which some argument restriction is violated, default is `np.nan`.

name [str, optional] The name of the instance. This string is used to construct the default example for distributions.

longname [str, optional] This string is used as part of the first line of the docstring returned when a subclass has no docstring of its own. Note: *longname* exists for backwards compatibility, do not use for new subclasses.

shapes [str, optional] The shape of the distribution. For example "m, n" for a distribution that takes two integers as the two shape arguments for all its methods. If not provided, shape parameters will be inferred from the signatures of the private methods, `_pmf` and `_cdf` of the instance.

extradoc [str, optional] This string is used as the last part of the docstring returned when a subclass has no docstring of its own. Note: *extradoc* exists for backwards compatibility, do not use for new subclasses.

seed [{None, int, *RandomState*, *Generator*}, optional] This parameter defines the object to use for drawing random variates. If *seed* is *None* the *RandomState* singleton is used. If *seed* is an int, a new *RandomState* instance is used, seeded with *seed*. If *seed* is already a *RandomState* or *Generator* instance, then that object is used. Default is *None*.

Notes

This class is similar to `rv_continuous`. Whether a shape parameter is valid is decided by an `_argcheck` method (which defaults to checking that its arguments are strictly positive.) The main differences are:

- the support of the distribution is a set of integers
- instead of the probability density function, `pdf` (and the corresponding private `_pdf`), this class defines the *probability mass function*, `pmf` (and the corresponding private `_pmf`.)
- scale parameter is not defined.

To create a new discrete distribution, we would do the following:

```
>>> from scipy.stats import rv_discrete
>>> class poisson_gen(rv_discrete):
...     "Poisson distribution"
...     def _pmf(self, k, mu):
...         return exp(-mu) * mu**k / factorial(k)
```

and create an instance:

```
>>> poisson = poisson_gen(name="poisson")
```

Note that above we defined the Poisson distribution in the standard form. Shifting the distribution can be done by providing the `loc` parameter to the methods of the instance. For example, `poisson.pmf(x, mu, loc)` delegates the work to `poisson._pmf(x-loc, mu)`.

Discrete distributions from a list of probabilities

Alternatively, you can construct an arbitrary discrete rv defined on a finite set of values `xk` with $\text{Prob}\{X=x_k\} = p_k$ by using the `values` keyword argument to the `rv_discrete` constructor.

Examples

Custom made discrete distribution:

```
>>> from scipy import stats
>>> xk = np.arange(7)
>>> pk = (0.1, 0.2, 0.3, 0.1, 0.1, 0.0, 0.2)
>>> custm = stats.rv_discrete(name='custm', values=(xk, pk))
>>>
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
>>> ax.plot(xk, custm.pmf(xk), 'ro', ms=12, mec='r')
>>> ax.vlines(xk, 0, custm.pmf(xk), colors='r', lw=4)
>>> plt.show()
```


Random number generation:

```
>>> R = custm.rvs(size=100)
```

Attributes

`random_state`

Get or set the `RandomState` object for generating random variates.



Methods

<code>rvs(self, *args, **kwargs)</code>	Random variates of given type.
<code>pmf(self, k, *args, **kwargs)</code>	Probability mass function at k of the given RV.
<code>logpmf(self, k, *args, **kwargs)</code>	Log of the probability mass function at k of the given RV.
<code>cdf(self, k, *args, **kwargs)</code>	Cumulative distribution function of the given RV.
<code>logcdf(self, k, *args, **kwargs)</code>	Log of the cumulative distribution function at k of the given RV.
<code>sf(self, k, *args, **kwargs)</code>	Survival function (1 - <code>cdf</code>) at k of the given RV.
<code>logsf(self, k, *args, **kwargs)</code>	Log of the survival function of the given RV.
<code>ppf(self, q, *args, **kwargs)</code>	Percent point function (inverse of <code>cdf</code>) at q of the given RV.
<code>isf(self, q, *args, **kwargs)</code>	Inverse survival function (inverse of <code>sf</code>) at q of the given RV.
<code>moment(self, n, *args, **kwargs)</code>	n-th order non-central moment of distribution.
<code>stats(self, *args, **kwargs)</code>	Some statistics of the given RV.
<code>entropy(self, *args, **kwargs)</code>	Differential entropy of the RV.
<code>expect(self[, func, args, loc, lb, ub, ...])</code>	Calculate expected value of a function with respect to the distribution for discrete distribution by numerical summation.
<code>median(self, *args, **kwargs)</code>	Median of the distribution.
<code>mean(self, *args, **kwargs)</code>	Mean of the distribution.
<code>std(self, *args, **kwargs)</code>	Standard deviation of the distribution.
<code>var(self, *args, **kwargs)</code>	Variance of the distribution.
<code>interval(self, alpha, *args, **kwargs)</code>	Confidence interval with equal areas around the median.
<code>__call__(self, *args, **kwargs)</code>	Freeze the distribution for the given arguments.
<code>support(self, *args, **kwargs)</code>	Return the support of the distribution.

scipy.stats.rv_discrete.rvs

`rv_discrete.rvs(self, *args, **kwargs)`
Random variates of given type.

6.29. Statistical functions (scipy.stats)

Parameters

arg1, arg2, arg3,...

[array_like] The shape parameter(s) for the distribution (see docstring of the instance)

scipy.stats.rv_discrete.pmf`rv_discrete.pmf` (*self*, *k*, **args*, ***kwargs*)Probability mass function at *k* of the given RV.**Parameters**

k [array_like] Quantiles.
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] Location parameter (default=0).

Returns

pmf [array_like] Probability mass function evaluated at *k*

scipy.stats.rv_discrete.logpmf`rv_discrete.logpmf` (*self*, *k*, **args*, ***kwargs*)Log of the probability mass function at *k* of the given RV.**Parameters**

k [array_like] Quantiles.
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).
loc [array_like, optional] Location parameter. Default is 0.

Returns

logpmf [array_like] Log of the probability mass function evaluated at *k*.

scipy.stats.rv_discrete.cdf`rv_discrete.cdf` (*self*, *k*, **args*, ***kwargs*)

Cumulative distribution function of the given RV.

Parameters

k [array_like, int] Quantiles.
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).
loc [array_like, optional] Location parameter (default=0).

Returns

cdf [ndarray] Cumulative distribution function evaluated at *k*.

scipy.stats.rv_discrete.logcdf

`rv_discrete.logcdf` (*self*, *k*, *args, **kwargs)

Log of the cumulative distribution function at *k* of the given RV.

Parameters

k [array_like, int] Quantiles.
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).
loc [array_like, optional] Location parameter (default=0).

Returns

logcdf [array_like] Log of the cumulative distribution function evaluated at *k*.

scipy.stats.rv_discrete.sf

`rv_discrete.sf` (*self*, *k*, *args, **kwargs)

Survival function ($1 - cdf$) at *k* of the given RV.

Parameters

k [array_like] Quantiles.
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).
loc [array_like, optional] Location parameter (default=0).

Returns

sf [array_like] Survival function evaluated at *k*.

scipy.stats.rv_discrete.logsf

`rv_discrete.logsf` (*self*, *k*, *args, **kwargs)

Log of the survival function of the given RV.

Returns the log of the “survival function,” defined as $1 - cdf$, evaluated at *k*.

Parameters

k [array_like] Quantiles.
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).
loc [array_like, optional] Location parameter (default=0).

Returns

logsf [ndarray] Log of the survival function evaluated at *k*.

scipy.stats.rv_discrete.ppf`rv_discrete.ppf` (*self*, *q*, **args*, ***kwds*)Percent point function (inverse of *cdf*) at *q* of the given RV.**Parameters**

q [array_like] Lower tail probability.
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).
loc [array_like, optional] Location parameter (default=0).

Returns

k [array_like] Quantile corresponding to the lower tail probability, *q*.

scipy.stats.rv_discrete.isf`rv_discrete.isf` (*self*, *q*, **args*, ***kwds*)Inverse survival function (inverse of *sf*) at *q* of the given RV.**Parameters**

q [array_like] Upper tail probability.
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).
loc [array_like, optional] Location parameter (default=0).

Returns

k [ndarray or scalar] Quantile corresponding to the upper tail probability, *q*.

scipy.stats.rv_discrete.moment`rv_discrete.moment` (*self*, *n*, **args*, ***kwds*)*n*-th order non-central moment of distribution.**Parameters**

n [int, *n* >= 1] Order of moment.
arg1, arg2, arg3,... [float] The shape parameter(s) for the distribution (see docstring of the instance object for more information).
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

scipy.stats.rv_discrete.stats

`rv_discrete.stats` (*self*, *args, **kwargs)

Some statistics of the given RV.

Parameters

arg1, arg2, arg3,...

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] location parameter (default=0)

scale [array_like, optional (continuous RVs only)] scale parameter (default=1)

moments [str, optional] composed of letters ['mvs'k'] defining which moments to compute: 'm' = mean, 'v' = variance, 's' = (Fisher's) skew, 'k' = (Fisher's) kurtosis. (default is 'mv')

Returns

stats [sequence] of requested moments.

scipy.stats.rv_discrete.entropy

`rv_discrete.entropy` (*self*, *args, **kwargs)

Differential entropy of the RV.

Parameters

arg1, arg2, arg3,...

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).

loc [array_like, optional] Location parameter (default=0).

scale [array_like, optional (continuous distributions only).] Scale parameter (default=1).

Notes

Entropy is defined base e :

```
>>> drv = rv_discrete(values=((0, 1), (0.5, 0.5)))
>>> np.allclose(drv.entropy(), np.log(2.0))
True
```

scipy.stats.rv_discrete.expect

`rv_discrete.expect` (*self*, func=None, args=(), loc=0, lb=None, ub=None, conditional=False, max-count=1000, tolerance=1e-10, chunksize=32)

Calculate expected value of a function with respect to the distribution for discrete distribution by numerical summation.

Parameters

func [callable, optional] Function for which the expectation value is calculated. Takes only one argument. The default is the identity mapping $f(k) = k$.

args [tuple, optional] Shape parameters of the distribution.

loc [float, optional] Location parameter. Default is 0.

lb, ub [int, optional] Lower and upper bound for the summation, default is set to the support of the distribution, inclusive ($lb \leq k \leq ub$).

conditional

[bool, optional] If true then the expectation is corrected by the conditional probability of the summation interval. The return value is the expectation of the function, *func*, conditional on being in the given interval (k such that $lb \leq k \leq ub$). Default is False.

maxcount [int, optional] Maximal number of terms to evaluate (to avoid an endless loop for an infinite sum). Default is 1000.

tolerance [float, optional] Absolute tolerance for the summation. Default is 1e-10.

chunksize [int, optional] Iterate over the support of a distributions in chunks of this size. Default is 32.

Returns

expect [float] Expected value.

Notes

For heavy-tailed distributions, the expected value may or may not exist, depending on the function, *func*. If it does exist, but the sum converges slowly, the accuracy of the result may be rather low. For instance, for `zipf(4)`, accuracy for mean, variance in example is only 1e-5. increasing *maxcount* and/or *chunksize* may improve the result, but may also make zipf very slow.

The function is not vectorized.

scipy.stats.rv_discrete.median

`rv_discrete.median` (*self*, **args*, ***kws*)

Median of the distribution.

Parameters

arg1, arg2, arg3,...

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] Location parameter, Default is 0.

scale [array_like, optional] Scale parameter, Default is 1.

Returns

median [float] The median of the distribution.

See also:

[*rv_discrete.ppf*](#)

Inverse of the CDF

scipy.stats.rv_discrete.mean`rv_discrete.mean` (*self*, *args, **kwargs)

Mean of the distribution.

Parameters**arg1, arg2, arg3,...**

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] location parameter (default=0)**scale** [array_like, optional] scale parameter (default=1)**Returns****mean** [float] the mean of the distribution**scipy.stats.rv_discrete.std**`rv_discrete.std` (*self*, *args, **kwargs)

Standard deviation of the distribution.

Parameters**arg1, arg2, arg3,...**

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] location parameter (default=0)**scale** [array_like, optional] scale parameter (default=1)**Returns****std** [float] standard deviation of the distribution**scipy.stats.rv_discrete.var**`rv_discrete.var` (*self*, *args, **kwargs)

Variance of the distribution.

Parameters**arg1, arg2, arg3,...**

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] location parameter (default=0)**scale** [array_like, optional] scale parameter (default=1)**Returns****var** [float] the variance of the distribution

scipy.stats.rv_discrete.interval

`rv_discrete.interval` (*self*, *alpha*, *args, **kwargs)

Confidence interval with equal areas around the median.

Parameters

- alpha** [array_like of float] Probability that an rv will be drawn from the returned range. Each value should be in the range [0, 1].
- arg1, arg2, ...** [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).
- loc** [array_like, optional] location parameter, Default is 0.
- scale** [array_like, optional] scale parameter, Default is 1.

Returns

- a, b** [ndarray of float] end-points of range that contain $100 * \text{alpha} \%$ of the rv's possible values.

scipy.stats.rv_discrete.__call__

`rv_discrete.__call__` (*self*, *args, **kwargs)

Freeze the distribution for the given arguments.

Parameters

- arg1, arg2, arg3, ...** [array_like] The shape parameter(s) for the distribution. Should include all the non-optional arguments, may include `loc` and `scale`.

Returns

- rv_frozen** [rv_frozen instance] The frozen distribution.

scipy.stats.rv_discrete.support

`rv_discrete.support` (*self*, *args, **kwargs)

Return the support of the distribution.

Parameters

- arg1, arg2, ...** [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).
- loc** [array_like, optional] location parameter, Default is 0.
- scale** [array_like, optional] scale parameter, Default is 1.

Returns

- a, b** [float] end-points of the distribution's support.

6.29.3 `scipy.stats.rv_histogram`

class `scipy.stats.rv_histogram` (*histogram*, *args, **kwargs)

Generates a distribution given by a histogram. This is useful to generate a template distribution from a binned datasample.

As a subclass of the `rv_continuous` class, `rv_histogram` inherits from it a collection of generic methods (see `rv_continuous` for the full list), and implements them based on the properties of the provided binned datasample.

Parameters

histogram [(tuple of array_like)] Tuple containing two array_like objects The first containing the content of n bins The second containing the (n+1) bin boundaries In particular the return value `np.histogram` is accepted

Notes

There are no additional shape parameters except for the loc and scale. The pdf is defined as a stepwise function from the provided histogram The cdf is a linear interpolation of the pdf.

New in version 0.19.0.

Examples

Create a `scipy.stats` distribution from a numpy histogram

```
>>> import scipy.stats
>>> import numpy as np
>>> data = scipy.stats.norm.rvs(size=100000, loc=0, scale=1.5, random_
↳state=123)
>>> hist = np.histogram(data, bins=100)
>>> hist_dist = scipy.stats.rv_histogram(hist)
```

Behaves like an ordinary `scipy rv_continuous` distribution


```
>>> hist_dist.pdf(1.0)
0.20538577847618705
>>> hist_dist.cdf(2.0)
0.90818568543056499
```

PDF is zero above (below) the highest (lowest) bin of the histogram, defined by the max (min) of the original dataset

```
>>> hist_dist.pdf(np.max(data))
0.0
>>> hist_dist.cdf(np.max(data))
1.0
>>> hist_dist.pdf(np.min(data))
7.7591907244498314e-05
>>> hist_dist.cdf(np.min(data))
0.0
```

PDF and CDF follow the histogram

```
>>> import matplotlib.pyplot as plt
>>> X = np.linspace(-5.0, 5.0, 100)
>>> plt.title("PDF from Template")
>>> plt.hist(data, density=True, bins=100)
>>> plt.plot(X, hist_dist.pdf(X), label='PDF')
>>> plt.plot(X, hist_dist.cdf(X), label='CDF')
>>> plt.show()
```



Attributes

random_state

Get or set the RandomState object for generating random variates.

Methods

<code>__call__(self, *args, **kwargs)</code>	Freeze the distribution for the given arguments.
<code>cdf(self, x, *args, **kwargs)</code>	Cumulative distribution function of the given RV.
<code>entropy(self, *args, **kwargs)</code>	Differential entropy of the RV.
<code>expect(self[, func, args, loc, scale, lb, ...])</code>	Calculate expected value of a function with respect to the distribution by numerical integration.
<code>fit(self, data, *args, **kwargs)</code>	Return MLEs for shape (if applicable), location, and scale parameters from data.
<code>fit_loc_scale(self, data, *args)</code>	Estimate loc and scale parameters from data using 1st and 2nd moments.
<code>freeze(self, *args, **kwargs)</code>	Freeze the distribution for the given arguments.
<code>interval(self, alpha, *args, **kwargs)</code>	Confidence interval with equal areas around the median.
<code>isf(self, q, *args, **kwargs)</code>	Inverse survival function (inverse of sf) at q of the given RV.
<code>logcdf(self, x, *args, **kwargs)</code>	Log of the cumulative distribution function at x of the given RV.

continues on next page

Table 257 – continued from previous page

<code>logpdf(self, x, *args, **kwargs)</code>	Log of the probability density function at x of the given RV.
<code>logsf(self, x, *args, **kwargs)</code>	Log of the survival function of the given RV.
<code>mean(self, *args, **kwargs)</code>	Mean of the distribution.
<code>median(self, *args, **kwargs)</code>	Median of the distribution.
<code>moment(self, n, *args, **kwargs)</code>	n -th order non-central moment of distribution.
<code>nllf(self, theta, x)</code>	Return negative loglikelihood function.
<code>pdf(self, x, *args, **kwargs)</code>	Probability density function at x of the given RV.
<code>ppf(self, q, *args, **kwargs)</code>	Percent point function (inverse of <code>cdf</code>) at q of the given RV.
<code>rvs(self, *args, **kwargs)</code>	Random variates of given type.
<code>sf(self, x, *args, **kwargs)</code>	Survival function ($1 - \text{cdf}$) at x of the given RV.
<code>stats(self, *args, **kwargs)</code>	Some statistics of the given RV.
<code>std(self, *args, **kwargs)</code>	Standard deviation of the distribution.
<code>support(self, *args, **kwargs)</code>	Return the support of the distribution.
<code>var(self, *args, **kwargs)</code>	Variance of the distribution.

scipy.stats.rv_histogram.__call__

`rv_histogram.__call__(self, *args, **kwargs)`

Freeze the distribution for the given arguments.

Parameters

arg1, arg2, arg3,...

[array_like] The shape parameter(s) for the distribution. Should include all the non-optional arguments, may include `loc` and `scale`.

Returns

rv_frozen [rv_frozen instance] The frozen distribution.

scipy.stats.rv_histogram.cdf

`rv_histogram.cdf(self, x, *args, **kwargs)`

Cumulative distribution function of the given RV.

Parameters

x [array_like] quantiles

arg1, arg2, arg3,...

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] location parameter (default=0)

scale [array_like, optional] scale parameter (default=1)

Returns

cdf [ndarray] Cumulative distribution function evaluated at x

scipy.stats.rv_histogram.entropy

`rv_histogram.entropy` (*self*, *args, **kws)
 Differential entropy of the RV.

Parameters

- arg1, arg2, arg3,...**
 [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).
- loc**
 [array_like, optional] Location parameter (default=0).
- scale**
 [array_like, optional (continuous distributions only).] Scale parameter (default=1).

Notes

Entropy is defined base *e*:

```
>>> drv = rv_discrete(values=((0, 1), (0.5, 0.5)))
>>> np.allclose(drv.entropy(), np.log(2.0))
True
```

scipy.stats.rv_histogram.expect

`rv_histogram.expect` (*self*, func=None, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)

Calculate expected value of a function with respect to the distribution by numerical integration.

The expected value of a function $f(x)$ with respect to a distribution `dist` is defined as:

$$E[f(x)] = \int_{lb}^{ub} f(x) * dist.pdf(x),$$

where `ub` and `lb` are arguments and `x` has the `dist.pdf(x)` distribution. If the bounds `lb` and `ub` correspond to the support of the distribution, e.g. `[-inf, inf]` in the default case, then the integral is the unrestricted expectation of $f(x)$. Also, the function $f(x)$ may be defined such that $f(x)$ is 0 outside a finite interval in which case the expectation is calculated within the finite range `[lb, ub]`.

Parameters

- func**
 [callable, optional] Function for which integral is calculated. Takes only one argument. The default is the identity mapping $f(x) = x$.
- args**
 [tuple, optional] Shape parameters of the distribution.
- loc**
 [float, optional] Location parameter (default=0).
- scale**
 [float, optional] Scale parameter (default=1).
- lb, ub**
 [scalar, optional] Lower and upper bound for integration. Default is set to the support of the distribution.
- conditional**
 [bool, optional] If True, the integral is corrected by the conditional probability of the integration interval. The return value is the expectation of the function, conditional on being in the given interval. Default is False.

Additional keyword arguments are passed to the integration routine.

Returns

- expect**
 [float] The calculated expected value.

Notes

The integration behavior of this function is inherited from `scipy.integrate.quad`. Neither this function nor `scipy.integrate.quad` can verify whether the integral exists or is finite. For example `cauchy(0).mean()` returns `np.nan` and `cauchy(0).expect()` returns `0.0`.

The function is not vectorized.

Examples

To understand the effect of the bounds of integration consider

```
>>> from scipy.stats import expon
>>> expon(1).expect(lambda x: 1, lb=0.0, ub=2.0)
0.6321205588285578
```

This is close to

```
>>> expon(1).cdf(2.0) - expon(1).cdf(0.0)
0.6321205588285577
```

If `conditional=True`

```
>>> expon(1).expect(lambda x: 1, lb=0.0, ub=2.0, conditional=True)
1.0000000000000002
```

The slight deviation from 1 is due to numerical integration.

scipy.stats.rv_histogram.fit

`rv_histogram.fit` (*self*, *data*, **args*, ***kwargs*)

Return MLEs for shape (if applicable), location, and scale parameters from data.

MLE stands for Maximum Likelihood Estimate. Starting estimates for the fit are given by input arguments; for any arguments not provided with starting estimates, `self._fitstart(data)` is called to generate such.

One can hold some parameters fixed to specific values by passing in keyword arguments `f0`, `f1`, ..., `fn` (for shape parameters) and `floc` and `fscale` (for location and scale parameters, respectively).

Parameters

data [array_like] Data to use in calculating the MLEs.

arg1, arg2, arg3,...

[floats, optional] Starting value(s) for any shape-characterizing arguments (those not provided will be determined by a call to `_fitstart(data)`). No default value.

kwargs [floats, optional]

- *loc*: initial guess of the distribution's location parameter.
- *scale*: initial guess of the distribution's scale parameter.

Special keyword arguments are recognized as holding certain parameters fixed:

- `f0...fn`: hold respective shape parameters fixed. Alternatively, shape parameters to fix can be specified by name. For example, if `self.shapes == "a, b"`, `fa` and `fix_a` are equivalent to `f0`, and `fb` and `fix_b` are equivalent to `f1`.
- `floc`: hold location parameter fixed to specified value.
- `fscale`: hold scale parameter fixed to specified value.

- `optimizer` : The optimizer to use. The optimizer must take `func`, and starting position as the first two arguments, plus `args` (for extra arguments to pass to the function to be optimized) and `disp=0` to suppress output as keyword arguments.

Returns

mle_tuple [tuple of floats] MLEs for any shape parameters (if applicable), followed by those for location and scale. For most random variables, shape statistics will be returned, but there are exceptions (e.g. `norm`).

Notes

This fit is computed by maximizing a log-likelihood function, with penalty applied for samples outside of range of the distribution. The returned answer is not guaranteed to be the globally optimal MLE, it may only be locally optimal, or the optimization may fail altogether. If the data contain any of `np.nan`, `np.inf`, or `-np.inf`, the fit routine will throw a `RuntimeError`.

Examples

Generate some data to fit: draw random variates from the *beta* distribution

```
>>> from scipy.stats import beta
>>> a, b = 1., 2.
>>> x = beta.rvs(a, b, size=1000)
```

Now we can fit all four parameters (`a`, `b`, `loc` and `scale`):

```
>>> a1, b1, loc1, scale1 = beta.fit(x)
```

We can also use some prior knowledge about the dataset: let's keep `loc` and `scale` fixed:

```
>>> a1, b1, loc1, scale1 = beta.fit(x, floc=0, fscale=1)
>>> loc1, scale1
(0, 1)
```

We can also keep shape parameters fixed by using `f`-keywords. To keep the zero-th shape parameter `a` equal 1, use `f0=1` or, equivalently, `fa=1`:

```
>>> a1, b1, loc1, scale1 = beta.fit(x, fa=1, floc=0, fscale=1)
>>> a1
1
```

Not all distributions return estimates for the shape parameters. `norm` for example just returns estimates for location and scale:

```
>>> from scipy.stats import norm
>>> x = norm.rvs(a, b, size=1000, random_state=123)
>>> loc1, scale1 = norm.fit(x)
>>> loc1, scale1
(0.92087172783841631, 2.0015750750324668)
```

scipy.stats.rv_histogram.fit_loc_scale

`rv_histogram.fit_loc_scale` (*self*, *data*, **args*)

Estimate loc and scale parameters from data using 1st and 2nd moments.

Parameters

data [array_like] Data to fit.
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).

Returns

Lhat [float] Estimated location parameter for the data.
Shat [float] Estimated scale parameter for the data.

scipy.stats.rv_histogram.freeze

`rv_histogram.freeze` (*self*, **args*, ***kws*)

Freeze the distribution for the given arguments.

Parameters

arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution. Should include all the non-optional arguments, may include `loc` and `scale`.

Returns

rv_frozen [rv_frozen instance] The frozen distribution.

scipy.stats.rv_histogram.interval

`rv_histogram.interval` (*self*, *alpha*, **args*, ***kws*)

Confidence interval with equal areas around the median.

Parameters

alpha [array_like of float] Probability that an rv will be drawn from the returned range. Each value should be in the range [0, 1].
arg1, arg2, ... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).
loc [array_like, optional] location parameter, Default is 0.
scale [array_like, optional] scale parameter, Default is 1.

Returns

a, b [ndarray of float] end-points of range that contain $100 * \alpha$ % of the rv's possible values.

scipy.stats.rv_histogram.isf`rv_histogram.isf(self, q, *args, **kwargs)`Inverse survival function (inverse of *sf*) at *q* of the given RV.**Parameters**

q [array_like] upper tail probability
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

x [ndarray or scalar] Quantile corresponding to the upper tail probability *q*.

scipy.stats.rv_histogram.logcdf`rv_histogram.logcdf(self, x, *args, **kwargs)`Log of the cumulative distribution function at *x* of the given RV.**Parameters**

x [array_like] quantiles
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

logcdf [array_like] Log of the cumulative distribution function evaluated at *x*

scipy.stats.rv_histogram.logpdf`rv_histogram.logpdf(self, x, *args, **kwargs)`Log of the probability density function at *x* of the given RV.

This uses a more numerically accurate calculation if available.

Parameters

x [array_like] quantiles
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

logpdf [array_like] Log of the probability density function evaluated at *x*

scipy.stats.rv_histogram.logsf

`rv_histogram.logsf` (*self*, *x*, **args*, ***kws*)

Log of the survival function of the given RV.

Returns the log of the “survival function,” defined as $(1 - cdf)$, evaluated at *x*.

Parameters

x [array_like] quantiles
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

logsf [ndarray] Log of the survival function evaluated at *x*.

scipy.stats.rv_histogram.mean

`rv_histogram.mean` (*self*, **args*, ***kws*)

Mean of the distribution.

Parameters

arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

mean [float] the mean of the distribution

scipy.stats.rv_histogram.median

`rv_histogram.median` (*self*, **args*, ***kws*)

Median of the distribution.

Parameters

arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] Location parameter, Default is 0.
scale [array_like, optional] Scale parameter, Default is 1.

Returns

median [float] The median of the distribution.

See also:

[*rv_discrete.ppf*](#)

Inverse of the CDF

scipy.stats.rv_histogram.moment

`rv_histogram.moment` (*self*, *n*, **args*, ***kwargs*)
n-th order non-central moment of distribution.

Parameters

n [int, n >= 1] Order of moment.
arg1, arg2, arg3,... [float] The shape parameter(s) for the distribution (see docstring of the instance object for more information).
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

scipy.stats.rv_histogram.nnlf

`rv_histogram.nnlf` (*self*, *theta*, *x*)
Return negative loglikelihood function.

Notes

This is $-\text{sum}(\log \text{pdf}(x, \text{theta}), \text{axis}=0)$ where *theta* are the parameters (including loc and scale).

scipy.stats.rv_histogram.pdf

`rv_histogram.pdf` (*self*, *x*, **args*, ***kwargs*)
Probability density function at *x* of the given RV.

Parameters

x [array_like] quantiles
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

pdf [ndarray] Probability density function evaluated at *x*

scipy.stats.rv_histogram.ppf

`rv_histogram.ppf` (*self*, *q*, **args*, ***kwargs*)
Percent point function (inverse of *cdf*) at *q* of the given RV.

Parameters

q [array_like] lower tail probability
arg1, arg2, arg3,... [array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)
loc [array_like, optional] location parameter (default=0)
scale [array_like, optional] scale parameter (default=1)

Returns

x [array_like] quantile corresponding to the lower tail probability q .

scipy.stats.rv_histogram.rvs

`rv_histogram.rvs` (*self*, *args, **kwargs)

Random variates of given type.

Parameters

arg1, arg2, arg3,...

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).

loc [array_like, optional] Location parameter (default=0).

scale [array_like, optional] Scale parameter (default=1).

size [int or tuple of ints, optional] Defining number of random variates (default is 1).

random_state

[{None, int, *RandomState*, *Generator*}, optional] If *seed* is *None* the *RandomState* singleton is used. If *seed* is an int, a new *RandomState* instance is used, seeded with *seed*. If *seed* is already a *RandomState* or *Generator* instance, then that object is used. Default is *None*.

Returns

rvs [ndarray or scalar] Random variates of given *size*.

scipy.stats.rv_histogram.sf

`rv_histogram.sf` (*self*, *x*, *args, **kwargs)

Survival function ($1 - cdf$) at *x* of the given RV.

Parameters

x [array_like] quantiles

arg1, arg2, arg3,...

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] location parameter (default=0)

scale [array_like, optional] scale parameter (default=1)

Returns

sf [array_like] Survival function evaluated at *x*

scipy.stats.rv_histogram.stats

`rv_histogram.stats` (*self*, *args, **kwargs)

Some statistics of the given RV.

Parameters

arg1, arg2, arg3,...

[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] location parameter (default=0)

scale [array_like, optional (continuous RVs only)] scale parameter (default=1)

moments [str, optional] composed of letters ['mvsk'] defining which moments to compute: 'm' = mean, 'v' = variance, 's' = (Fisher's) skew, 'k' = (Fisher's) kurtosis. (default is 'mv')

Returns

stats [sequence] of requested moments.

scipy.stats.rv_histogram.std

`rv_histogram.std` (*self*, *args, **kwargs)
Standard deviation of the distribution.

Parameters

arg1, arg2, arg3,...
[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] location parameter (default=0)

scale [array_like, optional] scale parameter (default=1)

Returns

std [float] standard deviation of the distribution

scipy.stats.rv_histogram.support

`rv_histogram.support` (*self*, *args, **kwargs)
Return the support of the distribution.

Parameters

arg1, arg2, ...
[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information).

loc [array_like, optional] location parameter, Default is 0.

scale [array_like, optional] scale parameter, Default is 1.

Returns

a, b [float] end-points of the distribution's support.

scipy.stats.rv_histogram.var

`rv_histogram.var` (*self*, *args, **kwargs)
Variance of the distribution.

Parameters

arg1, arg2, arg3,...
[array_like] The shape parameter(s) for the distribution (see docstring of the instance object for more information)

loc [array_like, optional] location parameter (default=0)

scale [array_like, optional] scale parameter (default=1)

Returns

var [float] the variance of the distribution

6.29.4 Continuous distributions

<i>alpha</i> (*args, **kwargs)	An alpha continuous random variable.
<i>anglit</i> (*args, **kwargs)	An anglit continuous random variable.
<i>arcsine</i> (*args, **kwargs)	An arcsine continuous random variable.
<i>argus</i> (*args, **kwargs)	Argus distribution
<i>beta</i> (*args, **kwargs)	A beta continuous random variable.
<i>betaprime</i> (*args, **kwargs)	A beta prime continuous random variable.
<i>bradford</i> (*args, **kwargs)	A Bradford continuous random variable.
<i>burr</i> (*args, **kwargs)	A Burr (Type III) continuous random variable.
<i>burr12</i> (*args, **kwargs)	A Burr (Type XII) continuous random variable.
<i>cauchy</i> (*args, **kwargs)	A Cauchy continuous random variable.
<i>chi</i> (*args, **kwargs)	A chi continuous random variable.
<i>chi2</i> (*args, **kwargs)	A chi-squared continuous random variable.
<i>cosine</i> (*args, **kwargs)	A cosine continuous random variable.
<i>crystalball</i> (*args, **kwargs)	Crystalball distribution
<i>dgamma</i> (*args, **kwargs)	A double gamma continuous random variable.
<i>dweibull</i> (*args, **kwargs)	A double Weibull continuous random variable.
<i>erlang</i> (*args, **kwargs)	An Erlang continuous random variable.
<i>expon</i> (*args, **kwargs)	An exponential continuous random variable.
<i>exponnorm</i> (*args, **kwargs)	An exponentially modified Normal continuous random variable.
<i>exponweib</i> (*args, **kwargs)	An exponentiated Weibull continuous random variable.
<i>exponpow</i> (*args, **kwargs)	An exponential power continuous random variable.
<i>f</i> (*args, **kwargs)	An F continuous random variable.
<i>fatiguelife</i> (*args, **kwargs)	A fatigue-life (Birnbaum-Saunders) continuous random variable.
<i>fisk</i> (*args, **kwargs)	A Fisk continuous random variable.
<i>foldcauchy</i> (*args, **kwargs)	A folded Cauchy continuous random variable.
<i>foldnorm</i> (*args, **kwargs)	A folded normal continuous random variable.
<i>genlogistic</i> (*args, **kwargs)	A generalized logistic continuous random variable.
<i>gennorm</i> (*args, **kwargs)	A generalized normal continuous random variable.
<i>genpareto</i> (*args, **kwargs)	A generalized Pareto continuous random variable.
<i>genexpon</i> (*args, **kwargs)	A generalized exponential continuous random variable.
<i>genextreme</i> (*args, **kwargs)	A generalized extreme value continuous random variable.
<i>gausshyper</i> (*args, **kwargs)	A Gauss hypergeometric continuous random variable.
<i>gamma</i> (*args, **kwargs)	A gamma continuous random variable.
<i>gengamma</i> (*args, **kwargs)	A generalized gamma continuous random variable.
<i>genhalflogistic</i> (*args, **kwargs)	A generalized half-logistic continuous random variable.
<i>geninvgauss</i> (*args, **kwargs)	A Generalized Inverse Gaussian continuous random variable.
<i>gilbrat</i> (*args, **kwargs)	A Gilbrat continuous random variable.
<i>gompertz</i> (*args, **kwargs)	A Gompertz (or truncated Gumbel) continuous random variable.
<i>gumbel_r</i> (*args, **kwargs)	A right-skewed Gumbel continuous random variable.
<i>gumbel_l</i> (*args, **kwargs)	A left-skewed Gumbel continuous random variable.
<i>halfcauchy</i> (*args, **kwargs)	A Half-Cauchy continuous random variable.
<i>halflogistic</i> (*args, **kwargs)	A half-logistic continuous random variable.
<i>halfnorm</i> (*args, **kwargs)	A half-normal continuous random variable.
<i>halfgennorm</i> (*args, **kwargs)	The upper half of a generalized normal continuous random variable.

continues on next page

Table 258 – continued from previous page

<i>hypsecant</i> (*args, **kwds)	A hyperbolic secant continuous random variable.
<i>invgamma</i> (*args, **kwds)	An inverted gamma continuous random variable.
<i>invgauss</i> (*args, **kwds)	An inverse Gaussian continuous random variable.
<i>invweibull</i> (*args, **kwds)	An inverted Weibull continuous random variable.
<i>johnsonsb</i> (*args, **kwds)	A Johnson SB continuous random variable.
<i>johnsonsu</i> (*args, **kwds)	A Johnson SU continuous random variable.
<i>kappa4</i> (*args, **kwds)	Kappa 4 parameter distribution.
<i>kappa3</i> (*args, **kwds)	Kappa 3 parameter distribution.
<i>ksone</i> (*args, **kwds)	Kolmogorov-Smirnov one-sided test statistic distribution.
<i>kstwo</i> (*args, **kwds)	Kolmogorov-Smirnov two-sided test statistic distribution.
<i>kstwobign</i> (*args, **kwds)	Limiting distribution of scaled Kolmogorov-Smirnov two-sided test statistic.
<i>laplace</i> (*args, **kwds)	A Laplace continuous random variable.
<i>laplace_asymmetric</i> (*args, **kwds)	An asymmetric Laplace continuous random variable.
<i>levy</i> (*args, **kwds)	A Levy continuous random variable.
<i>levy_l</i> (*args, **kwds)	A left-skewed Levy continuous random variable.
<i>levy_stable</i> (*args, **kwds)	A Levy-stable continuous random variable.
<i>logistic</i> (*args, **kwds)	A logistic (or Sech-squared) continuous random variable.
<i>loggamma</i> (*args, **kwds)	A log gamma continuous random variable.
<i>loglaplace</i> (*args, **kwds)	A log-Laplace continuous random variable.
<i>lognorm</i> (*args, **kwds)	A lognormal continuous random variable.
<i>loguniform</i> (*args, **kwds)	A loguniform or reciprocal continuous random variable.
<i>lomax</i> (*args, **kwds)	A Lomax (Pareto of the second kind) continuous random variable.
<i>maxwell</i> (*args, **kwds)	A Maxwell continuous random variable.
<i>mielke</i> (*args, **kwds)	A Mielke Beta-Kappa / Dagum continuous random variable.
<i>moyal</i> (*args, **kwds)	A Moyal continuous random variable.
<i>nakagami</i> (*args, **kwds)	A Nakagami continuous random variable.
<i>ncx2</i> (*args, **kwds)	A non-central chi-squared continuous random variable.
<i>ncf</i> (*args, **kwds)	A non-central F distribution continuous random variable.
<i>nct</i> (*args, **kwds)	A non-central Student's t continuous random variable.
<i>norm</i> (*args, **kwds)	A normal continuous random variable.
<i>norminvgauss</i> (*args, **kwds)	A Normal Inverse Gaussian continuous random variable.
<i>pareto</i> (*args, **kwds)	A Pareto continuous random variable.
<i>pearson3</i> (*args, **kwds)	A pearson type III continuous random variable.
<i>powerlaw</i> (*args, **kwds)	A power-function continuous random variable.
<i>powerlognorm</i> (*args, **kwds)	A power log-normal continuous random variable.
<i>powernorm</i> (*args, **kwds)	A power normal continuous random variable.
<i>rdist</i> (*args, **kwds)	An R-distributed (symmetric beta) continuous random variable.
<i>rayleigh</i> (*args, **kwds)	A Rayleigh continuous random variable.
<i>rice</i> (*args, **kwds)	A Rice continuous random variable.
<i>recipinvgauss</i> (*args, **kwds)	A reciprocal inverse Gaussian continuous random variable.
<i>semicircular</i> (*args, **kwds)	A semicircular continuous random variable.
<i>skewnorm</i> (*args, **kwds)	A skew-normal random variable.
<i>t</i> (*args, **kwds)	A Student's t continuous random variable.
<i>trapezoid</i> (*args, **kwds)	A trapezoidal continuous random variable.
<i>triang</i> (*args, **kwds)	A triangular continuous random variable.

continues on next page

Table 258 – continued from previous page

<code>truncexpon(*args, **kwargs)</code>	A truncated exponential continuous random variable.
<code>truncnorm(*args, **kwargs)</code>	A truncated normal continuous random variable.
<code>tukeylambd(*args, **kwargs)</code>	A Tukey-Lambda continuous random variable.
<code>uniform(*args, **kwargs)</code>	A uniform continuous random variable.
<code>vonmises(*args, **kwargs)</code>	A Von Mises continuous random variable.
<code>vonmises_line(*args, **kwargs)</code>	A Von Mises continuous random variable.
<code>wald(*args, **kwargs)</code>	A Wald continuous random variable.
<code>weibull_min(*args, **kwargs)</code>	Weibull minimum continuous random variable.
<code>weibull_max(*args, **kwargs)</code>	Weibull maximum continuous random variable.
<code>wrapcauchy(*args, **kwargs)</code>	A wrapped Cauchy continuous random variable.

scipy.stats.alpha

`scipy.stats.alpha(*args, **kwargs)` = `<scipy.stats._continuous_distns.alpha_gen object>`

An alpha continuous random variable.

As an instance of the `rv_continuous` class, `alpha` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `alpha` ([1], [2]) is:

$$f(x, a) = \frac{1}{x^2 \Phi(a) \sqrt{2\pi}} * \exp\left(-\frac{1}{2}(a - 1/x)^2\right)$$

where Φ is the normal CDF, $x > 0$, and $a > 0$.

`alpha` takes `a` as a shape parameter.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `alpha.pdf(x, a, loc, scale)` is identically equivalent to `alpha.pdf(y, a) / scale` with `y = (x - loc) / scale`. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

[1], [2]

Examples

```
>>> from scipy.stats import alpha
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a = 3.57
>>> mean, var, skew, kurt = alpha.stats(a, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(alpha.ppf(0.01, a),
...                 alpha.ppf(0.99, a), 100)
>>> ax.plot(x, alpha.pdf(x, a),
...         'r-', lw=5, alpha=0.6, label='alpha pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = alpha(a)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = alpha.ppf([0.001, 0.5, 0.999], a)
>>> np.allclose([0.001, 0.5, 0.999], alpha.cdf(vals, a))
True
```

Generate random numbers:

```
>>> r = alpha.rvs(a, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(a, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, a, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, a, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats anglit

`scipy.stats.anglit(*args, **kws) = <scipy.stats._continuous_distns.anglit_gen object>`

An `anglit` continuous random variable.

As an instance of the `rv_continuous` class, `anglit` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `anglit` is:

$$f(x) = \sin(2x + \pi/2) = \cos(2x)$$

for $-\pi/4 \leq x \leq \pi/4$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `anglit.pdf(x, loc, scale)` is identically equivalent to `anglit.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import anglit
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = anglit.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(anglit.ppf(0.01),
...                 anglit.ppf(0.99), 100)
>>> ax.plot(x, anglit.pdf(x),
...         'r-', lw=5, alpha=0.6, label='anglit pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = anglit()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = anglit.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], anglit.cdf(vals))
True
```

Generate random numbers:

```
>>> r = anglit.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains <i>alpha</i> percent of the distribution

scipy.stats.arcsine

`scipy.stats.arcsine(*args, **kwargs)` = `<scipy.stats._continuous_distns.arcsine_gen object>`

An arcsine continuous random variable.

As an instance of the `rv_continuous` class, `arcsine` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `arcsine` is:

$$f(x) = \frac{1}{\pi\sqrt{x(1-x)}}$$

for $0 < x < 1$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `arcsine.pdf(x, loc, scale)` is identically equivalent to `arcsine.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import arcsine
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = arcsine.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(arcsine.ppf(0.01),
...                 arcsine.ppf(0.99), 100)
>>> ax.plot(x, arcsine.pdf(x),
...         'r-', lw=5, alpha=0.6, label='arcsine pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = arcsine()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = arcsine.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], arcsine.cdf(vals))
True
```

Generate random numbers:

```
>>> r = arcsine.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.argus

```
scipy.stats.argus(*args, **kws) = <scipy.stats._continuous_distns.argus_gen
object>
```

Argus distribution

As an instance of the *rv_continuous* class, *argus* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *argus* is:

$$f(x, \chi) = \frac{\chi^3}{\sqrt{2\pi}\Psi(\chi)} x \sqrt{1-x^2} \exp(-\chi^2(1-x^2)/2)$$

for $0 < x < 1$ and $\chi > 0$, where

$$\Psi(\chi) = \Phi(\chi) - \chi\phi(\chi) - 1/2$$

with Φ and ϕ being the CDF and PDF of a standard normal distribution, respectively.

argus takes χ as shape a parameter.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `argus.pdf(x, chi, loc, scale)` is identically equivalent to `argus.pdf(y, chi) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

New in version 0.19.0.

References

[1]

Examples

```
>>> from scipy.stats import argus
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> chi = 1
>>> mean, var, skew, kurt = argus.stats(chi, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(argus.ppf(0.01, chi),
...                 argus.ppf(0.99, chi), 100)
>>> ax.plot(x, argus.pdf(x, chi),
...        'r-', lw=5, alpha=0.6, label='argus pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = argus(chi)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = argus.ppf([0.001, 0.5, 0.999], chi)
>>> np.allclose([0.001, 0.5, 0.999], argus.cdf(vals, chi))
True
```

Generate random numbers:

```
>>> r = argus.rvs(chi, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(chi, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, chi, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, chi, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, chi, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, chi, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, chi, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, chi, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, chi, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, chi, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, chi, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(chi, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(chi, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(chi,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(chi, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(chi, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(chi, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(chi, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, chi, loc=0, scale=1)</code>	Endpoints of the range that contains <i>alpha</i> percent of the distribution

scipy.stats.beta

`scipy.stats.beta(*args, **kws)` = <scipy.stats._continuous_distns.beta_gen object>

A beta continuous random variable.

As an instance of the `rv_continuous` class, `beta` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `beta` is:

$$f(x, a, b) = \frac{\Gamma(a+b)x^{a-1}(1-x)^{b-1}}{\Gamma(a)\Gamma(b)}$$

for $0 \leq x \leq 1$, $a > 0$, $b > 0$, where Γ is the gamma function (`scipy.special.gamma`).

`beta` takes `a` and `b` as shape parameters.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `beta.pdf(x, a, b, loc, scale)` is identically equivalent to `beta.pdf(y, a, b) / scale` with `y = (x - loc) / scale`. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import beta
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a, b = 2.31, 0.627
>>> mean, var, skew, kurt = beta.stats(a, b, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(beta.ppf(0.01, a, b),
...                 beta.ppf(0.99, a, b), 100)
>>> ax.plot(x, beta.pdf(x, a, b),
...         'r-', lw=5, alpha=0.6, label='beta pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = beta(a, b)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = beta.ppf([0.001, 0.5, 0.999], a, b)
>>> np.allclose([0.001, 0.5, 0.999], beta.cdf(vals, a, b))
True
```

Generate random numbers:

```
>>> r = beta.rvs(a, b, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(a, b, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, b, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, b, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, b, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, b, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, b, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, b, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, b, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, a, b, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, a, b, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, b, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, b, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a, b), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, b, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, b, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, b, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, b, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, b, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.betaprime

```
scipy.stats.betaprime(*args, **kws) = <scipy.stats._continuous_distns.
betaprime_gen object>
```

A beta prime continuous random variable.

As an instance of the *rv_continuous* class, *betaprime* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *betaprime* is:

$$f(x, a, b) = \frac{x^{a-1}(1+x)^{-a-b}}{\beta(a, b)}$$

for $x \geq 0$, $a > 0$, $b > 0$, where $\beta(a, b)$ is the beta function (see [scipy.special.beta](#)).

betaprime takes *a* and *b* as shape parameters.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `betaprime.pdf(x, a, b, loc, scale)` is identically equivalent to `betaprime.pdf(y, a, b) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import betaprime
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a, b = 5, 6
>>> mean, var, skew, kurt = betaprime.stats(a, b, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(betaprime.ppf(0.01, a, b),
...                 betaprime.ppf(0.99, a, b), 100)
>>> ax.plot(x, betaprime.pdf(x, a, b),
...         'r-', lw=5, alpha=0.6, label='betaprime pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = betaprime(a, b)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = betaprime.ppf([0.001, 0.5, 0.999], a, b)
>>> np.allclose([0.001, 0.5, 0.999], betaprime.cdf(vals, a, b))
True
```

Generate random numbers:

```
>>> r = betaprime.rvs(a, b, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(a, b, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, b, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, b, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, b, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, b, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, b, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, b, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, b, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, a, b, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, a, b, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, b, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, b, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a, b), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, b, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, b, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, b, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, b, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, b, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.bradford

```
scipy.stats.bradford(*args, **kwargs) = <scipy.stats._continuous_distns.
    bradford_gen object>
```

A Bradford continuous random variable.

As an instance of the *rv_continuous* class, *bradford* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *bradford* is:

$$f(x, c) = \frac{c}{\log(1+c)(1+cx)}$$

for $0 \leq x \leq 1$ and $c > 0$.

bradford takes *c* as a shape parameter for *c*.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `bradford.pdf(x, c, loc, scale)` is identically equivalent to `bradford.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import bradford
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 0.299
>>> mean, var, skew, kurt = bradford.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(bradford.ppf(0.01, c),
...                 bradford.ppf(0.99, c), 100)
>>> ax.plot(x, bradford.pdf(x, c),
...        'r-', lw=5, alpha=0.6, label='bradford pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = bradford(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = bradford.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], bradford.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = bradford.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.burr

`scipy.stats.burr(*args, **kws) = <scipy.stats._continuous_distns.burr_gen object>`

A Burr (Type III) continuous random variable.

As an instance of the `rv_continuous` class, `burr` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

`fisk`

a special case of either `burr` or `burr12` with `d=1`

`burr12`

Burr Type XII distribution

`mielke`

Mielke Beta-Kappa / Dagum distribution

Notes

The probability density function for *burr* is:

$$f(x, c, d) = cdx^{-c-1}/(1+x^{-c})^{d+1}$$

for $x \geq 0$ and $c, d > 0$.

burr takes c and d as shape parameters.

This is the PDF corresponding to the third CDF given in Burr's list; specifically, it is equation (11) in Burr's paper [1]. The distribution is also commonly referred to as the Dagum distribution [2]. If the parameter $c < 1$ then the mean of the distribution does not exist and if $c < 2$ the variance does not exist [2]. The PDF is finite at the left endpoint $x = 0$ if $c * d \geq 1$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `burr.pdf(x, c, d, loc, scale)` is identically equivalent to `burr.pdf(y, c, d) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

[1], [2], [3]

Examples

```
>>> from scipy.stats import burr
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c, d = 10.5, 4.3
>>> mean, var, skew, kurt = burr.stats(c, d, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(burr.ppf(0.01, c, d),
...                 burr.ppf(0.99, c, d), 100)
>>> ax.plot(x, burr.pdf(x, c, d),
...         'r-', lw=5, alpha=0.6, label='burr pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = burr(c, d)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = burr.ppf([0.001, 0.5, 0.999], c, d)
>>> np.allclose([0.001, 0.5, 0.999], burr.cdf(vals, c, d))
True
```

Generate random numbers:

```
>>> r = burr.rvs(c, d, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, d, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, d, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, d, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, d, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, d, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, d, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, d, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, d, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, c, d, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, c, d, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, d, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, d, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c, d), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, d, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, d, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, d, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, d, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, d, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.burr12

```
scipy.stats.burr12(*args, **kwds) = <scipy.stats._continuous_distns.burr12_gen
object>
```

A Burr (Type XII) continuous random variable.

As an instance of the *rv_continuous* class, *burr12* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

fisk

a special case of either *burr* or *burr12* with *d*=1

burr

Burr Type III distribution

Notes

The probability density function for *burr* is:

$$f(x, c, d) = cdx^{c-1}/(1+x^c)^{d+1}$$

for $x \geq 0$ and $c, d > 0$.

burr12 takes *c* and *d* as shape parameters for *c* and *d*.

This is the PDF corresponding to the twelfth CDF given in Burr’s list; specifically, it is equation (20) in Burr’s paper [1].

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `burr12.pdf(x, c, d, loc, scale)` is identically equivalent to `burr12.pdf(y, c, d) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

The Burr type 12 distribution is also sometimes referred to as the Singh-Maddala distribution from NIST [2].

References

[1], [2], [3]

Examples

```
>>> from scipy.stats import burr12
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c, d = 10, 4
>>> mean, var, skew, kurt = burr12.stats(c, d, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(burr12.ppf(0.01, c, d),
...                 burr12.ppf(0.99, c, d), 100)
>>> ax.plot(x, burr12.pdf(x, c, d),
...         'r-', lw=5, alpha=0.6, label='burr12 pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = burr12(c, d)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = burr12.ppf([0.001, 0.5, 0.999], c, d)
>>> np.allclose([0.001, 0.5, 0.999], burr12.cdf(vals, c, d))
True
```

Generate random numbers:

```
>>> r = burr12.rvs(c, d, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, d, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, d, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, d, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, d, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, d, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, d, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, d, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, d, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, c, d, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, c, d, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, d, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, d, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c, d), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, d, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, d, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, d, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, d, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, d, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.cauchy

`scipy.stats.cauchy(*args, **kws) = <scipy.stats._continuous_distns.cauchy_gen object>`

A Cauchy continuous random variable.

As an instance of the `rv_continuous` class, `cauchy` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `cauchy` is

$$f(x) = \frac{1}{\pi(1+x^2)}$$

for a real number x .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `cauchy.pdf(x, loc, scale)` is identically equivalent to `cauchy.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import cauchy
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = cauchy.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(cauchy.ppf(0.01),
...                 cauchy.ppf(0.99), 100)
>>> ax.plot(x, cauchy.pdf(x),
...         'r-', lw=5, alpha=0.6, label='cauchy pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = cauchy()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = cauchy.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], cauchy.cdf(vals))
True
```

Generate random numbers:

```
>>> r = cauchy.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs (loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf (x, loc=0, scale=1)	Probability density function.
logpdf (x, loc=0, scale=1)	Log of the probability density function.
cdf (x, loc=0, scale=1)	Cumulative distribution function.
logcdf (x, loc=0, scale=1)	Log of the cumulative distribution function.
sf (x, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf (x, loc=0, scale=1)	Log of the survival function.
ppf (q, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf (q, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment (n, loc=0, scale=1)	Non-central moment of order <i>n</i>
stats (loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy (loc=0, scale=1)	(Differential) entropy of the RV.
fit (data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect (func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)	Expected value of a function (of one argument) with respect to the distribution.
median (loc=0, scale=1)	Median of the distribution.
mean (loc=0, scale=1)	Mean of the distribution.
var (loc=0, scale=1)	Variance of the distribution.
std (loc=0, scale=1)	Standard deviation of the distribution.
interval (alpha, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.chi

```
scipy.stats.chi(*args, **kwargs) = <scipy.stats._continuous_distns.chi_gen object>
```

A chi continuous random variable.

As an instance of the `rv_continuous` class, `chi` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `chi` is:

$$f(x, k) = \frac{1}{2^{k/2-1}\Gamma(k/2)} x^{k-1} \exp(-x^2/2)$$

for $x \geq 0$ and $k > 0$ (degrees of freedom, denoted `df` in the implementation). Γ is the gamma function (`scipy.special.gamma`).

Special cases of `chi` are:

- `chi(1, loc, scale)` is equivalent to `halfnorm`
- `chi(2, 0, scale)` is equivalent to `rayleigh`
- `chi(3, 0, scale)` is equivalent to `maxwell`

`chi` takes `df` as a shape parameter.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `chi.pdf(x, df, loc, scale)` is identically equivalent to `chi.pdf(y, df) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import chi
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> df = 78
>>> mean, var, skew, kurt = chi.stats(df, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(chi.ppf(0.01, df),
...                 chi.ppf(0.99, df), 100)
>>> ax.plot(x, chi.pdf(x, df),
...         'r-', lw=5, alpha=0.6, label='chi pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = chi(df)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = chi.ppf([0.001, 0.5, 0.999], df)
>>> np.allclose([0.001, 0.5, 0.999], chi.cdf(vals, df))
True
```

Generate random numbers:

```
>>> r = chi.rvs(df, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs(df, loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf(x, df, loc=0, scale=1)	Probability density function.
logpdf(x, df, loc=0, scale=1)	Log of the probability density function.
cdf(x, df, loc=0, scale=1)	Cumulative distribution function.
logcdf(x, df, loc=0, scale=1)	Log of the cumulative distribution function.
sf(x, df, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(x, df, loc=0, scale=1)	Log of the survival function.
ppf(q, df, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, df, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment(n, df, loc=0, scale=1)	Non-central moment of order <i>n</i>
stats(df, loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(df, loc=0, scale=1)	(Differential) entropy of the RV.
fit(data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect(func, args=(df,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)	Expected value of a function (of one argument) with respect to the distribution.
median(df, loc=0, scale=1)	Median of the distribution.
mean(df, loc=0, scale=1)	Mean of the distribution.
var(df, loc=0, scale=1)	Variance of the distribution.
std(df, loc=0, scale=1)	Standard deviation of the distribution.
interval(alpha, df, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.chi2

```
scipy.stats.chi2(*args, **kws) = <scipy.stats._continuous_distns.chi2_gen object>
```

A chi-squared continuous random variable.

For the noncentral chi-square distribution, see [ncx2](#).

As an instance of the *rv_continuous* class, *chi2* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

[ncx2](#)

Notes

The probability density function for `chi2` is:

$$f(x, k) = \frac{1}{2^{k/2} \Gamma(k/2)} x^{k/2-1} \exp(-x/2)$$

for $x > 0$ and $k > 0$ (degrees of freedom, denoted `df` in the implementation).

`chi2` takes `df` as a shape parameter.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `chi2.pdf(x, df, loc, scale)` is identically equivalent to `chi2.pdf(y, df) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import chi2
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> df = 55
>>> mean, var, skew, kurt = chi2.stats(df, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(chi2.ppf(0.01, df),
...                 chi2.ppf(0.99, df), 100)
>>> ax.plot(x, chi2.pdf(x, df),
...         'r-', lw=5, alpha=0.6, label='chi2 pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = chi2(df)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = chi2.ppf([0.001, 0.5, 0.999], df)
>>> np.allclose([0.001, 0.5, 0.999], chi2.cdf(vals, df))
True
```

Generate random numbers:

```
>>> r = chi2.rvs(df, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs(df, loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf(x, df, loc=0, scale=1)	Probability density function.
logpdf(x, df, loc=0, scale=1)	Log of the probability density function.
cdf(x, df, loc=0, scale=1)	Cumulative distribution function.
logcdf(x, df, loc=0, scale=1)	Log of the cumulative distribution function.
sf(x, df, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(x, df, loc=0, scale=1)	Log of the survival function.
ppf(q, df, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, df, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment(n, df, loc=0, scale=1)	Non-central moment of order <i>n</i>
stats(df, loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(df, loc=0, scale=1)	(Differential) entropy of the RV.
fit(data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect(func, args=(df,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)	Expected value of a function (of one argument) with respect to the distribution.
median(df, loc=0, scale=1)	Median of the distribution.
mean(df, loc=0, scale=1)	Mean of the distribution.
var(df, loc=0, scale=1)	Variance of the distribution.
std(df, loc=0, scale=1)	Standard deviation of the distribution.
interval(alpha, df, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.cosine

`scipy.stats.cosine(*args, **kwargs) = <scipy.stats._continuous_distns.cosine_gen object>`

A cosine continuous random variable.

As an instance of the `rv_continuous` class, `cosine` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The cosine distribution is an approximation to the normal distribution. The probability density function for `cosine` is:

$$f(x) = \frac{1}{2\pi}(1 + \cos(x))$$

for $-\pi \leq x \leq \pi$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `cosine.pdf(x, loc, scale)` is identically equivalent to `cosine.pdf(y) / scale` with `y = (x - loc) / scale`. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import cosine
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = cosine.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(cosine.ppf(0.01),
...                 cosine.ppf(0.99), 100)
>>> ax.plot(x, cosine.pdf(x),
...         'r-', lw=5, alpha=0.6, label='cosine pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = cosine()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = cosine.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], cosine.cdf(vals))
True
```

Generate random numbers:

```
>>> r = cosine.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.crystalball

```
scipy.stats.crystalball(*args, **kws) = <scipy.stats._continuous_distns.
    crystalball_gen object>
```

Crystalball distribution

As an instance of the *rv_continuous* class, *crystalball* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *crystalball* is:

$$f(x, \beta, m) = \begin{cases} N \exp(-x^2/2), & \text{for } x > -\beta \\ NA(B - x)^{-m} & \text{for } x \leq -\beta \end{cases}$$

where $A = (m/|\beta|)^n \exp(-\beta^2/2)$, $B = m/|\beta| - |\beta|$ and N is a normalisation constant.

crystalball takes $\beta > 0$ and $m > 1$ as shape parameters. β defines the point where the pdf changes from a power-law to a Gaussian distribution. m is the power of the power-law tail.

References

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `crystalball.pdf(x, beta, m, loc, scale)` is identically equivalent to `crystalball.pdf(y, beta, m) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

New in version 0.19.0.

[1]

Examples

```
>>> from scipy.stats import crystalball
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> beta, m = 2, 3
>>> mean, var, skew, kurt = crystalball.stats(beta, m, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(crystalball.ppf(0.01, beta, m),
...                 crystalball.ppf(0.99, beta, m), 100)
>>> ax.plot(x, crystalball.pdf(x, beta, m),
...         'r-', lw=5, alpha=0.6, label='crystalball pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = crystalball(beta, m)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = crystalball.ppf([0.001, 0.5, 0.999], beta, m)
>>> np.allclose([0.001, 0.5, 0.999], crystalball.cdf(vals, beta, m))
True
```

Generate random numbers:

```
>>> r = crystalball.rvs(beta, m, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(beta, m, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, beta, m, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, beta, m, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, beta, m, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, beta, m, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, beta, m, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, beta, m, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, beta, m, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, beta, m, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, beta, m, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(beta, m, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(beta, m, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(beta, m), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(beta, m, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(beta, m, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(beta, m, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(beta, m, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, beta, m, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.dgamma

`scipy.stats.dgamma(*args, **kwargs) = <scipy.stats._continuous_distns.dgamma_gen object>`

A double gamma continuous random variable.

As an instance of the `rv_continuous` class, `dgamma` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `dgamma` is:

$$f(x, a) = \frac{1}{2\Gamma(a)} |x|^{a-1} \exp(-|x|)$$

for a real number x and $a > 0$. Γ is the gamma function (`scipy.special.gamma`).

`dgamma` takes `a` as a shape parameter for a .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `dgamma.pdf(x, a, loc, scale)` is identically equivalent to `dgamma.pdf(y, a) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import dgamma
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a = 1.1
>>> mean, var, skew, kurt = dgamma.stats(a, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(dgamma.ppf(0.01, a),
...                 dgamma.ppf(0.99, a), 100)
>>> ax.plot(x, dgamma.pdf(x, a),
...         'r-', lw=5, alpha=0.6, label='dgamma pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = dgamma(a)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = dgamma.ppf([0.001, 0.5, 0.999], a)
>>> np.allclose([0.001, 0.5, 0.999], dgamma.cdf(vals, a))
True
```

Generate random numbers:

```
>>> r = dgamma.rvs(a, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(a, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, a, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, a, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.dweibull

```
scipy.stats.dweibull(*args, **kws) = <scipy.stats._continuous_distns.
dweibull_gen object>
```

A double Weibull continuous random variable.

As an instance of the *rv_continuous* class, *dweibull* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *dweibull* is given by

$$f(x, c) = c/2|x|^{c-1} \exp(-|x|^c)$$

for a real number *x* and $c > 0$.

dweibull takes *c* as a shape parameter for *c*.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `dweibull.pdf(x, c, loc, scale)` is identically equivalent to `dweibull.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import dweibull
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 2.07
>>> mean, var, skew, kurt = dweibull.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(dweibull.ppf(0.01, c),
...                 dweibull.ppf(0.99, c), 100)
>>> ax.plot(x, dweibull.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='dweibull pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = dweibull(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = dweibull.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], dweibull.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = dweibull.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.erlang

`scipy.stats.erlang(*args, **kwargs) = <scipy.stats._continuous_distns.erlang_gen object>`

An Erlang continuous random variable.

As an instance of the `rv_continuous` class, `erlang` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

[gamma](#)

Notes

The Erlang distribution is a special case of the Gamma distribution, with the shape parameter a an integer. Note that this restriction is not enforced by `erlang`. It will, however, generate a warning the first time a non-integer value is used for the shape parameter.

Refer to [gamma](#) for examples.

Methods

<code>rvs(a, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, a, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, a, loc=0, scale=1)</code>	Non-central moment of order n
<code>stats(a, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwargs)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.expon

`scipy.stats.expon(*args, **kwargs)` = `<scipy.stats._continuous_distns.expon_gen object>`

An exponential continuous random variable.

As an instance of the `rv_continuous` class, `expon` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `expon` is:

$$f(x) = \exp(-x)$$

for $x \geq 0$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `expon.pdf(x, loc, scale)` is identically equivalent to `expon.pdf(y) / scale` with $y = (x - loc) / scale$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

A common parameterization for `expon` is in terms of the rate parameter `lambda`, such that `pdf = lambda * exp(-lambda * x)`. This parameterization corresponds to using `scale = 1 / lambda`.

Examples

```
>>> from scipy.stats import expon
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = expon.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(expon.ppf(0.01),
...                 expon.ppf(0.99), 100)
>>> ax.plot(x, expon.pdf(x),
...         'r-', lw=5, alpha=0.6, label='expon pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = expon()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = expon.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], expon.cdf(vals))
True
```

Generate random numbers:

```
>>> r = expon.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.exponnorm

`scipy.stats.exponnorm(*args, **kws) = <scipy.stats._continuous_distns.exponnorm_gen object>`

An exponentially modified Normal continuous random variable.

As an instance of the `rv_continuous` class, `exponnorm` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `exponnorm` is:

$$f(x, K) = \frac{1}{2K} \exp\left(\frac{1}{2K^2} - x/K\right) \operatorname{erfc}\left(-\frac{x - 1/K}{\sqrt{2}}\right)$$

where x is a real number and $K > 0$.

It can be thought of as the sum of a standard normal random variable and an independent exponentially distributed random variable with rate $1/K$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `exponnorm.pdf(x, K, loc, scale)` is identically equivalent to `exponnorm.pdf(y, K) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location

of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

An alternative parameterization of this distribution (for example, in [Wikipedia](#)) involves three parameters, μ , λ and σ . In the present parameterization this corresponds to having `loc` and `scale` equal to μ and σ , respectively, and shape parameter $K = 1/(\sigma\lambda)$.

New in version 0.16.0.

Examples

```
>>> from scipy.stats import exponnorm
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> K = 1.5
>>> mean, var, skew, kurt = exponnorm.stats(K, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(exponnorm.ppf(0.01, K),
...                 exponnorm.ppf(0.99, K), 100)
>>> ax.plot(x, exponnorm.pdf(x, K),
...         'r-', lw=5, alpha=0.6, label='exponnorm pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = exponnorm(K)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = exponnorm.ppf([0.001, 0.5, 0.999], K)
>>> np.allclose([0.001, 0.5, 0.999], exponnorm.cdf(vals, K))
True
```

Generate random numbers:

```
>>> r = exponnorm.rvs(K, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs(K, loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf(x, K, loc=0, scale=1)	Probability density function.
logpdf(x, K, loc=0, scale=1)	Log of the probability density function.
cdf(x, K, loc=0, scale=1)	Cumulative distribution function.
logcdf(x, K, loc=0, scale=1)	Log of the cumulative distribution function.
sf(x, K, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(x, K, loc=0, scale=1)	Log of the survival function.
ppf(q, K, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, K, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment(n, K, loc=0, scale=1)	Non-central moment of order <i>n</i>
stats(K, loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(K, loc=0, scale=1)	(Differential) entropy of the RV.
fit(data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect(func, args=(K,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)	Expected value of a function (of one argument) with respect to the distribution.
median(K, loc=0, scale=1)	Median of the distribution.
mean(K, loc=0, scale=1)	Mean of the distribution.
var(K, loc=0, scale=1)	Variance of the distribution.
std(K, loc=0, scale=1)	Standard deviation of the distribution.
interval(alpha, K, loc=0, scale=1)	Endpoints of the range that contains <i>alpha</i> percent of the distribution

scipy.stats.exponweib

```
scipy.stats.exponweib(*args, **kws) = <scipy.stats._continuous_distns.
    exponweib_gen object>
```

An exponentiated Weibull continuous random variable.

As an instance of the *rv_continuous* class, *exponweib* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

weibull_min, *numpy.random.RandomState.weibull*

Notes

The probability density function for *exponweib* is:

$$f(x, a, c) = ac[1 - \exp(-x^c)]^{a-1} \exp(-x^c)x^{c-1}$$

and its cumulative distribution function is:

$$F(x, a, c) = [1 - \exp(-x^c)]^a$$

for $x > 0$, $a > 0$, $c > 0$.

exponweib takes a and c as shape parameters:

- a is the exponentiation parameter, with the special case $a = 1$ corresponding to the (non-exponentiated) Weibull distribution *weibull_min*.
- c is the shape parameter of the non-exponentiated Weibull law.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, *exponweib.pdf(x, a, c, loc, scale)* is identically equivalent to *exponweib.pdf(y, a, c) / scale* with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

https://en.wikipedia.org/wiki/Exponentiated_Weibull_distribution

Examples

```
>>> from scipy.stats import exponweib
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a, c = 2.89, 1.95
>>> mean, var, skew, kurt = exponweib.stats(a, c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(exponweib.ppf(0.01, a, c),
...                  exponweib.ppf(0.99, a, c), 100)
>>> ax.plot(x, exponweib.pdf(x, a, c),
...         'r-', lw=5, alpha=0.6, label='exponweib pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = exponweib(a, c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = exponweib.ppf([0.001, 0.5, 0.999], a, c)
>>> np.allclose([0.001, 0.5, 0.999], exponweib.cdf(vals, a, c))
True
```

Generate random numbers:

```
>>> r = exponweib.rvs(a, c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(a, c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, c, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, a, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, a, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a, c), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.exponpow

```
scipy.stats.exponpow(*args, **kwds) = <scipy.stats._continuous_distns.
    exponpow_gen object>
```

An exponential power continuous random variable.

As an instance of the *rv_continuous* class, *exponpow* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *exponpow* is:

$$f(x, b) = bx^{b-1} \exp(1 + x^b - \exp(x^b))$$

for $x \geq 0$, $b > 0$. Note that this is a different distribution from the exponential power distribution that is also known under the names “generalized normal” or “generalized Gaussian”.

exponpow takes *b* as a shape parameter for *b*.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `exponpow.pdf(x, b, loc, scale)` is identically equivalent to `exponpow.pdf(y, b) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location

of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

<http://www.math.wm.edu/~leemis/chart/UDR/PDFs/Exponentialpower.pdf>

Examples

```
>>> from scipy.stats import exponpow
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> b = 2.7
>>> mean, var, skew, kurt = exponpow.stats(b, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(exponpow.ppf(0.01, b),
...                 exponpow.ppf(0.99, b), 100)
>>> ax.plot(x, exponpow.pdf(x, b),
...         'r-', lw=5, alpha=0.6, label='exponpow pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = exponpow(b)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = exponpow.ppf([0.001, 0.5, 0.999], b)
>>> np.allclose([0.001, 0.5, 0.999], exponpow.cdf(vals, b))
True
```

Generate random numbers:

```
>>> r = exponpow.rvs(b, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(b, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, b, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, b, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, b, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, b, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, b, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, b, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, b, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, b, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, b, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(b, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(b, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(b,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(b, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(b, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(b, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(b, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, b, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.f

`scipy.stats.f(*args, **kws)` = `<scipy.stats._continuous_distns.f_gen object>`
 An F continuous random variable.

For the noncentral F distribution, see `ncf`.

As an instance of the `rv_continuous` class, `f` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

`ncf`

Notes

The probability density function for `f` is:

$$f(x, df_1, df_2) = \frac{df_2^{df_2/2} df_1^{df_1/2} x^{df_1/2-1}}{(df_2 + df_1 x)^{(df_1+df_2)/2} B(df_1/2, df_2/2)}$$

for $x > 0$.

`f` takes `dfn` and `dfd` as shape parameters.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `f.pdf(x, dfn, dfd, loc, scale)` is identically equivalent to `f.pdf(y, dfn, dfd) / scale` with `y = (x - loc) / scale`. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import f
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> dfn, dfd = 29, 18
>>> mean, var, skew, kurt = f.stats(dfn, dfd, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(f.ppf(0.01, dfn, dfd),
...                 f.ppf(0.99, dfn, dfd), 100)
>>> ax.plot(x, f.pdf(x, dfn, dfd),
...         'r-', lw=5, alpha=0.6, label='f pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = f(dfn, dfd)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = f.ppf([0.001, 0.5, 0.999], dfn, dfd)
>>> np.allclose([0.001, 0.5, 0.999], f.cdf(vals, dfn, dfd))
True
```

Generate random numbers:

```
>>> r = f.rvs(dfn, dfd, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(dfn, dfd, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, dfn, dfd, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, dfn, dfd, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, dfn, dfd, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, dfn, dfd, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, dfn, dfd, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, dfn, dfd, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, dfn, dfd, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, dfn, dfd, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, dfn, dfd, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(dfn, dfd, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(dfn, dfd, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(dfn, dfd), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(dfn, dfd, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(dfn, dfd, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(dfn, dfd, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(dfn, dfd, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, dfn, dfd, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.fatiguelife

```
scipy.stats.fatiguelife(*args, **kwds) = <scipy.stats._continuous_distns.fatiguelife_gen object>
```

A fatigue-life (Birnbaum-Saunders) continuous random variable.

As an instance of the *rv_continuous* class, *fatiguelife* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *fatiguelife* is:

$$f(x, c) = \frac{x + 1}{2c\sqrt{2\pi x^3}} \exp\left(-\frac{(x - 1)^2}{2xc^2}\right)$$

for $x \geq 0$ and $c > 0$.

fatiguelife takes *c* as a shape parameter for *c*.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `fatiguelife.pdf(x, c, loc, scale)` is identically equivalent to `fatiguelife.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that

shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

[1]

Examples

```
>>> from scipy.stats import fatiguelife
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 29
>>> mean, var, skew, kurt = fatiguelife.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(fatiguelife.ppf(0.01, c),
...                 fatiguelife.ppf(0.99, c), 100)
>>> ax.plot(x, fatiguelife.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='fatiguelife pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = fatiguelife(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = fatiguelife.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], fatiguelife.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = fatiguelife.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.fisk

`scipy.stats.fisk(*args, **kws)` = `<scipy.stats._continuous_distns.fisk_gen object>`

A Fisk continuous random variable.

The Fisk distribution is also known as the log-logistic distribution.

As an instance of the `rv_continuous` class, `fisk` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

[`burr`](#)

Notes

The probability density function for `fisk` is:

$$f(x, c) = cx^{-c-1}(1 + x^{-c})^{-2}$$

for $x \geq 0$ and $c > 0$.

`fisk` takes `c` as a shape parameter for `c`.

`fisk` is a special case of `burr` or `burr12` with `d=1`.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `fisk.pdf(x, c, loc, scale)` is identically equivalent to `fisk.pdf(y, c) / scale` with `y = (x - loc) / scale`. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import fisk
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 3.09
>>> mean, var, skew, kurt = fisk.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(fisk.ppf(0.01, c),
...                 fisk.ppf(0.99, c), 100)
>>> ax.plot(x, fisk.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='fisk pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:


```
>>> rv = fisk(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = fisk.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], fisk.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = fisk.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.foldcauchy

```
scipy.stats.foldcauchy(*args, **kws) = <scipy.stats._continuous_distns.
foldcauchy_gen object>
```

A folded Cauchy continuous random variable.

As an instance of the *rv_continuous* class, *foldcauchy* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *foldcauchy* is:

$$f(x, c) = \frac{1}{\pi(1 + (x - c)^2)} + \frac{1}{\pi(1 + (x + c)^2)}$$

for $x \geq 0$.

foldcauchy takes *c* as a shape parameter for *c*.

Examples

```
>>> from scipy.stats import foldcauchy
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 4.72
>>> mean, var, skew, kurt = foldcauchy.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(foldcauchy.ppf(0.01, c),
...                 foldcauchy.ppf(0.99, c), 100)
>>> ax.plot(x, foldcauchy.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='foldcauchy pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = foldcauchy(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = foldcauchy.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], foldcauchy.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = foldcauchy.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.foldnorm

`scipy.stats.foldnorm(*args, **kwargs)` = `<scipy.stats._continuous_distns.foldnorm_gen object>`

A folded normal continuous random variable.

As an instance of the `rv_continuous` class, `foldnorm` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `foldnorm` is:

$$f(x, c) = \sqrt{2/\pi} \cosh(cx) \exp\left(-\frac{x^2 + c^2}{2}\right)$$

for $c \geq 0$.

`foldnorm` takes c as a shape parameter for c .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `foldnorm.pdf(x, c, loc, scale)` is identically equivalent to `foldnorm.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import foldnorm
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 1.95
>>> mean, var, skew, kurt = foldnorm.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(foldnorm.ppf(0.01, c),
...                 foldnorm.ppf(0.99, c), 100)
>>> ax.plot(x, foldnorm.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='foldnorm pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = foldnorm(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = foldnorm.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], foldnorm.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = foldnorm.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.genlogistic

```
scipy.stats.genlogistic(*args, **kws) = <scipy.stats._continuous_distns.
genlogistic_gen object>
```

A generalized logistic continuous random variable.

As an instance of the *rv_continuous* class, *genlogistic* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *genlogistic* is:

$$f(x, c) = c \frac{\exp(-x)}{(1 + \exp(-x))^{c+1}}$$

for $x \geq 0, c > 0$.

genlogistic takes *c* as a shape parameter for *c*.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `genlogistic.pdf(x, c, loc, scale)` is identically equivalent to `genlogistic.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import genlogistic
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 0.412
>>> mean, var, skew, kurt = genlogistic.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(genlogistic.ppf(0.01, c),
...                 genlogistic.ppf(0.99, c), 100)
>>> ax.plot(x, genlogistic.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='genlogistic pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = genlogistic(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = genlogistic.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], genlogistic.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = genlogistic.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```

Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.gennorm

```
scipy.stats.gennorm(*args, **kwargs) = <scipy.stats._continuous_distns.
    gennorm_gen object>
```

A generalized normal continuous random variable.

As an instance of the *rv_continuous* class, *gennorm* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

laplace

Laplace distribution

norm

normal distribution

Notes

The probability density function for *gennorm* is [1]:

$$f(x, \beta) = \frac{\beta}{2\Gamma(1/\beta)} \exp(-|x|^\beta)$$

Γ is the gamma function (*scipy.special.gamma*).

gennorm takes *beta* as a shape parameter for β . For $\beta = 1$, it is identical to a Laplace distribution. For $\beta = 2$, it is identical to a normal distribution (with *scale*=1/sqrt(2)).

References

[1]

Examples

```
>>> from scipy.stats import gennorm
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> beta = 1.3
>>> mean, var, skew, kurt = gennorm.stats(beta, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(gennorm.ppf(0.01, beta),
...                 gennorm.ppf(0.99, beta), 100)
>>> ax.plot(x, gennorm.pdf(x, beta),
...         'r-', lw=5, alpha=0.6, label='gennorm pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = gennorm(beta)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = gennorm.ppf([0.001, 0.5, 0.999], beta)
>>> np.allclose([0.001, 0.5, 0.999], gennorm.cdf(vals, beta))
True
```

Generate random numbers:

```
>>> r = gennorm.rvs(beta, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(beta, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, beta, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, beta, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, beta, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, beta, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, beta, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, beta, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, beta, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, beta, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, beta, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(beta, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(beta, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(beta,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(beta, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(beta, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(beta, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(beta, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, beta, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.genpareto

```
scipy.stats.genpareto(*args, **kwds) = <scipy.stats._continuous_distns.genpareto_gen object>
```

A generalized Pareto continuous random variable.

As an instance of the *rv_continuous* class, *genpareto* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *genpareto* is:

$$f(x, c) = (1 + cx)^{-1-1/c}$$

defined for $x \geq 0$ if $c \geq 0$, and for $0 \leq x \leq -1/c$ if $c < 0$.

genpareto takes *c* as a shape parameter for *c*.

For $c = 0$, *genpareto* reduces to the exponential distribution, *expon*:

$$f(x, 0) = \exp(-x)$$

For $c = -1$, `genpareto` is uniform on $[0, 1]$:

$$f(x, -1) = 1$$

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `genpareto.pdf(x, c, loc, scale)` is identically equivalent to `genpareto.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import genpareto
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 0.1
>>> mean, var, skew, kurt = genpareto.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(genpareto.ppf(0.01, c),
...                 genpareto.ppf(0.99, c), 100)
>>> ax.plot(x, genpareto.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='genpareto pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = genpareto(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = genpareto.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], genpareto.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = genpareto.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.genexpon

`scipy.stats.genexpon(*args, **kwargs)` = `<scipy.stats._continuous_distns.genexpon_gen object>`

A generalized exponential continuous random variable.

As an instance of the `rv_continuous` class, `genexpon` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `genexpon` is:

$$f(x, a, b, c) = (a + b(1 - \exp(-cx))) \exp(-ax - bx + \frac{b}{c}(1 - \exp(-cx)))$$

for $x \geq 0, a, b, c > 0$.

`genexpon` takes a, b and c as shape parameters.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `genexpon.pdf(x, a, b, c, loc, scale)` is identically equivalent to `genexpon.pdf(y, a, b, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

H.K. Ryu, “An Extension of Marshall and Olkin’s Bivariate Exponential Distribution”, Journal of the American Statistical Association, 1993.

N. Balakrishnan, “The Exponential Distribution: Theory, Methods and Applications”, Asit P. Basu.

Examples

```
>>> from scipy.stats import genexpon
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a, b, c = 9.13, 16.2, 3.28
>>> mean, var, skew, kurt = genexpon.stats(a, b, c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(genexpon.ppf(0.01, a, b, c),
...                 genexpon.ppf(0.99, a, b, c), 100)
>>> ax.plot(x, genexpon.pdf(x, a, b, c),
...        'r-', lw=5, alpha=0.6, label='genexpon pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = genexpon(a, b, c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = genexpon.ppf([0.001, 0.5, 0.999], a, b, c)
>>> np.allclose([0.001, 0.5, 0.999], genexpon.cdf(vals, a, b, c))
True
```

Generate random numbers:

```
>>> r = genexpon.rvs(a, b, c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs(a, b, c, loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf(x, a, b, c, loc=0, scale=1)	Probability density function.
logpdf(x, a, b, c, loc=0, scale=1)	Log of the probability density function.
cdf(x, a, b, c, loc=0, scale=1)	Cumulative distribution function.
logcdf(x, a, b, c, loc=0, scale=1)	Log of the cumulative distribution function.
sf(x, a, b, c, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(x, a, b, c, loc=0, scale=1)	Log of the survival function.
ppf(q, a, b, c, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, a, b, c, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment(n, a, b, c, loc=0, scale=1)	Non-central moment of order n
stats(a, b, c, loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(a, b, c, loc=0, scale=1)	(Differential) entropy of the RV.
fit(data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect(func, args=(a, b, c), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)	Expected value of a function (of one argument) with respect to the distribution.
median(a, b, c, loc=0, scale=1)	Median of the distribution.
mean(a, b, c, loc=0, scale=1)	Mean of the distribution.
var(a, b, c, loc=0, scale=1)	Variance of the distribution.
std(a, b, c, loc=0, scale=1)	Standard deviation of the distribution.
interval(alpha, a, b, c, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.genextreme

```
scipy.stats.genextreme(*args, **kws) = <scipy.stats._continuous_distns.  
genextreme_gen object>
```

A generalized extreme value continuous random variable.

As an instance of the *rv_continuous* class, *genextreme* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

[gumbel_r](#)

Notes

For $c = 0$, `genextreme` is equal to `gumbel_r`. The probability density function for `genextreme` is:

$$f(x, c) = \begin{cases} \exp(-\exp(-x)) \exp(-x) & \text{for } c = 0 \\ \exp(-(1 - cx)^{1/c})(1 - cx)^{1/c-1} & \text{for } x \leq 1/c, c > 0 \end{cases}$$

Note that several sources and software packages use the opposite convention for the sign of the shape parameter c . `genextreme` takes c as a shape parameter for c .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `genextreme.pdf(x, c, loc, scale)` is identically equivalent to `genextreme.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import genextreme
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = -0.1
>>> mean, var, skew, kurt = genextreme.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(genextreme.ppf(0.01, c),
...                 genextreme.ppf(0.99, c), 100)
>>> ax.plot(x, genextreme.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='genextreme pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = genextreme(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = genextreme.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], genextreme.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = genextreme.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.gausshyper

```
scipy.stats.gausshyper(*args, **kwargs) = <scipy.stats._continuous_distns.
    gausshyper_gen object>
```

A Gauss hypergeometric continuous random variable.

As an instance of the *rv_continuous* class, *gausshyper* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *gausshyper* is:

$$f(x, a, b, c, z) = Cx^{a-1}(1-x)^{b-1}(1+zx)^{-c}$$

for $0 \leq x \leq 1$, $a > 0$, $b > 0$, $z > -1$, and $C = \frac{1}{B(a,b)F[2,1](c,a;a+b;-z)}$. $F[2, 1]$ is the Gauss hypergeometric function *scipy.special.hyp2f1*.

gausshyper takes *a*, *b*, *c* and *z* as shape parameters.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, *gausshyper.pdf(x, a, b, c, z, loc, scale)* is identically equivalent to *gausshyper.pdf(y, a, b, c, z) / scale* with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

[1]

Examples

```
>>> from scipy.stats import gausshyper
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a, b, c, z = 13.8, 3.12, 2.51, 5.18
>>> mean, var, skew, kurt = gausshyper.stats(a, b, c, z, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(gausshyper.ppf(0.01, a, b, c, z),
...                 gausshyper.ppf(0.99, a, b, c, z), 100)
>>> ax.plot(x, gausshyper.pdf(x, a, b, c, z),
...         'r-', lw=5, alpha=0.6, label='gausshyper pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = gausshyper(a, b, c, z)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = gausshyper.ppf([0.001, 0.5, 0.999], a, b, c, z)
>>> np.allclose([0.001, 0.5, 0.999], gausshyper.cdf(vals, a, b, c, z))
True
```

Generate random numbers:

```
>>> r = gausshyper.rvs(a, b, c, z, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(a, b, c, z, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, b, c, z, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, b, c, z, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, b, c, z, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, b, c, z, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, b, c, z, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, b, c, z, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, b, c, z, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, a, b, c, z, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, a, b, c, z, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, b, c, z, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, b, c, z, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a, b, c, z), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, b, c, z, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, b, c, z, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, b, c, z, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, b, c, z, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, b, c, z, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.gamma

```
scipy.stats.gamma(*args, **kwds) = <scipy.stats._continuous_distns.gamma_gen
object>
```

A gamma continuous random variable.

As an instance of the *rv_continuous* class, *gamma* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

[erlang](#), [expon](#)

Notes

The probability density function for *gamma* is:

$$f(x, a) = \frac{x^{a-1}e^{-x}}{\Gamma(a)}$$

for $x \geq 0$, $a > 0$. Here $\Gamma(a)$ refers to the gamma function.

gamma takes *a* as a shape parameter for *a*.

When *a* is an integer, *gamma* reduces to the Erlang distribution, and when $a = 1$ to the exponential distribution.

Gamma distributions are sometimes parameterized with two variables, with a probability density function of:

$$f(x, \alpha, \beta) = \frac{\beta^\alpha x^{\alpha-1} e^{-\beta x}}{\Gamma(\alpha)}$$

Note that this parameterization is equivalent to the above, with $\text{scale} = 1 / \text{beta}$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `gamma.pdf(x, a, loc, scale)` is identically equivalent to `gamma.pdf(y, a) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import gamma
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a = 1.99
>>> mean, var, skew, kurt = gamma.stats(a, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(gamma.ppf(0.01, a),
...                 gamma.ppf(0.99, a), 100)
>>> ax.plot(x, gamma.pdf(x, a),
...         'r-', lw=5, alpha=0.6, label='gamma pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = gamma(a)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = gamma.ppf([0.001, 0.5, 0.999], a)
>>> np.allclose([0.001, 0.5, 0.999], gamma.cdf(vals, a))
True
```

Generate random numbers:

```
>>> r = gamma.rvs(a, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(a, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, a, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, a, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

`scipy.stats.gengamma`

```
scipy.stats.gengamma(*args, **kws) = <scipy.stats._continuous_distns.gengamma_gen object>
```

A generalized gamma continuous random variable.

As an instance of the `rv_continuous` class, `gengamma` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

`gamma`, `invgamma`, `weibull_min`

Notes

The probability density function for *gengamma* is ([1]):

$$f(x, a, c) = \frac{|c|x^{ca-1} \exp(-x^c)}{\Gamma(a)}$$

for $x \geq 0$, $a > 0$, and $c \neq 0$. Γ is the gamma function (*scipy.special.gamma*).

gengamma takes *a* and *c* as shape parameters.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, *gengamma.pdf(x, a, c, loc, scale)* is identically equivalent to *gengamma.pdf(y, a, c) / scale* with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

[1]

Examples

```
>>> from scipy.stats import gengamma
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a, c = 4.42, -3.12
>>> mean, var, skew, kurt = gengamma.stats(a, c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(gengamma.ppf(0.01, a, c),
...                 gengamma.ppf(0.99, a, c), 100)
>>> ax.plot(x, gengamma.pdf(x, a, c),
...         'r-', lw=5, alpha=0.6, label='gengamma pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = gengamma(a, c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = gengamma.ppf([0.001, 0.5, 0.999], a, c)
>>> np.allclose([0.001, 0.5, 0.999], gengamma.cdf(vals, a, c))
True
```

Generate random numbers:

```
>>> r = gengamma.rvs(a, c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(a, c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, c, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, a, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, a, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a, c), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.genhalflogistic

`scipy.stats.genhalflogistic(*args, **kwds) = <scipy.stats._continuous_distns.genhalflogistic_gen object>`

A generalized half-logistic continuous random variable.

As an instance of the *rv_continuous* class, *genhalflogistic* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *genhalflogistic* is:

$$f(x, c) = \frac{2(1 - cx)^{1/(c-1)}}{[1 + (1 - cx)^{1/c}]^2}$$

for $0 \leq x \leq 1/c$, and $c > 0$.

genhalflogistic takes *c* as a shape parameter for *c*.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `genhalflogistic.pdf(x, c, loc, scale)` is identically equivalent to `genhalflogistic.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import genhalflogistic
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 0.773
>>> mean, var, skew, kurt = genhalflogistic.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(genhalflogistic.ppf(0.01, c),
...                 genhalflogistic.ppf(0.99, c), 100)
>>> ax.plot(x, genhalflogistic.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='genhalflogistic pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = genhalflogistic(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = genhalflogistic.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], genhalflogistic.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = genhalflogistic.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.geninvgauss

```
scipy.stats.geninvgauss(*args, **kwargs) = <scipy.stats._continuous_distns.
    geninvgauss_gen object>
```

A Generalized Inverse Gaussian continuous random variable.

As an instance of the *rv_continuous* class, *geninvgauss* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *geninvgauss* is:

$$f(x, p, b) = x^{p-1} \exp(-b(x + 1/x)/2) / (2K_p(b))$$

where $x > 0$, and the parameters p, b satisfy $b > 0$ ([1]). K_p is the modified Bessel function of second kind of order p (*scipy.special.kv*).

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, *geninvgauss.pdf(x, p, b, loc, scale)* is identically equivalent to *geninvgauss.pdf(y, p, b) / scale* with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

The inverse Gaussian distribution *stats.invgauss(mu)* is a special case of *geninvgauss* with $p = -1/2, b = 1 / \text{mu}$ and *scale = mu*.

Generating random variates is challenging for this distribution. The implementation is based on [2].

References

[1], [2]

Examples

```
>>> from scipy.stats import geninvgauss
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> p, b = 2.3, 1.5
>>> mean, var, skew, kurt = geninvgauss.stats(p, b, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(geninvgauss.ppf(0.01, p, b),
...                 geninvgauss.ppf(0.99, p, b), 100)
>>> ax.plot(x, geninvgauss.pdf(x, p, b),
...         'r-', lw=5, alpha=0.6, label='geninvgauss pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = geninvgauss(p, b)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = geninvgauss.ppf([0.001, 0.5, 0.999], p, b)
>>> np.allclose([0.001, 0.5, 0.999], geninvgauss.cdf(vals, p, b))
True
```

Generate random numbers:

```
>>> r = geninvgauss.rvs(p, b, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(p, b, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, p, b, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, p, b, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, p, b, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, p, b, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, p, b, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, p, b, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, p, b, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, p, b, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, p, b, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(p, b, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(p, b, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(p, b), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(p, b, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(p, b, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(p, b, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(p, b, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, p, b, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.gilbrat

```
scipy.stats.gilbrat(*args, **kwds) = <scipy.stats._continuous_distns.
    gilbrat_gen object>
```

A Gilbrat continuous random variable.

As an instance of the *rv_continuous* class, *gilbrat* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *gilbrat* is:

$$f(x) = \frac{1}{x\sqrt{2\pi}} \exp\left(-\frac{1}{2}(\log(x))^2\right)$$

gilbrat is a special case of *lognorm* with *s*=1.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `gilbrat.pdf(x, loc, scale)` is identically equivalent to `gilbrat.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import gilbrat
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = gilbrat.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(gilbrat.ppf(0.01),
...                 gilbrat.ppf(0.99), 100)
>>> ax.plot(x, gilbrat.pdf(x),
...         'r-', lw=5, alpha=0.6, label='gilbrat pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = gilbrat()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = gilbrat.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], gilbrat.cdf(vals))
True
```

Generate random numbers:

```
>>> r = gilbrat.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.gompertz

```
scipy.stats.gompertz(*args, **kwargs) = <scipy.stats._continuous_distns.
    gompertz_gen object>
```

A Gompertz (or truncated Gumbel) continuous random variable.

As an instance of the *rv_continuous* class, *gompertz* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *gompertz* is:

$$f(x, c) = c \exp(x) \exp(-c(e^x - 1))$$

for $x \geq 0, c > 0$.

gompertz takes c as a shape parameter for c .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `gompertz.pdf(x, c, loc, scale)` is identically equivalent to `gompertz.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import gompertz
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 0.947
>>> mean, var, skew, kurt = gompertz.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(gompertz.ppf(0.01, c),
...                 gompertz.ppf(0.99, c), 100)
>>> ax.plot(x, gompertz.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='gompertz pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = gompertz(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = gompertz.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], gompertz.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = gompertz.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.gumbel_r

```
scipy.stats.gumbel_r(*args, **kws) = <scipy.stats._continuous_distns.gumbel_r_gen object>
```

A right-skewed Gumbel continuous random variable.

As an instance of the *rv_continuous* class, *gumbel_r* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

[gumbel_l](#), [gompertz](#), [genextreme](#)

Notes

The probability density function for `gumbel_r` is:

$$f(x) = \exp(-(x + e^{-x}))$$

The Gumbel distribution is sometimes referred to as a type I Fisher-Tippett distribution. It is also related to the extreme value distribution, log-Weibull and Gompertz distributions.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `gumbel_r.pdf(x, loc, scale)` is identically equivalent to `gumbel_r.pdf(y) / scale` with `y = (x - loc) / scale`. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import gumbel_r
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = gumbel_r.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(gumbel_r.ppf(0.01),
...                 gumbel_r.ppf(0.99), 100)
>>> ax.plot(x, gumbel_r.pdf(x),
...         'r-', lw=5, alpha=0.6, label='gumbel_r pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = gumbel_r()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = gumbel_r.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], gumbel_r.cdf(vals))
True
```

Generate random numbers:

```
>>> r = gumbel_r.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.gumbel_l

```
scipy.stats.gumbel_l(*args, **kws) = <scipy.stats._continuous_distns.
    gumbel_l_gen object>
```

A left-skewed Gumbel continuous random variable.

As an instance of the *rv_continuous* class, *gumbel_l* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

gumbel_r, *gompertz*, *genextreme*

Notes

The probability density function for *gumbel_l* is:

$$f(x) = \exp(x - e^x)$$

The Gumbel distribution is sometimes referred to as a type I Fisher-Tippett distribution. It is also related to the extreme value distribution, log-Weibull and Gompertz distributions.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, *gumbel_l.pdf(x, loc, scale)* is identically equivalent to *gumbel_l.pdf(y) / scale* with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import gumbel_l
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = gumbel_l.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(gumbel_l.ppf(0.01),
...                 gumbel_l.ppf(0.99), 100)
>>> ax.plot(x, gumbel_l.pdf(x),
...         'r-', lw=5, alpha=0.6, label='gumbel_l pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = gumbel_l()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = gumbel_l.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], gumbel_l.cdf(vals))
True
```

Generate random numbers:

```
>>> r = gumbel_l.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.halfcauchy

```
scipy.stats.halfcauchy(*args, **kws) = <scipy.stats._continuous_distns.
halfcauchy_gen object>
```

A Half-Cauchy continuous random variable.

As an instance of the *rv_continuous* class, *halfcauchy* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *halfcauchy* is:

$$f(x) = \frac{2}{\pi(1+x^2)}$$

for $x \geq 0$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `halfcauchy.pdf(x, loc, scale)` is identically equivalent to `halfcauchy.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import halfcauchy
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = halfcauchy.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(halfcauchy.ppf(0.01),
...                 halfcauchy.ppf(0.99), 100)
>>> ax.plot(x, halfcauchy.pdf(x),
...         'r-', lw=5, alpha=0.6, label='halfcauchy pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = halfcauchy()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = halfcauchy.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], halfcauchy.cdf(vals))
True
```

Generate random numbers:

```
>>> r = halfcauchy.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.halflogistic

```
scipy.stats.halflogistic(*args, **kwargs) = <scipy.stats._continuous_distns.
    halflogistic_gen object>
```

A half-logistic continuous random variable.

As an instance of the *rv_continuous* class, *halflogistic* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *halflogistic* is:

$$f(x) = \frac{2e^{-x}}{(1 + e^{-x})^2} = \frac{1}{2} \operatorname{sech}(x/2)^2$$

for $x \geq 0$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `halflogistic.pdf(x, loc, scale)` is identically equivalent to `halflogistic.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import halflogistic
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = halflogistic.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(halflogistic.ppf(0.01),
...                 halflogistic.ppf(0.99), 100)
>>> ax.plot(x, halflogistic.pdf(x),
...         'r-', lw=5, alpha=0.6, label='halflogistic pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = halflogistic()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = halflogistic.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], halflogistic.cdf(vals))
True
```

Generate random numbers:

```
>>> r = halflogistic.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.halfnorm

```
scipy.stats.halfnorm(*args, **kws) = <scipy.stats._continuous_distns.
halfnorm_gen object>
```

A half-normal continuous random variable.

As an instance of the *rv_continuous* class, *halfnorm* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *halfnorm* is:

$$f(x) = \sqrt{2/\pi} \exp(-x^2/2)$$

for $x \geq 0$.

halfnorm is a special case of *chi* with *df*=1.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, *halfnorm.pdf(x, loc, scale)* is identically equivalent to *halfnorm.pdf(y) / scale* with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import halfnorm
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = halfnorm.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(halfnorm.ppf(0.01),
...                 halfnorm.ppf(0.99), 100)
>>> ax.plot(x, halfnorm.pdf(x),
...         'r-', lw=5, alpha=0.6, label='halfnorm pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = halfnorm()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = halfnorm.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], halfnorm.cdf(vals))
True
```

Generate random numbers:

```
>>> r = halfnorm.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains <i>alpha</i> percent of the distribution

scipy.stats.halfgennorm

`scipy.stats.halfgennorm(*args, **kws)` = `<scipy.stats._continuous_distns.halfgennorm_gen object>`

The upper half of a generalized normal continuous random variable.

As an instance of the `rv_continuous` class, `halfgennorm` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

`gennorm`

generalized normal distribution

`expon`

exponential distribution

`halfnorm`

half normal distribution

Notes

The probability density function for `halfgennorm` is:

$$f(x, \beta) = \frac{\beta}{\Gamma(1/\beta)} \exp(-|x|^\beta)$$

for $x > 0$. Γ is the gamma function (`scipy.special.gamma`).

`gennorm` takes `beta` as a shape parameter for β . For $\beta = 1$, it is identical to an exponential distribution. For $\beta = 2$, it is identical to a half normal distribution (with `scale=1/sqrt(2)`).

References

[1]

Examples

```
>>> from scipy.stats import halfgennorm
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> beta = 0.675
>>> mean, var, skew, kurt = halfgennorm.stats(beta, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(halfgennorm.ppf(0.01, beta),
...                 halfgennorm.ppf(0.99, beta), 100)
>>> ax.plot(x, halfgennorm.pdf(x, beta),
...         'r-', lw=5, alpha=0.6, label='halfgennorm pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = halfgennorm(beta)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = halfgennorm.ppf([0.001, 0.5, 0.999], beta)
>>> np.allclose([0.001, 0.5, 0.999], halfgennorm.cdf(vals, beta))
True
```

Generate random numbers:

```
>>> r = halfgennorm.rvs(beta, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(beta, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, beta, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, beta, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, beta, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, beta, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, beta, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, beta, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, beta, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, beta, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, beta, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(beta, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(beta, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(beta,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(beta, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(beta, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(beta, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(beta, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, beta, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.hypsecant

```
scipy.stats.hypsecant(*args, **kws) = <scipy.stats._continuous_distns.
hypsecant_gen object>
```

A hyperbolic secant continuous random variable.

As an instance of the *rv_continuous* class, *hypsecant* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *hypsecant* is:

$$f(x) = \frac{1}{\pi} \operatorname{sech}(x)$$

for a real number *x*.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `hypsecant.pdf(x, loc, scale)` is identically equivalent to `hypsecant.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import hypsecant
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = hypsecant.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(hypsecant.ppf(0.01),
...                 hypsecant.ppf(0.99), 100)
>>> ax.plot(x, hypsecant.pdf(x),
...         'r-', lw=5, alpha=0.6, label='hypsecant pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = hypsecant()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = hypsecant.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], hypsecant.cdf(vals))
True
```

Generate random numbers:

```
>>> r = hypsecant.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs (loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf (x, loc=0, scale=1)	Probability density function.
logpdf (x, loc=0, scale=1)	Log of the probability density function.
cdf (x, loc=0, scale=1)	Cumulative distribution function.
logcdf (x, loc=0, scale=1)	Log of the cumulative distribution function.
sf (x, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf (x, loc=0, scale=1)	Log of the survival function.
ppf (q, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf (q, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment (n, loc=0, scale=1)	Non-central moment of order n
stats (loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy (loc=0, scale=1)	(Differential) entropy of the RV.
fit (data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect (func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)	Expected value of a function (of one argument) with respect to the distribution.
median (loc=0, scale=1)	Median of the distribution.
mean (loc=0, scale=1)	Mean of the distribution.
var (loc=0, scale=1)	Variance of the distribution.
std (loc=0, scale=1)	Standard deviation of the distribution.
interval (alpha, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.invgamma

```
scipy.stats.invgamma(*args, **kwargs) = <scipy.stats._continuous_distns.
    invgamma_gen object>
```

An inverted gamma continuous random variable.

As an instance of the *rv_continuous* class, *invgamma* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *invgamma* is:

$$f(x, a) = \frac{x^{-a-1}}{\Gamma(a)} \exp\left(-\frac{1}{x}\right)$$

for $x \geq 0, a > 0$. Γ is the gamma function (*scipy.special.gamma*).

invgamma takes *a* as a shape parameter for *a*.

invgamma is a special case of *gengamma* with *c*=-1.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, *invgamma.pdf(x, a, loc, scale)* is identically equivalent to *invgamma.pdf(y, a) / scale* with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import invgamma
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a = 4.07
>>> mean, var, skew, kurt = invgamma.stats(a, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(invgamma.ppf(0.01, a),
...                 invgamma.ppf(0.99, a), 100)
>>> ax.plot(x, invgamma.pdf(x, a),
...         'r-', lw=5, alpha=0.6, label='invgamma pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = invgamma(a)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:



```
>>> vals = invgamma.ppf([0.001, 0.5, 0.999], a)
>>> np.allclose([0.001, 0.5, 0.999], invgamma.cdf(vals, a))
True
```

Generate random numbers:

```
>>> r = invgamma.rvs(a, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(a, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, a, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, a, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.invgauss

```
scipy.stats.invgauss(*args, **kws) = <scipy.stats._continuous_distns.
    invgauss_gen object>
```

An inverse Gaussian continuous random variable.

As an instance of the *rv_continuous* class, *invgauss* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *invgauss* is:

$$f(x, \mu) = \frac{1}{\sqrt{2\pi x^3}} \exp\left(-\frac{(x - \mu)^2}{2x\mu^2}\right)$$

for $x \geq 0$ and $\mu > 0$.

invgauss takes *mu* as a shape parameter for μ .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `invgauss.pdf(x, mu, loc, scale)` is identically equivalent to `invgauss.pdf(y, mu) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location

of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

When μ is too small, evaluating the cumulative distribution function will be inaccurate due to $\text{cdf}(\mu \rightarrow 0) = \text{inf} * 0$. NaNs are returned for $\mu \leq 0.0028$.

Examples

```
>>> from scipy.stats import invgauss
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mu = 0.145
>>> mean, var, skew, kurt = invgauss.stats(mu, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(invgauss.ppf(0.01, mu),
...                 invgauss.ppf(0.99, mu), 100)
>>> ax.plot(x, invgauss.pdf(x, mu),
...         'r-', lw=5, alpha=0.6, label='invgauss pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = invgauss(mu)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = invgauss.ppf([0.001, 0.5, 0.999], mu)
>>> np.allclose([0.001, 0.5, 0.999], invgauss.cdf(vals, mu))
True
```

Generate random numbers:

```
>>> r = invgauss.rvs(mu, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs(mu, loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf(x, mu, loc=0, scale=1)	Probability density function.
logpdf(x, mu, loc=0, scale=1)	Log of the probability density function.
cdf(x, mu, loc=0, scale=1)	Cumulative distribution function.
logcdf(x, mu, loc=0, scale=1)	Log of the cumulative distribution function.
sf(x, mu, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(x, mu, loc=0, scale=1)	Log of the survival function.
ppf(q, mu, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, mu, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment(n, mu, loc=0, scale=1)	Non-central moment of order <i>n</i>
stats(mu, loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(mu, loc=0, scale=1)	(Differential) entropy of the RV.
fit(data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect(func, args=(mu,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)	Expected value of a function (of one argument) with respect to the distribution.
median(mu, loc=0, scale=1)	Median of the distribution.
mean(mu, loc=0, scale=1)	Mean of the distribution.
var(mu, loc=0, scale=1)	Variance of the distribution.
std(mu, loc=0, scale=1)	Standard deviation of the distribution.
interval(alpha, mu, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.invweibull

```
scipy.stats.invweibull(*args, **kwargs) = <scipy.stats._continuous_distns.
    invweibull_gen object>
```

An inverted Weibull continuous random variable.

This distribution is also known as the Fréchet distribution or the type II extreme value distribution.

As an instance of the *rv_continuous* class, *invweibull* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *invweibull* is:

$$f(x, c) = cx^{-c-1} \exp(-x^{-c})$$

for $x > 0, c > 0$.

invweibull takes c as a shape parameter for c .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `invweibull.pdf(x, c, loc, scale)` is identically equivalent to `invweibull.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

F.R.S. de Gusmao, E.M.M Ortega and G.M. Cordeiro, “The generalized inverse Weibull distribution”, Stat. Papers, vol. 52, pp. 591-619, 2011.

Examples

```
>>> from scipy.stats import invweibull
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 10.6
>>> mean, var, skew, kurt = invweibull.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(invweibull.ppf(0.01, c),
...                 invweibull.ppf(0.99, c), 100)
>>> ax.plot(x, invweibull.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='invweibull pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = invweibull(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = invweibull.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], invweibull.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = invweibull.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

`scipy.stats.johnsonsb`

```
scipy.stats.johnsonsb(*args, **kws) = <scipy.stats._continuous_distns.
johnsonsb_gen object>
```

A Johnson SB continuous random variable.

As an instance of the *rv_continuous* class, *johnsonsb* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

[johnsonsu](#)

Notes

The probability density function for *johnsonsb* is:

$$f(x, a, b) = \frac{b}{x(1-x)} \phi\left(a + b \log \frac{x}{1-x}\right)$$

for $0 \leq x \leq 1$ and $a, b > 0$, and ϕ is the normal pdf.

johnsonsb takes *a* and *b* as shape parameters.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `johnsonsb.pdf(x, a, b, loc, scale)` is identically equivalent to `johnsonsb.pdf(y, a, b) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import johnsonsb
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a, b = 4.32, 3.18
>>> mean, var, skew, kurt = johnsonsb.stats(a, b, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(johnsonsb.ppf(0.01, a, b),
...                 johnsonsb.ppf(0.99, a, b), 100)
>>> ax.plot(x, johnsonsb.pdf(x, a, b),
...         'r-', lw=5, alpha=0.6, label='johnsonsb pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = johnsonsb(a, b)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:

```
>>> vals = johnsonsb.ppf([0.001, 0.5, 0.999], a, b)
>>> np.allclose([0.001, 0.5, 0.999], johnsonsb.cdf(vals, a, b))
True
```

Generate random numbers:


```
>>> r = johnsonsb.rvs(a, b, size=1000)
```

And compare the histogram:


```

>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()

```



Methods

rvs(a, b, loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf(x, a, b, loc=0, scale=1)	Probability density function.
logpdf(x, a, b, loc=0, scale=1)	Log of the probability density function.
cdf(x, a, b, loc=0, scale=1)	Cumulative distribution function.
logcdf(x, a, b, loc=0, scale=1)	Log of the cumulative distribution function.
sf(x, a, b, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(x, a, b, loc=0, scale=1)	Log of the survival function.
ppf(q, a, b, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, a, b, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment(n, a, b, loc=0, scale=1)	Non-central moment of order <i>n</i>
stats(a, b, loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(a, b, loc=0, scale=1)	(Differential) entropy of the RV.
fit(data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect(func, args=(a, b), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)	Expected value of a function (of one argument) with respect to the distribution.
median(a, b, loc=0, scale=1)	Median of the distribution.
mean(a, b, loc=0, scale=1)	Mean of the distribution.
var(a, b, loc=0, scale=1)	Variance of the distribution.
std(a, b, loc=0, scale=1)	Standard deviation of the distribution.
interval(alpha, a, b, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.johnsonsu

```
scipy.stats.johnsonsu(*args, **kwargs) = <scipy.stats._continuous_distns.
johnsonsu_gen object>
```

A Johnson SU continuous random variable.

As an instance of the *rv_continuous* class, *johnsonsu* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

johnsonsb

Notes

The probability density function for *johnsonsu* is:

$$f(x, a, b) = \frac{b}{\sqrt{x^2 + 1}} \phi(a + b \log(x + \sqrt{x^2 + 1}))$$

for all $x, a, b > 0$, and ϕ is the normal pdf.

johnsonsu takes a and b as shape parameters.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `johnsonsu.pdf(x, a, b, loc, scale)` is identically equivalent to `johnsonsu.pdf(y, a, b) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import johnsonsu
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a, b = 2.55, 2.25
>>> mean, var, skew, kurt = johnsonsu.stats(a, b, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(johnsonsu.ppf(0.01, a, b),
...                 johnsonsu.ppf(0.99, a, b), 100)
>>> ax.plot(x, johnsonsu.pdf(x, a, b),
...        'r-', lw=5, alpha=0.6, label='johnsonsu pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = johnsonsu(a, b)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = johnsonsu.ppf([0.001, 0.5, 0.999], a, b)
>>> np.allclose([0.001, 0.5, 0.999], johnsonsu.cdf(vals, a, b))
True
```

Generate random numbers:

```
>>> r = johnsonsu.rvs(a, b, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(a, b, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, b, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, b, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, b, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, b, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, b, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, b, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, b, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, a, b, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, a, b, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, b, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, b, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a, b), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, b, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, b, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, b, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, b, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, b, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.kappa4

`scipy.stats.kappa4(*args, **kwds) = <scipy.stats._continuous_distns.kappa4_gen object>`

Kappa 4 parameter distribution.

As an instance of the *rv_continuous* class, *kappa4* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for kappa4 is:

$$f(x, h, k) = (1 - kx)^{1/k-1} (1 - h(1 - kx)^{1/k})^{1/h-1}$$

if *h* and *k* are not equal to 0.

If *h* or *k* are zero then the pdf can be simplified:

h = 0 and *k* != 0:

$$\text{kappa4.pdf}(x, h, k) = (1.0 - k*x) ** (1.0/k - 1.0) * \exp(-(1.0 - k*x) ** (1.0/k))$$

$h \neq 0$ and $k = 0$:

```
kappa4.pdf(x, h, k) = exp(-x) * (1.0 - h * exp(-x)) ** (1.0/h - 1.0)
```

$h = 0$ and $k = 0$:

```
kappa4.pdf(x, h, k) = exp(-x) * exp(-exp(-x))
```

`kappa4` takes h and k as shape parameters.

The `kappa4` distribution returns other distributions when certain h and k values are used.

h	k=0.0	k=1.0	-inf<=k<=inf
-1.0	Logistic logistic(x)		Generalized Logistic(1)
0.0	Gumbel gumbel_r(x)	Reverse Exponential(2)	Generalized Extreme Value genextreme(x, k)
1.0	Exponential expon(x)	Uniform uniform(x)	Generalized Pareto genpareto(x, -k)

- (1) There are at least five generalized logistic distributions. Four are described here: https://en.wikipedia.org/wiki/Generalized_logistic_distribution The “fifth” one is the one `kappa4` should match which currently isn’t implemented in `scipy`: https://en.wikipedia.org/wiki/Talk:Generalized_logistic_distribution https://www.mathwave.com/help/easyfit/html/analyses/distributions/gen_logistic.html
- (2) This distribution is currently not in `scipy`.

References

J.C. Finney, “Optimization of a Skewed Logistic Distribution With Respect to the Kolmogorov-Smirnov Test”, A Dissertation Submitted to the Graduate Faculty of the Louisiana State University and Agricultural and Mechanical College, (August, 2004), https://digitalcommons.lsu.edu/gradschool_dissertations/3672

J.R.M. Hosking, “The four-parameter kappa distribution”. *IBM J. Res. Develop.* 38 (3), 25 1-258 (1994).

B. Kumphon, A. Kaew-Man, P. Seenoi, “A Rainfall Distribution for the Lampao Site in the Chi River Basin, Thailand”, *Journal of Water Resource and Protection*, vol. 4, 866-869, (2012). DOI:10.4236/jwarp.2012.410101

C. Winchester, “On Estimation of the Four-Parameter Kappa Distribution”, A Thesis Submitted to Dalhousie University, Halifax, Nova Scotia, (March 2000). <http://www.nlc-bnc.ca/obj/s4/f2/dsk2/ftp01/MQ57336.pdf>

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `kappa4.pdf(x, h, k, loc, scale)` is identically equivalent to `kappa4.pdf(y, h, k) / scale` with $y = (x - loc) / scale$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import kappa4
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> h, k = 0.1, 0
>>> mean, var, skew, kurt = kappa4.stats(h, k, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(kappa4.ppf(0.01, h, k),
...                 kappa4.ppf(0.99, h, k), 100)
>>> ax.plot(x, kappa4.pdf(x, h, k),
...        'r-', lw=5, alpha=0.6, label='kappa4 pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = kappa4(h, k)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = kappa4.ppf([0.001, 0.5, 0.999], h, k)
>>> np.allclose([0.001, 0.5, 0.999], kappa4.cdf(vals, h, k))
True
```

Generate random numbers:

```
>>> r = kappa4.rvs(h, k, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs(h, k, loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf(x, h, k, loc=0, scale=1)	Probability density function.
logpdf(x, h, k, loc=0, scale=1)	Log of the probability density function.
cdf(x, h, k, loc=0, scale=1)	Cumulative distribution function.
logcdf(x, h, k, loc=0, scale=1)	Log of the cumulative distribution function.
sf(x, h, k, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(x, h, k, loc=0, scale=1)	Log of the survival function.
ppf(q, h, k, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, h, k, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment(n, h, k, loc=0, scale=1)	Non-central moment of order <i>n</i>
stats(h, k, loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(h, k, loc=0, scale=1)	(Differential) entropy of the RV.
fit(data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect(func, args=(h, k), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)	Expected value of a function (of one argument) with respect to the distribution.
median(h, k, loc=0, scale=1)	Median of the distribution.
mean(h, k, loc=0, scale=1)	Mean of the distribution.
var(h, k, loc=0, scale=1)	Variance of the distribution.
std(h, k, loc=0, scale=1)	Standard deviation of the distribution.
interval(alpha, h, k, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.kappa3

```
scipy.stats.kappa3(*args, **kws) = <scipy.stats._continuous_distns.kappa3_gen
object>
```

Kappa 3 parameter distribution.

As an instance of the *rv_continuous* class, *kappa3* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *kappa3* is:

$$f(x, a) = a(a + x^a)^{-(a+1)/a}$$

for $x > 0$ and $a > 0$.

kappa3 takes *a* as a shape parameter for *a*.

References

P.W. Mielke and E.S. Johnson, “Three-Parameter Kappa Distribution Maximum Likelihood and Likelihood Ratio Tests”, *Methods in Weather Research*, 701-707, (September, 1973), DOI:10.1175/1520-0493(1973)101<0701:TKDMLE>2.3.CO;2

B. Kumphon, “Maximum Entropy and Maximum Likelihood Estimation for the Three-Parameter Kappa Distribution”, *Open Journal of Statistics*, vol 2, 415-419 (2012), DOI:10.4236/ojs.2012.24050

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, *kappa3.pdf(x, a, loc, scale)* is identically equivalent to *kappa3.pdf(y, a) / scale* with $y = (x - loc) / scale$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import kappa3
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a = 1
>>> mean, var, skew, kurt = kappa3.stats(a, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(kappa3.ppf(0.01, a),
...                 kappa3.ppf(0.99, a), 100)
>>> ax.plot(x, kappa3.pdf(x, a),
...         'r-', lw=5, alpha=0.6, label='kappa3 pdf')
```


Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = kappa3(a)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = kappa3.ppf([0.001, 0.5, 0.999], a)
>>> np.allclose([0.001, 0.5, 0.999], kappa3.cdf(vals, a))
True
```

Generate random numbers:

```
>>> r = kappa3.rvs(a, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(a, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, a, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, a, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.ksone

`scipy.stats.ksone(*args, **kws) = <scipy.stats._continuous_distns.ksone_gen object>`

Kolmogorov-Smirnov one-sided test statistic distribution.

This is the distribution of the one-sided Kolmogorov-Smirnov (KS) statistics D_n^+ and D_n^- for a finite sample size *n* (the shape parameter).

As an instance of the `rv_continuous` class, `ksone` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

`kstwobign`, `kstwo`, `kstest`

Notes

D_n^+ and D_n^- are given by

$$D_n^+ = \sup_x (F_n(x) - F(x)),$$

$$D_n^- = \sup_x (F(x) - F_n(x)),$$

where F is a continuous CDF and F_n is an empirical CDF. `ksone` describes the distribution under the null hypothesis of the KS test that the empirical CDF corresponds to n i.i.d. random variates with CDF F .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `ksone.pdf(x, n, loc, scale)` is identically equivalent to `ksone.pdf(y, n) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

[1]

Examples

```
>>> from scipy.stats import ksone
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> n = 1e+03
>>> mean, var, skew, kurt = ksone.stats(n, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(ksone.ppf(0.01, n),
...                 ksone.ppf(0.99, n), 100)
>>> ax.plot(x, ksone.pdf(x, n),
...         'r-', lw=5, alpha=0.6, label='ksone pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = ksone(n)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = ksone.ppf([0.001, 0.5, 0.999], n)
>>> np.allclose([0.001, 0.5, 0.999], ksone.cdf(vals, n))
True
```

Generate random numbers:

```
>>> r = ksone.rvs(n, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(n, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, n, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, n, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, n, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, n, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, n, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, n, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, n, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, n, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(n, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(n, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(n,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(n, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(n, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(n, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(n, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, n, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.kstwo

`scipy.stats.kstwo(*args, **kws) = <scipy.stats._continuous_distns.kstwo_gen object>`

Kolmogorov-Smirnov two-sided test statistic distribution.

This is the distribution of the two-sided Kolmogorov-Smirnov (KS) statistic D_n for a finite sample size *n* (the shape parameter).

As an instance of the `rv_continuous` class, `kstwo` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

`kstwobign`, `ksone`, `kstest`

Notes

D_n is given by

$$D_n = \sup_x |F_n(x) - F(x)|$$

where F is a (continuous) CDF and F_n is an empirical CDF. `kstwo` describes the distribution under the null hypothesis of the KS test that the empirical CDF corresponds to n i.i.d. random variates with CDF F .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `kstwo.pdf(x, n, loc, scale)` is identically equivalent to `kstwo.pdf(y, n) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

[1]

Examples

```
>>> from scipy.stats import kstwo
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> n = 10
>>> mean, var, skew, kurt = kstwo.stats(n, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(kstwo.ppf(0.01, n),
...                 kstwo.ppf(0.99, n), 100)
>>> ax.plot(x, kstwo.pdf(x, n),
...         'r-', lw=5, alpha=0.6, label='kstwo pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = kstwo(n)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = kstwo.ppf([0.001, 0.5, 0.999], n)
>>> np.allclose([0.001, 0.5, 0.999], kstwo.cdf(vals, n))
True
```

Generate random numbers:

```
>>> r = kstwo.rvs(n, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(n, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, n, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, n, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, n, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, n, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, n, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, n, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, n, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, n, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(n, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(n, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(n,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(n, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(n, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(n, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(n, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, n, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.kstwobign

```
scipy.stats.kstwobign(*args, **kws) = <scipy.stats._continuous_distns.
    kstwobign_gen object>
```

Limiting distribution of scaled Kolmogorov-Smirnov two-sided test statistic.

This is the asymptotic distribution of the two-sided Kolmogorov-Smirnov statistic $\sqrt{n}D_n$ that measures the maximum absolute distance of the theoretical (continuous) CDF from the empirical CDF. (see *kstest*).

As an instance of the *rv_continuous* class, *kstwobign* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

ksone, *kstwo*, *kstest*

Notes

$\sqrt{n}D_n$ is given by

$$D_n = \sup_x |F_n(x) - F(x)|$$

where F is a continuous CDF and F_n is an empirical CDF. *kstwobign* describes the asymptotic distribution (i.e. the limit of $\sqrt{n}D_n$) under the null hypothesis of the KS test that the empirical CDF corresponds to i.i.d. random variates with CDF F .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `kstwobign.pdf(x, loc, scale)` is identically equivalent to `kstwobign.pdf(y) / scale` with `y = (x - loc) / scale`. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

[1]

Examples

```
>>> from scipy.stats import kstwobign
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = kstwobign.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(kstwobign.ppf(0.01),
...                 kstwobign.ppf(0.99), 100)
>>> ax.plot(x, kstwobign.pdf(x),
...         'r-', lw=5, alpha=0.6, label='kstwobign pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = kstwobign()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = kstwobign.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], kstwobign.cdf(vals))
True
```

Generate random numbers:

```
>>> r = kstwobign.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.laplace

```
scipy.stats.laplace(*args, **kwds) = <scipy.stats._continuous_distns.
laplace_gen object>
```

A Laplace continuous random variable.

As an instance of the *rv_continuous* class, *laplace* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *laplace* is

$$f(x) = \frac{1}{2} \exp(-|x|)$$

for a real number *x*.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `laplace.pdf(x, loc, scale)` is identically equivalent to `laplace.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import laplace
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = laplace.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(laplace.ppf(0.01),
...                 laplace.ppf(0.99), 100)
>>> ax.plot(x, laplace.pdf(x),
...         'r-', lw=5, alpha=0.6, label='laplace pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = laplace()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = laplace.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], laplace.cdf(vals))
True
```

Generate random numbers:

```
>>> r = laplace.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains <i>alpha</i> percent of the distribution

scipy.stats.laplace_asymmetric

```
scipy.stats.laplace_asymmetric(*args, **kws) = <scipy.stats.
    _continuous_distns.laplace_asymmetric_gen
    object>
```

An asymmetric Laplace continuous random variable.

As an instance of the *rv_continuous* class, *laplace_asymmetric* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

laplace

Laplace distribution

Notes

The probability density function for *laplace_asymmetric* is

$$f(x, \kappa) = \frac{1}{\kappa + \kappa^{-1}} \exp(-x\kappa), \quad x \geq 0$$

$$= \frac{1}{\kappa + \kappa^{-1}} \exp(x/\kappa), \quad x < 0$$

for $-\infty < x < \infty, \kappa > 0$.

laplace_asymmetric takes kappa as a shape parameter for κ . For $\kappa = 1$, it is identical to a Laplace distribution.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `laplace_asymmetric.pdf(x, kappa, loc, scale)` is identically equivalent to `laplace_asymmetric.pdf(y, kappa) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

[1], [2]

Examples

```
>>> from scipy.stats import laplace_asymmetric
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> kappa = 2
>>> mean, var, skew, kurt = laplace_asymmetric.stats(kappa, moments='mvsk
→')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(laplace_asymmetric.ppf(0.01, kappa),
...                 laplace_asymmetric.ppf(0.99, kappa), 100)
>>> ax.plot(x, laplace_asymmetric.pdf(x, kappa),
...         'r-', lw=5, alpha=0.6, label='laplace_asymmetric pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = laplace_asymmetric(kappa)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = laplace_asymmetric.ppf([0.001, 0.5, 0.999], kappa)
>>> np.allclose([0.001, 0.5, 0.999], laplace_asymmetric.cdf(vals, kappa))
True
```

Generate random numbers:

```
>>> r = laplace_asymmetric.rvs(kappa, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(kappa, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, kappa, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, kappa, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, kappa, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, kappa, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, kappa, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, kappa, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, kappa, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, kappa, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, kappa, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(kappa, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(kappa, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(kappa,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(kappa, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(kappa, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(kappa, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(kappa, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, kappa, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.levy

```
scipy.stats.levy(*args, **kwds) = <scipy.stats._continuous_distns.levy_gen object>
```

A Levy continuous random variable.

As an instance of the *rv_continuous* class, *levy* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

[levy_stable](#), [levy_1](#)

Notes

The probability density function for `levy` is:

$$f(x) = \frac{1}{\sqrt{2\pi x^3}} \exp\left(-\frac{1}{2x}\right)$$

for $x \geq 0$.

This is the same as the Levy-stable distribution with $a = 1/2$ and $b = 1$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `levy.pdf(x, loc, scale)` is identically equivalent to `levy.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import levy
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = levy.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(levy.ppf(0.01),
...                 levy.ppf(0.99), 100)
>>> ax.plot(x, levy.pdf(x),
...         'r-', lw=5, alpha=0.6, label='levy pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = levy()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:

```
>>> vals = levy.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], levy.cdf(vals))
True
```


Generate random numbers:

```
>>> r = levy.rvs(size=1000)
```

And compare the histogram:

```

>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
    
```



Methods

rvs (loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf (x, loc=0, scale=1)	Probability density function.
logpdf (x, loc=0, scale=1)	Log of the probability density function.
cdf (x, loc=0, scale=1)	Cumulative distribution function.
logcdf (x, loc=0, scale=1)	Log of the cumulative distribution function.
sf (x, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf (x, loc=0, scale=1)	Log of the survival function.
ppf (q, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf (q, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment (n, loc=0, scale=1)	Non-central moment of order n
stats (loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy (loc=0, scale=1)	(Differential) entropy of the RV.
fit (data)	Parameter estimates for generic data. See <code>scipy.stats.rv_continuous.fit</code> for detailed documentation of the keyword arguments.
expect (func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)	Expected value of a function (of one argument) with respect to the distribution.
median (loc=0, scale=1)	Median of the distribution.
mean (loc=0, scale=1)	Mean of the distribution.
var (loc=0, scale=1)	Variance of the distribution.
std (loc=0, scale=1)	Standard deviation of the distribution.
interval (alpha, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.levy_l

```
scipy.stats.levy_l(*args, **kwargs) = <scipy.stats._continuous_distns.levy_l_gen
object>
```

A left-skewed Levy continuous random variable.

As an instance of the *rv_continuous* class, *levy_l* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

levy, *levy_stable*

Notes

The probability density function for *levy_l* is:

$$f(x) = \frac{1}{|x|\sqrt{2\pi|x|}} \exp\left(-\frac{1}{2|x|}\right)$$

for $x \leq 0$.

This is the same as the Levy-stable distribution with $a = 1/2$ and $b = -1$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `levy_l.pdf(x, loc, scale)` is identically equivalent to `levy_l.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import levy_l
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = levy_l.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(levy_l.ppf(0.01),
...                 levy_l.ppf(0.99), 100)
>>> ax.plot(x, levy_l.pdf(x),
...         'r-', lw=5, alpha=0.6, label='levy_l pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = levy_l()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = levy_l.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], levy_l.cdf(vals))
True
```

Generate random numbers:

```
>>> r = levy_l.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs (loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf (x, loc=0, scale=1)	Probability density function.
logpdf (x, loc=0, scale=1)	Log of the probability density function.
cdf (x, loc=0, scale=1)	Cumulative distribution function.
logcdf (x, loc=0, scale=1)	Log of the cumulative distribution function.
sf (x, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf (x, loc=0, scale=1)	Log of the survival function.
ppf (q, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf (q, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment (n, loc=0, scale=1)	Non-central moment of order n
stats (loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy (loc=0, scale=1)	(Differential) entropy of the RV.
fit (data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect (func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)	Expected value of a function (of one argument) with respect to the distribution.
median (loc=0, scale=1)	Median of the distribution.
mean (loc=0, scale=1)	Mean of the distribution.
var (loc=0, scale=1)	Variance of the distribution.
std (loc=0, scale=1)	Standard deviation of the distribution.
interval (alpha, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.levy_stable

```
scipy.stats.levy_stable(*args, **kwds) = <scipy.stats._continuous_distns.levy_stable_gen object>
```

A Levy-stable continuous random variable.

As an instance of the *rv_continuous* class, *levy_stable* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

levy, *levy_1*

Notes

The distribution for `levy_stable` has characteristic function:

$$\varphi(t, \alpha, \beta, c, \mu) = e^{it\mu - |ct|^\alpha (1 - i\beta \operatorname{sign}(t)\Phi(\alpha, t))}$$

where:

$$\Phi = \begin{cases} \tan\left(\frac{\pi\alpha}{2}\right) & \alpha \neq 1 \\ -\frac{2}{\pi} \log|t| & \alpha = 1 \end{cases}$$

The probability density function for `levy_stable` is:

$$f(x) = \frac{1}{2\pi} \int_{-\infty}^{\infty} \varphi(t) e^{-ixt} dt$$

where $-\infty < t < \infty$. This integral does not have a known closed form.

For evaluation of pdf we use either Zolotarev S_0 parameterization with integration, direct integration of standard parameterization of characteristic function or FFT of characteristic function. If set to other than None and if number of points is greater than `levy_stable.pdf_fft_min_points_threshold` (defaults to None) we use FFT otherwise we use one of the other methods.

The default method is ‘best’ which uses Zolotarev’s method if $\alpha = 1$ and integration of characteristic function otherwise. The default method can be changed by setting `levy_stable.pdf_default_method` to either ‘zolotarev’, ‘quadrature’ or ‘best’.

To increase accuracy of FFT calculation one can specify `levy_stable.pdf_fft_grid_spacing` (defaults to 0.001) and `pdf_fft_n_points_two_power` (defaults to a value that covers the input range * 4). Setting `pdf_fft_n_points_two_power` to 16 should be sufficiently accurate in most cases at the expense of CPU time.

For evaluation of cdf we use Zolotarev S_0 parameterization with integration or integral of the pdf FFT interpolated spline. The settings affecting FFT calculation are the same as for pdf calculation. Setting the threshold to None (default) will disable FFT. For cdf calculations the Zolotarev method is superior in accuracy, so FFT is disabled by default.

Fitting estimate uses quantile estimation method in [MC]. MLE estimation of parameters in fit method uses this quantile estimate initially. Note that MLE doesn’t always converge if using FFT for pdf calculations; so it’s best that `pdf_fft_min_points_threshold` is left unset.

Warning: For pdf calculations implementation of Zolotarev is unstable for values where $\alpha = 1$ and $\beta \neq 0$. In this case the quadrature method is recommended. FFT calculation is also considered experimental.

For cdf calculations FFT calculation is considered experimental. Use Zolotarev’s method instead (default).

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `levy_stable.pdf(x, alpha, beta, loc, scale)` is identically equivalent to `levy_stable.pdf(y, alpha, beta) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

[MC], [MS], [BS]

Examples

```
>>> from scipy.stats import levy_stable
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> alpha, beta = 1.8, -0.5
>>> mean, var, skew, kurt = levy_stable.stats(alpha, beta, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(levy_stable.ppf(0.01, alpha, beta),
...                 levy_stable.ppf(0.99, alpha, beta), 100)
>>> ax.plot(x, levy_stable.pdf(x, alpha, beta),
...         'r-', lw=5, alpha=0.6, label='levy_stable pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = levy_stable(alpha, beta)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = levy_stable.ppf([0.001, 0.5, 0.999], alpha, beta)
>>> np.allclose([0.001, 0.5, 0.999], levy_stable.cdf(vals, alpha, beta))
True
```

Generate random numbers:

```
>>> r = levy_stable.rvs(alpha, beta, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(alpha, beta, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, alpha, beta, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, alpha, beta, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, alpha, beta, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, alpha, beta, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, alpha, beta, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, alpha, beta, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, alpha, beta, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, alpha, beta, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, alpha, beta, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(alpha, beta, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(alpha, beta, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(alpha, beta), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(alpha, beta, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(alpha, beta, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(alpha, beta, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(alpha, beta, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, alpha, beta, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.logistic

```
scipy.stats.logistic(*args, **kwargs) = <scipy.stats._continuous_distns.
    logistic_gen object>
```

A logistic (or Sech-squared) continuous random variable.

As an instance of the *rv_continuous* class, *logistic* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *logistic* is:

$$f(x) = \frac{\exp(-x)}{(1 + \exp(-x))^2}$$

logistic is a special case of *genlogistic* with $c=1$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `logistic.pdf(x, loc, scale)` is identically equivalent to `logistic.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import logistic
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = logistic.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(logistic.ppf(0.01),
...                 logistic.ppf(0.99), 100)
>>> ax.plot(x, logistic.pdf(x),
...         'r-', lw=5, alpha=0.6, label='logistic pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = logistic()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = logistic.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], logistic.cdf(vals))
True
```

Generate random numbers:

```
>>> r = logistic.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.loggamma

```
scipy.stats.loggamma(*args, **kws) = <scipy.stats._continuous_distns.
    loggamma_gen object>
```

A log gamma continuous random variable.

As an instance of the *rv_continuous* class, *loggamma* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *loggamma* is:

$$f(x, c) = \frac{\exp(cx - \exp(x))}{\Gamma(c)}$$

for all $x, c > 0$. Here, Γ is the gamma function ([scipy.special.gamma](#)).

loggamma takes *c* as a shape parameter for *c*.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `loggamma.pdf(x, c, loc, scale)` is identically equivalent to `loggamma.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import loggamma
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 0.414
>>> mean, var, skew, kurt = loggamma.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(loggamma.ppf(0.01, c),
...                 loggamma.ppf(0.99, c), 100)
>>> ax.plot(x, loggamma.pdf(x, c),
...        'r-', lw=5, alpha=0.6, label='loggamma pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = loggamma(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = loggamma.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], loggamma.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = loggamma.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs(c, loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf(x, c, loc=0, scale=1)	Probability density function.
logpdf(x, c, loc=0, scale=1)	Log of the probability density function.
cdf(x, c, loc=0, scale=1)	Cumulative distribution function.
logcdf(x, c, loc=0, scale=1)	Log of the cumulative distribution function.
sf(x, c, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(x, c, loc=0, scale=1)	Log of the survival function.
ppf(q, c, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, c, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment(n, c, loc=0, scale=1)	Non-central moment of order <i>n</i>
stats(c, loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(c, loc=0, scale=1)	(Differential) entropy of the RV.
fit(data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)	Expected value of a function (of one argument) with respect to the distribution.
median(c, loc=0, scale=1)	Median of the distribution.
mean(c, loc=0, scale=1)	Mean of the distribution.
var(c, loc=0, scale=1)	Variance of the distribution.
std(c, loc=0, scale=1)	Standard deviation of the distribution.
interval(alpha, c, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.loglaplace

`scipy.stats.loglaplace(*args, **kwargs) = <scipy.stats._continuous_distns.loglaplace_gen object>`

A log-Laplace continuous random variable.

As an instance of the `rv_continuous` class, `loglaplace` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `loglaplace` is:

$$f(x, c) = \begin{cases} \frac{c}{2}x^{c-1} & \text{for } 0 < x < 1 \\ \frac{c}{2}x^{-c-1} & \text{for } x \geq 1 \end{cases}$$

for $c > 0$.

`loglaplace` takes c as a shape parameter for c .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `loglaplace.pdf(x, c, loc, scale)` is identically equivalent to `loglaplace.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

T.J. Kozubowski and K. Podgorski, “A log-Laplace growth rate model”, *The Mathematical Scientist*, vol. 28, pp. 49-60, 2003.

Examples

```
>>> from scipy.stats import loglaplace
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 3.25
>>> mean, var, skew, kurt = loglaplace.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(loglaplace.ppf(0.01, c),
...                 loglaplace.ppf(0.99, c), 100)
>>> ax.plot(x, loglaplace.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='loglaplace pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = loglaplace(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = loglaplace.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], loglaplace.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = loglaplace.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.lognorm

```
scipy.stats.lognorm(*args, **kwds) = <scipy.stats._continuous_distns.
    lognorm_gen object>
```

A lognormal continuous random variable.

As an instance of the *rv_continuous* class, *lognorm* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *lognorm* is:

$$f(x, s) = \frac{1}{sx\sqrt{2\pi}} \exp\left(-\frac{\log^2(x)}{2s^2}\right)$$

for $x > 0, s > 0$.

lognorm takes *s* as a shape parameter for *s*.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `lognorm.pdf(x, s, loc, scale)` is identically equivalent to `lognorm.pdf(y, s) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location

of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

A common parametrization for a lognormal random variable Y is in terms of the mean, μ , and standard deviation, σ , of the unique normally distributed random variable X such that $\exp(X) = Y$. This parametrization corresponds to setting $s = \sigma$ and $\text{scale} = \exp(\mu)$.

Examples

```
>>> from scipy.stats import lognorm
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> s = 0.954
>>> mean, var, skew, kurt = lognorm.stats(s, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(lognorm.ppf(0.01, s),
...                 lognorm.ppf(0.99, s), 100)
>>> ax.plot(x, lognorm.pdf(x, s),
...         'r-', lw=5, alpha=0.6, label='lognorm pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = lognorm(s)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = lognorm.ppf([0.001, 0.5, 0.999], s)
>>> np.allclose([0.001, 0.5, 0.999], lognorm.cdf(vals, s))
True
```

Generate random numbers:

```
>>> r = lognorm.rvs(s, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(s, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, s, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, s, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, s, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, s, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, s, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, s, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, s, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, s, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, s, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(s, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(s, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(s,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(s, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(s, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(s, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(s, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, s, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.loguniform

```
scipy.stats.loguniform(*args, **kwargs) = <scipy.stats._continuous_distns.
reciprocal_gen object>
```

A loguniform or reciprocal continuous random variable.

As an instance of the `rv_continuous` class, `loguniform` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for this class is:

$$f(x, a, b) = \frac{1}{x \log(b/a)}$$

for $a \leq x \leq b, b > a > 0$. This class takes a and b as shape parameters.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `loguniform.pdf(x, a, b, loc, scale)` is identically equivalent to `loguniform.pdf(y, a, b) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import loguniform
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a, b = 0.01, 1
>>> mean, var, skew, kurt = loguniform.stats(a, b, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(loguniform.ppf(0.01, a, b),
...                 loguniform.ppf(0.99, a, b), 100)
>>> ax.plot(x, loguniform.pdf(x, a, b),
...         'r-', lw=5, alpha=0.6, label='loguniform pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = loguniform(a, b)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = loguniform.ppf([0.001, 0.5, 0.999], a, b)
>>> np.allclose([0.001, 0.5, 0.999], loguniform.cdf(vals, a, b))
True
```

Generate random numbers:

```
>>> r = loguniform.rvs(a, b, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



This doesn't show the equal probability of 0.01, 0.1 and 1. This is best when the x-axis is log-scaled:

```
>>> import numpy as np
>>> fig, ax = plt.subplots(1, 1)
>>> ax.hist(np.log10(r))
>>> ax.set_ylabel("Frequency")
>>> ax.set_xlabel("Value of random variable")
>>> ax.xaxis.set_major_locator(plt.FixedLocator([-2, -1, 0]))
>>> ticks = ["$10^{{{ }}}$".format(i) for i in [-2, -1, 0]]
>>> ax.set_xticklabels(ticks)
>>> plt.show()
```


This random variable will be log-uniform regardless of the base chosen for a and b. Let's specify with base 2 instead:

```
>>> rvs = loguniform(2**-2, 2**0).rvs(size=1000)
```

Values of 1/4, 1/2 and 1 are equally likely with this random variable. Here's the histogram:


```
>>> fig, ax = plt.subplots(1, 1)
>>> ax.hist(np.log2(rvs))
>>> ax.set_ylabel("Frequency")
>>> ax.set_xlabel("Value of random variable")
>>> ax.xaxis.set_major_locator(plt.FixedLocator([-2, -1, 0]))
>>> ticks = ["$2^{{{ }}}$".format(i) for i in [-2, -1, 0]]
```

(continues on next page)



(continued from previous page)

```
>>> ax.set_xticklabels(ticks)
>>> plt.show()
```



Methods

<code>rvs(a, b, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, b, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, b, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, b, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, b, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, b, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, b, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, b, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, a, b, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, a, b, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, b, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, b, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a, b), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, b, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, b, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, b, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, b, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, b, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.lomax

```
scipy.stats.lomax(*args, **kws) = <scipy.stats._continuous_distns.lomax_gen
object>
```

A Lomax (Pareto of the second kind) continuous random variable.

As an instance of the *rv_continuous* class, *lomax* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *lomax* is:

$$f(x, c) = \frac{c}{(1+x)^{c+1}}$$

for $x \geq 0, c > 0$.

lomax takes *c* as a shape parameter for *c*.

lomax is a special case of *pareto* with `loc=-1.0`.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `lomax.pdf(x, c, loc, scale)` is identically equivalent to `lomax.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of

a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import lomax
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 1.88
>>> mean, var, skew, kurt = lomax.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(lomax.ppf(0.01, c),
...                 lomax.ppf(0.99, c), 100)
>>> ax.plot(x, lomax.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='lomax pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = lomax(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = lomax.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], lomax.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = lomax.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.maxwell

```
scipy.stats.maxwell(*args, **kws) = <scipy.stats._continuous_distns.
    maxwell_gen object>
```

A Maxwell continuous random variable.

As an instance of the *rv_continuous* class, *maxwell* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

A special case of a *chi* distribution, with `df=3`, `loc=0.0`, and given `scale = a`, where `a` is the parameter used in the Mathworld description [1].

The probability density function for *maxwell* is:

$$f(x) = \sqrt{2/\pi} x^2 \exp(-x^2/2)$$

for $x \geq 0$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `maxwell.pdf(x, loc, scale)` is identically equivalent to `maxwell.pdf(y) / scale` with `y = (x - loc) / scale`. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

[1]

Examples

```
>>> from scipy.stats import maxwell
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = maxwell.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(maxwell.ppf(0.01),
...                 maxwell.ppf(0.99), 100)
>>> ax.plot(x, maxwell.pdf(x),
...         'r-', lw=5, alpha=0.6, label='maxwell pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = maxwell()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = maxwell.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], maxwell.cdf(vals))
True
```

Generate random numbers:

```
>>> r = maxwell.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.mielke

`scipy.stats.mielke(*args, **kws) = <scipy.stats._continuous_distns.mielke_gen object>`

A Mielke Beta-Kappa / Dagum continuous random variable.

As an instance of the `rv_continuous` class, `mielke` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `mielke` is:

$$f(x, k, s) = \frac{kx^{k-1}}{(1+x^s)^{1+k/s}}$$

for $x > 0$ and $k, s > 0$. The distribution is sometimes called Dagum distribution ([2]). It was already defined in [3], called a Burr Type III distribution (`burr` with parameters $c=s$ and $d=k/s$).

`mielke` takes *k* and *s* as shape parameters.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `mielke.pdf(x, k, s, loc, scale)` is identically equivalent to `mielke.pdf(y, k, s) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location

of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

[1], [2], [3]

Examples

```
>>> from scipy.stats import mielke
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> k, s = 10.4, 4.6
>>> mean, var, skew, kurt = mielke.stats(k, s, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(mielke.ppf(0.01, k, s),
...                 mielke.ppf(0.99, k, s), 100)
>>> ax.plot(x, mielke.pdf(x, k, s),
...        'r-', lw=5, alpha=0.6, label='mielke pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = mielke(k, s)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = mielke.ppf([0.001, 0.5, 0.999], k, s)
>>> np.allclose([0.001, 0.5, 0.999], mielke.cdf(vals, k, s))
True
```

Generate random numbers:

```
>>> r = mielke.rvs(k, s, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(k, s, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, k, s, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, k, s, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, k, s, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, k, s, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, k, s, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, k, s, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, k, s, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, k, s, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, k, s, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(k, s, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(k, s, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(k, s), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(k, s, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(k, s, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(k, s, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(k, s, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, k, s, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.moyal

`scipy.stats.moyal(*args, **kws)` = `<scipy.stats._continuous_distns.moyal_gen object>`

A Moyal continuous random variable.

As an instance of the `rv_continuous` class, `moyal` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `moyal` is:

$$f(x) = \exp(-(x + \exp(-x))/2) / \sqrt{2\pi}$$

for a real number x .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `moyal.pdf(x, loc, scale)` is identically equivalent to `moyal.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

This distribution has utility in high-energy physics and radiation detection. It describes the energy loss of a charged relativistic particle due to ionization of the medium [1]. It also provides an approximation for the Landau distribution. For an in depth description see [2]. For additional description, see [3].

References

New in version 1.1.0.

[1], [2], [3]

Examples

```
>>> from scipy.stats import moyal
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = moyal.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(moyal.ppf(0.01),
...                 moyal.ppf(0.99), 100)
>>> ax.plot(x, moyal.pdf(x),
...         'r-', lw=5, alpha=0.6, label='moyal pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = moyal()  
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = moyal.ppf([0.001, 0.5, 0.999])  
>>> np.allclose([0.001, 0.5, 0.999], moyal.cdf(vals))  
True
```

Generate random numbers:

```
>>> r = moyal.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)  
>>> ax.legend(loc='best', frameon=False)  
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.nakagami

```
scipy.stats.nakagami(*args, **kws) = <scipy.stats._continuous_distns.nakagami_gen object>
```

A Nakagami continuous random variable.

As an instance of the *rv_continuous* class, *nakagami* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *nakagami* is:

$$f(x, \nu) = \frac{2\nu^\nu}{\Gamma(\nu)} x^{2\nu-1} \exp(-\nu x^2)$$

for $x \geq 0, \nu > 0$.

nakagami takes *nu* as a shape parameter for ν .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `nakagami.pdf(x, nu, loc, scale)` is identically equivalent to `nakagami.pdf(y, nu) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import nakagami
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> nu = 4.97
>>> mean, var, skew, kurt = nakagami.stats(nu, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(nakagami.ppf(0.01, nu),
...                 nakagami.ppf(0.99, nu), 100)
>>> ax.plot(x, nakagami.pdf(x, nu),
...         'r-', lw=5, alpha=0.6, label='nakagami pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = nakagami(nu)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = nakagami.ppf([0.001, 0.5, 0.999], nu)
>>> np.allclose([0.001, 0.5, 0.999], nakagami.cdf(vals, nu))
True
```

Generate random numbers:

```
>>> r = nakagami.rvs(nu, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs(nu, loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf(x, nu, loc=0, scale=1)	Probability density function.
logpdf(x, nu, loc=0, scale=1)	Log of the probability density function.
cdf(x, nu, loc=0, scale=1)	Cumulative distribution function.
logcdf(x, nu, loc=0, scale=1)	Log of the cumulative distribution function.
sf(x, nu, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(x, nu, loc=0, scale=1)	Log of the survival function.
ppf(q, nu, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, nu, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment(n, nu, loc=0, scale=1)	Non-central moment of order <i>n</i>
stats(nu, loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(nu, loc=0, scale=1)	(Differential) entropy of the RV.
fit(data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect(func, args=(nu,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)	Expected value of a function (of one argument) with respect to the distribution.
median(nu, loc=0, scale=1)	Median of the distribution.
mean(nu, loc=0, scale=1)	Mean of the distribution.
var(nu, loc=0, scale=1)	Variance of the distribution.
std(nu, loc=0, scale=1)	Standard deviation of the distribution.
interval(alpha, nu, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.ncx2

`scipy.stats.ncx2(*args, **kwargs)` = <scipy.stats._continuous_distns.ncx2_gen object>

A non-central chi-squared continuous random variable.

As an instance of the `rv_continuous` class, `ncx2` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `ncx2` is:

$$f(x, k, \lambda) = \frac{1}{2} \exp(-(\lambda + x)/2) (x/\lambda)^{(k-2)/4} I_{(k-2)/2}(\sqrt{\lambda x})$$

for $x \geq 0$ and $k, \lambda > 0$. k specifies the degrees of freedom (denoted `df` in the implementation) and λ is the non-centrality parameter (denoted `nc` in the implementation). I_ν denotes the modified Bessel function of first order of degree ν (`scipy.special.iv`).

`ncx2` takes `df` and `nc` as shape parameters.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `ncx2.pdf(x, df, nc, loc, scale)` is identically equivalent to `ncx2.pdf(y, df, nc) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import ncx2
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> df, nc = 21, 1.06
>>> mean, var, skew, kurt = ncx2.stats(df, nc, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(ncx2.ppf(0.01, df, nc),
...                 ncx2.ppf(0.99, df, nc), 100)
>>> ax.plot(x, ncx2.pdf(x, df, nc),
...        'r-', lw=5, alpha=0.6, label='ncx2 pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = ncx2(df, nc)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = ncx2.ppf([0.001, 0.5, 0.999], df, nc)
>>> np.allclose([0.001, 0.5, 0.999], ncx2.cdf(vals, df, nc))
True
```

Generate random numbers:

```
>>> r = ncx2.rvs(df, nc, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs(df, nc, loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf(x, df, nc, loc=0, scale=1)	Probability density function.
logpdf(x, df, nc, loc=0, scale=1)	Log of the probability density function.
cdf(x, df, nc, loc=0, scale=1)	Cumulative distribution function.
logcdf(x, df, nc, loc=0, scale=1)	Log of the cumulative distribution function.
sf(x, df, nc, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(x, df, nc, loc=0, scale=1)	Log of the survival function.
ppf(q, df, nc, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, df, nc, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment(n, df, nc, loc=0, scale=1)	Non-central moment of order n
stats(df, nc, loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(df, nc, loc=0, scale=1)	(Differential) entropy of the RV.
fit(data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect(func, args=(df, nc), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)	Expected value of a function (of one argument) with respect to the distribution.
median(df, nc, loc=0, scale=1)	Median of the distribution.
mean(df, nc, loc=0, scale=1)	Mean of the distribution.
var(df, nc, loc=0, scale=1)	Variance of the distribution.
std(df, nc, loc=0, scale=1)	Standard deviation of the distribution.
interval(alpha, df, nc, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.ncf

```
scipy.stats.ncf(*args, **kws) = <scipy.stats._continuous_distns.ncf_gen object>
```

A non-central F distribution continuous random variable.

As an instance of the *rv_continuous* class, *ncf* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

[scipy.stats.f](#)

Fisher distribution

Notes

The probability density function for `ncf` is:

$$f(x, n_1, n_2, \lambda) = \exp\left(\frac{\lambda}{2} + \lambda n_1 \frac{x}{2(n_1 x + n_2)}\right) n_1^{n_1/2} n_2^{n_2/2} x^{n_1/2-1} \\ (n_2 + n_1 x)^{-(n_1+n_2)/2} \gamma(n_1/2) \gamma(1 + n_2/2) \\ \frac{L_{n_2/2}^{\frac{n_1}{2}-1}\left(-\lambda n_1 \frac{x}{2(n_1 x + n_2)}\right)}{B(n_1/2, n_2/2) \gamma\left(\frac{n_1+n_2}{2}\right)}$$

for $n_1, n_2 > 0$, $\lambda \geq 0$. Here n_1 is the degrees of freedom in the numerator, n_2 the degrees of freedom in the denominator, λ the non-centrality parameter, γ is the logarithm of the Gamma function, L_n^k is a generalized Laguerre polynomial and B is the beta function.

`ncf` takes `df1`, `df2` and `nc` as shape parameters. If `nc=0`, the distribution becomes equivalent to the Fisher distribution.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `ncf.pdf(x, dfn, dfd, nc, loc, scale)` is identically equivalent to `ncf.pdf(y, dfn, dfd, nc) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import ncf
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> dfn, dfd, nc = 27, 27, 0.416
>>> mean, var, skew, kurt = ncf.stats(dfn, dfd, nc, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(ncf.ppf(0.01, dfn, dfd, nc),
...                 ncf.ppf(0.99, dfn, dfd, nc), 100)
>>> ax.plot(x, ncf.pdf(x, dfn, dfd, nc),
...         'r-', lw=5, alpha=0.6, label='ncf pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = ncf(dfn, dfd, nc)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = ncf.ppf([0.001, 0.5, 0.999], dfn, dfd, nc)
>>> np.allclose([0.001, 0.5, 0.999], ncf.cdf(vals, dfn, dfd, nc))
True
```

Generate random numbers:

```
>>> r = ncf.rvs(dfn, dfd, nc, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(df, d, nc, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, df, d, nc, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, df, d, nc, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, df, d, nc, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, df, d, nc, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, df, d, nc, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, df, d, nc, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, df, d, nc, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, df, d, nc, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, df, d, nc, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(df, d, nc, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(df, d, nc, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(df, d, nc), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(df, d, nc, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(df, d, nc, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(df, d, nc, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(df, d, nc, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, df, d, nc, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.nct

`scipy.stats.nct(*args, **kwds) = <scipy.stats._continuous_distns.nct_gen object>`

A non-central Student's t continuous random variable.

As an instance of the `rv_continuous` class, `nct` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

If Y is a standard normal random variable and V is an independent chi-square random variable (*chi2*) with k degrees of freedom, then

$$X = \frac{Y + c}{\sqrt{V/k}}$$

has a non-central Student's t distribution on the real line. The degrees of freedom parameter k (denoted `df` in the implementation) satisfies $k > 0$ and the noncentrality parameter c (denoted `nc` in the implementation) is a real number.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `nct.pdf(x, df, nc, loc, scale)` is identically equivalent

to `nct.pdf(y, df, nc) / scale` with $y = (x - loc) / scale$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import nct
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> df, nc = 14, 0.24
>>> mean, var, skew, kurt = nct.stats(df, nc, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(nct.ppf(0.01, df, nc),
...                 nct.ppf(0.99, df, nc), 100)
>>> ax.plot(x, nct.pdf(x, df, nc),
...         'r-', lw=5, alpha=0.6, label='nct pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = nct(df, nc)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = nct.ppf([0.001, 0.5, 0.999], df, nc)
>>> np.allclose([0.001, 0.5, 0.999], nct.cdf(vals, df, nc))
True
```

Generate random numbers:

```
>>> r = nct.rvs(df, nc, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(df, nc, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, df, nc, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, df, nc, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, df, nc, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, df, nc, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, df, nc, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, df, nc, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, df, nc, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, df, nc, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, df, nc, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(df, nc, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(df, nc, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(df, nc), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(df, nc, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(df, nc, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(df, nc, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(df, nc, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, df, nc, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.norm

`scipy.stats.norm(*args, **kwargs)` = `<scipy.stats._continuous_distns.norm_gen object>`

A normal continuous random variable.

The location (`loc`) keyword specifies the mean. The scale (`scale`) keyword specifies the standard deviation.

As an instance of the `rv_continuous` class, `norm` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `norm` is:

$$f(x) = \frac{\exp(-x^2/2)}{\sqrt{2\pi}}$$

for a real number x .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `norm.pdf(x, loc, scale)` is identically equivalent to `norm.pdf(y) / scale` with $y = (x - loc) / scale$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import norm
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = norm.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(norm.ppf(0.01),
...                 norm.ppf(0.99), 100)
>>> ax.plot(x, norm.pdf(x),
...        'r-', lw=5, alpha=0.6, label='norm pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = norm()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = norm.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], norm.cdf(vals))
True
```

Generate random numbers:

```
>>> r = norm.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.norminvgauss

`scipy.stats.norminvgauss(*args, **kws) = <scipy.stats._continuous_distns.norminvgauss_gen object>`

A Normal Inverse Gaussian continuous random variable.

As an instance of the `rv_continuous` class, `norminvgauss` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `norminvgauss` is:

$$f(x, a, b) = \frac{a K_1(a\sqrt{1+x^2})}{\pi\sqrt{1+x^2}} \exp(\sqrt{a^2 - b^2} + bx)$$

where x is a real number, the parameter a is the tail heaviness and b is the asymmetry parameter satisfying $a > 0$ and $|b| \leq a$. K_1 is the modified Bessel function of second kind (`scipy.special.k1`).

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `norminvgauss.pdf(x, a, b, loc, scale)` is identically equivalent to `norminvgauss.pdf(y, a, b) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

A normal inverse Gaussian random variable Y with parameters a and b can be expressed as a normal mean-variance mixture: $Y = b * V + \text{sqr}(V) * X$ where X is $\text{norm}(0,1)$ and V is $\text{invgauss}(\text{mu}=1/\text{sqr}(a**2 - b**2))$. This representation is used to generate random variates.

References

O. Barndorff-Nielsen, “Hyperbolic Distributions and Distributions on Hyperbolae”, Scandinavian Journal of Statistics, Vol. 5(3), pp. 151-157, 1978.

O. Barndorff-Nielsen, “Normal Inverse Gaussian Distributions and Stochastic Volatility Modelling”, Scandinavian Journal of Statistics, Vol. 24, pp. 1-13, 1997.

Examples

```
>>> from scipy.stats import norminvgauss
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a, b = 1, 0.5
>>> mean, var, skew, kurt = norminvgauss.stats(a, b, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(norminvgauss.ppf(0.01, a, b),
...                 norminvgauss.ppf(0.99, a, b), 100)
>>> ax.plot(x, norminvgauss.pdf(x, a, b),
...         'r-', lw=5, alpha=0.6, label='norminvgauss pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = norminvgauss(a, b)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = norminvgauss.ppf([0.001, 0.5, 0.999], a, b)
>>> np.allclose([0.001, 0.5, 0.999], norminvgauss.cdf(vals, a, b))
True
```

Generate random numbers:

```
>>> r = norminvgauss.rvs(a, b, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs(a, b, loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf(x, a, b, loc=0, scale=1)	Probability density function.
logpdf(x, a, b, loc=0, scale=1)	Log of the probability density function.
cdf(x, a, b, loc=0, scale=1)	Cumulative distribution function.
logcdf(x, a, b, loc=0, scale=1)	Log of the cumulative distribution function.
sf(x, a, b, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(x, a, b, loc=0, scale=1)	Log of the survival function.
ppf(q, a, b, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, a, b, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment(n, a, b, loc=0, scale=1)	Non-central moment of order n
stats(a, b, loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(a, b, loc=0, scale=1)	(Differential) entropy of the RV.
fit(data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect(func, args=(a, b), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)	Expected value of a function (of one argument) with respect to the distribution.
median(a, b, loc=0, scale=1)	Median of the distribution.
mean(a, b, loc=0, scale=1)	Mean of the distribution.
var(a, b, loc=0, scale=1)	Variance of the distribution.
std(a, b, loc=0, scale=1)	Standard deviation of the distribution.
interval(alpha, a, b, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.pareto

`scipy.stats.pareto(*args, **kwargs) = <scipy.stats._continuous_distns.pareto_gen object>`

A Pareto continuous random variable.

As an instance of the `rv_continuous` class, `pareto` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `pareto` is:

$$f(x, b) = \frac{b}{x^{b+1}}$$

for $x \geq 1, b > 0$.

`pareto` takes `b` as a shape parameter for b .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `pareto.pdf(x, b, loc, scale)` is identically equivalent to `pareto.pdf(y, b) / scale` with $y = (x - loc) / scale$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import pareto
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> b = 2.62
>>> mean, var, skew, kurt = pareto.stats(b, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(pareto.ppf(0.01, b),
...                 pareto.ppf(0.99, b), 100)
>>> ax.plot(x, pareto.pdf(x, b),
...        'r-', lw=5, alpha=0.6, label='pareto pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = pareto(b)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:



```
>>> vals = pareto.ppf([0.001, 0.5, 0.999], b)
>>> np.allclose([0.001, 0.5, 0.999], pareto.cdf(vals, b))
True
```

Generate random numbers:

```
>>> r = pareto.rvs(b, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(b, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, b, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, b, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, b, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, b, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, b, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, b, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, b, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, b, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, b, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(b, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(b, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(b,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(b, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(b, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(b, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(b, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, b, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.pearson3

```
scipy.stats.pearson3(*args, **kws) = <scipy.stats._continuous_distns.
    pearson3_gen object>
```

A pearson type III continuous random variable.

As an instance of the `rv_continuous` class, `pearson3` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `pearson3` is:

$$f(x, \kappa) = \frac{|\beta|}{\Gamma(\alpha)} (\beta(x - \zeta))^{\alpha-1} \exp(-\beta(x - \zeta))$$

where:

$$\begin{aligned} \beta &= \frac{2}{\kappa} \\ \alpha &= \beta^2 = \frac{4}{\kappa^2} \\ \zeta &= -\frac{\alpha}{\beta} = -\beta \end{aligned}$$

Γ is the gamma function (`scipy.special.gamma`). Pass the skew κ into `pearson3` as the shape parameter `skew`.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `pearson3.pdf(x, skew, loc, scale)` is identically equivalent to `pearson3.pdf(y, skew) / scale` with `y = (x - loc) / scale`. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

R.W. Vogel and D.E. McMartin, “Probability Plot Goodness-of-Fit and Skewness Estimation Procedures for the Pearson Type 3 Distribution”, *Water Resources Research*, Vol.27, 3149-3158 (1991).

L.R. Salvosa, “Tables of Pearson’s Type III Function”, *Ann. Math. Statist.*, Vol.1, 191-198 (1930).

“Using Modern Computing Tools to Fit the Pearson Type III Distribution to Aviation Loads Data”, Office of Aviation Research (2003).

Examples

```
>>> from scipy.stats import pearson3
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> skew = 0.1
>>> mean, var, skew, kurt = pearson3.stats(skew, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(pearson3.ppf(0.01, skew),
...                 pearson3.ppf(0.99, skew), 100)
>>> ax.plot(x, pearson3.pdf(x, skew),
...         'r-', lw=5, alpha=0.6, label='pearson3 pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = pearson3(skew)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = pearson3.ppf([0.001, 0.5, 0.999], skew)
>>> np.allclose([0.001, 0.5, 0.999], pearson3.cdf(vals, skew))
True
```

Generate random numbers:

```
>>> r = pearson3.rvs(skew, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(skew, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, skew, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, skew, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, skew, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, skew, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, skew, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, skew, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, skew, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, skew, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, skew, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(skew, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(skew, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(skew,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(skew, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(skew, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(skew, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(skew, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, skew, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.powerlaw

```
scipy.stats.powerlaw(*args, **kwds) = <scipy.stats._continuous_distns.
powerlaw_gen object>
```

A power-function continuous random variable.

As an instance of the *rv_continuous* class, *powerlaw* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *powerlaw* is:

$$f(x, a) = ax^{a-1}$$

for $0 \leq x \leq 1, a > 0$.

powerlaw takes *a* as a shape parameter for *a*.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `powerlaw.pdf(x, a, loc, scale)` is identically equivalent to `powerlaw.pdf(y, a) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

`powerlaw` is a special case of `beta` with $b=1$.

Examples

```
>>> from scipy.stats import powerlaw
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a = 1.66
>>> mean, var, skew, kurt = powerlaw.stats(a, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(powerlaw.ppf(0.01, a),
...                 powerlaw.ppf(0.99, a), 100)
>>> ax.plot(x, powerlaw.pdf(x, a),
...        'r-', lw=5, alpha=0.6, label='powerlaw pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = powerlaw(a)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = powerlaw.ppf([0.001, 0.5, 0.999], a)
>>> np.allclose([0.001, 0.5, 0.999], powerlaw.cdf(vals, a))
True
```

Generate random numbers:

```
>>> r = powerlaw.rvs(a, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(a, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, a, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, a, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.powerlognorm

```
scipy.stats.powerlognorm(*args, **kwargs) = <scipy.stats._continuous_distns.
powerlognorm_gen object>
```

A power log-normal continuous random variable.

As an instance of the *rv_continuous* class, *powerlognorm* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *powerlognorm* is:

$$f(x, c, s) = \frac{c}{xs} \phi(\log(x)/s) (\Phi(-\log(x)/s))^{c-1}$$

where ϕ is the normal pdf, and Φ is the normal cdf, and $x > 0, s, c > 0$.

powerlognorm takes *c* and *s* as shape parameters.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `powerlognorm.pdf(x, c, s, loc, scale)` is identically equivalent to `powerlognorm.pdf(y, c, s) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import powerlognorm
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c, s = 2.14, 0.446
>>> mean, var, skew, kurt = powerlognorm.stats(c, s, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(powerlognorm.ppf(0.01, c, s),
...                 powerlognorm.ppf(0.99, c, s), 100)
>>> ax.plot(x, powerlognorm.pdf(x, c, s),
...        'r-', lw=5, alpha=0.6, label='powerlognorm pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = powerlognorm(c, s)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:



```
>>> vals = powerlognorm.ppf([0.001, 0.5, 0.999], c, s)
>>> np.allclose([0.001, 0.5, 0.999], powerlognorm.cdf(vals, c, s))
True
```

Generate random numbers:

```
>>> r = powerlognorm.rvs(c, s, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, s, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, s, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, s, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, s, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, s, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, s, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, s, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, s, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, c, s, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, c, s, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, s, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, s, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c, s), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, s, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, s, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, s, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, s, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, s, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.powernorm

```
scipy.stats.powernorm(*args, **kwds) = <scipy.stats._continuous_distns.
powernorm_gen object>
```

A power normal continuous random variable.

As an instance of the *rv_continuous* class, *powernorm* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *powernorm* is:

$$f(x, c) = c\phi(x)(\Phi(-x))^{c-1}$$

where ϕ is the normal pdf, and Φ is the normal cdf, and $x \geq 0$, $c > 0$.

powernorm takes *c* as a shape parameter for *c*.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `powernorm.pdf(x, c, loc, scale)` is identically equivalent to `powernorm.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import powernorm
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 4.45
>>> mean, var, skew, kurt = powernorm.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(powernorm.ppf(0.01, c),
...                 powernorm.ppf(0.99, c), 100)
>>> ax.plot(x, powernorm.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='powernorm pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = powernorm(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = powernorm.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], powernorm.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = powernorm.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.rdist

`scipy.stats.rdist(*args, **kwargs) = <scipy.stats._continuous_distns.rdist_gen object>`

An R-distributed (symmetric beta) continuous random variable.

As an instance of the `rv_continuous` class, `rdist` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `rdist` is:

$$f(x, c) = \frac{(1 - x^2)^{c/2-1}}{B(1/2, c/2)}$$

for $-1 \leq x \leq 1$, $c > 0$. `rdist` is also called the symmetric beta distribution: if B has a *beta* distribution with parameters $(c/2, c/2)$, then $X = 2*B - 1$ follows a R-distribution with parameter c .

`rdist` takes c as a shape parameter for c .

This distribution includes the following distribution kernels as special cases:

```
c = 2: uniform
c = 3: `semicircular`
c = 4: Epanechnikov (parabolic)
c = 6: quartic (biweight)
c = 8: triweight
```

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `rdist.pdf(x, c, loc, scale)` is identically equivalent to `rdist.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import rdist
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 1.6
>>> mean, var, skew, kurt = rdist.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(rdist.ppf(0.01, c),
...                 rdist.ppf(0.99, c), 100)
>>> ax.plot(x, rdist.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='rdist pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = rdist(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = rdist.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], rdist.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = rdist.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.rayleigh

```
scipy.stats.rayleigh(*args, **kws) = <scipy.stats._continuous_distns.
rayleigh_gen object>
```

A Rayleigh continuous random variable.

As an instance of the *rv_continuous* class, *rayleigh* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *rayleigh* is:

$$f(x) = x \exp(-x^2/2)$$

for $x \geq 0$.

rayleigh is a special case of *chi* with *df*=2.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `rayleigh.pdf(x, loc, scale)` is identically equivalent to `rayleigh.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import rayleigh
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = rayleigh.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(rayleigh.ppf(0.01),
...                 rayleigh.ppf(0.99), 100)
>>> ax.plot(x, rayleigh.pdf(x),
...         'r-', lw=5, alpha=0.6, label='rayleigh pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = rayleigh()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = rayleigh.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], rayleigh.cdf(vals))
True
```

Generate random numbers:

```
>>> r = rayleigh.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```

Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.rice

```
scipy.stats.rice(*args,**kws) = <scipy.stats._continuous_distns.rice_gen object>
```

A Rice continuous random variable.

As an instance of the `rv_continuous` class, `rice` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `rice` is:

$$f(x, b) = x \exp\left(-\frac{x^2 + b^2}{2}\right) I_0(xb)$$

for $x \geq 0, b > 0$. I_0 is the modified Bessel function of order zero (`scipy.special.i0`).

`rice` takes `b` as a shape parameter for b .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `rice.pdf(x, b, loc, scale)` is identically equivalent to `rice.pdf(y, b) / scale` with `y = (x - loc) / scale`. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

The Rice distribution describes the length, r , of a 2-D vector with components $(U + u, V + v)$, where U, V are constant, u, v are independent Gaussian random variables with standard deviation s . Let $R = \sqrt{U^2 + V^2}$. Then the pdf of r is `rice.pdf(x, R/s, scale=s)`.

Examples

```
>>> from scipy.stats import rice
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> b = 0.775
>>> mean, var, skew, kurt = rice.stats(b, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(rice.ppf(0.01, b),
...                 rice.ppf(0.99, b), 100)
>>> ax.plot(x, rice.pdf(x, b),
...         'r-', lw=5, alpha=0.6, label='rice pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = rice(b)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = rice.ppf([0.001, 0.5, 0.999], b)
>>> np.allclose([0.001, 0.5, 0.999], rice.cdf(vals, b))
True
```

Generate random numbers:

```
>>> r = rice.rvs(b, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(b, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, b, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, b, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, b, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, b, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, b, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, b, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, b, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, b, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, b, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(b, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(b, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(b,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(b, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(b, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(b, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(b, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, b, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.recipinvgauss

```
scipy.stats.recipinvgauss(*args, **kws) = <scipy.stats._continuous_distns.
    recipinvgauss_gen object>
```

A reciprocal inverse Gaussian continuous random variable.

As an instance of the `rv_continuous` class, `recipinvgauss` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `recipinvgauss` is:

$$f(x, \mu) = \frac{1}{\sqrt{2\pi x}} \exp\left(\frac{-(1 - \mu x)^2}{2\mu^2 x}\right)$$

for $x \geq 0$.

`recipinvgauss` takes `mu` as a shape parameter for μ .

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `recipinvgauss.pdf(x, mu, loc, scale)` is identically equivalent to `recipinvgauss.pdf(y, mu) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import recipinvgauss
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mu = 0.63
>>> mean, var, skew, kurt = recipinvgauss.stats(mu, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(recipinvgauss.ppf(0.01, mu),
...                 recipinvgauss.ppf(0.99, mu), 100)
>>> ax.plot(x, recipinvgauss.pdf(x, mu),
...         'r-', lw=5, alpha=0.6, label='recipinvgauss pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = recipinvgauss(mu)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = recipinvgauss.ppf([0.001, 0.5, 0.999], mu)
>>> np.allclose([0.001, 0.5, 0.999], recipinvgauss.cdf(vals, mu))
True
```

Generate random numbers:

```
>>> r = recipinvgauss.rvs(mu, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs(mu, loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf(x, mu, loc=0, scale=1)	Probability density function.
logpdf(x, mu, loc=0, scale=1)	Log of the probability density function.
cdf(x, mu, loc=0, scale=1)	Cumulative distribution function.
logcdf(x, mu, loc=0, scale=1)	Log of the cumulative distribution function.
sf(x, mu, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(x, mu, loc=0, scale=1)	Log of the survival function.
ppf(q, mu, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, mu, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment(n, mu, loc=0, scale=1)	Non-central moment of order n
stats(mu, loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(mu, loc=0, scale=1)	(Differential) entropy of the RV.
fit(data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect(func, args=(mu,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)	Expected value of a function (of one argument) with respect to the distribution.
median(mu, loc=0, scale=1)	Median of the distribution.
mean(mu, loc=0, scale=1)	Mean of the distribution.
var(mu, loc=0, scale=1)	Variance of the distribution.
std(mu, loc=0, scale=1)	Standard deviation of the distribution.
interval(alpha, mu, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.semicircular

`scipy.stats.semicircular(*args, **kwargs)` = `<scipy.stats._continuous_distns.semicircular_gen object>`

A semicircular continuous random variable.

As an instance of the `rv_continuous` class, `semicircular` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

`rdist`

Notes

The probability density function for `semicircular` is:

$$f(x) = \frac{2}{\pi} \sqrt{1 - x^2}$$

for $-1 \leq x \leq 1$.

The distribution is a special case of `rdist` with $c = 3$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `semicircular.pdf(x, loc, scale)` is identically equivalent to `semicircular.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

[1]

Examples

```
>>> from scipy.stats import semicircular
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = semicircular.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(semicircular.ppf(0.01),
...                 semicircular.ppf(0.99), 100)
>>> ax.plot(x, semicircular.pdf(x),
...         'r-', lw=5, alpha=0.6, label='semicircular pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = semicircular()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = semicircular.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], semicircular.cdf(vals))
True
```

Generate random numbers:

```
>>> r = semicircular.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.skewnorm

```
scipy.stats.skewnorm(*args, **kws) = <scipy.stats._continuous_distns.
skew_norm_gen object>
```

A skew-normal random variable.

As an instance of the *rv_continuous* class, *skewnorm* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The pdf is:

$$\text{skewnorm.pdf}(x, a) = 2 * \text{norm.pdf}(x) * \text{norm.cdf}(a*x)$$

skewnorm takes a real number *a* as a skewness parameter. When *a* = 0 the distribution is identical to a normal distribution (*norm*). *rvs* implements the method of [1].

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `skewnorm.pdf(x, a, loc, scale)` is identically equivalent to `skewnorm.pdf(y, a) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

[1]

Examples

```
>>> from scipy.stats import skewnorm
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a = 4
>>> mean, var, skew, kurt = skewnorm.stats(a, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(skewnorm.ppf(0.01, a),
...                 skewnorm.ppf(0.99, a), 100)
>>> ax.plot(x, skewnorm.pdf(x, a),
...         'r-', lw=5, alpha=0.6, label='skewnorm pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = skewnorm(a)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = skewnorm.ppf([0.001, 0.5, 0.999], a)
>>> np.allclose([0.001, 0.5, 0.999], skewnorm.cdf(vals, a))
True
```

Generate random numbers:

```
>>> r = skewnorm.rvs(a, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(a, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, a, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, a, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, loc=0, scale=1)</code>	Endpoints of the range that contains <i>alpha</i> percent of the distribution

scipy.stats.t

`scipy.stats.t(*args, **kwargs) = <scipy.stats._continuous_distns.t_gen object>`
 A Student's t continuous random variable.

For the noncentral t distribution, see `nct`.

As an instance of the `rv_continuous` class, `t` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

`nct`

Notes

The probability density function for `t` is:

$$f(x, \nu) = \frac{\Gamma((\nu + 1)/2)}{\sqrt{\pi\nu}\Gamma(\nu/2)} (1 + x^2/\nu)^{-(\nu+1)/2}$$

where x is a real number and the degrees of freedom parameter ν (denoted `df` in the implementation) satisfies $\nu > 0$. Γ is the gamma function (`scipy.special.gamma`).

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `t.pdf(x, df, loc, scale)` is identically equivalent to `t.pdf(y, df) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import t
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> df = 2.74
>>> mean, var, skew, kurt = t.stats(df, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(t.ppf(0.01, df),
...                 t.ppf(0.99, df), 100)
>>> ax.plot(x, t.pdf(x, df),
...         'r-', lw=5, alpha=0.6, label='t pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = t(df)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = t.ppf([0.001, 0.5, 0.999], df)
>>> np.allclose([0.001, 0.5, 0.999], t.cdf(vals, df))
True
```

Generate random numbers:

```
>>> r = t.rvs(df, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

rvs(df, loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf(x, df, loc=0, scale=1)	Probability density function.
logpdf(x, df, loc=0, scale=1)	Log of the probability density function.
cdf(x, df, loc=0, scale=1)	Cumulative distribution function.
logcdf(x, df, loc=0, scale=1)	Log of the cumulative distribution function.
sf(x, df, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(x, df, loc=0, scale=1)	Log of the survival function.
ppf(q, df, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, df, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment(n, df, loc=0, scale=1)	Non-central moment of order <i>n</i>
stats(df, loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(df, loc=0, scale=1)	(Differential) entropy of the RV.
fit(data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect(func, args=(df,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)	Expected value of a function (of one argument) with respect to the distribution.
median(df, loc=0, scale=1)	Median of the distribution.
mean(df, loc=0, scale=1)	Mean of the distribution.
var(df, loc=0, scale=1)	Variance of the distribution.
std(df, loc=0, scale=1)	Standard deviation of the distribution.
interval(alpha, df, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.trapezoid

```
scipy.stats.trapezoid(*args, **kwds) = <scipy.stats._continuous_distns.
trapezoid_gen object>
```

A trapezoidal continuous random variable.

As an instance of the *rv_continuous* class, *trapezoid* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The trapezoidal distribution can be represented with an up-sloping line from *loc* to $(loc + c*scale)$, then constant to $(loc + d*scale)$ and then downsloping from $(loc + d*scale)$ to $(loc+scale)$. This defines the trapezoid base from *loc* to $(loc+scale)$ and the flat top from *c* to *d* proportional to the position along the base with $0 \leq c \leq d \leq 1$. When *c=d*, this is equivalent to *triang* with the same values for *loc*, *scale* and *c*. The method of [1] is used for computing moments.

trapezoid takes *c* and *d* as shape parameters.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `trapezoid.pdf(x, c, d, loc, scale)` is identically equivalent to `trapezoid.pdf(y, c, d) / scale` with $y = (x - loc) / scale$. Note that

shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

The standard form is in the range $[0, 1]$ with c the mode. The location parameter shifts the start to *loc*. The scale parameter changes the width from 1 to *scale*.

References

[1]

Examples

```
>>> from scipy.stats import trapezoid
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c, d = 0.2, 0.8
>>> mean, var, skew, kurt = trapezoid.stats(c, d, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(trapezoid.ppf(0.01, c, d),
...                 trapezoid.ppf(0.99, c, d), 100)
>>> ax.plot(x, trapezoid.pdf(x, c, d),
...         'r-', lw=5, alpha=0.6, label='trapezoid pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = trapezoid(c, d)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = trapezoid.ppf([0.001, 0.5, 0.999], c, d)
>>> np.allclose([0.001, 0.5, 0.999], trapezoid.cdf(vals, c, d))
True
```

Generate random numbers:

```
>>> r = trapezoid.rvs(c, d, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, d, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, d, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, d, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, d, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, d, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, d, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, d, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, d, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, c, d, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, c, d, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, d, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, d, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c, d), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, d, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, d, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, d, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, d, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, d, loc=0, scale=1)</code>	Endpoints of the range that contains <i>alpha</i> percent of the distribution

scipy.stats.triang

```
scipy.stats.triang(*args, **kws) = <scipy.stats._continuous_distns.triang_gen
                                object>
```

A triangular continuous random variable.

As an instance of the `rv_continuous` class, `triang` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The triangular distribution can be represented with an up-sloping line from `loc` to `(loc + c*scale)` and then downsloping for `(loc + c*scale)` to `(loc + scale)`.

`triang` takes `c` as a shape parameter for `c`.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `triang.pdf(x, c, loc, scale)` is identically equivalent to `triang.pdf(y, c) / scale` with `y = (x - loc) / scale`. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

The standard form is in the range `[0, 1]` with `c` the mode. The location parameter shifts the start to `loc`. The scale parameter changes the width from 1 to `scale`.

Examples

```
>>> from scipy.stats import triang
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 0.158
>>> mean, var, skew, kurt = triang.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(triang.ppf(0.01, c),
...                 triang.ppf(0.99, c), 100)
>>> ax.plot(x, triang.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='triang pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = triang(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = triang.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], triang.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = triang.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.truncexpon

```
scipy.stats.truncexpon(*args, **kws) = <scipy.stats._continuous_distns.
truncexpon_gen object>
```

A truncated exponential continuous random variable.

As an instance of the `rv_continuous` class, `truncexpon` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `truncexpon` is:

$$f(x, b) = \frac{\exp(-x)}{1 - \exp(-b)}$$

for $0 \leq x \leq b$.

`truncexpon` takes `b` as a shape parameter for *b*.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `truncexpon.pdf(x, b, loc, scale)` is identically equivalent to `truncexpon.pdf(y, b) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import truncexpon
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> b = 4.69
>>> mean, var, skew, kurt = truncexpon.stats(b, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(truncexpon.ppf(0.01, b),
...                 truncexpon.ppf(0.99, b), 100)
>>> ax.plot(x, truncexpon.pdf(x, b),
...        'r-', lw=5, alpha=0.6, label='truncexpon pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = truncexpon(b)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = truncexpon.ppf([0.001, 0.5, 0.999], b)
>>> np.allclose([0.001, 0.5, 0.999], truncexpon.cdf(vals, b))
True
```

Generate random numbers:

```
>>> r = truncexpon.rvs(b, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(b, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, b, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, b, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, b, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, b, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, b, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, b, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, b, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, b, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, b, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(b, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(b, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(b,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(b, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(b, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(b, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(b, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, b, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.truncnorm

```
scipy.stats.truncnorm(*args, **kws) = <scipy.stats._continuous_distns.
truncnorm_gen object>
```

A truncated normal continuous random variable.

As an instance of the *rv_continuous* class, *truncnorm* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The standard form of this distribution is a standard normal truncated to the range [a, b] — notice that a and b are defined over the domain of the standard normal. To convert clip values for a specific mean and standard deviation, use:

```
a, b = (myclip_a - my_mean) / my_std, (myclip_b - my_mean) / my_std
```

truncnorm takes *a* and *b* as shape parameters.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `truncnorm.pdf(x, a, b, loc, scale)` is identically equivalent to `truncnorm.pdf(y, a, b) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import truncnorm
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a, b = 0.1, 2
>>> mean, var, skew, kurt = truncnorm.stats(a, b, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(truncnorm.ppf(0.01, a, b),
...                 truncnorm.ppf(0.99, a, b), 100)
>>> ax.plot(x, truncnorm.pdf(x, a, b),
...        'r-', lw=5, alpha=0.6, label='truncnorm pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = truncnorm(a, b)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = truncnorm.ppf([0.001, 0.5, 0.999], a, b)
>>> np.allclose([0.001, 0.5, 0.999], truncnorm.cdf(vals, a, b))
True
```

Generate random numbers:

```
>>> r = truncnorm.rvs(a, b, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(a, b, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, a, b, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, a, b, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, a, b, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, a, b, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, a, b, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, a, b, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, a, b, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, a, b, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, a, b, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(a, b, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, b, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(a, b), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, b, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(a, b, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(a, b, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(a, b, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, b, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.tukeylambda

```
scipy.stats.tukeylambda(*args, **kwds) = <scipy.stats._continuous_distns.
    tukeylambda_gen object>
```

A Tukey-Lambda continuous random variable.

As an instance of the *rv_continuous* class, *tukeylambda* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

A flexible distribution, able to represent and interpolate between the following distributions:

- Cauchy (*lambda* = -1)
- logistic (*lambda* = 0)
- approx Normal (*lambda* = 0.14)
- uniform from -1 to 1 (*lambda* = 1)

tukeylambda takes a real number *lambda* (denoted *lam* in the implementation) as a shape parameter.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `tukeylambda.pdf(x, lam, loc, scale)` is identically

equivalent to `tukeylambda.pdf(y, lam) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import tukeylambda
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> lam = 3.13
>>> mean, var, skew, kurt = tukeylambda.stats(lam, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(tukeylambda.ppf(0.01, lam),
...                 tukeylambda.ppf(0.99, lam), 100)
>>> ax.plot(x, tukeylambda.pdf(x, lam),
...         'r-', lw=5, alpha=0.6, label='tukeylambda pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = tukeylambda(lam)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = tukeylambda.ppf([0.001, 0.5, 0.999], lam)
>>> np.allclose([0.001, 0.5, 0.999], tukeylambda.cdf(vals, lam))
True
```

Generate random numbers:

```
>>> r = tukeylambda.rvs(lam, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(lam, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, lam, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, lam, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, lam, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, lam, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, lam, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, lam, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, lam, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, lam, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, lam, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(lam, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(lam, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(lam,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(lam, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(lam, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(lam, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(lam, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, lam, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.uniform

```
scipy.stats.uniform(*args, **kwargs) = <scipy.stats._continuous_distns.
    uniform_gen object>
```

A uniform continuous random variable.

In the standard form, the distribution is uniform on $[0, 1]$. Using the parameters `loc` and `scale`, one obtains the uniform distribution on $[loc, loc + scale]$.

As an instance of the `rv_continuous` class, `uniform` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Examples

```
>>> from scipy.stats import uniform
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = uniform.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(uniform.ppf(0.01),
...                 uniform.ppf(0.99), 100)
>>> ax.plot(x, uniform.pdf(x),
...         'r-', lw=5, alpha=0.6, label='uniform pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = uniform()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = uniform.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], uniform.cdf(vals))
True
```

Generate random numbers:

```
>>> r = uniform.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.vonmises

```
scipy.stats.vonmises(*args, **kwargs) = <scipy.stats._continuous_distns.
    vonmises_gen object>
```

A Von Mises continuous random variable.

As an instance of the *rv_continuous* class, *vonmises* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *vonmises* and *vonmises_line* is:

$$f(x, \kappa) = \frac{\exp(\kappa \cos(x))}{2\pi I_0(\kappa)}$$

for $-\pi \leq x \leq \pi$, $\kappa > 0$. I_0 is the modified Bessel function of order zero (*scipy.special.i0*).

vonmises is a circular distribution which does not restrict the distribution to a fixed interval. Currently, there is no circular distribution framework in *scipy*. The cdf is implemented such that `cdf(x + 2*np.pi) == cdf(x) + 1`.

vonmises_line is the same distribution, defined on $[-\pi, \pi]$ on the real line. This is a regular (i.e. non-circular) distribution.

vonmises and *vonmises_line* take *kappa* as a shape parameter.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `vonmises.pdf(x, kappa, loc, scale)` is identically equivalent to `vonmises.pdf(y, kappa) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import vonmises
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> kappa = 3.99
>>> mean, var, skew, kurt = vonmises.stats(kappa, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(vonmises.ppf(0.01, kappa),
...                 vonmises.ppf(0.99, kappa), 100)
>>> ax.plot(x, vonmises.pdf(x, kappa),
...         'r-', lw=5, alpha=0.6, label='vonmises pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = vonmises(kappa)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = vonmises.ppf([0.001, 0.5, 0.999], kappa)
>>> np.allclose([0.001, 0.5, 0.999], vonmises.cdf(vals, kappa))
True
```

Generate random numbers:

```
>>> r = vonmises.rvs(kappa, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(kappa, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, kappa, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, kappa, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, kappa, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, kappa, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, kappa, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, kappa, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, kappa, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, kappa, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, kappa, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(kappa, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(kappa, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(kappa,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(kappa, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(kappa, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(kappa, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(kappa, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, kappa, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.vonmises_line

```
scipy.stats.vonmises_line(*args, **kws) = <scipy.stats._continuous_distns.vonmises_gen object>
```

A Von Mises continuous random variable.

As an instance of the *rv_continuous* class, *vonmises_line* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *vonmises* and *vonmises_line* is:

$$f(x, \kappa) = \frac{\exp(\kappa \cos(x))}{2\pi I_0(\kappa)}$$

for $-\pi \leq x \leq \pi$, $\kappa > 0$. I_0 is the modified Bessel function of order zero (*scipy.special.i0*).

vonmises is a circular distribution which does not restrict the distribution to a fixed interval. Currently, there is no circular distribution framework in *scipy*. The *cdf* is implemented such that `cdf(x + 2*np.pi) == cdf(x) + 1`.

vonmises_line is the same distribution, defined on $[-\pi, \pi]$ on the real line. This is a regular (i.e. non-circular) distribution.

`vonmises` and `vonmises_line` take `kappa` as a shape parameter.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `vonmises_line.pdf(x, kappa, loc, scale)` is identically equivalent to `vonmises_line.pdf(y, kappa) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import vonmises_line
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> kappa = 3.99
>>> mean, var, skew, kurt = vonmises_line.stats(kappa, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(vonmises_line.ppf(0.01, kappa),
...                 vonmises_line.ppf(0.99, kappa), 100)
>>> ax.plot(x, vonmises_line.pdf(x, kappa),
...         'r-', lw=5, alpha=0.6, label='vonmises_line pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = vonmises_line(kappa)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = vonmises_line.ppf([0.001, 0.5, 0.999], kappa)
>>> np.allclose([0.001, 0.5, 0.999], vonmises_line.cdf(vals, kappa))
True
```

Generate random numbers:

```
>>> r = vonmises_line.rvs(kappa, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```

Methods

rvs(kappa, loc=0, scale=1, size=1, random_state=None)	Random variates.
pdf(x, kappa, loc=0, scale=1)	Probability density function.
logpdf(x, kappa, loc=0, scale=1)	Log of the probability density function.
cdf(x, kappa, loc=0, scale=1)	Cumulative distribution function.
logcdf(x, kappa, loc=0, scale=1)	Log of the cumulative distribution function.
sf(x, kappa, loc=0, scale=1)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(x, kappa, loc=0, scale=1)	Log of the survival function.
ppf(q, kappa, loc=0, scale=1)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, kappa, loc=0, scale=1)	Inverse survival function (inverse of <i>sf</i>).
moment(n, kappa, loc=0, scale=1)	Non-central moment of order <i>n</i>
stats(kappa, loc=0, scale=1, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(kappa, loc=0, scale=1)	(Differential) entropy of the RV.
fit(data)	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
expect(func, args=(kappa,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)	Expected value of a function (of one argument) with respect to the distribution.
median(kappa, loc=0, scale=1)	Median of the distribution.
mean(kappa, loc=0, scale=1)	Mean of the distribution.
var(kappa, loc=0, scale=1)	Variance of the distribution.
std(kappa, loc=0, scale=1)	Standard deviation of the distribution.
interval(alpha, kappa, loc=0, scale=1)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.wald

```
scipy.stats.wald(*args, **kws) = <scipy.stats._continuous_distns.wald_gen object>
```

A Wald continuous random variable.

As an instance of the *rv_continuous* class, *wald* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for *wald* is:

$$f(x) = \frac{1}{\sqrt{2\pi x^3}} \exp\left(-\frac{(x-1)^2}{2x}\right)$$

for $x \geq 0$.

wald is a special case of *invgauss* with $\mu=1$.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the *loc* and *scale* parameters. Specifically, `wald.pdf(x, loc, scale)` is identically equivalent to `wald.pdf(y) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import wald
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mean, var, skew, kurt = wald.stats(moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(wald.ppf(0.01),
...                 wald.ppf(0.99), 100)
>>> ax.plot(x, wald.pdf(x),
...        'r-', lw=5, alpha=0.6, label='wald pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = wald()
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = wald.ppf([0.001, 0.5, 0.999])
>>> np.allclose([0.001, 0.5, 0.999], wald.cdf(vals))
True
```

Generate random numbers:

```
>>> r = wald.rvs(size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, loc=0, scale=1)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, loc=0, scale=1)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>moment(n, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(loc=0, scale=1)</code>	Median of the distribution.
<code>mean(loc=0, scale=1)</code>	Mean of the distribution.
<code>var(loc=0, scale=1)</code>	Variance of the distribution.
<code>std(loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.weibull_min

```
scipy.stats.weibull_min(*args, **kws) = <scipy.stats._continuous_distns.
weibull_min_gen object>
```

Weibull minimum continuous random variable.

The Weibull Minimum Extreme Value distribution, from extreme value theory (Fisher-Gnedenko theorem), is also often simply called the Weibull distribution. It arises as the limiting distribution of the rescaled minimum of iid random variables.

As an instance of the *rv_continuous* class, *weibull_min* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

[weibull_max](#), [numpy.random.RandomState.weibull](#), [exponweib](#)

Notes

The probability density function for `weibull_min` is:

$$f(x, c) = cx^{c-1} \exp(-x^c)$$

for $x > 0, c > 0$.

`weibull_min` takes `c` as a shape parameter for c . (named k in Wikipedia article and a in `numpy.random.weibull`). Special shape values are $c = 1$ and $c = 2$ where Weibull distribution reduces to the `expon` and `rayleigh` distributions respectively.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `weibull_min.pdf(x, c, loc, scale)` is identically equivalent to `weibull_min.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

https://en.wikipedia.org/wiki/Weibull_distribution

https://en.wikipedia.org/wiki/Fisher-Tippett-Gnedenko_theorem

Examples

```
>>> from scipy.stats import weibull_min
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 1.79
>>> mean, var, skew, kurt = weibull_min.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(weibull_min.ppf(0.01, c),
...                 weibull_min.ppf(0.99, c), 100)
>>> ax.plot(x, weibull_min.pdf(x, c),
...        'r-', lw=5, alpha=0.6, label='weibull_min pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = weibull_min(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = weibull_min.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], weibull_min.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = weibull_min.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.weibull_max

```
scipy.stats.weibull_max(*args, **kwds) = <scipy.stats._continuous_distns.
weibull_max_gen object>
```

Weibull maximum continuous random variable.

The Weibull Maximum Extreme Value distribution, from extreme value theory (Fisher-Gnedenko theorem), is the limiting distribution of rescaled maximum of iid random variables. This is the distribution of $-X$ if X is from the `weibull_min` function.

As an instance of the `rv_continuous` class, `weibull_max` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

[weibull_min](#)

Notes

The probability density function for `weibull_max` is:

$$f(x, c) = c(-x)^{c-1} \exp(-(-x)^c)$$

for $x < 0, c > 0$.

`weibull_max` takes `c` as a shape parameter for `c`.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `weibull_max.pdf(x, c, loc, scale)` is identically equivalent to `weibull_max.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

References

https://en.wikipedia.org/wiki/Weibull_distribution

https://en.wikipedia.org/wiki/Fisher-Tippett-Gnedenko_theorem

Examples

```
>>> from scipy.stats import weibull_max
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 2.87
>>> mean, var, skew, kurt = weibull_max.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(weibull_max.ppf(0.01, c),
...                 weibull_max.ppf(0.99, c), 100)
>>> ax.plot(x, weibull_max.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='weibull_max pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = weibull_max(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = weibull_max.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], weibull_max.cdf(vals, c))
True
```

Generate random numbers:


```
>>> r = weibull_max.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kws)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.wrapcauchy

`scipy.stats.wrapcauchy(*args, **kws) = <scipy.stats._continuous_distns.wrapcauchy_gen object>`

A wrapped Cauchy continuous random variable.

As an instance of the `rv_continuous` class, `wrapcauchy` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability density function for `wrapcauchy` is:

$$f(x, c) = \frac{1 - c^2}{2\pi(1 + c^2 - 2c \cos(x))}$$

for $0 \leq x \leq 2\pi, 0 < c < 1$.

`wrapcauchy` takes *c* as a shape parameter for *c*.

The probability density above is defined in the “standardized” form. To shift and/or scale the distribution use the `loc` and `scale` parameters. Specifically, `wrapcauchy.pdf(x, c, loc, scale)` is identically equivalent to `wrapcauchy.pdf(y, c) / scale` with $y = (x - \text{loc}) / \text{scale}$. Note that shifting the location of a distribution does not make it a “noncentral” distribution; noncentral generalizations of some distributions are available in separate classes.

Examples

```
>>> from scipy.stats import wrapcauchy
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> c = 0.0311
>>> mean, var, skew, kurt = wrapcauchy.stats(c, moments='mvsk')
```

Display the probability density function (pdf):

```
>>> x = np.linspace(wrapcauchy.ppf(0.01, c),
...                 wrapcauchy.ppf(0.99, c), 100)
>>> ax.plot(x, wrapcauchy.pdf(x, c),
...         'r-', lw=5, alpha=0.6, label='wrapcauchy pdf')
```

Alternatively, the distribution object can be called (as a function) to fix the shape, location and scale parameters. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pdf:

```
>>> rv = wrapcauchy(c)
>>> ax.plot(x, rv.pdf(x), 'k-', lw=2, label='frozen pdf')
```

Check accuracy of cdf and ppf:


```
>>> vals = wrapcauchy.ppf([0.001, 0.5, 0.999], c)
>>> np.allclose([0.001, 0.5, 0.999], wrapcauchy.cdf(vals, c))
True
```

Generate random numbers:

```
>>> r = wrapcauchy.rvs(c, size=1000)
```

And compare the histogram:

```
>>> ax.hist(r, density=True, histtype='stepfilled', alpha=0.2)
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Methods

<code>rvs(c, loc=0, scale=1, size=1, random_state=None)</code>	Random variates.
<code>pdf(x, c, loc=0, scale=1)</code>	Probability density function.
<code>logpdf(x, c, loc=0, scale=1)</code>	Log of the probability density function.
<code>cdf(x, c, loc=0, scale=1)</code>	Cumulative distribution function.
<code>logcdf(x, c, loc=0, scale=1)</code>	Log of the cumulative distribution function.
<code>sf(x, c, loc=0, scale=1)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(x, c, loc=0, scale=1)</code>	Log of the survival function.
<code>ppf(q, c, loc=0, scale=1)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, c, loc=0, scale=1)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>moment(n, c, loc=0, scale=1)</code>	Non-central moment of order <i>n</i>
<code>stats(c, loc=0, scale=1, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(c, loc=0, scale=1)</code>	(Differential) entropy of the RV.
<code>fit(data)</code>	Parameter estimates for generic data. See scipy.stats.rv_continuous.fit for detailed documentation of the keyword arguments.
<code>expect(func, args=(c,), loc=0, scale=1, lb=None, ub=None, conditional=False, **kwds)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(c, loc=0, scale=1)</code>	Median of the distribution.
<code>mean(c, loc=0, scale=1)</code>	Mean of the distribution.
<code>var(c, loc=0, scale=1)</code>	Variance of the distribution.
<code>std(c, loc=0, scale=1)</code>	Standard deviation of the distribution.
<code>interval(alpha, c, loc=0, scale=1)</code>	Endpoints of the range that contains alpha percent of the distribution

6.29.5 Multivariate distributions

<code>multivariate_normal</code> ([mean, cov, ...])	A multivariate normal random variable.
<code>matrix_normal</code> ([mean, rowcov, colcov, seed])	A matrix normal random variable.
<code>dirichlet</code> (alpha[, seed])	A Dirichlet random variable.
<code>wishart</code> ([df, scale, seed])	A Wishart random variable.
<code>invwishart</code> ([df, scale, seed])	An inverse Wishart random variable.
<code>multinomial</code> (n, p[, seed])	A multinomial random variable.
<code>special_ortho_group</code> ([dim, seed])	A matrix-valued SO(N) random variable.
<code>ortho_group</code>	A matrix-valued O(N) random variable.
<code>unitary_group</code>	A matrix-valued U(N) random variable.
<code>random_correlation</code>	A random correlation matrix.
<code>multivariate_t</code> ([loc, shape, df, ...])	A multivariate t-distributed random variable.
<code>multivariate_hypergeom</code> (m, n[, seed])	A multivariate hypergeometric random variable.

scipy.stats.multivariate_normal

```
scipy.stats.multivariate_normal(mean=None, cov=1, allow_singular=False, seed=None)
= <scipy.stats._multivariate.multivariate_normal_gen object>
```

A multivariate normal random variable.

The *mean* keyword specifies the mean. The *cov* keyword specifies the covariance matrix.

Parameters

- x** [array_like] Quantiles, with the last axis of *x* denoting the components.
- mean** [array_like, optional] Mean of the distribution (default zero)
- cov** [array_like, optional] Covariance matrix of the distribution (default one)
- allow_singular** [bool, optional] Whether to allow a singular covariance matrix. (Default: False)
- random_state** [{None, int, np.random.RandomState, np.random.Generator}, optional] Used for drawing random variates. If *seed* is *None* the *RandomState* singleton is used. If *seed* is an int, a new *RandomState* instance is used, seeded with *seed*. If *seed* is already a *RandomState* or *Generator* instance, then that object is used. Default is *None*.

Alternatively, the object may be called (as a function) to fix the mean and covariance parameters, returning a “frozen” multivariate normal random variable:

```
rv = multivariate_normal(mean=None, cov=1, allow_singular=False)
```

- Frozen object with the same methods but holding the given mean and covariance fixed.

Notes

Setting the parameter mean to None is equivalent to having mean

be the zero-vector. The parameter *cov* can be a scalar, in which case the covariance matrix is the identity times that value, a vector of diagonal entries for the covariance matrix, or a two-dimensional array_like.

The covariance matrix *cov* must be a (symmetric) positive semi-definite matrix. The determinant and inverse of *cov* are computed as the pseudo-determinant and pseudo-inverse, respectively, so that *cov* does not need to have full rank.

The probability density function for `multivariate_normal` is

$$f(x) = \frac{1}{\sqrt{(2\pi)^k \det \Sigma}} \exp\left(-\frac{1}{2}(x - \mu)^T \Sigma^{-1} (x - \mu)\right),$$

where μ is the mean, Σ the covariance matrix, and k is the dimension of the space where x takes values.

New in version 0.14.0.


Examples


```
>>> import matplotlib.pyplot as plt
>>> from scipy.stats import multivariate_normal
```

```
>>> x = np.linspace(0, 5, 10, endpoint=False)
>>> y = multivariate_normal.pdf(x, mean=2.5, cov=0.5); y
array([ 0.00108914,  0.01033349,  0.05946514,  0.20755375,  0.43939129,
        0.56418958,  0.43939129,  0.20755375,  0.05946514,  0.01033349])
>>> fig1 = plt.figure()
>>> ax = fig1.add_subplot(111)
>>> ax.plot(x, y)
```

The input quantiles can be any shape of array, as long as the last axis labels the components. This allows us for instance to display the frozen pdf for a non-isotropic random variable in 2D as follows:

```
>>> x, y = np.mgrid[-1:1:.01, -1:1:.01]
>>> pos = np.dstack((x, y))
>>> rv = multivariate_normal([0.5, -0.2], [[2.0, 0.3], [0.3, 0.5]])
>>> fig2 = plt.figure()
>>> ax2 = fig2.add_subplot(111)
>>> ax2.contourf(x, y, rv.pdf(pos))
```





Methods

<code>pdf(x, mean=None, cov=1, allow_singular=False)</code>	Probability density function.
<code>logpdf(x, mean=None, cov=1, allow_singular=False)</code>	Log of the probability density function.
<code>cdf(x, mean=None, cov=1, allow_singular=False, maxpts=100000*dim, abseps=1e-5, releps=1e-5)</code>	Cumulative distribution function.
<code>logcdf(x, mean=None, cov=1, allow_singular=False, maxpts=100000*dim, abseps=1e-5, releps=1e-5)</code>	Log of the cumulative distribution function.
<code>rvs(mean=None, cov=1, size=1, random_state=None)</code>	Draw random samples from a multivariate normal distribution.
<code>entropy()</code>	Compute the differential entropy of the multivariate normal.

scipy.stats.matrix_normal

`scipy.stats.matrix_normal(mean=None, rowcov=1, colcov=1, seed=None) = <scipy.stats._multivariate.matrix_normal_gen object>`

A matrix normal random variable.

The *mean* keyword specifies the mean. The *rowcov* keyword specifies the among-row covariance matrix. The *colcov* keyword specifies the among-column covariance matrix.

Parameters

X	[array_like] Quantiles, with the last two axes of <i>X</i> denoting the components.
mean	[array_like, optional] Mean of the distribution (default: <i>None</i>)
rowcov	[array_like, optional] Among-row covariance matrix of the distribution (default: <i>1</i>)
colcov	[array_like, optional] Among-column covariance matrix of the distribution (default: <i>1</i>)
random_state	[{None, int, np.random.RandomState, np.random.Generator}, optional] Used for drawing random variates. If <i>seed</i> is <i>None</i> the <i>RandomState</i> singleton is used. If <i>seed</i> is an int, a new <i>RandomState</i> instance is used, seeded with <i>seed</i> . If <i>seed</i> is already a <i>RandomState</i> or <i>Generator</i> instance, then that object is used. Default is <i>None</i> .

Alternatively, the object may be called (as a function) to fix the mean and covariance parameters, returning a “frozen” matrix normal random variable:

```
rv = matrix_normal(mean=None, rowcov=1, colcov=1)
```

- Frozen object with the same methods but holding the given mean and covariance fixed.

Notes

If mean is set to None then a matrix of zeros is used for the mean.

The dimensions of this matrix are inferred from the shape of *rowcov* and *colcov*, if these are provided, or set to 1 if ambiguous.

rowcov and *colcov* can be two-dimensional array_likes specifying the covariance matrices directly. Alternatively, a one-dimensional array will be interpreted as the entries of a diagonal matrix, and a scalar or zero-dimensional array will be interpreted as this value times the identity matrix.

The covariance matrices specified by *rowcov* and *colcov* must be (symmetric) positive definite. If the samples in X are $m \times n$, then *rowcov* must be $m \times m$ and *colcov* must be $n \times n$. *mean* must be the same shape as X .

The probability density function for *matrix_normal* is

$$f(X) = (2\pi)^{-\frac{mn}{2}} |U|^{-\frac{n}{2}} |V|^{-\frac{m}{2}} \exp\left(-\frac{1}{2} \text{Tr} [U^{-1}(X - M)V^{-1}(X - M)^T]\right),$$

where M is the mean, U the among-row covariance matrix, V the among-column covariance matrix.

The *allow_singular* behaviour of the *multivariate_normal* distribution is not currently supported. Covariance matrices must be full rank.

The *matrix_normal* distribution is closely related to the *multivariate_normal* distribution. Specifically, $\text{Vec}(X)$ (the vector formed by concatenating the columns of X) has a multivariate normal distribution with mean $\text{Vec}(M)$ and covariance $V \otimes U$ (where \otimes is the Kronecker product). Sampling and pdf evaluation are $\mathcal{O}(m^3 + n^3 + m^2n + mn^2)$ for the matrix normal, but $\mathcal{O}(m^3n^3)$ for the equivalent multivariate normal, making this equivalent form algorithmically inefficient.

New in version 0.17.0.

Examples

```
>>> from scipy.stats import matrix_normal
```

```
>>> M = np.arange(6).reshape(3,2); M
array([[0, 1],
       [2, 3],
       [4, 5]])
>>> U = np.diag([1,2,3]); U
array([[1, 0, 0],
       [0, 2, 0],
       [0, 0, 3]])
>>> V = 0.3*np.identity(2); V
array([[ 0.3,  0. ],
       [ 0. ,  0.3]])
>>> X = M + 0.1; X
```

(continues on next page)

(continued from previous page)

```
array([[ 0.1,  1.1],
       [ 2.1,  3.1],
       [ 4.1,  5.1]])
>>> matrix_normal.pdf(X, mean=M, rowcov=U, colcov=V)
0.023410202050005054
```

```
>>> # Equivalent multivariate normal
>>> from scipy.stats import multivariate_normal
>>> vectorised_X = X.T.flatten()
>>> equiv_mean = M.T.flatten()
>>> equiv_cov = np.kron(V,U)
>>> multivariate_normal.pdf(vectorised_X, mean=equiv_mean, cov=equiv_cov)
0.023410202050005054
```

Methods

<code>pdf(X, mean=None, rowcov=1, colcov=1)</code>	Probability density function.
<code>logpdf(X, mean=None, rowcov=1, colcov=1)</code>	Log of the probability density function.
<code>rvs(mean=None, rowcov=1, colcov=1, size=1, random_state=None)</code>	Draw random samples.

scipy.stats.dirichlet

`scipy.stats.dirichlet(alpha, seed=None)` = `<scipy.stats._multivariate.dirichlet_gen object>`

A Dirichlet random variable.

The `alpha` keyword specifies the concentration parameters of the distribution.

New in version 0.15.0.

Parameters

- x** [array_like] Quantiles, with the last axis of *x* denoting the components.
- alpha** [array_like] The concentration parameters. The number of entries determines the dimensionality of the distribution.
- random_state** [{None, int, np.random.RandomState, np.random.Generator}, optional] Used for drawing random variates. If *seed* is *None* the *RandomState* singleton is used. If *seed* is an int, a new *RandomState* instance is used, seeded with *seed*. If *seed* is already a *RandomState* or *Generator* instance, then that object is used. Default is *None*.

Alternatively, the object may be called (as a function) to fix concentration parameters, returning a “frozen” Dirichlet random variable:

```
rv = dirichlet(alpha)
```

- Frozen object with the same methods but holding the given concentration parameters fixed.

Notes

Each α entry must be positive. The distribution has only support on the simplex defined by

$$\sum_{i=1}^K x_i = 1$$

where $0 < x_i < 1$.

If the quantiles don't lie within the simplex, a `ValueError` is raised.

The probability density function for `dirichlet` is

$$f(x) = \frac{1}{B(\alpha)} \prod_{i=1}^K x_i^{\alpha_i - 1}$$

where

$$B(\alpha) = \frac{\prod_{i=1}^K \Gamma(\alpha_i)}{\Gamma(\sum_{i=1}^K \alpha_i)}$$

and $\alpha = (\alpha_1, \dots, \alpha_K)$, the concentration parameters and K is the dimension of the space where x takes values.

Note that the dirichlet interface is somewhat inconsistent. The array returned by the rvs function is transposed with respect to the format expected by the pdf and logpdf.

Examples

```
>>> from scipy.stats import dirichlet
```

Generate a dirichlet random variable

```
>>> quantiles = np.array([0.2, 0.2, 0.6]) # specify quantiles
>>> alpha = np.array([0.4, 5, 15]) # specify concentration parameters
>>> dirichlet.pdf(quantiles, alpha)
0.2843831684937255
```

The same PDF but following a log scale

```
>>> dirichlet.logpdf(quantiles, alpha)
-1.2574327653159187
```

Once we specify the dirichlet distribution we can then calculate quantities of interest

```
>>> dirichlet.mean(alpha) # get the mean of the distribution
array([0.01960784, 0.24509804, 0.73529412])
>>> dirichlet.var(alpha) # get variance
array([0.00089829, 0.00864603, 0.00909517])
>>> dirichlet.entropy(alpha) # calculate the differential entropy
-4.3280162474082715
```

We can also return random samples from the distribution

```
>>> dirichlet.rvs(alpha, size=1, random_state=1)
array([[0.00766178, 0.24670518, 0.74563305]])
>>> dirichlet.rvs(alpha, size=2, random_state=2)
array([[0.01639427, 0.1292273 , 0.85437844],
       [0.00156917, 0.19033695, 0.80809388]])
```

Methods

<code>pdf(x, alpha)</code>	Probability density function.
<code>logpdf(x, alpha)</code>	Log of the probability density function.
<code>rvs(alpha, size=1, random_state=None)</code>	Draw random samples from a Dirichlet distribution.
<code>mean(alpha)</code>	The mean of the Dirichlet distribution
<code>var(alpha)</code>	The variance of the Dirichlet distribution
<code>entropy(alpha)</code>	Compute the differential entropy of the Dirichlet distribution.

scipy.stats.wishart

`scipy.stats.wishart` (*df=None, scale=None, seed=None*) = `<scipy.stats._multivariate.wishart_gen object>`

A Wishart random variable.

The *df* keyword specifies the degrees of freedom. The *scale* keyword specifies the scale matrix, which must be symmetric and positive definite. In this context, the scale matrix is often interpreted in terms of a multivariate normal precision matrix (the inverse of the covariance matrix).

Parameters

x [array_like] Quantiles, with the last axis of *x* denoting the components.
df [int] Degrees of freedom, must be greater than or equal to dimension of the scale matrix
scale [array_like] Symmetric positive definite scale matrix of the distribution
random_state [{None, int, np.random.RandomState, np.random.Generator}, optional] Used for drawing random variates. If *seed* is *None* the *RandomState* singleton is used. If *seed* is an int, a new *RandomState* instance is used, seeded with *seed*. If *seed* is already a *RandomState* or *Generator* instance, then that object is used. Default is *None*.

Alternatively, the object may be called (as a function) to fix the degrees of freedom and scale parameters, returning a “frozen” Wishart random variable:

```
rv = wishart(df=1, scale=1)
```

- Frozen object with the same methods but holding the given degrees of freedom and scale fixed.

See also:

[*invwishart*](#), [*chi2*](#)

Notes

The scale matrix *scale* must be a symmetric positive definite matrix. Singular matrices, including the symmetric positive semi-definite case, are not supported.

The Wishart distribution is often denoted

$$W_p(\nu, \Sigma)$$

where ν is the degrees of freedom and Σ is the $p \times p$ scale matrix.

The probability density function for *wishart* has support over positive definite matrices S ; if $S \sim W_p(\nu, \Sigma)$, then its PDF is given by:

$$f(S) = \frac{|S|^{\frac{\nu-p-1}{2}}}{2^{\frac{\nu p}{2}} |\Sigma|^{\frac{\nu}{2}} \Gamma_p\left(\frac{\nu}{2}\right)} \exp(-tr(\Sigma^{-1}S)/2)$$

If $S \sim W_p(\nu, \Sigma)$ (Wishart) then $S^{-1} \sim W_p^{-1}(\nu, \Sigma^{-1})$ (inverse Wishart).

If the scale matrix is 1-dimensional and equal to one, then the Wishart distribution $W_1(\nu, 1)$ collapses to the $\chi^2(\nu)$ distribution.

New in version 0.16.0.

References

[1], [2]


Examples

```
>>> import matplotlib.pyplot as plt
>>> from scipy.stats import wishart, chi2
>>> x = np.linspace(1e-5, 8, 100)
>>> w = wishart.pdf(x, df=3, scale=1); w[:5]
array([ 0.00126156,  0.10892176,  0.14793434,  0.17400548,  0.1929669 ])
>>> c = chi2.pdf(x, 3); c[:5]
array([ 0.00126156,  0.10892176,  0.14793434,  0.17400548,  0.1929669 ])
>>> plt.plot(x, w)
```

The input quantiles can be any shape of array, as long as the last axis labels the components.

Methods

<code>pdf(x, df, scale)</code>	Probability density function.
<code>logpdf(x, df, scale)</code>	Log of the probability density function.
<code>rvs(df, scale, size=1, random_state=None)</code>	Draw random samples from a Wishart distribution.
<code>entropy()</code>	Compute the differential entropy of the Wishart distribution.



scipy.stats.invwishart

`scipy.stats.invwishart` (*df=None*, *scale=None*, *seed=None*) = `<scipy.stats._multivariate.invwishart_gen object>`

An inverse Wishart random variable.

The *df* keyword specifies the degrees of freedom. The *scale* keyword specifies the scale matrix, which must be symmetric and positive definite. In this context, the scale matrix is often interpreted in terms of a multivariate normal covariance matrix.

Parameters

x [array_like] Quantiles, with the last axis of *x* denoting the components.
df [int] Degrees of freedom, must be greater than or equal to dimension of the scale matrix
scale [array_like] Symmetric positive definite scale matrix of the distribution
random_state [{None, int, np.random.RandomState, np.random.Generator}, optional] Used for drawing random variates. If *seed* is *None* the *RandomState* singleton is used. If *seed* is an int, a new *RandomState* instance is used, seeded with *seed*. If *seed* is already a *RandomState* or *Generator* instance, then that object is used. Default is *None*.

Alternatively, the object may be called (as a function) to fix the degrees of freedom and scale parameters, returning a “frozen” inverse Wishart random variable:

```
rv = invwishart(df=1, scale=1)
```

- Frozen object with the same methods but holding the given degrees of freedom and scale fixed.

See also:

[*wishart*](#)

Notes

The scale matrix *scale* must be a symmetric positive definite matrix. Singular matrices, including the symmetric positive semi-definite case, are not supported.

The inverse Wishart distribution is often denoted

$$W_p^{-1}(\nu, \Psi)$$

where ν is the degrees of freedom and Ψ is the $p \times p$ scale matrix.

The probability density function for `invwishart` has support over positive definite matrices S ; if $S \sim W_p^{-1}(\nu, \Sigma)$, then its PDF is given by:

$$f(S) = \frac{|\Sigma|^{\frac{\nu}{2}}}{2^{\frac{\nu p}{2}} |S|^{\frac{\nu+p+1}{2}} \Gamma_p\left(\frac{\nu}{2}\right)} \exp(-\text{tr}(\Sigma S^{-1})/2)$$

If $S \sim W_p^{-1}(\nu, \Psi)$ (inverse Wishart) then $S^{-1} \sim W_p(\nu, \Psi^{-1})$ (Wishart).

If the scale matrix is 1-dimensional and equal to one, then the inverse Wishart distribution $W_1(\nu, 1)$ collapses to the inverse Gamma distribution with parameters shape = $\frac{\nu}{2}$ and scale = $\frac{1}{2}$.

New in version 0.16.0.

References

[1], [2]


Examples

```
>>> import matplotlib.pyplot as plt
>>> from scipy.stats import invwishart, invgamma
>>> x = np.linspace(0.01, 1, 100)
>>> iw = invwishart.pdf(x, df=6, scale=1)
>>> iw[:3]
array([ 1.20546865e-15,  5.42497807e-06,  4.45813929e-03])
>>> ig = invgamma.pdf(x, 6/2., scale=1./2)
>>> ig[:3]
array([ 1.20546865e-15,  5.42497807e-06,  4.45813929e-03])
>>> plt.plot(x, iw)
```

The input quantiles can be any shape of array, as long as the last axis labels the components.

Methods

<code>pdf(x, df, scale)</code>	Probability density function.
<code>logpdf(x, df, scale)</code>	Log of the probability density function.
<code>rvs(df, scale, size=1, random_state=None)</code>	Draw random samples from an inverse Wishart distribution.



scipy.stats.multinomial

`scipy.stats.multinomial(n, p, seed=None)` = `<scipy.stats._multivariate.multinomial_gen object>`

A multinomial random variable.

Parameters

x [array_like] Quantiles, with the last axis of x denoting the components.
n [int] Number of trials
p [array_like] Probability of a trial falling into each category; should sum to 1
random_state

[{None, int, np.random.RandomState, np.random.Generator}, optional] Used for drawing random variates. If *seed* is *None* the *RandomState* singleton is used. If *seed* is an int, a new *RandomState* instance is used, seeded with *seed*. If *seed* is already a *RandomState* or *Generator* instance, then that object is used. Default is *None*.

See also:

`scipy.stats.binom`

The binomial distribution.

`numpy.random.Generator.multinomial`

Sampling from the multinomial distribution.

`scipy.stats.multivariate_hyergeom`

The multivariate hypergeometric distribution.

Notes

n should be a positive integer. Each element of p should be in the interval $[0, 1]$ and the elements should sum to 1. If they do not sum to 1, the last element of the p array is not used and is replaced with the remaining probability left over from the earlier elements.

Alternatively, the object may be called (as a function) to fix the n and p parameters, returning a “frozen” multinomial random variable:

The probability mass function for *multinomial* is

$$f(x) = \frac{n!}{x_1! \cdots x_k!} p_1^{x_1} \cdots p_k^{x_k},$$

supported on $x = (x_1, \dots, x_k)$ where each x_i is a nonnegative integer and their sum is n .

New in version 0.19.0.

Examples

```
>>> from scipy.stats import multinomial
>>> rv = multinomial(8, [0.3, 0.2, 0.5])
>>> rv.pmf([1, 3, 4])
0.0420000000000000072
```

The multinomial distribution for $k = 2$ is identical to the corresponding binomial distribution (tiny numerical differences notwithstanding):

```
>>> from scipy.stats import binom
>>> multinomial.pmf([3, 4], n=7, p=[0.4, 0.6])
0.290303999999999973
>>> binom.pmf(3, 7, 0.4)
0.290304000000000012
```

The functions `pmf`, `logpmf`, `entropy`, and `cov` support broadcasting, under the convention that the vector parameters (x and p) are interpreted as if each row along the last axis is a single object. For instance:

```
>>> multinomial.pmf([[3, 4], [3, 5]], n=[7, 8], p=[.3, .7])
array([0.2268945, 0.25412184])
```

Here, `x.shape == (2, 2)`, `n.shape == (2,)`, and `p.shape == (2,)`, but following the rules mentioned above they behave as if the rows `[3, 4]` and `[3, 5]` in `x` and `[.3, .7]` in `p` were a single object, and as if we had `x.shape = (2,)`, `n.shape = (2,)`, and `p.shape = ()`. To obtain the individual elements without broadcasting, we would do this:

```
>>> multinomial.pmf([3, 4], n=7, p=[.3, .7])
0.2268945
>>> multinomial.pmf([3, 5], 8, p=[.3, .7])
0.25412184
```

This broadcasting also works for `cov`, where the output objects are square matrices of size `p.shape[-1]`. For example:

```
>>> multinomial.cov([4, 5], [[.3, .7], [.4, .6]])
array([[ [ 0.84, -0.84],
```

(continues on next page)

(continued from previous page)

```

    [-0.84,  0.84]],
    [[ 1.2 , -1.2 ],
     [-1.2 ,  1.2 ]]])

```

In this example, `n.shape == (2,)` and `p.shape == (2, 2)`, and following the rules above, these broadcast as if `p.shape == (2,)`. Thus the result should also be of shape `(2,)`, but since each output is a 2×2 matrix, the result in fact has shape `(2, 2, 2)`, where `result[0]` is equal to `multinomial.cov(n=4, p=[.3, .7])` and `result[1]` is equal to `multinomial.cov(n=5, p=[.4, .6])`.

Methods

<code>pmf(x, n, p)</code>	Probability mass function.
<code>logpmf(x, n, p)</code>	Log of the probability mass function.
<code>rvs(n, p, size=1, random_state=None)</code>	Draw random samples from a multinomial distribution.
<code>entropy(n, p)</code>	Compute the entropy of the multinomial distribution.
<code>cov(n, p)</code>	Compute the covariance matrix of the multinomial distribution.

scipy.stats.special_ortho_group

```

scipy.stats.special_ortho_group(dim=None, seed=None) = <scipy.stats.
    _multivariate.special_ortho_group_gen
    object>

```

A matrix-valued SO(N) random variable.

Return a random rotation matrix, drawn from the Haar distribution (the only uniform distribution on SO(n)).

The `dim` keyword specifies the dimension N.

Parameters

dim [scalar] Dimension of matrices

See also:

`ortho_group`, `scipy.spatial.transform.Rotation.random`

Notes

This class is wrapping the `random_rot` code from the MDP Toolkit, <https://github.com/mdp-toolkit/mdp-toolkit>

Return a random rotation matrix, drawn from the Haar distribution (the only uniform distribution on SO(n)). The algorithm is described in the paper Stewart, G.W., “The efficient generation of random orthogonal matrices with an application to condition estimators”, SIAM Journal on Numerical Analysis, 17(3), pp. 403-409, 1980. For more information see https://en.wikipedia.org/wiki/Orthogonal_matrix#Randomization

See also the similar `ortho_group`. For a random rotation in three dimensions, see `scipy.spatial.transform.Rotation.random`.

Examples

```
>>> from scipy.stats import special_ortho_group
>>> x = special_ortho_group.rvs(3)
```

```
>>> np.dot(x, x.T)
array([[ 1.00000000e+00,  1.13231364e-17, -2.86852790e-16],
       [ 1.13231364e-17,  1.00000000e+00, -1.46845020e-16],
       [-2.86852790e-16, -1.46845020e-16,  1.00000000e+00]])
```

```
>>> import scipy.linalg
>>> scipy.linalg.det(x)
1.0
```

This generates one random matrix from SO(3). It is orthogonal and has a determinant of 1.

Methods

<code>rvs(dim=None, size=1, random_state=None)</code>	Draw random samples from SO(N).
---	---------------------------------

scipy.stats.ortho_group

`scipy.stats.ortho_group` = <scipy.stats._multivariate.ortho_group_gen object>

A matrix-valued O(N) random variable.

Return a random orthogonal matrix, drawn from the O(N) Haar distribution (the only uniform distribution on O(N)).

The *dim* keyword specifies the dimension N.

Parameters

dim [scalar] Dimension of matrices

Notes

This class is closely related to *special_ortho_group*.

Some care is taken to avoid numerical error, as per the paper by Mezzadri.

References

[1]

Examples

```
>>> from scipy.stats import ortho_group
>>> x = ortho_group.rvs(3)
```

```
>>> np.dot(x, x.T)
array([[ 1.00000000e+00,  1.13231364e-17, -2.86852790e-16],
       [ 1.13231364e-17,  1.00000000e+00, -1.46845020e-16],
       [-2.86852790e-16, -1.46845020e-16,  1.00000000e+00]])
```

```
>>> import scipy.linalg
>>> np.fabs(scipy.linalg.det(x))
1.0
```

This generates one random matrix from $O(3)$. It is orthogonal and has a determinant of +1 or -1.

Methods

<code>rvs(dim=None, size=1, random_state=None)</code>	Draw random samples from $O(N)$.
---	-----------------------------------

scipy.stats.unitary_group

`scipy.stats.unitary_group` = <scipy.stats._multivariate.unitary_group_gen object>
A matrix-valued $U(N)$ random variable.

Return a random unitary matrix.

The *dim* keyword specifies the dimension N .

Parameters

dim [scalar] Dimension of matrices

Notes

This class is similar to `ortho_group`.

References

[1]

Examples

```
>>> from scipy.stats import unitary_group
>>> x = unitary_group.rvs(3)
```

```
>>> np.dot(x, x.conj().T)
array([[ 1.00000000e+00,  1.13231364e-17, -2.86852790e-16],
       [ 1.13231364e-17,  1.00000000e+00, -1.46845020e-16],
       [-2.86852790e-16, -1.46845020e-16,  1.00000000e+00]])
```

This generates one random matrix from $U(3)$. The dot product confirms that it is unitary up to machine precision.

Methods

<code>``rvs(dim=None, size=1, random_state=None)``</code>	Draw random samples from $U(N)$.
---	-----------------------------------

scipy.stats.random_correlation

`scipy.stats.random_correlation = <scipy.stats._multivariate.random_correlation_gen object>`

A random correlation matrix.

Return a random correlation matrix, given a vector of eigenvalues.

The *eigs* keyword specifies the eigenvalues of the correlation matrix, and implies the dimension.

Parameters

eigs [1d ndarray] Eigenvalues of correlation matrix.

Notes

Generates a random correlation matrix following a numerically stable algorithm spelled out by Davies & Higham. This algorithm uses a single $O(N)$ similarity transformation to construct a symmetric positive semi-definite matrix, and applies a series of Givens rotations to scale it to have ones on the diagonal.

References

[1]

Examples

```
>>> from scipy.stats import random_correlation
>>> np.random.seed(514)
>>> x = random_correlation.rvs((.5, .8, 1.2, 1.5))
>>> x
array([[ 1.          , -0.20387311,  0.18366501, -0.04953711],
       [-0.20387311,  1.          , -0.24351129,  0.06703474],
       [ 0.18366501, -0.24351129,  1.          ,  0.38530195],
       [-0.04953711,  0.06703474,  0.38530195,  1.          ]])
```

(continues on next page)

(continued from previous page)

```
>>> import scipy.linalg
>>> e, v = scipy.linalg.eigh(x)
>>> e
array([ 0.5,  0.8,  1.2,  1.5])
```

Methods

```
``rvs(eigs=None, random_state=None)`` Draw random correlation matrices, all with eigenvalues eigs.
```

scipy.stats.multivariate_t

```
scipy.stats.multivariate_t(loc=None, shape=1, df=1, allow_singular=False, seed=None) =
    <scipy.stats._multivariate.multivariate_t_gen
    object>
```

A multivariate t-distributed random variable.

The *loc* parameter specifies the location. The *shape* parameter specifies the positive semidefinite shape matrix. The *df* parameter specifies the degrees of freedom.

In addition to calling the methods below, the object itself may be called as a function to fix the location, shape matrix, and degrees of freedom parameters, returning a “frozen” multivariate t-distribution random.

Parameters

x [array_like] Quantiles, with the last axis of *x* denoting the components.

loc [array_like, optional] Location of the distribution. (default 0)

shape [array_like, optional] Positive semidefinite matrix of the distribution. (default 1)

df [float, optional] Degrees of freedom of the distribution; must be greater than zero. If `np.inf` then results are multivariate normal. The default is 1.

allow_singular [bool, optional] Whether to allow a singular matrix. (default `False`)

random_state [{None, int, np.random.RandomState, np.random.Generator}, optional] Used for drawing random variates. If *seed* is `None` the `RandomState` singleton is used. If *seed* is an int, a new `RandomState` instance is used, seeded with *seed*. If *seed* is already a `RandomState` or `Generator` instance, then that object is used. Default is `None`.

Notes

Setting the parameter *loc* to `None` is equivalent to having *loc* be the zero-vector. The parameter *shape* can be a scalar, in which case the shape matrix is the identity times that value, a vector of diagonal entries for the shape matrix, or a two-dimensional array_like. The matrix *shape* must be a (symmetric) positive semidefinite matrix. The determinant and inverse of *shape* are computed as the pseudo-determinant and pseudo-inverse, respectively, so that *shape* does not need to have full rank.

The probability density function for *multivariate_t* is


$$f(x) = \frac{\Gamma(\nu + p)/2}{\Gamma(\nu/2)\nu^{p/2}\pi^{p/2}|\Sigma|^{1/2}} \exp \left[1 + \frac{1}{\nu}(\mathbf{x} - \boldsymbol{\mu})^\top \Sigma^{-1}(\mathbf{x} - \boldsymbol{\mu}) \right]^{-(\nu+p)/2},$$

where *p* is the dimension of **x**, **μ** is the *p*-dimensional location, **Σ** the *p* × *p*-dimensional shape matrix, and *ν* is the degrees of freedom.

New in version 1.6.0.

Examples

```
>>> import matplotlib.pyplot as plt
>>> from scipy.stats import multivariate_t
>>> x, y = np.mgrid[-1:3:.01, -2:1.5:.01]
>>> pos = np.dstack((x, y))
>>> rv = multivariate_t([1.0, -0.5], [[2.1, 0.3], [0.3, 1.5]], df=2)
>>> fig, ax = plt.subplots(1, 1)
>>> ax.set_aspect('equal')
>>> plt.contourf(x, y, rv.pdf(pos))
```



Methods

<code>pdf(x, loc=None, shape=1, df=1, allow_singular=False)</code>	Probability density function.
<code>logpdf(x, loc=None, shape=1, df=1, allow_singular=False)</code>	Log of the probability density function.
<code>rvs(loc=None, shape=1, df=1, size=1, random_state=None)</code>	Draw random samples from a multivariate t-distribution.

scipy.stats.multivariate_hypergeom

```
scipy.stats.multivariate_hypergeom(m, n, seed=None) = <scipy.
stats._multivariate.
multivariate_hypergeom_gen object>
```

A multivariate hypergeometric random variable.

Parameters

- m** [array_like] The number of each type of object in the population. That is, $m[i]$ is the number of objects of type i .
- n** [array_like] The number of samples taken from the population.
- random_state** [{None, int, np.random.RandomState, np.random.Generator}, optional] Used for drawing random variates. If *seed* is *None* the *RandomState* singleton is used. If *seed* is an int, a new *RandomState* instance is used, seeded with *seed*. If *seed* is already a *RandomState* or *Generator* instance, then that object is used. Default is *None*.

See also:

[*scipy.stats.hypergeom*](#)

The hypergeometric distribution.

[*scipy.stats.multinomial*](#)

The multinomial distribution.

Notes

m must be an array of positive integers. If the quantile i contains values out of the range $[0, m_i]$ where m_i is the number of objects of type i in the population or if the parameters are inconsistent with one another (e.g. $x.sum() \neq n$), methods return the appropriate value (e.g. 0 for pmf). If m or n contain negative values, the result will contain *nan* there.

The probability mass function for *multivariate_hypergeom* is

$$P(X_1 = x_1, X_2 = x_2, \dots, X_k = x_k) = \frac{\binom{m_1}{x_1} \binom{m_2}{x_2} \dots \binom{m_k}{x_k}}{\binom{M}{n}},$$

$$(x_1, x_2, \dots, x_k) \in \mathbb{N}^k \text{ with } \sum_{i=1}^k x_i = n$$

where m_i are the number of objects of type i , M is the total number of objects in the population (sum of all the m_i), and n is the size of the sample to be taken from the population.

New in version 1.6.0.

References

[1], [2]

Examples

To evaluate the probability mass function of the multivariate hypergeometric distribution, with a dichotomous population of size 10 and 20, at a sample of size 12 with 8 objects of the first type and 4 objects of the second type, use:

```
>>> from scipy.stats import multivariate_hypergeom
>>> multivariate_hypergeom.pmf(x=[8, 4], m=[10, 20], n=12)
0.0025207176631464523
```

The *multivariate_hypergeom* distribution is identical to the corresponding *hypergeom* distribution (tiny numerical differences notwithstanding) when only two types (good and bad) of objects are present in the population as in the example above. Consider another example for a comparison with the hypergeometric distribution:

```
>>> from scipy.stats import hypergeom
>>> multivariate_hypergeom.pmf(x=[3, 1], m=[10, 5], n=4)
0.4395604395604395
>>> hypergeom.pmf(k=3, M=15, n=4, N=10)
0.43956043956044005
```

The functions `pmf`, `logpmf`, `mean`, `var`, `cov`, and `rvs` support broadcasting, under the convention that the vector parameters (`x`, `m`, and `n`) are interpreted as if each row along the last axis is a single object. For instance, we can combine the previous two calls to *multivariate_hypergeom* as

```
>>> multivariate_hypergeom.pmf(x=[[8, 4], [3, 1]], m=[[10, 20], [10, 5]],
...                             n=[12, 4])
array([0.00252072, 0.43956044])
```

This broadcasting also works for `cov`, where the output objects are square matrices of size `m.shape[-1]`. For example:

```
>>> multivariate_hypergeom.cov(m=[[7, 9], [10, 15]], n=[8, 12])
array([[ [ 1.05, -1.05],
        [-1.05,  1.05]],
       [[ 1.56, -1.56],
        [-1.56,  1.56]]])
```

That is, `result[0]` is equal to `multivariate_hypergeom.cov(m=[7, 9], n=8)` and `result[1]` is equal to `multivariate_hypergeom.cov(m=[10, 15], n=12)`.

Alternatively, the object may be called (as a function) to fix the *m* and *n* parameters, returning a “frozen” multivariate hypergeometric random variable.

```
>>> rv = multivariate_hypergeom(m=[10, 20], n=12)
>>> rv.pmf(x=[8, 4])
0.0025207176631464523
```


Methods

<code>pmf(x, m, n)</code>	Probability mass function.
<code>logpmf(x, m, n)</code>	Log of the probability mass function.
<code>rvs(m, n, size=1, random_state=None)</code>	Draw random samples from a multivariate hypergeometric distribution.
<code>mean(m, n)</code>	Mean of the multivariate hypergeometric distribution.
<code>var(m, n)</code>	Variance of the multivariate hypergeometric distribution.
<code>cov(m, n)</code>	Compute the covariance matrix of the multivariate hypergeometric distribution.

6.29.6 Discrete distributions

<code>bernoulli(*args, **kwargs)</code>	A Bernoulli discrete random variable.
<code>betabinom(*args, **kwargs)</code>	A beta-binomial discrete random variable.
<code>binom(*args, **kwargs)</code>	A binomial discrete random variable.
<code>boltzmann(*args, **kwargs)</code>	A Boltzmann (Truncated Discrete Exponential) random variable.
<code>dlaplace(*args, **kwargs)</code>	A Laplacian discrete random variable.
<code>geom(*args, **kwargs)</code>	A geometric discrete random variable.
<code>hypergeom(*args, **kwargs)</code>	A hypergeometric discrete random variable.
<code>logser(*args, **kwargs)</code>	A Logarithmic (Log-Series, Series) discrete random variable.
<code>nbinom(*args, **kwargs)</code>	A negative binomial discrete random variable.
<code>nhypergeom(*args, **kwargs)</code>	A negative hypergeometric discrete random variable.
<code>planck(*args, **kwargs)</code>	A Planck discrete exponential random variable.
<code>poisson(*args, **kwargs)</code>	A Poisson discrete random variable.
<code>randint(*args, **kwargs)</code>	A uniform discrete random variable.
<code>skellam(*args, **kwargs)</code>	A Skellam discrete random variable.
<code>zipf(*args, **kwargs)</code>	A Zipf discrete random variable.
<code>yulesimon(*args, **kwargs)</code>	A Yule-Simon discrete random variable.

scipy.stats.bernoulli

```
scipy.stats.bernoulli(*args, **kwargs) = <scipy.stats._discrete_distns.bernoulli_gen object>
```

A Bernoulli discrete random variable.

As an instance of the `rv_discrete` class, `bernoulli` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability mass function for *bernoulli* is:

$$f(k) = \begin{cases} 1 - p & \text{if } k = 0 \\ p & \text{if } k = 1 \end{cases}$$

for k in $\{0, 1\}$, $0 \leq p \leq 1$

bernoulli takes p as shape parameter, where p is the probability of a single success and $1 - p$ is the probability of a single failure.

The probability mass function above is defined in the “standardized” form. To shift distribution use the `loc` parameter. Specifically, `bernoulli.pmf(k, p, loc)` is identically equivalent to `bernoulli.pmf(k - loc, p)`.

Examples

```
>>> from scipy.stats import bernoulli
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> p = 0.3
>>> mean, var, skew, kurt = bernoulli.stats(p, moments='mvsk')
```

Display the probability mass function (pmf):

```
>>> x = np.arange(bernoulli.ppf(0.01, p),
...               bernoulli.ppf(0.99, p))
>>> ax.plot(x, bernoulli.pmf(x, p), 'bo', ms=8, label='bernoulli pmf')
>>> ax.vlines(x, 0, bernoulli.pmf(x, p), colors='b', lw=5, alpha=0.5)
```

Alternatively, the distribution object can be called (as a function) to fix the shape and location. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pmf:


```
>>> rv = bernoulli(p)
>>> ax.vlines(x, 0, rv.pmf(x), colors='k', linestyle='-', lw=1,
...          label='frozen pmf')
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```

Check accuracy of cdf and ppf:

```
>>> prob = bernoulli.cdf(x, p)
>>> np.allclose(x, bernoulli.ppf(prob, p))
True
```

Generate random numbers:

```
>>> r = bernoulli.rvs(p, size=1000)
```



Methods

<code>rvs(p, loc=0, size=1, random_state=None)</code>	Random variates.
<code>pmf(k, p, loc=0)</code>	Probability mass function.
<code>logpmf(k, p, loc=0)</code>	Log of the probability mass function.
<code>cdf(k, p, loc=0)</code>	Cumulative distribution function.
<code>logcdf(k, p, loc=0)</code>	Log of the cumulative distribution function.
<code>sf(k, p, loc=0)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(k, p, loc=0)</code>	Log of the survival function.
<code>ppf(q, p, loc=0)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, p, loc=0)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>stats(p, loc=0, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(p, loc=0)</code>	(Differential) entropy of the RV.
<code>expect(func, args=(p,), loc=0, lb=None, ub=None, conditional=False)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(p, loc=0)</code>	Median of the distribution.
<code>mean(p, loc=0)</code>	Mean of the distribution.
<code>var(p, loc=0)</code>	Variance of the distribution.
<code>std(p, loc=0)</code>	Standard deviation of the distribution.
<code>interval(alpha, p, loc=0)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.betabinom

`scipy.stats.betabinom(*args, **kwargs)` = `<scipy.stats._discrete_distns.betabinom_gen object>`

A beta-binomial discrete random variable.

As an instance of the `rv_discrete` class, `betabinom` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

`beta`, `binom`

Notes

The beta-binomial distribution is a binomial distribution with a probability of success p that follows a beta distribution.

The probability mass function for `betabinom` is:

$$f(k) = \binom{n}{k} \frac{B(k+a, n-k+b)}{B(a, b)}$$

for k in $\{0, 1, \dots, n\}$, $n \geq 0$, $a > 0$, $b > 0$, where $B(a, b)$ is the beta function.

`betabinom` takes n , a , and b as shape parameters.

References

The probability mass function above is defined in the “standardized” form. To shift distribution use the `loc` parameter. Specifically, `betabinom.pmf(k, n, a, b, loc)` is identically equivalent to `betabinom.pmf(k - loc, n, a, b)`.

New in version 1.4.0.

[1]

Examples

```
>>> from scipy.stats import betabinom
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> n, a, b = 5, 2.3, 0.63
>>> mean, var, skew, kurt = betabinom.stats(n, a, b, moments='mvsk')
```


Display the probability mass function (pmf):

```
>>> x = np.arange(betabinom.ppf(0.01, n, a, b),
...               betabinom.ppf(0.99, n, a, b))
>>> ax.plot(x, betabinom.pmf(x, n, a, b), 'bo', ms=8, label='betabinom pmf
→')
>>> ax.vlines(x, 0, betabinom.pmf(x, n, a, b), colors='b', lw=5, alpha=0.
→5)
```

Alternatively, the distribution object can be called (as a function) to fix the shape and location. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pmf:

```
>>> rv = betabinom(n, a, b)
>>> ax.vlines(x, 0, rv.pmf(x), colors='k', linestyle='-', lw=1,
...          label='frozen pmf')
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Check accuracy of cdf and ppf:

```
>>> prob = betabinom.cdf(x, n, a, b)
>>> np.allclose(x, betabinom.ppf(prob, n, a, b))
True
```

Generate random numbers:

```
>>> r = betabinom.rvs(n, a, b, size=1000)
```

Methods

<code>rvs(n, a, b, loc=0, size=1, random_state=None)</code>	Random variates.
<code>pmf(k, n, a, b, loc=0)</code>	Probability mass function.
<code>logpmf(k, n, a, b, loc=0)</code>	Log of the probability mass function.
<code>cdf(k, n, a, b, loc=0)</code>	Cumulative distribution function.
<code>logcdf(k, n, a, b, loc=0)</code>	Log of the cumulative distribution function.
<code>sf(k, n, a, b, loc=0)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(k, n, a, b, loc=0)</code>	Log of the survival function.
<code>ppf(q, n, a, b, loc=0)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, n, a, b, loc=0)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>stats(n, a, b, loc=0, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(n, a, b, loc=0)</code>	(Differential) entropy of the RV.
<code>expect(func, args=(n, a, b), loc=0, lb=None, ub=None, conditional=False)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(n, a, b, loc=0)</code>	Median of the distribution.
<code>mean(n, a, b, loc=0)</code>	Mean of the distribution.
<code>var(n, a, b, loc=0)</code>	Variance of the distribution.
<code>std(n, a, b, loc=0)</code>	Standard deviation of the distribution.
<code>interval(alpha, n, a, b, loc=0)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.binom

`scipy.stats.binom(*args, **kwargs) = <scipy.stats._discrete_distns.binom_gen object>`

A binomial discrete random variable.

As an instance of the *rv_discrete* class, *binom* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

hypergeom, *nbinom*, *nhypergeom*

Notes

The probability mass function for *binom* is:

$$f(k) = \binom{n}{k} p^k (1-p)^{n-k}$$

for k in $\{0, 1, \dots, n\}$, $0 \leq p \leq 1$

binom takes n and p as shape parameters, where p is the probability of a single success and $1-p$ is the probability of a single failure.

The probability mass function above is defined in the “standardized” form. To shift distribution use the *loc* parameter. Specifically, `binom.pmf(k, n, p, loc)` is identically equivalent to `binom.pmf(k - loc, n, p)`.

Examples

```
>>> from scipy.stats import binom
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> n, p = 5, 0.4
>>> mean, var, skew, kurt = binom.stats(n, p, moments='mvsk')
```


Display the probability mass function (pmf):

```
>>> x = np.arange(binom.ppf(0.01, n, p),
...               binom.ppf(0.99, n, p))
>>> ax.plot(x, binom.pmf(x, n, p), 'bo', ms=8, label='binom pmf')
>>> ax.vlines(x, 0, binom.pmf(x, n, p), colors='b', lw=5, alpha=0.5)
```

Alternatively, the distribution object can be called (as a function) to fix the shape and location. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pmf:

```
>>> rv = binom(n, p)
>>> ax.vlines(x, 0, rv.pmf(x), colors='k', linestyle='-', lw=1,
...          label='frozen pmf')
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Check accuracy of cdf and ppf:

```
>>> prob = binom.cdf(x, n, p)
>>> np.allclose(x, binom.ppf(prob, n, p))
True
```

Generate random numbers:

```
>>> r = binom.rvs(n, p, size=1000)
```

Methods

rvs(n, p, loc=0, size=1, random_state=None)	Random variates.
pmf(k, n, p, loc=0)	Probability mass function.
logpmf(k, n, p, loc=0)	Log of the probability mass function.
cdf(k, n, p, loc=0)	Cumulative distribution function.
logcdf(k, n, p, loc=0)	Log of the cumulative distribution function.
sf(k, n, p, loc=0)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(k, n, p, loc=0)	Log of the survival function.
ppf(q, n, p, loc=0)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, n, p, loc=0)	Inverse survival function (inverse of <i>sf</i>).
stats(n, p, loc=0, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(n, p, loc=0)	(Differential) entropy of the RV.
expect(func, args=(n, p), loc=0, lb=None, ub=None, conditional=False)	Expected value of a function (of one argument) with respect to the distribution.
median(n, p, loc=0)	Median of the distribution.
mean(n, p, loc=0)	Mean of the distribution.
var(n, p, loc=0)	Variance of the distribution.
std(n, p, loc=0)	Standard deviation of the distribution.
interval(alpha, n, p, loc=0)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.boltzmann

```
scipy.stats.boltzmann(*args, **kwargs) = <scipy.stats._discrete_distns.  
boltzmann_gen object>
```

A Boltzmann (Truncated Discrete Exponential) random variable.

As an instance of the *rv_discrete* class, *boltzmann* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability mass function for *boltzmann* is:

$$f(k) = (1 - \exp(-\lambda)) \exp(-\lambda k) / (1 - \exp(-\lambda N))$$

for $k = 0, \dots, N - 1$.

boltzmann takes $\lambda > 0$ and $N > 0$ as shape parameters.

The probability mass function above is defined in the “standardized” form. To shift distribution use the *loc* parameter. Specifically, `boltzmann.pmf(k, lambda_, N, loc)` is identically equivalent to `boltzmann.pmf(k - loc, lambda_, N)`.

Examples

```
>>> from scipy.stats import boltzmann
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> lambda_, N = 1.4, 19
>>> mean, var, skew, kurt = boltzmann.stats(lambda_, N, moments='mvsk')
```


Display the probability mass function (pmf):

```
>>> x = np.arange(boltzmann.ppf(0.01, lambda_, N),
...               boltzmann.ppf(0.99, lambda_, N))
>>> ax.plot(x, boltzmann.pmf(x, lambda_, N), 'bo', ms=8, label='boltzmann_
↳pmf')
>>> ax.vlines(x, 0, boltzmann.pmf(x, lambda_, N), colors='b', lw=5,
↳alpha=0.5)
```

Alternatively, the distribution object can be called (as a function) to fix the shape and location. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pmf:

```
>>> rv = boltzmann(lambda_, N)
>>> ax.vlines(x, 0, rv.pmf(x), colors='k', linestyle='-', lw=1,
...           label='frozen pmf')
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Check accuracy of cdf and ppf:

```
>>> prob = boltzmann.cdf(x, lambda_, N)
>>> np.allclose(x, boltzmann.ppf(prob, lambda_, N))
True
```

Generate random numbers:

```
>>> r = boltzmann.rvs(lambda_, N, size=1000)
```

Methods

rvs (lambda_, N, loc=0, size=1, random_state=None)	Random variates.
pmf (k, lambda_, N, loc=0)	Probability mass function.
logpmf (k, lambda_, N, loc=0)	Log of the probability mass function.
cdf (k, lambda_, N, loc=0)	Cumulative distribution function.
logcdf (k, lambda_, N, loc=0)	Log of the cumulative distribution function.
sf (k, lambda_, N, loc=0)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf (k, lambda_, N, loc=0)	Log of the survival function.
ppf (q, lambda_, N, loc=0)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf (q, lambda_, N, loc=0)	Inverse survival function (inverse of <i>sf</i>).
stats (lambda_, N, loc=0, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy (lambda_, N, loc=0)	(Differential) entropy of the RV.
expect (func, args=(lambda_, N), loc=0, lb=None, ub=None, conditional=False)	Expected value of a function (of one argument) with respect to the distribution.
median (lambda_, N, loc=0)	Median of the distribution.
mean (lambda_, N, loc=0)	Mean of the distribution.
var (lambda_, N, loc=0)	Variance of the distribution.
std (lambda_, N, loc=0)	Standard deviation of the distribution.
interval (alpha, lambda_, N, loc=0)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.dlaplace

```
scipy.stats.dlaplace(*args, **kwargs) = <scipy.stats._discrete_distns.
    dlaplace_gen object>
```

A Laplacian discrete random variable.

As an instance of the *rv_discrete* class, *dlaplace* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability mass function for *dlaplace* is:

$$f(k) = \tanh(a/2) \exp(-a|k|)$$

for integers k and $a > 0$.

dlaplace takes a as shape parameter.

The probability mass function above is defined in the “standardized” form. To shift distribution use the `loc` parameter. Specifically, `dlaplace.pmf(k, a, loc)` is identically equivalent to `dlaplace.pmf(k - loc, a)`.

Examples

```
>>> from scipy.stats import dlaplace
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a = 0.8
>>> mean, var, skew, kurt = dlaplace.stats(a, moments='mvsk')
```

Display the probability mass function (pmf):


```
>>> x = np.arange(dlaplace.ppf(0.01, a),
...               dlaplace.ppf(0.99, a))
>>> ax.plot(x, dlaplace.pmf(x, a), 'bo', ms=8, label='dlaplace pmf')
>>> ax.vlines(x, 0, dlaplace.pmf(x, a), colors='b', lw=5, alpha=0.5)
```

Alternatively, the distribution object can be called (as a function) to fix the shape and location. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pmf:

```
>>> rv = dlaplace(a)
>>> ax.vlines(x, 0, rv.pmf(x), colors='k', linestyle='-', lw=1,
...          label='frozen pmf')
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```

Check accuracy of cdf and ppf:



```
>>> prob = dlaplace.cdf(x, a)
>>> np.allclose(x, dlaplace.ppf(prob, a))
True
```

Generate random numbers:

```
>>> r = dlaplace.rvs(a, size=1000)
```

Methods

<code>rvs(a, loc=0, size=1, random_state=None)</code>	Random variates.
<code>pmf(k, a, loc=0)</code>	Probability mass function.
<code>logpmf(k, a, loc=0)</code>	Log of the probability mass function.
<code>cdf(k, a, loc=0)</code>	Cumulative distribution function.
<code>logcdf(k, a, loc=0)</code>	Log of the cumulative distribution function.
<code>sf(k, a, loc=0)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(k, a, loc=0)</code>	Log of the survival function.
<code>ppf(q, a, loc=0)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, a, loc=0)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>stats(a, loc=0, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, loc=0)</code>	(Differential) entropy of the RV.
<code>expect(func, args=(a,), loc=0, lb=None, ub=None, conditional=False)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, loc=0)</code>	Median of the distribution.
<code>mean(a, loc=0)</code>	Mean of the distribution.
<code>var(a, loc=0)</code>	Variance of the distribution.
<code>std(a, loc=0)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, loc=0)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.geom

```
scipy.stats.geom(*args, **kwargs) = <scipy.stats._discrete_distns.geom_gen object>
```

A geometric discrete random variable.

As an instance of the *rv_discrete* class, *geom* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

planck

Notes

The probability mass function for *geom* is:

$$f(k) = (1 - p)^{k-1}p$$

for $k \geq 1, 0 < p \leq 1$

geom takes p as shape parameter, where p is the probability of a single success and $1 - p$ is the probability of a single failure.

The probability mass function above is defined in the “standardized” form. To shift distribution use the *loc* parameter. Specifically, `geom.pmf(k, p, loc)` is identically equivalent to `geom.pmf(k - loc, p)`.

Examples

```
>>> from scipy.stats import geom
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> p = 0.5
>>> mean, var, skew, kurt = geom.stats(p, moments='mvsk')
```


Display the probability mass function (pmf):

```
>>> x = np.arange(geom.ppf(0.01, p),
...               geom.ppf(0.99, p))
>>> ax.plot(x, geom.pmf(x, p), 'bo', ms=8, label='geom pmf')
>>> ax.vlines(x, 0, geom.pmf(x, p), colors='b', lw=5, alpha=0.5)
```

Alternatively, the distribution object can be called (as a function) to fix the shape and location. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pmf:

```
>>> rv = geom(p)
>>> ax.vlines(x, 0, rv.pmf(x), colors='k', linestyle='-', lw=1,
...          label='frozen pmf')
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Check accuracy of cdf and ppf:

```
>>> prob = geom.cdf(x, p)
>>> np.allclose(x, geom.ppf(prob, p))
True
```

Generate random numbers:

```
>>> r = geom.rvs(p, size=1000)
```

Methods

<code>rvs(p, loc=0, size=1, random_state=None)</code>	Random variates.
<code>pmf(k, p, loc=0)</code>	Probability mass function.
<code>logpmf(k, p, loc=0)</code>	Log of the probability mass function.
<code>cdf(k, p, loc=0)</code>	Cumulative distribution function.
<code>logcdf(k, p, loc=0)</code>	Log of the cumulative distribution function.
<code>sf(k, p, loc=0)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(k, p, loc=0)</code>	Log of the survival function.
<code>ppf(q, p, loc=0)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, p, loc=0)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>stats(p, loc=0, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(p, loc=0)</code>	(Differential) entropy of the RV.
<code>expect(func, args=(p,), loc=0, lb=None, ub=None, conditional=False)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(p, loc=0)</code>	Median of the distribution.
<code>mean(p, loc=0)</code>	Mean of the distribution.
<code>var(p, loc=0)</code>	Variance of the distribution.
<code>std(p, loc=0)</code>	Standard deviation of the distribution.
<code>interval(alpha, p, loc=0)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.hypergeom

`scipy.stats.hypergeom(*args, **kwargs)` = `<scipy.stats._discrete_distns.hypergeom_gen object>`

A hypergeometric discrete random variable.

The hypergeometric distribution models drawing objects from a bin. M is the total number of objects, n is total number of Type I objects. The random variate represents the number of Type I objects in N drawn without replacement from the total population.

As an instance of the `rv_discrete` class, `hypergeom` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

`nhypergeom`, `binom`, `nbinom`

Notes

The symbols used to denote the shape parameters (M , n , and N) are not universally accepted. See the Examples for a clarification of the definitions used here.

The probability mass function is defined as,

$$p(k, M, n, N) = \frac{\binom{n}{k} \binom{M-n}{N-k}}{\binom{M}{N}}$$

for $k \in [\max(0, N - M + n), \min(n, N)]$, where the binomial coefficients are defined as,

$$\binom{n}{k} \equiv \frac{n!}{k!(n-k)!}$$

The probability mass function above is defined in the “standardized” form. To shift distribution use the `loc` parameter. Specifically, `hypergeom.pmf(k, M, n, N, loc)` is identically equivalent to `hypergeom.pmf(k - loc, M, n, N)`.

Examples

```
>>> from scipy.stats import hypergeom
>>> import matplotlib.pyplot as plt
```

Suppose we have a collection of 20 animals, of which 7 are dogs. Then if we want to know the probability of finding a given number of dogs if we choose at random 12 of the 20 animals, we can initialize a frozen distribution and plot the probability mass function:


```
>>> [M, n, N] = [20, 7, 12]
>>> rv = hypergeom(M, n, N)
>>> x = np.arange(0, n+1)
>>> pmf_dogs = rv.pmf(x)
```

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> ax.plot(x, pmf_dogs, 'bo')
>>> ax.vlines(x, 0, pmf_dogs, lw=2)
```

(continues on next page)

(continued from previous page)

```
>>> ax.set_xlabel('# of dogs in our group of chosen animals')
>>> ax.set_ylabel('hypergeom PMF')
>>> plt.show()
```



Instead of using a frozen distribution we can also use *hypergeom* methods directly. To for example obtain the cumulative distribution function, use:

```
>>> prb = hypergeom.cdf(x, M, n, N)
```

And to generate random numbers:

```
>>> R = hypergeom.rvs(M, n, N, size=10)
```


Methods

<code>rvs(M, n, N, loc=0, size=1, random_state=None)</code>	Random variates.
<code>pmf(k, M, n, N, loc=0)</code>	Probability mass function.
<code>logpmf(k, M, n, N, loc=0)</code>	Log of the probability mass function.
<code>cdf(k, M, n, N, loc=0)</code>	Cumulative distribution function.
<code>logcdf(k, M, n, N, loc=0)</code>	Log of the cumulative distribution function.
<code>sf(k, M, n, N, loc=0)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(k, M, n, N, loc=0)</code>	Log of the survival function.
<code>ppf(q, M, n, N, loc=0)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, M, n, N, loc=0)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>stats(M, n, N, loc=0, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(M, n, N, loc=0)</code>	(Differential) entropy of the RV.
<code>expect(func, args=(M, n, N), loc=0, lb=None, ub=None, conditional=False)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(M, n, N, loc=0)</code>	Median of the distribution.
<code>mean(M, n, N, loc=0)</code>	Mean of the distribution.
<code>var(M, n, N, loc=0)</code>	Variance of the distribution.
<code>std(M, n, N, loc=0)</code>	Standard deviation of the distribution.
<code>interval(alpha, M, n, N, loc=0)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.logser

`scipy.stats.logser(*args, **kwargs) = <scipy.stats._discrete_distns.logser_gen object>`

A Logarithmic (Log-Series, Series) discrete random variable.

As an instance of the *rv_discrete* class, *logser* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability mass function for *logser* is:

$$f(k) = -\frac{p^k}{k \log(1-p)}$$

for $k \geq 1, 0 < p < 1$

logser takes *p* as shape parameter, where *p* is the probability of a single success and $1 - p$ is the probability of a single failure.

The probability mass function above is defined in the “standardized” form. To shift distribution use the *loc* parameter. Specifically, `logser.pmf(k, p, loc)` is identically equivalent to `logser.pmf(k - loc, p)`.

Examples

```
>>> from scipy.stats import logser
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> p = 0.6
>>> mean, var, skew, kurt = logser.stats(p, moments='mvsk')
```


Display the probability mass function (pmf):

```
>>> x = np.arange(logser.ppf(0.01, p),
...               logser.ppf(0.99, p))
>>> ax.plot(x, logser.pmf(x, p), 'bo', ms=8, label='logser pmf')
>>> ax.vlines(x, 0, logser.pmf(x, p), colors='b', lw=5, alpha=0.5)
```

Alternatively, the distribution object can be called (as a function) to fix the shape and location. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pmf:

```
>>> rv = logser(p)
>>> ax.vlines(x, 0, rv.pmf(x), colors='k', linestyle='-', lw=1,
...          label='frozen pmf')
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Check accuracy of cdf and ppf:

```
>>> prob = logser.cdf(x, p)
>>> np.allclose(x, logser.ppf(prob, p))
True
```

Generate random numbers:

```
>>> r = logser.rvs(p, size=1000)
```

Methods

<code>rvs(p, loc=0, size=1, random_state=None)</code>	Random variates.
<code>pmf(k, p, loc=0)</code>	Probability mass function.
<code>logpmf(k, p, loc=0)</code>	Log of the probability mass function.
<code>cdf(k, p, loc=0)</code>	Cumulative distribution function.
<code>logcdf(k, p, loc=0)</code>	Log of the cumulative distribution function.
<code>sf(k, p, loc=0)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(k, p, loc=0)</code>	Log of the survival function.
<code>ppf(q, p, loc=0)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, p, loc=0)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>stats(p, loc=0, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(p, loc=0)</code>	(Differential) entropy of the RV.
<code>expect(func, args=(p,), loc=0, lb=None, ub=None, conditional=False)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(p, loc=0)</code>	Median of the distribution.
<code>mean(p, loc=0)</code>	Mean of the distribution.
<code>var(p, loc=0)</code>	Variance of the distribution.
<code>std(p, loc=0)</code>	Standard deviation of the distribution.
<code>interval(alpha, p, loc=0)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.nbinom

```
scipy.stats.nbinom(*args, **kwargs) = <scipy.stats._discrete_distns.nbinom_gen
object>
```

A negative binomial discrete random variable.

As an instance of the *rv_discrete* class, *nbinom* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

[hypergeom](#), [binom](#), [nhypergeom](#)

Notes

Negative binomial distribution describes a sequence of i.i.d. Bernoulli trials, repeated until a predefined, non-random number of successes occurs.

The probability mass function of the number of failures for *nbinom* is:

$$f(k) = \binom{k+n-1}{n-1} p^n (1-p)^k$$

for $k \geq 0, 0 < p \leq 1$

nbinom takes *n* and *p* as shape parameters where *n* is the number of successes, *p* is the probability of a single success, and $1 - p$ is the probability of a single failure.

The probability mass function above is defined in the “standardized” form. To shift distribution use the `loc` parameter. Specifically, `nbinom.pmf(k, n, p, loc)` is identically equivalent to `nbinom.pmf(k - loc, n, p)`.

Examples

```
>>> from scipy.stats import nbinom
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> n, p = 0.4, 0.4
>>> mean, var, skew, kurt = nbinom.stats(n, p, moments='mvsk')
```


Display the probability mass function (pmf):

```
>>> x = np.arange(nbinom.ppf(0.01, n, p),
...               nbinom.ppf(0.99, n, p))
>>> ax.plot(x, nbinom.pmf(x, n, p), 'bo', ms=8, label='nbinom pmf')
>>> ax.vlines(x, 0, nbinom.pmf(x, n, p), colors='b', lw=5, alpha=0.5)
```

Alternatively, the distribution object can be called (as a function) to fix the shape and location. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pmf:

```
>>> rv = nbinom(n, p)
>>> ax.vlines(x, 0, rv.pmf(x), colors='k', linestyle='-', lw=1,
...          label='frozen pmf')
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Check accuracy of cdf and ppf:

```
>>> prob = nbinom.cdf(x, n, p)
>>> np.allclose(x, nbinom.ppf(prob, n, p))
True
```

Generate random numbers:

```
>>> r = nbinom.rvs(n, p, size=1000)
```

Methods

<code>rvs(n, p, loc=0, size=1, random_state=None)</code>	Random variates.
<code>pmf(k, n, p, loc=0)</code>	Probability mass function.
<code>logpmf(k, n, p, loc=0)</code>	Log of the probability mass function.
<code>cdf(k, n, p, loc=0)</code>	Cumulative distribution function.
<code>logcdf(k, n, p, loc=0)</code>	Log of the cumulative distribution function.
<code>sf(k, n, p, loc=0)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(k, n, p, loc=0)</code>	Log of the survival function.
<code>ppf(q, n, p, loc=0)</code>	Percent point function (inverse of <code>cdf</code> — percentiles).
<code>isf(q, n, p, loc=0)</code>	Inverse survival function (inverse of <code>sf</code>).
<code>stats(n, p, loc=0, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(n, p, loc=0)</code>	(Differential) entropy of the RV.
<code>expect(func, args=(n, p), loc=0, lb=None, ub=None, conditional=False)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(n, p, loc=0)</code>	Median of the distribution.
<code>mean(n, p, loc=0)</code>	Mean of the distribution.
<code>var(n, p, loc=0)</code>	Variance of the distribution.
<code>std(n, p, loc=0)</code>	Standard deviation of the distribution.
<code>interval(alpha, n, p, loc=0)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.nhypergeom

```
scipy.stats.nhypergeom(*args, **kwargs) = <scipy.stats._discrete_distns.
nhypergeom_gen object>
```

A negative hypergeometric discrete random variable.

Consider a box containing M balls: n red and $M - n$ blue. We randomly sample balls from the box, one at a time and *without* replacement, until we have picked r blue balls. *nhypergeom* is the distribution of the number of red balls k we have picked.

As an instance of the *rv_discrete* class, *nhypergeom* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

hypergeom, *binom*, *nbinom*

Notes

The symbols used to denote the shape parameters (M , n , and r) are not universally accepted. See the Examples for a clarification of the definitions used here.

The probability mass function is defined as,

$$f(k; M, n, r) = \frac{\binom{k+r-1}{k} \binom{M-r-k}{n-k}}{\binom{M}{n}}$$

for $k \in [0, n]$, $n \in [0, M]$, $r \in [0, M - n]$, and the binomial coefficient is:

$$\binom{n}{k} \equiv \frac{n!}{k!(n-k)!}.$$

It is equivalent to observing k successes in $k + r - 1$ samples with $k + r$ 'th sample being a failure. The former can be modelled as a hypergeometric distribution. The probability of the latter is simply the number of failures remaining $M - n - (r - 1)$ divided by the size of the remaining population $M - (k + r - 1)$. This relationship can be shown as:

$$NHG(k; M, n, r) = HG(k; M, n, k + r - 1) \frac{(M - n - (r - 1))}{(M - (k + r - 1))}$$

where NHG is probability mass function (PMF) of the negative hypergeometric distribution and HG is the PMF of the hypergeometric distribution.

The probability mass function above is defined in the “standardized” form. To shift distribution use the `loc` parameter. Specifically, `nhypergeom.pmf(k, M, n, r, loc)` is identically equivalent to `nhypergeom.pmf(k - loc, M, n, r)`.

References

[1], [2]


Examples

```
>>> from scipy.stats import nhypergeom
>>> import matplotlib.pyplot as plt
```

Suppose we have a collection of 20 animals, of which 7 are dogs. Then if we want to know the probability of finding a given number of dogs (successes) in a sample with exactly 12 animals that aren't dogs (failures), we can initialize a frozen distribution and plot the probability mass function:

```
>>> M, n, r = [20, 7, 12]
>>> rv = nhypergeom(M, n, r)
>>> x = np.arange(0, n+2)
>>> pmf_dogs = rv.pmf(x)
```

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> ax.plot(x, pmf_dogs, 'bo')
>>> ax.vlines(x, 0, pmf_dogs, lw=2)
>>> ax.set_xlabel('# of dogs in our group with given 12 failures')
>>> ax.set_ylabel('nhypergeom PMF')
>>> plt.show()
```



Instead of using a frozen distribution we can also use `nhypergeom` methods directly. To for example obtain the probability mass function, use:

```
>>> prb = nhypergeom.pmf(x, M, n, r)
```

And to generate random numbers:

```
>>> R = nhypergeom.rvs(M, n, r, size=10)
```

To verify the relationship between `hypergeom` and `nhypergeom`, use:

```
>>> from scipy.stats import hypergeom, nhypergeom
>>> M, n, r = 45, 13, 8
>>> k = 6
>>> nhypergeom.pmf(k, M, n, r)
0.06180776620271643
>>> hypergeom.pmf(k, M, n, k+r-1) * (M - n - (r-1)) / (M - (k+r-1))
0.06180776620271644
```

Methods

<code>rvs(M, n, r, loc=0, size=1, random_state=None)</code>	Random variates.
<code>pmf(k, M, n, r, loc=0)</code>	Probability mass function.
<code>logpmf(k, M, n, r, loc=0)</code>	Log of the probability mass function.
<code>cdf(k, M, n, r, loc=0)</code>	Cumulative distribution function.
<code>logcdf(k, M, n, r, loc=0)</code>	Log of the cumulative distribution function.
<code>sf(k, M, n, r, loc=0)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(k, M, n, r, loc=0)</code>	Log of the survival function.
<code>ppf(q, M, n, r, loc=0)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, M, n, r, loc=0)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>stats(M, n, r, loc=0, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(M, n, r, loc=0)</code>	(Differential) entropy of the RV.
<code>expect(func, args=(M, n, r), loc=0, lb=None, ub=None, conditional=False)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(M, n, r, loc=0)</code>	Median of the distribution.
<code>mean(M, n, r, loc=0)</code>	Mean of the distribution.
<code>var(M, n, r, loc=0)</code>	Variance of the distribution.
<code>std(M, n, r, loc=0)</code>	Standard deviation of the distribution.
<code>interval(alpha, M, n, r, loc=0)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.planck

`scipy.stats.planck(*args, **kwargs) = <scipy.stats._discrete_distns.planck_gen object>`

A Planck discrete exponential random variable.

As an instance of the *rv_discrete* class, *planck* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

See also:

geom

Notes

The probability mass function for *planck* is:

$$f(k) = (1 - \exp(-\lambda)) \exp(-\lambda k)$$

for $k \geq 0$ and $\lambda > 0$.

planck takes λ as shape parameter. The Planck distribution can be written as a geometric distribution (*geom*) with $p = 1 - \exp(-\lambda)$ shifted by $loc = -1$.

The probability mass function above is defined in the “standardized” form. To shift distribution use the `loc` parameter. Specifically, `planck.pmf(k, lambda_, loc)` is identically equivalent to `planck.pmf(k - loc, lambda_)`.

Examples

```
>>> from scipy.stats import planck
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> lambda_ = 0.51
>>> mean, var, skew, kurt = planck.stats(lambda_, moments='mvsk')
```


Display the probability mass function (pmf):

```
>>> x = np.arange(planck.ppf(0.01, lambda_),
...               planck.ppf(0.99, lambda_))
>>> ax.plot(x, planck.pmf(x, lambda_), 'bo', ms=8, label='planck pmf')
>>> ax.vlines(x, 0, planck.pmf(x, lambda_), colors='b', lw=5, alpha=0.5)
```

Alternatively, the distribution object can be called (as a function) to fix the shape and location. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pmf:

```
>>> rv = planck(lambda_)
>>> ax.vlines(x, 0, rv.pmf(x), colors='k', linestyle='--', lw=1,
...          label='frozen pmf')
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Check accuracy of cdf and ppf:

```
>>> prob = planck.cdf(x, lambda_)
>>> np.allclose(x, planck.ppf(prob, lambda_))
True
```

Generate random numbers:

```
>>> r = planck.rvs(lambda_, size=1000)
```

Methods

<code>rvs(lambda_, loc=0, size=1, random_state=None)</code>	Random variates.
<code>pmf(k, lambda_, loc=0)</code>	Probability mass function.
<code>logpmf(k, lambda_, loc=0)</code>	Log of the probability mass function.
<code>cdf(k, lambda_, loc=0)</code>	Cumulative distribution function.
<code>logcdf(k, lambda_, loc=0)</code>	Log of the cumulative distribution function.
<code>sf(k, lambda_, loc=0)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(k, lambda_, loc=0)</code>	Log of the survival function.
<code>ppf(q, lambda_, loc=0)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, lambda_, loc=0)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>stats(lambda_, loc=0, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(lambda_, loc=0)</code>	(Differential) entropy of the RV.
<code>expect(func, args=(lambda_), loc=0, lb=None, ub=None, conditional=False)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(lambda_, loc=0)</code>	Median of the distribution.
<code>mean(lambda_, loc=0)</code>	Mean of the distribution.
<code>var(lambda_, loc=0)</code>	Variance of the distribution.
<code>std(lambda_, loc=0)</code>	Standard deviation of the distribution.
<code>interval(alpha, lambda_, loc=0)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.poisson

`scipy.stats.poisson(*args, **kwargs) = <scipy.stats._discrete_distns.poisson_gen object>`

A Poisson discrete random variable.

As an instance of the *rv_discrete* class, *poisson* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability mass function for *poisson* is:

$$f(k) = \exp(-\mu) \frac{\mu^k}{k!}$$

for $k \geq 0$.

poisson takes μ as shape parameter. When $\mu = 0$ then at quantile $k = 0$, *pmf* method returns *1.0*.

The probability mass function above is defined in the “standardized” form. To shift distribution use the *loc* parameter. Specifically, `poisson.pmf(k, mu, loc)` is identically equivalent to `poisson.pmf(k - loc, mu)`.

Examples

```
>>> from scipy.stats import poisson
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mu = 0.6
>>> mean, var, skew, kurt = poisson.stats(mu, moments='mvsk')
```


Display the probability mass function (pmf):

```
>>> x = np.arange(poisson.ppf(0.01, mu),
...               poisson.ppf(0.99, mu))
>>> ax.plot(x, poisson.pmf(x, mu), 'bo', ms=8, label='poisson pmf')
>>> ax.vlines(x, 0, poisson.pmf(x, mu), colors='b', lw=5, alpha=0.5)
```

Alternatively, the distribution object can be called (as a function) to fix the shape and location. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pmf:

```
>>> rv = poisson(mu)
>>> ax.vlines(x, 0, rv.pmf(x), colors='k', linestyle='-', lw=1,
...           label='frozen pmf')
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Check accuracy of cdf and ppf:

```
>>> prob = poisson.cdf(x, mu)
>>> np.allclose(x, poisson.ppf(prob, mu))
True
```

Generate random numbers:

```
>>> r = poisson.rvs(mu, size=1000)
```

Methods

rvs(mu, loc=0, size=1, random_state=None)	Random variates.
pmf(k, mu, loc=0)	Probability mass function.
logpmf(k, mu, loc=0)	Log of the probability mass function.
cdf(k, mu, loc=0)	Cumulative distribution function.
logcdf(k, mu, loc=0)	Log of the cumulative distribution function.
sf(k, mu, loc=0)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(k, mu, loc=0)	Log of the survival function.
ppf(q, mu, loc=0)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, mu, loc=0)	Inverse survival function (inverse of <i>sf</i>).
stats(mu, loc=0, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(mu, loc=0)	(Differential) entropy of the RV.
expect(func, args=(mu,), loc=0, lb=None, ub=None, conditional=False)	Expected value of a function (of one argument) with respect to the distribution.
median(mu, loc=0)	Median of the distribution.
mean(mu, loc=0)	Mean of the distribution.
var(mu, loc=0)	Variance of the distribution.
std(mu, loc=0)	Standard deviation of the distribution.
interval(alpha, mu, loc=0)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.randint

`scipy.stats.randint(*args, **kwargs) = <scipy.stats._discrete_distns.randint_gen object>`

A uniform discrete random variable.

As an instance of the *rv_discrete* class, *randint* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability mass function for *randint* is:

$$f(k) = \frac{1}{\text{high} - \text{low}}$$

for $k = \text{low}, \dots, \text{high} - 1$.

randint takes *low* and *high* as shape parameters.

The probability mass function above is defined in the “standardized” form. To shift distribution use the *loc* parameter. Specifically, `randint.pmf(k, low, high, loc)` is identically equivalent to `randint.pmf(k - loc, low, high)`.

Examples

```
>>> from scipy.stats import randint
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> low, high = 7, 31
>>> mean, var, skew, kurt = randint.stats(low, high, moments='mvsk')
```


Display the probability mass function (pmf):

```
>>> x = np.arange(randint.ppf(0.01, low, high),
...               randint.ppf(0.99, low, high))
>>> ax.plot(x, randint.pmf(x, low, high), 'bo', ms=8, label='randint pmf')
>>> ax.vlines(x, 0, randint.pmf(x, low, high), colors='b', lw=5, alpha=0.
→5)
```

Alternatively, the distribution object can be called (as a function) to fix the shape and location. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pmf:

```
>>> rv = randint(low, high)
>>> ax.vlines(x, 0, rv.pmf(x), colors='k', linestyle='-', lw=1,
...          label='frozen pmf')
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Check accuracy of cdf and ppf:

```
>>> prob = randint.cdf(x, low, high)
>>> np.allclose(x, randint.ppf(prob, low, high))
True
```

Generate random numbers:

```
>>> r = randint.rvs(low, high, size=1000)
```

Methods

<code>rvs(low, high, loc=0, size=1, random_state=None)</code>	Random variates.
<code>pmf(k, low, high, loc=0)</code>	Probability mass function.
<code>logpmf(k, low, high, loc=0)</code>	Log of the probability mass function.
<code>cdf(k, low, high, loc=0)</code>	Cumulative distribution function.
<code>logcdf(k, low, high, loc=0)</code>	Log of the cumulative distribution function.
<code>sf(k, low, high, loc=0)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(k, low, high, loc=0)</code>	Log of the survival function.
<code>ppf(q, low, high, loc=0)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, low, high, loc=0)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>stats(low, high, loc=0, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(low, high, loc=0)</code>	(Differential) entropy of the RV.
<code>expect(func, args=(low, high), loc=0, lb=None, ub=None, conditional=False)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(low, high, loc=0)</code>	Median of the distribution.
<code>mean(low, high, loc=0)</code>	Mean of the distribution.
<code>var(low, high, loc=0)</code>	Variance of the distribution.
<code>std(low, high, loc=0)</code>	Standard deviation of the distribution.
<code>interval(alpha, low, high, loc=0)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.skellam

`scipy.stats.skellam(*args, **kwargs) = <scipy.stats._discrete_distns.skellam_gen object>`

A Skellam discrete random variable.

As an instance of the *rv_discrete* class, *skellam* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

Probability distribution of the difference of two correlated or uncorrelated Poisson random variables.

Let k_1 and k_2 be two Poisson-distributed r.v. with expected values λ_1 and λ_2 . Then, $k_1 - k_2$ follows a Skellam distribution with parameters $\mu_1 = \lambda_1 - \rho\sqrt{\lambda_1\lambda_2}$ and $\mu_2 = \lambda_2 - \rho\sqrt{\lambda_1\lambda_2}$, where ρ is the correlation coefficient between k_1 and k_2 . If the two Poisson-distributed r.v. are independent then $\rho = 0$.

Parameters μ_1 and μ_2 must be strictly positive.

For details see: https://en.wikipedia.org/wiki/Skellam_distribution

skellam takes μ_1 and μ_2 as shape parameters.

The probability mass function above is defined in the “standardized” form. To shift distribution use the `loc` parameter. Specifically, `skellam.pmf(k, mu1, mu2, loc)` is identically equivalent to `skellam.pmf(k - loc, mu1, mu2)`.

Examples

```
>>> from scipy.stats import skellam
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> mu1, mu2 = 15, 8
>>> mean, var, skew, kurt = skellam.stats(mu1, mu2, moments='mvsk')
```


Display the probability mass function (pmf):

```
>>> x = np.arange(skellam.ppf(0.01, mu1, mu2),
...               skellam.ppf(0.99, mu1, mu2))
>>> ax.plot(x, skellam.pmf(x, mu1, mu2), 'bo', ms=8, label='skellam pmf')
>>> ax.vlines(x, 0, skellam.pmf(x, mu1, mu2), colors='b', lw=5, alpha=0.5)
```

Alternatively, the distribution object can be called (as a function) to fix the shape and location. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pmf:

```
>>> rv = skellam(mu1, mu2)
>>> ax.vlines(x, 0, rv.pmf(x), colors='k', linestyle='-', lw=1,
...          label='frozen pmf')
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Check accuracy of cdf and ppf:

```
>>> prob = skellam.cdf(x, mu1, mu2)
>>> np.allclose(x, skellam.ppf(prob, mu1, mu2))
True
```

Generate random numbers:

```
>>> r = skellam.rvs(mu1, mu2, size=1000)
```

Methods

rvs(mu1, mu2, loc=0, size=1, random_state=None)	Random variates.
pmf(k, mu1, mu2, loc=0)	Probability mass function.
logpmf(k, mu1, mu2, loc=0)	Log of the probability mass function.
cdf(k, mu1, mu2, loc=0)	Cumulative distribution function.
logcdf(k, mu1, mu2, loc=0)	Log of the cumulative distribution function.
sf(k, mu1, mu2, loc=0)	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
logsf(k, mu1, mu2, loc=0)	Log of the survival function.
ppf(q, mu1, mu2, loc=0)	Percent point function (inverse of <i>cdf</i> — percentiles).
isf(q, mu1, mu2, loc=0)	Inverse survival function (inverse of <i>sf</i>).
stats(mu1, mu2, loc=0, moments='mv')	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
entropy(mu1, mu2, loc=0)	(Differential) entropy of the RV.
expect(func, args=(mu1, mu2), loc=0, lb=None, ub=None, conditional=False)	Expected value of a function (of one argument) with respect to the distribution.
median(mu1, mu2, loc=0)	Median of the distribution.
mean(mu1, mu2, loc=0)	Mean of the distribution.
var(mu1, mu2, loc=0)	Variance of the distribution.
std(mu1, mu2, loc=0)	Standard deviation of the distribution.
interval(alpha, mu1, mu2, loc=0)	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.zipf

`scipy.stats.zipf(*args, **kws)` = `<scipy.stats._discrete_distns.zipf_gen object>`
 A Zipf discrete random variable.

As an instance of the `rv_discrete` class, `zipf` object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability mass function for `zipf` is:

$$f(k, a) = \frac{1}{\zeta(a)k^a}$$

for $k \geq 1$.

`zipf` takes a as shape parameter. ζ is the Riemann zeta function (`scipy.special.zeta`)

The probability mass function above is defined in the “standardized” form. To shift distribution use the `loc` parameter. Specifically, `zipf.pmf(k, a, loc)` is identically equivalent to `zipf.pmf(k - loc, a)`.

Examples

```
>>> from scipy.stats import zipf
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> a = 6.5
>>> mean, var, skew, kurt = zipf.stats(a, moments='mvsk')
```

Display the probability mass function (pmf):


```
>>> x = np.arange(zipf.ppf(0.01, a),
...               zipf.ppf(0.99, a))
>>> ax.plot(x, zipf.pmf(x, a), 'bo', ms=8, label='zipf pmf')
>>> ax.vlines(x, 0, zipf.pmf(x, a), colors='b', lw=5, alpha=0.5)
```

Alternatively, the distribution object can be called (as a function) to fix the shape and location. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pmf:

```
>>> rv = zipf(a)
>>> ax.vlines(x, 0, rv.pmf(x), colors='k', linestyle='-', lw=1,
...          label='frozen pmf')
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```

Check accuracy of cdf and ppf:



```
>>> prob = zipf.cdf(x, a)
>>> np.allclose(x, zipf.ppf(prob, a))
True
```

Generate random numbers:

```
>>> r = zipf.rvs(a, size=1000)
```

Methods

<code>rvs(a, loc=0, size=1, random_state=None)</code>	Random variates.
<code>pmf(k, a, loc=0)</code>	Probability mass function.
<code>logpmf(k, a, loc=0)</code>	Log of the probability mass function.
<code>cdf(k, a, loc=0)</code>	Cumulative distribution function.
<code>logcdf(k, a, loc=0)</code>	Log of the cumulative distribution function.
<code>sf(k, a, loc=0)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(k, a, loc=0)</code>	Log of the survival function.
<code>ppf(q, a, loc=0)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, a, loc=0)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>stats(a, loc=0, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(a, loc=0)</code>	(Differential) entropy of the RV.
<code>expect(func, args=(a,), loc=0, lb=None, ub=None, conditional=False)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(a, loc=0)</code>	Median of the distribution.
<code>mean(a, loc=0)</code>	Mean of the distribution.
<code>var(a, loc=0)</code>	Variance of the distribution.
<code>std(a, loc=0)</code>	Standard deviation of the distribution.
<code>interval(alpha, a, loc=0)</code>	Endpoints of the range that contains alpha percent of the distribution

scipy.stats.yulesimon

```
scipy.stats.yulesimon(*args, **kwargs) = <scipy.stats._discrete_distns.
    yulesimon_gen object>
```

A Yule-Simon discrete random variable.

As an instance of the *rv_discrete* class, *yulesimon* object inherits from it a collection of generic methods (see below for the full list), and completes them with details specific for this particular distribution.

Notes

The probability mass function for the *yulesimon* is:

$$f(k) = \alpha B(k, \alpha + 1)$$

for $k = 1, 2, 3, \dots$, where $\alpha > 0$. Here B refers to the *scipy.special.beta* function.

The sampling of random variates is based on pg 553, Section 6.3 of [1]. Our notation maps to the referenced logic via $\alpha = a - 1$.

For details see the wikipedia entry [2].

References

The probability mass function above is defined in the “standardized” form. To shift distribution use the *loc* parameter. Specifically, *yulesimon.pmf(k, alpha, loc)* is identically equivalent to *yulesimon.pmf(k - loc, alpha)*.

[1], [2]

Examples

```
>>> from scipy.stats import yulesimon
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots(1, 1)
```

Calculate a few first moments:

```
>>> alpha = 11
>>> mean, var, skew, kurt = yulesimon.stats(alpha, moments='mvsk')
```


Display the probability mass function (pmf):

```
>>> x = np.arange(yulesimon.ppf(0.01, alpha),
...               yulesimon.ppf(0.99, alpha))
>>> ax.plot(x, yulesimon.pmf(x, alpha), 'bo', ms=8, label='yulesimon pmf')
>>> ax.vlines(x, 0, yulesimon.pmf(x, alpha), colors='b', lw=5, alpha=0.5)
```

Alternatively, the distribution object can be called (as a function) to fix the shape and location. This returns a “frozen” RV object holding the given parameters fixed.

Freeze the distribution and display the frozen pmf:

```
>>> rv = yulesimon(alpha)
>>> ax.vlines(x, 0, rv.pmf(x), colors='k', linestyle='-', lw=1,
...          label='frozen pmf')
>>> ax.legend(loc='best', frameon=False)
>>> plt.show()
```



Check accuracy of cdf and ppf:

```
>>> prob = yulesimon.cdf(x, alpha)
>>> np.allclose(x, yulesimon.ppf(prob, alpha))
True
```

Generate random numbers:

```
>>> r = yulesimon.rvs(alpha, size=1000)
```

Methods

<code>rvs(alpha, loc=0, size=1, random_state=None)</code>	Random variates.
<code>pmf(k, alpha, loc=0)</code>	Probability mass function.
<code>logpmf(k, alpha, loc=0)</code>	Log of the probability mass function.
<code>cdf(k, alpha, loc=0)</code>	Cumulative distribution function.
<code>logcdf(k, alpha, loc=0)</code>	Log of the cumulative distribution function.
<code>sf(k, alpha, loc=0)</code>	Survival function (also defined as $1 - \text{cdf}$, but <i>sf</i> is sometimes more accurate).
<code>logsf(k, alpha, loc=0)</code>	Log of the survival function.
<code>ppf(q, alpha, loc=0)</code>	Percent point function (inverse of <i>cdf</i> — percentiles).
<code>isf(q, alpha, loc=0)</code>	Inverse survival function (inverse of <i>sf</i>).
<code>stats(alpha, loc=0, moments='mv')</code>	Mean('m'), variance('v'), skew('s'), and/or kurtosis('k').
<code>entropy(alpha, loc=0)</code>	(Differential) entropy of the RV.
<code>expect(func, args=(alpha,), loc=0, lb=None, ub=None, conditional=False)</code>	Expected value of a function (of one argument) with respect to the distribution.
<code>median(alpha, loc=0)</code>	Median of the distribution.
<code>mean(alpha, loc=0)</code>	Mean of the distribution.
<code>var(alpha, loc=0)</code>	Variance of the distribution.
<code>std(alpha, loc=0)</code>	Standard deviation of the distribution.
<code>interval(alpha, alpha, loc=0)</code>	Endpoints of the range that contains alpha percent of the distribution

An overview of statistical functions is given below. Several of these functions have a similar version in `scipy.stats.mstats` which work for masked arrays.

6.29.7 Summary statistics

<code>describe(a[, axis, ddof, bias, nan_policy])</code>	Compute several descriptive statistics of the passed array.
<code>gmean(a[, axis, dtype])</code>	Compute the geometric mean along the specified axis.
<code>hmean(a[, axis, dtype])</code>	Calculate the harmonic mean along the specified axis.
<code>kurtosis(a[, axis, fisher, bias, nan_policy])</code>	Compute the kurtosis (Fisher or Pearson) of a dataset.
<code>mode(a[, axis, nan_policy])</code>	Return an array of the modal (most common) value in the passed array.
<code>moment(a[, moment, axis, nan_policy])</code>	Calculate the nth moment about the mean for a sample.
<code>skew(a[, axis, bias, nan_policy])</code>	Compute the sample skewness of a data set.
<code>kstat(data[, n])</code>	Return the nth k-statistic ($1 \leq n \leq 4$ so far).
<code>kstatvar(data[, n])</code>	Return an unbiased estimator of the variance of the k-statistic.
<code>tmean(a[, limits, inclusive, axis])</code>	Compute the trimmed mean.
<code>tvar(a[, limits, inclusive, axis, ddof])</code>	Compute the trimmed variance.
<code>tmin(a[, lowerlimit, axis, inclusive, ...])</code>	Compute the trimmed minimum.
<code>tmax(a[, upperlimit, axis, inclusive, ...])</code>	Compute the trimmed maximum.
<code>tstd(a[, limits, inclusive, axis, ddof])</code>	Compute the trimmed sample standard deviation.
<code>tsem(a[, limits, inclusive, axis, ddof])</code>	Compute the trimmed standard error of the mean.
<code>variation(a[, axis, nan_policy])</code>	Compute the coefficient of variation.
<code>find_repeats(arr)</code>	Find repeats and repeat counts.

continues on next page

Table 261 – continued from previous page

<code>trim_mean(a, proportiontocut[, axis])</code>	Return mean of array after trimming distribution from both tails.
<code>gstd(a[, axis, ddof])</code>	Calculate the geometric standard deviation of an array.
<code>iqr(x[, axis, rng, scale, nan_policy, ...])</code>	Compute the interquartile range of the data along the specified axis.
<code>sem(a[, axis, ddof, nan_policy])</code>	Compute standard error of the mean.
<code>bayes_mvs(data[, alpha])</code>	Bayesian confidence intervals for the mean, var, and std.
<code>mvstdist(data)</code>	'Frozen' distributions for mean, variance, and standard deviation of data.
<code>entropy(pk[, qk, base, axis])</code>	Calculate the entropy of a distribution for given probability values.
<code>median_absolute_deviation(*args, **kwargs)</code>	<code>median_absolute_deviation</code> is deprecated, use <code>median_abs_deviation</code> instead!
<code>median_abs_deviation(x[, axis, center, ...])</code>	Compute the median absolute deviation of the data along the given axis.

scipy.stats.describe

`scipy.stats.describe(a, axis=0, ddof=1, bias=True, nan_policy='propagate')`

Compute several descriptive statistics of the passed array.

Parameters

- a** [array_like] Input data.
- axis** [int or None, optional] Axis along which statistics are calculated. Default is 0. If None, compute over the whole array *a*.
- ddof** [int, optional] Delta degrees of freedom (only for variance). Default is 1.
- bias** [bool, optional] If False, then the skewness and kurtosis calculations are corrected for statistical bias.
- nan_policy** [{"propagate", "raise", "omit"}, optional] Defines how to handle when input contains nan. The following options are available (default is 'propagate'):
 - 'propagate': returns nan
 - 'raise': throws an error
 - 'omit': performs the calculations ignoring nan values

Returns

- nobs** [int or ndarray of ints] Number of observations (length of data along *axis*). When 'omit' is chosen as *nan_policy*, each column is counted separately.
- minmax: tuple of ndarrays or floats** Minimum and maximum value of data array.
- mean** [ndarray or float] Arithmetic mean of data along axis.
- variance** [ndarray or float] Unbiased variance of the data along axis, denominator is number of observations minus one.
- skewness** [ndarray or float] Skewness, based on moment calculations with denominator equal to the number of observations, i.e. no degrees of freedom correction.
- kurtosis** [ndarray or float] Kurtosis (Fisher). The kurtosis is normalized so that it is zero for the normal distribution. No degrees of freedom are used.

See also:

`skew, kurtosis`

Examples

```

>>> from scipy import stats
>>> a = np.arange(10)
>>> stats.describe(a)
DescribeResult(nobs=10, minmax=(0, 9), mean=4.5, variance=9.
→166666666666666666,
                skewness=0.0, kurtosis=-1.2242424242424244)
>>> b = [[1, 2], [3, 4]]
>>> stats.describe(b)
DescribeResult(nobs=2, minmax=(array([1, 2]), array([3, 4])),
                mean=array([2., 3.]), variance=array([2., 2.]),
                skewness=array([0., 0.]), kurtosis=array([-2., -2.]))

```

scipy.stats.gmean

`scipy.stats.gmean(a, axis=0, dtype=None)`

Compute the geometric mean along the specified axis.

Return the geometric average of the array elements. That is: n -th root of $(x_1 * x_2 * \dots * x_n)$

Parameters

- a** [array_like] Input array or object that can be converted to an array.
- axis** [int or None, optional] Axis along which the geometric mean is computed. Default is 0. If None, compute over the whole array *a*.
- dtype** [dtype, optional] Type of the returned array and of the accumulator in which the elements are summed. If dtype is not specified, it defaults to the dtype of *a*, unless *a* has an integer dtype with a precision less than that of the default platform integer. In that case, the default platform integer is used.

Returns

- gmean** [ndarray] See *dtype* parameter above.

See also:

[*numpy.mean*](#)

Arithmetic average

[*numpy.average*](#)

Weighted average

[*hmean*](#)

Harmonic mean

Notes

The geometric average is computed over a single dimension of the input array, `axis=0` by default, or all values in the array if `axis=None`. `float64` intermediate and return values are used for integer inputs.

Use masked arrays to ignore any non-finite values in the input or that arise in the calculations such as Not a Number and infinity because masked arrays automatically mask any non-finite values.

Examples

```
>>> from scipy.stats import gmean
>>> gmean([1, 4])
2.0
>>> gmean([1, 2, 3, 4, 5, 6, 7])
3.3800151591412964
```

`scipy.stats.hmean`

`scipy.stats.hmean(a, axis=0, dtype=None)`

Calculate the harmonic mean along the specified axis.

That is: $n / (1/x_1 + 1/x_2 + \dots + 1/x_n)$

Parameters

- a** [array_like] Input array, masked array or object that can be converted to an array.
- axis** [int or None, optional] Axis along which the harmonic mean is computed. Default is 0. If None, compute over the whole array *a*.
- dtype** [dtype, optional] Type of the returned array and of the accumulator in which the elements are summed. If *dtype* is not specified, it defaults to the dtype of *a*, unless *a* has an integer *dtype* with a precision less than that of the default platform integer. In that case, the default platform integer is used.

Returns

- hmean** [ndarray] See *dtype* parameter above.

See also:

`numpy.mean`

Arithmetic average

`numpy.average`

Weighted average

`gmean`

Geometric mean

Notes

The harmonic mean is computed over a single dimension of the input array, `axis=0` by default, or all values in the array if `axis=None`. float64 intermediate and return values are used for integer inputs.

Use masked arrays to ignore any non-finite values in the input or that arise in the calculations such as Not a Number and infinity.

Examples

```
>>> from scipy.stats import hmean
>>> hmean([1, 4])
1.6000000000000001
>>> hmean([1, 2, 3, 4, 5, 6, 7])
2.6997245179063363
```

scipy.stats.kurtosis

`scipy.stats.kurtosis(a, axis=0, fisher=True, bias=True, nan_policy='propagate')`

Compute the kurtosis (Fisher or Pearson) of a dataset.

Kurtosis is the fourth central moment divided by the square of the variance. If Fisher's definition is used, then 3.0 is subtracted from the result to give 0.0 for a normal distribution.

If `bias` is `False` then the kurtosis is calculated using k statistics to eliminate bias coming from biased moment estimators

Use `kurtosistest` to see if result is close enough to normal.

Parameters

a	[array] Data for which the kurtosis is calculated.
axis	[int or None, optional] Axis along which the kurtosis is calculated. Default is 0. If None, compute over the whole array <i>a</i> .
fisher	[bool, optional] If True, Fisher's definition is used (normal ==> 0.0). If False, Pearson's definition is used (normal ==> 3.0).
bias	[bool, optional] If False, then the calculations are corrected for statistical bias.
nan_policy	[{'propagate', 'raise', 'omit'}, optional] Defines how to handle when input contains nan. 'propagate' returns nan, 'raise' throws an error, 'omit' performs the calculations ignoring nan values. Default is 'propagate'.

Returns

kurtosis	[array] The kurtosis of values along an axis. If all values are equal, return -3 for Fisher's definition and 0 for Pearson's definition.
-----------------	--

References

[1]

Examples

In Fisher's definition, the kurtosis of the normal distribution is zero. In the following example, the kurtosis is close to zero, because it was calculated from the dataset, not from the continuous distribution.

```
>>> from scipy.stats import norm, kurtosis
>>> data = norm.rvs(size=1000, random_state=3)
>>> kurtosis(data)
-0.06928694200380558
```

The distribution with a higher kurtosis has a heavier tail. The zero valued kurtosis of the normal distribution in Fisher's definition can serve as a reference point.

```
>>> import matplotlib.pyplot as plt
>>> import scipy.stats as stats
>>> from scipy.stats import kurtosis
```

```
>>> x = np.linspace(-5, 5, 100)
>>> ax = plt.subplot()
>>> distnames = ['laplace', 'norm', 'uniform']
```

```
>>> for distname in distnames:
...     if distname == 'uniform':
...         dist = getattr(stats, distname)(loc=-2, scale=4)
...     else:
...         dist = getattr(stats, distname)
...     data = dist.rvs(size=1000)
...     kur = kurtosis(data, fisher=True)
...     y = dist.pdf(x)
...     ax.plot(x, y, label="{}, {}".format(distname, round(kur, 3)))
...     ax.legend()
```

The Laplace distribution has a heavier tail than the normal distribution. The uniform distribution (which has negative kurtosis) has the thinnest tail.

scipy.stats.mode


`scipy.stats.mode` (*a*, *axis=0*, *nan_policy='propagate'*)

Return an array of the modal (most common) value in the passed array.

If there is more than one such value, only the smallest is returned. The bin-count for the modal bins is also returned.

Parameters

- a** [array_like] n-dimensional array of which to find mode(s).
- axis** [int or None, optional] Axis along which to operate. Default is 0. If None, compute over the whole array *a*.
- nan_policy** [{"propagate", "raise", "omit"}, optional] Defines how to handle when input contains nan. The following options are available (default is 'propagate'):



- ‘propagate’: returns nan
- ‘raise’: throws an error
- ‘omit’: performs the calculations ignoring nan values

Returns

- mode** [ndarray] Array of modal values.
count [ndarray] Array of counts for each mode.

Examples

```
>>> a = np.array([[6, 8, 3, 0],
...               [3, 2, 1, 7],
...               [8, 1, 8, 4],
...               [5, 3, 0, 5],
...               [4, 7, 5, 9]])
>>> from scipy import stats
>>> stats.mode(a)
ModeResult(mode=array([[3, 1, 0, 0]]), count=array([[1, 1, 1, 1]]))
```

To get mode of whole array, specify axis=None:

```
>>> stats.mode(a, axis=None)
ModeResult(mode=array([3]), count=array([3]))
```

scipy.stats.moment

`scipy.stats.moment` (*a*, *moment*=1, *axis*=0, *nan_policy*='propagate')

Calculate the nth moment about the mean for a sample.

A moment is a specific quantitative measure of the shape of a set of points. It is often used to calculate coefficients of skewness and kurtosis due to its close relationship with them.

Parameters

- a** [array_like] Input array.
- moment** [int or array_like of ints, optional] Order of central moment that is returned. Default is 1.
- axis** [int or None, optional] Axis along which the central moment is computed. Default is 0. If None, compute over the whole array *a*.
- nan_policy** [{‘propagate’, ‘raise’, ‘omit’}, optional] Defines how to handle when input contains nan. The following options are available (default is ‘propagate’):
- ‘propagate’: returns nan
 - ‘raise’: throws an error
 - ‘omit’: performs the calculations ignoring nan values

Returns

n-th central moment

[ndarray or float] The appropriate moment along the given axis or over all values if axis is None. The denominator for the moment calculation is the number of observations, no degrees of freedom correction is done.

See also:

[*kurtosis*](#), [*skew*](#), [*describe*](#)

Notes

The k-th central moment of a data sample is:

$$m_k = \frac{1}{n} \sum_{i=1}^n (x_i - \bar{x})^k$$

Where n is the number of samples and x-bar is the mean. This function uses exponentiation by squares [1] for efficiency.

References

[1]

Examples

```
>>> from scipy.stats import moment
>>> moment([1, 2, 3, 4, 5], moment=1)
0.0
>>> moment([1, 2, 3, 4, 5], moment=2)
2.0
```

scipy.stats.skew

`scipy.stats.skew` (*a*, *axis=0*, *bias=True*, *nan_policy='propagate'*)

Compute the sample skewness of a data set.

For normally distributed data, the skewness should be about zero. For unimodal continuous distributions, a skewness value greater than zero means that there is more weight in the right tail of the distribution. The function `skewtest` can be used to determine if the skewness value is close enough to zero, statistically speaking.

Parameters

- a** [ndarray] Input array.
- axis** [int or None, optional] Axis along which skewness is calculated. Default is 0. If None, compute over the whole array *a*.
- bias** [bool, optional] If False, then the calculations are corrected for statistical bias.
- nan_policy** [{"propagate", "raise", "omit"}, optional] Defines how to handle when input contains nan. The following options are available (default is "propagate"):
 - "propagate": returns nan
 - "raise": throws an error
 - "omit": performs the calculations ignoring nan values

Returns

- skewness** [ndarray] The skewness of values along an axis, returning 0 where all values are equal.

Notes

The sample skewness is computed as the Fisher-Pearson coefficient of skewness, i.e.

$$g_1 = \frac{m_3}{m_2^{3/2}}$$

where

$$m_i = \frac{1}{N} \sum_{n=1}^N (x[n] - \bar{x})^i$$

is the biased sample *i*th central moment, and \bar{x} is the sample mean. If `bias` is False, the calculations are corrected for bias and the value computed is the adjusted Fisher-Pearson standardized moment coefficient, i.e.

$$G_1 = \frac{k_3}{k_2^{3/2}} = \frac{\sqrt{N(N-1)}}{N-2} \frac{m_3}{m_2^{3/2}}.$$

References

[1]

Examples

```
>>> from scipy.stats import skew
>>> skew([1, 2, 3, 4, 5])
0.0
>>> skew([2, 8, 0, 4, 1, 9, 9, 0])
0.2650554122698573
```

scipy.stats.kstat

`scipy.stats.kstat` (*data*, *n=2*)

Return the *n*th k-statistic (1<=*n*<=4 so far).

The *n*th k-statistic *k_n* is the unique symmetric unbiased estimator of the *n*th cumulant *kappa_n*.

Parameters

data [array_like] Input array. Note that n-D input gets flattened.
n [int, {1, 2, 3, 4}, optional] Default is equal to 2.

Returns

kstat [float] The *n*th k-statistic.

See also:

kstatvar

Returns an unbiased estimator of the variance of the k-statistic.

moment

Returns the *n*-th central moment about the mean for a sample.

Notes

For a sample size *n*, the first few k-statistics are given by:

$$k_1 = \mu k_2 = \frac{n}{n-1} m_2 k_3 = \frac{n^2}{(n-1)(n-2)} m_3 k_4 = \frac{n^2[(n+1)m_4 - 3(n-1)m_2^2]}{(n-1)(n-2)(n-3)}$$

where μ is the sample mean, m_2 is the sample variance, and m_i is the *i*-th sample central moment.

References

<http://mathworld.wolfram.com/k-Statistic.html>

<http://mathworld.wolfram.com/Cumulant.html>

Examples

```
>>> from scipy import stats
>>> rndm = np.random.RandomState(1234)
```

As sample size increases, n-th moment and n-th k-statistic converge to the same number (although they aren't identical). In the case of the normal distribution, they converge to zero.

```
>>> for n in [2, 3, 4, 5, 6, 7]:
...     x = rndm.normal(size=10**n)
...     m, k = stats.moment(x, 3), stats.kstat(x, 3)
...     print("%.3g %.3g %.3g" % (m, k, m-k))
-0.631 -0.651 0.0194
0.0282 0.0283 -8.49e-05
-0.0454 -0.0454 1.36e-05
7.53e-05 7.53e-05 -2.26e-09
0.00166 0.00166 -4.99e-09
-2.88e-06 -2.88e-06 8.63e-13
```

scipy.stats.kstatvar

`scipy.stats.kstatvar` (*data*, *n*=2)

Return an unbiased estimator of the variance of the k-statistic.

See *kstat* for more details of the k-statistic.

Parameters

data [array_like] Input array. Note that n-D input gets flattened.
n [int, {1, 2}, optional] Default is equal to 2.

Returns

kstatvar [float] The nth k-statistic variance.

See also:

kstat

Returns the n-th k-statistic.

moment

Returns the n-th central moment about the mean for a sample.

Notes

The variances of the first few k-statistics are given by:

$$\text{var}(k_1) = \frac{\kappa^2}{n} \text{var}(k_2) = \frac{\kappa^4}{n} + \frac{2\kappa_2^2}{n-1} \text{var}(k_3) = \frac{\kappa^6}{n} + \frac{9\kappa_2\kappa_4}{n-1} + \frac{9\kappa_3^2}{n-1} + \frac{6n\kappa_2^3}{(n-1)(n-2)} \text{var}(k_4) = \frac{\kappa^8}{n} + \frac{16\kappa_2\kappa_6}{n-1} + \frac{48\kappa_3\kappa_5}{n-1}$$

scipy.stats.tmean

`scipy.stats.tmean(a, limits=None, inclusive=True, True, axis=None)`

Compute the trimmed mean.

This function finds the arithmetic mean of given values, ignoring values outside the given *limits*.

Parameters

- a** [array_like] Array of values.
- limits** [None or (lower limit, upper limit), optional] Values in the input array less than the lower limit or greater than the upper limit will be ignored. When limits is None (default), then all values are used. Either of the limit values in the tuple can also be None representing a half-open interval.
- inclusive** [(bool, bool), optional] A tuple consisting of the (lower flag, upper flag). These flags determine whether values exactly equal to the lower or upper limits are included. The default value is (True, True).
- axis** [int or None, optional] Axis along which to compute test. Default is None.

Returns

- tmean** [float] Trimmed mean.

See also:

`trim_mean`

Returns mean after trimming a proportion from both tails.

Examples

```
>>> from scipy import stats
>>> x = np.arange(20)
>>> stats.tmean(x)
9.5
>>> stats.tmean(x, (3, 17))
10.0
```

scipy.stats.tvar

`scipy.stats.tvar(a, limits=None, inclusive=True, True, axis=0, ddof=1)`

Compute the trimmed variance.

This function computes the sample variance of an array of values, while ignoring values which are outside of given *limits*.

Parameters

- a** [array_like] Array of values.

limits	[None or (lower limit, upper limit), optional] Values in the input array less than the lower limit or greater than the upper limit will be ignored. When limits is None, then all values are used. Either of the limit values in the tuple can also be None representing a half-open interval. The default value is None.
inclusive	[(bool, bool), optional] A tuple consisting of the (lower flag, upper flag). These flags determine whether values exactly equal to the lower or upper limits are included. The default value is (True, True).
axis	[int or None, optional] Axis along which to operate. Default is 0. If None, compute over the whole array <i>a</i> .
ddof	[int, optional] Delta degrees of freedom. Default is 1.

Returns

tvar [float] Trimmed variance.

Notes

tvar computes the unbiased sample variance, i.e. it uses a correction factor $n / (n - 1)$.

Examples

```
>>> from scipy import stats
>>> x = np.arange(20)
>>> stats.tvar(x)
35.0
>>> stats.tvar(x, (3,17))
20.0
```

scipy.stats.tmin

`scipy.stats.tmin` (*a*, *lowerlimit*=None, *axis*=0, *inclusive*=True, *nan_policy*='propagate')

Compute the trimmed minimum.

This function finds the minimum value of an array *a* along the specified axis, but only considering values greater than a specified lower limit.

Parameters

a	[array_like] Array of values.
lowerlimit	[None or float, optional] Values in the input array less than the given limit will be ignored. When lowerlimit is None, then all values are used. The default value is None.
axis	[int or None, optional] Axis along which to operate. Default is 0. If None, compute over the whole array <i>a</i> .
inclusive	[[True, False], optional] This flag determines whether values exactly equal to the lower limit are included. The default value is True.
nan_policy	<p>['propagate', 'raise', 'omit'], optional] Defines how to handle when input contains nan. The following options are available (default is 'propagate'):</p> <ul style="list-style-type: none"> • 'propagate': returns nan • 'raise': throws an error • 'omit': performs the calculations ignoring nan values

Returns

tmin [float, int or ndarray] Trimmed minimum.

Examples

```
>>> from scipy import stats
>>> x = np.arange(20)
>>> stats.tmin(x)
0
```

```
>>> stats.tmin(x, 13)
13
```

```
>>> stats.tmin(x, 13, inclusive=False)
14
```

scipy.stats.tmax

`scipy.stats.tmax` (*a*, *upperlimit=None*, *axis=0*, *inclusive=True*, *nan_policy='propagate'*)
Compute the trimmed maximum.

This function computes the maximum value of an array along a given axis, while ignoring values larger than a specified upper limit.

Parameters

- a** [array_like] Array of values.
- upperlimit** [None or float, optional] Values in the input array greater than the given limit will be ignored. When upperlimit is None, then all values are used. The default value is None.
- axis** [int or None, optional] Axis along which to operate. Default is 0. If None, compute over the whole array *a*.
- inclusive** [{True, False}, optional] This flag determines whether values exactly equal to the upper limit are included. The default value is True.
- nan_policy** [{'propagate', 'raise', 'omit'}, optional] Defines how to handle when input contains nan. The following options are available (default is 'propagate'):
- 'propagate': returns nan
 - 'raise': throws an error
 - 'omit': performs the calculations ignoring nan values

Returns

tmax [float, int or ndarray] Trimmed maximum.

Examples

```
>>> from scipy import stats
>>> x = np.arange(20)
>>> stats.tmax(x)
19
```

```
>>> stats.tmax(x, 13)
13
```

```
>>> stats.tmax(x, 13, inclusive=False)
12
```

scipy.stats.tstd

`scipy.stats.tstd(a, limits=None, inclusive=True, True, axis=0, ddof=1)`

Compute the trimmed sample standard deviation.

This function finds the sample standard deviation of given values, ignoring values outside the given *limits*.

Parameters

- a** [array_like] Array of values.
- limits** [None or (lower limit, upper limit), optional] Values in the input array less than the lower limit or greater than the upper limit will be ignored. When *limits* is *None*, then all values are used. Either of the limit values in the tuple can also be *None* representing a half-open interval. The default value is *None*.
- inclusive** [(bool, bool), optional] A tuple consisting of the (lower flag, upper flag). These flags determine whether values exactly equal to the lower or upper limits are included. The default value is (True, True).
- axis** [int or None, optional] Axis along which to operate. Default is 0. If *None*, compute over the whole array *a*.
- ddof** [int, optional] Delta degrees of freedom. Default is 1.

Returns

- tstd** [float] Trimmed sample standard deviation.

Notes

tstd computes the unbiased sample standard deviation, i.e. it uses a correction factor $n / (n - 1)$.

Examples

```
>>> from scipy import stats
>>> x = np.arange(20)
>>> stats.tstd(x)
5.9160797830996161
>>> stats.tstd(x, (3, 17))
4.4721359549995796
```

scipy.stats.tsem

`scipy.stats.tsem(a, limits=None, inclusive=True, True, axis=0, ddof=1)`

Compute the trimmed standard error of the mean.

This function finds the standard error of the mean for given values, ignoring values outside the given *limits*.

Parameters

a	[array_like] Array of values.
limits	[None or (lower limit, upper limit), optional] Values in the input array less than the lower limit or greater than the upper limit will be ignored. When <i>limits</i> is <i>None</i> , then all values are used. Either of the limit values in the tuple can also be <i>None</i> representing a half-open interval. The default value is <i>None</i> .
inclusive	[(bool, bool), optional] A tuple consisting of the (lower flag, upper flag). These flags determine whether values exactly equal to the lower or upper limits are included. The default value is (True, True).
axis	[int or None, optional] Axis along which to operate. Default is 0. If <i>None</i> , compute over the whole array <i>a</i> .
ddof	[int, optional] Delta degrees of freedom. Default is 1.

Returns

tsem [float] Trimmed standard error of the mean.

Notes

tsem uses unbiased sample standard deviation, i.e. it uses a correction factor $n / (n - 1)$.

Examples

```
>>> from scipy import stats
>>> x = np.arange(20)
>>> stats.tsem(x)
1.3228756555322954
>>> stats.tsem(x, (3, 17))
1.1547005383792515
```

scipy.stats.variation

`scipy.stats.variation(a, axis=0, nan_policy='propagate')`

Compute the coefficient of variation.

The coefficient of variation is the ratio of the biased standard deviation to the mean.

Parameters

a	[array_like] Input array.
axis	[int or None, optional] Axis along which to calculate the coefficient of variation. Default is 0. If <i>None</i> , compute over the whole array <i>a</i> .
nan_policy	[{'propagate', 'raise', 'omit'}, optional] Defines how to handle when input contains nan. The following options are available (default is 'propagate'): <ul style="list-style-type: none">• 'propagate': returns nan• 'raise': throws an error

- 'omit': performs the calculations ignoring nan values

Returns

variation [ndarray] The calculated variation along the requested axis.

References

[1]

Examples

```
>>> from scipy.stats import variation
>>> variation([1, 2, 3, 4, 5])
0.47140452079103173
```

scipy.stats.find_repeats

`scipy.stats.find_repeats(arr)`

Find repeats and repeat counts.

Parameters

arr [array_like] Input array. This is cast to float64.

Returns

values [ndarray] The unique values from the (flattened) input that are repeated.

counts [ndarray] Number of times the corresponding 'value' is repeated.

Notes

In numpy >= 1.9 `numpy.unique` provides similar functionality. The main difference is that `find_repeats` only returns repeated values.

Examples

```
>>> from scipy import stats
>>> stats.find_repeats([2, 1, 2, 3, 2, 2, 5])
RepeatedResults(values=array([2.]), counts=array([4]))
```

```
>>> stats.find_repeats([[10, 20, 1, 2], [5, 5, 4, 4]])
RepeatedResults(values=array([4., 5.]), counts=array([2, 2]))
```

scipy.stats.trim_mean

`scipy.stats.trim_mean(a, proportiontocut, axis=0)`

Return mean of array after trimming distribution from both tails.

If `proportiontocut = 0.1`, slices off 'leftmost' and 'rightmost' 10% of scores. The input is sorted before slicing. Slices off less if proportion results in a non-integer slice index (i.e., conservatively slices off `proportiontocut`).

Parameters

a [array_like] Input array.

proportiontocut [float] Fraction to cut off of both tails of the distribution.

axis [int or None, optional] Axis along which the trimmed means are computed. Default is 0. If None, compute over the whole array *a*.

Returns

trim_mean [ndarray] Mean of trimmed array.

See also:

[`trimboth`](#)

[`tmean`](#)

Compute the trimmed mean ignoring values outside given *limits*.

Examples

```
>>> from scipy import stats
>>> x = np.arange(20)
>>> stats.trim_mean(x, 0.1)
9.5
>>> x2 = x.reshape(5, 4)
>>> x2
array([[ 0,  1,  2,  3],
       [ 4,  5,  6,  7],
       [ 8,  9, 10, 11],
       [12, 13, 14, 15],
       [16, 17, 18, 19]])
>>> stats.trim_mean(x2, 0.25)
array([ 8.,  9., 10., 11.])
>>> stats.trim_mean(x2, 0.25, axis=1)
array([ 1.5,  5.5,  9.5, 13.5, 17.5])
```

scipy.stats.gstd

`scipy.stats.gstd(a, axis=0, ddof=1)`

Calculate the geometric standard deviation of an array.

The geometric standard deviation describes the spread of a set of numbers where the geometric mean is preferred. It is a multiplicative factor, and so a dimensionless quantity.

It is defined as the exponent of the standard deviation of $\log(a)$. Mathematically the population geometric standard deviation can be evaluated as:

```
gstd = exp(std(log(a)))
```

New in version 1.3.0.

Parameters

- a** [array_like] An array like object containing the sample data.
- axis** [int, tuple or None, optional] Axis along which to operate. Default is 0. If None, compute over the whole array *a*.
- ddof** [int, optional] Degree of freedom correction in the calculation of the geometric standard deviation. Default is 1.

Returns

ndarray or float

An array of the geometric standard deviation. If *axis* is None or *a* is a 1d array a float is returned.

Notes

As the calculation requires the use of logarithms the geometric standard deviation only supports strictly positive values. Any non-positive or infinite values will raise a *ValueError*. The geometric standard deviation is sometimes confused with the exponent of the standard deviation, $\exp(\text{std}(a))$. Instead the geometric standard deviation is $\exp(\text{std}(\log(a)))$. The default value for *ddof* is different to the default value (0) used by other *ddof* containing functions, such as `np.std` and `np.nanstd`.

Examples

Find the geometric standard deviation of a log-normally distributed sample. Note that the standard deviation of the distribution is one, on a log scale this evaluates to approximately $\exp(1)$.

```
>>> from scipy.stats import gstd
>>> np.random.seed(123)
>>> sample = np.random.lognormal(mean=0, sigma=1, size=1000)
>>> gstd(sample)
2.7217860664589946
```

Compute the geometric standard deviation of a multidimensional array and of a given axis.

```
>>> a = np.arange(1, 25).reshape(2, 3, 4)
>>> gstd(a, axis=None)
2.2944076136018947
>>> gstd(a, axis=2)
array([[1.82424757, 1.22436866, 1.13183117],
```

(continues on next page)

(continued from previous page)

```

    [1.09348306, 1.07244798, 1.05914985]])
>>> gstd(a, axis=(1,2))
array([2.12939215, 1.22120169])

```

The geometric standard deviation further handles masked arrays.

```

>>> a = np.arange(1, 25).reshape(2, 3, 4)
>>> ma = np.ma.masked_where(a > 16, a)
>>> ma
masked_array(
  data=[[ [1, 2, 3, 4],
          [5, 6, 7, 8],
          [9, 10, 11, 12]],
        [[13, 14, 15, 16],
          [--, --, --, --],
          [--, --, --, --]]],
  mask=[[ [False, False, False, False],
          [False, False, False, False],
          [False, False, False, False]],
        [[False, False, False, False],
          [ True,  True,  True,  True],
          [ True,  True,  True,  True]]],
  fill_value=999999)
>>> gstd(ma, axis=2)
masked_array(
  data=[[1.8242475707663655, 1.2243686572447428, 1.1318311657788478],
        [1.0934830582350938, --, --]],
  mask=[[False, False, False],
        [False, True, True]],
  fill_value=999999)

```

scipy.stats.iqr

`scipy.stats.iqr(x, axis=None, rng=(25, 75), scale=1.0, nan_policy='propagate', interpolation='linear', keepdims=False)`

Compute the interquartile range of the data along the specified axis.

The interquartile range (IQR) is the difference between the 75th and 25th percentile of the data. It is a measure of the dispersion similar to standard deviation or variance, but is much more robust against outliers [2].

The `rng` parameter allows this function to compute other percentile ranges than the actual IQR. For example, setting `rng=(0, 100)` is equivalent to `numpy.ptp`.

The IQR of an empty array is `np.nan`.

New in version 0.18.0.

Parameters

- x** [array_like] Input array or object that can be converted to an array.
- axis** [int or sequence of int, optional] Axis along which the range is computed. The default is to compute the IQR for the entire array.
- rng** [Two-element sequence containing floats in range of [0,100] optional] Percentiles over which to compute the range. Each must be between 0 and 100, inclusive. The default is the true IQR: (25, 75). The order of the elements is not important.

- scale** [scalar or str, optional] The numerical value of scale will be divided out of the final result. The following string values are recognized:
- ‘raw’: No scaling, just return the raw IQR. **Deprecated!** Use `scale=1` instead.
 - ‘normal’: Scale by $2\sqrt{2}erf^{-1}(\frac{1}{2}) \approx 1.349$.
- The default is 1.0. The use of `scale='raw'` is deprecated. Array-like scale is also allowed, as long as it broadcasts correctly to the output such that `out / scale` is a valid operation. The output dimensions depend on the input array, `x`, the `axis` argument, and the `keepdims` flag.
- nan_policy** [{‘propagate’, ‘raise’, ‘omit’}, optional] Defines how to handle when input contains nan. The following options are available (default is ‘propagate’):
- ‘propagate’: returns nan
 - ‘raise’: throws an error
 - ‘omit’: performs the calculations ignoring nan values
- interpolation** [{‘linear’, ‘lower’, ‘higher’, ‘midpoint’, ‘nearest’}, optional] Specifies the interpolation method to use when the percentile boundaries lie between two data points `i` and `j`. The following options are available (default is ‘linear’):
- ‘linear’: $i + (j - i) * fraction$, where `fraction` is the fractional part of the index surrounded by `i` and `j`.
 - ‘lower’: `i`.
 - ‘higher’: `j`.
 - ‘nearest’: `i` or `j` whichever is nearest.
 - ‘midpoint’: $(i + j) / 2$.
- keepdims** [bool, optional] If this is set to `True`, the reduced axes are left in the result as dimensions with size one. With this option, the result will broadcast correctly against the original array `x`.

Returns

- iqr** [scalar or ndarray] If `axis=None`, a scalar is returned. If the input contains integers or floats of smaller precision than `np.float64`, then the output data-type is `np.float64`. Otherwise, the output data-type is the same as that of the input.

See also:

`numpy.std`, `numpy.var`

Notes

This function is heavily dependent on the version of `numpy` that is installed. Versions greater than 1.11.0b3 are highly recommended, as they include a number of enhancements and fixes to `numpy.percentile` and `numpy.nanpercentile` that affect the operation of this function. The following modifications apply:

Below 1.10.0

[`nan_policy` is poorly defined.] The default behavior of `numpy.percentile` is used for ‘propagate’. This is a hybrid of ‘omit’ and ‘propagate’ that mostly yields a skewed version of ‘omit’ since NaNs are sorted to the end of the data. A warning is raised if there are NaNs in the data.

Below 1.9.0: `numpy.nanpercentile` does not exist.

This means that `numpy.percentile` is used regardless of `nan_policy` and a warning is issued. See previous item for a description of the behavior.

Below 1.9.0: `keepdims` and `interpolation` are not supported.

The keywords get ignored with a warning if supplied with non-default values. However, multiple axes are still supported.

References

[1], [2], [3]

Examples

```
>>> from scipy.stats import iqr
>>> x = np.array([[10, 7, 4], [3, 2, 1]])
>>> x
array([[10,  7,  4],
       [ 3,  2,  1]])
>>> iqr(x)
4.0
>>> iqr(x, axis=0)
array([ 3.5,  2.5,  1.5])
>>> iqr(x, axis=1)
array([ 3.,  1.])
>>> iqr(x, axis=1, keepdims=True)
array([[ 3.],
       [ 1.]])
```

scipy.stats.sem

`scipy.stats.sem(a, axis=0, ddof=1, nan_policy='propagate')`

Compute standard error of the mean.

Calculate the standard error of the mean (or standard error of measurement) of the values in the input array.

Parameters

- a** [array_like] An array containing the values for which the standard error is returned.
- axis** [int or None, optional] Axis along which to operate. Default is 0. If None, compute over the whole array *a*.
- ddof** [int, optional] Delta degrees-of-freedom. How many degrees of freedom to adjust for bias in limited samples relative to the population estimate of variance. Defaults to 1.
- nan_policy** [{'propagate', 'raise', 'omit'}, optional] Defines how to handle when input contains nan. The following options are available (default is 'propagate'):
- 'propagate': returns nan
 - 'raise': throws an error
 - 'omit': performs the calculations ignoring nan values

Returns

- s** [ndarray or float] The standard error of the mean in the sample(s), along the input axis.

Notes

The default value for *ddof* is different to the default (0) used by other *ddof* containing routines, such as `np.std` and `np.nanstd`.

Examples

Find standard error along the first axis:

```
>>> from scipy import stats
>>> a = np.arange(20).reshape(5,4)
>>> stats.sem(a)
array([ 2.8284,  2.8284,  2.8284,  2.8284])
```

Find standard error across the whole array, using *n* degrees of freedom:

```
>>> stats.sem(a, axis=None, ddof=0)
1.2893796958227628
```

scipy.stats.bayes_mvs

`scipy.stats.bayes_mvs` (*data*, *alpha*=0.9)

Bayesian confidence intervals for the mean, var, and std.

Parameters

- data** [array_like] Input data, if multi-dimensional it is flattened to 1-D by `bayes_mvs`. Requires 2 or more data points.
- alpha** [float, optional] Probability that the returned confidence interval contains the true parameter.

Returns

mean_cntr, var_cntr, std_cntr

[tuple] The three results are for the mean, variance and standard deviation, respectively. Each result is a tuple of the form:

```
(center, (lower, upper))
```

with *center* the mean of the conditional pdf of the value given the data, and (*lower*, *upper*) a confidence interval, centered on the median, containing the estimate to a probability *alpha*.

See also:

[`mvstdist`](#)

Notes

Each tuple of mean, variance, and standard deviation estimates represent the (*center*, (*lower*, *upper*)) with *center* the mean of the conditional pdf of the value given the data and (*lower*, *upper*) is a confidence interval centered on the median, containing the estimate to a probability *alpha*.

Converts data to 1-D and assumes all data has the same mean and variance. Uses Jeffrey's prior for variance and std.

Equivalent to `tuple((x.mean(), x.interval(alpha)) for x in mvstdist(dat))`

References

T.E. Oliphant, “A Bayesian perspective on estimating mean, variance, and standard-deviation from data”, <https://scholarsarchive.byu.edu/facpub/278>, 2006.

Examples

First a basic example to demonstrate the outputs:


```
>>> from scipy import stats
>>> data = [6, 9, 12, 7, 8, 8, 13]
>>> mean, var, std = stats.bayes_mvs(data)
>>> mean
Mean(statistic=9.0, minmax=(7.103650222612533, 10.896349777387467))
>>> var
Variance(statistic=10.0, minmax=(3.176724206..., 24.45910382...))
>>> std
Std_dev(statistic=2.9724954732045084, minmax=(1.7823367265645143, 4.
→945614605014631))
```

Now we generate some normally distributed random data, and get estimates of mean and standard deviation with 95% confidence intervals for those estimates:

```
>>> n_samples = 100000
>>> data = stats.norm.rvs(size=n_samples)
>>> res_mean, res_var, res_std = stats.bayes_mvs(data, alpha=0.95)
```

```
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> ax.hist(data, bins=100, density=True, label='Histogram of data')
>>> ax.vlines(res_mean.statistic, 0, 0.5, colors='r', label='Estimated_
→mean')
>>> ax.axvspan(res_mean.minmax[0], res_mean.minmax[1], facecolor='r',
...             alpha=0.2, label=r'Estimated mean (95% limits)')
>>> ax.vlines(res_std.statistic, 0, 0.5, colors='g', label='Estimated_
→scale')
>>> ax.axvspan(res_std.minmax[0], res_std.minmax[1], facecolor='g',
→alpha=0.2,
...             label=r'Estimated scale (95% limits)')
```

```
>>> ax.legend(fontsize=10)
>>> ax.set_xlim([-4, 4])
>>> ax.set_ylim([0, 0.5])
>>> plt.show()
```



scipy.stats.mvstdist

`scipy.stats.mvstdist` (*data*)

'Frozen' distributions for mean, variance, and standard deviation of data.

Parameters

data [array_like] Input array. Converted to 1-D using `ravel`. Requires 2 or more data-points.

Returns

mdist ["frozen" distribution object] Distribution object representing the mean of the data.
vdist ["frozen" distribution object] Distribution object representing the variance of the data.
sdist ["frozen" distribution object] Distribution object representing the standard deviation of the data.

See also:

[*bayes_mvs*](#)

Notes

The return values from `bayes_mvs(data)` is equivalent to `tuple((x.mean(), x.interval(0.90)) for x in mvstdist(data))`.

In other words, calling `<dist>.mean()` and `<dist>.interval(0.90)` on the three distribution objects returned from this function will give the same results that are returned from [*bayes_mvs*](#).

References

T.E. Oliphant, “A Bayesian perspective on estimating mean, variance, and standard-deviation from data”, <https://scholarsarchive.byu.edu/facpub/278>, 2006.

Examples

```
>>> from scipy import stats
>>> data = [6, 9, 12, 7, 8, 8, 13]
>>> mean, var, std = stats.mvstdist(data)
```

We now have frozen distribution objects “mean”, “var” and “std” that we can examine:

```
>>> mean.mean()
9.0
>>> mean.interval(0.95)
(6.6120585482655692, 11.387941451734431)
>>> mean.std()
1.1952286093343936
```

scipy.stats.entropy

`scipy.stats.entropy(pk, qk=None, base=None, axis=0)`

Calculate the entropy of a distribution for given probability values.

If only probabilities pk are given, the entropy is calculated as $S = -\sum(pk * \log(pk), axis=axis)$.

If qk is not None, then compute the Kullback-Leibler divergence $S = \sum(pk * \log(pk / qk), axis=axis)$.

This routine will normalize pk and qk if they don't sum to 1.

Parameters

- pk** [sequence] Defines the (discrete) distribution. $pk[i]$ is the (possibly unnormalized) probability of event i .
- qk** [sequence, optional] Sequence against which the relative entropy is computed. Should be in the same format as pk .
- base** [float, optional] The logarithmic base to use, defaults to e (natural logarithm).
- axis: int, optional**
The axis along which the entropy is calculated. Default is 0.

Returns

- S** [float] The calculated entropy.

Examples

```
>>> from scipy.stats import entropy
```

Bernoulli trial with different p. The outcome of a fair coin is the most uncertain:

```
>>> entropy([1/2, 1/2], base=2)
1.0
```

The outcome of a biased coin is less uncertain:

```
>>> entropy([9/10, 1/10], base=2)
0.46899559358928117
```

Relative entropy:

```
>>> entropy([1/2, 1/2], qk=[9/10, 1/10])
0.5108256237659907
```

scipy.stats.median_absolute_deviation

`scipy.stats.median_absolute_deviation(*args, **kwargs)`

median_absolute_deviation is deprecated, use *median_abs_deviation* instead!

To preserve the existing default behavior, use `scipy.stats.median_abs_deviation(..., scale=1/1.4826)`. The value 1.4826 is not numerically precise for scaling with a normal distribution. For a numerically precise value, use `scipy.stats.median_abs_deviation(..., scale='normal')`.

Compute the median absolute deviation of the data along the given axis.

The median absolute deviation (MAD, [1]) computes the median over the absolute deviations from the median. It is a measure of dispersion similar to the standard deviation but more robust to outliers [2].

The MAD of an empty array is `np.nan`.

New in version 1.3.0.

Parameters

- | | |
|-------------------|---|
| x | [array_like] Input array or object that can be converted to an array. |
| axis | [int or None, optional] Axis along which the range is computed. Default is 0. If None, compute the MAD over the entire array. |
| center | [callable, optional] A function that will return the central value. The default is to use <code>np.median</code> . Any user defined function used will need to have the function signature <code>func(arr, axis)</code> . |
| scale | [int, optional] The scaling factor applied to the MAD. The default scale (1.4826) ensures consistency with the standard deviation for normally distributed data. |
| nan_policy | [{"propagate", "raise", "omit"}, optional] Defines how to handle when input contains nan. The following options are available (default is "propagate"): <ul style="list-style-type: none"> • "propagate": returns nan • "raise": throws an error • "omit": performs the calculations ignoring nan values |

Returns

mad [scalar or ndarray] If `axis=None`, a scalar is returned. If the input contains integers or floats of smaller precision than `np.float64`, then the output data-type is `np.float64`. Otherwise, the output data-type is the same as that of the input.

See also:

`numpy.std`, `numpy.var`, `numpy.median`, `scipy.stats.iqr`, `scipy.stats.tmean`
`scipy.stats.tstd`, `scipy.stats.tvar`

Notes

The `center` argument only affects the calculation of the central value around which the MAD is calculated. That is, passing in `center=np.mean` will calculate the MAD around the mean - it will not calculate the *mean* absolute deviation.

References

[1], [2]

Examples

When comparing the behavior of `median_absolute_deviation` with `np.std`, the latter is affected when we change a single value of an array to have an outlier value while the MAD hardly changes:

```
>>> from scipy import stats
>>> x = stats.norm.rvs(size=100, scale=1, random_state=123456)
>>> x.std()
0.9973906394005013
>>> stats.median_absolute_deviation(x)
1.2280762773108278
>>> x[0] = 345.6
>>> x.std()
34.42304872314415
>>> stats.median_absolute_deviation(x)
1.2340335571164334
```

Axis handling example:

```
>>> x = np.array([[10, 7, 4], [3, 2, 1]])
>>> x
array([[10,  7,  4],
       [ 3,  2,  1]])
>>> stats.median_absolute_deviation(x)
array([5.1891, 3.7065, 2.2239])
>>> stats.median_absolute_deviation(x, axis=None)
2.9652
```


scipy.stats.median_abs_deviation

`scipy.stats.median_abs_deviation(x, axis=0, center=<function median at 0x7f89442f2790>, scale=1.0, nan_policy='propagate')`

Compute the median absolute deviation of the data along the given axis.

The median absolute deviation (MAD, [1]) computes the median over the absolute deviations from the median. It is a measure of dispersion similar to the standard deviation but more robust to outliers [2].

The MAD of an empty array is `np.nan`.

New in version 1.5.0.

Parameters

- x** [array_like] Input array or object that can be converted to an array.
- axis** [int or None, optional] Axis along which the range is computed. Default is 0. If None, compute the MAD over the entire array.
- center** [callable, optional] A function that will return the central value. The default is to use `np.median`. Any user defined function used will need to have the function signature `func(arr, axis)`.
- scale** [scalar or str, optional] The numerical value of scale will be divided out of the final result. The default is 1.0. The string “normal” is also accepted, and results in *scale* being the inverse of the standard normal quantile function at 0.75, which is approximately 0.67449. Array-like scale is also allowed, as long as it broadcasts correctly to the output such that `out / scale` is a valid operation. The output dimensions depend on the input array, *x*, and the *axis* argument.
- nan_policy** [{‘propagate’, ‘raise’, ‘omit’}, optional] Defines how to handle when input contains nan. The following options are available (default is ‘propagate’):
 - ‘propagate’: returns nan
 - ‘raise’: throws an error
 - ‘omit’: performs the calculations ignoring nan values

Returns

- mad** [scalar or ndarray] If `axis=None`, a scalar is returned. If the input contains integers or floats of smaller precision than `np.float64`, then the output data-type is `np.float64`. Otherwise, the output data-type is the same as that of the input.

See also:

`numpy.std`, `numpy.var`, `numpy.median`, `scipy.stats.iqr`, `scipy.stats.tmean`
`scipy.stats.tstd`, `scipy.stats.tvar`

Notes

The *center* argument only affects the calculation of the central value around which the MAD is calculated. That is, passing in `center=np.mean` will calculate the MAD around the mean - it will not calculate the *mean* absolute deviation.

The input array may contain *inf*, but if *center* returns *inf*, the corresponding MAD for that data will be *nan*.

References

[1], [2]

Examples

When comparing the behavior of `median_abs_deviation` with `np.std`, the latter is affected when we change a single value of an array to have an outlier value while the MAD hardly changes:

```
>>> from scipy import stats
>>> x = stats.norm.rvs(size=100, scale=1, random_state=123456)
>>> x.std()
0.9973906394005013
>>> stats.median_abs_deviation(x)
0.82832610097857
>>> x[0] = 345.6
>>> x.std()
34.42304872314415
>>> stats.median_abs_deviation(x)
0.8323442311590675
```

Axis handling example:

```
>>> x = np.array([[10, 7, 4], [3, 2, 1]])
>>> x
array([[10, 7, 4],
       [ 3, 2, 1]])
>>> stats.median_abs_deviation(x)
array([3.5, 2.5, 1.5])
>>> stats.median_abs_deviation(x, axis=None)
2.0
```

Scale normal example:

```
>>> x = stats.norm.rvs(size=1000000, scale=2, random_state=123456)
>>> stats.median_abs_deviation(x)
1.3487398527041636
>>> stats.median_abs_deviation(x, scale='normal')
1.9996446978061115
```

6.29.8 Frequency statistics

<code>cumfreq(a[, numbins, defaultreallimits, weights])</code>	Return a cumulative frequency histogram, using the histogram function.
<code>itemfreq(*args, **kwargs)</code>	<code>itemfreq</code> is deprecated! <code>itemfreq</code> is deprecated and will be removed in a future version.
<code>percentileofscore(a, score[, kind])</code>	Compute the percentile rank of a score relative to a list of scores.
<code>scoreatpercentile(a, per[, limit, ...])</code>	Calculate the score at a given percentile of the input sequence.

continues on next page

Table 262 – continued from previous page

<code>relfreq(a[, numbins, defaultreallimits, weights])</code>	Return a relative frequency histogram, using the histogram function.
--	--

scipy.stats.cumfreq

`scipy.stats.cumfreq(a, numbins=10, defaultreallimits=None, weights=None)`

Return a cumulative frequency histogram, using the histogram function.

A cumulative histogram is a mapping that counts the cumulative number of observations in all of the bins up to the specified bin.

Parameters

- a** [array_like] Input array.
- numbins** [int, optional] The number of bins to use for the histogram. Default is 10.
- defaultreallimits** [tuple (lower, upper), optional] The lower and upper values for the range of the histogram. If no value is given, a range slightly larger than the range of the values in *a* is used. Specifically $(a.\min() - s, a.\max() + s)$, where $s = (1/2)(a.\max() - a.\min()) / (\text{numbins} - 1)$.
- weights** [array_like, optional] The weights for each value in *a*. Default is None, which gives each value a weight of 1.0

Returns

- cumcount** [ndarray] Binned values of cumulative frequency.
- lowerlimit** [float] Lower real limit
- binsize** [float] Width of each bin.
- extrapoints** [int] Extra points.

Examples

```
>>> import matplotlib.pyplot as plt
>>> from scipy import stats
>>> x = [1, 4, 2, 1, 3, 1]
>>> res = stats.cumfreq(x, numbins=4, defaultreallimits=(1.5, 5))
>>> res.cumcount
array([ 1.,  2.,  3.,  3.])
>>> res.extrapoints
3
```

Create a normal distribution with 1000 random values

```
>>> rng = np.random.RandomState(seed=12345)
>>> samples = stats.norm.rvs(size=1000, random_state=rng)
```

Calculate cumulative frequencies

```
>>> res = stats.cumfreq(samples, numbins=25)
```


Calculate space of values for x

```
>>> x = res.lowerlimit + np.linspace(0, res.binsize*res.cumcount.size,
...                                  res.cumcount.size)
```

Plot histogram and cumulative histogram

```
>>> fig = plt.figure(figsize=(10, 4))
>>> ax1 = fig.add_subplot(1, 2, 1)
>>> ax2 = fig.add_subplot(1, 2, 2)
>>> ax1.hist(samples, bins=25)
>>> ax1.set_title('Histogram')
>>> ax2.bar(x, res.cumcount, width=res.binsize)
>>> ax2.set_title('Cumulative histogram')
>>> ax2.set_xlim([x.min(), x.max()])
```

```
>>> plt.show()
```



scipy.stats.itemfreq

`scipy.stats.itemfreq(*args, **kwargs)`

itemfreq is deprecated! *itemfreq* is deprecated and will be removed in a future version. Use instead `np.unique(..., return_counts=True)`

Return a 2-D array of item frequencies.

Parameters

a [(N,) array_like] Input array.

Returns

itemfreq [(K, 2) ndarray] A 2-D frequency table. Column 1 contains sorted, unique values from *a*, column 2 contains their respective counts.

Examples

```
>>> from scipy import stats
>>> a = np.array([1, 1, 5, 0, 1, 2, 2, 0, 1, 4])
>>> stats.itemfreq(a)
array([[ 0.,  2.],
       [ 1.,  4.],
       [ 2.,  2.],
       [ 4.,  1.],
       [ 5.,  1.]])
>>> np.bincount(a)
array([2, 4, 2, 0, 1, 1])
```

```
>>> stats.itemfreq(a/10.)
array([[ 0. ,  2. ],
       [ 0.1,  4. ],
       [ 0.2,  2. ],
       [ 0.4,  1. ],
       [ 0.5,  1. ]])
```

scipy.stats.percentileofscore

`scipy.stats.percentileofscore` (*a*, *score*, *kind*='rank')

Compute the percentile rank of a score relative to a list of scores.

A *percentileofscore* of, for example, 80% means that 80% of the scores in *a* are below the given score. In the case of gaps or ties, the exact definition depends on the optional keyword, *kind*.

Parameters

- | | |
|--------------|--|
| a | [array_like] Array of scores to which <i>score</i> is compared. |
| score | [int or float] Score that is compared to the elements in <i>a</i> . |
| kind | [{'rank', 'weak', 'strict', 'mean'}, optional] Specifies the interpretation of the resulting score. The following options are available (default is 'rank'): |
- 'rank': Average percentage ranking of score. In case of multiple matches, average the percentage rankings of all matching scores.
 - 'weak': This kind corresponds to the definition of a cumulative distribution function. A percentileofscore of 80% means that 80% of values are less than or equal to the provided score.
 - 'strict': Similar to "weak", except that only values that are strictly less than the given score are counted.
 - 'mean': The average of the "weak" and "strict" scores, often used in testing. See https://en.wikipedia.org/wiki/Percentile_rank

Returns

- | | |
|-------------|---|
| pcos | [float] Percentile-position of score (0-100) relative to <i>a</i> . |
|-------------|---|

See also:

[*numpy.percentile*](#)

Examples

Three-quarters of the given values lie below a given score:

```
>>> from scipy import stats
>>> stats.percentileofscore([1, 2, 3, 4], 3)
75.0
```

With multiple matches, note how the scores of the two matches, 0.6 and 0.8 respectively, are averaged:

```
>>> stats.percentileofscore([1, 2, 3, 3, 4], 3)
70.0
```

Only 2/5 values are strictly less than 3:

```
>>> stats.percentileofscore([1, 2, 3, 3, 4], 3, kind='strict')
40.0
```

But 4/5 values are less than or equal to 3:

```
>>> stats.percentileofscore([1, 2, 3, 3, 4], 3, kind='weak')
80.0
```

The average between the weak and the strict scores is:

```
>>> stats.percentileofscore([1, 2, 3, 3, 4], 3, kind='mean')
60.0
```

scipy.stats.scoreatpercentile

`scipy.stats.scoreatpercentile(a, per, limit=(), interpolation_method='fraction', axis=None)`

Calculate the score at a given percentile of the input sequence.

For example, the score at *per*=50 is the median. If the desired quantile lies between two data points, we interpolate between them, according to the value of *interpolation*. If the parameter *limit* is provided, it should be a tuple (lower, upper) of two values.

Parameters

- a** [array_like] A 1-D array of values from which to extract score.
- per** [array_like] Percentile(s) at which to extract score. Values should be in range [0,100].
- limit** [tuple, optional] Tuple of two scalars, the lower and upper limits within which to compute the percentile. Values of *a* outside this (closed) interval will be ignored.
- interpolation_method** [{‘fraction’, ‘lower’, ‘higher’}, optional] Specifies the interpolation method to use, when the desired quantile lies between two data points *i* and *j*. The following options are available (default is ‘fraction’):
 - ‘fraction’: $i + (j - i) * \text{fraction}$ where *fraction* is the fractional part of the index surrounded by *i* and *j*
 - ‘lower’: *i*
 - ‘higher’: *j*
- axis** [int, optional] Axis along which the percentiles are computed. Default is None. If None, compute over the whole array *a*.

Returns

score [float or ndarray] Score at percentile(s).

See also:

percentileofscore, *numpy.percentile*

Notes

This function will become obsolete in the future. For NumPy 1.9 and higher, `numpy.percentile` provides all the functionality that `scoreatpercentile` provides. And it's significantly faster. Therefore it's recommended to use `numpy.percentile` for users that have `numpy >= 1.9`.

Examples

```
>>> from scipy import stats
>>> a = np.arange(100)
>>> stats.scoreatpercentile(a, 50)
49.5
```

scipy.stats.relfreq

`scipy.stats.relfreq(a, numbins=10, defaultreallimits=None, weights=None)`

Return a relative frequency histogram, using the histogram function.

A relative frequency histogram is a mapping of the number of observations in each of the bins relative to the total of observations.

Parameters

a [array_like] Input array.
numbins [int, optional] The number of bins to use for the histogram. Default is 10.
defaultreallimits [tuple (lower, upper), optional] The lower and upper values for the range of the histogram. If no value is given, a range slightly larger than the range of the values in *a* is used. Specifically $(a.min() - s, a.max() + s)$, where $s = (1/2)(a.max() - a.min()) / (numbins - 1)$.
weights [array_like, optional] The weights for each value in *a*. Default is None, which gives each value a weight of 1.0

Returns

frequency [ndarray] Binned values of relative frequency.
lowerlimit [float] Lower real limit.
binsize [float] Width of each bin.
extrapoints [int] Extra points.

Examples

```
>>> import matplotlib.pyplot as plt
>>> from scipy import stats
>>> a = np.array([2, 4, 1, 2, 3, 2])
>>> res = stats.relfreq(a, numbins=4)
>>> res.frequency
array([ 0.16666667, 0.5          , 0.16666667, 0.16666667])
>>> np.sum(res.frequency) # relative frequencies should add up to 1
1.0
```

Create a normal distribution with 1000 random values

```
>>> rng = np.random.RandomState(seed=12345)
>>> samples = stats.norm.rvs(size=1000, random_state=rng)
```

Calculate relative frequencies

```
>>> res = stats.relfreq(samples, numbins=25)
```

Calculate space of values for x

```
>>> x = res.lowerlimit + np.linspace(0, res.binsize*res.frequency.size,
...                                 res.frequency.size)
```

Plot relative frequency histogram

```
>>> fig = plt.figure(figsize=(5, 4))
>>> ax = fig.add_subplot(1, 1, 1)
>>> ax.bar(x, res.frequency, width=res.binsize)
>>> ax.set_title('Relative frequency histogram')
>>> ax.set_xlim([x.min(), x.max()])
```

```
>>> plt.show()
```

<code>binned_statistic(x, values[, statistic, ...])</code>	Compute a binned statistic for one or more sets of data.
<code>binned_statistic_2d(x, y, values[, ...])</code>	Compute a bidimensional binned statistic for one or more sets of data.
<code>binned_statistic_dd(sample, values[, ...])</code>	Compute a multidimensional binned statistic for a set of data.

scipy.stats.binned_statistic


`scipy.stats.binned_statistic(x, values, statistic='mean', bins=10, range=None)`

Compute a binned statistic for one or more sets of data.

This is a generalization of a histogram function. A histogram divides the space into bins, and returns the count of the number of points in each bin. This function allows the computation of the sum, mean, median, or other statistic of the values (or set of values) within each bin.

Parameters

x [(N,) array_like] A sequence of values to be binned.



- values** [(N,) array_like or list of (N,) array_like] The data on which the statistic will be computed. This must be the same shape as *x*, or a set of sequences - each the same shape as *x*. If *values* is a set of sequences, the statistic will be computed on each independently.
- statistic** [string or callable, optional] The statistic to compute (default is 'mean'). The following statistics are available:
- 'mean': compute the mean of values for points within each bin. Empty bins will be represented by NaN.
 - 'std': compute the standard deviation within each bin. This is implicitly calculated with `ddof=0`.
 - 'median': compute the median of values for points within each bin. Empty bins will be represented by NaN.
 - 'count': compute the count of points within each bin. This is identical to an unweighted histogram. *values* array is not referenced.
 - 'sum': compute the sum of values for points within each bin. This is identical to a weighted histogram.
 - 'min': compute the minimum of values for points within each bin. Empty bins will be represented by NaN.
 - 'max': compute the maximum of values for point within each bin. Empty bins will be represented by NaN.
 - function: a user-defined function which takes a 1D array of values, and outputs a single numerical statistic. This function will be called on the values in each bin. Empty bins will be represented by `function([])`, or NaN if this returns an error.
- bins** [int or sequence of scalars, optional] If *bins* is an int, it defines the number of equal-width bins in the given range (10 by default). If *bins* is a sequence, it defines the bin edges, including the rightmost edge, allowing for non-uniform bin widths. Values in *x* that are smaller than lowest bin edge are assigned to bin number 0, values beyond the highest bin are assigned to `bins[-1]`. If the bin edges are specified, the number of bins will be, $(n_x = \text{len}(\text{bins}) - 1)$.
- range** [(float, float) or [(float, float)], optional] The lower and upper range of the bins. If not pro-

vided, range is simply `(x.min(), x.max())`. Values outside the range are ignored.

Returns

statistic [array] The values of the selected statistic in each bin.
bin_edges [array of dtype float] Return the bin edges (`length(statistic)+1`).
binnumber: 1-D ndarray of ints
 Indices of the bins (corresponding to `bin_edges`) in which each value of `x` belongs. Same length as `values`. A binnumber of `i` means the corresponding value is between (`bin_edges[i-1]`, `bin_edges[i]`).

See also:

`numpy.digitize`, `numpy.histogram`, `binned_statistic_2d`, `binned_statistic_dd`

Notes

All but the last (righthand-most) bin is half-open. In other words, if `bins` is `[1, 2, 3, 4]`, then the first bin is `[1, 2)` (including 1, but excluding 2) and the second `[2, 3)`. The last bin, however, is `[3, 4]`, which includes 4.

New in version 0.11.0.

Examples

```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
```

First some basic examples:

Create two evenly spaced bins in the range of the given sample, and sum the corresponding values in each of those bins:

```
>>> values = [1.0, 1.0, 2.0, 1.5, 3.0]
>>> stats.binned_statistic([1, 1, 2, 5, 7], values, 'sum', bins=2)
BinnedStatisticResult(statistic=array([4. , 4.5]),
                       bin_edges=array([1., 4., 7.]), binnumber=array([1, 1, 1, 2, 2]))
```

Multiple arrays of values can also be passed. The statistic is calculated on each set independently:

```
>>> values = [[1.0, 1.0, 2.0, 1.5, 3.0], [2.0, 2.0, 4.0, 3.0, 6.0]]
>>> stats.binned_statistic([1, 1, 2, 5, 7], values, 'sum', bins=2)
BinnedStatisticResult(statistic=array([[4. , 4.5],
    [8. , 9. ]]), bin_edges=array([1., 4., 7.]),
                       binnumber=array([1, 1, 1, 2, 2]))
```

```
>>> stats.binned_statistic([1, 2, 1, 2, 4], np.arange(5), statistic='mean',
    ...                     bins=3)
BinnedStatisticResult(statistic=array([1., 2., 4.]),
                       bin_edges=array([1., 2., 3., 4.]),
                       binnumber=array([1, 2, 1, 2, 3]))
```

As a second example, we now generate some random data of sailing boat speed as a function of wind speed, and then determine how fast our boat is for certain wind speeds:

```

>>> windspeed = 8 * np.random.rand(500)
>>> boatspeed = .3 * windspeed**.5 + .2 * np.random.rand(500)
>>> bin_means, bin_edges, binnumber = stats.binned_statistic(windspeed,
...
...                               boatspeed, statistic='median', bins=[1,2,3,4,5,6,7])
>>> plt.figure()
>>> plt.plot(windspeed, boatspeed, 'b.', label='raw data')
>>> plt.hlines(bin_means, bin_edges[:-1], bin_edges[1:], colors='g', lw=5,
...
...           label='binned statistic of data')
>>> plt.legend()

```

Now we can use `binnumber` to select all datapoints with a windspeed below 1:

```

>>> low_boatspeed = boatspeed[binnumber == 0]

```

As a final example, we will use `bin_edges` and `binnumber` to make a plot of a distribution that shows the mean and distribution around that mean per bin, on top of a regular histogram and the probability distribution function:

```

>>> x = np.linspace(0, 5, num=500)
>>> x_pdf = stats.maxwell.pdf(x)
>>> samples = stats.maxwell.rvs(size=10000)

```

```

>>> bin_means, bin_edges, binnumber = stats.binned_statistic(x, x_pdf,
...
...                               statistic='mean', bins=25)
>>> bin_width = (bin_edges[1] - bin_edges[0])
>>> bin_centers = bin_edges[1:] - bin_width/2

```

```

>>> plt.figure()
>>> plt.hist(samples, bins=50, density=True, histtype='stepfilled',
...
...         alpha=0.2, label='histogram of data')
>>> plt.plot(x, x_pdf, 'r-', label='analytical pdf')
>>> plt.hlines(bin_means, bin_edges[:-1], bin_edges[1:], colors='g', lw=2,
...
...           label='binned statistic of data')
>>> plt.plot((binnumber - 0.5) * bin_width, x_pdf, 'g.', alpha=0.5)
>>> plt.legend(fontsize=10)
>>> plt.show()

```

scipy.stats.binned_statistic_2d



`scipy.stats.binned_statistic_2d(x, y, values, statistic='mean', bins=10, range=None, expand_binnumbers=False)`

Compute a bidimensional binned statistic for one or more sets of data.

This is a generalization of a `histogram2d` function. A histogram divides the space into bins, and returns the count of the number of points in each bin. This function allows the computation of the sum, mean, median, or other statistic of the values (or set of values) within each bin.

Parameters

- x** [(N,) array_like] A sequence of values to be binned along the first dimension.
- y** [(N,) array_like] A sequence of values to be binned along the second dimension.
- values** [(N,) array_like or list of (N,) array_like] The data on which the statistic will be computed. This must be the same shape as `x`, or a list of sequences - each with the same shape as `x`. If `values` is such a list, the statistic will be computed on each independently.



- statistic** [string or callable, optional] The statistic to compute (default is ‘mean’). The following statistics are available:
- ‘mean’: compute the mean of values for points within each bin. Empty bins will be represented by NaN.
 - ‘std’: compute the standard deviation within each bin. This is implicitly calculated with `ddof=0`.
 - ‘median’: compute the median of values for points within each bin. Empty bins will be represented by NaN.
 - ‘count’: compute the count of points within each bin. This is identical to an unweighted histogram. *values* array is not referenced.
 - ‘sum’: compute the sum of values for points within each bin. This is identical to a weighted histogram.
 - ‘min’: compute the minimum of values for points within each bin. Empty bins will be represented by NaN.
 - ‘max’: compute the maximum of values for point within each bin. Empty bins will be represented by NaN.
 - function: a user-defined function which takes a 1D array of values, and outputs a single numerical statistic. This function will be called on the values in each bin. Empty bins will be represented by `function([])`, or NaN if this returns an error.
- bins** [int or [int, int] or array_like or [array, array], optional] The bin specification:
- the number of bins for the two dimensions (`nx = ny = bins`),
 - the number of bins in each dimension (`nx, ny = bins`),
 - the bin edges for the two dimensions (`x_edge = y_edge = bins`),
 - the bin edges in each dimension (`x_edge, y_edge = bins`).
- If the bin edges are specified, the number of bins will be, (`nx = len(x_edge)-1`, `ny = len(y_edge)-1`).
- range** [(2,2) array_like, optional] The leftmost and rightmost edges of the bins along each dimension (if not specified explicitly in the *bins* parameters): `[[xmin, xmax], [ymin, ymax]]`. All values outside of this range will be considered outliers and not tallied in the histogram.
- expand_binnumbers** [bool, optional] ‘False’ (default): the returned *binnumber* is a shape (N,) array of linearized bin indices. ‘True’: the returned *binnumber* is ‘unraveled’ into a shape (2,N) ndarray, where each row gives the bin numbers in the corresponding dimension. See the *binnumber* returned value, and the *Examples* section.
- New in version 0.17.0.

Returns

- statistic** [(nx, ny) ndarray] The values of the selected statistic in each two-dimensional bin.
- x_edge** [(nx + 1) ndarray] The bin edges along the first dimension.
- y_edge** [(ny + 1) ndarray] The bin edges along the second dimension.
- binnumber** [(N,) array of ints or (2,N) ndarray of ints] This assigns to each element of *sample* an integer that represents the bin in which this observation falls. The representation depends on the *expand_binnumbers* argument. See *Notes* for details.

See also:

[*numpy.digitize*](#), [*numpy.histogram2d*](#), [*binned_statistic*](#), [*binned_statistic_dd*](#)

Notes

Binedges: All but the last (righthand-most) bin is half-open. In other words, if *bins* is `[1, 2, 3, 4]`, then the first bin is `[1, 2)` (including 1, but excluding 2) and the second `[2, 3)`. The last bin, however, is `[3, 4]`, which *includes* 4.

***binnumber*:** This returned argument assigns to each element of *sample* an integer that represents the bin in which it belongs. The representation depends on the *expand_binnumbers* argument. If `'False'` (default): The returned *binnumber* is a shape (N,) array of linearized indices mapping each element of *sample* to its corresponding bin (using row-major ordering). If `'True'`: The returned *binnumber* is a shape (2,N) ndarray where each row indicates bin placements for each dimension respectively. In each dimension, a *binnumber* of *i* means the corresponding value is between `(D_edge[i-1], D_edge[i])`, where `'D'` is either `'x'` or `'y'`.

New in version 0.11.0.

Examples

```
>>> from scipy import stats
```

Calculate the counts with explicit bin-edges:

```
>>> x = [0.1, 0.1, 0.1, 0.6]
>>> y = [2.1, 2.6, 2.1, 2.1]
>>> binx = [0.0, 0.5, 1.0]
>>> biny = [2.0, 2.5, 3.0]
>>> ret = stats.binned_statistic_2d(x, y, None, 'count', bins=[binx,
↳biny])
>>> ret.statistic
array([[2., 1.],
       [1., 0.]])
```

The bin in which each sample is placed is given by the *binnumber* returned parameter. By default, these are the linearized bin indices:

```
>>> ret.binnumber
array([5, 6, 5, 9])
```

The bin indices can also be expanded into separate entries for each dimension using the *expand_binnumbers* parameter:

```
>>> ret = stats.binned_statistic_2d(x, y, None, 'count', bins=[binx,
↳biny],
...                               expand_binnumbers=True)
>>> ret.binnumber
array([[1, 1, 1, 2],
       [1, 2, 1, 1]])
```

Which shows that the first three elements belong in the *xbin* 1, and the fourth into *xbin* 2; and so on for *y*.

scipy.stats.binned_statistic_dd

`scipy.stats.binned_statistic_dd`(*sample*, *values*, *statistic*='mean', *bins*=10, *range*=None, *expand_binnumbers*=False, *binned_statistic_result*=None)

Compute a multidimensional binned statistic for a set of data.

This is a generalization of a `histogramdd` function. A histogram divides the space into bins, and returns the count of the number of points in each bin. This function allows the computation of the sum, mean, median, or other statistic of the values within each bin.

Parameters

- sample** [array_like] Data to histogram passed as a sequence of N arrays of length D, or as an (N,D) array.
- values** [(N,) array_like or list of (N,) array_like] The data on which the statistic will be computed. This must be the same shape as *sample*, or a list of sequences - each with the same shape as *sample*. If *values* is such a list, the statistic will be computed on each independently.
- statistic** [string or callable, optional] The statistic to compute (default is 'mean'). The following statistics are available:
- 'mean': compute the mean of values for points within each bin. Empty bins will be represented by NaN.
 - 'median': compute the median of values for points within each bin. Empty bins will be represented by NaN.
 - 'count': compute the count of points within each bin. This is identical to an unweighted histogram. *values* array is not referenced.
 - 'sum': compute the sum of values for points within each bin. This is identical to a weighted histogram.
 - 'std': compute the standard deviation within each bin. This is implicitly calculated with `ddof=0`. If the number of values within a given bin is 0 or 1, the computed standard deviation value will be 0 for the bin.
 - 'min': compute the minimum of values for points within each bin. Empty bins will be represented by NaN.
 - 'max': compute the maximum of values for point within each bin. Empty bins will be represented by NaN.
 - function: a user-defined function which takes a 1D array of values, and outputs a single numerical statistic. This function will be called on the values in each bin. Empty bins will be represented by `function([])`, or NaN if this returns an error.
- bins** [sequence or positive int, optional] The bin specification must be in one of the following forms:
- A sequence of arrays describing the bin edges along each dimension.
 - The number of bins for each dimension (`nx, ny, ... = bins`).
 - The number of bins for all dimensions (`nx = ny = ... = bins`).
- range** [sequence, optional] A sequence of lower and upper bin edges to be used if the edges are not given explicitly in *bins*. Defaults to the minimum and maximum values along each dimension.
- expand_binnumbers** [bool, optional] 'False' (default): the returned *binnumber* is a shape (N,) array of linearized bin indices. 'True': the returned *binnumber* is 'unraveled' into a shape (D,N) ndarray, where each row gives the bin numbers in the corresponding dimension. See the *binnumber* returned value, and the *Examples* section of `binned_statistic_2d`.
- binned_statistic_result** [binnedStatisticddResult] Result of a previous call to the function in order to reuse bin edges and bin numbers with new values and/or a different statistic. To reuse bin numbers, *expand_binnumbers* must have been set to False (the default)
New in version 0.17.0.

Returns

statistic [ndarray, shape(nx1, nx2, nx3,...)] The values of the selected statistic in each two-dimensional bin.

bin_edges [list of ndarrays] A list of D arrays describing the $(n_x + 1)$ bin edges for each dimension.

binnumber [(N,) array of ints or (D,N) ndarray of ints] This assigns to each element of *sample* an integer that represents the bin in which this observation falls. The representation depends on the *expand_binnumbers* argument. See *Notes* for details.

See also:

numpy.digitize, *numpy.histogramdd*, *binned_statistic*, *binned_statistic_2d*

Notes

Binedges: All but the last (righthand-most) bin is half-open in each dimension. In other words, if *bins* is $[1, 2, 3, 4]$, then the first bin is $[1, 2)$ (including 1, but excluding 2) and the second $[2, 3)$. The last bin, however, is $[3, 4]$, which *includes* 4.

binnumber: This returned argument assigns to each element of *sample* an integer that represents the bin in which it belongs. The representation depends on the *expand_binnumbers* argument. If 'False' (default): The returned *binnumber* is a shape (N,) array of linearized indices mapping each element of *sample* to its corresponding bin (using row-major ordering). If 'True': The returned *binnumber* is a shape (D,N) ndarray where each row indicates bin placements for each dimension respectively. In each dimension, a binnumber of i means the corresponding value is between $(\text{bin_edges}[D][i-1], \text{bin_edges}[D][i])$, for each dimension 'D'.

New in version 0.11.0.

Examples

```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
>>> from mpl_toolkits.mplot3d import Axes3D
```

Take an array of 600 (x, y) coordinates as an example. *binned_statistic_dd* can handle arrays of higher dimension D . But a plot of dimension $D+1$ is required.

```
>>> mu = np.array([0., 1.])
>>> sigma = np.array([[1., -0.5], [-0.5, 1.5]])
>>> multinormal = stats.multivariate_normal(mu, sigma)
>>> data = multinormal.rvs(size=600, random_state=235412)
>>> data.shape
(600, 2)
```

Create bins and count how many arrays fall in each bin:

```
>>> N = 60
>>> x = np.linspace(-3, 3, N)
>>> y = np.linspace(-3, 4, N)
>>> ret = stats.binned_statistic_dd(data, np.arange(600), bins=[x, y],
...                               statistic='count')
>>> bincounts = ret.statistic
```

Set the volume and the location of bars:



```
>>> dx = x[1] - x[0]
>>> dy = y[1] - y[0]
>>> x, y = np.meshgrid(x[:-1]+dx/2, y[:-1]+dy/2)
>>> z = 0
```

```
>>> bincounts = bincounts.ravel()
>>> x = x.ravel()
>>> y = y.ravel()
```

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111, projection='3d')
>>> with np.errstate(divide='ignore'): # silence random axes3d warning
...     ax.bar3d(x, y, z, dx, dy, bincounts)
```

Reuse bin numbers and bin edges with new values:

```
>>> ret2 = stats.binned_statistic_dd(data, -np.arange(600),
...                                  binned_statistic_result=ret,
...                                  statistic='mean')
```



6.29.9 Correlation functions

<code>f_oneway(*args[, axis])</code>	Perform one-way ANOVA.
<code>pearsonr(x, y)</code>	Pearson correlation coefficient and p-value for testing non-correlation.
<code>spearmanr(a[, b, axis, nan_policy])</code>	Calculate a Spearman correlation coefficient with associated p-value.
<code>pointbiserialr(x, y)</code>	Calculate a point biserial correlation coefficient and its p-value.
<code>kendalltau(x, y[, initial_lexsort, ...])</code>	Calculate Kendall's tau, a correlation measure for ordinal data.

continues on next page

Table 264 – continued from previous page

<code>weightedtau(x, y[, rank, weigher, additive])</code>	Compute a weighted version of Kendall's τ .
<code>linregress(x[, y])</code>	Calculate a linear least-squares regression for two sets of measurements.
<code>siegelslopes(y[, x, method])</code>	Computes the Siegel estimator for a set of points (x, y).
<code>theilslopes(y[, x, alpha])</code>	Computes the Theil-Sen estimator for a set of points (x, y).
<code>multiscale_graphcorr(x, y[, ...])</code>	Computes the Multiscale Graph Correlation (MGC) test statistic.

scipy.stats.f_oneway

`scipy.stats.f_oneway(*args, axis=0)`

Perform one-way ANOVA.

The one-way ANOVA tests the null hypothesis that two or more groups have the same population mean. The test is applied to samples from two or more groups, possibly with differing sizes.

Parameters

sample1, sample2, ...

[array_like] The sample measurements for each group. There must be at least two arguments. If the arrays are multidimensional, then all the dimensions of the array must be the same except for *axis*.

axis [int, optional] Axis of the input arrays along which the test is applied. Default is 0.

Returns

statistic [float] The computed F statistic of the test.

pvalue [float] The associated p-value from the F distribution.

Warns

F_onewayConstantInputWarning

Raised if each of the input arrays is constant array. In this case the F statistic is either infinite or isn't defined, so `np.inf` or `np.nan` is returned.

F_onewayBadInputSizesWarning

Raised if the length of any input array is 0, or if all the input arrays have length 1. `np.nan` is returned for the F statistic and the p-value in these cases.

Notes

The ANOVA test has important assumptions that must be satisfied in order for the associated p-value to be valid.

1. The samples are independent.
2. Each sample is from a normally distributed population.
3. The population standard deviations of the groups are all equal. This property is known as homoscedasticity.

If these assumptions are not true for a given set of data, it may still be possible to use the Kruskal-Wallis H-test (`scipy.stats.kruskal`) although with some loss of power.

The length of each group must be at least one, and there must be at least one group with length greater than one. If these conditions are not satisfied, a warning is generated and `(np.nan, np.nan)` is returned.

If each group contains constant values, and there exist at least two groups with different values, the function generates a warning and returns `(np.inf, 0)`.

If all values in all groups are the same, function generates a warning and returns `(np.nan, np.nan)`.

The algorithm is from Heiman [2], pp.394-7.

References

[1], [2], [3]

Examples

```
>>> from scipy.stats import f_oneway
```

Here are some data [3] on a shell measurement (the length of the anterior adductor muscle scar, standardized by dividing by length) in the mussel *Mytilus trossulus* from five locations: Tillamook, Oregon; Newport, Oregon; Petersburg, Alaska; Magadan, Russia; and Tvarminne, Finland, taken from a much larger data set used in McDonald et al. (1991).

```
>>> tillamook = [0.0571, 0.0813, 0.0831, 0.0976, 0.0817, 0.0859, 0.0735,
...             0.0659, 0.0923, 0.0836]
>>> newport = [0.0873, 0.0662, 0.0672, 0.0819, 0.0749, 0.0649, 0.0835,
...            0.0725]
>>> petersburg = [0.0974, 0.1352, 0.0817, 0.1016, 0.0968, 0.1064, 0.105]
>>> magadan = [0.1033, 0.0915, 0.0781, 0.0685, 0.0677, 0.0697, 0.0764,
...            0.0689]
>>> tvarminne = [0.0703, 0.1026, 0.0956, 0.0973, 0.1039, 0.1045]
>>> f_oneway(tillamook, newport, petersburg, magadan, tvarminne)
F_onewayResult(statistic=7.121019471642447, pvalue=0.0002812242314534544)
```

`f_oneway` accepts multidimensional input arrays. When the inputs are multidimensional and *axis* is not given, the test is performed along the first axis of the input arrays. For the following data, the test is performed three times, once for each column.

```
>>> a = np.array([[9.87, 9.03, 6.81],
...              [7.18, 8.35, 7.00],
...              [8.39, 7.58, 7.68],
...              [7.45, 6.33, 9.35],
...              [6.41, 7.10, 9.33],
...              [8.00, 8.24, 8.44]])
>>> b = np.array([[6.35, 7.30, 7.16],
...              [6.65, 6.68, 7.63],
...              [5.72, 7.73, 6.72],
...              [7.01, 9.19, 7.41],
...              [7.75, 7.87, 8.30],
...              [6.90, 7.97, 6.97]])
>>> c = np.array([[3.31, 8.77, 1.01],
...              [8.25, 3.24, 3.62],
...              [6.32, 8.81, 5.19],
...              [7.48, 8.83, 8.91],
...              [8.59, 6.01, 6.07],
...              [3.07, 9.72, 7.48]])
>>> F, p = f_oneway(a, b, c)
>>> F
```

(continues on next page)

(continued from previous page)

```
array([1.75676344, 0.03701228, 3.76439349])
>>> p
array([0.20630784, 0.96375203, 0.04733157])
```

scipy.stats.pearsonr

`scipy.stats.pearsonr(x, y)`

Pearson correlation coefficient and p-value for testing non-correlation.

The Pearson correlation coefficient [1] measures the linear relationship between two datasets. The calculation of the p-value relies on the assumption that each dataset is normally distributed. (See Kowalski [3] for a discussion of the effects of non-normality of the input on the distribution of the correlation coefficient.) Like other correlation coefficients, this one varies between -1 and +1 with 0 implying no correlation. Correlations of -1 or +1 imply an exact linear relationship. Positive correlations imply that as x increases, so does y . Negative correlations imply that as x increases, y decreases.

The p-value roughly indicates the probability of an uncorrelated system producing datasets that have a Pearson correlation at least as extreme as the one computed from these datasets.

Parameters

x [(N,) array_like] Input array.
y [(N,) array_like] Input array.

Returns

r [float] Pearson's correlation coefficient.
p-value [float] Two-tailed p-value.

Warns

PearsonRConstantInputWarning

Raised if an input is a constant array. The correlation coefficient is not defined in this case, so `np.nan` is returned.

PearsonRNearConstantInputWarning

Raised if an input is “nearly” constant. The array x is considered nearly constant if $\text{norm}(x - \text{mean}(x)) < 1e-13 * \text{abs}(\text{mean}(x))$. Numerical errors in the calculation $x - \text{mean}(x)$ in this case might result in an inaccurate calculation of r .

See also:

spearmanr

Spearman rank-order correlation coefficient.

kendalltau

Kendall's tau, a correlation measure for ordinal data.

Notes

The correlation coefficient is calculated as follows:

$$r = \frac{\sum(x - m_x)(y - m_y)}{\sqrt{\sum(x - m_x)^2 \sum(y - m_y)^2}}$$

where m_x is the mean of the vector x and m_y is the mean of the vector y .

Under the assumption that x and m_y are drawn from independent normal distributions (so the population correlation coefficient is 0), the probability density function of the sample correlation coefficient r is ([1], [2]):

$$f(r) = \frac{(1 - r^2)^{n/2-2}}{B(\frac{1}{2}, \frac{n}{2} - 1)}$$

where n is the number of samples, and B is the beta function. This is sometimes referred to as the exact distribution of r . This is the distribution that is used in `pearsonr` to compute the p-value. The distribution is a beta distribution on the interval $[-1, 1]$, with equal shape parameters $a = b = n/2 - 1$. In terms of SciPy's implementation of the beta distribution, the distribution of r is:

```
dist = scipy.stats.beta(n/2 - 1, n/2 - 1, loc=-1, scale=2)
```

The p-value returned by `pearsonr` is a two-sided p-value. For a given sample with correlation coefficient r , the p-value is the probability that $\text{abs}(r')$ of a random sample x' and y' drawn from the population with zero correlation would be greater than or equal to $\text{abs}(r)$. In terms of the object `dist` shown above, the p-value for a given r and length n can be computed as:

```
p = 2*dist.cdf(-abs(r))
```

When n is 2, the above continuous distribution is not well-defined. One can interpret the limit of the beta distribution as the shape parameters a and b approach $a = b = 0$ as a discrete distribution with equal probability masses at $r = 1$ and $r = -1$. More directly, one can observe that, given the data $x = [x_1, x_2]$ and $y = [y_1, y_2]$, and assuming $x_1 \neq x_2$ and $y_1 \neq y_2$, the only possible values for r are 1 and -1. Because $\text{abs}(r')$ for any sample x' and y' with length 2 will be 1, the two-sided p-value for a sample of length 2 is always 1.

References

[1], [2], [3]

Examples

```
>>> from scipy import stats
>>> a = np.array([0, 0, 0, 1, 1, 1, 1])
>>> b = np.arange(7)
>>> stats.pearsonr(a, b)
(0.8660254037844386, 0.011724811003954649)
```

```
>>> stats.pearsonr([1, 2, 3, 4, 5], [10, 9, 2.5, 6, 4])
(-0.7426106572325057, 0.1505558088534455)
```

scipy.stats.spearmanr

`scipy.stats.spearmanr` (*a*, *b=None*, *axis=0*, *nan_policy='propagate'*)

Calculate a Spearman correlation coefficient with associated p-value.

The Spearman rank-order correlation coefficient is a nonparametric measure of the monotonicity of the relationship between two datasets. Unlike the Pearson correlation, the Spearman correlation does not assume that both datasets are normally distributed. Like other correlation coefficients, this one varies between -1 and +1 with 0 implying no correlation. Correlations of -1 or +1 imply an exact monotonic relationship. Positive correlations imply that as *x* increases, so does *y*. Negative correlations imply that as *x* increases, *y* decreases.

The p-value roughly indicates the probability of an uncorrelated system producing datasets that have a Spearman correlation at least as extreme as the one computed from these datasets. The p-values are not entirely reliable but are probably reasonable for datasets larger than 500 or so.

Parameters

- a, b** [1D or 2D array_like, *b* is optional] One or two 1-D or 2-D arrays containing multiple variables and observations. When these are 1-D, each represents a vector of observations of a single variable. For the behavior in the 2-D case, see under `axis`, below. Both arrays need to have the same length in the `axis` dimension.
- axis** [int or None, optional] If `axis=0` (default), then each column represents a variable, with observations in the rows. If `axis=1`, the relationship is transposed: each row represents a variable, while the columns contain observations. If `axis=None`, then both arrays will be raveled.
- nan_policy** [{'propagate', 'raise', 'omit'}, optional] Defines how to handle when input contains nan. The following options are available (default is 'propagate'):
- 'propagate': returns nan
 - 'raise': throws an error
 - 'omit': performs the calculations ignoring nan values

Returns

- correlation** [float or ndarray (2-D square)] Spearman correlation matrix or correlation coefficient (if only 2 variables are given as parameters. Correlation matrix is square with length equal to total number of variables (columns or rows) in *a* and *b* combined.
- pvalue** [float] The two-sided p-value for a hypothesis test whose null hypothesis is that two sets of data are uncorrelated, has same dimension as rho.

References

[1]

Examples

```
>>> from scipy import stats
>>> stats.spearmanr([1,2,3,4,5], [5,6,7,8,7])
(0.82078268166812329, 0.088587005313543798)
>>> np.random.seed(1234321)
>>> x2n = np.random.randn(100, 2)
>>> y2n = np.random.randn(100, 2)
>>> stats.spearmanr(x2n)
```

(continues on next page)

(continued from previous page)

```

(0.059969996999699973, 0.55338590803773591)
>>> stats.spearmanr(x2n[:,0], x2n[:,1])
(0.059969996999699973, 0.55338590803773591)
>>> rho, pval = stats.spearmanr(x2n, y2n)
>>> rho
array([[ 1.          ,  0.05997   ,  0.18569457,  0.06258626],
       [ 0.05997   ,  1.          ,  0.110003  ,  0.02534653],
       [ 0.18569457,  0.110003  ,  1.          ,  0.03488749],
       [ 0.06258626,  0.02534653,  0.03488749,  1.          ]])
>>> pval
array([[ 0.          ,  0.55338591,  0.06435364,  0.53617935],
       [ 0.55338591,  0.          ,  0.27592895,  0.80234077],
       [ 0.06435364,  0.27592895,  0.          ,  0.73039992],
       [ 0.53617935,  0.80234077,  0.73039992,  0.          ]])
>>> rho, pval = stats.spearmanr(x2n.T, y2n.T, axis=1)
>>> rho
array([[ 1.          ,  0.05997   ,  0.18569457,  0.06258626],
       [ 0.05997   ,  1.          ,  0.110003  ,  0.02534653],
       [ 0.18569457,  0.110003  ,  1.          ,  0.03488749],
       [ 0.06258626,  0.02534653,  0.03488749,  1.          ]])
>>> stats.spearmanr(x2n, y2n, axis=None)
(0.10816770419260482, 0.1273562188027364)
>>> stats.spearmanr(x2n.ravel(), y2n.ravel())
(0.10816770419260482, 0.1273562188027364)

```

```

>>> xint = np.random.randint(10, size=(100, 2))
>>> stats.spearmanr(xint)
(0.052760927029710199, 0.60213045837062351)

```

scipy.stats.pointbiserialr

`scipy.stats.pointbiserialr(x, y)`

Calculate a point biserial correlation coefficient and its p-value.

The point biserial correlation is used to measure the relationship between a binary variable, *x*, and a continuous variable, *y*. Like other correlation coefficients, this one varies between -1 and +1 with 0 implying no correlation. Correlations of -1 or +1 imply a determinative relationship.

This function uses a shortcut formula but produces the same result as *pearsonr*.

Parameters

x [array_like of bools] Input array.
y [array_like] Input array.

Returns

correlation [float] R value.
pvalue [float] Two-sided p-value.

Notes

`pointbiserialr` uses a t-test with $n-1$ degrees of freedom. It is equivalent to `pearsonr`.

The value of the point-biserial correlation can be calculated from:

$$r_{pb} = \frac{\bar{Y}_1 - \bar{Y}_0}{s_y} \sqrt{\frac{N_1 N_2}{N(N-1)}}$$

Where Y_0 and Y_1 are means of the metric observations coded 0 and 1 respectively; N_0 and N_1 are number of observations coded 0 and 1 respectively; N is the total number of observations and s_y is the standard deviation of all the metric observations.

A value of r_{pb} that is significantly different from zero is completely equivalent to a significant difference in means between the two groups. Thus, an independent groups t Test with $N - 2$ degrees of freedom may be used to test whether r_{pb} is nonzero. The relation between the t-statistic for comparing two independent groups and r_{pb} is given by:

$$t = \sqrt{N-2} \frac{r_{pb}}{\sqrt{1-r_{pb}^2}}$$

References

[1], [2], [3]

Examples

```
>>> from scipy import stats
>>> a = np.array([0, 0, 0, 1, 1, 1, 1])
>>> b = np.arange(7)
>>> stats.pointbiserialr(a, b)
(0.8660254037844386, 0.011724811003954652)
>>> stats.pearsonr(a, b)
(0.86602540378443871, 0.011724811003954626)
>>> np.corrcoef(a, b)
array([[ 1.          ,  0.8660254 ],
       [ 0.8660254 ,  1.          ]])
```

scipy.stats.kendalltau

`scipy.stats.kendalltau`(*x*, *y*, *initial_lexsort=None*, *nan_policy='propagate'*, *method='auto'*, *variant='b'*)

Calculate Kendall's tau, a correlation measure for ordinal data.

Kendall's tau is a measure of the correspondence between two rankings. Values close to 1 indicate strong agreement, and values close to -1 indicate strong disagreement. This implements two variants of Kendall's tau: tau-b (the default) and tau-c (also known as Stuart's tau-c). These differ only in how they are normalized to lie within the range -1 to 1; the hypothesis tests (their p-values) are identical. Kendall's original tau-a is not implemented separately because both tau-b and tau-c reduce to tau-a in the absence of ties.

Parameters

x, y [array_like] Arrays of rankings, of the same shape. If arrays are not 1-D, they will be flattened to 1-D.

initial_lexsort

[bool, optional] Unused (deprecated).

nan_policy

[{'propagate', 'raise', 'omit'}, optional] Defines how to handle when input contains nan. The following options are available (default is 'propagate'):

- 'propagate': returns nan
- 'raise': throws an error
- 'omit': performs the calculations ignoring nan values

method

[{'auto', 'asymptotic', 'exact'}, optional] Defines which method is used to calculate the p-value [5]. The following options are available (default is 'auto'):

- 'auto': selects the appropriate method based on a trade-off between speed and accuracy
- 'asymptotic': uses a normal approximation valid for large samples
- 'exact': computes the exact p-value, but can only be used if no ties are present. As the sample size increases, the 'exact' computation time may grow and the result may lose some precision.

variant: {'b', 'c'}, optional

Defines which variant of Kendall's tau is returned. Default is 'b'.

Returns**correlation**

[float] The tau statistic.

pvalue[float] The two-sided p-value for a hypothesis test whose null hypothesis is an absence of association, $\tau = 0$.**See also:***spearmanr*

Calculates a Spearman rank-order correlation coefficient.

theilslopes

Computes the Theil-Sen estimator for a set of points (x, y).

weightedtau

Computes a weighted version of Kendall's tau.

Notes

The definition of Kendall's tau that is used is [2]:

$$\text{tau}_b = (P - Q) / \text{sqrt}((P + Q + T) * (P + Q + U))$$

$$\text{tau}_c = 2 (P - Q) / (n**2 * (m - 1) / m)$$

where P is the number of concordant pairs, Q the number of discordant pairs, T the number of ties only in x, and U the number of ties only in y. If a tie occurs for the same pair in both x and y, it is not added to either T or U. n is the total number of samples, and m is the number of unique values in either x or y, whichever is smaller.

References

[1], [2], [3], [4], [5]

Examples

```
>>> from scipy import stats
>>> x1 = [12, 2, 1, 12, 2]
>>> x2 = [1, 4, 7, 1, 0]
>>> tau, p_value = stats.kendalltau(x1, x2)
>>> tau
-0.47140452079103173
>>> p_value
0.2827454599327748
```

scipy.stats.weightedtau

`scipy.stats.weightedtau` (*x*, *y*, *rank=True*, *weigher=None*, *additive=True*)

Compute a weighted version of Kendall's τ .

The weighted τ is a weighted version of Kendall's τ in which exchanges of high weight are more influential than exchanges of low weight. The default parameters compute the additive hyperbolic version of the index, τ_h , which has been shown to provide the best balance between important and unimportant elements [1].

The weighting is defined by means of a rank array, which assigns a nonnegative rank to each element, and a weigher function, which assigns a weight based from the rank to each element. The weight of an exchange is then the sum or the product of the weights of the ranks of the exchanged elements. The default parameters compute τ_h : an exchange between elements with rank r and s (starting from zero) has weight $1/(r + 1) + 1/(s + 1)$.

Specifying a rank array is meaningful only if you have in mind an external criterion of importance. If, as it usually happens, you do not have in mind a specific rank, the weighted τ is defined by averaging the values obtained using the decreasing lexicographical rank by (x, y) and by (y, x) . This is the behavior with default parameters.

Note that if you are computing the weighted τ on arrays of ranks, rather than of scores (i.e., a larger value implies a lower rank) you must negate the ranks, so that elements of higher rank are associated with a larger value.

Parameters

x, y	[array_like] Arrays of scores, of the same shape. If arrays are not 1-D, they will be flattened to 1-D.
rank	[array_like of ints or bool, optional] A nonnegative rank assigned to each element. If it is <code>None</code> , the decreasing lexicographical rank by (x, y) will be used: elements of higher rank will be those with larger x -values, using y -values to break ties (in particular, swapping x and y will give a different result). If it is <code>False</code> , the element indices will be used directly as ranks. The default is <code>True</code> , in which case this function returns the average of the values obtained using the decreasing lexicographical rank by (x, y) and by (y, x) .
weigher	[callable, optional] The weigher function. Must map nonnegative integers (zero representing the most important element) to a nonnegative weight. The default, <code>None</code> , provides hyperbolic weighing, that is, rank r is mapped to weight $1/(r + 1)$.
additive	[bool, optional] If <code>True</code> , the weight of an exchange is computed by adding the weights of the ranks of the exchanged elements; otherwise, the weights are multiplied. The default is <code>True</code> .

Returns

correlation	[float] The weighted τ correlation index.
--------------------	--

pvalue [float] Presently `np.nan`, as the null statistics is unknown (even in the additive hyperbolic case).

See also:

kendalltau

Calculates Kendall's tau.

spearmanr

Calculates a Spearman rank-order correlation coefficient.

theilslopes

Computes the Theil-Sen estimator for a set of points (x, y).

Notes

This function uses an $O(n \log n)$, mergesort-based algorithm [1] that is a weighted extension of Knight's algorithm for Kendall's τ [2]. It can compute Shieh's weighted τ [3] between rankings without ties (i.e., permutations) by setting *additive* and *rank* to `False`, as the definition given in [1] is a generalization of Shieh's.

NaNs are considered the smallest possible score.

New in version 0.19.0.

References

[1], [2], [3]

Examples

```
>>> from scipy import stats
>>> x = [12, 2, 1, 12, 2]
>>> y = [1, 4, 7, 1, 0]
>>> tau, p_value = stats.weightedtau(x, y)
>>> tau
-0.56694968153682723
>>> p_value
nan
>>> tau, p_value = stats.weightedtau(x, y, additive=False)
>>> tau
-0.62205716951801038
```

NaNs are considered the smallest possible score:

```
>>> x = [12, 2, 1, 12, 2]
>>> y = [1, 4, 7, 1, np.nan]
>>> tau, _ = stats.weightedtau(x, y)
>>> tau
-0.56694968153682723
```

This is exactly Kendall's tau:

```
>>> x = [12, 2, 1, 12, 2]
>>> y = [1, 4, 7, 1, 0]
>>> tau, _ = stats.weightedtau(x, y, weigher=lambda x: 1)
>>> tau
-0.47140452079103173
```

```
>>> x = [12, 2, 1, 12, 2]
>>> y = [1, 4, 7, 1, 0]
>>> stats.weightedtau(x, y, rank=None)
WeightedTauResult(correlation=-0.4157652301037516, pvalue=nan)
>>> stats.weightedtau(y, x, rank=None)
WeightedTauResult(correlation=-0.7181341329699028, pvalue=nan)
```

scipy.stats.linregress

`scipy.stats.linregress(x, y=None)`

Calculate a linear least-squares regression for two sets of measurements.

Parameters

x, y [array_like] Two sets of measurements. Both arrays should have the same length. If only *x* is given (and *y=None*), then it must be a two-dimensional array where one dimension has length 2. The two sets of measurements are then found by splitting the array along the length-2 dimension. In the case where *y=None* and *x* is a 2x2 array, `linregress(x)` is equivalent to `linregress(x[0], x[1])`.

Returns

result [LinregressResult instance] The return value is an object with the following attributes:

- slope** [float] Slope of the regression line.
- intercept** [float] Intercept of the regression line.
- rvalue** [float] Correlation coefficient.
- pvalue** [float] Two-sided p-value for a hypothesis test whose null hypothesis is that the slope is zero, using Wald Test with t-distribution of the test statistic.
- stderr** [float] Standard error of the estimated slope (gradient), under the assumption of residual normality.
- intercept_stderr** [float] Standard error of the estimated intercept, under the assumption of residual normality.

See also:

[`scipy.optimize.curve_fit`](#)

Use non-linear least squares to fit a function to data.

[`scipy.optimize.leastsq`](#)

Minimize the sum of squares of a set of equations.

Notes

Missing values are considered pair-wise: if a value is missing in x , the corresponding value in y is masked.

For compatibility with older versions of SciPy, the return value acts like a `namedtuple` of length 5, with fields `slope`, `intercept`, `rvalue`, `pvalue` and `stderr`, so one can continue to write:

```
slope, intercept, r, p, se = linregress(x, y)
```

With that style, however, the standard error of the intercept is not available. To have access to all the computed values, including the standard error of the intercept, use the return value as an object with attributes, e.g.:

```
result = linregress(x, y)
print(result.intercept, result.intercept_stderr)
```

Examples

```
>>> import matplotlib.pyplot as plt
>>> from scipy import stats
```

Generate some data:

```
>>> np.random.seed(12345678)
>>> x = np.random.random(10)
>>> y = 1.6*x + np.random.random(10)
```

Perform the linear regression:

```
>>> res = stats.linregress(x, y)
```

Coefficient of determination (R-squared):

```
>>> print(f"R-squared: {res.rvalue**2:.6f}")
R-squared: 0.735498
```

Plot the data along with the fitted line:


```
>>> plt.plot(x, y, 'o', label='original data')
>>> plt.plot(x, res.intercept + res.slope*x, 'r', label='fitted line')
>>> plt.legend()
>>> plt.show()
```

Calculate 95% confidence interval on slope and intercept:

```
>>> # Two-sided inverse Students t-distribution
>>> # p - probability, df - degrees of freedom
>>> from scipy.stats import t
>>> tinv = lambda p, df: abs(t.ppf(p/2, df))
```

```
>>> ts = tinv(0.05, len(x)-2)
>>> print(f"slope (95%): {res.slope:.6f} +/- {ts*res.stderr:.6f}")
slope (95%): 1.944864 +/- 0.950885
>>> print(f"intercept (95%): {res.intercept:.6f}")
```

(continues on next page)



(continued from previous page)

```
...         f" +/- {ts*res.intercept_stderr:.6f}")
intercept (95%): 0.268578 +/- 0.488822
```

scipy.stats.siegelslopes

`scipy.stats.siegelslopes` (*y*, *x=None*, *method='hierarchical'*)

Computes the Siegel estimator for a set of points (*x*, *y*).

`siegelslopes` implements a method for robust linear regression using repeated medians (see [1]) to fit a line to the points (*x*, *y*). The method is robust to outliers with an asymptotic breakdown point of 50%.

Parameters

- y** [array_like] Dependent variable.
- x** [array_like or None, optional] Independent variable. If None, use `arange(len(y))` instead.
- method** [{"hierarchical", "separate"}] If 'hierarchical', estimate the intercept using the estimated slope `medslope` (default option). If 'separate', estimate the intercept independent of the estimated slope. See Notes for details.

Returns

- medslope** [float] Estimate of the slope of the regression line.
- medintercept** [float] Estimate of the intercept of the regression line.

See also:

`theilslopes`

a similar technique without repeated medians

Notes

With $n = \text{len}(y)$, compute m_j as the median of the slopes from the point $(x[j], y[j])$ to all other $n-1$ points. `medslope` is then the median of all slopes m_j . Two ways are given to estimate the intercept in [1] which can be chosen via the parameter `method`. The hierarchical approach uses the estimated slope `medslope` and computes `medintercept` as the median of $y - \text{medslope} * x$. The other approach estimates the intercept separately as follows: for each point $(x[j], y[j])$, compute the intercepts of all the $n-1$ lines through the remaining points and take the median i_j . `medintercept` is the median of the i_j .

The implementation computes n times the median of a vector of size n which can be slow for large vectors. There are more efficient algorithms (see [2]) which are not implemented here.

References

[1], [2]

Examples

```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
```

```
>>> x = np.linspace(-5, 5, num=150)
>>> y = x + np.random.normal(size=x.size)
>>> y[11:15] += 10 # add outliers
>>> y[-5:] -= 7
```

Compute the slope and intercept. For comparison, also compute the least-squares fit with `linregress`:

```
>>> res = stats.siegelslopes(y, x)
>>> lsq_res = stats.linregress(x, y)
```

Plot the results. The Siegel regression line is shown in red. The green line shows the least-squares fit for comparison.

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> ax.plot(x, y, 'b.')
>>> ax.plot(x, res[1] + res[0] * x, 'r-')
>>> ax.plot(x, lsq_res[1] + lsq_res[0] * x, 'g-')
>>> plt.show()
```

scipy.stats.theilslopes


`scipy.stats.theilslopes` ($y, x=None, \text{alpha}=0.95$)

Computes the Theil-Sen estimator for a set of points (x, y) .

`theilslopes` implements a method for robust linear regression. It computes the slope as the median of all slopes between paired values.

Parameters

y	[array_like] Dependent variable.
x	[array_like or None, optional] Independent variable. If None, use <code>arange(len(y))</code> instead.



alpha [float, optional] Confidence degree between 0 and 1. Default is 95% confidence. Note that *alpha* is symmetric around 0.5, i.e. both 0.1 and 0.9 are interpreted as “find the 90% confidence interval”.

Returns

medslope [float] Theil slope.

medintercept

[float] Intercept of the Theil line, as $\text{median}(y) - \text{medslope} * \text{median}(x)$.

lo_slope [float] Lower bound of the confidence interval on *medslope*.

up_slope [float] Upper bound of the confidence interval on *medslope*.

See also:

siegelslopes

a similar technique using repeated medians

Notes

The implementation of *theilslopes* follows [1]. The intercept is not defined in [1], and here it is defined as $\text{median}(y) - \text{medslope} * \text{median}(x)$, which is given in [3]. Other definitions of the intercept exist in the literature. A confidence interval for the intercept is not given as this question is not addressed in [1].

References

[1], [2], [3]

Examples

```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
```


```
>>> x = np.linspace(-5, 5, num=150)
>>> y = x + np.random.normal(size=x.size)
>>> y[11:15] += 10 # add outliers
>>> y[-5:] -= 7
```

Compute the slope, intercept and 90% confidence interval. For comparison, also compute the least-squares fit with `linregress`:

```
>>> res = stats.theilslopes(y, x, 0.90)
>>> lsq_res = stats.linregress(x, y)
```

Plot the results. The Theil-Sen regression line is shown in red, with the dashed red lines illustrating the confidence interval of the slope (note that the dashed red lines are not the confidence interval of the regression as the confidence interval of the intercept is not included). The green line shows the least-squares fit for comparison.

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> ax.plot(x, y, 'b.')
>>> ax.plot(x, res[1] + res[0] * x, 'r-')
>>> ax.plot(x, res[1] + res[2] * x, 'r--')
>>> ax.plot(x, res[1] + res[3] * x, 'r--')
>>> ax.plot(x, lsq_res[1] + lsq_res[0] * x, 'g-')
>>> plt.show()
```



scipy.stats.multiscale_graphcorr

```
scipy.stats.multiscale_graphcorr(x, y, compute_distance=<function _euclidean_dist at
                                0x7f8935644af0>, reps=1000, workers=1, is_twosamp=False,
                                random_state=None)
```

Computes the Multiscale Graph Correlation (MGC) test statistic.

Specifically, for each point, MGC finds the k -nearest neighbors for one property (e.g. cloud density), and the l -nearest neighbors for the other property (e.g. grass wetness) [1]. This pair (k, l) is called the “scale”. A priori, however, it is not known which scales will be most informative. So, MGC computes all distance pairs, and then efficiently computes the distance correlations for all scales. The local correlations illustrate which scales are relatively informative about the relationship. The key, therefore, to successfully discover and decipher relationships between disparate data modalities is to adaptively determine which scales are the most informative, and the geometric implication for the most informative scales. Doing so not only provides an estimate of whether the modalities are related, but also provides insight into how the determination was made. This is especially important in high-dimensional data, where simple visualizations do not reveal relationships to the unaided human eye. Characterizations of this implementation in particular have been derived from and benchmarked within in [2].

Parameters

x, y [ndarray] If x and y have shapes (n, p) and (n, q) where n is the number of samples and p and q are the number of dimensions, then the MGC independence test will be run. Alternatively, x and y can have shapes (n, n) if they are distance or similarity matrices, and `compute_distance` must be sent to `None`. If x and y have shapes (n, p) and (m, p) , an unpaired two-sample MGC test will be run.

compute_distance

[callable, optional] A function that computes the distance or similarity among the samples within each data matrix. Set to `None` if x and y are already distance matrices. The default uses the euclidean norm metric. If you are calling a custom function, either create the distance matrix before-hand or create a function of the form `compute_distance(x)` where x is the data matrix for which pairwise distances are calculated.

reps [int, optional] The number of replications used to estimate the null when using the permutation test. The default is 1000.

workers [int or map-like callable, optional] If `workers` is an int the population is subdivided into `workers` sections and evaluated in parallel (uses `multiprocessing.Pool` `<multiprocessing>`). Supply `-1` to use all cores available to the Process. Alternatively supply a map-like callable, such as `multiprocessing.Pool.map` for evaluating the p-value in parallel. This evaluation is carried out as `workers(func, iterable)`. Requires that `func` be pickleable. The default is 1.

is_twosamp

[bool, optional] If `True`, a two sample test will be run. If x and y have shapes (n, p) and (m, p) , this optional will be overridden and set to `True`. Set to `True` if x and y both have shapes (n, p) and a two sample test is desired. The default is `False`. Note that this will not run if inputs are distance matrices.

random_state

[int or `np.random.RandomState` instance, optional] If already a `RandomState` instance, use it. If seed is an int, return a new `RandomState` instance seeded with seed. If `None`, use `np.random.RandomState`. Default is `None`.

Returns

stat [float] The sample MGC test statistic within $[-1, 1]$.

pvalue [float] The p-value obtained via permutation.

mgc_dict [dict] Contains additional useful additional returns containing the following keys:

- **mgc_map** [ndarray] A 2D representation of the latent geometry of the relationship. of the relationship.
- **opt_scale** [(int, int)] The estimated optimal scale as a (x, y) pair.

- **null_dist** [list] The null distribution derived from the permuted matrices

See also:

pearsonr

Pearson correlation coefficient and p-value for testing non-correlation.

kendalltau

Calculates Kendall's tau.

spearmanr

Calculates a Spearman rank-order correlation coefficient.

Notes

A description of the process of MGC and applications on neuroscience data can be found in [1]. It is performed using the following steps:

1. Two distance matrices D^X and D^Y are computed and modified to be mean zero columnwise. This results in two $n \times n$ distance matrices A and B (the centering and unbiased modification) [3].
2. For all values k and l from $1, \dots, n$,
 - The k -nearest neighbor and l -nearest neighbor graphs are calculated for each property. Here, $G_k(i, j)$ indicates the k -smallest values of the i -th row of A and $H_l(i, j)$ indicates the l smallest values of the i -th row of B
 - Let \circ denotes the entry-wise matrix product, then local correlations are summed and normalized using the following statistic:

$$c^{kl} = \frac{\sum_{ij} AG_k BH_l}{\sqrt{\sum_{ij} A^2 G_k \times \sum_{ij} B^2 H_l}}$$

1. The MGC test statistic is the smoothed optimal local correlation of $\{c^{kl}\}$. Denote the smoothing operation as $R(\cdot)$ (which essentially set all isolated large correlations) as 0 and connected large correlations the same as before, see [3].) MGC is,

$$MGC_n(x, y) = \max_{(k,l)} R(c^{kl}(x_n, y_n))$$

The test statistic returns a value between $(-1, 1)$ since it is normalized.

The p-value returned is calculated using a permutation test. This process is completed by first randomly permuting y to estimate the null distribution and then calculating the probability of observing a test statistic, under the null, at least as extreme as the observed test statistic.

MGC requires at least 5 samples to run with reliable results. It can also handle high-dimensional data sets. In addition, by manipulating the input data matrices, the two-sample testing problem can be reduced to the independence testing problem [4]. Given sample data U and V of sizes $p \times n$ and $p \times m$, data matrix X and Y can be created as follows:

$$X = [U|V] \in \mathcal{R}^{p \times (n+m)} \quad Y = [0_{1 \times n} | 1_{1 \times m}] \in \mathcal{R}^{(n+m)}$$

Then, the MGC statistic can be calculated as normal. This methodology can be extended to similar tests such as distance correlation [4].

New in version 1.4.0.

References

[1], [2], [3], [4]

Examples

```
>>> from scipy.stats import multiscale_graphcorr
>>> x = np.arange(100)
>>> y = x
>>> stat, pvalue, _ = multiscale_graphcorr(x, y, workers=-1)
>>> '%.1f, %.3f' % (stat, pvalue)
'1.0, 0.001'
```

Alternatively,

```
>>> x = np.arange(100)
>>> y = x
>>> mgc = multiscale_graphcorr(x, y)
>>> '%.1f, %.3f' % (mgc.stat, mgc.pvalue)
'1.0, 0.001'
```

To run an unpaired two-sample test,

```
>>> x = np.arange(100)
>>> y = np.arange(79)
>>> mgc = multiscale_graphcorr(x, y, random_state=1)
>>> '%.3f, %.2f' % (mgc.stat, mgc.pvalue)
'0.033, 0.02'
```

or, if shape of the inputs are the same,

```
>>> x = np.arange(100)
>>> y = x
>>> mgc = multiscale_graphcorr(x, y, is_twosamp=True)
>>> '%.3f, %.1f' % (mgc.stat, mgc.pvalue)
'-0.008, 1.0'
```

6.29.10 Statistical tests

<code>ttest_1samp(a, popmean[, axis, nan_policy, ...])</code>	Calculate the T-test for the mean of ONE group of scores.
<code>ttest_ind(a, b[, axis, equal_var, ...])</code>	Calculate the T-test for the means of <i>two independent</i> samples of scores.
<code>ttest_ind_from_stats(mean1, std1, nobs1, ...)</code>	T-test for means of two independent samples from descriptive statistics.
<code>ttest_rel(a, b[, axis, nan_policy, alternative])</code>	Calculate the t-test on TWO RELATED samples of scores, a and b.
<code>chisquare(f_obs[, f_exp, ddof, axis])</code>	Calculate a one-way chi-square test.
<code>cramervonmises(rvs, cdf[, args])</code>	Perform the Cramér-von Mises test for goodness of fit.
<code>power_divergence(f_obs[, f_exp, ddof, axis, ...])</code>	Cressie-Read power divergence statistic and goodness of fit test.

continues on next page

Table 265 – continued from previous page

<code>kstest(rvs, cdf[, args, N, alternative, mode])</code>	Performs the (one sample or two samples) Kolmogorov-Smirnov test for goodness of fit.
<code>ks_1samp(x, cdf[, args, alternative, mode])</code>	Performs the Kolmogorov-Smirnov test for goodness of fit.
<code>ks_2samp(data1, data2[, alternative, mode])</code>	Compute the Kolmogorov-Smirnov statistic on 2 samples.
<code>epps_singleton_2samp(x, y[, t])</code>	Compute the Epps-Singleton (ES) test statistic.
<code>mannwhitneyu(x, y[, use_continuity, alternative])</code>	Compute the Mann-Whitney rank test on samples <i>x</i> and <i>y</i> .
<code>tiecorrect(rankvals)</code>	Tie correction factor for Mann-Whitney U and Kruskal-Wallis H tests.
<code>rankdata(a[, method, axis])</code>	Assign ranks to data, dealing with ties appropriately.
<code>ranksums(x, y)</code>	Compute the Wilcoxon rank-sum statistic for two samples.
<code>wilcoxon(x[, y, zero_method, correction, ...])</code>	Calculate the Wilcoxon signed-rank test.
<code>kruskal(*args[, nan_policy])</code>	Compute the Kruskal-Wallis H-test for independent samples.
<code>friedmanchisquare(*args)</code>	Compute the Friedman test for repeated measurements.
<code>brunnermunzel(x, y[, alternative, ...])</code>	Compute the Brunner-Munzel test on samples <i>x</i> and <i>y</i> .
<code>combine_pvalues(pvalues[, method, weights])</code>	Combine p-values from independent tests bearing upon the same hypothesis.
<code>jarque_bera(x)</code>	Perform the Jarque-Bera goodness of fit test on sample data.

scipy.stats.ttest_1samp

`scipy.stats.ttest_1samp(a, popmean, axis=0, nan_policy='propagate', alternative='two-sided')`

Calculate the T-test for the mean of ONE group of scores.

This is a two-sided test for the null hypothesis that the expected value (mean) of a sample of independent observations *a* is equal to the given population mean, *popmean*.

Parameters

- a** [array_like] Sample observation.
- popmean** [float or array_like] Expected value in null hypothesis. If array_like, then it must have the same shape as *a* excluding the axis dimension.
- axis** [int or None, optional] Axis along which to compute test; default is 0. If None, compute over the whole array *a*.
- nan_policy** [{‘propagate’, ‘raise’, ‘omit’}, optional] Defines how to handle when input contains nan. The following options are available (default is ‘propagate’):
 - ‘propagate’: returns nan
 - ‘raise’: throws an error
 - ‘omit’: performs the calculations ignoring nan values
- alternative** [{‘two-sided’, ‘less’, ‘greater’}, optional] Defines the alternative hypothesis. The following options are available (default is ‘two-sided’):
 - ‘two-sided’
 - ‘less’: one-sided
 - ‘greater’: one-sided
 New in version 1.6.0.

Returns

statistic [float or array] t-statistic.
pvalue [float or array] Two-sided p-value.

Examples

```
>>> from scipy import stats
```

```
>>> np.random.seed(7654567) # fix seed to get the same result
>>> rvs = stats.norm.rvs(loc=5, scale=10, size=(50,2))
```

Test if mean of random sample is equal to true mean, and different mean. We reject the null hypothesis in the second case and don't reject it in the first case.

```
>>> stats.ttest_1samp(rvs, 5.0)
(array([-0.68014479, -0.04323899]), array([ 0.49961383,  0.96568674]))
>>> stats.ttest_1samp(rvs, 0.0)
(array([ 2.77025808,  4.11038784]), array([ 0.00789095,  0.00014999]))
```

Examples using axis and non-scalar dimension for population mean.

```
>>> result = stats.ttest_1samp(rvs, [5.0, 0.0])
>>> result.statistic
array([-0.68014479,  4.11038784]),
>>> result.pvalue
array([4.99613833e-01, 1.49986458e-04])
```

```
>>> result = stats.ttest_1samp(rvs.T, [5.0, 0.0], axis=1)
>>> result.statistic
array([-0.68014479,  4.11038784])
>>> result.pvalue
array([4.99613833e-01, 1.49986458e-04])
```

```
>>> result = stats.ttest_1samp(rvs, [[5.0], [0.0]])
>>> result.statistic
array([[ -0.68014479, -0.04323899],
       [ 2.77025808,  4.11038784]])
>>> result.pvalue
array([[4.99613833e-01, 9.65686743e-01],
       [7.89094663e-03, 1.49986458e-04]])
```

scipy.stats.ttest_ind

`scipy.stats.ttest_ind(a, b, axis=0, equal_var=True, nan_policy='propagate', alternative='two-sided')`

Calculate the T-test for the means of *two independent* samples of scores.

This is a two-sided test for the null hypothesis that 2 independent samples have identical average (expected) values. This test assumes that the populations have identical variances by default.

Parameters

a, b [array_like] The arrays must have the same shape, except in the dimension corresponding to *axis* (the first, by default).

axis	[int or None, optional] Axis along which to compute test. If None, compute over the whole arrays, <i>a</i> , and <i>b</i> .
equal_var	[bool, optional] If True (default), perform a standard independent 2 sample test that assumes equal population variances [1]. If False, perform Welch's t-test, which does not assume equal population variance [2]. New in version 0.11.0.
nan_policy	[{'propagate', 'raise', 'omit'}, optional] Defines how to handle when input contains nan. The following options are available (default is 'propagate'): <ul style="list-style-type: none"> • 'propagate': returns nan • 'raise': throws an error • 'omit': performs the calculations ignoring nan values
alternative	[{'two-sided', 'less', 'greater'}, optional] Defines the alternative hypothesis. The following options are available (default is 'two-sided'): <ul style="list-style-type: none"> • 'two-sided' • 'less': one-sided • 'greater': one-sided New in version 1.6.0.

Returns

statistic	[float or array] The calculated t-statistic.
pvalue	[float or array] The two-tailed p-value.

Notes

We can use this test, if we observe two independent samples from the same or different population, e.g. exam scores of boys and girls or of two ethnic groups. The test measures whether the average (expected) value differs significantly across samples. If we observe a large p-value, for example larger than 0.05 or 0.1, then we cannot reject the null hypothesis of identical average scores. If the p-value is smaller than the threshold, e.g. 1%, 5% or 10%, then we reject the null hypothesis of equal averages.

References

[1], [2]

Examples

```
>>> from scipy import stats
>>> np.random.seed(12345678)
```

Test with sample with identical means:

```
>>> rvs1 = stats.norm.rvs(loc=5, scale=10, size=500)
>>> rvs2 = stats.norm.rvs(loc=5, scale=10, size=500)
>>> stats.ttest_ind(rvs1, rvs2)
(0.26833823296239279, 0.78849443369564776)
>>> stats.ttest_ind(rvs1, rvs2, equal_var = False)
(0.26833823296239279, 0.78849452749500748)
```

`ttest_ind` underestimates p for unequal variances:

```
>>> rvs3 = stats.norm.rvs(loc=5, scale=20, size=500)
>>> stats.ttest_ind(rvs1, rvs3)
(-0.46580283298287162, 0.64145827413436174)
>>> stats.ttest_ind(rvs1, rvs3, equal_var = False)
(-0.46580283298287162, 0.64149646246569292)
```

When $n1 \neq n2$, the equal variance t-statistic is no longer equal to the unequal variance t-statistic:

```
>>> rvs4 = stats.norm.rvs(loc=5, scale=20, size=100)
>>> stats.ttest_ind(rvs1, rvs4)
(-0.99882539442782481, 0.3182832709103896)
>>> stats.ttest_ind(rvs1, rvs4, equal_var = False)
(-0.69712570584654099, 0.48716927725402048)
```

T-test with different means, variance, and n:

```
>>> rvs5 = stats.norm.rvs(loc=8, scale=20, size=100)
>>> stats.ttest_ind(rvs1, rvs5)
(-1.4679669854490653, 0.14263895620529152)
>>> stats.ttest_ind(rvs1, rvs5, equal_var = False)
(-0.94365973617132992, 0.34744170334794122)
```

scipy.stats.ttest_ind_from_stats

`scipy.stats.ttest_ind_from_stats(mean1, std1, nobs1, mean2, std2, nobs2, equal_var=True, alternative='two-sided')`

T-test for means of two independent samples from descriptive statistics.

This is a two-sided test for the null hypothesis that two independent samples have identical average (expected) values.

Parameters

- mean1** [array_like] The mean(s) of sample 1.
- std1** [array_like] The standard deviation(s) of sample 1.
- nobs1** [array_like] The number(s) of observations of sample 1.
- mean2** [array_like] The mean(s) of sample 2.
- std2** [array_like] The standard deviations(s) of sample 2.
- nobs2** [array_like] The number(s) of observations of sample 2.
- equal_var** [bool, optional] If True (default), perform a standard independent 2 sample test that assumes equal population variances [1]. If False, perform Welch's t-test, which does not assume equal population variance [2].
- alternative** [{"two-sided", "less", "greater"}, optional] Defines the alternative hypothesis. The following options are available (default is 'two-sided'):
 - 'two-sided'
 - 'less': one-sided
 - 'greater': one-sided
 New in version 1.6.0.

Returns

- statistic** [float or array] The calculated t-statistics.
- pvalue** [float or array] The two-tailed p-value.

See also:

`scipy.stats.ttest_ind`

Notes

New in version 0.16.0.

References

[1], [2]

Examples

Suppose we have the summary data for two samples, as follows:

	Size	Sample Mean	Sample Variance
Sample 1	13	15.0	87.5
Sample 2	11	12.0	39.0

Apply the t-test to this data (with the assumption that the population variances are equal):

```
>>> from scipy.stats import ttest_ind_from_stats
>>> ttest_ind_from_stats(mean1=15.0, std1=np.sqrt(87.5), nobs1=13,
...                      mean2=12.0, std2=np.sqrt(39.0), nobs2=11)
Ttest_indResult(statistic=0.9051358093310269, pvalue=0.3751996797581487)
```

For comparison, here is the data from which those summary statistics were taken. With this data, we can compute the same result using `scipy.stats.ttest_ind`:

```
>>> a = np.array([1, 3, 4, 6, 11, 13, 15, 19, 22, 24, 25, 26, 26])
>>> b = np.array([2, 4, 6, 9, 11, 13, 14, 15, 18, 19, 21])
>>> from scipy.stats import ttest_ind
>>> ttest_ind(a, b)
Ttest_indResult(statistic=0.905135809331027, pvalue=0.3751996797581486)
```

Suppose we instead have binary data and would like to apply a t-test to compare the proportion of 1s in two independent groups:

	Size	Number of ones	Sample Mean	Sample Variance
Sample 1	150	30	0.2	0.16
Sample 2	200	45	0.225	0.174375

The sample mean \hat{p} is the proportion of ones in the sample and the variance for a binary observation is estimated by $\hat{p}(1 - \hat{p})$.

```
>>> ttest_ind_from_stats(mean1=0.2, std1=np.sqrt(0.16), nobs1=150,
...                      mean2=0.225, std2=np.sqrt(0.174375), nobs2=200)
Ttest_indResult(statistic=-0.564327545549774, pvalue=0.5728947691244874)
```

For comparison, we could compute the t statistic and p-value using arrays of 0s and 1s and `scipy.stat.ttest_ind`, as above.

```
>>> group1 = np.array([1]*30 + [0]*(150-30))
>>> group2 = np.array([1]*45 + [0]*(200-45))
>>> ttest_ind(group1, group2)
Ttest_indResult(statistic=-0.5627179589855622, pvalue=0.573989277115258)
```

scipy.stats.ttest_rel

`scipy.stats.ttest_rel(a, b, axis=0, nan_policy='propagate', alternative='two-sided')`

Calculate the t-test on TWO RELATED samples of scores, a and b.

This is a two-sided test for the null hypothesis that 2 related or repeated samples have identical average (expected) values.

Parameters

- a, b** [array_like] The arrays must have the same shape.
- axis** [int or None, optional] Axis along which to compute test. If None, compute over the whole arrays, *a*, and *b*.
- nan_policy** [{‘propagate’, ‘raise’, ‘omit’}, optional] Defines how to handle when input contains nan. The following options are available (default is ‘propagate’):
- ‘propagate’: returns nan
 - ‘raise’: throws an error
 - ‘omit’: performs the calculations ignoring nan values
- alternative** [{‘two-sided’, ‘less’, ‘greater’}, optional] Defines the alternative hypothesis. The following options are available (default is ‘two-sided’):
- ‘two-sided’
 - ‘less’: one-sided
 - ‘greater’: one-sided
- New in version 1.6.0.

Returns

- statistic** [float or array] t-statistic.
- pvalue** [float or array] Two-sided p-value.

Notes

Examples for use are scores of the same set of student in different exams, or repeated sampling from the same units. The test measures whether the average score differs significantly across samples (e.g. exams). If we observe a large p-value, for example greater than 0.05 or 0.1 then we cannot reject the null hypothesis of identical average scores. If the p-value is smaller than the threshold, e.g. 1%, 5% or 10%, then we reject the null hypothesis of equal averages. Small p-values are associated with large t-statistics.

References

https://en.wikipedia.org/wiki/T-test#Dependent_t-test_for_paired_samples

Examples

```
>>> from scipy import stats
>>> np.random.seed(12345678) # fix random seed to get same numbers
```

```
>>> rvs1 = stats.norm.rvs(loc=5, scale=10, size=500)
>>> rvs2 = (stats.norm.rvs(loc=5, scale=10, size=500) +
...        stats.norm.rvs(scale=0.2, size=500))
>>> stats.ttest_rel(rvs1, rvs2)
(0.24101764965300962, 0.80964043445811562)
>>> rvs3 = (stats.norm.rvs(loc=8, scale=10, size=500) +
...        stats.norm.rvs(scale=0.2, size=500))
>>> stats.ttest_rel(rvs1, rvs3)
(-3.9995108708727933, 7.3082402191726459e-005)
```

scipy.stats.chisquare

`scipy.stats.chisquare` (*f_obs*, *f_exp*=None, *ddof*=0, *axis*=0)

Calculate a one-way chi-square test.

The chi-square test tests the null hypothesis that the categorical data has the given frequencies.

Parameters

f_obs	[array_like] Observed frequencies in each category.
f_exp	[array_like, optional] Expected frequencies in each category. By default the categories are assumed to be equally likely.
ddof	[int, optional] “Delta degrees of freedom”: adjustment to the degrees of freedom for the p-value. The p-value is computed using a chi-squared distribution with $k - 1 - \text{ddof}$ degrees of freedom, where k is the number of observed frequencies. The default value of <i>ddof</i> is 0.
axis	[int or None, optional] The axis of the broadcast result of <i>f_obs</i> and <i>f_exp</i> along which to apply the test. If <i>axis</i> is None, all values in <i>f_obs</i> are treated as a single data set. Default is 0.

Returns

chisq	[float or ndarray] The chi-squared test statistic. The value is a float if <i>axis</i> is None or <i>f_obs</i> and <i>f_exp</i> are 1-D.
p	[float or ndarray] The p-value of the test. The value is a float if <i>ddof</i> and the return value <i>chisq</i> are scalars.

See also:

`scipy.stats.power_divergence`

Notes

This test is invalid when the observed or expected frequencies in each category are too small. A typical rule is that all of the observed and expected frequencies should be at least 5.

The default degrees of freedom, $k-1$, are for the case when no parameters of the distribution are estimated. If p parameters are estimated by efficient maximum likelihood then the correct degrees of freedom are $k-1-p$. If the parameters are estimated in a different way, then the dof can be between $k-1-p$ and $k-1$. However, it is also possible that the asymptotic distribution is not chi-square, in which case this test is not appropriate.

References

[1], [2]

Examples

When just f_{obs} is given, it is assumed that the expected frequencies are uniform and given by the mean of the observed frequencies.

```
>>> from scipy.stats import chisquare
>>> chisquare([16, 18, 16, 14, 12, 12])
(2.0, 0.84914503608460956)
```

With f_{exp} the expected frequencies can be given.

```
>>> chisquare([16, 18, 16, 14, 12, 12], f_exp=[16, 16, 16, 16, 16, 8])
(3.5, 0.62338762774958223)
```

When f_{obs} is 2-D, by default the test is applied to each column.

```
>>> obs = np.array([[16, 18, 16, 14, 12, 12], [32, 24, 16, 28, 20, 24]])
>>> obs.shape
(6, 2)
>>> chisquare(obs)
(array([ 2.          ,  6.66666667]), array([ 0.84914504,  0.24663415]))
```

By setting `axis=None`, the test is applied to all data in the array, which is equivalent to applying the test to the flattened array.

```
>>> chisquare(obs, axis=None)
(23.31034482758621, 0.015975692534127565)
>>> chisquare(obs.ravel())
(23.31034482758621, 0.015975692534127565)
```

$ddof$ is the change to make to the default degrees of freedom.

```
>>> chisquare([16, 18, 16, 14, 12, 12], ddof=1)
(2.0, 0.73575888234288467)
```

The calculation of the p-values is done by broadcasting the chi-squared statistic with $ddof$.

```
>>> chisquare([16, 18, 16, 14, 12, 12], ddof=[0,1,2])
(2.0, array([ 0.84914504,  0.73575888,  0.5724067 ]))
```

f_{obs} and f_{exp} are also broadcast. In the following, f_{obs} has shape (6,) and f_{exp} has shape (2, 6), so the result of broadcasting f_{obs} and f_{exp} has shape (2, 6). To compute the desired chi-squared statistics, we use `axis=1`:

```
>>> chisquare([16, 18, 16, 14, 12, 12],
...           f_exp=[[16, 16, 16, 16, 16, 8], [8, 20, 20, 16, 12, 12]],
...           axis=1)
(array([ 3.5 ,  9.25]), array([ 0.62338763,  0.09949846]))
```

scipy.stats.cramervonmises

`scipy.stats.cramervonmises` (*rvs*, *cdf*, *args*=())

Perform the Cramér-von Mises test for goodness of fit.

This performs a test of the goodness of fit of a cumulative distribution function (cdf) F compared to the empirical distribution function F_n of observed random variates X_1, \dots, X_n that are assumed to be independent and identically distributed ([1]). The null hypothesis is that the X_i have cumulative distribution F .

Parameters

rvs [array_like] A 1-D array of observed values of the random variables X_i .

cdf [str or callable] The cumulative distribution function F to test the observations against. If a string, it should be the name of a distribution in `scipy.stats`. If a callable, that callable is used to calculate the cdf: `cdf(x, *args) -> float`.

args [tuple, optional] Distribution parameters. These are assumed to be known; see Notes.

Returns

res [object with attributes]

statistic [float] Cramér-von Mises statistic.

pvalue [float] The p-value.

See also:

[*kstest*](#)

Notes

New in version 1.6.0.

The p-value relies on the approximation given by equation 1.8 in [2]. It is important to keep in mind that the p-value is only accurate if one tests a simple hypothesis, i.e. the parameters of the reference distribution are known. If the parameters are estimated from the data (composite hypothesis), the computed p-value is not reliable.

References

[1], [2]

Examples

Suppose we wish to test whether data generated by `scipy.stats.norm.rvs` were, in fact, drawn from the standard normal distribution. We choose a significance level of $\alpha=0.05$.

```
>>> import numpy as np
>>> from scipy import stats
>>> np.random.seed(626)
>>> x = stats.norm.rvs(size=500)
>>> res = stats.cramervonmises(x, 'norm')
>>> res.statistic, res.pvalue
(0.06342154705518796, 0.792680516270629)
```

The p-value 0.79 exceeds our chosen significance level, so we do not reject the null hypothesis that the observed sample is drawn from the standard normal distribution.

Now suppose we wish to check whether the same samples shifted by 2.1 is consistent with being drawn from a normal distribution with a mean of 2.

```
>>> y = x + 2.1
>>> res = stats.cramervonmises(y, 'norm', args=(2,))
>>> res.statistic, res.pvalue
(0.4798693195559657, 0.044782228803623814)
```

Here we have used the `args` keyword to specify the mean (`loc`) of the normal distribution to test the data against. This is equivalent to the following, in which we create a frozen normal distribution with mean 2.1, then pass its `cdf` method as an argument.

```
>>> frozen_dist = stats.norm(loc=2)
>>> res = stats.cramervonmises(y, frozen_dist.cdf)
>>> res.statistic, res.pvalue
(0.4798693195559657, 0.044782228803623814)
```

In either case, we would reject the null hypothesis that the observed sample is drawn from a normal distribution with a mean of 2 (and default variance of 1) because the p-value 0.04 is less than our chosen significance level.

scipy.stats.power_divergence

`scipy.stats.power_divergence` (*f_obs*, *f_exp*=None, *ddof*=0, *axis*=0, *lambda_*=None)

Cressie-Read power divergence statistic and goodness of fit test.

This function tests the null hypothesis that the categorical data has the given frequencies, using the Cressie-Read power divergence statistic.

Parameters

f_obs	[array_like] Observed frequencies in each category.
f_exp	[array_like, optional] Expected frequencies in each category. By default the categories are assumed to be equally likely.
ddof	[int, optional] “Delta degrees of freedom”: adjustment to the degrees of freedom for the p-value. The p-value is computed using a chi-squared distribution with $k - 1 - \text{ddof}$ degrees of freedom, where k is the number of observed frequencies. The default value of <i>ddof</i> is 0.
axis	[int or None, optional] The axis of the broadcast result of <i>f_obs</i> and <i>f_exp</i> along which to apply the test. If <i>axis</i> is None, all values in <i>f_obs</i> are treated as a single data set. Default is 0.

lambda_ [float or str, optional] The power in the Cressie-Read power divergence statistic. The default is 1. For convenience, *lambda_* may be assigned one of the following strings, in which case the corresponding numerical value is used:

String	Value	Description
"pearson" ↪statistic.	1	Pearson's chi-squared. In this case, the function is equivalent to <code>`stats.chisquare`</code> .
"log-likelihood" ↪known as	0	Log-likelihood ratio. Also known as the G-test [Rf6c2a1ea428c-3].
"freeman-tukey"	-1/2	Freeman-Tukey statistic.
"mod-log-likelihood"	-1	Modified log-likelihood ratio.
"neyman"	-2	Neyman's statistic.
"cressie-read" ↪[Rf6c2a1ea428c-5].	2/3	The power recommended in [Rf6c2a1ea428c-5].

Returns

statistic [float or ndarray] The Cressie-Read power divergence test statistic. The value is a float if *axis* is None or if *f_obs* and *f_exp* are 1-D.

pvalue [float or ndarray] The p-value of the test. The value is a float if *ddof* and the return value *stat* are scalars.

See also:

[*chisquare*](#)

Notes

This test is invalid when the observed or expected frequencies in each category are too small. A typical rule is that all of the observed and expected frequencies should be at least 5.

When *lambda_* is less than zero, the formula for the statistic involves dividing by *f_obs*, so a warning or error may be generated if any value in *f_obs* is 0.

Similarly, a warning or error may be generated if any value in *f_exp* is zero when *lambda_* \geq 0.

The default degrees of freedom, $k-1$, are for the case when no parameters of the distribution are estimated. If *p* parameters are estimated by efficient maximum likelihood then the correct degrees of freedom are $k-1-p$. If the parameters are estimated in a different way, then the dof can be between $k-1-p$ and $k-1$. However, it is also possible that the asymptotic distribution is not a chisquare, in which case this test is not appropriate.

This function handles masked arrays. If an element of *f_obs* or *f_exp* is masked, then data at that position is ignored, and does not count towards the size of the data set.

New in version 0.13.0.

References

[1], [2], [3], [4], [5]

Examples

(See *chisquare* for more examples.)

When just *f_obs* is given, it is assumed that the expected frequencies are uniform and given by the mean of the observed frequencies. Here we perform a G-test (i.e. use the log-likelihood ratio statistic):

```
>>> from scipy.stats import power_divergence
>>> power_divergence([16, 18, 16, 14, 12, 12], lambda_='log-likelihood')
(2.006573162632538, 0.84823476779463769)
```

The expected frequencies can be given with the *f_exp* argument:

```
>>> power_divergence([16, 18, 16, 14, 12, 12],
...                  f_exp=[16, 16, 16, 16, 16, 8],
...                  lambda_='log-likelihood')
(3.3281031458963746, 0.6495419288047497)
```

When *f_obs* is 2-D, by default the test is applied to each column.

```
>>> obs = np.array([[16, 18, 16, 14, 12, 12], [32, 24, 16, 28, 20, 24]])
>>> obs.shape
(6, 2)
>>> power_divergence(obs, lambda_="log-likelihood")
(array([ 2.00657316,  6.77634498]), array([ 0.84823477,  0.23781225]))
```

By setting *axis=None*, the test is applied to all data in the array, which is equivalent to applying the test to the flattened array.

```
>>> power_divergence(obs, axis=None)
(23.31034482758621, 0.015975692534127565)
>>> power_divergence(obs.ravel())
(23.31034482758621, 0.015975692534127565)
```

ddof is the change to make to the default degrees of freedom.

```
>>> power_divergence([16, 18, 16, 14, 12, 12], ddof=1)
(2.0, 0.73575888234288467)
```

The calculation of the p-values is done by broadcasting the test statistic with *ddof*.

```
>>> power_divergence([16, 18, 16, 14, 12, 12], ddof=[0, 1, 2])
(2.0, array([ 0.84914504,  0.73575888,  0.5724067 ]))
```

f_obs and *f_exp* are also broadcast. In the following, *f_obs* has shape (6,) and *f_exp* has shape (2, 6), so the result of broadcasting *f_obs* and *f_exp* has shape (2, 6). To compute the desired chi-squared statistics, we must use *axis=1*:

```
>>> power_divergence([16, 18, 16, 14, 12, 12],
...                  f_exp=[[16, 16, 16, 16, 16, 8],
```

(continues on next page)

(continued from previous page)

```

...         [8, 20, 20, 16, 12, 12]],
...         axis=1)
(array([ 3.5 ,  9.25]), array([ 0.62338763,  0.09949846]))

```

scipy.stats.kstest

`scipy.stats.kstest` (*rvs*, *cdf*, *args=()*, *N=20*, *alternative='two-sided'*, *mode='auto'*)

Performs the (one sample or two samples) Kolmogorov-Smirnov test for goodness of fit.

The one-sample test performs a test of the distribution $F(x)$ of an observed random variable against a given distribution $G(x)$. Under the null hypothesis, the two distributions are identical, $F(x)=G(x)$. The alternative hypothesis can be either 'two-sided' (default), 'less' or 'greater'. The KS test is only valid for continuous distributions. The two-sample test tests whether the two independent samples are drawn from the same continuous distribution.

Parameters

rvs	[str, array_like, or callable] If an array, it should be a 1-D array of observations of random variables. If a callable, it should be a function to generate random variables; it is required to have a keyword argument <i>size</i> . If a string, it should be the name of a distribution in <code>scipy.stats</code> , which will be used to generate random variables.
cdf	[str, array_like or callable] If array_like, it should be a 1-D array of observations of random variables, and the two-sample test is performed (and <i>rvs</i> must be array_like) If a callable, that callable is used to calculate the cdf. If a string, it should be the name of a distribution in <code>scipy.stats</code> , which will be used as the cdf function.
args	[tuple, sequence, optional] Distribution parameters, used if <i>rvs</i> or <i>cdf</i> are strings or callables.
N	[int, optional] Sample size if <i>rvs</i> is string or callable. Default is 20.
alternative	[['two-sided', 'less', 'greater'], optional] Defines the alternative hypothesis. The following options are available (default is 'two-sided'): <ul style="list-style-type: none"> • 'two-sided' • 'less': one-sided, see explanation in Notes • 'greater': one-sided, see explanation in Notes
mode	[['auto', 'exact', 'approx', 'asympt'], optional] Defines the distribution used for calculating the p-value. The following options are available (default is 'auto'): <ul style="list-style-type: none"> • 'auto': selects one of the other options. • 'exact': uses the exact distribution of test statistic. • 'approx': approximates the two-sided probability with twice the one-sided probability • 'asympt': uses asymptotic distribution of test statistic

Returns

statistic	[float] KS test statistic, either D, D+ or D-.
pvalue	[float] One-tailed or two-tailed p-value.

See also:

[`ks_2samp`](#)

Notes

In the one-sided test, the alternative is that the empirical cumulative distribution function of the random variable is “less” or “greater” than the cumulative distribution function $G(x)$ of the hypothesis, $F(x) \leq G(x)$, resp. $F(x) \geq G(x)$.

Examples

```
>>> from scipy import stats
```

```
>>> x = np.linspace(-15, 15, 9)
>>> stats.kstest(x, 'norm')
(0.44435602715924361, 0.0388501427051711065)
```

```
>>> np.random.seed(987654321) # set random seed to get the same result
>>> stats.kstest(stats.norm.rvs(size=100), stats.norm.cdf)
(0.058352892479417884, 0.8653960860778898)
```

The above lines are equivalent to:

```
>>> np.random.seed(987654321)
>>> stats.kstest(stats.norm.rvs, 'norm', N=100)
(0.058352892479417884, 0.8653960860778898)
```

Test against one-sided alternative hypothesis

Shift distribution to larger values, so that $\text{CDF}(x) < \text{norm.cdf}(x)$:

```
>>> np.random.seed(987654321)
>>> x = stats.norm.rvs(loc=0.2, size=100)
>>> stats.kstest(x, 'norm', alternative='less')
(0.12464329735846891, 0.040989164077641749)
```

Reject equal distribution against alternative hypothesis: less

```
>>> stats.kstest(x, 'norm', alternative='greater')
(0.0072115233216311081, 0.98531158590396395)
```

Don't reject equal distribution against alternative hypothesis: greater

```
>>> stats.kstest(x, 'norm')
(0.12464329735846891, 0.08197335233541582)
```

Testing t distributed random variables against normal distribution

With 100 degrees of freedom the t distribution looks close to the normal distribution, and the K-S test does not reject the hypothesis that the sample came from the normal distribution:

```
>>> np.random.seed(987654321)
>>> stats.kstest(stats.t.rvs(100, size=100), 'norm')
(0.072018929165471257, 0.6505883498379312)
```

With 3 degrees of freedom the t distribution looks sufficiently different from the normal distribution, that we can reject the hypothesis that the sample came from the normal distribution at the 10% level:

```
>>> np.random.seed(987654321)
>>> stats.kstest(stats.t.rvs(3, size=100), 'norm')
(0.131016895759829, 0.058826222555312224)
```

scipy.stats.ks_1samp

`scipy.stats.ks_1samp(x, cdf, args=(), alternative='two-sided', mode='auto')`

Performs the Kolmogorov-Smirnov test for goodness of fit.

This performs a test of the distribution $F(x)$ of an observed random variable against a given distribution $G(x)$. Under the null hypothesis, the two distributions are identical, $F(x)=G(x)$. The alternative hypothesis can be either 'two-sided' (default), 'less' or 'greater'. The KS test is only valid for continuous distributions.

Parameters

x	[array_like] a 1-D array of observations of iid random variables.
cdf	[callable] callable used to calculate the cdf.
args	[tuple, sequence, optional] Distribution parameters, used with <i>cdf</i> .
alternative	[['two-sided', 'less', 'greater'], optional] Defines the alternative hypothesis. The following options are available (default is 'two-sided'): <ul style="list-style-type: none"> • 'two-sided' • 'less': one-sided, see explanation in Notes • 'greater': one-sided, see explanation in Notes
mode	[['auto', 'exact', 'approx', 'asympt'], optional] Defines the distribution used for calculating the p-value. The following options are available (default is 'auto'): <ul style="list-style-type: none"> • 'auto': selects one of the other options. • 'exact': uses the exact distribution of test statistic. • 'approx': approximates the two-sided probability with twice the one-sided probability • 'asympt': uses asymptotic distribution of test statistic

Returns

statistic	[float] KS test statistic, either D, D+ or D- (depending on the value of 'alternative')
pvalue	[float] One-tailed or two-tailed p-value.

See also:

[*ks_2samp*](#), [*kstest*](#)

Notes

In the one-sided test, the alternative is that the empirical cumulative distribution function of the random variable is "less" or "greater" than the cumulative distribution function $G(x)$ of the hypothesis, $F(x) \leq G(x)$, resp. $F(x) \geq G(x)$.

Examples

```
>>> from scipy import stats
```

```
>>> x = np.linspace(-15, 15, 9)
>>> stats.ks_1samp(x, stats.norm.cdf)
(0.44435602715924361, 0.038850142705171065)
```

```
>>> np.random.seed(987654321) # set random seed to get the same result
>>> stats.ks_1samp(stats.norm.rvs(size=100), stats.norm.cdf)
(0.058352892479417884, 0.8653960860778898)
```

Test against one-sided alternative hypothesis

Shift distribution to larger values, so that $\text{CDF}(x) < \text{norm.cdf}(x)$:

```
>>> np.random.seed(987654321)
>>> x = stats.norm.rvs(loc=0.2, size=100)
>>> stats.ks_1samp(x, stats.norm.cdf, alternative='less')
(0.12464329735846891, 0.040989164077641749)
```

Reject equal distribution against alternative hypothesis: less

```
>>> stats.ks_1samp(x, stats.norm.cdf, alternative='greater')
(0.0072115233216311081, 0.98531158590396395)
```

Don't reject equal distribution against alternative hypothesis: greater

```
>>> stats.ks_1samp(x, stats.norm.cdf)
(0.12464329735846891, 0.08197335233541582)
```

Don't reject equal distribution against alternative hypothesis: two-sided

Testing t distributed random variables against normal distribution

With 100 degrees of freedom the t distribution looks close to the normal distribution, and the K-S test does not reject the hypothesis that the sample came from the normal distribution:

```
>>> np.random.seed(987654321)
>>> stats.ks_1samp(stats.t.rvs(100, size=100), stats.norm.cdf)
(0.072018929165471257, 0.6505883498379312)
```

With 3 degrees of freedom the t distribution looks sufficiently different from the normal distribution, that we can reject the hypothesis that the sample came from the normal distribution at the 10% level:

```
>>> np.random.seed(987654321)
>>> stats.ks_1samp(stats.t.rvs(3, size=100), stats.norm.cdf)
(0.131016895759829, 0.058826222555312224)
```

scipy.stats.ks_2samp

`scipy.stats.ks_2samp` (*data1*, *data2*, *alternative*='two-sided', *mode*='auto')

Compute the Kolmogorov-Smirnov statistic on 2 samples.

This is a two-sided test for the null hypothesis that 2 independent samples are drawn from the same continuous distribution. The alternative hypothesis can be either 'two-sided' (default), 'less' or 'greater'.

Parameters

data1, data2

[array_like, 1-Dimensional] Two arrays of sample observations assumed to be drawn from a continuous distribution, sample sizes can be different.

alternative

[{'two-sided', 'less', 'greater'}, optional] Defines the alternative hypothesis. The following options are available (default is 'two-sided'):

- 'two-sided'
- 'less': one-sided, see explanation in Notes
- 'greater': one-sided, see explanation in Notes

mode

[{'auto', 'exact', 'asympt'}, optional] Defines the method used for calculating the p-value. The following options are available (default is 'auto'):

- 'auto': use 'exact' for small size arrays, 'asympt' for large
- 'exact': use exact distribution of test statistic
- 'asympt': use asymptotic distribution of test statistic

Returns

statistic [float] KS statistic.
pvalue [float] Two-tailed p-value.

See also:

[*kstest*](#), [*ks_1samp*](#), [*epps_singleton_2samp*](#), [*anderson_ksamp*](#)

Notes

This tests whether 2 samples are drawn from the same distribution. Note that, like in the case of the one-sample KS test, the distribution is assumed to be continuous.

In the one-sided test, the alternative is that the empirical cumulative distribution function $F(x)$ of the *data1* variable is "less" or "greater" than the empirical cumulative distribution function $G(x)$ of the *data2* variable, $F(x) < G(x)$, resp. $F(x) > G(x)$.

If the KS statistic is small or the p-value is high, then we cannot reject the hypothesis that the distributions of the two samples are the same.

If the mode is 'auto', the computation is exact if the sample sizes are less than 10000. For larger sizes, the computation uses the Kolmogorov-Smirnov distributions to compute an approximate value.

The 'two-sided' 'exact' computation computes the complementary probability and then subtracts from 1. As such, the minimum probability it can return is about 1e-16. While the algorithm itself is exact, numerical errors may accumulate for large sample sizes. It is most suited to situations in which one of the sample sizes is only a few thousand.

We generally follow Hodges' treatment of Drion/Gnedenko/Korolyuk [1].

References

[1]

Examples

```
>>> from scipy import stats
>>> np.random.seed(12345678) #fix random seed to get the same result
>>> n1 = 200 # size of first sample
>>> n2 = 300 # size of second sample
```

For a different distribution, we can reject the null hypothesis since the pvalue is below 1%:

```
>>> rvs1 = stats.norm.rvs(size=n1, loc=0., scale=1)
>>> rvs2 = stats.norm.rvs(size=n2, loc=0.5, scale=1.5)
>>> stats.ks_2samp(rvs1, rvs2)
(0.20833333333333334, 5.129279597781977e-05)
```

For a slightly different distribution, we cannot reject the null hypothesis at a 10% or lower alpha since the p-value at 0.144 is higher than 10%

```
>>> rvs3 = stats.norm.rvs(size=n2, loc=0.01, scale=1.0)
>>> stats.ks_2samp(rvs1, rvs3)
(0.10333333333333333, 0.14691437867433876)
```

For an identical distribution, we cannot reject the null hypothesis since the p-value is high, 41%:

```
>>> rvs4 = stats.norm.rvs(size=n2, loc=0.0, scale=1.0)
>>> stats.ks_2samp(rvs1, rvs4)
(0.07999999999999999, 0.41126949729859719)
```

scipy.stats.epps_singleton_2samp

`scipy.stats.epps_singleton_2samp(x, y, t=(0.4, 0.8))`

Compute the Epps-Singleton (ES) test statistic.

Test the null hypothesis that two samples have the same underlying probability distribution.

Parameters

x, y	[array-like] The two samples of observations to be tested. Input must not have more than one dimension. Samples can have different lengths.
t	[array-like, optional] The points (t1, ..., tn) where the empirical characteristic function is to be evaluated. It should be positive distinct numbers. The default value (0.4, 0.8) is proposed in [1]. Input must not have more than one dimension.

Returns

statistic	[float] The test statistic.
pvalue	[float] The associated p-value based on the asymptotic chi2-distribution.

See also:

[*ks_2samp*](#), [*anderson_ksamp*](#)

Notes

Testing whether two samples are generated by the same underlying distribution is a classical question in statistics. A widely used test is the Kolmogorov-Smirnov (KS) test which relies on the empirical distribution function. Epps and Singleton introduce a test based on the empirical characteristic function in [1].

One advantage of the ES test compared to the KS test is that it does not assume a continuous distribution. In [1], the authors conclude that the test also has a higher power than the KS test in many examples. They recommend the use of the ES test for discrete samples as well as continuous samples with at least 25 observations each, whereas `anderson_ksamp` is recommended for smaller sample sizes in the continuous case.

The p-value is computed from the asymptotic distribution of the test statistic which follows a `chi2` distribution. If the sample size of both `x` and `y` is below 25, the small sample correction proposed in [1] is applied to the test statistic.

The default values of `t` are determined in [1] by considering various distributions and finding good values that lead to a high power of the test in general. Table III in [1] gives the optimal values for the distributions tested in that study. The values of `t` are scaled by the semi-interquartile range in the implementation, see [1].

References

[1], [2]

scipy.stats.mannwhitneyu

`scipy.stats.mannwhitneyu(x, y, use_continuity=True, alternative=None)`

Compute the Mann-Whitney rank test on samples `x` and `y`.

Parameters

- x, y** [array_like] Array of samples, should be one-dimensional.
- use_continuity** [bool, optional] Whether a continuity correction (1/2.) should be taken into account. Default is True.
- alternative** [{None, 'two-sided', 'less', 'greater'}, optional] Defines the alternative hypothesis. The following options are available (default is None):
 - None: computes p-value half the size of the 'two-sided' p-value and a different U statistic. The default behavior is not the same as using 'less' or 'greater'; it only exists for backward compatibility and is deprecated.
 - 'two-sided'
 - 'less': one-sided
 - 'greater': one-sided
 Use of the None option is deprecated.

Returns

- statistic** [float] The Mann-Whitney U statistic, equal to $\min(U \text{ for } x, U \text{ for } y)$ if `alternative` is equal to None (deprecated; exists for backward compatibility), and U for `y` otherwise.
- pvalue** [float] p-value assuming an asymptotic normal distribution. One-sided or two-sided, depending on the choice of `alternative`.

Notes

Use only when the number of observation in each sample is > 20 and you have 2 independent samples of ranks. Mann-Whitney U is significant if the u-obtained is LESS THAN or equal to the critical value of U.

This test corrects for ties and by default uses a continuity correction.

References

[1], [2]

scipy.stats.tiecorrect

`scipy.stats.tiecorrect` (*rankvals*)

Tie correction factor for Mann-Whitney U and Kruskal-Wallis H tests.

Parameters

rankvals [array_like] A 1-D sequence of ranks. Typically this will be the array returned by *rankdata*.

Returns

factor [float] Correction factor for U or H.

See also:

rankdata

Assign ranks to the data

mannwhitneyu

Mann-Whitney rank test

kruskal

Kruskal-Wallis H test

References

[1]

Examples

```
>>> from scipy.stats import tiecorrect, rankdata
>>> tiecorrect([1, 2.5, 2.5, 4])
0.9
>>> ranks = rankdata([1, 3, 2, 4, 5, 7, 2, 8, 4])
>>> ranks
array([ 1. ,  4. ,  2.5,  5.5,  7. ,  8. ,  2.5,  9. ,  5.5])
>>> tiecorrect(ranks)
0.9833333333333333
```


scipy.stats.rankdata

`scipy.stats.rankdata` (*a*, *method*='average', *, *axis*=None)

Assign ranks to data, dealing with ties appropriately.

By default (*axis*=None), the data array is first flattened, and a flat array of ranks is returned. Separately reshape the rank array to the shape of the data array if desired (see Examples).

Ranks begin at 1. The *method* argument controls how ranks are assigned to equal values. See [1] for further discussion of ranking methods.

Parameters

a	[array_like] The array of values to be ranked.
method	[{'average', 'min', 'max', 'dense', 'ordinal'}, optional] The method used to assign ranks to tied elements. The following methods are available (default is 'average'): <ul style="list-style-type: none"> • 'average': The average of the ranks that would have been assigned to all the tied values is assigned to each value. • 'min': The minimum of the ranks that would have been assigned to all the tied values is assigned to each value. (This is also referred to as "competition" ranking.) • 'max': The maximum of the ranks that would have been assigned to all the tied values is assigned to each value. • 'dense': Like 'min', but the rank of the next highest element is assigned the rank immediately after those assigned to the tied elements. • 'ordinal': All values are given a distinct rank, corresponding to the order that the values occur in <i>a</i>.
axis	[{None, int}, optional] Axis along which to perform the ranking. If None, the data array is first flattened.

Returns

ranks	[ndarray] An array of size equal to the size of <i>a</i> , containing rank scores.
--------------	--

References

[1]

Examples

```
>>> from scipy.stats import rankdata
>>> rankdata([0, 2, 3, 2])
array([ 1. ,  2.5,  4. ,  2.5])
>>> rankdata([0, 2, 3, 2], method='min')
array([ 1,  2,  4,  2])
>>> rankdata([0, 2, 3, 2], method='max')
array([ 1,  3,  4,  3])
>>> rankdata([0, 2, 3, 2], method='dense')
array([ 1,  2,  3,  2])
>>> rankdata([0, 2, 3, 2], method='ordinal')
array([ 1,  2,  4,  3])
>>> rankdata([[0, 2], [3, 2]]).reshape(2,2)
array([[1. ,  2.5],
       [4. ,  2.5]])
>>> rankdata([[0, 2, 2], [3, 2, 5]], axis=1)
```

(continues on next page)

(continued from previous page)

```
array([[1. , 2.5, 2.5],
       [2. , 1. , 3. ]])
```

scipy.stats.ranksums

`scipy.stats.ranksums(x, y)`

Compute the Wilcoxon rank-sum statistic for two samples.

The Wilcoxon rank-sum test tests the null hypothesis that two sets of measurements are drawn from the same distribution. The alternative hypothesis is that values in one sample are more likely to be larger than the values in the other sample.

This test should be used to compare two samples from continuous distributions. It does not handle ties between measurements in `x` and `y`. For tie-handling and an optional continuity correction see `scipy.stats.mannwhitneyu`.

Parameters

x,y [array_like] The data from the two samples.

Returns

statistic [float] The test statistic under the large-sample approximation that the rank sum statistic is normally distributed.

pvalue [float] The two-sided p-value of the test.

References

[1]

Examples

We can test the hypothesis that two independent unequal-sized samples are drawn from the same distribution with computing the Wilcoxon rank-sum statistic.

```
>>> from scipy.stats import ranksums
>>> sample1 = np.random.uniform(-1, 1, 200)
>>> sample2 = np.random.uniform(-0.5, 1.5, 300) # a shifted distribution
>>> ranksums(sample1, sample2)
RanksumsResult(statistic=-7.887059, pvalue=3.09390448e-15) # may vary
```

The p-value of less than 0.05 indicates that this test rejects the hypothesis at the 5% significance level.

scipy.stats.wilcoxon

`scipy.stats.wilcoxon(x, y=None, zero_method='wilcox', correction=False, alternative='two-sided', mode='auto')`

Calculate the Wilcoxon signed-rank test.

The Wilcoxon signed-rank test tests the null hypothesis that two related paired samples come from the same distribution. In particular, it tests whether the distribution of the differences $x - y$ is symmetric about zero. It is a non-parametric version of the paired T-test.

Parameters

- x** [array_like] Either the first set of measurements (in which case y is the second set of measurements), or the differences between two sets of measurements (in which case y is not to be specified.) Must be one-dimensional.
- y** [array_like, optional] Either the second set of measurements (if x is the first set of measurements), or not specified (if x is the differences between two sets of measurements.) Must be one-dimensional.
- zero_method** [{"pratt", "wilcox", "zsplit"}, optional] The following options are available (default is "wilcox"):
- "pratt": Includes zero-differences in the ranking process, but drops the ranks of the zeros, see [4], (more conservative).
 - "wilcox": Discards all zero-differences, the default.
 - "zsplit": Includes zero-differences in the ranking process and split the zero rank between positive and negative ones.
- correction** [bool, optional] If True, apply continuity correction by adjusting the Wilcoxon rank statistic by 0.5 towards the mean value when computing the z-statistic if a normal approximation is used. Default is False.
- alternative** [{"two-sided", "greater", "less"}, optional] The alternative hypothesis to be tested, see Notes. Default is "two-sided".
- mode** [{"auto", "exact", "approx"}] Method to calculate the p-value, see Notes. Default is "auto".

Returns

- statistic** [float] If `alternative` is "two-sided", the sum of the ranks of the differences above or below zero, whichever is smaller. Otherwise the sum of the ranks of the differences above zero.
- pvalue** [float] The p-value for the test depending on `alternative` and `mode`.

See also:

[*kruskal, mannwhitneyu*](#)

Notes

The test has been introduced in [4]. Given n independent samples (x_i, y_i) from a bivariate distribution (i.e. paired samples), it computes the differences $d_i = x_i - y_i$. One assumption of the test is that the differences are symmetric, see [2]. The two-sided test has the null hypothesis that the median of the differences is zero against the alternative that it is different from zero. The one-sided test has the null hypothesis that the median is positive against the alternative that it is negative (`alternative == 'less'`), or vice versa (`alternative == 'greater'`).

To derive the p-value, the exact distribution (`mode == 'exact'`) can be used for sample sizes of up to 25. The default `mode == 'auto'` uses the exact distribution if there are at most 25 observations and no ties, otherwise a normal approximation is used (`mode == 'approx'`).

The treatment of ties can be controlled by the parameter `zero_method`. If `zero_method == 'pratt'`, the normal approximation is adjusted as in [5]. A typical rule is to require that $n > 20$ ([2], p. 383).

References

[1], [2], [3], [4], [5]

Examples

In [4], the differences in height between cross- and self-fertilized corn plants is given as follows:

```
>>> d = [6, 8, 14, 16, 23, 24, 28, 29, 41, -48, 49, 56, 60, -67, 75]
```

Cross-fertilized plants appear to be higher. To test the null hypothesis that there is no height difference, we can apply the two-sided test:

```
>>> from scipy.stats import wilcoxon
>>> w, p = wilcoxon(d)
>>> w, p
(24.0, 0.041259765625)
```

Hence, we would reject the null hypothesis at a confidence level of 5%, concluding that there is a difference in height between the groups. To confirm that the median of the differences can be assumed to be positive, we use:

```
>>> w, p = wilcoxon(d, alternative='greater')
>>> w, p
(96.0, 0.0206298828125)
```

This shows that the null hypothesis that the median is negative can be rejected at a confidence level of 5% in favor of the alternative that the median is greater than zero. The p-values above are exact. Using the normal approximation gives very similar values:

```
>>> w, p = wilcoxon(d, mode='approx')
>>> w, p
(24.0, 0.04088813291185591)
```

Note that the statistic changed to 96 in the one-sided case (the sum of ranks of positive differences) whereas it is 24 in the two-sided case (the minimum of sum of ranks above and below zero).

scipy.stats.kruskal

`scipy.stats.kruskal` (*args, nan_policy='propagate')

Compute the Kruskal-Wallis H-test for independent samples.

The Kruskal-Wallis H-test tests the null hypothesis that the population median of all of the groups are equal. It is a non-parametric version of ANOVA. The test works on 2 or more independent samples, which may have different sizes. Note that rejecting the null hypothesis does not indicate which of the groups differs. Post hoc comparisons between groups are required to determine which groups are different.

Parameters

sample1, sample2, ...

[array_like] Two or more arrays with the sample measurements can be given as arguments.

nan_policy

[{'propagate', 'raise', 'omit'}, optional] Defines how to handle when input contains nan. The following options are available (default is 'propagate'):

- 'propagate': returns nan
- 'raise': throws an error
- 'omit': performs the calculations ignoring nan values

Returns

statistic [float] The Kruskal-Wallis H statistic, corrected for ties.

pvalue [float] The p-value for the test using the assumption that H has a chi square distribution. The p-value returned is the survival function of the chi square distribution evaluated at H.

See also:*f_oneway*

1-way ANOVA.

mannwhitneyu

Mann-Whitney rank test on two samples.

friedmanchisquare

Friedman test for repeated measurements.

Notes

Due to the assumption that H has a chi square distribution, the number of samples in each group must not be too small. A typical rule is that each sample must have at least 5 measurements.

References

[1], [2]

Examples

```
>>> from scipy import stats
>>> x = [1, 3, 5, 7, 9]
>>> y = [2, 4, 6, 8, 10]
>>> stats.kruskal(x, y)
KruskalResult(statistic=0.2727272727272734, pvalue=0.6015081344405895)
```

```
>>> x = [1, 1, 1]
>>> y = [2, 2, 2]
>>> z = [2, 2]
>>> stats.kruskal(x, y, z)
KruskalResult(statistic=7.0, pvalue=0.0301973834223185)
```

scipy.stats.friedmanchisquare

`scipy.stats.friedmanchisquare` (*args)

Compute the Friedman test for repeated measurements.

The Friedman test tests the null hypothesis that repeated measurements of the same individuals have the same distribution. It is often used to test for consistency among measurements obtained in different ways. For example, if two measurement techniques are used on the same set of individuals, the Friedman test can be used to determine if the two measurement techniques are consistent.

Parameters

measurements1, measurements2, measurements3...

[array_like] Arrays of measurements. All of the arrays must have the same number of elements. At least 3 sets of measurements must be given.

Returns

statistic [float] The test statistic, correcting for ties.

pvalue [float] The associated p-value assuming that the test statistic has a chi squared distribution.

Notes

Due to the assumption that the test statistic has a chi squared distribution, the p-value is only reliable for $n > 10$ and more than 6 repeated measurements.

References

[1]

scipy.stats.brunnermunzel

`scipy.stats.brunnermunzel` (x, y, *alternative='two-sided', distribution='t', nan_policy='propagate'*)

Compute the Brunner-Munzel test on samples x and y.

The Brunner-Munzel test is a nonparametric test of the null hypothesis that when values are taken one by one from each group, the probabilities of getting large values in both groups are equal. Unlike the Wilcoxon-Mann-Whitney's U test, this does not require the assumption of equivariance of two groups. Note that this does not assume the distributions are same. This test works on two independent samples, which may have different sizes.

Parameters

x, y [array_like] Array of samples, should be one-dimensional.

alternative

[{'two-sided', 'less', 'greater'}, optional] Defines the alternative hypothesis. The following options are available (default is 'two-sided'):

- 'two-sided'
- 'less': one-sided
- 'greater': one-sided

distribution

[{'t', 'normal'}, optional] Defines how to get the p-value. The following options are available (default is 't'):

- 't': get the p-value by t-distribution
- 'normal': get the p-value by standard normal distribution.

nan_policy

[{'propagate', 'raise', 'omit'}, optional] Defines how to handle when input contains nan. The following options are available (default is 'propagate'):

- 'propagate': returns nan
- 'raise': throws an error
- 'omit': performs the calculations ignoring nan values

Returns

statistic [float] The Brunner-Munzer W statistic.

pvalue [float] p-value assuming an t distribution. One-sided or two-sided, depending on the choice of *alternative* and *distribution*.

See also:*mannwhitneyu*

Mann-Whitney rank test on two samples.

Notes

Brunner and Munzel recommended to estimate the p-value by t-distribution when the size of data is 50 or less. If the size is lower than 10, it would be better to use permuted Brunner Munzel test (see [2]).

References

[1], [2]

Examples

```
>>> from scipy import stats
>>> x1 = [1, 2, 1, 1, 1, 1, 1, 1, 1, 1, 2, 4, 1, 1]
>>> x2 = [3, 3, 4, 3, 1, 2, 3, 1, 1, 5, 4]
>>> w, p_value = stats.brunnermunzel(x1, x2)
>>> w
3.1374674823029505
>>> p_value
0.0057862086661515377
```

scipy.stats.combine_pvalues

`scipy.stats.combine_pvalues` (*pvalues*, *method*='fisher', *weights*=None)

Combine p-values from independent tests bearing upon the same hypothesis.

Parameters

pvalues [array_like, 1-D] Array of p-values assumed to come from independent tests.

method [{'fisher', 'pearson', 'tippett', 'stouffer', 'mudholkar_george'}, optional] Name of method to use to combine p-values. The following methods are available (default is 'fisher'):

- 'fisher': Fisher's method (Fisher's combined probability test), the sum of the logarithm of the p-values
- 'pearson': Pearson's method (similar to Fisher's but uses sum of the complement of the p-values inside the logarithms)

- ‘tippett’: Tippett’s method (minimum of p-values)
 - ‘stouffer’: Stouffer’s Z-score method
 - ‘mudholkar_george’: the difference of Fisher’s and Pearson’s methods divided by 2
- weights** [array_like, 1-D, optional] Optional array of weights used only for Stouffer’s Z-score method.

Returns

- statistic: float** The statistic calculated by the specified method.
- pval: float** The combined p-value.

Notes

Fisher’s method (also known as Fisher’s combined probability test) [1] uses a chi-squared statistic to compute a combined p-value. The closely related Stouffer’s Z-score method [2] uses Z-scores rather than p-values. The advantage of Stouffer’s method is that it is straightforward to introduce weights, which can make Stouffer’s method more powerful than Fisher’s method when the p-values are from studies of different size [6] [7]. The Pearson’s method uses $\log(1 - p_i)$ inside the sum whereas Fisher’s method uses $\log(p_i)$ [4]. For Fisher’s and Pearson’s method, the sum of the logarithms is multiplied by -2 in the implementation. This quantity has a chi-square distribution that determines the p-value. The *mudholkar_george* method is the difference of the Fisher’s and Pearson’s test statistics, each of which include the -2 factor [4]. However, the *mudholkar_george* method does not include these -2 factors. The test statistic of *mudholkar_george* is the sum of logistic random variables and equation 3.6 in [3] is used to approximate the p-value based on Student’s t-distribution.

Fisher’s method may be extended to combine p-values from dependent tests [5]. Extensions such as Brown’s method and Kost’s method are not currently implemented.

New in version 0.15.0.

References

- [1], [2], [3], [4], [5], [6], [7]

scipy.stats.jarque_bera

`scipy.stats.jarque_bera(x)`
 Perform the Jarque-Bera goodness of fit test on sample data.

The Jarque-Bera test tests whether the sample data has the skewness and kurtosis matching a normal distribution.

Note that this test only works for a large enough number of data samples (>2000) as the test statistic asymptotically has a Chi-squared distribution with 2 degrees of freedom.

Parameters

- x** [array_like] Observations of a random variable.

Returns

- jb_value** [float] The test statistic.
- p** [float] The p-value for the hypothesis test.

References

[1]

Examples

```
>>> from scipy import stats
>>> np.random.seed(987654321)
>>> x = np.random.normal(0, 1, 100000)
>>> jarque_bera_test = stats.jarque_bera(x)
>>> jarque_bera_test
Jarque_beraResult(statistic=4.716570798957913, pvalue=0.0945822550304295)
>>> jarque_bera_test.statistic
4.716570798957913
>>> jarque_bera_test.pvalue
0.0945822550304295
```

<i>ansari</i> (x, y)	Perform the Ansari-Bradley test for equal scale parameters.
<i>bartlett</i> (*args)	Perform Bartlett's test for equal variances.
<i>levene</i> (*args[, center, proportiontocut])	Perform Levene test for equal variances.
<i>shapiro</i> (x)	Perform the Shapiro-Wilk test for normality.
<i>anderson</i> (x[, dist])	Anderson-Darling test for data coming from a particular distribution.
<i>anderson_ksamp</i> (samples[, midrank])	The Anderson-Darling test for k-samples.
<i>binom_test</i> (x[, n, p, alternative])	Perform a test that the probability of success is p.
<i>fligner</i> (*args[, center, proportiontocut])	Perform Fligner-Killeen test for equality of variance.
<i>median_test</i> (*args[, ties, correction, ...])	Perform a Mood's median test.
<i>mood</i> (x, y[, axis])	Perform Mood's test for equal scale parameters.
<i>skewtest</i> (a[, axis, nan_policy])	Test whether the skew is different from the normal distribution.
<i>kurtosistest</i> (a[, axis, nan_policy])	Test whether a dataset has normal kurtosis.
<i>normaltest</i> (a[, axis, nan_policy])	Test whether a sample differs from a normal distribution.

scipy.stats.ansari

`scipy.stats.ansari(x, y)`

Perform the Ansari-Bradley test for equal scale parameters.

The Ansari-Bradley test ([1], [2]) is a non-parametric test for the equality of the scale parameter of the distributions from which two samples were drawn.

Parameters

x, y [array_like] Arrays of sample data.

Returns

statistic [float] The Ansari-Bradley test statistic.
pvalue [float] The p-value of the hypothesis test.

See also:

fligner

A non-parametric test for the equality of k variances

mood

A non-parametric test for the equality of two scale parameters

Notes

The p-value given is exact when the sample sizes are both less than 55 and there are no ties, otherwise a normal approximation for the p-value is used.

References

[1], [2]

Examples

```
>>> from scipy.stats import ansari
```

For these examples, we'll create three random data sets. The first two, with sizes 35 and 25, are drawn from a normal distribution with mean 0 and standard deviation 2. The third data set has size 25 and is drawn from a normal distribution with standard deviation 1.25.

```
>>> np.random.seed(1234567890)
>>> x1 = np.random.normal(loc=0, scale=2, size=35)
>>> x2 = np.random.normal(loc=0, scale=2, size=25)
>>> x3 = np.random.normal(loc=0, scale=1.25, size=25)
```

First we apply *ansari* to *x1* and *x2*. These samples are drawn from the same distribution, so we expect the Ansari-Bradley test should not lead us to conclude that the scales of the distributions are different.

```
>>> ansari(x1, x2)
AnsariResult(statistic=511.0, pvalue=0.35506083719834347)
```

With a p-value of 0.355, we cannot conclude that there is a significant difference in the scales (as expected).

Now apply the test to *x1* and *x3*:

```
>>> ansari(x1, x3)
AnsariResult(statistic=452.0, pvalue=0.006280278681971285)
```

With a p-value of 0.00628, the test provides strong evidence that the scales of the distributions from which the samples were drawn are not equal.

scipy.stats.bartlett

`scipy.stats.bartlett` (*args)

Perform Bartlett's test for equal variances.

Bartlett's test tests the null hypothesis that all input samples are from populations with equal variances. For samples from significantly non-normal populations, Levene's test `levene` is more robust.

Parameters

sample1, sample2,...

[array_like] arrays of sample data. Only 1d arrays are accepted, they may have different lengths.

Returns

statistic [float] The test statistic.
pvalue [float] The p-value of the test.

See also:

`fligner`

A non-parametric test for the equality of k variances

`levene`

A robust parametric test for equality of k variances

Notes

Conover et al. (1981) examine many of the existing parametric and nonparametric tests by extensive simulations and they conclude that the tests proposed by Fligner and Killeen (1976) and Levene (1960) appear to be superior in terms of robustness of departures from normality and power ([3]).

References

[1], [2], [3], [4]

Examples

Test whether or not the lists *a*, *b* and *c* come from populations with equal variances.

```

>>> from scipy.stats import bartlett
>>> a = [8.88, 9.12, 9.04, 8.98, 9.00, 9.08, 9.01, 8.85, 9.06, 8.99]
>>> b = [8.88, 8.95, 9.29, 9.44, 9.15, 9.58, 8.36, 9.18, 8.67, 9.05]
>>> c = [8.95, 9.12, 8.95, 8.85, 9.03, 8.84, 9.07, 8.98, 8.86, 8.98]
>>> stat, p = bartlett(a, b, c)
>>> p
1.1254782518834628e-05

```

The very small p-value suggests that the populations do not have equal variances.

This is not surprising, given that the sample variance of *b* is much larger than that of *a* and *c*:

```

>>> [np.var(x, ddof=1) for x in [a, b, c]]
[0.007054444444444413, 0.13073888888888888, 0.008890000000000002]

```

scipy.stats.levene

`scipy.stats.levene` (*args, center='median', proportiontocut=0.05)

Perform Levene test for equal variances.

The Levene test tests the null hypothesis that all input samples are from populations with equal variances. Levene's test is an alternative to Bartlett's test `bartlett` in the case where there are significant deviations from normality.

Parameters

sample1, sample2, ...

[array_like] The sample data, possibly with different lengths. Only one-dimensional samples are accepted.

center [{"mean", "median", "trimmed"}, optional] Which function of the data to use in the test. The default is "median".

proportiontocut

[float, optional] When `center` is "trimmed", this gives the proportion of data points to cut from each end. (See `scipy.stats.trim_mean`.) Default is 0.05.

Returns

statistic [float] The test statistic.

pvalue [float] The p-value for the test.

Notes

Three variations of Levene's test are possible. The possibilities and their recommended usages are:

- 'median' : Recommended for skewed (non-normal) distributions>
- 'mean' : Recommended for symmetric, moderate-tailed distributions.
- 'trimmed' : Recommended for heavy-tailed distributions.

The test version using the mean was proposed in the original article of Levene ([2]) while the median and trimmed mean have been studied by Brown and Forsythe ([3]), sometimes also referred to as Brown-Forsythe test.

References

[1], [2], [3]

Examples

Test whether or not the lists `a`, `b` and `c` come from populations with equal variances.

```
>>> from scipy.stats import levene
>>> a = [8.88, 9.12, 9.04, 8.98, 9.00, 9.08, 9.01, 8.85, 9.06, 8.99]
>>> b = [8.88, 8.95, 9.29, 9.44, 9.15, 9.58, 8.36, 9.18, 8.67, 9.05]
>>> c = [8.95, 9.12, 8.95, 8.85, 9.03, 8.84, 9.07, 8.98, 8.86, 8.98]
>>> stat, p = levene(a, b, c)
>>> p
0.002431505967249681
```

The small p-value suggests that the populations do not have equal variances.

This is not surprising, given that the sample variance of `b` is much larger than that of `a` and `c`:

```
>>> [np.var(x, ddof=1) for x in [a, b, c]]
[0.007054444444444413, 0.13073888888888888, 0.008890000000000002]
```

scipy.stats.shapiro

`scipy.stats.shapiro(x)`

Perform the Shapiro-Wilk test for normality.

The Shapiro-Wilk test tests the null hypothesis that the data was drawn from a normal distribution.

Parameters

x [array_like] Array of sample data.

Returns

statistic [float] The test statistic.

p-value [float] The p-value for the hypothesis test.

See also:

[anderson](#)

The Anderson-Darling test for normality

[kstest](#)

The Kolmogorov-Smirnov test for goodness of fit.

Notes

The algorithm used is described in [4] but censoring parameters as described are not implemented. For $N > 5000$ the W test statistic is accurate but the p-value may not be.

The chance of rejecting the null hypothesis when it is true is close to 5% regardless of sample size.

References

[1], [2], [3], [4]

Examples

```
>>> from scipy import stats
>>> np.random.seed(12345678)
>>> x = stats.norm.rvs(loc=5, scale=3, size=100)
>>> shapiro_test = stats.shapiro(x)
>>> shapiro_test
ShapiroResult(statistic=0.9772805571556091, pvalue=0.08144091814756393)
>>> shapiro_test.statistic
0.9772805571556091
>>> shapiro_test.pvalue
0.08144091814756393
```

scipy.stats.anderson

`scipy.stats.anderson` (*x*, *dist*='norm')

Anderson-Darling test for data coming from a particular distribution.

The Anderson-Darling test tests the null hypothesis that a sample is drawn from a population that follows a particular distribution. For the Anderson-Darling test, the critical values depend on which distribution is being tested against. This function works for normal, exponential, logistic, or Gumbel (Extreme Value Type I) distributions.

Parameters

x [array_like] Array of sample data.
dist [{‘norm’, ‘expon’, ‘logistic’, ‘gumbel’, ‘gumbel_l’, ‘gumbel_r’, ‘extreme1’}, optional] The type of distribution to test against. The default is ‘norm’. The names ‘extreme1’, ‘gumbel_l’ and ‘gumbel’ are synonyms for the same distribution.

Returns

statistic [float] The Anderson-Darling test statistic.
critical_values [list] The critical values for this distribution.
significance_level [list] The significance levels for the corresponding critical values in percents. The function returns critical values for a differing set of significance levels depending on the distribution that is being tested against.

See also:

kstest

The Kolmogorov-Smirnov test for goodness-of-fit.

Notes

Critical values provided are for the following significance levels:

normal/exponential

15%, 10%, 5%, 2.5%, 1%

logistic

25%, 10%, 5%, 2.5%, 1%, 0.5%

Gumbel

25%, 10%, 5%, 2.5%, 1%

If the returned statistic is larger than these critical values then for the corresponding significance level, the null hypothesis that the data come from the chosen distribution can be rejected. The returned statistic is referred to as ‘A2’ in the references.

References

[1], [2], [3], [4], [5], [6]

scipy.stats.anderson_ksamp

`scipy.stats.anderson_ksamp` (*samples*, *midrank=True*)

The Anderson-Darling test for k-samples.

The k-sample Anderson-Darling test is a modification of the one-sample Anderson-Darling test. It tests the null hypothesis that k-samples are drawn from the same population without having to specify the distribution function of that population. The critical values depend on the number of samples.

Parameters

samples [sequence of 1-D array_like] Array of sample data in arrays.
midrank [bool, optional] Type of Anderson-Darling test which is computed. Default (True) is the midrank test applicable to continuous and discrete populations. If False, the right side empirical distribution is used.

Returns

statistic [float] Normalized k-sample Anderson-Darling test statistic.
critical_values [array] The critical values for significance levels 25%, 10%, 5%, 2.5%, 1%, 0.5%, 0.1%.
significance_level [float] An approximate significance level at which the null hypothesis for the provided samples can be rejected. The value is floored / capped at 0.1% / 25%.

Raises

ValueError
 If less than 2 samples are provided, a sample is empty, or no distinct observations are in the samples.

See also:

ks_2samp

2 sample Kolmogorov-Smirnov test

anderson

1 sample Anderson-Darling test

Notes

[1] defines three versions of the k-sample Anderson-Darling test: one for continuous distributions and two for discrete distributions, in which ties between samples may occur. The default of this routine is to compute the version based on the midrank empirical distribution function. This test is applicable to continuous and discrete data. If midrank is set to False, the right side empirical distribution is used for a test for discrete data. According to [1], the two discrete test statistics differ only slightly if a few collisions due to round-off errors occur in the test not adjusted for ties between samples.

The critical values corresponding to the significance levels from 0.01 to 0.25 are taken from [1]. p-values are floored / capped at 0.1% / 25%. Since the range of critical values might be extended in future releases, it is recommended not to test $p == 0.25$, but rather $p >= 0.25$ (analogously for the lower bound).

New in version 0.14.0.

References

[1]

Examples

```
>>> from scipy import stats
>>> np.random.seed(314159)
```

The null hypothesis that the two random samples come from the same distribution can be rejected at the 5% level because the returned test value is greater than the critical value for 5% (1.961) but not at the 2.5% level. The interpolation gives an approximate significance level of 3.2%:

```
>>> stats.anderson_ksamp([np.random.normal(size=50),
... np.random.normal(loc=0.5, size=30)])
(2.4615796189876105,
 array([ 0.325,  1.226,  1.961,  2.718,  3.752,  4.592,  6.546]),
 0.03176687568842282)
```

The null hypothesis cannot be rejected for three samples from an identical distribution. The reported p-value (25%) has been capped and may not be very accurate (since it corresponds to the value 0.449 whereas the statistic is -0.731):

```
>>> stats.anderson_ksamp([np.random.normal(size=50),
... np.random.normal(size=30), np.random.normal(size=20)])
(-0.73091722665244196,
 array([ 0.44925884,  1.3052767 ,  1.9434184 ,  2.57696569,  3.41634856,
 4.07210043,  5.56419101]),
 0.25)
```

scipy.stats.binom_test

`scipy.stats.binom_test(x, n=None, p=0.5, alternative='two-sided')`

Perform a test that the probability of success is p .

This is an exact, two-sided test of the null hypothesis that the probability of success in a Bernoulli experiment is p .

Parameters

- x** [int or array_like] The number of successes, or if x has length 2, it is the number of successes and the number of failures.
- n** [int] The number of trials. This is ignored if x gives both the number of successes and failures.
- p** [float, optional] The hypothesized probability of success. $0 \leq p \leq 1$. The default value is $p = 0.5$.
- alternative** [{"two-sided", "greater", "less"}, optional] Indicates the alternative hypothesis. The default value is "two-sided".

Returns

- p-value** [float] The p-value of the hypothesis test.

References

[1]

Examples

```
>>> from scipy import stats
```

A car manufacturer claims that no more than 10% of their cars are unsafe. 15 cars are inspected for safety, 3 were found to be unsafe. Test the manufacturer's claim:

```
>>> stats.binom_test(3, n=15, p=0.1, alternative='greater')
0.18406106910639114
```

The null hypothesis cannot be rejected at the 5% level of significance because the returned p-value is greater than the critical value of 5%.

scipy.stats.fligner

`scipy.stats.fligner(*args, center='median', proportiontocut=0.05)`

Perform Fligner-Killeen test for equality of variance.

Fligner's test tests the null hypothesis that all input samples are from populations with equal variances. Fligner-Killeen's test is distribution free when populations are identical [2].

Parameters

sample1, sample2, ...

[array_like] Arrays of sample data. Need not be the same length.

center

[{'mean', 'median', 'trimmed'}, optional] Keyword argument controlling which function of the data is used in computing the test statistic. The default is 'median'.

proportiontocut

[float, optional] When *center* is 'trimmed', this gives the proportion of data points to cut from each end. (See `scipy.stats.trim_mean`.) Default is 0.05.

Returns

statistic

[float] The test statistic.

pvalue

[float] The p-value for the hypothesis test.

See also:

[bartlett](#)

A parametric test for equality of k variances in normal samples

[levene](#)

A robust parametric test for equality of k variances

Notes

As with Levene’s test there are three variants of Fligner’s test that differ by the measure of central tendency used in the test. See *levene* for more information.

Conover et al. (1981) examine many of the existing parametric and nonparametric tests by extensive simulations and they conclude that the tests proposed by Fligner and Killeen (1976) and Levene (1960) appear to be superior in terms of robustness of departures from normality and power [3].

References

[1], [2], [3], [4]

Examples

Test whether or not the lists *a*, *b* and *c* come from populations with equal variances.

```
>>> from scipy.stats import fligner
>>> a = [8.88, 9.12, 9.04, 8.98, 9.00, 9.08, 9.01, 8.85, 9.06, 8.99]
>>> b = [8.88, 8.95, 9.29, 9.44, 9.15, 9.58, 8.36, 9.18, 8.67, 9.05]
>>> c = [8.95, 9.12, 8.95, 8.85, 9.03, 8.84, 9.07, 8.98, 8.86, 8.98]
>>> stat, p = fligner(a, b, c)
>>> p
0.00450826080004775
```

The small p-value suggests that the populations do not have equal variances.

This is not surprising, given that the sample variance of *b* is much larger than that of *a* and *c*:

```
>>> [np.var(x, ddof=1) for x in [a, b, c]]
[0.007054444444444413, 0.13073888888888888, 0.008890000000000002]
```

scipy.stats.median_test

`scipy.stats.median_test(*args, ties='below', correction=True, lambda_=1, nan_policy='propagate')`
Perform a Mood’s median test.

Test that two or more samples come from populations with the same median.

Let $n = \text{len}(\text{args})$ be the number of samples. The “grand median” of all the data is computed, and a contingency table is formed by classifying the values in each sample as being above or below the grand median. The contingency table, along with *correction* and *lambda_*, are passed to `scipy.stats.chi2_contingency` to compute the test statistic and p-value.

Parameters

sample1, sample2, ...

[array_like] The set of samples. There must be at least two samples. Each sample must be a one-dimensional sequence containing at least one value. The samples are not required to have the same length.

ties [str, optional] Determines how values equal to the grand median are classified in the contingency table. The string must be one of:

```

"below":
    Values equal to the grand median are counted as "below
↪".
"above":
    Values equal to the grand median are counted as "above
↪".
"ignore":
    Values equal to the grand median are not counted.

```

The default is “below”.

- correction** [bool, optional] If True, *and* there are just two samples, apply Yates’ correction for continuity when computing the test statistic associated with the contingency table. Default is True.
- lambda_** [float or str, optional] By default, the statistic computed in this test is Pearson’s chi-squared statistic. *lambda_* allows a statistic from the Cressie-Read power divergence family to be used instead. See *power_divergence* for details. Default is 1 (Pearson’s chi-squared statistic).
- nan_policy** [{‘propagate’, ‘raise’, ‘omit’}, optional] Defines how to handle when input contains nan. ‘propagate’ returns nan, ‘raise’ throws an error, ‘omit’ performs the calculations ignoring nan values. Default is ‘propagate’.

Returns

- stat** [float] The test statistic. The statistic that is returned is determined by *lambda_*. The default is Pearson’s chi-squared statistic.
- p** [float] The p-value of the test.
- m** [float] The grand median.
- table** [ndarray] The contingency table. The shape of the table is (2, n), where n is the number of samples. The first row holds the counts of the values above the grand median, and the second row holds the counts of the values below the grand median. The table allows further analysis with, for example, *scipy.stats.chi2_contingency*, or with *scipy.stats.fisher_exact* if there are two samples, without having to recompute the table. If *nan_policy* is “propagate” and there are nans in the input, the return value for *table* is None.

See also:

kruskal

Compute the Kruskal-Wallis H-test for independent samples.

mannwhitneyu

Computes the Mann-Whitney rank test on samples x and y.

Notes

New in version 0.15.0.

References

[1], [2]

Examples

A biologist runs an experiment in which there are three groups of plants. Group 1 has 16 plants, group 2 has 15 plants, and group 3 has 17 plants. Each plant produces a number of seeds. The seed counts for each group are:

```
Group 1: 10 14 14 18 20 22 24 25 31 31 32 39 43 43 48 49
Group 2: 28 30 31 33 34 35 36 40 44 55 57 61 91 92 99
Group 3: 0 3 9 22 23 25 25 33 34 34 40 45 46 48 62 67 84
```

The following code applies Mood's median test to these samples.

```
>>> g1 = [10, 14, 14, 18, 20, 22, 24, 25, 31, 31, 32, 39, 43, 43, 48, 49]
>>> g2 = [28, 30, 31, 33, 34, 35, 36, 40, 44, 55, 57, 61, 91, 92, 99]
>>> g3 = [0, 3, 9, 22, 23, 25, 25, 33, 34, 34, 40, 45, 46, 48, 62, 67, 84]
>>> from scipy.stats import median_test
>>> stat, p, med, tbl = median_test(g1, g2, g3)
```

The median is

```
>>> med
34.0
```

and the contingency table is

```
>>> tbl
array([[ 5, 10,  7],
       [11,  5, 10]])
```

p is too large to conclude that the medians are not the same:

```
>>> p
0.12609082774093244
```

The "G-test" can be performed by passing `lambda_="log-likelihood"` to `median_test`.

```
>>> g, p, med, tbl = median_test(g1, g2, g3, lambda_="log-likelihood")
>>> p
0.12224779737117837
```

The median occurs several times in the data, so we'll get a different result if, for example, `ties="above"` is used:

```
>>> stat, p, med, tbl = median_test(g1, g2, g3, ties="above")
>>> p
0.063873276069553273
```

```
>>> tbl
array([[ 5, 11,  9],
       [11,  4,  8]])
```

This example demonstrates that if the data set is not large and there are values equal to the median, the p-value can be sensitive to the choice of *ties*.

scipy.stats.mood

`scipy.stats.mood(x, y, axis=0)`

Perform Mood's test for equal scale parameters.

Mood's two-sample test for scale parameters is a non-parametric test for the null hypothesis that two samples are drawn from the same distribution with the same scale parameter.

Parameters

x, y [array_like] Arrays of sample data.
axis [int, optional] The axis along which the samples are tested. *x* and *y* can be of different length along *axis*. If *axis* is None, *x* and *y* are flattened and the test is done on all values in the flattened arrays.

Returns

z [scalar or ndarray] The z-score for the hypothesis test. For 1-D inputs a scalar is returned.
p-value [scalar ndarray] The p-value for the hypothesis test.

See also:

[*fligner*](#)

A non-parametric test for the equality of k variances

[*ansari*](#)

A non-parametric test for the equality of 2 variances

[*bartlett*](#)

A parametric test for equality of k variances in normal samples

[*levene*](#)

A parametric test for equality of k variances

Notes

The data are assumed to be drawn from probability distributions $f(x)$ and $f(x/s) / s$ respectively, for some probability density function f . The null hypothesis is that $s == 1$.

For multi-dimensional arrays, if the inputs are of shapes (n_0, n_1, n_2, n_3) and (n_0, m_1, n_2, n_3) , then if `axis=1`, the resulting z and p values will have shape (n_0, n_2, n_3) . Note that n_1 and m_1 don't have to be equal, but the other dimensions do.

Examples

```
>>> from scipy import stats
>>> np.random.seed(1234)
>>> x2 = np.random.randn(2, 45, 6, 7)
>>> x1 = np.random.randn(2, 30, 6, 7)
>>> z, p = stats.mood(x1, x2, axis=1)
>>> p.shape
(2, 6, 7)
```

Find the number of points where the difference in scale is not significant:

```
>>> (p > 0.1).sum()
74
```

Perform the test with different scales:

```
>>> x1 = np.random.randn(2, 30)
>>> x2 = np.random.randn(2, 35) * 10.0
>>> stats.mood(x1, x2, axis=1)
(array([-5.7178125 , -5.25342163]), array([ 1.07904114e-08,  1.
→49299218e-07]))
```

scipy.stats.skewtest

`scipy.stats.skewtest` (*a*, *axis=0*, *nan_policy='propagate'*)

Test whether the skew is different from the normal distribution.

This function tests the null hypothesis that the skewness of the population that the sample was drawn from is the same as that of a corresponding normal distribution.

Parameters

- a** [array] The data to be tested.
- axis** [int or None, optional] Axis along which statistics are calculated. Default is 0. If None, compute over the whole array *a*.
- nan_policy** [{‘propagate’, ‘raise’, ‘omit’}, optional] Defines how to handle when input contains nan. The following options are available (default is ‘propagate’):
 - ‘propagate’: returns nan
 - ‘raise’: throws an error
 - ‘omit’: performs the calculations ignoring nan values

Returns

- statistic** [float] The computed z-score for this test.
- pvalue** [float] Two-sided p-value for the hypothesis test.

Notes

The sample size must be at least 8.

References

[1]

Examples

```

>>> from scipy.stats import skewtest
>>> skewtest([1, 2, 3, 4, 5, 6, 7, 8])
SkewtestResult(statistic=1.0108048609177787, pvalue=0.3121098361421897)
>>> skewtest([2, 8, 0, 4, 1, 9, 9, 0])
SkewtestResult(statistic=0.44626385374196975, pvalue=0.6554066631275459)
>>> skewtest([1, 2, 3, 4, 5, 6, 7, 8000])
SkewtestResult(statistic=3.571773510360407, pvalue=0.0003545719905823133)
>>> skewtest([100, 100, 100, 100, 100, 100, 100, 101])
SkewtestResult(statistic=3.5717766638478072, pvalue=0.000354567720281634)

```

scipy.stats.kurtosistest

`scipy.stats.kurtosistest` (*a*, *axis=0*, *nan_policy='propagate'*)

Test whether a dataset has normal kurtosis.

This function tests the null hypothesis that the kurtosis of the population from which the sample was drawn is that of the normal distribution: $kurtosis = 3(n-1)/(n+1)$.

Parameters

- a** [array] Array of the sample data.
- axis** [int or None, optional] Axis along which to compute test. Default is 0. If None, compute over the whole array *a*.
- nan_policy** [{‘propagate’, ‘raise’, ‘omit’}, optional] Defines how to handle when input contains nan. The following options are available (default is ‘propagate’):
 - ‘propagate’: returns nan
 - ‘raise’: throws an error
 - ‘omit’: performs the calculations ignoring nan values

Returns

- statistic** [float] The computed z-score for this test.
- pvalue** [float] The two-sided p-value for the hypothesis test.

Notes

Valid only for $n > 20$. This function uses the method described in [1].

References

[1]

Examples

```
>>> from scipy.stats import kurtosistest
>>> kurtosistest(list(range(20)))
KurtosistestResult(statistic=-1.7058104152122062, pvalue=0.
↳08804338332528348)
```

```
>>> np.random.seed(28041990)
>>> s = np.random.normal(0, 1, 1000)
>>> kurtosistest(s)
KurtosistestResult(statistic=1.2317590987707365, pvalue=0.
↳21803908613450895)
```

scipy.stats.normaltest

`scipy.stats.normaltest` (*a*, *axis*=0, *nan_policy*='propagate')

Test whether a sample differs from a normal distribution.

This function tests the null hypothesis that a sample comes from a normal distribution. It is based on D'Agostino and Pearson's [1], [2] test that combines skew and kurtosis to produce an omnibus test of normality.

Parameters

- a** [array_like] The array containing the sample to be tested.
- axis** [int or None, optional] Axis along which to compute test. Default is 0. If None, compute over the whole array *a*.
- nan_policy** [{'propagate', 'raise', 'omit'}, optional] Defines how to handle when input contains nan. The following options are available (default is 'propagate'):
- 'propagate': returns nan
 - 'raise': throws an error
 - 'omit': performs the calculations ignoring nan values

Returns

- statistic** [float or array] $s^2 + k^2$, where *s* is the z-score returned by `skewtest` and *k* is the z-score returned by `kurtosistest`.
- pvalue** [float or array] A 2-sided chi squared probability for the hypothesis test.

References

[1], [2]

Examples

```
>>> from scipy import stats
>>> pts = 1000
>>> np.random.seed(28041990)
>>> a = np.random.normal(0, 1, size=pts)
>>> b = np.random.normal(2, 1, size=pts)
>>> x = np.concatenate((a, b))
>>> k2, p = stats.normaltest(x)
>>> alpha = 1e-3
>>> print("p = {:g}".format(p))
p = 3.27207e-11
>>> if p < alpha: # null hypothesis: x comes from a normal distribution
...     print("The null hypothesis can be rejected")
... else:
...     print("The null hypothesis cannot be rejected")
The null hypothesis can be rejected
```

6.29.11 Transformations

<code>boxcox(x[, lmbda, alpha])</code>	Return a dataset transformed by a Box-Cox power transformation.
<code>boxcox_normmax(x[, brack, method])</code>	Compute optimal Box-Cox transform parameter for input data.
<code>boxcox_llf(lmb, data)</code>	The boxcox log-likelihood function.
<code>yeojohnson(x[, lmbda])</code>	Return a dataset transformed by a Yeo-Johnson power transformation.
<code>yeojohnson_normmax(x[, brack])</code>	Compute optimal Yeo-Johnson transform parameter.
<code>yeojohnson_llf(lmb, data)</code>	The yeojohnson log-likelihood function.
<code>obrientransform(*args)</code>	Compute the O'Brien transform on input data (any number of arrays).
<code>sigmaclip(a[, low, high])</code>	Perform iterative sigma-clipping of array elements.
<code>trimboth(a, proportiontocut[, axis])</code>	Slice off a proportion of items from both ends of an array.
<code>trim1(a, proportiontocut[, tail, axis])</code>	Slice off a proportion from ONE end of the passed array distribution.
<code>zmap(scores, compare[, axis, ddof])</code>	Calculate the relative z-scores.
<code>zscore(a[, axis, ddof, nan_policy])</code>	Compute the z score.

scipy.stats.boxcox

`scipy.stats.boxcox(x, lambda=None, alpha=None)`

Return a dataset transformed by a Box-Cox power transformation.

Parameters

- x** [ndarray] Input array. Must be positive 1-dimensional. Must not be constant.
- lambda** [{None, scalar}, optional] If *lambda* is not None, do the transformation for that value. If *lambda* is None, find the lambda that maximizes the log-likelihood function and return it as the second output argument.
- alpha** [{None, float}, optional] If *alpha* is not None, return the $100 * (1-\alpha)\%$ confidence interval for *lambda* as the third output argument. Must be between 0.0 and 1.0.

Returns

- boxcox** [ndarray] Box-Cox power transformed array.
- maxlog** [float, optional] If the *lambda* parameter is None, the second returned argument is the lambda that maximizes the log-likelihood function.
- (min_ci, max_ci)** [tuple of float, optional] If *lambda* parameter is None and *alpha* is not None, this returned tuple of floats represents the minimum and maximum confidence limits given *alpha*.

See also:

[*probplot*](#), [*boxcox_normplot*](#), [*boxcox_normmax*](#), [*boxcox_llf*](#)

Notes

The Box-Cox transform is given by:

$$y = \begin{cases} (x^{\lambda} - 1) / \lambda, & \text{for } \lambda \neq 0 \\ \log(x), & \text{for } \lambda = 0 \end{cases}$$

boxcox requires the input data to be positive. Sometimes a Box-Cox transformation provides a shift parameter to achieve this; *boxcox* does not. Such a shift parameter is equivalent to adding a positive constant to *x* before calling *boxcox*.

The confidence limits returned when *alpha* is provided give the interval where:

$$llf(\hat{\lambda}) - llf(\lambda) < \frac{1}{2}\chi^2(1 - \alpha, 1),$$

with *llf* the log-likelihood function and χ^2 the chi-squared function.

References

G.E.P. Box and D.R. Cox, “An Analysis of Transformations”, Journal of the Royal Statistical Society B, 26, 211-252 (1964).

Examples

```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
```


We generate some random variates from a non-normal distribution and make a probability plot for it, to show it is non-normal in the tails:

```
>>> fig = plt.figure()
>>> ax1 = fig.add_subplot(211)
>>> x = stats.loggamma.rvs(5, size=500) + 5
>>> prob = stats.probplot(x, dist=stats.norm, plot=ax1)
>>> ax1.set_xlabel('')
>>> ax1.set_title('Probplot against normal distribution')
```

We now use `boxcox` to transform the data so it's closest to normal:

```
>>> ax2 = fig.add_subplot(212)
>>> xt, _ = stats.boxcox(x)
>>> prob = stats.probplot(xt, dist=stats.norm, plot=ax2)
>>> ax2.set_title('Probplot after Box-Cox transformation')
```

```
>>> plt.show()
```



scipy.stats.boxcox_normmax

```
scipy.stats.boxcox_normmax(x, brack=(- 2.0, 2.0, method='pearsonr')
```

Compute optimal Box-Cox transform parameter for input data.

Parameters

x	[array_like] Input array.
brack	[2-tuple, optional] The starting interval for a downhill bracket search with <i>optimize.brent</i> . Note that this is in most cases not critical; the final result is allowed to be outside this bracket.
method	[str, optional] The method to determine the optimal transform parameter (<i>boxcox</i> lambda parameter). Options are: 'pearsonr' (default) Maximizes the Pearson correlation coefficient between $y = \text{boxcox}(x)$ and the expected values for y if x would be normally-distributed. 'mle' Minimizes the log-likelihood <i>boxcox_llf</i> . This is the method used in <i>boxcox</i> . 'all' Use all optimization methods available, and return all results. Useful to compare different methods.

Returns

maxlog	[float or ndarray] The optimal transform parameter found. An array instead of a scalar for <code>method='all'</code> .
---------------	--

See also:

[boxcox](#), [boxcox_llf](#), [boxcox_normplot](#)

Examples

```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
>>> np.random.seed(1234) # make this example reproducible
```


Generate some data and determine optimal lambda in various ways:

```
>>> x = stats.loggamma.rvs(5, size=30) + 5
>>> y, lmax_mle = stats.boxcox(x)
>>> lmax_pearsonr = stats.boxcox_normmax(x)
```

```
>>> lmax_mle
7.177...
>>> lmax_pearsonr
7.916...
>>> stats.boxcox_normmax(x, method='all')
array([ 7.91667384,  7.17718692])
```

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> prob = stats.boxcox_normplot(x, -10, 10, plot=ax)
>>> ax.axvline(lmax_mle, color='r')
>>> ax.axvline(lmax_pearsonr, color='g', ls='--')
```

```
>>> plt.show()
```



scipy.stats.boxcox_llf

`scipy.stats.boxcox_llf` (*lmb*, *data*)

The boxcox log-likelihood function.

Parameters

lmb [scalar] Parameter for Box-Cox transformation. See `boxcox` for details.
data [array_like] Data to calculate Box-Cox log-likelihood for. If *data* is multi-dimensional, the log-likelihood is calculated along the first axis.

Returns

llf [float or ndarray] Box-Cox log-likelihood of *data* given *lmb*. A float for 1-D *data*, an array otherwise.

See also:

`boxcox`, `probplot`, `boxcox_normplot`, `boxcox_normmax`

Notes

The Box-Cox log-likelihood function is defined here as

$$llf = (\lambda - 1) \sum_i (\log(x_i)) - N/2 \log(\sum_i (y_i - \bar{y})^2 / N),$$

where y is the Box-Cox transformed input data x .

Examples

```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
>>> from mpl_toolkits.axes_grid1.inset_locator import inset_axes
>>> np.random.seed(1245)
```

Generate some random variates and calculate Box-Cox log-likelihood values for them for a range of lambda values:

```
>>> x = stats.loggamma.rvs(5, loc=10, size=1000)
>>> lmbdas = np.linspace(-2, 10)
>>> llf = np.zeros(lmbdas.shape, dtype=float)
>>> for ii, lambda in enumerate(lmbdas):
...     llf[ii] = stats.boxcox_llf(lambda, x)
```

Also find the optimal lambda value with `boxcox`:

```
>>> x_most_normal, lambda_optimal = stats.boxcox(x)
```


Plot the log-likelihood as function of lambda. Add the optimal lambda as a horizontal line to check that that's really the optimum:

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> ax.plot(lmbdas, llf, 'b.-')
>>> ax.axhline(stats.boxcox_llf(lambda_optimal, x), color='r')
>>> ax.set_xlabel('lambda parameter')
>>> ax.set_ylabel('Box-Cox log-likelihood')
```

Now add some probability plots to show that where the log-likelihood is maximized the data transformed with `boxcox` looks closest to normal:

```
>>> locs = [3, 10, 4] # 'lower left', 'center', 'lower right'
>>> for lambda, loc in zip([-1, lambda_optimal, 9], locs):
...     xt = stats.boxcox(x, lambda=lambda)
...     (osm, osr), (slope, intercept, r_sq) = stats.probplot(xt)
...     ax_inset = inset_axes(ax, width="20%", height="20%", loc=loc)
...     ax_inset.plot(osm, osr, 'c.', osm, slope*osm + intercept, 'k-')
...     ax_inset.set_xticklabels([])
...     ax_inset.set_yticklabels([])
...     ax_inset.set_title(r'$\lambda=%1.2f$' % lambda)
```

```
>>> plt.show()
```



scipy.stats.yeojohnson

`scipy.stats.yeojohnson` (*x*, *lmbda*=None)

Return a dataset transformed by a Yeo-Johnson power transformation.

Parameters

- x** [ndarray] Input array. Should be 1-dimensional.
- lmbda** [float, optional] If *lmbda* is None, find the lambda that maximizes the log-likelihood function and return it as the second output argument. Otherwise the transformation is done for the given value.

Returns

- yeojohnson:** ndarray
Yeo-Johnson power transformed array.
- maxlog** [float, optional] If the *lmbda* parameter is None, the second returned argument is the lambda that maximizes the log-likelihood function.

See also:

[*probplot*](#), [*yeojohnson_normplot*](#), [*yeojohnson_normmax*](#), [*yeojohnson_llf*](#), [*boxcox*](#)

Notes

The Yeo-Johnson transform is given by:

$y = ((x + 1)**lmbda - 1) / lmbda,$	for $x \geq 0, lmbda \neq 0$
$\log(x + 1),$	for $x \geq 0, lmbda = 0$
$-((-x + 1)**(2 - lmbda) - 1) / (2 - lmbda),$	for $x < 0, lmbda \neq 2$
$-\log(-x + 1),$	for $x < 0, lmbda = 2$

Unlike *boxcox*, *yeojohnson* does not require the input data to be positive.

New in version 1.2.0.

References

I. Yeo and R.A. Johnson, “A New Family of Power Transformations to Improve Normality or Symmetry”, *Biometrika* 87.4 (2000):

Examples

```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
```


We generate some random variates from a non-normal distribution and make a probability plot for it, to show it is non-normal in the tails:

```
>>> fig = plt.figure()
>>> ax1 = fig.add_subplot(211)
>>> x = stats.loggamma.rvs(5, size=500) + 5
>>> prob = stats.probplot(x, dist=stats.norm, plot=ax1)
>>> ax1.set_xlabel('')
>>> ax1.set_title('Probplot against normal distribution')
```

We now use `yeojohnson` to transform the data so it's closest to normal:

```
>>> ax2 = fig.add_subplot(212)
>>> xt, lambda = stats.yeojohnson(x)
>>> prob = stats.probplot(xt, dist=stats.norm, plot=ax2)
>>> ax2.set_title('Probplot after Yeo-Johnson transformation')
```

```
>>> plt.show()
```



scipy.stats.yeojohnson_normmax

`scipy.stats.yeojohnson_normmax(x, brack=-2, 2)`

Compute optimal Yeo-Johnson transform parameter.

Compute optimal Yeo-Johnson transform parameter for input data, using maximum likelihood estimation.

Parameters

x	[array_like] Input array.
brack	[2-tuple, optional] The starting interval for a downhill bracket search with <i>optimize.brent</i> . Note that this is in most cases not critical; the final result is allowed to be outside this bracket.

Returns

maxlog	[float] The optimal transform parameter found.
---------------	--

See also:

[yeojohnson](#), [yeojohnson_llf](#), [yeojohnson_normplot](#)

Notes

New in version 1.2.0.

Examples

```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
>>> np.random.seed(1234) # make this example reproducible
```

Generate some data and determine optimal lambda

```
>>> x = stats.loggamma.rvs(5, size=30) + 5
>>> lmax = stats.yeojohnson_normmax(x)
```

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> prob = stats.yeojohnson_normplot(x, -10, 10, plot=ax)
>>> ax.axvline(lmax, color='r')
```

```
>>> plt.show()
```

scipy.stats.yeojohnson_llf


`scipy.stats.yeojohnson_llf(lmb, data)`

The yeojohnson log-likelihood function.

Parameters

lmb	[scalar] Parameter for Yeo-Johnson transformation. See yeojohnson for details.
data	[array_like] Data to calculate Yeo-Johnson log-likelihood for. If <i>data</i> is multi-dimensional, the log-likelihood is calculated along the first axis.

Returns



llf [float] Yeo-Johnson log-likelihood of *data* given *lmb*.

See also:

[yeojohnson](#), [probplot](#), [yeojohnson_normplot](#), [yeojohnson_normmax](#)

Notes

The Yeo-Johnson log-likelihood function is defined here as

$$llf = N/2 \log(\hat{\sigma}^2) + (\lambda - 1) \sum_i \text{sign}(x_i) \log(|x_i| + 1)$$

where $\hat{\sigma}^2$ is estimated variance of the the Yeo-Johnson transformed input data x .

New in version 1.2.0.

Examples

```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
>>> from mpl_toolkits.axes_grid1.inset_locator import inset_axes
>>> np.random.seed(1245)
```

Generate some random variates and calculate Yeo-Johnson log-likelihood values for them for a range of *lmbda* values:

```
>>> x = stats.loggamma.rvs(5, loc=10, size=1000)
>>> lmbdas = np.linspace(-2, 10)
>>> llf = np.zeros(lmbdas.shape, dtype=float)
>>> for ii, lmbda in enumerate(lmbdas):
...     llf[ii] = stats.yeojohnson_llf(lmbda, x)
```

Also find the optimal *lmbda* value with [yeojohnson](#):

```
>>> x_most_normal, lambda_optimal = stats.yeojohnson(x)
```


Plot the log-likelihood as function of lambda. Add the optimal lambda as a horizontal line to check that that's really the optimum:

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> ax.plot(lmbdas, llf, 'b.-')
>>> ax.axhline(stats.yeojohnson_llf(lambda_optimal, x), color='r')
>>> ax.set_xlabel('lambda parameter')
>>> ax.set_ylabel('Yeo-Johnson log-likelihood')
```

Now add some probability plots to show that where the log-likelihood is maximized the data transformed with *yeojohnson* looks closest to normal:

```
>>> locs = [3, 10, 4] # 'lower left', 'center', 'lower right'
>>> for lambda, loc in zip([-1, lambda_optimal, 9], locs):
...     xt = stats.yeojohnson(x, lambda=lambda)
...     (osm, osr), (slope, intercept, r_sq) = stats.probplot(xt)
...     ax_inset = inset_axes(ax, width="20%", height="20%", loc=loc)
...     ax_inset.plot(osm, osr, 'c.', osm, slope*osm + intercept, 'k-')
...     ax_inset.set_xticklabels([])
...     ax_inset.set_yticklabels([])
...     ax_inset.set_title(r'$\lambda=%1.2f$' % lambda)
```

```
>>> plt.show()
```



scipy.stats.obrientransform

`scipy.stats.obrientransform(*args)`

Compute the O'Brien transform on input data (any number of arrays).

Used to test for homogeneity of variance prior to running one-way stats. Each array in `*args` is one level of a factor. If `f_oneway` is run on the transformed data and found significant, the variances are unequal. From Maxwell and Delaney [1], p.112.

Parameters

args [tuple of array_like] Any number of arrays.

Returns

obrientransform

[ndarray] Transformed data for use in an ANOVA. The first dimension of the result corresponds to the sequence of transformed arrays. If the arrays given are all 1-D of the same length, the return value is a 2-D array; otherwise it is a 1-D array of type object, with each element being an ndarray.

References

[1]

Examples

We'll test the following data sets for differences in their variance.

```
>>> x = [10, 11, 13, 9, 7, 12, 12, 9, 10]
>>> y = [13, 21, 5, 10, 8, 14, 10, 12, 7, 15]
```

Apply the O'Brien transform to the data.

```
>>> from scipy.stats import obrientransform
>>> tx, ty = obrientransform(x, y)
```

Use `scipy.stats.f_oneway` to apply a one-way ANOVA test to the transformed data.

```
>>> from scipy.stats import f_oneway
>>> F, p = f_oneway(tx, ty)
>>> p
0.1314139477040335
```

If we require that $p < 0.05$ for significance, we cannot conclude that the variances are different.

scipy.stats.sigmaclip

`scipy.stats.sigmaclip(a, low=4.0, high=4.0)`

Perform iterative sigma-clipping of array elements.

Starting from the full sample, all elements outside the critical range are removed, i.e. all elements of the input array *c* that satisfy either of the following conditions:

```
c < mean(c) - std(c)*low
c > mean(c) + std(c)*high
```

The iteration continues with the updated sample until no elements are outside the (updated) range.

Parameters

a [array_like] Data array, will be raveled if not 1-D.
low [float, optional] Lower bound factor of sigma clipping. Default is 4.
high [float, optional] Upper bound factor of sigma clipping. Default is 4.

Returns

clipped [ndarray] Input array with clipped elements removed.
lower [float] Lower threshold value use for clipping.
upper [float] Upper threshold value use for clipping.

Examples

```
>>> from scipy.stats import sigmaclip
>>> a = np.concatenate((np.linspace(9.5, 10.5, 31),
...                     np.linspace(0, 20, 5)))
>>> fact = 1.5
>>> c, low, upp = sigmaclip(a, fact, fact)
>>> c
array([ 9.96666667, 10.          , 10.03333333, 10.          ])
>>> c.var(), c.std()
(0.00055555555555555165, 0.023570226039551501)
>>> low, c.mean() - fact*c.std(), c.min()
(9.9646446609406727, 9.9646446609406727, 9.9666666666666668)
>>> upp, c.mean() + fact*c.std(), c.max()
(10.035355339059327, 10.035355339059327, 10.033333333333333)
```

```
>>> a = np.concatenate((np.linspace(9.5, 10.5, 11),
...                     np.linspace(-100, -50, 3)))
>>> c, low, upp = sigmaclip(a, 1.8, 1.8)
>>> (c == np.linspace(9.5, 10.5, 11)).all()
True
```

scipy.stats.trimboth

`scipy.stats.trimboth(a, proportiontocut, axis=0)`

Slice off a proportion of items from both ends of an array.

Slice off the passed proportion of items from both ends of the passed array (i.e., with *proportiontocut* = 0.1, slices leftmost 10% **and** rightmost 10% of scores). The trimmed values are the lowest and highest ones. Slice off less if proportion results in a non-integer slice index (i.e. conservatively slices off *proportiontocut*).

Parameters

a [array_like] Data to trim.
proportiontocut [float] Proportion (in range 0-1) of total data set to trim of each end.
axis [int or None, optional] Axis along which to trim data. Default is 0. If None, compute over the whole array *a*.

Returns

out [ndarray] Trimmed version of array *a*. The order of the trimmed content is undefined.

See also:

[`trim_mean`](#)

Examples

```
>>> from scipy import stats
>>> a = np.arange(20)
>>> b = stats.trimboth(a, 0.1)
>>> b.shape
(16,)
```

scipy.stats.trim1

`scipy.stats.trim1(a, proportiontocut, tail='right', axis=0)`

Slice off a proportion from ONE end of the passed array distribution.

If *proportiontocut* = 0.1, slices off 'leftmost' or 'rightmost' 10% of scores. The lowest or highest values are trimmed (depending on the tail). Slice off less if proportion results in a non-integer slice index (i.e. conservatively slices off *proportiontocut*).

Parameters

a [array_like] Input array.
proportiontocut [float] Fraction to cut off of 'left' or 'right' of distribution.
tail [{'left', 'right'}, optional] Defaults to 'right'.
axis [int or None, optional] Axis along which to trim data. Default is 0. If None, compute over the whole array *a*.

Returns

trim1 [ndarray] Trimmed version of array *a*. The order of the trimmed content is undefined.

scipy.stats.zmap

`scipy.stats.zmap` (*scores*, *compare*, *axis=0*, *ddof=0*)

Calculate the relative z-scores.

Return an array of z-scores, i.e., scores that are standardized to zero mean and unit variance, where mean and variance are calculated from the comparison array.

Parameters

scores	[array_like] The input for which z-scores are calculated.
compare	[array_like] The input from which the mean and standard deviation of the normalization are taken; assumed to have the same dimension as <i>scores</i> .
axis	[int or None, optional] Axis over which mean and variance of <i>compare</i> are calculated. Default is 0. If None, compute over the whole array <i>scores</i> .
ddof	[int, optional] Degrees of freedom correction in the calculation of the standard deviation. Default is 0.

Returns

zscore	[array_like] Z-scores, in the same shape as <i>scores</i> .
---------------	---

Notes

This function preserves ndarray subclasses, and works also with matrices and masked arrays (it uses *asanyarray* instead of *asarray* for parameters).

Examples

```
>>> from scipy.stats import zmap
>>> a = [0.5, 2.0, 2.5, 3]
>>> b = [0, 1, 2, 3, 4]
>>> zmap(a, b)
array([-1.06066017,  0.          ,  0.35355339,  0.70710678])
```

scipy.stats.zscore

`scipy.stats.zscore` (*a*, *axis=0*, *ddof=0*, *nan_policy='propagate'*)

Compute the z score.

Compute the z score of each value in the sample, relative to the sample mean and standard deviation.

Parameters

a	[array_like] An array like object containing the sample data.
axis	[int or None, optional] Axis along which to operate. Default is 0. If None, compute over the whole array <i>a</i> .
ddof	[int, optional] Degrees of freedom correction in the calculation of the standard deviation. Default is 0.
nan_policy	[{'propagate', 'raise', 'omit'}, optional] Defines how to handle when input contains nan. 'propagate' returns nan, 'raise' throws an error, 'omit' performs the calculations ignoring nan values. Default is 'propagate'. Note that when the value is 'omit', nans in the input also propagate to the output, but they do not affect the z-scores computed for the non-nan values.

Returns

zscore [array_like] The z-scores, standardized by mean and standard deviation of input array *a*.

Notes

This function preserves ndarray subclasses, and works also with matrices and masked arrays (it uses *asanyarray* instead of *asarray* for parameters).

Examples

```
>>> a = np.array([ 0.7972,  0.0767,  0.4383,  0.7866,  0.8091,
...               0.1954,  0.6307,  0.6599,  0.1065,  0.0508])
>>> from scipy import stats
>>> stats.zscore(a)
array([ 1.1273, -1.247 , -0.0552,  1.0923,  1.1664, -0.8559,  0.5786,
        0.6748, -1.1488, -1.3324])
```

Computing along a specified axis, using n-1 degrees of freedom (ddof=1) to calculate the standard deviation:

```
>>> b = np.array([[ 0.3148,  0.0478,  0.6243,  0.4608],
...               [ 0.7149,  0.0775,  0.6072,  0.9656],
...               [ 0.6341,  0.1403,  0.9759,  0.4064],
...               [ 0.5918,  0.6948,  0.904 ,  0.3721],
...               [ 0.0921,  0.2481,  0.1188,  0.1366]])
>>> stats.zscore(b, axis=1, ddof=1)
array([[ -0.19264823, -1.28415119,  1.07259584,  0.40420358],
       [  0.33048416, -1.37380874,  0.04251374,  1.00081084],
       [  0.26796377, -1.12598418,  1.23283094, -0.37481053],
       [ -0.22095197,  0.24468594,  1.19042819, -1.21416216],
       [ -0.82780366,  1.4457416 , -0.43867764, -0.1792603 ]])
```

An example with *nan_policy='omit'*:

```
>>> x = np.array([[25.11, 30.10, np.nan, 32.02, 43.15],
...               [14.95, 16.06, 121.25, 94.35, 29.81]])
>>> stats.zscore(x, axis=1, nan_policy='omit')
array([[ -1.13490897, -0.37830299,          nan, -0.08718406,  1.60039602],
       [ -0.91611681, -0.89090508,  1.4983032 ,  0.88731639, -0.5785977 ]])
```

6.29.12 Statistical distances

<code>wasserstein_distance(u_values, v_values[, ...])</code>	Compute the first Wasserstein distance between two 1D distributions.
<code>energy_distance(u_values, v_values[, ...])</code>	Compute the energy distance between two 1D distributions.

scipy.stats.wasserstein_distance

`scipy.stats.wasserstein_distance` (*u_values*, *v_values*, *u_weights=None*, *v_weights=None*)

Compute the first Wasserstein distance between two 1D distributions.

This distance is also known as the earth mover’s distance, since it can be seen as the minimum amount of “work” required to transform *u* into *v*, where “work” is measured as the amount of distribution weight that must be moved, multiplied by the distance it has to be moved.

New in version 1.0.0.

Parameters**u_values, v_values**

[array_like] Values observed in the (empirical) distribution.

u_weights, v_weights

[array_like, optional] Weight for each value. If unspecified, each value is assigned the same weight. *u_weights* (resp. *v_weights*) must have the same length as *u_values* (resp. *v_values*). If the weight sum differs from 1, it must still be positive and finite so that the weights can be normalized to sum to 1.

Returns

distance [float] The computed distance between the distributions.

Notes

The first Wasserstein distance between the distributions *u* and *v* is:

$$l_1(u, v) = \inf_{\pi \in \Gamma(u, v)} \int_{\mathbb{R} \times \mathbb{R}} |x - y| d\pi(x, y)$$

where $\Gamma(u, v)$ is the set of (probability) distributions on $\mathbb{R} \times \mathbb{R}$ whose marginals are *u* and *v* on the first and second factors respectively.

If *U* and *V* are the respective CDFs of *u* and *v*, this distance also equals to:

$$l_1(u, v) = \int_{-\infty}^{+\infty} |U - V|$$

See [2] for a proof of the equivalence of both definitions.

The input distributions can be empirical, therefore coming from samples whose values are effectively inputs of the function, or they can be seen as generalized functions, in which case they are weighted sums of Dirac delta functions located at the specified values.

References

[1], [2]

Examples

```
>>> from scipy.stats import wasserstein_distance
>>> wasserstein_distance([0, 1, 3], [5, 6, 8])
5.0
>>> wasserstein_distance([0, 1], [0, 1], [3, 1], [2, 2])
0.25
>>> wasserstein_distance([3.4, 3.9, 7.5, 7.8], [4.5, 1.4],
...                       [1.4, 0.9, 3.1, 7.2], [3.2, 3.5])
4.0781331438047861
```

scipy.stats.energy_distance

`scipy.stats.energy_distance` (*u_values*, *v_values*, *u_weights=None*, *v_weights=None*)

Compute the energy distance between two 1D distributions.

New in version 1.0.0.

Parameters

u_values, v_values

[array_like] Values observed in the (empirical) distribution.

u_weights, v_weights

[array_like, optional] Weight for each value. If unspecified, each value is assigned the same weight. *u_weights* (resp. *v_weights*) must have the same length as *u_values* (resp. *v_values*). If the weight sum differs from 1, it must still be positive and finite so that the weights can be normalized to sum to 1.

Returns

distance [float] The computed distance between the distributions.

Notes

The energy distance between two distributions u and v , whose respective CDFs are U and V , equals to:

$$D(u, v) = (2\mathbb{E}|X - Y| - \mathbb{E}|X - X'| - \mathbb{E}|Y - Y'|)^{1/2}$$

where X and X' (resp. Y and Y') are independent random variables whose probability distribution is u (resp. v).

As shown in [2], for one-dimensional real-valued variables, the energy distance is linked to the non-distribution-free version of the Cramér-von Mises distance:

$$D(u, v) = \sqrt{2}l_2(u, v) = \left(2 \int_{-\infty}^{+\infty} (U - V)^2\right)^{1/2}$$

Note that the common Cramér-von Mises criterion uses the distribution-free version of the distance. See [2] (section 2), for more details about both versions of the distance.

The input distributions can be empirical, therefore coming from samples whose values are effectively inputs of the function, or they can be seen as generalized functions, in which case they are weighted sums of Dirac delta functions located at the specified values.

References

[1], [2], [3], [4]

Examples

```

>>> from scipy.stats import energy_distance
>>> energy_distance([0], [2])
2.0000000000000004
>>> energy_distance([0, 8], [0, 8], [3, 1], [2, 2])
1.0000000000000002
>>> energy_distance([0.7, 7.4, 2.4, 6.8], [1.4, 8. ],
...                 [2.1, 4.2, 7.4, 8. ], [7.6, 8.8])
0.88003340976158217

```

6.29.13 Random variate generation

<code>rvs_ratio_uniforms(pdf, umax, vmin, vmax[, ...])</code>	Generate random samples from a probability density function using the ratio-of-uniforms method.
---	---

`scipy.stats.rvs_ratio_uniforms`

`scipy.stats.rvs_ratio_uniforms` (*pdf, umax, vmin, vmax, size=1, c=0, random_state=None*)

Generate random samples from a probability density function using the ratio-of-uniforms method.

Parameters

pdf	[callable] A function with signature <i>pdf(x)</i> that is proportional to the probability density function of the distribution.
umax	[float] The upper bound of the bounding rectangle in the u-direction.
vmin	[float] The lower bound of the bounding rectangle in the v-direction.
vmax	[float] The upper bound of the bounding rectangle in the v-direction.
size	[int or tuple of ints, optional] Defining number of random variates (default is 1).
c	[float, optional.] Shift parameter of ratio-of-uniforms method, see Notes. Default is 0.
random_state	[{None, int, <i>RandomState</i> , <i>Generator</i> }, optional] If <i>random_state</i> is <i>None</i> the <i>RandomState</i> singleton is used. If <i>random_state</i> is an int, a new <i>RandomState</i> instance is used, seeded with <i>random_state</i> . If <i>random_state</i> is already a <i>RandomState</i> or <i>Generator</i> instance, then that object is used. Default is <i>None</i> .

Returns

rvs	[ndarray] The random variates distributed according to the probability distribution defined by the pdf.
------------	---

Notes

Given a univariate probability density function pdf and a constant c , define the set $A = \{(u, v) : 0 < u \leq \sqrt{pdf(v/u + c)}\}$. If (U, V) is a random vector uniformly distributed over A , then $V/U + c$ follows a distribution according to pdf .

The above result (see [1], [2]) can be used to sample random variables using only the pdf, i.e. no inversion of the cdf is required. Typical choices of c are zero or the mode of pdf . The set A is a subset of the rectangle $R = [0, umax] \times [vmin, vmax]$ where

- $umax = \sup \sqrt{pdf(x)}$
- $vmin = \inf (x - c) \sqrt{pdf(x)}$
- $vmax = \sup (x - c) \sqrt{pdf(x)}$

In particular, these values are finite if pdf is bounded and $x^2 * pdf(x)$ is bounded (i.e. subquadratic tails). One can generate (U, V) uniformly on R and return $V/U + c$ if (U, V) are also in A which can be directly verified.

The algorithm is not changed if one replaces pdf by $k * pdf$ for any constant $k > 0$. Thus, it is often convenient to work with a function that is proportional to the probability density function by dropping unnecessary normalization factors.

Intuitively, the method works well if A fills up most of the enclosing rectangle such that the probability is high that (U, V) lies in A whenever it lies in R as the number of required iterations becomes too large otherwise. To be more precise, note that the expected number of iterations to draw (U, V) uniformly distributed on R such that (U, V) is also in A is given by the ratio $area(R) / area(A) = 2 * umax * (vmax - vmin) / area(pdf)$, where $area(pdf)$ is the integral of pdf (which is equal to one if the probability density function is used but can take on other values if a function proportional to the density is used). The equality holds since the area of A is equal to $0.5 * area(pdf)$ (Theorem 7.1 in [1]). If the sampling fails to generate a single random variate after 50000 iterations (i.e. not a single draw is in A), an exception is raised.

If the bounding rectangle is not correctly specified (i.e. if it does not contain A), the algorithm samples from a distribution different from the one given by pdf . It is therefore recommended to perform a test such as `kstest` as a check.

References

[1], [2], [3]

Examples

```
>>> from scipy import stats
```

Simulate normally distributed random variables. It is easy to compute the bounding rectangle explicitly in that case. For simplicity, we drop the normalization factor of the density.

```
>>> f = lambda x: np.exp(-x**2 / 2)
>>> v_bound = np.sqrt(f(np.sqrt(2))) * np.sqrt(2)
>>> umax, vmin, vmax = np.sqrt(f(0)), -v_bound, v_bound
>>> np.random.seed(12345)
>>> rvs = stats.rvs_ratio_uniforms(f, umax, vmin, vmax, size=2500)
```

The K-S test confirms that the random variates are indeed normally distributed (normality is not rejected at 5% significance level):

```
>>> stats.kstest(rvs, 'norm')[1]
0.33783681428365553
```

The exponential distribution provides another example where the bounding rectangle can be determined explicitly.

```
>>> np.random.seed(12345)
>>> rvs = stats.rvs_ratio_uniforms(lambda x: np.exp(-x), umax=1,
...                               vmin=0, vmax=2*np.exp(-1), size=1000)
>>> stats.kstest(rvs, 'expon')[1]
0.928454552559516
```

6.29.14 Circular statistical functions

<code>circmean(samples[, high, low, axis, nan_policy])</code>	Compute the circular mean for samples in a range.
<code>circvar(samples[, high, low, axis, nan_policy])</code>	Compute the circular variance for samples assumed to be in a range.
<code>circstd(samples[, high, low, axis, nan_policy])</code>	Compute the circular standard deviation for samples assumed to be in the range [low to high].

scipy.stats.circmean

```
scipy.stats.circmean(samples, high=6.283185307179586, low=0, axis=None,
                    nan_policy='propagate')
```

Compute the circular mean for samples in a range.

Parameters

samples [array_like] Input array.

high [float or int, optional] High boundary for circular mean range. Default is 2π .

low [float or int, optional] Low boundary for circular mean range. Default is 0.

axis [int, optional] Axis along which means are computed. The default is to compute the mean of the flattened array.

nan_policy [{'propagate', 'raise', 'omit'}, optional] Defines how to handle when input contains nan. 'propagate' returns nan, 'raise' throws an error, 'omit' performs the calculations ignoring nan values. Default is 'propagate'.

Returns

circmean [float] Circular mean.

Examples

```
>>> from scipy.stats import circmean
>>> circmean([0.1, 2*np.pi+0.2, 6*np.pi+0.3])
0.2
```

```
>>> from scipy.stats import circmean
>>> circmean([0.2, 1.4, 2.6], high = 1, low = 0)
0.4
```

scipy.stats.circvar

`scipy.stats.circvar` (*samples, high=6.283185307179586, low=0, axis=None, nan_policy='propagate'*)
Compute the circular variance for samples assumed to be in a range.

Parameters

samples [array_like] Input array.
high [float or int, optional] High boundary for circular variance range. Default is 2π .
low [float or int, optional] Low boundary for circular variance range. Default is 0.
axis [int, optional] Axis along which variances are computed. The default is to compute the variance of the flattened array.
nan_policy [{‘propagate’, ‘raise’, ‘omit’}, optional] Defines how to handle when input contains nan. ‘propagate’ returns nan, ‘raise’ throws an error, ‘omit’ performs the calculations ignoring nan values. Default is ‘propagate’.

Returns

circvar [float] Circular variance.

Notes

This uses a definition of circular variance that in the limit of small angles returns a number close to the ‘linear’ variance.

Examples

```
>>> from scipy.stats import circvar
>>> circvar([0, 2*np.pi/3, 5*np.pi/3])
2.19722457734
```

scipy.stats.circstd

`scipy.stats.circstd` (*samples, high=6.283185307179586, low=0, axis=None, nan_policy='propagate'*)
Compute the circular standard deviation for samples assumed to be in the range [low to high].

Parameters

samples [array_like] Input array.
high [float or int, optional] High boundary for circular standard deviation range. Default is 2π .
low [float or int, optional] Low boundary for circular standard deviation range. Default is 0.
axis [int, optional] Axis along which standard deviations are computed. The default is to compute the standard deviation of the flattened array.
nan_policy [{‘propagate’, ‘raise’, ‘omit’}, optional] Defines how to handle when input contains nan. ‘propagate’ returns nan, ‘raise’ throws an error, ‘omit’ performs the calculations ignoring nan values. Default is ‘propagate’.

Returns

circstd [float] Circular standard deviation.

Notes

This uses a definition of circular standard deviation that in the limit of small angles returns a number close to the ‘linear’ standard deviation.

Examples

```
>>> from scipy.stats import circstd
>>> circstd([0, 0.1*np.pi/2, 0.001*np.pi, 0.03*np.pi/2])
0.063564063306
```

6.29.15 Contingency table functions

<code>chi2_contingency(observed[, lambda_])</code>	<code>correction,</code>	Chi-square test of independence of variables in a contingency table.
<code>contingency.expected_freq(observed)</code>		Compute the expected frequencies from a contingency table.
<code>contingency.margins(a)</code>		Return a list of the marginal sums of the array <i>a</i> .
<code>fisher_exact(table[, alternative])</code>		Perform a Fisher exact test on a 2x2 contingency table.

scipy.stats.chi2_contingency

`scipy.stats.chi2_contingency(observed, correction=True, lambda_=None)`

Chi-square test of independence of variables in a contingency table.

This function computes the chi-square statistic and p-value for the hypothesis test of independence of the observed frequencies in the contingency table [1] *observed*. The expected frequencies are computed based on the marginal sums under the assumption of independence; see `scipy.stats.contingency.expected_freq`. The number of degrees of freedom is (expressed using numpy functions and attributes):

```
dof = observed.size - sum(observed.shape) + observed.ndim - 1
```

Parameters

- observed** [array_like] The contingency table. The table contains the observed frequencies (i.e. number of occurrences) in each category. In the two-dimensional case, the table is often described as an “R x C table”.
- correction** [bool, optional] If True, *and* the degrees of freedom is 1, apply Yates’ correction for continuity. The effect of the correction is to adjust each observed value by 0.5 towards the corresponding expected value.
- lambda_** [float or str, optional.] By default, the statistic computed in this test is Pearson’s chi-squared statistic [2]. *lambda_* allows a statistic from the Cressie-Read power divergence family [3] to be used instead. See `power_divergence` for details.

Returns

- chi2** [float] The test statistic.
- p** [float] The p-value of the test
- dof** [int] Degrees of freedom
- expected** [ndarray, same shape as *observed*] The expected frequencies, based on the marginal sums of the table.

See also:

contingency.expected_freq

fisher_exact

chisquare

power_divergence

Notes

An often quoted guideline for the validity of this calculation is that the test should be used only if the observed and expected frequencies in each cell are at least 5.

This is a test for the independence of different categories of a population. The test is only meaningful when the dimension of *observed* is two or more. Applying the test to a one-dimensional table will always result in *expected* equal to *observed* and a chi-square statistic equal to 0.

This function does not handle masked arrays, because the calculation does not make sense with missing values.

Like `stats.chisquare`, this function computes a chi-square statistic; the convenience this function provides is to figure out the expected frequencies and degrees of freedom from the given contingency table. If these were already known, and if the Yates' correction was not required, one could use `stats.chisquare`. That is, if one calls:

```
chi2, p, dof, ex = chi2_contingency(obs, correction=False)
```

then the following is true:

```
(chi2, p) == stats.chisquare(obs.ravel(), f_exp=ex.ravel(),
                             ddof=obs.size - 1 - dof)
```

The *lambda_* argument was added in version 0.13.0 of scipy.

References

[1], [2], [3]

Examples

A two-way example (2 x 3):

```
>>> from scipy.stats import chi2_contingency
>>> obs = np.array([[10, 10, 20], [20, 20, 20]])
>>> chi2_contingency(obs)
(2.7777777777777777,
 0.24935220877729619,
 2,
 array([[ 12.,  12.,  16.],
        [ 18.,  18.,  24.]])
```

Perform the test using the log-likelihood ratio (i.e. the “G-test”) instead of Pearson’s chi-squared statistic.


```
>>> g, p, dof, expctd = chi2_contingency(obs, lambda_="log-likelihood")
>>> g, p
(2.7688587616781319, 0.25046668010954165)
```

A four-way example (2 x 2 x 2 x 2):

```
>>> obs = np.array(
...     [[ [ [12, 17],
...         [11, 16]],
...        [ [11, 12],
...         [15, 16]]],
...     [ [ [23, 15],
...         [30, 22]],
...        [ [14, 17],
...         [15, 16]]]])
>>> chi2_contingency(obs)
(8.7584514426741897,
0.64417725029295503,
11,
array([[ [ [ 14.15462386,  14.15462386],
          [ 16.49423111,  16.49423111]],
        [ [ 11.2461395 ,  11.2461395 ],
          [ 13.10500554,  13.10500554]]],
       [ [ [ 19.5591166 ,  19.5591166 ],
          [ 22.79202844,  22.79202844]],
        [ [ 15.54012004,  15.54012004],
          [ 18.10873492,  18.10873492]]]])
```

scipy.stats.contingency.expected_freq

`scipy.stats.contingency.expected_freq` (*observed*)

Compute the expected frequencies from a contingency table.

Given an n-dimensional contingency table of observed frequencies, compute the expected frequencies for the table based on the marginal sums under the assumption that the groups associated with each dimension are independent.

Parameters

observed [array_like] The table of observed frequencies. (While this function can handle a 1-D array, that case is trivial. Generally *observed* is at least 2-D.)

Returns

expected [ndarray of float64] The expected frequencies, based on the marginal sums of the table. Same shape as *observed*.

Examples

```
>>> observed = np.array([[10, 10, 20],[20, 20, 20]])
>>> from scipy.stats.contingency import expected_freq
>>> expected_freq(observed)
array([[ 12.,  12.,  16.],
       [ 18.,  18.,  24.]])
```

scipy.stats.contingency.margins

`scipy.stats.contingency.margins(a)`

Return a list of the marginal sums of the array *a*.

Parameters

a [ndarray] The array for which to compute the marginal sums.

Returns

margsums [list of ndarrays] A list of length *a.ndim*. *margsums[k]* is the result of summing *a* over all axes except *k*; it has the same number of dimensions as *a*, but the length of each axis except axis *k* will be 1.

Examples

```
>>> a = np.arange(12).reshape(2, 6)
>>> a
array([[ 0,  1,  2,  3,  4,  5],
       [ 6,  7,  8,  9, 10, 11]])
>>> from scipy.stats.contingency import margins
>>> m0, m1 = margins(a)
>>> m0
array([[15],
       [51]])
>>> m1
array([[ 6,  8, 10, 12, 14, 16]])
```

```
>>> b = np.arange(24).reshape(2, 3, 4)
>>> m0, m1, m2 = margins(b)
>>> m0
array([[[ 66]],
       [[210]])]
>>> m1
array([[[ 60],
        [ 92],
        [124]])]
>>> m2
array([[[60, 66, 72, 78]])]
```

scipy.stats.fisher_exact

`scipy.stats.fisher_exact` (*table*, *alternative='two-sided'*)

Perform a Fisher exact test on a 2x2 contingency table.

Parameters

- table** [array_like of ints] A 2x2 contingency table. Elements should be non-negative integers.
- alternative** [{‘two-sided’, ‘less’, ‘greater’}, optional] Defines the alternative hypothesis. The following options are available (default is ‘two-sided’):
- ‘two-sided’
 - ‘less’: one-sided
 - ‘greater’: one-sided

Returns

- oddsratio** [float] This is prior odds ratio and not a posterior estimate.
- p_value** [float] P-value, the probability of obtaining a distribution at least as extreme as the one that was actually observed, assuming that the null hypothesis is true.

See also:

[chi2_contingency](#)

Chi-square test of independence of variables in a contingency table.

Notes

The calculated odds ratio is different from the one R uses. This scipy implementation returns the (more common) “unconditional Maximum Likelihood Estimate”, while R uses the “conditional Maximum Likelihood Estimate”.

For tables with large numbers, the (inexact) chi-square test implemented in the function [chi2_contingency](#) can also be used.

Examples

Say we spend a few days counting whales and sharks in the Atlantic and Indian oceans. In the Atlantic ocean we find 8 whales and 1 shark, in the Indian ocean 2 whales and 5 sharks. Then our contingency table is:

	Atlantic	Indian
whales	8	2
sharks	1	5

We use this table to find the p-value:

```
>>> import scipy.stats as stats
>>> oddsratio, pvalue = stats.fisher_exact([[8, 2], [1, 5]])
>>> pvalue
0.0349...
```

The probability that we would observe this or an even more imbalanced ratio by chance is about 3.5%. A commonly used significance level is 5%—if we adopt that, we can therefore conclude that our observed imbalance is statistically significant; whales prefer the Atlantic while sharks prefer the Indian ocean.

6.29.16 Plot-tests

<code>ppcc_max(x[, brack, dist])</code>	Calculate the shape parameter that maximizes the PPCC.
<code>ppcc_plot(x, a, b[, dist, plot, N])</code>	Calculate and optionally plot probability plot correlation coefficient.
<code>probplot(x[, sparams, dist, fit, plot, rvalue])</code>	Calculate quantiles for a probability plot, and optionally show the plot.
<code>boxcox_normplot(x, la, lb[, plot, N])</code>	Compute parameters for a Box-Cox normality plot, optionally show it.
<code>yeojohnson_normplot(x, la, lb[, plot, N])</code>	Compute parameters for a Yeo-Johnson normality plot, optionally show it.

`scipy.stats.ppcc_max`

`scipy.stats.ppcc_max(x, brack=0.0, 1.0, dist='tukeylambda')`

Calculate the shape parameter that maximizes the PPCC.

The probability plot correlation coefficient (PPCC) plot can be used to determine the optimal shape parameter for a one-parameter family of distributions. `ppcc_max` returns the shape parameter that would maximize the probability plot correlation coefficient for the given data to a one-parameter family of distributions.

Parameters

- x** [array_like] Input array.
- brack** [tuple, optional] Triple (a,b,c) where (a<b<c). If bracket consists of two numbers (a, c) then they are assumed to be a starting interval for a downhill bracket search (see `scipy.optimize.brent`).
- dist** [str or stats.distributions instance, optional] Distribution or distribution function name. Objects that look enough like a stats.distributions instance (i.e. they have a `ppf` method) are also accepted. The default is `'tukeylambda'`.

Returns

- shape_value** [float] The shape parameter at which the probability plot correlation coefficient reaches its max value.

See also:

`ppcc_plot`, `probplot`, `boxcox`

Notes

The `brack` keyword serves as a starting point which is useful in corner cases. One can use a plot to obtain a rough visual estimate of the location for the maximum to start the search near it.

References

[1], [2]

Examples

First we generate some random data from a Tukey-Lambda distribution, with shape parameter -0.7:

```
>>> from scipy import stats
>>> x = stats.tukeylambd.rvs(-0.7, loc=2, scale=0.5, size=10000,
...                          random_state=1234567) + 1e4
```

Now we explore this data with a PPCC plot as well as the related probability plot and Box-Cox normplot. A red line is drawn where we expect the PPCC value to be maximal (at the shape parameter -0.7 used above):

```
>>> import matplotlib.pyplot as plt
>>> fig = plt.figure(figsize=(8, 6))
>>> ax = fig.add_subplot(111)
>>> res = stats.ppcc_plot(x, -5, 5, plot=ax)
```

We calculate the value where the shape should reach its maximum and a red line is drawn there. The line should coincide with the highest point in the `ppcc_plot`.

```
>>> max = stats.ppcc_max(x)
>>> ax.vlines(max, 0, 1, colors='r', label='Expected shape value')
```

```
>>> plt.show()
```

scipy.stats.ppcc_plot

`scipy.stats.ppcc_plot(x, a, b, dist='tukeylambda', plot=None, N=80)`

Calculate and optionally plot probability plot correlation coefficient.


The probability plot correlation coefficient (PPCC) plot can be used to determine the optimal shape parameter for a one-parameter family of distributions. It cannot be used for distributions without shape parameters (like the normal distribution) or with multiple shape parameters.

By default a Tukey-Lambda distribution (`stats.tukeylambda`) is used. A Tukey-Lambda PPCC plot interpolates from long-tailed to short-tailed distributions via an approximately normal one, and is therefore particularly useful in practice.

Parameters

x	[array_like] Input array.
a, b	[scalar] Lower and upper bounds of the shape parameter to use.
dist	[str or stats.distributions instance, optional] Distribution or distribution function name. Objects that look enough like a <code>stats.distributions</code> instance (i.e. they have a <code>ppf</code> method) are also accepted. The default is <code>'tukeylambda'</code> .
plot	[object, optional] If given, plots PPCC against the shape parameter. <code>plot</code> is an object that has to have methods “plot” and “text”. The <code>matplotlib.pyplot</code> module or a Matplotlib Axes object can be used, or a custom object with the same methods. Default is <code>None</code> , which means that no plot is created.
N	[int, optional] Number of points on the horizontal axis (equally distributed from <code>a</code> to <code>b</code>).

Returns



svals [ndarray] The shape values for which *ppcc* was calculated.
ppcc [ndarray] The calculated probability plot correlation coefficient values.

See also:

ppcc_max, *probplot*, *boxcox_normplot*, *tukeylambda*

References

J.J. Filliben, “The Probability Plot Correlation Coefficient Test for Normality”, *Technometrics*, Vol. 17, pp. 111-117, 1975.


Examples

First we generate some random data from a Tukey-Lambda distribution, with shape parameter -0.7:

```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
>>> np.random.seed(1234567)
>>> x = stats.tukeylambda.rvs(-0.7, loc=2, scale=0.5, size=10000) + 1e4
```

Now we explore this data with a PPCC plot as well as the related probability plot and Box-Cox normplot. A red line is drawn where we expect the PPCC value to be maximal (at the shape parameter -0.7 used above):

```
>>> fig = plt.figure(figsize=(12, 4))
>>> ax1 = fig.add_subplot(131)
>>> ax2 = fig.add_subplot(132)
>>> ax3 = fig.add_subplot(133)
>>> res = stats.probplot(x, plot=ax1)
>>> res = stats.boxcox_normplot(x, -5, 5, plot=ax2)
>>> res = stats.ppcc_plot(x, -5, 5, plot=ax3)
>>> ax3.vlines(-0.7, 0, 1, colors='r', label='Expected shape value')
>>> plt.show()
```



scipy.stats.probplot

`scipy.stats.probplot` (*x*, *sparams*=(), *dist*='norm', *fit*=True, *plot*=None, *rvalue*=False)

Calculate quantiles for a probability plot, and optionally show the plot.

Generates a probability plot of sample data against the quantiles of a specified theoretical distribution (the normal distribution by default). `probplot` optionally calculates a best-fit line for the data and plots the results using Matplotlib or a given plot function.

Parameters

x	[array_like] Sample/response data from which <code>probplot</code> creates the plot.
sparams	[tuple, optional] Distribution-specific shape parameters (shape parameters plus location and scale).
dist	[str or stats.distributions instance, optional] Distribution or distribution function name. The default is 'norm' for a normal probability plot. Objects that look enough like a stats.distributions instance (i.e. they have a <code>ppf</code> method) are also accepted.
fit	[bool, optional] Fit a least-squares regression (best-fit) line to the sample data if True (default).
plot	[object, optional] If given, plots the quantiles and least squares fit. <code>plot</code> is an object that has to have methods "plot" and "text". The <code>matplotlib.pyplot</code> module or a Matplotlib Axes object can be used, or a custom object with the same methods. Default is None, which means that no plot is created.

Returns

(osm, osr)	[tuple of ndarrays] Tuple of theoretical quantiles (<code>osm</code> , or order statistic medians) and ordered responses (<code>osr</code>). <code>osr</code> is simply sorted input <code>x</code> . For details on how <code>osm</code> is calculated see the Notes section.
(slope, intercept, r)	[tuple of floats, optional] Tuple containing the result of the least-squares fit, if that is performed by <code>probplot</code> . <code>r</code> is the square root of the coefficient of determination. If <code>fit=False</code> and <code>plot=None</code> , this tuple is not returned.

Notes

Even if `plot` is given, the figure is not shown or saved by `probplot`; `plt.show()` or `plt.savefig('filename.png')` should be used after calling `probplot`.

`probplot` generates a probability plot, which should not be confused with a Q-Q or a P-P plot. Statsmodels has more extensive functionality of this type, see `statsmodels.api.ProbPlot`.

The formula used for the theoretical quantiles (horizontal axis of the probability plot) is Filliben's estimate:

```
quantiles = dist.ppf(val), for
    0.5**(1/n), for i = n
val = (i - 0.3175) / (n + 0.365), for i = 2, ..., n-1
    1 - 0.5**(1/n), for i = 1
```

where `i` indicates the `i`-th ordered value and `n` is the total number of values.

Examples

```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
>>> nsample = 100
>>> np.random.seed(7654321)
```

A t distribution with small degrees of freedom:

```
>>> ax1 = plt.subplot(221)
>>> x = stats.t.rvs(3, size=nsample)
>>> res = stats.probplot(x, plot=plt)
```

A t distribution with larger degrees of freedom:

```
>>> ax2 = plt.subplot(222)
>>> x = stats.t.rvs(25, size=nsample)
>>> res = stats.probplot(x, plot=plt)
```

A mixture of two normal distributions with broadcasting:

```
>>> ax3 = plt.subplot(223)
>>> x = stats.norm.rvs(loc=[0,5], scale=[1,1.5],
...                   size=(nsample//2,2)).ravel()
>>> res = stats.probplot(x, plot=plt)
```

A standard normal distribution:

```
>>> ax4 = plt.subplot(224)
>>> x = stats.norm.rvs(loc=0, scale=1, size=nsample)
>>> res = stats.probplot(x, plot=plt)
```

Produce a new figure with a loggamma distribution, using the `dist` and `sparams` keywords:

```
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> x = stats.loggamma.rvs(c=2.5, size=500)
>>> res = stats.probplot(x, dist=stats.loggamma, sparams=(2.5,), plot=ax)
>>> ax.set_title("Probplot for loggamma dist with shape parameter 2.5")
```

Show the results with Matplotlib:

```
>>> plt.show()
```

scipy.stats.boxcox_normplot



`scipy.stats.boxcox_normplot` (*x*, *la*, *lb*, *plot=None*, *N=80*)

Compute parameters for a Box-Cox normality plot, optionally show it.

A Box-Cox normality plot shows graphically what the best transformation parameter is to use in `boxcox` to obtain a distribution that is close to normal.

Parameters

x [array_like] Input array.



la, lb	[scalar] The lower and upper bounds for the <code>lambda</code> values to pass to <code>boxcox</code> for Box-Cox transformations. These are also the limits of the horizontal axis of the plot if that is generated.
plot	[object, optional] If given, plots the quantiles and least squares fit. <code>plot</code> is an object that has to have methods “plot” and “text”. The <code>matplotlib.pyplot</code> module or a Matplotlib Axes object can be used, or a custom object with the same methods. Default is None, which means that no plot is created.
N	[int, optional] Number of points on the horizontal axis (equally distributed from <code>la</code> to <code>lb</code>).

Returns

lmbdas	[ndarray] The <code>lambda</code> values for which a Box-Cox transform was done.
ppcc	[ndarray] Probability Plot Correlation Coefficient, as obtained from <code>probplot</code> when fitting the Box-Cox transformed input <code>x</code> against a normal distribution.

See also:

`probplot`, `boxcox`, `boxcox_normmax`, `boxcox_illf`, `ppcc_max`

Notes

Even if `plot` is given, the figure is not shown or saved by `boxcox_normplot`; `plt.show()` or `plt.savefig('filename.png')` should be used after calling `probplot`.

Examples

```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
```

Generate some non-normally distributed data, and create a Box-Cox plot:

```
>>> x = stats.loggamma.rvs(5, size=500) + 5
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> prob = stats.boxcox_normplot(x, -20, 20, plot=ax)
```

Determine and plot the optimal `lambda` to transform `x` and plot it in the same plot:

```
>>> _, maxlog = stats.boxcox(x)
>>> ax.axvline(maxlog, color='r')
```

```
>>> plt.show()
```

scipy.stats.yeojohnson_normplot


`scipy.stats.yeojohnson_normplot(x, la, lb, plot=None, N=80)`

Compute parameters for a Yeo-Johnson normality plot, optionally show it.

A Yeo-Johnson normality plot shows graphically what the best transformation parameter is to use in `yeojohnson` to obtain a distribution that is close to normal.

Parameters

x [array_like] Input array.



- la, lb** [scalar] The lower and upper bounds for the `lambda` values to pass to `yeojohnson` for Yeo-Johnson transformations. These are also the limits of the horizontal axis of the plot if that is generated.
- plot** [object, optional] If given, plots the quantiles and least squares fit. `plot` is an object that has to have methods “plot” and “text”. The `matplotlib.pyplot` module or a Matplotlib Axes object can be used, or a custom object with the same methods. Default is `None`, which means that no plot is created.
- N** [int, optional] Number of points on the horizontal axis (equally distributed from `la` to `lb`).
- Returns**
- lmbdas** [ndarray] The `lambda` values for which a Yeo-Johnson transform was done.
- ppcc** [ndarray] Probability Plot Correlation Coefficient, as obtained from `probplot` when fitting the Box-Cox transformed input `x` against a normal distribution.

See also:

[`probplot`](#), [`yeojohnson`](#), [`yeojohnson_normmax`](#), [`yeojohnson_llf`](#), [`ppcc_max`](#)

Notes

Even if `plot` is given, the figure is not shown or saved by `boxcox_normplot`; `plt.show()` or `plt.savefig('figname.png')` should be used after calling `probplot`.

New in version 1.2.0.

Examples

```
>>> from scipy import stats
>>> import matplotlib.pyplot as plt
```


Generate some non-normally distributed data, and create a Yeo-Johnson plot:

```
>>> x = stats.loggamma.rvs(5, size=500) + 5
>>> fig = plt.figure()
>>> ax = fig.add_subplot(111)
>>> prob = stats.yeojohnson_normplot(x, -20, 20, plot=ax)
```

Determine and plot the optimal `lambda` to transform `x` and plot it in the same plot:

```
>>> _, maxlog = stats.yeojohnson(x)
>>> ax.axvline(maxlog, color='r')
```

```
>>> plt.show()
```



6.29.17 Masked statistics functions

Statistical functions for masked arrays (`scipy.stats.mstats`)

This module contains a large number of statistical functions that can be used with masked arrays.

Most of these functions are similar to those in `scipy.stats` but might have small differences in the API or in the algorithm used. Since this is a relatively new package, some API changes are still possible.

Summary statistics

<code>describe(a[, axis, ddof, bias])</code>	Computes several descriptive statistics of the passed array.
<code>gmean(a[, axis, dtype])</code>	Compute the geometric mean along the specified axis.
<code>hmean(a[, axis, dtype])</code>	Calculate the harmonic mean along the specified axis.
<code>kurtosis(a[, axis, fisher, bias])</code>	Computes the kurtosis (Fisher or Pearson) of a dataset.
<code>mode(a[, axis])</code>	Returns an array of the modal (most common) value in the passed array.
<code>mquantiles(a[, prob, alphap, betap, axis, limit])</code>	Computes empirical quantiles for a data array.
<code>hdmedian(data[, axis, var])</code>	Returns the Harrell-Davis estimate of the median along the given axis.
<code>hdquantiles(data[, prob, axis, var])</code>	Computes quantile estimates with the Harrell-Davis method.
<code>hdquantiles_sd(data[, prob, axis])</code>	The standard error of the Harrell-Davis quantile estimates by jackknife.
<code>idealfourths(data[, axis])</code>	Returns an estimate of the lower and upper quartiles.
<code>plotting_positions(data[, alpha, beta])</code>	Returns plotting positions (or empirical percentile points) for the data.
<code>meppf(data[, alpha, beta])</code>	Returns plotting positions (or empirical percentile points) for the data.
<code>moment(a[, moment, axis])</code>	Calculates the nth moment about the mean for a sample.
<code>skew(a[, axis, bias])</code>	Computes the skewness of a data set.
<code>tmean(a[, limits, inclusive, axis])</code>	Compute the trimmed mean.
<code>tvar(a[, limits, inclusive, axis, ddof])</code>	Compute the trimmed variance
<code>tmin(a[, lowerlimit, axis, inclusive])</code>	Compute the trimmed minimum
<code>tmax(a[, upperlimit, axis, inclusive])</code>	Compute the trimmed maximum
<code>tsem(a[, limits, inclusive, axis, ddof])</code>	Compute the trimmed standard error of the mean.
<code>variation(a[, axis])</code>	Computes the coefficient of variation, the ratio of the biased standard deviation to the mean.
<code>find_repeats(arr)</code>	Find repeats in arr and return a tuple (repeats, repeat_count).
<code>sem(a[, axis, ddof])</code>	Calculates the standard error of the mean of the input array.
<code>trimmed_mean(a[, limits, inclusive, ...])</code>	Returns the trimmed mean of the data along the given axis.
<code>trimmed_mean_ci(data[, limits, inclusive, ...])</code>	Selected confidence interval of the trimmed mean along the given axis.
<code>trimmed_std(a[, limits, inclusive, ...])</code>	Returns the trimmed standard deviation of the data along the given axis.
<code>trimmed_var(a[, limits, inclusive, ...])</code>	Returns the trimmed variance of the data along the given axis.

scipy.stats.mstats.describe

`scipy.stats.mstats.describe` (*a*, *axis*=0, *ddof*=0, *bias*=True)

Computes several descriptive statistics of the passed array.

Parameters

a	[array_like] Data array
axis	[int or None, optional] Axis along which to calculate statistics. Default 0. If None, compute over the whole array <i>a</i> .
ddof	[int, optional] degree of freedom (default 0); note that default ddof is different from the same routine in <code>stats.describe</code>
bias	[bool, optional] If False, then the skewness and kurtosis calculations are corrected for statistical bias.

Returns

nobs	[int] (size of the data (discarding missing values))
minmax	[(int, int)] min, max
mean	[float] arithmetic mean
variance	[float] unbiased variance
skewness	[float] biased skewness
kurtosis	[float] biased kurtosis

Examples

```
>>> from scipy.stats.mstats import describe
>>> ma = np.ma.array(range(6), mask=[0, 0, 0, 1, 1, 1])
>>> describe(ma)
DescribeResult(nobs=3, minmax=(masked_array(data=0,
      mask=False,
      fill_value=999999), masked_array(data=2,
      mask=False,
      fill_value=999999)), mean=1.0, variance=0.6666666666666666,
skewness=masked_array(data=0., mask=False, fill_value=1e+20),
kurtosis=-1.5)
```

scipy.stats.mstats.gmean

`scipy.stats.mstats.gmean` (*a*, *axis*=0, *dtype*=None)

Compute the geometric mean along the specified axis.

Return the geometric average of the array elements. That is: n -th root of $(x_1 * x_2 * \dots * x_n)$

Parameters

a	[array_like] Input array or object that can be converted to an array.
axis	[int or None, optional] Axis along which the geometric mean is computed. Default is 0. If None, compute over the whole array <i>a</i> .
dtype	[dtype, optional] Type of the returned array and of the accumulator in which the elements are summed. If dtype is not specified, it defaults to the dtype of <i>a</i> , unless <i>a</i> has an integer dtype with a precision less than that of the default platform integer. In that case, the default platform integer is used.

Returns

gmean [ndarray] See *dtype* parameter above.

See also:

numpy.mean

Arithmetic average

numpy.average

Weighted average

hmean

Harmonic mean

Notes

The geometric average is computed over a single dimension of the input array, `axis=0` by default, or all values in the array if `axis=None`. float64 intermediate and return values are used for integer inputs.

Use masked arrays to ignore any non-finite values in the input or that arise in the calculations such as Not a Number and infinity because masked arrays automatically mask any non-finite values.

Examples

```
>>> from scipy.stats import gmean
>>> gmean([1, 4])
2.0
>>> gmean([1, 2, 3, 4, 5, 6, 7])
3.3800151591412964
```

scipy.stats.mstats.hmean

`scipy.stats.mstats.hmean` (*a*, *axis=0*, *dtype=None*)

Calculate the harmonic mean along the specified axis.

That is: $n / (1/x_1 + 1/x_2 + \dots + 1/x_n)$

Parameters

- a** [array_like] Input array, masked array or object that can be converted to an array.
- axis** [int or None, optional] Axis along which the harmonic mean is computed. Default is 0. If None, compute over the whole array *a*.
- dtype** [dtype, optional] Type of the returned array and of the accumulator in which the elements are summed. If *dtype* is not specified, it defaults to the dtype of *a*, unless *a* has an integer dtype with a precision less than that of the default platform integer. In that case, the default platform integer is used.

Returns

hmean [ndarray] See *dtype* parameter above.

See also:

numpy.mean

Arithmetic average

numpy.average

Weighted average

gmean

Geometric mean

Notes

The harmonic mean is computed over a single dimension of the input array, `axis=0` by default, or all values in the array if `axis=None`. float64 intermediate and return values are used for integer inputs.

Use masked arrays to ignore any non-finite values in the input or that arise in the calculations such as Not a Number and infinity.

Examples

```
>>> from scipy.stats import hmean
>>> hmean([1, 4])
1.6000000000000001
>>> hmean([1, 2, 3, 4, 5, 6, 7])
2.6997245179063363
```

scipy.stats.mstats.kurtosis

`scipy.stats.mstats.kurtosis(a, axis=0, fisher=True, bias=True)`

Computes the kurtosis (Fisher or Pearson) of a dataset.

Kurtosis is the fourth central moment divided by the square of the variance. If Fisher's definition is used, then 3.0 is subtracted from the result to give 0.0 for a normal distribution.

If `bias` is `False` then the kurtosis is calculated using k statistics to eliminate bias coming from biased moment estimators

Use `kurtosistest` to see if result is close enough to normal.

Parameters

- a** [array] data for which the kurtosis is calculated
- axis** [int or None, optional] Axis along which the kurtosis is calculated. Default is 0. If None, compute over the whole array *a*.
- fisher** [bool, optional] If True, Fisher's definition is used (normal ==> 0.0). If False, Pearson's definition is used (normal ==> 3.0).
- bias** [bool, optional] If False, then the calculations are corrected for statistical bias.

Returns

- kurtosis** [array] The kurtosis of values along an axis. If all values are equal, return -3 for Fisher's definition and 0 for Pearson's definition.

Notes

For more details about *kurtosis*, see *stats.kurtosis*.

scipy.stats.mstats.mode

`scipy.stats.mstats.mode(a, axis=0)`

Returns an array of the modal (most common) value in the passed array.

Parameters

a [array_like] n-dimensional array of which to find mode(s).
axis [int or None, optional] Axis along which to operate. Default is 0. If None, compute over the whole array *a*.

Returns

mode [ndarray] Array of modal values.
count [ndarray] Array of counts for each mode.

Notes

For more details, see *stats.mode*.

Examples

```
>>> from scipy import stats
>>> from scipy.stats import mstats
>>> m_arr = np.ma.array([1, 1, 0, 0, 0, 0], mask=[0, 0, 1, 1, 1, 0])
>>> stats.mode(m_arr)
ModeResult(mode=array([0]), count=array([4]))
>>> mstats.mode(m_arr)
ModeResult(mode=array([1.]), count=array([2.]))
```

scipy.stats.mstats.mquantiles

`scipy.stats.mstats.mquantiles(a, prob=[0.25, 0.5, 0.75], alphap=0.4, betap=0.4, axis=None, limit=())`

Computes empirical quantiles for a data array.

Samples quantile are defined by $Q(p) = (1-\gamma)*x[j] + \gamma*x[j+1]$, where $x[j]$ is the j -th order statistic, and γ is a function of $j = \text{floor}(n*p + m)$, $m = \text{alphap} + p*(1 - \text{alphap} - \text{betap})$ and $g = n*p + m - j$.

Reinterpreting the above equations to compare to **R** lead to the equation: $p(k) = (k - \text{alphap}) / (n + 1 - \text{alphap} - \text{betap})$

Typical values of (alphap,betap) are:

- (0,1): $p(k) = k/n$: linear interpolation of cdf (**R** type 4)
- (.5,.5): $p(k) = (k - 1/2.) / n$: piecewise linear function (**R** type 5)
- (0,0): $p(k) = k / (n+1)$: (**R** type 6)

- (1,1): $p(k) = (k-1) / (n-1)$: $p(k) = \text{mode}[F(x[k])]$. (**R** type 7, **R** default)
- (1/3,1/3): $p(k) = (k-1/3) / (n+1/3)$: Then $p(k) \sim \text{median}[F(x[k])]$. The resulting quantile estimates are approximately median-unbiased regardless of the distribution of x . (**R** type 8)
- (3/8,3/8): $p(k) = (k-3/8) / (n+1/4)$: Blom. The resulting quantile estimates are approximately unbiased if x is normally distributed (**R** type 9)
- (.4,.4): approximately quantile unbiased (Cunnane)
- (.35,.35): APL, used with PWM

Parameters

a	[array_like] Input data, as a sequence or array of dimension at most 2.
prob	[array_like, optional] List of quantiles to compute.
alphap	[float, optional] Plotting positions parameter, default is 0.4.
betap	[float, optional] Plotting positions parameter, default is 0.4.
axis	[int, optional] Axis along which to perform the trimming. If None (default), the input array is first flattened.
limit	[tuple, optional] Tuple of (lower, upper) values. Values of a outside this open interval are ignored.

Returns

mquantiles	[MaskedArray] An array containing the calculated quantiles.
-------------------	---

Notes

This formulation is very similar to **R** except the calculation of m from `alphap` and `betap`, where in **R** m is defined with each type.

References

[1], [2]

Examples

```
>>> from scipy.stats.mstats import mquantiles
>>> a = np.array([6., 47., 49., 15., 42., 41., 7., 39., 43., 40., 36.])
>>> mquantiles(a)
array([ 19.2,  40. ,  42.8])
```

Using a 2D array, specifying axis and limit.

```
>>> data = np.array([[ 6.,  7.,  1.],
...                 [ 47., 15.,  2.],
...                 [ 49., 36.,  3.],
...                 [ 15., 39.,  4.],
...                 [ 42., 40., -999.],
...                 [ 41., 41., -999.],
...                 [  7., -999., -999.],
...                 [ 39., -999., -999.]])
```

(continues on next page)

(continued from previous page)

```

...           [ 43., -999., -999.],
...           [ 40., -999., -999.],
...           [ 36., -999., -999.]]
>>> print(mquantiles(data, axis=0, limit=(0, 50)))
[[19.2  14.6   1.45]
 [40.   37.5   2.5 ]
 [42.8  40.05  3.55]]

```

```

>>> data[:, 2] = -999.
>>> print(mquantiles(data, axis=0, limit=(0, 50)))
[[19.200000000000003 14.6 --]
 [40.0 37.5 --]
 [42.800000000000004 40.05 --]]

```

scipy.stats.mstats.hdmedian

`scipy.stats.mstats.hdmedian` (*data*, *axis=-1*, *var=False*)

Returns the Harrell-Davis estimate of the median along the given axis.

Parameters

data [ndarray] Data array.
axis [int, optional] Axis along which to compute the quantiles. If None, use a flattened array.
var [bool, optional] Whether to return the variance of the estimate.

Returns

hdmedian [MaskedArray] The median values. If `var=True`, the variance is returned inside the masked array. E.g. for a 1-D array the shape change from (1,) to (2,).

scipy.stats.mstats.hdquantiles

`scipy.stats.mstats.hdquantiles` (*data*, *prob=[0.25, 0.5, 0.75]*, *axis=None*, *var=False*)

Computes quantile estimates with the Harrell-Davis method.

The quantile estimates are calculated as a weighted linear combination of order statistics.

Parameters

data [array_like] Data array.
prob [sequence, optional] Sequence of quantiles to compute.
axis [int or None, optional] Axis along which to compute the quantiles. If None, use a flattened array.
var [bool, optional] Whether to return the variance of the estimate.

Returns

hdquantiles [MaskedArray] A (p,) array of quantiles (if `var` is False), or a (2,p) array of quantiles and variances (if `var` is True), where `p` is the number of quantiles.

See also:

[`hdquantiles_sd`](#)

scipy.stats.mstats.hdquantiles_sd

`scipy.stats.mstats.hdquantiles_sd` (*data*, *prob*=[0.25, 0.5, 0.75], *axis*=None)

The standard error of the Harrell-Davis quantile estimates by jackknife.

Parameters

data [array_like] Data array.
prob [sequence, optional] Sequence of quantiles to compute.
axis [int, optional] Axis along which to compute the quantiles. If None, use a flattened array.

Returns

hdquantiles_sd
 [MaskedArray] Standard error of the Harrell-Davis quantile estimates.

See also:

[*hdquantiles*](#)

scipy.stats.mstats.idealfourths

`scipy.stats.mstats.idealfourths` (*data*, *axis*=None)

Returns an estimate of the lower and upper quartiles.

Uses the ideal fourths algorithm.

Parameters

data [array_like] Input array.
axis [int, optional] Axis along which the quartiles are estimated. If None, the arrays are flattened.

Returns

idealfourths
 [{list of floats, masked array}] Returns the two internal values that divide *data* into four parts using the ideal fourths algorithm either along the flattened array (if *axis* is None) or along *axis* of *data*.

scipy.stats.mstats.plotting_positions

`scipy.stats.mstats.plotting_positions` (*data*, *alpha*=0.4, *beta*=0.4)

Returns plotting positions (or empirical percentile points) for the data.

Plotting positions are defined as $(i - \alpha) / (n + 1 - \alpha - \beta)$, where:

- *i* is the rank order statistics
- *n* is the number of unmasked values along the given axis
- *alpha* and *beta* are two parameters.

Typical values for alpha and beta are:

- (0,1) : $p(k) = k/n$, linear interpolation of cdf (R, type 4)
- (.5,.5) : $p(k) = (k - 1/2) / n$, piecewise linear function (R, type 5)
- (0,0) : $p(k) = k / (n + 1)$, Weibull (R type 6)

- (1,1): $p(k) = (k-1)/(n-1)$, in this case, $p(k) = \text{mode}[F(x[k])]$. That's R default (R type 7)
- (1/3,1/3): $p(k) = (k-1/3)/(n+1/3)$, then $p(k) \sim \text{median}[F(x[k])]$. The resulting quantile estimates are approximately median-unbiased regardless of the distribution of x . (R type 8)
- (3/8,3/8): $p(k) = (k-3/8)/(n+1/4)$, Blom. The resulting quantile estimates are approximately unbiased if x is normally distributed (R type 9)
- (.4,.4): approximately quantile unbiased (Cunnane)
- (.35,.35): APL, used with PWM
- (.3175, .3175): used in `scipy.stats.probplot`

Parameters

- data** [array_like] Input data, as a sequence or array of dimension at most 2.
- alpha** [float, optional] Plotting positions parameter. Default is 0.4.
- beta** [float, optional] Plotting positions parameter. Default is 0.4.

Returns

- positions** [MaskedArray] The calculated plotting positions.

scipy.stats.mstats.meppf

`scipy.stats.mstats.meppf(data, alpha=0.4, beta=0.4)`

Returns plotting positions (or empirical percentile points) for the data.

Plotting positions are defined as $(i-\alpha)/(n+1-\alpha-\beta)$, where:

- i is the rank order statistics
- n is the number of unmasked values along the given axis
- α and β are two parameters.

Typical values for α and β are:

- (0,1): $p(k) = k/n$, linear interpolation of cdf (R, type 4)
- (.5,.5): $p(k) = (k-1/2)/n$, piecewise linear function (R, type 5)
- (0,0): $p(k) = k/(n+1)$, Weibull (R type 6)
- (1,1): $p(k) = (k-1)/(n-1)$, in this case, $p(k) = \text{mode}[F(x[k])]$. That's R default (R type 7)
- (1/3,1/3): $p(k) = (k-1/3)/(n+1/3)$, then $p(k) \sim \text{median}[F(x[k])]$. The resulting quantile estimates are approximately median-unbiased regardless of the distribution of x . (R type 8)
- (3/8,3/8): $p(k) = (k-3/8)/(n+1/4)$, Blom. The resulting quantile estimates are approximately unbiased if x is normally distributed (R type 9)
- (.4,.4): approximately quantile unbiased (Cunnane)
- (.35,.35): APL, used with PWM
- (.3175, .3175): used in `scipy.stats.probplot`

Parameters

data [array_like] Input data, as a sequence or array of dimension at most 2.
alpha [float, optional] Plotting positions parameter. Default is 0.4.
beta [float, optional] Plotting positions parameter. Default is 0.4.

Returns

positions [MaskedArray] The calculated plotting positions.

scipy.stats.mstats.moment

`scipy.stats.mstats.moment(a, moment=1, axis=0)`

Calculates the nth moment about the mean for a sample.

Parameters

a [array_like] data
moment [int, optional] order of central moment that is returned
axis [int or None, optional] Axis along which the central moment is computed. Default is 0. If None, compute over the whole array *a*.

Returns**n-th central moment**

[ndarray or float] The appropriate moment along the given axis or over all values if axis is None. The denominator for the moment calculation is the number of observations, no degrees of freedom correction is done.

Notes

For more details about *moment*, see *stats.moment*.

scipy.stats.mstats.skew

`scipy.stats.mstats.skew(a, axis=0, bias=True)`

Computes the skewness of a data set.

Parameters

a [ndarray] data
axis [int or None, optional] Axis along which skewness is calculated. Default is 0. If None, compute over the whole array *a*.
bias [bool, optional] If False, then the calculations are corrected for statistical bias.

Returns

skewness [ndarray] The skewness of values along an axis, returning 0 where all values are equal.

Notes

For more details about *skew*, see *stats.skew*.

scipy.stats.mstats.tmean

`scipy.stats.mstats.tmean` (*a*, *limits=None*, *inclusive=True*, *True*, *axis=None*)

Compute the trimmed mean.

Parameters

a	[array_like] Array of values.
limits	[None or (lower limit, upper limit), optional] Values in the input array less than the lower limit or greater than the upper limit will be ignored. When limits is None (default), then all values are used. Either of the limit values in the tuple can also be None representing a half-open interval.
inclusive	[(bool, bool), optional] A tuple consisting of the (lower flag, upper flag). These flags determine whether values exactly equal to the lower or upper limits are included. The default value is (True, True).
axis	[int or None, optional] Axis along which to operate. If None, compute over the whole array. Default is None.

Returns

tmean	[float]
--------------	---------

Notes

For more details on *tmean*, see *stats.tmean*.

Examples

```
>>> from scipy.stats import mstats
>>> a = np.array([[6, 8, 3, 0],
...              [3, 9, 1, 2],
...              [8, 7, 8, 2],
...              [5, 6, 0, 2],
...              [4, 5, 5, 2]])
...
...
>>> mstats.tmean(a, (2,5))
3.3
>>> mstats.tmean(a, (2,5), axis=0)
masked_array(data=[4.0, 5.0, 4.0, 2.0],
             mask=[False, False, False, False],
             fill_value=1e+20)
```


scipy.stats.mstats.tvar

`scipy.stats.mstats.tvar` (*a*, *limits=None*, *inclusive=True*, *True*, *axis=0*, *ddof=1*)

Compute the trimmed variance

This function computes the sample variance of an array of values, while ignoring values which are outside of given *limits*.

Parameters

- a** [array_like] Array of values.
- limits** [None or (lower limit, upper limit), optional] Values in the input array less than the lower limit or greater than the upper limit will be ignored. When *limits* is *None*, then all values are used. Either of the limit values in the tuple can also be *None* representing a half-open interval. The default value is *None*.
- inclusive** [(bool, bool), optional] A tuple consisting of the (lower flag, upper flag). These flags determine whether values exactly equal to the lower or upper limits are included. The default value is (True, True).
- axis** [int or None, optional] Axis along which to operate. If *None*, compute over the whole array. Default is zero.
- ddof** [int, optional] Delta degrees of freedom. Default is 1.

Returns

- tvar** [float] Trimmed variance.

Notes

For more details on *tvar*, see *stats.tvar*.

scipy.stats.mstats.tmin

`scipy.stats.mstats.tmin` (*a*, *lowerlimit=None*, *axis=0*, *inclusive=True*)

Compute the trimmed minimum

Parameters

- a** [array_like] array of values
- lowerlimit** [None or float, optional] Values in the input array less than the given limit will be ignored. When *lowerlimit* is *None*, then all values are used. The default value is *None*.
- axis** [int or None, optional] Axis along which to operate. Default is 0. If *None*, compute over the whole array *a*.
- inclusive** [{True, False}, optional] This flag determines whether values exactly equal to the lower limit are included. The default value is *True*.

Returns

- tmin** [float, int or ndarray]

Notes

For more details on `tmin`, see `stats.tmin`.

Examples

```
>>> from scipy.stats import mstats
>>> a = np.array([[6, 8, 3, 0],
...              [3, 2, 1, 2],
...              [8, 1, 8, 2],
...              [5, 3, 0, 2],
...              [4, 7, 5, 2]])
...
>>> mstats.tmin(a, 5)
masked_array(data=[5, 7, 5, --],
             mask=[False, False, False,  True],
             fill_value=999999)
```

`scipy.stats.mstats.tmax`

`scipy.stats.mstats.tmax(a, upperlimit=None, axis=0, inclusive=True)`

Compute the trimmed maximum

This function computes the maximum value of an array along a given axis, while ignoring values larger than a specified upper limit.

Parameters

- a** [array_like] array of values
- upperlimit** [None or float, optional] Values in the input array greater than the given limit will be ignored. When upperlimit is None, then all values are used. The default value is None.
- axis** [int or None, optional] Axis along which to operate. Default is 0. If None, compute over the whole array *a*.
- inclusive** [{True, False}, optional] This flag determines whether values exactly equal to the upper limit are included. The default value is True.

Returns

- tmax** [float, int or ndarray]

Notes

For more details on `tmax`, see `stats.tmax`.

Examples

```
>>> from scipy.stats import mstats
>>> a = np.array([[6, 8, 3, 0],
...              [3, 9, 1, 2],
...              [8, 7, 8, 2],
...              [5, 6, 0, 2],
...              [4, 5, 5, 2]])
...
...
>>> mstats.tmax(a, 4)
masked_array(data=[4, --, 3, 2],
             mask=[False,  True, False, False],
             fill_value=999999)
```

scipy.stats.mstats.tsem

`scipy.stats.mstats.tsem(a, limits=None, inclusive=True, True, axis=0, ddof=1)`

Compute the trimmed standard error of the mean.

This function finds the standard error of the mean for given values, ignoring values outside the given *limits*.

Parameters

a	[array_like] array of values
limits	[None or (lower limit, upper limit), optional] Values in the input array less than the lower limit or greater than the upper limit will be ignored. When <i>limits</i> is <i>None</i> , then all values are used. Either of the limit values in the tuple can also be <i>None</i> representing a half-open interval. The default value is <i>None</i> .
inclusive	[(bool, bool), optional] A tuple consisting of the (lower flag, upper flag). These flags determine whether values exactly equal to the lower or upper limits are included. The default value is (True, True).
axis	[int or None, optional] Axis along which to operate. If <i>None</i> , compute over the whole array. Default is zero.
ddof	[int, optional] Delta degrees of freedom. Default is 1.

Returns

tsem	[float]
-------------	---------

Notes

For more details on *tsem*, see *stats.tsem*.

scipy.stats.mstats.variation

`scipy.stats.mstats.variation(a, axis=0)`

Computes the coefficient of variation, the ratio of the biased standard deviation to the mean.

Parameters

a [array_like] Input array.
axis [int or None, optional] Axis along which to calculate the coefficient of variation. Default is 0. If None, compute over the whole array *a*.

Returns

variation [ndarray] The calculated variation along the requested axis.

Notes

For more details about *variation*, see *stats.variation*.

Examples

```
>>> from scipy.stats.mstats import variation
>>> a = np.array([2, 8, 4])
>>> variation(a)
0.5345224838248487
>>> b = np.array([2, 8, 3, 4])
>>> c = np.ma.masked_array(b, mask=[0, 0, 1, 0])
>>> variation(c)
0.5345224838248487
```

In the example above, it can be seen that this works the same as *stats.variation* except ‘stats.mstats.variation’ ignores masked array elements.

scipy.stats.mstats.find_repeats

`scipy.stats.mstats.find_repeats(arr)`

Find repeats in *arr* and return a tuple (repeats, repeat_count).

The input is cast to float64. Masked values are discarded.

Parameters

arr [sequence] Input array. The array is flattened if it is not 1D.

Returns

repeats [ndarray] Array of repeated values.
counts [ndarray] Array of counts.

scipy.stats.mstats.sem

`scipy.stats.mstats.sem(a, axis=0, ddof=1)`

Calculates the standard error of the mean of the input array.

Also sometimes called standard error of measurement.

Parameters

- a** [array_like] An array containing the values for which the standard error is returned.
- axis** [int or None, optional] If axis is None, ravel *a* first. If axis is an integer, this will be the axis over which to operate. Defaults to 0.
- ddof** [int, optional] Delta degrees-of-freedom. How many degrees of freedom to adjust for bias in limited samples relative to the population estimate of variance. Defaults to 1.

Returns

- s** [ndarray or float] The standard error of the mean in the sample(s), along the input axis.

Notes

The default value for *ddof* changed in scipy 0.15.0 to be consistent with *stats.sem* as well as with the most common definition used (like in the R documentation).

Examples

Find standard error along the first axis:

```
>>> from scipy import stats
>>> a = np.arange(20).reshape(5,4)
>>> print(stats.mstats.sem(a))
[2.8284271247461903 2.8284271247461903 2.8284271247461903
 2.8284271247461903]
```

Find standard error across the whole array, using n degrees of freedom:

```
>>> print(stats.mstats.sem(a, axis=None, ddof=0))
1.2893796958227628
```

scipy.stats.mstats.trimmed_mean

`scipy.stats.mstats.trimmed_mean(a, limits=0.1, 0.1, inclusive=1, 1, relative=True, axis=None)`

Returns the trimmed mean of the data along the given axis.

Parameters

- a** [sequence] Input array
- limits** [{None, tuple}, optional] If *relative* is False, tuple (lower limit, upper limit) in absolute values. Values of the input array lower (greater) than the lower (upper) limit are masked. If *relative* is True, tuple (lower percentage, upper percentage) to cut on each side of the array, with respect to the number of unmasked data. Noting *n* the number of unmasked data before trimming, the (*n**limits[0])th smallest data and the (*n**limits[1])th largest data are masked, and the total number of unmasked data after

trimming is $n*(1-\text{sum}(\text{limits}))$. In each case, the value of one limit can be set to `None` to indicate an open interval.

If `limits` is `None`, no trimming is performed

- inclusive** [(bool, bool) tuple], optional] If *relative* is `False`, tuple indicating whether values exactly equal to the absolute limits are allowed. If *relative* is `True`, tuple indicating whether the number of data being masked on each side should be rounded (`True`) or truncated (`False`).
- relative** [bool, optional] Whether to consider the limits as absolute values (`False`) or proportions to cut (`True`).
- axis** [int, optional] Axis along which to trim.

scipy.stats.mstats.trimmed_mean_ci

`scipy.stats.mstats.trimmed_mean_ci` (*data*, *limits*=0.2, 0.2, *inclusive*=`True`, `True`, *alpha*=0.05, *axis*=`None`)

Selected confidence interval of the trimmed mean along the given axis.

Parameters

- data** [array_like] Input data.
- limits** [(None, tuple), optional] `None` or a two item tuple. Tuple of the percentages to cut on each side of the array, with respect to the number of unmasked data, as floats between 0. and 1. If *n* is the number of unmasked data before trimming, then $(n * \text{limits}[0])$ th smallest data and $(n * \text{limits}[1])$ th largest data are masked. The total number of unmasked data after trimming is $n * (1. - \text{sum}(\text{limits}))$. The value of one limit can be set to `None` to indicate an open interval. Defaults to (0.2, 0.2).
- inclusive** [(2,) tuple of boolean, optional] If *relative*==`False`, tuple indicating whether values exactly equal to the absolute limits are allowed. If *relative*==`True`, tuple indicating whether the number of data being masked on each side should be rounded (`True`) or truncated (`False`). Defaults to (`True`, `True`).
- alpha** [float, optional] Confidence level of the intervals. Defaults to 0.05.
- axis** [int, optional] Axis along which to cut. If `None`, uses a flattened version of *data*. Defaults to `None`.

Returns

- trimmed_mean_ci** [(2,) ndarray] The lower and upper confidence intervals of the trimmed data.

scipy.stats.mstats.trimmed_std

`scipy.stats.mstats.trimmed_std` (*a*, *limits*=0.1, 0.1, *inclusive*=`1`, `1`, *relative*=`True`, *axis*=`None`, *ddof*=0)

Returns the trimmed standard deviation of the data along the given axis.

Parameters

- a** [sequence] Input array
- limits** [(None, tuple), optional] If *relative* is `False`, tuple (lower limit, upper limit) in absolute values. Values of the input array lower (greater) than the lower (upper) limit are masked. If *relative* is `True`, tuple (lower percentage, upper percentage) to cut on each side of the array, with respect to the number of unmasked data. Noting *n* the number of unmasked data before trimming, the $(n*\text{limits}[0])$ th smallest data and the $(n*\text{limits}[1])$ th largest data are masked, and the total number of unmasked data after

trimming is $n*(1-\text{sum}(\text{limits}))$ In each case, the value of one limit can be set to None to indicate an open interval.
 If limits is None, no trimming is performed

inclusive	[(bool, bool) tuple], optional] If <i>relative</i> is False, tuple indicating whether values exactly equal to the absolute limits are allowed. If <i>relative</i> is True, tuple indicating whether the number of data being masked on each side should be rounded (True) or truncated (False).
relative	[bool, optional] Whether to consider the limits as absolute values (False) or proportions to cut (True).
axis	[int, optional] Axis along which to trim.
ddof	[[0,integer], optional] Means Delta Degrees of Freedom. The denominator used during computations is (n-ddof). DDOF=0 corresponds to a biased estimate, DDOF=1 to an unbiased estimate of the variance.

scipy.stats.mstats.trimmed_var

`scipy.stats.mstats.trimmed_var(a, limits=0.1, 0.1, inclusive=1, 1, relative=True, axis=None, ddof=0)`

Returns the trimmed variance of the data along the given axis.

Parameters

a	[sequence] Input array
limits	[[None, tuple], optional] If <i>relative</i> is False, tuple (lower limit, upper limit) in absolute values. Values of the input array lower (greater) than the lower (upper) limit are masked. If <i>relative</i> is True, tuple (lower percentage, upper percentage) to cut on each side of the array, with respect to the number of unmasked data. Noting n the number of unmasked data before trimming, the (n*limits[0])th smallest data and the (n*limits[1])th largest data are masked, and the total number of unmasked data after trimming is $n*(1-\text{sum}(\text{limits}))$ In each case, the value of one limit can be set to None to indicate an open interval. If limits is None, no trimming is performed
inclusive	[(bool, bool) tuple], optional] If <i>relative</i> is False, tuple indicating whether values exactly equal to the absolute limits are allowed. If <i>relative</i> is True, tuple indicating whether the number of data being masked on each side should be rounded (True) or truncated (False).
relative	[bool, optional] Whether to consider the limits as absolute values (False) or proportions to cut (True).
axis	[int, optional] Axis along which to trim.
ddof	[[0,integer], optional] Means Delta Degrees of Freedom. The denominator used during computations is (n-ddof). DDOF=0 corresponds to a biased estimate, DDOF=1 to an unbiased estimate of the variance.

Frequency statistics

<code>scoreatpercentile(data, per[, limit, ...])</code>	Calculate the score at the given 'per' percentile of the sequence a.
---	--

scipy.stats.mstats.scoreatpercentile

`scipy.stats.mstats.scoreatpercentile` (*data*, *per*, *limit=()*, *alphan=0.4*, *betan=0.4*)

Calculate the score at the given 'per' percentile of the sequence a. For example, the score at per=50 is the median.

This function is a shortcut to `mquantile`

Correlation functions

<code>f_oneway(*args)</code>	Performs a 1-way ANOVA, returning an F-value and probability given any number of groups.
<code>pearsonr(x, y)</code>	Calculates a Pearson correlation coefficient and the p-value for testing non-correlation.
<code>spearmanr(x[, y, use_ties, axis, nan_policy])</code>	Calculates a Spearman rank-order correlation coefficient and the p-value to test for non-correlation.
<code>pointbiserialr(x, y)</code>	Calculates a point biserial correlation coefficient and its p-value.
<code>kendalltau(x, y[, use_ties, use_missing, method])</code>	Computes Kendall's rank correlation tau on two variables <i>x</i> and <i>y</i> .
<code>kendalltau_seasonal(x)</code>	Computes a multivariate Kendall's rank correlation tau, for seasonal data.
<code>linregress(x[, y])</code>	Linear regression calculation
<code>siegelslopes(y[, x, method])</code>	Computes the Siegel estimator for a set of points (<i>x</i> , <i>y</i>).
<code>theilslopes(y[, x, alpha])</code>	Computes the Theil-Sen estimator for a set of points (<i>x</i> , <i>y</i>).
<code>sen_seasonal_slopes(x)</code>	

scipy.stats.mstats.f_oneway

`scipy.stats.mstats.f_oneway` (**args*)

Performs a 1-way ANOVA, returning an F-value and probability given any number of groups. From Heiman, pp.394-7.

Usage: `f_oneway(*args)`, where **args* is 2 or more arrays, one per treatment group.

Returns

statistic [float] The computed F-value of the test.
pvalue [float] The associated p-value from the F-distribution.

scipy.stats.mstats.pearsonr

`scipy.stats.mstats.pearsonr` (*x*, *y*)

Calculates a Pearson correlation coefficient and the p-value for testing non-correlation.

The Pearson correlation coefficient measures the linear relationship between two datasets. Strictly speaking, Pearson's correlation requires that each dataset be normally distributed. Like other correlation coefficients, this one varies between -1 and +1 with 0 implying no correlation. Correlations of -1 or +1 imply an exact linear relationship. Positive correlations imply that as *x* increases, so does *y*. Negative correlations imply that as *x* increases, *y* decreases.

The p-value roughly indicates the probability of an uncorrelated system producing datasets that have a Pearson correlation at least as extreme as the one computed from these datasets. The p-values are not entirely reliable but are probably reasonable for datasets larger than 500 or so.

Parameters

x [1-D array_like] Input
y [1-D array_like] Input

Returns

pearsonr [float] Pearson's correlation coefficient, 2-tailed p-value.

References

<http://www.statsoft.com/textbook/glosp.html#Pearson%20Correlation>

scipy.stats.mstats.spearmanr

`scipy.stats.mstats.spearmanr(x, y=None, use_ties=True, axis=None, nan_policy='propagate')`

Calculates a Spearman rank-order correlation coefficient and the p-value to test for non-correlation.

The Spearman correlation is a nonparametric measure of the linear relationship between two datasets. Unlike the Pearson correlation, the Spearman correlation does not assume that both datasets are normally distributed. Like other correlation coefficients, this one varies between -1 and +1 with 0 implying no correlation. Correlations of -1 or +1 imply a monotonic relationship. Positive correlations imply that as x increases, so does y . Negative correlations imply that as x increases, y decreases.

Missing values are discarded pair-wise: if a value is missing in x , the corresponding value in y is masked.

The p-value roughly indicates the probability of an uncorrelated system producing datasets that have a Spearman correlation at least as extreme as the one computed from these datasets. The p-values are not entirely reliable but are probably reasonable for datasets larger than 500 or so.

Parameters

x, y [1D or 2D array_like, y is optional] One or two 1-D or 2-D arrays containing multiple variables and observations. When these are 1-D, each represents a vector of observations of a single variable. For the behavior in the 2-D case, see under `axis`, below.

use_ties [bool, optional] DO NOT USE. Does not do anything, keyword is only left in place for backwards compatibility reasons.

axis [int or None, optional] If `axis=0` (default), then each column represents a variable, with observations in the rows. If `axis=1`, the relationship is transposed: each row represents a variable, while the columns contain observations. If `axis=None`, then both arrays will be raveled.

nan_policy [{"propagate", "raise", "omit"}, optional] Defines how to handle when input contains nan. 'propagate' returns nan, 'raise' throws an error, 'omit' performs the calculations ignoring nan values. Default is 'propagate'.

Returns

correlation [float] Spearman correlation coefficient
pvalue [float] 2-tailed p-value.

References

[CRCProbStat2000] section 14.7

scipy.stats.mstats.pointbiserialr

`scipy.stats.mstats.pointbiserialr(x, y)`

Calculates a point biserial correlation coefficient and its p-value.

Parameters

x [array_like of bools] Input array.
y [array_like] Input array.

Returns

correlation [float] R value
pvalue [float] 2-tailed p-value

Notes

Missing values are considered pair-wise: if a value is missing in x, the corresponding value in y is masked.

For more details on *pointbiserialr*, see *stats.pointbiserialr*.

scipy.stats.mstats.kendalltau

`scipy.stats.mstats.kendalltau(x, y, use_ties=True, use_missing=False, method='auto')`

Computes Kendall's rank correlation tau on two variables x and y.

Parameters

x [sequence] First data list (for example, time).
y [sequence] Second data list.
use_ties [{True, False}, optional] Whether ties correction should be performed.
use_missing [{False, True}, optional] Whether missing data should be allocated a rank of 0 (False) or the average rank (True)

method: {'auto', 'asymptotic', 'exact'}, optional

Defines which method is used to calculate the p-value [1]. 'asymptotic' uses a normal approximation valid for large samples. 'exact' computes the exact p-value, but can only be used if no ties are present. As the sample size increases, the 'exact' computation time may grow and the result may lose some precision. 'auto' is the default and selects the appropriate method based on a trade-off between speed and accuracy.

Returns

correlation [float] Kendall tau
pvalue [float] Approximate 2-side p-value.

References

[1]

scipy.stats.mstats.kendalltau_seasonal

`scipy.stats.mstats.kendalltau_seasonal(x)`

Computes a multivariate Kendall's rank correlation tau, for seasonal data.

Parameters

x [2-D ndarray] Array of seasonal data, with seasons in columns.

scipy.stats.mstats.linregress

`scipy.stats.mstats.linregress(x, y=None)`

Linear regression calculation

Note that the non-masked version is used, and that this docstring is replaced by the non-masked docstring + some info on missing data.

scipy.stats.mstats.siegelslopes

`scipy.stats.mstats.siegelslopes(y, x=None, method='hierarchical')`

Computes the Siegel estimator for a set of points (x, y).

siegelslopes implements a method for robust linear regression using repeated medians to fit a line to the points (x, y). The method is robust to outliers with an asymptotic breakdown point of 50%.

Parameters

y [array_like] Dependent variable.
x [array_like or None, optional] Independent variable. If None, use `arange(len(y))` instead.
method [{'hierarchical', 'separate'}] If 'hierarchical', estimate the intercept using the estimated slope `medslope` (default option). If 'separate', estimate the intercept independent of the estimated slope. See Notes for details.

Returns

medslope [float] Estimate of the slope of the regression line.
medintercept [float] Estimate of the intercept of the regression line.

See also:

theilslopes

a similar technique without repeated medians

Notes

For more details on *siegelslopes*, see `scipy.stats.siegelslopes`.

scipy.stats.mstats.theilslopes

`scipy.stats.mstats.theilslopes` (*y*, *x=None*, *alpha=0.95*)

Computes the Theil-Sen estimator for a set of points (*x*, *y*).

theilslopes implements a method for robust linear regression. It computes the slope as the median of all slopes between paired values.

Parameters

- y** [array_like] Dependent variable.
- x** [array_like or None, optional] Independent variable. If None, use `arange(len(y))` instead.
- alpha** [float, optional] Confidence degree between 0 and 1. Default is 95% confidence. Note that *alpha* is symmetric around 0.5, i.e. both 0.1 and 0.9 are interpreted as “find the 90% confidence interval”.

Returns

- medslope** [float] Theil slope.
- medintercept** [float] Intercept of the Theil line, as `median(y) - medslope*median(x)`.
- lo_slope** [float] Lower bound of the confidence interval on *medslope*.
- up_slope** [float] Upper bound of the confidence interval on *medslope*.

See also:

siegelslopes

a similar technique with repeated medians

Notes

For more details on *theilslopes*, see `stats.theilslopes`.

scipy.stats.mstats.sen_seasonal_slopes

`scipy.stats.mstats.sen_seasonal_slopes` (*x*)

Statistical tests

<code>ttest_1samp(a, popmean[, axis])</code>	Calculates the T-test for the mean of ONE group of scores.
<code>ttest_onesamp(a, popmean[, axis])</code>	Calculates the T-test for the mean of ONE group of scores.
<code>ttest_ind(a, b[, axis, equal_var])</code>	Calculates the T-test for the means of TWO INDEPENDENT samples of scores.
<code>ttest_rel(a, b[, axis])</code>	Calculates the T-test on TWO RELATED samples of scores, a and b.

continues on next page

Table 276 – continued from previous page

<code>chisquare(f_obs[, f_exp, ddof, axis])</code>	Calculate a one-way chi-square test.
<code>kstest(data1, data2[, args, alternative, mode])</code>	
<i>Parameters</i>	
<code>ks_2samp(data1, data2[, alternative, mode])</code>	Computes the Kolmogorov-Smirnov test on two samples.
<code>ks_1samp(x, cdf[, args, alternative, mode])</code>	Computes the Kolmogorov-Smirnov test on one sample of masked values.
<code>ks_twosamp(data1, data2[, alternative, mode])</code>	Computes the Kolmogorov-Smirnov test on two samples.
<code>mannwhitneyu(x, y[, use_continuity])</code>	Computes the Mann-Whitney statistic
<code>rankdata(data[, axis, use_missing])</code>	Returns the rank (also known as order statistics) of each data point along the given axis.
<code>kruskal(*args)</code>	Compute the Kruskal-Wallis H-test for independent samples
<code>kruskalwallis(*args)</code>	Compute the Kruskal-Wallis H-test for independent samples
<code>friedmanchisquare(*args)</code>	Friedman Chi-Square is a non-parametric, one-way within-subjects ANOVA.
<code>brunnermunzel(x, y[, alternative, distribution])</code>	Computes the Brunner-Munzel test on samples x and y
<code>skewtest(a[, axis])</code>	Tests whether the skew is different from the normal distribution.
<code>kurtosistest(a[, axis])</code>	Tests whether a dataset has normal kurtosis
<code>normaltest(a[, axis])</code>	Tests whether a sample differs from a normal distribution.

scipy.stats.mstats.ttest_1samp

`scipy.stats.mstats.ttest_1samp(a, popmean, axis=0)`

Calculates the T-test for the mean of ONE group of scores.

Parameters

a	[array_like] sample observation
popmean	[float or array_like] expected value in null hypothesis, if array_like than it must have the same shape as <i>a</i> excluding the axis dimension
axis	[int or None, optional] Axis along which to compute test. If None, compute over the whole array <i>a</i> .

Returns

statistic	[float or array] t-statistic
pvalue	[float or array] two-tailed p-value

Notes

For more details on `ttest_1samp`, see `stats.ttest_1samp`.

scipy.stats.mstats.ttest_onesamp`scipy.stats.mstats.ttest_onesamp(a, popmean, axis=0)`

Calculates the T-test for the mean of ONE group of scores.

Parameters

- a** [array_like] sample observation
- popmean** [float or array_like] expected value in null hypothesis, if array_like than it must have the same shape as *a* excluding the axis dimension
- axis** [int or None, optional] Axis along which to compute test. If None, compute over the whole array *a*.

Returns

- statistic** [float or array] t-statistic
- pvalue** [float or array] two-tailed p-value

NotesFor more details on `ttest_1samp`, see `stats.ttest_1samp`.**scipy.stats.mstats.ttest_ind**`scipy.stats.mstats.ttest_ind(a, b, axis=0, equal_var=True)`

Calculates the T-test for the means of TWO INDEPENDENT samples of scores.

Parameters

- a, b** [array_like] The arrays must have the same shape, except in the dimension corresponding to *axis* (the first, by default).
- axis** [int or None, optional] Axis along which to compute test. If None, compute over the whole arrays, *a*, and *b*.
- equal_var** [bool, optional] If True, perform a standard independent 2 sample test that assumes equal population variances. If False, perform Welch's t-test, which does not assume equal population variance.
New in version 0.17.0.

Returns

- statistic** [float or array] The calculated t-statistic.
- pvalue** [float or array] The two-tailed p-value.

NotesFor more details on `ttest_ind`, see `stats.ttest_ind`.

scipy.stats.mstats.ttest_rel

`scipy.stats.mstats.ttest_rel` (*a*, *b*, *axis*=0)

Calculates the T-test on TWO RELATED samples of scores, *a* and *b*.

Parameters

a, b [array_like] The arrays must have the same shape.
axis [int or None, optional] Axis along which to compute test. If None, compute over the whole arrays, *a*, and *b*.

Returns

statistic [float or array] t-statistic
pvalue [float or array] two-tailed p-value

Notes

For more details on `ttest_rel`, see `stats.ttest_rel`.

scipy.stats.mstats.chisquare

`scipy.stats.mstats.chisquare` (*f_obs*, *f_exp*=None, *ddof*=0, *axis*=0)

Calculate a one-way chi-square test.

The chi-square test tests the null hypothesis that the categorical data has the given frequencies.

Parameters

f_obs [array_like] Observed frequencies in each category.
f_exp [array_like, optional] Expected frequencies in each category. By default the categories are assumed to be equally likely.
ddof [int, optional] “Delta degrees of freedom”: adjustment to the degrees of freedom for the p-value. The p-value is computed using a chi-squared distribution with $k - 1 - \text{ddof}$ degrees of freedom, where *k* is the number of observed frequencies. The default value of *ddof* is 0.
axis [int or None, optional] The axis of the broadcast result of *f_obs* and *f_exp* along which to apply the test. If *axis* is None, all values in *f_obs* are treated as a single data set. Default is 0.

Returns

chisq [float or ndarray] The chi-squared test statistic. The value is a float if *axis* is None or *f_obs* and *f_exp* are 1-D.
p [float or ndarray] The p-value of the test. The value is a float if *ddof* and the return value *chisq* are scalars.

See also:

`scipy.stats.power_divergence`

Notes

This test is invalid when the observed or expected frequencies in each category are too small. A typical rule is that all of the observed and expected frequencies should be at least 5.

The default degrees of freedom, $k-1$, are for the case when no parameters of the distribution are estimated. If p parameters are estimated by efficient maximum likelihood then the correct degrees of freedom are $k-1-p$. If the parameters are estimated in a different way, then the dof can be between $k-1-p$ and $k-1$. However, it is also possible that the asymptotic distribution is not chi-square, in which case this test is not appropriate.

References

[1], [2]

Examples

When just f_{obs} is given, it is assumed that the expected frequencies are uniform and given by the mean of the observed frequencies.

```
>>> from scipy.stats import chisquare
>>> chisquare([16, 18, 16, 14, 12, 12])
(2.0, 0.84914503608460956)
```

With f_{exp} the expected frequencies can be given.

```
>>> chisquare([16, 18, 16, 14, 12, 12], f_exp=[16, 16, 16, 16, 16, 8])
(3.5, 0.62338762774958223)
```

When f_{obs} is 2-D, by default the test is applied to each column.

```
>>> obs = np.array([[16, 18, 16, 14, 12, 12], [32, 24, 16, 28, 20, 24]])
>>> obs.shape
(6, 2)
>>> chisquare(obs)
(array([ 2.          ,  6.66666667]), array([ 0.84914504,  0.24663415]))
```

By setting $axis=None$, the test is applied to all data in the array, which is equivalent to applying the test to the flattened array.

```
>>> chisquare(obs, axis=None)
(23.31034482758621, 0.015975692534127565)
>>> chisquare(obs.ravel())
(23.31034482758621, 0.015975692534127565)
```

$ddof$ is the change to make to the default degrees of freedom.

```
>>> chisquare([16, 18, 16, 14, 12, 12], ddof=1)
(2.0, 0.73575888234288467)
```

The calculation of the p-values is done by broadcasting the chi-squared statistic with $ddof$.

```
>>> chisquare([16, 18, 16, 14, 12, 12], ddof=[0,1,2])
(2.0, array([ 0.84914504,  0.73575888,  0.5724067 ]))
```


f_{obs} and f_{exp} are also broadcast. In the following, f_{obs} has shape (6,) and f_{exp} has shape (2, 6), so the result of broadcasting f_{obs} and f_{exp} has shape (2, 6). To compute the desired chi-squared statistics, we use `axis=1`:

```
>>> chisquare([16, 18, 16, 14, 12, 12],
...           f_exp=[[16, 16, 16, 16, 16, 8], [8, 20, 20, 16, 12, 12]],
...           axis=1)
(array([ 3.5 ,  9.25]), array([ 0.62338763,  0.09949846]))
```

scipy.stats.mstats.kstest

`scipy.stats.mstats.kstest` (*data1*, *data2*, *args*=(), *alternative*='two-sided', *mode*='auto')

Parameters

data1	[array_like]
data2	[str, callable or array_like]
args	[tuple, sequence, optional] Distribution parameters, used if <i>data1</i> or <i>data2</i> are strings.
alternative	[str, as documented in stats.kstest]
mode	[str, as documented in stats.kstest]

Returns

tuple of (K-S statistic, probability)

scipy.stats.mstats.ks_2samp

`scipy.stats.mstats.ks_2samp` (*data1*, *data2*, *alternative*='two-sided', *mode*='auto')

Computes the Kolmogorov-Smirnov test on two samples.

Missing values in *x* and/or *y* are discarded.

Parameters

data1	[array_like] First data set
data2	[array_like] Second data set
alternative	[{'two-sided', 'less', 'greater'}, optional] Indicates the alternative hypothesis. Default is 'two-sided'.
mode	[{'auto', 'exact', 'asympt'}, optional] Defines the method used for calculating the p-value. The following options are available (default is 'auto'): <ul style="list-style-type: none"> • 'auto': use 'exact' for small size arrays, 'asympt' for large • 'exact': use approximation to exact distribution of test statistic • 'asympt': use asymptotic distribution of test statistic

Returns

d	[float] Value of the Kolmogorov Smirnov test
p	[float] Corresponding p-value.

scipy.stats.mstats.ks_1samp

`scipy.stats.mstats.ks_1samp(x, cdf, args=(), alternative='two-sided', mode='auto')`

Computes the Kolmogorov-Smirnov test on one sample of masked values.

Missing values in *x* are discarded.

Parameters

- | | |
|--------------------|--|
| x | [array_like] a 1-D array of observations of random variables. |
| cdf | [str or callable] If a string, it should be the name of a distribution in <code>scipy.stats</code> . If a callable, that callable is used to calculate the cdf. |
| args | [tuple, sequence, optional] Distribution parameters, used if <i>cdf</i> is a string. |
| alternative | [{'two-sided', 'less', 'greater'}, optional] Indicates the alternative hypothesis. Default is 'two-sided'. |
| mode | [{'auto', 'exact', 'asympt'}, optional] Defines the method used for calculating the p-value. The following options are available (default is 'auto'): <ul style="list-style-type: none"> • 'auto': use 'exact' for small size arrays, 'asympt' for large • 'exact': use approximation to exact distribution of test statistic • 'asympt': use asymptotic distribution of test statistic |

Returns

- | | |
|----------|--|
| d | [float] Value of the Kolmogorov Smirnov test |
| p | [float] Corresponding p-value. |

scipy.stats.mstats.ks_twosamp

`scipy.stats.mstats.ks_twosamp(data1, data2, alternative='two-sided', mode='auto')`

Computes the Kolmogorov-Smirnov test on two samples.

Missing values in *x* and/or *y* are discarded.

Parameters

- | | |
|--------------------|--|
| data1 | [array_like] First data set |
| data2 | [array_like] Second data set |
| alternative | [{'two-sided', 'less', 'greater'}, optional] Indicates the alternative hypothesis. Default is 'two-sided'. |
| mode | [{'auto', 'exact', 'asympt'}, optional] Defines the method used for calculating the p-value. The following options are available (default is 'auto'): <ul style="list-style-type: none"> • 'auto': use 'exact' for small size arrays, 'asympt' for large • 'exact': use approximation to exact distribution of test statistic • 'asympt': use asymptotic distribution of test statistic |

Returns

- | | |
|----------|--|
| d | [float] Value of the Kolmogorov Smirnov test |
| p | [float] Corresponding p-value. |

scipy.stats.mstats.mannwhitneyu

`scipy.stats.mstats.mannwhitneyu(x, y, use_continuity=True)`

Computes the Mann-Whitney statistic

Missing values in *x* and/or *y* are discarded.

Parameters

x [sequence] Input
y [sequence] Input
use_continuity [{True, False}, optional] Whether a continuity correction (1/2.) should be taken into account.

Returns

statistic [float] The Mann-Whitney statistics
pvalue [float] Approximate p-value assuming a normal distribution.

scipy.stats.mstats.rankdata

`scipy.stats.mstats.rankdata(data, axis=None, use_missing=False)`

Returns the rank (also known as order statistics) of each data point along the given axis.

If some values are tied, their rank is averaged. If some values are masked, their rank is set to 0 if `use_missing` is False, or set to the average rank of the unmasked values if `use_missing` is True.

Parameters

data [sequence] Input data. The data is transformed to a masked array
axis [{None,int}, optional] Axis along which to perform the ranking. If None, the array is first flattened. An exception is raised if the axis is specified for arrays with a dimension larger than 2
use_missing [bool, optional] Whether the masked values have a rank of 0 (False) or equal to the average rank of the unmasked values (True).

scipy.stats.mstats.kruskal

`scipy.stats.mstats.kruskal(*args)`

Compute the Kruskal-Wallis H-test for independent samples

Parameters

sample1, sample2, ...
 [array_like] Two or more arrays with the sample measurements can be given as arguments.

Returns

statistic [float] The Kruskal-Wallis H statistic, corrected for ties
pvalue [float] The p-value for the test using the assumption that H has a chi square distribution

Notes

For more details on `kruskal`, see `stats.kruskal`.

Examples

```
>>> from scipy.stats.mstats import kruskal
```

Random samples from three different brands of batteries were tested to see how long the charge lasted. Results were as follows:

```
>>> a = [6.3, 5.4, 5.7, 5.2, 5.0]
>>> b = [6.9, 7.0, 6.1, 7.9]
>>> c = [7.2, 6.9, 6.1, 6.5]
```

Test the hypothesis that the distribution functions for all of the brands' durations are identical. Use 5% level of significance.

```
>>> kruskal(a, b, c)
KruskalResult(statistic=7.113812154696133, pvalue=0.028526948491942164)
```

The null hypothesis is rejected at the 5% level of significance because the returned p-value is less than the critical value of 5%.

`scipy.stats.mstats.kruskalwallis`

`scipy.stats.mstats.kruskalwallis(*args)`

Compute the Kruskal-Wallis H-test for independent samples

Parameters

sample1, sample2, ...

[array_like] Two or more arrays with the sample measurements can be given as arguments.

Returns

statistic [float] The Kruskal-Wallis H statistic, corrected for ties

pvalue [float] The p-value for the test using the assumption that H has a chi square distribution

Notes

For more details on `kruskal`, see `stats.kruskal`.

Examples

```
>>> from scipy.stats.mstats import kruskal
```

Random samples from three different brands of batteries were tested to see how long the charge lasted. Results were as follows:

```
>>> a = [6.3, 5.4, 5.7, 5.2, 5.0]
>>> b = [6.9, 7.0, 6.1, 7.9]
>>> c = [7.2, 6.9, 6.1, 6.5]
```

Test the hypothesis that the distribution functions for all of the brands' durations are identical. Use 5% level of significance.

```
>>> kruskal(a, b, c)
KruskalResult(statistic=7.113812154696133, pvalue=0.028526948491942164)
```

The null hypothesis is rejected at the 5% level of significance because the returned p-value is less than the critical value of 5%.

scipy.stats.mstats.friedmanchisquare

`scipy.stats.mstats.friedmanchisquare(*args)`

Friedman Chi-Square is a non-parametric, one-way within-subjects ANOVA. This function calculates the Friedman Chi-square test for repeated measures and returns the result, along with the associated probability value.

Each input is considered a given group. Ideally, the number of treatments among each group should be equal. If this is not the case, only the first n treatments are taken into account, where n is the number of treatments of the smallest group. If a group has some missing values, the corresponding treatments are masked in the other groups. The test statistic is corrected for ties.

Masked values in one group are propagated to the other groups.

Returns

statistic [float] the test statistic.
pvalue [float] the associated p-value.

scipy.stats.mstats.brunnermunzel

`scipy.stats.mstats.brunnermunzel(x, y, alternative='two-sided', distribution='t')`

Computes the Brunner-Munzel test on samples x and y

Missing values in x and/or y are discarded.

Parameters

x, y [array_like] Array of samples, should be one-dimensional.
alternative ['less', 'two-sided', or 'greater', optional] Whether to get the p-value for the one-sided hypothesis ('less' or 'greater') or for the two-sided hypothesis ('two-sided'). Defaults value is 'two-sided'.
distribution: 't' or 'normal', optional
 Whether to get the p-value by t-distribution or by standard normal distribution. Defaults value is 't'.

Returns

statistic [float] The Brunner-Munzer W statistic.
pvalue [float] p-value assuming an t distribution. One-sided or two-sided, depending on the choice of *alternative* and *distribution*.

See also:

mannwhitneyu

Mann-Whitney rank test on two samples.

Notes

For more details on *brunnermunzel*, see *stats.brunnermunzel*.

scipy.stats.mstats.skewtest

`scipy.stats.mstats.skewtest` (*a*, *axis=0*)

Tests whether the skew is different from the normal distribution.

Parameters

a [array] The data to be tested
axis [int or None, optional] Axis along which statistics are calculated. Default is 0. If None, compute over the whole array *a*.

Returns

statistic [float] The computed z-score for this test.
pvalue [float] a 2-sided p-value for the hypothesis test

Notes

For more details about *skewtest*, see *stats.skewtest*.

scipy.stats.mstats.kurtosistest

`scipy.stats.mstats.kurtosistest` (*a*, *axis=0*)

Tests whether a dataset has normal kurtosis

Parameters

a [array] array of the sample data
axis [int or None, optional] Axis along which to compute test. Default is 0. If None, compute over the whole array *a*.

Returns

statistic [float] The computed z-score for this test.
pvalue [float] The 2-sided p-value for the hypothesis test

Notes

For more details about *kurtosistest*, see *stats.kurtosistest*.

scipy.stats.mstats.normaltest

`scipy.stats.mstats.normaltest(a, axis=0)`

Tests whether a sample differs from a normal distribution.

Parameters

a [array_like] The array containing the data to be tested.
axis [int or None, optional] Axis along which to compute test. Default is 0. If None, compute over the whole array *a*.

Returns

statistic [float or array] $s^2 + k^2$, where *s* is the z-score returned by *skewtest* and *k* is the z-score returned by *kurtosistest*.
pvalue [float or array] A 2-sided chi squared probability for the hypothesis test.

Notes

For more details about *normaltest*, see *stats.normaltest*.

Transformations

<code>obrientransform(*args)</code>	Computes a transform on input data (any number of columns).
<code>trim(a[, limits, inclusive, relative, axis])</code>	Trims an array by masking the data outside some given limits.
<code>trima(a[, limits, inclusive])</code>	Trims an array by masking the data outside some given limits.
<code>trimmed_stde(a[, limits, inclusive, axis])</code>	Returns the standard error of the trimmed mean along the given axis.
<code>trimr(a[, limits, inclusive, axis])</code>	Trims an array by masking some proportion of the data on each end.
<code>trimtail(data[, proportiontocut, tail, ...])</code>	Trims the data by masking values from one tail.
<code>trimboth(data[, proportiontocut, inclusive, ...])</code>	Trims the smallest and largest data values.
<code>winsorize(a[, limits, inclusive, inplace, ...])</code>	Returns a Winsorized version of the input array.
<code>zmap(scores, compare[, axis, ddof])</code>	Calculate the relative z-scores.
<code>zscore(a[, axis, ddof, nan_policy])</code>	Compute the z score.

scipy.stats.mstats.obrientransform

`scipy.stats.mstats.obrientransform(*args)`

Computes a transform on input data (any number of columns). Used to test for homogeneity of variance prior to running one-way stats. Each array in **args* is one level of a factor. If an *f_oneway()* run on the transformed data and found significant, variances are unequal. From Maxwell and Delaney, p.112.

Returns: transformed data for use in an ANOVA

scipy.stats.mstats.trim

`scipy.stats.mstats.trim(a, limits=None, inclusive=True, True, relative=False, axis=None)`

Trims an array by masking the data outside some given limits.

Returns a masked version of the input array.

Parameters

a	[sequence] Input array
limits	[[None, tuple], optional] If <i>relative</i> is False, tuple (lower limit, upper limit) in absolute values. Values of the input array lower (greater) than the lower (upper) limit are masked. If <i>relative</i> is True, tuple (lower percentage, upper percentage) to cut on each side of the array, with respect to the number of unmasked data. Noting <i>n</i> the number of unmasked data before trimming, the (<i>n</i> *limits[0])th smallest data and the (<i>n</i> *limits[1])th largest data are masked, and the total number of unmasked data after trimming is <i>n</i> *(1.-sum(limits)) In each case, the value of one limit can be set to None to indicate an open interval. If limits is None, no trimming is performed
inclusive	[(bool, bool) tuple], optional] If <i>relative</i> is False, tuple indicating whether values exactly equal to the absolute limits are allowed. If <i>relative</i> is True, tuple indicating whether the number of data being masked on each side should be rounded (True) or truncated (False).
relative	[bool, optional] Whether to consider the limits as absolute values (False) or proportions to cut (True).
axis	[int, optional] Axis along which to trim.

Examples

```
>>> from scipy.stats.mstats import trim
>>> z = [ 1, 2, 3, 4, 5, 6, 7, 8, 9,10]
>>> print(trim(z, (3,8)))
[-- -- 3 4 5 6 7 8 -- --]
>>> print(trim(z, (0.1,0.2), relative=True))
[-- 2 3 4 5 6 7 8 -- --]
```

scipy.stats.mstats.trima

`scipy.stats.mstats.trima(a, limits=None, inclusive=True, True)`

Trims an array by masking the data outside some given limits.

Returns a masked version of the input array.

Parameters

a	[array_like] Input array.
limits	[[None, tuple], optional] Tuple of (lower limit, upper limit) in absolute values. Values of the input array lower (greater) than the lower (upper) limit will be masked. A limit is None indicates an open interval.
inclusive	[(bool, bool) tuple, optional] Tuple of (lower flag, upper flag), indicating whether values exactly equal to the lower (upper) limit are allowed.

Examples

```
>>> from scipy.stats.mstats import trima
```

```
>>> a = np.arange(10)
```

The interval is left-closed and right-open, i.e., $[2, 8)$. Trim the array by keeping only values in the interval.

```
>>> trima(a, limits=(2, 8), inclusive=(True, False))
masked_array(data=[--, --, 2, 3, 4, 5, 6, 7, --, --],
             mask=[ True,  True, False, False, False, False, False, False,
                   True,  True],
             fill_value=999999)
```

scipy.stats.mstats.trimmed_stde

`scipy.stats.mstats.trimmed_stde` (*a*, *limits*=0.1, 0.1, *inclusive*=1, 1, *axis*=None)

Returns the standard error of the trimmed mean along the given axis.

Parameters

- a** [sequence] Input array
- limits** [{(0.1,0.1), tuple of float}, optional] tuple (lower percentage, upper percentage) to cut on each side of the array, with respect to the number of unmasked data.
If *n* is the number of unmasked data before trimming, the values smaller than $n * \text{limits}[0]$ and the values larger than $n * \text{limits}[1]$ are masked, and the total number of unmasked data after trimming is $n * (1 - \text{sum}(\text{limits}))$. In each case, the value of one limit can be set to None to indicate an open interval. If *limits* is None, no trimming is performed.
- inclusive** [{(bool, bool) tuple} optional] Tuple indicating whether the number of data being masked on each side should be rounded (True) or truncated (False).
- axis** [int, optional] Axis along which to trim.

Returns

- trimmed_stde**
[scalar or ndarray]

scipy.stats.mstats.trimr

`scipy.stats.mstats.trimr` (*a*, *limits*=None, *inclusive*=True, True, *axis*=None)

Trims an array by masking some proportion of the data on each end. Returns a masked version of the input array.

Parameters

- a** [sequence] Input array.
- limits** [{None, tuple}, optional] Tuple of the percentages to cut on each side of the array, with respect to the number of unmasked data, as floats between 0. and 1. Noting *n* the number of unmasked data before trimming, the ($n * \text{limits}[0]$)th smallest data and the ($n * \text{limits}[1]$)th largest data are masked, and the total number of unmasked data after trimming is $n * (1 - \text{sum}(\text{limits}))$. The value of one limit can be set to None to indicate an open interval.
- inclusive** [{(True, True) tuple}, optional] Tuple of flags indicating whether the number of data being masked on the left (right) end should be truncated (True) or rounded (False) to integers.

axis [None,int], optional] Axis along which to trim. If None, the whole array is trimmed, but its shape is maintained.

scipy.stats.mstats.trimtail

`scipy.stats.mstats.trimtail` (*data*, *proportiontocut*=0.2, *tail*='left', *inclusive*=True, *True*, *axis*=None)
 Trims the data by masking values from one tail.

Parameters

data [array_like] Data to trim.
proportiontocut [float, optional] Percentage of trimming. If *n* is the number of unmasked values before trimming, the number of values after trimming is $(1 - \text{proportiontocut}) * n$. Default is 0.2.
tail [{'left','right'}, optional] If 'left' the *proportiontocut* lowest values will be masked. If 'right' the *proportiontocut* highest values will be masked. Default is 'left'.
inclusive [(bool, bool) tuple], optional] Tuple indicating whether the number of data being masked on each side should be rounded (True) or truncated (False). Default is (True, True).
axis [int, optional] Axis along which to perform the trimming. If None, the input array is first flattened. Default is None.

Returns

trimtail [ndarray] Returned array of same shape as *data* with masked tail values.

scipy.stats.mstats.trimboth

`scipy.stats.mstats.trimboth` (*data*, *proportiontocut*=0.2, *inclusive*=True, *True*, *axis*=None)
 Trims the smallest and largest data values.

Trims the *data* by masking the $\text{int}(\text{proportiontocut} * n)$ smallest and $\text{int}(\text{proportiontocut} * n)$ largest values of data along the given axis, where *n* is the number of unmasked values before trimming.

Parameters

data [ndarray] Data to trim.
proportiontocut [float, optional] Percentage of trimming (as a float between 0 and 1). If *n* is the number of unmasked values before trimming, the number of values after trimming is $(1 - 2 * \text{proportiontocut}) * n$. Default is 0.2.
inclusive [(bool, bool) tuple], optional] Tuple indicating whether the number of data being masked on each side should be rounded (True) or truncated (False).
axis [int, optional] Axis along which to perform the trimming. If None, the input array is first flattened.

scipy.stats.mstats.winsorize

`scipy.stats.mstats.winsorize` (*a*, *limits=None*, *inclusive=True*, *True*, *inplace=False*, *axis=None*, *nan_policy='propagate'*)

Returns a Winsorized version of the input array.

The (`limits[0]`)th lowest values are set to the (`limits[0]`)th percentile, and the (`limits[1]`)th highest values are set to the $(1 - \text{limits}[1])$ th percentile. Masked values are skipped.

Parameters

- a** [sequence] Input array.
- limits** [{None, tuple of float}, optional] Tuple of the percentages to cut on each side of the array, with respect to the number of unmasked data, as floats between 0. and 1. Noting *n* the number of unmasked data before trimming, the $(n * \text{limits}[0])$ th smallest data and the $(n * \text{limits}[1])$ th largest data are masked, and the total number of unmasked data after trimming is $n * (1 - \text{sum}(\text{limits}))$. The value of one limit can be set to None to indicate an open interval.
- inclusive** [{(True, True) tuple}, optional] Tuple indicating whether the number of data being masked on each side should be truncated (True) or rounded (False).
- inplace** [{False, True}, optional] Whether to winsorize in place (True) or to use a copy (False)
- axis** [{None, int}, optional] Axis along which to trim. If None, the whole array is trimmed, but its shape is maintained.
- nan_policy** [{'propagate', 'raise', 'omit'}, optional] Defines how to handle when input contains nan. The following options are available (default is 'propagate'):
 - 'propagate': allows nan values and may overwrite or propagate them
 - 'raise': throws an error
 - 'omit': performs the calculations ignoring nan values

Notes

This function is applied to reduce the effect of possibly spurious outliers by limiting the extreme values.

Examples

```
>>> from scipy.stats.mstats import winsorize
```

A shuffled array contains integers from 1 to 10.

```
>>> a = np.array([10, 4, 9, 8, 5, 3, 7, 2, 1, 6])
```

The 10% of the lowest value (i.e., 1) and the 20% of the highest values (i.e., 9 and 10) are replaced.

```
>>> winsorize(a, limits=[0.1, 0.2])
masked_array(data=[8, 4, 8, 8, 5, 3, 7, 2, 2, 6],
              mask=False,
              fill_value=999999)
```

scipy.stats.mstats.zmap

`scipy.stats.mstats.zmap(scores, compare, axis=0, ddof=0)`

Calculate the relative z-scores.

Return an array of z-scores, i.e., scores that are standardized to zero mean and unit variance, where mean and variance are calculated from the comparison array.

Parameters

- scores** [array_like] The input for which z-scores are calculated.
- compare** [array_like] The input from which the mean and standard deviation of the normalization are taken; assumed to have the same dimension as *scores*.
- axis** [int or None, optional] Axis over which mean and variance of *compare* are calculated. Default is 0. If None, compute over the whole array *scores*.
- ddof** [int, optional] Degrees of freedom correction in the calculation of the standard deviation. Default is 0.

Returns

- zscore** [array_like] Z-scores, in the same shape as *scores*.

Notes

This function preserves ndarray subclasses, and works also with matrices and masked arrays (it uses *asanyarray* instead of *asarray* for parameters).

Examples

```
>>> from scipy.stats import zmap
>>> a = [0.5, 2.0, 2.5, 3]
>>> b = [0, 1, 2, 3, 4]
>>> zmap(a, b)
array([-1.06066017,  0.          ,  0.35355339,  0.70710678])
```

scipy.stats.mstats.zscore

`scipy.stats.mstats.zscore(a, axis=0, ddof=0, nan_policy='propagate')`

Compute the z score.

Compute the z score of each value in the sample, relative to the sample mean and standard deviation.

Parameters

- a** [array_like] An array like object containing the sample data.
- axis** [int or None, optional] Axis along which to operate. Default is 0. If None, compute over the whole array *a*.
- ddof** [int, optional] Degrees of freedom correction in the calculation of the standard deviation. Default is 0.
- nan_policy** [{‘propagate’, ‘raise’, ‘omit’}, optional] Defines how to handle when input contains nan. ‘propagate’ returns nan, ‘raise’ throws an error, ‘omit’ performs the calculations ignoring nan values. Default is ‘propagate’. Note that when the value is ‘omit’, nans in the input also propagate to the output, but they do not affect the z-scores computed for the non-nan values.

Returns

zscore [array_like] The z-scores, standardized by mean and standard deviation of input array *a*.

Notes

This function preserves ndarray subclasses, and works also with matrices and masked arrays (it uses *asanyarray* instead of *asarray* for parameters).

Examples

```
>>> a = np.array([ 0.7972,  0.0767,  0.4383,  0.7866,  0.8091,
...              0.1954,  0.6307,  0.6599,  0.1065,  0.0508])
>>> from scipy import stats
>>> stats.zscore(a)
array([ 1.1273, -1.247 , -0.0552,  1.0923,  1.1664, -0.8559,  0.5786,
        0.6748, -1.1488, -1.3324])
```

Computing along a specified axis, using n-1 degrees of freedom (ddof=1) to calculate the standard deviation:

```
>>> b = np.array([[ 0.3148,  0.0478,  0.6243,  0.4608],
...              [ 0.7149,  0.0775,  0.6072,  0.9656],
...              [ 0.6341,  0.1403,  0.9759,  0.4064],
...              [ 0.5918,  0.6948,  0.904 ,  0.3721],
...              [ 0.0921,  0.2481,  0.1188,  0.1366]])
>>> stats.zscore(b, axis=1, ddof=1)
array([[ -0.19264823, -1.28415119,  1.07259584,  0.40420358],
       [  0.33048416, -1.37380874,  0.04251374,  1.00081084],
       [  0.26796377, -1.12598418,  1.23283094, -0.37481053],
       [ -0.22095197,  0.24468594,  1.19042819, -1.21416216],
       [ -0.82780366,  1.4457416 , -0.43867764, -0.1792603 ]])
```

An example with *nan_policy='omit'*:

```
>>> x = np.array([[25.11, 30.10, np.nan, 32.02, 43.15],
...              [14.95, 16.06, 121.25, 94.35, 29.81]])
>>> stats.zscore(x, axis=1, nan_policy='omit')
array([[ -1.13490897, -0.37830299,          nan, -0.08718406,  1.60039602],
       [ -0.91611681, -0.89090508,  1.4983032 ,  0.88731639, -0.5785977 ]])
```

Other

<code>argstoarray(*args)</code>	Constructs a 2D array from a group of sequences.
<code>count_tied_groups(x[, use_missing])</code>	Counts the number of tied values.
<code>msign(x)</code>	Returns the sign of x, or 0 if x is masked.
<code>compare_medians_ms(group_1, group_2[, axis])</code>	Compares the medians from two independent groups along the given axis.
<code>median_cihs(data[, alpha, axis])</code>	Computes the alpha-level confidence interval for the median of the data.
<code>mjci(data[, prob, axis])</code>	Returns the Maritz-Jarrett estimators of the standard error of selected experimental quantiles of the data.

continues on next page

Table 278 – continued from previous page

<code>mquantiles_cimj(data[, prob, alpha, axis])</code>	Computes the alpha confidence interval for the selected quantiles of the data, with Maritz-Jarrett estimators.
<code>rsh(data[, points])</code>	Evaluates Rosenblatt's shifted histogram estimators for each data point.

scipy.stats.mstats.argstoarray

`scipy.stats.mstats.argstoarray(*args)`

Constructs a 2D array from a group of sequences.

Sequences are filled with missing values to match the length of the longest sequence.

Parameters

args [sequences] Group of sequences.

Returns

argstoarray

[MaskedArray] A ($m \times n$) masked array, where m is the number of arguments and n the length of the longest argument.

Notes

`numpy.ma.row_stack` has identical behavior, but is called with a sequence of sequences.

Examples

A 2D masked array constructed from a group of sequences is returned.

```
>>> from scipy.stats.mstats import argstoarray
>>> argstoarray([1, 2, 3], [4, 5, 6])
masked_array(
  data=[[1.0, 2.0, 3.0],
        [4.0, 5.0, 6.0]],
  mask=[[False, False, False],
        [False, False, False]],
  fill_value=1e+20)
```

The returned masked array filled with missing values when the lengths of sequences are different.

```
>>> argstoarray([1, 3], [4, 5, 6])
masked_array(
  data=[[1.0, 3.0, --],
        [4.0, 5.0, 6.0]],
  mask=[[False, False, True],
        [False, False, False]],
  fill_value=1e+20)
```

scipy.stats.mstats.count_tied_groups

`scipy.stats.mstats.count_tied_groups(x, use_missing=False)`

Counts the number of tied values.

Parameters

- x** [sequence] Sequence of data on which to counts the ties
- use_missing** [bool, optional] Whether to consider missing values as tied.

Returns

- count_tied_groups** [dict] Returns a dictionary (nb of ties: nb of groups).

Examples

```
>>> from scipy.stats import mstats
>>> z = [0, 0, 0, 2, 2, 2, 3, 3, 4, 5, 6]
>>> mstats.count_tied_groups(z)
{2: 1, 3: 2}
```

In the above example, the ties were 0 (3x), 2 (3x) and 3 (2x).

```
>>> z = np.ma.array([0, 0, 1, 2, 2, 2, 3, 3, 4, 5, 6])
>>> mstats.count_tied_groups(z)
{2: 2, 3: 1}
>>> z[[1,-1]] = np.ma.masked
>>> mstats.count_tied_groups(z, use_missing=True)
{2: 2, 3: 1}
```

scipy.stats.mstats.msign

`scipy.stats.mstats.msign(x)`

Returns the sign of *x*, or 0 if *x* is masked.

scipy.stats.mstats.compare_medians_ms

`scipy.stats.mstats.compare_medians_ms(group_1, group_2, axis=None)`

Compares the medians from two independent groups along the given axis.

The comparison is performed using the McKean-Schrader estimate of the standard error of the medians.

Parameters

- group_1** [array_like] First dataset. Has to be of size ≥ 7 .
- group_2** [array_like] Second dataset. Has to be of size ≥ 7 .
- axis** [int, optional] Axis along which the medians are estimated. If *None*, the arrays are flattened. If *axis* is not *None*, then *group_1* and *group_2* should have the same shape.

Returns

compare_medians_ms

[{float, ndarray}] If *axis* is None, then returns a float, otherwise returns a 1-D ndarray of floats with a length equal to the length of *group_1* along *axis*.

scipy.stats.mstats.median_cihs

`scipy.stats.mstats.median_cihs` (*data*, *alpha*=0.05, *axis*=None)

Computes the alpha-level confidence interval for the median of the data.

Uses the Hettmasperger-Sheather method.

Parameters

data [array_like] Input data. Masked values are discarded. The input should be 1D only, or *axis* should be set to None.
alpha [float, optional] Confidence level of the intervals.
axis [int or None, optional] Axis along which to compute the quantiles. If None, use a flattened array.

Returns

median_cihs
 Alpha level confidence interval.

scipy.stats.mstats.mjci

`scipy.stats.mstats.mjci` (*data*, *prob*=[0.25, 0.5, 0.75], *axis*=None)

Returns the Maritz-Jarrett estimators of the standard error of selected experimental quantiles of the data.

Parameters

data [ndarray] Data array.
prob [sequence, optional] Sequence of quantiles to compute.
axis [int or None, optional] Axis along which to compute the quantiles. If None, use a flattened array.

scipy.stats.mstats.mquantiles_cimj

`scipy.stats.mstats.mquantiles_cimj` (*data*, *prob*=[0.25, 0.5, 0.75], *alpha*=0.05, *axis*=None)

Computes the alpha confidence interval for the selected quantiles of the data, with Maritz-Jarrett estimators.

Parameters

data [ndarray] Data array.
prob [sequence, optional] Sequence of quantiles to compute.
alpha [float, optional] Confidence level of the intervals.
axis [int or None, optional] Axis along which to compute the quantiles. If None, use a flattened array.

Returns

ci_lower [ndarray] The lower boundaries of the confidence interval. Of the same length as *prob*.
ci_upper [ndarray] The upper boundaries of the confidence interval. Of the same length as *prob*.

scipy.stats.mstats.rsh

`scipy.stats.mstats.rsh` (*data*, *points=None*)

Evaluates Rosenblatt's shifted histogram estimators for each data point.

Rosenblatt's estimator is a centered finite-difference approximation to the derivative of the empirical cumulative distribution function.

Parameters

data [sequence] Input data, should be 1-D. Masked values are ignored.
points [sequence or None, optional] Sequence of points where to evaluate Rosenblatt shifted histogram. If None, use the data.

6.29.18 Univariate and multivariate kernel density estimation

<code>gaussian_kde</code> (<i>dataset</i> [, <i>bw_method</i> , <i>weights</i>])	Representation of a kernel-density estimate using Gaussian kernels.
--	---

scipy.stats.gaussian_kde

class `scipy.stats.gaussian_kde` (*dataset*, *bw_method=None*, *weights=None*)

Representation of a kernel-density estimate using Gaussian kernels.

Kernel density estimation is a way to estimate the probability density function (PDF) of a random variable in a non-parametric way. `gaussian_kde` works for both uni-variate and multi-variate data. It includes automatic bandwidth determination. The estimation works best for a unimodal distribution; bimodal or multi-modal distributions tend to be oversmoothed.

Parameters

dataset [array_like] Datapoints to estimate from. In case of univariate data this is a 1-D array, otherwise a 2-D array with shape (# of dims, # of data).
bw_method [str, scalar or callable, optional] The method used to calculate the estimator bandwidth. This can be 'scott', 'silverman', a scalar constant or a callable. If a scalar, this will be used directly as *kde.factor*. If a callable, it should take a `gaussian_kde` instance as only parameter and return a scalar. If None (default), 'scott' is used. See Notes for more details.
weights [array_like, optional] weights of datapoints. This must be the same shape as dataset. If None (default), the samples are assumed to be equally weighted

Notes

Bandwidth selection strongly influences the estimate obtained from the KDE (much more so than the actual shape of the kernel). Bandwidth selection can be done by a "rule of thumb", by cross-validation, by "plug-in methods" or by other means; see [3], [4] for reviews. `gaussian_kde` uses a rule of thumb, the default is Scott's Rule.

Scott's Rule [1], implemented as `scotts_factor`, is:

$$n^{**(-1./(d+4))},$$

with *n* the number of data points and *d* the number of dimensions. In the case of unequally weighted points, `scotts_factor` becomes:

```
neff**(-1./(d+4)),
```

with `neff` the effective number of datapoints. Silverman's Rule [2], implemented as `silverman_factor`, is:

```
(n * (d + 2) / 4.)**(-1. / (d + 4)).
```

or in the case of unequally weighted points:

```
(neff * (d + 2) / 4.)**(-1. / (d + 4)).
```

Good general descriptions of kernel density estimation can be found in [1] and [2], the mathematics for this multi-dimensional implementation can be found in [1].

With a set of weighted samples, the effective number of datapoints `neff` is defined by:

```
neff = sum(weights)^2 / sum(weights^2)
```

as detailed in [5].

References

[1], [2], [3], [4], [5]

Examples

Generate some random two-dimensional data:

```
>>> from scipy import stats
>>> def measure(n):
...     "Measurement model, return two coupled measurements."
...     m1 = np.random.normal(size=n)
...     m2 = np.random.normal(scale=0.5, size=n)
...     return m1+m2, m1-m2
```

```
>>> m1, m2 = measure(2000)
>>> xmin = m1.min()
>>> xmax = m1.max()
>>> ymin = m2.min()
>>> ymax = m2.max()
```

Perform a kernel density estimate on the data:

```
>>> X, Y = np.mgrid[xmin:xmax:100j, ymin:ymax:100j]
>>> positions = np.vstack([X.ravel(), Y.ravel()])
>>> values = np.vstack([m1, m2])
>>> kernel = stats.gaussian_kde(values)
>>> Z = np.reshape(kernel(positions).T, X.shape)
```

Plot the results:

```
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots()
```


(continues on next page)

(continued from previous page)

```

>>> ax.imshow(np.rot90(Z), cmap=plt.cm.gist_earth_r,
...           extent=[xmin, xmax, ymin, ymax])
>>> ax.plot(m1, m2, 'k.', markersize=2)
>>> ax.set_xlim([xmin, xmax])
>>> ax.set_ylim([ymin, ymax])
>>> plt.show()

```



Attributes

dataset	[ndarray] The dataset with which <i>gaussian_kde</i> was initialized.
d	[int] Number of dimensions.
n	[int] Number of datapoints.
neff	[int] Effective number of datapoints. New in version 1.2.0.
factor	[float] The bandwidth factor, obtained from <i>kde.covariance_factor</i> , with which the covariance matrix is multiplied.
covariance	[ndarray] The covariance matrix of <i>dataset</i> , scaled by the calculated bandwidth (<i>kde.factor</i>).
inv_cov	[ndarray] The inverse of <i>covariance</i> .

Methods

<i>evaluate</i> (self, points)	Evaluate the estimated pdf on a set of points.
<i>__call__</i> (self, points)	Evaluate the estimated pdf on a set of points.
<i>integrate_gaussian</i> (self, mean, cov)	Multiply estimated density by a multivariate Gaussian and integrate over the whole space.
<i>integrate_box_1d</i> (self, low, high)	Computes the integral of a 1D pdf between two bounds.
<i>integrate_box</i> (self, low_bounds, high_bounds)	Computes the integral of a pdf over a rectangular interval.
<i>integrate_kde</i> (self, other)	Computes the integral of the product of this kernel density estimate with another.

continues on next page

Table 280 – continued from previous page

<code>pdf(self, x)</code>	Evaluate the estimated pdf on a provided set of points.
<code>logpdf(self, x)</code>	Evaluate the log of the estimated pdf on a provided set of points.
<code>resample(self[, size, seed])</code>	Randomly sample a dataset from the estimated pdf.
<code>set_bandwidth(self[, bw_method])</code>	Compute the estimator bandwidth with given method.
<code>covariance_factor(self)</code>	Computes the coefficient (<i>kde.factor</i>) that multiplies the data covariance matrix to obtain the kernel covariance matrix.

scipy.stats.gaussian_kde.evaluate

`gaussian_kde.evaluate(self, points)`

Evaluate the estimated pdf on a set of points.

Parameters

points [(# of dimensions, # of points)-array] Alternatively, a (# of dimensions,) vector can be passed in and treated as a single point.

Returns

values [(# of points,)-array] The values at each point.

Raises

ValueError

[if the dimensionality of the input points is different than] the dimensionality of the KDE.

scipy.stats.gaussian_kde.__call__

`gaussian_kde.__call__(self, points)`

Evaluate the estimated pdf on a set of points.

Parameters

points [(# of dimensions, # of points)-array] Alternatively, a (# of dimensions,) vector can be passed in and treated as a single point.

Returns

values [(# of points,)-array] The values at each point.

Raises

ValueError

[if the dimensionality of the input points is different than] the dimensionality of the KDE.

scipy.stats.gaussian_kde.integrate_gaussian

`gaussian_kde.integrate_gaussian(self, mean, cov)`

Multiply estimated density by a multivariate Gaussian and integrate over the whole space.

Parameters

mean [array_like] A 1-D array, specifying the mean of the Gaussian.
cov [array_like] A 2-D array, specifying the covariance matrix of the Gaussian.

Returns

result [scalar] The value of the integral.

Raises**ValueError**

If the mean or covariance of the input Gaussian differs from the KDE's dimensionality.

scipy.stats.gaussian_kde.integrate_box_1d

`gaussian_kde.integrate_box_1d` (*self*, *low*, *high*)

Computes the integral of a 1D pdf between two bounds.

Parameters

low [scalar] Lower bound of integration.

high [scalar] Upper bound of integration.

Returns

value [scalar] The result of the integral.

Raises**ValueError**

If the KDE is over more than one dimension.

scipy.stats.gaussian_kde.integrate_box

`gaussian_kde.integrate_box` (*self*, *low_bounds*, *high_bounds*, *maxpts=None*)

Computes the integral of a pdf over a rectangular interval.

Parameters

low_bounds [array_like] A 1-D array containing the lower bounds of integration.

high_bounds [array_like] A 1-D array containing the upper bounds of integration.

maxpts [int, optional] The maximum number of points to use for integration.

Returns

value [scalar] The result of the integral.

scipy.stats.gaussian_kde.integrate_kde

`gaussian_kde.integrate_kde` (*self*, *other*)

Computes the integral of the product of this kernel density estimate with another.

Parameters

other [gaussian_kde instance] The other kde.

Returns

value [scalar] The result of the integral.

Raises**ValueError**

If the KDEs have different dimensionality.

scipy.stats.gaussian_kde.pdf`gaussian_kde.pdf` (*self*, *x*)

Evaluate the estimated pdf on a provided set of points.

Notes

This is an alias for `gaussian_kde.evaluate`. See the `evaluate` docstring for more details.

scipy.stats.gaussian_kde.logpdf`gaussian_kde.logpdf` (*self*, *x*)

Evaluate the log of the estimated pdf on a provided set of points.

scipy.stats.gaussian_kde.resample`gaussian_kde.resample` (*self*, *size=None*, *seed=None*)

Randomly sample a dataset from the estimated pdf.

Parameters

- size** [int, optional] The number of samples to draw. If not provided, then the size is the same as the effective number of samples in the underlying dataset.
- seed** [{None, int, *RandomState*, *Generator*}, optional] This parameter defines the object to use for drawing random variates. If *seed* is *None* the *RandomState* singleton is used. If *seed* is an int, a new *RandomState* instance is used, seeded with *seed*. If *seed* is already a *RandomState* or *Generator* instance, then that object is used. Default is *None*. Specify *seed* for reproducible drawing of random variates.

Returns

- resample** [(*self.d*, *size*) ndarray] The sampled dataset.

scipy.stats.gaussian_kde.set_bandwidth`gaussian_kde.set_bandwidth` (*self*, *bw_method=None*)

Compute the estimator bandwidth with given method.

The new bandwidth calculated after a call to `set_bandwidth` is used for subsequent evaluations of the estimated density.

Parameters

- bw_method** [str, scalar or callable, optional] The method used to calculate the estimator bandwidth. This can be 'scott', 'silverman', a scalar constant or a callable. If a scalar, this will be used directly as *kde.factor*. If a callable, it should take a `gaussian_kde` instance as only parameter and return a scalar. If *None* (default), nothing happens; the current *kde.covariance_factor* method is kept.


Notes

New in version 0.11.

Examples

```
>>> import scipy.stats as stats
>>> x1 = np.array([-7, -5, 1, 4, 5.])
>>> kde = stats.gaussian_kde(x1)
>>> xs = np.linspace(-10, 10, num=50)
>>> y1 = kde(xs)
>>> kde.set_bandwidth(bw_method='silverman')
>>> y2 = kde(xs)
>>> kde.set_bandwidth(bw_method=kde.factor / 3.)
>>> y3 = kde(xs)
```

```
>>> import matplotlib.pyplot as plt
>>> fig, ax = plt.subplots()
>>> ax.plot(x1, np.full(x1.shape, 1 / (4. * x1.size)), 'bo',
...        label='Data points (rescaled)')
>>> ax.plot(xs, y1, label='Scott (default)')
>>> ax.plot(xs, y2, label='Silverman')
>>> ax.plot(xs, y3, label='Const (1/3 * Silverman)')
>>> ax.legend()
>>> plt.show()
```



scipy.stats.gaussian_kde.covariance_factor

`gaussian_kde.covariance_factor` (*self*)

Computes the coefficient (*kde.factor*) that multiplies the data covariance matrix to obtain the kernel covariance matrix. The default is `scotts_factor`. A subclass can overwrite this method to provide a different method, or set it through a call to `kde.set_bandwidth`.

6.29.19 Warnings used in `scipy.stats`

<code>F_onewayConstantInputWarning</code> ([msg])	Warning generated by <code>f_oneway</code> when an input is constant, e.g.
<code>F_onewayBadInputSizesWarning</code>	Warning generated by <code>f_oneway</code> when an input has length 0, or if all the inputs have length 1.
<code>PearsonRConstantInputWarning</code> ([msg])	Warning generated by <code>pearsonr</code> when an input is constant.
<code>PearsonRNearConstantInputWarning</code> ([msg])	Warning generated by <code>pearsonr</code> when an input is nearly constant.
<code>SpearmanRConstantInputWarning</code> ([msg])	Warning generated by <code>spearmanr</code> when an input is constant.

scipy.stats.F_onewayConstantInputWarning

exception `scipy.stats.F_onewayConstantInputWarning` (*msg=None*)

Warning generated by `f_oneway` when an input is constant, e.g. each of the samples provided is a constant array.

with_traceback ()

Exception.with_traceback(tb) – set `self.__traceback__` to `tb` and return `self`.

scipy.stats.F_onewayBadInputSizesWarning

exception `scipy.stats.F_onewayBadInputSizesWarning`

Warning generated by `f_oneway` when an input has length 0, or if all the inputs have length 1.

with_traceback ()

Exception.with_traceback(tb) – set `self.__traceback__` to `tb` and return `self`.

scipy.stats.PearsonRConstantInputWarning

exception `scipy.stats.PearsonRConstantInputWarning` (*msg=None*)

Warning generated by `pearsonr` when an input is constant.

with_traceback ()

Exception.with_traceback(tb) – set `self.__traceback__` to `tb` and return `self`.

scipy.stats.PearsonRNearConstantInputWarning

exception `scipy.stats.PearsonRNearConstantInputWarning` (*msg=None*)
Warning generated by `pearsonr` when an input is nearly constant.

with_traceback ()
Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

scipy.stats.SpearmanRConstantInputWarning

exception `scipy.stats.SpearmanRConstantInputWarning` (*msg=None*)
Warning generated by `spearmanr` when an input is constant.

with_traceback ()
Exception.with_traceback(tb) – set self.__traceback__ to tb and return self.

For many more stat related functions install the software R and the interface package rpy.

6.30 Low-level callback functions

Some functions in SciPy take as arguments callback functions, which can either be python callables or low-level compiled functions. Using compiled callback functions can improve performance somewhat by avoiding wrapping data in Python objects.

Such low-level functions in SciPy are wrapped in `LowLevelCallable` objects, which can be constructed from function pointers obtained from ctypes, cffi, Cython, or contained in Python `PyCapsule` objects.

<code>LowLevelCallable</code> (function[, user_data, ...])	Low-level callback function.
--	------------------------------

6.30.1 scipy.LowLevelCallable

class `scipy.LowLevelCallable` (*function, user_data=None, signature=None*)
Low-level callback function.

Parameters

function [[PyCapsule, ctypes function pointer, cffi function pointer]] Low-level callback function.
user_data [[PyCapsule, ctypes void pointer, cffi void pointer]] User data to pass on to the callback function.
signature [str, optional] Signature of the function. If omitted, determined from *function*, if possible.

Notes

The argument `function` can be one of:

- PyCapsule, whose name contains the C function signature
- ctypes function pointer
- cffi function pointer

The signature of the low-level callback must match one of those expected by the routine it is passed to.

If constructing low-level functions from a PyCapsule, the name of the capsule must be the corresponding signature, in the format:

```
return_type (arg1_type, arg2_type, ...)
```

For example:

```
"void (double)"
"double (double, int *, void *)"
```

The context of a PyCapsule passed in as `function` is used as `user_data`, if an explicit value for `user_data` was not given.

Attributes

function Callback function given.
user_data User data given.
signature Signature of the function.

Methods

<code>from_cython</code> (<code>module</code> , <code>name</code> [, <code>user_data</code> , <code>signature</code>])	Create a low-level callback function from an exported Cython function.
--	--

scipy.LowLevelCallable.from_cython

classmethod `LowLevelCallable.from_cython`(`module`, `name`, `user_data=None`, `signature=None`)
 Create a low-level callback function from an exported Cython function.

Parameters

module [module] Cython module where the exported function resides
name [str] Name of the exported function
user_data [{}PyCapsule, ctypes void pointer, cffi void pointer], optional] User data to pass on to the callback function.
signature [str, optional] Signature of the function. If omitted, determined from *function*.

See also:

Functions accepting low-level callables:

`scipy.integrate.quad`, `scipy.ndimage.generic_filter`, `scipy.ndimage.generic_filter1d`, `scipy.ndimage.geometric_transform`

Usage examples:

Extending scipy.ndimage in C, Faster integration using low-level callback functions

BIBLIOGRAPHY

- [WPR] https://en.wikipedia.org/wiki/Romberg's_method
- [MOL] https://en.wikipedia.org/wiki/Method_of_lines
- [TRLIB] F. Lenders, C. Kirches, A. Potschka: “trlib: A vector-free implementation of the GLTR method for iterative solution of the trust region problem”, [arXiv:1611.04718](https://arxiv.org/abs/1611.04718)
- [GLTR] N. Gould, S. Lucidi, M. Roma, P. Toint: “Solving the Trust-Region Subproblem using the Lanczos Method”, *SIAM J. Optim.*, 9(2), 504–525, (1999). DOI:10.1137/S1052623497322735
- [NW] J. Nocedal, S.J. Wright “Numerical optimization.” 2nd edition. Springer Science (2006).
- [CGT] Conn, A. R., Gould, N. I., & Toint, P. L. “Trust region methods”. Siam. (2000). pp. 169-200.
- [TRIP] Byrd, Richard H., Mary E. Hribar, and Jorge Nocedal. 1999. An interior point algorithm for large-scale nonlinear programming. *SIAM Journal on Optimization* 9.4: 877-900.
- [EQSQP] Lalee, Marucha, Jorge Nocedal, and Todd Plantega. 1998. On the implementation of an algorithm for large-scale equality constrained optimization. *SIAM Journal on Optimization* 8.3: 682-706.
- [KK] D.A. Knoll and D.E. Keyes, “Jacobian-free Newton-Krylov methods”, *J. Comp. Phys.* 193, 357 (2004). DOI:10.1016/j.jcp.2003.08.010
- [PP] PETSc <https://www.mcs.anl.gov/petsc/> and its Python bindings <https://bitbucket.org/petsc/petsc4py/>
- [AMG] PyAMG (algebraic multigrid preconditioners/solvers) <https://github.com/pyamg/pyamg/issues>
- [CT65] Cooley, James W., and John W. Tukey, 1965, “An algorithm for the machine calculation of complex Fourier series,” *Math. Comput.* 19: 297-301.
- [NR07] Press, W., Teukolsky, S., Vetterline, W.T., and Flannery, B.P., 2007, *Numerical Recipes: The Art of Scientific Computing*, ch. 12-13. Cambridge Univ. Press, Cambridge, UK.
- [Mak] J. Makhoul, 1980, ‘A Fast Cosine Transform in One and Two Dimensions’, *IEEE Transactions on acoustics, speech and signal processing* vol. 28(1), pp. 27-34, DOI:10.1109/TASSP.1980.1163351
- [WPW] https://en.wikipedia.org/wiki/Window_function
- [WPC] https://en.wikipedia.org/wiki/Discrete_cosine_transform
- [WPS] https://en.wikipedia.org/wiki/Discrete_sine_transform
- [JKB] Johnson, Kotz, and Balakrishnan, “Continuous Univariate Distributions, Volume 1”, Second Edition, John Wiley and Sons, p. 173 (1994).
- [1] D. Arthur and S. Vassilvskii, “k-means++: the advantages of careful seeding”, Proceedings of the Eighteenth Annual ACM-SIAM Symposium on Discrete Algorithms, 2007.
- [1] Daniel Mullner, “Modern hierarchical, agglomerative clustering algorithms”, [arXiv:1109.2378v1](https://arxiv.org/abs/1109.2378v1).

- [2] Ziv Bar-Joseph, David K. Gifford, Tommi S. Jaakkola, “Fast optimal leaf ordering for hierarchical clustering”, 2001. *Bioinformatics* DOI:10.1093/bioinformatics/17.suppl_1.S22
- [1] https://en.wikipedia.org/wiki/Disjoint-set_data_structure
- [CODATA2018] CODATA Recommended Values of the Fundamental Physical Constants 2018.
<https://physics.nist.gov/cuu/Constants/>
- [1] Cooley, James W., and John W. Tukey, 1965, “An algorithm for the machine calculation of complex Fourier series,” *Math. Comput.* 19: 297-301.
- [2] Bluestein, L., 1970, “A linear filtering approach to the computation of discrete Fourier transform”. *IEEE Transactions on Audio and Electroacoustics.* 18 (4): 451-455.
- [1] ‘A Fast Cosine Transform in One and Two Dimensions’, by J. Makhoul, *IEEE Transactions on acoustics, speech and signal processing* vol. 28(1), pp. 27-34, DOI:10.1109/TASSP.1980.1163351 (1980).
- [2] Wikipedia, “Discrete cosine transform”, https://en.wikipedia.org/wiki/Discrete_cosine_transform
- [1] Wikipedia, “Discrete sine transform”, https://en.wikipedia.org/wiki/Discrete_sine_transform
- [1] ‘A Fast Cosine Transform in One and Two Dimensions’, by J. Makhoul, *IEEE Transactions on acoustics, speech and signal processing* vol. 28(1), pp. 27-34, DOI:10.1109/TASSP.1980.1163351 (1980).
- [2] Wikipedia, “Discrete cosine transform”, https://en.wikipedia.org/wiki/Discrete_cosine_transform
- [1] Wikipedia, “Discrete sine transform”, https://en.wikipedia.org/wiki/Discrete_sine_transform
- [1] ‘Romberg’s method’ https://en.wikipedia.org/wiki/Romberg%27s_method
- [1] Wikipedia page: https://en.wikipedia.org/wiki/Trapezoidal_rule
- [2] Illustration image: https://en.wikipedia.org/wiki/File:Composite_trapezoidal_rule_illustration.png
- [1] J. R. Dormand, P. J. Prince, “A family of embedded Runge-Kutta formulae”, *Journal of Computational and Applied Mathematics*, Vol. 6, No. 1, pp. 19-26, 1980.
- [2] L. W. Shampine, “Some Practical Runge-Kutta Formulas”, *Mathematics of Computation*, Vol. 46, No. 173, pp. 135-150, 1986.
- [3] P. Bogacki, L.F. Shampine, “A 3(2) Pair of Runge-Kutta Formulas”, *Appl. Math. Lett.* Vol. 2, No. 4. pp. 321-325, 1989.
- [4] E. Hairer, G. Wanner, “Solving Ordinary Differential Equations II: Stiff and Differential-Algebraic Problems”, Sec. IV.8.
- [5] [Backward Differentiation Formula](#) on Wikipedia.
- [6] L. F. Shampine, M. W. Reichelt, “THE MATLAB ODE SUITE”, *SIAM J. SCI. COMPUTE.*, Vol. 18, No. 1, pp. 1-22, January 1997.
- [7] A. C. Hindmarsh, “ODEPACK, A Systematized Collection of ODE Solvers,” *IMACS Transactions on Scientific Computation*, Vol 1., pp. 55-64, 1983.
- [8] L. Petzold, “Automatic selection of methods for solving stiff and nonstiff systems of ordinary differential equations”, *SIAM Journal on Scientific and Statistical Computing*, Vol. 4, No. 1, pp. 136-148, 1983.
- [9] [Stiff equation](#) on Wikipedia.
- [10] A. Curtis, M. J. D. Powell, and J. Reid, “On the estimation of sparse Jacobian matrices”, *Journal of the Institute of Mathematics and its Applications*, 13, pp. 117-120, 1974.
- [11] [Cauchy-Riemann equations](#) on Wikipedia.
- [12] [Lotka-Volterra equations](#) on Wikipedia.

- [13] E. Hairer, S. P. Norsett G. Wanner, "Solving Ordinary Differential Equations I: Nonstiff Problems", Sec. II.
- [14] [Page with original Fortran code of DOP853.](#)
- [1] P. Bogacki, L.F. Shampine, "A 3(2) Pair of Runge-Kutta Formulas", Appl. Math. Lett. Vol. 2, No. 4. pp. 321-325, 1989.
- [1] J. R. Dormand, P. J. Prince, "A family of embedded Runge-Kutta formulae", Journal of Computational and Applied Mathematics, Vol. 6, No. 1, pp. 19-26, 1980.
- [2] L. W. Shampine, "Some Practical Runge-Kutta Formulas", Mathematics of Computation, Vol. 46, No. 173, pp. 135-150, 1986.
- [1] E. Hairer, S. P. Norsett G. Wanner, "Solving Ordinary Differential Equations I: Nonstiff Problems", Sec. II.
- [2] [Page with original Fortran code of DOP853.](#)
- [1] E. Hairer, G. Wanner, "Solving Ordinary Differential Equations II: Stiff and Differential-Algebraic Problems", Sec. IV.8.
- [2] A. Curtis, M. J. D. Powell, and J. Reid, "On the estimation of sparse Jacobian matrices", Journal of the Institute of Mathematics and its Applications, 13, pp. 117-120, 1974.
- [1] G. D. Byrne, A. C. Hindmarsh, "A Polyalgorithm for the Numerical Solution of Ordinary Differential Equations", ACM Transactions on Mathematical Software, Vol. 1, No. 1, pp. 71-96, March 1975.
- [2] L. F. Shampine, M. W. Reichelt, "THE MATLAB ODE SUITE", SIAM J. SCI. COMPUTE., Vol. 18, No. 1, pp. 1-22, January 1997.
- [3] E. Hairer, G. Wanner, "Solving Ordinary Differential Equations I: Nonstiff Problems", Sec. III.2.
- [4] A. Curtis, M. J. D. Powell, and J. Reid, "On the estimation of sparse Jacobian matrices", Journal of the Institute of Mathematics and its Applications, 13, pp. 117-120, 1974.
- [1] A. C. Hindmarsh, "ODEPACK, A Systematized Collection of ODE Solvers," IMACS Transactions on Scientific Computation, Vol 1., pp. 55-64, 1983.
- [2] L. Petzold, "Automatic selection of methods for solving stiff and nonstiff systems of ordinary differential equations", SIAM Journal on Scientific and Statistical Computing, Vol. 4, No. 1, pp. 136-148, 1983.
- [HNW93] E. Hairer, S.P. Norsett and G. Wanner, Solving Ordinary Differential Equations i. Nonstiff Problems. 2nd edition. Springer Series in Computational Mathematics, Springer-Verlag (1993)
- [1] J. Kierzenka, L. F. Shampine, "A BVP Solver Based on Residual Control and the Matlab PSE", ACM Trans. Math. Softw., Vol. 27, Number 3, pp. 299-316, 2001.
- [2] L.F. Shampine, P. H. Muir and H. Xu, "A User-Friendly Fortran BVP Solver".
- [3] U. Ascher, R. Mattheij and R. Russell "Numerical Solution of Boundary Value Problems for Ordinary Differential Equations".
- [4] [Cauchy-Riemann equations](#) on Wikipedia.
- [1] Krogh, "Efficient Algorithms for Polynomial Interpolation and Numerical Differentiation", 1970.
- [1] [Cubic Hermite spline](#) on Wikipedia.
- [1] F. N. Fritsch and R. E. Carlson, Monotone Piecewise Cubic Interpolation, SIAM J. Numer. Anal., 17(2), 238 (1980). DOI:10.1137/0717021.
- [2] see, e.g., C. Moler, Numerical Computing with Matlab, 2004. DOI:10.1137/1.9780898717952
- [1] [Cubic Spline Interpolation](#) on Wikiversity.
- [2] Carl de Boor, "A Practical Guide to Splines", Springer-Verlag, 1978.
- [1] https://en.wikipedia.org/wiki/Bernstein_polynomial

- [2] Kenneth I. Joy, Bernstein polynomials, <http://www.idav.ucdavis.edu/education/CAGDNotes/Bernstein-Polynomials.pdf>
- [3] E. H. Doha, A. H. Bhrawy, and M. A. Saker, Boundary Value Problems, vol 2011, article ID 829546, DOI:10.1155/2011/829543.
- [1] <http://www.qhull.org/>
- [1] <http://www.qhull.org/>
- [CT] See, for example, P. Alfeld, "A trivariate Clough-Tocher scheme for tetrahedral data". Computer Aided Geometric Design, 1, 169 (1984); G. Farin, "Triangular Bernstein-Bezier patches". Computer Aided Geometric Design, 3, 83 (1986).
- [Nielson83] G. Nielson, "A method for interpolating scattered data based upon a minimum norm network". Math. Comp., 40, 253 (1983).
- [Renka84] R. J. Renka and A. K. Cline. "A Triangle-based C1 interpolation method.", Rocky Mountain J. Math., 14, 223 (1984).
- [1] Python package *regulargrid* by Johannes Buchner, see <https://pypi.python.org/pypi/regulargrid/>
- [2] Wikipedia, "Trilinear interpolation", https://en.wikipedia.org/wiki/Trilinear_interpolation
- [3] Weiser, Alan, and Sergio E. Zarantonello. "A note on piecewise linear and multilinear table interpolation in many dimensions." MATH. COMPUT. 50.181 (1988): 189-196. <https://www.ams.org/journals/mcom/1988-50-181/S0025-5718-1988-0917826-0/S0025-5718-1988-0917826-0.pdf>
- [1] Tom Lyche and Knut Morken, Spline methods, <http://www.uio.no/studier/emner/matnat/ifi/INF-MAT5340/v05/undervisningsmateriale/>
- [2] Carl de Boor, A practical guide to splines, Springer, 2001.
- [1] P. Dierckx, "An algorithm for smoothing, differentiation and integration of experimental data using spline functions", J.Comp.Appl.Maths 1 (1975) 165-184.
- [2] P. Dierckx, "A fast algorithm for smoothing data on a rectangular grid while using spline functions", SIAM J.Numer.Anal. 19 (1982) 1286-1304.
- [3] P. Dierckx, "An improved algorithm for curve fitting with spline functions", report tw54, Dept. Computer Science, K.U. Leuven, 1981.
- [4] P. Dierckx, "Curve and surface fitting with splines", Monographs on Numerical Analysis, Oxford University Press, 1993.
- [1] P. Dierckx, "Algorithms for smoothing data with periodic and parametric splines, Computer Graphics and Image Processing", 20 (1982) 171-184.
- [2] P. Dierckx, "Algorithms for smoothing data with periodic and parametric splines", report tw55, Dept. Computer Science, K.U.Leuven, 1981.
- [3] P. Dierckx, "Curve and surface fitting with splines", Monographs on Numerical Analysis, Oxford University Press, 1993.
- [1] C. de Boor, "On calculating with b-splines", J. Approximation Theory, 6, p.50-62, 1972.
- [2] M. G. Cox, "The numerical evaluation of b-splines", J. Inst. Maths Appics, 10, p.134-149, 1972.
- [3] P. Dierckx, "Curve and surface fitting with splines", Monographs on Numerical Analysis, Oxford University Press, 1993.
- [1] P.W. Gaffney, The calculation of indefinite integrals of b-splines", J. Inst. Maths Appics, 17, p.37-41, 1976.
- [2] P. Dierckx, "Curve and surface fitting with splines", Monographs on Numerical Analysis, Oxford University Press, 1993.

- [1] C. de Boor, “On calculating with b-splines”, J. Approximation Theory, 6, p.50-62, 1972.
- [2] M. G. Cox, “The numerical evaluation of b-splines”, J. Inst. Maths Applics, 10, p.134-149, 1972.
- [3] P. Dierckx, “Curve and surface fitting with splines”, Monographs on Numerical Analysis, Oxford University Press, 1993.
- [1] C. de Boor: On calculating with b-splines, J. Approximation Theory 6 (1972) 50-62.
- [2] M. G. Cox : The numerical evaluation of b-splines, J. Inst. Maths applics 10 (1972) 134-149.
- [3] P. Dierckx : Curve and surface fitting with splines, Monographs on Numerical Analysis, Oxford University Press, 1993.
- [1] W. Boehm, “Inserting new knots into b-spline curves.”, Computer Aided Design, 12, p.199-201, 1980.
- [2] P. Dierckx, “Curve and surface fitting with splines, Monographs on Numerical Analysis”, Oxford University Press, 1993.
- [1] Dierckx P.:An algorithm for surface fitting with spline functions Ima J. Numer. Anal. 1 (1981) 267-283.
- [2] Dierckx P.:An algorithm for surface fitting with spline functions report tw50, Dept. Computer Science,K.U.Leuven, 1980.
- [3] Dierckx P.:Curve and surface fitting with splines, Monographs on Numerical Analysis, Oxford University Press, 1993.
- [1] Dierckx P. : An algorithm for surface fitting with spline functions Ima J. Numer. Anal. 1 (1981) 267-283.
- [2] Dierckx P. : An algorithm for surface fitting with spline functions report tw50, Dept. Computer Science,K.U.Leuven, 1980.
- [3] Dierckx P. : Curve and surface fitting with splines, Monographs on Numerical Analysis, Oxford University Press, 1993.
- [1] IBM Corporation and Microsoft Corporation, “Multimedia Programming Interface and Data Specifications 1.0”, section “Data Format of the Samples”, August 1991 http://www.tactilemedia.com/info/MCI_Control_Info.html
- [2] Adobe Systems Incorporated, “Adobe Audition 3 User Guide”, section “Audio file formats: 24-bit Packed Int (type 1, 20-bit)”, 2007
- [1] IBM Corporation and Microsoft Corporation, “Multimedia Programming Interface and Data Specifications 1.0”, section “Data Format of the Samples”, August 1991 http://www.tactilemedia.com/info/MCI_Control_Info.html
- [1] Jacob R Gardner, Geoff Pleiss, David Bindel, Kilian Q Weinberger, Andrew Gordon Wilson, “GPYtorch: Blackbox Matrix-Matrix Gaussian Process Inference with GPU Acceleration” with contributions from Max Balandat and Ruihan Wu. Available online: <https://github.com/cornelius-gp/gpytorch>
- [2] J. Demmel, P. Koev, and X. Li, “A Brief Survey of Direct Linear Solvers”. In Z. Bai, J. Demmel, J. Dongarra, A. Ruhe, and H. van der Vorst, editors. Templates for the Solution of Algebraic Eigenvalue Problems: A Practical Guide. SIAM, Philadelphia, 2000. Available at: <http://www.netlib.org/utk/people/JackDongarra/etemplates/node384.html>
- [3] R. Scheibler, E. Bezzam, I. Dokmanic, Pyroomacoustics: A Python package for audio room simulations and array processing algorithms, Proc. IEEE ICASSP, Calgary, CA, 2018. <https://github.com/LCAV/pyroomacoustics/blob/pypi-release/pyroomacoustics/adaptive/util.py>
- [4] Marano S, Edwards B, Ferrari G and Fah D (2017), “Fitting Earthquake Spectra: Colored Noise and Incomplete Data”, Bulletin of the Seismological Society of America., January, 2017. Vol. 107(1), pp. 276-291.
- [1] G. H. Golub and C. F. Van Loan, *Matrix Computations*, Baltimore, MD, Johns Hopkins University Press, 1985, pg. 15

- [1] Peter H. Schonemann, "A generalized solution of the orthogonal Procrustes problem", *Psychometrika* – Vol. 31, No. 1, March, 1996.
- [1] : B.N. Parlett and C. Reinsch, "Balancing a Matrix for Calculation of Eigenvalues and Eigenvectors", *Numerische Mathematik*, Vol.13(4), 1969, DOI:10.1007/BF02165404
- [2] : R. James, J. Langou, B.R. Lowery, "On matrix balancing and eigenvector computation", 2014, arXiv:1401.5766
- [3] : D.S. Watkins. A case where balancing is harmful. *Electron. Trans. Numer. Anal.*, Vol.23, 2006.
- [1] Knyazev A, Argentati M (2002) Principal Angles between Subspaces in an A-Based Scalar Product: Algorithms and Perturbation Estimates. *SIAM J. Sci. Comput.* 23:2008-2040.
- [1] J.R. Bunch, L. Kaufman, Some stable methods for calculating inertia and solving symmetric linear systems, *Math. Comput.* Vol.31, 1977. DOI:10.2307/2005787
- [1] R. A. Horn and C. R. Johnson, "Matrix Analysis", Cambridge University Press, 1985.
- [2] N. J. Higham, "Functions of Matrices: Theory and Computation", SIAM, 2008.
- [1] Golub, G. H. & Van Loan, C. F. *Matrix Computations*, 3rd Ed. (Johns Hopkins University Press, 1996).
- [2] Daniel, J. W., Gragg, W. B., Kaufman, L. & Stewart, G. W. Reorthogonalization and stable algorithms for updating the Gram-Schmidt QR factorization. *Math. Comput.* 30, 772-795 (1976).
- [3] Reichel, L. & Gragg, W. B. Algorithm 686: FORTRAN Subroutines for Updating the QR Decomposition. *ACM Trans. Math. Softw.* 16, 369-377 (1990).
- [1] Golub, G. H. & Van Loan, C. F. *Matrix Computations*, 3rd Ed. (Johns Hopkins University Press, 1996).
- [2] Daniel, J. W., Gragg, W. B., Kaufman, L. & Stewart, G. W. Reorthogonalization and stable algorithms for updating the Gram-Schmidt QR factorization. *Math. Comput.* 30, 772-795 (1976).
- [3] Reichel, L. & Gragg, W. B. Algorithm 686: FORTRAN Subroutines for Updating the QR Decomposition. *ACM Trans. Math. Softw.* 16, 369-377 (1990).
- [1] Golub, G. H. & Van Loan, C. F. *Matrix Computations*, 3rd Ed. (Johns Hopkins University Press, 1996).
- [2] Daniel, J. W., Gragg, W. B., Kaufman, L. & Stewart, G. W. Reorthogonalization and stable algorithms for updating the Gram-Schmidt QR factorization. *Math. Comput.* 30, 772-795 (1976).
- [3] Reichel, L. & Gragg, W. B. Algorithm 686: FORTRAN Subroutines for Updating the QR Decomposition. *ACM Trans. Math. Softw.* 16, 369-377 (1990).
- [1] : Brian D. Sutton. Computing the complete CS decomposition. *Numer. Algorithms*, 50(1):33-65, 2009.
- [1] Awad H. Al-Mohy and Nicholas J. Higham (2009) "A New Scaling and Squaring Algorithm for the Matrix Exponential." *SIAM Journal on Matrix Analysis and Applications*. 31 (3). pp. 970-989. ISSN 1095-7162
- [1] Awad H. Al-Mohy and Nicholas J. Higham (2012) "Improved Inverse Scaling and Squaring Algorithms for the Matrix Logarithm." *SIAM Journal on Scientific Computing*, 34 (4). C152-C169. ISSN 1095-7197
- [2] Nicholas J. Higham (2008) "Functions of Matrices: Theory and Computation" ISBN 978-0-898716-46-7
- [3] Nicholas J. Higham and Lijing lin (2011) "A Schur-Pade Algorithm for Fractional Powers of a Matrix." *SIAM Journal on Matrix Analysis and Applications*, 32 (3). pp. 1056-1078. ISSN 0895-4798
- [1] Edvin Deadman, Nicholas J. Higham, Rui Ralha (2013) "Blocked Schur Algorithms for Computing the Matrix Square Root, *Lecture Notes in Computer Science*, 7782. pp. 171-182.
- [1] Gene H. Golub, Charles F. van Loan, *Matrix Computations* 4th ed.
- [1] Awad H. Al-Mohy and Nicholas J. Higham (2009) Computing the Frechet Derivative of the Matrix Exponential, with an application to Condition Number Estimation. *SIAM Journal On Matrix Analysis and Applications.*, 30 (4). pp. 1639-1657. ISSN 1095-7162

- [1] Nicholas J. Higham and Lijing lin (2011) “A Schur-Pade Algorithm for Fractional Powers of a Matrix.” *SIAM Journal on Matrix Analysis and Applications*, 32 (3). pp. 1056-1078. ISSN 0895-4798
- [1] P. van Dooren , “A Generalized Eigenvalue Approach For Solving Riccati Equations.”, *SIAM Journal on Scientific and Statistical Computing*, Vol.2(2), DOI:10.1137/0902010
- [2] A.J. Laub, “A Schur Method for Solving Algebraic Riccati Equations.”, Massachusetts Institute of Technology. Laboratory for Information and Decision Systems. LIDS-R ; 859. Available online : <http://hdl.handle.net/1721.1/1301>
- [3] P. Benner, “Symplectic Balancing of Hamiltonian Matrices”, 2001, *SIAM J. Sci. Comput.*, 2001, Vol.22(5), DOI:10.1137/S1064827500367993
- [1] P. van Dooren , “A Generalized Eigenvalue Approach For Solving Riccati Equations.”, *SIAM Journal on Scientific and Statistical Computing*, Vol.2(2), DOI:10.1137/0902010
- [2] A.J. Laub, “A Schur Method for Solving Algebraic Riccati Equations.”, Massachusetts Institute of Technology. Laboratory for Information and Decision Systems. LIDS-R ; 859. Available online : <http://hdl.handle.net/1721.1/1301>
- [3] P. Benner, “Symplectic Balancing of Hamiltonian Matrices”, 2001, *SIAM J. Sci. Comput.*, 2001, Vol.22(5), DOI:10.1137/S1064827500367993
- [1] Hamilton, James D. *Time Series Analysis*, Princeton: Princeton University Press, 1994. 265. Print. <http://doc1.lbfli.li/aca/FLMF037168.pdf>
- [2] Gajic, Z., and M.T.J. Qureshi. 2008. *Lyapunov Matrix Equation in System Stability and Control*. Dover Books on Engineering Series. Dover Publications.
- [1] Kenneth L. Clarkson and David P. Woodruff. Low rank approximation and regression in input sparsity time. In *STOC*, 2013.
- [2] David P. Woodruff. Sketching as a tool for numerical linear algebra. In *Foundations and Trends in Theoretical Computer Science*, 2014.
- [1] R. A. Horn & C. R. Johnson, *Matrix Analysis*. Cambridge, UK: Cambridge University Press, 1999, pp. 146-7.
- [1] “Convolution”, <https://en.wikipedia.org/wiki/Convolution>
- [1] “DFT matrix”, https://en.wikipedia.org/wiki/DFT_matrix
- [1] J. Todd, “Basic Numerical Mathematics: Vol.2 : Numerical Algebra”, 1977, Birkhauser, DOI:10.1007/978-3-0348-7286-7
- [1] M. Fiedler, ” A note on companion matrices”, *Linear Algebra and its Applications*, 2003, DOI:10.1016/S0024-3795(03)00548-2
- [1] P. H. Leslie, On the use of matrices in certain population mathematics, *Biometrika*, Vol. 33, No. 3, 183–212 (Nov. 1945)
- [2] P. H. Leslie, Some further notes on the use of matrices in population mathematics, *Biometrika*, Vol. 35, No. 3/4, 213–245 (Dec. 1948)
- [1] “Pascal matrix”, https://en.wikipedia.org/wiki/Pascal_matrix
- [2] Cohen, A. M., “The inverse of a Pascal matrix”, *Mathematical Gazette*, 59(408), pp. 111-112, 1975.
- [R5a82238cdab4-1] P.G. Martinsson, V. Rokhlin, Y. Shkolnisky, M. Tygert. “ID: a software package for low-rank approximation of matrices via interpolative decompositions, version 0.2.” http://tygert.com/id_doc.4.pdf.
- [R5a82238cdab4-2] H. Cheng, Z. Gimbutas, P.G. Martinsson, V. Rokhlin. “On the compression of low rank matrices.” *SIAM J. Sci. Comput.* 26 (4): 1389–1404, 2005. DOI:10.1137/030602678.

- [R5a82238cdab4-3] E. Liberty, F. Woolfe, P.G. Martinsson, V. Rokhlin, M. Tygert. “Randomized algorithms for the low-rank approximation of matrices.” *Proc. Natl. Acad. Sci. U.S.A.* 104 (51): 20167–20172, 2007. DOI:10.1073/pnas.0709640104.
- [R5a82238cdab4-4] P.G. Martinsson, V. Rokhlin, M. Tygert. “A randomized algorithm for the decomposition of matrices.” *Appl. Comput. Harmon. Anal.* 30 (1): 47–68, 2011. DOI:10.1016/j.acha.2010.02.003.
- [R5a82238cdab4-5] F. Woolfe, E. Liberty, V. Rokhlin, M. Tygert. “A fast randomized algorithm for the approximation of matrices.” *Appl. Comput. Harmon. Anal.* 25 (3): 335–366, 2008. DOI:10.1016/j.acha.2007.12.002.
- [1] https://en.wikipedia.org/wiki/Finite_difference
- [1] Moody GB, Mark RG. The impact of the MIT-BIH Arrhythmia Database. *IEEE Eng in Med and Biol* 20(3):45-50 (May-June 2001). (PMID: 11446209); DOI:10.13026/C2F305
- [2] Goldberger AL, Amaral LAN, Glass L, Hausdorff JM, Ivanov PCh, Mark RG, Mietus JE, Moody GB, Peng C-K, Stanley HE. PhysioBank, PhysioToolkit, and PhysioNet: Components of a New Research Resource for Complex Physiologic Signals. *Circulation* 101(23):e215-e220; DOI:10.1161/01.CIR.101.23.e215
- [1] <http://citeseerx.ist.psu.edu/viewdoc/summary?doi=10.1.1.42.2777>
- [2] <http://www.richardhartersworld.com/cr/2001/slidingmin.html>
- [1] <http://citeseerx.ist.psu.edu/viewdoc/summary?doi=10.1.1.42.2777>
- [2] <http://www.richardhartersworld.com/cr/2001/slidingmin.html>
- [1] https://en.wikipedia.org/wiki/Homogeneous_coordinates
- [1] James R. Weaver, “Centrosymmetric (cross-symmetric) matrices, their basic properties, eigenvalues, and eigenvectors.” *The American Mathematical Monthly* 92.10 (1985): 711-717.
- [1] A.X. Falcao, J. Stolfi and R. de Alencar Lotufo, “The image foresting transform: theory, algorithms, and applications”, *Pattern Analysis and Machine Intelligence*, vol. 26, pp. 19-29, 2004.
- [1] https://en.wikipedia.org/wiki/Closing_%28morphology%29
- [2] https://en.wikipedia.org/wiki/Mathematical_morphology
- [1] https://en.wikipedia.org/wiki/Dilation_%28morphology%29
- [2] https://en.wikipedia.org/wiki/Mathematical_morphology
- [1] https://en.wikipedia.org/wiki/Erosion_%28morphology%29
- [2] https://en.wikipedia.org/wiki/Mathematical_morphology
- [1] https://en.wikipedia.org/wiki/Mathematical_morphology
- [1] https://en.wikipedia.org/wiki/Hit-or-miss_transform
- [1] https://en.wikipedia.org/wiki/Opening_%28morphology%29
- [2] https://en.wikipedia.org/wiki/Mathematical_morphology
- [1] <http://cmm.ensmp.fr/~serra/cours/pdf/en/ch6en.pdf>, slide 15.
- [2] I.T. Young, J.J. Gerbrands, and L.J. van Vliet, “Fundamentals of image processing”, 1998 <ftp://qiftp.tudelft.nl/DIPimage/docs/FIP2.3.pdf>
- [1] https://en.wikipedia.org/wiki/Mathematical_morphology
- [1] https://en.wikipedia.org/wiki/Dilation_%28morphology%29
- [2] https://en.wikipedia.org/wiki/Mathematical_morphology
- [1] https://en.wikipedia.org/wiki/Erosion_%28morphology%29

- [2] https://en.wikipedia.org/wiki/Mathematical_morphology
- [1] https://en.wikipedia.org/wiki/Mathematical_morphology
- [1] https://en.wikipedia.org/wiki/Mathematical_morphology
- [1] P. T. Boggs and J. E. Rogers, "Orthogonal Distance Regression," in "Statistical analysis of measurement error models and applications: proceedings of the AMS-IMS-SIAM joint summer research conference held June 10-16, 1989," Contemporary Mathematics, vol. 112, pg. 186, 1990.
- [1] Nelder, J A, and R Mead. 1965. A Simplex Method for Function Minimization. The Computer Journal 7: 308-13.
- [2] Wright M H. 1996. Direct search methods: Once scorned, now respectable, in Numerical Analysis 1995: Proceedings of the 1995 Dundee Biennial Conference in Numerical Analysis (Eds. D F Griffiths and G A Watson). Addison Wesley Longman, Harlow, UK. 191-208.
- [3] Powell, M J D. 1964. An efficient method for finding the minimum of a function of several variables without calculating derivatives. The Computer Journal 7: 155-162.
- [4] Press W, S A Teukolsky, W T Vetterling and B P Flannery. Numerical Recipes (any edition), Cambridge University Press.
- [5] Nocedal, J, and S J Wright. 2006. Numerical Optimization. Springer New York.
- [6] Byrd, R H and P Lu and J. Nocedal. 1995. A Limited Memory Algorithm for Bound Constrained Optimization. SIAM Journal on Scientific and Statistical Computing 16 (5): 1190-1208.
- [7] Zhu, C and R H Byrd and J Nocedal. 1997. L-BFGS-B: Algorithm 778: L-BFGS-B, FORTRAN routines for large scale bound constrained optimization. ACM Transactions on Mathematical Software 23 (4): 550-560.
- [8] Nash, S G. Newton-Type Minimization Via the Lanczos Method. 1984. SIAM Journal of Numerical Analysis 21: 770-778.
- [9] Powell, M J D. A direct search optimization method that models the objective and constraint functions by linear interpolation. 1994. Advances in Optimization and Numerical Analysis, eds. S. Gomez and J-P Hennart, Kluwer Academic (Dordrecht), 51-67.
- [10] Powell M J D. Direct search algorithms for optimization calculations. 1998. Acta Numerica 7: 287-336.
- [11] Powell M J D. A view of algorithms for optimization without derivatives. 2007. Cambridge University Technical Report DAMTP 2007/NA03
- [12] Kraft, D. A software package for sequential quadratic programming. 1988. Tech. Rep. DFVLR-FB 88-28, DLR German Aerospace Center – Institute for Flight Mechanics, Koln, Germany.
- [13] Conn, A. R., Gould, N. I., and Toint, P. L. Trust region methods. 2000. Siam. pp. 169-200.
- [14] F. Lenders, C. Kirches, A. Potschka: "trlib: A vector-free implementation of the GLTR method for iterative solution of the trust region problem", [arXiv:1611.04718](https://arxiv.org/abs/1611.04718)
- [15] N. Gould, S. Lucidi, M. Roma, P. Toint: "Solving the Trust-Region Subproblem using the Lanczos Method", SIAM J. Optim., 9(2), 504–525, (1999).
- [16] Byrd, Richard H., Mary E. Hribar, and Jorge Nocedal. 1999. An interior point algorithm for large-scale nonlinear programming. SIAM Journal on Optimization 9.4: 877-900.
- [17] Lalee, Marucha, Jorge Nocedal, and Todd Plantega. 1998. On the implementation of an algorithm for large-scale equality constrained optimization. SIAM Journal on Optimization 8.3: 682-706.
- [1] Gao, F. and Han, L. Implementing the Nelder-Mead simplex algorithm with adaptive parameters. 2012. Computational Optimization and Applications. 51:1, pp. 259-277
- [1] Conn, A. R., Gould, N. I., & Toint, P. L. Trust region methods. 2000. Siam. pp. 19.

- [1] Nocedal, Jorge, and Stephen J. Wright. "Numerical optimization" Second Edition (2006).
- [1] Nocedal, Jorge, and Stephen J. Wright. "Numerical optimization" Second Edition (2006).
- [1] Wales, David J. 2003, Energy Landscapes, Cambridge University Press, Cambridge, UK.
- [2] Wales, D J, and Doye J P K, Global Optimization by Basin-Hopping and the Lowest Energy Structures of Lennard-Jones Clusters Containing up to 110 Atoms. *Journal of Physical Chemistry A*, 1997, 101, 5111.
- [3] Li, Z. and Scheraga, H. A., Monte Carlo-minimization approach to the multiple-minima problem in protein folding, *Proc. Natl. Acad. Sci. USA*, 1987, 84, 6611.
- [4] Wales, D. J. and Scheraga, H. A., Global optimization of clusters, crystals, and biomolecules, *Science*, 1999, 285, 1368.
- [5] Olson, B., Hashmi, I., Molloy, K., and Shehu1, A., Basin Hopping as a General and Versatile Optimization Framework for the Characterization of Biological Macromolecules, *Advances in Artificial Intelligence*, Volume 2012 (2012), Article ID 674832, DOI:10.1155/2012/674832
- [1] Storn, R and Price, K, Differential Evolution - a Simple and Efficient Heuristic for Global Optimization over Continuous Spaces, *Journal of Global Optimization*, 1997, 11, 341 - 359.
- [2] <http://www1.icsi.berkeley.edu/~storn/code.html>
- [3] http://en.wikipedia.org/wiki/Differential_evolution
- [4] Wormington, M., Panaccione, C., Matney, K. M., Bowen, D. K., - Characterization of structures from X-ray scattering data using genetic algorithms, *Phil. Trans. R. Soc. Lond. A*, 1999, 357, 2827-2848
- [5] Lampinen, J., A constraint handling approach for the differential evolution algorithm. *Proceedings of the 2002 Congress on Evolutionary Computation. CEC'02 (Cat. No. 02TH8600)*. Vol. 2. IEEE, 2002.
- [1] Endres, SC, Sandrock, C, Focke, WW (2018) "A simplicial homology algorithm for lipschitz optimisation", *Journal of Global Optimization*.
- [2] Sobol, IM (1967) "The distribution of points in a cube and the approximate evaluation of integrals", *USSR Comput. Math. Math. Phys.* 7, 86-112.
- [3] Joe, SW and Kuo, FY (2008) "Constructing Sobol sequences with better two-dimensional projections", *SIAM J. Sci. Comput.* 30, 2635-2654.
- [4] Hoch, W and Schittkowski, K (1981) "Test examples for nonlinear programming codes", *Lecture Notes in Economics and Mathematical Systems*, 187. Springer-Verlag, New York. http://www.ai7.uni-bayreuth.de/test_problem_coll.pdf
- [5] Wales, DJ (2015) "Perspective: Insight into reaction coordinates and dynamics from the potential energy landscape", *Journal of Chemical Physics*, 142(13), 2015.
- [1] Tsallis C. Possible generalization of Boltzmann-Gibbs statistics. *Journal of Statistical Physics*, 52, 479-487 (1998).
- [2] Tsallis C, Stariolo DA. Generalized Simulated Annealing. *Physica A*, 233, 395-406 (1996).
- [3] Xiang Y, Sun DY, Fan W, Gong XG. Generalized Simulated Annealing Algorithm and Its Application to the Thomson Model. *Physics Letters A*, 233, 216-220 (1997).
- [4] Xiang Y, Gong XG. Efficiency of Generalized Simulated Annealing. *Physical Review E*, 62, 4473 (2000).
- [5] Xiang Y, Gubian S, Suomela B, Hoeng J. Generalized Simulated Annealing for Efficient Global Optimization: the GenSA Package for R. *The R Journal*, Volume 5/1 (2013).
- [6] Mullen, K. Continuous Global Optimization in R. *Journal of Statistical Software*, 60(6), 1 - 45, (2014). DOI:10.18637/jss.v060.i06

- [STIR] M. A. Branch, T. F. Coleman, and Y. Li, “A Subspace, Interior, and Conjugate Gradient Method for Large-Scale Bound-Constrained Minimization Problems,” *SIAM Journal on Scientific Computing*, Vol. 21, Number 1, pp 1-23, 1999.
- [NR] William H. Press et. al., “Numerical Recipes. The Art of Scientific Computing. 3rd edition”, Sec. 5.7.
- [Byrd] R. H. Byrd, R. B. Schnabel and G. A. Shultz, “Approximate solution of the trust region problem by minimization over two-dimensional subspaces”, *Math. Programming*, 40, pp. 247-263, 1988.
- [Curtis] A. Curtis, M. J. D. Powell, and J. Reid, “On the estimation of sparse Jacobian matrices”, *Journal of the Institute of Mathematics and its Applications*, 13, pp. 117-120, 1974.
- [JJMore] J. J. More, “The Levenberg-Marquardt Algorithm: Implementation and Theory,” *Numerical Analysis*, ed. G. A. Watson, *Lecture Notes in Mathematics* 630, Springer Verlag, pp. 105-116, 1977.
- [Voglis] C. Voglis and I. E. Lagaris, “A Rectangular Trust Region Dogleg Approach for Unconstrained and Bound Constrained Nonlinear Optimization”, *WSEAS International Conference on Applied Mathematics*, Corfu, Greece, 2004.
- [NumOpt] J. Nocedal and S. J. Wright, “Numerical optimization, 2nd edition”, Chapter 4.
- [BA] B. Triggs et. al., “Bundle Adjustment - A Modern Synthesis”, *Proceedings of the International Workshop on Vision Algorithms: Theory and Practice*, pp. 298-372, 1999.
- [STIR] M. A. Branch, T. F. Coleman, and Y. Li, “A Subspace, Interior, and Conjugate Gradient Method for Large-Scale Bound-Constrained Minimization Problems,” *SIAM Journal on Scientific Computing*, Vol. 21, Number 1, pp 1-23, 1999.
- [BVLS] P. B. Start and R. L. Parker, “Bounded-Variable Least-Squares: an Algorithm and Applications”, *Computational Statistics*, 10, 129-141, 1995.
- [Brent1973] Brent, R. P., *Algorithms for Minimization Without Derivatives*. Englewood Cliffs, NJ: Prentice-Hall, 1973. Ch. 3-4.
- [PressEtal1992] Press, W. H.; Flannery, B. P.; Teukolsky, S. A.; and Vetterling, W. T. *Numerical Recipes in FORTRAN: The Art of Scientific Computing*, 2nd ed. Cambridge, England: Cambridge University Press, pp. 352-355, 1992. Section 9.3: “Van Wijngaarden-Dekker-Brent Method.”
- [Ridders1979] Ridders, C. F. J. “A New Algorithm for Computing a Single Root of a Real Continuous Function.” *IEEE Trans. Circuits Systems* 26, 979-980, 1979.
- [APS1995] Alefeld, G. E. and Potra, F. A. and Shi, Yixun, *Algorithm 748: Enclosing Zeros of Continuous Functions*, *ACM Trans. Math. Softw.* Volume 221(1995) doi = {10.1145/210089.210111}
- [1] Burden, Faires, “Numerical Analysis”, 5th edition, pg. 80
- [1] More, Jorge J., Burton S. Garbow, and Kenneth E. Hillstrom. 1980. User Guide for MINPACK-1.
- [2] C. T. Kelley. 1995. *Iterative Methods for Linear and Nonlinear Equations*. Society for Industrial and Applied Mathematics. <<https://archive.siam.org/books/kelley/fr16/>>
- [3] W. La Cruz, J.M. Martinez, M. Raydan. *Math. Comp.* 75, 1429 (2006).
- [1] “Spectral residual method without gradient information for solving large-scale nonlinear systems of equations.” W. La Cruz, J.M. Martinez, M. Raydan. *Math. Comp.* 75, 1429 (2006).
- [2] W. La Cruz, *Opt. Meth. Software*, 29, 24 (2014).
- [3] W. Cheng, D.-H. Li. *IMA J. Numer. Anal.* 29, 814 (2009).
- [1] Dantzig, George B., *Linear programming and extensions*. Rand Corporation Research Study Princeton Univ. Press, Princeton, NJ, 1963
- [2] Hillier, S.H. and Lieberman, G.J. (1995), “Introduction to Mathematical Programming”, McGraw-Hill, Chapter 4.

- [3] Bland, Robert G. New finite pivoting rules for the simplex method. *Mathematics of Operations Research* (2), 1977: pp. 103-107.
- [4] Andersen, Erling D., and Knud D. Andersen. "The MOSEK interior point optimizer for linear programming: an implementation of the homogeneous algorithm." *High performance optimization*. Springer US, 2000. 197-232.
- [5] Andersen, Erling D. "Finding all linearly dependent rows in large-scale linear programming." *Optimization Methods and Software* 6.3 (1995): 219-227.
- [6] Freund, Robert M. "Primal-Dual Interior-Point Methods for Linear Programming based on Newton's Method." Unpublished Course Notes, March 2004. Available 2/25/2017 at https://ocw.mit.edu/courses/sloan-school-of-management/15-084j-nonlinear-programming-spring-2004/lecture-notes/lec14_int_pt_mthd.pdf
- [7] Fourer, Robert. "Solving Linear Programs by Interior-Point Methods." Unpublished Course Notes, August 26, 2005. Available 2/25/2017 at <http://www.4er.org/CourseNotes/Book%20B/B-III.pdf>
- [8] Andersen, Erling D., and Knud D. Andersen. "Presolving in linear programming." *Mathematical Programming* 71.2 (1995): 221-245.
- [9] Bertsimas, Dimitris, and J. Tsitsiklis. "Introduction to linear programming." *Athena Scientific* 1 (1997): 997.
- [10] Andersen, Erling D., et al. *Implementation of interior point methods for large scale linear programming*. HEC/Universite de Geneve, 1996.
- [11] Bartels, Richard H. "A stabilization of the simplex method." *Journal in Numerische Mathematik* 16.5 (1971): 414-434.
- [12] Tomlin, J. A. "On scaling linear programming problems." *Mathematical Programming Study* 4 (1975): 146-166.
- [13] Huangfu, Q., Galabova, I., Feldmeier, M., and Hall, J. A. J. "HiGHS - high performance software for linear optimization." Accessed 4/16/2020 at <https://www.maths.ed.ac.uk/hall/HiGHS/#guide>
- [14] Huangfu, Q. and Hall, J. A. J. "Parallelizing the dual revised simplex method." *Mathematical Programming Computation*, 10 (1), 119-142, 2018. DOI: 10.1007/s12532-017-0130-5
- [1] Dantzig, George B., *Linear programming and extensions*. Rand Corporation Research Study Princeton Univ. Press, Princeton, NJ, 1963
- [2] Hillier, S.H. and Lieberman, G.J. (1995), "Introduction to Mathematical Programming", McGraw-Hill, Chapter 4.
- [3] Bland, Robert G. New finite pivoting rules for the simplex method. *Mathematics of Operations Research* (2), 1977: pp. 103-107.
- [4] Andersen, Erling D., and Knud D. Andersen. "The MOSEK interior point optimizer for linear programming: an implementation of the homogeneous algorithm." *High performance optimization*. Springer US, 2000. 197-232.
- [6] Freund, Robert M. "Primal-Dual Interior-Point Methods for Linear Programming based on Newton's Method." Unpublished Course Notes, March 2004. Available 2/25/2017 at https://ocw.mit.edu/courses/sloan-school-of-management/15-084j-nonlinear-programming-spring-2004/lecture-notes/lec14_int_pt_mthd.pdf
- [8] Andersen, Erling D., and Knud D. Andersen. "Presolving in linear programming." *Mathematical Programming* 71.2 (1995): 221-245.
- [9] Bertsimas, Dimitris, and J. Tsitsiklis. "Introduction to linear programming." *Athena Scientific* 1 (1997): 997.
- [10] Andersen, Erling D., et al. *Implementation of interior point methods for large scale linear programming*. HEC/Universite de Geneve, 1996.

- [9] Bertsimas, Dimitris, and J. Tsitsiklis. "Introduction to linear programming." Athena Scientific 1 (1997): 997.
- [11] Bartels, Richard H. "A stabilization of the simplex method." *Journal in Numerische Mathematik* 16.5 (1971): 414-434.
- [13] Huangfu, Q., Galabova, I., Feldmeier, M., and Hall, J. A. J. "HiGHS - high performance software for linear optimization." Accessed 4/16/2020 at <https://www.maths.ed.ac.uk/hall/HiGHS/#guide>
- [14] Huangfu, Q. and Hall, J. A. J. "Parallelizing the dual revised simplex method." *Mathematical Programming Computation*, 10 (1), 119-142, 2018. DOI: 10.1007/s12532-017-0130-5
- [13] Huangfu, Q., Galabova, I., Feldmeier, M., and Hall, J. A. J. "HiGHS - high performance software for linear optimization." Accessed 4/16/2020 at <https://www.maths.ed.ac.uk/hall/HiGHS/#guide>
- [14] Huangfu, Q. and Hall, J. A. J. "Parallelizing the dual revised simplex method." *Mathematical Programming Computation*, 10 (1), 119-142, 2018. DOI: 10.1007/s12532-017-0130-5
- [15] Harris, Paula MJ. "Pivot selection methods of the Devex LP code." *Mathematical programming* 5.1 (1973): 1-28.
- [16] Goldfarb, Donald, and John Ker Reid. "A practicable steepest-edge simplex algorithm." *Mathematical Programming* 12.1 (1977): 361-371.
- [13] Huangfu, Q., Galabova, I., Feldmeier, M., and Hall, J. A. J. "HiGHS - high performance software for linear optimization." Accessed 4/16/2020 at <https://www.maths.ed.ac.uk/hall/HiGHS/#guide>
- [14] Huangfu, Q. and Hall, J. A. J. "Parallelizing the dual revised simplex method." *Mathematical Programming Computation*, 10 (1), 119-142, 2018. DOI: 10.1007/s12532-017-0130-5
- [15] Harris, Paula MJ. "Pivot selection methods of the Devex LP code." *Mathematical programming* 5.1 (1973): 1-28.
- [16] Goldfarb, Donald, and John Ker Reid. "A practicable steepest-edge simplex algorithm." *Mathematical Programming* 12.1 (1977): 361-371.
- [1] J.T. Vogelstein, J.M. Conroy, V. Lyzinski, L.J. Podrazik, S.G. Kratzer, E.T. Harley, D.E. Fishkind, R.J. Vogelstein, and C.E. Priebe, "Fast approximate quadratic programming for graph matching," *PLOS one*, vol. 10, no. 4, p. e0121002, 2015, DOI:10.1371/journal.pone.0121002
- [2] D. Fishkind, S. Adali, H. Patsolic, L. Meng, D. Singh, V. Lyzinski, C. Priebe, "Seeded graph matching", *Pattern Recognit.* 87 (2019): 203-215, DOI:10.1016/j.patcog.2018.09.014
- [3] "2-opt," Wikipedia. <https://en.wikipedia.org/wiki/2-opt>
- [1] J.T. Vogelstein, J.M. Conroy, V. Lyzinski, L.J. Podrazik, S.G. Kratzer, E.T. Harley, D.E. Fishkind, R.J. Vogelstein, and C.E. Priebe, "Fast approximate quadratic programming for graph matching," *PLOS one*, vol. 10, no. 4, p. e0121002, 2015, DOI:10.1371/journal.pone.0121002
- [2] D. Fishkind, S. Adali, H. Patsolic, L. Meng, D. Singh, V. Lyzinski, C. Priebe, "Seeded graph matching", *Pattern Recognit.* 87 (2019): 203-215, DOI:10.1016/j.patcog.2018.09.014
- [3] "Doubly stochastic Matrix," Wikipedia. https://en.wikipedia.org/wiki/Doubly_stochastic_matrix
- [1] "2-opt," Wikipedia. <https://en.wikipedia.org/wiki/2-opt>
- [2] D. Fishkind, S. Adali, H. Patsolic, L. Meng, D. Singh, V. Lyzinski, C. Priebe, "Seeded graph matching", *Pattern Recognit.* 87 (2019): 203-215, <https://doi.org/10.1016/j.patcog.2018.09.014>
- [1] Nocedal, Jorge. "Updating quasi-Newton matrices with limited storage." *Mathematics of computation* 35.151 (1980): 773-782.
- [1] Nelder, J.A. and Mead, R. (1965), "A simplex method for function minimization", *The Computer Journal*, 7, pp. 308-313

- [2] Wright, M.H. (1996), "Direct Search Methods: Once Scorned, Now Respectable", in Numerical Analysis 1995, Proceedings of the 1995 Dundee Biennial Conference in Numerical Analysis, D.F. Griffiths and G.A. Watson (Eds.), Addison Wesley Longman, Harlow, UK, pp. 191-208.
- [1] Wright & Nocedal, "Numerical Optimization", 1999, pp. 120-122.
- [1] B.A. van der Rotten, PhD thesis, "A limited memory Broyden method to solve high-dimensional systems of nonlinear equations". Mathematisch Instituut, Universiteit Leiden, The Netherlands (2003).
<https://web.archive.org/web/20161022015821/http://www.math.leidenuniv.nl/scripts/Rotten.pdf>
- [1] B.A. van der Rotten, PhD thesis, "A limited memory Broyden method to solve high-dimensional systems of nonlinear equations". Mathematisch Instituut, Universiteit Leiden, The Netherlands (2003).
<https://web.archive.org/web/20161022015821/http://www.math.leidenuniv.nl/scripts/Rotten.pdf>
- [1] D.A. Knoll and D.E. Keyes, J. Comp. Phys. 193, 357 (2004). DOI:10.1016/j.jcp.2003.08.010
- [2] A.H. Baker and E.R. Jessup and T. Manteuffel, SIAM J. Matrix Anal. Appl. 26, 962 (2005). DOI:10.1137/S0895479803422014
- [Ey] V. Eyert, J. Comp. Phys., 124, 271 (1996).
- [1] Wikipedia, "Overlap-add_method". https://en.wikipedia.org/wiki/Overlap-add_method
- [2] Richard G. Lyons. Understanding Digital Signal Processing, Third Edition, 2011. Chapter 13.10. ISBN 13: 978-0137-02741-5
- [1] Bouma H., Vilanova A., Bescos J.O., ter Haar Romeny B.M., Gerritsen F.A. (2007) Fast and Accurate Gaussian Derivatives Based on B-Splines. In: Sgallari F., Murli A., Paragios N. (eds) Scale Space and Variational Methods in Computer Vision. SSVM 2007. Lecture Notes in Computer Science, vol 4485. Springer, Berlin, Heidelberg
- [2] <http://folk.uio.no/inf3330/scripting/doc/python/SciPy/tutorial/old/node24.html>
- [1] Lim, Jae S., Two-Dimensional Signal and Image Processing, Englewood Cliffs, NJ, Prentice Hall, 1990, p. 548.
- [1] F. Gustaffson, "Determining the initial states in forward-backward filtering", Transactions on Signal Processing, Vol. 46, pp. 988-992, 1996.
- [1] Wikipedia, "Analytic signal". https://en.wikipedia.org/wiki/Analytic_signal
- [2] Leon Cohen, "Time-Frequency Analysis", 1995. Chapter 2.
- [3] Alan V. Oppenheim, Ronald W. Schaffer. Discrete-Time Signal Processing, Third Edition, 2009. Chapter 12. ISBN 13: 978-1292-02572-8
- [1] Wikipedia, "Analytic signal", https://en.wikipedia.org/wiki/Analytic_signal
- [1] P. P. Vaidyanathan, Multirate Systems and Filter Banks, Prentice Hall, 1993.
- [1] Ivan Selesnick, Linear-Phase Fir Filter Design By Least Squares. OpenStax CNX. Aug 9, 2005. <http://cnx.org/contents/eb1ecb35-03a9-4610-ba87-41cd771c95f2@7>
- [1] Oppenheim, A. V. and Schaffer, R. W., "Discrete-Time Signal Processing", Prentice-Hall, Englewood Cliffs, New Jersey (1989). (See, for example, Section 7.4.)
- [2] Smith, Steven W., "The Scientist and Engineer's Guide to Digital Signal Processing", Ch. 17. <http://www.dspguide.com/ch17/1.htm>
- [1] Slaney, Malcolm, "An Efficient Implementation of the Patterson-Holdsworth Auditory Filter Bank", Apple Computer Technical Report 35, 1993, pp.3-8, 34-39.
- [1] Richard G. Lyons, "Understanding Digital Signal Processing, 3rd edition", p. 830.

- [1] N. Damera-Venkata and B. L. Evans, "Optimal design of real and complex minimum phase digital FIR filters," *Acoustics, Speech, and Signal Processing, 1999. Proceedings., 1999 IEEE International Conference on*, Phoenix, AZ, 1999, pp. 1145-1148 vol.3. DOI:10.1109/ICASSP.1999.756179
- [2] X. Chen and T. W. Parks, "Design of optimal minimum phase FIR filters by direct factorization," *Signal Processing*, vol. 10, no. 4, pp. 369-383, Jun. 1986.
- [3] T. Saramaki, "Finite Impulse Response Filter Design," in *Handbook for Digital Signal Processing*, chapter 4, New York: Wiley-Interscience, 1993.
- [4] J. S. Lim, *Advanced Topics in Signal Processing*. Englewood Cliffs, N.J.: Prentice Hall, 1988.
- [5] A. V. Oppenheim, R. W. Schaffer, and J. R. Buck, "Discrete-Time Signal Processing," 2nd edition. Upper Saddle River, N.J.: Prentice Hall, 1999.
- [1] J. H. McClellan and T. W. Parks, "A unified approach to the design of optimum FIR linear phase digital filters," *IEEE Trans. Circuit Theory*, vol. CT-20, pp. 697-701, 1973.
- [2] J. H. McClellan, T. W. Parks and L. R. Rabiner, "A Computer Program for Designing Optimum FIR Linear Phase Digital Filters", *IEEE Trans. Audio Electroacoust.*, vol. AU-21, pp. 506-525, 1973.
- [1] J. F. Mahoney, B. D. Sivazlian, "Partial fractions expansion: a review of computational methodology and efficiency", *Journal of Computational and Applied Mathematics*, Vol. 9, 1983.
- [1] C.R. Bond, "Bessel Filter Constants", <http://www.crbond.com/papers/bsf.pdf>
- [2] Campos and Calderon, "Approximate closed-form formulas for the zeros of the Bessel Polynomials", [arXiv:1105.0957](https://arxiv.org/abs/1105.0957).
- [3] Thomson, W.E., "Delay Networks having Maximally Flat Frequency Characteristics", *Proceedings of the Institution of Electrical Engineers, Part III*, November 1949, Vol. 96, No. 44, pp. 487-490.
- [4] Aberth, "Iteration Methods for Finding all Zeros of a Polynomial Simultaneously", *Mathematics of Computation*, Vol. 27, No. 122, April 1973
- [5] Ehrlich, "A modified Newton method for polynomials", *Communications of the ACM*, Vol. 10, Issue 2, pp. 107-108, Feb. 1967, DOI:10.1145/363067.363115
- [6] Miller and Bohn, "A Bessel Filter Crossover, and Its Relation to Others", *RaneNote 147*, 1998, <https://www.ranecommercial.com/legacy/note147.html>
- [1] Lutova, Tosic, and Evans, "Filter Design for Signal Processing", Chapters 5 and 12.
- [1] Thomson, W.E., "Delay Networks having Maximally Flat Frequency Characteristics", *Proceedings of the Institution of Electrical Engineers, Part III*, November 1949, Vol. 96, No. 44, pp. 487-490.
- [1] Sophocles J. Orfanidis, "Introduction To Signal Processing", Prentice-Hall, 1996
- [1] Sophocles J. Orfanidis, "Introduction To Signal Processing", Prentice-Hall, 1996
- [1] Sophocles J. Orfanidis, "Introduction To Signal Processing", Prentice-Hall, 1996
- [1] https://en.wikipedia.org/wiki/Discretization#Discretization_of_linear_state_space_models
- [2] http://techteach.no/publications/discretetime_signals_systems/discrete.pdf
- [3] G. Zhang, X. Chen, and T. Chen, Digital redesign via the generalized bilinear transformation, *Int. J. Control*, vol. 82, no. 4, pp. 741-754, 2009. (https://www.mypolyuweb.hk/~magzhang/Research/ZCC09_IJC.pdf)
- [4] G. F. Franklin, J. D. Powell, and M. L. Workman, *Digital control of dynamic systems*, 3rd ed. Menlo Park, Calif: Addison-Wesley, pp. 204-206, 1998.
- [1] J. Kautsky, N.K. Nichols and P. van Dooren, "Robust pole assignment in linear state feedback", *International Journal of Control*, Vol. 41 pp. 1129-1155, 1985.

- [2] A.L. Tits and Y. Yang, "Globally convergent algorithms for robust pole assignment by state feedback", IEEE Transactions on Automatic Control, Vol. 41, pp. 1432-1452, 1996.
- [1] S. Mallat, "A Wavelet Tour of Signal Processing (3rd Edition)", Academic Press, 2009.
- [1] Bioinformatics (2006) 22 (17): 2059-2065. DOI:10.1093/bioinformatics/btl355
- [1] Wikipedia Article for Topographic Prominence: https://en.wikipedia.org/wiki/Topographic_prominence
- [1] P. Welch, "The use of the fast Fourier transform for the estimation of power spectra: A method based on time averaging over short, modified periodograms", IEEE Trans. Audio Electroacoust. vol. 15, pp. 70-73, 1967.
- [2] M.S. Bartlett, "Periodogram Analysis and Continuous Spectra", Biometrika, vol. 37, pp. 1-16, 1950.
- [1] P. Welch, "The use of the fast Fourier transform for the estimation of power spectra: A method based on time averaging over short, modified periodograms", IEEE Trans. Audio Electroacoust. vol. 15, pp. 70-73, 1967.
- [2] Rabiner, Lawrence R., and B. Gold. "Theory and Application of Digital Signal Processing" Prentice-Hall, pp. 414-419, 1975
- [1] P. Welch, "The use of the fast Fourier transform for the estimation of power spectra: A method based on time averaging over short, modified periodograms", IEEE Trans. Audio Electroacoust. vol. 15, pp. 70-73, 1967.
- [2] Stoica, Petre, and Randolph Moses, "Spectral Analysis of Signals" Prentice Hall, 2005
- [1] Oppenheim, Alan V., Ronald W. Schaffer, John R. Buck "Discrete-Time Signal Processing", Prentice Hall, 1999.
- [1] N.R. Lomb "Least-squares frequency analysis of unequally spaced data", Astrophysics and Space Science, vol 39, pp. 447-462, 1976
- [2] J.D. Scargle "Studies in astronomical time series analysis. II - Statistical aspects of spectral analysis of unevenly spaced data", The Astrophysical Journal, vol 263, pp. 835-853, 1982
- [3] R.H.D. Townsend, "Fast calculation of the Lomb-Scargle periodogram using graphics processing units.", The Astrophysical Journal Supplement Series, vol 191, pp. 247-253, 2010
- [1] Oppenheim, Alan V., Ronald W. Schaffer, John R. Buck "Discrete-Time Signal Processing", Prentice Hall, 1999.
- [2] Daniel W. Griffin, Jae S. Lim "Signal Estimation from Modified Short-Time Fourier Transform", IEEE 1984, 10.1109/TASSP.1984.1164317
- [1] Oppenheim, Alan V., Ronald W. Schaffer, John R. Buck "Discrete-Time Signal Processing", Prentice Hall, 1999.
- [2] Daniel W. Griffin, Jae S. Lim "Signal Estimation from Modified Short-Time Fourier Transform", IEEE 1984, 10.1109/TASSP.1984.1164317
- [1] Julius O. Smith III, "Spectral Audio Signal Processing", W3K Publishing, 2011, ISBN 978-0-9745607-3-1.
- [2] G. Heinzl, A. Ruediger and R. Schilling, "Spectrum and spectral density estimation by the Discrete Fourier transform (DFT), including a comprehensive list of window functions and some new at-top windows", 2002, <http://hdl.handle.net/11858/00-001M-0000-0013-557A-5>
- [1] Julius O. Smith III, "Spectral Audio Signal Processing", W3K Publishing, 2011, ISBN 978-0-9745607-3-1.
- [2] G. Heinzl, A. Ruediger and R. Schilling, "Spectrum and spectral density estimation by the Discrete Fourier transform (DFT), including a comprehensive list of window functions and some new at-top windows", 2002, <http://hdl.handle.net/11858/00-001M-0000-0013-557A-5>

- [1] Awad H. Al-Mohy and Nicholas J. Higham (2009) “A New Scaling and Squaring Algorithm for the Matrix Exponential.” *SIAM Journal on Matrix Analysis and Applications*. 31 (3). pp. 970-989. ISSN 1095-7162
- [1] Awad H. Al-Mohy and Nicholas J. Higham (2011) “Computing the Action of the Matrix Exponential, with an Application to Exponential Integrators.” *SIAM Journal on Scientific Computing*, 33 (2). pp. 488-511. ISSN 1064-8275 <http://eprints.ma.man.ac.uk/1591/>
- [2] Nicholas J. Higham and Awad H. Al-Mohy (2010) “Computing Matrix Functions.” *Acta Numerica*, 19. 159-208. ISSN 0962-4929 <http://eprints.ma.man.ac.uk/1451/>
- [1] G. H. Golub and C. F. Van Loan, *Matrix Computations*, Baltimore, MD, Johns Hopkins University Press, 1985, pg. 15
- [1] Nicholas J. Higham and Françoise Tisseur (2000), “A Block Algorithm for Matrix 1-Norm Estimation, with an Application to 1-Norm Pseudospectra.” *SIAM J. Matrix Anal. Appl.* Vol. 21, No. 4, pp. 1185-1201.
- [2] Awad H. Al-Mohy and Nicholas J. Higham (2009), “A new scaling and squaring algorithm for the matrix exponential.” *SIAM J. Matrix Anal. Appl.* Vol. 31, No. 3, pp. 970-989.
- [1] A.H. Baker and E.R. Jessup and T. Manteuffel, “A Technique for Accelerating the Convergence of Restarted GMRES”, *SIAM J. Matrix Anal. Appl.* 26, 962 (2005).
- [2] A.H. Baker, “On Improving the Performance of the Linear Solver restarted GMRES”, PhD thesis, University of Colorado (2003).
- [1] E. de Sturler, “Truncation strategies for optimal Krylov subspace methods”, *SIAM J. Numer. Anal.* 36, 864 (1999).
- [2] J.E. Hicken and D.W. Zingg, “A simplified and flexible variant of GCROT for solving nonsymmetric linear systems”, *SIAM J. Sci. Comput.* 32, 172 (2010).
- [3] M.L. Parks, E. de Sturler, G. Mackey, D.D. Johnson, S. Maiti, “Recycling Krylov subspaces for sequences of linear systems”, *SIAM J. Sci. Comput.* 28, 1651 (2006).
- [1] C. C. Paige and M. A. Saunders (1982a). “LSQR: An algorithm for sparse linear equations and sparse least squares”, *ACM TOMS* 8(1), 43-71.
- [2] C. C. Paige and M. A. Saunders (1982b). “Algorithm 583. LSQR: Sparse linear equations and least squares problems”, *ACM TOMS* 8(2), 195-209.
- [3] M. A. Saunders (1995). “Solution of sparse rectangular systems using LSQR and CRAIG”, *BIT* 35, 588-604.
- [1] D. C.-L. Fong and M. A. Saunders, “LSMR: An iterative algorithm for sparse least-squares problems”, *SIAM J. Sci. Comput.*, vol. 33, pp. 2950-2971, 2011. [arXiv:1006.0758](https://arxiv.org/abs/1006.0758)
- [2] LSMR Software, <https://web.stanford.edu/group/SOL/software/lsmr/>
- [1] ARPACK Software, <http://www.caam.rice.edu/software/ARPACK/>
- [2] R. B. Lehoucq, D. C. Sorensen, and C. Yang, *ARPACK USERS GUIDE: Solution of Large Scale Eigenvalue Problems by Implicitly Restarted Arnoldi Methods*. SIAM, Philadelphia, PA, 1998.
- [1] ARPACK Software, <http://www.caam.rice.edu/software/ARPACK/>
- [2] R. B. Lehoucq, D. C. Sorensen, and C. Yang, *ARPACK USERS GUIDE: Solution of Large Scale Eigenvalue Problems by Implicitly Restarted Arnoldi Methods*. SIAM, Philadelphia, PA, 1998.
- [1] A. V. Knyazev (2001), Toward the Optimal Preconditioned Eigensolver: Locally Optimal Block Preconditioned Conjugate Gradient Method. *SIAM Journal on Scientific Computing* 23, no. 2, pp. 517-541. DOI:10.1137/S1064827500366124
- [2] A. V. Knyazev, I. Lashuk, M. E. Argentati, and E. Ovchinnikov (2007), Block Locally Optimal Preconditioned Eigenvalue Solvers (BLOPEX) in hypr and PETSc. [arXiv:0705.2626](https://arxiv.org/abs/0705.2626)
- [3] A. V. Knyazev’s C and MATLAB implementations: <https://bitbucket.org/joseroman/blopex>

- [4] S. Yamada, T. Imamura, T. Kano, and M. Machida (2006), High-performance computing for exact numerical approaches to quantum many-body problems on the earth simulator. In Proceedings of the 2006 ACM/IEEE Conference on Supercomputing. DOI:10.1145/1188455.1188504
- [1] SuperLU <http://crd.lbl.gov/~xiaoye/SuperLU/>
- [1] D. J. Pearce, “An Improved Algorithm for Finding the Strongly Connected Components of a Directed Graph”, Technical Report, 2005
- [1] Edmonds, J. and Karp, R. M. Theoretical improvements in algorithmic efficiency for network flow problems. 1972. Journal of the ACM. 19 (2): pp. 248-264
- [2] Cormen, T. H. and Leiserson, C. E. and Rivest, R. L. and Stein C. Introduction to Algorithms. Second Edition. 2001. MIT Press.
- [3] https://en.wikipedia.org/wiki/Graph_cuts_in_computer_vision
- [1] John E. Hopcroft and Richard M. Karp. “An $n^{\frac{5}{2}}$ Algorithm for Maximum Matchings in Bipartite Graphs” In: SIAM Journal of Computing 2.4 (1973), pp. 225–231. DOI:10.1137/0202019
- [1] Richard Manning Karp: An algorithm to Solve the $m \times n$ Assignment Problem in Expected Time $O(mn \log n)$. Networks, 10(2):143-152, 1980.
- [2] Roy Jonker and Anton Volgenant: A Shortest Augmenting Path Algorithm for Dense and Sparse Linear Assignment Problems. Computing 38:325-340, 1987.
- [3] https://en.wikipedia.org/wiki/Assignment_problem
- [1] I. S. Duff, “Computing the Structural Index”, SIAM J. Alg. Disc. Meth., Vol. 7, 594 (1986).
- [2] <http://www.cise.ufl.edu/research/sparse/matrices/legend.html>
- [1] Gray and Moore, “N-body problems in statistical learning”, Mining the sky, 2000, <https://arxiv.org/abs/astro-ph/0012333>
- [2] Landy and Szalay, “Bias and variance of angular correlation functions”, The Astrophysical Journal, 1993, <http://adsabs.harvard.edu/abs/1993ApJ...412...64L>
- [3] Sheth, Connolly and Skibba, “Marked correlations in galaxy formation models”, Arxiv e-print, 2005, <https://arxiv.org/abs/astro-ph/0511773>
- [4] Hawkins, et al., “The 2dF Galaxy Redshift Survey: correlation functions, peculiar velocities and the matter density of the Universe”, Monthly Notices of the Royal Astronomical Society, 2002, <http://adsabs.harvard.edu/abs/2003MNRAS.346...78H>
- [5] <https://github.com/scipy/scipy/pull/5647#issuecomment-168474926>
- [1] Gray and Moore, “N-body problems in statistical learning”, Mining the sky, 2000, arXiv:astro-ph/0012333
- [2] Landy and Szalay, “Bias and variance of angular correlation functions”, The Astrophysical Journal, 1993, DOI:10.1086/172900
- [3] Sheth, Connolly and Skibba, “Marked correlations in galaxy formation models”, 2005, arXiv:astro-ph/0511773
- [4] Hawkins, et al., “The 2dF Galaxy Redshift Survey: correlation functions, peculiar velocities and the matter density of the Universe”, Monthly Notices of the Royal Astronomical Society, 2002, DOI:10.1046/j.1365-2966.2003.07063.x
- [5] <https://github.com/scipy/scipy/pull/5647#issuecomment-168474926>
- [Qhull] <http://www.qhull.org/>
- [Caroli] Caroli et al. Robust and Efficient Delaunay triangulations of points on or close to a sphere. Research Report RR-7004, 2009.

- [VanOosterom] Van Oosterom and Strackee. The solid angle of a plane triangle. *IEEE Transactions on Biomedical Engineering*, 2, 1983, pp 125–126.
- [Qhull] <http://www.qhull.org/>
- [1] S. Boyd, L. Vandenberghe, *Convex Optimization*, available at <http://stanford.edu/~boyd/cvxbook/>
- [1] Krzanowski, W. J. (2000). “Principles of Multivariate analysis”.
- [2] Gower, J. C. (1975). “Generalized procrustes analysis”.
- [1] https://en.wikipedia.org/wiki/Slerp#Geometric_Slerp
- [2] Ken Shoemake (1985) Animating rotation with quaternion curves. *ACM SIGGRAPH Computer Graphics*, 19(3): 245-254.
- [1] A. A. Taha and A. Hanbury, “An efficient algorithm for calculating the exact Hausdorff distance.” *IEEE Transactions On Pattern Analysis And Machine Intelligence*, vol. 37 pp. 2153-63, 2015.
- [1] https://en.wikipedia.org/wiki/Jaccard_index
- [2] S. Kosub, “A note on the triangle inequality for the Jaccard distance”, 2016, [arXiv:1612.02696](https://arxiv.org/abs/1612.02696)
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [2] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>
- [1] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Milton Abramowitz and Irene A. Stegun, eds. *Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables*. New York: Dover, 1972.
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [2] Milton Abramowitz and Irene A. Stegun, eds. *Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables*. New York: Dover, 1972.
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [2] Milton Abramowitz and Irene A. Stegun, eds. *Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables*. New York: Dover, 1972.
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [2] Milton Abramowitz and Irene A. Stegun, eds. *Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables*. New York: Dover, 1972.
- [1] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>
- [1] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>

- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>
- [1] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>
- [1] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>
- [2] Donald E. Amos, “Algorithm 644: A portable package for Bessel functions of a complex argument and nonnegative order”, ACM TOMS Vol. 12 Issue 3, Sept. 1986, p. 265
- [1] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>
- [2] Donald E. Amos, “Algorithm 644: A portable package for Bessel functions of a complex argument and nonnegative order”, ACM TOMS Vol. 12 Issue 3, Sept. 1986, p. 265
- [3] NIST Digital Library of Mathematical Functions, Eq. 10.25.E3. <https://dlmf.nist.gov/10.25.E3>
- [1] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>
- [2] Donald E. Amos, “Algorithm 644: A portable package for Bessel functions of a complex argument and nonnegative order”, ACM TOMS Vol. 12 Issue 3, Sept. 1986, p. 265
- [1] Temme, Journal of Computational Physics, vol 21, 343 (1976)
- [2] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>
- [1] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>
- [1] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>
- [1] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>
- [1] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>
- [1] Donald E. Amos, “AMOS, A Portable Package for Bessel Functions of a Complex Argument and Nonnegative Order”, <http://netlib.org/amos/>
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [2] Jahnke, E. and Emde, F. “Tables of Functions with Formulae and Curves” (4th ed.), Dover, 1945
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996, chapter 5. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996, chapter 5. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996, chapter 5. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996, chapter 5. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html

- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996, chapter 5. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996, chapter 5. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996, chapter 5. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996, chapter 5. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996, chapter 5. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996, chapter 5. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [2] NIST Digital Library of Mathematical Functions. <https://dlmf.nist.gov/10.6.E7>
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996, chapter 5. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [2] NIST Digital Library of Mathematical Functions. <https://dlmf.nist.gov/10.6.E7>
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996, chapter 6. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [2] NIST Digital Library of Mathematical Functions. <https://dlmf.nist.gov/10.29.E5>
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996, chapter 6. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [2] NIST Digital Library of Mathematical Functions. <https://dlmf.nist.gov/10.29.E5>
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996, chapter 5. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [2] NIST Digital Library of Mathematical Functions. <https://dlmf.nist.gov/10.6.E7>
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996, chapter 5. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [2] NIST Digital Library of Mathematical Functions. <https://dlmf.nist.gov/10.6.E7>

- [1] <https://dlmf.nist.gov/10.47.E3>
- [2] <https://dlmf.nist.gov/10.51.E1>
- [3] <https://dlmf.nist.gov/10.51.E2>
- [1] <https://dlmf.nist.gov/10.47.E4>
- [2] <https://dlmf.nist.gov/10.51.E1>
- [3] <https://dlmf.nist.gov/10.51.E2>
- [1] <https://dlmf.nist.gov/10.47.E7>
- [2] <https://dlmf.nist.gov/10.51.E5>
- [1] <https://dlmf.nist.gov/10.47.E9>
- [2] <https://dlmf.nist.gov/10.51.E5>
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [2] NIST Digital Library of Mathematical Functions. <https://dlmf.nist.gov/10.51.E1>
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [2] NIST Digital Library of Mathematical Functions. <https://dlmf.nist.gov/10.51.E1>
- [1] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/11>
- [1] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/11>
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [2] Barry Brown, James Lovato, and Kathy Russell, CDFLIB: Library of Fortran Routines for Cumulative Distribution Functions, Inverses, and Other Parameters.
- [1] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [2] Barry Brown, James Lovato, and Kathy Russell, CDFLIB: Library of Fortran Routines for Cumulative Distribution Functions, Inverses, and Other Parameters.
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Barry Brown, James Lovato, and Kathy Russell, CDFLIB: Library of Fortran Routines for Cumulative Distribution Functions, Inverses, and Other Parameters.

- [2] DiDinato, A. R. and Morris, A. H., Algorithm 708: Significant Digit Computation of the Incomplete Beta Function Ratios. *ACM Trans. Math. Softw.* 18 (1993), 360-373.
- [1] Barry Brown, James Lovato, and Kathy Russell, CDFLIB: Library of Fortran Routines for Cumulative Distribution Functions, Inverses, and Other Parameters.
- [2] DiDinato, A. R. and Morris, A. H., Algorithm 708: Significant Digit Computation of the Incomplete Beta Function Ratios. *ACM Trans. Math. Softw.* 18 (1993), 360-373.
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Barry Brown, James Lovato, and Kathy Russell, CDFLIB: Library of Fortran Routines for Cumulative Distribution Functions, Inverses, and Other Parameters.
- [2] DiDinato, A. R. and Morris, A. H., Computation of the incomplete gamma function ratios and their inverse. *ACM Trans. Math. Softw.* 12 (1986), 377-393.
- [1] Barry Brown, James Lovato, and Kathy Russell, CDFLIB: Library of Fortran Routines for Cumulative Distribution Functions, Inverses, and Other Parameters.
- [2] DiDinato, A. R. and Morris, A. H., Computation of the incomplete gamma function ratios and their inverse. *ACM Trans. Math. Softw.* 12 (1986), 377-393.
- [1] Barry Brown, James Lovato, and Kathy Russell, CDFLIB: Library of Fortran Routines for Cumulative Distribution Functions, Inverses, and Other Parameters.
- [2] DiDinato, A. R. and Morris, A. H., Computation of the incomplete gamma function ratios and their inverse. *ACM Trans. Math. Softw.* 12 (1986), 377-393.
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [1] Barry Brown, James Lovato, and Kathy Russell, CDFLIB: Library of Fortran Routines for Cumulative Distribution Functions, Inverses, and Other Parameters.
- [2] Milton Abramowitz and Irene A. Stegun, eds. *Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables*. New York: Dover, 1972.
- [1] Barry Brown, James Lovato, and Kathy Russell, CDFLIB: Library of Fortran Routines for Cumulative Distribution Functions, Inverses, and Other Parameters.
- [2] Milton Abramowitz and Irene A. Stegun, eds. *Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables*. New York: Dover, 1972.
- [1] Barry Brown, James Lovato, and Kathy Russell, CDFLIB: Library of Fortran Routines for Cumulative Distribution Functions, Inverses, and Other Parameters.
- [2] Milton Abramowitz and Irene A. Stegun, eds. *Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables*. New York: Dover, 1972.
- [1] https://en.wikipedia.org/wiki/Poisson_distribution
- [1] Chi-Square distribution, <https://www.itl.nist.gov/div898/handbook/eda/section3/eda3666.htm>
- [1] Chi-Square distribution, <https://www.itl.nist.gov/div898/handbook/eda/section3/eda3666.htm>

- [1] Chi-Square distribution, <https://www.itl.nist.gov/div898/handbook/eda/section3/eda3666.htm>
- [1] Chi-Square distribution, <https://www.itl.nist.gov/div898/handbook/eda/section3/eda3666.htm>
- [1] M. Patefield and D. Tandy, “Fast and accurate calculation of Owen’s T Function”, *Statistical Software* vol. 5, pp. 1-25, 2000.
- [1] Grant, Boyd, and Ye, “CVX: Matlab Software for Disciplined Convex Programming”, <http://cvxr.com/cvx/>
- [2] Kullback-Leibler divergence, https://en.wikipedia.org/wiki/Kullback%E2%80%93Leibler_divergence
- [1] Grant, Boyd, and Ye, “CVX: Matlab Software for Disciplined Convex Programming”, <http://cvxr.com/cvx/>
- [dlmf] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/5.2#E1>
- [dlmf] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/5>
- [hare1997] D.E.G. Hare, *Computing the Principal Branch of log-Gamma*, *Journal of Algorithms*, Volume 25, Issue 2, November 1997, pages 221-236.
- [dlmf] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/5.2#E1>
- [dlmf] NIST Digital Library of Mathematical functions <https://dlmf.nist.gov/8.2#E4>
- [boost] Maddock et. al., “Incomplete Gamma Functions”, https://www.boost.org/doc/libs/1_61_0/libs/math/doc/html/math_toolkit/sf_gamma/igamma.html
- [dlmf] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/8.2#E4>
- [dlmf] NIST Digital Library of Mathematical functions <https://dlmf.nist.gov/8.2#E4>
- [boost] Maddock et. al., “Incomplete Gamma Functions”, https://www.boost.org/doc/libs/1_61_0/libs/math/doc/html/math_toolkit/sf_gamma/igamma.html
- [dlmf] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/8.2#E4>
- [1] NIST Digital Library of Mathematical Functions, Eq. 5.12.1. <https://dlmf.nist.gov/5.12>
- [1] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/8.17>
- [1] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/8.17>
- [1] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/5>
- [2] Fredrik Johansson and others. “mpmath: a Python library for arbitrary-precision floating-point arithmetic” (Version 0.19) <http://mpmath.org/>
- [dlmf] Nist, Digital Library of Mathematical functions, <https://dlmf.nist.gov/5.2#i>
- [dlmf] NIST, Digital Library of Mathematical Functions, <https://dlmf.nist.gov/5.15>
- [1] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/5>
- [2] Fredrik Johansson and others. “mpmath: a Python library for arbitrary-precision floating-point arithmetic” (Version 0.19) <http://mpmath.org/>
- [dlmf] Nist, Digital Library of Mathematical Functions <https://dlmf.nist.gov/5.2#iii>
- [1] https://en.wikipedia.org/wiki/Error_function
- [2] Milton Abramowitz and Irene A. Stegun, eds. *Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables*. New York: Dover, 1972. http://www.math.sfu.ca/~cbm/aands/page_297.htm
- [3] Steven G. Johnson, Faddeeva W function implementation. <http://ab-initio.mit.edu/Faddeeva>
- [1] Steven G. Johnson, Faddeeva W function implementation. <http://ab-initio.mit.edu/Faddeeva>
- [1] Steven G. Johnson, Faddeeva W function implementation. <http://ab-initio.mit.edu/Faddeeva>

- [1] Steven G. Johnson, Faddeeva W function implementation. <http://ab-initio.mit.edu/Faddeeva>
- [1] Steven G. Johnson, Faddeeva W function implementation. <http://ab-initio.mit.edu/Faddeeva>
- [1] Steven G. Johnson, Faddeeva W function implementation. <http://ab-initio.mit.edu/Faddeeva>
- [dlmf] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/7.2#iii>
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] https://en.wikipedia.org/wiki/Voigt_profile
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Jin, "Computation of Special Functions", John Wiley and Sons, Inc, 1996.
- [1] Digital Library of Mathematical Functions, 14.30. <https://dlmf.nist.gov/14.30>
- [2] https://en.wikipedia.org/wiki/Spherical_harmonics#Condon.E2.80.93Shortley_phase
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [2] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/14.21>
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [2] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/14.3>
- [1] Zhang, Shanjie and Jin, Jianming. "Computation of Special Functions", John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Digital Library of Mathematical Functions 29.12 <https://dlmf.nist.gov/29.12>
- [2] Bardhan and Knepley, "Computational science and re-discovery: open-source implementations of ellipsoidal harmonics for problems in potential theory", *Comput. Sci. Disc.* 5, 014006 (2012) DOI:10.1088/1749-4699/5/1/014006.
- [3] David J. and Dechambre P, "Computation of Ellipsoidal Gravity Field Harmonics for small solar system bodies" pp. 30-36, 2000
- [4] George Dassios, "Ellipsoidal Harmonics: Theory and Applications" pp. 418, 2012
- [AS] Milton Abramowitz and Irene A. Stegun, eds. *Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables*. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. *Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables*. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. *Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables*. New York: Dover, 1972.

- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [townsend.trogdon.olver-2014] Townsend, A. and Trogdon, T. and Olver, S. (2014) *Fast computation of Gauss quadrature nodes and weights on the whole real line*. [arXiv:1410.5286](https://arxiv.org/abs/1410.5286).

- [townsend.trogdon.olver-2015] Townsend, A. and Trogdon, T. and Olver, S. (2015) *Fast computation of Gauss quadrature nodes and weights on the whole real line*. IMA Journal of Numerical Analysis DOI:10.1093/imanum/drv002.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [AS] Milton Abramowitz and Irene A. Stegun, eds. Handbook of Mathematical Functions with Formulas, Graphs, and Mathematical Tables. New York: Dover, 1972.
- [1] Abramowitz and Stegun, “Handbook of Mathematical Functions” Section 22. National Bureau of Standards, 1972.
- [1] Abramowitz and Stegun, “Handbook of Mathematical Functions” Section 22. National Bureau of Standards, 1972.
- [1] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/15.2>
- [2] S. Zhang and J.M. Jin, “Computation of Special Functions”, Wiley 1996
- [3] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [dlmf] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/13.2#E2>
- [dlmf] NIST Digital Library of Mathematics Functions <https://dlmf.nist.gov/13.2#E6>
- [1] Wolfram MathWorld, “Confluent Hypergeometric Limit Function”, <http://mathworld.wolfram.com/ConfluentHypergeometricLimitFunction.html>
- [1] Digital Library of Mathematical Functions, 14.30. <https://dlmf.nist.gov/14.30>
- [2] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996, chapter 13. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996, chapter 13. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996, chapter 13. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [2] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/28.4#i>
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html

- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [dlmf] NIST, Digital Library of Mathematical Functions, <https://dlmf.nist.gov/10.61>
- [dlmf] NIST, Digital Library of Mathematical Functions, <https://dlmf.nist.gov/10.61>
- [dlmf] NIST, Digital Library of Mathematical Functions, <https://dlmf.nist.gov/10#PT5>
- [dlmf] NIST, Digital Library of Mathematical Functions, <https://dlmf.nist.gov/10#PT5>
- [dlmf] NIST, Digital Library of Mathematical Functions, <https://dlmf.nist.gov/10.61>
- [dlmf] NIST, Digital Library of Mathematical Functions, <https://dlmf.nist.gov/10.61>
- [dlmf] NIST, Digital Library of Mathematical Functions, <https://dlmf.nist.gov/10#PT5>
- [dlmf] NIST, Digital Library of Mathematical Functions, <https://dlmf.nist.gov/10#PT5>
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] https://en.wikipedia.org/wiki/Lambert_W_function
- [2] Corless et al, “On the Lambert W function”, *Adv. Comp. Math.* 5 (1996) 329-359. <https://cs.uwaterloo.ca/research/tr/1993/03/W.pdf>
- [1] Lawrence, Corless, and Jeffrey, “Algorithm 917: Complex Double-Precision Evaluation of the Wright ω Function.” *ACM Transactions on Mathematical Software*, 2012. DOI:10.1145/2168773.2168779.
- [1] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [1] Sequence A122045, The On-Line Encyclopedia of Integer Sequences, <https://oeis.org/A122045>
- [2] Zhang, Shanjie and Jin, Jianming. “Computation of Special Functions”, John Wiley and Sons, 1996. https://people.sc.fsu.edu/~jburkardt/f_src/special_functions/special_functions.html
- [dlmf] Digital Library of Mathematical Functions, 8.19.2 <https://dlmf.nist.gov/8.19#E2>

- [1] Digital Library of Mathematical Functions, 6.2.1 <https://dlmf.nist.gov/6.2#E1>
- [1] Digital Library of Mathematical Functions, 6.2.5 <https://dlmf.nist.gov/6.2#E5>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [2] Fredrik Johansson and others. “mpmath: a Python library for arbitrary-precision floating-point arithmetic” (Version 0.19) <http://mpmath.org/>
- [1] Cephes Mathematical Functions Library, <http://www.netlib.org/cephes/>
- [2] Fredrik Johansson and others. “mpmath: a Python library for arbitrary-precision floating-point arithmetic” (Version 0.19) <http://mpmath.org/>
- [dlmf] NIST, Digital Library of Mathematical Functions, <https://dlmf.nist.gov/25.11#i>
- [dlmf] NIST Digital Library of Mathematical Functions <https://dlmf.nist.gov/25>
- [1] Weisstein, Eric W. “Sinc Function.” From MathWorld—A Wolfram Web Resource. <http://mathworld.wolfram.com/SincFunction.html>
- [2] Wikipedia, “Sinc function”, https://en.wikipedia.org/wiki/Sinc_function
- [1] Johnson, Kotz, and Balakrishnan, “Continuous Univariate Distributions, Volume 1”, Second Edition, John Wiley and Sons, p. 173 (1994).
- [2] Anthony A. Salvia, “Reliability applications of the Alpha Distribution”, IEEE Transactions on Reliability, Vol. R-34, No. 3, pp. 251-252 (1985).
- [1] “ARGUS distribution”, https://en.wikipedia.org/wiki/ARGUS_distribution
- [1] Burr, I. W. “Cumulative frequency functions”, Annals of Mathematical Statistics, 13(2), pp 215-232 (1942).
- [2] https://en.wikipedia.org/wiki/Dagum_distribution
- [3] Kleiber, Christian. “A guide to the Dagum distributions.” Modeling Income Distributions and Lorenz Curves pp 97-117 (2008).
- [1] Burr, I. W. “Cumulative frequency functions”, Annals of Mathematical Statistics, 13(2), pp 215-232 (1942).
- [2] <https://www.itl.nist.gov/div898/software/dataplot/refman2/auxillar/b12pdf.htm>
- [3] “Burr distribution”, https://en.wikipedia.org/wiki/Burr_distribution
- [1] “Crystal Ball Function”, https://en.wikipedia.org/wiki/Crystal_Ball_function
- [1] “Birnbaum-Saunders distribution”, https://en.wikipedia.org/wiki/Birnbaum-Saunders_distribution
- [1] “Generalized normal distribution, Version 1”, https://en.wikipedia.org/wiki/Generalized_normal_distribution#Version_1
- [1] Armero, C., and M. J. Bayarri. “Prior Assessments for Prediction in Queues.” *Journal of the Royal Statistical Society. Series D (The Statistician)* 43, no. 1 (1994): 139-53. doi:10.2307/2348939
- [1] E.W. Stacy, “A Generalization of the Gamma Distribution”, Annals of Mathematical Statistics, Vol 33(3), pp. 1187–1192.
- [1] O. Barndorff-Nielsen, P. Blaesild, C. Halgreen, “First hitting time models for the generalized inverse gaussian distribution”, Stochastic Processes and their Applications 7, pp. 49–54, 1978.
- [2] W. Hoermann and J. Leydold, “Generating generalized inverse Gaussian random variates”, Statistics and Computing, 24(4), p. 547–557, 2014.
- [1] “Generalized normal distribution, Version 1”, https://en.wikipedia.org/wiki/Generalized_normal_distribution#Version_1

- [1] Birnbaum, Z. W. and Tingey, F.H. “One-sided confidence contours for probability distribution functions”, *The Annals of Mathematical Statistics*, 22(4), pp 592-596 (1951).
- [1] Simard, R., L’Ecuyer, P. “Computing the Two-Sided Kolmogorov-Smirnov Distribution”, *Journal of Statistical Software*, Vol 39, 11, 1-18 (2011).
- [1] Feller, W. “On the Kolmogorov-Smirnov Limit Theorems for Empirical Distributions”, *Ann. Math. Statist.* Vol 19, 177-189 (1948).
- [1] “Asymmetric Laplace distribution”, Wikipedia https://en.wikipedia.org/wiki/Asymmetric_Laplace_distribution
- [2] Kozubowski TJ and Podgórski K. A Multivariate and Asymmetric Generalization of Laplace Distribution, *Computational Statistics* 15, 531–540 (2000). DOI:10.1007/PL00022717
- [MC] McCulloch, J., 1986. Simple consistent estimators of stable distribution parameters. *Communications in Statistics - Simulation and Computation* 15, 11091136.
- [MS] Mittnik, S.T. Rachev, T. Doganoglu, D. Chenyao, 1999. Maximum likelihood estimation of stable Paretian models, *Mathematical and Computer Modelling*, Volume 29, Issue 10, 1999, Pages 275-293.
- [BS] Borak, S., Hardle, W., Rafal, W. 2005. Stable distributions, *Economic Risk*.
- [1] <http://mathworld.wolfram.com/MaxwellDistribution.html>
- [1] Mielke, P.W., 1973 “Another Family of Distributions for Describing and Analyzing Precipitation Data.” *J. Appl. Meteor.*, 12, 275-280
- [2] Dagum, C., 1977 “A new model for personal income distribution.” *Economie Appliquee*, 33, 327-367.
- [3] Burr, I. W. “Cumulative frequency functions”, *Annals of Mathematical Statistics*, 13(2), pp 215-232 (1942).
- [1] J.E. Moyal, “XXX. Theory of ionization fluctuations”, *The London, Edinburgh, and Dublin Philosophical Magazine and Journal of Science*, vol 46, 263-280, (1955). DOI:10.1080/14786440308521076 (gated)
- [2] G. Cordeiro et al., “The beta Moyal: a useful skew distribution”, *International Journal of Research and Reviews in Applied Sciences*, vol 10, 171-192, (2012). http://www.arpapress.com/Volumes/Vol10Issue2/IJRRAS_10_2_02.pdf
- [3] C. Walck, “Handbook on Statistical Distributions for Experimentalists; International Report SUF-PFY/96-01”, Chapter 26, University of Stockholm: Stockholm, Sweden, (2007). <http://www.stat.rice.edu/~dobelman/textfiles/DistributionsHandbook.pdf>
- [1] “Wigner semicircle distribution”, https://en.wikipedia.org/wiki/Wigner_semicircle_distribution
- [1] A. Azzalini and A. Capitanio (1999). Statistical applications of the multivariate skew-normal distribution. *J. Roy. Statist. Soc.*, B 61, 579-602. arXiv:0911.2093
- [1] Kacker, R.N. and Lawrence, J.F. (2007). Trapezoidal and triangular distributions for Type B evaluation of standard uncertainty. *Metrologia* 44, 117-127. DOI:10.1088/0026-1394/44/2/003
- [1] M.L. Eaton, “Multivariate Statistics: A Vector Space Approach”, Wiley, 1983.
- [2] W.B. Smith and R.R. Hocking, “Algorithm AS 53: Wishart Variate Generator”, *Applied Statistics*, vol. 21, pp. 341-345, 1972.
- [1] M.L. Eaton, “Multivariate Statistics: A Vector Space Approach”, Wiley, 1983.
- [2] M.C. Jones, “Generating Inverse Wishart Matrices”, *Communications in Statistics - Simulation and Computation*, vol. 14.2, pp.511-514, 1985.
- [1] F. Mezzadri, “How to generate random matrices from the classical compact groups”, arXiv:math-ph/0609050v2.

- [1] F. Mezzadri, “How to generate random matrices from the classical compact groups”, [arXiv:math-ph/0609050v2](https://arxiv.org/abs/math-ph/0609050v2).
- [1] Davies, Philip I; Higham, Nicholas J; “Numerically stable generation of correlation matrices and their factors”, BIT 2000, Vol. 40, No. 4, pp. 640 651
- [1] The Multivariate Hypergeometric Distribution, <http://www.randomservices.org/random/urn/MultiHypergeometric.html>
- [2] Thomas J. Sargent and John Stachurski, 2020, Multivariate Hypergeometric Distribution https://python.quantecon.org/_downloads/pdf/multi_hyper.pdf
- [1] https://en.wikipedia.org/wiki/Beta-binomial_distribution
- [1] Negative Hypergeometric Distribution on Wikipedia https://en.wikipedia.org/wiki/Negative_hypergeometric_distribution
- [2] Negative Hypergeometric Distribution from <http://www.math.wm.edu/~leemis/chart/UDR/PDFs/Negativehypergeometric.pdf>
- [1] Devroye, Luc. “Non-uniform Random Variate Generation”, (1986) Springer, New York.
- [2] https://en.wikipedia.org/wiki/Yule-Simon_distribution
- [1] Zwillinger, D. and Kokoska, S. (2000). CRC Standard Probability and Statistics Tables and Formulae. Chapman & Hall: New York. 2000.
- [1] <https://eli.thegreenplace.net/2009/03/21/efficient-integer-exponentiation-algorithms>
- [1] Zwillinger, D. and Kokoska, S. (2000). CRC Standard Probability and Statistics Tables and Formulae. Chapman & Hall: New York. 2000. Section 2.2.24.1
- [1] Zwillinger, D. and Kokoska, S. (2000). CRC Standard Probability and Statistics Tables and Formulae. Chapman & Hall: New York. 2000.
- [1] “Interquartile range” https://en.wikipedia.org/wiki/Interquartile_range
- [2] “Robust measures of scale” https://en.wikipedia.org/wiki/Robust_measures_of_scale
- [3] “Quantile” <https://en.wikipedia.org/wiki/Quantile>
- [1] “Median absolute deviation”, https://en.wikipedia.org/wiki/Median_absolute_deviation
- [2] “Robust measures of scale”, https://en.wikipedia.org/wiki/Robust_measures_of_scale
- [1] “Median absolute deviation”, https://en.wikipedia.org/wiki/Median_absolute_deviation
- [2] “Robust measures of scale”, https://en.wikipedia.org/wiki/Robust_measures_of_scale
- [1] R. Lowry, “Concepts and Applications of Inferential Statistics”, Chapter 14, 2014, <http://vassarstats.net/textbook/>
- [2] G.W. Heiman, “Understanding research methods and statistics: An integrated introduction for psychology”, Houghton, Mifflin and Company, 2001.
- [3] G.H. McDonald, “Handbook of Biological Statistics”, One-way ANOVA. <http://www.biostathandbook.com/onewayanova.html>
- [1] “Pearson correlation coefficient”, Wikipedia, https://en.wikipedia.org/wiki/Pearson_correlation_coefficient
- [2] Student, “Probable error of a correlation coefficient”, Biometrika, Volume 6, Issue 2-3, 1 September 1908, pp. 302-310.
- [3] C. J. Kowalski, “On the Effects of Non-Normality on the Distribution of the Sample Product-Moment Correlation Coefficient” Journal of the Royal Statistical Society. Series C (Applied Statistics), Vol. 21, No. 1 (1972), pp. 1-12.

- [1] Zwillinger, D. and Kokoska, S. (2000). CRC Standard Probability and Statistics Tables and Formulae. Chapman & Hall: New York. 2000. Section 14.7
- [1] J. Lev, “The Point Biserial Coefficient of Correlation”, *Ann. Math. Statist.*, Vol. 20, no.1, pp. 125-126, 1949.
- [2] R.F. Tate, “Correlation Between a Discrete and a Continuous Variable. Point-Biserial Correlation.”, *Ann. Math. Statist.*, Vol. 25, np. 3, pp. 603-607, 1954.
- [3] D. Kornbrot “Point Biserial Correlation”, In *Wiley StatsRef: Statistics Reference Online* (eds N. Balakrishnan, et al.), 2014. DOI:10.1002/9781118445112.stat06227
- [1] Maurice G. Kendall, “A New Measure of Rank Correlation”, *Biometrika* Vol. 30, No. 1/2, pp. 81-93, 1938.
- [2] Maurice G. Kendall, “The treatment of ties in ranking problems”, *Biometrika* Vol. 33, No. 3, pp. 239-251. 1945.
- [3] Gottfried E. Noether, “Elements of Nonparametric Statistics”, John Wiley & Sons, 1967.
- [4] Peter M. Fenwick, “A new data structure for cumulative frequency tables”, *Software: Practice and Experience*, Vol. 24, No. 3, pp. 327-336, 1994.
- [5] Maurice G. Kendall, “Rank Correlation Methods” (4th Edition), Charles Griffin & Co., 1970.
- [1] Sebastiano Vigna, “A weighted correlation index for rankings with ties”, *Proceedings of the 24th international conference on World Wide Web*, pp. 1166-1176, ACM, 2015.
- [2] W.R. Knight, “A Computer Method for Calculating Kendall’s Tau with Ungrouped Data”, *Journal of the American Statistical Association*, Vol. 61, No. 314, Part 1, pp. 436-439, 1966.
- [3] Grace S. Shieh. “A weighted Kendall’s tau statistic”, *Statistics & Probability Letters*, Vol. 39, No. 1, pp. 17-24, 1998.
- [1] A. Siegel, “Robust Regression Using Repeated Medians”, *Biometrika*, Vol. 69, pp. 242-244, 1982.
- [2] A. Stein and M. Werman, “Finding the repeated median regression line”, *Proceedings of the Third Annual ACM-SIAM Symposium on Discrete Algorithms*, pp. 409-413, 1992.
- [1] P.K. Sen, “Estimates of the regression coefficient based on Kendall’s tau”, *J. Am. Stat. Assoc.*, Vol. 63, pp. 1379-1389, 1968.
- [2] H. Theil, “A rank-invariant method of linear and polynomial regression analysis I, II and III”, *Nederl. Akad. Wetensch., Proc.* 53:, pp. 386-392, pp. 521-525, pp. 1397-1412, 1950.
- [3] W.L. Conover, “Practical nonparametric statistics”, 2nd ed., John Wiley and Sons, New York, pp. 493.
- [1] Vogelstein, J. T., Bridgeford, E. W., Wang, Q., Priebe, C. E., Maggioni, M., & Shen, C. (2019). Discovering and deciphering relationships across disparate data modalities. *ELife*.
- [2] Panda, S., Palaniappan, S., Xiong, J., Swaminathan, A., Ramachandran, S., Bridgeford, E. W., ... Vogelstein, J. T. (2019). mgcpy: A Comprehensive High Dimensional Independence Testing Python Package. [arXiv:1907.02088](https://arxiv.org/abs/1907.02088)
- [3] Shen, C., Priebe, C.E., & Vogelstein, J. T. (2019). From distance correlation to multiscale graph correlation. *Journal of the American Statistical Association*.
- [4] Shen, C. & Vogelstein, J. T. (2018). The Exact Equivalence of Distance and Kernel Methods for Hypothesis Testing. [arXiv:1806.05514](https://arxiv.org/abs/1806.05514)
- [1] https://en.wikipedia.org/wiki/T-test#Independent_two-sample_t-test
- [2] https://en.wikipedia.org/wiki/Welch%27s_t-test
- [1] https://en.wikipedia.org/wiki/T-test#Independent_two-sample_t-test
- [2] https://en.wikipedia.org/wiki/Welch%27s_t-test

- [1] Lowry, Richard. "Concepts and Applications of Inferential Statistics". Chapter 8. <https://web.archive.org/web/20171022032306/http://vassarstats.net:80/textbook/ch8pt1.html>
- [2] "Chi-squared test", https://en.wikipedia.org/wiki/Chi-squared_test
- [1] https://en.wikipedia.org/wiki/Cramér-von_Mises_criterion
- [2] Csorgo, S. and Faraway, J. (1996). The Exact and Asymptotic Distribution of Cramér-von Mises Statistics. *Journal of the Royal Statistical Society*, pp. 221-234.
- [1] Lowry, Richard. "Concepts and Applications of Inferential Statistics". Chapter 8. <https://web.archive.org/web/20171015035606/http://faculty.vassar.edu/lowry/ch8pt1.html>
- [2] "Chi-squared test", https://en.wikipedia.org/wiki/Chi-squared_test
- [3] "G-test", <https://en.wikipedia.org/wiki/G-test>
- [4] Sokal, R. R. and Rohlf, F. J. "Biometry: the principles and practice of statistics in biological research", New York: Freeman (1981)
- [5] Cressie, N. and Read, T. R. C., "Multinomial Goodness-of-Fit Tests", *J. Royal Stat. Soc. Series B*, Vol. 46, No. 3 (1984), pp. 440-464.
- [1] Hodges, J.L. Jr., "The Significance Probability of the Smirnov Two-Sample Test," *Arkiv fiur Matematik*, 3, No. 43 (1958), 469-86.
- [1] T. W. Epps and K. J. Singleton, "An omnibus test for the two-sample problem using the empirical characteristic function", *Journal of Statistical Computation and Simulation* 26, p. 177–203, 1986.
- [2] S. J. Goerg and J. Kaiser, "Nonparametric testing of distributions - the Epps-Singleton two-sample test using the empirical characteristic function", *The Stata Journal* 9(3), p. 454–465, 2009.
- [1] https://en.wikipedia.org/wiki/Mann-Whitney_U_test
- [2] H.B. Mann and D.R. Whitney, "On a Test of Whether one of Two Random Variables is Stochastically Larger than the Other," *The Annals of Mathematical Statistics*, vol. 18, no. 1, pp. 50-60, 1947.
- [1] Siegel, S. (1956) *Nonparametric Statistics for the Behavioral Sciences*. New York: McGraw-Hill.
- [1] "Ranking", <https://en.wikipedia.org/wiki/Ranking>
- [1] https://en.wikipedia.org/wiki/Wilcoxon_rank-sum_test
- [1] https://en.wikipedia.org/wiki/Wilcoxon_signed-rank_test
- [2] Conover, W.J., *Practical Nonparametric Statistics*, 1971.
- [3] Pratt, J.W., Remarks on Zeros and Ties in the Wilcoxon Signed Rank Procedures, *Journal of the American Statistical Association*, Vol. 54, 1959, pp. 655-667. DOI:10.1080/01621459.1959.10501526
- [4] Wilcoxon, F., Individual Comparisons by Ranking Methods, *Biometrics Bulletin*, Vol. 1, 1945, pp. 80-83. DOI:10.2307/3001968
- [5] Cureton, E.E., The Normal Approximation to the Signed-Rank Sampling Distribution When Zero Differences are Present, *Journal of the American Statistical Association*, Vol. 62, 1967, pp. 1068-1069. DOI:10.1080/01621459.1967.10500917
- [1] W. H. Kruskal & W. W. Wallis, "Use of Ranks in One-Criterion Variance Analysis", *Journal of the American Statistical Association*, Vol. 47, Issue 260, pp. 583-621, 1952.
- [2] https://en.wikipedia.org/wiki/Kruskal-Wallis_one-way_analysis_of_variance
- [1] https://en.wikipedia.org/wiki/Friedman_test
- [1] Brunner, E. and Munzel, U. "The nonparametric Benhrens-Fisher problem: Asymptotic theory and a small-sample approximation". *Biometrical Journal*. Vol. 42(2000): 17-25.

- [2] Neubert, K. and Brunner, E. "A studentized permutation test for the non-parametric Behrens-Fisher problem". *Computational Statistics and Data Analysis*. Vol. 51(2007): 5192-5204.
- [1] https://en.wikipedia.org/wiki/Fisher%27s_method
- [2] https://en.wikipedia.org/wiki/Fisher%27s_method#Relation_to_Stouffer.27s_Z-score_method
- [3] George, E. O., and G. S. Mudholkar. "On the convolution of logistic random variables." *Metrika* 30.1 (1983): 1-13.
- [4] Heard, N. and Rubin-Delanchey, P. "Choosing between methods of combining p-values." *Biometrika* 105.1 (2018): 239-246.
- [5] Whitlock, M. C. "Combining probability from independent tests: the weighted Z-method is superior to Fisher's approach." *Journal of Evolutionary Biology* 18, no. 5 (2005): 1368-1373.
- [6] Zaykin, Dmitri V. "Optimally weighted Z-test is a powerful method for combining probabilities in meta-analysis." *Journal of Evolutionary Biology* 24, no. 8 (2011): 1836-1841.
- [7] https://en.wikipedia.org/wiki/Extensions_of_Fisher%27s_method
- [1] Jarque, C. and Bera, A. (1980) "Efficient tests for normality, homoscedasticity and serial independence of regression residuals", *6 Econometric Letters* 255-259.
- [1] Ansari, A. R. and Bradley, R. A. (1960) Rank-sum tests for dispersions, *Annals of Mathematical Statistics*, 31, 1174-1189.
- [2] Sprent, Peter and N.C. Smeeton. *Applied nonparametric statistical methods*. 3rd ed. Chapman and Hall/CRC. 2001. Section 5.8.2.
- [1] <https://www.itl.nist.gov/div898/handbook/eda/section3/eda357.htm>
- [2] Snedecor, George W. and Cochran, William G. (1989), *Statistical Methods*, Eighth Edition, Iowa State University Press.
- [3] Park, C. and Lindsay, B. G. (1999). *Robust Scale Estimation and Hypothesis Testing based on Quadratic Inference Function*. Technical Report #99-03, Center for Likelihood Studies, Pennsylvania State University.
- [4] Bartlett, M. S. (1937). *Properties of Sufficiency and Statistical Tests*. Proceedings of the Royal Society of London. Series A, Mathematical and Physical Sciences, Vol. 160, No.901, pp. 268-282.
- [1] <https://www.itl.nist.gov/div898/handbook/eda/section3/eda35a.htm>
- [2] Levene, H. (1960). In *Contributions to Probability and Statistics: Essays in Honor of Harold Hotelling*, I. Olkin et al. eds., Stanford University Press, pp. 278-292.
- [3] Brown, M. B. and Forsythe, A. B. (1974), *Journal of the American Statistical Association*, 69, 364-367
- [1] <https://www.itl.nist.gov/div898/handbook/prc/section2/prc213.htm>
- [2] Shapiro, S. S. & Wilk, M.B (1965). An analysis of variance test for normality (complete samples), *Biometrika*, Vol. 52, pp. 591-611.
- [3] Razali, N. M. & Wah, Y. B. (2011) Power comparisons of Shapiro-Wilk, Kolmogorov-Smirnov, Lilliefors and Anderson-Darling tests, *Journal of Statistical Modeling and Analytics*, Vol. 2, pp. 21-33.
- [4] ALGORITHM AS R94 APPL. STATIST. (1995) VOL. 44, NO. 4.
- [1] <https://www.itl.nist.gov/div898/handbook/prc/section2/prc213.htm>
- [2] Stephens, M. A. (1974). EDF Statistics for Goodness of Fit and Some Comparisons, *Journal of the American Statistical Association*, Vol. 69, pp. 730-737.
- [3] Stephens, M. A. (1976). Asymptotic Results for Goodness-of-Fit Statistics with Unknown Parameters, *Annals of Statistics*, Vol. 4, pp. 357-369.

- [4] Stephens, M. A. (1977). Goodness of Fit for the Extreme Value Distribution, *Biometrika*, Vol. 64, pp. 583-588.
- [5] Stephens, M. A. (1977). Goodness of Fit with Special Reference to Tests for Exponentiality , Technical Report No. 262, Department of Statistics, Stanford University, Stanford, CA.
- [6] Stephens, M. A. (1979). Tests of Fit for the Logistic Distribution Based on the Empirical Distribution Function, *Biometrika*, Vol. 66, pp. 591-595.
- [1] Scholz, F. W and Stephens, M. A. (1987), K-Sample Anderson-Darling Tests, *Journal of the American Statistical Association*, Vol. 82, pp. 918-924.
- [1] https://en.wikipedia.org/wiki/Binomial_test
- [1] Park, C. and Lindsay, B. G. (1999). Robust Scale Estimation and Hypothesis Testing based on Quadratic Inference Function. Technical Report #99-03, Center for Likelihood Studies, Pennsylvania State University. <https://cecas.clemson.edu/~cspark/cv/paper/qif/draftqif2.pdf>
- [2] Fligner, M.A. and Killeen, T.J. (1976). Distribution-free two-sample tests for scale. 'Journal of the American Statistical Association.' 71(353), 210-213.
- [3] Park, C. and Lindsay, B. G. (1999). Robust Scale Estimation and Hypothesis Testing based on Quadratic Inference Function. Technical Report #99-03, Center for Likelihood Studies, Pennsylvania State University.
- [4] Conover, W. J., Johnson, M. E. and Johnson M. M. (1981). A comparative study of tests for homogeneity of variances, with applications to the outer continental shelf bidding data. *Technometrics*, 23(4), 351-361.
- [1] Mood, A. M., Introduction to the Theory of Statistics. McGraw-Hill (1950), pp. 394-399.
- [2] Zar, J. H., Biostatistical Analysis, 5th ed. Prentice Hall (2010). See Sections 8.12 and 10.15.
- [1] R. B. D'Agostino, A. J. Belanger and R. B. D'Agostino Jr., "A suggestion for using powerful and informative tests of normality", *American Statistician* 44, pp. 316-321, 1990.
- [1] see e.g. F. J. Anscombe, W. J. Glynn, "Distribution of the kurtosis statistic b_2 for normal samples", *Biometrika*, vol. 70, pp. 227-234, 1983.
- [1] D'Agostino, R. B. (1971), "An omnibus test of normality for moderate and large sample size", *Biometrika*, 58, 341-348
- [2] D'Agostino, R. and Pearson, E. S. (1973), "Tests for departure from normality", *Biometrika*, 60, 613-622
- [1] S. E. Maxwell and H. D. Delaney, "Designing Experiments and Analyzing Data: A Model Comparison Perspective", Wadsworth, 1990.
- [1] "Wasserstein metric", https://en.wikipedia.org/wiki/Wasserstein_metric
- [2] Ramdas, Garcia, Cuturi "On Wasserstein Two Sample Testing and Related Families of Nonparametric Tests" (2015). [arXiv:1509.02237](https://arxiv.org/abs/1509.02237).
- [1] "Energy distance", https://en.wikipedia.org/wiki/Energy_distance
- [2] Szekely "E-statistics: The energy of statistical samples." Bowling Green State University, Department of Mathematics and Statistics, Technical Report 02-16 (2002).
- [3] Rizzo, Szekely "Energy distance." *Wiley Interdisciplinary Reviews: Computational Statistics*, 8(1):27-38 (2015).
- [4] Bellemare, Danihelka, Dabney, Mohamed, Lakshminarayanan, Hoyer, Munos "The Cramer Distance as a Solution to Biased Wasserstein Gradients" (2017). [arXiv:1705.10743](https://arxiv.org/abs/1705.10743).
- [1] L. Devroye, "Non-Uniform Random Variate Generation", Springer-Verlag, 1986.
- [2] W. Hoermann and J. Leydold, "Generating generalized inverse Gaussian random variates", *Statistics and Computing*, 24(4), p. 547-557, 2014.

- [3] A.J. Kinderman and J.F. Monahan, “Computer Generation of Random Variables Using the Ratio of Uniform Deviates”, *ACM Transactions on Mathematical Software*, 3(3), p. 257–260, 1977.
- [1] “Contingency table”, https://en.wikipedia.org/wiki/Contingency_table
- [2] “Pearson’s chi-squared test”, https://en.wikipedia.org/wiki/Pearson%27s_chi-squared_test
- [3] Cressie, N. and Read, T. R. C., “Multinomial Goodness-of-Fit Tests”, *J. Royal Stat. Soc. Series B*, Vol. 46, No. 3 (1984), pp. 440-464.
- [1] J.J. Filliben, “The Probability Plot Correlation Coefficient Test for Normality”, *Technometrics*, Vol. 17, pp. 111-117, 1975.
- [2] <https://www.itl.nist.gov/div898/handbook/eda/section3/ppccplot.htm>
- [1] *R* statistical software: <https://www.r-project.org/>
- [2] *R* quantile function: <http://stat.ethz.ch/R-manual/R-devel/library/stats/html/quantile.html>
- [1] Maurice G. Kendall, “Rank Correlation Methods” (4th Edition), Charles Griffin & Co., 1970.
- [1] Lowry, Richard. “Concepts and Applications of Inferential Statistics”. Chapter 8. <https://web.archive.org/web/20171022032306/http://vassarstats.net:80/textbook/ch8pt1.html>
- [2] “Chi-squared test”, https://en.wikipedia.org/wiki/Chi-squared_test
- [1] D.W. Scott, “Multivariate Density Estimation: Theory, Practice, and Visualization”, John Wiley & Sons, New York, Chicester, 1992.
- [2] B.W. Silverman, “Density Estimation for Statistics and Data Analysis”, Vol. 26, *Monographs on Statistics and Applied Probability*, Chapman and Hall, London, 1986.
- [3] B.A. Turlach, “Bandwidth Selection in Kernel Density Estimation: A Review”, *CORE and Institut de Statistique*, Vol. 19, pp. 1-33, 1993.
- [4] D.M. Bashtannyk and R.J. Hyndman, “Bandwidth selection for kernel conditional density estimation”, *Computational Statistics & Data Analysis*, Vol. 36, pp. 279-298, 2001.
- [5] Gray P. G., 1969, *Journal of the Royal Statistical Society. Series A (General)*, 132, 272

Symbols

- `__call__()` (*scipy.integrate.DenseOutput* method), 808
- `__call__()` (*scipy.integrate.OdeSolution* method), 809
- `__call__()` (*scipy.interpolate.Akima1DInterpolator* method), 846
- `__call__()` (*scipy.interpolate.BPoly* method), 860
- `__call__()` (*scipy.interpolate.BSpline* method), 886
- `__call__()` (*scipy.interpolate.BarycentricInterpolator* method), 831
- `__call__()` (*scipy.interpolate.BivariateSpline* method), 930
- `__call__()` (*scipy.interpolate.CloughTocher2DInterpolator* method), 871
- `__call__()` (*scipy.interpolate.CubicHermiteSpline* method), 839
- `__call__()` (*scipy.interpolate.CubicSpline* method), 851
- `__call__()` (*scipy.interpolate.InterpolatedUnivariateSpline* method), 914
- `__call__()` (*scipy.interpolate.KroghInterpolator* method), 833
- `__call__()` (*scipy.interpolate.LSQBivariateSpline* method), 939
- `__call__()` (*scipy.interpolate.LSQSphereBivariateSpline* method), 943
- `__call__()` (*scipy.interpolate.LSQUnivariateSpline* method), 920
- `__call__()` (*scipy.interpolate.LinearNDInterpolator* method), 867
- `__call__()` (*scipy.interpolate.NdPPoly* method), 882
- `__call__()` (*scipy.interpolate.NearestNDInterpolator* method), 869
- `__call__()` (*scipy.interpolate.PPoly* method), 854
- `__call__()` (*scipy.interpolate.PchipInterpolator* method), 843
- `__call__()` (*scipy.interpolate.Rbf* method), 872
- `__call__()` (*scipy.interpolate.RectBivariateSpline* method), 879
- `__call__()` (*scipy.interpolate.RectSphereBivariateSpline* method), 928
- `__call__()` (*scipy.interpolate.RegularGridInterpolator* method), 878
- `__call__()` (*scipy.interpolate.SmoothBivariateSpline* method), 933
- `__call__()` (*scipy.interpolate.SmoothSphereBivariateSpline* method), 937
- `__call__()` (*scipy.interpolate.UnivariateSpline* method), 909
- `__call__()` (*scipy.interpolate.interp1d* method), 830
- `__call__()` (*scipy.interpolate.interp2d* method), 874
- `__call__()` (*scipy.optimize.LbfgsInvHessProduct* method), 1711
- `__call__()` (*scipy.sparse.linalg.LinearOperator* method), 2159
- `__call__()` (*scipy.stats.gaussian_kde* method), 3080
- `__call__()` (*scipy.stats.rv_continuous* method), 2552
- `__call__()` (*scipy.stats.rv_discrete* method), 2564
- `__call__()` (*scipy.stats.rv_histogram* method), 2567
- `__getitem__()` (*scipy.cluster.hierarchy.DisjointSet* method), 679
- `__getitem__()` (*scipy.optimize.OptimizeResult* method), 1594
- `__len__()` (*scipy.optimize.OptimizeResult* method), 1594
- `__len__()` (*scipy.sparse.bsr_matrix* method), 2014
- `__len__()` (*scipy.sparse.coo_matrix* method), 2032
- `__len__()` (*scipy.sparse.csc_matrix* method), 2050
- `__len__()` (*scipy.sparse.csr_matrix* method), 2070
- `__len__()` (*scipy.sparse.dia_matrix* method), 2087
- `__len__()` (*scipy.sparse.dok_matrix* method), 2103
- `__len__()` (*scipy.sparse.lil_matrix* method), 2116
- `__len__()` (*scipy.sparse.spmatrix* method), 2127
- `__mul__()` (*scipy.signal.StateSpace* method), 1903
- `__mul__()` (*scipy.sparse.bsr_matrix* method), 2014
- `__mul__()` (*scipy.sparse.coo_matrix* method), 2032
- `__mul__()` (*scipy.sparse.csc_matrix* method), 2050
- `__mul__()` (*scipy.sparse.csr_matrix* method), 2070
- `__mul__()` (*scipy.sparse.dia_matrix* method), 2087
- `__mul__()` (*scipy.sparse.dok_matrix* method), 2103
- `__mul__()` (*scipy.sparse.lil_matrix* method), 2116

`__mul__()` (*scipy.sparse.spmatrix method*), 2127

A

`abcd_normalize()` (*in module scipy.signal*), 1857

`AccuracyWarning`, 784

`add()` (*scipy.cluster.hierarchy.DisjointSet method*), 678

`add_halfspaces()`
(*scipy.spatial.HalfspaceIntersection method*),
2276

`add_points()` (*scipy.spatial.ConvexHull method*),
2267

`add_points()` (*scipy.spatial.Delaunay method*), 2262

`add_points()` (*scipy.spatial.Voronoi method*), 2270

`add_xi()` (*scipy.interpolate.BarycentricInterpolator
method*), 831

`adjoint()` (*scipy.optimize.LbfgsInvHessProduct
method*), 1711

`adjoint()` (*scipy.sparse.linalg.LinearOperator method*),
2159

`affine_transform()` (*in module scipy.ndimage*),
1517

`agm` (*in module scipy.special*), 2514

`ai_zeros()` (*in module scipy.special*), 2322

`airy` (*in module scipy.special*), 2319

`airyx` (*in module scipy.special*), 2320

`Akima1DInterpolator` (*class in scipy.interpolate*),
845

`alpha` (*in module scipy.stats*), 2579

`anderson()` (*in module scipy.optimize*), 1745

`anderson()` (*in module scipy.stats*), 2986

`anderson_ksamp()` (*in module scipy.stats*), 2987

`anglit` (*in module scipy.stats*), 2581

`ansari()` (*in module scipy.stats*), 2981

`antiderivative()`
(*scipy.interpolate.Akima1DInterpolator method*),
847

`antiderivative()` (*scipy.interpolate.BPoly method*),
861

`antiderivative()` (*scipy.interpolate.BSpline
method*), 888

`antiderivative()`
(*scipy.interpolate.CubicHermiteSpline method*),
840

`antiderivative()` (*scipy.interpolate.CubicSpline
method*), 852

`antiderivative()`
(*scipy.interpolate.InterpolatedUnivariateSpline
method*), 914

`antiderivative()`
(*scipy.interpolate.LSQUnivariateSpline method*),
920

`antiderivative()` (*scipy.interpolate.NdPPoly
method*), 882

`antiderivative()`
(*scipy.interpolate.PchipInterpolator method*), 844

`antiderivative()` (*scipy.interpolate.PPoly method*),
855

`antiderivative()`
(*scipy.interpolate.UnivariateSpline method*), 909

`approx_fprime()` (*in module scipy.optimize*), 1706

`approximate_taylor_polynomial()` (*in module
scipy.interpolate*), 947

`arcsin()` (*scipy.sparse.bsr_matrix method*), 2014

`arcsin()` (*scipy.sparse.coo_matrix method*), 2032

`arcsin()` (*scipy.sparse.csc_matrix method*), 2050

`arcsin()` (*scipy.sparse.csr_matrix method*), 2070

`arcsin()` (*scipy.sparse.dia_matrix method*), 2088

`arcsine` (*in module scipy.stats*), 2584

`arcsinh()` (*scipy.sparse.bsr_matrix method*), 2014

`arcsinh()` (*scipy.sparse.coo_matrix method*), 2033

`arcsinh()` (*scipy.sparse.csc_matrix method*), 2051

`arcsinh()` (*scipy.sparse.csr_matrix method*), 2070

`arcsinh()` (*scipy.sparse.dia_matrix method*), 2088

`arctan()` (*scipy.sparse.bsr_matrix method*), 2014

`arctan()` (*scipy.sparse.coo_matrix method*), 2033

`arctan()` (*scipy.sparse.csc_matrix method*), 2051

`arctan()` (*scipy.sparse.csr_matrix method*), 2070

`arctan()` (*scipy.sparse.dia_matrix method*), 2088

`arctanh()` (*scipy.sparse.bsr_matrix method*), 2014

`arctanh()` (*scipy.sparse.coo_matrix method*), 2033

`arctanh()` (*scipy.sparse.csc_matrix method*), 2051

`arctanh()` (*scipy.sparse.csr_matrix method*), 2070

`arctanh()` (*scipy.sparse.dia_matrix method*), 2088

`ArffError`, 973

`argmax()` (*scipy.sparse.bsr_matrix method*), 2014

`argmax()` (*scipy.sparse.coo_matrix method*), 2033

`argmax()` (*scipy.sparse.csc_matrix method*), 2051

`argmax()` (*scipy.sparse.csr_matrix method*), 2070

`argmin()` (*scipy.sparse.bsr_matrix method*), 2015

`argmin()` (*scipy.sparse.coo_matrix method*), 2033

`argmin()` (*scipy.sparse.csc_matrix method*), 2051

`argmin()` (*scipy.sparse.csr_matrix method*), 2071

`argrelextrema()` (*in module scipy.signal*), 1969

`argrelmax()` (*in module scipy.signal*), 1968

`argrelmin()` (*in module scipy.signal*), 1967

`argstoarray()` (*in module scipy.stats.mstats*), 3074

`argus` (*in module scipy.stats*), 2586

`ArpackError`, 2201

`ArpackNoConvergence`, 2199

`ascent()` (*in module scipy.misc*), 1469

`asformat()` (*scipy.sparse.bsr_matrix method*), 2015

`asformat()` (*scipy.sparse.coo_matrix method*), 2034

`asformat()` (*scipy.sparse.csc_matrix method*), 2052

`asformat()` (*scipy.sparse.csr_matrix method*), 2071

`asformat()` (*scipy.sparse.dia_matrix method*), 2088

`asformat()` (*scipy.sparse.dok_matrix method*), 2103

`asformat()` (*scipy.sparse.lil_matrix method*), 2116

- asformat () (*scipy.sparse.spmatrix method*), 2127
 asfptype () (*scipy.sparse.bsr_matrix method*), 2015
 asfptype () (*scipy.sparse.coo_matrix method*), 2034
 asfptype () (*scipy.sparse.csc_matrix method*), 2052
 asfptype () (*scipy.sparse.csr_matrix method*), 2071
 asfptype () (*scipy.sparse.dia_matrix method*), 2089
 asfptype () (*scipy.sparse.dok_matrix method*), 2103
 asfptype () (*scipy.sparse.lil_matrix method*), 2116
 asfptype () (*scipy.sparse.spmatrix method*), 2127
 aslinearoperator () (*in module
 scipy.sparse.linalg*), 2161
 assignValue () (*scipy.io.netcdf_variable method*), 965
 assoc_laguerre () (*in module scipy.special*), 2456
 astype () (*scipy.sparse.bsr_matrix method*), 2016
 astype () (*scipy.sparse.coo_matrix method*), 2034
 astype () (*scipy.sparse.csc_matrix method*), 2052
 astype () (*scipy.sparse.csr_matrix method*), 2072
 astype () (*scipy.sparse.dia_matrix method*), 2089
 astype () (*scipy.sparse.dok_matrix method*), 2103
 astype () (*scipy.sparse.lil_matrix method*), 2116
 astype () (*scipy.sparse.spmatrix method*), 2127
 average () (*in module scipy.cluster.hierarchy*), 641
- ## B
- BadCoefficients, 1856
 band_stop_obj () (*in module scipy.signal*), 1857
 bartlett () (*in module scipy.stats*), 2983
 barycentric_interpolate () (*in module
 scipy.interpolate*), 834
 BarycentricInterpolator (*class in
 scipy.interpolate*), 830
 basinhopping () (*in module scipy.optimize*), 1620
 basis_element () (*scipy.interpolate.BSpline class
 method*), 886
 bayes_mvs () (*in module scipy.stats*), 2911
 BDF (*class in scipy.integrate*), 802
 bdtr (*in module scipy.special*), 2372
 bdtrc (*in module scipy.special*), 2373
 bdtri (*in module scipy.special*), 2373
 bdtrik (*in module scipy.special*), 2374
 bdtrin (*in module scipy.special*), 2375
 bei (*in module scipy.special*), 2502
 bei_zeros () (*in module scipy.special*), 2507
 beip (*in module scipy.special*), 2503
 beip_zeros () (*in module scipy.special*), 2508
 bellman_ford () (*in module scipy.sparse.csgraph*),
 2210
 ber (*in module scipy.special*), 2501
 ber_zeros () (*in module scipy.special*), 2507
 bernoulli (*in module scipy.stats*), 2853
 bernoulli () (*in module scipy.special*), 2515
 berp (*in module scipy.special*), 2503
 berp_zeros () (*in module scipy.special*), 2507
 bessel () (*in module scipy.signal*), 1885
 besselpoly () (*in module scipy.signal*), 1857
 besselpoly (*in module scipy.special*), 2358
 beta (*in module scipy.special*), 2428
 beta (*in module scipy.stats*), 2589
 betabinom (*in module scipy.stats*), 2856
 betainc (*in module scipy.special*), 2430
 betaincinv (*in module scipy.special*), 2431
 betaln (*in module scipy.special*), 2429
 betaprime (*in module scipy.stats*), 2591
 BFGS (*class in scipy.optimize*), 1616
 bi_zeros () (*in module scipy.special*), 2323
 bicg () (*in module scipy.sparse.linalg*), 2171
 bicgstab () (*in module scipy.sparse.linalg*), 2172
 bilinear () (*in module scipy.signal*), 1811
 bilinear_zpk () (*in module scipy.signal*), 1812
 binary_closing () (*in module scipy.ndimage*), 1548
 binary_dilation () (*in module scipy.ndimage*),
 1551
 binary_erosion () (*in module scipy.ndimage*), 1553
 binary_fill_holes () (*in module scipy.ndimage*),
 1554
 binary_hit_or_miss () (*in module scipy.ndimage*),
 1556
 binary_opening () (*in module scipy.ndimage*), 1557
 binary_propagation () (*in module scipy.ndimage*),
 1559
 binned_statistic () (*in module scipy.stats*), 2924
 binned_statistic_2d () (*in module scipy.stats*),
 2927
 binned_statistic_dd () (*in module scipy.stats*),
 2931
 binom (*in module scipy.special*), 2515
 binom (*in module scipy.stats*), 2858
 binom_test () (*in module scipy.stats*), 2988
 bisect () (*in module scipy.optimize*), 1659
 bisplev () (*in module scipy.interpolate*), 945
 bisplrep () (*in module scipy.interpolate*), 944
 BivariateSpline (*class in scipy.interpolate*), 929
 black_tophat () (*in module scipy.ndimage*), 1561
 block_diag () (*in module scipy.linalg*), 1072
 block_diag () (*in module scipy.sparse*), 2141
 bmat () (*in module scipy.sparse*), 2143
 bode () (*in module scipy.signal*), 1920
 bode () (*scipy.signal.dlti method*), 1924
 bode () (*scipy.signal.lti method*), 1900
 boltzmann (*in module scipy.stats*), 2860
 Bounds (*class in scipy.optimize*), 1615
 boxcox (*in module scipy.special*), 2413
 boxcox () (*in module scipy.stats*), 2998
 boxcox1p (*in module scipy.special*), 2413
 boxcox_llf () (*in module scipy.stats*), 3001
 boxcox_normmax () (*in module scipy.stats*), 3000
 boxcox_normplot () (*in module scipy.stats*), 3029
 BPoly (*class in scipy.interpolate*), 858

bracket () (in module *scipy.optimize*), 1708
 bradford (in module *scipy.stats*), 2594
 braycurtis () (in module *scipy.spatial.distance*), 2300
 breadth_first_order () (in module *scipy.sparse.csgraph*), 2213
 breadth_first_tree () (in module *scipy.sparse.csgraph*), 2215
 brent () (in module *scipy.optimize*), 1734
 brenth () (in module *scipy.optimize*), 1656
 brentq () (in module *scipy.optimize*), 1654
 broyden1 () (in module *scipy.optimize*), 1739
 broyden2 () (in module *scipy.optimize*), 1741
 brunnermunzel () (in module *scipy.stats*), 2978
 brunnermunzel () (in module *scipy.stats.mstats*), 3065
 brute () (in module *scipy.optimize*), 1624
 BSpline (class in *scipy.interpolate*), 884
 bspline () (in module *scipy.signal*), 1772
 bsr_matrix (class in *scipy.sparse*), 2010
 btdtr (in module *scipy.special*), 2375
 btdtri (in module *scipy.special*), 2376
 btdtria (in module *scipy.special*), 2377
 btdtrib (in module *scipy.special*), 2378
 burr (in module *scipy.stats*), 2596
 burr12 (in module *scipy.stats*), 2599
 buttap () (in module *scipy.signal*), 1858
 butter () (in module *scipy.signal*), 1869
 buttord () (in module *scipy.signal*), 1871

C

calculate_areas () (*scipy.spatial.SphericalVoronoi* method), 2273
 canberra () (in module *scipy.spatial.distance*), 2301
 cascade () (in module *scipy.signal*), 1961
 cauchy (in module *scipy.stats*), 2602
 caxpy (in module *scipy.linalg.blas*), 1094
 cbrt (in module *scipy.special*), 2531
 cc_diff () (in module *scipy.fftpack*), 760
 ccopy (in module *scipy.linalg.blas*), 1095
 cdf () (*scipy.stats.rv_continuous* method), 2546
 cdf () (*scipy.stats.rv_discrete* method), 2558
 cdf () (*scipy.stats.rv_histogram* method), 2567
 cdf2rdf () (in module *scipy.linalg*), 1049
 cdist () (in module *scipy.spatial.distance*), 2292
 cdotc (in module *scipy.linalg.blas*), 1095
 cdotu (in module *scipy.linalg.blas*), 1095
 ceil () (*scipy.sparse.bsr_matrix* method), 2016
 ceil () (*scipy.sparse.coo_matrix* method), 2034
 ceil () (*scipy.sparse.csc_matrix* method), 2052
 ceil () (*scipy.sparse.csr_matrix* method), 2072
 ceil () (*scipy.sparse.dia_matrix* method), 2089
 center_of_mass () (in module *scipy.ndimage*), 1531
 central_diff_weights () (in module *scipy.misc*), 1470
 centroid () (in module *scipy.cluster.hierarchy*), 644

cg () (in module *scipy.sparse.linalg*), 2173
 cgbmv (in module *scipy.linalg.blas*), 1126
 cgbsv (in module *scipy.linalg.lapack*), 1171
 cgbtrf (in module *scipy.linalg.lapack*), 1173
 cgbtrs (in module *scipy.linalg.lapack*), 1175
 cgebal (in module *scipy.linalg.lapack*), 1176
 cgecon (in module *scipy.linalg.lapack*), 1178
 cgeequ (in module *scipy.linalg.lapack*), 1179
 cgeequb (in module *scipy.linalg.lapack*), 1181
 cgees (in module *scipy.linalg.lapack*), 1183
 cgeev (in module *scipy.linalg.lapack*), 1185
 cgeev_lwork (in module *scipy.linalg.lapack*), 1187
 cgegsv () (in module *scipy.linalg.lapack*), 1189
 cgehrd (in module *scipy.linalg.lapack*), 1191
 cgehrd_lwork (in module *scipy.linalg.lapack*), 1192
 cgels (in module *scipy.linalg.lapack*), 1195
 cgels_lwork (in module *scipy.linalg.lapack*), 1197
 cgelsd (in module *scipy.linalg.lapack*), 1198
 cgelsd_lwork (in module *scipy.linalg.lapack*), 1200
 cgelss (in module *scipy.linalg.lapack*), 1202
 cgelss_lwork (in module *scipy.linalg.lapack*), 1204
 cgelsy (in module *scipy.linalg.lapack*), 1206
 cgelsy_lwork (in module *scipy.linalg.lapack*), 1207
 cgemm (in module *scipy.linalg.blas*), 1149
 cgemqrt (in module *scipy.linalg.lapack*), 1399
 cgemv (in module *scipy.linalg.blas*), 1127
 cgeqp3 (in module *scipy.linalg.lapack*), 1209
 cgeqrf (in module *scipy.linalg.lapack*), 1211
 cgeqrf_lwork (in module *scipy.linalg.lapack*), 1212
 cgeqrfp (in module *scipy.linalg.lapack*), 1213
 cgeqrfp_lwork (in module *scipy.linalg.lapack*), 1215
 cgeqrt (in module *scipy.linalg.lapack*), 1398
 cgerc (in module *scipy.linalg.blas*), 1127
 cgerqf (in module *scipy.linalg.lapack*), 1216
 cgeru (in module *scipy.linalg.blas*), 1128
 cgesc2 (in module *scipy.linalg.lapack*), 1236
 cgesdd (in module *scipy.linalg.lapack*), 1218
 cgesdd_lwork (in module *scipy.linalg.lapack*), 1219
 cgesv (in module *scipy.linalg.lapack*), 1221
 cgesvd (in module *scipy.linalg.lapack*), 1223
 cgesvd_lwork (in module *scipy.linalg.lapack*), 1225
 cgesvx (in module *scipy.linalg.lapack*), 1227
 cgetc2 (in module *scipy.linalg.lapack*), 1230
 cgetrf (in module *scipy.linalg.lapack*), 1229
 cgetri (in module *scipy.linalg.lapack*), 1232
 cgetri_lwork (in module *scipy.linalg.lapack*), 1233
 cgetrs (in module *scipy.linalg.lapack*), 1234
 cgges (in module *scipy.linalg.lapack*), 1239
 cggev (in module *scipy.linalg.lapack*), 1242
 cgglse (in module *scipy.linalg.lapack*), 1244
 cgglse_lwork (in module *scipy.linalg.lapack*), 1246
 cgs () (in module *scipy.sparse.linalg*), 2173
 cgtsv (in module *scipy.linalg.lapack*), 1248
 cgtsvx (in module *scipy.linalg.lapack*), 1250

- cgttrf (in module *scipy.linalg.lapack*), 1401
 cgttrs (in module *scipy.linalg.lapack*), 1403
 chbevd (in module *scipy.linalg.lapack*), 1252
 chbevz (in module *scipy.linalg.lapack*), 1253
 chbmv (in module *scipy.linalg.blas*), 1128
 chdtr (in module *scipy.special*), 2399
 chdtrc (in module *scipy.special*), 2400
 chdtri (in module *scipy.special*), 2401
 chdtriv (in module *scipy.special*), 2402
 cheb1ap () (in module *scipy.signal*), 1858
 cheb1ord () (in module *scipy.signal*), 1875
 cheb2ap () (in module *scipy.signal*), 1859
 cheb2ord () (in module *scipy.signal*), 1879
 cheby1 () (in module *scipy.signal*), 1872
 cheby2 () (in module *scipy.signal*), 1877
 chebyc () (in module *scipy.special*), 2479
 chebys () (in module *scipy.special*), 2480
 chebyshev () (in module *scipy.spatial.distance*), 2301
 chebyt () (in module *scipy.special*), 2478
 chebyu () (in module *scipy.special*), 2479
 check_COLA () (in module *scipy.signal*), 2007
 check_format () (*scipy.sparse.bsr_matrix* method), 2016
 check_format () (*scipy.sparse.csc_matrix* method), 2053
 check_format () (*scipy.sparse.csr_matrix* method), 2072
 check_grad () (in module *scipy.optimize*), 1707
 check_NOLA () (in module *scipy.signal*), 2008
 checon (in module *scipy.linalg.lapack*), 1254
 cheequb (in module *scipy.linalg.lapack*), 1255
 cheev (in module *scipy.linalg.lapack*), 1255
 cheev_lwork (in module *scipy.linalg.lapack*), 1256
 cheevd (in module *scipy.linalg.lapack*), 1257
 cheevd_lwork (in module *scipy.linalg.lapack*), 1258
 cheevr (in module *scipy.linalg.lapack*), 1258
 cheevr_lwork (in module *scipy.linalg.lapack*), 1260
 cheevx (in module *scipy.linalg.lapack*), 1260
 cheevx_lwork (in module *scipy.linalg.lapack*), 1262
 chegst (in module *scipy.linalg.lapack*), 1262
 chegv (in module *scipy.linalg.lapack*), 1263
 chegv_lwork (in module *scipy.linalg.lapack*), 1264
 chegvd (in module *scipy.linalg.lapack*), 1265
 chegvx (in module *scipy.linalg.lapack*), 1266
 chegvx_lwork (in module *scipy.linalg.lapack*), 1267
 chemm (in module *scipy.linalg.blas*), 1149
 chemv (in module *scipy.linalg.blas*), 1129
 cher (in module *scipy.linalg.blas*), 1129
 cher2 (in module *scipy.linalg.blas*), 1130
 cher2k (in module *scipy.linalg.blas*), 1150
 cherk (in module *scipy.linalg.blas*), 1150
 chesv (in module *scipy.linalg.lapack*), 1268
 chesv_lwork (in module *scipy.linalg.lapack*), 1269
 chesvx (in module *scipy.linalg.lapack*), 1269
 chesvx_lwork (in module *scipy.linalg.lapack*), 1270
 chetrd (in module *scipy.linalg.lapack*), 1271
 chetrd_lwork (in module *scipy.linalg.lapack*), 1272
 chetrf (in module *scipy.linalg.lapack*), 1272
 chetrf_lwork (in module *scipy.linalg.lapack*), 1273
 chfrk (in module *scipy.linalg.lapack*), 1274
 chi (in module *scipy.stats*), 2605
 chi2 (in module *scipy.stats*), 2607
 chi2_contingency () (in module *scipy.stats*), 3019
 chirp () (in module *scipy.signal*), 1945
 chisquare () (in module *scipy.stats*), 2959
 chisquare () (in module *scipy.stats.mstats*), 3059
 chndtr (in module *scipy.special*), 2403
 chndtridf (in module *scipy.special*), 2403
 chndtrinc (in module *scipy.special*), 2404
 chndtrix (in module *scipy.special*), 2404
 cho_factor () (in module *scipy.linalg*), 1028
 cho_solve () (in module *scipy.linalg*), 1029
 cho_solve_banded () (in module *scipy.linalg*), 1029
 cholesky () (in module *scipy.linalg*), 1026
 cholesky_banded () (in module *scipy.linalg*), 1027
 choose_conv_method () (in module *scipy.signal*), 1769
 chpmv (in module *scipy.linalg.blas*), 1130
 chpr (in module *scipy.linalg.blas*), 1131
 chpr2 (in module *scipy.linalg.blas*), 1131
 circmean () (in module *scipy.stats*), 3017
 circstd () (in module *scipy.stats*), 3018
 circulant () (in module *scipy.linalg*), 1073
 circvar () (in module *scipy.stats*), 3018
 cityblock () (in module *scipy.spatial.distance*), 2302
 cKDTree (class in *scipy.spatial*), 2246
 clang (in module *scipy.linalg.lapack*), 1276
 clarf (in module *scipy.linalg.lapack*), 1277
 clarfg (in module *scipy.linalg.lapack*), 1279
 clarkson_woodruff_transform () (in module *scipy.linalg*), 1069
 clartg (in module *scipy.linalg.lapack*), 1280
 claswp (in module *scipy.linalg.lapack*), 1282
 clauum (in module *scipy.linalg.lapack*), 1284
 clear () (*scipy.optimize.OptimizeResult* method), 1594
 clear () (*scipy.sparse.dok_matrix* method), 2104
 close () (*scipy.io.FortranFile* method), 958
 close () (*scipy.io.netcdf_file* method), 963
 close () (*scipy.spatial.ConvexHull* method), 2267
 close () (*scipy.spatial.Delaunay* method), 2263
 close () (*scipy.spatial.HalfspaceIntersection* method), 2276
 close () (*scipy.spatial.Voronoi* method), 2270
 CloughTocher2DInterpolator (class in *scipy.interpolate*), 869
 clpmn () (in module *scipy.special*), 2450
 ClusterNode (class in *scipy.cluster.hierarchy*), 663
 cmplx_sort () (in module *scipy.signal*), 1859

- coherence () (in module *scipy.signal*), 1991
- comb () (in module *scipy.special*), 2510
- combine_pvalues () (in module *scipy.stats*), 2979
- companion () (in module *scipy.linalg*), 1074
- compare_medians_ms () (in module *scipy.stats.mstats*), 3075
- complete () (in module *scipy.cluster.hierarchy*), 639
- complex_ode (class in *scipy.integrate*), 819
- conj () (*scipy.sparse.bsr_matrix* method), 2016
- conj () (*scipy.sparse.coo_matrix* method), 2035
- conj () (*scipy.sparse.csc_matrix* method), 2053
- conj () (*scipy.sparse.csr_matrix* method), 2072
- conj () (*scipy.sparse.dia_matrix* method), 2089
- conj () (*scipy.sparse.dok_matrix* method), 2104
- conj () (*scipy.sparse.lil_matrix* method), 2117
- conj () (*scipy.sparse.spmatrix* method), 2128
- conjtransp () (*scipy.sparse.dok_matrix* method), 2104
- conjugate () (*scipy.sparse.bsr_matrix* method), 2017
- conjugate () (*scipy.sparse.coo_matrix* method), 2035
- conjugate () (*scipy.sparse.csc_matrix* method), 2053
- conjugate () (*scipy.sparse.csr_matrix* method), 2073
- conjugate () (*scipy.sparse.dia_matrix* method), 2090
- conjugate () (*scipy.sparse.dok_matrix* method), 2104
- conjugate () (*scipy.sparse.lil_matrix* method), 2117
- conjugate () (*scipy.sparse.spmatrix* method), 2128
- connected () (*scipy.cluster.hierarchy.DisjointSet* method), 679
- connected_components () (in module *scipy.sparse.csgraph*), 2202
- ConstantWarning, 683
- construct_dist_matrix () (in module *scipy.sparse.csgraph*), 2227
- construct_fast () (*scipy.interpolate.BPoly* class method), 861
- construct_fast () (*scipy.interpolate.BSpline* class method), 890
- construct_fast () (*scipy.interpolate.NdPPoly* class method), 883
- construct_fast () (*scipy.interpolate.PPoly* class method), 858
- cont2discrete () (in module *scipy.signal*), 1940
- convert_temperature () (in module *scipy.constants*), 693
- convex_hull_plot_2d () (in module *scipy.spatial*), 2278
- ConvexHull (class in *scipy.spatial*), 2263
- convolution_matrix () (in module *scipy.linalg*), 1074
- convolve () (in module *scipy.fftpack.convolve*), 765
- convolve () (in module *scipy.ndimage*), 1476
- convolve () (in module *scipy.signal*), 1755
- convolve1d () (in module *scipy.ndimage*), 1478
- convolve2d () (in module *scipy.signal*), 1764
- convolve_z () (in module *scipy.fftpack.convolve*), 765
- coo_matrix (class in *scipy.sparse*), 2029
- cophenet () (in module *scipy.cluster.hierarchy*), 649
- copy () (*scipy.optimize.OptimizeResult* method), 1594
- copy () (*scipy.sparse.bsr_matrix* method), 2017
- copy () (*scipy.sparse.coo_matrix* method), 2035
- copy () (*scipy.sparse.csc_matrix* method), 2053
- copy () (*scipy.sparse.csr_matrix* method), 2073
- copy () (*scipy.sparse.dia_matrix* method), 2090
- copy () (*scipy.sparse.dok_matrix* method), 2104
- copy () (*scipy.sparse.lil_matrix* method), 2117
- copy () (*scipy.sparse.spmatrix* method), 2128
- correlate () (in module *scipy.ndimage*), 1479
- correlate () (in module *scipy.signal*), 1757
- correlate1d () (in module *scipy.ndimage*), 1481
- correlate2d () (in module *scipy.signal*), 1765
- correlation () (in module *scipy.spatial.distance*), 2302
- correlation_lags () (in module *scipy.signal*), 1771
- correspond () (in module *scipy.cluster.hierarchy*), 674
- cosdg (in module *scipy.special*), 2533
- coshm () (in module *scipy.linalg*), 1055
- cosine (in module *scipy.stats*), 2610
- cosine () (in module *scipy.spatial.distance*), 2303
- cosm () (in module *scipy.linalg*), 1054
- cosm1 (in module *scipy.special*), 2537
- cossin () (in module *scipy.linalg*), 1050
- cotdg (in module *scipy.special*), 2535
- count_neighbors () (*scipy.spatial.cKDTree* method), 2248
- count_neighbors () (*scipy.spatial.KDTree* method), 2237
- count_nonzero () (*scipy.sparse.bsr_matrix* method), 2017
- count_nonzero () (*scipy.sparse.coo_matrix* method), 2035
- count_nonzero () (*scipy.sparse.csc_matrix* method), 2054
- count_nonzero () (*scipy.sparse.csr_matrix* method), 2073
- count_nonzero () (*scipy.sparse.dia_matrix* method), 2090
- count_nonzero () (*scipy.sparse.dok_matrix* method), 2105
- count_nonzero () (*scipy.sparse.lil_matrix* method), 2117
- count_nonzero () (*scipy.sparse.spmatrix* method), 2128
- count_tied_groups () (in module *scipy.stats.mstats*), 3075
- covariance_factor () (*scipy.stats.gaussian_kde* method), 3084
- cpbsv (in module *scipy.linalg.lapack*), 1293
- cpbtrf (in module *scipy.linalg.lapack*), 1295
- cpbtrs (in module *scipy.linalg.lapack*), 1296

- cpftfrf (in module *scipy.linalg.lapack*), 1298
 cpfttri (in module *scipy.linalg.lapack*), 1300
 cpfttrs (in module *scipy.linalg.lapack*), 1301
 cpocon (in module *scipy.linalg.lapack*), 1303
 cposv (in module *scipy.linalg.lapack*), 1307
 cposvx (in module *scipy.linalg.lapack*), 1309
 cpotrf (in module *scipy.linalg.lapack*), 1311
 cpotri (in module *scipy.linalg.lapack*), 1313
 cpotrs (in module *scipy.linalg.lapack*), 1314
 cppcon (in module *scipy.linalg.lapack*), 1315
 cppsv (in module *scipy.linalg.lapack*), 1317
 cpptrf (in module *scipy.linalg.lapack*), 1319
 cpptri (in module *scipy.linalg.lapack*), 1320
 cpptrs (in module *scipy.linalg.lapack*), 1322
 cpstf2 (in module *scipy.linalg.lapack*), 1306
 cpstrf (in module *scipy.linalg.lapack*), 1304
 cpteqr (in module *scipy.linalg.lapack*), 1331
 cptsv (in module *scipy.linalg.lapack*), 1323
 cptsvx (in module *scipy.linalg.lapack*), 1325
 cpttrf (in module *scipy.linalg.lapack*), 1327
 cpttrs (in module *scipy.linalg.lapack*), 1329
 cramervonmises () (in module *scipy.stats*), 2961
 createDimension () (*scipy.io.netcdf_file* method), 963
 createVariable () (*scipy.io.netcdf_file* method), 964
 crot (in module *scipy.linalg.lapack*), 1332
 crotg (in module *scipy.linalg.blas*), 1096
 crystalball (in module *scipy.stats*), 2612
 cs_diff () (in module *scipy.fftpack*), 759
 csc_matrix (class in *scipy.sparse*), 2047
 cscal (in module *scipy.linalg.blas*), 1096
 csd () (in module *scipy.signal*), 1989
 csgraph_from_dense () (in module *scipy.sparse.csgraph*), 2228
 csgraph_from_masked () (in module *scipy.sparse.csgraph*), 2229
 csgraph_masked_from_dense () (in module *scipy.sparse.csgraph*), 2230
 csgraph_to_dense () (in module *scipy.sparse.csgraph*), 2230
 csgraph_to_masked () (in module *scipy.sparse.csgraph*), 2232
 cspline1d () (in module *scipy.signal*), 1775
 cspline1d_eval () (in module *scipy.signal*), 1778
 cspline2d () (in module *scipy.signal*), 1777
 csr_matrix (class in *scipy.sparse*), 2066
 csrot (in module *scipy.linalg.blas*), 1096
 csscal (in module *scipy.linalg.blas*), 1097
 cswap (in module *scipy.linalg.blas*), 1097
 csycon (in module *scipy.linalg.lapack*), 1343
 csyconv (in module *scipy.linalg.lapack*), 1344
 csyequb (in module *scipy.linalg.lapack*), 1346
 csymm (in module *scipy.linalg.blas*), 1151
 csyr (in module *scipy.linalg.blas*), 1134
 csyr2k (in module *scipy.linalg.blas*), 1151
 csyrk (in module *scipy.linalg.blas*), 1151
 csysv (in module *scipy.linalg.lapack*), 1360
 csysv_lwork (in module *scipy.linalg.lapack*), 1361
 csysvx (in module *scipy.linalg.lapack*), 1363
 csysvx_lwork (in module *scipy.linalg.lapack*), 1365
 csytf2 (in module *scipy.linalg.lapack*), 1366
 csytrf (in module *scipy.linalg.lapack*), 1369
 csytrf_lwork (in module *scipy.linalg.lapack*), 1371
 ctbmv (in module *scipy.linalg.blas*), 1132
 ctbsv (in module *scipy.linalg.blas*), 1132
 ctbtrs (in module *scipy.linalg.lapack*), 1372
 ctfsm (in module *scipy.linalg.lapack*), 1374
 ctfttp (in module *scipy.linalg.lapack*), 1375
 ctfttr (in module *scipy.linalg.lapack*), 1377
 ctgsen (in module *scipy.linalg.lapack*), 1379
 ctpmqrt (in module *scipy.linalg.lapack*), 1407
 ctpmv (in module *scipy.linalg.blas*), 1133
 ctpqrt (in module *scipy.linalg.lapack*), 1405
 ctpsv (in module *scipy.linalg.blas*), 1133
 ctpttf (in module *scipy.linalg.lapack*), 1381
 ctpttr (in module *scipy.linalg.lapack*), 1382
 ctrmm (in module *scipy.linalg.blas*), 1152
 ctrmv (in module *scipy.linalg.blas*), 1134
 ctrsm (in module *scipy.linalg.blas*), 1152
 ctrsv (in module *scipy.linalg.blas*), 1134
 ctrsyl (in module *scipy.linalg.lapack*), 1384
 ctrtri (in module *scipy.linalg.lapack*), 1385
 ctrtrs (in module *scipy.linalg.lapack*), 1387
 ctrttf (in module *scipy.linalg.lapack*), 1389
 ctrttp (in module *scipy.linalg.lapack*), 1390
 ctzrzf (in module *scipy.linalg.lapack*), 1391
 ctzrzf_lwork (in module *scipy.linalg.lapack*), 1393
 cubic () (in module *scipy.signal*), 1773
 CubicHermiteSpline (class in *scipy.interpolate*), 838
 CubicSpline (class in *scipy.interpolate*), 848
 cumfreq () (in module *scipy.stats*), 2919
 cumulative_trapezoid () (in module *scipy.integrate*), 786
 cuncsd (in module *scipy.linalg.lapack*), 1408
 cuncsd_lwork (in module *scipy.linalg.lapack*), 1410
 cunghr (in module *scipy.linalg.lapack*), 1393
 cunghr_lwork (in module *scipy.linalg.lapack*), 1394
 cungrq (in module *scipy.linalg.lapack*), 1395
 cungrq (in module *scipy.linalg.lapack*), 1395
 cunmqr (in module *scipy.linalg.lapack*), 1396
 cunmrz (in module *scipy.linalg.lapack*), 1411
 cunmrz_lwork (in module *scipy.linalg.lapack*), 1411
 curve_fit () (in module *scipy.optimize*), 1649
 cut_tree () (in module *scipy.cluster.hierarchy*), 667
 cwt () (in module *scipy.signal*), 1965

D

dasum (in module *scipy.linalg.blas*), 1098

- Data (class in *scipy.odr*), 1577
- daub () (in module *scipy.signal*), 1961
- dawsn (in module *scipy.special*), 2444
- daxpy (in module *scipy.linalg.blas*), 1098
- dblquad () (in module *scipy.integrate*), 773
- dbode () (in module *scipy.signal*), 1931
- dcopy (in module *scipy.linalg.blas*), 1098
- dct () (in module *scipy.fft*), 724
- dct () (in module *scipy.fftpack*), 748
- dctn () (in module *scipy.fft*), 727
- dctn () (in module *scipy.fftpack*), 751
- ddot (in module *scipy.linalg.blas*), 1099
- decimate () (in module *scipy.signal*), 1802
- deconvolve () (in module *scipy.signal*), 1795
- deg2rad () (*scipy.sparse.bsr_matrix* method), 2017
- deg2rad () (*scipy.sparse.coo_matrix* method), 2036
- deg2rad () (*scipy.sparse.csc_matrix* method), 2054
- deg2rad () (*scipy.sparse.csr_matrix* method), 2073
- deg2rad () (*scipy.sparse.dia_matrix* method), 2090
- Delaunay (class in *scipy.spatial*), 2259
- delaunay_plot_2d () (in module *scipy.spatial*), 2277
- dendrogram () (in module *scipy.cluster.hierarchy*), 659
- dense_output () (*scipy.integrate.BDF* method), 804
- dense_output () (*scipy.integrate.DOP853* method), 800
- dense_output () (*scipy.integrate.LSODA* method), 806
- dense_output () (*scipy.integrate.OdeSolver* method), 807
- dense_output () (*scipy.integrate.Radau* method), 802
- dense_output () (*scipy.integrate.RK23* method), 797
- dense_output () (*scipy.integrate.RK45* method), 799
- DenseOutput (class in *scipy.integrate*), 808
- depth_first_order () (in module *scipy.sparse.csgraph*), 2214
- depth_first_tree () (in module *scipy.sparse.csgraph*), 2216
- derivative () (in module *scipy.misc*), 1470
- derivative () (*scipy.interpolate.Akima1DInterpolator* method), 846
- derivative () (*scipy.interpolate.BPoly* method), 860
- derivative () (*scipy.interpolate.BSpline* method), 888
- derivative () (*scipy.interpolate.CubicHermiteSpline* method), 840
- derivative () (*scipy.interpolate.CubicSpline* method), 851
- derivative () (*scipy.interpolate.InterpolatedUnivariateSpline* method), 915
- derivative () (*scipy.interpolate.KroghInterpolator* method), 833
- derivative () (*scipy.interpolate.LSQUnivariateSpline* method), 921
- derivative () (*scipy.interpolate.NdPPoly* method), 882
- derivative () (*scipy.interpolate.PchipInterpolator* method), 843
- derivative () (*scipy.interpolate.PPoly* method), 855
- derivative () (*scipy.interpolate.UnivariateSpline* method), 910
- derivatives () (*scipy.interpolate.InterpolatedUnivariateSpline* method), 916
- derivatives () (*scipy.interpolate.KroghInterpolator* method), 834
- derivatives () (*scipy.interpolate.LSQUnivariateSpline* method), 922
- derivatives () (*scipy.interpolate.UnivariateSpline* method), 910
- describe () (in module *scipy.stats*), 2890
- describe () (in module *scipy.stats.mstats*), 3035
- destroy_convolve_cache () (in module *scipy.fftpack.convolve*), 766
- det () (in module *scipy.linalg*), 986
- detrend () (in module *scipy.signal*), 1803
- dfreqresp () (in module *scipy.signal*), 1929
- dft () (in module *scipy.linalg*), 1077
- dgamma (in module *scipy.stats*), 2615
- dgbmv (in module *scipy.linalg.blas*), 1119
- dgbsv (in module *scipy.linalg.lapack*), 1170
- dgbtrf (in module *scipy.linalg.lapack*), 1172
- dgbtrs (in module *scipy.linalg.lapack*), 1174
- dgebal (in module *scipy.linalg.lapack*), 1176
- dgecon (in module *scipy.linalg.lapack*), 1178
- dgeequ (in module *scipy.linalg.lapack*), 1179
- dgeequb (in module *scipy.linalg.lapack*), 1180
- dgees (in module *scipy.linalg.lapack*), 1182
- dgeev (in module *scipy.linalg.lapack*), 1185
- dgeev_lwork (in module *scipy.linalg.lapack*), 1187
- dgegv () (in module *scipy.linalg.lapack*), 1188
- dgehrd (in module *scipy.linalg.lapack*), 1191
- dgehrd_lwork (in module *scipy.linalg.lapack*), 1192
- dgejsv (in module *scipy.linalg.lapack*), 1194
- dgels (in module *scipy.linalg.lapack*), 1195
- dgels_lwork (in module *scipy.linalg.lapack*), 1196
- dgelsd (in module *scipy.linalg.lapack*), 1198
- dgelsd_lwork (in module *scipy.linalg.lapack*), 1200
- dgelss (in module *scipy.linalg.lapack*), 1202
- dgelss_lwork (in module *scipy.linalg.lapack*), 1204
- dgelsy (in module *scipy.linalg.lapack*), 1205
- dgelsy_lwork (in module *scipy.linalg.lapack*), 1207
- dgemm (in module *scipy.linalg.blas*), 1146
- dgemqrt (in module *scipy.linalg.lapack*), 1399
- dgemv (in module *scipy.linalg.blas*), 1120
- dgeqp3 (in module *scipy.linalg.lapack*), 1209
- dgeqrf (in module *scipy.linalg.lapack*), 1210
- dgeqrf_lwork (in module *scipy.linalg.lapack*), 1212

- dgeqrfp (in module *scipy.linalg.lapack*), 1213
 dgeqrfp_lwork (in module *scipy.linalg.lapack*), 1214
 dgeqrt (in module *scipy.linalg.lapack*), 1397
 dger (in module *scipy.linalg.blas*), 1121
 dgerqf (in module *scipy.linalg.lapack*), 1216
 dgesc2 (in module *scipy.linalg.lapack*), 1236
 dgesdd (in module *scipy.linalg.lapack*), 1217
 dgesdd_lwork (in module *scipy.linalg.lapack*), 1219
 dgesv (in module *scipy.linalg.lapack*), 1221
 dgesvd (in module *scipy.linalg.lapack*), 1222
 dgesvd_lwork (in module *scipy.linalg.lapack*), 1224
 dgesvx (in module *scipy.linalg.lapack*), 1226
 dgetc2 (in module *scipy.linalg.lapack*), 1230
 dgetrf (in module *scipy.linalg.lapack*), 1229
 dgetri (in module *scipy.linalg.lapack*), 1231
 dgetri_lwork (in module *scipy.linalg.lapack*), 1233
 dgetrs (in module *scipy.linalg.lapack*), 1234
 dggges (in module *scipy.linalg.lapack*), 1238
 dggev (in module *scipy.linalg.lapack*), 1241
 dggls (in module *scipy.linalg.lapack*), 1244
 dggls_lwork (in module *scipy.linalg.lapack*), 1246
 dgtsv (in module *scipy.linalg.lapack*), 1247
 dgtsvx (in module *scipy.linalg.lapack*), 1250
 dgttrf (in module *scipy.linalg.lapack*), 1401
 dgttrs (in module *scipy.linalg.lapack*), 1403
 dia_matrix (class in *scipy.sparse*), 2085
 diagbroyden () (in module *scipy.optimize*), 1748
 diagonal () (*scipy.sparse.bsr_matrix* method), 2017
 diagonal () (*scipy.sparse.coo_matrix* method), 2036
 diagonal () (*scipy.sparse.csc_matrix* method), 2054
 diagonal () (*scipy.sparse.csr_matrix* method), 2073
 diagonal () (*scipy.sparse.dia_matrix* method), 2090
 diagonal () (*scipy.sparse.dok_matrix* method), 2105
 diagonal () (*scipy.sparse.lil_matrix* method), 2118
 diagonal () (*scipy.sparse.spmatrix* method), 2129
 diags () (in module *scipy.sparse*), 2139
 diagsvd () (in module *scipy.linalg*), 1022
 dice () (in module *scipy.spatial.distance*), 2308
 diff () (in module *scipy.fftpack*), 757
 differential_evolution () (in module *scipy.optimize*), 1626
 digamma (in module *scipy.special*), 2435
 dijkstra () (in module *scipy.sparse.csgraph*), 2206
 dimpulse () (in module *scipy.signal*), 1927
 directed_hausdorff () (in module *scipy.spatial.distance*), 2297
 diric () (in module *scipy.special*), 2516
 dirichlet (in module *scipy.stats*), 2837
 DisjointSet (class in *scipy.cluster.hierarchy*), 677
 distance_matrix () (in module *scipy.spatial*), 2282
 distance_transform_bf () (in module *scipy.ndimage*), 1562
 distance_transform_cdt () (in module *scipy.ndimage*), 1563
 distance_transform_edt () (in module *scipy.ndimage*), 1563
 dlamch (in module *scipy.linalg.lapack*), 1275
 dlange (in module *scipy.linalg.lapack*), 1275
 dlaplace (in module *scipy.stats*), 2863
 dlarf (in module *scipy.linalg.lapack*), 1277
 dlarfg (in module *scipy.linalg.lapack*), 1278
 dlartg (in module *scipy.linalg.lapack*), 1280
 dlasd4 (in module *scipy.linalg.lapack*), 1281
 dlaswp (in module *scipy.linalg.lapack*), 1282
 dlauum (in module *scipy.linalg.lapack*), 1283
 dlsim () (in module *scipy.signal*), 1926
 dlti (class in *scipy.signal*), 1922
 dnrn2 (in module *scipy.linalg.blas*), 1099
 dok_matrix (class in *scipy.sparse*), 2100
 DOP853 (class in *scipy.integrate*), 799
 dorcsd (in module *scipy.linalg.lapack*), 1285
 dorcsd_lwork (in module *scipy.linalg.lapack*), 1286
 dorghr (in module *scipy.linalg.lapack*), 1287
 dorghr_lwork (in module *scipy.linalg.lapack*), 1288
 dorgqr (in module *scipy.linalg.lapack*), 1288
 dorgqr_lwork (in module *scipy.linalg.lapack*), 1289
 dormqr (in module *scipy.linalg.lapack*), 1290
 dormrz (in module *scipy.linalg.lapack*), 1291
 dormrz_lwork (in module *scipy.linalg.lapack*), 1292
 dot () (*scipy.optimize.BFGS* method), 1617
 dot () (*scipy.optimize.HessianUpdateStrategy* method), 1714
 dot () (*scipy.optimize.LbfgsInvHessProduct* method), 1711
 dot () (*scipy.optimize.SR1* method), 1618
 dot () (*scipy.sparse.bsr_matrix* method), 2018
 dot () (*scipy.sparse.coo_matrix* method), 2036
 dot () (*scipy.sparse.csc_matrix* method), 2054
 dot () (*scipy.sparse.csr_matrix* method), 2074
 dot () (*scipy.sparse.dia_matrix* method), 2091
 dot () (*scipy.sparse.dok_matrix* method), 2105
 dot () (*scipy.sparse.lil_matrix* method), 2118
 dot () (*scipy.sparse.linalg.LinearOperator* method), 2159
 dot () (*scipy.sparse.spmatrix* method), 2129
 dpbsv (in module *scipy.linalg.lapack*), 1293
 dpbtrf (in module *scipy.linalg.lapack*), 1294
 dpbtrs (in module *scipy.linalg.lapack*), 1296
 dpftrf (in module *scipy.linalg.lapack*), 1298
 dpftri (in module *scipy.linalg.lapack*), 1299
 dpftrs (in module *scipy.linalg.lapack*), 1301
 dpocon (in module *scipy.linalg.lapack*), 1302
 dposv (in module *scipy.linalg.lapack*), 1307
 dposvx (in module *scipy.linalg.lapack*), 1309
 dpotrf (in module *scipy.linalg.lapack*), 1311
 dpotri (in module *scipy.linalg.lapack*), 1312
 dpotrs (in module *scipy.linalg.lapack*), 1314
 dppcon (in module *scipy.linalg.lapack*), 1315
 dppsv (in module *scipy.linalg.lapack*), 1317

- dpptrf (in module *scipy.linalg.lapack*), 1318
 dpptri (in module *scipy.linalg.lapack*), 1320
 dpptrs (in module *scipy.linalg.lapack*), 1321
 dpstf2 (in module *scipy.linalg.lapack*), 1305
 dpstrf (in module *scipy.linalg.lapack*), 1304
 dpteqr (in module *scipy.linalg.lapack*), 1330
 dptsv (in module *scipy.linalg.lapack*), 1323
 dptsvx (in module *scipy.linalg.lapack*), 1325
 dpttrf (in module *scipy.linalg.lapack*), 1327
 dpttrs (in module *scipy.linalg.lapack*), 1328
 drot (in module *scipy.linalg.blas*), 1099
 drotg (in module *scipy.linalg.blas*), 1100
 drotm (in module *scipy.linalg.blas*), 1100
 drotmg (in module *scipy.linalg.blas*), 1101
 dsbev (in module *scipy.linalg.lapack*), 1333
 dsbevd (in module *scipy.linalg.lapack*), 1334
 dsbevz (in module *scipy.linalg.lapack*), 1335
 dsbmv (in module *scipy.linalg.blas*), 1121
 dscal (in module *scipy.linalg.blas*), 1101
 dsfrk (in module *scipy.linalg.lapack*), 1336
 dspr (in module *scipy.linalg.blas*), 1122
 dspr2 (in module *scipy.linalg.blas*), 1122
 dst () (in module *scipy.fft*), 729
 dst () (in module *scipy.fftpack*), 753
 dstebz (in module *scipy.linalg.lapack*), 1337
 dstein (in module *scipy.linalg.lapack*), 1338
 dstemr (in module *scipy.linalg.lapack*), 1339
 dstemr_lwork (in module *scipy.linalg.lapack*), 1340
 dstep () (in module *scipy.signal*), 1928
 dsterf (in module *scipy.linalg.lapack*), 1341
 dstev (in module *scipy.linalg.lapack*), 1342
 dstn () (in module *scipy.fft*), 731
 dstn () (in module *scipy.fftpack*), 755
 dswap (in module *scipy.linalg.blas*), 1101
 dsycon (in module *scipy.linalg.lapack*), 1342
 dsyconv (in module *scipy.linalg.lapack*), 1344
 dsyequb (in module *scipy.linalg.lapack*), 1345
 dsyev (in module *scipy.linalg.lapack*), 1347
 dsyev_lwork (in module *scipy.linalg.lapack*), 1348
 dsyevd (in module *scipy.linalg.lapack*), 1348
 dsyevd_lwork (in module *scipy.linalg.lapack*), 1349
 dsyevr (in module *scipy.linalg.lapack*), 1350
 dsyevr_lwork (in module *scipy.linalg.lapack*), 1351
 dsyevz (in module *scipy.linalg.lapack*), 1352
 dsyevz_lwork (in module *scipy.linalg.lapack*), 1353
 dsygst (in module *scipy.linalg.lapack*), 1354
 dsygv (in module *scipy.linalg.lapack*), 1355
 dsygv_lwork (in module *scipy.linalg.lapack*), 1355
 dsygvd (in module *scipy.linalg.lapack*), 1356
 dsygvx (in module *scipy.linalg.lapack*), 1357
 dsygvx_lwork (in module *scipy.linalg.lapack*), 1358
 dsymm (in module *scipy.linalg.blas*), 1147
 dsymv (in module *scipy.linalg.blas*), 1123
 dsyr (in module *scipy.linalg.blas*), 1123
 dsyr2 (in module *scipy.linalg.blas*), 1124
 dsyr2k (in module *scipy.linalg.blas*), 1147
 dsyrk (in module *scipy.linalg.blas*), 1148
 dsysv (in module *scipy.linalg.lapack*), 1359
 dsysv_lwork (in module *scipy.linalg.lapack*), 1361
 dsysvx (in module *scipy.linalg.lapack*), 1363
 dsysvx_lwork (in module *scipy.linalg.lapack*), 1365
 dsytf2 (in module *scipy.linalg.lapack*), 1366
 dsytrd (in module *scipy.linalg.lapack*), 1368
 dsytrd_lwork (in module *scipy.linalg.lapack*), 1368
 dsytrf (in module *scipy.linalg.lapack*), 1369
 dsytrf_lwork (in module *scipy.linalg.lapack*), 1370
 dtbmv (in module *scipy.linalg.blas*), 1124
 dtbtrs (in module *scipy.linalg.lapack*), 1372
 dtfsm (in module *scipy.linalg.lapack*), 1373
 dtfttp (in module *scipy.linalg.lapack*), 1375
 dtfttr (in module *scipy.linalg.lapack*), 1376
 dtgsen (in module *scipy.linalg.lapack*), 1378
 dtpmqrt (in module *scipy.linalg.lapack*), 1407
 dtpqrt (in module *scipy.linalg.lapack*), 1405
 dtpsv (in module *scipy.linalg.blas*), 1125
 dtpttf (in module *scipy.linalg.lapack*), 1381
 dtpttr (in module *scipy.linalg.lapack*), 1382
 dtrmm (in module *scipy.linalg.blas*), 1148
 dtrmv (in module *scipy.linalg.blas*), 1125
 dtrsm (in module *scipy.linalg.blas*), 1148
 dtrsv (in module *scipy.linalg.blas*), 1126
 dtrsyl (in module *scipy.linalg.lapack*), 1383
 dtrtri (in module *scipy.linalg.lapack*), 1385
 dtrtrs (in module *scipy.linalg.lapack*), 1387
 dtrttf (in module *scipy.linalg.lapack*), 1388
 dtrttp (in module *scipy.linalg.lapack*), 1390
 dtzrzf (in module *scipy.linalg.lapack*), 1391
 dtzrzf_lwork (in module *scipy.linalg.lapack*), 1392
 dual_annealing () (in module *scipy.optimize*), 1635
 dweibull (in module *scipy.stats*), 2617
 dzasum (in module *scipy.linalg.blas*), 1102
 dznrm2 (in module *scipy.linalg.blas*), 1102
- ## E
- eig () (in module *scipy.linalg*), 1002
 eig_banded () (in module *scipy.linalg*), 1009
 eigh () (in module *scipy.linalg*), 1005
 eigh_tridiagonal () (in module *scipy.linalg*), 1013
 eigs () (in module *scipy.sparse.linalg*), 2186
 eigsh () (in module *scipy.sparse.linalg*), 2188
 eigvals () (in module *scipy.linalg*), 1003
 eigvals_banded () (in module *scipy.linalg*), 1011
 eigvalsh () (in module *scipy.linalg*), 1007
 eigvalsh_tridiagonal () (in module *scipy.linalg*),
 1014
 electrocardiogram () (in module *scipy.misc*), 1472
 eliminate_zeros () (*scipy.sparse.bsr_matrix*
 method), 2018

- `eliminate_zeros()` (*scipy.sparse.coo_matrix method*), 2037
`eliminate_zeros()` (*scipy.sparse.csc_matrix method*), 2055
`eliminate_zeros()` (*scipy.sparse.csr_matrix method*), 2074
`ellip()` (*in module scipy.signal*), 1881
`ellip_harm()` (*in module scipy.special*), 2452
`ellip_harm_2()` (*in module scipy.special*), 2454
`ellip_normal()` (*in module scipy.special*), 2454
`ellipap()` (*in module scipy.signal*), 1859
`ellipe` (*in module scipy.special*), 2328
`ellipeinc` (*in module scipy.special*), 2329
`ellipj` (*in module scipy.special*), 2324
`ellipk` (*in module scipy.special*), 2325
`ellipkinc` (*in module scipy.special*), 2327
`ellipkm1` (*in module scipy.special*), 2326
`ellipord()` (*in module scipy.signal*), 1884
`energy_distance()` (*in module scipy.stats*), 3014
`entr` (*in module scipy.special*), 2416
`entropy()` (*in module scipy.stats*), 2914
`entropy()` (*scipy.stats.rv_continuous method*), 2549
`entropy()` (*scipy.stats.rv_discrete method*), 2561
`entropy()` (*scipy.stats.rv_histogram method*), 2568
`epps_singleton_2samp()` (*in module scipy.stats*), 2970
`erf` (*in module scipy.special*), 2437
`erf_zeros()` (*in module scipy.special*), 2447
`erfc` (*in module scipy.special*), 2437
`erfcinv` (*in module scipy.special*), 2442
`erfcx` (*in module scipy.special*), 2438
`erfi` (*in module scipy.special*), 2439
`erfinv` (*in module scipy.special*), 2440
`erlang` (*in module scipy.stats*), 2620
`errno` (*scipy.io.arff.ArffError attribute*), 973
`errno` (*scipy.io.arff.ParseArffError attribute*), 974
`errno` (*scipy.io.FortranEOFError attribute*), 960
`errno` (*scipy.io.FortranFormattingError attribute*), 960
`errstate` (*class in scipy.special*), 2317
`estimate_rank()` (*in module scipy.linalg.interpolative*), 1463
`estimate_spectral_norm()` (*in module scipy.linalg.interpolative*), 1463
`estimate_spectral_norm_diff()` (*in module scipy.linalg.interpolative*), 1463
`euclidean()` (*in module scipy.spatial.distance*), 2303
`euler()` (*in module scipy.special*), 2518
`ev()` (*scipy.interpolate.BivariateSpline method*), 931
`ev()` (*scipy.interpolate.LSQBivariateSpline method*), 939
`ev()` (*scipy.interpolate.LSQSphereBivariateSpline method*), 943
`ev()` (*scipy.interpolate.RectBivariateSpline method*), 879
`ev()` (*scipy.interpolate.RectSphereBivariateSpline method*), 928
`ev()` (*scipy.interpolate.SmoothBivariateSpline method*), 933
`ev()` (*scipy.interpolate.SmoothSphereBivariateSpline method*), 937
`eval_chebyc` (*in module scipy.special*), 2460
`eval_chebys` (*in module scipy.special*), 2461
`eval_chebyt` (*in module scipy.special*), 2457
`eval_chebyu` (*in module scipy.special*), 2459
`eval_gegenbauer` (*in module scipy.special*), 2465
`eval_genlaguerre` (*in module scipy.special*), 2463
`eval_hermite` (*in module scipy.special*), 2464
`eval_hermitenorm` (*in module scipy.special*), 2464
`eval_jacobi` (*in module scipy.special*), 2462
`eval_laguerre` (*in module scipy.special*), 2462
`eval_legendre` (*in module scipy.special*), 2456
`eval_sh_chebyt` (*in module scipy.special*), 2466
`eval_sh_chebyu` (*in module scipy.special*), 2467
`eval_sh_jacobi` (*in module scipy.special*), 2468
`eval_sh_legendre` (*in module scipy.special*), 2466
`evaluate()` (*scipy.stats.gaussian_kde method*), 3080
`excitingmixing()` (*in module scipy.optimize*), 1746
`exp1` (*in module scipy.special*), 2520
`exp10` (*in module scipy.special*), 2531
`exp2` (*in module scipy.special*), 2532
`expect()` (*scipy.stats.rv_continuous method*), 2549
`expect()` (*scipy.stats.rv_discrete method*), 2561
`expect()` (*scipy.stats.rv_histogram method*), 2568
`expected_freq()` (*in module scipy.stats.contingency*), 3021
`expi` (*in module scipy.special*), 2521
`expit` (*in module scipy.special*), 2411
`expm()` (*in module scipy.linalg*), 1052
`expm()` (*in module scipy.sparse.linalg*), 2163
`expm1` (*in module scipy.special*), 2536
`expm1()` (*scipy.sparse.bsr_matrix method*), 2018
`expm1()` (*scipy.sparse.coo_matrix method*), 2037
`expm1()` (*scipy.sparse.csc_matrix method*), 2055
`expm1()` (*scipy.sparse.csr_matrix method*), 2074
`expm1()` (*scipy.sparse.dia_matrix method*), 2091
`expm_cond()` (*in module scipy.linalg*), 1061
`expm_frechet()` (*in module scipy.linalg*), 1060
`expm_multiply()` (*in module scipy.sparse.linalg*), 2163
`expn` (*in module scipy.special*), 2518
`expon` (*in module scipy.stats*), 2621
`exponential` (*in module scipy.odr*), 1588
`exponnorm` (*in module scipy.stats*), 2623
`exponpow` (*in module scipy.stats*), 2628
`exponweib` (*in module scipy.stats*), 2626
`exprel` (*in module scipy.special*), 2540
`extend()` (*scipy.interpolate.BPoly method*), 860
`extend()` (*scipy.interpolate.PPoly method*), 857
`extrema()` (*in module scipy.ndimage*), 1532
`eye()` (*in module scipy.sparse*), 2137

F

- `f` (in module `scipy.stats`), 2631
- `f_oneway` () (in module `scipy.stats`), 2934
- `f_oneway` () (in module `scipy.stats.mstats`), 3052
- `F_onewayBadInputSizesWarning`, 3084
- `F_onewayConstantInputWarning`, 3084
- `face` () (in module `scipy.misc`), 1471
- `factorial` () (in module `scipy.special`), 2523
- `factorial2` () (in module `scipy.special`), 2523
- `factorialk` () (in module `scipy.special`), 2524
- `factorized` () (in module `scipy.sparse.linalg`), 2169
- `fatiguelife` (in module `scipy.stats`), 2633
- `fcluster` () (in module `scipy.cluster.hierarchy`), 628
- `fclusterdata` () (in module `scipy.cluster.hierarchy`), 631
- `fdtr` (in module `scipy.special`), 2378
- `fdtrc` (in module `scipy.special`), 2379
- `fdtri` (in module `scipy.special`), 2380
- `fdtridfd` (in module `scipy.special`), 2380
- `fft` () (in module `scipy.fft`), 696
- `fft` () (in module `scipy.fftpack`), 741
- `fft2` () (in module `scipy.fft`), 701
- `fft2` () (in module `scipy.fftpack`), 743
- `fftconvolve` () (in module `scipy.signal`), 1760
- `fftfreq` () (in module `scipy.fft`), 735
- `fftfreq` () (in module `scipy.fftpack`), 763
- `fftn` () (in module `scipy.fft`), 705
- `fftn` () (in module `scipy.fftpack`), 744
- `fftshift` () (in module `scipy.fft`), 733
- `fftshift` () (in module `scipy.fftpack`), 761
- `fiedler` () (in module `scipy.linalg`), 1078
- `fiedler_companion` () (in module `scipy.linalg`), 1079
- `filename` (`scipy.io.arff.ArffError` attribute), 973
- `filename` (`scipy.io.arff.ParseArffError` attribute), 974
- `filename` (`scipy.io.FortranEOFError` attribute), 960
- `filename` (`scipy.io.FortranFormattingError` attribute), 960
- `filename2` (`scipy.io.arff.ArffError` attribute), 973
- `filename2` (`scipy.io.arff.ParseArffError` attribute), 974
- `filename2` (`scipy.io.FortranEOFError` attribute), 960
- `filename2` (`scipy.io.FortranFormattingError` attribute), 960
- `filtfilt` () (in module `scipy.signal`), 1791
- `find` () (in module `scipy.constants`), 682
- `find` () (in module `scipy.sparse`), 2149
- `find_best_blas_type` () (in module `scipy.linalg`), 1090
- `find_best_blas_type` () (in module `scipy.linalg.blas`), 1093
- `find_objects` () (in module `scipy.ndimage`), 1533
- `find_peaks` () (in module `scipy.signal`), 1970
- `find_peaks_cwt` () (in module `scipy.signal`), 1975
- `find_repeats` () (in module `scipy.stats`), 2905
- `find_repeats` () (in module `scipy.stats.mstats`), 3048
- `find_simplex` () (`scipy.spatial.Delaunay` method), 2263
- `findfreqs` () (in module `scipy.signal`), 1814
- `firls` () (in module `scipy.signal`), 1815
- `firwin` () (in module `scipy.signal`), 1817
- `firwin2` () (in module `scipy.signal`), 1819
- `fisher_exact` () (in module `scipy.stats`), 3023
- `fisk` (in module `scipy.stats`), 2636
- `fit` () (`scipy.stats.rv_continuous` method), 2553
- `fit` () (`scipy.stats.rv_histogram` method), 2569
- `fit_loc_scale` () (`scipy.stats.rv_continuous` method), 2554
- `fit_loc_scale` () (`scipy.stats.rv_histogram` method), 2571
- `fixed_point` () (in module `scipy.optimize`), 1668
- `fixed_quad` () (in module `scipy.integrate`), 778
- `fligner` () (in module `scipy.stats`), 2989
- `floor` () (`scipy.sparse.bsr_matrix` method), 2018
- `floor` () (`scipy.sparse.coo_matrix` method), 2037
- `floor` () (`scipy.sparse.csc_matrix` method), 2055
- `floor` () (`scipy.sparse.csr_matrix` method), 2074
- `floor` () (`scipy.sparse.dia_matrix` method), 2091
- `floyd_warshall` () (in module `scipy.sparse.csgraph`), 2208
- `flush` () (`scipy.io.netcdf_file` method), 964
- `fmin` () (in module `scipy.optimize`), 1718
- `fmin_bfgs` () (in module `scipy.optimize`), 1724
- `fmin_cg` () (in module `scipy.optimize`), 1721
- `fmin_cobyla` () (in module `scipy.optimize`), 1730
- `fmin_l_bfgs_b` () (in module `scipy.optimize`), 1726
- `fmin_ncg` () (in module `scipy.optimize`), 1725
- `fmin_powell` () (in module `scipy.optimize`), 1720
- `fmin_slsqp` () (in module `scipy.optimize`), 1731
- `fmin_tnc` () (in module `scipy.optimize`), 1728
- `fminbound` () (in module `scipy.optimize`), 1733
- `foldcauchy` (in module `scipy.stats`), 2638
- `foldnorm` (in module `scipy.stats`), 2641
- `FortranEOFError`, 960
- `FortranFile` (class in `scipy.io`), 956
- `FortranFormattingError`, 960
- `fourier_ellipsoid` () (in module `scipy.ndimage`), 1512
- `fourier_gaussian` () (in module `scipy.ndimage`), 1512
- `fourier_shift` () (in module `scipy.ndimage`), 1514
- `fourier_uniform` () (in module `scipy.ndimage`), 1515
- `fractional_matrix_power` () (in module `scipy.linalg`), 1062
- `freeze` () (`scipy.stats.rv_histogram` method), 2571
- `freqresp` () (in module `scipy.signal`), 1918
- `freqresp` () (`scipy.signal.dlti` method), 1924
- `freqresp` () (`scipy.signal.lti` method), 1900

- freqs () (in module *scipy.signal*), 1820
 freqs_zpk () (in module *scipy.signal*), 1821
 freqz () (in module *scipy.signal*), 1823
 freqz_zpk () (in module *scipy.signal*), 1827
 fresnel (in module *scipy.special*), 2445
 fresnel_zeros () (in module *scipy.special*), 2446
 fresnelc_zeros () (in module *scipy.special*), 2448
 fresnels_zeros () (in module *scipy.special*), 2448
 friedmanchisquare () (in module *scipy.stats*), 2978
 friedmanchisquare () (in module *scipy.stats.mstats*), 3065
 from_bernstein_basis () (*scipy.interpolate.PPoly* class method), 858
 from_cython () (*scipy.LowLevelCallable* class method), 3086
 from_derivatives () (*scipy.interpolate.BPoly* class method), 862
 from_mlab_linkage () (in module *scipy.cluster.hierarchy*), 651
 from_power_basis () (*scipy.interpolate.BPoly* class method), 861
 from_spline () (*scipy.interpolate.PPoly* class method), 857
 fromkeys () (*scipy.optimize.OptimizeResult* method), 1595
 fromkeys () (*scipy.sparse.dok_matrix* method), 2106
 fsolve () (in module *scipy.optimize*), 1738
 funm () (in module *scipy.linalg*), 1059
- ## G
- gamma (in module *scipy.special*), 2419
 gamma (in module *scipy.stats*), 2658
 gammainc (in module *scipy.special*), 2424
 gammaincc (in module *scipy.special*), 2426
 gammainccinv (in module *scipy.special*), 2427
 gammaincinv (in module *scipy.special*), 2425
 gammaln (in module *scipy.special*), 2420
 gammasgn (in module *scipy.special*), 2423
 gammatone () (in module *scipy.signal*), 1831
 gauss_spline () (in module *scipy.signal*), 1774
 gausshyper (in module *scipy.stats*), 2656
 gaussian_filter () (in module *scipy.ndimage*), 1482
 gaussian_filter1d () (in module *scipy.ndimage*), 1483
 gaussian_gradient_magnitude () (in module *scipy.ndimage*), 1485
 gaussian_kde (class in *scipy.stats*), 3077
 gaussian_laplace () (in module *scipy.ndimage*), 1487
 gausspulse () (in module *scipy.signal*), 1949
 gcrotmk () (in module *scipy.sparse.linalg*), 2179
 gdtr (in module *scipy.special*), 2380
 gdtrc (in module *scipy.special*), 2381
 gdtria (in module *scipy.special*), 2382
 gdtrib (in module *scipy.special*), 2383
 gdtrix (in module *scipy.special*), 2384
 gegenbauer () (in module *scipy.special*), 2483
 generate_binary_structure () (in module *scipy.ndimage*), 1565
 generic_filter () (in module *scipy.ndimage*), 1489
 generic_filter1d () (in module *scipy.ndimage*), 1490
 generic_gradient_magnitude () (in module *scipy.ndimage*), 1492
 generic_laplace () (in module *scipy.ndimage*), 1493
 genexpon (in module *scipy.stats*), 2651
 genextreme (in module *scipy.stats*), 2653
 gengamma (in module *scipy.stats*), 2661
 genhalflogistic (in module *scipy.stats*), 2664
 geninvgauss (in module *scipy.stats*), 2667
 genlaguerre () (in module *scipy.special*), 2481
 genlogistic (in module *scipy.stats*), 2643
 gennorm (in module *scipy.stats*), 2646
 genpareto (in module *scipy.stats*), 2648
 geom (in module *scipy.stats*), 2865
 geometric_slerp () (in module *scipy.spatial*), 2285
 geometric_transform () (in module *scipy.ndimage*), 1518
 get () (*scipy.optimize.OptimizeResult* method), 1595
 get () (*scipy.sparse.dok_matrix* method), 2106
 get_blas_funcs () (in module *scipy.linalg*), 1088
 get_blas_funcs () (in module *scipy.linalg.blas*), 1092
 get_coeffs () (*scipy.interpolate.BivariateSpline* method), 931
 get_coeffs () (*scipy.interpolate.InterpolatedUnivariateSpline* method), 916
 get_coeffs () (*scipy.interpolate.LSQBivariateSpline* method), 940
 get_coeffs () (*scipy.interpolate.LSQSphereBivariateSpline* method), 944
 get_coeffs () (*scipy.interpolate.LSQUnivariateSpline* method), 922
 get_coeffs () (*scipy.interpolate.RectBivariateSpline* method), 880
 get_coeffs () (*scipy.interpolate.RectSphereBivariateSpline* method), 929
 get_coeffs () (*scipy.interpolate.SmoothBivariateSpline* method), 933
 get_coeffs () (*scipy.interpolate.SmoothSphereBivariateSpline* method), 937
 get_coeffs () (*scipy.interpolate.UnivariateSpline*

method), 911
 get_count() (*scipy.cluster.hierarchy.ClusterNode method*), 663
 get_id() (*scipy.cluster.hierarchy.ClusterNode method*), 664
 get_knots() (*scipy.interpolate.BivariateSpline method*), 931
 get_knots() (*scipy.interpolate.InterpolatedUnivariateSpline method*), 916
 get_knots() (*scipy.interpolate.LSQBivariateSpline method*), 940
 get_knots() (*scipy.interpolate.LSQSphereBivariateSpline method*), 944
 get_knots() (*scipy.interpolate.LSQUnivariateSpline method*), 923
 get_knots() (*scipy.interpolate.RectBivariateSpline method*), 880
 get_knots() (*scipy.interpolate.RectSphereBivariateSpline method*), 929
 get_knots() (*scipy.interpolate.SmoothBivariateSpline method*), 933
 get_knots() (*scipy.interpolate.SmoothSphereBivariateSpline method*), 937
 get_knots() (*scipy.interpolate.UnivariateSpline method*), 911
 get_lapack_funcs() (*in module scipy.linalg*), 1089
 get_lapack_funcs() (*in module scipy.linalg.lapack*), 1157
 get_left() (*scipy.cluster.hierarchy.ClusterNode method*), 664
 get_matrix() (*scipy.optimize.BFGS method*), 1617
 get_matrix() (*scipy.optimize.HessianUpdateStrategy method*), 1714
 get_matrix() (*scipy.optimize.SR1 method*), 1619
 get_residual() (*scipy.interpolate.BivariateSpline method*), 931
 get_residual() (*scipy.interpolate.InterpolatedUnivariateSpline method*), 917
 get_residual() (*scipy.interpolate.LSQBivariateSpline method*), 940
 get_residual() (*scipy.interpolate.LSQSphereBivariateSpline method*), 944
 get_residual() (*scipy.interpolate.LSQUnivariateSpline method*), 923
 get_residual() (*scipy.interpolate.RectBivariateSpline method*), 880
 get_residual() (*scipy.interpolate.RectSphereBivariateSpline method*), 929
 get_residual() (*scipy.interpolate.SmoothBivariateSpline method*), 934
 get_residual() (*scipy.interpolate.SmoothSphereBivariateSpline method*), 937
 get_residual() (*scipy.interpolate.UnivariateSpline method*), 911
 get_return_code() (*scipy.integrate.complex_ode method*), 820
 get_return_code() (*scipy.integrate.ode method*), 816
 get_right() (*scipy.cluster.hierarchy.ClusterNode method*), 664
 get_shape() (*scipy.sparse.bsr_matrix method*), 2019
 get_shape() (*scipy.sparse.coo_matrix method*), 2037
 get_shape() (*scipy.sparse.csc_matrix method*), 2056
 get_shape() (*scipy.sparse.csr_matrix method*), 2075
 get_shape() (*scipy.sparse.dia_matrix method*), 2092
 get_shape() (*scipy.sparse.dok_matrix method*), 2106
 get_shape() (*scipy.sparse.lil_matrix method*), 2119
 get_shape() (*scipy.sparse.spmatrix method*), 2130
 get_window() (*in module scipy.signal*), 1959
 get_workers() (*in module scipy.fftpack*), 737
 getcol() (*scipy.sparse.bsr_matrix method*), 2019
 getcol() (*scipy.sparse.coo_matrix method*), 2037
 getcol() (*scipy.sparse.csc_matrix method*), 2056
 getcol() (*scipy.sparse.csr_matrix method*), 2075
 getcol() (*scipy.sparse.dia_matrix method*), 2092
 getcol() (*scipy.sparse.dok_matrix method*), 2106
 getcol() (*scipy.sparse.lil_matrix method*), 2119
 getcol() (*scipy.sparse.spmatrix method*), 2130
 geterr() (*in module scipy.special*), 2315
 getformat() (*scipy.sparse.bsr_matrix method*), 2019
 getformat() (*scipy.sparse.coo_matrix method*), 2038
 getformat() (*scipy.sparse.csc_matrix method*), 2056
 getformat() (*scipy.sparse.csr_matrix method*), 2075
 getformat() (*scipy.sparse.dia_matrix method*), 2092
 getformat() (*scipy.sparse.dok_matrix method*), 2106
 getformat() (*scipy.sparse.lil_matrix method*), 2119
 getformat() (*scipy.sparse.spmatrix method*), 2130
 getH() (*scipy.sparse.bsr_matrix method*), 2019
 getH() (*scipy.sparse.coo_matrix method*), 2037
 getH() (*scipy.sparse.csc_matrix method*), 2055
 getH() (*scipy.sparse.csr_matrix method*), 2075
 getH() (*scipy.sparse.dia_matrix method*), 2091
 getH() (*scipy.sparse.dok_matrix method*), 2106
 getH() (*scipy.sparse.lil_matrix method*), 2118
 getH() (*scipy.sparse.spmatrix method*), 2129
 getmaxprint() (*scipy.sparse.bsr_matrix method*), 2019

- getmaxprint () (*scipy.sparse.coo_matrix method*), 2038
 getmaxprint () (*scipy.sparse.csc_matrix method*), 2056
 getmaxprint () (*scipy.sparse.csr_matrix method*), 2075
 getmaxprint () (*scipy.sparse.dia_matrix method*), 2092
 getmaxprint () (*scipy.sparse.dok_matrix method*), 2106
 getmaxprint () (*scipy.sparse.lil_matrix method*), 2119
 getmaxprint () (*scipy.sparse.spmatrix method*), 2130
 getnnz () (*scipy.sparse.bsr_matrix method*), 2019
 getnnz () (*scipy.sparse.coo_matrix method*), 2038
 getnnz () (*scipy.sparse.csc_matrix method*), 2056
 getnnz () (*scipy.sparse.csr_matrix method*), 2075
 getnnz () (*scipy.sparse.dia_matrix method*), 2092
 getnnz () (*scipy.sparse.dok_matrix method*), 2107
 getnnz () (*scipy.sparse.lil_matrix method*), 2119
 getnnz () (*scipy.sparse.spmatrix method*), 2130
 getrow () (*scipy.sparse.bsr_matrix method*), 2020
 getrow () (*scipy.sparse.coo_matrix method*), 2038
 getrow () (*scipy.sparse.csc_matrix method*), 2056
 getrow () (*scipy.sparse.csr_matrix method*), 2076
 getrow () (*scipy.sparse.dia_matrix method*), 2092
 getrow () (*scipy.sparse.dok_matrix method*), 2107
 getrow () (*scipy.sparse.lil_matrix method*), 2119
 getrow () (*scipy.sparse.spmatrix method*), 2130
 getrowview () (*scipy.sparse.lil_matrix method*), 2120
 getValue () (*scipy.io.netcdf_variable method*), 966
 gilbrat (*in module scipy.stats*), 2669
 gmean () (*in module scipy.stats*), 2891
 gmean () (*in module scipy.stats.mstats*), 3035
 gmres () (*in module scipy.sparse.linalg*), 2174
 golden () (*in module scipy.optimize*), 1735
 gompertz (*in module scipy.stats*), 2672
 grey_closing () (*in module scipy.ndimage*), 1567
 grey_dilation () (*in module scipy.ndimage*), 1568
 grey_erosion () (*in module scipy.ndimage*), 1570
 grey_opening () (*in module scipy.ndimage*), 1572
 griddata () (*in module scipy.interpolate*), 863
 group_delay () (*in module scipy.signal*), 1833
 gstd () (*in module scipy.stats*), 2907
 gumbel_l (*in module scipy.stats*), 2677
 gumbel_r (*in module scipy.stats*), 2674
- ## H
- h1vp () (*in module scipy.special*), 2362
 h2vp () (*in module scipy.special*), 2362
 hadamard () (*in module scipy.linalg*), 1080
 halfcauchy (*in module scipy.stats*), 2679
 halfgennorm (*in module scipy.stats*), 2687
 halflogistic (*in module scipy.stats*), 2682
 halfnorm (*in module scipy.stats*), 2684
 HalfspaceIntersection (*class in scipy.spatial*), 2273
 hamming () (*in module scipy.spatial.distance*), 2309
 hankel () (*in module scipy.linalg*), 1081
 hankel1 (*in module scipy.special*), 2339
 hankel1e (*in module scipy.special*), 2340
 hankel2 (*in module scipy.special*), 2340
 hankel2e (*in module scipy.special*), 2341
 hb_read () (*in module scipy.io*), 966
 hb_write () (*in module scipy.io*), 967
 hdmedian () (*in module scipy.stats.mstats*), 3040
 hdquantiles () (*in module scipy.stats.mstats*), 3040
 hdquantiles_sd () (*in module scipy.stats.mstats*), 3041
 helmert () (*in module scipy.linalg*), 1081
 hermite () (*in module scipy.special*), 2482
 hermitenorm () (*in module scipy.special*), 2482
 hessenberg () (*in module scipy.linalg*), 1048
 HessianUpdateStrategy (*class in scipy.optimize*), 1714
 hfft () (*in module scipy.fftfreq*), 717
 hfft2 () (*in module scipy.fftfreq*), 719
 hfftn () (*in module scipy.fftfreq*), 720
 hilbert () (*in module scipy.fftpack*), 758
 hilbert () (*in module scipy.linalg*), 1082
 hilbert () (*in module scipy.signal*), 1800
 hilbert2 () (*in module scipy.signal*), 1802
 histogram () (*in module scipy.ndimage*), 1534
 hmean () (*in module scipy.stats*), 2892
 hmean () (*in module scipy.stats.mstats*), 3036
 hstack () (*in module scipy.sparse*), 2144
 huber (*in module scipy.special*), 2418
 hyp0f1 (*in module scipy.special*), 2489
 hyp1f1 (*in module scipy.special*), 2487
 hyp2f1 (*in module scipy.special*), 2485
 hypergeom (*in module scipy.stats*), 2867
 hyperu (*in module scipy.special*), 2488
 hypsecant (*in module scipy.stats*), 2689
- ## I
- i0 (*in module scipy.special*), 2351
 i0e (*in module scipy.special*), 2352
 i1 (*in module scipy.special*), 2353
 i1e (*in module scipy.special*), 2353
 icamax (*in module scipy.linalg.blas*), 1102
 id_to_svd () (*in module scipy.linalg.interpolative*), 1462
 idamax (*in module scipy.linalg.blas*), 1103
 idct () (*in module scipy.fftfreq*), 726
 idct () (*in module scipy.fftpack*), 750
 idctn () (*in module scipy.fftfreq*), 728
 idctn () (*in module scipy.fftpack*), 752
 idealfourths () (*in module scipy.stats.mstats*), 3041
 identity () (*in module scipy.sparse*), 2137

- idst()* (in module *scipy.fft*), 730
idst() (in module *scipy.fftpack*), 754
idstn() (in module *scipy.fft*), 732
idstn() (in module *scipy.fftpack*), 756
ifft() (in module *scipy.fft*), 699
ifft() (in module *scipy.fftpack*), 742
ifft2() (in module *scipy.fft*), 703
ifft2() (in module *scipy.fftpack*), 744
ifftn() (in module *scipy.fft*), 706
ifftn() (in module *scipy.fftpack*), 745
ifftshift() (in module *scipy.fft*), 734
ifftshift() (in module *scipy.fftpack*), 762
ihfft() (in module *scipy.fft*), 718
ihfft2() (in module *scipy.fft*), 720
ihfftn() (in module *scipy.fft*), 722
ihilbert() (in module *scipy.fftpack*), 759
iircomb() (in module *scipy.signal*), 1894
iirdesign() (in module *scipy.signal*), 1835
iirfilter() (in module *scipy.signal*), 1837
iirnotch() (in module *scipy.signal*), 1890
iirpeak() (in module *scipy.signal*), 1892
ilaver() (in module *scipy.linalg.lapack*), 1412
impulse() (in module *scipy.signal*), 1913
impulse() (*scipy.signal.dlti* method), 1926
impulse() (*scipy.signal.lti* method), 1901
impulse2() (in module *scipy.signal*), 1914
inconsistent() (in module *scipy.cluster.hierarchy*), 652
init_convolution_kernel() (in module *scipy.fftpack.convolve*), 766
initialize() (*scipy.optimize.BFGS* method), 1617
initialize() (*scipy.optimize.HessianUpdateStrategy* method), 1715
initialize() (*scipy.optimize.SR1* method), 1619
insert() (in module *scipy.interpolate*), 904
integral() (*scipy.interpolate.BivariateSpline* method), 931
integral() (*scipy.interpolate.InterpolatedUnivariateSpline* method), 917
integral() (*scipy.interpolate.LSQBivariateSpline* method), 940
integral() (*scipy.interpolate.LSQUnivariateSpline* method), 923
integral() (*scipy.interpolate.RectBivariateSpline* method), 880
integral() (*scipy.interpolate.SmoothBivariateSpline* method), 934
integral() (*scipy.interpolate.UnivariateSpline* method), 911
integrate() (*scipy.integrate.complex_ode* method), 821
integrate() (*scipy.integrate.ode* method), 818
integrate() (*scipy.interpolate.BPoly* method), 861
integrate() (*scipy.interpolate.BSpline* method), 888
integrate() (*scipy.interpolate.CubicHermiteSpline* method), 841
integrate() (*scipy.interpolate.CubicSpline* method), 852
integrate() (*scipy.interpolate.NdPPoly* method), 883
integrate() (*scipy.interpolate.PPoly* method), 856
integrate_1d() (*scipy.interpolate.NdPPoly* method), 883
integrate_box() (*scipy.stats.gaussian_kde* method), 3081
integrate_box_1d() (*scipy.stats.gaussian_kde* method), 3081
integrate_gaussian() (*scipy.stats.gaussian_kde* method), 3080
integrate_kde() (*scipy.stats.gaussian_kde* method), 3081
IntegrationWarning, 784
interp1d (class in *scipy.interpolate*), 828
interp2d (class in *scipy.interpolate*), 872
interp_decomp() (in module *scipy.linalg.interpolative*), 1459
interp_n() (in module *scipy.interpolate*), 875
InterpolatedUnivariateSpline (class in *scipy.interpolate*), 912
interval() (*scipy.stats.rv_continuous* method), 2552
interval() (*scipy.stats.rv_discrete* method), 2564
interval() (*scipy.stats.rv_histogram* method), 2571
inv() (in module *scipy.linalg*), 975
inv() (in module *scipy.sparse.linalg*), 2162
inv_boxcox (in module *scipy.special*), 2414
inv_boxcox1p (in module *scipy.special*), 2414
invgamma (in module *scipy.stats*), 2692
invgauss (in module *scipy.stats*), 2694
invhilbert() (in module *scipy.linalg*), 1083
invpascal() (in module *scipy.linalg*), 1085
invres() (in module *scipy.signal*), 1854
invresz() (in module *scipy.signal*), 1855
invweibull (in module *scipy.stats*), 2697
invwishart (in module *scipy.stats*), 2841
iqr() (in module *scipy.stats*), 2908
irfft() (in module *scipy.fft*), 710
irfft() (in module *scipy.fftpack*), 747
irfft2() (in module *scipy.fft*), 713
irfftn() (in module *scipy.fft*), 715
is_isomorphic() (in module *scipy.cluster.hierarchy*), 672
is_leaf() (*scipy.cluster.hierarchy.ClusterNode* method), 665
is_monotonic() (in module *scipy.cluster.hierarchy*), 673
is_valid_dm() (in module *scipy.spatial.distance*), 2298

is_valid_im() (in module *scipy.cluster.hierarchy*), 669
 is_valid_linkage() (in module *scipy.cluster.hierarchy*), 670
 is_valid_y() (in module *scipy.spatial.distance*), 2299
 isamax (in module *scipy.linalg.blas*), 1103
 isf() (*scipy.stats.rv_continuous* method), 2548
 isf() (*scipy.stats.rv_discrete* method), 2560
 isf() (*scipy.stats.rv_histogram* method), 2572
 issparse() (in module *scipy.sparse*), 2150
 isspmatrix() (in module *scipy.sparse*), 2150
 isspmatrix_bsr() (in module *scipy.sparse*), 2152
 isspmatrix_coo() (in module *scipy.sparse*), 2153
 isspmatrix_csc() (in module *scipy.sparse*), 2151
 isspmatrix_csr() (in module *scipy.sparse*), 2151
 isspmatrix_dia() (in module *scipy.sparse*), 2154
 isspmatrix_dok() (in module *scipy.sparse*), 2153
 isspmatrix_lil() (in module *scipy.sparse*), 2152
 istft() (in module *scipy.signal*), 2003
 it2i0k0 (in module *scipy.special*), 2358
 it2j0y0 (in module *scipy.special*), 2357
 it2struve0 (in module *scipy.special*), 2369
 itairy (in module *scipy.special*), 2323
 itemfreq() (in module *scipy.stats*), 2920
 items() (*scipy.optimize.OptimizeResult* method), 1595
 items() (*scipy.sparse.dok_matrix* method), 2107
 itemsize() (*scipy.io.netcdf_variable* method), 966
 iterate_structure() (in module *scipy.ndimage*), 1573
 iti0k0 (in module *scipy.special*), 2358
 itilbert() (in module *scipy.fftpack*), 758
 itj0y0 (in module *scipy.special*), 2357
 itmodstruve0 (in module *scipy.special*), 2370
 itstruve0 (in module *scipy.special*), 2369
 iv (in module *scipy.special*), 2338
 ive (in module *scipy.special*), 2338
 ivp() (in module *scipy.special*), 2361
 izamax (in module *scipy.linalg.blas*), 1103

J

j0 (in module *scipy.special*), 2349
 j1 (in module *scipy.special*), 2349
 jaccard() (in module *scipy.spatial.distance*), 2310
 jacobi() (in module *scipy.special*), 2480
 jarque_bera() (in module *scipy.stats*), 2980
 jensenshannon() (in module *scipy.spatial.distance*), 2304
 jn_zeros() (in module *scipy.special*), 2344
 jnjnp_zeros() (in module *scipy.special*), 2343
 jnp_zeros() (in module *scipy.special*), 2345
 jnyn_zeros() (in module *scipy.special*), 2343
 johnson() (in module *scipy.sparse.csgraph*), 2211
 johnsonsb (in module *scipy.stats*), 2699
 johnsonsu (in module *scipy.stats*), 2702

jv (in module *scipy.special*), 2331
 jve (in module *scipy.special*), 2331
 jvp() (in module *scipy.special*), 2359

K

k0 (in module *scipy.special*), 2354
 k0e (in module *scipy.special*), 2355
 k1 (in module *scipy.special*), 2355
 k1e (in module *scipy.special*), 2356
 kaiser_atten() (in module *scipy.signal*), 1839
 kaiser_beta() (in module *scipy.signal*), 1840
 kaiserord() (in module *scipy.signal*), 1841
 kappa3 (in module *scipy.stats*), 2708
 kappa4 (in module *scipy.stats*), 2704
 KDTree (class in *scipy.spatial*), 2236
 kei (in module *scipy.special*), 2505
 kei_zeros() (in module *scipy.special*), 2509
 keip (in module *scipy.special*), 2506
 keip_zeros() (in module *scipy.special*), 2509
 kelvin (in module *scipy.special*), 2500
 kelvin_zeros() (in module *scipy.special*), 2501
 kendalltau() (in module *scipy.stats*), 2940
 kendalltau() (in module *scipy.stats.mstats*), 3054
 kendalltau_seasonal() (in module *scipy.stats.mstats*), 3055
 ker (in module *scipy.special*), 2504
 ker_zeros() (in module *scipy.special*), 2508
 kerp (in module *scipy.special*), 2506
 kerp_zeros() (in module *scipy.special*), 2509
 keys() (*scipy.optimize.OptimizeResult* method), 1595
 keys() (*scipy.sparse.dok_matrix* method), 2107
 khatri_rao() (in module *scipy.linalg*), 995
 kl_div (in module *scipy.special*), 2417
 kmeans() (in module *scipy.cluster.vq*), 623
 kmeans2() (in module *scipy.cluster.vq*), 625
 kn (in module *scipy.special*), 2334
 kolmogi (in module *scipy.special*), 2409
 kolmogorov (in module *scipy.special*), 2407
 krogh_interpolate() (in module *scipy.interpolate*), 835
 KroghInterpolator (class in *scipy.interpolate*), 832
 kron() (in module *scipy.linalg*), 994
 kron() (in module *scipy.sparse*), 2138
 kronsum() (in module *scipy.sparse*), 2138
 kruskal() (in module *scipy.stats*), 2976
 kruskal() (in module *scipy.stats.mstats*), 3063
 kruskalwallis() (in module *scipy.stats.mstats*), 3064
 ks_1samp() (in module *scipy.stats*), 2967
 ks_1samp() (in module *scipy.stats.mstats*), 3062
 ks_2samp() (in module *scipy.stats*), 2969
 ks_2samp() (in module *scipy.stats.mstats*), 3061
 ks_twosamp() (in module *scipy.stats.mstats*), 3062
 ksone (in module *scipy.stats*), 2710
 kstat() (in module *scipy.stats*), 2898

kstatvar() (in module *scipy.stats*), 2899
 kstest() (in module *scipy.stats*), 2965
 kstest() (in module *scipy.stats.mstats*), 3061
 kstwo (in module *scipy.stats*), 2713
 kstwobign (in module *scipy.stats*), 2716
 kulsinski() (in module *scipy.spatial.distance*), 2311
 kurtosis() (in module *scipy.stats*), 2893
 kurtosis() (in module *scipy.stats.mstats*), 3037
 kurtosistest() (in module *scipy.stats*), 2995
 kurtosistest() (in module *scipy.stats.mstats*), 3066
 kv (in module *scipy.special*), 2335
 kve (in module *scipy.special*), 2337
 kvp() (in module *scipy.special*), 2360

L

label() (in module *scipy.ndimage*), 1535
 labeled_comprehension() (in module *scipy.ndimage*), 1537
 lagrange() (in module *scipy.interpolate*), 946
 laguerre() (in module *scipy.special*), 2481
 lambda2nu() (in module *scipy.constants*), 695
 lambertw() (in module *scipy.special*), 2511
 laplace (in module *scipy.stats*), 2719
 laplace() (in module *scipy.ndimage*), 1494
 laplace_asymmetric (in module *scipy.stats*), 2722
 laplacian() (in module *scipy.sparse.csgraph*), 2204
 LbfgsInvHessProduct (class in *scipy.optimize*), 1710
 ldl() (in module *scipy.linalg*), 1024
 leaders() (in module *scipy.cluster.hierarchy*), 632
 least_squares() (in module *scipy.optimize*), 1638
 leastsq() (in module *scipy.optimize*), 1736
 leaves_list() (in module *scipy.cluster.hierarchy*), 665
 legendre() (in module *scipy.special*), 2478
 leslie() (in module *scipy.linalg*), 1084
 levene() (in module *scipy.stats*), 2984
 levy (in module *scipy.stats*), 2724
 levy_l (in module *scipy.stats*), 2727
 levy_stable (in module *scipy.stats*), 2729
 lfilter() (in module *scipy.signal*), 1786
 lfilter_zi() (in module *scipy.signal*), 1790
 lfiltic() (in module *scipy.signal*), 1789
 lgmres() (in module *scipy.sparse.linalg*), 2176
 lift_points() (*scipy.spatial.Delaunay* method), 2263
 lil_matrix (class in *scipy.sparse*), 2113
 LinAlgError, 1000
 LinAlgWarning, 1001
 line_search() (in module *scipy.optimize*), 1709
 linear_sum_assignment() (in module *scipy.optimize*), 1698
 LinearConstraint (class in *scipy.optimize*), 1615
 linearmixing() (in module *scipy.optimize*), 1747

LinearNDInterpolator (class in *scipy.interpolate*), 866
 LinearOperator (class in *scipy.sparse.linalg*), 2157
 linkage() (in module *scipy.cluster.hierarchy*), 634
 linprog() (in module *scipy.optimize*), 1678
 linprog_verbose_callback() (in module *scipy.optimize*), 1698
 linregress() (in module *scipy.stats*), 2944
 linregress() (in module *scipy.stats.mstats*), 3055
 lmbda() (in module *scipy.special*), 2342
 load_npz() (in module *scipy.sparse*), 2148
 loadarff() (in module *scipy.io.arff*), 971
 loadmat() (in module *scipy.io*), 950
 lobpcg() (in module *scipy.sparse.linalg*), 2191
 log1p (in module *scipy.special*), 2535
 log1p() (*scipy.sparse.bsr_matrix* method), 2020
 log1p() (*scipy.sparse.coo_matrix* method), 2038
 log1p() (*scipy.sparse.csc_matrix* method), 2057
 log1p() (*scipy.sparse.csr_matrix* method), 2076
 log1p() (*scipy.sparse.dia_matrix* method), 2093
 log_ndtr (in module *scipy.special*), 2403
 log_softmax() (in module *scipy.special*), 2527
 logcdf() (*scipy.stats.rv_continuous* method), 2547
 logcdf() (*scipy.stats.rv_discrete* method), 2559
 logcdf() (*scipy.stats.rv_histogram* method), 2572
 loggamma (in module *scipy.special*), 2422
 loggamma (in module *scipy.stats*), 2735
 logistic (in module *scipy.stats*), 2733
 logit (in module *scipy.special*), 2410
 loglaplace (in module *scipy.stats*), 2738
 logm() (in module *scipy.linalg*), 1053
 lognorm (in module *scipy.stats*), 2740
 logpdf() (*scipy.stats.gaussian_kde* method), 3082
 logpdf() (*scipy.stats.rv_continuous* method), 2546
 logpdf() (*scipy.stats.rv_histogram* method), 2572
 logpmf() (*scipy.stats.rv_discrete* method), 2558
 logser (in module *scipy.stats*), 2869
 logsf() (*scipy.stats.rv_continuous* method), 2547
 logsf() (*scipy.stats.rv_discrete* method), 2559
 logsf() (*scipy.stats.rv_histogram* method), 2573
 logsumexp() (in module *scipy.special*), 2538
 loguniform (in module *scipy.stats*), 2743
 lomax (in module *scipy.stats*), 2746
 lombscargle() (in module *scipy.signal*), 1997
 LowLevelCallable (class in *scipy*), 3085
 lp2bp() (in module *scipy.signal*), 1860
 lp2bp_zpk() (in module *scipy.signal*), 1861
 lp2bs() (in module *scipy.signal*), 1862
 lp2bs_zpk() (in module *scipy.signal*), 1863
 lp2hp() (in module *scipy.signal*), 1864
 lp2hp_zpk() (in module *scipy.signal*), 1865
 lp2lp() (in module *scipy.signal*), 1866
 lp2lp_zpk() (in module *scipy.signal*), 1867
 lpmn() (in module *scipy.special*), 2451

- lpmv (in module *scipy.special*), 2448
 lpn () (in module *scipy.special*), 2451
 lqmn () (in module *scipy.special*), 2452
 lqn () (in module *scipy.special*), 2451
 lsim () (in module *scipy.signal*), 1908
 lsim2 () (in module *scipy.signal*), 1911
 lsmr () (in module *scipy.sparse.linalg*), 2184
 LSODA (class in *scipy.integrate*), 804
 lsq_linear () (in module *scipy.optimize*), 1646
 LSQBivariateSpline (class in *scipy.interpolate*), 938
 lsqr () (in module *scipy.sparse.linalg*), 2181
 LSQSphereBivariateSpline (class in *scipy.interpolate*), 940
 LSQUnivariateSpline (class in *scipy.interpolate*), 918
 lstsq () (in module *scipy.linalg*), 989
 lti (class in *scipy.signal*), 1898
 lu () (in module *scipy.linalg*), 1016
 lu_factor () (in module *scipy.linalg*), 1017
 lu_solve () (in module *scipy.linalg*), 1018
- ## M
- mahalnobis () (in module *scipy.spatial.distance*), 2305
 make_interp_spline () (in module *scipy.interpolate*), 890
 make_lsq_spline () (in module *scipy.interpolate*), 892
 mannwhitneyu () (in module *scipy.stats*), 2971
 mannwhitneyu () (in module *scipy.stats.mstats*), 3063
 map_coordinates () (in module *scipy.ndimage*), 1521
 margins () (in module *scipy.stats.contingency*), 3022
 mathieu_a (in module *scipy.special*), 2493
 mathieu_b (in module *scipy.special*), 2493
 mathieu_cem (in module *scipy.special*), 2494
 mathieu_even_coef () (in module *scipy.special*), 2493
 mathieu_modcem1 (in module *scipy.special*), 2495
 mathieu_modcem2 (in module *scipy.special*), 2495
 mathieu_modsem1 (in module *scipy.special*), 2495
 mathieu_modsem2 (in module *scipy.special*), 2496
 mathieu_odd_coef () (in module *scipy.special*), 2494
 mathieu_sem (in module *scipy.special*), 2495
 matmat () (*scipy.optimize.LbfgsInvHessProduct* method), 1712
 matmat () (*scipy.sparse.bsr_matrix* method), 2020
 matmat () (*scipy.sparse.linalg.LinearOperator* method), 2159
 matmul_toeplitz () (in module *scipy.linalg*), 985
 matrix_balance () (in module *scipy.linalg*), 998
 matrix_normal (in module *scipy.stats*), 2835
 MatrixRankWarning, 2170
 matvec () (*scipy.optimize.LbfgsInvHessProduct* method), 1712
 matvec () (*scipy.sparse.bsr_matrix* method), 2020
 matvec () (*scipy.sparse.linalg.LinearOperator* method), 2160
 max () (*scipy.sparse.bsr_matrix* method), 2020
 max () (*scipy.sparse.coo_matrix* method), 2038
 max () (*scipy.sparse.csc_matrix* method), 2057
 max () (*scipy.sparse.csr_matrix* method), 2076
 max_distance_point () (*scipy.spatial.Rectangle* method), 2258
 max_distance_rectangle () (*scipy.spatial.Rectangle* method), 2258
 max_len_seq () (in module *scipy.signal*), 1950
 maxdists () (in module *scipy.cluster.hierarchy*), 655
 maximum () (in module *scipy.ndimage*), 1538
 maximum () (*scipy.sparse.bsr_matrix* method), 2021
 maximum () (*scipy.sparse.coo_matrix* method), 2039
 maximum () (*scipy.sparse.csc_matrix* method), 2057
 maximum () (*scipy.sparse.csr_matrix* method), 2076
 maximum () (*scipy.sparse.dia_matrix* method), 2093
 maximum () (*scipy.sparse.dok_matrix* method), 2107
 maximum () (*scipy.sparse.lil_matrix* method), 2120
 maximum () (*scipy.sparse.spmatrix* method), 2131
 maximum_bipartite_matching () (in module *scipy.sparse.csgraph*), 2221
 maximum_filter () (in module *scipy.ndimage*), 1495
 maximum_filter1d () (in module *scipy.ndimage*), 1496
 maximum_flow () (in module *scipy.sparse.csgraph*), 2219
 maximum_position () (in module *scipy.ndimage*), 1540
 maxinconsts () (in module *scipy.cluster.hierarchy*), 653
 maxRstat () (in module *scipy.cluster.hierarchy*), 656
 maxwell (in module *scipy.stats*), 2749
 mean () (in module *scipy.ndimage*), 1541
 mean () (*scipy.sparse.bsr_matrix* method), 2021
 mean () (*scipy.sparse.coo_matrix* method), 2039
 mean () (*scipy.sparse.csc_matrix* method), 2057
 mean () (*scipy.sparse.csr_matrix* method), 2077
 mean () (*scipy.sparse.dia_matrix* method), 2093
 mean () (*scipy.sparse.dok_matrix* method), 2107
 mean () (*scipy.sparse.lil_matrix* method), 2120
 mean () (*scipy.sparse.spmatrix* method), 2131
 mean () (*scipy.stats.rv_continuous* method), 2551
 mean () (*scipy.stats.rv_discrete* method), 2563
 mean () (*scipy.stats.rv_histogram* method), 2573
 medfilt () (in module *scipy.signal*), 1783
 medfilt2d () (in module *scipy.signal*), 1784
 median () (in module *scipy.cluster.hierarchy*), 645
 median () (in module *scipy.ndimage*), 1542
 median () (*scipy.stats.rv_continuous* method), 2551

- median() (*scipy.stats.rv_discrete method*), 2562
- median() (*scipy.stats.rv_histogram method*), 2573
- median_abs_deviation() (*in module scipy.stats*), 2917
- median_absolute_deviation() (*in module scipy.stats*), 2915
- median_cihs() (*in module scipy.stats.mstats*), 3076
- median_filter() (*in module scipy.ndimage*), 1498
- median_test() (*in module scipy.stats*), 2990
- meppf() (*in module scipy.stats.mstats*), 3042
- merge() (*scipy.cluster.hierarchy.DisjointSet method*), 678
- MetaData (*class in scipy.io.arff*), 972
- mielke (*in module scipy.stats*), 2751
- min() (*scipy.sparse.bsr_matrix method*), 2021
- min() (*scipy.sparse.coo_matrix method*), 2040
- min() (*scipy.sparse.csc_matrix method*), 2058
- min() (*scipy.sparse.csr_matrix method*), 2077
- min_distance_point() (*scipy.spatial.Rectangle method*), 2258
- min_distance_rectangle() (*scipy.spatial.Rectangle method*), 2258
- min_weight_full_bipartite_matching() (*in module scipy.sparse.csgraph*), 2223
- minimize() (*in module scipy.optimize*), 1599
- minimize_scalar() (*in module scipy.optimize*), 1596
- minimum() (*in module scipy.ndimage*), 1543
- minimum() (*scipy.sparse.bsr_matrix method*), 2022
- minimum() (*scipy.sparse.coo_matrix method*), 2040
- minimum() (*scipy.sparse.csc_matrix method*), 2058
- minimum() (*scipy.sparse.csr_matrix method*), 2078
- minimum() (*scipy.sparse.dia_matrix method*), 2093
- minimum() (*scipy.sparse.dok_matrix method*), 2108
- minimum() (*scipy.sparse.lil_matrix method*), 2120
- minimum() (*scipy.sparse.spmatrix method*), 2131
- minimum_filter() (*in module scipy.ndimage*), 1500
- minimum_filter1d() (*in module scipy.ndimage*), 1501
- minimum_phase() (*in module scipy.signal*), 1843
- minimum_position() (*in module scipy.ndimage*), 1544
- minimum_spanning_tree() (*in module scipy.sparse.csgraph*), 2217
- minkowski() (*in module scipy.spatial.distance*), 2305
- minkowski_distance() (*in module scipy.spatial*), 2283
- minkowski_distance_p() (*in module scipy.spatial*), 2284
- minres() (*in module scipy.sparse.linalg*), 2177
- mjci() (*in module scipy.stats.mstats*), 3076
- mminfo() (*in module scipy.io*), 955
- mmread() (*in module scipy.io*), 955
- mmwrite() (*in module scipy.io*), 956
- mode() (*in module scipy.stats*), 2894
- mode() (*in module scipy.stats.mstats*), 3038
- Model (*class in scipy.odr*), 1580
- modfresnelm (*in module scipy.special*), 2446
- modfresnelp (*in module scipy.special*), 2446
- modstruve (*in module scipy.special*), 2368
- module
 - scipy, 619
 - scipy.cluster, 621
 - scipy.cluster.hierarchy, 628
 - scipy.cluster.vq, 621
 - scipy.constants, 679
 - scipy.fft, 696
 - scipy.fftpack, 740
 - scipy.fftpack.convolve, 765
 - scipy.integrate, 766
 - scipy.interpolate, 827
 - scipy.io, 949
 - scipy.io.arff, 971
 - scipy.io.wavfile, 968
 - scipy.linalg, 974
 - scipy.linalg.blas, 1091
 - scipy.linalg.cython_blas, 1412
 - scipy.linalg.cython_lapack, 1416
 - scipy.linalg.interpolative, 1458
 - scipy.linalg.lapack, 1156
 - scipy.misc, 1468
 - scipy.ndimage, 1475
 - scipy.odr, 1577
 - scipy.optimize, 1590
 - scipy.optimize.cython_optimize, 1751
 - scipy.optimize.nonlin, 1749
 - scipy.signal, 1754
 - scipy.sparse, 2010
 - scipy.sparse.csgraph, 2202
 - scipy.sparse.linalg, 2157
 - scipy.spatial, 2235
 - scipy.spatial.distance, 2288
 - scipy.special, 2314
 - scipy.stats, 2541
 - scipy.stats.mstats, 3034
- moment() (*in module scipy.stats*), 2896
- moment() (*in module scipy.stats.mstats*), 3043
- moment() (*scipy.stats.rv_continuous method*), 2548
- moment() (*scipy.stats.rv_discrete method*), 2560
- moment() (*scipy.stats.rv_histogram method*), 2574
- mood() (*in module scipy.stats*), 2993
- morlet() (*in module scipy.signal*), 1961
- morlet2() (*in module scipy.signal*), 1963
- morphological_gradient() (*in module scipy.ndimage*), 1574
- morphological_laplace() (*in module scipy.ndimage*), 1576
- moyal (*in module scipy.stats*), 2754
- mquantiles() (*in module scipy.stats.mstats*), 3038

mquantiles_cimj() (in module *scipy.stats.mstats*), 3076
 msign() (in module *scipy.stats.mstats*), 3075
 multigammaln() (in module *scipy.special*), 2434
 multilinear (in module *scipy.odr*), 1588
 multinomial (in module *scipy.stats*), 2843
 multiply() (*scipy.sparse.bsr_matrix* method), 2022
 multiply() (*scipy.sparse.coo_matrix* method), 2040
 multiply() (*scipy.sparse.csc_matrix* method), 2059
 multiply() (*scipy.sparse.csr_matrix* method), 2078
 multiply() (*scipy.sparse.dia_matrix* method), 2094
 multiply() (*scipy.sparse.dok_matrix* method), 2108
 multiply() (*scipy.sparse.lil_matrix* method), 2121
 multiply() (*scipy.sparse.spmatrix* method), 2131
 multiscale_graphcorr() (in module *scipy.stats*), 2950
 multivariate_hypergeom (in module *scipy.stats*), 2851
 multivariate_normal (in module *scipy.stats*), 2833
 multivariate_t (in module *scipy.stats*), 2849
 mvstdist() (in module *scipy.stats*), 2913

N

nakagami (in module *scipy.stats*), 2756
 names() (*scipy.io.arff.MetaData* method), 973
 nbdtr (in module *scipy.special*), 2385
 nbdtrc (in module *scipy.special*), 2386
 nbdtri (in module *scipy.special*), 2387
 nbdtrik (in module *scipy.special*), 2387
 nbdtrin (in module *scipy.special*), 2388
 nbinom (in module *scipy.stats*), 2871
 ncf (in module *scipy.stats*), 2761
 ncfdtr (in module *scipy.special*), 2389
 ncfdtri (in module *scipy.special*), 2393
 ncfdtridfd (in module *scipy.special*), 2390
 ncfdtridfn (in module *scipy.special*), 2392
 ncfdtrinc (in module *scipy.special*), 2394
 nct (in module *scipy.stats*), 2764
 nctdtr (in module *scipy.special*), 2395
 nctdtridf (in module *scipy.special*), 2396
 nctdtrinc (in module *scipy.special*), 2396
 nctdtrit (in module *scipy.special*), 2396
 ncx2 (in module *scipy.stats*), 2759
 NdPPoly (class in *scipy.interpolate*), 880
 ndtr (in module *scipy.special*), 2402
 ndtri (in module *scipy.special*), 2403
 NearestNDInterpolator (class in *scipy.interpolate*), 868
 NegativeCycleError, 2227
 netcdf_file (class in *scipy.io*), 961
 netcdf_variable (class in *scipy.io*), 964
 newton() (in module *scipy.optimize*), 1660
 newton_cotes() (in module *scipy.integrate*), 783
 newton_krylov() (in module *scipy.optimize*), 1743

next_fast_len() (in module *scipy.fft*), 736
 next_fast_len() (in module *scipy.fftpack*), 764
 nhypergeom (in module *scipy.stats*), 2873
 nnlf() (*scipy.stats.rv_continuous* method), 2554
 nnlf() (*scipy.stats.rv_histogram* method), 2574
 nnls() (in module *scipy.optimize*), 1645
 NonlinearConstraint (class in *scipy.optimize*), 1613
 nonzero() (*scipy.sparse.bsr_matrix* method), 2022
 nonzero() (*scipy.sparse.coo_matrix* method), 2040
 nonzero() (*scipy.sparse.csc_matrix* method), 2059
 nonzero() (*scipy.sparse.csr_matrix* method), 2078
 nonzero() (*scipy.sparse.dia_matrix* method), 2094
 nonzero() (*scipy.sparse.dok_matrix* method), 2108
 nonzero() (*scipy.sparse.lil_matrix* method), 2121
 nonzero() (*scipy.sparse.spmatrix* method), 2132
 norm (in module *scipy.stats*), 2767
 norm() (in module *scipy.linalg*), 987
 norm() (in module *scipy.sparse.linalg*), 2165
 normalize() (in module *scipy.signal*), 1868
 normaltest() (in module *scipy.stats*), 2996
 normaltest() (in module *scipy.stats.mstats*), 3067
 norminvgauss (in module *scipy.stats*), 2769
 nquad() (in module *scipy.integrate*), 776
 nrdtrimn (in module *scipy.special*), 2397
 nrdtrisd (in module *scipy.special*), 2397
 nu2lambda() (in module *scipy.constants*), 695
 null_space() (in module *scipy.linalg*), 1023
 num_obs_dm() (in module *scipy.spatial.distance*), 2299
 num_obs_linkage() (in module *scipy.cluster.hierarchy*), 675
 num_obs_y() (in module *scipy.spatial.distance*), 2299

O

oaconvolve() (in module *scipy.signal*), 1763
 obl_ang1 (in module *scipy.special*), 2497
 obl_ang1_cv (in module *scipy.special*), 2499
 obl_cv (in module *scipy.special*), 2498
 obl_cv_seq() (in module *scipy.special*), 2498
 obl_rad1 (in module *scipy.special*), 2497
 obl_rad1_cv (in module *scipy.special*), 2500
 obl_rad2 (in module *scipy.special*), 2497
 obl_rad2_cv (in module *scipy.special*), 2500
 obrientransform() (in module *scipy.stats*), 3008
 obrientransform() (in module *scipy.stats.mstats*), 3067
 ode (class in *scipy.integrate*), 813
 odeint() (in module *scipy.integrate*), 809
 OdeSolution (class in *scipy.integrate*), 808
 OdeSolver (class in *scipy.integrate*), 806
 ODR (class in *scipy.odr*), 1581
 odr() (in module *scipy.odr*), 1585
 OdrError, 1586
 OdrStop, 1586

- OdrWarning, 1586
 onenormest () (in module *scipy.sparse.linalg*), 2166
 optimal_leaf_ordering () (in module *scipy.cluster.hierarchy*), 668
 OptimizeResult (class in *scipy.optimize*), 1593
 OptimizeWarning, 1596
 order_filter () (in module *scipy.signal*), 1782
 ordqz () (in module *scipy.linalg*), 1044
 orth () (in module *scipy.linalg*), 1023
 ortho_group (in module *scipy.stats*), 2846
 orthogonal_procrustes () (in module *scipy.linalg*), 997
 Output (class in *scipy.odr*), 1584
 output () (*scipy.signal.dlti* method), 1926
 output () (*scipy.signal.lti* method), 1901
 owens_t (in module *scipy.special*), 2415
- ## P
- pade () (in module *scipy.interpolate*), 948
 pareto (in module *scipy.stats*), 2772
 ParseArffError, 974
 pascal () (in module *scipy.linalg*), 1084
 pbdn_seq () (in module *scipy.special*), 2492
 pbdv (in module *scipy.special*), 2490
 pbdv_seq () (in module *scipy.special*), 2491
 pbvv (in module *scipy.special*), 2490
 pbvv_seq () (in module *scipy.special*), 2492
 pbwa (in module *scipy.special*), 2491
 pchip_interpolate () (in module *scipy.interpolate*), 836
 PchipInterpolator (class in *scipy.interpolate*), 841
 pdf () (*scipy.stats.gaussian_kde* method), 3082
 pdf () (*scipy.stats.rv_continuous* method), 2546
 pdf () (*scipy.stats.rv_histogram* method), 2574
 pdist () (in module *scipy.spatial.distance*), 2289
 pdtr (in module *scipy.special*), 2397
 pdtrc (in module *scipy.special*), 2398
 pdtri (in module *scipy.special*), 2398
 pdtrik (in module *scipy.special*), 2398
 peak_prominences () (in module *scipy.signal*), 1977
 peak_widths () (in module *scipy.signal*), 1980
 pearson3 (in module *scipy.stats*), 2774
 pearsonr () (in module *scipy.stats*), 2936
 pearsonr () (in module *scipy.stats.mstats*), 3052
 PearsonRConstantInputWarning, 3084
 PearsonRNearConstantInputWarning, 3085
 percentile_filter () (in module *scipy.ndimage*), 1503
 percentileofscore () (in module *scipy.stats*), 2921
 periodogram () (in module *scipy.signal*), 1983
 perm () (in module *scipy.special*), 2511
 physical_constants (in module *scipy.constants*), 683
 pinv () (in module *scipy.linalg*), 992
 pinv2 () (in module *scipy.linalg*), 992
 pinvh () (in module *scipy.linalg*), 993
 place_poles () (in module *scipy.signal*), 1941
 planck (in module *scipy.stats*), 2876
 plane_distance () (*scipy.spatial.Delaunay* method), 2263
 plotting_positions () (in module *scipy.stats.mstats*), 3041
 pmf () (*scipy.stats.rv_discrete* method), 2558
 poch (in module *scipy.special*), 2435
 pointbiserialr () (in module *scipy.stats*), 2939
 pointbiserialr () (in module *scipy.stats.mstats*), 3054
 poisson (in module *scipy.stats*), 2878
 polar () (in module *scipy.linalg*), 1030
 polygamma () (in module *scipy.special*), 2434
 polynomial () (in module *scipy.odr*), 1586
 pop () (*scipy.optimize.OptimizeResult* method), 1595
 pop () (*scipy.sparse.dok_matrix* method), 2108
 popitem () (*scipy.optimize.OptimizeResult* method), 1595
 popitem () (*scipy.sparse.dok_matrix* method), 2109
 power () (*scipy.sparse.bsr_matrix* method), 2022
 power () (*scipy.sparse.coo_matrix* method), 2041
 power () (*scipy.sparse.csc_matrix* method), 2059
 power () (*scipy.sparse.csr_matrix* method), 2078
 power () (*scipy.sparse.dia_matrix* method), 2094
 power () (*scipy.sparse.dok_matrix* method), 2109
 power () (*scipy.sparse.lil_matrix* method), 2121
 power () (*scipy.sparse.spmatrix* method), 2132
 power_divergence () (in module *scipy.stats*), 2962
 powerlaw (in module *scipy.stats*), 2777
 powerlognorm (in module *scipy.stats*), 2780
 powernorm (in module *scipy.stats*), 2782
 ppcc_max () (in module *scipy.stats*), 3024
 ppcc_plot () (in module *scipy.stats*), 3025
 ppf () (*scipy.stats.rv_continuous* method), 2548
 ppf () (*scipy.stats.rv_discrete* method), 2560
 ppf () (*scipy.stats.rv_histogram* method), 2574
 PPoly (class in *scipy.interpolate*), 853
 pprint () (*scipy.odr.Output* method), 1585
 pre_order () (*scipy.cluster.hierarchy.ClusterNode* method), 665
 precision () (in module *scipy.constants*), 682
 prewitt () (in module *scipy.ndimage*), 1504
 pro_ang1 (in module *scipy.special*), 2496
 pro_ang1_cv (in module *scipy.special*), 2499
 pro_cv (in module *scipy.special*), 2497
 pro_cv_seq () (in module *scipy.special*), 2498
 pro_rad1 (in module *scipy.special*), 2496
 pro_rad1_cv (in module *scipy.special*), 2499
 pro_rad2 (in module *scipy.special*), 2497
 pro_rad2_cv (in module *scipy.special*), 2499
 probplot () (in module *scipy.stats*), 3028

procrustes() (in module *scipy.spatial*), 2284
 prune() (*scipy.sparse.bsr_matrix* method), 2023
 prune() (*scipy.sparse.csc_matrix* method), 2059
 prune() (*scipy.sparse.csr_matrix* method), 2078
 pseudo_huber (in module *scipy.special*), 2418
 psi (in module *scipy.special*), 2432

Q

qmf() (in module *scipy.signal*), 1962
 qmr() (in module *scipy.sparse.linalg*), 2178
 qr() (in module *scipy.linalg*), 1032
 qr_delete() (in module *scipy.linalg*), 1037
 qr_insert() (in module *scipy.linalg*), 1039
 qr_multiply() (in module *scipy.linalg*), 1033
 qr_update() (in module *scipy.linalg*), 1034
 qspline1d() (in module *scipy.signal*), 1776
 qspline1d_eval() (in module *scipy.signal*), 1779
 qspline2d() (in module *scipy.signal*), 1778
 quad() (in module *scipy.integrate*), 767
 quad_explain() (in module *scipy.integrate*), 783
 quad_vec() (in module *scipy.integrate*), 772
 quadratic (in module *scipy.odr*), 1589
 quadratic() (in module *scipy.signal*), 1774
 quadratic_assignment() (in module *scipy.optimize*), 1700
 quadrature() (in module *scipy.integrate*), 780
 query() (*scipy.spatial.cKDTree* method), 2250
 query() (*scipy.spatial.KDTree* method), 2239
 query_ball_point() (*scipy.spatial.cKDTree* method), 2251
 query_ball_point() (*scipy.spatial.KDTree* method), 2241
 query_ball_tree() (*scipy.spatial.cKDTree* method), 2253
 query_ball_tree() (*scipy.spatial.KDTree* method), 2242
 query_pairs() (*scipy.spatial.cKDTree* method), 2253
 query_pairs() (*scipy.spatial.KDTree* method), 2244
 qz() (in module *scipy.linalg*), 1042

R

rad2deg() (*scipy.sparse.bsr_matrix* method), 2023
 rad2deg() (*scipy.sparse.coo_matrix* method), 2041
 rad2deg() (*scipy.sparse.csc_matrix* method), 2059
 rad2deg() (*scipy.sparse.csr_matrix* method), 2078
 rad2deg() (*scipy.sparse.dia_matrix* method), 2094
 Radau (class in *scipy.integrate*), 800
 radian (in module *scipy.special*), 2532
 rand() (in module *scipy.linalg.interpolative*), 1464
 rand() (in module *scipy.sparse*), 2145
 randint (in module *scipy.stats*), 2880
 random() (in module *scipy.sparse*), 2146
 random_correlation (in module *scipy.stats*), 2848
 rank_filter() (in module *scipy.ndimage*), 1506

rankdata() (in module *scipy.stats*), 2973
 rankdata() (in module *scipy.stats.mstats*), 3063
 ranksums() (in module *scipy.stats*), 2974
 rayleigh (in module *scipy.stats*), 2787
 Rbf (class in *scipy.interpolate*), 871
 rdist (in module *scipy.stats*), 2785
 read() (in module *scipy.io.wavfile*), 968
 read_ints() (*scipy.io.FortranFile* method), 958
 read_reals() (*scipy.io.FortranFile* method), 958
 read_record() (*scipy.io.FortranFile* method), 958
 readsav() (in module *scipy.io*), 954
 RealData (class in *scipy.odr*), 1579
 recipinvgauss (in module *scipy.stats*), 2792
 reconstruct_interp_matrix() (in module *scipy.linalg.interpolative*), 1461
 reconstruct_matrix_from_id() (in module *scipy.linalg.interpolative*), 1460
 reconstruct_path() (in module *scipy.sparse.csgraph*), 2233
 reconstruct_skel_matrix() (in module *scipy.linalg.interpolative*), 1461
 Rectangle (class in *scipy.spatial*), 2257
 RectBivariateSpline (class in *scipy.interpolate*), 878
 RectSphereBivariateSpline (class in *scipy.interpolate*), 924
 register_backend() (in module *scipy.fftpack*), 739
 RegularGridInterpolator (class in *scipy.interpolate*), 876
 rel ENTR (in module *scipy.special*), 2416
 relfreq() (in module *scipy.stats*), 2923
 remez() (in module *scipy.signal*), 1847
 resample() (in module *scipy.signal*), 1804
 resample() (*scipy.stats.gaussian_kde* method), 3082
 resample_poly() (in module *scipy.signal*), 1806
 reshape() (*scipy.sparse.bsr_matrix* method), 2023
 reshape() (*scipy.sparse.coo_matrix* method), 2041
 reshape() (*scipy.sparse.csc_matrix* method), 2060
 reshape() (*scipy.sparse.csr_matrix* method), 2079
 reshape() (*scipy.sparse.dia_matrix* method), 2094
 reshape() (*scipy.sparse.dok_matrix* method), 2109
 reshape() (*scipy.sparse.lil_matrix* method), 2121
 reshape() (*scipy.sparse.spmatrix* method), 2132
 residue() (in module *scipy.signal*), 1852
 residuez() (in module *scipy.signal*), 1853
 resize() (*scipy.sparse.bsr_matrix* method), 2023
 resize() (*scipy.sparse.coo_matrix* method), 2042
 resize() (*scipy.sparse.csc_matrix* method), 2060
 resize() (*scipy.sparse.csr_matrix* method), 2079
 resize() (*scipy.sparse.dia_matrix* method), 2095
 resize() (*scipy.sparse.dok_matrix* method), 2109
 resize() (*scipy.sparse.lil_matrix* method), 2122
 resize() (*scipy.sparse.spmatrix* method), 2133
 restart() (*scipy.odr.ODR* method), 1583

reverse_cuthill_mckee() (in module *scipy.sparse.csgraph*), 2218
 rfft() (in module *scipy.fft*), 708
 rfft() (in module *scipy.fftpack*), 746
 rfft2() (in module *scipy.fft*), 712
 rfftfreq() (in module *scipy.fft*), 735
 rfftfreq() (in module *scipy.fftpack*), 763
 rfftn() (in module *scipy.fft*), 714
 rgamma (in module *scipy.special*), 2433
 riccati_jn() (in module *scipy.special*), 2366
 riccati_yn() (in module *scipy.special*), 2366
 rice (in module *scipy.stats*), 2790
 ricker() (in module *scipy.signal*), 1962
 ridder() (in module *scipy.optimize*), 1657
 rint() (*scipy.sparse.bsr_matrix* method), 2024
 rint() (*scipy.sparse.coo_matrix* method), 2042
 rint() (*scipy.sparse.csc_matrix* method), 2061
 rint() (*scipy.sparse.csr_matrix* method), 2080
 rint() (*scipy.sparse.dia_matrix* method), 2095
 RK23 (class in *scipy.integrate*), 796
 RK45 (class in *scipy.integrate*), 797
 rmatmat() (*scipy.optimize.LbfgsInvHessProduct* method), 1712
 rmatmat() (*scipy.sparse.linalg.LinearOperator* method), 2160
 rmatvec() (*scipy.optimize.LbfgsInvHessProduct* method), 1713
 rmatvec() (*scipy.sparse.linalg.LinearOperator* method), 2160
 rogerstanimoto() (in module *scipy.spatial.distance*), 2311
 romb() (in module *scipy.integrate*), 789
 romberg() (in module *scipy.integrate*), 781
 root() (in module *scipy.optimize*), 1669
 root_scalar() (in module *scipy.optimize*), 1652
 RootResults (class in *scipy.optimize*), 1664
 roots() (*scipy.interpolate.Akima1DInterpolator* method), 847
 roots() (*scipy.interpolate.CubicHermiteSpline* method), 841
 roots() (*scipy.interpolate.CubicSpline* method), 853
 roots() (*scipy.interpolate.InterpolatedUnivariateSpline* method), 917
 roots() (*scipy.interpolate.LSQUnivariateSpline* method), 924
 roots() (*scipy.interpolate.PchipInterpolator* method), 844
 roots() (*scipy.interpolate.PPoly* method), 857
 roots() (*scipy.interpolate.UnivariateSpline* method), 912
 roots_chebyc() (in module *scipy.special*), 2470
 roots_chebys() (in module *scipy.special*), 2471
 roots_chebyt() (in module *scipy.special*), 2469
 roots_chebyu() (in module *scipy.special*), 2470

roots_gegenbauer() (in module *scipy.special*), 2474
 roots_genlaguerre() (in module *scipy.special*), 2472
 roots_hermite() (in module *scipy.special*), 2473
 roots_hermitenorm() (in module *scipy.special*), 2474
 roots_jacobi() (in module *scipy.special*), 2471
 roots_laguerre() (in module *scipy.special*), 2472
 roots_legendre() (in module *scipy.special*), 2469
 roots_sh_chebyt() (in module *scipy.special*), 2476
 roots_sh_chebyu() (in module *scipy.special*), 2476
 roots_sh_jacobi() (in module *scipy.special*), 2477
 roots_sh_legendre() (in module *scipy.special*), 2475
 rosen() (in module *scipy.optimize*), 1715
 rosen_der() (in module *scipy.optimize*), 1716
 rosen_hess() (in module *scipy.optimize*), 1717
 rosen_hess_prod() (in module *scipy.optimize*), 1717
 rotate() (in module *scipy.ndimage*), 1522
 round (in module *scipy.special*), 2537
 rq() (in module *scipy.linalg*), 1041
 rsf2csf() (in module *scipy.linalg*), 1047
 rsh() (in module *scipy.stats.mstats*), 3077
 run() (*scipy.odr.ODR* method), 1583
 russellrao() (in module *scipy.spatial.distance*), 2312
 rv_continuous (class in *scipy.stats*), 2542
 rv_discrete (class in *scipy.stats*), 2555
 rv_histogram (class in *scipy.stats*), 2565
 rvs() (*scipy.stats.rv_continuous* method), 2545
 rvs() (*scipy.stats.rv_discrete* method), 2557
 rvs() (*scipy.stats.rv_histogram* method), 2575
 rvs_ratio_uniforms() (in module *scipy.stats*), 3015

S

sasum (in module *scipy.linalg.blas*), 1104
 save_npz() (in module *scipy.sparse*), 2147
 savemat() (in module *scipy.io*), 952
 savgol_coeffs() (in module *scipy.signal*), 1845
 savgol_filter() (in module *scipy.signal*), 1794
 sawtooth() (in module *scipy.signal*), 1952
 saxpy (in module *scipy.linalg.blas*), 1104
 sc_diff() (in module *scipy.fftpack*), 759
 scasum (in module *scipy.linalg.blas*), 1104
 schur() (in module *scipy.linalg*), 1045
 scipy
 module, 619
 scipy.cluster
 module, 621
 scipy.cluster.hierarchy
 module, 628
 scipy.cluster.vq
 module, 621
 scipy.constants

module, 679
 scipy.fft
 module, 696
 scipy.fftpack
 module, 740
 scipy.fftpack.convolve
 module, 765
 scipy.integrate
 module, 766
 scipy.interpolate
 module, 827
 scipy.io
 module, 949
 scipy.io.arff
 module, 971
 scipy.io.wavfile
 module, 968
 scipy.linalg
 module, 974
 scipy.linalg.blas
 module, 1091
 scipy.linalg.cython_blas
 module, 1412
 scipy.linalg.cython_lapack
 module, 1416
 scipy.linalg.interpolative
 module, 1458
 scipy.linalg.lapack
 module, 1156
 scipy.misc
 module, 1468
 scipy.ndimage
 module, 1475
 scipy.odr
 module, 1577
 scipy.optimize
 module, 1590
 scipy.optimize.cython_optimize
 module, 1751
 scipy.optimize.nonlin
 module, 1749
 scipy.signal
 module, 1754
 scipy.sparse
 module, 2010
 scipy.sparse.csgraph
 module, 2202
 scipy.sparse.linalg
 module, 2157
 scipy.spatial
 module, 2235
 scipy.spatial.distance
 module, 2288
 scipy.special
 module, 2314
 scipy.stats
 module, 2541
 scipy.stats.mstats
 module, 3034
 scnrn2 (*in module scipy.linalg.blas*), 1105
 scopy (*in module scipy.linalg.blas*), 1105
 scoreatpercentile() (*in module scipy.stats*), 2922
 scoreatpercentile() (*in module scipy.stats.mstats*), 3052
 sdot (*in module scipy.linalg.blas*), 1105
 seed() (*in module scipy.linalg.interpolative*), 1464
 sem() (*in module scipy.stats*), 2910
 sem() (*in module scipy.stats.mstats*), 3049
 semicircular (*in module scipy.stats*), 2795
 sen_seasonal_slopes() (*in module scipy.stats.mstats*), 3056
 sepfir2d() (*in module scipy.signal*), 1769
 set_backend() (*in module scipy.fft*), 738
 set_bandwidth() (*scipy.stats.gaussian_kde method*), 3082
 set_f_params() (*scipy.integrate.complex_ode method*), 821
 set_f_params() (*scipy.integrate.ode method*), 818
 set_global_backend() (*in module scipy.fft*), 739
 set_initial_value() (*scipy.integrate.complex_ode method*), 822
 set_initial_value() (*scipy.integrate.ode method*), 818
 set_integrator() (*scipy.integrate.complex_ode method*), 822
 set_integrator() (*scipy.integrate.ode method*), 818
 set_iprint() (*scipy.odr.ODR method*), 1583
 set_jac_params() (*scipy.integrate.complex_ode method*), 822
 set_jac_params() (*scipy.integrate.ode method*), 818
 set_job() (*scipy.odr.ODR method*), 1584
 set_link_color_palette() (*in module scipy.cluster.hierarchy*), 676
 set_meta() (*scipy.odr.Data method*), 1578
 set_meta() (*scipy.odr.Model method*), 1581
 set_meta() (*scipy.odr.RealData method*), 1580
 set_shape() (*scipy.sparse.bsr_matrix method*), 2024
 set_shape() (*scipy.sparse.coo_matrix method*), 2042
 set_shape() (*scipy.sparse.csc_matrix method*), 2061
 set_shape() (*scipy.sparse.csr_matrix method*), 2080
 set_shape() (*scipy.sparse.dia_matrix method*), 2095
 set_shape() (*scipy.sparse.dok_matrix method*), 2110
 set_shape() (*scipy.sparse.lil_matrix method*), 2122
 set_shape() (*scipy.sparse.spmatrix method*), 2133
 set_smoothing_factor() (*scipy.interpolate.InterpolatedUnivariateSpline method*), 918
 set_smoothing_factor()

- (scipy.interpolate.LSQUnivariateSpline method)*, 924
- set_smoothing_factor()
 - (scipy.interpolate.UnivariateSpline method)*, 912
- set_solout() (*scipy.integrate.complex_ode method*), 822
- set_solout() (*scipy.integrate.ode method*), 819
- set_workers() (*in module scipy.fft*), 737
- set_yi() (*scipy.interpolate.BarycentricInterpolator method*), 831
- setdefault() (*scipy.optimize.OptimizeResult method*), 1595
- setdefault() (*scipy.sparse.dok_matrix method*), 2110
- setdiag() (*scipy.sparse.bsr_matrix method*), 2024
- setdiag() (*scipy.sparse.coo_matrix method*), 2042
- setdiag() (*scipy.sparse.csc_matrix method*), 2061
- setdiag() (*scipy.sparse.csr_matrix method*), 2080
- setdiag() (*scipy.sparse.dia_matrix method*), 2096
- setdiag() (*scipy.sparse.dok_matrix method*), 2110
- setdiag() (*scipy.sparse.lil_matrix method*), 2122
- setdiag() (*scipy.sparse.spmatrix method*), 2133
- seterr() (*in module scipy.special*), 2316
- seuclidean() (*in module scipy.spatial.distance*), 2306
- sf() (*scipy.stats.rv_continuous method*), 2547
- sf() (*scipy.stats.rv_discrete method*), 2559
- sf() (*scipy.stats.rv_histogram method*), 2575
- sgbmv (*in module scipy.linalg.blas*), 1113
- sgbsv (*in module scipy.linalg.lapack*), 1170
- sgbtrf (*in module scipy.linalg.lapack*), 1172
- sgbtrs (*in module scipy.linalg.lapack*), 1174
- sgebal (*in module scipy.linalg.lapack*), 1176
- sgecon (*in module scipy.linalg.lapack*), 1177
- sgeequ (*in module scipy.linalg.lapack*), 1179
- sgeequb (*in module scipy.linalg.lapack*), 1180
- sgees (*in module scipy.linalg.lapack*), 1181
- sgeev (*in module scipy.linalg.lapack*), 1184
- sgeev_lwork (*in module scipy.linalg.lapack*), 1186
- sgegv() (*in module scipy.linalg.lapack*), 1188
- sgehrd (*in module scipy.linalg.lapack*), 1190
- sgehrd_lwork (*in module scipy.linalg.lapack*), 1192
- sgejsv (*in module scipy.linalg.lapack*), 1193
- sgels (*in module scipy.linalg.lapack*), 1194
- sgels_lwork (*in module scipy.linalg.lapack*), 1196
- sgelsd (*in module scipy.linalg.lapack*), 1197
- sgelsd_lwork (*in module scipy.linalg.lapack*), 1199
- sgelss (*in module scipy.linalg.lapack*), 1201
- sgelss_lwork (*in module scipy.linalg.lapack*), 1203
- sgelsy (*in module scipy.linalg.lapack*), 1205
- sgelsy_lwork (*in module scipy.linalg.lapack*), 1207
- sgemm (*in module scipy.linalg.blas*), 1144
- sgemqrt (*in module scipy.linalg.lapack*), 1399
- sgemv (*in module scipy.linalg.blas*), 1114
- sgeqp3 (*in module scipy.linalg.lapack*), 1208
- sgeqrf (*in module scipy.linalg.lapack*), 1210
- sgeqrf_lwork (*in module scipy.linalg.lapack*), 1211
- sgeqrfp (*in module scipy.linalg.lapack*), 1212
- sgeqrfp_lwork (*in module scipy.linalg.lapack*), 1214
- sgeqrt (*in module scipy.linalg.lapack*), 1397
- sger (*in module scipy.linalg.blas*), 1114
- sgerqf (*in module scipy.linalg.lapack*), 1215
- sgesc2 (*in module scipy.linalg.lapack*), 1235
- sgesdd (*in module scipy.linalg.lapack*), 1217
- sgesdd_lwork (*in module scipy.linalg.lapack*), 1219
- sgesv (*in module scipy.linalg.lapack*), 1220
- sgesvd (*in module scipy.linalg.lapack*), 1222
- sgesvd_lwork (*in module scipy.linalg.lapack*), 1224
- sgesvx (*in module scipy.linalg.lapack*), 1225
- sgetc2 (*in module scipy.linalg.lapack*), 1230
- sgetrf (*in module scipy.linalg.lapack*), 1228
- sgetri (*in module scipy.linalg.lapack*), 1231
- sgetri_lwork (*in module scipy.linalg.lapack*), 1233
- sgetrs (*in module scipy.linalg.lapack*), 1234
- sgges (*in module scipy.linalg.lapack*), 1237
- sggev (*in module scipy.linalg.lapack*), 1241
- sgglse (*in module scipy.linalg.lapack*), 1243
- sgglse_lwork (*in module scipy.linalg.lapack*), 1245
- sgtsv (*in module scipy.linalg.lapack*), 1247
- sgtsvx (*in module scipy.linalg.lapack*), 1249
- sgttrf (*in module scipy.linalg.lapack*), 1400
- sgttrs (*in module scipy.linalg.lapack*), 1402
- sh_chebyt() (*in module scipy.special*), 2483
- sh_chebyu() (*in module scipy.special*), 2484
- sh_jacobi() (*in module scipy.special*), 2484
- sh_legendre() (*in module scipy.special*), 2483
- shapiro() (*in module scipy.stats*), 2985
- shgo() (*in module scipy.optimize*), 1630
- shichi (*in module scipy.special*), 2525
- shift() (*in module scipy.fftpack*), 761
- shift() (*in module scipy.ndimage*), 1524
- shortest_path() (*in module scipy.sparse.csgraph*), 2205
- show_options() (*in module scipy.optimize*), 1591
- sici (*in module scipy.special*), 2525
- siegelslopes() (*in module scipy.stats*), 2946
- siegelslopes() (*in module scipy.stats.mstats*), 3055
- sigmaclip() (*in module scipy.stats*), 3009
- sign() (*scipy.sparse.bsr_matrix method*), 2024
- sign() (*scipy.sparse.coo_matrix method*), 2043
- sign() (*scipy.sparse.csc_matrix method*), 2061
- sign() (*scipy.sparse.csr_matrix method*), 2080
- sign() (*scipy.sparse.dia_matrix method*), 2096
- signm() (*in module scipy.linalg*), 1057
- simpson() (*in module scipy.integrate*), 788
- sin() (*scipy.sparse.bsr_matrix method*), 2025
- sin() (*scipy.sparse.coo_matrix method*), 2043
- sin() (*scipy.sparse.csc_matrix method*), 2061
- sin() (*scipy.sparse.csr_matrix method*), 2080
- sin() (*scipy.sparse.dia_matrix method*), 2096

- sinc() (in module *scipy.special*), 2540
 sindg (in module *scipy.special*), 2534
 single() (in module *scipy.cluster.hierarchy*), 638
 sinh() (*scipy.sparse.bsr_matrix* method), 2025
 sinh() (*scipy.sparse.coo_matrix* method), 2043
 sinh() (*scipy.sparse.csc_matrix* method), 2061
 sinh() (*scipy.sparse.csr_matrix* method), 2080
 sinh() (*scipy.sparse.dia_matrix* method), 2096
 sinhm() (in module *scipy.linalg*), 1056
 sinm() (in module *scipy.linalg*), 1054
 skellam (in module *scipy.stats*), 2882
 skew() (in module *scipy.stats*), 2897
 skew() (in module *scipy.stats.mstats*), 3043
 skewnorm (in module *scipy.stats*), 2797
 skewtest() (in module *scipy.stats*), 2994
 skewtest() (in module *scipy.stats.mstats*), 3066
 skip_backend() (in module *scipy.fft*), 738
 slamch (in module *scipy.linalg.lapack*), 1275
 slange (in module *scipy.linalg.lapack*), 1275
 slarf (in module *scipy.linalg.lapack*), 1276
 slarfg (in module *scipy.linalg.lapack*), 1278
 slartg (in module *scipy.linalg.lapack*), 1279
 slasd4 (in module *scipy.linalg.lapack*), 1281
 slaswp (in module *scipy.linalg.lapack*), 1281
 slauum (in module *scipy.linalg.lapack*), 1283
 smirnov (in module *scipy.special*), 2404
 smirnovi (in module *scipy.special*), 2406
 SmoothBivariateSpline (class in *scipy.interpolate*), 931
 SmoothSphereBivariateSpline (class in *scipy.interpolate*), 934
 snrm2 (in module *scipy.linalg.blas*), 1106
 sobel() (in module *scipy.ndimage*), 1507
 softmax() (in module *scipy.special*), 2526
 sokalmichener() (in module *scipy.spatial.distance*), 2312
 sokalsneath() (in module *scipy.spatial.distance*), 2313
 solve() (in module *scipy.linalg*), 976
 solve() (*scipy.interpolate.PPoly* method), 856
 solve() (*scipy.sparse.linalg.SuperLU* method), 2199
 solve_banded() (in module *scipy.linalg*), 977
 solve_bvp() (in module *scipy.integrate*), 823
 solve_circulant() (in module *scipy.linalg*), 980
 solve_continuous_are() (in module *scipy.linalg*), 1064
 solve_continuous_lyapunov() (in module *scipy.linalg*), 1067
 solve_discrete_are() (in module *scipy.linalg*), 1065
 solve_discrete_lyapunov() (in module *scipy.linalg*), 1068
 solve_ivp() (in module *scipy.integrate*), 791
 solve_sylvester() (in module *scipy.linalg*), 1063
 solve_toeplitz() (in module *scipy.linalg*), 984
 solve_triangular() (in module *scipy.linalg*), 982
 solveh_banded() (in module *scipy.linalg*), 979
 sorcsd (in module *scipy.linalg.lapack*), 1284
 sorcsd_lwork (in module *scipy.linalg.lapack*), 1286
 sorghr (in module *scipy.linalg.lapack*), 1287
 sorghr_lwork (in module *scipy.linalg.lapack*), 1287
 sorgqr (in module *scipy.linalg.lapack*), 1288
 sorgrq (in module *scipy.linalg.lapack*), 1289
 sormqr (in module *scipy.linalg.lapack*), 1290
 sormrz (in module *scipy.linalg.lapack*), 1291
 sormrz_lwork (in module *scipy.linalg.lapack*), 1291
 sort_indices() (*scipy.sparse.bsr_matrix* method), 2025
 sort_indices() (*scipy.sparse.csc_matrix* method), 2062
 sort_indices() (*scipy.sparse.csr_matrix* method), 2081
 sorted_indices() (*scipy.sparse.bsr_matrix* method), 2025
 sorted_indices() (*scipy.sparse.csc_matrix* method), 2062
 sorted_indices() (*scipy.sparse.csr_matrix* method), 2081
 sos2tf() (in module *scipy.signal*), 1940
 sos2zpk() (in module *scipy.signal*), 1939
 sosfilt() (in module *scipy.signal*), 1796
 sosfilt_zi() (in module *scipy.signal*), 1797
 sosfiltfilt() (in module *scipy.signal*), 1799
 sosfreqz() (in module *scipy.signal*), 1829
 spalde() (in module *scipy.interpolate*), 902
 sparse_distance_matrix() (*scipy.spatial.cKDTree* method), 2255
 sparse_distance_matrix() (*scipy.spatial.KDTree* method), 2244
 SparseEfficiencyWarning, 2155
 SparseWarning, 2155
 spbsv (in module *scipy.linalg.lapack*), 1292
 spbtrf (in module *scipy.linalg.lapack*), 1294
 spbtrs (in module *scipy.linalg.lapack*), 1296
 spdiags() (in module *scipy.sparse*), 2140
 spearmanr() (in module *scipy.stats*), 2938
 spearmanr() (in module *scipy.stats.mstats*), 3053
 SpearmanRConstantInputWarning, 3085
 special_ortho_group (in module *scipy.stats*), 2845
 SpecialFunctionError, 2318
 SpecialFunctionWarning, 2318
 spectrogram() (in module *scipy.signal*), 1994
 spence (in module *scipy.special*), 2528
 spftrf (in module *scipy.linalg.lapack*), 1297
 spftri (in module *scipy.linalg.lapack*), 1299
 spftrs (in module *scipy.linalg.lapack*), 1300
 sph_harm (in module *scipy.special*), 2449
 spherical_in() (in module *scipy.special*), 2364

- spherical_jn() (in module *scipy.special*), 2363
 spherical_kn() (in module *scipy.special*), 2365
 spherical_yn() (in module *scipy.special*), 2364
 SphericalVoronoi (class in *scipy.spatial*), 2270
 spilu() (in module *scipy.sparse.linalg*), 2196
 splantider() (in module *scipy.interpolate*), 903
 splder() (in module *scipy.interpolate*), 902
 splev() (in module *scipy.interpolate*), 899
 spline_filter() (in module *scipy.ndimage*), 1526
 spline_filter() (in module *scipy.signal*), 1781
 spline_filter1d() (in module *scipy.ndimage*), 1526
 splint() (in module *scipy.interpolate*), 900
 split() (*scipy.spatial.Rectangle* method), 2258
 splprep() (in module *scipy.interpolate*), 896
 splrep() (in module *scipy.interpolate*), 895
 splu() (in module *scipy.sparse.linalg*), 2195
 spmatrix (class in *scipy.sparse*), 2125
 spocon (in module *scipy.linalg.lapack*), 1302
 sposv (in module *scipy.linalg.lapack*), 1306
 sposvx (in module *scipy.linalg.lapack*), 1308
 spotrf (in module *scipy.linalg.lapack*), 1311
 spotri (in module *scipy.linalg.lapack*), 1312
 spotrs (in module *scipy.linalg.lapack*), 1313
 sppcon (in module *scipy.linalg.lapack*), 1315
 sppsv (in module *scipy.linalg.lapack*), 1316
 spptrf (in module *scipy.linalg.lapack*), 1318
 spptri (in module *scipy.linalg.lapack*), 1319
 spptrs (in module *scipy.linalg.lapack*), 1321
 sproot() (in module *scipy.interpolate*), 901
 spsolve() (in module *scipy.sparse.linalg*), 2168
 spsolve_triangular() (in module *scipy.sparse.linalg*), 2168
 spstf2 (in module *scipy.linalg.lapack*), 1305
 spstrf (in module *scipy.linalg.lapack*), 1303
 spteqr (in module *scipy.linalg.lapack*), 1329
 sptsv (in module *scipy.linalg.lapack*), 1322
 sptsvx (in module *scipy.linalg.lapack*), 1324
 spttrf (in module *scipy.linalg.lapack*), 1326
 spttrs (in module *scipy.linalg.lapack*), 1328
 squeuclidean() (in module *scipy.spatial.distance*), 2307
 sqrt() (*scipy.sparse.bsr_matrix* method), 2025
 sqrt() (*scipy.sparse.coo_matrix* method), 2043
 sqrt() (*scipy.sparse.csc_matrix* method), 2062
 sqrt() (*scipy.sparse.csr_matrix* method), 2081
 sqrt() (*scipy.sparse.dia_matrix* method), 2096
 sqrtm() (in module *scipy.linalg*), 1058
 square() (in module *scipy.signal*), 1954
 squareform() (in module *scipy.spatial.distance*), 2296
 SR1 (class in *scipy.optimize*), 1618
 srot (in module *scipy.linalg.blas*), 1106
 srotg (in module *scipy.linalg.blas*), 1107
 srotm (in module *scipy.linalg.blas*), 1107
 srotmg (in module *scipy.linalg.blas*), 1107
 ss2tf() (in module *scipy.signal*), 1938
 ss2zpk() (in module *scipy.signal*), 1939
 ss_diff() (in module *scipy.fftpack*), 760
 ssbev (in module *scipy.linalg.lapack*), 1333
 ssbevd (in module *scipy.linalg.lapack*), 1334
 ssbevz (in module *scipy.linalg.lapack*), 1335
 ssbmv (in module *scipy.linalg.blas*), 1115
 sscal (in module *scipy.linalg.blas*), 1108
 ssfrk (in module *scipy.linalg.lapack*), 1336
 sspr (in module *scipy.linalg.blas*), 1115
 sspr2 (in module *scipy.linalg.blas*), 1116
 sstebz (in module *scipy.linalg.lapack*), 1337
 sstein (in module *scipy.linalg.lapack*), 1338
 sstemr (in module *scipy.linalg.lapack*), 1338
 sstemr_lwork (in module *scipy.linalg.lapack*), 1339
 ssterf (in module *scipy.linalg.lapack*), 1340
 sstev (in module *scipy.linalg.lapack*), 1341
 sswap (in module *scipy.linalg.blas*), 1108
 ssycon (in module *scipy.linalg.lapack*), 1342
 ssyconv (in module *scipy.linalg.lapack*), 1343
 ssyequb (in module *scipy.linalg.lapack*), 1345
 ssyev (in module *scipy.linalg.lapack*), 1346
 ssyev_lwork (in module *scipy.linalg.lapack*), 1347
 ssyevd (in module *scipy.linalg.lapack*), 1348
 ssyevd_lwork (in module *scipy.linalg.lapack*), 1349
 ssyevr (in module *scipy.linalg.lapack*), 1350
 ssyevr_lwork (in module *scipy.linalg.lapack*), 1351
 ssyevz (in module *scipy.linalg.lapack*), 1352
 ssyevz_lwork (in module *scipy.linalg.lapack*), 1353
 ssygst (in module *scipy.linalg.lapack*), 1353
 ssygv (in module *scipy.linalg.lapack*), 1354
 ssygv_lwork (in module *scipy.linalg.lapack*), 1355
 ssygvd (in module *scipy.linalg.lapack*), 1356
 ssygvx (in module *scipy.linalg.lapack*), 1357
 ssygvx_lwork (in module *scipy.linalg.lapack*), 1358
 ssymm (in module *scipy.linalg.blas*), 1144
 ssymv (in module *scipy.linalg.blas*), 1116
 ssyr (in module *scipy.linalg.blas*), 1117
 ssyr2 (in module *scipy.linalg.blas*), 1117
 ssyr2k (in module *scipy.linalg.blas*), 1145
 ssyrk (in module *scipy.linalg.blas*), 1145
 ssysv (in module *scipy.linalg.lapack*), 1359
 ssysv_lwork (in module *scipy.linalg.lapack*), 1361
 ssysvx (in module *scipy.linalg.lapack*), 1362
 ssysvx_lwork (in module *scipy.linalg.lapack*), 1364
 ssytf2 (in module *scipy.linalg.lapack*), 1366
 ssytrd (in module *scipy.linalg.lapack*), 1367
 ssytrd_lwork (in module *scipy.linalg.lapack*), 1368
 ssytrf (in module *scipy.linalg.lapack*), 1369
 ssytrf_lwork (in module *scipy.linalg.lapack*), 1370
 standard_deviation() (in module *scipy.ndimage*), 1545
 StateSpace (class in *scipy.signal*), 1901

- stats () (*scipy.stats.rv_continuous method*), 2549
 stats () (*scipy.stats.rv_discrete method*), 2561
 stats () (*scipy.stats.rv_histogram method*), 2575
 stbmv (*in module scipy.linalg.blas*), 1118
 stbtrs (*in module scipy.linalg.lapack*), 1371
 std () (*scipy.stats.rv_continuous method*), 2551
 std () (*scipy.stats.rv_discrete method*), 2563
 std () (*scipy.stats.rv_histogram method*), 2576
 stdtr (*in module scipy.special*), 2399
 stdtridf (*in module scipy.special*), 2399
 stdtrit (*in module scipy.special*), 2399
 step () (*in module scipy.signal*), 1916
 step () (*scipy.integrate.BDF method*), 804
 step () (*scipy.integrate.DOP853 method*), 800
 step () (*scipy.integrate.LSODA method*), 806
 step () (*scipy.integrate.OdeSolver method*), 807
 step () (*scipy.integrate.Radau method*), 802
 step () (*scipy.integrate.RK23 method*), 797
 step () (*scipy.integrate.RK45 method*), 799
 step () (*scipy.signal.dlti method*), 1926
 step () (*scipy.signal.lti method*), 1901
 step2 () (*in module scipy.signal*), 1916
 stfsm (*in module scipy.linalg.lapack*), 1373
 stfft () (*in module scipy.signal*), 2000
 stfftq (*in module scipy.linalg.lapack*), 1375
 stffttr (*in module scipy.linalg.lapack*), 1376
 stgsen (*in module scipy.linalg.lapack*), 1377
 stpmqrt (*in module scipy.linalg.lapack*), 1406
 stpqrt (*in module scipy.linalg.lapack*), 1404
 stpsv (*in module scipy.linalg.blas*), 1118
 stpttf (*in module scipy.linalg.lapack*), 1380
 stpttr (*in module scipy.linalg.lapack*), 1382
 strerror (*scipy.io.arff.ArffError attribute*), 973
 strerror (*scipy.io.arff.ParseArffError attribute*), 974
 strerror (*scipy.io.FortranEOFError attribute*), 960
 strerror (*scipy.io.FortranFormattingError attribute*), 960
 strmm (*in module scipy.linalg.blas*), 1145
 strmv (*in module scipy.linalg.blas*), 1119
 strsm (*in module scipy.linalg.blas*), 1146
 strsv (*in module scipy.linalg.blas*), 1119
 strsyl (*in module scipy.linalg.lapack*), 1383
 strtri (*in module scipy.linalg.lapack*), 1385
 strtrs (*in module scipy.linalg.lapack*), 1386
 strttf (*in module scipy.linalg.lapack*), 1388
 strttp (*in module scipy.linalg.lapack*), 1389
 structural_rank () (*in module scipy.sparse.csrgraph*), 2226
 struve (*in module scipy.special*), 2367
 stzrzf (*in module scipy.linalg.lapack*), 1391
 stzrzf_lwork (*in module scipy.linalg.lapack*), 1392
 subset () (*scipy.cluster.hierarchy.DisjointSet method*), 679
 subsets () (*scipy.cluster.hierarchy.DisjointSet method*), 679
 subspace_angles () (*in module scipy.linalg*), 999
 successful () (*scipy.integrate.complex_ode method*), 822
 successful () (*scipy.integrate.ode method*), 819
 sum () (*scipy.sparse.bsr_matrix method*), 2025
 sum () (*scipy.sparse.coo_matrix method*), 2043
 sum () (*scipy.sparse.csc_matrix method*), 2062
 sum () (*scipy.sparse.csr_matrix method*), 2081
 sum () (*scipy.sparse.dia_matrix method*), 2097
 sum () (*scipy.sparse.dok_matrix method*), 2110
 sum () (*scipy.sparse.lil_matrix method*), 2122
 sum () (*scipy.sparse.spmatrix method*), 2133
 sum_duplicates () (*scipy.sparse.bsr_matrix method*), 2026
 sum_duplicates () (*scipy.sparse.coo_matrix method*), 2044
 sum_duplicates () (*scipy.sparse.csc_matrix method*), 2063
 sum_duplicates () (*scipy.sparse.csr_matrix method*), 2082
 sum_labels () (*in module scipy.ndimage*), 1546
 SuperLU (*class in scipy.sparse.linalg*), 2197
 support () (*scipy.stats.rv_continuous method*), 2555
 support () (*scipy.stats.rv_discrete method*), 2564
 support () (*scipy.stats.rv_histogram method*), 2576
 svd () (*in module scipy.linalg*), 1019
 svd () (*in module scipy.linalg.interpolative*), 1462
 svds () (*in module scipy.sparse.linalg*), 2193
 svdvals () (*in module scipy.linalg*), 1020
 sweep_poly () (*in module scipy.signal*), 1954
 symiirorder1 () (*in module scipy.signal*), 1785
 symiirorder2 () (*in module scipy.signal*), 1786
 sync () (*scipy.io.netcdf_file method*), 964
- ## T
- t (*in module scipy.stats*), 2800
 tan () (*scipy.sparse.bsr_matrix method*), 2026
 tan () (*scipy.sparse.coo_matrix method*), 2044
 tan () (*scipy.sparse.csc_matrix method*), 2063
 tan () (*scipy.sparse.csr_matrix method*), 2082
 tan () (*scipy.sparse.dia_matrix method*), 2097
 tandg (*in module scipy.special*), 2534
 tanh () (*scipy.sparse.bsr_matrix method*), 2026
 tanh () (*scipy.sparse.coo_matrix method*), 2044
 tanh () (*scipy.sparse.csc_matrix method*), 2063
 tanh () (*scipy.sparse.csr_matrix method*), 2082
 tanh () (*scipy.sparse.dia_matrix method*), 2097
 tanhm () (*in module scipy.linalg*), 1057
 tanm () (*in module scipy.linalg*), 1055
 tf2sos () (*in module scipy.signal*), 1934
 tf2ss () (*in module scipy.signal*), 1934
 tf2zpk () (*in module scipy.signal*), 1933

- theilslopes () (in module *scipy.stats*), 2947
theilslopes () (in module *scipy.stats.mstats*), 3056
tiecorrect () (in module *scipy.stats*), 2972
tilbert () (in module *scipy.fftpack*), 757
tklmbda (in module *scipy.special*), 2410
tmax () (in module *scipy.stats*), 2902
tmax () (in module *scipy.stats.mstats*), 3046
tmean () (in module *scipy.stats*), 2900
tmean () (in module *scipy.stats.mstats*), 3044
tmin () (in module *scipy.stats*), 2901
tmin () (in module *scipy.stats.mstats*), 3045
to_discrete () (*scipy.signal.lti* method), 1901
to_mlab_linkage () (in module *scipy.cluster.hierarchy*), 657
to_ss () (*scipy.signal.StateSpace* method), 1904
to_ss () (*scipy.signal.TransferFunction* method), 1906
to_ss () (*scipy.signal.ZerosPolesGain* method), 1908
to_tf () (*scipy.signal.StateSpace* method), 1904
to_tf () (*scipy.signal.TransferFunction* method), 1906
to_tf () (*scipy.signal.ZerosPolesGain* method), 1908
to_tree () (in module *scipy.cluster.hierarchy*), 666
to_zpk () (*scipy.signal.StateSpace* method), 1904
to_zpk () (*scipy.signal.TransferFunction* method), 1906
to_zpk () (*scipy.signal.ZerosPolesGain* method), 1908
toarray () (*scipy.sparse.bsr_matrix* method), 2026
toarray () (*scipy.sparse.coo_matrix* method), 2044
toarray () (*scipy.sparse.csc_matrix* method), 2063
toarray () (*scipy.sparse.csr_matrix* method), 2082
toarray () (*scipy.sparse.dia_matrix* method), 2098
toarray () (*scipy.sparse.dok_matrix* method), 2111
toarray () (*scipy.sparse.lil_matrix* method), 2123
toarray () (*scipy.sparse.spmatrix* method), 2134
tobsr () (*scipy.sparse.bsr_matrix* method), 2027
tobsr () (*scipy.sparse.coo_matrix* method), 2044
tobsr () (*scipy.sparse.csc_matrix* method), 2063
tobsr () (*scipy.sparse.csr_matrix* method), 2082
tobsr () (*scipy.sparse.dia_matrix* method), 2098
tobsr () (*scipy.sparse.dok_matrix* method), 2111
tobsr () (*scipy.sparse.lil_matrix* method), 2123
tobsr () (*scipy.sparse.spmatrix* method), 2134
tocoo () (*scipy.sparse.bsr_matrix* method), 2027
tocoo () (*scipy.sparse.coo_matrix* method), 2044
tocoo () (*scipy.sparse.csc_matrix* method), 2064
tocoo () (*scipy.sparse.csr_matrix* method), 2083
tocoo () (*scipy.sparse.dia_matrix* method), 2098
tocoo () (*scipy.sparse.dok_matrix* method), 2111
tocoo () (*scipy.sparse.lil_matrix* method), 2124
tocoo () (*scipy.sparse.spmatrix* method), 2135
tocsc () (*scipy.sparse.bsr_matrix* method), 2027
tocsc () (*scipy.sparse.coo_matrix* method), 2045
tocsc () (*scipy.sparse.csc_matrix* method), 2064
tocsc () (*scipy.sparse.csr_matrix* method), 2083
tocsc () (*scipy.sparse.dia_matrix* method), 2098
tocsc () (*scipy.sparse.dok_matrix* method), 2112
tocsc () (*scipy.sparse.lil_matrix* method), 2124
tocsc () (*scipy.sparse.spmatrix* method), 2135
todense () (*scipy.optimize.LbfgsInvHessProduct* method), 1713
todense () (*scipy.sparse.bsr_matrix* method), 2027
todense () (*scipy.sparse.coo_matrix* method), 2046
todense () (*scipy.sparse.csc_matrix* method), 2064
todense () (*scipy.sparse.csr_matrix* method), 2083
todense () (*scipy.sparse.dia_matrix* method), 2099
todense () (*scipy.sparse.dok_matrix* method), 2112
todense () (*scipy.sparse.lil_matrix* method), 2124
todense () (*scipy.sparse.spmatrix* method), 2135
todia () (*scipy.sparse.bsr_matrix* method), 2028
todia () (*scipy.sparse.coo_matrix* method), 2046
todia () (*scipy.sparse.csc_matrix* method), 2064
todia () (*scipy.sparse.csr_matrix* method), 2083
todia () (*scipy.sparse.dia_matrix* method), 2099
todia () (*scipy.sparse.dok_matrix* method), 2112
todia () (*scipy.sparse.lil_matrix* method), 2124
todia () (*scipy.sparse.spmatrix* method), 2135
todok () (*scipy.sparse.bsr_matrix* method), 2028
todok () (*scipy.sparse.coo_matrix* method), 2046
todok () (*scipy.sparse.csc_matrix* method), 2065
todok () (*scipy.sparse.csr_matrix* method), 2084
todok () (*scipy.sparse.dia_matrix* method), 2099
todok () (*scipy.sparse.dok_matrix* method), 2112
todok () (*scipy.sparse.lil_matrix* method), 2125
todok () (*scipy.sparse.spmatrix* method), 2136
toeplitz () (in module *scipy.linalg*), 1087
tolil () (*scipy.sparse.bsr_matrix* method), 2028
tolil () (*scipy.sparse.coo_matrix* method), 2046
tolil () (*scipy.sparse.csc_matrix* method), 2065
tolil () (*scipy.sparse.csr_matrix* method), 2084
tolil () (*scipy.sparse.dia_matrix* method), 2099
tolil () (*scipy.sparse.dok_matrix* method), 2113
tolil () (*scipy.sparse.lil_matrix* method), 2125
tolil () (*scipy.sparse.spmatrix* method), 2136
toms748 () (in module *scipy.optimize*), 1663
tplquad () (in module *scipy.integrate*), 775
TransferFunction (class in *scipy.signal*), 1904
transpose () (*scipy.optimize.LbfgsInvHessProduct* method), 1713
transpose () (*scipy.sparse.bsr_matrix* method), 2028
transpose () (*scipy.sparse.coo_matrix* method), 2046
transpose () (*scipy.sparse.csc_matrix* method), 2065
transpose () (*scipy.sparse.csr_matrix* method), 2084

transpose() (*scipy.sparse.dia_matrix method*), 2100
 transpose() (*scipy.sparse.dok_matrix method*), 2113
 transpose() (*scipy.sparse.lil_matrix method*), 2125
 transpose() (*scipy.sparse.linalg.LinearOperator method*), 2161
 transpose() (*scipy.sparse.spmatrix method*), 2136
 trapezoid (*in module scipy.stats*), 2802
 trapezoid() (*in module scipy.integrate*), 785
 tri() (*in module scipy.linalg*), 1088
 triang (*in module scipy.stats*), 2805
 tril() (*in module scipy.linalg*), 996
 tril() (*in module scipy.sparse*), 2141
 trim() (*in module scipy.stats.mstats*), 3068
 trim1() (*in module scipy.stats*), 3010
 trim_mean() (*in module scipy.stats*), 2906
 trima() (*in module scipy.stats.mstats*), 3068
 trimboth() (*in module scipy.stats*), 3010
 trimboth() (*in module scipy.stats.mstats*), 3070
 trimmed_mean() (*in module scipy.stats.mstats*), 3049
 trimmed_mean_ci() (*in module scipy.stats.mstats*), 3050
 trimmed_std() (*in module scipy.stats.mstats*), 3050
 trimmed_stde() (*in module scipy.stats.mstats*), 3069
 trimmed_var() (*in module scipy.stats.mstats*), 3051
 trimr() (*in module scipy.stats.mstats*), 3069
 trimtail() (*in module scipy.stats.mstats*), 3070
 triu() (*in module scipy.linalg*), 996
 triu() (*in module scipy.sparse*), 2142
 trunc() (*scipy.sparse.bsr_matrix method*), 2028
 trunc() (*scipy.sparse.coo_matrix method*), 2047
 trunc() (*scipy.sparse.csc_matrix method*), 2065
 trunc() (*scipy.sparse.csr_matrix method*), 2084
 trunc() (*scipy.sparse.dia_matrix method*), 2100
 truncexpon (*in module scipy.stats*), 2807
 truncnorm (*in module scipy.stats*), 2810
 tsearch() (*in module scipy.spatial*), 2282
 tsem() (*in module scipy.stats*), 2904
 tsem() (*in module scipy.stats.mstats*), 3047
 tstd() (*in module scipy.stats*), 2903
 ttest_1samp() (*in module scipy.stats*), 2953
 ttest_1samp() (*in module scipy.stats.mstats*), 3057
 ttest_ind() (*in module scipy.stats*), 2954
 ttest_ind() (*in module scipy.stats.mstats*), 3058
 ttest_ind_from_stats() (*in module scipy.stats*), 2956
 ttest_onesamp() (*in module scipy.stats.mstats*), 3058
 ttest_rel() (*in module scipy.stats*), 2958
 ttest_rel() (*in module scipy.stats.mstats*), 3059
 tukeylambd (*in module scipy.stats*), 2812
 tvar() (*in module scipy.stats*), 2900
 tvar() (*in module scipy.stats.mstats*), 3045
 typecode() (*scipy.io.netcdf_variable method*), 966
 types() (*scipy.io.arff.MetaData method*), 973

U

uniform (*in module scipy.stats*), 2815
 uniform_filter() (*in module scipy.ndimage*), 1509
 uniform_filter1d() (*in module scipy.ndimage*), 1510
 unilinear (*in module scipy.odr*), 1588
 unique_roots() (*in module scipy.signal*), 1850
 unit() (*in module scipy.constants*), 681
 unit_impulse() (*in module scipy.signal*), 1957
 unitary_group (*in module scipy.stats*), 2847
 UnivariateSpline (*class in scipy.interpolate*), 905
 update() (*scipy.optimize.BFGS method*), 1617
 update() (*scipy.optimize.HessianUpdateStrategy method*), 1715
 update() (*scipy.optimize.OptimizeResult method*), 1595
 update() (*scipy.optimize.SR1 method*), 1619
 update() (*scipy.sparse.dok_matrix method*), 2113
 upfirdn() (*in module scipy.signal*), 1808
 use_solver() (*in module scipy.sparse.linalg*), 2170

V

value() (*in module scipy.constants*), 681
 values() (*scipy.optimize.OptimizeResult method*), 1596
 values() (*scipy.sparse.dok_matrix method*), 2113
 var() (*scipy.stats.rv_continuous method*), 2552
 var() (*scipy.stats.rv_discrete method*), 2563
 var() (*scipy.stats.rv_histogram method*), 2576
 variance() (*in module scipy.ndimage*), 1546
 variation() (*in module scipy.stats*), 2904
 variation() (*in module scipy.stats.mstats*), 3048
 vectorstrength() (*in module scipy.signal*), 1999
 voigt_profile (*in module scipy.special*), 2446
 volume() (*scipy.spatial.Rectangle method*), 2259
 vonmises (*in module scipy.stats*), 2817
 vonmises_line (*in module scipy.stats*), 2819
 Voronoi (*class in scipy.spatial*), 2267
 voronoi_plot_2d() (*in module scipy.spatial*), 2279
 vq() (*in module scipy.cluster.vq*), 622
 vstack() (*in module scipy.sparse*), 2144

W

wald (*in module scipy.stats*), 2822
 ward() (*in module scipy.cluster.hierarchy*), 647
 wasserstein_distance() (*in module scipy.stats*), 3013
 watershed_ift() (*in module scipy.ndimage*), 1547
 WavFileWarning, 971
 weibull_max (*in module scipy.stats*), 2827
 weibull_min (*in module scipy.stats*), 2824
 weighted() (*in module scipy.cluster.hierarchy*), 642
 weightedtau() (*in module scipy.stats*), 2942
 welch() (*in module scipy.signal*), 1985
 white_tophat() (*in module scipy.ndimage*), 1576

- whiten() (in module *scipy.cluster.vq*), 622
 - whosmat() (in module *scipy.io*), 953
 - wiener() (in module *scipy.signal*), 1784
 - wilcoxon() (in module *scipy.stats*), 2975
 - winsorize() (in module *scipy.stats.mstats*), 3071
 - wishart (in module *scipy.stats*), 2839
 - with_traceback() (*scipy.constants.ConstantWarning* method), 683
 - with_traceback() (*scipy.integrate.AccuracyWarning* method), 784
 - with_traceback() (*scipy.integrate.IntegrationWarning* method), 784
 - with_traceback() (*scipy.io.arff.ArffError* method), 973
 - with_traceback() (*scipy.io.arff.ParseArffError* method), 974
 - with_traceback() (*scipy.io.FortranEOFError* method), 960
 - with_traceback() (*scipy.io.FortranFormattingError* method), 961
 - with_traceback() (*scipy.io.wavfile.WavFileWarning* method), 971
 - with_traceback() (*scipy.linalg.LinAlgError* method), 1001
 - with_traceback() (*scipy.linalg.LinAlgWarning* method), 1001
 - with_traceback() (*scipy.odr.OdrError* method), 1586
 - with_traceback() (*scipy.odr.OdrStop* method), 1586
 - with_traceback() (*scipy.odr.OdrWarning* method), 1586
 - with_traceback() (*scipy.optimize.OptimizeWarning* method), 1596
 - with_traceback() (*scipy.signal.BadCoefficients* method), 1856
 - with_traceback() (*scipy.sparse.csgraph.NegativeCycleError* method), 2227
 - with_traceback() (*scipy.sparse.linalg.ArpackError* method), 2201
 - with_traceback() (*scipy.sparse.linalg.ArpackNoConvergence* method), 2199
 - with_traceback() (*scipy.sparse.linalg.MatrixRankWarning* method), 2170
 - with_traceback() (*scipy.sparse.SparseEfficiencyWarning* method), 2155
 - with_traceback() (*scipy.sparse.SparseWarning* method), 2155
 - with_traceback() (*scipy.special.SpecialFunctionError* method), 2318
 - with_traceback() (*scipy.special.SpecialFunctionWarning* method), 2318
 - with_traceback() (*scipy.stats.F_onewayBadInputSizesWarning* method), 3084
 - with_traceback() (*scipy.stats.F_onewayConstantInputWarning* method), 3084
 - with_traceback() (*scipy.stats.PearsonRConstantInputWarning* method), 3084
 - with_traceback() (*scipy.stats.PearsonRNearConstantInputWarning* method), 3085
 - with_traceback() (*scipy.stats.SpearmanRConstantInputWarning* method), 3085
 - wminkowski() (in module *scipy.spatial.distance*), 2307
 - wofz (in module *scipy.special*), 2443
 - wrapcauchy (in module *scipy.stats*), 2830
 - wrightomega (in module *scipy.special*), 2513
 - write() (in module *scipy.io.wavfile*), 970
 - write_record() (*scipy.io.FortranFile* method), 960
- ## X
- xlog1py (in module *scipy.special*), 2538
 - xlogy (in module *scipy.special*), 2538
- ## Y
- y0 (in module *scipy.special*), 2350
 - y0_zeros() (in module *scipy.special*), 2347
 - y1 (in module *scipy.special*), 2351
 - y1_zeros() (in module *scipy.special*), 2347
 - y1p_zeros() (in module *scipy.special*), 2348
 - yeojohnson() (in module *scipy.stats*), 3003
 - yeojohnson_llf() (in module *scipy.stats*), 3005
 - yeojohnson_normmax() (in module *scipy.stats*), 3005
 - yeojohnson_normplot() (in module *scipy.stats*), 3031
 - yn (in module *scipy.special*), 2332
 - yn_zeros() (in module *scipy.special*), 2345
 - ynp_zeros() (in module *scipy.special*), 2346
 - yule() (in module *scipy.spatial.distance*), 2314
 - yulesimon (in module *scipy.stats*), 2887
 - yv (in module *scipy.special*), 2333
 - yve (in module *scipy.special*), 2333
 - yvp() (in module *scipy.special*), 2360
- ## Z
- zaxpy (in module *scipy.linalg.blas*), 1108
 - zcopy (in module *scipy.linalg.blas*), 1109
 - zdotc (in module *scipy.linalg.blas*), 1109

zdotu (in module *scipy.linalg.blas*), 1110
 zdrot (in module *scipy.linalg.blas*), 1110
 zdscal (in module *scipy.linalg.blas*), 1111
 ZerosPolesGain (class in *scipy.signal*), 1906
 zeta () (in module *scipy.special*), 2529
 zetac (in module *scipy.special*), 2530
 zgblmv (in module *scipy.linalg.blas*), 1135
 zgbsv (in module *scipy.linalg.lapack*), 1171
 zgbtrf (in module *scipy.linalg.lapack*), 1173
 zgbtrs (in module *scipy.linalg.lapack*), 1175
 zgebal (in module *scipy.linalg.lapack*), 1177
 zgecon (in module *scipy.linalg.lapack*), 1178
 zgeequ (in module *scipy.linalg.lapack*), 1180
 zgeequb (in module *scipy.linalg.lapack*), 1181
 zgees (in module *scipy.linalg.lapack*), 1184
 zgeev (in module *scipy.linalg.lapack*), 1186
 zgeev_lwork (in module *scipy.linalg.lapack*), 1187
 zgegv () (in module *scipy.linalg.lapack*), 1190
 zgehrd (in module *scipy.linalg.lapack*), 1191
 zgehrd_lwork (in module *scipy.linalg.lapack*), 1193
 zgels (in module *scipy.linalg.lapack*), 1196
 zgels_lwork (in module *scipy.linalg.lapack*), 1197
 zgelsd (in module *scipy.linalg.lapack*), 1199
 zgelsd_lwork (in module *scipy.linalg.lapack*), 1201
 zgels (in module *scipy.linalg.lapack*), 1203
 zgels_lwork (in module *scipy.linalg.lapack*), 1204
 zgelsy (in module *scipy.linalg.lapack*), 1206
 zgelsy_lwork (in module *scipy.linalg.lapack*), 1208
 zgemm (in module *scipy.linalg.blas*), 1153
 zgemqrt (in module *scipy.linalg.lapack*), 1400
 zgemv (in module *scipy.linalg.blas*), 1135
 zgeqp3 (in module *scipy.linalg.lapack*), 1209
 zgeqrf (in module *scipy.linalg.lapack*), 1211
 zgeqrf_lwork (in module *scipy.linalg.lapack*), 1212
 zgeqrfp (in module *scipy.linalg.lapack*), 1214
 zgeqrfp_lwork (in module *scipy.linalg.lapack*), 1215
 zgeqrt (in module *scipy.linalg.lapack*), 1398
 zgerc (in module *scipy.linalg.blas*), 1136
 zgerqf (in module *scipy.linalg.lapack*), 1216
 zgeru (in module *scipy.linalg.blas*), 1136
 zgesc2 (in module *scipy.linalg.lapack*), 1236
 zgesdd (in module *scipy.linalg.lapack*), 1218
 zgesdd_lwork (in module *scipy.linalg.lapack*), 1220
 zgesv (in module *scipy.linalg.lapack*), 1221
 zgesvd (in module *scipy.linalg.lapack*), 1223
 zgesvd_lwork (in module *scipy.linalg.lapack*), 1225
 zgesvx (in module *scipy.linalg.lapack*), 1228
 zgetc2 (in module *scipy.linalg.lapack*), 1231
 zgetrf (in module *scipy.linalg.lapack*), 1229
 zgetri (in module *scipy.linalg.lapack*), 1232
 zgetri_lwork (in module *scipy.linalg.lapack*), 1233
 zgetrs (in module *scipy.linalg.lapack*), 1235
 zgges (in module *scipy.linalg.lapack*), 1240
 zggev (in module *scipy.linalg.lapack*), 1242
 zggls (in module *scipy.linalg.lapack*), 1245
 zggls_lwork (in module *scipy.linalg.lapack*), 1246
 zgtsv (in module *scipy.linalg.lapack*), 1248
 zgtsvx (in module *scipy.linalg.lapack*), 1251
 zgttrf (in module *scipy.linalg.lapack*), 1402
 zgttrs (in module *scipy.linalg.lapack*), 1404
 zhbevd (in module *scipy.linalg.lapack*), 1252
 zhbevz (in module *scipy.linalg.lapack*), 1253
 zhbm (in module *scipy.linalg.blas*), 1137
 zhecon (in module *scipy.linalg.lapack*), 1254
 zheequb (in module *scipy.linalg.lapack*), 1255
 zheev (in module *scipy.linalg.lapack*), 1256
 zheev_lwork (in module *scipy.linalg.lapack*), 1256
 zheevd (in module *scipy.linalg.lapack*), 1257
 zheevd_lwork (in module *scipy.linalg.lapack*), 1258
 zheevr (in module *scipy.linalg.lapack*), 1259
 zheevr_lwork (in module *scipy.linalg.lapack*), 1260
 zheevz (in module *scipy.linalg.lapack*), 1261
 zheevz_lwork (in module *scipy.linalg.lapack*), 1262
 zhegst (in module *scipy.linalg.lapack*), 1263
 zhegv (in module *scipy.linalg.lapack*), 1264
 zhegv_lwork (in module *scipy.linalg.lapack*), 1264
 zhegvd (in module *scipy.linalg.lapack*), 1265
 zhegvz (in module *scipy.linalg.lapack*), 1266
 zhegvz_lwork (in module *scipy.linalg.lapack*), 1267
 zhemm (in module *scipy.linalg.blas*), 1153
 zhemv (in module *scipy.linalg.blas*), 1137
 zher (in module *scipy.linalg.blas*), 1138
 zher2 (in module *scipy.linalg.blas*), 1138
 zher2k (in module *scipy.linalg.blas*), 1154
 zherk (in module *scipy.linalg.blas*), 1154
 zhesv (in module *scipy.linalg.lapack*), 1268
 zhesv_lwork (in module *scipy.linalg.lapack*), 1269
 zhesvx (in module *scipy.linalg.lapack*), 1270
 zhesvx_lwork (in module *scipy.linalg.lapack*), 1271
 zhetrd (in module *scipy.linalg.lapack*), 1271
 zhetrd_lwork (in module *scipy.linalg.lapack*), 1272
 zhetrf (in module *scipy.linalg.lapack*), 1273
 zhetrf_lwork (in module *scipy.linalg.lapack*), 1273
 zhfrk (in module *scipy.linalg.lapack*), 1274
 zhpmv (in module *scipy.linalg.blas*), 1139
 zhpr (in module *scipy.linalg.blas*), 1139
 zhpr2 (in module *scipy.linalg.blas*), 1140
 zipf (in module *scipy.stats*), 2885
 zlange (in module *scipy.linalg.lapack*), 1276
 zlarf (in module *scipy.linalg.lapack*), 1277
 zlarfg (in module *scipy.linalg.lapack*), 1279
 zlartg (in module *scipy.linalg.lapack*), 1280
 zlaswp (in module *scipy.linalg.lapack*), 1283
 zlauum (in module *scipy.linalg.lapack*), 1284
 zmap () (in module *scipy.stats*), 3011
 zmap () (in module *scipy.stats.mstats*), 3072
 zoom () (in module *scipy.ndimage*), 1529
 zpbsv (in module *scipy.linalg.lapack*), 1294

zpbtrf (in module *scipy.linalg.lapack*), 1295
 zpbtrs (in module *scipy.linalg.lapack*), 1297
 zpfttrf (in module *scipy.linalg.lapack*), 1298
 zpfttri (in module *scipy.linalg.lapack*), 1300
 zpfttrs (in module *scipy.linalg.lapack*), 1302
 zpk2sos () (in module *scipy.signal*), 1936
 zpk2ss () (in module *scipy.signal*), 1938
 zpk2tf () (in module *scipy.signal*), 1935
 zpocon (in module *scipy.linalg.lapack*), 1303
 zposv (in module *scipy.linalg.lapack*), 1308
 zposvx (in module *scipy.linalg.lapack*), 1310
 zpotrf (in module *scipy.linalg.lapack*), 1312
 zpotri (in module *scipy.linalg.lapack*), 1313
 zpotrs (in module *scipy.linalg.lapack*), 1314
 zppcon (in module *scipy.linalg.lapack*), 1316
 zppsv (in module *scipy.linalg.lapack*), 1317
 zppttrf (in module *scipy.linalg.lapack*), 1319
 zppttri (in module *scipy.linalg.lapack*), 1320
 zppttrs (in module *scipy.linalg.lapack*), 1322
 zpstf2 (in module *scipy.linalg.lapack*), 1306
 zpstrf (in module *scipy.linalg.lapack*), 1304
 zpsteqr (in module *scipy.linalg.lapack*), 1331
 zptsv (in module *scipy.linalg.lapack*), 1324
 zptsvx (in module *scipy.linalg.lapack*), 1326
 zpttrf (in module *scipy.linalg.lapack*), 1327
 zpttrs (in module *scipy.linalg.lapack*), 1329
 zrot (in module *scipy.linalg.lapack*), 1332
 zrotg (in module *scipy.linalg.blas*), 1111
 zscal (in module *scipy.linalg.blas*), 1111
 zscore () (in module *scipy.stats*), 3011
 zscore () (in module *scipy.stats.mstats*), 3072
 zswap (in module *scipy.linalg.blas*), 1112
 zsycon (in module *scipy.linalg.lapack*), 1343
 zsyconv (in module *scipy.linalg.lapack*), 1345
 zsyequb (in module *scipy.linalg.lapack*), 1346
 zsymm (in module *scipy.linalg.blas*), 1154
 zsytr (in module *scipy.linalg.blas*), 1142
 zsytr2k (in module *scipy.linalg.blas*), 1155
 zsytrk (in module *scipy.linalg.blas*), 1155
 zsysv (in module *scipy.linalg.lapack*), 1360
 zsysv_lwork (in module *scipy.linalg.lapack*), 1362
 zsysvx (in module *scipy.linalg.lapack*), 1364
 zsysvx_lwork (in module *scipy.linalg.lapack*), 1365
 zsytf2 (in module *scipy.linalg.lapack*), 1367
 zsytrf (in module *scipy.linalg.lapack*), 1370
 zsytrf_lwork (in module *scipy.linalg.lapack*), 1371
 ztbmv (in module *scipy.linalg.blas*), 1140
 ztbsv (in module *scipy.linalg.blas*), 1141
 ztbttrs (in module *scipy.linalg.lapack*), 1372
 ztfsm (in module *scipy.linalg.lapack*), 1374
 ztfttp (in module *scipy.linalg.lapack*), 1376
 ztfttr (in module *scipy.linalg.lapack*), 1377
 ztgsen (in module *scipy.linalg.lapack*), 1380
 ztpmqrt (in module *scipy.linalg.lapack*), 1408
 ztpmv (in module *scipy.linalg.blas*), 1141
 ztpqrt (in module *scipy.linalg.lapack*), 1406
 ztpttf (in module *scipy.linalg.lapack*), 1381
 ztpttr (in module *scipy.linalg.lapack*), 1383
 ztrmm (in module *scipy.linalg.blas*), 1156
 ztrmv (in module *scipy.linalg.blas*), 1142
 ztrsm (in module *scipy.linalg.blas*), 1156
 ztrsv (in module *scipy.linalg.blas*), 1142
 ztrsyl (in module *scipy.linalg.lapack*), 1384
 ztrtri (in module *scipy.linalg.lapack*), 1386
 ztrtrs (in module *scipy.linalg.lapack*), 1388
 ztrttf (in module *scipy.linalg.lapack*), 1389
 ztrttp (in module *scipy.linalg.lapack*), 1390
 ztzrzf (in module *scipy.linalg.lapack*), 1392
 ztzrzf_lwork (in module *scipy.linalg.lapack*), 1393
 zuncsd (in module *scipy.linalg.lapack*), 1409
 zuncsd_lwork (in module *scipy.linalg.lapack*), 1410
 zunghr (in module *scipy.linalg.lapack*), 1394
 zunghr_lwork (in module *scipy.linalg.lapack*), 1394
 zungqr (in module *scipy.linalg.lapack*), 1395
 zungqrq (in module *scipy.linalg.lapack*), 1396
 zunmqr (in module *scipy.linalg.lapack*), 1397
 zunmrz (in module *scipy.linalg.lapack*), 1411
 zunmrz_lwork (in module *scipy.linalg.lapack*), 1412